**Idaho
National
Engineering
Laboratory**

*Managed
by the U.S.
Department
of Energy*

EGG-WTD-9594 Vol. VII
January 1992

APR 27 1992

**Preliminary Systems Design Study
Assessment Report**
Volume VII: Subsystem Concepts

**J. L. Mayberry
F. Felzollahi
J. C. Del Signore**

*Work performed under
DOE Contract
No. DE-AC07-76ID01570*

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

This document contains new concepts or the author(s) interpretation of new calculations and/or measurements; accordingly, EG&G Idaho, Inc. is required by the United States Government to include the following disclaimer:

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights. References herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PRELIMINARY SYSTEMS DESIGN STUDY ASSESSMENT REPORT

Volume VII
SUBSYSTEM CONCEPTS

J. L. Mayberry
F. Feizollahi
J. C. Del Signore

Published January 1992

Idaho National Engineering Laboratory
EG&G Idaho, Inc.
Idaho Falls, Idaho 83415

Prepared for the
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
Under DOE Idaho Field Office
Contract DE-AC07-76ID01570

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PRELIMINARY SYSTEMS DESIGN STUDY
ASSESSMENT REPORT
EGG-WTD-9594
Volume VII

Prepared by:

John L. Mayberry, EG&G Idaho, Inc.

1-21-92
Date

Fred Feizollahi, Bechtel National, Inc.

1-21-92
Date

Chris Del Signore, EBASCO

01-21-92
Date

Reviewed and Approved by:

William J. Quapp, Manager Technology Demonstration,
Waste Technology Development Dept.

1-21-92
Date

ABSTRACT

The System Design Study (SDS), part of the Waste Technology Development Department at the Idaho National Engineering Laboratory (INEL), examined techniques available for the remediation of hazardous and transuranic waste stored at the Radioactive Waste Management Complex's Subsurface Disposal Area at the INEL. Using specific technologies, system concepts for treating the buried waste and the surrounding contaminated soil were evaluated. Evaluation included implementability, effectiveness, and cost. The SDS resulted in the development of technology requirements including demonstration, testing, and evaluation activities needed for implementing each concept.

The SDS results are published in eight volumes. Volume I contains an executive summary. The SDS summary and analysis of results are presented in Volume II. Volumes III through VII contain detailed descriptions of twelve system and four subsystem concepts. Volume VIII contains the appendixes.

ACKNOWLEDGMENTS

The authors would like to acknowledge the efforts of those that contributed to this report.

EG&G Idaho, Inc., Bechtel National, Inc., Ebasco Environmental, and IT Corp. for providing the assessments and functional and operational requirements for the 12 system and 4 subsystem concepts. Specifically, C. Klassy, K. Sherick and D. Haifner of EG&G Idaho, Inc., R. Schlueter, M. Pong, D. Harris, M. Beathard and P. Yen of Bechtel National, Inc., D. Prinzing, J. Bjorkstam, R. Vankateswar and S. Peck of Ebasco Environmental, J. Plum, J. Valdez, D. Vetter, M. Chavez, S. Djordevic, M. Swientoniewski, John McFee of IT Corp., and H. Kresny of Solmont Corporation.

Karen Grant and Janalee Nelson of EG&G Idaho, and Debra Iniquez of Bechtel National, Inc., for the extra effort required in editing this report.

CONTENTS

ABSTRACT	VII-iii
ACKNOWLEDGMENTS	VII-iv
ACRONYMS	VII-ix
1. INTRODUCTION	VII-1
1.1 Background	VII-1
1.2 Organization of the System Design Study Report	VII-2
2. METAL DECONTAMINATION AND SIZING SUBSYSTEM (S-BE-1)	VII-3
2.1 Functional and Operational Requirements	VII-3
2.1.1 Subsystem Description	VII-3
2.1.2 Subsystem Boundaries	VII-7
2.1.3 Process Functional Diagram	VII-11
2.1.4 Facility Description	VII-11
2.1.5 System Design Requirements	VII-13
2.1.6 Interface Requirements	VII-14
2.2 System Assessment	VII-15
2.2.1 Current Status of Unit Operations	VII-15
2.2.2 Program Implementation Risks	VII-17
2.2.3 Unit Operations Pro and Con Analysis	VII-19
2.2.4 Unit Operations Lead-Time Estimates	VII-21
2.2.5 Rough Order of Magnitude Cost Estimates	VII-23
2.2.6 System Evaluation Results	VII-25
2.2.7 Summary of Demonstration, Testing, and Evaluation Needs	VII-28
2.3 Recommendation for the System	VII-28
3. SOILS PROCESSING SUBSYSTEM (S-EB-2)	VII-33
3.1 Functional and Operational Requirements	VII-33
3.1.1 System Description	VII-33
3.1.2 Subsystem Boundaries	VII-34
3.1.3 Process Functional Diagram	VII-35
3.1.4 Facility Description	VII-39
3.1.5 System Design Description	VII-39
3.1.6 Interface Requirements	VII-41
3.2 System Assessment	VII-42

3.2.1	Current Status of Unit Operations	VII-42
3.2.2	Program Implementation Risks	VII-44
3.2.3	Unit Operations Pro and Con Analysis	VII-50
3.2.4	Unit Operations Lead-Time Estimates	VII-52
3.2.5	Rough Order of Magnitude Cost Estimates	VII-52
3.2.6	System Evaluation Results	VII-56
3.2.7	Summary of Demonstration, Testing, and Evaluation Needs	VII-59
3.3	Recommendation for the Subsystem	VII-62
4.	LOW-LEVEL WASTE SUBSYSTEM (S-IT-3)	VII-65
4.1	Functional and Operational Requirements	VII-65
4.1.1	Subsystem Description	VII-65
4.1.2	Subsystem Boundaries	VII-65
4.1.3	Process Functional Diagram	VII-67
4.1.4	Facility Description	VII-73
4.1.5	Subsystem Design Requirements	VII-73
4.2	System Assessment	VII-82
4.2.1	Current Status of Unit Operations	VII-82
4.2.2	Program Implementation Risks	VII-88
4.2.3	Unit Operations Pro and Con Analysis	VII-90
4.2.4	Unit Operations Lead-Time Estimates	VII-97
4.2.5	Rough Order of Magnitude Cost Estimates	VII-97
4.2.6	Subsystem Evaluation Results	VII-103
5.	RETRIEVAL SUBSYSTEM (S-BE-4)	VII-107
5.1	Functional and Operational Requirements	VII-107
5.1.1	Subsystem Description	VII-107
5.1.2	Subsystem Boundaries	VII-114
5.1.3	Process Functional Diagram	VII-117
5.1.4	Facility Description	VII-117
5.1.5	Subsystem Design Requirements	VII-121
5.1.6	Interface Requirements	VII-122
5.2	System Assessment	VII-123
5.2.1	Current Status of Unit Operations	VII-123
5.2.2	Program Implementation Risks	VII-130
5.2.3	Unit Operations Pro and Con Analysis	VII-136
5.2.4	Unit Operations Lead-Time Estimates	VII-138
5.2.5	Rough Order of Magnitude Cost Estimates	VII-138
5.2.6	System Evaluation Results	VII-142
5.2.7	Summary of Demonstration, Testing, and Evaluation Needs	VII-143

5.3 Recommendation for the System	VII-149
6. BIBLIOGRAPHY	VII-151

FIGURES

VII-2-1. Unit operations for the Metal Decontamination and Sizing Subsystem	VII-9
VII-2-2. General arrangements for the Waste Receiving, Processing, and Packaging Facility	VII-12
VII-3-1. Process functional diagram for soils processing subsystem . .	VII-37
VII-3-2. Facility layout for the Soils Processing Subsystem.	VII-40
VII-4-1. Process functional diagram for Low-Level Waste Subsystem . .	VII-69
VII-4-2. Facility layout for Low-Level Waste Subsystem	VII-75
VII-5-1. Process functional diagram for Retrieval Subsystem	VII-115
VII-5-2. General arrangements for the Retrieval Subsystem (S-BE-4) .	VII-119

TABLES

VII-2-1. DT&E assessment summary for the Metal Decontamination and Sizing Subsystem (S-BE-1)	VII-22
VII-2-2. Rough order of magnitude cost estimates (S-BE-1)	VII-24
VII-2-3. Rating performance measurables for the Metal Decontamination and Sizing Subsystem (S-BE-1)	VII-27
VII-2-4. DT&E needs for the Metal Decontamination and Sizing Subsystem (S-BE-1)	VII-29
VII-3-1. DT&E assessment summary for the Soils Processing Subsystem (S-EB-2)	VII-53
VII-3-2. Rough order of magnitude cost estimates (S-EB-2)	VII-54
VII-3-3. Rating performance measurables for the Soils Processing Subsystem (S-EB-2)	VII-59
VII-3-4. DT&E needs for the Soils Processing Subsystem (S-EB-2) . . .	VII-60

VII-4-1.	DT&E needs for the Low-Level Waste Subsystem (S-IT-3)	VII-87
VII-4-2.	Risk rankings (S-IT-3)	VII-91
VII-4-3.	Open packages and sort packages analysis	VII-91
VII-4-4.	Land disposal restriction treatment analysis	VII-93
VII-4-5.	Land disposal restriction organic treatment (for sludges) analysis	VII-93
VII-4-6.	Land disposal restriction organics treatment (combustibles and loose material) analysis	VII-95
VII-4-7.	Secondary waste treatment analysis	VII-95
VII-4-8.	Solidification analysis	VII-96
VII-4-9.	DT&E assessment summary for the Low-Level Waste Subsystem (S-IT-3)	VII-98
VII-4-10.	Rough order of magnitude cost estimates (S-IT-3)	VII-99
VII-4-11.	Rating performance measurables for the Low-Level Waste Processing Subsystem (S-IT-3)	VII-105
VII-5-1.	Summary of program implementation risks and major areas of concern (S-BE-4)	VII-131
VII-5-2.	DT&E assessment summary for the Retrieval Subsystem (S-BE-4)	VII-139
VII-5-3.	Rough order of magnitude cost estimates (S-BE-4)	VII-140
VII-5-4.	Rating performance measurables for the Retrieval Subsystem (S-BE-4)	VII-144
VII-5-5.	DT&E needs for the Retrieval Subsystem (S-BE-4)	VII-145

ACRONYMS

AEC	U.S. Atomic Energy Commission
ALARA	as low as reasonably achievable
ANL-W	Argonne National Laboratory-West
ARAR	applicable or relevant and appropriate requirement
CAA	Clean Air Act
CCD	charged coupled device
CDIF	Component Development Integration Facility
CEA	Atomic Energy Commission (France)
CEPOD	catalytic electrolytic plutonium oxide dissolution
CEQ	Council of Environmental Quality
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
CM	construction management
CWA	Clean Water Act
DOD	U.S. Department of Defense
DOE	U.S. Department of Energy
DOE-ID	Department of Energy-Field Office, Idaho
DOT	U.S. Department of Transportation
dscf	dry standard cubic feet
DT&E	demonstration, testing, and evaluation
EG&G Idaho	EG&G Idaho, Inc.
EM	electromagnetics
EOF	energy optimizing furnace
EPA	U.S. Environmental Protection Agency

ER	environmental restoration
ERDA	Energy Research and Development Administration
ERP	Environmental Restoration Program
F&OR	functional and operational requirement
FFBD	functional flow block diagram
FOM	Figure of Merit
FS	feasibility study
FY	fiscal year
GPR	ground penetrating radar
HAZMAT	hazardous material
HEPA	high-efficiency particulate air (filter)
HVAC	heating, ventilating, and air conditioning
IAG	Interagency Agreement
INEL	Idaho National Engineering Laboratory
I/O	input/output
ISV	in situ vitrification
LANL	Los Alamos National Laboratory
LDR	land disposal restriction
LLNL	Lawrence Livermore National Laboratory
LLW	low-level waste
MAF	moisture and ash-free fraction
MF	melting furnace
MSA	Major System Acquisition
MSO	Molten Salt Oxidation
MSW	municipal solid waste
NEPA	National Environmental Policy Act of 1969

VII-x

2.1.5 System Design Requirements

2.1.5.1 Functional Requirements. Functional requirements for the Metal Decontamination and Sizing Subsystem include the following:

- Receives bulk and loose metal from RWMC
- Decontaminates metallic waste

NPL	National Priorities List
NRC	U.S. Nuclear Regulatory Commission
NWCF	New Waste Calcining Facility
ORNL	Oak Ridge National Laboratory
PAF	plasma arc furnace
PAN	passive neutron counting
PCB	polychlorinated biphenyl
PCR	plasma centrifugal reactor
PEC	Plasma Energy Corporation
PFD	process functional diagram
PLC	programmable logic controller
PLPF	Plutonium Processing Facility
PPF	plasma pyrolysis furnace
PRD	program requirements document
PREPP	Process Experimental Pilot Plant
PVC	polyvinyl chloride
R&D	research and development
RAM	reliability, availability, and maintainability
RCRA	Resource Conservation and Recovery Act
RI	Rockwell International
RI/FS	Remedial Investigation and Feasibility Study
RO	reverse osmosis
ROD	Record of Decision
ROM	rough order of magnitude
ROV	remotely operated vehicles
RTR	real-time radiography

RWMC	Radioactive Waste Management Complex
SAIC	Science Applications International Corporation
scfm	standard ft ³ /min
SDA	Subsurface Disposal Area
SDS	System Design Study
SDWA	Safe Drinking Water Act
SEG	Scientific Ecology Group
SGS	gamma spectroscopy
SWEPP	Stored Waste Examination Pilot Plant
TCLP	toxicity characteristic leaching procedure
TEC	total estimated cost
T/O	tradeoff
TRAMPAC	transportation package
TRU	transuranic
TSA	Transuranic Storage Area
TSCA	Toxic Substances Control Act
TVR-III	Transportable Volume Reduction and Solidification System
UCRL	University of California Research Laboratories
U/R	utilization of resources
VOC	volatile organic compound
WAC	waste acceptance criteria
WAG	Waste Area Group
WERF	Waste Experimental Reduction Facility
WIPP	Waste Isolation Pilot Plant

VOLUME VII SUBSYSTEM OPTIONS

1. INTRODUCTION

1.1 BACKGROUND

Remediating the Idaho National Engineering Laboratory (INEL) transuranic (TRU) buried waste at the Subsurface Disposal Area (SDA) will require a complex set of technologies for safe treatment and disposal of the waste. A key question for achieving the Buried Waste Program objectives is which practical and cost effective technologies could be used as candidates to satisfy the objectives of this program. To provide an answer to this question, a system design study (SDS) was commissioned based on system engineering principles advocated by the U.S. Department of Energy (DOE) Order 4700.1. The SDS examined the existing and emerging technologies for cost-effective remediation of the buried waste. Since no one technology can accommodate the complex remedial action process, several technologies were considered as a system. While examining the technology options, the SDS focused on the technology requirements aspect of the systems engineering. The intent was to identify a set of cost-effective, practical, acceptable treatment strategies; develop system concepts encompassing these strategies; and identify technologies within these concepts that will require demonstration, testing, and evaluation (DT&E).

In addition to developing technology requirements, the SDS concepts were developed so they can be used in future studies for establishing other detailed (derived) system requirements such as input/output (I/O) requirements and utilization of resource (U/R) requirements.

1.2 ORGANIZATION OF THE SYSTEM DESIGN STUDY REPORT

The SDS results are published in eight volumes. Volume I contains an executive summary. The SDS summary and analysis of the results are presented in Volume II. Volumes III through VII contain a detailed description and assessment of twelve system and four subsystem concepts. Volume VIII contains appendixes.

This volume contains the descriptions and other relevant information of the four subsystems required for most of the ex situ processing systems described in Volumes IV, V, and VI. Information regarding the design-related assumptions for the subsystems is the same as for the systems and thus is not repeated here.

2. METAL DECONTAMINATION AND SIZING SUBSYSTEM (S-BE-1)

The Metal Decontamination and Sizing Subsystem (S-BE-1) includes all facilities, processes, equipment, and ancillary components required for the retrieval, sorting, and processing of the TRU contaminated metallic waste buried at the Radioactive Waste Management Complex (RWMC). The subsystem processes the metallic waste and transfers it to a waste receiving, processing, and packaging facility.

2.1 FUNCTIONAL AND OPERATIONAL REQUIREMENTS

2.1.1 Subsystem Description

The Metal Decontamination and Sizing Subsystem (S-BE-1) is comprised of several unit operations including (a) metal pretreatment, (b) size reduction, (c) metal decontamination, (d) liquid waste treatment, and (e) assay.

The subsystem is housed within the Waste Receiving, Processing, and Packaging Facility and receives bulk metallic waste from the Retrieval Subsystem and loose metallic waste from unit operations within the Waste Receiving, Processing, and Packaging Facility. The Retrieval Subsystem provides all the necessary processes and unit operations to retrieve and gross sort the buried waste. The Retrieval Subsystem and its related unit operations are described in Section 5.

There are four major output streams from the Metal Decontamination and Sizing Subsystem including low-level waste (LLW), TRU metal, TRU residue, and treated clean liquid.

The subsystem includes equipment to pretreat and size-reduce the contaminated bulk metal and loose metal that requires size reduction. The size-reduced metal and remaining loose metal is decontaminated to remove or reduce land disposal restriction (LDR) materials and TRU contamination from the surface of the metallic waste. The decontaminated metal is assayed to

segregate the TRU metal from the LLW metal. The LLW and TRU metals are transferred via reusable containers to other unit operations with the Waste Receiving, Processing, and Packaging Facility for treatment and disposal.

The liquid waste stream produced from the metal decontamination and pretreatment is treated in a liquid waste treatment unit operation. The concentrated TRU residue waste is transferred via reusable containers or piping to other unit operations within the Waste Receiving, Processing, and Packaging Facility for treatment and disposal. The treated liquid is discharged to the environment.

The Metal Decontamination and Sizing Subsystem includes an alpha certified enclosure with the appropriate ventilation equipment to maintain control and prevent release of TRU and other hazardous waste. Spent filters from this ventilation unit are transferred to other unit operations in the Waste Receiving, Processing, and Packaging Facility for treatment and disposal.

The Waste Receiving, Processing, and Packaging Facility may be represented by nine of the candidate system models. A description of the unit operations of the Waste Receiving, Processing, and Packaging Facility may be found in Volumes IV-VI.

2.1.1.1 Metal Pretreatment Unit Operation Summary. The metal pretreatment unit operation includes all facilities, subsystems, and equipment needed perform the following:

- Transport bulk metal and loose metal from the opening and sorting unit operations within the Waste Receiving, Processing, and Packaging Facility.
- Empty out waste containers of loose metals.
- Dump the incoming loose metal onto a vibratory screen and wash with a high-pressure rinse to remove debris and soil from the surface of the metal. Some metal decontamination treatments may require the incoming

loose metal to be size reduced. The small metal will be collected and transferred to the metal decontamination unit operation. The remaining loose metal will be transferred to the size reduction unit operation. Bulk metal will be placed on treatment stations and pretreated with a high-pressure rinse. The bulk metal will remain on the treatment station for the size reduction unit operation.

2.1.1.2 Size Reduction Unit Operation Summary. The size reduction unit operation includes all facilities, subsystems, and equipment needed to reduce the size of the pretreated bulk metal and loose metal to facilitate the metal decontamination unit operation.

- Size reduction device: The bulk metal will be processed by a size reduction unit operation. Various technologies such as shearing, sawing, shredding, laser sectioning, and plasma torch may be used to reduce the size of the bulk metals. The size-reduced metal will be transferred to the metal decontamination unit operation.
- Metal transfer device: The metal transfer device will include equipment and components to transfer the size-reduced metal to the metal decontamination unit operation.

2.1.1.3 Metal Decontamination Unit Operation Summary. The metal decontamination operation includes all facilities, subsystems, and equipment needed to perform the following:

- Transport contaminated size-reduced metal and small metal from the metal pretreatment unit operation.
- Transfer the incoming metal waste via metal transfer units from the size reduction unit operation to the metal decontamination staging area.
- Decontaminate the metallic waste from the size reduction unit operation and metal pretreatment. Various technologies such as

electropolishing, grit blasting, ultrasonic cleaning, vibratory finishing, steam cleaning, and chemical cleaning may be used to decontaminate the sectioned and loose metal waste. Any liquid produced from the decontamination unit operation will be collected and pumped to the liquid waste treatment unit operation. After drying, the decontaminated metal will be transferred to the container filling unit operation. If additional decontamination of the metal is required, the metal will be diverted from the waste stream and reprocessed.

- Collect and transfer liquid waste to the liquid waste treatment unit operation.
- Transfer the decontaminated metal to the container assay unit operation.

2.1.1.4 Liquid Waste Treatment Unit Operation Summary. The liquid waste treatment unit operation includes all facilities, subsystems, and equipment needed to perform the following:

- Receive and store liquid waste and sludge from the metal decontamination unit operation and metal pretreatment.
- Treat the liquid waste to reduce the waste volume and detoxify and remove contaminants to meet discharge criteria. A combination of evaporation, precipitation, calcination, filtration, TRU/Clear, grouting, and centrifuge are available treatment methods. The treated clean liquid meeting the discharge regulations will be released. The remaining concentrated TRU residue will be transferred to the Waste Receiving, Processing, and Packaging Facility for treatment and disposal.
- Transfer concentrated TRU residue in reusable containers to the Waste Receiving, Processing, and Packaging Facility for treatment and disposal.

- Sample the treated clean liquid for radioactivity by a monitoring device before being discharged.
- Discharge the clean liquid to the Waste Receiving, Processing, and Packaging Facility for final treatment and disposal as required.

2.1.1.5 Assay Unit Operation Summary. The assay unit operation includes all facilities, subsystems, and equipment to (a) determine radioactivity, physical properties, and parameters needed to classify the metallic waste, and (b) separate LLW metal from TRU metal.

- The metal waste stream will be examined by radio-assay devices to allow classification of waste in accordance with the DOE and U.S. Nuclear Regulatory Commission (NRC) transportation and disposal requirements. Various devices, such as passive neutron counting (PAN) and gamma spectroscopy (SGS) instruments, may be used. The radio-assayed containers will be first classified as LLW or TRU metal waste. The LLW and the TRU metal containers will be transported to the Waste Receiving, Processing, and Packaging Facility for treatment and disposal.

2.1.2 Subsystem Boundaries

The Metal Decontamination and Sizing Subsystem consists of the unit operations shown in Figure VII-2-1. The Metal Decontamination and Sizing Subsystem will be contained in alpha cells within the Waste Receiving, Processing, and Packaging Facility.

2.1.2.1 Physical Boundaries. The physical boundaries include (a) opening and sorting unit operations within the Waste Receiving, Processing, and Packaging Facility are the boundaries for bulk metal and loose metal input streams, and (b) the Waste Receiving, Processing, and Packaging Facility is the boundary for the output streams.

Figure VII-2-1. Unit operations for the Metal Decontamination and Sizing Subsystem (S-BL-1).

Note: Mass flow balance does not show the input process additives.

(H) 100% 100% 100%

THE REACTION OF THE SUBSTANCE WITH THE REAGENT AND
AFTER THE REACTION THE REACTION MIXTURE IS
EXTRACTED WITH THE REAGENT AND THE REACTION MIXTURE IS
EXTRACTED WITH THE REAGENT AND THE REACTION MIXTURE IS
EXTRACTED WITH THE REAGENT AND THE REACTION MIXTURE IS

DATE
2/13/01

2.1.2.2 Utilities. The Metal Decontamination and Sizing Subsystem will require services from the service water system, plant steam, and electrical power supply. The boundaries for the utilities include (a) service water shut-off valves located at the Waste Receiving, Processing, and Packaging Facility service water header, (b) the steam shut-off valves located at the Waste Receiving, Processing, and Packaging Facility steam header, and (c) the power supply at the Waste Receiving, Processing, and Packaging Facility power main.

2.1.2.3 Environment. The Metal Decontamination and Sizing Subsystem will have interfaces with the building ventilation system discharge.

2.1.3 Process Functional Diagram

2.1.3.1 Subsystem Specific Assumptions. The following unique subsystem specific assumptions apply to the Metal Decontamination and Sizing Subsystem: (a) seventy pounds of LLW metal are obtained per 100 lb of metal feed, (b) thirty pounds of TRU metal are obtained per 100 lb of metal feed, and (c) twenty pounds of TiU residue are expected per 100 lb of metal feed after extra solution is introduced for the washing operation.

2.1.3.2 Process Functional Diagram. The mass flow rates and energy requirements for the Metal Decontamination and Sizing Subsystem are shown in Figure VII-2-1.

2.1.4 Facility Description

2.1.4.1 General Arrangement. General arrangements for the Waste Receiving, Processing, and Packaging Facility are shown in Figure VII-2-2.

2.1.4.2 Surge Storage Requirements. Storage capacity will be provided for the incoming reusable containers and packaged containers of LLW metal, TRU metal, and TRU residue. The storage area will contain (a) a material handling system, (b) fire protection, (c) ventilation, and (d) monitoring per RCRA.

WASTE RECEIVING, PROCESSING AND PACKAGING FACILITY			
METAL DECON AND SIZING SUBSYSTEM			
(S-BE-1) - GENERAL ARRANGEMENT
JOB NO.	FIGURE	DATE
	20995-005	2-2	02/14/91

Figure VII-2-2. General arrangements for the Waste Receiving, Processing, and Packaging Facility (S-BE-1).

2.1.5 System Design Requirements

2.1.5.1 Functional Requirements. Functional requirements for the Metal Decontamination and Sizing Subsystem include the following:

- Receives bulk and loose metal from RWMC
- Decontaminates metallic waste
- Processes and transfers all metallic waste streams to the Waste Receiving, Processing, and Packaging Facility
- Processes and transfers liquid waste from the decontamination process to the Waste Receiving, Processing and Packaging Facility.

2.1.5.2 Performance Requirements.

- The Metal Decontamination and Sizing Subsystem capacity will be designed to process and package buried metallic waste from RWMC over a 10-year period
- The Metal Decontamination and Sizing Subsystem will have an operational availability of 24 h/d, 5 d/wk, and 70% plant availability during operation, operating 240 d/yr
- The Metal Decontamination and Sizing Subsystem will meet the INEL onsite transportation requirements for hazardous waste transfer
- The Metal Decontamination and Sizing Subsystem will have the ability to sort and segregate LLW and IRU metal
- The effect of the subsystem operation on the worker and public health and safety will be minimal

- The system will have high reliability, operability, and maintainability factors
- The Metal Decontamination and Sizing Subsystem will have the ability to reduce the size of the incoming metal waste
- The Metal Decontamination and Sizing Subsystem will have the ability to decontaminate the metal waste for LDR treatment.

2.1.6 Interface Requirements

The subsystem interfaces with the Retrieval Subsystem (S-BE-4).

2.1.6.1 Support to Other Systems (Output). The Metal Decontamination and Sizing Subsystem provides the following output to the Waste Receiving, Processing, and Packaging Facility:

- LLW of 70 lb per 100 lb of feed metal
- TRU metal of 30 lb per 100 lb of feed metal
- TRU residue of 20 lb per 100 lb of feed metal resulting from adding 20 lb of cleaning liquid per 100 lb of feed metal

2.1.6.2 Support from Other Systems (Input). The Metal Decontamination and Sizing Subsystem receives the output of the Waste Receiving, Processing, and Packaging Facility in the form of bulk and loose metals. The subsystem receives (a) service water, (b) power, (c) ventilation input, (d) steam from the utilities subsystem. Input consumables are (a) reusable containers, (b) solidification materials, and (c) decontamination (cleaning) fluids.

2.2 SYSTEM ASSESSMENT

The current status, program implementation risks, and pro/con analysis of the unit operations associated with the Metal Decontamination/Sizing System are discussed below. The integration aspects of forming a complete subsystem that satisfies the functional, performance, and interface requirements are complex and may perturb individual unit operations or necessitate research and development efforts because of integration problems not previously identified.

2.2.1 Current Status of Unit Operations

There are five unique unit operations associated with the Metal Decontamination and Sizing Subsystem (S-BE-1). The unit operations are discussed below.

2.2.1.1 Metal Pretreatment. The metal pretreatment unit operation cleans and provides a preliminary sorting of the incoming bulk metal stream. Sorting operation classifies the incoming material to allow decontamination by a proper technique. The pretreatment of the bulk metal removes soil, soluble salts, and other nonmetal materials attached or adhered to the metal surface. The technologies employed include vibratory screen, material handling, manipulators, and high-pressure pulsating jet wash equipment. The components associated with the metal pretreatment unit operation are commercially available and in use by industry; therefore, no DT&E of the technology will be required except minor efforts to determine pretreatment requirements for various metal types.

2.2.1.2 Size Reduction. The technology employed for size reduction may include shearing, sawing, shredding, laser sectioning, and plasma torch. The components, except for laser sectioning, associated with the metal pretreatment unit operation are all commercially available and in use by industry. Plasma torch is currently in use in an alpha cell environment at the Rocky Flats Plant and Los Alamos National Laboratory (LANL). Because these components, with the exception of laser sectioning, are commercially

available, no DT&E of the technology will be required. Laser sectioning requires DT&E to develop applications, and to integrate the equipment within an alpha cell enclosure.

2.2.1.3 Metal Decontamination. The metal decontamination unit operation uses decontamination techniques to remove surface contamination to the greatest extent possible. Technologies under consideration for the decontamination unit operation include electropolishing, grit blasting, CO₂ pellets, blasting, ultrasonic cleaning, vibratory finishing, steam cleaning, and chemical cleaning.

These technologies are currently employed in the nuclear industry and are commercially available. Research of additional technologies is not required. DT&E of the application of these techniques to a wide range of expected metal objects would be required to ensure that the objectives of the metal decontamination unit operation are achieved. The development of these technologies should also focus on waste minimization and integration within an alpha cell enclosure.

2.2.1.4 Liquid Waste Treatment. The liquid waste treatment unit operation collects and drains any contaminated waste liquids and sludges from the other metal decontamination unit operations. The collected waste may be treated to remove dissolved and suspended solids and to minimize the liquid waste volume using a combination of technologies including demineralization, centrifuge, evaporation, calcination, grouting, filtration, and TRU/Clear (a proprietary process that removes TRU contamination).

These technologies, except for TRU/Clear, are currently in use in the nuclear industry, and the components associated with these technologies are all commercially available. TRU/Clear (see Section 3 for a more detailed description) is in the DT&E phase. Because the components are commercially available, no DT&E will be required. Development efforts will be required to integrate and improve the efficiencies of the technologies within the metal decontamination unit operation and to ensure that the output streams are compatible with waste disposal requirements.

2.2.1.5 Assay. The assay unit operation provides a characterization of the metal waste streams in accordance with the DOE and NRC transportation and disposal requirements. The technologies employed in this unit operation include PAN, SGS/multichannel analysis, gross gamma detectors, gross alpha detectors, gross beta detectors, and smear tests.

The components of this unit operation are all commercially available and are currently in use in the nuclear industry. There should be no research required of these technologies or new technologies.^a Demonstrating the integration the component to meet the objectives of the assay unit operation may be required.

2.2.2 Program Implementation Risks

The following is a qualitative assessment of risk associated with each unit operation of the Metal Decontamination and Sizing Subsystem (S-BE-1). The purpose of this risk assessment is to determine if this subsystem will have a significant impact on the technical performance, health and safety, schedule, and cost risks of the parent system. Based on the discussions presented below, it is believed that program implementation risk from this subsystem is low in all areas.

2.2.2.1 Metal Pretreatment. The metal pretreatment unit operation cleans and provides a preliminary sorting of the incoming bulk metal stream. The pretreatment of the bulk metal removes soil, soluble salts, and other nonmetal materials attached or adhered to the metal surface. The metal pretreatment segregates, washes, and prepares the waste for processing. It is unlikely that there will be a failure by these technologies. All technologies identified are currently in use at various industrial facilities performing the exact same tasks. The safety function isolates the hazardous waste from human contact. The risk is low because there is little likelihood of failure,

a. Based on independent efforts at the INEL subsequent to the completion of this effort, PAN techniques commercially available today are not likely to satisfy the detection requirements for TRU materials. Additional DT&E is expected.

providing reasonable precautions are taken to ensure proper operation within an alpha cell environment. The cost model is not at significant risk because known technologies are used. There is no unusual schedule risk.

2.2.2.2 Size Reduction. This unit operation will size-reduce the larger bulk metal objects to aid in decontamination of the metal and to permit a more efficient container filling operation. This step reduces the size of bulk metal for subsequent operations. All of the identified technologies under consideration have historically performed well at this task. There is little technical risk that these methods will not perform their function within the given environment. Large machine tool equipment will be difficult to size-reduce and may take specialized procedures and additional time. There is little risk associated with these technologies as long as the appropriate industrial safety and operations procedures are observed. The cost model is not at significant risk because known technologies are used. There is no unusual schedule risk.

2.2.2.3 Metal Decontamination. The metal decontamination unit operation uses decontamination techniques to remove surface contamination to the greatest extent possible. The function of metal decontamination is to remove surface radioactive contamination from metals. Most of the identified technologies have historically performed well at this task. There is little technical risk that these methods will not perform their function within the given environment, and safety risk associated with these technologies is small as long as the appropriate industrial safety and operations procedures are observed. The cost model is not at significant risk because known technologies are used. There is no unusual schedule risk.

2.2.2.4 Liquid Waste Treatment. The liquid waste treatment unit operation collects and treats any contaminated waste liquids and sludges from the other metal decontamination unit operations. The function of the liquid waste treatment is to remove suspended and dissolved solid impurities and to minimize the volume of output waste. All of the identified technologies have historically performed well at this task. There is little technical risk that these methods will not perform their function within the given environment.

The only risk will be associated with regulatory compliance for waste stream byproduct handling and disposal (in a continually changing regulatory environment). There is little safety risk associated with these technologies as long as the appropriate industrial safety and operations procedures are observed. The cost model is not at significant risk since known technologies are used. There is no unusual schedule risk.

2.2.2.5 Assay. The assay unit operation provides a characterization of the metal waste streams in accordance with the DOE and NRC transportation and disposal requirements. The function of the assay unit operation is to sense, quantify, record, and report levels of radioactive contamination of metals. All of the identified technologies have historically performed well at this task. There is some technical risk that these methods will not perform their function within the given environment. The assay process must be improved to match the anticipated system material process rate. The safety risk associated with these technologies is small as long as the appropriate industrial safety and operations procedures are observed. The cost model is not at significant risk because known technologies are used. There is no unusual schedule risk.

2.2.3 Unit Operations Pro and Con Analysis

The following is a pro and con assessment of each unit operation of the Metal Decontamination/Sizing Subsystem (S-BE-1). The pros (advantages) and cons (disadvantages) are discussed in light of the overall objectives of the Environmental Restoration Program. The compatibility of interfaces and specific areas of weaknesses in the unit operation are addressed.

2.2.3.1 Metal Pretreatment. The metal pretreatment unit operation cleans and provides a preliminary sorting of the incoming bulk metal stream. The pretreatment of the bulk metal removes soil, some of the contamination, soluble salts, and other nonmetal materials attached or adhered to the metal surface. The advantages of this unit operation are that it eliminates extraneous nonmetallic materials that may contaminate or neutralize decontamination solutions, reduces waste volume, reduces soil and dust

carryover to process units, and minimizes spread of contamination from dust and loose material. However, it creates a secondary waste stream(s) requiring further treatment or processing, resulting in an expansion of waste processing. This unit operation may not be required for all bulk metal, and as a result may not be beneficial in every case.

2.2.3.2 Size Reduction. This unit operation will size-reduce the larger bulk metal objects to aid in the decontamination of the metal and to permit a more efficient filling operation. Advantages of size reduction are that the plasma arc torch is used extensively for industrial metal cutting applications. It can handle odd shapes, thick stock, and hardened metals. In addition, mechanical nibblers have a punch and die cutting action and produce minimal contamination entrainment in the cut. Mechanical saws are lightweight, versatile, and maneuverable. Hydraulic shear is rapid and produces little contamination of the cut. Disadvantages of this system are that the plasma arc torch generates a shower of sparks that represents a potential fire and contamination dispersion hazard. They generate smoke that impairs visibility for the operator. Also, the smoke and fumes tend to plug HEPA filters. Large machine tool equipment will be very difficult to size reduce. Mechanical nibblers are largely limited to cutting material with planar surfaces and gentle contours from limited maneuverability with the larger units. Mechanical saws are relatively slow when cutting thick sections, and the hydraulic shear requires its feed to be previously sectioned to fit in the machine.

2.2.3.3 Metal Decontamination. The metal decontamination unit operation uses decontamination techniques to remove surface and entrained contamination to the greatest extent possible. Several pros have been identified for this unit operation. High-pressure water wash, steam cleaning, and chemical cleaning are standard decontamination techniques in the nuclear industry, and electropolishing and vibratory finishing are efficient techniques capable of decontaminating metal to below TRU levels. Vibratory finishing is a commercial metal finishing process. Also, electropolishing is capable of decontaminating large sections of metal using a large immersion tank. A disadvantage of metal decontamination is that oxide and corrosion layers on

metal surfaces will slow down electropolishing. Vibratory finishing requires the metal to be size-reduced sufficiently to allow the vibratory media to reach all the contaminated surfaces. However, grit abrasive blasting can smear the contamination further into the surfaces of some metals. A secondary waste stream (grit slurry) is generated, which must be processed. The metal decontamination process may not always decontaminate the metal to free release.

2.2.3.4 Liquid Waste Treatment. The liquid waste treatment unit operation collects and drains any contaminated waste liquids from the other metal decontamination unit operations. Advantages of this unit operation are that evaporation is a standard waste treatment process in the DOE complex (e.g., Savannah River Site and Hanford Site), and demineralization is a standard treatment at nuclear power plants. The disadvantage is that treatment techniques are not readily available for detoxification if the decontamination solution is subject to RCRA control.

2.2.3.5 Assay. The assay unit operation provides a characterization of the metal waste streams in accordance with the DOE and NRC transportation and disposal requirements. The advantage of assay unit operation is that instruments for certification are available. Disadvantages include (a) changing WIPP acceptance criteria may change the instruments required, and (b) production-scale instrumentation with high throughput and reliability needs development.

2.2.4 Unit Operations Lead-Time Estimates

The lead-time required for DT&E is estimated for each unit operation that may require research and development before landing in the field (see Table VII-2-1). The development of the lead-time required for DT&E is based on a qualitative judgment and should be further refined.

For each unit operation (as appropriate), time lines are shown for research, development, and demonstration. In many cases, only development or

demonstration lead-time is required. To reflect weaknesses, each time line reflects an expected lead-time.

2.2.5 Rough Order of Magnitude Cost Estimates

ROM costs were developed for the Metal Decontamination and Sizing Subsystem (S-BE-1) using the assumption given in Section 1 of this volume and those listed below (the costs are summarized in Table VII-2-2):

- Special site preparation costs are not included such as drainage, substations, roadwork, and other utilities.
- Owner's costs such as environmental impact report costs, owner's labor, and overheads, are not included.
- The estimate is based on first quarter 1991 wage and price levels.
- The facility areas are developed based on a conceptual layout of process equipment. Allowances for administrative and remote operation facilities are not included.
- The equipment scope is based on conceptual process flow diagrams.
- Equipment pricing is based on conventional commercial construction.
- Minimal allowance (e.g., one-of-a-kind demonstration) has been included for remote operation as well as any nuclear quality assurance program cost.
- The areas shown in the functional and operational requirement (F&OR) general arrangement were adjusted to account for the unit operation capacities.

Table VII-2-2. Rough order of magnitude cost estimates (S-BE-1)

Cost Code	Cost Items	Normalized Cost (\$x1000)	Modified Cost (\$x1000)
1.0	Studies and bench scale costs		
1.1	Manpower costs during research	\$1,600	
1.2	Equipment costs	\$1,000	
1.3	Installation costs	\$250	
1.4	Contingency	\$713	
	Subtotal 1.0	\$3,563	
2.0	Demonstration costs		
2.1	Manpower cost during construction	\$1,600	
2.2	Design cost (30% of 2.5)	\$2,088	
2.3	Inspection cost (7% of 2.5)	\$487	
2.4	Project administration (10% of 2.5)	\$696	
2.5	Construction cost		
2.5.1	Building structure costs		
2.5.2	Equipment costs		
2.5.3	Indirect (20.9% of 2.5)		
	Subtotal of 2.5	\$6,959	
2.6	Construction management costs (27.8% of 2.5)	\$1,997	
2.7	Contingency	\$3,457	
	Subtotal 2.0	\$17,284	
3.0	Production construction costs		
3.1	Design cost (30% of 3.4)	\$11,302	
3.2	Inspection cost (7% of 3.4)	\$2,637	
3.3	Project administration (10% of 3.4)	\$3,767	
3.4	Construction cost		
3.4.1	Building structure costs	\$15,170	
3.4.2	Equipment costs	\$14,612	
3.4.3	Indirect (20.9% of 3.4)	\$7,892	
	Subtotal of 3.4	\$37,674	
3.5	Construction management costs and construction management reserve (26.5% of 3.4)	\$10,812	
3.6	Contingency (25% of 3.1 through 3.5)	\$16,548	
	Subtotal 3.0	\$82,741	
	Total Capital Cost (1.0, 2.0, and 3.0)	\$103,588	
4.0	Annual Operating and maintenance costs		
4.1	Operating costs	\$6,000	
4.2	Utility costs	\$1,400	
4.3	Material costs	\$2,400	
4.4	Maintenance costs	\$2,800	
4.5	Contingency	\$3,150	
	Subtotal 4.0	\$15,750	
TOTAL	10 Years Operating and Maintenance Costs	\$157,500	

- An allowance for process bulks is included at 30% of the equipment cost to account for electrical, piping, and local control requirements.
- Equipment costs include material, fabrication, delivery, inspection, and installation costs (all in costs).
- Costs for widening or strengthening existing roads for construction are not included.
- An adequate supply of labor is assumed to exist within the local area.
- Testing and initial startup costs are not included.
- Demonstration of the subsystem is assumed to occur within existing facilities.
- Operating and maintenance costs are based on 15% of production construction costs.
- Cost estimates are based on nominal costs associated with the best currently available technology considered. The latest technology and the state-of-the-art systems were not considered in the cost model.

Component costs may vary between unit operations depending on the technologies employed, and the cost estimate is based on relatively well-known technologies. No provision was made for DT&E associated with state-of-the-art technologies.

2.2.6 System Evaluation Results

The purpose of this section is to provide an overall evaluation of the subsystem and to identify the major considerations (both advantages and disadvantages) resulting from the assessments in the previous sections. This

includes an evaluation of the ability to integrate the various unit operations into a smooth, well-functioning subsystem.

Specific areas addressed include identification of the major considerations for the subsystem, a qualitative judgment rating of performance measurables, a summary of research and development needs, and an overall recommendation for the subsystem.

2.2.6.1 Identification of Major Considerations for the Subsystem. The techniques employed in this subsystem are well-known, commercially available, and in current use by the industry. There is a risk associated with the alpha cell enclosure and accessibility to repair or maintain the equipment. There is operational risk associated with processing the size and volume of the anticipated waste stream. This risk may require added redundancy and/or larger capacity to avoid processing delays.

The significant advantages for this subsystem are that most of the techniques employed by the subsystem are currently in use and well-known. The significant disadvantage for this subsystem is the generation of additional liquid waste without the benefit of free release of metal. Other cons for the subsystem include are that many metallic materials absorb radioactive contamination within the grain boundaries of the metal, and decontamination of the metal to free release is extremely difficult.

The technologies do not require significant DT&E. Demonstration time is required for integration of all unit operations for this subsystem. The costs for this subsystem should be well-known because the technologies are in current use.

2.2.6.2 Performance Measurables Rating. Performance measurables that should be used in the evaluation of the overall subsystem represent the top level of performance requirements that will be allocated and then applied to appropriate elements of the subsystem in subsequent phases of the program. Table VII-2-3 provides a qualitative assessment of how well the Metal Decontamination/Sizing Subsystem satisfies these performance measurables.

Table VII-2-3. Rating performance measurables for the Metal Decontamination and Sizing Subsystem (S-BE-1)

Measurables	Metal Pretreatment	Size Reduction	Metal Decon	Liquid Waste Treatment	Assay	Total
Timeliness	9	8	8	9	9	43
Availability	9	8	8	9	9	43
Completeness	7	7	7	8	9	38
Risk	7	7	7	8	9	38
Flexibility	8	8	7	8	8	39
Cost	8	8	6	8	9	39
Safety	8	8	7	8	9	40
Waste reduction	7	8	7	8	7	37
Complexity	8	7	7	7	7	36
Totals	71	69	64	73	76	353

2.2.7 Summary of Demonstration, Testing, and Evaluation Needs

The DT&E needs for each unit operation and for the overall subsystem have been summarized in Table VII-2-4. This table provides a ready reference to R&D needs in the final subsystem evaluation and for comparison purposes with other subsystems.

2.3 RECOMMENDATION FOR THE SYSTEM

The Metal Decontamination/Sizing Subsystem essentially using existing technology to pretreat, size-reduce, decontaminate, and assay retrieved metallic waste to minimize the quantity of metal waste requiring long-term burial. The technologies employed are all currently available, permitting an early start on design, fabrication, and installation. Recommended DT&E for this subsystem includes the following:

- An analysis of the queuing of the metal waste stream is needed to determine the capacities of components for unit operations
- The system as a whole will require fine tuning of all the selected technologies to produce the desired end results
- The integration of the process streams should be reviewed to ensure compatibility
- Consideration should be given to on-line sensors that monitor and report the status and progress of waste stream processing
- Sampling and processing of the types of metals and the degree of contamination with a prototype of this subsystem would assist in determining the benefits of this subsystem.

The study helped to characterize and define a number of alternatives for the unit operations of this system. The evaluations conducted under this

Table VII-2-4. DT&E needs for the Metal Decontamination and Sizing Subsystem (S-BE-1)

Unit Operation	Technology		DT&E
	Development Status		
Metal pretreatment	• Commercially available		• Application in production-scale environment
	• Currently used in the manufacturing industry		• Integration
Size reduction			• Application to waste stream (various metal types)
			• Remote operation
			• Maintenance concepts (remote or contact)
	• Commercially available		• Application in production-scale environment
	• Currently used in the nuclear industry		• Integration
			• Application in alpha cell
			• Application to waste stream
			• Remote operation
			• Maintenance concepts (remote or contact)
Metal decontamination	• Commercially available		• Application in production-scale environment
	• Currently used in the nuclear industry		• Integration
			• Application in alpha cell
Liquid waste treatment	• Commercially available		• Application in production-scale environment
	• Currently used in the nuclear industry		• Integration
			• Application in alpha cell
			• Application to a wide range of metal objects

Table VII-2-4. (continued)

Unit Operation	Technology Development Status	DT&E
Liquid waste treatment (continued)		<ul style="list-style-type: none">• Remote operation• Maintenance concepts (remote or contact)• Application to a wide range of influents• Identify recovery methods of liquid contaminants• Characterization of liquid waste stream• Identify clean up efficiency decontamination factor requirements
Integrated subsystem		<ul style="list-style-type: none">• Application in production-scale environment• Integration• Reliability, availability, and maintainability of the process in an alpha cell environment• Remote operation and maintenance• Automation• Remote operation and maintenance

study conclude that DT&E is required. Qualitative judgments were used in developing the extent of DT&E required. A more detailed assessment is needed to draw a definitive conclusion on DT&E programs, costs, and technology selection.

Program implementation risk assessments in the study are qualitative and judgmental and are based on the assumption that wastes having dangerous physical or chemical characteristics (e.g., pyrophoric, gas cylinders containing toxic, and volatile and reactive gases) are not being processed. A more detailed definition of the incoming waste will be needed to perform a complete risk assessment and significant changes in the composition of the waste may impact the technologies selected and the general arrangement of the facilities.

In summary, the key benefit of the Metal Decontamination/Sizing Subsystem is that it offers a treatment process for metals to minimize the degree of contamination and quantity of metals requiring long-term disposal.

3. SOILS PROCESSING SUBSYSTEM (S-EB-2)

The Soils Processing Subsystem is used by other systems within the SDS to process the large quantities of soil retrieved from the SDA at RWMC. The final products are clean soil, TRU soil (which goes back to the host system), and LLW that meets the LDR requirements.

3.1 FUNCTIONAL AND OPERATIONAL REQUIREMENTS

3.1.1 System Description

Thermal desorption is used to remove organic contaminants, solidification is used to fix inorganic contaminants, and a soiling washing process is used to minimize the volume of TRU contaminated soil. "TRU/Clear" is used to purify the water used to slurry the soil in the soil washing process.

Thermal desorption is a thermal process in which the soil is heated at low temperatures to volatilize the organic compounds adsorbed to the soil. Soil washing may be one of several mining technology processes that separates TRUs, other radioactive isotopes, and heavy metals from a soil slurry. In most processes, the contaminate particles are concentrated in a small fraction of the slurry, resulting in a clean fraction and a contaminated fraction that contains the contaminants. The final product is dewatered and packaged for further processing by the parent system. The TRU/Clear process uses potassium ferrate (extremely soluble in caustic solutions, pH 9-12) to precipitate out a ferric hydroxide complexed metal sludge. Solidification is a well-established, proven process.

Soil entering the Soils Processing Subsystem is initially emptied from its container into a crusher to homogenize the soil before thermal desorption treatment. A thermal desorber heats the soil to approximately 450°F. At or below this temperature, most volatile and semivolatile organic compounds are thermally stripped from the soil. The organic vapors are captured in an off-

gas treatment system consisting of either granular activated carbon or an afterburner and/or scrubber.

Water from the soil washing operation can be recycled if the TRUs are removed from it. The TRU/Clear process will polish this recycle water. TRU/Clear uses potassium ferrate to precipitate out ferric hydroxide complexes containing TRUs. The sludge that is formed in the TRU/Clear process is dewatered and combined with the TRU soil exiting the soil washing operation.

The non-TRU soil separated in the soil washing operation is assayed for LLW on a conveyor. Batches of soil that are detected as containing LLW are segregated from the clean soil. The clean soil is packaged for delivery to its proper disposal/refill site. Before packaging, each batch of clean soil will be tested for metal contamination. Those soils contaminated with metals will be combined with the LLW soil for solidification/stabilization.

The LLW soil is solidified by mixing the soil with a binder (such as Portland cement) and water and pouring the mixture into drums. The dried product is leach resistant and will meet the standards for LDR. The solidification operation will be automated to the extent feasible.

3.1.2 Subsystem Boundaries

This subsystem includes those processes required to produce clean soil, an LLW form that meets LDR and TRU soil ready for processing in the system that uses this subsystem.

Material crosses the system boundary in several places. Bulk soil is received from the Retrieval Subsystem. There are three major system effluents: clean soil, LLW that meets LDR requirements, and TRU soil that is returned to the host system for processing.

3.1.3 Process Functional Diagram

3.1.3.1 System-Specific Assumptions. The following system-specific assumptions were used in estimating the values in the Process Functional Diagram:

- Remediation is to be completed in 10 years. There are 240 24-hour work days per year. Equipment availability is 70%.
- The bulk density of the soil is 116 lb/ft³. The total mass of soil to be processed over a 10-year period is 565,900 tons.
- Composition of the waste fed to the thermal desorber: 84% inerts, 14% moisture, and 2% MAF (moisture and ash-free fraction).
- The soil washing process concentrates the TRU and heavy metal contaminants in 5% of the product. Ninety-five percent of the product is clean soil. Two pounds of water per pound of soil is used to create a slurry. The water used to create the slurry is purified with the TRU/Clear process and recycled back to the soil washing process.
- The LLW soil assay shows 25% of the soil to be LLW and 75% of the soil to be nonradioactive.
- The metals testing shows 25% of the soil batches to be contaminated with metals and 75% to be clean soil.
- Fifty-nine percent of the solidified LLW product is soil, the balance being water and cement.

3.1.3.2 Process Functional Diagram. Figure VII-3-1 is a process functional diagram for this subsystem. Mass flow rates are noted on the diagram for each applicable stream. The capacities noted are based on current working technology, although some process technologies require additional

DESCRIPTION:

- DECONTAMINATE SOIL TO REMOVE ORGANIC CONTAMINANTS.
- PREPARE SOIL FOR REUSE OR TO CONTINUE WATER CONTAMINANTS AND REDUCE VOLUME OF EXCAVATED SOIL.
- ARIAY AND DECONTAMINATE WITH THERMAL DESORPTION AND ACTIVE SOIL.
- THERMAL DESORPTION AND ACTIVE SOIL DECONTAMINATE SOIL CONTAMINANTS AND REDUCE VOLUME OF EXCAVATED SOIL.
- THERMAL DESORPTION AND ACTIVE SOIL DECONTAMINATE SOIL CONTAMINANTS AND REDUCE VOLUME OF EXCAVATED SOIL.

Figure VII-3-1. Process functional diagram for the Soils Processing Subsystem (S).

Note: Mass Flow balance does not show the input process additives.

testing and experience before they can be called proven technologies. Energy requirements are also indicated in Figure VII-3-1.

3.1.4 Facility Description

Figure VII-3-2 shows the footprint of the Soils Processing Subsystem. The unit operations are divided into two equal, parallel trains: Train One and Train Two.

Approximately 4000 ft² of floor space will be required to house the thermal desorber, soil crusher, and the off-gas treatment equipment (vapor and liquid phase carbon absorbers, condensers, and oil/water separators).

The soil washing operation will require approximately 7900 ft² of workspace for the following equipment: feed hopper, disc screen, conveyors, monitoring/assay equipment, slurry mixer, gravimetric separator, and dewatering equipment. It also includes space for the LLW soil assay equipment.

The TRU/Clear process will require approximately 1000 ft² of floor space for wastewater tanks, feed systems, and dewatering equipment.

The cement solidification operation will require approximately 3100 ft² of workspace for the following equipment: feed hoppers, mixers, pouring station, and interim storage space for feed material and curing product.

3.1.5 System Design Description

3.1.5.2 Functional Requirements. This subsystem must significantly reduce the volume of TRU contaminated soil. Also, the low-level final waste form must meet LDR requirements (destroy organic contaminants and fix inorganic contaminants). Feed to the system will consist of contaminated soil retrieved from Pits 1-6, 9, and 10 and Trenches 1-10 of RWMC. The system must be capable of processing all of the soil within a 10-year time frame.

256'-0"

SOIL PROCESSING SUBSYSTEM	EGRG SYSTEM DESIGN STUDY	
	FACILITY LAYOUT	
PROCESS: INEL SYSTEM DESIGN STUDY SOIL PROCESSING SUBSYSTEM	EBASCO ENVIRONMENTAL	LAYOUT NO
		S-EB-2
SCALE 1"=25'		2/21/91

Figure VII-3-2. Facility layout for the Soils Processing Subsystem (S-EB-2).

Thermal desorption will be used to remove organic contaminants. The soil washing process will be used for TRU soil volume reduction. Solidification with Portland cement will be used to immobilize inorganic contaminants and produce a solid waste form that meets the LDRs.

3.1.5.2 Performance Requirements. The thermal desorber(s) will have the capacity to process 35,000 lb of contaminated soil per hour and will be fired on propane. The off-gas treatment process will be required to meet all appropriate municipal, state, and federal regulations.

The soil washing operation will have a 30,000 lb/h capacity, with a minimum detection sensitivity of approximately 5 pCi/g for plutonium-239.

The TRU/Clear process will have the capacity to treat 120 gal/min of soil washing recycle water.

The cement solidification plant will have the capacity to solidify contaminated soil at a minimum rate of 5 yd³/h.

3.1.6 Interface Requirements

Soil received from the Retrieval Subsystem will be solid material packaged in standard boxes and drums. Each package will be labeled with general identification and assay information.

Containers of solidified waste will have been assayed to confirm classification as LLW. The containers will be labeled with general identification and assay information. The solidified mass will meet LDRs.

TRU contaminated soil will be returned to the host system for further processing. This material will be packaged in standard boxes and drums. Each package will be labeled with general identification and assay information. Although not a slurry, substantial amounts of moisture will be present in the soil.

Clean soil will be dewatered, sampled, and certified to be ready for release for unrestricted use. The soil will be packaged in standard boxes and drums. Each package will be labeled with general identification and assay information.

3.2 SYSTEM ASSESSMENT

The following section is an assessment of the feasibility of implementing the Soils Processing Subsystem. This assessment includes a review of the current status of each unit operation composing the subsystem; a discussion of the technical, safety, cost and schedule risks associated with each unit operation; and a pro/con analysis of the unit operations.

3.2.1 Current Status of Unit Operations

The Soils Processing Subsystem is a unique application of combining several unit operations that are currently either commercially available or operating as full-scale demonstrations. These unit operations include thermal desorption (to remove volatile and semivolatile compounds), soil washing process (to separate TRU contaminated soil from LLW/clean soil), TRU/Clear process (to separate TRU elements from the soil washing process recycle water), solidification (to fix the inorganic contaminants), and an assay conveyer (to separate LLW soil from nonradioactive soil).

3.2.1.1 Thermal Desorption. Thermal desorption has demonstrated at full-scale the ability to remove petroleum hydrocarbons below detection level and aromatic compounds at an average of 99.9% from soil. The technology is also being applied full-scale to the removal of jet fuel and chlorinated solvents from soils (demonstrated at Tinker Air Force Base). Previous bench-scale studies and pilot-scale studies have shown greater than 99.9% removal of VOCs and 99.8% removal of the oil and grease (Nielson et al., 1989). Thermal desorption has also been used successfully to separate volatile organics from low-level mixed wastes at a pilot-scale plant demonstration at Oak Ridge National Laboratory (ORNL) in 1988.

The off-gas would be decontaminated using either vapor phase carbon adsorption (if the organic content is low) or an afterburner or scrubber (if the organic content is high). Both of these technologies are commonplace.

3.2.1.2 Soil Washing. A soil washing system has been demonstrated at full-scale on Johnston Island (AWC Inc., 1989) to remove plutonium-239 from soil. The plant had a capacity of 15 yd³/h and a minimum detection sensitivity of approximately 5 pCi/g. A total of 1400 yd³ was processed during this demonstration. Numerous other vendors have adopted soil separation processing equipment from the mining industry and used it for soil washing.

Pilot-scale plant demonstrations have been performed since 1985 on radioactive soil wastes containing plutonium, uranium, and radium. These soils were collected from various facilities including Johnston Atoll, the Rocky Flats Plant, Nevada Test Site, and BOMARC Missile Site. The process has achieved overall volume reductions of 45 to 95% and is capable of reducing the activity to less than 15 pCi/g of soil. (AWC Inc., 1989; Bramlitt, 1988) Soil feed that has been incinerated in high-temperature incinerators or soil that is rich with oils may pose a problem for this technology.

3.2.1.3 TRU/Clear. The TRU/Clear process (Analytical Development Corp.) was bench tested in 1990 using radioactive wastewaters from several DOE facilities (including LANL, the Rocky Flats Plant, West Valley, and Savannah River). Full-scale studies at LANL demonstrated the technology could remove TRUs to a level below both DOE and EPA criteria. In addition, a full-scale demonstration was performed at the West Valley Demonstration Plant. The wastewater throughput at West Valley is on the order of 21 million gal/yr and contains such radioactive elements as plutonium, americium, uranium, and strontium. (Deiningner, 1990; Boehmer et al., 1986) The flow rate and compounds of the West Valley wastewater is similar to the predicted contaminated effluent from a soil washing process in this proposed soil processing subsystem.

The TRU/Clear process is a precipitation technology and therefore will generate a sludge containing the TRU elements. This TRU sludge will require dewatering via either ultrafiltration or clarification (both established technologies). The TRU sludge would then be combined with the TRU soil separated in the soil washing process.

3.2.1.4 Solidification. Solidification is a commercially available technology. A previous study using INEL hazardous and mixed wastes concluded that solidification was an effective method for treating these wastes. Waste samples included both metals and LLW. Binders used successfully in this study included cement, cement-silicate, and Envirostone. A mechanical/manual grout preparation and drum fill system was demonstrated at the Process Experimental Pilot Plant (PREPP) at the INEL (Cwynar et al., 1986). The system has the capacity to produce 8.5 t/d of cemented waste.

An automated cement solidification system and material handling system controlled by a programmable logic controller (PLC) has been developed and demonstrated to solidify 55-gal drums at a rate of 6 drums/h at West Valley in 1985 (Jessop et al., 1986; Borham et al., 1986).

3.2.1.5 Low-Level Waste Assay Conveyor. Assay conveyor systems have been used on a production scale to separate LLW from nonradioactive wastes. Puget Sound Naval Shipyard uses such a system to detect levels of cobalt-60 greater than 10 pCi/g. The size of the shield tunnel is 8 ft³ and separates the materials at a rate of 30 ft³/min. The soil washing system previously discussed uses an assay conveyor system to detect and separate the stray TRU soil from the LLW/nonradioactive soils by measuring the americium gamma ray, which can be related to Pu-239 presence. Soil assay in buried wastes will be considerably more complex than previously employed on the Johnson Atoll.

3.2.2 Program Implementation Risks

3.2.2.1 Technical Risks. All the unit operations within the Soils Processing Subsystem have been operating on at least a full-scale demonstration basis.

The thermal desorption system recommended here (using a screw processor) has only been tested in a hazardous waste environment containing no radioactive waste. Another thermal desorption system using a rotary kiln processor has been applied to low-level mixed wastes. These mixed wastes, however, did not contain TRU materials. The thermal desorber can remove most of organics, yet it is necessary to determine the concentration and character of the Texas Regal Oil in the soil. If the soil is saturated with heavy hydrocarbons, low-temperature thermal desorption may not be effective in treating the soil, and another technology (e.g., incineration) may be required. To produce an effluent compatible with the influent requirements of the soil washing process, the thermal desorber must remove the oils. In addition, the soil must exit in a matrix that is nonceramic. Considering the low operating temperatures (below 450°F), it appears unlikely that a ceramic matrix would form. However, the temperature must be based on the lowest melting temperature of the eutectics in the soil.

To date, a thermal desorber has not been designed to process 35,000 lb/h. A thermal desorber has been operated as high as 22,000 lb/h. By designing two parallel trains (each with a capacity of 18,000 lb/h) for the Soils Processing Subsystem, the performance requirements will be within a range previously tested. The system will require further testing and additional information before that rate can be guaranteed.

The off-gas treatment system would be based on a well-established technology. A properly designed activated carbon column, for example, is reliable. A potential problem for this system would be filtering random plutonium dust in the off-gas before treatment. HEPA filters alone may not be sufficient.

The soils processed at the demonstration plant at Johnston Atoll consisted mainly of sands. At the INEL, the soils contain basalt and clays. The performance of the soil washing systems will vary with the physical characteristics of the soil and will require initial research with a variety of INEL soils to minimize performance risks. Furthermore, as previously mentioned, the soil entering the soil washing process must be characterized to

determine the eutectics and oil content of the soil. The demonstration plant has been built and operated on a scale (15 yd³/h) that exceeds the performance requirements (10 yd³/h) of the Soils Processing Subsystem. Two parallel trains (5 yd³/h each) would give further confidence in performance as well as decreased downtime.

The uncertainty of the performance of the soil assay system will require DT&E to achieve sufficient precision and accuracy. Redundancy of the detectors may be required. A line of monitoring detectors will also be used to further segregate the LLW soil from the clean soil.

The TRU/Clear process has been designed for a TRU waste environment. Pilot plants have been operated at 50 gal/min to treat waters containing similar compounds (plutonium, americium) to those expected here. If two parallel trains are used, then each TRU/Clear system can be operated at 50 gal/min. If the feed soil and the process water from the soil washing system can be adequately defined, then a bench-scale test should produce confidence levels. A better understanding of the variation in contaminate concentrations in the process water over time will reduce the uncertainty of the precipitation chemistry. The theory of the chemistry itself is well-developed. Careful consideration of a dewatering process for the TRU/Clear sludge should not be overlooked. The dewatering process could potentially be the instigator of downtime.

The solidification process has been widely researched. A bench-scale study should give confidence levels. A worst-case scenario (for leaching) must be defined. If the system cannot properly mix the components (soil, water, and cement) for the worst case, then the drum will not pass the toxicity characteristic leaching procedure (TCLP) test. It is expected that a small percentage of drums will need to be reprocessed; however, the soil in use must be well-characterized to ensure that there will not be a large quantity of soil that does not meet TCLP.

Although the technology behind materials handling is well-understood, it is also the greatest source of downtime. The conveying and packaging of soil

will probably be the limiting factor of the Soils Processing Subsystem. If the processed soil cannot be packaged properly and quickly, the other unit operations will work inefficiently. The solidification of the LLW soil constitutes the largest effluent stream at 20 drums/h (480 drums/d). In addition, the drums will require manifesting/tracking. Many operators have not experienced the quantity of handling and paperwork expected here.

If two parallel trains are used, the downtime is significantly decreased. Each train would solidify and package 10 drums/h. (To further reduce performance risk, three trains at 10 drums/h could be used.) Automatic solidification and packaging of LLW has been demonstrated to handle this 10 drum/h requirement. Further research has developed, mixing systems that are more efficient than those demonstrated in the past. The research was directed at reducing the occurrence of plugging in the mixing and loading process. Plugging and blending are risks associated with the solidification system. Mechanical failures are risks associated with the material conveying/packaging to ease the operation and maintenance of these systems. Consideration will need to be given to space requirements necessary for quick repairs. Based on the above discussions, the technical risks are believed to be moderate.

3.2.2.2 Safety Risks. Safety risks are guided by the extent of plutonium in the soil. The release of plutonium-contaminated dust is a major concern. A screw-fitted thermal desorber run under negative pressure may be more successful in containing the plutonium dust than a rotatory kiln-type thermal desorber. The thermal desorber has not been run under such an environment, so some uncertainty exists.

Because the soil washing and TRU/Clear processes have been both used in this type of environment, it is assumed the safety risks are better defined and controlled. The volatiles have been removed, thus greatly reducing the likelihood of pressure excursions.

The greatest likelihood of safety risk would be associated with the materials solidification and handling. Worker interface and exposure would

occur most often in the drum opening and packaging tasks. Many tasks will be automated but with constant worker interface. Malfunction of material handling systems would increase safety risks as well as the repair of this equipment. Based on the above discussions, the safety risks are believed to be moderate.

3.2.2.3 Institutional Risks. There are no uncertainties regarding achievement of institutional objectives. The thermal desorber unit is a low-temperature process and should not be subject to public opposition. The institutional risk is believed to be low.

3.2.2.4 Cost Risks. Because of the lack of characterization of the feed soil, all the costs contain a great amount of uncertainty. In addition, all unit operations will be custom designed and built.

The cost of the thermal desorption unit is a vendor estimate based on a full-scale mobile operating unit. As stated, this device has not been used in a mixed waste site. There may be significant alterations in design and material to produce such a unit for this application.

The soil washing system is based on a vendor estimate for a slightly larger unit for a previous demonstration operation. The TRU/Clear system is based on a vendor price for a pilot-scale system. The cost risk for this system is associated with the operating cost, which is directly related to the concentration of TRU elements in the process stream. A wide range of unit costs were given, and a middle value was chosen.

The solidification system estimate is derived from commonly used systems and given a safety factor to include a radioactive environment. This system has the greatest uncertainty in cost, but will not be the highest cost component. The cost of this system and the materials handling systems will be tied significantly to the architectural design of the building.

A complete demonstration unit for the Soils Processing Subsystem would be roughly the size of one (proposed) parallel train. Once this train has been

demonstrated successfully, the second train would be added for full-scale operation. This approach would decrease cost risks. Based on the above discussions, the cost risk for this subsystem is believed to be low.

3.2.2.5 Scheduling Risks. It is assumed that technologies are established and do not require more than a year of development.

The thermal desorber will require the greater share of the demonstration time. This system can be fabricated and skid-mounted offsite. The thermal desorber is expected to require the greatest fabrication time. Startup time for the system will also depend on the operation of the thermal desorber and the soil washing operation. Permitting time will be required for the off-gas system.

The soil washing unit operation is the center of the Soils Processing Subsystem. The other unit operation depends on the information from this operation. If the demonstration for the soil washing operation is shifted off schedule, the schedule of the other operations and the startup time will be more than likely shifted as well. This unit operation can be fabricated and skid-mounted offsite.

The TRU/Clear operation can be fabricated and skid-mounted offsite. It is not expected that changes in the TRU/Clear schedule will affect the schedule of the other unit operations.

The solidification and packaging system would require the greatest installation time. Most of the system cannot be skid-mounted. Operating time would be limited by the solidification and materials handling systems (see Section 1.6.2).

Based on the above discussions, the risk associated with achieving schedule objectives is believed to be moderate.

3.2.3 Unit Operations Pro and Con Analysis

3.2.3.1 Thermal Desorption. To remove organic compounds from the INEL soil, a low-temperature thermal desorber is preferable to an incinerator. The advantages of a thermal desorber include less expensive operating costs, a more facile permitting climate, and an effluent more likely to be compatible with the influent requirements of the soil washing process (i.e., a nonceramic matrix). A disadvantage is that the technology works only for those organic compounds that volatilize at or below 450°F; very heavy hydrocarbons may not be thermally stripped. While thermal strippers have been successfully used to separate VOCs from low-level mixed wastes, such devices have not been operated in a TRU environment and may require materials testing and modifications in design. It is recommended that a screw-type processor be used because this type of processor may contain plutonium dust better than a rotary-kiln type. However, the rotary-kiln type has been used to treat mixed wastes while the screw-type has not. Another disadvantage is that the thermal desorber has not been designed and built to process the required throughput. The use of two parallel desorbers will be necessary to accommodate throughput capacity within current designs.

3.2.3.2 Off-gas Treatment. There are several advantages to using an off-gas treatment system based on granular activated carbon technology. This system is easier to operate and permit than an afterburner and/or scrubber system(s). The carbon can be regenerated for reuse if the radionuclides can be filtered from the off-gas prior to condensation. The carbon system also does not require chemicals to be added and maintained at a proper dosage, and energy requirements are minimal. However, the carbon system will require an oil/water separator to keep any condensed oil from fouling the carbon bed, and processing and disposal of the contaminated carbon will be necessary.

3.2.3.3 Soil Washing. The soil washing system must be specifically designed for SDA soils and TRU contamination. The system may be designed to detect and presort TRU soils, thereby reducing the volume of soil that will be gravimetrically separated. Downstream of the separation process, the system must also detect and reprocess contaminated soils that happen to exit with the

"clean" effluent. Soil washing systems require that influent soil meet certain characteristics (e.g., nonceramic, oil-free). While the process itself is based on simple physical separation, supporting equipment is technologically advanced (e.g., on-line assay units) and therefore prone to expensive repairs. The largest concern, however, lies in the fact that only one full-scale system has been built for separation of plutonium and that it was operated for a limited time. The soils processed at this facility consisted of sands as opposed to the nonhomogeneous basalt and clay soils at the INEL. Significant development may be needed for INEL soils.

3.2.3.4 Low-Level Waste Assay. The on-line assay system allows soil to be automatically and continuously detected and sorted instead of having to manually batch test drums. A disadvantage is that the LLW assay is limited by the precision and accuracy of the detectors and their reliability over time.

3.2.3.5 TRU/Clear. The TRU/Clear system is specifically designed for treating TRU contaminated water and has been demonstrated on a production scale on waste water similar to that expected from the Soils Processing Subsystem. This production scale, however, does not match the throughputs required here, thus necessitating the use of two parallel units. TRU/Clear results in less sludge than iron precipitation processes, and the sludge is in a highly filterable, crystalline form. Special consideration is necessary for choosing a dewatering device that can handle the sludge with minimal maintenance/repair. There will be an advantage if the sludge from the TRU/Clear system can be processed with the TRU soil from the soil washing system. A strong advantage is that the technology uses common wastewater treatment equipment with minor modifications. The technology was patented by DOE, and confidence in the system can be determined by bench-scale tests. TRU/Clear has been demonstrated for several DOE facilities. Testing of the TRU/Clear system will be tied to the testing and requirements of the soil washing system.

3.2.3.6 Solidification. Solidification is a well-established technology and has been proven to be effective for INEL wastes, and automated systems for solidification have been operated. While the technology does not destroy the

toxic waste or eliminate its radioactivity, solidification does yield a waste form that meets LDR requirements and is considered safe for long-term disposal. On the downside, problems such as plugging can occur in the mixing and loading process. Soil characteristics and metals content can vary from batch to batch, thus requiring flexibility in the ratios of soil to cement to water. The treatment is not normally influenced by the radioactivity of the waste, but by other characteristics including ignitability, corrosivity, reactivity, and toxicity. However, worst-case scenarios can be tested in the laboratory to determine boundary conditions. Several solidification processing trains can be run in parallel to ensure production rates are met, which also allows the processing of different soil types simultaneously.

3.2.4 Unit Operations Lead-Time Estimates

A DT&E lead-time schedule for each unit operation of the Soils Processing Subsystem is depicted in Table VII-3-1.

The DT&E of one unit operation will be dependent on the characterized effluent from another unit operation; therefore, this work is assumed to be staggered. The thermal desorption effluent must be compatible with the requirements of the soil washing influent and vice versa. The influent to TRU/Clear is dependent on the characteristics of the soil washing liquid effluent. The solidification process is dependent on the LLW soil output from soil washing. It is further assumed that all the unit operations will be required to operate simultaneously during the demonstration in order to treat all the effluents.

3.2.5 Rough Order of Magnitude Cost Estimates

Table VII-3-2 summarizes the cost for each phase of the life cycle of the Soils Processing Subsystem including research and development, demonstration, production construction, and operation. The costs presented here are understood to be on an ROM. The assumptions used to derive these costs are given in Section 1 and as stated below. Risks associated with the cost estimate are discussed in Section 3.2.2.

Table VII-3-1. DT&E assessment summary for the Soils Processing Subsystem (S-EB-2)

Table VII-3-2. Rough order of magnitude cost estimates (S-EB-2)

Cost Code	Cost Items	Normalized Cost (\$x1000)	Modified Cost (\$x1000)
1.0	Studies and bench scale costs		
1.1	Manpower costs during research	\$1,730	
1.2	Equipment costs	\$910	
1.3	Installation costs	\$370	
1.4	Contingency	\$753	
	Subtotal 1.0	\$3,763	
2.0	Demonstration costs		
2.1	Manpower cost during construction	\$4,490	
2.2	Design cost (30% of 2.5)	\$6,728	
2.3	Inspection cost (7% of 2.5)	\$1,570	
2.4	Project administration (10% of 2.5)	\$2,243	
2.5	Construction cost		
2.5.1	Building structure costs		
2.5.2	Equipment costs		
2.5.3	Indirect (20.9% of 2.5)		
	Subtotal of 2.5	\$22,428	
2.6	Construction management costs (27.8% of 2.5)	\$6,437	
2.7	Contingency	\$10,974	
	Subtotal 2.0	\$54,870	
3.0	Production construction costs		
3.1	Design cost (30% of 3.4)	\$20,698	
3.2	Inspection cost (7% of 3.4)	\$4,830	
3.3	Project administration (10% of 3.4)	\$6,899	
3.4	Construction cost		
3.4.1	Building structure costs	\$35,390	
3.4.2	Equipment costs	\$19,150	
3.4.3	Indirect (20.9% of 3.4)	\$14,453	
	Subtotal of 3.4	\$68,993	
3.5	Construction management costs and construction management reserve (26.5% of 3.4)	\$19,801	
3.6	Contingency (25% of 3.1 through 3.5)	\$30,305	
	Subtotal 3.0	\$151,526	
	Total Capital Cost (1.0, 2.0, and 3.0)	\$210,159	
4.0	Annual operating and maintenance costs		
4.1	Operating costs	\$8,986	
4.2	Utility costs	\$826	
4.3	Material costs	\$5,264	
4.4	Maintenance costs	\$3,305	
4.5	Contingency	\$4,595	
	Subtotal 4.0	\$22,976	
TOTAL	10 Years Operating and Maintenance Costs	\$229,763	

3.2.5.1 Research and Development Cost Assumptions. Testing is needed for soil washing, TRU/Clear, unit operation solidification, and thermal desorption, with each process averaging six months in duration with three people employed per process working eight-hour days. Assumed installation costs are 41% of the equipment costs.

3.2.5.2 Demonstration Cost Assumptions. The following demonstration cost assumptions were made for the Soils Processing Subsystem:

- Assumed one-half full-production staff for seven months
- Demonstration requires one-half of production-scale alpha cell space; assume exterior building preexists
- Design, inspection, and project administration, construction, management, and contingency costs (determined in the same manner as described for production construction costs)
- Demonstration-scale equipment is approximately one-half the scale of the full-production equipment.

3.2.5.3 Production Construction Cost Assumptions. The following production construction cost assumptions were made:

- Assumed 48,350 ft² of LLW processing building
- Assumed 18,470 ft² of alpha cell space with one confinement barrier
- Equipment will be designed as two parallel trains each sized at 50% of the total required capacity

3.2.5.4 Operation Cost Assumptions.

- Assumed staff of 26 people (includes operators, health physicists, a safety engineer, maintenance personnel, and supervisors)

- Assumed 24-hour operation, 240 work days per year, 10-year operation
- Assumed 70% equipment availability
- Propane is used for firing the thermal desorber
- Final soil product is packaged in drums
- Drums used for clean soil product are reusable each year
- Testing program consists of TCLP and more.

3.2.6 System Evaluation Results

3.2.6.1 Identification of Major System Considerations. A soils processing subsystem based on thermal desorption (to remove volatile organics), off-gas treatment (to capture the organics), soil washing (to separate TRU soil, LLW soil, and clean soil), TRU/Clear (to polish the TRU/Clear recycle water), and solidification (to stabilize LLW and metal contaminated soils) is both conceivable and implementable. Most of the unit operations have been demonstrated in a TRU environment (the exception being the thermal desorber). Thermal desorption has been demonstrated in hazardous and LLW environments.

Before further assessment of the subsystem, a greater characterization of the INEL soils will have to be made. Samples that represent the extreme conditions of contamination should be taken. From the information, a profile can be drawn of variations of concentration of individual contaminants in the soil.

It is recommended that the Soils Processing Subsystem be divided into two parallel operating trains of the same size. Although the cost of two trains would be larger than one, there are several advantages to operating two trains. The principle advantages are the reduction of downtime by 50% (assuming one train, capable of handling half the process rate, will always be

on-line) and equipment sizing on a scale that vendors have used and can guarantee.

The Soils Processing Subsystem is designed to treat soils and cannot be used for other matrices. In particular, the thermal desorber is designed to remove organics from soil that will volatilize at or below 450°F. If the soils contain heavy hydrocarbons, this technology may have to be replaced with another technology, such as incineration. The remaining operations of the subsystem are unlikely to be eliminated by such limitations. However, the soil washing operation at Johnson Atoll has been demonstrated primarily with sandy soils, whereas the INEL soil consists of basalt and clay and therefore is more difficult to process.

Interfaces between the unit operations will require a continuous exchange of information between the vendors. The soil washing operation is the heart of the subsystem and will interface with the other operations. It is expected that all interfaces can be made compatible.

The production rate and performance of the subsystem will be limited by two operations: the accuracy of the LLW detectors in the soil washing system and the reliability of the solidification system. A better sense of these indicators may come from the demonstration runs. The production rate requires a substantial amount of LLW soil to be solidified and packaged and clean soil to be packaged. Careful consideration of the materials handling and storage of the processed soils is required. To understand the immensity of the volume, picture the soil being packaged in 55-gal drums. There would be 528 drums of LLW packaged and manifested per day (or 14,800 drums per month) and 384 drums of clean soil packaged per day (or 10,800 drums per month). Many operators have not experienced the quantity of handling and paperwork expected here.

Safety concerns lie with those processes (thermal desorption and soil washing) where plutonium dust could escape from the vessel. A demonstration should help clarify if the risks are acceptable. Another area of concern is the initial unloading of soils and final packaging of TRU soil and LLW soil.

These tasks require the constant presence of operators. These operations should be automated to the greatest extent possible and designed to minimize radioactive emissions. Easy and quick repairs should be kept in mind when designing the placement of the materials handling equipment.

The largest cost component of the system is the thermal desorber followed by the soil washing process. The cost components that will require further examination are the thermal desorber and the solidification/materials handling. The thermal desorber may require alterations in the current design and materials in order to operate in a TRU environment. The cost of the solidification/material handling system will be tied to the architectural design of the building. The bulk of the operating costs are attributed to the packaging required for the soils and, to a lesser extent, the TCLP and metals testing. Material costs for the TRU/Clear system will vary directly with fluctuations in contaminant concentration power requirements for the subsystem. Thermal desorption, off-gas treatment, and soil washing require most of the power needs.

DT&E of the subsystem could be performed in 24 months at best. Because the technologies have been developed for the most part, efforts would be directed toward the specific application of these technologies to the INEL soil. This includes testing each unit operation in meeting its performance requirements. A pilot-scale demonstration could be scheduled so that the unit operations are demonstrated at or close to the same time and, thus, use real influent streams. Ideally, one production-scale train (of the proposed two-train system) would be built for demonstration and, if successful, the second train would be added for full-scale operation. This takes advantage of the fact that one train alone is on the same scale as most of the vendors' pilot-scale equipment. TRU/Clear has been demonstrated for several DOE facilities and is a DOE patented process.

Most of the subsystem can be fabricated and skid-mounted offsite with the exception of the solidification system. The thermal desorber would require the longest fabrication time, and the solidification and packaging systems would take the longest time to install. Startup of the subsystem depends on

the operation of the more complex equipment: the thermal desorber and the soil washing system. Permitting (especially of the off-gas treatment system) can cause delays in startup and should be filed far in advance (one year or more).

3.2.6.2 Performance Measurables Rating. Table VII-3-3 gives a qualitative assessment of the major unit operations of the Soils Processing Subsystem using performance measurables. A score on a scale of 1 to 10 was given to each measurable to indicate the degree of success the unit operation has in meeting that measurable. A score of 10 indicates highly successful.

Table VII-3-3. Rating performance measurables for the Soils Processing Subsystem (S-EB-2)

<u>Measurable</u>	<u>Thermal Desorption with Off-gas Treatment</u>	<u>Soil Washing</u>	<u>Tru/Clear</u>	<u>Solidification</u>	<u>Total</u>
Timeliness	7	9	9	8	33
Dependability	4	6	8	8	26
Completeness	3	5	6	6	20
Risk	5	8	7	6	26
Flexibility	5	7	8	7	27
Cost	7	7	8	7	29
Safety	<u>5</u>	<u>8</u>	<u>8</u>	<u>5</u>	<u>26</u>
Total	36	50	54	47	187

Upon summing the scores, the table shows where the weaker (thermal desorption) and stronger (TRU/Clear) points are in the subsystem.

3.2.7 Summary of Demonstration, Testing, and Evaluation Needs

Table VII-3-4 summarizes the DT&E needs of each major unit operation. All of the technologies have been developed except for the thermal desorption system, which was not intentionally built for processing TRU contaminated waste. The bulk of the DT&E efforts would therefore be directed toward the

Table VII-3-4. DT&E needs for the Soils Processing Subsystem (S-EB-2)

Unit Operation	Technology Development Status	DT&E
Thermal desorption with off-gas treatment	• Full-scale mobile unit	<ul style="list-style-type: none"> • Evaluate the containment of plutonium dust • Determine the extent of radionuclide contamination in off-gas treatment carbon beds
		<ul style="list-style-type: none"> • Evaluate effectiveness of HEPA filters
Soil Washing		<ul style="list-style-type: none"> • Test production rate
		<ul style="list-style-type: none"> • Determine operating temperature
		<ul style="list-style-type: none"> • Evaluate effectiveness of thermal desorption for removing the organics from the specific soil
		<ul style="list-style-type: none"> • Determine effects of radioactivity on current design and modify design
		<ul style="list-style-type: none"> • Produce product compatible with soil washing
		<ul style="list-style-type: none"> • Evaluate which off-gas treatment system to use
	• Full-scale demonstration	<ul style="list-style-type: none"> • Examine interface logistics with other unit operations
		<ul style="list-style-type: none"> • Evaluate the efficiency and accuracy of the LLW assay and sorter
		<ul style="list-style-type: none"> • Test effects of scale up on separation physics
		<ul style="list-style-type: none"> • Evaluate the containment of plutonium dust
		<ul style="list-style-type: none"> • Determine if additives are required
		<ul style="list-style-type: none"> • Determine the extent of volume reduction of TRU soil
		<ul style="list-style-type: none"> • Provide influent requirements to thermal desorption
		<ul style="list-style-type: none"> • Provide wastewater information to TRU/Clear
		<ul style="list-style-type: none"> • Determine the level of detectors required

Table VII-3-4. (continued)

Unit Operation	Technology Development Status	DI&E
TRU/Clear	<ul style="list-style-type: none"> • Full-scale production 	<ul style="list-style-type: none"> • Test effects of scale up on chemistry and residence time • Determine method of dewatering sludge • Establish linkage with soil washing
Solidification	<ul style="list-style-type: none"> • Full-scale mobile unit 	<ul style="list-style-type: none"> • Test production rate • Determine the number of parallel trains to build • Evaluate the layout of equipment and ease of operation and maintenance • Evaluate operator exposure at interface points • Determine variation of constituents in water over time • Determine if additives other than TRU/Clear are required • Characterize sludge effluent • Identify which additive(s) to use • Determine worst-case scenarios and variations in the ratio of additives • Develop automation to keep pace with the production rate

specific application of these technologies to the INEL soil. Other typical needs not listed in the table would include optimization of all the operating variables with the intention of increasing the efficiency of the unit operation.

3.3 RECOMMENDATION FOR THE SUBSYSTEM

The Soils Processing Subsystem presented here is feasible. The weakest point is probably the thermal desorber. Thermal desorption produces an effluent that is more compatible with the soil washing process than the effluent from incineration; however, it is possible that there are hydrocarbons in the Texas Regal Oil (or other sources) that cannot be thermally desorbed. Without a detailed characterization of the extent of contamination in the soil, much of the information presented here (especially the costs) is based solely on engineering judgment. There are a few different designs patented for thermal desorption. The only design tested with radioactive wastes (LLW, not TRU) is a rotary-kiln type. Because the INEL had some reservations about the release of plutonium dust from the rotary-kiln incinerator, it is recommended that a screw-type thermal desorber be used. This type of thermal desorber has not been used in a radioactive environment and will require research to determine the compatibility of design and materials with the TRU soil. The remaining unit operations have been used in cases similar to that at the INEL.

To achieve the required production rate for the subsystem, two parallel trains, each designed at 50% of the production rate (plus 25% safety factor), are recommended. The vendors have manufactured equipment at the 50% scale, but very few have manufactured equipment for the full (100%) production scale of the subsystem. More than two trains for the solidification operation may be required to ensure production rate.

A very large volume of soil (clean and LLW) will have to be packaged and stored. For this study, it was assumed that drums would be used; however, more practical and cost-effective containers should be studied. In addition,

storage facilities will need to be constructed to store the soil for the length of time required during analyses and awaiting disposal. The volume of TRU soil will be small enough not to pose the same concern. At facilities that have solidified and packaged 10 drums or more per hour, a great concern has been the amount of downtime experienced as a result of lengthy repairs. The recommendation here is to have the equipment layout in a manner that facilitates quick and easy repairs. Saving building space results in more costly repairs and possibly greater risks to the operators.

An off-gas system will be required to treat the off-gas from the thermal desorber. If radionuclides can be adequately filtered from the off-gas, then a carbon bed using regenerable carbon would be the most practical method of treatment. If not, other technologies will have to be considered. A dewatering system should be considered for the TRU/Clear sludge.

The soil washing system is the center of the Soils Processing Subsystem. This system has only been tested full-scale once. It is important that the parameters for operating this system be determined early so that the information can be used in the overall subsystem design. Specific testing on INEL soils is critical.

4. LOW-LEVEL WASTE SUBSYSTEM (S-IT-3)

This section describes one of the possible systems for addressing the RWMC remediation. The purpose of the task is to provide a basis for the developing technology requirements and DT&E required to remediate the buried waste in Waste Area Group (WAG) -7 of RWMC. The buried waste includes constituents that make it mixed waste. As a result, RWMC will be remediated under the terms of the Resource Conservation and Recovery Act (RCRA) and CERCLA.

4.1 FUNCTIONAL AND OPERATIONAL REQUIREMENTS

4.1.1 Subsystem Description

LLW sludges are solidified in one of several solidification agents. Combustibles and inerts are processed through a thermal treatment process and the resultant ash is similarly immobilized. Ferrous metals are sized before packaging. Lead is decontaminated in a melting process.

4.1.2 Subsystem Boundaries

The particular system under consideration is a complete LLW waste processing system. It assumes the start is LLW from presort operations in the TRU waste treatment system. The processing system, with the exceptions noted below, sorts the waste, processes it, and packages it for disposal. The study boundary ends at the assayed and packaged waste. Transportation for disposal and disposal itself are not considered.

The following system boundaries indicate nonprocessed and by-product material streams that exit the process.

4.1.2.1 Input Interface. The LLW from the retrieval subsystem is within the boundary of this study. No retrieval steps are within the study boundary.

A second input is the raw material input to the system. No detail beyond acknowledgement of a need for equipment, utilities, and processing raw materials, (e.g., solidification agents) is provided.

4.1.2.2 Output Interfaces. LLW will be separated from TRU waste before processing and will be processed in the LLW subsystem. The outputs from the LLW processing subsystem include packaged LLW, TRU waste, clean water, and clean off-gas.

Because lead is a heavy element included in the TCLP list and there is a substantial amount of lead in the buried waste inventory, it is separated and treated in the LLW processing system. The recovered lead is expected to be decontaminated to the extent that it can be reused in DOE facilities. The recovered lead is an output stream.

The packaged LLW waste is assayed and placed in its transportation package. The boundary of this study is the final assayed waste package.

The thermal treatment process is likely to have a gaseous release as off-gas. This gaseous effluent will be processed to meet the appropriate regulations as a part of this study.

Treated water, of a quality acceptable for process use, will be recovered from the various processing steps. The treated water will be released from the facility.

Ferrous metals will be size-reduced and packaged. The subsystem outputs include metals meeting the LDRs, decontaminated metals for reuse, clean water, and a TRU sludge.

The following list of considerations is given as a reminder that the function and requirements inherent in this list will influence the process design.

- Security

- Work control/personnel support
- Contaminated maintenance
- Noncontaminated maintenance
- Heating, ventilating, and air conditioning (HVAC)-nonprocess
- Fire protection
- Safety (equipment, training)
- Health physics
- Sanitary facilities
- Electrical (including emergency)
- Process control/data logging
- Environmental regulatory reporting/records management
- Criticality control/monitoring
- Radiation instrumentation
- Personnel decontamination
 - Radioactive
 - Hazardous
- Bulk chemical supply/storage
- Storm water runoff control
- Wastewater treatment
 - Hazardous/radioactive
 - Sanitary
- Communications
 - Internal
 - External (public relations)
- Spill or emergency response team
 - Hazardous
 - Radioactive
- Analytical laboratory
- Environmental field sampling team.

4.1.3 Process Functional Diagram

The processing system studied in this task is schematically presented in Figure VII-4-1. The individual components of the system are described below.

DESCRIPTION

DRY LOW LEVEL WASTE SUBSYSTEM WITH
DRY LOW LEVEL WASTE REQUIREMENTS TO
PROCESSED AND CONTAINERIZED, SEPARATE
METALS AND SLUDGE, AND SEPARATE
COMBUSTIBLES, LOOSE MATERIAL.

Open
UDR
LDR
LLW
5sec on
5amp
Solid
Pack
6sec on

Figure VII-4-1. Process functional diagram for the low level Waste Subsystem (5-II-3).

Note: Mass flow balance does not show the input process additives.

4.1.3.1 Open Packages and Sort. LLW waste will be processed through four subsystems. At this point, all packages will be opened remotely in appropriate containment. Each package will be examined visually and using X-ray, and will be directed to either the sludge processing unit operation, the thermal treatment unit operation, the Metals Decontamination/Sizing Subsystem, or the lead treatment unit operation.

4.1.3.2 Land Disposal Restriction Organics Treatment (Sludge). Organic sludges must be thermally treated to meet LDR requirements. Thermal treatment by any of a number of direct or indirect heating methods would be acceptable. The off-gases will contain the organic constituents and will be further treated in a secondary combustion chamber associated with the combustibles incinerator.

4.1.3.2 Secondary Waste Treatment. An off-gas cleanup system will be required to meet RCRA and Clean Air Act effluent requirements. Because of the chlorinated material in the waste, a wet off-gas system is the likely choice, but dry scrubbing may be an alternative.

4.1.3.3 Solidification. Based on test results, a solidification agent will be selected that will immobilize the treated solids to meet the LDR requirements. Cement, sulfur cement, polymers, and bitumen are all candidate solidification agents.

4.1.3.4 Land Disposal Restriction Organics Treatment (Combustibles). An incinerator capable of processing large volumes of combustibles, noncombustibles, and large items will be required. In addition, a very high carbon burnout will be necessary to make the resultant product compatible with the subsequent solidification system. Several candidate incinerator types may be considered in addition to thermal desorption.

4.1.3.5 Land Disposal Restriction Treatment (Lead). Lead will be encapsulated or decontaminated and reused.

4.1.3.6 Sample and Analysis for Land Disposal Restrictions. All processed waste streams will be analyzed to determine if they meet the LDR requirements.

4.1.3.7 Assay and Sort. All packages will be assayed to determine TRU content and other analytical and physical testing dictated by the waste acceptance criteria. It is expected that this LLW processing system will generate some TRU waste, and this final assay will complete the certification necessary for waste destined for geologic disposal.

4.1.3.8 Process Specific Assumptions. The waste composition is derived from *A Brief Analysis and Description of Transuranic Wastes in the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL*, (Arrenhold and Knight, 1991) (see Volume VIII). Additional assumptions are listed below:

- One percent of the waste is lead. Ninety-eight percent of the lead can be recycled after melting.
- The mass of the special items, oversized items, and materials requiring special treatment is assumed to be negligible.
- All sorting operations are assumed to be perfect; that is, no allowance is made for combustibles in the metals or vice versa.
- All sludges are assumed to contain either heavy metals or hazardous organics and will require treatment to meet LDR criteria.
- Combustible contents are 5% ash.
- All combustibles and inerts must be treated to meet LDR disposal requirements.
- The entire scrubber sludge, a concentration of the fine particulate, is TRU waste.

- A fraction of the LLW will become TRU waste when incinerated. The fraction, which converts to TRU, is related to the mass reduction factor of the combustibles and inerts treated in the incinerator.
- Sludges, after thermal desorption and solidification, will remain LLW.
- The solidification process will use a 50% waste formulation to meet LDR requirements.

4.1.4 Facility Description

The facility layout for this subsystem is shown in Figure VII-4-2. This layout is designed for simple movement of material through the facility from waste receipt to packaged waste shipment. Processing lines for sludges and combustibles/inerts run in parallel, with common links at the secondary waste treatment system and solidification. It is expected that some process links will be made in overhead or underfloor connections to allow safe operating and maintenance corridors between the lines.

Depending on relative locations of the LLW system to the processing systems for TRU waste, it may be necessary to incorporate a TRU solidification system for the sludge. This separate solidification system would avoid long transport of the sludge. Because of the volume reduction achieved in the LLW system, some of the packaged waste will be concentrated to TRU. Therefore, the waste shipment facilities for LLW should be collocated with the TRU system shipping area.

4.1.5 Subsystem Design Requirements

4.1.5.1 General Requirements. The waste constituents of the LLW portion of buried waste are described in *A Brief Analysis and Description of Transuranic Waste Disposal in the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL*. (Arrenholz and Knight, 1991). The

processing system shown in Figure VII-4-1 is designed to treat the waste constituents described in that document.

The waste handling and treatment systems will be designed in accordance with applicable regulations. Specifically, RCRA places design conditions on storage and treatment systems, and performance specifications on incinerator and solidification systems. All equipment will be high quality, low-maintenance items to keep personnel exposure as low as reasonably achievable. Remote operations will be used to the greatest extent practicable. The facility design will be compatible with DOE Orders, including the DOE Idaho Architectural Engineering Standard and the DOE General Design Criteria Manual, DOE Order 6430.1A.

The treatment objectives for the remediation concept of the process functional diagram in Figure VII-4-1 include the following:

- Treat LLW sludges by thermal treatment to remove hazardous organics and immobilize the radioactive and heavy metal constituents.
- Treat LLW combustibles by thermal treatment to volume reduce and remove and destroy any organic hazardous constituents. The resulting ash will be solidified to immobilize the radioactive and heavy metal constituents.
- Treat lead by a technology that either allows disposal of the lead in compliance with the TCLP leach test criteria or decontaminates to facilitate recycle.
- Package LLW metal for disposal in a reduced volume state.

4.1.5.2 Unit Operation Design Requirements. The functional and performance requirements of each of the process subsystems are outlined below for Figure VII-4-1. The nominal mass flow rates and equipment sizing information is shown on Figure VII-4-1.

- Open packages/sort: The objective of this unit operation is to remotely separate the waste packages into four categories: sludge, combustibles and inerts, metals (except lead), and lead. The unit operation must provide a means to visually and nonintrusively determine waste package contents. The sorting operation must be capable of achieving 125% for the maximum design capacity of the four separation categories processing systems. The process must provide for fire suppression and an inert atmosphere, if necessary, and must be integrated with the regulatory reporting process.

- LDR organics treatment (sludge): The objective is to thermally remove organic constituents in the sludge stream. The gaseous emissions would be directed to a secondary combustion chamber. The system must have the following characteristics:
 - Has a maximum design capacity of 125% of the nominal throughput and accept items as large as 24 in.
 - Reduces the organic content of the sludges to levels below 1 ppm of nonvolatile compounds such as polychlorinated biphenyl
 - May use direct or indirect heating
 - May provide for inert gas or no inlet air operation to reduce the off-gas required for further processing
 - Is maintainable such that an overall on-line operating factor of 70% be achieved over a one-year period
 - Construction materials of the waste contacting surfaces in the heating section are compatible with chlorinated wastes and alkali metals
 - Includes provisions for cooling the output material

- Provides a fully integrated process control/data acquisition/regulatory reporting system.
- Solidification: The objective is to solidify the treated organic and cemented sludges and the untreated inorganic sludges to immobilize the radioactive and heavy metal constituents. There is also a lead slag solidification in the lead LDR treatment unit operation. The system must provide for the following:
 - Accommodates variable solidification formulations, depending on the waste to meet the TCLP leach test criteria
 - Has a capacity design maximum throughput of 125% of the sludge processing subsystems and the combustibles/inerts processing subsystems
 - Accommodates radiation monitoring instrumentation
 - Is integrated with the regulatory reporting system
 - Includes system clean out provisions.
- LDR organics treatment (combustibles/inerts): The objective is to oxidize organic constituents in the combustibles stream. The following are required:
 - Accepts drums and waste boxes as input.
 - Has a maximum design capacity of 125% of the nominal throughput.
 - May use an auxiliary fuel.
 - Provides for high carbon burnout. Therefore, a minimum solids retention time of 90 minutes is required.

- Is maintainable such that an overall on-line operating factor of 70% is achieved over a one-year period.
- Operates at a temperature/residence time condition that reduces residual organic solvent levels to less than 1 ppm.
- Secondary chamber has provisions for accepting off-gas from the thermal desorption system.
- Secondary chamber has a gaseous residence time of two seconds at 2000°F.
- Construction materials of the waste contacting surfaces must be compatible with chlorinated wastes and alkali metals.
- Feed system has provisions for inerting atmosphere and fire suppression.
- Ash handling system is compatible with the downstream ash solidification system.
- Provides a fully integrated process control/data acquisition/regulatory reporting system.
- Feed system provides for control of fugitive emissions.
- Process is integrated with the gaseous emission monitoring system.
- Provides for ash cooling.
- Secondary waste treatment: The objective is to clean the gaseous emissions from the thermal process to comply with applicable regulatory requirements. The system must have the following:

- System is capable of removing 99% of HCl from the gas stream
- May use any combination of wet/dry systems that achieves the treatment standards
- Accepts the maximum expected off-gas from both LDR organics treatment processes
- Reduces particulate concentrations of the off-gas to less than 0.08 g/dry standard cubic feet (DSCF) and radionuclide emissions to DOE standards
- Has redundant power supplies to ensure continuous operation.
- LDR treatment (lead): The objective is to encapsulate the lead or decontaminate it to be reused outside of this project. The following are required:
 - Process will be designed at a rate of 125% of the nominal processing rate
 - The process can be batch operated, allowing storage until adequate material is accumulated for processing
 - The slag is solidified in a manner that meets TCLP criteria.
- Package (metals): The objective is to size-reduce and package LLW metal in compact forms. The process must perform the following:
 - Accept the waste metal as sorted from other waste
 - Facilitate safe (remote or manual) size-reduction of the metal for efficient packaging
 - Allow for package exterior cleaning and decontamination.

- Package (organics and sludge treatment): The objective is to package the fully treated waste forms for transportation and disposal. The system must perform the following:
 - Accept the solidified material from the various solidification systems
 - Ensure a dense package filling
 - Allow for package exterior cleaning and decontamination for handling.
- Sample and analysis for LDR: The objective is to determine the content of the waste packages. This will also include other regulatory requirements for transportation and disposal. The process is required to sample packages for compliance with LDR disposal requirements and analyze the sample according to standard techniques.
- Assay and sort: The objective is to determine the TRU content of the waste packages, as well as other weight and radionuclide content information required for transportation and disposal. The process must identify TRU content and fissionable material content.

4.2 SYSTEM ASSESSMENT

4.2.1 Current Status of Unit Operations

4.2.1.1 Open Packages/Sort. Commercial systems that open packages and sort waste are not currently available. Waste characteristics such as size, weight, and physical form are all important to the design of a sorting system. The Scientific Ecology Group (SEG) at Oak Ridge, Tennessee developed a revolving sorting table and a shaker table for hand sorting feed for a 725 kg/h LLW incinerator. The Solid Waste Certification Facility at LANL will

be used for packaging, sorting, and certifying WIPP-bound TRU waste. This facility consists of nine interconnected glove boxes for various operations. The SEG sorting system is an operating full-scale facility, and the LANL facility will be operational in 1991. The SEG LLW sorting system is used for combustible waste and does not handle large objects. The LANL system sorts dry waste and can accept some solid objects. It should be noted that real-time radiography (RTR) is being routinely used as a waste characterization tool and could be applied to sorting waste packages. DOE sites, such as the INEL and the Rocky Flats Plant, routinely use this technique on a full-scale basis for analyzing the contents of TRU waste drums. The process has not yet been demonstrated for waste boxes.

Remote operations using through-the-wall and crane mounted manipulators are commonly used in the nuclear industry. Remote tooling to handle and open waste containers requires engineering to apply these tools to the specific task. Because waste needs to be characterized before thermal treatment or solidification, remote operations can be designed to handle containers, open containers, remove waste from containers (and from waste bags where process knowledge is inadequate), and repackage or prepare waste for treatment. With the possible exception of certain chemical analyses (i.e., organic sludges), these are engineering challenges rather than research and development requirements.

4.2.1.2 Land Disposal Restriction Treatment of Lead. Lead melting equipment and facilities exist commercially and may be adaptable as slagging processes. Contaminated metals melting was demonstrated at the Waste Experimental Reduction Facility (WERF) at the INEL. A lead melting pot is part of this process. Depending on the end result required, this process may be somewhat sensitive to materials other than lead being included in the melt. Also, lead shot (in bags) will have to be separated from the bags, and large pieces may have to be presized. Lead melting pots of various sizes can be operated in parallel, resulting in a flexible process capacity. Nuclide partitioning into slag has been demonstrated for other metals and although expected, remains to be demonstrated for lead.

Cementitious solidification and vitrification processes are operational, but specific demonstrations for solidifying lead slag do not appear to have been performed. Depending on the solidification process used, other metals in the waste stream can have an adverse effect on solidification. This process will require demonstration and possibly some research and development preceding demonstration before it can become operational.

4.2.1.3 Land Disposal Restriction Organics Treatment for Sludges.

Microwave and indirect heating devices for removing organics from soil are commercially available and operational. Microwave heating of sludges is being evaluated at the Rocky Flats Plant and at Oak Ridge National Laboratory (ORNL). Although being evaluated for solidification, the technology could be applied to desorption of organics from sludges. Decontamination has been reported of various soils that contained PCBs, furans, and dioxins, and this process could be applied to sludges. This demonstration was performed in an externally fired calciner pilot plant. Incineration can also be used to eliminate organics from sludges.

4.2.1.4 Land Disposal Restriction Organics Treatment for Combustibles.

Incineration is highly developed in the hazardous waste industry. In addition, over 80 radioactive waste incinerators have been operated since 1949. Since 1976, LANL has demonstrated a controlled-air incinerator for reducing TRU waste volume. Currently, the incinerator is shut down pending approval of National Environmental Policy Act of 1969 (NEPA) documentation. Other incinerators for LLW have been demonstrated at WERF at the INEL, the K-25 facility at ORNL and the SEG at Oak Ridge, Tennessee. Europe and Japan make extensive use of incineration for reducing radioactive waste volume. A recent tabulation shows 18 operating radioactive waste incinerators in Japan.

Incinerator design is influenced by both the combustible and noncombustible fractions of the feed, as are off-gas and ash handling systems. In municipal solid waste applications, waste compositions similar to TRU waste have been treated. No radioactive waste incinerator has been tested using the buried TRU waste mixture.

Other possible incineration technologies include the fluidized bed incinerators used extensively at commercial facilities, pyrolysis units that are used in other countries but not applied at DOE facilities, and the rotary kiln, which is commonly used in commercial applications and is particularly suited for large bulk, unsorted wastes.

Thermal treatment systems do not need significant research and development at this time. However, it is expected that engineering development and scaleup will be needed to apply incineration technology to the unique TRU and LLW wastes.

4.2.1.5 Secondary Waste Treatment. Almost all the radioactive waste incinerators worldwide have had off-gas treatment systems to control radioactive or other hazardous material releases, including TRU radionuclides. The type of off-gas system is determined by the amount and type of particulates and halogenated plastics in the feed material. Historically, wet off-gas systems have been used, but newer applications are using dry scrubbing techniques. The latter employ sintered metal filters, high-efficiency particulate air (HEPA) filtration, and cooling dilution air. Off-gas systems, without the HEPA filters employed for radioactive applications, have been demonstrated on a large scale. Radioactive waste incinerators use HEPA filters for final treatment, which are not commonly used on hazardous waste systems. Additionally, the buried waste combination of alkali sludges and chlorinated wastes is unique. Factors such as these require careful design of the off-gas system to remove acid gases and trap fine particulates.

4.2.1.6 Solidification of Sludges and Combustible Ash. The cementation of TRU sludges is a proven technology and has been operationally demonstrated at the Rocky Flats Plant. Other solidification operations exist in stationary and mobile form for a variety of wastes. Cementation is the predominant solidification technique being used. Bitumen solidification is being used for processing boric acid concentrates, sodium sulfate concentrates, and spent ion exchange resins from commercial nuclear power plants. Incinerator ash from the INEL WERF incinerator is cemented and meets TCLP requirements. A bitumen solidification process developed and demonstrated in France by the French

Atomic Energy Commission has been used for processing French and United States power plant wastes and French military wastes. The Transportable Volume Reduction and Solidification System (TVR-III) has been used since 1975 to solidify commercial nuclear power plant wastes in the United States.

Cementation and bitumen solidification processes, although operational, should be verified by demonstration with a broader range of ash compositions to ensure they can meet the LDR requirements. The formulation of cements for longevity is sensitive to waste characteristics and should be specifically demonstrated for the waste characteristics in question.

4.2.1.7 Assay. Assay systems, developed and demonstrated at LANL, are currently operational. The technology consists of a combined passive and active neutron approach and is proven for assaying drums of TRU waste and to a lesser extent boxes of waste. This assay technique has been in use since 1987 and is currently in full-scale operation. Two major DOE sites that routinely use the technique are the INEL and the Rocky Flats Plant. The INEL SWEPP facility uses the assay system to determine whether waste is LLW or TRU by determining the fissile content of drums as well as to certify waste to the WIPP Waste Acceptance Criteria. At the Rocky Flats Plant, both drums and boxes are assayed for fissile content. Waste characteristics may significantly affect the operation. The low radiation levels emitted from contact-handled TRU waste are not expected to have any substantial effect on assay readings.

4.2.1.8 Sample and Analysis. Radioactive and hazardous chemical constituent sampling and analysis facilities exist commercially and within the DOE complex. Techniques are well-developed, and no further discussions of this unit operation are required.

A summary of the current status of unit operations for this waste treatment is provided in Table VII-4-1.

Table VII-4-1. DT&E needs for the Low-Level Waste Subsystem (S-II-3)

Unit Operation	Technology Development Status	DT&E
Open packages and sort	<ul style="list-style-type: none"> Individual operations available 	<ul style="list-style-type: none"> Integrated systems demonstrations
LDR treatment of lead	<ul style="list-style-type: none"> Lead melting equipment available Nuclide partitioning from other metals has been demonstrated 	<ul style="list-style-type: none"> Demonstration of nuclide partitioning into lead slag
LDR treatment of sludges	<ul style="list-style-type: none"> Microwave and indirect heating devices available Tests being conducted at the Rocky Flats Plant and ORNL Incineration well-developed 	<ul style="list-style-type: none"> Demonstration of effectiveness for eliminating volatile organics using microwave or indirect heating devices
LDR treatment of combustibles	<ul style="list-style-type: none"> Incineration technology well-developed and commercially available 	<ul style="list-style-type: none"> Engineering development and scaleup Test and evaluation
Secondary waste treatment	<ul style="list-style-type: none"> Off-gas systems well-developed and commercially available 	<ul style="list-style-type: none"> Demonstration of effectiveness for specific effluents
Solidification of sludges and ash	<ul style="list-style-type: none"> Solidification technologies being used for nuclear wastes 	<ul style="list-style-type: none"> Development of formulations for specific waste forms

4.2.2 Program Implementation Risks

The identification of programmatic risks associated with implementing the waste treatment concepts described in Section 4.1 and the program requirements documents (PRDs) are important to future selection decisions. The cumulative technical, safety, cost, and schedule estimating risks of the individual unit operations that comprise each waste treatment system determine that system's programmatic risk.

In this preliminary risk analysis, the following definitions of the risk parameters were used:

- Technical and performance risk--Probability of failure to meet processing requirements
- Safety risk--Consequences of failure
- Cost risk--The ability to reasonably estimate cost
- Schedule--The ability to reasonably estimate the schedule.

On the basis of these definitions, the risks associated with each unit operation for each waste treatment system were considered. This was done by applying the knowledge of experienced personnel and converting this knowledge into a ranking of low, medium, or high risk for each risk parameter. In general, a low rank implies that the unit operation could be implemented now with virtually no risk. Assignment of medium rank to a unit operation meant that although the implementation of the unit operation was generally feasible, certain aspects of implementation still needed to be resolved. If a unit operation was assigned a high rank, then considerable uncertainty exists regarding needed research and development and the ability to estimate costs and schedules.

For the most part, this subsystem is comprised of low to medium risk unit operations. However, higher risks are associated with the ability to estimate

the cost of the thermal treatment off-gas system and the ability to estimate schedules for the implementation of the incinerator, off-gas system, and solidification units. Therefore, this waste treatment system ranks as a medium risk for successful implementation.

4.2.2.1 Technical and Performance Risks. Although partitioning of radionuclides into metal slag has been demonstrated, further demonstration of this process for lead treatment is required. The development status of desorbers suggests that some additional development will be required when the characteristics of the LLW LDR constituents are firmly identified. Off-gas systems are sensitive to the incinerator feed material and need to be designed and demonstrated for the specific wastes being treated. Solidification processes are also sensitive to the waste being processed and require further demonstration. There are also known operational problems associated with the off-gas and solidification processes. Overall, the risk is believed to be in the moderate category.

4.2.2.2 Safety Risks. The nature of thermal treatment processes requires that their operational safety, as defined for this study, is ensured by extraordinary means relative to other more benign waste treatment operations. Off-gas systems fall into a similar category because their failure can have significant consequences. However, because of extensive experience in applying processing systems to LLW, the risk associated with identification and mitigation of safety concerns is believed to be low.

4.2.2.3 Institutional Objectives. Because the subsystem uses an incinerator, the public acceptance is considered to be low. Therefore, the institutional risk is high.

4.2.2.4 Cost Risks. The cost estimating challenges noted above stem from the regulatory uncertainties associated with the design and operation of off-gas systems. Additionally, lead treatment systems, solidification processes, and desorbers will have some development requirements, making the costs of these systems somewhat more difficult to estimate. The overall cost risk is believed to be moderate.

4.2.2.5 Schedule Risks. The schedule estimating uncertainties are the result of regulatory unknowns pertaining to the incineration, off-gas, and solidification systems. The additional development work that may be required for lead treatment and desorbers also affects the ability to estimate their implementation schedules. The rankings attached to the unit operations of the Low-Level Waste Processing Subsystem are provided in Table VII-4-2. Based on this table, the overall schedule risk is believed to be moderate.

4.2.3 Unit Operations Pro and Con Analysis

Each candidate process is qualitatively measured against the eight criteria. The maximum score possible for any process measured on any evaluation criteria is 10. In some cases, even the best alternative is scored less than 10. Each of the criteria is given equal weight, so a simple summation of the scores assigned to a candidate process determines the overall score. This score, when compared to the total score of the other candidate processes, determines the selected process. The criteria are timeliness, availability, completeness, risk, flexibility, cost, safety and waste reduction.

4.2.3.1 Open Packages and Sort Packages. Two basic processes were considered: remote and contact. The reference systems for this analysis are the manual sorting systems available for LLW at SEG, the glove box sorting line installed at LANL, and the previous drum opening experience at the Rocky Flats Plant. Remote assay equipment is in use at several DOE facilities, including the Stored Waste Examination Pilot Plant (SWEPP). Although the remote handling of the packages after assay has not been demonstrated, it is assumed that this would be a simple application of available remote equipment. Table VII-4-3 gives an analysis of the pros and cons of this system.

This analysis favors the remote process for determining the contents of a package before assigning it to the subsequent waste treatment process. Although the remote process system does present increased technical risk and is somewhat less flexible than manual sorting, the safety concerns of manual

Table VII-4-2. Risk rankings (S-IT-3)

<u>Technical and Unit Operation</u>	<u>Performance^a</u>	<u>Safety^a</u>	<u>Cost^a</u>	<u>Schedule^a</u>
Sorting	L	L	L	L
LDR treatment (lead)	M	L	M	M
LDR treatment (sludge)	M	L	M	M
LDR treatment (combustibles)	L	M	L	H
Secondary waste treatment	M	M	H	H
Solidification	M	L	M	H
Assay and sort	L	L	L	L

a. L = low
M = medium
H = high

Table VII-4-3. Open packages and sort packages analysis

	<u>Score</u>	
	<u>Remote</u>	<u>Contact</u>
Timeliness	10	10
Availability	7	10
Completeness	10	7
Risk	5	5
Flexibility	7	6
Cost	10	10
Safety	10	0
Waste reduction	NA	NA
Total	59	48

waste handling and the problems of the inability for dealing with highly radioactive packages are overriding.

4.2.3.2 Land Disposal Restriction Treatment (Lead). Two technologies have been proposed for lead treatment, macroencapsulation, and decontamination by melting in the presence of a slagging agent. The known encapsulation techniques will not meet the TCLP criteria when the sample is crushed, as the test requires. It is known that some successful development work was carried out on lead melting at the INEL. On this basis, there will be no scoring because only one candidate process is expected to meet the regulatory criteria. An analysis of this system is given in Table VII-4-4.

4.2.3.3 Land Disposal Restriction Organics Treatment (Sludge). Two processes were considered: thermal desorber and incineration.

Thermal desorption involves the thermal heating of the sludges in an oxygen deficient environment. The organics are either directly volatilized or decomposed into light organics and then volatilized. Both indirectly heated systems and microwave systems have been tested on a pilot-scale. Incineration of the sludges directly destroys the organics in a high temperature oxidizing environment. Many candidate incinerator types could be used for this task, including fluidized bed, rotary kiln, rotary hearth, and molten salt. Table VII-4-5 gives an analysis of these processes.

Both processes address the problem well. In the scoring, the thermal desorber was downgraded because of its pilot-plant status. However, the direct application of incineration to these light materials could cause extraordinary requirements on the off-gas system, and the higher temperatures could cause other product melting problems. Therefore, the incinerator was downgraded more on the safety aspects. Because of the desire for the SDS to consider some research stage unit operations and the closeness of the scores of these alternatives, thermal desorption will be the technology of choice for this application.

Table VII-4-4. Land disposal restriction treatment analysis

	<u>Score</u>
Timeliness	10
Availability	8
Completeness	10
Risk	7
Flexibility	10
Cost	7
Safety	9
Waste reduction	<u>10</u>
Total	71

Table VII-4-5. Land disposal restriction organic treatment (for sludges) analysis

	<u>Score</u>	
	<u>Thermal Desorber</u>	<u>Incinerator</u>
Timeliness	10	10
Availability	7	10
Completeness	8	8
Risk	8	10
Flexibility	7	7
Cost	7	7
Safety	1	5
Waste reduction	<u>10</u>	<u>10</u>
Total	58	67

4.2.3.4 Land Disposal Restriction Organics Treatment (Combustibles and Loose Material). Two processes were considered: incineration (many options) and biological treatment.

Incineration of LLW is currently being done at the INEL using the WERF controlled air incinerator and at the commercial SEG facility at ORNL.

Incineration of radioactive waste is also carried out at numerous facilities abroad. Biological treatment has been used in lieu of incineration in some hazardous waste applications. However, these applications are generally in oil-contaminated soil. No biological treatment of solid waste with widely varying organics contaminants was identified. In fact, it is unlikely, with the current state of biological treatment systems, that such a treatment is possible. An analysis of these processes is given in Table VII-4-6.

Biological treatment is inferior to incineration for almost all of the criteria. Safety is an aspect in which biological treatment may be superior, but even that is not ensured.

4.2.3.5 Secondary Waste Treatment. The off-gases from the incineration process must be treated to remove acid gases and particulate matter. Two options are commonly available: wet and dry processes. With the expected amount of acid gases generated by the chlorinated wastes, a wet system (or semidry) is the only option that will meet regulatory requirements. Because wet and semidry processes are similar in chemical and contact mechanisms, no pro/con analysis is warranted. Table VII-4-7 gives an analysis of this process.

4.2.3.6 Solidification. Four processes were considered: cement, polymer, sulfur cement, and asphalt.

Several DOE facilities use waste cementation processes and some have demonstrated compliance with the TCLP test requirements. Sulfur cement is a polymer that has shown some promise of solidification in more favorable ratios than Portland cement. Polymeric waste solidification was evaluated for use in the commercial nuclear industry, but no current application is known. Asphalt solidification was routinely used in Europe but has not found favor in the U.S. because of safety considerations. There was no indication of an ability for asphalt to pass TCLP testing. Table VII-4-8 gives an analysis of this process.

Table VII-4-6. Land disposal restriction organics treatment (combustibles and loose material) analysis

	<u>Score</u>	
	<u>Incineration</u>	<u>Biological</u>
Timeliness	10	4
Availability	10	2
Completeness	8	3
Risk	10	3
Flexibility	10	3
Cost	7	6
Safety	5	10
Waste reduction	<u>10</u>	<u>5</u>
Total	70	36

Table VII-4-7. Secondary waste treatment analysis

	<u>Score</u>
Timeliness	10
Availability	6
Completeness	7
Risk	8
Flexibility	7
Cost	4
Safety	7
Waste reduction	<u>NA</u>
Total	49

Table VII-4-8. Solidification analysis

	Score			
	<u>Cement</u>	<u>Polymer</u>	<u>Sulfur Cement</u>	<u>Asphalt</u>
Timeliness	10	10	10	10
Availability	10	10	8	10
Completeness	8	8	8	8
Risk	8	6	10	4
Flexibility	8	8	8	8
Cost	6	6	6	6
Safety	10	8	8	2
Waste reduction	<u>8</u>	<u>8</u>	<u>10</u>	<u>8</u>
Total	68	64	68	56

In this situation, sulfur cement and Portland cement received the highest scores. The state of development of Portland cement does not quite overcome the apparent process benefits of sulfur cement. For costing purposes, Portland cement will be assumed, but it should be remembered that sulfur cement is nearly an equivalent technical choice.

4.2.3.7 Assay. The assay process at this point is to identify waste that has been concentrated to TRU by the volume reduction process. The unit is a straightforward application of assay equipment of the type used at SWEPP, and no options are proposed.

4.2.4 Unit Operations Lead-Time Estimates

An ROM estimate was made of the effect that DT&E requirements have on unit operation lead-times. Table VII-4-9 depicts these lead-times for each unit operation.

4.2.5 Rough Order of Magnitude Cost Estimates

This section presents the various categories of cost estimates for the following: DT&E, capital costs, and operations. Table VII-4-10 gives the estimated breakdown for the Low-Level Waste Subsystem (S-IT-3).

4.2.5.1 Demonstration, Testing, and Evaluation Costs. The estimates are based on the lead-time estimates in the previous section. The lead-time estimates were developed on a unit operation-by-unit operation basis allowing for DT&E periods. Demonstration projects were assumed to be nonradioactive production-scale tests of complete unit operations or combinations of unit operations.

Only the lead treatment unit operation requires more basic DT&E effort. This effort would identify slagging agents and slagging agent solidification formulations for this process. Because the process is relatively small, it is expected that the DT&E costs would be low. Only two of the remaining unit operations were judged to require DT&E. The thermal treatment system for sludge was judged to require waste specific demonstration on a small pilot plant to ensure that adequate organics destruction could be expected. The thermal treatment system for combustibles was assumed to require some development to refine the design for controlling particulate material, to develop a reliable seal design, and to develop reliable solids handling systems meeting operations criteria. Solidification testing for the specific wastes would be necessary to ensure compliance with the TCLP test under widely varying waste recipes.

Table VII-4-10. Rough order of magnitude cost estimates (S-IT-3)

Cost Code	Cost Items	Normalized Cost (\$x1000)	Modified Cost (\$x1000)
1.0	Studies and bench scale costs		
1.1	Manpower costs during research	\$6,500	
1.2	Equipment costs	\$880	
1.3	Installation costs	\$3,500	
1.4	Contingency	\$2,720	
	Subtotal 1.0	\$13,600	
2.0	Demonstration costs		
2.1	Manpower cost during construction	\$0	
2.2	Design cost (30% of 2.5)	\$2,998	
2.3	Inspection cost (7% of 2.5)	\$699	
2.4	Project administration (10% of 2.5)	\$999	
2.5	Construction cost		
2.5.1	Building structure costs		
2.5.2	Equipment costs		
2.5.3	Indirect (20.9% of 2.5)		
	Subtotal of 2.5	\$9,992	
2.6	Construction management costs (27.8% of 2.5)	\$2,868	
2.7	Contingency	\$4,389	
	Subtotal 2.0	\$21,945	
3.0	Production construction costs		
3.1	Design cost (30% of 3.4)	\$21,383	
3.2	Inspection cost (7% of 3.4)	\$4,989	
3.3	Project administration (10% of 3.4)	\$7,128	
3.4	Construction cost		
3.4.1	Building structure costs	\$21,050	
3.4.2	Equipment costs	\$35,289	
3.4.3	Indirect (20.9% of 3.4)	\$14,931	
	Subtotal of 3.4	\$71,275	
3.5	Construction management costs and construction management reserve (26.5% of 3.4)	\$20,456	
3.6	Contingency (25% of 3.1 through 3.5)	\$31,308	
	Subtotal 3.0	\$156,538	
	Total Capital Cost (1.0, 2.0, and 3.0)	\$192,083	
4.0	Annual operating and maintenance costs		
4.1	Operating costs	\$7,983	
4.2	Utility costs	\$76	
4.3	Material costs	\$179	
4.4	Maintenance costs	\$2,222	
4.5	Contingency	\$2,615	
	Subtotal 4.0	\$13,075	
TOTAL	10 Years Operating and Maintenance Costs	\$130,750	

The following assumptions were used to arrive at a DT&E cost estimate:

- A laboratory program would be required to establish the distribution coefficients for lead decontamination and to select the appropriate slagging agents. The resulting slag would then be combined with solidification agents to ensure leach test compliance. A similar effort would be required on a small pilot-plant scale to ensure that typical industrial equipment can be expected to perform as the bench-scale tests.
- The drum dumper would be assembled from commonly available drum handling systems, but a mechanical development test would be required to ensure that the designed system would operate on the sludge drums, irrespective of the condition of the contents. The effort would involve a group of 10 engineers and pilot-plant operators for a short period.
- The organics treatment system should be tested on a pilot-plant scale to ensure that simulated waste could be treated to a residual organics level satisfactory to regulatory bodies. The test could be carried out in a contract pilot plant, but for estimating purposes it is assumed that a pilot plant can be simply assembled. The operation of the pilot plant will entail a complete year of staff to identify problems and corrections. The equipment cost can be kept relatively low. However, it is expected that sampling and analytical costs will be high. A few hundred samples can be expected to be taken in the test period and at costs as high as \$2000 per sample. As a thermal treatment system, it would have to be run around the clock, and a team of 15 operators and engineers would be required to devise tests, run the system, and make modifications as necessary.
- The major demonstration activities associated with the thermal treatment of combustible materials are associated with the testing of reliable, nondusting handling systems for the feed and ash. It

is expected that the confirmation of the incinerator seals will be required to ensure that the final system will be acceptable in the TRU contaminated waste processing service. These mechanical mockups will require considerable equipment and design cost, but limited operations cost. A staff of 12 engineers and operators would be necessary for these tests.

- The use of solidification agents to immobilize waste is reasonably well developed. However, a laboratory program is required to confirm the exact formulations to meet the leach test criteria. The laboratory effort is relatively small, but analytical costs are assumed to be high. This effort would require a staff of three chemists and technicians. The one-year program recognizes the typical delays in analytical results.

The following costing assumptions were made:

- The engineering of this small equipment will equal the procured equipment cost.
- The average fully-loaded cost for manpower (all grades) is \$50/h.

Several of the mechanical systems, such as "open packages and sort," require demonstration in a nonradioactive mockup system. Both thermal treatment systems, along with associated solids handling equipment, should be demonstrated in a nonradioactive environment. Unless suitable portable systems can be identified for use in testing, these demonstration tests are expected to require substantial design, setup, and operation costs. The capital cost assumptions were as follows:

- A 1/10 full-scale nonradioactive development system would be constructed in an existing building space, which requires only minor building modifications

- The thermal treatment desorber and incineration systems would have to be mocked up.

4.2.5.2 Capital Costs. The capital cost estimates were developed using the following methodology:

- Equipment costs were obtained from four sources: vendor estimates of these components or similar components, engineering estimates, handbook and literature information, and file information on purchased equipment.
- Building costs were estimated from the layout drawings developed in the F&OR section. These layouts and the areas calculated in the layouts were used to determine moderate hazard areas and alpha containment areas. Building space costs were estimated per assumptions given in Section 1.
- Equipment costs for unit operations of similar capacity were scaled according to the $X^{0.6}$ rule, where X equals the capacity to correct costs for the appropriate capacity.
- Standard handbook information was used to scale the purchased equipment costs to installed equipment costs. These factors include installation, field engineering, and fees. For facilities of this type, the overall factor assumed was approximately four.

Other applicable assumptions include the following:

- The costs of offices and nonprocessing areas of the facility were not calculated.
- Stainless steel equipment was generally costed to allow for easy decontamination and maintenance, even when materials considerations indicated cheaper construction would be

appropriate. This generally resulted in assuming the most expensive equipment or factors.

4.2.5.3 Operating Costs. Four subcategories of costs were included as operating costs and included operating labor, maintenance (5% of equipment cost), utilities (estimated from mass and energy balance information), and raw material costs (such as Portland cement). Cost estimates are summarized in Table VII-4-10.

4.2.6 Subsystem Evaluation Results

This section provides an overall evaluation of the subsystem, including any clear advantages or disadvantages, a subjective numerical measure of overall efficiency of the subsystem's summary of DT&E needs, and an overall recommendation regarding the implementation of the subsystem within the context of this very preliminary study.

4.2.6.1 Identification of Major Considerations. For the most part, the major unit operations within this subsystem are either developed and demonstrated or can probably be fully demonstrated within two to four years. It appears that basic research will only be required for LDR treatment of lead, assuming that this also entails elimination of radionuclides. This will include investigating the elimination of hazardous constituents and radionuclide partitioning into the lead slag and evaluating slag solidification/immobilization formulations and techniques. Some development will be required for LDR treatment of sludges and combustibles and for solidification of the various treated waste products. The integration of the unit operations into a viable waste treatment facility seems to be well within the capability of the architect/engineering and chemical plants industries to perform.

By presorting LLW before processing, the lower volume of waste processed by the TRU waste processing systems minimizes the amount of waste being shipped to the TRU waste geologic repository. The facility can also be designed on the basis of the LLW, rather than alpha confinement criteria. A

disadvantage identified during the course of the study pertains to the effect of changing regulatory climates on the thermal treatment, off-gas, and solidification operations. The tendency toward more stringent requirements may produce regulatory uncertainties that must be recognized during the facility planning stage. An inherent disadvantage of a separate LLW subsystem is the need for additional equipment and building space, apart from that needed for other waste processing needs.

4.2.6.2 Performance Measurables Rating. Each of the systems and subsystems studied were evaluated for comparison with other systems. This was accomplished using a subjective numerical ranking process. Each unit operation was given a score of one to ten, with ten being the best, for the following criteria: timeliness, availability, completeness, risk, flexibility, cost, safety, and waste reduction.

Table VII-4-11 shows the scores that were assigned to each unit operation and the sum of these scores. Because each subsystem studied has a different number of unit operations, the total scores were normalized by using the average unit operations score. On this basis, the score for this subsystem is 66.

Table VII-4-11. Rating performance measurables for the Low-Level Waste Processing Subsystem (S-IT-3)

Measurable	Open Packages and Sort	LDR Treatment (lead)	LDR Organic Treatment (sludges)	LDR Organic Treatment (combustibles)	Secondary Waste Treatment	Solidification	Assay	Total
Timeliness	10	10	10	10	10	10	10	70
Availability	7	8	7	10	6	10	10	58
Completeness	10	10	8	8	7	8	10	61
Risk	5	7	8	10	8	8	10	56
Flexibility	7	10	7	10	7	8	10	59
Cost	10	7	7	7	4	6	10	51
Safety	10	9	10	5	7	10	10	61
Waste reduction	NA	10	10	10	NA	8	NA	38
Totals	59	71	67	70	49	68	70	454

5. RETRIEVAL SUBSYSTEM (S-BE-4)

The Retrieval Subsystem (S-BE-4), includes all facilities, processes, equipment, and ancillary components required for the retrieval, sorting, and packaging of the TRU waste with the peripheral soil buried at RWMC. The subsystem packages the waste and ships it to a waste receiving, processing, and packaging facility.

5.1 FUNCTIONAL AND OPERATIONAL REQUIREMENTS

5.1.1 Subsystem Description

The Retrieval Subsystem (S-BE-4), capable of movement and positioning over the buried waste, is comprised of several unit operations. The subsystem characterizes, retrieves, gross sorts, and packages the material for transportation to the Waste Receiving, Processing, and Packaging Facility, the Soils Processing Subsystem, and the Metal Decontamination and Sizing Subsystem. The retrieval operation is accomplished in an airtight alpha environmental enclosure. The four major output streams from the Retrieval Subsystem are peripheral soil, bulk metal, loose material, and intact containers.

The subsystem includes excavation equipment, which removes the topsoil cover placed on the buried waste trenches or pits. The excavated cover (peripheral soil), which may contain low concentrations of TRU material, is placed in reusable transportation containers and shipped to the Soils Processing Subsystem (S-EB-2) for treatment and disposal.

After removing the cover soil, the Retrieval Subsystem scans the area of the trench under consideration. The scanning operation identifies and prepares a location map of buried large objects and other wastes requiring special handling. The information obtained from the scanning operation is used to plan the retrieval operation.

Remotely-operated excavation tools are provided to extract special waste such as high radiation objects, large discarded components, and structural pieces. After retrieval, special waste is packaged and placed in an enclosed interim storage area near the trench. Final disposal of special waste will be decided on a case-by-case basis.

Also included are remotely operated tools, equipment, and instruments for excavation of loose material, as well as instruments for removing intact waste containers and bulk metal objects.

The excavated waste is grouped into bulk metal objects, loose material, and intact containers. Each type of waste is placed in a separate reusable transportation container. The bulk metal waste containers are transported to the Metal Decontamination and Sizing Subsystem (S-BE-1) for treatment and disposal.

The loose material and intact containers are sent to the Waste Receiving, Processing, and Packaging Facility for treatment and disposal. The Waste Receiving, Processing, and Packaging Facility may be represented by any of the 12 candidate systems.

Ventilation equipment is provided to maintain barriers needed for an alpha certified environmental enclosure. The ventilation equipment provides barriers in case of fire and release of harmful gases. Spent filters from this ventilation unit are placed in loose material containers and shipped to the Waste Receiving, Processing, and Packaging Facility for treatment and disposal.

A description of the unit operations of the Waste Receiving, Processing, and Packaging Facility may be found in Volumes IV-VI.

5.1.1.1 Alpha Enclosure. The alpha enclosure unit will include all equipment and components housing the retrieval subsystem components, maintain the required confinement for an alpha environment, and transport the retrieval subsystem components from one excavation area to another.

5.1.1.2 Object Location Identifier. The object location identifier unit will include equipment and components for scanning the area beneath the soil to identify large metallic objects and large structural objects.

5.1.1.3 Visual Inspection. The visual inspection unit will include equipment and components for visual inspection of the retrieval area during the remote excavation operation.

5.1.1.4 Radiation Surveyor. The radiation survey unit will include equipment and components for detection of high radiation objects in the retrieval area during the remote excavation operation.

5.1.1.5 Peripheral Soil.

- Peripheral soil excavator: The peripheral soil excavation unit will include equipment and components for excavation of trench topsoil cover and trench sides and bottom peripheral soil.
- Peripheral soil on-line survey: The peripheral soil on-line survey unit will include equipment and components for on-line assay of plutonium in the retrieved soil during the excavation operation.
- Peripheral soil container filling: The container filling unit will include equipment and components for placing the waste in reusable containers designed for onsite handling and transportation.
- Peripheral soil container inspection: The peripheral soil container inspection unit will include equipment and components for cleaning the container exterior as needed for onsite transportation and performing smear and radiation tests.

- Peripheral soil vehicle loading: The peripheral soil vehicle loading unit will include equipment and components for placing the soil containers on the onsite transportation vehicles.
- Onsite transportation vehicle: Onsite transportation vehicles will be used to ship the waste containers from the Retrieval Subsystem to the Soils Processing Subsystem.

5.1.1.6 High Radiation Objects.

- High radiation objects removal: The high radiation object removal unit will include equipment, components, and tools for excavating and extracting high radiation objects from the trenches or pits and placing the high radiation objects on the designated special waste packaging area. Capacity and other limitations of this unit are based on remote technology availability and economics. Objects exceeding the capacity and limitation of the unit will be handled on a case-by-case basis.
- High radiation objects container: The container filling unit will include areas for placing the waste in a container designed for interim storage. Each containerization operation is handled on a case-by-case basis.
- High radiation objects container storage: The high radiation objects storage unit will include space for placing the waste containers in an interim storage area. Material handling for each waste container will be provided on a case-by-case basis.

5.1.1.7 Large Objects.

- Large objects removal: The large object removal unit will include equipment, components, and tools for excavating and extracting of large objects from the trenches or pits and placing the large objects on the designated special waste packaging area. Capacity

and other limitations of this unit are based on remote technology availability and economics. Objects exceeding the capacity and limitation of the unit will be handled on a case-by-case basis.

- Large objects container filling: The container filling unit will include areas for placing the waste in containers designed for interim storage. Each containerization operation is handled on a case-by-case basis.
- Large objects container storage: The large object storage unit will include space for placing the waste containers in an interim storage area. Material handling for each waste container will be provided on a case-by-case basis.

5.1.1.8 Large Construction Material.

- Large construction material removal: The large construction object removal unit will include equipment, components, and tools for excavating and extracting large construction materials from the trenches or pits and for placing the large construction materials on the designated special waste packaging area. Capacity and other limitations of this unit are based on remote technology availability and economics. Objects exceeding the capacity and limitation of the unit will be handled on a case-by-case basis.
- Large construction material container filling: The container filling unit will include areas for placing the waste in containers designed for interim storage. Each containerization operation is handled on a case-by-case basis.
- Large construction material container storage: The construction material storage unit will include space for placing waste containers in an interim storage mode. Material handling for each waste container will be provided on a case-by-case basis.

5.1.1.9 Loose Material.

- Loose material excavator: The loose material excavator unit will include equipment, components, and tools for excavating and extracting loose material from the trenches or pits and placing loose material in reusable containers.
- Loose material container filling: The container filling unit will include equipment and components for placing the loose material in reusable containers designed for onsite handling and transportation. An on-line plutonium assay instrument will detect the plutonium waste concentration to limit the plutonium content of a container.
- Loose material container inspection: The loose material container inspection unit will include equipment for cleaning the container exterior as needed for onsite transportation and performing smear and radiation tests.
- Loose material container vehicle loading: The loose material loading unit will include equipment for and components for placing the soil containers on onsite transportation vehicles.
- Loose material container transport vehicle: An onsite transportation vehicle will be used to ship the reusable containers from the Retrieval Subsystem to the Waste Receiving, Processing, and Packaging Facility.

5.1.1.10 Intact Container.

- Intact container extractor: The intact container extractor unit will include equipment, components, and tools for excavating and extracting intact containers from the trenches or pits and placing the intact containers in reusable containers.

- Intact container over-pack filling: The container filling unit will include equipment and components for placing the intact containers in reusable containers designed for onsite handling and transportation.
- Intact container over-pack inspection: The intact container inspection unit will include equipment and components for cleaning the container exterior as needed for onsite transportation and performing smear and radiation tests.
- Intact container over-pack vehicle loading: The intact container vehicle loading unit will include equipment and components for placing the soil containers on onsite transportation vehicles.
- Intact container over-pack transport vehicle: An onsite transportation vehicle will be used to ship the reusable containers from the Retrieval Subsystem to the Waste Receiving, Processing, and Packaging Facility.

5.1.1.11 Bulk Metal.

- Bulk metal extractor: The bulk metal extractor unit will include equipment, components, and tools for excavating and extracting bulk metal from the trenches or pits and placing the bulk metal in reusable containers.
- Bulk metal container filling: The container filling unit will include equipment and components for placing the bulk metal in reusable containers designed for onsite handling and transportation.
- Bulk metal container inspection: The bulk metal container inspection unit will include equipment and components for cleaning the container exterior as needed for onsite transportation and performing smear and radiation tests.

- Bulk metal container vehicle loading: The bulk metal vehicle loading unit will include equipment and components for placing the soil containers on onsite transportation vehicles.
- Bulk metal container transport vehicle: An onsite transportation vehicle will be used to ship the reusable containers from the Retrieval Subsystem to the Metals Decontamination and Sizing Subsystem.

5.1.2 Subsystem Boundaries

The Retrieval Subsystem (S-BE-4) consists of the unit operations shown in Figure VII-5-1.

5.1.2.1 Physical Boundaries. The physical boundaries include an alpha environmental enclosure unit, interim storage structures for the high radiation, large objects, large construction material waste containers, TRU waste Trenches 1-10 and Pits 1-6, 9, and 10, and peripheral soil consisting of approximately 5 ft on top and 5 ft on each side of the waste pits and 3 ft in the bottom of the trenches and pits.

The shipping dock is the boundary for the output stream to the Waste Receiving, Processing, and Packaging Facility. The output waste stream includes packaged peripheral soil, packaged bulk metals, loose materials, and intact containers.

5.1.2.2 Utilities. The Retrieval Subsystem will require services from the service water system and electrical power supply. The boundaries for the utilities are the service water shut-off valves located about 30 ft from the environmental enclosure and the 4-kV power supply pole located 30 ft from the environmental enclosure.

NOTES:

A. WEIGHT FRACTIONS BASED ON TABLE 11 WEIGHT AND VOLUME FRACTIONS OF WASTE BURIED AT THE SDA, "A BRIEF ANALYSIS AND DESCRIPTION OF TRU WASTE DISPOSAL IN THE SUBSURFACE DISPOSAL AREA OF THE RWMC AT THE INEL".

B. ASSUME TEN PERCENT OF THE WASTE IS IN INTACT CONTAINERS; REMAINDER IS LOOSE MATERIAL.

C. ALL FLOWRATES ARE IN POUNDS PER HOUR (PPH)

D. ASSUME 80% OF METAL IS BULK METAL.

LEGEND:

SHADING DENOTES UNIT OPERATIONS THAT REQUIRE RESEARCH AND DEVELOPMENT, OR DEMONSTRATION.

RESEARCH & DEVELOPMENT

DEMONSTRATION

NOTES:

1. LARGE OBJECTS, ETC.

2. LARGE CONSTRUCTION SLABS, STEEL BE

Figure VII-5-1. Process functional diagram for the Retrieval Subsystem (S-BE-4).

DESCRIPTION

AREA TO BE EXCAVATED IS ENCLOSED WITH A PORTABLE ALPHA-TIGHT ENCLOSURE. SOIL IS EXCAVATED TO EXPOSE WASTE. WASTE IS REMOVED REMOTELY AND PACKAGED FOR TRANSPORT TO PROCESS FACILITY.

EG&G SYSTEM DESIGN STUDY
WASTE RETRIEVAL SUBSYSTEM
FLOW DIAGRAM

JOB NO.
20996-005

FIGURE
2-1

DATE
2/14/91

5.1.2.3 Environment. The Retrieval Facility will have the following physical interface with the environment:

- Building ventilation system discharge
- Treated liquid waste discharge
- Containerized soil and TRU waste shipment to treatment facilities
- Nonradioactive solid waste shipments to municipal disposal facilities.

5.1.3 Process Functional Diagram

5.1.3.1 Subsystem Specific Assumptions. The following unique subsystem specific assumptions apply to the Retrieval Subsystem:

- A 10,000 ft² storage area is assumed for special waste storage including high radiation, large objects, and large construction materials
- A 5000 ft² storage area is assumed for the filled and empty reusable waste containers.

5.1.3.2 Process Functional Diagram. The mass flow rates and energy requirements for the Retrieval Subsystem are shown in Figure VII-5-1.

5.1.4 Facility Description

5.1.4.1 General Arrangement. General arrangements for the Waste Receiving, Processing, and Packaging Facility are shown in Figure VII-5-2.

5.1.4.2 Surge Storage Requirements. Storage capacity will be provided for the incoming reusable containers and the final packaged containers. The

SCALE 40'-1"

0 20 40 FT

WASTE RETRIEVAL SUBSYSTEM

(S-BE-4) - GENERAL ARRANGEMENT

JOB NO.
20996-005

FIGURE
2-2

DATE
02/12/91

storage area will contain a material handling system, fire protection, ventilation, and monitoring per RCRA.

5.1.5 Subsystem Design Requirements

5.1.5.1 Functional Requirements. The Retrieval Subsystem should meet the following functional requirements:

- Retrieves the buried waste and peripheral contaminated soil from the TRU waste trenches and pits located at RWMC
- Provides a gross sorting of the retrieved waste
- Prepares, packages, and transfers all special waste streams to an interim storage area.

5.1.5.2 Performance Requirements. The Retrieval Subsystem will meet the following performance requirements:

- Designed to process and package buried waste from RWMC over a 10-year period.
- Have an operational availability of 24 hours/day, 5 days/week, 70% plant availability during operation, operating 240 days/year.
- Meet the INEL onsite transportation requirements for hazardous waste transfer.
- Have the ability to sort and segregate special waste, peripheral soil, loose TRU material, metal objects, and intact waste containers.
- Have the ability to remotely scan, detect, and excavate buried special waste objects, including large construction material and high radiation and large objects. The unit operations excavation

and handling capacity and radiation limitation for large construction, high radiation, and large objects will be based on the technology availability and economics. Objects exceeding the size, radiation, and handling limitation of the unit operation will be handled on a case-by-case basis.

- Have the ability to conduct the operation in environmentally safe and acceptable conditions.
- Capable of positioning over the buried waste and moving from one buried waste site to another.

5.1.6 Interface Requirements

The Metal Decontamination and Sizing Subsystem (S-BE-1) and the Soils Processing Subsystem (S-EB-2) interface with the Retrieval Subsystem (S-BE-4).

5.1.6.1 Support to Other Systems (Output). The Retrieval Subsystem provides output to the following:

- Soils Processing Subsystem (S-EB-2)
- Interim storage
 - High radiation objects
 - Large objects
 - Large construction materials
- Output to the Waste Receiving, Processing, and Packaging Facility
 - Loose material
 - Intact containers
 - Bulk metals.

5.1.6.2 Support from Other Systems (Input). The Retrieval Subsystem receives input from utilities, service water, power, ventilation, and

consumables including packaging materials and shipping containers (both disposable and reusable).

5.2 SYSTEM ASSESSMENT

The current status, program implementation risks, and a pro/con analysis of the unit operations associated with the Retrieval System are discussed below. The integration aspects in forming a complete subsystem that satisfies the functional, performance, and interface requirements are complex and may perturb individual unit operations or necessitate DT&E efforts because of integration problems not previously identified.

5.2.1 Current Status of Unit Operations

There are 11 unit operations associated with the Retrieval Subsystem (S-BE-4). The unit operation and reference to the F&OR are discussed below.

5.2.1.1 Characterization. Characterization of RWMC as a site was assumed to be performed by others. As an input to the other unit operations, it is necessary to characterize the waste streams. The Retrieval Subsystem performs this characterization before and during the excavation and extraction of the buried waste. The characterization of the waste is performed by the following unit operations: visual inspection, radiation surveyor, and high radiation objects. These unit operations are discussed below. The characterization process is continuous and ensures that the information acquired before and during excavation and extraction is carried forward to the next unit operation.

5.2.1.2 Alpha Enclosure. Alpha enclosures, as used in the nuclear environment, are defined as three-part environmentally controlled enclosures. The three parts typically consist of the working volume, an isolation vestibule, and an entry/exit vestibule. The system is required to have filtered ventilation and is normally negatively aspirated. Depending on the

case, positive ventilation systems have been built and used. The enclosure also provides protection against gas release during excavation and fire.

These systems are currently commercially available but must usually be tailored to the specifics of the operating environment, local procedures, work space requirements, and the type of hazard. There is no specific DT&E required for the design, fabrication, and installation of this unit operation, except for the enclosure's mobility and reliability of ground-enclosure seals after movement. Containment of toxic, volatile, and hazardous gases during normal and accident events will also require DT&E. In this concept, mobility is provided by installing the enclosure on a traction wheel (see Figure VII-5-2).

5.2.1.3 Object Location Identifier. This unit operation provides dimensional information on buried objects. This would include X, Y, and Z coordinates based on a local coordinate system and may also include such information as the type of object, object dimension, and object orientation. This provides a prior knowledge that will facilitate the safe excavation, extraction, and processing of the buried waste object.

The state-of-the-art operation is based on existing geotechnical practices and methodology. This includes such tools as ground penetrating radar (similar to sonar), induced current, magnetic anomaly detection, acoustic refraction, and cone penetrometer probes. The latter method may have shortcomings if liquid or compressed gases are present.

This instrumentation is commercially available in hand-held, portable, and fixed installation configurations. Any combination of these may be required. Most of these are amenable to sensor integration packages for remotely operated equipment. Development will be required for detecting such objects as 55-gal drums for translating the information to the control architecture for automated excavation equipment. Specifically, the issues of usable graphic interpretation need to be addressed. Geological conditions have significant impact on the efficiency, resolution, and applicability of these various techniques. Sonar is not a viable technique because this

process is typically used in aqueous environments. The reference to sonar with respect to ground penetrating radar (GPR) is merely one of similitude for understanding the concept.

5.2.1.4 Visual Inspection. The advanced techniques range from still photography (35 mm) to digital still video using fuzzy logic control. Available visual inspection systems consist of a wide range of sensing technologies including but not limited to (a) remote camera system controls (e.g., focus, iris, zoom, and white balance), (b) environmentally-sealed pan and tilt units with remote controls and remote position indication, (c) laser imaging systems with high resolution monochromatic images or artificially colored images based on reflectance values that can provide distance and size resolution information, (d) charged coupled device (CCD) cameras that provide digital encoded picture information lending themselves to small camera size, high resolution, and direct interface to computer processing systems, and (e) tube type cameras (e.g., satacon, vidacon, and newvacon tubes) provide high image resolution and a great degree of tolerance to radiation fields. Other means of visual inspection may include direct observation either from a remote position or from direct human control at the side of the remote equipment.

The equipment is commercially available; however, state-of-the-art integration of the systems for equipment control, excavation interface data acquisition, and image acquisition for historical or assessment purposes most often requires customization and innovative integration that may not have been previously performed. Depending on the nature of the information required during excavation, some DT&E effort may be necessary to tailor this unit operation to the specific needs.

5.2.1.5 Radiation Surveyor. This unit operation provides a radiological profile of the excavation site before and during excavation. This information is required for the segregation of waste streams, the identification of special wastes, and information feedback on the nature and extent of the radiological hazard. The tools used include multichannel analyzers, directional and gross gamma detectors, and alpha/beta detectors.

Surveys to be performed would include baseline surveys before excavation, in situ surveys with instrumented probes (for depth profiling), on-line assay and segregation surveys as required, environmental/boundary surveys, and characterization of both soil matrix and objects.

This instrumentation is commercially available in hand-held, portable, and fixed installation configurations. Any combination of these may be required. Most of these are amenable to sensor integration packages for remotely operated equipment. DT&E of the integration of the component to meet the objectives of the radiation survey unit operation may be required.

5.2.1.6 Peripheral Soil. This unit operation is intended to remove and prepare for shipment overburden and peripheral soils from the buried waste site. The first on-line assay for segregation of plutonium/TRU materials from LLW contaminants is also performed at this point. The recovered materials from this process will provide feed stock to the Soils Processing Subsystem (S-EB-2). The equipment will typically consist of (a) remotely operated excavation equipment capable of removing large quantities of soils anticipated to be processed, (b) a fine excavation system for removal of interstitial soils (soils between or adjacent to buried objects), (c) an on-line assay system capable of detecting plutonium/TRU and high radioactive objects, (d) automated container loading and handling equipment, (e) automated equipment for the transport of bulk soils from the excavation interface to the soil container loading area, (f) vacuum equipment, and (g) vision system and control equipment.

Recent advances in bilateral forced feedback controls integrated into remotely operated construction equipment make the viability of these operations a reality. The majority of the equipment is commercially available and in use today.

The Remote Operated Vehicles (ROV) System is currently in use in the marine industry for inspecting, digging trenches, burying pipelines, and highly dexterous tasks. Supervisory control architectures, based on graphic user interfaces and several levels of built-in protection, are being developed

and used to support ROV operations and construction equipment automation. The systems are slated for demonstration as part of the underground storage tank remediation at the Hanford Site and Fernald. The system has been able to prevent operator errors in task planning execution, and correct and compensate for vehicle or manipulator-based movements with a resolution accuracy of approximately 1/2 in.

Force reflection methods and advances in manipulator control architecture have enabled integration of these technologies into usable scale construction equipment that allows excavation from a single station joystick control. The integration of force reflection permits resolution of small forces to prevent the manipulator from crushing the objects to be retrieved.

An excellent example of both technology transfer and task/environment-based robotic system development would be the "HAZTRACK" by KRAFT telerobotics. HAZTRACK is based on a John Deere 25 excavator (a 7000-lb excavator). This system has a useful bucket capacity (up to approximately 1-1/2 yd³), low ground pressure footprint (approximately 400 psi), and useful range of motion (approximately 15-ft reach). In addition, all tractor, boom, bucket, and cab functions are controlled from a single station and a single joystick, and force reflection is integrated into the boom/bucket such that you can now resolve forces detected (contact with objects) down to the range of less than 5 lb; thus, you can detect lines, pipes, barrels, etc. without rupturing them.

DT&E may be required to integrate an on-line assay system with a vacuum excavation system that will have a measurable level of detection threshold at a useful process feed rate. DT&E of the integration of the components to meet the objectives of the peripheral soil unit operation may also be required.

5.2.1.7 High Radiation Objects. This unit operation detects and advises the control operator of the presence of high radiation objects. Upon detection of the high radiation objects, remote manipulators assist in the excavation and extraction of the object. The equipment consists of a remotely-operated high payload manipulator system having force feedback,

integrated radiation detection and proximity sensor package, automated container loading and handling system, vision system and control equipment, and special shielded containers. DT&E may be required for the integration of the sensor package with the manipulator control system.

5.2.1.8 Large Objects. This unit operation detects and advises the control operator of the presence of large objects. Upon detection of the large objects, remote manipulators assist in the excavation and extraction of the object. Large objects exceeding the capacity of the manipulator will be excavated by special equipment provided on a case-by-case basis. The equipment consists of a remotely-operated high payload manipulator system having force feedback, an integrated radiation detection and proximity sensor package, an automated container loading and handling system, and vision system and control equipment.

The equipment associated with this unit operation is commercially available. Additional DT&E may be required for the integration of the sensor package with the manipulator control system.

5.2.1.9 Large Construction Material. This unit operation detects and advises the control operator of the presence of large construction material. Upon detection of the large construction material, remote manipulators assist in the excavation and extraction. Large construction materials exceeding the capacity of the manipulator will be excavated by special equipment provided on a case-by-case basis. Provisions will be made for the segregation of easily disposed construction materials from special case large objects. The equipment consists of a remotely-operated high payload manipulator system having force feedback, an integrated radiation detection and proximity sensor package, an automated container loading and handling system, and vision system and control equipment. The equipment associated with this unit operation is commercially available. However, DT&E may be required for the integration of the sensor package with the manipulator control system.

5.2.1.10 Loose Material. Contents of corroded and decomposed boxes and drums are expected to be dispersed inside the disposal pits and trenches as

loose materials. Included in this material could be paper, plastic, wood, glass, residual soil, and other wastes. This unit operation is intended to remove and prepare loose materials for repackaging and shipping from the buried waste site. These materials are differentiated from construction materials primarily by size. The equipment will typically consist of a fine manipulator system for removal of loose materials, an on-line assay system, automated container loading and handling equipment, automated equipment for the transport of loose materials, and vision system and control equipment.

Recent advances in bilateral forced feedback controls, integrated into remotely operated construction equipment, make the viability of these operations a reality. The majority of the equipment is commercially available and in use today. (The comments in Section 5.2.1.6 also apply to loose material.) DT&E of the integration of the components to perform within an alpha cell enclosure may be required.

5.2.1.11 Intact Container. This unit operation is intended to remove and prepare intact containers (drums and boxes) for repackaging and shipping from the buried waste site. The equipment will typically consist of a manipulator system with a force feedback control and drum handling grab mechanism, an on-line assay system, automated container loading and handling equipment, automated equipment for the transport of intact containers, and vision system and control equipment.

Recent advances in bilateral forced feedback controls integrated into remotely operated construction equipment make the viability of these operations a reality. The majority of the equipment is commercially available and in use today. (The comments in Section 5.2.1.6 also apply to intact containers.) DT&E of the integration of the component to meet the intact container objectives may be required.

5.2.1.12 Bulk Metal. This unit operation is intended to remove and prepare bulk metal for repackaging and shipping from the buried waste site. The equipment will typically consist of a manipulator system with a force feedback control and drum handling grab mechanism, an on-line assay system,

automated container loading and handling equipment, automated equipment for the transport of intact containers, and vision system and control equipment.

Recent advances in bilateral forced feedback controls integrated into remotely operated construction equipment make the viability of these operations a reality. The majority of the equipment is commercially available and in use today. (The comments in Section 5.2.1.6 also apply to bulk metal.) DT&E of the integration of the component to meet the bulk metal objectives may be required.

5.2.2 Program Implementation Risks

This section identifies major concerns associated with program implementation assuming that the Retrieval Subsystem is selected. Furthermore, risk of accomplishing the program objectives is qualitatively characterized. A summary of results and major areas of concern is shown in Table VII-5-1. Program mission and objectives are given in Volume II.

5.2.2.1 Performance Objectives. Baseline cleanup standards for the SDA pits and trenches at RWMC cannot be established until an ROD pursuant to the CERCLA process is reached. These standards will be derived ARARs under CERCLA, standards set by risk assessments, and the State and local statutes. Since no specific requirements have been formally established at this time, it is assumed that the major ARARs for this subsystem will be RCRA rules, the appropriate NRC regulations and guides, and the DOE regulations and Orders.

In the Retrieval Subsystem, the major uncertainties listed below have been identified as areas of concern in the achievement of the performance objectives:

- The function of the alpha enclosure is to contain any radioactive, hazardous, toxic, and volatile gases that may become airborne during the retrieval operation. This protection will have to be provided in normal and postulated accident events (e.g., a fire). Alpha enclosures, as used in the nuclear environment, typically

Table VII-5-1. S-BE-4 summary of program implementation risks and major areas of concern

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> Ability to define a cost effective alpha enclosure design to confine radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events Ability to define a cost effective design for enclosure mobility Operation choking due to case-by-case excavation, treatment and storage of high radiation and large construction objects and special waste Effectiveness of seal between alpha enclosure and ground 	<ul style="list-style-type: none"> Ability to identify and mitigate normal and postulated accident events (such as fire, criticality, unforeseen release of toxic/hazardous material) 	None	<ul style="list-style-type: none"> Alpha enclosure is a first-of-a-kind and require prolonged DT&E, design, and construction Remotely operated equipment for characterization, excavation, and handling of TRU could require prolonged DT&E, design, and construction Remotely operated equipment for characterization, excavation, and handling of TRU waste is a first-of-a-kind application and subject to cost overruns 	<ul style="list-style-type: none"> Alpha enclosure is a first-of-a-kind and could be subject to cost overruns due to prolonged design development Remotely operated equipment for characterization, excavation, and handling of TRU waste is a first-of-a-kind application and subject to cost overruns
Moderate	Moderate	Low	Low	Moderate

Table VII-5-1. (Continued)

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> Dust control during operations could require very large and complex ventilation and filtration systems Reliable operation of some of the characterization equipment in dusty environment is in doubt 				
Moderate	Moderate	Low	Low	Moderate

have triple confinement barriers. A triple barrier is needed to ensure the protection of workers, public health and safety, and the environment. The three parts typically consist of an operation area (which is usually contaminated), an isolation vestibule, and an entry exit vestibule. Because the excavation area in SDA covers several pits and trenches, the enclosure must be mobile. This feature makes the enclosure a first-of-a-kind facility with many uncertainties regarding the program's ability to develop a cost effective design that adequately confines radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events. This complexity is further because several excavation manipulators, handling equipment, and related components must be installed inside the enclosure.

- The characterization, excavation, and handling unit operations are remotely operated and are located inside the alpha cells. There is a concern regarding potential jamming and maloperation of the components. Also, any of these unit operations could be a potential choke point because of limited prior knowledge of waste streams and the high throughput requirements. Areas of major concern are case-by-case excavation, treatment and storage of high radiation and large construction objects, and special waste.
- Additional technical concerns are (a) an unreliable seal between the alpha cell enclosure and the ground, (b) dust control during operations could require very large and complex ventilation and filtration systems, (c) questionable operation of some of the characterization equipment in a dusty environment, and (d) dusting and equipment decontamination for maintenance could become a limitation on the application of commercially available equipment. DT&E efforts could become more extensive than estimated.

Based on the above discussions, it is believed that the risk associated with achieving the performance objectives is moderate.

5.2.2.2 Health and Safety Objectives. Key health and safety objectives for the Buried Waste Program are to (a) identify the hazards of the remedial action operation, and (b) provide measures to eliminate, control, or mitigate identified hazards. In the Retrieval Subsystem, a major area of uncertainty is the ability to define postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material) for the alpha enclosure and provide mitigation measures to satisfy the RCRA, NRC, and DOE requirements. The ability of the current characterization technologies to provide advanced information to support a safe excavation operation is also of concern. Currently, the limited availability of information on waste characteristics contributes to these uncertainties. It is believed that using remote handling equipment and conducting operations inside an alpha enclosure could provide mitigation to the majority of the postulated events. Hence, the risk associated with achieving the health and safety objectives is characterized to be moderate.

5.2.2.3 Institutional Objectives. A key institutional objective is to involve the public, as required by CERCLA and NEPA, in the process of selecting a remedial action for the Buried Waste Program. Public support of the Retrieval Subsystem is anticipated because it is part of a remedial action strategy that is consistent with the desire of the public and the State of Idaho to retrieve the SDA waste. Hence, it is believed that the risk associated with achieving the institutional objectives is low.

5.2.2.4 Schedule Objectives. The objective of the Buried Waste Program schedule is to reach approval for Title II start by mid 1999. This is based on the assumptions that an ROD will be reached by the end of FY 2001. The schedule objective for completion of the Buried Waste Program remedial action is by FY 2019. The following major uncertainties in achieving these objectives have been identified:

- The alpha enclosure is a relatively complex first-of-a-kind structure and could be subject to prolonged DT&E, design, and construction. However, with advanced planning, uncertainties in achieving schedule objectives could be reduced.

- Using remotely operated equipment for characterization, excavation, and handling of TRU waste is a first-of-a-kind application. Schedule uncertainties from prolonged DT&E, design, and construction are anticipated. Again, with advanced planning, uncertainties in achieving schedule objectives could be reduced.

Based on the above discussions, and an assumption that the program implementation activities will begin in FY 1992, the schedule risk is believed to be low.

5.2.2.5 Cost Objective. Assessment of the cost objective is a qualitative characterization based on the uncertainties involved in defining a reasonably accurate cost estimate for the Retrieval Subsystem. Some of the major uncertainties are presented below:

- The alpha enclosure is a first-of-a-kind design and could be subject to cost overruns from prolonged design development. Major areas of uncertainty are the extent of design features needed to provide safety for postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material), and satisfying the RCRA, NRC, and DOE requirements. Currently, the limited information available on waste characteristics contributes to these uncertainties.
- Using remotely operated equipment for characterization, excavation, and handling of TRU waste is a first-of-a-kind application. Cost uncertainties are anticipated until design, based on DT&E, is well into maturity.

Based on the above discussions, the cost risk is believed to be moderate.

5.2.3 Unit Operations Pro and Con Analysis

The following is a pro and con assessment of each unit operation of the Retrieval Subsystem (S-BE-4). The advantages and disadvantages are discussed in light of the overall objectives of the Environmental Restoration Program. The compatibility of interfaces and specific areas of weakness in the unit operation are addressed.

5.2.3.1 Alpha Enclosure. Alpha enclosures, as used in the nuclear environment, are defined as three-part environmentally controlled enclosures. The three parts typically consist of the working volume, an isolation vestibule, and an entry/exit vestibule. An advantage is that an alpha enclosure will prevent the spread of contamination during the excavation and extraction process. Disadvantages include (a) working conditions limit access by operators and rely on robotics and remotely operated equipment with a potential for reliability problems, (b) the seal of the alpha enclosure to the surrounding soil may present unique problems in designing a movable alpha cell enclosure, and (c) decontamination of equipment and components before maintenance.

5.2.3.2 Object Location Identifier. This unit operation provides dimensional information on buried objects. This would include X, Y, and Z coordinates based on a local coordinate system and may also include such information as the type of object, object dimension, and object orientation. An advantage is that the process uses existing technology. A disadvantage is that additional DT&E is needed on resolution, geological conditions, and application to automated excavation.

5.2.3.3 Visual Inspection. The visual inspection unit operation provides the operators with visual information of the progress of excavation through remote monitoring. The advantage is that visual inspections are an existing technology. The disadvantage is that it may be susceptible to dusting and contamination, resulting in malfunction.

5.2.3.4 Radiation Surveyor. This unit operation provides a radiological profile of the excavation site. The radiation surveyor uses existing technology; high radiation objects will be located for isolation. The surveyor will provide a radiological profile of the site before excavation. The disadvantage is that integration of existing technologies and the application to the physical location may require DT&E.

5.2.3.5 Peripheral Soil. This unit operation is intended to remove and prepare overburden and peripheral soils for shipping from the buried waste site. The advantage is that excavation of peripheral soil uses existing technology. The disadvantage is that excavation will produce large amounts of dust on all associated equipment, which may become contaminated.

5.2.3.6 High Radiation Objects. This unit operation detects and advises the control operator of the presence of high radiation objects. Advantages are that high radiation objects are easily detected and provisions have been made to extract these objects on a case-by-case basis. Disadvantages are that it may be difficult to handle because of size and shielding requirements, and complicated high radiation objects with many nooks and crannies may be difficult to clean inside an alpha enclosure.

5.2.3.7 Large Objects. This unit operation detects and advises the control operator of the presence of large objects. An advantage, depending on the nature of the large object, is that these may be bypassed by the alpha enclosure for later extraction. Disadvantages are that the object may be difficult to work around in the alpha enclosure, complicated large objects with many nooks and crannies may be difficult to clean inside an alpha enclosure, and excavation and retrieval will generate large amounts of dust.

5.2.3.8 Large Construction Material. This unit operation detects and advises the control operator of the presence of large construction material. An advantage is that it may be easily extracted. Disadvantages are that it may be difficult to work around the material in the alpha enclosure, and excavation and retrieval will generate large amounts of dust.

5.2.3.9 Loose Material. This unit operation is intended to remove and prepare loose materials for repackaging and shipping from the buried waste site. An advantage is that loose material is easily excavated and packed for shipment. Disadvantages are that handling loose material may result in dusting and thus impose a larger loading of material on the HVAC filtration system, and loose material in damaged boxes and bags may spill into the excavation area.

5.2.3.10 Intact Container. This unit operation is intended to remove and prepare intact containers for repackaging and shipping from the buried waste site. An advantage is that the equipment uses existing technology. A disadvantage is that handling intact containers may be difficult because of corrosion or deterioration of the intact containers.

5.2.3.11 Bulk Metal. This unit operation is intended to remove and prepare bulk metal for repackaging and shipping from the buried waste site. An advantage is that this unit operation uses existing technology. A disadvantage is that the equipment may have to be over-designed to handle the heaviest objects. On a case-by-case basis, special size reduction may have to be provided.

5.2.4 Unit Operations Lead-Time Estimates

The lead-times required for DT&E are estimated for each unit of operation that may require DT&E before landing in the field and are shown in Table VII-5-2. The development of the lead-time required for DT&E is based on a qualitative judgment and should be further refined.

5.2.5 Rough Order of Magnitude Cost Estimates

ROM costs were developed for the Retrieval Subsystem (S-BE-4) using the assumptions given in Section 1. The costs are summarized in Table VII-5-3.

The assumptions and qualifications used in the preparation of the ROM estimate for this system are as follows:

Table VII-5-2. DT&E assessment summary for the Retrieval Subsystem (S-BE-4)

DT&E Step	Primary paper evaluation			Bench-scale studies			Secondary paper evaluation			Pilot-Plant/Mock-up Test studies			Total Duration
	Required	Duration		Required	Duration		Required	Duration		Required	Duration		
Unit Operation	Yes	6 Months	No	No			No			Yes	12 Months		18 Months
Object Location Identifier													
Visual Inspection	Yes	6 Months	No	No			No			Yes	6 Months		12 Months
Radiation Surveyor	Yes	6 Months	No	No			No			Yes	6 Months		12 Months
Peripheral Soil	Yes	6 Months	No	No			No			Yes	6 Months		12 Months
High Radiation Object	Yes	6 Months	No	No			No			Yes	6 Months		12 Months
Large Objects	Yes	6 Months	No	No			No			Yes	12 Months		18 Months
Large Construction Material	Yes	6 Months	No	No			No			Yes	12 Months		18 Months
Loose Material	Yes	6 Months	No	No			No			Yes	9 Months		15 Months
Intact Containers	Yes	6 Months	No	No			No			Yes	9 Months		15 Months
Bulk Metal	Yes	6 Months	No	No			No			Yes	9 Months		15 Months
Integrated Subsystem	Yes	6 Months	No	No			No			Yes	12 Months		18 Months

Table VII-5-3. Rough order of magnitude cost estimates (S-BE-4)

Cost Code	Cost Items	Normalized Cost (\$x1000)	Modified Cost (\$x1000)
1.0	Studies and bench scale costs		
1.1	Manpower costs during research	\$4,800	
1.2	Equipment costs	\$3,000	
1.3	Installation costs	\$750	
1.4	Contingency	\$2,138	
	Subtotal 1.0	\$10,688	
2.0	Demonstration costs		
2.1	Manpower cost during construction	\$17,280	
2.2	Design cost (30% of 2.5)	\$15,370	
2.3	Inspection cost (7% of 2.5)	\$3,586	
2.4	Project administration (10% of 2.5)	\$5,123	
2.5	Construction cost		
2.5.1	Building structure costs		
2.5.2	Equipment costs		
2.5.3	Indirect (20.9% of 2.5)		
	Subtotal of 2.5	\$51,233	
2.6	Construction management costs (27.8% of 2.5)	\$14,704	
2.7	Contingency	\$26,824	
	Subtotal 2.0	\$134,120	
3.0	Production construction costs		
3.1	Design cost (30% of 3.4)	\$22,725	
3.2	Inspection cost (7% of 3.4)	\$5,303	
3.3	Project administration (10% of 3.4)	\$7,575	
3.4	Construction cost		
3.4.1	Building structure costs	\$50,513	
3.4.2	Equipment costs	\$9,369	
3.4.3	Indirect (20.9% of 3.4)	\$15,869	
	Subtotal of 3.4	\$75,751	
3.5	Construction management costs and construction management reserve (26.5% of 3.4)	\$21,741	
3.6	Contingency (25% of 3.1 through 3.5)	\$33,274	
	Subtotal 3.0	\$166,368	
	Total Capital Costs (1.0, 2.0, and 3.0)	\$311,177	
4.0	Annual operating and maintenance costs		
4.1	Operating costs	\$17,000	
4.2	Utility costs	\$4,000	
4.3	Material costs	\$6,000	
4.4	Maintenance costs	\$8,000	
4.5	Contingency	\$8,750	
	Subtotal 4.0	\$43,750	
TOTAL	10 Years Operating and Maintenance Costs	\$437,500	

- Special site preparation costs are not included (drainage, substations, roadwork, and other utilities).
- Owner's costs such as environmental impact report costs and owner's labor and overheads are not included.
- The estimate is based on first-quarter 1991 wage and price levels.
- The facility areas are developed based on a conceptual layout of the process equipment. Allowances for administrative and remote operation facilities are not included.
- The equipment scope was based on conceptual process flow diagrams.
- Equipment pricing is based on conventional commercial construction. A minimal allowance (e.g., one-of-a-kind demonstration) has been included for remote operation and any nuclear quality assurance program cost. An allowance for process bulks is included at 30% of the equipment cost to account for electrical, piping, and local control requirements.
- The areas shown in the general arrangement were adjusted to account for the unit operations capabilities.
- Equipment costs include material, fabrication, delivery, inspection, and installation costs (all in costs).
- Costs for widening or strengthening existing roads for construction are not included.
- Adequate supply of labor exists within the local area.
- Testing and initial startup costs are not included.

- An assumption was made that the demonstration of the Retrieval Subsystem in a 100 by 250-ft facility will be suitable for later production use.
- Operating and maintenance costs are based on 15% of production construction costs.
- Cost estimates are based on nominal costs associated with the best currently available technology considered. The lowest technology and the state-of-the-art systems were not considered in the cost model.

Strengths and weaknesses of the cost estimate include the following:

- Component costs may vary between unit operations depending on the technologies employed.

5.2.6 System Evaluation Results

The purpose of this section is to provide an overall evaluation of the subsystem and to identify the major considerations (both advantages and disadvantages) resulting from the assessments in the previous sections. This includes an evaluation of the ability to integrate the various unit operations into a smooth, well-functioning subsystem.

Specific areas addressed include the following: identification of major considerations of the subsystem, a qualitative judgment rating of performance measurables, a summary of DT&E needs, and an overall recommendation for the subsystem.

5.2.6.1 Identification of Major Considerations of the Subsystem. The techniques employed in this system are well-known, commercially available, and in current use by industry. This subsystem is depicted in the process functional diagram as separate unique unit operations. There is equipment currently available that combines many of the functions into a single unit.

The excavation, extraction, and retrieval of buried waste may be made more efficient through the application of robotics currently under development.

There is a risk associated with the alpha cell enclosure and accessibility to repair or maintain the equipment. There is risk in achieving an adequate seal between the ground and the alpha cell enclosure. There are risks associated with the design of the overall size and mobility of the alpha cell enclosure and the ability to provide mitigation measures for normal and accident events.

The significant pro for this system is that the processes, except for the alpha cell enclosure size, employed by the subsystem are all in use and well-known. The significant con associated with the Retrieval Subsystem is containing the dust and contamination during the excavation and extraction process.

The technologies employed in this subsystem require integration of all unit operations. The costs for this system should be well-known because the technologies are in current use.

5.2.6.2 Performance Measurables Rating. Performance measurables that should be used in the evaluation of the overall subsystem represent the top level of performance requirements that will be allocated and then applied to appropriate elements of the subsystem in subsequent phases of the program. Table VII-5-4 provides a qualitative assessment of how well the Retrieval Subsystem satisfies these performance measurables.

5.2.7 Summary of Demonstration, Testing, and Evaluation Needs

DT&E needs for each unit operation and for the overall subsystem have been summarized in Table VII-5-5. This table provides a ready reference to DT&E needs in the final subsystem evaluation and for comparison purposes with other subsystems.

Table VII-5-4. Rating performance measurables for the Retrieval Subsystem (S-BE-4)

Measurable	Alpha Enclosure	Object Location Identifier	Visual Inspection	Radiation Surveyor	Peripheral Soil	High Radiation Objects	Large Construction Material	Loose Material	Intact Container	Bulk Metal	Total
Timeliness	8	6	9	9	9	8	8	8	8	8	90
Availability	8	8	9	8	9	8	8	8	7	8	89
Completeness	8	7	9	8	8	6	6	7	7	8	80
Risk	7	6	8	9	8	8	7	7	7	7	82
Flexibility	7	7	8	8	8	8	7	7	7	7	82
Cost	6	7	8	8	8	7	7	8	6	7	79
Safety	6	8	8	8	8	6	7	7	7	7	79
Waste reduction	5	6	6	6	6	6	6	6	5	6	65
Complexity	5	7	8	8	8	6	7	7	7	7	77
Totals	60	64	73	72	72	63	64	65	62	65	723

Table VII-5-5. DT&E needs for the Retrieval Subsystem (S-BE-4)

Unit Operation	Technology Development Status	DT&E
Alpha enclosure	<ul style="list-style-type: none"> • Commercially available • Currently used in the mining and metal industries • Commercially available 	<ul style="list-style-type: none"> • Select design concepts and criteria
Object location identifier		<ul style="list-style-type: none"> • Application in a production environment • Application to waste at RWMC • Remote operation • Automation • Integration • Select design concepts, criteria, and requirements specific to waste at RWMC
Visual inspection	<ul style="list-style-type: none"> • Commercially available • Currently used in the nuclear industry 	<ul style="list-style-type: none"> • Application to waste at RWMC • Remote operation • Maintenance concepts (remote or contact) • Integration • Automation • Application to RWMC site • Confirm compatibility with the location of the RWMC

Table VII-5-5. (continued)

Unit Operation	Technology Development Status	DT&E
Peripheral soil	<ul style="list-style-type: none"> Majority commercially available Currently used in the construction industry 	<ul style="list-style-type: none"> Integration of an on-line assay system with a vacuum excavation system Automation Integration
High radiation objects	<ul style="list-style-type: none"> Commercially available 	<ul style="list-style-type: none"> Application to waste at RWMC Remote operation Integration Automation
Large objects	<ul style="list-style-type: none"> Commercially available 	<ul style="list-style-type: none"> Application to waste at RWMC Remote operation Integration Remote maintenance
Large construction material	<ul style="list-style-type: none"> Commercially available 	<ul style="list-style-type: none"> Integration Remote operation Remote maintenance Application to waste at RWMC

Table VII-5-5. (continued)

Unit Operation	Technology Development Status	DT&E
Loose material	• Commercially available	• Application in alpha cell environment
	• Currently used in nuclear facilities	• Automation
	• Under development	• Integration of the process in production-scale environment
Intact containers		• Application to waste at RWMC
		• Remote operation
	• Commercially available	• Application in an alpha cell environment
Bulk metal	• Currently used in nuclear facilities	• Automation
	• Under development	• Integration of the process in a production-scale environment
		• Application to waste at RWMC
		• Remote operation
	• Commercially available	• Application in an alpha cell environment
	• Currently used in the nuclear industry	• Automation
	• Under development	• Integration of process in production-scale environment
		• Application to waste at RWMC
		• Remote operation

Table VII-5-5. (continued)

Unit Operation	Technology Development Status	DT&E
Integrated subsystem demonstration		• Application in production-scale environment
		• Integration of entire process
		• Reliability, availability, and maintainability of the process in an environment
		• Remote operation and maintenance
		• Automation

5.3 RECOMMENDATION FOR THE SYSTEM

The Retrieval Subsystem essentially uses existing technology to characterize, excavate, extract, sort, and package the retrieved waste for processing by unit operations in other systems and subsystems. There is no physical conversion of the buried waste to the waste output streams. Technologies employed are all currently available, permitting an early start on design, fabrication, and installation.

Several issues that will require further DT&E include (a) an analysis of available component designs that will incorporate multiple functions required during the excavation and extraction process should be conducted, (b) the application of robotics to improve efficiencies and minimize operator exposure should be investigated, (c) the system as a whole will require fine tuning of all the selected technologies to produce the desired end results, (d) consideration should be given to on-line sensors that monitor and report status and progress of waste stream processing, and (e) a large alpha enclosure that is transportable and maintains isolation capabilities after multiple movements.

The study helped characterize and define a number of alternatives for the unit operations of this system. The evaluations conducted under this study conclude that DT&E is required. Qualitative judgments were used in developing the extent of DT&E. A more detailed assessment is needed to draw a definitive conclusion on the DT&E programs and technology selection.

Risk assessments in the study are qualitative and judgmental and are based on the assumption that wastes having dangerous physical or chemical characteristics (e.g., pyrophoric and gas cylinders containing toxic, volatile, and reactive gases) are not being processed. A more detailed definition of the incoming waste will be needed to perform a complete risk assessment. Significant changes in the composition of the waste may impact the technology selected and the general arrangement of the facilities.

The Retrieval Subsystem offers techniques for excavation, extraction, and removal of buried waste. The subsystem is required if the remediation of RWMC requires removal of the waste.

6. BIBLIOGRAPHY

- Arrenholz, D. A., 1990, *In Situ Vittrification Program Treatability Investigation Program Report*, EGG-WTD-9383, December.
- Arrenholz, D. A., and J. L. Knight, 1991, *A Brief Analysis and Description of Transuranic Wastes in the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL*, EGG-WTD-9438, February.
- AWC Inc., 1989, *TRU Clean: A Process for Decontaminating Radioactive and Hazardous Soils*.
- Boehmer, A. M., et al., 1986, "Solidification of Hazardous and Mixed Radioactive Waste at the Idaho National Engineering Laboratory," *Proceedings of the 1986 Symposium on Waste Management, Tucson, Arizona, March*.
- Borham, B. M., et al., 1986, "Handling of Transuranic Waste for Volume Reduction by Incineration," *Proceedings of the 1986 Symposium on Waste Management, Tucson, Arizona, March*.
- Bowen, M. D., et al., 1978, "A Vertical-Bed Pyrolysis System, Solid Waste and Residues Conversion by Advanced Thermal Processes," *175th Meeting of the American Chemical Society, Anaheim, California, March 13-17*.
- Bramlitt, E. T., 1988, "Plutonium Mining for Cleanup," *Health Physics*, 55, 2, August, pp. 451-453.
- Cleveland, J. M., 1970, *The Chemistry of Plutonium*, Garden and Breech Publications: New York, pp. 48-61.
- Cwynar, J. C., et al., 1986, "Retrofit and Operation of Low-level Radwaste Solidification System," *Proceedings of the 1986 Symposium on Waste Management, Tucson, Arizona, March*.
- Deininger, J. P., 1990, "Developments in Transuranic Element Polishing from Radioactive Wastewaters Using Ferrate Chemical Technology," *Waste Management '90 Conference, Tucson, Arizona, March*.
- Edinborough, C. R., 1990, *Processing Criteria for TRU Removal from RWMC Stored Waste*, ERDP 2802, August 15.
- EPA, 1989, *Guide for Conducting Treatability Studies Under CERCLA*, EPA/540/2-89/058, December.
- Francis, C. J., and T. M. Starr, 1990, "The ANF LLW Incinerator Design & Start-Up," *Fourth Annual Symposium on Incineration of Industrial Wastes, Knoxville, Tennessee*.

- Freeman, H. M., 1989, *Standard Handbook of Hazardous Waste Treatment and Disposal*, McGraw Hill: New York.
- Geosafe Corporation, 1989, *Application and Evaluation Considerations for In Situ Vitrification Technology: A Treatment Process for Destruction and/or Permanent Immobilization of Hazardous Materials*, GSC 1901, April.
- Jessop, D., et al., 1986, "Design, Installation, Testing and Start-up of a Material Handling System at the West Valley Demonstration Project," *Proceedings of the 1986 Symposium on Waste Management, Tucson, Arizona, March*.
- Koegler, S. S., R. K. Farnsworth, R. K. Nakaoka, and S. O. Bates, 1989, *Vitrification Technologies for Weldon Spring Raffinate Sludges and Contaminated Soils Phase 2 Report: Screening of Alternatives*, PNL-7125, November.
- Nielson, R. K., et al., 1989, "Low Temperature Thermal Treatment of Volatile Organic Compounds," *1989 Incineration Conference, Knoxville, Tennessee, May*.
- Palmer, C. A., 1989, "X-TRAX Y-12 Sludge Detoxification Demonstration," *1989 Incineration Conference for Chemical Waste Management, Knoxville, Tennessee, May*.
- Penberthy, H. L., 1990, *Full Scale Demonstrating In Situ Vitrification Showing the Fatal Flaw Which is Called Vapor Retreat*, June.
- Perry, R. H., and C. H. Chilton (eds.), 1973, *Perry's Chemical Engineer's Handbook*, Fifth Edition, Table 25-50.
- Peters, M. S., and K. Timmerhaus, 1990, *Plant Design and Economics for Chemical Engineers*, 4th edition, New York: McGraw-Hill.
- Stewart, J. A., and D. L. Charlesworth, 1986, "Design and Operation of a Remotely Operated Plutonium Waste Size Reduction and Material Handling Process," *Waste Management-'86, Proceedings of the Symposium on Waste Management at Tucson, Arizona, March 2-6*.
- Theodore, L., and T. Reynolds, 1987, *Introduction to Hazardous Waste Incineration*, Wiley-Interscience.
- Vietzke, H., *Minimizing of Organic Waste by Pyrohydrolysis*.
- Wheelwright, E. J., L. A. Bray, and J. L. Ryan, 1987, *Development of the CEPOD Process for Dissolving Plutonium Oxide and Leaching Plutonium from Scrap or Wastes*, PN-6483.

END

**DATE
FILMED**

6 / 1 / 1 / 92