**DEFENSE WASTE PROCESSING FACILITY:
REPORT OF TASK FORCE ON OPTIONS TO MITIGATE THE
EFFECT OF NITRITE ON DWPF OPERATIONS (U)**

**SAVANNAH RIVER SITE
200-S AREA**

Author:

J. C. Marek

Contributors:

D. D. Walker
D. H. McGuire
J. W. Nelson/Bechtel National
P. E. Zapp
D. F. Brown
D. F. Bickford
P. D. D'Entremont
J. F. McGlynn

Editor:

D. Randall

March 1992

Authorized Derivative Classifier

C. T. Randall, 704-T

MASTER

**Westinghouse Savannah River Company
Savannah River Site
Aiken, SC 29808**

PREPARED FOR THE U.S. DEPARTMENT OF ENERGY UNDER CONTRACT NO. DE-AC09-89SR18035

MB

DISCLAIMER

This report was prepared by Westinghouse Savannah River Company (WSRC) for the United States Department of Energy under Contract No. DE-AC09-89SR18035 and is an account of work performed under that contract. Neither the United States Department of Energy, nor WSRC, nor any of their employees makes any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, or product or process disclosed herein or represents that its use will not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trademark, name, manufacturer or otherwise does not necessarily constitute or imply endorsement, recommendation, or favoring of same by WSRC or by the United States Government or any agency thereof. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Distribution:

P. M. Hekman, Jr., 703-A
L. C. Sjoström, 703-A
A. L. Schwallie, 703-A
D. B. Amerine, 704-S
M. A. Baich, 704-T
R. T. Begley, 773-A
D. F. Bickford, 773-A
N. C. Boyter, 703-A
D. F. Brown, 703-H
J. T. Carter, 704-1T
P. D. d'Entremont, 703-H
R. E. Eibling, 704-T
D. L. Fish, 773-A
S. T. Goforth, 773-A
R. W. Harral, 703-H
D. W. Harrison, 704-S
E. W. Holtzscheiter, 773-A
C. W. Hsu, 704-1T
R. A. Jacobs, 704-T
A. L. Kielpinski, 773-11A
L. F. Landon, 704-T
L. M. Lee, 704-T
B. L. Lewis, 703-H
J. C. Marek, 704-T
J. C. Marra, 773-A
J. F. McGlynn, 773-A
D. H. McGuire, 704-27S
J. F. Ortaldo, 704-S
L. M. Papouchado, 773-A
C. Peckinpaugh, 703-A
M. J. Plodinec, 773-A
C. T. Randall, 704-T
D. Randall, 773-42A
H. E. Shook, 704-1T
W. E. Stevens, 773-43A
W. L. Tamosaitis, 773-A
W. J. Vetch, WYATT
D. D. Walker, 773-A
G. T. Wright, 703-H
P. E. Zapp, 773-A
SRTC Records (4)

**DEFENSE WASTE PROCESSING FACILITY:
REPORT OF TASK FORCE ON OPTIONS TO MITIGATE THE
EFFECT OF NITRITE ON DWPF OPERATIONS (U)**

ABSTRACT

The possibility of accumulating ammonium nitrate (an explosive) as well as organic compounds in the DWPF Chemical Processing Cell Vent System was recently discovered. A task force was therefore organized to examine ways to avoid this potential hazard. Of thirty-two processing/engineering options screened, the task force recommended five options, deemed to have the highest technical certainty, for detailed development and evaluation:

- Radiolysis of nitrite in the tetraphenylborate precipitate slurry feed in a new corrosion-resistant facility.
- Construction of a Late Washing Facility for precipitate washing before transfer to the DWPF.
- "Just-in-Time" precipitation.
- Startup Workaround by radiolysis of nitrite in the existing corrosion-resistant Pump Pit tanks.
- Ammonia venting and organics separation in the DWPF.

Estimated costs and schedules are included in this report.

BLANK

**DEFENSE WASTE PROCESSING FACILITY:
REPORT OF TASK FORCE ON OPTIONS TO MITIGATE THE
EFFECT OF NITRITE ON DWPF OPERATIONS (U)**

CONTENTS

- 1.0 EXECUTIVE SUMMARY**
- 2.0 INTRODUCTION**
 - 2.1 Process Description**
 - 2.2 Discovery of Problem**
- 3.0 SUMMARY**
 - 3.1 Task Force Studies**
 - 3.2 Task Force Recommendations**
 - 3.2.1 Recommended Options for the Chemical Process Cell**
 - 3.2.2 Recommended Long-Range Options for the Salt Process Cell**
 - 3.2.3 Recommended Short-Term Workaround Option**
 - 3.2.4 Actions Recommended for Immediate Implementation**
 - 3.2.5 Results from Immediate Actions**
- 4.0 SCHEDULE AND COST OF RECOMMENDED OPTIONS**
 - 4.1 Salt Process Cell Options**
 - 4.1.1 Radiolysis Facility**
 - 4.1.2 Late Washing Facility**
 - 4.1.3 Just-in-Time Precipitation**
 - 4.1.4 Startup Workaround by Pump Pit Radiolysis**
 - 4.1.5 Ammonia Venting and Organics Separation**
 - 4.2 Chemical Process Cell Options**
 - 4.2.1 Ammonia Scrubbers**
- 5.0 NITRITE AND AMMONIUM ION CHEMISTRY**
 - 5.1 Nitrite Chemistry in the Tank Farm**
 - 5.2 Nitrite Chemistry in the DWPF**
 - 5.3 Sources of Ammonium Ion**
- 6.0 DESCRIPTION OF OPTIONS WITH HIGHEST TECHNICAL CERTAINTY**
 - 6.1 Salt Process Cell: Radiolysis Facility**
 - 6.1.1 Approach**
 - 6.1.2 Process Details**
 - 6.1.3 Technical Certainty Rating**
 - 6.1.4 Technical Certainties and Benefits**
 - 6.1.5 Technical Uncertainties and Risks**
 - 6.2 Late (or Final) Washing**
 - 6.2.1 Approach**
 - 6.2.2 Process Details**
 - 6.2.3 Technical Certainty Rating**
 - 6.2.4 Technical Certainties and Benefits**

CONTENTS (Contd)

- 6.2.5 Technical Uncertainties and Risks
- 6.3 "Just In Time" Precipitation
 - 6.3.1 Approach
 - 6.3.2 Process Details
 - 6.3.3 Technical Certainty Rating
 - 6.3.4 Technical Certainties and Benefits
 - 6.3.5 Technical Uncertainties and Risks
- 6.4 Chemical Process Cell: Ammonia Scrubbers
 - 6.4.1 Approach
 - 6.4.2 Process Details
 - 6.4.3 Technical Certainty Rating
 - 6.4.4 Technical Certainties and Benefits
 - 6.4.5 Technical Uncertainties and Risks
- 6.5 Workaround Option for Startup: Pump Pit Radiolysis
 - 6.5.1 Approach
 - 6.5.2 Process Details
 - 6.5.3 Technical Certainty Rating
 - 6.5.4 Technical Certainties and Benefits
 - 6.5.5 Technical Uncertainties and Risks
- 7.0 DESCRIPTION OF OTHER OPTIONS FOR SALT PROCESS CELL
 - 7.1 SPC Modifications to Mitigate Ammonium Nitrate by Ammonia Vent
 - 7.1.1 Approach
 - 7.1.2 Process Details
 - 7.1.3 Technical Certainty Rating
 - 7.1.4 Technical Certainties and Benefits
 - 7.1.5 Technical Uncertainties and Risks
 - 7.2 Physical Separation of Organic-Coated Solids
 - 7.2.1 Approach
 - 7.2.2 Process Details
 - 7.2.3 Technical Certainty Rating
 - 7.2.4 Technical Certainties and Benefits
 - 7.2.5 Technical Uncertainties and Risks
- 8.0 GENERIC RECOMMENDATIONS
 - 8.1 Reducing Nitrite in the Precipitate
 - 8.2 Reworking the Precipitate
 - 8.3 Mitigation of Ammonium Nitrate Accumulation
 - 8.4 Noble Metal Testing
 - 8.5 Organic High-Boiler Carryover in the Salt Process Cell
 - 8.6 Improving Attainment During Pump-Pit Workaround
 - 8.7 DWPF Recycle to Tank Farm
- 9.0 SUMMARY OF ALL OPTIONS CONSIDERED
 - 9.1 Promising Options
 - 9.1.1 Options That Eliminate Ammonium Formation in the SPC
 - Option 1: Radiolysis of Nitrite

CONTENTS (Contd)

- Option 32: Set Corrosion Allowance for Tanks 48 and 49**

CONTENTS (Contd)

REFERENCES

- APPENDIX A. Nitrite Task Force Charter**
- APPENDIX B. Task Force Rating Criteria and Assessment Process**
- APPENDIX C. Pitting Corrosion and Its Inhibition in Carbon-Steel Waste Tanks**
- APPENDIX D. Radiolysis of Nitrate and Nitrite Solutions**
- APPENDIX E. Summary of Option Project Schedule Estimates**
- APPENDIX F. Sizing the Nitrite Radiolysis Facility and Attainment Estimates for the Pump-Pit Startup Workaround**
- APPENDIX G. Conceptual Design of a Nitrite Radiolysis Facility**
- APPENDIX H. Overhead Slides From Task Force Presentation**

GLOSSARY

1.0 EXECUTIVE SUMMARY

Ammonium nitrate (a known explosive) and non-polar organics accumulated in the process vessel vent system of the Integrated DWPF Melter System (IDMS) during preparations of simulated melter feeds. The accumulated material created a potential safety hazard and operational problems (e.g., filter pluggage) in the pilot facility at TNX. These technical problems result from the addition of sodium nitrite to the soluble radioactive waste to inhibit pitting corrosion of the carbon-steel processing tanks (Tanks 48 and 49) during In-Tank Precipitation. The impact of nitrite must be aggressively resolved to ensure a safe and timely startup of the Defense Waste Processing Facility (DWPF).

A Task Force was chartered on December 12, 1991 (Appendix A) to rapidly evaluate and supplement all potential options for mitigating or eliminating the impact of nitrite on DWPF operations. Each option was evaluated for technical feasibility and risk, schedule impact (assuming 6/94 startup of radioactive operations in the DWPF), and cost impact. The recommendations were presented to R. T. Begley and N. C. Boyter on 12/19/91.

Under the current DWPF process chemical flowsheet, the primary source of ammonium ion will be the aqueous product produced in the Salt Process Cell (SPC). At projected levels of nitrite ($\leq 0.08M$)* in the washed precipitate feed to DWPF, hydroxylamine nitrate (HAN) is needed in the DWPF Precipitate Hydrolysis Process to minimize production of non-polar organics and tars from the nitrite. However, HAN also produces ammonium ion that is eventually transferred from the SPC to the Chemical Process Cell (CPC) when the precipitate hydrolysis aqueous product (PHA) is blended with the acidified sludge.

The pH of the acidified sludge waste rises during the SRAT process. This phenomenon is probably accelerated by noble-metal-catalyzed dehydrogenation of the formic acid used during melter feed preparation.[1] The pH rise promotes evolution of ammonia from the processing vessels into the vent system. Ammonium ion is also formed during the sludge adjustment with formic acid, presumably by reactions of hydrogen and nitrate catalyzed by noble metals. At the design-basis nitrite content of precipitate feed (0.20M), it is estimated 620 lbs of ammonium nitrate could accumulate in the DWPF CPC process vessel vent system per melter feed batch. It is estimated that the PHA/HAN source accounts for about 90% and the CPC generation of ammonium accounts for about 10% of the total potential ammonium.

For highest technical certainty of mitigating ammonium from the PHA source term, the task force recommends installing a corrosion-resistant (Type 304L or Type 316 stainless steel) facility to reduce the nitrite content of the washed precipitate feed to $\leq 0.01M$ and operation of the Salt Process Cell without HAN. Bench-scale experiments indicate precipitate hydrolysis could be performed without HAN at feed nitrite levels $< 0.01M$. The new facility should be designed for maximum flexibility to reduce the nitrite concentration to $\leq 0.01M$ by any of three identified technologies: radiolytic nitrite destruction, late (or final) washing of the stored precipitate, or "Just In Time" (JIT) precipitation. Which of these three technologies is of highest technical certainty is not clear at this time. SRL priorities should be re-aligned to address the technical uncertainties associated with these three options.

Radiolytic nitrite destruction offers several attractive benefits: a straightforward workaround to meet the 6/94 radioactive operation startup date, minimal complexity of operations, minimal changes in the existing Tank Farm and DWPF processing plans, and no change in the degree to which the Tank Farm operations are coupled to DWPF. The radiolysis would destroy the nitrite during storage of the washed precipitate slurry in the facility. Depending on several factors (extent

* Revised downward from 0.2M, the design basis concentration.

of precipitate washing in Tank 48, storage temperature in Tank 49, initial nitrite content of washed precipitate, radionuclide content, preliminary data for nitrite destruction (Appendix D), etc.), the projected additional storage capacity could range from 160,000 gallons to 570,000 gallons.

Assuming one of the above technologies is selected for long-term implementation, the schedule for the new facility would not meet the 6/94 startup date for DWPF radioactive operation. As a "workaround", the existing pump pit tanks and the Precipitate Reactor Feed Tank could be used to radiolytically destroy nitrite and meet the 6/94 startup date while accepting a significant attainment penalty. However, it is further recommended that a new task force be chartered to assess In-Tank Precipitation and DWPF operational improvements to minimize the attainment penalty with this option and identify more attractive startup workarounds.

The Task Force recommends an aggressive development effort on a nitric acid sludge-adjustment process because an estimated 10% of the potential ammonium nitrate is generated in the current CPC melter feed preparation process. Bench-scale scoping experiments indicate that no ammonium ion is formed and hydrogen production is greatly reduced when simulated sludge waste with noble metals is treated with nitric acid instead of formic acid. The Task Force recommends designing and installing scrubber jumpers on the exhaust line from the Formic Acid Vent Condenser (FAVC) and the vent line of the Recycle Collection Tank (RCT), to mitigate ammonium nitrate generation and accumulation in the CPC with the current formic acid sludge flowsheet. The scrubbers should be supplemented with periodic inspection and cleaning of FAVC jumpers and flooding of the Process Vessel Vent System filter.

2.0 INTRODUCTION

2.1 PROCESS DESCRIPTION

A simplified process diagram is shown in Figure 1. Sludge waste will be transferred from storage to specially equipped waste processing tanks and washed to remove soluble salts. The washed sludge will be stored in the Tank Farm and fed in small batches to the Sludge Receipt Adjustment Tank (SRAT) in the DWPF Chemical Process Cell (CPC). In the SRAT, formic acid is added and the sludge is boiled to reduce metal oxides and remove mercury by steam-stripping.

The soluble waste in the Tank Farm will be decontaminated by the In-Tank Precipitation (ITP) process, and the decontaminated salt solution will be converted into Saltstone at Z Area. The concentrated radioactive organic precipitate (primarily potassium tetraphenylborate, KTPB) from the ITP process will be stored in Tank 49 until it is fed in small batches to the Salt Process Cell (SPC) in the DWPF. In the Precipitate Reactor (PR) of the SPC, the precipitate will be reacted with formic acid and a copper catalyst to remove the aromatic carbon by converting it primarily to benzene (organic waste). The organic will be stripped, decontaminated, and recovered for eventual disposal, possibly by incineration. The aqueous hydrolysis product (Precipitate Hydrolysis Aqueous, or PHA) contains the radioactive elements (primarily cesium-137 and barium 137) and will be sent to the Precipitate Reactor Bottoms Tank (PRBT) for eventual transfer to the SRAT. In the SRAT, the PHA will be combined with the sludge waste and boiled down to reduce the water content of the waste slurry.

The combined Sludge/PHA slurry will then be transferred to the Slurry Mix Evaporator (SME). In the SME, glass frit will be added and the slurry will be further concentrated by boiling off more water. The material will then be sampled and analyzed for process control of glass quality before it is transferred to the Melter Feed Tank (MFT) and eventually to the DWPF glass melter.

2.2 DISCOVERY OF PROBLEM

Pilot-scale operations at TNX use the Precipitate Hydrolysis Experimental Facility (PHEF) to produce PHA for processing tests in the Integrated DWPF Melter System (IDMS). The IDMS simulates both the SRAT and SME operations in the DWPF Chemical Process Cell with a single tank and the glass melter. During recent pilot-scale operations, ammonium nitrate (an explosive) and organic compounds accumulated in the IDMS SRAT/SME vessel vent system (not to be confused with the melter off-gas system). The accumulation was detected after loss of instrument-sampling capability on the vent lines due to pluggage of the small sampling lines. Further investigation revealed significant deposits consisting of ammonium nitrate mixed with organic solids in the ventilation lines. The accumulation of ammonium nitrate was observed after processing simulated sludge that included noble metals (palladium, rhodium, and ruthenium).^[1]

The implications for the feed preparation processes of the DWPF are:

- a potential explosion hazard from the accumulation of ammonium nitrate, and
- a potentially severe attainment reduction by the accumulation of organic solids.

As a result of these findings, a task force was chartered on December 12, 1991 (Appendix A) to develop and evaluate options to mitigate or eliminate the impact of sodium nitrite on the DWPF.

FIGURE 1. WASTE PROCESSING OVERVIEW

3.0 SUMMARY

3.1 TASK FORCE STUDIES

The Task Force completed its work on an ambitious schedule (one week) and presented its conclusions and recommendations to N. C. Boyter and R. T. Begley on December 19, 1991. WSRC-TR-92-67 (this report) documents the conclusions and activities of the Task Force. The Task Force recommendations emphasize minimizing technical risk but also consider schedule impact, cost, and attainment impact. Members of the Task Force unanimously agreed that these recommendations are the best path forward for further development and demonstration with minimal technical risk and with reasonable cost and schedule impact.

The Task Force evaluated 32 potential options for mitigating the impact of nitrite on DWPF. From this initial large set of alternatives, two options for the Chemical Process Cell (CPC) and four options for the Salt Process Cell (SPC) were judged to be of sufficiently high technical certainty that they were further developed and assessed in greater detail.

3.2 TASK FORCE RECOMMENDATIONS

3.2.1 Recommended Options for the Chemical Process Cell

It is recommended that *both* of the options below be pursued for the highest technical certainty of mitigating the accumulation of ammonium nitrate in the CPC by way of any ammonium generated in or transferred to the CPC:

- Scrub ammonia vapors from the CPC vessel vent system and vent the ammonia to the atmosphere through the pump pit recycle tanks.
- Accelerate development of a nitric-acid SRAT process to reduce the quantity of ammonium and hydrogen generated during the melter feed preparation processes.

3.2.2 Recommended Long-Range Options for the Salt Process Cell

For the highest technical certainty of mitigating ammonium production from the PHA feed to the DWPF, the Task Force recommends installing a corrosion-resistant (Type 304L or Type 316 stainless steel) facility to reduce the nitrite content of washed precipitate feed to $\leq 0.01M$, and operating the SPC without HAN. The new facility should be designed for maximum flexibility to reduce the nitrite concentration to $\leq 0.01M$ by any of the first three technologies listed below: radiolytic nitrite destruction, late (or final) washing of the stored precipitate, or "Just-In-Time" (JIT) precipitation.

Which of these three technologies is of highest technical certainty is not clear at this time. SRL priorities should be redirected to evaluate the technical uncertainties of these options, as well as the feasibility of a fourth option (also listed below) which would required several engineering changes in the DWPF. In the meantime, a "Workaround" option (Section 3.2.3) should be implemented in order to accomplish the scheduled hot startup of the DWPF in June 1994.

- Recommended Option 1. Allow *radiolytic destruction of nitrite* by long-term storage of the radioactive precipitate in corrosion-resistant (Type 304L or Type 316) stainless steel tankage. Allow the nitrite concentration to diminish to less than 0.01M before transferring the precipitate feed to the SPC. Discontinue adding HAN (no longer needed to eliminate nitrite) during Precipitate Hydrolysis in order to avoid generation of ammonium in the SPC.

This option would avoid the formation of ammonium nitrate and reduce the amount of organics transferred to the CPC. It was judged to have a technical certainty of about 90%.

- Recommended Option 2. Install a corrosion-resistant (Type 304L or Type 316 stainless steel) *late washing* facility. If deemed necessary, reprecipitate any dissolved cesium (from radiolytic solubilization of CsTPB during precipitate storage) with more sodium tetraphenylborate. Wash the precipitate to a nitrite concentration below 0.01M before transfer to the DWPF. Discontinue use of HAN during Precipitate Hydrolysis to eliminate generation of ammonium in the SPC.

This option would avoid the formation of ammonium ion from HAN and reduce the amount of organics transferred to the CPC. It was judged to have a technical certainty of about 70%.

- Recommended Option 3. Install a new corrosion resistant (Type 304L or Type 316 stainless steel) facility for "*Just-In-Time*" precipitation. Discontinue the use of the sodium nitrite corrosion inhibitor in the precipitation process. Wash the precipitate to reduce the nitrite and nitrate concentrations below 0.01M before transfer to the DWPF. Discontinue the use of HAN in Precipitate Hydrolysis to eliminate generation of ammonium in the Salt Process Cell.

"Just-In-Time" precipitation would reduce the storage time before transfer of the material to the DWPF, which would reduce benzene emissions in the Tank Farm and the quantity of organic irradiation products (ionic species and high-boilers) formed during the current two-year average storage time. This option would avoid formation of ammonium nitrate and reduce the amount of organics transferred to the CPC. It was judged to have a technical certainty greater than or equal to that of the current ITP process.

- A fourth option involved several *engineering changes in DWPF*, retaining the current tank farm operating strategy and use of HAN in the precipitate hydrolysis process. A chemical agent (base) would be added to raise the pH of the Precipitate Hydrolysis Aqueous product and convert ammonium ion to ammonia. Re-routing the Salt Process Cell vessel vent would allow *venting the ammonia* out the SPC independently of the CPC vent system. This option was judged to have a technical certainty of about 80% for mitigating the accumulation of ammonium nitrate in the CPC from the SPC operation, but it would do nothing to mitigate the quantity of organics transferred to the CPC. To address the organics a *physical separation of the organic solids* (settling followed by decantation) was included in this option. The technical certainty of the organics separation step was deemed to be about 75%, so that the technical certainty of the combined steps is about 60%.

3.2.3 Recommended Short-Term Workaround Option

Until a new corrosion-resistant facility can be installed, a "workaround" option is recommended to permit hot startup of the DWPF as scheduled for 6/94.

Workaround Option. Use the existing Type 304L stainless-steel precipitate pump tanks in the Interarea Transfer System (i.e., the Low Point Pump Pit and the Auxiliary Pump Pit) and the Hastelloy® (Cabot Corp.) C-276 Precipitate Reactor Feed Tank in the DWPF Salt Process Cell to store the precipitate as long as is necessary for radiolysis to reduce the nitrite concentration to 0.01M or less in the precipitate feed to the DWPF. Operate the SPC without HAN (no longer necessary).

This workaround option is judged to have a technical certainty >90%. It would permit the start of cold chemical runs in the DWPF, using a nonradioactive precipitate simulant containing a maximum of 0.01M nitrite, and it would permit hot startup with real waste precipitate by June 1994, on schedule. However, the DWPF would incur a severe attainment penalty until one of the long-term options (Section 3.2.2) comes online.

3.2.4 Actions Recommended for Immediate Implementation

The following actions are recommended for aggressive implementation to reduce the technical uncertainty remaining in the radiolysis option:

- Confirm the radiolytic destruction of nitrite by obtaining kinetic data of sufficient quality to design a nitrite radiolysis facility. The experiments should be done with a precipitate slurry containing Cs-137 and with a composition similar to that projected for Tank 49 to make the results applicable to real waste.
- Determine the forecasted Cs-137 concentrations for the existing In-Tank Precipitation schedule to use in sizing the radiolysis tankage.
- Appoint a Task Force to optimize startup attainment using the pump pits and the PRFT to implement either the radiolysis option or the late-washing option.
- Demonstrate the modified DWPF flowsheet at TNX at workaround nitrite levels (0.01 M) and long-term nitrite levels (0.00 to 0.01M) with simulated precipitate. In addition, perform bench-scale experiments with irradiated precipitate feeds without HAN.
- Provide design basis for CPC vent system ammonia scrubbers.
- Aggressively develop a nitric-acid sludge adjustment flowsheet.
- Determine the amount of any ammonium tetraphenylborate in real precipitate, either as a result of waste content or radiolysis reactions.
- Obtain corrosion data on Type 304L and Type 316 stainless steels in zero-nitrite washed precipitate.
- Obtain corrosion data in Shielded Cells on Type 304L and Type 316 stainless steels in samples of washed precipitate.

3.2.5 Results from Immediate Actions

Following the presentation (Appendix H) of options to mitigate the impact of nitrite on DWPF to senior SRS management, an aggressive team effort was implemented to assess the technical viability of destroying nitrite by radiolytic reactions. More detailed results will be documented later by the respective investigators. A synopsis of the results is included below.

- The G-value for nitrite destruction was found to be dose-rate-dependent in an unfavorable direction (i.e., the lower the dose rate, the lower the G-value). The G-value expected in the pump pit workaround option is about 0.25, reducing the attainment for this option to about 2% and increasing the size of the tankage required for the long-term radiolysis facility by 220%.
- The cesium-137 concentrations in Tank 49 will average about 24 Ci/gal for the first five years of DWPF/ITP operation, and are forecast to reach levels of as low as 10 - 12 Ci/gal.

- Ammonium ion is formed not only by decomposition of excess HAN, but also during irradiation of precipitate slurries that simulate the composition of the material transferred from Tank 48 to Tank 49.
- Radioysis products of the simulated slurries include ionic organic species (highly polar and water soluble), including formate, oxalate, and many as yet unidentified ionic organic species. Precipitate hydrolysis studies have found that copper catalyst activity is reduced when irradiated precipitate slurries are acid-hydrolyzed, requiring additional copper beyond the reference 400 ppm and causing concern about exceeding the solubility of copper in the borosilicate glass product. This concern is heightened by the longer storage times necessitated by diminishing G values (first item above). The reduced catalyst activity is believed to be the result of a complexing mechanism involving the organic ionic species and is an active area of research and development.
- The counterions formed from nitrite destruction include carbonate and hydroxide. This increases the formic acid requirement in the acid hydrolysis process, creating additional concerns about foaming (due to evolution of CO_2) in the Precipitate Reactor feed step and increased hydrogen generation rates in the CPC from the additional formic acid and formate in the PHA.

Based on these results and concerns, a major effort to assess the Late Washing option was initiated in late February, 1992. The late wash option considered most likely to be achievable by the 6/94 radioactive operation uses the Auxiliary Pump Pit Precipitate Tank as the wash tank. Late washing can address all these concerns by washing out the soluble species (assuming the ammonium in the spent wash is purged from the system before reprecipitating). The main technical uncertainties to be addressed were the crossflow filter performance and the impact of the spent wash on saltstone performance, two areas identified by the Nitrite Task Force.

4.0 SCHEDULE AND COST OF RECOMMENDED OPTIONS

This section summarizes the expected cost and schedule for the various options developed. More detailed schedule breakdowns are provided in Appendix E.

4.1 SALT PROCESS CELL OPTIONS

4.1.1 Radiolysis Facility

A Nitrite Radiolysis Facility (Section 3.2.2) is estimated to cost about \$35 to \$50 million and may take about 5 to 6 years to bring online. The cost estimate is based on a current project estimate of \$54 million for installing two 750,000 gallon stainless-steel low-level waste tanks in the waste management facilities. The low-level waste tanks do not include cooling coils or an inert-gas blanketing system.

4.1.2 Late Washing Facility

A Late or "Final" Washing Facility (Section 3.2.2) is estimated to cost about \$50 to \$100 million and will take about 6 to 8 years to bring online. The cost estimate is based on the project estimate of \$54 million for installing two 750,000 gallon stainless-steel low-level waste tanks plus cooling coils, inert gas blanketing, and allowances for adding a new crossflow filter cell, a nitrogen-inerted benzene stripping column, associated filtrate hold tanks, and sampling and analytical capability. These tanks do not include cooling coils or an inert-gas blanketing system.

4.1.3 Just-in-Time Precipitation

The cost and schedule for a "Just-in-Time" Precipitation Facility (Section 3.2.2) would be about the same as for a Late Washing Facility. The cost would be reduced significantly if it is possible to tie in to the crossflow filter cell and benzene stripping columns that are part of the ITP facilities.

4.1.4 Startup Workaround by Pump Pit Radiolysis

Only minor modifications are anticipated for the precipitate pump tanks to implement pump-pit radiolysis as a startup workaround (Section 3.2.3). The spare penetrations in the Low-Point Pump Pit (or the Auxiliary Pump Pit) would be extended prior to processing radioactive feed, to allow future tie-ins of the new long-term nitrite reduction facility with minimal radiation exposure. This option is estimated to cost about \$1 million and take about 14 months to complete.

4.1.5 Ammonia Venting and Organics Separation

The combined chemical and engineered solution (Section 3.2.2, fourth option) to vent ammonia from the SPC is estimated to cost about \$10 million and will take about 3 years to complete. Re-routing of the SPC vent would conflict with the current DWPF Integrated Cold Run schedule. The cost estimate stated here is an average of individual estimates made by members of the Task Force.

4.2 CHEMICAL PROCESS CELL OPTIONS

4.2.1 Ammonia Scrubbers

The CPC options to scrub ammonia (Section 3.2.1) are estimated to cost about \$5 million and would take about 27 months to complete. The switch to a nitric acid flowsheet, if found to be viable, would have minimal cost and schedule impact. The cost estimate stated here is an average of individual estimates made by members of the Task Force.

5.0 NITRITE AND AMMONIUM ION CHEMISTRY

5.1 NITRITE CHEMISTRY IN THE TANK FARM

In the Tank Farm, nitrite is present in the stored wastes and is also formed by radiolytic conversion of nitrate ion in the residual soluble waste. Sodium nitrite will be added to both the washed tetraphenylborate precipitate and the washed sludge waste to inhibit pitting corrosion.

Nitrite is decomposed by radiation when organic compounds (such as the potassium tetraphenylborate^[2] precipitate) are present. The loss of nitrite is proportional to the radiation dose and depends on the type and concentration of organic material present, but is independent of the nitrite concentration (i.e., the reaction is zero order in nitrite). Hence, there is a need to replenish the nitrite, and sodium nitrite will be added periodically to the stored washed precipitate in order to maintain the required level of pitting corrosion inhibitor in Tank 49. Additional details on pitting corrosion and inhibitor requirements are contained in Appendix C and additional details on radiolysis of nitrate and nitrite solutions are contained in Appendix D.

5.2 NITRITE CHEMISTRY IN THE DWPF

The washed precipitate will be reacted with formic acid and a copper catalyst in the SPC to convert the potassium tetraphenylborate mainly to benzene. At the same time, most of the nitrite ion in the washed precipitate will be converted to nitrous acid. Nitrous acid is very reactive and initiates chain reactions that produce organic compounds other than benzene, including tars and high-boilers. High-boilers, such as diphenylamine and biphenyl, are difficult to remove from the PHA. Tars are of such low volatility that they would not be removed from the Precipitate Reactor to any appreciable extent and could drastically foul heat-transfer surfaces within the PR.

To prevent the formation of tars and reduce high-boiler production in the PR, hydroxylamine nitrate (HAN) is added to the reaction. Nitrous acid reacts rapidly with HAN to generate nitrous oxide (N_2O), reducing the severity of reactions of nitrous acid with the organics. Although the production of tars and high-boilers could be controlled within acceptable limits for the SPC operation with HAN to destroy the nitrite, a significant quantity of high-boilers would still be present in the aqueous product. These high-boilers probably would be adsorbed on the solid sodium titanate and sludge particles.

5.3 SOURCES OF AMMONIUM ION

Ammonium ion can result from at least two and possibly three independent sources, as shown in Figure 2.

- Excess HAN added to destroy nitrite in the Precipitate Reactor (Section 5.2 above) eventually decomposes, yielding ammonium ion in solution. Under the acidic conditions (pH 3 to 4) in the PR, the ammonium ion remains largely dissolved in the PHA stream from the SPC.
- A second source of ammonium ion is the reaction of nitrate and/or nitrite ions in the PHA when it is combined with sludge containing formic acid in the SRAT and SME. If the sludge does not contain noble metals, the resultant slurry remains acidic (pH 4 to 5.5), and the ammonium ion remains largely in solution and is eventually fed to the glass melter. However, during IDMS runs with sludge containing noble metals, the formic acid was catalytically decomposed to hydrogen and carbon dioxide, increasing the pH of the slurry (in some cases to neutrality,

FIGURE 2. NITRITE & AMMONIUM CHEMISTRY

pH 7). The higher pH promoted ammonium ion conversion to dissolved ammonia, which was released to the vessel vent system (Figure 3). Although this source of ammonium ion is smaller than the HAN source, it is estimated to account for about 10% of the total potential ammonium.

- Some ammonium ion might be present in the stored salt cake used to produce the tetraphenylborate precipitate. Although this source is expected to be small compared to the first two sources, the Task Force agreed that *all* sources must be addressed to obtain a complete and technically certain solution to the ammonium nitrate problem.

FIGURE 3. AMMONIA EVOLUTION INTO CPC VENT SYSTEM

6.0 DESCRIPTION OF OPTIONS WITH HIGHEST TECHNICAL CERTAINTY

6.1 SALT PROCESS CELL: RADIOLYSIS FACILITY

6.1.1 Approach

Allow radiolysis reactions to destroy nitrite and reduce the nitrite concentration to less than 0.01M in the precipitate feed to the DWPF by storing the washed precipitate feed in corrosion resistant (stainless steel) tankage. The facility could be designed with sufficient capacity to eliminate the need for Tank 49 (including the operating costs, sampling requirements, and sodium nitrite inhibitor additions). An overview of the radiolysis option is depicted in Figure 4.

6.1.2 Process Details

Size the radiolysis facility to achieve an adequate supply of precipitate feed to DWPF with reasonable control of the nitrite concentration and radioactivity level of the precipitate transferred to the radiolysis facility. Operate the Salt Process Cell without HAN, based on data from scoping experiments that indicate HAN is not required in the SPC for nitrite concentrations $\leq 0.01\text{M}$.

6.1.3 Technical Certainty Rating

The Task Force rated the technical certainty of this option at $>90\%$.

6.1.4 Technical Certainties and Benefits

- No HAN would be needed in SPC, based on scoping experimental data. The annual cost savings from eliminating use of HAN in the DWPF is about \$750,000.
- Nitrite consumption has been demonstrated in laboratory experiments (irradiation in cobalt-60 facility).
- Would reduce organic carryover as well as eliminate the main source of ammonium nitrate.
- Facility could be sized to free Tank 49 for other uses and avoid continual additions of sodium nitrite inhibitor.
- Would have no impact on In-Tank Precipitation startup schedule.
- Would require no new chemical additions.

6.1.5 Technical Uncertainties and Risks

- Low Cs-137 concentrations in waste would increase radiolysis time and might impact DWPF attainment.
- Need to demonstrate precipitate hydrolysis process on irradiated feed without HAN. Earlier demonstrations with HAN showed problems with maintaining copper catalyst activity for phenylboric acid hydrolysis.
- Would not affect ammonium present in precipitate feed or mitigate ammonium generated in the CPC.

FIGURE 4. NITRITE RADIOLYSIS FACILITY

- The nitrite destruction rate may be sensitive to other variables including temperature, dose rate, and organic concentration.

6.2 LATE (OR FINAL) WASHING

6.2.1 Approach

Remove nitrite by reprecipitating* and rewashing small batches of ITP product in a new corrosion-resistant facility prior to transfer to DWPF (Figure 5). This option both addresses the ammonium nitrate issue and reduces the quantity of organics transferred to the CPC. It has been proposed several times in the past ten years, but the proposals did not include the required benzene stripping and nitrogen purging. The late washing option as presented here would be a new, large facility, but it might be possible to modify a pump pit to implement the wash and meet the 6/94 radioactive operation startup date.

6.2.2 Process Details

Current operating plans require storing the ITP washed precipitate in Tank 49 for an average of two years before it is transferred to S-area. During this storage, radiolysis would destroy about 15% of the tetraphenylborate, solubilizing some of the Cs-137 activity and generating various organic decomposition products. Radiolysis would also consume the nitrite corrosion inhibitor, necessitating its periodic replenishment, which would increase the sodium content of the S-Area feed by about 0.08M to 0.16M per year.

A new corrosion-resistant (Type 304L or Type 316 stainless steel) "late-washing" facility would be installed. The solubilized Cs-137 would be reprecipitated with sodium tetraphenylborate, combined with small batches of existing ITP precipitate, and washed in the new facility to reduce the nitrite concentration to less than 0.01M and remove the added sodium before transfer to the DWPF. Use of HAN in precipitate hydrolysis would be discontinued to eliminate generation of ammonium in the Salt Process Cell.

The "late washing" facility would essentially be a half-size ITP facility, consisting of:

- A source of sodium tetraphenylborate (NaTPB), oxalic acid, nitrogen, etc. (connected to current Cold Feeds, or a stand-alone supply).
- A filter cell (similar size to one of the current ITP filters).
- A nitrogen-blanketed benzene stripper column (similar to the current ITP "small" column).
- Filtrate tanks and analytical capability.
- Two stainless-steel, shielded, double-wall, inert-gas-blanketed tanks for reprecipitation and washing (fulfilling functions similar to those of Tanks 48 and 49).

*The need to reprecipitate soluble Cs-137 freed by radiolysis of the slurry should be carefully assessed.

FIGURE 5. LATE (OR FINAL) WASHING

The size of the two tanks would determine the batch size, and thus the number of cycles per year (e.g., approximately one cycle per month at 50,000 gal each). ITP could be operated per current plans, or all/part of the washing could be deferred to the new facility, or the corrosion inhibitor content of Tank 49 could be increased.

6.2.3 Technical Certainty Rating

The Task Force rated the technical certainty of this option at > 70%.

6.2.4 Technical Certainties and Benefits

- HAN would not be needed in the SPC, because nitrite would be <0.01M in S-Area feed.
- The ammonia and heavy-organics problems in the SPC should be eliminated.
- The required glass production would be reduced, because of the lower sodium content of the S-Area feed.
- Concern about eventually exceeding S-Area's limit of 0.45M sodium (because of inhibitor additions over an extended time) would be addressed.
- The amount of organic decomposition products in the feed to the SPC (resulting from radiolysis of tetraphenylborate during storage in Tank 49) would be reduced.
- Any concern about corrosion of Tank 49 would be decreased (if additional inhibitors were added for "comfort", or if less washing were done).
- ITP attainment would increase if some of the washing were deferred to the new facility.
- The new facility could partially utilize and/or duplicate the existing ITP design.
- No new chemicals would be required (although the amount of chemicals currently used would increase).

6.2.5 Technical Uncertainties and Risks

- The organic content (TPB-decomposition products) of the feed to Z Area would increase. The ability to produce acceptable quality saltstone would have to be investigated, demonstrated, and perhaps re-permitted.
- It is known that irradiated feed has a very different rheology (e.g., shear stress, viscosity, "pumpability") than does fresh precipitate. With irradiated feed, the ITP filter process design has been demonstrated only on a very limited basis (e.g., on a very small laboratory scale). Note that this concern is also valid for the current ITP process (see Section 8, Generic Recommendations).
- The late washing facility may increase ITP workload, and may require additional manpower and incur additional operating expense. The consumption of NaTPB would increase, as would the production of Saltstone (because of the increased volume of washwater) and the amount of benzene generated, which must ultimately be disposed of, possibly in the Consolidated Incineration Facility (CIF).

- If the Late Wash Facility is operated by ITP, the degree of coupling and the complexity of operations and communications between ITP and S Area may increase, because of the smaller inventory of washed feed available at any given time.
- The late wash would not remove ammonium ion if it were present in the salt waste and precipitated in Tank 48 as ammonium tetraphenylborate.
- The late wash would remove soluble ammonium ion only if the reprecipitation were not used and the ammonium were purged from the spent wash water.

6.3 "JUST-IN-TIME" PRECIPITATION

6.3.1 Approach

Perform essentially the same precipitation and washing process as planned for ITP in a new corrosion-resistant (stainless steel) facility but reduce the storage time. The precipitation and washing tank (Tank 48 analogue) would have capacity on the order of 0.5 to 1 million gallons, and the storage tank would have capacity of about 75,000 to 150,000 gallons. The facility would deliver feed with $\leq 0.01\text{M}$ nitrite to the DWPF SPC, which would be operated without HAN.

6.3.2 Process Details

The storage time of the precipitate would be reduced to about 2 to 5 months by the close-coupling of precipitation in the new facility to the DWPF operation. Tanks 48 and 49 would accept DWPF recycle or other wastes, which alleviates concerns about waste storage capacity during the DWPF startup. About 133,000 gallons of precipitate is to be generated every four months according to current operating plans for ITP. Current plans require storing the ITP washed precipitate in Tank 49 for an average of two years before it will be transferred to S Area. During the two year storage, radiolysis would destroy about 15% of the tetraphenylborate, solubilizing some of the Cs-137 activity, and generating a variety of organic decomposition products, including benzene, high-boilers, and ionic species (formate, oxalate, and other unidentified ions). Radiolysis would also consume the nitrite corrosion inhibitor, necessitating periodic replenishment with sodium nitrite and increasing the sodium content of the S Area feed by about 0.08 to 0.16 molar/year.

6.3.3 Technical Certainty Rating

The Task Force rated the technical certainty of this option as equal to or greater than that for the current ITP process.

6.3.4 Technical Certainties and Benefits

- Impact of irradiation on precipitate processing would be mitigated by the reduced storage time, because the amount of organic radiolysis products in the feed to the SPC would be reduced.
- No corrosion inhibitor would be required.
- The SPC ammonia and heavy-organics problems would be eliminated, and HAN would not be needed (because the S-Area feed would be $< 0.01\text{M}$ nitrite).
- Concern about eventually exceeding S-Area's limit of 0.45M sodium. (due to inhibitor replenishment over an extended time) would be relieved.

- Required glass production would be reduced (due to the reduced sodium content of the S Area feed).
- Benzene emissions from the Tank Farm would be reduced by shorter storage times.
- No new chemicals would be required.

6.3.5 Technical Uncertainties and Risks

- If the new stainless steel tanks are operated by ITP, the degree of coupling, and the complexity of operation/communications between ITP and S Area, would increase (due to the smaller inventory of washed feed available). This would be an important consideration for the startup period of DWPF and Tank Farm processing, but the schedule for implementation of this option is well beyond the 6/94 DWPF radioactive startup date.

6.4 CHEMICAL PROCESS CELL: AMMONIA SCRUBBERS

6.4.1 Approach

Design and install scrubbers on the Formic Acid Vent Condenser (FAVC) exit and the Recycle Collection Tank (RCT) vent to prevent any ammonia from reaching the Process Vessel Vent Header. Analyze for ammonia in the SRAT/SME off-gas using, if possible, the planned sample lines and analyzers for hydrogen. Modify the Process Vessel Vent Filter (PVVF) to allow water flooding and soaking for periodic removal of ammonium nitrate. A schematic overview of this option is shown in Figure 6.

6.4.2 Process Details

The scrubbed ammonia would be retained in the recycle waste liquid by operating the scrubber during the RCT neutralization. The ammonia would then be vented through the pump pit recycle tank vessel vents. Inspection and cleaning of the jumpers from the SRAT and SME to the FAVC and from the FAVC to the PVVH could be performed periodically. The scrubber water flow requirements are estimated to be small. However, there would be an attainment penalty associated with increased water load to the RCT, which is already an attainment bottleneck. The magnitude of the penalty needs to be assessed after the scrubber design is finalized, and the frequency and duration of scrubber operation are better defined. A potential workaround to avoid the penalty is to use the SMECT contents as the source of the RCT scrubber liquid. See also Section 8.7.

6.4.3 Technical Certainty Rating

The Task Force rated the technical certainty of this option at > 75%.

6.4.4 Technical Certainties and Benefits

- Water is effective for scrubbing ammonia gas.
- Have F & H Canyon experience with using scrubber jumpers.
- Have ability to remove, inspect, clean SRAT, SME, and FAVC jumpers and the PVVF.

FIGURE 6. CPC AMMONIA SCRUBBER JUMPERS

6.4.5 Technical Uncertainties and Risks

- Scrubber efficiencies are never 100% (but efficiencies in excess of 99% are readily achievable). See also Section 8.3.
- Possible environmental impact of ammonia release at pump pit.
- SME Condensate Tank (SMECT) equivalent in IDMS has been recently observed to operate alkaline, thereby releasing ammonia.
- Additional aqueous recycle would be sent to tank farm.
- Scrubber liquid would be routed through the RCT, which is expected to be a very busy vessel and a potential attainment bottleneck.

6.5 WORKAROUND OPTION FOR STARTUP: PUMP PIT RADIOLYSIS

6.5.1 Approach

Use the existing Type 304L stainless-steel precipitate pump pit tanks and the Precipitate Reactor Feed Tank (see Figure 7) for radiolytic nitrite removal to meet the 6/94 radioactive startup date, albeit with a severe attainment penalty until the radiolysis facility (or other long-term solution) comes on line.

6.5.2 Process Details

The precipitate feed to the DWPF would be stored in the two Type 304L stainless-steel precipitate pump pit tanks in the Interarea Transfer System (Auxiliary Pump Pit and Low Point Pump Pit) and in the Hastelloy® (Cabot Corp.) C-276 Precipitate Reactor Feed Tank (PRFT) in the Salt Process Cell for the time required for radiolysis to reduce the nitrite concentration to $\leq 0.01\text{M}$ in the precipitate feed to DWPF. The DWPF Salt Process Cell would be operated without HAN. Start DWPF Cold Chemical Runs on schedule with precipitate simulant containing a maximum of 0.01M nitrite.

6.5.3 Technical Certainty Rating

The Task Force rated the technical certainty of this option at $> 90\%$.

6.5.4 Technical Certainties and Benefits

- No HAN would be needed in SPC, based on scoping experimental data. The annual cost savings from eliminating use of HAN in the DWPF is about \$750,000.
- Essentially the same as the long-term option with high technical certainty for destroying nitrite.
- Nitrite consumption has been demonstrated in laboratory experiments (irradiation in cobalt-60 facility).
- Would reduce organic carryover as well as eliminate the main source of ammonium nitrate.
- Would have no impact on In-Tank Precipitation startup schedule.

FIGURE 7. PUMP PIT NITRITE RADIOLYSIS WORKAROUND

- Would require no new chemical additions.

6.5.5 Technical Uncertainties and Risks

- Low Cs-137 concentrations in waste would increase radiolysis time and might further impact DWPF startup attainment.
- Need to demonstrate precipitate hydrolysis process on irradiated feed without HAN. Earlier demonstrations with HAN showed problems with maintaining copper catalyst activity for phenylboric acid hydrolysis.
- Would not affect ammonium present in precipitate feed or mitigate ammonium generated in the CPC.
- The nitrite destruction rate may be sensitive to other variables including temperature, dose rate, and organic concentration.
- The Interarea Transfer Line is made of Type 304L stainless-steel (primary containment) and carbon steel (secondary containment). The adequacy of the carbon-steel secondary containment for transferring uninhibited precipitate feed needs to be assessed.
Note: this concern is also valid for any extended downtime in the current operating scheme.

7.0 DESCRIPTION OF OTHER OPTIONS FOR SALT PROCESS CELL

This section describes other options developed for the SPC to mitigate the ammonium nitrate and organics problems. These options were deemed to have technical certainties >50% but not as high as for the radiolysis option.

7.1 SPC MODIFICATIONS TO MITIGATE AMMONIUM NITRATE BY AMMONIA VENT

7.1.1 Approach

The current Tank Farm operating strategy and the hydroxylamine nitrate flowsheet for the Salt Process Cell is retained to mitigate nitrite. A combined chemical and engineered solution is used to deal with the ammonium formed from the HAN in the SPC, before transfer of the Precipitate Hydrolysis Aqueous (PHA) product to the PRBT. The SPC vent, which presently exits the Salt Cell Vent Condenser (SCVC) and flows into the Process Vessel Vent Header (PVVH), would be separated from the PVVH and routed to a new exhaust location (Figure 8). The Precipitate Reactor (PR) contents would be neutralized after the normal batch cycle, thereby releasing ammonia gas out the new exhaust vent. Since the ammonia coming off the Salt Cell would not contact nitric acid (HNO_3) fumes in the Chemical Process Cell (CPC) or PVVH, no ammonium nitrate would be formed from the SPC HAN source.

Because this approach does nothing to address the heavy organics carried into the CPC with the PHA product, a separate option was devised to work in conjunction with the SPC vent reroute. The organic solids in the PHA would be physically separated from the aqueous by settling and decantation. The organic separation option is discussed in Section 7.2, after the combined engineering and chemical option (below).

7.1.2 Process Details

HAN is presently used in the SPC (in conjunction with formic acid) to facilitate conversion of the nitrite ion to nitrous oxide (N_2O). This reaction is necessary to avoid, or at least minimize, a competing reaction in which the nitrite reacts in the presence of tetraphenylborate to form organic tars and high boilers. The high boilers can create tarlike compounds that cause fouling and pluggage problems in both the SPC and the CPC. HAN was chosen over other chemical candidates, and its nitrite destruction effectiveness has been proven in the Precipitate Hydrolysis Experimental Facility (PHEF) at TNX.

The SPC vent can be rerouted by utilizing existing spare lines that pass through the 221-S canyon wall and extend underground approximately 50 feet west of the building, where they are capped. These spare lines were initially installed for feeding the PR directly from the Low Point Pump Pit (no longer required with change to an in-canyon Precipitate Reactor Feed Tank). A new facility would be required to provide the motive force and filtration for this new vent. The facility would consist of a concrete structure, blower(s), filter(s), a new stack, and perhaps tie-ins for future benzene-abatement equipment. If direct release of the ammonia to the atmosphere proved unacceptable, then a catalytic converter could be added, which might then allow the vent to exhaust straight into the Zone 1 air tunnel, thereby eliminating the need for a new stack. An additional in-canyon HEPA filter would probably be added upstream of the new facility to allow easier access to and changeout of the new blower and filters, with minimal personnel exposure.

FIGURE 8. SPC VENT RE-ROUTE FOR AMMONIA

Under the present operating strategy, the PR is maintained acidic (pH 3 to 4) and the ammonium ion remains in the PHA that is transferred to the CPC. To liberate the ammonia from the PR, the pH of the PR contents would be raised by adding a base, probably lithium hydroxide (LiOH). Lithium has a lesser adverse effect on the glass (susceptibility to leaching) than does sodium or potassium. This adverse effect can be countered by increasing the amount of frit added to the glass, but this reduces the waste loading. The amount of LiOH required would have to be evaluated. There is also potential that lithium already present in the clean frit could be reduced or eliminated to minimize the added glass volume.

7.1.3 Technical Certainty Rating

The Task Force rated the technical certainty of this option at > 80% for mitigating the accumulation of ammonium nitrate. However, this option does nothing to reduce the amount of organics transferred to the CPC; that problem is addressed by the physical separation of organics (Section 7.2). If these two options are used together, the combined technical certainty diminishes to > 60% (Section 7.2.3).

7.1.4 Technical Certainties and Benefits

- Two spare lines are available to provide the path out of the canyon for the vent reroute.
- The Salt Cell vent reroute design has already been conceptualized for the benzene abatement proposal.
- The chemical liberation of ammonia gas by neutralization of the PHA has been demonstrated in the laboratory. Essentially all the ammonium ion can be released as ammonia, given enough time and an adequate increase in pH.

7.1.5 Technical Uncertainties and Risks

- The primary uncertainty would be the impact, if any, of the ammonia release on the environment and on obtaining an operating permit.
- Effectiveness of a catalytic converter, if required, is unproven.
- Additional glass production and operating costs because of the reduced waste loading from use of an alkali base to raise the pH.
- Potential impact on attainment from increasing the PR cycle to vent the ammonia.
- Initial consideration of exhausting the rerouted vent (no catalytic converter) into the Zone 1 air tunnel was rejected due to concern of ammonium nitrate accumulation in the Sand Filter. Hence a separate stack is required if a catalytic converter is not used.

7.2 PHYSICAL SEPARATION OF ORGANIC-COATED SOLIDS

7.2.1 Approach

Many of the options (e.g., see Section 7.1) mitigate accumulation of ammonium nitrate but not the transfer of organic high-boilers to the CPC. A separate option was therefore devised to reduce the quantity of high-boilers when used in conjunction with any of the other options. The organic-

coated solids in the PHA would be physically separated from the aqueous by settling and decantation. Known solids in the PHA include sodium titanate (or titanium dioxide after the PR processing), traces of sludge solids originally entrained in the salt/sludge separation in the Tank Farm, and solidified high-boilers, which may or may not be coated on the sludge and titanate. The solids would be routed to SME after the vessel is cooled and then transferred to the Melter Feed Tank (MFT) and the DWPF melter (Figure 9).

7.2.2 Process Details

After transferring two batches of PHA to the PRBT, the material would be sampled for process control analyses; then the agitator would be turned off and the solids allowed to settle. The aqueous phase would be transferred to the SRAT, as in the current operating scheme. The SME contents would be concentrated somewhat more than currently planned and after SME cool-down, the solids would be re-suspended in the PRBT and transferred to the SME. This should reduce the quantity of high-boilers stripped up into the CPC vessel vent system.

7.2.3 Technical Certainty Rating

The Task Force rated the technical certainty of this option at about 75%. When this option is used, together with the option discussed in Section 7.1, the overall technical certainty is about 60% (cf. Section 7.1.3).

7.2.4 Technical Certainties and Benefits

- A reduction in the quantity of organic high-boilers transferred into the boiling SRAT vessel.

7.2.5 Technical Uncertainties and Risks

- The reduction may not be sufficient to significantly increase attainment.
- Would not mitigate ammonium nitrate problem - must be paired with other option(s).
- Impact on cycle time not determined.
- Settling time for expected range of solids concentrations not determined.

FIGURE 9. PHYSICAL SEPARATION OF ORGANIC-COATED SOLIDS

SOLIDS TRANSFER TO SME

PHA TRANSFER TO SRAT

8.0 GENERIC RECOMMENDATIONS

This section presents recommendations that are common to many or all of the options considered by the Task Force.

8.1 REDUCING NITRITE IN THE PRECIPITATE

For a number of the options examined by the Task Force, it is desirable to reduce the nitrite concentration in the washed precipitate sent from the Tank Farm to the DWPF. In the option identified for startup (radiolytic reduction of nitrite in stainless-steel pump pit tanks and the PRFT), reducing the nitrite during the workaround period increases the rate at which precipitate can be fed to the DWPF. Increasing this rate is desirable for two reasons:

- Salt space in the Tank Farm is currently tight. Increasing the precipitate feed rate would increase the rate at which salt can be removed from the Tank Farm. Expeditious rates of salt removal are needed to meet regulatory and DOE requirements, and to ensure that sufficient space is available in the Tank Farms to receive new wastes (including DWPF recycle and Extended Sludge Processing wash water).
- Operating the DWPF at low rates would be economically unattractive because much of the operating costs are fixed.

With respect to reducing the nitrite in the Tank Farm, the Task Force makes the following recommendations:

- Additional washing in Tank 48 should be pursued to reduce the concentration of aggressive corrosion species, such as nitrate, and hence reduce the required level of nitrite corrosion inhibitor. The level of nitrite corrosion inhibitor could be lowered while retaining current safety margins. The additional washing could involve certain penalties, such as reduced ITP rate, increased Saltstone feed, and more frequent nitrite additions to Tank 49. The Task Force recommends that the SRL Corrosion Working group, chaired by D. T. Hobbs, determine the cost and feasibility of additional washing to various nitrite levels.
- Cooling of Tank 49 with chillers should be pursued since lower temperatures reduce the required level of nitrite. Chiller systems need to be designed with redundancy and other measures to ensure their reliability, since they will be needed to maintain the integrity of Tank 49.
- The monitoring of Tank 49 nitrite levels should be upgraded by improving sampling techniques, analytical capability, and adjustment of nitrite addition frequency. Sampling and nitrite additions are needed more frequently at low nitrite levels, since the rate of nitrite disappearance is fixed.
- Improved inspection techniques for detecting corrosion should be considered for Tank 49 because the tank will be operated at inhibitor levels lower than other tanks in the Tank Farm.

8.2 REWORKING THE PRECIPITATE

A plan needs to be developed for reworking precipitate in Tank 49 that cannot be processed through the DWPF. Plans are to store washed precipitate in Tank 49 for an average residence time of about two years before transfer to DWPF. Such precipitate might become unacceptable to DWPF if:

- An unanticipated DWPF downtime required storing precipitate for longer than two years (because periodic inhibitor additions during this time would raise the sodium level unacceptably or might produce an unacceptable amount of organic radiolysis products).
- An inadvertent inhibitor addition to Tank 49 or a problem in ITP caused salts to be added to Tank 49.

A limited amount of unpublished bench-scale data exists for filtration of two-year-aged, washed precipitate. The data, developed by D. D. Walker, suggest that aged precipitate will filter at an adequate rate. These data need to be published and/or supplemented with further experiments.

The following items also need to be addressed:

- Can Saltstone handle the degraded organics produced during two or more years of aging?
- What are the logistics of transferring a million-gallon batch of precipitate from Tank 48 to Tank 49 and washing it? Could the precipitate be washed in Tank 49 similarly to sludge, i.e., by letting the precipitate settle, decanting, adding water, and agitating?
- Related to the two items above, the flexibility of transfers and processing in Tanks 48 and 49 should be evaluated.

8.3 MITIGATION OF AMMONIUM NITRATE ACCUMULATION

Because it is unlikely that any of the options will completely eliminate all ammonium nitrate, and scrubber efficiencies approach but cannot achieve 100%, the following measures should be adopted:

- Inspect the Process Vessel Vent System routinely. Periodically remove vent jumpers, inspect for ammonium nitrate deposits, and flush if necessary.
- Develop capability to flood the Process Vessel Vent Filter (PVVF) if deposits of ammonium nitrate are found in the vent system.
- To inspect for ammonium nitrate accumulations downstream from the ammonia scrubbers, install inspection ports in the Process Vessel Vent Header similar to those installed in new plutonium vent systems.
- Analyze the gas stream for ammonia (perhaps using the sample lines and analyzers that are being installed for hydrogen monitoring). The most critical sample points for monitoring the potential accumulation of ammonium nitrate in the PVVH are regions downstream from the scrubbers.

- One other concern is that ammonium nitrate could accumulate in the DWPF sand filter, perhaps causing an accident that is not anticipated in the current Safety Analysis Report (SAR). Since the ammonium nitrate hazard cannot be completely eliminated, this should be addressed in the DWPF SAR and the DWPF Operating Safety Requirements.

8.4 NOBLE METAL TESTING

The inclusion of noble metals in the IDMS sludge feed simulant led directly to identification of several major technical issues for DWPF operation in advance of DWPF Integrated Cold Runs. The Task Force recommends that flowsheet levels of noble metals be included during a portion of the DWPF cold runs, perhaps by including noble metals as part of the waste simulant used for "mercury runs." The noble metals should be tested to demonstrate the ability of the DWPF to control the hydrogen and ammonium nitrate hazards before the facility processes actual high-level radioactive waste.

8.5 ORGANIC HIGH-BOILER CARRYOVER IN THE SALT PROCESS CELL

The option to physically separate the organic-coated solids from the aqueous material transferred to the SRAT may be viable with any of the other options developed. It should be pursued as a contingency option to provide additional mitigation of organic high-boiler carryover.

8.6 IMPROVING ATTAINMENT DURING PUMP PIT WORKAROUND

During a radiolysis "pump pit workaround" period, the precipitate feed rate will be limited by the storage time required to destroy nitrite by radiolysis. The Task Force has recommended a number of options that might allow increased precipitate feed rate, including (1) additional washing, (2) cooling of Tank 49, and (3) improved monitoring of nitrite levels in Tank 49.

The Task Force generated a number of other ideas to improve the workaround attainment but didn't include them in the final recommendations because they are not fully developed. However, for the benefit of future groups trying to optimize the workaround rate, these ideas are listed below:

- Radiation sources could be added to one or more of the Interarea Transfer System pump-pit tanks to increase the radiation dose rate. Some possible radiation sources are Cs-137 capsules at Hanford and the cobalt tubes stored in the SRS reactor areas. A good way to use these sources would be to construct a large metal tube in a pump tank, similar to a thermowell, into which the source would be inserted, so that the exterior of the source would remain uncontaminated. The design would include a mechanism for withdrawing the source from the pump tank into a shielded cask for maintenance work in the pump pit.
- An X-ray machine could be used to increase the dose rate instead of a radioactive source. Some specialty plastics are commercially cross-linked using X-ray machines at doses of up to about 8 megarads.
- The pump pit tanks could be enlarged, perhaps by making them square so that they would fill more of the pump pit.
- A soluble organic might increase the rate of nitrite destruction - for example, ethylene glycol (see Appendix D). The challenge is to find an organic that works at low enough concentration to avoid causing other problems in DWPF.
- One of the recycle pump pits could be converted to precipitate service.

- One of the tanks planned for the Hazardous Low-Level Waste Processing Tank project could be converted to high-level waste service. By making use of the existing project, it might be possible to accelerate the construction relative to a completely new tank project.
- The solids loading of precipitate in the Tank Farm could be increased, perhaps by settling in Tank 49 and decanting. This would increase the amount of potassium tetraphenylborate precipitate carried along with each pound of nitrite, effectively increasing the attainment of the entire process.
- The feed from the Tank Farm to the DWPF could be diluted in the Precipitate Reactor Feed Tank to reduce the nitrite concentration to 0.01M or less. This would allow feed from the Tank Farm to be received at the DWPF with nitrite concentrations in excess of 0.01M. This scheme would reduce the storage time required for nitrite radiolysis in the pump pit.*

8.7 DWPF RECYCLE TO TANK FARM

If implemented, the use of ammonia scrubbers in the CPC vessel vent system might increase the recycle stream flow back to the tank farm.

The adequacy of the Tank Farm to accommodate the DWPF recycle stream should be assessed as soon as the impact of the scrubbers on the recycle flow is defined. Consideration should be given to the needs and benefits of installing an evaporator for the DWPF recycle stream.

* For instance, if it were planned to dilute the feed in the PRFT by a factor of two, the DWPF could accept feed that had been stored only long enough to reduce the nitrite content to 0.02M or less, rather than to $\leq 0.01\text{M}$.

9.0 SUMMARY OF ALL OPTIONS CONSIDERED

9.1 PROMISING OPTIONS

9.1.1 Options That Eliminate Ammonium Formation in the SPC

OPTION 1: let radiolysis reduce nitrite to $< 0.01\text{M}$ during storage in stainless-steel vessels.

OPTION 2: remove nitrite in late washing facility (see also Options 4 & 5).

Both of the above were further developed because use of HAN would be eliminated and both address the organics problem.

9.1.2 Option That Deals with Ammonium Formed in the SPC

OPTION 3: neutralize (raise pH) of PR contents to evolve ammonia, and re-route SPC vent.

This option was selected for further development and supplemented with physical separation of the organic-coated solids to address the organics issue.

9.1.3 SPC Options That Close-Couple ITP to DWPF Operations

OPTION 4: "Just-in-Time" (JIT) precipitation in new stainless-steel facility.

Start ITP at the Tank Farm in smaller batches using a new stainless-steel facility just before DWPF startup. This could eliminate the need for a corrosion inhibitor and reduce the quantity of radiolysis organic products and benzene emissions by shortening the storage time. Option 4 would close-couple tank farm operation to the DWPF, creating a potential gridlock in Tank Farm, which needs to start up before DWPF to make room for the DWPF recycle stream. The gridlock could be offset by starting up ITP two years ahead of DWPF, as currently planned, and switching to JIT precipitation in the future, at which time Tanks 48 and 49 could be used to accept DWPF recycle waste. However, Option 4 could not meet the 6/94 radioactive operation startup date. Investment cost would be about equal to that of a Radiolysis Facility or Late Washing Facility; but Option 4 would not require any additional NaTPB. Technical certainty should be greater than or equal to the current ITP process because of the reduced storage time.

OPTION 5: "Just-in-Time" (JIT) precipitation, using both Tanks 48 and 49, together with a new, small stainless-steel tank for washing.

This option was proposed by L. Lee and was deemed to have higher technical certainty than Late Washing. Would operate at high ionic levels (5M Na , 0.15M NO_2^-) using both Tank 48 and 49 for precipitation and concentration. Under these conditions, NaTPB would be precipitated in crystalline form during storage. The impact from release of the irradiation products (biphenyl, terphenyls) during washing and filtering is the main technical uncertainty. Would close-couple tank farm operation to the DWPF, creating a potential gridlock in Tank Farm which Tanks 48 and 49 would not be available to alleviate, as they are in Option 4. However, this might become a very attractive option after the first five years or so of DWPF operation because of the ability to control sodium levels. On this basis, the radiolysis tank design should facilitate attachment of the crossflow filters for washing in a close-coupled operation.

This option was not further developed because of the degree to which ITP would be coupled to the DWPF during DWPF startup, as well as the similarity to Option 4.

9.1.4 Options That Deal with Ammonia Evolved in the CPC

OPTION 6: add ammonia gas scrubbers in FAVC and RCT vents, add flush system on PVV filter.

OPTION 7: run FAVC HEME spray continuously (instead of separate scrubber), add flush system on PVV filter

The scrubber option was selected because of the precedent and operating success in the Separations Canyons. Design considerations may dictate which is eventually selected to scrub the ammonia.

9.1.5 Option That Prevents Formation of Ammonium in the CPC

OPTION 8: use nitric acid in SRAT.

Data from a single bench-scale experiment suggest this would greatly minimize the amount of hydrogen and ammonium formed in the SRAT. But it would have no impact on the amount of ammonium formed in the SPC and vented in the CPC, or on the organics problem. This is recommended as an accelerated development program because of the potential benefits in the CPC.

9.1.6 Option That Reduces Organic Carryover in the CPC

OPTION 9: physically separate the organic-coated solids before transferring the PHA to the boiling SRAT vessel and route them to the SME after cooldown. This entails allowing the solids to settle and decanting the clear aqueous phase to the SRAT.

This option was proposed by M. A. Baich. It does not address the ammonium nitrate problem but was deemed to have about 75% technical certainty for mitigating the organic carryover into the CPC vessel vent system.

9.2 REJECTED OPTIONS

Twenty-three other options were considered. Most addressed only a part of the problem. Many would require extensive research and development prior to implementation. All were deemed to have technical certainties < 50% and were therefore rejected.

OPTION 10: use steam/cooling jackets around SRAT/SME vent jumpers.

Partially addresses the organic problem, but only shifts the ammonium nitrate problem further downstream because it is a solid with finite vapor pressure.

OPTION 11: use absorber for ammonium (in liquid phase) or ammonium nitrate (in gas).

No "getters" for liquid-phase ammonium are currently identified; whatever chemical agent is used would require extensive testing to determine process impact. Relying solely on gas scrubbers would probably involve large equipment.

OPTION 12: incorporate explosion-proof design, rupture disc.

Unknown impact of explosion on performance of sand filter. Changes would be very extensive, probable negative perception problems.

OPTION 13: add flush system on PVV header.

Uncertain what amount of ammonium nitrate buildup would be acceptable (if any) on the PVV filter or downstream (all the way to the sand filter). Probable major attainment loss to conduct the flush operation, "in-cell" changes would be extensive. Organics not mitigated. Flushing the PVV filter is recommended in conjunction with other options.

OPTION 14: catalytic combustion of ammonia.

Many of the possible catalysts are poisoned by mercury, no workable catalyst currently identified. Requires invention and lengthy demonstration.

OPTION 15: reroute the CPC vent.

Ammonium nitrate would still be formed in the new vent system. Preliminary calculations indicate that although ammonium nitrate has a significant vapor pressure, the air flow is not high enough to prevent accumulation (even in the sand filter).

OPTION 16: install ammonia gas scrubber in SPC vent.

Would neutralize the PR to evolve the ammonia, then scrub it as ammonium ion. Problem is where to route the scrubbed ammonium since benzene can potentially be present. Does not address the organic problem, or the ammonia formed in CPC.

OPTION 17: maintain acidic pH in SRAT.

Ammonium would be routed to melter (instead of being converted to ammonia and then being released to the vent system). No currently identified/demonstrated method is available to accomplish this; even when using nitric acid instead of formic acid (see Option 8), some pH rise would still occur.

OPTION 18: dewater PHA in PR and route PRBT to SME after cooldown.

Suggested by L. Lee and has previously been evaluated separately. A lengthy list of questions and uncertainties need to be addressed on this proposal. The Task Force did not review Lee's latest "response/rebuttal". Transfer of frit to SRAT was later found to be physically intractable.

OPTION 19: replace HAN with sulfamate or some other alternative.

OPTION 20: reduce HAN usage by supplementing with sulfamate, etc.

While partial substitution may be possible, glass quality limits on amount of sulfur and/or sulfate deposition in the melter off-gas system would prohibit totally replacing HAN with sulfamate. No other alternatives are currently identified; implementation depends on invention. Alternatives require extensive testing to determine process impact.

OPTION 21: reduce HAN usage to achieve an acceptable level of ammonium nitrate.

OPTION 22: don't use any HAN (but this would foul terribly).

It is uncertain what amount of ammonium nitrate buildup would be acceptable (if any). Would aggravate the organic problem. Could be used to help reduce quantity of ammonium in conjunction with other options (ammonia scrubbers).

OPTION 23: eliminate nitrite and/or nitrate, or ammonium (e.g., by chemical oxidizer or electrolytic cell).

No method has been identified to accomplish this without also attacking the precipitate and generating tars, high-boilers, and oxidation products.

OPTION 24: operate at higher concentration of precipitate solids (and then dilute supernate in PR).

Increasing the solids significantly would greatly affect the rheology (e.g., "pumpability"), at least with fresh precipitate (as it would be if this were accomplished in ITP). Supernate could be decanted from aged precipitate in Tank 49, but it would contain high levels of cesium and organics (see Late Washing, Sections 4.1.2 and 6.2, and Option 2). Probably can't reduce nitrite from expected levels (~ 0.08M) to the required value (< 0.01M).

OPTION 25: minimize nitrite by additional washing.

OPTION 26: minimize nitrite by cooling waste tanks with chillers.

OPTION 27: minimize nitrite by sampling with on-line analysis and using more frequent but smaller inhibitor additions.

Additional washing would reduce the nitrate level, thus reducing the nitrite requirement. Cooling the waste tanks would reduce the corrosion rate, also reducing the nitrite requirement. Obtaining more current sample results (without the drawbacks of the current sample method) would allow minimizing the amount of excess nitrite currently used.

While all these methods would have a desirable effect, they are not deemed to be sufficient to eliminate the problem (i.e., to reduce the nitrite to <0.01M). Depending on these "active" measures (especially chillers, samplers, analyzers) would necessitate a significant degree of redundancy to ensure reliability. The consequences of "failure" would be pitting failure of Tank 49 (not simply a batch to be reprocessed).

These steps could be utilized in conjunction with the other recommended long-term solutions to minimize the size of the new facilities and maximize the startup attainment, and are therefore included in the Generic Recommendations (Section 8.1).

OPTION 28: minimize nitrite by inhibiting with hydroxide (could use LiOH).

Corrosion experts believe an oxidizing inhibitor is required so hydroxide could not be the sole inhibitor. Both hydroxide and nitrite are consumed by radiolytic reactions, so the sodium/lithium addition would actually increase (tending towards impacting glass formulation).

OPTION 29: use additional washings/cooling, to some level where inhibitor is not required.

Technical basis is lacking for operating without a corrosion inhibitor. Current inhibitor requirements allow for the presence of a certain amount of "other" aggressive anions (e.g., chloride, sulfate, fluoride), plus additional nitrite based on the amount of nitrate. With additional

washing, all these anions could be removed to any desired extent. However, this would not eliminate the need for some form of corrosion inhibitor, as even pure water is corrosive to carbon steel.

OPTION 30: use an alternative/supplemental inhibitor (chromate, molybdate, borate).

All identified alternatives are also expected to be affected by the organic decomposition/radiolysis products and many of these would impact glass quality.

OPTION 31: use a "non-chemical" corrosion inhibitor (e.g., cathodic protection).

Cathodic protection has previously been investigated and been ruled impractical (by the experts), due to the physical complexity of the waste tanks.

OPTION 32: set corrosion allowance for Tanks 48 and 49 (i.e., set their lifetime).

Without an inhibitor, the corrosion rate would be excessive (a matter of months for pits to penetrate the tank wall). Thus this is not a viable option (as it might be if the tank life were to be measured in years).

REFERENCES

1. J. T. Carter, D. H. Miller, R. E. Eibling, L. M. Lee, L. F. Landon, and J. C. Marek. **Recommendations for Control of Ammonium Nitrate Deposits in the DWPF Process Vessel Vent System.** WSRC-RP-91-1174, Westinghouse Savannah River Company, Savannah River Site, Aiken, SC (November 21, 1991).
2. D. D. Walker and B. S. Johnston. **Radiolytically Induced Changes in the Concentrations of Nitrate and Nitrite Ions in Potassium Tetrphenylborate Slurries.** DPST-86-716, E. I. Du Pont de Nemours and Co., Savannah River Laboratory, Aiken, SC (October 14, 1986).
3. M. Daniels and E. E. Wigg. **Radiation Chemistry of the Aqueous Nitrate System. I. Gamma Radiolysis of Dilute Solutions.** *J. Phys. Chem.* **71**, 1024 (1967).
4. M. L. Hyder. **The Radiolysis of Aqueous Nitrate Solutions.** *J. Phys. Chem.* **69**, 1858 (1965).
5. D. D. Walker. **Benzene Distribution in Product Streams From In-Tank Processing.** DPST-86-390, E. I. Du Pont de Nemours and Co., Savannah River Laboratory, Aiken, SC (January 15, 1987).
6. N. E. Bibler, personal communication.
7. D. D. Walker and B. A. Hamm. **Material Balance and Planned Operating Schedule for the In-Tank Process (U).** WSRC-RP-89-1303. Westinghouse Savannah River Company, Savannah River Site, Aiken, SC (December 27, 1989).

APPENDIX A. NITRITE TASK FORCE CHARTER

Appendix A displays the authorization letter for establishment of the Nitrite Task Force. The letter outlines the problem, indicates the goals to be accomplished and the schedule to be followed, and lists the membership of the task force.

**Westinghouse
Savannah River Company**

PO Box 616
Aiken, SC 29802

WSRC-TR-92-67, Rev 0 p. A-2

WSRC-TR-91-664

Keywords: Nitrite; DWPF

cc: N. C. Boyter, 703-A
R. T. Begley, 773-A
R. Miller, 241-120H
C. Baker, 241-120H
D. L. Fish, 773-A
L. F. Landon, 704-T
H. H. Elder, 704-S
J. A. Gentilucci, 704-S
M. J. Plodinec, 773-A
J. T. Carter, 704-1T
C. B. Jones, 719-12A
J. M. McKibben, 704-S
SRL Records (4), 773-A

December 11, 1991

D. B. Amerine, Manager/DWPF
G. T. Wright, Manager/Waste Management
L. M. Papouchado, Acting Manager/DWP & HT-SRL

TASK FORCE TO MITIGATE/ELIMINATE THE IMPACT OF SODIUM NITRITE ON THE DWPF

Process simulations in the Integrated DWPF Melter System (IDMS) at TNX have revealed the accumulation of ammonium nitrate (a known explosive) in the process vessel vent system during melter feed preparation processes as well as several operational problems due to the accumulation of non-polar organics. The presence of the non-polar organics in the precipitate hydrolysis aqueous product (PHA) are a direct result of the corrosion inhibitor (sodium nitrite) added during In-Tank Precipitation to prevent pitting corrosion of the carbon steel waste tanks (Tanks 48 and 49). With the nitrite present, it is necessary to use hydroxylamine nitrate (HAN) in the DWPF Precipitate Hydrolysis Process to minimize the production of tars and non-polar organics; however, the HAN results in the formation of ammonium nitrate in the DWPF Chemical Processing Cell. The greater the nitrite concentration, the

Authorized Derivative Classifier

greater the concentration of organics and ammonium ion in the PHA sent to the Chemical Process Cell. Without nitrite in the precipitate feed no HAN is needed in the Salt Processing Cell (SPC); the hydrolysis process thus produces PHA containing no ammonium ion and extremely low concentrations of non-polar organics.

Accelerated process and equipment development have been in progress by SRL; however, a straightforward chemical "fix" in the DWPF process alone, has not surfaced. At this time, it appears that the resolution of this problem will require process/equipment modifications in both ITP and DWPF. To provide the best and most balanced path forward to resolution of this issue, the subject task force is being assembled to apply their expertise and technical judgement. Attachment 1, provides the definition of the task. Attachment 2 provides the current options logic diagram developed by DWPT for the DWPF process. Attachment 3 provides the current options chart for the Tank Farm Processes. Attachments 2 & 3 should be treated as a starting point by the team.

The Task Statement in Attachment 1 should be reviewed by the Task Force at their first meeting scheduled for December 12, 1991, 8:00 am in the 704-T Exhibit Room at TNX. At 10:00 am Dick Harral, Walt Tamosaitis, Joe Ortaldo, and Bill Holtzscheiter will join the Task Force meeting to address questions, clarifications, and modifications to the Task Statement in Attachment 1. For the remainder of the year, the Conference Room in 679-T at TNX has been reserved for the use of the Task Force.

The Task Force recommendations, as presented on the 19th of December, 1991 will be incorporated into the SRL, DWPF, and ITP Programs. The progress, will then be monitored in the Plan of the Week meetings of both DWPF and SRL. The success of this effort is key to providing a good and operable process for the DWPF Salt Processing Cell and to the timely removal and processing of salt currently stored in the Tank Farm.

R. W. Harral, Manager
Waste Management-Technical

J. F. Ortaldo, Manager, DWPF
Technical & Engineering

W. L. Tamosaitis, Manager
Interim Waste Technology
Savannah River Laboratory

E. W. Holtzscheiter, Manager
Defense Waste Processing Tech.
Savannah River Laboratory

TASK FORCE TO MITIGATE/ELIMINATE THE IMPACT OF SODIUM NITRITE ON THE DWPF

Purpose:

This team is formed of the minimum number of experts in the required disciplines to rapidly evaluate options for mitigating or eliminating the impact of nitrite on the DWPF operations. The team's recommendations should provide a balance of technical risk, schedule attainment, and cost. The result of this effort is to provide the best path(s) forward for further development and demonstration. This result will also provide the basis for prioritizing the development and project expenditures.

Required Product and Deliverables:

1. Verbal presentation of the Task Force's evaluation of the options that the site has to mitigate or eliminate the impact on the DWPF of sodium nitrite introduced as a corrosion inhibitor in the tank farm. The options evaluations should include discussion of relative merit of the options and recommendations.

This presentation has been scheduled with Mr. Begley and Mr. Boyter for December 19, 1991 12-2 pm in 773-A , Conference Room A224.

2. Written report of the Task Force's evaluation of options and presentation of recommendations discussed in item 1 above should be complete 1/10/92.

Process:

The evaluations of options should include the following:

- Review of the options evaluations prepared by SRL/TWT and SRL/DWPT. The options should be reviewed for completeness and revised and augmented as appropriate.

- Evaluation for 1) technical risk/feasibility, 2) ability to meet 6/94 DWPF radioactive start-up milestone or realistic but fast-track alternate start-up date, 3) cost impact. Relative ratings should be reported for each option and for each of the above parameters.
- Resources outside the Task Force membership can be utilized via the appropriate L-3 Manager.
- Recommendations for paths forward based on the combined technical expertise of the team.

Resources:

The following team of experts will be placed on full time special assignment effective December 12, 1991 through January 3, 1992. Vacation schedules should be adjusted to allow 100% of your time starting December 12, 1991 through December 19, 1991. Finalizing the report can be accomplished by all or part of the team allowing appropriate celebration of the holiday period.

Chairperson: Jim Marek/DWPT	Precipitate Hydrolysis
Doug Walker/IWT	In-Tank Precipitation
Dave McGuire/DWPF	DWPF Technical/Salt Cell
Jack Nelson/Bechtel	Waste Mgt & DWPF Projects
Phil Zapp/MTS	Corrison-DWPF & Waste Mgt
Doug Brown/WM	ITP-Waste Management
Denny Bickford/DWPT	Glass Quality
Paul D'Entremont/WM	Waste Management-Tech.
Jim McGlenn/WM	Waste Management-ITP Ops

Other Resources:

As indicated previously, other expertise will be provide as required through the appropriate L-3 Managers in DWPF, WM, SRL.

ATTACHMENT 2
Options Chart for DWPF

OPTIONS TO ELIMINATE NH_4NO_3 ACCUMULATION IN DWPF CPC VENT SYSTEM

ENGINEERED SOLUTIONS TO ELIMINATE NH4NO3 CONTRIBUTION FROM PRECIPITATE HYDROLYSIS PROCESS

CHEMICAL SOLUTIONS TO ELIMINATE NH_4NO_3 CONTRIBUTION FROM PRECIPITATE HYDROLYSIS PROCESS

CHEMICAL/ENGINEERED SOLUTIONS TO ELIMINATE NH₄NO₃ CONTRIBUTION FROM FROM PRECIPITATE HYDROLYSIS PROCESS

ATTACHMENT 3

Options Chart for ITP

OPTIONS/PATH FORWARD

ENGINEERING	CONCERNS
o Additional washing	storage, attainment, \$\$
o Lower temperature	\$\$, min.temp?
o On-line inhibitor control	Feasible?, \$\$ schedule
o Late washing	\$\$, 2nd ITP
o Stainless steel tanks	\$\$, schedule, site
CHEMISTRY	
o Change inhibitor	major DWPF process impact
COMBINATIONS	
o Addn.washing/lower temp/change inhibitor	Under study
ION EXCHANGE	\$\$, schedule, unknowns

Options

Engineering

- Additional Washing
- Lower Temperature
- On-line Inhibitor Control
- Late Washing
- Stainless Steel Tanks

Chemistry

- Change Inhibitor

Combinations

- Additional Washing
Lower Temperature
Change Inhibitor

APPENDIX B. TASK FORCE RATING CRITERIA AND ASSESSMENT PROCESS

CRITERIA FOR INITIAL CUT

To be deemed worthy of further consideration, an option must be deemed to have a probability of success ("technical certainty") in excess of 50% (see Section 6 and Section 9.1). Other options are to be rejected (see Section 9.2) at this time.

OPERATIONAL, TECHNICAL, AND FINANCIAL CONSTRAINTS

The following general goals were established:

- The option **MUST** MITIGATE ammonium nitrate in the Chemical Process Cell vent system.
- It is **DESIRABLE** that the option **ELIMINATE** ammonium nitrate in the Chemical Process Cell vent system. The basis for the source terms was 90% of the total ammonium nitrate from the Salt Process Cell and 10% of the total from the Chemical Process Cell.
- The amount of non-polar organic high-boilers should be reduced.
- Schedule for radioactive operations: **MUST** by 7/95, **DESIRABLE** by 6/94.
- Cost must be minimized.
- Impact on attainment must be minimized.
- Need for new equipment must be minimized.
- Complex operations should be avoided.
- Coupling of Tank Farm and DWPF operations should be minimized.
- Integrity of waste tanks **MUST** be maintained.
- Environmental impact **MUST** be minimized. All provisions of the Federal Clean Air Act must be satisfied. All EPA, OSHA, and SCDHEC regulations must be complied with.
- Safety features of DWPF equipment and procedures **MUST NOT** be degraded. All DOE orders must be complied with.

ASSESSMENT PROCESS

After brainstorming 32 options to mitigate the impact of nitrite on the DWPF, the Task Force undertook exhaustive discussion about the relative merits, drawbacks, potential advantages, and potential pitfalls of each option. Detailed development and evaluation of all 32 options was not compatible with the time resources allocated to the Task Force. The options were thus screened, using an Adelphi statistical approach to distribute them into two categories according to whether the projected probability of technical success was greater than or less than 50%. This left the Task Force with two CPC options (vent system scrubbers and nitric acid sludge adjustment) and three SPC options (radiolytic nitrite destruction, late washing, and combined chemical and engineering SPC modifications to retain HAN and vent the ammonia). These options were then developed in greater detail as to their technical feasibility and risk, schedule, and cost.

"Just-in-Time" precipitation was not included in the original list of options because of the degree to which it close-couples Tank Farm operations to DWPF operations. It was incorporated after the Task Force presentation when it became apparent that if selected, Tank 49 (and perhaps even Tank 48) would be available to provide waste storage during the DWPF startup and thus alleviate the coupling somewhat.

The remaining options were assessed by individual vote of each Task Force member for their effect on the following:

- Probability of success
- Reduction of ammonium nitrate from the SPC source term
- Reduction of ammonium nitrate from the CPC source term
- Attainment
- Degree to which equipment changes would be required
- Degree to which coupling would be increased/decreased
- Waste tank integrity
- Degree to which additional red tape (environmental and safety-related paperwork) would be created
- Engineering and Project man-months
- Schedule for SRL Basic Data and Technical Development
- Schedule for Project Engineering and Construction.

The values reported in the text of this report are for the "Probability of Success" portion of the Task Force rating process. "Just-in-Time" precipitation by definition has technical certainty greater than or equal to the current ITP process.

After determining the probability of success for mitigating ammonium nitrate accumulation, the Task Force assessed whether the SPC options also mitigated the organic high-boiler carryover problem. Because the combined chemical and engineering approach to vent the ammonium formed from HAN would result in no appreciable decrease in the organic high-boilers, the Task Force supplemented this option with the physical separation of the organic-coated solids.

APPENDIX C. PITTING CORROSION AND ITS INHIBITION IN CARBON-STEEL WASTE TANKS

Dilute salt solutions containing tetraphenylborate solids are known to be corrosive to carbon-steel waste tanks. Under waste storage conditions, waste tank corrosion is inhibited with a high hydroxide concentration (1.0M). In ITP the hydroxide concentration is reduced by washing, by adsorption of atmospheric carbon dioxide, and by radiolysis. At the reduced hydroxide concentration, the tank wall and cooling coils become vulnerable to pitting.

Initially it is the steel immediately above the solution-air interface that is subject to pitting. An aqueous film develops on the steel and rapidly absorbs atmospheric carbon dioxide, which reacts with hydroxide to form carbonate and bicarbonate. Since the transport of hydroxide from the bulk solution into the film is very slow, the concentration of hydroxide is depleted and the pH drops to a steady-state value of about 9.5 in several hours from an initial pH of about 12 after washing. The pH of the bulk solution reaches 9.5 during the 2-year storage of washed precipitate slurry in Tank 49. Therefore, in the absence of other inhibitors, all wetted steel surfaces of that tank might eventually be attacked.

Five inhibitors were identified that can protect carbon steel from pitting when exposed to washed precipitate slurries. These were hydroxide, nitrite, chromate, carbonate, and pertechnetate. Nitrite was selected to inhibit washed precipitate because it is readily available and was deemed compatible with the DWPF. Minimum nitrite concentrations were established for inhibiting pitting corrosion. It was determined that nitrate, chloride, fluoride, and sulfate are the corrosive species in this system, and these ions were found to function independently in promoting pitting. That is, the required nitrite inhibitor concentration depended only on the concentration of a particular corrosive ion, when the concentration of that ion exceeded a critical concentration. Nitrate is the dominant corrosive ion in "fresh" washed precipitate. From laboratory tests at 40°C, the required molar concentration of nitrite, including a safety factor, was found to depend on the nitrate molar concentration according to a polynomial expression:

$$[\text{NO}_2^-] = 0.014 + 1.4[\text{NO}_3^-] - 2.5[\text{NO}_3^-]^2 + 3.8[\text{NO}_3^-]^3$$

Nitrate is destroyed by radiolysis in Tank 49. As its concentration goes to zero, the dominant corrosive ion becomes sulfate. A constant nitrite concentration of 0.014M inhibits pitting under this condition at 40°C. The temperature dependence of the nitrite concentration required to inhibit pitting was investigated from 2°C to 60°C. The data were empirically fitted by the expression:

$$[\text{NO}_2^-] = 0.0056 e^{0.048T}$$

where T is the temperature in °C. Lowering the temperature of Tank 49 to 30°C leads to a 40% reduction in the nitrite requirement.

APPENDIX D. RADIOLYSIS OF NITRATE AND NITRITE SOLUTIONS

The radiolysis of aqueous nitrate and nitrite solutions has been extensively studied and the major features of this chemistry are well known.^[3,4] Recently, however, there has been renewed interest in nitrate and nitrite radiolysis in the presence of organic compounds. Organic compounds dramatically change the chemistry and lead to the formation of N_2O gas. This reaction is believed to have contributed to the formation of flammable gas mixtures (H_2 and N_2O) in Hanford's Tank 101-SY and has been investigated at the Savannah River Laboratory in relation to the storage of potassium tetraphenylborate slurries in the In-Tank Precipitation Process. The basic features of this chemistry are described below.

The primary reactive species from the irradiation of alkaline aqueous solutions are the aqueous electron and hydroxyl radical:

In the absence of organic compounds, nitrate ion reacts with the aqueous electrons to produce nitrite ion:

There is also a back-reaction of nitrite with the hydroxyl radical which can regenerate nitrate or slow the formation of nitrite:

The concentrations where Reaction (3) is balanced by Reaction (4) lie in favor of the nitrite ion. For example, if a 0.1M sodium nitrite solution is irradiated, no change is apparent in the nitrite concentration for doses up to 1000 megrads (within a few percent error). Similarly, irradiation of a 0.1M nitrate solution will produce 0.1M nitrite.

However, if organic compounds are present, it is found that both nitrate and nitrite disappear upon irradiation. Recent work has demonstrated that much of the nitrite is converted to nitrous oxide gas (N_2O), although some was previously observed to form nitrated organic compounds.^[5] The exact mechanism for N_2O formation is not known at this time but is being investigated at Argonne and at Savannah River. Results from Savannah River show that the production of nitrous oxide gas is a general reaction and occurs with a wide variety of organic compounds (Table I).

TABLE I. Organic Compounds Which Form N_2O Gas During Irradiation in the Presence of Nitrate Ion.

Sodium acetate	Ethanol
Sodium tetraphenylborate	iso-Propanol
Benzene	n-Butanol
Phenol	tert-Butanol
Tri-butylphosphate	Ethylene glycol
n-Paraffin	Dow Corning #544 antifoam
Acetone	Ethylenediaminetetraacetic acid (EDTA)
Methanol	Ion-exchange resin

N_2O does not appear to be formed in the presence of a few highly oxidized carbon species, such as carbonate and formate ions.

It has also been found that the rate of disappearance of nitrate is faster with organic compounds present than when they are absent. This is due to the scavenging effect of organics for hydroxyl radicals, which interferes with Reaction (4). This effect on nitrate radiolysis has been shown with several organic compounds, including formate ion, methanol, ethanol, and ethylene glycol.^[6]

The rate of loss of nitrite ion has been studied for potassium tetraphenylborate slurries simulating the washed precipitate from the In-Tank Precipitation process. The results are shown in Figure 1. The rate of the reaction appears to be independent of the initial nitrite concentration and dependent on the radiation dose and organic precipitate concentration. The results for a 10 wt% slurry show that nitrite is lost at 0.84 molecules per 100 eV of radiation energy deposited in the slurry (see figure below). Other tests have indicated that the rate of loss is directly proportional to the organic concentration. At the radiation levels expected in average washed slurry (36 Ci/gal), the rate of disappearance of nitrite is 0.010 molar/month. A earlier estimate of this rate was significantly lower (0.004 molar/month),^[2] but it was made by curve fitting of data from experiments with high nitrate concentrations (i.e., the rate of loss of nitrite was not measured directly due to the high rate of conversion of nitrate into nitrite). The data in Figure 1 is probably be more accurate since it was a direct measurement without nitrate present, similar to the situation that will exist in Tank 49 (washed precipitate storage). However, further measurements are recommended to obtain higher confidence in the rate and to ascertain what factors may affect the rate.

Loss of Nitrite From Radiolysis

APPENDIX E. SUMMARY OF OPTION PROJECT SCHEDULE ESTIMATES

Scope, cost estimates, and projected schedules are summarized below for three promising options previously discussed:

- Nitrite Radiolysis Facility (Section 6.1)
- Late (or Final) Washing (Section 6.2)
- Chemical Process Cell Modifications (Section 6.4).

Schedules are displayed in the five appended figures.

NITRITE RADIOLYSIS FACILITY

SCOPE: The Nitrite Radiolysis Facility will contain approximately one million gallons of double-walled, stainless-steel tankage. The facility will include transfer pumps, recirculating pumps or agitators for solid suspension, cooling coils for heat removal, inert gas blanketing facilities, off-gas filtering and monitoring facilities, slurry sampling facilities, leak detection facilities, and instrumentation. Size, shape, and location of this facility have not been determined at this time.

COST: The cost for these facilities is estimated to be in the \$35 to \$50 million range. This estimate is based on a current project estimate of \$54 million for installing two 750,000 gallon stainless-steel low-level waste tanks in the waste management facilities. These tanks do not include cooling coils or an inert gas blanketing system.

SCHEDULE: The overall schedule for the nitrite radiolysis facility is about five years. The critical path components of the schedule are:

PREPARE BASIC DATA REPORT 6 months

Include time for SRL to verify that feed with low nitrite ion can be processed and to measure rates of nitrite destruction.

DESIGN 12 months

This includes time for Process Hazards Reviews, quality assessments, preparation of piping and instrument diagrams, equipment specifications, and equipment and piping layout drawings required for permit application.

PERMIT APPROVAL 12 months

This includes six months for DOE review and approval and six months for South Carolina DHEC approval.

BASE MAT CONSTRUCTION 6 months

This includes clearing, excavating, relocating underground line/ductbanks, if required, and constructing the base mat.

TANK ERECTION BY SUBCONTRACTOR

12 months

This assumes award of the subcontract at the time the permit is approved and that the subcontractor can procure and fabricate the initial quantities of corrosion-evaluated material in the six-month period required for base mat construction.

LONG LEAD EQUIPMENT DELIVERY

18 months

This is a parallel critical path to the base mat construction/tank erection path. It assumes that bidding and bid approvals are in place and that awards can be made when the permit is approved.

FINAL CONSTRUCTION

12 months

This includes construction of the concrete vault walls and roof, backfilling around the vault, installation of equipment, installation of cooling water piping, process piping, inert gas blanketing, off-gas processing facilities, and electrical.

OPERATIONS TESTING

2 months

TOTAL TIME

62 months

In conjunction with the nitrite radiolysis facility, the spare penetrations in the low point pump pit or the auxiliary pump pit should be extended prior to processing radioactive feed. This will allow tie-ins for the new nitrite radiolysis facility to be made with a minimum exposure to radiation. It is estimated that this will cost less than \$1 million, and can be completed in the first quarter of 1993.

LATE (OR FINAL) WASHING

SCOPE: Nitrite will be removed by reprecipitating and rewashing small batches of ITP product in a new stainless-steel facility before transfer to the DWPF (see Section 6.2.1). Process details are discussed in Section 6.2.2.

COST: The estimated cost is in the \$50 to \$100 million range.

SCHEDULE:

SRL/Technical	1 to 2 years
Design/Project Engineering	about 2 years (Conceptual, Title 1 & 2)
Procurement/Construction	2 to 3 years
Checkout	<u>> 1 year</u>

TOTAL TIME

6 to 8 years (does not meet 6/94 date for radioactive startup)

CHEMICAL PROCESS CELL MODIFICATIONS

SCOPE: Replace vent line jumpers from the RCT and the FAVC with scrubber jumpers. Modify Process Vessel Vent Filter to allow periodic flooding to dissolve any ammonium nitrate deposits.

COST: The estimated cost is in the \$3 to \$5 million range. The estimate is an average of the individual estimates made by the members of the Task Team.

SCHEDULE: The overall schedule is approximately 2 years. The critical activities in the schedule are:

Develop Basic Data Report	6 months
Prepare design documents for Procurement	6 months
Procurement (assumes no major equipment is required)	6 months
Construct and install new scrubber jumpers	6 months
Operations Test	<u>3 months</u>

TOTAL TIME ***27 months***

COST AND SCHEDULE SUMMARY

READY FOR
RADIOACTIVE START*

\$ MILLION

OPTION

Nitrite Radiolysis

- Short Term

< 1

3/93

- Long Term

35-50

3/97

CPC Modifications

3-5

4/94

Target Radioactive Start is 6/94

* Assumes R&D start 1/92

Assumes no funding restraints

TASK FORCE - NITRITE IMPACT

NITRITE RADIOLYSIS SCHEDULE

Critical Path

LATE PRECIPITATE WASH SCHEDULE

TASK FORCE - NITRITE IMPACT

CPC OPTIONS SCHEDULE

Critical Path

RETAIN HAN AND VENT AMMONIA

Critical Path

APPENDIX F. SIZING THE NITRITE RADIOLYSIS FACILITY AND ATTAINMENT ESTIMATES FOR THE PUMP-PIT STARTUP WORKAROUND

This approach is discussed in Section 6.5, "Workaround Option for Startup: Pump Pit Radiolysis," and briefly mentioned as Option 1 ("Radiolysis of Nitrite") in Section 9.1.1. Two ways of implementing Option 1 are discussed below.

OPTION 1A: USE OF SINGLE LARGE TANK

Under this option, a single large, stainless-steel tank is constructed to hold the washed precipitate between Tank 49 and the DWPF. The tank is sized to hold the washed precipitate while radiolysis decomposes the nitrite. The size of the tank depends on the required feed rate to the DWPF, the nitrite concentration in the slurry from Tank 49, and the radioactivity level in the precipitate. The effect of these variables is shown in Table II, based on a nitrite decomposition yield of 0.80 molecules/100 eV (slightly conservative in comparison with the measured 0.84 molecules/100 eV cited on p. D-2).

TABLE II. Tank Size Required to Reduce Nitrite Concentration to Less than 0.1M

Required Tank Size (gallons) as a Function of Nitrite Concentration (M) in Tank 49

Nitrite (M):	<u>0.030</u>	<u>0.040</u>	<u>0.050</u>	<u>0.060</u>	<u>0.070</u>
Attainment = 405,000 gal/yr					
Cs-137 (Ci/gal)					
36	68,000	101,000	135,000	169,000	202,000
18	135,000	203,000	270,000	338,000	405,000
7.2	338,000	506,000	675,000	844,000	1,012,000
Attainment = 525,000 gal/yr					
36	88,000	131,000	175,000	219,000	263,000
18	175,000	262,000	350,000	438,000	525,000
7.2	438,000	656,000	875,000	1,094,000	1,312,000

The two attainment rates are based on ITP and DWPF plans. The current material balance for ITP shows a precipitate production rate of 405,000 gallons per year (at 75% attainment).^[7] This is 25% lower than the DWPF design basis of 525,000 gal/yr (at 75% attainment).

The nitrite concentration in Tank 49 is set by Operational Safety Requirements and depends on the temperature and nitrate levels in the slurry. The minimum nitrite requirements is 0.014M when no nitrate is present. By operational adjustments to In-Tank Precipitation (such as extra washing), the required level can approach 0.014M. The excess above 0.014M at which the Tank Farm will run will depend on the frequency of sampling and analysis, analytical errors, and the rate of change of the nitrite concentration. Table II covers the expected range of potential nitrite levels due to these factors.

Cesium-137 levels in waste will also vary. The current CPES* material balance would produce a washed 10 wt% precipitate slurry containing 36 Ci of Cs-137 per gallon.^[7] At lower cesium levels, the rate of loss of the nitrite would decrease. The effect on tank size of reductions of Cs-137 by as much as 80% are shown in Table II. It has been estimated from the volume of precipitate and the radioactivity levels in the waste process during the first five years of ITP operation that the average Cs-137 activity would be 23 Ci/gal, about 40% below the current CPES value.

OPTION 1B: STARTUP WITH AVAILABLE TANKAGE

Although it is unlikely that sufficient stainless-steel tankage could be built in time for the scheduled DWPF startup, it is possible to begin hot operations at a greatly reduced attainment by using currently available tankage. The available tankage consists of the two pump-pit tanks (working volumes of 4,700 gallons each) and the Precipitate Reactor Feed Tank (working volume 7,400 gallons). Precipitate could be transferred to these tanks and allowed to age while the nitrite decomposes, then sent to the Salt Process Cell. The workoff time for 16,800 gallons would be 9 days. The net attainment for the DWPF is shown in Table III. Very low attainment rates are possible, but they could be significantly increased by adding additional tankage.

TABLE III. Attainment Using Current Tankage

<u>Nitrite (M) in Tank 49</u>	<u>% Attainment*</u>
0.030	8.4
0.040	5.8
0.050	4.4
0.060	3.5
0.070	3.0

*Based on 23 Ci Cs-137/gallon of slurry,
100% attainment = 700,000 gal/yr

* CPES = Chemical Process Evaluation System, a Du Pont proprietary program.

APPENDIX G. CONCEPTUAL DESIGN OF A NITRITE RADIOLYSIS FACILITY

Bechtel

101525

Savannah River Site
BNISC DWPF
P.O. Box 116
New Eenton, SC 29809-0116

January 29, 1992

BD-14396

Mr. M. L. Stephenson
Senior Project Manager
Westinghouse Savannah River Company
Savannah River Site
Aiken, South Carolina 29801

SAVANNAH RIVER SITE - 200-AREA
DEFENSE WASTE PROCESSING FACILITY
CONTRACT AXC-1997-W JOB NO. 13239
S-1780 RELATED ACTIVITIES
BECHTEL NATIONAL, INC. SITE OFFICE (BNISO)
NITRITE RADIOLYSIS FACILITY, REACTOR SIZING STUDY

Dear Mr. Stephenson:

Enclosed is a study of reactor sizes for the Nitrite Radiolysis Facility. The study was done to determine the affect of the following parameters on the reactor size required:

1. Number of Reactors
2. Cesium Concentration in Precipitate Feed
3. Tank 49 Operating Temperature
4. Tank 49 Sample Cycle.

If you have any questions, please contact J. W. (Jack) Nelson, extension 7-2994.

Very truly yours,

SC Foelber

S. C. Foelber
Project Engineering Manager

SCF/JWN/phb

Enclosure

Bechtel National, Inc. Systems Engineers-Constructors

Mr. M. L. Stephenson
January 29, 1992
Page 2

cc: All w/encl.

WSRC

H. K. Bethmann
G. E. Meek
L. F. Landon (704-T)
J. C. Marek (704-T)
D. H. McGuire (704-27S)
PRC

BSRI

J. E. Crain

BNISO

D. L. Ketcham
J. W. Nelson

NITRITE RADIOLYSIS FACILITY
REACTOR SIZING STUDY

J. W. NELSON
BECHTEL NATIONAL, INC.

JANUARY 1992

NITRITE RADIOLYSIS FACILITY
REACTOR SIZING STUDY

TABLE OF CONTENTS

INTRODUCTION	1
BASES OF STUDY	1
SUMMARY	2
DISCUSSION	4
NITRITE CONCENTRATION VS TIME GRAPHS	
BLOCK FLOW DIAGRAM	FIG. 1
CONCEPTUAL LAYOUT PLAN	FIG. 2
CONCEPTUAL LAYOUT - SECTION	FIG. 3
CALCULATIONS	APPENDIX A
FORMULAE	APPENDIX B

NITRITE RADIOLYSIS FACILITY (NRF) REACTOR SIZING STUDY

INTRODUCTION

In December 1991, a task force was convened to address the problem of ammonium nitrate and non-polar organic accumulation in the TNX-IDMS Vessel Vent System and the potential impact on DWPF operation. The task force concluded that the major source of ammonium resulted from the destruction of nitrite in the precipitate feed using hydroxylamine nitrate (HAN) and the best way to minimize ammonium nitrate formation was to reduce the nitrite in the precipitate feed to DWPF. Feed with less than 0.01M nitrite can be processed without the use of HAN. This also will reduce the amount of non-polar organics produced.

Nitrite ion is used as corrosion inhibitor in the carbon steel Waste Storage Tanks, but nitrite ion is also destroyed by radiation in the presence of organic material.

The task force recommended that stainless steel reactors be installed between TK-49 and DWPF, to allow radioactivity to destroy the nitrite ion.

This study was done to determine the affect of the following parameters on the size of stainless steel reactors required:

1. Single Reactor vs Multiple Reactors
2. Cesium Concentration
3. Tank 49 Operating Temperature
4. Tank 49 Sample Cycle.

BASES OF STUDY

NRF Processing Rate - 42,500 Gal/Mon (75% of BDR)

MAX Nitrite in DWPF Feed - 0.01M NO₂

Transfer Cycles

NRF to DWPF	as needed, approximately 15 batches/month
TK-49 to NRF	2 batches/month

No. of Reactors	1, 2, 3
Cesium concentration	9.5 to 36 Ci/Gal.
TK-49 Sample Schedule	1 month & 3 months
TK-49 Temp.	40°C & 50°C

SUMMARY

SINGLE REACTORS VS. MULTIPLE REACTORS:

The number of reactors has a minor impact on the total volume required.

<u>Case</u>	<u>Cs</u> <u>Ci/Gal</u>	<u>TK-49</u> <u>Temp</u> <u>°C</u>	<u>TK-49</u> <u>Sample</u> <u>Cycle, Mon</u>	<u>NRF Reactors</u> <u>Required</u> <u>No. Gals.</u>	<u>Total</u> <u>Volume</u> <u>Percent</u>
1	36	50	3	1 200,000	100
2	36	50	3	2 95,000	95
3	36	50	3	3 62,000	93

CESIUM CONCENTRATION:

Cesium concentration in the feed has a major impact of volume required.

<u>Case</u>	<u>Cs</u> <u>Ci/Gal</u>	<u>TK-49</u> <u>Temp</u> <u>°C</u>	<u>TK-49</u> <u>Sample</u> <u>Cycle, Mon</u>	<u>NRF Reactors</u> <u>Required</u> <u>No. Gals.</u>	<u>Total</u> <u>Volume</u> <u>Percent</u>
2	36	50	3	2 95,000	100
4	23	50	3	2 120,000	126
5	19	50	3	2 140,000	147
6	13	50	3	2 170,000	179
7	9.5	50	3	2 200,000	210

Where 36 = Average All Waste
 23 = Average First 5 yr. Waste
 19 = Minimum First 5 yr. Waste
 13 = Minimum First 5 yr. Waste with 1.5X Safety Factor
 9.5 = Minimum First 5 yr. Waste with 2X Safety Factor

TK-49 OPERATING TEMPERATURE:

Operating Tank 49 at 40°C rather than 50°C would reduce the NRF volume required about 16 percent.

<u>Case</u>	<u>Cs</u> <u>Ci/Gal</u>	<u>TK-49</u> <u>Temp</u> <u>°C</u>	<u>TK-49</u> <u>Sample</u> <u>Cycle, Mon</u>	<u>NRF Reactors</u> <u>Required</u> <u>No. Gals.</u>	<u>Total</u> <u>Volume</u> <u>Percent</u>
2	36	50	3	2 95,000	100
8	36	40	3	2 80,000	84

TK-49 SAMPLE CYCLE:

Reducing the Tank 49 sample frequency from 3 months to 1 month will reduce the NRF volume about 21 percent.

<u>Case</u>	<u>Cs</u> <u>Ci/Gal</u>	<u>TK-49</u> <u>Temp</u> <u>°C</u>	<u>TK-49</u> <u>Sample</u> <u>Cycle, Mon</u>	<u>NRF Reactors</u> <u>Required</u> <u>No. Gals.</u>	<u>Total</u> <u>Volume</u> <u>Percent</u>
2	36	50	3	2 95,000	100
9	36	50	1	2 75,000	79

MINIMUM RECOMMENDED SIZE

Assuming that Tank 49 can be operated at 40°C and sampled once a month, and the NRF is designed for the average cesium expected in the first 5 years, then the recommended minimum size is 2-80,000 gallon reactors.

<u>Case</u>	<u>Cs</u> <u>Ci/Gal</u>	<u>TK-49</u> <u>Temp</u> <u>°C</u>	<u>TK-49</u> <u>Sample</u> <u>Cycle, Mon</u>	<u>NRF Reactors</u> <u>Required</u> <u>No. Gals.</u>
10	23	40	1	2 80,000

DISCUSSION

This study was done to show the impact of various parameters on the size of Nitrite Radiolysis Facility (NRF). Final sizing will be done later.

Flowsheet: For this study, the high nitrite precipitate feed would be pumped from TK-49 to the NRF via the existing Low Point Pump Pit (LPPP). Existing Inter Area Transfer Lines would be used from TK-49 to the LPPP. New underground lines would be required from the LPPP to the NRF. Spare penetrations exist in the LPPP.

Low nitrite precipitate feed would be pumped from the NRF to the Precipitate Reactor Feed Tank (PRFT) via the LPPP. The existing line from LPPP to DWPF would be used. See Fig. 1 for Block Flow Diagram.

TK-49 OPERATIONS

Current TK-49 operating philosophy, as understood by the writer, were used in this study.

They are:-

- o Minimum NO_2 concentration is 50% above minimum required as a corrosion inhibitor. Maximum NO_2 concentration is a function of the NO_2 destruction rate and the sample cycle. For the case where the minimum NO_2 is 0.036M NO_2 , the sample cycle is every three months and the NO_2 destruction rate is 0.01M NO_2 ; the maximum NO_2 is $0.036 + (3)(0.01) = 0.066\text{M}$.
- o Batches of washed precipitate are transferred from TK-48 to TK-49 three times a year. TK-49 has about two years of production stored in it. The impact of different NO_2 concentrations in TK-48 and TK-49 was not considered in this study.
- o The normal TK-49 sample cycle is three months, however, the affect of reducing the sample cycle to one month was studied.
- o The normal TK-49 operating temperature is 50°C, however the affect of reducing the temperature to 40°C was studied.

FEED RATE

The feed rate used in this study was 42,500 gals/month, which is 75% of the instantaneous rate in the Basic Data Report. For final design, it may be prudent to design the NRF for 100% of the BDR rate. This would allow the DWPF to operate for extended periods between shut downs.

TRANSFER CYCLES

Low nitrite feed is transferred from the NRF to the PRFT every 43 hours. High nitrite feed is transferred from TK-49 to the NRF twice a month. The transfer cycle would be coordinated with the TK-49 nitrite addition cycle, i.e., the TK-49 to NRF transfer would be done just prior to the addition of NaNO_2 to TK-49.

NRF OPERATION

The NRF reactors will initially be filled with feed from TK-49 at the minimum TK-49 nitrite concentration. When the nitrite level in the NRF reactors is less than 0.01M, feed to the DWPF will start. After 15 days, the second reactor will be filled from the first reactor and the first reactor will be filled from TK-49. For each case studied, the reactors are sized to ensure the feed transferred to DWPF is always less than 0.01M NO_2 .

The calculation for sizing the reactors and the resulting graphs were done using the EXCEL™ spread sheet program.

The calculated values for each case are included in Appendix A and the formulae used are included in Appendix B.

SINGLE REACTOR VS MULTIPLE REACTORS

Three cases were studied: 1, 2 and 3 reactors. The results of these studies are shown as Cases 1, 2, and 3. The nitrite concentration points for each period are the maximum at the start of each 15 day period. The total volume required for each case was essentially the same: 200,000 gallons for a single reactor; 190,000 gallons for two reactors; and 186,000 gallons for three reactors.

Increasing the number of reactors increases the costs, but also increases the operating flexibility and reliability. For the balance of this study, two reactors were used.

CESIUM CONCENTRATION

Cesium in the feed is the source of radioactivity which destroys the nitrite. The nitrite destruction rate is directly proportional to the cesium concentration. Since the nitrite destruction rate also affects the maximum nitrite concentration in Tank 49, the size of the Nitrite Radiolysis Reactors required is not inversely proportional to cesium concentration, but close.

The maximum cesium concentration used in the study was 36 Ci/Gal, the average of all salt waste in the waste tanks. This would require 2-95,000 gallon reactors. The minimum cesium concentration studied was 9.5 Ci/Gal, which is 1/2 the minimum concentration estimated for the salt to be processed in the first five years of operation. This would require 2-200,000 gallon reactors. See Cases 2, 4, 5, 6 and 7.

Conclusion: A realistic evaluation of cesium concentration is necessary to size the NRF reactors.

TANK SAMPLE CYCLE

If it is possible and practical to sample Tank 49 monthly as opposed to sampling every three months, the size of the reactors can be reduced about 20 percent. See Cases 2 and 9.

Conclusion: The feasibility of making this change should be investigated as soon as possible.

TANK 49 OPERATING TEMPERATURE

Decreasing the Tank 49 operating temperature from 50°C to 40°C will reduce the required NRF volume about 14 percent. See Cases 2 and 8.

Conclusion: The cost of adding chillers to the Tank 49 cooling system needs to be compared with the cost of a larger Nitrite Radiolysis Facility.

HYPOTHETICAL DESIGN CASE

This case is based on using the average cesium concentration expected in the first five years, operating Tank 49 at 40°C and sampling on a monthly basis. For this case, the NRF would require 2-80,000 gallon reactors.

Conclusion: The potential for significantly reducing the size of the million gallon stainless steel Nitrite Radiolysis Facility is great if a reasonable cesium concentration can be established and changing the operating philosophy of Tank 49 is possible.

PRELIMINARY CONCEPTUAL LAYOUT

A conceptual layout for a two reactor Nitrite Radiolysis Facility is shown in Figures 2 and 3. It is based on a Pump Pit configuration. The reactors are horizontal cylindrical vessels, permanently installed in the cells. Only equipment subject to failure, such as pumps, agitators, temperature sensors and level sensors, would be designed for remote maintenance. This equipment would be removed using an overhead crane, as currently done in the Low Point Pump Pit. The structure housing the crane would be designed with smooth interior walls to improve housekeeping.

The overhead crane would be used to replace jumpers in the diversion box. The conceptual layout shows an equipment decon/maintenance cell which may or may not be required.

Sample cells, closed loop heat exchangers and piping penetrations to the cells would be located in the operating corridor.

The rationale used to develop the conceptual layout was:

- o A long narrow facility could be located northeast of the Low Point Pump Pit. Only the treated effluent line and several storm drains would need to be relocated.
- o The existing spare penetrations from the LPPP precipitate cell are located in the east wall.
- o The reactors could be field fabricated during the same time frame as the cells and then lowered into the cell.
- o The elevation of the NRF can be raised. The only criteria is that the high point of the transfer lines between the NRF and the LPPP be in the diversion box. This could minimize dewatering the site during construction.
- o By using the existing LPPP precipitate pump tank to transfer feed from Waste Tank 49 to NRF and from NRF to DWPF, all precipitate transfer lines will continue to drain to LPPP.

NITRITE RADIOLYSIS FACILITY
REACTOR SIZING STUDY

NITRITE CONCENTRATION VS TIME GRAPHS

NRF REACTOR SIZE STUDY CASE 1

101525

NRF REACTOR SIZE STUDY CASE 2

CS Conc. = 36 Ci/Gal (Average all Waste).

NO₂ Destruction Rate = 0.01 M/Month

TK-49 Temp = 50°C

TK-49 Sample Cycle = 3 Months

TK-49 NO₂ Range = 0.036 to 0.066M

Process Rate = 42,500 Gal/Mon (75% BDR)

JWN 1/16/92

NRF REACTOR SIZE STUDY CASE 3

NRF REACTOR SIZE STUDY CASE4

Cs Conc. = 23.2 Ci/Gal. (Ave First 5 Years)
 NO2 Destruction Rate = 0.064 M/Month
 TK-49 Temp = 50°C
 TK-49 Sample Cycle = 3 Months
 TK-49 NO2 Range = 0.036 to 0.055M
 Process Rate = 42,500 Gal/Mon. (75% BDR)
 NRF Reactors 2-120,000 Gallons

NRF REACTOR SIZE STUDY CASE 5

Cs Conc = 19 Ci/Gal (Min First 5 Years)

NO₂ Destruction Rate = 0.053 M/Month

TK-49 Temp. = 50°

TK-49 Sample Cycle = 3 Months

TK-49 NO₂ Range = 0.036 to 0.052 M

Process Rate = 42,500 Gal/Mon (75% BDR)

NRF Reactors 2-140,000 Gallons

NRF REACTOR SIZE STUDY CASE 6

Cs Conc= 12.7 Ci/Gal, (Min First 5 Years with 1.5 Safety Factor)

NO2 Destruction Rate = 0.0035 M/Month

TK-49 Temp. = 50°C

TK-49 Sample Cycle= 3 Months

TK-49 NO2 Range 0.036 to 0.047M

Process Rate= 42,500 Gal/Month (75% BDR)

NRF Reactors 2-170,000 Gallons

NRF REACTOR SIZE STUDY CASE 7

Cs Conc = 9.5 Ci/Gal(Min First 5 years with 2X Safety Factor)

NO₂ Destruction Rate = 0.0026 M/Month

TK-49 Temp= 50°C

TK-49 Sample Cycle= 3 Months

TK-49 NO₂ Range 0.036 to 0.044M

Process Rate 42,500 Gal/Mon (75%BDR)

NRF Reactors 2-200,000 Gallon

NRF REACTOR SIZE STUDY CASE 8

Cs Conc. = 36 Ci/Gal (Average all Waste)
NO₂ Destruction Rate= 0.01 M/Month

TK-49 Temp= 40°C

TK-49 Sample Cycle= 3 Months

TK-49 NO₂ Range 0.029 to 0.059 M

Process Rate = 42,500 Gal/Mon (75% BDR)

NRF Reactors 2-80,000 Gallons

NRF REACTOR SIZE STUDY CASE 9

NRF REACTOR SIZE STUDY CASE 10

Cs Conc. = 23.2 Ci/Gal (Ave. First 5 Years)

NO₂ Destruction Rate = 0.0064 M/Month

TK-49 Temp = 40°C

TK-49 Sample Cycle = 1 Month

TK-49 NO₂ Range = 0.029 to 0.0354

Process Rate = 42,500 Gal/Mon (75% BDR)

NRF Reactors 2-80,000 Gallons

NITRITE RADIOLYSIS FACILITY
REACTOR SIZING STUDY

FIGURE 1	BLOCK FLOW DIAGRAM
FIGURE 2	CONCEPTUAL LAYOUT PLAN
FIGURE 3	CONCEPTUAL LAYOUT SECTION

BLOCK FLOW DIAGRAM NITRITE RADIOLYSIS FACILITY

- PUMP LOW NITRITE FEED FROM NRF-2 TO DWPF AS REQUIRED VIA THE PRECIPITATE PUMP TANK IN THE LOW POINT PUMP PIT
- FILL NRF-2 FROM NRF-1 ON A BI-WEEKLY BASIS
- PUMP FEED FROM TANK 49 TO NRF-1 VIA THE PRECIPITATE PUMP TANK IN THE LOW POINT PUMP PIT ON A BI-WEEKLY BASIS.
- WILL REQUIRE INSTALLATION OF SECOND PUMP ON THE LPPP PRECIPITATE TANK

FIG. 1

NRF CONCEPTUAL LAYOUT

FIG. 2

NRF CONCEPTUAL SECTION

FIG. 3

NITRITE RADIOLYSIS FACILITY
REACTOR SIZING STUDY

APPENDIX A
CALCULATIONS
NITRITE CONCENTRATION VS TIME

	D	E	F	G	H
1			NRF REACTOR SIZE STUDY CASE 1		
2			Cs Conc = 36 Ci/Gal		
3			NO2 Destruction Rate =0.01 M/Mon.		
4			Tk-49 Temp. = 50°C		
5			Tk-49 Sample Cycle = 3 Months		
6			Tk-49 NO2 Range 0.036-0.066 M		
7			Process Rate =42,500 Gal/Mon (75% of BDR)		
8			NRF Reactor 1-200,000 Gallons		
9					
10					
11	TIME	TANK 49	NRF TANK		
12	DAYS	M NO2	M NO2		
13	0	0.066	0.036		
14	15	0.061	0.031		
15	30	0.056	0.026		
16	45	0.051	0.021		
17	60	0.046	0.016		
18	75	0.041	0.011		
19	90	0.066	0.006		
20	105	0.061	0.007375		
21	120	0.056	0.008072656		
22	135	0.051	0.008164937		
23	150	0.046	0.007716162		
24	165	0.041	0.00678382		
25	180	0.066	0.005419289		
26	195	0.061	0.006855989		
27	210	0.056	0.007608791		
28	225	0.051	0.007750357		
29	240	0.046	0.007345631		
30	255	0.041	0.006452658		
31	270	0.066	0.005123313		
32	285	0.061	0.006591461		
33	300	0.056	0.007372368		
34	315	0.051	0.007539054		
35	330	0.046	0.00715678		
36	345	0.041	0.006283872		
37	360	0.066	0.00497246		
38	375	0.061	0.006456637		
39	390	0.056	0.007251869		
40	405	0.051	0.007431358		
41	420	0.046	0.007060526		
42		0.041	0.006197845		

	E	F	G	H	I
1			NRF REACTOR SIZE STUDY CASE 2		
2			Cs =36 Ci/Gal (Average all waste)		
3			NO2 Destruction Rate= 0.01 M/Mon.		
4			TK-49 Temp. = 50°C		
5			TK-49 Sample Cycle = 3 Months		
6			TK-49 NO2 Range = 0.036 TO 0.066 M		
7			Process Rate = 42,500 Gal/Mon (75% of BDR)		
8			NRF Reactors 2-95,000 gallons		
9					
10					
11					
12					
13	TIME	TK 49	NRF-1	NRF-2	
14	DAYS	M NO2	M NO2	M NO2	
15	0	0.066	0.036	0.036	
16	15	0.061	0.031	0.031	
17	30	0.056	0.026	0.026	
18	45	0.051	0.021	0.021	
19	60	0.046	0.016	0.016	
20	75	0.041	0.011	0.011	
21	90	0.066	0.006	0.006	
22	105	0.061	0.014421053	0.001	
23	120	0.056	0.019840028	0.002107341	
24	135	0.051	0.022928443	0.00331948	
25	150	0.046	0.024207607	0.00401031	
26	165	0.041	0.024082221	0.004296438	
27	180	0.066	0.022866461	0.004268392	
28	195	0.061	0.027514753	0.003996445	
29	210	0.056	0.030004874	0.005036195	
30	225	0.051	0.030819573	0.005621294	
31	240	0.046	0.030333616	0.006257751	
32	255	0.041	0.028837939	0.006643142	
33	270	0.066	0.0265584	0.006607768	
34	285	0.061	0.030380863	0.006070409	
35	300	0.056	0.03222988	0.006508274	
36	315	0.051	0.032546881	0.007261791	
37	330	0.046	0.031674552	0.007917666	
38	345	0.041	0.029878929	0.008231707	
39	360	0.066	0.027366537	0.008073848	
40	375	0.061	0.031008233	0.007389318	
41	390	0.056	0.032716917	0.007672496	
42	405	0.051	0.032924975	0.008274538	
43	420	0.046	0.031968073	0.008788452	
44	435	0.041	0.030106793	0.008973367	

	F	G	H	I	J
1			NRF REACTOR SIZE STUD / CASE 3		
2			Cs Conc = 36 Ci/Gal		
3			NO2 Destruction Rate =0.01 M/Mon.		
4			Tk-49 Temp. = 50°C		
5			Tk-49 Sample Cycle = 3 Months		
6			Tk-49 NO2 Range 0.036-0.066 M		
7			Process Rate =42,500 Gal/Mon (75% of BDR)		
8			NRF Reactors 3-62,000 Gallons		
9					
10	TIME	TANK 49	NRF-1	NRF-2	NRF-3
11	DAYS	MNO2	MNO2	MNO2	MNO2
12	0	0.066	0.036	0.036	0.036
13	15	0.061	0.031	0.031	0.031
14	30	0.056	0.026	0.026	0.026
15	45	0.051	0.021	0.021	0.021
16	60	0.046	0.016	0.016	0.016
17	75	0.041	0.011	0.011	0.011
18	90	0.066	0.016282258	0.006	0.006
19	105	0.061	0.028322613	0.004524161	0.001
20	120	0.056	0.034522524	0.007680889	0
21	135	0.051	0.036883756	0.011880643	0.000918853
22	150	0.046	0.036721985	0.015450258	0.002358285
23	165	0.041	0.03490195	0.017740971	0.003581742
24	180	0.066	0.031992007	0.018622758	0.004366865
25	195	0.061	0.038647972	0.01820496	0.00466909
26	210	0.056	0.04130895	0.020211638	0.004525894
27	225	0.051	0.041344189	0.022442571	0.005213666
28	240	0.046	0.03965364	0.023920948	0.006118734
29	255	0.041	0.036828804	0.024313201	0.0072203
30	270	0.066	0.033258448	0.023602823	0.008078754
31	285	0.061	0.039480351	0.021912211	0.008399503
32	300	0.056	0.041856037	0.022933549	0.008030875
33	315	0.051	0.041703766	0.024419079	0.008138646
34	330	0.046	0.039889975	0.025343266	0.008718633
35	345	0.041	0.036984137	0.025329033	0.009416592
36	360	0.066	0.033360542	0.024323726	0.009870453
37	375	0.061	0.039547453	0.022421022	0.009824196
38	390	0.056	0.04190014	0.023290968	0.009141656
39	405	0.051	0.041732754	0.024669112	0.008991219
40	420	0.046	0.039909028	0.025517537	0.00936469
41		0.041	0.036996659	0.025450105	0.009900948

	E	F	G	H	I
1			NRF REACTOR SIZE STUDY CASE 4		
2			Cs =23.2 Ci/Gal		
3			NO2 Destruction Rate= 0.0064 M/Mon.		
4			TK-49 Temp. = 50°C		
5			TK-49 Sample Cycle = 3 Months		
6			TK-49 NO2 Range = 0.036 TO 0.055 M		
7			Process Rate = 42.500 Gal/Mon (75% of BDR)		
8			NRF Reactors 2-120,000 gallons		
9					
10	TIME	TK 49	NRF-1	NRF-2	
11	DAYS	M NO2 (FORMULA	M NO2 (FORMULA	M NO2 (FORMULA	
12	0	0.055	0.036	0.036	
13	15	0.0518	0.0328	0.0328	
14	30	0.0486	0.0296	0.0296	
15	45	0.0454	0.0264	0.0264	
16	60	0.0422	0.0232	0.0232	
17	75	0.039	0.02	0.02	
18	90	0.055	0.0168	0.0168	
19	105	0.0518	0.0136	0.0136	
20	120	0.0486	0.0104	0.0104	
21	135	0.0454	0.0072	0.0072	
22	150	0.0422	0.010764583	0.004	
23	165	0.039	0.013131272	0.001997895	
24	180	0.055	0.014512192	0.001758663	
25	195	0.0518	0.018481908	0.002003201	
26	210	0.0486	0.021181987	0.002706171	
27	225	0.0454	0.02283726	0.00318431	
28	240	0.0422	0.023632745	0.003477431	
29	255	0.039	0.023720697	0.003846602	
30	270	0.055	0.023226407	0.004165973	
31	285	0.0518	0.02565298	0.004341258	
32	300	0.0486	0.027083182	0.004915209	
33	315	0.0454	0.027693452	0.005640787	
34	330	0.0422	0.027828986	0.006345947	
35	345	0.039	0.02700927	0.006914818	
36	360	0.055	0.025932628	0.007273211	
37	375	0.0518	0.027879975	0.007377483	
38	390	0.0486	0.028915813	0.007808132	
39	405	0.0454	0.029201555	0.008345951	
40	420	0.0422	0.028870029	0.008839131	
41	435	0.039	0.028030545	0.009186269	

	E	F	G	H	I
1			NRF REACTOR SIZE STUDY CASE 5		
2			Cs =19 Ci/Gal		
3			NO2 Destruction Rate= 0.053 M/Mon.		
4			TK-49 Temp. = 50°C		
5			TK-49 Sample Cycle = 3 Months		
6			TK-49 NO2 Range = 0.036 TO 0.052 M		
7			Process Rpte = 42,500 Gal/Mon (75% of BDR)		
8			NRF Reactors 2-140,000 gallons		
9					
10	TIME	TK 49	NRF-1	NRF-2	
11	DAYS	MNO2	MNO2	MNO2	
12	0	0.052	0.036	0.036	
13	15	0.0494	0.0334	0.0334	
14	30	0.0468	0.0308	0.0308	
15	45	0.0442	0.0282	0.0282	
16	60	0.0416	0.0256	0.0256	
17	75	0.039	0.023	0.023	
18	90	0.052	0.0204	0.0204	
19	105	0.0494	0.0178	0.0178	
20	120	0.0468	0.0152	0.0152	
21	135	0.0442	0.0126	0.0126	
22	150	0.0416	0.01	0.01	
23	165	0.039	0.012196429	0.0074	
24	180	0.052	0.013664828	0.005528029	
25	195	0.0494	0.016883559	0.004163079	
26	210	0.0468	0.01921909	0.003493866	
27	225	0.0442	0.020805479	0.003280731	
28	240	0.0416	0.0221756433	0.003340737	
29	255	0.039	0.022168403	0.003535977	
30	270	0.052	0.022123199	0.003764113	
31	285	0.0494	0.02405807	0.00395076	
32	300	0.0468	0.025304613	0.004402762	
33	315	0.0442	0.025967306	0.004975365	
34	330	0.0416	0.026134768	0.005561641	
35	345	0.039	0.02588217	0.006084348	
36	360	0.052	0.025273269	0.006489375	
37	375	0.0494	0.026730005	0.006740501	
38	390	0.0468	0.027570986	0.007174622	
39	405	0.0442	0.027889676	0.007670499	
40	420	0.0416	0.02776535	0.008139481	
41	435	0.039	0.027265252	0.008518408	
42	450	0.052	0.026446419	0.008763911	
43	465	0.0494	0.027725088	0.008847863	
44	480	0.0468	0.02841503	0.009113156	
45	495	0.0442	0.028605606	0.009442905	
46	510	0.0416	0.028372612	0.009751529	
47	525	0.039	0.027780341	0.009977943	

	E	F	G	H	I	J
1			NRF REACTOR SIZE STUDY CASE 6			
2			Cs =12.7 Ci/Gal (Min First 5 Years with 1.5 Safety Factor)			
3			NO2 Destruction Rate= 0.0035 M/Mon.			
4			TK-49 Temp. = 50°C			
5			TK-49 Sample Cycle = 3 Months			
6			TK-49 NO2 Range = 0.036 to 0.047 M			
7			Process Rate = 42,500 Gal/Mon (75% of BDR)			
8			NRF Reactors 2-170,000 gallons			
9						
10	TIME	TK 49	NRF-1	NRF-2		
11	DAYS	MNO2	MNO2	MNO2		
13	15	0.0453	0.0343	0.0343		
14	30	0.0436	0.0326	0.0326		
15	45	0.0419	0.0309	0.0309		
16	60	0.0402	0.0292	0.0292		
17	75	0.0385	0.0275	0.0275		
18	90	0.047	0.0258	0.0258		
19	105	0.0453	0.0241	0.0241		
20	120	0.0436	0.0224	0.0224		
21	135	0.0419	0.0207	0.0207		
22	150	0.0402	0.019	0.019		
23	165	0.0385	0.0173	0.0173		
24	180	0.047	0.0156	0.0156		
25	195	0.0453	0.0139	0.0139		
26	210	0.0436	0.0122	0.0122		
27	225	0.0419	0.0105	0.0105		
28	240	0.0402	0.0088	0.0088		
29	255	0.0385	0.011025	0.0071		
30	270	0.047	0.012759375	0.005890625		
31	285	0.0453	0.015339453	0.005049219		
32	300	0.0436	0.017384521	0.004635498		
33	315	0.0419	0.018961456	0.004529126		
34	330	0.0402	0.020128774	0.004633167		
35	345	0.0385	0.020937677	0.004870118		
36	360	0.047	0.021432968	0.005178563		
37	375	0.0453	0.022928847	0.005510364		
38	390	0.0436	0.024025241	0.005987674		
39	405	0.0419	0.024772086	0.00654237		
40	420	0.0402	0.025213075	0.007121084		
41	435	0.0385	0.025386441	0.007682583		
42	450	0.047	0.025325636	0.008195565		
43	465	0.0453	0.026334931	0.008636824		
44	480	0.0436	0.027005565	0.009149088		
45	495	0.0419	0.027379869	0.009681147		
46	510	0.0402	0.027494886	0.010193487		
47	525	0.0385	0.027383025	0.010656162		

	E	F	G	H	I	J
1			NRF REACTOR SIZE STUDY CASE 7			
2			Cs =9.5 Ci/Gal (Min First 5 Years with 2X Safety Factor)			
3			NO2 Destruction Rate= 0.026 M/Mon.			
4			TK-49 Temp. = 50°C			
5			TK-49 Sample Cycle = 3 Months			
6			TK-49 NO2 Range = 0.036 TO 0.044 M			
7			Process Rate = 42,500 Gal/Mon (75% of BDR)			
8			NRF Reactors 2-200,000 gallons			
9						
10	TIME	TK 49	NRF-1	NRF-2		
11	DAYS	MNO2	MNO2	MNO2		
12	0	0.044	0.036	0.036		
13	15	0.0427	0.0347	0.0347		
14	30	0.0414	0.0334	0.0334		
15	45	0.0401	0.0321	0.0321		
16	60	0.0388	0.0308	0.0308		
17	75	0.0375	0.0295	0.0295		
18	90	0.044	0.0282	0.0282		
19	105	0.0427	0.0269	0.0269		
20	120	0.0414	0.0256	0.0256		
21	135	0.0401	0.0243	0.0243		
22	150	0.0388	0.023	0.023		
23	165	0.0375	0.0217	0.0217		
24	180	0.044	0.0204	0.0204		
25	195	0.0427	0.0191	0.0191		
26	210	0.0414	0.0178	0.0178		
27	225	0.0401	0.0165	0.0165		
28	240	0.0388	0.0152	0.0152		
29	255	0.0375	0.0139	0.0139		
30	270	0.044	0.0126	0.0126		
31	285	0.0427	0.0113	0.0113		
32	300	0.0414	0.01	0.01		
33	315	0.0401	0.01203625	0.0087		
34	330	0.0388	0.013718023	0.007754477		
35	345	0.0375	0.015082983	0.007088103		
36	360	0.044	0.016164791	0.006637559		
37	375	0.0427	0.017822282	0.006349828		
38	390	0.0414	0.01916554	0.006268776		
39	405	0.0401	0.020227951	0.006339057		
40	420	0.0388	0.021039356	0.006514752		
41	435	0.0375	0.021626425	0.006757991		
42	450	0.044	0.022012992	0.007037762		
43	465	0.0427	0.023049112	0.007328881		
44	480	0.0414	0.023837019	0.007699155		
45	495	0.0401	0.024403085	0.008113803		
46	510	0.0388	0.024770883	0.008544539		
47	525	0.0375	0.024961476	0.008968588		

	E	F	G	H	I
1			NRF REACTOR SIZE STUDY CASE 8		
2			Cs =36 Ci/Gal (Average all waste)		
3			NO2 Destruction Rate= 0.01 M/Mon.		
4			TK-49 Temp. = 40°C		
5			TK-49 Sample Cycle = 3 Months		
6			TK-49 NO2 Range = 0.029 to 0.059 M		
7			Process Rate = 42,500 Gal/Mon (75% of BDR)		
8			NRF Reactors 2-80,000 gallons		
9					
10					
11					
12	TIME	TANK49	NRF-1	NRF-2	
13	DAYS	M NO2	M NO2	M NO2	
14	0	0.059	0.029	0.029	
15	15	0.054	0.024	0.024	
16	30	0.049	0.019	0.019	
17	45	0.044	0.014	0.014	
18	60	0.039	0.011	0.011	
19	75	0.034	0.0134375	0.006	
20	90	0.059	0.013899414	0.002975586	
21	105	0.054	0.020879257	0.002363907	
22	120	0.049	0.024676955	0.004217928	
23	135	0.044	0.026137763	0.005226691	
24	150	0.039	0.02588242	0.005781195	
25	165	0.034	0.024366777	0.006120583	
26	180	0.059	0.021925602	0.005967228	
27	195	0.054	0.026773489	0.005206171	
28	210	0.049	0.029005531	0.00593499	
29	225	0.044	0.029316562	0.007063102	
30	240	0.039	0.02821685	0.007974178	
31	255	0.034	0.026081124	0.008351137	
32	270	0.059	0.023184576	0.008060665	
33	285	0.054	0.027698048	0.007077954	
34	300	0.049	0.029684504	0.007555166	
35	315	0.044	0.029815182	0.008433272	
36	330	0.039	0.028583025	0.009112842	
37	345	0.034	0.026350034	0.009284609	
38	360	0.059	0.023382056	0.008817612	
39	375	0.054	0.027843072	0.007686293	
40	390	0.049	0.029791006	0.008040437	
41	405	0.044	0.029893395	0.008817932	
42	420	0.039	0.028640462	0.009416102	
43		0.034	0.026392214	0.009522573	

	E	F	G	H	I
1			NRF REACTOR SIZE STUDY CASE 9		
2			Cs =36 Ci/Gal (Average all waste)		
3			NO2 Destruction Rate= 0.01 M/Mon.		
4			TK-49 Temp. = 50°C		
5			TK-49 Sample Cycle = 1 Month		
6			TK-49 NO2 Range = 0.036 TO 0.046 M		
7			Process Rate = 42,500 Gal/Mon (75% of BDR)		
8			NRF Reactors 2-75,000 gallons		
9					
10					
11					
12	TIME	TK 49	NRF-1	NRF-2	
13	DAYS	MNO2	MNO2	MNO2	
14	0	0.046	0.036	0.036	
15	15	0.041	0.031	0.031	
16	30	0.046	0.026	0.026	
17	45	0.041	0.021	0.021	
18	60	0.046	0.016	0.016	
19	75	0.041	0.011	0.011	
20	90	0.046	0.0145	0.006	
21	105	0.041	0.018425	0.003408333	
22	120	0.046	0.01982125	0.00380375	
23	135	0.041	0.022238563	0.004199354	
24	150	0.046	0.022554303	0.004884259	
25	165	0.041	0.024197251	0.004973719	
26	180	0.046	0.02395803	0.005439221	
27	195	0.041	0.025203255	0.005686217	
28	210	0.046	0.024678999	0.006216044	
29	225	0.041	0.025719949	0.006447215	
30	240	0.046	0.025049297	0.006907823	
31	255	0.041	0.02598533	0.007047907	
32	270	0.046	0.025239486	0.00741351	
33	285	0.041	0.026121632	0.007464203	
34	300	0.046	0.025337169	0.007750475	
35	315	0.041	0.026191638	0.007733372	
36	330	0.046	0.025387341	0.007963214	
37	345	0.041	0.026227594	0.00790005	
38	360	0.046	0.025413109	0.008092854	
39	375	0.041	0.026246062	0.00800026	
40	390	0.046	0.025426344	0.008169903	
41	405	0.041	0.026255547	0.008059228	
42	420	0.046	0.025433142	0.008214852	
43	435	0.041	0.026260418	0.008093367	

	E	F	G	H	I
1			NRF REACTOR SIZE STUDY CASE 10		
2			Cs =23.2 Ci/Gal (Average First 5 Years)		
3			NO2 Destruction Rate= 0.064 M/Mon.		
4			TK-49 Temp. = 40°C		
5			TK-49 Sample Cycle = 1 Months		
6			TK-49 NO2 Range = 0.029 to 0.0354 M		
7			Process Rate = 42,500 Gal/Mon (75% of BDR)		
8			NRF Reactors 2-80,000 gallons		
9					
10					
11					
12					
13	TIME	TANK 49	NRF-1	NRF-2	
14	DAYS	M NO2	M NO2	M NO2	
16	0	0.0354	0.029	0.029	
17	15	0.0322	0.0258	0.0258	
18	30	0.0354	0.0226	0.0226	
19	45	0.0322	0.0194	0.0194	
20	60	0.0354	0.0162	0.0162	
21	75	0.0322	0.013	0.013	
22	90	0.0354	0.0149	0.0098	
23	105	0.0322	0.017145313	0.007954688	
24	120	0.0354	0.017944214	0.007195947	
25	135	0.0322	0.019380907	0.006850956	
26	150	0.0354	0.019585979	0.006979224	
27	165	0.0322	0.020586578	0.007127893	
28	180	0.0354	0.020471393	0.007502856	
29	195	0.0322	0.021236804	0.007747624	
30	210	0.0354	0.020948903	0.008130688	
31	225	0.0322	0.021587476	0.008335526	
32	240	0.0354	0.021206428	0.008655575	
33	255	0.0322	0.021776595	0.008789395	
34	270	0.0354	0.021345312	0.00903912	
35	285	0.0322	0.021878589	0.009107953	
36	300	0.0354	0.021420213	0.009300153	
37	315	0.0322	0.021933594	0.009319544	
38	330	0.0354	0.021460608	0.009470151	
39	345	0.0322	0.021963259	0.009455116	
40	360	0.0354	0.021482393	0.009577592	
41	375	0.0322	0.021979258	0.009539805	
42	390	0.0354	0.021494142	0.009644034	
43	405	0.0322	0.021987886	0.009591719	
44	420	0.0354	0.021500479	0.009684451	
45	435	0.0322	0.021992539	0.009623083	
46	450	0.0354	0.021503896	0.00970872	
47		0.0322	0.021995049	0.009641814	

NITRITE RADIOLYSIS FACILITY
REACTOR SIZING STUDY

APPENDIX B

FORMULAE USED IN CALCULATIONS

	D	E	F
1			NRF REACTOR SIZE STUDY CASE 1
2			Cs Conc = 36 Ci/Gal
3			NO2 Destruction Rate =0.01 M/Mon.
4			Tk-49 Temp. = 50°C
5			Tk-49 Sample Cycle = 3 Months
6			Tk-49 NO2 Range 0.036-0.066 M
7			Process Rate =42,500 Gal/Mon (75% of BDR)
8			NRF Reactor 1-200,000 Gallons
9			
10			
11	TIME	TANK 49	NRF TANK
12	DAYS	MNO2	MNO2
13	0	0.066	0.036
14	15	0.061	0.031
15	30	0.056	0.026
16	45	0.051	0.021
17	60	0.046	0.016
18	75	0.041	0.011
19	90	0.066	0.006
20	105	0.061	$=(21250*(E19-0.005)+178750*(F19-0.005))/200000$
21	120	0.056	$=(21250*(E20-0.005)+178750*(F20-0.005))/200000$
22	135	0.051	$=(21250*(E21-0.005)+178750*(F21-0.005))/200000$
23	150	0.046	$=(21250*(E22-0.005)+178750*(F22-0.005))/200000$
24	165	0.041	$=(21250*(E23-0.005)+178750*(F23-0.005))/200000$
25	180	0.066	$=(21250*(E24-0.005)+178750*(F24-0.005))/200000$
26	195	0.061	$=(21250*(E25-0.005)+178750*(F25-0.005))/200000$
27	210	0.056	$=(21250*(E26-0.005)+178750*(F26-0.005))/200000$
28	225	0.051	$=(21250*(E27-0.005)+178750*(F27-0.005))/200000$
29	240	0.046	$=(21250*(E28-0.005)+178750*(F28-0.005))/200000$
30	255	0.041	$=(21250*(E29-0.005)+178750*(F29-0.005))/200000$
31	270	0.066	$=(21250*(E30-0.005)+178750*(F30-0.005))/200000$
32	285	0.061	$=(21250*(E31-0.005)+178750*(F31-0.005))/200000$
33	300	0.056	$=(21250*(E32-0.005)+178750*(F32-0.005))/200000$
34	315	0.051	$=(21250*(E33-0.005)+178750*(F33-0.005))/200000$
35	330	0.046	$=(21250*(E34-0.005)+178750*(F34-0.005))/200000$
36	345	0.041	$=(21250*(E35-0.005)+178750*(F35-0.005))/200000$
37	360	0.066	$=(21250*(E36-0.005)+178750*(F36-0.005))/200000$
38	375	0.061	$=(21250*(E37-0.005)+178750*(F37-0.005))/200000$
39	390	0.056	$=(21250*(E38-0.005)+178750*(F38-0.005))/200000$
40	405	0.051	$=(21250*(E39-0.005)+178750*(F39-0.005))/200000$
41	420	0.046	$=(21250*(E40-0.005)+178750*(F40-0.005))/200000$
42		0.041	$=(21250*(E41-0.005)+178750*(F41-0.005))/200000$

	E	F	G
1			NRF REACTOR SIZE STUDY CASE 2
2			Cs =36 Ci/Gal (Average all waste)
3			NO2 Destruction Rate= 0.01 M/Mon.
4			TK-49 Temp. = 50°C
5			TK-49 Sample Cycle = 3 Months
6			TK-49 NO2 Range = 0.036 TO 0.066 M
7			Process Rate = 42,500 Gal/Mon (75% of BDR)
8			NRF Reactors 2-95,000 gallons
9			
10			
11			
12			
13	TIME	TK 49	NRF-1
14	DAYS	M NO2	M NO2 (FORMULA)
15	0	0.066	0.036
16	15	0.061	0.031
17	30	0.056	0.026
18	45	0.051	0.021
19	60	0.046	0.016
20	75	0.041	0.011
21	90	0.066	0.006
22	105	0.061	$=(21250*(F21-0.005)+73750*(G21-0.005))/95000$
23	120	0.056	$=(21250*(F22-0.005)+73750*(G22-0.005))/95000$
24	135	0.051	$=(21250*(F23-0.005)+73750*(G23-0.005))/95000$
25	150	0.046	$=(21250*(F24-0.005)+73750*(G24-0.005))/95000$
26	165	0.041	$=(21250*(F25-0.005)+73750*(G25-0.005))/95000$
27	180	0.066	$=(21250*(F26-0.005)+73750*(G26-0.005))/95000$
28	195	0.061	$=(21250*(F27-0.005)+73750*(G27-0.005))/95000$
29	210	0.056	$=(21250*(F28-0.005)+73750*(G28-0.005))/95000$
30	225	0.051	$=(21250*(F29-0.005)+73750*(G29-0.005))/95000$
31	240	0.046	$=(21250*(F30-0.005)+73750*(G30-0.005))/95000$
32	255	0.041	$=(21250*(F31-0.005)+73750*(G31-0.005))/95000$
33	270	0.066	$=(21250*(F32-0.005)+73750*(G32-0.005))/95000$
34	285	0.061	$=(21250*(F33-0.005)+73750*(G33-0.005))/95000$
35	300	0.056	$=(21250*(F34-0.005)+73750*(G34-0.005))/95000$
36	315	0.051	$=(21250*(F35-0.005)+73750*(G35-0.005))/95000$
37	330	0.046	$=(21250*(F36-0.005)+73750*(G36-0.005))/95000$
38	345	0.041	$=(21250*(F37-0.005)+73750*(G37-0.005))/95000$
39	360	0.066	$=(21250*(F38-0.005)+73750*(G38-0.005))/95000$
40	375	0.061	$=(21250*(F39-0.005)+73750*(G39-0.005))/95000$
41	390	0.056	$=(21250*(F40-0.005)+73750*(G40-0.005))/95000$
42	405	0.051	$=(21250*(F41-0.005)+73750*(G41-0.005))/95000$
43	420	0.046	$=(21250*(F42-0.005)+73750*(G42-0.005))/95000$
44	435	0.041	$=(21250*(F43-0.005)+73750*(G43-0.005))/95000$

	H	I
1	CASE 2	
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13	NRF-2	
14	M NO2 (FORMULA)	
15	0.036	
16	0.031	
17	0.026	
18	0.021	
19	0.016	
20	0.011	
21	0.006	
22	$=(21250*(G21-0.005)+73750*(H21-0.005))/95000$	
23	$=(21250*(G22-0.005))/95000$	
24	$=(21250*(G23-0.005))/95000$	
25	$=(21250*(G24-0.005))/95000$	
26	$=(21250*(G25-0.005))/95000$	
27	$=(21250*(G26-0.005))/95000$	
28	$=(21250*(G27-0.005))/95000$	
29	$=(21250*(G28-0.005))/95000$	
30	$=(21250*(G29-0.005)+73750*(H29-0.005))/95000$	
31	$=(21250*(G30-0.005)+73750*(H30-0.005))/95000$	
32	$=(21250*(G31-0.005)+73750*(H31-0.005))/95000$	
33	$=(21250*(G32-0.005)+73750*(H32-0.005))/95000$	
34	$=(21250*(G33-0.005)+73750*(H33-0.005))/95000$	
35	$=(21250*(G34-0.005)+73750*(H34-0.005))/95000$	
36	$=(21250*(G35-0.005)+73750*(H35-0.005))/95000$	
37	$=(21250*(G36-0.005)+73750*(H36-0.005))/95000$	
38	$=(21250*(G37-0.005)+73750*(H37-0.005))/95000$	
39	$=(21250*(G38-0.005)+73750*(H38-0.005))/95000$	
40	$=(21250*(G39-0.005)+73750*(H39-0.005))/95000$	
41	$=(21250*(G40-0.005)+73750*(H40-0.005))/95000$	
42	$=(21250*(G41-0.005)+73750*(H41-0.005))/95000$	
43	$=(21250*(G42-0.005)+73750*(H42-0.005))/95000$	
44	$=(21250*(G43-0.005)+73750*(H43-0.005))/95000$	

	F	G	H
1			NRF REACTOR SIZE STUDY CASE 3
2			Cs Conc = 36 Ci/Gal
3			NO2 Destruction Rate = 0.01 M/Mon.
4			Tk-49 Temp. = 50°C
5			Tk-49 Sample Cycle = 3 Months
6			Tk-49 NO2 Range 0.036-0.066 M
7			Process Rate = 42,500 Gal/Mon (75% of BDR)
8			NRF Reactors 3-62,000 Gallons
9			
10	TIME	TANK 49	NRF-1
11	DAYS	MNO2	MNO2
12	0	0.066	0.036
13	15	0.061	0.031
14	30	0.056	0.026
15	45	0.051	0.021
16	60	0.046	0.016
17	75	0.041	0.011
18	90	0.066	$=(21250 \cdot (G17-0.005) + 40750 \cdot (H17-0.005)) / 62000$
19	105	0.061	$=(21250 \cdot (G18-0.005) + 40750 \cdot (H18-0.005)) / 62000$
20	120	0.056	$=(21250 \cdot (G19-0.005) + 40750 \cdot (H19-0.005)) / 62000$
21	135	0.051	$=(21250 \cdot (G20-0.005) + 40750 \cdot (H20-0.005)) / 62000$
22	150	0.046	$=(21250 \cdot (G21-0.005) + 40750 \cdot (H21-0.005)) / 62000$
23	165	0.041	$=(21250 \cdot (G22-0.005) + 40750 \cdot (H22-0.005)) / 62000$
24	180	0.066	$=(21250 \cdot (G23-0.005) + 40750 \cdot (H23-0.005)) / 62000$
25	195	0.061	$=(21250 \cdot (G24-0.005) + 40750 \cdot (H24-0.005)) / 62000$
26	210	0.056	$=(21250 \cdot (G25-0.005) + 40750 \cdot (H25-0.005)) / 62000$
27	225	0.051	$=(21250 \cdot (G26-0.005) + 40750 \cdot (H26-0.005)) / 62000$
28	240	0.046	$=(21250 \cdot (G27-0.005) + 40750 \cdot (H27-0.005)) / 62000$
29	255	0.041	$=(21250 \cdot (G28-0.005) + 40750 \cdot (H28-0.005)) / 62000$
30	270	0.066	$=(21250 \cdot (G29-0.005) + 40750 \cdot (H29-0.005)) / 62000$
31	285	0.061	$=(21250 \cdot (G30-0.005) + 40750 \cdot (H30-0.005)) / 62000$
32	300	0.056	$=(21250 \cdot (G31-0.005) + 40750 \cdot (H31-0.005)) / 62000$
33	315	0.051	$=(21250 \cdot (G32-0.005) + 40750 \cdot (H32-0.005)) / 62000$
34	330	0.046	$=(21250 \cdot (G33-0.005) + 40750 \cdot (H33-0.005)) / 62000$
35	345	0.041	$=(21250 \cdot (G34-0.005) + 40750 \cdot (H34-0.005)) / 62000$
36	360	0.066	$=(21250 \cdot (G35-0.005) + 40750 \cdot (H35-0.005)) / 62000$
37	375	0.061	$=(21250 \cdot (G36-0.005) + 40750 \cdot (H36-0.005)) / 62000$
38	390	0.056	$=(21250 \cdot (G37-0.005) + 40750 \cdot (H37-0.005)) / 62000$
39	405	0.051	$=(21250 \cdot (G38-0.005) + 40750 \cdot (H38-0.005)) / 62000$
40	420	0.046	$=(21250 \cdot (G39-0.005) + 40750 \cdot (H39-0.005)) / 62000$
41		0.041	$=(21250 \cdot (G40-0.005) + 40750 \cdot (H40-0.005)) / 62000$

101525

	I
1	CASE 3
2	
3	
4	
5	
6	
7	
8	
9	
10	NRF-2
11	MNO2
12	0.036
13	0.031
14	0.026
15	0.021
16	0.016
17	0.011
18	$=(21250 \cdot (H17-0.005) + 40750 \cdot (I17-0.005)) / 62000$
19	$=(21250 \cdot (H18-0.005) + 40750 \cdot (I18-0.005)) / 62000$
20	$=(21250 \cdot (H19-0.005) + 40750 \cdot (I19-0.005)) / 62000$
21	$=(21250 \cdot (H20-0.005) + 40750 \cdot (I20-0.005)) / 62000$
22	$=(21250 \cdot (H21-0.005) + 40750 \cdot (I21-0.005)) / 62000$
23	$=(21250 \cdot (H22-0.005) + 40750 \cdot (I22-0.005)) / 62000$
24	$=(21250 \cdot (H23-0.005) + 40750 \cdot (I23-0.005)) / 62000$
25	$=(21250 \cdot (H24-0.005) + 40750 \cdot (I24-0.005)) / 62000$
26	$=(21250 \cdot (H25-0.005) + 40750 \cdot (I25-0.005)) / 62000$
27	$=(21250 \cdot (H26-0.005) + 40750 \cdot (I26-0.005)) / 62000$
28	$=(21250 \cdot (H27-0.005) + 40750 \cdot (I27-0.005)) / 62000$
29	$=(21250 \cdot (H28-0.005) + 40750 \cdot (I28-0.005)) / 62000$
30	$=(21250 \cdot (H29-0.005) + 40750 \cdot (I29-0.005)) / 62000$
31	$=(21250 \cdot (H30-0.005) + 40750 \cdot (I30-0.005)) / 62000$
32	$=(21250 \cdot (H31-0.005) + 40750 \cdot (I31-0.005)) / 62000$
33	$=(21250 \cdot (H32-0.005) + 40750 \cdot (I32-0.005)) / 62000$
34	$=(21250 \cdot (H33-0.005) + 40750 \cdot (I33-0.005)) / 62000$
35	$=(21250 \cdot (H34-0.005) + 40750 \cdot (I34-0.005)) / 62000$
36	$=(21250 \cdot (H35-0.005) + 40750 \cdot (I35-0.005)) / 62000$
37	$=(21250 \cdot (H36-0.005) + 40750 \cdot (I36-0.005)) / 62000$
38	$=(21250 \cdot (H37-0.005) + 40750 \cdot (I37-0.005)) / 62000$
39	$=(21250 \cdot (H38-0.005) + 40750 \cdot (I38-0.005)) / 62000$
40	$=(21250 \cdot (H39-0.005) + 40750 \cdot (I39-0.005)) / 62000$
41	$=(21250 \cdot (H40-0.005) + 40750 \cdot (I40-0.005)) / 62000$

101525

	J
1	CASE 3
2	
3	
4	
5	
6	
7	
8	
9	
10	NRF-3
11	MNO2
12	0.036
13	0.031
14	0.026
15	0.021
16	0.016
17	0.011
18	$-(21250 \cdot (I17 - 0.005) + 40750 \cdot (J17 - 0.005)) / 62000$
19	$-(21250 \cdot (I18 - 0.005) + 40750 \cdot (J18 - 0.005)) / 62000$
20	0
21	$-(21250 \cdot (I20 - 0.005)) / 62000$
22	$-(21250 \cdot (I21 - 0.005)) / 62000$
23	$-(21250 \cdot (I22 - 0.005)) / 62000$
24	$-(21250 \cdot (I23 - 0.005)) / 62000$
25	$-(21250 \cdot (I24 - 0.005)) / 62000$
26	$-(21250 \cdot (I25 - 0.005)) / 62000$
27	$-(21250 \cdot (I26 - 0.005)) / 62000$
28	$-(21250 \cdot (I27 - 0.005) + 40750 \cdot (J27 - 0.005)) / 62000$
29	$-(21250 \cdot (I28 - 0.005) + 40750 \cdot (J28 - 0.005)) / 62000$
30	$-(21250 \cdot (I29 - 0.005) + 40750 \cdot (J29 - 0.005)) / 62000$
31	$-(21250 \cdot (I30 - 0.005) + 40750 \cdot (J30 - 0.005)) / 62000$
32	$-(21250 \cdot (I31 - 0.005) + 40750 \cdot (J31 - 0.005)) / 62000$
33	$-(21250 \cdot (I32 - 0.005) + 40750 \cdot (J32 - 0.005)) / 62000$
34	$-(21250 \cdot (I33 - 0.005) + 40750 \cdot (J33 - 0.005)) / 62000$
35	$-(21250 \cdot (I34 - 0.005) + 40750 \cdot (J34 - 0.005)) / 62000$
36	$-(21250 \cdot (I35 - 0.005) + 40750 \cdot (J35 - 0.005)) / 62000$
37	$-(21250 \cdot (I36 - 0.005) + 40750 \cdot (J36 - 0.005)) / 62000$
38	$-(21250 \cdot (I37 - 0.005) + 40750 \cdot (J37 - 0.005)) / 62000$
39	$-(21250 \cdot (I38 - 0.005) + 40750 \cdot (J38 - 0.005)) / 62000$
40	$-(21250 \cdot (I39 - 0.005) + 40750 \cdot (J39 - 0.005)) / 62000$
41	$-(21250 \cdot (I40 - 0.005) + 40750 \cdot (J40 - 0.005)) / 62000$

	E	F	G
1			NRF REACTOR SIZE STUDY CASE 4
2			Cs =23.2 Ci/Gal
3			NO2 Destruction Rate= 0.0064 M/Mon.
4			TK-49 Temp. = 50°C
5			TK-49 Sample Cycle = 3 Months
6			TK-49 NO2 Range = 0.036 TO 0.055 M
7			Process Rate = 42,500 Gal/Mon (75% of BDR)
8			NRF Reactors 2-120,000 gallons
9			
10	TIME	TK 49	NRF-1
11	DAYS	M NO2 (FORM)	M NO2 (FORMULA)
12	0	0.055	0.036
13	15	=F12-0.0032	=G12-0.0032
14	30	=F13-0.0032	=G13-0.0032
15	45	=F14-0.0032	=G14-0.0032
16	60	=F15-0.0032	=G15-0.0032
17	75	=F16-0.0032	=G16-0.0032
18	90	0.055	=G17-0.0032
19	105	=F18-0.0032	=G18-0.0032
20	120	=F19-0.0032	=G19-0.0032
21	135	=F20-0.0032	=G20-0.0032
22	150	=F21-0.0032	=(21250*(F21-0.0032)+98750*(G21-0.0032))/120000
23	165	=F22-0.0032	=(21250*(F22-0.0032)+98750*(G22-0.0032))/120000
24	180	0.055	=(21250*(F23-0.0032)+98750*(G23-0.0032))/120000
25	195	=F24-0.0032	=(21250*(F24-0.0032)+98750*(G24-0.0032))/120000
26	210	=F25-0.0032	=(21250*(F25-0.0032)+98750*(G25-0.0032))/120000
27	225	=F26-0.0032	=(21250*(F26-0.0032)+98750*(G26-0.0032))/120000
28	240	=F27-0.0032	=(21250*(F27-0.0032)+98750*(G27-0.0032))/120000
29	255	=F28-0.0032	=(21250*(F28-0.0032)+98750*(G28-0.0032))/120000
30	270	0.055	=(21250*(F29-0.0032)+98750*(G29-0.0032))/120000
31	285	=F30-0.0032	=(21250*(F30-0.0032)+98750*(G30-0.0032))/120000
32	300	=F31-0.0032	=(21250*(F31-0.0032)+98750*(G31-0.0032))/120000
33	315	=F32-0.0032	=(21250*(F32-0.0032)+98750*(G32-0.0032))/120000
34	330	=F33-0.0032	=(21250*(F33-0.0032)+98750*(G33-0.0032))/120000
35	345	=F34-0.0032	=(21250*(F34-0.0032)+98750*(G34-0.0032))/120000
36	360	0.055	=(21250*(F35-0.0032)+98750*(G35-0.0032))/120000
37	375	=F36-0.0032	=(21250*(F36-0.0032)+98750*(G36-0.0032))/120000
38	390	=F37-0.0032	=(21250*(F37-0.0032)+98750*(G37-0.0032))/120000
39	405	=F38-0.0032	=(21250*(F38-0.0032)+98750*(G38-0.0032))/120000
40	420	=F39-0.0032	=(21250*(F39-0.0032)+98750*(G39-0.0032))/120000
41	435	=F40-0.0032	=(21250*(F40-0.0032)+98750*(G40-0.0032))/120000

	H
1	CASE 4
2	
3	
4	
5	
6	
7	
8	
9	
10	NRF-2
11	MNO2 (FORMULA)
12	0.036
13	=H12-0.0032
14	=H13-0.0032
15	=H14-0.0032
16	=H15-0.0032
17	=H16-0.0032
18	=H17-0.0032
19	=H18-0.0032
20	=H19-0.0032
21	=H20-0.0032
22	=(21250*(G21-0.0032)+98750*(H21-0.0032))/120000
23	=(21250*(G22-0.0032)+98750*(H22-0.0032))/120000
24	=(21250*(G23-0.0032))/120000
25	=(21250*(G24-0.0032))/120000
26	=(21250*(G25-0.0032))/120000
27	=(21250*(G26-0.0032))/120000
28	=(21250*(G27-0.0032))/120000
29	=(21250*(G28-0.0032)+98750*(H28-0.0032))/120000
30	=(21250*(G29-0.0032)+98750*(H29-0.0032))/120000
31	=(21250*(G30-0.0032)+98750*(H30-0.0032))/120000
32	=(21250*(G31-0.0032)+98750*(H31-0.0032))/120000
33	=(21250*(G32-0.0032)+98750*(H32-0.0032))/120000
34	=(21250*(G33-0.0032)+98750*(H33-0.0032))/120000
35	=(21250*(G34-0.0032)+98750*(H34-0.0032))/120000
36	=(21250*(G35-0.0032)+98750*(H35-0.0032))/120000
37	=(21250*(G36-0.0032)+98750*(H36-0.0032))/120000
38	=(21250*(G37-0.0032)+98750*(H37-0.0032))/120000
39	=(21250*(G38-0.0032)+98750*(H38-0.0032))/120000
40	=(21250*(G39-0.0032)+98750*(H39-0.0032))/120000
41	=(21250*(G40-0.0032)+98750*(H40-0.0032))/120000

	E	F	G
1			NRF REACTOR SIZE STUDY CASE 5
2			Cs =19 CI/Gal
3			NO2 Destruction Rate= 0.053 M/Mon.
4			TK-49 Temp. = 50°C
5			TK-49 Sample Cycle = 3 Months
6			TK-49 NO2 Range = 0.036 TO 0.052 M
7			Process Rate = 42,500 Gal/Mon (75% of BDR)
8			NRF Reactors 2-140,000 gallons
9			
10	TIME	TK 49	NRF-1
11	DAYS	M NO2 FORMULA	M NO2 FORMULA
12	0	0.052	0.036
13	15	=F12-0.0026	=G12-0.0026
14	30	=F13-0.0026	=G13-0.0026
15	45	=F14-0.0026	=G14-0.0026
16	60	=F15-0.0026	=G15-0.0026
17	75	=F16-0.0026	=G16-0.0026
18	90	0.052	=G17-0.0026
19	105	=F18-0.0026	=G18-0.0026
20	120	=F19-0.0026	=G19-0.0026
21	135	=F20-0.0026	=G20-0.0026
22	150	=F21-0.0026	=G21-0.0026
23	165	=F22-0.0026	=(21250*(F22-0.0026)+118750*(G22-0.0026))/140000
24	180	0.052	=(21250*(F23-0.0026)+118750*(G23-0.0026))/140000
25	195	=F24-0.0026	=(21250*(F24-0.0026)+118750*(G24-0.0026))/140000
26	210	=F25-0.0026	=(21250*(F25-0.0026)+118750*(G25-0.0026))/140000
27	225	=F26-0.0026	=(21250*(F26-0.0026)+118750*(G26-0.0026))/140000
28	240	=F27-0.0026	=(21250*(F27-0.0026)+118750*(G27-0.0026))/140000
29	255	=F28-0.0026	=(21250*(F28-0.0026)+118750*(G28-0.0026))/140000
30	270	0.052	=(21250*(F29-0.0026)+118750*(G29-0.0026))/140000
31	285	=F30-0.0026	=(21250*(F30-0.0026)+118750*(G30-0.0026))/140000
32	300	=F31-0.0026	=(21250*(F31-0.0026)+118750*(G31-0.0026))/140000
33	315	=F32-0.0026	=(21250*(F32-0.0026)+118750*(G32-0.0026))/140000
34	330	=F33-0.0026	=(21250*(F33-0.0026)+118750*(G33-0.0026))/140000
35	345	=F34-0.0026	=(21250*(F34-0.0026)+118750*(G34-0.0026))/140000
36	360	0.052	=(21250*(F35-0.0026)+118750*(G35-0.0026))/140000
37	375	=F36-0.0026	=(21250*(F36-0.0026)+118750*(G36-0.0026))/140000
38	390	=F37-0.0026	=(21250*(F37-0.0026)+118750*(G37-0.0026))/140000
39	405	=F38-0.0026	=(21250*(F38-0.0026)+118750*(G38-0.0026))/140000
40	420	=F39-0.0026	=(21250*(F39-0.0026)+118750*(G39-0.0026))/140000
41	435	=F40-0.0026	=(21250*(F40-0.0026)+118750*(G40-0.0026))/140000
42	450	0.052	=(21250*(F41-0.0026)+118750*(G41-0.0026))/140000
43	465	=F42-0.0026	=(21250*(F42-0.0026)+118750*(G42-0.0026))/140000
44	480	=F43-0.0026	=(21250*(F43-0.0026)+118750*(G43-0.0026))/140000
45	495	=F44-0.0026	=(21250*(F44-0.0026)+118750*(G44-0.0026))/140000
46	510	=F45-0.0026	=(21250*(F45-0.0026)+118750*(G45-0.0026))/140000
47	525	=F46-0.0026	=(21250*(F46-0.0026)+118750*(G46-0.0026))/140000

101525

	H
1	CASE 5
2	
3	
4	
5	
6	
7	
8	
9	
10	NRF-2
11	MNO2 FORMULA
12	0.036
13	=H12-0.0026
14	=H13-0.0026
15	=H14-0.0026
16	=H15-0.0026
17	=H16-0.0026
18	=H17-0.0026
19	=H18-0.0026
20	=H19-0.0026
21	=H20-0.0026
22	=H21-0.0026
23	= (21250*(G22-0.0026)+118750*(H22-0.0026))/140000
24	= (21250*(G23-0.0026)+118750*(H23-0.0026))/140000
25	= (21250*(G24-0.0026)+118750*(H24-0.0026))/140000
26	= (21250*(G25-0.0026)+118750*(H25-0.0026))/140000
27	= (21250*(G26-0.0026)+118750*(H26-0.0026))/140000
28	= (21250*(G27-0.0026)+118750*(H27-0.0026))/140000
29	= (21250*(G28-0.0026)+118750*(H28-0.0026))/140000
30	= (21250*(G29-0.0026)+118750*(H29-0.0026))/140000
31	= (21250*(G30-0.0026)+118750*(H30-0.0026))/140000
32	= (21250*(G31-0.0026)+118750*(H31-0.0026))/140000
33	= (21250*(G32-0.0026)+118750*(H32-0.0026))/140000
34	= (21250*(G33-0.0026)+118750*(H33-0.0026))/140000
35	= (21250*(G34-0.0026)+118750*(H34-0.0026))/140000
36	= (21250*(G35-0.0026)+118750*(H35-0.0026))/140000
37	= (21250*(G36-0.0026)+118750*(H36-0.0026))/140000
38	= (21250*(G37-0.0026)+118750*(H37-0.0026))/140000
39	= (21250*(G38-0.0026)+118750*(H38-0.0026))/140000
40	= (21250*(G39-0.0026)+118750*(H39-0.0026))/140000
41	= (21250*(G40-0.0026)+118750*(H40-0.0026))/140000
42	= (21250*(G41-0.0026)+118750*(H41-0.0026))/140000
43	= (21250*(G42-0.0026)+118750*(H42-0.0026))/140000
44	= (21250*(G43-0.0026)+118750*(H43-0.0026))/140000
45	= (21250*(G44-0.0026)+118750*(H44-0.0026))/140000
46	= (21250*(G45-0.0026)+118750*(H45-0.0026))/140000
47	= (21250*(G46-0.0026)+118750*(H46-0.0026))/140000

	E	F	G
1			NRF REACTOR SIZE STUDY CASE 6
2			Cs =12.7 Ci/Gal (Min First 5 Years with 1.5 Safety Factor)
3			NO2 Destruction Rate= 0.0035 M/Mon.
4			TK-49 Temp. = 50°C
5			TK-49 Sample Cycle = 3 Months
6			TK-49 NO2 Range = 0.036 to 0.047 M
7			Process Rate = 42,500 Gal/Mon (75% of BDR)
8			NRF Reactors 2-170,000 gallons
9			
10	TIME	TK 49	NRF-1
11	DAYS	MNO2	MNO2
12	0	0.047	0.036
13	15	=F12-0.0017	=G12-0.0017
14	30	=F13-0.0017	=G13-0.0017
15	45	=F14-0.0017	=G14-0.0017
16	60	=F15-0.0017	=G15-0.0017
17	75	=F16-0.0017	=G16-0.0017
18	90	0.047	=G17-0.0017
19	105	=F18-0.0017	=G18-0.0017
20	120	=F19-0.0017	=G19-0.0017
21	135	=F20-0.0017	=G20-0.0017
22	150	=F21-0.0017	=G21-0.0017
23	165	=F22-0.0017	=G22-0.0017
24	180	0.047	=G23-0.0017
25	195	=F24-0.0017	=G24-0.0017
26	210	=F25-0.0017	=G25-0.0017
27	225	=F26-0.0017	=G26-0.0017
28	240	=F27-0.0017	=G27-0.0017
29	255	=F28-0.0017	=(21250*(F28-0.0017)+148750*(G28-0.0017))/170000
30	270	0.047	=(21250*(F29-0.0017)+148750*(G29-0.0017))/170000
31	285	=F30-0.0017	=(21250*(F30-0.0017)+148750*(G30-0.0017))/170000
32	300	=F31-0.0017	=(21250*(F31-0.0017)+148750*(G31-0.0017))/170000
33	315	=F32-0.0017	=(21250*(F32-0.0017)+148750*(G32-0.0017))/170000
34	330	=F33-0.0017	=(21250*(F33-0.0017)+148750*(G33-0.0017))/170000
35	345	=F34-0.0017	=(21250*(F34-0.0017)+148750*(G34-0.0017))/170000
36	360	0.047	=(21250*(F35-0.0017)+148750*(G35-0.0017))/170000
37	375	=F36-0.0017	=(21250*(F36-0.0017)+148750*(G36-0.0017))/170000
38	390	=F37-0.0017	=(21250*(F37-0.0017)+148750*(G37-0.0017))/170000
39	405	=F38-0.0017	=(21250*(F38-0.0017)+148750*(G38-0.0017))/170000
40	420	=F39-0.0017	=(21250*(F39-0.0017)+148750*(G39-0.0017))/170000
41	435	=F40-0.0017	=(21250*(F40-0.0017)+148750*(G40-0.0017))/170000
42	450	0.047	=(21250*(F41-0.0017)+148750*(G41-0.0017))/170000
43	465	=F42-0.0017	=(21250*(F42-0.0017)+148750*(G42-0.0017))/170000
44	480	=F43-0.0017	=(21250*(F43-0.0017)+148750*(G43-0.0017))/170000
45	495	=F44-0.0017	=(21250*(F44-0.0017)+148750*(G44-0.0017))/170000
46	510	=F45-0.0017	=(21250*(F45-0.0017)+148750*(G45-0.0017))/170000
47	525	=F46-0.0017	=(21250*(F46-0.0017)+148750*(G46-0.0017))/170000

	H
1	CASE 6
2	
3	
4	
5	
6	
7	
8	
9	
10	NRF-2
11	MNO2
12	0.036
13	=H12-0.0017
14	=H13-0.0017
15	=H14-0.0017
16	=H15-0.0017
17	=H16-0.0017
18	=H17-0.0017
19	=H18-0.0017
20	=H19-0.0017
21	=H20-0.0017
22	=H21-0.0017
23	=H22-0.0017
24	=H23-0.0017
25	=H24-0.0017
26	=H25-0.0017
27	=H26-0.0017
28	=H27-0.0017
29	$= (21250^{\circ}(G28-0.0017) + 148750^{\circ}(H28-0.0017)) / 170000$
30	$= (21250^{\circ}(G29-0.0017) + 148750^{\circ}(H29-0.0017)) / 170000$
31	$= (21250^{\circ}(G30-0.0017) + 148750^{\circ}(H30-0.0017)) / 170000$
32	$= (21250^{\circ}(G31-0.0017) + 148750^{\circ}(H31-0.0017)) / 170000$
33	$= (21250^{\circ}(G32-0.0017) + 148750^{\circ}(H32-0.0017)) / 170000$
34	$= (21250^{\circ}(G33-0.0017) + 148750^{\circ}(H33-0.0017)) / 170000$
35	$= (21250^{\circ}(G34-0.0017) + 148750^{\circ}(H34-0.0017)) / 170000$
36	$= (21250^{\circ}(G35-0.0017) + 148750^{\circ}(H35-0.0017)) / 170000$
37	$= (21250^{\circ}(G36-0.0017) + 148750^{\circ}(H36-0.0017)) / 170000$
38	$= (21250^{\circ}(G37-0.0017) + 148750^{\circ}(H37-0.0017)) / 170000$
39	$= (21250^{\circ}(G38-0.0017) + 148750^{\circ}(H38-0.0017)) / 170000$
40	$= (21250^{\circ}(G39-0.0017) + 148750^{\circ}(H39-0.0017)) / 170000$
41	$= (21250^{\circ}(G40-0.0017) + 148750^{\circ}(H40-0.0017)) / 170000$
42	$= (21250^{\circ}(G41-0.0017) + 148750^{\circ}(H41-0.0017)) / 170000$
43	$= (21250^{\circ}(G42-0.0017) + 148750^{\circ}(H42-0.0017)) / 170000$
44	$= (21250^{\circ}(G43-0.0017) + 148750^{\circ}(H43-0.0017)) / 170000$
45	$= (21250^{\circ}(G44-0.0017) + 148750^{\circ}(H44-0.0017)) / 170000$
46	$= (21250^{\circ}(G45-0.0017) + 148750^{\circ}(H45-0.0017)) / 170000$
47	$= (21250^{\circ}(G46-0.0017) + 148750^{\circ}(H46-0.0017)) / 170000$

	E	F	G
1			NRF REACTOR SIZE STUDY CASE 7
2			Cs =9.5 Ci/Gal (Min First 5 Years with 2X Safety Factor)
3			NO2 Destruction Rate= 0.026 M/Mon.
4			TK-49 Temp. = 50°C
5			TK-49 Sample Cycle = 3 Months
6			TK-49 NO2 Range = 0.036 TO 0.044 M
7			Process Rate = 42,500 Gal/Mon (75% of BDR)
8			NRF Reactors 2-200,000 gallons
9			
10	TIME	TK 49	NRF-1
11	DAYS	MNO2	MNO2
12	0	0.044	0.036
13	15	=F12-0.0013	=G12-0.0013
14	30	=F13-0.0013	=G13-0.0013
15	45	=F14-0.0013	=G14-0.0013
16	60	=F15-0.0013	=G15-0.0013
17	75	=F16-0.0013	=G16-0.0013
18	90	0.044	=G17-0.0013
19	105	=F18-0.0013	=G18-0.0013
20	120	=F19-0.0013	=G19-0.0013
21	135	=F20-0.0013	=G20-0.0013
22	150	=F21-0.0013	=G21-0.0013
23	165	=F22-0.0013	=G22-0.0013
24	180	0.044	=G23-0.0013
25	195	=F24-0.0013	=G24-0.0013
26	210	=F25-0.0013	=G25-0.0013
27	225	=F26-0.0013	=G26-0.0013
28	240	=F27-0.0013	=G27-0.0013
29	255	=F28-0.0013	=G28-0.0013
30	270	0.044	=G29-0.0013
31	285	=F30-0.0013	=G30-0.0013
32	300	=F31-0.0013	=G31-0.0013
33	315	=F32-0.0013	=(21250*(F32-0.0013)+178750*(G32-0.0013))/200000
34	330	=F33-0.0013	=(21250*(F33-0.0013)+178750*(G33-0.0013))/200000
35	345	=F34-0.0013	=(21250*(F34-0.0013)+178750*(G34-0.0013))/200000
36	360	0.044	=(21250*(F35-0.0013)+178750*(G35-0.0013))/200000
37	375	=F36-0.0013	=(21250*(F36-0.0013)+178750*(G36-0.0013))/200000
38	390	=F37-0.0013	=(21250*(F37-0.0013)+178750*(G37-0.0013))/200000
39	405	=F38-0.0013	=(21250*(F38-0.0013)+178750*(G38-0.0013))/200000
40	420	=F39-0.0013	=(21250*(F39-0.0013)+178750*(G39-0.0013))/200000
41	435	=F40-0.0013	=(21250*(F40-0.0013)+178750*(G40-0.0013))/200000
42	450	0.044	=(21250*(F41-0.0013)+178750*(G41-0.0013))/200000
43	465	=F42-0.0013	=(21250*(F42-0.0013)+178750*(G42-0.0013))/200000
44	480	=F43-0.0013	=(21250*(F43-0.0013)+178750*(G43-0.0013))/200000
45	495	=F44-0.0013	=(21250*(F44-0.0013)+178750*(G44-0.0013))/200000
46	510	=F45-0.0013	=(21250*(F45-0.0013)+178750*(G45-0.0013))/200000
47	525	=F46-0.0013	=(21250*(F46-0.0013)+178750*(G46-0.0013))/200000

	H
1	CASE 7
2	
3	
4	
5	
6	
7	
8	
9	
10	NRF-2
11	MNO2
12	0.036
13	=H12-0.0013
14	=H13-0.0013
15	=H14-0.0013
16	=H15-0.0013
17	=H16-0.0013
18	=H17-0.0013
19	=H18-0.0013
20	=H19-0.0013
21	=H20-0.0013
22	=H21-0.0013
23	=H22-0.0013
24	=H23-0.0013
25	=H24-0.0013
26	=H25-0.0013
27	=H26-0.0013
28	=H27-0.0013
29	=H28-0.0013
30	=H29-0.0013
31	=H30-0.0013
32	=H31-0.0013
33	$=(21250^*(G32-0.0013)+178750^*(H32-0.0013))/200000$
34	$=(21250^*(G33-0.0013)+178750^*(H33-0.0013))/200000$
35	$=(21250^*(G34-0.0013)+178750^*(H34-0.0013))/200000$
36	$=(21250^*(G35-0.0013)+178750^*(H35-0.0013))/200000$
37	$=(21250^*(G36-0.0013)+178750^*(H36-0.0013))/200000$
38	$=(21250^*(G37-0.0013)+178750^*(H37-0.0013))/200000$
39	$=(21250^*(G38-0.0013)+178750^*(H38-0.0013))/200000$
40	$=(21250^*(G39-0.0013)+178750^*(H39-0.0013))/200000$
41	$=(21250^*(G40-0.0013)+178750^*(H40-0.0013))/200000$
42	$=(21250^*(G41-0.0013)+178750^*(H41-0.0013))/200000$
43	$=(21250^*(G42-0.0013)+178750^*(H42-0.0013))/200000$
44	$=(21250^*(G43-0.0013)+178750^*(H43-0.0013))/200000$
45	$=(21250^*(G44-0.0013)+178750^*(H44-0.0013))/200000$
46	$=(21250^*(G45-0.0013)+178750^*(H45-0.0013))/200000$
47	$=(21250^*(G46-0.0013)+178750^*(H46-0.0013))/200000$

	E	F	G
1			NRF REACTOR SIZE STUDY CASE 8
2			Cs =36 Ci/Gal (Average all waste)
3			NO2 Destruction Rate= 0.01 M/Mon.
4			TK-49 Temp. = 40°C
5			TK-49 Sample Cycle = 3 Months
6			TK-49 NO2 Range = 0.029 to 0.059 M
7			Process Rate = 42,500 Gal/Mon (75% of BDR)
8			NRF Reactors 2-80,000 gallons
9			
10			
11			
12	TIME	TANK49	NRF-1
13	DAYS	MNO2	MNO2
14	0	0.059	0.029
15	15	0.054	0.024
16	30	0.049	0.019
17	45	0.044	0.014
18	60	0.039	0.011
19	75	0.034	$=(21250 \cdot (F18-0.005)+58750 \cdot (G18-0.005))/80000$
20	90	0.059	$=(21250 \cdot (F19-0.005)+58750 \cdot (G19-0.005))/80000$
21	105	0.054	$=(21250 \cdot (F20-0.005)+58750 \cdot (G20-0.005))/80000$
22	120	0.049	$=(21250 \cdot (F21-0.005)+58750 \cdot (G21-0.005))/80000$
23	135	0.044	$=(21250 \cdot (F22-0.005)+58750 \cdot (G22-0.005))/80000$
24	150	0.039	$=(21250 \cdot (F23-0.005)+58750 \cdot (G23-0.005))/80000$
25	165	0.034	$=(21250 \cdot (F24-0.005)+58750 \cdot (G24-0.005))/80000$
26	180	0.059	$=(21250 \cdot (F25-0.005)+58750 \cdot (G25-0.005))/80000$
27	195	0.054	$=(21250 \cdot (F26-0.005)+58750 \cdot (G26-0.005))/80000$
28	210	0.049	$=(21250 \cdot (F27-0.005)+58750 \cdot (G27-0.005))/80000$
29	225	0.044	$=(21250 \cdot (F28-0.005)+58750 \cdot (G28-0.005))/80000$
30	240	0.039	$=(21250 \cdot (F29-0.005)+58750 \cdot (G29-0.005))/80000$
31	255	0.034	$=(21250 \cdot (F30-0.005)+58750 \cdot (G30-0.005))/80000$
32	270	0.059	$=(21250 \cdot (F31-0.005)+58750 \cdot (G31-0.005))/80000$
33	285	0.054	$=(21250 \cdot (F32-0.005)+58750 \cdot (G32-0.005))/80000$
34	300	0.049	$=(21250 \cdot (F33-0.005)+58750 \cdot (G33-0.005))/80000$
35	315	0.044	$=(21250 \cdot (F34-0.005)+58750 \cdot (G34-0.005))/80000$
36	330	0.039	$=(21250 \cdot (F35-0.005)+58750 \cdot (G35-0.005))/80000$
37	345	0.034	$=(21250 \cdot (F36-0.005)+58750 \cdot (G36-0.005))/80000$
38	360	0.059	$=(21250 \cdot (F37-0.005)+58750 \cdot (G37-0.005))/80000$
39	375	0.054	$=(21250 \cdot (F38-0.005)+58750 \cdot (G38-0.005))/80000$
40	390	0.049	$=(21250 \cdot (F39-0.005)+58750 \cdot (G39-0.005))/80000$
41	405	0.044	$=(21250 \cdot (F40-0.005)+58750 \cdot (G40-0.005))/80000$
42	420	0.039	$=(21250 \cdot (F41-0.005)+58750 \cdot (G41-0.005))/80000$
43		0.034	$=(21250 \cdot (F42-0.005)+58750 \cdot (G42-0.005))/80000$

	H
1	CASE 8
2	
3	
4	
5	
6	
7	
8	
9	
10	
11	
12	NRF-2
13	MNO2
14	0.029
15	0.024
16	0.019
17	0.014
18	0.011
19	$=(21250^*(G18-0.005)+58750^*(H18-0.005))/80000$
20	$=(21250^*(G19-0.005)+58750^*(H19-0.005))/80000$
21	$=(21250^*(G20-0.005))/80000$
22	$=(21250^*(G21-0.005))/80000$
23	$=(21250^*(G22-0.005))/80000$
24	$=(21250^*(G23-0.005)+58750^*(H23-0.005))/80000$
25	$=(21250^*(G24-0.005)+58750^*(H24-0.005))/80000$
26	$=(21250^*(G25-0.005)+58750^*(H25-0.005))/80000$
27	$=(21250^*(G26-0.005)+58750^*(H26-0.005))/80000$
28	$=(21250^*(G27-0.005)+58750^*(H27-0.005))/80000$
29	$=(21250^*(G28-0.005)+58750^*(H28-0.005))/80000$
30	$=(21250^*(G29-0.005)+58750^*(H29-0.005))/80000$
31	$=(21250^*(G30-0.005)+58750^*(H30-0.005))/80000$
32	$=(21250^*(G31-0.005)+58750^*(H31-0.005))/80000$
33	$=(21250^*(G32-0.005)+58750^*(H32-0.005))/80000$
34	$=(21250^*(G33-0.005)+58750^*(H33-0.005))/80000$
35	$=(21250^*(G34-0.005)+58750^*(H34-0.005))/80000$
36	$=(21250^*(G35-0.005)+58750^*(H35-0.005))/80000$
37	$=(21250^*(G36-0.005)+58750^*(H36-0.005))/80000$
38	$=(21250^*(G37-0.005)+58750^*(H37-0.005))/80000$
39	$=(21250^*(G38-0.005)+58750^*(H38-0.005))/80000$
40	$=(21250^*(G39-0.005)+58750^*(H39-0.005))/80000$
41	$=(21250^*(G40-0.005)+58750^*(H40-0.005))/80000$
42	$=(21250^*(G41-0.005)+58750^*(H41-0.005))/80000$
43	$=(21250^*(G42-0.005)+58750^*(H42-0.005))/80000$

	E	F	G
1			NRF REACTOR SIZE STUDY CASE 9
2			Cs =36 Ci/Gal (Average all waste)
3			NO2 Destruction Rate= 0.01 M/Mon.
4			TK-49 Temp. = 50°C
5			TK-49 Sample Cycle = 1 Month
6			TK-49 NO2 Range = 0.036 TO 0.046 M
7			Process Rate = 42,500 Gal/Mon (75% of BDR)
8			NRF Reactors 2-75,000 gallons
9			
10			
11			
12	TIME	TK 49	NRF-1
13	DAYS	M NO2	M NO2
14	0	0.046	0.036
15	15	0.041	0.031
16	30	0.046	0.026
17	45	0.041	0.021
18	60	0.046	0.016
19	75	0.041	0.011
20	90	0.046	$=(21250*(F19-0.005)+53750*(G19-0.005))/75000$
21	105	0.041	$=(21250*(F20-0.005)+53750*(G20-0.005))/75000$
22	120	0.046	$=(21250*(F21-0.005)+53750*(G21-0.005))/75000$
23	135	0.041	$=(21250*(F22-0.005)+53750*(G22-0.005))/75000$
24	150	0.046	$=(21250*(F23-0.005)+53750*(G23-0.005))/75000$
25	165	0.041	$=(21250*(F24-0.005)+53750*(G24-0.005))/75000$
26	180	0.046	$=(21250*(F25-0.005)+53750*(G25-0.005))/75000$
27	195	0.041	$=(21250*(F26-0.005)+53750*(G26-0.005))/75000$
28	210	0.046	$=(21250*(F27-0.005)+53750*(G27-0.005))/75000$
29	225	0.041	$=(21250*(F28-0.005)+53750*(G28-0.005))/75000$
30	240	0.046	$=(21250*(F29-0.005)+53750*(G29-0.005))/75000$
31	255	0.041	$=(21250*(F30-0.005)+53750*(G30-0.005))/75000$
32	270	0.046	$=(21250*(F31-0.005)+53750*(G31-0.005))/75000$
33	285	0.041	$=(21250*(F32-0.005)+53750*(G32-0.005))/75000$
34	300	0.046	$=(21250*(F33-0.005)+53750*(G33-0.005))/75000$
35	315	0.041	$=(21250*(F34-0.005)+53750*(G34-0.005))/75000$
36	330	0.046	$=(21250*(F35-0.005)+53750*(G35-0.005))/75000$
37	345	0.041	$=(21250*(F36-0.005)+53750*(G36-0.005))/75000$
38	360	0.046	$=(21250*(F37-0.005)+53750*(G37-0.005))/75000$
39	375	0.041	$=(21250*(F38-0.005)+53750*(G38-0.005))/75000$
40	390	0.046	$=(21250*(F39-0.005)+53750*(G39-0.005))/75000$
41	405	0.041	$=(21250*(F40-0.005)+53750*(G40-0.005))/75000$
42	420	0.046	$=(21250*(F41-0.005)+53750*(G41-0.005))/75000$
43	435	0.041	$=(21250*(F42-0.005)+53750*(G42-0.005))/75000$

	H
1	CASE 9
2	
3	
4	
5	
6	
7	
8	
9	
10	
11	
12	NRF-2
13	MNO2
14	0.036
15	0.031
16	0.026
17	0.021
18	0.016
19	0.011
20	$=(21250 \cdot (G19-0.005) + 53750 \cdot (H19-0.005)) / 75000$
21	$=(21250 \cdot (G20-0.005) + 53750 \cdot (H20-0.005)) / 75000$
22	$=(21250 \cdot (G21-0.005)) / 75000$
23	$=(21250 \cdot (G22-0.005)) / 75000$
24	$=(21250 \cdot (G23-0.005)) / 75000$
25	$=(21250 \cdot (G24-0.005)) / 75000$
26	$=(21250 \cdot (G25-0.005)) / 75000$
27	$=(21250 \cdot (G26-0.005) + 53750 \cdot (H26-0.005)) / 75000$
28	$=(21250 \cdot (G27-0.005) + 53750 \cdot (H27-0.005)) / 75000$
29	$=(21250 \cdot (G28-0.005) + 53750 \cdot (H28-0.005)) / 75000$
30	$=(21250 \cdot (G29-0.005) + 53750 \cdot (H29-0.005)) / 75000$
31	$=(21250 \cdot (G30-0.005) + 53750 \cdot (H30-0.005)) / 75000$
32	$=(21250 \cdot (G31-0.005) + 53750 \cdot (H31-0.005)) / 75000$
33	$=(21250 \cdot (G32-0.005) + 53750 \cdot (H32-0.005)) / 75000$
34	$=(21250 \cdot (G33-0.005) + 53750 \cdot (H33-0.005)) / 75000$
35	$=(21250 \cdot (G34-0.005) + 53750 \cdot (H34-0.005)) / 75000$
36	$=(21250 \cdot (G35-0.005) + 53750 \cdot (H35-0.005)) / 75000$
37	$=(21250 \cdot (G36-0.005) + 53750 \cdot (H36-0.005)) / 75000$
38	$=(21250 \cdot (G37-0.005) + 53750 \cdot (H37-0.005)) / 75000$
39	$=(21250 \cdot (G38-0.005) + 53750 \cdot (H38-0.005)) / 75000$
40	$=(21250 \cdot (G39-0.005) + 53750 \cdot (H39-0.005)) / 75000$
41	$=(21250 \cdot (G40-0.005) + 53750 \cdot (H40-0.005)) / 75000$
42	$=(21250 \cdot (G41-0.005) + 53750 \cdot (H41-0.005)) / 75000$
43	$=(21250 \cdot (G42-0.005) + 53750 \cdot (H42-0.005)) / 75000$

	E	F	G
1			NRF REACTOR SIZE STUDY CASE 10
2			Cs =23.2 Ci/Gal (Average First 5 Years)
3			NO2 Destruction Rate= 0.064 M/Mon.
4			TK-49 Temp. = 40°C
5			TK-49 Sample Cycle = 1 Months
6			TK-49 NO2 Range = 0.029 to 0.0354 M
7			Process Rate = 42,500 Gal/Mon (75% of BDR)
8			NRF Reactors 2-80,000 gallons
9			
10			
11			
12			
13	TIME	TANK 49	NRF-1
14	DAYS	MNO2	MNO2
16	0	0.0354	0.029
17	15	=F16-0.0032	=G16-0.0032
18	30	0.0354	=G17-0.0032
19	45	=F18-0.0032	=G18-0.0032
20	60	0.0354	=G19-0.0032
21	75	=F20-0.0032	=G20-0.0032
22	90	0.0354	=(21250*(F21-0.0032)+58750*(G21-0.0032))/80000
23	105	=F22-0.0032	=(21250*(F22-0.0032)+58750*(G22-0.0032))/80000
24	120	0.0354	=(21250*(F23-0.0032)+58750*(G23-0.0032))/80000
25	135	=F24-0.0032	=(21250*(F24-0.0032)+58750*(G24-0.0032))/80000
26	150	0.0354	=(21250*(F25-0.0032)+58750*(G25-0.0032))/80000
27	165	=F26-0.0032	=(21250*(F26-0.0032)+58750*(G26-0.0032))/80000
28	180	0.0354	=(21250*(F27-0.0032)+58750*(G27-0.0032))/80000
29	195	=F28-0.0032	=(21250*(F28-0.0032)+58750*(G28-0.0032))/80000
30	210	0.0354	=(21250*(F29-0.0032)+58750*(G29-0.0032))/80000
31	225	=F30-0.0032	=(21250*(F30-0.0032)+58750*(G30-0.0032))/80000
32	240	0.0354	=(21250*(F31-0.0032)+58750*(G31-0.0032))/80000
33	255	=F32-0.0032	=(21250*(F32-0.0032)+58750*(G32-0.0032))/80000
34	270	0.0354	=(21250*(F33-0.0032)+58750*(G33-0.0032))/80000
35	285	=F34-0.0032	=(21250*(F34-0.0032)+58750*(G34-0.0032))/80000
36	300	0.0354	=(21250*(F35-0.0032)+58750*(G35-0.0032))/80000
37	315	=F36-0.0032	=(21250*(F36-0.0032)+58750*(G36-0.0032))/80000
38	330	0.0354	=(21250*(F37-0.0032)+58750*(G37-0.0032))/80000
39	345	=F38-0.0032	=(21250*(F38-0.0032)+58750*(G38-0.0032))/80000
40	360	0.0354	=(21250*(F39-0.0032)+58750*(G39-0.0032))/80000
41	375	=F40-0.0032	=(21250*(F40-0.0032)+58750*(G40-0.0032))/80000
42	390	0.0354	=(21250*(F41-0.0032)+58750*(G41-0.0032))/80000
43	405	=F42-0.0032	=(21250*(F42-0.0032)+58750*(G42-0.0032))/80000
44	420	0.0354	=(21250*(F43-0.0032)+58750*(G43-0.0032))/80000
45	435	=F44-0.0032	=(21250*(F44-0.0032)+58750*(G44-0.0032))/80000
46	450	0.0354	=(21250*(F45-0.0032)+58750*(G45-0.0032))/80000
47		=F46-0.0032	=(21250*(F46-0.0032)+58750*(G46-0.0032))/80000

	H	I
1	CASE 10	
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13	NRF-2	
14	MNO2	
16	0.029	
17	=H16-0.0032	
18	=H17-0.0032	
19	=H18-0.0032	
20	=H19-0.0032	
21	=H20-0.0032	
22	=H21-0.0032	
23	=(21250*(G22-0.0032)+58750*(H22-0.0032))/80000	
24	=(21250*(G23-0.0032)+58750*(H23-0.0032))/80000	
25	=(21250*(G24-0.0032)+58750*(H24-0.0032))/80000	
26	=(21250*(G25-0.0032)+58750*(H25-0.0032))/80000	
27	=(21250*(G26-0.0032)+58750*(H26-0.0032))/80000	
28	=(21250*(G27-0.0032)+58750*(H27-0.0032))/80000	
29	=(21250*(G28-0.0032)+58750*(H28-0.0032))/80000	
30	=(21250*(G29-0.0032)+58750*(H29-0.0032))/80000	
31	=(21250*(G30-0.0032)+58750*(H30-0.0032))/80000	
32	=(21250*(G31-0.0032)+58750*(H31-0.0032))/80000	
33	=(21250*(G32-0.0032)+58750*(H32-0.0032))/80000	
34	=(21250*(G33-0.0032)+58750*(H33-0.0032))/80000	
35	=(21250*(G34-0.0032)+58750*(H34-0.0032))/80000	
36	=(21250*(G35-0.0032)+58750*(H35-0.0032))/80000	
37	=(21250*(G36-0.0032)+58750*(H36-0.0032))/80000	
38	=(21250*(G37-0.0032)+58750*(H37-0.0032))/80000	
39	=(21250*(G38-0.0032)+58750*(H38-0.0032))/80000	
40	=(21250*(G39-0.0032)+58750*(H39-0.0032))/80000	
41	=(21250*(G40-0.0032)+58750*(H40-0.0032))/80000	
42	=(21250*(G41-0.0032)+58750*(H41-0.0032))/80000	
43	=(21250*(G42-0.0032)+58750*(H42-0.0032))/80000	
44	=(21250*(G43-0.0032)+58750*(H43-0.0032))/80000	
45	=(21250*(G44-0.0032)+58750*(H44-0.0032))/80000	
46	=(21250*(G45-0.0032)+58750*(H45-0.0032))/80000	
47	=(21250*(G46-0.0032)+58750*(H46-0.0032))/80000	

APPENDIX H. OVERHEAD SLIDES FROM TASK FORCE PRESENTATION

TASK FORCE IMPACT OF NITRITE ON DWPF

TASK FORCE CHARTER

- Evaluate options to eliminate or mitigate impact of the Sodium Nitrite Corrosion Inhibitor on DWPF.

Evaluate For:

- Technical feasibility and risk
- Schedule impact (6/94 Rad. Op.)
- Cost Impact

- Recommend Low Technical /Risk Option

(Schedule should be achievable via a work around if required - initial attainment penalty is acceptable)

- 1 week to complete

TASK FORCE

JIM MAREK	DWPT	PRECIPITATE HYDROLYSIS
DOUG WALKER	IWT	ITP & RAD CHEMISTRY
DENNY BICKFORD	DWPT	MELTER, GLASS, CORROSION
PAUL D'ENTREMONT	WM	TANK FARM TECHNICAL
DOUG BROWN	WM	ITP-TECHNICAL
JIM McGLYNN	WM	ITP - OPS
JACK NELSON	BECHTEL	DWPF PROJECTS
DAVE McGUIRE	DWPF	DWPF-OPS
PHIL ZAPP	MTS	WASTE TANK/CORROSION
MARTHA BROADWATER	HR	SECRETARIAL SUPPORT

CONSULTANTS

JOHN GRAY	ATD	NITROGEN CHEMISTRY
RUSS EIBLING	DWPT	ORGANIC & NITRITE CHEMISTRY
DAVE HOBBS	SRL/IWT	CORROSION CHEMISTRY
BOB ONDRECJIN	SRL/MTS	TANK CORROSION LIMITS
DAVE CHOSTNER	SEP. TECH	F-CANYON PROCESS
JOE GENTILUCCI	DWPF	PROCESS
BILL VAN PELT	WM	TANK FARM & ITP TECHNICAL
BRUCE LONG	WM	WM - OPS
DICK POSTLES	SRT	STATISTICIAN

PRESENTATION

- Problem Description - Doug Walker
- Task Force Recommendation:
 - Long Term Solution - Jim Marek
 - Start-up Work Around - Jim Marek
 - COC Modifications - Dave McGuire
- Cost and Schedule - Jack Nelson
- Immediate Actions Required - Jim Marek
- Generic Recommendations - Paul D'Entremont
- Other Potential Options:
 - Late Washing - Doug Brown
 - Salt Modifications
 - NH₂N0₃ without mitigation

PROBLEM

ACCUMULATION OF AMMONIUM NITRATE AND ORGANICS IN TNX PILOT OPERATIONS VENT SYSTEM AFTER INCLUSION OF NOBLE METALS IN FEED.

IMPLICATIONS FOR DWPF:

- POTENTIAL EXPLOSION HAZARD**
- SEVERE ATTAINMENT REDUCTION**

NITRITE CHEMISTRY

TECHNICAL OVERVIEW

SALT PROCESS CELL

TECHNICAL CERTAINTY

SS NITRITE RADIOLYSIS TANK

90%

RETAIN HAN, VENT AMMONIA
AND PHYSICALLY SEPARATE
ORGANICS

60/80%

LATE WASHING FACILITY

70%

CHEMICAL PROCESSING CELL

AMMONIA SCRUBBERS &
VENT AT PUMP PIT

75%

USE NITRIC ACID IN SRAT

69%

NOTE: RATINGS ARE RELATIVE NOT ABSOLUTE PROBABILITIES

LONG TERM RECOMMENDATIONS FOR HIGHEST TECHNICAL CERTAINTY

TANK FARM / SPC

- Install nominal 1 MM gallon stainless steel tank for Radiolytic Removal of Nitrite

CPC MODIFICATIONS

- Design and Install scrubbers in vessel vents

SS RADIOLYSIS TANK

DESCRIPTION AND APPROACH:

- Nominal 1MM gallon tank for full attainment
- Existing tanks at low attainment
- Radiolysis will reduce nitrite below 0.01 M
- Operate SPC without HAN

BENEFITS/RISKS:

- Minimum Technical risk
- Reduces organics as well as ammonium nitrate
- No change in IOP operating plans or startup date
- Frees Tank 49 for other uses

SS RADIOLYSIS TANK (Cont'd.)

TECHNICAL CERTAINTIES:

- Radiolytic nitrite destruction demonstrated experimentally

TECHNICAL RISKS:

- Low Cs-137 concentrations increase radiolysis time
- Need to demonstrate hydrolysis on irradiated feed/no HAN
- Doesn't affect non-HAN ammonia

STARTUP RECOMMENDATIONS

- Use existing pump pit tanks for radiolytic nitrite removal.
- Meet 8/94 rad operation startup date with severe attainment penalty.
- Operations improvement to increase startup attainment.
- Start cold chemical runs on schedule at ≤ 0.01 M nitrite.
- New Task Force to optimize startup attainment.

IMMEDIATE ACTIONS **REQUIRED FOR SUCCESS**

- Demonstrate modified DWPF flowsheet at TNX
 - Work around nitrite levels
 - Long term nitrite levels
- Provide design basis for vent system scrubbers
- Aggressive development effort on nitric acid sludge flowsheet
- Demonstrate the lack of any NH_4TPB in Precipitate
- Corrosion data on SS in zero-nitrite
- Corrosion studies in shielded cells

CPC - MODIFICATIONS TO MITIGATE

AMMONIUM NITRATE

DESCRIPTION: • Scrub Ammonia and Release at Pump Pit

APPROACH: • Prevent NH₃ from entering FAVC exhaust and PVVH.
• Install scrubber jumpers on FAVC exit and RCT vent.
• NH₃ liberated in SRAT on pH shift, and in RCT when neutralized.
• Scrubbed NH₃ maintained in Recycle Waste liquid by operating scrubber during RCT neutralization.
• NH₃ released through Pump Pit vessel vents.

CONTINGENCY: • Analyze for NH₃ in SRAT/SME off gas.
• Modify PVV filter to allow flood and soak removal of ammonium nitrate deposition.
• Periodic jumper/PVVH inspection and cleaning.
TECHNICAL CERTAINTY: > 75%

SCHEDULE IMPACT: • Meets 6/94 DWPF Rad start-up milestone

CPC Option: Scrub Ammonia and Release at Pump Pit

TECHNICAL CERTAINTY:

- Water is proven effective scrub for NH₃ gas
- F & H Canyon experience using scrubber jumpers
- Ability to remove, inspect and clean SRAT, SME and FAVC jumpers and PVV filter

TECHNICAL RISK:

- Environmental impact of NH₃ release at Pump Pits
- SMECT goes alkaline thereby releasing NH₃

TASK FORCE - NITRITE IMPACT

CPC MODIFICATIONS TO MITIGATE AMMONIUM NITRATE

CPC Option: Scrub Ammonia and Release at Pump Pit

PATH FORWARD

- Revise environmental permit for NH₃, or pursue catalytic converter.
- Determine need/method of maintaining SMECT acidic.
- Design/Fabricate and test scrubber jumpers.
- Modify PVV filter to allow flood and soak removal of ammonium nitrate.
- Assess attainment impact due to increased load from scrubber water:
 - Minimize RCT neutralization cycle by no post-nitrite addition sample verification.

COST AND SCHEDULE SUMMARY

OPTION **\$ MILLION** **READY FOR
RADIOACTIVE START***

Nitrite Radiolysis

- Short Term < 1 3/93
- Long Term 35-50 3/97

CPC Modifications

3-5 4/94

Target Radioactive Start is 6/94

- * Assumes R&D start 1/92
- Assumes no funding restraints

TASK FORCE - NITRITE IMPACT

NITRITE RADIOLYSIS SCHEDULE

CPC OPTIONS SCHEDULE

GENERIC RECOMMENDATIONS

TANK FARM:

- To improve attainment during pump pit work around:
 - Pursue additional washing and waste tank cooling to reduce nitrite levels.
 - Improve sampling, analysis and inhibitor addition capabilities in ITP.
 - Evaluate/Improve inspection techniques for Tank 49.
- Develop viable plan to re-work washed precipitate.

GENERIC RECOMMENDATIONS

DWPF:

- To guarantee safety:
 - Implement NH₃ monitoring and periodic inspection/cleaning of jumpers and PVV filter.
- To fully test DWPF and the additional complexity of DWPF versus the pilot facilities:
 - Include noble-metal runs in DWPF cold-run testing.

LATE WASHING

(also known as final washing)

DESCRIPTION: Remove nitrite prior to transfer to DWPF, by reprecipitating and rewashing small batches of ITP product in a new stainless steel facility.

TECHNICAL CERTAINTY: >70%

PROCESS DETAILS: Operate ITP per current plans
 Construct a "half-size/scope" ITP

BENEFITS: Increase ITP attainment
 Eliminate ammonia & organic problems
 Eliminate use of HAN (improving safety)
 Reduce glass production

Late Washing - Tech Considerations

CERTAINTIES: • Would reduce nitrite content of feed to SPC

- Would eliminate need for HAN in SPC and improve process safety hazard by reducing flammability hazard
- Would eliminate production of high-boilers in SPC
- Would eliminate production of ammonia in SPC
- Would reduce sodium content of feed to DWPF, thus reducing glass production
- Would not require any new chemicals
- Would reduce amount of TPB-decomposition products (from storage in Tank-49) in feed to SPC

Late Washing - Tech Considerations

PENALTIES:

- Additional facility, manpower, operating expense, "hassle" (double the total ITP workload)
- Increased Saltstone production & benzene generation & NaTPB consumption
- Increased complexity/coupling between ITP and S-area

UNCERTAINTIES:

- Z-area ability to accept the increased organic content (the TPB decomposition products) has not been demonstrated
- Crossflow filter process/design has not been demonstrated on irradiated feed (rheology changes)

SPC MODIFICATIONS TO MITIGATE AMMONIUM NITRATE

DESCRIPTION: RETAIN HAN AND VENT AMMONIA

APPROACH: • Combined Chemical/Engineered solution.

- Separate SPC vent from PVVH.
- Route separately through new facility, located outside 221-S consisting of:

Exhaust blower

Filter

Building Structure

Benzene Abate. Tie-in

(Possible) Catalytic Converter

- Vent NH₃ through new stack (or into existing Zone 1 air tunnel after catalytic conversion)

• Use existing spare line(s) for new SPC vent.

TECHNICAL: CERTAINLY PR to operate ammonia.
Neutralize PR to \$7MM - \$12M

COST:

SCHEDULE:

Typical 1/96 ; Aggressive and efficient
schedule could meet FFCA commitment
of 7/95

SPC Option: Retain HAN and Vent Ammonia

TECHNICAL CERTAINTY:

- Two Spare Lines available.
- NH₃ liberation by PR caustic addition has been demonstrated on bench scale.
- SPC vent re-route design already conceptualized for benzene abatement proposal.
- High degree of confidence in both engineering and chemical feasibility.
- Environmental Impact of NH₃ release. (Potential need for catalytic converter)

TECHNICAL RISK:

- PATH FORWARD:**
- Revise environmental permit for NH₃, or pursue catalytic converter.
 - Demonstrate PR neutralization at PHEF; assess PR cycle attainment impact.
 - Evaluate use of LiOH, and impact on frit specification

BENEFITS / PENALTIES

<p>CERTAIN:</p> <ul style="list-style-type: none"> • Allows for Benzene Abatement Tie-Ins • Separates MOC from LEL Control • Simplifies SPC Pressure Control • No change to ITP operation • Reduced flammability hazard (in PVVH and overall) • More flexibility for PVVH vacuum control 	<p>CERTAIN:</p> <ul style="list-style-type: none"> • Attainment: Increase PR batch cycle time. • New exhaust/filter facility outside of canyon • New cold chemical feed equipment
<p>UNKNOWN:</p> <ul style="list-style-type: none"> • Potential benefit in redesign of FAVC HEME for H2 concern if PVVH can be operated at lower vacuum 	<p>UNKNOWN:</p> <ul style="list-style-type: none"> • Added glass load to compensate for LiOH addition • Additional formic acid requirement in CPC to acidify PHA • Impact during DWPF Chemical Runs

Physical Separation of Organic Coated Solids

APPROACH: The organic-coated solids are allowed to settle in the PRBT. The clean aqueous phase is transferred to the SRAT as in the current operating scheme. The solids are re-suspended and transferred to the SME after cool-down.

TECHNICAL CERTAINTY: A reduction in the quantity of organics transferred into the boiling SRAT vessel.

TECHNICAL RISKS: The reduction may not be sufficient to significantly increase attainment.

Does not reduce quantity of ammonium nitrate.

Settling time not Determined

Cycle Time not Determined

SCHEDULE IMPACT: Not further evaluated. Option presented to supplement others that mitigate ammonium, but have no reduction in quantity of high boilers.

LATE PRECIPITATE WASH SCHEDULE

RETAIN HAN AND VENT AMMONIA

Critical Path

SUMMARY

- Stainless Steel Radiolysis Tank concept provides a solution that does not compromise either Waste Management or DWPF Operations.
- There may be other facility/tank combinations that would provide a faster, less-expensive work around with higher attainment. A team to assess this should be initiated.
- Strategy for Waste Management/DWPF/SRL must be developed and pursued as soon as possible.
- SRL work will be prioritized to address the "Immediate Action" data needs as soon as possible.

OPTIONS CONSIDERED

SELECTED: • CPC vent scrubbers & S/S radiolysis vessels

OTHERS:

- Late wash
- SPC vent re-route
- Minimize nitrite by inhibiting with hydroxide
- Minimize nitrite by additional washing
- Acidify FAVC HEME spray (instead of separate scrubber)
- Don't use HAN (foul terribly)
- Additional washings to level not requiring inhibitor

<50%:

- Alternate inhibitor
- Supplement inhibitor
- Corrosion allowance
- Operate at higher precipitate solids
- Chillers to cool waste tanks
- Ammonium nitrate absorber
- Ammonia gas scrubber in SPC
- Catalytic combustion of ammonia
- Incorporate explosion-proof design, rupture disc
- Flush PVVH
- Steam/Cooling jackets around SRAT/SME jumpers

TASK FORCE - NITRITE IMPACT

THIS ENDS ORIGINAL TALK

TECHNICAL CONSIDERATIONS

CERTAINTIES:

- Nitrite destruction by radiolysis demonstrated experimentally
- Documented corrosion database for nitrite inhibitor in TK 49.
- Literature data and SRL tests support precipitate compatibility with stainless steel.

UNCERTAINTIES:

- Variations in Cs-137 will affect attainment.
- Acid hydrolysis at 0-0.01 M nitrite (W/O HAN) not demonstrated on large scale or with irradiated precipitate.
- Tk 49 minimum acceptable operating margin for nitrite (above OSR requirement) not established.

CRITERIA/CONSTRAINTS

Criteria for Initial Cull: Must have greater than 50% chance of success.

Chance for evaluating "The Short List" of Options:

- **Probability of success (ignoring cost and schedule)**
- **Estimated reduction of ammonium nitrate in**
 - **Salt Process Cell (90% of total)**
 - **Chemical Process Cell (10% of total)**
- **Effect on Attainment**
- **Need for new equipment**
- **Degree of coupling of tank farm to DWPF**
- **Effect on waste tank integrity**
- **Environmental/safety effects**
- **Cost and Schedule**

SUMMARY AND CONCLUSION

2 Independent parts to problem in CPC, SPC.

- **Recommend immediate CPC design changes.**
 - **Nitric acid based SRAT cycle.**
 - **Scrub NH₃ and vent to separate filter and stack.**
 - **Route organic residue to SME.**

Two Alternative SPC Changes:

- **Radiolytic destruction of nitrite in stainless steel.**
- **Vent NH₃ from Salt Cell to separate filter and stack.**

SM NITRITE RADIOLYSIS TANK (CONT'D)

TECHNICAL CERTAINTIES:

- High confidence
- No Han needed in SPC

TECHNICAL RISKS:

- Low Cs-137 concentrations increase radiolysis time
- Need to demonstrate on irradiated feed
- Doesn't affect non-HAN ammonia

SM NITRITE RADIOLYSIS TANKAGE

DESCRIPTION AND APPROACH:

- Use existing DWPF pump pit tankage, or
- Build new stainless steel tankage -- minimum required to assure destruction
- Reduce nitrite concentration in ITP by additional washing

BENEFITS/RISKS:

- Minimum technical risk
- Reduces organics as well as ammonia
- Requires additional saltstone and impacts ITP and DWPF rates

TASK FORCE - NITRITE IMPACT

TEST

PATH FORWARD

Develop permits, schedule and cost for stainless tankage.

Develop (Permits?) schedule and cost for CPC changes.

Develop schedule and cost for alternative SPC.

Demonstrate CPC changes in IDMS.

Demonstrate NH₃ venting in PHEF.

AMMONIUM GENERATION

MAIN SOURCE: SALT PROCESS CELL

HAN DECOMPOSITION PRODUCES AMMONIUM

SECONDARY, MINOR SOURCE: CHEMICAL PROCESS CELL

POSTULATED REACTION: $\longrightarrow$

RELATED TO HYDROGEN GENERATION

pH DRIFT UP IN CPC - RELEASES NH_3 INTO VENT SYSTEM

REACTS WITH NO_x OR HNO_3

WHAT QUANTITY IS INSUFFICIENT TO CAUSE CONCERN?

AMMONIUM SENSITIZED DECOMPOSITION

Ammonium Nitrate As Explosive

Powerful Oxidant - Positive Oxygen Balance

Shock Sensitivity Increases with Temperature

10 kg weight from 20 cm.

2 kg weight from 79 cm.

Sensitized by Organic Compounds

Aniline, Diphenylamine, Azobenzene, Azoxybenzene

Detonation Velocity from 1100 to 2700 meters/sec

Minimum Diameter Required for Propagation

Unconfined : 7.5 - 13 cm

Confined: 4 cm

EFFECT OF NITRITE

NO REAGENT TO MITIGATE NITRITE

AMOUNT OF DIPHENYLAMINE TRANSFERRED TO CPC EACH
SRAT BATCH AS ESTIMATED FROM TWO CONSECUTIVE
BENCH-SCALE EXPERIMENTS:

H-45

<u>NO2- CONC., M</u>	<u>LBS DIPHENYLAMINE</u>
0.01	2.2
0.01	3.1
0.02	6.7
0.02	19.3
0.04	58
0.04	257

TASK FORCE - NITRITE IMPACT

TITLE

TASK FORCE - NITRITE IMPACT

IMPACT DIAGRAM

GLOSSARY

CAA	Federal Clean Air Act
CIF	Consolidated Incineration Facility
CPC	Chemical Process Cell
CPES	Chemical Process Evaluation System
CsTPB	Cesium Tetrphenylborate, $(C_6H_5)_4BCs$
DHEC	see SCDHEC
DWPF	Defense Waste Processing Facility
EPA	U.S. Environmental Protection Agency
ESP	Extended Sludge Processing
FAVC	Formic Acid Vent Condenser
FFCA	Federal Facilities Compliance Act
HAN	Hydroxylamine Nitrate, $NH_2OH \cdot HNO_3$
HEME	High-Efficiency Mist Eliminator
IDMS	Integrated DWPF Melter System (at TNX)
IPHS	Integrated Precipitate Hydrolysis System
ITP	In-Tank (Precipitation) Process
KTPB	Potassium Tetrphenylborate, $(C_6H_5)_4BK$
LEL	Lower Explosive Limit
MFT	Melter Feed Tank
MOC	Minimum Oxidant Concentration (for combustion)
NaTPB	Sodium Tetrphenylborate, $(C_6H_5)BNa$
OE	Organic Evaporator
OECD	Organic Evaporator Condenser-Decanter
OECT	Organic Evaporator Condensate Tank
OSHA	U.S. Occupational Safety and Health Administration
OWST	Organic Waste Storage Tank
PBA	Phenylboric Acid, $C_6H_5B(OH)_2$
PHA	Precipitate Hydrolysis Aqueous product
PHEF	Precipitate Hydrolysis Experimental Facility (at TNX)
PHP	Precipitate Hydrolysis Process
PR	Precipitate Reactor
PRBT	Precipitate Reactor Bottoms Tank
PRC	Precipitate Reactor Condenser (in the PHEF)
PRCD	Precipitate Reactor Condenser-Decanter
PRFT	Precipitate Reactor Feed Tank

GLOSSARY (Concluded)

PVVF	Process Vessel Vent Filter
PVVH	Process Vessel Vent Header
RCT	Recycle Collection Tank
S Area	SRS Vitrification Facility (DWPF)
SCDHEC	South Carolina Department of Health and Environmental Control
SCVC	Salt Cell Vent Condenser
SME	Slurry Mix Evaporator
SMECT	Slurry Mix Evaporator Condensate Tank
SPC	Salt Process Cell
SRAT	Sludge Receipt and Adjustment Tank
SRL	Savannah River Laboratory
SRP	Savannah River Plant
SRS	Savannah River Site
SRTC	Savannah River Technology Center (new name for SRL 4/1/92)
TNX	SRL's Semiworks Experimental Facility (in the 400 Area)
TOC	Total Organic Carbon (aromatic carbon + formate carbon)
TPB	Tetraphenylborate, $(C_6H_5)_4B^-$
UEL	Upper Explosive Limit
Z Area	Saltstone Facility

END

**DATE
FILMED**

5 / 4 / 93