SEP 22 1998
Station 15

21 ENGINEERING DATA TRANSMITTAL

Page 1 of 1
1. EDT 616:90

2. To: (Receiving Organization) 327 Projects	3. From: (Originating Organization) 327 Projects	4. Related EDT No.: N/A
5. Proj./Prog./Dept./Div.: 19340	6. Design Authority/ Design Agent/Cog. Engr.: JE Ham	7. Purchase Order No.: N/A
8. Originator Remarks: For Approval and Release. HAN 98200/K4 M11		9. Equip./Component No.: N/A
		10. System/Bldg./Facility: 327
11. Receiver Remarks: 11A. Design Baseline Document? ☐ Yes ☒ No		12. Major Assm. Dwg. No.: N/A
		13. Permit/Permit Application No.: N/A
		14. Required Response Date: September 15, 1998

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Approval Designator	Reason for Transmittal	Originator Disposition	Receiver Disposition
1	HNF-3365		Rev. 0	327 Fuel Element Return to K-Basin Quality Process Plan	Q	1,2		

16. KEY					
Approval Designator (F)		Reason for Transmittal (G)			Disposition (H) & (I)
E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7)		1. Approval 2. Release 3. Information	4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment	4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)									
(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.	(J) Name	(K) Signature
		Design Authority							
		Design Agent							
1	1	Cog.Eng. JE Ham	<i>JE Ham</i>	9/15/98	L1-06				
1		Cog. Mgr. DS Takasumi	<i>DS Takasumi</i>	9/15/98	L1-03				
1	1	QA DH Sandoz	<i>D.H. Sandoz</i>	9/16/98	L1-06				
		Safety							
		Env.							

18. JE Ham <i>JE Ham</i> 9/17/98 Signature of EDT Originator Date	19. JE Ham <i>JE Ham</i> 9/17/98 Authorized Representative Date for Receiving Organization	20. DS Takasumi <i>DS Takasumi</i> 9/17/98 Design Authority/ Cognizant Manager Date	21. DOE APPROVAL (if required) Ctrl. No. N/A ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments
---	--	---	--

327 SNF FUEL RETURN TO K-BASIN QUALITY PROCESS PLAN

J.E. Ham
Babcock and Wilcox Hanford Co., Richland, WA 99352
U.S. Department of Energy Contract DE-AC06-96RL13200

EDT/ECN: 616490 UC: 513
Org Code: 19340 Charge Code: K4M11 (HAN98200)
B&R Code: EW7002010 Total Pages: 5

Key Words: 327 Facility, SNF Fuel Element Return, K-Basin, 105-KE, Chem Nuc, CNS 1-13G, Cask

Abstract: The B&W Hanford Company's (BWHC) 327 Facility, in the 300 Area of the Hanford Site, contains Spent Nuclear Fuel (SNF) single fuel element canisters (SFEC) and fuel remnant canisters (FRC) which are to be returned to K-Basin. Seven shipments of up to six fuel canisters will be loaded into the CNS 1-13G Cask and transported to 105-KE.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

Release Approval Date 9/22/98

Release Stamp

Approved for Public Release

1.0 PURPOSE

The purpose of this Quality Process Plan is to ensure appropriate and effective quality assuring activities have been built into the work controlling documents and procedures.

2.0 SCOPE

The scope of this project is to return the Spent Nuclear Fuel (SNF) single fuel element canisters (SFEC) and fuel remnant canisters (FRC) from the 327 Building to the 105 KE Storage Basin via the CNS 1-13G Shipping Cask. The CNS 1-13G is a commercially owned cask which has been leased for use on the Hanford Site. A cask insert (liner/rack) will be used to hold up to six fuel canisters at one time inside the cask. The insert will be added to the cask prior to loading fuel canisters.

K-Basin will determine the fuel canisters for each shipment and provide written authorization prior to loading. K-Basin will also provide time/duration calculations for the sealed cask to ensure hydrogen gas limits will not be exceeded. A safety evaluation for packaging (SEP) has been written to allow use of the cask beyond the evaluations identified in the certificate of compliance (CoC) provided with the cask. The SEP was evaluated for the transport of up to six fuel assemblies (inner plus outer elements within canister) per shipment, using a cask insert.

Major activities for returning the fuel canisters include: receiving the cask, preparing and loading the fuel canisters, and loading shipping the cask to 105-KE.

3.0 OVERVIEW

The described activities will be performed under the standard operating procedure 3M-SOP-PTL-057, Receiving, Loading or Unloading, and Shipping CNS 1-13G Vertical Casks, and its supporting procedures. Babcock & Wilcox Hanford Company (BWHC) will be responsible for the preparation and loading of the fuel cansiters into the CNS 1-13G Cask. DynCorp TriCities will provide transportation, and crane & rigging support. Duke Engineering & Services Hanford, Inc. maintains ownership and management of the fuel, including coordination with Waste Management Federal Services, Inc., NW Operations (WMNW) for the preparation of shipping documents, scheduling road closures, and providing necessary inspections and oversight to ensure compliance with D.O.T. requirements.

4.0 PROCESS PLAN

RECEIVE CNS 1-13G CASK

The CNS 1-13G Cask will be delivered to the Hanford Site, and receipt inspected to verify it's acceptance for use in transporting SFECs. The cask will be transported empty to the 327 Building. After a radiological receipt inspection has been performed by an RCT, Crane & Rigging Services will remove the over-pack and place it in a lay-down area outside of the building. The cask will be moved into the truck-lock and surveyed again. Once surveyed, removed from the truck and transferred to the small basin, the cask will be opened and prepared for loading.

PREPARING AND LOADING THE FUEL CANISTERS

Each fuel canister authorized for shipment will be transported one at a time from the large basin to A-Cell via the small basin. The fuel canister identification label will be verified, and the gas trap removed. The fuel canister will be transported to the CNS 1-13G Cask and placed inside. This evolution will occur for each authorized fuel canister, up to the allowed six.

SHIPPING THE CNS 1-13G CASK

Once loaded with fuel canisters, the cask will be decontaminated, drained and sealed for shipment. The cask will be returned to the truck-lock, surveyed and loaded back onto the truck. It will be moved outside, over-packed, and surveyed again. The proper shipping documents will be completed and the cask will be transported to K-Basin for unloading. The cask will be unloaded by K-Basin personnel and returned for the next shipment.

Table 1

Activity	Product	Work Control Method	Procedure and Instruction	Lead Individual (Title & Co.)	Quality Assuring Actions
Receipt Inspection	Accepted for use at Hanford	FDH QA Inspection Plan	HNF-PRO-158	FDH QA	WMNW accepts shipping package per FDH Inspection Plan. BWHC HCT Supervisor verifies WMNW acceptance.
Receive CNS 1-13G Cask at 327 Building	Ready for transfer to Basin	Standard Operating Procedure	Section 5.1 of 3M-SOP-PTL-057 and 3M-SOP-PTL-071 when referenced	HCT Supervisor, BWHC	HCT verifies cask shipping package arrives free of flaws. HCT verifies cask external is free of flaws.
Transfer CNS 1-13G Cask to Basin	Ready for loading	Standard Operating Procedure	Section 5.2 of 3M-SOP-PTL-057	HCT Supervisor, BWHC	HCT verifies cask interior and gaskets/seals are free of flaws. QC verifies that all bolts/plugs are free from damage and not suspect counterfeit.
Load CNS1-13G Cask					
a. Move fuel canister to A-Cell	Ready for gas trap removal	Standard Operating Procedure	Section 5.4 of 3M-SOP-PTL-057 and 3M-SOP-PTL-084 when referenced	HCT Supervisor, BWHC	MBA Custodian verifies SNF shipment authorization. MBA Custodian verifies cask hydrogen calculations received.
		Standard Operating Procedure	3M-SOP-PTL-118	HCT Supervisor, BWHC	HCT signs CFML. HCT verifies fuel canister identification in large basin.
b. Remove gas trap	Ready for loading	Standard Operating Procedure	Section 5.4 of 3M-SOP-PTL-057	HCT Supervisor, BWHC	HCT verifies fuel canister ID in A-Cell.

c. Load fuel canister		Standard Operating Procedure	3M-SOP-PTL-118	HCT Supervisor, BWHC	QC verifies fuel canister ID in A-Cell. HCT signs CFMI.
Prepare CNS 1-13G Cask for shipping to 105-KE	Ready to Ship	Standard Operating Procedure	Section 5.5 & 5.6 of 3M-SOP-PTL-057	HCT Supervisor, BWHC	Procedure step.
		Standard Operating Procedure	3M-SOP-PTL-118	HCT Supervisor, BWHC	HCT signs CFMI.
				HCT Supervisor, BWHC	BWHC QC approves completion of procedure.

DISTRIBUTION SHEET

To	From	Page 1 of 1
Distribution	327 Projects	Date 09-15-98
Project Title/Work Order		EDT No. 616490
327 SNF Fuel Return to K-Basin Quality Process Plan		ECN No. N/A

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
------	------	-----------------------------	-----------	------------------------------	-----------------

RP Bodeau	L1-03	X
TL Erickson	L1-03	X
JE Ham	L1-06	X
KA Hedquist	L1-03	X
SH Norton	L1-02	X
DH Sandoz	L1-06	X
RW Stevens	L1-03	X
DS Takasumi	L1-03	X
Central Files	B1-07	X