EGG-WTD-9594 Vol. V
November 1991

APR 27 1992

**Idaho
National
Engineering
Laboratory**

*Managed
by the U.S.
Department
of Energy*

INFORMAL REPORT

**Preliminary Systems Design Study
Assessment Report**

**Volume V: Land Disposal Compliance and
Hydrogen Generation Restricted Concepts**

**J. L. Mayberry
F. Felzollahi
J. C. Del Signore**

*Work performed under
DOE Contract
No. DE-AC07-76ID01570*

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

This document contains new concepts or the author(s) interpretation of new calculations and/or measurements; accordingly, EG&G Idaho, Inc. is required by the United States Government to include the following disclaimer:

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights. References herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PRELIMINARY SYSTEMS DESIGN STUDY ASSESSMENT REPORT

Volume V
LAND DISPOSAL COMPLIANCE AND HYDROGEN
GENERATION RESTRICTED CONCEPTS

J. L. Mayberry
F. Feizollahi
J. C. Del Signore

Published November 1991

Idaho National Engineering Laboratory
EG&G Idaho, Inc.
Idaho Falls, Idaho 83415

Prepared for the
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
Under DOE Field Office, Idaho
Contract No. DE-AC07-76ID01570

MASTER

ds
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PRELIMINARY SYSTEMS DESIGN STUDY
ASSESSMENT REPORT
EGG-WTD-9594
Volume V

Prepared by:

John L. Mayberry, EG&G Idaho, Inc.

11-26-91
Date

Fred Feizollahi, Bechtel National, Inc.

11-19-91
Date

Chris Del Signore, EBASCO

11-19-91
Date

Reviewed and Approved by:

William J. Quapp, Manager Technology Demonstration,
Waste Technology Development Dept.

11-15-91
Date

ABSTRACT

The System Design Study (SDS), part of the Waste Technology Development Department at the Idaho National Engineering Laboratory (INEL), examined techniques available for the remediation of hazardous and transuranic waste stored at the Radioactive Waste Management Complex's Subsurface Disposal Area at the INEL. Using specific technologies, system concepts for treating the buried waste and the surrounding contaminated soil were evaluated. Evaluation included implementability, effectiveness, and cost. The SDS resulted in the development of technology requirements including demonstration, testing, and evaluation activities needed for implementing each concept.

The SDS results are published in eight volumes. Volume I contains an executive summary. The SDS summary and analysis of results are presented in Volume II. Volumes III through VII contain detailed descriptions of twelve system and four subsystem concepts. Volume VIII contains the appendixes.

ACKNOWLEDGMENTS

The authors would like to acknowledge the efforts of those that contributed to this report.

EG&G Idaho, Inc., Bechtel National, Inc., Ebasco Environmental, and IT Corp. for providing the assessments and functional and operational requirements for the 12 system and 4 subsystem concepts. Specifically, C. Klassy, K. Sherick and D. Haifner of EG&G Idaho, Inc., R. Schlueter, M. Pong, D. Harris, M. Beathard and P. Yen of Bechtel National, Inc., D. Prinzing, J. Bjorkstam, R. Vankateswar and S. Peck of Ebasco Environmental, J. Plum, J. Valdez, D. Vetter, M. Chavez, S. Djordevic, M. Swientoniewski, John McFee of IT Corp., and H. Kresny of Solmont Corporation.

Karen Grant and Janalee Nelson of EG&G Idaho, and Debra Iniquez of Bechtel National, Inc., for the extra effort required in editing this report.

CONTENTS

ABSTRACT	V-iii
ACKNOWLEDGMENTS	V-iv
ACRONYMS AND ABBREVIATIONS	V-xi
1. INTRODUCTION	V-1
1.1 Background	V-1
1.2 Organization of the System Design Study Report	V-2
1.3 Content and Organization of this Volume	V-2
1.4 System Concept Limitations	V-3
1.5 General Considerations and Assumptions Used in System Concepts Development	V-3
1.5.1 Waste Property Assumptions	V-3
1.5.2 General Assumptions	V-5
1.6 Criteria and Assumptions for Program Implementation Risk Assessment	V-6
1.6.1 Project Mission Need and Objectives	V-6
1.6.2 Technical and Performance Risk Considerations	V-7
1.6.3 Health and Safety Risk Considerations	V-8
1.6.4 Institutional Risk Considerations	V-9
1.6.5 Schedule Risk Considerations	V-10
1.6.6 Cost Risk Considerations	V-11
1.7 Cost Estimating Assumptions	V-11
1.7.1 Cost Estimating Guidelines	V-11
1.7.2 System Model Cost Estimate Normalization and Modification	V-13
1.8 Demonstration, Testing, and Evaluation Assessment Assumptions	V-14
2. THERMAL TREATMENT/SOLIDIFICATION SYSTEM WITH LOW-LEVEL WASTE PRESORT (3-IT-1)	V-21
2.1 Functional and Operational Requirements	V-21
2.1.1 System Description	V-21
2.1.2 System Boundaries	V-27

2.1.3	Process Functional Diagram	V-30
2.1.4	Facility Description	V-30
2.1.5	System Design Requirements	V-33
2.2	System Assessment	V-42
2.2.1	Current Status of Unit Operations	V-42
2.2.2	Program Implementation Risks	V-48
2.2.3	Unit Operations Pro and Con Analysis	V-55
2.2.4	Unit Operations Lead-Time Estimates	V-63
2.2.5	Rough Order of Magnitude Cost Estimates	V-63
2.2.6	System Evaluation Results	V-69
2.2.7	Summary of Demonstration, Testing, and Evaluation Needs	V-70
2.3	Recommendation for the System	V-70
3.	THERMAL TREATMENT/SOLIDIFICATION SYSTEM WITH POSTSORT (3-IT-3) . . .	V-72
3.1	Functional and Operational Requirements	V-72
3.2	System Assessment	V-78
4.	PYROLYSIS AND ACID LEACH WITH PLUTONIUM EXTRACTION SYSTEM (3-EB-6)	V-83
4.1	Functional and Operational Requirements	V-83
4.1.1	System Description	V-83
4.1.2	System Boundaries	V-84
4.1.3	Process Functional Diagram	V-84
4.1.4	Facility Description	V-87
4.1.5	System Design Requirements	V-89
4.2	System Assessment	V-90
4.2.1	Current Status of Unit Operations	V-90
4.2.2	Program Implementation Risks	V-96
4.2.3	Unit Operations Pro and Con Analysis	V-105
4.2.4	Unit Operations Lead-Time Estimates	V-108
4.2.5	Rough Order of Magnitude Cost Estimates	V-110
4.2.6	System Evaluation Results	V-111
4.2.7	Summary of Demonstration, Testing, and Evaluation Needs	V-114
4.3	Recommendation for the System	V-118
5.	MOLTEN SALT OXIDATION SYSTEM (3-BE-7)	V-119
5.1	Functional and Operational Requirements	V-119
5.1.1	System Description	V-119

5.1.2	System Boundaries	V-128
5.1.3	Process Functional Diagram	V-130
5.1.4	Facility Description	V-130
5.1.5	System Design Requirements	V-135
5.1.6	Interface Requirements	V-135
5.2	System Assessment	V-137
5.2.1	Current Status of Unit Operations	V-137
5.2.2	Program Implementation Risks	V-143
5.2.3	Unit Operations Pro and Con Analysis	V-151
5.2.4	Unit Operations Lead-Time Estimates	V-154
5.2.5	Rough Order of Magnitude Cost Estimates	V-154
5.2.6	System Evaluation Results	V-158
5.2.7	Summary of Demonstration, Testing, and Evaluation Needs	V-159
5.3	Recommendations for the System	V-164
6.	CHEMICAL OXIDATION/SOLIDIFICATION SYSTEM WITH LOW-LEVEL WASTE POSTSORT (3-IT-8)	V-165
6.1	Functional and Operational Requirements	V-165
6.1.1	System Description	V-165
6.1.2	System Boundaries	V-170
6.1.3	Process Functional Diagram	V-173
6.1.4	Facility Description	V-174
6.1.5	System Design Requirements	V-174
6.2	System Assessment	V-182
6.2.1	Current Status of Unit Operations	V-182
6.2.2	Program Implementation Risks	V-187
6.2.3	Unit Operations Pro and Con Analysis	V-194
6.2.4	Unit Operation Lead-Time Estimates	V-203
6.2.5	Rough Order of Magnitude Cost Estimates	V-203
6.2.6	System Evaluation Results	V-209
6.2.7	Summary of Demonstration, Testing, and Evaluation Needs	V-211
6.3	Recommendation for the System	V-211
7.	BIBLIOGRAPHY	V-213

FIGURES

V-1-1.	Categories of work effort and research and development or acquisition phases	V-16
V-1-2.	Breakdown of demonstration, testing, and evaluation activities during advanced development	V-17
V-2-1.	Process functional diagram for the Thermal Treatment/Solidification System with LLW Presort (3-IT-1)	V-23
V-2-2.	Plant layout for the Thermal Treatment/Solidification System with LLW Presort (3-IT-1)	V-31
V-3-1.	Process functional diagram for the Thermal Treatment Solidification System with LLW Postsort (3-IT-3)	V-73
V-3-2.	Facility layout for the Thermal Treatment/Solidification System with LLW Postsort (3-IT-3)	V-75
V-4-1.	Process functional diagram for the Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6)	V-85
V-4-2.	Floor plan for the Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6)	V-88
V-5-1.	Process functional diagram for the Molten Salt Oxidation System (3-BE-7)	V-131
V-5-2.	General arrangement for the Molten Salt Oxidation System (3-BE-7)	V-133
V-6-1.	Process functional diagram for the Chemical Oxidation/Solidification System with LLW Postsort (3-IT-8)	V-167
V-6-2.	Facility layout for the Chemical Oxidation/Solidification System with LLW Postsort (3-IT-8)	V-175

TABLES

V-2-1.	3-IT-1 summary of program implementation risks and major areas of concern	V-50
V-2-2.	Risk rankings of unit operations (3-IT-1)	V-51
V-2-3.	Open packages and sort packages analysis	V-57
V-2-4.	Organics treatment analysis	V-57
V-2-5.	Solidification analysis	V-58
V-2-6.	Shredder analysis	V-59
V-2-7.	Thermal treatment analysis	V-60
V-2-8.	Off-gas treatment analysis	V-61
V-2-9.	Organics treatment analysis	V-62
V-2-10.	Metal melt analysis	V-62
V-2-11.	DT&E assessment summary table for the Thermal Treatment/ Solidification System with LLW Presort (3-IT-1)	V-64
V-2-12.	Rough order of magnitude cost estimates (3-IT-1)	V-65
V-2-13.	Rating performance measurables for Thermal Treatment/Solidification System with LLW Presort (3-IT-1) . . .	V-71
V-3-1.	DT&E needs for the Thermal Treatment/Solidification System with LLW Presort (3-IT-3)	V-79
V-3-2.	Rough order of magnitude cost estimates (3-IT-3)	V-81
V-3-3.	Rating performance measurables for the Thermal Treatment/Solidification System with LLW Postsort (3-IT-3) . . .	V-82
V-4-1.	3-EB-6 summary of program implementation risks and major areas of concern	V-98
V-4-2.	DT&E assessment summary for the Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6)	V-109
V-4-3.	Rough order of magnitude cost estimates (3-EB-6)	V-112
V-4-4.	Rating performance measurables for the Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6)	V-115

V-4-5.	DT&E needs for the Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6)	V-116
V-5-1.	3-BE-7 summary of program implementation risks and major areas of concern	V-144
V-5-2.	DT&E assessment summary for the Molten Salt Oxidation System (3-BE-7)	V-155
V-5-3.	Rough order of magnitude cost estimates (3-BE-7)	V-156
V-5-4.	Rating performance measurables for the Molten Salt Oxidation System (3-BE-7)	V-160
V-5-5.	DT&E needs for the Molten Salt Oxidation System (3-BE-7)	V-161
V-6-1.	3-IT-8 summary of program implementation risks and major areas of concern	V-188
V-6-2.	Open packages and sort packages analysis	V-195
V-6-3.	Inerts treatment analysis	V-196
V-6-4.	Shredder analysis	V-196
V-6-5.	Chemical oxidation analysis	V-198
V-6-6.	Biological treatment/absorption analysis	V-198
V-6-7.	Dewatering analysis	V-199
V-6-8.	Off-gas treatment analysis	V-200
V-6-9.	Solidification analysis	V-200
V-6-10.	Liquid waste treatment	V-201
V-6-11.	Metal/melt analysis	V-202
V-6-12.	Lead decontamination analysis	V-202
V-6-13.	DT&E assessment summary for the Chemical Oxidation/Solidification System with LLW Postsort (3-IT-8)	V-204
V-6-14.	Rough order of magnitude cost estimates (3-IT-8)	V-205
V-6-15.	Rating performance measureables for the Chemical Oxidation/Solidification System with LLW Postsort (3-IT-8)	V-210
V-6-16.	DT&E needs for the Chemical Oxidation/Solidification System with LLW Postsort (3-IT-8)	V-212

ACRONYMS AND ABBREVIATIONS

AEC	U.S. Atomic Energy Commission
ALARA	as low as reasonably achievable
ANL-W	Argonne National Laboratory-West
ARAR	applicable or relevant and appropriate requirement
CAA	Clean Air Act
CCD	charged coupled device
CDIF	Component Development Integration Facility
CEA	Atomic Energy Commission (France)
CEPOD	catalytic electrolytic plutonium oxide dissolution
CEQ	Council of Environmental Quality
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
CM	construction management
CWA	Clean Water Act
DOD	U.S. Department of Defense
DOE	U.S. Department of Energy
DOE-ID	Department of Energy-Field Office, Idaho
DOT	U.S. Department of Transportation
dscf	dry standard cubic feet
DT&E	demonstration, testing, and evaluation
EG&G Idaho	EG&G Idaho, Inc.
EM	electromagnetics
EOF	energy optimizing furnace
EPA	U.S. Environmental Protection Agency

ER	environmental restoration
ERDA	Energy Research and Development Administration
ERP	Environmental Restoration Program
F&OR	functional and operational requirement
FFBD	functional flow block diagram
FOM	Figure of Merit
FS	feasibility study
FY	fiscal year
GPR	ground penetrating radar
HAZMAT	hazardous material
HEPA	high-efficiency particulate air (filter)
HVAC	heating, ventilating, and air conditioning
IAG	Interagency Agreement
INEL	Idaho National Engineering Laboratory
I/O	input/output
ISV	in situ vitrification
LANL	Los Alamos National Laboratory
LDR	land disposal restriction
LLNL	Lawrence Livermore National Laboratory
LLW	low-level waste
MAF	moisture and ash-free fraction
MF	melting furnace
MSA	Major System Acquisition
MSO	Molten Salt Oxidation
MSW	municipal solid waste
NEPA	National Environmental Policy Act of 1969

NPL	National Priorities List
NRC	U.S. Nuclear Regulatory Commission
NWCF	New Waste Calcining Facility
ORNL	Oak Ridge National Laboratory
PAF	plasma arc furnace
PAN	passive neutron counting
PCB	polychlorinated biphenyl
PCR	plasma centrifugal reactor
PEC	Plasma Energy Corporation
PFD	process functional diagram
PLC	programmable logic controller
PLPF	Plutonium Processing Facility
PPF	plasma pyrolysis furnace
PRD	program requirements document
PREPP	Process Experimental Pilot Plant
PVC	polyvinyl chloride
R&D	research and development
RAM	reliability, availability, and maintainability
RCRA	Resource Conservation and Recovery Act
RI	Rockwell International
RI/FS	Remedial Investigation and Feasibility Study
RO	reverse osmosis
ROD	Record of Decision
ROM	rough order of magnitude
ROV	remotely operated vehicles
RTR	real-time radiography

RWMC	Radioactive Waste Management Complex
SAIC	Science Applications International Corporation
scfm	standard ft ³ /min
SDA	Subsurface Disposal Area
SDS	System Design Study
SDWA	Safe Drinking Water Act
SEG	Scientific Ecology Group
SGS	gamma spectroscopy
SWEPP	Stored Waste Examination Pilot Plant
TCLP	toxicity characteristic leaching procedure
TEC	total estimated cost
T/O	tradeoff
TRAMPAC	transportation package
TRU	transuranic
TSA	Transuranic Storage Area
TSCA	Toxic Substances Control Act
TVR-III	Transportable Volume Reduction and Solidification System
UCRL	University of California Research Laboratories
U/R	utilization of resources
VOC	volatile organic compound
WAC	waste acceptance criteria
WAG	Waste Area Group
WERF	Waste Experimental Reduction Facility
WIPP	Waste Isolation Pilot Plant

VOLUME V LAND DISPOSAL COMPLIANCE AND HYDROGEN GENERATION RESTRICTED CONCEPTS

1. INTRODUCTION

1.1 BACKGROUND

Remediating the Idaho National Engineering Laboratory (INEL) transuranic (TRU) buried waste at the Subsurface Disposal Area (SDA) will require a complex set of technologies for safe treatment and disposal of the waste. A key question for achieving the Buried Waste Program objectives is which practical and cost effective technologies could be used as candidates to satisfy the objectives of this program. To provide an answer to this question, a system design study (SDS) was commissioned based on system engineering principles advocated by the U.S. Department of Energy (DOE) Order 4700.1. The SDS examined the existing and emerging technologies for cost-effective remediation of the buried waste. Since no one technology can accommodate the complex remedial action process, several technologies were considered as a system. While examining the technology options, the SDS focused on the technology requirements aspect of the systems engineering. The intent was to identify a set of cost-effective, practical, acceptable treatment strategies; develop system concepts encompassing these strategies; and identify technologies within these concepts that will require demonstration, testing, and evaluation (DT&E).

In addition to developing technology requirements, the SDS concepts were developed so they can be used in future studies for establishing other detailed (derived) system requirements such as input/output (I/O) requirements and utilization of resource (U/R) requirements.

1.2 ORGANIZATION OF THE SYSTEM DESIGN STUDY REPORT

The SDS results are published in eight volumes. Volume I contains an executive summary. The SDS summary and analysis of the results are presented in Volume II. Volumes III through VII contain a detailed description and assessment of twelve system and four subsystem concepts. Volume VIII also includes appendixes.

1.3 CONTENT AND ORGANIZATION OF THIS VOLUME

This volume contains an introduction section containing a brief SDS background and lists the general assumptions and considerations used during the development of the system concepts. The introduction section is followed by sections describing five system concepts that produce a waste form in compliance with the EPA land disposal requirements (LDRs) and have a reduced hydrogen generation capability. This system concept category is referred to as Waste Form 3, "Land Disposal Restriction Required/Hydrogen Generation Restrictive." The following five system concepts are under this category:

- Thermal Treatment/Solidification System with Low-Level Waste (LLW) Presort (3-IT-1)
- Thermal Treatment Solidification System with LLW Postsort (3-IT-3)
- Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6)
- Molten Salt Oxidation Packaging System (3-BE-7)
- Chemical Oxidation/Solidification System with LLW Postsort (3-IT-8).

Each concept is developed through functional allocation and analysis up to a point that major unit operations are identified. For each concept, first a system description is presented. The system description section describes

the overall system and its functional and operational requirements, boundaries, process functional diagram, facility, and design and interface requirements. This section is followed by a system assessment section consisting of the current status of unit operations, system implementation risks, unit operations pro and con analyses, unit operations lead time estimates, and rough order of magnitude (ROM) cost estimates. Also included is a summary of the system evaluation results.

1.4 SYSTEM CONCEPT LIMITATIONS

The system concepts developed for the SDS are of a preliminary nature. System assessments are qualitative and are based on the judgment of the SDS team members assigned to develop the given system model. It is believed that the current level of detail is adequate to provide input to develop the Buried Waste Program technology requirements and provide a vision for the DT&E planning process. More detailed development of these models will be needed to support the concept exploration, evaluation, and recommendation phase of the Buried Waste Program.

1.5 GENERAL CONSIDERATIONS AND ASSUMPTIONS USED IN SYSTEM CONCEPTS DEVELOPMENT

1.5.1 Waste Property Assumptions

The waste input considered in this study are described in a document titled *A Brief Analysis and Description of Transuranic Wastes in the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL* (see Volume VIII, Appendix A) (Arrenholz and Knight, 1991). The following are additional assumptions concerning the input waste criteria:

- The total volume of waste is 2,325,000 ft³; the total volume of contaminated soil is 9,734,000 ft³. The average density of the waste is 37.23 lb/ft³. The average density of the soil is 116 lb/ft³.

- Forty percent of the actual waste is low-level waste (LLW) (i.e., less than 100 nCi/g).
- Ninety percent of the soil is LLW or clean. Soils contain both organic and inorganic hazardous components.
- All lead wastes are or can be made into LLW. Assume that lead is one percent of the waste by weight.
- Waste containing materials that can jeopardize the safety of retrieval and processing operations either exist in small quantities and can be safely handled, or can be segregated out for handling and processing as special material (see below). Examples of waste material in this category are high radiation objects, containers having free liquids, and compressed gas cylinders.
- The removal and treatment of the rock sub-layer are not included in this system analysis.
- Terms used to characterize certain waste types are as follows:
 - Special material--includes waste that is not suitable for normal processing (i.e., processing capability of the system concept described in this report) including large objects, high radiation materials, large construction material, and any object requiring special handling and processing not included in the system design. Processing and handling features for special material are not included in the system models. Special material handling, processing, and disposal methods will be decided on a case by case basis.
 - Large objects--include discarded vehicles, reactor shielding, tanks, etc.

- Large construction material--includes discarded construction material such as concrete slabs, steel beams, sections of brick walls, timber, etc.
- High radiation objects--include reactor vessels, piping, pumps, fuel components, etc.

1.5.2 General Assumptions

The following general assumptions used in developing a system concept:

- Plutonium recovery is strictly for TRU reduction, not recycling.
- All TRU waste metals will be decontaminated for volume reduction.
- The bulk of the soil will be excavated without waste being entrained. A small amount of soil is contaminated by the waste.
- The retrieval will be done inside a building that is classified as a low hazard facility per University of California Research Laboratories (UCRL) 15910.
- The processing buildings for LLW and TRU are classified as a Solid Radioactive Waste Facility per DOE Order 6430.1A and a moderate hazard facility per UCRL 15910.
- The operational time span for the processing of the plutonium-contaminated waste is 10 years.
- Operational assumptions:
 - 24 h/d
 - 5 d/wk
 - 70% plant availability during operation
 - Operational 240 d/yr.

1.6 CRITERIA AND ASSUMPTIONS FOR PROGRAM IMPLEMENTATION RISK ASSESSMENT

For each of the system concepts, the programmatic risks associated with implementing the model are assessed. This assessment has attempted to identify the major uncertainties requiring focused work and attention, and has provided an estimate of the confidence level so that the program can meet the objectives stated in Volume II. The assessment is performed according to the guidelines given in DOE Order 4700.1 for risk assessment during the initial project planning phase. Program implementation risk assessments in this report are qualitative and are based on the judgement of the study team members. Because the buried waste remedial action program is still early in the initial phase of the acquisition process, detailed information for a full analysis does not yet exist. Hence, the qualitative judgments are based on several assumptions, which are presented below.

Each of the unit operations was considered during an initial risk assessment of the system concepts. Then, a composite risk level for the overall system concept was assigned based on the risk associated with the unit operations. In most cases, only the overall system risks are presented in this report. In general, a low ranking implies that the system could be implemented now with virtually no risk. Assignment of moderate rank means that although the implementation of the system concept is feasible, certain aspects of implementation still need to be resolved. If a system concept has a considerable amount of uncertainty regarding achievement of the given objective, then a high risk ranking is assigned.

1.6.1 Project Mission Need and Objectives

The project mission need and objectives are given in Volume II. A summary of the objectives is presented below:

- Performance objectives: Baseline cleanup standards for buried waste sites at the Radioactive Waste Management Complex (RWMC) cannot be established until a Record of Decision (ROD) pursuant to

the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) process is reached for the Remedial Action. These standards will be derived through (a) the Applicable or Relevant and Appropriate Requirement (ARAR) process under CERCLA, (b) standards set by risk assessments, and (c) the State and local requirements.

- Health and safety: Key health and safety objectives are to (a) identify the hazards of the remedial action operation, and (b) provide measures to eliminate, control, or mitigate identified hazards.
- Institutional objectives: Key institutional objectives are to involve the state agencies and the public in the process of selecting a remedial action for the buried waste and ensure compliance with the National Environmental Policy Act of 1969 (NEPA) and CERCLA public participation requirements.
- Schedule objectives: The objective schedule is to reach approval for Title II start by fiscal year FY 1999. This is based on the assumptions that an ROD under CERCLA will be reached by the end of FY 2001. The schedule objective is to complete the Buried Waste Program by FY 2019.
- Cost objective: At this time, the cost objective for the Buried Waste Program is cost-effectiveness. A baseline budget including cleanup costs has not yet been established.

1.6.2 Technical and Performance Risk Considerations

The following considerations were used in characterizing the technical performance risks:

- Contamination type and size: The TRU waste buried at RWMC has been characterized for this study (see Volume VIII, Appendix A).

Based on these waste characteristics, the risks are characterized relative to the ability to comply with the performance objectives. However, it should be noted that detailed and accurate information on the materials buried at each of the trenches and pits or the extent of the site contaminants does not exist at this time. If found in large quantities, pyrophoric materials and compressed gas cylinders containing volatile and toxic gases may have an impact on the performance compliance risk characterization given in this report.

- Major ARARs for in situ treatment options: Major ARARs are Resource Conservation and Recovery Act (RCRA), DOE, and U.S. Nuclear Regulatory Commission (NRC) regulations and guidelines for disposal of waste in shallow land burial sites [10 Code of Federal Regulation (CFR) 61].
- Major ARARs for thermal processes are the Clean Air Act, and RCRA and DOE regulations for radiation protection.

1.6.3 Health and Safety Risk Considerations

The following considerations were used to characterize the health and safety risks:

- General construction-related concerns: As with any construction-related activity, there will be general health and safety concerns associated with the buried waste cleanup operations. Risk associated with the ability of the program to define and mitigate general construction related to health and safety concerns is believed to be low.
- Radioactive and hazardous material handling concerns: Because of radioactive (including TRU), hazardous, mixed waste contamination of the material that will be encountered during operations, the program will be subject to health and safety concerns with respect

to low-level radiation, TRU contamination, and hazardous material exposures. The risk associated with the ability of the program to define and mitigate these health and safety concerns is believed to be moderate for all systems options involving retrieval and processing, and low for all options involving in situ treatment.

- **Criticality:** Because of the measurable quantity of plutonium in the buried waste, the program will be subject to health and safety concerns with respect to criticality. The risk associated with the ability of the program to define and mitigate these health and safety concerns is largely dependent on the availability of techniques to detect Pu contamination in the waste before it is handled. In this study, it is assumed that such techniques are available. Because of the consequences of a criticality occurrence, however, the subject should be examined in more depth during the site characterization effort. For this study, the risk to identify and mitigate criticality concerns is considered to be low.
- **Pyrophoric and volatile and toxic gas:** Since the SDS waste characteristics document (see Volume VIII, Appendix A) does not identify pyrophoric material or compressed gas cylinders containing volatile and toxic gases, the ability of the program to define and mitigate health and safety concerns related to these wastes are not addressed at this time.

1.6.4 Institutional Risk Considerations

The following considerations were used in characterizing the risks:

- **Disposing residues after retrieval:** Options involving ex situ treatments (i.e., excavation, removal, and disposal) will involve disposal of TRU-contaminated mixed waste. Currently, DOE has no disposal space for these wastes. Therefore, the question of institutional risk of ex situ techniques will require addressing

ultimate disposal of the residues. However, since the system boundary for the SDS does not include the ultimate disposal of the residues, characterization of the institutional risk did not address the disposal question.

- State and public acceptance of leave-in-place options: System leave-in-place options are characterized as a high risk with regard to institutional acceptance. This is due to anticipated opposition by the state and the public. Over the last several years, the State of Idaho and the Federal Government have communicated several times concerning the retrieval and removal of TRU waste buried at the INEL. DOE and its predecessors, the U.S. Atomic Energy Commission (AEC) and the Energy Research and Development Administration (ERDA), have made commitments to the State of Idaho to remove the TRU waste.
- Thermal process public acceptability: Because of past experience in public opposition at other DOE sites (e.g., Rocky Flats), system options involving the incineration process are characterized as a high risk with regard to public acceptance.

1.6.5 Schedule Risk Considerations

The following considerations were used to characterize the risks:

- Time available for DT&E: As indicated above, the schedule objective is to reach Title II design by FY 1999. To achieve this objective, it is assumed that detailed information to evaluate the remedial action options is needed by 1996. Therefore, any system concept requiring DT&E lead-time longer than five years is believed to be a high risk.
- Thermal system burn test requirements: Because of past experience in lengthy burn tests and the U. S. Environmental Protection Agency (EPA) approval process at other DOE sites (e.g., Rocky

Flats and Oak Ridge National Laboratories), system options involving incineration processes are characterized as a moderate risk in regard to compliance with the schedule objectives.

1.6.6 Cost Risk Considerations

Since a baseline cost estimate has not been established at this time, the assessment of cost risk is based on how well the program will be able to define the cost of the given system in the future if the system is selected as the preferred option. As indicated in Section 1.6.2, pyrophorics and compressed gas cylinders containing volatile and toxic gases can have a significant impact on the technical performance risk characterization if found. This will also impact cost risk characterization.

1.7 COST ESTIMATING ASSUMPTIONS

1.7.1 Cost Estimating Guidelines

Cost estimating guidelines were developed to support development of an ROM cost for each system concept. The guidelines included building/space cost per square foot, and design, inspection, and project administration percentages for the various types of building/space. Also included are operating costs to be considered for development of life cycle costs. All costs are presented in FY 1991 dollars, including operating and maintenance costs.

1.7.1.1 Building Space Costs. The building unit rate costs listed below are based on similar facilities at the INEL. The costs are representative of the building and its support systems, including utilities and site development costs. The Alpha Cell Space building costs include the high-efficiency particulate air (HEPA) filter systems. Special equipment and any additional mechanical or electrical systems needed for the operation of the equipment has not been included in these costs. The unit rates include direct and indirect construction costs. Indirect costs associated with the

additional building costs and equipment costs are established to be 20.5 percent of the direct costs.

- High hazard building space \$ 650/ft²
- Moderate hazard building space \$ 350/ft²
- Alpha cell space with one confinement barrier \$1000/ft²
- Alpha cell space with two confinement barriers \$1200/ft²
- Retrieval building space \$ 100/ft²

1.7.1.2 Design Inspection and Project Administration Costs. To determine the design, inspection, and project administration costs for each option, the percentages listed below were applied. These percentages are historical averages for types of activities covered by SDS concepts.

- Contingency on all costs 25%
- Design costs applied to construction costs (both demonstration and production) 30%
- Inspection costs applied to construction costs (both demonstration and production) 7%
- Project administration applied to construction costs (both demonstration and production) 10%
- Indirect costs applied to total construction costs (both demonstration and production) 20.9%
- Construction management (CM) and CM reserve (combined percent) applied only to production construction cost 28.7%

1.7.1.3 Operating Costs. The utility rates and operating rates listed below were established by EG&G Idaho, Inc. (EG&G Idaho) for use in the development of life cycle costs. Present day costs were used for the preparation of these estimates. A contingency factor of 25% was applied to the project subtotal.

- Electricity \$0.035/kWh
- Propane \$0.60/gal
- Operating staff \$60/h

1.7.2 System Model Cost Estimate Normalization and Modification

ROM cost estimates were prepared by the team members for the 12 systems and 4 subsystems based on the above guidelines. These initial cost estimates were examined by an independent estimating team to determine if the estimates were comparable in estimating approach and techniques. If not, the estimate approach and techniques were modified so that the estimates could be compared to one another. The independent estimating team corrected the initial estimate inconsistencies concerning the application of multipliers, estimating approach, summary sheets, backup sheets, years of operation, and cost per square foot. The following steps were used to modify the estimates:

- Normalized costs: The initial ROM estimates for the 12 systems and 4 subsystems were first "normalized" by a consistent application of the multipliers for indirect, design, inspection, project administration, construction management, and contingency. These revised ROM cost estimates were referred to as normalized ROM costs.
- Modified costs: A second review of the 12 system and 4 subsystem model ROM cost estimates was conducted for comparable square footage in allocating the building space, consistent cost per square foot, consistent time basis used in operating and maintenance costs, omissions and errors, and comparable equipment costs with other similar equipment used within the 16 estimates. The ROM cost estimates of the 12 system models were revised to correct any of the above inconsistencies. These estimates were called modified costs. The following modifications were made:

- Because of inconsistent use of criteria, the system models facility sizes were corrected to remove front end receiving, unloading and storage areas, and back end drum storage areas. Space requirements for these functions were assumed to be 200,000 ft² for all ex situ system models. The ROM cost for this space was estimated to be approximately \$30 million.
- An average square footage for similar operations was developed and used in cases where assignment of alpha cell square footage varied widely for similar operations.

1.8 DEMONSTRATION, TESTING, AND EVALUATION ASSESSMENT ASSUMPTIONS

Major unit operations in each of the system and subsystem models were evaluated to estimate DT&E needs, lead-time, and resource requirements. Some of the criteria and assumptions used as the basis for these estimates follow:

- Project execution: It is assumed that the Buried Waste Program will be executed according to the project management system advocated by DOE Order 4700.1. Figure IV-1-1 shows the various categories of work and the various phases of the research and development in a typical project executed under the DOE Order 4700.1 requirements.
- Research and development (R&D) categories of technologies: It is intended that the 12 system and 4 subsystem options considered in the SDS do not use technologies that fall in the categories of "basic research," "applied research," or "technology or exploration development" as defined in DOE Order 4700.1 (page I-5). Only technologies that have passed the "technology or exploration development" stage are assessed. Under the EG&G Idaho Research Development DT&E Program definitions, technologies considered are assumed to

- Have completed R&D activities to apply knowledge from research toward proof of technology including development of non-specific application prototypes and processes
- Require only DT&E activities to
 - Compare the effectiveness of alternative processes
 - Determine the applicability of a particular technology to a site-specific use
 - Establish a level of confidence in a treatment process
 - Yield such information as process results, design criteria, and operational sensitivities
 - Obtain regulatory agency concurrence or approvals, as needed. The EG&G Idaho DT&E activities are considered to be comparable to the "advanced development" activities defined in DOE Order 4700.1.
- DT&E output assumptions: When a DT&E program is proposed for a given unit operation, the intent is to develop the unit operation to a point where the results will support DOE key decision 2 for the Buried Waste Program. As defined in DOE Order 4700.1, key decision 2 is approval of the start of Title II or final/detailed design activities. In addition, it is intended that the program output will be in accordance with the *EPA Guide for Conducting Treatability Studies Under CERCLA* (EPA, 1989).
- DT&E steps: In order to allow a consistent assessment of DT&E needs, the activities are divided into the following logical steps (Figure IV-1-2). These steps are consistent with the *EPA Guide for Conducting Treatability Studies Under CERCLA* (EPA, 1989).

Figure V-1-1. Categories of work effort and research and development or acquisition phases.

Figure V-1-2. Breakdown of demonstration, testing, and evaluation activities during advanced development.

- Primary paper evaluation: The objective of the primary paper evaluation is to study the various options using existing information. This evaluation will result in defining scope and conceptual design for the next steps of the DT&E phase. It will eliminate those options that are not likely to be cost effective from further consideration.
- Bench-scale studies: Bench-scale studies are the next logical step, but in some cases it is assumed that the DT&E efforts can move directly from initial paper evaluation to the pilot-plant/prototype test studies. For example, evaluating a robotics operation in waste segregation would not be conducive to bench-scale studies. If required, these studies will address scaling issues.
- Secondary paper evaluation: When further pilot-scale studies are shown to be necessary, a secondary paper including more detailed concept development may be needed. This will help eliminate options that are not cost effective and focus the pilot or prototype test study on essential issues, normally using a single technology option.
- Pilot-plant/prototype test studies: The objective of pilot-plant/prototype test studies is to provide reliable information for developing design criteria including scale-up limitations and cost estimates for processes and ancillary equipment. Full-scale prototype tests are assumed for non-process equipment such as robotics development. Generally, pilot-plant/prototype studies are assumed to cover only the critical portions of the equipment requiring advanced development.
- Number of technology options studied in a typical DT&E program: It is assumed that primary paper evaluation, bench scale studies, and secondary paper evaluation steps will result in narrowing the

alternatives to a single option. Pilot-plant/prototype studies are assumed to be applied only to the selected option and are proposed only if it is deemed necessary.

- DT&E lead-times: In order to provide a consistent estimate of the DT&E lead-times, a set of timespans is assumed for the DT&E steps. Based on the complexity of the technologies being considered, the timespan is narrowed down to a specific duration in the assessment sections of the system models. The timespans include allowances for a one-month procurement process and one-month report preparation for bench scale and paper studies. For pilot-plant/mock-up studies, a 2-month procurement process, 2-12-month design, 4-12-month fabrication, and 6-24-month test and report preparation are assumed. Based on the above, the assumed timespans are

-	Primary paper evaluation	5-6 months
-	Bench-scale studies	5-18 months
-	Secondary paper evaluation	5-6 months
-	Pilot-plant/mock-up test studies	14-60 months.

2. THERMAL TREATMENT/SOLIDIFICATION SYSTEM WITH LOW-LEVEL WASTE PRESORT (3-IT-1)

This functional and operational requirement (F&OR) section is prepared as a component of the EG&G Idaho System Design Study task. The purpose of the task is to provide a basis for the development of technologies required to remediate the buried waste in Waste Area Group-7 (WAG-7) of RWMC. The buried waste includes constituents that make it mixed waste. As a result, the RWMC will be remediated under the terms of RCRA and CERCLA.

2.1 FUNCTIONAL AND OPERATIONAL REQUIREMENTS

2.1.1 System Description

The processing system studied in this task is schematically presented in Figure V-2-1. The individual components of the system are described below.

2.1.1.1 Assay. All packages will be passed through an assay system to determine if the packages are LLW or TRU. The system would be patterned after the Stored Waste Examination Pilot Plant (SWEPP) and would allow identification of fissionable material inventory as well as beta/gamma scanning.

2.1.1.2 Open Packages/Sort. TRU waste will be processed through three unit operations. At this point, all packages will be opened remotely in appropriate containment. Each package will be examined visually and by x-ray, and will be directed to either the sludge process, incineration process, or the Metals Decontamination Subsystem (5-BE-1).

2.1.1.3 Dump Drums and Sort (Sludges). It is expected that all sludges will be in drums (if the drums are still intact). The sludge sorting will be accomplished by a combination of remote detectors and visual means. Visually, it will be determined if the sludges were cemented. A "sniffer" will be used to locate organic sludges, and the rest will be assumed to be inorganic. The

DESCRIPTION:

THE SYSTEM IS A THERMAL TREATMENT/SOLIDIFICATION SYSTEM TO MEET LDR REQUIREMENTS. LLW IS PRESORTED. KEY OPERATIONS INCLUDE THERMAL TREATMENT, SIZING AND SOLIDIFICATION. SPECIAL LDR WASTES ARE TREATED IN A SPECIALIZED PROCESS.

Figure V-2-1. Process functional diagram for the Thermal Treatment/Solidification System with LLW Presort (3-IT-1).

Note: Mass flow balance does not show the input process additives.

DRAWING NUMBER 3-IT-1

UNIT OPERATION

DESIGN
CAPACITY
(lbs/hr)

PROPANE
(gal/hr)

ELECTRICITY
(kW)

Assay
Open Packages and Sort
Dump Drums and Sort
Shredder
Thermal Treatment
Off-Gas Treatment
Organics Treatment
Grinder
Concentration Dryer
Melter
Solidification
Package
Assay and Sort

2680
3000
125
125
1300
150
150
150
150
150
150
2170
2170

0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00

1
4
4
150
4.7
1
2
1
5
15
175
4
1

E 13/11/91		DESIGNED FOR REVIEW		J.P.	J.H.	J.V.
NO.	DATE	REVISION	BY	CHK'D.	ENGR.	APPR.
1	1/18/91	1	J.M.	J.M.	J.M.	J.M.
PROJECT		TITLE		DRAWN BY		
3-IT-1		WASTE MANAGEMENT FACILITY		JOHN V. DILL
INTERNATIONAL TECHNOLOGY CORPORATION ALEXANDRIA, NEW MEXICO						
E.C. & G. IDAHO, INCORPORATED SYSTEM DESIGN STUDY IDAHO FALLS, IDAHO						
PROCESS FLOW DIAGRAMS FOR SYSTEM DESIGN STUDY						
JOB NUMBER		DRAWING NUMBER		REVISION		
3-IT-1		3-IT-1		1		

drum contents will be dumped into appropriate hoppers for further treatment, and the drums will be sent to the Metals Processing Subsystem (5-BE- 1).

2.1.1.4 Grinder. Some inorganic sludges have been cemented in layers, much like a parfait. Because it is unlikely that this treatment will meet toxicity characterization leaching procedure (TCLP) criteria, the cement will be ground in a simple crusher so these sludges can be processed in the same fashion as uncemented sludges.

2.1.1.5 Organics Treatment. Organic sludges must be thermally treated to meet the land disposed restriction (LDR). Thermal treatment by any of a number of direct or indirect heating methods would be acceptable. The off-gases from the desorber will contain the organic constituent and will be further treated in a secondary combustion chamber associated with the combustibles incinerator.

2.1.1.6 Solidification (Sludge). Based on test results, a solidification agent will be selected to immobilize the sludges and meet LDRs. Sludges from other processes will also be treated in this unit. Cement, sulfur cement, polymers, and bitumen are all candidate solidification agents.

2.1.1.7 Shredder. Combustibles and inerts are expected to require some size reduction before feeding the incinerator. A shredder system consisting of remote package handling, oversize item retrieval, and sticky material handling equipment is required to ensure proper incinerator operation. Reusable waste packages will be dumped and cleaned at this point.

2.1.1.8 Thermal Treatment. An incinerator capable of processing large volumes of noncombustibles and large items will be required. In addition, a very high carbon burnout will be necessary to make the resultant product compatible with the subsequent solidification agents. Several candidate incinerator types are listed. The incinerator secondary combustion chamber will also accept off-gas from the thermal desorber.

2.1.1.9 Off-gas Treatment. An off-gas cleanup process will be required to meet RCRA and Clean Air Act effluent requirements. Acid gas removal and particulate removal must be accomplished in this process.

2.1.1.10 Solidification (Ash). A solidification process, with a formulation compatible with incinerator ash, could use any of the agents described with the sludge solidification.

2.1.1.11 Concentrator and Dryer. The thermal off-gas treatment equipment will produce a liquid waste consisting of an aqueous salt solution. This TRU waste will be dried before solidification. Two-step and one-step processes are available for this operation.

2.1.1.12 Solidification (Salt). Solidification of the salts from the dryer will also be accomplished in specialized equipment. Because of the solubility of the dryer product, unique formulations will be required for this waste.

2.1.1.13 Packaging. All waste forms will be packaged into drums or boxes compatible with the disposal site requirements.

2.1.1.14 Assay and Sort. All packages will be assayed to determine TRU content and any other analytical and physical factors dictated by the regulations or waste acceptance requirements. These final measurements will complete certification for packages destined for the Waste Isolation Pilot Plant (WIPP) or equivalent disposal location.

2.1.1.15 System Specific Design Assumptions. The waste composition is derived from *A Brief Analysis and Description of Transuranic Wastes in the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL* (Arrenholz and Knight, 1991). The specific system design assumptions are listed below:

- The mass of the "special items," oversized items, and materials requiring special treatment is assumed to be negligible

- All sorting operations are assumed to be perfect; (i.e., no allowance is made for combustibles in the metals or vice versa)
- All sludges are assumed to contain either heavy metals or hazardous organics and will require treatment to meet LDR criteria
 - The combustibles ash content is 5%
 - All combustibles and inerts must be treated to meet LDR disposal requirements
 - The solidification process will use a 50% waste formulation to meet LDR requirements.

2.1.2 System Boundaries

The particular system under consideration is a complete TRU waste retrieval and processing system. It assumes the start is the WAG-7 pits and trenches. The processing system, with the exceptions noted below, retrieves the waste, transports it to a processing facility, processes it, and packages it for disposal. The study boundary ends at the assayed and packaged waste. Transportation for disposal and disposal itself are not considered. The following system boundaries indicate nonprocessed and by-product material streams, which exit the process.

2.1.2.1 Input Interface. The WAG-7 portion of RWMC is within the boundary of this study. All retrieval steps are within the study boundary. A second input is the raw material input to the system. No detail beyond acknowledgement of a need for equipment, utilities, and processing raw materials (e.g., solidification agents) is provided.

2.1.2.2 Output Interfaces. Soils, including overburden and interstitial soils, will be sorted from the TRU waste and processed in the Soils Processing Subsystem. The subsystem will produce clean, unpackaged soil

for return to the site: some packaged low-level waste for disposal as LLW, and some TRU sludge.

LLW will be separated from TRU waste before the TRU process and processed in a separate LLW subsystem. The outputs from the LLW processing subsystem include packaged LLW, TRU waste, clean water, and clean off-gas.

There will be certain special items retrieved from the buried waste that have a size or nature incompatible with the TRU processing system. Treatment of these items to meet the LDR is outside the scope of this study.

The treated and packaged TRU waste will be assayed for TRU content. The boundary of this study is the final assayed waste package. Transportation and disposal costs and considerations are not included.

The thermal treatment process will have a gaseous release as off-gas. This gaseous effluent will be processed to meet the appropriate regulations.

Treated water, of a quality acceptable for process use, will be recovered from the various processing steps. This treated (clean) water will be released from the facility.

Metals will be treated in the Metals Decontamination Subsystem (S-BE-1). The subsystem outputs include LLW metals, TRU metals, TRU sludge, and clean water.

The following list of considerations is given as a reminder that the function and requirements inherent in this list will influence the process design:

- Security
- Work control/personnel support
- Contaminated maintenance

- Noncontaminated maintenance
- Heating, ventilating, and air conditioning (HVAC)-nonprocess
- Fire protection
- Safety (equipment, training)
- Health physics
- Sanitary facilities
- Electrical (including emergency)
- Process control/data logging
- Environmental regulatory reporting/records management
- Criticality control/monitoring
- Radiation instrumentation
- Personnel decontamination
 - Radioactive
 - Hazardous
- Bulk chemical supply/storage
- Storm water runoff control
- Wastewater treatment
 - Hazardous/radioactive

- Sanitary
- Communications
 - Interior
 - External (public relations)
- Spill or emergency response team
 - Hazardous
 - Radioactive
- Analytical laboratory
- Environmental field sampling team.

2.1.3 Process Functional Diagram

The process functional diagram (PFD) for the Thermal Treatment/Solidification System with LLW Presort (Figure V-2-1) shows a system in which the buried waste is treated to meet the requirements of RCRA LDRs using the technologies of incineration and solidification. More specifically, TRU sludges are solidified in one of several solidification agents, combustibles and inerts are processed through a thermal treatment system, and the resultant ash is similarly immobilized. Metals are processed in the Metals Decontamination/Sizing Subsystem to convert most of the metal to low-level waste. LLW is separated from TRU so that it can be processed in a subsystem.

2.1.4 Facility Description

The facility layout is shown in Figure V-2-2. This layout is designed for simple movement of material through the facility from waste receipt to packaged waste shipment. Processing lines are parallel in the building with

NOTES

- PROCESS CELLS INCLUDE WASTE PASS-THROUGH AREAS
- INCINERATOR OFF-GAS, CONCENTRATION, DRYER SYSTEMS ARE MULTI-STORY
- PERSONNEL & MATERIAL BASEMENT ACCESS & PASSAGE AS REQUIRED
- PROCESS HAPX FILTRATION AT EACH STATION AS REQ'D
- BUILDING VENTILATION FOR HEPA FILTRATION - MINIMIZE DUST LOSS
- ADMINISTRATION BUILDING LOCATION IS OPTIONAL

Figure V-2-2. Plant layout for the Thermal Treatment/Solidification System with LLW Pres

NO.	DATE	REVISION	BY	CHKD	ENG	APP
1	10/1/57	1	CHM	ENG	APP	
<p>INTERNATIONAL TECHNOLOGY CORPORATION ALBUQUERQUE - NEW MEXICO</p>						
<p>CONFIDENTIAL PROPERTY OF IT CORPORATION THIS DRAWING AND ALL INFORMATION THEREON IS CONFIDENTIAL AND MUST NOT BE MADE PUBLIC OR COPIED UNLESS SO AUTHORIZED. IT SHALL NOT BE USED EXCEPT FOR THE PURPOSE FOR WHICH IT WAS SUBMITTED, AND IT SHALL BE RETURNED ON DEMAND. ALL RIGHTS OF INVENTION OR DESIGN ARE RESERVED.</p>						
<p>EG & S IDAHO, INCORPORATED SYSTEM DESIGN STUDY IDAHO FALLS, IDAHO</p>						
<p>PLANT LAYOUT FOR SYSTEM DESIGN STUDY</p>						
JOE NUMBER	DRAWING NUMBER		REVISION			
331411	3 - 13 - 11		1			

rt (3-IT-1).

shielded pipelines and conveyors passing over the operating areas as necessary. Because of the size of the LLW processing subsystem and the distance from that subsystem to the incineration solidification process, it may be necessary to solidify sludges from the LLW system in a separate facility.

2.1.5 System Design Requirements

2.1.5.1 General Requirements. The waste constituents of the buried waste are described in *A Brief Analysis and Description of Transuranic Wastes in the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL* (Arrenholz and Knight, 1991).

The waste handling and treatment process will be designed in accordance with applicable regulations. Specifically, RCRA places design conditions on the storage and treatment process, and performance specifications on the incinerator and solidification process. All equipment will be high-quality, low-maintenance items to keep personnel exposure as low as reasonably achievable. Remote operations will be used to the greatest extent practicable. The facility design will be compatible with DOE Orders, including the DOE Idaho Architectural Engineering Standard and the DOE General Design Criteria Manual, DOE Order 6430.1A.

The TRU waste will meet the appropriate RCRA disposal criteria, the WIPP waste acceptance criteria, and transportation package (TRAMPAC) requirements.

The treatment objectives for the remediation concept of the process functional diagram including the following:

- Separate LLW so that a dedicated, less complex process may be used.
- Treat TRU sludges by solidifying and immobilizing the radioactive and heavy metal constituents.

- Treat TRU combustibles by thermal treatment to remove and destroy any organic hazardous constituents. The resulting ash will be solidified to immobilize the radioactive and heavy metal constituents.
- Decontaminate metals in the metals decontamination subsystem to reduce the mass of material undergoing treatment in the complex TRU process treatment system.

2.1.5.2 Unit Operation Design Requirements. The functional and performance requirements of each of the process unit operations in Figure V-2-1 are outlined below. The nominal mass flow rates and equipment sizing information is shown in Figure V-2-1.

- Assay: All packages will be assayed and sorted according to TRU or LLW categories. Packages will not be opened.
- Open packages/sort: The objective of this process is to remotely separate the waste packages into three categories: sludge, combustibles, and ferrous metals. The unit operations must provide the following:
 - A means to visually (via camera) and nonintrusively (via x-ray) determine package contents
 - The sorting line must be capable of achieving 125% for the maximum design capacity of the four separation categories processing systems (1600 lb/h)
 - The process must provide for fire suppression and an inert atmosphere, if necessary
 - Must be integrated with the regulatory reporting process.

- Dump drums and sort: This subsystem identifies the sludge stream as one of two categories: organic or inorganic. The drums will be remotely dumped into the appropriate conveyor or process line. The unit operation must provide the following:
 - A means to open the drum head, cut the plastic, and visually examine the sludge
 - A simple analytical determination that the presence of organic vapors provides 125% of the maximum design capacity of the organic and inorganic sludge maximum design capacity (525 lb/h)
 - Must provide for inerting atmosphere and fire suppression.
- Grinder: The objective is to grind inorganic sludges that have previously been cmented. This process must have the following capabilities:
 - A maximum design capacity of 330 lb/h
 - The ability to reduce nominal size to 1/4 in.
 - The capability to use two in-series units
 - The capability to accommodate an input size range of 6 x 24 in.
 - The ability to be compatible with the downstream solidification processing equipment
 - The ability to provide for inerting atmosphere and fire suppression

- The ability to be maintainable, such that an overall on-line operating factor of 70% be achieved over a one-year period of time
- Must be capable of having provisions for criticality monitoring and controlling.
- Organics treatment: The objective is to thermally remove organic constituents in the sludge stream. The gaseous emissions would be directed to an afterburner. The process must contain the following:
 - Must have a maximum design capacity of 150 lb/h and accept items as large as 3 in.
 - Must reduce the organic content of the residual solids below 1 ppm for nonvolatile components such as polychlorinated biphenyls (PCBs)
 - May use direct or indirect heating
 - May provide for inert gas or no inlet air operation to reduce the off-gas required for further processing
 - Must be maintainable, such that an overall on-line operating factor of 70% can be achieved over a one-year period
 - Must have provisions for criticality monitoring
 - Materials of construction of the waste contacting surfaces must be compatible with chlorinated organic wastes and alkali metals
 - Must include provisions for cooling the output material

- Must provide a fully integrated process/data acquisition/regulatory reporting process.
- Solidification (sludges): The objective is to solidify the treated organic and cemented sludges and the untreated inorganic sludges to immobilize the radioactive and heavy metal constituents. The process must provide for the following:
 - Accommodate variable solidification formulations to meet the TCLP test criteria
 - Must have a capacity design maximum throughput of 125% of the sludge processing subsystems (600 lb/h)
 - Must accommodate radiation monitoring instrumentation
 - Must be integrated with the regulatory reporting system
 - Must include system clean-out provisions.
- Shredder: The objective is to shred combustible materials to a size suitable for the incinerator feed. The following requirements are necessary:
 - Must have a maximum capacity of 725 lb/h
 - Must reduce to a nominal size of 3 in.
 - May use two in-series units
 - Must accommodate an input size up to a 7-ft dimension
 - Output must be compatible with the incinerator feed input
 - Must provide for inerting atmosphere and fire suppression

- Must be maintainable, such that an overall on-line operating factor of 70% is achieved over a one-year period
 - Must provide for criticality monitoring and controlling
 - Must have remote package handling capability
 - Must provide for reusable package dumping and return
 - Must provide for oversize item retrieval
 - Must have provisions for handling sticky materials.
- Thermal treatment: The objective is to oxidize organic constituents in the combustibles stream. The following conditions are required:
 - Must have a maximum design capacity of 725 lb/h
 - May use an auxiliary fuel
 - Must provide for high carbon burnout; therefore, a minimum solids retention time of 90 min is required
 - Must be maintainable so that an overall on-line operating factor of 70% can be achieved over a one-year period of time
 - Must have provisions for criticality monitoring
 - Must operate at a temperature/residence time condition that reduces residual organic solvent content of the ash to less than 1 ppm
 - Secondary combustion chamber must have provisions for accepting off-gas from the thermal desorption system

- Secondary combustion chamber design must allow a 2-second residence time at 2000°F for PCB destruction
 - Construction materials of the waste contacting surfaces must be compatible with chlorinated wastes and alkali metal salts
 - Feed process must have provisions for inerting atmosphere and fire suppression
 - Ash handling process must be compatible with the downstream ash solidification system
 - Must provide a fully integrated process/data acquisition/regulatory reporting process
 - Feed system has provisions for fugitive emissions
 - System must be integrated with the gaseous emission monitoring system
 - Provide provisions for ash cooling.
- Off-gas treatment: The objective is to clean the gaseous emissions from the thermal process to comply with applicable regulatory requirements. The process must have the following:
 - Process must be capable of removing 99% of the HCl from the gas stream
 - May use any combination of wet/dry process that achieves the treatment standards
 - Must reduce particulate concentrations to less than 0.08 g/dry standard cubic feet (dscf)

- Must have redundant power supplies to ensure continuous operation.
- Solidification (ash): The objective is to solidify the resulting noncombustibles to immobilize the radioactive and heavy metal constituents. The system must provide for the following:
 - Must accommodate different solidification agent formulations to allow compliance with the appropriate leach tests
 - Must have a capacity design maximum throughput of 125% of the thermal processing ash discharge maximum capacity (425 lb/h)
 - Must accommodate radioactive monitoring instrumentation
 - Must be integrated with the regulatory reporting process
 - Must accept both fine particulate ash and noncombustible items.
- Concentration dryer: The objective is to process the off-gas treatment system blowdown salt solutions by concentration and dry them for input to the solidification process. The following conditions are requirements:
 - Must accept spent solutions at a rate of 70 lb/h with salt concentrations ranging from 3 to 20%, as well as insoluble particulate
 - Must produce a product compatible with the downstream solidification process
 - Must generate recovered water of a quality to allow release.

- Solidification (salts): The objective is to solidify the resulting noncombustibles to immobilize the radioactive and heavy metal constituents. The system must provide for the following:
 - Accommodate different solidification agent formulations to allow compliance with the appropriate leach tests
 - Must have a capacity design maximum throughput of 125% of the concentrator/dryer discharge maximum capacity (5 lb/h)
 - Must accommodate radioactive monitoring instrumentation
 - Must be integrated with the regulatory reporting system
 - Must accept soluble salt products from the dryer.
- Packaging: The objective is to package the fully treated waste forms for transportation and disposal. The system must perform the following:
 - Accept the solidified material from the various solidification process
 - Ensure a dense package filling
 - Allow package exterior cleaning and decontamination for handling.
- Assay and Sort: The objective is to determine the TRU content of the waste packages. This will also include other regulatory requirements for transportation and disposal. The process requires identification of TRU content and fissionable material content.

2.2 SYSTEM ASSESSMENT

2.2.1 Current Status of Unit Operations

The Thermal Treatment/Solidification System with LLW Presort (3-IT-1) is described in Section 2.1.1.

2.2.1.1 Low-Level Waste Treatment Subsystem. See the description of unit operations for this subsystem (Volume VII).

2.2.1.2 Assay. Assay systems, which were developed and demonstrated at Los Alamos National Laboratory (LANL), are currently operational. The technology consists of a combined passive and active neutron approach and is proven for assaying drums of TRU waste and to a lesser extent, boxes of waste. This assay technique has been used since 1987 and is currently in full-scale operation. Two major DOE sites that routinely use the technique are the INEL and the Rocky Flats Plant. The INEL SWEPP facility uses the assay system to determine whether waste is LLW or TRU by determining the fissile content of drums. It is also used to certify waste to the WIPP waste acceptance criteria. At the Rocky Flats Plant, both drums and boxes are assayed for fissile content. The low radiation levels emitted from contact-handled TRU waste are not expected to have any substantial effect on assay readings.

2.2.1.3 Open Packages/Sort. Commercial systems that open packages and sort waste are not currently available. The Scientific Ecology Group (SEG) at Oak Ridge, Tennessee developed a revolving sorting table and a shaker table for hand sorting feed for a 725 kg/h LLW incinerator. The Solid Waste Certification Facility at LANL will be used for packaging, sorting, and certifying WIPP-bound TRU waste. This facility consists of nine interconnected glove boxes for various operations. The SEG sorting system is an operating, full-scale facility; the LANL facility will be operational in 1991. Waste characteristics such as size, weight, and physical form are all important to the design of a sorting system. The SEG LLW sorting system is used for combustible waste and does not handle large objects. The LANL system

sorts dry waste and can accept some solid objects. It should be noted that real-time radiography (RTR) is being routinely used as a waste characterization tool and could be applied to sorting waste packages. DOE sites, such as the INEL and the Rocky Flats Plant, routinely use this technique on a full-scale basis for analyzing the contents of TRU waste drums. The system has not yet been demonstrated for waste boxes.

Remote operations using through-the-wall and crane mounted manipulators are commonly used in the nuclear industry. Remote tooling to handle and open waste containers requires engineering to apply these tools to the specific task. Because waste needs to be characterized before thermal treatment or solidification, remote operations can be designed to handle containers, open containers, remove waste from containers (and from waste bags where process knowledge is inadequate), and repackage or prepare waste for treatment. With the possible exception of certain chemical analyses (i.e., organic sludges), these are engineering challenges rather than R&D requirements.

2.2.1.4 Dump Drums and Sort. Manual opening and visual examination of TRU wastes has been accomplished in the Rocky Flats Plant Size Reduction Vault. Since 1984, approximately 240 drums have been opened using this "hands-on" operation. Argonne National Laboratory-West (ANL-W) will have an operational glove box available for this purpose in 1990. Before visual examination of the TRU waste at the Rocky Flats Plant, the waste drums are examined by real time radiography (RTR) at the INEL. However, RTR cannot determine whether sludges are organic or inorganic. To make this determination, a gas sampling manifold similar to that used at the Rocky Flats Plant to examine TRU wastes can be used to fill sample canisters and analyze drum head space gases.

For full-scale, remote operations, as-low-as-reasonably-achievable (ALARA) needs to be considered and designed into a remote or semi-remote unit operation. Application of remote handling technology, glove box technology, or a combination of the two, would require applications engineering. Research and development should not be required.

2.2.1.5 Grinder for Cemented Inorganic Sludges. Grinders and crushers of many varieties are available and have been used commercially for many years. Various industries, including mineral ore sizing and particulate sizing, have used such equipment for all types of minerals. Available crusher-type equipment includes jaws, gyratories, cones, pans, rolls, rotaries, and hammer types. Grinders such as balls, ring rollers, hammers, disks, and fluid energy mills are readily available. Selection is a function of feed size, hardness, and reduction ratio desired. Capacities are commercially available for full-scale radioactive waste operations on cemented sludges. Most can be operated closed circuit; therefore modification for radioactive or alpha confinement is expected to require only engineering and demonstration.

2.2.1.6 Organics Treatment for Sludges. Microwave and indirect heating devices are commercially available and operational. Microwave heating of sludges is being evaluated at the Rocky Flats Plant and at Oak Ridge National Laboratory (ORNL). Although this technology is being evaluated for solidification, it could be applied to desorption of organics from sludges. Decontamination has been reported of various soils that contained PCBs, furans, and dioxin, and this process could be applied to sludges. The demonstration was performed in an externally-fired calciner pilot plant. Incineration can also be used to eliminate organics from sludges.

2.2.1.7 Shredder. Shredders of the counter rotation type are installed at the Savannah River Site and were previously installed in the Process Experimental Pilot Plant (PREPP). The PREPP facility at the INEL tested a shredder for feed preparation before incineration/solidification using simulated TRU wastes. A shredder/compactor also exists at the Tennessee Valley Authority-Watts Bar Nuclear Plant. Other technologies also exist, such as the screw-type auger (KOMAR) shredder, which was tested at PREPP. In general, large shredders have been demonstrated commercially and at municipal waste treatment plants.

Hardened steels and large pieces of material are difficult to shred. Separation of metals from the waste will eliminate this problem. Large pieces

will require some size reduction before shredding. Thin, flat material has also been a challenge at times. It is anticipated that shredder maintenance in TRU waste service may present some difficulties, but removal of metals from the waste should minimize maintenance. These are primarily engineering challenges, and research and development is not required to place shredders into TRU waste service.

2.2.1.8 Thermal Treatment. Incineration is highly developed in the hazardous waste industry. In addition, over 80 radioactive waste incinerators have been operated since 1949. LANL has, since 1976, demonstrated a controlled-air incinerator for reducing TRU waste volume. Currently, the incinerator is shut down, pending approval of NEPA documentation. Other incinerators for LLW have been demonstrated at the Waste Experimental Reduction Facility (WERF) at the INEL, the K-25 facility at ORNL, and the SEG at Oak Ridge. Europe and Japan make extensive use of incineration for reduction of radioactive waste volume. A recent tabulation shows 18 operating radioactive waste incinerators in Japan.

Incinerator design is influenced by both the combustible and noncombustible fractions of the feed, as are off-gas and ash handling systems. In municipal solid waste applications, waste compositions similar to TRU waste have been treated. No radioactive waste incinerator has been tested using the buried TRU waste mixture.

Other technologies that have not been applied to TRU waste are the fluidized bed incinerators, used extensively at commercial facilities, pyrolysis units that are used in other countries but not applied at DOE facilities, and the rotary kiln, which is commonly used in commercial applications and is particularly suited for large bulk, unsorted wastes. Thermal treatment systems do not need significant research and development at this time. However, it is expected that engineering development and scaleup will be needed to apply incineration technology to the subject TRU and LLW wastes. A more detailed description of incineration technology is given in Volume IV.

2.2.1.9 Off-gas Treatment. Almost all the radioactive waste incinerators worldwide have had off-gas treatment systems to control radioactive or other hazardous material releases, including TRU radionuclides. The type of off-gas system is determined by the amount and type of particulates and halogenated plastics in the feed material. Historically, "wet" off-gas systems have been used, but newer applications are using "dry" scrubbing techniques. The latter employ sintered metal filters, HEPA filtration, and cooling dilution air. Off-gas systems, without the HEPA filters employed for radioactive applications, have been demonstrated on a large scale. Radioactive waste incinerators use HEPA filters for final treatment, which are not commonly used on hazardous waste systems. Additionally, the buried waste combination, including alkali sludges and chlorinated wastes, is unique. Factors such as these require careful design of the off-gas system to remove acid gases and trap fine particulates.

2.2.1.10 Concentrator and Liquid Waste Treatment System. Several options are available to concentrate solutes and treat liquid wastes. Evaporator/crystallizers are in operation to treat LLW in Spain, Japan, Taiwan, and U.S. nuclear power stations and have had many years of operation. A process known as TRU/Clear appears to be effective in eliminating alpha-emitting nuclides from aqueous solutions and could be used in conjunction with other unit operations. This process results from research performed at LANL and is now exclusively licensed to the Analytical Development Corporation. Reverse osmosis has been used in some industrial applications, and high-level waste evaporators are used at the Hanford Site to solidify high-level tank wastes. In Germany, concentrating and solidifying low-level salt solutions using microwave heating has been demonstrated. Another technique demonstrated in the early 1980s by the Rockwell Energy Systems Group is spray drying baghouse effluents.

Evaporator/crystallizers are well-demonstrated. The TRU/Clear process continues to be demonstrated at LANL and the West Valley Demonstration Project with good results. Although the aqueous wastes from the TRU process are different from those of nuclear power plants, the differences are not expected to impact concentration or treatment operations.

Evaporators/crystallizers have been demonstrated up to 30 gal/min while the TRU/Clear process is being demonstrated on a small-scale plant basis. Depending on the process ultimately chosen, some further development and demonstration may be needed to tailor these unit operations to the specific waste forms and chemistry involved.

2.2.1.11 Dryer. This technology is well established. The INEL calciner operates on high-level wastes. Wiped film evaporators are commercially available as well. The INEL calciner and its predecessor have been operating for more than 20 years. Wiped film evaporators have been used in nonnuclear application for over 30 years. Only engineering is expected to be required to apply these technologies to LLW and TRU waste applications.

2.2.1.12 Solidification of Salts. The solidification process for LLW is currently operational, using bitumen or cement. At commercial utilities, evaporator bottoms are solidified in drum scale systems. These technologies have been demonstrated in the United States and abroad, particularly for nuclear power station wastes. The degree to which these technologies have been proven is a function of leach resistance required. The Transportable Volume Reduction and Solidification System (TVR-III) is a mobile unit that uses bitumen as the solidifying agent. Operational cementing systems have been applied at Pennsylvania Power and Light using the Hittman Mobile Solidification System, at the Hanford Site using the Transportable Grout Equipment, and by the Atomic Energy Commission (CEA) in France for liquid radwaste immobilization. The formulation of cements for longevity is often sensitive to waste characteristics. For instance, high liquid organic content can prevent cement from curing. Cementitious formulations have been developed for many waste forms. The specific concentrates from the concentrator/dryer will determine the cement formulations to be used for solidification of salts. Determination of precise formulations may require some development testing.

2.2.1.13 Solidification of Sludges and Combustible Ash. The cementation of TRU sludges is a proven technology and has been operationally demonstrated at the Rocky Flats Plant. Other solidification operations exist in stationary and mobile form for a variety of wastes. Cementation is the

predominant solidification technique being used. Bitumen solidification is being used for processing boric acid concentrates, sodium sulfate concentrates, and spent ion exchange resins from commercial nuclear power plants. Incinerator ash from the INEL WERF incinerator is cemented. A bitumen solidification process developed and demonstrated in France by CEA has been used for processing French and United States power plant wastes and French military wastes. TVR-III has been used since 1975 to solidify commercial nuclear power plant wastes in the United States.

Cementation and bitumen solidification processes, although operational, should be verified by demonstration with a broader range of ash compositions to ensure they can meet the LDR requirements. The formulation of cements for longevity is sensitive to waste characteristics and should be specifically demonstrated for the waste characteristics in question.

2.2.1.14 Metal Melting. Metal melting equipment and facilities exist commercially, including metal refining systems for highly specialized metals products. Contaminated metals melting was demonstrated at WERF at the INEL. Radionuclide partitioning into slag from the melted metal has been demonstrated, but the specific design of this system and the potential need for further development depend on the output of the Metals Decontamination/Sizing Subsystem. For this study, it has been assumed that only the melting of metals into ingots is required; therefore, neither research, development, nor demonstration is required.

2.2.2 Program Implementation Risks

This section identifies major concerns associated with program implementation assuming that Thermal Treatment/Solidification System with LLW Presort is selected. Furthermore, risk of accomplishing the program objectives is qualitatively characterized. A summary of results and major

areas of concern is shown in Table V-2-1. Individual unit operation risk characterization is shown in Table V-2-2. Program mission and objectives are given in Volume II.

2.2.2.1 Performance Objectives. Baseline cleanup standards for SDA pits and trenches at RWMC cannot be established until an ROD pursuant to the CERCLA process is reached. These standards will be derived ARARs under CERCLA, standards set by risk assessments, and the State and local statutes. Since no specific requirements have been formally established at this time, it is assumed that the major ARARs for this system will be RCRA rules, the appropriate NRC regulations and guides, and DOE regulations and Orders.

In the Thermal Treatment/Solidification System with LLW Presort, the major uncertainties listed below have been identified as areas of concern in the achievement of the performance objectives:

- Inability to characterize the incoming waste input and apply the LDR specified treatment technologies.
- Ability to efficiently assay TRU waste and segregate the incoming LLW.
- In this system, thermal desorption is an emerging technology. The process has limited commercial experience and has been demonstrated only on a pilot-plant basis. DT&E will be needed to demonstrate (a) versatility for buried waste streams applications, and (b) compliance with RCRA, NRC, and DOE requirements.
- Solidification processes require specific formulations to provide longevity, low leachability, and LDR compliance. These processes are sensitive to the materials being treated. Because of insufficient data on the input waste characteristics, there are uncertainties regarding the effectiveness of the proposed solidification unit operations.

Table V-2-1. 3-IT-1 summary of program implementation risks and major areas of concern

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> Ability to characterize waste and implement the proper LDR treatment techniques Alpha cell confinement of radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events Potential jamming and malfunction of complex mechanical devices and becoming a choking point Dust control during operations in the alpha cells Dust control and equipment decontamination & maintenance. Requirements could become a limitation on application of commercially available equipment. Thermal desorber DT&E to demonstrate versatility and compliance with rules and regulations Solidification process DT&E to demonstrate compliance with rules and regulations 	<ul style="list-style-type: none"> Ability to define and mitigate Pu-contaminated material safety concerns Ability to define and mitigate radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events Ability to define postulated accident events for thermal desorber process 	<ul style="list-style-type: none"> Public acceptance of thermal process 	<ul style="list-style-type: none"> Solidification process application, verification, and compliance with RCRA & NRC may require prolonged DT&E Thermal desorber application, verification, and compliance with RCRA & NRC may require prolonged DT&E 	<ul style="list-style-type: none"> Thermal desorber application to large scale plants Alpha cells in this environment is a first-of-a-kind design Use of remotely operated mechanical equipment on TRU waste is a first-of-a-kind application
Moderate	Low	High	Low	Moderate

Table V-2-2. Risk rankings of unit operations (3-IT-1)^a

<u>Technical and Unit Operation</u>	<u>Performance</u>	<u>Safety</u>	<u>Cost</u>	<u>Schedule</u>
Assay	L	L	L	L
Open/sort drums	L	L	L	L
Dump/sort waste	L	L	L	L
Grinder	L	M	L	L
Organics treatment	M	L	M	M
Shredder	L	M	L	L
Thermal treatment	L	M	L	H
Off-gas treatment	M	M	H	H
Concentrator/dryer	L	M	L	L
Solidification (all)	M	L	M	H
Melting metal	L	M	L	L

a. L = low
M = medium
H = high.

- Processing of the waste will be conducted in several alpha cells. These cells will contain dust and any radioactive, hazardous, toxic, and volatile gases that may become airborne during the waste handling and processing operations. Protection will have to be provided in normal and postulated accident events (e.g., a fire). Alpha cells, as used in the nuclear environment, typically have triple confinement barriers. Several of the waste handling operations will use technologies that are existing but will have to be adopted for use in an alpha cell environment. This requires remote operation and ease of decontamination for maintenance. These features make this system a first-of-a-kind facility with many uncertainties regarding the development of a cost effective design that provides the following:

- Adequate confinement of radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events.
- Efficient operation of the complex mechanical equipment such as drum opening devices, sorting units, size reduction machines, manipulators, waste conveyors, and all related components that must be installed inside alpha cells. There is a concern regarding potential jamming and malfunction of these components. Any of these unit operations could be a potential choke point because of limited prior knowledge of waste streams and the high throughput requirements.
- Additional technical concerns are (a) dust control during operations in the alpha cells could require very large and complex ventilation and filtration systems, (b) questionable operation of some of the equipment in a dusty environment, and (c) dust control in the alpha cell environment and equipment decontamination requirements before maintenance could become a limitation on the application of commercially available equipment. DT&E efforts could become more extensive than estimated.

Based on the above discussions, it is believed that the overall risk associated with achieving the performance objectives is moderate.

2.2.2.2 Health and Safety Objectives. The key health and safety objectives for the Buried Waste Program are to (a) identify the hazards of the remedial action operation, and (b) provide measures to eliminate, control, or mitigate identified hazards. In this system, the major areas of uncertainty are

- The ability to define postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material) for the alpha cells and provide mitigation measures to satisfy the RCRA, NRC, and DOE requirements.

- The ability to define postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material) for the thermal processes. Definition and mitigation of the normal and accident events could become more complex than currently envisioned.

The uncertainties in regard to health and safety objectives are largely from the inability to characterize the incoming waste. DT&E of characterization could provide a better confidence level. It is believed that using remote handling equipment and conducting operations inside alpha cells will enhance mitigation measures for a majority of the normal and postulated events. This approach reduces the risk associated with achieving the health and safety objectives. At this stage of the system modeling, it is believed that the overall risk is low.

2.2.2.3 Institutional Objectives. A key institutional objective is to involve the public, as required by CERCLA and NEPA, in the process of selecting a remedial action for the Buried Waste Program. Thermal processes are believed to receive low public support. Hence, it is believed that the risk associated with achieving the institutional objective is high.

2.2.2.4 Schedule Objectives. The objective of the Buried Waste Program schedule is to reach approval for Title II start by mid 1999. This is based on the assumption that an ROD will be reached by the end of FY 2001. The schedule objective for completion of the Buried Waste Program remedial action is by FY 2019. The following major uncertainties in achieving these objectives have been identified:

- Thermal desorbers are relatively new processes. DT&E work needed to confirm the process applicability and regulatory compliance could be prolonged.
- The alpha enclosure is a relatively complex first-of-a-kind structure and could be subject to prolonged DT&E, design, and

construction. However, with advanced planning, uncertainties of achieving schedule objectives could be reduced.

- Use of remotely operated mechanical equipment for sorting, conveying, size reduction, and handling of TRU waste is a first-of-a-kind application. Schedule uncertainties from prolonged DT&E, design, and construction are anticipated. Again, with advanced planning, uncertainties of achieving schedule objectives could be reduced.
- Demonstration of waste solidification and compliance with EPA, NRC, and DOE standards may require prolonged DT&E.

It is believed that the above uncertainties could be resolved within the timeframe allowed by the schedule objectives if program implementation activities start in FY 1992. Accordingly, schedule risk is believed to be low.

2.2.2.5 Cost Objective. Assessment of the cost objective is a qualitative characterization based on the uncertainties involved in defining a reasonably accurate cost estimate for the system. Some of the major uncertainties are presented below:

- Thermal desorber techniques have not been used in large-scale applications such as the Buried Waste Program. Uncertainties in defining the cost primarily involve regulatory compliance, and are anticipated to exist until design, based on DT&E, is well into maturity.
- Uncertainties in defining the cost of the solidification unit operations are anticipated primarily because of regulatory compliance.
- The use of an alpha cell in the given waste processing environment is a first-of-a-kind design subject to cost overruns from

prolonged design development. Major areas of uncertainty are (a) the scope of design features needed for operating in a dusty environment, (b) providing safety for postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material), and (c) satisfying the RCRA, NRC, and DOE requirements. Currently, the limited information available on waste characteristics contributes to these uncertainties.

- Use of remotely operated mechanical equipment for container opening, sorting, size reduction, and handling of TRU waste is a first-of-a-kind application. Cost uncertainties are anticipated until design, based on DT&E, is well into maturity.

Based on the above discussions, the cost risk is believed to be moderate.

2.2.3 Unit Operations Pro and Con Analysis

The maximum score possible for any process measured on any evaluation criteria is 10. In some cases, the ability of even the best alternative is such that the highest score is less than 10. Each of the criteria is given equal weight, so a simple summation of the scores assigned to a candidate process determines the overall score.

This score, when compared to the total score of the other candidate processes determines the selected process. The criteria are timeliness, availability, completeness, risk, flexibility, cost, safety, and waste reduction.

2.2.3.1 Assay. Even though assay systems have been developed and demonstrated at LANL and are currently operational for drum handlings, their application for segregating LLW from a TRU waste stream is questionable. Therefore, the overall score given to the assay systems is 5. The key criteria receiving low scores are timeliness, availability, completeness, risk, and flexibility.

2.2.3.2 Open Packages and Sort Packages. Two basic processes were considered, remote and contact.

The reference systems for this analysis are the manual sorting systems available for LLW at SEG, the glove box sorting line installed at LANL, and the previous drum opening experience at the Rocky Flats Plant. Remote assay equipment is in use at several DOE facilities, including SWEPP. Although remote handling of the packages after the assay has not been demonstrated, it is assumed that this would be a direct application of available remote equipment. Table V-2-3 gives an analysis of the pros and cons of this system. This analysis favors the remote process for determining the contents of a package before assigning it to the subsequent waste treatment process.

Although the remote process system does present increased technical risk and is somewhat less flexible than manual sorting, the safety concerns of manual waste handling and the problems of the inability to deal with highly radioactive packages are overriding.

2.2.3.3 Dump Drums and Sort Waste. The same discussion applies to this unit operation as the previous one. The conclusion is that remote handling is the preferred and recommended alternative.

2.2.3.4 Grinder. Any of several commercial grinders available for crushing ores and soft processing solids are assumed to be acceptable. No specific item of equipment is selected at this stage of the analysis. The score given commercially available grinders for each criterion is 10, except for safety, which is scored 7.

2.2.3.5 Organics Treatment (Sludges). Two processes were considered, thermal desorption and incineration. Thermal desorption involves the thermal heating of the sludges in an oxygen deficient environment. The organics are either directly volatilized or decomposed into light organics and then volatilized. Both indirectly heated systems and microwave systems have been tested on a pilot scale. Incineration of the sludges directly destroys the organics in a high-temperature oxidizing environment. Many candidate

Table V-2-3. Open packages and sort packages analysis

	Score	
	<u>Remote</u>	<u>Contact</u>
Timeliness	10	10
Availability	7	10
Completeness	10	7
Risk	5	5
Flexibility	7	6
Cost	10	10
Safety	10	10
Waste reduction	<u>NA</u>	<u>NA</u>
Total	59	48

incinerator types could be used for this task, including fluidized bed, rotary kiln, rotary hearth, and molten salt. An analysis of these processes is given in Table V-2-4.

Table V-2-4. Organics treatment analysis

	Score	
	<u>Thermal Desorber</u>	<u>Incineration</u>
Timeliness	10	10
Availability	7	10
Completeness	8	8
Risk	8	10
Flexibility	7	7
Cost	7	7
Safety	10	5
Waste reduction	<u>10</u>	<u>10</u>
Total	67	67

Both processes address the problem well. In the scoring, the thermal desorber was downgraded because of its pilot-plant status. However, the direct application of incineration to these light materials could cause extraordinary requirements on the off-gas system, and the higher temperatures could cause incinerator operating problems. Therefore, the incinerator was downgraded more on the safety aspects. Because of the desire for the SDS to consider some research stage unit operations and the closeness of the scores of these alternatives, thermal desorption will be the technology of choice for this application.

2.2.3.6 Solidification. Four alternative solidification agents are listed to solidify the TRU wastes. Three of these selections use organic solidification agents. Because gas generation from the biological degradation of organics is a concern at WIPP, these agents must be disqualified from consideration at this level of the analysis. Therefore, only Portland cement remains as an alternative for solidifying TRU waste. Table V-2-5 gives an analysis of this process.

Table V-2-5. Solidification analysis

	<u>Score</u>
Timeliness	10
Availabilty	8
Completeness	6
Risk	8
Cost	8
Flexibility	6
Safety	10
Waste reduction	<u>10</u>
Total	66

2.2.3.7 Shredder. Size reduction of the waste to enable simple subsequent handling can be remotely accomplished with a shredder. There are several types of shredders available in the municipal solid waste industry.

Slow-speed rip/tear operations are commonly used, although hammer mills and high-speed chippers are also options. A slow-speed rip/tear system was selected for the PREPP system, and maintenance requirements were high. The analysis in Table V-2-6 assumes the complete rip/tear shredder system includes a remote feed system and a capability to remove oversized and hard objects.

Table V-2-6. Shredder analysis

	<u>Score</u>		
	<u>Rip/Tear</u>	<u>Remote</u>	<u>Contact</u>
Timeliness	10	10	10
Availability	10	10	10
Completeness	8	8	8
Risk	10	8	8
Flexibility	8	8	8
Cost	10	10	10
Safety	7	5	5
Waste reduction	<u>10</u>	<u>10</u>	<u>10</u>
Total	73	69	69

The analysis shows the slow-speed rip/tear system to be slightly superior based on safety and risk factors. The safety factor is related to the dusting created by the high-speed systems, and the risk advantage is related to the demonstrated system at PREPP. The high scores should not imply that the systems are entirely satisfactory. In fact, all of these systems are expected to present a problem, but on most factors they are similar so they are scored similarly.

2.2.3.8 Thermal Treatment (Combustibles and Loose Material). Two processes were considered: incineration (many options) and biological treatment.

Incineration of LLW is currently being done at the INEL using the WERF controlled air incinerator and at the commercial SEG facility at ORNL. Incineration of radioactive waste is also carried out at numerous facilities abroad. Biological treatment has been used in lieu of incineration in some hazardous waste applications. However, these applications are generally in oil-contaminated soil. No biological treatment of solid waste with widely varying organics contaminants was identified. In fact, it is unlikely with the current state of biological treatment systems that such a treatment is possible. An analysis of these processes is given in Table V-2-7.

Table V-2-7. Thermal treatment analysis

	Score	
	<u>Incineration</u>	<u>Biological Treatment</u>
Timeliness	10	4
Availability	10	2
Completeness	8	3
Risk	10	3
Flexibility	10	3
Cost	7	6
Safety	5	10
Waste reduction	<u>10</u>	<u>5</u>
Total	70	36

Biological treatment is inferior to incineration for almost all of the criteria. Safety is an aspect in which biological treatment may be superior, but even that is not ensured.

2.2.3.9 Off-gas Treatment. The off-gases from the incineration process must be treated to remove acid gases and particulate matter. Two options are commonly available, wet and dry systems. With the expected amount of acid gases generated by the chlorinated wastes, a wet system (or semidry) is the only option that will meet regulatory requirements. Because wet and semidry

systems are similar in chemical and contact mechanisms, no pro/con analysis is warranted. An analysis of off-gas treatment is given in Table V-2-8.

Table V-2-8. Off-gas treatment analysis

	<u>Score</u>
Timeliness	10
Availability	6
Completeness	7
Risk	8
Flexibility	4
Cost	7
Safety	7
Waste reduction	<u>NA</u>
Total	49

2.2.3.10 Concentrator/Dryer. Three processes were considered: evaporator, reverse osmosis, and TRU/Clear. Evaporators for either process industry wastes or radioactive wastes are available commercially. Dryers for the solids are also commercially available. The New Waste Calcining Facility (NWCF) fluidized bed dryer operates on acidic radioactive waste at the INEL. Reverse osmosis can be used for preconcentration of clean solutions. Application to the "dirty" streams of this process would entail prefiltration. TRU/Clear is a commercial process for clarifying contaminated water solutions, specifically with TRU contaminants. The TRU/Clear process is more appropriate for a "polishing" following the other treatments; therefore, it is deleted as a unique alternative. The pros and cons of this system are analyzed in Table V-2-9. The readily available state of evaporators overrides the reverse osmosis applicability.

2.2.3.12 Assay and Sort. The assay system at this point identifies waste that has been converted to TRU by the volume reduction process. The unit is a straightforward application of assay equipment and of the type used at SWEPP. No options are proposed.

Table V-2-9. Organics treatment analysis

	<u>Score</u>	
	<u>Evaporator</u>	<u>Reverse Osmosis</u>
Timeliness	10	10
Availability	10	10
Completeness	10	8
Risk	10	6
Flexibility	10	8
Cost	10	8
Safety	8	8
Waste reduction	<u>10</u>	<u>10</u>
Total	78	68

2.2.3.11 Melt Metal. The output of the Metals Decontamination and Sizing Subsystem will determine the need to either further decontaminate TRU metals or melt the metal into ingots for disposal. Further decontamination may require melting and radionuclide partitioning into slag. If only surface reduction is required, the metal will be melted and formed into ingots. For this study, the latter is assumed, and no pro/con analysis is warranted, as is shown in Table V-2-10.

Table V-2-10. Metal melt analysis

	<u>Score</u>
Timeliness	10
Availability	10
Completeness	8
Risk	10
Flexibility	10
Cost	7
Safety	10
Waste reduction	<u>10</u>
Total	75

2.2.4 Unit Operations Lead-Time Estimates

An ROM estimate was made of the effect that research development and demonstration requirements have on unit operation lead-times. Table V-2-11 depicts these lead-times for each unit operation included in this system.

2.2.5 Rough Order of Magnitude Cost Estimates

This section presents four categories of cost estimates for this system: research and development, demonstration, capital costs, and operations. These costs are shown in Table V-2-12.

2.2.5.1 Demonstration, Testing, and Evaluation Costs. The cost estimates are based on the lead-time estimates in the previous section. The lead-time estimates were developed on a unit operation by unit operation basis. Demonstration projects are assumed to be nonradioactive production-scale tests of complete unit operations or combinations of unit operations. The unit operations used in this process functional diagram are adequately developed, and no research was judged to be necessary.

The thermal treatment system for sludge was judged to require waste specific demonstration on a small pilot plant to ensure adequate organics destruction could be expected. The thermal treatment system for combustibles was assumed to require some development to refine the design for controlling particulate material, develop a reliable seal design, and develop reliable solids handling systems meeting operations criteria.

Solidification testing for the specific waste would be necessary to ensure compliance with the TCLP test under widely varying waste recipes.

The following assumptions were used to arrive at a demonstration cost estimate:

- The drum dumper would be assembled from commonly available drum handling systems. A mechanical test would be required to ensure

Table V-2-11. DT&E assessment summary for the Thermal Treatment/Solidification System with LLW Presort (3-IT-1)

DT&E step	Primary paper evaluation		Bench-scale studies		Secondary paper evaluation		Pilot-plant/mock-up test studies		
	Required	Duration	Required	Duration	Required	Duration	Required	Duration	Total Duration
Assay	Yes	6 Months	Yes	36 Months	No		Yes	12 Months	54 Months
Open Packages & Sort	Yes	6 Months	No		No		Yes	18 Months	24 Months
Dump Drums & Sort	Yes	6 Months	No		No		Yes	18 Months	24 Months
Organic Treatment (sludge)	Yes	6 Months	Yes	12 Months	Yes	6 Months	Yes	12 Months	36 Months
Solidification (Sludge)	Yes	6 Months	No		No		Yes	18 Months	24 Months
Shredder	Yes	6 Months	No		No		Yes	18 Months	24 Months
Thermal Treatment	Yes	6 Months	Yes	6 Months	Yes	6 Months	Yes	18 Months	36 Months
Off-Gas Treatment	Yes	6 Months	No		No		Yes	12 Months	18 Months
Solidification (Ash)	Yes	6 Months	No		No		Yes	18 Months	24 Months
Concentrator/Dryer	Yes	6 Months	No		No		Yes	12 Months	18 Months
Solidification (Salts)	Yes	6 Months	No		No		Yes	18 Months	24 Months
Melting Metal	Yes	6 Months	No		No		Yes	12 Months	18 Months

Table V-2-12. Rough order of magnitude cost estimates (3-IT-1)^a

Cost Code	Cost Items	Normalized Cost (\$x1000)	Modified Cost (\$x1000)
1.0	Studies and bench scale costs		
1.1	Manpower costs during research	\$5,300	\$5,300
1.2	Equipment costs	\$840	\$840
1.3	Installation costs	\$3,400	\$3,400
1.4	Contingency	\$2,385	\$2,385
	Subtotal 1.0	\$11,925	\$11,925
2.0	Demonstration costs		
2.1	Manpower cost during construction	\$1,368	\$1,368
2.2	Design cost (30% of 2.5)	\$3,419	\$3,419
2.3	Inspection cost (7% of 2.5)	\$798	\$798
2.4	Project administration (10% of 2.5)	\$1,140	\$1,140
2.5	Construction cost		
2.5.1	Building structure costs	\$1,000	\$1,000
2.5.2	Equipment costs	\$8,010	\$8,010
2.5.3	Indirect (20.9% of 2.5)	\$2,388	\$2,388
	Subtotal of 2.5	\$11,398	\$11,398
2.6	Construction management costs (27.8% of 2.5)	\$3,271	\$3,271
2.7	Contingency	\$5,349	\$5,349
	Subtotal 2.0	\$26,743	\$26,743
3.0	Production construction costs		
3.1	Design cost (30% of 3.4)	\$79,074	\$66,300
3.2	Inspection cost (7% of 3.4)	\$18,451	\$15,470
3.3	Project administration (10% of 3.4)	\$26,358	\$22,100
3.4	Construction cost		
3.4.1	Building structure costs	\$129,281	\$95,621
3.4.2	Equipment costs	\$79,082	\$79,082
3.4.3	Indirect (20.9% of 3.4)	\$55,216	\$46,296
	Subtotal of 3.4	\$263,579	\$220,999
3.5	Construction costs and construction management reserve (26.5% of 3.4)	\$75,647	\$63,427
3.6	Contingency (25% of 3.1 through 3.5)	\$115,777	\$97,074
	Subtotal 3.0	\$578,886	\$485,369
	Total Capital Cost (1.0, 2.0, and 3.0)	\$617,554	\$524,037
4.0	Annual operating and maintenance costs		
4.1	Operating costs	\$22,499	\$22,499
4.2	Utility costs	\$152	\$152
4.3	Material costs	\$635	\$635
4.4	Maintenance costs	\$5,047	\$5,047
4.5	Contingency	\$7,083	\$7,083
	Subtotal 4.0	\$35,416	\$35,416
TOTAL	10 Years Operating and Maintenance Costs		\$354,163

a. Does not include the appropriate subsystem costs (see Volume VII for subsystem costs).

that the designed system would operate on the sludge drums, irrespective of the condition of the contents. The effort would involve a group of 10 engineers and pilot plant operators for a short period.

- The organics treatment system should be tested on a pilot-plant scale to ensure simulated waste could be treated to a residual organics level satisfactory to regulatory bodies. The test could be carried out in a contract pilot plant; however, for estimating purposes, it is assumed that a pilot plant could simply be assembled. The operation of the pilot plant will entail a complete year of staff to identify problems and corrections. The equipment cost can be kept relatively low. However, it is expected that sampling and analytical costs will be high. A few hundred samples can be expected to be taken in the test period at costs as high as \$2000 per sample. As a thermal treatment system, it would have to be run around the clock, and a team of 15 operators and engineers would be required to devise tests, run the system, and modify as necessary.
- The major activities associated with the thermal treatment of combustible materials are related to the demonstration of reliable, nondusting handling systems for the feed and ash. It is expected that confirmation of the incinerator seals will be required to ensure that the final system will be acceptable in a TRU waste processing service. These mechanical mockups will require considerable equipment and design cost but limited operations cost. A staff of 12 engineers and operators would be necessary for these tests.
- The use of solidification agents to immobilize waste is reasonably well developed. However, a laboratory program is required to confirm the exact formulations to meet the leach test criteria. The laboratory effort is relatively small, but analytical costs are assumed to be high. This effort would require a staff of three

chemists and technicians. The one-year program recognizes the typical delays in analytical results.

- The following costing assumptions were made:
 - The engineering of the small equipment will equal the procured equipment cost
 - The average fully-loaded cost for manpower (all grades) is \$50/h.

2.2.5.2 Demonstration Costs. It was judged that several of the mechanical systems, such as open packages and sort, would require demonstration in a nonradioactive mockup system. Both thermal treatment systems, along with associated solids handling equipment, should be demonstrated in a nonradioactive environment. Unless suitable portable systems can be identified for use in testing, these demonstration tests are expected to require substantial design, setup, and operation costs.

The capital cost assumptions were as follows:

- A 1/10 full-scale nonradioactive development system would be constructed in existing building space, which requires only minor building modifications
- The thermal desorter, metal melter, incinerator, off-gas system, and concentration/dryer would have to be mocked up.

The resulting cost elements are summarized in the estimated cost breakdown (Table V-2-12).

2.2.5.3 Capital Costs. The capital cost estimates were developed using the following methodology:

- Equipment costs were obtained from vendor estimates of these components or similar components, or engineering estimates
- Building costs were estimated from the layout drawings developed in the F&OR sections. These layouts and the areas calculated in the layouts were used to determine moderate hazard areas and alpha containment areas. These building space costs were estimated on the basis of \$350 and \$1000/ft², respectively.
- Equipment costs for unit operations of similar capacity were scaled according to the $X^{0.6}$ rule, where X equals the capacity to correct costs for the appropriate capacity.
- Standard handbook information was used to scale the purchased equipment costs to installed equipment costs. These factors include installation, field engineering, and fees. For facilities of this type, the overall factor assumed was approximately four.
- The resulting information is provided in Table V-2-12, which summarizes costs and adds applicable factors.
- The costs of offices and nonprocessing areas of the facility were not calculated.
- Stainless steel equipment was generally costed to allow for easy decontamination and maintenance, even when materials considerations indicated cheaper construction would be appropriate. This generally resulted in assuming the most expensive equipment or factors.

The calculated alpha cell containment area is 66,800 ft² and the moderate hazard area is 179,000 ft². The resulting building cost is then \$129,281,000. The cost of the installed processing equipment was estimated to be \$79,082,000, including the cost of the Low Level Waste Subsystem (5-IT-3). These costs were entered into the capital cost estimate summary sheet, which led to a calculated facility cost of approximately \$483,400,000.

2.2.5.4 Operating Costs. Four subcategories of costs were included as operating costs: operating labor, maintenance (5% of equipment cost), utilities (estimated from mass and energy balance information), and raw material costs (such as Portland cement).

2.2.6 System Evaluation Results

This section provides an overall evaluation of the system, including any clear advantages or disadvantages, a subjective numerical measure of the overall efficacy relative to other systems studied, a summary of research and development needs, and an overall recommendation regarding the implementation of the system within the context of this very preliminary study.

2.2.6.1 Identification of Major Considerations. For the most part, the major unit operations within this system are either developed and demonstrated or can probably be fully demonstrated within two to four years. It does not appear that basic research will be required for any unit operation. Some demonstration will be required for organics treatment of sludges, thermal treatment of combustibles, and solidification of the various treated waste products. The integration of the unit operations into a viable waste treatment facility seems to be well within the capability of the architect/engineering and chemical plants industries to perform. This is, of course, a distinct advantage. Presorting LLW before processing the TRU waste also has advantages, because the confinement requirements for TRU processing are more stringent than those for LLW.

By presorting the LLW, a smaller TRU processing line can be built, with commensurate safety advantages. In addition, the volume of waste disposed in a TRU geologic repository is minimized. Two disadvantages were identified during the course of the study. The first pertains to the effect of changing regulatory climates on the thermal treatment, off-gas, and solidification operations. The tendency toward more stringent requirements may produce regulatory uncertainties that must be recognized during the facility planning stage. The second disadvantage concerns the presorting of LLW and the need

for a reliable assay technology and an additional LLW process line in addition to the TRU waste processing line.

2.2.6.2 Performance Measurables Rating. Each of the systems studied were evaluated for comparison with other systems. This was accomplished using a subjective numerical ranking process. Each unit operation was given a score of 1 to 10, with 10 being the best, for the following criteria: timeliness, availability, completeness, risk, flexibility, cost, safety, and waste reduction.

Table V-2-13 shows the scores that were assigned to each unit operation and the sum of these scores.

2.2.7 Summary of Demonstration, Testing, and Evaluation Needs

The system DT&E needs are summarized in Table V-2-11.

2.3 RECOMMENDATION FOR THE SYSTEM

There are several considerations that recommend this system for consideration. By presorting the LLW, less waste will need to be disposed in a TRU geologic repository. The smaller space required for TRU waste processing also improves the operating safety of the facility. Implementation of the system involves relatively little development and demonstration, except the assay unit operation, before a facility can be built and does not appear to require any basic research. The integration of the unit operations into a functioning facility should not present any extraordinary challenges, which results in a definite advantage in light of the urgency for processing DOE radioactive wastes.

Overall, the system appears to be sufficiently viable to warrant further consideration. It should be recognized, however, that this conclusion needs to be compared to the results of other system studies.

Table V-2-13. Rating performance measurables for Thermal Treatment/Solidification System with LLW Presort (3-IT-1)

Measurable	Assay	Open Packages and Sort	Dump Drums and Sort	Grinder	Organic Treatment (sludges)	Solidification	Shredder	Thermal Treatment	Off-gas Treatment	Concentrator Dryer	Melt Metal	Assay and Sort	Total
Timeliness	10	10	10	10	10	10	10	10	10	10	3	10	113
Availability	10	7	7	10	7	8	10	10	6	10	3	10	98
Completeness	10	10	10	10	8	6	8	8	7	10	3	10	100
Risk	10	5	5	10	8	8	10	10	8	10	3	10	97
Flexibility	10	7	7	10	7	8	8	10	7	10	3	10	97
Cost	10	10	10	10	7	6	7	7	4	10	5	10	96
Safety	10	10	10	7	10	10	10	5	7	8	10	10	107
Waste Reduction	NA	NA	NA	10	10	8	10	10	NA	10	10	NA	68
Totals	70	59	59	77	67	64	73	70	49	78	40	70	776

3. THERMAL TREATMENT/SOLIDIFICATION SYSTEM WITH POSTSORT (3-IT-3)

This section describes a system in which the buried waste is treated to meet the requirements of RCRA LDRs using the technologies of incineration and solidification. More specifically, TRU sludges are solidified in one of several solidification agents, combustibles and inerts are processed through a thermal treatment system, and the resultant ash is similarly immobilized. Metals are processed in the Metals Decontamination and Sizing Subsystem to convert most of the metal to LLW. LLW is separated from TRU after processing in the TRU system.

3.1 FUNCTIONAL AND OPERATIONAL REQUIREMENTS

The F&OR for the Thermal Treatment/Solidification System with LLW Postsort is the same as Section 2.1 with the exceptions noted below:

- Assay—All packages will be passed through an assay process to determine fissionable material inventory as well as beta/gamma scanning. Segregation of LLW will not be accomplished at the front end.
- Process functional diagram—The processing system studied in this task is schematically presented in Figure V-3-1. The individual components of the system are the same as Section 2.1 with the exception that the system will not include an LLW processing subsystem and, hence, as assay unit operation for segregating LLW from the incoming waste stream will not be required.
- Facility description—The facility layout for this system is shown in Figure V-3-2.
- Unit operations design requirements.

DESCRIPTION: THE SYSTEM IS A THERMAL TREATMENT/SOLIDIFICATION SYSTEM TO MEET LDR REQUIREMENTS. LLW IS POSTSORTED. POSTSORTING INCLUDES ORGANIC TREATMENT, THERMAL TREATMENT, SOLIDIFICATION, AND MELTING. SPECIAL LDR WASTES ARE TREATED IN A SPECIALIZED PROCESS.

Figure V-3-1. Process functional diagram for the Thermal Treatment/Solidification System with LLW Postsort (3-IT-3).

Note: Mass flow balance does not show the input process additives.

FACILITY PROCESS

DRAWING NUMBER 3-IT 3

DESIGN
CAPACITY
(lbs/hr)

PROPANE
(gal/hr)

ELECTRICITY
(kW)

UNIT OPERATION

Assay
Open Packages and Sort
Dump Drums and Sort
Shredder
Thermal Treatment
Off-Gas Treatment
Organics Treatment
Grinder
Concentration Dryer
Melter
Solidification
Package
Assay and Sort

2680
2680
886
1000
1200
5450
250
550
120
110
1000
3360
3360

0.00
0.00
0.00
0.00
7.75
0.00
3.24
0.00
0.00
0.00
0.00
0.00
0.00

1
4
4
1.1
4.2
2.4
2
5
5
1.2
170
4
1

E 12/11/91		READY FOR REVIEW		J.P.		J.N.		J.V.		APPR.	
NO. 1		DATE 1		REVISION		BY		CHKD.		ENGR.	
3/6/91		1/1/91		1/1/91		1/1/91		1/1/91		1/1/91	
<p>INTERNATIONAL TECHNOLOGY CORPORATION A FORT WORTH, TEXAS</p>											
<p>EG & G IDAHO, INCORPORATED SYSTEM DESIGN STUDY IDAHO FALLS, IDAHO</p>											
<p>PROCESS FLOW DIAGRAMS FOR SYSTEM DESIGN STUDY</p>											
JOB NUMBER				DRAWING NUMBER				REVISION			
101411				5-11-3				1

NOTES:

- PROCESS COULD INCLUDE WASTE PASSTHROUGH AREAS
- INCINERATOR OFFGAS, CONCENTRATING/ DRYER SYSTEMS ARE MULTISTORY
- PERSONNEL & MATERIAL BASEMENT ACCESS & PASSAGE AS REQUIRED
- PROCESS HEPA FILTRATION AT EACH STATION AS REQUIRED
- BUILDING VENTILATION FOR HEPA FILTRATION - MINIMIZE DUCT LENGTH
- ADMINISTRATION BUILDING LOCATION IS OPTIONAL

Figure V-3-2. Facility layout for the Thermal Treatment/Solidification System

SCALE 30'-0" 75' 75'

ATION, ETC
IT-1)

tem with LLW Postsort (3-IT-3).

NO.	DATE	REVISION	BY	CHKD	ENG	APPD
101411	10/14/11	1	JG	JG	JG	JG
INTERNATIONAL TECHNOLOGY CORPORATION ALBUQUERQUE, NEW MEXICO						
CONFIDENTIAL PROPERTY OF IT CORPORATION THIS DRAWING AND ALL INFORMATION THEREON IS CONFIDENTIAL AND NOT TO BE MADE PUBLIC OR COPIED, UNLESS SOLELY AUTHORIZED BY THE COMPANY. IT IS TO BE USED ONLY FOR THE PURPOSES FOR WHICH IT WAS SUBMITTED AND IS TO BE RETURNED ON DEMAND. ALL RIGHTS OF INVENTION OR DESIGN ARE RESERVED.						
I & G IDAHO, INCORPORATED SYSTEM DESIGN STUDY IDAHO FALLS, IDAHO						
PLANT LAYOUT FOR SYSTEM DESIGN STUDY						
JOB NUMBER	DRAWING NUMBER		REVISION			
101411	3-17-3c		1			

- The sorting line must be capable of achieving 125% for the maximum design capacity of the four separation categories processes (2700 lb/h)
- Drum and sort must provide 12% of the maximum design capacity of the organic and inorganic sludge maximum design capacity (880 lb/h)
- Grinder must have a maximum design capacity of 550 lb/h
- Organic treatment must have a maximum design capacity of 250 lb/h and accept items as large as 3 in.
- Sludge solidification must have a capacity design maximum throughput of 125% of the sludge processing process (900 lb/h)
- Shredder must have a maximum capacity of 1200 lb/h
- Thermal treatment must have a maximum design capacity of 1200 lb/h
- Ash solidification must have a capacity design maximum throughput of 125% of the thermal processing ash discharge maximum capacity (680 lb/h)
- Concentrator dryer must accept spent solutions at a rate of 120 lb/h with salt concentrations ranging from 3 to 20%, as well as insoluble particulate
- Salt solidification must have a capacity design maximum throughput of 125% of the concentrator/dryer discharge maximum capacity (7 lb/h)

3.2 SYSTEM ASSESSMENT

Assessment for this system is the same as Section 2.2 except as noted below:

- A summary of the current status of unit operations for this waste treatment system is provided in Table V-3-1
- Rough order of magnitude costs are shown in Table V-3-2
- Table V-3-3 shows the scores that were assigned to each unit operation.

Table V-3-1. DT&E needs for the Thermal Treatment/Solidification System with LLW Presort (3-IT-3)

<u>Unit Operation</u>	<u>Technology Development Status</u>	<u>DT&E</u>
Assay	<ul style="list-style-type: none"> • Being used to perform fissile assays in drums 	<ul style="list-style-type: none"> • Production line assay of TRU waste streams to segregate LLW with high reliability
Open Packages and Sort	<ul style="list-style-type: none"> • Individual operations available 	<ul style="list-style-type: none"> • Integrated Systems demonstration
Dump Drums and Sort Waste	<ul style="list-style-type: none"> • Individual operations available 	<ul style="list-style-type: none"> • Integrated Systems demonstration
Grinder	<ul style="list-style-type: none"> • Commercially available 	<ul style="list-style-type: none"> • Engineering only • Vendor demonstration
Organic Treatment	<ul style="list-style-type: none"> • Microwave and indirect heating devices available • Test being conducted at the Rocky Flats Plant and ORNL • Incineration well developed 	<ul style="list-style-type: none"> • Demonstration of effectiveness for eliminating volatile organics using microwave or indirect heating devices. • Test and evaluation
Shredder	<ul style="list-style-type: none"> • Commercially available 	<ul style="list-style-type: none"> • Engineering only • Vendor demonstration
Thermal Treatment	<ul style="list-style-type: none"> • Incineration technology well developed and commercially available 	<ul style="list-style-type: none"> • Engineering development and scaleup demonstration • Test and evaluation
Off-gas Treatment	<ul style="list-style-type: none"> • Well developed and commercially available 	<ul style="list-style-type: none"> • Demonstration of effectiveness for specific effluents
Concentrator	<ul style="list-style-type: none"> • Well developed • Some commercially available 	<ul style="list-style-type: none"> • Development for specific waste forms and chemistry • Vendor demonstration
Dryer	<ul style="list-style-type: none"> • Well developed and commercially available 	<ul style="list-style-type: none"> • Engineering only • Vendor demonstration

Table V-3-1. (continued)

Unit Operation	Technology Development Status	DT&E
Solidification of Salts	<ul style="list-style-type: none"> • Lead melting equipment available • Nuclide partitioning from other metals has been demonstrated 	<ul style="list-style-type: none"> • Development of formulations for specific salts • Vendor demonstration
Melting of Lead	<ul style="list-style-type: none"> • Solidification technologies being used for nuclear wastes • Nuclide partitioning from other metals has been demonstrated 	<ul style="list-style-type: none"> • Demonstration of nuclide partitioning into lead slag • Test evaluation
Solidification of Lead Slag	<ul style="list-style-type: none"> • Solidification processes generally available • Solidification of lead slag not demonstrated 	<ul style="list-style-type: none"> • Development of a low leaching form that can pass TCLP • Demonstration of lead slag solidification using current methods
Solidification of Sludges and Ash	<ul style="list-style-type: none"> • Solidification technologies being used for nuclear wastes 	<ul style="list-style-type: none"> • Vendor demonstration • Development of formulations for specific waste forms
Melting Metal	<ul style="list-style-type: none"> • Melting equipment available • Nuclide partitioning into slag has been demonstrated 	<ul style="list-style-type: none"> • Vendor demonstration

Table V-3-2. Rough order of magnitude cost estimates (3-IT-3)^a

Cost Code	Cost Items	Normalized Cost (\$x1000)	Modified Cost (\$x1000)
1.0	Studies and bench scale costs		
1.1	Manpower costs during research	\$6,500	\$6,500
1.2	Equipment costs	\$880	\$880
1.3	Installation costs	\$3,500	\$3,500
1.4	Contingency	\$2,720	\$2,720
	Subtotal 1.0	\$13,600	\$13,600
2.0	Demonstration costs		
2.1	Manpower cost during construction	\$0	\$1,955
2.2	Design cost (30% of 2.5)	\$4,886	\$4,886
2.3	Inspection cost (7% of 2.5)	\$1,140	\$1,140
2.4	Project administration (10% of 2.5)	\$1,629	\$1,629
2.5	Construction cost		
2.5.1	Building structure costs	\$1,000	\$1,000
2.5.2	Equipment costs	\$11,876	\$11,876
2.5.3	Indirect (20.9% of 2.5)	\$3,412	\$3,412
	Subtotal of 2.5	\$16,288	\$16,288
2.6	Construction management costs (27.8% of 2.5)	\$4,675	\$4,675
2.7	Contingency	\$7,155	\$7,643
	Subtotal 2.0	\$35,773	\$38,216
3.0	Production construction costs		
3.1	Design cost (30% of 3.4)	\$67,092	\$59,082
3.2	Inspection cost (7% of 3.4)	\$15,655	\$13,786
3.3	Project administration (10% of 3.4)	\$22,364	\$19,694
3.4	Construction cost		
3.4.1	Building structure costs	\$111,408	\$90,301
3.4.2	Equipment costs	\$65,383	\$65,383
3.4.3	Indirect (20.9% of 3.4)	\$46,850	\$41,256
	Subtotal of 3.4	\$223,641	\$196,940
3.5	Construction management costs and construction management reserve (26.5% of 3.4)	\$64,185	\$56,522
3.6	Contingency (25% of 3.1 through 3.5)	\$98,234	\$86,506
	Subtotal 3.0	\$491,171	\$432,529
	Total Capital Cost (1.0, 2.0, and 3.0)	\$540,544	\$484,346
4.0	Annual operating and maintenance costs		
4.1	Operating costs	\$15,240	\$15,240
4.2	Utility costs	\$117	\$117
4.3	Material costs	\$1,023	\$1,023
4.4	Maintenance costs	\$4,086	\$4,086
4.5	Contingency	\$5,117	\$5,117
	Subtotal 4.0	\$25,583	\$25,583
TOTAL	10 Years Operating and Maintenance Costs		\$255,825

a. Does not include the appropriate subsystem costs (see Volume VII for subsystem costs).

Table V-3-3. Rating performance measurables for the Thermal Treatment/Solidification System with LLW Postsort (3-IT-3)

Measurable	Assay	Open Packages and Sort	Dump Drums and Sort	Grinder	Organic Treatment (sludges)	Solidification	Shredder	Thermal Treatment	Off-gas Treatment	Concentrator Dryer	Lead Decon.	Melt Metal	Assay and Sort	Total
Timeliness	3	10	10	10	10	10	10	10	10	10	10	10	10	130
Availability	3	7	7	10	7	8	10	10	6	10	8	10	10	113
Completeness	3	10	10	10	8	6	8	8	7	10	10	8	10	115
Risk	3	5	5	10	8	8	10	10	8	10	7	10	10	111
Flexibility	3	7	7	10	7	8	8	10	7	10	10	10	10	114
Cost	10	10	10	10	7	6	10	7	4	10	7	7	10	108
Safety	10	10	10	7	10	10	7	5	7	7	9	10	10	112
Waste Reduction	NA	NA	NA	10	10	8	10	10	NA	10	10	10	NA	78
Totals	35	59	59	77	67	64	73	70	49	77	71	75	70	846

4. PYROLYSIS AND ACID LEACH WITH PLUTONIUM EXTRACTION SYSTEM (3-EB-6)

This system uses pyrolysis, acid leach, plutonium extraction, and solidification to produce a waste form that meets LDR requirements and restricts the generation of hydrogen gas. Pyrolysis is used to destroy organic contaminants, solidification is used to fix inorganic contaminants, and acid leach and solvent extraction are used to minimize the volume of TRU waste. LLW is sorted out from TRU waste as a final step in the process.

Pyrolysis is a process that breaks down organic waste into less complex materials through the application of heat in the absence of oxygen. The resulting products are combustible off-gases (typically CO, H₂, and CH₄) and a carbonaceous char. The char is then leached with nitric acid in the presence of a silver catalyst to extract the plutonium. The leachate is concentrated by solvent extraction and evaporation and then solidified with other TRU waste.

4.1 FUNCTIONAL AND OPERATIONAL REQUIREMENTS

4.1.1 System Description

Following site characterization, waste material is retrieved through the Retrieval Subsystem (S-BE-4). Soils proceed to the Soils Processing Subsystem (S-EB-2), metals proceed to the Metal Decontamination and Sizing Subsystem (S-EG-1), and all other waste is assayed and packaged for transportation to the processing facility. At the processing facility, the waste material is assayed and sorted into two fractions. Combustible TRU and organic contaminated waste proceeds to the pyrolyzer, and noncombustible TRU waste proceeds to size reduction and solidification. The ash from the pyrolyzer is subjected to an acid leach and solvent extraction process to minimize the volume of TRU waste. Solid waste from the acid leach process is solidified along with waste from the off-gas treatment process and the noncombustible TRU waste.

4.1.2 System Boundaries

The boundary for this system is defined as the interfaces with the standard subsystems (retrieval, soil processing, and metal sizing and decontamination) through the final waste form. Accordingly, the following processes are examined: sorting, size reduction, pyrolysis, fume incineration, off-gas treatment, acid leach, solvent extraction, solidification, packaging, and container assay.

4.1.3 Process Functional Diagram

4.1.3.1 System Specific Assumptions. The following system-specific assumptions were used in estimating the values on the drawing shown in Figure V-4-1:

- Remediation is to be completed in 10 years. There are 240 24-hour work days per year. Equipment availability is 70%.
- The total mass of the retrieved waste (not including soils) is 43,280 tons. Of that, 28,990 tons are combustibles, 9610 tons are bulk metals, and 4680 tons are other noncombustibles.
- 25% of the bulk metals enter this system from the Metal Decontamination and Sizing Subsystem as TRU metals.
- The quantity of TRU soil received from the Soils Processing Subsystem is 240 ton/yr.
- Composition of the combustible waste fed to the pyrolyzer: 30% inerts, 15% moisture, and 55% moisture and ash-free fraction (MAF). The MAF is assumed to be 90% volatiles and 10% fixed carbon.
- The pyrogas exiting the pyrolyzer will contain all of the entering moisture, all of the entering volatile MAF, all of the entering fixed carbon (as CO_2), and 3% of the entering inerts in the form of airborne particulates.

DESCRIPTION:

- RETRIEVAL SUBSYSTEM IS USED TO RETRIEVE AND PRESORT WASTE.
- SOIL PROCESSING SUBSYSTEM IS USED TO PROCESS SOILS.
- METAL SIZING AND DECON SUBSYSTEM IS USED TO PROCESS BULK METALS.
- COMBUSTIBLE WASTE IS PYROLYZED TO REDUCE VOLUME AND DESTROY ORGANIC CONTAMINANTS.
- PLUTONIUM IS EXTRACTED FROM THE PYROLYSIS CHAR TO MINIMIZE THE VOLUME OF TRU WASTE.
- NONCOMBUSTIBLE WASTE, SOLIDS FROM THE ACID LEACH PROCESS, AND WASTES FROM THE OFFGAS TREATMENT ARE SOLIDIFIED TO FIX INORGANIC CONTAMINANTS.
- CONTAINERS ARE ASSAYED AND TRU IS SEPARATED FROM LLW FOLLOWING WASTE PROCESSING.

Figure V-4-1. Process functional diagram for the Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6).

Note: Mass flow balance does not show the input process additives.

PROCESS:
PYROLYSIS AND ACID LEACH WITH
PLUTONIUM EXTRACTION

LLW/TRU: POST SORT

FINAL WASTE FORM #3:
MEETS LDR REQUIREMENTS AND RESTRICTS
HYDROGEN GAS GENERATION

EG&G SYSTEM DESIGN STUDY PROCESS FLOW DIAGRAM

EBASCO
ENVIRONMENTAL

PFD No.

3-EB-6

3/15/91

- The char exiting the pyrolyzer will contain 97% of the entering inerts.
- The fume incinerator uses 3 lb of combustion air per pound of organic gas fed.
- The off-gas treatment process uses 0.16 lb of scrubber chemicals per pound of organic gas fed to the fume incinerator.
- The acid leach process dissolves 25% of the total entering solid mass (char). Fifty percent of the plutonium in the char is dissolved into the leachate.
- 75% of the solidified final waste is TRU. The remaining 25% is LLW.

4.1.3.2 Process Functional Diagram. Mass flow rates are noted in Figure V-4-1 for each applicable stream. Each functional flow box is referred to as a "unit operation," and estimated capacities are noted on the diagram. The capacities noted are based on today's working technology, although some process technologies require additional testing and experience before they can be referred to as "proven" technologies. Energy requirements are also indicated on the diagram.

4.1.4 Facility Description

The pyrolysis plant shown in Figure V-4-2 will include the following equipment: feed hoppers, conveyors, pyrolytic module, fume incinerator, adiabatic quencher, high-energy venturi scrubber, packed bed scrubber, induction heater, and HEPA filters. The acid leach and solvent extraction processes will include the following process equipment: stirred tank reactor for acid leaching, packed bed columns, solvent extraction columns, mixing tanks, and holding tanks. The cement solidification plant will include the following equipment: feed hoppers, mixers, pouring station, and interim storage space for feed material and curing product.

4.1.5 System Design Requirements

4.1.5.1 Functional Requirements. This system will produce a solid waste form that meets LDR requirements and restricts the generation of hydrogen gas. The feed to the system will consist of contaminated soil and waste material retrieved from Pits 1-6, 9, and 10 and Trenches 1-10 of RWMC. The system must be capable of processing all of the waste within a ten-year time frame.

Pyrolysis will be used to destroy organic contaminants and to reduce the volume of waste material. Acid leaching and solvent extraction (plutonium recovery) will be used for TRU waste reduction. Solidification with Portland cement will be used to immobilize inorganic contaminants and produce a solid waste form that meets the LDR requirements. TRU waste will be separated from LLW by container assay as a final process in the system.

4.1.5.2 Performance Requirements. The pyrolyzer will be operated at approximately 1000-1200°F. Lower temperatures are required to generate a more soluble form of plutonium in preparation for the acid leach process. Also, the pyrolyzer must be operated at a slight negative pressure to prevent combustible gases from escaping. The pyrolyzer must be capable of processing 1 ton of waste material per hour.

At least 50% of the plutonium in the char from the pyrolyzer will be recovered in the acid leach process. The plutonium in the aqueous leachate will be concentrated in an organic phase with solvent extraction. A second stage of solvent extraction will concentrate the plutonium back into an aqueous phase. The aqueous phase is then solidified along with other TRU waste. The cement solidification plant will be capable of processing a minimum of 1 yd³ of solid waste per hour.

4.1.5.3 Interface Requirements. Waste material received from the Retrieval Subsystem will be solid material packaged in standard boxes and drums. Each package will be labeled with general identification and assay information.

TRU soil received from the Soils Processing Subsystem will be in a solid or sludge form packaged in standard boxes or drums. Each package will be labeled with general identification and assay information.

TRU metals received from the Metal Decontamination and Sizing Subsystem will be packaged in standard boxes or drums. Each package will be labeled with general identification and assay information.

TRU metal decontaminated sludge from the Metal Decontamination and Sizing Subsystem will be packaged in standard boxes or drums. Each package will be labeled with general identification and assay information. Although a more solid form is desirable, the sludge may be mostly liquid if necessary. Clean gases from the off-gas treatment process will have a low moisture content and will have been processed through HEPA filters.

Containers of solidified waste will have been assayed to determine classification as LLW or TRU waste. The containers will be labeled with general identification and assay information. The solidified mass will meet the requirements for final waste form (meets LDR requirements and restricts hydrogen gas generation).

4.2 SYSTEM ASSESSMENT

4.2.1 Current Status of Unit Operations

The proposed system, as presented in Figure V-4-1, is conceptual and is not being commercially operated. However, the key unit operations shown in the PFD have been widely used. A brief discussion of each unit operation follows.

4.2.1.1 Sort. The two commonly used sorting technologies are manipulator sorting and air classification. Both are established technologies. Air classification sorts by density difference and does not appear to be appropriate for the proposed application. Because of the presence of heavy metals, combustible materials could be present in substantial amounts in the underflow, resulting in poor separation. In

addition, air classification would require large quantities of air that would come in contact with TRU wastes and would subsequently be treated before atmospheric discharge.

Manual sorting using remote control equipment would be slow but would provide a better separation of combustible materials from noncombustible materials. This would also facilitate a closer control over the characteristics of the feed to the pyrolysis unit. Robotically controlled manipulators or telerobots have been successfully tested at the Savannah River Laboratory under a program to test the design and operation of a remotely-operated waste size-reduction and material handling process (Stewart and Charlesworth, 1986). The program was initiated as part of the long-term plan to process the stored waste and generated plutonium waste for permanent disposal. Items tested included plutonium-contaminated glove boxes, piping, valves, and small vessels. The wastes are consistent with the type of wastes to be encountered in the proposed process.

4.2.1.2 Pyrolysis. Pyrolysis is the process of thermally decomposing materials in the absence of oxygen. Pyrolysis accomplishes volume reduction without producing SO_x , NO_x , or other objectionable compounds (dioxins and furans) because the internal atmosphere is deficient in oxygen.

Pyrolytic units are not off-the-shelf items and are generally custom designed for each application. Several different types of pyrolysis units are commercially operated for gasifying wood, coal, refuse, and municipal solid wastes. Commonly used designs include rotary kilns (direct and indirect heating), fluidized bed pyrolyzers, and hearth-type kettle retort units. Testing under the EG&G Idaho PREPP program has shown that rotary units are prone to leaks and may not be appropriate for the proposed applications until suitable seals are developed. Fluidized bed pyrolytic units would require close control over waste feed characteristics and large quantities of air that must subsequently be processed to remove contaminants.

The preferred design would be a hearth-type kettle retort unit in which the waste is fed batchwise from a surge hopper and heated indirectly to 1000-1200°F. A slight negative pressure may be maintained to prevent

emissions from the system and facilitate gentle mixing through turbulence generated as the off-gases are drawn off. Because the waste is likely to contain paper, Kim-wipes, gloves, and similar types of materials, indirect heating using a commonly available fuel source such as diesel or fuel oil would prevent conditions that promote automatic ignition. A nondestructive assay may be necessary on each batch of material fed to the pyrolysis unit as a control method to ensure that the critical mass for plutonium is not exceeded.

The technology to design and build this type of pyrolysis unit is commercially available, but no such unit is currently operational for processing plutonium wastes. A 200 lb/h dual chamber-controlled air incinerator operating at 1400-1800°F has been built and successfully used to process approximately 1.5 million pounds of combustible waste contaminated with enriched uranium from fuel fabrication activities. This system was installed in 1986 to reduce the volume of waste and concentrate the uranium in the ash for recovery. As of April 1989, approximately 100,000 lb of contaminated waste has been successfully processed (Francis and Starr, 1990). Although not a true pyrolysis unit, the system is a hearth-type unit. The proposed feed rate of 3170 ton/yr (1585 lb/h) of waste feed to the pyrolysis unit implies that more than one unit may be required to ensure that the critical plutonium mass is not exceeded in any given unit. Another hearth-type pyrolysis system available for the proposed application is the Tech-Air pyrolysis system. This is a vertical-bed system that has been successfully demonstrated on wood and dry agricultural waste at 2000-4000 lb/h feed rates (Bowen et al., 1978).

Regardless of the system design used, the operation of the pyrolysis unit will have a significant impact on the downstream process. The PFD assumes all of the fixed carbon is removed from the char during the pyrolysis step. The presence of substantial amounts of fixed carbon in the char is likely to interfere with the opportunity for contact between acid and the plutonium, thereby reducing plutonium recovery in the acid leach step. On the other hand, burning off the fixed carbon by introducing hot air could increase the operating temperature locally within the pyrolysis unit. High temperature has a tendency to incorporate plutonium oxide within the silica matrix, thereby

reducing plutonium recovery. The combustion of fixed carbon must therefore be conducted under controlled conditions. A German study conducted on a bench scale (1.5 kg/h of continuous feed) shows that pyrolysis conducted in the presence of steam of organic waste produced in plutonium fabrication, results in a char amenable to acid leaching (Vietzke). This system appears promising but is still in the development stage. In addition, the hydrogen generated during the pyrohydrolysis may conflict with the overall project objective for reducing hydrogen generation.

4.2.1.3 Acid Leach. The proposed acid leaching process uses a mixture of nitric and hydrofluoric acid to dissolve plutonium. This process has been used and researched for a number of applications within the nuclear industry; however, the process may not be effective for specific types of matrices likely to be encountered in the waste. For example, soils generally contain significant amounts of silica. Because of the greater availability of silica (as compared to plutonium) in the waste (contaminated soil), hydrofluoric acid is likely to be consumed in dissolving silica rather than plutonium. Plutonium yield in the extract is expected to be low.

An alternative process suggested is the catalytic electrolytic plutonium oxide dissolution (CEPOD) process. This process, developed by Battelle Pacific Northwest Laboratory in Richland, Washington, uses a solution of silver in nitric acid instead of the nitric/hydrofluoric mixture as the leaching agent. Monovalent silver is converted into a divalent state in an electrolytic cell. The silver oxidizes the plutonium to a hexavalent state. The hexavalent plutonium is soluble in the aqueous phase. The silver, which is reduced to the monovalent state, is reconverted to the divalent state in the electrolytic cell. The silver thus acts as a catalyst.

The CEPOD process has been demonstrated at facilities in France and the United Kingdom. Four test runs were performed at production rates using plutonium contaminated ash. Yields of plutonium in the extract exceeded 90%. The process also removes americium, another TRU metal from the ash. In addition, the CEPOD process has been installed at the Hanford Plutonium Finishing Plant (Wheelwright, Bray, and Ryan, 1987). The CEPOD process avoids the corrosion problems associated with the HF. The generation of hydrogen gas

is insignificant and the rate of plutonium dissolution is substantially higher than the conventional HF/HNO₃ acid extraction process. Several different process configurations could be developed for contacting the acid with the char to suit specific process needs. A continuous stirred tank reactor with a recirculation loop could be used and is a common configuration in industrial applications. An alternative configuration would be to make the acid flow through a column containing a fixed bed of char and recirculate through the bed until the desired plutonium concentration was attained in the solution or the acid solution was spent.

The technology for designing and constructing commercial scale equipment for the acid leaching step is available and can be adapted for the proposed application. However, performance data using actual or surrogate wastes must be generated to develop the optimum design.

4.2.1.4 Solvent Extraction. The solvent extraction step is needed to separate the plutonium, americium, and other TRU metals from the waste. The established method to perform this unit operation is to conduct the extraction in two stages. In the first stage, the acid solution from the acid leach step is contacted with a solvent such as tributyl phosphate dispersed in a diluent like kerosene or Stoddard II solvent. The TRU materials are transferred into the organic phase. In the second stage, the organic phase is contacted with a nitric acid solution or water to recover TRU metals from the organic phase.

The contact between the acid solution and the solvent can be accomplished in a pulse column reactor. This reactor consists of a vertical pipe with a concentric rod (made of acid resistant material) at the center. The rod has several evenly spaced plates with holes or sieves. The acid solution and the solvent enter the reactor in counter current flow. The plates are pulsed to provide mixing and promote uniform dispersion of the solvent in the aqueous phase. An alternative device would be a centrifugal contactor. However, the centrifugal contactor requires more maintenance; therefore, for the proposed application, the pulse column reactor would be the preferred alternative.

The technology for solvent extraction has been demonstrated and extensively used in the separation of plutonium from uranium, but has not been

applied to the separation of plutonium from plutonium-contaminated wastes. An alternative technology that is commercially available is ion exchange. Special resins can selectively remove plutonium from the acid extract, but removal of americium is not guaranteed (Cleveland, 1970). A combination of available demonstrated technologies can be applied for the solvent extraction step to meet specific process needs.

4.2.1.5 Fume Incinerator. The function of the fume incinerator is to destroy the organics present in the gases that leave the pyrolysis unit. Fume incinerators have been widely used in a variety of industrial applications. The technology to design and construct a system for the proposed application is commercially available. The design of the pyrolysis unit may be integrated with the fume incinerator if equipment space is limited. The precise configuration to be used should be tailored for the proposed application and can be addressed during the detailed design phase.

4.2.1.6 Off-gas Treatment. The flue gas from the fume incinerator must be treated to remove contaminants before discharge. This is accomplished in the off-gas treatment system. The design of the off-gas treatment system is state-of-the-art and commercially available but will have to be tailored for the specific application.

Based on the characteristics of the wastes that are likely to be processed, the off-gas is not likely to contain SO_x . Some NO_x could be generated from the CEPOD dissolver but can be removed by dissolving in water. Hydrochloric acid will be formed from the chlorinated contaminants present in the waste. A suggested system is to cool the flue gas to saturation by liquid sprays in a quench column. Particulate material can be captured by a high-energy venturi scrubber. A packed column can be provided to neutralize the acid gases. The gas can be reheated electrically to lower its relative humidity, passed through a bank of HEPA filters, and discharged.

4.2.1.7 Shredder. Shredding equipment is required to process noncombustible wastes into a form amenable for subsequent solidification. Shredding devices and the associated material handling system is commercially available, but must be tailored for specific applications. One such system,

Shred Pax Model AZ-160 (a low-speed 160 hp electrically-driven unit), has been successfully tested at the Savannah River Laboratory on noncombustible plutonium wastes generated from normal operations and decommissioning activity (Stewart and Charlesworth, 1986). Shred Tech Ltd. manufactures a variety of different models of size reduction equipment to handle municipal solid wastes, hazardous wastes, and nuclear wastes (Wheelwright, Bray, and Ryan, 1987). The low-speed equipment reduces noise, dust, and maintenance associated with traditional high-speed methods and should be considered for the proposed application. These systems can also be fully automated. A 50-hp unit appears to be adequate for the proposed process.

4.2.1.8 Solidification. The purpose of solidification is to immobilize the contaminants. This technology is extensively used in treating hazardous wastes and has also been applied to low-level radioactive wastes. A previous study using INEL hazardous and mixed wastes concluded that solidification is an effective method to treat these wastes, and the final product complies with applicable land disposal restrictions. The waste samples used in the study contained both metals and LLW. Solidification reagents successfully tested in this study include cement, cement-silicate, and Envirostone.

A mechanical/manual grout preparation and drum fill system has been demonstrated at PREPP. The system has the capacity to produce 8.5 t/d of cemented waste. An automated cement solidification system and a materials handling system have also been developed and demonstrated to solidify 55-gal drums at the rate of 6 drums/h at another DOE facility (West Valley in 1985).

Solidification is a well-developed and commercially available technology. The type of reagent to be selected will depend on the waste matrix and composition. Treatability studies will be required to select solidification reagents and optimize mix ratios before commercial operations.

4.2.2 Program Implementation Risks

This section identifies major concerns associated with program implementation assuming that the Pyrolysis and Acid Leach With Plutonium Extraction System is selected. Furthermore, the risk of accomplishing the

program objectives is qualitatively characterized. A summary of results and major areas of concern is shown in Table V-4-1. Program mission and objectives are given in Volume II.

4.2.2.1 Performance Objectives. Baseline cleanup standards for SDA pits and trenches at RWMC cannot be established until an ROD pursuant to the CERCLA process is reached. These standards will be derived ARARs under CERCLA, standards set by risk assessments, and the State and local statutes. Since no specific requirements have been formally established at this time, it is assumed that the major ARARs for this system will be RCRA rules, the appropriate NRC regulations and guides, and DOE regulations and Orders.

In the Pyrolysis and Acid Leach With Plutonium Extraction System, the major uncertainties listed below have been identified as areas of concern in the achievement of the performance objectives:

- Effectiveness of the pyrolysis process in areas of pyrolysis temperature control, adequate removal of fixed carbon before acid leach, and heat transfer rates for indirect heating mode. The heart of the system is a pyrolysis unit. The pyrolysis proposed for this application is a hearth-type vertical retort operated at a minimum temperature of 1000°F under slight negative pressure. The pyrolyzer must be indirectly heated to keep the size of the off-gas small. At the same time, the fixed carbon in the char must be burned off after pyrolysis using enriched oxygen or air to limit the volume of combustion products generated and facilitate Pu extraction in the acid leach step. Pyrolysis units have been successfully operated on wood and dry agriculture waste at flow rates larger than those anticipated in this process. However, some DT&E will be required to identify whether pyrolysis temperature can be controlled and the fixed carbon adequately removed before acid leach. Tests will also be required to ascertain heat transfer rates for indirect heating mode. These tests will indicate whether or not indirect heating is practical or if some form of direct heating is essential.

Table V-4-1. 3-EB-6 summary of program implementation risks and major areas of concern

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> Effectiveness of pyrolysis process in temperature control, removal of fixed carbon prior to acid leach, and heat transfer rates Ability to define characteristics of char Ability to control pyrolysis temperature Fume incinerator trial burn for operability & environmental compliance Design maturity of the acid leach process Availability of commercial scale CEPD dissolver Alpha cell confinement of radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events 	<ul style="list-style-type: none"> Ability to define and mitigate Pu-contaminated material safety concerns Ability to define and mitigate radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events Ability to define postulated accident events for thermal desorber process 	<ul style="list-style-type: none"> Low public support of thermal processes 	<ul style="list-style-type: none"> Prolonged pyrolysis and fume incinerator DT&E to confirm process applicability and regulatory compliance Prolonged pyrolysis DT&E Prolonged DT&E in definition of char characteristics Prolonged DT&E to develop a commercial scale CEPD process Prolonged, DT&E of the solidification unit regulatory compliance Prolonged DT&E, design, and construction of alpha cells Prolonged DT&E, design, and construction of remotely operated mechanical equipment 	<ul style="list-style-type: none"> Cost of pyrolysis, acid leach, and solvent extraction unit operations cannot be defined until DT&E is complete Uncertainties in defining cost of the solidification unit operations Alpha cells in TRU waste environment is a first-of-a-kind design Use of remotely operated mechanical equipment on TRU waste is a first-of-a-kind application

High

Moderate

High

Moderate

High

Table V-4-1. (Continued)

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> • Potential jamming and maloperation of complex mechanical devices and becoming a choking point 				
<ul style="list-style-type: none"> • Dust control during operations in the alpha cells 				
<ul style="list-style-type: none"> • Dust control and equipment decontamination & maintenance, requirements could preclude application of commercially available equipment 				
<ul style="list-style-type: none"> • Solidification process demo compliance with rules and regulations 				
High	Moderate	High	Moderate	High

- Adequate definition of char characteristics so that a suitable pyrolysis unit can be designed. Two pyrolysis units have been considered for the proposed application. One unit will remove volatile material. The char from this unit will be fed into the second unit in which hot enriched oxygen/air is passed concurrently to burn off the fixed carbon. Alternatively, the second unit could be a fluidized bed unit. Both units are to be maintained at 1000-1200°F. Because the effective combustion of carbon will depend on the ability of the oxygen to contact the carbon in the char, the characteristics of the char must be known before a suitable unit can be designed.
- Ability to control temperature during pyrolysis. Pyrolysis temperature control is important because temperatures higher than the required process control temperatures could incorporate plutonium in the silica matrix and affect acid leaching of Pu dioxide. Although the bulk temperature can be controlled in the second pyrolysis unit, the local temperature could exceed 1500°F. Consequently, some DT&E is required.
- Performing fume incinerator trial burn to determine operating conditions for obtaining environmental permits compliance. The trial burn as a part of the requirements would also demonstrate that the equipment with the applicable controls can be safely operated.
- Design maturity of the acid leach process. The acid leach is to be performed using the CEPOD process. This process has been successfully demonstrated on a pilot-plant scale using incinerator ash from the Rocky Flats Plant. For this demonstration, the fixed carbon in the ash was burned off as a feed preparations step. An excessive amount of carbon product in the char could reduce leaching efficiently by reducing the opportunities for the acid and the silver catalyst from contacting plutonium.
- Availability of commercial-scale CEPOD dissolver process. The maximum available size of the CEPOD dissolver is an eleven-liter

dissolver that can process up to 2 kg/h of Pu. A commercial electrolyte cell will have to be designed for the anticipated scale of operation; no such cell is available. The nature of char is also uncertain. The presence of chlorides in char should increase silver consumption in the process. The char may have to be pre-washed with nitric acid to remove chloride. A commercial-scale CEPD process should also be included. Thus, some bench-scale and pilot-scale DT&E will be necessary to generate design data for a commercial system.

- Solvent extraction is a well-known process; however, there may be a need to explore alternative methods (e.g., ion exchange) as an alternative to conventional solvent extraction to improve overall process efficiency.
- Solidification processes require specific formulations designed to provide longevity, low leachability, and LDR compliance. These processes are sensitive to the materials being treated. Because of insufficient data on the input waste characteristics, there are uncertainties regarding the effectiveness of the proposed solidification unit operations.
- Alpha cell designs for normal and postulated accidents. Alpha cells will be needed to contain Pu-contaminated dust and any radioactive, hazardous, toxic, and volatile gases that may become airborne during the waste handling and processing operations. This protection will have to be provided in normal and postulated accident events (e.g., a fire).
- Using commercial equipment in an alpha cell environment and providing ease of decontamination for maintenance. Several of the waste handling operations will use existing technologies that will have to be adopted for use in an alpha cell environment. This requires remote operation and ease of decontamination for maintenance.

- Potential jamming and maloperation of the complex mechanical components. Any of these unit operations could be a potential choke point because of limited prior knowledge of waste streams and the high throughput requirements.
- Large and complex ventilation and filtration systems to control dust during operations in the alpha cells.
- Unreliable operation of some of the equipment in a dusty environment. Dust control in an alpha cell environment and equipment decontamination requirements before maintenance could become limitations on the use of commercially available equipment. DT&E efforts could become more extensive than estimated.

Based on the above discussions, it is believed that the overall risk associated with achieving the performance objectives is high.

4.2.2.2 Health and Safety Objectives. The key health and safety objectives for the Buried Waste Program are to (a) identify the hazards of the remedial action operation, and (b) provide measures to eliminate, control, or mitigate identified hazards. In this system, major areas of uncertainty are

- Ability to define and mitigate criticality concerns. The key assumption of the overall process is that the concentration of Pu in the wastes is so small that criticality will not be attained in any of the unit operations. The risks associated with this assumption can be somewhat mitigated by running most of the units in a batch mode and performing a nondestructive assay of each batch feed for Pu concentration.
- The inability to define postulated accident events (such as fire and unforeseen release of toxic/hazardous material) for the alpha cells and provide mitigation measures to satisfy RCRA, NRC, and DOE requirements. The unit operations associated with opening drums provide unique safety concerns regarding potential for release of toxic, hazardous, and volatile gases.

The health and safety uncertainties are largely due to the inability to characterize the incoming waste. DT&E of characterization could provide a better confidence level. It is believed that using remote handling equipment and conducting operations inside alpha cells will enhance the mitigation measures for a majority of the normal and postulated events. This approach reduces the risk associated with achieving the health and safety objectives. At this stage of the system modeling, it is believed that the overall risk is moderate.

4.2.2.3 Institutional Objectives. A key institutional objective is to involve the public as required by CERCLA and NEPA in the process of selecting a remedial action for the Buried Waste Program. The system is based on using a pyrolysis process in conjunction with a fume incinerator. Low public support for these processes is anticipated. Hence, it is believed that the risk associated with achieving the institutional objective is high.

4.2.2.4 Schedule Objectives. The objective of the Buried Waste Program schedule is to reach approval for Title II start by mid 1999. This is based on the assumption that an ROD will be reached by the end of FY 2001. The schedule objective for completion of the Buried Waste Program remedial action is by FY 2019. The following major uncertainties in achieving these objectives have been identified:

- Pyrolysis and fume incinerator unit operation DT&E work (needed to confirm the process applicability and regulatory compliance) could be prolonged.
- Prolonged DT&E of the pyrolysis process in areas of pyrolysis temperature control, adequate removal of fixed carbon before acid leach, and heat transfer rates for indirect heating mode.
- Prolonged DT&E in the definition of char characteristics and temperature so that a suitable pyrolysis unit can be designed.
- Prolonged DT&E to develop a commercial-scale CEPD process.

- Prolonged DT&E of solidification processes to define specific formulations providing longevity, low leachability, and LDR compliance.
- DT&E of equipment reliability operating in dusty environments could become more extensive than estimated.
- The alpha cells are relatively complex first-of-a-kind structures and could be subject to prolonged design and construction. However, with advanced planning, uncertainties in achieving schedule objectives could be reduced.
- Prolonged DT&E involving design and construction of remotely operated mechanical equipment for sorting, conveying, size reduction, etc. Application of a majority of this equipment for TRU waste is a first-of-a-kind application. Again, with advanced planning, uncertainties regarding achievement of schedule objectives can be reduced.

It is believed that there is adequate time to resolve the above uncertainties and achieve the goals within the timeframe allowed by the schedule objectives. Accordingly, schedule risk is believed to be moderate.

4.2.2.5 Cost Objective. Assessment of the cost objective is a qualitative characterization based on the uncertainties involved in defining a reasonably accurate cost estimate for the system. Some of the major uncertainties are presented below:

- The pyrolysis, leaching, and solvent extraction unit operations are first-of-a-kind processes. Reliable cost estimates cannot be developed until DT&E of the appropriate unit operations is completed.
- Uncertainties in defining the cost of the solidification unit operations, primarily from regulatory compliance uncertainties, are anticipated.

- The use of an alpha cell in the given waste processing environment is a first-of-a-kind design and could be subject to cost overruns from prolonged design development. Major areas of uncertainty are (a) the extent of design features needed for operating in a dusty environment, (b) providing safety for postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material), and (c) satisfying RCRA, NRC, and DOE requirements. Currently, the limited information available on waste characteristics contributes to these uncertainties.
- Use of remotely operated mechanical equipment for container opening, sorting, size reduction, and handling of TRU waste is a first-of-a-kind application. Cost uncertainties are anticipated until design, based on DT&E, is well into maturity.

Based on the above discussions, the cost risk is believed to be high.

4.2.3 Unit Operations Pro and Con Analysis

This section addresses the pros and cons of the individual unit operations of the system under consideration and highlights any weaknesses identified.

4.2.3.1 Sort. A manipulator sort is recommended for the proposed system. The chief advantage of the manipulator sort is its ability to handle a wide variety of wastes. Materials that appear suspect can be manually picked up and set aside. In addition, the technology is proven and commercially available. Manipulator sorters require relatively less maintenance and have been used widely in the nuclear industry. However, manipulator sorters could slow down the waste processing rate. They are not easy to use for extended time periods. This disadvantage can probably be overcome by providing adequate relief for operators. No problems are anticipated in interfacing the sort unit with the shredder or the pyrolysis unit.

4.2.3.2 Pyrolysis. The main advantage of the recommended design for the pyrolysis unit is its simplicity and low-temperature operations. A hearth-

type pyrolytic retort is relatively simple to construct, and many such units have been constructed and operated in the past to process wood and agricultural wastes. Operating the unit under slight negative pressure will prevent material from leaking out. The low temperature of operations is likely to reduce the chances of plutonium from being incorporated into the silica matrix, especially when processing soils. The indirect heating of material inside the pyrolysis chamber will minimize the off-gas volume and reduce the size of the fume incinerator.

The biggest drawback with the recommended pyrolysis unit is the lack of performance and design data on radioactive wastes. Proper operation of this unit is vital to the separation of plutonium from the resulting char. The goal is to remove all of the volatiles, fixed carbon, and moisture in the vapor phase, leaving a char amenable to acid leach. The lack of performance design data can be overcome by research and testing using surrogate materials with characteristics similar to the types of wastes to be processed.

4.2.3.3 Fume Incinerator. A cyclonic fume incinerator offers several important advantages: better mixing and temperature uniformity, higher destruction and removal efficiency, a wider operating range, greater flexibility to variations in waste properties, and molten-ash discharge capability. The disadvantage with the fume incinerator is that it is capital intensive and requires a long lead-time (approximately 12 to 18 months) for construction and delivery. The capital and operating costs can be substantially reduced by incorporating efficient heat recovery systems into the design.

4.2.3.4 Off-gas Treatment. The proposed off-gas treatment system is a combination of wet and dry acid gas and particulate removal technologies. The key component in the wet section is a high energy venturi scrubber functionally supported by an off-gas quencher and entrained liquid removal devices. This wet system is optimized for removal of acid gases and most entrained particulates in the exhaust system. The biggest advantage of the proposed off-gas treatment system is that each individual piece of equipment that constitutes the system is proven and commercially available.

Despite the well-developed state-of-the-art technology, some problems could be encountered in the operation of the off-gas treatment system. The quencher could be a source of particulate generation and increase particulate loading on prefilters. Flooding the quencher with the scrubber solution and removing particulates from the scrubber solution could be difficult. These potential problems have been identified in the PREPP experiments and can be alleviated by adequately addressing the concerns during the design phase.

4.2.3.5 Acid Leach. There are many advantages in using the CEPOD dissolver for the acid leach step. First, the generation of hydrogen gas has been critically examined during tests and found to be insignificant when the catholyte acid concentration is maintained above a specific level. Second, the rate of PuO_2 dissolution is considerably faster (about 15 times) than the conventional HF/HNO_3 technology. Third, the process is practically independent of pyrolysis temperature. However, very low pyrolysis temperatures could produce a large concentration of fixed carbon in the char and interfere with the leaching process. Finally, the CEPOD dissolver design eliminates the potential for criticality.

The biggest disadvantage of the CEPOD dissolver is that it is still under development. Plant-scale prototype dissolvers have been designed, fabricated, and successfully tested. Yet the characteristics of the materials tested and the rates at which they were tested are not identical to the proposed application. The compatibility of the acid leach system with the pyrolysis unit is the key element to the successful operation of the process. Because of the lack of performance data, the uncertainties associated with the interface between these units can be mitigated only through research and development and testing.

4.2.3.6 Solvent Extraction. Solvent extraction is a well-established technology. Despite its wide-spread use in the nuclear industry, each solvent extraction unit must be custom designed and constructed for specific applications. Solvent recovery is usually the key element in the commercial viability of the solvent extraction step. However, for the proposed application, plutonium separation from the waste is the goal rather than recovery (for reuse). Consequently, solvent recovery would be less critical.

Thus, in the overall analysis, solvent extraction should be relatively simple to design, install, and operate and should be expected to interface well with the acid leach step.

4.2.3.7 Shredder. The main advantage of the low-speed shredder is its ability to shred a wide variety of waste materials. The shredder can also reverse itself automatically if material gets stuck in between the cutting teeth. The low speed minimizes noise pollution. In addition, the type of shredder recommended for the proposed application has been tested on TRU wastes at the Savannah River facility. The disadvantage with the shredder is that it is not a maintenance-free piece of equipment. Because of the unknown nature of materials to be processed, significant allowance must be made for equipment downtime; this could be reduced through preventive maintenance. The shredder is expected to interface well with the sorter and the solidification unit.

4.2.3.8 Solidification. The advantage of solidification is that it is a proven and commercially available technology. Solidification immobilizes hazardous constituents but does not destroy them or reduce their toxicity.

The disadvantage with this unit operation is that the addition of solidification agents results in an increase in waste volume. The final product must eventually be repackaged and land disposed. Consequently, the environmental liabilities associated with such disposal are not eliminated. Despite these stated disadvantages, solidification is an effective tool and has been established by EPA as the best developed available technology for treating heavy metals in solid matrix.

4.2.4 Unit Operations Lead-Time Estimates

Table V-4-2 shows an estimate of lead-time for each unit operation. This bar chart estimate is based on information provided by vendors supplying the key pieces of equipment and conversations with individuals involved in the development of specific units. The construction of the commercial CEPD dissolver (acid leach unit) will most likely control the schedule for bringing the plant on-line. No commercial vendor has yet been identified. The

Table V-4-2. DT&E assessment summary for the Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6)

[illegible]

pyrolysis unit, the fume incinerator, and the off-gas treatment system all have long lead-times. The bulk of this lead-time is required for obtaining environmental permits for construction and operation.

The unit operations involved in this process are based on available state-of-the-art technology. Although some research, development, and demonstration are anticipated for some unit operations, a separate demonstration test for the system as a whole is not required. The integration of the unit operations can be tested during plant start up. The implementation risks associated with each unit operation to meet overall project objectives are discussed in detail in Section 4.2.2.

4.2.5 Rough Order of Magnitude Cost Estimates

This section presents an ROM cost estimate for the proposed system. In most cases, these costs are based on verbal quotations from vendors. Because the process conditions are not clearly defined, vendors were able to provide only a range of estimated costs. Vendors also provided estimates of floor space for their respective equipment. Although they are approximate, these cost estimates should be sufficient to provide useful insight into anticipated costs for the system. Errors in the estimated equipment cost are less critical because the bulk of the capital costs will depend on the facility layout (square feet of floor space and square feet of alpha cell space). Research and development costs are based on best estimates of work needed to bring specific techniques to commercial application for RWMC plutonium-contaminated buried wastes.

The assumptions made in preparing these cost estimates include the following:

- Cost to construct alpha cell is \$1000/ft²
- Cost to construct other building structures is \$350/ft²
- One year consists of 240 days with 24 h/d

- Availability of equipment is 70%
- Design capacity of each equipment is 25% over anticipated capacity
- Manpower costs are estimated at \$60/h
- Electricity cost is estimated at 3.5/kWh
- Constructor management cost is 17% of the total estimated direct and indirect costs
- Indirect cost is 26.5% of the estimated equipment cost
- Materials cost is 15% of the total estimated equipment cost
- Maintenance cost is 6% of the total estimated cost (Peter and Timmerhaus, 1990)
- Operating costs are calculated for 10 years
- The plant crew for each shift consists of eight operators, two health physics technicians, three maintenance engineers, one safety engineer, and one shift supervisor
- A contingency of 25% has been applied to the total estimated cost under each category of fixed cost (e.g., research and development, decontamination, and production costs).

Table V-4-3 gives a breakdown of ROM cost estimates for the system.

4.2.6 System Evaluation Results

This section presents an overall evaluation of the system involving pyrolysis and acid leach with plutonium extraction. In particular, the evaluation includes a discussion of the ability for the various unit operations to function smoothly as an integrated system. Specifically, the

Table V-4-3. Rough order of magnitude cost estimates (3-EB-6)^a

Cost Code	Cost Items	Normalized Cost (\$x1000)	Modified Cost (\$x1000)
1.0	Studies and bench scale cost		
1.1	Manpower costs during research	\$691	\$691
1.2	Equipment costs	\$120	\$120
1.3	Installation costs	\$25	\$25
1.4	Contingency	\$209	\$209
	Subtotal 1.0	\$1,045	\$1,045
2.0	Demonstration costs		
2.1	Manpower cost during construction	\$1,617	\$1,617
2.2	Design cost (30% of 2.5)	\$275	\$275
2.3	Inspection cost (7% of 2.5)	\$64	\$64
2.4	Project administration (10% of 2.5)	\$92	\$92
2.5	Construction cost		
2.5.1	Building structure costs	\$525	\$525
2.5.2	Equipment costs	\$200	\$200
2.5.3	Indirect (20.9% of 2.5)	\$192	\$192
	Subtotal of 2.5	\$917	\$917
2.6	Construction management costs (27.8% of 2.5)	\$263	\$263
2.7	Contingency	\$807	\$807
	Subtotal 2.0	\$4,035	\$4,035
3.0	Production construction costs		
3.1	Design cost (30% of 3.4)	\$6,478	\$19,652
3.2	Inspection cost (7% of 3.4)	\$1,512	\$4,585
3.3	Project administration (10% of 3.4)	\$2,160	\$6,551
3.4	Construction cost		
3.4.1	Building structure costs	\$16,125	\$50,837
3.4.2	Equipment costs	\$946	\$946
3.4.3	Indirect (20.9% of 3.4)	\$4,524	\$13,723
	Subtotal of 3.4	\$21,595	\$65,506
3.5	Construction management costs and construction management reserve (26.5% of 3.4)	\$6,198	\$18,800
3.6	Contingency (25% of 3.1 through 3.5)	\$9,485	\$28,774
	Subtotal 3.0	\$47,427	\$143,868
	Total Capital Cost (1.0, 2.0, and 3.0)	\$52,508	\$148,948
4.0	Annual operating and maintenance costs		
4.1	Operating costs	\$15,552	\$15,552
4.2	Utility costs	\$14	\$14
4.3	Material costs	\$142	\$142
4.4	Maintenance costs	\$57	\$57
4.5	Contingency	\$3,941	\$3,941
	Subtotal 4.0	\$19,706	\$19,706
TOTAL	10 Years Operating and Maintenance Costs		\$197,061

a. Does not include the appropriate subsystem costs (see Volume VII for subsystem costs).

areas addressed are identification of major system considerations, a qualitative judgment rating of performance measurements identified in Section 2, a summary of research and development needs, and an overall recommendation for the system.

4.2.6.1 Identification of Major System Considerations. In evaluating the system as a whole, the following questions identify the major considerations:

- Does the system use state-of-the-art technology?
- Is the technology currently available and demonstrated?
- What is perceived as the weakest link in the system design?
- Is the system safe to operate?

The answers to these questions will provide an indication of the technical viability of the system and will also point to research and development needs. In general, all of the eight major unit operations in the proposed system use state-of-the-art technology. The acid leach step using the CEPOD dissolver appears to be the only exception where some innovative technology is involved. Each of these unit operations is currently available and individually demonstrated. These operations are not conceptual, and considerable performance data are available from operations on other materials. The weakest link in the entire system design is the lack of specific performance data on the type of waste materials that will actually be processed through the system. The success of the design to meet specific performance objectives will depend largely on the availability of such data. The lack of such data is not an unusual or insurmountable problem. The necessary data can be generated through testing and research and development.

Throughout the analysis of the system, Ebasco has assumed that the concentration of plutonium in the wastes will be so small that criticality will not be achieved at the proposed processing rates. The validity of this assumption is fundamental to the safe operation of the system.

4.2.6.2 Qualitative Judgment Rating. Table V-4-4 presents a qualitative rating of measurable parameters for each unit operation constituting the system. Each unit operation has been assigned a value between 0 and 10 based on Ebasco's judgment of how the unit operation rates with respect to a specific parameter.

The waste reduction parameter does not apply to sorting and shredding. These unit operations merely assist in making the waste amenable to further processing and, as such, do not contribute to an increase or decrease in the final waste volume. Solidification is always accompanied by a volume increase because of reagents added. Therefore, the success of the system in terms of waste reduction will depend on whether or not the increase in waste volume from solidification is offset by an overall reduction in the TRU waste volume. The ratings presented in Table V-4-4 are based on Ebasco's best engineering judgment and reflect the level of confidence in the system to accomplish the specified objectives. The level of confidence is high, but some areas need additional research to improve the chances for the system to perform as expected.

4.2.7 Summary of Demonstration, Testing, and Evaluation Needs

Table V-4-5 summarizes the DT&E needs for the system. The program must be designed to answer the questions below.

4.2.7.1 Pyrolysis Unit.

- Can the necessary heat be supplied to the waste through indirect heating?
- Will the heat transfer rates be adequate or will some form of direct contact heating be necessary?
- Can pyrolysis temperature be controlled in the 1000-1200°F range?
- Can the fixed carbon in the char be adequately removed by controlled combustion in the pyrolysis unit?

Table V-4-4. Rating performance measurables for the Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6)

	<u>Sort</u>	<u>Shredder</u>	<u>Solidification</u>	<u>Pyrolysis</u>	<u>Fume Incinerator</u>	<u>Off-gas Treatment</u>	<u>Acid Leach</u>	<u>Solvent Extraction</u>	<u>Total</u>
Timeliness	10	10	10	10	10	10	10	10	80
Availability	10	10	10	7	10	10	7	8	72
Completeness	10	9	10	7	10	8	7	7	68
Risk	10	9	10	8	10	8	8	8	71
Flexibility	9	9	10	9	9	7	7	7	67
Cost	9	9	9	8	8	7	7	7	64
Safety ^a	9	9	9	9	8	8	9	9	70
Waste Reduction	NA ^b	NA ^b	6	8	9	8	8	8	47
Complexity	<u>9</u>	<u>8</u>	<u>9</u>	<u>8</u>	<u>7</u>	<u>8</u>	<u>7</u>	<u>8</u>	<u>64</u>
Total	76	73	83	74	81	74	70	72	603

a. A key assumption is that criticality will not be a problem with any of the unit operations based on the concentration of plutonium in the waste.

b. These unit operations do not contribute to increased or decreased final waste volume.

Table V-4-5. DT&E needs for the Pyrolysis and Acid Leach with Plutonium Extraction System (3-EB-6)

<u>Unit Operations</u>	<u>DT&E</u>
Manipulator Sort	None
Shredder	None
Pyrolysis	Limited testing will be required during plant startup to ensure the unit functions properly Research heat transfer rates, temperature control, fixed carbon combustion, and criticality from geometry
CEPOD Dissolver	Obtain useful design data and optimize process conditions Integrate CEPOD dissolver operation with pyrolysis unit, establish char characteristics, determine need for char pretreatment, and generate performance data on real or surrogate waters Obtain design data for commercial scale dissolver and optimize process conditions
Solvent extraction	Explore alternative (e.g., ion exchange) to conventional solvent extraction technology Simplify operations and improve plutonium extraction efficiency
Fumes incinerator	Heat recovery systems and characterization of generated off-gas Properly design the off-gas treatment system and improve process operations
Off-gas treatment	Gaseous and particulate emissions control These data will be required for obtaining environmental permits
Solidification	Reagent selection, mix ratios, and analytical procedures for testing solidified product containing radioactive substances Develop protocols for proper operations

- Will the geometry of the pyrolysis unit present a criticality problem during waste processing?

4.2.7.2 Catalytic Electrolytic Plutonium Oxide Dissolution Dissolver.

- What design data are specifically needed to construct a commercial scale CEPOD dissolver?
- What characteristics are desirable in the char from the pyrolysis unit to ensure efficient plutonium extraction? Will the char require pretreatment before extraction?
- How will changes in process conditions in the pyrolysis unit affect the operation of the CEPOD dissolver?

4.2.7.3 Solvent Extraction.

- Can the efficiency of the solvent extraction technology be improved to extract plutonium from the CEPOD product?
- Is ion exchange a better alternative to solvent extraction for removing plutonium?

4.2.7.4 Fume Incinerator.

- What type of heat recovery system should be incorporated to improve overall operation efficiency?
- Will there be a significant amount of NO_x or SO_x generated that will require treatment?

4.2.7.5 Off-gas Treatment System.

- How effective is the off-gas treatment system in controlling gaseous and particulate emissions?

- Is the operation of the off-gas treatment system susceptible to changes in waste characteristics fed to the pyrolysis unit?

4.2.7.6 Solidification.

- What are the reagents to be added to accomplish immobilization of hazardous constituents?
- What is the optimum mix ratio to use for solidification?
- What analytical procedures will be used to ensure that the required treatment standards are met?

4.3 RECOMMENDATION FOR THE SYSTEM

In the overall analysis, pyrolysis and acid leach with plutonium extraction is a technically viable process. No system can be guaranteed to perform as designed without adequate testing. Although the individual unit operations for the proposed system are all based on proven and established technologies, none of them has been used specifically for the proposed application. Consequently, no precedence exists to make a performance-based recommendation. However, a subjective recommendation can be made based on the proven performance of these individual units on similar types of materials. The economic viability of the system will largely depend on the extent to which the system reduces the volume of TRU wastes and how well process conditions within each unit operation can be optimized and controlled to ensure smooth integrated operations. This can only be determined through testing.

5. MOLTEN SALT OXIDATION SYSTEM (3-BE-7)

The Molten Salt Oxidation (MSO) System (3-BE-7) includes all facilities, processes, equipment, and ancillary components required for the retrieval, processing, and packaging of TRU waste buried at RWMC. The system converts the incoming waste into a physical and chemical form that has reduced hydrogen generation potential and meets the EPA LDR requirements.

5.1 FUNCTIONAL AND OPERATIONAL REQUIREMENTS

5.1.1 System Description

MSO is comprised of three subsystems and several unit operations. They are the Retrieval Subsystem (S-BE-4), Soils Processing Subsystem (S-EB-2), Metal Decontamination and Sizing Subsystem (S-BE-1), and the unit operation housed within the Waste Receiving, Processing, and Packaging Facility.

The Retrieval Subsystem provides all the necessary processes and unit operations to retrieve and gross sort the buried waste. The Retrieval Subsystem and its related unit operations are described in Volume VII. Peripheral soil, bulk metal, loose material, and intact containers are four major output streams from the Retrieval Subsystem.

The peripheral soil output is transported via reusable containers to the Soils Processing Subsystem (S-EB-2). This subsystem has all the facilities and equipment needed for treatment and disposal of the contaminated soil. The Soils Processing Subsystem and its related unit operations are described in Volume VII.

The bulk metal output is containerized and transported to the Metal Decontamination and Sizing Subsystem (S-BE-1). This subsystem has all the facilities and equipment needed for treatment of the metal to meet LDRs and reduce hydrogen generation potential. The Metal Decontamination and Sizing Subsystem and its related unit operations are described in Volume VII.

Loose material and intact containers are transported to the Waste Receiving, Processing, and Packaging Facility. At this facility, the containers are opened and waste is removed and processed through a sorting unit. The sorting unit segregates the waste into metal and nonmetal streams. The nonmetal stream is sent to a size reduction unit. The metallic waste stream is sent to the Metal Decontamination and Sizing Subsystem (S-BE-1).

MSO requires pretreatment of the incoming waste. This is done by a size reduction unit that first reduces the size of the incoming waste objects and then performs a fine sorting operation. Two streams will result from this operation: soil and nonmetal waste. The soil is sent to the Soils Processing Subsystem (S-EB-2). The remaining nonmetallic waste is pretreated and prepared for processing by an MSO unit.

After preparation, the nonmetal waste stream is fed to the MSO vessels. The MSO vessels also receive sodium carbonate, which is used as the salt media in the MSO unit. The MSO process converts the organic and hydrogenated compounds into carbon dioxide and salt.

The MSO unit's major secondary product includes gaseous and liquid waste streams. The gaseous stream is treated by gas condensers, dryers, filters, and other applicable contamination removal techniques and discharged to the atmosphere. The liquid stream is treated to remove dissolved suspended solids. The treated liquid is discharged while the by-product (concentrated liquid and sludge) is sent to a waste solidification unit.

The MSO product discharged from the MSO vessel is washed and sent to the solidification unit. The liquid waste generated from the washing operation is sent to the liquid waste treatment unit for processing. The washed MSO product, along with the concentrated liquid waste and sludge generated from the liquid waste treatment unit, are mixed with a solidification agent and packaged into containers.

Each packaged waste container is processed through a radio-assay and a final certification process. At this point, the containers are certified either as TRU or LLW.

Certified containers are sent to an interim storage facility. Shipment of the containers is performed by taking them out of the interim storage area and loading them into transportation over-packs. Over-packs, mounted on a shipping vehicle, are used for offsite shipment and disposal.

Descriptions of the unit operations of the Waste Receiving, Processing, and Packaging Facility are presented below.

5.1.1.1 Incoming (Unprocessed) Waste Receiving and Opening.

- Unit operation summary: The receiving portion of the Waste Receiving, Processing, and Packaging Facility processes the incoming waste by unloading the incoming vehicle, providing surge storage of the waste contained in reusable containers, unloading the reusable containers, and uncapping, opening, and dumping the waste contained in the intact containers.
- Reusable containers: The retrieval waste (loose material and intact containers) will be placed in reusable containers designed for onsite transportation.
- Onsite transportation vehicle: An onsite transportation vehicle will be used to ship the reusable containers from the Retrieval Subsystem to the Waste Receiving, Processing, and Packaging Facility.
- Receiving, unloading, and surge storage: At the Waste Receiving, Processing, and Packaging Facility, the reusable containers will be unloaded from the incoming vehicles and placed in an interim storage area.
- Unloading of reusable containers: Reusable containers will be taken out of the storage area to the container opening and unloading unit operation. This unit operation removes the reusable container caps and empties its contents.

- Intact drum unloading: A drum unloading device will remove the intact drum caps and feed its contents to the sorting unit.

5.1.1.2 Reusable Container Decontamination. The empty reusable containers will be decontaminated, inspected, and sent back to the Retrieval Subsystem.

5.1.1.3 Sorting (Nonmetal/Metal).

- Unit operation summary: The sorting unit operation includes all facilities, supporting subsystems, and equipment that will be needed to sort metal objects from the incoming waste stream.
- Coarse sorting: Loose material and contents removed from the intact drums are conveyed to a sorting table (various sorting technologies such as vibratory tables and air classifiers may be used). The device will remove and separate out bulk metallic objects from the incoming waste stream. The bulk metallic objects will be fed to the Metal Decontamination and Sizing Subsystem. The remaining loose material and any gas cylinders will be processed through a fine sorting device.
- Fine sorting: The first sorting device will contain a separator to remove any remaining metal from the waste stream (various technologies such as magnetic separation devices may be used). The metal contents will be diverted to waste containers and transferred to the Metal Decontamination and Sizing Subsystem. The nonmetallic waste, primarily loose material, will be sent to the size reduction unit operation.

5.1.1.4 Size Reduction and Sort.

- Unit operation summary: The size reduction unit operation includes all facilities, subsystems, and equipment needed to convey the waste from the sorting unit operation, uncap and empty out drums

containing loose materials, and reduce the size of the incoming waste to facilitate the MSO operation.

- **Size reduction:** Incoming waste streams from the sorting unit and waste containers containing combustibles, noncombustibles, soil, and sludge will be dumped into a size reduction unit (e.g., shredder). The shredded waste will be transferred to the fine sorting device.
- **Fine sorting:** The fine sorting device will contain a separator to remove soil from the waste stream (various technologies such as air classification and screening may be used). The soil will be diverted to waste containers and transferred to the Soils Processing Subsystem. The remaining waste, primarily loose material, will be sent to MSO.
- **Sludge drum unloading:** A drum unloading device will remove sludge drum caps and feed the content to the size reduction unit.

5.1.1.5 Molten Salt Oxidizer.

- **Unit operation summary:** The MSO unit operation includes all facilities, subsystems, and equipment needed to convey the waste from the size reduction unit to the MSO pretreatment subsystem; inject the waste to the MSO vessel; store, feed, and heat sodium carbonate to the MSO first stage vessel; collect, store, and feed the molten salt product to the solidification unit; collect and transfer gaseous waste to the off-gas treatment unit; and collect and transfer liquid waste to the liquid waste treatment unit.
- **Pretreatment:** The waste pretreatment unit will entrain the waste with air and inject it into the first stage molten salt vessel below the molten salt liquid surface.
- **Sodium carbonate storage and feed:** The salt used for the MSO operation will be a low melting temperature eutectic of potassium/sodium carbonate. The sodium carbonate storage and feed

unit will provide a receipt of salt from bulk shipping vehicles, a three-month storage capacity for the bulk material, a seven-day operation capacity day tank, and salt transfer and injection. Salt will be injected into the MSO first stage vessel.

- MSO first stage vessel: The MSO first stage vessel will receive waste and sodium carbonate. Electric heaters are provided to heat the refractory-lined oxidation vessel during start up and to provide additional heat if the heating value of the feed is insufficient. The first stage will be operated at an oxygen deficient atmosphere to promote pyrolysis of the combustible material. Chloride compounds in the feed, such as chlorinated organics and polyvinyl chloride, will react with the salt to form potassium/sodium chloride, which is retained in the melt. Noncombustibles and ash will also be retained in the melt.
- MSO second stage vessel: The gaseous pyrolysis products will go to the second stage molten salt oxidizer operating at 1652°F, where additional air is fed to complete oxidation of combustible gases and destruction of hazardous chemicals. The off-gas will go to the off-gas treatment system.
- Product collection and feed: The resultant salt and ash will be drained from the oxidation vessels when the ash buildup is excessive or when the salt has been consumed by reaction with halogens. The salt and ash mixture will be washed to recover carbonate salts for reuse in the oxidizers. The remaining salt and ash, which contain the radionuclides from the waste material, will be transferred to the solidification area. Liquid waste will be transferred to liquid waste treatment.

5.1.1.6 Off-gas Treatment.

- Unit operation summary: The off-gas treatment unit operation includes all facilities, subsystems, and equipment needed to transfer gaseous waste from the MSO vessel discharge point to the

treatment unit, treat gaseous waste to remove particulates and moisture, and sample and measure gas radiation concentration before discharge to ensure compliance with the discharge criteria. The concentration of radioactive particulates and gaseous pollutants in the MSO off-gas is expected to be minimal because the molten salt effectively retains these materials. The off-gas, consisting primarily of air, carbon dioxide, and water vapor, will be treated to condense water and remove any particulates and volatile compounds. Various technologies, such as filtration and condensation, may be used.

- Dryers/condensers: The gaseous waste will pass through a rough moisture separation step and then through condensers before passing through the dryer. The condensed liquid will be sent to the liquid waste treatment unit operation.
- Filtration: The dried off-gas passes through HEPA filters before release to the atmosphere.
- Sampling and monitoring: The clean off-gas will be sampled before being discharged to the atmosphere. A radiation monitoring device will measure the concentration of the radionuclides in the sample.

5.1.1.7 Liquid Waste Treatment.

- Unit operation summary: The liquid waste treatment unit operation includes all facilities, subsystems, and equipment needed to receive and store liquid waste from the MSO product feed and the off-gas treatment units, treat liquid waste to remove suspended and ionic impurities, reduce the volume of waste to be disposed, transfer concentrated waste to the solidification unit, discharge the treated liquid waste to the environment, and monitor the radioactivity concentration of the treated liquid waste before discharge.
- Receiving: The incoming liquid waste will be transferred by pumps to the receiving tanks.

- Treatment: Liquid waste will be treated to remove suspended and ionic impurities to meet discharge criteria. Filtration, demineralization, evaporation, precipitation, and neutralization are available treatment methods. The treated clean liquid that meets the discharge regulations will be released. The remaining concentrated liquid or sludge will be transferred to the solidification unit.
- Sampling and monitoring: The treated liquid will be monitored for radioactivity before being discharged to the environment. A radiation monitoring device will accomplish this function.

5.1.1.8 Solidification.

- Unit operation summary: The solidification unit operation includes all facilities, subsystems, and equipment needed to receive and store concentrated liquid waste, molten salt, ash, and sludge from the MSO liquid waste treatment and off-gas treatment units, receive and store bulk shipments of solidification agents, inject solidification agents and waste into a mixing device, inject the mixture into waste containers, cap the filled waste containers, allow curing of the containers filled with solidified waste, smear (swipe) test the container surface to determine contamination, and, if necessary, decontaminate the container to remove surface contamination, transfer the filled containers to radio-assay and certification station, and collect and treat the flush water generated during the system flush and decontamination operations.
- Waste receiving: The incoming concentrated liquid waste, sludge, ash, and molten salt will be transferred by pumps to the receiving tanks and silos.
- Solidification storage and feed: The agent used for solidification can be cement, polymer, or bitumen. The solidification agent storage and feed unit will provide receipt of the solidification agent from bulk shipping vehicles, a three-month storage capacity

for the bulk material, a seven-day operation capacity day tank and solidification agent transfer, and feed devices. The solidification agents will be metered into the mixing device.

- Mixer: The mixer will mix the waste with the solidification agent. The mixture will be poured or injected into containers. The mixer will include features for flushing. The flush water will be collected in tanks and treated for reuse. Concentrated sludge will be solidified.
- Filled container handling: Filled containers will first be set aside for a curing period (24-48 hours). The containers will then be capped, smear (swipe) tested to determine surface contamination, and washed down if necessary. The container will be sent to the assay/certification station. The liquid waste from the container wash down operation will be discharged into the flush water storage tanks.

5.1.1.9 Assay/Certification.

- Unit operation summary: The assay/certification unit operation includes all facilities, subsystems, and equipment needed to determine radioactivity, physical properties, and parameters to classify and certify that the waste package is in compliance with the transportation and disposal regulations and provide interim storage for the packaged waste.
- Radio-assay: Packaged waste (i.e., filled waste containers meeting the ultimate waste form requirements) will be examined by radio-assay devices to allow classification of waste in accordance with the U.S. Department of Transportation (DOT), DOE, and NRC transportation and disposal requirements. Containers will also be weighed. Various devices, such as passive neutron counting (PAN) and gamma spectroscopy (SGS) instruments and load cells, may be used. Data from the examination will be logged and recorded for each container. The radio-assayed containers will first be

classified either as LLW or TRU waste. LLW containers will be further classified according to the DOT and NRC requirements and transported to a labeling and LLW certification station. At this station, they will be examined for compliance with shipping and LLW disposal site requirements. Containers classified as TRU will be transported to the TRU certification area.

- **Certification:** As a minimum, each LLW and TRU container will be examined by a nondestructive examination and nondestructive assay by a real-time radiography (RTR) device. The containers will also be smear tested again to determine the extent of any exterior contamination. If the drums are contaminated, a water decontamination process will remove surface contamination. The clean containers will be transferred to an interim storage area.

5.1.1.10 Interim Storage. The system will have a six-month capacity to store TRU and LLW packaged and certified waste containers (e.g., filled waste containers meeting the ultimate waste form requirements).

- **Shipping:** The certified waste packages will be transferred from the storage area to the loading station. At this station, the waste packages will be loaded into shipping over-packs, mounted on transportation vehicles, and shipped to the disposal site.

5.1.2 System Boundaries

5.1.2.1 Subsystems. The Molten Salt Oxidation System (3-BE-7) includes the Retrieval Subsystem (S-BE-4), Metal Decontamination and Sizing Subsystem (S-BE-1), and Soils Processing Subsystem (S-EB-2).

The physical boundaries for the above subsystems are shown in Volume VII. The boundaries for other unit operations of the Molten Salt Oxidation and Packaging System are given below.

5.1.2.2 Waste, Receiving, Processing, and Packaging Facility.

- Physical boundaries: The physical boundaries include the following:
 - The Waste Receiving, Processing, and Packaging Facility buildings will be located on a 5-acre site. The facility boundary is at the site perimeter fence.
 - Building foundations include preparation of the site.
 - The loading dock is the boundary for the input waste streams.
 - The shipping dock is the boundary for the output streams from the facility. Shipments will be distributed as follows:
 - (a) packaged LLW and TRU waste shipments to disposal facilities, (b) non-radioactive solid waste shipments to municipal disposal facilities, and (c) non-radioactive chemical hazardous waste to off-site chemical disposal facilities
- Utilities: The Waste Receiving, Processing, and Packaging Facility will require services from the service water system and electrical power supply. The system boundaries with the utilities are
 - Service water shut-off valves located at the site fence
 - Four kV power supply pole located at the fence. Other utilities such as service air, emergency power are a part of the Waste Receiving, Processing, and Packaging Facility.
- Environment: The Waste Receiving, Processing, and Packaging Facility will have an off-gas discharge stack, building ventilation system discharge, treated liquid waste evaporation pond, and sanitary drain field.

5.1.3 Process Functional Diagram

5.1.3.1 System Specific Assumptions.

- The waste volume increases by 10% during packaging
- Solidification process increases the volume by a factor of two
- All soil must be removed from the waste stream before entering the MSO vessel
- Off-gas from the molten salt oxidation process is relatively inactive; therefore, particulate filtration is adequate to treat the off-gas
- Six-month storage capacity for the packaged waste
- The waste volume is decreased by a factor of two during size reduction.

5.1.3.2 Process Functional Diagram. The mass flow rates and energy requirements for the MSO process are shown in Figure V-5-1.

5.1.4 Facility Description

5.1.4.1 General Arrangement. General arrangements for the Waste Receiving, Processing, and Packaging Facility are shown in Figure V-5-2.

5.1.4.2 Surge Storage Requirements. Storage capacity will be provided for the incoming reusable containers and the final packaged containers. The storage area will contain a material handling system, fire protection, ventilation, and monitoring per RCRA.

Figure V-5-1. Process functional diagram for the Molten Salt Oxidation System (3-BE-7).
Note: Mass flow balance does not show the input process additives.

PROCESS DEVELOPED BY ING MOLTEN SALT TO TERIALS PERIODIC AN BE PACKAGED FOR IN (SOLIDIFICATION) NS REPORTED ATED TO MEET	DESCRIPTION RETRIEVE, SORT, PACKAGE AND SEND TO TREATMENT FACILITY, SORT AND TREAT SOILS AND METALS. TREAT REMAINING MATERIAL IN A MOLTEN SALT OXIDATION PROCESS, AND SOLIDIFY SALT, ASH AND LIQUID FROM OFF GAS AND LIQUID TREATMENTS	3-BE-7	FINAL WASTE FORM REQUIREMENT		
			CREATE WASTE FORM THAT MEETS THE LDR REQUIREMENTS AND RESTRICTS THE HYDROGEN GENERATION FROM METALS.		
		EG&G SYSTEM DESIGN STUDY MOLTEN SALT OXIDATION & PACKAGING SYSTEM FLOW DIAGRAM
		JOB NO 20996-005	FIGURE 2 - 1	DATE 4/3 /91

Figure V-5-2. General arrangement for the Molten Salt Oxidation System (3-BE-7).

WASTE RECEIVING, PROCESSING AND PACKAGING FACILITY
MOLTEN SALT OXIDATION AND PACKAGING SYSTEM
(3-BE-7) - GENERAL ARRANGEMENT

JOB NO.
20996-005

FIGURE
2-2

DATE
2/11/91

5.1.5 System Design Requirements

5.1.5.1 Functional Requirements. The MSO System retrieves buried TRU waste and peripheral soil from RWMC. The TRU waste and peripheral soil is classified, sorted, and processed within the facility. The soil is treated for compliance with the LDR requirements. The TRU waste is then converted to a form that has reduced hydrogen generation potential and meets the LDR requirements.

5.1.5.2 Performance Requirements. The MSO System will be designed to process and package buried waste from the RWMC over a ten-year period. The operational availability of this system is 24 h/d, 5 d/wk, and 70% plant availability during operation, operating 240 d/yr. The packaged TRU waste will meet LDR requirements and the system will have the ability to sort and segregate LLW and TRU waste containers. The system will have the ability to separate metal objects from the waste stream; it will minimize the volume of the waste as much as possible. The system will have the ability to incinerate noncombustibles, combustibles, and sludge process streams. The impact of this licensable system operation on the environment will be minimal. The effect of the system operation on the worker and public health and safety will be minimal. It will have high reliability, operability, and maintainability factors plus the capability to receive waste types having a diverse set of characteristics. The system will have the ability to oxidize and solidify combustibles, noncombustibles, and sludge.

5.1.6 Interface Requirements

The F&OR sections for the Retrieval Subsystem (S-BE-4), Metal Decontamination and Sizing Subsystem (S-BE-I), and Soils Processing Subsystem (S-EB-2) identify the interface requirements for these subsystems. The following interface requirements are those of the other unit operations of the waste solidification and packaging system. The flow rate values for the input, output, and intermediate points are given in the process functional diagram, Figure V-5-1.

5.1.6.1 Support to Other Systems (Output). The Waste Receiving, Processing, and Packaging Facility provides output to the following:

- Low-level waste disposal consisting of the output of molten salt oxidation, sludges, and solidified wastes
- Metal Decontamination and Sizing Subsystem (5-BE-1)
- Soils Processing Subsystem (S-EB-2)
- TRU geological repository
- Clean soil
- Exhaust gases from the stack
- Treated water and sanitary waste.

5.1.6.2 Support from Other Systems (Input). The Waste Receiving, Processing, and Packaging Facility receives input from the following:

- Retrieval Subsystem (S-BE-4) input includes soil and waste
- Soils Processing Subsystem (S-EB-2) input includes TRU, LLW, and clean soil
- Metal Decontamination Subsystem (5-BE-1) input includes TRU residue, TRU metal, and LLW
- Utilities input includes service water, power, and ventilation input
- Consumable input includes solidification materials, packaging materials, shipping containers (both disposable and reusable), and molten salt (sodium and potassium carbonate).

5.2 SYSTEM ASSESSMENT

The current status, program implementation risks, and a pro/con analysis of the unit operations associated with the MSO System are discussed in this section. The integration aspects in forming a complete system that satisfies the functional, performance, and interface requirements are complex and may perturb individual unit operations or necessitate DT&E efforts because of integration problems not previously identified.

5.2.1 Current Status of Unit Operations

There are 10 unique unit operations associated with the Molten Salt Oxidation System (3-BE-7). The unit operations are discussed below.

5.2.1.1 Incoming (Unprocessed) Waste Receiving and Opening. This unit operation receives prepackaged waste from the Waste Retrieval Subsystem (S-BE-4) and integrates subsystems and unit operations of the overall system based on assay and segregation of the waste stream. The functions of this unit operation include opening the prepackaged containers (reusable); sorting and segregating waste for input into appropriate unit operations; completing inventory storage and accountability of waste; and uncapping, opening, and dumping waste. Uncapping and opening of incoming containers will be accomplished in an alpha cell environment with the capability to control dust, drum gas vents, and other hazardous airborne gases and any liquid that may leak out of the containers.

The unit operation will typically consist of a loading dock, shielded and enclosed workspace, gantry cranes, manipulator systems, drum/container handling systems (for repackaging, uncapping, and recapping), and radiological survey instrumentation. Additional automated process components may include an automated bar coding system for accountability and tracking purposes; information management systems for data retrieval, storage, and processing; and an inventory controls system that will monitor and quantify input waste streams. Special hoods, dust collection devices, vents, and filters will be provided. Design features will also be provided to collect any potential free liquid that may leak out of the drums and boxes.

The technologies employed in this unit operation are similar to existing material handling and inventory systems currently commercially available. Dust, airborne gases, and free liquid contamination control processes are also existing techniques. However, special designs may be needed to account for unique hazards associated with the chemical and radioactive toxicity nature of the gases and liquids. DT&E addressing integration of automated systems within a controlled environment may be required.

5.2.1.2 Sorting (Nonmetal/Metal). The sorting unit operation is designed to segregate metals from nonmetals and, where applicable, to further sort by waste type (TRU, LLW, soil, etc.). There is a wide range of technologies and equipment available. These range from simple manual sorting techniques to sophisticated neutrography and x-ray fluorescence sorting techniques. The equipment employed in the sorting process may include manipulators, screen sieves, glove boxes (for manual sort), trommels, disc screens, magnetic detection/separation equipment, inductive coil metal detectors, and robotics. On-line radiation detection/assay units and on-line hazardous gas detectors/analyzers may also be used.

Some of these technologies are currently employed in the nuclear industry and most are commercially available. DT&E of the application of these techniques in a controlled environment with appropriate redundancy and error recovery capabilities will be required. In addition, further development of assay equipment with high throughput will be required. Also, DT&E of techniques for segregation of metal/non-metal composites will be required.

5.2.1.3 Size Reduction. This unit operation prepares the incoming non-metal waste stream for the molten salt oxidizer. The preparation steps include coarse size reduction through shredding or crushing and fine sorting to minimize the amount of soils fed to the molten salt oxidizer. The soil waste stream will be diverted to the soil processing system. The operation also allows for integration of sludges into the MSO waste stream. The equipment employed in this unit operation includes sludge drum handling and uncapping systems, shredders or crushers, and cryofracture technique. This latter technique is being used for size reduction of chemical weapons.

Most of these technologies are currently employed in the nuclear industry and are all commercially available. DT&E of the application of these techniques to an alpha cell environment may be required. In addition, integration of these technologies may require DT&E. The size reduction unit may need a further step to classify the size-reduced waste and remove silicates. DT&E in this area will be needed.

5.2.1.4 Molten Salt Oxidizer. The MSO program is a currently funded DOE program being executed by LLNL and Rockwell International (RI). The RI system consists of a 1 t/d baseline design, and its mass balance is for LLNL waste streams. The pilot-scale unit for LLNL is scheduled to be completed and operated in FY 1991. The process developed by RI is patented (30 patents). It is an air breathing (open loop exhaust), isothermal 1652°F process. The prototype 1 t/d unit has demonstrated the destruction of plutonium-containing wastes, where the plutonium is retained by the melt, and a high level of destruction of hazardous wastes occurs (PCBs, chemical warfare agents, halogenated organics, solids, and aqueous slurries). In most cases, the destruction was quantified to be in the 99.99% efficiency range. The RI process is a single vessel system that favors low-ash, low-moisture feed stock. High alumino-silicate ash combined with an excessive oxygen level dynamically increases viscosity to the point of solidification, thereby rendering the melt useless. High moisture requires a large increase in fuel use.

LLNL is working on an advanced design for a two-stage process. The objective is to reduce the process temperature, which will allow a wider range of construction materials and mechanical process options and will reduce salt vapor loss and the transmission of volatiles. An additional objective will be the elimination of the alumino-silicate polymerization (freeze) phenomena. Bench-scale testing of the two-stage process is scheduled for FY 1991.

This unit operation is currently undergoing DT&E at LLNL. For application to the Buried Waste Program, the following additional DT&E will be needed:

- Characterization of the feed stock and off-gas stream

- Demonstration of the two-stage process
- Definition of the mechanics and improvement in the process of salt recovery and recycling
- Identification/extraction of trace off-gas contaminants through improvements in analytical techniques and recovery methods
- Achievement of a better understanding of the waste cycle thermodynamic analysis
- Definition of feed stock type, quantity, and preprocess requirements and options
- Development and implementation of regulatory planning and acceptance criteria
- Elimination of alumino-silicate polymerization (freeze) problem
- Specification of materials of construction for the process
- Development to ensure operability, reliability, and maintainability in the alpha cell environment.

5.2.1.5 Off-gas Treatment. The off-gas treatment unit operation examines, quantifies, and treats the process stream to permit release to the environment and secondary waste stream process subsystems (e.g., condensed liquids to liquid waste stream). The major components of this unit operation may consist of assay and gas stream composition equipment, filtration (HEPA and charcoal), spray/scrubber with provisions for chemical addition, and condensation equipment.

Most of these technologies are currently employed in the nuclear industry and all are commercially available. DT&E may be required in integration and optimization to treat a potentially wide range of influents from the diverse waste streams from the MSO treatment.

5.2.1.6 Liquid Waste Treatment. The liquid waste unit operation will collect, filter, process, and direct effluents to other unit operations or discharge them to the environment after analysis. The processes may include filtration, neutralization, demineralization, reverse osmosis (RO), evaporation, and precipitation. The equipment used during these processes may include tanks, pumps, liquid transport equipment, filters, ion exchangers, heat exchangers, evaporators, RO membranes, and chemical addition, mixing, and flocculation equipment.

Most of these technologies are currently employed in the nuclear industry and all are commercially available. DT&E may be required in integration and optimization to treat a potentially wide range of effluents.

5.2.1.7 Solidification. The solidification unit operation receives fines, liquids, and MSO waste by-products and combines them using physical or chemical processes to solidify the materials. The solidified waste is then placed into certified containers. There are several candidate processes, which include the following:

- Cementitious solidification
- Dow process (solidification of waste in a polymer medium supplied by Dow Chemical)
- Other polymer process (solidification of waste in a polymer medium)
- Bitumen (mixing of waste with hot bitumen to allow evaporation of the liquids and retention of solids in bitumen).

The equipment typically used in these processes includes automated conveyor equipment, container handling equipment, drums/containers, tanks, pumps, slurry equipment, chemical process control equipment, and dewatering equipment.

Most of these technologies are currently employed in the nuclear industry and all are commercially available. DT&E may be required in the area of

solidifying MSO by-product with a process that will meet various regulatory requirements. DT&E of the application of these techniques to waste streams anticipated for this system may be required.

5.2.1.8 Assay/Certification. The assay/certification unit operation examines and quantifies the radioactive physical properties of the filled containers to determine proper classification and adherence to the appropriate regulations for the hazardous material and to ensure compliance with current transportation and disposal regulations. The equipment employed in this unit operation includes the following:

- Passive neutron detection
- Gamma spectroscopy/multichannel analysis equipment
- Gross gamma detectors
- Real-time radiography
- Visual inspection equipment
- Surface contamination measurement equipment
- Automated handling systems
- Container labeling and tracking equipment.

The operation is expected to confirm data already collected during the processing of all waste streams and final package operations. Final verification of the waste form (LLW or TRU) will be conducted at this time. In addition, final labeling, material accountability tags, and transportation/storage compliance certification will be accomplished during this process step.

Some of these technologies are currently employed in the nuclear industry and most are commercially available. However, DT&E of the application of

these techniques to meet the current transportation and disposal regulations may be required.

5.2.1.9 Interim Storage. This unit operation should consist of a clean environment on a controlled area/pad and should be regulated and monitored to ensure compliance with local and/or broad agency radiological regulations. The storage area is serviceable by remote and contact handling equipment with the capability of reading container labels.

This unit operation is similar to any industrial warehouse operation. All of these technologies are currently employed in industry and all are commercially available. DT&E of additional technologies is not required.

5.2.1.10 Shipping. This unit operation is intended to be the external interface of the processing subsystems to the final waste disposition. The shipping station will prepare bills of lading for the inspected/certified waste containers. Where necessary, the containers will be over-packed to meet appropriate transportation limitations.

This unit operation should not require any special equipment other than that normally used in current shipping cask handling and loading operations. All of these technologies are currently employed in the nuclear industry and all are commercially available. Research and development of additional technologies is not required.

5.2.2 Program Implementation Risks

This section identifies major concerns associated with program implementation assuming that the MSO System is selected. The risk of accomplishing the program objectives is qualitatively characterized. A summary of the results and major areas of concern is shown in Table V-5-1. Program mission and objectives are given in Volume II.

5.2.2.1 Performance Objectives. Baseline cleanup standards for SDA pits and trenches at RWMC cannot be established until an ROD pursuant to the CERCLA process is reached. These standards will be derived ARARs under CERCLA,

Table V-5-1. 3-BE-7 summary of program implementation risks and major areas of concern

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> Alpha cell confinement of radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events Potential jamming and maloperation of complex mechanical devices and becoming a choking point Dust control during operations in the alpha cells Dust control and equipment decontamination & maintenance. Requirements could become a limitation on the application of commercially available equipment. Extensive DT&E to demonstrate versatility and compliance with rules and regulations 	<ul style="list-style-type: none"> Ability to define and mitigate Pu-contaminated material safety concerns Ability to define and mitigate radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events Ability to define postulated accident events for the MSO (high-temperature) process 	<ul style="list-style-type: none"> Institutional acceptance of thermal process 	<ul style="list-style-type: none"> Buried waste streams application verification and compliance with RCRA & NRC may require prolonged DT&E 	<ul style="list-style-type: none"> Alpha cells in this environment is a first-of-a-kind design MSO is a first-of-a-kind application Use of remotely operated mechanical equipment on TRU waste is a first-of-a-kind application

Table V-5-1. (Continued)

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> • High-temperature operation with limited experience on feeds similar to buried waste • Critical material life is unknown • Characteristic requirements for the incoming waste stream waste effluent are unknown • DT&E will be needed to demonstrate versatility needed for buried waste streams application and compliance with RCRA, NRC, and DOE requirements 				

Table V-5-1. (Continued)

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> Technologies for solidification(stabilization) of the MSO waste output has not been tested. There is a concern that the waste output may not be compatible with the existing technologies Defining the composition of the waste and testing properties of solidified waste could require prolonged DT&E 	Moderate	High	Moderate	Moderate

standards set by risk assessments, and the State and local statutes. Since no specific requirements have been formally established at this time, it is assumed that the major ARARs for this system will be RCRA rules, the appropriate NRC regulations and guides, and DOE regulations and Orders.

In the MSO and Packaging System, the major uncertainties listed below have been identified as areas of concern in the achievement of the performance objectives:

- Processing of the waste will be conducted in several alpha cells. These cells are to contain dust and any radioactive, hazardous, toxic, and volatile gases that may become airborne during the waste handling and processing operations. This protection will have to be provided in normal and postulated accident events (e.g., a fire). Alpha cells, as used in the nuclear environment, typically have triple confinement barriers. A triple barrier is needed to ensure protection of workers, public health and safety, and the environment. The three parts typically consist of an operation area (which is usually contaminated), an isolation vestibule, and corridors where workers conduct the operations. Several of the waste handling operations will use technologies that are existing but will have to be adopted for use in an alpha cell environment. This requires remote operation and ease of decontamination for maintenance. These features make this system a first-of-a-kind facility with many uncertainties regarding the program's ability to develop a cost effective design with the following:
 - Adequate confinement of radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events.
 - Efficient operation of the complex mechanical equipment, such as drum opening devices, sorting units, size reduction machines, manipulators, waste conveyors, and all related components that must be installed inside alpha cells. There is a concern regarding potential jamming and maloperation of these components. Also, any of these unit operations could become a

potential choke point because of limited prior knowledge of waste streams and the high throughput requirements.

- Additional technical concerns are (a) dust control during operations in the alpha cells could require very large and complex ventilation and filtration systems, (b) questionable operation of some of the equipment in a dusty environment, and (c) dust control in the alpha cell environment and equipment decontamination requirements before maintenance could become limitations on the use of commercially available equipment. DT&E efforts could become more extensive than estimated.
- The unit operations of MSO are new technologies. The process has no commercial experience and has been only demonstrated on a pilot-plant basis, mostly in coal application. The process is high-temperature and the duration of critical materials is unknown. This concern could be eliminated through long-term DT&E. A pilot plant is being tested at LLNL but the waste stream is different than that anticipated from the Buried Waste Program. In general, there are uncertainties in characteristic requirements of the incoming waste stream, waste effluent characteristics based on a given set of incoming waste streams, and equipment life. DT&E will be needed to demonstrate (a) versatility needed for buried waste streams application, and (b) compliance with RCRA, NRC, and DOE requirements.
- Technologies for solidification (stabilization) of the MSO waste output have not been tested. There is a concern that the waste output may not be compatible with existing technologies.

Based on the above discussions, it is believed that the overall risk associated with achieving the performance objectives is high.

5.2.2.2 Health and Safety Objectives. The key health and safety objectives for the Buried Waste Program are to (a) identify the hazards of the

remedial action operation, and (b) provide measures to eliminate, control, or mitigate identified hazards. In this system, major areas of uncertainty are

- The ability to define postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material) for the alpha cells and provide mitigation measures to satisfy the RCRA, NRC, and DOE requirements.
- The ability to define postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material) for the MSO process. Definition and mitigation of the normal and accident events for MSO could also become complex because of high-temperature processing.

The uncertainties are largely from the inability to characterize the incoming waste. DT&E on characterization could provide a better confidence level. It is believed that using remote handling equipment and conducting operations inside alpha cells will enhance the mitigation measures for a majority of the normal and postulated events. This approach reduces the risk associated with achieving the health and safety objectives. At this stage of the system modeling, it is believed that the overall risk is moderate.

5.2.2.3 Institutional Objectives. A key institutional objective is to involve the public, as required by CERCLA and NEPA, in the process of selecting a remedial action for the Buried Waste Program. Public support of the MSO, which is a commercially unproven thermal process, is considered to be low. Hence, it is believed that the risk associated with achieving the institutional objectives is high.

5.2.2.4 Schedule Objectives. The objective of the Buried Waste schedule is to reach approval for Title II start by mid 1999. This is based on the assumption that an ROD will be reached by the end of FY 2001. The schedule objective for completion of the Buried Waste Program remedial action is by FY 2019. The following major uncertainties in achieving these objectives have been identified:

- The alpha cells are relatively complex first-of-a-kind structures and could be subject to prolonged DT&E, design, and construction. However, with advanced planning, uncertainties in achieving schedule objectives could be reduced.
- Use of remotely operated mechanical equipment for sorting, conveying, size reduction, and handling of TRU waste is a first-of-a-kind application. Schedule uncertainties because of prolonged DT&E, design, and construction are anticipated. Again, with advanced planning, uncertainties in achieving schedule objectives could be reduced.
- Demonstration of MSO versatility needed for buried waste streams application, and compliance with RCRA, NRC, and DOE requirements may require prolonged DT&E.
- Demonstration of MSO waste solidification and compliance with EPA, NRC, and DOE standards may require prolonged DT&E.

Based on the above discussions and an assumption that the program implementation activities will start in FY 1992, the schedule risk is believed to be moderate.

5.2.2.5 Cost Objective. Assessment of the cost objective is a qualitative characterization based on the uncertainties involved in defining a reasonably accurate cost estimate for the system. Some of the major uncertainties are presented below:

- The use of an alpha cell in the given waste processing environment is a first-of-a-kind design and could be subject to cost overruns because of prolonged design development. Major areas of uncertainty are (a) the extent of design features needed for operating in a dusty environment, (b) providing safety for postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material), and (c) satisfying RCRA, NRC, and DOE

requirements. Currently, the limited information available on waste characteristics contributes to these uncertainties.

- Use of remotely operated mechanical equipment for container opening, sorting, size reduction, and handling of TRU waste is a first-of-a-kind application. Cost uncertainties are anticipated until design, based on DT&E, is well into maturity.
- Use of MSO for buried waste is a first-of-a-kind application. Cost uncertainties are anticipated until design, based on DT&E, is well into maturity.

Based on the above discussions, the cost risk is believed to be moderate.

5.2.3 Unit Operations Pro and Con Analysis

The following is a pro and con assessment of each unit operation of the Molten Salt Oxidation System (3-BE-7).

5.2.3.1 Incoming (Unprocessed) Waste Receiving and Opening. This unit operation receives prepackaged waste from the Waste Retrieval Subsystem (S-BE-4) and provides inventory storage for waste processing streams to maintain production lines. The technologies required are well-known. However, there is a potential for contamination in the event of a dropped intact drum or waste container. Uncapping and opening of containers may involve potential airborne release of radioactive, toxic, and volatile gases to the alpha cell.

5.2.3.2 Sorting (Nonmetal/Metal). The sorting unit operation segregates metals from nonmetals and, where applicable, further sorts by waste type (TRU, LLW, soil, etc.). Advantages to this unit operation are (a) master/slave manipulators are versatile and can perform most tasks, (b) trommel and disc screens are simple reliable devices for soil separation, and (c) inductive metal detectors will separate nonmagnetic metals (stainless steel). Also, manual sorting in gloveboxes is the most versatile, and power manipulators (e.g., electromechanical manipulators) have high lifting capacities.

Several disadvantages are associated with this unit operation. For example, master/slave manipulators may be maintenance items and have relatively limited lifting capacities (10 to 400 lb for standard manipulators; new ones under development should have capacities up to 1500 lb). Some work objects will be composites of metals plus non-metals and will not be easily separable without size reduction/cutting, etc. This could lead to master/slave manipulators that are slow and labor-intensive. In addition, trommel and disc screens require large operating spaces. Magnetic separators will not work for austenitic stainless steels, which are not magnetic.

5.2.3.3 Size Reduction. The size reduction unit operation prepares the incoming waste stream by coarse size reduction through shredding or crushing and fine sorting to minimize the amount of soils fed to the molten salt oxidizer. The advantage of this unit operation is that shredders and crushers are commercial items that can accommodate a wide variety of feeds. In addition, the cryofracture process reduces both metals and nonmetals to small sizes and does not create dust. However, shredders and crushers are complex mechanical devices, have many moving parts that may be difficult to maintain in an alpha cell, are difficult to decontaminate, and generate dust. Also, cryofracture requires additional DT&E because there are some materials, such as stainless steel, that the process does not reduce well. Also, off-gas from cryofracture needs additional DT&E.

5.2.3.4 Molten Salt Oxidizer. The molten salt oxidation unit operation combines organic and halogenated compounds with molten sodium/potassium carbonate to produce water vapor, carbon dioxide, and salt. The pros of this unit operation include high destruction efficiencies and lower operating temperatures in the primary vessel allowed by a two-stage process. The two-stage process can process feeds mixed with small quantities of aluminosilicates, such as soil. In addition, once started, the process maintains temperature through exothermic reaction. LLNL is developing a hold and release off-gas system to ensure system upsets do not cause excess emissions. The significant pro for this system is the ability to convert organic halogens to water, carbon dioxide, and salt.

Several disadvantages for this unit operation are (a) high-temperature thermal processes with their associated gaseous emissions are perceived negatively by the public, (b) acceptable feeds need to be better defined, and (c) sludges may present problems depending on composition. The MSO process is sensitive to alumino/silicates, so sludges with a high content of sand or clay may present problems in processing. Also, solidification of the bed because of feed impurities is a concern, the one-stage process cannot process feeds mixed with soil, and there may be material compatibility problems with high temperatures, salt, and required long-service life.

5.2.3.5 Off-gas Treatment. The off-gas treatment unit operation examines, quantifies, and treats the off-gas from the MSO process. There are several advantages to this unit operation. HEPA filtration is standard technology, and baghouse filtration and electrostatic precipitation are highly efficient for particulate collection and generate no secondary liquid wastes. Another pro is that wet scrubbing can remove gaseous pollutants as well as particulates. However, wet scrubbing generates a secondary waste stream and HEPA filters deteriorate over time and must be replaced periodically.

5.2.3.6 Liquid Waste Treatment. The liquid waste unit operation collects, filters, and processes effluents from other unit operations. Evaporation is a standard waste treatment process in the DOE complex, and demineralization is a standard treatment at nuclear power plants. One disadvantage of precipitation, flocculation, etc. is that they have limited experience in radioactive waste treatment. Another disadvantage is that RO, one of the techniques proposed for this unit operation, is sensitive to fouling.

5.2.3.7 Solidification. The solidification unit operation solidifies fines, liquids, and organic waste by-products using physical or chemical processes. Several advantages have been identified for this unit operation. For example, Portland cement is a simple well-known process that is readily available. It works best for inorganic contaminants but also works with oil and grease. Lime-based pozzolana systems have similar pros as Portland cement and can work better with organics but not oils. In addition, Portland cement and lime-based pozzolana solidification agents will provide a product that

meets TCLP. However, Portland cement and pozzolanic systems are not exceptionally leach resistant. The ratio of waste loading to cement is fairly low (one to one). These systems may not be suitable for MSO waste output because (a) Portland cement tends to generate a lot of dust, (b) thermoplastic resins require the waste to be dried before solidification, (c) the resin product can be damaged by fire, and organic compounds may vaporize during heating in the solidification process, and (d) organic polymers are highly viscous, which makes them difficult to process. Also, costs are about five times those for cement.

5.2.3.8 Assay/Certification. The assay/certification unit operation examines and quantifies the radioactive properties of the filled containers to classify and ensure compliance with regulations for final disposal. This unit operation provides the final check for regulatory compliance, and instruments for certification are available.

5.2.4 Unit Operations Lead-Time Estimates

The lead-time required for DT&E is estimated for each unit operation that may require research and development before landing in the field, as shown in Table V-5-2. The development of the lead-time required for DT&E is based on a qualitative judgment and should be further refined.

5.2.5 Rough Order of Magnitude Cost Estimates

ROM costs were developed for the Molten Salt Oxidation System (3-BE-7) using the assumption given in Section 1. The costs are summarized in Table V-5-3.

The additional assumptions and qualifications used in the preparation of the ROM estimate for this system are as follows:

- Special site preparation costs are not included, such as drainage, substations, roadwork, and other utilities.

Table V-5-3. Rough order of magnitude cost estimates (3-BE-7)^a

Cost Code	Cost Items	Normalized Cost (\$x1000)	Modified Cost (\$x1000)
1.0	Studies and bench scale cost		
1.1	Manpower costs during research	\$3,900	\$3,900
1.2	Equipment costs	\$2,000	\$2,000
1.3	Installation costs	\$950	\$950
1.4	Contingency	\$1,713	\$1,713
	Subtotal 1.0	\$8,563	\$8,563
2.0	Demonstration costs		
2.1	Manpower cost during construction	\$8,000	\$8,000
2.2	Design cost (30% of 2.5)	\$3,416	\$3,416
2.3	Inspection cost (7% of 2.5)	\$797	\$797
2.4	Project administration (10% of 2.5)	\$1,139	\$1,139
2.5	Construction cost		
2.5.1	Building structure costs	\$1	\$1
2.5.2	Equipment costs	\$9,000	\$9,000
2.5.3	Indirect (20.9% of 2.5)	\$2,385	\$2,385
	Subtotal of 2.5	\$11,386	\$11,386
2.6	Construction management costs (27.8% of 2.5)	\$3,268	\$3,268
2.7	Contingency	\$7,001	\$7,001
	Subtotal 2.0	\$35,007	\$35,007
3.0	Production construction costs		
3.1	Design cost (30% of 3.4)	\$77,324	\$39,602
3.2	Inspection cost (7% of 3.4)	\$18,042	\$9,240
3.3	Project administration (10% of 3.4)	\$25,775	\$13,201
3.4	Construction cost		
3.4.1	Building structure costs	\$135,555	\$36,155
3.4.2	Equipment costs	\$68,198	\$68,198
3.4.3	Indirect (20.9% of 3.4)	\$53,995	\$27,654
	Subtotal of 3.4	\$257,748	\$132,007
3.5	Construction management costs and construction management reserve (26.5% of 3.4)	\$73,974	\$37,886
3.6	Contingency (25% of 3.1 through 3.5)	\$113,216	\$57,984
	Subtotal 3.0	\$566,079	\$289,920
	Total Capital Cost (1.0, 2.0, and 3.0)	\$609,649	\$333,490
4.0	Annual operating and maintenance costs		
4.1	Operating costs	\$36,000	\$36,000
4.2	Utility costs	\$8,000	\$8,000
4.3	Material costs	\$14,000	\$14,000
4.4	Maintenance costs	\$16,000	\$16,000
4.5	Contingency	\$18,500	\$18,500
	Subtotal 4.0	\$92,500	\$92,500
TOTAL	10 Years Operating and Maintenance Costs		\$925,000

a. Does not include the appropriate subsystem costs (see Volume VII for subsystem costs).

- Owner's costs such as environmental impact report costs, labor, overheads, etc. are not included.
- The estimate is based on first quarter 1991 wage and price levels.
- The facility areas are developed based on conceptual layout of process equipment. Allowance for administrative and remote operation facilities are not included.
- The areas shown in the F&OR general arrangement were adjusted to account for the unit operation capacities.
- The equipment scope was based on conceptual process functional diagrams.
- Equipment pricing is based on conventional commercial construction
- Minimal allowance (e.g., one of a kind for demonstration) has been included for remote operation as well as any nuclear quality assurance program cost.
- An allowance for process bulks are included at 30% of the equipment cost to account for electrical, piping, and local control requirements.
- Equipment costs include material, fabrication, delivery, inspection, and installation costs (all in costs).
- Costs for widening or strengthening existing roads for construction are not included.
- An adequate supply of labor is assumed to exist within the local area.
- Testing and initial startup costs are not included.

- Operating and maintenance costs are based on 15% of production construction costs.
- Cost estimates are based on nominal costs associated with the best currently available technology considered. The lowest technology and the state-of-the-art systems were not considered in the cost model.
- The cost estimate does not include the cost of the Retrieval, Metal Decontamination and Sizing, or Soils Processing Subsystems.

Strengths and weaknesses of the cost estimate are subsystem costs that may vary between systems depending on the technologies employed. The cost estimate is based on relatively well-known technologies. No provision was made for research and development associated with state-of-the-art technologies such as cryofracture.

5.2.6 System Evaluation Results

The purpose of this section is to provide an overall evaluation on a system basis and to identify the major considerations (both advantages and disadvantages) resulting from the assessments in the previous sections. This includes an evaluation of the ability to integrate the various unit operations into a smooth, well-functioning system.

Specific areas addressed include identification of system major considerations, a qualitative judgment rating of performance measurables, a summary of research and development needs, and an overall recommendation for the system.

5.2.6.1 Identification of System Major Considerations. The Molten Salt Oxidation unit operation is currently undergoing significant DT&E. The process has difficulty with waste streams of high soil content.

The MSO unit operation and design of alpha cells and the mechanical handling devices with the system safety requirements represent the greatest

uncertainty for this system. The other unit operations are well-known and present minimal risk. In addition, the safety risk associated with operation processing mixed waste (radioactive and organic) may be significant. The ability to process waste streams of unknown characteristics presents significant risk. The significant pro for this system is the ability to convert organic halogens to water, carbon dioxide, and salt. Processing efficiencies are high for known waste stream compositions. The significant con for this system is the ability to process unknown waste stream compositions. Problems have occurred with sand/clay mixtures at high temperatures. This system requires significant lead-time for DT&E. The cost estimate for this system is highly dependent on the final configuration of the MSO process.

5.2.6.2 Performance Measurables Rating. Performance measurables, used in the evaluation of the overall system, represent the top level of performance requirements that will be allocated and then applied to appropriate elements of the system in subsequent phases of the program. Table V-5-4 provides a qualitative assessment of how well the MSO System satisfies these performance measurables.

5.2.7 Summary of Demonstration, Testing, and Evaluation Needs

The DT&E needs for each unit operation and the overall system have been summarized in Table V-5-5. This table provides a ready reference to DT&E needs in the final system evaluation and for comparison purposes with other systems.

Some of the issues that require further DT&E include the following:

- Full-scale operating parameters for both the single stage and the two-stage process should be confirmed
- The integration of the process streams should be reviewed to ensure compatibility

Table V-5-4. Rating performance measurables for the Molten Salt Oxidation System (3-BE-7)

<u>Measurable</u>	<u>Incoming Waste Receiving and Opening</u>	<u>Sorting Metal/ Nonmetal</u>	<u>Size Reduction</u>	<u>Molten Salt Oxidizer</u>	<u>Off-gas Treatment</u>	<u>Liquid Waste Treatment</u>	<u>Solidification</u>	<u>Assay Certification</u>	<u>Total</u>
Timeliness	8	7	8	6	9	9	8	9	64
Availability	8	8	8	3	9	9	8	9	62
Completeness	7	6	7	4	8	8	7	9	56
Risk	7	6	7	3	7	8	7	8	53
Flexibility	8	8	7	7	7	8	7	7	59
Cost	8	7	8	4	7	8	8	9	59
Safety	8	8	8	5	8	8	8	9	62
Waste Reduction	6	8	8	9	8	8	6	7	60
Complexity	<u>7</u>	<u>7</u>	<u>7</u>	<u>5</u>	<u>7</u>	<u>7</u>	<u>7</u>	<u>7</u>	<u>54</u>
Totals	67	65	68	46	70	73	66	74	529

Table V-5-5. DT&E needs for the Molten Salt Oxidation System (3-BE-7)

<u>Unit Operation</u>	<u>Technology Development Status</u>	<u>DT&E</u>
Incoming Waste Receiving and Opening	<ul style="list-style-type: none"> • Commercially available • Currently used in mining and metal industry 	
Sorting	<ul style="list-style-type: none"> • Commercially available • Currently used in nuclear industry 	<ul style="list-style-type: none"> • Application to waste stream • Remote operation • Maintenance concepts (remote or contact) • Application in production scale environment • Integration • Application in alpha cell
Size Reduction	<ul style="list-style-type: none"> • Commercially available • Currently used in nuclear industry 	<ul style="list-style-type: none"> • Application to waste stream • Remote operation • Maintenance concepts (remote or contact) • Application in production scale environment • Integration in alpha cell • Select materials of construction • Feedstock type, quantity and pre-process requirements • Characterization of off-gas stream • Design of salt recovery and recycling processes • Identify recovery methods of contaminants from spent salts

Table V-5-5. (continued)

Unit Operation	Technology Development Status	DT&E
Molten Salt Oxidation	<ul style="list-style-type: none"> • RI Prototype unit is in operation • Bench scale operational at LLNL FY 91 	<ul style="list-style-type: none"> • Remote operation in alpha cell environment • Regulatory planning and acceptance criteria • Characterization of off-gas stream • Optimization of salt recovery and recycling processes • Determine hazardous waste destruction efficiency • Two-stage process • Regulatory planning and acceptance criteria • Operability in alpha cell environment
Off-gas Treatment	<ul style="list-style-type: none"> • Commercially available • Currently used in DOE and nuclear facilities 	<ul style="list-style-type: none"> • Remote operation • Remote maintenance • Optimization to wide range of influents • Characterization of off-gas stream • Integration • Identify recovery methods of off-gas contaminants • Identify clean up efficiency decontamination factor requirements
Liquid Waste Treatment	<ul style="list-style-type: none"> • Commercially available • Currently used in DOE and nuclear facilities 	<ul style="list-style-type: none"> • Integration • Remote operation • Remote maintenance • Optimization to a wide range of influents
Solidification	<ul style="list-style-type: none"> • Commercially available • Currently used in DOE and nuclear facilities 	<ul style="list-style-type: none"> • Integration of process in production-scale environment • RAM^a of prototype equipment

Table V-5-5. (continued)

<u>Unit Operation</u>	<u>Technology Development Status</u>	<u>DT&E</u>
Assay/Certification	<ul style="list-style-type: none"> • Commercially available • Currently used in DOE and nuclear facilities 	<ul style="list-style-type: none"> • Application to current transportation and disposal requirements • RAM^a of prototype equipment • Automation • Integration of process in production-scale environment
Overall System		<ul style="list-style-type: none"> • Application in production-scale environment • Integration of entire process • RAM^a of process in an alpha cell environment • Remote operation and maintenance • Automation

a. RAM = reliability, availability, and maintainability.

- Consideration should be given to on-line sensors reporting to monitor and report the status and progress of waste stream processing.
- Sensitivity of the process to the composition of the input waste streams should be determined (note: this may be answered by the two-stage process)
- The system as a whole will require fine tuning of all the selected technologies to produce the desired end results
- Confirmation of the compatibility of construction materials with the process
- Confirmation that all the safety issues associated with processing hazardous radioactive mixed waste have been addressed

- An analysis of the queuing of the waste stream to determine capacities of components for unit operations is required

The study helped characterize and define a number of alternatives for the unit operations of this system. The evaluations conducted under this study conclude that DT&E is required. Qualitative judgments were used in developing the extent of DT&E required. A more detailed assessment is needed to draw a definitive conclusion on DT&E programs and technology selection.

Risk assessment in the study is qualitative and judgmental and is based on the assumption that wastes having dangerous physical or chemical characteristics (e.g., pyrophoric and gas cylinders containing toxic, volatile, and reactive gases) are not being processed. A more detailed definition of the incoming waste will be needed to perform a complete risk assessment, and significant changes in the composition of the waste may impact the technology selected and the general arrangement of the facilities.

This system definitely provides a unique capability that apparently results in benign end products and should be considered for remediation of defined hazardous waste streams. The waste stream composition of RWMC is not well-defined at this time. Hence, the feasibility of the MSO process should be studied further when more specific waste characteristic data are available.

5.3 RECOMMENDATIONS FOR THE SYSTEM

The MSO process converts organic halogenated wastes into water, carbon dioxide, and salt. Application to the Buried Waste Program should be pursued if halogenated wastes such as polyvinyl chloride (PVC) are proven to be significant waste streams. This conversion process occurs at relatively high temperatures and atmospheric conditions. The process is sensitive to the composition of the input waste streams and is currently undergoing significant DT&E.

6. CHEMICAL OXIDATION/SOLIDIFICATION SYSTEM WITH LOW-LEVEL WASTE POSTSORT (3-IT-8)

6.1 FUNCTIONAL AND OPERATIONAL REQUIREMENTS

This F&OR is prepared as a component of the EG&G Idaho SDS task. The purpose of the task is to provide a basis for the development of technologies required to remediate the buried waste in WAG-7 of RWMC. The buried waste includes constituents that make it mixed waste. As a result, RWMC will be remediated under the terms of RCRA and CERCLA.

6.1.1 System Description

The system is shown in Figure in V-6-1 and is described in the following paragraphs.

6.1.1.1 Open Packages and Sort. Waste will be processed through four unit operations. At this point, all packages will be opened in appropriate containment, and the contents of each package will be examined visually using x-rays, dumped, and then directed to either the inerts processing operation, the combustibles oxidation process, the Metals Decontamination and Sizing Subsystem, or the lead melting process.

6.1.1.2 Screen. Inerts and sludges will be screened to separate large inerts from sludges and small particulates. The large inerts will proceed to the bioremediation treatment process, and the remainder will be conveyed to the combustibles oxidation process.

6.1.1.3 Inerts Treatment. Large inerts will be treated to remove organic and oxidizable inorganic constituents using a bioremediation process. Alternative processes include soil washing, oxidation/ozonation and irradiation, and bioremediation.

6.1.1.4 Shredder. A shredder will size-reduce the combustibles for subsequent processing.

DESCRIPTION: THE SYSTEM IS A CHEMICAL OXIDATION/SOLIDIFICATION SYSTEM TO MEET EDR REQUIREMENTS. KEY OPERATIONS INCLUDE: SIZING, CHEMICAL OXIDATION, BIOTREATMENT AND REMEDIATION.

Figure V-6-1. Process functional diagram for the Chemical Oxidation/Solidification System with ILW Postsort (3-IT-8).

Note: Mass flow balance does not show the input process additives.

DRAWING

UNIT

Open &
Screen
Shredd
Inerts
Chemical
Biotreat
Off-Gas
Dewater
Liquid
Solidifi
Melter
Package
Assay

PROCESS

3 NUMBER 3-IT-8	DESIGN	PROPANE	ELECTRICITY
OPERATION	CAPACITY (lbs/hr)	(gal/hr)	(kW)
ackages and Sort	2680	0.00	4
	1520	0.00	7
	1740	0.00	311
r treatment	320	0.00	164
al Oxidation	1740	0.00	328
ment Adsorption	16900	0.00	164
Treatment	800	0.00	6
ring	16600	0.00	164
Waste Treatment	16650	0.00	1126
ation	2200	0.00	376
	210	0.00	65
	4500	0.00	4
and Sort	4600	0.00	1

H. 3/11/91		ISSUED FOR REVIEW		BY J.P. J.M. J.V. J.A.V.	
NO.	DATE	REVISION	BY	CHKD.	ENGR.
3/8/91	3/8/91	1	J.P.	J.M.	J.V.
<p>IT INTERNATIONAL TECHNOLOGY CORPORATION KIRKLAND, WA 98033</p>					
<p>EG & G IDAHO, INCORPORATED SYSTEM DESIGN STUDY IDAHO FALLS, IDAHO</p>					
<p>PROCESS FLOW DIAGRAMS FOR SYSTEM DESIGN STUDY</p>					
JOB NUMBER		DRAWING NUMBER		REVISION	
301411		3 - 1 - 8b		P	

6.1.1.5 Chemical Oxidation. Oxidizables will be treated by supercritical water oxidation, acid digestion, or wet oxidation to remove oxidizable constituents from the waste stream.

6.1.1.6 Biotreatment/Adsorption. Residual organic constituents from the oxidation process will be further processed by biological treatment or carbon adsorption.

6.1.1.7 Dewatering. Sludge will be removed from the treated waste stream and forwarded to the solidification process. Effluent will be treated in the liquid waste treatment system.

6.1.1.8 Off-gas Treatment. Light organics emitted from the oxidation system may be treated by scrubbing, adsorption, or fume incineration. Liquid solutions would be processed in the liquid waste treatment process.

6.1.1.9 Solidification. A solidification process, with a formulation compatible with the treated waste, could use any of the agents listed.

6.1.1.10 Liquid Waste Treatment. Liquid effluents will be treated using the TRU/Clear system to remove radioactive contamination. Residues will be forwarded to the solidification process.

6.1.1.11 Lead Melting. Lead will be decontaminated by melting and partitioning radionuclides into the slag.

6.1.1.12 Packaging. All waste forms will be packaged into drums or boxes compatible with the disposal site requirements.

6.1.1.13 Assay and Sort. All packages will be assayed to determine TRU content, as well as any other analytical and physical testing dictated by the regulations or waste acceptance requirements. LLW packages will be identified and separated from TRU.

6.1.1.14 Design Assumptions and Boundaries. The following are system-specific design assumptions for 3-IT-8:

- The waste composition is derived from *A Brief Analysis and Description of Transuranic Wastes in the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL*. (Arrenholz and Knight, 1991).
- The mass of the "special items," oversized items, and materials requiring special treatment is assumed to be negligible
- All sorting operations are assumed to be perfect (i.e., no allowance is made for combustibles in the metals or vice versa)
- All wastes are assumed to contain either heavy metals or hazardous organics and will require treatment to meet LDR criteria.

The solidification process will use a 50% waste formulation to meet LDR requirements. One percent of the waste is lead.

6.1.2 System Boundaries

The particular system under consideration is a complete TRU waste retrieval and processing system. It assumes the "start" is the WAG-7 pits and trenches. The processing system, with the exceptions noted below, retrieves the waste, transports it to a processing facility, processes it, and packages it for disposal. The study boundary ends at the assayed and packaged waste. Transportation for disposal is not considered.

The following system boundaries indicate nonprocessed and by-product material streams, which exit the process.

6.1.2.1 Input Interface. The WAG-7 portion of RWMC is within the boundary of this study. All retrieval steps are within the study boundary. A second input is the raw material input to the system. No detail beyond acknowledgement of a need for equipment, utilities, and processing raw materials (such as solidification agents) is provided.

6.1.2.2 Output Interfaces. Soils, including overburden and interstitial soil, will be separated from the TRU waste and processed in the Soils Processing Subsystem. The subsystem will produce clean, unpackaged soil for return to the site, some packaged low-level waste for disposal as LLW, and some TRU soil and sludge. LLW will be separated from TRU waste after treatment rather than before processing.

There will be certain special items retrieved from the buried waste that have a size or nature incompatible with the TRU processing system. Treatment of these items to meet the LDR is outside the scope of this study. The treated and packaged TRU waste is placed in its disposal package and assayed. The boundary of this study is the final assayed waste package. Transportation and disposal costs and considerations are not included.

The oxidation process will have a gaseous release as off-gas. Similarly, the facility HVAC will exhaust filtered air. These two gaseous effluents will be processed to meet the appropriate regulations.

Treated water, of a quality acceptable for process use, will be recovered from the various processing steps. This treated (clean) water will be released from the facility.

Metals will be treated in the Metals Decontamination and Sizing Subsystem. The subsystem outputs include LLW metals, TRU metals, TRU sludge, and clean water. Treated lead, decontaminated adequately for recycling within DOE, will exit the system.

The following list of consolidations is given as a reminder that the function and requirements inherent in this list will influence the process design:

- Security
- Work control/personnel support
- Contaminated maintenance
- Noncontaminated maintenance
- HVAC process
- Fire protection
- Safety (equipment, training)
- Health physics
- Sanitary facilities
- Electrical (including emergency)
- Process control/data logging
- Environmental regulatory reporting/records management
- Criticality control/monitoring
- Radiation instrumentation
- Personnel decontamination
 - Radioactive
 - Hazardous
- Bulk chemical supply/storage

- Storm water runoff control
- Wastewater treatment
 - Hazardous/radioactive
 - Sanitary
- Communications
 - Interior
 - External (public relations)
- Spill or emergency response team
 - Hazardous
 - Radioactive
- Analytical laboratory
- Environmental field sampling team.

6.1.3 Process Functional Diagram

This section describes the remediation concept of the process functional diagram (Figure V-6-1), a system in which the buried waste is treated to meet the requirements of RCRA LDRs using chemical oxidation and solidification. More specifically, large inert items, such as building rubble, are treated or washed to remove hazardous organics. Combustibles, inerts, and sludges are processed through an oxidation system. All treated products and residues are solidified. Metals are processed in the Metal Decontamination and Sizing Subsystem to convert most to LLW or clean metal. LLW is separated from TRU waste after processing.

6.1.4 Facility Description

The facility layout for this drawing is shown in Figure V-6-2. The layout is designed for simple movement of material from receipt to packaged waste treatment. The size of the tankage required for the biological treatment and chemical oxidation will require special considerations for maintenance and operations. The drawing shows operating corridors between the processing lines and an extensive liquid waste treatment capacity.

6.1.5 System Design Requirements

6.1.5.1 General Requirements. Each process subsystem will interface with the original waste material or some intermediate product of another process subsystem. The waste constituents are described briefly in *A Brief Analysis and Description of Transuranic Wastes in the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL* (Arrenholz and Knight, 1991).

The waste handling and treatment systems will be designed in accordance with applicable regulations. Specifically, RCRA places design conditions on storage and treatment systems and performance specifications on incinerator and solidification systems. All equipment will be high-quality, low-maintenance items to keep personnel exposure as low as reasonably achievable. Remote operations will be used to the greatest extent practicable. The facility design will be compatible with DOE Orders, including the DOE Idaho Architectural Engineering Standard and the DOE General Design Criteria Manual (DOE Order 6430.1A).

The TRU waste will meet the appropriate RCRA disposal criteria, the WIPP waste acceptance criteria and TRAMPAC requirements. The treatment objectives for the remediation concept of the process functional diagram (3-IT-8) are to perform the following:

- Separate large inerts so that bioremediation treatment may result in clean inert objects.

NOTES:

- PROCESS CELLS INCLUDE WASTE
- PASSTHROUGH AREAS
- INCINERATOR OFFGAS, CONCENTRATING / DRYER SYSTEMS ARE MULTISTORY
- PERSONNEL & MATERIAL BASINMENT ACCESS & PASSAGE AS REQUIRED
- PROCESS HEPA FILTRATION AT EACH STATION AS REQ'D
- BUILDING VENTILATION FOR HEPA FILTRATION - MINIMIZE DUCT LENGTH
- ADMINISTRATION BUILDING LOCATION IS OPTIONAL

Figure V-6-2. Facility layout for the Chemical Oxidation System with LLW Postsort (3-IT-8).

ADMINISTRATION, ETC.
SEE 3-17-1)

1/Solidification

B 3/11/91		ISSUED FOR REVIEW		J.P. J.M. J.V.		S/mv	
NO.	DATE	REVISION		BY		CHKD./ENGR.	
1	3/3/91	1		J.P.		J.V.	
BY		DATE		BY		DATE	
J.P.		3/3/91		J.V.		3/3/91
INTERNATIONAL TECHNOLOGY CORPORATION ALBUQUERQUE, NEW MEXICO				CONFIDENTIAL PROPERTY OF IT CORPORATION THIS DRAWING AND ALL INFORMATION THEREON IS CONFIDENTIAL AND MUST NOT BE MADE PUBLIC OR COPIED UNLESS AUTHORIZED. SHALL NOT BE USED EXCEPT FOR THE PURPOSE FOR WHICH IT WAS SUPPLIED AND IS SUBJECT TO RETURN ON DEMAND. ALL RIGHTS OF INVENTION OR DESIGN ARE RESERVED.			
EC & G IDAHO, INCORPORATED SYSTEM DESIGN STUDY IDAHO FALLS, IDAHO							
PLANT LAYOUT FOR SYSTEM DESIGN STUDY							
JOB NUMBER		DRAWING NUMBER		REVISION			
351411		3-17-Bc		B			

- Treat TRU combustibles and sludges by chemical oxidation to remove and destroy any organic hazardous constituents. The resulting sludge will be solidified to immobilize the radioactive and heavy metal constituents.
- Decontaminate metals to reduce the mass of material undergoing treatment in the more complex TRU process treatment system. The objective is to reduce metal contamination to a LLW reference level.
- Decontaminate lead to reduce the quantity requiring disposal.

6.1.5.2 Unit Operations Design Requirements. The functional and performance requirements of each of the process subsystems are outlined below. Nominal waste material flow rates and equipment sizing information is shown in Figure V-6-1.

- Open packages and sort: The objective of this process is to remotely separate the waste packages into three categories: inerts and sludges, combustibles, and metals. The process must provide the following:
 - A means for visual and x-ray determination of package contents
 - A remote means for dumping the package contents into the various process line conveyors
 - A sorting line capable of achieving 125% for the maximum design capacity of the four separation categories processing systems
 - Provision for fire suppressions and an inert atmosphere if necessary
 - Integration with the regulatory reporting system.

- Screen: The objective is to separate sludges and small particulates from the large inert items. This process must have the following:
 - A maximum design capacity of 1520 lb/h
 - A capability to process to a nominal size of 1 in.
 - The ability to accommodate an input size with a maximum dimension of 4 ft
 - The ability to be maintained so that an overall on-line operating factor of 70% can be achieved over a one-year period of time
 - Provisions for criticality monitoring and controlling.
- Treatment (large inerts): The objective is to remove light organic constituents by a bioremediation process. The gaseous emissions would be directed to an off-gas treatment system. The system must contain the following:
 - A maximum design capacity of 650 lb/h and the ability to accept items as large as 24 in.
 - The ability to be maintainable so that an overall on-line operating factor of 70% can be achieved over a one-year period of time
 - Provisions for criticality monitoring and control
 - The capability of being compatible with the off-gas treatment process
 - The ability to provide a fully integrated process control/data acquisition/regulatory reporting process.

- Shredder: The objective is to shred combustible materials to a size suitable for the incinerator feed operation. The following requirements are necessary:
 - Must have a maximum capacity of 1740 lb/h
 - Must reduce to a nominal size of 3 in.
 - May use two in-series units
 - Must include remote manipulator systems to feed the shredder
 - Must accommodate an input size up to a 7-ft dimension
 - Output must be compatible with the incinerator feed input
 - Must provide for inerting atmosphere and fire suppression
 - Must be maintainable so that an overall on-line operating factor of 70% can be achieved over a one-year period
 - Must provide for criticality monitoring and control
 - Must have remote package handling capability
 - Must provide for oversize retrieval
 - Must have provisions for handling sticky materials.
- Chemical oxidation: The objective is to chemically oxidize combustible materials before subsequent treatment in a biotreatment reactor or adsorption process. The following requirements are necessary:
 - Must have a maximum capacity of 1740 lb/h

- May use in-series units
 - Must accommodate an input size range of 3 by 3 in.
 - Must have an output compatible with the biotreatment feed input
 - Must be maintainable so that an overall on-line operating factor of 70% can be achieved over a one-year period of time.
- Bioremediation/adsorption: The objective is to oxidize remaining organic constituents in the oxidizables stream. The following are required:
 - Must have a maximum design capacity of 16,600 lb/h
 - Must be maintainable so that an overall on-line operating factor of 70% can be achieved over a one-year period of time
 - Must have provisions for criticality monitoring and control.
- Dewatering system: The objective is to separate sludges from the process stream. Sludge goes to the solidification process while water is further treated in the liquid waste treatment system. The following requirements are necessary:
 - Must have a design capacity of 16,600 lb/h
 - Must be maintainable such that an overall operating factor of 70% can be achieved over a one-year period of time
 - Must have provisions for criticality monitoring and control.
- Off-gas treatment: The objective is to clean the gaseous emissions from the chemical oxidation process to comply with

applicable regulatory requirements. The process must have the following:

- Must be capable of removing 99% of HCl from the gas stream
 - May use any combination of wet/dry process that achieves the treatment standards
 - Must include provisions for removing or incinerating light organics.
- Solidification: The objective is to solidify the treated residues and sludges to immobilize the radioactive and heavy metal constituents. The process must provide for the following:
 - Must accommodate variable solidification formulations (depending on the waste) to meet the appropriate leach test criteria
 - Must have a capacity design maximum throughput of 125% of the combustibles
 - Must accommodate radiation monitoring instrumentation
 - Must be integrated with the regulatory reporting system
 - Must include system clean out provisions.
 - Liquid waste treatment: The objective is to isolate the radioactive constituents and heavy metals in a sludge and produce a clean, treated liquid. The following are required:
 - Must have a capacity design maximum throughput of 125% of the oxidizables processing maximum capacity
 - Must accommodate radioactive monitoring instrumentation

- Lead melting: The objective is to decontaminate lead for reuse and solidify the slag containing radionuclides. The system must perform the following:
 - Accept various shapes and sizes of lead
 - Ensure adequate slagging
 - Ensure nuclide partitioning into slag
 - Adequately solidify slag to meet regulatory requirements.
- Packaging: The objective is to package the fully treated waste forms for transportation and disposal. The process must perform the following:
 - Accept the solidified material from the various solidification process
 - Ensure a dense package filling
 - Allow for package exterior cleaning and decontamination for handling.
- Assay and sort: The objective is to determine the TRU content of the waste packages. This will also include other regulatory requirements for transportation and disposal. The process requires identification of TRU content and fissionable material content.

6.2 SYSTEM ASSESSMENT

6.2.1 Current Status of Unit Operations

6.2.1.1 Open Packages and Sort. There is currently no known remote-manipulator sorting operation for TRU wastes. Manual operations involving the

removal and sorting of TRU wastes were performed at the Rocky Flats Plant in the mid 1980s and again during late 1990 and early 1991. Additionally, remote operations using through-the-wall and crane-mounted manipulators have been used and proven in the nuclear industry for the last 30-40 years but have not been applied to opening TRU waste containers for purposes of sorting waste. Remote manipulator operations have been used in the DOE weapons complex, space nuclear propulsion facilities, and nuclear power plants. When applied to TRU and LLW sorting, the operation and design of these unit operations will be affected by the size and shape of waste containers but not by waste characteristics. Size and capacity are generally not expected to be a problem because large systems have been demonstrated; maintenance can be a problem, but is primarily an engineering challenge.

6.2.1.2 Screens. Screens are commercially available and are commonly used in waste operations to separate small particulate solids from the lighter combustible materials. The fraction of soils to combustible and noncombustible size will influence design and operation. However, it is expected that TRU and LLW have sufficiently similar characteristics to municipal wastes, and application and capacity will not be a problem.

6.2.1.3 Inerts Treatment. Several operations have the potential to treat inert materials. The TRU/Clear process (a potassium ferrate-based chemical formulation) has been shown to remove TRU metals from wastewater streams. If this treatment can be coupled to a soils washing process, a viable unit operation may result. The TRU/Clear process is exclusively licensed to the Analytical Development Corporation, which has stated that the process has been demonstrated to remove TRU metals from aqueous wastewaters to well below present and proposed federal discharge levels. The TRU/Clear process needs to be demonstrated in combination with an inerts washing operation.

Biological treatment has not been demonstrated on wastes and contaminants of this nature. The types of organics involved will determine whether biological treatment will work at all. Biological treatment of chlorinated organics is slow at best. Therefore, considerable development,

and possibly research, will be required before these processes are shown to be viable for treatment of LLW and TRU contaminated soils.

6.2.1.4 Shredder. Shredders of the counter rotation type are installed at the Savannah River Site and were previously installed at PREPP. The PREPP facility at the INEL tested a shredder for feed preparation before incineration/solidification using simulated TRU wastes. In addition, a shredder/compactor also exists at the Tennessee Valley Authority-Watts Bar Nuclear Plant. Other technologies also exist, such as the screw-type auger (KOMAR) shredder, which was tested at PREPP. In general, large shredders have been demonstrated commercially and at municipal waste treatment plants.

Hardened steels and large pieces are difficult to shred. In this PFD, the problem is eliminated by sorting metals. Large pieces will require some size reduction before shredding. Thin, flat material has also been a challenge at times. It is anticipated that shredder maintenance in TRU waste service may present some difficulties. These are primarily engineering challenges, and research and development are not required to place shredders into TRU waste service.

6.2.1.5 Chemical Oxidation. Several types of chemical oxidation may be applicable to LLW and TRU waste. These include acid digestion, supercritical water treatment, and wet oxidation. All technologies have proven useful to some extent on particular contaminated wastes. The acid digestion technology was tested in a Hanford Engineering Development Laboratory demonstration during 1978-1979. At that time, the facility known as RADTU successfully digested 2100 kg of surrogate TRU waste (nonradioactive). This process should, ideally, be used only for oxidizable materials, although the RADTU tests found that some small metal objects were part of the simulated waste and did not seem to perturb the results. Supercritical water and wet oxidation have been demonstrated primarily on organically contaminated aqueous solutions. All of these technologies will need to be demonstrated with actual wastes, and careful scaleup engineering of these processes will be required.

6.2.1.6 Biotreatment/Adsorption. Biotreatment applications as a polishing step for final cleanup is a new application and has not been

demonstrated. Adsorption is widely applied to organically contaminated solutions and is accepted for water treatment systems, particularly groundwater treatment. Biotreatment will require research and development applied to the expected residual wastes from the main processing system. Adsorption technology will require demonstration of specific efficiencies for this application.

6.2.1.7 Off-gas Treatment. The off-gas from the oxidation process will be hot and resemble an incinerator off-gas. Almost all the radioactive waste incinerators worldwide have had off-gas treatment systems to control radioactive or other hazardous material releases, including TRU radionuclides. The type of off-gas system is determined by the amount and type of particulates and halogenated plastics in the feed material. Historically, "wet" off-gas systems have been used, but newer applications are using "dry" scrubbing techniques.

6.2.1.8 Dewatering of Sludges. Wastewater dewatering systems are commonly used and commercially available. In its simplest form, dewatering can be a filter. If the treatment technologies are inefficient, the sludges would be separated using wastewater dewatering systems. The Rocky Flats Plant performs filter pressing of sludges for partial dewatering. Because large-scale dewatering systems are commercially available, research and development is not expected to be required. However, because the precise nature of all the sludges is not known, dewatering system selection requires matching to the sludge characteristics.

6.2.1.9 Liquid Waste Treatment. Several options are available to concentrate solutes and treat liquid wastes. Evaporator/crystallizers are in operation to treat LLW in Spain, Japan, Taiwan, and U.S. nuclear power stations, and have had up to nine years of operations. TRU/Clear appears to be effective in removing alpha-emitting nuclides from aqueous solutions and could be used in conjunction with other unit operations. This process results from research performed at LANL and is now exclusively licensed to the Analytical Development Corporation. Reverse osmosis has been used in some industrial applications and high-level waste evaporators are used at the Hanford Site to solidify high-level tank wastes. In Germany, concentration

and solidification of low-level salt solutions using microwave heating has been demonstrated. Another technique demonstrated in the early 1980s by Rockwell Energy Systems Group is spray drying of baghouse effluents.

Evaporator/crystallizers are well-demonstrated. The TRU/Clear process continues to be demonstrated at LANL and the West Valley Demonstration Project with good results. Although the aqueous wastes from the TRU process are different from those of nuclear power plants, the differences are not expected to impact concentration or treatment operations. Evaporators/crystallizers have been demonstrated up to 30 gal/min while the TRU/Clear process is being demonstrated on a small-scale plant basis. Depending on the process ultimately chosen, some further development and demonstration may be needed to tailor these unit operations to the specific waste forms and chemistry involved.

6.2.1.10 Solidification of Sludges. The cementation of TRU sludges is a proven technology and has been operationally demonstrated at the Rocky Flats Plant. Other solidification operations exist in stationary and mobile form for a variety of wastes. Cementation is the predominant solidification technique being used. Bitumen solidification is being used for processing boric acid concentrates, sodium sulfate concentrates, and spent ion exchange resins from commercial nuclear power plants. Incinerator ash from the INEL WERF incinerator is cemented and meets TCLP requirements. A bitumen solidification process developed and demonstrated in France by CEA has been used for processing French and United States power plant wastes and French military wastes. TVR-III has been used since 1975 to solidify commercial nuclear power plant wastes in the United States.

Cementation and bitumen solidification processes, although operational, should be verified by demonstration with a broader range of compositions to ensure they can meet the LDR requirements. The formulation of cements for longevity is sensitive to waste characteristics and should be specifically demonstrated for the waste characteristics in question.

6.2.1.11 Lead Decontamination. Lead melting equipment and facilities exist commercially and may be adaptable as slagging systems. Contaminated

metals melting was demonstrated at WERF. A lead melting pot is part of this system. Depending on the end result required, this process may be somewhat sensitive to materials other than lead being included in the melt. Also, lead shot (in bags) will have to be separated from the bags, and large pieces may have to be presized. Nuclide partitioning into slag has been demonstrated for other metals, and, although expected, remains to be demonstrated for lead.

6.2.1.12 Melting Metal. Metal melting equipment and facilities exist commercially, including metal refining systems for highly specialized metals products. Contaminated metals melting was demonstrated at WERF. Radionuclide partitioning into slag from the melted metal has been demonstrated, but the specific design of this system and the potential need for further development depends on the output of the Metal Decontamination and Sizing Subsystem. For this study, it has been assumed that only melting of metals into ingots is required; therefore, research, development, or demonstration is required.

Cementitious solidification and vitrification systems are operational, but specific demonstrations for solidifying lead slag do not appear to have been performed. Depending on the solidification process used, other metals in the waste stream can have an adverse effect on solidification. This process will require demonstration and possibly some research and development preceding demonstration before it can become operational.

6.2.2 Program Implementation Risks

This section identifies major concerns associated with program implementation assuming that the Chemical Oxidation/Solidification System with LLW Postsort is selected. Furthermore, risk of accomplishing the program objectives is qualitatively characterized. A summary of results and major areas of concern is shown in Table V-6-1. Program mission and objectives are given in Volume II.

6.2.2.1 Performance Objectives. Baseline cleanup standards for SDA pits and trenches at RWMC cannot be established until an ROD pursuant to the CERCLA process is reached. These standards will be derived ARARs under CERCLA, standards set by risk assessments, and the State and local statutes.

Table V-6-1. 3-II-8 summary of program implementation risks and major areas of concern

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> The three major processes, inert treatment, chemical oxidation, and biotreatment, are immature Ability to define waste characteristics for LDR and provide the EPA specified treatment Alpha cell confinement of radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events 	<ul style="list-style-type: none"> Ability to define and mitigate Pu-contaminated material safety concerns Ability to define and mitigate radioactive, hazardous, toxic, and volatile gases during normal and postulated accident events 	None	<ul style="list-style-type: none"> Prolonged DT&E of treatment, chemical oxidation, and biotreatment processes Prolonged DT&E of the solidification unit operations, primarily because of regulatory compliance Prolonged DT&E, design, and construction of alpha cells Prolonged DT&E, design and construction of remotely operated mechanical equipment 	<ul style="list-style-type: none"> Cost of inert treatment, chemical oxidation, and biotreatment processes cannot be defined until DT&E is complete Uncertainties in defining the cost of the solidification unit operations Alpha cells in a TRU waste environment is a first-of-a-kind design Use of remotely operated mechanical equipment on TRU waste is a first-of-a-kind application

Table V-6-1. (Continued)

Technical	Health and Safety	Institutional	Schedule	Cost
<ul style="list-style-type: none"> • Potential jamming and maloperation of complex mechanical devices and becoming a choking point 				
<ul style="list-style-type: none"> • Dust control during operations in the alpha cells 				
<ul style="list-style-type: none"> • Dust control and equipment decontamination & maintenance Requirements could preclude application of commercially available equipment 				
<ul style="list-style-type: none"> • Solidification process demonstration compliance with rules and regulations 				
High	Moderate	Low	Moderate	High

Since no specific requirements have been formally established at this time, it is assumed that the major ARARs for this system will be RCRA rules, the appropriate NRC regulations and guides, and DOE regulations and Orders.

In the Chemical Oxidation/Solidification System with LLW Postsort, the major uncertainties listed below have been identified as areas of concern in achieving of the performance objectives:

- Lack of development maturity of the major processes: inert treatment, chemical oxidation, and biotreatment. These unit operations require considerable development before becoming operational for the Buried Waste Program. Although some development work has been performed, it is not appropriate for these applications (i.e., chemical oxidation tests conducted at Hanford were with surrogate combustible waste materials).
- The design of off-gas systems requires better knowledge of the oxidation system output using actual TRU waste materials.
- Solidification processes require specific design formulations to provide longevity, low leachability, and LDR compliance. These processes are sensitive to the materials being treated. Because of insufficient data on the input waste characteristics, there are uncertainties regarding the effectiveness of the proposed solidification unit operations.
- Alpha cell designs for normal and postulated accidents. Alpha cells will be needed to contain Pu-contaminated dust and any radioactive, hazardous, toxic, and volatile gases that may become airborne during the waste handling and processing operations. This protection will have to be provided in normal and postulated accident events (e.g., a fire).
- Using commercial equipment in an alpha cell environment and providing ease of decontamination for maintenance. Several of the waste handling operations will use existing technologies that will

have to be adopted for use in an alpha cell environment. This requires remote operation and ease of decontamination for maintenance.

- Potential jamming and maloperation of the complex mechanical components. Also, any of these unit operations could be a potential choke point because of limited prior knowledge of waste streams and the high throughput requirements.
- Large and complex ventilation and filtration systems to control dust during operations in the alpha cells.
- Unreliable operation of some of the equipment in a dusty environment. Dust control in an alpha cell environment and equipment decontamination requirements before maintenance could become limitations in the use of commercially available equipment. DT&E efforts could become more extensive than estimated. Based on the above discussions, it is believed that the overall risk associated with achieving the performance objectives is high.

6.2.2.2 Health and Safety Objectives. The key health and safety objectives for the Buried Waste Program are to (a) identify the hazards of the remedial action operation, and (b) provide measures to eliminate, control, or mitigate identified hazards. In this system, major areas of uncertainty are

- The ability to derive postulated accident events (such as criticality, fire, and unforeseen release of toxic/hazardous material) for the alpha cells.
- The ability to provide mitigation measures to satisfy RCRA, NRC, and DOE requirements. The unit operations associated with opening drums provide unique safety concerns regarding potential for release of toxic, hazardous, and volatile gases.

The uncertainties in regard to health and safety objectives are largely from the inability to characterize the incoming waste. DT&E on

characterization could provide a better confidence level. It is believed that using remote handling equipment and conducting operations inside alpha cells will enhance mitigation measures for a majority of the normal and postulated events. This approach reduces the risk associated with achieving the health and safety objectives. At this stage of the system modeling, it is believed that the overall risk is moderate.

6.2.2.3 Institutional Objectives. A key institutional objective is to involve the public, as required by CERCLA and NEPA, in the process of selecting a remedial action for the Buried Waste Program. Since this system does not involve processes that have historically received low public support, the risk associated with achieving the institutional objective is believed to be low.

6.2.2.4 Schedule Objectives. The objective of the Buried Waste Program schedule is to reach approval for Title II start by mid 1999. This is based on the assumption that an ROD will be reached by the end of FY 2001. The schedule objective for completing the Buried Waste Program remedial action is FY 2019. The following major uncertainties in achieving these objectives have been identified:

- Prolonged DT&E of inert treatment, chemical oxidation, and biotreatment processes are anticipated.
- Prolonged DT&E of solidification processes and development of specific formulations designed to provide longevity, low leachability and LDR compliance.
- Unreliability of the equipment in a dusty environment. Dust control in the alpha cell environment and equipment decontamination requirements before maintenance could become limitations on the application of commercially available equipment. DT&E efforts could become more extensive than estimated.

- The alpha cells are relatively complex first-of-a-kind structures and could be subject to prolonged design and construction. However, with advanced planning, uncertainties of achieving schedule objectives could be reduced.
- Prolonged DT&E, design, and construction of remotely operated mechanical equipment for sorting, conveying, size reduction, etc. Application of this equipment for TRU waste is a first-of-a-kind application. Again, with advanced planning, uncertainties of achieving schedule objectives could be reduced.

It is believed that there may not be adequate time to resolve the above uncertainties and achieve the goals within the timeframe allowed by the schedule objectives. Accordingly, schedule risk is believed to be moderate.

6.2.2.5 Cost Objective. Assessment of the cost objective is a qualitative characterization based on the uncertainties involved in defining a reasonably accurate cost estimate for the system. Some of the major uncertainties are presented below:

- The ability to define the cost of inert treatment, chemical oxidation, and biotreatment processes for application to the Buried Waste Program is questionable. Reliable cost estimates cannot be developed until DT&E on the appropriate unit operations are completed.
- Definition of the cost of the solidification unit operations is anticipated, primarily because of regulatory compliance uncertainties.
- The use of alpha cell in the given waste processing environment is a first-of-a-kind design subject to cost overruns from prolonged design development. Major areas of uncertainty are (a) the extent of design features needed for operating in a dusty environment, (b) providing safety for postulated accident events (such as fire, criticality, and unforeseen release of toxic/hazardous material),

and (c) satisfying RCRA, NRC, and DOE requirements. Currently, the limited information available on waste characteristics contributes to these uncertainties.

- Use of remotely operated mechanical equipment for container opening, sorting, size reduction, and handling of TRU waste is a first-of-a-kind application. Cost uncertainties are anticipated until design, based on DT&E, is well into maturity.

Based on the above discussions, the cost risk is believed to be high.

6.2.3 Unit Operations Pro and Con Analysis

Each of the candidate processes for accomplishing a unit operation has been qualitatively measured against eight criteria: timeliness, availability, completeness, risk, flexibility, cost, safety, and waste reduction. The maximum score possible for any process measured on an evaluation criteria is ten. In some cases, the ability of even the best alternative is such that the highest score is less than ten. Each criteria is given equal weight, so a simple summation of the scores assigned to a candidate process determines the overall score. This score, when compared to the total score of the other candidate processes, determines the selected process.

6.2.3.1 Open Packages and Sort. Two basic processes were considered, remote and contact, as shown in Table V-6-2. The reference systems for this analysis are the manual sorting systems available for LLW at SEG, the glove box sorting line installed at LANL, and the previous drum opening experience at the Rocky Flats Plant. Remote assay equipment is in use at several DOE facilities, including SWEPP. Although the remote handling of the packages after the assay has not been demonstrated, it is assumed that this would be a direct application of available remote equipment.

This analysis favors the remote process for determining the contents of a package before assigning it to the subsequent waste treatment process. Although the remote process system does present increased technical risk and is somewhat less flexible than manual sorting, the safety concerns of manual

Table V-6-2. Open packages and sort packages analysis

	Score	
	<u>Remote</u>	<u>Contact</u>
Timeliness	10	10
Availability	7	10
Completeness	10	7
Risk	5	5
Flexibility	7	6
Cost	10	10
Safety	10	10
Waste reduction	<u>NA</u>	<u>NA</u>
Total	59	48

waste handling and the problems of the inability for dealing with highly radioactive packages are overriding.

6.2.3.2 Inerts Treatment. The options for treatment of organics in large inerts include biological treatments, thermal treatments, and washing/decontamination treatments. Thermal treatments are appropriate, but would represent a costly alternative for a minimal application. Therefore, biological treatment and washing/decontamination alternatives are preferred, if not well developed. Biological treatment of contaminated soils has been used for specific organics, but the large variety of organics in the buried waste is expected to be a problem for biological treatment. Soil washing has been demonstrated in some limited applications and is expected to be more flexible, but not well-developed. Table V-6-3 shows the scores for inerts treatment analysis.

The developmental status of both options limits their scores, but the uncertainty that biological treatment could address the total problem results in poor scores. The washing/decontamination alternative is the superior choice.

Table V-6-3. Inerts treatment analysis

	<u>Score</u>	
	<u>Biological Treatment</u>	<u>Washing/ Decontamination</u>
Timeliness	6	10
Availability	2	8
Completeness	12	8
Risk	2	6
Flexibility	2	6
Cost	2	10
Safety	10	0
Waste reduction	<u>4</u>	<u>8</u>
Total	40	56

6.2.3.3 Shredder. Size reduction of the waste to enable simple subsequent handling can be remotely accomplished with a shredder. There are several types of shredders available in the municipal solid waste industry. Slow-speed rip/tear operations are commonly used, although hammer mills and high-speed chippers are also options. A slow-speed rip/tear system was selected for the PREPP system, and maintenance requirements are a concern. Table V-6-4 assumes that the complete shredder system includes a remote feed system, and a capability to remove oversized and hard objects.

Table V-6-4. Shredder analysis

	<u>Score</u>		
	<u>Rip/Tear</u>	<u>Hammer Mill</u>	<u>Chipper</u>
Timeliness	10	10	10
Availability	10	10	10
Completeness	8	8	8
Risk	10	8	8
Flexibility	8	8	8
Cost	10	10	10
Safety	7	5	5
Waste reduction	<u>10</u>	<u>10</u>	<u>10</u>
Total	73	69	69

waste handling and the problems of the inability for dealing with highly radioactive packages are overriding.

6.2.3.4 Screening. Several commercial systems are available for screening fine sludges and inerts from the course materials. The options available include trommels and rotary screens. A discussion with a supplier of the equipment suggested that the criteria for selection should be based on the size of the application, not on developmental criteria. Based on these criteria, a rotary screen will be used for the analysis. Therefore, scores given for all criteria are 10 except for safety, which is given a score of 7. The safety factor is related to the dusting created by the high-speed systems, and the risk advantage is related to the demonstrated system at PREPP.

6.2.3.5 Chemical Oxidation. Three options are available for this unit operation: wet oxidation, supercritical water oxidation, and acid digestion. Because the waste should consist of solid organics and inerts, there are advantages to wet oxidation and acid digestion. The mechanical problems of using supercritical water in processing solid materials at very high pressures are an extraordinary design problem. Wet oxidation has been demonstrated for organic contamination of waters, and acid digestion has been demonstrated for simulated radioactive waste. These two latter processes are expected to be somewhat similar in equipment costs. Table V-6-5 shows the scores for chemical oxidation analysis.

The mechanical problems and lack of application of supercritical water to the buried waste type of materials result in a poor score for that option. Wet oxidation and acid digestion got similar scores. However, the safety aspects of wet oxidation over acid digestion gave it a slightly favorable score.

6.2.3.6 Biological Treatment/Adsorption. Removal of the residual organic acids and light organics from the oxidation process could be accomplished by adsorption systems, or it could be treated by biological treatment technologies. Because the aqueous wastes from the oxidation process are expected to be heavily loaded with dissolved and undissolved materials, adsorption would be a poor choice. Therefore, biotreatment would probably be

Table V-6-5. Chemical oxidation analysis

	<u>Score</u>		
	<u>Super-Critical Water</u>	<u>Wet Oxidation</u>	<u>Acid Digestion</u>
Timeliness	10	10	10
Availability	1	4	6
Completeness	4	6	6
Risk	2	4	4
Flexibility	2	4	4
Cost	2	6	6
Safety	10	7	3
Waste reduction	<u>6</u>	<u>4</u>	<u>4</u>
Total	37	45	43

pursued, even though significant research and development will be necessary as indicated in Table V-6-6.

Table V-6-6. Biological treatment/absorption analysis

	<u>Score</u>
Timeliness	10
Availability	4
Completeness	5
Flexibility	4
Risk	5
Cost	4
Safety	7
Waste reduction	<u>8</u>
Total	47

6.2.3.7 Dewatering Sludges. Several sludge dewatering techniques are available. Systems employing filter dewatering, such as those employed at the Rocky Flats Plant, and those systems used for wastewater dewatering are

acceptable options. The specific dewatering system that should be employed for TRU sludges is a function of the sludge characteristics rather than the relative characteristics of the dewatering systems themselves. Therefore, the pro/con analysis for the dewatering systems will be performed after the sludge characteristics have been identified. The criteria scores for dewatering system are provided in Table V-6-7.

Table V-6-7. Dewatering analysis

	<u>Score</u>
Timeliness	10
Availability	10
Completeness	10
Flexibility	10
Risk	10
Cost	10
Safety	7
Waste reduction	<u>NA</u>
Total	67

6.2.3.8 Off-gas Treatment. The off-gases from the chemical oxidation process must be treated to remove acid gases and particulate matter. The specific gas treatment is a function of the chemical oxidation process used. Nevertheless, two options are commonly available: wet and dry systems. With the expected amount of acid gases generated by the chlorinated wastes, a wet system (or semidry) is the only option that will meet regulatory requirements. Because wet and semidry systems are similar in chemical and contact mechanisms, no pro/con analysis is warranted. Table V-6-8 shows the off-gas treatment analysis.

6.2.3.9 Solidification. Four alternative solidification agents are listed for solidification of the TRU wastes. Three of these selections use organic solidification agents. Because gas generation from the biological degradation of organics is a concern at WIPP, these agents must be disqualified from consideration at this level of the analysis. Therefore,

Table V-6-8. Off-gas treatment analysis

	<u>Score</u>
Timeliness	10
Availability	6
Completeness	7
Flexibility	8
Risk	7
Cost	4
Safety	7
Waste reduction	<u>NA</u>
Total	49

only Portland cement remains as an alternative for solidification of TRU waste. Criteria scores for solidification are given in Table V-6-9.

Table V-6-9. Solidification analysis

	<u>Score</u>
Timeliness	10
Availability	6
Completeness	7
Flexibility	8
Risk	7
Cost	4
Safety	7
Waste reduction	<u>NA</u>
Total	49

6.2.3.10 Liquid Waste Treatment. Three processes were considered: evaporator/crystallizers, RO, and spray drying. There are several options available to treat liquid wastes. Evaporator/crystallizers are well-demonstrated in the United States and other countries with nuclear industries. High-level waste evaporators are being used at the Hanford Site.

RO is used for some industrial applications, and spray drying of baghouse effluents has also been demonstrated. A process known as TRU/Clear may be an appropriate addition to one or more of these processes but is not considered as a stand-alone process in this analysis. Analysis of the liquid waste treatment is provided in Table V-6-10.

Table V-6-10. Liquid waste treatment

	Score		
	<u>Evaporator/ Crystallizers</u>	<u>Reverse Osmosis</u>	<u>Spray Drying</u>
Timeliness	10	10	10
Availability	10	8	8
Completeness	10	8	10
Risk	10	6	8
Flexibility	10	6	6
Cost	10	8	8
Safety		10	8
Waste reduction	<u>NA</u>	<u>NA</u>	<u>NA</u>
Total	60	56	58

The availability of radioactive waste evaporators from commercial sources gives that option a strong advantage over the other proven, but not applied, technologies.

6.2.3.11 Melt Metal. The output of the Metal Decontamination and Sizing Subsystem will determine the need to either further decontaminate TRU metals or to melt the metal into ingots for disposal. Further decontamination may require melting and radionuclide partitioning into slag. If only surface reduction is required, the metal will be melted and formed into ingots. For this study, the latter is assumed and no pro/con analysis is warranted. An analysis of melt metal is given in Table V-6-11.

6.2.3.12 Lead Decontamination. Two technologies have been proposed for lead treatment, microencapsulation, and decontamination by melting in the

Table V-6-11. Metal/melt analysis

	<u>Score</u>
Timeliness	10
Availability	8
Completeness	6
Flexibility	8
Risk	8
Cost	6
Safety	10
Waste reduction	<u>8</u>
Total	64

presence of a slagging agent. The known encapsulation techniques will not meet the TCLP criteria when the sample is crushed, as the test requires. It is known that some successful development work was carried out on lead melting at the INEL. On this basis, only one candidate process was scored (see Table V-6-12).

Table V-6-12. Lead decontamination analysis

	<u>Score</u>
Timeliness	10
Availability	8
Completeness	10
Flexibility	7
Risk	10
Cost	7
Safety	9
Waste reduction	<u>10</u>
Total	71

6.2.3.13 Assay and Sort. Assay systems have been operational for some time and are well-developed. Because current design represents industry standards, no pro/con analysis is necessary.

6.2.4 Unit Operation Lead-Time Estimates

Table V-6-13 depicts the lead-times for each unit operation included in this system.

6.2.5 Rough Order of Magnitude Cost Estimates

This section presents four categories of cost estimates: research and development, demonstration, capital costs, and operations. Table V-6-14 gives the estimated cost breakdown for these categories.

6.2.5.1 Demonstration, Testing, and Evaluation Costs. The research and development cost estimates are based on the lead-time estimates in the previous section. The lead-time estimates were developed on a unit operation-by-unit operation basis allowing for research, development, and demonstration periods. The research schedule is assumed to include bench-scale research studies and small-scale process studies. The development phase is assumed to represent pilot-plant studies of specific processes or mockups of specific mechanical components. Demonstration projects were assumed to be nonradioactive production-scale tests of complete unit operations or combinations of unit operations.

The unit operations on this process flow diagram include several processes that are expected to require substantial research, development, and demonstration. The washing system for inerts treatment could be developed using the technology of the TRU/Clear process, or it could identify new radionuclide leaching solutions. Either concept should be evaluated in a research program. Similarly, the chemical oxidation system and biotreatment systems would require research programs. All three programs would then benefit from a pilot-plant development program of similar cost.

The following assumptions were used to arrive at a research and development cost estimate:

Table V-6-13. DT&E assessment summary for the Chemical Oxidation/Solidification System with LLW Postsort (3-IT-8)

DT&E Step Unit	Primary paper evaluation		Bench-scale studies		Secondary paper evaluation		Pilot-Plant/Mock-up Test studies		Total Duration
	Required	Duration	Required	Duration	Required	Duration	Required	Duration	
Operation									
Open Package & Sort	Yes	6 Months	No		No		Yes	24 Months	30 Months
Screenings									
	Yes	6 Months	No		No		Yes	24 Months	30 Months
Inert Treatment	Yes	6 Months	Yes	18 Months	Yes	6 Months	Yes	12 Months	42 Months
Shredder	Yes	6 Months	No		No		Yes	18 Months	24 Months
Chemical Oxidation	Yes	6 Months	Yes	18 Months	Yes	6 Months	Yes	42 Months	* 54 Months
Bioreact/Adsorption	Yes	6 Months	Yes	18 Months	Yes	6 Months	Yes	42 Months	* 54 Months
Off-Gas Treatment	Yes	6 Months	No		No		Yes	12 Months	18 Months
Solidification (Sludge)	Yes	6 Months	No		No		Yes	18 Months	24 Months
Dewatering Sludge	Yes	6 Months	No		No		Yes	12 Months	18 Months
Liquid Waste Treatment	Yes	6 Months	Yes	9 Months	Yes	6 Months	Yes	12 Months	33 Months
Lead Decontamination	Yes	6 Months	Yes	10 Months	Yes	6 Months	Yes	26 Months	48 Months
Melting Metal	Yes	6 Months	No		No		Yes	12 Months	18 Months

* Some activities in DT&E can be performed simultaneously.

Table V-6-14. Rough order of magnitude cost estimates (3-IT-8)^a

Cost Code	Cost Items	Normalized Cost (\$x1000)	Modified Cost (\$x1000)
1.0	Studies and bench scale costs		
1.1	Manpower costs during research	\$17,100	\$17,100
1.2	Equipment costs	\$2,900	\$2,900
1.3	Installation costs	\$11,100	\$11,100
1.4	Contingency	\$7,775	\$7,775
	Subtotal 1.0	\$38,875	\$38,875
2.0	Demonstration costs		
2.1	Manpower cost during construction	\$3,435	\$3,435
2.2	Design cost (30% of 2.5)	\$8,588	\$8,588
2.3	Inspection cost (7% of 2.5)	\$2,004	\$2,004
2.4	Project administration (10% of 2.5)	\$2,863	\$2,863
2.5	Construction cost		
2.5.1	Building structure costs	\$15,341	\$15,341
2.5.2	Equipment costs	\$7,289	\$7,289
2.5.3	Indirect (20.9% of 2.5)	\$5,997	\$5,997
	Subtotal of 2.5	\$28,627	\$28,627
2.6	Construction management costs (27.8% of 2.5)	\$8,216	\$8,216
2.7	Contingency	\$13,433	\$13,433
	Subtotal 2.0	\$67,166	\$67,166
3.0	Production construction costs		
3.1	Design cost (30% of 3.4)	\$50,041	\$41,522
3.2	Inspection cost (7% of 3.4)	\$11,676	\$9,688
3.3	Project administration (10% of 3.4)	\$16,680	\$13,841
3.4	Construction cost		
3.4.1	Building structure costs	\$115,114	\$92,665
3.4.2	Equipment costs	\$16,747	\$16,747
3.4.3	Indirect (20.9% of 3.4)	\$34,943	\$28,994
	Subtotal of 3.4	\$166,804	\$138,406
3.5	Construction management costs and construction management reserve (26.5% of 3.4)	\$47,873	\$39,723
3.6	Contingency (25% of 3.1 through 3.5)	\$73,269	\$60,795
	Subtotal 3.0	\$366,343	\$303,974
	Total Capital Cost (1.0, 2.0, and 3.0)	\$472,384	\$410,015
4.0	Annual operating and maintenance costs		
4.1	Operating costs	\$15,966	\$15,966
4.2	Utility costs	\$336	\$336
4.3	Material costs	\$1,060	\$1,060
4.4	Maintenance costs	\$1,055	\$1,055
4.5	Contingency	\$4,604	\$4,604
	Subtotal 4.0	\$23,021	\$23,021
TOTAL	10 Years Operating and Maintenance Costs		\$230,213

a. Does not include the appropriate subsystem costs (see Volume VII for subsystem costs).

- A laboratory program would be required to establish the distribution coefficients and select the appropriate slagging agents for lead treatment. The resulting slag would then be combined with solidification agents to ensure leach test compliance. The research program is expected to require only a few people, but analytical charges will be significant.
- The washing/decontamination system for inerts treatment would require a more substantial research effort and a larger pilot-plant effort to confirm the laboratory results. It is expected that four technical personnel would be involved in the research program. As in many of these programs, the analytical chemistry costs are expected to be significant.
- The chemical oxidation research program will be similar to that of the washing system, and a lengthy pilot-plant test will be required to confirm the operability on simulated, nonradioactive waste. The research program is estimated to require 6 persons, and the pilot plant development program will require 15.
- The biological waste treatment process is expected to be the most challenging of those in this system. It would be necessary to develop special microbes to address the wide mixture of wastes expected in the buried waste. The microbe research is very expensive. Similarly, the pilot-plant development testing would be expensive to confirm or further develop the technology. The research program is estimated to require more expensive equipment than the other programs and a total of 10 scientists and technicians. The development program is estimated to require 12 personnel.
- After the waste treatment process is developed, at least on a bench scale, it will be necessary to confirm the applicability of the liquid waste treatment purification technologies. The TRU/Clear process is a candidate for this task, but both bench-scale and pilot-scale confirmation would be required to

ensure applicability to this process. This pilot program is estimated to require a staff of five.

- The use of solidification agents to immobilize waste is reasonably well-developed. However, a laboratory program is required to confirm the exact formulations to meet the leach test criteria. The laboratory effort is relatively small, but analytical costs are assumed to be high. This effort would require a staff of three chemists and technicians. The one-year program recognizes the typical delays in analytical results.
- The following costing assumptions were made:
 - The engineering of this small equipment will equal the procured equipment cost
 - The average fully-loaded cost for manpower (all grades) is \$50/h.

6.2.5.2 Demonstration Costs. Because of the research nature of the processes in this PFD, extensive demonstration of the integrated system would be required to ensure safe and effective operation of the facility. This integrated test would easily equal the cost of several larger DOE demonstration programs. The capital cost assumptions were as follows:

- A 1/4 full-scale, nonradioactive development system would be constructed from the ground up
- The entire system will require mock-up.

6.2.5.3 Capital Costs. The capital cost estimates were developed using the following methodology:

- Equipment costs were obtained from four sources: vendor estimates of these components or similar components, engineering estimates,

handbook and literature information, and file information on purchased equipment.

- Building costs were estimated from the layout drawings developed in the F&OR sections. These layouts and the areas calculated in the layouts were used to determine moderate hazard areas and alpha containment areas. These building space costs were estimated on the basis of \$350 and \$1000 ft², respectively.
- Equipment costs for unit operations of similar capacity were scaled according to the $X^{0.6}$ rule, where X equals the capacity to correct costs for the appropriate capacity.
- Standard handbook information was used to scale the purchased equipment costs to installed equipment costs. These factors include installation, field engineering, and fees. For facilities of this type, the overall factor assumed was approximately four (Perry and Chilton, 1973).

Another applicable assumption is that the costs of offices and nonprocessing areas of the facility were not calculated. Stainless steel equipment was generally costed to allow for easy decontamination and maintenance, even when materials considerations indicated cheaper construction would be appropriate. This generally resulted in assuming the most expensive equipment or factors.

The calculated alpha cell containment area is 92,600 ft², and the moderate hazard area is 82,700 ft². The resulting building cost is then \$115,100,000. The cost of the installed processing equipment is estimated to be \$16,800,000. These costs led to a calculated facility cost of approximately \$472,400,000.

6.2.5.4 Operating Costs. Four subcategories of costs were included as operating costs: operating labor, maintenance (5% of equipment), utilities (estimated from mass and energy balance information), and raw material costs (such as Portland cement).

6.2.6 System Evaluation Results

This section provides an overall evaluation of the system, including any clear advantages or disadvantages, a subjective numerical measure of the system's overall efficacy relative to other systems studied, and a summary of research and development needs.

6.2.6.1 Identification of Major Considerations. Approximately one-third of the major unit operations within this system will require DT&E. As a result, it will probably require about five to six years before these unit operations have been demonstrated for use in the facility. It appears that DT&E will be required for the inerts treatment, chemical oxidation, biotreatment/adsorption, liquid waste treatment, and lead decontamination unit operations. Some additional development will be required for solidification of sludges. In general, the integration of the unit operations into a viable waste treatment facility seems to be well within the capabilities of the architect/engineering and chemical plant industries. This is a distinct advantage. However, the application of chemical oxidation and biotreatment techniques may complicate the integration of unit operations from the standpoint of waste and product flow through the system. Oxidation and biotreatment are typically slower processes than incineration, for example.

By not presorting LLW, the higher volume of waste processed by the common system will require a larger waste processing line designed to the more stringent requirements of a TRU waste processing facility. The larger TRU facility also has some safety disadvantages over a smaller TRU line. The volume of waste that will be disposed in a TRU geologic repository is likely to be higher than if LLW was presorted before process. This disadvantage might be minimized by using a campaign approach to process TRU and LLW through the facility. However, campaigning may require a large receiving and storage area. Another disadvantage identified during the course of the study pertains to the effect of changing regulatory climates on the off-gas and solidification operations. The tendency toward more stringent requirements may produce regulatory uncertainties that must be recognized during the facility planning stage.

Table V-6-15. Rating performance measureables for the Chemical Oxidation/Solidification System with LLW Postsort (3-IT-8)

Measurable	Open Packages and Sort	Screen	Inerts Treatments	Shredder	Chemical Oxidation	Biotreat/ Adsorption	Dewatering (sludges)	Off-gas Treatment	Solidification	Liquid Waste Treatment	Melt Metal	Lead Decon.	Assay and Sort	Total
Timeliness	10	10	10	10	10	10	10	10	10	10	10	10	10	130
Availability	7	10	8	10	4	4	10	6	8	10	10	8	10	105
Completeness	10	10	8	8	6	5	10	7	6	10	8	10	10	108
Risk	5	10	6	10	4	4	10	8	8	10	10	7	10	102
Flexibility	7	10	6	8	4	5	10	7	8	10	10	10	10	105
Cost	10	10	6	10	6	4	10	4	6	10	7	7	10	100
Safety	10	7	10	7	7	7	7	7	10	10	10	9	10	111
Waste reduction	NA	10	8	10	4	5	NA	NA	8	10	10	10	NA	162
Totals	59	77	62	73	45	44	67	49	64	70	75	71	70	923

If only the major process systems had been given scores, the Chemical Oxidation/Solidification System would have scored considerably lower than is implied by the overall system scores above. Therefore, on the basis of these very subjective scores, the thermal treatment systems appear to be the most viable.

6.2.7 Summary of Demonstration, Testing, and Evaluation Needs

This system is expected to require research and development for the unit operations shown in Table V-6-16.

6.3 RECOMMENDATION FOR THE SYSTEM

A key advantage of the system is that it does not use thermal processes and therefore may receive more public support. However, the system tends to require a significant amount of DT&E. The major unit operations require research and development before operational demonstrations can be started. Another disadvantage pertains to the processing of LLW with TRU waste, thereby increasing the amount of waste shipped to the TRU geologic repository for disposal. This concept also requires the entire system to be designed to alpha confinement criteria.

There are also advantages to this system. By not presorting LLW before processing, an entire separate LLW processing line can be eliminated. Whereas processing all the waste together has disadvantages, this might be overcome by campaigning the waste through the facility. By not mixing LLW with TRU waste before processing, it may be possible to minimize the amount of waste shipped to the TRU geologic repository. In addition, the implementation of this system eliminates some of the unit operations associated with thermal treatment, which involve regulatory uncertainties.

Nevertheless, the disadvantages appear to outweigh the advantages, and this system is not as viable as the thermal treatment systems studied. It should be recognized, however, that this conclusion is based on the results of a very preliminary study. There are many potential considerations that cannot be uncovered until these systems have been evaluated in more detail.

Table V-6-16. DT&E needs for the Chemical Oxidation/Solidification System with LLW Postsort (3-IT-8)

<u>Unit Operation</u>	<u>Technology Development Status</u>	<u>DT&E</u>
Open packages and sort	<ul style="list-style-type: none"> • Individual operations available 	<ul style="list-style-type: none"> • Integrated systems demonstrated
Screens	<ul style="list-style-type: none"> • Commercially available 	<ul style="list-style-type: none"> • Engineering only • Vendor demonstration
Inerts treatment	<ul style="list-style-type: none"> • Promising technologies available but not demonstrated for this application 	<ul style="list-style-type: none"> • Demonstration with some possible development to tailor process • Test and evaluation
Shredder	<ul style="list-style-type: none"> • Commercially available 	<ul style="list-style-type: none"> • Engineering only • Vendor demonstration
Chemical oxidation	<ul style="list-style-type: none"> • Acid digestion supercritical water, and wet oxidation partially proven for other applications 	<ul style="list-style-type: none"> • Development and scaleup needed • Test and evaluation
Biotreatment adsorption	<ul style="list-style-type: none"> • Biotreatment is a new process for this application • Adsorption widely applied to organically contaminated solution 	<ul style="list-style-type: none"> • Research with various bacteria plus engineering development • Adsorber demonstrations for specific effluents • Test and evaluation
Off-gas treatment	<ul style="list-style-type: none"> • Well developed and commercially available 	<ul style="list-style-type: none"> • Demonstration of effectiveness for specific effluents
Dewatering sludges	<ul style="list-style-type: none"> • Filter and wastewater dewatering systems commercially available 	<ul style="list-style-type: none"> • Demonstrate dewatering effectiveness for specific sludge
Liquid waste treatment	<ul style="list-style-type: none"> • Reverse osmosis, evaporators, and crystallizers available • TRU/Clear process shows promise 	<ul style="list-style-type: none"> • Development to tailor operation to specific waste and chemistry • Test and evaluation
Solidification of sludges and ash	<ul style="list-style-type: none"> • Solidification technologies being used for nuclear wastes 	<ul style="list-style-type: none"> • Development of formulations for specific waste forms • Vendor demonstration
Melting of lead	<ul style="list-style-type: none"> • Lead melting equipment available. Nuclide partitioning from other metals has been demonstrated 	<ul style="list-style-type: none"> • Demonstration of low leaching form that can pass TCLP • Demonstration of lead slag solidification using current methods
Melting metal	<ul style="list-style-type: none"> • Melting equipment available. Nuclide partitioning into slag has been demonstrated 	<ul style="list-style-type: none"> • Vendor demonstration

7. BIBLIOGRAPHY

- Arrenholz, D. A., 1990, *In Situ Vittrification Program Treatability Investigation Program Report*, EGG-WTD-9383, December.
- Arrenholz, D. A., and J. L. Knight, 1991, *A Brief Analysis and Description of Transuranic Wastes in the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL*, EGG-WTD-9438, February.
- AWC Inc., 1989, *TRU Clean: A Process for Decontaminating Radioactive and Hazardous Soils*.
- Boehmer, A. M., et al., 1986, "Solidification of Hazardous and Mixed Radioactive Waste at the Idaho National Engineering Laboratory," *Proceedings of the 1986 Symposium on Waste Management, Tucson, Arizona, March*.
- Borham, B. M., et al., 1986, "Handling of Transuranic Waste for Volume Reduction by Incineration," *Proceedings of the 1986 Symposium on Waste Management, Tucson, Arizona, March*.
- Bowen, M. D., et al., 1978, "A Vertical-Bed Pyrolysis System, Solid Waste and Residues Conversion by Advanced Thermal Processes," *175th Meeting of the American Chemical Society, Anaheim, California, March 13-17*.
- Bramlitt, E. T., 1988, "Plutonium Mining for Cleanup," *Health Physics*, 55, 2, August, pp. 451-453.
- Cleveland, J. M., 1970, *The Chemistry of Plutonium*, Garden and Breech Publications: New York, pp. 48-61.
- Cwynar, J. C., et al., 1986, "Retrofit and Operation of Low-level Radwaste Solidification System," *Proceedings of the 1986 Symposium on Waste Management, Tucson, Arizona, March*.
- Deininger, J. P., 1990, "Developments in Transuranic Element Polishing from Radioactive Wastewaters Using Ferrate Chemical Technology," *Waste Management '90 Conference, Tucson, Arizona, March*.
- Edinburgh, C. R., 1990, *Processing Criteria for TRU Removal from RWMC Stored Waste*, ERDP 2802, August 15.
- EPA, 1989, *Guide for Conducting Treatability Studies Under CERCLA*, EPA/540/2-89/058, December.
- Francis, C. J., and T. M. Starr, 1990, "The ANF LLW Incinerator Design & Start-Up," *Fourth Annual Symposium on Incineration of Industrial Wastes, Knoxville, Tennessee*.

- Freeman, H. M., 1989, *Standard Handbook of Hazardous Waste Treatment and Disposal*, McGraw Hill: New York.
- Geosafe Corporation, 1989, *Application and Evaluation Considerations for In Situ Vitrification Technology: A Treatment Process for Destruction and/or Permanent Immobilization of Hazardous Materials*, GSC 1901, April.
- Jessop, D., et al., 1986, "Design, Installation, Testing and Start-up of a Material Handling System at the West Valley Demonstration Project," *Proceedings of the 1986 Symposium on Waste Management, Tucson, Arizona, March*.
- Koegler, S. S., R. K. Farnsworth, R. K. Nakaoka, and S. O. Bates, 1989, *Vitrification Technologies for Weldon Spring Raffinate Sludges and Contaminated Soils Phase 2 Report: Screening of Alternatives*, PNL-7125, November.
- Nielson, R. K., et al., 1989, "Low Temperature Thermal Treatment of Volatile Organic Compounds," *1989 Incineration Conference, Knoxville, Tennessee, May*.
- Palmer, C. A., 1989, "X-TRAX Y-12 Sludge Detoxification Demonstration," *1989 Incineration Conference for Chemical Waste Management, Knoxville, Tennessee, May*.
- Penberthy, H. L., 1990, *Full Scale Demonstrating In Situ Vitrification Showing the Fatal Flaw Which is Called Vapor Retreat*, June.
- Perry, R. H., and C. H. Chilton (eds.), 1973, *Perry's Chemical Engineer's Handbook*, Fifth Edition, Table 25-50.
- Peters, M. S., and K. Timmerhaus, 1990, *Plant Design and Economics for Chemical Engineers*, 4th edition, New York: McGraw-Hill.
- Stewart, J. A., and D. L. Charlesworth, 1986, "Design and Operation of a Remotely Operated Plutonium Waste Size Reduction and Material Handling Process," *Waste Management-'86, Proceedings of the Symposium on Waste Management at Tucson, Arizona, March 2-6*.
- Theodore, L., and T. Reynolds, 1987, *Introduction to Hazardous Waste Incineration*, Wiley-Interscience.
- Vietzke, H., *Minimizing of Organic Waste by Pyrohydrolysis*.
- Wheelwright, E. J., L. A. Bray, and J. L. Ryan, 1987, *Development of the CEPOD Process for Dissolving Plutonium Oxide and Leaching Plutonium from Scrap or Wastes*, PN-6483.

END

**DATE
FILMED**

6 / 15 / 92