DOE/PC/91345--T3

JAN 25 1992

DOE/PC/91345--T3

DE92 009475

A NOVEL CARBON-BASED PROCESS FOR FLUE GAS CLEANUP

**Second Quarterly Technical Progress Report
October 1 to December 31, 1991**

**Contract No. DE-AC21-91PC91345
Ms. Diane Revay Madden: DOE COR**

Submitted to:

**U.S. Department of Energy
Pittsburgh Energy Technology Center
P.O. Box 10940, Pittsburgh, PA 15236**

**S.K. Gangwal, Project Manager
Research Triangle Institute
Research Triangle Park, NC 27709
(919) 541-8033**

**P.L. Silveston, Co-Principal Investigator
University of Waterloo
Waterloo, Ontario, Canada N2L3G1
(519) 885-1211, EXT. 2534**

January 1992

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TABLE OF CONTENTS

LIST OF TABLES AND FIGURES	ii
ABSTRACT	iii
1.0 INTRODUCTION	1
1.1 OBJECTIVE	1
1.2 PROCESS DESCRIPTION	1
1.3 BACKGROUND	1
1.4 PROJECT SCOPE/SCHEDULE	4
1.5 MEASURES OF SUCCESS	6
2.0 WORK COMPLETED IN PREVIOUS QUARTER	7
3.0 WORK COMPLETED IN PRESENT QUARTER	8
3.1 ACCOMPLISHMENTS	8
3.2 SO ₂ REMOVAL	8
3.2.1 Equipment Modifications	8
3.2.2 Experimental Work	8
3.3 NO _x REMOVAL	11
3.3.1 Experimental Modifications	11
3.3.2 Experimental Work	12
4.0 WORK PLANNED FOR NEXT QUARTER	19
4.1 SO ₂ REMOVAL	19
4.2 NO _x REMOVAL	19
5.0 REFERENCES	20

TABLES

	<u>Page</u>
Table 1 Advantages of Process	2
Table 2 Common Experimental Conditions for SO ₂ Removal Experiments with Periodic Flushing	10
Table 3 Initial SO ₂ Removal Experiments	11
Table 4 Low Flow SO ₂ Removal Experiments	12
Table 5 Common Experimental Conditions for NO _x Conversion Tests	13
Table 6 Shakedown Test Results for NO _x Conversion	14
Table 7 NO _x Conversion Test Results	15
Table 8 First Order Rate Constants for NO _x Conversion on 1% Pt/Carbon Catalyst	17

FIGURES

Figure 1 Flue Gas Cleanup Process Concept	2
Figure 2 Multi-Bed Periodic-Flushing Sulfuric Acid Production from Flue Gas	3
Figure 3 Apparatus for SO ₂ Removal	9
Figure 4 First Order Rate Constant Arrhenius Plot for NO Reduction with NH ₃ on Degussa 1% Pt/Carbon Catalyst	18

ABSTRACT

The objective of this project is to demonstrate the preliminary technical and economic feasibility of a novel carbon-based process for removal of at least 95 % SO_2 and at least 75 % NO_x from coal combustion flue gas. In the process, flue gas leaving the electrostatic precipitator (ESP) is passed through a trickle bed of activated carbon catalyst employing a periodic flush of low strength sulfuric acid. The SO_2 is oxidized to SO_3 and removed as medium strength sulfuric acid. The SO_2 -free flue gas is then mixed with NH_3 , and the NO_x in the gas is subjected to selective catalytic reduction (SCR) to N_2 over a fixed-bed of activated carbon catalyst.

The project is being carried out over 14 months (June 4, 1991 to July 31, 1992). The experimental work is divided between Research Triangle Institute (RTI) and the University of Waterloo (Waterloo). RTI will conduct the NO_x removal studies, whereas Waterloo will conduct the SO_2 removal studies. The ultimate goal of the project is to demonstrate that the process can reduce the cost of electricity by 20% over conventional SCR/flue gas desulfurization (FGD) processes.

In the previous quarter, a detailed project management plan was prepared describing the experimental set-up, work plan and test plan. The experimental equipment was nearly constructed. Also, a paper was prepared and presented for the Seventh Annual Contractor's Conference.

In the present quarter, the experimental system, with the exception of a continuous SO_2 analyzer at Waterloo, were completed for SO_2 conversion at Waterloo and for NO_x conversion at RTI. Shakedown experiments were completed. Scoping studies at Waterloo showed that 100% SO_2 removal could be achieved by continuous flow of water and gas through the activated carbon catalyst at 21°C . Periodic flushing tests with a 15 to 30 minute cycle time and 3 minutes flush time on the other hand could only achieve up to 40% removal. NO_x conversion tests at RTI showed that at about 130°C , 75% conversion could be achieved at a space velocity of about 700 scc/(cc·h).

Work in the next quarter will include installation of the continuous SO_2 analyzer at Waterloo, optimization of cycle and flush time to achieve optimum SO_2 conversion, investigation of the effect of temperature on the SO_2 removal at RTI, investigation of other candidate NO_x conversion catalysts at RTI, and optimization of NO_x conversion to achieve 75% conversion with less than 25 ppmv ammonia slip.

1.0 INTRODUCTION

1.1 OBJECTIVE

The objective of this project is to demonstrate the preliminary technical and economic feasibility of a novel carbon-based process for removal of at least 95% SO₂ and at least 75% NO_x from coal combustion flue gas. The process is based on the demonstrated ability of activated carbons to catalyze SO₂ oxidation and NO_x reduction below 150°C.

1.2 PROCESS DESCRIPTION

The process concept is shown in Figure 1. The hot flue gas leaves the ESP at ~150°C and enters a recuperative gas-gas heat exchanger, employing a bed of ceramic balls, to cool the flue gas for SO₂ removal and simultaneously heat the cold flue gas for NO_x removal. The gas leaving the exchanger enters a series of two to three activated carbon trickle-bed catalytic reactors at approximately 100°C to remove the SO₂ and convert it to medium strength sulfuric acid. The essentially SO₂-free gas from the last trickle bed goes through the exchanger to the NO_x converter. The required amount of NH₃ (typically in a NO_x/NH₃ mole ratio of 1) is mixed with the flue gas prior to the activated carbon catalyst bed. The advantages of the proposed process concept compared to currently available SO₂/NO_x processes are summarized in Table 1.

1.3 BACKGROUND

The SO₂ removal process proposed herein is based on the well-known low-temperature catalytic properties of activated carbon, but uses a novel periodically flushed trickle bed to produce a strong acid and a low level of SO₂ in the gas discharge. Hartman et al. (1971) and Hartman and Coughlin (1973) provide a detailed description of the mechanism of SO₂ oxidation [$\text{SO}_2 + (1/2)\text{O}_2 \rightarrow \text{SO}_3$ or $\text{SO}_2 + (1/2)\text{O}_2 + \text{H}_2\text{O} \rightarrow \text{H}_2\text{SO}_4$] over activated carbon. The SO₃ formed does not desorb spontaneously at low temperature. It is desorbed with water as sulfuric acid. Sulfuric acid, however, suppresses the ionization of dissolved sulfur dioxide and solubility of oxygen so that countercurrent contacting must be used to continue the reaction at an appreciable rate. Acid formation is accomplished in our process by periodic flushing, which results in a lower pressure drop and more concentrated sulfuric acid than achievable by continuous flushing.

Work in the co-principal investigator's laboratory at the University of Waterloo (Haure et al. 1989) has shown the feasibility of the process. With a single bed and periodic water flushing (0.9 minute water flow in every 90 minute cycle), a time averaged acid concentration of nearly 0.2 molar was achieved. Based on this result, a conceptual process employing acid recycle to produce medium strength sulfuric acid is shown in Figure 2. SO₂ is absorbed from the gas phase and converted into sulfuric acid by two to three in-line periodically liquid-pulsed beds of carbon. Typically water, dilute strength acid or medium

Figure 1. Flue gas cleanup process concept.

TABLE 1. ADVANTAGES OF PROCESS

SO₂ Removal

• Easier retrofit	- Downstream of ESP where space is more readily available
• No waste product	- Sulfuric acid is potentially marketable
• Low temperature	- Reduced equipment stress, non energy intensive, no hazards including carbon combustion
• Simple regeneration	- No carbon loss
• Periodic Operation	- Low pressure drop, concentrated sulfuric acid

NO_x Removal

• High Catalyst Life	- Low temperature operation in the absence of SO ₂ and particles significantly increases catalyst life.
• Low Salt/SO ₃ formation	- Due to complete SO ₂ removal upstream, the acid dew point of the gas is very low and salt formation is avoided.

**Figure 2. Multi-Bed Periodic-Flushing
Sulfuric Acid Production from Flue Gas**

strength acid flows through them for 2 to 4 minutes in every 30 to 40 minutes cycle. The gas phase flows through the beds continuously. Co-current flow is employed so that high superficial velocities can be used without flooding. Two to three in-line, co-current trickle beds of sufficient depth should provide complete removal of SO_2 . The recycling arrangement passes the strongest acid through the bed, treating the richest gas, and thereby produces medium strength acid as a product. The gas-gas heat exchanger brings the flue gas leaving the third bed to the desired temperature for catalytic NO_x removal, which is the second part of our process, as shown previously in Figure 1.

NO_x is reduced in a separate reactor at 120°C using NH_3 after the SO_2 has been removed, and the N_2 and H_2O are vented to the stack. One possible reaction is $4\text{NH}_3 + 4\text{NO} + \text{O}_2 \rightarrow 4\text{N}_2 + 6\text{H}_2\text{O}$, although many others are possible. Many catalysts for the NH_3 - NO reaction are reported in the literature (commercially practiced in SCR technology using vanadium based catalysts). However, many of these catalysts are inactive at 120°C . A comprehensive unpublished review of the literature by the principal investigators indicated that activated carbon or "coke" catalysts are the only catalysts with a potential to carry out the reaction at 120°C . Such catalysts are commercially used in the Mitsui process, which claims some 85% NO_x removal at 130°C . A number of studies (Kusakabe et al. 1988, Kuehl et al. 1986, Seki et al. 1975, U.S. Patent 4,194,373, Kareko et al. 1988) corroborate that activated carbons are active low temperature catalysts for the NO - NH_3 - O_2 and NO - NH_3 reactions. These studies further suggest that activated carbons promoted with very small quantities of group VIII transition metals (particularly platinum) should be considered.

1.4 PROJECT SCOPE/SCHEDULE

The novel carbon-based process to be studied has the potential to provide a technically sound and economically attractive solution to flue gas cleanup. The SO_2 removal experiments will be carried out in the apparatus of Haure et al. (1989) at Waterloo, modified to handle dilute to medium strength sulfuric acid and temperatures up to 100°C . The questions to be addressed in the research include:

- What acid concentrations are attainable by periodic pulsing and acid recycle?
- What is the pressure drop as a function of time during a cycle of no liquid flow to liquid flow?
- What is the optimum size of the granular activated carbon?
- What is the optimum pulse length to prevent poisoning (as occurring in steady state operation) of the activated carbon?
- What is the optimal temperature of operation?
- What will be the effect and fate of NO_x ?

The experimental parameters investigated will include carbon type, size, bed depth, gas composition, liquid composition, gas velocity, liquid velocity, cycle time, flush time and gas temperature. To reduce the number of variables, the carbon used will be the BPL carbon (Calgon Corporation) which was found to be the most active in the previous study. Since the experiments are expected to be short, a large number of parametric experiments will be carried out to prove feasibility and obtain data to permit a process evaluation.

The NO_x removal experiments will be carried out at Research Triangle Institute (RTI). The experiments will be geared toward demonstrating > 75% NO_x removal from off-gases expected from the activated carbon SO₂ conversion process. The principle variables considered will include carbon type (BPL carbon, 0.1 to 1% Pt on carbon, and three others), temperature (100 to 150°C), and space velocity [5000 to 20,000 scf/(cf·h)]. A proper N₂ balance will be carried out in each experiment and slip of NH₃ and NO/NO_x in the reaction products will be measured. Effect of traces of SO₂ up to 250 ppmv on NO_x conversion will be examined.

Based on the experimental data, technical and economic evaluation of the process for 1 MW and 100 MW plants will be carried out. The technical evaluation shall determine the degree of SO₂ and NO_x removal that may be achieved in full-scale plants using the data collected in the controlled laboratory experiments. Economic evaluation will determine the cost of our process on unit power generation basis. The predicted cost will be compared with the cost of the conventional limestone FGD/SCR system. If cost is at least 20% less for our process, our process will be considered for scale-up in future investigations.

The work to be carried out is divided into the following tasks:

	<u>Task</u>	<u>Schedule</u>
Task 1:	Program Definition (RTI and Waterloo)	June 4, 1991 to July 31, 1991
Task 2:	Experimental	August 1, 1991 to May 30, 1992
2.1:	SO ₂ Removal (Waterloo)	
2.2:	NO _x Removal (RTI)	
Task 3:	Process Evaluation (RTI)	May 1, 1992 to July 31, 1992

Task 1 (Program Definition) entails preparation of a detailed Project Management Plan describing a detailed work plan for the entire project and detailed test plans describing the experimental work. In Task 2 (Experimental), facilities will be constructed and experiments will be carried out per the approved Project Management Plan. SO₂ removal experiments will be carried out at Waterloo under the supervision of Dr. P.L. Silveston. NO_x removal experiments will be carried out at the Research Triangle Institute (RTI) under the supervision of Dr. S.K. Gangwal. In Task 3 (Process Evaluation), technical and economic evaluation of the process for 1 MW and 100 MW plants will be carried out by RTI.

It will be important to maintain a high degree of communication between Waterloo and RTI to assure success of the project. The communication will be maintained by weekly conference calls. Also, an RTI investigator will travel to Waterloo at least twice during the project to review their experimental progress. Similarly, a Waterloo investigator will travel to RTI at least twice during the project.

1.5 MEASURES OF SUCCESS

The targets that we hope to achieve during the course of our experiments are:

- 1) 95% or greater removal of SO_2 ,
- 2) Production of at least 2 molar sulfuric acid,
- 3) Pressure drop of at most 30 inches in the SO_2 removal process,
- 4) 75% or greater removal of NO_x , and
- 5) 25 ppmv or less NH_3 slip.

The experimental data would also indicate how to achieve further improvements in the above targets. The project is designed to prove the technical and economic feasibility of the process and provide sufficient data to permit a preliminary process evaluation. The ultimate test of the success of the project will be whether the process can reduce the cost of electricity over conventional FGD/SCR processes by 20%.

2.0 WORK COMPLETED IN PREVIOUS QUARTER

The accomplishments in the previous quarter were as follows:

- A paper was published and presented at the Seventh Annual Coal Preparation, Utilization, and Environmental Control Contractor's Conference sponsored by DOE/PETC;
- Task 1 was completed. A detailed Project Management Plan was prepared describing the work plan, experimental apparatus, experimental test plan/sequence, milestone schedule, cost plan, key personnel plan, project management structure, and measures of success;
- Task 2 was begun. The assembly of experimental apparatus at Waterloo and RTI was nearly completed with shakedown tests scheduled to begin on or about November 1, 1991. Calibration of all analytical instrumentation was nearly completed;
- Sufficient catalyst was procured for the SO₂ removal experiments at Waterloo. For the NO_x removal experiments at RTI, two catalysts have been selected and procured for the initial tests.

3.0 WORK COMPLETED IN PRESENT QUARTER

3.1 ACCOMPLISHMENTS

The accomplishments in the present quarter are as follows:

- An abstract was submitted for the AIChE meeting in Minneapolis.
- The experimental apparatus at RTI and Waterloo were commissioned. A continuous SO₂ analyzer was ordered for the SO₂ conversion tests at Waterloo.
- It was shown that 100% SO₂ removal was possible with continuous flushing of the SO₂ conversion trickle bed reactor.
- It was shown that 75% NO_x conversion was possible at a space velocity of about 700 scc/(cc · h) with a commercial Pt-impregnated carbon catalyst.
- Further optimization of the periodic flushing SO₂ conversion tests with respect to time, temperature, and catalyst was planned.

3.2 SO₂ Removal

3.2.1 Equipment Modifications

Shakedown runs of the apparatus described in detail in the first quarterly report commenced the first week of November. During initial shakedown runs it became necessary to make certain minor modifications to the proposed apparatus.

Figure 3 shows the new apparatus. The air used to saturate the liquid phase is now disengaged from the liquid phase in the overhead feed tank. It was found that the air pressure could be used to lift the liquid phase into the overhead feed tank. The overhead feed tank is open to the atmosphere and will not over pressurize the system.

The second modification was that instead of pumping liquid from the liquid saturator to the reactor the liquid is now pumped from the overhead feed tank into the reactor. Also a continuous SO₂ analyzer has been ordered to enable optimization of conditions for 95% removal.

3.2.2 Experimental Work

Initial shakedown runs of the apparatus commenced the beginning of November 1991. Common experimental conditions for all periodic flush experiments are shown in Table 2.

Figure 3. Apparatus for SO₂ Removal

Table 2. Common Experimental Conditions for SO₂ Removal Experiments with Periodic Flushing

Bed Size	:	176 g; 360 cc Catalyst
Bed Diameter	:	2" (5.08 cm)
Bed Depth	:	7" (17.78 cm)
Reactor Temperature	:	21°C
Flush Duration	:	3 minutes
Dry Gas Composition (Volume %):		N ₂ -- Balance SO ₂ -- 0.25 CO ₂ -- 15.0 O ₂ -- 5.0
Saturation Temperature	:	21°C

	High Flow Condition	Low Flow Condition
Superficial Gas Velocity, U _s , gas (cm/s)	16.35	5.65
Superficial Liquid Velocity, U _L , liquid (cm/s)	1.0	0.2
ΔP (with liquid flow) (inches of H ₂ O)	18.67	1.07
ΔP (without liquid flow) (inches of H ₂ O)	1.6	0.53

A number of experiments were conducted during the quarter. Results of initial scoping studies are shown in Table 3.

Experiments SD-1 to SD-4 were shakedown experiments where as P3 and P3-duplicate were experiments during which the average acid strength produced was measured. Average SO₂ removal increased with reduction in cycle time and flush liquid acid strength. However, no more than 35% apparent SO₂ removal was achieved. SO₂ removal is being measured indirectly at the present time although a continuous SO₂ analyzer is on order.

It was decided to concentrate on improving the SO₂ removal rather than follow the statistical design as proposed. Low flow conditions were tried next with a bigger carbon (4 x 6 mesh). Test data at these conditions are shown in Table 4.

The average SO₂ removal and acid strength achieved improved with lower flow, but not dramatically. At the same conditions, a steady state (i.e., continuous flush) experiment showed 100% SO₂ removal but a factor of 2 lower acid strength. Further optimization of cycle time and liquid flush time was thus indicated and will be carried out in the next quarter. Also a continuous SO₂ analyzer will be installed to allow decisions to be made on

changing cycle time and flush durations as the run proceeds. SO₂ removal may improve at higher temperature due to increased rate of SO₂ oxidation to SO₃. This will be investigated at RTI for the periodic flushing process. Finally, more active carbons as identified in the NO_x removal process may be tried to improve the SO₂ removal rate to the desired 95% level. Particularly, wider pore lower surface area carbons may be better than the baseline Calgon material being used.

3.3 NO_x REMOVAL

3.3.1 Experimental Modifications

The fixed-bed activated carbon catalyst-based NO_x removal reactor system with selective reduction using NH₃ was described in detail in the previous quarterly report. Experimental modifications following shakedown experiments are as follows:

- (i) The vertical split tube furnace was replaced with a convective GC oven to better control the low-temperatures of the reaction (<175°C)
- (ii) A number of reactor tubes of different diameters (ranging from 2 to 4 cm) and lengths (ranging from 8 to 32 cm) have been prepared to allow a wide range of space velocities to be tested.

Table 3. Initial SO₂ Removal Experiments

Run No.	SD-1	SD-2	SD-3	SD-4	P3	P3-Duplicate
Run Time (hours)	--	--	--	--	4	4
Cycle Time (minutes)	30	60	60	30	30	30
Flush Liquid Acid Strength (mol/liter)	0	0	0.1	0.1	0	0
Catalyst	Calgon 6 x 16	Calgon 6 x 16	Calgon 6 x 16	Calgon 6 x 16	Calgon 6 x 16	Calgon 6 x 16
Flow Condition	High	High	High	High	High	High
Average SO ₂ Removal (%)	30.0	17.8	13.5	20.8	30.4	35.0
Average Acid Strength Achieved (mol/liter)	--	--	--	--	0.00475	0.00550

Table 4. Low Flow SO₂ Removal Experiments

Run No.	T1	T1-Duplicate	S1 (Continuous Flush)
Run Time (hours)	4	5.5	2
Cycle Time (min)	30	30	Continuous
Flush Liquid Acid Strength (mol/liter)	0	0	0
Catalyst	Calgon 4 x 6	Calgon 4 x 6	Calgon 4 x 6
Flow Condition	Low	Low	Low
Average SO ₂ Removal (%)	37.4	39.0	100
Average Acid Strength Achieved (mol/liter)	0.0094	0.0098	0.0046

3.3.2 Experimental Work

Four different carbon-based catalysts were screened this quarter. These include the following: Calgon BPL 10 x 16, Calgon BPL 4 x 6 Lot No. 1430-R, Degussa 0.5% Pt on Carbon and Degussa 1% Pt on Carbon.

Experimental conditions common to all tests are shown in Table 5. The shakedown experiments were carried out in a tube reactor positioned in a vertical split tube furnace. The experimental conditions and results of these tests are shown in Table 6.

The results of Run SDT-1 indicated that space velocities > 4000 scc/(cc·h) are too high. The superficial contact time at these velocities in the reactor was less than a second. The reactor size for Run SDT-2 was increased by a factor of 4, thus reducing the space velocity to about 1000 scc/(cc·h) [for reference, the Mitsui NO_x removal process runs at a space velocity of around 400 scc/(cc·h)]. However the conversion was still quite low (i.e., ~19% at 110°C). The higher "apparent conversion of 26.7% at 104°C was later determined to be due to the influence of adsorption and not chemical reaction between NH₃ and NO_x. Thus it is not a conversion at all.

The reactor system was considered to be commissioned after Runs SDT-1 and SDT-2. To improve control at low temperature, the reactor was modified and installed in a GC oven which gave very good temperature control for later tests.

A series of tests was conducted with various catalysts. The results of these tests are presented in Table 7.

Table 5. Common Experimental Conditions for NO_x Conversion Tests

Pressure	:	1 psig
Gas Composition (Volume %)		
O ₂	:	5
CO ₂	:	10
H ₂ O	:	10
He		Balance
Nominal NO _x	:	500 ppmv
NO _x /NH ₃	:	~ 1

Table 6. Shakedown Test Results for NO_x Conversion

Run No.	SDT-1	SDT-2
Catalyst Type	Calgon BPL 10 x 16	Calgon BPL 6 x 16
Bed Size (g)	12	52
Bed Volume (cc)	27	110
Reactor I.D. (cm)	2.1	3.4
Space Velocity (scc/cc·h)	8274	1081
NO _x in (ppmv)	420	530
NH ₃ in (ppmv)	524	506
Average Temperature (%)	150	150
NO _x Conversion (%)	0	18.9
		26.7*

* Later results indicate adsorption to be dominant at temperatures below 120°C.

Table 7. NO_x Conversion Test Results

Run No.	1	2	3
Catalyst Type	Calgon BPL, Carbon 4 x 6, Lot 1430-R	Degussa, 0.5% Pt/Carbon 2.5 - 4.5 mm	Degussa, 1% Pt/Carbon 2.5 - 4.5 mm
Bed Size (g)	42.3	37.8	38.8
Bed Volume (cc)	85	85	85
Reactor I.D. (cm)	3.0	3.0	3.0
Space Velocity (scc/cc·h) Velocity /h	1412 1412	1419 1419	1412 1412 1390 1390 1390 1390
NO _x in (ppmv)	500 500	470 470	485 485 490 490 490 490
NH ₃ in (ppmv)	513 513	500 500	500 500 500 500 500 500
Temperature (°C)	82 152	82 153	82 153 122 137 168 168
NO _x Conversion	29* 24	36.2* 55.3	35.1* 55.7 23.5 46.9 61.2 61.2

* Adsorption is dominant at temperatures below 120°C.

To improve the conversion, Calgon recommended using a Calgon BPL 4 x 6 Lot 1430-R. This catalyst showed a 24% conversion at 150°C as shown in Table 7. Using a noble metal-based carbon catalyst from Degussa, the conversion increased significantly to 55.3% at 150°C. Increasing the Pt loading to 1% did not appear to increase conversion at 150°C, i.e., it remained at ~55%.

A complete temperature series was tested for the Degussa 1% Pt/Carbon catalyst. Conversion ranged from 23.5% at 122°C to 61.2% at 168°C at a space velocity of 1400 scc/(cc·h). A simple first order plug-flow reaction model was used to determine if the data were being obtained in the kinetic regime or were influenced by diffusional limitations. This model leads to

$$k = -(v_0/w) \ln (1-x) \quad (1)$$

where, k = first order rate constant ($\text{cm}^3/\text{g catalyst} \cdot \text{sec}$)

v_0 = volumetric flow rate at reactor (cm^3/sec)
temperature and pressure

w = weight of catalyst, g

x = fractional conversion of NO_x

Using Equation (1), calculated k values as a function of temperature are shown in Table 8. These values suggest that 75% NO_x conversion can be achieved at a space velocity of 700 scc/cc·h at 137°C.

The data in Table 8 are plotted in an Arrhenius plot in Figure 4. The results suggest the influence of diffusion control at temperatures above 137°C and an activation energy of about 19 kcal/mol in the kinetic region. The rate constants of around $1 \text{ cm}^3/(\text{g} \cdot \text{sec})$ are quite high for 2.5 - 4.5 mm particles so that diffusional limitations can be expected based on theoretical evaluations using literature correlations. $k = 1 \text{ cm}^3/\text{g} \cdot \text{sec}$ is a reasonable rate constant target to achieve for 2.5 - 4.5 mm particles for industrial application at 122 to 137°C. Thus there is still some room (but small room) for improvement in the catalyst before considering special packing, e.g., structured packing or monoliths to reduce diffusional limitations and pressure drop.

**Table 8. First Order Rate Constants for NO_x
Conversion on 1% Pt/Carbon Catalyst**

Temperature (°C)	Rate Constant [cm³/g catalyst-sec]
122	0.307
137	0.755
153	1.022
168	1.214

NO Reduction on Degussa 1% Pt/Carbon

Arrhenius Plot

$1/T$

Figure 4. First Order Rate Constant Arrhenius Plot for NO Reduction with NH_3 on Degussa 1% Pt/Carbon Catalyst

4.0 WORK PLANNED FOR NEXT QUARTER

4.1 SO₂ REMOVAL

Experiments will concentrate on optimizing flush duration, cycle time, catalyst, and temperature to demonstrate 95% SO₂ removal. Temperatures of 21°C, 50°C, and 80°C will be tested. Wider-pore active carbons will be evaluated.

4.2 NO_x REMOVAL

A Carbotech lignite coke material used for the Mitsui process will be tested. Catalysts will be requested from AECL Canada, Shell, and University of Kentucky, and if available, will be tested. The best catalyst to date will be subjected to tests to find conditions for 75% NO_x removal with <25 ppmv NH₃ slip.

5.0 REFERENCES

- Hartman, M., and R.W. Coughlin. 1972. Chem. Eng. Sci. 127:867-880.
- Harman, M., J. Polek, and R.W. Coughlin. 1971. Chem. Eng. Prog. Symp. Ser., No. 115, 67:7-22.
- Haure, P., R.R. Hudgins, and P.L. Silveston. 1989. AIChE Journal, 35:1437.
- Karebo, K., Y. Nakahigashi, and K. Nagata. 1988. Carbon, 26(3):327-333.
- Keuhl, H., E. Richter, K. Knoblauch, and H. Juentgn. 1986. Carbon '86, Bergan-Forschung, Essen, Germany, pp. 351-353.
- Kusakube, K., M. Karhima, S. Morook, and K. Shigeharu. 1988. Fuel, 67(5):714-718.
- Seki, M., Y. Sakurai, and K. Yoshida. 1975. Am. Chem. Soc. Div. Eng. Chem. Reprints: 15(2), Chicago Meeting, August 24-29, pp. 28-31.

END

**DATE
FILMED**

4 / 27 / 92