**Development of an Advanced Continuous Mild Gasification
Process for the Production of Coproducts**

Final Report

**N.W. Merriam
M.C. Jha**

November 1991

Work Performed Under Contract No.: DE-AC21-87MC24268

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
Morgantown, West Virginia**

**By
Western Research Institute
Laramie, Wyoming
and
AMAX Research & Development Center
Golden, Colorado
and
Riley Stoker Corporation
Worcester, Massachusetts**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, ~~FTS-606-8401~~.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

**Development of an Advanced Continuous Mild Gasification
Process for the Production of Coproducts**

Final Report

**N.W. Merriam
M.C. Jha**

Work Performed Under Contract No.: DE-AC21-87MC24268

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
Western Research Institute
P.O. Box 3395, University Station
Laramie, Wyoming 82071-3395
and
AMAX Research & Development Center
5950 McIntyre Street
Golden, Colorado 80403-7499
and
Riley Stoker Corporation
Worcester, Massachusetts 01613**

November 1991

ABSTRACT

This report is a final, brief summary of development of a mild-gasification and char conversion process under contract DE-AC21-87MC24268. It serves as a focal center from which readers can refer to other reports that contain more detailed information about the results from the various tasks. Western Research Institute (WRI) served as the prime contractor with AMAX R&D Center (AMAX) and Riley Stoker Corporation (Riley) as subcontractors.

A joint literature survey was completed by the team members in early 1988. A market survey by AMAX Coal Company and JDS Group Incorporated was also completed in early 1988. A two-part strategy was then formulated. First, we chose to avoid making products that would compete directly with petroleum products. Second, we chose to make products that could be used by divisions of AMAX. Thus, electrode-binder pitch and diesel fuel were selected as liquid products, and char was converted to anode-grade carbon, carbon black, and activated carbon.

In late 1988, WRI completed bench-scale testing of the mild-gasification process using a bench-scale, plug-flow, inclined, fluidized-bed reactor. AMAX completed bench-scale testing of char conversion in late 1989. Both programs showed encouraging results. A preliminary economic assessment by Stearns-Roger indicated that the process may be economically attractive.

Riley completed design of a 100-lb/hr mild-gasification process research unit (PRU) in early 1989. The PRU was constructed at WRI and successfully operated for 24-hour and 5-day tests during late 1989 and 1990.

AMAX completed design and construction of a char-to-carbon (CTC) PRU in early 1991. The 50-lb/hr unit is based upon a two-step methane formation and decomposition process to produce pure carbon. The PRU was operated during the first half of 1991.

As the next step in commercial development, the Ralph M. Parsons Company designed a 20 ton/day coal mild gasification and product upgrading process development unit (PDU) with inputs from WRI and AMAX. This information was then used to perform a preliminary design of a 1,000 ton/day commercial demonstration plant. Based on the estimated cost and product revenues, the project looks economically attractive.

It is recommended that the process development efforts should continue, first on PRU scale and then on PDU scale.

ACKNOWLEDGEMENT

The authors express their appreciation to the United States Department of Energy and the Morgantown Energy Technology Center for funding this work under contract DE-AC21-87MC24268. We also thank the AMAX Coal Industries and AMAX Incorporated for their support of this project in general and the partial funding of the char upgrading process research and development in particular.

EXECUTIVE SUMMARY

The U.S. Department of Energy (DOE) is developing processes to convert coal to usable gaseous and liquid forms. Successful development of the processes will increase the use of coal, the largest domestic fossil energy resource. However, these processes typically require high temperatures and pressures and have been slow in receiving commercial acceptance because they require high capital and operating costs.

To overcome this problem, Morgantown Energy Technology Center (METC), the lead technical center in gasification technology, developed a concept called mild gasification. In this concept, devolatilization of coal under nonoxidizing and relatively mild temperature and pressure conditions can yield three marketable products: (1) a high-heating-value gas, (2) a high-aromatic coal liquid, and (3) a high-carbon char.

METC awarded a contract (DE-AC21-87MC24268), Development of an Advanced, Continuous Mild-Gasification Process for the Production of Coproducts, to Western Research Institute (WRI) in Laramie, Wyoming, with AMAX R&D and Riley Stoker as subcontractors to further enhance the technology and the economics of mild gasification.

The objective of this program is to develop an advanced, continuous, mild-gasification process to produce products that will make the concept economically and environmentally viable.

The program consists of four tasks:

- Task 1--Literature Survey and Market Assessment
- Task 2--Bench-Scale Mild-Gasification Study
- Task 3--Bench-Scale Char-Upgrading Study
- Task 4--System Integration Studies

Task 1--Results of Literature Survey and Market Assessment

Market assessment studies were performed by AMAX Coal Company and JDS Group Inc. as part of task 1. The studies showed that revenue from a commercial plant could be significantly improved if char is converted to carbon black, electrode-grade carbon, activated carbon, or metallurgical coke. The fact that Alumax, a division of AMAX, consumes over 250,000 tons of anode-grade carbon per year at delivered prices of about \$200 per ton resulted in a decision to develop a process to produce anode-grade carbon from char. The carbon is produced by a two-step methane formation-decomposition process.

We decided to produce four liquid products: (1) dirty pitch, (2) clean pitch, (3) heavy oil, and (4) light oil. The dirty pitch will be used to coat dried coal before shipment. It will displace a petroleum product purchased for \$100 per ton. Clean pitch will be used as electrode-binder pitch by Alumax, displacing pitch imported for \$200 to \$250 per ton. Heavy oil will be blended with diesel

fuel to operate equipment at the mine for about \$100 per ton. The light oil will be sold as octane enhancer for about \$100 per ton.

It is presently not economically attractive to convert the gas produced to pipeline gas; although, it is technically feasible. The best economic use for this process gas is to burn the gas to supply heat for the mild-gasification process.

Only one of the selected products, the light oil, will not be consumed within AMAX. All other products will be used at the mine or within divisions of AMAX. The internal use will help gain market acceptance for the products.

A preliminary economic evaluation of the process performed by Stearns-Roger showed that the process may be commercially attractive. This evaluation also reaffirmed our perception that we must develop a low-cost process if we are to achieve commercial success.

Task 2--Results of Bench-Scale Mild-Gasification Tests

WRI conducted 23 successful coal-drying tests and 14 successful mild-gasification tests using inclined fluidized-bed reactors. The tests in the 10-lb/hr reactors ran for four to sixteen hours with most tests maintaining steady-state conditions for eight hours. The effects of bed temperature, particle size, and drying-gas water content on the drying rates and residual moisture content of the dried coal were determined.

The effects of bed temperature, heating rate, coal particle size, solids residence time, and fluidizing-gas composition on the yield of liquid products and the composition of char and gas produced were determined from the mild-gasification tests.

Task 3--Results of Bench-Scale Char-Upgrading Tests

Evaluation of char samples produced by mild gasification of subbituminous Wyoming coal in an inclined fluidized-bed reactor showed them to have an open pore structure, low ash, volatile and sulfur contents, and high heating value. The char is very reactive and maintains its reactivity when stored in inert atmosphere. While the char could be used as a utility fuel, its upgrading to higher value product(s) would significantly enhance the commercial feasibility of mild gasification based coal refining technology.

The goal of Task 3 was to develop a char upgrading process. AMAX succeeded in conceiving and developing a two step char-to-carbon process for upgrading mild gasification char to pure carbon and activated carbon. In the first step, most of the carbon in the char is converted to methane gas in the presence of an excess of hydrogen. All of the ash and most of the sulfur remain behind in the spent char. In the second step, the methane-rich gas is heated to a higher temperature to produce pure carbon and hydrogen for recycle.

A bench-scale reactor system was built for an independent study of the two steps. Results from these tests indicated that methanation of char can be

accomplished using an excess of hydrogen in a fluidized-bed reactor in the temperature range of 1,300 to 1,500°F (705 to 815°C) and pressure range of 200 to 400 psia. About 70 percent carbon conversion was obtained in less than 2 hours residence time. The use of catalyst or steam did not improve the conversion.

The remaining spent char was found to have a high specific surface area and very porous structure. AMAX conceived and developed a process to upgrade this spent char to activated carbon by recovering a relatively ash-free fraction using gravity separation. The phenol adsorption capacity of the carbon so produced was comparable to a commercial grade carbon.

An indirectly heated continuous reactor system was conceived and developed for cracking of methane and other hydrocarbons to produce pure carbon and hydrogen. The theoretical carbon yield by this process is higher than obtained in state-of-the-art technology, and the hydrogen product is not contaminated. Bench-scale tests were performed in the temperature range of 1,600 to 2,200°F (870 to 1205°C) and atmospheric to 150 psia pressure using a synthetic methane/hydrogen gas mixture. It was found that methane could be cracked at temperatures as low as 1,600 to 1,800°F (870 to 980°C) and at 50 to 150 psia in the presence of seed carbon. This gives the flexibility of producing fine or coarse carbon for different markets. Under these conditions, metal tubes can be used to supply heat indirectly.

The carbon produced in the bench-scale program had properties which depended upon the temperature, gas composition, residence time, and seed carbon employed.

Task 4--Results of Mild-Gasification PRU Tests

A series of 24-hr and 5-day tests were conducted using the PRU designed by Riley Stoker and assembled by WRI. Coal feed rates varying from 93 to 149 lb/hr of minus 8-mesh Wyodak coal were used. The effects of maximum bed temperatures of 950 to 1150°F (510 to 620°C) and coal (char) residence times of 5 to 9 minutes upon the distribution and properties of products were determined.

Results of the tests using the PRU show that the yield of coal liquids increases from about 10 wt % of the MAF coal feed to the mild-gasification reactor when using a maximum bed temperature of 950°F (510°C) to about 15 wt % at 1150°F (620°C).

The coal liquids are heavy, tarry substances with 55 to 60 wt % boiling in the range of 700+ °F (370+ °C) needed for anode-binder pitch. Typical H:C atomic ratios vary from 1.15 to 1.25. The liquids are sufficiently low in ash content to meet specifications for binder pitch. However, they contain too much hydrogen and oxygen, and the specific gravity is low. Heat treatment of the liquid has been shown to reduce the hydrogen and oxygen content while increasing the specific gravity.

The yield of char produced varies from about 42 wt % of the raw coal at a bed temperature of 950°F (510°C) to about 38 wt % at 1150°F (620°C). The char contains 15 to 21 wt % volatiles and is highly reactive in both hydrogen and air. Tests at Oak Ridge National Laboratories indicate that the char appears to be sufficiently reactive for firing in a wide variety of combustors, possibly including those burning pulverized fuel.

The hydrogen and oxygen content of the char can be controlled by the degree of devolatilization used in the mild-gasification reactor.

Task 4--Results of Char-Upgrading PRU Tests

Amax R&D designed, built, and operated a 50 pound/hour CTC PRU at its Golden, Colorado, facilities. The PRU was designed by BEI Engineers/Constructors of Lakewood, Colorado, during the second half of 1989 based on the results obtained in Task 3. It was built with assistance from The Industrial Company of Steamboat Springs, Colorado, during the first half of 1990.

The PRU was operated for about one year, from July 1990 to July 1991, completing 35 runs covering about 800 hours of operation. These runs included:

- Six shakedown runs during which the primary goal was to calibrate the instruments, develop start-up and shut-down procedures, and train the operators for safe operation of the plant.
- Ten methanation runs during which the primary focus was on the methane reactor and its modifications. The membrane was included in the flowsheet so that unreacted hydrogen could be recovered and reused. The methane-rich gas product was simply burned in the flare.
- Eight carbon formation runs during which the primary focus was the carbon formation reactor and its modifications. Bottled methane gas mixed with hydrogen from the tank was used in these runs and the exit gas was flared.
- Eleven integrated runs during which both the reactors were operated and emphasis was on demonstrating the proof of concept for the process, as well as on developing a better understanding of the process control.

The later runs were integrated runs which provided the data for process evaluation. The longest runs lasted for up to 3 days.

The PRU operation provided the proof of concept for the CTC process. Mild gasification char was successfully converted to methane in the methanation reactor, and after gas separation in a membrane, it was decomposed to carbon in the carbon formation reactor. The two reactions occurred at designed temperature and pressure conditions.

However, the percent conversion was well below the design in both reactors, mostly due to the lack of adequate residence time at proper temperature. Heat losses were significantly higher than allowed for in the design. The fluidization quality was also poor, as was seen by the cold flow models.

The carbon product was contaminated by chromium, iron, and nickel metals due to erosion and corrosion of metal tubes used as muffles for the glow bars. Scaling of these surfaces by carbon product was the primary cause for poor heat transfer coefficient.

A materials of construction problem led to the poor performance of the carbon reactor and its shutdown due to safety concerns.

Other systems, including the membrane, cyclones, baghouse, heat exchangers, and compressors, worked well. The solids feeding and discharging systems had to be modified. Most of the instruments, with the exception of turbine flowmeters, worked well.

The plant is highly computerized for data logging, as well as process control. This system worked well and was primarily responsible for the safe operation of the plant involving explosive and toxic gases.

It is recommended that the PRU test program be continued, after the required modifications, to accomplish the following goals.

- Process optimization
- Production of enough product for market evaluation

Task 4.6--Technical and Economic Evaluation

The goal of this task was to prepare a preliminary process design and economic evaluation of a 1,000 ton/day coal mild gasification and product upgrading commercial demonstration plant (CDP). The design is based on a process flowsheet developed and improved by WRI and AMAX over the last 3 years by bench-scale research and design, construction, operation, and evaluation of a 100 lb/hr mild gasification PRU at WRI and a companion CTC PRU at AMAX. An adjunct power plant was assumed to be of conventional design.

The product slate now consists of pitch (to be used as a binder in the manufacture of carbon anodes), cresylic acid (to be marketed as a chemical feedstock), and oil (to be blended with diesel to operate heavy mine equipment). The solid products include pure carbon (fine carbon to be used as fine carbon black for rubber compounding and coarse carbon to be used in the manufacture of carbon anodes) and activated carbon (to be used in water purification). Electricity is a major coproduct.

The mild gasification process flowsheet as tested by WRI was slightly modified to improve the operability of the plant and recovery of the desired

liquid products. The CTC process flowsheet was based on the AMAX PRU design with only one major change, that the carbon reactor be heated by heat pipes. Since the completion of the CDP design, it was learned that this design of the carbon reactor was not satisfactory and an alternative design has to be developed.

The process flowsheet and mass balance calculations were based on more detailed design work performed on a 20 ton/day process development unit (PDU) encompassing the same unit operations. This also formed the basis for sizing of the reactors and estimation of the purchased equipment cost for the process plant. The estimated purchased equipment cost for the power plant was based on Parsons' experience.

The total capital cost for the plant is estimated at \$169 million which includes a contingency of \$26 million. The annual operating cost is estimated at \$11 million, which includes \$4 million for labor, \$4.2 million for maintenance, and the balance for feedstock and supplies.

The estimated annual revenues are \$30 million for pure carbon, \$11 million for activated carbon, \$7 million for liquid products, and \$11 million for electricity, for a total of \$59 million.

An economic evaluation model was used to calculate the discounted cash flow rate of return (DCFROR), assuming zero net present value and 20-year plant life. Sensitivity analysis was performed on the capital cost, operating cost, and product revenues. The DCFROR was 16.4 percent for the base case.

In summary, the project is technically sound and offers good economic potential for commercial development. Based on the economic potential for the commercial development of this project, it is recommended that the project development efforts should continue.

Task 4.7--PDU Design and Cost Estimate

The objective of the task was to provide DOE with a realistic design and cost estimate of a 20 ton/day coal mild gasification and product upgrading PDU, which is the next logical step in the commercial development of this technology. An implied goal was to develop a low cost, but technically sound, design based on the results of Tasks 2, 3, and 4.

It was decided that only those operations would be included that need scale-up design information for the commercial demonstration plant. Thus, both the mild gasification and char upgrading operations (studied in the two PRUs) were included, with additional equipment to provide process heat and recover energy as steam. However, the power production, which is a significant part of the commercial flowsheet, was not included.

The location of the PDU at the pilot plant facilities of Amax R&D Center assured that most of the required infrastructure was already in place. This included roads, pads, buildings, offices, laboratories, and utilities. Only one

new building has to be added. Some of the required equipment, including that for batch production of activated carbon, are available at Amax R&D and, therefore, were excluded from the cost estimate.

Parsons reviewed all the project reports prepared by WRI, AMAX, and Riley Stoker Corporation. These included topical reports for Tasks 2 and 3, as well as quarterly progress reports. Based on these data, they developed conceptual process flowsheets and used a computer simulation program to prepare the mass and energy balance.

After the flowsheet was finalized, Parsons finished the process flow diagrams and mass balance, which are presented as three drawings in the topical report. Next, they prepared 19 P&I diagrams, which were thoroughly reviewed by AMAX. These drawings are detailed enough to show all of the equipment and instruments, as well as control logic.

They then prepared an equipment list, which included about 125 items. Equipment design condition summary sheets were prepared for all the major pieces. The instrument summary list contains 662 field devices and 447 computer inputs/outputs. The Parsons' topical report also includes electrical single lines, materials diagrams and equipment lay out, and general arrangements drawings.

Parsons estimated that the PDU can be designed and built in 16 months for a total cost of \$16,750,000, which includes contingency. AMAX R&D, based on its own experience of construction of the PRU and other pilot plants, using local contractors, considers this cost estimate to be high.

Task 4.8--Decommissioning of PRUs and Disposal of Samples

WRI and AMAX R&D Center have prepared a plan, schedule, and estimated costs for disposal of materials produced by testing, and decontamination and disassembly of both PRUs. WRI proposes to dispose of materials during 1992 at an estimated cost of \$76,000 and to disassemble the mild-gasification PRU during 1993 at an estimated cost of \$169,000. AMAX R&D Center proposes to operate the char-to-carbon PRU during the next two (2) years. Disposal of materials and disassembly of the PRU, both during 1993, are estimated to cost \$31,000 and \$162,000 respectively.

TABLE OF CONTENTS

	<u>Page</u>
LIST OF TABLES.....	xiv
LIST OF FIGURES.....	xv
1.0 INTRODUCTION.....	1
2.0 Task 1--LITERATURE SURVEY AND MARKET ASSESSMENT.....	2
3.0 Task 2--BENCH-SCALE MILD GASIFICATION STUDY.....	5
3.1 Bench-Scale Mild-Gasification System.....	6
3.2 Bench-Scale Mild Gasification Test Results.....	10
4.0 Task 3--BENCH-SCALE CHAR-UPGRADING STUDY.....	10
4.1 Process Chemistry.....	11
4.2 Char-Methanation Tests.....	12
4.3 Carbon-Formation Tests.....	14
4.4 Production of Activated Carbon.....	16
4.5 Conclusions from Task 3.....	17
5.0 Task 4--SYSTEM INTEGRATION STUDIES, MILD-GASIFICATION PRU.....	18
5.1 Mild-Gasification PRU.....	18
5.2 Mild-Gasification PRU Test Results.....	24
6.0 Task 4--SYSTEM INTEGRATION STUDIES-CHAR-TO-CARBON PRU.....	31
6.1 Description of Char-to-Carbon PRU.....	32
6.2 Char-to-Carbon PRU Test Results.....	37
7.0 Task 4.6--TECHNICAL AND ECONOMIC EVALUATION OF A 1000 TPD COMMERCIAL DEMONSTRATION PLANT.....	42
8.0 Task 4.7--PRELIMINARY DESIGN AND COST ESTIMATE FOR 20 TPD PDU.....	52
9.0 Task 4.8--DECOMMISSIONING OF PRU'S AND DISPOSAL OF SAMPLES.....	55

TABLE OF CONTENTS (continued)

	<u>Page</u>
10.0 CONCLUSIONS.....	56
11.0 RECOMMENDATIONS.....	59
12.0 REFERENCES.....	60

LIST OF TABLES

<u>Table</u>	<u>Page</u>
1. Typical Composition /Characteristics of Feed Coal for the Mild Gasification Project.....	5
2. Summary of Design Conditions for the Inclined Fluidized-Bed Reactors.....	6
3. Properties of Mild-Gasification Char and Spent Char.....	14
4. Results of High-Pressure, Carbon-Formation Studies.....	16
5. Summary of Design Conditions for the Mild-Gasification PRU.....	21
6. Feed Coal Size.....	22
7. Conditions Used for Drying Coal During Mild-Gasification Tests.....	24
8. Conditions Used for Mild-Gasification Tests.....	25
9. Product Distribution from Mild-Gasification Tests.....	26
10. Summary of Liquids Produced by Mild Gasification.....	30
11. Summary of Design Conditions for CTC PRU.....	32
12. Estimated Capital Cost of 1,000 TPD Plant.....	49
13. Annual Revenues for the 1,000 TPD Plant.....	50
14. Estimated Cost of Design and Construction for PDU.....	55

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
1. Inclined Fluidized-Bed Reactors Used as 10-lb/hr Dryer and Mild-Gasification Reactor.....	7
2. Bench-Scale Drying and Mild-Gasification System.....	9
3. Conversion versus Time Plots for Methanation of Mild-Gasification Char.....	13
4. Phenol Adsorption Isotherms for Darco KB-B and AMAX Activated Carbon.....	17
5. Process Flow Diagram for Mild-Gasification PRU.....	19
6. Solid and Gas Flow in Inclined Fluidized-Bed Reactor.....	20
7. Yield of Dry Coal Liquid Products at Various Bed Temperatures.....	28
8. Distribution of Products from Mild Gasification at Various Maximum Bed Temperatures.....	29
9. Char-to-Carbon PRU.....	33
10. Photomicrographs of Cross Sections of a) Original Seed Carbon and b) Seed Carbon Removed from the Carbon Reactor.....	40
11. Potential Products and Markets.....	45
12. Conceptual Flowsheet of the Commercial Demonstration Plant.....	47
13. DCFROR Sensitivity versus Revenue and Capital.....	51

1.0 INTRODUCTION

To increase the use of coal, the largest domestic potential source of fossil energy, in an economically competitive and environmentally acceptable manner, the United States Department of Energy (DOE) has been developing several gasification and liquefaction processes to convert coal to usable gaseous and liquid forms. However, these processes, which require high temperatures and pressures in most cases, have been slow in receiving commercial acceptance because they require high capital and operating costs.

To overcome this problem, Morgantown Energy Technology Center (METC), the lead technical center in gasification technology, has developed a concept called mild gasification. In this concept, devolatilization of coal under nonoxidizing and relatively mild temperature and pressure conditions can yield three marketable products: (1) a high-heating-value gas, (2) a high-aromatic coal liquid, and (3) a high-carbon char.

To further enhance the technology and the economics of mild gasification, METC awarded a contract (DE-AC21-87MC24268), Development of an Advanced, Continuous Mild-Gasification Process for the Production of Co-Products, to Western Research Institute (WRI) in Laramie, with AMAX R&D and Riley Stoker as subcontractors.

WRI provided project management and conducted the mild-gasification tests. AMAX R&D Center did the char upgrading work as well as economic evaluation for a commercial integrated plant. Riley Stoker designed and procured the mild-gasification PRU that was used for tests at WRI. Stearns-Roger developed a preliminary cost estimate for a 1000 TPD plant based upon data from bench-scale tests. The Ralph M. Parsons Company produced a preliminary design for a 20 TPD PDU and cost estimates for a 20 TPD PDU and a 1000 TPD commercial demonstration plant based upon data from bench-scale and PRU tests.

The objective of this program was to develop an advanced, continuous, mild-gasification process to produce products that would make the concept economically and environmentally viable.

The program consisted of four tasks:

1. Task 1--Literature Survey and Market Assessment
2. Task 2--Bench-Scale Mild-Gasification Study
3. Task 3--Bench-Scale Char-Upgrading Study
4. Task 4--System Integration Studies

The work on task 1 was completed and reported by Cha et al. (1988). The work on tasks 2 and 3 was completed and reported by Merriam and Cha (1989) and Jha and McCormick (1989), respectively. The results of mild-gasification tests using a 100-lb/hr process research unit (PRU) at WRI have been reported by Merriam et al. (1990). Results of tests using a char-to-carbon (CTC) PRU to upgrade char at AMAX R&D have been reported by Jha et al. (1991).

This is the final report describing work under contract DE-AC21-87MC24268. Summaries of results from Tasks 1, 2, 3, 4.4, 4.6, 4.7, and 4.8 are included in this report.

2.0. Task 1--LITERATURE SURVEY AND MARKET ASSESSMENT

The major goal for developing and demonstrating mild gasification of high-volatile coal is to stimulate commercial production of fuels and feedstocks from coal in the United States. The achievement of this goal will reduce the dependence of broad sectors of the American economy on petroleum from foreign sources and will also stimulate production of coal from vast domestic resources.

Much work has been done in the United States during the last several decades to produce fuels and feedstocks from coal. However, nearly all of the development has focused on severe conditions to produce maximum yields of liquid and gaseous products. Although some of the processes have been shown to be technically feasible, the high temperatures ($>1292^{\circ}\text{F}$ [700°C]) and high pressure (>50 psig) used in those processes have resulted in high-cost processes that do not appear to be economically feasible for commercial production in the foreseeable future.

One approach to developing low-cost processes is to use mild conditions (i.e., lower temperatures and pressures) to reduce the cost of producing fuels and feedstocks from coal. The use of mild conditions may produce less than maximum yields of gaseous and liquid products; however, it is likely that low-cost processes can produce a slate of products with marketable properties and economically acceptable yields. The focus of mild gasification is, therefore, upon developing and demonstrating processes that can be built and operated with relatively low cost on the commercial scale and will give a satisfactory return on the investment.

Cost estimates for plants using severe processing conditions show that investments of billions of dollars are needed to construct a single plant. Few organizations in the United States have the capital needed for such an undertaking and are willing to accept the enormous risk. Thus, one goal of the mild-gasification work is to prove that processes can be built for a small fraction of the investment needed for severe processes, thus, significantly lowering the financial risk of constructing a mild-gasification plant. Mild-gasification processes must also have low operating costs to be economically feasible.

Versions of mild gasification of coal, frequently called devolatilization, are presently practiced in England, India, and South Africa and have been used commercially in many countries in the past. The development of new mild-gasification processes will be based on experience with older technology combined with recent technological improvements and systems approach to optimizing the overall value of the products.

There are four factors to be considered for successful operation of a mild-gasification plant: (1) properties of the coal source, (2) gasification conditions, (3) product upgrading, and (4) the locations and sizes of markets for products. All these factors are requisite for the mild-gasification process to be successful. The most important factor is markets for the products because the operator has less control over the markets than over other factors.

Market assessment studies were performed by AMAX Coal Company and JDS Group Inc. as part of task 1 (Cha et al. 1988). The studies showed that revenue from a commercial plant could be significantly improved if char is converted to carbon black, electrode-grade carbon, activated carbon, or metallurgical coke. The fact that Alumax, a division of AMAX, consumes over 250,000 tons of anode-grade carbon per year at delivered prices of over \$200 per ton resulted in a decision to develop a process to produce anode-grade carbon from char.

We decided to produce four liquid products: (1) dirty pitch, (2) clean pitch, (3) heavy oil, and (4) light oil. The dirty pitch will be used to coat dried coal before shipment. It will displace a petroleum product purchased for \$100 per ton. Clean pitch will be used as electrode-binder pitch by Alumax, displacing pitch imported for \$150 to \$250 per ton. Heavy oil will be blended with diesel fuel to operate equipment at the mine or be sold to a refinery for about \$100 per ton. Light oil will be sold as an octane enhancer for \$100 per ton.

It is presently not economically attractive to convert the gas produced to pipeline gas, although it is technically feasible. The best economic use for this process gas is to burn it to supply heat for the mild-gasification process.

Only one of the selected products, the light oil, will not be consumed within AMAX. All other products will be used at the mine or within divisions of AMAX. The internal use will help gain market acceptance for the products.

We selected inclined fluidized-bed (IFB) reactors for the dryer and mild-gasification reactors because the plug-flow of solids, shallow beds, and cross-flow of gas with respect to solids provide strong driving forces for drying and devolatilization as well as high thermal efficiency. The high sweep gas flow and shallow bed in the mild-gasification reactor produce a high yield of pitch by minimizing the exposure of coal liquids to secondary reactions.

For char upgrading, after evaluating several options, AMAX decided to develop char-to-carbon (CTC) process. This is a two-step process in which no external reagent is consumed. In the first step, the carbon in char is converted to methane in presence of an excess of hydrogen. In the second step, after separation of ash, the methane is heated to decompose it to carbon product and hydrogen gas which is recycled. The process is capable of producing pure carbon of varying particle size for different target markets.

A preliminary economic evaluation of the process was performed by Stearns-Roger. The evaluation showed that the process is commercially

attractive. This evaluation also reaffirmed our perception that we must develop a low-cost process if we are to achieve commercial success.

Coal from an AMAX mine was selected as feed for the mild gasification process (Table 1). Wyodak, a subbituminous coal, has the advantages of low sulfur and ash contents and the disadvantages of high moisture and oxygen contents. AMAX Coal Company is drying Wyodak coal for shipment. The cost of the proposed plant may be lowered by using some of the coal handling and drying facilities as part of the mild-gasification plant. Wyodak coal is also a low-cost coal.

The mild-gasification testing was conducted to maximize production of clean pitch, the most valuable liquid product, and to produce highly reactive char having a hydrogen-to-oxygen mass ratio higher than 0.125 so that no hydrogen from external sources is needed to react with oxygen during char upgrading. We also wanted to completely dry the coal and drive out as much oxygen as possible by partial decarboxylation during drying while producing clean water from the drying operation.

Complete drying and partial decarboxylation is achieved by drying below the temperature at which primary tar decomposes to avoid producing dirty water. Maximum pitch production requires high heating rates, high sweep-gas flow rates and use of a relatively small average particle size. The hydrogen-to-oxygen mass ratio in the char can be maintained above 0.125 by avoiding temperatures above about 1200°F (649°C).

Table 1. Typical Composition/Characteristics of Feed Coal for the Mild-Gasification Project

Coal Seam	Wyodak
Coal Rank	Subbituminous
Mine Name	Belle Ayr/ Eagle Butte
Nearest City, State	Gillette, WY
Proximate Analysis, % (as received)	
Moisture	30.68
Ash	4.93
Volatile Matter	33.66
Fixed Carbon	30.73
Sulfur	0.35
Forms of Sulfur	
Pyritic	0.05
Organic	0.28
Sulfate	0.02
Ultimate Analysis, % (dry basis)	
Carbon	68.96
Hydrogen	5.29
Ash	7.11
Sulfur	0.50
Nitrogen	0.94
Chlorine	0.01
Oxygen	11.91
Btu/lb, as received	8,300
Btu/lb, Dry	11,975

3.0 Task 2--BENCH-SCALE MILD-GASIFICATION STUDY

The bench-scale mild-gasification testing is described in this section of the report (Merriam and Cha 1989).

3.1 Bench-Scale Mild-Gasification System

The inclined fluidized-bed (IFB) reactor is a long, shallow fluidized bed designed and constructed by WRI to cause plug-flow of solids in an excellent gas-solids contacting device. The plug-flow provides cross-flow of gas in relation to solids and offers the opportunity to control bed temperature profiles in a nonisothermal manner. The two reactors we used as a dryer and a mild-gasification reactor (Figure 1) had previously been used for oil shale retorting and combustion of spent oil shales and tar sands.

The reactors (Table 2) are 5 feet long to provide 5 to 10 minutes of solids residence time using slopes of 3 and 0 degrees, respectively. Fluidizing gas is introduced through holes in the bottom of a 1-inch pipe that runs the length of the reactor. Multiple gas outlets and symmetrical gas outlet piping are used to provide for uniform vertical gas velocity with no significant horizontal gas flow inside the reactor. The reactor is V-shaped to provide good heat transfer from external heaters through the wall to solids in the fluidized bed. Solids and gas sample points are installed at one-fourth, one-half, and three-fourths of the length of the reactor and at the solids outlet. The solids sample ports permit us to evaluate samples at one-fourth, one-half, three-fourths and the full solids residence time. The reactors are equipped with four pairs of independently controlled electrical heaters mounted along the outside.

Table 2. Summary of Design Conditions for the Inclined Fluidized-Bed Reactors

Size:	5 feet long, 6 inches wide, 7.5 inches high
Material:	304 stainless steel with welded joints
Rating:	1500°F (816°C) wall temperature at 1.0 psig
Solids Flow:	0-20 lb/hr of 0.5-mm particles with specific gravity of 2.2 gm/cm ³
Fluid Flow Rate:	0-25 scfm for many gases
Fluid Preheat:	6000 Btu/hr to 900°F (482°C)
Reactor Heat:	15,000 Btu/hr on 2.7 ft ² of heated surface
Flow:	Horizontal plug-flow of solids Vertical flow of fluidizing gas

End View

Thermocouples

- In Reactor (opposite sample points)
- ⊗ Outer Surface (both sides)

- GI Gas In
- GO Gas Out
- SI Solids In
- SO Solids Out
- SSP Solids Sample Point
- GSP Gas Sample Point
- B Baffle

Figure 1. Inclined Fluid-Bed Reactor Details

The initial drying tests were conducted using an IFB reactor with a variable-speed coal feeder, gas preheater, cyclone, water-cooled condenser, gas-liquid separator, and effluent gas filters. The system was sized to handle 10 lb/hr of wet coal (25 to 30 wt % moisture) fluidized in carbon dioxide while heating the coal to 700°F (371°C).

We intended to dry the coal to zero moisture and remove as much carbon dioxide as possible without releasing any pollutants into the atmosphere or into the condensed water. Because the process we are developing will use recycle gas, it is necessary to condense clean water from the gas stream. The first tests using this system resulted in a buildup of coal dust in the condenser inlet. Consequently, we replaced the condenser with a water spray and separator to remove coal dust. The spray was so effective at separating coal dust from the gas that we stopped using filters in the gas line for subsequent tests. We also used a small boiler to inject steam into the fluidizing gas for three tests, which were conducted to study the effects of fluidizing gas water content upon drying rate and residual water content of the dried coal.

Test startup began by flowing carbon dioxide through the drying system while bringing the temperatures to the desired level. We used carbon dioxide that had flowed once through the reactor to simulate recycle gas (which we expect is predominantly carbon dioxide) and avoid the expense of installing a recycle-gas system. A small flow of nitrogen was injected into the carbon dioxide as a tracer. When the flows and temperatures were properly adjusted, we started to feed coal. The introduction of solids into the dryer caused the temperatures to drop, so we again adjusted heater set points to bring temperatures to the desired level. When the temperatures were at the desired level with coal flowing, we emptied the cyclone, the dried coal receiver, and the water collection pot and started the test.

After we conducted nine tests using the drying system separately, we combined it with the mild-gasification system to produce dried coal for mild gasification (Figure 2). The mild-gasification system used for the initial tests consisted of a gas flow meter and controller, a gas heater, an IFB reactor identical to the dryer, char receivers, an effluent gas cyclone, and a two-stage oil-condensing system designed to condense and separate heavy oil at 400°F (204°C) and the remaining oil at 40°F (4°C). The dryer and mild-gasification reactors were connected by a lock-hopper that permitted dried coal to pass but prevented the flow of gas from one reactor to the other. The procedure used for the mild-gasification tests was similar to that used for drying tests. The gas flows were started, temperatures adjusted, coal feed introduced, temperatures readjusted, products discarded, and then the test period was begun. We used carbon dioxide as fluidizing gas, except for two tests in which we used nitrogen and steam mixed with carbon dioxide.

The size of particles that we were able to test in the dryer/mild-gasification unit was limited by the capacity of heaters. Larger particles require higher flow rates of fluidizing gas that, in turn, require higher heating capacity. We limited the tests to three particle-size ranges that were within the heating and gas flow capacity of our existing equipment.

Figure 2. Bench-Scale Drying and Mild Gasification System

We were able to conduct tests at bed temperatures up to 1175°F (635°C) with the largest particle size range (average particle size of 0.020 inches) and up to 1225°F (660°C) with the smallest size (0.004-inch particles).

3.2 Bench-Scale Mild Gasification Test Results

WRI conducted 23 successful coal-drying tests and 14 successful mild-gasification tests using inclined fluidized-bed reactors. The tests in the 10-lb/hr reactors ran for four to sixteen hours with most tests maintaining steady-state conditions for eight hours. The effects of bed temperature, particle size, and drying-gas water content on the drying rates and residual moisture content of the dried coal were determined. Coal was readily dried to zero moisture, and about 1 wt % of the raw coal was driven off as carbon dioxide by partial decarboxylation at a maximum bed temperature of 575°F (302°C) using a solids residence time of five minutes. The drying rate was slightly slower using 0.050 lb of water per lb of dry carbon dioxide than when 0.030 and 0.015 lb/lb were used. Differences in particle size from 0.004 to 0.020 inch did not measurably affect the drying rate or residual moisture content of the coal.

The effects of bed temperature, heating rate, coal particle size, solids residence time, and fluidizing-gas composition on the yield of liquid products and the composition of char and gas produced were determined from the mild-gasification tests. The char contained 11 to 19 wt % volatiles, had hydrogen-to-oxygen mass ratios of 0.18 to 0.30, and had heating values of 12,333 to 12,905 Btu/lb. The volatiles content and the hydrogen-to-oxygen ratio of the char were reduced by increasing the maximum bed temperature in the mild-gasification reactor from 1100 to 1200°F (593 to 649°C). The hydrogen-to-oxygen mass ratios were greater than the 0.125 value needed to supply hydrogen for formation of water during char upgrading, avoiding any need for makeup hydrogen.

Liquid products collected varied from 8.3 to 18.1 wt % of the MAF coal with most of the coal liquids boiling above 700°F (371°C), a characteristic needed for electrode-binder pitch. The median hydrogen-to-carbon atomic ratio of the condensates was 1.23. Maximum liquid yield occurred at a maximum bed temperature of about 1150°F (621°C). The yield of coal liquids increased with higher heating rates in the inlet portion of the mild-gasification bed. We were not able to determine any effect of particle size on yield from 0.004- to 0.020-inch average particle size.

The produced gas had typical heating values of about 675 Btu/scf and contained 30 to 50% by volume carbon monoxide and about 3600 ppm hydrogen sulfide. A test using steam as the fluidizing gas produced gas that contained about 40% hydrogen.

4.0 Task 3--BENCH-SCALE CHAR UPGRADING STUDY

This section of the report describes the equipment used and the results obtained from bench-scale char upgrading work. Task 3, the bench-scale char

upgrading study, was performed by AMAX R&D and completed in mid-1989. The results have been presented in a topical report (Jha and McCormick, 1989).

As discussed earlier, it was concluded in Task 1 that the char should be upgraded to pure carbon, which could be used in several markets depending upon its particle size. In view of its interest in the technology, Amax Coal Industries provided funds to supplement the DOE project to develop a proprietary CTC process.

4.1 Process Chemistry

The mild gasification char contains ash as the primary impurity and heteroatoms as the secondary impurity. The CTC process developed by AMAX separates the carbon present in the char from these impurities without using any external chemical reagent.

The process involves two steps. In the first step, the carbon present in char is converted to methane according to the reaction:

In the second step, the reverse reaction takes place at a higher temperature, producing carbon and hydrogen to be recycled to the first step:

The ash is left behind in the spent char which also retains most of the sulfur. Nitrogen, oxygen, and hydrogen impurities are gasified, along with carbon, but they remain in the gas phase during carbon formation and are removed from the system as part of the bleed gas.

The first reaction is exothermic and the reverse reaction is endothermic. In the temperature range of interest, the heat of reaction is about 42,000 Btu/lbmole or 24 kcal/gmole. Thus, the main challenge in commercializing this process will be the design of reactors that will permit efficient energy recovery from the first reactor and efficient energy input into the second reactor so that overall energy cost is kept low.

Thermodynamic calculation of equilibrium gas compositions for this system indicates that methane formation is favored at high pressure and low temperature. At low temperatures, reaction rates tend to be very slow, so in practice, this reaction must be performed at 1,300°F (705°C) or above. Also, the pressure at which this reaction can be conducted is constrained by pressure vessel cost and the cost of gas compression. Carbon formation is favorable at high temperatures, and in commercial furnace and thermal black plants, temperatures well above 2,000°F (1095°C) are employed.

The goal of Task 3, therefore, was to study these two reactions separately to determine the effect of operating conditions on the two conversions. Bench-scale batch reactors were used in these studies to provide proof of concept

results. These results were then used to design a continuous integrated process research unit under Task 4.

4.2 Char-Methanation Tests

The test apparatus consisted of a 2-inch diameter Haynes alloy reactor which was heated by an electric tube furnace. The reactor was used as a fixed bed of char through which a mixture of hydrogen/methane flowed at a specified pressure and flow rate (controlled by a back pressure regulator and mass flowmeters). Product gas was analyzed by gas chromatography, and the methane content was also determined using a continuous gas analyzer.

A run was started by putting in a weighed amount of char into the reactor (60 to 160 grams). The reactor was then sealed and pressure tested in nitrogen at a specified test pressure (200 to 400 psia). It was then heated in a flowing stream of nitrogen to the desired temperature 1292 to 1652°F (700 to 900°C). At this point, the gas flow was switched to hydrogen and the run clock was started. Product gas was analyzed by gas chromatograph about every 10 minutes. The test was usually continued for 4 hours. At the end of the run, the unit was flushed with nitrogen and depressurized as it cooled to room temperature.

The residual char was weighed and analyzed to calculate the percent conversion. Gas flow rates and methane/hydrogen concentrations were used to calculate the conversion at different times during the test.

A large number of bench-scale methanation tests were conducted using chars produced by WRI in Task 2. These tests indicated that for the range of mild gasification conditions studied, there were only minor differences in char properties with regard to methanation reactivity. Results also indicated that acceptably high rates of methane formation (70 - 75 percent conversion in less than 2 hours) could be achieved at 1,300 to 1,475°F (705 to 800°C) and 200 to 300 psia. Temperature had a significant effect on the ultimate carbon conversion which could be achieved, however. This effect is shown in Figure 3, where total conversion as a function of time for fixed-bed char methanation runs is plotted as a function of time.

Based on the results detailed in the topical report, a temperature of 1,400°F (760°C) and 300 psia were chosen as the design basis for the continuous unit to be built in Task 4.

Figure 3. Conversion versus Time Plots for Methanation of Mild-Gasification Char

Studies of the fate of char heteroatoms during methanation indicated that very little sulfur is liberated during reaction with hydrogen. The data also indicate that most of the nitrogen and virtually all of the oxygen in the chars are gasified. The oxygen reacts with hydrogen to form water under methanation conditions and, therefore, consumes valuable hydrogen. Fortunately, there is enough hydrogen present in the chars to accommodate this. Carbon conversion was slightly higher for chars with higher oxygen content.

Table 3 shows the analysis of a typical mild gasification char and a spent char produced by methanation at nominal conditions of 1,400°F (760°C) and 300 psig. On a moisture- and ash-free (MAF) basis, the spent char contains more carbon than the starting char because of the high level of gasification of hydrogen, nitrogen, and oxygen.

Table 3. Properties of Mild Gasification Char and Spent Char

	Fresh	Spent
<hr/>		
Proximate Analysis, Weight %		
Fixed Carbon	74.7	Not Determined
Volatile Matter	16.3	Not Determined
Moisture	0.2	0.0
Ash	8.8	19.8
<hr/>		
Ultimate Analysis, Weight % (maf)		
Carbon	84.3	93.0
Hydrogen	2.6	1.4
Nitrogen	1.3	0.1
Sulfur	0.5	1.1
Oxygen	11.3	4.4
<hr/>		

4.3 Carbon-Formation Tests

Conventional thermal black processes for decomposing CH₄ to carbon and H₂ operate at atmospheric pressure and temperatures between 2,300 and 2,800°F (1260 and 1540°C). At these conditions, thermodynamics favor an equilibrium gas composition very low in residual CH₄. Process concepts similar to the thermal black process were investigated during Task 3.

Under Task 3, a 1-inch diameter, indirectly heated mullite tube reactor was used to study carbon formation from methane-hydrogen mixtures. Gas composition was varied from 33 to 66 volume percent hydrogen (balance methane). In one test, 0.1 volume percent H₂S was also included in the feed gas. The heated zone of this reactor was 6-inches long and residence time was varied from 0.07 to 7.7 seconds. Fourteen tests were conducted covering the temperature range from 2190 to 2550°F (1200 to 1400°C). The carbon product was entrained from the reactor, cooled in a double pipe heat exchanger and separated from the gas in a bag filter. Run duration ranged from 30 to 360 minutes.

The average particle size of the carbon product ranged from 64 to 143 nm, as determined by transmission electron microscopy. Particle size was dependent upon residence time and gas composition. Surface area of the product ranged from 15 to 43 m²/g. These properties indicate that the carbon produced is similar to a coarse grade furnace black or a fine grade thermal black. Most of the product samples were more than 99 wt % carbon although samples produced at lower temperatures could contain up to 1 wt % hydrogen. In the test conducted with 0.1 volume percent H₂S in the feed, the product carbon contained 0.06 wt % sulfur.

Thermal black processes use two regenerative checker work reactors in tandem. While one reactor is being used for cracking methane, the other is being heated by burning the exhaust gas (from the other reactor) and the carbon left on the checker work from the previous cycle. The main drawbacks of this process are: (a) low carbon recovery of about 50 percent, (b) variation in product particle size because of variation of temperature during a cycle, and (c) contamination of product hydrogen from combustion products left in the reactor from the heating cycle.

To avoid these problems, AMAX R&D conducted tests during the fall of 1989 on the development of an indirectly heated, continuous process for methane cracking to produce carbon. Thermodynamic calculations and preliminary high pressure TGA experiments indicated that at elevated pressure (50 to 150 psia), carbon can form from methane at temperatures as low as 1,650°F (900°C).

Further test work at bench scale using the methanation reactor and synthetic methane/hydrogen gas mixture indicated that the concept was indeed feasible. This resulted in a significant process simplification relative to the thermal black option because metal rather than ceramic reactors can be used for carbon production and the process can be continuous rather than cyclic.

During bench-scale testing, reaction conditions were narrowed down to 1,500 to 1,800°F (815 to 980°C) and 50 to 150 psia. At these conditions, particularly in the presence of carbon seed particles to act as nucleation sites for the formation of new carbon, reaction rates are reasonably fast and the materials of construction and fabrication techniques for the reactor are available.

From the standpoint of integrating these two reactors into a single process, it is desirable to operate them at similar pressures and temperatures in order to achieve a high mechanical and thermal energy efficiency. These conditions do, however, raise the equilibrium methane content in the residual gas to about 20 to 30 volume percent, i.e., diminish the one pass conversion efficiency which would require a large excess of hydrogen recycle. To overcome this problem, a gas separation membrane was included in the process flowsheet, as described under Task 4.

The results of a series of bench-scale carbon formation runs are shown in Table 4. While not reported in Table 4, it was also observed that longer seed carbon residence times produced larger product particles. Particles as large as 100 microns have been produced by this method. While fine, submicron carbon particles are required in the carbon black market for rubber compounding, coarser carbon is required for the anode carbon market.

Table 4. Results of High Pressure Carbon Formation Studies

Temperature, °F	Pressure, psig	Seed Diameter, Microns	Product Diameter, Microns
1,650	50	None	0.1
1,650	100	None	0.4
1,560	100	0.2	0.2
1,650	50	0.2	0.3
1,650	100	0.2	2.0

The Task 3 results indicated that both coarse and fine carbon might be produced by this technology, if a proper reactor is designed.

4.4 Production of Activated Carbon

After the Task 3 test program was completed and the topical report was submitted to DOE, AMAX R&D continued to develop the process with AMAX funds to improve its economics. The concept of including activated carbon as one of the coproducts of the CTC process was developed during this time. While the market for activated carbon is small, the price is high (\$1,000/ton or more), so its addition to the product slate may significantly enhance the economics.

Analysis of the spent char materials indicated that they could be upgraded to activated carbon. Surface areas of the spent chars range up to 800 m²/g. Upon removal of low surface area ash by acid leaching or gravity separation, the surface area increases still further. Figure 4 compares phenol adsorption isotherms for Amax activated carbon produced by upgrading spent methanation char and a commercial activated carbon (Darco KB-B). The Amax carbon compares quite favorably with the commercial carbon in terms of phenol adsorption.

Figure 4. Phenol Adsorption Isotherms for Darco KB-B and AMAX activated carbon

4.5 Conclusions from Task 3

Work performed under Task 3, or soon after, led to the following conclusions on the char upgrading, CTC, process:

- Mild gasification chars have a relatively high reactivity in hydrogen and can be converted to methane in the temperature range of 1,300 to 1,550°F (705 to 845°C) and the pressure range of 200 to 300 psig. Carbon conversions in excess of 70 weight percent can be obtained in less than 2 hours.
- Sulfur in the mild gasification char is not gasified and so remains with spent char or ash.
- The spent char is easily upgraded to a high surface area activated carbon.
- The production of carbon from methane in a continuous, indirectly heated reactor is feasible. At moderate pressures of 50 to 100 psia, the reaction can take place at 1650°F (900°C). Under these conditions, metal tubes can be used to supply heat indirectly.

- The carbon produced in this type of reactor has properties which depend upon the temperature, gas composition, residence time, and seed carbon employed.

5.0 Task 4--SYSTEM INTEGRATION STUDIES-MILD GASIFICATION PRU

This section of the report describes the mild-gasification PRU and results of tests conducted using the PRU (Merriam et al. 1990).

5.1 Mild-Gasification PRU

The mild-gasification PRU (Figure 5) consists of a coal feed system and drying system (left-half of Figure 5) and a mild-gasification system (right-half). The PRU was designed and equipment procured by Riley Stoker Corporation. After assembly of the drying and mild-gasification systems at Riley Research Center, the equipment was partially disassembled and shipped to WRI. WRI reassembled the system, added utilities systems, and conducted shakedown tests to locate and fix problems with the equipment.

We replaced the solids pump (Figure 5) used to feed coal to the dryer with a lockhopper before test 115. The PRU also has a lockhopper between the drying reactor and the mild-gasification reactor that is not shown in Figure 5. The equipment (Table 5) has all wetted parts made of 304 stainless steel.

The IFB reactors used for drying and mild gasification feature plug-flow of solids along shallow beds fluidized by cross-flow of gas (Figure 6). The plug-flow of solids permits nonisothermal control of bed temperatures and allows small and large particles to have the same residence times. The cross-flow of gas through the shallow beds rapidly sweeps volatiles out of the beds and causes a high concentration gradient between volatiles in the particles and in the bulk gas flow. The plug-flow also permits solids to flow from the beds at temperatures above the temperature of the effluent gas, indicating higher thermal efficiency than conventional fluidized beds. Plug-flow also permits us to collect solids samples with the distance along the bed proportional to residence time.

Figure 6. Solid and Gas Flow in Inclined Fluidized-Bed Reactor

Table 5. Summary of Design Conditions for the Mild-Gasification PRU

Coal Feed Rate	100 lb/hr
Coal Size	minus 8-mesh
Drying System	
Recycle Gas Flow	72 scfm
Heater Capacity	40 kW
Reactor	0.35 x 6.75 ft IFB
Condensers (3)	70,000 Btu/hr
Condensers (2)	18,000 Btu/hr
Design Operating Pressure	3 psig
Mild-Gasification System	
Recycle Gas Flow	76 scfm
Heater 1	16 kW
Heater 2	65 kW
Reactor	0.35 x 10.8 ft IFB
Air-Cooled Condensers	85,900 Btu/hr
Water/Glycol-Cooled Condensers (3)	76,330 Btu/hr
Electrostatic Precip. Loading	4.2 gr/scf
Chilled Condenser	17,500 Btu/hr
Design Operating Pressure	4 psig

Gases are analyzed once each hour using gas chromatographs. The chromatographs use thermoconductivity detectors for general gases such as CO₂, photometric detectors for hydrocarbon gases; and flame ionization detectors for sulfur species.

Coal feed rate is controlled using a variable-speed screw feeder. Recycle gas flows are controlled by differential pressure controllers across the blowers. The flow rates are measured using turbine meters with temperature and pressure compensators. Temperature of the recycle gas in both the drying and mild-gasification loops is controlled by electronic controllers, which vary the power load to the heaters to maintain a set outlet gas temperature. Both the dryer and mild-gasification reactor are equipped with adiabatic heaters that are automatically controlled. Pressure is maintained in both loops by vent valves, which are operated by pressure controllers.

The water-cooled condensers in the mild-gasification system develop a high pressure drop when the gas outlet temperature falls below 70°F (21°C). Therefore, we control the gas outlet at 70 to 80°F (21 to 27°C). Apparently, heavy tars build up in the tubes at low temperature. The pressure drop across the chilled condenser increases rapidly when the gas outlet temperature is below 75°F (24°C). Therefore, we control the gas outlet temperature at 75 to 85°F (24 to 29°C) to avoid the formation of hydrates in the tubes.

Pressures, temperatures, flow rates, and differential pressures are read by a computer and displayed on a screen that is updated every 30 seconds. Key parameters are displayed graphically to assist in controlling conditions during tests. All of the data are stored on discs, and a hard copy is printed with data shown at 5-minute intervals. All of the liquid and solid materials are weighed. Gas flow from the dryer is measured using a dry-gas meter. Gas produced in the mild-gasification reactor is computed from gas analyses using a metered flow of 0.1 scfm of argon as a tracer.

Coal Preparation

Wyodak coal from the sampling system at the AMAX Eagle Butte mine is shipped in sealed steel drums to the PRU. The coal is screened to remove the plus 8-mesh particles, which typically are about 20 wt % of the coal. The minus 8-mesh fraction (Table 6) is stored for use in the PRU.

The moisture from the coal, typically 30 wt %, migrates to the outer and lower portions of the drums when the coal is stored out of doors in warm weather. When the coal contains about 33 wt % or more moisture, it is sticky and plugs the discharge from the feed screw. The coal will flow freely when it contains about 25 wt % moisture or less. The screened coal is stored indoors to avoid temperature cycles and is spread on the concrete floor to predry the coal overnight. This procedure results in coal containing about 28-29 wt % moisture that will flow through the feed system and plug the discharge from the feed screw less frequently.

Table 6. Feed Coal Size

Screen, mesh ^a	Sample, wt % Retained			
	A	B	C	D
6	0	0	1.1	1.2
8	0.6	5.0	6.0	5.7
20	42.5	33.0	48.1	48.1
40	29.6	25.3	24.3	23.7
70	16.8	19.3	11.2	10.9
100	4.6	5.6	2.8	2.9
140	2.3	4.5	2.0	2.1
200	1.0	1.8	0.8	1.0
Pan	2.6	5.5	3.6	4.2

^a U.S. Standard

Coal Drying

The operating procedure for the drying tests is to purge air out of the system using CO₂, turn on the recycle gas blower, start the coolant flow to the condensers, and heat the fluidizing gas to 400°F (204°C). The coal feed is started to the dryer when the reactor temperature is below 450°F (232°C) to avoid heating the Nomex™ bags in the dust filter to greater than 450°F. When the coal enters the drying reactor, the effluent gas temperature decreases. We then increase the temperature of the fluidizing gas to the temperature for the test. If the flow of coal is interrupted, it is necessary to reduce the temperature of the fluidizing gas to avoid damage to the filter bags.

A flow of about 10 scfh of CO₂ into the dryer feed lockhopper prevents moisture in gas from the dryer from being condensed on coal in the feed system. About one-half of the purge gas flows into the dryer, and the other one-half is vented through the feed screw. The drying system has a leak rate of 21 scfh at 3.0 psig and ambient temperature. Thus, during tests when the rate of gas production is less than 16 scfh, it is necessary to add CO₂ into the drying system to maintain a positive pressure on the system to prevent air from leaking into the system. We typically operate the drying system with 0.5 psig at the recycle blower suction and 3.0 psig at the blower discharge.

Mild-Gasification Tests

The procedure for operating the mild-gasification system is to purge the system using CO₂ until no oxygen is detected in the loop, establish the flow rate, and then turn on the heaters and cooling system. When the bed temperatures reach 900°F (482°C), we turn on the electrostatic precipitator (ESP), the lockhoppers, and the coal feed. The temperatures and flow rate of recycle gas are then adjusted to the values specified for the test. The selected steady-state temperatures are typically reached in about 2 hours. When production of gas is detected, we light the flare used to burn the gas produced. The recycle gas composition reaches steady state in 3 to 5 hours. We typically operate the mild-gasification system with 0.5 psig at the suction of the recycle-gas blower and 7 psig at the discharge.

Fines from the cyclone and char from the reactor flow continuously into collection drums. Liquid products are drained from the system each half-hour into sealed collection pails and drums. Liquid drain lines from the air-cooled condensers are held at 400°F (204°C), whereas drain lines from the water-cooled condensers and ESP are heated to 250°F (121°C). The drain line from the chilled condenser is not heated.

The pressure profile in the mild-gasification PRU at typical operating conditions is blower discharge, 7.0 psig; reactor, 6.0 psig; outlet from air-cooled condensers, 2.7 psig; outlet from water-cooled condensers, 1.7 psig; outlet from ESP, 1.5 psig; outlet from chilled condenser, 0.5 psig; and the blower suction pressure, 0.5 psig.

Collection of Coal Liquids

Collection of the liquid products from these tests is difficult because of the properties of the liquids. Some of the heavier liquids have pour points greater than 150°F (66°C), whereas light liquids have relatively high vapor pressures at 150°F. Much of the liquid enters the collection system in the form of mist. Dust from the reactor, which is not separated in the cyclone, collects in the liquids, as does water.

5.2 Mild-Gasification PRU Test Results

Drying tests were conducted as part of mild-gasification tests for tests 115 and later (Table 7). Material balance results for drying tests 115 and later are reported as part of mild-gasification tests.

A sample of raw coal and samples from the dryer heated to 310 and 550°F (154 and 288°C), respectively, were analyzed using infrared spectroscopy to verify that decarboxylation does occur in the dryer.

Table 7. Conditions Used for Drying Coal During Mild-Gasification Tests

Test:	115	117	118	119	120	122	123	124	125	126
Fluidizing Gas										
Flow, scfm	93	92	84	86	83	81	82	80	87	81
Temp, °F	540	540	620	540	699	710	817	754	578	709
Coal Feed Rate, lb/hr	104	119	94	93	107	96	149	138	149	93
Bed Temp, °F										
Zone 1 (0.16)	130	128	129	128	136	142	169	178	159	145
Zone 2 (0.48)	162	151	163	150	230	267	224	254	181	287
Zone 3 (0.79)	296	284	420	347	531	549	430	466	277	547
Water in Coal, wt %										
Zone 1 (0.28)	18.4	5.8	0.6	-	5.5	1.5	1.2	-	9.6	16.2
Zone 2 (0.59)	2.0	0.8	0.1	-	0.4	1.3	0.0	-	0.5	2.3
Zone 3 (0.91)	0.0	0.0	0.0	-	0.0	0.3	0.4	-	0.0	0.0
Test Duration, hr	24	24	25	25	25	103	102	64	98	24

All tests were conducted using minus 8-mesh Wyodak coal and a coal residence time of approximately three minutes.

Numbers in parentheses () show fraction of bed length

The mild-gasification tests were conducted to determine the effects of maximum bed temperature and heating rate upon the yield of liquid products (zone 4 in Table 8).

Table 8. Conditions Used for Mild-Gasification Tests

Test	Bed Temperature, °F				Heating Rate, °F/min	
	Zone 1 (0.1242)	Zone 2 (0.3747)	Zone 3 (0.6253)	Zone 4 (0.8758)	Zone 1	Zone 2
115	659	869	914	950	325	93
117	669	916	987	1043	344	110
118	777	1010	1068	1129	319	103
119	721	952	995	1050	335	102
120	794	1023	1071	1131	235	102
122	880	1061	1124	1113	381	83
123	822	1030	1040	1051	574	95
124	941	1020	1080	1079	695	36
125	722	907	974	993	651	84
126	827	1036	1133	1146	322	95

Numbers in parentheses () show fraction of bed length

All mild-gasification tests were conducted using recycle-gas (fluidizing-gas) flow rates of approximately 80 scfm. The char residence times were approximately 9 minutes for tests 115 through 120, 7 minutes for tests 122 and 126, and 5.5 minutes for tests 123 through 125. Char residence times are defined as the weight of char in the bed divided by the average char production rate.

Material balances for the tests are listed as wt % of the raw coal feed (Table 9). Following test 120, we revised the liquid receivers to increase the capacity of the containers and reduce plugging in drain lines. This was done by combining the drains from air-cooled condenser 6 and water-cooled condenser 1 with drains from water-cooled condensers 2 and 3. All weights were determined by placing materials on a scale, except the weight of gas produced. The amount of gas produced in the dryer was determined from volatile balances. The amount of gas produced in the mild-gasification loop was determined by argon tracer balance for all tests except 122. After test 122, we found that the meter used to measure the argon flow had gradually failed during the test. The amount of gas produced during test 122 was determined by forcing closure on the mass balance.

Table 9. Product Distribution from Mild-Gasification (MG) Tests, wt % of raw coal

Test:	115	117	118	119	120	122	123	124	125	126
Raw Coal Feed	100.0	100.0	100.0	100.0	100.0	100.0	100.0	100.0	100.0	100.0
Fines from Dryer	5.2	5.5	5.8	6.7	6.9	4.7	4.8	5.5	5.0	8.2
Dust from Dryer	0.0	0.0	0.9	0.3	0.2	0.1	0.0	0.0	0.2	0.0
Water from Dryer	28.9	29.8	28.9	29.4	26.4	30.7	30.1	30.8	29.3	30.5
Gas from Dryer	0.8	0.9	0.7	0.8	1.0	2.3	2.0	2.3	1.7	1.1
Fines from MG	1.9	2.5	2.5	2.2	4.6	6.2	6.2	6.8	6.6	6.2
Char	42.8	40.0	39.1	40.4	40.7	36.4	38.1	37.2	40.4	39.7
Gas from MG	3.5	8.9	9.8	8.5	9.4	7.1	5.0	7.3	4.2	6.2
Liquids from MG										
ACC 1-3	0.2	0.2	0.3	0.2	0.2	0.3	0.2	0.0	0.4	0.5
ACC 6, WCC 1	3.2	6.3	3.3	3.3	3.4	7.6	7.2	7.3	4.6	6.2
WCC 2, WCC 3	4.0	5.2	5.0	4.8	5.3					
ESP	1.6	2.3	3.1	2.5	2.4	3.6	2.3	3.0	3.4	2.4
Chilled Cond.	1.1	0.7	1.9	1.8	1.4	1.1	2.6	2.7	2.2	2.6
Total Out	93.2	102.3	101.5	100.5	101.7	100.2	98.7	102.9	98.0	103.7

Liquid products collected from ACC 6 and WCC 1 were combined with liquids drained from WCC 2 and WCC 3 for all tests after 120.

The yields of dry liquids based upon the MAF coal feed to the mild-gasification reactor range from 9.8 to 17.0% (Table 10). Yields from the 10-lb/hr tests range from 8.3 to 18.1% (Merriam 1989). The maximum yield from the 10-lb/hr tests occurred at about 1100 to 1150°F (593 to 621°C). Data from the 100-lb/hr PRU tests show yields increasing with temperatures to about 1100 to 1150°F (Figure 7). However, we were not able to conduct tests in the PRU above the 1100 to 1150°F range to verify a decrease in yields at higher temperatures determined in the 10-lb/hr tests.

The distribution of products from mild-gasification tests (Figure 8) is based upon the exclusion of fines from both the dryer and mild-gasification system. The gases produced in the dryer and mild-gasification systems, char, dry coal liquids, and water from pyrolysis (produced in the mild-gasification system) are normalized to make the sum of the products equal to 100%. These adjustments have the effect of removing fines production and losses (or gains) as variations in the data. We then focus on the effect that temperature has on the distribution of the products.

In Figure 8, we have included the water collected from pyrolysis in the mild-gasification section of the PRU because we think the recycle gas system causes water to form from gaseous products. Gaseous products from the bench-scale reactor had little chance to react in the carbon dioxide flowing once through the reactor. Thus, we think gas produced in the PRU is more directly comparable to gas produced in the bench-scale unit if pyrolysis water is included. The adjusted data show good agreement between the bench-scale and PRU units.

Figure 7. Yield of Dry Coal Liquid Products at Various Bed Temperatures

Figure 8. Distribution of Products from Mild Gasification at Various Maximum Bed Temperatures

Table 10. Summary of Liquids Produced by Mild Gasification (MG)

Test:	115	117	118	119	120	122	123	124	125	126
Water, lb	139.3	207.3	94.8	93.2	113.7	417.5	641.7	379.9	460.1	81.1
Water, wt % of raw coal	4.0	7.2	4.8	3.9	4.3	4.2	4.2	4.3	3.2	3.7
Hydrocarbons, lb	202.6	211.7	232.6	207.2	219.6	759.2	1230.5	766.8	1090.9	176.0
Hydrocarbons, wt % of raw coal	5.9	7.3	9.9	8.7	8.3	7.7	8.1	8.7	7.5	8.0
Yield based on MAF raw coal feed, %	9.1	11.4	15.4	13.5	12.9	12.0	12.5	13.5	11.4	12.4
Yield based on MAF coal feed to MG reactor, %	9.8	12.3	17.0	14.9	14.3	12.8	13.4	14.6	12.2	13.9

6.0 Task 4--SYSTEM INTEGRATION STUDIES, CHAR-TO-CARBON PRU

At the conclusion of Task 3, AMAX requested DOE/METC through WRI modify the scope of Task 4 of the contract to include design, construction, operation, and evaluation of a CTC PRU. The request was granted to build the CTC PRU at Amax R&D Center in Golden, Colorado, with partial funding by AMAX to purchase all the equipment and instruments.

The size of the PRU was specified at 50 pounds/hour to keep it comparable to the 100 pound/hour mild gasification PRU at WRI. About 27,000 pounds of char produced during various tests at WRI (discussed in the last chapter) was shipped to Golden, where some was used as the feedstock for the CTC PRU.

The CTC PRU was planned to achieve specific goals related to process development and commercialization of the technology. These goals were to:

- Validate process design, models, and control strategy.
- Develop start-up, shut-down, and operational procedures.
- Optimize process conditions.
- Produce product for market evaluation.
- Obtain data for scale-up to a 1 ton/hour process development unit.

The PRU was designed during the summer and fall of 1989 with assistance from BEI Engineers and Constructors of Lakewood, Colorado. Table 11 presents a summary of the PRU design conditions. Equipment procurement occurred during the winter of 1989 - 1990. An existing building in the Amax R&D pilot plant was revamped to house the PRU.

Construction activities began in February of 1990 and construction was completed in June of 1990. The Industrial Company (TIC) of Steamboat Springs, Colorado, acted as the general contractor. Shakedown and testing occurred during July. Process development runs in the PRU commenced at the end of July 1990 and continued until July 1991.

The PRU consists of a char methanation fluid-bed reactor, indirectly heated carbon formation fluid-bed reactor, gas separation membrane, two compressors, several heat exchangers, filters, systems for feeding and discharging solids, and systems for supplying start-up gases to the process. The plant is entirely computer controlled, and process gas analysis is performed with a mass spectrometer.

Details of the PRU equipment, operating procedures, control systems, and safety precautions are described in the topical report prepared by Amax R&D for this task (Jha et al. 1991).

Table 11. Summary of Design Conditions for CTC PRU

Char Feed Rate	50 lb/hr
Char Size	minus 10-mesh
Methanation System	
Feed Gas Flow	60 scfm
Hydrogen Content	96 vol percent
Preheater Capacity	16 kW
Reactor Dimensions	
Bottom Zone	5" dia x 4'2" height
Top Zone	10" dia x 4'1" height
Temperature	1382°F
Pressure	311 psia
Spent Char Discharge Rate	15-lb/hr
Carbon Formation System	
Feed Gas Flow	54 scfm
Methane Content	60 vol %
Glow Bar Capacity	51 kW
Heat Transfer Surface Area	14 ft ²
Reactor Dimensions	20" dia x 8'5" height
Temperature	1652°F
Pressure	95 psia
Carbon Production Rate	28-lb/hr

6.1 Description of Char-to-Carbon PRU

The following paragraphs describe the PRU in general terms. The plant included some unique design features which are discussed next, along with the modifications that were made to improve the operability of the plant. The results are summarized in the last section.

A simplified flowsheet for the PRU is shown in Figure 9. In addition to those systems shown in Figure 9, a hydrogen supply system consisting of a hydrogen tube trailer and associated gas regulators and piping was installed outside the battery limits of the plant. Also, a nitrogen purge system consisting of a liquid nitrogen tank and associated regulators and piping was installed. A flare system was installed for venting flammable gases.

Referring to Figure 9, mild gasification char is manually weighed and dumped into a feed bin. From here, char is conveyed by a screw feeder to the feed lock hopper and batch fed into the methanation unit at a nominal feed rate of 50 pounds/hour. Spent char exits the reactor through a discharge leg, J-valve, and lock hopper system and is conveyed in a water cooled screw to a nitrogen purged drum. Gas exiting the reactor passes through a cyclone and then a shell-and-tube heat exchanger where feed gas is preheated by cooling the exit gas.

Figure 9. Char-to-Carbon PRU

The cooled methane reactor exit gas is then mixed with the carbon reactor exit gas and passes through a set of filters to remove any solids not collected in the cyclones. The gas is then further cooled to condense water which is removed in a separator. The gas is then heated to well above the dew point, passes through a final set of filters, and fed to the gas separation membrane. The gas separation membrane produces a hydrogen-rich stream at about 90 psig and a methane-rich stream at about 290 psig.

The hydrogen-rich gas stream from gas separation is compressed to above 300 psig. This compressed gas is preheated by heat exchange with the methanation product gas and then heated further in an electric circulation heater before being fed to the methanation reactor.

The methane-rich gas stream from the membrane is reduced in pressure to about 100 psig and then passed through a shell-and-tube heat exchanger where it is preheated by the carbon reactor product gas. The preheated gas then enters the carbon reactor through sparge tubes. In the carbon reactor, methane is cracked to form carbon and hydrogen. The coarse carbon product is to be discharged from the bottom of the reactor into a J-valve and lock hopper system. Medium sized carbon particles can be removed as a bed overflow to the J-valve and lock hopper system.

Gas exiting the reactor passes through a cyclone where fines are collected and returned to the bed. The hot exit gas then preheats the feed gas and is fed to a second compressor. Here the gas is compressed to above 300 psig and then mixed with the methanation reactor product gas. Before compression, excess gas is bled out of the system.

Unique Design Features

The PRU was designed based on very limited data from batch tests performed on bench-scale under Task 3 (summarized in a previous chapter). However, several novel features were included in the design of the individual reactors and in their integration to improve the process. This was accomplished by a computer model and technical assistance from some consultants. These are discussed below, along with the modifications that were made during the one year operation of the plant.

Methanation Reactor

The design char feed rate into the methanation reactor is 40 to 60 pounds/hour. Methanation is performed in a refractory-lined steel reactor designed to operate at up to 1,500°F (815°C) at 300 psia. It consists of a lower, 5-inch diameter zone which operates as a slugging fluidized bed and an expanded top zone of 10-inch diameter which is not fluidized and should act like a moving bed. The purpose of this arrangement was to minimize entrainment and freeboard requirement. The bed discharged out the side of the 5-inch zone to a J-valve and lock hopper system.

The design was later modified so that the discharge pipe functioned as a bed overflow and served to control bed level at the top of the 5-inch zone. This resulted in reduced capacity but led to major improvements in operability.

The incoming fluidizing gas is about 95 to 99 percent H_2 , with the balance being CH_4 , N_2 , CO , and other impurities. The inlet gas flow rate was measured with a turbine flowmeter. The unit is designed to produce gas consisting of 30 to 40 percent CH_4 , 60 to 50 percent H_2 , and 5 to 10 percent other gas species as impurities after passing through a high pressure cyclone to return entrained solids to the reactor bed. The reactor is designed as an equilibrium reactor so that thermodynamics dictates the CH_4 -to- H_2 ratio in the product gas, depending on reactor temperature and pressure conditions. A lower temperature in the reactor will favor higher CH_4 concentration, but at the expense of a slower reaction rate.

Char is fed through a double valve lock hopper system, cycling at about a 5-minute frequency in the original design. This system was substantially modified to improve operability, and the modifications are described in the results section. Spent char was to be removed from the reactor on a variable time frequency such that level control was maintained in the fluid bed. This did not prove to be practical, and the discharge system was later modified to control bed level by bed overflow, as described in the results section. A lock hopper system similar to the feed system was used to remove the spent char from the reactor. This system was also substantially modified during PRU studies. After exiting the lock hopper system, the spent char was cooled in a water jacketed screw and transported to a sealed bin under a blanket of N_2 .

As designed, fluidizing gas entered the reactor at a temperature about $300^\circ F$ ($150^\circ C$) lower than reactor operating conditions. The amount of sensible heat required to heat the fluidizing gas to reactor conditions, plus the amount required to heat up the feed char, was expected to balance with the heat released in the exothermic reaction. In practice, heat losses were much higher than design and oxygen had to be injected to heat the reactor by burning a small fraction of the char or hydrogen. This modification was developed during PRU runs and is described in the results section.

Carbon Formation Reactor

The approach developed in Task 3 for carbon formation was implemented in the PRU in a fluid-bed reactor where the fluidized particles could function as seed carbon and as a heat transfer medium. The fluid-bed was designed for flexibility in the particle size range and distribution of the carbon product.

Gas entered the bed through sparge tubes, and inlet flow was monitored with a turbine flowmeter. Immersed in the bed were twelve horizontal Incoloy 800HT muffle tubes containing silicon carbide glow bars. These electric heating elements supplied the endothermic heat of reaction and sensible heat requirements through roughly 14 ft^2 of heat transfer surface area. Heat transfer coefficients were not high enough with this arrangement, however, and the unit was later modified to have vertical, finned tubes enclosing the glow

bars yielding 64 ft² of heat transfer surface area, including the fins. Because of the constraint of availability, stainless steel fins were welded on the Incoloy tubes. As will be discussed later, this was a mistake and caused severe problems. The unit was also modified to have a gas distribution plate to improve the quality of fluidization. In both designs, the glow bars and their electrical connections were enclosed in an air tight, nitrogen purged box which was constantly monitored for leakage of process gases.

Originally, carbon was to be removed via bed overflow through a lock hopper system, cooled in a water jacketed screw, and packed in cardboard drums. Also, by operating the reactor at higher gas velocities, finer carbon particles could be removed with a cyclone and lock hopper system. A third alternative was to remove only the largest particles of carbon from the bottom of the bed by using a bottom discharge and letting coarse carbon pass downward below the fluidizing zone. This was accomplished by using sparge pipes for gas distribution rather than a distribution plate. The open spaces between the sparge pipes allowed those particles large enough to defluidized to settle in the reactor and pass out. By using these three discharge methods, either separately or in combination, the product size distribution was expected to range from sub-micron to about 250 microns.

In practice, only fine carbon could be removed from the reactor, and this was collected in a baghouse which was added to the PRU flowsheet halfway through the test program.

Gas Separation Membrane

Gases exiting from both reaction steps were combined into a common mixed H₂/CH₄ gas stream and fed to a gas separation membrane to separate the mixed gas into a hydrogen-rich and a methane-rich stream. Design gas composition for the membrane feed gas ranged from 55 to 65 percent H₂ and 35 to 25 percent CH₄, with the balance being impurities. When the membrane is operated at an inlet pressure of 300 psia, the hydrogen-rich stream should range from 90 to 95 percent H₂, while the methane-rich stream should range from 60 to 65 percent CH₄. Most of the impurities should concentrate in the methane-rich stream. The hydrogen-rich stream discharges at 80 to 100 psia, while the methane-rich stream discharges at 290 psia. The most important variable in terms of membrane performance is the difference in H₂ partial pressure between the feed stream and the hydrogen-rich discharge stream. Increasing the pressure drop improves separation efficiency, as does increasing the H₂ content of the feed stream.

The membrane material is degraded by liquid water, so gases must always be above the dew point. A condensing cooler is used to lower the mixed gas temperature down to 122°F (50°C) which, at 300 psia, results in efficient condensation of water. If oxygen is not removed as water, it will convert to CO in the carbon formation reactor and be bled out with excess hydrogen. Conversion of oxygen to CO ultimately results in a greater loss of carbon from the process than would otherwise occur and in higher impurity concentrations in the recirculating gas. Therefore, water removal before membrane separation

results in significant benefits to the process in terms of carbon yield, removal of impurities from the recirculating gas, and volume of gas which must be recirculated.

After condensation of water, the gas is then reheated to 70°F (40°C) above the dew point and filtered before being sent to the membrane.

PRU OPERATION

The CTC PRU at Golden, Colorado, was operated for nearly one year (July 1990 - July 1991) during which 35 runs were completed, for a total of nearly 800 hours of operation. These runs included:

- Six shakedown runs during which the primary goal was to calibrate the instruments, develop start-up and shut-down procedures, and train the operators for safe operation of the plant.
- Ten methanation runs during which the primary focus was on the methane reactor and its modifications. The membrane was included in the flowsheet so that unreacted hydrogen could be recovered and reused. The methane-rich gas product was simply burned in the flare.
- Eight carbon formation runs during which the primary focus was the carbon formation reactor and its modifications. Bottled methane gas mixed with hydrogen from the tank was used in these runs and the exit gas was flared.
- Eleven integrated runs during which both the reactors were operated and emphasis was on demonstrating the proof of concept for the process, as well as on developing a better understanding of the process control.

The methanation and carbon formation runs were intermingled with the integrated runs. The scheduling was primarily dictated by what piece of equipment was being modified or replaced and what section of the plant could be operated without it. The main modifications were mentioned in the previous section. More detailed information can be found in the topical report.

The later runs were integrated runs which provided the data for process evaluation. The longest runs lasted for up to 3 days.

6.2 Char-to-Carbon PRU Test Results

Detailed results from selected runs are presented and analyzed in the topical report. A general discussion of the performance of the various units and the integrated plant is presented here.

Methane Reactor

Results from PRU operation confirmed that the carbon in char could be converted to methane in the presence of an excess of hydrogen gas at about 1,400°F (760°C) and 300 psia. However, the percent conversion of char to methane and the methane concentration in the exit gas were lower than design values. The reasons for non-attainment of design performance are discussed below, along with possible solutions.

The feeding and discharging of the high pressure reactor through Everlasting laps disk valves and an AMAX-designed J-valve proved difficult. These were replaced with a pressurized double-valve lock hopper system. A further modification of the feed system, a pressurized screw feeder or the addition of another lock hopper system, can ensure continuous feeding, which should provide more consistent operation.

The designed positioning of a moving bed on top of a fluidized bed did not work. The cold flow model showed that the solids mixing was extremely poor. In the reactor, this manifested as a temperature difference of 100°F (56°C) or more between different parts. To overcome this problem, only the lower part of the bed, a fluidized bed, was used. This, however, cut down the active reaction volume and solids residence time by almost half. This in turn resulted in incomplete char conversion to methane, about 25 to 35 percent compared to 70 to 75 percent called for by design. The incomplete conversion of char was the primary reason for lower methane concentration in the exit gas than designed for, about 15 to 20 percent CH₄ in comparison to 35 to 40 percent. Other factors might have also contributed, as discussed in the next paragraph. A revamping of the reactor to increase its active volume (and hence residence time), relocation of feed and discharge points to minimize bypassing, and control of particle size and gas velocity to insure proper fluidization (based on cold flow model studies) would allow attainment of design conversion rates.

The heat losses through the reactor walls and piping surfaces were much more than designed, even after they were insulated. The gas preheater at its peak design load could barely keep up with it. Higher than design hydrogen flow rates were used to improve the heat transfer and fluidization in the reactor. This caused a further reduction in methane concentration in the exit gas. The addition of oxygen, to start or maintain the reaction when exothermic heat was not enough due to operational problems, also contributed to lower methane concentration. Although improvement in insulation or addition of another gas preheater (in parallel) may help, these are not considered necessary for a future successful operation. If continuous feeding and longer residence time in a well fluidized reactor can be provided, as discussed above, there is enough heat of exothermic reaction (observed in the PRU runs) to overcome this problem.

Membrane Separation

The gas separation membrane worked very well, although the methane concentration in the gas feed stream was well below design conditions. With feed concentrations of about 20 percent, the residue exit stream approached 60

percent methane. On the permeate side, hydrogen recoveries approached 90 percent at 95 percent purity. Operation of the membrane was totally trouble free.

Carbon Reactor

As methane-rich gas passed through the carbon reactor at about 1,600°F (870°C) and 100 psia, it cracked to form carbon. The carbon yield was, however, very low due to inadequate gas residence time at design temperature. Some carbon was collected as fine carbon in the baghouse and some was deposited on seed carbon, as shown in Figure 10. Thus, the PRU operation confirmed the original concept of using a continuous indirectly heated fluidized-bed reactor for production of fine and coarse carbon.

However, most of the carbon was produced as pyrolytic carbon, either as scale on the metal surfaces, or as massive deposits between the tubes. Chemical analysis of carbon samples indicated that they were all contaminated with chromium, nickel, and iron metals. This totally unexpected result was caused by corrosion of the materials of construction, as discussed below.

During start-up, it was found that the reactor volume could not be heated up to the desired temperature without a fluidized bed of solids, which would improve heat transfer and also act as seed particles for carbon growth. After unsuccessful attempts with lampblack and mild gasification char as seed particles, Desulco was used. The design temperature of 1,600°F (870°C) or more, could not be reached with horizontally oriented silicon carbide glowbars enclosed in Incoloy muffle tubes.

As a means of increasing the heat transfer area in the reactor, the horizontal tubes were replaced with vertical finned tubes. Due to time and materials availability constraints, 316 stainless steel fins were welded to the Incoloy 800HT tubes. In retrospect, this was not a good decision. Heat applied to the Incoloy tubes where the fins were welded on sensitized the Incoloy alloy structure, caused carbon depletion from the grain structure to the grain boundaries. This lowered the corrosion resistance of the alloy at high temperatures and sensitized areas were deeply pitted. The present theory behind the pitting attack is that during conversion of methane to carbon, a liquid phase was formed on the hot alloy surfaces that resulted in localized violent boiling action that caused the pitting.

In addition, the 316 stainless steel, and to a lesser extent the Incoloy 800HT, were severely damaged by exposure to the high carbon and high temperature environment. These condition caused carburization of the metal. In the case of the 316 SS, spot analysis showed areas where the metal structure consisted only of an iron-carbon binary eutectic at 5.3 percent carbon. All of the original alloying agents such as chrome, nickel, and molybdenum were completely depleted from the metal structure.

Figure 10. Photomicrographs of cross sections of a) original seed carbon and b) seed carbon withdrawn from the reactor after Run C-8.

There was also some problem in optimizing electrical power input to the glowbars that limited heat transfer and maximum temperatures. Each glowbar had a slightly different high-temperature electrical resistance that resulted in unevenly matched temperatures when supply voltage was obtained from an SCR control circuit supplying multiple glowbars. Ideally each glowbar should have had it's own control and supply circuit. Temperature variation was as much as 100°F (56°C) and since the hottest glowbar in a control group limited the amount of power applied to the group, overall power input was less than optimum.

Heat transfer was also limited by scaling of the heat transfer surfaces with tightly adhering pyrolytic carbon deposits. When all factors were considered and the combined effect evaluated, the use of metal surfaces to affect indirect heat transfer to the carbon reactor environment turned out to be a poor choice and is deemed not practical for further work.

Auxiliary Systems

Cyclones, baghouse, and filters worked reasonably well, as did the compressors. The computer monitoring and control system worked very well in both data logging and process control applications. The on-line instruments worked well except for the turbine flowmeters. Condensation of hydrocarbons and deposition of dust on them led to poor reliability. The safety system worked as designed and the plant was operated for one year in a safe manner.

Conclusions

The design, construction, and operation of a 50 pound/hour continuous PRU for the CTC process, based on very limited batch test data from bench-scale reactors, was a major task which was successfully accomplished.

The PRU was operated for about one year, completing 35 runs covering about 800 hours of operation. The PRU operation provided the proof of concept for the CTC process. Mild gasification char was successfully converted to methane in the methanation reactor, and after gas separation in a membrane, it was decomposed to carbon in the carbon formation reactor. The two reactions occurred at designed temperature and pressure conditions.

The percent conversion was well below the design in both reactors, mostly due to lack of adequate residence time at proper temperature. Heat losses were significantly higher than allowed for in design. The fluidization quality was also poor, as was seen by the cold flow models.

The carbon product was contaminated by chromium, iron, and nickel metals due to erosion and corrosion of metal tubes used as muffle for the glow bars. Scaling of these surfaces was the primary cause for the poor heat transfer coefficient.

A materials of construction problem led to the poor performance of the carbon reactor and its shutdown due to safety concerns.

Other systems, including the membrane, cyclones, baghouse, heat exchangers, and compressors, worked well. The solids feeding and discharging systems had to be modified. Most of the instruments with the exception of the turbine flowmeters worked well.

The plant is highly computerized for data logging, as well as process control. This system worked well and was primarily responsible for the safe operation of the plant involving explosive and toxic gases.

Recommendations

- It is recommended that the PRU test program be continued, after the required modifications, to accomplish the remaining goals viz.
- Process optimization.
- Production of enough product for market evaluation.

Such an operation will also confirm or provide information for the 20 ton/day integrated process development unit (PDU) design discussed in a later chapter. The PDU is a prerequisite to the commercialization of this technology.

Specific recommendations for the PRU modification are to:

- Develop, design, and install an alternative carbon formation system based on existing commercial technology and aimed at producing only fine carbon. Thermal black process and plasma technology are the obvious candidates.
- Modify the methanation reactor to provide longer residence time and better fluidization, along with continuous feed and discharge systems.

7.0 Task 4.6--TECHNICAL AND ECONOMIC EVALUATION OF 1000 TPD COMMERCIAL DEMONSTRATION PLANT

The goal of this task was to prepare a preliminary process design and economic evaluation of a 1,000 ton/day coal mild gasification and product upgrading commercial demonstration plant (CDP). The design was based on the results obtained in Tasks 2, 3, and 4 of the project.

Background

In view of AMAX's interest in commercialization of this technology, Amax R&D assumed the responsibility of performing this task. Early in the project, when Task 1 was completed, the project team (WRI, Amax R&D, and Riley Stoker) concluded that upgrading of mild gasification products, particularly char, to higher value products was essential for commercial success.

To confirm this notion, as well as to determine what areas of the process flowsheet would benefit most by research and development, Amax R&D asked

Stearns-Roger Division of United Enngineers & Constructors of Denver, Colorado, to perform a prefeasibility study. This was done during summer of 1988 without any test data being available from the project (Stearns 1988).

AMAX elected to site the 1,000 ton/day plant at a coal mine near Gillette, Wyoming. The low-su'fur Powder River Basin (PRB) subbituminous coal is inexpensive to mine and, therefore, offers the greatest economic potential from the feed cost point of view. Stearns prepared a process flowsheet based on information presented in the Task 1 topical report and discussions held with WRI and Riley Stoker for the mild gasification section of the plant and Amax R&D for the char upgrading section. They supplemented this information from their own experience of designing such plants and power plants. A thermal black type reactor was selected for production of pure carbon by cracking of methane produced from char.

Stearns estimated the plant capital cost at about \$80 million and the operating cost at about \$8 million. Stearns' report was submitted to DOE as a topical report in October 1988. The capital cost was roughly one third for mild gasification, one third for char upgrading, and one third for the power plant. This estimate, coupled with revenue estimates, indicated that the project will be economically attractive if char could be converted to pure carbon.

Based on this economic potential, DOE authorized funds for actual research and development work for Tasks 2, 3, and 4, discussed in earlier chapters. Amax Coal Industries and AMAX Inc. provided supplemental funds (over a million dollars) for development of the char-to-carbon process.

In early 1991, after most of the test work on the project was completed and Parsons was performing the design of a 20 ton/day process development unit (PDU) under Task 4.7 (discussed in next chapter), Amax R&D awarded a subcontract to Ralph M. Parsons Company of Pasadena, California, to update the design and cost estimate for the CDP based on all available results from the project.

AMAX performed the revenue estimates and economic evaluation. A topical report prepared by Amax R&D presents the details of this technical and economic evaluation (Hogsett and Jha 1991).

A brief summary is presented here.

Product Slate

Figure 11 shows the product slate from the proposed 1,000 ton/day commercial demonstration project, also sometimes called Wyoming Coal Refinery (WYCOR) project. It is somewhat different than the product slate selected in Task 1 and used in the Stearns' study. This simply reflects the evolutionary nature of the process development aimed at improving the project economics.

The gas produced during mild gasification will be simply used as a process fuel. The tar and oil collected by condensation of the volatiles will be upgraded and marketed as three products:

1. **Pitch**
To be used as a binder for the manufacture of carbon anodes used in aluminum production.
2. **Chemical Feedstock**
The lighter condensate will be processed with caustic soda to extract cresylic acid which will be marketed as a chemical feedstock.
3. **Oil**
The remaining oil will be used as a diesel additive to operate the heavy equipment at the mine site.

Char, the largest tonnage product of mild gasification, will be converted to pure carbon and activated carbon. Three markets have been identified:

1. **Carbon Black**
This is the short term, low-volume (1.6 million tons/year), high-value (\$500/ton) market. Carbon produced by this process could be used for compounding rubber for tires or other applications.

WYCOR Project - Potential Products/Markets

Figure 11. Potential Products and Markets

2. Anode Carbon

This is the medium-term, medium-volume (8 million tons/year), medium-value (\$250/ton) market. High purity carbon could be used as a partial substitute for petroleum coke to control sulfur and metal impurities.

Equal distribution of carbon product, between these two markets, was considered for the economic evaluation of the project.

3. Premium Fuel

This is the ultimate market. An ash, sulfur, nitrogen, and hydrogen-free particulate fuel could be used in efficient heat engines to produce electric power in stationary or mobile power plants. There will be no need for a scrubber, feed preparation, or waste disposal. By the time technology matures, the process cost could be lowered enough to produce and sell the carbon product as fuel.

Activated carbon is a high-value product (\$1,000/ton), but the market is small. Thus, it could be used only in the first few plants to boost the economics.

Electricity is a major coproduct of the process. This will improve overall energy efficiency of the coal refinery. Part of the produced power will be used internally, but a major amount will be available for export.

Process Technology

Just as the product slate has gone through some evolutionary changes, the process flowsheet to produce them has also been revised based on the results obtained in Tasks 2, 3, and 4 of the project. Figure 12 shows the conceptual process flowsheet for the CDP, which was used in the cost estimation and economic evaluation of the project.

Crushed coal is screened to remove fines and fed to an inclined fluidized-bed dryer in which it is dried to less than 2 percent moisture at a temperature of about 400°F (205°C). Hot flue gas mixed with recycle flue gas is used to fluidize and heat the coal. The exit gas, after particulate removal, is vented to the atmosphere.

The dry coal then enters an inclined fluidized-bed mild gasification reactor in which it is rapidly heated to about 1,100°F (593°C) by flue gas entering at about 1,260°F (682°C). A majority of the volatile matter is removed from the coal. The hot gas, after removal of fines in high-efficiency hot cyclones, passes through scrubber type condensers which collect tar and oil, as well as produce steam. Oil is processed further to produce the cresylic acid and light oil products.

The hot char is fed to the methanation reactor which operates as a multi-stage fluid bed at about 1,400°F (760°C) and 310 psig. Here, in an excess of hydrogen, most of the carbon present in the char is converted to methane. The exothermic heat of reaction is recovered as steam.

The spent char, which contains all the ash, most of the sulfur, and about one fourth of the carbon present in the feed char, is upgraded to activated carbon. This is accomplished by physically separating the ash-rich fraction and then leaching the product.

After removal of fines in the cyclones and water in a condenser, the gas is fed to a membrane separation unit. Here most of the hydrogen is recovered and recycled to the methanation reactor through a compressor and a heat exchanger.

The methane-rich gas from the membrane goes to the carbon formation reactor through a pressure reduction valve and heat exchanger. This reactor operates at about 1,650°F (900°C) and 100 psig. Under these conditions in the presence of seed carbon, most of the methane is decomposed to produce carbon and hydrogen. After cooling in a heat exchanger, and separation of fine carbon in a baghouse, the gas is fed to a compressor. Excess gas is bled to control the impurities. The remaining gas joins the methanation reactor exit gas before being fed to the membrane.

The carbon reactor is heated by heat pipes at about 2,000°F (1093°C). They in turn are heated by combustion of make gas from mild gasification, bleed gas from the carbon reactor loop, and a fuel gas which is produced in a conventional gasifier fed by coal fines, spent char reject, and additional coal if necessary. The temperature in the fire box will be about 2,900°F (1593°C).

The hot off gas from the system, at about 2,300°F (1260°C), is used to raise steam, as well as to provide heat to the dryer and mild gasification reactor. The steam produced here, as well as in mild gasification condensers and the methanation reactor, is used to produce electricity.

Sulfur emissions control will be provided by a scrubber in the power plant. Gypsum sludge from the scrubber and ash from the gasifier will be the only waste products from the plant. They will be disposed of as landfill in the mine.

Plant Design

Parsons designed the plant essentially following the design developed for the PDU. The power plant was added as a conventional unit. Detailed process flow diagrams are included in the Task 4.6 topical report, as is an equipment list. P&I diagrams were not prepared. The equipment were sized based on the detailed work done for the PDU.

Cost Estimate

Table 12 presents a summary of the capital cost estimate for the plant. This is broken down for the process plant, which will be first of its kind, and power plant, which will be a standard design. The purchased cost for the major pieces of equipment was estimated by Parsons using informal vendor quotes or in-house files. As for the installation cost, there was significant difference in the factors recommended by Parsons and those used by Stearns. Amax closely examined each equipment and selected the factor that was considered more realistic for the project size and project site.

Table 12. Estimated Capital Cost of 1,000 TPD Plant

Cost Item	Process Plant Cost, \$	Power Plant Cost, \$	Total Cost, \$
Purchased Equipment	48,098,800	12,659,300	60,758,100
Installation	48,298,300	11,883,400	60,181,700
Other Direct	7,811,800	1,963,400	9,775,200
Engineering Design	10,420,900	2,120,500	12,541,400
Contingency	22,926,000	2,862,700	25,788,700
Total Plant Capital Cost	137,555,800	31,489,300	169,045,100

Other direct cost categories include sales tax on equipment and materials and construction management fees (5 percent). The engineering design fee was estimated by AMAX at 10 percent of the field cost for the process plant and 8 percent for the power plant. The contingency was provided at 20 and 10 percent, respectively.

The annual operating cost is estimated at \$11 million, which includes \$4 million for labor, \$4.2 million for maintenance, and the balance for feedstock and supplies.

Revenue Estimate

Table 13 presents a summary of the revenue estimates. The annual production rates are based on the mass balance developed by Parsons during the plant design. The prices were estimated by Amax Coal Industries and Amax R&D based on discussions with potential users of these products. The electricity was priced based on what Amax Coal is currently paying at the mine site.

Table 13. Annual Revenues for the 1,000 TPD Plant

Product	Annual Production, TPY	Price, \$/T	Revenue, \$/Year
Fine Carbon	40,100	500	20,050,000
Coarse Carbon	40,100	250	10,025,000
Activated Carbon	10,950	1,000	10,950,000
Pitch	17,200	250	4,300,000
Cresylic Acid	3,700	250	1,850,000
Fuel Oil	5,800	125	725,000
Electricity, MWh	192,700	0.005/kWh	<u>10,598,000</u>
Total Revenue			<u>58,498,000</u>

It is obvious that the revenues from pure carbon are the most important. Since the CTC PRU at Golden could not confirm how much of the product will qualify as fine carbon for the rubber compounding market and how much as coarse carbon for the anode carbon market, a 50 percent split was assumed.

Economic Evaluation

An economic evaluation model was used to calculate the DCFROR, assuming zero net present value and 20-year plant life. The DCFROR was 16.4 percent for the base case. Sensitivity analysis was performed on the capital cost, operating cost, and product revenues. It was found that the DCFROR was not very sensitive to operating cost. The sensitivity to capital cost and product revenue is shown in Figure 13.

Conclusions and Recommendations

The CDP design is based on a process flowsheet developed and improved by WRI and AMAX over the last 3 years by bench-scale research and design, construction, operation, and evaluation of a 100 pound/hour mild gasification PRU at WRI and a companion CTC PRU at AMAX. An adjunct power plant was assumed to be of conventional design.

The mild gasification process flowsheet as tested by WRI was slightly modified to improve the operability of the plant and recovery of the desired liquid products. The CTC process flowsheet was based on the AMAX PRU design with only a major change that the carbon reactor be heated by heat pipes. Since the completion of the CDP design, it was learned that this design of carbon reactor was not satisfactory and an alternative design has to be developed.

Figure 13. DCFROR Sensitivity versus Revenue and Capital

The process flowsheet and mass balance calculations were based on more detailed design work performed on a 20 ton/day PDU encompassing the same unit operations. This also formed the basis for sizing of the reactors and estimation of the purchased equipment cost for the process plant. The estimated purchased equipment cost for the power plant was based on Parsons' experience.

The total capital cost for the plant is estimated at \$169 million (\$138 million for the process plant and \$31 million for the power plant). This total includes a contingency of \$26 million. The annual operating cost is estimated at \$11 million, which includes \$4 million for labor, \$4.2 million for maintenance, and the balance for feedstock and supplies.

The estimated annual revenues are \$30 million for pure carbon, \$11 million for activated carbon, \$7 million for liquid products, and \$11 million for electricity, for a total of \$59 million.

An economic evaluation model was used to calculate the DCFROR, assuming zero net present value and 20-year plant life. Sensitivity analysis was

performed on the capital cost, operating cost, and product revenues. The DCFROR was 16.4 percent for the base case.

In summary, the project is technically sound and offers good economic potential for commercial development. Based on the economic potential for the commercial development of this project, it is recommended that the project development efforts should continue.

8.0 Task 4.7--PRELIMINARY DESIGN AND COST ESTIMATE FOR 20 TPD PDU

This chapter presents a summary of work accomplished under Task 4.7. The details are included in a topical report prepared by the Ralph M. Parsons Company submitted to DOE in September 1991 (Parsons 1991).

Background

In the summer of 1990, DOE/METC modified the contract to add Task 4.7, preliminary engineering design and cost estimate for an integrated 1 ton/hour mild gasification and product upgrading PDU. The design, construction, operation, and evaluation of such a PDU is considered a necessary step before a 1,000 ton/day commercial demonstration plant (CDP), discussed in the previous chapter, can be built.

Amax R&D Center was given the responsibility for this task, and it was decided that the PDU will be built at the pilot plant facilities of Amax R&D Center, Golden, Colorado.

In the fall of 1990, Amax R&D prepared a work statement and approached over a dozen engineering and construction companies to perform the design and cost estimation study on a subcontract basis. Finally, the Ralph M. Parsons Company of Pasadena, California, was selected for the job, and a subcontract was awarded to them in December 1990. At the same time, Tecogen Inc. of Waltham, Massachusetts, was given a small subcontract by AMAX to prepare design and cost estimates for the drying and mild gasification reactors and a fluidized bed combustor to provide heat.

The actual work was performed by Parsons under the direct supervision of Amax R&D during the December 1990 - May 1991 period. Tecogen and WRI provided significant input, particularly in the area of drying and mild gasification. The draft topical report was prepared by Parsons during June - July 1991, and it was submitted in final form in September 1991.

Objective

The objective of the task was to provide DOE with a realistic design and cost estimate of the PDU, which would assist DOE in deciding whether or not to proceed with the actual design and construction of the PDU. Thus, an implied

goal was to develop a low cost, but technically sound, design based on the results of Tasks 2, 3, and 4.

Scope

It was decided that only those operations would be included that need scale-up design information for the commercial demonstration plant. Thus, both the mild gasification and char upgrading operations (studied in the two PRUs) were included, with additional equipment to provide process heat and recover energy as steam. However, the power production, which is a significant part of the commercial flowsheet, was not included.

To keep the cost of the PDU under control and to focus on the main steps of the process, it was decided that the feed to the PDU would be partly dried and sized coal from the Belle Ayr coal drying plant of Amax Coal Company rather than Eagle Butte coal used in the PRU studies. The nominal size of the PDU was set at 20 tons/day (raw coal basis).

The location of the PDU at the pilot plant facilities assured that most of the required infrastructure was already in place. This included roads, pads, buildings, offices, laboratories, and utilities. Only one new building has to be added. Some of the required equipment, including that for batch production of activated carbon, are available at Amax R&D and, therefore, excluded from the cost estimate.

Approach

Parsons reviewed all the project reports prepared by WRI, AMAX, and Riley Stoker Corporation. These included topical reports for Tasks 2 and 3, as well as quarterly progress reports. Based on these data, they developed conceptual process flowsheets and used a computer simulation program to prepare the mass and energy balance.

This technical evaluation performed by Parsons and AMAX revealed that in the area of drying and mild gasification, two modifications should be made to the PRU flowsheet studied at WRI. It was concluded that indirect heating of recirculating make gas (by electric heaters in the PRU and in tubes submersed in an atmospheric fluidized-bed combustor in the PDU and CDP) is expensive and likely to cause two problems.

If the light oil and any mist are not completely eliminated during liquid recovery, they will crack and foul the tubes, adversely affecting its heat transfer characteristics and requiring frequent cleanup. Even if an expensive scrubber, cooler, and demister system was installed, to accomplish this, the presence of methane and higher hydrocarbons at about 15 to 25 percent concentration will cause the same problem in heat exchanger tubes.

This concern is based on Parsons' experience with other hydrocarbon plants, as well as Amax's and WRI's experience in PRU heat exchangers and heaters. To overcome this problem, the PDU flowsheet has been modified to

include heating of the inclined fluidized-bed dryer and mild gasification reactor with flue gas produced by combustion of make gas. In spite of the dilution caused by nitrogen in such a recirculating system, the gas can be burned in a simple inexpensive burner to provide the process heat.

Another area of change is the condenser system. The simple air and water cooled condensers used in the PRU at WRI did not perform well in terms of condensation efficiency, and particularly in terms of separating high-boiling tars from low-boiling oil.

To achieve the objective of collecting these two separate products, the PDU will use a venturi pitch scrubber and an oil absorber scrubber column (packed or tray).

At the time Task 4.7 was being performed, the CTC PRU at Golden was still going through preliminary operation and modifications. Any knowledge gained to date was incorporated in the PDU design. For example, a double lock hopper system was provided for feeding the char to the methanation reactor, which is a multi-stage fluidized bed design.

For the carbon reactor, a heat pipe system was selected to replace the glow bars used in the PRU. The heat pipes were to be heated by burning natural gas in the PDU, while the commercial plant would use coal-derived gas for this purpose.

Plant Design

After the flowsheet was finalized, Parsons finished the process flow diagrams and mass balance, which are presented as three drawings in the topical report.

Next, they prepared 19 P&I diagrams, which were thoroughly reviewed by AMAX. These drawings are detailed enough to show all the equipment and instruments, as well as control logic.

They then prepared an equipment list, which included about 125 items. Equipment design condition summary sheets were prepared for all the major pieces. The instrument summary list contains 662 field devices and 447 computer input/output.

The Parsons' topical report also includes electrical single lines, material diagrams and equipment lay out, and general arrangements drawings.

Cost and Schedule

Parsons estimated the total cost for design and construction of the PDU at \$16.75 million. The cost breakdown is summarized in Table 14.

Table 14. Estimated Cost of Design and Construction for PDU

Item	Cost in Thousands of Dollars		
	Material	Labor	Total
Major Equipment	3,270	245	3,515
Bulk Materials	2,416	1,485	3,901
Other Direct Costs	180	120	300
Indirect Costs	<u>1,154</u>	<u>510</u>	<u>1,644</u>
Subtotal	7,020	2,360	9,380
Allowances			
New Building, Modifications	205	245	450
Site Development	80	100	180
Sales Tax	280		280
Construction Management		350	350
Subtotal	565	695	1,260
Total Constructed Cost	7,585	3,055	10,640
Home Office (Engineering Design)			3,800
Permits, Insurance, Constructor's Fee			<u>125</u>
Total Cost			14,565
Contingency			<u>2,185</u>
Grand Total			16,750

Some of the major costs included above are estimated by Parsons based on percentage factors. Amax R&D, based on its own experience of construction of the PRU and other pilot plants, considers this cost estimate to be high.

As for the schedule, Parsons' topical report indicates that the PDU can be designed and constructed in 16 months.

9.0 Task 4.8--DECOMMISSIONING OF PRU's AND DISPOSAL OF SAMPLES

WRI has disposed of water produced in the PRU dryer by passing the relatively clean water through activated charcoal and putting the treated water into the city sewer system (after discussion with Wyoming Department of Environmental Quality and the City of Laramie).

WRI proposes to dispose of remaining fines and dried coal by combustion and remaining coal liquids by incineration during mid-1992. The mild-gasification PRU will be available for additional tests until 1993, at which time WRI proposes to decontaminate and disassemble the PRU (Merriam and Jha 1991).

The estimated cost for disposal of materials produced by WRI testing is \$75,854 (1991 \$). The estimated cost to decontaminate and disassemble the mild-gasification PRU is \$169,173.

Amax R&D Center operated the CTC PRU from August 1990 to July 1991. Feed char, spent char, carbon black, and Desulco seed are the main solid products from PRU campaigns. During that operation, liquid by-products were also collected. All of these feedstocks and products need to be disposed. Amax R&D Center intends to modify and operate the PRU during the next two years, converting the char to carbon and activated carbon. This will reduce the amount to be disposed in half. The remaining spent char will be returned to the Eagle Butte Mine and combined with product coal. By-product liquids produced during the PRU operation will be burned for heating value. Upon completion of the testing, the PRU will be cleaned and dismantled. Equipment (all purchased by AMAX) will be removed and stored on site. The building in which the PRU was built will be repaired and restored to its previous condition.

AMAX R&D has estimated the cost of disposal of the material as \$31,351 and the cost to disassemble the CTC PRU as \$161,753.

10.0 CONCLUSIONS

Conclusions from the Mild-Gasification Tests:

- Minus 8-mesh Wyodak coal was dried to zero moisture content and partially decarboxylated in the IFB dryer at a maximum bed temperature of 575°F (302°C) using three minutes solid residence time and recycle gas flow of about 5.6 lb of gas per lb of raw coal feed.
- We were able to conduct successful 24-hr and 5-day tests using the mild-gasification PRU at raw coal feed rates of 100 to 150 lb/hr using mild-gasification temperatures of 950 to 1150°F (510 to 621°C) and char residence times varying from 5.5 to 9 minutes.
- Results of tests using the PRU agree well with test results from the bench-scale unit. One slight difference is that carbon balances show that the PRU produces slightly more liquid and slightly less gas than is produced by the 10-lb/hr system.
- We are not able to detect any effects of particle size upon product distribution when comparing results of minus 8-mesh Wyodak coal in the PRU with smaller sizes tested using the 10-lb/hr system.

- The distribution of products as wt % of the raw coal varies from 950 to 1150°F (510 to 621°C) as char, 43 to 40; gas, 4 to 9; and liquids, 10 to 13.
- The yield of coal liquids is typically 12 to 15 wt % of the MAF feed to the mild-gasification reactor. Our data show that the yield increases with increasing maximum bed temperature from 950 to 1100°F (510 to 621°C). The liquid produced is heavy (about 60 wt % boiling above 700°F/371°C) and has H:C ratios of about 1.15.
- The char contains 16 to 21 wt % volatiles and is highly reactive. The oxygen content of the char varies proportionately with the volatiles content. Thus, the oxygen content of the char can be reduced to less than 8 wt % by devolatilizing the char to about 15 wt % volatiles content.
- The quantity of gas produced increases with temperature over the range of temperatures tested, and the hydrogen, carbon monoxide, methane, and ethylene contents of the gas increase at higher temperatures. The gross heating value of the gas varies from 550 to 600 Btu/scf.

Char Upgrading Process Research

- Char produced by mild gasification of subbituminous Wyoming coal in an inclined fluidized-bed reactor has an open pore structure, low ash, volatile and sulfur contents, and high fuel value. It is very reactive and maintains its reactivity when stored in inert atmosphere. While this char can be an excellent utility fuel, its upgrading to higher value product(s) is critical for the commercial feasibility of mild gasification based coal refining technology.
- AMAX has developed a two step char-to-carbon process for upgrading mild gasification char to pure carbon and activated carbon. In the first step, most of the carbon in the char is converted to methane gas in the presence of an excess of hydrogen. All of the ash and most of the sulfur remain behind in the spent char. In the second step, the methane-rich gas is heated to a higher temperature to produce pure carbon and hydrogen for recycle.
- Bench-scale tests indicated that methanation of char can be accomplished using an excess of hydrogen in a fluidized-bed reactor in the temperature range of 1,300 to 1,500°F (705 to 815°C) and pressure range of 200 to 400 psia. About 70 percent carbon conversion was obtained in less than 2 hours residence time. The use of catalyst or steam did not improve the conversion.
- The remaining spent char has a high specific surface area. It is easily upgraded to activated carbon by recovering a relatively ash-free fraction using gravity separation. The phenol adsorption capacity of the carbon so produced was comparable to a commercial grade carbon.

- An indirectly heated continuous reactor system was conceived and developed for cracking of methane and other hydrocarbons to produce pure carbon and hydrogen. The theoretical carbon yield by this process is higher than obtained in state-of-the-art technology, and the hydrogen product is not contaminated. The AMAX process works in the temperature range of 1,650 to 1,850°F (900 to 1010°C) at 50 to 100 psia (in comparison to conventional processes operating at atmospheric pressure but temperatures in the range of 2,500 to 3,500°F/1370 to 1925°C) in the presence of seed carbon. This gives the flexibility of producing fine or coarse carbon for different markets.
- Since the methanation and carbon formation reaction conditions are close to each other, the process provides good mechanical and thermal energy efficiency, but at the expense of a thermodynamic driving force. The problem is overcome by introducing a gas separation membrane between the two reactors.
- A 50 pound/hour integrated PRU was designed, built, and operated for almost one year. Char from the mild gasification PRU at Laramie was used as the feedstock. The PRU operation provided the proof of concept for the process. The conversions obtained in the PRU were lower than designed due to lower residence time, lower heat transfer coefficients caused by poor fluidization and scaling of heat transfer surfaces, and significantly higher heat losses than the design provided. A materials of construction problem in the carbon reactor led to product contamination and shutdown of the PRU.

Technical and Economic Evaluation

- As the next step towards commercial development, a 20 ton/day coal mild gasification and product upgrading PDU was designed by the Ralph M. Parsons Company of Pasadena, California, with input from WRI and AMAX. Some changes were made in the process flowsheet to improve the operability of the process. These included heating of the coal dryer and mild gasification reactor with flue gas rather than indirectly heated recycle gas, replacement of air and water cooled condensers with venturi and column scrubbers for separate recovery of tar and oil, and replacement of electric glow bars with heat pipes in the carbon formation reactor.
- The PDU flowsheet was also used to design a 1,000 ton/day CDP to be located at an AMAX coal mine near Gillette, Wyoming. A conventional power plant was added to recover energy from various process plant units and to produce electricity for plant consumption as well as export.
- The design and construction cost for the CDP was estimated at \$169 million, which includes a contingency of \$26 million. The annual operating cost was estimated at \$11 million, while the product revenues were estimated at \$59 million. An economic evaluation model indicated that the project will have a DCFROR of 16.4 percent.

Summary Statement

In summary, WRI and AMAX have developed a coal mild gasification and char upgrading process that offers commercialization potential. The innovative technology has been tested in continuous PRUs. Further development work is needed to modify and improve some of the operations, first on PRU scale and then on PDU scale, before a commercial demonstration plant is designed and built.

11.0 RECOMMENDATIONS

In view of the commercialization potential of the technology, it is recommended that the process development efforts should continue.

- A two-phase program is recommended. In the first phase, the two PRUs should be modified to correct their identified deficiencies and incorporate new designs to improve their operability. The PRUs should then be operated to produce products for market evaluation and scale-up design data to update the PDU design and technical and economic evaluation of the 1,000 ton/day plant.
- In the second phase, a 1 ton/hour integrated mild gasification and product upgrading PDU should be designed, built, and operated in preparation for the commercial demonstration plant.

12.0 REFERENCES

- Cha, C.Y., N.W. Merriam, M.C. Jha, and R.W. Breault, 1988, Development of an Advanced, Continuous Mild-Gasification Process for the Production of Coproducts, Topical Report for Task 1, Literature Survey and Market Assessment. DOE Report, DOE/MC/24268-2700.
- Hogsett, R.F., and M.C. Jha. 1991. Development of an Advanced, Continuous Mild-Gasification Process for the Production of Coproducts, Topical Report for Task 4.6, Technical and Economic Evaluation. AMAX R&D Center, Golden, CO, Morgantown Energy Technology Center, DOE, in press.
- Jha, M.C., and R.L. McCormick. 1989. Development of an Advanced, Continuous Mild-Gasification Process for the Production of Coproducts, Topical Report for Task 3, Bench-Scale Char Upgrading and Utilization Study, AMAX R&D Center, Golden, CO, Morgantown Energy Technology Center, DOE, in press.
- Jha, M.C., R.L. McCormick, R.F. Hogsett, R.M. Rowe, and K.R. Anast. 1991. Development of an Advanced, Continuous Mild-Gasification Process for the Production of Coproducts, Topical Report for Task 4, System Integration Studies--Char Upgrading. AMAX R&D Center, Golden, CO, Morgantown Energy Technology Center, DOE, in press.
- Merriam, N.W., and C.Y. Cha. 1989. Development of an Advanced, Continuous Mild-Gasification Process for the Production of Coproducts, Task 2 Topical Report, Mild-Gasification Tests. Laramie, WY, Western Research Institute, WRI-91-R018.
- Merriam, N.W., C.Y. Cha, T.W. Kang, and M.B. Vaillancourt. 1990. Development of an Advanced, Continuous Mild-Gasification Process for the Production of Coproducts, Topical Report for Task 4, Mild Gasification Tests--System Integration Studies. Laramie, WY, Western Research Institute Report to DOE, WRI-91-R023.
- Merriam, N.W., and M.C. Jha. 1991. Development of an Advanced, Continuous Mild-Gasification Process for the Production of Coproducts, Topical Report for Task 4.8, Decontamination and Disassembly of the Mild-Gasification and Char-to-Carbon PRUs and Disposal of Products from Testing. Laramie, WY, Western Research Institute Report to DOE, WRI-91-R071.
- The Ralph M. Parsons Company, 1991. Preliminary Engineering Design and Cost Estimate for a 20-Tons/Day Coal Mild-Gasification and Product Upgrading Process Development Unit (PDU). AMAX R&D Center, Golden, CO, Morgantown Energy Technology Center, DOE.
- Stearns-Roger, Division of United Engineers and Constructors, 1988. Engineering Evaluation and Cost Estimate of an Advanced Continuous Mild-Gasification Process. AMAX R&D Center, Golden, CO, Morgantown Energy Technology Center, DOE.

END

**DATE
FILMED**

6 / 24 / 92