**DOE/PC/88885-T4
(DE92015920)**

**PROOF OF CONCEPT AND PERFORMANCE OPTIMIZATION OF HIGH GRAVITY
BATCH-TYPE CENTRIFUGAL DRYER FOR DEWATERING FINE COAL**

Final Report for the Period September 20, 1989–September 21, 1991

**By
Lloyd B. Smith
Ted Durney**

Work Performed Under Contract No. AC22-89PC88885

**For
U.S. Department of Energy
Pittsburgh Energy Technology Center
Pittsburgh, Pennsylvania**

**By
Coal Technology Corporation
Bristol, Virginia**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, ~~888-696-8401~~.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

Printed in the United States of America, Office of Scientific and Technical Information, Oak Ridge, Tennessee

PROOF OF CONCEPT AND PERFORMANCE OPTIMIZATION OF
HIGH GRAVITY BATCH-TYPE CENTRIFUGAL DRYER
FOR DEWATERING FINE COAL

FINAL REPORT
Period of Contract DE-AC22-89PC88885 Performance
September 20, 1989 to September 21, 1991

By

Lloyd B. Smith
Ted Durney

For

U. S. Department of Energy
Office of Fossil Energy
Pittsburgh Energy Technology Center
P. O. Box 10940
Pittsburgh, PA 15236

by

Coal Technology Corporation
103 Thomas Road
Bristol, Virginia 24201

ABSTRACT

The primary objective of the project was to assemble, analyze and make use of those data that could help to clearly identify, optimize and confirm the technical and economic advantages that the new high gravity centrifugal dryer technology can provide to the coal industry and to end users. Other objectives were: to confirm the feasibility of the dryer for drying coals from a number of different seams; to use the data base for optimizing the dryer's systems, and; to produce projected technical and economic comparisons with thermal dryers as applied to an existing coal processing plant flow sheet.

The new centrifuge employs a rather simple principle. However, the successful implementation of this principle involves coordinating a substantial number of independent variables with one another to a level commensurate with commercialization. To accomplish this, a new data base was developed during the initial part of the project which included data obtained from earlier research activities. The work plan called for the use of statistical software to analyze test data from matrices in order to point to optimum values for the principal independent variables. Rapidly changing coal feeds from the host plant precluded this. After obtaining the approval of the COR, evolutionary operational testing (EVOP) was used instead.

The project was successful in developing combinations of the independent variables which can produce commercially feasible productivity, moistures, and total costs for a variety of widely used coals. The project also produced comparative models of coal plant installations which indicate that the new centrifugal coal dryers can successfully compete with fluidized bed thermal dryers in coal processing plants.

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
Disclaimer.....	ii
Abstract.....	iii
Table of Contents.....	iv
Executive Summary.....	1
Overview of Project.....	3
Modification of Controls & Data Logger.....	7
Proof of Concept Tests.....	14
Filter Performance Tests.....	14
Coal Versatility Tests.....	21
Performance Optimization Tests.....	36
Filter Flow Rate vs Moisture.....	36
Bowl Speed vs Moisture.....	49
Nozzle Configuration vs Moisture.....	52
Feed Rate & Mode vs Moisture.....	55
Feed Rate vs Ash.....	59
Cutter Blade Configuration.....	59
Recovery System.....	62
Projection of Productivity & Operating Costs.....	65
Economic Model of Centrifuge Installation.....	69
Conclusions.....	77
Recommendations.....	78
Acknowledgements.....	79
References.....	80

LIST OF TABLES

<u>TABLE NUMBER</u>		<u>PAGE</u>
1	Production Centrifuge Cycle	6
2	Results with Original Filter	38
3	Depth/Pressure/Density Relationship	51

LIST OF FIGURES

<u>FIGURE</u>		<u>PAGE</u>
1	Prototype 2 Centrifugal Dryer	4
2	Schematic of Centrifuge Systems	5
3	Quadra-Beam 2 Moisture Analyzer	9
4	Cutter System	9
5	Microwave Moisture Accuracy Test	11
6	Dry Coal Weight Unit	12
7	Overflow & Filtrate Weight Systems	12
8	Data Logger Monitor Screen	13
9	Non-Blinding Filter System	15
10	Feed Density vs Load Weight	17
11	Depth/Pressure/Density Curves	18
12	Mixing & Reconstituting System	22
13	Analysis of Feed, Penn. Source Coal	24
14	Analysis of Prod., Penn. Source Coal	25
15	Analysis of Feed, Ala. Source Coal	27
16	Analysis of Prod., Ala. Source Coal	28
17	Analysis of Feed, WV Source Coal	29
18	Analysis of Prod., WV Source Coal	30
19	Analysis of Feed, S. IL Source Coal	32
20	Analysis of Prod., S. IL Source Coal	33
21	Finished Filter Segment	39
22	Interior of Centrifuge Bowl	39
23	Media Resistivity Test Rigs	41
24	High Pressure Resistivity Test Rig	44

LIST OF FIGURES (CONTINUED)

<u>FIGURE</u>		<u>PAGE</u>
25	Filter Flow Rate Test Coal Analysis	46
26	Plating Thickness vs Moisture	47
27	Vibration Containment System	50
28	Coal Load Before Wiping	53
29	Coal Load After Wiping	53
30	Filling and Wiping System Front	54
31	Filling and Wiping System & Scoop	54
32	LVDT Bowl Level Indicator	56
33	Flattened Nozzle Configuration	57
34	Stir-Fill Programming	58
35	Polished SS Cutter Screw	61
36	Schematic of Dryer System Models	63
37	Recovery System Loops	64

EXECUTIVE SUMMARY

This report describes the work performed by Coal Technology Corporation from September 20, 1989 through September 21, 1991 under DOE Contract DE-AC22-89PC88885, "Proof of Concept and Performance Optimization of High-Gravity Batch Type Centrifuge for Dewatering Fine Coal." The primary objective of this project was to determine the operational and economic feasibility of a new centrifuge system for drying clean fine coal froth product of 28 mesh top size with 35% minus 325 mesh. A second objective was to determine how the more vital systems could be integrated so that the centrifuge could achieve the performance level required for service in commercial coal processing plants. The following is a summary of the work, the resulting accomplishments and the conclusions reached from the project:

OPERATIONAL FEASIBILITY

At the project start-up, the Prototype 2 centrifugal dryer as well as its coal supply and disposal systems, were operational at the host plant site in Big Rock, Virginia. The centrifuge was built by the Roberts & Schaefer Company according to designs supplied by UCC Research Corporation, the predecessor of Coal Technology Corporation. Roberts & Schaefer, was originally scheduled to participate in the project but because of the demands of other work, they were unable to do so. Some development work had been done on this completely redesigned pilot centrifuge prior to this project, but it was not ready for commercialization. During the project some of its vital systems were taken from marginal feasibility to market readiness. Among these were the filling system, the pre-drying wiper system, the non-blinding filter and the cutter system.

ECONOMIC FEASIBILITY

For the new centrifugal dryer technology to be economically feasible, both the centrifuge and the auxiliaries necessary to its integration into the process plant must create an attractive cost structure when operating in concert and when compared with a fluidized bed thermal dryer. For the centrifuge to operate efficiently, the coal must be introduced to the centrifuges in the form of a thick slurry. Extensive studies were made of slurrying methods for use in the commercialization of the centrifuges. A review of these studies led to a decision to use disk filters and then to reconstitute the filter cake into a slurry with the desired solids concentration. The thermal dryer also has to have the fines in its feed pre-dried in a disk filter. When the costs attendant to using the new centrifuges are compared with those of fluidized bed thermal dryers, it is important that coal streams of equal total mass flow, size consist and coal characteristics be used for determining the comparative costs of the two types of dryer systems. Senior officials of major coal producers were consulted and they confirmed that this is the appropriate method for cost comparisons of competitive fine coal dryer systems. It was on this basis that comparisons of the cost effectiveness of centrifugal dryer systems and fluidized bed thermal dryer systems were developed.

OPTIMIZATION OF TECHNICAL SYSTEMS

After the centrifuge systems were developed and proven feasible, the key systems in the centrifuge were integrated with one another and optimized to the point where the centrifuge was able to demonstrate market ready performance. During the development work, some new discoveries were made which led to substantive improvements in centrifugal fine coal drying. These improvements included an improved filling system, a device for quick removal of the decanted water from newly forming loads, a new cutter material and blade form as well as new concepts for maintaining the leveling of the bowl under changing load weights. To optimize the centrifuge systems, it was necessary to cope with more than twenty significant independent variables as well as with changes in the coal consist from the host plant on an hour by hour basis. The original plan called for matrix testing, but continual variations in the coal feed from the host plant made it necessary to rely on evolutionary operational testing (EVOP) with only minimal use of formal matrices. Nevertheless, the project yielded values for the principal independent variables which allow the centrifuge to achieve results which were within the project goals and which are appropriate for the beginning of commercialization.

SUMMARY OF CONCLUSIONS

1. The new centrifugal dryer system is a technically feasible system for reliably and economically drying froth flotation product of 28 mesh top size with 35% minus 325 mesh to 10% surface moisture.
2. The operating costs for energy of complete centrifugal dryer systems will be on the order of 33% of those for fluidized bed thermal dryer systems for the same coal stream. The overall cost per ton of coal dried will be on the order of 80% of that for fluidized bed thermal dryer systems for the same coal streams.
3. The development and continuation of optimization of the independent variables in the new centrifugal dryer technology will continue after commercialization begins. However, the values for the major independent variables as identified and tested during the project, demonstrated the capability of the centrifuge to meet the project goals and that the centrifuge is ready for commercialization.

OVERVIEW OF THE PROJECT

Centrifugal drying of certain size fractions of coal is commonplace. However, for centrifugal dryers to compete with fluidized bed thermal dryers, they must reduce the surface moisture in froth flotation product to the order of 10%. None of the previously available centrifugal dryers can accomplish this. The high-gravity, batch-type centrifugal dryer concept, which is the subject of this project, can reduce the surface moisture in froth product to 6% to 10.5%, depending on size consist.

The high-gravity, batch-type centrifugal dryer technology is a total departure from conventional centrifugal dryer technology. Conventional screen bowl and solid bowl decanter centrifuges employ either decanting or decanting with low gravity filtration. The new centrifuge combines decanting and very high gravity filtration in a single process. Conventional coal centrifuges operate at gravity levels of from 800 to 1,200, while the new centrifuges operate at above 4,000 x gravity.

In order to bring the new high gravity, batch centrifuge concept to a condition of feasibility for the commercial drying of clean coal fines, it was necessary to further explore several of its systems and to solve some problems remaining in them. At very high gravity levels, the coal bed becomes quite dense and the minute passages in it through which the filtrate must pass, become restricted. This results in a slow filtration rate. Because of this, if all of the water were to be removed by filtration only, the productivity of the system would be no more than 2 TPH, or 25% of the productivity needed for drying clean coal fines commercially. At the beginning of each cycle of the new process, most of the water is quickly decanted. This results in acceptable productivity since only about 25% of the water must be removed by filtration. While a decanting system was in use prior to the project, it was not ready for the marketplace.

The loads of coal fines formed in a batch centrifuge are inherently unbalanced. This makes it necessary to have a system in place for processing unbalanced loads at very high speeds. Such a system was in place but it needed improvement to stabilize it during the wiping operation.

Filtering systems in various kinds of filtration devices (including centrifuges) have been prone to blinding while drying very fine particulate. The non-blinding filter system of the new centrifuge was functional, but it needed serious development work to make it reliable and capable of reproduction for a commercial centrifuge. The batch system, as employed in conventional centrifugal dryers, operates on cycles of about 10 minutes duration. This yields a total of about 6 cycles per hour. The subject high-gravity centrifuge operates on a cycle rate of 22 per hour. It is fully automated and can be controlled by either a programmable controller or a computer. The software which controls the systems was improved and brought to a condition of market-readiness during the project. The 8 TPH Prototype 2 which was used during the project, is shown in Figure 1. It uses a 36 in. ID bowl which is 36 in. in inside length. However, it was determined during the project that in order to achieve 12 TPH, the production design centrifuges will need to be equipped with a 44.5 in. ID x 46.5 in. inside length bowl. The principal elements of the dryer system are shown in the schematic in Figure 2. The expected cycle of the production dryer is shown in Table 1.

FIGURE 1
THERMAL ENGINE COMPONENT

SCHEMATIC OF HIGH GRAVITY CENTRIFUGAL DRYER

FIGURE 2

TABLE 1
PRODUCTION CENTRIFUGE CYCLE

<u>Function</u>	<u>RPM *</u>	<u>Time</u>
CHANGE-OUT: after cutting out the previous load of coal, the cutter is withdrawn, the filling tube is inserted and the bowl is accelerated to the filling speed	1,890	16 sec.
FILL: 310 gallons of coal slurry at 53% solids is quickly injected into the bowl. As the solids settle to the periphery of the bowl, clay laden water collects on the inner surface. A major portion of the water and clay is decanted to overflow out the mouth of the bowl. Most of the remainder is removed by the wiper during wipe	1,890	30 **
WIPE: water & clay which collects on the inner surface of the coal, during load formation, is squeegeed off and removed as overflow	1,485	6
ACCELERATE: bowl is accelerated to drying speed	2,500	10
DWELL: coal is spin-dried to 10% surface moisture. Water is filtered through the coal and exits the bowl through filter media in two filter gutters and in turn through orifices in the bowl	2,500	50
DECELERATION: bowl is slowed to cutting speed	180	22
CUTTING: dried coal is cut out by a ceramic blade running the full length of the coal load and a high speed screw conveyor conducts it out of the bowl from where it free-falls onto the clean coal conveyor belt. Approximately 1 in. of coal is left in the bowl as a filter bed	180	<u>30</u> 164 sec.

* Speed at end of function, RPM

** Filling is done in a two stage process with a first full pressure segment of about 9 seconds and then a second lowered flow segment of about 6 seconds. The times and flows are controlled automatically by the computer

To make the overall system feasible, it will be necessary to feed the future production centrifuges with coal slurry at solids concentrations between 50% and 56%. In addition, because of the necessity of decanting, it is necessary to recover the decanted slurry and to recycle it as is done with other coal centrifuges. Both of these areas were studied and satisfactory solutions were developed. They will be discussed later in this report.

MODIFICATION OF CONTROLS & DATA LOGGER - Task 2

Successful operation of the high-gravity centrifuge involves coordinating more than twenty independent variables with one another so that the final moistures, productivity levels and energy consumption are acceptable. The principal independent variables are:

- Slurry % solids
- Fill
 - Drying speed
 - Constant vs. changing speed
 - Fill rate, first segment
 - Fill rate, second segment
 - Fill time, first segment
 - Fill time, second segment
 - Nozzle pressure
 - Nozzle size
 - Nozzle shape
- Delay (settling time after fill)
- Wipe
 - Time span
 - Attack rate
 - Pressure
 - Wiper design
 - Scoop design
- Acceleration time span
- Dwell at high speed
 - Speed (gravity level)
 - Time span
- Deceleration time span
- Cut
 - Time span
 - Beginning speed of bowl
 - Constant speed vs. deceleration
 - Rate of attack
- Depth of bed cake after cutting
- Resistivity of filter media
- Total cross sectional area of restrictive orifices

To facilitate bringing each of the large number of variables to a functional level, it was necessary to up-grade the data acquisition and control systems so that most of the variables could be monitored in real time. The programmable controller and data logging systems were modified so that the following functions could be controlled, monitored and/or recorded:

- Cycle time/speed
- Moisture reading
- Dry coal weight
- Decanted slurry weight
- Filtrate weight
- Motor average power usage
- Slurry feed SG
- Timing of the fill valve operation
- Vibration information
- Bearing temperatures
- Inside diameter index of most recent batch

A Moisture Systems Quadra-Beam II Moisture Analyzer was installed so that trends in final moisture could be identified quickly. It is illustrated in Figure 3. It allowed surface moistures from 5 samples to be determined and averaged in less than 3 minutes. The same analysis required 30 minutes with the microwave oven (now widely used). Several hours were required for the full ASTM moisture test determination. The centrifuge cycle time is about 3 minutes. The very long turn-around time for ASTM moisture determinations would have been a major impediment to testing of the centrifuge without the new instrument.

To establish the accuracy of the microwave moisture determinations (which was used to calibrate the moisture meter and for precise moisture readings) made in the centrifuge lab, a test was run to compare the microwave oven moisture determinations with those made by a commercial lab using the ASTM methodology. The following procedure confirmed that the differences are not significant:

1. A sample of dried coal was collected at the centrifuge.
2. This sample was split into 3 parts. Two parts were given ASTM moisture tests. The third part was tested for moisture using the same microwave and procedures used at CTC, but the work was performed at a respected commercial testing laboratory by their personnel.
3. This test confirmed that there is less than 0.1% difference between the results of the microwave method and the ASTM Method D2961.
4. Based on these results, the microwave oven was then considered sufficiently reliable to be used for moisture determination and for calibrating the Quadra Beam 2 at regular intervals.

QUADRA-BEAM 2 MOISTURE ANALYZER
FIGURE 3

CUTTER SYSTEM
FIGURE 4

The microwave moisture test results were used when recording data because the Quadrabeam 2 had to be calibrated for the particular coal blend being tested at any given time. The Quadrabeam 2 had a repeatability of about + or - 1% (=1%) except for coals with high clay content. In the latter case, the repeatability error was greater. However in every case, the accuracy of the instrument was sufficient to indicate the moisture trends. It made a substantial contribution to the effort by providing readouts of moisture trends in near real time. The results of the Microwave/ASTM D2961 Comparison tests are shown in Figure 5.

The product moisture samples were obtained by grab sampling at the cutter, shown in Figure 4. Grab sampling was done because of problems attendant to developing an automatic sampler for the centrifuge. An indicator on the cutter identified the depth at which each of the 5 proportional samples should be taken.

The cutter system transferred the dried test coal to a screw conveyor which conducted the dry coal to a point above the main clean coal belt of the host plant. The dry coal weight system, shown in Figure 6, is located below the outlet of the screw conveyor and above the main clean coal belt. It was improved and enlarged to enable it to handle the expected 650 pound loads of dried coal. However, during testing, loads as high as 800 pounds were produced.

The Decanted Slurry and Filtrate Weight Systems were modified so that the weights measured by each, could be recorded automatically after each cycle. Figure 7, illustrates the Decanted Slurry and Filtrate Weight Systems. The Decanted Slurry Weight System is in the foreground.

Vibration is monitored and recorded at two points on the centrifuge. To measure the reaction on the centrifuge frame, a vibration transducer is mounted on the gimbal. A second vibration transducer measures the vibration of the bearing housing to allow a determination of the imbalance present in each batch of dried coal. The processors for the vibration transducers were originally set up to read out the amplitudes of vibration. This was found to be unsatisfactory because it did not reflect the energy in the vibration pattern. In view of these findings the vibration indicators were modified so that they read out velocity instead of amplitude of vibration. This gave an excellent vibrational energy index and hence an indication of the potential for problems. The main bearing monitor records up to 6 in./sec. of vibration while the gimbal monitor records up to 2 in./sec. At 2,800 RPM, this would give the indicators the capability of recording up to 82 and 27 mils of amplitude respectively. The ability of the test team to read these values on real time graphs on the data recorder monitor, was invaluable to the development process in that potential vibration problem areas could be monitored in real time. The screen on the data logging computer is illustrated in Figure 8. The lower of the 3 graphs shows both of the vibration patterns as recorded during a drying cycle. Gimbal vibration usually was at 0.15 inch/second. Vibration amplitudes of under 2 mils are considered smooth for large machinery.

COMMERCIAL TESTING & ENGINEERING CO.

EAST KENTUCKY DIVISION MANAGER
STEVE CAMPBELL

PLEASE ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 2721, PIKEVILLE, KY 41501-2721
OFFICE TEL. (606) 432-2511

March 21, 1990

Coal Technology Corporation
ATTN: Mr. Lloyd Smith
103 Thomas Road
Bristol, VA 24201

Dear Lloyd,

Commercial Testing and Engineering Company, per your request, performed a test program for moisture determination using a microwave oven. It should be noted that there is no prescribed test method for total moisture using microwave ovens. However, many studies are underway to determine its accuracy as well as repeatability. Similar techniques are being considered by A.S.T.M.

This test program followed the prescribed test methods as provided by Coal Technology Corporation, Mr. Lloyd Smith. The test equipment included one Anana 500 watt microwave oven, five pyrex glass weighing dishes approximately 3-1/2" diameter by 1/2" deep, and five styrofoam cups. A series of tests were performed on a single coal sample of approximately -28 mesh in size and weighing 2,392.0 grams. This sample was riffled into four equal parts, each weighing approximately 600 grams. The samples were tested and the results are given in the enclosed report.

If we can be of further assistance please feel free to call.

Respectfully submitted,
[Signature]
Rodney D. Campbell, Manager
Pikeville Laboratory

RDC/jm

Charter Member

OVER 40 BRANCH LABORATORIES STRATEGICALLY LOCATED IN PRINCIPAL COAL MINING AREAS, TIDEWATER AND GREAT LAKES PORTS, AND RIVER LOADING FACILITIES

COAL TECHNOLOGY PROCEDURE FOR MICROWAVE OVEN MOISTURE DETERMINATION

This test performed by CT&E - Pikeville, Ky. Laboratory

March 14, 1990

Report No. 48-64462

Subsample No. 1 was weighed and placed in an air drying cabinet as prescribed in A.S.T.M. D3302 for Determining Total Moisture.

Subsample No. 2 and 4 were used to determine Total Moisture by A.S.T.M. D2961 (Limited Purpose Method).

Subsample No. 3 was used for microwave oven test.

The test procedure was conducted as follows: Two 6 oz. styrofoam cups of water were placed in the farthest two corners of the oven. A sample was then weighed (to .0000), each approximately 10 grams in size, into the pyrex weighing dishes. The microwave oven was set for 20 minutes and the sample placed inside. After the time elapsed the sample was then cooled in a desiccator and reweighed. Then the sample was returned to the oven for increments of 5 minutes until a moisture loss of less than 0.10% was obtained.

This test program followed the prescribed test methods as provided by Coal Technology Corporation, Mr. Lloyd Smith. The test equipment included one Anana 500 watt microwave oven, five pyrex glass weighing dishes approximately 3-1/2" diameter by 1/2" deep, and five styrofoam cups. A series of tests were performed on a single coal sample of approximately -28 mesh in size and weighing 2,392.0 grams. This sample was riffled into four equal parts, each weighing approximately 600 grams. The analytical results of this test are given below.

Subsample No. 1 - Total Moisture by D3302 = 12.03%

Subsample No. 2 and 4 - Total Moisture by D2961

Subsample No. 1 = 11.94%
Subsample No. 2 = 11.98%

Microwave Oven Moisture Determination Data

	Total Moisture (after 20 min. in oven)	Total Moisture (after 25 min. in oven)	Total Moisture (after 30 min. in oven)
Subsample No. 3-1	11.80%	11.92%	11.92%
Subsample No. 3-2	11.89%	11.89%	*
Subsample No. 3-3	11.85%	11.87%	*
Subsample No. 3-4	11.71%	11.92%	11.93%
Subsample No. 3-5	11.82%	11.89%	*
Subsample No. 3-6	11.75%	11.88%	11.89%
Subsample No. 3-7	11.83%	11.89%	*
Subsample No. 3-8	11.90%	11.94%	*
Subsample No. 3-9	11.82%	11.90%	*
Subsample No. 3-10	11.85%	11.85%	*

*test not necessary

COMMERCIAL TESTING & ENGINEERING CO.

Original Copy Watermarked
For Your Protection
P.466

ATTN: D. Campbell vs. 11.94% vs. 11.98%

MICROWAVE MOISTURE ACCURACY TEST

FIGURE 5

DRY COAL WALKWAY OVER
FIGURE 6

OVERFLOW AND COLLECTION OF COAL
FIGURE 7

TABLE 1. SUMMARY OF RESULTS
FOR THE 1970-71 SEASON

In order to facilitate the testing of coal fines samples from sources other than the host plant, a system was designed and constructed so that test coal could be transported as filter cake to the centrifuge lab and reconstituted into slurry of the appropriate % solids. This system will be described under COAL VERSATILITY TESTS.

PROOF OF CONCEPT TESTS - Task 3

A primary objective of the project was to establish the technical feasibility of the high-gravity, batch centrifuge. The ability of the filter to operate over long periods of time without blinding was the focus of this determination. The non-blinding filter concept depends on the system shown in Figure 9. This figure illustrates how slurry is introduced into the centrifuge bowl during the filling portion of a cycle and how the jets of slurry from the individual nozzles cause agitation in the portion of the forming load of coal fines which is still in a slurry form. The figure also shows how the combined restrictivity of the already solidified portion of the coal bed, the filter media and the orifices in the bowl, operate in concert to slow the outflow of filtrate. This enables the agitation to cause the clays to remain in suspension in the portion of the load which is still in slurry form as the load is solidifying. Thus the clays are not forced down to the filter media where blinding would otherwise occur.

Filter Technology Performance Tests - Subtask 3.1

During more than 1,000, tests the filter was able to operate without blinding. However, during the Proof of Concept testing of the filter, it became apparent that there were many interactive variables which must be investigated if the filter was to be truly ready for commercialization. The following, from among the independent variables listed under TEST ENHANCEMENT VARIABLES, were investigated because of their critical relationship to the successful functioning of the non-blinding filtration process:

- Slurry % solids
- Fill
 - Speed
 - Constant vs. changing speed
 - Fill rate, first segment
 - Fill rate, second segment
 - Fill time, first segment
 - Fill time, second segment
 - Nozzle pressure
 - Nozzle size
 - Nozzle shape
- Delay (time allowed for solidification after fill)
- Wipe
 - Time span
 - Attack rate
 - Pressure
 - Scoop Design

SCHEMATIC OF NON-BLINDING FILTER SYSTEM

FIGURE 9

Some of these variables will be discussed in more detail under PERFORMANCE OPTIMIZATION Task 4. Some of the more important findings made during the PROOF-OF-CONCEPT (POC) testing which are concerned with these variables will be partially described here. It was deemed necessary to address some of the improvements originally planned for PERFORMANCE OPTIMIZATION Task 4 during the POC tests in order to achieve satisfactory results. These improvements will also be partially described here.

The primary item which was investigated during the POC testing was the method by which the non-blinding filter can operate with up to 12% ash in the coal fines and with minimal deterioration of filtration performance due to blinding. This method depends on controlling the location of the clay content of the ash as each new load of coal fines is being formed prior to drying. Particles of clay, unlike those of coal, are flat, leaf-like structures. This gives them the ability to quickly blind a filter. If the non-blinding system is not employed, the particles of clay in the coal will be quickly conducted by the filtrate toward the filter medium, where they will form an impervious layer. To prevent this, the non-blinding filter system shown in Figure 9 performs the following functions:

1. As the coal slurry is discharged from jets into the centrifuge bowl during filling, the agitation caused by the relatively high jet velocity and wide distribution of the jets, keeps the clay in suspension while the coal bed is beginning to solidify.

2. A metering system for retarding the outflow of filtrate through the filter media is employed to hold the filtrate flow to a rate which is too slow to overcome the tendency of the clay to remain in suspension due to the agitation caused by the jets. Thus the clay is kept away from the filter and the filter does not blind.

The original test plan for the POC Sub-task 3.1, called for 500 cycles of general testing using EVOP (evolutionary operational testing) to be followed by 500 cycles employing five matrices with several independent variables in each. This proved to be impractical because the feed slurry from the host plant varied sufficiently from hour to hour to cause standard deviations in final moistures of more than 1.5%. It was decided that simple EVOP tests in which only one independent variable at a time was changed, were best suited to the test conditions and objectives.

The following are the more important accomplishments and findings from this testing:

FEED SLURRY DENSITY SYSTEM IMPROVEMENTS

A used diaphragm pump was installed to pump the test slurry from the host plant. This pump can pump the thick, inherently foamy froth product at up to 58% solids by weight. This improvement enabled the slurry system to produce and deliver thicker slurry in adequate quantities to the centrifuge holding tank. The thicker slurry resulted in a significant improvement in the dried coal load weights. Test results concerning the relationship between feed solids percentage and load weight, are summarized in Figure 10. Figure 11 shows the density distribution in a typical 765 pound load as developed by an in-house generated computer program. The density of the coal in the outer portion of the load and the resulting reduction in the permeability of the coal are an important

SLURRY DENSITY VS. PRODUCTIVITY

FIGURE 10

DEPTH/PRESSURE/DENSITY CURVES
Figure 11

dependent variable which must be considered in optimizing the process. Slurry densities from 52% to 56% produced the best combinations of productivity and moisture. Thicker slurry became difficult to feed while thinner slurry yielded lighter weight loads and higher moistures.

FILLING AND WIPING IMPROVEMENTS (also relates to Subtask 4.3)

The present centrifuge feed system with the holding tank located on the same floor as the centrifuge, causes limitations in the potential head pressure supplied to the feed nozzles. It was found that the maximum potential nozzle head pressure could be raised by about 1.2 psi by raising the liquid level in the main tank. During the testing, increases in load weight and decreases in final product moistures resulted when nozzle head pressures were higher. The nozzle head pressure was inconsistent due to variations in the coal and foam in the feed slurry. Because of the limited potential, the response to higher nozzle head pressures could not be quantified accurately. Investigations pertaining to improvements in load weight and moisture could not be pursued at head pressures higher than an average of about 5 psi because to do so would have required major improvements in the feed system. The required improvements were not within the Scope of Work.

To enhance the turbulence which holds the clays in suspension during the forming of the loads, a feature designated as "stir-filling" was added. This process lowers the fill pipes to within about 3 inches of the old coal bed surface during the beginning of filling. The proximity of the feed nozzles to the slurry surface in the bowl, enhances the agitation of the slurry during the critical first few seconds of load formation. The fill tubes are then raised automatically after a preset percentage of the time used for the high flow portion of the fill sequence. The nozzles were lengthened to bring them closer to the slurry as a further improvement. The combination of these two measures has cut the initial distance from the nozzles to the bed onto which the slurry is being introduced by 50%. The importance of these measures is brought into focus when the conditions in the bowl during filling (as shown in Figure 9) are considered.

The wiper system was improved by changing from the earlier fabric and plastic wipers to a steel wiper blade. Due to wear and fatigue, the earlier blades were inconsistent. The addition of a device designated as the "wiper scoop" also represented a most important improvement. This device quickly removes the water and clay which collects on the inner surface of newly formed loads. As a result, most of the water which lies on the surface of the unwiped load of coal immediately after filling, is now conducted out of the mouth of the bowl in about 5 seconds. The wiper and the wiper scoop improvements have been responsible for improving the centrifuge performance by reducing the moisture on the inner two inches of the load by from 2 to 4%. In addition, the wiper scoop, by removing the clay laden coal from the inner surface of the load before spin-drying, has also contributed to better cutting out operation. The clay in the dried coal caused a major problem with the cutter screw clogging prior to the development of the wiper scoop.

It was found during the tests of Subtask 3.1, that running the bowl at higher speeds during filling, yielded better results. The loads were larger and less overflow was generated. In addition the bowl was more stable during filling because of the greater gyrodynamic effect. At the 1800 rpm filling speed used during this subtask, the loads could be formed in 10 seconds less than had been the case when the filling speed was 1400 rpm.

It was found during an earlier calibration of the bowl speed readout in March of 1990, that the bowl speed had been improperly calibrated. The result was that all testing performed in the preceding two quarters had been reported at 150 RPM higher than the actual speed. When 2800 rpm was reported, the actual speed was 2650. The programmer was in the centrifuge lab during September of 1990 to re-program the system for the addition of the STIR FILL feature when the error was discovered. During this work, the programmer corrected the bowl speed readout. Also at that time, CTC personnel under the direction of engineers from Westinghouse who designed the drive, raised the top speed of the machine to 3000 rpm. Stress analyses were made (using the in-house generated CTC stress programs for the centrifuge) to verify that the stress levels in the shaft and bowl were safe. The result of this work was an increase in the usable speed to 2,900 rpm and the indicated speeds were correct from that time forward.

Prior to the filling and wiping system improvements described above, the average total moisture was 13.5% with a load weight of 600 pounds. Surface clay was often causing trouble with the clean coal cutter screw clogging. The filling and wiping improvements resulted in these test results of September 5, 1990:

Cycle

Function	<u>Cngout</u>	<u>Fill</u>	<u>Wipe</u>	<u>Accel</u>	<u>Dwell</u>	<u>D'cel</u>	<u>Cut</u>
RPM (ending)	1800	1600	1400	2800	2800	200	200
Time, sec.	17	30	20	25	40	30	50

Stage 1 of filling cycle: 5 sec. (high flow rate)
Total filling time: 15 sec. (low flow rate)

Test Results

Total moisture of dried coal: 11.8%
Surface moisture of dried coal: 10.0%
Weight of dried coal cut out: 720 pounds

CUTTER IMPROVEMENTS (also relates to Subtask 4.6)

Much of the POC testing was done with a 6 1/8 inch depth of cut. Test data indicated that a deeper cut could be advantageous. The most obvious advantage was the increase in weight of the dried coal loads, with the resulting higher productivity. Figure 11 shows how a 0.625 inch increase in the outside radius of the cut increases the yield of dried coal by 90 pounds. This amounts to a productivity increase of 13%. In addition, the better removal of the clay from the inner surface of the new loads of coal by the improved wiper and scoop, dramatically reduced the level of problems with the cutter clogging. Although it was not confirmed, test personnel felt that there was also an improvement in moisture on the order of 1% with the deeper cut depths.

Ceramic cutter blades were substituted for the original steel blades. Carbide tipped blades were considered but they are much more expensive. To prevent sticking during cutting, the inside of the cutter body was coated with a ceramic/epoxy composite paint-on. This surface may be satisfactory for production units. The leading face of the cutter screw is of particular importance. The ceramic/epoxy surface was tested on the screw, but it was not sufficiently durable for production. A stainless steel screw with the leading face polished did prove to be satisfactory.

Coal Versatility Tests - Subtask 3.2

The objective of the Coal Versatility Tests was to confirm the ability of the new dryer system to efficiently dry an adequate variety of coals from various coal fields and seams. To facilitate these tests, an apparatus was constructed and tested for receiving and reconstituting the samples of clean coal froth product prior to transporting the slurry to the centrifuge holding tank. Samples of clean coal filter cake were grab sampled at the vacuum filters in preparation plants in Pennsylvania, West Virginia, Southern Illinois and Alabama. The filter cake samples were shipped in drums to the centrifuge lab at Big Rock, Virginia. The slurry reconstituting apparatus is illustrated in Figure 12. The slurry sample processing equipment consisted of:

- Drum handling hardware for the lab.
- A mixing deck for emptying and feeding filter cake from the drums.
- A mixing system using a mechanical mixer and compressed air jets.
- An air operated diaphragm pump to conduct the slurry to the holding tank.

While the centrifuge was designed for drying typical froth flotation product containing 28 mesh x 0 coal with from 25% to 35% minus 325 mesh, it was decided that test results would be more valuable if both coarser and finer samples were tested. After discussions with prospective sample suppliers, the following samples of froth product were selected for the tests:

MIXER/PUMP SYSTEM FOR HANDLING SAMPLES
OF COAL FINES FROM VARIOUS COAL FIELDS

MIXING CHAMBER OF MIXER/PUMP SYSTEM

FIGURE 12

<u>Location</u>	<u>Coal Seam</u>	<u>Top Size</u>	<u>- 325 Mesh</u>
Pennsylvania	Pittsburgh No. 8	28 mesh	58.2%
Alabama	Blue Creek	28 mesh	20.7%
West Virginia	Pittsburgh No. 8	28 mesh	25.7%
Southern Illinois	Herron No. 6	28 mesh	55.1%

Tests of Pennsylvania Source Coal - from Pittsburgh No. 8 Seam

This sample of very fine coal was included to determine the limiting parameters of the centrifuge concerning the finer fractions. The coal, as originally sampled, contained 49.9% minus 325 mesh. The process of remixing, preparing and holding the sample in suspension overnight, caused the minus 325 fraction to increase to 58.2%. The size consist of the feed slurry is shown in Figure 13. The analysis of a composite of the dried coal product is shown in Figure 14. This coal was much finer than that for which the centrifuge was designed, so the product moistures are higher. This test which was conducted on July 26, 1990, served as a valuable benchmark.

The moistures recorded were:

<u>Test Number</u>	<u>Total moisture</u>	<u>Surface Moisture</u>
1	28.8%	26.6%
2	24.0	21.8
3	24.2	22.0
4	21.4	19.2

COMMERCIAL TESTING & ENGINEERING CO.

GENERAL OFFICES: 1919 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-9300

Member of the SGS Group (Société Générale de Surveillance)

August 28, 1990

PLEASE ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 2721, PIKEVILLE, KY 41501-2721
TELEPHONE: (606) 432-2511
FAX: (606) 437-4657

COAL TECHNOLOGY CORPORATION
103 Thomas Road
Bristol VA 24201
Lloyd Smith

Sample identification by
Wellmore No. 8

SAMPLE ID

Kind of sample
reported to us Coal

CON-BT (Slurry)

Sample taken at Wellmore No. 8

Sample taken by Wellmore No. 8

Date sampled August 16, 1990

Date received August 16, 1990

(picked up sample)

Analysis report no. 48-67805

SHORT PROXIMATE ANALYSIS

	<u>As Received</u>	<u>Dry Basis</u>	
% Moisture	XXXXX	XXXXX	
% Ash	XXXXX	5.96	
Btu/lb	XXXXX	14396	MAF 15308
% Sulfur	XXXXX	1.51	

% EQUILIBRIUM MOISTURE = 2.2

SCREEN PERCENTAGES

<u>Passing</u>	<u>Retained On</u>	<u>% Weight</u>	<u>Cumulative % Weight</u>
--	+28 MESH	0.65	0.65
28 MESH	100 MESH	15.26	15.91
100 MESH	200 MESH	19.23	35.14
200 MESH	325 MESH	6.67	41.81
325 MESH	0	58.19	100.00

Pennsylvania Coal
Feed Slurry Analysis
FIGURE 13

Respectfully submitted,
COMMERCIAL TESTING & ENGINEERING CO.

Robert Campbell
Manager, Pikeville Laboratory

OVER 40 BRANCH LABORATORIES STRATEGICALLY LOCATED IN PRINCIPAL COAL MINING AREAS, TIDEWATER AND GREAT LAKES PORTS, AND RIVER LOADING FACILITIES

F-465
Original Watermarked For Your Protection

TERMS AND CONDITIONS ON REVERSE

TEST NO. 3 PRODUCT

% H₂O: 26.9

Volatile Matter, wt % dry	35.02
Fixed Carbon, wt % dry	58.68
Sulfur, Total, wt % dry	1.61
Btu/Lb.	14,361
MAF Btu/Lb.	15,327

<u>Screen Size</u>	<u>Wt %</u>	<u>Ash %</u>	<u>CUMULATIVE</u>	
			<u>Wt %</u>	<u>Ash %</u>
+28 M	0.00	0.00	0.00	0.00
28 x 60 M	7.11	4.71	7.11	4.71
60 x 100 M	7.52	4.67	14.63	4.69
100 x 200 M	19.83	4.75	34.46	4.72
200 x 325 M	11.32	5.48	45.79	4.91
-325 M	54.21	7.62	100.00	6.38
Head				6.30

Pennsylvania Coal
Dried Product Analysis

FIGURE 14

The slurry was introduced at 50% coal solids by weight. Because of the calibration error in the controls, actual filling speed was 1650 rpm and the drying speed was 2650 rpm instead of the intended 1800 and 2800 rpm. Better results would have been obtained at higher bowl speeds. This test was performed prior to the improvements described above on the filling and wiping system. Because of this and the very fine size consist of the test coal, the dry product weights averaged 556 pounds. This very light weight indicated poorly formed loads.

During the four tests which the available slurry permitted, there was a progressive improvement in moisture of 7.4% despite the successive lowering of the holding tank head pressure and the resulting lower nozzle pressure. This suggested that further improvement in moisture for the Pennsylvania coal sample would be probable after more thorough development of the process.

Tests of Alabama Source Coal - Blue Creek Seam

This coal had only 3% minus 325 mesh as collected. But, despite efforts to hold the mixing and stirring actions to a minimum, substantial comminution occurred prior to the test. The slurry as tested, is described in Figure 15. The analysis of a composite of the dried product from the test, is shown in Figure 16. The feed slurry was at 44% coal solids. The centrifuge drying speed was 2650 rpm and the load weights averaged 707 pounds. Final moistures recorded were:

<u>Test Number</u>	<u>Total Moisture</u>	<u>Surface Moisture</u>
1	8.6%	6.9%
2	9.0	7.3
3	9.0	7.3
4	<u>9.2</u>	<u>7.5</u>
Average	9.0%	7.25%

Tests of West Virginia Source Coal - from Pittsburgh No. 8 Seam

This coal contained 21.6% minus 325 mesh as sampled. In spite of care to minimize excessive mixing and stirring, the feed of the coal as tested had the size consist and analysis shown in Figure 17. The analysis and size consist of a composite of the dried coal are shown in Figure 18. The feed slurry was at 48.4% coal solids. The centrifuge drying speed was 2,650 RPM and the load weights averaged 753 pounds. Recorded final moistures were:

<u>Test Number</u>	<u>Total Moisture</u>	<u>Surface Moisture</u>
1	10.2%	8.2%
2	8.6	6.6
3	8.8	6.8
4	<u>8.0</u>	<u>6.0</u>
Average	8.9%	6.9%

COMMERCIAL TESTING & ENGINEERING CO.

GENERAL OFFICES: 1919 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-9300

Member of the SGS Group (Société Générale de Surveillance)

August 28, 1990

PLEASE ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 2721, PIKEVILLE, KY 41501-2721
TELEPHONE: (606) 432-2511
FAX: (606) 437-4657

COAL TECHNOLOGY CORPORATION
103 Thomas Road
Bristol VA 24201
Lloyd Smith

Sample identification by
Wellmore No. 8

SAMPLE ID

Kind of sample
reported to us Coal

JW-BT
Slurry
56% solids

Sample taken at Wellmore No. 8

Sample taken by Wellmore No. 8

Date sampled August 16, 1990

Date received August 16, 1990

(picked up sample)

Analysis report no. 48-67804

SHORT PROXIMATE ANALYSIS

	<u>As Received</u>	<u>Dry Basis</u>	
% Moisture	XXXXX	XXXXX	
% Ash	XXXXX	8.22	
Btu/lb	XXXXX	14368	MAF 15655
% Sulfur	XXXXX	0.86	

SCREEN PERCENTAGES

<u>Passing</u>	<u>Retained On</u>	<u>% Weight</u>	<u>Cumulative % Weight</u>
--	+28 MESH	19.27	19.27
28 MESH	100 MESH	42.48	61.75
100 MESH	200 MESH	10.99	72.74
200 MESH	325 MESH	6.60	79.34
325 MESH	0	20.66	100.00

*Alabama Coal
Feed Slurry Analysis*

FIGURE 15

27

Respectfully submitted,
COMMERCIAL TESTING & ENGINEERING CO.

Kathery Campbell
Manager, Pikeville Laboratory

COMMERCIAL TESTING & ENGINEERING CO.

GENERAL OFFICES: 1919 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-9300

Member of the SGS Group (Société Générale de Surveillance)

August 28, 1990

PLEASE ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 2721, PIKEVILLE, KY 41501-2721
TELEPHONE: (606) 432-2511
FAX: (606) 437-4657

COAL TECHNOLOGY CORPORATION
103 Thomas Road
Bristol VA 24201
Lloyd Smith

Sample identification by
Wellmore No. 8

SAMPLE ID

Kind of sample
reported to us Coal

JW-AT (CAKE)

Sample taken at Wellmore No. 8

Sample taken by Wellmore No. 8

Date sampled August 16, 1990

Date received August 16, 1990 (picked up sample)

Analysis report no. 48-67806

SHORT PROXIMATE ANALYSIS

	<u>As Received</u>	<u>Dry Basis</u>	
% Moisture	XXXXX	XXXXX	
% Ash	XXXXX	8.78	
Btu/lb	XXXXX	14287	MAF 15662
% Sulfur	XXXXX	0.92	

% EQUILIBRIUM MOISTURE = 1.7

SCREEN PERCENTAGES

<u>Passing</u>	<u>Retained On</u>	<u>% Weight</u>	<u>Cumulative % Weight</u>
--	+28 MESH	23.94	23.94
28 MESH	100 MESH	48.22	72.16
100 MESH	200 MESH	9.19	81.35
200 MESH	325 MESH	4.36	85.71
325 MESH	0	14.29	100.00

Alabama Coal
Dried Product Analysis

Respectfully submitted,
COMMERCIAL TESTING & ENGINEERING CO.

FIGURE 16

28

Manager, Pikeville Laboratory

OVER 40 BRANCH LABORATORIES STRATEGICALLY LOCATED IN PRINCIPAL COAL MINING AREAS, TIDEWATER AND GREAT LAKES PORTS, AND RIVER LOADING FACILITIES

F-465

Original Watermarked For Your Protection

TERMS AND CONDITIONS ON REVERSE

COMMERCIAL TESTING & ENGINEERING CO.

GENERAL OFFICES: 1919 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-9300

Member of the SGS Group (Société Générale de Surveillance)

September 19, 1990

PLEASE ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 2721, PIKEVILLE, KY 41501-2721
TELEPHONE: (606) 432-2511
FAX: (606) 437-4657

COAL TECHNOLOGY CORPORATION
103 Thomas Road
Bristol VA 24201
Lloyd Smith

Sample identification by
COAL TECHNOLOGY CORPORATION

SAMPLE ID

CON 2-BT

Kind of sample
reported to us Coal

Sample taken at Wellmore No. 8

Sample taken by Wellmore No. 8

Date sampled -----

Date received September 13, 1990

(picked up sample)

Analysis report no. 48-68270

SHORT PROXIMATE ANALYSIS

	<u>As Received</u>	<u>Dry Basis</u>	
% Moisture	XXXXX	XXXXX	
% Ash	XXXXX	7.35	
Btu/lb	XXXXX	14048	MAF 15162
% Sulfur	XXXXX	2.34	

% EQUILIBRIUM MOISTURE = 2.0

SCREEN PERCENTAGES

<u>Passing</u>	<u>Retained On</u>	<u>% Weight</u>	<u>Cumulative % Weight</u>
--	+28 MESH	8.91	8.91
28 MESH	100 MESH	47.06	55.97
100 MESH	200 MESH	13.10	69.07
200 MESH	325 MESH	5.24	74.31
325 MESH	0	25.69	100.00

*West Virginia Coal
Feed Slurry Analysis*

Respectfully submitted,
COMMERCIAL TESTING & ENGINEERING CO.

Rooney Campbell

FIGURE 17

29

Manager, Pikeville Laboratory

COMMERCIAL TESTING & ENGINEERING CO.

GENERAL OFFICES: 1919 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-9300

SINCE 1908

Member of the SGS Group (Société Générale de Surveillance)

September 19, 1990

PLEASE ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 2721, PIKEVILLE, KY 41501-2721
TELEPHONE: (606) 432-2511
FAX: (606) 437-4857

COAL TECHNOLOGY CORPORATION
103 Thomas Road
Bristol VA 24201
Lloyd Smith

Sample identification by
COAL TECHNOLOGY CORPORATION

SAMPLE ID

CON 2-AT

Kind of sample
reported to us Coal

Sample taken at Wellmore No. 8

Sample taken by Wellmore No. 8

Date sampled -----

Date received September 13, 1990

(picked up sample)

Analysis report no. 48-68269

SHORT PROXIMATE ANALYSIS

	<u>As Received</u>	<u>Dry Basis</u>	
% Moisture	XXXXXX	XXXXXX	
% Ash	XXXXXX	8.04	
Btu/lb	XXXXXX	13947	MAF 15166
% Sulfur	XXXXXX	2.68	

SCREEN PERCENTAGES

<u>Passing</u>	<u>Retained On</u>	<u>% Weight</u>	<u>Cumulative % Weight</u>
--	+28 MESH	8.00	8.00
28 MESH	100 MESH	52.37	60.37
100 MESH	200 MESH	15.31	75.68
200 MESH	325 MESH	5.35	81.03
325 MESH	0	18.97	100.00

West Virginia Coal
Dried Coal Analysis

Respectfully submitted,
COMMERCIAL TESTING & ENGINEERING CO.

Rooney Campbell

FIGURE 18

Manager, Pikeville Laboratory

30

OVER 40 BRANCH LABORATORIES STRATEGICALLY LOCATED IN PRINCIPAL COAL MINING AREAS, TIDEWATER AND GREAT LAKES PORTS, AND RIVER LOADING FACILITIES

465
Original Watermarked For Your Protection

TERMS AND CONDITIONS ON REVERSE

Tests of Southern Illinois Source Coal - From Herron No.6 Seam

The final test in Subtask 3.2 was completed on October 25, 1990. The sample was from the vacuum disk filters at a Southern Illinois coal processing plant. The test coal was quite fine and it (like the Pennsylvania sample tested earlier) represented a size consist finer than the centrifuge was designed for. Nevertheless the test revealed that:

- Improvements in both equipment and methodology allowed much more successful drying of this very fine coal
- If the clay content in the coal is low, higher percentages of minus 325 mesh coal can be dried successfully

The size consist and analysis of the test coal as fed to the centrifuge, is given in Figure 19. The size consist and analysis of the dried coal product is shown in Figure 20. By using a 2,000 RPM filling speed and a 90 second dwell speed at 2,800 RPM the final surface moisture of the test coal was reduced to 9.4 % by the third of the four tests. This result was obtained in spite of the handicap of the lower head pressure on the nozzles created by the lowering of the physical level in the holding tank with no make-up being added. The inherent moisture (measured as equilibrium moisture) of the sample was 6.9%. Centrifuges are only effective for the removal of surface moisture.

The following developments influenced the improvement in final moistures of the Southern Illinois coal over the earlier Pennsylvania sample results:

- The higher filling speed resulted in better load formation
- The new wiper and scoop removed the clays from the surface of the newly formed loads with greater efficiency
- The LVDT Load Level Control which is described on Page 55, kept the bowl level and this yielded better wipes
- The higher dwell speeds resulting from the correction of the speed control calibration lowered moisture

The following are some observations pertinent to the feasibility of the CTC High Gravity Centrifugal Dryer for drying coal fines represented by the sample from the Pennsylvania processing plant. The tests of this very fine coal were conducted prior to the perfection of the filling and wiping techniques during this project. The tests of the Southern Illinois sample were conducted after the improvements listed above had been accomplished. Later testing indicated that the performance would have been further enhanced by higher nozzle pressures and the Load Depth Control Dam (described later) for facilitating the use of loads with less radial depth. The Southern Illinois coal had a size consist quite similar to that of the Pennsylvania sample.

COMMERCIAL TESTING & ENGINEERING CO.

GENERAL OFFICES: 1919 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-9300

Member of the SGS Group (Société Générale de Surveillance)

October 24, 1990

PLEASE ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 2721, PIKEVILLE, KY 41501-2721
TELEPHONE: (606) 432-2511
FAX: (606) 437-4657

COAL TECHNOLOGY CORPORATION
103 Thomas Road
Bristol VA 24201

Sample identification by
Coal Technology

SAMPLE ID

Kind of sample
reported to us Coal

Southern Illinois Coal Feed

Sample taken at United Coal

Sample taken by Coal Technology

Date sampled -----

Date received October 22, 1990

(picked up sample)

Analysis Report No. 48-69096

SHORT PROXIMATE ANALYSIS

	<u>As Received</u>	<u>Dry Basis</u>		
% Moisture	31.73	XXXXXX		
% Ash	4.77	6.99		
Btu/lb	9250	13549	MAF	14567
% Sulfur	1.66	2.43		

% EQUILIBRIUM MOISTURE = 6.9

SIEVE ANALYSIS

<u>CUMULATIVE RESULTS</u>				
<u>Passing</u>	<u>Retained On</u>	<u>% Weight</u>	<u>% Retained</u>	<u>% Passing</u>
-----	28 MESH	1.22	1.22	100.00
28 MESH	100 MESH	24.28	25.50	98.78
100 MESH	200 MESH	12.42	37.92	74.50
200 MESH	325 MESH	6.99	44.91	62.08
325 MESH	0	55.09	100.00	55.09

Respectfully submitted,
COMMERCIAL TESTING & ENGINEERING CO.

Figure 19

32

Manager, Pikeville Laboratory

COMMERCIAL TESTING & ENGINEERING CO.

GENERAL OFFICES: 1919 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-9300

Member of the SGS Group (Société Générale de Surveillance)

November 2, 1990

PLEASE ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 2721, PIKEVILLE, KY 41501-2721
TELEPHONE: (606) 432-2511
FAX: (606) 437-4657

COAL TECHNOLOGY CORPORATION
103 Thomas Road
Bristol VA 24201
Lloyd Smith

Sample identification by
COAL TECHNOLOGY CORPORATION

SAMPLE ID

Kind of sample
reported to us Coal

Southern Illinois Coal Product

Sample taken at xxxx

Sample taken by COAL TECHNOLOGY CORPORATION

Date sampled -----

Date received October 29, 1990

(picked up sample)

Analysis Report No. 48-69303

SHORT PROXIMATE ANALYSIS

	<u>As Received</u>	<u>Dry Basis</u>		
% Moisture	16.30	xxxxx		
% Ash	5.52	6.60		
Btu/lb	11358	13570	MAF	14529
% Sulfur	2.09	2.50		

SIEVE ANALYSIS

<u>Passing</u>	<u>Retained On</u>	<u>% Weight</u>	<u>CUMULATIVE RESULTS</u>	
			<u>% Retained</u>	<u>% Passing</u>
-----	28 MESH	1.09	1.09	100.00
28 MESH	100 MESH	37.57	38.66	98.91
100 MESH	200 MESH	19.77	58.43	61.34
200 MESH	325 MESH	8.90	67.33	41.57
325 MESH	0	32.67	100.00	32.67

Respectfully submitted,
COMMERCIAL TESTING & ENGINEERING CO.

Robert Campbell
Manager, Pikeville Laboratory

Figure 20

33

OVER 40 BRANCH LABORATORIES STRATEGICALLY LOCATED IN PRINCIPAL COAL MINING AREAS, TIDEWATER AND GREAT LAKES PORTS, AND RIVER LOADING FACILITIES

Given below are the comparative size consists:

<u>Screen Size</u>	<u>Pennsylvania</u>	<u>Sou. Ill.</u>
+28 M	0.65	1.22
28 x 100 M	15.26	24.28
100 x 200 M	19.23	12.42
200 x 325 M	6.67	6.99
-325 M	58.19	55.09
Ash	5.96%	6.99%
Best Surf. Moist.	19.2%	9.4%

These results are not meant to describe what is judged to be the capability of the new centrifugal dryer. They are meant to support the opinion of CTC test personnel that the probability is good that the centrifuge can do an adequate job of drying a coal feed finer than the design size consist of 28 mesh x 0 with 35% minus 325 mesh.

Material Balance Determinations

To facilitate planning for the integration of the centrifugal dryer into coal plants, it was necessary to know the material balance of the system for coals likely to be encountered. While it is possible that improvements can be made in reducing the overflow percentages experienced during the testing, the level of overflow recorded during the tests, yields a practical economic framework.

WORST CASE MATERIAL RECOVERY- Higher Clay Fines from Host Plant

The test coal was froth product at 37-1/2% minus 325 mesh. Final total moisture was 11.4%. Equilibrium moisture was 1.7%.

	<u>Weight #</u>		
	<u>Coal</u>	<u>Water</u>	<u>Total</u>
Dried Coal	642	83	725
Overflow	374	742	1116
Filtrate	<u>25</u>	<u>219</u>	<u>244</u>
Feed	1041	1044	2085

The coal used in the test described above was found to have improved in Btu/pound as well as in ash content by the centrifugal drying process. Tabulated below are size consist and the values of ash, Btu/pound, and sulphur for the host plant coal:

<u>Passing</u>	<u>Retained on</u>	<u>Feed</u>	<u>Product</u>	<u>Overflow</u>	<u>Filtrate</u>
-----	28 mesh	3.85%	6.49%	1.16%	0.09%
28 mesh	100	32.64	43.10	14.74	7.12
100	200	18.12	18.62	14.81	12.56
200	325	7.85	7.72	9.19	10.54
325	0	37.54	24.07	60.10	69.69

Dry Basis Values:

Ash	11.81%	7.74%	17.58%	16.74%
BTU/pound	13,456	14,223	12,635	12,823
Sulphur, Total	0.87%	0.98%	0.73%	0.76%

Test work has shown ash reductions varying from 1.0% to 4.0%. The improvements in ash are due to the loss of high ash ultra-fines in the overflow and filtrate. The amount of beneficiation is dependent on the type of coal and its size consist. The improvements in the wiper and scoop units appeared to produce concurrent improvements in beneficiation. These factors also improve the direct recovery rate of the centrifuge. The direct recovery rate for the test described above was 61.7%. Later tests using almost identical coal, yielded a 75.0% direct recovery. Methods for achieving total system recoveries above 98% will be described later under RECOVERY SYSTEM.

BEST CASE MATERIAL RECOVERY- Pittsburgh No. 8 Seam Coal Fines From West Virginia

The test coal was froth product at 25.69% minus 325 mesh. The final total moisture was 9% and equilibrium moisture was 2.0%.

	<u>Weight #</u>		
	<u>Coal</u>	<u>Water</u>	<u>Total</u>
Dried Coal	695	67	762
Overflow	148	697	845
Filtrate	<u>17</u>	<u>153</u>	<u>170</u>
Feed	860	917	1777

Tabulated below are the size consist and analysis of the test coal:

<u>Passing</u>	<u>Retained On</u>	<u>Feed</u>	<u>Product</u>	<u>Overflow</u>	<u>Filtrate</u>
-----	28 mesh	9.71%	8.08% 2	.26%	4.38%
28 mesh	100	47.06	52.38	19.35	34.15
100	200	16.03	17.07	10.25	13.77
200	325	6.32	7.17	6.36	7.52
325	0	20.73	15.30	61.78	40.18

Dry Basis Values:

Ash	7.46%	7.50%	7.29%	7.02%
BTU/pound	14,048	13,947	-----	-----
Sulphur, Total	2.55%	2.68%	1.92%	2.16%

These data indicate a direct recovery rate of 80.8%. Coal of this order of size consist can be recovered at nearly 100% total system recovery as will be explained in ECONOMIC EVALUATION.

PERFORMANCE OPTIMIZATION TESTS - Task 4

The objective of the performance optimization tests was to sufficiently coordinate the independent variables with one another to achieve a level of performance commensurate with readiness for commercialization of the high-gravity, batch-type centrifuge. Because of the great number of interactive independent variables, the project work plan divided these tests into six primary areas which will be discussed separately. The project work plan originally included the use of formal test matrices and statistical analysis to optimize the independent variables. However, variations in the size consist in the coal from the host plant precluded this. With the approval of the COR, evolutionary operational testing was used instead.

Tests of Filter Flow Rate vs Surface Moisture - Subtask 4.1

The objective of these tests was to find the values of the principal independent variables in the filter system which yielded the best combination of final product surface moisture and productivity.

In order to conduct the filter flow rate tests efficiently, it was necessary to develop a filter system which could be removed and re-installed quickly. Such a system was needed since the changing of the orifice area with the original filter would have been too time consuming. The orifice area is the total cross sectional area of the holes in the bowl through which the filtrate exits the bowl. These holes in combination with the filter media, control the rate of outflow of the filtrate as a part of the non-blinding filter system. It was also important to identify a method whereby production filters could be precisely duplicated and quickly installed in the commercial centrifuges.

The original filter segments were constructed by Newark Wire Cloth Co. by layering a number of wire cloths of different mesh sizes and wire diameters. The filter medium on the inner surface of each filter segment was 120 mesh SS wire cloth. The other layers were of progressively coarser wire cloth and offered minimal resistance. The filters were formed to fit the inside of the bowl and then they were sintered together. There were 6 segments in each of the 2 filter gutters in the centrifuge bowl, for a total of 12 segments. The cross sectional area of the orifices in the bowl were adjusted by placing plugs in some of the holes. It became impractical to continue this testing with the original filters because the filters were glued into the bowl and they became progressively more deteriorated with each removal for orifice area changes.

The original filters were used prior to and during the first 15 months of this project. They were removed to allow the installation of the production prototype filters. It was observed by test personnel that during the period from 10-16-90 to 12-19-90, the original filters performed consistently well. Table 2 summarizes the test results obtained during this period and the analysis of a coal sample typical of that used during this testing. The average total moisture from these tests was 12.6%. When the equilibrium moisture of 1.8% is considered, the resulting surface moisture average was 10.8%. These tests were obtained prior to the optimization of the resistivity of the new filter and therefore do not represent the potential of the new centrifugal drying system.

While the concept of the six segment filter in each of the two gutters was judged to be a good one, the previously used method of installation was too tedious. A new construction was decided on which would include a system of retainers for holding the filter segments in place prior to operation. Then, when the centrifuge was started, a self sealing system would use the artificial gravity to seal the filter segments against the bowl. A vinyl channel around each filter segment would form the seal.

In constructing the new prototype filters with multiple layers of various thicknesses of wire cloth, a number of plastic matrix materials were investigated for holding the multiple layers together. It was important that the plastic which was used around and melted into the edges of the filter segments be of sufficient resilience to allow the segments to yield under the centrifugal force and assume the exact shape of the bowl to complete the sealing action. After several plastics were investigated, it was found that ordinary hot-melt glue gave an ideal level of resilience and could be easily melted into the edges of the wire cloth. A system of forms was constructed and used during the hot melt operation to assure that the segments would fit the bowl properly. Ordinary vinyl plate glass edging channel was used around the filter segments to form the self sealing border. The vinyl channel was installed with automobile trim cement. One of the finished filter segments is shown in Figure 21.

DATE	TYPE COAL	CHARGE CUT	FILL	RPM DWELL	SEC. DWELL	% SLURRY	ORIFICE AREA	WT. PROD.	% MOIST.	REMARKS
12-19-90	KY Hagy	1650	1300	2500	50	51.0	40	652	11.1	
11-14-90	Met	2000	2000	2800	80	56.0	40	727	13.6	
11-12-90	Met	2000	1800	2800	40	53.9	40	732	15.0	
11-05-90	KY Hagy	2000	2000	2800	40	50.1	40	749	12.4	Steel wiper in
10-30-90	Met	2000	1800	2650 2400	40	51.6	40	740	12.5	
10-29-90	Met	1800	1600	2800	50	51.6	40	754	11.7	
10-18-90	Met	1800	1600	2800	40	52.0	40	750	12.8	First 5 sec. wipe
10-17-90	Met	1800	1600	2650	40	53.2	40	770	11.9	
10-16-90	Met	1800	1600	2650	40	52.8	40	745	12.4	

SIEVE ANALYSIS

Passing	Retained On	% Weight	CUMULATIVE RESULTS	
			% Retained	% Passing
28 MESH	28 MESH	4.74	4.74	100.00
100 MESH	100 MESH	38.26	43.00	95.26
200 MESH	200 MESH	11.16	54.16	57.00
325 MESH	325 MESH	12.67	66.83	45.84
0	0	33.17	100.00	33.17

SHORT PROXIMATE ANALYSIS

	As Received	Dry Basis
% Moisture	56.93	XXXXX
% Ash	4.04	9.38
Btu/Lb	5963	13846
% Sulfur	0.37	0.87
		MAF 15279

TABLE 2

RESULTS WITH ORIGINAL FILTER

FINISHED FILTER SEGMENT

FIGURE 21

INTERIOR OF CENTRIFUGE BOWL

- A ---- FILTER CHANNEL
- B ---- FILTER INSTALLED
- C ---- RETAINER

FIGURE 22

Wire retainers were used to hold the segments in place prior to operation of the centrifuge. Figure 22 shows the interior of the centrifuge bowl. In Figure 22 at (A), is an empty filter gutter revealing the orifices in the bowl. At (B) is the other filter gutter with six filter segments held in place with the stainless steel wire retainers at (C). The structures with axial divisions between them, are the slats which form a system of conical filtrate biasing members. The conical surfaces bias the filtrate toward the filters when under artificial gravity.

The final step of filter construction was to bring all 12 segments to within 0.01 pound of the same weight. The result was that changing filters made no perceptible difference in the balance of the bowl. The sealing system was also successful to the extent that no significant leakage was detected in any of the tests after the new filters were adopted. The new filters were successful in being easy to install, in sealing and in remaining in balance.

The original filter media were single layers of 120 mesh stainless steel cloth. Underneath the media were several layers of progressively coarse wire cloth to support the media and to provide passages for lateral movement of the filtrate to the orifices in the bowl. The first new prototype filters were fitted with fresh 120 mesh stainless steel cloth media.

When the new filters were tested, performance was poor. Loading was difficult, wipes were unsatisfactory. Water and clay remained on the inner surface of the load of coal during the spin drying portion of the cycle. The product weights averaged around 100 pounds less than that which had been experienced with the original prototype filters. An investigation revealed that there was a significant difference between the resistivity of the fresh stainless steel cloth and the stainless steel cloth on the original filters. The lower resistivity of the new wire cloth was found to have allowed the filtrate to move too rapidly toward the filter and to have brought the clays with it to blind the filter. A test procedure aimed at obtaining an accurate comparison of the resistivity of different test media, was then developed. The test hardware shown in Figure 23 consisted of a 12 inch long tube and a 2 inch long tube each of 1.25 inch diameter with a socket into which sample media could be sealed. A convenient test index was found to be:

RESISTIVITY INDEX = seconds for 16 fluid ounces of water to flow through the 1.25 inch diameter media samples under a water pressure head equal to the height of the tube.
(A correction was made for variations in viscosity caused by temperature changes)

When the stainless steel cloth from the original filter was compared with fresh stainless cloth in the 12 inch tube, the resistivity of the used media was found to be higher. The resistivity test results were:

<u>Material</u>	<u>Flow Index</u>
Original 120 Mesh SS Media	3.4 seconds
Fresh 120 Mesh SS Media	0.8 seconds

MEDIA RESISTIVITY TEST RIGS

FIGURE 23

A careful comparison of the sample media revealed that the used stainless steel media cloth had picked up a metallic coating over time. Electrolysis seems to have been the source of the metallic plating deposited on the cloth. These results indicated that the resistivity of the media is more critical to the process than had been thought earlier. With this discovery revealed, it was concluded that the originally planned optimization of the orifice area, must now be planned as an optimization with 2 independent variables which are interdependent. It would be necessary to optimize both the filter media resistivity and the resistivity of the orifices as interdependent variables.

In order to get back to the baseline performance indicated by the performance of the original filters after about 18 months of electroplating, a search was begun for media satisfactory for testing the new theory. A non-metallic fabric from a fabric store with a 5 second resistivity index (with the 12 in. test column) was located. It was installed on filter segments and tested. Tests of the non-metallic filter media, produced results sufficiently close to the baseline moistures in the tabulation, and seemed to vindicate the media resistivity theory. Total moistures averaged 13.9%. While these were not considered to be satisfactory moistures, the actions of the centrifuge during loading as well as the product weights, were closer to the baseline performance obtained with the original filters.

As the testing of the first non-metallic fabric filter media progressed, it became apparent that there were some elusive qualities about the media that had not yet been identified and which materially affected performance. In an effort to learn more about these qualities, the filter media flows rate index tests were modified to include the two inch long tube. Originally, only the 12 inch water column was used. As before, the flow rate index is the number of seconds required for 16 fluid ounces of water to flow through the filter under the designated head in inches of water. The results of the more significant tests with the two columns are tabulated below:

FILTER FLOW RATE TESTS

Head - Inches of Water

<u>Filter</u>	<u>Avg. Test</u>		<u>Moisture</u>
	<u>12</u>	<u>2</u>	
New 120 mesh SS cloth(un-used)	0.8 sec.	2.0 sec.	16.8%
Original 120 mesh SS cloth	3.4	12.4	12.0
First fabric (orange)	5.0	21.0	13.9
Second fabric (yellow)	15.0	492.0	13.8
Third fabric (green)	18.0	240.0	13.2

There were some indications that the original 120 mesh stainless steel filter had some coal lodged in it before removal. This lodged coal would have caused a higher index, and thus, a lower flow rate than was indicated after removal and handling. This possibility was not fully verified.

It became apparent during the testing that the resistance of the production filter media must be held to close tolerances. Close tolerances called for accurate resistance measurements. Since the exact nature of the filtration process was not known, three systems for indexing the media for resistivity were finally adopted. In all of the resistivity tests the test sample medium was clamped across a 1.25 inch diameter tube. The net medium area was equivalent to 1.25 inch diameter or 1.227 sq. in.

To check the rate of flow under laminar (low pressure) conditions, the 2 inch gravity loaded water test column was used. After installing a media sample in the 2 inch test column, the column was held under a water faucet and water flow was adjusted until the faucet flow with the column full, exactly balanced the outflow through the filter sample. The test column was then removed and the time for 16 fluid ounces to flow from the faucet was measured with the stop watch and 16 ounce measuring cup. The number of seconds required for 16 ounces to flow was the laminar flow index. To correct for viscosity variations a correction was made based on a flow test with a standard sample from the original filter during each test.

Similarly, for measuring moderately turbulent (medium pressure) flow, the 12 inch column, was used. The test procedure for the 12 inch column was the same as that used with the 2 inch column. This produced a medium turbulence flow index.

For indexing the flow with severe turbulence (high pressure), the test rig shown in Figure 24 was used. This air flow test employed a vacuum source which draws a vacuum across the media sample. To test a media sample, the test rig was first calibrated using a standard media sample from the original filter, which had proved to be at or near the ideal resistivity. The media standard was inserted in the test rig and the level of vacuum was adjusted by means of a leak valve so that the vacuum in the test rig was at 2 inches of mercury (.9824 psi). After calibrating the test rig, the standard sample was removed and the media sample to be indexed was inserted into the test rig. A reading of the vacuum produced with the test sample was then recorded as the high turbulence flow index. During this test, the air from the static outside atmosphere accelerated to a velocity approaching 20,883 feet per minute as it passed through the filter media sample. This produced sufficient turbulence to give a satisfactory high turbulence flow index.

A variety of filter media were tested. The media concept selected was the use of 120 mesh SS wire cloth with a carefully controlled thickness of nickel plating. This had the effect of precisely increasing the wire diameter and of accurately modulating the resistivity of the media. The first filters made according to this new concept, were much too high in resistivity. However, further investigation indicated that this method can produce satisfactory filters. The resulting filters are capable of yielding highly repeatable results at low cost. The filter media resistivity optimization process then was begun.

HIGH PRESSURE RESISTIVITY TEST RIG

FIGURE 24

Plating thicknesses greater than 0.0009 in. for the new filters showed no promise that loads could be formed on them or wiped consistently. The optimization tests progressed from 0.0009 in. through 0.0004 in. in plating thickness before the bottom of the predicted inverted bell curve was established at 0.0005 in. Tests were also run with unplated 120 mesh stainless cloth to establish the low resistivity boundary of the bell curve. Since the general construction and the wire thicknesses of the coarser supporting layers of wire cloth in the new and in the original filters were different, the results are not directly comparable. The cycles used and the data averages from these tests are tabulated below:

Cycle Used During Tests

<u>Function</u>	<u>Bowl RPM</u>	<u>Duration sec.</u>
Ready	200	- - -
Change-Out	2,100	20
Fill	2,000	30
Wipe	1,400	7
Accelerate	2,800	27
Dwell	2,800	40
Decelerate	200	60
Cut	200	50
First Portion of Fill	7 sec. @ 100% flow	
Second Portion of Fill	8 sec. @ 35% flow	
Delay After Fill	15 sec. @ 0% flow	

<u>Average Final Total Moistures</u>	
<u>Plating Thickness</u>	<u>Moisture</u>
.0009 in.	18.0%
.0008	14.6
.0007	13.1
.0006	12.0
.0005	10.6
.0004	12.2
0	15.7

The coal used was typical of that which was used during most of the testing. It is a metallurgical coal blend from Southwest Virginia and Eastern Kentucky seams. The size consist and an analysis of the coal is shown in Figure 25. A graphic representation of the plating thickness/ moisture relationship, is shown in Figure 26.

COMMERCIAL TESTING & ENGINEERING CO.

GENERAL OFFICES: 1919 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-9300

Member of the SGS Group (Société Générale de Surveillance)

November 8, 1990

PLEASE ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 2721, PIKEVILLE, KY 41501-2721
TELEPHONE: (606) 432-2511
FAX: (606) 437-4657

COAL TECHNOLOGY CORPORATION
103 Thomas Road
Bristol VA 24201
Lloyd Smith

Sample identification by
COAL TECHNOLOGY CORPORATION

SAMPLE ID

Kind of sample
reported to us Coal

Met Feed Stock
11/5/90
Metra
25"

Sample taken at xxxx

Sample taken by COAL TECHNOLOGY CORPORATION

Date sampled November 5, 1990

Date received November 5, 1990

(picked up sample)

Analysis Report No. 48-69494

SIEVE ANALYSIS

<u>Passing</u>	<u>Retained On</u>	<u>% Weight</u>	<u>CUMULATIVE RESULTS</u>	
			<u>% Retained</u>	<u>% Passing</u>
-----	28 MESH	4.74	4.74	100.00
28 MESH	100 MESH	38.26	43.00	95.26
100 MESH	200 MESH	11.16	54.16	57.00
200 MESH	325 MESH	12.67	66.83	45.84
325 MESH	0	33.17	100.00	33.17

SHORT PROXIMATE ANALYSIS

	<u>As Received</u>	<u>Dry Basis</u>	
% Moisture	56.93	XXXXXX	
% Ash	4.04	9.38	
Btu/lb	5963	13846	MAF 15279
% Sulfur	0.37	0.87	

Respectfully submitted,
COMMERCIAL TESTING & ENGINEERING CO.

Robert Campbell

FILTER FLOW RATE TEST COAL ANALYSIS

Manager, Pikeville Laboratory

Figure 25

OVER 40 BRANCH LABORATORIES STRATEGICALLY LOCATED IN PRINCIPAL COAL MINING AREAS, TIDEWATER AND GREAT LAKES PORTS, AND RIVER LOADING FACILITIES

Solid Line From Data

Dotted Line Estimated

PLATING THICKNESS VS. MOISTURE

FIGURE 26

The following two points are significant. First, about 0.001 in. of metal was deposited on the stainless steel media in two years of testing. This would indicate a rate of 0.000125 in. of build-up per quarter. These data point to at least the order of six months service life for a set of filters which carried a total cost in pilot quantities of less than \$1,000. The filters can be changed in one hour by one person. It is also significant that the original filter experienced the plating on stainless steel wire. We are informed by the plater that a nickel plated surface is less active than was the stainless steel when receiving electroplating. From this, the plater expects a slower rate of build up on the nickel plated media.

Another finding during the testing was that the previously successful filter now being used as a standard, was constructed with heavy SS wire cloth supporting layers next to the orifices in the bowl. The effect of this heavy wire cloth was measured and found to have had the effect of reducing the orifice area in the standard filter (relative to the orifice area of the new production filters) by about 25%. The new filters have thinner, less tightly woven screen, next to the metering orifices in the bowl. Using 40 sq. in. of orifice area with the original filter equals 30 sq. in. of effective orifice area with the new filters. This development is favorable for the bowl stresses as fewer holes are required to give the needed orifice area. The stresses in the bowl shell are reduced proportionately.

Final optimization of the centrifuge system can only be possible during continuous production when long term tuning of the components can be accomplished. However, the 120 mesh stainless steel wire cloth media with 0.0005 in. thick nickel plating in combination with 30 sq. in. of orifice area is considered to be satisfactory for the beginning of commercialization.

Tests of Bowl Speed vs Surface Moisture - Subtask 4.2

The objective of these tests was to optimize the relationship between bowl speed and final product moisture. The test team decided that the project would benefit from tests at up to 2,900 RPM instead of the original speed limit of 2800 RPM which had been adopted for Prototype 2. To prepare for the higher speed testing, the bowl and neutralizer ring were re-balanced. The re-balancing was also beneficial in that the capability of the vibration containment system could be fully demonstrated. The vibration containment system is shown in Figure 27.

Since the vibration encountered in a very high speed centrifuge can transmit considerable energy, the vibration instrumentation must read in velocity of vibration rather than in the more traditional amplitude. Using the control panel readouts of radial velocity of vibration of the bowl and of the gimbal, the neutralizer ring and the centrifuge bowl were balanced. After balancing, the bowl which had been registering up to 2.5 inches per second, registered from 0.5 to 1.0 inch per second. This is equivalent to a range of 14 to 28 mils of vibration at 2,800 rpm at the center of the bowl with 750 pounds of coal in the bowl. The gimbal vibration reading (which indicates the vibration which is transmitted to the foundation of the centrifuge) was reduced from 0.8 inches per second before balancing to less than 0.2 inches per second after balancing. This amounts to reducing the amplitude of vibration at the gimbal from 5.2 mils down to 1.3 mils at 2,800 rpm. Anything below 2 mils is considered smooth for large rotating machinery.

Following the balancing, the main variable frequency AC drive was adjusted for a top speed of 3,000 rpm. This provided a sufficient overspeed allowance for testing at up to 2,900 RPM.

In connection with the study of speed vs product moisture, studies were made to explore the amount by which the reduction of cross section of the minute passages in the coal bed through which the water must pass may render excessively high gravity levels with thick coal beds to be counter-productive.

In addition to tests in Prototype 2 (the full size prototype), an in house generated computer program which models the loads of coal was developed and used. Table 3 uses this program to show the relationships of gravity, density, cumulative pressure and cumulative load weight as the radius of the load increases. The density of solid coal with no voids from the seams processed in the host plant average about 83 pounds/ cubic foot. The outer layer of centrifuged coal after drying, weighed 73.8 pounds/ cubic foot. It can be seen that the voids through which the filtrate must pass are very small. Studies have also shown that at above 1,000 pounds/ sq. in. of pressure on the coal, the particles will begin to lose their integrity of shape and thus generate more fines. Table 3 shows that there is a limit to the gravity/load thickness levels that are practical for centrifugally drying coal fines.

VIBRATION CONTAINMENT SYSTEM

FIGURE 27

Table 3

COAL DENSITY & PRESSURE VS DEPTH

From CTC Program PRSDPTHW.5

Parameters:

Inside diameter of load 18.0 in.
 Length of Load 34.5 in.
 Radial Interval of Layers 0.5 in.

Conditions at Layer

<u>Layer OD</u>	<u>Gravity</u>	<u>Density</u>	<u>Pressure</u>	<u>Cum. WT.</u>
19 in.	2,060	.0341#/in ³	34.2 psi	34.2#
20	2,172	.0362	70.8	72.5
21	2,283	.0375	109.2	114.1
22	2,394	.0384	149.2	158.9
23	2,505	.0391	190.7	206.6
24	2,617	.0397	233.7	257.2
25	2,728	.0403	278.1	310.7
26	2,839	.0407	324.1	366.9
27	2,951	.0411	371.7	426.0
28	3,062	.0415	420.8	487.8
29	3,173	.0418	471.5	552.4
30	3,285	.0421	523.9	619.8
31	3,396	.0424	577.9	690.0
32	3,396	.0427	633.5	762.3

This does not mean that there is a definite limit to the number of gravities that can be applied, but it does show that there is a limit to the artificial gravity that can be used efficiently for a load of a particular thickness.

Observations of the filling process suggest that for the finer size consists, somewhat thinner loads would be more efficient. Providing for thinner loads can be easily accomplished by providing dams in the form of replaceable rings in the mouths of the centrifuge bowls. With this arrangement, the hole in each bowl can be larger and the ring dams of appropriate inside diameter can be applied to provide the optimum inside diameter at the mouth of the bowl for each different coal. For a bowl the size of Prototype 2 with its 18.5 in. I. D. opening, 2,800 to 2,900 RPM is judged to be an ideal working range for drying the feed from the host plant. For the Pennsylvania and Southern Illinois samples, larger opening and a thinner load would yield better performance.

Tests of Nozzle configuration vs Surface Moisture - Subtask 4.3

The objective of these tests was to optimize the filling and wiping system components to yield dried product with the best possible moisture and productivity.

During the first few seconds in the process of forming a 750 pound load of coal from 175 gallons of slurry, the events occur swiftly and in a chaotic manner. During this period, the 7 to 15 pounds of clay, which typically make up part of the ash in the coal, can blind the filter in no more than 6 to 10 cycles. To defeat this tendency, the new centrifuges keep the clay in suspension while the load is forming so that it is the last to settle out. After the formation of the load is completed, the wiper blade, which is really a squeegee, removes most of this clay and sends it out of the mouth of the bowl. To illustrate this action, Figure 28 shows a load of coal before wiping with a layer of clay of 0.045 inch thickness on the surface of the coal. Figure 29 shows the load of coal with a portion of the clay peeled away, thus, exposing the coal.

The original wiper blades were made of rubber belting. This was later replaced with plastic. Finally the wiper blade was constructed of 0.125 inch thick steel. The steel wiper solves the wear problem and thus can be used on the production centrifuges without having the wiping edge become rounded and ineffective.

When the layer of clay (as shown in Figure 28) has formed, but just before it is wiped away, there is a layer of water trapped on the surface of the clay. This layer may be as much as 0.500 inch thick and weigh more than 35 pounds. This 35 pounds of water, if not removed otherwise, must travel through the coal being dried and exit the bowl through the filter. This will both slow the process and substantially raise the final moisture level in the coal. To prevent this, a feature designated a "wiper scoop" was designed and added to the wiper system so that this water could be rapidly ejected from the mouth of the bowl. The clay material is also ejected in the process. A diverter can then separate the clay laden slurry from the remainder of the overflow and send the waste to the static thickener.

The complete filling and wiping system is shown in Figures 30 and 31. In Figure 30, the wiper blade is on the near side. In Figure 31, the nozzles can be seen on the near side with the wiper scoop to the right of the nozzles. When the wiper scoop was first built, it was prone to plugging and stoppages. This condition was corrected by making the wiper scoop open sided so that it is automatically washed out during each cycle.

The result of these improvements were consistently good wipes with low moistures on the surface of the load. Whereas the surface moistures near the inner surface of the loads, prior to the improvements described above, were at about 13%, they averaged under 9% afterward.

FIGURE 28

FRESHLY FORMED FOLD, TOP OF CLAY LAYER
FILLED WITH SAND, 100% OF CLAY LAYER

FIGURE 29

FRESHLY FORMED FOLD, TOP OF CLAY LAYER
FILLED WITH SAND, 100% OF CLAY LAYER

FILLING & WIPING SYSTEM FRONT

Figure 30

FILL AND WIPE SYSTEM AND SCOOP

Figure 31

For the wiping process to be fully effective, the dryer bowl must remain level. The bowl leveling system supplied with the machine, was not fully effective and thus there were geometric errors between the wiper blade and the load of coal. To correct this problem a new bowl level transducer was installed. The new LVDT (linear variable differential transformer) which supplies the signal to the computer to enable it to maintain the bowl in a level mode, was successful in holding the bowl to an accurate condition of leveling regardless of the weight of coal in the bowl at the time. This change was responsible for improving the filling and wiping performance. The LVDT and its mounting hardware are shown in Figure 32.

Tests were run in order to improve the configuration of the filling nozzles. The nozzles used prior to this test work, were 1.25-inch schedule 40 steel pipe with no modifications. These nozzles were cylindrical and 1.48 sq. in. in cross section. Because of the importance of agitating the slurry during load formation, tests were conducted with flattened nozzles which produce a fan like pattern of higher velocity. The tests indicated improvements in performance with this change. The new flattened configuration yielded better results with lower moistures near the surface of the load. Figure 33 shows the nozzles flattened to 7/8 inch inside.

Another innovation which has proven to be successful is the stir-fill system. It was added in the further interest of keeping the clays in suspension during load formation. This new method involves the lowering of the nozzles during the initial part of the filling segment of the cycle. It has improved the quality of the load forming and wiping operations. Figure 34 shows program screen 16 of the centrifuge control computer. The operations controlled from screen 16 allow the operator to change the load level goal and to use or not use the stir fill function. In each case the operator can modulate the correction factors which the computer will use to make automatic corrections and bring the machine into continually corrected levels for each parameter.

Because of these improvements, as well as the steel wiper, the scoop and an improved wiper pressure control, the weights of the dried coal loads increased significantly. During the late spring of 1990 loads of 650 pounds were considered to be excellent. After the completion of the work described above, the loads averaged 765 pounds with some loads recorded at above 800 pounds. To put these changes in perspective, 8 tph productivity requires a 146 second cycle with 650 pound loads. With 765 pound loads, a 169 second cycle will achieve the 8 tph productivity which was the original goal for Prototype 2.

Tests of Feed Rate & Mode vs Surface Moisture - Subtask 4.4

Tests were run to determine the relationship between the feed rate of the slurry into the bowl and the final surface moisture. Because of the high viscosity of the slurry and the air entrapped in the slurry, it was difficult to pump. It was found that without a full head of slurry in the main holding tank which supplies the feed pump, the nozzle pressure would be lower. This condition resulted in lighter and erratic load weights with unsatisfactory final product weights and with higher moistures.

LVDT BOWL LEVELING SYSTEM

Figure 32

FLATTENED NOZZLE CONFIGURATION

Figure 33

To reduce this effect, the slurry level in the main tank was raised. A special diaphragm gauge was then installed in the feed tube so that desirable pressures could be established. The filling system could maintain 5 psi with some coals, but, with certain other coals, no more than 3 psi could be sustained. In a commercial installation, this would not be a problem since the holding tank could be placed one story above the centrifuge so that another 5 psi of reserve pressure would be available. Test personnel suspect that higher nozzle pressure than the system could achieve would have improved performance.

Tests of Modulation of Feed Rate vs Ash Reduction - Subtask 4.5

The objective of these tests was to investigate the possibility that an ideal level of feed flow might enhance the ability of the centrifuge to reduce the ash content of the product. Here again, higher slurry feed rates during filling, produced better results, but because of the inadequate pressure potential of the feed system, no clear cut correlation between the feed rate and the reduction of ash in the product was established during the project. However, the test team formed the opinion that when the centrifuge's independent variables were properly balanced, there were reductions in the product ash on those cycles when nozzle pressures were at 5 psi. During the project, the ash content of the centrifuge product averaged 1.0% to 1.5% less than that of the centrifuge feed from the host plant.

Tests of Cutter Configuration vs Cutting Rate - Subtask 4.6

The objective of these tests was to improve the cutter system components in order to obtain the most reliable and fastest possible removal of the dried coal from the bowl.

In order for the centrifuge to be a commercial success, the cutter system must remove dry coal at a rate of 25 pounds per second. While the construction, configuration and materials used in the cutter system are important, the condition of the coal to be cut out is also of critical importance. It was found that when the wipe is of poor quality, a layer of water of up to 0.5 inches thickness supported by an impervious layer of clay of the order of 0.040 inch thickness will be left on the inner surface of the coal after the spin dry portion of the cycle, as shown in Figure 28. This surface clay was identified as the principal cause of plugging in the cutter screw experienced in early testing. The clay is capable of causing the cutter to clog and to become dysfunctional. The tests of nozzle configuration vs. surface moisture described above, contributed greatly to the improved operation of the cutter system.

When the cutter unit which was used during the project was under construction, both the body and the screw were sand blasted by mistake. The resulting rough surfaces created plugging problems which had to be addressed. The roughness on both the high-speed screw (which operates at 665 RPM), and the inside of the cutter body, contributed to plugging when the cutter was operated. A ceramic/epoxy paint-on liner was applied to the inside of the cutter body to reduce plugging. This measure cured the problem of coal sticking to the body. However the ceramic/epoxy coated screw was only satisfactory for a short period before the coating became roughened.

A discussion of the critically important cutter screw surface with several knowledgeable sources revealed that a polished stainless steel screw of heavy construction might continue to polish during its service with minimal clogging

and wear. A polished stainless steel conveyor screw was installed and tested in the cutter system. This new screw is shown in Figure 35. It was installed on November 1, 1991 and the reliability, even with very moist, high ash coals, was nearly 100% thereafter. Careful inspections revealed that the stainless steel screw face continued to polish and that there was no tendency for the screw surface to gall and become rough.

It was considered important to identify and test an inexpensive cutter blade for the dryer. Early tests indicated that rapid wear would be a problem with any steel blades used. Calcium carbide tipped blades would probably serve well, but they were found to be very expensive.

Early in the project, ceramic blades were procured and tested with encouraging results. The original ceramic blades, which were in use throughout most of the testing in this project, served well. However, these sharply pointed ceramic blades did not prove to be sufficiently durable as the sharp points on the tips of these blades were prone to chipping. A discussion of the problem with the ceramics manufacturer's representative revealed a design which he felt would likely solve the problem. The improved design had radiused points and valleys instead of the sharp points and valleys used previously. Since the straight sides of the original blades exhibited excellent wear characteristics, it seemed logical to assume that the new blades with no delicate points to chip off, would be satisfactory. A set of the new blades was designed, ordered and installed.

When tested, the new ceramic cutter blades with rounded teeth exhibited excellent wear characteristics. The rounded teeth showed minimal signs of chipping, and the cutting operation was relatively free of the vibration patterns which had been prevalent before. Tests of the new ceramic cutter with the rounded points included numerous cuts of 650 pound loads in less than 30 seconds. The improved cutter was shown to be capable of cutting a 650 pound load of dried coal in as little as 22 sec. (29.5 pounds per second). At this rate a 750 pound load could be cut out in 25.4 seconds.

Studies of the cutter system indicated that a cutter blade with a profile matching the inside profile of the bowl with its system of filtrate biasing cones would allow the removal of 55 pounds of additional product per cycle. This would raise the present level of 765 pounds per cycle to 820 pounds per cycle. The indicated productivity increase would be 7.2% - a significant improvement. This concept is reported as an important matter for productivity improvement but since the goals of the project had already been met, it was not considered to be within the scope of work to investigate this concept further.

POLISHED SS CUTTER SCREW

Figure 35

RECOVERY SYSTEM

Since any significant difference in the total system product recovery for centrifugal dryer systems relative to thermal dryer systems, would influence the operating cost comparison, and since the centrifugal dryer must decant as well as filter out the water to be removed, the decanted coal fines must be recycled and recovered. The decanting process classifies the coal dried in the centrifuge and its recovery rate of the coarse fractions is higher than for the finer fractions. For this reason, there is an initial build up of fines in the centrifuge system during the first few loops of the overflow through the recovery process and back to the centrifuges.

During the few seconds (about 7 seconds) while the wiping process occurs, more than 7 pounds of clay (and other ash) will normally collect on the inner surface of the load. As a part of the centrifuge recovery system, when the clay and ash is wiped off, a diverter will send the clay and ash bearing portion of the overflow slurry to the thickener. The circuit for integrating the centrifuges into a process plant, which includes the recovery circuits, is shown in Figure 36.

A computer program which models the recycling of the decanted slurry and which takes into account the diversion of the wipe solids, was used to determine the effect of the buildup of fines in the system. It was found that coal of the size consist of the West Virginia sample with only 25.7% of the 28 mesh x 0 fraction at minus 325 mesh, produced a negligible buildup of fines after stabilization. The coal from the host plant with 37.5% of the 28 mesh x 0 coal at minus 325 mesh, did cause a significant build-up of the minus 325 mesh coal to 50.8% after stabilization. This resulted in a stabilized centrifuge coal feed size consist about the same as the Southern Illinois feed coal with which less than 10% surface moistures were obtained. In both cases, the overflow could be returned to the mixer for recycling with a recovery rate of over 98%. It would be advisable to use the Load Depth Control Dam to slightly lower the load depth when drying coal with a feed of more than 35.0% minus 325 mesh.

Since the diverter will be controlled and timed by the computer, the amount of overflow diverted during each cycle can be easily modulated. Figure 37 shows a printout of the computer recovery program when coal with 37.5% minus 325 mesh is being dried. Execution of the program involves 198 individual calculations. Because of cumulative errors from rounding, the final total of the percentages of the size fractions studied, may not add up to 100%. The recovery in the centrifuge system will produce an almost exact match with the recovery of a fluidized bed thermal dryer system. Sending a portion of the dryer overflow through the optional 3 inch Krebs cyclones, as shown in Figure 36, with their underflows returning to the mixer and the remainder of the centrifuge overflow reporting directly to the mixer, can contribute to both the performance of the centrifuge and the further beneficiation of the coal fines while they are being dried. However, this arrangement would not be advantageous unless additional beneficiation is needed. With the above considered, no account is taken in the economics studies presented later in this report, for difference in product loss between the centrifuges and the thermal dryer systems.

INSTALLATION OF CTC HIGH GRAVITY CENTRIFUGE
IN A COAL PREPARATION PLANT WITH OPTIONAL WIPE DIVERTER
AND CYCLONES FOR ADDITIONAL BENEFICIATION

Figure 36

RECOVERY SYSTEM COMPUTER LOOPS

flostcy7 FLOW DIAGRAM & RECOVERY, WITH WIPE GATE

```
% cent. recov., solids +200 = .94
% cent. recov., solids 200 x 325 = .79
% cent. recov., solids 325 x 500 = .62
% cent. recov., solids -500 = .42
% overflow recov., solids, +200 = 1
% overflow recov., solids, 200 x 325 = .995
% overflow recov., solids, 325 x 500 = .985
% overflow recov., solids, -500 = .96
+ 200 from flotation, solids, #/min = 210.87
200 x 325 from flotation, solids, #/min = 23
325 x 500 from flotation, #/min = 53.68
-500 from flotation, solids, #/min = 80.51
total flow from flotation, solids, #/min = 368.06
```

* * FIRST AND SIXTH LOOPS * *

```
cent. fd., solids, +200, #/min = 210.87
cent. fd., solids, 200 x 325, #/min = 23
cent. fd., solids, 325 x 500, #/min = 53.68
cent. fd., solids, -500, #/min = 80.51
total cent. fd., solids, #/min = 368.06

prod., solids, +200, #/min = 198.2178
prod., solids, 200 x 325, #/min = 18.17
prod., solids, 325 x 500, #/min = 33.2816
prod., solids, -500, #/min = 33.8142
total prod., solids, #/min = 283.4836

cent. OF & filt., solids, +200, BDC #/min = 12.65221
cent. OF & filt., solids, 200 x 325, BDC #/min = 4.83
cent. OF & filt., solids, 325 x 500, BDC #/min = 20.3984
cent. OF & filt., solids, -500, BDC #/min = 46.6958
total cent. OF & filt., solids, #/min = 84.57641

=====
% of 325 x 500 solids in cent. FD = 14.58458
% of -500 solids in cent. FD = 21.87415
% of 325 x 500 solids in cent. prod. = 11.74022
% of -500 solids in cent. prod. = 11.9281
```

OVERALL SOLIDS RECOVERY OF SYSTEM, % = 77.02103

Overall solids loss of system, % of 325 x 500 = 38
Overall solids loss of system, % of 500 x 0 = 58

```
=====
cent. fd., solids, +200, #/min = 224.3298
cent. fd., solids, 200 x 325, #/min = 29.07286
cent. fd., solids, 325 x 500, #/min = 85.556
cent. fd., solids, -500, #/min = 176.243
total cent. fd., solids, #/min = 515.2017

prod., solids, +200, #/min = 210.87
prod., solids, 200 x 325, #/min = 22.96756
prod., solids, 325 x 500, #/min = 53.04472
prod., solids, -500, #/min = 74.02207
total prod., solids, #/min = 360.9043

cent. OF & filt., solids, +200, BDC #/min = 13.45979
cent. OF & filt., solids, 200 x 325, BDC #/min = 6.105301
cent. OF & filt., solids, 325 x 500, BDC #/min = 32.51128
cent. OF & filt., solids, -500, BDC #/min = 102.221
total cent. OF & filt., solids, #/min = 154.2974

=====
% of 325 x 500 solids in cent. FD = 16.60631
% of -500 solids in cent. FD = 34.20855
% of 325 x 500 solids in cent. prod. = 14.69772
% of -500 solids in cent. prod. = 20.51017
```

OVERALL SOLIDS RECOVERY OF SYSTEM, % = 98.05584

Overall solids loss of system, % of 325 x 500 = 1.183459
Overall solids loss of system, % of 500 x 0 = 8.05854

Figure 37

Projection of Productivity and Operating Cost Subtask 5.1

The productivity goal for the project was defined as 8 tons per hour of froth product dried to the order of 10% surface moisture. The support systems which mix the slurry, deliver it to the dryer, weigh it and then remove the dried coal, are inadequate for continuous production at 8 TPH. In particular, it is not possible to hand sample the dried coal accurately at five different levels of the cut at a cutting rate of 25 pounds per second. A practical cutting rate while sampling is 13.5 pounds per second. In addition, the outfeed conveyor which carries the dried product to the clean coal belt of the host plant, can only accommodate cutting at about 18 pounds per second. In spite of these limitations, every portion of the 8 ton per hour cycle has been demonstrated and shown to be feasible.

It was assumed at the beginning of the project that 650 pound batches would be produced every 146 seconds in order to achieve the 8 TPH productivity goal. During the project, it became apparent that the 146 second cycle was an impractical goal for Prototype 2. Fortunately, the batch weight goal turned out to be conservative. During the last three quarters of the testing, loads of 765 pounds were the norm. Loads of more than 800 pounds were dried on a number of occasions. Batches of 765 pounds will require cycle times of 169 seconds for 8 TPH production. This is a practical figure. The following is a composite cycle built on well proven cycle time segments from the project:

Cycle Segment Speeds & Times for 8 TPH Production-Prototype 2

<u>function</u>	<u>Bowl Speed*</u>	<u>Time Used</u>	<u>Cum. Time</u>
Change-Out	2,100 RPM	15 sec.	15 sec.
Fill	2,000	30	45
Wipe	1,800	5	50
Accelerate	2,900	11	61
Dwell	2,900	50	111
Decelerate	200	28	139
Cut	200	30	169

* At end of function

Loads as high as 815 pounds have been dried during the testing, however, the mean load weight for tests was 765 pounds after the principal system independent variables were brought into satisfactory relationships with one another. Productivity for Prototype 2 at the conclusion of the project and with a 169 second cycle would be 21.3 cycles per hour of 765 pounds per cycle. This would total 16,295 pounds per hour (8.15 TPH).

While these demonstrated cycle function times and load weights for Prototype 2 met the project goals, comments were received from a number of senior operations personnel in major coal companies that 12 TPH productivity would make the centrifuge system more attractive to them. This goal became practical when it was found that the ultimate strength of the carbon fiber from which the bowl is made has been increased in strength from the original 290,000 psi as used in Prototype 2, to 550,000 psi, by advancements in the fiber production industry. The Prototype 2 Centrifuge which was used in the project used a "hand laid-up" bowl because for experimental work this construction method is more flexible and faster. The pre-production Prototype 3 will include a bowl constructed by the continuous filament winding process. This method in addition to producing a stronger bowl, results in lower production costs in finished products. With these facts in view, studies with complete design calculations were made of a production centrifuge with 12 TPH productivity. The 50% increase in productivity (over Prototype 2) would involve an estimated capital cost increase of 15 to 18%. It was determined when new design calculations were executed, that the specification changes shown below, would result in meeting the new 12 TPH design goal. With full depth loads of coal of no more than 35% minus 325 mesh, it would achieve up to 13.33 TPH of coal at 12% total moisture.

<u>Item</u>	<u>Prototype 2</u>	<u>Prototype 3*</u>
Bowl Diameter, Inside	36 in.	44.5 in.
Bowl Length, Inside	36 in.	46.5 in.
Load Weights	762#	1,333 pounds
Maximum Operating Speed	2,900 RPM	2,600 RPM
Maximum Operating Gravity	4,302	4,274
WK ² of Bowl, Coal, and Shaft in Pound Ft ²	4,037	8,822
Main Drive Power**	300 HP	500 HP
Main Drive Average Power	60 HP	80 HP
Productivity	8.15 TPH	13.33 TPH

* The recommended commercial design of the centrifugal dryer will hereafter be referred to as Prototype 3

** With 50% short term overload capability

Prototype 3 is projected to be able to dry 12 TPH (solids) of 28 mesh x 0 coal of 35% minus 325 mesh to 10 % surface moisture. When coal of 28 mesh x 0 but with 25% minus 325 mesh, is dried, the surface moisture is projected to be 7.5% and some increase in productivity can be expected. The final surface moisture is affected primarily by the percentage of minus 325 mesh coal in the coal size consist.

A new feature will be added to Prototype 3. This feature will be referred to as the Load Depth Control Dam. This feature will hereafter be referred to as the LDCD. It will be vital for the drying of very fine coals such as the samples from Pennsylvania and Southern Illinois sources in the Various Coal Tests.

It was found during the project that the finer the coal, the more difficult it was to build full depth loads of 6.87 inches cutting depth. When the original Prototype 1 was tested in Birmingham, Alabama (with its 28.5 in. diameter bowl) there was evidence that the shallower loads of about 3.75 inches depth, were much easier to form and to process even when very fine coals were dried. During the testing of the various coal test samples from Pennsylvania and Southern Illinois, it was observed that it was difficult to load the bowl to the full depth. It was the opinion of the test personnel that a larger hole in the bowl would have made it easier to produce well formed loads which would dry well.

The LDCD system will include increasing the diameter of the hole in the open end of the bowl by approximately 4 in. Then dam rings will be custom designed to maintain the ideal load depth for any particular coal. This means that the maximum cutting depth can be reduced by as much as 2 in. The results of this change, as applied to Prototype 2, are predicted to be:

<u>Item</u>	<u>With Dam</u>	<u>Without Dam</u>
Inside Diameter of Hole	19.5 in. min.	23.5 in., max.
Pressure On Outer Layer of Coal	633.5 psi	420.8 psi
Bulk Density of Outer Layer	0.0427 #/in ³	0.0415 #/in ³
Volume of Voids in Coal	11.1%	12.5%

The significantly larger voids in the coal would allow quicker and more efficient filtration and the shallower loads could be formed faster and more easily with finer coals. From these projections, the prospects for drying coal of 100% minus 100 mesh with more than 50% minus 325 mesh in Prototype 3 seem to be good. There will be several advantages in using the LDCD. Among these will be faster loading, shorter dwell times, shorter cutting times and lower moistures. However, the trade-off will be that the load weights will diminish as the hole diameter increases. The estimated magnitude of reduction in load weights along with corresponding changes in other dependent variables for 3 different inside diameters of the hole in the open end of the bowl, are shown below:

<u>LDCD HEIGHT</u>	<u>Load Weight</u>	<u>Productivity</u>	<u>WK² of Load</u>
2 in.	1,333 pounds	100% 13.3 TPH	3,457 #Ft ²
1	1,187	89 11.9	2,791
0	1,028	77 10.2	2,545

PRICE PROJECTION OF CENTRIFUGAL DRYER FOR
28 MESH X 0 FROTH PRODUCT WITH PRODUCTIVITY OF
12 TONS/HOUR OF SOLIDS OF 35% MINUS 325 MESH

(CNTPRC04)

Bowl, 44.5" ID x 46.5" long, 1,200# @ \$35.00/#	\$42,000
After a tooling cost of \$80,000 to \$100,000 which is included in the pro-forma	
Drive and Control Systems:	
Variable AC Inverter	55,650
Motor	21,550
Control Computer, etc.	<u>27,830</u>
	105,030
	105,030
Bearing Sleeve, 696 pounds @ \$12.50/pound	8,700
Shaft and Hub, 829 pounds @ \$13.90/pound	11,523
Main Bearings	1,500
Gimbal	1,800
Main Frame, 11,090 pounds @ \$3.25/pound	32,793
Suspension	11,590
Feeder/Cutter/Robotics System	46,000
Hydraulics Unit	11,500
Slurry Loop	18,500
Assembly & Test, 25,143 pounds @ \$1.10/ pound	27,645
Misc.	<u>20,000</u>
	\$338,581
Margin @ 30% of Invoice Price	161,229
Royalty @ 7% of Invoice Price	<u>37,620</u>
	\$537,430

INSTALLATION COSTS (PER CENTRIFUGE)

Purchased Equipment:

Centrifuge feed pump	\$15,000
Diverting valves	5,000
Lightning mixer, tank & belt	14,500
Low yield atomic density gauge	5,000
Effluent pumps	9,000

Process Plate Work:

Mild steel sumps	11,300
Mild steel chutes	5,400
Stainless steel liners	1,700

Instrumentation	25,000
Electrical	18,125
Piping	45,000
Fire protection	5,500
Structural steel	46,500
Architectural components	5,300
Foundations, including installation	27,000
Erection, mech., struct., elect., arch.	162,674
Engineering	53,688
Miscellaneous	20,000
Freight	8,000

TOTAL INSTALLATION COST

\$483,687

Cost of one centrifuge	\$537,430
Installation cost/centrifuge	483,687
INSTALLED COST PER CENTRIFUGE	\$1,021,117

Economic Models of Centrifuge Installations

The principal competition for the new centrifugal dryers is the fluidized bed thermal dryer. For a fluidized bed thermal dryer to function efficiently without fires and other malfunctions, a quantity of coarse coal must be included in the feed along with the 28 mesh x 0 froth product. But the thermal dryer would not be needed except for the problem of drying the 28 mesh x 0 coal. It is accepted in the industry that about 3 parts of coal coarser than 28 mesh must be fed along with each one part of 28 mesh x 0 coal for satisfactory thermal dryer operation. Therefore, two plants will be studied. In each case, coal streams of typical thermal dryer feed size consists will be used for a complete centrifuge system and a complete thermal dryer system.

The first plant modeled, will be a hypothetical plant similar to the host plant. The coal size consist is similar to that of the host plant. The 28 mesh x 0 coal at this plant averages 37.5% minus 325 mesh. About 2% of the centrifuge overflow will be diverted to the thickener. The overall system recovery will be at 98%. The second model will be designed for one of the coal processing plants from which the coal samples used in the various coal tests were drawn. The 28 mesh x 0 coal from this plant contained 20.66% minus 325 mesh and so the total overflow from the centrifuges can be returned directly to the disk filters for recycling. System recovery is over 99.0%.

No attempt will be made here to precisely quantify the savings resulting from the lower permitting costs of the centrifuge system. However, representatives of the Virginia Air Quality Control Authority, to whom the EPA has delegated responsibility for air quality control in Virginia, has reviewed the centrifuge system and they anticipate a simple permitting procedure requiring a maximum of 3 months duration for the centrifugal dryers. The permitting costs of a centrifuge system are minor because there are no discharges except for the clay and ash laden portions of the wipe slurry diverted to the thickener. The permitting of thermal dryers can entail significant delays and expense.

There are also possible savings from the total lack of any ongoing environmental problems in the centrifuge system. No attempt will be made to quantify this possible but difficult to account for savings. Since there is minimal wear on the principal parts of the centrifuge, and, since the carbon fiber in the bowl has an almost infinite fatigue life, the centrifuge is expected to have a long service life, another possible savings.

The two systems modeled below are shown in schematic in Figure 36. Centrifuges are estimated to cost \$537,430 each. The installation cost of each centrifuge is estimated at \$483,687. In both cases, engineering estimates of components have been added to estimated fabrication and assembly costs to arrive at the totals. Capital costs are given straight line amortization and depreciation to zero in equal time periods.

The total cost per dried ton for the 108 TPH centrifuge system is only 9.6% higher than that of the 703 centrifuge TPH system. The thermal dryer system cost per dried ton is 31.9% higher than the that of the 703 centrifuge TPH system. This may enable the centrifugal dryer systems to become practical for coal preparation plants which are too small for thermal dryer installations to be economically feasible.

COMPARATIVE COSTS OF SMALL HYPOTHETICAL DRYERS FOR
FOR 108 TPH SOLIDS WITH 84 TPH 3/4 X 28 AND 24 TPH 28 X 0
CTC CENTRIFUGE SYSTEM VS FLUIDIZED BED THERMAL DRYER

(CSTCMP21)

BASIS

The feed solids to both systems will be assumed to be identical at 28 TPH of 3/4 in. x 5/16 coal, 56 TPH of 5/16 x 28 mesh and 24 TPH of 28 mesh x 0 coal with 37.59% minus 325 mesh. The coal is at 10.0% ash. The 3/4 in. x 5/16 coal is assumed to be at 3.5 % moisture and the 5/16 x 28 mesh coal is assumed to be at 6.5% moisture upon exiting the coarse coal centrifuges. The 28 mesh x 0 coal in both systems is assumed to be received from the disk filters at 25% moisture. Slurry to the CTC Centrifuges will be received from the disk filters and remixed with special Lightning mixers similar to the one serving the prototype centrifuge. Overflow from the centrifuges (except for the high-clay wipe suspension) will report to the Lightning mixer for recycling. Total centrifuge system recovery of the 3/4 in. x 0 coal stream is 98.0%. Both systems will be assumed to operate for 3,720 hours per year. Both systems will be amortized and depreciated (SL to 0) in 10 years. Interest will be at 10%. Labor and maintenance expense for both systems will, for this study, be assumed to be equal.

Total Installed Capital Cost Of Centrifuge System

2 ea. CTC Centrifuges @ \$1,021,117	\$2,042,234
Disk Filters	600,000
Coarse Coal Centrifuges	125,000
Permitting and Start-up Costs @ 5%	<u>138,362</u>
TOTAL INSTALLED COST OF CTC SYSTEM	\$2,905,596

Capital Cost Of Thermal Dryer System

Installed Cost of Thermal Dryer	\$2,800,000
Installed Cost of Disk Filters	600,000
Installed Cost, Coarse Coal Centrifuges	125,000
Permitting and Start-up Costs @ 7.5%	<u>264,375</u>
TOTAL INSTALLED COST OF THERMAL DRYER	\$3,789,375

Average Hourly Costs Of Capital

CENTRIFUGE SYSTEM

\$2,905,596 @ 10.0% for 10 yrs
@ 3,720 hrs/yr = \$123.86/hour

THERMAL DRYER SYSTEM

\$3,789,375 @ 10.0% for 10 yrs
@ 3,720 hrs/yr = \$161.54/hour

HOURLY COSTS OF ENERGY & MISC

CENTRIFUGE

2 Main Drives @ 82 HP	164 HP
Hydraulics	65
Air Compressor	25
Pumps	65
Coarse Coal Centrifuges	120
Disk Filters	500
Lightning Mixer & Feed	30
Dry Product Conveyors	15
	<u>984 HP</u>

984 hp x .746 @ \$0.055 = \$40.37/hour

THERMAL DRYER

Therm. Dryer	1,250 HP x .746 @ \$0.055 -	\$51.29
Disk Filters	500 HP x .746 @ \$0.055 -	20.52
Coarse Coal Cent.	120 HP x .746 @ \$0.055 -	4.92
Coal	1.5 TPH @ \$25.00/ton -	37.50
Soda Ash for Dryer Desulphurization		4.69
Fuel Oil	7.5 gal/hour @ \$1.00 -	<u>7.50</u>
		\$126.42/HR

COMPARATIVE TOTAL HOURLY COST FOR FIRST 10 YEARS

	<u>Centrifuge</u>	<u>Thermal Dryer</u>
Average Cost of Capital	\$123.86	\$161.54
Energy & Misc.	40.37	126.42
Labor	20.00	20.00
Maintenance	<u>50.00</u>	<u>50.00</u>
TOTAL COST	\$234.23	\$357.96
Cost/Dried Ton	\$2.17	\$3.31
Cost For Ten Years	\$8,718,192	\$13,298,256

COMPARATIVE TOTAL HOURLY COSTS AFTER 10 YEARS

	<u>Centrifuge</u>	<u>Thermal Dryer</u>
Energy	\$40.37	\$126.42
Labor	20.00	20.00
Maintenance	<u>50.00</u>	<u>50.00</u>
TOTAL COST	\$110.37	\$196.42
Cost/Dried Ton	\$1.02	\$1.82
Cost For One Year	\$409,795	\$731,203

CAPITAL COST DIFFERENTIAL

	<u>Project Costs</u>	<u>Operating Cost/Year</u>
Centrifuge System	\$2,905,596	\$409,795
Thermal Dryer System	<u>3,789,375</u>	<u>731,203</u>
Realization	\$883,779	\$321,408

PROJECTED OVERALL PRODUCT SURFACE MOISTURE WITH CENTRIFUGE SYSTEM

<u>Size</u>	<u>Proportion & SM</u>	
3/4" x 5/16"	26% @ 3.5%	.26 x .035=.0091
5/16" x 28 mesh	52% @ 6.5%	.52 x .065=.0338
28 mesh x 0	22% @ 10.5%	.22 x .105=.0231
		.0660
Resultant product surface moisture = 6.60%		

PERMITTING COSTS and OTHER CONSIDERATIONS

Representatives of the Virginia Air Quality Control Authority to whom the EPA has delegated responsibility for air quality control in Virginia, have reviewed the centrifuge system and they anticipate a simple permitting procedure requiring a maximum of 3 months duration for the centrifugal dryers. The permitting costs of a centrifuge system are minor because a small stream of high-ash coal slurry from the wipe process (reporting to the thickener) is the only waste from the centrifuge. The process of permitting a thermal dryer can cause significant delays in a project with the attendant project expense.

There are also possible savings from the total lack of any environmental problems during the operation of the centrifuge system. No attempt will be made to quantify this possible, but difficult to account for savings.

Since there is minimal wear on the principal parts of the centrifuge and since the carbon fiber in the bowl, has an almost infinite fatigue life, the centrifuge is expected to have a long service life.

COMPARATIVE COSTS OF LARGE HYPOTHETICAL DRYERS FOR
703 TPH SOLIDS WITH 548 TPH 5/16 X 28 AND 155 TPH 28 X 0
CTC CENTRIFUGE SYSTEM VS FLUIDIZED BED THERMAL DRYER

(CSTCMP22)

BASIS

The feed to both systems will be assumed to be identical at 548 TPH of 5/16 in. x 28 mesh coal and 155 TPH of 28 mesh x 0 coal with 20.66% minus 325 mesh. The coal is at 8.22% ash. The 5/16 in. x 28 mesh coal is assumed to be at 6.25 % moisture upon exiting the coarse coal centrifuges. The 28 mesh x 0 coal in both systems is assumed to be received from the disk filters at 25% moisture. Slurry to the CTC Centrifuges will be received from the disk filters and remixed with special Lightning mixers similar to the one serving the prototype centrifuge. Overflow from the centrifuges (except for the high-clay wipe suspension) will report to the Lightning mixer for recycling. Total centrifuge system recovery of the 3/4 in. x 0 coal stream is 98 1/2%.

Both systems will be assumed to operate for 3,720 hours per year. Both systems will be amortized and depreciated (SL to 0) in 10 years. Interest will be at 10%. Labor and maintenance expense for both systems will, for this study, be assumed to be equal.

Total Installed Capital Cost Of Centrifuge System

13 ea. CTC Centrifuges @ \$1,021,117	\$13,274,521
Disk Filters	3,140,000
Coarse Coal Centrifuges	848,000
Permitting and Start-up Costs @ 5%	863,126
TOTAL INSTALLED COST OF CTC SYSTEM	\$18,125,647

Total Installed Capital Cost Of Thermal Dryer System

Installed Cost of Thermal Dryer	\$11,000,000
Installed Cost of Disk Filters	3,140,000
Installed Cost, Coarse Coal Centrifuges	848,000
Permitting and Start-up Costs @ 7.5%	1,124,100
TOTAL INSTALLED COST OF THERMAL DRYER	\$16,112,100

Average Hourly Costs Of Capital

CENTRIFUGE SYSTEM

\$18,125,647 @ 10.0% for 10 yrs
@ 3,720 hrs/yr = \$722.68/hour

THERMAL DRYER SYSTEM

\$16,112,100 @ 10.0% for 10 yrs
@ 3,720 hrs/yr = \$686.85/hour

HOURLY COSTS OF ENERGY & MISC

CENTRIFUGE

13 Main Drives @ 82 HP	1,066 HP
Hydraulics	447
Air Compressor	163
Pumps	660
Coarse Coal Centrifuges	488
Disk Filters	2,030
Lightning Mixer & Feed	211
Dry Product Conveyors	81
	<u>5,146 HP</u>

5,146 hp x .746 @ \$0.055 = \$211.14/hour

THERMAL DRYER

Therm. Dryer	5,500 HP x .746 @ \$0.055 =	\$225.67
Disk Filters	2,030 HP x .746 @ \$0.055 =	83.29
Coarse Coal Cent.	488 HP x .746 @ \$0.055 =	20.02
Coal	8.5 TPH @ \$25.00/ton =	212.50
Soda Ash for Dryer Desulphurization		30.47
Fuel Oil	49 gal/hour @ \$1.00 =	<u>49.00</u>
		\$620.95/hour

COMPARATIVE TOTAL HOURLY COSTS FOR FIRST 10 YEARS

	<u>Centrifuge</u>	<u>Thermal Dryer</u>
Average Costs of Capital	\$722.68	\$686.85
Energy & Misc.	211.14	620.95
Labor	130.00	130.00
Maintenance	<u>325.00</u>	<u>325.00</u>
TOTAL COST	\$1,388.82	\$1,762.80
Cost/Dried Ton	\$1.98	\$2.51
Cost For Ten Years	\$51,780,168	\$65,640,516

COMPARATIVE TOTAL HOURLY COSTS AFTER 10 YEARS

	<u>Centrifuge</u>	<u>Thermal Dryer</u>
Energy	\$211.14	\$620.95
Labor	130.00	130.00
Maintenance	<u>325.00</u>	<u>325.00</u>
TOTAL COST	\$665.14	\$1,075.95
Cost/Dried Ton	\$0.95	\$1.53
Costs For One Year	\$2,484,402	\$4,001,195

JUSTIFICATION OF CENTRIFUGE CAPITAL COST DIFFERENTIAL

	<u>Capital Cost</u>	<u>Operating Cost/Year</u>
Centrifuge System	\$18,125,647	\$2,484,402
Thermal Dryer System	<u>16,112,100</u>	<u>4,001,195</u>
Difference	\$ 2,013,547	\$1,516,793

Return on Investment Differential:

$$1,516,793/2,013,547 = 75\%$$

The time required to recover the differential on the investment of capital is 1.33 years.

PROJECTED OVERALL PRODUCT SURFACE MOISTURE WITH CENTRIFUGE SYSTEM

<u>Size</u>	<u>Proportion & SM</u>	
5/16" x 28 mesh	78% @ 6.25%	.78 x .0625 = .0488
28 mesh x 0	22% @ 7.5%	.22 x .0750 = .0165
		.0653

Resultant product surface moisture = 6.53%

PERMITTING COSTS and OTHER CONSIDERATIONS

Representatives of the Virginia Air Quality Control Authority to whom the EPA has delegated responsibility for air quality control in Virginia, have reviewed the centrifuge system and they anticipate a simple permitting procedure requiring a maximum of 3 months duration for the centrifugal dryers. The permitting costs of a centrifuge system are minor because a small stream of thin, high-ash slurry from the wipe process (reporting to the thickener) is the only waste from the centrifuge. The process of permitting a thermal dryer can cause significant delays in a project with the attendant project expense.

There are also possible savings from the total lack of any environmental problems during the operation of the centrifuge system. No attempt will be made to quantify this possible, but difficult to account for savings.

Since there is minimal wear on the principal parts of the centrifuge and since the carbon fiber in the bowl, has an almost infinite fatigue life, the centrifuge is expected to have a long service life.

CONCLUSIONS

1. All of the performance objectives of the centrifuge were demonstrated during the project and the economic projections shown above indicate attractive costs. The general conclusion is therefore drawn that the new high-gravity, high-production, batch-type centrifuge is a technically and economically feasible alternative to the fluidized bed thermal dryer.

2. It is concluded that for large dryer installations, the capital cost of a complete centrifuge system will be no more than 12.5% higher than that of a complete fluidized bed thermal dryer system for drying identical coal streams. It is concluded that for small installations, the capital cost of the centrifuge system will be lower than for the fluidized bed thermal dryer for identical coal streams.

3. It is concluded that for identical coal streams, the capital and operating costs of drying coal fines in a centrifuge system (per ton of dried coal) will average between 66% and 79% of that of a fluidized bed thermal dryer system depending on the volume of the coal streams.

4. A review by the Virginia Air Quality Control Authority (to whom the EPA has delegated responsibility for air quality control in the State of Virginia) has resulted in a finding that there are no significant pollution problems associated with the centrifuge. It is therefore concluded that the centrifuge can be of value in reducing the pollution problems in coal processing plants.

5. It is concluded that the technology embodied in Prototype 2, which was the subject of this project, is now ready for commercialization.

6. It is concluded that the arbitrarily selected design limitations of the Prototype 2 centrifugal dryer, do not necessarily represent the limits in gravity levels and degree of comminution of coals that can be dried with the high gravity centrifugal dryer. It is also concluded that when the improvements developed during the project (in particular the Load Depth Control Dam) are combined with the appropriate combinations of size and bowl speed, the probability exists of successfully drying finer coals than any of those tested during the project.

RECOMMENDATIONS

1. There is in prospect, a continuous tightening of EPA regulations on pollution emissions for the next several years. There is also a probability that modern mining methods will continue to increase the level of coal fines being generated. It is therefore recommended that the process of commercialization of the pollution free, high speed, high production, batch type centrifugal coal fines dryer go forward immediately.

2. As the first step in the commercialization of the centrifuge, it is recommended that Prototype 2 be placed in a continuous production mode in a coal processing plants.

3. Continuing research and development on comminuted, deep cleaned coal indicates that there will be a need for an economical, pollution free, energy efficient method for drying deep cleaned, comminuted coal. It is therefore recommended that the high gravity, high production batch type centrifuge be considered as a method worthy of further development for drying this emerging coal product.

ACKNOWLEDGEMENTS

Coal Technology Corporation wishes to recognize and thank a number of organizations whose efforts and cooperation contributed to the successful work described in this report.

The personnel of the Pittsburgh Energy Technology Center, of the U. S. Department of Energy have been most cooperative in that when unforeseen problems were encountered, the test team was allowed the flexibility (within the scope of the Statement of Work) to make the alterations in scheduling and methodology to react successfully to the new findings developed during the testing. Without this project, the new coal drying technology would not now be ready for commercialization.

The United Coal Company has been most gracious in its cooperation in supplying the host plant location at its Wellmore No. 8 processing plant. The many fine people of the Virginia Division of United, have been cooperative and helpful in too many ways to list here.

The Roberts & Schaefer Company has supplied valuable information and has made the arrangements for the coal samples brought in from West Virginia and Illinois.

Consolidation Coal Company has supplied test samples from both West Virginia and Pennsylvania preparation plants. They have also shared with us their analytical data.

Jim Walter Resources supplied both coal samples and laboratory analyses of the coal.

The Old Ben-Zeigler Coal Company supplied samples of coal for tests at considerable inconvenience to them.

To all of the above, we extend our sincerest thanks.

REFERENCES

Hucko, R. E., Gala, M. B., and Jacobsen, P. S., "Status of DOE-Sponsored Advanced Coal Cleaning Processes", March 1989, Prepared for Pittsburgh Energy Technology Center

U. S. Patent No. 4,640,770, Smith 2-3-87, Apparatus for Extracting Water from Solid Fines and the Like.

U. S. Patent No. 4,855,042, Smith 8-8-89, Apparatus for Minimizing Reactive Forces on a Gimbal-Mounted Centrifuge.

U. S. Patent No. 4,857,210, Smith 8-15-89, Method and Apparatus for Prevention of Blinding of Centrifuge Filter Screens.

END

**DATE
FILMED**

9/04/92