AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910

301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

**Cover Sheet for a Hanford
Historical Document
Released for Public Availability**

Released 1994

**Prepared for the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830**

**Pacific Northwest Laboratory
Operated for the U.S. Department of Energy
by Battelle Memorial Institute**

DISCLAIMER

This is a **historical document** that is being released for public availability. This was made from the best available copy. Neither the United States Government nor any agency thereof, nor Battelle Memorial Institute, nor any of their employees, makes any **warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.** The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

(CLASSIFICATION)

DECLASSIFIED

GENERAL ELECTRIC

HANFORD ATOMIC PRODUCTS OPERATION - RICHLAND, WASHINGTON

DOCUMENT NO.

HW-63122 A

C-44a
SERIES AND COPY NO.

A

35

DATE

December 22, 1959

☒ XX

THIS DOCUMENT CONTAINS RESTRICTED DATA AS DEFINED IN THE ATOMIC ENERGY ACT OF 1946. ITS TRANSMITTAL OR DISCLOSURE IN ANY MANNER TO AN UNAUTHORIZED PERSON IS PROHIBITED.

TITLE

DESIGN OF PRODUCTION TEST IP-297-A-FP,
THE EFFECT OF AUTOCLAVE FILM DAMAGE ON THE
INCIDENCE OF GROOVE PITTING ON
X-8001 ALLOY FUEL JACKETS

☐

OTHER OFFICIAL CLASSIFIED INFORMATION

THIS MATERIAL CONTAINS INFORMATION AFFECTING THE NATIONAL DEFENSE OF THE UNITED STATES WITHIN THE MEANING OF THE ESPIONAGE LAWS, TITLE 18, U. S. C., SECS. 793 AND 794, THE TRANSMISSION OR REVELATION OF WHICH IN ANY MANNER TO AN UNAUTHORIZED PERSON IS PROHIBITED BY LAW.

AUTHOR

R. E. Hall

and

W. H. Hodgson

ISSUING FILE

THIS DOCUMENT MUST NOT BE LEFT UNATTENDED OR WHERE AN UNAUTHORIZED PERSON MAY HAVE ACCESS TO IT. WHEN NOT IN USE, IT MUST BE STORED IN AN APPROVED LOCKED CONTAINER WITHIN AN APPROVED GUARDED AREA. WHEN IN YOUR POSSESSION AND UNDER YOUR CONTROL, YOU MUST OBTAIN A SIGNED RECORD FROM THE ISSUING OFFICE. IT IS YOUR RESPONSIBILITY TO PROTECT IT AND ITS CONTENTS WITHIN THE LIMITS OF THIS DOCUMENT AND FROM ANY UNAUTHORIZED PERSON. ITS TRANSMITTAL TO, AND ITS USE AT YOUR PLACE OF BUSINESS IS PROHIBITED. IT IS NOT TO BE DUPLICATED. IF ADDITIONAL COPIES ARE REQUIRED, OBTAIN THEM FROM THE RELATED ISSUING FILE. ALL PERSONS READING THIS DOCUMENT ARE REQUESTED TO SIGN IN THE SPACE PROVIDED BELOW.

ROUTE TO:

PAYROLL NO.

LOCATION

FILES ROUTE
DATE

SIGNATURE AND DATE

DUN for 60008

60008

103

JUN 25 1968

RECORD
COPY

Indefinite Retention

Disposal Date

Authority

Authority

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

(CLASSIFICATION)

DECLASSIFIED

DESIGN OF PRODUCTION TEST IP-297-A-FP
 THE EFFECT OF AUTOCLAVE FILM DAMAGE ON THE
 INCIDENCE OF GROOVE PITTING ON
 X-8001 ALLOY FUEL JACKETS

BY

Classification Cancelled and Changed To

R. E. Hall

DECLASSIFIED

and

By Authority of WA Snyder,

W. H. Hodgson

CG-PR-2, 1-7-94By DK Hanson, 1-13-94Verified By J. E. Savelly 1-31-94

December 22, 1959

DISTRIBUTION

1. FW Albaugh	26. HP Kraemer
2. JA Ayres	27. WK Kratzer
3. RI Beaver	28. CG Lewis
4. RS Bell	29. AR Maguire
5. HE Berg-JS Shipp	30. NR Miller
6. AG Blasewitz	31. HC Money
7. RW Bown	32. JF Music
8. JH Brown (1703D)	33. TD Naylor
9. JJ Cadwell	34. R Nilson
10. AC Callen	35. EV Padgett
11. VR Cooper	36. CA Priode-WG Albert
12. RL Dickeman	37. T Prudich-RE McGrath
13. RL Dillon	38. RW Reid
14. EJ Filip	39. RB Richman-JF Hokenson
15. JM Fouts	40. WD Richmond
16. GC Fullmer-GF Owsley	41. HG Spencer-RR Bloomstrand
17. SM Gill	42. K Stewart
18. OH Greager	43. CA Strand
19. CN Gross	44. JT Stringer
20. FW Grubb	45. JW Talbott
21. LT Hagie	46. FL Van Wyck
22. RE Hall	47. EA Weakley
23. WH Hodgson-WA Blanton	48. DC Worlton
24. PC Jerman	49. Records Center
25. DG Kern	50. 300 Files

DECLASSIFIED

This document is Restricted Data as defined in the Atomic Energy Act of 1954. Its release or the disclosure of its contents is prohibited.

This document consists of 9 pages, Copy No. 33 of 50 copies, [redacted]

EXCLUDED FROM DECLASSIFICATION

DESIGN OF PRODUCTION TEST IP-297-A-FP,
THE EFFECT OF AUTOCLAVE FILM DAMAGE ON THE
INCIDENCE OF GROOVE PITTING ON
X-8001 ALLOY FUEL JACKETS

Introduction

The recent increase in the incidence of groove pitting on X-8001 clad fuel elements in the old reactors apparently refutes the earlier hypothesis that surface segregation of the secondary phase of this alloy was the primary cause of the unique, preferential attack sustained during irradiation. Components received within the past fifteen months have exhibited essentially none of the segregation. On the other hand, recent evidence suggests that localized penetration of the autoclave film on X-8001 may influence groove attack. The implications of this hypothesis include the necessity of special handling to preserve the autoclave film integrity or possibly elimination of the film altogether.

Either certain conditions or properties of the X-8001 alloy or unusual autoclave conditions intermittently produce non-uniform autoclave films. If some of these film conditions are a result of non-uniform alloy structure in the cans, they may contribute to the groove pitting attack. This report presents the design of a test to compare the scratched and non-uniform autoclave films with uniform unscratched controls under special irradiation conditions to compare the incidence of groove pitting.

Objective

The objective of this test is to evaluate the hypothesis that autoclave film damage contributes to groove pitting of X-8001 alloy clad fuel elements.

Summary of Test

The initial test of sixteen charges containing test elements having three non-uniform autoclave film conditions, and the standard control elements, in a latin square configuration, will be irradiated in new tubes in an old reactor under special flow conditions to 800 MWD/T exposure goal. The need for subsequent testing will be based on the results of this test.

Basis

The persistence of peculiar groove pitting which appears intermittently on X-8001 aluminum alloy-clad fuel elements in the old reactors continues to be a major problem. Radiometallurgical examination of many fuel elements having these pits has

DECLASSIFIED

never revealed evidence of intergranular corrosion; rather, the corroded surfaces appear to have had mechanical work performed on them. Several mechanisms for this type of attack are proposed. These include: a) segregation of alloying constituents on the cladding surface; b) formation of a brittle oxide film which may be mechanically damaged by flowing water¹; c) "cavitation" like attack on the surface of downstream pieces because of high water temperature - low vapor-pressure relationship; and d) mechanical damage to the autoclave film resulting in sacrificial corrosion in the damaged area. These latter "grooves" appear to be the result of scratches, but may be caused by other mechanical damage to the film.

An in-reactor test² to reproduce the "grooving" phenomena was interrupted by a failure which necessitated discharge of the entire test at about 50 percent of goal exposure. Coincidental with the in-reactor test, arrangements were made with the vendor for increased "scalping" of the bloom stock from which X-8001 alloy components were fabricated, to reduce observed nickel segregation. The apparent relief of the groove-pitting problem, which coincided with increased utilization of the segregation-free components, resulted in a de-emphasis of testing programs to reproduce the groove-pitting phenomena. Subsequent experience has shown that in spite of the improvement in jacket surface fabrication, decrease in the incidence of groove pitting may have been a result of lower tube outlet temperatures and that once again it is a serious corrosion problem in the old reactors. Recent experience in D, DR and H Reactors has indicated that groove pitting may be associated with side failures (although conclusive proof is missing, the presence of groove pitting in the vicinity of the failure point on three recent failures in these reactors could be circumstantial evidence.) In addition, a production test³ to evaluate core stability, recently discharged from DR Reactor contained pieces with both longitudinal and transverse pits which appear to support the hypothesis that groove pitting may be initiated by damage to the oxide film.

Photographs of pieces from the charges in which ruptures occurred in D and DR Reactors show various degrees of groove pitting may be present on a single piece. There appeared to be large, deep (20-30 mils) filmed-over, pits adjacent to tear-drop shaped pits of shallow to medium depth (0-20 mils) having one side shiny (to the downstream side) or the entire surface shiny, showing active corrosion (or erosion) was taking place at the time of discharge. In addition to the above, most pieces had at least one long (1 to 6 inches) groove which had clean exposed surfaces indicating active corrosion. Failures at the older reactors have generally occurred only in new

1. F. H. Krenz, "CORROSION OF ALUMINUM-NICKEL TYPE ALLOYS IN HIGH TEMPERATURE AQUEOUS SERVICE," Corrosion 13, 575t-81t (1957).
2. HW-54010, "PRODUCTION TEST IP-124-A, INVESTIGATION OF CONDITIONS LEADING TO THE SEVERE PITTING OF M-388 ALLOY SLUG JACKETS," N. R. Miller, December 3, 1957 (Secret).
3. HW-59222, "PRODUCTION TEST IP-220-A-4-FP, EVALUATION OF THE DIMENSIONAL INSTABILITY OF CORE BLANK HEAT-TREATED URANIUM," R. E. Hall, February 11, 1959 (Secret).

DECLASSIFIED

tubes wherein the reduced top annulus provided the necessary flow and temperature conditions to cause groove pitting; however, a failure in an old tube in H Reactor (installed in 1956) which exhibited groove pitting, possibly de-emphasized the new tube as an essential cause.

In summary, in spite of improved jacket surfaces from additional scalping operations, the groove pitting of X-8001 aluminum alloy-jacketed fuel elements continues. The postulated mechanism has been revised to include as suspected causes brittle or damaged oxide film, unusual flow and temperature conditions, and normal corrosive mechanisms.

Flow tests under extreme temperature conditions are underway in mock-up facilities; however, it remains that the final, conclusive testing must be done in-reactor. Since the conversion to X-8001 aluminum alloy jackets has reached a point where over seventy percent of I & E fuel elements in old reactors are clad in the nickel aluminum alloy, it is desirable to determine the cause or causes of the phenomena and take necessary steps to eliminate or reduce the hazard of groove pitting of X-8001 alloy cladding. To provide the necessary experience, this test is proposed to attempt to determine the cause of these phenomena and possibly infer means of eliminating groove pitting. Further, since the source of groove pitting has not been pinpointed, this program will include a series of sub-tests designed to evaluate the most probable sources. Currently in the old reactors, the use of water-mixing pieces to reduce tube corrosion may show if the high top annulus temperature is a primary cause and if water-mixing pieces may be used to prevent groove pitting.

The appearance of transverse grooves to a depth of 0.038 inch on recently discharged X-8001 clad PT elements strongly suggests a primary influence of minor damage to the autoclave film, such as scratches or gouges. These transverse grooves have not been noted on C-64 clad elements.

Fabrication of Test Material

1. Fuel Elements

Fuel elements for this test will be eight-inch natural OIIN I & E, clad in X-8001 aluminum alloy jacketing material. All components are to meet all requirements of Fuel Element Process Specifications.⁴

2. Assembly

All fuel elements shall be fabricated in accordance with the Fuel Element Process Specifications.

4. HW-47029, "PROCESS SPECIFICATIONS, FUEL ELEMENT MANUFACTURING PROCESSES, FUELS PREPARATION DEPARTMENT." (Confidential)

DECLASSIFIED

3. Quality of Material

All standard quality control measures will be applied in the fabrication of fuel elements. After autoclave, a sharp tool will be used to mark the test elements. These marks, although serious enough to be considered a cause of rejection on standard fuel elements, are considered essential for this test. These are discussed in detail in the "Testing" section of this report.

4. Quantity of Material

For the initial test, to evaluate the effects of scratches and non-uniform film, 576 X-8001 clad OIIN I & E fuel elements will be required. These are to consist of the following categories:

- a. One hundred forty-four (144) having uniform autoclave film.
- b. One hundred forty-four (144) having non-uniform autoclave film, and
- c. Two hundred eighty-eight (288) pieces to complete the charges on the upstream ends.

Quantities of fuel elements for subsequent testing will depend on the size of the test required.

5. Standard Controls

The standard controls will consist of the 72 fuel elements from the group having a uniform film and which will not be scratched. These elements will be further defined under the "Testing" section which follows.

Testing1. Pre-irradiation Testing and Measurements

Groove pitting appears on fuel elements in the downstream half of the charge, in the high coolant temperature zone. Therefore, to evaluate causes of this condition, only the downstream half of each charge will contain test elements. The test and control elements will be grouped into the following categories.

AUTOCLAVE FILM CONDITION

<u>Surface Condition</u>	<u>Uniform</u>	<u>Non-uniform</u>
Scratched	Code A 72 Pieces	Code C 72 Pieces
Non-scratched	Code B 72 Pieces (Standard Controls)	Code D 72 Pieces

DECLASSIFIED

- a. Scratches will be applied in the selected pattern (see attached sketch) using a sharp corundum tool. Penetration will be less than 0.004 inch.
- b. Charges will be made up in latin square arrangement as one charge in each of the following configurations.

ABCD...thru 16 pieces
 BCDA...thru 16 pieces
 CDAB...thru 16 pieces
 DABC...thru 16 pieces
 BACD...thru 16 pieces
 ACDB...thru 16 pieces
 CDBA...thru 16 pieces
 DBAC...thru 16 pieces

CADB...thru 16 pieces
 ADBC...thru 16 pieces
 DBCA...thru 16 pieces
 BCAD...thru 16 pieces
 ADCB...thru 16 pieces
 DCBA...thru 16 pieces
 CBAD...thru 16 pieces
 BADC...thru 16 pieces

The remainder of each charge will be made up of the 288 non-selected fuel elements. Each selected piece will be marked with the code letters and position number as well as all pieces in each charge having the series number.

- c. 1) All pieces will be measured for warp, length and diameter.
- ii) The selected pieces in positions 1 thru 16 will be weighed and photographed with the slit camera to record surface conditions prior to irradiation. The slit camera pictures will be indexed on the code letter on the base of each selected piece and by a rectangular slot cut in the male contour and on the base adjacent to the outer edge (see attached sketch).

2. Irradiation

The initial test of 16 charges containing test and control elements in a latin square configuration will be irradiated in new tubes in an old reactor under special flow conditions to 800 MWD/T exposure goal. The set of conditions selected for this test will represent conditions under which groove pitting has occurred, as nearly as possible. Thus, based on past experience, there is a reasonable probability that groove pits will appear on some, if not all, of the downstream pieces in this test. Since it is possible that water-mixers affect the incidence of groove pitting, it will be necessary to preclude use of mixers in these charges.

3. Post Exposure Examination

- a. All fuel elements from this test will be visually examined for surface conditions. Those pieces exhibiting groove pitting are to be photographed with the slit camera, indexed in such a way that the post-irradiation photographs may be compared with the pre-irradiation photographs.

DECLASSIFIED

- b. Pre-measured fuel elements will be measured for diameter, warp and weight changes.
- c. All fuel elements will be weaseled to permit calculation of specific power and specific exposure.

Test Audit

Notebook HW-63122 will be needed to record all laboratory data pertaining to this test. Any unusual incidents, whether or not they seem important at the time, are to be recorded in the notebook.

The appendix of the report contains a list of items to be used as a guide for preparation of the notebook.

Test Limitations and Hazards

Since the mechanism for generation of groove pits is not fully understood, the possibility exists that groove pitting may not appear on any pieces from this test. If this condition occurred, this test must be considered inconclusive, yet the results are expected to point out probable conditions necessary to produce groove pitting in further testing.

R. E. Hall
 Process and Reactor Development
 Irradiation Processing Department

W. H. Hodgson
 Engineering Section
 Fuels Preparation Department

REH/WWH/gb

DECLASSIFIED

APPENDIX

DATA TO BE RECORDED IN PRODUCTION TEST NOTEBOOK

- I. Fuel Element Core Lot Number
- II. Can Lot Number
- III. Assembly Process
 - A. Process Used
 - B. Brief Explanation of Process
 - C. Attendant Conditions
- IV. Post Assembly Treatment
 - A. Autoclaving
 - B. Marking
 - C. Inspection
 - D. Photography
- V. Pre-irradiation Examination
 - A. Dimensions
 - B. Warp
 - C. Weight 1-16 Downstream
- VI. Irradiation
 - A. Coolant Temperature
 - 1. Inlet
 - 2. Outlet
 - B. Panellit and Crossheader Pressures
 - C. Number of Shutdowns (Controlled and Scram)
 - D. Other
- VII. Post Irradiation Examination
 - A. Visual
 - B. Warp (And Other Profilometer Data)
 - C. Photographs
 - D. Other
- VIII. Log

Running account with dates recording the progress of the PT, unusual incidents (such as a slight change in process during assembly) and other deviations whether or not they seem pertinent at the time of occurrence.

DECLASSIFIED

MALE END

SKETCH OF PROPOSED MARKINGS ON DOWNSTREAM

FUEL ELEMENTS

DATE

FILMED

6/15/94

END