FOSSIL

**DOE/MC/23167-3065
(DE92001145)**

**ADVANCED COAL-FUELED GAS TURBINE SYSTEMS
Annual Report for the Period July 1990—June 1991**

September 1991

Work Performed Under Contract No. AC21-86MC23167

**For
U.S. Department of Energy
Morgantown Energy Technology Center
Morgantown, West Virginia**

**By
Westinghouse Electric Corporation
Orlando, Florida**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

Advanced Coal-Fueled Gas Turbine Systems

**Annual Report
July 1990-June 1991**

Work Performed Under Contract No.: DE-AC21-86MC23167

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
Westinghouse Electric Corporation
Power Generation Business Unit
440 Alafaya Trail
Orlando, Florida 32826-2399**

September 1991

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1 EXECUTIVE SUMMARY	1-1
2 INTRODUCTION	2-1
2.1 Scope of Report	2-1
2.2 Program Objectives	2-2
2.3 Combustor Concept	2-3
2.4 Development Progress and Plan	2-6
3 SUBSCALE SLAGGING COMBUSTOR TEST: APPARATUS, PLAN AND METHOD	3-1
3.1 Test Facility and Apparatus	3-1
3.2 Fuel Feed Systems	3-1
3.3 Combustor Test Rig	3-2
3.4 Gas Sampling System	3-5
3.5 Sorbent Feed System	3-5
3.6 Description of Combustor Configuration Tested	3-6
3.7 Coals Tested	3-8
3.8 Sorbents Tested	3-10
3.9 Nominal Test Conditions	3-10
4 SUBSCALE SLAGGING COMBUSTOR: TEST RESULTS AND DISCUSSION	4-1
4.1 Slagging Cyclone Tests	4-4
4.2 Slag Tap Tests	4-20
4.3 Slag Tap/Sulfur Reduction Tests	4-23
4.4 Carry-over Tests	4-29
5 OTHER ONGOING EFFORTS	5-1
5.1 Update of Reference System Definition	5-1
6 CONCLUSIONS	6-1
7 REFERENCES	7-1

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
2-1	Schematic of Slagging Combustor Concept, Including Slag and Spent Sorbent Removal Subsystem	2-4
2-2	Slagging Combustor Configuration Prior to this Reporting Period.....	2-6
3-1	Schematic of Subscale Slagging Combustor Test Rig as Utilized During Slagging Cyclone Testing.....	3-2
3-2	Schematic of Subscale Slagging Combustion Rig After Addition of Modified Impact Separator and Real-Time Slag-Tapping Capability.....	3-3
3-3	Modified Impact Separator with Slag Tap and Collection Vessel.....	3-4
3-4	Sketch of Vibrating Louver Apparatus Added to Sorbent Feed System	3-6
4-1	Coal/Air Injector Assembly as Originally Installed.....	4-8
4-2	Coal/Air Injector Assembly, Showing Melted Injector Tubes.....	4-8
4-3	Particle Size Distributions from Cyclone Bucket.....	4-15
4-4	Particle Size Distributions from Isokinetic Sampler.....	4-16
4-5	ϕ and NO_x for Test SL1-3.....	4-28
4-6	Percent of Total Sulfur Present and Ca/S Molar Ratio for Test SL1-3.....	4-28

LIST OF TABLES

<u>Table</u>	<u>Page</u>
3-1 Combustor Configuration Employed for Slagging Cyclone Tests During the Period of June 30, 1990 to July 1, 1991	3-7
3-2 Combustor Impact Separator and Slag Tap-Bath Configuration for All Tests During the Period January 18, 1991 to June 30, 1991.....	3-7
3-3 Ultimate and Proximate Analyses of Coals Tested During This Reporting Period - (Dry Basis)	3-8
3-4 Ash Analysis for Coals Tested During This Reporting Period - (Dry Basis)	3-9
3-5 Sorbents Evaluated During This Reporting Period	3-10
3-6 Nominal Test Conditions	3-10
4-1 Chronology of Testing During the Report Period	4-2
4-2 Proximate Analyses for Dorchester, VA Coal.....	4-10
4-3 August 1988 Analyses of Dorchester, VA Coal.....	4-11
4-4 Ultimate and Ash Analysis of Dorchester, VA Coal.....	4-12
4-5 Proximate Analyses of Haverhill Dorchester and Pittsburgh No. 8 Coal Samples.....	4-13
4-6 Proximate Analyses of Everett Dorchester Coal Samples.....	4-13
4-7 Fly Ash Loading and Overall Slag Collection Efficiency Estimates with Slagging Cyclone.....	4-14
4-8 Slag Material Balances.....	4-17
4-9 Brief Listing of Subscale Slagging Combustor - Slagging Cyclone Test Results.....	4-18

EXECUTIVE SUMMARY

Westinghouse's Advanced Coal-Fueled Gas Turbine System Program (DE-AC21-86MC23167) was originally split into two major phases - a Basic Program and an Option. The Basic Program also contained two phases. The development of a 6 atm, 7 lb/s, 12 MMBtu/hr slagging combustor with an extended period of testing of the subscale combustor, was the first part of the Basic Program. In the second phase of the Basic Program, the combustor was to be operated over a 3-month period with a stationary cascade to study the effect of deposition, erosion and corrosion on combustion turbine components.

The Option phase was to have been devoted towards performing a verification test of a 70 MMBtu/hr combustor.

It was decided by DOE/METC to terminate the experimental portion of this program at the conclusion of the slagging combustor tests in 1991. New work-scope, Basic Combustion Turbine Generic Design Studies, being conducted under this contract are to be completed by the end of 1992.

Participants in this Westinghouse-led effort include: Westinghouse's Power Generation Business Unit, and Science and Technology Center; Avco Research Laboratory/Textron (now referred to as Textron due to an internal reorganization); Gilbert/ Commonwealth, Inc.; and, AMAX Extractive Research and Development, Inc.

The objective of this contract is to establish the technology required for subsequent commercial development and application by the private sector of utility-size direct coal-fueled gas turbines. Emissions from these units are to meet or be lower than the Environment Protection Agency's (EPA's) New Source Performance Standards (NSPS) for a pulverized coal-fired steam turbine generator plant.

Cost of electricity (COE) is to be kept low by burning raw or moderately cleaned coal. Within the program, coal is to be burned as dried pulverized coal (PC) powder and as a coal-water mixture (CWM).

Critical slagging combustor technology concerns that are being addressed within this program included:

- Slag removal
- Sorbent stimulated sulfur removal in the slag
- Suppression of NO_x formation
- Complete carbon burnout
- Adequate particulate capture
- Acceptable pressure loss and availability

- Slag, particulate and sulfur removal from fuel-rich primary combustion gases in the second stage
- Final gas oxidation and dilution in the third stage (operated lean).

Textron, based on over a decade of experience in developing coal combustors for magnetohydrodynamics (MHD) programs, has had the technical lead in the fundamental design effort of a direct coal-fired combustor. The purpose of a coal combustor in an MHD system is to produce a plasma flow that meets certain specific requirements which include steady uniform flow, and control or utilization of slag. This is very similar to the purpose in a combustion turbine system.

In slagging combustion systems, coal is burned at a temperature high enough so that coal ash melts and turns to liquid. This liquid, which flows down the combustor walls, is collected and withdrawn. Therefore, there are few solid ash particles to pass out of the chamber with the hot gases and damage the turbine. In addition, the sulfur found in most coals can also be removed at this point. Calcium compounds are introduced into the chamber, where they combine with the sulfur. The resulting sulfates melt and join the slag. Also, because a slagging combustor operates fuel-rich in the primary zone it will suppress NO_x formation.

The slagging combustor being developed in this program consists of three stages:

- First stage - Primary combustion zone (operated rich)
- Second stage - Slag, particulate and sulfur removed from fuel-rich primary combustion gases
- Third stage - Final gas oxidation and dilution (operated lean).

The nature of the slagging combustor requires that the walls be kept at a temperature where the slag flows readily; approximately 2600°F or higher. This, of course, only applies to the primary and secondary zones which have refractory lined and water-cooled walls. These zones convey less than one-third of the combustor air flow; two-thirds enters in the lean combustion zone, which is air-cooled.

For the conceptual design of a combustion turbine slagging combustor, Westinghouse was to have explored the possibility of using fewer and larger combustors. Larger vessels would have a more favorable volume-to-surface ratio.

In testing to date, the concept, in subscale, has demonstrated its ability to handle high- and low-sulfur bituminous coals, and low-sulfur subbituminous coal. Feeding the fuel in the form of PC has proven to be superior to CWM type feed. The program objectives relative to combustion efficiency, combustor exit temperature, NO_x emissions, carbon burnout, and slag rejection have been met. Work continues to reduce alkali, particulate, and SO_x levels

leaving the combustor. Parametric studies have been made that focus on the latter two problems. They indicate that faster, more thorough slag removal between the rich and lean stages is the path towards achieving lower emissions of SO_x .

During this reporting period, after reconfiguring the slagging combustor from burning the CWM back to PC and adding a slagging cyclone, a char carry-over problem developed and has yet to be resolved. Current testing results suggest that elevation of the system for the purpose of cyclone integration may have upset the distribution of coal to the four coal/air injectors used to feed the coal into the primary zone. This could lead to spatial non-uniformities in primary zone stoichiometry. Additional testing will be performed to completely identify and eliminate this phenomena.

In an update of the concept's economics, calculations were made to define the COE for the reference pulverized coal steam plant with a flue gas desulfurizer (FGD) and two combined cycle plants that fire oil or natural gas against the COE of two direct coal-fired combustion turbine combined cycle plants. (One plant would use pulverized coal while the second plant uses coal-water mixture [60% coal/40% water]).

The COE margin, which is the difference between the COE of a candidate system and the COE of the pulverized coal steam plant with FGD, showed COE margins of 17.9 and 11.0, for the direct coal-fired combined cycle plants, fired with pulverized coal and coal-water mixture, respectively.

Subscale slagging combustor tests are continuing at Textron, with the specific goals of improving the real time slag removal system, measuring alkali, improving sulfur capture with improved sorbent feeding, and resolving the char carry-over phenomenon.

The slagging combustor system was modified at the beginning of this reporting period, as well as during the period, in order to try and improve on the combustor performance goals. The first of these changes included the addition of a slagging cyclone separator downstream of the impact separator. This change was made with the goal of improving particulate removal. The second major change to the slagging combustor system was made during the February and March 1991 time frame. This modification included replacement of the original symmetrical centerbody impact separator with a new impact separator and real-time slag removal system. The combination of the improved impact separator, real-time slag removal and slagging cyclone separator has provided improvement in particulate and sulfur removal.

INTRODUCTION

This is the fourth annual technical progress report for the Advanced Coal-Fueled Gas Turbine Systems Program. This program was initiated by the Department of Energy as an R&D effort to establish the technology base for the commercial application of direct coal-fired combustion turbines. The combustion system under consideration incorporates a modular three-stage slagging combustor concept. Fuel-rich conditions inhibit NO_x formation from fuel nitrogen in the first stage; also in the first stage, sulfur is captured with sorbent; coal ash and sulfated sorbent are removed from the combustion gases by inertial means in the second stage by the use of an impact separator and slagging cyclone separator in series. Final oxidation of the fuel-rich gases, and dilution to achieve the desired turbine inlet conditions are accomplished in the third stage, which is maintained sufficiently lean so that here, too, NO_x formation is inhibited.

Prior to this reporting period the slagging combustor had been configured to operate on PC and was then modified to operate on CWM. The slagging combustor system was then redesigned to accommodate a slagging cyclone and a modified impact separator with real-time slag removal. During the period covered by this annual report, the redesigned system was fabricated, assembled and tested. Because PC fuel proved to be the preferred fuel over CWM, the slagging combustor was once again retrofitted for its use during the balance of combustor testing.

2.1 SCOPE OF REPORT

This report covers work performed under DOE METC Contract DE-AC21-86MC23167, Advanced Coal-Fueled Gas Turbine Systems, for the period July 1990 through June 1991. During this time frame, effort has been divided between Task 3.1, Subscale Combustion System, and two smaller tasks: 8.0, Update of Reference System Definition; and 10.0, Slag Tapping.

Subtask 3.1 involves the design, fabrication, testing and evaluation of a 12 MMBtu/hr slagging combustor for utility gas turbine applications. Task 8.0 is an economic study and Task 10.0 is for the introduction of real-time slag tapping hardware and subsequent testing. The work that was on hold under Task 7.0, Cascade, was officially deleted from the program's work-scope based on DOE/METC's decision to discontinue funding of the hardware portion of this program at the conclusion of subscale combustor testing.

2.2 PROGRAM OBJECTIVES

The primary objective of this work was to verify the feasibility of a direct coal-fueled combustion system for combustion turbine applications. This has been accomplished by the design, fabrication, testing and operation of a subscale development-type coal combustor. Because this was a complete departure from present-day combustion turbine combustors and fuels, it was considered necessary to make a thorough evaluation of this design, and its operation in subscale, before applying it in commercial combustion turbine power systems.

Another objective was to keep fuel costs acceptably low by burning raw or moderately cleaned coal, as is normal utility practice. Both bituminous and subbituminous coals have been tested. Coal grinding has been, and, is to be, consistent with that considered practical and economical for electric utility utilization. The coal was burned exclusively as dried PC during the 1988-1989 reporting period and then burned as CWM during much of the 1989-1990 period. Testing revealed PC to be the preferred fuel both from performance and economic standpoints. Therefore, the slagging combustor system was reconfigured to burn PC for the balance of the program.

The ultimate goal for the coal combustion system was to attain efficient combustion of the coal, and simultaneously to satisfy all of the environmental emission regulations (e.g., EPA's New Source Performance Standards [NSPS] for coal-fired steam generators) and combustion turbine power system requirements.

Objectives

1. Attain high efficiency with emphasis on effective fuel utilization (burn-out) and low pressure and heat losses.
2. Achieve stable and reliable operation.
3. Control and limit NO_x formation in the gas to meet or better NSPS.
4. Remove sulfur to meet or better NSPS.
5. Demonstrate efficient removal of slag and all particulates in the gas with the ultimate objective to meet or better NSPS.
6. Retain alkalies in ash/slag removed from the combustor.

Specific Performance Goals

1. Demonstrate self-sustaining coal combustion at the thermal design rating of 12 MMBtu/hr.
2. Burn utility grade bituminous and subbituminous coal, both in the pulverized form, and as coal-water mixture.
3. Produce a lean-zone exit gas stream having an average temperature of at least 1850°F, and having a uniformity such that the exit temperature pattern factor will be 20 percent or less.
4. Achieve combustion efficiency of greater than 98 percent.
5. Demonstrate stable and reliable operation and acceptable refractory performance.
6. Show that heat and pressure losses are acceptable; (interim values of 8 and 7 percent, respectively are being used in Task 8.0, for example).
7. Operate with NO_x emissions of less than the NSPS limit of 0.6 lb/10⁶ Btu.
8. Limit SO_x per the NSPS to a maximum of 1.2 lb/10⁶ Btu, where 90 percent reduction is required for SO_x greater than 0.6 lb/10⁶ Btu, and 70 percent reduction is required for SO_x less than 0.6 lb/10⁶ Btu.

2.3 COMBUSTOR CONCEPT

The slagging combustor is a modular unit with three combustor stages and a slag/sorbent removal train of several stages. Figure 2-1 is a schematic representation of these stages. (It should be noted that the cyclone and third stage of the subscale combustor is water-cooled, instead of air-cooled as shown in this figure.) The stages are:

First Combustor Stage	-	All the coal, the sorbent, and about one-third of the gas turbine compressor discharge air enter this stage. Rich burning takes place; hot, fuel-rich gases and melted slag and spent sorbent exit downward, towards Stage 2.
Second Combustor Stage	-	Here the melted solids are separated from the hot, fuel-rich gases by inertia, in either an impact separator, or in a cyclone separator, immediately downstream. The hot gases go to Combustor Stage 3, while

Figure 2-1. Schematic of Slagging Combustor Concept, Including Slag and Spent Sorbent Removal Subsystem

the melted solids flow by gravity out through a tap hole into a water spray, and on, into a water collection vat.

Third Combustor Stage

Here the hot, fuel-rich gases from Stage 2, are mixed with the balance of the gas turbine compressor discharge air. The gases burn, but at such a lean fuel-to-air ratio that little NO_x is formed. Relatively clean, hot gas flows from this stage to the expander, where the shaft work is extracted.

- First Slag Removal Stage - This is where the slag is quenched and crushed. A water spray cools the molten slag, causing it to solidify and fracture. The resulting fragments are further reduced in size by underwater roller-crushers.
- Second Slag Removal Stage - The slag and spent sorbent particles are conveyed under water, away from the combustor, to a point where they are slurried by an impeller.
- Third Slag Removal Stage - Here the slag/sorbent slurry is let down to 1 atmosphere pressure through a valve and dewatered. The water is returned to the system, and the dry particles, which are stable, are conveyed to a landfill.

Test Combustor Concept

Figure 2-2 shows the subscale slagging combustor as it was prior to this reporting period, in a simplified section view. Although there was no slag/sorbent removal system, the first, second, and third combustion modules were all included.

The first stage is the primary combustion zone. Coal and preheated air enter the primary zone coaxially through four injection nozzles which are equally spaced around the combustion chamber. This coaxial injection promotes intense air/coal mixing and rapid particle heat-up/devolatilization, which minimizes carbon burnout time.

The four incoming coal-air jets converge at the combustor center line and form one vertical jet which impacts the combustor dome. This forms a toroidal vortex which provides the mechanisms for flame stabilization and centrifugal separation of larger ash/slag particles. This separated ash/slag forms a stable flowing layer on the combustor walls. The vertical geometry of this stage allows gravity to assist in the removal of the molten slag.

Fuel-rich conditions in this stage inhibit NO_x formation from fuel-bound nitrogen. It also provides the necessary reducing conditions for removal and capture of sulfur. The sulfur sorbent, limestone, dolomite, or one of various iron oxides is counter-flow injected into the downstream end of the primary zone. The first stage was designed for a coal particle residence time of about 100 ms (for 75-micron sized particles).

Figure 2-2. Slagging Combustor Configuration Prior to this Reporting Period

The second stage is an efficient impact separator which is closely coupled to the first stage. The impact separator removes particulates carried over with the gas from the primary zone, whether they are sorbent or fine particles of ash. The impact separator alone did not demonstrate the ability to satisfy the turbine particulate loading requirements. Additional gas cleanup to meet NSPS particulate standards was provided by adding a slagging cyclone separator in series with the impact separator (Section 3.3).

The third stage is used to complete combustion and to temper the products to meet turbine inlet requirements. The rapid mixing between gases coming from the second stage and secondary air insures that the peak gas temperatures and hence thermal NO_x formation is minimized. This stage is designed based on conventional gas turbine combustor practice.

2.4 DEVELOPMENT PROGRESS AND PLAN

Initial development of the direct coal-fired combustion turbine combined cycle power plant revolved around Task 3.1, Subscale Combustor Development. It then was to have moved to Task 7.0, Subscale Stationary Cascade Test, and next to

Optional Task 6.0, Utility System Prototype Combustor Evaluation. In parallel with these major tasks, shorter, tasks have been undertaken to supply particular data needs. Tasks 8.0 through 11.0 fall into this latter category. The development plan, along with progress made, is described below for each Task worked on during this period.

Subtask 3.1, Subscale Combustor Development. During this reporting period the subscale combustor development has been devoted to evaluating the addition of a slagging cyclone and a modified impact separator with real-time slag tapping. These evaluations have been done with regards to particulate and sulfur removal efficiency. Resolving the char carry-over problem that developed after modification of the system, became another objective of the testing program.

Subtask 7.0 Stationary Cascade Test. Under the original program, the second phase of the Basic Program was to include evaluation of the effects of combustor exit gas on turbine materials. Two 30-hour subscale combustor and stationary cascade tests were to be conducted at the Textron facility to determine turbine vane erosion, corrosion, and deposition trends. The stationary cascade rig was designed, approved by METC, but never released for manufacture. The cascade portion of the program was officially deleted from the program in the fall of 1990.

Subtask 8.0 Update of Reference System Definition. In a previous DOE program (Reference 2), studies showed that the lowest-cost environmentally acceptable method of generating electricity from coal was a coal-fired combustion turbine combined cycle plant employing on-site coal preparation. With the passage of several years time, it was felt necessary to update these economic studies, to maintain their validity. This was done, and during this reporting period a final draft report was prepared and submitted to DOE for review and comment. The final report will be issued in September 1991.

Subtask 10.0 Slag Tap. The objective of this effort was to design and procure slag tapping and improved impact separation components to address three concerns: (1) Testing times were limited, due to a buildup of molten slag and spent sorbent in the bottom of the impact separator vessel; (2) The impact separator had experienced heat loss caused by poor refractory retention on the convex surface around the inlet nozzle and, by over-sizing of the slag retention zone; (3) Slag entrainment on the walls of the impact separator vessel in the vicinity of the gas exit port has caused approximately 20 percent of the collected slag to flow to the lean-zone, out of the impact separator. During this reporting period, an improved impact separator including real-time slag tapping and a slagging cyclone were installed and tested as described in Section 3 and 4.

Subtask 11.0 Basic Sulfur Capture Studies. A study was done prior to this reporting period with the objective of learning the effects of operating variables (temperature, residence time, sorbent type, and sorbent feed rate) on sulfur capture and to improve sulfur capture in the subscale slagging combustor. The final report, "Basic Sulfur Capture Studies," was submitted to METC in October 1990.

SUBSCALE SLAGGING COMBUSTOR: TEST APPARATUS, PLAN, AND METHOD

3.1 TEST FACILITIES AND APPARATUS

All combustion tests during this reporting period were conducted at the Textron facility located in Haverhill, MA (Reference 3). This facility supplies unvitiated combustion air to the burner test rig at up to 120 psia and 7 lb/sec, and at a temperature of up to 800°F.

3.2 FUEL FEED SYSTEMS

During the initial year of subscale slagging combustor testing, and also in the first, three tests of the 1989-1990 reporting period, PC was utilized as fuel. This fuel was fed to the combustor from a 10,000 lb capacity, conical-bottom tank. Coal is carried from the tank to the combustor in a stream of high velocity air. PC loadings in the carrier air are high, with the coal to air mass ratio being as high as eight. The feed rate of coal is controlled by the flow rate of transport air, and the difference in pressure between the tank and the feed line.

The coal feed rate is measured by monitoring the weight change of the coal feed tank using load cells which support the tank. Coal feed to the combustor has been through four injectors, equally spaced around the primary zone. A fluid dynamic flow splitter near the combustor divides the carrier gas, with its entrained coal, to supply equal fuel streams to each injector.

For the balance of the 1989-1990 reporting period, the fuel was fed as CWM. The CWM was stored, heated, and continually recirculated, in a 500 gallon tank located inside the test building. A pumping, metering, and control system for the CWM was built up on a skid, and located next to the test rig. A progressive cavity pump is used for the CWM. The same four injection stations in the primary zone are used for CWM as PC, and all the primary combustion air was introduced coaxially around the CWM injection nozzles. High pressure compressed air from a storage trailer outside the building was used to operate the four air-atomizing CWM nozzles.

The slagging combustor system was retrofitted at the beginning of this reporting period, to again burn pulverized coal for the balance of subscale combustor testing. The change over was done at the same time the slagging cyclone was added to the system.

3.3 COMBUSTOR TEST RIG

The combustor test rig configuration used during slagging cyclone testing, is shown schematically in Figure 3-1. In the upper left of the figure is the dome-topped primary zone. Air and PC are injected upward into this primary zone through four angled fuel injectors, equally spaced around the zone. For simplicity, only two are shown in the figure. When needed, pulverized sorbent, with carrier air, is also injected into the primary zone. Four smaller injectors handle this task.

Rich combustion occurs in the primary zone, and melted coal ash (slag) and hot, fuel-rich gases exit downward out of the zone through the small diameter nozzle shown. The nozzle leads the rich gases into the impact separator with slag bucket, shown at the lower left. A sudden change of direction, and gravity, separate slag and particles. Leaving the liquid and solid matter behind, the cleaned, hot fuel-rich gases move out of the top right-hand side of the impact separator. The primary zone, the impact separator, the internals of the impact separator, and the connecting passages are water-cooled, high-pressure, steel vessels, lined with refractory.

Figure 3-1. Schematic of Subscale Slagging Combustor Test Rig as Utilized During Slagging Cyclone Testing

Having left the impact separator, the hot gases pass to the right and enter into the slagging cyclone separator where the particulate emissions are further reduced. The cyclone separator is water-cooled and refractory-lined, so that the slag and sorbent particles it collects are liquid, and flow to the bottom. Cleaned, very hot, fuel-rich gases then pass out the center tube and directly into the lean-burn zone. The lean-burn zone is a cylindrical water-cooled section having 32 inclined air jet inlets. The first 16 of these bring combustion air in, to oxidize the fuel-rich gases which burn spontaneously. The second 16 inlet jets admit dilution air, which drops the burning gases to a temperature acceptable to a turbine, (1850°F to 2000°F).

Following the lean-burn zone, the hot gases pass through a water-cooled instrumentation section, and then through a water-cooled orifice plate which drops them to near atmospheric pressure. Emissions, pressure, and temperature profile are detected in the instrumentation section. Following the orifice plate, the gases pass through a water spray, and to the exhaust.

Figure 3-2. Schematic of Subscale Slagging Combustor Rig After Addition of Modified Real-Time Slag-Tapping Capability

Figure 3-2 shows a schematic of the subscale combustor rig after the addition of the modified impact separator and real-time slag-tapping capability. These changes were made at the conclusion of the slagging cyclone tests in January 1991. This configuration was used for testing during the balance of this reporting period.

As described in Reference 4, the modified impact separator was designed to minimize slag droplet re-entrainment, to better control the bucket wall slag flow and also reduce heat losses. The revised impact separator also includes a slag tap and is illustrated schematically in Figure 3-3. Separated slag flows out of the bucket via the centrally located slag tap hole and is collected in a water bath below the tap. The exhaust housing has been re-designed to reduce the exit gas velocities and also to reduce heat losses by reducing surface area. Also, with the slag now being collected in a separate slag vessel, the slag bucket itself has been reduced in size considerably, again reducing heat losses.

The problem of slag flow out of the bucket exit has been addressed by both re-contouring the exit duct and by re-designing the centerbody to be asymmetric. The intention here is to direct the high momentum inlet jet away

Figure 3-3. Modified Impact Separator with Slag Tap and Collection Vessel

from the bucket exit. Inertial separation of slag will take place both on the asymmetric centerbody and on the bucket walls in the region of jet impingement. By intent, the slag is separated onto the wall opposite the exit, and the upper part of the asymmetric centerbody acts as a shield to prevent slag being directed towards the exit. The strong re-circulation in the vicinity of the slag tap will also help to keep the slag tap clear by increasing the heat flux in that region.

3.4 GAS SAMPLING SYSTEM

Gas sampling was done both to obtain discrete samples for off-line analysis, and continuously for on-line instruments. Either a heated sample line or a drier was employed, to avoid loss of SO_2 due to moisture condensation. A hot sample was led to the SO_2 , H_2S , and NO_x analyzers. For the CO , CO_2 and O_2 analyzers, there was a cold trap in the line just before the instruments. Ethylene glycol, cooled by dry ice, was used in the cold trap to drop out moisture upstream of the instruments. The on-line gas analysis instruments were:

<u>Gas</u>	<u>Analysis Instrument</u>
CO	Beckman Model 868-18 Non-Dispersive Infrared
CO_2	Beckman Model 868-23 Non-Dispersive Infrared
SO_2	Thermo Electron Model 40 Pulsed Fluorescence
O_2	Beckman Model 755 Paramagnetic
NO/NO_x	Thermo Electron Model 10 Chemiluminescence
H_2S	Thermo Electron Model 340 H_2S Converter
H_2S	Western Research Model 721-A U-V Absorption $\text{H}_2\text{S}/\text{SO}_2$ Analyzer

In addition to continuous gas sampling using the above instrumentation, rapid samples were taken during the combustor tests for off-line analysis using a Perkin- Elmer Sigma II gas chromatograph.

3.5 SORBENT FEED SYSTEM

Sorbent is carried into the combustor by streams of air, densely packed with particles, in response to the pressure difference between the sorbent hopper and the combustor. A conical-bottom feed tank, fluid-dynamic flow splitter, and a set of four small injectors for the combustor are employed. This system is satisfactory for large sorbent flows. A different system is needed to

handle small flows, and was installed during this reporting period. It utilizes a vibrating horizontal louvered plate to meter the sorbent, rather than air pressure differential.

Figure 3-4 shows a sketch of the vibrating louver system used to improve sorbent feed. A pressure shell houses the feeder, and attaches to the bottom of the conical sorbent feed hopper. The key feature of the feeder is a set of variable speed vibrating louvers which meter the solid material into a sheet metal cone. This cone guides the sorbent into a carrier line. Feeder speed is determined by a 4-20 mA signal from the combustor programmable logic controller.

Figure 3-4. Sketch of Vibrating Louver Apparatus Address to Sorbent Feed System

3.6 DESCRIPTION OF COMBUSTOR CONFIGURATION TESTED

At the start of this testing period, the primary zone, impact separator, and lean-burn third-stage zone were of the same design and dimensions as what had been used for the PC testing in the program in 1988 and 1989 except for the orientation of the third stage, which was now vertical instead of horizontal, and the addition of the slagging cyclone, as is depicted in Figure 3-1. Table 3-1 shows hardware data for this subscale slagging combustor configuration.

During February and March 1991, the combustor test rig was reconfigured to include the modified impact separator and real-time slag-tapping capability as discussed in Section 3.3 and shown in Figure 3-2. The data for these two new pieces of hardware is shown in Table 3-2, while the other components remained as shown in Table 3-1.

Table 3-1. Combustor Configuration Employed for All Tests During the Period of June 30, 1990 to January 17, 1991.

Primary Zone	Diameter:	16.75 in.
	Length/Diameter:	1.25/1.50
	Injector Horizontal Angle:	55 deg.
	Injector Vertical Angle:	0 deg.
	Nominal Injection Velocity:	200 ft/s
Impact Separator	Type:	Centerbody
	Nozzle Diameter:	3.5 in.
	Nominal Inlet Velocity:	450 ft/s
	Jet/Impactor Plate Spacing:	4.8 in.
Slagging Cyclone	Nominal Inlet Velocity:	120 ft/s
	Overall Height:	85.0 in.
	Maximum Diameter (ID):	14.5 in.
	Slag Bucket Height:	17.2 in.
Lean-Burn Zone	No. of Secondary Injectors:	16
	Secondary Injector Diameter:	1.02 in.
	Secondary Injection Velocity:	260 ft/s
	No. of Dilution Injectors:	16
	Dilution Injector Diameter:	1.02 in.
	Dilution Injection Velocity:	260 ft/s

Table 3-2. Combustor Impact Separator and Slag Tap/Bath Configuration for All Tests During the Period January 18, 1991 to June 30, 1991.

Impact Separator	Type:	Curved Body
	Radius of Curvature:	19.0 in.
	Arc Length:	17.6 in.
	Width:	12.0 in.
	Jet/Impactor-Plate Separation:	6.0 in.
	Nozzle Diameter:	3.5 in.
	Nominal Inlet Velocity:	450 ft/s
Slag Tap/Bath	Height:	48.0 in.
	Diameter:	24.0 in.
	Tap Diameter:	4.5 in.

During February and March 1991, the combustor test rig was reconfigured to include the modified impact separator and real-time slag-tapping capability as discussed in Section 3.3 and shown in Figure 3-2. The data for these two new pieces of hardware is shown in Table 3-2, while the other components remained as shown in Table 3-1.

Table 3-1. Combustor Configuration Employed for All Tests During the Period of June 30, 1990 to January 17, 1991.

Primary Zone	Diameter:	16.75 in.
	Length/Diameter:	1.25/1.50
	Injector Horizontal Angle:	55 deg.
	Injector Vertical Angle:	0 deg.
	Nominal Injection Velocity:	200 ft/s
Impact Separator	Type:	Centerbody
	Nozzle Diameter:	3.5 in.
	Nominal Inlet Velocity:	450 ft/s
	Jet/Impactor Plate Spacing:	4.8 in.
Slagging Cyclone	Nominal Inlet Velocity:	120 ft/s
	Overall Height:	85.0 in.
	Maximum Diameter (ID):	14.5 in.
	Slag Bucket Height:	17.2 in.
Lean-Burn Zone	No. of Secondary Injectors:	16
	Secondary Injector Diameter:	1.02 in.
	Secondary Injection Velocity:	260 ft/s
	No. of Dilution Injectors:	16
	Dilution Injector Diameter:	1.02 in.
	Dilution Injection Velocity:	260 ft/s

Table 3-2. Combustor Impact Separator and Slag Tap/Bath Configuration for All Tests During the Period January 18, 1991 to June 30, 1991.

Impact Separator	Type:	Curved Body
	Radius of Curvature:	19.0 in.
	Arc Length:	17.6 in.
	Width:	12.0 in.
	Jet/Impactor-Plate Separation:	6.0 in.
	Nozzle Diameter:	3.5 in.
	Nominal Inlet Velocity:	450 ft/s
Slag Tap/Bath	Height:	48.0 in.
	Diameter:	24.0 in.
	Tap Diameter:	4.5 in.

3.7 COALS TESTED

Two coals were used during this reporting period for the slagging combustor tests. They were a low sulfur bituminous coal, Dorchester, from Virginia, and a high sulfur eastern bituminous coal, Pittsburgh No. 8. Both were used as utility grind, with the particle size such that 95% would pass through a 200 mesh screen. Table 3-3 shows the ultimate and proximate analyses, along with the ash fusion data (which is of special concern in a slagging combustor), for the two coals used. Table 3-4 provides the ash analysis for each coal.

Due to the char carry-over phenomenon that appeared after the slagging cyclone was added to the system, and the subsequent investigation into the coal that had been being used for the combustor testing, two fresh loads of Dorchester and Pittsburgh No. 8 coal were ordered. The last two combustor tests conducted during this reporting period utilized these fresh loads of coal but proved not to be the cause of the char carry-over, even though the chemical compositions of each of the older, respective coal types had shown some degradation over a couple years while being stored in barrels.

Table 3-3. Ultimate and Proximate Analyses of Coals Tested During This Reporting Period - (Dry Basis)

	<u>COAL TYPE</u>	
	EASTERN BITUMINOUS (DORCHESTER, VIRGINIA)	EASTERN BITUMINOUS (PITTSBURGH, NO. 8)
<u>PERCENT</u>		
ASH	6.49	7.71
VOLATILE MATTER	34.02	38.86
FIXED CARBON	<u>59.49</u>	<u>53.43</u>
	100.00	100.00
SULFUR	1.04	2.39
CHLORINE	0.04	0.14
CARBON	80.80	77.89
HYDROGEN	5.37	5.29
NITROGEN	1.43	1.36
OXYGEN, (BY DIFFERENCE)	4.83	5.22
ASH	6.49	7.71
HEATING VALUE, BTU/LB	14,390	14,031
ASH FREE HTG. VAL., BTU/LB	15,389	15,203
PERCENT MOISTURE IN THE AS-RECEIVED CONDITION	6.13	1.49

Table 3-3. (Continued)

ASH FUSION TEMPERATURES IN REDUCING ATMOSPHERE FOR COALS
TESTED DURING THIS REPORTING PERIOD, (°F):

INITIAL DEFORMATION	2183	1900
SOFTENING	2305	2080
HEMISPHERICAL DROP FORMATION	2379	2140
BECOMES FLUID	2466	2210
VISCOSITY = 250	2340	2295

RELATED DATA

BASE ACID RATIO	0.46	0.41
WATER SOLUBLE SODIUM (PPM)	110.00	200.00
WATER SOLUBLE POTASSIUM (PPM)	52.50	22.80
CALCIUM (CALCULATED)	-	-
ASH BASIS	3.14	4.68

Table 3-4. Ash Analysis for Coals Tested During This Reporting
Period - (Dry Basis)

CONSTITUENT	COAL TYPE	
	EASTERN BITUMINOUS (DORCHESTER, VIRGINIA)	EASTERN BITUMINOUS (PITTSBURGH NO. 8)
SiO ₂	44.78	39.40
Al ₂ O ₃	20.89	21.80
Fe ₂ O ₃	22.65	22.79
CaO	4.40	6.55
MgO	1.20	2.10
Na ₂ O	0.51	1.45
K ₂ O	1.85	1.51
TiO ₂	1.51	1.27
P ₂ O ₅	0.52	0.40
SO ₃	1.54	--
Undetermined	0.15	2.73

3.8 SORBENTS TESTED

Table 3-5 shows the sorbents that were used with the various tests conducted during this reporting period. Both calcia-based and iron-oxide based sorbents were evaluated. Sorbent was injected into the system as a dry powder through separate sorbent injectors.

Table 3-5. Sorbents Evaluated During This Reporting Period

<u>SORBENT TYPE</u>	<u>TEST RUNS (NO.)</u>
Limestone (CaCO_3) 100% through 325 mesh	SL1-1
Hematite (Fe_2O_3) 400 mesh/ Limestone Mixture 1:1	SL1-2
Magnetite (Fe_3O_4) 100 mesh/ Limestone Mixture 1:1	SL1-3

3.9 NOMINAL TEST CONDITIONS

The nominal test conditions in the subscale slagging combustor were set to essentially the same values for each test during this reporting period, and are summarized in Table 3-6.

Table 3-6. Nominal Test Conditions

Combustion Chamber Pressure, psia	80 to 87
Combustion Air Temperature, °F	600 to 660
Primary Air Mass Flow Rate, lb/s	1.9 to 2.3
Secondary Air Mass Flow Rate, lb/s	2.0 to 2.3
Dilution Air Mass Flow Rate, lb/s	2.0 to 2.4
Pulverized Coal Mass Flow Rate, lb/s	0.2 to 0.3

SUBSCALE SLAGGING COMBUSTOR: TEST RESULTS AND DISCUSSION

During this reporting period, July 1, 1990 through June 30, 1991, two major system configuration changes were made and 17 tests conducted with the subscale slagging combustor.

At the beginning of the reporting period, the slagging combustor system was in the process of being disassembled for maintenance and repair along with modifications. The modifications included adding a slagging cyclone separator between the rich-burn primary and lean-burn secondary zones, and changing over from CWM fuel feed to the PC system used earlier in the program. After the slagging cyclone tests were completed in January 1991, the slagging combustor system was once again reconfigured, this time to include a modified impact separator and a slag tap. This work was done during the months of February and March 1991.

The objective of the first 9 tests of this period was to determine the collection efficiency of the slagging cyclone. Specific details of the slagging cyclone tests are discussed in Section 4.1. After the second series of modifications were made, 4 tests were conducted to test the effectiveness of the slag tap and 3 tests were conducted to ascertain the further reduction of sulfur due to the slag tap. These tests are discussed in detail in Section 4.2 and 4.3, respectively.

When testing resumed in November of this period, an unexpected problem developed in the primary zone. Although the design of this zone was unchanged from previous periods, and although the fuel used during this period was PC, which had worked well in the program in 1988 and 1989, a char carry-over problem nevertheless developed. Relative to PC testing earlier in this program, primary zone carbon conversion was lower by two percentage points. Therefore, at the end of December, an unofficial additional program goal became restoring high primary zone coal conversion efficiency. As testing progressed during the period the char carry-over problem continued to persist despite numerous efforts to correct it. A series of five tests to specifically investigate the char carry-over problem was planned. The first of these tests was conducted just prior to the end of this reporting period. This test is discussed in Section 4.4. All the tests conducted during this reporting period, along with brief remarks about it, are listed in Table 4-1.

Table 4-1. Chronology of Testing During the Report Period

Designation, Date, and Time Burning 100% Coal:	Coal:	Sorbent:	Remarks:
Test C1-1 11/13/90 51 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Shakedown test; char carry-over found.
Test C1-2 11/30/90 134 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	>100% slag collection; 97.8% slag collection comb. C1-1.
Test C1-3 12/11/90 28 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Mass flows verified to prior tests; no effect on carry-over.
Test C1-4 12/12/90 18 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Coal injector tubes moved; no change.
Test C1-5 12/20/90 17 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Injector tubes moved again; no change.
Test C1-6 1/4/91 17 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Total slag recovery 100.6% thru test C1-6.
Test C1-7 1/8/91 17 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Spool piece added to chg prim. zone aspect ratio 1.25 to 1.50.
Test C1-8 1/17/91 16 Min.	Pittsburgh No. 8 Pulverized coal, 2.4% S, (dry basis); 95% through 200 mesh	No Sorbent	>90% cyclone efficiency corroborated. Carry-over coal independent.

Table 4-1. (Continued)

Test C1-9 1/24/91 16 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	No change from prior testing data.
Test S1-1 4/16/91 N/A	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Test shutdown due to high wall temp. of slag bath.
Test S1-2 4/19/91 15 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Slag tap worked well; Equiv. ratio = 1.1.
Test S1-3 4/25/91 N/A	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Shutdown due to slag bath overflow.
Test S1-4 5/15/91 87 Min.	Dorchester, VA Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Slag tap plugged due to very viscous slag; Equiv. ratio = 1.2.
Test SL1-1 6/4/91 71 Min.	Pittsburg No. 8 Pulverized coal, 2.4% S, (dry basis); 95% through 200 mesh	Limestone only	10% sulfur reduction; injectors clogged.
Test SL1-2 6/13/91 80 Min.	Pittsburg No. 8 Pulverized coal, 2.4% S, (dry basis); 95% through 200 mesh	Limestone/ Hematite, 1:1 mix	20% sulfur reduction; poor sorbent flow.
Test SL1-3 6/20/91 87 Min.	Pittsburg No. 8 (fresh) Pulverized coal, 2.4% S, (dry basis); 95% through 200 mesh	Limestone/ Magnetite, 1:1 mix.	45-50% sulfur reduction obtained.
Test CR-1 6/28/91 50 Min.	Dorchester, VA (fresh) Pulverized coal, 1.04% S, (dry basis); 95% through 200 mesh	No Sorbent	Test for char behavior of fresh coal.

4.1 SLAGGING CYCLONE TESTS

Refractory Curing

An oil-fired run was made on November 6, 1990 in order to complete curing of the newly installed refractory layers in the combustor and cyclone separator. The system was allowed to come up to pre-heated air temperature (650°F) before lighting off a fuel oil flame. The oil flow was progressively increased over a period of several hours in order to increase the bulk gas temperature in the combustor and cyclone and allow the refractory to cure.

Test C1-1

The first coal combustion with the cyclone separator installed (Test C1-1) was made on November 13, 1990. A few minor problems with the logic control program were encountered during the start-up sequence. These came about because of the change over from CWM to PC fuel and were easily rectified. In general, this test was unsatisfactory and was regarded as a shakedown test. Computer problems were experienced throughout the test; the computer data acquisition program randomly timed out and stopped acquiring data, therefore an incomplete data record was obtained. Immediately after initiating the PC flow (Dorchester, VA coal: 6% ash, 1% sulfur), steam and smoke were observed at the exterior of the primary zone, indicating a leak. An emergency shut down was safely carried out. A gas sample probe, at the exit from the primary zone, had failed due to lack of cooling water, thereby allowing combustion gases to leak into the test cell.

The sample probe access port was plugged and the system was re-started. The coal flow was stopped again after some ten minutes of coal burning, due to the failure of a thermocouple probe in the primary zone, which allowed combustion gas to reach and damage the thermocouple wire connector block for that probe. The thermocouple was removed and the access port plugged. During the same shutdown, it was observed that the membrane drier on gas sample port No. 5 had overheated. This was due to the fact that a seal on the particle filter housing for that sample line was incorrectly installed, allowing an excessive flow of combustion gas through the drier. This access port was also plugged. The system was re-started for the second time and some 45 minutes of uninterrupted coal burning were obtained. A total of 768 lbs of coal were burned during the three periods.

The combustor was disassembled for inspection the next day. The dome was removed. The dome, the primary zone walls and the exit nozzle appeared as expected with a smooth, purplish-black, glassy slag layer throughout. The slag bucket was removed to reveal a normal slag layer on the centerbody top and sidewalls and a pool of frozen slag in the bucket. The cyclone was opened at the top of the conical section to reveal a visible slag spiral that was proceeding down the barrel (it had completed approximately one quarter of one revolution). The cyclone barrel wall was covered with a spotty slag coating,

which became progressively sootier towards the bottom of the cyclone. Most surprising of all was the fact that the cyclone bucket appeared to be full of coal, or a black powder which appeared to be very much like the coal feed. Slag pieces were found to be mixed in with the powder.

By measuring the weight change of the slag bucket and adding the weight of the slag found mixed with powder in the cyclone bucket, the total slag collection efficiency was determined to be 83%. This figure, however, does not account for any slag in new layers on the walls of the primary zone and the cyclone inlet and upper barrel. The downstream particulate sampling probe filter showed a weight gain of less than 0.1 g. The weight gain for previous runs of this duration was on the order of 3 to 5 g. The indicated slag collection efficiency from the particle sampler measurement was 99.7%, indicating a particulate loading of 13 ppmw in the combustor exhaust gas.

However, the reason for the presence of the black powder in the cyclone bucket remained uncertain. The quantity obtained represents some 2 percent of the total coal flowed. Two possibilities presented themselves: (1) that coal had flowed through the system with no flame present in the primary zone and had been caught in the cyclone separator, perhaps as part of the regular or emergency shut-down procedures; or (2) a fraction of the inlet coal flow was simply not being burned and was passing to the cyclone where it was retained. The first of these hypotheses seemed implausible, as the quantity involved was large enough to be readily accounted for with the highly accurate load cell measurement system employed and represented approximately one minutes' flow at design conditions. No discrepancies could be found. A detailed examination of the data records indicated that there was no period when coal was flowing without a flame in the primary zone.

In order for the second hypothesis to be plausible, a change in either injection geometry or coal specifications from the previous period of PC firing seemed necessary, as no such black powder was ever observed in the previous tests, either on downstream surfaces or in the downstream particulate sampling system. In this scenario, a fraction of the coal is not injected properly into the upward-directed jet in the primary zone, but rather turns over and exits directly through the primary zone nozzle. This coal would have a very limited residence time in the primary zone and would travel through an oxygen depleted zone, and therefore would at best be partially pyrolyzed.

Initial indications are that the size distribution of the coal and the powder found in the cyclone bucket are remarkably similar, lending credence to the first hypothesis: that the coal in the cyclone bucket came from an as yet undetermined shutdown phenomenon.

Test C1-2

It was obvious that the previous test had not been long enough for the slag layer in the cyclone barrel to reach the bottom of the cyclone, so a longer

repeat test was made. Before making this test, a number of modifications were made to the cyclone. Additional instrumentation access ports were added to the cyclone bucket and at the exit from the lean burn combustor. A number of faulty cooling water flowmeters and RTDs were replaced and the computer software system was overhauled in an attempt to cure the data acquisition problem noticed during Test C1-1.

Test C1-2 was made on November 30, 1990, burning 1888 lbs of Dorchester coal in an uneventful test (compared to Test C1-1). There was one brief shutdown due to a momentary loss of quench water pressure during a manual topping-up operation. The same computer problems were experienced. The indicated temperature at the bottom of the cyclone was well below the ash fusion temperature.

The combustor, slag bucket and cyclone were again opened for inspection. The overall appearance was similar to the previous test. The slag spiral in the cyclone barrel was now further down, having completed three-quarters of one revolution. Once more the cyclone lower sections were covered with a spotty slag layer. The cyclone bucket was again full of unburned or partially burned coal. This time the downstream particle sample filter was completely full of the same black powder, indicating extensive carry-over to the combustor exhaust. The amount of coal carried over to the exit combined with that found in the cyclone bucket again were on the order of 2% of the input flow. On further examination of the particulate filter, a very thin grey-white fly ash layer was found at the tip of the filter underneath the coal layer.

The reason for the presence of the coal downstream may be that the cyclone bucket was completely filled, due to the longer test duration. Therefore, it would be possible for the cyclone barrel vortex to attach in the powder layer at the top of the bucket, picking up powder and carrying it out of the cyclone. (In normal dry cyclone operations, the bucket is never allowed to fill.) The fact that there was an ash layer underneath the coal layer would support this hypothesis. The ash on the filter was separated from the coal as carefully as possible: the quantity of ash discovered would again indicate an exhaust ash loading on the order of 10 ppmw. A size distribution measurement was made of this ash and also of a fine deposit on the outside of the particulate probe. This material was found to be very fine indeed, with a mean size of 2 - 3 microns.

The total slag recovery for Test C1-2 was greater than 100%, indicating that a portion of the slag captured in Test C1-1 was accounted for in Test C1-2. The overall slag collection measurement for the two tests combined was 97.8%. The material in the cyclone bucket was carefully excavated in order to provide an insight into the source and cause of the unburned coal. A shallow (2 inches) layer of slag/powder was found at the top of the bucket. Underneath that was a 5-in. layer of pure powder, and the bottom 6-in. was a well-mixed slag/powder layer. All the slag found in the cyclone bucket was frozen when

it entered the bucket. The size range of the slag pieces found was large: small spheroids of less than 1 mm in diameter were mixed with pieces several inches across.

In order to visualize the interaction between frozen slag and powder in the cyclone bucket, experiments were conducted with a Plexiglas cyclone model. These tests indicated that irrespective of the order of arrival in the bucket, any slag and powder would soon be intimately mixed by the residual vorticity in the bucket. It seemed increasingly apparent that the unburned coal was arriving in the cyclone bucket continuously during the test. Attention then turned to the coal injection system, in an attempt to discover any changes since that previous series of tests.

Test C1-3

Combustor operating conditions for Tests C-1 and C1-2 were compared in detail with those of the previous series of PC tests. It was observed that the coal carrier air mass flow rates for the cyclone tests were significantly higher than those for the previous PC tests. This would produce higher coal injector velocities and poorer mixing of the PC stream and the primary combustion air stream, possibly leading to the coal carry-over problem. In Test C1-3, conducted on December 11, 1990, care was taken to ensure that the coal carrier mass flows were similar to those for the previous PC tests.

This change had no effect, once more a quantity of unburned coal was collected in the cyclone bucket. A computer problem during the test meant that the usual on-line display of air/fuel ratio and combustor stoichiometry was not available, so conditions were actually a little more fuel-rich than in Test C1-2. Once more there was unburned coal in the downstream particle filter, indicating carry-over from the cyclone bucket to the combustor exhaust. The amount of coal carried over to the exit combined with that found in the cyclone bucket were on the order of 4 to 5% of the input coal flow. This compares with 2% for Test C1-2 and could be related to the increased fuel/air ratio in Test C1-3.

Injector Modifications

Figure 4-1 shows the coal/air injector assembly as originally installed. The coal injector tube is located just upstream of a contraction section, which is designed to promote mixing of the coal and primary air. The contraction leads to the main injector tube, which extends to the primary zone wall. The purpose of the injector tube is to ensure that all the coal is injected towards the dome region and none is allowed to turn over and exit the primary zone.

Figure 4-1. Coal/Air Injector Assembly as Originally Installed

Figure 4-2 shows the coal/air injector assembly as it was during the cyclone tests to date. The main injector tube, which was uncooled, had melted back as far as the pivot joint. This had happened early on in the previous PC testing, but had not been remedied as there was no discernable effect on combustor performance. It was decided to manufacture replacement tubes in order to return the coal/air injector assembly to its original configuration so that any uncertainties about the fuel injection could be eliminated.

Figure 4-2. Coal/Air Injector Assembly, Showing Melted Injector Tubes

Test C1-4 and C1-5

While the tubes were being procured and machined, two other short tests were conducted. In Test C1-4 (December 12, 1990) the coal injector tubes were moved towards the contraction section and positioned exactly as specified in the original design. This produced no change: approximately 2 percent of the coal was passed to the cyclone bucket and/or the downstream particle collector. In Test C1-5 (December 20, 1990) the contraction section was removed and the coal injector tips were moved in so that the coal stream was injected right at the primary zone wall. While this is not favorable from the point of view of coal/primary air mixing, it eliminates the possibility of any coal impinging on the cold injector assembly walls and being injected at an excessively low velocity, with the attendant possibility of by-passing the primary combustion zone. This also produced no change: approximately 4% of the coal was passed to the cyclone bucket and/or the downstream particle collector.

Test C1-6

In Test C1-6 (January 4, 1991) the coal/air injector assembly was returned to its original design, see Figure 4-1. Once again, no change was observed: approximately 2% of the coal was passed to the cyclone bucket and/or the downstream particle collector. This test was rather inconclusive, in that the injector tubes once again melted as far down as the pivot joint. It was not clear how long they had survived and served to direct all injected fuel upwards. The possibility of fabricating these tubes from molybdenum was investigated. The appropriate long-term solution is to cool these tubes.

Test C1-7

Test C1-7 was conducted on January 17, 1991. In this test a spool piece was installed in the primary zone in order to increase the primary zone aspect ratio (L/D) from 1.25 to 1.50. However, no significant effect was observed on the char carry-over. Attention then turned to the coal fuel itself. Proximate analyses were obtained for the Dorchester, VA coal being used in these tests and also for a number of samples of char obtained from the cyclone bucket. The results of these analyses are shown in Table 4-2. Compared to the coal feed, the char analyses show extremely low volatile content, high ash content, very high fixed carbon contents and reduced heating values. These results are consistent with the previously suggested hypothesis: that the char found in the cyclone bucket results from a portion of the inlet coal flow that has somehow by-passed the toroidal vortex region in the primary zone. This coal would have a relatively low residence time in a high temperature fuel-rich environment, leading to significant devolatilization, but very little char oxidation.

Table 4-2. Proximate Analyses for Dorchester, VA Coal

<u>Sample No.</u>	<u>Lab No.</u>	<u>Moisture</u> (%)	<u>Ash*</u> (%)	<u>***</u> <u>Btu/lb</u>	<u>Volatile</u> <u>Matter*</u> (%)	<u>Fixed</u> <u>Carbon*</u> (%)
Dorchester Coal	012324	0.79	10.24	13,019	21.03	68.73
C1-2	12325	2.40	13.19	11,704	1.41	85.40
C1-3	12326	0.38	14.42	11,340	1.11	84.47
C1-4	12327	0.61	24.25	10,467	1.26	74.49
C1-5	12328	0.29	19.25	9,283	1.40	79.35

* On dried basis

*** On as is basis

The Dorchester coal analysis was rather puzzling, however. Compared with an August 1988 analysis, Table 4-3, the coal appeared to have a much higher ash content (10% versus 6%) and a much lower volatile content (21% versus 34%). Combustion of a very low volatile content coal could lead to the phenomena currently being observed. Low volatile coal would have worse ignition characteristics and would require longer char burnout times than high volatile coal. Ultimate and ash analyses were obtained for the same Dorchester sample. These analyses are shown in Table 4-4. They indicate that the sample analyzed last month appears to be a different coal than that analyzed in August, 1988: the ash chemistry in particular is very different.

In order to resolve this question, two further samples of Dorchester coal from two different barrels of the existing coal stocks at Haverhill and two samples from older stocks of Dorchester at Everett were sent for analysis.

PROXIMATE ANALYSIS		% Weight	
		As Received	Dry Basis
Moisture		1.00	xxxxxx
Ash		6.24	6.30
Volatile		33.30	33.64
Fixed Carbon		59.46	60.06
		100.00	100.00
Btu/lb		14234	14378
Sulfur		0.96	0.97
Alkali as Na ₂ O		0.12	0.12
SULFUR FORMS			
Pyritic		-----	-----
Sulfate		-----	-----
Organic		-----	-----
WATER SOLUBLE ALKALIES			
Na ₂ O		0.010	0.010
K ₂ O		0.003	0.003
ULTIMATE ANALYSIS			
Moisture		1.00	xxxxxx
Carbon		80.43	81.24
Hydrogen		4.79	4.84
Nitrogen		1.72	1.74
Chlorine		0.04	0.04
Sulfur		0.96	0.97
Ash		6.24	6.30
Oxygen		4.82	4.87
		100.00	100.00
MINERAL ANALYSIS OF ASH			% Weight Ignited Basis
Silica, SiO ₂			47.79
Alumina, Al ₂ O ₃			23.75
Titania, TiO ₂			1.35
Ferric oxide, Fe ₂ O ₃			18.15
Lime, CaO			1.95
Magnesia, MgO			0.88
Potassium oxide, K ₂ O			1.64
Sodium oxide, Na ₂ O			0.82
Sulfur trioxide, SO ₃			2.23
Phos. pentoxide, P ₂ O ₅			0.84
Strontium Oxide, SrO			0.25
Barium Oxide, BaO			0.20
Manganese Oxide, Mn ₂ O ₄			0.15
			100.00
Silica Value	69.49	Fouling Index	0.26
Base: Acid Ratio	0.32	Slagging Index	0.31
T ₂₅₀ Temperature	2531°F		

Table 4-3. August 1988 Analyses of Dorchester, VA Coal

Table 4-4. Ultimate and Ash Analysis of Dorchester, VA Coal

Dorchester Coal

<u>Ultimate Analysis (%) (as is)</u>		
Carbon	-	81.14
Hydrogen	-	5.13
Nitrogen	-	2.11
Sulfur	-	1.04
Chlorine	-	<0.05
 <u>Ashed Sample %</u>		
Iron	-	4.00
Silicon	-	23.11
Calcium	-	<0.06
Magnesium	-	0.68
Potassium	-	1.93
Sodium	-	0.21
Aluminum	-	14.70
Titanium	-	2.16

Test C1-8 and C1-9

While waiting for the coal analyses, a test was conducted with Pittsburgh No. 8 coal. This test, C1-8, was run on January 17, 1991. The results were inconclusive: the same char carry-over phenomenon was observed. In one last test, Dorchester coal from the Textron Everett stocks was burned in Test C1-9 on January 24, 1991. Once more, no change was observed.

Proximate analyses for the two additional Haverhill Dorchester samples (Dorchester No. 1 and No. 2) are shown in Table 4-5. Proximate analyses for the two Everett Dorchester samples (Dorchester Coal Everett A and B) are shown in Table 4-6. These analyses are much closer to the original August 1988 analysis than to the January 9, 1991 analysis. The latter now appears to be spurious, though it seems that at least one barrel of different coal was burned sometime in the cyclone tests. Some variability in the four latest Dorchester analyses is seen. In particular, the ash content was measured at 6.32, 7.00, 6.45 and 6.44% compared with the original value of 6.30%.

Table 4-5. Proximate Analyses of Haverhill Dorchester and Pittsburg No. 8 Coal Samples

<u>Sample No.</u>	<u>Lab No.</u>	<u>Btu/lb.</u> ***	<u>Moisture</u> (%)	<u>Ash*</u> (%)	<u>Volatile*</u> <u>Matter</u> (%)	<u>Fixed*</u> <u>Carbon</u> (%)
Dorchester Coal No. 1	D12599	14,217	0.82	6.32	31.03	62.65
Dorchester Coal No. 2	12600	13,783	0.84	7.00	30.21	62.79
Pittsburgh No. 8 Coal	12601	13,657	1.22	7.89	36.11	56.00

* On dried basis

*** On As Is basis

Table 4-6. Proximate Analyses of Everett Dorchester Coal Samples

	<u>Dorchester Coal</u> <u>Everett A</u> <u>(Lab No. #D12658)</u>	<u>Dorchester Coal</u> <u>Everett B</u> <u>(Lab No. D12659)</u>
Moisture (%)	0.69	0.78
Ash (dry) (%)	6.45	6.44
Btu/lb	13,914	14,157
Volatile C (%) (dry)	32.26	32.01
Fixed Carbon (%) (dry)	61.29	61.55

Thus, the char carry-over problem was found to be essentially independent of the coal burned and remains unresolved to date. The only significant potential cause of the problem which had remained uninvestigated was the dense phase coal feed itself. A series of experiments to assess the uniformity and steadiness of the coal feed were suggested. These were carried out prior to the re-commencement of combustor testing and found to be inconclusive.

Cyclone Performance

Despite the problems associated with the coal carry-over, several strong indications of excellent cyclone performance were obtained from the cyclone tests. First, the total slag recovery, both from the slag bucket and the cyclone bucket, through Test C1-6 was 100.6%. This measurement has some inherent inaccuracies, due to slag movement on the walls of the entire combustion system, refractory cracking at flanges that are regularly opened and small amounts of refractory dissolution. Total slag recovery before cyclone installation was typically 90%. Thus, slag collection with the

cyclone is significantly greater than that obtained prior to the cyclone installation, and indicates cyclone collection efficiencies on the order of 90%.

Second, in a number of tests a good estimate of fly ash carry-over to the downstream section was obtained from particulate samples. As previously described, unburned coal was carried over to the downstream isokinetic particle sample when enough has accumulated in the cyclone bucket for it to be re-entrained into the cyclone outlet flow. For most tests there was a noticeably distinct fly ash layer on the particle filter. This fly ash layer was underneath the unburned coal layer. With care, relatively uncontaminated samples of each layer can be obtained which allows estimates of fly ash size and loading and overall slag collection efficiency to be made for each run. Table 4-7 shows these estimates for the tests C1-1 through C1-6.

Table 4-7. Fly Ash Loading and Overall Slag Collection Efficiency Estimates with Slagging Cyclone

Test Number	Estimated Total Slag Collection (%)	Estimated Exhaust Fly Ash Loading (ppmw)
C1-1	99.7	7
C1-2	99.6	9
C1-3	99.2	18
C1-4	97.2	64
C1-5	98.9	25
C1-6	98.4	37

For these test conditions, the NSPS emissions limit of 0.03 lbs/MM Btu would correspond to approximately 15 ppmw. These estimates confirm that the cyclone is operating at approximately 90% collection efficiency and definitely shows the potential for meeting the turbine inlet particulate loading requirements and possibly the NSPS requirements.

Particle Size Distributions

Figure 4-3 shows measured size distributions for the coal feed and for three samples of unburned coal recovered from the cyclone bucket. The top size of the cyclone bucket samples was the same as that of the coal feed, but the mean size was somewhat larger. The mass fraction contained in particles less than 10 microns in diameter was considerably smaller for the bucket samples than for the coal feed. This is consistent with by-passing of the main primary zone flame zone; coal that has been exposed briefly to a high temperature environment will be deficient in small particles, as these will have time to

be oxidized completely. In addition, the cyclone separator will be less efficient at capturing the finest coal particles.

Figure 4-3. Particle Size Distributions from Cyclone Bucket. Measured Size Distributions for (1) 200 mesh Dorchester Coal; (2) Sample from Cyclone Bucket, Test C1-1; (3) Sample No. 1 from Cyclone Bucket, Test C1-2; (4) Sample No. 2 from Cyclone Bucket, Test C1-2.

Figure 4-4 shows measured size distributions for particle samples collected by isokinetic sampling downstream of the cyclone separator. The figure shows the size distribution of a cyclone bucket powder sample, a sample of black powder from the particle filter and a sample of fly ash removed from underneath the black powder on the same particle filter. The unburned coal carried over from the cyclone bucket to the isokinetic particle sampler is somewhat smaller than that remaining in the bucket, but is still relatively large. The fly ash collected on the filter, however, is extremely fine, with a mean size of around 3 microns. Some 90% of the fly ash is contained in particles of diameter 5 microns or less.

Figure 4-4. Particle Size Distributions from Isokinetic Sampler. Measured Size Distributions for (1) Sample No. 1 from Cyclone Bucket, Test C1-2; (2) Unburned Coal from Particle Sampler, Test C1-2; (3) Fly Ash from Particle Sampler, Test C1-2.

Material Balances for Cyclone Tests

A summary table for the slag material balance for the slagging cyclone tests is shown in Table 4-8. All tests were with Dorchester coal (6.3 to 7.0% ash) except for Test C1-8, which was with Pittsburgh No. 8 coal (7.6 to 7.9% ash). As pointed out above, the ash content of the coal appears to be variable, with Dorchester analyses showing between 6.3 and 7.0% ash and Pittsburgh No. 8 analyses showing 7.6 to 7.9% ash. An accurate assessment of the total slag collection efficiency obviously depends on accurate knowledge of the coal ash input. Allowing for the above mentioned variability in ash contents, total slag collection efficiencies of between 96.5 (assumes Dorchester ash is 7.00%, Pittsburgh No. 8 is 7.9%) and 106.9% (assumes Dorchester ash is 6.3% and Pittsburgh ash is 7.6%) are obtained. Median ash contents based on the five available Dorchester analyses and the two available Pittsburgh No. 8 analyses are 6.50% for Dorchester and 7.75% for Pittsburgh No. 8. Based on these median ash contents, the total slag collection efficiency for all slagging cyclone tests to date is 99.5%. Despite the variability of these assessments, it is obvious that the slagging cyclone performs extremely well and gives approximately 90% collection of any slag that escapes the impact separator. Table 4-9 provides a description of data for each of the slagging cyclone tests.

Table 4-8. Slag Material Balances

Test	<u>Coal In</u>	<u>Slag Collected in</u> <u>Slag Bucket</u>	<u>Slag Collected in</u> <u>Cyclone Bucket</u>	<u>Cumulative Total</u> <u>Slag Collection</u>
	(lb)	(lb)	(lb)	(lb)
C1-1	768	36	2.0	38.0
C1-2	1888	103	14.5	155.5
C1-3	418	N/A	5.0	N/A
C1-4	200	N/A	2.8	N/A
C1-5	203	50	1.4	214.7
C1-6	204	13	3.4	231.1
C1-7	202	17	2.6	250.7
C1-8	202	8	1.6	260.3
C1-9	189	20	1.4	281.7

TABLE 4-9 BRIEF LISTING OF SUBSCALE SLAGGING COMBUSTOR - SLAGGING CYCLONE TEST RESULTS

TEST NO. & DATE	AIR TO COMBUSTOR PRESS./TEMP. PSIA/°F	BURNING TIME WHEN 100% COAL FUELED (MIN.)	AIRFLOW SPLIT PRI/SEC/ DILUENT (LB/S)	PRIMARY ZONE EQUI- VALENCE RATIO --	FLAME TEMP. (°F)	BURNER OUTLET TEMP. (°F)	COAL THERMAL INPUT (10 ⁶ BTU PER HR)	OVERALL PRESSURE LOSS (#)	PRIMARY ZONE CARBON BURNOUT (#)	HEAT LOSS, STAGE I & STAGE II (#)	SLAG COLL- ECTION (#)
C1-1 11-13-90	83/600	51	1.9-2.0 2.1-2.2 2.3-2.4	1.20 TO 1.30	3200 TO 3400	1350 TO 1470	11.0 TO 12.0	7.0 TO 8.0	N/A	N/A	79
C1-2 11-30-90	87/620	134	1.9-2.1 2.2-2.3 2.2-2.3	1.20 TO 1.30	3400 TO 3500	1600 TO 1750	11.5 TO 12.5	7.5 TO 8.5	96 TO 98	20 TO 22	100
C1-3 12-11-90	87/660	28	1.9-2.0 2.2-2.3 2.0-2.1	1.30 TO 1.50	3200 TO 3500	1800 TO 2000	12.0 TO 14.0	7.0 TO 8.5	N/A	18 TO 20	N/A
C1-4 12-12-90	80/650	18	2.2-2.3 2.0-2.1 2.0-2.1	0.95 TO 1.00	3550 TO 3650	1350 TO 1500	10.0 TO 12.0	10.0 TO 12.0	N/A	N/A	N/A
C1-5 12-20-90	80/630	17	1.9-2.0 2.1-2.2 2.1-2.2	1.10 TO 1.20	3400 TO 3500	1550 TO 1650	11.0 TO 11.5	6.0 TO 7.0	94 TO 96	24 TO 26	116
C1-6 01-04-91	80/620	17	1.9-2.0 2.2-2.3 2.2-2.3	1.10 TO 1.20	3600 TO 3700	1400 TO 1500	10.5 TO 11.0	7.0 TO 8.0	95 TO 98	N/A	129
C1-7 01-08-91	80/620	17	2.0-2.1 2.0-2.1 2.1-2.2	1.10 TO 1.20	3500 TO 3600	1400 TO 1550	11.0 TO 12.0	7.5 TO 8.5	96 TO 98	22 TO 24	136

TABLE 4-9 BRIEF LISTING OF SUBSCALE SLAGGING COMBUSTOR - SLAGGING CYCLONE TEST RESULTS
PAGE 2

TEST NO. & DATE	AIR TO COMBUSTOR PRESS./TEMP. (PSIA/°F)	BURNING TIME WHEN 100% COAL FUELED (MIN.)	AIRFLOW SPLIT PRI/SEC/ DILUENT (LB/S)	PRIMARY ZONE EQUI- VALENCE RATIO --	FLAME TEMP. (°F)	BURNER OUTLET TEMP. (°F)	COAL THERMAL INPUT (10 ⁶ BTU PER HR)	OVERALL PRESSURE LOSS (%)	PRIMARY ZONE CARBON BURNOUT (%)	HEAT LOSS, STAGE I & STAGE II (%)	SLAG COL- LECTION (%)
C1-8 01-17-91	78/650	16	2.0-2.1	1.10	3500	1500	10.0	7.0	96	24	62
			2.1-2.2	TO	TO	TO	TO	TO	TO	TO	
			2.1-2.2	1.20	3600	1600	11.0	8.0	98	26	
C1-9 01-24-91	80/640	16	2.0-2.1	1.10	3550	1550	11.0	7.0	N/A	24	181
			2.1-2.2	TO	TO	TO	TO	TO		TO	
			2.1-2.2	1.20	3650	1600	12.0	8.0		26	

4.2 SLAG TAP TESTS

Slag Tap

At the conclusion of slagging cyclone testing, the combustor was torn down and installation of the revised impact separator and slag tap hardware commenced. The primary zone components were first removed from the test assembly to allow the upper housing of the old slag separator to be removed. The new slag separator upper housing was installed and aligned with the cyclone separator inlet. The primary zone components were then re-installed, along with the new slag separator nozzle. Subsequently, the new impact separator/centerbody assembly was installed. A quartz window was installed to provide a view of the top of the new separator surface. The water supply, water level controls and the pneumatically actuated slag ram were installed in the slag bucket. The cooling water system was modified to provide cooling to the new components. Additional gas and water instrumentation systems were installed and calibrated. The slag ram system was tested. Movement of the ram was relatively slow, the limitation being the airflow capacity of the actuating solenoid valve. A solenoid valve of larger airflow capacity was procured. The automatic level control system for the slag water-bath was checked and worked well.

Upon completion of the slag tap hardware installation, shakedown testing started in March. Pre-heated air (650°F) was passed through the combustor for two four-hour periods to dry the newly installed refractory liners. Subsequently an oil-burning test was made to cure the refractory and check out the slag bath systems. Pre-heated air was run for two hours and then the oil flame was ignited. The oil flow-rate and gas temperature were increased slowly over a four-hour period. In this test, the slag water bath systems were checked out. Thermocouples were installed to measure the outside wall temperatures of the bath above the water line, the water temperature, the gas temperature above the bath, and the bleed steam/gas temperatures before and after water quench. The outside temperature of the bath above the water line stabilized at approximately 150°F after one hour of oil burning. The water temperature some 6-in. below the surface stabilized at approximately 210°F (boiling point at 6 atm is 320°F) after one hour of oil burning. No operational problems were encountered during the test.

After the test, the combustor was opened for inspection. It was discovered that the water level in the slag water bath had been considerably above the design level during the test. The level switch was checked and found to be functioning properly. It was discovered that the ball valve controlling the water supply to the water bath had been leaking, leading to the overfilling of the bath. The valve was replaced. A number of other changes were made before commencing coal-burning tests. In particular, a window was added to the slag bath, so that the tap hole itself could be remotely viewed during the run.

Test S1-1

The first coal-burning test with the slag tap installed was made on April 16, 1991. A camera and remote video monitor were used to observe the region beneath the slag tap. While burning oil, water was observed dripping from the edges of the slag tap itself. Fearing a water leak in the slag separator section the test was stopped. No water leak was found, and it became apparent that what was observed were droplets of condensate falling from the cooled bottom surface of the slag separator.

The test was then continued the next day. The coal flow was started slowly and ramped up to approximately 50% load (6 MMBtu/hr). The temperature of the slag bath wall above the waterline rose to over 500°F, causing concern about the integrity of the newly installed window. The test was stopped. A total of 172 lbs Dorchester coal was burned. The rig was disassembled for inspection. A pancake of slag had formed on the slag separator centerbody, but no slag had reached the tap. The low temperatures at half-load had resulted in an extremely high slag viscosity in the slag separator, leading to poor slag flow.

Test S1-2

For the April 19, 1991 test, a water spray was installed on the outside wall of the upper part of the slag bath, to prevent overheating of this section. In this test the coal flow was ramped up to the design flow (15 lb/min, 12 MMBtu/hr) over a period of 30 minutes. No overheating problems were encountered. Very shortly after reaching the design thermal input, slag was observed to begin flowing out of the tap. The slag flowed continuously until the coal ran out, a period of some 15 minutes. A total of 531 lbs Dorchester coal was burned. The video monitor showed that large globules of slag were descending through the tap and freezing as they fell towards the water.

After removing the water bath, a considerable amount of frozen slag buildup beneath the tap was noted. A chimney of frozen slag extended some 8 to 10 in. down into the slag bath chamber. This chimney had several large openings in it. It was apparent from the nature of the slag flow, both in the chimney and above it in the slag bucket, that in addition to hot gases flowing down the tap cold gases from the slag bath chamber were flowing upwards into the slag separator. This caused a piling up of slag at the bottom of the slag separator near the tap opening. No attempt was made to exercise the slag ram during this first shakedown test. The slag chimney was found to be very easy to knock-off. No estimate of overall slag collection was possible at this stage.

Test S1-3

A third test was made on April 25, 1991. While heating the refractory liner by burning oil, it was noticed that the water in the slag water bath had risen

above the desired level which caused an emergency shutdown. No damage was done. However, a considerable amount of slag was shattered and fell off the walls in the slag separator. The even coating of the slag separator centerbody that resulted from Test S1-2 was destroyed, again by thermal shock. The water level switch was found to be working perfectly.

A cause for this problem was traced to a float switch, yet the exact problem with this switch was not identified. It appeared to be an intermittent problem. Thermocouple probes were mounted inside the slag bath chamber just above and below the normal water line to monitor water level. Water is now added manually based on the temperatures indicated by the thermocouple signals.

Test S1-4

This test, which was a continuation of slag tap testing, was conducted on May 15, 1991. The thermocouples installed after Test S1-3 indicated that no water had to be added due to evaporation. Approximately 1100 lbs of Dorchester seam coal were burned during this run. Over a twenty minute period the coal flow was ramped up to a steady value of 13.5 lb/min. The air flow was adjusted to give a primary zone equivalence ratio of 1.2 which remained constant over the remainder of the run. The coal combustion part of the run lasted 87 minutes.

Slag droplets appeared at the slag tap after 35 minutes of coal combustion. A combination of slag flow via droplets and globules was observed at the slag tap. This process was monitored via a CCD video camera, with the video image displayed on a monitor in the control room. By the end of the run, the slag tap appeared plugged. The plug that formed at the slag tap consisted of many long (nominally 10 inches or so) coalesced globules. The time to achieve steady slag flow at the slag tap seemed long, and the viscosity of the slag flow seemed high.

The post run breakdown of the system indicated that there was considerable slag build-up in the slag bucket and on the slag separator. The slag formation on the slag separator was clam-shell in shape. A thick coating of slag was also observed in the primary combustion zone. It was also confirmed that the slag tap had plugged. Removal of the cyclone slag bucket revealed that it was full of what appeared to be char. The particle collection filter located after the lean-burn, rapid-quench section was also full of char-like material.

The observed increase in slag viscosity and, possibly, slag tap plugging were due to two effects. The viscosity of the slag in the slag tap region was probably higher during this run than during a previous April run (S1-2) because a more fuel-rich equivalence ratio of $\phi = 1.2$ was used rather than the value $\phi = 1.1$ used in the previous run. This should have dropped temperatures throughout the system. Since Dorchester seam coal has the highest T_{250}

temperature of the three coals tested, and the viscosity of coal varies strongly with temperature, the lower temperatures associated with an equivalence ratio of 1.2 could have led to labored slag flow. Since a considerable amount of char was collected in the cyclone slag bucket, complete coal burn-out was not achieved, so temperatures throughout the system could have been reduced further, which would have hindered slag flow further. Improved slag flow was achieved during the sulfur reduction tests by operating with lower primary zone equivalence ratios ($1.1 < \phi < 1.2$), and burning Pittsburgh No. 8 coal which has a lower T_{250} temperature.

4.3 SLAG TAP/SULFUR REDUCTION TESTS

The main focus of these tests was to acquire sulfur reduction performance data in addition to obtaining improved slag flow.

Sorbent Feed System

A number of modifications were made to the sorbent feed system during March 1991. The intention was to improve the stability of the sorbent feed and to provide a method of clearing plugs in the sorbent feed nozzle. First the entire sorbent hopper bottom conical section was removed and remachined so as to provide a completely smooth contraction. Then a number of pairs of one-eighth-inch holes were drilled into the nozzle along its axis. The holes were distributed along the length and periphery of the nozzle. Each pair of holes is supplied separately with high pressure nitrogen via a number of remotely operated solenoid valves. The purpose of the nitrogen jets is to provide a method of clearing plugs.

A number of sorbent feed tests were made to evaluate the blockage clearing system. The nozzle itself was of too large a diameter to give the required limestone flow rate with a reasonable tank-to-carrier line pressure difference. Given the success of the blockage clearing system, a small diameter sorbent nozzle was determined acceptable and installed. During sorbent feed tests the sorbent tank load cell indicator failed. The indicator was too old to warrant repair so it was replaced.

Test SL1-1

This was the first sulfur reduction test conducted using the slag tapping hardware that was added to the system. During this test 896 lbs of Pittsburgh No. 8 coal were burned. The coal combustion portion of this test lasted 71 minutes. A flame-out occurred 33 minutes into the coal combustion portion. Coal combustion ceased at that point for 7 minutes. There was no difficulty in restarting coal combustion and the reason for the flame-out was not determined. Since slag tap plugging occurred in previous tests when operating at an equivalence ratio of 1.2, it was decided to use a slightly lower value to achieve overall higher temperatures with hopes of achieving better slag flow. Good slag flow and slag tapping are critical for achieving good sulfur

reduction. This test, therefore, was conducted with $\phi = 1.1$. The sorbent injected into the primary zone was limestone. A total of 54 lbs were injected over a 27-minute period which began 48 minutes after coal combustion commenced.

Steady sorbent injection was not achieved. The flow rate of limestone varied between 0 and 4 lbs/min. The calcium to sulfur molar ratio varied between 0 and 3, with the mean being approximately 2. The limestone flow stopped several times, but was restarted by cycling the nitrogen gas jets installed on the cone feeding limestone into the transfer line to the combustor, and in the orifice between the cone and transfer line. This series of nitrogen jets is a very effective approach for maintaining sorbent flow, but they cannot be cycled continuously because the injected gas tends to continually increase the sorbent tank pressure and because their impulse generates enough force to corrupt the load cell based sorbent flow rate signal. It is well known that limestone does not flow well, especially at the flow rates we require. In an attempt to obtain a more steady sorbent flow, the limestone was diluted with an inert substance that has much better flow behavior. Both hematite (Fe_2O_3) and magnetite (Fe_3O_4) were used as the diluents. These iron compounds are inert regarding sulfur capture, since little H_2S will be produced in the primary zone for the equivalence ratios of interest ($1.15 < \phi < 1.25$). Furthermore, these compounds are known to be good fluxing agents and should subsequently improve slag flow substantially.

During this test, limestone injection produced less than a 10% reduction in sulfur at the exit of the combustor, i.e., downstream of the lean-burn/quench section. We had expected to see a much greater impact than this with a $\text{Ca/S}=2$. During tear-down and inspection, it was noticed that the tips of the sorbent injectors were almost entirely coated with slag. The passages through the slag were varied and convoluted. It was concluded that good sulfur reduction was not obtained because good sorbent dispersion in the primary zone was not achieved. The tips of the sorbent injectors were flush with the inside surface of the primary zone wall. Thus, slag flowing down the primary zone wall could easily flow over the injector tips. The sorbent injectors were moved inward so they extended nominally 1 in. beyond the inner surface of the primary zone wall. This minimized the wall slag flow from fouling the sorbent injectors, yet didn't disturb the gas phase flow field.

During this test, the slag flowed through the tap very well when limestone sorbent was not being injected. The slag flow through the tap became more viscous and generated attached globules at the tap when the limestone sorbent was being injected. This trend is consistent with the observation of others, which is that limestone tends to increase slag viscosity with all else being equal. Even though slag began to accumulate on the slag tap, it was easy to break loose with the slag ram.

Although sulfur reduction measurements were the primary goal for this test, slag collection efficiency and char carry-over data were also of interest. It

was not possible to get good data for slag collection because we changed coals between this test and the last test (i.e., from Dorchester seam in the prior test to Pittsburgh No. 8 in this one). The cyclone bucket was nominally half full of char, which is considerable and consistent with tests conducted after installation of the slagging cyclone. Results derived from the particle collection filter downstream of the lean-burn/quench section indicated that 0.7% (5.4 lbs-char/896 lbs-coal) of the coal by weight was not burned. With the char problem persisting, it was hoped that the delivery of new coal would prove the hypothesis that our present coal had degraded and was responsible for the problem. Heat loss data was collected for the redesigned separator stage during this test. This data showed that the redesigned stage heat loss is lower than the old stage. The difference between the redesigned and old stages is 3% (i.e., the heat loss for the old stage is 14% and the heat loss for the redesigned stage was 11%).

Test SL1-2

This test continued exploration of exhaust gas sulfur reduction by primary zone sorbent injection. During this test 1133 lbs of Pittsburgh No. 8 coal were burned. This coal combustion portion of this test lasted 80 minutes and the equivalence ratio was held nearly constant at $\phi = 1.2$. Overall, no aberrant behavior occurred. The sorbent used for this test was a 1:1 mixture by weight of limestone and hematite. Hematite was selected over magnetite because our supply of hematite has a mesh size (400 mesh) more compatible with our limestone (325 mesh). The supply of magnetite has a larger particle size (100 mesh). A total of 76 lbs of sorbent mixture were injected over a 43 minute period. The sorbent flow was started at 29 minutes into the coal combustion portion of the test.

As discussed above in Test SL1-1, hematite was added to the sorbent to help the sorbent flow more smoothly and to act as a slag fluxing agent. Also, the sorbent injectors were moved inward so that wall slag flow in the primary zone would not foul the tips of the sorbent injectors.

In the mean, the Ca/S molar ratio was nominally 1, while the actual ratio varied between 0 and 3.5. After Ca/S molar ratio peaks of 3.5, sulfur reduction in the exhaust gas downstream of the lean-burn/quench section of nominally 20% were observed, which is far short of expected. Given the inability to achieve steady sorbent flow and Ca/S molar ratios in excess of 2, this result was not to surprising. Although the gain was small, it was an improvement over the last test (SL1-1).

The slag passing through the slag tap flowed extremely well when the sorbent was being injected. At times, it was difficult to distinguish between the water that condensed on the top of the slag bath chamber, which drips back into the slag bath water and the molten slag dripping through the slag tap. This observation is consistent with the observations of others, which is that iron oxide compounds act as a fluxing agent and reduce the slag viscosity with

all else being equal. The slag tap works very well, especially when a fluxing agent is introduced.

During tear-down and inspection after this test, the sorbent injectors were found to be almost free of slag. It was concluded that the poor sulfur reduction results for this test were due to the inability to achieve steady sorbent injection.

As expected, the cyclone slag bucket was full to the top with char and slag, mostly char. The mass balance between injected sorbent plus slag input from the coal did not agree well with what was collected in the separator slag bucket, slag bath chamber, cyclone, and cyclone slag bucket. This was in part due to the presence of modest amounts of char and otherwise due to changing operating conditions from one run to the next. The equivalence ratio for this run was $\phi = 1.2$ versus $\phi = 1.1$ for the last run. This change, by virtue of the difference in temperatures throughout the system, can shift slag from one area to the next, etc. Based on the mass of material collected by the particle probe located downstream of the lean-burn/quench section, which appeared to be almost entirely char (although it had a slight coating of sorbent, presumably from shutdown behavior), approximately 0.8% (8.5 lbs-char/1133 lbs-coal) passed through the system unburned.

Impact separator and slag-tap/quench chamber weights, as measured before and after this test, indicates that a collection efficiency of 78% was achieved by the new curved body impact separator.

Test SL1-3

This test continued exploration of exhaust gas sulfur reduction by primary zone sorbent injection. The new supply of coal arrived in time to be used. During this test 1146 lbs of new Pittsburgh No. 8 coal were burned. The coal combustion portion of this test lasted 87 minutes and the equivalence ratio was held constant at $\phi = 1.2$. The sorbent used during this test was a 1:1 mixture of limestone (325 mesh) and magnetite (100 mesh). A total of 98 lbs of sorbent were injected over a period of 33 minutes, which began 43 minutes after coal combustion commenced. Magnetite was selected as a diluent for limestone based on its good flow propensity and good fluxing characteristics.

From a combustion view point, this was not a smooth run. Difficulties were experienced for the first time in igniting the coal during coal combustion startup. The plan was to get to the desired equivalence ratio as soon as possible in order to have the maximum amount of time to perform sulfur reduction tests. As a result, coal combustion was started with a relatively high coal flow rate. The flame detector on the primary zone went out, indicating combustion had ceased. Basically, the combustor was operated too rich for some 20 minutes. This sooted all optical access windows and, without doubt, passed a certain amount of unburnt coal through the system. After shutting down the oil-fired preheat combustion, the system began to recover,

although it did take some time. There is good reason, therefore, to start fuel-lean and work up to the required equivalence ratio slowly (i.e., in nominally 15 minutes). This procedure helps to further preheat the system and minimizes soot/char formation.

After the system recovered, the sorbent flow was initiated, but some difficulty was experienced in achieving steady and smooth flow. At first the nitrogen jets in the cone at the base of the sorbent tank were run nearly constantly to insure sorbent flow was maintained. Thus, the indicated unsteadiness may have been impulse forces fouling the load cell based sorbent flow rate signal. Approximately half-way through the sorbent injection portion of the test, the nitrogen jets were shut-off and a steady flow of nominally 3 lbs/min was indicated. This corresponded to a Ca/S molar ratio of 1.5. The mean calcium to sulfur ratio over the sorbent injection period was 1.5 and had an apparent variation between 0 and 3. When the Ca/S ratio peaked at 3, the sulfur reduction after the lean-burn/quench section peaked at 45-50%. When the sorbent was flowing smoothly producing a Ca/S ratio of 1.5 the sulfur reduction was 30-35%. The attached figures show the key aspects of these results. In Figure 4-5 ϕ is the primary zone equivalence ratio and NO_x is the amount of NO_x present in ppm molar at Port No. 8. In Figure 4-6 the percent of total sulfur present is the total amount of sulfur present at either Port No. 3, which is the primary zone, or Port No. 8 which is downstream of the lean-burn/quench section; and Ca/S is the calcium to sulfur molar ratio produced by sorbent injection. These sulfur reduction results are the best to date with the present configuration and it is important to recognize that whatever sulfur is captured in the primary zone is not being released and appearing in the lean-burn/quench section. This indicates that spent sorbent is being tapped out before it releases the captured sulfur.

After concluding this test, system tear-down and inspection commenced. Char was found in the slag bath and the cyclone slag bucket was full. The particle sampler filter was full. Due to the large amount of char present, it was not possible to make any reasonable measurements of slag collection efficiency or material exhausted from the system.

During shutdown, the slag bath chamber overfilled with water. Inspection later found that the curved slag separator had developed a water leak. Close examination of the water flow rate data stored on disk for this part and test showed that the leak was greater than 3 gpm. When the leak began, it could not be determined, but it was deduced that the water flow rate to this part increased by 3 gpm as the system pressure dropped from 6 atm to 1 atm. The water leak was fixed by welding over the seam which had failed. Weight changes in the impact separator housing and slag bath chamber indicated a 76% slag collection efficiency was achieved with the new curved body impact separator.

Figure 4-5. ϕ and NO_x for Test SL1-3

Figure 4-6. Percent of Total Sulfur Present and Ca/S Molar Ratio for Test SL1-3

4.4 CHAR CARRY-OVER TESTS

Test CR1-1

This was the first test in a series of five tests to investigate the char problem. New Pittsburgh No. 8 coal was burned during the last test and a considerable amount of char was produced. The amount of char produced was not entirely out of line with what has been observed since the installation of the slagging cyclone. It was decided to test the char behavior of the new Dorchester seam coal during this test, rather than perform a repeat of the conditions selected for the last test. No sorbent was injected during this test. During this test 657 lbs of new Dorchester seam coal were burned. The coal combustion portion of this run lasted 50 minutes and the equivalence ratio was held nearly constant at $\phi = 1.2$. Overall, no aberrant behavior accompanied this run.

The particle sampling probe was operated in a slightly different manner in this test relative to prior tests. A nitrogen flow was driven through the probe into the combustor exhaust duct until the desired equivalence ratio was achieved. Before the coal ran-out and the system was shutdown, the flow to the probe filter was valved off. The amount of coal burned during the time the probe was sampling was recorded. This procedure was defined in order to ensure that elevated particle loading that may occur during startup or shutdown is not influencing particle sampling. During particle sampling 426 lbs of coal were burned. The change in particle filter weight implied that 4.3 lbs of char were exhausted from the system (examination of the filter suggested that most of the material collected was char). These results indicate that 1.0% (4.3 lbs-char/426 lbs-coal) of coal passed through the system unburned. This is roughly the same as measured in previous tests. The material in the cyclone slag bucket was separated into slag (8.3 lbs) and char (21.7 lbs). The amount of unburned, non-slag material collected by the cyclone turned out to be 3.3% of the total coal burned.

OTHER ONGOING EFFORTS

5.1 UPDATE OF REFERENCE SYSTEM DEFINITION

In a previous DOE program (Reference 2), studies showed that the lowest-cost environmentally acceptable method of generating electricity from coal was a coal-fired combustion turbine combined cycle plant employing on-site coal preparation. With the passage of several years time, it was felt necessary to update these economic studies, to maintain their validity. This was done, and a draft of the update was submitted to METC for review, during April 1990. Suggested revisions were received from METC, shortly after the beginning of this reporting period. The Reference System Definition Update report was revised during this reporting period and a final draft prepared and submitted to METC again for review. Included in the final draft was additional information with regards to coal beneficiation and its impact on overall plant economics. This data revealed no economic benefit is obtained from either physical or chemical coal beneficiation. This additional work scope was approved and funded by METC earlier in the reporting period. The final Reference System Definition Update report will be issued to METC prior to the end of September 1991.

CONCLUSIONS

During the period covered by this report, a third year of testing the subscale slagging combustor at Textron was completed. The subscale slagging combustor was reconfigured twice during the period: 1) prior to the first tests a slagging cyclone was added to the system between the impact separator and the lean-burn third stage, and 2) after the series of slagging cyclone tests a modified impact separator and real-time slag removal system were installed replacing the original impact separator with the symmetrical centerbody. The slagging combustor was also converted back to burning dry PC at the beginning of the period due to dry PC's superior performance versus CWM. As a result of three years of active testing in this program, the following conclusions may be drawn:

- It was possible to achieve the full design thermal capacity of 12 MMBtu/hr with the subscale slagging combustor, while burning 100% PC and operating at the design pressure of 6 atmospheres.
- Because of the separate-chamber, rich-lean design of the subscale slagging combustor, NO_x emissions that easily meet the NSPS limits are readily achieved.
- Because of its refractory-lined, toroidal-vortex design, the subscale slagging combustor readily achieves in excess of 99% carbon burn-out efficiency when 100% coal-fired.
- Objectives for third-stage exit temperature (1850°F), and exit temperature pattern factor (14%) were readily achieved.
- Overall pressure loss is currently an acceptable 6 to 8% with the cyclone separator.
- Sulfur reductions at the exit of the third stage up to 50% have been achieved. The NSPS goal is 70 to 90% reduction, depending on the coal's sulfur content.
- Feeding pulverized coal and sorbent into the combustor against 6 atm pressure has been shown achievable.
- Slag collection with the curved centerbody impact separator was only slightly degraded relative to the centerbody impact separator which has a 90% slag capture efficiency.
- Addition of the cyclone separator has provided exit particulate loadings on the order of 10 to 50 ppmw. When compared to test operating

conditions, NSPS emissions limit of 0.03 lbs/MMBtu would correspond to approximately 15 ppmw. This confirms that the cyclone is operating at approximately 90% collection efficiency, providing an overall slag collection efficiency of approximately 99%.

- Curved centerbody impact separator has a lower heat loss (approximately 3%) compared to the symmetrical centerbody design, 11% versus 14%, respectively.
- The real time slag tap has been effective in removing spent sorbent from the system and preventing reentrainment of the captured sulfur.
- After modifications were made to the slagging combustor system at the beginning of the reporting period, which included the addition of the slagging cyclone, a char carry-over problem developed. As a result, carbon burnout efficiency has been consistently lower (96-97%) during this period of testing. Efforts continue to try and quantify and resolve this phenomenon.

A final draft of the Reference System Definition Update report was prepared during this reporting period. As was reported in last years Technical Progress Report (Reference 3), the reference cost-of-electricity (COE) standard for this report is a 220 MW conventional pulverized coal-fired steam turbine generator plant with a flue gas desulfurizer (PC-FGD). This plant is fueled with Pittsburgh No. 8 coal (\$1.80/MMBtu). The COE margin, which is the difference between the COE of a candidate system and the COE of the PC-FGD, showed margins of 17.9 and 11.0% for the direct coal-fired combustion turbine combined cycle plants (CFCTCC) fueled with PC and CWM, respectively. Both the CWM- and PC-fired CFCTCCs and the PC-FGD steam plant have higher COEs than a combined cycle plant fueled by natural gas or oil at \$4.00/MMBtu (i.e., \$4.11/1000 scf and \$23.30/barrel for No. 2 oil). However an increase in gas or oil prices makes the CFCTCC less expensive to operate than its gas or oil fueled counter part. In fact, when comparing coal prices against a rising price in gas or oil, the economics switch immediately to any coal-fueled based power generation process. In addition this final draft report reveals that coal beneficiation, with respect to the CFCTCC plant, provides no economic benefit.

REFERENCES

1. "Advanced Coal-Fueled Gas Turbine Systems Annual Technical Progress Report for Period July 1988 - 1989," U.S. Department of Energy, Contract No. DE-AC21-86MC23167, Morgantown, WV, July 1989.
2. "Gas Turbine Systems Research and Development Program Topical Report," U.S. Department of Energy, Contract No. DE-AC21-83MC20324, Morgantown, WV, January 1985.
3. "Advanced Coal-Fueled Gas Turbine Systems Annual Technical Progress for Period July 1989 - June 1990," U.S. Department of Energy, Contract No. DC-AC21-86MC23167, Morgantown, WV, July 1990.
4. "Slag Utilization and Behavior in a Pressurized Gas Turbine Coal Combustor," Loftus, P.J, Diehl, R.C., Stickler, D.B., and Bannister, R.L., presented at Engineering Foundation Conference on Inorganic Transformations and Ash Deposition During Combustion, Palm Coast, FL, March 10-15, 1991.

END

**DATE
FILMED**

6 / 1 / 92