DOE/MC/26364-3230

THE MAGSORB PROCESS FOR BULK SEPARATION OF CARBON DIOXIDE

Progress Report for the Period August 28 - November 27, 1991

DOE/MC/26364--3230

DE93 008071

By

Ronald H. Carty
Richard A. Knight

Work Performed Under Contract No. DE-AC21-90MC26364

For

U.S. Department of Energy
Office Of Fossil Energy
Morgantown Energy Technology Center
Morgantown, West Virginia 26505

By

Institute of Gas Technology
Chicago, Illinois 60616

RECEIVED
FEB 22 1993
OSTI

December 1991

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Printed in the United States of America

**Available from
National Technical Information Service
U.S. Department of Commerce
5285 Port Royal Road
Springfield, VA 22161**

**NTIS price codes
Printed copy: A01
Microfiche copy: A01**

SUMMARY

The work performed during the eighth quarterly reporting period (August 28 - November 27, 1991) on the research program, "The MAGSORB Process for Bulk Separation of Carbon Dioxide," is presented in this report. This research program consists of the following eight tasks:

1. Test Plan Preparation
2. Facility Preparation and Equipment Modification
3. Preparation of Sorbent
4. Thermobalance Sorbent Tests
5. Cycle Tests of Sorbent in Packed-Bed Reactor
6. Analysis of Chemical and Physical Properties of Sorbent
7. Test Data Analysis and Interpretation
8. Systems Analysis and Technoeconomic Evaluation

The goal of this study is to investigate the removal of carbon dioxide from a fuel gas produced by a coal gasifier with a K_2CO_3 -modified MgO sorbent. The work consists of the measurement of the capacity and rates of absorption of the sorbent as a function of temperature, pressure, and gaseous contaminants. In addition, the effects of repeated absorption and desorption cycling on the physical and chemical properties of the sorbent will be studied.

During the eighth quarter of this program, 12 successful thermobalance tests were conducted, one with Batch 22, a K-free MgO standard prepared with the addition of NH_4HCO_3 as a pore structure control agent, and 11 with Batch 23, a MAGSORB batch made according to the grinding/repelletization procedure which resulted in the best compromise of absorption rate and homogeneity.

The Batch 22 standard showed no detectable absorption, confirming the importance of the role of potassium for effective CO_2 absorption by MAGSORB.

Batch 23 was tested with the standard gas (41.5 vol% CO_2 , 41.5% He, 17% H_2O), standard gas + 0.9 vol% H_2S , standard gas + 0.2 vol% NH_3 , simulated synthesis gas (42.4% CO_2 , 11.0% H_2 , 25.8% CO, 4.0% N_2 , 17.0% H_2O), and a dry

standard gas consisting of 50% CO₂ in helium. All tests were performed at 820° to 830°F and 300 psig total system pressure, with a CO₂ partial pressure of 131-134 psi in all tests except the dry standard gas test, in which the CO₂ pressure was 157 psi.

The standard gas gave typical asymptotic weight gain curves with a mean absorption of 70.1%±12.2% of stoichiometric (95% error limits) after 30 minutes. Standard gas + H₂S, standard gas + NH₃, and syngas gave significantly higher absorption rates, with 30-minute weight gains ranging from 86.4% to 96.7% of stoichiometric, while the dry standard gas did not show any statistically significant change in absorption rate. Desorption was essentially complete in less than 12 minutes with standard gas with or without H₂S or NH₃, but took about 30 minutes in the syngas mixture. In tests with added NH₃, the absorption rate appeared to be significantly enhanced, but there is some disagreement between thermobalance weight data in desorption tests and actual recovered sample weight measurements. This aspect of the test data is being further explored, and standard gas/NH₃ tests may be repeated.

Preparation of the packed-bed reactor system is proceeding on schedule, and a large batch of sorbent is currently being prepared for those tests.

In the next quarter, thermobalance tests with MAGSORB batches using Mg:K mol ratios of 6.0 and 8.0 will be conducted. Packed-bed cycling tests to assess the effects of absorption/desorption cycling on MAGSORB physical properties will also be conducted and completed, and the final report will be submitted.

TABLE OF CONTENTS

	<u>Page</u>
INTRODUCTION	1
TECHNICAL DISCUSSION	3
Task 1. Test Plan Preparation	3
Objective	3
Summary	3
Task 2. Facility Preparation and Equipment Modification	3
Objective	3
Summary	3
Plans for Next Quarter	3
Task 3. Preparation of Sorbent Material	4
Objective	4
Summary	5
Plans for Next Quarter	5
Task 4. Thermobalance Sorbent Tests	5
Objective	5
Summary	6
Plans for Next Quarter	11
Task 5. Cycle Tests of Sorbent in Packed-Bed Reactors	11
Objective	11
Summary	11
Plans for Next Quarter	11
Task 6. Analysis of Chemical and Physical Properties of Sorbent	12
Objective	12
Summary	12
Task 7. Test Data Analysis and Interpretation	12
Task 8. Systems Analysis and Technoeconomic Evaluation	13
Objective	13
Summary	13

LIST OF FIGURES

<u>Figure No.</u>		<u>Page</u>
1	Working Schematic of Packed-Bed Reactor System	4
2	Thermobalance Curves for Tests With Standard Gas	8
3	Thermobalance Curves for Tests With Standard Gas Containing H_2S	8
4	Thermobalance Curves for Tests With Simulated Synthesis Gas	10
5	Thermobalance Curves for Tests With Standard Gas Containing NH_3	10
6	Thermobalance Curve for Test With Dry Standard Gas	12

LIST OF TABLES

<u>Table No.</u>		<u>Page</u>
1	MAGSORB Batch 23 Analysis	5
2	Thermobalance Tests Performed During the Quarter	7

INTRODUCTION

Gasification of coal for synthesis gas production yields a mixture of CO, CO₂, H₂, H₂O, H₂S, and NH₃. The composition of the resulting gas is adjusted as required for various uses by removing or enhancing the concentration of the various components. For example, the use of the gas for methanol synthesis requires the enhancement of the H₂ content with respect to CO, removal of the bulk of the CO₂ and H₂O, and complete removal of the H₂S. This program deals with the bulk separation of carbon dioxide by application of the novel MAGSORB process.

In the MAGSORB process, the CO₂ is removed from raw fuel gases by a MgO/K₂CO₃ sorbent at elevated temperature (650° to 1000°F) and pressure (300 to 850 psi) to match with pressurized coal gasification and high-temperature water-gas shift operations. The CO₂ removal is conducted in a swing-bed absorption/desorption cycle in which MgO absorbs the CO₂ and the MgCO₃-containing spent sorbent is regenerated either by decreasing the pressure or by elevating the temperature to convert the MgCO₃ to MgO and CO₂. The overall objective of this program is to evaluate and develop a high-temperature process for CO₂ separation using a MgO/K₂CO₃ sorbent, which has the potential to significantly reduce the capital and operating costs for converting raw fuel gas to synthesis gas.

The specific objectives of this study will address the following topics:

- Preparation of a CO₂ sorbent material composed of MgO modified with K₂CO₃
- Investigation of the CO₂ absorption and desorption rates of the MgO/K₂CO₃ sorbent as a function of the system temperature and pressure
- Determination of the effects of H₂S and NH₃ on the absorption characteristics of the MgO/K₂CO₃ sorbent
- Testing of the change in absorption and desorption characteristics of the sorbent after 3, 7, and 20 absorption/desorption cycles
- Examination of the chemical and physical changes in the sorbent as a result of the absorption/desorption cycles
- A technoeconomic analysis and comparison of the novel CO₂ separation scheme with conventional alternatives, performed in conjunction with Bechtel National, Inc.

The objectives of the program tasks, their technical progress during the eighth quarter (August 28 through November 27, 1991), and the plans for the next quarter are presented in this report.

TECHNICAL DISCUSSION

Task 1. Test Plan Preparation

Objective

The objective of this task is to prepare a test plan including a baseline experimental program, chemical and physical analyses, and data and systems analyses to be accomplished in the project, and to define the schedule for performing these tasks.

Summary

The Test Plan for this project, which details the experiments to be conducted, their rationale, the analyses to be performed, and the handling of the experimental results, was completed and submitted for approval during the first quarter of the program. The implementation of the Test Plan was begun in January 1990.

Task 2. Facility Preparation and Equipment Modification

Objective

The objective of this task is to modify existing equipment and to fabricate new apparatus to be used in the experimental work. In addition, this task also include the operational shakedown of the apparatus to ensure minimal downtime during the experimental tests. This task includes operational checks of the thermobalance that will be used in Task 4 and construction of a laboratory packed-bed reactor for the cycle tests to be performed in Task 5.

Summary

Modifications of existing equipment to accommodate a packed-bed reactor were begun, and initial operational checks were completed. A working design of the packed-bed system is shown in Figure 1. System components, including fittings, tubing, a hot filter, and thermocouples, have been ordered.

Plans for Next Quarter

Construction of the packed-bed reactor system will be completed.

Figure 1. WORKING SCHEMATIC OF PACKED-BED REACTOR SYSTEM

Task 3. Preparation of Sorbent Material

Objective

The purpose of this task is to prepare the primary reference sorbent to be tested, as well as compositional variations of this sorbent, and a standard sorbent material consisting of unmodified MgO pellets, to be used for comparison. The sorbents to be used in the experimental tests include the following:

- A MgO standard
- A K_2CO_3 -modified MgO reference sorbent with an approximate Mg:K molar ratio of 7:1
- A K_2CO_3 -modified MgO sorbent with an approximate Mg:K molar ratio of 6:1
- A K_2CO_3 -modified MgO sorbent with an approximate Mg:K molar ratio of 8:1

Summary

This quarter, two sorbent batches (batch 22 and batch 23) were prepared. Batch 22 was an MgO standard that included the use of a pore structure modifier, NH_4HCO_3 , in the pellet preparation. This batch was prepared to determine whether NH_4HCO_3 alone could increase the CO_2 chemisorption rate in the absence of the potassium additive. Batch 23 was a large batch of NH_4HCO_3 -modified MAGSORB pellets made from ground and repelletized material from combined batches 10, 11 and 12. The chemical properties of Batch 23 are given in Table 1 below.

Table 1. MAGSORB BATCH 23 ANALYSIS

Wt% Mg:	40.2
Wt% K:	9.5
Wt% CO_2 :	10.0
Mg/K atomic ratio:	6.8
Relative standard deviation of Mg/K ratio:	2.7%

Plans for Next Quarter

A large batch similar to batch 23 will be prepared for packed-bed cycle testing. It is estimated that 100 g of sorbent will be required for the eight cycle tests planned. Two smaller batches with Mg:K mol ratios of approximately 6.0 and 8.0 will also be prepared for thermobalance testing. The grinding/repelletization technique with added NH_4HCO_3 will be used for all of these batches.

Task 4. Thermobalance Sorbent Tests

Objective

The objectives of this task are to determine the operating conditions of temperature and pressure to be used in the absorption and desorption of CO_2 by the sorbent and to investigate the effect of variation of the K_2CO_3 content of the MgO sorbent. Once the operating conditions and sorbent composition are fixed, the rates of absorption and desorption are determined. All of the

tests in this task are conducted in a high-pressure thermobalance containing the sorbent in a fixed bed exposed to excess flowing gas.

Summary

This quarter, 12 successful thermobalance tests were performed, one test with the batch 22 MgO standard and 11 tests with batch 23. Table 2 lists the conditions of the tests completed. Each absorption cycle was run for 32 minutes, and desorption cycles were run until the weight loss appeared to be complete. Absorption cycles were performed at 820°-830°F and 300 psig total system pressure, and desorption was conducted by switching to 100% N₂ at atmospheric pressure. The descriptions of the test results with each gas mixture are discussed individually below.

Standard Gas

The standard gas mixture used in thermobalance tests is provided by a 1:1 vol mixture of CO₂ and He, with steam added to approximate the steam content of a typical coal gasifier. The resulting test gas has the following composition: 41.5% CO₂, 41.5% He, 17% H₂O. At 300 psig test pressure, the CO₂ partial pressure is 131 psi.

One test (02-24) was performed with the standard gas mixture and Batch 22, an MgO blank prepared with NH₄HCO₃. No detectable weight gain was recorded after 32 minutes at 800°F and 300 psig. This verifies the importance of the potassium additive in promoting CO₂ absorption.

Three tests (02-25, 02-26, and 02-27) were conducted with the standard gas mixture and Batch 23 sorbent, resulting in the weight gain/loss curves displayed in Figure 2. Two of the tests were absorption only, and one was absorption/desorption. The CO₂ absorption at 30 minutes residence time, expressed as percent of stoichiometric, ranged from 61.5% to 76.1%, with a mean of 70.1% and a standard deviation of 6.2%. In the desorption cycle of Test 02-27, the sorbent desorbed very rapidly. Because of an electrical problem with the chart recorder, the initial desorption signal was interrupted, so a portion of the desorption curve in Figure 1 is interpolated. However, the remaining data show that desorption was essentially complete in 10 minutes or less. The indicated weight loss curve excursion below

Table 2. THERMOBALANCE TESTS PERFORMED DURING THE QUARTER

Test	Sorbent batch	Temp, °F	Pres, psig	Gas comp ^a	Mode ^b
02-24	22	830	300	Std	A
02-25	23	830	300	Std	A
02-26	23	830	300	Std	A
02-27	23	830	300	Std	A/D
02-28	23	830	300	Std+0.9% H ₂ S	A/D
02-29	23	830	300	Std+0.9% H ₂ S	A
02-30	23	820	300	Syngas	A
02-31	23	820	300	Syngas	A/D
02-32	23	830	300	Dry std	A
02-34	23	820	300	Std+0.2% NH ₃	A
02-35	23	820	300	Std+0.2% NH ₃	A/D
02-36	23	830	300	Std+0.2% NH ₃	A/D

^a "Std" = standard gas: 41.5% CO₂, 41.5% He, 17% H₂O; "Syngas" = 11.03% H₂, 25.8% CO, 42.4% CO₂, 4.0% N₂, 17% H₂O; "Dry std" = 50% CO₂, 50% He.
^b "A" = absorption; "A/D" = absorption/desorption

baseline may be attributed to CO₂ and H₂O desorption beyond the content of the original sample, but is also within the precision limits of the instrumentation.

Standard Gas with H₂S

Two tests (02-28, 02-29) were conducted with the standard gas containing 0.9 vol% H₂S, to determine if any reaction takes place between MAGSORB and H₂S or whether H₂S has any effect on the CO₂ absorption/desorption rates. One of the two tests also included the desorption cycle. Figure 3 shows the thermobalance curves for these tests. The mean CO₂ absorption at 30 minutes was 86.4%, with a standard deviation of 1.1%. These data indicated H₂S did not inhibit CO₂ absorption rate at these conditions, but in fact appeared to significantly enhance it. Analyses of the sorbents recovered from the tests showed no detectable sulfur, confirming the absence of a chemical reaction between H₂S and MAGSORB. Analyses also showed Mg:K ratios of 6.47 for Test 02-28 sorbent and 6.55 for Test 02-29 sorbent, indicating no significant changes in these ratios.

Figure 2. THERMOBALANCE CURVES FOR TESTS WITH STANDARD GAS

Figure 3. THERMOBALANCE CURVES FOR TESTS WITH STANDARD GAS CONTAINING H₂S

In the desorption cycle of Test 02-28, desorption is complete in about 10 minutes. As observed with the standard gas, the desorption weight loss curve falls slightly below baseline, but the discrepancy is within the precision limits of the instrumentation.

Synthesis Gas

Two tests, one absorption (02-30) and one absorption/desorption (02-31), were conducted with a simulated syngas mixture based on a Texaco coal gasifier. The syngas composition was 11.0% H₂, 25.8% CO, 42.4% CO₂, 4.0% N₂, and 17% H₂O. Figure 4 shows the results of these thermobalance tests, giving an average CO₂ absorption of 96.7% of stoichiometric limit at 30 minutes, with a standard deviation of 5.0%. As with the standard gas + H₂S, there is a significant increase in the CO₂ absorption rate in syngas compared to the standard gas. The desorption data show that the desorption rate is slowed somewhat in synthesis gas compared to the standard gas, taking about 30 minutes for essentially complete CO₂ desorption (within 5% of baseline).

Standard Gas With NH₃

Three tests (02-34, 02-35, and 02-36) were performed with the standard gas plus 0.2 vol% NH₃ added by including an appropriate concentration of ammonia in the water added for steam. Figure 5 shows the thermobalance curves for these tests, indicating a mean 30-minute weight gain of 92.1% of stoichiometric, with a standard deviation of 3.6%. This mean absorption rate is significantly higher than the absorption rate with standard gas. Analysis of the recovered sorbent from Test 02-34 showed no detectable N in the solid, and, based on analyzed CO₂ content, confirmed the absorption recorded on the thermobalance.

The desorption curves for Tests 02-35 and 02-36 flatten out after about 12 minutes, but remain well above baseline, which seems to indicate about 12% residual weight. However, these data are inconsistent with the actual measured weights of the samples recovered from the thermobalance, which showed 1% and 6% residual weight, respectively, for Tests 02-35 and 02-36. Further study of these samples and test data are continuing, in order to uncover possible explanations for these observations. If no satisfactory explanation can be discovered, the tests will be repeated.

Figure 4. THERMOBALANCE CURVES FOR TESTS WITH SIMULATED SYNTHESIS GAS

Figure 5. THERMOBALANCE CURVES FOR TESTS WITH STANDARD GAS CONTAINING NH_3

Dry Standard Gas

In Test 02-32, which was intended to be a test with standard gas + NH_3 , a pump malfunction prevented the entry of NH_3 -spiked water into the system. The decision was made to continue the test, resulting in a gas atmosphere of 50% CO_2 /50% He. The data, shown in Figure 6, indicate 73.5% of limiting CO_2 absorption at 30 minutes. Since the CO_2 partial pressure was 157 psi, compared to 131 psi in the standard gas tests with steam, the data is not directly comparable. However, if first-order kinetics are assumed for the chemisorption, the absorption rate for this gas mixture would fall within the 95% confidence limits observed for the standard gas. This indicates that there is no significant difference in CO_2 absorption rate with or without steam.

Plans for Next Quarter

Thermobalance tests will be conducted on MAGSORB batches with Mg:K ratios of approximately 5.0 and 8.0, prepared with the current grinding/re-pelletization technique with pore structure control. Absorption/desorption tests with the standard gas: NH_3 mixture may also be repeated if further data analysis of Tests 02-34, 02-35, and 02-36 does not turn up a satisfactory explanation of the non-return to baseline weight after the desorption cycle.

Task 5. Cycle Tests of Sorbent in Packed-Bed Reactors

Objective

The objective of this task is to perform absorption/desorption cycle tests in a laboratory packed-bed reactor to determine the effects of cycling on the reactivity and physical integrity of the sorbent. Tests of 3, 7, and 20 cycles are to be performed in duplicate with a simulated syngas atmosphere, for a total of 6 tests.

Summary

The packed-bed reactor is currently being prepared for operation under Task 2. No tests have yet been performed.

Plans for Next Quarter

Packed-bed tests will be completed during the next quarter.

Figure 6. THERMOBALANCE CURVE FROM TEST WITH DRY STANDARD GAS

Task 6. Analysis of Chemical and Physical Properties of Sorbent

Objective

The objective of this task is to analyze relevant chemical and physical properties of the sorbents used in thermobalance and packed-bed tests.

Summary

The analyses performed this quarter were the Mg, K, and CO₂ contents of the modified sorbents, the S contents of recovered sorbents from Tests 02-28 and 02-29, and the N content of recovered sorbent from Test 02-34. These results are reported in connection with the results of the testing of these sorbents.

Task 7. Test Data Analysis and Interpretation

Analysis and interpretation of the data obtained this quarter have been included in the discussion of the tasks in which the data were collected.

Task 8. Systems Analysis and Technoeconomic Evaluation

Objective

The objective of this task is to develop an optimum scheme for integrating the MAGSORB Process for CO₂ absorption with selected gasification and gas-upgrading processes for a technoeconomic analysis and comparison with conventional alternatives. In particular, this will entail a comparison of the estimated economics of the MAGSORB process with removal of CO₂ by conventional Rectisol technology using refrigerated methanol scrubbing, in the production of a synthesis gas for methanol production.

Summary

No work was scheduled on this task for this quarter.

END

DATE
FILMED
3/19/93