EGG-WTD-9985
January 1992
Volume 2

Received 6891
APR 27 1992

**Idaho
National
Engineering
Laboratory**

*Managed
by the U.S.
Department
of Energy*

**Technical Issues Associated with In
Situ Vitrification of the INEL
Subsurface Disposal Area
Volume 2: Application of Technical
Issues to the Acid Pit**

**Carl M. Stoots
Steven O. Bates
Richard A. Callow
Kris A. Campbell
Richard K. Farnsworth
Gretchen K. Gratson
Michael G. McKellar
David F. Nickelson
Calvin E. Slater**

*Work performed under
DOE Contract
No. DE-AC07-76ID01570*

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

This document contains new concepts or the author(s) interpretation of new calculations and/or measurements; accordingly, EG&G Idaho, Inc. is required by the United States Government to include the following disclaimer:

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights. References herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Technical Issues Associated with In Situ Vitrification of the INEL Subsurface Disposal Area

Volume 2: Application of Technical Issues to the Acid Pit

EGG-WTD--9985-Vol.2

DE92 012514

**Carl M. Stoots
Steven O. Bates
Richard A. Callow
Kris A. Campbell
Richard K. Farnsworth
Gretchen K. Gratson
Michael G. McKellar
David F. Nickelson
Calvin E. Slater**

Published January 1992

**Idaho National Engineering Laboratory
EG&G Idaho, Inc.
Idaho Falls, Idaho 83415**

**Prepared for the
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
Under DOE Idaho Field Office
Contract DE-AC07-76ID01570**

MASTER

ds
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

**Technical Issues Associated with In Situ Vitrification of the INEL
Subsurface Disposal Area**

Volume 2: Application of Technical Issues to the Acid Pit

Prepared by:

Carl M. Stoots, Chairman ISV Steering Committee

1/27/92
Date

Peer review by:

David Nickelson

1/27/92
Date

Approved by:

S. Kenneth Merrill

1/24/92
Date

ABSTRACT

In situ vitrification (ISV) has been identified as an alternative technology for remediation of the Acid Pit and Transuranic Pits and Trenches (TRU-PTs) that are present at the Idaho National Engineering Laboratory (INEL) Subsurface Disposal Area (SDA). However, a number of technical issues exist that must be resolved before ISV can be considered applicable to these waste sites. To assist in the ISV technology evaluation, an ISV Steering Committee was formed to identify, prioritize, and develop closure roadmaps for technical issues associated with ISV application at the INEL SDA. The activities of the ISV Steering Committee are summarized in three volumes of this report. Volume 1 identifies the systematic approach used to identify and prioritize the ISV technical issues, and briefly discusses the methodology that will be employed to resolve these issues. Volumes 2 and 3 discuss each technical issue in greater detail and suggest specific closure roadmaps to be used in resolving technical issues associated with ISV at the SDA Acid Pit and TRU-PTs, respectively. The report is a working document that will be updated as necessary to reflect the current evaluation strategy for the ISV technology.

SUMMARY

The Idaho National Engineering Laboratory (INEL) is currently in the process of evaluating different technology alternatives for remediating waste sites at the INEL Subsurface Disposal Area (SDA). Currently, in situ vitrification (ISV) is being evaluated for two operable units within the INEL SDA, the Acid Pit and the Transuranic-contaminated Waste Pits and Trenches (TRU-PTs). While ISV is relatively well-developed for contaminated soils, there are a number of issues that need to be resolved before ISV can be applied to the Acid Pit. In addition, the ISV technology still needs to be developed and understood before it can be considered applicable to buried mixed-waste sites, such as the TRU-PTs.

As a result, an ISV Steering Committee was formed to assist in the evaluation of ISV technology for remediating the INEL SDA. The purpose of the ISV Steering Committee is to define, prioritize, and develop roadmaps for closure of technical issues associated with the proposed application of ISV to the SDA. The activities of the ISV Steering Committee are summarized in this report. Volume 1 of this report identifies the methods used for identifying and prioritizing ISV technical issues associated with the Acid Pit and TRU-PTs, while briefly discussing the methodologies that will be employed to resolve these issues. Volumes 2 and 3 discuss each technical issue and specifically address the suggested resolution for technical issues associated with the Acid Pit and the TRU-PTs, respectively.

In Volume 2, specific closure roadmaps are identified for the 25 technical issues that have been identified as applicable to the Acid Pit. In addition, the report includes a short discussion of the 10 issues that were determined to be not applicable to the Acid Pit, and the reason for that determination. Based on the prioritization criteria discussed in Volume 1, the three most important ISV technical issues that need to be resolved for the Acid Pit are as follows:

- Subsurface contaminant migration due to thermal gradients in the surrounding soil
- Concerns over secondary waste stream concentrations, volumes, and remediation techniques
- Concerns over post-processing hood containment following an ISV melt.

Contaminant migration is a concern because of the potential for certain volatile and semivolatile contaminants to migrate away from the melt during ISV processing. Excessive migration could contaminate the soil surrounding the Acid Pit, which may require additional remediation measures if the level of contamination is high enough to classify the surrounding soil as hazardous. To close the issue, the report recommends the following steps: (a) characterize the site to determine the type of contaminants in the Acid Pit and the morphology of the soil, (b) evaluate potential controlling mechanisms or influencing factors that affect contaminant migration, (c) evaluate existing data on contaminant migration, (d) perform specially-designed laboratory tests that

look at contaminant diffusion through porous media, away from the high temperature ISV melt front, and (e) use the data to validate computer codes that predict contaminant migration potential for the full-scale ISV process.

Secondary waste streams of the ISV process include stack emissions, scrub solutions, high efficiency particulate air (HEPA) filters, and glycol cooling solutions. These waste streams need to be disposed of in an acceptable manner. In addition, the amount of secondary waste from the ISV process should be minimized, if possible. To close the issue, the following steps have been recommended: (a) characterize the site to determine the potential contaminants in the secondary waste streams, (b) use this data, along with existing ISV knowledge, to estimate the volume and contaminant concentration of all potential secondary waste streams, (c) identify requirements for disposal of these waste streams, and (d) evaluate potential methods for recycling or minimizing the amount of secondary waste generation.

Concerns over post-processing hood containment stem from the fact that latent heat in the ISV melt causes the surrounding soil isotherms to move farther away from the ISV product after the ISV process is complete. This could result in volatilization and migration of contaminants away from the melt or surrounding unprocessed wastes after ISV processing is complete. This may expose ISV operational personnel to hazardous waste during post-processing operations. To close the issue, the following steps have been recommended: (a) characterize the site to determine the potential contaminants that may volatilize and migrate away from the melt, (b) use existing data, modelling techniques and laboratory testing to predict the amount and type of contaminants that may be present as residues on the off-gas hood and ground surface, and the contaminant release rates and time periods following termination of an ISV melt, and (c) develop effective monitoring equipment to determine the necessary time periods for post-processing hood containment.

Because of the dynamic nature of the development process, the identification, prioritization, and proposed methods for closure of the ISV technical issues will change with time. Therefore, this report does not represent the final approach for resolving technical issues associated with ISV remediation of contaminated soils and buried waste sites. As conditions change, this report will need to be updated to reflect the current evaluation strategy for the ISV technology.

ACKNOWLEDGEMENTS

The authors would like to thank the following people for their contributions to the report:
R. W. Bonnenberg, C. Casey, V. Esparza, L. L. Fritz, C. J. Graden, M. Herd, P. Nagata,
N. L. Smith, P. A. Sloan, P. R. Stoots.

CONTENTS

ABSTRACT	iii
SUMMARY	v
ACKNOWLEDGEMENTS	vii
ACRONYMS	xv
1. INTRODUCTION	1
1.1 Background	1
1.2 Site Characterization Studies	2
1.3 Assumptions	4
1.4 Acid Pit Technical Issues	5
1.5 References	11
2. ENVIRONMENTAL ISSUES	12
2.1 Release characteristics of the product are an acceptable risk to the environment. (Priority: 5/25)	12
2.1.1 Description	12
2.1.2 Closure Requirements and Roadmap	12
2.1.3 Related Technical Issues	16
2.1.4 References	16
2.2 The homogeneity and other physical characteristics of the product are well characterized. (Priority: 14/25)	19
2.2.1 Description	19
2.2.2 Closure Roadmap and Requirements	20
2.2.3 Related Technical Issues	23
2.2.4 Reference	23
2.3 The degree and affects of metals pooling in the product are well characterized. (Priority: N/A)	26
2.3.1 References	26
2.4 The radiological characteristics of the product are acceptable. (Priority: 24/25)	27
2.4.1 Description	27
2.4.2 Closure Roadmap and Requirements	28

2.4.3	Related Technical Issues	28
2.5	Any enhancements to subsurface contaminant migration provided by subsurface structures (pipes, drum surfaces, voids, etc.) are within acceptable limits. (Priority: N/A)	30
2.6	Subsurface contaminant migration due to the effects of sealed containers is within acceptable limits (Priority: N/A)	31
2.7	Subsurface contaminant migration due to thermal gradients into surrounding homogeneous soil is within acceptable limits. (Priority: 1/25)	32
2.7.1	Description	32
2.7.2	Closure Requirements and Roadmap	33
2.7.3	Related Technical Issues	36
2.7.4	References	36
2.8	The melt width and depth are such that it captures the desired waste (Priority: 16/25)	37
2.8.1	Description	37
2.8.2	Closure Requirements and Roadmap	38
2.8.3	Related Technical Issues	40
2.8.4	References	40
2.9	Melt channelling or preferential flow of the melt through the path of least resistance is predictable and does not impact the capture of the waste intended to be captured (Priority: N/A)	41
2.10	The quantity of any uncaptured waste between adjacent vitrified blocks is acceptable (Priority: 7/25)	42
2.10.1	Description	42
2.10.2	Closure Requirements and Roadmap	43
2.10.3	Related Technical Issues	45
2.10.4	References	45
2.11	The quantity of any waste that may be encapsulated (unprocessed) within the glass is acceptable (Priority: N/A)	46
2.12	Secondary waste streams (effluents from the off-gas treatment system, scrub solutions, HEPA filters, decontamination solutions, etc.) are within acceptable limits (Priority: 2/25)	47
2.12.1	Description	47
2.12.2	Closure Requirements and Roadmap	48
2.12.3	Related Technical Issues	49
2.12.4	Reference	49

3. SAFETY ISSUES	50
3.1 The possibility of criticality is avoided. (Priority: N/A)	50
3.2 Hood containment seals are adequate (Priority: 8/25)	51
3.2.1 Description	51
3.2.2 Closure Requirements and Roadmap	51
3.2.3 Related Technical Issues	52
3.2.4 References	53
3.3 Any fires that occur do not affect the integrity of the hood. (Priority: 6/25)	54
3.3.1 Description	54
3.3.2 Closure Requirements and Roadmap	54
3.3.3 Related Technical Issues	55
3.3.4 References	55
3.4 A sidewall collapse does not impact the seal between the hood skirt and the ground (Priority: 13/25)	56
3.4.1 Description	56
3.4.2 Closure Requirements and Roadmap	57
3.4.3 Related Technical Issues	57
3.4.4 References	58
3.5 The melt and thermally altered zone do not extend laterally beyond the hood boundaries (Priority: 19/25)	59
3.5.1 Description	59
3.5.2 Closure Requirements and Roadmap	59
3.5.3 Related Technical Issues	61
3.6 Pressurizations due to explosions remain contained within the hood (Priority: 11/25)	62
3.6.1 Description	62
3.6.2 Closure Requirements and Roadmap	62
3.6.3 Related Technical Issues	64
3.6.4 References	64
3.7 Pressurizations due to the breach of pressurized sealed containers remain contained within the hood (Priority: N/A)	65
3.7.1 References	65
3.8 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained within the hood. (Priority: 21/25)	66

3.8.1	Description	66
3.8.2	Closure Requirements and Roadmap	66
3.8.3	Related Technical Issues	68
3.8.4	References	68
3.9	Increases in off-gas due to the melt encountering voids remain contained within the hood. (Priority: N/A)	69
3.10	Off-gas generation caused by combustion is contained within the hood. (Priority: 22/25)	70
3.10.1	Description	70
3.10.2	Closure Requirements	72
3.10.3	Related Technical Issues	72
3.10.4	References	73
3.11	Any matter ejected from the melt is contained within the hood. (Priority: 23/25)	74
3.11.1	Description	74
3.11.2	Closure Requirements and Roadmap	75
3.11.3	Related Technical Issues	76
3.11.4	References	76
3.12	Off-gas treatment system containment seals are adequate. (Priority: 12/25)	77
3.12.1	Description	77
3.12.2	Closure Requirements and Roadmap	77
3.12.3	Related Technical Issues	78
3.12.4	References	78
3.13	Off-gas treatment system capacity for treatment of products from within the hood is adequate (Priority: 15/25)	79
3.13.1	Description	79
3.13.2	Closure Requirements	80
3.13.3	Related Technical Issues	81
3.13.4	References	81
3.14	Pressurizations due to explosions remain contained within the off-gas treatment system. (Priority: 18/25)	83
3.14.1	Description	83
3.14.2	Closure Requirements and Roadmap	83
3.14.3	Related Technical Issues	85
3.14.4	References	85

3.15	Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately by the off-gas treatment system. (Priority: N/A)	86
3.16	Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately within the off-gas treatment system. (Priority: 20/25)	87
3.16.1	Description	87
3.16.2	Closure Requirements and Roadmap	87
3.16.3	Related Technical Issues	89
3.16.4	References	89
3.17	Increases in off-gas due to the melt encountering voids are contained and processed adequately within the off-gas treatment system (Priority: N/A)	90
3.18	Excessive off-gas generation caused by combustion is contained within the off-gas treatment system. (Priority: 9/25)	91
3.18.1	Description	91
3.18.2	Closure Requirements	93
3.18.3	Related Technical Issues	93
3.18.4	References	94
3.19	Any corrosion within the off-gas treatment system does not affect containment or effluents. (Priority: 10/25)	95
3.19.1	Description	95
3.19.2	Closure Requirements and Roadmap	96
3.19.3	Related Technical Issues	98
3.19.4	References	98
3.20	Risks due to any exposed waste are within acceptable limits. (Priority: 4/25)	99
3.20.1	Description	99
3.20.2	Closure Requirements and Roadmap	100
3.20.3	Related Technical Issues	102
3.20.4	References	102
3.21	Post-processing hood containment is maintained as required	104
3.21.1	Description	104
3.21.2	Closure Requirements and Roadmap	106
3.21.3	Related Technical Issues	107
3.21.4	References	107

3.22	Underground fires are avoided (Priority: 17/25)	108
3.22.1	Description	108
3.22.2	Closure Requirements	109
3.22.3	Related Technical Issues	110
3.22.4	References	110
3.23	Electrical hazards are controlled (Priority: 25/25)	111
3.23.1	Description	111
3.23.2	Closure Requirements and Roadmap	112
3.23.3	Related Technical Issues	113
3.23.4	References	113

FIGURES

2.1.	Roadmap to closure for Acid Pit Technical Issue 2.1 - Release characteristics of the product are an acceptable risk to the environment	14
2.2.	Roadmap for closure for Acid Pit Technical Issue 2.4 - Characterization of radiological acceptability	29

TABLES

1-1.	ISV environmental and safety issues identified by the INEL ISV Steering Committee	6
1-2.	Technical issues organized by section.	9
2-1.	Analytical procedures to be conducted for ISV product evaluation	24
2-2.	Summary of data uses of the different data types	25

ACRONYMS

AA	atomic absorption
ARARs	applicable and relevant or appropriate requirements
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CLP	Contract Laboratory Program
CRDL	contract-required detection limit
DCG	Direct Concentration Guidelines
DOE	Department of Energy
EPA	Environmental Protection Agency
ERP	Environmental Restoration Program
EM	electro-magnetic conductivity
GPR	ground-penetrating radar
ICP	inductively coupled plasma
ICP-MS	inductively coupled plasma-mass spectroscopy
ICPP	Idaho Chemical Processing Plant
IFT	Intermediate Field Test
INEL	Idaho National Engineering Laboratory
ISV	in situ vitrification
LSRT	large-scale radioactive test
MCC	Materials Characteristic Center
MDL	method detection limit
N/A	not applicable
NEC	National Electric Code
NEPA	National Environmental Policy Act
PSFT	pilot-scale field test

RCRA	Resource Conservation and Recovery Act
RI/FS	Remedial Investigation/Feasibility Study
RML	Radiation Measurements Laboratory
RWMC	Radioactive Waste Management Complex
SAP	sampling and analysis plan
SDA	Subsurface Disposal Area
SOW	Statement of Work
STEM	scanning transmitted electron microscopy
TAN	Test Area North
TCLP	toxicity characteristic leaching procedure
TOC	total organic carbon
TRU	transuranic
WINCO	Westinghouse Idaho Nuclear Company, Inc.
XRD	x-ray diffraction

Technical Issues Associated with In Situ Vitrification of the INEL Subsurface Disposal Area

Volume 2: Application of Technical Issues to the Acid Pit

1. INTRODUCTION

The Subsurface Disposal Area (SDA) Acid Pit is one operable unit being considered for in situ vitrification (ISV) at the Idaho National Engineering Laboratory (INEL). The ISV Steering Committee was formed to assist in the evaluation of ISV technology for remediating the INEL SDA. The purpose of the ISV Steering Committee is to define, prioritize, and develop roadmaps for closure of technical issues associated with the proposed application of ISV to the SDA.

Determination of the technical issues confronting such an application of ISV is directly dependent upon waste configuration and composition in the pit. The Waste Management/Environmental Restoration Department of EG&G Idaho, Inc., is currently compiling a comprehensive description of the Acid Pit. Their findings to date are summarized below.

1.1 Background

The Acid Pit is a contaminated soil site that was used from 1954 to 1970 for disposing low-level radioactive decontamination solutions and solvents. The Acid Pit is centrally located within the SDA, and its historic boundary measured approximately 197 x 104 ft. The pit extended down to the underlying basalt and was periodically backfilled with soil to cover disposed wastes. No consistent record-keeping was maintained during operation of the pit; but based on chemical waste disposal records, some of the suspected contaminants in the pit are nitric, sulfuric, and perchloric acids; normal and depleted uranium; hydrogen fluoride; tributyl phosphate; calcium hydroxide; sodium hydroxide; ferrocyanide; mercury; aluminum; chromium; zirconium; nitrites; organic wastes; and Amsco (a brand name of kerosene).¹

During past Radioactive Waste Management Complex (RWMC) operations, a second disposal location called the Chemical Waste Disposal Pit was in operation at the same time as the Acid Pit, and the terms "Acid Pit," "Chemical Waste Disposal Pit," and "Fluoride Pit" may have been used interchangeably to refer to either of these disposal locations. Thus, due to the past practice of using these three different pit names, it is not verifiable that all the substances listed on the chemical waste disposal records were disposed of specifically in the Acid Pit. However, personnel interviews and record searches indicate that some of the disposed of organic waste included carbon tetrachloride, trichlorethylene, trichloroethane, and tetrachloroethylene (see Reference 1). Radiologically-contaminated wastes disposed of in the Acid Pit are believed to have been primarily low-level wastes. The nuclides believed to be present in the low-level wastes are primarily uranium,

with potential for smaller quantities of strontium-90, cesium-137, cobalt-60, and transuranic radionuclides. The method of disposal usually consisted of draining containers or tanks directly into the pit. Neutralizing agents and/or soil covers were periodically applied over the waste.

Three surface geophysical studies were performed at the Acid Pit in 1989. Ebasco Services, Inc., conducted a seismic refraction survey at the pit to determine the depth to basalt.² Depths to basalt ranged from 15 to 21 ft under the Acid Pit. Geophysical studies completed by United Nuclear Corporation (UNC) Geotech indicated that the pit was apparently smaller than the size reported in the literature, contained no large metal objects, and suggested that contaminations may have migrated beneath the original base of the pit.³ An induction electromagnetic (EM) conductivity survey conducted by UNC Geotech indicated a central point of elevated conductivity within the pit, with decreasing conductivity in all directions outward from this point (see Reference 3). This seems to imply that much of the waste was disposed of at a single location in the Acid Pit. Also, the absence of large metal inclusions, such as drums or metal pipes, categorizes the Acid Pit as a contaminated soil site.

1.2 Site Characterization Studies

To augment the limited data available to characterize the Acid Pit, soil from the pit will be sampled and analyzed by the EG&G Idaho Environmental Restoration Program (ERP) in the fall of 1991. A sampling and analysis plan (SAP) for this preliminary site characterization of the Acid Pit has been prepared by ERP (see Reference 1). The SAP's objectives include evaluating the chemical and radiological data generated from this sampling effort to (a) provide treatability and technology demonstration information, (b) provide information to be used in risk assessments, (c) evaluate remediation alternatives, and (d) determine if additional characterization activities need to be performed.

The Acid Pit sampling will consist of sonic drilling and core retrieval at multiple depths and at preselected locations. Cores will be collected continuously from the ground surface to the basalt located 20 ft below the surface. Core samples collected from 4-6 ft, 9-12 ft, and 16-19 ft intervals have been selected by the EG&G Idaho ERP for chemical and radiological characterization. A complete list of the type of characterization data sought by ERP is included in the SAP (see Reference 1).

To evaluate the potential process limitations of ISV at the Acid Pit, the following supplemental characterization data have been identified (see Reference 1):

- Plutonium concentration in the Acid Pit area due to criticality considerations: kg/m^2 and total plutonium mass. According to *In Situ Vitrification of Transuranic Waste: An Updated Systems Evaluation and Applications Assessment*,⁴ the recommended operational limits of ISV at sites containing Pu are set at one-third the critical limits. A waste site should be capable of vitrification if it has an areal Pu concentration of

<1.0 kg/m² (33% of the 2.9 kg/m² critical areal concentration) with no potential for increasing concentration because of the presence of a vertical barrier, or if it contains a total Pu mass <0.6 kg (33% of the 1.7 kg minimum critical mass). Levels of concern for other critical radionuclides have not been determined. However, Pu generally accounts for over 90% of the critical material disposed of at the INEL. In addition, Pu has a relatively small subcritical mass limit, compared to other critical materials. Radiation Measurements Laboratory (RML) detection limits for Pu are sufficient to provide data quality compatible with the ISV level of concern.

- Metal analysis for evaluation of potential process performance: arsenic, beryllium, cadmium, lead, mercury, selenium, antimony, barium chromium, cobalt, copper, magnesium, manganese, nickel, silver, vanadium, zinc, tin, titanium, and zirconium. The metal analyses will be evaluated to provide baseline data on the types and concentration of inorganic contaminants in the melt. The data will also be useful in determining product quality of the monolith and assessing power requirements for the ISV operational system.
- Natural earth oxides for determination of power requirements for the ISV system and assessment of the ability of the technology to form a durable glass product: sodium, lithium, and potassium concentrations will be evaluated to determine the requirement for fluxant addition. The sum total of monovalent earth metals must be greater than 2%; if less than 2%, fluxant addition may be required. The concentrations of silica, aluminum, calcium, and iron are evaluated to determine if sufficient natural glass formers are present in the soil to produce a durable monolith. In order to produce a durable ISV monolith, where durable is defined as "resistant to weathering and dissolution," the soil at the Acid Pit should have silica concentrations in the 55-65 weight percent range. The calcium, aluminum, and iron oxide concentrations should be in the 30-40 weight percent range. Potassium, lithium, and sodium concentrations should be approximately 5 weight percent of the composition of the soil. These samples will be temporarily archived by ISV until additional funding is approved to perform the analyses.
- Electrical conductivity and 100 poise temperature (viscosity) analyses to assess power requirements for the operational system and to evaluate the mixing characteristics of the melt process. These samples will be temporarily archived by ISV until additional funding is approved to perform the analyses.
- Fusion and melting temperatures, thermal conductivity, and specific heat to (a) assess power requirements for the operational system, (b) evaluate product quality (specifically, the incorporation of various waste types into the monolith), and (c) validate melt growth predictions. These samples will be temporarily archived by ISV until additional funding is approved to perform the analyses.

- Nitrate and sulfate analysis for the following ISV data needs: (a) potential off-gas emissions for preparation of National Environmental Policy Act (NEPA), safety analysis documentation, and air quality permit applications, (b) power requirements for the ISV operational system, (c) ISV product quality, and (d) baseline data needed for determining technology effectiveness.
- Halogen analysis for (a) determining emissions for preparation of NEPA, safety analysis documentation, and air quality permit applications and (b) determine potential corrosion to the off-gas system.
- Total organic carbon (TOC) for determining the potential reduction/oxidation (redox) conditions and off-gas temperatures (heat load) of the operational system.
- Moisture content, bulk density, calculated porosity, saturated hydraulic conductivity, moisture retention curve, and unsaturated hydraulic conductivity analyses to provide data for input into computer models developed to determine operating procedures for the ISV technology and to determine technical specifications required to avoid off-normal events during an ISV test.

1.3 Assumptions

Since this report predates this site characterization study, certain assumptions concerning the composition of the Acid Pit had to be made to identify technical issues relevant to the Acid Pit. These assumptions were based on the waste disposal records and the geophysical surveys. When Acid Pit site characterization study results become available, the ISV Steering Committee can reevaluate the importance of each technical issue and concentrate closure efforts on those issues that may have the most impact on ISV remediation of the Acid Pit. The following main assumptions were used by the committee:

- Some of the waste disposed in the Acid Pit is radioactively contaminated. However, the uranium and transuranic (TRU) radionuclides are considered to be present in very small quantities. Until further information is available, it is assumed that the quantity of TRU waste existing in the pit is insignificant in having adverse effects on the ISV process. This assumption implies that the issue of criticality is not applicable to the Acid Pit.^a
- Based on the results of the geophysical studies, it is assumed that no large metal inclusions are in the Acid Pit. Also, it is assumed that the redox potential of the soil is not great and will not reduce significant amounts of metal oxides during the melt.

a. Transuranic radionuclides that emit neutrons may reach criticality if they are sufficiently concentrated or if the moderation properties of the waste site become suitably altered.

Therefore, the technical issue involving the degree and effects of metals pooling in the melt product is not applicable to the Acid Pit.

- The Acid Pit is thought to have homogeneous contaminated soil. Based on chemical waste disposal records, personnel interviews, and geophysical studies, it is assumed that there are no large subsurface structures such as pipes, drums, or other sizable inclusions or voids. However, the results from the EM conductivity survey suggest that there is a concentrated mass of contaminants in the Acid Pit. Technical issues deemed not applicable from this assumption include issues involving the effects that subsurface structures and large voids have upon contaminant migration, melt channelling, and excessive or uncontrollable pressurization or off-gas generation.

1.4 Acid Pit Technical Issues

To coordinate the resolution of technical issues related to ISV processing of buried waste, the ISV Steering Committee identified technical issues related to ISV at the INEL. Based on the above assumptions, 25 of the 35 technical issues were identified as being relevant to the Acid Pit. Issue categories, subcategories, and technical issues are listed in Table 1-1.

The ISV Steering Committee prioritized the technical issues according to nine criteria (see Volume 1). Table 1-2 lists each technical issue and its priority with the section number where it is discussed in this volume. Prioritization was necessary to facilitate the closure process by utilizing available resources, while at the same time striving to meet schedule, budget, and programmatic requirements. Prioritization also serves as a rational and technical basis for planning experimental and analytical programs supporting closure of these issues. Note that an issue's priority does not necessarily equate to, lessen, or increase its importance.

Table 1-1. ISV environmental and safety issues identified by the INEL ISV Steering Committee.

I. Environmental Issues

A. The durability/quality of product is acceptable.

1. Release characteristics of the product are an acceptable risk to the environment.
2. The product is well characterized.
 - a. The homogeneity and other physical characteristics of the product are well characterized.
 - b. The degree and effects of metals pooling in the product are well characterized.
3. The radiological characteristics of the product are acceptable.

B. Subsurface contaminant migration during processing is within acceptable limits.

1. Any enhancements to subsurface contaminant migration provided by subsurface structures (pipes, drum surfaces, voids, etc.) are within acceptable limits.
2. Subsurface contaminant migration due to the effects of sealed containers is within acceptable limits.
3. Subsurface contaminant migration due to thermal gradients into surrounding homogeneous soil is within acceptable limits.

C. Any residual waste is acceptable. That is, the quantity of any waste that is left unprocessed in the soil is acceptable.

1. The melt shape is predictable and suitable for capturing the waste intended to be captured.
 - a. The melt width and depth are such that it captures the desired waste.
 - b. Melt channelling or preferential flow of the melt through the path of least resistance is predictable and does not impact the capture of the waste intended to be captured.

Table 1-1. (continued).

- c. The quantity of any uncaptured waste between adjacent vitrified blocks is acceptable.
- 2. The quantity of any waste that may be encapsulated (unprocessed) within the glass is acceptable.
- D. Secondary waste streams (effluents from the off-gas treatment system, scrub solutions, HEPA filters, decontamination solutions, etc.) are within acceptable limits.

II. Safety Issues

- A. The possibility of criticality is avoided.
- B. Hazardous/radioactive material is adequately contained by the equipment.
 - 1. Hazardous/radioactive material is adequately contained by the hood.
 - a. Hood containment seals are adequate.
 - b. Any fires that may occur do not affect the integrity of the hood.
 - c. The hood covers adequate ground area to prevent releases.
 - (1) A sidewall collapse does not impact the seal between the hood skirt and the ground.
 - (2) The melt and thermally altered zone do not extend laterally beyond the hood boundaries.
 - d. The hood handles pressure transients adequately.
 - (1) Pressurization due to explosions remain contained.
 - (2) Pressurization due to the breach of pressurized sealed containers remain contained.
 - (3) Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained.

Table 1-1. (continued).

-
- (4) Increases in off-gas due to the melt encountering voids remain contained.
 - (5) Off-gas generation caused by combustion within the hood is contained.
 - e. Any matter ejected from the melt is contained by the hood.
 - 2. The off-gas treatment system provides adequate containment and maintains effluents to acceptable levels.
 - a. Off-gas treatment system seals are adequate.
 - b. Off-gas treatment system capacity for treatment of products from within the hood is adequate.
 - c. The off-gas treatment system handles pressure transients adequately.
 - (1) Pressurization due to explosions remain contained.
 - (2) Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately.
 - (3) Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately.
 - (4) Increases in off-gas due to the melt encountering voids is contained and processed adequately.
 - (5) Excessive off-gas generation caused by combustion is contained.
 - d. Any corrosion within the off-gas treatment system does not affect containment or effluents.
 - 3. Risks due to any exposed waste are within acceptable limits.
 - 4. Post-processing hood containment is maintained as required.
- C. Underground fires are avoided.
- D. Electrical hazards are controlled.
-

Table 1-2. Technical issues organized by section.

2. Environmental Issues	
2.1	Release characteristics of the product are an acceptable risk to the environment. (Priority: 5/25)
2.2	The homogeneity and other physical characteristics of the product are well characterized. (Priority: 14/25)
2.3	The degree and effects of metals pooling in the product are well characterized. (Priority: N/A)
2.4	The radiological characteristics of the product are acceptable. (Priority: 24/25)
2.5	Any enhancements to subsurface contaminant migration provided by subsurface structures (pipes, drum surfaces, voids, etc.) are within acceptable limits. (Priority: N/A)
2.6	Subsurface contaminant migration due to the effects of sealed containers is within acceptable limits. (Priority: N/A)
2.7	Subsurface contaminant migration due to thermal gradients into surrounding homogeneous soil is within acceptable limits. (Priority: 1/25)
2.8	The melt width and depth are such that it captures the desired waste. (Priority: 16/25)
2.9	Melt channelling or preferential flow of the melt through the path of least resistance is predictable and does not impact the capture of the waste intended to be captured. (Priority: N/A)
2.10	The quantity of any uncaptured waste between adjacent vitrified blocks is acceptable. (Priority: 7/25)
2.11	The quantity of any waste that may be encapsulated (unprocessed) within the glass is acceptable. (Priority: N/A)
2.12	Secondary waste streams (effluents from the off-gas treatment system, scrub solutions, HEPA filters, decontamination solutions, etc.) are within acceptable limits. (Priority: 2/25)
3. Safety Issues	
3.1	The possibility of criticality is avoided. (Priority: N/A)
3.2	Hood containment seals are adequate. (Priority: 8/25)
3.3	Any fires that may occur do not affect the integrity of the hood. (Priority: 6/25)
3.4	A sidewall collapse does not impact the seal between the hood skirt and the ground. (Priority: 13/25)

Table 1-2. (continued).

-
3.5	The melt and thermally altered zone do not extend laterally beyond the hood boundaries. (Priority: 19/25)
3.6	Pressurizations due to explosions remain contained within the hood. (Priority: 11/25)
3.7	Pressurization due to the breach of pressurized sealed containers remain contained within the hood. (Priority: N/A)
3.8	Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained within the hood. (Priority: 21/25)
3.9	Increases in off-gas due to the melt encountering voids remain contained within the hood. (Priority: N/A)
3.10	Off-gas generation caused by combustion is contained within the hood. (Priority: 22/25)
3.11	Any matter ejected from the melt is contained within the hood. (Priority: 23/25)
3.12	Off-gas treatment system containment seals are adequate. (Priority: 12/25)
3.13	Off-gas treatment system capacity for treatment of products from within the hood is adequate. (Priority: 15/25)
3.14	Pressurization due to explosions remain contained within the off-gas treatment system. (Priority: 18/25)
3.15	Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately by the off-gas treatment system. (Priority: N/A)
3.16	Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately within the off-gas treatment system. (Priority: 20/25)
3.17	Increases in off-gas due to the melt encountering voids are contained and processed adequately within the off-gas treatment system. (Priority: N/A)
3.18	Excessive off-gas generation caused by combustion is contained within the off-gas treatment system. (Priority: 9/25)
3.19	Any corrosion within the off-gas treatment system does not affect containment or effluents. (Priority: 10/25)
3.20	Risks due to any exposed waste are within acceptable limits. (Priority: 4/25)
3.21	Post-processing hood containment is maintained as required. (Priority: 3/25)
3.22	Underground fires are avoided. (Priority: 17/25)
3.23	Electrical hazards are controlled. (Priority: 25/25)
-

This volume consists of closure roadmaps for each of the 25 technical issues relevant to the Acid Pit. In general, those roadmaps include:

- description
- importance
- influencing factors
- suggested steps/requirements for issue closure
- references.

Brief paragraphs about issues not applicable to the Acid Pit are also included.

1.5 References

1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)
2. Ebasco Services Inc., Geophysics Report for the Subpit Sampling of Pit 9 and the Acid Pit in the Radioactive Waste Management Complex at the Idaho National Engineering Laboratory, March 1990.
3. J. C. Hasbrouck, Geophysical Surveys at INEL/RWMC Cold Pit, Acid Pit, and Pit 9, UNC Geotech GP-0-89-3, May 1989.
4. J. L. Buelt, V. F. FitzPatrick, C. L. Timmerman, J. G. Carter, and K. H. Oma, In Situ Vitrification of Transuranic Waste: An Updated Systems Evaluation and Applications Assessment, PNL-4800, DOE Contract No. DE-AC06-76RLO1830, March 1987.

2. ENVIRONMENTAL ISSUES

2.1 Release characteristics of the product are an acceptable risk to the environment.

(Priority: 5/25)

2.1.1 Description

2.1.1.1 Description of the Issue. This technical issue addresses the durability (release or dissolution characteristics) of the in situ vitrification (ISV) product produced by the ISV process to determine its ability to immobilize hazardous and radioactive waste components. The composition of the melt product is the primary factor in making an assessment of release characteristics of the product; therefore, it is important to properly characterize the Acid Pit to address this issue.

2.1.1.2 Importance. Since the primary purpose of the ISV process is to stabilize and immobilize radioactive and hazardous waste components, release characteristics of ISV waste forms must be known to provide for an accurate performance assessment. Failure to adequately bound the release characteristics of ISV waste forms from laboratory and field tests does not allow for the required data to be presented in the treatability study evaluating ISV in the Remedial Investigation/Feasibility Study (RI/FS) process. Release data is also required for input to the health-based risk assessment that is part of the RI/FS process. Furthermore, it must be shown that any demonstrations of ISV, such as in the Acid Pit, will not adversely affect the migration of hazardous and radioactive contaminants in the soil. Waste and soil composition are of prime importance with respect to product durability. The potentially high alkaline content in the Acid Pit may result in poor product durability.

2.1.1.3 Influencing Factors. Factors influencing the release characteristics of the product are the type, composition, and amount of contaminants in the Acid Pit, and the type, composition, and amount of soil in the overburden, underburden, and interstitial volume of the Acid Pit. Of particular interest is the amount of alkalis present in the Acid Pit since a high alkali content may result in poor product durability.

2.1.2 Closure Requirements and Roadmap

2.1.2.1 Assumptions. None.

2.1.2.2 Requirements and Steps to Close Issue. To make a proper decision about the suitability of the ISV process for remediation of the Acid Pit and to address the appropriate portions of the nine Environmental Protection Agency (EPA) Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) criteria, the following technical questions must be answered:

- Does the ISV product meet regulatory requirements [e.g., toxicity characteristic leaching procedure (TCLP)¹]?
- How does the ISV product compare (solubility and release) with other similar waste products?
- How does the ISV product compare (solubility and release) with natural analogs?
- What are the source terms for waste component release in the ISV product? (This will be a requirement for the health-based risk assessment modeling activities.)

There are currently no specific durability specifications established for ISV products. The minimum expected testing requirements will be those currently established for landfill disposal. One of those requirements is the TCLP test. However, the TCLP does not (a) address radioactive waste components, (b) provide a technical basis for assessing long-term durability, (c) provide a basis for a comparison to highly durable products or natural analogs, or (d) provide an assessment of the source term release rate of the waste component for risk assessment models. Therefore, additional durability tests must be conducted. These additional tests fall into two categories, comparative testing (comparing ISV products to similar waste forms and natural analogs) and testing to determine the intrinsic rate of the product dissolution (k_+). Each category of durability testing is discussed in detail in the following subsections. For each type of test, all major phases within the ISV product should be included, if possible. Where multiple phases cannot be separated, such as when devitrification produces an intimate mixture of different small grain crystalline phases, these phase mixtures should be tested as a single phase. Where possible, tests should be conducted at the largest scale possible. Laboratory-scale tests should be the minimum when testing the durability of the waste form.

A roadmap outlining the steps to closure is presented in Figure 2-1.

2.1.2.2.1 Regulatory Required Tests (TCLP)—One of the requirements for determining if waste is hazardous is the TCLP test. Waste is hazardous if it meets the criteria for the definition of hazardous waste, cited in the Code of Federal Regulations 40 CFR 261.3.² This definition includes criteria for ignitability, reactivity, corrosiveness, and TCLP toxicity. After being formed at temperatures greater than 1300°C, the ISV products are neither ignitable, reactive, nor corrosive. The TCLP test is designed to simulate the leaching process a waste undergoes if disposed of in a sanitary landfill. Accordingly, the ISV product will need to be tested for TCLP. However, since hazardous organic compounds will not be present in the glass after ISV processing, the organic analysis portion of TCLP will not be necessary. Organic compounds are destroyed by the extreme processing temperatures through pyrolysis.

2.1.2.2.2 Comparative Testing—To provide a scientific basis for evaluating the short- and long-term durability of ISV products, additional testing will be required. While the TCLP test satisfies compliance with EPA requirements for hazardous waste disposal, these tests have little value

T91 0806

Figure 2-1. Roadmap to closure for Acid Pit Technical Issue 2.1 - Release characteristics of the product are an acceptable risk to the environment.

in quantifying the release characteristics of the ISV product. The resulting product from the ISV process is similar to a number of natural analogs, and also to the waste forms evaluated for high-level nuclear waste. By comparing test results for ISV products to other well documented products and natural analogs, a baseline can be established for comparing the durability of the ISV product.

Assessing the long-term durability of ISV product is difficult because it requires extrapolation of data from short-term laboratory tests (a few hours to a few years) to geologic time frames. One way to assess the long-term durability performance is to compare the ISV product with natural analogs. A number of natural analogs are similar in composition and morphology to the ISV products. These include obsidian, basalts, tektites, and andesites (all of which can be millions of years old). The relative durability of many natural and ancient manmade glasses have been shown to bracket the durability of waste glasses.³⁻⁶ Thus, relating the behavior of the ISV products determined from short-term leach test and modelling results with the observed behavior of natural analogs provides an excellent means of validating the long-term stability of the ISV product.

Natural analogs also provide a basis for assisting in public acceptance of the ISV process and product. While the public has little understanding of the durability of high-level waste glasses, they may have appreciation for a comparison made of the ISV product to a "rock" they can pick up in the field that has been exposed to the environment for perhaps millions of years (geologic times).

The Materials Characteristic Center's (MCC) MCC-1 and MCC-3 test methods and current procedures were originally developed and written for application to high-level waste repositories in deep geological environments.^{7,8} The primary applications of the MCC tests will be to compare ISV products with information from existing data bases, and will have limited use for mass transport analysis. By conducting the MCC-1 and MCC-3 leach testing at 90°C, the results can be compared to the existing large data base of leaching data on the high-level glasses. One drawback to the MCC-1 procedure is that it requires a small monolithic sample. Inhomogeneities in the test samples, such as varying amounts of exposed crystalline phases or metals, may result in inconsistent results. If possible, MCC-1 testing should be conducted with single phase samples. The MCC-3 is similar to the MCC-1 test procedure, with two exceptions; the glass sample is ground to a powder, and glass powder and leachant are agitated by rotating the Teflon container in which the sample is placed. The elemental leachate concentrations from MCC-3 tests are estimated to represent long-term extrapolation of MCC-1 test results (from increased saturation of the leachates). This objective is achieved more rapidly in the MCC-3 test because higher ratios of glass surface areas/ leachate volumes (SA/V) are used than those used for the MCC-1 tests (2000 m⁻¹ and 10 m⁻¹, respectively). For evaluation and comparison of ISV products to similar waste form data, tests should be conducted with an SA/V of 2000 m⁻¹ in deionized water at 90°C for 28 days (a large amount of 7 to 90-day data also exists). Because a powdered sample is used for the MCC-3 tests, combinations of glass and devitrified phases may be tested together.

2.1.2.2.3 Intrinsic Rate of Dissolution (k_+)—The fastest rate at which a glass/ceramic will dissolve is the intrinsic rate of dissolution (k_+). This glass parameter has the most technical relevance when evaluating and predicting the dissolution (durability) behavior of the glass. The

intrinsic rate will be used as the source term in health-based risk assessment models to determine the risk associated with leaving the ISV product in the ground. This will be a conservative value for the source term as saturated or partially saturated ground water will slow the dissolution of the product significantly. A detailed discussion of intrinsic rate is presented in other documents.⁹⁻¹²

The intrinsic rate of dissolution (k_+) is measured by multiplying SA/V values by time. A low k_+ value means that the rate at which a glass/ceramic dissolves is very slow and that the resulting concentration of the dissolution solution is low. Low k_+ values are expected for the ISV product at normal, ambient conditions. Ambient conditions at the SDA are semi-arid and the average annual precipitation at the INEL is 8.5 inches.¹³ Saturation of the ISV product is not expected due to the relatively dry climate and the measures taken at the SDA to prevent flooding, direct surface water runoff, reduce water infiltration, and reduce soil erosion. Thus, the intrinsic rate of dissolution will be the limiting factor in the release rates of contaminants. In addition, because k_+ represents the absolute maximum dissolution rate, a conservative source term (the quantity of material available for release to the human environment during normal conditions or accidents) can be derived from an accurate determination of this parameter. This source term can be used in health-based risk assessment modelling.

Many chemical reaction rates, including k_+ , increase with temperature. Because of the high durability of the ISV product, it may not be possible to conduct leach testing at ambient ground temperatures (less than or equal to 20°C) because the resulting leachate concentrations may be below analytical detection limits. Conducting leach testing at higher temperatures (approximately between 40 to 90°C) will provide more detectable leachate concentrations. If leachates are tested at two or more temperatures, the Arrhenius activation energy of k_+ can be determined, from which the temperature dependence can be established. Using this temperature dependence, k_+ at ambient storage conditions can be calculated.

2.1.3 Related Technical Issues

2.2 The homogeneity and other physical characteristics of the product are well characterized.

2.1.4 References

1. Code of Federal Regulations, 40 CFR 268, Appendix 1, "Toxicity Characteristic Leaching Procedure (TCLP)," U.S. Environmental Protection Agency, Office of the Federal Register, Washington, D.C., 1988, pp. 724-738. (Appended to on March 29, 1990, U.S. Federal Register, Vol. 55, #61, pp. 11798-11877.)
2. Code of Federal Regulations, 40 CFR 261.3, "Definition of Hazardous Waste," U.S. Environmental Protection Agency, Office of the Federal Register, Washington, D.C., Revision 9, February 1, 1990.

3. M. J. Plodinec, C. M. Jantzen, and G. G. Wicks, "Stability of Radioactive Waste Glasses Assessed from Hydration Thermodynamics," Scientific Basis for Nuclear Waste Management, Vol. 7, edited by G. L. McVay, North-Holland, New York, 1984, pp. 755-762.
4. M. J. Plodinec, C. M. Jantzen, and G. G. Wicks, "Thermodynamic Approach to Prediction of the Stability of Proposed Radwaste Glasses," Nuclear Waste Management Advances in Ceramics, Vol. 8, edited by G. G. Wicks and W. A. Ross, The American Ceramic Society, Columbus, Ohio, 1984, pp. 491-495.
5. C. M. Jantzen and M. J. Plodinec, "Thermodynamic Model of Natural, Medieval, and Nuclear Waste Glass Durability," Journal of Non-Crystalline Solids, Vol. 67, 1984, pp. 207-233.
6. C. M. Jantzen, "Prediction of Nuclear Waste Glass Durability from Natural Analogs," Nuclear Waste Management II Advances in Ceramics, Vol. 20, editors D. E. Clark, W. B. White, and J. Machiels, American Ceramic Society, Columbus, Ohio, 1987, pp. 703-712.
7. Materials Characterization Center, "MCC-1P Static Leach Test Method," Nuclear Waste Materials Handbook Test Methods, DOE/TIC-11400, Rev. 7, Technical Information Center, Springfield, Virginia, 1986.
8. Materials Characterization Center, "MCC-3S Agitated Powder Leach Test Method," Nuclear Waste Materials Handbook Test Methods, DOE/TIC-11400, Rev. 7, Technical Information Center, Springfield, Virginia, 1986.
9. S. O. Bates, In Situ Vitrification Product Evaluation Strategy, EGG-WTD-9148, EG&G Idaho, Inc., Idaho Falls, Idaho, 1990.
10. J. G. Carter, S. O. Bates, and G. D. Maupin, In Situ Vitrification Of Oak Ridge National Laboratory Soil and Limestone, PNL-6174, Pacific Northwest Laboratory, Richland, Washington, 1987.
11. B. C. Bunker, B. W. Arnold, E. K. Beauchamp, and D. E. Day, "Mechanisms for Alkali Leaching Mixed Na-K Silicate Glasses," Journal of Non-Crystalline Solids, Vol. 58, 1983, pp. 295-322.
12. N. Kawanishi, H. Igarashi, H. Nagaki, and N. Tsunoda, Leaching Test on Chemical Durability of Glasses Containing Simulated High Level Wastes, PNCY N831-80-01, Power Reactor and Nuclear Fuels Corporation, Japan, 1980.

13. EG&G Idaho, Inc., Remedial Investigation/Feasibility Study Work Plan of the Subsurface Disposal Area, Radioactive Waste Management Complex at the INEL, EGG-WM-8776, December 1989.

2.2 The homogeneity and other physical characteristics of the product are well characterized. (Priority: 14/25)

2.2.1 Description

2.2.1.1 Description of the Issue. The ISV glass-like product may devitrify to crystalline material, resulting in an inhomogeneous product. This is due to the slow thermal diffusion, the long cooling times, and the elemental components of the product. Surface effects will also affect the morphology of the product. By identifying the major regions of the product, with stratified random sampling of those regions, sufficient data can be generated to determine the chemical, morphological, and durability properties of each region. This megascopic description of the product is important because the sampling strategy for all other characterization data needed cannot be detailed until the type and distribution of the major regions are known. The megascopic evaluation is also important in determining the percent volume that each region represents out of the total product volume. This information is required to allow for a bulk mass balance, an identification of potential reactions at regional interfaces, and the determination of an overall source term (the quantity of material available for release to the environment) for release rate and durability. The structure and elemental composition of each crystalline phase will reveal if any waste components have segregated into a less durable phase.

2.2.1.2 Importance. The ultimate goal of ISV as a remedial technology is to produce a durable product which will immobilize radioactive and/or hazardous constituents at a waste site. If the product devitrifies into several crystalline phases, or if the product has several distinct regions having different chemical and physical properties, the overall product may not meet the durability needs of ISV. Thus, it is important to know the physical characteristics and the homogeneity of the product in order to determine the durability and quality of the product.

2.2.1.3 Influencing Factors.

2.2.1.3.1 Composition of the Soil and Buried Waste—The composition of the soil and its buried waste will have a direct affect on the homogeneity and physical characteristics of the product. Since the Acid Pit is relatively void of large metal inclusions and sizeable voids, metal pooling and sidewall collapse are not expected to occur. Waste that contains significant amounts of metals has the potential for metals to separate from the melt and pool at the bottom of the melt, resulting in a product having unacceptable release rates and durability characteristics. Also, the reducing nature of the graphite electrodes along with organic content of the pit may cause certain metal oxides to reduce to metallic states and pool at the melt bottom. Melts that encounter sizeable voids may cause the sidewalls next to the melt to collapse onto the melt. Major sidewall collapses occurring towards the end of the ISV process may not get sufficiently incorporated into the melt, resulting in an inhomogeneous product that may have less durable physical properties.

Certain soil or waste properties can affect the formation of an acceptable product. For example, during initial scoping tests, it was found that the soil crystallized rather than vitrified with Na_2O concentrations in excess of 35-40 percent weight, even under rapid cooling conditions.¹ The Acid Pit may contain excessive or undesirable amounts of nitric acid and aluminum nitrate. By modifying the soil composition with soil additives, such as by adding a determined amount of CaO , undesirable soil/waste properties may be adjusted to suit ISV application at the Acid Pit.

2.2.1.3.2 Radiological Characteristics—Similar to metal pooling, waste that contains significant amounts of radioactive compounds could amass in one area of the melt product, generating undesirable or unacceptable levels of radioactivity from the final melt product. However, it is assumed that the amount of radioactive components in the Acid Pit is small enough to be soluble in the melt.

2.2.1.3.3 Dissolution Rates of Soil and Waste—As the melt front progresses, the melt may come in contact with individual pockets of waste which dissolve slower than the progressing melt front. If the power input is shut down before the surrounded waste can dissolve into the melt, a pocket of unprocessed waste may be present in the final glass product. If the amount of this encapsulated, unprocessed waste is sufficiently large, the product's durability or quality may be adversely affected.

2.2.1.3.4 Rate of Cooling—The rate of cooling may result in the product having inhomogeneous regions. Just as obsidian is formed when volcanic lava loses heat too quickly to permit crystallization, the ISV glass product is formed as the melted soil cools. A long cooling time may allow parts of the glass product to devitrify into crystalline phases. Because the ISV glass product is similar to obsidian in composition and weathering characteristics (durability), it is desirable to produce a homogeneous glass product with few crystalline phases. However, leach resistance studies on non-radioactive vitrified soil that contained large fractions of crystalline products have indicated that the crystalline phases are not detrimental to overall leach resistance (see Reference 1).

2.2.1.3.5 Sidewall Collapse—If the amount of sidewall collapse is great, and occurs towards the end or after ISV processing is complete, the melt may not have sufficiently processed the newly-added soil/waste. This may result in the top of the melt product being inhomogeneous and having physical properties that adversely affect the durability and quality of the product.

2.2.2 Closure Roadmap and Requirements

2.2.2.1 Assumptions. Waste disposal records indicate that the Acid Pit did not typically receive great quantities of radioactive or metal waste. Thus, it is assumed that the amount of radioactive components is below the solubility level for ISV melts, and that pooling of radioactive or metal components will not occur.

2.2.2.2 Requirements and Steps to Close Issue. Characterization of the ISV product can be divided into three parts, (a) sampling of the monolith and general structure, (b) evaluating the

chemical and morphological properties of the ISV product, and (c) evaluating the durability (release properties) of the ISV product. Parts 1 and 2 are addressed in this technical issue while the durability is addressed separately, but with input from the closure of this technical issue.

The sampling of the monolith and general structure includes a physical description of the ISV product and an evaluation of some important physical properties (i.e., the major phases observed during excavation, coring, and sampling of the products; and the density and volume of each phase).

Evaluating the chemical and morphological characteristics includes the elemental and radiological compositions, identification of crystalline phases, distribution of waste components in vitreous and crystalline phases, and redox state of the glass.

Because of the unique types of sampling and analysis needed to characterize the ISV product, it is difficult to generate data that meet the rigorous analytical levels generally required by the EPA for risk assessment and the technology evaluation (Analytical Levels III or IV) (see Reference 2). Most of the ISV product evaluation data quality needs are considered to be EPA Analytical Level V (for non-conventional parameters), due to the non-standard tests [excluding the Toxicity Characterization Leaching Procedure (TCLP)] for ISV product evaluation.

2.2.2.2.1 Sampling and General Structure—The primary objective of the product evaluation sampling activities of the laboratory and field tests are to provide representative samples in sufficient number and quantity that provide a general description of the ISV monolith and detailed evaluation of the properties of the different phases observed. Sampling will be conducted using cores drilled through the monolith and/or a fracture of the monolith. A megascopic, bulk, physical description of an ISV product is the necessary first step in the characterization of that material. The megascopic description provides the most general information gained during the material characterization processes. It is a narrative and photographic record of the type and distribution of those regions that can be distinguished and defined by the unaided eye.

Previous ISV tests conducted at other sites indicate that there are generally five distinct regions within a typical ISV product that should be evaluated: (a) the vitreous frothy surface layer, (b) the partially reacted "rind" layer, which marks the vitrification surface of the monolith, (c) the glass material, (d) the crystalline devitrified material near the center of the monolith, and (e) the potential "pools" or segregation of metals at the electrodes or at the bottom of the monolith.

A megascopic description of the monolith is important because the sampling strategy of all other characterization techniques cannot be detailed until the type and distribution of the megascopic regions are known. A random sampling of the whole monolith may fail to sample each region sufficiently. By identifying the major regions of the monolith, with stratified random sampling of those regions, sufficient data can be generated to determine the chemical, morphological, and durability properties of each region. The megascopic evaluation will also assess the volume percentage of the total that each region represents. This information is required to allow for a bulk mass balance, an identification of potential reactions at regional interfaces, and a determination of

a bulk durability (release) source term. Additional samples will be taken and archived. This will allow for further testing if regulatory requirements change or additional data is required.

2.2.2.2.2 Chemical and Morphological Properties—Evaluating the chemical and morphological properties is necessary to determine the elemental composition of the ISV product as a whole, by region, and of each phase in the region. Because of the many elemental components, the thermal diffusion of the glass, and the long cooling times of the monolith, some of the glass will devitrify to crystalline material. The structure and elemental composition of each crystalline phase will reveal if any waste components have segregated into possibly less-durable phases or migrated to interface boundaries between the metal, glass, and crystalline phases.

Several techniques will be used for this portion of the evaluation. Inductively coupled plasma (ICP) atomic emission spectroscopy will be used to determine the overall elemental composition of each region and phase. The ICP will also provide the elemental composition to be used to determine normalized release in the durability tests. While ICP will be the main elemental analytical technique, other analytical techniques will be used to augment ICP for specific elements and data drive needs. These include ICP-mass spectroscopy (ICP-MS), atomic absorption (AA), and scanning transmitted electron microscopy (STEM).

A scanning electron microscope with energy dispersive analysis by an x-ray (SEM/EDAX) microprobe will be used to observe the crystalline types present. Elemental mapping of SEM scans and EDAX microprobe analysis will indicate the semiquantitative elemental makeup of each phase. This will indicate if any detectable segregation of waste components has occurred. Particular attention will be given to the interface boundaries between the metal, glass and crystalline phases. The SEM will also provide micrographs for image analysis and determination of the percent of crystalline material.

X-ray diffraction (XRD) will be used to identify the structure of the crystalline material. When used in conjunction with the SEM/EDAX data, the specific crystalline phases that result from devitrification near the center of the monolith can be determined. Knowledge of the crystalline morphology will help determine how waste components are incorporated into the ISV product, allow for comparison to natural analogs, and assist in assessing long-term behavior of the waste (e.g., geochemical solution and reaction path modeling).

The redox state of the ISV product should also be determined. This will provide an indication as to the valence state expected for waste components and will help predict in which phase waste components will be partitioned within the ISV product. For example, if conditions within the ISV melt are sufficiently reducing, elements such as chromium, lead, or cadmium may be present in the metallic state. If in the metallic state, metals may combine with other metals within the melt and partition to the bottom of the ISV product. The redox state will be determined by analyzing the $\text{Fe}^{+2}/\text{total Fe}$ ratio in the glass using a compleximetric, spectro-photometric technique (see Reference 2).

A summary of the analytical procedures and their output data is presented in Table 2-1. A summary of the data uses of the different data types is presented in Table 2-2.

2.2.3 Related Technical Issues

- 2.1 Release characteristics of the products are an acceptable risk to the environment.

2.2.4 Reference

1. J. L. Buelt, V. F. FitzPatrick, C. L. Timmerman, J. G. Carter, and K. H. Oma, In Situ Vittrification of Transuranic Waste: An Updated Systems Evaluation and Applications Assessment, PNL-4800, DOE Contract No. DE-AC06-76RLO1830, March 1987.
2. D. S. Goldman and D. W. Brite, "Redox Characterization of Simulated Nuclear Waste Glass," Journal of American Ceramic Society, Vol. 69(5), 1986, pp. 411-413.

Table 2-1. Analytical procedures to be conducted for ISV product evaluation.

Analytical Procedure	Variable/Parameter
Scanning electron microscopy with energy dispersive analysis by X-ray, microprobe (SEM/EDAX)	Waste component segregation, elemental mapping, input to image anal., phase identification, phase %vol, partial size
X-ray diffraction (XRD)	Phase identification, phase %vol
Density	Specific gravity
Image analysis	phase %vol
Optical analysis	Sampling and test requirements, phase identification, phase %vol
Inductively coupled plasma atomic emission spectroscopy (ICP) and atomic absorption (AA)	Elemental analysis
Radionuclide analysis	Radionuclide content
Redox state	$\text{Fe}^{+2}/\Sigma\text{Fe}$ (oxidation state of waste form)

Table 2-2. Summary of data uses of the different data types.

DATA USES	ICP	SEM/EDAX	PHASE ID (XRD)	LEACH TESTS			FORWARD RATE OF DISSOLUTION
				EPTox/TCL P	MCC-1	MCC-3	
ISV feasibility study for input to the SDA RI/FS	X	X	X	X	X	X	X
ISV process modelling activities	X	X	X				X
Health-based risk assessment modelling activities	X		X	X			X
Laboratory ISV testing (input to the types of tests that need to be conducted)	X	X	X	X			X
ISV field test	X	X	X	X			X
Buried Waste Program	X	X	X	X	X	X	X
ISV Durability activities	X	X	X	X	X	X	X

2.3 The degree and affects of metals pooling in the product are well characterized.

(Priority: N/A)

In wastes where large amounts (approximately >4 wt%) of metals are present, (possibly as contaminated metal objects, metal drums used as disposal containers, metallic hazardous waste components, etc.) there is the potential for metals to separate from the melt and form a metal pool at the bottom of the melt. As the melt interacts with these metals, some of the metals (depending on the type and total amounts) dissolve into the glass matrix until the glass becomes saturated. This generally requires the metals to oxidize with other compounds, forming metal oxides which are more soluble in the melt. Once the melt solution becomes saturated with metal cations, the denser metal compounds amass and sink to the bottom of the melt, forming a metal pool at the bottom of the melt. Metal pools can also form within the melt due to redox reactions with the cations in the melt and the graphite electrodes. Redox states within previous melts have had $\text{Fe}^{+2}/\text{total Fe}$ ratios of approximately 0.8 to 0.95 (very reducing). Both these reactions and the formation of some metal pools have been observed in laboratory and field tests evaluating Pit 9 waste and soils.^{1,2}

Based on current Acid Pit site characterization data, the amount of metallic material within the Acid Pit is too small to result in significant amounts of metal pooling.³ This issue has been determined not to be applicable to the Acid Pit at this time. If the current site characterization activities result in significantly different site/waste data, this issue will be reevaluated.

2.3.1 References

1. R. K. Farnsworth, K. H. Oma, and M. A. H. Reimus, Crucible Melts and Bench-Scale ISV Test on Simulated Wastes in INEL Soils, PNL-7344, Pacific Northwest Laboratory, Richland, Washington, 1990.
2. R. A. Callow, L. E. Thompson, and J. R. Weidner, In Situ Vitrification Application to Buried Waste: Interim Report of Intermediate Field Tests at Idaho National Engineering Laboratory, EGG-WTD-9422, EG&G Idaho, Inc., Idaho Falls, Idaho, 1991.
3. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

2.4 The radiological characteristics of the product are acceptable. (Priority: 24/25)

2.4.1 Description

2.4.1.1 Description of the Issue. The radiological acceptability of the ISV product is generally based on the radioactive dose that is given off and the concentration of radionuclides within the waste. During the ISV process the waste undergoes radical physical changes in structure, volume, density, and component distribution. These changes could alter the radiological characteristics of the ISV product to the point where the waste classification of the product would change or handling requirements (as in the case of retrieval) would be restrictive.

The ISV processing of buried waste in Subsurface Disposal Area (SDA) soil results in an overall volume reduction of approximately 50-65%. When radionuclides are present, volume reduction increases their concentration (measured as nanocuries/cubic meter). This may result in an increase in the amount of radiation at the surface of the product (millirems/hour). However, emanation of radioactivity from existing ISV products is low.

Because the ISV process incorporates additional material (as soil) into the waste, the radionuclide concentration measured as nanocuries/gram decrease. However, waste component segregation potentially could concentrate some radionuclides into locally higher concentrations, such as in the case of metal pooling.

2.4.1.2 Importance. Since the primary goal of ISV as a remedial technology is to immobilize radioactive and/or hazardous constituents at a waste site, it is important to know if the radiological characteristics of the product are acceptable. Although the contents of the Acid Pit are not yet detailed, records indicate that the Acid Pit did not typically receive great quantities of radioactive waste. The small amount of radioactive components in the Acid Pit will be soluble in the melt. The risk that ISV will produce a product with unacceptable levels of radiation at the Acid Pit is much lower than if ISV was used on pits and trenches known to contain various amounts of high-level radioactive waste, such as Pit 9.

2.4.1.3 Influencing Factors. The major factor affecting the radiological characteristics of the product is the type and amount of radioactivity in the buried waste at the Acid Pit. High-level waste containing transuranics would require increased monitoring and assessment of the final product. Another factor is the location of the radioactive waste. Hot spots of radioactivity, could be elevated during volume reduction.

2.4.2 Closure Roadmap and Requirements

2.4.2.1 Assumptions. Waste disposal records indicate that the Acid Pit did not typically receive great quantities of radioactive waste. Thus, it is assumed that the final ISV product will not be not be significantly radioactive, and that its radiological characteristics will be acceptable.

2.4.2.2 Requirements and Steps to Close Issue. The roadmap for closure of this issue is presented in Figure 2-2. This issue can be closed with calculations and little or no experimental work outside that required in the related technical issues.

2.4.3 Related Technical Issues

- 2.2 The homogeneity and other physical characteristics of the product are well characterized.
- 2.3 The degree and affects of metals pooling in the product are well characterized.
- 3.1 The possibility of criticality is avoided.

T91 0807

Figure 2-2. Roadmap for closure of Acid Pit Technical Issue 2.4 - Characterization of radiological acceptability.

**2.5 Any enhancements to subsurface contaminant migration
provided by subsurface structures
(pipes, drum surfaces, voids, etc.)
are within acceptable limits.
(Priority: N/A)**

Subsurface contaminant migration can be enhanced by subsurface structures in the waste such as pipes, drum surfaces, and substantial voids. Since information from geophysical surveys conducted at the Acid Pit indicates the absence of large inclusions of pipes, drums, or substantial voids, the ISV Steering Committee has determined that this technical issue is not applicable to the Acid Pit.

2.6 Subsurface contaminant migration due to the effects of sealed containers is within acceptable limits. (Priority: N/A)

Sealed containers have the possibility of increasing subsurface contaminant migration if they become breached during the ISV process and release significant amounts of radioactive and/or hazardous waste during the melt. Since information from geophysical surveys conducted at the Acid Pit indicates the absence of large inclusions of drums and containers, the ISV Steering Committee has determined that this technical issue is not applicable to the Acid Pit.

2.7 Subsurface contaminant migration due to thermal gradients into surrounding homogeneous soil is within acceptable limits.

(Priority: 1/25)

2.7.1 Description

2.7.1.1 Description of the Issue. In situ vitrification of contaminated soil has been studied for several years. However, subsurface contaminant migration into the surrounding soil due to thermal gradients from the ISV process has not been fully tested. Buried waste typically contains contaminants that have volatile or semivolatile properties. These contaminants tend to be very mobile and, through several mechanisms or in different physical forms (liquid, gas), can leach through waste pits and soil into deeper, uncontaminated portions of the ground. Heat from the ISV melt process could initiate and/or accelerate this movement of contaminants into uncontaminated or inaccessible portions of the soil.

The transport of volatile and semivolatile contaminants away from the molten ISV melt front is a highly complex phenomenon, and is influenced by a number of potential mechanisms. One of these mechanisms is called vapor retreat.¹ Vapor retreat is the vaporization of volatile and semivolatile compounds from the heat of the melt process and their movement away from the melt front into cooler portions of the soil. As these compounds are transformed into vapors, their ability to move through the soil is accelerated. Vapor retreat of compounds through the soil will continue until a zone of soil is reached where the soil temperature is sufficient to cause condensation of those vapors, thus limiting their mobility. Vaporization and migration rates are specific to each contaminant, due to their varying vapor pressures. Other mechanisms that have been postulated to either inhibit contaminant migration away from the melt or even favor contaminant migration into the melt are molecular diffusion, carrier gas transport, capillary forces, soil column flow resistance, and liquid-vapor soil sorption.²⁻⁴ More ISV tests are necessary to determine which of these contaminant transport mechanisms are relevant to the Acid Pit. In addition, the influence of each relevant mechanism needs to be better quantified.

2.7.1.2 Importance. Excessive subsurface contaminant migration could contaminate the surrounding soil of the Acid Pit. Soil contaminated by the ISV process could require remediation if tests, such as the toxicity characteristic leaching procedure (TCLP), classified the soil as hazardous waste, as defined by the Code of Federal Regulations 40 CFR 261.3.⁵ Remediation efforts may be complicated by the potentially massive and durable melt product lying above the contaminated soil. Further, if remedial processes were not available or feasible for newly contaminated portions of the soil, the contamination of the Snake River Plain Aquifer might be accelerated due to migration of contaminants from the ISV process at the Acid Pit. These issues, if not resolved, could result in the failure of ISV as a viable remedial technology for the INEL.

The potential for subsurface contaminant migration magnifies if there are large quantities of volatile and/or semivolatile compounds in the Acid Pit. Although records indicate that the Acid Pit does not contain bulk quantities of volatile and semivolatile organic compounds in waste containers, they do reveal that some organic waste was dumped into the pit. The extent of subsurface contaminant migration cannot be fully assessed until more information is known about the types and concentrations of waste in the Acid Pit.

2.7.1.3 Influencing Factors. Factors that may influence the migratory nature of specific contaminants are thermal gradients produced by the melt, depth and composition of contaminated soil, differential vapor pressures of various contaminants, and ISV process variables (melt rate, power level, etc.).

2.7.1.3.1 Thermal Gradients—During ISV operations, thermal gradients are produced by extreme temperatures. To accurately assess the possibility of subsurface contaminant migration, it is necessary to predict and monitor the temperature distribution in the surrounding soil resulting from the melt process.

2.7.1.3.2 Contaminated Soil Composition—The possibility of subsurface contaminant migration is heavily dependent on the concentration, type, and depth of hazardous waste buried in the Acid Pit. Clearly, the greater the amount of volatile and semivolatile material buried in the soil, the greater the chance for subsurface contaminant migration. In addition, other types of hazardous waste could contribute to the vaporizable, migratory nature of the contaminants, via "carrier-gas effects." The migration of organic chemicals near the melt can be significantly affected by gaseous convection, which is also known as carrier-gas transport. Gaseous convection results when an organic chemical is swept along the flow path of another gas present in much higher quantities (see Reference 4).

2.7.1.3.3 Differential Vapor Pressure—Because of the differing vapor pressures of each volatile or semivolatile contaminant, the potential for migration away from the ISV melt front, via vapor retreat, will be different for each particular contaminant. The magnitude of this difference, and its effect, needs to be evaluated for each contaminant in question.

2.7.1.3.4 ISV Process Variables—Subsurface contaminant migration may also be affected by the downward rate of the melt. ISV process variables, such as electrode temperature and depth, are used to control the downward rate of the melt. In addition, the ratio of migration to volatilization may also be affected by the depth of contamination in the pit.

2.7.2 Closure Requirements and Roadmap

2.7.2.1 Assumptions.

- Records indicate that some organic waste was dumped into the Acid Pit. This organic waste may include volatile and semivolatile organic

compounds. Some records indicate that a mixture of tributyl phosphate (a semivolatile compound) and Amsco (a brand name of kerosene) was dumped into the Acid Pit.

- The relative moisture content and concentration of volatile and semivolatile materials in the Acid Pit should not be enough to contribute to carrier-gas effects.

2.7.2.2 Requirements and Steps to Close Issue.

1. Characterize the site. Determine the types and concentrations of the volatile and semivolatile substances present in the Acid Pit according to the sampling and analysis plan for the Acid Pit.⁶
2. Evaluate the potential controlling mechanisms or influencing factors that may contribute to contaminant migration. Document through modelling techniques and calculations the effects of thermal gradients on contaminant migration. Verify that melt size, rate, and carrier gas effects will not contribute significantly to contaminant migration.
3. Evaluate existing data relative to contaminant migration. Possible sources include:
 - Pacific Northwest Laboratory (PNL) tests on cesium contaminated soils for Oak Ridge National Laboratory (ORNL) (see Reference 2).
 - Geosafe tests on PCB-contaminated soils for Northwest Transformer (see Reference 3).
 - PNL tests on arsenic and cadmium contaminated soils for EG&G Idaho, Inc.⁷
4. Perform laboratory-scale tests and/or specially-designed experiments to evaluate the migration of volatile and semivolatile contaminants. Issues to be evaluated by ISV Laboratory Test Series 1 are the migration properties of mercury and three halogenated organic compounds (carbon tetrachloride, tetrachloroethylene, and trichloroethylene). The tests will evaluate how migration is affected by different rates of downward melt growth. Additional tests may also be necessary to resolve remaining issues

on contaminant migration. The need for additional testing will be determined after ISV Laboratory Test Series 1 is completed.

5. Use data from computer modelling, testing, experimentation, and existing data to predict the amount of contaminant migration that will occur at the Acid Pit during ISV operations. Two criteria are recommended for issue closure as follows:
 - The peak concentrations of contaminants within the surrounding soil
 - The percent migration of contaminants away from the ISV melt during processing.

The first criterion is necessary to determine if the concentration of contaminated material in the surrounding soil (following an ISV melt) is such that it could be considered a hazardous waste, as defined by 40 CFR 261.3. This involves TCLP leach testing on the surrounding soil with the peak contaminant concentrations. The second criterion is necessary to evaluate the effectiveness of the ISV process for soils contaminated with volatile and semivolatile contaminants.

To accomplish these criteria, it is necessary to determine the level of confidence for the migration prediction. If ISV is shown to not affect contaminant migration during test scales (such as ISV Laboratory Test Series 1), and the effects of different constituents on contaminant migration are negligible, then the results from existing data and ISV laboratory tests and experiments can be used to evaluate the potential for contaminant migration during ISV processing at the Acid Pit. Otherwise, the results from laboratory tests will be used to model what could happen with larger-scale tests.

6. Determine how the predicted migration of specific contaminants compares to the requirements that have been or will be set by the EPA for remediation activities. This comparison is the final step necessary for closure. Determination of EPA requirements will also determine if either or both of the closure criteria identified in Step 5 will have to be met. In addition, it may be necessary to perform other leach tests that can be used to provide data in support of a risk assessment of the post-test soil surrounding an ISV melt.

2.7.3 Related Technical Issues

- 2.5 Any enhancements to subsurface contaminant migration provided by subsurface structures (pipes, drum surfaces, voids, etc.) are within acceptable limits.
- 2.6 Subsurface contaminant migration due to the effects of sealed containers is within acceptable limits.

2.7.4 References

1. H. L. Penberthy, "Failure of In Situ Vitrification Test on Mercury, Arsenic, Dieldrin, Aldrin," (Critique of GeoSafe Article in Pollution Engineering, June 1990, p. 76-81), Pyro, August 1990, p. 32-F.
2. C. L. Timmerman and M. E. Peterson, Pilot-Scale Testing of In Situ Vitrification of Arnold Development Center Site 10 Contaminated Soils, Appendix A: ISV Organic Destruction Mechanisms, ORNL/Sub/89-14384/2 (PNL-7211), prepared by Pacific Northwest Laboratory for HAZWRAP Support Contractor Office, Oak Ridge, Tennessee, February 1990.
3. S. C. Liikala, "Engineering-Scale Tests of In Situ Vitrification to PCB and Radioactive Contaminated Soils," Cleaning up the Environment for the 21st Century, Pasco, Washington, September 8-11, 1991, Pacific Testing Laboratories, Seattle, Washington.
4. J. Dragun, "Geochemistry and Soil Chemistry Reactions Occurring during In Situ Vitrification," Journal of Hazardous Materials, Vol. 26, 1991, pp. 343-364.
5. Code of Federal Regulations, 40 CFR 261.3, "Definition of Hazardous Waste," U.S. Environmental Protection Agency, Office of the Federal Register, Washington D.C., Revision 9, February 1, 1990.
6. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)
7. J. W. Shade, F. K. Farnsworth, J. S. Tixier, and B. L. Charboneau, Engineering Test 4: In Situ Vitrification of Toxic Metals and Volatile Organics Buried in INEL Soils, PNL-7611, Pacific Northwest Laboratory, Richland, Washington, June 1991.

2.8 The melt width and depth are such that it captures the desired waste. (Priority: 16/25)

2.8.1 Description

2.8.1.1 Description of the Issue. One of the concerns of the ISV process is controlling the size and shape of the melt so that it captures the intended waste to be processed. The depth of the melt product has to be sufficient to process waste to the contamination boundaries. In the case of the Acid Pit, this might require a melt depth extending to the underlying basalt. The depth to the basalt is about 15 feet but may be as deep as 21 feet depending upon the degree of soil overburden.

Controlling the melt is important in preventing undesirable lateral spread of the melt. Excessive melt width may limit downward rate of melting and inhibit remediation of underlying and surrounding waste.

2.8.1.2 Importance. The importance of this issue lies in the threat of the possible release of hazardous and/or radioactive waste to the environment if the waste is not completely captured by the melt. Large obstructions, or unusual or unknown waste forms, may inhibit melt width and depth, resulting in incomplete encapsulation or dissolution of the waste by the melt. This technical issue is of relatively low priority for the Acid Pit due to the general homogeneity of the soil contents. However, it is expected that the Acid Pit has a concentrated mass of contamination that might be processed by ISV. Therefore, it is important to estimate and control the melt width and depth to encapsulate this possible concentrated mass of contamination.

2.8.1.3 Influencing Factors. There are two major factors that must be considered when addressing this issue, the characteristics of the soil (and its contents) and the ISV melt operations.

2.8.1.3.1 Soil Characteristics—Previous ISV field tests have shown that the waste being vitrified can play an important factor in the resulting width and depth of the melt. Layers of soil containing a uniform distribution of rocks do not inhibit the downward rate of the melt. ISV field tests conducted by Pacific Northwest Laboratory (PNL) on relatively homogeneous soils have produced bowl-shaped or square-shaped (with rounded corners) monoliths. However, layers of varying soil types can adversely affect the downward rate of the melt. An ISV large-scale radioactive test (LSRT) in 1987 was terminated at a depth of 16 feet after it was determined that the test would not reach the desired depth of 23 feet. It was concluded that the downward melt progression was inhibited by the presence of a rock layer at the 16.4 ft depth.¹

The fusion temperature of the soil and the particle sizes encountered can also affect the width of the melt. When a higher fusion temperature layer or a larger particle size (greater than 2 cm diameter) layer is encountered, a higher equilibrium temperature is needed to achieve the downward progression of the melt. When this occurs, the molten zone will spread preferentially

outward into surrounding soil with lower equilibrium melting temperatures. Excessive lateral growth occurred during the LSRT in 1987, due to differences in soil melting temperatures (see Reference 1).

Other soil characteristics that could influence ISV melt operations at the Acid Pit include the soil composition, density, soil/waste ratio, depth to waste material (and the amount of overburden), depth to basalt, soil conductivity, and the size and contents of the concentrated mass of contamination.

2.8.1.3.2 Melt Operations—Melt operations greatly influence melt width and depth. Melt operating factors include electrode feed rate, electrode spacing, electrode configuration (number and position), electrode design (e.g., "hot-tip" electrodes), and power input. Previous testing and mathematical models have determined that melt width and depth can be controlled by these factors. For example, studies have shown that as the distance between the electrodes decreases, the depth of the melt zone increases.²

2.8.2 Closure Requirements and Roadmap

2.8.2.1 Assumptions.

- Limited information suggests that the Acid Pit is fairly homogeneous in composition. Geophysical surveys indicated that there were no large inclusions of metal debris. The composition of the buried waste in the Acid Pit seems to be mostly soil with residuals from past disposal (e.g., salt residue from acid waste, neutralization products such as $\text{Ca}(\text{OH})_2$ and CaCO_3 , and miscellaneous glassware). There could exist an area of the Acid Pit that is more highly concentrated with contaminants than compared to the rest of the pit. An induction electromagnetic (EM) conductivity survey of the Acid Pit found one area of the pit that had higher conductivity readings than the rest of the pit, possibly suggesting a concentrated mass of contamination.
- The width and depth of the melt should not be inhibited by the soil/waste type at the Acid Pit due to the assumption that the pit does not contain significantly different types or layers of soil, and is void of large inclusions of metal debris or unusual waste forms.

2.8.2.2 Requirements and Steps to Close Issue. In order to define what is required for closure of this technical issue, the following questions must be considered:

- What is the actual "make-up" of the Acid Pit?

- How will the melt progress vertically and horizontally through the Acid Pit based on its "make-up" and the selected operating parameters? Is there any affect of varying concentrations on ISV melt progress?
- What are the melt boundaries resulting from ISV processing?
- What processing parameters can be varied during the ISV process to improve ISV capture of the intended waste?
- If residual waste remains and is hazardous and/or radioactive, what remedial technologies are available/feasible to contain the waste?

The following steps are recommended for resolving this issue:

1. Characterize the site according to the sampling and analysis plan for the Acid Pit.³ Review the historical waste disposal records for the Acid Pit and verify the estimated waste types and quantities of contaminants by sampling and analysis. Determine the soil characteristics discussed in Influencing Factors. From sampling and analysis, determine the cause for the higher conductivity readings coming from one area of the Acid Pit. If this area of the pit is significantly contaminated with radioactive and/or hazardous waste, determine the extent of the contamination (size, depth, and width).
2. Use results obtained from lab test versus field test operations, and mathematical modelling to predict the vertical and horizontal melt progress through the waste composition and structure at the Acid Pit. Previous testing has shown that the energy requirements and vitrified block size, shape, and mass for a large-scale operational acceptance test (LSOAT) were sufficiently equivalent to the requirements and dimensions predicted by a mathematical model, supporting the usefulness of models as predictive tools.⁴
3. Use monitoring techniques such as thermocouple, infrared sensing, ultrasonics, power/design parameters, acoustics, ground-penetrating radar, depth transmitters, and electrode insertions measurements to determine the melt boundaries during and after the melt.
4. Use laboratory and field testing experience and modelling to predict the optimal process conditions. Develop worst-case scenarios involving melt shape during ISV processing, and be prepared to vary process parameters to halt or correct the undesirable spread of a melt. This might include varying the electrode feed rate or the power input.

5. If residual waste remains, use sampling and analysis schemes to determine if it is above acceptable levels for radioactivity or hazardous waste. Use risk assessment calculations to estimate the threat that remaining waste poses to human health (toxicity and exposure assessments, etc.). If the residual waste does not meet the applicable and relevant or appropriate regulations (ARARs) for site remediation, use ISV or alternative remedial technologies to contain the waste (e.g., retrieval).

2.8.3 Related Technical Issues

Related technical issues are:

- 2.2 The homogeneity and other physical characteristics of the product are well characterized.
- 2.9 Melt channelling or preferential flow of the melt through the path of least resistance is predictable and does not impact the capture of the waste intended to be captured.
- 2.10 The quantity of any uncaptured waste between adjacent vitrified blocks is acceptable.
- 3.20 Risks due to any exposed waste are within acceptable limits.

2.8.4 References

1. J. L. Buelt, C. L. Timmerman, and J. H. Westsik, Jr., In Situ Vitrification: Test Results for a Contaminated Soil-Melting Process, PNL-SA-15767, DOE Contract No. DE-AC06-76RLO 1830, October 1989, pp. 13-14.
2. G. A. Sandness and C. L. Timmerman, In Situ Vitrification Process Monitoring Methods and Development Needs, PNL, August 1982, p. 36.
3. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)
4. J. L. Buelt and J. G. Carter, In Situ Vitrification Large-Scale Operational Acceptance Test Analysis, PNL-5828, UC-70, May 1986.

2.9 Melt channelling or preferential flow of the melt through the path of least resistance is predictable and does not impact the capture of the waste intended to be captured.

(Priority: N/A)

Melt channelling can potentially occur if, in the course of processing a waste cell, the melt's downward path is affected or even redirected by large obstacles, substantial voids, conduits of various types, and/or other metal debris. Since information from geophysical surveys conducted at the Acid Pit indicates the absence of large physical obstacles, large metal inclusions, or substantial voids, the ISV Steering Committee has determined that this technical issue is not applicable to the Acid Pit.

2.10 The quantity of any uncaptured waste between adjacent vitrified blocks is acceptable. (Priority: 7/25)

2.10.1 Description

2.10.1.1 Description of the Issue. Vitrifying a small, known quantity of waste can be a manageable, feasible operation. When the amount of waste to be vitrified extends beyond capabilities of a single ISV melt, vitrifying the waste in contiguous melts becomes an option. Concerns exist that these operations may result in unprocessed waste remaining in the soil between the adjacent vitrified blocks.

2.10.1.2 Importance. In overlapping of ISV melts for site remediation, there is the potential for some of the radioactive and/or hazardous waste to not be incorporated into the final contiguous ISV product. There are several adverse effects that could result from unacceptable amounts of unprocessed waste remaining in the soil between vitrified blocks. Unprocessed waste may release radioactive/hazardous constituents into the underlying soil or basalt fractures, which in time may migrate into the groundwater. Unprocessed waste could also have the potential of emitting volatile organic and radioactive compounds into the air, degrading air quality and endangering the health of workers located within the area of the Acid Pit. If the remaining unprocessed waste was not remediated and failed to meet the applicable or relevant and appropriate requirements (ARARs) for site remediation, such as RCRA, EPA, and DOE requirements, then ISV be considered unsuitable as a viable remedial technology for the SDA. Uncontained radioactive/hazardous waste may result in public and government unacceptance of ISV, jeopardizing ISV funding and support. Furthermore, incomplete resolution of capturing and containing the buried waste weakens the economic justification of ISV as a viable remedial technology for the Acid Pit.

2.10.1.3 Influencing Factors.

2.10.1.3.1 Type and Quantity of Buried Waste—A major factor in determining whether the quantity of uncaptured waste remaining between adjacent vitrified blocks will be acceptable is the type and quantity of buried waste that exists in the Acid Pit before ISV operations begin. If the Acid Pit is highly contaminated with radioactive/hazardous waste throughout the entire pit, then remediation might require more than one melt. The overlap of these melts may miss some of the adjacent waste material, increasing the possibility of unacceptable levels of uncaptured residual waste remaining between blocks.

2.10.1.3.2 Contiguous Melts—The following questions arise if conditions at the Acid Pit require more than one ISV melt to adequately contain the buried waste:

- How many melts will be required and are feasible to contain the waste at the Acid Pit?

- How close can ISV be operated next to a vitrified block?
- How much melt overlap is necessary to contain all of the waste in the Acid Pit?
- How much cooling time is required before ISV can be operated next to a cooling vitrified block? Contiguous melting tests at PNL have shown that contiguous melting should not be attempted unless sufficient time has been allowed for the adjacent vitrified block to cool. Otherwise, the cooling ISV melt may pull some of the joule heat away from the adjacent ISV melt, limiting melt growth.

2.10.1.3.3 Retrieval—One option for resolving this issue is retrieving any waste that is not within acceptable limits after ISV operations have been completed. Some of the questions concerning retrieval are:

- Will the remaining waste between vitrified blocks be accessible for retrieval?
- Do conditions at the Acid Pit (soil characteristics and levels of contamination) allow for retrieval options?

2.10.1.3.4 Size, Depth, and Width of the Melt Product (melt geometry)—Governing the size, depth, and width of the melt product is important to adequately capture the waste to be processed.

2.10.1.3.5 Soil Characteristics—Soil moisture, composition, stratigraphy, density, disturbance (for example, from previous drilling activities), soil/waste ratio, depth to waste material, depth to basalt, ground water location, hydraulic conductivity (thermal and electrical), viscosity, and specific heat all affect the ISV process. Soil characteristics can greatly influence melt geometry, retrieval options, and the feasibility of ISV at the Acid Pit.

2.10.2 Closure Requirements and Roadmap

2.10.2.1 Assumptions.

- Limited information suggests that the Acid Pit is fairly homogeneous in composition. Geophysical surveys indicated that there are no large inclusions of metal debris. The composition of the buried waste in the Acid Pit seems to be mostly soil with residuals from past disposal [e.g., salts, neutralization products (such as $\text{Ca}(\text{OH})_2$), miscellaneous glassware]. However, there could exist an area of the Acid Pit that is more highly concentrated with contaminants than compared to the rest of the pit. An induction electromagnetic (EM) conductivity survey of the Acid Pit found

one area of the pit that had higher conductivity readings than the rest of the pit, possibly suggesting a concentrated mass of contamination.

- Limited information suggests that the Acid Pit is not highly contaminated with radioactivity.
- Retrieval operations, if necessary, will not be impeded by large inclusions of metal debris, intact or breached drums, or major "hot spots" of radioactivity.
- The Acid Pit may require contiguous melts.

2.10.2.2 Requirements and Steps to Close Issue.

1. Characterize the site according to the sampling and analysis plan for the Acid Pit.¹ Verify the estimated waste types, quantities of contaminants, and degree of homogeneity within the Acid Pit. Determine the soil characteristics as discussed earlier in Section 2.10.1.3. Determine the cause for the higher conductivity readings from the EM conductivity survey. If this area of the pit is significantly contaminated with radioactive and/or hazardous waste, determine the extent of the contamination (size, depth, and width).
2. Determine the size of the contamination spread and the number of melts required.
3. Evaluate existing data on contiguous large-scale ISV melts.
4. Use lab-scale tests to determine the effects of employing the ISV process next to a vitrified block. Determine the effects of the overlaps.
5. Use current ISV techniques (e.g., pretest waste configuration data, electrode power and temperature, on-line measurements of melt) along with the site characteristics to estimate the size of the melts needed to adequately contain the waste to be processed.
6. Through the use of computer modelling, determine the distance or degree of overlap needed between ISV melts to ensure efficient ISV melt processes. If overlap is required, determine the necessary cooling time for the adjacent melts.

7. Use engineering calculations to estimate the amount of unprocessed waste that will remain between vitrified blocks. Will the amount of remaining waste be accessible and can it be retrieved or contained if it is contaminated beyond acceptable limits?
8. Use risk assessment calculations to estimate the threat that the remaining waste poses to human health (toxicity and exposure assessments, etc.) Will the remaining waste meet the ARARs for site remediation?

This issue will meet closure requirements if the remaining waste between vitrified blocks can be retrieved or contained (if necessary), passes the appropriate regulations, and does not pose a threat to human health or the environment.

2.10.3 Related Technical Issues

2.8 The melt width and depth are such that it captures the desired waste.

3.20 Risks due to any exposed waste are within acceptable limits.

2.10.4 References

1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

**2.11 The quantity of any waste that may be encapsulated
(unprocessed) within the glass is acceptable.
(Priority: N/A)**

As the melt front progresses, the melt comes in contact with waste which starts to dissolve into the glass. The glass may surround some individual pockets of waste which dissolve slower than the rate of the progressing melt front. If the power to the ISV process is shut down before the surrounded waste can dissolve into the melt, a pocket of unprocessed waste may be present within the final product. If the amount of this encapsulated, unprocessed waste is sufficiently large, the durability and quality of the product may not be acceptable.

The potential impact of this encapsulated waste should be negligible for three reasons. First, the amount of this waste should be only a minor fraction of the total amount of final product. If power is maintained to the melt for a sufficient time after all of the designated waste has been processed by ISV, most of any individual pockets of waste within the melt should be dissolved into the melt. Second, any encapsulated, unprocessed waste would be surrounded by an outer covering of very durable glass, restricting migration paths and carriers. Third, waste disposal records indicate that the disposal techniques at the Acid Pit precludes the presence of large pockets of pure waste.

It should be noted that this technical issue refers to unprocessed, encapsulated waste within the final product and does not refer to the uncaptured waste between vitrified blocks (technical issue 2.10).

**2.12 Secondary waste streams (effluents from the off-gas treatment system, scrub solutions, HEPA filters, decontamination solutions, etc.) are within acceptable limits.
(Priority: 2/25)**

2.12.1 Description

2.12.1.1 Description of the Issue. The ISV process generates secondary waste as part of normal operation of the off-gas processing system. This waste includes stack off-gases, used scrub solutions, used HEPA filters, and glycol cooling solutions resulting from treatment of gaseous effluents exhausted from the hood. It is essential that the secondary wastes can be disposed of in conformance to applicable regulations. In the case of off-gases, they must not exceed established regulatory limits. The amount and type of secondary waste produced in a single test must be determined to verify that it can be stored and disposed of without violating any regulations. Ultimately, the data required for evaluating the secondary waste issue are the amounts of each waste generated and the costs to treat and dispose of these wastes. Such costs are a factor in the overall feasibility of the ISV process. In addition, efforts are needed to ensure that generation of secondary wastes is held to a minimum.

2.12.1.2 Importance. The ISV process retains much of the radioactive and chemical constituents in the vitrified product. However, gaseous effluents from the process must be decontaminated by the off-gas treatment system before they are exhausted to the atmosphere. This is important because the ISV process must comply with Federal and State regulations for air emissions and other applicable regulations governing treatment and disposal of radioactive and hazardous waste.

Secondary waste generation should be held to a minimum in order for ISV to be considered viable and cost effective. Excessive treatment and disposal costs might diminish the benefits for using ISV technology at the Acid Pit.

2.12.1.3 Influencing Factors. Factors influencing the production of secondary waste streams are the amounts and types of primary waste, the hood temperature, the off-gas system design, and the amount of volatile and semivolatile organic compounds present in the waste. Volatile and semivolatile organic compounds could also serve as carrier gases in entraining radioactive compounds during processing, and produce mixed (hazardous and radioactive) secondary wastes. Effluents from the off-gas treatment system will have to meet the regulations governing treatment, storage, and/or disposal of secondary waste.

2.12.2 Closure Requirements and Roadmap

2.12.2.1 Assumptions. None.

2.12.2.2 Requirements and Steps to Close Issue.

1. Characterize the site according to the sampling and analysis plan for the Acid Pit.¹ Determine the types and concentrations of the contaminants in the Acid Pit.
2. Identify all the potential secondary waste streams using site characterization data. Use existing data to chart amounts of secondary waste deposited in the scrub solutions, HEPA filters, and glycol cooling solutions, and amounts of effluents emitted by the stack off-gases from previous tests. Use this data to estimate (by modelling and calculations) the amounts that could be produced during ISV operations at the Acid Pit.
3. Develop methods to minimize the amount of secondary waste generated by the ISV process.
4. Document that the system will meet the ARARs and other limits for off-gas emissions. (Again, documentation is part of the permitting process and is currently in progress.) Record secondary waste data (amounts generated, levels of hazardous constituents, levels of radioactivity) from future field tests.
5. Identify requirements for storage and disposal of the secondary waste (i.e., RCRA). Prepare cost estimates for disposal of wastes generated. Some of those requirements include the following:
 - Identify what techniques are available for disposal of secondary wastes
 - Prepare cost estimates for secondary waste disposal per volume of waste remediated
 - Calculate volumes of secondary treated waste per volume of primary waste remediated
 - Determine whether ISV processing could be used to treat and contain some of the secondary wastes.

6. Document that a waste management plan is in place for the storage and treatment of the secondary wastes, including mixed (hazardous and radioactive) waste. This waste management plan must conform to company mandates, DOE Orders, and ARARs.

2.12.3 Related Technical Issues

- 3.12 Off-gas treatment system containment seals are adequate.
- 3.13 Off-gas treatment system capacity for treatment of products from within the hood is adequate.
- 3.14 Pressurizations due to explosions remain contained within the off-gas treatment system.
- 3.15 Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately by the off-gas treatment system.
- 3.16 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately within the off-gas treatment system.
- 3.17 Increases in off-gas due to the melt encountering voids are contained and processed adequately within the off-gas treatment system.
- 3.18 Excessive off-gas generation caused by combustion is contained within the off-gas treatment system.
- 3.19 Any corrosion within the off-gas treatment system does not affect containment or effluents.

2.12.4 Reference

1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3. SAFETY ISSUES

3.1 The possibility of criticality is avoided.

(Priority: N/A)

Criticality must be prevented in both the melt and in the off-gas treatment system. Waste pits at the Subsurface Disposal Area (SDA) may contain fissile material in sufficient quantities to form a critical mass, under the right geometry. While not critical in its present forms, the fissile material could become critical if concentrated by ISV processes. A potential scenario would involve the reduction of fissile material to its metallic state. The fissile metal would then sink and concentrate at the bottom of the melt, due to the density differences and convection in the melt. The resultant metal pool, if in contact with a suitable moderator (such as water), could potentially result in a critical geometry.

In the off-gas treatment system, fissile material could collect and settle within some of the filters and other off-gas treatment system components, forming a critical mass. This mechanism can be avoided through design and operational procedures.

Waste disposal records indicate that some of the waste disposed of in the Acid Pit is radioactively contaminated. However, the amount of uranium and transuranic radionuclides estimated in the Acid Pit is thought to be relatively small. Based on current Acid Pit site characterization data, the amount of fissile material in the pit is too small to result in a critical mass from the ISV process. Therefore, this issue has been determined to not be applicable to the Acid Pit at this time. If the current site characterization activities result in significantly different site/waste data, this issue will be reevaluated.

3.2 Hood containment seals are adequate. (Priority: 8/25)

3.2.1 Description

3.2.1.1 Description of the Issue. This issue arises because the hood used for testing will have seals where pieces of metal are joined. Additionally, the placing of the hood onto the test site results in an effective seal to the ground. At each of these seals, air flow will occur in response to a pressure differential between the hood interior and exterior. During normal operation the interior is at a negative pressure with respect to outside the hood, and seal leakage will be into the hood. In situations where the inside of the hood experiences positive pressure (e.g., during combustion or other events causing a buildup of pressure inside the hood), air flow out of the hood could occur. The bulk of the excess air flow will be contained and processed by the air inlet line equipped with AWP filters, which act as barriers against unrestricted release. Too much pressure in the hood, however, could cause a breach in the hood seals and release radioactive and/or hazardous constituents to the environment.

3.2.1.2 Importance. This would normally be of less concern than issues that may result in a more catastrophic failure and release of materials. However, contents of the Acid Pit are not believed to offer a potential for concentrated transient releases of combustible material. In July 1991, Battelle halted an ISV test because molten glass ejected and escaped from beneath the hood. This was due to a higher than expected rate of bubbling and gas release.¹

3.2.1.3 Influencing Factors. Factors influencing this issue are the amount of gas-generating materials in the melt, and the variation in release rates of generated gases from the melt. Specific hood design measures may also be implemented to prevent or mitigate pressure transients.

3.2.2 Closure Requirements and Roadmap

3.2.2.1 Assumptions.

- No Pu is present in the Acid Pit.
- There is a potential for pressurization due to accidents such as equipment failure and operator error. However, pressurization is not an issue unless harmful constituents may be released from the melt.

3.2.2.2 Requirements and Steps to Close Issue.

1. Characterize the site according to the sampling and analysis plan for the Acid Pit.² Obtain characterization data on harmful volatile and semi-volatile constituents in the Acid Pit that may be plausibly released in quantities that could endanger workers.
2. Obtain site characterization data on other volatile and semi-volatile constituents in the pit that may contribute to hood pressurization, either through gaseous heat expansion or via chemical reactions (e.g., pyrolysis/combustion). Analytical modeling and testing may be required to quantify the potential pressure increase within the hood. Contributing factors for which data are needed include (a) chemical interactions in the melt among pit constituents, (b) gaseous release rates from the melt, (c) gaseous release rates around the side of the melt, and (d) combustion rates in the hood (based on hood flow patterns).
3. Based on plausible expectations of what situations may be encountered during testing, establish the chemical/physical mechanisms for gas production that may cause pressurization within the ISV hood plenum.
4. Calculate (in bounding way) the maximum pressure that could occur in the hood plenum. Determine if the resultant maximum pressure could be adequately contained by existing hood seals. If found to be inadequate, are there other hood seal designs that could be used?

3.2.3 Related Technical Issues

- 3.6 Pressurizations due to explosions remain contained within the hood.
- 3.7 Pressurizations due to the breach of pressurized sealed containers remain contained within the hood.
- 3.8 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained within the hood.
- 3.9 Increases in off-gas due to the melt encountering voids remain contained within the hood.
- 3.10 Off-gas generation caused by combustion is contained within the hood.

3.2.4 References

1. In Situ Vitrification Test Failure, Forcing Reevaluation of Process, Report on Defense Plant Waste, August 16, 1991, p. 143.
2. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.3 Any fires that occur do not affect the integrity of the hood. (Priority: 6/25)

3.3.1 Description

3.3.1.1 Description of the Issue. Two hood fires have occurred during testing of ISV. Both of these fires occurred with fabric hoods containing combustible coatings.¹ Two things must be established regarding hood design, (a) that combustion in the hood plenum does not result in temperatures high enough to cause failure of hood material or electrode seals and (b) that melt splatter does not cause failure of hood material or electrode seals. Some of the solvents dumped into the Acid Pit are combustible; however, it is likely that these are dispersed into the ground so that large transient releases of combustible gases to the hood plenum are not likely. Evidence from review of records and specific site characterization will provide needed information on expected plenum conditions. Hood contact with melt material due to melt splatter is a possibility. Melt splatter is addressed as a separate technical issue (3.11).

3.3.1.2 Importance. The hood design must be able to withstand the ISV hood plenum environment during processing of the Acid Pit. Two areas of concern for fires are (a) the combustion of gases in the hood plenum and (b) the splatter of melt material that comes into contact with the hood surface. In July 1991, Geosafe Corporation had a head fire due to melt splatter. The hood had a ceramic and glass-layered fabric coated with a thin layer of silicone. Molten glass splattered, hit the silicone coating, and ignited a fire (see Reference 1).

3.3.1.3 Influencing Factors. The primary factor contributing to this issue is the type and amount of combustible material in the buried waste.

3.3.2 Closure Requirements and Roadmap

3.3.2.1 Assumptions. None.

3.3.2.2 Requirements and Steps to Close Issue.

1. Obtain data from intended site characterization studies² to establish the types and amounts of pyrolysis products and determine the potential for melt splatter.
2. Calculate (in a bounding way) the maximum temperatures that could occur in the hood plenum from combustion of hood gases. Compare these temperatures to design limits for the hood material. If found to be inadequate, evaluate and determine if there are other hood materials that could be used in lieu of the existing hood material.

3.3.3 Related Technical Issues

3.6 Pressurizations due to explosions remain contained within the hood.

3.7 Pressurizations due to the breach of pressurized sealed containers remain contained within the hood.

3.3.4 References

1. "Geosafe Suspends ISV Operations Following Fire at Test Site," HAZMAT WORLD, September 1991, p. 16.
2. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.4 A sidewall collapse does not impact the seal between the hood skirt and the ground. (Priority: 13/25)

3.4.1 Description

3.4.1.1 Description of the Issue. Sidewall collapse is considered a technical issue since the potential exists to release hazardous materials into the environment. During the ISV process, the melt subsides below the initial soil surface. As the melt subsides, part of the unmelted soil forming the boundary (sidewall) to the melt can collapse into the melt. When the subsidence of the melt is large, the potential for sidewall collapse is increased. If the amount of sidewall collapse is great, the soil that forms a seal with the ISV hood can collapse into the melt, leaving a gap between the hood and the soil. If the hood is improperly designed, the resultant gap could allow particulates and off-gases to escape into the surrounding environment. The off-gases evolved from the Acid Pit could contain sulfuric, hydrochloric, and nitric acid, as well as organic decomposition products and particulates. These materials must be removed in a controlled manner by the off-gas treatment system to protect the environment and operation personnel.

The probability of a sidewall collapse occurring is low, but may increase with excessive subsidence caused by the melt. As a result, design of the hood needs to take into account the sluff angle of the SDA soil, assuming no molten sidewall is created.

From a design point of view, the Pacific Northwest Laboratory (PNL) hood structure should survive tipping caused by partial sidewall collapse. If a dimpled skin is added, the weight of the hood sheathing will be increased by 33% thus increasing the structural integrity of the hood. However, tipping may impose bending moments on the off-gas pipe in the event of significant dislocation of the hood.^b

3.4.1.2 Importance. The probability of a possible collapse and breach depends on the potential sluff angle of the SDA soil and whether the hood is adequately designed to handle this sluff. Any breach of the off-gas hood could be an immediate hazard to operation personnel.

3.4.1.3 Influencing Factors. Contributing factors that may affect the possibility of a collapse and breach include melt subsidence, melt aspect ratio, melt rate, site conditions (including potential sluff angle, moisture content, density, and void volume), and hood design.

b. Private communication with R. W. Bonnenberg, ISV Design Task Manager for Equipment Design, Technology Demonstration, EG&G Idaho, Inc., Idaho Falls, Idaho, August 29, 1991.

3.4.2 Closure Requirements and Roadmap

3.4.2.1 Assumptions.

- Existing data are extensive enough so that correlations can be made among factors that contribute to sidewall collapse. In particular, the existing data can be used to determine the sluff angle range of the SDA site soil.

3.4.2.2 Requirements and Steps to Close Issue.

1. Characterize the site according to the sampling and analysis plan for the Acid Pit.¹ Existing site data should be reviewed to attempt to determine the sluff angle of the soil, the potential subsidence of the soil, and the potential aspect ratio (width/depth) of the melt.
2. Use modelling techniques and calculations to predict potential width and amount of sidewall collapse. Based on the information collected from existing test data, it may be possible to close the issue of sidewall collapse by performing calculations made from assumptions and/or models. Calculations are possible assuming that the primary factors determining sidewall collapse are the sluff angle of the soil and the subsidence of the melt, which in turn is determined by the void volume. If an upper limit to the void volume can be determined, and the assumptions hold, it should be possible to estimate the amount of sidewall collapse that could occur.
3. Compare the model calculations to the existing hood design to determine if the potential breach from sidewall collapse is real. If a problem exists, determine if the hood or melt size can be designed to better accommodate all potential sluffing of the soil.

3.4.3 Related Technical Issues

- 3.2 Hood containment seals are adequate.
- 3.5 The melt and thermally altered zone do not extend laterally beyond the hood boundaries.
- 3.8 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained within the hood.

3.16 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately within the off-gas treatment system.

3.4.4 References

1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.5 The melt and thermally altered zone do not extend laterally beyond the hood boundaries.

(Priority: 19/25)

3.5.1 Description

3.5.1.1 Description of the Issue. This issue relates to the thermally altered soil zones (i.e., isotherms) that extend around the ISV melt during and after ISV processing. Thermally altered zones are sections of the soil surrounding the melt through which gaseous contaminants may migrate due to thermal gradients within the soil. These zones are bounded by the melt/soil interface and the isotherm at which condensation occurs for the specific contaminant of interest. During ISV processing, these areas are generally close (within 2 ft) to the ISV melt front.

3.5.1.2 Importance. The thermally altered zones of interest are those areas (i.e., isotherms) where there is a potential for hazardous material emissions to the atmosphere. The movement and location of these isotherms need to be evaluated, to determine the ISV hood dimensions needed to contain the hazardous emissions released from both the melt and the surrounding soils during ISV processing.

3.5.1.3 Influencing Factors. Factors that can influence the movement of soil isotherms (and contaminants) away from the melt during and after ISV processing are thermal conductivity and thermal diffusivity of the contaminated areas in the Acid Pit. The presence of soil saturated with water, acids, and/or salts may enhance the potential for isothermal movement away from the melt, both during and after ISV processing. Another factor that may influence this issue is the relative homogeneity of the Acid Pit, both in terms of soil porosity and of contaminant composition and concentration. In addition, certain (though not all) ISV large-scale melts have had melt aspect ratios (ratio of melt width to melt depth) that were higher than expected. This may also affect the required dimensions of the ISV hood.

3.5.2 Closure Requirements and Roadmap

3.5.2.1 Assumptions.

- The contaminants of interest will migrate to a temperature range in the soil that is directly related to the vapor pressure-temperature relationships of the contaminant itself. If this is true, it should be possible to calculate the potential contaminant release to the environment at various distances (and peak soil temperatures) away from the melt. This assumption should be verifiable by using engineering or computer calculations. The

assumption could also be verified via air monitoring of the soil surface at various predetermined locations during ISV processing.

3.5.2.2 Requirements and Steps to Close Issue. To close the issue of hood containment of the thermally altered soil zones, it will be necessary to:

- Estimate or determine the subsidence, sluff angle, and aspect ratio of a typical Acid Pit melt (pilot and large-scale tests). (See Technical Issue 3.4.)
- Estimate or determine how far the soil isotherms of interest extend away from an Acid Pit melt (both horizontally and vertically), during and after ISV processing (pilot and large-scale tests).
- Determine if and where the isotherms of interest come in contact with the surface of the soil (pilot and large-scale tests).
- Determine the effects that clean soil overburden may have on the migration of contaminants to the surface.
- Determine if the existing ISV hood (pilot and large-scale tests) is large enough to contain any hazardous material emissions that are released from either the melt or the thermally altered soil surface.

The steps towards closure of this issue are:

1. Characterize the site to obtain a good understanding of the thermal conductivity of the soil in the area to be ISV processed. Thermal conductivity is very important in predicting the aspect ratio of the melt, as well as how far the soil isotherms of interest may move away from the melt.
2. Use samples from the Acid Pit to obtain meaningful data on the potential sluff angle, side wall formation, and amount of subsidence expected during ISV processing of the Acid Pit.
3. Determine the factors that influence contaminant emissions from both the ISV melt and the soil surrounding the ISV melt. Are the contaminant emissions directly related to soil and melt surface temperatures? This determination may be done using either existing data, engineering calculations, computer modelling, or specially designed experimental testing.

4. If contaminant emissions are related to the surface temperatures of the melt and surrounding soil, use computer modeling and/or engineering calculations to determine the potential release of contaminants from the surrounding soil surfaces at various distances away from the melt.
5. If the relationship of contaminants to the melt and soil surface temperatures cannot be established, perform an ISV test evaluating the release of contaminants from the surrounding soil surfaces, at various radial distances away from the melt.
6. Determine that the ISV hood to be used is large enough to capture most of the hazardous emissions released from the surrounding soil during ISV processing. If the hood size is not sufficient, evaluate how much it would cost to design and fabricate a sufficiently sized hood. Some stray emissions can be expected and dealt with through the use of appropriate mechanisms and procedures (i.e., radiation and gas detection devices, personnel protection, etc.).

3.5.3 Related Technical Issues

Determination of the required ground surface area of the hood will also provide data on what off-gas emissions are expected and the rates at which they are released. As a result, this issue is also related to the following technical issues:

- 2.12 Secondary waste streams (effluents from the off-gas treatment system, scrub solutions, HEPA filters, decontamination solutions, etc.) are within acceptable limits.
- 3.4 A sidewall collapse does not impact the seal between the hood skirt and the ground.
- 3.8 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained within the hood.
- 3.16 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately within the off-gas treatment system.
- 3.19 Any corrosion within the off-gas treatment system does not affect containment or effluents.
- 3.20 Risks due to any exposed waste are within acceptable limits.
- 3.21 Post-processing hood containment is maintained as required.

3.6 Pressurizations due to explosions remain contained within the hood. (Priority: 11/25)

3.6.1 Description

3.6.1.1 Description of the Issue. Several mechanisms can be postulated that could cause explosions to occur both in and above the melt. Possible mechanisms that could produce explosions in the melt include the melt encountering inherently explosive compounds such as organic nitrates or military ordnance. Explosions above the melt could occur as a result of explosive gases collecting in the hood and detonating as they reach explosive concentrations. A potential scenario for a hood explosion is a temporary loss of power which could cause the air supply and the attendant combustion of the off-gases to cease. Without the availability of an emergency generator, this could cause the off-gases to collect in the hood and explode upon reentry of air when the power is restored.

3.6.1.2 Importance. Detonation of explosive compounds and mixtures can cause a sudden release of energy resulting in large temperature, pressure, and off-gas excursions. The rapid energy release can potentially cause physical damage to the ISV equipment which could result in a breach of the containment and the release or expulsion of hazardous material to the environment.

3.6.1.3 Influencing Factors. None.

3.6.2 Closure Requirements and Roadmap

3.6.2.1 Assumptions.

- It is assumed that there is no military ordnance in the Acid Pit.
- It is conservatively assumed that the explosions occurring in the melt occur above ground.

3.6.2.2 Requirements and Steps to Close Issue. The general approach will be to first characterize the Acid Pit and assess the potential presence of explosive compounds or mixtures. If it is established that explosive compounds or mixtures will be encountered, potential mechanisms for detonation will be evaluated. If plausible mechanisms are identified, calculations will then be performed to determine the maximum amounts of each explosive that can be tolerated for those detonation mechanisms or scenarios considered plausible. Estimates will then be made of the amount of explosives to be expected. If the amounts of expected explosives are above acceptable limits, calculations will be performed to establish design requirements for an acceptable system. Both deterministic and probabilistic methods will be used in this approach.

The issue will be considered closed when the following closure criteria have been met:

- The probability of explosive material being encountered is acceptably low (10^{-6})
- The probability of an explosion occurring is acceptably low (10^{-6})
- The hood will maintain its integrity after experiencing the maximum plausible explosion
- The design requirements have been established for an ISV hood that will maintain its integrity after experiencing the maximum plausible explosion.

The steps to the close issue are:

1. Characterize the site according to the sampling and analysis plan for the Acid Pit to determine if explosive compounds or mixtures are in the soil.¹ Particular attention will be made to evaluate the presence of explosive compounds (ammonium nitrate, ammonium perchlorate, nitrated organics, etc.). Also, the potential for producing explosive gases (H_2 , CO, etc.) from the pit contents will be evaluated. If the probability of explosives being present is found to be acceptably low, the issue is closed under Closure Criterion 1. If explosives are found to be present or the probability of explosives being present is high, proceed to Step 2.
2. If explosive compounds are found to be present, potential scenarios and mechanisms for causing explosive compounds to detonate will be examined and their probability of occurrence established. If the probability of explosions actually occurring is found to be acceptably low, the issue is closed under Closure Criterion 2. If the probability of explosives occurring is high, proceed to Steps 3 and 4.
3. For plausible explosion scenarios and mechanisms, calculations will be performed to determine the maximum amount of each explosive that can be detonated in the selected hood and still have the hood maintain its integrity. If necessary, laboratory experiments may have to be performed to provide specific data for the calculations.
4. Perform analyses to determine the amounts of the explosive compounds that can be expected and see if the amounts are below those established in Step 3. If the amounts are below those established in Step 3, then the issue is closed under Closure Criterion 3. If the amounts are above those established in Step 3 proceed to Step 5.
5. Repeat the calculations described in Step 3 except use the actual amounts of compounds expected and determine the design requirements for the hood to maintain its integrity. The issue is closed under Closure Criterion 4.

3.6.3 Related Technical Issues

- 3.2 Hood containment seals are adequate.
- 3.7 Pressurizations due to the breach of pressurized sealed containers remain contained within the hood.
- 3.8 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained within the hood.
- 3.9 Increases in off-gas due to the melt encountering voids remain contained within the hood.
- 3.10 Off-gas generation caused by combustion is contained within the hood.

3.6.4 References

- 1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.7 Pressurizations due to the breach of pressurized sealed containers remain contained within the hood. (Priority: N/A)

Sealed containers have the possibility of increasing the pressure to the hood and the off-gas treatment system if they become breached during the ISV process and release significant amounts of gases during the melt. Since the information from geophysical surveys conducted at the Acid Pit indicates the absence of large inclusions of drums and containers, the ISV Steering Committee has determined that this technical issue is not applicable to the Acid Pit. The Acid Pit is known to contain various types and sizes of glass containers, but whether the containers are empty, sealed, filled, or broken is unknown. Even so, sealed glassware should not contribute significantly to pressure transients due to the general limited size of the glass waste and the assumption that any sealed glassware will likely fracture due to thermal stresses at very low temperatures and pressures, prior to coming in contact with the melt.¹ This assumption was verified in the Engineering Test 4 of INEL soils.²

3.7.1 References

1. Letter report from J. W. Shade, R. K. Farnsworth, and C. H. Kindle, Pacific Northwest Laboratory, to EG&G, Idaho, Inc., Subject: "Technical Issues for ISV Processing of Buried Waste Sites," April 1990.
2. J. W. Shade, R. K. Farnsworth, J. S. Tixier and B. L. Charboneau, Engineering-Scale Test 4: In Situ Vitrification of Toxic Metals and Volatile Organics Buried in INEL Soils, PNL-7611, Pacific Northwest Laboratory, Richland, Washington, 1991.

3.8 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained within the hood.

(Priority: 21/25)

3.8.1 Description

3.8.1.1 Description of the Issue. The containment hood must be able to withstand pressurizations that occur as a result of waste falling from the sidewall onto the melt surface. During the ISV process, the melt subsides below the initial soil surface. As the melt subsides, part of the unmelted soil forming the boundary (sidewall) to the melt can collapse onto the melt. When the subsidence of the melt is large, the potential and amount of sidewall collapse is increased. If the amount of sidewall collapse is great, the soil that falls onto the melt surface potentially can release a large transient amount of off-gas which must be processed by the off-gas system. Off-gases evolved from the Acid Pit could contain sulfuric, hydrochloric, and nitric acid as well as organic decomposition products and particulates. These materials must be removed in a controlled manner by the off-gas treatment system to protect the environment and operational personnel. Equipment could fail from extremely large transient amounts of off-gases (i.e., seals may be breached by overpressurization of the hood). This is a particular problem where large amounts of volatile waste materials are present. Since the Acid Pit is expected to consist of only contaminated soil, the problem is anticipated to be a small concern.

3.8.1.2 Importance. The seriousness of a possible emission depends on the type of materials that would be released, and on the size of the breach. This, in turn, depends on the amounts and kinds of materials present in the Acid Pit, the size of the melt, the hood design, the soil conditions, and the potential volume of soil involved in a sidewall collapse. Any release would be an immediate hazard to the operational personnel, as well as to the environment.

3.8.1.3 Influencing Factors. Contributing factors that may affect the possibility of an emission include soil contamination, potential sidewall formation, melt size, melt rate, off-gas evolution rate, soil conditions, void volume, overburden, sluff angle of the soil, and hood design.

3.8.2 Closure Requirements and Roadmap

3.8.2.1 Assumptions.

- It is assumed that the possibility of waste falling from the sidewall and causing an increase in off-gas cannot be dismissed with confidence.
- It is assumed that the Acid Pit contains only contaminated soil (no waste containers, large equipment, metal debris, etc.).

3.8.2.2 Requirements and Steps to Close Issue. The issue will be considered closed when one of the following Closure Criteria have been met:

1. The probability of waste material falling from the sidewall and causing a significant increase in off-gas rate is acceptably small. (This Closure Criteria cannot be satisfied based on the first assumption. However, the first assumption needs to be established before rejecting Closure Criteria 1.)
2. The potential volume of soil involved in any sidewall collapse is such that the hood can maintain its integrity and contain the transient increases in off-gas generation following such a collapse.
3. The design requirements have been established for a hood to contain increases in off-gas generation caused by waste material falling from the sidewall onto the melt.

The steps toward issue closure are:

1. Characterize the site according to the sampling and analysis plan for the Acid Pit.¹ Particular attention should be given to evaluating the presence and determining the concentration of compounds that could generate large volumes of gas.
2. Determine the potential sluff angle of the dry SDA soil.
3. Estimate the amount of gas that would be generated per unit volume of waste, based on site characterization data. The volume of soil/waste that might fall onto the melt can be calculated using conservative subsidence and angle of repose values. The total volume of gas that would be generated can then be calculated. Without appropriate experimental data, determining the rate of gas evolution will be difficult. The rate of heating and the gas release from a sidewall soil collapse can be estimated using the thermal conductivity and the specific heat of the bulk soil. A more conservative estimate can be made by assuming that vaporization is instantaneous and that gas evolution rate is determined by the rate at which the waste falls onto the melt. Conservative estimates can be made for the rate at which soil slides into the pit.
4. Estimate the maximum hood pressure and the hood's ability to maintain its integrity, based on the rate of gas generation calculated in Step 2. If

the hood can maintain its integrity, the issue is closed under Closure Criteria 2.

5. If the hood cannot maintain its integrity, the design requirements for an adequate and safe hood must be established. The issue will then be closed under Closure Criterion 3.

3.8.3 Related Technical Issues

3.2 Hood containment seals are adequate.

3.12 Off-gas treatment system containment seals are adequate.

3.13 Off-gas treatment system capacity for treatment of products from within the hood is adequate.

3.16 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately within the off-gas treatment system.

3.8.4 References

1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.9 Increases in off-gas due to the melt encountering voids remain contained within the hood. (Priority: N/A)

If the melt encounters a large void of combustible gases, it could result in a sudden release of off-gases that could breach or damage the hood and off-gas containment system. The presence of large voids could halt the test process due to loss of a conductive path. Since information from geophysical surveys conducted at the Acid Pit indicates the absence of substantial voids, the ISV Steering Committee has determined that this technical issue is not applicable to the Acid Pit.

3.10 Off-gas generation caused by combustion is contained within the hood. (Priority: 22/25)

3.10.1 Description

3.10.1.1 Description of the Issue. Most of the organic material within the vitrification zone will pyrolyze into volatile byproducts which will rise to the surface of the melt and combust upon contact with the air above the melt. The pressures and temperatures due to combustion depend upon the type and amount of byproducts formed by pyrolysis and the amount of air available for combustion. Pressures could be large enough to compromise the vacuum pressure maintained within the hood. This could result in the release of undesirable waste products to the environment.¹⁻⁴

3.10.1.2 Importance. The design of the confinement hood must be capable of handling the pressure transients and temperatures due to combustion and still maintain the vacuum pressure needed to direct the off-gas to the off-gas processing unit. The importance of this issue lies in the threat of the possible release of hazardous and/or radioactive off-gas to the environment if the vacuum pressure within the hood is lost due to pressure transients caused by combustion. The off-gas can be in the form of volatile hazardous and/or radioactive vapor effluents or in the form of hazardous and/or radioactive non-volatile particulates entrained by the off-gas.

3.10.1.3 Influencing Factors. The following factors influence the combustion process within the hood:

1. Composition, amount, concentration and location of organic and combustible materials within the vitrification zone
2. Composition, amount, concentration, and location of catalytic materials within the vitrification zone that may accelerate pyrolysis
3. Amount of air within the containment hood and the amount of oxidizers within the vitrification zone
4. Cold cap existence
5. Temperature and composition of the melt
6. Design of the confinement hood.

3.10.1.3.1 Composition, Amount, Concentration, and Location of Organic and Combustible Material within the Vitrification Zone—The amount and type of combustible material found within the confinement hood is determined by the amount and composition of the organic and

combustible material within the vitrification zone. Pyrolytic processes convert the organic materials into combustible material (see References 1-4). The Acid Pit contains tributyl phosphate, Amsco, and other unidentified organic materials. Examples of potential combustibles that may or may not be found in the Acid Pit are materials such as gasoline, paint, wood, oil rags, paperboard, plastics, and rubber.⁵

The concentration of organic and combustible materials in the Acid Pit will influence the off-gas flow rate. The rate at which combustible material is formed will be less for a given volume of organic material spread throughout the pit as opposed to the same volume of organic material concentrated within a small region of the Acid Pit. A large-scale system can contain gases released from combustible volumes as large as 0.9 m³ without losing hood vacuum assuming a decreased rate for pyrolyzed gases over a 30-minute period (see Reference 1).

The depth of the organic and/or combustible material can influence the off-gas flow rate. Gases formed by pyrolysis at lower depths are less likely to escape the melt as opposed to the gases formed near the melt surface (see Reference 1).

3.10.1.3.2 Composition, Amount, Concentration, and Location of Catalytic Materials within the Vitrification Zone that may Accelerate Pyrolysis—Pyrolysis may be accelerated if catalysts such as sulfuric acid, certain clay materials, or metallic oxides are present (see Reference 1). The Acid Pit contains sulfuric acid.

3.10.1.3.3 The Amount of Air within the Containment Hood and the Amount of Oxidizers within the Vitrification Zone—All combustion processes need a source of oxygen either in the form of a gas or in another form, such as a nitrate or chlorate (see Reference 1). In a normal ISV process, air is drawn into the confinement hood and mixed with the off-gas from the melt. The temperature within the hood is sufficient to promote combustion. In order to properly destroy the organics and combustibles within the vitrification zone, sufficient oxygen must be supplied to ensure complete combustion. However, the air/off-gas flow rate may not exceed the capacity of the off-gas treatment system. The amount of combustibles determines the amount of oxygen needed to achieve complete combustion (see References 1, 2, and 4).

Combustion may occur within the vitrification zone if the pyrolyzed organics and/or combustibles are near a sufficient amount of oxidizers (see Reference 1). Oxidizers within the Acid Pit are nitric acid and aluminum nitrate.

3.10.1.3.4 Cold Cap Existence—When a cold cap or an insulated surface exists over the ISV melt, the amount of off-gas released from the melt is reduced. This in turn will reduce the amount of combustion within the hood.

3.10.1.3.5 Temperature and Composition of the Melt—At higher temperatures and lower melt viscosities, gases from the melt escape more readily. Temperature has the greater effect on gas release. Therefore, to reduce the amount of combustible vapors leaving the melt, the temperature of the melt needs to be reduced.

3.10.1.3.6 Design of the Confinement Hood—The design of the confinement hood must be capable of handling the transient pressure pulses caused by combustion, while maintaining the desired vacuum pressure within the hood. The hood must also be properly designed to prevent circulation dead spots where combustible gases may accumulate. Finally, the hood must be designed such that pressure transients due to combustion and other pressure pulse generating mechanisms may not cause structural fatigue to the hood (see References 2 and 4).

3.10.2 Closure Requirements

3.10.2.1 Assumptions. None.

3.10.2.2 Requirements and Steps to Close Issue.

1. Characterize the site. Through historical waste disposal records and sampling of the Acid Pit (see Reference 5), determine the type, amount, and location of organic and/or combustible materials within the pit. The type, amount, and location of potential oxidizers and pyrolytic catalysts need also to be determined.
2. Determine the mechanisms of pyrolysis and combustion for the organic and/or combustible materials present in the Acid Pit. This can be achieved experimentally or numerically.
3. Determine the magnitude and the temporal range of the pressure transients that may occur within the hood due to combustion of the materials within the Acid Pit.
4. Perform a numerical analysis of combustion within the hood to determine if the hood design used in the ISV process is capable of handling the pressure transients due to combustion.

3.10.3 Related Technical Issues

3.18 Excessive off-gas generation caused by combustion is contained within the off-gas treatment system.

3.10.4 References

1. Letter report from J. W. Shade, R. K. Farnsworth, and C. H. Kindle, Pacific Northwest Laboratory, to EG&G, Idaho, Inc., Subject: "Technical Issues for ISV Processing of Buried Waste Sites," April 1990.
2. Calvin E. Slater, Carl M. Stoots, and Robert J. MacKinnon, Discussion of Technical Issues Associated with the Application of In Situ Vitrification at the Idaho National Engineering Laboratory and a Suggested Approach for their Resolution, EGG-WM-9048, September 1990.
3. V. F. FitzPatrick, In Situ Vitrification - A Status of the Technology, PNL-SA-14281, September 1986.
4. J. L. Buelt, V. F. FitzPatrick, C. L. Timmerman, J. G. Carter, and K. H. Oma, In Situ Vitrification of Transuranic Waste: An Updated Systems Evaluation and Applications Assessment, PNL-4800, DOE Contract No. DE-AC06-76RLO1830, March 1987.
5. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.11 Any matter ejected from the melt is contained within the hood. **(Priority: 23/25)**

3.11.1 Description

3.11.1.1 Description of the Issue. During the ISV process, gases bubbling in the melt may eject melt material onto the hood. The ejected materials may erode the hood through corrosion, abrasion, or extreme heat. The potential for ejection of melt material depends on the type of waste being processed by ISV. Waste containing a significant amount of combustible materials could result in excessive gas generation and melt splattering. Combustible waste in sealed containers (e.g., metal drums) can result in rapid venting of pyrolyzed gases and particulates. For example, a pilot-scale field test (PSFT), PSFT-3, conducted by Pacific Northwest Laboratory evaluated ISV performance with a 208-liter (55-gallon) metal drum containing simulated combustible waste and soil buried between electrodes.¹ When molten soil contacted the waste drum, rapid venting of pyrolyzed gases and carbonaceous particulates occurred for about 30 minutes.

Recent events involving excessive melt ejection during a full-scale operational acceptance test (OAT-2) at Geosafe, and a full-scale underground tank test at Pacific Northwest Laboratory (PNL) have given increased importance to understanding mechanisms for water and/or other volatile material transport underneath the melt. It has been postulated that under certain conditions of soil moisture and soil permeability, the ability of the soil to relieve pressure buildup underneath the melt may be challenged. In these cases, large melt bubbles and associated expulsion (of varying magnitude) may be a possibility during vitrification of the soil. The mechanisms of vapor transport must be studied (analytically and experimentally) in greater detail in order to provide certainty that excessive melt splatter will not occur during ISV processes at the Acid Pit.

3.11.1.2 Importance. This technical issue is less of a concern for the Acid Pit than for other pits and trenches at the Subsurface Disposal Area (SDA). This is due primarily to the lack of sealed containers buried in the Acid Pit. However, as noted above, the issue of large bubble formation from soil vapor may increase the importance of this issue.

3.11.1.3 Influencing Factors. Factors affecting the amount of melt splatter are the gas-generating capability of the waste, the rate of ISV processing, and the rate of vapor diffusion in the surrounding soil.

3.11.2 Closure Requirements and Roadmap

3.11.2.1 Assumptions.

- According to information from historical records, the Acid Pit does not contain a significant amount of sealed containers containing combustible waste.

3.11.2.2 Requirements and Steps to Close Issue. In order to resolve this issue, it is necessary to determine the maximum melt splatter potential from ISV processing at the Acid Pit. Preliminary site characterization data is needed to determine melt splatter potential. By determining the maximum amount of splatter that may occur, it could then be possible to mitigate and/or avoid the effects of melt splatter through hood design (e.g., use of splatter shields or varying the distance of the hood from the melt surface). However, due to the recent melt ejection event at PNL, this issue and its importance may have to be reevaluated.

The steps towards issue closure are:

1. Establish plausible gas pressurization and release mechanisms that may result in melt splatter, based on results from preliminary site characterization studies.
2. Calculate (in a bounding way) the maximum amount of material that could be ejected and the distance it could travel at different ISV processing rates and conditions. Assess the capability of current ISV hood designs for containing the calculated maximum amount of melt splatter. This includes evaluating the potential for hood failure due to stress loading or melting from possible localized, concentrated areas of melt splatter.
3. Verify the validity of melt splatter predictions made through calculations and modelling with observed results from lab-scale testing of ISV. Determine if melt splatter could be significant during ISV processing at the Acid Pit.
4. If melt splatter is determined to be a hazard, implement applicable hood designs to mitigate or avoid erosion of the hood and adequately contain melt materials.
5. The possibility of large bubble formation in the melt should be addressed via a parameter study which looks at pressure beneath the melt as a function of soil permeability, porosity, and moisture content. Soil moisture content data and permeability data should be obtained as part of site characterization studies. Comparison between these data and information from the analytical studies should be performed.

3.11.3 Related Technical Issues

None.

3.11.4 References

1. J. L. Buelt, V. F. FitzPatrick, C. L. Timmerman, J. G. Carter, and K. H. Oma, In Situ Vitrification of Transuranic Waste: An Updated Systems Evaluation and Applications Assessment, PNL-4800, DOE Contract No. DE-AC06-76RLO1830, March 1987.

3.12 Off-gas treatment system containment seals are adequate. (Priority: 12/25)

3.12.1 Description

3.12.1.1 Description of the Issue. Containment seals will be employed throughout the off-gas treatment system. Piping connections within the off-gas trailer will likely have double containment; however, piping between the hood and trailer may not. At each of these seals, air flow will occur in response to a pressure differential between the piping interior and exterior. During normal operations the interior is at a negative pressure with respect to outside the off-gas treatment system, and seal leakage will be into the piping. During overpressurization, airflow out of the piping may occur if the off-gas seals are under designed.

3.12.1.2 Importance. Due to the assumptions that no voids or large metal drums are within the Acid Pit, the contents of the Acid Pit are not believed to offer potential concentrated transient releases of combustible or pyrophoric materials. Therefore, releases through the off-gas seals are believed to represent a more credible possibility for release than that of hood containment, and are of greater concern. However, even though releases through the off-gas seals are more credible, the potential for a release is very slight. This is because it is anticipated that much of the off-gas system will have double containment, reducing the potential threat posed by a release.

3.12.1.3 Influencing Factors. The factors influencing this issue are the amount of gas-generating materials in the melt, and the release rate of the gases generated from the melt. Specific containment seal design measures may be implemented to prevent or mitigate pressure transients.

3.12.2 Closure Requirements and Roadmap

3.12.2.1 Assumptions. None.

3.12.2.2 Requirements and Steps to Close Issue.

1. Characterize the site according to the sampling and analysis plan for the Acid Pit.¹ Verify the presence of any harmful constituents in the SDA Acid Pit that may be plausibly released in quantities that could endanger workers.
2. Identify constituents in the pit that may contribute to off-gas pressurizations, either through gaseous expansion or via chemical reactions (e.g., pyrolysis/combustion). Analytical modeling and testing may be required to quantify the potential pressure increases within the off-gas system. Contributing factors for which data are needed include chemical interactions between constituents in the melt, gaseous release rates from the melt, gaseous rates

around the side of the melt, and combustion rates in the hood (based on hood flow patterns).

3. Based on plausible expectations of what may be encountered during testing, establish the chemical/physical mechanisms for gas production that cause pressurization within the ISV off-gas system.
4. Calculate the maximum pressure that could occur in the off-gas system.
5. Using the information gained from the pressure calculations, perform supplementary calculations to determine the response of the off-gas piping interior to pressure transients and extremes. Determine if the resultant maximum pressure could be adequately contained by existing off-gas treatment containment seals. If found to be inadequate, review or create other seal designs that could be used.
6. If the potential pressure calculations exceed design requirements for the off-gas seals, expand the calculation to estimate the concentrations of hazardous materials that could be released through the off-gas treatment system containment seals. Compare these to the exposure limits for these materials.

3.12.3 Related Technical Issues

3.2 Hood containment seals are adequate.

3.12.4 References

1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.13 Off-gas treatment system capacity for treatment of products from within the hood is adequate. (Priority: 15/25)

3.13.1 Description

3.13.1.1 Description of the Issue. Within the Acid Pit are a number of volatile and semivolatile contaminants that could be emitted to the environment during ISV processing. These include nitrates, sulfates, and organics. To prevent possible emissions, an off-gas system is placed over the ISV melt. The off-gas treatment system must perform the following tasks:

1. Supply a sufficient flow rate to maintain the necessary vacuum pressure within the confinement hood to prevent the leakage of hazardous and/or radioactive effluents from the confinement hood or the off-gas treatment system.
2. Scrub and filter the off-gas to remove hazardous and/or radioactive waste within the off-gas to ensure the exiting gas is environmentally safe.
3. Cool the off-gas to ensure the temperature of the exiting gas is near ambient.
4. Supply enough oxygen for full combustion of off-gasses in the hood.

3.13.1.2 Importance. The composition of the hazardous and radioactive material exiting the off-gas treatment system must be within the standards set by the government. The off-gas treatment system must be able to safely scrub, filter, and cool the off-gas to meet these standards.

3.13.1.3 Influencing Factors. The influencing factors for this issue are:

1. The composition of the off-gas exiting the confinement hood.
2. Flow rate of the off-gas.

3.13.1.3.1 The Composition of the Off-Gas Exiting the Confinement Hood—The off-gas is composed of vapors generated within the ISV melt, particles entrained within the vapors, and products from combustion within the confinement hood. Vapors generated within the ISV melt are due to the pyrolysis of organic materials, void volumes, sealed containers, and volatile inorganics. It is assumed that no sealed containers or void volumes are within the Acid Pit; therefore, major mechanisms of vapor generation are pyrolysis and volatile materials. The Acid Pit contains tributyl phosphate, Amsco, and organic wastes. These materials can pyrolyze and produce combustible vapors.¹ Pyrolyzed products could yield other hazardous products through reactions with adjacent

nitrate material or other inorganics. Potential volatile inorganics within the Acid Pit are nitric acid, sulphuric acid, fluorine, aluminum nitrate, hydrogen fluoride, and perchloric acid. Although not observed, nitrate reactions with carbonaceous materials may produce cyanides or aromatic amines.² Under the assumption that no or little radioactive waste is in the pit, volatile radionuclides can be neglected.

Non-volatile particulates can be entrained within the off-gas stream.^{2,3,4} The following material may be found within the Acid Pit: lime, depleted or normal uranium, calcium hydroxide, sodium hydroxide, zirconium, and chromium. The heavier the element and/or compound is, the less likely it will become entrained in the off-gas stream.

Pyrolyzed products will combust within the confinement hood with sufficient oxygen. Therefore, it is necessary to determine the products of combustion to determine the design of the off-gas treatment system to handle those products.

Based on pilot-scale tests,^{4,5} the following was learned about the components of the off-gas treatment system. Larger particles are collected primarily in the venturi scrubber (see Reference 5). Fluorides and chlorides not dissolved in the melt can be scrubbed by the off-gas treatment system using a caustic scrub solution (see Reference 5). The Venturi-ejector scrubber effectively removed several of the nonvolatile soil components during a pilot-scale test (see Reference 4). HEPA filters were effective in removing submicron particles, which were not easily removed by scrubbers and condensers. Semi-volatile elements like cesium, potassium and sodium were more uniformly collected by the venturi-ejector and hydro-sonic scrubbers.

3.13.1.3.2 Flow Rate of the Off-gas—The flow rate of the off-gas must be known to maintain the vacuum pressure within the confinement hood, to effectively treat the off-gas, and to supply sufficient air for combustion (see Reference 4). The off-gas flow rate is affected by the amount of vapor generated within the melt and the air flow used for combustion. The vapor within the Acid Pit will likely be generated from the pyrolysis of organic materials and the release of volatile inorganic materials. A cold cap, a low melt temperature, and a high melt viscosity will reduce the amount of vapor generation. A certain amount of air will be necessary to ensure complete combustion of the combustible vapor entering the confinement hood. This air flow will also affect the off-gas flow rate.

3.13.2 Closure Requirements

3.13.2.1 Assumptions.

1. There are no void volumes or sealed containers in the Acid Pit.
2. There is no radioactive material within the Acid Pit.

3.13.2.2 Requirements and Steps to Close Issue.

1. Characterize the site through historical waste disposal records and sampling of the Acid Pit (see Reference 1); determine the type, amount, and location of hazardous and/or radioactive materials within the pit.
2. Determine the off-gas flow rate necessary for complete combustion of any organic contaminants in the off-gas system.
3. Determine the products of combustion through experiments and numerical simulations.
4. Determine the temperature of the off-gas entering the off-gas treatment system. The off-gas treatment system needs to be designed to reduce the temperature of the off-gas to ambient.
5. Determine the amount and type of particulates that are entrained within the off-gas stream. Also determine where the particles will precipitate or plate-out in the system.

3.13.3 Related Technical Issues

3.10 Off-gas generation caused by combustion is contained within the hood.

3.18 Excessive off-gas generation caused by combustion is contained within the off-gas treatment system.

3.13.4 References

1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)
2. J. W. Shade, R. K. Farnsworth, and C. H. Kindle, Technical Issues for ISV Processing of Buried Waste Sites, Letter Report from Pacific Northwest Laboratory prepared for EG&G, Idaho, Inc., April 1990.
3. Calvin E. Slater, Carl M. Stoots, and Robert J. MacKinnon, Discussion of Technical Issues Associated with the Application of In Situ Vitrification at the Idaho National Engineering Laboratory and a Suggested Approach for their Resolution, EGG-WM-9048, September 1990.

4. J. L. Buel, V. F. FitzPatrick, C. L. Timmerman, J. G. Carter, and K. H. Oma, In Situ Vitrification of Transuranic Waste: An Updated Systems Evaluation and Applications Assessment, PNL-4800, DOE Contract No. DE-AC06-76RLO1830, March 1987.
5. V. F. FitzPatrick, In Situ Vitrification - A Status of the Technology, PNL-SA-14281, September 1986.

3.14 Pressurizations due to explosions remain contained within the off-gas treatment system. (Priority: 18/25)

3.14.1 Description

3.14.1.1 Description of the Issue. Several mechanisms can be postulated that could cause explosions to occur both in and above the melt. Possible mechanisms that could produce explosions in the melt include the melt encountering inherently explosive compounds such as organic nitrates or military ordnance. Explosions above the melt could occur as a result of explosive gases collecting in the hood and detonating as they reach their explosive concentrations. A potential scenario for a hood explosion is a temporary loss of power which could cause the air supply and the attendant combustion of the off-gases to cease. Without the availability of an emergency generator, this could cause the off-gases to collect in the hood and explode upon reentry of air when the power is restored.

Conditions can also be postulated that can cause explosions to occur in the off-gas treatment system downstream of the hood. An explosion could result from incomplete combustion of explosive gases in the hood that subsequently collect or mix with other compounds in the off-gas treatment system and reach a concentration and environment favorable for explosion.

3.14.1.2 Importance. Detonation of explosive compounds and mixtures can cause a sudden release of energy resulting in large temperature, pressure, and off-gas excursions. The rapid energy release can potentially cause physical damage to the ISV equipment which could result in a breach of the containment and the release or expulsion of hazardous material to the environment. The off-gas treatment system must be able to withstand pressurizations that occur as a result of explosions that occur in the melt, in the hood, or in the off-gas system itself.

3.14.2 Closure Requirements and Roadmap

3.14.2.1 Assumptions.

- It is assumed that there is no military ordnance in the Acid Pit.
- It is conservatively assumed that the explosions occurring in the melt occur aboveground.

3.14.2.2 Requirements and Steps to Close Issue. The general approach will be to first characterize the Acid Pit and assess the potential presence of explosive compounds or mixtures. If it is established that explosive compounds or mixtures will be encountered, potential mechanisms for detonation will be evaluated. If plausible mechanisms are identified, calculations will then be performed to determine the maximum amounts of each explosive that can be tolerated for those detonation mechanisms or scenarios considered plausible. Estimates will then be made of the amount

of explosives to be expected. If the amounts of expected explosives are above acceptable limits, calculations will be performed to establish design requirements for an acceptable system. Both deterministic and probabilistic methods will be used in this approach.

The issue will be considered closed when the following Closure Criteria have been met:

1. The probability of explosive material being encountered is acceptably low (10^{-6})
2. The probability of an explosion occurring is acceptably low (10^{-6})
3. The off-gas treatment system will maintain its integrity after experiencing the maximum plausible explosion
4. The design requirements have been established for an ISV off-gas treatment system that will maintain its integrity after experiencing the maximum plausible explosion.

The steps to close the issues are:

1. Characterize the site according to the sampling and analysis plan for the Acid Pit to determine if explosive compounds or mixtures are in the soil.¹ Particular attention will be made to evaluate the presence of explosive compounds (ammonium nitrate, ammonium perchlorate, nitrated organics, etc.). Also, the potential for producing explosive gases (H_2 , CO, etc.) from the pit contents will be evaluated. If the probability of explosives being present is found to be acceptably low, the issue is closed under Closure Criterion 1. If explosives are found to be present or the probability of explosives being present is high, proceed to step 2.
2. If explosive compounds are found to be present, potential scenarios and mechanisms for causing explosive compounds to detonate will be examined and their probability of occurrence established. If the probability of explosions occurring is found to be acceptably low, the issue is closed under Closure Criterion 2. If the probability of explosives occurring is high, proceed to steps 3 and 4.
3. For plausible explosion scenarios and mechanisms, calculations will be performed to determine the maximum amount of each explosive that can be detonated in the selected off-gas treatment system and still have the off-gas treatment system maintain its integrity. If necessary, laboratory experiments may have to be performed to provide specific data for the calculations.
4. Perform analyses to determine the amounts of the explosive compounds that can be expected and see if the amounts are below those established in step 3. If the amounts are below those established in step 3, then the issue is closed under Closure Criterion 3. If the amounts are above those established in step 3, proceed to step 5.

5. Repeat the calculations described in step 3, except use the actual amounts of compounds expected and determine the design requirements for the off-gas treatment system to maintain its integrity. The issue is closed under Closure Criterion 4.

3.14.3 Related Technical Issues

- 3.15 Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately by the off-gas treatment system.
- 3.16 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately within the off-gas treatment system.
- 3.17 Increases in off-gas due to the melt encountering voids are contained and processed adequately within the off-gas treatment system.
- 3.18 Excessive off-gas generation caused by combustion is contained within the off-gas treatment system.

3.14.4 References

1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.15 Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately by the off-gas treatment system. (Priority: N/A)

Sudden releases of pressure that result from the breaching of pressurized sealed containers could breach or damage the hood and off-gas containment system. Since information from geophysical surveys conducted at the Acid Pit indicates the absence of large inclusions of drums and containers, the ISV Steering Committee has determined that this technical issue is not applicable to the Acid Pit.

**3.16 Sudden increases in off-gas due to waste falling from the
sidewall onto the melt surface are contained and processed
adequately within the off-gas treatment system.
(Priority: 20/25)**

3.16.1 Description

3.16.1.1 Description of the Issue. The off-gas treatment system must be able to withstand any off-gas pressurizations that may occur as a result of waste falling from the sidewall onto the melt surface. During the ISV process, the melt subsides below the initial soil surface. As the melt subsides, part of the unmelted soil forming the boundary (sidewall) to the melt may collapse onto the melt. When the subsidence of the melt is large, the potential for sidewall collapse is increased. If the amount of sidewall collapse is great, the soil that falls onto the melt surface may release large amounts of off-gas which must be processed by the off-gas system. The off-gases evolved from the Acid Pit could contain sulfuric, hydrochloric, and nitric acid, as well as organic decomposition products and particulates. These materials must be removed in a controlled manner by the off-gas treatment system to protect the environment and operational personnel. Equipment could fail from extremely large amounts of off-gases (i.e., seals may be breached by overpressurization of the hood). This is a particular problem where large containers of volatile waste materials are present. Since the Acid Pit is expected to consist of only contaminated soil, the problem is anticipated to be a small concern.

3.16.1.2 Importance. The seriousness of a possible emission depends on the type of materials that may be released and the size of the breach. This, in turn, depends on the amounts and kinds of materials present in the Acid Pit, the size of the melt, the off-gas treatment system design, and the soil conditions. Any release would be an immediate hazard to both the operational personnel and the environment.

3.16.1.3 Influencing Factors. Contributing factors that may affect the possibility of an emission include soil contamination, potential sidewall formation, melt size, melt rate, off-gas evolution rate, soil conditions, void volume, overburden, sluff angle for soils, and off-gas treatment system design.

3.16.2 Closure Requirements and Roadmap

3.16.2.1 Assumptions.

- It is assumed that the possibility of waste falling from the sidewall and causing an increase in off-gas cannot be dismissed with confidence.
- It is assumed that the Acid Pit contains only contaminated soil (no waste containers, large equipment, metal debris, etc.).

3.16.2.2 Requirements and Steps to Close Issue. The issue will be considered closed when one of the following Closure Criteria have been met:

1. The probability of waste material falling from the sidewall and causing a significant increase in off-gas rate is acceptably small. (This Closure Criterion cannot be satisfied based on the first assumption. However, the above assumption needs to be established before rejecting Closure Criterion 1).
2. The off-gas treatment system can maintain its integrity and contain increases in off-gas caused by waste material falling from the sidewall onto the melt.
3. The design requirements have been established for an off-gas treatment system to contain increases in off-gas caused by waste material falling from the sidewall onto the melt.

The steps towards issue closure are:

1. Characterize the contents of the Acid Pit. Based on historical data, recent studies, and proposed sampling, the chemicals present in the Acid Pit will be established.¹ Particular attention should be given to evaluating the presence of compounds that could generate large volumes of gas and to hazardous contaminants.
2. Estimate the amount of gas that would be generated per unit volume of waste, based on site characterization data. The volume of soil/waste that might fall into the melt can be calculated using conservative subsidence and angle of repose values. The total volume of gas that would be generated can then be calculated. Without appropriate experimental data, determining the rate at which the gas evolves will be difficult. The rate of heating and the gas release from a sidewall soil collapse can be estimated using the thermal conductivity and the specific heat of the bulk soil. A more conservative estimate can be made by assuming that vaporization is instantaneous and that gas evolution rate is determined by the rate at which the waste falls onto the melt. Conservative estimates can be made for the rate at which soil slides into the pit.
3. Based on the calculated rate of gas generation, further calculations would be performed to estimate the amount and thermal condition of the gases leaving the hood. Maximum off-gas pressures will be determined and the ability of the off-gas treatment system to maintain its integrity will be evaluated. If the off-gas treatment system can maintain its integrity, the issue is closed under Closure Criterion 2.

4. If the off-gas treatment system cannot maintain its integrity, establish the design requirements for an adequate and safe off-gas treatment system. The issue will then be closed under Closure Criterion 3.

3.16.3 Related Technical Issues

- 3.2 Hood containment seals are adequate.
- 3.4 A sidewall collapse does not impact the seal between the hood skirt and the ground.
- 3.8 Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained within the hood.
- 3.12 Off-gas treatment system containment seals are adequate.
- 3.13 Off-gas treatment system capacity for treatment of products from within the hood is adequate.
- 3.14 Pressurizations due to explosions remain contained within the off-gas treatment system.
- 3.18 Excessive off-gas generation caused by combustion is contained within the off-gas treatment system.

3.16.4 References

1. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.17 Increases in off-gas due to the melt encountering voids are contained and processed adequately within the off-gas treatment system. (Priority: N/A)

If the melt encounters a large void of combustible gases, it could result in a sudden release of energy that could rupture the melt, and breach or damage the hood and off-gas containment system. Since information from geophysical surveys conducted at the Acid Pit indicates the absence of substantial voids, the ISV Steering Committee has determined that this technical issue is not applicable to the Acid Pit.

3.18 Excessive off-gas generation caused by combustion is contained within the off-gas treatment system.
(Priority: 9/25)

3.18.1 Description

3.18.1.1 Description of the Issue. Most of the organic material within the vitrification zone will pyrolyze into volatile byproducts which will rise to the surface of the melt and combust upon contact with the air above the melt. The pressures and temperatures due to combustion depend upon the type and amount of byproducts formed by pyrolysis and the amount of air available for combustion. Pressures could be large enough to breach the off-gas system or to allow some of the off-gas to pass through the scrubbers and the HEPA filters untreated. This could result in the release of undesirable waste products to the environment.¹⁻⁴

3.18.1.2 Importance. The design of the off-gas treatment system must be capable of handling the pressure transients and temperatures due to combustion and still remain sealed and capable of treating the excess waste material within the off-gas. The importance of this issue lies in the threat of the possible release of hazardous and/or radioactive off-gas to the environment if the treatment system is breached or if part of the off-gas passes through the system untreated. The off-gas can be in the form of volatile hazardous and/or radioactive vapor effluents or in the form of hazardous and/or radioactive non-volatile particulates entrained by the off-gas.

3.18.1.3 Influencing Factors. The following factors influence the combustion processes within the confinement hood which affect the off-gas treatment system:

1. Composition, amount, concentration, and location of organic and combustible materials within the vitrification zone
2. Composition, amount, concentration, and location of catalytic materials within the vitrification zone that may accelerate pyrolysis
3. The amount of air within the containment hood and the amount of oxidizers within the vitrification zone
4. Cold cap existence
5. Temperature and composition of the melt
6. Design of the off-gas treatment system.

3.18.1.3.1 Composition, Amount, Concentration, and Location of Organic and Combustible Material within the Vitrification Zone—The amount and type of combustible material found within the confinement hood is determined by the amount and composition of the organic and combustible material within the vitrification zone. Pyrolytic processes convert the organic materials into combustible material (see References 1-4). The Acid Pit contains tributyl phosphate, Amsco, and other unidentified organic materials. Examples of potential combustibles that may or may not be found in the Acid Pit are materials such as gasoline, paint, wood, oil rags, paperboard, plastics, and rubber.⁵

The concentration of organic and combustible materials in the Acid Pit will influence the off-gas flow rate. The rate at which combustible material is formed will be less for a given volume of organic material spread throughout the pit as opposed to the same volume of organic material concentrated within a small region of the Acid Pit.

The depth of the organic and/or combustible material can influence the off-gas flow rate. Gases formed by pyrolysis at lower depths are less likely to escape the melt as opposed to the gases formed near the melt surface (see Reference 1).

3.18.1.3.2 Composition, Amount, Concentration, and Location of Catalytic Materials within the Vitrification Zone that may Accelerate Pyrolysis—Pyrolysis may be accelerated if catalysts such as sulfuric acid, certain clay materials, or metallic oxides are present (see Reference 1). The Acid Pit contains sulfuric acid.

3.18.1.3.3 The Amount of Air within the Containment Hood and the Amount of Oxidizers within the Vitrification Zone—All combustion processes need a source of oxygen either in the form of a gas or in another form, such as a nitrate or chlorate (see Reference 1). In a normal ISV process, air is drawn into the confinement hood and mixed with the off-gas from the melt. The temperature within the hood is sufficient to promote combustion. To completely destroy the organics and combustibles within the vitrification zone, sufficient oxygen must be supplied. However, the air/off-gas flow rate may not exceed the capacity of the off-gas treatment system. The amount of combustibles determines the amount of oxygen needed to achieve complete combustion (see References 1, 2 and 4).

Combustion may also occur within the vitrification zone if the pyrolyzed organics and/or combustibles are near a sufficient amount of oxidizers (see Reference 1). Potential oxidizers within the Acid Pit are nitric acid and aluminum nitrate.

3.18.1.3.4 Cold Cap Existence—When a cold cap exists or insulated surface exists over the ISV melt, the amount of off-gas released from the melt is reduced. This in turn will reduce the amount of combustion within the hood.

3.18.1.3.5 Temperature and Composition of the Melt—At higher temperatures and lower melt viscosities, gases from the melt escape more readily. Temperature has the greater effect on gas release. Therefore, to reduce the amount of combustible vapors leaving the melt, the temperature of the melt needs to be reduced.

3.18.1.3.6 Design of the Off-gas Treatment System—The off-gas treatment system must have sufficient capacity to contain and treat gaseous releases that result from combustion and other sources such as void volumes and sealed containers. The off-gas flow rate must be large enough to contain the maximum potential flow rate while providing sufficient air for combustion and maintaining the vacuum pressure within the hood. Gases from pyrolysis can carry with them to the off-gas treatment system an amount of radionuclide elements associated with the combustible waste. The off-gas system must anticipate and treat those wastes (See Reference 4).

3.18.2 Closure Requirements

3.18.2.1 Assumptions. None.

3.18.2.2 Requirements and Steps to Close Issue.

1. Characterize the site (see Reference 5). Through historical waste disposal records and sampling of the Acid Pit, determine the type, amount, and location of organic and/or combustible materials within the pit. The type, amount, and location of potential oxidizers and pyrolytic catalysts also need to be determined.
2. Determine the mechanisms of pyrolysis and combustion for the organic and/or combustible materials found. This can be achieved experimentally or numerically.
3. Determine the magnitude and the temporal range of the pressure transients that may occur within the hood due to combustion of the materials within the Acid Pit.
4. Perform a numerical analysis of the off-gas from the hood to determine if the off-gas treatment system design used in the ISV process is capable of handling the pressure transients due to combustion.

3.18.3 Related Technical Issues

3.10 Off-gas generation caused by combustion is contained within the hood.

3.18.4 References

1. J. W. Shade, R. K. Farnsworth, and C. H. Kindle, Technical Issues for ISV Processing of Buried Waste Sites, Letter Report from the Pacific Northwest Laboratory prepared for EG&G, Idaho, Inc., April 1990.
2. Calvin E. Slater, Carl M. Stoots, and Robert J. MacKinnon, Discussion of Technical Issues Associated with the Application of In Situ Vitrification at the Idaho National Engineering Laboratory and a Suggested Approach for their Resolution, EGG-WM-9048, September 1990.
3. V. F. FitzPatrick, In Situ Vitrification - A Status of the Technology, PNL-SA-14281, September 1986.
4. J. L. Buelt, V. F. FitzPatrick, C. L. Timmerman, J. G. Carter, and K. H. Oma, In Situ Vitrification of Transuranic Waste: An Updated Systems Evaluation and Applications Assessment, PNL-4800, DOE Contract No. DE-AC06-76RLO1830, March 1987.
5. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.19 Any corrosion within the off-gas treatment system does not affect containment or effluents. (Priority: 10/25)

3.19.1 Description

3.19.1.1 Description of the Issue. The following is written for Type 304 austenitic stainless steel, components in the hood and off-gas treatment system.

3.19.1.1.1 Attack by Sulfur and its Compounds—Nickel-containing alloys are attacked by sulfur and its compound (H_2S and SO_2)^{1,2} through a process called sulfidation.^c Nickel and sulfur form NiS, an eutectic compound that melts at 303°C (579°F).³ Therefore, nickel-containing alloys are not considered "usefully resistant" to sulfur-containing atmospheres above 315°C (599°F).⁴ This is especially true under reducing conditions⁵ because the protective chromium oxide layer has less of a chance to reform after being disrupted. The concentration of sulfur in the gaseous environment that can cause sulfidation is as low as 1%.^d

Some sources of sulfur in the ISV gaseous effluent are burning paper and other organic compounds. If sulfuric acid is present in the Acid Pit, this will be another source of sulfur.

3.19.1.1.2 Attack by Chlorine and its Compounds—Chromium-containing alloys such as 304L stainless steel are attacked by chlorine and its compounds (principally HCl) in both high-temperature gases and aqueous solutions. High-temperature chlorine attack proceeds by forming metal halide scales, which give some protection to the metal. However, these metal halides have a very high vapor pressure so that they will vaporize after reaching a certain temperature, leaving the base metal unprotected (see Reference 2). This probably results in general attack (similar to the corrosion of iron when exposed to air). Corrosion is also a problem at lower temperatures when aqueous HCl is beginning to precipitate from the gas. This results in chloride stress corrosion cracking^e or pitting (see Reference 1).

Aqueous chloride attack occurs when HCl locally disrupts the Cr_2O_3 protective layer. This results in pitting and, eventually, perforation. Chloride stress corrosion cracking can also occur. Sources of chlorine are hydrochloric acid and organic compounds.

3.19.1.1.3 Attack by Carbon—Chromium-containing alloys are attacked by carbon at high temperatures. The carbon combines with the chromium, forming chromium carbides. This

c. Type 304 stainless steel nominally contains 18% chromium and 8% nickel.

d. Personal communication with R. E. Minzia, Westinghouse Idaho Nuclear Company, Inc. (WINCO), Idaho Falls, Idaho, April 2, 1991.

e. Personal communication with R. E. Minzia, Westinghouse Idaho Nuclear Company, Inc. (WINCO), Idaho Falls, Idaho, April 3, 1991

causes the alloy's chromium content to decrease, leaving it susceptible to other types of attack (see Reference 2).

Another type of attack occurs when oxidizing and reducing conditions alternate. The high-carbon areas of the alloy formed when reducing conditions dominated will be burned out and the metal oxidized. This will lead to perforation (see Reference 2).

3.19.1.2 Importance. Corrosion of the hood by the off-gases is one of the safety issues that needs to be resolved before the treatability study of the Acid Pit can be completed. If sufficient corrosion of the hood occurs, it could result in breaching of the hood during ISV operation and the escape of effluent gases. These gases will probably contain acids and pyrolysis products of organic compounds. Treating this gaseous effluent is akin to treating the gaseous effluent from an incinerator.

Another effect of these corrosive gases is degradation of the off-gas treatment system. Most of the off-gas treatment system is made of austenitic stainless steel, and wet hydrochloric acid vapors and aqueous hydrochloric acid will pit austenitic stainless steel. In addition, the acid gasses in combination with moisture could degrade the HEPA filters. Degrading the off-gas treatment system will probably reduce its efficiency and occur slowly over a period of time. It is not known whether this reduced efficiency will result in untreated off-gas release to the atmosphere.

3.19.1.3 Influencing Factors. The probability of hood corrosion depends upon many factors, among which are (a) the types and amounts of chemicals buried in the Acid Pit, (b) the hood operating temperature, and (c) the likelihood of developing a vent in the glass that spews super-heated gases onto the hood.

The factors that affect the probability of degradation of the off-gas treatment system are the same as for the hood. However, the probability of off-gas treatment system corrosion is even greater than that of hood corrosion because the hood may be somewhat protected with a coating of amorphous carbon from the ISV process. Over time, water may build up a very aggressive, fairly concentrated acid solution in the off-gas scrubber. A method of pH modification can be used to control this build up.

3.19.2 Closure Requirements and Roadmap

3.19.2.1 Assumptions.

- It is assumed that the Acid Pit contains significant amounts of nitric acid, as indicated by old shipping records.

3.19.2.2 Requirements and Steps to Close Issue.

1. Determine the amount and species of all chemicals and other buried waste in the Acid Pit. Of especial interest are acids, organic compounds, and those materials that contain chlorine and sulfur.
2. Use existing large-scale data, computer modeling, and lab testing to determine the following:
 - Off-gas temperature and composition resulting from vitrification of the Acid Pit waste
 - Degradation of various candidate hood and off-gas treatment materials after exposure to the off-gases.
3. After consulting with materials experts (personnel with experience in incinerator off-gas treatment systems should be included), design an experiment that will determine the combination of buried waste that is the most corrosive to the hood and off-gas treatment system components and the materials that best resist corrosion. The candidate materials should be in wrought form that have had welds made on them.^f
4. Perform the experiment and determine which conditions are the most corrosive and which candidate material will withstand the environment best. Analysis of the test results should provide the following:
 - The calculated corrosion rates of the hood and the off-gas treatment system components.^g This information can be used to predict how many cycles those materials will withstand before they need replacement.
 - Confidence level of these predictions.
5. Compare the calculated corrosion rates of different components to requirements set by industry or government agencies for incinerators.

f. Welds often behave differently than wrought base metals under corrosive conditions.

g. It is expected that components will have different corrosion rates that are dependent on their environment.

3.19.3 Related Technical Issues

None.

3.19.4 References

1. Metals Handbook, Ninth Edition, Volume 13, Corrosion, Metals Park, Ohio: American Society for Metals, 1987.
2. Corrosion Basics: An Introduction, Houston, Texas: National Association of Corrosion Engineers, 1984.
3. E. A. Brandes, ed., Smithells Metals Reference Book, Sixth Edition, London, England: Butterworths, pp. 11-382.
4. H. H. Uhlig and R. W. Revie, Corrosion and Corrosion Prevention, Third Edition, New York: Wiley, 1985.
5. P. D. Harvey, ed., "Stainless Steels at High Temperatures," Lesson 15 from Stainless Steels, Metals Park, Ohio: Metals Engineering Institute of the American Society for Metals, 1978.

3.20 Risks due to any exposed waste are within acceptable limits. (Priority: 4/25)

3.20.1 Description

3.20.1.1 Description of the Issue. The ISV process could expose untreated waste to the environment, posing a hazard to workers and increasing the spread of contamination to the environment. One process by which untreated waste could be exposed is through excessive subsidence. Excessive subsidence could release hazardous materials by uncovering portions of the pit next to the melt that have not been processed. A second possibility is that large amounts of newly formed and potentially unstable sidewalls could collapse onto the melt surface. If a cold cap has been previously formed on top of the melt, portions of the sidewalls that have collapsed onto the melt may not have been thoroughly processed. In this case, when the hood is removed, untreated waste could remain on the melt surface and in the newly exposed sidewalls.

3.20.1.2 Importance. This issue is significant because of the hazards that radioactive and/or hazardous waste pose to ISV workers and the environment. Because information about the contents of the Acid Pit is limited (due to past undocumented waste disposal practices), site characterization data is needed before all the risks of exposing waste can be assessed. With proper protection, such as anti-C clothing, respirators, radiation monitors, and barrier ropes, unplanned exposure of workers to radioactive/hazardous waste can be prevented, thereby lessening the importance of this issue. However, if large amounts of radioactive/hazardous waste were exposed to the environment, then further remediation might be required, increasing environmental clean-up costs and risking disapproval and unacceptance by local, state, and federal agencies. Ensuring that "risks due to any exposed waste are within acceptable limits" requires that ISV operations minimize exposure of radioactive/hazardous waste. And, any newly exposed waste would have to meet the appropriate or relevant and applicable requirements (ARARs) for radioactive and/or hazardous contaminants.

3.20.1.3 Influencing Factors. A number of factors may contribute to the risk of exposing waste due to ISV operations. These are listed below.

3.20.1.3.1 The Potential for Volume Reduction and Melt Subsidence—The potential for volume reduction at the Acid Pit is dependent on the possibility of large void fractions or large quantities of combustible waste. Ground-penetrating radar images revealed no major anomalies (such as buried trucks or drums), but an electromagnetic survey of the soil found an area of soil with higher conductivity readings than the rest of the pit, suggesting a possible concentration of contaminants. This condition could cause an increased reduction in volume during processing, increasing the melt subsidence and the potential for sidewall formation and collapse.

3.20.1.3.2 Melt Geometry and Aspect Ratio—Melt geometry is affected by many factors, including the thermal and spatial characteristics of the soil, the rate of melting, the amount of power applied, and the temperature produced during the ISV process. Controlling the size, shape, and spread of the melt is important in preventing excessive lateral melt movement.

3.20.1.3.3 Composition and Concentration of Buried Waste—The risk of exposing waste depends heavily upon the amounts of organic solvents, toxic metals, radionuclides, and metal debris buried in the soil. Historical records indicate that the Acid Pit contains miscellaneous acidic, alkaline, organic, and radioactive waste. Detailed site characterization information about the types and concentrations of each waste form in the pit is limited and further studies are needed to adequately assess this issue.

3.20.1.3.4 Soil Characteristics—Various soil characteristics affect the ISV melt geometry, sluff angle, and degree of subsidence. These include soil moisture, composition, stratigraphy, density, degree of disturbance (for example, from previous drilling activities), soil/waste ratio, angle of repose, depth of waste material, ground water location, thermal and electrical conductivity, viscosity, and specific heat. Because the soil characteristics can greatly influence melt geometry, and because melt geometry can contribute to excessive subsidence, it is important to characterize the Acid Pit soil fully before ISV is implemented.

3.20.1.3.5 Overburden Contamination—If the layer of overburden on the Acid Pit has become contaminated since application, ISV industrial operations might spread the contamination during equipment setup. Although this factor increases the risk of exposing waste and might impede the ISV setup process (by requiring increased safety measures), it should not discredit the capabilities of ISV.

3.20.1.3.6 Cold Cap Behavior—A rising cold cap can bring untreated waste above the original soil surface, complicating closure procedures and increasing the potential for future ground subsidence. (During one initial ISV test, a cold cap of porous molten soil formed on the surface of the melt and rose above the original soil surface see Reference 1). A rising cold cap should not be a problem at the Acid Pit since ISV techniques have been developed to control cold cap subsidence (e.g., graphite electrodes and surface insulation¹).

3.20.2 Closure Requirements and Roadmap

3.20.2.1 Assumptions.

- The Acid Pit soil is physically homogeneous and does not include large inclusions of metal and other debris (including drums, boxes, or equipment) or large void fractions.

3.20.2.2 Requirements and Steps to Close Issue.

1. Characterize the site according to the Acid Pit sampling and analysis plan, including verification of the estimated waste types and quantities of contaminants.² Determine the soil characteristics as discussed in Section 3.20.1.3. This step is a prerequisite to accomplishing all other closure steps and is crucial for closure of this technical issue.
2. Use modelling techniques and calculations to determine or predict the amount of volume reduction, melt geometry, and the potential angle of repose for the soil. This will be useful in estimating the potential volume of waste that may be exposed following a melt. As discussed in Section 3.20.1.3, an electromagnetic survey of the soil found an area of soil with higher conductivity readings than compared with the rest of the pit, suggesting a possible concentration of contaminants. Determine if the higher conductivity readings in this area will affect the geometry and degree of subsidence in the melt. Any variation in melt geometry, subsidence, or angle of repose may affect the amount of waste that is left unprocessed following a melt.
3. Determine if the Acid Pit overburden has become contaminated since application. Overburden contamination will require increased ISV safety measures to reduce the spread of contamination to workers and environment during preparation activities, such as drilling, hood placement, and introducing the graphite frit starter path. Safety measures should include extra personal protective equipment (anti-C clothing and respirators), barrier ropes and signs, and radiation and gas monitors. Contaminated overburden should not affect the actual melt process.
4. Use the appropriate techniques to govern cold cap subsidence (graphite electrodes and surface insulation, see Reference 1).
5. Implement effective monitoring equipment. Perhaps the greatest mitigation factor in preventing exposure of contaminated waste may be the use of effective monitoring equipment. Monitoring equipment could warn of abnormal ISV processing conditions and potential hazards, such as excessive lateral melt growth. The release of contaminants from abnormal conditions could be alleviated and/or avoided by reducing or shutting down power to the electrodes. Once power to the electrodes is terminated, contaminant release from the melt zone decreases

exponentially with time and contaminant release rates become negligible 0 to 4 hours after power is terminated.³

6. To prepare for an abnormal event of ISV operations at the Acid Pit, the following criteria should be considered:
 - Compare the estimated maximum volume of exposed contaminants to the ARARs for the contaminants of concern. These would include chemical-specific ARARs for airborne particulates, RCRA regulations for hazardous and radioactive waste, and relevant DOE Orders [such as the Direct Concentration Guidelines (DCGs)].
 - Estimate the occupational and public doses for acute and chronic exposures to a release of hazardous and/or radioactive contaminants from the Acid Pit.
7. Determine whether additional remedial activities are needed to cleanup or contain any newly exposed waste. The extent of these remedial activities needs to be estimated. If extensive, are there any mitigation activities that could be performed during ISV operations at the Acid Pit (such as backfilling the melt area while the hood is still intact) that will make ISV more economically and environmentally viable as a remedial technology for the INEL?

3.20.3 Related Technical Issues

- 3.4 A sidewall collapse does not impact the seal between the hood skirt and the ground.
- 3.5 The melt and thermally altered zone do not extend laterally beyond the hood boundaries.
- 3.21 Post-processing hood containment is maintained as required.

3.20.4 References

1. J. L. Buelt and J. G. Carter, In Situ Vitrification Large-Scale Operational Acceptance Test Analysis, PNL-5828, May 1986, pp. 33-34.
2. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3. D. A. Lamar and T. J. McLaughlin, "Large-scale Radioactive Testing of the In Situ Vitrification Process at the 216-2-12 Crib," Safety Analysis Documentation, PNL, May 1987, pp. 49-50.

3.21 Post-processing hood containment is maintained as required. **(Priority: 3/25)**

3.21.1 Description

3.21.1.1 Description of the Issue. Hood containment of radioactive and/or hazardous constituents is not only necessary during the ISV melt process but is also required after the melt is complete. Vapors and particulates that are generated during the melt process are trapped by the hood and then processed by the off-gas treatment system. Accordingly, vapors and particulates that are released during the cooling of the melt product after ISV processing, also need to be contained and processed. Once power to the electrodes is terminated, the contaminant release from the melt zone decreases exponentially with time.¹ Modelling predicts that contaminant release rates become negligible 0 to 4 hours after power to the electrodes is terminated (see Reference 1).

Remaining vapors and particulates need to be processed by the off-gas treatment system before the hood can be safely removed. Determining when to remove the hood requires careful monitoring with radiation and gas monitors and off-gas treatment system controls. Accessing the hood during the melt process or after the melt is complete, could cause serious injury to ISV workers. This includes damaging the lungs and/or skin, increasing the possibility of contracting cancer from radiological/chemical exposure, burns, heat exhaustion, and maybe death. Premature hood removal could also produce a release of airborne radiological/chemical constituents, which might result in occupational and/or public exposure or the spread of contamination, increasing environmental cleanup costs.

3.21.1.2 Importance. The most significant factor in post-processing hood containment is determining when the hood can be safely removed. The underlying goal of this technical issue is to minimize the risk of contaminant exposure to ISV workers, the general public, and the environment from premature hood access or removal. Reducing, minimizing, or eliminating the risk of contaminant exposure to humans or the environment is one of the main concerns when demonstrating the viability of ISV technology for future treatability studies.

Post-processing hood containment operations involve hood access, hood maintenance, hood decontamination, contamination fixation, equipment disassembly, and soil backfilling. All of these operations present the hazard of radiological/chemical release. The probabilities of occurrence associated with these hazards have been estimated in an initial probabilistic risk assessment for an ISV large field test at the INEL.²

3.21.1.3 Influencing Factors. The following factors may influence post-processing hood containment procedures.

3.21.1.3.1 Concentration of Buried Waste—The amount of entrained, potentially hazardous particulates deposited on the interior surface of the hood and the melt surface is heavily dependent on the types and amounts of organic solvents, toxic metals, radionuclides, metal debris, and other waste buried in the pit. The length of time required for post-processing hood containment is also dependent upon the type and amount of buried waste, since variations in waste composition and its off-gas products affect the processing abilities of the off-gas treatment system. Shipping records indicate that the Acid Pit includes miscellaneous acidic, alkaline, organic, and radioactive waste. However, detailed information about the pit contents is limited and site characterization data is needed to accurately assess the implications of this issue.

3.21.1.3.2 Particulate Containment by the Melt—In addition to knowing the types and amounts of buried waste, it is important to know the ability of the melt to contain various contaminants. Some contaminants are more volatile and mobile than others and will be more readily released as particulates or vapors into the hood interior and off-gas system during the ISV process. For example, cesium is a volatile radioactive compound and (if present in the Acid Pit) will likely be released into the hood interior during ISV processing. Transuranic radioactive compounds, however, are not as volatile and are more likely to be captured and maintained within the melt product, and thus not be released or deposited into the hood and off-gas system environment.

3.21.1.3.3 Excessive Subsidence—The length of time required for post-processing hood containment also depends upon the amount of subsidence that occurs during and/or after the melt process. Excessive subsidence could result in exposure of radiological/ hazardous waste from unprocessed waste remaining either in the sidewalls or on top of the cold cap (from sidewall collapse). Premature hood removal after excessive subsidence could expose ISV workers and the environment to radioactive/hazardous waste.

3.21.1.3.4 Cold Cap Formation—The formation of a suitable cold cap acts as a barrier to vapor release. Improper formation of a cold cap impacts post-processing hood containment by lengthening the time needed to process off-gas vapors, thus increasing the time required for hood containment.

3.21.1.3.5 Melt Cooling Rate—The length of time required for hood post-processing and maintenance depends on the cooling rate of the melt product. The hood has to remain intact to contain any residual vapors or particulates that may be released during cooling of the melt product.

3.21.2 Closure Requirements and Roadmap

3.21.2.1 Assumptions.

- The Acid Pit soil is homogeneous. There are no large inclusions of metal and other debris (including drums, boxes, or equipment) or large void fractions. Ground-penetrating radar images revealed no major anomalies (such as buried trucks or drums). However, an electromagnetic survey of the soil found an area of soil with higher conductivity readings than compared to the rest of the pit, suggesting a possible concentration of contaminants.

3.21.2.2 Requirements and Steps to Close Issue.

1. Characterize the site, including verification of estimated waste types and quantities of contaminants in the Acid Pit.³ Knowledge of contaminants and their quantities can be used to predict off-gas treatment system efficiency and to estimate the types and concentration of contaminant emissions and hazardous particulates that may build up within the hood. This knowledge can be used to select the appropriate solvents and fixation agents that might be needed for hood decontamination and fixation. Also, buried waste data can be used to choose effective personal protective equipment (such as anti-C clothing, respirators, and radiation and gas monitors) to prevent worker exposure and to prevent a release of contaminants during hood access activities.
2. Review existing ISV literature and data, specifically, performance analysis data for off-gas hood containment and off-gas treatment system efficiency relative to the conditions at the Acid Pit. Determine if the current procedures used for hood access, decontamination, disassembly, and removal are viable for the Acid Pit.
3. Use modelling techniques and calculations to determine or predict the amount of volume reduction. As discussed in Section 3.21.1.3, an electromagnetic survey of the soil found an area of soil with higher conductivity readings than the rest of the pit, suggesting a possible concentration of contaminants. Determine if the higher conductivity readings have a likelihood of causing large reductions in surface volume during processing. If excessive subsidence were to occur from volume reduction, workers and the environment could be exposed to increased levels of hazardous/ radioactive waste during hood removal activities.

4. Use modelling techniques and lab-scale tests or specially designed experiments along with site characterization data to predict the amounts and types of contaminants that may be released from the melt after power to electrodes is terminated. Also, verify the predicted contaminant release rates that may occur once power is shut down. These data are important for estimating the types and concentrations of contaminants that could be present in the hood after the melt is complete, estimating the time required for off-gas post-processing hood containment, and for preventing premature hood removal.
5. Implement effective monitoring equipment. Use appropriate monitoring to determine necessary length of post-processing hood containment. Re-entry procedures should be governed by the appropriate detailed operating procedures.

3.21.3 Related Technical Issues

- 3.4 A sidewall collapse does not impact the seal between the hood skirt and the ground.
- 3.5 The melt and thermally altered zone do not extend laterally beyond the hood boundaries.

3.21.4 References

1. D. A. Lamar and T. J. McLaughlin, Large-Scale Radioactive Testing of the In Situ Vitrification Process at the 216-Z-12 Crib, Safety Analysis Documentation, Pacific Northwest Laboratory, May 1987, pp. 49-50.
2. T. E. Wierman and C. Sullivan, Initial Probabilistic Risk Assessment of the In Situ Vitrification Large Field Test Volume Three: Industrial Safety, EGG-SSRE-PRA-001-90, September 1990.
3. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.22 Underground fires are avoided.

(Priority: 17/25)

3.22.1 Description

3.22.1.1 Description of the Issue. Ignition and propagation of underground fires is complex and a function of many variables such as waste composition, moisture content, available oxygen, and ambient pressure. A combustible material can spontaneously ignite if enough oxygen and high enough temperatures are present. In the case of a landfill, certain combustible materials in the presence of adequate oxygen containing materials will oxidize. The insulating properties of the surrounding matter determine whether the heat produced is retained and the chemical oxidation rate continues to increase. If the insulating properties are such that the oxidation rate increases, the temperature will likewise increase until the combustible material eventually reaches its ignition temperature. Aerobic biological decomposition can result in a maximum waste temperature of 140 to 160°F.

3.22.1.2 Importance. An underground fire related to the ISV processing of a waste site is not a problem unless it causes one or more of the following to occur:

- Surface settlement (ground subsidence) resulting from subsurface decomposition that may affect normal ISV operations, by affecting hood containment. This poses a risk to workers and may expose previously buried waste.
- Venting of noxious vapors from the surface of the soil that may pose a risk to workers or the community.

3.22.1.3 Influencing Factors. Factors influencing the formation of underground fires are (a) location, size, and type of combustible or pyrophoric materials, (b) location, size, and type of oxidizers, (c) properties of the soil, and (d) surrounding temperature.

3.22.1.3.1 Location, Size, and Type of Combustible or Pyrophoric Materials—If a continuous layer of combustible or pyrophoric materials, in combination with an oxidizer, extends beyond the confinement hood, underground fires may propagate outside the confines of the hood and release hazardous materials to the environment and endanger workers at the ISV site. Some items such as wood, paper board, or oil rags may be present in extensive layers or zones so that combustion could propagate outside the containment zone. Ponding of combustible liquids could produce similar combustion propagation. The ignition temperature for combustion is dependent on the type of material. Pyrophoric reactions are a special case of spontaneous combustion where ignition can occur immediately on exposure to oxygen. Ignition temperatures for pyrophoric materials are low compared to ignition temperatures for combustible materials. Pyrophoric materials can include metals with high surface areas (powders and lathe shavings), organics such as oil or

grease rags, partly decayed vegetation, and certain hydrides. Combustible or pyrophoric materials within the Acid Pit are tributyl phosphate, Amsco (a kerosene-like substance), aluminum, and organics.

3.22.1.3.2 Location, Size, and Type of Oxidizers—To create and maintain an underground fire, oxygen must be present. The oxygen source must also continuously extend beyond the confinement hood to propagate underground fires beyond the hood. Oxygen can be in the form of air, nitrates, chlorates, or other sources. The Acid Pit contains large amounts of nitrates.

3.22.1.3.3 Properties of the Soil—Certain combustible materials in the presence of adequate oxygen will oxidize. The insulating properties of the surrounding material determine whether the heat produced is retained and the chemical oxidation rate increases. If the insulating properties are such that the oxidation rate increases, the surrounding temperature will likewise increase until the combustible material eventually reaches its ignition temperature.

3.22.1.3.4 The Surrounding Temperature—As previously mentioned, combustion and pyrophoric processes are dependent on the temperature. If the surrounding temperature rises to the ignition temperature, combustion or pyrophoric reactions will occur.

3.22.2 Closure Requirements

3.22.2.1 Assumptions. None.

3.22.2.2 Requirements and Steps to Close Issue.

1. Characterize the site according to the Acid Pit sampling and analysis plan.⁴ Through historical waste disposal records for the Acid Pit and sampling of the Acid Pit, determine the type, amount, and location of organic and/or combustible materials within the pit. The type, amount, and location of potential oxidizers need to be determined.
2. Determine the mechanisms needed for underground fire generation and propagation. This may include details on the amount and form of oxidant required, ignition temperatures, surface area of pyrophoric materials, etc. This can be achieved experimentally and/or numerically.
3. During the ISV process, install temperature measuring devices within the soil to determine if underground fires are occurring.

3.22.3 Related Technical Issues

- 3.6 Pressurizations due to explosions remain contained within the hood.
- 3.10 Off-gas generation caused by combustion is contained within the hood.
- 3.14 Pressurizations due to explosions remain contained within the off-gas treatment system.

3.22.4 References

1. Letter report from J. W. Shade, R. K. Farnsworth, and C. H. Kindle, Pacific Northwest Laboratory, to EG&G Idaho, Inc., Subject: "Technical Issues for ISV Processing of Buried Waste Sites," April 1990.
2. Calvin E. Slater, Carl M. Stoots, and Robert J. MacKinnon, Discussion of Technical Issues Associated with the Application of In Situ Vitrification at the Idaho National Engineering Laboratory and a Suggested Approach for their Resolution, EGG-WM-9048, September 1990.
3. The Merck Index: An Encyclopedia of Chemicals, Drugs, and Biologicals, 11th edition, Rahway, New Jersey: Merck & Co., Inc., 1989.
4. EG&G Idaho, Inc., Radioactive Waste Management Complex Subsurface Disposal Area Acid Pit Investigation: Sampling and Analysis Plan, EGG-WM-9638, DOE Contract No. DE-AC07-76ID015670, Revision 2, October 1991. (Information only.)

3.23 Electrical hazards are controlled. (Priority: 25/25)

3.23.1 Description

3.23.1.1 Description of the Issue. Equipment used to date for ISV has been designed and built to requirements of the National Electrical Code (NEC) and other codes and standards relative to electrical equipment. It is, therefore, assumed that electrical hazards associated with normal operation of lights, electrical heaters, transformers, and off-gas system pump motors are no greater than would be expected for any other industrial operation. However, there have been some electrical hazards that have been identified which are somewhat unique to ISV. These hazards include:

1. The metal containment hood and/or surrounding support structure becoming electrically energized.
2. Catastrophic failure of electrical power supply equipment.
3. The possibility of stray currents. This includes both the possibility of stray current corrosion and high energy stray currents that could be hazardous to personnel and equipment.

3.23.1.2 Importance. The importance of this issue arises from the threat of electrical shock to ISV workers from electrical mishaps. Worker safety should be of highest priority when conducting ISV tests. The first two hazards can be controlled by the use of proper safety measures. Electrical shock hazards during ISV setup, operation, and maintenance (including the electrical shock hazard that could result during electrode lengthening) can be controlled by separation of operations from overhead power lines and insulation of conductors. Insulation of conductors should be inspected and tested. Only authorized personnel using electrical gloves and rubber shoe covers should be permitted in the controlled area during ISV operations. Lock and tag procedures and protective equipment should be used when working on electrical systems. Specific Health and Safety Plans will give detailed information on the personnel protective measures and the emergency plans needed during ISV tests.

The third hazard may be important if stray currents from ISV activities at the Radioactive Waste Management Complex (RWMC) could cause corrosion and perforation of underground metal structures for miles around. Examples of structures that could be affected are underground storage tanks, double-walled pipes at the Idaho Chemical Processing Plant (ICPP) that carry mixed hazardous wastes, and emergency firewater pipes. "Stray electrical currents are those that follow paths other than the intended circuit, or they may be any extraneous currents in the earth. If currents of this kind enter a metal structure, they cause corrosion at areas where the currents leave again to enter the soil or water."¹ Stray currents can travel underground for miles if they have conductive paths (e.g., metal pipes or, in the case of RWMC, an aquifer). During the Intermediate Field Test (IFT) at Test Area North (TAN), Westinghouse Idaho Nuclear Company, Inc. (WINCO) personnel in charge of maintaining the cathodic protection system at ICPP placed a potentiometer on a pipe to determine whether the IFT affected the voltage readings. A 0.15 volt increase was detected, but the readings were taken at such intervals that it was not known whether the IFT was the proximate cause of the voltage increase. [Note that the test site (TAN) was over 20 miles from the place at which the voltage increase was detected (ICPP)].

The full-scale ISV process uses 5 megawatts (about 2200 volts at 2200 amps) to vitrify the ground, increasing the possibility of an ISV operation causing a significant electrical stray current. The amount of metal corroded, or wasted, is proportional to the amount of current that leaves the structure. Stray current corrosion is concentrated at the point of exit from the metal structure, so the damage takes the form of pitting rather than general attack.^h Therefore, even small currents can cause perforation quickly (depending on the thickness of the metal being attacked).

3.23.1.3 Influencing Factors. To be determined.

3.23.2 Closure Requirements and Roadmap

3.23.2.1 Assumptions.

- It is assumed that electrical hazards associated with normal operation of lights, electrical heaters, transformers, and off-gas system pump motors are no greater than would be expected for any other industrial operation.
- It is assumed that accidental power-up of the system when electrodes are being lengthened, the metal containment hood and/or surrounding support structure become electrically energized, or catastrophic failure of electrical power supply equipment can be controlled through the use of proper safety measures.

3.23.2.2 Requirements and Steps to Close Issue. As stated earlier, most of the electrical hazards can be controlled through proper safety measures. However, the issue of stray currents requires additional steps to resolve the issue.

1. Use computer modeling and engineering calculations to determine if stray currents may be of concern for ISV operation in the INEL SDA.
2. Inform ICPP personnel (or suitable outside contractors with experience in cathodic protection and stray current detection) of the date for the next in-ground ISV experiment. (Engineering-scale tests may not be applicable here because the metal container used in engineering-scale tests will effectively stop all stray currents.)
3. Identify structures at different distances and depths that will be monitored. Measurements should be made on these structures before and after the ISV test.
4. Monitor those structures continuously with recording instruments to measure the change in potential and amperage during the ISV experiment.
5. Compare the records to the duration of the ISV experiment.

h. Personal communication with R. E. Minzia, Westinghouse Idaho Nuclear Company, Inc. (WINCO), Idaho Falls, Idaho, August 1990.

6. If stray currents are detected, consult experts in cathodic protection to determine the following:

- The severity of the problem
- Ways to mitigate the effects.

3.23.3 Related Technical Issues

None.

3.23.4 References

1. H. H. Uhlig and R. W. Revie, Corrosion and Corrosion Control, Third Edition, New York: Wiley, p. 120.

END

**DATE
FILMED**

6 / 4 / 92