AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 2

Environmental Assessment

Self-Scrubbing Coal™: An Integrated Approach to Clean Air

A Proposed Clean Coal Technology Demonstration Project

**Shade Township
Somerset County, Pennsylvania**

January 1994

**U.S. Department of Energy
Assistant Secretary for Fossil Energy**

MASTER

YBR

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
INTRODUCTION	1
1.0 PURPOSE AND NEED FOR THE PROPOSED FEDERAL ACTION .	5
2.0 PROPOSED FEDERAL ACTION AND ALTERNATIVES	7
2.1 THE PROPOSED ACTION	7
2.1.1 Project Location	10
2.1.2 Laurel Coal Preparation Plant Site	11
2.1.2.1 Water Management Operations	14
2.1.3 Description of Proposed Technology	18
2.1.4 Proposed Activities for Custom Coals No. 1 Plant	25
2.2 ALTERNATIVES ELIMINATED FROM CONSIDERATION ..	30
2.3 NO-ACTION ALTERNATIVE	31
2.4 ALTERNATIVE SITES	31
3.0 ENVIRONMENTAL IMPACTS OF THE PROPOSED FEDERAL ACTION AND THE NO-ACTION ALTERNATIVE	32
3.1 THE PROPOSED ACTION	32
3.1.1 Atmospheric Resources	32
3.1.1.1 Regulatory Issues	33
3.1.1.2 Proposed Project Air Pollution Sources and Mitigation Measures	34
3.1.1.3 Modeling Method and Results	37
3.1.2 Land Resources	39
3.1.3 Water Resources	41
3.1.3.1 Discharge Water Quality	43
3.1.3.2 Additional Environmental Protection Measures	47
3.1.4 Ecological Resources	48
3.1.5 Floodplains and Wetlands	50
3.1.6 Waste Management	52
3.1.7 Transportation	54

TABLE OF CONTENTS (CONTINUED)

3.1.7.1	Demonstration Phase Assumptions	56
3.1.7.2	Commercial Phase Assumptions	56
3.1.7.3	Study Results	59
3.1.7.4	Summary	61
3.1.8	Noise	61
3.1.8.1	Study Results	62
3.1.8.2	Summary	65
3.1.8.3	Construction/Health and Safety Impacts	66
3.1.9	Socioeconomic Impacts	67
3.1.10	Cultural and Historic Resources	68
3.1.11	Energy and Material Resources	59
3.1.12	Occupational Health and Safety	70
3.1.13	Pollution Prevention	70
3.1.14	Biodiversity	71
3.1.15	Cumulative and Long Term Impacts	72
3.1.16	Findings	73
3.2	THE NO-ACTION ALTERNATIVE	75
3.3	REGULATORY COMPLIANCE	76
3.3.1	Air Permit Application	76
3.3.2	Coal Refuse Disposal Permit	76
3.3.3	Coal Mining Activity Permit	77
3.3.4	Other Required Permits	78
4.0	ENVIRONMENTAL IMPACTS OF THE PROPOSED FEDERAL ACTION AT THE TEST BURN SITES	79
4.1	CHESWICK POWER PLANT	79
4.1.1	Project Activities and Site Description	79
4.1.2	Environmental Impacts	80
4.1.2.1	Atmospheric Resources	80
4.1.2.2	Land Resources	85
4.1.2.3	Water Resources	86
4.1.2.4	Ecological Resources	86
4.1.2.5	Transportation Impacts	87
4.1.2.6	Socioeconomic Impacts/Cultural Resources	87
4.1.2.7	Energy and Material Resources	88
4.1.3	Regulatory Compliance	88

TABLE OF CONTENTS (CONTINUED)

4.2	WHITEWATER VALLEY GENERATING STATION	88
4.2.1	Project Activities and Site Description	88
4.2.2	Environmental Impacts	89
4.2.2.1	Atmospheric Resources	92
4.2.2.2	Land Resources	94
4.2.2.3	Water Resources	94
4.2.2.4	Ecological Resources	96
4.2.2.5	Transportation Impacts	97
4.2.2.6	Socioeconomic Impacts/Cultural Resources	97
4.2.2.7	Energy and Material Resources	98
4.2.3	Regulatory Compliance	98
4.3	ASHTABULA C POWER PLANT	98
4.3.1	Project Activities and Site Description	99
4.3.2	Environmental Impacts	99
4.3.2.1	Atmospheric Resources	99
4.3.2.2	Land Resources	102
4.3.2.3	Water Resources	105
4.3.2.4	Ecological Resources	105
4.3.2.5	Transportation Impacts	106
4.3.2.6	Socioeconomic Impacts/Cultural Resources	106
4.3.2.7	Energy and Material Resources	107
4.3.3	Regulatory Compliance	107
5.0	LIST OF AGENCIES AND PERSONS CONSULTED	108
6.0	REFERENCES	111
APPENDIX: AGENCY CONSULTATIONS		

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
1	Proposed Demonstration Site Locations	8
2	Regional Location - Laurel Coal Preparation Plant Site	9
3	Laurel Coal Preparation Plant Site	12
4	Laurel Coal Preparation Plant Plot Plan	13
5	Existing Treatment System	16
6	Existing Collection System	17
7	Schematic for Proposed Demonstration of Advanced Coal Cleaning Technology	20
8	Proposed Custom Coal No. 1 Plant Plot Plan	27
9	Proposed Custom Coals No. 1 Plant Site	28
10	Proposed Treatment System	42
11	Floodplain Map of the Proposed Custom Coals No. 1 Plant	51
12	Existing and Projected Peak Hour Traffic Volumes	55
13	Residences Exceeding FHWA Guidelines During A.M. Peak Hour in Year 2013	58
14	Cheswick Power Plant Site	81
15	Cheswick Power Plant Plot Plan	82
16	Whitewater Valley Generating Station Site	90
17	Whitewater Valley Generating Station Plot Plan	91
18	Ashtabula C Power Plant Site	100
19	Ashtabula C Power Plant Plot Plan	101

LIST OF TABLES

<u>Table</u>	<u>Page</u>
1 Proximate and Ultimate Analysis of Proposed Demonstration Phase Coals	23
2 Trace Element Concentrations of Proposed Demonstration Phase Coals (and Sorbent Additive)	24
3 Proximate and Ultimate Analysis of Commercial Phase Coals	25
4 Laurel Coal Preparation Site 1992 Ambient Air Quality Monitoring Data	33
5 Summary of Potential Emissions Due to the Proposed Custom Coal No. 1 Plant (Tons/yr)	35
6 Existing and Projected Annual Average PM-10 Concentrations	38
7 Existing and Projected Second High 24-Hour PM-10 Concentrations	40
8 Outfall 002 (Pond K) Discharge Data and Regulatory Requirements	45
9 Comparison of Existing and Projected Noise Levels	66
10 Cheswick Power Plant Site 1990-1993 Ambient Air Quality Monitoring Data	84
11 Cheswick Power Plant Test Burn Data	85
12 Whitewater Valley Generating Station Site 1989-1992 Ambient Air Quality Monitoring Data	93
13 Whitewater Valley Generating Station Test Burn Data	95
14 Ashtubula C Power Plant Site 1989-1992 Ambient Air Quality Monitoring Data	103
15 Ashtabula C Power Plant Test Burn Data	104

LIST OF ACRONYMS AND ABBREVIATIONS

ACM	asbestos containing material
ACPP	Centerior Energy's Ashtabula C Power Plant
CAA	Clean Air Act, as amended in 1990
CaSO ₄	calcium sulfate
CCI	Custom Coals International
CCT	Clean Coal Technology
CEQ	Council on Environmental Quality
CFR	Code of Federal Regulations
CMAP	Coal Mining Activity Permit
CO	carbon monoxide
CO ₂	carbon dioxide
CPP	Duquesne Light Company's Cheswick Power Plant
CQIM	Coal Quality Impact Model
CRDP	Coal Refuse Disposal Permit
dBA	Decibels read on the A-scale of a sound level meter
DOE	U.S. Department of Energy
DOI	U.S. Department of the Interior
EA	Environmental Assessment
EIS	Environmental Impact Statement
EIV	Environmental Information Volume
EPA	U.S. Environmental Protection Agency
EPRI	Electric Power Research Institute
ESP	electrostatic precipitator
HOP	Highway Occupancy Permit
HT	Tri-Axle Heavy Truck
IDEM	Indiana Department of Environmental Management
lb/MMBtu	pounds per million British thermal units
L _{eq}	energy equivalent sound level
mm	millimeter
mph	miles per hour
MSHA	Mine Safety and Health Administration
MT	Medium Truck
MW	megawatt
NAAQS	National Ambient Air Quality Standards
NEPA	National Environmental Policy Act
NO ₂	nitrogen dioxide
NO _x	oxides of nitrogen
NPDES	National Pollutant Discharge Elimination System
O ₃	ozone
OHPO	Ohio Historic Preservation Office
OSHA	Occupational Safety and Health Administration
PADER	Pennsylvania Department of Environmental Resources

LIST OF ACRONYMS AND ABBREVIATIONS (CONTINUED)

PCB	polychlorinated biphenyls
PEIS	Programmatic Environmental Impact Statement
PennDOT	Pennsylvania Department of Transportation
PETC	Pittsburgh Energy Technology Center
pH	measure of acidity/alkalinity
PHMC	Pennsylvania Historical and Museum Commission
PM	particulate matter
PM-10	particulate matter less than or equal to 10 microns in aerodynamic diameter
PON	Program Opportunity Notice
ppm	parts per million
PSD	Prevention of Significant Deterioration
ROM	run-of-mine
SO₂	sulfur dioxide
SO₃	sulfur trioxide
SR	State Route
tph	tons per hour
tpy	tons per year
TSP	total suspended particulate matter
T-xxx	Township Road number
VOC	volatile organic compounds
WVGS	Richmond Power and Light's Whitewater Valley Generating Station
µg/m³	micrograms per cubic meter

INTRODUCTION

This environmental assessment (EA) was prepared by the U.S. Department of Energy (DOE), in compliance with the National Environmental Policy Act (NEPA) of 1969, Council on Environmental Quality (CEQ) regulations for implementing NEPA (40 CFR 1500-1508) and DOE regulations for compliance with NEPA (10 CFR 1021), to evaluate the potential environmental impacts associated with a proposed demonstration project to be cost-shared by DOE and Custom Coals International (CCI) under the Clean Coal Technology (CCT) Demonstration Program of DOE's Office of Fossil Energy. CCI is a Pennsylvania general partnership located in Pittsburgh, Pennsylvania engaged in the commercialization of advanced coal cleaning technologies.

The proposed federal action is for DOE to provide, through a cooperative agreement with CCI, cost-shared funding support for the land acquisition, design, construction and demonstration of an advanced coal cleaning technology project, "Self-Scrubbing Coal: An Integrated Approach to Clean Air." The proposed demonstration project would take place on the site of the presently inactive Laurel Coal Preparation Plant in Shade Township, Somerset County, Pennsylvania. A newly constructed, advanced design, coal preparation plant would replace the existing facility. The cleaned coal produced from this new facility would be fired in full-scale test burns at coal-fired electric utilities in Indiana, Ohio and Pennsylvania as part of this project.

The CCT Demonstration Program is a \$5 billion technology demonstration program that was legislated by Congress to be funded jointly by the federal government and industrial or other sector participants. The goal of the Program is to make available to the U.S. energy marketplace a number of advanced, more efficient, reliable, and environmentally responsive coal utilization and environmental control technologies. These technologies are intended to reduce or eliminate the economic and environmental impediments that limit the full consideration of coal as a future energy resource. Over the next decade, the Program will advance the technical, environmental and economic performance of these advanced technologies to the point where the private sector will be able to introduce them into the commercial marketplace. Each of these demonstrations is

in a scale large enough to generate sufficient design, construction and operation data for the private sector to judge the technology's commercial potential and to make informed confident decisions on its commercial readiness.

The strategy being implemented to achieve the goal of the CCT Demonstration Program is to conduct a multiphase effort consisting of at least five separate solicitations for projects, each with individual objectives that, when integrated, will make technology options available on a schedule consistent with the demands of the energy market and responsive to the relevant environmental considerations.

On October 23, 1989, Public Law 101-121, "An Act Making Appropriations for the Department of the Interior and Related Agencies for the Fiscal Year Ending September 30, 1990, and for Other Purposes" (the "Act"), was signed into law. This Act, among other things, provided funds to conduct cost-shared CCT projects for the design, construction and operation of facilities that would demonstrate the feasibility of future commercial applications of technologies capable of replacing, retrofitting or repowering existing facilities. Subsequently, Public Law 101-512 was signed into law on November 5, 1990. This Law, among other things, directed DOE to issue a "general request for proposals" for CCT Round IV by no later than February 1, 1991, and to select projects for negotiations no later than eight months after the date of the general request for proposals. On January 15, 1991, DOE issued a Program Opportunity Notice (PON) for Round IV of the CCT Demonstration Program, soliciting proposals to conduct cost-shared CCT projects to demonstrate innovative, energy-efficient clean coal technologies capable of being commercialized in the 1990's. The technologies proposed in response to this PON were to be capable of (1) achieving significant reductions in the emissions of sulfur dioxide (SO₂) and/or oxides of nitrogen (NO_x) from existing facilities and/or (2) providing for future energy needs in an environmentally acceptable manner. The proposed demonstration project was selected along with eight other projects from among the 33 proposals received by DOE.

To comply with the environmental review requirements of NEPA, the CCT Demonstration Program has developed a three-level strategy that is consistent with the CEQ regulations for implementing NEPA and DOE regulations for compliance with NEPA. The

strategy includes the consideration of both programmatic and project-specific environmental impacts during and subsequent to the project selection process. For the first level of environmental review, DOE prepared a programmatic environmental impact statement (PEIS). The PEIS, issued by DOE as a public document in November 1989 (DOE/EIS-0146), addressed the potential environmental consequences of the widespread commercialization of each of 22 successfully demonstrated clean coal technologies in the year 2010. The PEIS evaluated (1) a no-action alternative, which assumed that the CCT Demonstration Program was not implemented and that conventional coal-fired technologies with flue gas desulfurization controls were used for new plants or as replacements for existing plants that were retired or refurbished, and (2) a proposed action, which assumed that CCT Demonstration Program projects were selected for cost-shared funding support and that successfully demonstrated technologies underwent widespread commercialization by 2010.

At the second level of environmental review, a confidential pre-selection project-specific environmental review was prepared for each of the proposals submitted under CCT Round IV that were determined to be suitable for comprehensive evaluation. This review summarized for the Source Selection Official the strengths and weaknesses of each specific project relative to the environmental evaluation criteria including, to the maximum extent possible based upon the information provided in the proposal, a discussion of alternative sites and technologies reasonably available to the proposer, a brief discussion of the potential environmental impacts of each proposal, necessary mitigative measures and a list of known permits and licenses which must be obtained to implement the proposal.

The third element of DOE's NEPA strategy provides for the preparation and public distribution of site-specific NEPA documents for each of the projects selected for proposed financial assistance under the PON. This EA provides a site-specific analysis of the potential environmental impacts of the proposed federal action. In accordance with NEPA, this EA will result in either a Finding of No Significant Impact or a determination that significant impacts may occur and that an Environmental Impact Statement (EIS) must be prepared. The sources of information for this EA include the technical proposal for the project submitted by CCI to DOE in response to the CCT Round IV PON; discussions with

CCI and their environmental consultants; discussions with federal and state agencies; the CCI Environmental Information Volume (EIV) for the project provided by CCI to the DOE (CCI EIV, July 1993, Revised); and visits to the Laurel Coal Preparation Plant site.

The scope of this EA includes consideration of (1) the nature and extent of proposed construction, installation and operational activities; (2) changes in emissions, effluents and wastes that would be generated; and (3) changes in resource requirements. To fulfill the requirements of Section 1508.9 of the CEQ regulations, the following information is provided in this EA:

- Purpose and Need for the Proposed Federal Action
- Proposed Federal Action and Alternatives
- Environmental Impacts of the Proposed Federal Action and the No-Action Alternative
- List of Agencies and Persons Consulted
- References

1.0 PURPOSE AND NEED FOR THE PROPOSED FEDERAL ACTION

The proposed federal action is for DOE to provide, through a cooperative agreement with CCI, cost-shared funding support for the land acquisition, design, construction and demonstration of an advanced coal cleaning technology project, "Self-Scrubbing Coal: An Integrated Approach to Clean Air." The proposed demonstration project would take place on a purchased site where the inactive Laurel Coal Preparation Plant in Shade Township, Somerset County, Pennsylvania, is located. A newly constructed, advanced design, coal preparation plant would replace the existing facility. The cleaned coal produced from this new facility would be fired in full-scale test burns at coal-fired electric utilities in Indiana, Ohio and Pennsylvania as part of this project.

Successful future application of the proposed demonstration project could result in reduced SO₂ emissions from both new and existing coal-fired plants. No reductions in NO_x emissions would result. The Clean Air Act, as amended in 1990, (CAA) instigates the implementation of a market-based approach for the control of SO₂ emissions designed to result in very significant reductions (by about 9 million tons by 2000, down from 1980 levels of around 26 million tons). The CAA also supports the incentives for clean coal technology demonstration projects funded through DOE. Future use of such technologies could help contribute to the attainment of post-2000 air quality standards for SO₂ and NO_x. The CCT Demonstration Program, in concert with the CAA, encourages and assists in the development of clean-burning coal technologies for electrical generating plants. SO₂ emissions reduction is being pursued to meet post year-2000 air quality standards.

The proposed advanced coal cleaning technology was identified as a project which, if successfully demonstrated at large-scale commercial operation, would assist utilities in achieving SO₂ emission reductions. Reductions in the emissions of SO₂, a National Ambient Air Quality Standards (NAAQS) criterion air pollutant, would be achieved by burning fuel provided by a reliable, efficient, coal-cleaning process without negatively impacting utility boilers or air pollution control devices. This would provide utilities with another option to meet CAA requirements in addition to the use of as-mined low sulfur coal or modifications such as flue gas treatment by a scrubber. Accordingly, the proposed demonstration of this

technology has the potential to contribute significantly toward achieving the objectives of the CCT Demonstration Program.

Additionally, the objective of the proposed demonstration of this technology is consistent with the U.S. Environmental Protection Agency (EPA) pollution prevention strategy for federal agency activities. The intent of EPA's pollution prevention initiative is to reduce the amount and/or toxicity of pollutants being generated, thereby reducing the environmental impacts of man's technological activities. Section 3.1.13 of this EA provides further information on pollution prevention aspects of this project.

2.0 PROPOSED FEDERAL ACTION AND ALTERNATIVES

This section presents the proposed federal action and alternatives to the proposed demonstration project. The advanced coal cleaning technology would be implemented at the Laurel Coal Preparation Plant site which would be designated the Custom Coals No. 1 Plant. Cleaned coal produced would be test burned at coal-fired electric utilities in Indiana, Ohio and Pennsylvania as part of the federal action. The potential environmental impacts of construction and operation for the proposed Custom Coals No. 1 Plant are described in Section 3.0, and the environmental impacts at the test burn sites are described in Section 4.0.

2.1 THE PROPOSED ACTION

The proposed federal action is for DOE to provide, through a cooperative agreement with CCI, cost-shared funding support for land acquisition, design, construction and demonstration of a 500 tons per hour (tph), advanced design, coal preparation plant producing either a cleaned coal ("Carefree Coal"), or a cleaned coal combined with dolomite (a carbonate of calcium and magnesium), or combined with limestone (calcium carbonate) sorbent ("Self-Scrubbing Coal"). The proposed demonstration of this technology would take place at a purchased site where the presently inoperative Laurel Coal Preparation Plant in Shade Township, Somerset County, Pennsylvania, is located. The proposed federal action would include test burns, of limited duration, of Carefree or Self-Scrubbing Coals produced by the Custom Coals No. 1 Plant, at coal-fired utilities in Indiana, Ohio and Pennsylvania. Figure 1 indicates the Proposed Demonstration Site Locations and Figure 2 shows the Regional Location of the Laurel Coal Preparation Plant site.

The proposed Custom Coals No. 1 Plant would extend current coal cleaning techniques to finer sizes of coal and would separate the coal from associated sulfur-containing minerals (pyrites) more efficiently than existing processes. Also unique to this project would be the combination of dolomite or limestone with cleaned coal to produce a coal product that would chemically react with SO_2 during combustion to reduce SO_2 emissions.

FIGURE 1. Proposed Demonstration Site Locations

FIGURE 2. Regional Location - Laurel Coal Preparation Plant Site

The total estimated cost of this proposed demonstration project is nearly \$82 million, of which DOE would provide \$38 million, or 47 percent, in cost-shared financial assistance. Federal funds for CCT Demonstration Program projects cannot be provided for facility construction, operation, or dismantlement until and unless, following completion of the NEPA review process, a determination has been made to proceed with the particular proposed project. If such a favorable outcome is reached regarding this project, a 16-month demonstration phase would be expected to begin in the winter of 1994, assuming that construction would be initiated during the winter of 1993. At the conclusion of the demonstration phase in the early part of 1996, CCI intends to continue operating the Custom Coals No. 1 Plant on a commercial basis into the year 2016.

The proposed demonstration phase would process run-of-mine coals currently burned at the test burn sites so that products of the advanced coal cleaning technology could be evaluated under actual operating conditions. Test burn coals to be cleaned would require 25 percent of the proposed Custom Coal No. 1 Plant capacity during the 16-month demonstration phase; with the remaining capacity used to process local Kittanning Seam coal for commercial sale.

During the commercial phase, the proposed Custom Coals No. 1 Plant would operate for a 20-year duration using Kittanning Seam coal. Kittanning Seam coal processed during the demonstration and commercial phases would be burned at the Homer City Power Plant in Homer City, Pennsylvania and would fulfill the existing contractual relationship between mines supplying Kittanning Seam coal to this power plant.

2.1.1 Project Locations

The Laurel Coal Preparation Plant site is located in Shade Township, Somerset County, Pennsylvania, and is situated on a 586-acre parcel of land in a rural area of southwestern Pennsylvania. The 586-acre parcel is north of U.S. Route 30 and west of State Route (SR) 160 (Figure 2).

Test burns of cleaned coals produced at the proposed Custom Coals No. 1 Plant would be conducted at Duquesne Light Company's Cheswick Power Plant (CPP) in Springdale, Allegheny County, Pennsylvania; Richmond Power and Light's Whitewater

Valley Generating Station (WVGS) near Richmond, Wayne County, Indiana; and Centerior Energy's Ashtabula C Power Plant (ACPP) near Ashtabula, Ashtabula County, Ohio (Figure 1). Test burns of Carefree or Self-Scrubbing Coals at each of these power plants would be limited to a three to five week period. Given the limited test burn activity at these power plant sites, the vast majority of project activities and potential impacts would occur at the site of the proposed coal cleaning plant.

2.1.2 Laurel Coal Preparation Plant Site

The Laurel Coal Preparation Plant was built by National Mines Corporation, Lexington, Kentucky and began operations in 1974, producing approximately 1.75 million tons per year of cleaned coal. Coal from an on-site mine was processed at this conventional coal cleaning plant and shipped off-site by rail. Figure 3 locates the outline of the Laurel Coal Preparation Plant site with respect to SR 160 and Township Roads 649 and 744 which cross the property. The figure indicates the approximate location of the coal refuse disposal facility; the refuse truck access road; the water storage tank; the coal preparation plant area; thirteen ponds, an aeration basin and lime slurry building that comprise the remainder of the site water collection and treatment system; two streams that receive discharges from the site water management system (Miller Run and Little Dark Shade Creek); two groundwater monitoring wells and the outparcel property that is not part of the proposed demonstration project.

Figure 4, Laurel Coal Preparation Plant Plot Plan, shows major features located near the coal preparation plant area such as the portal to the underground coal mine, coal preparation plant, railroad loop and loadout building, administration and shop buildings, thickener tank used to recover magnetite (iron oxide particles with magnetic properties), sample building, two caustic tanks used to treat Pond F water before discharge, run-of-mine coal storage and unloading area, breaker building used for coal crushing, two clean coal silos, an underground and elevated coal conveying system which fed coal from the underground mine to the run-of-mine coal storage, coal preparation plant, silos and the railroad loadout building.

FIGURE 3. Laurel Coal Preparation Plant Site

FIGURE 4. Laurel Coal Preparation Plant Plot Plan

The site closed in 1982 due to economic considerations. When the site closed, mine-seepage water was no longer required to be pumped from the underground coal mine and treated by the site water management system (see Section 2.1.2.1). As a result, the underground mine was flooded. The site has not been used for commercial activities since 1982 except for an 18-month period in 1986 when Hansen Coal Mining Company, a West Virginia company, leased part of the elevated coal conveying system, the two silos and the railroad loadout facilities. During this time, Hansen transported coal by truck from West Virginia to the site and loaded 3-unit trains (72 cars each) per week using the leased facilities. In 1992, Triebel Inc. purchased the Laurel Coal Preparation Plant site from National Mines Corporation. Triebel is a subsidiary of Everclear Valley, Inc., a Delaware holding company, engaged in coal mining and coal related activities. After the completion of a favorable NEPA outcome, CCI would purchase land containing the Laurel Coal Preparation Plant site currently owned by Triebel, Inc.

2.1.2.1 Water Management Operations

In 1974 the Laurel Coal Preparation Plant was constructed with an elaborate site water management system. The purpose of this system was to provide process and potable water for the site and to treat water resulting from site activities. This system consisted of numerous ponds, underground pipelines with pumping capabilities, an on-site deep well supplying a 200,000-gallon storage tank, and water treatment facilities.

Upon closure of the underground mine and the coal preparation plant in 1982, the site water management system was modified to create 1) the existing treatment system (Figure 5) and 2) the existing collection system (Figure 6). The purpose of these two systems is to provide for environmentally sound water discharges from the site which comply with Pennsylvania Department of Environmental Resources (PADER) requirements. The potable water system remained unchanged.

The existing treatment system consists of 1) treatment components (a lime slurry building and an aeration basin) which are connected by several underground pipelines to four ponds (Ponds I, J, K and Surge Pond) and a sump (Figures 3 and 5). Water from Pond K flows to Pond I in a surface diversion ditch and subsequently to Pond J which is

periodically pumped to the Surge Pond. Water from Pond K also flows to a sump which continually returns this leachate to the upper portion of Pond K. Pond K is divided into an upper and lower portion. The upper portion collects stormwater and leachate from the existing coal refuse disposal facility as well as treated water containing excess lime from the aeration basin. This excess lime allows further water treatment to take place in the upper portion of Pond K. Solids formed as a result of the lime treatment settle out of the water in the upper portion of Pond K.

Water in the Surge Pond is sampled and periodically analyzed. When monitoring results indicate that treatment is required, water in the Surge Pond is pumped to the lime slurry building for treatment where it is mixed with a lime slurry and discharged into the aeration basin. Then, the water from the aeration basin flows by gravity to the upper portion of Pond K for further settling.

The upper portion of Pond K may overflow during periods of above normal rainfall into the lower portion of Pond K. When the lower portion of Pond K reaches a predetermined height, the water is monitored and treated with sodium carbonate so that it meets PADER water quality discharge permit criteria, and is discharged to Miller Run.

The existing collection system consists of Ponds A-B, L, M and N (Figure 6). The purpose of this system is to collect stormwater which may contain coal fines left in the soil from previous operations of the Laurel Coal Preparation Plant. The water collected in these four ponds is allowed to evaporate, or gravity discharged to Little Dark Shade Creek or Miller Run as these ponds near their storage capacity. Before any discharge to streams is allowed, this water is treated in the ponds with sodium carbonate. Additional information on stream discharge permits is contained in Section 3.3.

Ponds C, D, E, F and G, shown only on Figure 3, collect stormwater which is allowed to evaporate. There is no discharge from these ponds to any receiving stream. These ponds serve no current purpose and are a remnant of the previous Laurel Coal Preparation Plant operations.

SCHEMATIC

Reference: CCI EIV, July 1993 (Revised).

FA93031017V4

FIGURE 5. Existing Treatment System

SCHEMATIC

Note: Discharges from each pond are neutralized with sodium carbonate.

Reference: CCI EIV , July 1993 (Revised).

FA93031016V5

FIGURE 6. Existing Collection System

2.1.3 Description of Proposed Technology

Carefree and Self-Scrubbing Coals would be produced through an aggressive, proprietary, two-stage sulfur and mineral matter removal process. This proposed technology combines conventional coal cleaning technology with new technology consisting of finely ground magnetite in an aqueous suspension to clean very fine-sized coal which is separated in an advanced cyclone for sulfur and ash removal. This new technology was developed and patented at DOE's Pittsburgh Energy Technology Center (PETC). As PETC researchers were developing their laboratory findings, CCI was in the process of developing and patenting similar technology. Realizing that the PETC technology complemented their own process, CCI licensed the Micro-Mag patent from PETC in early 1993.

Sulfur in coal occurs chiefly as pyrite and as organic sulfur. Conventional physical coal cleaning processes are able to remove approximately 40% of the inorganic sulfur. However, conventional coal cleaning processes cannot remove organic sulfur which is chemically bonded with the organic molecules of the coal. Only chemical coal cleaning processes have the ability to remove organic sulfur and none of these processes have been demonstrated at near commercial scale and they are not likely to be demonstrated within the next five to ten years. These chemical cleaning processes require the use of severe operating conditions not currently being used in coal cleaning, and some of the processes use corrosive reagents and toxic gases.

In the first process stage of the proposed project, run-of-mine coal is subjected to a combination of coarse coal cleaning and selective crushing in a dense-media cyclone separation process using ultra-fine magnetite slurries. This unique separation system removes non-combustible material from the coal, including more than 90 percent of its pyritic sulfur resulting in the product, Carefree Coal. The Carefree Coal produced by the proposed demonstration project would achieve compliance with the CAAA mandate for SO₂ emissions.

This process alone, however, cannot produce a compliance coal from coals with high organic sulfur content. In these cases, Self-Scrubbing Coal would be produced. Self-Scrubbing Coal is Carefree Coal taken one step further. The finest fraction of the Carefree Coal is pelletized with dolomite or limestone. During combustion at utility plants, 30-35

percent of the remaining pyritic and organic sulfur would react with this dolomite or limestone, thereby reducing SO_2 present in the flue gas. Self-Scrubbing Coal would be able to reduce sulfur emissions by 70 percent compared to run-of-mine coal. The use of coals produced by the proposed demonstration project by electric utilities as a fuel source for coal-fired power plants could help contribute to the attainment of post-2000 air quality standards for SO_2 .

Figure 7 is a simplified flow diagram of the coal cleaning process. Run-of-mine coal would be crushed by a coal breaker producing raw coal, and then the raw coal would be divided into three size intervals using screens: intermediate raw coal, 38.1 millimeters (mm) to 1.1 mm; fine raw coal, 1.1 mm to 0.105 mm; and ultra-fine raw coal, 0.105 mm to 0.015 mm.

The three sizes of raw coal would be cleaned using a dense-media cyclone separation process which is described below. This process is able to separate the raw coal into three fractions: cleaned coal, middlings and refuse (ash and pyritic sulfur) using differences in specific gravity. The cleaned coal fraction has a specific gravity of 1.2 to 1.3 (water has a specific gravity of 1.0) while the middlings, that fraction which contains high quality coal locked with pyrite or other high density impurities, have a specific gravity between 1.3 and 2.0. The refuse fraction has a specific gravity equal to or greater than 2.0. The separation of the clean coal, middlings and refuse fractions present in the raw coal is accomplished by mixing crushed coal into a heavy water slurry (water with suspended solids) that has a specific gravity of 1.2 to 1.3. This raw coal and heavy water slurry mixture is then placed in a cyclone (similar to a funnel in appearance) and rotated in one direction at high speed. The centrifugal (whirlpool-like) action generated in the cyclone causes the low density materials (clean coal) to rise to the top of the cyclone while the high density materials (refuse) sink to the bottom. The middlings stay in the middle, between the refuse and clean coal, hence their name. The clean coal is collected from the top of the cyclone, the refuse from the bottom and the middlings from the middle.

Reference: Clean Coal Technology
Demonstration Program Update, February 1992.

FIGURE 7
SCHEMATIC FOR PROPOSED DEMONSTRATION OF ADVANCED COAL CLEANING TECHNOLOGY

The intermediate raw coal is mixed into a heavy water slurry and separated into the three fractions described above using two cyclones set in series. The middlings collected from the intermediate cyclone process are crushed to a size of less than 0.5 mm, separated by size using screens, and added to the fine raw coal or ultra-fine raw coal cleaning process. Similar cycloning, coal/refuse separation sequences are then performed on the fine raw coal and ultra-fine raw coal. Any material not retrieved as coal from the ultra-fine process is disposed of as refuse.

Magnetite is used to create the heavy water slurry which promotes separation of clean coal (specific gravity 1.2 to 1.3) and refuse (specific gravity 2.0). The clean coal and the refuse recovered from the cyclones are dewatered using screens in which the magnetite/water liquid slurry drains from the clean coal or refuse through the screen. Magnetite that has adhered to the clean coal is rinsed off with water, densified (concentrated) in densifiers (settling tanks), and returned to the cyclones. Trace amounts of magnetite (less than one-half of 1 percent) would continue with the clean coal and become part of the Carefree Coal or Self-Scrubbing Coal products, or become part of the refuse. Magnetite is currently used in conventional heavy media coal processing; however, the Self-Scrubbing Coal technology proposes to use cyclones and a finely grained magnetite to maximize the fine coal cleaning efficiency.

After settling of the cleaned coal/water slurry in thickeners and dewatering by screening, the intermediate, fine, and ultra-fine high quality cleaned coals would be dried using an indirect thermal dryer (powered by No. 2 fuel oil) and combined to produce a composite clean coal. If this coal has a low enough sulfur content to comply with CAA requirements, the product is ready for shipment and is called a Carefree Coal. If the composite coal still has a sulfur content that would produce unacceptable emissions during combustion, sorbent addition would be employed and the resulting product is termed a Self-Scrubbing Coal. In Carefree Coal because low quality, high density refuse has been removed from the coal, less fly ash and slag products would be produced during combustion in comparison to that produced from the burning of conventionally cleaned coals.

In producing a Self-Scrubbing Coal, the coal is combined with dolomite or limestone, and then pressed into briquettes. Upon combustion, the added sorbent would react with

organic sulfur in the coal to produce an ash by-product of calcium or magnesium sulfate instead of SO_2 . Because much of the ash forming mineral impurities have been removed from the composite coal, the increase in ash by-product produced due to the addition of sorbent would have minimal impact on the total quantity of ash produced and would not overload electrostatic precipitators (ESP) which remove particles from flue gas streams. Refuse generated from coal cleaning, after settling in a thickener, would be dewatered by screening. Refuse remaining on the screen is considered "coarse" refuse. Small refuse particles contained in the water passing the screen are considered "fine" refuse. Coarse refuse would be trucked to the coal refuse disposal facility on the Laurel Coal Preparation Plant site. This coal refuse disposal facility is located approximately 6,000 feet west of the proposed coal preparation plant area and would be accessed through a roadway easement located on neighboring private property. The fine slurry refuse would be pumped through an existing pipeline to the coal refuse disposal facility.

Four different coals would be processed during the proposed demonstration phase; Sewickley, Illinois No. 5, and Lower Freeport coals as they are the test burn coals for this project. Kittanning Seam coal would be processed during portions of the demonstration phase and all of the commercial phase due to its abundance in Somerset County, Pennsylvania. Table 1 shows the proximate and ultimate analysis of coals that would be used in the proposed demonstration phase of the project. Data presented in this table show, among other information, how much refuse would be generated from the cleaning of these coals and the percent of sulfur and ash in the cleaned coals. Also presented is information on Carefree and Self-Scrubbing Coal.

Table 2 shows trace element concentrations of run-of-mine, cleaned coal and refuse that would be generated by the test burn coals. The reduction in trace elements present in cleaned coals would result in increased trace elements content in the refuse. Dolomite and limestone are included in this table as they are a component of Self-Scrubbing Coal.

Table 3 shows the proximate and ultimate analysis for Kittanning Seam coal which would be processed during both the demonstration and commercial phases. Data presented in this table show, among other information, how much refuse would be generated from the cleaning of these coals and the percent of sulfur and ash in the cleaned coals.

TABLE 1**PROXIMATE AND ULTIMATE ANALYSIS OF PROPOSED DEMONSTRATION PHASE COALS**

DESCRIPTION	SEWICKLEY			ILLINOIS NO. 5			LOWER FREEPORT		
	Feed	Carefree	Refuse	Feed	S	Refuse	Feed	S	Refuse
Dry Tons	149,131	100,395	48,736	26,930	21,210*	5,720	100,878	73,076*	27,802
Dry Yield (%)	100	67	33	100	79	21	100	72	28
Moisture (%)	5	7	52	6	6	52	5	6	52
PROXIMATE									
Ash (%)	29.24	11.18	66.44	9.26	11.85	25.28	13.19	10.28	39.13
Sulfur (%)	1.56	0.70	3.33	3.08	1.28	9.16	4.12	1.32	11.06
Btu	10,195	12,304	5,851	13,102	12,306	10,514	12,920	N/A	8,709
ULTIMATE (%)									
Carbon	58.19	72.84	N/A	73.00	71.45	N/A	69.72	71.57	N/A
Hydrogen	4.05	5.07	N/A	5.08	4.97	N/A	5.80	5.95	N/A
Sulfur	1.39	0.70	N/A	3.08	1.28	N/A	2.59	1.32	N/A
Nitrogen	1.17	1.46	N/A	1.45	1.42	N/A	1.35	1.39	N/A
Oxygen	5.96	8.75	N/A	8.13	9.02	N/A	7.35	9.49	N/A
Ash	29.24	11.18	N/A	9.26	11.85	N/A	13.19	10.28	N/A

*Does not include sorbent weight estimated at 2,573 tons for Illinois No. 5 and 8,664 tons for Lower Freeport.

N/A = Not Available (Ultimate analysis is typically not performed on coal refuse).

S = Self-Scrubbing

Reference: CCI EIV, July 1993 (Revised).

TABLE 2

**TRACE ELEMENT CONCENTRATIONS OF PROPOSED
DEMONSTRATION PHASE COALS (AND SORBENT ADDITIVE)**

TRACE ELEMENT	SEWICKLEY SEAM COAL			ILLINOIS NO. 5 COAL			LOWER FREEPORT COAL			DOLOMITE/ LIMESTONE (ppm)
	ROM Coal (ppm)	Cleaned Coal (ppm)	Refuse (ppm)	ROM Coal (ppm)	Cleaned Coal (ppm)	Refuse (ppm)	ROM Coal (ppm)	Cleaned Coal (ppm)	Refuse (ppm)	
Antimony	0.80	0.26	2.09	N/A	N/A	N/A	1.08	0.42	4.35	0.3
Arsenic	14	3.5	39.16	6.8	2.96	8.37	19.4	7.04	11.70	1.1
Beryllium	N/A	N/A	N/A	0.66	0.49	0.73	1.78	0.63	N/A	N/A
Cadmium	0.2	0.34	N/A	5.90	2.41	7.33	0.11	0.04	N/A	N/A
Chromium	16.07	8.22	34.88	13.16	7.17	15.61	12.05	4.93	31.6	5
Cobalt	0.27	0.22	0.39	N/A	N/A	N/A	4.9	1.87	3.48	1
Lead	14.73	6.16	35.27	90.77	10.3	123.72	10.8	3.84	73.89	0.01
Mercury*	0.16	0.14	0.21	578.1	443.47	633.29	0.35	0.12	N/A	N/A
Nickel	13.39	8.21	25.81	27.5	9.7	34.79	15.8	6.17	21.79	4.25
Selenium	1.14	1.24	0.90	1.16	0.57	1.40	3.5	1.25	3.26	0.07

* Parts Per Billion

ROM = Run-of-Mine

N/A = Not Available

ppm = parts per million

Reference: CCI EIV, July 1993 (Revised).

After the completion of a favorable NEPA outcome, CCI would purchase land containing the Laurel Coal Preparation Plant site currently owned by Triebel, Inc. The land to be acquired by CCI consists of 586 acres. The inactive coal preparation plant area consists of 134 acres, while the coal refuse disposal facility is 64 acres in size. The balance

2.1.4 Proposed Activities for Custom Coals No. 1 Plant

Reference: CCI, October 1993.

* Hourly rates. Annual throughput of feed coal is estimated at 2,500,000 tons.

DESCRIPTION	Feed	Carefree	Refuse	KITANNING SEAM	
Dry Tons*	475	361	114		
Dry Yield (%)	100	76	24		
Moisture (%)	5	6.5	50.5		
PROXIMATE					
Ash (%)	20.64	7.06	63.64		
Sulfur (%)	2.87	0.87	9.20		
Btu	12,196	14,561	4,707		
ULTIMATE (%)					
Carbon	69.71	84.28	N/A		
Hydrogen	3.69	4.08	N/A		
Sulfur	2.87	0.87	N/A		
Nitrogen	1.14	1.37	N/A		
Oxygen	1.95	2.34	N/A		
Ash	20.64	7.06	N/A		

TABLE 3 PROXIMATE AND ULTIMATE ANALYSIS OF COMMERCIAL PHASE COAL

of the acreage consists of buffer areas and tracts of land which form the southwestern portion of the property which will not be used for Custom Coals No. 1 plant operation.

Planned demolition activities for the proposed Custom Coals No. 1 Plant would be confined to the existing portions of the property already disturbed by the former Laurel Coal Preparation Plant site facilities. Although some of the existing Laurel Coal Preparation Plant site facilities would be refurbished including the two clean coal silos and much of the coal conveying system, many of the existing facilities would be demolished to create room for the proposed Custom Coals No. 1 Plant. Structures to be demolished include the stacking tube, breaker building, the coal preparation plant, thickener tank and an elevated conveyor. (See Figure 4).

New facilities to be installed include: an elevated conveyor, preparation plant building, thermal dryer, a 5,000 ton capacity clean coal silo, five open treatment tanks for coal cleaning (two densifiers and three thickeners) similar to structures at wastewater treatment plants, a new run-of-mine coal unloading area with truck scales, and a cleaned coal truck loading area consisting of a storage bin and truck scale. An above ground storage tank area for No. 2 fuel oil, and a stacking tube would also be installed on-site. Figure 8 shows the proposed Custom Coals No. 1 Plant plot plan.

Figure 9 shows general selected features within the site vicinity including roadways, residences, and the Shade Church. A junkyard is located between the preparation plant area and the coal refuse disposal facility, as are open fields containing residences and wooded areas. Mining activities occur within the general region of the project.

Materials resulting from demolition activities that could not be used in the Custom Coals No. 1 Plant would be sold or disposed of in a permitted landfill in accordance with PADER regulations. Waste materials would consist of concrete, wood, metals from the conveyor and other systems, and equipment used in the former preparation plant structure for coal processing. Asbestos would be removed from all structures prior to demolition.

Reference: CCI EIV, July 1983 (Revised).

FA93031008V3

FIGURE 8. Proposed Custom Coals No. 1 Plant Plot Plan

FIGURE 9. Proposed Custom Coals No. 1 Plant Site

New construction would include a truck receiving station, plant feed conveyor, 500 tph preparation plant, three thickeners, two densifiers, a clean coal silo, a reclaim conveyor, and a truck loadout building. Precautions would be taken to control erosion during construction by implementing a sedimentation and erosion control plan which would be submitted for approval to the Somerset County Soil Conservation Service and PADER. Sediment and erosion control measures would be in-place prior to demolition and construction. Disturbed areas would be revegetated promptly to minimize erosion due to precipitation and runoff.

The proposed Custom Coals No. 1 Plant would produce approximately 50,397 tons of fine refuse slurry and 116,608 tons of coarse refuse during the demonstration project. During commercial operation, it is estimated that 203,125 tons of fine refuse slurry and 421,875 tons of coarse refuse would be generated annually. All refuse would be disposed of at the existing on-site coal refuse disposal facility located on the northwestern portion of the property. The base of the coal refuse disposal facility was formed in 1974 by spreading and compacting coarse coal refuse from previous operations of the previous coal preparation plant. Leachate and stormwater water from the coal refuse disposal facility are currently collected by the existing water management system. The coal refuse disposal facility has the capacity to handle the refuse from the proposed demonstration project and sixteen years of commercial operation. A new coal refuse disposal facility would then be needed to continue commercial operation. Water resources issues and environmental impacts are discussed in Sections 3.1.3 and 3.1.6.

Land use at the Custom Coals No. 1 Plant would be substantially the same as previous operations and is not expected to require additional pond construction or result in substantial changes in topography except for the coal refuse disposal facility. The final height of the coal refuse disposal facility would not be out of place with regard to surrounding topographical features. Most areas that are meadows and woodlands (located on undisturbed areas of the site) would remain untouched. An existing tree line 550 feet long and 20 feet wide would be disturbed to place the on-site run-of-mine truck route. An approximately 15 locust and maple trees, 6-12 feet in height and less than 6 inches in diameter would be cleared. Surrounding land uses would be similar to those present at the time of previous preparation plant activities.

2.2 ALTERNATIVES ELIMINATED FROM CONSIDERATION

Under Round IV of the CCT Demonstration Program, DOE solicited proposals to conduct cost-shared CCT projects to demonstrate innovative, energy efficient, technologies that offered the prospect for commercialization in the 1990's. The selection guidelines included the capability of reducing emissions from existing facilities and/or providing for future energy needs in an environmentally acceptable manner. Other than compliance with these basic objectives of the CCT Demonstration Program, location of the project in the United States and the use of coal from U.S. mines, the prospective offerors were not constrained with regard to technology or site. For those proposals submitted that were determined to be suitable for comprehensive evaluation, each received a confidential pre-selection environmental review. This review summarized for the Source Selection Official the strengths and weaknesses of the specific project relative to the environmental evaluation criteria including, to the maximum extent possible based upon the information provided in the proposal, a discussion of alternative sites and technologies reasonably available to the proposer, a brief discussion of the potential environmental impacts of each proposal, necessary mitigative measures and, to the extent known, a list of permits and licenses which must be obtained in implementing the proposal.

Based upon the overall technical and environmental merit of the respective proposals, including the Program Policy Factors, the Source Selection Official selected a series of projects for possible cost-shared financial assistance, within the budgetary constraints of Round IV of the CCT Demonstration Program. The proposed demonstration project was included among the nine selected under Round IV of the CCT Demonstration Program for its potential to demonstrate the use of innovative emission reducing technologies for the control of SO₂ emissions from coal-fired boilers. Given the nature of the CCT selection process, DOE is limited to either accepting or rejecting the overall demonstration project as proposed by the participant, including both the technology and site designated by the offeror. Therefore, the only technology and sites addressed in this EA are those proposed by the participant. Alternative sites were considered by the offeror, and these sites are discussed later in this section.

2.3 NO-ACTION ALTERNATIVE

Under the No-Action Alternative, whereby DOE does not provide cost-shared funding support, it is likely that the CCI advanced coal cleaning technology would not be demonstrated. CCI may elect to complete the project without DOE participation or cancel the project which would result in the project not contributing to the objective of the CCT Demonstration Program, which is to make a number of advanced, more efficient, economically feasible, and environmentally acceptable coal technologies available to the U.S. energy marketplace. Without DOE funding, the offeror would likely not construct the proposed demonstration project. If the CCI process is not demonstrated, it is unlikely that electric utilities would be able to plan the use of this advanced coal cleaning technology as a component of their strategy to attain post-2000 air quality standards for SO₂.

2.4 ALTERNATIVE SITES

Alternative sites for the proposed Custom Coals No. 1 Plant were considered by CCI prior to their selection of the Laurel Coal Preparation site. The sites were screened for the following siting constraints: the ability of CCI to acquire the site; the site's ability to house the coal preparation and material handling facilities; the current permit status of the site; the proximity to coal sources applicable to the Self-Scrubbing Coal technology; availability of a permitted coal refuse disposal facility; existing on-site utilities; and existing transportation access. CCI originally chose the Solar Coal Processing Plant site, near Stoystown, Somerset County, Pennsylvania for the proposed Custom Coals No. 1 Plant site and the Cooperative Agreement between CCI and DOE was signed in anticipation of the proposed demonstration project being at the Stoystown site. Further investigation of available alternative sites by CCI, revealed that the Laurel Coal Preparation Plant site, near Central City, Somerset County, Pennsylvania, was preferred as the Laurel Coal Preparation Plant site was found to be superior when compared to the Stoystown site. The Laurel Coal Preparation Plant site would require less ancillary facilities, create less impact on existing traffic patterns, was free and clear of any legal disputes and did not appear to be restricted by any of the above constraints (CCI EIV, July 1993, Revised).

3.0 ENVIRONMENTAL IMPACTS OF THE PROPOSED FEDERAL ACTION AND THE NO-ACTION ALTERNATIVE

3.1 THE PROPOSED ACTION

This section discusses the environmental impacts of the proposed Custom Coals No. 1 Plant located in Shade Township, Somerset County, Pennsylvania. This assessment has been prepared by utilizing available reference material, conducting information searches and direct investigation of the proposed Custom Coals No. 1 Plant site. Emphasis is placed on those features that could be affected by the proposed action. Figure 8 shows the general area of the proposed Custom Coals No. 1 Plant including adjacent residences, the Shade Church, and adjacent roadways. The area shown in this figure as not part of project property contains land which is partially wooded, containing a junkyard and four residences. Section 4.0 describes environmental impacts at the test burn sites.

3.1.1 Atmospheric Resources

The area of southwestern Pennsylvania where the proposed Custom Coals No. 1 Plant would be located has a humid continental climate with warm summers (average temperature 70°F) and fairly cold winters (average temperature 33°F). The average annual precipitation for this area is 42 inches according to the Somerset County, Pennsylvania Soil Survey. Somerset County is in the Central Pennsylvania Interstate Air Quality Control Region (40 CFR 81.104). Ambient air pollutant concentrations in the Shade Township area are better than the NAAQS for total suspended particulate matter (TSP), particulate matter less than or equal to 10 microns in aerodynamic diameter (PM-10), SO₂, nitrogen dioxides (NO₂), and carbon monoxide (CO). The area is designated as nonattainment of the NAAQS for ozone (O₃), and ambient O₃ concentrations are classified as marginal (40 CFR 81.339). Table 4 shows ambient air quality data for this area.

TABLE 4
LAUREL COAL PREPARATION SITE
1992 AMBIENT AIR QUALITY MONITORING DATA¹

Pollutant	Averaging Period	NAAQS	Maximum Ambient Concentration³
CO	8-hour	10	6.9
	1-hour	40	10.2
Pb	Quarterly	1.5	0.09
NO₂	Annual	100	36
O₃	1-hour	235	186
PM-10	Annual	50	28
	24-hour	150	67
TSP	Annual	No Standard	51
	24-hour	No Standard	203
SO₂	Annual	80	34.7
	24-hour	365	240
	3-hour	1300²	403

¹All values are in $\mu\text{g}/\text{m}^3$ except CO which are in mg/m^3 .

²Secondary standard

³CO, NO₂, O₃, PM-10, and SO₂ data are from Cambria County monitors located approximately 16 miles north of the site. Pb and TSP data are also from a Cambria County monitor located approximately 19 miles north of the site. Data are presented for the most recent year reported.

Reference: PADER Bureau of Air Quality Control, 1993.

3.1.1.1 Regulatory Issues

Both Federal and State regulations have been promulgated to provide pre-construction review of industrial projects that could potentially have an adverse impact on ambient air quality. The federal regulations are codified in Title 40 of the Code of Federal Regulations, Part 52 (40 CFR 52); the State regulations are codified in Title 25 of the Pennsylvania Code, Subchapter C, Article III, Chapter 127.

Regulations for Prevention of Signification Deterioration (PSD) apply, to major construction projects in clean air areas, i.e., areas for which existing ambient air pollutant concentrations are better than the NAAQS, and areas that are unclassifiable due to a lack of monitoring data. Pollutants for which the proposed project could be subject to PSD review include TSP, PM-10, SO₂, NO₂, and CO. A different set of regulations apply to proposed major construction projects in areas that do not achieve ambient air pollutant levels prescribed by the NAAQS. The only pollutant for which the proposed project could be subject to offset requirements is ozone.

Based on the amount of air pollutants potentially emitted from the proposed project, PADER has determined that the proposed project is not subject to PSD or New Source Review (NSR) regulations.

In the case of a coal cleaning plant with a thermal dryer, both stack releases (i.e., those from point sources) and non-stack releases (i.e., those from fugitive sources) must be considered when evaluating air quality impacts. Fugitive sources cause emissions that cannot easily be captured and will typically include sources such as plant roadways, outdoor storage piles, and material handling operations occurring out of doors. Secondary emission sources are defined in air quality regulations as emissions from off-site sources, such as transport vehicles delivering material to the plant site and are typically included in air quality impact assessments. Secondary emissions do not count in determining the potential to emit of a stationary source.

3.1.1.2 Proposed Project Air Pollutant Sources and Mitigating Measures

Table 5 presents a summary of the potential air pollutant emissions estimated to result from the proposed project based on operation 240 days per year. Emission quantities are presented on an annual basis for TSP, PM-10, SO_x, NO_x, HC and carbon dioxide (CO₂). As discussed above, PADER has determined that these emission quantities do not subject the proposed Custom Coals No. 1 Plant to PSD or NSR.

TABLE 5
SUMMARY OF POTENTIAL EMISSIONS
DUE TO PROPOSED CUSTOM COALS NO. 1 PLANT (Tons/yr)

Source	TSP	PM-10	SO _x	NO _x	HC	CO
<u>Point Sources</u>						
Hot Oil Furnace	0.6	0.3	8.6	6.0	*	1.5
Indirect Thermal Dryer	2.3	2.3	*	*	*	*
<u>Fugitive Sources</u>						
Process Sources	17.0	8.6	*	*	*	*
Coal Storage Pile Emissions	2.8	1.4	*	*	*	*
Vehicle Travel on Plant Roads	5.8	1.3	0.1	1.0	0.3	1.1
Point and Fugitive Sources Total	28.5	13.9	8.7	7.0	0.3	2.6
<u>Secondary Sources (local only)</u>						
Vehicle Travel on Refuse Road	16.7	3.5	*	0.4	0.1	0.4
Refuse Truck Dumping	0.8	0.4	*	*	*	*
Vehicle Travel on Off-site Paved Roads	10.4	3.8	*	10.8	1.5	8.6
Secondary Emissions Total	27.9	7.7	*	11.2	1.6	9.0

- Notes: 1. * Indicates emissions of less than 0.1 tons per year.
2. Due to the scrubber on the indirect thermal dryer, all particulate emissions are presumed to be PM-10.
3. Total emissions for the proposed project would be the sum of the point sources, fugitive sources, and the secondary emissions.

Reference: DOE environmental contractor, October 1993.

Point sources included in the proposed coal cleaning plant are the hot oil furnace and the thermal dryer. The hot oil furnace would use low sulfur oil and a low-NO_x burner to minimize releases of SO₂ and NO₂ which would result from fuel oil combustion. The thermal dryer would use a wet scrubber to minimize emissions of TSP and PM-10. The EPA requires that new thermal dryers employ pollution control technology, and has specified allowable emission levels in the New Source Performance Standards (NSPS) for

thermal dryers at coal cleaning plants (40 CFR 60.250). The wet scrubber for this project would be designed to achieve a particulate emission rate of $70 \mu\text{g}/\text{m}^3$ in accordance with the Standards of Performance for Coal Preparation Plants (40 CFR 60.8).

Fugitive emission sources associated with the proposed coal cleaning plant include material handling processes, coal storage piles, and dust/exhaust produced by vehicles traveling on plant roads. Material handling processes would employ standard industry operating practices including enclosures, hoods, and filters to minimize potential particulate releases and to collect released particulates. Plant operations would be performed as wet processes to the extent practicable. Wet operation would largely eliminate particulate releases from many coal and refuse handling processes. The coal storage area would be watered regularly to minimize wind-blown dust. Most plant roads would be paved, and would be flushed with water at least twice daily followed by broom sweeping. Flushing/sweeping, and low plant traffic speed limits would minimize dust emissions from plant roadways.

However, some process operations would be performed using dry materials including raw coal delivery, transport of coal by conveyor and loading cleaned coal into transport vehicles. Particulate emission controls for dry operations include an enclosed coal unloading area; use of enclosed silos and storage bins; covering all conveyors with 3/4 hoods; enclosed pneumatic transfer of dolomite, limestone, and magnetite from trucks to storage bins; and covering all trucks carrying coal.

Secondary emission sources associated with the proposed coal cleaning plant include vehicles traveling on SR 160 and Township Road 649 and other off-site roadways, truck travel on the gravel road leading to the refuse disposal area, and activities at the coal refuse disposal facility. The refuse truck access road is a gravel road, and would be wetted on a regular basis. Activities conducted in the coal refuse disposal facility would also use wetting to reduce emissions. Other secondary sources in the vicinity of the proposed Custom Coals No. 1 Plant would be controlled using the same techniques as applied to the plant roadways i.e., road watering and sweeping. A typical street sweeping vehicle would continually clean Township Road 649 and the plant roadways.

3.1.1.3 Modeling Method and Results

Calculations were performed to estimate the proposed Custom Coals No. 1 Plant potential impact on air quality. The major pollutant generated by the proposed Custom Coals No. 1 Plant would be particulates. As shown in Table 5, other pollutants would be released in such small quantities that detailed assessment of their impacts is not required. Based on the low quantities of emissions projected for SO₂, NO_x and CO; and estimates of air quality in the area based on adjacent land uses, the NAAQS for these pollutants would not be violated by the proposed Custom Coals No. 1 Plant. Hydrocarbon emissions would be minimal and would not impact on the ozone nonattainment status of this area.

Modeling was performed on PM-10 emissions, as opposed to TSP, as PM-10 is the form of particulate which most effects human health. Calculations were performed using the Industrial Source Complex (ISC) Model in its short-term (ST) mode. The ISCST model is an EPA-developed and approved atmospheric dispersion model. Meteorological data from the nearest National Weather Service station (Pittsburgh, Pennsylvania) was used in the calculations. The impact model calculations were performed using the emission rates provided previously in Table 5.

Calculations for the model were performed for a total of 175 receptor locations surrounding the proposed project. The receptors analyzed in the model include: 1) points along the property line, 2) the actual location of an existing structure, and 3) a grid of evenly-spaced receptors located within 5 kilometers (approximately 3 miles) of the center of the proposed processing facility. Calculations were performed to acquire annual concentrations and second-highest 24-hour concentrations for direct comparison with the annual and 24-hour NAAQS for PM-10. Upon the advice of PADER a background value of 18 µg/m³ was selected for the area of the proposed Custom Coals No. 1 Plant (CCI EIV, July 1993, Revised).

Table 6 presents the results obtained from the ISCST model on an annual basis and presents results at a variety of locations included in the model. Prior to operation of the proposed project, annual ambient PM-10 concentrations in the area are calculated to be between 37 and 47 percent of the NAAQS, due solely to vehicular traffic on the paved roads included in the model. Following project startup, the ambient annual PM-10

TABLE 6**EXISTING AND PROJECTED ANNUAL AVERAGE PM-10 CONCENTRATIONS**

Location ¹	Existing Conditions		Future Conditions With Custom Coals No. 1 Plant	
	Ambient Concentration ($\mu\text{g}/\text{m}^3$)	Percent of NAAQS ⁽²⁾	Ambient Concentration ($\mu\text{g}/\text{m}^3$)	Percent of NAAQS ⁽²⁾
Residence 1	22.2	44.4	23.5	47.0
Residence 2	23.7	47.4	25.8	51.6
Residence 3	18.7	37.4	20.7	41.4
Residence 4	18.4	36.8	19.7	39.4
Residence 5	18.3	36.6	19.6	39.2
Residence 6	18.3	36.6	20.1	40.2
Residence 7	18.3	36.6	19.7	39.4
Residence 8	18.7	37.4	19.2	38.4
Shade Church	18.3	37.0	19.2	38.4
Intersection SR 160 and Township Road 649 ⁽³⁾	22.9	45.8	24.8	49.6
1.5 Miles South of Plant Adjacent to SR 160	21.4	42.8	22.2	44.4
Maximum off-site receptor	23.7 ⁽⁴⁾	47.4	25.8 ⁽⁴⁾	51.6

¹See Figure 9 for receptor locations.

²The primary National Ambient Air Quality Standard for PM-10 on an annual basis is $50 \mu\text{g}/\text{m}^3$.

³Receptor A.

⁴Same location as Residence 2.

Reference: DOE environmental contractor, October 1993.

concentrations are calculated to be between 38 and 52 percent of the annual NAAQS. The differences between the results obtained for existing and future conditions indicate that no change in the quality of air resources in the area is expected.

Table 7 presents the results obtained from the ISCST model on a 24-hour basis. Because the 24-hour PM-10 NAAQS is based on the second highest concentration, results displayed in Table 7 are also the second highest 24-hour concentrations at receptors. Prior to operation of the proposed project, the 24-hour ambient PM-10 concentrations in the area are calculated to be between 14 and 40 percent of the NAAQS, due solely to vehicular traffic on the paved roads included in the model. Following project startup, the ambient 24-hour PM-10 concentrations are calculated to be between 19 and 49 percent of the 24-hour NAAQS. Increases would be limited to the surrounding area in close proximity to the proposed Custom Coals No. 1 Plant; generally less than 4900 feet (1500 meters) from the center of the processing area. The increase in 24-hour PM-10 concentrations would essentially produce no change in the character of the ambient air quality, and would not be expected to be detrimental to air resources surrounding the proposed Custom Coals No. 1 Plant site.

Air quality impacts resulting from demolition of existing structures and construction of the plant would be minimal and limited in duration. Construction activities would take place at least 400 feet from the nearest residence. Standard control measures would be used to minimize impacts such as wetting dry soils and revegetating disturbed areas. Asbestos would be removed from all site structures in accordance with all applicable regulations prior to demolition activities (See Section 3.1.6).

3.1.2 Land Resources

Somerset County has an area of approximately 1,085 square miles or 694,400 acres. This area's geology consists of sedimentary rocks of the Pennsylvanian, Mississippian and Devonian ages. Geologic resources include Lower Freeport, Upper Kittanning and Lower Kittanning Seam coals which lie within 170 feet of the site surface, separated by 50 foot thick beds of sandstone and thin layers of claystone and mudstone (CCI EIV, July 1993, Revised). Based on the seismic intensity characteristics of the region, the proposed CCI

TABLE 7

EXISTING AND PROJECTED SECOND HIGH 24-HOUR PM-10 CONCENTRATIONS

Location ¹	Existing Conditions		Future Conditions With Custom Coals No. 1 Plant	
	Ambient Concentration ($\mu\text{g}/\text{m}^3$)	Percent of NAAQS ⁽²⁾	Ambient Concentration ($\mu\text{g}/\text{m}^3$)	Percent of NAAQS ⁽²⁾
Residence 1	59.4	39.6	72.7	48.5
Residence 2	45.5	30.3	51.6	34.4
Residence 3	23.0	15.3	36.8	24.5
Residence 4	21.4	14.3	29.0	19.3
Residence 5	21.1	14.1	28.0	18.7
Residence 6	21.0	14.0	30.8	20.5
Residence 7	20.9	13.9	29.3	19.5
Residence 8	27.1	18.1	30.9	20.3
Shade Church	21.6	14.4	29.2	19.5
Intersection SR 160 and Township Road 649 ⁽³⁾	42.9	28.6	51.2	34.1
1.5 miles South of Plant Adjacent to SR 160	34.9	23.3	40.9	27.3
Maximum off-site receptor	59.4 ⁽⁴⁾	39.6	72.7 ⁽⁴⁾	48.5

¹See Figure 9 for receptor locations.

²The primary National Ambient Air Quality Standard for PM-10 on a 24-hour basis is a second high value of $150 \mu\text{g}/\text{m}^3$.

³Receptor A.

⁴Same location as Residence 1.

Reference: DOE environmental contractor, October 1993.

plant would not include any special seismic design criteria (personal communication with CCI personnel, July 1993).

3.1.3 Water Resources

The proposed Custom Coals No. 1 Plant would use large quantities of water to produce Carefree and Self-Scrubbing Coals. Water management operations would be very similar to the system used by the previous Laurel Coal Preparation Plant. Figure 10 shows the site's proposed treatment system which would serve the following purposes: 1) provide chlorinated water for potable use and 2) collect and treat: stormwater, leachate from the coal refuse disposal facility, and coal refuse slurry from the proposed coal preparation plant containing coal fines; and return this treated water via Pond G to the proposed coal preparation plant to be used as process water. This proposed system would maximize the reuse of process water and would provide for environmentally sound discharges to receiving streams.

Potable water for the facility is currently supplied by an on-site deep well which feeds a 200,000-gallon water tank, which in turn utilizes gravity to supply water to the office/bathhouse, fire system, and an off-site local resident. It is estimated that a total of 4,600 gpd of potable water would be required for the proposed Custom Coals No. 1 Plant. Other residential drinking water in the area is supplied by private off-site wells. A new potable water treatment system, with chlorination, would be installed during construction activities. This proposed system would be designed in accordance with Somerset County Health Department and PADER requirements and sized appropriately to meet the estimated 4,600 gpd potable water demand. Until this system is constructed, other provisions would be made to supply potable water to workers associated with the proposed Custom Coals No. 1 Plant. Potable supplies would be withdrawn from the 200,000-gallon water tank and treated before use. This tank would also store water for fire protection purposes. Sanitary sewage from the facility would be directed to the Shade-Central City Sewage System.

Section 2.1.2.1 described how stormwater and coal refuse disposal facility leachate are currently treated on-site. The proposed Custom Coals No. 1 Plant would add water flows from an operating coal preparation plant to the existing system which would result in numerous changes. Bringing coal on-site for processing in the proposed coal preparation plant would require connecting Ponds D, E and F to the treatment system Surge Pond as

Reference: CCI EIV, July 1993 (Revised).

FA93031019V4

FIGURE 10. Proposed Treatment System

stormwater collected in these ponds would now contain coal fines. Preparation plant process water containing coal refuse slurry would be pumped to the upper portion of Pond K through existing underground pipelines and would subsequently be pumped to the Surge Pond. The proposed treatment system would be designed to neutralize, settle, and clarify coal refuse slurry from the proposed preparation plant and the water from Ponds D, E, and F using the same treatment as discussed in Section 2.1.2.1. Pond G would be connected to the system to serve as a water reservoir for the proposed coal preparation plant and would be supplied by treated water from the lower portion of Pond K. The proposed system changes would result in a closed loop circuit so that all water entering the system would be treated and recycled to the proposed preparation plant.

The proposed preparation plant would require 143-million gallons per year of process water and 10 million gallons per year of water for dust control purposes for a total estimated water requirement of 153-million gallons annually. Ninety-five percent (136,000-million gallons per year) of the total process water used annually would be recycled and the pond system would collect 72-million gallons a year of stormwater which would feed into the treatment system. Therefore, the site would have a water excess of 55-million gallons annually which would be discharged through outfalls permitted by the PADER Coal Refuse Disposal Permit (CRDP) (CCI EIV, July 1993, Revised). During periods of extremely low rainfall, when the treatment system could not adequately supply the proposed preparation plant; makeup water from the on-site deep well, without treatment, would be pumped to the proposed preparation plant via Pond G.

Stormwater from areas not currently flowing into the treatment system are directed into Ponds A-B, L, M, or N as discussed in Section 2.1.2.1 which would be discharged through outfalls permitted by the PADER Coal Mining Activity Permit (CMAP). This collection system would remain in operation and function in the same manner as part of this proposed Custom Coals No. 1 Plant.

3.1.3.1 Discharge Water Quality

All five outfalls (001, 002, 003, 004 and 005) at the existing Laurel Preparation Plant have PADER permits as noted in Section 2.1.2.1. The proposed Custom Coals No. 1 Plant

would apply for a renewal and/or extension to these permits as the same outfalls would be used. The proposed treatment system shown in Figure 10 would discharge to Miller Run (Outfall 002) and would be regulated by the PADER CRDP. The existing collection system shown in Figure 6 would remain in use unchanged for the proposed Custom Coals No. 1 Plant, would continue to discharge to Little Dark Shade Creek and Miller Run (Outfalls 001, 003, 004 and 005) and would be regulated by the PADER CMAP.

To determine the possible impact of surface water discharges from facility operation, discharge water quality data from the Laurel Coal Preparation Plant during its previous operation were reviewed for the December 1981, through December 1982, time period, and are presented in Table 8 along with current (1993) site discharge permit requirements. Future permit requirements are expected to be similar (personal communication with PADER). This table also presents recent discharge data from September 1992, through July 1993, although discharges only occurred during May and June of 1993 when sufficient stormwater had accumulated. Since the proposed preparation plant has not been operated since 1982, the eleven year old data are most representative of conditions expected during future operations. Also included in this table are EPA effluent guidelines (minimum requirements) for the Coal Mining Point Source Category (40 CFR 434), showing that PADER has placed more stringent requirements on this discharge than required by EPA.

Table 8 indicates that for the parameters monitored in the 1981-1982 time period, discharges were at a level which complies with 1993 PADER permit requirements. Water conservation measures employed as part of the treatment process resulted in a high degree of recycle, reuse and fresh water minimization. These measures achieved a "no discharge" condition for six of twelve months of the period shown in Table 8. Recent data for May and June of 1993 show slightly elevated values for aluminum and total dissolved solids. While aluminum discharges can be controlled with proper treatment, measures to treat total dissolved solids are very costly to implement. One option is to only discharge this water after sufficient rainfall has been collected to reduce the solids concentration. Based upon current and 1981-1982, discharge data, the discharge from Outfall 002 during the demonstration and commercial phases of this project should have no adverse impact on water quality.

TABLE 8

**OUTFALL 002 (POND K) DISCHARGE DATA
AND REGULATORY REQUIREMENTS**

	Concentration (milligrams per liter)					
Parameter	1981-1982 Long Term Average ¹	1992-1993 Long Term Average ²	Current 1993 Limits		Current EPA Nationwide Effluent Guidelines	
			CRDP			
			For Outfall 002		Average	Daily Maximum
pH ³	7.54	7.40	6.0-9.0	6.0-9.0	6.0-9.0	6.0-9.0
Total Suspended Solids	10.8	6.4	35.0	70.0	35	70
Iron	0.63	1.08	1.5	3.0	3.5	7.0
Manganese	0.26	0.21	1.0	2.0	2.0	4.0
Aluminum	NM ⁴	0.72	0.5	1.0	NR ⁵	NR
Total Dissolved Solids	NM	2,414	2,000	4,000	NR	NR
Osmotic Pressure ⁶	NM	25	50	100	NR	NR
Alkalinity ⁷	17.6	12.5	Alkalinity > Acidity		NR	NR

¹Six of twelve months had no discharge (January-June 1982).

²Ten of twelve months for the period August 1992-July 1993 had no discharge.

³Concentration in standard units.

⁴NM = Not Monitored.

⁵NR = No Requirement.

⁶Concentration in millimoles per kilogram.

⁷Any positive number shows alkalinity is greater than acidity.

References: A. 1981-1982 data from National Mines Corporation correspondence with DOE's environmental contractor, July 1993; 1993 data supplied by Triebel, Inc.

B. CRDP Permit No. 56743701 for the Laurel Coal Preparation Plant Site expires October 31, 1995.

C. EPA Effluent Guidelines for Coal Preparation Plants, 40 CFR 434.2.

Differences would exist between operations conducted in 1981 and those proposed for the demonstration project. As the Laurel Mine has been closed, acid mine drainage would not be present in the proposed Custom Coals No. 1 Plant water treatment circuit, thereby eliminating a significant acid and metals loading source. Due to increased coal cleaning efficiency, the demonstration project technology would result in additional sulfur and trace metals in the fine refuse slurry and coarse refuse compared to Laurel Coal Preparation Plant activities, even though the coal type processed would be similar to previous operations.

The water treatment system proposed for the Custom Coals No. 1 Plant is conceptually similar to treatment methods used successfully at a large number of preparation plants nationwide. Properly operated and maintained, the site treatment system would be capable of operating within the current and anticipated PADER discharge permit limits. The co-mingling of the alkaline preparation plant water depositing fine refuse in Pond K, with treated water containing excess lime from the lime mix tank and aeration basin; and the settling properties of Pond K, should be sufficient to settle solids and precipitate metals from the waste streams entering Pond K. Sulfate and metal discharges to Miller Run may increase slightly due to the proposed demonstration project when compared to existing conditions yet impacts are expected to be minimal.

In summary, the discharge from Outfall 002 (Pond K) would be controlled by a treatment system designed to comply with PADER permit requirements which are expected to be similar to those in effect today. CCI would ensure that the system would be operated in accordance with design requirements. Based on the successful use of this treatment technology at other sites throughout the United States, and the stringent requirements imposed by PADER, water quality impacts associated with Outfall 002 should be minimal.

Site stormwater that would contain coal fines or other sediments would be transferred by existing ditches (which would be lined with impermeable material as part of this project) or culverts to the existing collection system shown in Figure 6 consisting of Ponds A-B, L, M, or N (Outfalls 001, 003, 004 and 005). The CMAP and CRDP set discharge limits for these outfalls for the following parameters: iron, total suspended solids, manganese, aluminum, total dissolved solids, osmotic pressure and measure of

acidity/alkalinity (pH). Discharge data provided by Triebel, Inc. for Ponds A-B, L, M and N were also reviewed for the period of August 1992 through July 1993. During most of this period there was no discharge from these ponds, and no permit exceedances were reported. During the proposed Custom Coals No. 1 Plant operation, sodium carbonate would continue to be used to treat this water before discharge, and no adverse impacts would occur to receiving streams.

Discharge permit requirements which would be contained in the CRDP and CMAP would be based on EPA effluent limitation guidelines, PADER water quality standards, and in-stream standards for Little Dark Shade Creek and Miller Run which are classified as cold water fisheries. Therefore, permit compliance would ensure that water resources and aquatic life resources would be protected and adverse impacts would not occur.

3.1.3.2 Additional Environmental Protection Measures

Discussions between CCI and PADER have resulted in PADER expressing concern over existing ground water quality based on previous site activities and engineering controls in effect during previous operations. The potential need to line Pond K to protect ground water resources from the proposed Custom Coals No. 1 Plant operation would be resolved during permit negotiations between CCI and PADER (see Section 3.3.2).

Prior to the CCI plant commencing operation (as an expected requirement of the CMAP), CCI's environmental consultant will conduct a site-wide study on past and proposed practices, which will include hydrogeologic investigations. Recommendations of this study, with regard to water resources protection, would be implemented by CCI prior to the start of demonstration phase operations.

Some limited data, regarding ground water were submitted to PADER as part of the CMAP application. These monitoring data included samples from five upgradient springs, five upgradient domestic wells, two adjacent wells, and one downgradient well. These data indicate that previous mining and associated activity have had a minimal impact on the overall quality of subsurface waters in the area. The upgradient, adjacent, and downgradient subsurface waters are chemically very similar, and with proper seepage management (i.e. liners) and maintenance of alkalinity in the refuse area treatment ponds,

minimal impact would be expected from the proposed project. There are no water intakes within 10 miles of the proposed project area and no public water supplies within one mile of the proposed project area covered by the CMAP. No water supply source would be contaminated, diminished, or interrupted by the proposed preparation plant activities.

All ponds would be monitored to determine when sediments would require dredging to assure adequate pond capacity for ongoing operations. During such routine maintenance, the pond would be inspected to ensure structural integrity. Dredged sediments would either be disposed of in the refuse area after dewatering or would be placed in an approved landfill after characterization for disposal purposes.

Ponds receiving stormwater with coal fines would be lined with one foot of the most impermeable on-site or local borrow material, or a synthetic liner to prevent leachate from entering the ground water (CCI EIV, July 1993, Revised). PADER would determine which type of liner material is required during the permitting process. The run-of-mine coal stockpile area would be paved with asphalt. Runoff from this area would be collected and treated in the facility pond system. The integrity of the pond piping and pumping system, as well as refuse slurry pipelines, would be verified by CCI before the proposed demonstration project commences.

3.1.4 Ecological Resources

The region surrounding the proposed demonstration project contains rural wooded areas, land which has been heavily strip mined, and active coal mining sites. The land immediately surrounding the proposed Custom Coals No. 1 Plant site is best characterized as an upland meadow dominated by grasses and other herbaceous species. According to the U.S. Department of the Interior (DOI) Fish and Wildlife Service (letter dated March 23, 1993, from Charles Kulp, Appendix) except for occasional transient species, no federally listed or proposed threatened or endangered species under their jurisdiction are known to exist in the project area. This letter was received in response to a DOE letter requesting agency information per the Endangered Species Act as well as the Fish and Wildlife Coordination Act.

The PADER was contacted to verify the presence of natural resources of special concern in the proposed project area. In a letter from the PADER (letter dated October 4, 1993, from Kathy McKenna, Appendix) the review by PADER did not indicate any confirmed presence of resources of special concern within the proposed project area.

The Pennsylvania Game Commission was also contacted to verify the presence of candidate and State-listed species in Pennsylvania in the vicinity of the proposed project area. The Pennsylvania Game Commission considers the Bald Eagle, King Rail, Osprey, Indiana bat, Red-Bellied Turtle, Three-Spined Stickleback, and Eastern Tiger and Eastern Mud Salamanders to be a threatened species that may inhabit the area. The Eastern Wood Rat is considered to be a threatened species that may inhabit the area. The Pennsylvania Game Commission has reviewed this project and indicated that this project should not affect any endangered or threatened species (letter dated November 30, 1993, from Pennsylvania Game Commission to PADER, Appendix). No fish, amphibians, or reptiles in this area are listed by the Pennsylvania Fish Commission as being endangered or threatened (CCI EIV, July 1993, Revised).

Direct impacts to terrestrial animal species inhabiting the proposed Custom Coals No. 1 Plant site would be limited. Although there would be potential for some animal displacement due to demolition and dismantling of existing structures, grading, earthwork, and construction of new facilities including the 625 square feet wooded area which would be cleared for the raw coal trucking circuit; the lack of unique habitat as well as the site's previous use would minimize such impacts. Indirect construction impacts may be experienced by plants and animals near the site. Wildlife inhabiting the adjacent wooded and open areas may leave the area temporarily. Over time, most species would acclimate and return to areas adjacent to the proposed Custom Coals No. 1 Plant site.

Approximately five to ten acres of the proposed Custom Coals No. 1 Plant site would experience construction activity as a result of this project. New structures would be built, as well as a coal storage area and site roadways as discussed in Section 2.1.4. An existing tree line 550 feet long and 20 feet wide would be disturbed to place the on-site run-of-mine truck route. An approximately 15 locust and maple trees, 6-12 feet in height and less than 6 inches in diameter would be cleared. The proposed development would be similar to

previous uses at the site and would not result in the permanent loss of habitat. Revegetation of areas affected by construction would mitigate vegetative impacts.

3.1.5 Floodplains and Wetlands

Little Dark Shade Creek, located east of the proposed preparation plant, flows into Dark Shade Creek. Miller Run, located west of the coal refuse disposal facility, also flows into Dark Shade Creek. Neither the proposed preparation plant area, nor the coal refuse disposal facility lie within the 100-year or 500-year floodplains. A small portion of the property near the coal refuse disposal facility does lie within the floodplain of Miller Run along the northwest site boundary; however, the coal refuse disposal facility does not extend into the floodplain (CCI EIV, July 1993, Revised) (Figure 11).

The National Wetlands Inventory Maps produced by the U.S. Fish and Wildlife Service (USFWS) were used to identify the potential locations of wetlands. Ponds A-B, E, I, J, and L are indicated as wetlands and are classified as Palustrine, Open Water, Intermittently Exposed/Permanent. These man-made ponds are used to collect, and in some cases, treat the water collected. These ponds would experience impacts due to maintenance dewatering, dredging, and lining. Pond E would serve as the emergency thickener dump pond. Should a situation arise in which material in any of the thickeners could not be removed normally due to mechanical failure, material would be directed to Pond E. Upon settling of the material, water would be treated by the proposed collection and treatment system and recovered sediment would be disposed of at the coal refuse disposal facility. The ponds described above are not considered waters of the United States according to 33 CFR 328.3, and would not be subject to federal wetlands regulations.

A field reconnaissance survey of the proposed Custom Coals No. 1 Plant site indicated small, isolated wetland areas within the property boundaries (CCI EIV, July 1993, Revised). No activities within these wetland areas are planned. These isolated wetlands occupy less than one acre in area and would not be regulated under Section 404 of the Clean Water Act under the U.S. Army Corps of Engineers nationwide permitting process.

+++ = Railroad

----- = Areas inundated by 100 year flood

□ = SITE

REFERENCE: BASE MAP FROM THE FLOOD INSURANCE RATE MAP, SHADE TOWNSHIP, SOMERSET COUNTY, PENNSYLVANIA
PANEL NUMBERS 422054-0020-B, 422054-0025-B.

FA93031010V2

FIGURE 11 . Floodplain Map of the Proposed Custom Coals No. 1 Plant

3.1.6 Waste Management

In the spring of 1993, CCI's environmental consultant completed a Phase I Environmental Audit for the Laurel Coal Preparation Plant site with the objective of identifying areas of existing and potential environmental degradation resulting from past activities at the site. The Phase I Environmental Audit found that there were 6 on-site underground storage tanks that previously contained oil, diesel fuel, gasoline or surfactants; 24 transformers and capacitors containing polychlorinated biphenyls (PCB's); and various chemicals, additives, and hydraulic fluids present that were used during previous activities at the site.

A contractor for Triebel, Inc. has recently removed all on-site underground storage tanks and will provide a certificate stating that the removal process complied with the required PADER closure procedures prior to purchase of the site by CCI. No evidence of tank leakage was observed based on visual observation during removal operations. Another Triebel, Inc. contractor has removed unusable on-site transformers and capacitors and has retrofitted the remaining on-site transformers and capacitors. These operations were conducted in accordance with the Toxic Substances Control Act, Resource Conservation and Recovery Act, and Pennsylvania regulations. The remaining transformers and capacitors would be monitored by CCI during the proposed Custom Coals No. 1 Plant operation. If monitoring indicated the need for further retrofitting of transformers or capacitors, this would be performed in accordance with the above noted regulations.

Tile flooring and mastic samples were found during the audit to contain greater than 1 percent asbestos at several site locations and approximately 4000 sq. ft. of "transite" (asbestos - cement wallboard) was found in the existing Laurel Preparation Plant structure. Other asbestos containing materials (ACM) were also found during the audit. Prior to any renovations or demolition, all ACMs will be removed by a certified asbestos contractor. CCI will be responsible for ensuring that the required removal is completed and proper disposal is accomplished in accordance with all applicable federal, state and local regulations.

Demolition of structures associated with the existing Laurel Preparation Plant would occur during a four month period immediately prior to construction of the proposed Custom

Coals No. 1 Plant. All materials not identified as hazardous would be sold as scrap or surplus equipment, reused, or taken to a landfill approved to accept such wastes. Any hazardous wastes would be handled and disposed of by qualified contractors in accordance with federal, state and local regulations.

Non-hazardous solid wastes (other than coal cleaning refuse) generated as a normal part of operations, such as office waste, would be taken to the Resource Conservation Company landfill in Central City by a private contractor.

In summary, previous environmental contamination of the site is currently being studied and remediated. Additional work will be performed by CCI's environmental consultant to assess potential ground water contamination associated with the existing water management system and the coal refuse disposal facility. Any potential hazards which could impact construction workers or site personnel would be understood before construction of the proposed demonstration project so that mitigating measures, if required, could be taken. In the event that long term cleanup of the site is needed, such as ground water pumping and treatment, the proposed demonstration project could proceed simultaneously with this effort.

The proposed Custom Coals No. 1 Plant would produce approximately 50,397 tons of fine refuse and 116,608 tons of coarse refuse during the demonstration project. During commercial operation, it is estimated that 203,125 tons of fine refuse slurry and 421,875 tons of coarse refuse would be generated annually. All refuse would be disposed of at the existing on-site coal refuse disposal facility located on the northwestern portion of this site. It is currently estimated that approximately 8,237,000 cubic yards of coarse coal refuse and 2,116,900 cubic yards of fine refuse disposal space remains (CCI EIV, July 1993, Revised). The coal refuse disposal facility has the capacity to handle the refuse from the demonstration project and sixteen years of commercial operation. A new coal refuse disposal facility would then be needed to continue commercial operation.

The coal refuse disposal facility was formed by placing and compacting coal refuse from the previous Laurel Preparation Plant operations. Refuse slurried to this area was allowed to settle and combine with coarse refuse trucked from the previous Laurel Preparation Plant operations which resulted in an increase in the volume of the facility.

The proposed Custom Coal No. 1 Plant would operate in an identical manner. This coal refuse disposal facility was designed by a consulting engineering firm for the Laurel Mines Corporation in 1977. In April 1992, the Laurel Mines Corporation submitted to PADER a Certificate of Facility and Design, signed and sealed by a professional engineer, stating the Laurel Mine Coal Refuse Disposal Facility was constructed in accordance with designs and plans submitted to PADER, which formed the basis for previous issuance of the CRDP.

Environmental impacts associated with the coal refuse disposal facility (impacts to air and water resources) have been discussed previously, with permitting issues discussed in Section 3.3.2.

3.1.7 Transportation

To assess the impacts of coal deliveries to the proposed Custom Coals No. 1 Plant, a traffic study was performed by Wilbur Smith Associates in March 1993, and revised in October 1993, which evaluated existing traffic and roadway conditions within the study area. Figure 12 shows the study area and includes existing and projected traffic volumes which are discussed later in this section. The traffic study included the following:

- Existing traffic and roadway conditions including approach routes, speed limits, traffic control, daily traffic volumes, grades and sight distances on SR 160, SR 1021, Township Road 649 and U.S. Route 30.
- Determination of the proposed Custom Coals No. 1 Plant traffic generation and distribution on the existing roadways.
- Roadway and intersection capacity analysis for study intersections and associated roadways along U.S. Route 30 and SR 160 for existing and future traffic conditions.

U.S. Route 30, SR 160, and SR 1021 are two-lane rural highways. The 4-way intersection of U.S. Route 30 and SR 160 (Reels Corner) is controlled by a flashing beacon with stop control on SR 160, while the other intersections studied are controlled by stop signs on the roads intersecting SR 160. U.S. Route 30 is an arterial highway (capacity of 5,000 to 12,000 vehicles per day) serving through traffic and businesses along its route. The SR 160 is a minor arterial highway (capacity of 2,000 to 6,000 vehicles per day) functioning

FIGURE 12. Existing and Projected Peak Hour Traffic Volumes

as a collector for major through routes. There are 50 residences along SR 160, 14 between Reels Corner and the Shade Tipple access road and 36 located between the Shade Tipple access road and the proposed Custom Coals No. 1 Plant. One bus from the Shade-Central City School District passes the proposed plant site along SR 160 daily. Township Road 649 is a two-lane roadway (capacity of less than 3,000 vehicles per day) serving local traffic. There are no residences located along Township Road 649 within the proposed Custom Coals No. 1 Plant vicinity.

3.1.7.1 Demonstration Phase Assumptions

The demonstration phase would be limited in duration (16 months) and would process 500 tph for eight hours a day, five days per week. The demonstration phase would process test burn coal and local Kittanning Seam coal. Test burn run-of-mine coal would be delivered to the proposed Custom Coals No. 1 Plant by rail, cleaned and shipped off-site by rail. Local Kittanning Seam coal would be transported to the proposed Custom Coals No. 1 Plant by tri-axle heavy truck (HT), cleaned and shipped off-site by HT to Homer City Power Plant. Two-axle medium truck (MT) traffic would be negligible during operation of the proposed Custom Coals No. 1 Plant, consisting of roughly two MTs per day for fuel oil and magnetite, and five limestone/dolomite deliveries. Rail deliveries of run-of-mine test burn coals would require approximately 28 unit trains (100 cars each). Rail transport would be used for test burn coals since it would be mined and burned at distant locations from the proposed Custom Coals No. 1 Plant. A portable rail car unloading system which meets all PADER requirements for dust suppression would be employed during the demonstration phase. Run-of-mine coal would be unloaded into HT and delivered to the new run-of-mine coal unloading area. All HT would be covered to control particulate emissions.

3.1.7.2 Commercial Phase Assumptions

The commercial phase (20 year duration) would process 500 tph for 20 hours a day, six days per week, an average of 250 days per year. During this period, the use of locally mined coal would require HT deliveries as local mines do not have rail loading facilities. Approximately 40% of commercial phase cleaned coal is projected to leave the proposed

Custom Coals No. 1 Plant by rail (100 unit trains per year) as it would be sold to power plants having rail facilities. The MT traffic would be the same as during the demonstration phase except there would not be limestone/dolomite deliveries. Run-of-mine coal would be delivered to the proposed Custom Coals No. 1 Plant only during daylight hours, approximately 12 hours a day for five days per week. The HT volumes entering the proposed Custom Coals No. 1 Plant during the commercial phase are forecasted at 542 per day (a total of 1,084 HT round trips per day into and out of the proposed Custom Coals No. 1 Plant). Run-of-mine coal deliveries are forecasted at 417 HTs per day entering the proposed Custom Coals No. 1 Plant from SR 160 south of the proposed Custom Coals No. 1 Plant (a total of 834 HT round trips per day into and out of the proposed Custom Coals No. 1 Plant). Shipment of cleaned coal is forecasted at 125 HTs per day using SR 160 north of the proposed Custom Coals No. 1 Plant (a total of 250 HTs round trips per day into and out of the proposed Custom Coals No. 1 Plant). The run-of-mine coal and cleaned coal truck routes would not overlap. Cleaned coal would be trucked to the Homer City Power Plant which currently receives all coal supplies by HT.

An existing coal cleaning facility, the Shade Tipple Coal Preparation Plant is located east of SR 160, between Reels Corner and Township Road 621, and processes run-of-mine coal into cleaned coal. PBS Coal Company, Inc. (PBS) owns the Shade Tipple site and supplies it with coal from PBS mines in the area. The facility operates 24 hours per day, five days per week and can process up to 3.5 million tons of coal per year. The traffic analysis for existing conditions (October 1993) included HT traffic from the Shade Tipple access road which provides vehicle access off of SR 160 to this site (See Figure 13).

Future projections for the Shade Tipple site assumed a cessation of operations once full scale commercial operation of the Custom Coals No. 1 Plant commenced in 1996. The rationale for determining the Shade Tipple site would cease operations is based on environmental regulations and economics. The Shade Tipple site produces cleaned coal which will not meet the compliance requirements of the CAA. However, the proposed Custom Coals No. 1 Plant would produce a compliance coal. See Sections 3.1.9 and 3.1.15 for additional discussion.

FIGURE 13. Residences Exceeding FHWA Guidelines During A.M. Peak Hour in Year 2013 with Mitigation

3.1.7.3 Study Results

The traffic analysis focuses on the commercial phase which would result in the highest levels of HT and MT traffic. The study used the most reasonable upper limit assumption for HT traffic based upon closure of the Shade Tipple site. Traffic engineers use a "Level of Service" concept to categorize roadway conditions. Roadways are graded "A" through "F", where Level of Service A equates to total freedom of movement for motorists, while Level of Service F is a congested traffic flow condition with vehicle demand exceeding roadway capacity. Roadways are designed for a 20 year life span to operate at Level of Service C, balancing the economics of roadway construction with the need for an efficient transportation system. Level of Service C is defined as a stable traffic flow condition without excessive delays. The traffic engineering study analyzed the intersection and roadway segments shown in Figure 12. The following three roadway segments would change from an existing Level of Service "B" to "C" as a result of projected conditions in the year 2013: 1) U.S. Route 30 west of SR 160 during the A.M. peak hour (7 to 8 A.M. when maximum hourly volumes occur); 2) SR 160 between the Shade Tipple access road and the proposed Custom Coals No. 1 Plant during the A.M. and P.M. peak hours; and 3) SR 160 between the proposed Custom Coals No. 1 Plant and SR 1021 during the A.M. and P.M. peak hours. Roadway segments that change from "B" to "C" would cause drivers to experience less freedom of movement and some delays. The traffic study determined that Level of Service C or better would be present for all intersections and roadway segments during the peak hour for commercial phases of operation (through the year 2013). There would be no driveway access problems on the studied roadways.

Figure 12 shows existing and projected peak hour traffic volumes for roadway segments influenced by the proposed Custom Coals No. 1 Plant. An annual background traffic growth projection of 1.5 percent was assumed and includes increases to existing landfill traffic.

U.S. Route 30 and SR 160 south of the Shade Tipple access road would not experience an increase in HT traffic since the proposed Custom Coals No. 1 Plant would replace the HT volumes currently going to and from the Shade Tipple site. SR 160 between

the Shade Tipple access road and the proposed Custom Coals No. 1 Plant would experience a HT increase during the A.M. and P.M. peak hours from 22 to 97 HTs; during the remainder of the daylight hours HT volumes would average 65 vehicles per hour compared to an existing 18 vehicles per hour. The HT traffic north of the proposed Custom Coals No. 1 Plant would increase during the A.M. peak hour from 22 to 48 HTs; during the remainder of the daylight hours HT volumes would average 35 vehicles per hour compared to an existing 15 vehicles per hour. The MT and car traffic impacts from the proposed Custom Coals No. 1 Plant are expected to be minimal.

Wilbur Smith Associates made a number of recommendations so that safe traffic conditions would be present on area roadways. These include relocating the proposed Custom Coals No. 1 Plant truck exit driveway on SR 160, 70 feet north to improve sight distance and to form a perpendicular intersection; signing to show the truck exit driveway would be for exiting truck traffic only; placing truck crossing warning signs on SR 160; installing a flashing beacon at the intersection of SR 160 and Township Road 649; and construction of a deceleration lane on southbound SR 160 for right turns onto Township Road 649. The Pennsylvania Department of Transportation (PennDOT) has reviewed the Wilbur Smith Associates traffic study, and believes additional traffic safety measures may be necessary beyond those described above. PennDOT is considering the need for turning lanes, additional acceleration and deceleration lanes, and shoulder widening. CCI is currently discussing these additional recommendations with PennDOT.

During construction, it is estimated that 200 construction workers would be on-site resulting in increased commuter traffic. This increase in car volume on adjacent roadways would have minimal impacts, due to its limited duration (approximately one year) and the available capacity of the existing roadways. During construction, MT traffic including construction vehicles and supplies would arrive throughout the day, and would not raise off-peak hour traffic levels to levels greater than the A.M. peak hour. Therefore, the impact would be minimal.

3.1.7.4 Summary

The existing roadway system with proposed improvements can safely and adequately handle truck traffic proposed for this facility without adversely degrading traffic flow conditions. The HT traffic along U.S. Route 30 and along SR 160 north to the Shade Tipple access road would not change. The SR 160, between the Shade Tipple access road and the proposed Custom Coals No. 1 Plant would experience a large increase in the number of HTs, which would be noticeable by residents located along this roadway segment. The new conditions experienced by these residents would only occur during daylight hours, and would be very similar to those currently experienced by residents to the south of the Shade Tipple access road on SR 160 due to the current Shade Tipple operations. The projected traffic conditions are typical of those experienced on state highways throughout this and other regions where coal mining occurs.

3.1.8 Noise

The proposed Custom Coals No. 1 Plant would generate noise from a variety of activities including demolition of existing structures; construction and operation of the proposed Custom Coals No. 1 Plant; and transportation noise associated with coal movement on and off-site.

Truck traffic travelling to and from the proposed Custom Coals No. 1 Plant along SR 160 would be the major noise generator. A detailed noise analysis was performed by Wilbur Smith Associates in October 1993, to determine existing and projected noise levels at residences located along SR 160. Existing noise levels were monitored along SR 160 at six locations to quantify conditions during the A.M. traffic peak, P.M. traffic peak, afternoon off-peak, and nighttime (10:00 P.M. - 6:00 A.M.) time periods. Projected noise levels were calculated using traffic data and projections discussed in Section 3.1.7 for Custom Coals No. 1 Plant commercial operation in the year 2013.

The unit of measurement for evaluating traffic noise is known as the energy equivalent sound level (L_{eq}). The L_{eq} equals the constant sound level whose acoustic energy is equivalent to the acoustic energy of a fluctuating sound over some time interval. The L_{eq} provides a composite picture of noise conditions which are noisier when vehicles pass a

location and quieter during periods when there is no traffic. All noise levels presented in this section are L_{eq} values. The A.M. peak hour was determined to be the most critical time period with the highest noise levels.

The Federal Highway Administration (FHWA) has developed policy guidelines for highway construction projects to use in evaluating noise impacts. Although these guidelines are not directly applicable to this project, it is common practice to use this type of guidance when evaluating traffic noise generated by commercial development projects. The FHWA policy states that when traffic noise levels based on the busiest projected traffic hour approach or exceed 67 decibels read on the A-scale of a sound level meter (dBA) or experience a substantial increase (10-15 dBA) at the exterior of residential dwellings, then mitigation measures must be evaluated. When mitigation measures are judged reasonable and feasible, it is FHWA policy they should be implemented as part of the project improvements. PennDOT has almost identical policies and procedures as the FHWA.

3.1.8.1 Study Results

The noise analysis focuses on the commercial phase when the largest HT and MT traffic volumes would occur. The model used to project traffic noise was the STAMINA 2.0 computer program developed by the FHWA. Railroad operations were not included in the analysis because impacts would be similar or less than that experienced from passing trucks, and daily rail movements would be small compared to the number of HT traffic movements (see Section 3.1.7).

The 50 residences along SR 160 (see Section 3.1.7) would experience HT traffic associated with the proposed Custom Coals No. 1 Plant. Figure 13 shows residences along SR 160 which would approach or exceed FHWA noise guidelines as a result of HT traffic along SR 160. Figure 9 shows residences directly adjacent to the proposed Custom Coals No. 1 Plant which were investigated for noise impacts from on-site activities including HT and MT traffic.

The noise analysis modeled 50 residences located along SR 160 between Reels Corner and the proposed Custom Coals No. 1 Plant. Noise levels approach or exceed the

FHWA noise abatement criteria of 67 dBA at five residences under existing conditions during the A.M. peak hour.

During commercial operations projected for the year 2013, noise levels would approach or exceed FHWA criteria at numerous residences during the A.M. peak hour due to this proposed project's HT traffic. Maximum projected increases above existing conditions at residences would be between 5 and 5.5 dBA. Most of these residences are located along SR 160 between the existing Shade Tipple access road and the entrance for the proposed Custom Coals No. 1 Plant. An increase in 3 dBA is considered just noticeable while an increase of 5 dBA is perceived as clearly noticeable. A 10 dBA increase corresponds to a perceived doubling in loudness. Coal would not be transported to or from the proposed Custom Coals No. 1 Plant during nighttime hours, so there would be no change to these existing noise levels.

Because projected noise levels at numerous residences would exceed FHWA guidelines, mitigation measures were investigated. FHWA policy states both the social and economic aspects of mitigation measures should be considered, along with their effectiveness, in determining whether they are reasonable and feasible. Mitigation measures evaluated for this project included:

- Enforcing the 35 miles per hour (mph) posted speed limit along SR 160. Currently 85% of vehicles on SR 160 operate at speeds of 45 mph or greater. Reduced vehicle operating speeds would result in lower noise impacts.**
- Reducing the daily coal quantity processed by the proposed Custom Coals No. 1 Plant.**
- Constructing noise barriers (walls) along SR 160.**
- Re-routing exiting HT traffic from the proposed Custom Coals No. 1 Plant along Township Road 744 instead of using SR 160.**
- Adding Saturday deliveries of run-of-mine coal to the proposed Custom Coals No. 1 Plant to reduce the average daily peak HT traffic on SR 160.**
- Delivering run-of-mine coal to the proposed Custom Coals No. 1 Plant by rail and increasing the percentage of cleaned coal shipments off-site by rail.**

Enforcement of the 35 mph posted speed limit along SR 160 was determined to be the only feasible mitigation measure for this proposed Custom Coals No. 1 Plant. This abatement method would result in noise reductions of up to 2.5 dBA for year 2013 projections. Figure 13 shows projected noise levels for the 12 residences (A through L) which would exceed FHWA guidelines in the year 2013 when the 35 mph speed limit is enforced and also shows noise levels for these 12 residences without mitigation. The residences on SR 160 between U.S. Route 30 and the Shade Tipple access road would experience negligible increases in noise levels compared to existing conditions as HT volumes would not increase along this roadway segment. The HT traffic on SR 160 between the Shade Tipple access road and the proposed Custom Coals No. 1 Plant would increase over existing conditions (see Figure 12) yet noise level increases would be limited to 3.0 dBA for residences located along this roadway segment. Noise increases of less than 3 dBA would be barely perceptible and would not change the noise character of the area.

Two factors would ensure that the 35 mph vehicle speed abatement measure would be enforced. Changes outlined in Section 3.1.7 regarding traffic safety should inherently reduce vehicle speeds. Also, CCI, as part of its health and safety program, would contractually require all of its suppliers of run-of-mine coal to obey the posted speed limit.

Other mitigation measures would not be implemented for the following reasons. Minor reductions (10 to 20 percent) in the amount of coal processed by the proposed Custom Coals No. 1 Plant would only reduce noise levels by a minimal amount. Further processing reductions would harm the economic viability of the project. Noise barriers would be ineffective due to the need for driveway openings, would reduce visibility and would not be cost effective. Re-routing exiting HT traffic from the proposed Custom Coals No. 1 Plant along Township Road 744 would cause substantial noise impacts of approximately 18 dBA above existing conditions at residences along this road, as this township road currently carries minimal traffic. Saturday coal delivery would introduce weekend HT traffic to this area and was determined to be inappropriate. Run-of-mine coal delivery to the proposed Custom Coals No. 1 Plant by rail would not be practical because commercial phase coal would be mined from local mines (within 10 miles or less of the proposed Custom Coals No. 1 Plant) which do not have rail access. Trucking this coal to

a rail loading point would involve excessive costs. Shipping all cleaned coal off-site by rail would not reduce noise levels at those residences which would be predominantly impacted by the run-of-mine HT traffic.

The noise study conducted by Wilbur Smith Associates also analyzed other residences and the Shade Church which could be impacted by the project (see Figure 9). Noise generation from the proposed Custom Coals No. 1 is estimated at 70 dBA at 50 feet (personal communication with CCI, August 1993). Noise from the proposed Custom Coals No. 1 Plant as well as from the operations at the coal refuse disposal facility were determined to have minimal impacts on residences and the Shade Church due to the distances involved between noise generator and receptor.

Table 9 shows existing noise levels at residences and the Shade Church based on ambient noise monitoring and projected levels due to the proposed Custom Coals No. 1 Plant. Residences #1, #2 and #8 would be most affected by HT traffic on SR 160. The Shade Church would experience no perceptible change in L_{eq} levels. Residences #6 and #7 would be influenced by eight MT truck movements per hour, 20 hours per day on the refuse truck access road, but the L_{eq} increases between 2.9 and 5.1 dBA would not cause an adverse impact. These noise level increases associated with refuse road MT traffic would not raise the existing low background levels to a point where residents would be disturbed.

3.1.8.2 Summary

Changes in existing noise conditions at all residences would barely be perceptible due to truck traffic on SR 160 traveling at the 35 mph speed limit. Twelve residences along SR 160 would exceed FHWA noise abatement criteria with vehicles operating at 35 mph. There would be no increase in existing nighttime noise levels along SR 160. FHWA and PennDOT have implemented projects with similar projected noise levels and noise level increases and determined that impacts were permissible. Noise levels in the proposed Custom Coals No. 1 Plant area would not substantially change from existing conditions, and no major adverse impact is expected.

3.1.8.3 Construction/Health and Safety Impacts

Earth removal, hauling, grading, paving, demolition, and building construction would be the major noise generators during construction. Construction noise impacts would be minimal and limited in duration. Activities would occur during daylight hours at least 400 feet from the nearest residences. Construction vehicles travelling to and from the proposed Custom Coals No. 1 Plant site would add to noise levels at residences along SR 160, but would not exceed noise levels projected during commercial operations.

TABLE 9
COMPARISON OF EXISTING AND PROJECTED
NOISE LEVELS

Receptor	Existing Noise Level in dBA (L_{eq})	Year 2013 Commercial Phase: Projected Noise Level in dBA (L_{eq})
Residence #1	62.0	65.1
Residence #2	59.3	61.5
Residence #3	37.8	42.7
Residence #6	34.3	39.4
Residence #7	40.8	43.7
Residence #8	60.8	62.7
Shade Church	42.2	44.9

- Notes:
1. See Figure 9 for receptor locations.
 2. Noise level projections include on-site and off-site HT and MT traffic.
 3. L_{eq} levels are for the A.M. peak hour.
 4. Residences #4 and #5 were not modeled as conditions were projected to be similar to or quieter than Residence #6.

Reference: Wilbur Smith Associates, October 1993.

Most equipment in the proposed Custom Coals No. 1 Plant would operate below 85 dBA within three feet of the machinery and would have no impact on worker health and safety. In areas where equipment would exceed this noise level, sound enclosures would be installed or ear protection would be mandated for personnel working in these locations.

3.1.9 Socioeconomic Impacts

Somerset County, in 1990, had a population of 78,218, of which the gender distribution is 52 percent female and 48 percent male, and over 99.5 percent of the population is of Caucasian ancestry. The proposed Custom Coals No. 1 Plant site is in a rural area of Somerset County with a low population density and no significant concentrations of racial minority groups. By age category, 25 percent of the County residents are under 18 years of age, 58 percent are between 18 and 64 years of age, and 17 percent are older than 64 years of age. Based on these demographic distributions, exposure probabilities would not concentrate risks on any particular gender, age, or racial minority group.

The May 1992 unemployment rate was 9.5 percent compared to the May 1991 rate of 9.2 percent. This placed Somerset County significantly higher than state and national unemployment rates (7.6 percent and 7.2 percent, respectively). The average per capita income of County residents is \$10,422, and approximately 15 percent of County residents are considered to be living below poverty level.

Peak construction activities would occur during 1993 and 1994. The project would have a positive impact on local employment and the local economy. The construction phase is expected to require approximately 200 workers. This would create short-term employment for the local and regional labor force. With additional workers required during the construction phase, local retail establishments could expect increases in revenues.

During the demonstration phase, the Shade Tipple site and the proposed Custom Coals No. 1 Plant would both be operational, processing the same total quantity of coal as currently produced by the Shade Tipple site. In 1996, when the commercial phase of the proposed project would commence, the Shade Tipple site would cease operations (See Section 3.1.7). There would be no change in the amount of coal mined and cleaned in the

region as a result of the proposed Custom Coals No. 1 Plant. As only locally mined coals would be cleaned, jobs would be maintained for miners and mine related functions during the commercial operation of the facility. Current employees of the Shade Tipple site would likely be employed at the proposed Custom Coals No. 1 Plant. Commercial phase operations at the plant are expected to require a total of 41 full-time, local employees on a six day per week, three-shift basis. In essence, the proposed Custom Coals No. 1 Plant would replace the existing Shade Tipple site. This should result in minimal socioeconomic changes to the local community and would not place a burden on fire protection, schools, health care, or other services.

Contact with the EPA's Office of Environmental Equity failed to result in identification of any citizen calls to their Equity Hotline regarding concerns about equity issues in Somerset County communities.

In accordance with provisions that DOE would incorporate into the cooperative agreement document for this project, Custom Coals, Inc., would take all necessary affirmative steps to assure that small businesses, small-disadvantaged businesses, women-owned small businesses, and labor surplus area concerns are used when possible.

3.1.10 Cultural and Historic Resources

The Pennsylvania Historical and Museum Commission (PHMC) has concluded (letter dated May 6, 1993 and January 3, 1994 from Kurt Carr, Chief, Division of Archaeology and Protection, Appendix) that there is a high probability that prehistoric and historic archaeological resources are located in the project area. In their opinion, the activity at the proposed Custom Coals No. 1 Plant site would have no effect on such resources as all land to be utilized has previously been disturbed. The PHMC also concluded that the project would have no effect on historic structures. According to the PHMC there are no Native American entities in or near the proposed Custom Coals No. 1 Plant site. The nearest Native American tribal entity is the Seneca Nation of Indians located in Salamanca, New York, along the Pennsylvania/New York border. The proposed project would not impact Native American tribal or other religious practices or sites.

The Shade Church, an inactive church located at the intersection of T-744 and T-649 (See Figure 9), is not eligible for consideration as a historic structure due to extensive renovations that have been performed. The project would have no adverse impact on the graveyard adjacent to the church.

3.1.11 Energy and Material Resources

The material resources required for the 500 tph operation of the proposed Custom Coals No. 1 Plant include run-of-mine coal, magnetite, dolomite or limestone, water, electricity, and No. 2 fuel oil (used in the thermal dryer). The resource requirements for the proposed 31 week demonstration of this technology consist of 620,000 tons of coal; 1,800 tons of magnetite; and 11,200 tons of dolomite or limestone. No. 2 fuel oil requirements for the proposed Custom Coals No. 1 Plant vehicles and the thermal dryer are estimated at 500,000 gallons for 5100 hours of operation, annually. Electrical power requirements for the proposed Custom Coals No. 1 Plant are estimated at 10 megawatt (MW). Run-of-mine coal for the demonstration phase would be shipped from the Warwick Mine, Greene County, Pennsylvania (Sewickley Seam Coal for CPP); Amax-Wabash Mine, Wabash County, Illinois (Illinois No. 5 Seam Coal for WVGS); Harrison Mine, Belmont County, Ohio (Lower Freeport Seam Coal for the ACPP); and from PBS Coal mines in Somerset County, Pennsylvania (Upper Kittanning Seam coal for demonstration and commercial plant operation). During the demonstration project and commercial operation, magnetite for the coarse circuits would be purchased from PennMag, Inc., in Adrian, Pennsylvania, and the fine sized magnetite used in the finer circuits would be purchased from Pea Ridge Iron Ore Co. Inc., Sullivan, Missouri. The source for the limestone used in the Self-Scrubbing Coal process has not yet been determined. Pennsylvania Electric is the current supplier of electricity to the plant and would, if necessary, provide supplementary electric lines. No. 2 fuel oil would be stored on-site in above ground tanks to refuel the off-road refuse vehicles and to power the thermal dryer.

3.1.12 Occupational Health and Safety

Potential exposure of workers to hazards would be minimized by a combination of adherence to Occupational Safety and Health Administration (OSHA) standards, mandatory health and safety standards of the Mine Safety and Health Administration (MSHA), engineering controls, sound work practices and procedures, and personal protective equipment. Training programs would be conducted to ensure that workers are aware of potential hazards and are able to react properly to emergency situations.

CCI would minimize the inherent risks associated with construction and operation activities by enforcing all OSHA and CCI health and safety standards. During construction, CCI would comply with OSHA Construction Industry standards (29 CFR 1926) and MSHA standards for any modifications to refuse piles, impoundments, and mine sealing (30 CFR 1-199). A CCI representative responsible for monitoring health and safety compliance would be available at all times during construction.

Any chemicals used during operation of the proposed facility would be required to pass a health and safety review and be approved by CCI's certified industrial hygienist prior to use. Through CCI's Hazard Communication Training Program, all employees (who might be exposed to the chemicals) would receive training on how to handle the chemicals safely. Construction and demonstration project operating equipment would meet regulatory and industry safety standards.

Storage tanks and unloading facilities would be designed with protective systems including adequate containment to hold the full capacity of the tank or transport vehicle in case of a leak or a spill. All above ground storage tanks over 250 gallons would be registered with PADER, which would review the protective systems, and tanks would be inspected regularly by site personnel.

3.1.13 Pollution Prevention

Pollution prevention focuses on reducing the amount and/or toxicity of pollutants generated by an industrial process. It seeks to control pollutants at their source in contrast to using treatment methods which manage pollutants after they are formed. The Pollution Prevention Act of 1990 establishes a protection hierarchy of environmental management

techniques, and in 1992 EPA issued a draft Federal Sector Strategy which calls for federal agencies to lead the nation in implementing pollution prevention policies and practices.

The proposed project would incorporate several pollution prevention principles and techniques. These measures include: demonstration of an innovative method of advanced coal cleaning to reduce sulfur content of coals, thereby preventing sulfur dioxide generation upon coal combustion; demonstration of a technology that would reduce the sulfur content of fine sizes of coal and enable the recovery of this coal cleaning waste as a utility fuel rather than being incorporated into the refuse; and recycle of stormwater and preparation plant water for reuse as process makeup thus reducing the demand for fresh water.

3.1.14 Biodiversity

Biodiversity is gaining increased attention as an important aspect of environmental protection. This principle places value on the diversity of genes, species, and ecosystems; and holds that the loss of biological diversity is potentially harmful to our ecological and economic systems.

The construction and operation of the proposed Custom Coals No. 1 Plant would have negligible effects on biodiversity. Positive impacts of the project include reducing pollution associated with acid rain precursors due to coal combustion. Land resources needed for this project have already been disturbed, and few vegetated areas other than grassland would be disturbed. No endangered, threatened or special concern plant or animal species would be impacted; and aquatic ecological resources associated with the adjacent streams would be unaffected by the project.

With regard to global climate change and the associated biodiversity impacts, the proposed demonstration project would indirectly generate CO₂ emissions by its electrical power needs of 10 MW, as well as CO₂ associated with rail and HT traffic transport of coal. Impacts would be minimal and similar to other coal cleaning plants. Carefree Coal produced during the commercial phase of the project would generate similar CO₂ emissions upon combustion at coal-fired power plants.

3.1.15 Cumulative and Long Term Impacts

Because the proposed Custom Coals No. 1 Plant would continue to operate and produce Carefree Coal after the demonstration has been completed, the cumulative and long term environmental impacts of the proposed project were considered. Long term environmental impacts are the projection of environmental impacts over a longer period of time than the demonstration project. Cumulative impacts are the result of the incremental impact of the project when added to the impact of other past, present or future actions including industrial development. Cumulative impacts can result from individually minor, but collectively significant actions taking place over a period of time.

It is anticipated that there would be no adverse long term impacts resulting from this project. All waste discharges would be monitored in accordance with permit requirements. Periodic inspections would monitor pond liner integrity and underground piping systems to ensure that low pH water or other constituents do not permeate to the ground water. The coal refuse disposal facility may reach maximum capacity during the proposed commercial operation. A new coal refuse disposal facility would be sought. Oversight of facility operation by PADER through permitting and periodic inspections, in conjunction with engineering controls discussed in this report, would preclude long term adverse impacts from this project.

Somerset County Planning Commission and Shade Township officials were contacted in order to evaluate the cumulative impact of the proposed Custom Coals No. 1 Plant in conjunction with other actions (CCI EIV, July 1993, Revised; and DOE personal communications, October 1993). The Shade Township area of Somerset County contains several existing surface and underground coal mines, and a landfill has recently been completed in nearby Central City. No future development for this area of Somerset County is planned. The correlation between the proposed Custom Coals No. 1 Plant operations and the Shade Tipple site was discussed previously (See Sections 3.1.7 and 3.1.9). It is highly unlikely that the Shade Tipple site would reopen for coal cleaning or other industrial uses based upon the long period of inactivity at the Laurel Coal Preparation Plant site. The HT traffic travelling to the Central City landfill has been included in the traffic study for the proposed Custom Coals No. 1 Plant discussed in Section 3.1.7.

3.1.16 Findings

The purpose of an EA is to determine whether the proposed action could have a significant impact on the human environment, as well as provide information on alternatives to the proposed action. If an EA shows that the proposed action is likely to result in a significant impact, an environmental impact statement must be prepared. Otherwise, a "Finding Of No Significant Impact" is issued.

The potential impacts of the proposed action have been evaluated relative to the nine indicators of significance specified by the CEQ (40 CFR 1508.27). The results of this evaluation follow:

- **The degree to which the public health or safety would be affected:**
Public health and safety would not be affected by this project as there are no controversial technologies that would be implemented, the facility would be regulated by the State of Pennsylvania, and similar operations take place in a safe manner at coal cleaning plants throughout the country. Environmental impacts addressed in this EA are consistent with previous activities at the site.
- **The unique geographic characteristics of the site:**
There are no unique characteristics at this site that would experience impacts or modifications. The uses of this site for the proposed demonstration project are essentially the same as its previous uses.
- **The degree to which the effects on the environment are likely to be highly controversial:**
There have been news releases made by CCI to present the proposal to the public as well as public notices associated with CCI's CMAP and CRDP applications. Public concerns have focused on traffic safety. Coal cleaning plants and the associated traffic are an accepted land use at similar sites nationwide.

- **The degree to which the environmental effects are highly uncertain or involve unique or unknown risks:**
Technologies to be used at the proposed facility have been used previously at the site and at other sites nationwide. The finer cleaning processes proposed are not anticipated to impact the environment in a unique way.
- **The degree to which the proposed action establishes a precedent regarding future actions with significant effects:**
No precedent for future actions that would have significant effects is expected to be established as a result of the proposed demonstration project. Innovative aspects of this project include the advanced coal cleaning technique and the use of a cleaned coal combined with a sorbent. This technology is a variation of other flue gas cleaning techniques which use limestone to react with SO₂ in flue gas. Therefore, this environmental control technology is a variation of already existing processes.
- **Whether the action is related to other actions with individually insignificant but cumulatively significant impacts:**
There are no proposed activities in the region that, combined with the potential impacts of the proposed demonstration project, would be expected to result in significant cumulative impacts.
- **The degree to which the action may cause loss or destruction of significant scientific, cultural, or historic resources:**
There are no known archaeological, historic, cultural, or scientific resources that would be affected by the construction and operation of the proposed demonstration project. In compliance with the National Historic Preservation Act, consultation with the Pennsylvania Historic and Museum Commission, Bureau for Historic Preservation has been undertaken and completed. The results of this consultation indicate that the proposed project would not impact such resources.

- **The degree to which the action may adversely affect threatened or endangered species or their critical habitats:**
DOE correspondence with the DOI, Fish and Wildlife Service has indicated that construction and operation of the proposed demonstration project would not effect any Federally listed or proposed threatened or endangered species. Project activities would occur on lands which have been previously disturbed and little ecological habitat would be disturbed.
- **Whether the action would threaten violation of Federal, State, or local law or environmental regulations:**
Analysis of atmospheric emissions, wastewater discharges, potential solid wastes and other factors discussed in this EA indicates that neither construction nor operation of the proposed demonstration project would threaten to violate any Federal, State, or local law or regulation for protection of the environment.

3.2 THE NO-ACTION ALTERNATIVE

Under the No-Action Alternative, whereby DOE does not provide cost-shared funding support, it is likely the Custom Coals No. 1 Plant would not be constructed. Environmental conditions at the Laurel Coal Preparation site would remain the same, although clean-up activities associated with past practices would likely occur at a slower pace if this proposed demonstration project was canceled. Little remediation of the site has occurred since the existing facilities were shutdown in 1982. Positive impacts, such as local economic improvements associated with continued coal mining, would not occur without construction of the proposed Custom Coals No. 1 Plant.

In the unlikely event CCI proceeded with this project without DOE participation, the anticipated environmental impacts would be the same as described in this EA. Proceeding with the No-Action Alternative would not contribute to the objectives of the CCT Demonstration Program which is to make a number of advanced, more efficient,

economically feasible, and environmentally acceptable coal technologies available to the U.S. energy marketplace. Utilities would not have this option to meet CAA requirements.

3.3 REGULATORY COMPLIANCE

This section describes current permits in effect at this site and permit requirements for the proposed demonstration project. The construction and operation of the proposed Custom Coals No. 1 Plant would require the following regulatory approvals:

- Air Permit
- CRDP
- CMAP
- Registration of all tanks greater than 250 gallons
- Highway Occupancy Permit (HOP)
- Potable water supply approval

3.3.1 Air Permit Application

Under Part C of the CAA coal cleaning plants are subject to the PSD program, and the pertinent rules that have been codified and promulgated by EPA from the CAA are found in 40 CFR Parts 51 and 52. As discussed previously, PADER has determined that this facility would not be a major source subject to PSD review. A request for determination has been submitted to PADER Bureau of Air Quality Control as to whether an air permit would be required for demolition of existing site structures. CCI received a verbal response that a permit would not be required for demolition and is currently awaiting a written confirmation. An air permit application for construction and operation of the proposed Custom Coals No. 1 Plant has been submitted to PADER and a permit is expected to be issued.

3.3.2 Coal Refuse Disposal Permit

Currently, the coal refuse disposal facility is inoperative, although leachate discharge is monitored (Outfall 002) by the present owner as required by the existing CRDP No. 56743701 issued to National Mines Corporation, Lexington, Kentucky, which expires

October 31, 1995. This permit was based upon a Coal Refuse Disposal Plan prepared by D'Appolonia Consulting Engineers for National Mines Corporation in July 1977. This plan calls for a seven-stage coal refuse disposal facility to be constructed over a period of 17 years consisting of coarse refuse and fine refuse slurry. An application was submitted to PADER to request transfer of this permit to CCI from the present owner, and this transfer is expected to be approved early in 1994, after the purchase of the land by CCI.

Prior to and during the coal preparation plant construction, an environmental consultant for CCI would evaluate hydrologic conditions in the refuse area. The need for conducting additional site characterization activities would be evaluated. A modification to the CRDP would be prepared at that time. This modification would be required because the existing permit allows only refuse derived from coal from the on-site Laurel Mine to be disposed of at the coal refuse disposal facility. The modification application would evaluate the staging of the coal refuse disposal facility due to the change in fine and coarse refuse ratios, and the changes in coal type and processing techniques. A discussion of hydrologic conditions and recommendations to prevent the contamination of ground water, such as Pond K lining, would be included in the permit modification application. It is not anticipated that PADER would revise National Pollutant Discharge Elimination System (NPDES) sampling points, intervals, or discharge limits as set by the existing permit; yet sampling for additional parameters, such as metals may be required.

3.3.3 Coal Mining Activity Permit

Currently, the flooded underground mine and the inactive coal preparation plant are inoperative. The flooded underground mine would be sealed and would not be part of the proposed demonstration project. National Mines Corporation made application to PADER to renew and transfer the existing CMAP, which expired on September 23, 1991, to Triebel, Inc. PADER is currently reviewing this application. Pending the outcome of the PADER action, Triebel continues to treat the stormwater and monitor outfalls 001, 003, 004, and 005 as required by the existing CMAP No. 56841325 permit. CCI has submitted a CMAP application for the Custom Coals No. 1 Plant to PADER in August 1993 and permit issuance is expected in the 1993 calendar year. This application includes operating

information, erosion and sediment control plans, reclamation plans, demolition bonding, information relating to ground water and geology, and analysis of the two CMAP sampling points set by the existing permit. PADER has stated informally that aluminum may be added to the list of water discharge parameters to be monitored. The transfer from Triebel to CCI is expected to be approved early in 1994, after the purchase of the land by CCI. Since the flooded underground mine would be sealed a CMAP would not be expected to be required by PADER of National Mines Corporation. Notice of CCI's intent to acquire a CMAP (and the CRDP discussed in Section 3.3.3) was advertised in a local Somerset County newspaper and this Shade Township public meeting October 7, 1993.

3.3.4 Other Required Permits

Applications for local permits required for the construction of the facility (building permit, land development permit, etc.) would also be made. All storage tanks would be installed and registered in accordance with the PADER Storage Tank and Spill Prevention Act.

A HOP would be required from PennDOT for the clean coal loadout exit driveway and would be applied for prior to acquisition of the land from Triebel, Inc.

Use of the on-site well for potable drinking water would require either a permit from or a submission notice to the county health department or PADER's Division of Water Supplies.

4.0 ENVIRONMENTAL IMPACTS OF THE PROPOSED FEDERAL ACTION AT THE TEST BURN SITES

The proposed Custom Coals No. 1 Plant would produce Carefree Coal or Self-Scrubbing Coal. These coals would be fired in full-scale test burns at CPP in Springdale, Allegheny County, Pennsylvania; WVGS near Richmond, Wayne County, Indiana; and ACPP near Ashtabula, Ashtabula County, Ohio. Test burns at each of these coal-fired electric utilities would be of limited duration ranging from a three to five week period. Baseline testing at all units would be limited to one to three weeks since station operators are familiar with the current coals. Carefree Coal testing would be limited to three weeks since few additional operating variables would need to be optimized. Self-Scrubbing Coal tests would be extended to five weeks to permit station operations to be tuned to the new fuel. Due to the limited test burn activity at the coal-fired electric utility sites, potential environmental impacts would be limited. All of the utility sites are currently operating using conventionally cleaned coals.

The cleaned coals to be burned would be from the same or similar coal formations currently used at each of these facilities. The three utility sites would operate in an almost identical manner during the full-scale test burns compared to current operations. Test burn data at each of the sites would be collected in accordance with an Environmental Monitoring Plan written by CCI and approved by DOE at PETC which contains sampling methods, protocols, etc. Project activities, site descriptions and environmental impacts associated with each site are described in this section.

4.1 CHESWICK POWER PLANT

Proposed project activities and a site description of the CCP in Sprindale, Allegheny County, Pennsylvania are presented in the following section.

4.1.1 Project Activities and Site Description

The CPP has one tangentially fired operational unit manufactured by Combustion Engineering which has a design capacity of 570 MW. The test burn at CPP would consist

of a one week burn of baseline (existing) coal and a three week burn of Carefree Coal, made from Sewickley Seam coal. During each of these two burn periods, testing would be conducted to assess impacts on boiler performance and flue gas emissions.

The CPP is located in Allegheny County, Pennsylvania, between Springdale and Cheswick, 15 miles northeast of Pittsburgh. Figure 14 shows its regional location with a site plan provided as Figure 15.

The CPP is accessible by barge and truck. The Allegheny River provides the southern property boundary for the facility allowing for barge unloading. From SR 28, trucks can reach the site using Business Route 28.

Cooling and service water for the facility is provided by the Allegheny River, and is chlorinated prior to use by an on-site water treatment plant. Drinking water is provided by on-site wells.

A 2.4 million gallon sedimentation pond receives rainwater runoff from the coal pile, allowing suspended coal dust and other particles to settle. Two smaller ponds, 450,000 gallons each, handle a low volume of wastewater from the plant. The ash disposal system employed includes the mixing of ash with water to form a slurry which is then pumped into the abandoned Harwick mine. This mine is also owned by Duquesne Light Company and is located near the CPP. The ash slurry in the abandoned mine is dewatered at the Monarch dewatering plant located five miles north of the power plant. The CPP also draws water from and discharges into the Allegheny River. The facility has an approved PADER NPDES permit.

4.1.2 Environmental Impacts

The existing environment and environmental impacts associated with the test burns of cleaned coal at the CCP site are presented in the following sections.

4.1.2.1 Atmospheric Resources

The area of western central Pennsylvania, in which the CPP proposed demonstration site is located, provides a climate of mild summers (average temperature 69°F) and moderately cold winters (average temperature 39°F). Wind in the region is predominately

-NOT TO SCALE-

Reference: CCI EIV, July 1993 (Revised).

FA 83031002

FIGURE 14. Cheswick Power Plant Site

FIGURE 15. Cheswick Power Plant Plot Plan

from the south-southwest with speeds averaging 9.1 mph. The average annual precipitation for this area is 36.3 in. (CCI EIV, July 1993, Revised).

Allegheny County is in the Southwest Pennsylvania Intrastate Air Quality Control Region (40 CFR 81.339). The CPP is located in Springdale, and the area of Allegheny County within a two mile radius of the Springdale monitor is better than national standards for TSP. The Cheswick area of Allegheny County is better than national standards for SO₂, and is better than national standards or cannot be classified for NO₂, PM-10 and CO. Allegheny County does not meet primary standards for O₃. The CPP is currently in compliance with state and federal air quality requirements and operates continuous on-site emissions monitoring for SO₂ and opacity. Table 10 shows ambient air quality data for the area and compares this data to NAAQS.

CPP currently emits approximately 40,000 tpy of SO₂ and 10,000 tpy of NO_x. To increase the efficiency of the ESP at the plant, a sulfur trioxide (SO₃) injection system was previously installed. The SO₃ bonds to the surface of fly ash, providing the fly ash with a low electrical resistivity, allowing increased capture by the charge induced by the ESP.

In order to predict the impacts which would occur due to the change in coal quality during the proposed demonstration phase, the Electric Power Research Institute's (EPRI) Coal Quality Impact Model (CQIM) was used. This computer model is an established method for estimating coal combustion emissions. CQIM predicted emission rates for CO₂, SO₂, NO_x, and ash in the Sewickley Seam Carefree Coal. Test burn data is presented in Table 11, and represent estimates which would be verified during the test burn period. Fly ash properties influencing ESP efficiency would be one of many parameters quantified during the test burn. The emission rate of SO₂ was modeled as being reduced from 2.46 pounds per million British thermal units (lb/MMBtu) to 1.14 lb/MMBtu after coal cleaning at the proposed Custom Coals No. 1 Plant.

The test burning of Carefree Coal during the proposed demonstration phase would not be of sufficient duration to produce long-term impacts. SO₂ emissions from the CPP during the proposed demonstration phase are expected to decrease. The Cheswick facility is currently permitted to emit SO₂ at a rate of 2.8 lb/MMBtu. The demonstration would

TABLE 10
CHESWICK POWER PLANT SITE
1990-1993 AMBIENT AIR QUALITY MONITORING DATA¹

Pollutant	Averaging Period	NAAQS	Maximum Ambient Concentration ³
CO	8-hour	10	4.1
	1-hour	40	10.4
Pb	Quarterly	1.5	0.05
NO ₂	Annual	100	38
O ₃	1-hour	235	206
PM-10	Annual	50	24
	24-hour	150	57
TSP	Annual	No Standard	49
	24-hour	No Standard	156
SO ₂	Annual	80	24
	24-hour	365	99
	3-hour	1300 ²	No Data

¹All values are in $\mu\text{g}/\text{m}^3$ except CO which are in mg/m^3 .

²Secondary standard

³Pb, SO₂, and TSP data are from monitors in Braddock located approximately 10 miles south of the site. CO and NO₂ data are from a monitor in Monroeville located 8 miles south of the site. O₃ data is from the Harrison monitor located 7 miles northeast of the site. PM-10 data is from the Springdale monitor located approximately 1 mile east of the site. Data are presented for the most recent year reported.

Reference: PADER Bureau of Air Quality Control, 1993.

show how SO₂ emissions could be reduced to 1.2 lb/MMBtu or lower with the continued use of locally available Sewickley Coal. There is no anticipated change in emissions of NO_x or particulates during the demonstration. Likewise, emissions of CO₂ (a greenhouse gas) would decrease during the proposed demonstration phase because of higher heat content of the fuel would require less fuel to be burned. Test burn data are summarized in Table 11, and would have minimal short term impacts.

TABLE 11
CHESWICK POWER PLANT TEST BURN DATA¹

Type of Coal	Current	Carefree
Unit Net MW	570	570
Total Generation During Demonstration Project (MW)	287,280	287,280
Coal BTU Content (BTU/lb)	12,275	12,304
Total Coal Consumed (Tons)	108,523	107,952
Fuel Sulfur %	1.51	0.7
SO ₂ Formation (lbs of SO ₂ /MMBTU)	2.46	1.14
Total SO ₂ Produced (Tons)	3,277	1,511
NO _x Formation (lbs of NO _x /MMBTU)	0.45	0.45
Total NO _x Produced (Tons)	599	598
CO ₂ Formation (lbs of CO ₂ /MMBTU)	205	202
Total CO ₂ Produced (Tons)	273,289	268,131
Fuel Ash %	11.52	11.18
Total Ash (Tons)	12,502	12,069
Total Fly Ash (Tons)	10,001	9,655
Total Bottom Ash (Tons)	2,500	2,414
Total Fly Ash Emitted (Tons) ²	133	133

¹Projections have been equalized for three weeks duration, even though the baseline testing duration is one week.

²Total fly ash emitted is limited by permit and can be controlled by adjusting the ESP.

Reference: CCI EIV, July 1993 (Revised).

4.1.2.2 Land Resources

A cemetery lies within the CPP site and older residential neighborhoods border on the west, north and east. The National Wetlands Inventory Map produced by the DOI, Fish and Wildlife Service shows several wetlands in the vicinity of the power plant and a wetlands corridor running along the west property line. The wetland corridor is classified as Riverine, Upper Perennial, Open Water, Intermittently Exposed/Permanent.

The barge unloading area is the only part of this facility located within the 100-year floodplain. Cleaned coal would be delivered directly to the site by truck, therefore this area would be unaffected by the demonstration. No impacts to the floodplain or adjacent wetlands would occur since no construction activities are scheduled for the proposed demonstration project.

Land required for the storage of coals associated with this project is available by modification of the existing coal stockpile yard. The burning of Carefree Coal would produce less bottom and fly ash compared to the current fuel burned. The total ash disposal requirements would be reduced by approximately 450 tons during the proposed demonstration phase.

4.1.2.3 Water Resources

The CPP is bordered on the south by the Allegheny River. The Allegheny River originates from the Allegheny Reservoir located in northwest Pennsylvania and flows south and west through Pennsylvania passing the site. The river continues south and west until it joins the Monongahela River in Pittsburgh to form the Ohio River.

The CPP is able to draw water from and discharge into the Allegheny River, which is classified as suitable for drinking water and recreational purposes. Water used by the CPP is pumped from the Allegheny River and supplemented by a deep well located on site. Eleven outfalls are authorized to discharge wastewater under the existing NPDES permit. No adverse change in the chemical composition or volume of the NPDES discharges is expected due to the burning of Carefree Coal.

4.1.2.4 Ecological Resources

The region surrounding CPP is mostly urban and woodland areas. The wooded lands in the region are classified as mixed eastern hardwood. According to the DOI, Fish and Wildlife Service, (letter dated August 2, 1993, from Charles Kulp, Appendix) except for transient species, no federally listed or proposed threatened or endangered species under their jurisdiction are known to exist in the project area. This letter was in response to a

AIIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910

301/587-8202

Centimeter

Inches

MANUFACTURED TO AIIM STANDARDS
BY APPLIED IMAGE, INC.

2 of 2

DOE letter requesting agency information per the Endangered Species Act as well as the Fish and Wildlife Coordination Act.

No construction activities are associated with the proposed demonstration project test burns being performed at the CPP, and therefore, no ecological impacts are anticipated.

4.1.2.5 Transportation Impacts

The Carefree Coal to be utilized for test burns would be brought to the CPP by truck from a rail facility located close to the CCP. Trucks would reach the CPP using Business Route 28 from SR 28. The CPP currently receives coal by truck and barge. Current coal deliveries at the site are estimated at 85 trucks daily. As trucks carrying Carefree Coal would displace current truck deliveries, and as all Carefree Coal would be stockpiled before the test burn commences, the power plant projects 100 Carefree Coal deliveries would be needed daily. This truck volume would be similar to existing conditions and minimal impacts are expected.

4.1.2.6 Socioeconomic Impacts/Cultural Resources

The CPP is located in the southwest corner of Springdale in Allegheny County, Pennsylvania. Approximately, 1,336,449 people reside in the county (Southwestern Pennsylvania Regional Planning Council, 1991). The May 1992 unemployment rate in Allegheny County was 6.5 percent compared with the August 1990 rate of 3.4 percent. According to the PHMC, there are no Native American entities in or near the plant site. The nearest Native American tribal entity is the Seneca Nation of Indians located in Salamanca, New York along the Pennsylvania/New York border.

The PHMC has concluded (letter dated July 27, 1993 from Kurt Carr, PHMC, Appendix) that the proposed demonstration project would have no effect on archaeological or historical resources in the vicinity of the CPP. No socioeconomic/cultural resource impacts are expected.

4.1.2.7 Energy and Material Resources

Unit 1 of the CPP currently burns coal from the Pittsburgh, Sewickley, and Kittanning seams. This coal is obtained from the Warwick Mine Coal Cleaning Facility, Greensboro, Pennsylvania, which utilizes conventional coal cleaning methods. Although the CPP does currently use a "cleaned" coal product, this coal does not comply with CAA emission standards.

Approximately 108,000 tons of Sewickley Seam Carefree Coal would be test burned at the CPP during the three week demonstration phase. The test burning of these coals is not expected to impact the consumption of coal, fuel, oil or natural gas at the CPP.

4.1.3 Regulatory Compliance

The test burning of Carefree Coal at the CPP would not require modifications to the plant's air emissions permit due to the limited duration of the test burn. No modifications are anticipated to the existing solid waste disposal permits or NPDES permits. PADER and the Allegheny County Health Department would be notified of the proposed demonstration project by means of a Letter of Intent.

4.2 WHITEWATER VALLEY GENERATING STATION

Proposed project activities and a site description of the WVGS near Richmond, Wayne County, Indiana are presented in the following section.

4.2.1 Project Activities and Site Description

WVGS operates two boiler-turbine units with a combined rated capacity of 93 MW. Unit two, which has a continuous capacity rating of 60 MW and is a tangentially fired unit manufactured by Combustion Engineering, would be utilized for the proposed demonstration project. The proposed demonstration project at WVGS would consist of a three week burn of baseline (existing) coal and a five week burn of Self-Scrubbing Coal, made from Illinois #5 Seam coal. During each of these two burn periods, testing would be conducted to assess impacts on boiler performance and flue gas emissions.

The WVGS is located in Wayne County, Indiana, near the southern boundary of the City of Richmond. Wayne County is located in the east central part of the state and has the Indiana - Ohio state line as its eastern border. Figure 16 shows its regional location with a site plan provided as Figure 17.

The power plant is accessible by rail and truck. From Interstate Route 70 trucks can reach the site using State Route 27. Water needs at the plant are met by pumping water from the East Fork Whitewater River, which flows through the City of Richmond and within one mile of the generating station, or through Indiana American Water, a privately owned water company.

Bottom ash is sluiced to dewatering bins. Fly ash is collected in storage silos, emptied into trucks, and hauled to an approved off-site landfill with the bottom ash.

Approximately 1.8 million gallons of river water are pumped to the generating station each day for use as cooling water, or as sealer for the boilers. Two pumps deliver the water from the East Fork Whitewater River through a common header. Prior to use, the water may undergo clarification or chemical stabilization (pH adjustment) at the on-site water treatment facility. Cooling water is stored in a three million gallon holding tank located 200 yards southwest of the boiler building. Circulation pumps cycle the water from the holding tank to condensers, where the water is used to cool steam from the boiler. The water then moves to cooling towers and back to the holding tank, completing the cycle. Water used for boiler sealing and cooling tower blowdown does not recirculate, but moves to on-site sedimentation ponds and into an on-site city storm sewer. The facility has an approved NPDES permit.

4.2.2 Environmental Impacts

The existing environment and environmental impacts associated with the test burns of cleaned coal at the WVGS site are presented in the following sections.

Reference: CCI EIV, July 1993 (Revised).

FA93031007

FIGURE 16. Whitewater Valley Generating Station Site

FIGURE 17. Whitewater Valley Generating Station Plot Plan

4.2.2.1 Atmospheric Resources

The area of east central Indiana, in which the proposed WVGS proposed demonstration site is located, provides a typical midwestern climate with warm summers (average temperature 70°F) and fairly cold winters (average temperature 31°F). Wind in the region is predominately from the south-southwest with speeds ranging on average from 10-20 knots. The average annual precipitation in Richmond, Indiana is 38.8 inches.

The air quality in the Richmond area is generally good. Wayne County is in the East Central Indiana Intrastate Air Quality Control Region (40 CFR 81.315). Air quality control and permitting for the county falls under the jurisdiction of the Indiana Department of Environmental Management (IDEM) Air Pollution Control Board. The area surrounding the WVGS is better than national standards for TSP and SO₂. Wayne County cannot be classified or is better than national standards for PM-10, O₃, CO, and NO₂. Table 12 shows ambient air quality data for this area and compares this data to the NAAQS.

Currently, WVGS is operating above its particulate emission permit limits. IDEM is in the process of preparing a formal rule change for WVGS's Units 1 and 2, which would increase the allowable amount of particulate emissions. On October 5, 1993, a variance was granted which allows WVGS to exceed the allowable amount of particulate emissions until the final rule is adopted. A decision on whether to grant WVGS a variance was deferred until review of modeling data prepared by WVGS, demonstrated that NAAQS would not be threatened in Wayne County if limits proposed by WVGS were adopted. It is anticipated that the formal rule change would be in place prior to the start of the proposed demonstration project test burn (personal communication with IDEM). (See Section 4.2.3).

Emissions from the burning of Self-Scrubbing Coal during the five week demonstration phase are shown in Table 13 and were estimated by CCI based upon their knowledge of the coal cleaning technology to be employed (CCI EIV, July 1993, Revised). Based on these calculations, no increase in NO_x emissions was assumed and a substantial reduction in total SO₂ emissions was predicted. These estimates would be verified during the test burn period. The information collected during the five week demonstration burn would be compared to a three week baseline burn of coals commonly used by WVGS.

TABLE 12
WHITEWATER VALLEY GENERATING STATION SITE
1989-1992 AMBIENT AIR QUALITY MONITORING DATA¹

Pollutant	Averaging Period	NAAQS	Maximum Ambient Concentration³
CO	8-hour	10	No Data
	1-hour	40	No Data
Pb	Quarterly	1.5	0.35
NO ₂	Annual	100	30
O ₃	1-hour	235	186
PM-10	Annual	50	26
	24-hour	150	34
TSP	Annual	No Standard	No Data
	24-hour	No Standard	No Data
SO ₂	Annual	80	77
	24-hour	365	195
	3-hour	1300 ²	321

¹All values are in $\mu\text{g}/\text{m}^3$ except CO which are in mg/m^3 .

²Secondary standard

³There is no readily available CO data. Pb, NO₂ and SO₂ data are from monitors in Wayne County located less than 30 miles from the site. O₃ and PM-10 data are from a Madison County monitor located 45 miles from the site. Data are presented for the most recent year reported.

Reference: Aerometric Information Retrieval System, EPA, 1993.

The proposed demonstration project test burn is not of sufficient duration to have long-term air quality impacts. Emissions of SO₂ would decrease during the demonstration resulting in a slight positive impact. Particulate emissions would be expected to meet the state regulations as provided in the proposed new rule change currently proposed by IDEM. NO_x and fly ash emissions would be comparable to existing conditions during the proposed demonstration project. Emissions of CO₂ (a greenhouse gas) would remain the same with

no effect on global warming considerations. Test burn data are summarized in Table 13, and would have minimal short term impacts.

4.2.2.2 Land Resources

The area of the WVGS is a nearly flat to gently rolling glacial plain, which is virtually featureless throughout much of the area. The National Wetlands Inventory Map produced by the DOI, Fish and Wildlife Service shows several wetlands in the vicinity of the WVGS. Wetlands on the power plant property are associated with the ash and sediment ponds and are classified Palustrine, Unconsolidated Bottom, Semipermanently Flooded, Excavated; and Palustrine, Unconsolidated Bottom, Intermittently Exposed, Excavated. These waste treatment ponds are not considered waters of the United States and are not subject to federal wetlands regulations.

The entire WVGS facility lies above the probable maximum flood level for that area. No impacts to the floodplain would occur since no construction activities are scheduled for the proposed demonstration project test burn. The Self-Scrubbing Coal burned would decrease the amount of solid waste requiring disposal during the proposed demonstration phase.

Solid waste would be disposed of in a licensed disposal facility according to IDEM regulations using the same method as under existing conditions. It is anticipated that the currently utilized waste disposal site in Cincinnati, Ohio, would be used to dispose of demonstration ash. Land required for the storage of coals associated with this project can be readily made available by modification of the existing coal stockpile yard.

4.2.2.3 Water Resources

The WVGS is located approximately 3/4 of a mile east of the East Fork Whitewater River. The East Fork Whitewater River originates just north of New Paris, Ohio, and flows west until it reaches Richmond, Indiana, where it turns south and passes near the power plant.

TABLE 13
WHITEWATER VALLEY GENERATING STATION TEST BURN DATA¹

Type of Coal	Current	Self-Scrubbing
Unit Net MW	61	61
Total Generation During Demonstration Project (MW)	51,240	51,240
Coal BTU Content (BTU/lb)	11,080	11,608
Total Coal Consumed (Tons)	26,543	25,216
Fuel Sulfur %	2.7	1.28
SO ₂ Formation (lbs of SO ₂ /MMBTU)	4.87	1.2
Total SO ₂ Produced (Tons)	1,433	351
NO _x Formation (lbs of NO _x /MMBTU)	0.65	0.65
Total NO _x Produced (Tons)	191	190
CO ₂ Formation (lbs of CO ₂ /MMBTU)	211	210
Total CO ₂ Produced (Tons)	62,063	61,439
Fuel Ash %	12	11.16
Total Ash (Tons) ²	3,185	2,819
Total Fly Ash (Tons)	2,548	2,255
Total Bottom Ash (Tons)	637	564
Total Fly Ash Emitted (Tons) ³	29	29

¹Projections have been equalized for five weeks duration, even though the baseline testing duration is three weeks.

²The ash values for Self-Scrubbing Coal include the weight of calcium sulfate (CaSO₄) produced during combustion.

³Total fly ash emitted is limited by permit and can be controlled by adjusting the ESP.

Reference: CCI EIV, July 1993 (Revised).

Water used at the WVGS is supplied from the East Fork Whitewater River and Indiana American Water. There are no wells operating on the WVGS property.

Approximately 150,000 gallons of water enter the sedimentation ponds each day. During cooling tower blowdown events, the flowrate rises to about 320,000 gallons per day. The ponds have a current estimated retention time of five days.

Bottom ash constitutes 20 percent of ash generated, and is landfilled off-site. Fly ash is also landfilled off-site. Water for sluicing bottom ash on-site to the truck loading system contains small amounts of suspended ash and is discharged to a series of on-site ash ponds for clarification. There are four ponds connected by french drains and overflow pipes. Total estimated storage capacity of the ponds is 1.6 million gallons. The current wet ash transport system requires approximately 540,000 gallons of water per day and this volume eventually enters the ash pond network. Less than 5 percent of the ash moved by the system (less than six tons per day) is unintentionally carried with the water flow into the ash ponds. The ash ponds have an estimated retention time of three days. If needed, the sedimentation ponds can be used to create additional ash pond volume.

Ash and sediment pond overflows merge and enter a city storm sewer on the WVGS generating station property. Effluent characteristics for this flow are controlled by a NPDES permit. It is not anticipated that there would be any change in the volume or effluent quality of the discharge from the ash pond due to the change in fuel supply. Negligible quantities of sulfate would be solubilized from CaSO_4 which forms part of the ash when Self-Scrubbing Coal is burned. Landfill disposal of small quantities of CaSO_4 mixed with the bottom and fly ash would also have minimal impacts. Therefore, no water quality impact is anticipated from this project.

4.2.2.4 Ecological Resources

The region surrounding WVGS is mostly urban and woodland areas, with some farmland. The wooded lands in the region are classified as temperate deciduous forest. IDEM's Division of Nature Preserves has indicated that several species of wildlife are listed as endangered or threatened, federally or on a state level, for the Richmond Quadrangle, but only the Indiana bat range lies within the project area. According to the DOI, Fish and Wildlife Service, (letter dated January 21, 1993, from David Hudak, Appendix) the proposed project is not likely to affect the federally-endangered Indian bat, which is the only federally

listed species whose range includes the proposed demonstration site. This letter was in response to a DOE letter requesting agency information per the Endangered Species Act as well as the Fish and Wildlife Coordination Act. No plant life is considered endangered for the quadrangle, but softleaf arrow-wood and barren strawberry are designated as threatened by the state.

No construction activities are associated with the proposed demonstration project test burns being performed at the WVGS and no ecological impacts are anticipated.

4.2.2.5 Transportation Impacts

The Self-Scrubbing Coal to be utilized for test burns would be brought to the WVGS by rail. The WVGS currently receives coal by truck, and Self-Scrubbing Coal deliveries would displace existing truck deliveries. As ash generation would decrease, landfill truck traffic would be similar to existing conditions and no impacts are expected.

4.2.2.6 Socioeconomic Impacts/Cultural Resources

The WVGS is located just inside the southern limit of the City of Richmond in Wayne County. In May 1992 the unemployment rate for Wayne County was 11.1 percent, significantly higher than state and national averages. The proposed demonstration project is not anticipated to have an effect on the area economy and no construction is required. The Ball State Archeological Resource Management Service reviewed their records and determined that there are no Native American entities in the plant site area. The nearest ancestral Native American area is the Miami Tribe located approximately 25 to 30 miles away near New Castle and Muncie, Indiana.

The Indiana Department of Natural Resources, Division of Historic Preservation and Archaeology has concluded (letter dated January 15, 1993 from Patrick Ralston, HPA, Appendix) that no known historical, architectural, or archaeological sites listed in or eligible for inclusion in the National Register of Historic Places would be affected by this project. No socioeconomic/cultural resource impacts are expected.

4.2.2.7 Energy and Material Resources

WVGS currently burns coal supplied by mines in western Indiana, including the Black Beauty Coal Company. Approximately 25,000 tons of Illinois No. 5 Self-Scrubbing Coal would be transported to the WVGS and test burned during the five week demonstration phase. The Illinois No. 5 coal is of local origin and readily available for this project. The test burning of these coals is not expected to impact the consumption of coal at the WVGS.

4.2.3 Regulatory Compliance

IDEM is in the process of preparing a formal rule change for WVGS's Units 1 and 2 because they are presently operating above the permitted level for particulate emissions. It is anticipated that the formal rule change will be in place prior to the start of the proposed demonstration project test burns (personal communications with IDEM). WVGS has asked for and received a variance for WVGS's Units 1 and 2 until the formal rule is adopted. On October 5, 1993, a variance was granted to WVGS by IDEM which allows WVGS to exceed the allowable amount of particulate emissions until the formal rule is adopted. The current limits on particulates from Units 1 and 2 are 0.19 lb/MMBtu and 0.22 lb/MMBtu. The combined particulate limits for both Units is 0.22 lb/MMBtu (letter dated October 5, 1993, from IDEM to WVGS, Appendix). Particulate emissions are not expected to increase due to this project.

No modifications are anticipated to existing solid waste disposal permits or NPDES permits. IDEM and the current ash disposal site would be notified of the proposed demonstration project by means of a Letter of Intent.

4.3 ASHTABULA C POWER PLANT

Proposed project activities and a site description of the ACCP near Ashtabula, Ashtabula County, Ohio are presented in the following section.

4.3.1 Project Activities and Site Description

The ACCP has four operational units (Babcock & Wilcox Stirling boilers) and a nominal plant capacity of 188 MW. Testing would be conducted on all four units. The proposed demonstration project at the ACCP would consist of a three week burn of baseline (existing) coal and a five week test burn of the Self-Scrubbing Coal, made from Lower Freeport raw coal. During each of these two burn periods, evaluations would be conducted on boiler performance and flue gas emissions.

The ACCP is located on Lake Erie in Ashtabula County, Ohio, 15 miles west of the Ohio-Pennsylvania border. Figure 18 shows its regional location with a site plan provided as Figure 19. The ACCP is accessible by trucks which deliver coal from a railroad unloading facility located on Lake Erie about two miles west of the plant.

Bottom ash is sluiced to on-site ash hydrobins for dewatering. Fly ash is collected dry in storage silos, emptied into trucks and hauled to an approved off-site landfill.

The ACCP draws water from and discharges into Lake Erie. Potable water for the plant is supplied by nearby industrial plants as part of a reciprocal agreement. The facility has an approved NPDES permit.

4.3.2 Environmental Impact

The existing environment and environmental impacts associated with the test burns of cleaned coal at the ACCP site are presented in the following sections.

4.3.2.1 Atmospheric Resources

The area of the proposed ACCP demonstration site is described as having a continental climate with average summer and winter temperatures of 68°F to 32°F. Average annual precipitation for this area is 37 inches. Lake Erie affects the weather by moderating ambient temperature.

Ashtabula County is in the Northwest Pennsylvania-Youngstown Interstate Air Quality Control Region (40 CFR 81.74). Ashtabula County is better than national standards or cannot be classified for the EPA criteria pollutants PM-10, SO₂, CO, and NO₂. Ashtabula County does not meet primary standards for O₃. The ACCP is currently in

Reference: CCI EIV, July 1993 (Revised).

FA93031005

FIGURE 18. Ashtabula C Power Plant Site

Reference: CCI EIV, July 1993 (Revised).

FA93031001

FIGURE 19. Ashtabula C Power Plant Plot Plan

compliance with state and federal air quality requirements and operates an on-site continuous emission monitors for opacity. Table 14 shows ambient air quality for this area and compares this data to the NAAQS.

In order to predict the impacts which may occur due to the change in coal quality during the proposed demonstration phase, the EPRI CQIM was implemented. This model predicted emission rates for CO₂, SO₂, and NO_x as presented in Table 15, and these estimates would be verified during the test burn period. The emission rate of SO₂ was modeled as being reduced from 5.12 lb/MMBtu to 1.20 lb/MMBtu after coal cleaning at the proposed Custom Coals No. 1 Plant. It would require nearly 4,300 more tons (including sorbent weight) of Self-Scrubbing Coal to produce the same electrical generation as the baseline coal at the ACPP during the proposed demonstration phase. Nearly 4,200 less tons of SO₂ would be produced and emitted to the atmosphere than currently emitted; however, approximately 1,000 additional tons of fly ash would be captured and require disposal, when compared to currently used coals. CO₂ production would increase by approximately 24,000 tons.

The combustion testing of the Self-Scrubbing Coal during the proposed demonstration phase is not of sufficient duration to cause long-term air quality impacts. SO₂ emissions from the ACPP during the proposed demonstration phase are expected to decrease. The ACPP is currently permitted to emit SO₂ at a rate of 8.2 lb/MMBtu. The demonstration would show how SO₂ emissions could be reduced to 1.2 lb/MMBtu or lower by the use of Self-Scrubbing Coal. There is no anticipated change in NO_x emissions during the demonstration. Emissions of CO₂ (a greenhouse gas) would increase marginally, resulting in a 5 parts in ten million increase in the U.S. contribution to global warming, or an increase in 1 part in 10 million global contribution. Test burn data are summarized in Table 15, and would have minimal short term impacts.

4.3.2.2 Land Resources

Lake Erie forms the northern border of the ACPP. Elevations along the shore are approximately 573 feet above sea level. The ACPP lies just east of the limits of the city of Ashtabula.

TABLE 14
ASHTABULA C POWER PLANT SITE
1989-1992 AMBIENT AIR QUALITY MONITORING DATA¹

Pollutant	Averaging Period	NAAQS	Maximum Ambient Concentration³
CO	8-hour	10	3.8
	1-hour	40	7.4
Pb	Quarterly	1.5	No Data
NO ₂	Annual	100	No Data
O ₃	1-hour	235	233
PM-10	Annual	50	21
	24-hour	150	53
TSP	Annual	No Standard	No Data
	24-hour	No Standard	No Data
SO ₂	Annual	80	19
	24-hour	365	148
	3-hour	1300 ²	306

¹All values are in $\mu\text{g}/\text{m}^3$ except CO which are in mg/m^3 .

²Secondary standard..

³O₃ and SO₂ data are from an Ashtabula County Monitor located 12 miles northeast of the site. CO and PM-10 data are from Lake County monitors located approximately 30-40 miles southwest of the site. Data are presented for the most recent year reported.

Reference: Ohio Environmental Protection Agency, 1993.

The National Wetlands Inventory Map produced by the DOI, Fish and Wildlife Service shows no wetlands within the ACPP property, although the shore area of Lake Erie is classified Lacustrine, Littoral, Open Water, Intermittently Exposed/Permanent.

TABLE 15
ASHTABULA C POWER PLANT TEST BURN DATA¹

Type of Coal	Current	Self-Scrubbing
Unit Net MW	188	188
Total Generation During Demonstration Project (MW)	151,200	151,200
Coal BTU Content (BTU/lb)	12,882	12,246
Total Coal Consumed (Tons)	82,384	86,663
Fuel Sulfur %	3.3	1.25
SO ₂ Formation (lbs of SO ₂ /MMBTU)	5.12	1.20
Total SO ₂ Produced (Tons)	5,437	1,274
NO _x Formation (lbs of NO _x /MMBTU)	0.9	0.9
Total NO _x Produced (Tons)	956	956
CO ₂ Formation (lbs of CO ₂ /MMBTU)	177	199
Total CO ₂ Produced (Tons)	187,710	211,503
Fuel Ash %	8.9	9.7
Total Ash (Tons) ²	7,332	8,406
Total Fly Ash (Tons)	5,866	6,723
Total Bottom Ash (Tons)	1,466	1,681
Total Fly Ash Emitted (Tons) ³	106	106

¹Projections have been equalized for five weeks duration, even though the baseline testing duration is three weeks.

²The ash values for Self-Scrubbing Coal include the weight of CaSO₄ produced during combustion.

³Total fly ash emitted is limited by permit and can be controlled by adjusting the ESP.

Reference: CCI EIV, July 1993 (Revised).

No construction activities for the proposed demonstration project would be required at the ACPP. The project would have no impacts on wetland areas or a floodplain.

The burning of Self-Scrubbing Coal would produce more bottom and fly ash than the current fuel burned due to the addition of limestone to the cleaned coal. The total ash disposal requirements would be increased by approximately 1,100 tons during the proposed demonstration phase but emissions to the atmosphere would remain constant. The ash would be disposed of in a permitted residual waste landfill, as it is considered to be a residual waste under Ohio EPA regulations. It is anticipated that the ash would be disposed of at a residual waste landfill in Plymouth Township, Ohio which currently accepts ACPP ash. The power plant does not have an on-site coal stockpile area. Coal is brought to the site daily by truck from the railroad storage area.

4.3.2.3 Water Resources

The ACPP is bordered on the north by Lake Erie. Water from Lake Erie is used as condenser cooling water and house service water, and is supplied to the plant through two 102 inch diameter pipes from two cribs submerged about 20 feet below lake level. Water is discharged back to the lake in accordance with an existing NPDES permit.

Potable water for the plant is supplied by nearby industrial plants. Water used by the ACPP is pumped from Lake Erie and is supplemented by the nearby industrial plants. Bottom ash and fly ash are transported off-site for disposal. Water used to slurry bottom ash on-site is collected in an ash settling basin and then recycled for those operations. The ash settling basin may accumulate soluble sulfates from water used to slurry ash containing CaSO_4 , formed by the sorbent reacting with SO_2 during combustion. No adverse change in the chemical composition or volume of ash basin discharge is expected due to burning of Self-Scrubbing Coal.

4.3.2.4 Ecological Resources

The region surrounding the ACPP is mostly rural/industrial. According to the DOI, Fish and Wildlife Service, (letter dated January 14, 1993, from Kent Kroonemeyer, Appendix) the proposed project lies within the range of the Indiana bat and bald eagle, federally listed endangered species. Due to the type of habitat and location, the project as proposed would have no impact on these species. This letter was in response to a DOE

letter requesting agency information per the Endangered Species Act as well as the Fish and Wildlife Coordination Act.

No construction activities are associated with the proposed demonstration project test burns being performed at the ACPD and no ecological impacts are anticipated.

4.3.2.5 Transportation Impacts

The Self-Scrubbing Coal to be utilized for test burns would be brought to the ACPD by train from the proposed Custom Coals No. 1 Plant. From the train unloading station located adjacent to Lake Erie, the Self-Scrubbing Coal would be transferred to the ACPD by truck. This would represent no change in the current coal delivery system for the site. There would be a minimal increase in truck traffic during the demonstration project, estimated at 35 additional trucks per week, and the associated transportation impacts would be minimal.

4.3.2.6 Socioeconomic Impacts/Cultural Resources

The ACPD is located in the northwest corner of Ashtabula in Ashtabula County, Ohio. Approximately 99,821 people reside in the county. In May 1992, the unemployment rate of 11.9 percent was significantly higher than state and national averages. The proposed demonstration project is not anticipated to have an effect on the area economy as no construction is required. According to the Ohio Historical Society, there are no Native American entities in or near the plant site. The nearest Native American tribal entity is the Seneca Nation of Indians located in Salamanca, New York, along the Pennsylvania/New York border.

The Ohio Historic Preservation Office (OHPO) has concluded (letter dated February 5, 1993 from Martha Raymond, OHPO, Appendix) that the proposed demonstration would have no effect upon any properties listed or eligible for the National Register. No socioeconomic/cultural resource impacts are expected.

4.3.2.7 Energy and Material Resources

During the test burn period, 86,663 tons of Self-Scrubbing Lower Freeport Coal would be required and 82,384 tons of Lower Freeport Seam Coal would be needed for the baseline burn. This coal is readily available for the demonstration and the project would not adversely impact the consumption of other resources currently used at the site.

4.3.3 Regulatory Compliance

The test burning of the Self-Scrubbing Coal would not require modification of air and NPDES permits currently held by the ACPP. The Ohio EPA would be notified of the demonstration project by submission of a letter of notification describing the demonstration project.

5.0 LIST OF AGENCIES AND PERSONS CONSULTED

**Ms. Shari Beener
Somerset County Planning Commission
P.O. Box 4
Somerset, PA 15501**

**Ms. Lorena Butler
U.S. Bureau of Indian Affairs
Eastern Region
3701 North Fairfax Dr.
Arlinton, VA 22203**

**Mr. James Byers
Department of Transportation
Commonwealth of Pennsylvania
1009 Transportation and Safety Building
Harrisburg, PA 17120**

**Mr. Kurt Carr
Pennsylvania Historical and Museum Commission
Bureau for Historic Preservation
P.O. Box 1026
Harrisburg, Pennsylvania 17108-1026**

**Mr. Larry Fedor
Indiana Department of Environmental Management
Office of Air Management
105 South Meridian St.
Indianapolis, Indiana 46206-6015**

**Mr. David Hudak
U.S. Department of the Interior
Fish and Wildlife Service
Bloomington Field Office
718 North Walnut Street
Bloomington, Indiana 47404**

**Mr. Joel Koricich
Pennsylvania Department of Natural resources
Bureau of mining and reclamation
3913 Washington Road
McMurray, PA 15317**

LIST OF AGENCIES AND PERSONS CONSULTED (Continued)

**Mr. Kent Kroonemeyer
U.S. Department of the Interior
Fish and Wildlife Service
Reynoldsburg Field Office
6950-H Americana Parkway
Reynoldsburg, Ohio 43068-4115**

**Ms. Kathy McKenna
Pennsylvania Department of Environmental Resources
Bureau of Forestry
P.O. Box 8552
Harrisburg, PA 17105-8552**

**Mr. Roy Osborne
Department of Transportation
Commonwealth of Pennsylvania
1009 Transportation and Safety Building
Harrisburg, PA 17120**

**Mr. Edward Perry
U.S. Department of the Interior
Fish and Wildlife Service
Suite 322
315 South Allen Street
State College, Pennsylvania 16801**

**Mr. Patrick Ralston
Indiana Department of Natural Resources
Division of Historic Preservation and Archaeology
402 W. Washington Street, Rm. 274
Indianapolis, Indiana 46204**

**Ms. Martha Raymond
Ohio Historic Preservation Office
Ohio Historical Center
1982 Velma Avenue
Columbus, Ohio 43211-2497**

**Mr. Donald Wills
National Mines Corporation
333 West Vine St., Suite 1000
Lexington, Kentucky 40507**

LIST OF AGENCIES AND PERSONS CONSULTED (Continued)

**Mr. William Young
Triebel, Inc.
P.O. Box 51
New Florence, PA 15944**

**Mr. Ed Zelenski
Shade Township Board of Supervisors
P.O. Box 39
Cairnbrook, PA 15924**

6.0 REFERENCES

- 40 CFR 434. Revised 1991. "EPA Effluent Guidelines and Standards for Coal Mining."
- 40 CFR 60.250. 1992. "Standards of Performance for Coal Preparation Plants."
- 40 CFR 81.315. Revised 1989. "Attainment Status Designation - Indiana."
- 40 CFR 81.339. Revised 1989. "Attainment Status Designation - Pennsylvania."
- 40 CFR 81.74. Revised 1989. "Attainment Status Designation - Ohio."
- CCI. "Environmental Information Volume for Self-Scrubbing Coal Technology." Revision 2, July 2, 1993. Pittsburgh, Pennsylvania.
- CCI. DOE personal communications with Ken Harrison, Senior Engineer. July 1993.
- CCI. DOE personal communications with Ken Harrison, Senior Engineer. August-October 1993.
- Commonwealth of Pennsylvania, Department of Environmental Resources. "Summary of Key Requirements for Nontransient Noncommunity Water Systems." Bureau of Community Environmental Control, Division of Water Supplies. October, 1989.
- Cowardin, L.M. et al, "Classification of Wetlands and Deepwater Habitats of the United States", p.5, 11-13, U.S. Fish & Wildlife service Report FWS/OBS-79/31, December 1979.
- Cunniff, Patrick F. "Environmental Noise Pollution." 1977. John Wiley & Sons, Inc. New York, New York.
- National Mines Corporation. Letter to PADER on discharge monitoring reports for Laurel Mine. April 1992. Lexington, Kentucky.
- DOE Assistant Secretary for Fossil Energy. "Clean Coal Technology Demonstration Program Update -1992." February 1993. DOE/FE - 0272.
- EPA. "Compilation of Air Pollutant Emission Factors - Volume 1: Stationary Point and Area Sources, AP-42, Fourth Edition." September 1985.
- EPA Hazardous Waste Engineering Research Laboratory. "Dust Control at Hazardous Waste Sites (Handbook)." November 1985. EPA/540/2-85/003.
- Shade Township Board of Supervisors. DOE personal communication with Ed Zelenski. October 1993.

REFERENCES (Continued)

Somerset County Planning Commission. DOE personal communication with Shari Beener. October 1993.

Wilbur Smith Associates. "Noise Analysis Report on Custom Coals Plant No. 1, Laurel Mine Site." October 1993. Raleigh, North Carolina.

APPENDIX

AGENCY CONSULTATIONS

APPENDIX

AGENCY CONSULTATIONS

1. DOI letter on threatened or endangered species, Custom Coals No. 1 Plant site, 3/23/93.
2. PHMC letter on historic and archaeological resources, Custom Coals No. 1 Plant site, 5/6/93.
3. PHMC letter on historic and archaeological resources, Custom Coals No. 1 Plant site, 1/3/94.
4. PADER letter on the presence of natural resources of special concern, Custom Coals No. 1 Plant site, 10/4/93.
5. Pennsylvania Game Commission letter to PADER on endangered or threatened species, Custom Coals No. 1 Plant site, 11/30/93.
6. DOI letter on threatened or endangered species, CPP site, 8/2/93.
7. PHMC letter on historic and archaeological resources, CPP site, 7/27/93.
8. DOI letter on threatened or endangered species, WVGS site, 1/21/93.
9. Indiana Department of Natural Resources letter on historic and archaeological resources, WVGS site, 1/15/93.
10. IDEM letter to WVGS on notice of decision for variance, WVGS site, 10/5/93.
11. DOI letter on threatened or endangered species, ACP site, 1/14/93.
12. SHPO letter on historic and archaeological resources, ACP site, 2/5/93.

United States Department of the Interior

FISH AND WILDLIFE SERVICE
Suite 322
315 South Allen Street
State College, Pennsylvania 16801

March 23, 1993

FILE COPY

Mr. Joseph B. Renk III
Office of Clean Coal Technology
Department of Energy
Pittsburgh Energy Technology Center
P.O. Box 10940
Pittsburgh, Pennsylvania 15236-0940

circulate
1010 No. 32.9004

Dear Mr. Renk:

This responds to your letter of March 11, 1993, requesting information about federally listed or proposed endangered and threatened species within the area affected by the proposed construction of a coal cleaning plant located in Shade Township, Somerset County, Pennsylvania.

Except for occasional transient species, no federally listed or proposed threatened or endangered species under our jurisdiction are known to exist in the project impact area. Therefore, no Biological Assessment or further Section 7 consultation under the Endangered Species Act (87 Stat. 884, as amended; 16 U.S.C. 1531 et seq.) is required with the Fish and Wildlife Service. Should project plans change, or if additional information on listed or proposed species becomes available, this determination may be reconsidered. A compilation of federally listed endangered and threatened species in Pennsylvania is enclosed for your information.

This response relates only to endangered or threatened species under our jurisdiction based on an office review of the proposed project's location. No field inspection of the project area has been conducted by this office. Consequently, this letter is not to be construed as addressing other Service concerns under the Fish and Wildlife Coordination Act or other legislation.

Federal Candidate and State-listed Species

Candidate species are species under consideration by the Service for possible inclusion on the Federal List of Endangered and Threatened Wildlife and Plants. Because many of these species are known to have suffered population declines, the Service encourages federal agencies and other planners to consider candidate species when planning and implementing their projects.

The Pennsylvania Natural Diversity Inventory (PNDI) is maintained by the Pennsylvania Department of Environmental Resources, The Nature Conservancy and the Western Pennsylvania Conservancy. The Pennsylvania Fish and Wildlife Database is maintained by the Pennsylvania Game Commission. These databases contain the most up-to-date information about candidate and State-listed species in Pennsylvania. Requests for a PNDI review for the presence of candidate and State-listed species, as well as other natural resources of special concern, should be directed to:

Pennsylvania Department of Environmental Resources
Bureau of Forestry
Division of Forest Advisory Services
P.O. Box 8552
Harrisburg, PA 17105-8552

Requests for a review of the Pennsylvania Fish and Wildlife Database should be directed to:

Pennsylvania Game Commission
Bureau of Land Management
Division of Wildlife Data Base
2001 Elmerton Avenue
Harrisburg, PA 17110-9797

Should the data search reveal the presence of any candidate species on the site, the Service should be contacted to ensure that these species are not adversely affected by project activities.

Requests for information regarding State-listed endangered or threatened species should be directed to the Pennsylvania Game Commission (birds and mammals), the Pennsylvania Fish and Boat Commission (fish, reptiles, and amphibians), and the Pennsylvania Department of Environmental Resources (plants).

Please contact Philip Edmunds of this office at 814-234-4090 if you have any questions or require further assistance regarding endangered, threatened, or candidate species.

Sincerely,

Edward W. Perry
Acting Supervisor

Enclosure

FEDERALLY LISTED ENDANGERED SPECIES IN PENNSYLVANIA

<u>COMMON NAME</u>	<u>SCIENTIFIC NAME</u>	<u>STATUS*</u>	<u>DISTRIBUTION</u>
<u>FISHES</u>			
Shortnose sturgeon**	<i>Acipenser brevirostrum</i>	E	Delaware River and other Atlantic coastal waters
<u>REPTILES & AMPHIBIANS</u>			
None			
<u>BIRDS</u>			
Bald eagle	<i>Haliaeetus leucocephalus</i>	E	Entire state-recent nesting in Butler, Crawford, Dauphin, Lancaster, Pike, Tioga, York Counties
Peregrine falcon (American)	<i>Falco peregrinus anatum</i>	E	Entire state-reestablishment to former breeding range in progress
Peregrine falcon (Arctic)	<i>Falco peregrinus tundrius</i>	E	Entire state-migratory
Piping plover	<i>Charadrius melodus</i>	E	Presque Isle-no current nesting
<u>MAMMALS</u>			
Indiana bat	<i>Myotis sodalis</i>	E	Entire state
<u>MOLLUSKS</u>			
Clubshell mussel	<i>Pleurobema clava</i>	E	French Creek and Allegheny River watersheds; Clarion, Crawford, Erie, Forest, Mercer and Venango Counties
Dwarf wedge mussel	<i>Alasmidonta heterodon</i>	E	Delaware River drainage-possibly extirpated
Fanshell	<i>Cyprogenia stegaria</i>	E	Ohio River drainage-possibly extirpated
Northern riffleshell	<i>Epioblasma torulosa rangiana</i>	E	French Creek and Allegheny River watersheds; Crawford, Erie, Forest, Venango and Warren Counties
Orange pimpleback	<i>Plethobasus striatus</i>	E	Ohio River drainage-possibly extirpated
Pink mucket pearly mussel	<i>Lamprellis abrupta</i>	E	Ohio River drainage-possibly extirpated
Rough pigtoe	<i>Pleurobema plenum</i>	E	Ohio River drainage-possibly extirpated
<u>PLANTS</u>			
Northeastern bulrush	<i>Scirpus ancistrochaetus</i>	E	Current - Blair, Centre, Clinton, Cumberland, Dauphin, Franklin, Huntingdon, Lackawanna, Monroe, Union Counties. Historic - Lehigh, Northampton Counties.
Small whorled pogonia	<i>Isotria medeoloides</i>	E	Current - Centre and Venango Counties. Historic - Berks, Chester, Greene, Monroe, Montgomery, Philadelphia Counties.

* E = Endangered

** Shortnose sturgeon is under the jurisdiction of the National Marine Fisheries Service

The following is a partial list of species that no longer occur in Pennsylvania: gray wolf, eastern cougar, moose, bison, lynx, wolverine, passenger pigeon, Bachman's sparrow, common tern, lark sparrow, tiger salamander, mud sunfish, longjaw cisco, lake whitefish, butterfly mussel, American burying beetle, precious underwing moth, Karner blue butterfly, American barberry, small white lady's-slipper, eastern prairie fringed orchid, Virginia spiraea, etc. etc.

Commonwealth of Pennsylvania
Pennsylvania Historical and Museum Commission
Bureau for Historic Preservation
Post Office Box 1026
Harrisburg, Pennsylvania 17108-1026

May 6, 1993

FILED
Circulate_____

File No. 32 900

Joseph B. Renk III
Office of Clean Coal Technology
Pittsburgh Energy Technology Center
P.O. Box 10940
Pittsburgh, PA 15236-0940

RE: ER 92-3334-111-F
Shade Twp., Somerset Co.
U.S. Dept. of Energy
Clean Coal Technology IV
Program Demonstration
Project, Laurel Mine Coal
Cleaning Plant

Dear Mr. Renk:

The above named project has been reviewed by the Bureau for Historic Preservation (the State Historic Preservation Office) in accordance with Section 106 of the National Historic Preservation Act of 1966, as amended in 1980, and the regulations (36 CFR Part 800) of the Advisory Council on Historic Preservation. These requirements include consideration of the projects' potential effects upon both historic and archaeological resources.

There is a high probability that prehistoric and historic archaeological resources are located in this project area. In our opinion, the activity described in your proposal will have no effect on such resources. Should the scope of the project be amended to include additional ground disturbing activity such that the integrity of these resources is effected, this office should be contacted immediately and a Phase I Archaeological Survey may be necessary to locate all potentially significant archaeological resources.

In our opinion this project will have no effect on historic structures.

If you need further information in this matter please consult Noel Strattan at (717) 783-9900.

Sincerely,

Kurt Carr, Chief
Division of Archaeology &
Protection

cc: Jeannette Duvall, ICF Kaiser Engineers
KC/NS

Commonwealth of Pennsylvania
Pennsylvania Historical and Museum Commission
Bureau for Historic Preservation
Post Office Box 1026
Harrisburg, Pennsylvania 17106-1026

January 3, 1994

JOSEPH B RENK III
OFFICE OF CLEAN COAL TECHNOLOGY
PITTSBURGH ENERGY TECHNOLOGY CENTER
PO BOX 10940
PITTSBURGH PA 15236-0940

TO EXPEDITE REVIEW USE
BHP REFERENCE NUMBER

Re: ER# 92 3334 111 H
Clean Coal Technology IV
Program Demonstration Project
New Run-of-Mine Coal Unloading
Area, Proposed Custom Coals
No. 1 Plant
Shade Twp, Somerset County

Dear Mr. Renk:

The above named project has been reviewed by the Bureau for Historic Preservation (the State Historic Preservation Office) in accordance with Section 106 of the National Historic Preservation Act of 1966, as amended in 1980, and the regulations (36 CFR Part 800) of the Advisory Council on Historic Preservation. These requirements include consideration of the project's potential effect upon both historic and archaeological resources.

Based on the available information, there are no National Register eligible or listed historic or archaeological properties in the area of this proposed project and therefore, this project should have no effect upon such resources. Should you become aware, from any source, that historic or archaeological properties are located at or near the project site, please telephone the Bureau for Historic Preservation at (717) 783-8946.

Sincerely,

A handwritten signature in cursive script, appearing to read "Kurt W. Carr".

Kurt W. Carr, Chief
Division of Archaeology &
Protection

KC/dns

COMMONWEALTH OF PENNSYLVANIA
DEPARTMENT OF ENVIRONMENTAL RESOURCES

Bureau of Forestry
Forest Advisory Services
P.O. Box 8552
Harrisburg, PA 17105-8552

717/787-3444

October 4, 1993

Mr. Joe Renk
U.S. Department of Energy
Pittsburgh Energy Technology Center
P.O. Box 10940
Pittsburgh, PA 15236-0940

Dear Mr. Renk:

Re: PNDI Review of a Site on the Central City USGS 7.5' Topo.
Quad., Shade Twp., Somerset Co., Pennsylvania.

Your request of September 30 to review a location within the Central City Quadrangle for the presence of natural resources of special concern was processed by using the Pennsylvania Natural Diversity Inventory (PNDI) information system.

The review did not indicate any confirmed presence of resources of special concern within the study area. However, several plant specimens have been collected historically in the area, but not confirmed to date. Several of these species are wetland plants and should be searched for in the southern section of the project area in wetlands associated with the headwaters of Little Dark Shade Creek. Specimens stored at the Carnegie Museum in Pittsburgh, indicate that both *Solidago purshii*, Pursh's Goldenrod (Pa. Tentatively Undetermined) and *Polemonium vanbruntiae*, Jacob's Ladder (Pa. Endangered) were collected by O.E. Jennings in 1936 within wetlands east of Buckstown. Another plant specimen maintained at the Academy of Natural Sciences in Philadelphia documents *Listera smallii*, Kidney-Leaved Twayblade, (Pa. Endangered) as being collected in mountains near Buckstown. Populations of these three species may still be growing in undisturbed wetlands within your project area.

If any wetlands are to be disturbed by this project, a field survey of such sites by a qualified botanist is recommended to confirm or deny the presence of *Solidago purshii*, *Polemonium vanbruntiae*, and *Listera smallii*. A list of consulting botanists is available from our office. Any population found should be delineated and efforts to preserve the plants and their habitat included in the project planning. Please notify the Bureau of Forestry if your field survey reveals any occurrence of this or other species of concern and PNDI staff will assist with conservation efforts.

October 4, 1993

Be advised that legal authority for Pennsylvania's biological resources resides with three agencies. The enclosure titled, PNDI Species List, outlines which species groups are managed by these agencies. While PNDI functions solely as an information system for natural resources of concern, the Pennsylvania Game Commission maintains the Fish and Wildlife Data Base which can provide data descriptive of all mammals and birds common to Pennsylvania.

PNDI is a site specific information system which describes significant natural resources of Pennsylvania. PNDI includes data descriptive of plant and animal species of special concern, exemplary natural communities and unique geological features. The information system is a cooperative project of the Department of Environmental Resources, The Nature Conservancy and the Western Pennsylvania Conservancy. This response represents the most up-to-date summary of the PNDI data files. However, the absence of recorded information does not necessarily imply actual conditions on-site. A field survey of any site may reveal previously unreported populations.

The PNDI project is funded largely through contributions to the Wild Resource Conservation Fund. This fund was established in 1982 by the Pennsylvania Legislature to provide support for the research and conservation of native plants and non-game animals within the Commonwealth.

Please phone this office should you have questions regarding this response, PNDI or the DER Wild Plant Management Program.

Sincerely,

Kathy A. McKenna, Plant Pgm, Mgr.
Div. of Forest Advisory Services
Bureau of Forestry

Enclosures

cc: Charles Bier, PNDI-West
John Arway, PF&BC
Gregory Grabowicz, PGC
Charles Kulp, US Fish and Wildlife Service
File

PENNSYLVANIA NATURAL DIVERSITY INVENTORY

SPECIES LISTS

The statutory authority for Pennsylvania's animals and plants resides with three separate agencies. The Pennsylvania Department of Environmental Resources has the responsibility for management of the Commonwealth's native wild plants. The Pennsylvania Fish Commission is responsible for management of fish, reptiles, amphibians and aquatic organisms within the Commonwealth. The Pennsylvania Game Commission has the responsibility for managing the state's wild birds and mammals.

For information on current official status for a species, please consult the appropriate agency. Requests for information should be directed to:

PLANTS and
PNDI - general

Plant Program Manager
Pa. Department of Environmental Resources
Bureau of Forestry
Forest Advisory Services
P. O. Box 8552
Harrisburg, PA 17105-8552
(717)787-3444

FISH, REPTILES,
AMPHIBIANS,
AQUATIC ORGANISMS

Endangered Species & Herpetology
Coordinator
Pennsylvania Fish & Boat Commission
Bureau of Fisheries and Engineering
450 Robinson Lane
Bellefonte, PA 16823
(814)359-5113

BIRDS and MAMMALS

Pennsylvania Game Commission
Bureau of Wildlife Management
2001 Elmerton Avenue
Harrisburg, PA 17110-9797
(717)787-5529

For information on species listed under the federal Endangered Species Act of 1973 occurring in Pennsylvania, contact:

Endangered Species Biologist
U.S. Fish and Wildlife Service
315 South Allen Street, Suite 322
State College, PA 16801
(814)234-4090

Thank you for your request. Feel free to contact PNDI if we can be of further assistance.

COMMONWEALTH OF PENNSYLVANIA

PENNSYLVANIA GAME COMMISSION

2001 ELMERTON AVENUE
HARRISBURG, PA 17110-9797

ADMINISTRATIVE BUREAUX:	
ADMINISTRATION	717-787-5670
AUTOMOTIVE AND	
PROCUREMENT DIVISION	717-787-6894
LICENSE DIVISION	717-787-7838
PERSONNEL DIVISION	717-787-7838
WILDLIFE MANAGEMENT	717-787-6589
INFORMATION & EDUCATION	717-787-6585
LAW ENFORCEMENT	717-787-6740
LAND MANAGEMENT	717-787-6816
REAL ESTATE DIVISION	717-787-6800
MANAGEMENT INFORMATION SYSTEMS	717-787-4076

November 30, 1993

Mr. John Pari
Department of Environmental Resources
3913 Washington Road
McMurray PA 15317

In re: Custom Coals International
Somerset County #56931601

Dear Mr. Pari:

Thank you for forwarding the above referenced application to our agency for review.

A field assessment team has recently reviewed this project and reported that except for occasional transient individuals, this project should not affect any endangered or threatened species of bird or mammal recognized by the Pennsylvania Game Commission, nor should it produce an adverse impact to any critical or unique habitat.

Based on these findings, we have no objection to the issuance of this permit, but should project plans change, or if additional information becomes available, this determination could be re-evaluated.

Very truly yours,

Denver A. McDowell, Chief
Division of Environmental
Planning and Habitat Protection
Bureau of Land Management

United States Department of the Interior

FISH AND WILDLIFE SERVICE

Suite 322

315 South Allen Street

State College, Pennsylvania 16801-4850

August 2, 1993

Joseph B. Rank III
Department of Energy
Office of Clean Coal Technology
P.O. Box 10840
Pittsburgh, PA 15236-0840

Dear Mr. Rank:

This responds to your letter of March 11, 1993 requesting information about federally listed or proposed endangered and threatened species within the area affected by the Cheswick Power Station located in Allegheny County, Pennsylvania.

Except for occasional transient species, no federally listed or proposed threatened or endangered species under our jurisdiction are known to exist in the project impact area. Therefore, no Biological Assessment or further Section 7 consultation under the Endangered Species Act (87 Stat. 884, as amended; 16 U.S.C. 1531 et seq.) is required with the Fish and Wildlife Service. Should project plans change, or if additional information on listed or proposed species becomes available, this determination may be reconsidered. A compilation of federally listed endangered and threatened species in Pennsylvania is enclosed for your information.

This response relates only to endangered or threatened species under our jurisdiction based on an office review of the proposed project's location. No field inspection of the project area has been conducted by this office. Consequently, this letter is not to be construed as addressing other Service concerns under the Fish and Wildlife Coordination Act or other legislation.

Federal Candidate and State-Listed Species

Candidate species are species under consideration by the Service for possible inclusion on the Federal List of Endangered and Threatened Wildlife and Plants. Because many of these species are known to have suffered population declines, the Service encourages federal agencies and other planners to consider candidate species when planning and implementing their projects.

The Pennsylvania Natural Diversity Inventory (PNDI) is maintained by the Pennsylvania Department of Environmental Resources, The Nature Conservancy and the Western Pennsylvania Conservancy. The Pennsylvania Fish and Wildlife Database is maintained by the Pennsylvania Game Commission. These databases contain the most up-to-date information about candidate and State-listed species in Pennsylvania. Requests for a PNDI review for the presence of candidate and State-listed species, as well as other natural resources of special concern, should be directed to:

Pennsylvania Department of Environmental Resources
Bureau of Forestry
Division of Forest Advisory Services
P.O. Box 8552
Harrisburg, PA 17105-8552

Requests for a review of the Pennsylvania Fish and Wildlife Database should be directed to:

Pennsylvania Game Commission
Bureau of Land Management
Division of Wildlife Data Base
2001 Elmerton Avenue
Harrisburg, PA 17110-8797

Should the data search reveal the presence of any candidate species on the site, the Service should be contacted to ensure that these species are not adversely affected by project activities.

Requests for information regarding State-listed endangered or threatened species should be directed to the Pennsylvania Game Commission (birds and mammals), the Pennsylvania Fish and Boat Commission (fish, reptiles, and amphibians), and the Pennsylvania Department of Environmental Resources (plants).

Please contact Philip Edmunds of my staff at 814-234-4080 if you have any questions or require further assistance regarding endangered, threatened, or candidate species.

Sincerely,

Charles J. Kulp
Supervisor

Enclosure

cc:
PFBC - Arvey
- Shiffer
PGC - Grabowicz
EPA - Hoffman
DARD - ES
Reader's file
Project file
ES:PAFO:PEdmonds:ls:8/2/93
filename:renk.esl

Commonwealth of Pennsylvania
Pennsylvania Historical and Museum Commission
Bureau for Historic Preservation
Post Office Box 1026
Harrisburg, Pennsylvania 17108-1026

July 27, 1993

JOSEPH B RENK III
OFFICE OF CLEAN COAL TECHNOLOGY
PITTSBURGH ENERGY TECHNOLOGY CENTER
PO BOX 10940
PITTSBURGH PA 15236-0940

TO EXPEDITE REVIEW USE
BHP REFERENCE NUMBER

Re: ER# 92 3334 111
Clean Coal Technology IV
Program Demonstration Project
Cheswick Power Station Test
Burn, Allegheny County

Dear Mr. Renk:

The above named project has been reviewed by the Bureau for Historic Preservation (the State Historic Preservation Office) in accordance with Section 106 of the National Historic Preservation Act of 1966, as amended in 1980, and the regulations (36 CFR Part 800) of the Advisory Council on Historic Preservation. These requirements include consideration of the project's potential effect upon both historic and archaeological resources.

It is our opinion that the test burning of the cleaned coal from the CCT-IV program will have no effect on archaeological or historical resources in the vicinity of the Cheswick Power Station.

If you need further information in this matter please consult Noël Strattan at (717) 783-9900.

Sincerely,

Kurt W. Carr, Chief
Division of Archaeology &
Protection

KC/dns

IN REPLY REFER TO:

United States Department of the Interior

FISH AND WILDLIFE SERVICE
BLOOMINGTON FIELD OFFICE (ES)
718 North Walnut Street
Bloomington, Indiana 47404
(812) 334-4261 FAX 334-4273

32 755A

January 21, 1993

Mr. Joseph Renk III
Office of Clean Coal Technology
Department of Energy
Pittsburgh Energy Technology Center
P.O. Box 10940
Pittsburgh, Pennsylvania 15236-0940

Dear Mr. Renk:

This responds to your letter of January 4, 1993, concerning the Clean Coal Technology Program's proposed test burn at the Whitewater Valley Generating Station in Wayne County, Indiana.

These comments have been prepared under the authority of the Fish and Wildlife Coordination Act (16 U.S.C. 661 et. seq.) and are consistent with the intent of the National Environmental Policy Act of 1969, the Endangered Species Act of 1973, and the U. S. Fish and Wildlife Service's Mitigation Policy.

We concur with your conclusion that the proposed project is not likely to affect the federally-endangered Indiana bat (*Myotis sodalis*), which is the only federally-listed species whose range includes the project site.

This precludes the need for further consultation on this project as required under Section 7 of the Endangered Species Act of 1973, as amended. If, however, new information on endangered species at the site becomes available or if project plans are changed significantly, please contact our office for further consultation.

Since the project involves an existing facility and no new construction is proposed, we do not anticipate any significant impacts to fish and wildlife resources.

For further discussion, please contact Mike Litwin at (812) 334-4268.

Sincerely yours,

David C. Hudak
Supervisor

INDIANA DEPARTMENT OF NATURAL RESOURCES

PATRICK R. RALSTON, DIRECTOR

Division of Historic Preservation
and Archaeology
402 W. Washington St., Rm. 274
Indianapolis, Indiana 46204
317-232-1646

32.900f

January 15, 1993

Joseph B. Renk III
Department of Energy
Pittsburgh Energy Technology Center
P.O. Box 10940
Pittsburgh, Pennsylvania 15236-0940

Dear Mr. Renk:

We have reviewed the proposed test burn of cleaned coal at Richmond Power and Light's Whitewater Valley Generating Station located in Richmond, Wayne County, Indiana.

No known historical, architectural, or archaeological sites listed in or eligible for inclusion in the National Register of Historic Places will be affected by this project.

We appreciate the opportunity to be of service.

Very truly yours,

Patrick R. Ralston
State Historic Preservation Officer

PRR:SBG:vk

"EQUAL OPPORTUNITY EMPLOYER"

cc: Director, Indiana Div. of Fish & Wildlife, Indianapolis, IN
Indiana Dept. of Environmental Mgt., Bradbury, Indianapolis, IN
Indiana Div. of Outdoor Rec., Indianapolis, IN

INDIANA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT

We make Indiana a cleaner, healthier place to live

Evan Bayh
Governor
Kathy Prosser
Commissioner

105 South Meridian Street
P.O. Box 6015
Indianapolis, Indiana 46206-6015
Telephone 317-232-8603
Environmental Helpline 1-800-451-6027

October 5, 1993

Mr. Irving A. Huffman
General Manager
Richmond Power & Light Co.
2000 U.S. 27 South
P.O. Box 908
Richmond, IN 47374

Re: Notice of Decision
Petition for Variance

Dear Mr. Huffman:

On August 17, 1990, the Indiana Department of Environmental Management, Office of Air Management ("OAM") received Richmond Power & Light's ("RPL") petition for a variance from 326 IAC 6-1-14. An amended request was received on September 27, 1991, and this amended request was further supplemented on November 4, 1992. Specifically, the variance request pertains to particulate emissions from boiler Unit Nos. 1 and 2, both during normal operation and during that period when RPL's pilot project for sulfur dioxide removal ("LIFAC") is operational. The variance request asks for relief from the boilers' particulate limits until such time that (a) there is a ruling on a formal request for a change of these State Implementation Plan limits and that (b) the LIFAC project is completed.

On May 15, 1992, the OAM ruled after reviewing RPL's petition, that because of the pending LIFAC project, an "undue hardship" would be caused to RPL if a variance was not granted immediately. At that time, a variance from 326 IAC 6-1-14 for the period when LIFAC is operational was granted, and specific particulate limits for the various stages of the LIFAC project were set. That variance was renewed on July 9, 1993. A decision on whether to grant RPL a variance for non-LIFAC operation was deferred until review of modeling data prepared by RPL, demonstrated that national ambient air quality standards would not be threatened in Wayne County if limits proposed by RPL were adopted. On August 13, 1992, a report detailing this modeling was submitted to the OAM. That modeling

EXHIBIT A

Mr. Irving A. Huffman

Page 2

supports RPL's position that, pursuant to Ind. Code § 13-7-7-6, a variance from 326 IAC 6-1-14 is justified during routine, non-LIFAC operation, and such variance is hereby granted.

The following conditions are attached to this variance:

- 1) The variance will become effective immediately and will have a statutory expiration date of one year from the date of this letter.
- 2) Particulate limits for Unit 1, Unit 2 and the combined effluent shall be as follows:

Unit 1:	0.19 lbs/MMBtu
Unit 2:	0.22 lbs/MMBtu
Combined effluent limit:	0.22 lbs/MMBtu
- 3) All other conditions of the plant's Operation Permits (ID numbers 89-09-94-0205, 0206, and subsequent amendment dated October 18, 1990) are applicable, including those limiting opacity and requiring particulate stack testing.
- 4) Compliance with the limits set forth in this variance may be demonstrated by stack test results that are corrected for soot blowing. (See attached equation).

If there are any questions regarding this matter, please contact Dan Hancock at the above address, or by telephone at (317) 232-8429.

Sincerely,

Timothy Method
Assistant Commissioner
Office of Air Management

Enclosure:

cc: Jay Rodia, Office of Legal Counsel
Leslie H. Williams, Attorney General's Office
Anthony C. Sullivan, Barnes & Thornburg
Dan Hancock, Air Compliance Section I

EXHIBIT A

Emission test results from equipment with intermittent rapping or cleaning cycles can be evaluated by using a time-weighted averaging procedure as opposed to a straight averaging technique. The representative pounds per hour of particulate emissions (E) can be calculated using the following equation. This equation insures proper weighting of an intermittent cleaning cycle performance test run regardless of the length of the cleaning cycle, and regardless of the number and duration of the test runs made on the unit.

$$E = E_{cc} \frac{(A+B)S}{AR} + E_{ccc} \frac{(R-S)}{R} - \frac{BS}{AR}$$

where;

E = pounds per hour of particulate emissions

E_{cc} = average E of sample(s) containing cleaning cycle

E_{ccc} = average E of sample(s) containing no cleaning cycle

A = hours of cleaning cycle operation during sample

B = hours with no cleaning cycle operation during sample

R = average hours of operation per 24 hours

S = average hours of cleaning cycle operations per 24 hours

United States Department of the Interior

Fish and Wildlife Service
Reynoldsburg Field Office
6950-H Americana Parkway
Reynoldsburg, Ohio 43068-4115

FILE COPY

COMM: 614/469-6923 FAX: 614/469-6919

January 14, 1993

In Reply Refer to:

Circulate _____

File No. 32-100A

Mr. Joseph B. Renk III
Office of Clean Coal Technology
Department of Energy
Pittsburgh Energy Technology Center
Post Office Box 10940
Pittsburgh, Pennsylvania 15236-0940

Dear Mr. Renk:

This responds to your January 7, 1993 letter requesting our comments on your proposal to conduct a clean coal technology test burn at the Centerior Energy's Ashtabula C Plant in Ashtabula, Ashtabula County, Ohio.

As proposed, the coal will be cleaned and then shipped by rail from the Pennsylvania cleaning facility to the test burn site in Ashtabula. No new construction will be necessary at the Ashtabula site.

These comments are provided under the authority of the Endangered Species Act of 1973, as amended.

ENDANGERED SPECIES COMMENTS: The proposed project lies within the range of the Indiana bat and bald eagle, Federally listed endangered species. Due to the type of habitat and location, the project, as proposed, will have no impact on these species. This precludes the need for further action on this project as required by the 1973 Endangered Species Act, as amended. Should the project be modified or new information become available that indicates listed or proposed species may be affected, consultation should be initiated.

Sincerely,

Kent E. Kroonmeyer
for Kent E. Kroonmeyer
Supervisor

cc: DOW, Wildlife Environmental Section, Columbus, OH
ODNR, Office of Realty and Land Management, Columbus, OH
Ohio EPA, Water Quality Monitoring, Attn: G.Hesse, Columbus, OH
US EPA, Office of Environmental Review, Chicago, IL

Ohio Historic Preservation Office

Ohio Historical Center
1982 Velma Avenue
Columbus, Ohio 43211-2497
614/297-2470
Fax 297-2411

**OHIO
HISTORICAL
SOCIETY**
SINCE 1885

February 5, 1993

Joseph B. Renk III
Office of Clean Coal Technology
Department of Energy
Pittsburgh Energy Technology Center
P.O. Box 10940
Pittsburgh, PA 15236-0940

Dear Mr. Renk:

Re: Demonstration Coal Burning at Centerior Energy's Ashtabula C Plant
Ashtabula, Ohio

This is in response to your letter dated January 7, 1992 (received January 12th) concerning the proposed project. Our comments are submitted in accordance with the provisions of Section 106 of the National Historic Preservation Act of 1966 (36 CFR 800). Section 106 requires that all federally funded, permitted or licensed projects be reviewed to determine their effect on historic properties. We initially reviewed this project in December, 1992 at the request of Ms. Jeanette C. Duvall, ICF Kaiser Engineers, Inc.

It is still our opinion that the project will have no effect upon any properties listed or eligible for the National Register. Should any archaeological remains be accidentally discovered, this office should be contacted. Otherwise, no further coordination is required for this project.

Please contact Julie Quinlan at the above number if you have any questions. Her hours are from 9:30 a.m.-12:30 p.m. Thank you for your cooperation.

Sincerely,

Martha J. Raymond, Department Head
Technical and Review Services

MJR/JAQ:jq

FINDING OF NO SIGNIFICANT IMPACT

for the Proposed

Custom Coal International's
"Self-Scrubbing Coal™: An Integrated Approach to Clean Air"
Clean Coal Technology Demonstration Project

AGENCY: U.S. Department of Energy (DOE)

ACTION: Finding of No Significant Impact (FONSI)

SUMMARY: DOE has prepared an Environmental Assessment (EA) (DOE/ EA-0916) for a project proposed by Custom Coals International (CCI) for cost-shared funding support for land acquisition, design, construction, and operation of an advanced design coal cleaning technology project, "Self-Scrubbing Coal™: An Integrated Approach to Clean Air." This project would clean run-of-mine coal using CCI technology, and would fire the resulting clean coals in limited duration test burns at coal burning utilities in Indiana, Ohio, and Pennsylvania. The proposed project would be located in Shade Township, Somerset County, Pennsylvania, at the site of the presently inactive Laurel Coal Preparation Plant, which would be purchased by CCI. The demonstration project, including the limited duration test burns at coal-fired utilities, would last 34 months, with construction scheduled to begin in the winter of 1994, and would cost a total of \$81.7 million. Subsequent to the demonstration period, the proposed Custom Coals No. 1 Plant would operate commercially for a 20-year duration.

The proposed Federal action is to provide cost-shared financial assistance to the project. DOE's share of the project cost would be 47 percent, or \$38 million. Based on the analysis in the EA, DOE has determined that the proposed action is not a major Federal action significantly affecting the quality of the human environment within the meaning of the National Environmental Policy Act (NEPA) of 1969. Therefore, the preparation of an Environmental Impact Statement is not required, and the Department is issuing this Finding of No Significant Impact (FONSI).

COPIES OF THIS EA ARE AVAILABLE FROM:

Mr. Joseph B. Renk, III
Office of Clean Coal Technology, MS 920-L
Pittsburgh Energy Technology Center
P.O. Box 10940
MS-920L
Pittsburgh, Pennsylvania 15236-0940
(412) 892-6249

FOR FURTHER INFORMATION CONTACT:

Ms. Carol M. Borgstrom, Director
Office of NEPA Oversight (EH-25)
U.S. Department of Energy
1000 Independence Avenue, S.W.
Washington, DC 20585
Tel: (202) 586-4600 or (800) 472-2756

BACKGROUND: In October 1989, Public Law No. 101-121, "An Act Making Appropriations for the Department of the Interior and Related Agencies for the Fiscal Year Ending September 30, 1990, and for Other Purposes" (the Act), was signed into

law, providing \$600 million in funding to the DOE to conduct cost-shared Clean Coal Technology (CCT) projects under the fourth round of the Clean Coal Technology Demonstration Program. The Act included funding appropriations for the design, construction, and operation of cost-shared clean coal projects to demonstrate technologies capable of replacing, retrofitting, or repowering existing power generating facilities.

Pursuant to Public Law No. 101-512 (Department of the Interior and Related Agencies Appropriations Act for Fiscal Year 1990), a Program Opportunity Notice (PON) was issued by the DOE in January 1991, soliciting proposals to conduct cost-shared CCT projects demonstrating innovative, energy efficient, technologies capable of being commercialized in the 1990s. The technologies proposed in response to this PON were to be capable of (1) achieving significant reductions in the emissions of sulfur dioxide (SO_2) and/or oxides of nitrogen (NO_x) from existing facilities and/or (2) providing for future energy needs in an environmentally acceptable manner. In May 1991, DOE received 33 proposals in response to the PON, nine of which were selected for award. The "Self-Scrubbing Coal™: An Integrated Approach to Clean Air" project, proposed by CCI, was one of these nine. The proposed Federal action would be to provide, through a cooperative agreement, 47 percent cost-shared financial assistance to the project, or \$38 million. Total cost of the project would be \$81.7 million. Including the limited duration test burns at coal-fired utilities, the demonstration project would last 34 months, with construction scheduled to begin in the winter of 1994.

DESCRIPTION OF THE PROPOSED PROJECT: DOE proposes to provide cost-shared funding support for the project, which would include the purchase of property in Shade Township, Somerset County, Pennsylvania, and the design, construction, and operation of a 500 ton per hour coal preparation plant. The CCI technology would extend current coal cleaning techniques to finer sizes of coal, and would separate the coal from associated sulfur-containing minerals (pyrites) more

efficiently than existing processes. This plant would produce a cleaned coal (to be called "Carefree Coal") or a cleaned coal mixed with limestone/dolomite (referred to as "Self-Scrubbing Coal"). The Self-Scrubbing Coal would chemically react with SO_2 during combustion within a utility boiler, thereby further reducing SO_2 emissions.

Carefree and Self-Scrubbing Coals would be produced through an aggressive, proprietary, two-stage sulfur and mineral matter removal process. The proposed technology combines conventional coal cleaning technology with new technology that cleans very fine-sized coal. The fine-sized coal, produced through coal crushing, is cleaned using an aqueous suspension of finely ground magnetite (iron oxide particles) that separates coal fractions based on density. An advanced cyclone is then used to separate the fine-sized clean coal from the remaining sulfur and ash. This unique separation system removes non-combustible material from the coal, including more than 90 percent of its pyritic sulfur. Coal produced in this manner that would be capable of complying with the requirements of the 1990 Clean Air Act Amendments (CAAA) would be marketed as Carefree Coal. However, coals with high organic sulfur contents would need further processing to meet CAAA requirements; limestone or dolomite would be incorporated into the cleaned coal to produce the product called Self-Scrubbing Coal. During combustion at utility plants, 30-35 percent of the remaining pyritic and organic sulfur would react with this dolomite or limestone, thereby reducing the quantity of SO_2 present in the flue gas.

The proposed project would be located at the presently inactive Laurel Coal Preparation Plant site, and would be designated as the Custom Coals No. 1 Plant. The proposed demonstration would include limited duration test burns of the Carefree or Self-Scrubbing Coals at Duquesne Light Company's Cheswick Power Plant (CPP) in Springdale, Allegheny County, Pennsylvania; Richmond Power and Light's Whitewater Valley Generating Station (WVGS) near Richmond, Wayne County, Indiana; and Centerior Energy's Ashtabula C Power Plant (ACPP) near Ashtabula, Ashtabula County, Ohio.

Upon completion of the demonstration period, the proposed Custom Coals No. 1 Plant would operate commercially for twenty years, processing Kittanning Seam coal and producing Carefree Coal that would be burned at electric utilities in the Northeast and sold to other non-utility markets. No mining activity would occur at the project site; all coals processed would be delivered from existing off-site mines.

ENVIRONMENTAL IMPACTS: Potential environmental impacts of the proposed demonstration project were analyzed for both construction activities and plant operations with regard to the Custom Coals No. 1 Plant, and also for the full-scale, limited duration test burns at the three utilities. The test burns would not require construction at the CPP, WVGS, and ACPP sites, and would each be limited to a three- to five-week period. These three sites, currently operating with conventional cleaned coals, would operate in an almost identical manner during the test burns when compared to current operations; therefore, the potential environmental impacts would be minimal. Almost all of the potential environmental impacts associated with the project would occur at the 586-acre site of the proposed Custom Coals No. 1 Plant. Air emissions, wastewater discharges, and other physical and environmental modifications associated with the proposed demonstration plant construction and operation were compared with existing baseline conditions at the existing site to determine potential environmental impacts.

Construction Impacts: Custom Coals No. 1 Plant

Planned demolition activities at the inactive Laurel Coal Preparation Plant site would be confined to existing portions of the property already disturbed by former industrial activity. Asbestos would be removed from all structures in accordance with all applicable regulations prior to demolition. New construction, which would take place on only five to ten acres of the site, would not change the current industrial setting of the land. New facilities would include an elevated conveyor, preparation building, thermal dryer, clean coal silo, coal cleaning treatment tanks, raw coal receiving

facilities, and clean coal loading areas. To minimize waste disposal, some materials resulting from demolition activities would be used in the Custom Coals No. 1 Plant or sold. Remaining nonhazardous materials would be taken to an approved landfill. Any hazardous wastes from demolition or construction activities would be handled in accordance with Resource Conservation and Recovery Act regulations.

Construction of the proposed Custom Coals No. 1 Plant would not affect any federally listed threatened or endangered species. Both the U.S. Fish and Wildlife Service and the Pennsylvania Department of Environmental Resources (PADER) were notified of the proposed project and concurred in writing that the proposed Custom Coals No. 1 Plant would likely have no impacts to protected flora and fauna. The Pennsylvania Historic and Museum Commission, Bureau for Historic Preservation, has concluded that no known archaeological, historical, cultural, or scientific resources, or Native American tribal or other religious practices would likely be impacted by the proposed Custom Coals No. 1 Plant.

To minimize erosion, a PADER-approved sedimentation and control plan would be implemented prior to construction and disturbed areas would be revegetated promptly. When required, wetting of dry soils will be employed to minimize dust emissions from construction activities. Construction noise would have minimal impacts since it would be limited in duration, and the closest residence is 400 feet away from construction areas. The existing roadway system can adequately handle construction worker commuter traffic, and the delivery of construction supplies.

Peak construction activities would occur during 1994. The proposed project, expected to require 200 workers during the construction period, would have a positive impact on the local economy.

Operational Impacts: Custom Coals No. 1 Plant

The Custom Coals No. 1 Plant would operate for approximately 20 years. The proposed DOE-assisted demonstration phase covers the first 16 months of operation, beginning in 1994. Commercial-phase operations of the plant would continue through the year 2016. Coal cleaning would take place eight hours per day, five days per week, during the demonstration phase; during the commercial phase, the plant would operate 20 hours per day, six days per week. The EA analyzed environmental impacts for both phases of the project, and focused on the commercial-phase impacts when approximately 2.5 million tons per year of coal would be processed.

This project would incorporate a number of mitigating measures that would minimize air pollutant emissions. The primary pollutant generated would be particulates. Annual emissions of total suspended particulates (TSP) and particulate matter less than 10 microns in diameter (PM_{10}) for the Custom Coals No. 1 Plant are estimated at 56.4 and 21.6 tons per year, respectively. These emissions include point and fugitive sources as well as secondary emissions associated with coal transport vehicles. Similar calculations revealed that emissions would be 18.2 tons per year for NO_x , 11.6 tons per year for carbon monoxide, and less than 10 tons per year for SO_2 and hydrocarbons. Based on these calculations, PADER has determined that the proposed project is not subject to Prevention of Significant Deterioration or New Source Review requirements. Modeling was performed to estimate the proposed Custom Coals No. 1 Plant's impact on air quality. The EPA Industrial Source Complex Model, in its short-term mode, was used to assess PM_{10} impacts. Prior to operation of the project, the 24-hour ambient PM_{10} concentration was calculated to be between 14 and 40 percent of the National Ambient Air Quality Standards (NAAQS); project operation would increase PM_{10} levels to between 19 and 49 percent of the 24-hour NAAQS. This increase in PM_{10} concentration would produce essentially no change in the character of the ambient air quality.

Water use for the proposed Custom Coals No. 1 Plant is estimated at 153 million gallons annually. Potable water demand would be an estimated 4,600 gallons per day, to be supplied by an on-site deep well. An elaborate system of ponds, combined with a lime/aeration wastewater treatment system, would provide process water for the site, and maintain water quality discharges according to stringent permit requirements set by the PADER. The ponds and wastewater treatment system originally were constructed for the currently inactive Laurel Coal Preparation Plant, and would function in a similar manner for the proposed Custom Coals No. 1 Plant. The ponds collect stormwater runoff, and would allow process water to be recycled. Discharges from the plant to two streams would be regulated by two PADER-issued permits: a Coal Mining Activity Permit (CMAP), and a Coal Refuse Disposal Permit (CRDP). Based on analysis of previous discharge data from the Laurel Coal Preparation Plant, and the proposed treatment system, wastewater discharges to streams would have no adverse impacts on water quality.

Discussions between CCI and PADER with regard to the CRDP may result in the need to line one of the ponds to protect groundwater. PADER has expressed concern with existing groundwater quality based on previous site activities and engineering controls in effect during previous operations.

The proposed Custom Coals No. 1 Plant would generate approximately 625,000 tons of refuse annually, since approximately 25 percent of the run-of-mine coals would become waste products of the coal preparation plant. This refuse would be disposed of in an on-site refuse disposal facility originally constructed for the Laurel Coal Preparation Plant. The capacity of the existing refuse disposal facility is sufficient for the demonstration phase wastes, and for 16 years of commercial operation. After that time, a new coal refuse disposal facility would be needed in order for commercial operation to continue. In addition to the existing environmental controls designed into the disposal site, PADER may impose additional conditions before granting permit approval.

Operation of the proposed coal cleaning facility would not affect flora, fauna, or other ecological resources. The project is not located in either a 100- or 500-year floodplain, and would not impact any wetlands.

Test burn run-of-mine coals for the demonstration phase would be delivered to the Custom Coals No. 1 plant by rail, and the cleaned coals would also be shipped off site by rail. During the commercial phase of the project, coal would be delivered to the site by truck and shipped off site by truck. A traffic study was conducted to assess existing traffic and roadway conditions within the study area, and the impact of coal deliveries to the site by truck. Traffic volumes would be highest during the commercial phase, when 542 trucks would use the site daily. The traffic study assumed a background traffic growth rate of 1.5 percent a year through 2013, and that a coal preparation plant located south of the proposed site (which currently affects area roadways) would cease operations due to the effects of environmental regulations and economic factors. The traffic analysis found that all roadways and intersections affected by the project would operate at Level of Service "C," which is a stable traffic flow condition without excessive delays. Three roadway segments would deteriorate from Level of Service "B" to "C," which would cause drivers to experience less freedom of movement and some delays. The traffic study recommended some roadway improvements, which would be implemented by CCI to promote safe traffic conditions. The Pennsylvania Department of Transportation (PennDOT) believes that additional safety measures may be necessary, and these are currently being evaluated by CCI. During the a.m. and p.m. peak hours, truck traffic would increase from 22 to 97 trucks along a segment of State Route 160 that has 36 adjacent homes. During the remainder of the daylight hours, truck traffic would average 65 vehicles per hour, as compared to the existing 18 vehicles per hour. Truck traffic north of the proposed Custom Coals No. 1 Plant would increase during the a.m. peak hour from 22 to 48 vehicles per hour; during the remainder of the daylight hours, truck traffic would average 35 vehicles per hour, as compared to the existing 15 vehicles per hour.

Truck traffic travelling to and from the proposed Custom Coals No. 1 Plant along State Route 160 would be the major noise generator. A noise analysis was conducted to determine truck traffic impacts, directly associated with trucking activity for the proposed project, on the 50 residences located along State Route 160. Existing noise levels were monitored and project impacts were determined with the use of a Federal Highway Administration-approved (FHWA) computer model. Off-site truck traffic would occur only during daylight hours, such that nighttime impacts would be minimal. The analysis determined that, during commercial operations, noise levels would approach or exceed an average noise level (L_{eq}) of 66.5 A-weighted decibels (dBA) at numerous resident locations. Under these conditions, FHWA guidelines require that noise mitigation measures be evaluated and implemented where reasonable and feasible. However, the only suitable mitigation measure for this project was determined to be adherence to the 35-mph speed limit on this roadway. The noise study concluded that, during the year 2013, 12 residences would experience noise levels above 66.5 dBA even with 35-mph truck speeds. However, changes in noise levels from existing conditions at each of these 12 locations would be barely perceptible because noise level increases would be limited to no more than 3.0 dBA. Noise increases of less than 3.0 dBA would be barely perceptible and would not change the noise character of the area. Discussions with PennDOT, which has noise policies essentially similar to those of FHWA, indicate that project impacts would not be substantial, and are permissible.

The noise analysis also evaluated impacts to residents and other receptor locations influenced by on-site preparation plant activities, as well as impacts to worker health and safety associated with project noise levels. These impacts were determined to be minimal.

Commercial phase operations at the plant are expected to require a total of 41 full-time employees, hired locally. Based on contacts with the Somerset County Planning Commission and Shade Township officials, it is anticipated there would be no adverse cumulative impacts resulting from this project.

Impacts associated with the project would not concentrate risks to any particular gender, age, or racial minority group; therefore, the project does not present environmental equity concerns. The project would not impact Native American Tribal or other religious practices or sites. The project would have negligible impacts on the Shade Church, an inactive church with an adjacent graveyard located near the proposed preparation plant site. The proposed project would be subject to the regulations of both the Occupational Safety and Health Administration and the Mine Safety and Health Administration. Impacts to worker health and safety would be minimal.

When the commercial phase of the project begins in 1996, no change in the amount of coal mined and cleaned in the region is expected, due to the expected termination of operations of the nearby coal preparation plant. The commercial phase of the project would require approximately 2.5 million tons a year of coal, and 500,000 gallons annually of No. 2 fuel oil to power vehicles and a thermal dryer used to dry processed coal. Electrical power requirements are estimated at 10 megawatts annually. Other materials required for the project, i.e., dolomite, limestone, and magnetite, are readily available in sufficient quantities. The Custom Coals No. 1 Plant would be a net discharger of water due to the extensive water recycle system, including process plant use of collected stormwater. Only during periods of low rainfall would an on-site deep well be used to supplement water supplies.

The project would employ several pollution prevention principles and techniques, including: demonstration of an innovative method of advanced coal cleaning to reduce sulfur content of coals, thereby preventing sulfur dioxide generation upon coal combustion; demonstration of a technology that would reduce the sulfur content of fine sizes of coal and enable the recovery of this coal cleaning waste as a utility fuel rather than being incorporated into the refuse; and recycle of stormwater and

preparation plant water for reuse as process makeup, thus reducing the demand for fresh water. The project would have negligible impacts on biodiversity.

Regulatory approvals from PADER are required for the project with regard to air emissions, wastewater discharges, coal refuse disposal facility operation, and other environmental issues associated with coal cleaning activities. On January 27, 1994, an informal public meeting was held by PADER in response to a request from concerned citizens regarding two permits: the CMAP and the CRDP. About 30 people attended the meeting, and eight individuals presented comments to the State. Concerns were expressed regarding potential environmental impacts related to transportation (truck traffic, noise, and dust), air quality, and water quality, and in general related to enforcement by PADER of regulatory requirements. However, no comments were expressed or information presented at the meeting that had not already been addressed and considered in the EA or that would alter the findings of this FONSI. Pittsburgh Energy Technology Center personnel attended the public meeting, and distributed copies of the EA to interested parties for their information and review.

PETC received a response from an interested party who attended the PADER meeting. The main concern was that for the demonstration phase of the proposed project, there was no mention of rail car unloading facilities in the EA. In fact, during the demonstration phase a portable rail car unloading system which meets all PADER requirements for dust suppression would be employed. In addition, a copy of a letter addressed to PADER was received by PETC which expressed concern with regard to truck traffic related issues. The letter expressed concern about increased truck traffic on State Route 30, traffic impacts on bus routes and the Shade-Central City School District, and possible pollution from the trucks.- The traffic impacts on bus routes and the school district would not experience any change from existing conditions. One school bus passes the proposed site entrance in the morning and in the afternoon. The bus has no stops along the route that would experience an increase in truck traffic. No other responses were received or are anticipated that would materially affect this FONSI. Similarly, PADER does not anticipate that the meeting will result in

delaying the issuance of the facility permits. DOE expects that permit conditions will be satisfied by the project during both demonstration and commercial operation.

Operational Impacts: Test Burns

The demonstration project test burns would compare conventionally cleaned coals currently burned at the three test sites to coals from the same or similar formations that would be processed at the Custom Coals No. 1 Plant. Baseline testing on existing coals would occur at all three utilities for a one to three week period, while test burn activity would last for three to five weeks.

Test burn coals would produce air emissions comparable to or less than levels currently produced at the three utility sites, except, however, that SO₂ emissions should be much lower. There would be negligible changes in wastes produced and water discharges. Burning of Carefree Coal would generate less fly ash and bottom ash, as well as reduced trace metal emissions due to the higher coal cleaning efficiency of the proposed Custom Coals No. 1 Plant. The presence of the limestone or dolomite sorbent in Self-Scrubbing Coals would have negligible impacts on coal pile runoff, and on ash quantities and composition. There would be no construction activities required at any of the test burn sites. Transportation impacts from test burn coal deliveries would be similar to existing conditions. No impacts are expected at the sites with regard to ecological resources, socioeconomic and cultural resources, and energy and material resources.

Test burn data at each site would be collected according to a formal Environmental Monitoring Plan, approved by DOE, that specifies sampling methods and protocols. Appropriate regulatory authorities in each state where test burns would occur would be notified of the proposed project prior to any test burn activity. Operations at the three utility sites during the full-scale test burns would be almost identical to current operations, and negligible environmental impacts are anticipated.

ALTERNATIVES CONSIDERED: In addition to the proposed action, the no action alternative was considered. Under the No Action alternative, DOE would not provide cost-shared funding for the "Self-Scrubbing Coal™: An Integrated Approach to Clean Air" proposed demonstration project. The industrial participant might elect to complete the project without DOE participation or, more likely, cancel the project. If CCI were to proceed with the demonstration project absent DOE participation, the potential impacts would be the same as for the proposed action. Project cancellation would result in the project not contributing to the objective of the CCT program, which is to make a number of advanced, more efficient, economically feasible, and environmentally acceptable coal technologies available to the U.S. energy marketplace. If the CCI process is not demonstrated, it is unlikely that utilities will choose this coal cleaning method to fulfill CAAA regulatory requirements. Alternative technologies and alternative sites were discussed in the EA, and eliminated from further consideration.

PUBLIC AVAILABILITY: Copies of the final EA and FONSI will be distributed to all persons and agencies known to be interested in or affected by the proposed action or alternatives, including appropriate agencies within the States of Pennsylvania, Indiana, and Ohio. Additional copies of the final EA and FONSI are available upon request from the Pittsburgh Energy Technology Center at the address given above.

DETERMINATION: The proposed Federal action, to provide cost-shared financial assistance for a demonstration project involving the construction and operation of a coal preparation plant using an advanced coal cleaning technology to produce cleaned coal, including the firing of the cleaned coal in full-scale test burns, does not constitute a major Federal action that would significantly affect the quality of the human environment within the meaning of the National Environmental Policy Act. This conclusion is based on the information and analysis in the EA. Therefore, an Environmental Impact Statement is not required and DOE is issuing this FONSI.

ISSUED IN WASHINGTON, D.C., this 14th day of February, 1994.

for Tara O'Toole, M.D., M.P.H.
Assistant Secretary
Environment, Safety and Health

DATE

FILMED

7 / 8 / 94

END