AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100

Silver Spring, Maryland 20910

301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 1

HW-77125

SERIES AND COPY NO.

DATE
May 6, 1963

HANFORD TECHNICAL RECORD

HANFORD ATOMIC PRODUCTS OPERATION - RICHLAND, WASHINGTON

X

X **RESTRICTED DATA**
THIS DOCUMENT CONTAINS RESTRICTED DATA
TRANSMITTED IN THE ATOMIC ENERGY ACT
CONTENTS IN SUCH A MANNER TO AN UNAUTHORIZED
PERSON IS PROHIBITED.

TITLE

Phase III - B Plant Operations

1

OTHER OFFICIAL CLASSIFIED INFORMATION

THIS MATERIAL CONTAINS INFORMATION AFFECTING THE NATIONAL DEFENSE OF THE UNITED STATES WITHIN THE MEANING OF THE ESPIONAGE LAWS, TITLE 18, U. S. C. , SECS. 793 AND 794, THE TRANSMISSION OR REVELATION OF WHICH IN ANY MANNER TO AN UNAUTHORIZED PERSON IS PROHIBITED BY LAW.

AUTHOR

J. E. McDonald

ISSUING FILE

RECEIVED 300 AREA

MAY 7 1968

THIS DOCUMENT IS NOT TO BE LEFT UNATTENDED OR IN THE POSSESSION OF AN UNAUTHORIZED PERSON WHO MAY HAVE ACCESS TO IT. WHEN IN USE, IT MUST BE STORED IN AN APPROVED LOCKED REPOSITORY OR IN AN APPROVED GUARDED AREA. WHILE IT IS YOUR RESPONSIBILITY AND UNTIL YOU HAVE OBTAINED A SIGNED RECEIPT FROM THE ISSUING OFFICE, IT IS YOUR RESPONSIBILITY TO KEEP IT AND ITS CONTENTS WITHIN THE LIMITS OF THE PROJECT AND FROM ANY UNAUTHORIZED PERSON. ITS TRANSFER, LOAN, AND STORAGE AT YOUR RESIDENCE IS PROHIBITED. IT IS NOT TO BE DUPLICATED. IF ADDITIONAL COPIES ARE REQUIRED, OBTAIN THEM FROM THE ISSUING OFFICE. ALL PERSONS READING THIS DOCUMENT MUST BE REQUESTED TO SIGN IN THE SPACE PROVIDED BELOW.

[illegible]

54-3000-340 (3-57)

AEC-95 RICHLAND, WASH

(CLASSIFICATION)

DECLASSIFIED

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DECLASSIFIED

HW-77125

Page 1

This document consists of
8 pages. No. 1 of
18 copies.

PHASE III - B PLANT OPERATIONS

Distribution

Copy 1 - J. M. Blackburn
2 - J. B. Fecht
3 - W. S. Frank
4 - K. G. Grimm
5 - B. F. Judson
6 - J. E. McDonald
7 - P. R. McMurray
8 - L. R. Michels
9 - P. H. Reinker
10 - H. P. Shaw
11 - O. V. Smiset
12 - R. E. Smith
13 - S. G. Smolen
14 - R. E. Tomlinson
15 - A. J. Waligura
16 - J. H. Warren
17 - Records Center
18 - 300 File

Classification Cancelled and Changed To

DECLASSIFIED

By Authority of D. S. Lewis

CG-PR-2, 3-18-94

By J. E. Sperry 3-30-94

Verified By DK Hanson 4-4-94

ATA

This document contains restricted information
under the Atomic Energy Act of
1954. Its disclosure to an unauthorized person is prohibited.

Financial Operation
JE McDonald:jwm
May 6, 1963

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DECLASSIFIED

DECLASSIFIEDPHASE III - B PLANT OPERATIONSINTRODUCTION

The completion of Phase III construction in B Plant will provide facilities to meet certain common needs of departmental Waste Management and Fission Product programs. This is an estimate of the total and unit costs of operation in these facilities on a "going concern" basis, recognizing full well the highly tentative nature of information available with respect to staffing, process rates, equipment, etc., approximately 3 to 4 years in advance of operations. It is planned that this document serve as an operating cost guideline during the interim period, subject to periodic revision as more firm data of significant cost impact becomes available.

SCOPE OF COSTS

This review covers those functions performed within B Plant proper plus a PAW feed material preparation function tentatively planned for Purex head end for convenience purposes. Feed material streams from supernatant and sludge removal functions are considered F.O.B. B Plant. No staffing or costs have been included for tank farm activities or the 200 North storage function. Cesium and strontium costs include processing to a solid and packaging in a high integrity container compatible with final confinement requirements. Staffing is provided to perform a peroxyacetate strike or similar function for the cerium-rare earth fraction, but additional study would be necessary to develop unit costs of particular isotopes involved.

COST DISTRIBUTION

B Plant processing costs have been allocated to four segments of common costing interest to both the Waste Management and Fission Products programs as follows:

1. Strontium-90
2. Cesium-137
3. A fraction containing cerium and rare earths
4. Residue which includes the balance of feed material streams and represents approximately 99% of total volume.

DECLASSIFIED

HW-77125

Page 3.

These four segments have been treated as joint products and full-costed accordingly. The intent of this accounting treatment is to give full recognition to the planned confinement and/or marketing programs for both the long- and short-lived fractions making up the gross feed material streams and thereby minimize the potential for bias which could adversely influence the marketing versus confinement relationship. For example, in-tank solidification plans assume removal of relatively long-lived isotopes from the bulk of the volume, so that the short-lived bulk may be immobilized in existing tanks. Likewise, final confinement and/or marketing plans for long-lived isotopes assume their extraction and segregation from the short-lived fractions. Costs involved in performing this type function have been considered joint costs and apportioned accordingly. Further processing of the cerium-rare earth fraction or the residue fraction to isolate a specific fission product, would require further study to develop unit costs of the product involved.

No attempt has been made to distribute costs to either the Waste Management or Fission Product programs. An informal proposal has been submitted to the Commission, which would result in booking B Plant costs to inventory in their entirety. These values would then be the asset base for billing quantities marketed or the base for amortizing the cost to Hanford operations benefitting from the confinement process, at rates based on half-life decay.

COST SUMMARY

During the period commencing with 1967, when B Plant is processing material from both stored and currently generated sources, it is estimated that canned cesium-137 glass can be produced at 5 to 6 cents per curie and strontium-90 at 7 to 8 cents per curie (F.O.B. B Plant), based on annual production rates of 36.0 megacuries and 33.6 megacuries respectively. After stored feed is exhausted, it is quite likely that the unit cost of these two products will increase appreciably as a result of the decreased production. Schedules that follow present the details of these calculations.

DECLASSIFIED

HW-77125

Page 4.

PHASE III - B PLANT OPERATIONS
TOTAL COST, UNIT COST, AND PRODUCTION SUMMARY

	<u>Cesium</u>	<u>Strontium</u>	<u>Cerium & Rare Earths</u>	<u>Residue</u>	<u>Total</u>
<u>Total Cost</u> (dollars in thousands)					
Manufacturing Cost	\$ 993	\$1 307	\$390	\$211	\$2 901
Overhead	397	523	156	84	1 160
Process Technology	<u>57</u>	<u>66</u>	<u>24</u>	<u>13</u>	<u>160</u>
Total Fund Cost	1 447	1 896	570	308	4 221
Depreciation	<u>426</u>	<u>547</u>	<u>158</u>	<u>85</u>	<u>1 216</u>
Total Cost	<u>\$1 873</u>	<u>\$2 443</u>	<u>\$728</u>	<u>\$393</u>	<u>\$5 437</u>
<u>Assumed Production*</u>	36.0 Mc	33.6 Mc			
<u>Unit Cost/Curie (in dollars)</u>					
Fund Cost	\$.040	\$.056			
Depreciation Cost	<u>.012</u>	<u>.017</u>			
Total Unit Cost	<u>\$.052</u>	<u>\$.073</u>			

* Calculation of Output in Curies

	<u>Megacuries</u>
Cesium: 7,600 tons, 120 days from reactor discharge at 1979 curies per ton**	15.0
13,200 tons equivalent of supernatant, 5 year average from reactor discharge at 1776 curies per ton**	<u>23.0</u>
Total available	<u>38.0</u>
Assumed Recovery (95%)	<u>36.0</u>
Strontium: 7,600 tons, 120 days from reactor discharge at 1828 curies per ton**	13.9
13,200 tons equivalent of sludge, 5 year average from reactor discharge at 1628 curies per ton**	<u>21.5</u>
Total available	<u>35.4</u>
Assumed Recovery (95%)	<u>33.6</u>

** HW-75978 - Fission Product Generation and Decay Calculations (p. 30-31),
H. H. Van Tuy1, (December 12, 1962).

B PLANT OPERATIONS
COST SUMMARY AND DISTRIBUTION

Dry ble lies	Total				Manufacturing Cost Distribution			
	Analytical	Maintenance	Utilities	Mfg. Cost	Cs	Sr	Ce & Re	Residue
2	\$ 26	\$ 90	\$ 3	\$ 269	\$	\$	\$	\$
5	13	45	2	140				
3	<u>39</u>	<u>135</u>	<u>5</u>	<u>409</u>	<u>164</u>	<u>164</u>	<u>41</u>	<u>40</u>
5	13	45	13	186	186			
5	52	180	59	1 068	171	672	150	75
5	13	45		138	14	14	14	96
6	13	45	5	143	48	48	47	
6	65	180	10	743	372	371		
6	13	45		138			138	
8	<u>91</u>	<u>270</u>	<u>15</u>	<u>1 024</u>	<u>420</u>	<u>419</u>	<u>185</u>	—
4	—	<u>30</u>	<u>5</u>	<u>76</u>	<u>38</u>	<u>38</u>	—	—
7	<u>\$208</u>	<u>\$705</u>	<u>\$97</u>	<u>\$2 901</u>	<u>\$993</u>	<u>\$1 307</u>	<u>\$390</u>	<u>\$211</u>

phases. It is not expected that the operating cost impact of performing
nt, should it become necessary to do so.

DECLASSIFIED

DECLASSIFIED

HW-77125

Page 6.

PHASE III - B PLANT OPERATIONS STAFFING REQUIREMENTS

	<u>Operations</u>		<u>Labor-</u>	<u>Mainte-</u>	<u>Process</u>	(2)	
	<u>Direct</u>	<u>Pro-(1)</u>	<u>atory</u>	<u>nance</u>	<u>Tech.</u>	<u>Other</u>	
	<u>Direct</u>	<u>rated</u>	<u>Direct</u>	<u>Direct</u>	<u>Direct</u>	<u>Prorated</u>	<u>Total</u>
<u>Receiving & Feed Mtl. Storage</u>							
B Plant	8	7	2	6	1	2	26
Purex Head End	<u>4</u>	<u>4</u>	<u>1</u>	<u>3</u>	<u>—</u>	<u>1</u>	<u>13</u>
	12	11	3	9	1	3	39
<u>Cesium Separation (Supernatant)</u>	4	4	1	3	1	1	14
<u>Solvent Extraction</u>	16	15	4	12	2	4	53
<u>Process Residue Handling</u>	4	4	1	3	1	1	14
<u>Storage-Packaging</u>							
Isotope Storage	4	4	1	3		1	13
Packaging	16	16	5	12	1	4	54
Peroxyacetate Strike	<u>4</u>	<u>4</u>	<u>1</u>	<u>3</u>	<u>1</u>	<u>1</u>	<u>14</u>
	24	24	7	18	2	6	81
<u>Load Out</u>	<u>2</u>	<u>2</u>	<u>—</u>	<u>2</u>	<u>1</u>	<u>1</u>	<u>8</u>
Total	<u>62</u>	<u>60</u>	<u>16</u>	<u>47</u>	<u>8</u>	<u>16</u>	<u>209</u>

- (1) Direct operations personnel are operators only while operations prorated personnel include the following:

Power Operators	4
Radiation Monitors	20
Crane Operators	4
Dispatchers	4
Samplers	8
Relief, Day Shift	6
Processing Supervisor	4
Supervisor - Operation Services	4
Analyst, Processing	1
Specialist, Processing	1
Specialist, Reports & Personnel	1
Clerical	2
Janitor	<u>1</u>
Total	<u>60</u>

- (2) Other prorated manpower includes administrative and supervisory personnel included in Laboratory, Maintenance, and Process Technology liquidating rates.

DECLASSIFIED

HW-77125

Page 7.

PHASE III - B PLANT OPERATIONS
ESSENTIAL MATERIALS AND CONTAINERS COST SUMMARY

	<u>\$/Ton</u>	<u>\$/Year</u>	<u>\$/Total</u>
<u>Containers</u>			\$168 000
<u>Essential Materials</u>			
Current Waste	\$15.00	\$114 000	
Sludge	26.60	352 000	
Purex Supernatant	2.30	23 000	
Redox Supernatant	3.80	<u>12 000</u>	
Total			501 000
<u>Steam - Product Concentration</u>			
Current Waste	0.85	6 400	
Sludge	0.85	11 300	
Purex Supernatant	0.70	7 100	
Redox Supernatant	1.15	<u>3 600</u>	
Total			28 400
<u>Steam-Waste Concentration</u>			
Sludge	1.18	15 600	
Purex Supernatant	0.75	7 500	
Redox Supernatant	1.25	<u>4 000</u>	
Total			<u>27 100</u>
<u>Total Essential Materials and Containers</u>			<u>\$724 500</u>

Assumptions Used:

- 1) Stored sludge and supernatant feeds will be processed through B Plant at a rate of 13,200 ton equivalents each, per year.
- 2) Currently generated PAW feed is assumed to amount to 7,600 tons per year.
- 3) Containers will hold the equivalent of 0.5 megacuries of strontium, cesium or a mixture thereof, at a cost of \$1,000 per annular-type container.

DECLASSIFIED

HW-77125

Page 8.

PHASE III - B PLANT OPERATIONS
ANNUAL DEPRECIATION COST

(dollars in thousands)	<u>First Cost</u>	<u>Annual Rate %</u>	<u>Annual Depreciation</u>
Building and Structures	\$ 9 185	2.01%	\$ 184
Equipment	8 965	4.11	369
Project Capital Cost	6 800	4.11	280
Common Facilities			<u>383</u>
Total	<u>\$24 950*</u>		<u>\$1 216</u>

Depreciation Cost Distribution

Cesium	\$ 426
Strontium	547
Cerium and Rare Earths	158
Residue	<u>85</u>
Total	<u>\$1 216</u>

* Asset values shown represent basically the first cost of B Plant proper plus that portion of Phase I, II, and III projects which will be capitalized. No values have been included for such items as underground lines between East and West areas. Annual depreciation has been calculated at standard service life rates.

CPD General Accounting is currently formalizing asset values and rates. Annual depreciation should not exceed the above amount.

DATE

FILMED

7/21/94

END