RECEIVED
MAR 19 1993
OSTI

**Cover Sheet for a Hanford
Historical Document
Released for Public Availability**

Released 1993

**Prepared for the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830**

**Pacific Northwest Laboratory
Operated for the U.S. Department of Energy
by Battelle Memorial Institute**

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This is a **historical document** that is being released for public availability. This was made from the best available copy. Neither the United States Government nor any agency thereof, nor Battelle Memorial Institute, nor any of their employees, makes **any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.** The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PRELIMINARY EVALUATION OF THE GASEOUS
EFFLUENT SAMPLING SYSTEM AT THE
296-A-12 STACK, 244-AR VAULT VESSEL VENT

by

J. A. Glissmeyer
L. C. Schwendiman

February 1977

Battelle
Pacific Northwest Laboratories
Richland, Washington 99352

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

CONTENTS

1.0 INTRODUCTION	1
2.0 SUMMARY	1
3.0 DESCRIPTION OF SAMPLING SYSTEM	2
3.1 SAMPLE COLLECTION	2
3.2 SAMPLE MONITORING	9
4.0 PRELIMINARY EVALUATION	9
4.1 SAMPLE COLLECTION SYSTEM OPERATION	9
4.2 SAMPLE ALIQUOT SELECTION	11
4.3 SAMPLE COLLECTION SYSTEM PERFORMANCE	13
4.4 EVALUATION OF MONITORING SYSTEM	13
5.0 CONCLUSIONS	15
6.0 RECOMMENDATIONS FOR CORRECTIVE ACTION	16
NOMENCLATURE	20
REFERENCES	21
APPENDIX A - RADIOACTIVE GASEOUS DISCHARGES, TANK FARMS, ARH 222-2.3.12	A-1
APPENDIX B - INTERIM RADIOACTIVE GASEOUS EFFLUENT SAMPLING AND MONITORING CRITERIA FOR ATLANTIC RICHFIELD HANFORD COMPANY FACILITIES, ARH-CH-498	B-1

PRELIMINARY EVALUATION OF THE GASEOUS EFFLUENT
SAMPLING SYSTEM AT THE 296-A-12 STACK,
244-AR VAULT VESSEL VENT

1.0 INTRODUCTION

This evaluation of the 296-A-12 stack sampling system is part of a larger study, sponsored by ARCHO and conducted by Battelle-Northwest, of gaseous effluent sampling systems in ARHCO facilities. The objectives of this study are:

- Evaluate the compliance of the existing effluent particulate sampling system with ARHCO's Interim Criteria for such systems by using sampling theory and radioactivity counting statistics,
- Make recommendations for corrective action which will lead to a particulate sampling system in compliance with the Interim Criteria.

This study is considered preliminary because no experiments have been conducted to verify the sampling system's performance.

The following report includes a brief summary, a detailed description and evaluation of the sampling system, conclusions about satisfactory or deficient areas of the sampling system and recommendations for corrective action. The appendices contain a copy of the Interim Criteria and the applicable ARHCO Emergency Procedure for radioactive gaseous discharges.

2.0 SUMMARY

The airborne radioactive particulate effluent sampling system for the 244-AR Vault Vessel Vent has been evaluated for compliance with both ARHCO's Interim Criteria for such systems and other good sampling practices. The evaluation is not based on experimental findings but rather on observations of the system, sampling theory and radioactivity counting

statistics. The existing sampling system has several deficiencies which are listed in the Conclusions. Among these are poor sampling probe location, long and complicated sample piping, unsatisfactory flowrate measurement, insufficiently characterized monitoring instrumentation, moisture condensation and a probe of unknown configuration. Extensive recommendations were given outlining the design effort for a replacement sampling system. Some of these recommendations included characterizing the effluent, moving the sampling probe to the stack and designing separate inventory and monitor sampling systems. Some recommendations for interim improvements were made such as installing new flowmeter instrumentation and reducing sample transport piping. Although many of the recommendations are specific for the facility in question, others are generally applicable to many of the sampling systems studied as part of this program.

3.0 DESCRIPTION OF SAMPLING SYSTEM

The gaseous effluent from the vessel vent system for the 244-AR Vault is discharged through the 296-A-12 stack.⁽¹⁾ The radioactive particulates most likely to be found in the effluent are cesium-137, antimony-125 and strontium-90.⁽³⁾ Before discharge to the stack the effluent has passed through a prefilter, a heater to prevent condensation and HEPA filters as diagrammed in Figure 1. The effluent temperature is approximately 55-65°C at the outlet of the HEPA filters and may be about 50°C at the stack.⁽²⁾ The airflow through the 8-in. schedule 40 stainless steel inner stack is about 560 CFM⁽⁴⁾ at effluent conditions. The effluent particulate sampling system consists of the sample collection and sample monitoring components to be described.

3.1 SAMPLE COLLECTION

A sample of the 296-A-12 stack effluent is continuously extracted from the 8-in. horizontal duct (7.981 in. ID) between the fan and the stack as shown in Figures 2 and 3. The interior of the sampler enclosure is shown in Figure 4 and the sample collection system is diagrammed in Figure 5.

FIGURE 1. Diagram of 244-AR Vault Vessel Vent System⁽¹⁾

FIGURE 2. Photograph of 296-A-12 Stack and Exhaust System Components.
PNL Neg. No. 7610920-1.

FIGURE 3. Photograph Showing Sampling Point, Enclosure and Ductwork.
PNL Neg. No. 7610920-7.

FIGURE 4. Photograph of Interior of Sampler Enclosure.
PNL Neg. No. 7610920-8.

FIGURE 5. Diagram of Existing Sampling System

The sample airstream is extracted through a probe of unknown configuration. None of the existing engineering drawings^(5,6,7) nor any of the personnel consulted could shed any light on this detail. From the probe the air sample passes through a length of rubber-insulated and heat-traced stainless steel tubing to the sampler enclosure. Once inside the enclosure the air sample is transported through more stainless steel tubing, a ball valve and plastic tubing to the collector/detector⁽⁸⁾. The particulates are filtered from the airstream by a 47 mm diameter asbestos fiber filter paper (Hollingsworth and Vose, HV-70) in the collector/detector. The filtered sample air is then piped to the stack via piping which, according to the original design,^(2,5) was intended to serve as sample transport piping from a probe in the stack to the enclosure. Table 1 lists the known piping that the sample passes through.

TABLE 1. Sampler Piping, Excluding Probe

Two	90° Bends	@ 6 in. radius	0.37 in. ID
One	90° Bend	@ 10 in. radius	0.37 in. ID
Four	90° Bends	@ 6 in. radius	0.376 in. ID
12 in.	Horizontal		0.37 in. ID
8 in.	Vertical		0.37 in. ID

The air sample flowrate is unknown but is assumed by ARHCO to be 2 CFM (unspecified gas conditions). There is a flowmeter installed between the collector/detector and the vacuum pump and the flowrate reads 3 SCFM. However, the existing flowmeter installation is inadequate for proper flow indication.

According to the ARHCO Emergency Procedure for loss of electricity at the 244-AR Vault,⁽⁹⁾ emergency electrical power to the 296-A-12 stack sampling system is provided by the same system supplying the vessel vent exhaust fan. Therefore, if there is an electrical power failure the ventilation system will function and an effluent sample will be obtained and monitored. Also, failure of the sampler vacuum pump is indicated by an alarm light in the 244-AR service building.

3.2 SAMPLE MONITORING

The collected particulates are continuously monitored for beta-gamma emitting particles. The collected sample is changed once each week-day and is sent to the 222-S Building Air Sample Counting Room for analysis of total beta and alpha emitters according to the procedures in References 10 and 11. Total emission limits are set in the ARHCO Emergency Procedure for radioactive gaseous discharges (see Appendix A).

The monitoring system is diagrammed in Figure 6 and is similar to the monitoring system at the 296-A-17 stack (A, AX, AY Tank Farm).⁽¹²⁾ The detector is a mica window GM tube housed in the collector/detector. The signal is amplified and discriminated to reduce the background. The counts per second are displayed on the count rate meter and on the recorder. Count rate ranges have maxima from 10 to 100,000 c/sec and the count rate meter is normally set on the 0-10 c/sec range. The high level release alarm light is actuated by the recorder when the count rate is 85% of full scale or 8.5 c/sec as presently set. The counting efficiency of the detector has not been determined but should be about 5%. The instrumentation response is checked on a monthly basis. There is no instrumentation malfunction alarm provided but all of the instrumentation except the detector is located in the continuously occupied service area of the 244-AR Vault.

4.0 PRELIMINARY EVALUATION

This preliminary evaluation of the 296-A-12 stack sampling system will focus on the areas considered deficient in light of ARHCO's Interim Criteria for Gaseous Effluent Sampling. Because these criteria will be referred to frequently, a copy is included in Appendix B. The portions of the sampling system considered satisfactory will be listed later in the conclusion.

4.1 SAMPLE COLLECTION SYSTEM OPERATION

A major deficiency in the sample collection system is that there is no inventory sample collected separately from the present monitor sample. The

FIGURE 6. Block Diagram of Stack Sampler Monitoring System

monitor sample does not function well for inventory or quantitative sampling because there is significant particulate deposition inherent in the collector/detector geometry.⁽¹³⁾

Another operational deficiency is the unknown sample flowrate caused by improper use of the flowmeter. The flowmeter is mounted on an angle rather than level and there is significant rust on the float and float guide. This inhibits the free motion of the float and changes the flowmeter characteristics. Also, the flowmeter is used under conditions different than it was calibrated for, i.e., clean air at 70°F and 29.92 in. Hg. There is also no vacuum pressure or temperature instrumentation that will allow correcting the flowmeter readings for the actual conditions.

Finally, there is a significant problem of condensation in the sample transport tubing. Air sample filters are frequently found to be wet with condensation. The existing heat tracing is not adequate to keep the sample airstream above the effluent dewpoint; however, the effluent is quite humid and the dewpoint may be rather high. The actual effluent humidity should be investigated.

4.2 SAMPLE ALIQUOT SELECTION

Whether or not the extracted sample is representative of the effluent depends in part on the location of the sampling probe. Although the sampling probe configuration is unknown, it is unlikely that the extracted sample is representative because the extraction location is too close to major airflow disturbances. The convergence of two horizontal ducts, the condensate collector and the stack inlet are all within two duct diameters of the sampling location. The airflow is not likely to be well developed and stable at that point.

The size of the sample aliquot is unknown because of the uncertainty of the flowrate measurement. The Interim Criteria (Sampling Criterion

No. 1) indicates that when an average ^{90}Sr concentration of $3 \times 10^{-11} \mu\text{Ci/ml}^*$ occurs during a 24-hr period that the collected sample must contain sufficient activity for an appropriately accurate determination of the release. Let us assume that a sample counting accuracy of $\pm 10\%$, 95% confidence level is appropriate and that the collected sample is ideally representative. The current counting room method for calculating release concentration is⁽¹¹⁾

$$\begin{aligned} \frac{\mu\text{Ci}}{\text{ml}} = & \text{net } \frac{\text{c}}{\text{min}} \times \frac{\text{d}^{**}}{0.383\text{c}} \times \frac{\text{min}}{\text{sample flowrate, ft}^3} \times \frac{\text{ft}^3}{28,320\text{ml}} \\ & \times \frac{1}{0.7^\dagger} \times \frac{\mu\text{Ci-min}}{2.22(10^6)\text{d}} \times \frac{1}{1440\text{min}^{\dagger\dagger}} \end{aligned} \quad (1)$$

The accuracy of the sample analysis at the 95% confidence level is established by Equation 2.

$$\pm \text{Interval} = 1.96 \sqrt{\frac{\text{net c/min} + \text{background c/min}}{\text{sample counting time, min}} + \frac{\text{background c/min}}{\text{background counting time, min}}} \quad (2)$$

Assuming an average beta counting background of 15 c/min and a one minute counting time, a net count of 400 c/min is required for a $\pm 10\%$ accuracy. Rearranging Equation 1 and substituting the 400 c/min and the $3(10^{-11}) \mu\text{Ci/ml}$ concentration into the calculation yields a minimum sample flowrate of at least 0.55 CFM (at stack conditions) to measure that concentration assuming the sample is ideally representative. If the sample flowrate were known to be above 0.55 CFM, then the size of the sample aliquot would satisfy the criterion.

* Here the volume units are assumed to be in terms of effluent conditions, i.e., approximately 50°C and 29.92 in. Hg. This concentration limit is the most restrictive "Table II"⁽¹⁴⁾ limit for the expected radionuclides. This limit is more restrictive than $1/2 \times$ Class I Action Level of the Emergency Procedure (Appendix A) which, when expressed as a concentration, is only $3(10^{-9}) \mu\text{Ci/ml}$.

** The counting efficiency for total beta is 0.383 c/d.

† The estimated collection efficiency of the HV-70 filter is assumed to be 70%.

†† The duration of the sampling period is one day or 1440 min.

4.3 SAMPLE COLLECTION SYSTEM PERFORMANCE

As already pointed out, the particulate sample withdrawn from the 296-A-12 stack is not likely to be representative of the effluent because of the poor sampling location. The particulate sample ultimately reaching the collection filter is probably even less representative because of anisokinetic sampling and particle deposition in the tubing, valves and collector/detector. Because the details about the probe configuration, sample flowrate and gas conditions are not known no firm predictions can be made of the magnitudes of these other effects. Some calculations of particle deposition in the tubing using some assumed conditions may give a rough indication of the sample bias.

Let us assume a sample flowrate of 2 CFM at 50°C and atmospheric pressure. Calculated particulate penetration through the sampler tubing listed in Table 1 is shown in Table 2 (see Ref. 15 and 16 for calculational methods). The fractional deliveries of the particulates through the sample piping are shown for both monodispersed and polydispersed aerosols with geometric mean diameters as listed. Clearly, the many bends are the major contributors to particle deposition. Add to that the likely effects of anisokinetic sampling and particle deposition in the probe, valve and collector/detector, then the total delivery of the particulate sample is probably much less than the 90% of particles 10 μm AED and smaller that is required by Sampling Criterion 2 (see Appendix B).

TABLE 2. Fractional Delivery of Aerosols Through Sample Transport Piping

Particle Size, μm AED	Monodispersed Aerosols			Polydispersed Aerosols	
	Vertical Lines	Horizontal Lines	Bends	Total System	Total System
0.5	1.00	1.00	.99	.99	.94
1	1.00	1.00	.94	.94	.82
2	1.00	1.00	.79	.79	.63
5	.99	.98	.24	.23	.36
8	.96	.94	.02	.02	.24
10	.94	.91	.003	.003	.19

* AED refers to aerodynamic equivalent diameter, i.e., the diameter of a sphere with density 1g/cm^3 .

4.4 EVALUATION OF MONITORING SYSTEM

The present sample monitoring system appears adequate although some of its important characteristics are unknown. The beta-gamma detector is satisfactory for the expected radionuclides; however, because the counting efficiency, energy discrimination level, usual background and sample flow-rate are unknown it is difficult to assess if the signals from the decay of the radionuclides of interest are monitored and if the instrumentation is sensitive enough to detect release levels of interest. A rough evaluation of the sensitivity and range of the instrumentation can be made based upon the assumptions of 5% counting efficiency and a sample flowrate of 2 CFM (effluent conditions).

The Monitoring Criteria require that the samples collected at release levels of one-half and one hundred times Class I, II Action Levels (see Appendix A, Monitoring Criteria Nos. 1 and 11) be within the range of the monitoring instrumentation.* The release level concentration consistent with the Class I, II Action Levels is

$$\begin{aligned} \text{Conc } \frac{\mu\text{Ci}}{\text{ml}} &= \frac{\text{Limit, } 0.01 \text{ Ci}}{\text{wk}} \times \frac{\text{wk}}{10,080 \text{ min.}} \times \frac{10^6 \mu\text{Ci}}{\text{Ci}} \times \frac{\text{min}}{560 \text{ ft}^3} \times \frac{\text{ft}^3}{28,320 \text{ ml}} \times \frac{1}{10} \\ &= 6.26 (10^{-9}) \mu\text{Ci/ml} \end{aligned} \quad (3)$$

where the effluent flowrate, 560 CFM, and the concentration are measured at the previously mentioned effluent conditions (p. 2). During a 24-hr average release of $6.26(10^{-9}) \mu\text{Ci/ml}$ the c/sec collected on the sample are

* Both Class I and II Action Levels are concerned with measuring the same daily release levels. The only difference is that for a Class I Action the release is exceeded for only one day and for a Class II Action the daily release is exceeded two days in a row.

$$\begin{aligned} \text{Class I, II} \\ \text{Collected c/sec} &= \frac{6.26(10^{-9})\mu\text{Ci}}{\text{ml}} \times \frac{2 \text{ ft}^3}{\text{min}} \times 1440 \text{ min} \times \frac{28,320 \text{ ml}}{\text{ft}^3} \\ &\times \frac{2.22(10^6)\text{d}}{\mu\text{Ci-min}} \times \frac{0.05 \text{ c}}{\text{d}} \times \frac{\text{min}}{60 \text{ sec}} \end{aligned} \quad (4)$$

$$= 944 \text{ c/sec}$$

assuming the 5% counting efficiency, an ideal sample and a 2 CFM sample flowrate. Therefore, the material collected during releases one-half or one hundred times the Class I, II Action Levels are 472 c/sec and 94,400 c/sec respectively. Both of these are within the count rate range of the instrumentation and are probably well above background. If the alarm is sounded at the level specified in the Monitoring Criterion No. 7 then the alarm actuation point would be 944 c/sec rather than the current 8.5 c/sec. Presently the alarm is actuated when the average daily release concentration is only $5.63(10^{-11}) \mu\text{Ci/ml}$ assuming the same conditions as in Equation 4. The existing monitoring instrumentation probably has sufficient sensitivity and range but this should be confirmed once more information about the system is known.

5.0 CONCLUSIONS

The following is a list of conclusions reached as a result of this preliminary evaluation of the 296-A-12 stack sampling system.

1. There is no provision for separate inventory and monitor sampling as required by Sampling Criterion No. 5.
2. The collected radioactive particulate samples are not likely to be representative of the effluent because of the poor sampling location, particle deposition and condensation in the sampler piping. A good estimate of the bias in the collected samples could not be given because the configuration of the sampling probe and the sample flowrate were not known; however, the sample collection system probably performs very poorly.

3. The provisions for measuring sample flowrate and preventing moisture condensation in the sampling system are unsatisfactory.
4. There are no visual or audible alarms of monitoring instrumentation malfunctions. The existing high level release and loss of vacuum alarms are not audible, but are visual only. Alarms are located in a continuously occupied area.
5. The monitoring instrumentation is appropriate for the expected radionuclides. This instrumentation also appears to have adequate sensitivity and range; however, this cannot be confirmed until the detector efficiency, and sample flowrate are known.
6. The documentation of sampling system modifications and existing configuration is unsatisfactory.
7. The availability of emergency electrical power is satisfactory.

6.0 RECOMMENDATIONS FOR CORRECTIVE ACTION

The following is a list of recommendations which, if implemented, should result in a sampling system which will comply with the Interim Criteria. A new sampling system needs to be designed. The following should be elements of that design or must be considered before proceeding with the design work. Many of the recommendations are generally applicable to any sampling system and the reader will notice that some of them are taken verbatim from earlier reports.⁽¹⁷⁾

1. The new sampling program should include separate inventory and monitor sample collection systems.
2. Both sample collection systems will need new probes with knife edged nozzles which will sample isokinetically with a net sample flowrate in the 2-10 SCFM range. The probes should be installed at least ten stack diameters downstream and five stack diameters upstream of significant flow disturbances. The original stack penetration designed for effluent sampling is nearly 80 in. above the transition into the stack and may provide a suitable location

for one of the sampling systems.⁽²⁾ This should be verified by a velocity traverse at that level. If the velocity profile is not sufficiently well developed, a higher location on the stack or a flow straightener will be needed.

3. For the inventory system the sample collector should be in the stack or short coupled to it. For the monitor system the collector/detector should be short coupled to the stack. There should be no more than two bends or 180° of total bend in either system's delivery piping.
4. A new collector/detector design with significantly lower particle deposition is recommended as a valuable improvement for the monitor system. (ARHCO has already begun design work on an improved collector/detector.)
5. The effluent conditions should be better characterized before a sampling system design is finalized. The effluent dewpoint and temperature need to be determined to proceed with designing a thermostatically controlled heat trace for the sampler piping up to the collection filter. Consideration should be given to the practicality of heating the sampler piping above the dewpoint and the effect of the temperature on the detector component.
6. Provision should be made to periodically clean the sampling system piping to account for deposited radioactive particles.
7. Both sample collection systems must be properly instrumented for the measurement and control of sample flowrates. The temperature and pressure conditions for the measurement of effluent flowrate, sample flowrate and the calculation of releases must be defined and, when these sets of conditions differ, corrections must be applied to calculations and measurements. Commercially available mass flowmeters would be ideal for sample flow measurement and can be easily made part of a feedback control loop. If other flowmetering devices are used (e.g., rotameters) they should be properly instrumented to allow corrections to be made when they

are used in conditions different from the calibration conditions. Consideration should be given to flow totalizers such as gas meters or flowrate recorders.

8. Audible and visual alarms should be added to indicate monitoring instrumentation failure. The existing high level release and loss of vacuum visual alarms should be made audible as well.
9. The sensitivity and range of the monitoring instrumentation should be reevaluated when the sample flowrate, counting efficiency and other characteristics are obtained.
10. It is desirable to test sampling system performance and bias when suitable validation techniques become available.
11. The personnel authorized to make adjustments in the sampling system operations must be thoroughly trained in the system's operation and design features.
12. Define what constitutes appropriate accuracy for the measurement of releases required in Sampling Criterion No. 1. The size of the sample aliquot required for that accuracy should then be reevaluated as shown on Page 14.
13. The above recommendations require extensive design work. The following recommendations are for interim improvements to the existing sampling system:
 - a. properly mount a new flowmeter, with vacuum and temperature gauges, in the place of the existing flowmeter and provide a chart for correcting readings,
 - b. determine the dewpoint of the effluent and heat the sampler piping to the collector/detector to a temperature above the dewpoint,
 - c. consider moving the sampler enclosure so that the collector/detector is short coupled to the sampling probe,

- d. if that collector/detector relocation is not practical, then six of the bends in the sampler piping can be removed by rerouting the piping through a new hole in the enclosure and directly into the collector/detector.

NOMENCLATURE

AED - aerodynamic equivalent diameter
c - counts
CFM - cubic feet per minute at effluent conditions
Ci - curies
cm - centimeters
d - disintegrations
ft - feet
g - grams
hr - hour
ID - inside diameter
in - inch
in. Hg - inches of mercury pressure
min - minutes
ml - milliliter
mm - millimeter
SCFM - standard cubic feet per minute @ 70°F, 29.92 in. Hg
sec - seconds
wk - week
 μCi - micro (10^{-6}) curies
 μm - micro (10^{-6}) meters, microns

REFERENCES

1. Drawing SK-2-4152, "Title I, Plot Plan, Containment Vault and Piping", ARHCO Engineering Files.
2. Drawing H-2-62010, "Vessel Vent Stack, Elevation and Details", ARHCO Engineering Files.
3. G. D. Campbell, Private Communications, ARHCO (December, 1976).
4. J. H. Palmer, Private Communications, ARHCO (November, 1976).
5. Drawing H-2-62041, "Vessel and Vault Vent Stack, Radiation Monitor Installation and Details", ARHCO Engineering Files.
6. Drawing H-2-62098, "Miscellaneous Details", ARHCO Engineering Files.
7. Drawing H-2-34701, "Stack Sampling", ARHCO Engineering Files.
8. Drawing H-2-33904, "Stack Monitor-Air Sampler Assembly and Details", ARHCO Engineering Files.
9. 244-AR Vault Loss of Electricity, ARHCO Emergency Procedure, ARH-222-2.3.7.2, (January, 1975).
10. Emergency and Holiday Coverage of 222-S Counting Room, Technical Services Section, Laboratory Operations Procedure No. ECOVCR-01A, ARHCO, (October, 1973).
11. An Outline of Environmental Air Sample Analysis, ARH-869, ARHCO (October, 1968).
12. B. G. Powaukee, Private Communications, ARHCO (December, 1976).
13. L. C. Schwendiman, J. Mishima, J. A. Glissmeyer, Evaluation of the Sampling of Radioactive Particles in Gaseous Effluents-Monthly Progress Report, January, 1975, (February, 1975).
14. ERDA Manual Chapter 0524, "Standards for Radiation Protection," Appendix 0524, Annex A, (April, 1975).
15. L. C. Schwendiman, G. E. Stegen, J. Mishima, J. A. Glissmeyer, Interim Report: An Analysis of the Gaseous Effluent Sampling System - 225-B, Waste Encapsulation and Storage Facility, NWL-B-408, Battelle-Northwest, Richland, WA, (April, 1975).

16. L. C. Schwendiman, G. E. Stegen, J. A. Glissmeyer, "Methods and Aids for Assessing Particle Losses in Sampling Lines." BNWL-SA-5138, presented to the American Industrial Hygiene Association, Minneapolis, MN, 1975.
17. J. A. Glissmeyer, L. C. Schwendiman, Preliminary Evaluation of the Gaseous Effluent Sampling System at the 296-A-17 Stack - A, AX, AY, Tank Farm, Report to D. J. Carrell, ARHCO, by Battelle, Pacific Northwest Laboratories, Richland, WA, 99352, 1976.

APPENDIX A

RADIOACTIVE GASEOUS DISCHARGES, TANK FARMS, ARH 222-2.3.12

ISSUED BY THE MANAGER	SUBJECT	CLASSIFICATION
Tank Farm Operations	RADIOACTIVE GASEOUS DISCHARGES TANK FARMS	ARH-222
<p>A. <u>Introduction</u></p> <p>Gases discharged from the various Tank Farm stacks are monitored for radioactivity. Some of the emissions are measured and recorded continuously while others are monitored by periodic counts of air samples. Laboratory measurements are used for final determination and record all stack samples.</p> <p>Certain actions and notifications are required in the event of a significant discharge of radioactivity.</p> <p>B. <u>Gaseous Discharge-Radioactivity Level Determination</u></p> <p>First indication that a release of radioactive material to the atmosphere may have occurred will come from a monitoring instrument alarm or preliminary radiation instrument reading on a stack air sample.</p> <p>Operating supervision is to be notified at the first indication of an abnormal reading or alarm and will proceed to determine actions as outlined in section C, below.</p> <p>Table 1 and 2 attached provide some information to assist in preliminary evaluation of release levels.</p> <p>C. <u>Action Required</u></p> <p>1. <u>Supervisor's Responsibilities</u></p> <p>a. Upon receiving an alarm, the responsible supervisor will immediately notify radiation monitoring, then proceed to investigate or determine whether the alarm was due to high radioactivity or an instrument malfunction.</p> <p>b. The supervisor will request replacements of the air sample and an immediate count of the sample by radiation monitoring.</p>		
DATE ISSUED JUN 1 1976	SUPERSEDES ISSUE DATED 5-20-75	PAGE 1 of 6
		EMERGENCY PROCEDURE 2.3.12

EMERGENCY PROCEDURE

- c. The supervisor will notify his management if the alarm is found to be due to a radioactivity level that exceeds the levels described in section D, below.
- d. The supervisor will initiate an investigation to determine the source of radioactive emissions.
- e. The supervisor will keep management informed throughout the progress of his investigations. He will consult with management upon the course of action to resolve the problem. He will prepare a written report of the investigation and findings.

2. Radiation Monitoring Responsibilities

Radiation monitoring will provide assistance by changing air samples, counting samples and evaluating data.

3. Tank Farm Process Engineering

Operations Support Engineering will provide assistance as required during the investigation, isolation and resolution of problems.

4. Management Responsibilities

- a. Tank Farm Operations (TFO) management will provide guidance as required during the investigation, isolation and resolution of problems.
- b. The Manager, TFO will determine when environmental discharges warrant defining the situation as being in the emergency category.
- c. TFO Management will implement activities required of personnel under emergency conditions.
- d. The Manager, TFO will communicate all information to Departmental Management required under emergency conditions.

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
JUN 1 1976	5-20-75	2 OF 6	NO. 2.3.12

D. Situation Definitions and Action

1. Class I

Definition

Daily environmental discharge exceeds ten percent of the release level values specified in section 5 of Radiation Protection Standards and returns to less than ten percent within 48 hours. ARH-220 (see table 2, attached).

Action

Notify plant and department management. Investigate to determine the cause. Document investigation and conclusions.

2. Class II

Definition

Daily environmental discharge exceeds ten percent of the release level values in section 5 of Radiation Protection Standards for more than 48 hours.

Action

Notify plant, department and division management. Investigate to determine the cause. Document the investigation and conclusions.

3. Class III An Emergency

Definition

Environmental discharge exceeds the release level value in section 5 of Radiation Protection Standards.

Action

Notify plant, department, division management and the U. S. Energy Research and Development Administration. Promptly investigate to determine the cause and corrective action.

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
JUN 1 1976	5-20-75	3 OF 6	NO. 2.3.12

EMERGENCY PROCEDURE

4. Class IV An Emergency

Definition

Environmental discharge that exceeds ten times the release level values in section 5 of Radiation Protection Standards.

Action

Notify plant, department, division management and the U. S. Energy Research and Development Administration immediately. Investigate promptly to determine the cause and corrective actions. If control cannot be immediately established or the discharge has exceeded 100 times the release level values, the facility shall be shut down. Document the investigation and conclusions. Take positive action to prevent recurrence.

PREPARED BY J. P. Ferguson DATE 3-25-76

REVIEWED BY C. H. Hickey DATE 4-20-76
(TFO)

APPROVED BY B. J. Sammons DATE 5-18-76
(RMS)

APPROVED BY B. H. Hixon DATE 5-25-76
(MPP)

ISSUED BY J. P. Hixon DATE 1 June 76
(TFO)

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
JUN 1 1976	5-20-75	4 OF 6	NO. 2.3.12

TABLE I

CONVERSION FACTORS FOR
SELECTED TANK FARM STACKSCONVERSION FACTORS
for Ci emitted per sampling period

Stack Code Number	Ident.	Location	Filter Size in.	Sample Flow Rate Cu. Ft./Min	Stack Flow Rate Cu. Ft./Min	EGM Ci per c/m	P11 Probe Ci per c/m	CP Ci per Mrads/hr at contact	Alpha Ci per d/m
6	91-F	291-S	4"	3	40,000	6×10^{-7}	1.5×10^{-7}	4×10^{-4}	6.0×10^{-9}
52	ARCS	244-AR	2"	1	20,000	9×10^{-7}	2.3×10^{-7}	6×10^{-4}	9×10^{-9}
58	ARVVS	AR-Vessel	2"	1	380	1.8×10^{-8}	4.5×10^{-9}	1.2×10^{-5}	1.8×10^{-10}
59	702-A	AXFS	2"	1	6,900	3×10^{-7}	8×10^{-8}	2×10^{-4}	3×10^{-9}

A-6

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
Jul 1 1976	5-20-75	5 of 6	NO. 2.3.12

84-6000-086 (2-73)

TABLE 2

GASEOUS WASTES
 (Ref. ARH-220)

Gaseous radioactive wastes (mists or gases) shall be controlled so that the amounts released will be kept as small as practicable and should not average greater than the following amounts:

Radionuclide	AMOUNT IN CURIES PER WEEK	
	Released from 200-ft. Stack	Released from Shorter Stacks or Vents
^{90}Sr	0.1	0.01
^{131}I	0.03	0.003
Plutonium (total)	0.001	0.0001
Uranium (natural)	0.004	0.0004
Total of all others (excluding ^3H , ^{14}C , and noble gases)	0.5	0.05

In addition, the total amount of ^{131}I released from all 200 Area sources shall not exceed 1 curies per calendar quarter.

DATE ISSUED: JUN 1 1976	SUPERSEDES ISSUE DATED: 5-20-75	PAGE 6 OF 6	EMERGENCY PROCEDURE NO. 2.3.12
----------------------------	------------------------------------	----------------	-----------------------------------

APPENDIX B

INTERIM RADIOACTIVE GASEOUS EFFLUENT SAMPLING AND
MONITORING CRITERIA FOR ATLANTIC RICHFIELD HANFORD
COMPANY FACILITIES, ARH-CD-498

INTERIM RADIOACTIVE
GASEOUS EFFLUENT SAMPLING AND MONITORING CRITERIA
FOR ATLANTIC RICHFIELD HANFORD COMPANY FACILITIES

INTRODUCTION

To ensure that gaseous radioactive releases to the environment are kept as low as practicable, it is necessary to sample all of the radioactive or potentially radioactive gaseous effluent streams in the 200 Areas. Specific gaseous effluent streams that have the potential for release of large quantities of radioactive materials must also be monitored by radiation detection instrumentation.

The criteria listed below are intended to be used as guidelines to aid in the design of new systems or the upgrading of existing systems. It is highly desirable that new or upgraded systems be able to meet or nearly approach as many of the following criteria as is practicable.

SAMPLING CRITERIA

The term "sampling" applies to the extraction, transport and collection of a sample of the radionuclides present in the gaseous effluent stream on a collection media suitable for subsequent laboratory analysis. Gaseous effluent sampling systems shall:

1. extract in a 24-hour period a representative fraction of the effluent stream such that an activity release at least as low as the concentration guides given in ERDA Appendix 0524, Annex A, Table II can be measured with appropriate accuracy upon subsequent laboratory analysis.*
2. be designed, fabricated, and operated so that the particles extracted and transported to the collector will be representative to the degree that particles 10 micrometers and smaller in the sample collected will be at least 90 percent of the 10 micrometer and smaller particles in the same volume of a truly representative sample. At least 90 percent of the radioactive gases withdrawn shall be collected on the media selected or delivered to the activity sensing chamber in flow through monitors.
3. operate in a continuous mode, except for short periods when the sample collection media is being changed, whenever the facility is exhausting to the atmosphere.
4. extract samples of particles and gases that are a representative aliquot of the actual effluent stream.

* If one half of the Class I Action Level in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility) is less than the Table II concentration guides, use one half of the Class I Action Level from the appropriate Emergency Procedure as the basis for this criterion.

5. collect at least two samples, one of which will be designated and used exclusively as an inventory sample.
6. shall provide particulate and gaseous samples that have not been adversely affected by condensation of moisture.
7. be equipped with a vacuum system for sample extraction that has the same number of back-up power systems as the exhaust fans of the facility. The vacuum system shall be provided with an alarm that is activated upon the loss of vacuum.
8. provide an inventory sample which is an accurate aliquot, within a factor of two, of the absolute radioactive materials of the effluent stream. (Note: This statement relates only to the sample extraction and delivery capability, not to the accuracy of detection and measurement.)
9. provide inventory samples with less than 25 percent variation from the mean of several similar samplings at the 95 percent confidence level.
10. have at least an annual check to ensure that variation in effluent characteristics (particle size, mass activity concentrations, etc.) have not changed significantly.

MONITORING CRITERIA

The term "monitoring" applies to the use of radiation detection instrumentation to measure the amount of radioactivity collected by the collection media. Gaseous effluent monitoring systems shall:

1. monitor the samples collected (except for the designated inventory sample) as detailed in items 1-10 under Sampling Criteria. The monitoring system shall be able to detect an activity release at least as low as one half that required for the Class I Action Level listed in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
2. detect the radiation from radionuclides in the effluent stream with appropriate sensitivity for the radiation emitted.
3. operate in a continuous mode, except for short periods while samples are being changed, whenever the facility is exhausting to the atmosphere.
4. be equipped with the same number of back-up power systems as the exhaust fans of the facility.
5. incorporate a permanent recorder to document the level of radioactivity measured by the radiation detection instrument.

11/14/75
DJC:bac

6. be provided with a "fail-safe" system that alarms when a malfunction occurs in the radiation detection instrument or upon loss of vacuum.
7. alarm at a pre-set "trip" point that is consistent with a Class II Action Level as specified in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
8. be able to detect a Class II Action Level as specified in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility) in less than 24 hours.
9. alarm visually and audibly in a continuously occupied area for both the "fail-safe" alarm(s) and the emergency alarm(s).
10. be equipped with sufficient range to detect activity levels up to 100 times the Class II Action Level in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
11. have the radiation detection instrumentation calibrated on at least a quarterly basis.

END

DATE
FILMED

7 / 21 / 93