DOE/PC/89857--T7

DOE/PC/89857--T7

DE92 018509

**U.S. DEPARTMENT OF ENERGY
PITTSBURGH ENERGY TECHNOLOGY CENTER**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

**DIRECT COAL LIQUEFACTION
BASELINE DESIGN
AND
SYSTEM ANALYSIS**

CONTRACT NO. DEAC22 90PC89857

QUARTERLY REPORT

MAY - AUGUST, 1990

Received OSTI
JUL 24 1992

SEPTEMBER, 1990

PITTSBURGH, PENNSYLVANIA

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Bechtel

3000 Post Oak Boulevard
Houston, Texas 77056-6503
Mailing address: P.O. Box 2166
Houston, Texas 77252-2166

October 3, 1990

U. S. Department of Energy/PETC
P. O. Box 10940, Mail Stop 922-H
Pittsburgh, PA 15236

Attention: Mr. Swenam Lee
Project Manager

Subject: D.O.E. Direct Coal Liquefaction
Baseline Design & System Analysis
Contract No. DEAC22 90PC89857
Bechtel Job No. 20952
Quarterly Status Report
Letter No. BLD-022

Dear Mr. Lee:

Attached for your information are three copies of the subject Quarterly Status Report covering the May 16 through August 19, 1990 reporting period. Copies to other PETC members, as required by the contract are being separately and directly transmitted.

As you know, obtaining and reconciling design basis information from Wilsonville has been slow. This will in time have cost and schedule consequences. Fortunately, Amoco was able to step in and expedite this process.

As agreed in our kickoff meeting, this Quarterly Report is a technical status report covering the last three months of work. Thus, no schedule and/or budget status reports are included.

Note that this report does not contain any confidential information which, as agreed, would have been segregated in the appendix of this report.

Bechtel Corporation

Mr. Swenam Lee
October 2, 1990
Page 2

If you have any questions or comments on this, please feel free to contact me.

Sincerely yours,

SN/Habash
S. N. Habash
Project Manager

SNH:deb
Attachment

cc: Martin Byrnes, DOE/PETC Gilbert V. McGurl, DOE/PETC
Robert Hamilton, DOE/PETC Joanne Wastek, DOE/PETC
A. B. Schachtschneider, AMOCO
File

TABLE OF CONTENTS

1. INTRODUCTION	1
2. SUMMARY	3
3. TECHNICAL PROGRESS (BY TASKS)	5
3.1 TASK I	6
3.1.1 OVERALL SCOPE OF WORK	7
3.1.1.1 PROCESS SCOPE	7
3.1.1.2 OVERALL PLANT BLOCK FLOW DIAGRAM AND DESCRIPTION - BASELINE DESIGN	11
3.1.1.3 PRIMARY FACILITY ALTERNATES	14
3.1.1.4 SUPPORT FACILITIES ALTERNATES	15
3.1.1.5 BLOCK FLOW DIAGRAM FOR PROCESS SIMULATION MODEL	16
3.1.1.6 EXECUTION PHILOSOPHY	20
3.1.1.7 TASKS DESCRIPTION	21
3.1.1.8 NUMBERING SYSTEM	30
3.1.1.9 LIST OF TECHNOLOGIES	35
3.1.2 CONFIGURATION MANAGEMENT	38
3.1.3 PROGRAM ADMINISTRATION	42
3.1.4 DELIVERABLES	47
3.1.4.1 MONTHLY REPORTS	47
3.1.4.2 QUARTERLY REPORTS	51
3.1.4.3 SEMI-ANNUAL REPORTS	54
3.1.4.4 TOPICAL TASK REPORT	54
3.1.4.5 FINAL TECHNICAL REPORT	54
3.1.4.6 PROCESS SIMULATION DOCUMENTATION & OPERATING MANUAL	54
3.1.4.7 PROCESS SIMULATION SOFTWARE	54
3.1.5 BASELINE CONFIGURATION	55
3.1.6 APPENDIX	56

TABLE OF CONTENTS (CONTINUED)

3.2	TASK II	59
3.2.1	BASELINE DESIGN BASIS	59
3.2.2	LIQUEFACTION REACTOR SECTION DESIGN	59
3.2.3	COAL CLEANING/COAL HANDLING	62
3.2.4	SIMULATION OF PRODUCT FRACTIONATION	63
3.3	TASK IV	65
3.3.1	MATHEMATICAL MODELING	65
3.4	TASK V	66
3.4.1	PROCESS FLOWSHEET SIMULATION MODEL	66
3.4.1.1	PLANT CAPITAL COST SCALING	66
3.4.1.2	COAL CLEANING AND PREPARATION PLANT	67
3.4.1.3	AIR SEPARATION PLANT	67
3.4.1.4	GAS PLANT	68
4.	KEY PERSONNEL STAFFING REPORT	69

LIST OF TABLES

TABLE 3-1	Simulation Model Capability Summary	19
TABLE 3-2	Process Facilities Identification	32
TABLE 3-3	Support Facilities Identification	34
TABLE 3-4	Equipment Letter Code	34
TABLE 3-5	Technology/Licenser Lists	36
TABLE 3-6	List of Open Art Units	37
TABLE 3-7	Time Allocation of Key Bechtel Personnel	45
TABLE 3-8	Time Allocation of Key Amoco Personnel	46
TABLE 3-9	Monthly Report Format	50
TABLE 3-10	Key Personnel Staffing Report Format	52
TABLE 3-11	Quarterly Report Format	53
TABLE 3-12	Primary Liquefaction Yield Data	61
TABLE 4-1	Key Personnel Staffing Report	69

LIST OF FIGURES

FIGURE 3-1	Block Flow Diagram Of Required Tasks	10
FIGURE 3-2	Simplified Block Flow Diagram	13
FIGURE 3-3	Simplified Block Flow Diagram of Plant 1- Process Simulation Model	17
FIGURE 3-4	Simplified Block Flow Diagram of Plant 2 Process Simulation Model	18
FIGURE 3-5	Critical Path Monitoring Diagram	29
FIGURE 3-6	Interface of Configuration Management With Other Relevant Functions	40
FIGURE 3-7	Logic Flow Diagram For Configuration Management As Applied To This Study	41
FIGURE 3-8	Organization Chart of PETC	43
FIGURE 3-9	Bechtel/Amoco Organization Chart	44
FIGURE 3-10	Schematic of Coal Cleaning Facility	64

1. INTRODUCTION

Effective May 16, 1990, Bechtel with Amoco as subcontractor, initiated a study to develop a computer model for a base line direct coal liquefaction design for the U.S. Department of Energy's (DOE) Pittsburgh Energy Technology Center (PETC). The project is for a duration of 18 months with an approved budget of \$2 MM. This study is under DOE contract No. DE-AC22 90PC89857.

The primary objective of the study is to develop a computer model for a base line direct coal liquefaction design based on two stage direct coupled catalytic reactors. This primary objective is to be accomplished by completing the following:

- A base line design based on previous DOE/PETC results from Wilsonville pilot plant and other engineering evaluations
- A cost estimate and economic analysis
- A computer model incorporating the above two steps over a wide range of capacities and selected process alternatives
- A comprehensive training program for DOE/PETC Staff to understand and use the computer model
- A thorough documentation of all underlying assumptions for baseline economics, and
- A user manual and training material which will facilitate updating of the model in the future

The report consists of the following five sections:

- Introduction
- Summary
- Technical Progress Report (By Tasks)
- Key Personnel Staffing Report.

Introduction (Continued)

The quarterly report will present any confidential information as a separate section under the heading "confidential". As agreed upon by DOE/PETC, information included in this section will be treated confidential by DOE/PETC and its contractors.

This report is Bechtel's first quarterly progress report and covers the period of May 16, 1990 through August 19, 1990 which is the reporting period covered by the three already published monthly status reports.

2. SUMMARY

Effective May 16, 1990, Bechtel initiated this study, with Amoco as subcontractor, as an assignment from the U.S. Department of Energy (DOE)'s Pittsburgh Energy Technology Center (PETC). The objective of the study is to develop a computer model for a baseline direct coal liquefaction design based on two stage direct coupled catalytic reactors. The study is for a period of 18 months with an approved total budget of \$2MM.

This is Bechtel's first quarterly progress report and covers the period of May 16, 1990 through August 19, 1990. This reporting period was previously covered by three already published monthly status reports.

The report contains accomplishments made during this time period in all the Tasks scheduled for the period i.e., Tasks I, II, IV and V. As per schedule, the major focus, however, was on Task I. Therefore, the accomplishments included in this report are predominantly for Task I.

The accomplishments are presented in the report on Task by Task basis for all the Tasks covered during this reporting period.

In Task I (which defines the project) the Project Management Plan Draft Report was completed and subsequently updated incorporating the comments and suggestions of DOE/PETC and their contractors. The final version has been sent to DOE/PETC for their approval. The approved copy is the deliverable for the Task.

A summary of the Project Management Plan report is included as Task I accomplishments. This covers the overall scope of work, the methodology of managing the cost and schedule of the project (configuration management), program administration, the deliverables during various phases of work and the definition of the baseline configuration.

In Task II the following activities were completed:

- A preliminary design basis has been set utilizing Wilsonville Run 257E.
- A Licensing Agreement is being awarded to HRI, INC. to perform a portion of the liquefaction section design.
- A preliminary basis for coal preparation, cleaning and grinding basis has been established.

Summary (Continued)

- Simulation of the product fractionator has been started utilizing PROCESS software of Simulation Sciences Inc.

In Task IV the following accomplishments are reported:

- For modeling purposes the total complex was divided into block models and detailed models.
- Algorithms for capital costs and multiple train requirements were developed for the block models.

In Task V the following activities were accomplished:

- Equations for computing the plant capital cost for the design capacity range are being coded into each base case plant model. The equations are based on the flow rate of a key stream and number of duplicate plants.
- The Fortran user block model for plant 10, the Air Separation Plant as well as a first draft of documentation describing the model has been completed.
- The mathematical formulations of the material balance equations for Plant 1, Coal Cleaning and Preparation Plant, have been checked out in a stand-alone Fortran program. Incorporation of these equations into ASPEN/SP Fortran user block model has been started.
- Modeling of Plant 3, Gas Plant, has been completed and a report writer (a customized version of ASPEN/SP output) is being developed.

3. TECHNICAL PROGRESS (BY TASKS)

In order to carry out this Study efficiently, the Study has been divided in seven major tasks. Task I defines the project. Task II develops the baseline design. Task III develops the capital, operating and maintenance costs. Task IV develops the mathematical model necessary for the process computer simulation model. Task V develops and verifies the process simulation model. Task VI documents the process simulation model and training. Task VII is a level of effort task for project management, technical coordination and other miscellaneous support functions.

During this reporting period (May 16, 1990 through August 19, 1990) several accomplishments were made in Tasks I, II, IV and VI. These accomplishments are included in this report task by task.

3.1 TASK I

During this reporting period the Project Management Plan Draft Report was completed and subsequently updated incorporating the comments and suggestions of DOE/PETC and their contractors. The final report has been sent to DOE/PETC for their approval. This task will be completed upon receiving the approved report.

The Project Management Plan report is comprised of the following 9 sections:

- Executive Summary
- Background/Introduction
- Study Objective
- Overall Scope Of Work
- Configurational Management
- Program Administration
- Deliverables
- Baseline Configuration
- Appendix/Project Procedure Booklet
List Of Contents

The Executive Summary, Background/Introduction and Study Objectives are summarized in Section 1 of this report.

3.1.1 Overall Scope of Work

3.1.1.1 Process Scope

The conceptual baseline design shown in the Block Flow Diagram, Figure 3-2 shall be for a plant with a capacity of approximately 60,000 barrels per day of liquid products plus propane and butanes. Plant capacity will be based on the following procedure.

- a. Bechtel/Amoco in consultation with HRI will establish the maximum size coal liquefaction train based on reactor design/fabrication/shipping limitations. This is estimated to be between 15,000 to 20,000 BPSD of equivalent coal liquids, or 4000 -5000 TPSD of moisture free (MF) coal feed based on expected yield.
- b. Maximum plant capacity will then be based on several maximum size trains' production in the range of approximately 60,000 3PSD of coal liquids, or 15,000 - 20,000 TPSD of moisture free (MF) coal based on expected yield.
- c. Coal throughput will float to match the above output, depending on the design basis yield.

Reactor feed coal particle size: Instead of the particle size currently specified in the RFP (70% thru 200 mesh from ROM coal < 8 in), Bechtel/Amoco coal experts and HRI will recommend optimum particle size for coal grinding/handling and downstream processing.

The final capacity shall be determined based on the maximum commercial size of the liquefaction reactors. The battery limits for the design are as follows:

- Coal received from mine by conveyor belt
- Coal storage for 30 days
- Coal grinding, jig cleaning, and drying

Process Scope (Continued)

- Ash concentrate/coal/coke gasification for hydrogen production using Texaco or Shell technology
- Combined cycle cogeneration for steam and electric power generation
- Two HRI ebulated bed reactors in series per reactor train
- Recycle hydrogen gas clean up
- Product recovery and treating including:
 - LPG
 - Naphtha (C₅ to 350°F)
 - Light Distillate (350°F to 450°F)
 - Atmospheric Gas Oil (450°F to 650°F)
 - Light Vacuum Gas Oil (650°F to 850°F)
- ROSE^{SR} solids and liquid separation
- Syngas shift
- Acid gas removal
- Sulfur recovery
- Ammonia recovery
- Phenol recovery from waste water
- Solids waste disposal

The unit operations should be those most suitable for the overall baseline design. After the baseline design is completed, a study shall be done for

Process Scope (Continued)

alternate process units or configuration. The process units to be investigated include first-stage thermal reactor, vent gas separation between catalytic reactors, coal cleaning by heavy media and/or spherical agglomeration, delayed coking and fluid bed coking of vacuum bottoms, low ash coal with no vacuum bottoms deashing, (inclusion or exclusion of this option will be decided at a later date), and hydrogen production using steam reforming of natural gas.

The basis for the operating and capital cost is a plant located at a generic midwestern U. S. location at the mouth of an Illinois #6 coal mine. Feedstock will be Burning Star No. 2 mine Illinois #6 run-of-mine coal. The plant will meet all U. S. Federal and State environmental requirements and appropriate good practices. The process simulation model shall be a suitable software for the operation on an IBM compatible PC. The software selected must be able to be operated on either a VMS, DOS, or OS/2. The delivered software shall be suitable for installation on one of the previously described systems. The software shall be delivered to PETC and except for the modules developed for this contract shall be commercially available.

The project is divided into seven (7) tasks. Task I defines the project. Task II develops the baseline design. Task III develops the capital, operating and maintenance costs. Task IV develops the mathematical model necessary for the process computer simulation model. Task V develops the process simulation model and verifies the model. Task VI documents the process simulation model and training. Task VII is a level of effort task for project management, technical coordination and other miscellaneous support functions.

The inter-relationship of the above tasks is shown in the attached Block Flow Diagram of Tasks, Figure 3-1.

FIGURE 3-1
BLOCK FLOW DIAGRAM OF REQUIRED TASKS

REV 0
07.11.90

3.1.1.2 Overall Plant Block Flow Diagram and Description - Baseline Design

As shown in Figure 3-2, Run-of-mine (ROM) coal will be received at the plant fence line. The coal is then fed to Plant 1 (Coal Cleaning/Preparation) by conveyor, where the coal is cleaned by jigging, crushed, and dried. Clean coal of the required particle size is fed into Plant 2, (Coal Liquefaction). The coal is slurried with the recycle solvent from the liquefaction plant, ashy recycle (a portion of the atmospheric fractionator bottoms), and extract recycle from the Solids/Liquid Extraction Plant. Make-up/recycle hydrogen and the coal slurry are combined and heated before entering the two-stage catalytic coal liquefaction reactor system.

The off gas from Plant 2 is sent to Plant 3 (Gas Plant) where the gas stream is separated into a) an acid gas stream, b) fuel gas, c) propane LPG product and d) mixed butanes LPG product. The heavier reactor products are fractionated in atmospheric and vacuum distillation towers into various boiling range cuts. These are C_5 - 350°F, 350 - 450°F, 450 - 650°F, 650 - 850°F, 850 - 1000°F and 1000°F+. The C_5 - 350°F fraction is charged to Plant 4 (Naphtha Hydrotreater) to stabilize the naphtha product. The 350 - 450°F fraction enters Plant 5 (Distillate Hydrotreater) to produce a stable light distillate product. Plant 6 (Atmospheric Gas Oil Hydrotreater) treats the 450 - 650°F fraction to produce a heavy distillate. The 650 - 850°F fraction is sent to Plant 7 (Light VGO Hydrotreater) to produce a stable light vacuum gas oil. None of the main liquid products will be considered to be finished or fungible.

The 850 - 1000°F heavy vacuum gas oil fraction is recycled back to the reactor system as recycle solvent. The 1000°F+ vacuum bottom fraction is charge to Plant 8-1 (Solids/Liquid Extraction ("ROSE-SR")). This plant uses a hydrocarbon solvent to remove heavy hydrocarbon molecules from the feed to produce an ash concentrate, consisting mostly of ash, fixed carbon, unreacted coal, and asphaltenes. The extract from this plant is recycled to Plant 2. The ash concentrate from Plant 8-1 is sent to Plant 9 where hydrogen is produced by coal gasification. Middling coal from Plant 1 and oxygen from Plant 10 (Air Separation) are also feeds to Plant 9. Two coal gasification technologies, will be evaluated for synthesis gas production in Plant 9. The selected technology (TEXACO or SHELL) will be included in the base line design. Hydrogen

Overall Plant Block Flow Diagram and Description - Baseline Design (Continued)

from the coal gasification process is purified in shift reactors, amine treating, and a hydrogen purification unit (pressure swing adsorption, PSA). The purified hydrogen goes to the liquefaction plant, and the product hydrotreaters as makeup hydrogen. The medium BTU gas from Plant 9 is used as fuel in the cogeneration facilities of Plant 31 (Steam and Power Generation).

Plant 10 (Air Separation) cryogenically fractionates air into oxygen and nitrogen streams. The oxygen stream (95.0%) is fed to Plant 9 whereas nitrogen (99.9%) is supplied to the coal liquefaction complex for various uses.

Acid gases generated from various plants are sent to Plant 11, (Sulfur Recovery) to produce by-product sulfur using the Claus process. The Sulfur Recovery Plant contains a tail gas treater to increase the conversion of acid gas to elemental sulfur and reduce atmospheric release of sulfur compounds.

Figure No. 3-2
SIMPLIFIED BLOCK FLOW DIAGRAM OF
BASELINE DIRECT COAL LIQUEFACTION

3.1.1.3 Primary Facility Alternates

The process alternates to the baseline design which are included in the study are:

1. Two alternates to the main process configuration of two catalytic reactors in series for the liquefaction plant include:
 - a. A first-stage thermal reactor and a second-stage catalytic reactor in series (Plant 2.3-01)
 - b. Two catalytic reactors in series with a separator between the two stages to remove cracked gases from the feed to the second reactor and thus improve its hydrogen partial pressure (Plant 2.3-02)
2. Two coking alternates to the Solids/Liquid Separation ("ROSE-SR") Plant are included.
 - a. The 1000°F+ fraction would be processed in a delayed coker, using Conoco technology (Plant 8.1-01).
 - b. The same fraction would alternately be processed in a FLUID COKER, using Exxon technology (Plant 8.1-02).

The primary products from either of these coking alternates are coker gas, naphtha, gas oil, and coke. Liquid products are combined with the liquefaction plant products for upgrading. The coker gases are treated with the gases from Plant 2 and end up in fuel gas and LPG. The coke from the coker has the same disposition as the ash concentrate from the "ROSE-SR" plant.

3. Steam reforming of natural gas (Plant 9.1 - 03) to produce hydrogen instead of coal gasification. The products from this plant are hydrogen and medium BTU gas. Hydrogen is sent to Plants 2, 4, 5, 6 and 7, whereas medium BTU gas is used as plant fuel. This alternate must be combined with fluid bed combustion for steam production in order to process the solid products from the Solids/Liquids Separation Plant or from either of the two coking options.

3.1.1.4 Support Facilities Alternates

The Support Facilities Alternates to the baseline design which are included in the study are:

1. Two alternates to the main support facility configuration of Coal Preparation (Plant 1) - grinding, jig cleaning, and drying - for the liquefaction plant are:
 - a. Heavy Medium Separation
 - b. Spherical Agglomeration
2. One alternate to the steam and electric power generation systems for the liquefaction complex is:
 - a. Fluidized Bed Combustor (Plant 31.4-01) for steam production in order to process the solid products from the solids/liquids separation process (Plant 8-1) or from either of the two coking options (Plant 8-1-01 or Plant 8.1-02). The alternate is utilized when steam reforming of natural gas (Plant 9.1-03) is used to produce hydrogen instead of Coal Gasification (Plant 9).

3.1.1.5 Block Flow Diagram for Process Simulation Model

Figure 3-2 (Simplified Block Flow Diagram of Baseline Direct Coal Liquefaction) shows the various plants and the main process flows. Plants 3,4,5,6,7, 10, and 11 will be modeled as blocks in the process simulation model as shown in the figure. Plants 8,9 and 31, which are shown with separate main and optional plants, will be modeled so that each main or optional plant will be modeled as a separate block. Plants 1 and 2 will be modeled with each sub-plant as a block as shown on the separate simplified block flow diagram for each of these plants, Figures 3-3 and 3-4 respectively. For example, Plant 1, will be modeled with five firm plant blocks and two optional plant blocks.

Heat and mass balances, elemental balances and a utility balance will be reported for each main plant block and for most of the sub-plant blocks shown on the three figures. For example, elemental balances on the fresh and spent catalyst plants, Plants 2.9 and 2.10, seem unnecessary since these sub-plants are only physical transfer operations which are being modeled to estimate their capital and operating costs.

Capital and operating costs will be generated for each plant. In addition, for each plant and sub-plant a table of the major process equipment and outline specs will be generated.

The process simulation model will be developed with sufficient flexibility to allow PETC to:

- a. use the model for case studies to examine effects of various processing options and operating conditions,
- b. modify the model for cases not included in the scope of the current project.

The capability of the simulation model are summarized in Table 3-1.

Figure 3-3
SIMPLIFIED BLOCK FLOW DIAGRAM OF PLANT 1
PROCESS SIMULATION MODEL

SIMPLIFIED BLOCK FLOW DIAGRAM OF PLANT 2 PROCESS SIMULATION MODEL

8/14/90

0890030-2

TABLE 3-1 Simulation Model Capability Summary

Plant Capital No. Modeled	Single Block Model (a)	Detailed Model (b)	Heat/Mass Balance (c)	Elemental Balance (d)	Utility Balance (e)	Major Equipment List (f)	Cost (g)	Key Parameters
1. Coal Cleaning/ Preparation	x	x	x	x	x	x	x	Coal quality size distribution and moisture content
2. Liquefaction	x	x	x	x	x	x	x	Coal Conversion Yields by boiling range Liquid product qualities (gravity, S, N, O) Heteroatom removal (S, N, O), H ₂ consumption Correct response to variable changes temperature, space velocity, recycle rates
3. Gas Plant	x	x	x	x	x	x	x	Gas yields and H ₂ S to sulfur plant
4. Naphtha Treater	x	x	x	x	x	x	x	Hydrogen consumption, heteroatom removal
5. Distillate Treater	x	x	x	x	x	x	x	Hydrogen consumption, heteroatom removal
6. Light VGO Treater	x	x	x	x	x	x	x	Hydrogen consumption, heteroatom removal
7. Heavy VGO Treater	x	x	x	x	x	x	x	Hydrogen consumption, heteroatom removal
8. Solid/Liquid Separation	x	x	x	x	x	x	x	Ash concentration, recycle rate/quality
Delayed coking	x	x	x	x	x	x	x	Liquid yields, coke production
Fluid Coking	x	x	x	x	x	x	x	Liquid yields, coke production
9. Hydrogen Generation	x	x	x	x	x	x	x	Hydrogen yield, compression, oxygen input Modeled as a block with yields per licensor package plus yield and utility correctors for delayed and fluid coke feed options Steam reforming option also modeled as block Oxygen and nitrogen yields Compression
10. Air Separation	x	x	x	x	x	x	x	Sulfur yield
11. Sulfur Recovery	x	x	x	x	x	x	x	Steam Production
31. Steam/Power Plant	x	x	x	x	x	x	x	Steam production, power generation
Fluid Bed Combustor	x	x	x	x	x	x	x	Steam production
Alternate								

Notes: (a) Only one simulation block for this plant

(b) Multiple plant sections within a block

(c) Report lbs/hr, lb moles/hr, barrels/day

WMSCFD, temperature and pressure of

all input and output streams

(d) Carbon, hydrogen, oxygen, nitrogen, sulfur

(e) Fuel gas, steam, power, cooling water

(f) Output will list major equipment per baseline design

and provide outline equipment specifications

(g) Capital cost scaled by block

3.1.1.6 Execution Philosophy:

The Effective Project start date is May 16, 1990 (the day the contract was signed).

Project Execution is on Task Force Basis. The Project team is composed of a small full time core management group with part time functional groups.

Project schedule gaps mean manhour expenditure to the Project. The current Project schedule contained one month gap between Tasks 1 and 2. We recommended bridging the one month DOE approval gap between Tasks 1 and 2. This was most effectively done by initiating Tasks 2, 4, and 5 activities prior to final approval of Task 1.

Single task budgets (manhours and ODC's) could be slightly off-target as long as overall budget is not exceeded.

Technical concurrence of PETC on any contract items to be reviewed is requested to be done on an expeditious basis. Such concurrence could be obtained verbally by Bechtel by calling the PETC Project Manager, or his designate. Any issue requiring contract change, however, will follow the contract procedure.

Task #7 is a new task. It includes all Project Administration and Technical Coordination functions. These are Program Management, Technical Coordination, Secretarial, Cost/Scheduling and Legal/Contracts/Controller. It is a level of effort activity. Reporting on this task will be on a Summary basis in various Monthly and Quarterly Reports (primarily in early stages of the project). There will be no separate report issued on this task.

3.1.1.7 Tasks Description

Task I: Project Management Plan

a. Bechtel/Amoco has prepared and submitted to PETC's COTR within sixty (60) calendar days after contract award, five copies of this Draft Project Management Plan covering the entire period of performance of the contract. The Project Management Plan shall provide details for, but not be limited to, the following information:

- Understanding of the Statement of Work
- Project management methods to complete the Statement of work
- Project organization chart listing key personnel, their functions and percent of their time spent on the tasks
- Consultants and subcontractors if needed to be used
- Detailed project schedule and methods to be used to maintain schedule
- Cost plan detailed by task and by month
- Project cost control methods
- Process model simulation verification methods
- Configuration management and control
- Reporting and documentation
- Cost estimating procedures.

b. Upon receipt of the PETC's written approval of the Project Management Plan, Bechtel shall issue the Final Plan and shall initiate its implementation immediately. Moreover, as agreed in the Bechtel/Amoco/PETC kickoff meeting of June 12/13, 1990, verbal approval of the Draft Plan will be granted in a short period of time to allow the initiation of other tasks and conserve manhour expenditure.

Task Description (Continued)

- c. Bechtel/Amoco may submit written recommended revisions to the Project Management Plan whenever Bechtel deems such revisions to be desirable for optimum achievement of contractual objectives. Incorporation of any Bechtel-recommended changes in the original Project Management Plan must be approved by PETC prior to implementation.
- d. The subtask description of the activities and their sequencing are depicted pictorially on the Critical Path Monitoring Diagram (Figure 3-5).

Task Description (Continued)

Task II

Task II concerns the development of the baseline design of the coal liquefaction facility. This part of the study includes the acquisition of process licensor information, incorporation of various processing options into the design, and developing the design of the onsite processing units and offsite facilities (including storage and loading, utilities, and waste handling).

In this task certain plants are handled as packaged plants (or blocks) with an overall heat and material balance only.

Task Description (Continued)

Task III

Task III concerns the development of the cost estimate and economics for the base-line design and the alternates for the coal liquefaction facility. This part of the study includes the compilation of equipment lists and utilities summary, development of scaling factors for equipment size and plant cost, and development of the estimates for capital equipment, working capital, and owner's costs. Work to perform the economic analysis includes the workup of the manpower requirements and operating costs for the baseline design and for the alternates and the completion of sensitivity studies.

In this task plants are handled as packaged plants or blocks for the purposes of capital investment, and operating costs as well as overall capacity scale-up.

Task Description (Continued)

Task IV

Task IV concerns the development of mathematical algorithms and models for equipment sizing, scale-up, costing, train duplication for incorporation into the Task V ASPEN simulation program. This task will be done in parallel with Task V.

Task Description (Continued)

Task V

Task V concerns the development of an ASPEN process simulation model of the baseline design. The model will produce complete heat and material balances, elemental balances around each plant and the entire process complex, a major equipment list and outline specifications for Plants 1 through 11, utility requirements, capital cost for all plants, and a discounted cash flow economics model for the total complex. The model will be suitable for studying technology advances and options in a case study approach. The model will not feature optimization capabilities. Additional detail is provided in Figures 3-2, 3-3 and 3-4 and Table 3-1.

Task Description (Continued)

TASK VI

Task VI concerns the development of a training manual and a training course for the process simulation model. The training course will include an overview of the system, modification of the reporting system, interfacing user models, modification of chemical properties, use of the cost and economic modules, specifying flowsheets, streams, components, properties, and convergence. Trainees will be instructed through the use of case study example problems.

Task Description (Continued)

Task VII

Task VII is a new task formally introduced during the June 12-13, 1990 Kickoff Meeting and accepted by PETC. This has been subsequently included in the Execution Philosophy of the project and is included in Section 3.1.1.6 of this report.

Task VII is the overall Management and Technical Coordination function. It also included all the support functions such as Project Control (Cost & Scheduling), Legal, Contracts, Secretarial and Accounting. It is a level of effort activity with no subtasks. All engineering functions are on part-time and as-needed basis for maximum cost-effective execution of this study.

Critical P

3.1.1.8 Numbering System

Philosophy

Numbering For Plants:

The total coal liquefaction complex is comprised of a group of Plants. These plants are divided into two categories:

- 1) Primary Process facilities, and 2) Support facilities.

Each plant in either of these two facilities is individually numbered. For example: coal cleaning and preparation is Plant number 1, coal liquefaction is Plant 2, etc.

Numbering For Parallel Trains:

Parallel trains are numbered by adding suffix A, B, C, etc. to the plant number. (For example if there are three parallel trains for coal liquefaction plant (Plant 2) it will be numbered as 2A, 2B and 2C).

Numbering For Sections:

Numbers for each plant are listed in Block Flow Diagram Figure 4-2. Each plant is subdivided into various identifiable sections. Such sections are listed as the subclassification. For example, sections for Plant 1 are numbered as 1.1, 1.2, etc; for Plant 2, the sections are numbered as 2.0, 2.1, etc.

Numbering For Alternates:

The alternates are numbered by adding hyphenated suffix to the plant number, or plant section number (For example; 9.1 is the plant number of hydrogen production). The numbering for alternate technology option of hydrogen production by coal gasification is 9.1 - 01. Similarly, the numbering for the alternate option for hydrogen production by steam reforming is 9.1 - 02.

Numbering of Individual Equipment at a particular location:

Consider an example of numbering one heat exchanger located in area 100 for liquefaction reactor with the option of first stage reactor being thermal. From plant listing, the plant no. is 2 and section number is 3 with option 1. From Bechtel's equipment letter code shown in Table 3-4, heat exchanger's group letter is E.

The numbering for the above heat exchanger will be:

If there are three exchangers instead of one in the above example, they will be numbered as:

- 2.3 - 01 - E101 for first exchanger
- 2.3 - 01 - E102 for 2nd exchanger
- 2.3 - 01 - E103 for 3rd exchanger.

Primary Process Plants Numbering System

The main process plants numbers and description are shown in Table 3-2.

Table 3-2
Process Facilities Identification

<u>Process Plant No.</u>	<u>Primary Process Plants</u>
1	Coal Cleaning and Preparation
1.2 - 01	Coal Cleaning Option of Heavy Medium Separation
1.2 - 02	Coal Cleaning Option of Spherical Agglomeration
2	Two Stages Coal Liquefaction
2.3 - 01	Thermal Reactor
2.3 - 02	Vent Gas Separation
3	Gas Separation Plant
4	Naphtha Diene H ₂ Treating & Merox
5	Distillate Hydrotreater
6	Atmospheric Gas Oil Hydrotreater
7	Light Vacuum Gas Oil Hydrotreater
8.1	Solids/Liquids Separation (ROSE - SR)
8.1-01	Delayed Coker
8.1-02	Fluid Bed Coker
9.1-01	Hydrogen Production By Coal Gasification (Texaco)
9.1-02	Hydrogen Production By Coal Gasification (Shell)
9.1-03	Hydrogen Production By Steam Reforming
10	Air Separation
11.1	Sulfur Recovery Unit
11.2	Tail Gas Treater

Support Facilities Numbering System

The main support facility plant numbers and descriptions are shown on Table 3-3.

TABLE 3-3
Support Facilities Identification

<u>Support Facilities No.</u>	<u>Support Facilities</u>
19	Relief and Blowdown
20	Raw Material Receiving Storage and Product Tonnage
21	Interconnecting Piping Systems
22	Product Shipping
23	Tank Car/Tank Truck Loading
24	Ash Disposal
25	Chemical and Catalyst Handling
30	Electrical Distribution System
31	Steam and Power Generation
31.1	Co-Generation System
31.4-01	Fluidized Bed Combustor
32	Raw, Cooling and Potable Water Systems
33	Fire Protection Systems
34	Waste Water Treatment Systems
36	Instrument & Plant Air Systems
37	Solid Waste Disposal System
40	General Site Systems
41	Buildings
42	Telecommunications Systems

TABLE 3-4
EQUIPMENT LETTER CODE

<u>Group Letter</u>	<u>Equipment Group</u>
C	Columns and Pressure Vessels
D	Tanks (Ex. ASME Code Vessels)
E	Exchangers (Heat Transfer Equipment)
F	Fired Heaters
G	Pumps and Drivers
H	Vaccum Equipment
J	Instruments
K	Compressors & Drivers
L	Piping
M	Structures
N	Insulation
P	Electrical
R	Building
S	Site Improvements
T	Material Handling Equipment
U	Expendables (Chemicals, Catalysts, Refrigerants, etc.)
V	Package Units
Y	Processing
Z	Water & Waste Treatment

3.1.1.9

List of Technologies

Licensed Technologies and Licensors

The proposed licensors for the licensed technologies are shown in Table 3-5. Except for coal gasification and hydrogen purification (each of which has two technologies for evaluation), all other technologies are assumed to come from the single licensor.

Open Art Units

These are shown in Table 3-6.

**Table 3-5
Technology/Licensors Lists**

TECHNOLOGY	LICENSOR	PROCESS
Coal Liquefaction	HRI*	H Coal
Vacuum Bottoms (Solid Liquid Separations)	Kerr McGee	ROSE ^{SR}
	Conoco* Exxon	Delayed Coking Fluid Coking
Hydrogen Manufacture from natural gas	KTI*	Steam Reforming
Coal Gasification or Hydrogen	Texaco	Coal
	Shell	Gasification
Hydrogen Purification	UOP	PSA/Membrane
LPG Treating	UOP	Merox
Ammonia Removal	USX	Phosam-W
Phenol Removal	Lurgi	Phenolsolvan

* Suggested Sole Licensor

Table 3-6
List of Open Art Units

Hydrotreating

Sulfur Plant

Tail Gas Treating

Amine Treating

Fractionation

* Waste Water Treatment

Combined Cycle

Air Separation

Sour Water Stripping

Coal Preparation and Handling

Fluid Bed Combustion

* Wilsonville Data is being requested

3.1.2 CONFIGURATION MANAGEMENT

Definition and Relevancy to this Study

The traditional role of Configuration Management is to orient the Technical Management of the project to Program Management through the use of standardized documentation. It is the framework on which the Project Manager for both Government and Contractor will run the project. This framework must provide for:

1. Specification definition and maintenance,
2. Identification and documentation of any potential change,
3. A procedure for controlling changes; and
4. A documented record of incorporation of changes to close the loop.

The scope and detail of Configuration Management of a manufactured product or item is tailored to the item's or product's complexity, life cycle phase and quantity, and generally, involves the following functions:

1. Identification and Documentation,
2. Audit,
3. Status Accounting, and
4. Change Control.

The relevant activities for a developmental program such as this study (with no discrete manufactured products or items) are:

1. Program Management,
2. Systems Engineering (Technical Management), and
3. Resource Management (People, Budget, Schedule, and Reports).

We therefore interpret Configuration Management as the body of procedures required to utilize an orderly, well documented path, from the first baseline through the last.

Configuration Management (Continued)

Changes will always be measurable back to the latest baseline. The interface of Configuration Management with the other relevant functions discussed above is shown in Figure 3-6.

The four functions of Configuration Management as applied to this study are condensed into the following two control mechanisms:

1. Trend Control
2. Change Control

The sequential flow of logical events encompassing these two control mechanisms are shown as a logic flow diagram in Figure 3-7.

Trend Control

Trend Control is the system/procedure for identifying and documenting a potential change (Trend) in a timely advanced manner. This Trend Notice brings the potential change to the attention of the Bechtel Program Manager. If the Bechtel Program Manager deems the potential change justifiable, he with the Bechtel Contract Manager then brings it to the attention of the PETC Program and Contract Managers for a preliminary review. If PETC upon reviewing the Trend concurs with Bechtel recommendation, then the trend becomes a Change Order and is processed under the Change Control Program. The Change Control Program identifies the associated scope, cost, and schedule changes.

Change Control

The approved change after documentation with a contract change, will be incorporated in the project in accordance with a change control procedure.

INTERFACE OF CONFIGURATION MANAGEMENT WITH OTHER RELEVANT FUNCTIONS

Figure 3-6

Figure 3-7

LOGIC FLOW DIAGRAM FOR CONFIGURATION MANAGEMENT AS APPLIED TO THIS STUDY

3.1.3 PROGRAM ADMINISTRATION

This section presents the organizational charts of PETC, Bechtel and Amoco. It also includes the percent time allocation to Bechtel and Amoco key personnel dedicated to this program. These are shown in Tables 3-8 and 3-9 respectively.

Additionally, this section describes the control procedures as stipulated in the contract. The complete list of procedures are appended to this plan (Section 9) and are compiled as a free-standing booklet for easy reference. One copy of this booklet is transmitted to PETC separately.

PETC's Organization

The general organization chart for the Division of PETC responsible for this program is given in Figure 3-8. This chart also shows the inter-relationship of this Division with Bechtel and the other two PETC contractors assisting PETC in this program.

Bechtel/Amoco Organization Chart

The Bechtel/Amoco overall project organization for this study is shown in Figure 3-9. Also named on this chart are the Bechtel and Amoco executive sponsors for this project.

Figure 3-8
ORGANIZATIONAL CHART OF PETC

Figure 3-9
BECHTEL / AMOCO ORGANIZATION CHART

06/09/90

TABLE 3-7
Time Allocation of Key Bechtel Personnel

<u>Key Person</u>	<u>Function</u>	<u>Task Number</u>	<u>% Time *</u>
S. N. Habash	Project Manager	7	100
S. K. Poddar	Technical Coordinator	7	100
D. E. Brockman	Project Secretary	7	100
R. F. Earhart	Process Manager	1	48 **
		2	31
		3	17
		4	1
		5	3
		6	-
E. J. Swain	Support Facilities Manager	1	48 **
		2	58
		3	19
		4	2
		5	2
		6	-

* % Time is defined as (number of hours spent by the individual key person on any particular task/duration of the task in hours) X 100.

** These numbers are on the basis of 2 calendar months of the duration of Task 1, although Task 1 continues for 3 calendar months.

TABLE 3-8
Time Allocation of Key Amoco Personnel

<u>Key Person</u>	<u>Function</u>	<u>Task Number</u>	<u>% Time *</u>
A.B.Schachtschneider	Amoco/ Project Manager	1	18
		4	1
		5	12
		6	3
S.J.Kramer	Principal Investigator	2	10
		4	3
		5	42
		6	13
A. Basu	Principal Investigator	2	10
		4	2
		5	24

* % Time is defined as (number of hours spent by the individual key person on any particular task/duration of the task in hours) x 100.

** These numbers are on the basis of 2 calendar months of the duration of Task I, although Task I continues for 3 calendar months.

3.1.4 DELIVERABLES

3.1.4.1 Monthly Reports

This report consists of the following three sections:

- Management Status Report
- Milestone Schedule Status Report
- Cost Management Report

As agreed in the Kickoff Meeting, the Monthly Report is internal to DOE and its contractors, and will not be a part of the public domain. As a result, the confidential material, if any, will not be shown separately in the report and will be protected by DOE and its contractors.

Management Status Report

The Management Status Report for a developmental study of this type consists of a discussion of Program Activities by task. Such discussion for each task will include the accomplishments, plans for next month, areas of concern/action taken, and any configuration changes with or without any resultant scope changes.

Milestone Status Report

This report simply involves completing the form (DOE F 1332.3) as required by the contract. A copy of the completed form for the May/June reporting period is included herein as a sample.

Cost Management Report

This report also involves completing the required form (DOE F 1332.9) as per contract. A copy of the completed form for the May/June reporting period is included herein as a sample.

Monthly Report Format

The format of this report including typical contents of the report is shown in Table 3-9.

U.S. DEPARTMENT OF ENERGY

MILESTONE SCHEDULE ☐ PLAN ☒ STATUS REPORT

DOE F1302.3

TITLE Baseline Design and Systems Analysis		IDENTIFICATION NUMBER DE-AC22-SUPC88657	
PARTICIPANT NAME AND ADDRESS Bechtel Corporation P.O. Box 2186 Houston, Texas 77252-2186		REPORTING PERIOD 5/16/80 THRU 6/30/80	START DATE May 1980
		COMPLETION DATE November 1981	

ELEMENT CODE (TASK NO.)	REPORTING ELEMENT (DESCRIPTION)	DURATION												FY '80												FY '81												PERCENT COMPLETE	
		M	J	J	A	S	O	N	D	J	F	M	A	M	A	M	J	J	A	S	O	N	PLAN	ACTUAL															
Task #1	Project Management Plan																							67	67														
Task #2	Baseline Design																							0	0														
Task #3	Baseline Economics																							0	0														
Task #4	Mathematical Model																							0	0														
Task #5	Simulation Model																							0	0														
Task #6	Documentation and Training																							0	0														
Task #7	Project Management and other support																							10	10														
	SUMMARY																							6	6														

SAMPLE

SIGNATURE OF PARTICIPANT'S PROJECT MANAGER AND DATE									
LEGEND:	STATUS Line	SCHEDULE Line	ACTUAL Line	MONTHLY/QUARTERLY REPORTS Line	COMPLETION OF TASK Line	COMPLETION OF TASK Critical Path Line	COMPLETION OF TASK Critical Path Line	COMPLETION OF TASK Critical Path Line	COMPLETION OF TASK Critical Path Line

F1302.3S

SAMPLE

U.S. DEPARTMENT OF ENERGY COST MANAGEMENT REPORT

TITLE		REPORTING PERIOD		IDENTIFICATION NUMBER							
Baseline Design and System Analysis		5/16/90 THRU 6/24/90		DE-AC22-90PC89857							
PARTICIPANT NAME AND ADDRESS		COST PLAN DATE		START DATE							
Bechtel Corporation P.O. Box 2166 Houston, Texas 77252-2166		JULY 1990		May 1990							
				COMPLETION DATE							
				November 1991							
ELEMENT CODE (TASK NO.)	REPORTING ELEMENT (DESCRIPTION)	ACCRUED COSTS			ESTIMATED ACCRUED COSTS			TOTAL CONTRACT VALUE	VARIANCE		
		REPORTING PERIOD		CUMULATIVE TO DATE	SUBSEQUENT REPORTING PERIOD	BALANCE OF CURRENT YEAR	SUBSEQUENT CALENDAR YEAR			TOTAL	
		ACTUAL	PLAN								ACTUAL
Task #1	Project Management Plan	15.7	15.4	15.7	15.4	11.1	7.9	0.0	34.7	34.4	(0.3)
Task #2	Baseline Design	0.0	0.0	0.0	0.0	2.0	422.1	270.0	694.1	694.1	0.0
Task #3	Baseline Economics	0.0	0.0	0.0	0.0	0.0	0.0	94.1	94.1	94.1	0.0
Task #4	Mathematical Model	0.0	0.0	0.0	0.0	0.2	6.1	15.6	21.9	21.9	0.0
Task #5	Simulation Model	0.0	0.0	0.0	0.0	0.0	151.5	184.3	335.8	335.8	0.0
Task #6	Documentation and Training	0.0	0.0	0.0	0.0	0.0	0.0	50.7	50.7	50.7	0.0
Task #7	Project Management and other support	51.1	59.0	51.1	59.0	36.3	215.2	458.9	761.5	769.4	7.9
TOTAL		66.8	74.4	66.8	74.4	49.6	802.8	1073.6	1992.8	2000.4	7.6
DOLLARS EXPRESSED IN		SIGNATURE OF PARTICIPANT'S PROJECT MANAGER AND DATE				SIGNATURE OF PARTICIPANT'S AUTHORIZED FINANCIAL REPRESENTATIVE AND DATE					
Thousands											

TABLE 3-9
Monthly Report Format

- Introduction
- Summary
- Management Status Report
- Program Activities By Task
 - Task Number
 - Accomplishments Last Months
 - Plans for Next Month
 - Areas of Concern/Action Taken
 - Scope Changes
- Milestone Schedule Status Report - (Form F 1332.3)
 - Discussion
 - Recommendation
- Cost Management Report - (Form F 1332.9)
 - Discussion
 - Recommendation

3.1.4.2 Quarterly Reports

This report consist of the following three sections:

- Technical Progress Report
- Key Personnel Staffing Report
- Summary Subcontract Report

As agreed in the Kickoff Meeting of June 12 - 13, 1990, the Quarterly Report will present any confidential information as a separate section under the heading "Confidential". Information included in this Section will be treated confidential by DOE and its contractors.

Technical Progress Report

The reporting of technical progress is done by tasks for all tasks included for the reporting period. This report is, in effect, a summary of the three preceding monthly reports, but with a separate confidential section.

Key Personnel Staffing Report

The updated list of the key Bechtel personnel working on the project during the duration of the reporting quarter will be included. In addition, the percentage of time spent on the project by each individual key person will be reported, the format of which is illustrated in Table 3-10.

Quarterly Report Format

The format of this report is included in this section as Table 3-11.

TABLE 3-10
Key Personnel Staffing Report Format

Duration of Quarter: From.....To.....

<u>Name of Key Person</u>	<u>Function</u>	<u>% Time Spent</u>
<u>Bechtel:</u>		
S. N. Habash	Project Manager	
S. K. Poddar	Technical Coordinator	
D. E. Brockman	Project Secretary	
R. F. Earhart	Process Manager	
E. J. Swain	Support Facilities Manager	
<u>Amoco:</u>		
A. B. Schachtschneider	Project Manager	
S. J. Kramer	Principal Investigator	
Arun Basu	Principal Investigator	
J. D. Fox	Principal Investigator	

TABLE 3-11
Quarterly Report Format

- Introduction
- Summary
- Technical Progress Report (Activities by Task)
 - Task Number
 - Accomplishments For The Quarter
 - Plans For Next Quarter
 - Areas of Concern/Action Taken
 - Scope Change
- Key Personnel Staffing Report

3.1.4.3 Semi-Annual Reports

Subcontracting Report For Individual Contracts (Semi-Annual)

This report involves completing form SF 294 as required by the contract. A copy of the form is included in this section.

3.1.4.4 Topical Task Reports

As agreed in our Kickoff Meeting the topical reports are the same as the final task reports for each task. Hence, the reports will be titled Topical/Task Reports.

These reports will present the deliverable information for each task.

3.1.4.5 Final Technical Report

This report will be issued at the completion of this study in accordance with the provisions of the contract as described Management Plan.

3.1.4.6 Process Simulation Documentation and Operating Manual

The documentation of the Process Simulation and Operating Manual will be issued at the completion of the relevant task of the study. This will be done as per contract.

3.1.4.7 Process Simulation Software

The process Simulation Model will be developed in such a way that it will be a suitable software for the operation on an IBM compatible personal computer (PC). The software shall be operable on either a VMS, DOS or OS/2. The delivered software shall be suitable for installation on one of the previously described systems. The software shall be delivered to PETC as required by the contract.

3.1.5. BASELINE CONFIGURATION

Baseline Configuration

As discussed earlier in this report, and as illucidated in the contract, configuration management is an essential ingredient in program management. The key factor for the successful implementation of this concept is the appropriate definition of the baseline configuration.

The definition of the baseline configuration for this study consists of all the details included in Sections 3.1.1 through 3.1.4 of this document. Therefore, any deviation from the initial baseline configuration described in the above sections constitutes a change with possible contract, cost and schedule changes.

3.1.6 APPENDIX

A Project Procedure booklet is being prepared for internal use by the Bechtel Project team. A courtesy copy of this booklet will be issued for PETC's information at the same time as the approved Management Plan.

The preliminary Table of Contents of this booklet is tentatively shown in this appendix.

3.1.6 Project Procedures Table of Contents

APPENDIX/PROJECT PROCEDURE BOOKLET LIST OF CONTENTS

General

- .1 Project Procedures
- .2 Correspondence
- .3 Meeting Notes
- .4 Conference Notes
- .5 Action List
- .6 Distribution of Reports and Documents
- .7 Project Files
- .8 Weekly Activity Reports
- .9 Quarterly Reports
- .10 Monthly Reports
- .11 Topical/Task Reports

Project Controls

- .1 Cost and Schedule Control
- .2 Trend Control
- .3 Change Control
- .4 Bi-weekly Manhour Monitoring

Table of Contents (Cont'd)

Engineering

- .1 Numbering System
- .2 Technology/Information
 Acquisitions
- .3 Cost Estimating

Procurement

- .1 Subcontract Report
 for Individual Controls
- .2 Summary Sub-Contract Report
- .3 Notice of Energy RD&D
 (Project Form 538)

Project Administration

- .1 Billings
- .2 Travel Expense
- .3 Reporting Schedule
- .4 Invoicing Schedule

3.2 Task II

3.2.1 Baseline Design Basis

It was decided by PETC that the baseline plant design should be based on test data from Wilsonville Run 257 (material balance period E) using Illinois #6 coal feedstock. The 257E data were subsequently simulated by MITRE. The MITRE simulation was further adjusted by Amoco to provide a complete design basis. Specifically, heteroatom, carbon oxides, water and light end (C1 to c6) components were further broken down. In addition, the design basis was elementally balanced. Primary liquefaction yield data thus obtained are shown in Table 3-12.

3.2.2 Liquefaction Reactor Section Design

Bechtel is in the process of awarding a subcontract to HRI to perform a portion of the liquefaction section design. The scope of work would include the following portions of the liquefaction section:

- preheating
- first-stage reactor
- second-stage reactor
- high pressure separation
- recycle hydrogen compression

In addition to the baseline design, HRI will prepare one alternative case based on an interstage separator, between the two catalytic reactor stages.

HRI will perform a preliminary engineering design of a conceptual commercial coal liquefaction plant. The conceptual design will be for a full-scale commercial facility, containing maximum sized reaction trains, based on design basis information provided by Bechtel. A summary of the work to be performed is as follows:

- Process Flowsheets will be prepared showing major equipment and flows.

Liquefaction Section Reactor Design (Continued)

- Process Description will be provided explaining the process flow through the steps identified within the battery limits.
- Overall Material Balance showing composition, conditions and rates of all process streams.
- Utility and Chemicals requirements will be estimated.
- Equipment List and Process Data for the major equipment showing the following information.
 1. Pumps - design gpm at pumping temperature, differential pressure, estimated BHP. For reactor ebullating pumps, HRI will provide estimated cost.
 2. Heat Exchangers - heat duty, type, design conditions, materials of construction, estimated surface area, estimated BHP for air coolers.
 3. Fired Heaters - heat absorbed, tube material of construction, design pressure.
 4. Reactors - dimensions and estimated cost.
 5. Towers - dimensions, number of trays or volume of packing, design conditions, materials of construction.
 6. Drums - dimensions, design conditions, materials of construction.
 7. Compressors - normal and design SCFD, MW, suction and discharge pressure, suction temperature and Cp/Cv ratio, estimated BHP.
 8. Special Equipment Specifications - HRI will provide estimated cost for catalyst addition and withdrawal equipment based catalyst replacement rate provided by Bechtel.

TABLE 3-12

PRIMARY LIQUEFACTION YIELD DATA: BASE LINE DESIGN

	<u>WT% MAF</u>
INPUT	
Coal	100.00
Hydrogen	<u>6.20</u>
OUTPUT	106.20
H ₂ O	9.51
H ₂ S	2.86
NH ₃	1.39
CO ₂	0.14
CO	0.06
CH ₄	1.84
C ₂ H ₆	1.43
C ₃ H ₆	1.52
i - C ₄	0.12 (a)
n - C ₄	0.67
C ₃	0.15
C ₆ - 350	15.97
350 - 450	7.51 (b)
450 - 650	25.11
650 - 850	21.36
Phenols	0.30 (a)
Organics (in Ash Conc.)	<u>16.26</u> (c)
	106.20

(a) The i-C₄/n-C₄ ratio and phenols yield are estimates.

(b) For elemental balances, the phenols yield is included in the 350-450°F fraction.

(c) Estimated by difference to reflect 6.20% MAF H₂ consumption: the Mitre number is 16.33% MAF.

3.2.3 Coal Cleaning/Coal Handling

The following were established as the scope of the coal cleaning/coal handling portion of the Coal Liquefaction Project:

- The fence line of the liquefaction complex is shown in Figure-3-9 whereby 3" x 0" coal is fed to the complex via conveyor.
- The following section of this plant are included in plant one of this complex.

Storing/mixing
Jig cleaning, (base case)
Heavy medium separation
Spherical agglomeration
Product Storage

- The remaining sections (Coal grinding and drying operation) will be included as a part of Plant No. 2, liquefaction section.
- Base case coal cleaning is via one jig plant with cycloning of fines and de-watering.
- Heavy medium separation process is alternate 1 for coal cleaning.
- Spherical agglomeration is alternate 2 for coal cleaning.
- There will not be any middlings as the washability of the selected coal, and product qualities, and plant economics do not warrant production of a middling product.
- A total of 30 days coal storage will be provided in this plant of which 2 days storage will be provided at the front end of the cleaning plant and a 28-days storage will be for the clean coal.
- The coal cleaning plants will operate 2 shifts a day and 5 days a week. Alternate 2, spherical agglomeration, will include a conventional coal cleaning section and an agglomeration section. The agglomeration part of the plant will operate 3 shifts a day and 5 days a week.

Coal Cleaning and Preparation Plant

- From the cleaning plant it is intended to make a coarse refuse which is classified as non-hazardous to be trucked to a land fill and a fine refuse slurry for disposal in a permitted pond as is commonly done in coal fields.
- The capacities to be considered are between 5,000 and 20,000 tons per day of clean coal. Spherical agglomeration process will use Heptane. Use of liquefaction process liquids of similar characteristics for agglomeration may be considered if suitable. ROM coal data will be as per the proposal.

3.2.4 Simulation of Product Fractionation

Simulation of product fractionator has been started utilizing PROCESS software of Simulation Sciences Inc.

Figure 3.10 - Schematic of Coal Cleaning Facility
Showing Plant Fence Line

3.3 Task IV

3.3.1 Mathematical modeling

During this reporting algorithms for capital costs and multiple train requirements were developed for the block models. For modeling purposes the total complex is divided into block models and detailed models.

3.4 Task V

3.4.1 Process Flowsheet Simulation Model

3.4.1.1 Plant Capital Cost Scaling

Equations for handling the plant capital cost scaling are being coded into each simple base case plant model. The equations are based on the flow rate of a key stream and number of duplicate plants. These equations are:

$$\text{COST} = \text{FCOST} + (n - 1) * \text{SCOST}$$

$$\text{FCOST} = A + B * (C + D * F_o / (N * \text{RF}_o))^E$$

$$\text{SCOST} = F * \text{FCOST}$$

where,

COST = Total capital cost of all duplicate sub-plants

FCOST = Capital cost of the first sub-plant

SCOST = Capital cost of each subsequent duplicate sub-plant after the first one

N = Total number of duplicate sub-plants

F_o = Total flow rate of the key stream in MM SCF/hour or Mlbs/hour from all duplicate sub-plants

RF_o = Reference flow rate of the key stream in MM SCF/hour or Mlbs/hour used to scale the capital cost of the sub-plant as a function of plant capacity.

A, B, C, D, E and F = Constants for the calculation of the capital cost of sub-plant

In the above capital cost equation, constant A is a fixed cost associated with each sub-plant. When constants A and C are zero, constant B is the capital cost of a sub-plant of capacity RF_o. When constant C is zero, constant B minus constant A is the capital cost of a sub-plant of capacity RF_o. Constant E is the sub-plant cost scaling exponent. Constant F is the

Plant Capital Cost Scaling (Continued)

cost reduction factor for the construction of duplicate sub-plants after the first one. Constants C and D provide additional flexibility in the costing equation. Normally constant C will be 0 (zero), and constant D will have a value of 1.0.

As the capital cost estimates become available, the appropriate coefficients will be developed for the above cost equations. Development of the simple base case plant models continues. Initially development of simple unit models with available data is being carried out. Gradual improvement of them will be done as process design unfolds and more process, utility and cost information becomes available.

3.4.1.2 Coal Cleaning and Preparation Plant

The mathematical formulations of the material balance equations for Plant 1, the Coal Cleaning and Preparation Plant, have been checked out in a stand-alone Fortran program. Work has begun to incorporate these equations into an ASPEN/SP Fortran user block model. The baseline design model for Plant 1 is another black box model with a single coal input stream (the ROM coal), and four output streams; clean coal, middling coal, refuse, and water. The user must specify the fraction carbon, hydrogen, nitrogen, chlorine, sulfur, oxygen, and ash in the feed ROM coal that will appear in the clean coal and in the middling coal. In addition, the moisture contents of the clean coal, middling coal, and refuse must be specified.

3.4.1.3 Air Separation Plant

The Fortran user block model for Plant 10, the Air Separation Plant, is complete and a first draft of documentation describing the model has been completed. The Fortran user block model for Plant 10 is a black box with an input air stream and two output streams, an oxygen stream and a nitrogen stream. The user can specify the purity of both the product oxygen and nitrogen streams.

3.4.1.4 Gas Plant

Plant 3, Gas plant, has been completed and a report writer (a customized version of ASPEN/SP output) is under development. Unlike Plants 10 and 1, Plant 3 is not modeled as a simple black box. It is being modeled using various unit operation models for compressors, heaters, expanders, and simplified fractionators.

During the next reporting period we expect to complete the simple models for Plants 1 and 3, and initiate work on Plant 2, Coal Liquefaction, Plant 11, Sulfur Plant, and Plant 4, Naphtha Hydrotreating.

4. KEY PERSONNEL STAFFING REPORT

Key Personnel staffing report for this reporting period (May 16th - August 19, 1990) as required by DOE/PETC is included in Table 4-1 shown below.

**TABLE 4-1
KEY PERSONNEL STAFFING REPORT**

Duration of Quarter From May 16, 1990 to August 19, 1990

<u>Name of Key Person</u>	<u>Function</u>	<u>% Time Spent*</u>
---------------------------	-----------------	----------------------

Bechtel:

S. N. Habash	Project Manager	100
S. N. Poddar	Technical Coordinator	100
D. E. Brockman	Project Secretary	100
R. F. Earhart	Process Manager	37
E. J. Swain	Support Facil. Manager	54

Amoco:

A. B. Schachtschneider	Project Manager	20%
S. J. Kramer	Principal Investigator	46%
Arun Basu	Principal Investigator	31%
J. D. Fox	Principal Investigator	32%

* (Number of hours spent/total available working hours for May 16 through August 19, 1990) x 100.

END

**DATE
FILMED
9/22/92**