AIIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 1

Molten Carbonate Fuel Cell Product Development Test Environmental Assessment/Protection Plan

Topical Report

November 1992

Work Performed Under Contract No.: DE-FC21-92MC28065

For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
Morgantown, West Virginia

By
M-C Power Corp.
8040 S. Madison Street
Burr Ridge, Illinois

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

pe

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

**Molten Carbonate Fuel Cell Product Development Test
Environmental Assessment/Protection Plan**

Topical Report

Work Performed Under Contract No.: DE-FC21-92MC28065

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
M-C Power Corp.
8040 S. Madison Street
Burr Ridge, Illinois 60521**

November 1992

PURPOSE

This Molten Carbonate Fuel Cell Product Development Environmental Assessment Topical Report has been prepared by M-C Power in accordance with the scope of work and deliverables identified in Contract No. DE-FC21-92MC28065. The report contains environmental assessment information described in Part IV, Attachment A, Exhibit I, "Information Required For The National Environmental Protection Act (NEPA)" of the subject contract.

MOLTEN CARBONATE FUEL CELL PRODUCT DEVELOPMENT TEST ENVIRONMENTAL ASSESSMENT

INTRODUCTION

This Environmental Assessment (EA) has been prepared by the Department of Energy (DOE) in compliance with the National Environmental Policy Act of 1969 (NEPA). It has been prepared in accordance with the President's Council on Environmental Quality (CEQ) regulations implementing NEPA and the DOE Guidelines for Compliance with NEPA.

As required by Section 1508.9 of the CEQ regulations, the sections contained in this EA include the following:

- 1.0 Purpose and Need for the Proposed Action
- 2.0 The Proposed Action and Alternatives
- 3.0 Environmental Impacts of the Proposed Action
- 4.0 List of Agencies and Persons Contacted

1.0 PURPOSE AND NEED FOR THE PROPOSED ACTION

The objective of the proposed action would be to conduct a 250 kilowatt (kW) Product Development Test (PDT) of M-C Power Corporation's (MCP) Molten Carbonate Fuel Cell (MCFC) concept. The proposed action, which involves the construction and operation of a test facility, would show the feasibility of using fuel cells for electric power generation and would demonstrate the performance obtainable with the MCFC product. The project would provide a necessary iteration in the product manufacture and testing necessary for customer acceptance and eventual MCFC commercialization.

MCFCs operated electrochemically with natural gas could provide a solution to the problem of generating affordable electricity while satisfying stringent environmental regulations. The technology that would be utilized not only meets the National Energy Strategy of "increasing energy and economic efficiency" but also provides sulfur and nitrogen oxide emissions at least an order of magnitude below environmental standards. The MCFC technology possesses technical, economic, and environmental advantages compared to commercial alternatives.

2.0 ALTERNATIVES INCLUDING THE PROPOSED ACTION

2.1 The Proposed Action

2.1.1 Project Description

The overall objective of the proposed action would be to design, construct, and test a proof-of-concept MCFC PDT at the Kaiser Permanente San Diego Medical Center. The work would include development of a management plan, gathering environmental information, design of a 250 kW MCFC test facility, purchase of MCFC stacks, acquisition of balance-of-plant equipment, plant construction, and plant testing. All power and thermal energy produced would be utilized on-site. The proposed product development test facility would not require major modification to the Medical Center. The heat generated by the PDT could be used for process heat, absorption cooling, thermal storage, hot water system, and sterilization.

In the MCFC stack, hydrogen (H_2) and carbon monoxide (CO) made from reformed natural gas is electrochemically oxidized, with the valance electrons released for power generation. This process is simpler and more efficient than competing technologies. Upstream of the fuel cell, a guard bed of manganese dioxide captures any sulfur present in the natural gas fuel streams, thus dramatically reducing potential SO_x emissions. Downstream, the exhaust gases are used in heat recovery processes to generate steam (or cogenerate electricity in a turbine). This maximizes overall thermal efficiency. The spent gas (principally water vapor, CO_2 , and nitrogen [N_2]) is then exhausted to the atmosphere.

Figure 1 shows the process flow schematic. The PDT consists of the MCFC, reformer, desulfurizer, heat exchangers, blowers, expander, compressor, inverter, and control panel.

The MCFC power plant would be tested in a manner representative of commercial, dual-fuel MCFC power plant operation. Important emissions would be measured, including at a minimum, water, carbon monoxide (CO), carbon dioxide (CO_2), nitrogen oxides (NO_x), sulfur oxides (SO_x), and unburned hydrocarbons (UBHC). The proposed action would require 36 months. The test facility would operate for 12 months.

One of the key objectives of the PDT facility is to prove that noise, gaseous, and liquid emissions from the plant are significantly lower than emissions from competitive power generation technologies. The San Diego County APCD and other local environmental agencies will be consulted when establishing testing procedures to insure that data collected will be useful in evaluating the test facility's environmental impacts.

Figure 1

The following are the expected inputs to the plant during rated power operation:

Natural Gas - 88lbs/hr	(0.44×10^6 lbs/yr)
Air - 2520 lbs/hr	(12.6×10^6 lbs/yr)
Water - 293 lbs/hr	(1.42×10^6 lbs/yr)

The following are the expected plant outputs during rated power operation:

Sulfur Dioxide (SO_2) - <0.0002 lbs/hr	(<1.0 lb/yr)
NO_x - < 0.008 lbs/hr to 0.025 lbs/hr	(<4 lbs/yr up to 125 lbs/yr)
Water Vapor - 483 lbs/hr	(2.42×10^6 lb/yr)
CO_2 - 240 lbs/hr	(1.2×10^6 lb/yr)

Annual input/output quantities are based on an estimated 5000 hours of operation for the demonstration.

The manganese oxide catalyst used for natural gas desulfurization is sized to exceed anticipated plant operating life. The manufacturer accepts the spent catalyst to reclaim it, therefore, the catalyst is not considered an input or output for environmental impact considerations.

If the natural gas contains its maximum specification value of 1% Nitrogen, ammonia (NH_3) will be formed in the reformer. Until tests are run with NH_3 in the anode inlet, it is uncertain how much of this would be converted into NO_x . However, if it is assumed that all of the ammonia is converted into NO_x and is discharged in the system exhaust, the exhaust stream can contain up to 5 ppm at NO_x , which for this plant is 0.025 lbs/hr.

As presently configured, the plant requires an external water supply of 293 lbs/hr. All of this water, plus the water produced in the plant, is carried out of the plant as vapor in the plant exhaust. However, an air cooled condenser to reduce the exhaust temperature to 120°F can be placed in the exhaust stream to recover all of the water required by the plant, making the system water self-sufficient. If the exhaust temperature is further dropped to 100°F, 9.6 gallons/hr. (76.8 lbs/hr.) of excess water can be recovered.

2.1.2 Description of the Project Location

2.1.2.1 General Description of the Area

The PDT would be conducted at an existing permitted facility. The eastern and northern surrounding areas of the site are residential. The southern and western surrounding areas are heavy commercial. There are no water bodies in close proximity. The weather and terrain of the general area are typical of the San Diego, California metropolitan area.

2.1.2.2 Description of Project Site

The proposed site for the 250 kW MCFC PDT is the Kaiser Permanente San Diego Medical Center located at 4647 Zion Avenue in the City of San Diego (Figure 2). The proposed project is part of an expansion of the existing 300-bed hospital with emergency care, pharmacy, and associated medical office facilities. The medical facility is located in a developed section of the City of San Diego known as Mission Valley. Residential and commercial land uses dominate the area surrounding the Medical Center (Figure 3). There is easy access to the site via commercial roadway system.

The test facility would be sited adjacent to existing incineration and power distribution systems. Interconnection facilities to electric transformers, heat exchangers, and fuel supply are within 100 feet from where the proposed PDT would be located. The proposed site has more than sufficient area for construction, start-up, servicing, and repair activities. Visitor access to the site is excellent. The site's current zoning designation by the City of San Diego is R-1-5 which is residential single family detached unit in minimum 5,000 square-foot lot.

The Medical Center has existing natural gas-fueled engine cogenerators and a medical waste incineration facility. The incineration system is currently shut down as it is being replaced with a plasma pyrolysis system. The existing incineration structure will be used by the pyrolysis system. The proposed MCFC test facility would consist of skid mounted units which would be installed behind the Medical Center, near the existing cogeneration system and adjacent to the incineration facilities. The MCFC unit would be installed as part of the Medical Center's overall expansion program. The expansion has the capability of accepting and using all power and thermal outputs from the PDT. The installation of the 250 kW test facility would cause no negative impact to the environment.

2.2 No Action Alternative

Under the No Action Alternative, the project would not be conducted, and an opportunity would be missed to demonstrate an advanced power generation technology with potential to replace operation of less efficient systems having greater environmental impacts. Successful development of molten carbonate fuel cells with the potential to offer higher efficiency, lower-cost, and environmentally benign power generation would be delayed or not occur. Successful development of this technology would help to ensure an adequate supply of electrical energy to the American public, reduce air emissions, decrease the dependence on foreign energy supplies, and stimulate the use of abundant U.S. domestic coal/natural gas. Successful coal/natural gas integrated MCFC systems would play a major role in the future implementation of environmentally benign power generation technologies for commercial, industrial, and electric utility applications.

Figure 3

Site Definition

Lots 5 through 18, Block 17; Lots 19 through 22, Block 19; Lots 1 through 13 and Lots 25 through 40, Block 20; all of Blocks 21 and 22, and all of "Grant Circle", Grantville and Outlets, Map No. 776, on file in the office of the County Recorder, in the R-1-5 zone.

Conditional Use Permit No. 231-PC

2.3 Alternative Sites

The following sites, all located in Southern California, were evaluated as alternatives for location of the PDT.

- Encino Power Plant
- South Bay Power Plant
- Veterans Administration Hospital, La Jolla, CA
- U.S. Navy Base Camp Pendelton
- U.S. Navy Hospital, San Diego

Major factors which contributed to the site selection included access to existing electrical and thermal service, access to the site by potential visitors, progressive and willing partner, opportunity to expand the demonstration site to a larger installation at a later time, and minimum impact to existing facility and surrounding community.

It was determined that the project would benefit by installing the demonstration power plant in a location other than a large central power plant. In this manner, commercial customers would receive first-hand exposure to the technology. Further, operational data at a commercial facility would be more meaningful because it would correlate with potential early commercial applications.

The Kaiser Permanente Medical Center was selected as the primary host site for the PDT facility rather than the alternate sites listed above because of Kaiser Permanente's management interest in the MCFC technology. The hospital's expansion program also facilitated the permitting process. There is an excellent relationship between the medical center management and San Diego Gas & Electric (SDG&E). SDG&E is a partner with M-C Power in the commercialization of the molten carbonate fuel cell technology and are cost sharing in the PDT.

The Veteran's Administration Hospital located in La Jolla, California a city 15 miles north of the city of San Diego, California and a U.S. Navy facility either at the Navy hospital in San Diego, California or Camp Pendelton located approximately 40 miles north of San Diego were considered to be primary alternative sites. Each of these alternative sites have a high energy consumption. Therefore, the proposed PDT facility would not have a significant negative impact to the environment. These alternative hosts have expressed interest in cofunding a large demonstration MCFC power generation system at a future date.

2.4 Alternative Technologies

A variety of potential alternative technologies for utility/industrial power generation were evaluated as alternative technologies. Several of them are in similar stages of research and development as the MCFC. Among these are the fossil-based solid-oxide fuel cell (SOFC) and coal-fired gas turbine engine systems. SOFCs are similar in operation to MCFCs, but have different developmental issues to resolve. Coal-fired gas turbine systems are also in the developmental

stage, but have projected lower system efficiencies and higher air emissions than fuel cell systems. The MCFC was selected because of its inherent and superior environmentally benign and highly efficient power generation characteristics. Selection of an alternative technology would delay or prevent the MCFC technology from inclusion among the technologies available to provide clean and efficient electric power generation. Alternative technologies were therefore eliminated from further consideration.

2.5 Other Alternatives

As mentioned in 2.4, the primary objective of this program is to further the development and commercialization of MCFC power plants. Conventional power generating equipment such as diesel engine generator sets and gas fired gas turbines were not considered as alternatives. Phosphoric Acid Fuel Cell (PAFC) power plants are in their commercialization stage and already have a number of sites where they are being evaluated. Therefore, PAFC technology was not considered as an alternative.

3.0 ENVIRONMENTAL IMPACTS OF THE PROPOSED PROJECT AND NO ACTION ALTERNATIVE

The proposed site of the PDT facility is adjacent to an existing incineration building and cogeneration system which are in close proximity to the hospital. It is next to a two-level parking facility separated by an eight foot embankment which is landscaped with ivy. Approximately 30 ft. x 40 ft. of the embankment would be removed to install a pad for the PDT skids. This minimal amount of earth movement is expected to have no impacts on land use. It will have no impacts on historical sites, parks, wilderness areas, valuable ecological habitats, or other sensitive natural resources. Noise and dust will be marginal during facility construction and such effects will be temporary. There will be no safety hazards produced during construction or other serious disturbances. During operation the PDT facility will be noticeable to the surrounding human population, primarily as a physical structure similar in size and appearance to the other structures adjacent to it. Also, the PDT facility will be designed to achieve an aesthetically pleasing environment facility.

The Kaiser Medical Center in San Diego received a negative declaration to the EIR and California Environmental Quality Act (CEQA). A Conditional Use Permit (CUP) was issued to Kaiser for the facility to operate a 400 bed general hospital, related off-street parking, and other accessory uses as determined and approved by the San Diego Planning Director. The PDT facility would fit within the accessory uses and approval from the Planning Director would be required. It is anticipated that such approval would be given. Failure to get such approval would trigger a CEQA compliance. At this time, the only "siting permit" that may be required could possibly be a CUP amendment and Planning Director approval under the existing CUP. There are no special building code requirements or existing building code violations. The only permit requirements envisioned at this time are a building permit that may be needed for the PDT facility enclosure and a plumbing permit for water and gas piping.

3.1 The Proposed Action

3.1.1 Air Quality

The City of San Diego Air Pollution Control District (SDAPCD) currently exempts the proposed PDT facility under Rule 11(d), 4 (ii). The SDAPCD maintains state and federal ambient air quality standards that have been established to protect the public health and welfare.

Having very low sulfur oxide (SO_x) or nitrous oxide (NO_x) (<0.0002 lbs/hr. and <0.008 lbs/hr., respectively) emissions, fuel cells are two orders of magnitude cleaner than most advanced fossil fuel-based energy systems contemplated or in existence.

Because of their efficiencies, CO₂ emissions from MCFCs are from 22 percent to 165 percent *lower* than other fossil fuel-based systems, either now in existence or on the drawing board. MCFCs emit no other "non-criteria" air pollutants.

3.1.2 Water Quality/Quantity Impacts

Quantities of water needed for the proposed action would not be above the capacity already available at the facility from the public supply system. Water demand for a 250 kW MCFC facility is approximately 7000 lbs/day. The standard operating procedures at the existing medical facility are fully adequate to handle any water needs and water disadvantages that may result from the MCFC project. Therefore, no water quality impacts are anticipated as a result of conducting this project.

Surface and ground waters would not be impacted by the proposed PDT facility which will discharge any unused condensed water vapor effluents to the sanitary sewage system. Water effluents would be of potable quality and would not require further treatment prior to discharge to the sewer system. All water discharges would be in compliance with federal, state and local permit requirements. There would be no streams or surface impoundments impacted by construction activities.

3.1.3 Solid Waste Disposal

The proposed action would generate only minor construction and packaging solid wastes that could be readily handled by the existing, standard operating procedures of the medical center. There would be no solid wastes produced incidental to the proposed action. Therefore, no solid waste disposal impacts are anticipated as a result of conducting the proposed project.

3.1.4 Land Use

The Kaiser Medical Center occupies approximately 18.5 acres. Of this area, the proposed PDT facility would occupy about 1,000 square feet. The MCFC project would be built within existing facilities. There would be relatively minor site construction work because the power plant system will be located on skids which will be factory assembled and tested prior to shipping and installation at the project site. Less than 100 cubic yards of soil would be removed from an existing earthen berm. The project site would be landscaped in accordance with current site practices.

3.1.5 Noise

The proposed PDT site is subject to the Occupational Safety and Health Act (OSHA) standards for noise. All operations would be within enclosed structures. It is expected that noise levels at the fuel cell PDT will be low (53 dB at the site boundary). No increase in noise within the boundaries of the site is anticipated due to the PDT. Hearing protection for workers is not presently required and is not anticipated for the proposed PDT. Delivery of the PDT facility on skid will minimize on-site construction activity and associated noise.

3.1.6 Floodplains or Wetlands

The MCFC PDT would be installed within an existing paved area with storm sewers. There would be no impacts to floodplains or wetlands.

3.1.7 Historic Areas

The MCFC PDT would be installed at a fully developed medical facility site. Because earth moving would be limited to partial removal of a man-made earthen berm, no impacts to historic landmarks, archaeological sites, or cultural places are anticipated.

3.1.8 Ecological Impacts

The MCFC PDT would be installed on a concrete pad approximately 12 inches thick. No impacts to flora and fauna, or threatened and endangered species would occur. Vegetation in the immediate proximity is limited to ivy installed for esthetic purposes.

3.1.9 Socioeconomic Impacts

The PDT would be located next to a newly constructed pyrolysis unit and a two level parking structure near a loading area. This PDT would be built adjacent to an existing medical facility. Construction labor required for the proposed PDT will be comprised of two riggers for ½ day duration, earth moving equipment for ½ day, two electricians for skid interconnects, an instrument engineer, two plumbers and two general sheet metal mechanics. The facilities routinely receive shipments of materials and have

delivery systems/transportation networks in place. No impacts are anticipated on the current transportation resources. Other hospital construction work would be taking place in parallel with the proposed PDT project.

3.1.10 Occupational Safety and Health

The proposed PDT construction and operation would be fully permitted and subjected to Occupational Safety and Health Administration regulations. Workers would be routinely trained in the proper use of equipment. The activities required by the proposed PDT do not represent any new health and safety hazards at the existing facility, nor do they represent conditions not generally associated with industrial and manufacturing facilities. Applicable engineering standards and codes will be adhered to.

Construction of the PDT would be conducted according to standard industry procedures to ensure that health, safety, and the environment are protected. Factory subsystem qualification testing would be conducted prior to shipment to the site.

3.1.11 Cumulative Impacts

MCFC power plants are currently under development specifically because of their minimal environmental impact. As noted in sections 3.1.1 through 3.1.10, the MCFC power plant should be equal to, or significantly better than, alternative systems in their impact on the environment. In fact, if these systems are used to replace existing systems, dramatic improvements in overall water and air quality can be achieved.

3.1.12 Summary of Impacts

The environmental effects associated with the Molten Carbonate Fuel Cell Product Development Test have been reviewed. This proposed PDT is expected to have no impacts on solid waste disposal, water quality, noise levels, floodplains, wetlands, ecological resources, historic areas, or socioeconomic resources. Impacts on air quality are expected to be positive. The PDT would benefit from environmental assessment studies and permits that are obtained as part of the overall medical center expansion. Because the PDT would be shop fabricated on skids and tested prior to shipment and installation at the site, there would be virtually no requirements for disturbing the site. No new site construction is needed for the deployment of the field test unit other than the specific mounting pads and electrical/mechanical interconnections.

3.2 No Action Alternative

Under the No Action Alternative, electricity generation would continue under current technology. There would be no improvement in current emission levels. The potential benefits of cleaner, more efficient technologies would not be realized.

4.0 LIST OF AGENCIES AND PERSONS CONSULTED

Mr. Jack Brunton
Manager of Environmental Services
San Diego Gas & Electric
110 West "A" Street
Suite 840
San Diego, CA 92112
"Environmental Requirements"

Mr. Vance Furukawa
Land Use Manager
Property Acquisition Department
Kaiser Permanente
Los Angeles, CA
(818) 405-6567
"Land Use Permit Requirements"

Mr. Grant Frost,
Manager, Environmental Permitting
San Diego Gas & Electric
101 Ash St.
San Diego, CA 92101
(619) 696-2000
"Air Pollution Control Board and EPA Regulations"

Mr. Mike Danna
Senior Planner
Land Planning Department
San Diego Gas & Electric
101 Ash St.
San Diego, CA 92101
(619) 696-2000
"Land Use Permit Requirements and San Diego Building Codes"

Mr. Al Figueroa
San Diego Gas & Electric
110 West "A" Street, Suite 840
San Diego, CA 92112
(619) 696-1924
"Site Description and Project Scoping"

Mr. Joseph Scroppo
Senior Project Manager
M-C Power Corporation
8040 S. Madison Street
Burr Ridge, IL 60521
(708) 986-8040 ext. 111
"Project Description"

REFERENCES

The following documents and contacts have been used to prepare this EA:

- The City of San Diego Air Pollution Control District (SDAPCD)
Rule 11 - Exemptions from Permit Requirements (Rev. Adopted: 3/27/90;
Rev. Effective: 5/28/90)
- The City of San Diego Air Pollution Control District (SDAPCD);
Regulation IV - Prohibitions (Effective 1/1/69)
Rule 50.1 - New Source Performance Standard (NSPS) and National
Emission Standard for Hazardous Air Pollutant (NESHAPS)
Visible Emissions Requirements (Effective 11/8/76)
Rule 51 - Nuisance
Rule 52 - Particulate Matter (Rev. Effective 9/21/83)
Rule 52.1 - New Source Performance Standard (NSPS) and NESHAPS
Particulate Matter Requirements (Effective 11/8/76)
Rule 53.1 - Scavenger Plants
Rule 53.2 - NSPS and NESHAPS Specific Containments Requirements
(Effective 11/8/76)
Rule 54 - Dust and Fumes (Rev. Effective 1/17/72)
Rule 68 - fuel-Burning Equipment - Oxides of Nitrogen (Effective 7/1/71;
Rev. 5/1/90)
- City of San Diego, Kaiser Parking Lot Addition, Environmental Quality
Division, File No. 76-04-37P, Negative Declaration
- City of San Diego, Kaiser Foundation Hospital, Conditional Use Permit,
Resolution No. 198854, January 8, 1970
- City of San Diego - Decision of the Zoning Administrator - Case No. 12662
Conditional Use Permit (Hearing) June 29, 1976

**DATE
FILMED**

7 / 29 / 93

END