NOTICE

**CERTAIN DATA
CONTAINED IN THIS
DOCUMENT MAY BE
DIFFICULT TO READ
IN MICROFICHE
PRODUCTS.**

INNOVATIVE CLEAN COAL TECHNOLOGY

Prepared by:

**Southern Company Services, Inc.
Birmingham, Alabama**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

INNOVATIVE CLEAN COAL TECHNOLOGY (ICCT)
DEMONSTRATION OF SELECTIVE CATALYTIC REDUCTION (SCR)
TECHNOLOGY FOR THE CONTROL OF NITROGEN OXIDE (NOx)
EMISSIONS FROM HIGH-SULFUR COAL-FIRED BOILERS

DOE Contract
DE-FC22-90PC89652

SCS Contract
C-91-000026

Quarterly Report No. 3
For the Period
January-March, 1991

July 1991

Prepared by:

Southern Company Services, Inc.
800 Shades Creek Parkway
Birmingham, Alabama 35209

Patents Cleared by Chicago on May 20, 1991

150E/VEI
1500E/VEI
01 JUL 21 PM 1991

LEGAL NOTICE

This report was prepared by Southern Company Services, Inc. pursuant to a cooperative agreement partially funded by the U.S. Department of Energy and neither Southern Company Services, Inc. nor any of its subcontractors nor the U.S. Department of Energy, nor any person acting on behalf of either:

- (a) Makes any warranty or representation, express or implied with respect to the accuracy, completeness, or usefulness of the information contained in this report, or that the use of any information, apparatus, method, or process disclosed in this report may not infringe privately-owned rights; or
- (b) Assumes any liabilities with respect to the use of, or for damages resulting from the use of, any information, apparatus, method or process disclosed in this report.

Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the U.S. Department of Energy. The views and opinion of authors expressed herein do not necessarily state or reflect those of the U.S. Department of Energy.

Section 1

SUMMARY

The objective of this project is to demonstrate and evaluate commercially available Selective Catalytic Reduction (SCR) catalysts from U. S., Japanese and European catalyst suppliers on a high-sulfur U. S. coal-fired boiler. SCR is a post-combustion nitrogen oxide (NO_x) control technology that involves injecting ammonia into the flue gas generated from coal combustion in an electric utility boiler. The flue gas containing ammonia is then passed through a reactor that contains a specialized catalyst. In the presence of the catalyst, the ammonia reacts with NO_x to convert it to nitrogen and water vapor.

Although SCR is widely practiced in Japan and Europe, there are numerous technical uncertainties associated with applying SCR to U. S. coals. These uncertainties include:

- (1) potential catalyst deactivation due to poisoning by trace metal species present in U.S. coals that are not present in other fuels.
- (2) performance of the technology and effects on the balance-of-plant equipment in the presence of high amounts of SO₂ and SO₃.
- (3) performance of a wide variety of SCR catalyst compositions, geometries and methods of manufacture under typical high-sulfur coal-fired utility operating conditions.

These uncertainties will be explored by constructing a series of small-scale SCR reactors and simultaneously exposing different SCR catalysts to flue gas derived from the combustion of high sulfur U. S. coal.

The demonstration will be performed at Gulf Power Company's Plant Crist Unit No. 5 (75 MW capacity) near Pensacola, Florida. The project will be funded by the U. S. Department of Energy (DOE), Southern Company Services, Inc. (SCS on behalf of the entire Southern electric system), and the Electric Power Research Institute (EPRI). SCS is the participant responsible for managing all aspects of this project.

The project is being conducted in the following three phases:

Phase I - Permitting, Environmental Monitoring Plan and Preliminary Engineering

Phase II - Detailed Design Engineering and Construction

Phase III - Operation, Testing, Disposition and Final Report

During this reporting period, DOE reviewed and provided comments on the Environmental Monitoring Plan (EMP). Radian Corporation, the projects's environmental subcontractor, and SCS are now addressing the issues raised by DOE's comments.

DynaGen, Inc., a fluid mechanics consulting subcontractor, constructed and performed flow modeling tests with a 1/2 scale model of the reactor inlet ducting. Two basic designs were selected for evaluation and optimization. As a result of testing, one design was selected for its slightly better velocity uniformity results and for its minimum space and cost requirements. In both designs resistance pipes were needed to improve velocity profile uniformity and these pipes may be used as the ammonia injection grid. These pipes were located in a horizontal arrangement during these tests. An additional test has been requested to examine the effect of orienting the pipes in a vertical arrangement.

Two status review and interface issue meetings were held with Gulf Power Engineering and Plant Crist personnel. The review of interface issues between the SCR pilot plant and Plant Crist primarily include electrical, steam, water, air and flue gas systems. Specific tie-in locations were tentatively identified for service water pumps, potable water, and the economizer bypass, and locations for the air compressors and ammonia storage were selected.

The flue gas/hot air disposition from the pilot plant was re-evaluated to alleviate the potential of exacerbating an existing cold end temperature problem. Several alternative flow schemes were evaluated. The one chosen for future detailed design is similar to the original concept in that flue gas and air are re-injected at the same points as originally designed. However, instead of using an ambient air supply, the air is now to be supplied from the Unit 5 forced draft fan discharge. This alternative presented the preferred method of integration of the pilot plant with Plant Crist Unit 5.

Another major interface issue being resolved is the electrical distribution system. The scope for electrical station service loading increased substantially as a result of pilot plant electrical demand growth, limitation of Plant Crist station service reserves, and re-arrangement of the Crist 115 KV bus. After re-defining the electrical distribution system, work began in specifying portions of the electrical equipment.

The detailed design engineering phase was initiated during this reporting period. Specifications for the rotary and heat pipe air preheaters were drafted, reviewed and revised, and released for bids. Bid packages from the vendors were received and evaluation is underway. Work also begun on venturi, fan, and control system specifications, and also on detailed platform design, control room internal partitioning, and extractive gas sampling system definition.

SCS reviewed information from the catalyst suppliers to finalize SCR reactor design. Although the exact same module dimensions could not be established among all the suppliers, the dimensions were similar enough that only small adjustments in clearance between the module and reactor are needed to allow reactors to be designed to the same size, i.e., for each of the small and large reactors.

FIGURE 1. BLOCK FLOW DIAGRAM OF SCR INSTALLATION.

Section 2

INTRODUCTION

The Innovative Clean Coal Technology (ICCT) Program is designed to demonstrate clean coal technologies that are capable of retrofitting or repowering existing facilities to achieve significant reduction in sulfur dioxide (SO_2) and/or nitrogen oxides (NO_x) emissions. The technologies selected for demonstration are capable of being commercialized in the 1990s and are expected to be more cost effective than current technologies.

This ICCT project is jointly funded by the U.S. Department of Energy, the Electric Power Research Institute (EPRI), and by Southern Company Services (SCS) on behalf of the entire Southern electric system. The project's objective is to demonstrate the selective catalytic reduction (SCR) process that removes nitrogen oxides (NO_x) from the flue gas of boilers that burn U.S. high-sulfur coal. The SCR technology involves the catalytic reduction of NH_3 , which is injected into the flue gas to react with NO_x contained in the flue gas to produce molecular nitrogen (N_2) and water vapor.

A simplified SCR process flow diagram with major equipment is shown in Figure 1. Specifically, hot flue gas leaving the economizer section of the boiler is ducted to the SCR reactor. Prior to entering the reactor, NH_3 is injected into the flue gas at a sufficient distance upstream of the reactor to provide for complete mixing of the NH_3 and flue gas. The quantity of NH_3 can be adjusted and it reacts with the NO_x from the flue gas. The flue gas leaving the catalytic reactor enters the air preheater where it transfers heat to the incoming combustion air. Provisions are made for ash removal from the bottom of the reactor since some fallout of fly ash is expected. Duct work is also provided to bypass some flue gas around the economizer during periods when the boiler is operating at reduced load. This is done to maintain the temperature of the flue gas entering the catalytic reactor at the proper reaction temperature of about 700°F . The flue gas leaving the air preheater goes to the electrostatic precipitator (ESP) where fly ash is removed. The ESP is part of the existing plant and is generally unaffected by the SCR system except as higher SO_2 content affects the electrical resistivity of the fly ash or if NH_4HSO_4 co-precipitates with the fly ash.

The SCR technology is in commercial use in Japan and western Europe on gas, oil, and on low-sulfur, coal-fired power plants. The first utility

applications of SCR catalyst technology started in Japan in 1977 for oil- and gas-fired boilers and subsequently in 1979 for coal-fired boilers. As of 1986, ninety utility boilers in Japan had been equipped with SCR catalyst technology including twenty-two coal-fired boilers. These coal-fired boilers represent a combined capacity in excess of 6500 MWe and are typically fired with a low-ash, low-sulfur coal.

In addition to Japanese experience, several countries in western Europe (most notably West Germany and Austria) have passed stringent NO_x emission regulations that have all but mandated the installation of SCR. Prior to commercial SCR installations in West Germany, utility companies demonstrated several types of SCR facilities in prototype demonstration programs similar to this ICCT project. Over 50 SCR pilot plants were built and operated in western Europe. These pilot plants ranged from 19 to 6200 SCFM and provided the data base that led to commercialization of the SCR technology in western Europe.

Previously completed U.S. work with the SCR process on utility boilers consists of three projects which were carried out in the late 1970s and early 1980s. One of these was carried out on a natural gas fired boiler by Southern California Edison. Another project consisted of a pilot test conducted for the EPA at Georgia Power's Plant Mitchell. This pilot plant treated a 1000 ACFM (0.5 MWe) slip stream of flue gas resulting from the combustion of low- to medium-sulfur coal. A third pilot-scale project, carried out at the Public Service Company of Colorado's Arapaho Station treated a 5000 ACFM (2.5 MWe) slip stream of flue gas resulting from the combustion of U.S. low-sulfur coal.

Although SCR is widely practiced in Japan and Europe, there are numerous technical uncertainties associated with applying SCR to U.S. coals. These uncertainties include:

- (1) potential catalyst deactivation due to poisoning by trace metal species present in U.S. coals that are not present in other fuels.

- (2) performance of the technology and effects on the balance-of-plant equipment in the presence of high amounts of SO_2 and SO_3 .
- (3) performance of a wide variety of SCR catalyst compositions, geometries and methods of manufacture under typical high-sulfur coal-fired utility operating conditions.

These uncertainties will be explored by constructing a series of small-scale SCR reactors and simultaneously exposing different SCR catalysts to flue gas derived from the combustion of high sulfur U.S. coal.

The first uncertainty above will be handled by evaluating SCR catalyst performance for two years under realistic operating conditions found in U.S. pulverized coal utility boilers. The deactivation rates for the catalysts exposed to flue gas from high sulfur U.S. coal will be documented to determine accurate catalyst life, and thus, accurate process economics.

The second uncertainty above will be explored by performing parametric testing and through the installation/operation of air preheaters downstream of the larger reactors. During parametric testing, operating conditions will be adjusted above and below design values to observe deNO_x performance and ammonia slip as functions of the change in operating conditions. Air preheater performance will be observed to evaluate effects from SCR operation upon heat transfer, and therefore, upon boiler efficiency.

The third uncertainty is being handled by using honeycomb- and plate-type SCR catalysts from U.S., Japan and Europe of various commercial composition. Results from the tests with these catalysts will expand our knowledge of performance on a variety of SCR catalysts under U.S. utility operating conditions with high-sulfur coal.

The intent of this project is to demonstrate commercial catalyst performance, proper operating conditions, and catalyst life for the SCR process. This project will also demonstrate the technical and economic viability of SCR while reducing NO_x emissions by at least 80%.

The project will be conducted at Gulf Power Company's Plant Crist Unit 5, a commercially operating 75 MW unit, located in Pensacola, Florida, on U. S. coals with a sulfur content near 3.0%. Unit 5 is a tangentially-fired, dry

bottom boiler, with a hot and cold side ESPs for particulate control. The SCR process to be used in this demonstration will be designed to treat a slip-stream of flue gas and will feature multiple reactors installed in parallel. With all reactors in operation, the maximum amount of combustion flue gas that can be treated is 17,400 standard cubic feet per minute (scfm) which is roughly equivalent to 8.7 MWe.

The proposed SCS facility is a slip-stream SCR test facility consisting of three 2.5 MWe (5000SCFM) SCR reactors and six 0.20 MWe (400SCFM) reactors that will operate in parallel for side-by-side comparisons of commercially available SCR catalyst technologies obtained from vendors throughout the world. Figure 2 presents a simplified process flow diagram for the proposed facility. The large (2.5 MWe) SCR reactors will contain commercially available SCR catalysts as offered by SCR catalyst suppliers. These reactors will be coupled with small-scale air preheaters to evaluate the long-term effects of SCR reaction chemistry on air preheater deposit formation and the deposits' effects on air preheater. The small reactors will be used to test additional commercially available catalysts. This demonstration facility size will be adequate to develop performance data to evaluate SCR capabilities and costs that are applicable to boilers using high-sulfur U.S. coals.

The demonstration project is organized into three phases: (1) Phase I - Permitting, Environmental Monitoring Plan and Preliminary Engineering; (2) Phase II - Detail Design Engineering and Construction; and (3) Phase III - Operation, Testing, Disposition, and Final Report. The cooperative agreement was signed June 14, 1990, and the project completion date is now projected to be in the second quarter of 1995. The total estimated project costs are \$15,574,355. The co-funders are SCS (\$6,049,017), DOE (\$7,525,338), and EPRI (\$2,000,000).

FIGURE 2. PROTOTYPE SCR DEMONSTRATION FACILITY-PROCESS FLOW DIAGRAM.

Section 3 PROJECT DESCRIPTION

Within the three phases of the project, the following tasks will be conducted to effectively demonstrate the SCR process:

Phase I - Permitting, Environmental Monitoring Plan and Preliminary Engineering

- Task 1.1.1 - Prototype Plant Permitting Activities
- Task 1.1.2 - Develop Environmental Monitoring Program
- Task 1.1.3 - Preliminary Engineering
- Task 1.1.4 - Engineering and Construction Contracts Scope Development
- Task 1.1.5 - Project Management and Reporting

Phase II - Detail Design Engineering and Construction

- Task 1.2.1 - Detailed Design Engineering
- Task 1.2.2 - Construction
- Task 1.2.3 - Operation Staff Training
- Task 1.2.4 - Planning for Detailed Testing
- Task 1.2.5 - Start-Up/Shakedown
- Task 1.2.6 - Project Management and Reporting

Phase III - Operations, Testing, Disposition and Final Report

- Task 1.3.1 - SCR Demonstration Facility Operations and Maintenance
- Task 1.3.2 - Process Evaluation
- Task 1.3.3 - Environmental Data Management and Reporting
- Task 1.3.4 - Economic Evaluation
- Task 1.3.5 - Dismantling/Disposition
- Task 1.3.6 - Project Management and Reporting

Section 4

PROJECT STATUS

Progress during January - March, 1991, is summarized below for each of the on-going tasks in the Scope of Work.

PHASE I - PERMITTING, ENVIRONMENTAL MONITORING PLAN AND PRELIMINARY ENGINEERING

Task 1.1.2 - Develop Environmental Monitoring Program

The Environmental Monitoring Plan (EMP) was reviewed by DOE and comments were provided to Radian Corporation, the project's environmental subcontractor, and SCS. Radian and SCS are currently addressing the issues raised by DOE's comments in order to finalize the EMP.

Task 1.1.3 - Preliminary Engineering

During this reporting period, DynaGen, Inc., a fluid mechanics consulting subcontractor, constructed and completed flow modeling tests with a 1/2 scale model of the reactor inlet ducting. Two basic design were selected for evaluation and optimization using experimental model testing. The two model designs, including testing arrangements, are shown in Figures 3 and 4. Testing was completed using material from one of the catalyst vendors as the dummy layer. The model design no. 1 achieved the best velocity uniformity results for the minimum space and cost. About 96% of the results were within +/- 10% of the average velocity and 99% of the results were within +/- 15% of the average. Resistance pipes were needed to improve velocity profile uniformity and these pipes should be used as the ammonia injection grid. An additional test has been requested to examine the effect of orienting the resistance pipes in a vertical arrangement instead of the previously tested horizontal arrangement. This testing will be conducted during the next reporting period. A memorandum describing the complete experimental results for model design no.1 and partial results for the reactor inlet model design no. 2 was issued as a preliminary report and is attached in Appendix A.

Figure 3

MODEL GEOMETRY AND VELOCITY TRAVERSE LOCATIONS
FOR REACTOR INLET MODEL DESIGN NO. 1
(Model Scale Factor = 2.0)

Instrumentation Locations

1. Pitot tube
40 points, 8 radii, 5 points
2. Hot wire anemometer
96 points (8 x 12)
3. Hot wire anemometer
288 points (12 x 24)
4. Hot wire anemometer
288 points (12 x 24)

Figure 4

Two status review and interface issue meetings were held with Gulf Power Engineering and Plant Crist personnel. The review of interface issues between the SCR pilot plant and Plant Crist primarily included electrical, steam, water, air and flue gas systems. Specific tie-in locations were tentatively identified for service water pumps, potable water, and the economizer bypass, and locations for the air compressors and ammonia storage were selected at the Crist Unit 5 site.

As stated in the previous progress report, one of the major changes in the conceptual design regards the disposition of flue gas and hot air from the pilot plant air heaters. The original process flowsheet called for the pilot plant flue gas, extracted upstream of the hot-side ESP, to be reinjected upstream of the cold-side ESP. The pilot plant hot air from the air heaters would be injected into the hot combustion air exiting the plant air heater. Extracting flue gas in front of the Unit 5 air heater for the pilot plant was calculated to exacerbate an existing problem with cold end temperatures. To resolve this problem, several alternative process flow options were identified. Three of many alternatives considered are shown in Figures 5 through 7. In summary, after much review and discussion with Gulf Power, the option in Figure 7 was selected. In comparison with Figure 5, the Figure 7 option is much simpler, eliminating the need for a baghouse and booster fan, with their increased requirements in ash handling design and air requirements for pulsing bags. The flue gas and air are re-injected at the same points as originally designed and the State of Florida had already approved this design. Options in Figures 6 and 7 are similar except the air supplied to the pilot plant air preheaters is provided from the Unit 5 forced draft fan discharge in Figure 7 versus from ambient air in Figure 6. However, Gulf Power preferred the method of integration of the pilot plant with Unit 5 depicted in Figure 7. The option in Figure 6 would make the Unit 5 FD fan operation more reactionary to the pilot plant air fans and potentially present more operational problems to the Unit 5. Figure 7 was viewed as having less effect on Unit 5 operation. Detailed design is therefore continuing on the basis of the flow scheme depicted in Figure 7.

Another major interface issue being resolved is the electrical distribution system. The original design was rather simple and based on using station service from Gulf through an existing 4160 volt switchgear as the main source

FIGURE 5
DOE/SCR PROJECT
AIR AND FLUE GAS DISPOSITION OPTION

FIGURE 6
DOE/SCR PROJECT
AIR AND FLUE GAS DISPOSITION OPTION

FIGURE 7
DOE/SCR PROJECT
AIR AND FLUE GAS DISPOSITION OPTION

feed and tie point for the entire SCR electrical station service. This source fed two transformers, with each transformer feeding a 600 volt motor control center (MCC), and each MCC had a distribution capability of five frames.

The scope for electrical station service loading has increased substantially. The primary reasons for the scope changes are the growth of electrical demands for the pilot plant over original design, limitation of Plant Crist station service reserves, and the re-arrangement of the Crist 115 KV bus. The scope changes include the following: (a) Replace the 600 volt system with a 480 volt low voltage distribution system, which is state-of-the-art and a more stock or "off-the-shelf" equipment. (b) Add an entire 115 KV system consisting of cable bus, transformer, switcher or circuit breaker, and metering and protective relaying. (c) Add a medium voltage 4160 volt distribution system, consisting of 4 feeds with 4 transformers and 4 MCCs instead of the single 4160 volt tie breaker per the original design. (d) Add several variable speed motors and controllers (not covered in the original design). (e) Increase requirements of power and control cables, conduits, and cable trays.

The SCR process Design Data Book continued to be prepared and minor revisions to previously drafted drawings were made. As a result of the major design changes and ongoing interface issues resolution, issuing the Design Data Book for review was postponed to incorporate the latest revisions possible. The Design Data Book will be released for review during the next reporting period.

Task 1.1.4 - Engineering and Construction Contracts Scope Development

Several discussions were held between SCS and Gulf Power in defining work to be performed in project construction and contracting construction scope packages. Proposed construction contract scope packages were submitted by SCS and are being reviewed by Gulf Power.

Task 1.1.5 - Project Management and Reporting

The MIS, developed for tracking overall budget and schedule information, was used to monitor budget and schedule and to help fulfill DOE reporting requirements. Monthly progress reports were submitted to DOE. Coordination meetings with Design Engineering were conducted on a weekly basis. Two status

review and plant interface issue meetings were held with Gulf Power, January 9 and February 15.

PHASE II - DETAIL DESIGN ENGINEERING AND CONSTRUCTION

Task 1.2.1 - Detailed Design Engineering

The detailed design engineering phase was initiated during this reporting period. Specifications for the rotary and heat pipe air preheaters were drafted, reviewed and revised, and released for bids. Bid packages from the vendors were received and evaluation is underway. Work also begun on specifications for venturis, fans, portions of the electrical equipment, and instrumentation and controls systems. Other Phase II work that was initiated included detailed platform design, control room internal partitioning, and extractive gas sampling system definition.

Information from the catalyst suppliers regarding their catalyst module sizes was reviewed and follow-up information was requested for the purpose of determining a common size reactor for each of the large and small modules and for defining the reactor internal dimensions. Although the exact same module dimensions could not be established among all the suppliers, the dimensions were so similar that only small adjustments in clearance between the module and reactor are needed to allow reactors to be designed to the same size.

Task 1.2.6 - Project Management and Reporting

Weekly coordination meetings were held with Design Engineering. The process design changes made in this and the previous reporting period and the requirements for resolving interface issues with pilot plant and Plant Crist Unit 5 have adversely affected the project schedule. The schedule has been revised and the major changes include the following: (a) Construction start date has slipped to January 1992; (b) Pilot plant start-up/shakedown has changed from the original estimated date of June 1992 to November 1992; (c) The beginning of process testing and evaluation has slipped from August 1992 to January 1993, with conclusion of the project now expected to extend through May 1995. For further details see the revised Milestone Plan shown in Figure 8. The cost impacts from scope and design revisions are also being estimated and a revised cost estimate is expected to be completed during the next reporting period.

1997

1997

1997

1997

1997

Section 5
PLANNED ACTIVITIES

During the April - June, 1991 quarter, the following activities are planned:

- o Issue the draft Design Data Book to DOE for review.
- o Complete additional reactor flow modeling with resistance piping (also ammonia injection grid) in vertical arrangement, as opposed to originally-tested horizontal configuration.
- o Complete the following portions of Phase II, detailed engineering design:
 1. Award contract for air preheaters (rotary and heat pipe).
 2. Develop specifications, issue inquiries for vendor bids, complete evaluations of vendor bid packages, and award contract for fans.
 3. Develop specifications, issue inquiries for vendor bids, and complete evaluations of vendor bid packages for venturists.
 4. Develop specifications and issue inquiries for the following: bypass ductwork heat exchangers; air and flue gas electric heaters; cyclones; air compressors; control systems; extractive gas sampling system; and portions of the electrical distribution system.
 5. Begin development of specifications for the design of the reactor vessel and ammonia storage and delivery system.
- o Hold project review meeting with DOE.

APPENDIX A

Preliminary Results from Dynagen
for Reactor Inlet Model Designs

MEMORANDUM ON TEST RESULTS FOR REACTOR INLET MODEL DESIGNS

SCR Pilot Plant Project
Contract No. 195-89-044

DynaGen, Inc.
Gerald B. Gilbert
February 27, 1991

1.0 INTRODUCTION

During a meeting at Southern Company Services in early December, 1990, the large reactor inlet piping system was discussed and two basic designs were selected for evaluation and optimization using experimental model testing. The two basic model designs are shown on Figures 2A and 2B in model dimensions for a one-half scale model. The velocity uniformity objective at the outlet of the dummy core (Location 4 on Figures 1A and 1B) is all data points with $\pm 10\%$ of average velocity.

This memorandum presents the complete experimental results for the reactor inlet model design no. 1 (Figure 1A) and partial results for the reactor inlet model design no. 2 (Figure 1B).

2.0 TEST DESCRIPTION

2.1 Test Rig Description

The test rig arrangement for both model designs is similar as shown on Figures 1A and 1B. Both rigs start in a 12" diameter circular pipe with a flow straightening grid and a 63% perforated plate to achieve a uniform flow approaching the model reactor inlet ducts. This model inlet pipe simulates the pilot plant pipe with a flow measurement nozzle located approximately where the flow straightener is located.

At the outlet of each model inlet duct is located a dummy core constructed from actual core material supplied to us by the W.R. Grace Company at the request of Southern Company Services. The core in the model test rig is constructed of actual core pieces 6" x 6" x 12" long arranged in a 3 x 4 pattern in an 18" x 24" cross-section and two rows deep for a total of 24" length. We draw air through this model reactor inlet duct and core using our laboratory blowers.

2.2 Instrumentation

The following instrumentation was used to measure data and make observations on the model:

1. Flow Measurement

- A 20" diameter pipe system with a 10" diameter orifice was used to measure total flow rate.

2. Velocity Profiles and Static Pressure

- A standard "L" shaped Prandtl type pitot tube was used for velocity measurements at Location 1 and for all pressure measurements. The pitot tube was connected to one or more pressure transducers, a data acquisition system, and a computer for on-line data recording, reduction, and tabular printout.
- A hot wire anemometer was used to measure velocity profiles at Locations 2, 3, and 4 near the core.

3. Observations

- Smoke filament and tufts of yarn were used to visualize the gas flow in the ducts.

The location of the measurement stations for velocity and pressure are shown on Figures 1A and 1B. The measurements taken at each station and the number of data points are specified on the same figures.

2.3 Data Reduction and Scaling

1. Orifice Flow Rate

Orifice flow calculations are carried out using equations and orifice coefficients developed by ASME and documented in their publications.

2. Velocity Values

Velocity is calculated from the velocity head sensed by the pitot tube, measured by the pressure transducer, and recorded by the computer. The velocity head is:

$$VH = \frac{\rho V^2}{2g_o} \quad (5.21)$$

where: VH = velocity head (inches of water);
 V = velocity data point (fps);
 ρ = air density (lbm/ft³); and
 g_o = 32.2 (ft · lbm/lbf · s²).

The density is calculated from the measured barometric pressure, local static pressure, and the gas temperature using the perfect gas equation. For the hot wire anemometer, the velocity is read directly in feet per minute and recorded by the data acquisition system.

3. RMS Velocity Uniformity

The root mean square velocity uniformity value listed on the velocity data reduction sheets is similar to a standard deviation. It is defined as follows:

$$\text{delta } V_{RMS} = \left(\frac{\sum (V/V_{AVG} - 1)^2}{N} \right)^{1/2}$$

where: V = velocity data point in fps;
 V_{AVG} = average of all velocity values in fps; and
 N = number of data points.

In effect, it is the standard deviation of velocity about an average velocity, expressed as a fraction of the average velocity. For a value of zero, the flow would be perfectly uniform with all data points equal.

4. Velocity in Bands

For each velocity test, the percentage of data in bands of $\pm 10\%$, $\pm 15\%$, $\pm 25\%$, and $\pm 40\%$ about the average is calculated and printed on the computer data sheet at the bottom (see Figure 9).

5. Stagnation Pressure Loss

Static pressure data is measured in inches of water at six points in each cross-section with the pressure transducer. The average flow velocity head for a cross-section is determined by:

$$VH = \frac{\rho V_o^2}{2g_o} \quad (5.21)$$

where: VH = velocity head (inches of water);
 ρ = air density (lbm/ft³);
 V_o = cross-section flow rate divided by the cross-sectional area (fps); and
 g_o = 32.2 (ft · lbm/lbf · s²).

Total pressure at each cross-section is calculated as:

$$P_T = P_s + VH$$

where: P_T = total pressure (inches of water);
 P_s = measured static pressure (inches of water); and
 VH = velocity head (inches of water).

The field value of total pressure loss between two cross-sections is calculated as:

$$(\Delta P_T)_{FIELD} = (\Delta P_T)_{MODEL} \times \frac{(VH)_{FIELD}}{(VH)_{MODEL}}$$

2.4 Model Test Condition

The field flow condition being simulated on the model is taken from the process flow diagram dated September 27, 1990 at point 40:

Flow Rate = 12,074 ACFM
 Temperature = 700°F
 Gas Density = 0.0344 lb/ft³

The model flow condition at the same velocity will be:

Flow Rate = 3,018.5 ACFM
 Temperature = ~75°F
 Air Density = 0.0742 lb/ft³

Model pressure losses will be larger by the ratio of model air density to pilot plant gas density equal to 2.16.

3.0 TEST RESULTS FOR REACTOR INLET MODEL DESIGN NO. 1

The geometry of model design no. 1 is shown on Figure 2A. It is the shortest, most compact reactor inlet duct under evaluation and it includes provision for insertion of expansion spacers to improve velocity uniformity by allowing more axial distance. Model design no. 1 includes the following elements:

1. A transition from a circle to a square cross-section of the same dimension. This provides a 27% area expansion.
2. A two-dimensional diffuser to expand from 12" to 18" (model) in a horizontal plane. This provides a 50% area expansion in a diffuser with three internal baffles forming four diffuser cells of about 7° included angle.
3. A 90° expanding elbow with 11 turning vanes to expand from 12" to 24" (model). This is a 100% area expansion. All vanes will have a flow separation on the convex side of the vane.
4. The elbow outlet cross-section of 18" x 24" leads directly to the model core section.

3.1 Test of the Base Geometry for the Reactor Inlet Duct

The velocity profile in the inlet pipe at Location 1 (Figure 1A) was measured for several combinations of flow control devices from an open pipe to the geometry shown on Figure 1A which was selected for all subsequent tests. The velocity profile data for this inlet geometry is shown on Figure 4 to be uniform and symmetric. This profile will probably be quite typical of what will develop in the field pipe system where a flow measurement nozzle will be located approximately where the model flow straightening grid is located.

The velocity profile at Location L2 is shown on Figures 5 and 6 for Test 10. Figure 5 shows the measured velocity profile data (8 x 12 grid) in feet per minute at the top and in percent of average velocity at the bottom. The RMS value of 0.312 and percent of average velocity data in four bands are listed in the lower left corner. Figure 6 shows the same percent of average velocity data and isovelocity contours with the side of the traverse nearest the inner bend of the elbow located on the horizontal axis. The flow comes out of the paper for all data presented. The velocity profile uniformity at Location 2 is much less uniform than at Location 1 because the flow area expands from a 1' circle to a 1' square and then passes through the diffuser that expands the area to 18" x 24" cross-section. The high velocities are in the center of the duct (maximum of 46.8% above average) and low velocities are all around the edges. Flow out of the circle to square transition is very low in the four corners. The flow out of the diffuser does not

show any reversed flow regions but there are some visible regions of low velocity. The velocity profile between Figure 5 and Figure 6 has been rotated 90° so that all isovelocity plots are oriented the same way and can be compared directly.

The isovelocity profile (Figure 7) at the core inlet (Location 3) shows a slightly better profile than Location 2 after passing through the 90° expanding area elbow. However, velocities range from 48% above average to 70% below average. The RMS and velocity data in bands of $\pm 10\%$ and $\pm 15\%$ are shown on Table 1 for Test 10 as 0.240, 30.9%, and 45.5%. This is a long way from the objective.

The isovelocity profile (Figure 8) at the core outlet (Location 4) shows a greatly improved uniformity with a maximum value of 18% above average and 31% below average. The RMS and velocity data in bands of $\pm 10\%$ and $\pm 15\%$ are shown on Table 1 for Test 10 as 0.086, 77.1%, and 91.3%. The improvement is caused by the resistance of the 24" long core which is 0.713 inches of water for measured model flow conditions and 0.320 inches of water for scaled field flow conditions. This test shows that 23% of the data are outside of the $\pm 10\%$ uniformity objective and 8.7% are outside of $\pm 15\%$ of average velocity.

Test 11 geometry is the same as Test 10 except that a 12" model spacer was added between the elbow outlet and the core. Velocity traverses were taken on both ends of the core at L3 and L4 and the data and isovelocity profiles are presented on Figures 9, 10, 11, and 12. As summarized on Table 1, only a small improvement occurred bringing the velocity uniformity at the core outlet to RMS equal to 0.078 and 81.9% of data within $\pm 10\%$ of average velocity.

3.2 Test of Modified Reactor Inlet Duct Geometry

The velocity profiles for the base duct geometry show that the velocity is too high in the center region of the duct and too low around the sides for traverse locations L2, L3, and L4. The biggest problem and greatest profile non-uniformity is caused by the transition from a 1' circle to a 1' square. Peak velocities at the outlet of the gradual diffuser (Location 2, Figure 5 data) show velocities still greater than 50 fps, more than three times what is desired at the core inlet and outlet. The only practical way to reduce these velocities and distribute the flow more uniformly in the short duct path of the model design no. 1 is to use a resistance device that will have the following characteristics:

1. reasonable pressure loss while creating the required velocity profile improvement at the core;
2. simple and low cost design;

3. resistance to erosion; and
4. could be part of the ammonia injection system requirements.

The type of resistance that meets these requirements the best is a set of pipes installed across the duct cross-section at a location where the velocity profile is poor and must be improved downstream. The location selected was immediately at the outlet of the circle to square transition which also corresponds to a possible ammonia injection cross-section.

Table 1 summarizes data for four tests with three different pipe resistances and shows what figures present the detailed geometry and detailed velocity profiles. The use of a pipe resistance has progressively increased the diffuser outlet (Location 2) uniformity from 16.7% of data within $\pm 10\%$ for Test 10 and 11 to 87.5% of data within $\pm 10\%$ for Test 16 and 17. At the same time, the same values at Location 3 have improved from 41.3% for Test 11 to 93.8% for Test 16 and at Location 4 have improved from 81.9% for Test 11 to 95.5% for Test 17. This is probably as close as we can hope to get to the objective with a two foot dummy core. Further improvement can be obtained by increasing from 2' to 3' or more of dummy core length.

The difference between Tests 16 and 17 geometries is that Test 16 has the 12" model spacer in place between the elbow and the core whereas Test 17 does not have the spacer in place. When the spacer is removed, the uniformity at Location 3 (core inlet) gets a little worse but the uniformity at Location 4 (core outlet) actually gets a little better.

For these two tests (16 and 17) at Location 3 (core inlet), the velocities below 90% of average are near the duct sides that correspond to the inner and outer walls of the 90° duct elbow. Only Test 17 without the 12" spacer shows low velocities near the inner bend because the traverse station 3 is 12" closer to the vanes in the elbow. These are the values that make the uniformity worse for Test 17 at Location 3. The high velocities occur mostly near one side wall. For Location 4 (core outlet), the low velocities occur near the outside of the elbow and the high velocities occur near the same side wall as Location 3.

3.3 Pressure Loss Results for Reactor Inlet Model Design No. 1

Pressure measurements were taken for all of the tests at the four test locations shown on Figure 1A and reduced to stagnation pressure loss as described in Section 2.3. These tests showed the following results when scaled to field operating conditions using the field condition in Section 2.4:

1. The reactor core material showed a field stagnation pressure loss of 0.160 inches of water per foot of core material equivalent to 5.57 inlet face velocity heads loss per foot of core length.

2. The 90° vaned expanding area elbow showed a field stagnation pressure loss of 0.043 inches of water.
3. The duct and pipe resistances between Locations 1 and 2 showed the following field stagnation pressure loss values:

<u>Test</u>	<u>deltaP_T (inches of water)</u>
10, 11	0.081"
12	0.219"
14	0.326"
16, 17	0.331"

4.0 TEST RESULTS FOR REACTOR INLET MODEL DESIGN NO. 2

The geometry of model design no. 2 is shown on Figure 2B. It is slightly longer in the horizontal direction but considerably taller in the vertical direction because of the inclusion of a second diffuser. Model design no. 2 includes the following elements:

1. A constant area transition from a 12" diameter circle to a 12" x 9-1/2" rectangle (model).
2. A two dimensional diffuser to expand from 12" to 18" (model) in a horizontal plane. This provides a 50% area expansion in a diffuser with three internal baffles forming four diffuser cells of about 7° included angle.
3. A 90° constant area elbow with five turning vanes.
4. A two dimensional diffuser to expand from 9.5" to 24" (model) in a vertical direction. This provides a 153% area expansion in a diffuser with three internal baffles forming four diffuser cells of about 7° included angle.
5. The diffuser outlet cross-section of 18" x 24" (model) leads directly to the model core section.

4.1 Test of the Base Geometry for the Reactor Inlet Duct

The inlet pipe velocity profile at Location 1 (Figure 1B) is the same as presented on Figure 4 for model design no. 1. The data for the other traverse stations is presented on Table 2, Test 19 and on Figures 27, 28, and 29. Isovelocity plots have not been prepared yet but will be included in the complete task report to follow soon. In the meantime, I have sketched them by hand on the data figures.

The velocity profile data at the outlet of the first diffuser (Location 2, Figure 1B) is presented on Figure 27 and summarized on Table 2. As compared to model design no. 1, Test 10, the profile uniformity is much better as shown below:

	<u>Test 10</u> <u>Model Design No. 1</u>	<u>Test 19</u> <u>Model Design No. 2</u>
RMS	0.312	0.14
$\pm 10\%$	16.7%	43.8%
$\pm 15\%$	29.2%	64.6%

The uniformity measures have been improved by a factor of two. However, peak velocities in the center are still as much as 28% above average and low velocities near the sides as much as 33% below average. The improvement in velocity profile is due to the use of a constant area transition for Test 19 and an increasing area transition for Test 10. The profile may need further improvement at Location 2.

The velocity profile (Figure 28) at the core inlet (Location 3) is also significantly better for Test 19, model design no. 2, as compared to Test 10 for model design no. 1, and slightly better than Test 11 as shown below:

	<u>Model Design No. 1</u>		<u>Model Design No. 2</u>
	<u>Test 10</u>	<u>Test 11</u>	<u>Test 19</u>
RMS	0.240	0.164	0.141
$\pm 10\%$	30.9%	41.3%	51.0%
$\pm 15\%$	45.5%	64.2%	72.2%

High velocities appear in the center region for Test 19 and low velocities around the sides. Also, the baffle locations that run side to side on Figure 28 are also evident in the data as strips of low velocity.

The velocity profile (Figure 29) at the core outlet (Location 4) is also better for Test 19, model design no. 2, as compared to Tests 10 and 11 for model design no. 1 as shown below:

	<u>Model Design No. 1</u>		<u>Model Design No. 2</u>
	<u>Test 10</u>	<u>Test 11</u>	<u>Test 19</u>
RMS	0.086	0.078	0.061
$\pm 10\%$	77.1%	81.9%	87.8%
$\pm 15\%$	91.3%	94.4%	98.6%

However, the Test 19 results without any added resistance does not reach the objective of all data within $\pm 10\%$ of the average and is not as good as Test 17 for model design no. 1 with an added pipe resistance. High velocities are in the center region of the cross-section and low velocities are near the wall at the outside of the elbow.

A visual inspection of the flow pattern out of the second diffuser just above the core inlet shows low velocities in the corners of all four diffuser cells and small flow separations ($\sim 2''$ model) in the center two cells along the wall to the left as you look at the data on Figure 29. These separations disappear as the flow moves toward the core inlet. Since the velocity data along this wall is within the $\pm 10\%$ limits at the reactor outlet, these small flow separations do not affect the uniformity results.

4.2 Test of Modified Reactor Inlet Duct Geometry

The high and low velocity zones at traverse locations 3 and 4 are traceable back to the traverse location 2. Since this is the same situation as existed for the model design no. 1 data in Section 3.1, we elected to use a pipe resistance at the outlet of the circle to rectangular constant area transition for the same reasons as discussed in Section 3.2.

The results for these tests are summarized on Table 2 for three configurations of pipe resistances. The detailed geometry will be specified in the final report but the number of pipes and the average percent open area are listed on Table 2. Progressive improvement in the velocity profile at Location 2 provided an initial improvement at Locations 3 and 4 but then no significant further improvement. In fact, we achieved a Location 2 profile uniformity for Test 22 that was as good as Test 16 and 17 for model design no. 1 but the velocity uniformity for model design no. 2 at Locations 3 and 4 never did equal the results for model design no. 1.

The velocity profile data for Test 22, Locations 2, 3, and 4 is presented on Figures 30, 31, and 32 respectively. Basically, the difference is due to the flow boundary layers that form on the diffuser baffles which lower velocities near the baffles and raise velocities in the center of the diffuser cells. The baffles are clearly shown as horizontal strips of below average velocity on Figures 31 and 32. This profile could be improved with the addition of some pipe resistance elements at the outlet of the second diffuser or possibly with the addition of pipes or deflector vanes between the elbow and the second diffuser inlet. I would expect that the first approach would provide better results.

5.0 CONCLUSIONS FROM EXPERIMENTAL EVALUATION OF TWO REACTOR INLET MODELS

5.1 Model Design No. 1

1. This is the minimum height and length design and is a more practical field unit configuration.
2. The initial base design with elbow vanes and diffuser baffles but no resistance pipes was very poor.
3. Resistance pipes are needed at the outlet of the circle to square transition to improve velocity profile uniformity.
4. The best velocity uniformity results achieved for Test 17 were $RMS = 0.049$, 95.5% of data with $\pm 10\%$ of average, and 99.0% of data within $\pm 15\%$.
5. This velocity uniformity could be improved further by:
 - a. adding more dummy core length;
 - b. using unequally spaces vanes; or
 - c. adding a second resistance at the diffuser outlet or the elbow outlet.
6. The pressure loss is low from Location 1 in the inlet pipe to Location 4 at the core outlet and equal to about 0.69 inches of water at field operating conditions.
7. The pipe resistance can be used as the grid for the ammonia injection nozzles.
8. The use of a 12" model (24" field) spacer between the elbow outlet and dummy core inlet gives better results above the dummy core but worse results at the dummy core outlet.

5.2 Model Design No. 2

1. The length of this design is at a practical minimum but the elevation is about 66 field inches more than design no. 1.
2. The initial base design with elbow vanes and diffuser baffles but no resistance pipes was better than model design no. 1 without resistance pipes but not as good as the best configuration of model design no. 1 with resistance pipes.

3. Resistance pipes are needed at the outlet of the circle to rectangular transition to improve velocity profile uniformity.
4. The best velocity uniformity results achieved for Test 21 were $RMS = 0.055$, 91.3% within $\pm 10\%$ of average and 99.0% within $\pm 15\%$ of average. This is almost as good as model design no. 1.
5. This velocity uniformity could be improved further by:
 - a. adding more dummy core length; or
 - b. adding resistance pipes to the outlet of the second diffuser.
6. The pressure loss is about the same as model design no. 1 but data has not been reduced in final numbers yet.
7. The pipe resistance can be used as the grid for the ammonia injection nozzles.

5.3 General Conclusions

1. Model design no. 1 achieves the best velocity uniformity results at the core outlet for the minimum space and cost although the objective of all data within $\pm 10\%$ of average is not achieved.
2. The pipe resistance at the duct transition outlet should be used as the ammonia injection grid. A grid of 25 nozzles could be used conveniently, five on each of five pipes. We may want to change the horizontal diffuser to five cells rather than four.
3. The best way to further improve uniformity would be to add one or two additional feet of dummy core to the two feet of core tested in the model.

6.0 OPTIONS LEADING TO A FINAL REACTOR INLET DESIGN

1. Accept the velocity uniformity results achieved with Test 17 of model design no. 1 and a 2' long dummy core.
2. Use model design no. 1, Test 17 geometry but add one or more feet of dummy core to improve the velocity uniformity some more.
3. Continue tests on model design no. 1 to see if velocity uniformity at the core inlet can be improved by:

- a. unequal spacing of elbow vanes; or
- b. adding a second resistance at the diffuser outlet or the elbow outlet.

Table 1

SUMMARY OF VELOCITY PROFILE TEST RESULTS
FOR MODEL REACTOR INLET DESIGN NO. 1 FOR
SCR PILOT PLANT

Test No.	Description of Geometry	Geometry Figures	Location 2			Location 3			Location 4			Data Figures
			RMS	+10%	+15%	RMS	+10%	+15%	RMS	+10%	+15%	
			(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	
10	1. Open design with elbow and diffuser vanes	1A,2A	0.312	16.7	29.2	0.240	30.9	45.5	0.086	77.1	91.3	5,6,7,8
	2. No spacer between elbow and core											
11	1. Open design with elbow and diffuser vanes	1A,2A	0.312	16.7	29.2	0.164	41.3	64.2	0.078	81.9	94.4	5,6,9,10,11,12
	2. Spacer between elbow and core, 12" model, 24" pilot plant											
12	1. Open design with elbow and diffuser vanes plus 12" model spacer	1A,2A,3	0.137	47.9	74.0	0.081	79.5	96.2	0.058	90.3	99.3	13,14,15
	2. Four 1" dia- meter model dowels equally spaced, 66.7% open											

Table 1 (Continued)

Test No.	Description of Geometry	Location 2		Location 3		Location 4		Data Figures				
		Geometry Figures	RMS ±10% (%)	±15% (%)	RMS ±10% (%)	±15% (%)	RMS ±10% (%)		±15% (%)			
14	1. Open design with elbow and diffuser vanes plus 12" model spacer 2. Five 1" dia- meter dowels equally spaced, 58.3% open	1A,2A,3	0.104	61.5	85.4	0.088	80.9	92.7	0.062	89.9	98.6	16,17,18
16	1. Open design with elbow and diffuser vanes plus 12" model spacer 2. Five 1" dowels unequally spaced, 58.3% open average	1A,2A,3	0.066	87.5	97.9	0.054	93.8	96.5	0.055	92.0	98.3	19,20,21,22
17	1. Open design with elbow and diffuser vanes 2. No spacer between elbow and core 3. Five 1" dowels same as Test 16	1A,2A,3	0.066	87.5	97.9	0.074	86.1	95.5	0.049	95.5	99.0	19,20,23,24, 25,26

Table 2

SUMMARY OF VELOCITY PROFILE TEST RESULTS
FOR MODEL REACTOR INLET DESIGN NO. 2 FOR
SCR PILOT PLANT

Test No.	Description of Geometry	Geometry Figures	Location 2			Location 3			Location 4			Data Figures
			RMS	+10% (+%)	+15% (+%)	RMS	+10% (+%)	+15% (+%)	RMS	+10% (+%)	+15% (+%)	
19	1. Open design 1B,2B with elbow and diffuser vanes	1B,2B	0.140	43.8	64.6	0.141	51.0	72.2	0.061	87.8	98.6	27,28,29
20	1. Open design 1B,2B with elbow and diffuser vanes	1B,2B	0.099	67.7	89.6	0.096	71.2	86.1	0.062	90.6	98.3	---
	2. Eight 1/2" diameter model dowels											
	unequally spaced, 57.9% open											
21	1. Open duct 1B,2B with elbow and diffuser vanes	1B,2B	0.092	69.8	93.8	0.098	68.4	84.0	0.055	91.3	99.0	---
	2. Nine 1/2" diameter model dowels											
	unequally spaced, 52.6% open											

Table 2 (Continued)

Test No.	Description of Geometry	Location 2		Location 3		Location 4		Data Figures				
		Geometry Figures	RMS ±10% (%)	±15% (%)	RMS ±10% (%)	±15% (%)	RMS ±10% (%)		±15% (%)			
22	1. Open duct with elbow and diffuser vanes	1B,2B	0.068	89.6	97.9	0.097	63.5	88.2	0.059	89.6	98.6	30,31,32
	2. Nine 1/2" diameter model dowels unequally spaced, 52.6% open											

Figure 1A

MODEL GEOMETRY AND VELOCITY TRAVERSE LOCATIONS
FOR REACTOR INLET MODEL DESIGN NO. 1
(Model Scale Factor = 2.0)

Figure 1B

Figure 2A

MODEL GEOMETRY FOR ELBOW VANES AND DIFFUSER BAFFLES
FOR REACTOR INLET MODEL DESIGN NO. 1
(Model Scale Factor = 2)

Diffuser baffles equally
spaced at inlet and outlet

MODEL GEOMETRY FOR ELBOW VANES AND DIFFUSER BAFFLES
FOR REACTOR INLET
MODEL DESIGN NO. 2

Figure 3

GEOMETRY OF MODEL PIPE RESISTANCES FOR TESTS 12, 14, 16, AND 17
(Model Scale Factor = 2)

Pipe Resistance for Test 12

Pipe Resistance for Test 14

Pipe Resistance for Tests 16 and 17

Figure 4

MODEL INLET PIPE VELOCITY PROFILE AT LOCATION 1
FOR GEOMETRY DOCUMENTED ON FIGURE 1
APPLICABLE TO ALL TESTS FOR REACTOR INLET DESIGN NO. 1

Percent of average velocity
Flow out of paper

Data located at center of equal area segments

RMS = 0.084

% of data within bands

+10%	80%
+15%	92.5%
+25%	100%

FIGURE 5

VELOCITY DATA FOR TEST 10 AND 11
AT LOCATION 2 DOWNSTREAM OF DIFFUSER
REACTOR INLET MODEL DESIGN #1

JOB: SCS-2

DATE OF TEST: 01-28-1991

TRAVERSE LOCATION: T10-L2-2

DENSITY= .0747(LB/FT³)

ORIFICE FLOWRATE= 3058ACFM

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE=-2.7 IN.H₂O

NUMERICAL AVE. VELOCITY = 2150. FT/MIN

MODEL VELOCITY HEAD(0-orifice)=0.258IN.H₂O

VELOCITY FT/MIN

ROW AVG

1459.	1365.	1580.	1612.	1599.	1339.	1272.	1473.	1431.
2201.	1793.	2531.	2637.	2559.	2243.	1886.	2211.	1749.
2545.	2426.	2855.	2909.	2878.	2601.	2517.	2434.	1743.
2271.	2311.	2667.	2881.	2749.	2400.	2398.	1959.	803.
2556.	2042.	2845.	3158.	3123.	2956.	2928.	2510.	885.
2389.	1984.	2533.	2996.	2964.	2790.	2627.	2464.	754.
2505.	2022.	2935.	3148.	2941.	2829.	2730.	2443.	989.
2627.	2464.	3010.	3022.	2867.	2700.	2738.	2641.	1573.
2181.	2414.	2429.	2376.	2169.	2200.	2189.	2190.	1480.
2364.	2352.	2508.	2723.	2643.	2575.	2268.	2186.	1655.
1739.	1777.	1600.	1905.	2172.	2029.	1623.	1695.	1114.
967.	984.	920.	1050.	1074.	929.	1089.	1216.	471.

COL AVG

1994.	2368.	2535.	2478.	2299.	2189.	2119.	1221.
-------	-------	-------	-------	-------	-------	-------	-------

VELOCITY (% OF NUM. AVE.)

ROW AVG

67.8	63.5	73.5	75.0	74.4	62.3	59.1	68.5	66.6
102.4	83.4	117.7	122.6	119.0	104.3	87.7	102.8	81.3
118.4	112.8	132.8	135.3	133.9	121.0	117.1	113.2	81.1
105.6	107.5	124.0	134.0	127.8	111.6	111.5	91.1	37.3
118.9	94.9	132.3	146.8	145.2	137.5	136.2	116.7	41.2
111.1	92.3	117.8	139.3	137.9	129.7	122.2	114.6	35.1
116.5	94.0	136.5	146.4	136.8	131.6	127.0	113.6	46.0
122.2	114.6	140.0	140.5	133.3	125.6	127.3	122.8	73.1
101.4	112.2	113.0	110.5	100.9	102.3	101.8	101.8	68.8
109.9	109.4	116.6	126.6	122.9	119.7	105.5	101.7	77.0
80.9	82.7	74.4	88.6	101.0	94.3	75.5	78.8	51.8
45.0	45.8	42.8	48.8	50.0	43.2	50.6	56.5	21.9

OUTSIDE OF ELBOW

INSIDE OF ELBOW

COL AVG

92.8	110.1	117.9	115.3	106.9	101.8	98.5	56.8
------	-------	-------	-------	-------	-------	------	------

BANDSIZE

VRANGE

COUNT

PERCENT

FT/MIN

PERCENT

10

1935. - 2365.

16.7

15

1828. - 2473.

29.2

25

1613. - 2688.

50.0

40

1290. - 3010.

81.3

RMS= 0.312

DEV. OF MAX=0.468

DEV. OF MIN=0.781

FIGURE 6 TEST No. 10x11 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW AND CORE NO
 RESISTANCE PIPE NEAR DIFFUSER INLET NO
 TRAVERSE LOCATION DOWN STREAM OF DIFFUSER 2

Percent of Average Velocity
 Flow Out of Paper

FIGURE 7 TEST No. 10 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE NO
 RESISTANCE PIPES NEAR DIFFUSER INLET NO
 TRAVERSE LOCATION 3 CORE INLET

FIGURE 8 TEST No. 10 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE NO
 RESISTANCE PIPES NEAR DIFFUSER INLET NO
 TRAVERSE LOCATION 4 CORE OUTLET

FIGURE 9 VELOCITY DATA FOR TEST 11 AT LOCATION 3 CORE INLET REACTOR INLET MODEL DESIGN #1

JOB: SC5-2
DATE OF TEST: 01-29-1991

TRAVERSE LOCATION: T11-L3-1
DENSITY: .0749 (LB/FT³)

ORIFICE FLOWRATE= 3054ACFM

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE=-2.5 IN.H2O

NUMERICAL AVE. VELOCITY = 1085. FT/MIN

MODEL VELOCITY HEAD(G-orifice)=0.064IN.H2O

VELOCITY FT/MIN

ROW AVE

875.	669.	823.	967.	1025.	822.	1036.	992.	822.	685.	949.	807.	717.
891.	613.	703.	866.	947.	1026.	1008.	964.	976.	996.	952.	903.	777.
1011.	617.	803.	916.	994.	1232.	1211.	1170.	1188.	1136.	1084.	989.	841.
1105.	625.	816.	1065.	1122.	1315.	1290.	1309.	1190.	1235.	1273.	1126.	945.
1154.	747.	867.	887.	1252.	1347.	1422.	1294.	1270.	1374.	1293.	1230.	929.
1185.	695.	835.	926.	1229.	1389.	1327.	1270.	1307.	1376.	1350.	1260.	1025.
1251.	801.	1091.	1106.	1361.	1401.	1361.	1351.	1434.	1396.	1358.	1313.	1044.
1275.	761.	1025.	1207.	1362.	1397.	1402.	1431.	1401.	1442.	1397.	1330.	1119.
1284.	892.	1101.	1180.	1364.	1353.	1373.	1500.	1377.	1365.	1382.	1362.	1162.
1251.	941.	1054.	1235.	1267.	1274.	1362.	1431.	1362.	1279.	1356.	1268.	1190.
1277.	885.	1007.	1166.	1199.	1233.	1360.	1398.	1330.	1239.	1251.	1352.	1305.
1135.	913.	991.	1084.	1146.	1186.	1364.	1424.	1240.	1252.	1180.	1235.	1326.
1153.	948.	1006.	1060.	1093.	1162.	1243.	1337.	1202.	1166.	1128.	1227.	1261.
1115.	967.	986.	1032.	1055.	1080.	1212.	1314.	1122.	1156.	1086.	1118.	1252.
1052.	991.	958.	1033.	1042.	1040.	1238.	1194.	1074.	1087.	1064.	1123.	1275.
1080.	1002.	966.	1019.	997.	1052.	1111.	1122.	1061.	1065.	1040.	1109.	1180.
1025.	966.	966.	981.	997.	1033.	1083.	1143.	1062.	1018.	1051.	1038.	1084.
1025.	959.	950.	998.	976.	1014.	1087.	1091.	1008.	1003.	1034.	1088.	1091.
991.	938.	912.	956.	937.	969.	1055.	1106.	975.	951.	1029.	1005.	1056.
974.	963.	880.	951.	946.	980.	979.	1010.	973.	929.	1036.	1023.	1016.
960.	902.	896.	958.	942.	937.	964.	1050.	980.	948.	1047.	1080.	1060.
980.	946.	926.	966.	938.	920.	997.	994.	994.	922.	1015.	1077.	1066.
985.	976.	913.	986.	980.	965.	1013.	979.	990.	912.	953.	1039.	1111.
961.	926.	915.	924.	919.	955.	964.	943.	950.	895.	940.	1087.	1109.

COL AVE 860. 930. 1020. 1087. 1129. 1186. 1199. 1137. 1126. 1133. 1133. 1080.

VELOCITY% OF NUM. AVE.

ROW AVE

81.1	61.7	75.8	91.0	95.4	76.7	95.5	91.4	75.8	81.6	87.4	74.4	66.1
82.1	56.5	64.8	79.8	87.3	94.5	92.9	88.9	90.1	92.0	87.7	83.3	67.9
93.2	56.5	74.0	84.6	91.6	113.5	111.7	103.2	109.5	104.9	99.9	91.2	77.5
101.8	57.6	74.6	98.2	103.4	121.2	118.9	120.7	109.7	113.9	112.7	104.0	87.1
106.4	68.5	74.4	81.4	115.4	123.8	131.0	119.3	117.0	126.7	119.2	113.3	86.6
107.4	64.1	77.0	84.8	113.3	128.0	122.3	117.0	120.5	127.0	124.5	116.1	94.4
115.3	73.8	100.6	101.9	125.4	129.1	125.5	124.5	132.1	128.6	125.2	121.0	96.3
117.3	70.2	94.5	111.2	125.6	128.7	129.2	131.9	129.1	132.9	128.8	122.6	103.2
118.4	82.2	101.5	108.7	125.7	124.7	126.5	138.3	127.0	125.8	127.3	125.5	107.1
115.4	86.7	97.1	113.8	116.7	117.4	125.6	131.9	125.5	117.9	125.0	116.9	109.7
113.1	81.6	92.4	107.4	110.6	113.7	125.4	128.8	122.6	114.2	115.3	124.7	120.3
110.0	84.1	91.3	99.9	105.6	109.4	125.8	131.2	114.3	113.6	108.8	113.9	122.2
106.7	87.4	92.7	97.7	100.7	107.1	114.6	123.3	110.8	107.5	104.0	113.1	116.2
102.6	89.1	90.9	95.1	97.2	99.5	111.7	121.1	103.4	106.6	100.3	103.0	115.4
100.8	91.3	88.3	95.2	96.0	95.9	114.1	110.1	99.0	100.2	98.1	103.5	117.5
97.7	92.4	89.0	93.9	91.9	96.9	102.4	103.4	97.8	98.2	95.9	102.2	108.8
95.4	89.0	89.0	90.4	91.9	95.3	99.9	105.4	97.9	93.8	96.9	95.7	99.9
94.5	88.4	87.6	92.0	89.9	93.4	100.2	100.6	93.0	92.4	95.4	100.3	100.6
91.7	86.4	84.1	88.1	86.4	89.3	97.3	101.9	89.8	87.6	94.9	92.6	97.4
89.6	88.8	81.1	87.6	87.2	90.3	90.2	93.1	89.7	85.6	95.5	94.3	93.7
90.4	83.1	82.6	88.3	85.9	86.3	88.9	96.7	90.4	87.4	96.5	99.6	97.7
90.3	87.2	85.4	89.0	86.5	84.8	91.9	91.6	91.6	85.0	93.5	99.3	98.3
90.8	89.4	84.2	90.9	90.4	89.3	93.4	90.2	91.2	84.1	87.8	95.8	102.4
88.5	85.3	84.4	85.2	84.7	88.1	88.6	86.9	87.6	82.5	86.6	100.2	102.2

COL AVE 79.2 85.7 94.6 100.2 104.0 109.3 110.5 104.8 103.7 104.5 104.4 95.5

RANDSIZE

PERCENT

VRANGE	COUNT
FT/MIN	PERCENT
10	976. - 1193. 41.3
15	922. - 1248. 64.2
25	814. - 1356. 84.0
40	651. - 1519. 99.0

INSIDE OF ELBOW

RMS= 0.164

DEV. OF MAX=0.382

DEV. OF MIN=0.425

FIGURE 10 TEST No. 11 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE 12" MODEL
 RESISTANCE PIPES NEAR DIFFUSER INLET NO
 TRAVERSE LOCATION 3 CORE INLET

Percent Of Average Velocity
 Flow Out of Paper

FIGURE 11

VELOCITY DATA FOR TEST 11 AT LOCATION 4 CORE OUTLET REACTOR INLET MODEL DESIGN #1

JOB: SSC-2

DATE OF TEST: 01-29-1991

TRAVERSE LOCATION: 111-14-1

DENSITY: .0748 (LB/FT³)

ORIFICE FLOW RATE: 3059 ACFM

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE = -2.2 IN. H₂O

NUMERICAL AVE VELOCITY = 1064. FT/MIN

MODEL VELOCITY HEAD (Q-orifice) = 0.064 IN. H₂O

VELOCITY (FT/MIN)

ROW AVE

991.	969.	1135.	760.	1028.	1028.	1019.	1022.	982.	1055.	1145.	942.	879.
918.	805.	894.	858.	925.	936.	948.	922.	965.	961.	1014.	875.	888.
957.	888.	922.	933.	924.	986.	965.	971.	952.	986.	1004.	917.	1018.
1026.	997.	1005.	968.	1012.	1085.	1025.	982.	1002.	1047.	1050.	1092.	1077.
1076.	989.	1032.	1060.	1077.	1051.	1129.	1084.	1040.	1096.	1119.	1162.	1068.
1078.	1011.	1019.	1056.	1088.	1051.	1108.	1058.	1002.	1102.	1094.	1192.	1151.
1099.	995.	1019.	1075.	1086.	1082.	1162.	1120.	1095.	1125.	1098.	1187.	1149.
1115.	1034.	1025.	1085.	1085.	1100.	1166.	1157.	1045.	1168.	1196.	1164.	1152.
1138.	1115.	1044.	1047.	1116.	1134.	1162.	1163.	1182.	1161.	1190.	1204.	1142.
1144.	1035.	1055.	1055.	1070.	1154.	1182.	1235.	1200.	1167.	1179.	1210.	1190.
1130.	1060.	1030.	1056.	1071.	1114.	1153.	1158.	1153.	1198.	1176.	1195.	1193.
1119.	1058.	1059.	1067.	1027.	1076.	1164.	1081.	1075.	1189.	1184.	1185.	1264.
1115.	1054.	1045.	1065.	1100.	1079.	1150.	1112.	1101.	1156.	1155.	1105.	1256.
1096.	1024.	1026.	1033.	1031.	1039.	1139.	1121.	1097.	1159.	1150.	1127.	1205.
1107.	1044.	1077.	1018.	1056.	1039.	1126.	1180.	1126.	1143.	1124.	1148.	1208.
1108.	1075.	1092.	1033.	1056.	1032.	1146.	1112.	1077.	1129.	1123.	1143.	1253.
1090.	1100.	1055.	1067.	1023.	1135.	1076.	1065.	1089.	1048.	1100.	1144.	1181.
1075.	1091.	1037.	1022.	1079.	950.	1117.	1067.	1077.	1071.	1119.	1117.	1159.
992.	1029.	976.	978.	936.	876.	1022.	981.	1007.	960.	1052.	1027.	1054.
1006.	1083.	1006.	972.	936.	846.	1016.	1002.	1000.	1028.	1087.	1094.	1094.
1022.	1047.	992.	983.	997.	847.	1033.	993.	1030.	1068.	1094.	1043.	1137.
1032.	1106.	1079.	969.	978.	971.	1028.	1010.	1022.	1066.	1023.	1096.	1093.
1022.	1098.	998.	947.	995.	968.	1027.	990.	982.	1006.	1036.	1109.	1102.
1067.	1108.	1127.	980.	1080.	1062.	1040.	1068.	1006.	965.	1159.	1118.	1091.
CCL AVE	1034.	1031.	1004.	1033.	1025.	1088.	1070.	1051.	1085.	1109.	1109.	1173.

VELOCITY (% OF NUM. AVE.)

ROW AVE

93.2	91.1	106.7	71.5	96.7	96.7	95.8	97.0	84.8	99.2	107.6	88.5	82.7
86.3	75.7	84.0	80.7	87.9	88.0	89.1	87.6	90.7	90.4	95.4	82.6	83.3
89.6	82.7	86.7	87.7	86.9	90.9	90.8	91.3	89.5	92.9	94.4	86.2	95.5
96.5	93.8	94.5	92.7	95.2	100.1	97.3	92.3	94.3	98.5	98.7	102.6	97.5
101.7	93.0	97.0	99.6	101.2	98.8	106.2	102.9	97.8	103.0	105.2	109.3	100.2
101.3	95.0	95.6	99.3	102.3	98.8	104.2	99.4	94.3	103.7	102.6	112.1	106.2
103.4	92.5	95.8	101.1	102.3	101.7	109.3	105.3	102.9	105.8	103.2	111.6	108.0
104.6	97.7	96.4	102.1	102.0	103.4	109.7	108.8	98.2	109.8	112.5	109.4	108.2
107.0	104.6	98.2	98.4	105.0	106.6	109.2	109.3	111.2	109.2	111.9	112.5	107.4
107.6	97.4	99.2	99.2	100.6	108.6	111.2	116.1	112.9	109.7	110.9	112.6	111.9
106.2	99.6	96.6	99.3	100.7	104.8	108.4	108.9	106.4	112.6	110.6	112.4	112.2
105.2	99.5	95.6	100.3	96.6	101.2	109.5	101.6	101.1	111.8	111.4	111.4	116.8
104.6	99.1	98.7	100.1	103.4	101.5	106.2	104.6	103.5	108.7	108.6	103.5	116.1
103.0	96.2	96.5	97.1	96.9	97.7	107.1	105.4	103.2	109.0	108.2	106.0	112.2
104.1	98.2	101.2	95.8	99.2	97.7	105.9	111.0	105.9	107.5	105.7	107.9	113.6
104.0	101.0	102.7	97.1	99.3	97.1	107.8	104.6	101.3	106.1	105.6	107.5	117.6
102.5	103.4	99.2	100.3	96.2	106.7	101.2	100.2	102.4	98.5	103.4	107.5	111.0
101.1	102.6	97.5	96.1	101.5	89.3	105.0	100.3	101.2	100.7	105.2	105.1	108.9
92.7	96.7	91.7	92.0	88.2	82.6	96.1	92.2	94.7	90.3	98.9	97.5	99.1
94.6	101.9	94.6	91.4	88.2	79.5	95.5	94.2	94.0	94.3	96.7	102.2	102.8
96.1	98.4	93.2	92.4	93.7	79.6	97.1	93.4	97.3	100.4	102.9	98.1	106.9
97.5	104.0	101.5	91.1	91.9	91.3	96.6	95.0	96.0	100.2	96.2	103.2	102.8
96.1	103.2	93.8	89.1	93.5	91.1	96.5	93.1	92.3	94.7	97.6	104.3	103.6
106.2	104.0	105.9	92.1	101.6	99.9	97.6	100.4	94.6	90.8	109.0	105.2	102.5
CCL AVE	97.2	97.0	94.4	97.1	96.4	102.2	100.6	98.9	102.0	104.2	104.2	105.6

OUTSIDE OF ELBOW

INSIDE OF ELBOW

RANGE: 100%

DEV. OF MAX = 1.18%

DEV. OF MIN = 0.28%

FIGURE 12 TEST No. 11 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE 12" MODEL
 RESISTANCE PIPES NEAR DIFFUSER INLET NO
 TRAVERSE LOCATION 4 CORE OUTLET

FIGURE 13 TEST No. 12 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW AND CORE 12" MODEL
 RESISTANCE PIPE NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION DOWN STREAM OF DIFFUSER 2

Percent of Average Velocity
 Flow Out of Paper

FIGURE 14 TEST No. 12 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE 12" MODEL
 RESISTANCE PIPES NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION 3 CORE INLET

FIGURE 15 TEST No. 12 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE 12" MODEL
 RESISTANCE PIPES NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION 4 CORE OUTLET

FIGURE 16 TEST No. 14 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW AND CORE 12" MODEL
 RESISTANCE PIPE NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION DOWN STREAM OF DIFFUSER 2

Percent Of Average Velocity
Flow Out of Paper

FIGURE 18 TEST No. 14 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE 12" MODEL
 RESISTANCE PIPES NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION 4 CORE OUTLET

FIGURE 19 VELOCITY DATA FOR TEST 16, 17, AND 18 AT LOCATION 2 DOWNSTREAM OF DIFFUSER REACTOR INLET MODEL DESIGN #1

JOB: SCS-1

DATE OF TEST: 02-05-1991

TRAVERSE LOCATION: T16-L2-1

DENSITY= .0752(LB/FT^3)

ORIFICE FLOWRATE= 3049ACFM

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE=-3.4 IN.H2O

NUMERICAL AVE. VELOCITY = 2137. FT/MIN

MODEL VELOCITY HEAD(Q-orifice)=0.258IN.H2O

VELOCITY(FT/MIN)

ROW AVE

1905.	1924.	2026.	2077.	1939.	1874.	1907.	1874.	1622.
2200.	2250.	2320.	2371.	2253.	2162.	2184.	2146.	1911.
2273.	2348.	2405.	2377.	2278.	2265.	2263.	2253.	1997.
2000.	2031.	2128.	2139.	2038.	1999.	2026.	1928.	1709.
2147.	2119.	2281.	2219.	2190.	2167.	2199.	2097.	1906.
2165.	2120.	2275.	2258.	2142.	2171.	2185.	2195.	1973.
2140.	2145.	2269.	2213.	2173.	2120.	2145.	2102.	1951.
2220.	2235.	2358.	2317.	2232.	2149.	2189.	2196.	2079.
2143.	2226.	2243.	2218.	2091.	2081.	2141.	2124.	2019.
2139.	2199.	2278.	2225.	2208.	2099.	2088.	2027.	1990.
2225.	2332.	2366.	2317.	2226.	2178.	2169.	2135.	2077.
2092.	2234.	2194.	2171.	2085.	2078.	2014.	2021.	1936.

COL AVE

2180.	2262.	2242.	2155.	2112.	2126.	2092.	1931.
-------	-------	-------	-------	-------	-------	-------	-------

VELOCITY(2 OF NUM. AVE.)

ROW AVE

89.1	90.0	94.8	97.2	90.7	87.7	89.2	87.7	75.9
102.9	105.3	108.5	110.9	105.4	101.2	102.2	100.5	89.4
106.4	109.8	112.5	111.2	106.6	105.9	105.9	105.4	93.4
93.6	95.0	99.6	100.1	95.4	93.5	94.8	90.2	79.9
100.5	99.1	106.7	103.8	102.5	101.4	102.9	98.1	89.2
101.3	99.2	106.4	105.6	100.2	101.6	102.2	102.9	92.3
100.1	100.3	106.2	103.5	101.6	99.2	100.4	98.4	91.3
103.8	104.6	110.3	108.4	104.4	100.5	102.4	102.8	97.3
100.3	104.2	104.9	103.8	97.8	97.4	100.2	99.4	94.5
100.1	102.9	106.6	104.1	103.3	98.2	97.7	94.8	93.1
104.1	109.1	110.7	108.4	104.1	101.9	101.5	99.9	97.2
97.9	104.5	102.6	101.6	97.5	97.2	94.2	94.6	90.6

OUTSIDE OF ELBOW

INSIDE OF ELBOW

COL AVE

102.0	105.8	104.9	100.8	98.8	99.5	97.9	90.3
-------	-------	-------	-------	------	------	------	------

RANDSIZE
PERCENT

VRANGE
FT/MIN

COUNT
PERCENT

10	1924. - 2351.	87.5
15	1817. - 2456.	97.5
25	1603. - 2672.	2100.0
40	1282. - 2992.	2100.0

RMS= 0.066

DEV. OF MAX=0.125

DEV. OF MIN=0.241

FIGURE 20 TEST No. 16 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW AND CORE 12" MODEL
 RESISTANCE PIPE NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION DOWN STREAM OF DIFFUSER 2

Percent of Average Velocity
 Flow Out of Paper

FIGURE 21 TEST No. 16 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE 12" MODEL
 RESISTANCE PIPES NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION 3 CORE INLET

FIGURE 22 TEST No. 16 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE 12" MODEL
 RESISTANCE PIPES NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION 4 CORE OUTLET

FIGURE 4

VELOCITY DATA FOR TEST 17
AT LOCATION 3 CORE INLET

JOB: SCE-2

DATE OF TEST: 02-05-1991

TRAVERSE LOCATION: T17-L3-1

DENSITY= .0752 (LB/FT³)

ORIFICE FLOWRATE= 3049ACFM

REACTOR INLET MODEL DESIGN #1

MODEL STATIC PRESSURE=3.2 IN.H₂O

** FLOW OUT OF PAPER **

NUMERICAL AVE. VELOCITY = 1092. FT/MIN

MODEL VELOCITY HEAD(Q-orifice)=0.064IN.H₂O

VELOCITY FT/MIN

ROW AVG

937.	1014.	974.	997.	956.	917.	885.	905.	891.	926.	932.	944.	921.
995.	1002.	1039.	1024.	996.	931.	989.	979.	979.	972.	986.	1012.	966.
1051.	1056.	1114.	1102.	1055.	1055.	997.	1011.	1063.	1046.	1054.	1062.	995.
1125.	1096.	1114.	1180.	1199.	1152.	1136.	1127.	1154.	1152.	1162.	1094.	1056.
1162.	1147.	1110.	1187.	1229.	1204.	1200.	1182.	1195.	1185.	1141.	1069.	1100.
1136.	1187.	1052.	1159.	1185.	1163.	1142.	1152.	1142.	1150.	1109.	1070.	1142.
1128.	1185.	1019.	1111.	1169.	1152.	1136.	1131.	1124.	1142.	1118.	1082.	1164.
1146.	1157.	1036.	1138.	1193.	1172.	1168.	1163.	1142.	1148.	1126.	1111.	1220.
1160.	1190.	1060.	1128.	1194.	1153.	1191.	1179.	1154.	1174.	1129.	1087.	1276.
1145.	1167.	1056.	1096.	1174.	1151.	1160.	1150.	1165.	1162.	1109.	1078.	1277.
1124.	1201.	1048.	1091.	1161.	1133.	1140.	1122.	1132.	1114.	1106.	1021.	1221.
1110.	1190.	1038.	1065.	1148.	1110.	1141.	1130.	1110.	1127.	1088.	993.	1179.
1121.	1192.	1012.	1072.	1156.	1125.	1140.	1140.	1132.	1143.	1133.	1037.	1171.
1130.	1202.	1033.	1076.	1161.	1098.	1122.	1149.	1136.	1140.	1156.	1063.	1221.
1125.	1144.	1030.	1076.	1142.	1099.	1136.	1141.	1143.	1153.	1169.	1058.	1208.
1131.	1122.	1030.	1096.	1140.	1111.	1145.	1157.	1134.	1153.	1159.	1081.	1241.
1135.	1128.	1029.	1102.	1166.	1118.	1159.	1172.	1154.	1180.	1149.	1052.	1214.
1106.	1102.	1009.	1064.	1139.	1058.	1099.	1142.	1114.	1176.	1098.	1002.	1192.
1061.	1070.	975.	1009.	1095.	1026.	1063.	1076.	1051.	1119.	1099.	975.	1183.
1052.	1079.	978.	1025.	1071.	991.	1022.	1058.	1041.	1111.	1094.	1012.	1148.
1069.	1069.	1012.	1070.	1133.	1036.	1052.	1049.	1044.	1146.	1119.	979.	1119.
1058.	1076.	1021.	1090.	1173.	1006.	1042.	1041.	1029.	1101.	1051.	965.	1098.
1055.	1129.	992.	1095.	1133.	1022.	1036.	1034.	1023.	1062.	1031.	976.	1125.
931.	881.	767.	926.	1037.	834.	951.	984.	965.	1005.	958.	840.	1024.
COL AVG	1116.	1023.	1082.	1134.	1078.	1094.	1099.	1092.	1116.	1094.	1028.	1145.

VELOCITY (% OF NUM. AVE.)

ROW AVG

85.8	92.9	89.2	91.3	87.6	84.0	81.0	83.3	81.6	84.2	82.6	86.5	85.3
91.1	91.8	95.1	93.8	91.2	90.8	90.6	89.7	89.7	89.1	90.5	92.7	88.5
96.3	96.7	102.0	100.9	96.6	96.7	91.4	92.6	97.4	96.0	96.5	97.3	91.2
104.0	100.4	102.1	108.1	109.8	105.6	104.3	102.9	105.7	105.7	106.5	100.2	96.8
106.4	104.7	101.7	108.7	112.6	110.3	110.0	108.3	109.5	108.4	104.5	97.9	100.7
104.2	108.7	96.4	106.2	108.5	106.5	104.6	105.5	104.7	105.3	101.6	98.0	104.6
103.3	108.6	93.3	101.7	107.0	105.5	104.3	103.6	102.9	104.6	102.4	99.1	106.6
105.1	105.9	94.9	104.2	109.3	107.4	107.0	106.5	104.6	105.1	103.1	101.7	111.7
106.2	109.0	97.1	103.3	109.4	105.6	109.1	108.0	105.7	107.5	103.4	99.5	116.9
104.9	106.9	96.7	100.4	107.6	105.5	106.2	105.4	106.7	106.4	101.6	98.7	117.0
103.0	110.0	96.0	99.9	106.4	103.8	104.4	102.8	103.7	102.0	101.3	93.5	111.8
101.7	109.0	95.1	97.5	105.1	101.6	104.6	103.5	101.6	103.3	99.7	90.9	108.0
102.7	109.1	92.7	98.2	105.9	103.0	104.4	104.4	103.6	104.7	103.8	95.0	107.3
103.5	110.1	94.6	98.8	106.3	100.6	102.8	105.2	104.1	104.4	105.9	97.4	111.9
103.0	104.8	94.4	98.6	104.6	100.7	104.1	104.5	104.7	105.6	107.1	96.9	110.7
103.6	102.8	94.4	100.4	104.5	101.7	104.9	106.0	103.9	105.6	106.2	99.0	113.7
104.0	103.3	94.3	101.0	106.8	102.4	106.2	107.3	105.7	108.1	105.3	96.4	111.2
100.7	100.9	92.4	97.5	104.3	96.9	100.6	104.6	102.1	107.7	100.5	91.8	109.2
97.3	98.0	89.3	92.4	100.3	94.0	97.3	98.6	96.3	102.5	100.7	89.3	108.4
96.5	98.9	89.6	94.8	98.1	90.7	93.6	96.9	95.4	101.8	100.2	92.7	105.1
97.9	97.9	92.8	98.0	103.8	94.9	96.4	96.0	95.7	105.0	102.5	89.7	102.5
96.9	98.6	92.5	99.9	107.5	92.2	95.5	95.4	94.2	100.9	96.3	88.3	100.6
96.6	103.4	90.9	100.3	103.8	93.6	94.9	94.7	93.7	97.3	94.5	89.4	103.0
85.7	80.7	70.2	84.8	94.4	76.4	87.1	90.1	88.4	92.1	87.7	76.9	92.6
COL AVG	102.2	93.7	99.2	103.8	98.8	100.1	100.7	100.1	102.2	100.2	94.1	104.8

HAND SIZE

PERCENT

VRANGE	COUNT
FT/MIN	PERCENT
1- 96.7 - 120.1	66.1
15 92.6 - 125.6	95.5
25 81.9 - 136.5	99.7
40 65.5 - 152.8	100.0

INSIDE OF ELBOW

RMS= 0.674

DEV. OF MAX=0.170

DEV. OF MIN=0.296

FIGURE 24 TEST No. 17 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE NO
 RESISTANCE PIPES NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION 3 CORE INLET

FIGURE 22

VELOCITY DATA FOR TEST 17
AT LOCATION 4 CORE OUTLET

ID# 509-2

DATE OF TEST: 02-06-1991

TRAVERSE LOCATION: T17-L4-1

DENSITY = 1.0757 G/CM³

ORIFICE FLOWRATE = 3040 ACFM

REACTOR INLET MODEL DESIGN #1

MODEL STATIC PRESSURE = 3.8 IN. H₂O

** FLOW OUT OF PAPER **

NUMERICAL AVE. VELOCITY = 1060. FT/MIN

MODEL VELOCITY HEAD (Q=orifice) = 0.165 IN. H₂O

VELOCITY (FT/MIN)

ROW AVG

99	1052.	992.	975.	942.	1074.	981.	1055.	941.	960.	955.	911.	917.
92.	987.	997.	1030.	1015.	877.	871.	991.	975.	966.	1014.	961.	956.
1007.	1004.	1063.	1041.	1009.	941.	866.	972.	1006.	976.	1027.	1060.	957.
1075.	1075.	1045.	1007.	1017.	1011.	974.	996.	952.	1047.	1076.	1041.	1029.
1054.	1045.	1090.	1047.	1061.	1006.	1041.	1041.	1079.	1057.	1067.	1054.	1056.
1054.	1097.	1111.	1084.	1104.	995.	1022.	1026.	967.	1043.	1025.	1066.	1099.
1047.	1015.	1062.	1047.	1074.	1044.	1066.	1050.	1046.	1021.	999.	1046.	1071.
1056.	1081.	1052.	1034.	1075.	1030.	1064.	1066.	973.	1075.	1064.	1085.	1085.
1076.	1093.	1065.	1063.	1123.	1050.	1060.	1055.	1055.	1109.	1090.	1085.	1087.
1094.	1066.	1053.	1072.	1099.	1065.	1095.	1102.	1102.	1148.	1084.	1095.	1144.
1077.	1055.	1026.	1048.	1063.	1044.	1062.	1103.	1050.	1084.	1114.	1114.	1106.
1064.	1064.	1065.	1062.	1012.	997.	1078.	1091.	1022.	1090.	1092.	1058.	1135.
1060.	1051.	1072.	1081.	1042.	1040.	1081.	1151.	1068.	1055.	1094.	1096.	1145.
1100.	1090.	1072.	1132.	1058.	1061.	1094.	1119.	1077.	1117.	1129.	1120.	1156.
1108.	1081.	1108.	1099.	1086.	1068.	1113.	1157.	1084.	1087.	1077.	1119.	1215.
1112.	1080.	1092.	1107.	1061.	1100.	1115.	1110.	1120.	1124.	1123.	1118.	1190.
1104.	1106.	1081.	1108.	1089.	1067.	1101.	1126.	1086.	1068.	1125.	1095.	1192.
1086.	1096.	1064.	1090.	1038.	1049.	1099.	1062.	1073.	1094.	1128.	1099.	1141.
1074.	1052.	1029.	1030.	997.	1043.	1001.	1029.	1017.	1000.	1083.	1029.	1102.
1056.	1106.	1025.	1026.	1040.	1044.	1027.	1061.	1044.	1045.	1067.	1074.	1091.
1055.	1172.	1037.	1062.	1107.	1146.	1049.	1002.	1025.	1053.	1030.	1037.	1078.
1075.	1110.	1082.	1082.	1120.	1030.	1052.	1058.	1084.	1127.	1069.	1013.	1114.
1063.	1118.	1078.	1068.	1069.	1040.	1022.	1077.	1047.	1057.	1027.	1076.	1075.
1077.	1152.	1026.	1123.	1151.	1032.	1014.	1084.	1032.	1034.	1094.	1108.	1099.

COL AVG 1081. 1058. 1058. 1061. 1032. 1041. 1064. 1036. 1060. 1070. 1065. 1094.

VELOCITY (% OF NUM. AVE.)

ROW AVG

92.5	99.2	94.0	86.3	89.3	106.9	92.5	99.5	88.8	90.5	90.4	86.0	86.1
90.7	92.7	93.6	94.3	96.1	79.0	82.2	93.7	87.6	91.1	95.6	92.7	90.2
95.0	104.7	100.2	98.2	95.2	88.7	83.5	91.7	94.9	92.2	96.9	100.0	93.7
96.5	101.8	98.6	94.6	96.0	95.4	91.9	94.2	90.2	98.7	101.7	98.2	97.1
99.4	103.3	102.8	98.7	100.1	94.3	98.2	98.2	98.0	99.7	100.7	99.4	99.1
99.4	102.8	104.8	102.7	104.1	93.8	96.4	96.7	93.1	98.4	96.7	100.6	103.6
98.7	96.1	100.2	98.4	101.3	98.4	102.5	99.0	98.7	96.7	94.2	98.7	101.0
99.6	102.0	99.2	97.5	101.8	97.2	100.4	100.5	91.8	101.4	100.3	106.4	102.4
101.7	103.1	100.5	100.3	105.9	99.0	100.0	99.5	99.5	104.6	102.8	102.3	102.6
102.7	100.5	99.3	101.1	103.7	100.4	103.3	103.9	103.9	108.2	102.3	103.3	107.9
101.1	99.5	96.8	98.9	100.3	98.5	100.2	104.0	99.0	102.2	105.0	105.1	104.3
101.7	100.4	100.5	100.2	95.5	94.0	101.7	102.9	96.4	102.8	103.0	99.8	107.1
101.6	99.2	101.1	102.0	96.3	98.1	102.0	106.6	100.7	99.5	107.2	103.4	108.0
102.7	102.8	101.1	103.9	99.6	100.1	103.2	105.6	101.6	105.7	106.5	105.6	109.1
104.5	102.0	104.6	103.6	102.5	100.8	105.0	109.2	102.2	102.5	101.6	105.6	114.6
104.9	101.8	103.6	104.4	100.1	103.7	105.1	104.7	105.7	106.0	105.9	105.4	112.7
104.1	104.3	102.0	104.5	102.7	100.7	103.9	106.2	102.4	100.8	106.1	103.7	112.4
102.5	103.4	100.4	102.8	93.0	98.9	103.7	100.1	101.2	103.2	106.4	103.7	107.6
97.6	99.3	97.1	97.2	94.0	98.4	94.4	97.0	95.9	94.3	102.2	97.1	103.9
99.6	104.3	96.7	97.0	98.1	98.5	96.9	100.0	98.5	96.6	102.2	101.3	102.9
99.5	106.8	97.8	100.1	104.4	98.9	99.0	94.5	96.7	99.3	97.2	97.8	101.7
101.6	104.7	102.1	102.3	106.6	97.2	99.6	102.3	106.3	100.8	95.6	105.0	
100.7	105.4	101.7	100.7	100.8	98.1	96.4	101.6	98.8	99.7	96.9	101.5	101.4
101.6	108.7	96.8	106.0	108.6	97.4	95.7	100.4	97.3	97.5	103.2	104.5	103.7

COL AVG 102.0 99.8 99.8 100.1 97.4 98.2 100.4 97.7 100.0 100.9 100.5 103.2

BANDSIZE

PERCENT

VRANGE

FT/MIN

COUNT

PERCENT

15	954. - 1166.	95.5
25	954. - 1219.	99.0
25	795. - 1025.	1100.0
40	636. - 1484.	1100.0

INSIDE OF ELBOW

RMSE = 0.045

DEV. OF MAX = 0.142

DEV. OF MIN = 0.210

FIGURE 26 TEST No. 17 ISO-VELOCITY CONTOURS
 BASE CONFIGURATION REACTOR INLET DESIGN #1
 SPACER BETWEEN ELBOW CORE NO
 RESISTANCE PIPES NEAR DIFFUSER INLET YES
 TRAVERSE LOCATION 4 CORE OUTLET

Percent Of Average Velocity
 Flow Out of Paper

FIGURE 27 VELOCITY DATA FOR TEST 19 AT LOCATION 2 DOWNSTREAM OF FIRST DIFFUSER REACTOR INLET MODEL DESIGN #2

JOB: SCS-2
DATE OF TEST: 02-08-1991

TRAVERSE LOCATION: T19-L2-2
DENSITY= .0743(LB/FT³)

ORIFICE FLOWRATE= 3067ACFM

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE=-3 IN.H2O

NUMERICAL AVE. VELOCITY = 2561. FT/MIN

MODEL VELOCITY HEAD(@-orifice)=0.410IN.H2O

VELOCITY(FT/MIN)

ROW AVE

2226.	2046.	2020.	2076.	2378.	2508.	2344.	2174.	2266.
2425.	2210.	2453.	2394.	2678.	2390.	2376.	2803.	2097.
2537.	2330.	2420.	2652.	2865.	2881.	2566.	2635.	1946.
2792.	2250.	2658.	3093.	3040.	3047.	3009.	2802.	2435.
2706.	2270.	2578.	3286.	3071.	2826.	2912.	2709.	1993.
2687.	2002.	2457.	2684.	3104.	3117.	2922.	2934.	2274.
2640.	1903.	2130.	2500.	3056.	3138.	3286.	2846.	2263.
2666.	2167.	2618.	3071.	3146.	2878.	2751.	2589.	2111.
2733.	2219.	2611.	2866.	3045.	2988.	3032.	2703.	2398.
2661.	2279.	2513.	2712.	2970.	2974.	2844.	2548.	2445.
2272.	2256.	2448.	2438.	2351.	2317.	2077.	2571.	1715.
2382.	2091.	2247.	2488.	2618.	2700.	2431.	2330.	2153.

COL AVE

2169.	2429.	2688.	2860.	2814.	2712.	2637.	2175.
-------	-------	-------	-------	-------	-------	-------	-------

VELOCITY(% OF NUM. AVE.)

ROW AVE

87.0	79.9	78.9	81.1	92.9	98.0	91.5	84.9	88.5
94.7	86.3	95.8	93.5	104.6	93.3	92.8	109.5	81.9
99.1	91.0	94.5	103.6	111.9	112.5	100.2	102.9	76.0
109.0	87.9	103.8	120.8	118.7	119.0	117.5	109.4	95.1
105.7	88.6	100.7	128.3	119.9	110.4	113.7	105.8	77.8
104.9	78.2	96.0	104.8	121.2	121.7	114.1	114.6	88.8
103.1	74.3	83.2	97.7	119.3	122.5	128.3	111.2	88.4
104.1	84.6	102.2	119.9	122.9	112.4	107.4	101.1	82.4
106.7	86.7	102.0	111.9	118.9	116.7	118.4	105.6	93.7
103.9	89.0	98.2	105.9	116.0	116.2	111.1	99.5	95.5
88.7	88.1	95.6	95.2	91.8	90.5	81.1	100.4	67.1
93.0	81.7	87.8	97.2	102.2	105.5	94.9	91.0	84.1

COL AVE

84.7	94.9	105.0	111.7	109.9	105.9	103.0	84.9
------	------	-------	-------	-------	-------	-------	------

RANDSIZE
PERCENT

VRANGE
FT/MIN

COUNT
PERCENT

10	2305. - 2817.	43.8
15	2177. - 2945.	64.6
25	1920. - 3201.	95.8
40	1536. - 3585.	100.0

PMO= 0.140

DEV. OF MAX=0.283

DEV. OF MIN=0.329

FIGURE 28 VELOCITY DATA FOR TEST 19 AT LOCATION 3 CORE INLET - REACTOR INLET MODEL DESIGN #2

JDR: SCS-2
DATE OF TEST: 02-08-1991

TRAVERSE LOCATION: T19-L3-1
DENSITY: .0744(LB/FT³)

ORIFICE FLOWRATE= 3064ACFM

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE=-2.7 IN.H₂O

NUMERICAL AVE. VELOCITY = 1089. FT/MIN

MODEL VELOCITY HEAD(W-orifice)=0.0641IN.H₂O

VELOCITY FT/MIN

ROW AVG

914.	879.	948.	973.	885.	787.	901.	732.	969.	1018.	999.	964.	916.
1077.	975.	1114.	1079.	1015.	922.	945.	934.	1056.	1073.	1213.	1096.	1068.
1095.	1023.	1206.	1206.	1085.	1054.	976.	969.	1105.	1139.	1210.	1132.	1040.
1083.	1031.	1217.	1219.	1143.	1026.	1034.	1036.	1036.	1127.	1135.	1079.	984.
1054.	1064.	1143.	1210.	1106.	992.	1065.	1026.	1055.	1087.	1009.	917.	992.
1049.	961.	1033.	1052.	1071.	1055.	1087.	1116.	1209.	1156.	1060.	897.	895.
1074.	906.	909.	1001.	1025.	1110.	1152.	1172.	1307.	1307.	1116.	998.	881.
1150.	878.	926.	1016.	1135.	1233.	1315.	1309.	1363.	1333.	1309.	1109.	905.
1209.	810.	859.	978.	1177.	1290.	1409.	1339.	1463.	1428.	1406.	1305.	1043.
1207.	784.	774.	1027.	1178.	1377.	1403.	1420.	1404.	1434.	1476.	1373.	837.
1145.	798.	867.	937.	1073.	1246.	1313.	1343.	1359.	1355.	1385.	1156.	910.
1058.	856.	881.	1002.	1091.	1155.	1149.	1127.	1194.	1242.	1222.	1006.	770.
1117.	893.	1091.	1202.	1289.	1278.	1260.	1176.	1254.	1079.	1049.	945.	882.
1177.	945.	1147.	1284.	1326.	1402.	1408.	1355.	1248.	1108.	1117.	939.	845.
1226.	918.	1132.	1246.	1415.	1407.	1429.	1366.	1346.	1177.	1217.	1103.	960.
1198.	940.	1101.	1212.	1332.	1342.	1382.	1304.	1253.	1239.	1184.	1151.	933.
1111.	927.	972.	1128.	1227.	1277.	1315.	1216.	1127.	1083.	1098.	1006.	944.
1075.	976.	955.	1075.	1117.	1192.	1136.	1095.	1029.	956.	976.	940.	852.
994.	970.	999.	1021.	1068.	1097.	1073.	999.	967.	951.	969.	952.	865.
1026.	1053.	1074.	1064.	1079.	1057.	1016.	1041.	1015.	980.	1010.	989.	930.
1031.	1042.	1075.	1030.	1027.	1019.	1066.	1104.	1087.	1130.	1071.	1008.	951.
1060.	1017.	1061.	1048.	984.	1050.	1077.	1175.	1160.	1086.	1062.	1073.	930.
1046.	984.	1045.	1024.	969.	1033.	1076.	1174.	1171.	1093.	1061.	1026.	898.
1032.	940.	996.	974.	1002.	1083.	1092.	1202.	1141.	1090.	993.	945.	923.

COL AVG 938. 1022. 1084. 1117. 1145. 1170. 1155. 1180. 1153. 1139. 1045. 921.

VELOCITY (% OF NUM. AVE.)

ROW AVG

83.9	80.7	87.0	89.3	81.3	72.2	82.7	67.2	88.9	93.3	91.7	88.5	84.1
95.2	89.8	102.3	99.1	93.2	85.6	86.8	85.7	97.1	98.5	111.4	100.7	92.3
100.6	93.9	110.2	110.8	99.6	96.8	89.8	89.0	101.5	104.6	111.1	103.9	95.5
99.7	94.7	112.3	111.9	105.0	94.2	94.9	95.1	95.1	103.4	104.2	95.4	90.3
96.4	92.2	104.9	111.1	101.0	91.1	98.2	94.4	96.9	99.8	100.2	93.8	91.1
96.4	88.2	94.9	96.6	98.4	96.9	99.8	102.5	100.0	106.2	97.3	82.3	82.2
98.6	83.2	83.5	91.9	94.1	102.0	105.8	107.6	100.0	100.0	102.4	91.6	80.9
105.8	80.6	85.0	93.3	104.2	113.2	120.7	120.7	120.7	125.2	122.4	120.2	83.1
111.0	74.4	78.9	89.8	108.0	118.4	129.3	122.9	134.3	131.1	129.1	119.8	95.6
110.8	72.0	71.1	94.3	108.2	126.5	128.8	130.4	128.9	131.7	135.5	126.3	76.8
105.1	73.2	79.6	86.0	98.5	114.4	120.5	123.3	124.8	124.4	127.4	106.2	83.5
97.1	78.6	80.9	92.0	100.1	106.0	105.5	103.5	109.6	114.1	112.2	92.4	70.7
102.5	82.0	100.2	110.4	116.4	117.3	115.7	108.0	115.1	99.1	96.3	86.8	81.0
108.1	86.8	105.3	117.9	121.8	128.8	129.3	124.4	114.6	101.7	102.5	86.3	77.5
112.6	84.3	104.0	114.4	129.9	129.2	131.2	125.4	123.5	108.1	111.8	101.3	88.2
110.0	86.3	101.0	111.3	122.4	123.2	126.8	119.7	115.1	113.8	108.7	105.7	85.7
101.9	85.1	89.2	103.6	112.7	116.9	120.7	111.2	103.5	99.4	100.8	92.6	86.7
94.1	89.8	87.6	98.7	102.5	109.5	104.5	100.5	94.5	87.8	89.6	86.3	78.3
91.3	89.1	91.7	93.7	98.1	100.8	98.6	91.7	88.8	87.3	89.0	87.5	79.4
94.2	96.7	98.6	97.7	99.1	96.7	93.5	95.6	93.2	90.0	92.8	90.8	85.4
96.5	95.8	99.1	94.6	94.3	93.6	97.9	101.3	99.8	103.7	98.3	92.6	87.3
97.3	93.3	97.5	96.3	90.3	96.4	98.8	107.9	106.5	99.7	97.5	98.5	85.4
96.1	90.4	95.9	94.0	85.9	94.9	98.9	107.0	107.5	100.4	97.4	94.2	82.4
94.7	86.3	91.4	89.4	92.1	99.4	100.3	110.3	104.8	100.0	91.2	86.6	84.7

COL AVG 86.1 93.6 99.5 102.6 105.2 107.5 108.1 108.3 105.9 104.6 95.9 84.5

RANGE
PERCENT

VRANGE
FT/MIN

COUNT
PERCENT

INSIDE OF ELBOW

10	980. - 1198.	51.0
15	926. - 1250.	72.1
25	817. - 1361.	90.6
4	654. - 1529.	100.0

RMS= 0.141

DEV. OF MAX=0.355

DEV. OF MIN=0.328

FIGURE 29 VELOCITY DATA FOR TEST 19 AT LOCATION 4 **CORE OUTLET - REACTOR INLET MODEL DESIGN #2**

JOB: SCS-2
 DATE OF TEST: 02-08-1991

TRAVERSE LOCATION: T19-L4-1
 DENSITY: .0743(LB/FT³)

ORIFICE FLOWRATE= 3070ACFM

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE=-3.4 IN.H2O

NUMERICAL AVE. VELOCITY = 1087. FT/MIN

MODEL VELOCITY HEAD(Orifice)=0.065IN.H2O

VELOCITY(FT/MIN)
 ROW AVG

966.	1177.	977.	1070.	980.	671.	939.	966.	926.	934.	964.	957.	894.
997.	1020.	1044.	1041.	1001.	895.	926.	945.	967.	1004.	1023.	1085.	1003.
1049.	1106.	1092.	1109.	1047.	983.	975.	1015.	1024.	1045.	1040.	1129.	1020.
1044.	1115.	1074.	1057.	1013.	986.	968.	974.	969.	1041.	1109.	1121.	1097.
1063.	1098.	1117.	1066.	1037.	1003.	1023.	1037.	1038.	1058.	1087.	1097.	1094.
1059.	1090.	1122.	1092.	1044.	991.	1028.	1046.	1022.	1033.	1092.	1098.	1049.
1075.	1012.	1064.	1043.	1013.	1064.	1086.	1119.	1072.	1104.	1128.	1117.	1076.
1104.	1026.	1064.	1055.	1051.	1099.	1138.	1159.	1088.	1201.	1183.	1096.	1086.
1136.	1077.	1077.	1093.	1103.	1132.	1138.	1191.	1113.	1243.	1217.	1139.	1112.
1157.	1072.	1065.	1109.	1112.	1160.	1195.	1214.	1181.	1256.	1204.	1176.	1143.
1130.	1054.	1051.	1068.	1087.	1142.	1150.	1181.	1128.	1243.	1197.	1155.	1105.
1090.	1054.	1054.	1086.	1022.	1084.	1111.	1115.	1083.	1131.	1134.	1115.	1086.
1098.	1059.	1070.	1084.	1057.	1138.	1111.	1148.	1088.	1134.	1065.	1091.	1126.
1131.	1045.	1089.	1106.	1089.	1160.	1202.	1222.	1181.	1169.	1133.	1082.	1101.
1149.	1068.	1107.	1131.	1168.	1164.	1232.	1229.	1154.	1184.	1118.	1116.	1122.
1162.	1093.	1122.	1155.	1109.	1199.	1226.	1218.	1147.	1206.	1167.	1146.	1158.
1136.	1050.	1071.	1118.	1147.	1166.	1224.	1158.	1109.	1156.	1156.	1155.	1118.
1116.	1042.	1043.	1118.	1123.	1140.	1153.	1118.	1097.	1126.	1213.	1114.	1124.
1046.	1055.	1076.	1020.	984.	1080.	1053.	1037.	1063.	1001.	1057.	1064.	1063.
1061.	1075.	1062.	1024.	978.	1054.	1074.	1081.	1092.	1047.	1069.	1084.	1081.
1066.	1079.	1032.	1061.	1022.	1044.	1111.	1051.	1111.	1066.	1078.	1078.	1057.
1094.	1123.	1091.	1063.	1005.	1025.	1115.	1163.	1164.	1106.	1068.	1106.	1095.
1091.	1101.	1075.	1107.	1001.	1038.	1126.	1127.	1154.	1081.	1125.	1105.	1056.
1077.	1115.	1076.	1122.	1061.	997.	1096.	1111.	1125.	1017.	1056.	1069.	1080.
COL AVG	1074.	1071.	1082.	1052.	1067.	1100.	1110.	1087.	1108.	1112.	1104.	1081.

VELOCITY(% OF NUM. AVE.)
 ROW AVG

88.8	104.2	89.5	94.9	90.2	80.1	86.4	90.7	85.1	85.9	88.6	88.0	82.2
91.6	94.0	96.0	95.8	92.1	82.3	85.1	86.9	89.0	92.4	94.1	99.8	92.3
96.5	101.9	100.4	102.0	96.3	90.4	89.7	93.3	94.2	96.1	95.6	103.9	93.8
96.0	102.6	98.8	97.2	93.2	90.7	89.0	89.6	89.	95.7	102.0	103.1	100.8
97.7	100.9	102.7	98.0	95.4	92.2	94.0	95.4	95.5	97.5	99.9	100.9	100.6
97.4	100.3	103.2	100.4	96.0	91.2	94.5	96.2	94.0	95.0	100.4	101.0	96.4
98.8	95.0	97.6	95.9	93.1	97.8	99.8	103.0	98.6	101.5	103.7	102.7	98.9
101.5	94.6	97.8	97.0	96.6	101.1	104.7	106.6	100.0	110.5	108.8	100.8	99.9
104.5	99.0	99.0	100.5	101.4	104.1	104.6	105.6	102.3	114.3	111.9	104.7	102.3
106.4	92.8	97.9	102.2	106.7	109.9	111.7	108.6	115.5	110.8	108.2	105.1	105.1
107.9	97.1	96.7	98.2	100.0	105.0	105.7	108.6	102.8	114.3	110.0	106.2	101.6
100.2	96.9	96.9	99.9	94.0	99.9	102.2	102.6	99.6	104.0	104.3	102.6	99.9
100.9	97.4	98.4	99.7	97.2	104.6	102.2	105.6	100.1	104.3	98.0	100.4	103.6
104.0	96.1	100.1	101.7	100.1	106.6	110.5	112.5	108.6	107.5	104.2	99.5	101.2
105.7	98.2	101.8	104.0	107.5	107.1	113.3	113.1	106.1	108.8	102.8	102.7	103.1
106.9	100.5	103.2	106.2	102.0	110.5	112.8	112.0	105.5	110.9	107.3	105.4	106.5
104.5	96.6	98.5	102.8	105.5	107.5	112.6	106.5	102.0	106.3	106.3	106.2	102.9
102.8	95.8	95.9	102.8	103.3	104.9	106.1	102.8	100.9	103.5	111.5	102.4	103.4
96.2	97.1	99.1	93.8	90.5	99.3	96.8	95.4	97.8	92.1	97.2	97.6	97.7
97.5	99.2	97.7	94.2	89.9	97.0	98.8	99.4	100.4	96.3	98.3	99.7	99.4
98.0	99.2	94.9	97.6	94.0	96.0	102.2	96.6	102.2	98.1	99.1	99.2	97.2
100.6	102.0	100.0	97.7	92.5	94.2	102.5	107.0	107.1	101.7	98.2	101.7	100.7
100.7	101.2	98.8	101.6	92.0	95.5	103.5	103.6	106.1	99.9	103.5	101.6	97.1
99.1	102.6	99.0	103.2	97.6	91.7	100.8	102.2	103.4	93.6	97.1	98.3	99.4
COL AVG	98.8	96.5	99.5	96.8	98.2	101.2	102.1	100.0	101.9	102.2	101.5	99.4

INSIDE OF ELBOW

RAWSIZE PERCENT	VRANGE FT/MIN	COUNT PERCENT
10	979. - 1196.	87.6
15	924. - 1250.	98.6
25	816. - 1259.	2100.0
40	852. - 1521.	2100.0

RMS= 0.061

DEV. OF MAX=0.155

DEV. OF MIN=0.199

FIGURE 3a VELOCITY DATA FOR TEST 22 AT LOCATION 2 DOWNSTREAM OF FIRST DIFFUSER REACTOR INLET MODEL DESIGN #2

JOB: SCS-2

DATE OF TEST: 02-21-1991

TRAVERSE LOCATION: T22-L2-2

DENSITY= .0743(LB/FT³)

ORIFICE FLOWRATE= 6602ACFK

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE=-4.15 IN.H2O

NUMERICAL AVE. VELOCITY = 2558. FT/MIN

MODEL VELOCITY HEAD(Q-orifice)=1.897IN.H2O

VELOCITY(FT/MIN)

ROW AVE

2332.	2303.	2040.	2395.	2339.	2296.	2345.	2369.	2570.
2461.	2393.	2357.	2558.	2411.	2311.	2575.	2847.	2233.
2574.	2349.	2501.	2660.	2555.	2491.	2769.	2628.	2641.
2583.	2360.	2356.	2620.	2659.	2623.	2612.	2641.	2790.
2615.	2491.	2647.	2605.	2596.	2642.	2716.	2560.	2664.
2619.	2447.	2504.	2650.	2650.	2642.	2686.	2580.	2795.
2634.	2410.	2421.	2637.	2707.	2658.	2671.	2673.	2896.
2712.	2517.	2635.	2619.	2636.	2767.	2893.	2636.	2993.
2674.	2441.	2597.	2654.	2611.	2689.	2792.	2693.	2914.
2557.	2324.	2387.	2616.	2537.	2579.	2571.	2660.	2781.
2423.	2349.	2346.	2463.	2349.	2232.	2604.	2811.	2230.
2515.	2403.	2416.	2481.	2476.	2430.	2532.	2785.	2600.

COL AVE

2399.	2434.	2580.	2544.	2530.	2647.	2657.	2675.
-------	-------	-------	-------	-------	-------	-------	-------

VELOCITY(% OF NUM. AVE.)

ROW AVE

91.2	90.0	79.7	93.6	91.4	89.7	91.7	100	92.6	100.5
96.2	93.5	92.1	100.0	94.2	90.3	100.7	111.3	87.3	103.2
100.6	91.8	97.8	104.0	99.9	97.4	108.2	102.7	103.2	109.1
100.9	92.3	92.1	102.4	103.9	102.5	102.1	103.2	104.1	109.2
102.2	97.4	103.5	101.8	101.5	103.3	106.2	100.1	104.1	109.2
102.4	95.6	97.9	103.6	103.6	103.3	105.0	100.9	104.5	113.2
103.0	94.2	94.6	103.1	105.8	103.9	104.4	104.5	113.9	117.0
106.0	98.4	103.0	102.4	103.0	108.2	113.1	103.0	108.7	101.6
104.5	95.4	101.5	103.7	102.0	105.1	109.1	105.3	108.7	101.6
99.9	90.8	93.5	102.3	99.2	100.8	100.5	104.0	109.9	101.6
94.7	91.8	91.7	96.3	91.8	87.2	101.8	109.9	108.7	101.6
98.3	93.9	94.4	97.0	96.8	95.0	99.0	108.9	101.6	101.6

COL AVE

93.8	95.1	100.9	99.4	98.9	103.5	103.9	104.6
------	------	-------	------	------	-------	-------	-------

BANDSIZE
PERCENT

VRANGE
FT/MIN

COUNT
PERCENT

10	2302. - 2814.	89.6
15	2174. - 2942.	97.9
25	1919. - 3198.	100.0
40	1535. - 3582.	100.0

RMS= 0.068

DEV. OF MAX=0.170

DEV. OF MIN=0.203

FIGURE 31 VELOCITY DATA FOR TEST 22 AT LOCATION 3 CORE INLET - REACTOR INLET MODEL DESIGN #2

JOB: SC6-2
DATE OF TEST: 02-21-1991

TRAVERSE LOCATION: T22-L3-1
DENSITY: .0743(LB/FT³)

ORIFICE FLOWRATE: 6597ACFM

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE=-3.85 IN.H₂O

NUMERICAL AVE. VELOCITY = 1078. FT/MIN

MODEL VELOCITY HEAD(Q-orifice)=0.298IN.H₂O

VELOCITY(FT/MIN)

ROW AVG

926.	947.	952.	894.	927.	994.	927.	881.	855.	902.	961.	1012.	884.
1036.	929.	1076.	1015.	1035.	1086.	1069.	1047.	981.	958.	1095.	1135.	1002.
1121.	1030.	1120.	1104.	1071.	1202.	1206.	1197.	1102.	1058.	1146.	1178.	1046.
1153.	1003.	1163.	1058.	1129.	1245.	1292.	1246.	1158.	1126.	1202.	1164.	1055.
1155.	1039.	1111.	1152.	1189.	1213.	1240.	1211.	1113.	1143.	1099.	1040.	1041.
975.	972.	963.	1007.	1054.	1005.	1000.	980.	953.	952.	951.	943.	925.
977.	903.	917.	963.	964.	1001.	1005.	960.	1015.	1016.	987.	1016.	972.
1070.	885.	969.	1043.	1020.	1098.	1144.	1094.	1104.	1109.	1096.	1188.	1088.
1152.	879.	1019.	1108.	1146.	1203.	1224.	1203.	1212.	1200.	1216.	1258.	1161.
1144.	840.	957.	1031.	1189.	1216.	1239.	1244.	1200.	1240.	1232.	1206.	1138.
1058.	821.	864.	971.	1103.	1096.	1115.	1192.	1129.	1187.	1141.	1105.	968.
960.	881.	890.	921.	989.	996.	1010.	1036.	997.	1015.	976.	951.	859.
1019.	938.	987.	1034.	1051.	1092.	1091.	1049.	1010.	988.	983.	1019.	986.
1134.	964.	1085.	1157.	1182.	1233.	1222.	1173.	1126.	1088.	1104.	1166.	1110.
1188.	934.	1052.	1197.	1266.	1314.	1312.	1279.	1205.	1176.	1176.	1218.	1122.
1156.	920.	1009.	1105.	1241.	1254.	1266.	1256.	1201.	1241.	1142.	1203.	1037.
1059.	968.	952.	1044.	1076.	1108.	1116.	1148.	1063.	1194.	1087.	1049.	905.
1012.	1091.	996.	1024.	998.	1003.	1027.	1034.	1033.	1130.	982.	934.	887.
1007.	1187.	1140.	1170.	1108.	1043.	1020.	1035.	1004.	1044.	1005.	1019.	980.
1151.	1147.	1225.	1257.	1201.	1153.	1152.	1145.	1050.	1145.	1083.	1129.	1128.
1154.	1080.	1229.	1223.	1190.	1147.	1171.	1186.	1016.	1138.	1128.	1174.	1162.
1129.	1076.	1213.	1204.	1141.	1092.	1121.	1174.	1007.	1094.	1125.	1192.	1105.
1074.	1070.	1146.	1110.	1105.	1020.	1092.	1130.	943.	1053.	1021.	1160.	1046.
1016.	997.	1062.	1046.	1025.	991.	1003.	1069.	895.	961.	1008.	1088.	1039.
COL AVG	979.	1046.	1077.	1100.	1117.	1128.	1124.	1057.	1090.	1081.	1106.	1027.

VELOCITY(% OF NUM. AVE.)

ROW AVG

88.1	87.9	88.3	82.9	86.0	92.3	86.0	81.7	79.3	83.7	89.1	93.9	82.1
96.1	86.2	99.9	94.2	96.1	100.7	99.2	100.7	91.1	88.9	101.6	105.4	93.0
104.1	95.6	103.9	102.4	99.4	111.6	112.0	110.7	102.3	98.2	106.4	109.3	97.0
107.0	93.0	107.9	98.0	104.7	115.5	119.9	115.7	107.5	104.5	111.6	108.0	97.9
105.1	96.5	103.1	106.9	100.4	112.5	115.1	112.4	103.3	106.1	107.0	96.6	96.6
90.5	90.2	89.4	93.5	97.8	93.3	92.8	90.9	88.5	88.3	88.3	87.3	85.8
90.6	83.8	85.1	89.4	89.4	92.9	93.3	89.0	94.2	94.3	91.6	94.3	90.2
99.7	82.2	90.0	96.8	94.7	101.9	106.1	101.5	102.5	102.9	101.7	110.2	101.0
106.9	81.6	94.6	102.9	106.3	111.6	113.6	111.7	112.4	111.3	112.9	116.7	107.8
106.2	78.0	88.8	95.6	110.4	112.9	115.0	115.4	111.3	115.1	114.3	112.0	105.6
98.2	76.2	80.1	90.1	102.4	101.7	103.5	110.7	104.8	110.2	105.9	102.6	89.8
89.1	81.7	83.6	85.4	91.8	92.4	93.7	96.1	92.5	94.2	90.6	88.2	79.7
94.6	87.1	91.6	95.9	97.5	101.3	101.2	97.3	93.7	91.7	91.2	94.6	91.5
105.3	89.5	100.7	107.4	109.7	114.5	113.4	108.9	104.5	101.0	102.5	108.3	103.0
110.2	86.7	97.6	111.1	117.5	121.9	121.8	118.7	111.8	109.1	109.1	113.0	104.1
107.3	85.4	93.7	102.6	115.2	116.4	117.5	116.5	111.4	115.2	105.9	111.7	96.2
98.3	89.8	88.3	96.8	99.8	102.8	103.6	106.6	98.7	110.8	100.9	97.4	84.0
93.9	101.3	92.5	95.0	92.6	93.0	95.3	95.9	95.9	104.9	91.1	86.7	82.3
98.6	110.1	105.8	108.6	102.8	96.8	94.6	96.0	93.1	96.9	93.2	94.5	91.0
106.8	106.4	113.7	116.6	111.5	107.0	106.9	106.2	97.5	106.3	100.5	104.8	104.6
107.1	100.2	114.1	113.5	110.5	106.5	108.7	110.2	94.3	105.7	104.7	109.0	107.8
104.8	96.9	112.6	111.8	105.9	101.4	104.1	109.0	93.4	101.5	104.4	110.6	102.6
99.7	99.3	106.3	103.0	102.7	94.6	101.3	104.9	87.5	97.8	94.8	107.6	97.1
94.1	92.5	96.5	97.2	95.1	92.0	93.0	99.2	83.0	89.2	93.6	101.0	96.5
COL AVG	90.9	97.0	99.9	102.1	103.6	104.7	104.3	98.1	101.1	100.3	102.7	95.3

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

VRANGE

FT/MIN

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

VRANGE

FT/MIN

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

VRANGE

FT/MIN

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

VRANGE

FT/MIN

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

VRANGE

FT/MIN

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

VRANGE

FT/MIN

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

VRANGE

FT/MIN

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

PERCENT

VRANGE

FT/MIN

PERCENT

PERCENT

FIGURE 30 VELOCITY DATA FOR TEST 22 AT LOCATION 4 CORE OUTLET - REACTOR INLET MODEL DESIGN#2

JOB: SES-2
DATE OF TEST: 02-21-1991

TRAVERSE LOCATION: T22-L4-1
DENSITY: .0742(LB/FT³)

ORIFICE FLOWRATE= 6608ACFM

** FLOW OUT OF PAPER **

MODEL STATIC PRESSURE=-4.55 IN.H2O

NUMERICAL AVE. VELOCITY = 1078. FT/MIN

MODEL VELOCITY HEAD(Q-orifice)=0.2991IN.H2O

VELOCITY FT/MIN
ROW AVG

966.	1139.	1044.	963.	1002.	906.	928.	924.	939.	908.	916.	965.	957.
975.	917.	926.	998.	960.	938.	976.	975.	992.	965.	1013.	1035.	1004.
1047.	1159.	1002.	1030.	1029.	1025.	1015.	1010.	1053.	996.	1091.	1078.	1076.
1045.	1043.	1070.	1009.	1007.	1020.	1049.	994.	1035.	1009.	1141.	1129.	1079.
1095.	1136.	1108.	1076.	1074.	1072.	1049.	1090.	1032.	1077.	1140.	1131.	1150.
1042.	1100.	1066.	1057.	1037.	993.	1010.	1024.	969.	1040.	1021.	1114.	1069.
1048.	1026.	1069.	1022.	1010.	1007.	1038.	1069.	1051.	1060.	1043.	1111.	1061.
1084.	1043.	1061.	1090.	1020.	1088.	1079.	1124.	1023.	1112.	1084.	1159.	1127.
1111.	1090.	1053.	1056.	1107.	1078.	1109.	1112.	1043.	1217.	1170.	1161.	1133.
1131.	1061.	1060.	1067.	1111.	1095.	1167.	1206.	1072.	1227.	1214.	1190.	1108.
1098.	1049.	1013.	1042.	1070.	1116.	1093.	1197.	1085.	1134.	1136.	1149.	1098.
1050.	1028.	1005.	1020.	981.	1027.	1064.	1109.	1018.	1066.	1122.	1122.	1043.
1056.	1057.	1036.	1027.	998.	1034.	1028.	1074.	1032.	1103.	1086.	1094.	1109.
1115.	1101.	1038.	1104.	1081.	1102.	1157.	1135.	1090.	1152.	1126.	1149.	1151.
1132.	1062.	1056.	1086.	1101.	1150.	1221.	1152.	1088.	1153.	1147.	1183.	1190.
1143.	1054.	1074.	1116.	1082.	1118.	1249.	1197.	1133.	1198.	1167.	1166.	1157.
1102.	1051.	1026.	1090.	1052.	1065.	1163.	1183.	1080.	1106.	1130.	1136.	1143.
1077.	1042.	1015.	1075.	1012.	1011.	1096.	1114.	1096.	1087.	1140.	1139.	1095.
1057.	1106.	1136.	1082.	951.	1063.	1007.	1037.	1049.	1006.	1080.	1068.	1092.
1087.	1082.	1063.	1072.	1053.	1073.	1082.	1079.	1081.	1052.	1129.	1078.	1114.
1092.	1098.	1054.	1051.	1063.	1084.	1117.	1135.	1081.	1103.	1105.	1099.	1109.
1157.	1168.	1146.	1171.	1123.	1110.	1077.	1166.	1134.	1135.	1095.	1149.	1171.
1096.	1134.	1069.	1054.	1120.	1118.	1057.	1108.	1117.	1059.	1081.	1151.	1088.
1101.	1100.	1162.	1066.	1060.	997.	1181.	1205.	1054.	969.	1116.	1188.	1108.
COL AVG	1077.	1056.	1059.	1046.	1054.	1084.	1101.	1056.	1081.	1104.	1123.	1101.

VELOCITY (% OF NUM. AVE.)
ROW AVG

89.6	105.6	96.8	89.3	93.0	84.0	86.0	85.7	87.1	84.2	84.9	89.5	88.7
90.4	95.0	90.0	92.6	89.0	90.0	90.5	90.4	92.0	89.5	93.9	95.9	93.1
97.1	107.4	92.9	95.5	95.4	95.0	94.1	93.6	97.6	92.3	101.1	100.0	99.7
97.2	96.7	99.2	93.6	93.4	94.6	97.3	92.2	96.0	93.5	105.8	104.7	100.0
101.5	105.3	102.8	99.7	99.6	99.4	97.3	101.1	95.7	99.9	105.7	104.9	106.6
96.6	102.0	98.8	98.0	96.1	92.1	93.6	94.9	89.9	96.4	94.7	103.3	99.1
97.1	95.3	99.2	94.8	93.7	93.4	96.3	99.2	97.5	98.3	96.7	103.0	98.4
100.5	96.7	98.4	101.1	94.6	100.9	100.0	104.2	94.9	103.2	100.5	107.4	104.5
103.0	101.1	97.6	97.9	102.7	99.9	102.9	103.1	96.8	112.9	108.5	107.7	105.1
104.9	98.3	98.3	99.0	103.1	101.5	108.2	111.8	99.4	113.8	112.5	110.3	102.7
101.8	97.2	93.9	96.6	99.3	103.5	101.3	111.0	100.6	105.1	105.3	106.5	101.8
97.4	95.3	93.2	94.6	90.9	95.2	96.7	102.9	94.4	98.8	104.0	104.0	96.7
98.6	98.0	96.1	95.2	92.5	95.8	95.3	99.6	95.7	102.3	100.7	101.5	102.8
102.4	102.1	96.3	102.3	100.3	102.2	107.3	105.2	101.0	106.8	104.4	106.5	106.7
105.0	98.5	98.0	100.7	102.1	106.6	113.2	106.9	100.9	106.9	106.4	109.6	110.3
105.9	97.7	99.6	103.5	100.3	103.7	115.8	110.3	105.0	111.1	108.2	108.2	107.3
102.2	97.4	95.1	101.1	97.5	98.8	107.8	109.7	100.2	102.6	104.8	105.3	105.9
99.6	96.6	94.1	99.7	93.8	93.7	101.7	103.3	101.6	100.8	105.7	105.6	101.5
98.0	102.8	105.3	100.3	88.2	98.6	93.4	96.2	97.3	93.3	100.2	99.0	101.2
100.1	100.4	98.5	99.4	97.7	99.5	100.3	100.1	100.2	97.5	104.7	100.0	103.3
101.2	101.9	97.7	97.5	98.6	100.5	103.6	105.3	100.2	102.2	102.5	101.9	102.9
105.4	108.3	106.3	108.6	104.1	102.9	99.9	108.2	105.2	105.2	101.5	106.6	108.6
101.6	105.2	99.1	97.7	103.8	103.6	98.0	102.8	103.6	98.2	100.2	106.8	100.9
102.0	102.0	107.7	98.9	98.2	92.5	109.5	111.7	97.8	89.9	103.5	110.2	102.8
COL AVG	99.9	98.0	98.2	97.0	97.7	100.5	102.1	97.9	100.2	102.3	104.1	102.1

RANGE
PERCENT

VRANGE
FT/MIN
COUNT
PERCENT

INSIDE OF ELBOW

RMS= 1.052

DEV. OF MAX=0.156

DEV. OF MIN=0.160

END

**DATE
FILMED**

9 / 8 / 92