Savannah River Site

DOES NOT CONTAIN
UNCLASSIFIED CONTROLLED
NUCLEAR INFORMATION

Reviewing
Official:

R. M. Gregory
(Name and Title)

Date:

9/30/91

REACTOR RESTART DIVISION

CONFIGURATION MANAGEMENT PROGRAM PLAN (U)

Revision 1

September 25, 1991

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

CONFIGURATION MANAGEMENT PROGRAM PLAN (U)

by

Westinghouse Savannah River Company
Savannah River Site
Aiken, South Carolina 29808

JUL 24 1992

The information contained in this document was prepared in connection with work done under Contract No. DE-AC09-89SR18035 with the U.S. Department of Energy. By acceptance of this report, the publisher and/or recipient acknowledges the U.S. Government's right to retain a nonexclusive, royalty-free license in and to any copyright covering this report, along with the right to reproduce and to authorize others to reproduce all or part of the copyrighted report.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Westinghouse
Savannah River Company

P. D. Rice
Vice President and General Manager
Reactor Restart Division

P. O. Box 616
Aiken, SC 29802

RRD-DOE-910082

September 25, 1991

Mr. Frank R. McCoy, III, Director
SR Restart Special Projects Office
U. S. Department of Energy
Savannah River Operations Office
P. O. Box A
Aiken, South Carolina 29802

Dear Mr. McCoy:

RRD CONFIGURATION MANAGEMENT PROGRAM PLAN, REV. 1 (U)

This letter transmits the revised RRD Configuration Management Program Plan and the implementation schedule for your review and approval. The Program Plan has been revised to incorporate comments by DNFSB, RRD and DOE, including your comments provided with the conditional approval memorandum transmitted on July 11, 1991. The implementation schedule reflects the planned activities, pending approval of the FY '92 budget. Submittal of this plan satisfies the requirements to develop a CM program plan as stated in Section 5.4 of the Safety Evaluation Report.

The revised Program Plan defines the program objectives, scope and technical approach to configuration management. It has also defined a new element, Codes and Standards, to address the needs for engineering standards development. A summary of implementation tasks for each program is also provided.

The RRD CM Program Plan is responsive to the SRS Configuration Management Policy and DOE Orders. It is a comprehensive document that lays the foundation for the program and provides the basis for implementing tasks.

If you have any questions regarding this plan, please contact Fred Beranek at 557-9230.

Yours truly,

Paul D. Rice
Vice President and General Manager
Reactor Restart Division

PDR:DC:kbk

CC: S. J. Smith, 704-C
D. B. Rankin, 704-C
T. W. Greene, 703-A
F. Beranek, 704-C

L. H. Sain, 707-C
D. E. Haley, Jr., CDC
D. W. Freeman, 706-14C
H. Burruss, 706-14C

The Reactor Restart Division Configuration Management Program Plan represents the comprehensive approach essential to ensuring the effective implementation of a configuration management program. All affected RRD departments have reviewed this program plan revision and concurred with the program strategies. RRD will align CM interfaces with external support organizations through the SRS CM and other divisional CM program plans.

RRD is committed to fully achieve the stated CM objectives and will provide the necessary resources to implement the Program.

	CONCURRENCE	DATE
ROD	<u> </u> Stephen J. Smith, Manager, ROD	<u>9.24.91</u>
RTAP	<u> </u> for Leo H. Sain, Manager, RTAP	<u>9/12/91</u>
RQAA	<u> </u> D. Brent Rankin, Manager, RQAA	<u>9/25/91</u>
E&PD/CM	<u> </u> Damon E. Haley, Manager, SRS CM	<u>9/16/91</u>
BS&F/IRM	<u> </u> Thomas W. Greene, Manager, Info. Services	<u>9/16/91</u>

	APPROVALS	DATE
RED/EP	<u> </u> David W. Freeman, Deputy Manager, EP	<u>9/12/91</u>
RED	<u> </u> Fred Berahek, Manager, RED	<u>9/12/91</u>
RRD	<u> </u> Paul D. Rice, Vice President, RRD	<u>9/27/91</u>

REVISION LOG

Revision Number	Issue Date	Description	Pages Affected
0	3/6/91	Initial Issue	All
1	9/25/91	Incorporate DOE comments Divide rev. 0 into CM Program Plan and Integrated Action Plan	All

Executive Summary

Westinghouse Savannah River Company (WSRC) has established a configuration management (CM) plan to execute the SRS CM Policy and the requirements of the DOE Order 4700.1. The Reactor Restart Division (RRD) has developed its CM Plan under the SRS CM Program and is implementing it via the RRD CM Program Plan and the Integrated Action Plan. The purpose of the RRD CM program is to improve those processes which are essential to the safe and efficient operation of SRS production reactors.

The CM Program Plan forms a basis for implementation by establishing the CM objectives, defining the program scope and delineating the technical approach for program enhancement. It also provides a summary of the implementation tasks and management responsibilities. The Program is divided into four phases: Definition, Assessment, Enhancement and Validation. RRD has adopted the following CM objectives to assess the defined program elements:

1. Technical baseline information is defined, documented and retrievable.
2. Plant accurately reflects design intent and conforms to design and DOE requirements.
3. Plant documents and databases accurately reflect the physical plant, change status and its functional characteristics.
4. Changes to the technical baseline, the physical plant and its documents are properly evaluated, approved and incorporated.

The scope of each program element will be based on a graded approach commensurate with the relative importance to safety, security, industrial and process requirements, and business needs. The specific program elements are:

- 1.0 Baseline Configuration
- 2.0 Design Basis
- 3.0 Change Control
- 4.0 Document Control
- 5.0 Material Control
- 6.0 Information Systems Integration
- 7.0 Administrative Controls
- 8.0 Plant Status Control
- 9.0 Code & Standards

The RRD CM Program takes advantage of the various process assessments and the pre-restart enhancements initiated earlier. It consolidates those initiatives with the future CM efforts into a single process which will ensure integration and coordination of all CM-related activities.

The RRD CM organization combines the staff of RED Engineering Programs Section (RED/EP) under the supervision of the Manager of RED/EP and the matrixed staff from various implementing organizations. The RED/EP Section will be involved in specific program tasks to ensure technical consistency, adequacy and interface among tasks in meeting the overall objectives of the CM Program.

The CM Group of the RED/EP Section will coordinate and monitor all tasks. The specific relationship and involvement of the CM Group in the tasks being performed by the matrixed organization will vary depending on the task and will be formalized via the Integrated Action Plan which will include functions, assignments and responsibilities.

The RRD CM Program will enhance the functional performance within each organization supporting the operation of the reactor facilities. Specifically, benefits will include:

- Integrated source of information to support engineering, operations and maintenance activities,
- More effective and efficient organizational responsibilities and interfaces,
- Timely and complete update of changes, and
- Improved awareness of and adherence to DOE and design basis requirements.

Full implementation will take three to four years and costs approximately \$75 million.

TABLE OF CONTENTS

Executive Summary.....	iii
1.0 Introduction	1
2.0 CM Program Overview.....	2
3.0 Technical Approach to CM.....	3
3.1 Develop CM Definition and Objectives	4
3.1.1 Define CM Program.....	4
3.1.2 Develop Program Objectives.....	4
3.1.3 Define Program Elements/Scope	6
3.2 Assessment and Enhancements	9
3.2.1 Process Review.....	9
3.2.2 Program Enhancements.....	10
3.3 Implement Enhancements.....	10
3.3.1 Scope of Enhancement.....	10
3.3.2 Restart CM Initiatives.....	12
3.3.3 Long-Term Integration.....	15
3.4 Program Validation.....	16
4.0 Program Implementation.....	18
4.1 Task Specifics & Responsibilities.....	18
4.2 Management and Organization.....	21
4.2.1 SRS Site Configuration Management.....	21
4.2.2 RRD Configuration Management Organization.....	21
4.2.3 RED Responsibilities	22
4.2.4 RED/EP Organization Responsibilities.....	23
5.0 References.....	25

1.0 Introduction

The Savannah River Site (SRS) Configuration Management Plan¹ establishes the requirements and responsibilities for implementing configuration management (CM) within each WSRC division. In turn, the Reactor Restart Division (RRD) has established its Configuration Management Program² to set the goals and objectives for CM implementation. This revision of the RRD CM Program Plan is intended to align the CM processes with those divisions with whom RRD interfaces and to divide the Program Plan (Rev. 0) into two parts:

- A program plan which defines the objectives, scope, and technical approach to CM
- An integrated action plan which provides the details for implementing CM for each program element, including specific task descriptions and projected schedules.

The RRD CM Program is primarily driven by the need to define and enhance CM processes to ensure that the existing production reactors are operated safely and maintained within their design bases beyond the current restart initiatives. This need is exemplified by the results of many site engineering programs and recent evaluations of configuration management processes (e.g. design change control, document control, etc.).

The RRD CM Program will work within the broad guidelines and requirements of the site program to strengthen the configuration management processes to meet the needs of the operating facilities. Specifically, the Program will focus on re-establishing the technical baseline for the existing production reactors, using a graded approach as the selection criteria.

During program development, several restart-related CM enhancement activities were underway to assess and enhance the existing plant processes. In particular, the design change control and document control processes have been significantly improved by a concerted effort involving various intra-divisional and inter-divisional groups. The RRD CM Program will initiate, coordinate and build upon those enhancement efforts. It will provide a systematic approach to establish and control technical baselines to ensure that the facilities, structures, systems, components and software at the production reactors meet design, performance and operational requirements throughout their life cycles. The objectives of the Program and the application to specific program elements are discussed in the following sections.

The CM Program also addresses the concerns in the U. S. DOE Safety Evaluation Report (SER) for restart of K-Reactor (SER 5.4)³. This Program Plan is responsive to the SRS Configuration Management Policy⁴, U. S. DOE Orders 4700.1⁵ and SR 5700.6C (the implementing order for ASME NQA-1, "Quality Assurance Program Requirements for Nuclear Facilities"). The RRD CM Program was initially documented in the RRD Configuration Management Course of Action Report⁶ and the RRD CM Program Plan (Rev. 0, issued via Memo RRD-CFM-910070, 3/6/91). The current revision is based on the following industry guidance documents:

1. Design Basis Program Guidelines - Nuclear Management and Resources Council (NUMARC 90-12)
2. Configuration Management Program - Nuclear Information and Records Management Association (PP 02-1989)
3. Implementing a CM Enhancement Program for a Nuclear Facility - Nuclear Information and Records Management Association (PP 03-1991)
4. Report on Configuration Management in the Nuclear Utility Industry - Institute of Nuclear Power Operations (INPO 87-006)

NOTE: References are indicated by superscript numbers in this document.

2.0 CM Program Overview

The RRD CM Program establishes the requirements and responsibilities for implementing the SRS Configuration Management Policy in the production reactors. This document defines the program, its objectives and those plant activities involved in the CM processes.

The approach to establish the RRD CM Program for the production reactors is summarized in the following steps. These steps can be categorized into four (4) distinctive phases, as recommended in the initial course of action for the RRD Configuration Management Program. The development and implementation of all aspects of the Program are expected to require approximately three to four years, based on experience in the commercial nuclear industry.

PHASES			
1. Definition	2. Assessment	3. Enhancement	4. Validation
CM Definition CM Program Objectives CM Program Elements Configuration Items & Processes	Assessment/Modeling Develop Enhancements	Implement Enhance- ments Monitor Progress	Validation/Feedback Refine Processes

Phase 1 defines configuration management, program objectives, program elements and configuration items. In order to consistently apply CM across the Reactor Restart Division, a clear and concise CM definition is adopted for the Program (see Section 3.1.1). With CM defined, program objectives can be derived and applied to each program element. The elements are the building blocks that support one another in achieving the objectives. Within each element, there are various configuration items which are controlled by the CM processes. Phase 1 results are documented in the CM Program Plan and serves as the basis for program implementation.

In Phase 2, the configuration items and CM processes are assessed against the established objectives. There are a number of restart-related initiatives which addresses these points. The CM Program would integrate and build upon the many on-going restart assessments, engineering programs and process enhancement activities. The enhancement tasks based on various assessments were originally identified in the RRD CM Program Plan (Rev. 0). Additional assessments will be performed, where necessary, to better define the enhancement activities. For a complex process, a process model will be developed to illustrate the process interfaces and to support the implementation and validation phases. Enhancement activities identified by the assessments will be prioritized and documented in the Integrated Action Plan. Section 3.2 presents the results of several formal process assessments and the proposed areas of enhancements.

Phase 3 represents the implementation of the enhancements to effect changes in the support organizations. The REL/CM Group will coordinate the development, implementation and validation of the enhancements. Effective configuration management will be achieved when all objectives are met.

Phase 4 represents the validation and maintenance of Configuration Items and CM processes. From time to time, the processes may require refinement based on feedback and re-assessments. The completion of this phase represents the endpoint of the program. However, the CM functional responsibilities within each process will continue to co-exist and their performance will be monitored by the RED Engineering Assurance function.

3.0 Technical Approach to CM

The RRD CM Program Plan presents the approach of the overall program. It implements Phase 1 steps to develop the basis for the program. It also identifies the approach to Phase 2 assessments, taking into account restart initiatives and long-term implementation activities. Enhancements are documented in specific engineering program assessment reports and the Integrated Action Plan. The RRD CM functional group will coordinate and monitor enhancement activities. Section 4.0 describes the responsibilities for those activities.

The 4-phase approach was derived from proven industry practices. It forms a systematic approach to build the CM foundation by 1) Developing a basis for evaluation, 2) Developing consistent and implementable enhancements, 3) Optimizing enhancement efforts to achieve CM, and 4) Maintaining CM in an operating facility. The benefits of this approach include:

- ❑ A documented basis to support the justification for restart
- ❑ Consistent application of program objectives in all functional areas
- ❑ A documented assessment of how current processes and programs meet CM needs
- ❑ Identification of program strengths and vulnerabilities, and necessary improvements
- ❑ A documented basis for management acceptance of program enhancements
- ❑ A consistent basis for validation, measurement of progress and future enhancements

The Program Plan establishes the basis for an auditable and defensible program for all implementation actions. The following diagram shows the specific steps of the approach:

3.1 Develop CM Definition and Objectives

3.1.1 Define CM Program

The approach to CM begins with the development of a clear CM definition and the program objectives to establish the desired outcome of the program. Configuration management can be defined in many ways dependent upon the emphasis placed by a particular organization. In older commercial nuclear reactor plants, CM programs typically have been derived from the need to establish the design basis, which often is not readily retrievable. Thus CM programs tend to place heavy emphasis on design basis activities, perhaps even to be solely defined by a design basis reconstitution program.

RRD also defines its program with special focus on technical baseline and design change control. However, several other elements also play an important role in CM (See section on Program Elements/Scope). The program, which has finite enhancement activities, is intended to define the strategies to achieve CM objectives. Configuration management, however, is an on-going process for the supporting program elements. To ensure consistent application of CM objectives, the SRS CM Program definition has been adopted for the production reactors. It becomes the foundation for developing specific CM objectives for the facilities and the interfacing organizations.

Configuration Management is an integrated management process which:

- I. Identifies and documents the technical baseline, defined as the physical, functional, and operational characteristics of facilities, structures, systems, components, and computer software.
- II. Verifies that the physical, functional, and operational configuration of facilities, structures, systems, components, and software conform to the technical baseline documentation, including approved changes.
- III. Maintains a system for recording, safeguarding, distributing, and indicating the status of documentation on a current basis for reference and reporting purposes.
- IV. Ensures that changes to these characteristics are properly proposed, evaluated, implemented if approved, verified, and incorporated in all impacted documentation.

Definitions for various terms are derived from the SRS CM Glossary⁷ for consistency with the Site CM Program. Where necessary, RRD-specific terms are defined within this document.

3.1.2 Develop Program Objectives

The definition of configuration management is translated into implementable program objectives. When developing the objectives, the desired outcome of the program content and the methods employed to accomplish each objective were carefully considered. This provides the basis to support each of the program elements. The program objectives are represented in Figure 3-1.

The following criteria were derived from the program objectives which will be applied to measure the adequacy of each of the program elements:

OBI.	Criteria
I.	1. The technical baseline of the plant is established, documented, maintained, and retrievable.
II.	2. Plant physical structures, systems, components, and computer software conform to the approved design requirements.
III.	3. Plant physical and functional characteristics are accurately reflected in the plant documents (e.g. engineering & design, procurement, operating, maintenance, testing, and training).
IV.	4. Unnecessary plant changes are minimized through an integrated review and approval process with established approval criteria.
IV.	5. Proposed changes to plant hardware, documents and software are fully evaluated to determine their impact on other hardware, documents and software.
III.	6. Consistency is maintained among controlled documents and databases (e.g., design, procurement, operating, maintenance, testing, and training).

- III. 7. Current and thorough training programs are developed according to the latest requirements and facility configuration and are consistently implemented by qualified trainers for all applicable personnel.

3.1.3 Define Program Elements/Scope

The RRD CM Program consists of the following nine elements:

- 1.0 Baseline Configuration
- 2.0 Design Basis
- 3.0 Change Control
- 4.0 Document Control
- 5.0 Material Control
- 6.0 Information Systems Integration
- 7.0 Administrative Control
- 8.0 Plant Status Control
- 9.0 Codes & Standards

These are the functional elements necessary to establish the RRD CM Program and to implement the stated objectives. Program elements are processes that form the integral network of multi-departmental and multi-divisional support activities. It is critical not only to align configuration items and process interfaces within each program element, but among all elements as well. This section describes the application of program objectives for each program element. The effectiveness of each element will be measured against the CM objectives established for the Program. The following briefly describe the program elements and their applicable program criteria:

1.0) Baseline Configuration- This element addresses processes to identify, document and verify the "as-built" plant configuration, resolve any discrepancies with design documentation, and establish the necessary tools to ensure that plant documentation can be identified for retrieval to support the plant modification process. It contributes to the overall program objectives by assuring that the plant documents and databases accurately reflect the physical plant and its functional characteristics.

Applicable Criteria are 1, 2, 3 & 6 (see Section 3.1.2)

2.0) Design Basis- This element addresses processes to establish information that identifies the specific functions to be performed by structures, systems, or components of the plant and the specific values or range of values chosen for controlling parameters as reference bounds for design. These values may be:

- 1. Restraints derived from generally accepted 'state-of-the-art' practices for achieving functional goals; or
- 2. Requirements derived from analysis of the effects of a postulated accident for which a structure, system or component must meet its functional goals."
(10CFR 50.2(u))

Tasks within this element will compile design basis information into useful documents, including design requirements, functional requirements, system descriptions, operating limits, setpoints and precautions, and the rationale for their selection. The scope of this element will be based on a graded approach commensurate with the relative importance to safety, security, industrial and process requirements, and business needs.

This element contributes to the overall program objectives by assuring that the plant accurately reflects the design intent and conforms to design and DOE requirements. Since industry commercial nuclear codes & standards were not used in the design of SRS production reactors, the identification of applicable codes and standards is treated as a separate program element (9.0) to specifically determine necessary backfits.

Applicable Criteria are 1, 2, 3 & 6 (see Section 3.1.2)

3.0) Change Control- This element addresses the aggregate processes necessary to control physical and process changes to the baseline configuration, design bases and their supporting documentation. It contributes to the overall program objectives by assuring that these changes are properly proposed, evaluated, approved, implemented, verified and incorporated in all impacted documentation. This includes work control as it relates to the design change implementation process.

Applicable Criteria are 4 & 5 (see Section 3.1.2)

4.0) Document Control- This element addresses the processes necessary to ensure control of the generation, review, approval, distribution, access, usage, status, retention and retrieval of plant documents within RRD. It contributes to the overall program objectives by assuring that plant documents accurately reflect the physical plant and that the current revision is in use at the location where the prescribed activity is performed.

Applicable Criteria are 1, 3, 5 & 6 (see Section 3.1.2)

5.0) Material Control- This element addresses the processes necessary to control all stages of material specification, procurement, receipt and inspection. It also addresses processes necessary to control storage, handling, issuance and traceability of materials used in SRS reactors. It contributes to the overall program objectives by assuring that material procured for SRS reactors conforms to the design bases and design requirements throughout the material life cycle.

Applicable Criteria are 1, 2 & 6 (see Section 3.1.2)

6.0) Information Systems Integration- This element addresses the processes necessary to establish, maintain and integrate configuration item data in support of all program elements. This includes the control of data accuracy, redundancy and changes as well as system integrity, accessibility, testing and usage. It contributes to the overall program objectives by assuring that information management needs of the program elements are satisfied.

Applicable Criteria are 1, 2, 5 & 6 (see Section 3.1.2)

7.0) Administrative Control- This element addresses the processes necessary to establish, review, approve and implement policies and procedures under the CM Program. It also establishes a performance monitoring mechanism to control and report on CM activities. It contributes to the overall program objectives by aligning organizational interfaces among implementing documents and assuring that adequate training has been provided to the users.

Applicable Criteria are 3, 5, 6 & 7 (see Section 3.1.2)

8.0) Plant Status Control- This element addresses the processes to ensure that plant operations personnel are informed of plant and equipment status, and related work activities, to allow personnel to make knowledgeable decisions regarding plant operations. Plant procedures are used to provide uniform guidance for the safe operation of plant systems and components. Plant Status Control will help provide the information necessary for operations to verify that systems and components will perform their designed functions under both normal and emergency conditions. It contributes to the overall program goals by assuring that plant systems are operated within the design bases.

Applicable Criteria are 1, 2, 3 & 6 (see Section 3.1.2)

9.0) Codes and Standards- This element addresses the processes to establish applicable nuclear industry codes and engineering standards that govern the design activities for the SRS reactors. It establishes a "code of record" for the existing plant configuration and determines applicable codes and standards for future plant modifications. It contributes to the overall program objectives of assuring that the plant conforms to applicable design and DOE requirements.

Applicable Criteria are 1, 2, 3 & 6 (see Section 3.1.2)

3.2 Assessment and Enhancements

3.2.1 Process Review

In the assessment phase, CM processes are evaluated against the applicable program criteria. The RRD CM Program assessments include a series of reactor restart initiatives and separate CM functional evaluations. The following assessments were used in deriving the enhancement activities:

CM Program Process Assessments

	Program Elements Affected								
	Baseline Conf.	Design Basis	Change Control	Doc Control	Material Control	Info Systems	Admin Control	Plant Status	Codes & Standard
Evaluations Performed									
Administrative Procedures Steering Committee Review			✓	✓	✓		✓	✓	
Design Change Form Task Team Review	✓	✓	✓	✓		✓	✓		
Design Change Package Task Team Review	✓	✓	✓	✓		✓	✓		
Document Control Assessment	✓	✓	✓	✓		✓	✓	✓	✓
DOE Audits	✓	✓	✓	✓			✓		
Drawing Control Review	✓		✓	✓		✓	✓	✓	
Information Systems Architecture Study	✓	✓	✓	✓	✓	✓	✓	✓	✓
Material Control Review	✓	✓	✓	✓	✓	✓	✓		✓
Plant Status Control Review	✓		✓	✓		✓	✓	✓	
Reactor Maintenance Self-Assessment Report (U) ⁸	✓	✓	✓	✓	✓	✓	✓	✓	✓
RQA Surveillance Audits	✓	✓	✓	✓	✓	✓	✓	✓	✓
Safety Evaluation Report ³	✓	✓	✓	✓	✓		✓		✓
SRS Site Quality Audits			✓	✓	✓		✓		
Systematic Evaluation Program (SEP)		✓							✓
Technical Baseline Program	✓	✓		✓	✓	✓	✓		✓
Vertical Slice Assessment Program ⁹			✓	✓			✓		
Westinghouse Independent Safety Review (WSIR) ¹⁰	✓	✓	✓	✓	✓		✓	✓	✓

The program will integrate and build upon the many on-going restart assessments, engineering programs and process enhancement activities. Additional assessments will be performed as indicated in the Integrated Action Plan. For complex processes with many interfacing loops, a process model will be developed to illustrate the process interfaces and to support the implementation and validation phases.

Results of the assessments indicate processes that are incomplete or inadequately integrated between functional organizations. Also, the program objectives were applied against each of the program elements via the criteria presented in Section 3.1.2. The significance of the enhancement areas vary greatly. Several enhancement areas which required immediate corrective action were addressed in the restart initiatives. Certain program elements may have implemented interim corrective actions for restart. Consequently these elements will warrant further study to determine the extent of enhancements required to achieve CM objectives. An example of this is the review and integration of information systems supporting the RRD CM program elements.

Enhancements were formulated to fully achieve the CM objectives. Section 4.1 shows a summary of enhancement tasks and the implementing organizations involved.

3.2.2 Program Enhancements

Upon completing the configuration management program evaluation for a given program element, the results are consolidated into a list of enhancements that will improve the processes for that element. It is essential to have centralized control over enhancement activities and to consistently measure the progress against the program objectives. The Reactor Engineering Department/Engineering Programs Section (RED/EP) will continue to coordinate and integrate enhancement actions to optimize the results of the implementation. Enhancement actions are documented in the Integrated Action Plan. Prior to issuing the Integration Action Plan, RED/EP will coordinate reviews and approvals by the various implementing organization to better define the details of enhancement activities. During implementation, RED/EP will work with each of these groups to implement, monitor and validate the activities. Enhancements will be validated and additional adjustments made, as necessary.

The optimized and integrated processes will result in the successful management and control of the safe and efficient operation of the SRS production reactors. RRD is committed to allocate necessary resources to support these activities and to achieve the program objectives.

3.3 Implement Enhancements

3.3.1 Scope of Enhancement

The scope of the CM program enhancements is comprised of two parts: 1) those items that require configuration control (configuration item) and 2) the administrative process procedures that are used to implement configuration control.

A configuration item (CI) may be a facility, system, structure, component, or software. The criteria for selecting the configuration items are contained in the following sections. Additionally, those documents and information system data that describe the technical baseline of a configuration item (CI Descriptors) are also included in the CM

Program. Once determined, configuration items will be subject to configuration control under the requirements of the CM Program.

The administrative processes that are used to implement configuration control are governed by procedures to control and maintain the configuration and design information of the configuration items.

Facilities

The facilities that will be configuration items are those that are under the responsibility of the Reactor Restart Division (RRD) according to the Course of Action for the Configuration Management Program. Specifically, this includes the K Reactor. The simulator, which reflects the K-Reactor CCR physically and functionally, is treated as a separate facility within this program.

Systems, Structures, and Components

The systems, structures, and components that will be configuration items are commensurate with their relative importance (i.e. graded approach). As a minimum, they are those necessary for the safe, reliable, and efficient operation of the reactor plants. This includes those items that perform a safety related function, support the safety functions, control radioactive material, and provide efficient and reliable production of nuclear materials.

The criteria to be used to determine the systems, structures, and components to be configuration items will be based on the Design Authority safety classifications document¹¹. A list of system classifications is presented in the Design Authority Document, *Uniform Listing of Reactor Systems, Acronyms and Safety Classes*.¹² The structures and components to be configuration items will be determined during the implementation of the CM Program tasks based on the Design Authority references.

The level of detail of configuration and design information for a configuration item will vary depending on the function that the item performs and the standard operating, maintenance, or engineering practices associated with the item. The level of detail to be applied will be determined during the implementation of the tasks.

The priority for the implementation of the CM Program tasks will be based on the criteria referenced above.

Documents

The documents to be included as CI Descriptors are those that: 1) depict the configuration of the systems, structures, and components (e.g., P&IDs, electrical one-lines, connection drawings, instrument loop drawings), 2) define the design basis of the plant (e.g., Technical Baseline Documents (TBDs), Restart Test Identification Reports (RTIRs), Safety Analysis Report, Technical Specifications & calculations), 3) are used to operate, maintain, and test the plant (e.g., operation, maintenance, and test procedures), 4) control changes to the above documents.

Configuration item documents will be listed in the Configuration Controlled Documents List developed in the Change Control element. The level of verification of the accuracy of these documents will depend on how the document is used in support of the plant.

Information System Data

Information systems will be used for the collection, control, and dissemination of configuration and design data. The specific data fields that will contain configuration item data will be defined in the functional and detailed specification for the information system. As a result of the definition of configuration item data, a given information system may contain data that is required to be controlled as well as data that is not required to be controlled. For example, the Process Location Identifier (PLI) number for a component will be a configuration item, but the cost data for a component will not be a configuration item.

Administrative Process Procedures

Control and maintenance of configuration and design information for configuration items are accomplished through administrative process procedures that control the activities that can change a configuration item. These procedures must contain certain aspects to ensure configuration control is maintained.

The CM Program scope will include the design control, work control, material control, and document control processes to ensure that the governing procedures include the necessary aspects for configuration control.

3.3.2 Restart CM Initiatives

The restart initiatives (commonly referred to as Short Term Initiatives) are primarily focused on the design information and controls necessary to resolve audit findings and DOE concerns. These restart initiatives focus on:

- Providing operations and engineering with selected, important design information and procedures which have been validated as required by the reactor facility walkdowns and documentation reviews.
- Establishing the necessary interim and permanent design change controls to update this information as changes are made in the reactor facility, and ensure the changes have been properly controlled in the design change process.
- Upgrading document storage, processing and distribution to ensure this information can be conveniently updated and accessed in a timely manner.

The following identifies the restart initiatives which contribute to the enhancement of the RRD CM Program:

1.0) Baseline Configuration- The combined efforts of the Startup Test Program (SUTP) and the Technical Baseline Program (TBP) have made significant progress in the area of Baseline Configuration:

- Central Control Room (CCR) and Startup Test (SUT) drawings have been completed for 39 systems.
- Vendor Technical Manuals (VTMs) have been completed for 18 components.
- An Interim Safety Equipment List (ISEL) has been completed for all reactor safety systems. The final Safety Equipment List (SEL) has been compiled for two systems.

- A Reactor Engineering Database System (REDS) has been developed to store and manage system/component baseline information. (Also referenced in Program Element 6.0, Information Systems Integration)

Applicable Criteria are 1, 2, 3 & 6 (see Section 3.1.2)

2.0) Design Basis- Prior to restart the TBP and SUTP have recaptured certain design basis information and compiled it within two types of documents, Technical Baseline Documents (TBDs) and Restart Test Identification Reports (RTIRs). TBDs have been issued for six systems, and 34 RTIRs covering 45 systems have been issued.

Applicable Criteria are 1, 2, 3 & 6 (see Section 3.1.2)

3.0) Change Control- Several initiatives are in place to implement change control processes for RRD:

- A work control program has been developed and implemented.
- A modification and design control program has been established, and detailed design control procedures have been developed.
- A process to govern completion of plant modifications has been developed.
- Detailed design reviews have been performed for restart modification projects.

Applicable Criteria are 4 & 5 (see Section 3.1.2)

4.0) Document Control- The following restart initiatives have been focused on document control processes:

- A sitewide document control procedure has been developed.
- An enhanced process for the control and distribution of documents has been developed.
- An initial Controlled Documents List (CDL) has been established and issued. (This list establishes the types of documents that will be controlled.)
- Desktop guides have been developed for the conduct of document control activities.
- A comprehensive Document Control Register (DCR) has been developed and implemented. The DCR provides a database of all documents currently being controlled by the site Document Control organization as well as the current controlled revision and design change statuses.
- Satellite Document Control Stations (SDCSs) and field offices have been established in the reactor areas.
- Training on document control processes has been provided to RRD personnel.

Applicable Criteria are 1, 3, 5 & 6 (see Section 3.1.2)

5.0) Material Control- A pilot spare parts evaluation program was conducted to assess the spare parts procurement process relative to the requirements of NQA-1 and EPRI procurement initiatives.

In a short-term, spare parts for restart safety systems were subject to a validation program developed to ensure physical identification review and evaluation for traceability and shelf-life prior to installation. Additionally, RQA independently reviewed and approved procurement documents for Level 1 and 2 procurements.

RED is establishing a Materials Engineering Group to ensure appropriate technical and quality requirements are specified for safety related spare parts and materials.

Applicable Criteria are 1, 2 & 6 (see Section 3.1.2)

6.0) Information Systems Integration- The following efforts have been implemented with regard to information systems:

- The Work Management System (WMS) Database has been upgraded.
- A Reactor Engineering Database System (REDS) has been developed in connection with the TBP.
- Integration efforts were initiated to upload REDS data into WMS to eliminate discrepancies.
- Process Location Identifiers, unique component identification numbers, have been formulated and assigned for reactor system components.
- The Document Control Register (DCR) has been upgraded to include change control status on design documents.

Applicable Criteria are 1, 2, 5 & 6 (see Section 3.1.2)

7.0) Administrative Control- To provide administrative support and control for CM processes, the following activities are in progress or have been implemented:

- Guidelines for Reactor Engineering Design Authority activities have been established.
- A Design Review Board process has been established.
- Post startup-test configuration control is being implemented by the RED Engineering Technical Support Section to maintain the integrity of the plant configuration.
- The Administrative Procedures Steering Committee (APSC) was established to review and approve all administrative procedures developed within the Reactor Engineering Department for use at the Department or Division level. The APSC also evaluates external procedures that have significant impact on RED and RRD procedures to ensure process alignment.
- Numerous RRD and RED procedures were developed and/or enhanced to support various CM processes.

Applicable Criteria are 3, 5, 6 & 7 (see Section 3.1.2)

8.0) Plant Status Control- System lineup sheets along with a system status file were developed to provide system/component status information to the operating personnel. Temporary labels were placed on components in selected reactor systems. Efforts are underway to implement permanent component labels for these systems.

Applicable Criteria are 1, 2, 3 & 6 (see Section 3.1.2)

9.0) Codes and Standards- A "code of record" has been initiated for the K Reactor reflecting the codes and standards to which the reactor was built, where known.

Applicable Criteria are 1, 2, 3 & 6 (see Section 3.1.2)

3.3.3 Long-Term Integration

The Configuration Management Program Plan outlines the specific tasks to be performed in order to meet the objectives and to enhance the effectiveness of the program. The program assessments performed in Phase 2 identified the areas of enhancement. These areas can be divided into two types. The first type involves the development and/or enhancement of CM processes. A number of process and procedure changes identified in the evaluation can be implemented by the responsible department or group with the assistance of EP/CM. These improvements will be implemented as part of procedure revisions or instruction updates.

The second type involves the development and/or enhancement of "final products." The majority of these final products were begun or are in progress within the Technical Baseline Program (TBP) of the Reactor Engineering Department. These include the Technical Baseline Documents (TBDs), the Central Control Room (CCR) Drawings and the Interim Safety Equipment List (ISEL). These efforts are being consolidated within the RED Engineering Programs Section as part of the CM Program implementation. Likewise, the establishment of Codes and Standards Group has been initiated within the Engineering Programs Section to ensure its alignment with the CM Program.

The scope of the baseline configuration will be expanded to include all reactor systems. However, the scope of work within each task will be determined using a graded approach. The selection criteria will be based on the importance to safety, security, industrial and process requirements, and business needs.¹³ The focus for the "product" elements will be to equalize the generation of these products on a system basis. The advantages to this approach include:

- Consistency Of The Products For A System

Emphasis will be placed on developing all the CM products (e.g. Technical Baseline Documents, CCR drawings, Vendor Technical Manuals) for a system in parallel. This will reduce the potential for problems resulting from the "half-life" of the associated information. Consequently there is less likelihood of discrepancies among them.

- Product Usefulness

Development of CM products in parallel will significantly increase the impact they have on the CM processes and the end user. The availability of a complete set of information for a system will ensure that work activities are performed with

consistent information. This will increase the users confidence in the CM products and will result in increased use.

- **Quality Assurance By The Users**

As confidence in the CM products grows and the value of the CM products is fully appreciated, the users will develop a sense of "ownership" and provide feedback which will help maintain and enhance the products.

The enhancement of final products requires substantially more effort and warrants a carefully integrated effort to implement. The Integrated Action Plan (IAP) will define and integrate the activities among the program elements. The IAP will provide the following:

1. Task description & priority,
2. Scope of configuration items (where applicable)
3. Resource needs,
4. Responsibilities,
5. Schedule, and
6. Expected results

Expected results will be established for each enhancement activity in the Integrated Action Plan. Specific results will be measured against the program objectives. A formal reassessment will be performed in the program validation phase.

3.4 Program Validation

The fourth phase consists of the validation of program elements. This is primarily a verification process to assure the quality of the plant specific information and the adequacy of the enhanced processes. In order to achieve program objectives I & II, the validation phase ensures that technical baseline information is defined, documented and retrievable; and the plant accurately reflects the design and conforms to design and DOE requirements. Similarly, objectives III & IV are met when plant processes are enhanced to ensure that plant documents and databases are accurately updated; and changes are properly evaluated, approved and incorporated. Validation is an essential part of the configuration management program since it confirms the achievement of CM objectives.

A typical systematic review plan will include the following attributes:

- Scope of review
- Identification of system interfaces
- Organization & responsibilities
- Identification of relevant requirements,
(such as DOE Orders, Codes & Standards, Tech. Specs., etc.)
- Instructions for review
- Instructions for the disposition of issues
- Issues tracking
- Plans for corrective action
- Reconciliation of CM process interfaces

The following are typical techniques to implement Program Validation:

- System walkdowns to verify component types, configuration, and IDs
- Safety System Functional Inspections (SSFI)
(e.g. Self-SSFI on specific systems)
- Safety System Outage Modification Inspections (SSOMI)
- Review of categoric program elements
(e.g. change control records, maintenance records, etc. related to various systems and components.)
- Quality Assurance review, audits and surveillances
- Engineering Assurance audits and monitoring of technical input, output and processes.

As the enhancement activities progress, symptomatic problems will be identified for re-assessment. Relevant issues will be tracked and refinement to the enhancement activity will be implemented. A formal validation review method will be developed by the RED Engineering Assurance Section and will be coordinated with the Systematic Evaluation Program (SEP) for the SRS production reactors.

4.0 Program Implementation

4.1 Task Specifics & Responsibilities

In addition to the revised RRD CM Program Plan, the Integrated Action Plan will identify detailed tasks and activities to be performed for each program element. Each task will specifically address the problems identified in the assessment phase. Figure 4-1 shows a matrix of specific tasks for implementation. Detailed task descriptions and organizational responsibilities will be developed in the Integrated Action Plan. Various implementing organizations will include:

- RED, Reactor Engineering Department
- IRM, Information Resources Management (Document Control/Records Management)
- RTAP, Reactor Training & Procedures
- RQAA, Reactor Quality Assurance and Assessment
- OPS/Maint, Operations & Maintenance
- E&PD, Engineering & Projects Division

The RED/EP Section has direct responsibility for ensuring the nine elements of the CM Program are completed as delineated in the plan and for performing selected tasks. A "Lead" group will be assigned for the implementation of the task in order to produce a deliverable. "Direct Support" groups will provide additional resources to implement the tasks, as needed. "Contributing" group will provide support for input and review of products, as needed. Several external organizations such as DOE-SR and SRL will serve as contributing groups in various tasks.

Resource estimates are based on a dedicated RED/EP organization to implement these tasks with the support of matrixed personnel from those groups identified. Activities are implemented in logical steps to ensure process alignment. To this end, detailed process flow models will be developed to establish interfaces and priorities. Specific organizational interfaces will be established and documented for those process-related tasks such as Task 3-2, Design Change Process. The process flows will identify the sequence of implementation and provide a model to determine impacts due to process changes. Figure 4-2 shows a top level task relations process model for all the program elements.

FIGURE 4-2
REACTOR RESTART DIVISION
CONFIGURATION MANAGEMENT PROGRAM
ELEMENT TASK

TASK DEPENDENCY
DIAGRAM

4.2 Management and Organization

This section describes the management structure and the organizational responsibilities for the RRD CM Program.

4.2.1 SRS Site Configuration Management

The Savannah River Site CM Manager is responsible for defining site-wide configuration management policies and requirements. This includes development and maintenance of the SRS Configuration Management Plan¹, issuance of Company-level CM-related procedures, and coordination of CM activities among WSRC Divisions. The CM Manager also leads the activities of the SRS CM Coordination Group, an organization consisting of representatives from all SRS divisions. The purpose of the group is to share information on CM implementation activities and to discuss issues and divisional interfaces among the divisions.

4.2.2 RRD Configuration Management Organization

The RRD CM Program will be implemented under the management of Reactor Engineering Department (RED) who, as the Design Authority for the Reactor Restart Division, is responsible for ensuring that adequate and consistent CM processes exist for the entire division. RED also establishes and maintains the technical baselines for the plant systems. Overall program direction, scope, and budget is the responsibility of the RRD Vice-President.

The management of the program and implementation of the CM Program Plan is assigned to the RED Manager of Engineering Programs (RED/EP) by the Manager of the Reactor Engineering Department. The RED/EP Section has direct responsibility for ensuring the nine elements of the CM Program are completed as delineated in the plan and for performing selected tasks. Some tasks will be performed by other SRS departments and divisions that will have matrixed responsibility to the RED/EP Manager. Additional support to the CM Program Plan will be provided by other SRS organizations on an as-needed basis.

The CM Program organization will be structured to address the functional areas of the program plan as delineated in Figure 4-1. This organization will combine the RED/EP staff and a matrixed staff from other departments and divisions. The RED/EP staff will implement those tasks within the cognizance of RED Engineering Programs. The matrixed staff will implement their CM tasks under the direction of their respective functional organizations and the RED/EP Manager.

Within the Engineering Programs Section, the Manager of the Configuration Management Group (EP/CM) is assigned the responsibility to implement the RRD CM Program Plan on the task level. The involvement of the EP/CM Group Manager in the individual program tasks will be to ensure technical consistency and adequate interface between tasks. The specific relationship and involvement of the EP/CM Manager in the tasks being performed will vary based on the task and will be formalized via the individual task descriptions.

The functional organization chart (Figure 4-1) shows a preliminary breakdown of tasks. The RED/EP Section is dedicated to those tasks that are considered to be most important to the overall CM program (e.g. tasks that generate a CM product or require a

high degree of close interaction and integration with other tasks). Appropriate matrixed organizations are assigned those tasks that require a high degree of technical input and evaluation, or deal directly with establishing or enhancing a process outside RED.

With the RED/EP Section as a point of focus, the execution of the CM Program Plan will be performed in a coordinated and integrated manner. The centralized responsibility will help ensure that program objectives are met within the budget and schedules established. The RRD CM organization will provide:

- a degree of organizational hierarchy that maintains closely related activities under the control and coordination of a single manager;
- a unified line of authority, responsibility, and reportability for the tasks that are essential to meeting the CM objectives;
- a span of control that limits the direct responsibilities of an individual lead to a number of personnel that will ensure adequate supervision at each level;
- a structure that will ensure that problems and concerns are resolved at a level of management that is consistent with the nature of the problem.

The organizations responsible for implementation of particular tasks defined in this plan will be identified in the Integrated Action Plan. If support is required from other RRD departments or WSRC divisions, it is the responsibility of the RED/EP Manager to procure the assistance needed.

4.2.3 RED Responsibilities

RED/EP Section Manager

The RED/EP Section Manager is responsible for the overall program coordination and specific task supervision. Specific responsibilities include:

1. Oversight of the CM Program activities, budgets and schedule;
2. Direct supervision of CM tasks implemented within RED/EP;
3. Ensuring that CM objectives and requirements are communicated to the other RRD and WSRC organizations;
4. Ensuring that the necessary resources are made available for efficient implementation of the CM Program Plan;
5. Helping to resolve conflicts between various tasks and programs that support the CM Program that cannot be resolved by the EP/CM Manager.

EP/CM Group Manager

The EP/CM Group Manager is responsible for the coordination and implementation of the CM Program. Specific responsibilities include:

1. Developing overall administrative processes, procedures, and management structure for the implementation and control of the Configuration Management Program;
2. Developing the CM Program Integrated Action Plan which will:
 - a) translate the Configuration Management Program requirements and tasks into specific work breakdown structures (WBS);
 - b) optimize the scope of ongoing SRS projects to reduce resource needs and to minimize duplication of efforts;
 - c) integrate the detailed interfaces between tasks on the activity level;
 - d) establish detailed schedules and budgets based on the WBS;
3. Initiating program element assessments, as necessary, to measure CM processes against the program objectives;
4. Managing the efforts of the EP/CM Group in developing, implementing and tracking the Integrated Action Plan tasks to ensure that the tasks are properly coordinated and that effective communication is maintained;
5. Ensuring the performance and completion of necessary tasks are within established schedule and budget;
6. Reporting on the progress of program implementation.

4.2.4 RED/EP Organization Responsibilities

The CM Program will utilize a dedicated RED section combined with matrixed support organizations to complete the tasks included in this program plan. The RED/EP Section consists of group managers with additional staffing provided to implement the tasks identified in the CM Program Plan. The matrixed organizations will interface with the RED/EP section through the associated group manager. This will allow information to be coordinated at the working level, thereby enhancing its usefulness and helping to maintain a high degree of consistency and efficiency.

The matrixed organization will report to the RED/EP section via two levels of management interface:

Direct Matrix - where the supporting group for the assigned task reports directly to the RED/EP Manager. RED/EP will be responsible for task scope, budget, and the quality of the task deliverables.

Project Matrix - where the supporting group reports through their normal line management and performs the assigned task as a complementary effort to CM. RED/EP (via the EP/CM Manager) will be responsible for monitoring the task and coordinating their efforts with the rest of the CM Program.

RED/EP Group Managers

The CM Program tasks will be assigned to RED/EP Groups by the RED/EP Section Manager. The responsibilities of a RED/EP Group Manager are:

1. Assisting the EP/CM Manager in developing the detailed scope, methodology, and schedule for the element(s) under his/her responsibility;
2. Ensuring that implemented tasks within a specific program element(s) meet the objectives of the element(s);
3. Ensuring that tasks are performed according to schedule and budget;
4. Reporting to the EP/CM Manager on the progress of the tasks;
5. Coordinating the interfaces between his/her respective tasks and the other CM Program Plan Elements, and with the matrixed support organizations to ensure that they are properly integrated with the overall CM program.

Direct Matrix Staff

Direct Matrixed Staff are Technical Lead Engineers within RED/EP responsible for performing specific task(s) of a CM Program Plan Element. Their specific responsibilities are:

1. Assisting the RED/EP Group Manager in developing the detailed scope, methodology, and schedule for the task(s) under their responsibility;
2. Performing the specific activities of the assigned task(s);
3. Ensuring that the specific task(s) is performed according to schedule and budget;
4. Reporting to the respective RED/EP Group Manager on the progress of the task(s).

Project Matrixed Staff

Project Matrixed Staff are Technical Lead Engineers outside of RED/EP responsible for performing specific task(s) of a CM Program Plan Element. Their specific responsibilities are:

1. Assisting the RED/EP Group Manager in developing the detailed scope, methodology, and schedule for the task(s) under their responsibility;
2. Performing the specific activities of the assigned task(s);
3. Ensuring that the specific task(s) is performed according to schedule and budget;
4. Reporting to their respective management and the EP/CM Manager on the progress of the task(s).

5.0 References

- 1 WSRC-RP-90-257, SRS Configuration Management Plan, Rev. 0, dated 3/1/90
- 2 RRD-CFM-910070, RRD Configuration Management Program Plan, Rev. 0, dated 3/6/91
- 3 DOE /DP 0084T, Safety Evaluation Report Restart of K-Reactor, dated April 1991
- 4 WSRC-1-01, MP 5.7, Configuration Management,
- 5 U. S. DOE Order 4700.1, Project Management System,
- 6 RP-OMM-89-020, RRD Configuration Management Course of Action Report, dated 9/1/89
- 7 WSRC-IM-91-96, SRS Configuration Management Glossary, dated 9/19/91
- 8 DOC# 900334, Reactor Maintenance Self-Assessment Report, January 1990
- 9 VS-93, Vertical Slice Final Report, dated 5/20/91
- 10 Westinghouse Independent Safety Review of Savannah River Production Reactors, dated 4/1/89
- 11 RP 5.1307, Nuclear Safety Classification Criteria For Systems, Structures and Equipment, to be issued.
- 12 Technical Report WSRC-TR-90-42-133, Uniform Listing of Reactor Systems, Acronyms and Safety Classes, dated 12/13/90
- 13 WSRC 1E-2.01 Draft, Configuration Item (CI) Selection and Grading Criteria, to be issued

CM PROGRAM--K RX IMPLEMENTATION SCHEDULE DETAILED SCHEDULE of ACTIVITIES

SAVANNAH RIVER SITE

WDCR /DDN /DR

Date: 18SEP91

PAGE: 1

Legend

▲ MILESTONE
■ =Planned

CM PROGRAM-K RX IMPLEMENTATION SCHEDULE DETAILED SCHEDULE of ACTIVITIES

Activity	Description	Start	Finish	Dur	01 OCT 91	01 JAN 92	01 APR 92	01 JUL 92	01 OCT 92	01 JAN 93	01 APR 93	01 JUL 93	01 OCT 93	01 JAN 94	01 APR 94	01 JUL 94	01 OCT 94	01 JAN 95
760	CM TRAINING	020CT91	23FEB95	865														
770	04 AUDITS	03FEB92	01FEB95	766														
780	CM PROGRAM MANAGEMENT	020CT91	23FEB95	865														
810	DEVELOP CODE OF RECORD	230CT91	07MAY94	600														
821	REVIEW DUE ORDERS ON CDSSSTUS	020CT91	14SEP92	240														
822	DEVELOP BRO STANDARDS (100 TOT)	26MAY92	11FEB94	480														
830	IDENTIFY BACKLOG CRITERIA	19JUN92	01JUN93	240														
899	PROGRAM COMPLETE	24FEB95	23FEB95	0														

END

**DATE
FILMED**

8 / 26 / 92