An Experimental Study of NO_x Recycle in the NOXSO Flue Gas Cleanup Process

DOE/PC/91337--T2

DE92 018395

Quarterly Technical Progress Reports

Submitted to
U.S. Department of Energy
Pittsburgh Energy Technology Center
AC 22-91PC 91337

January 1 through March 31, 1992

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Prepared by

NOXSO
CORPORATION
P.O. Box 469
Library, PA 15129

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

TABLE OF CONTENTS

1.0	Executive Summary
2.0	Introduction
3.0	Project Description
4.0	Project Status
5.0	Planned Activities
6.0	Summary

Prepared by

NOXSO

CORPORATION

P.O. Box 469

Library, PA 15129

1.0 EXECUTIVE SUMMARY

DRAFT

In the previous reporting period (from October to December), efforts focused on site preparation, shakedown testing and baseline testing. The analysis of the coal, which is representative of coal burned at the Niles Plant, has been completed. The NO injection system and sampling system have been installed. Baseline stack NO_x levels have been established from the baseline tests. A shakedown of the facility for the NO injection testing has been performed. Varied amounts of NO were injected into the furnace from the primary air stream and the secondary air stream. The test results indicated that large amounts of injected NO were destroyed in the furnace, especially when NO was injected at the primary air stream. However, there were some problems in the measurement of NO_x concentration and injected NO flow rate. The major problems were:

1. There was a difference between the measurements of NO and NO_x concentrations for pure NO injection into the combustion air. The higher the injected NO flow rate, the larger the difference. This implied that part of NO was converted into NO₂, and the conversion could occur in both combustion air ducts and sample lines.
2. The NO_x mass balance could not be closed. This was probably because the water removed in the ice bath of the analyzer sample system scrubbed some amount of NO_x.

The solutions to the problems have been proposed to modify the sampling and the measurement system for the accuracy of the data.

2.0 INTRODUCTION

NO_x recycle is one part of the NOXSO process. In this process, 90% of the acid pollutants (NO_x and SO_2) can be removed simultaneously by adsorption on the surface of a sorbent material. The sorbent is subsequently regenerated by heating and contacting the hot sorbent with a reducing gas followed by steam. The NO_x is removed in the heating process, and the SO_2 is removed by the chemical reaction of the reducing gas and steam. The NO_x stream produced is returned to the combustion process with combustion air, which is called the NO_x recycle. The NO_x is reduced in the flame to N_2 , H_2O , and CO_2 .

The NO_x recycle concept operates by means of two different mechanisms. The first relies on the thermodynamic and kinetic conditions in the flame. When NO_x is fed to the coal combustor at concentrations greater than the equilibrium concentration, a portion of the recycled NO_x is reduced to N_2 and O_2 to approach the equilibrium concentrations (from high to equilibrium value). The kinetic rate of NO formation also decreases due to the high initial recycled NO concentration. The second mechanism relies on the reducing nature of the combustor flame. Free radicals generated at flame temperatures react with the NO_x species reducing them to N_2 and H_2O or CO_2 . Therefore, reaction equilibrium and the reducing atmosphere in the flame both serve to destroy recycled NO_x species.

NO_x recycle will be implemented at the full-scale commercial demonstration plant at Niles. The concept of NO_x recycle has been tested previously at DOE-Pittsburgh Energy Technology Center (PETC) using a 500 lb/hr coal combustor used for the 3/4 MW tests and also using a tunnel furnace capable of being fired with a variety of fuels including gas, fuel oil, coal, and coal-water mixtures. The results were very promising and demonstrated the destruction of NO_x compounds when fed to the combustion system. The data also indicate that the extent of NO_x reduction is determined by the location of the NO_x injection and the combustor design.

This current project is pilot-scale testing of NO_x recycle. The objectives are to provide further fundamental understanding of the NO_x destruction mechanisms and to help with the

implementation of NO_x recycle at the Niles station. A Babcock & Wilcox 6 million Btu/hr Small Boiler Simulator (SBS) (see Figures 1 and 2) was chosen to perform the tests. The SBS is the same type of cyclone furnace as that at Niles and simulates a large cyclone unit very well (see Table 1).

The project involves conducting a series of tests which include injecting NO, NO₂, N₂O, and a simulated NO_x recycle stream respectively. The work performed during this reporting period focused on solving the problems encountered during shakedown tests, and modifying the gas injection and measurement system to ensure the accuracy of the data. After the modification of the system, acceptable NO_x mass balances (between 92% to 95%) were achieved.

The test data demonstrated quite consistent NO_x reduction efficiencies, which is similar to the previous test results on the pulverized coal combustor at DOE-PETC. An average NO_x destruction efficiency of about 70% was achieved for NO injection into the primary air duct independent of injected NO flow rate and exit O₂ concentration. About 58%, 50%, and 46% average destruction efficiencies were obtained for NO injection into the secondary air duct corresponding to exit O₂ concentrations of 2%, 3%, and 4% respectively.

3.0 PROJECT DESCRIPTION

In order to provide further fundamental understanding and practical information for NO_x recycle implementation at the Niles station, the following four tasks have been defined to be performed in this project:

Task 1: Project management and reporting. This includes overall management of the project, preparation of monthly reports, preparation of draft and final project work plan, supervision of tests performed by B&W, and final report preparation.

Task 2: Experimental Testing. This has been subcontracted to B&W. It involves site preparation and testing. A schematic diagram of the NO injection and sampling system is shown in Figure 3. Pure NO gas from the gas cylinder goes through a rotameter and is injected into

the combustion air duct a short distance from the furnace. The sampling probes for the inlet NO and NO_x measurement are installed downstream of the injection location and before the cyclone. Both inlet and stack NO and NO_x concentrations are measured by continuous NO/NO_x analyzers. The tests consist of shakedown, baseline, simulated NO recycle, simulated NO₂/N₂O recycle, and novel concept tests. The NO, NO₂ and N₂O will be injected separately to investigate their effects on the NO_x destruction in the furnace. The injection of a simulated NO_x recycle stream will also be tested. The injection location will be in the primary air alone, secondary air alone, and both primary air and secondary air together. The parameters varied during the tests are furnace load, outlet oxygen concentration, and the amount of injected gases which are multiples of the baseline NO_x production levels.

Task 3: Data Analysis. The collected data will be analyzed. Data will be compiled into tables and graphs. The test data will be compared with previous NO_x recycle test results using pulverized coal combustor (performed at PETC) and recommendations for burner operation and NO_x recycle will be prepared.

Task 4: Comparison of B&W's pilot scale boiler to Ohio Edison's commercial boiler at Niles, Ohio. The end result of this task will be a comparison of the two units and suggested conditions for the NO_x recycle tests.

4.0 PROJECT STATUS

Experimental Testing

Management and Reporting: B&W has prepared a revised cost estimate for the completion of the experimental test program. NOXSO is writing a proposal which includes an extended work scope and a revised cost estimation.

A safety meeting for B&W personnel was held to discuss the hazards involved with the use of nitrogen dioxide. The design of the NO₂ injection system was thoroughly checked to

make sure that it meets all safety requirements. Personnel that are in charge of containing any spills or leak of NO and NO₂ were trained on the procedures that should be followed and the equipment that is required to be worn.

A meeting was held between NOXSO, B&W, and W.R. Grace at the Alliance Research Center on March 27, 1992. An overview of the project was presented by NOXSO Corporation and the introduction of the facility was given by B&W. A tour of the facility was conducted after discussions.

Site Preparation: The NO₂ injection system was designed by NOXSO and modified by B&W to meet all safety and piping regulations. Set up of the system was concluded and was approved by B&W's Quality Assurance section so that testing could begin. The new nitric oxide system was designed and installed according to the safety and piping regulations.

Based on problems encountered during the shakedown tests, the following work was done to ensure the accuracy of the data. A new rotameter was installed for accurate measurement of the injected NO flow rates. A TECO NO/NO_x analyzer with heated capillaries was installed to take measurements at the stack. This analyzer was connected to the data acquisition system for continuous on-line monitoring. For the measurement of inlet NO and NO_x concentrations, a heated sample line was installed and the ice bath was removed from the sample system to avoid possible conversion of NO into NO₂ in the sample line. The converter efficiency of all the analyzers used for testing was checked. The different ranges for each analyzer were tested. The converter efficiency for all the cases was above 96%.

Testing: After modifying the injection and the measurement systems, in order to evaluate the accuracy of the measurements, a series of tests were conducted to check mass balance. The NO gas was injected into the combustion air ducts without combustion occurring. The NO and NO_x concentrations were measured at the stack and compared with the measurement from the rotameter. Since the mass balance was closed to greater than 92%, a series of NO injection tests with combustion were conducted. In the completed tests, the furnace load was 6 MBTU/HR

(full load), the exit oxygen concentrations were 2%, 3% and 4% respectively, and the amounts of NO injected were about 0.25, 0.5, 1.0 and 1.5 times baseline stack NO_x (lb/hr). The test procedures for each NO injection run were:

- 1). Measure the baseline stack NO_x before injection of NO.
- 2). Inject NO and take data at the steady state condition.
- 3). Stop injection and measure the baseline condition again before next injection.

Preliminary data analysis of the completed tests is given in the following section.

Data Analysis

The preliminary data analysis has been done for the mass balance tests and NO injection tests as mentioned above. Table 2 shows the preliminary data for the mass balance tests. In Table 2, the mass balance (MB %) is defined as follows:

$$MB = (1 - (\frac{NO_i - NO_{xs}}{NO_i})) * 100 \quad (1)$$

where, NO_i is the injected NO (lb/hr) measured from the rotameter, NO_{xs} is the stack NO_x (lb/hr) measured by the continuous NO/NO_x analyzer. In general, the NO_x measured at the stack is very close to the NO_x measured from the rotameter in the injection line. Most of the mass balance data are between 92% to 95%, which is considered to be acceptable.

The preliminary test data for the NO injection with combustion are shown in Figures 4, 5, 6, and 7. Figures 4 and 5 display the NO_x reduction efficiency (eff.) vs. normalized NO feed rate (F*) at different exit O₂ concentrations for pure NO injection into the primary and secondary air ducts respectively. The NO_x reduction efficiency is defined as follows:

$$eff. = \frac{NO_i + NO_{xb} - NO_{xs}}{NO_i} * 100 \quad (2)$$

where, NO_i is the feed rate of pure NO gas (lb/hr), NO_{xb} is the baseline stack NO_x without NO injection (lb/hr), and NO_{xs} is the stack NO_x with NO injection (lb/hr). F^* is the normalized NO feed rate which is given by:

$$F^* = \frac{NO_i}{NO_{xb}} \quad (3)$$

Figures 6 and 7 show the normalized NO_x production rate (R^*) vs. normalized NO_x feed rate (F^*). The normalized NO_x production rate is calculated according to the following equation:

$$R^* = \frac{R}{R_0} = \frac{NO_{xs} - NO_i}{NO_{xb}}$$

where, R is the net NO_x production rate which equals the NO_x flow rate at the exit of the combustor minus the NO feed rate into the combustor; R_0 is the NO_x production rate at $NO_i=0$, i.e. the baseline NO_x flow rate at the exit of the combustor. These figures also indicate the NO_x reduction efficiency if the data can be represented by the straight line described by the equation $R^*=1-aF^*$. It can be derived that the parameter "a" is the slope of the line and represents the NO_x reduction efficiency.

In the present tests performed at B&W, when the pure NO is injected into the primary air duct of the cyclone furnace (see Figures 4 and 6), the test data show quite consistent NO_x reduction efficiencies. The average NO_x reduction efficiency is about 70%, which is not affected by the exit O_2 concentrations. This is quite similar to the test results on the pulverized coal combustor at DOE/PETC, as shown in Figure 8, which shows a constant NO_x reduction efficiency of 65% for the pure NO injection into the primary air duct.

When pure NO is injected into the secondary air duct of the cyclone furnace (see Figures 5 and 7), the NO_x reduction efficiency is lower than that of the NO injection into the primary air duct and slightly varies with the exit O₂ concentrations. The average reduction efficiencies are about 58%, 50% and 46% corresponding to the exit O₂ concentrations of 2%, 3%, and 4% respectively. The lower reduction efficiency and the slight effect of the exit O₂ concentrations for the secondary air duct injection are attributed to the less reducing atmosphere in the secondary air region. It should be noted that the test data shown in Figures 4-7 are preliminary. Further data reduction is needed for the final evaluation.

5.0 PLANNED ACTIVITIES

Testing will continue to complete the rest of the NO injection series, NO₂ injection series, N₂O injection series, addition of methane injection and simulated mixture testing defined in the work scope. Data reduction and analysis will be performed.

6.0 SUMMARY

During the current reporting period (from January to March), efforts focused on solving the problems encountered during shakedown tests, and modifying the gas injection and measurement system to ensure the accuracy of the data. After the system was modified, the mass balance between the NO amount injected into the combustion air duct and the NO_x measured at the stack was checked without combustion. Most of the tests showed a very good NO_x mass balance (between 92% to 95%).

The tests of NO injection with combustion have demonstrated very promising results. The test data showed quite consistent NO_x reduction efficiencies, which is similar to the previous test results on the pulverized coal combustor at DOE-PETC. An average of about 70% NO_x destruction efficiency was achieved for the NO injection into the primary air duct independent of injected NO flowrates and exit O₂ concentrations. About 58%, 50%, and 46% average destruction efficiencies were obtained for the NO injection into the secondary air duct

corresponding to the exit O₂ concentrations of 2%, 3%, and 4% respectively. This data analysis is only preliminary and further data reduction is needed for the final evaluation.

Table 1. Comparison of Baseline Conditions Between the SBS Facility and Commercial Units		
	SBS	Typical Cyclone-Fired Boilers
Cyclone Temperature	> 3000°F	> 3000°F
Resident Time	1.4 sec. at full load	0.7-2 sec.
Furnace Exit Gas Temperature	2265°F	2200°-2350°F
NO _x Level	900-1200 PPM	600-1400 PPM
Ash Retention	80-85%	60-80%
Unburned Carbon	< 1% in Ash	1-20%
Ash Particle Size (MMD; Bahco)	6-8 microns	6-11 microns

Figure 1. Small Boiler Simulator (SBS) Schematic

Figure 2. Cyclone Furnace

Figure 3. Schematic of NO Injection and Sampling System

PRELIMINARY DATA OF NO_x RECYCLE ON B&W'S CYCLONE FURNACE (Pure NO Injection into the Primary Air Duct)

Figure 4

EXPERIMENTAL DATA OF NO_x RECYCLE ON B&W'S CYCLONE FURNACE (Pure NO Injection into the Secondary Air Duct)

Figure 5

PRELIMINARY DATA OF NO_x RECYCLE ON B&W'S CYCLONE FURNACE (Pure NO Injection into the Primary Air Duct)

Figure 6

PRELIMINARY DATA OF NOx RECYCLE ON B&W'S CYCLONE FURNACE (Pure NO Injection into the Secondary Air Duct)

Figure 7

EXPERIMENTAL DATA OF NOx RECYCLE ON PETC'S PC COMBUSTOR (Pure NO Injection into the Primary Air Pipe)

Figure 8

END

**DATE
FILMED**

9/16/92