DOE/MC/25146--3085

DE92 001271

PrimeEnergy/DOE/GRI Slant Well

Final Report

**C.E. Drimal
G. Muncey
R. Carden**

Work Performed Under Contract No.: DE-FC21-88MC25146

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
PrimeEnergy Corporation
One Landmark Square
Stamford, Connecticut 06891**

December 1991

PrimeEnergy/DOE/GRI Slant Well

Final Report

**C.E. Drimal
G. Muncey
R. Carden**

Work Performed Under Contract No.: DE-FC21-88MC25146

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
PrimeEnergy Corporation
One Landmark Square
Stamford, Connecticut 06891**

December 1991

3. Angle-Build Section	11
4. Slant Section.....	12
5. Logging.....	14
III. Completion and Stimulation.....	14
IV. Reservoir Properties	15
V. Production.....	17
VI. Project Cost	19
VII. Project Economics	19
VIII. Summary and Conclusions	26
IX. Appendices	
A. Daily Drilling Reports	28
B. Casing Tallies	51
C. Drill Pipe Tallies.....	55
D. Motor Performance and Bottom Hole Assemblies	59
E. Bottom Hole Assembly Data.....	63
F. Build and Walk Rate Data	67
G. Hole Cleaning.....	69
H. Drilling Mud Reports (Foam Data).....	72
I. Pressure Build-up Analysis.....	78

EXECUTIVE SUMMARY

This report presents final results of the high-angle Devonian Shale development well drilled under DOE contract number DE-FC21-88MC25146. The well was drilled in Roane County, West Virginia on the foreland flank of the Chestnut Ridge Anticline; a structure closely associated with a fairway of locally significant Devonian Shale gas production. The target of the well was a tabular, southeast-dipping, fractured zone near the top of the Lower Huron Member of the Devonian-age Ohio Shale.

The well was conventionally drilled to a kick-off point of 2,150'. Positive displacement motors were then used to build inclination, at an average rate of 9 degrees per 100', to an inclination of 67 degrees at a true vertical depth of 2,954'. Conventional rotary assemblies were then used to drill the slant section of the well across a 1,500' target section to a true vertical depth of 3,571'. Inclination in the slant section varied from 67 to 72 degrees. Total measured depth of the borehole was 4,833'.

Hydraulic fracturing treatments were performed in four separate stages. Stimulation intervals ranged in length from 6' to 570'. Each interval was treated with straight nitrogen in volumes ranging from 1,303,000 to 1,800,000 standard cubic feet after breakdown with 400 to 500 gallons of 7.5% acid.

Estimates of open flow from all zones summed to approximately 1,400,000 cubic feet per day; an apparent three-fold improvement over the average vertical well in the area. Post-stimulation flow rates summed to about 195,000 cubic feet per day against simulated line pressure, but were not sustainable at that level under producing conditions. Unexpected oil production of approximately 1 barrel per day has had a substantial detrimental effect on gas deliverability. Operational aspects of gas production have been complicated, and gas deliverability reduced, by the periodic buildup of hydrostatic pressure due to accumulation of oil in the wellbore. Moreover, gas flow into the wellbore may be significantly curtailed due to relative permeability of the reservoir rock to oil and gas.

Cumulative production for the period September 1990 through August 1991 totalled 5,750,000 cubic feet of gas and 493 barrels of oil. In contrast, production of near-offset vertical wells ranged from 5,200,000 to 53,500,000 cubic feet of gas, and no oil, during an equivalent 12-month period.

Lower-than-expected gas deliverability suggests that neither high-angle drilling nor subsequent hydraulic fracturing treatments were successful in connecting the borehole with the natural fracture system(s) encountered in near-offset high-deliverability vertical wells. This, combined with a borehole which met virtually all of its design criteria, suggests that the vertical-well-based reservoir model failed to adequately predict fracture distribution within the reservoir. Furthermore, the apparent absence of fractures predicted by the vertical-well-based reservoir model suggests that Devonian Shale fracture systems, at least in the study area, may not exhibit sufficient continuity along strike and/or depth for directional drilling to produce an economic benefit.

INTRODUCTION

This report presents final results of the Sterling Boggs 1240 slant well. The Boggs 1240 was drilled under DOE Cooperative agreement number DE-FC21-88MC25146 as a part of an ongoing DOE investigation of directional drilling in the development of marginal gas resources. The United States Department of Energy and PrimeEnergy Corporation (successor to Sterling Drilling and Production Company) developed a cost sharing contract under which the high-angle well would be drilled, logged, tested, and stimulated. Early on in the project the Gas Research Institute (GRI) joined as a research participant to conduct supporting research in well siting, well logging, testing and stimulation, and PrimeEnergy was joined by Columbia Natural Resources, McCormick Resources, and the Pennzoil Company as working interest partners.

Objectives of the project were (1) to test the potential for improved recovery efficiency in a fractured Devonian Shale reservoir from a directionally drilled well, (2) to perform detailed tests of reservoir properties and completion methods, and (3) to provide technology to industry which may ultimately improve the economics of drilling in the Devonian Shale and thereby stimulate development of its resources.

This report updates information presented in earlier papers (Muncey, 1989, Muncey and Carden, 1989, and Muncey, 1990) regarding the background, plans for, and results of the slant well project. Like the earlier papers, this report is influenced by the investigations of Lowery et al (1988) and Sweeney (1986) and by communications with many government and private-sector scientists and engineers.

The report is divided into eight sections. In Part I the geologic setting and site selection are discussed. Drilling plans, a detailed discussion of drilling operations and logging are presented in Part II. Completion and stimulation are discussed in Part III and reservoir properties are discussed in part IV. The well's production history and projected performance are topics of Part V. Project cost and economics are presented in Parts VI and VII respectively. Finally, project findings are summarized and conclusions are presented in Part VIII.

I. SITE SELECTION

The primary objective of the project was to test the potential for improved gas recovery from a fractured Devonian Shale reservoir from a directionally drilled well. Historically, Devonian Shale wells have been drilled vertically. Within a given population of Devonian Shale wells, drilling results have typically shown large variances in reserves with low reserves per borehole on average. Moreover, because of the low average reserves per borehole, drilling in the Devonian Shale has tended to show poor economic results. Over time operators have recognized that wells with relatively high reserves intersected with one or more naturally occurring fractures. It was also recognized that relatively few wells connected with these fracture systems because they tended to have a largely vertical orientation, making them a difficult target for conventional vertical drilling.

To test the potential for improved recovery with directional drilling, the plan was to select a fracture-prone area using available geological data, map a high-production-potential fracture system utilizing data from near-offset vertical wells; then drill across the strike of the mapped fracture system. It was hypothesized that (1) by drilling across the strike of the mapped fracture system, the probability of intersecting multiple high-potential fractures would be increased substantially, and (2) that multiple fracture systems encountered by one borehole could then be stimulated with hydraulic fracturing techniques. It was further hypothesized that the combined effect of conditions (1) and (2) would result in sufficiently improved recovery efficiency to make such drilling economically feasible. This concept is illustrated schematically in Figure 1. Moreover, it would provide the opportunity to conduct additional research on reservoir properties and completion methods. It would also provide a case study for operators on the application of directional drilling technology in the Appalachian Basin.

Accordingly, primary site selection criteria were: (1) that the selected location be in an area with known fracture-controlled Devonian Shale gas production, (2) where fractures were intersected by vertical wells, that production be of sufficient quality to make a commercial vertical well, (3) that there be sufficient well control to substantially mitigate exploration ("dry-hole") risk, and (4) that there be sufficient geological control to define a drilling target which offered a high probability of intersecting with production-controlling fractures.

A project area located in the Geary district of southeastern Roane County, West Virginia was selected. The well location and surface expressions of local structural features are presented in Figure 2. The project area lies within the Alleghany Plateau structural province. Structural style of the area is dominated by the intersection of two regional structural elements; an Alleghanian detachment, defined by the north to northwest-striking Burning Springs and Mann Mountain thrust sheets, and a northeast-striking system of relatively low-amplitude folds which overlies the southern boundary of the Rome Trough (Lowery et al, 1988). Additional structural complexity arises from a jump in stratigraphic position of the basal Alleghanian detachment from the Silurian Salina Salt level at the Burning Springs anticline to the Devonian Marcellus (?) Formation or perhaps to a sub-Salina Salt position beneath the Mann Mountain Anticline (T.K. Reeves, personal communication).

The well was drilled on the foreland flank of the Chestnut Ridge Anticline, approximately at the intersection of the Alleghanian front and the Rome Trough trends; a location thought to offer good opportunity for locally enhanced fracturing. In order to minimize exploration-type risk, the wellsite was located in an area with good well control within a narrow, relatively high-production-potential fairway. The presence of the narrow high-production fairway suggests the influence of vertical or sub-vertical fractures on the reservoir. Evidence corroborating the existence of such fractures is seen in well logs from the offsetting vertical wells (Lowery et al, 1988).

The high-production fairway is illustrated schematically in Figure 3 which shows the surface location and approximate azimuth of the Boggs 1240 wellbore with 12-month cumulative gas production as mapped from offsetting vertical wells (i.e., as mapped before drilling the Boggs 1240). Contoured values are in millions of cubic feet (MMCF). Dashed lines represent traces of faults, on the top of the Lower Huron, interpreted from repeat sections observed in offset wells (Lowery et al, 1988).

Figure 1. Multiple Hydraulic Fracturing Potential for a Deviated Well

Figure 2. Regional Tectonic Map (modified after Lowery et al, 1988)

Figure 3. Cumulative 12-Month Production (MMCF) and Fault Traces on the Lower Huron (after Lowery et al, 1988)

First year cumulative production in the area ranges from a high in excess of 157 MMCF to lows of less than 3 MMCF. First year cumulative production is highly variable within the fairway, but a strong systematic correlation with the structural fabric can be observed. It is apparent that the northeast component of the local structural fabric is the dominant influence on the reservoir, and hence that the northeast-trending fractures are of primary importance in the reservoir system. However, it is also apparent that some of the better wells may be associated with a northwest structural trend that has been correlated with Alleghanian shear faulting (Lowery et al, 1988).

No drilling locations were available with proximity to prospective northwest-trending structures. Therefore, a location was selected within one of the stronger production anomalies associated with the northeast trend. Data from offsetting vertical wells was used to map a tabular, southeast-dipping, fractured zone near the top of the Lower Huron Member of the Devonian Shale. A wellbore trajectory was then designed which was to maximize potential for borehole intersection with the production-controlling fracture system(s).

II. DRILLING OPERATIONS

1. SUMMARY

Figure 4 presents a schematic of the project-well design, the target zone as envisioned from offset well data, and the actual wellbore as drilled. On the vertical axis is true vertical depth - beginning at 2,000' subsurface. On the horizontal axis is horizontal departure. Stratigraphically, the kick-off point (KOP) is just above the top of the Upper Devonian Undivided at about 2,100' subsurface. The target zone is located within the lower few hundred feet of the Upper Devonian Undivided and the upper 100' of the Lower Huron member of the Devonian Shale. Figure 5 presents the planned and actual wellbore trajectories in planview.

Well design targets were (1) to be at 68° inclination by 2,950' true vertical depth (TVD), plus or minus 50', (2) to attain a lateral departure of 600' plus or minus 50', by 2,950' TVD with a target angle-build rate of 8.6° per 100' using a double-bend motor assembly and steering tool, and (3) to drill across the target zone building angle at about 0.5° per 100' using a rotary assembly. The total planned measured depth was to be 5,160' (3,426' TVD).

Drilling operations were conducted at the site between July 10, 1989 and August 1, 1989. The vertical portion of the well to the kickoff point took one day longer than anticipated. The build section required seven days to drill and was the same as the planned time. An additional two days were needed to drill the slant section because of a motor correction made at 3,785' as the borehole had begun to walk to the left (east), getting too close to the adjacent lease and threatening the prospect of too little lateral departure. The wellbore length was 327' shorter than the planned wellbore (5,160' planned vs. 4,833' actual). Total days on location were 23 compared to the anticipated time of 20 days. Planned versus actual drilling days were as close as can reasonably be estimated for a well of this nature. Figure 6 is a plot of depth versus days for the actual and planned drilling programs.

Daily drilling reports can be found in Appendix A.

VERTICAL VIEW

BOGGS #1240 AZIMUTH = 128.88

Figure 4. Drilling Plan vs. Outcome - Vertical View

PLAN VIEW

BOGGS #1240

Figure 5. Drilling Plan vs. Outcome - Planview

DEPTH VS. DAYS

BOGGS #1240

Figure 6. Drilling Plan vs. Outcome - Depth vs. Days

2. VERTICAL HOLE TO 2,150 FEET

The vertical portion of the well to the KOP was drilled on a footage basis by Exeter Drilling. The well was spud at 7:45 pm on July 10, 1989. A 17 1/2" hole was drilled to 394' KB. Fresh water was encountered at 75' KB.

Nine joints of 13 3/8", 54.5 #/ft, ST&C casing was run and set at 381.75' KB (371.85' GL) to isolate fresh water zones as required by the State of West Virginia. The casing was cemented to the surface as follows:

Twenty barrels water with 6 ppb gel and 2.5 ppb celloflake, 10 barrels fresh water, 260 sacks Class "A" cement containing 2% calcium chloride and 1/8 pps celloflake. The cement was mixed at 15.6 ppg with a yield of 1.18 cubic feet per sack. The cement was displaced with 59.5 barrels of water and the plug was bumped with 480 psi.

The 12 1/4" intermediate hole was drilled to 2,010' using three bits. Water was encountered and the hole was soaped after the first bit run at 1,359'.

The intermediate casing was run and set at 1,988.90' KB below the Big Injun. The intermediate casing was 9 5/8", 36#/ft, J-55, ST&C. The casing was cemented as follows:

Five barrels water, 20 barrels water with 6 ppb gel, 11 barrels water, 384 sacks 50/50 poz containing 2% calcium chloride and 1/8 pps celloflake followed by 100 sacks Class "A" cement containing 2% calcium chloride and 1/8 pps celloflake. The 50/50 poz cement was mixed at 14.2 ppg with a yield of 1.26 cubic feet per sack, and the Class "A" cement was mixed at 15.6 ppg with a yield of 1.18 cubic feet per sack. The cement was displaced with 154 barrels of fresh water and the plug was bumped with 850 psi. Had good returns while cementing.

After waiting on cement twelve hours, the 13 3/8" casing was cut off and welded to the 9 5/8" for support. The BOP's were nipped-up and the casing drilled out with an 8 3/4" bit to the kickoff point of 2,150 feet.

3. ANGLE-BUILD SECTION

At a measured depth of 2,150', a directional survey was run prior to kicking the well off. The survey was 1°, N60°E at a measured depth of 2,097'. The drilling assembly was pulled and the Eastman 8.6°/100' motor system was run to start building inclination. The motor was oriented using the Eastman DOT tool and a side entry sub.

The first motor run was terminated at 2,362' because of the slow penetration rate. The penetration rate would have varied from 30' to about 3' per hour. The motor was drilling less than 3' per hour when it was pulled. Inspection of the bit and motor indicated that there was no problem with either. The slow penetration rates were due to changes in lithology from shale to the slower drilling siltstones.

The Eastman Mach I motor was designed to build inclination at $8.6^{\circ}/100'$. The actual build rate was $10.5^{\circ}/100'$ which was more than the required build rate. The Baker 2° bent housing motor was run to reduce the build rate to the planned rate of $8.6^{\circ}/100'$. The Baker motor actually built inclination at a rate of $9.5^{\circ}/100'$.

The penetration rate for the Baker motor was comparable to the Eastman motor ($9.8'$ /hr and $10.6'$ /hr respectively). Because of the low penetration rates and the fact that the inclination was ahead of schedule, the tangent section was started early. Siltstone stringers were causing the low penetration rate. After the tangent section, very little siltstone stringers would be left and motor penetration rates were expected to be much higher.

The tangent section was started at 2,548' measured depth (MD). The motor-drilled hole was reamed with the same assembly that would be used to drill the tangent section in order to avoid making an additional trip. After the directional hole was reamed, the hole was dried out and dusted to 2,811' MD. At this point, an estimated build rate of $9.5^{\circ}/100'$ would be needed to hit the target of 2,965' true vertical depth (TVD).

Because of the price differential between the Baker motor and Eastman motor, the Baker motor was used to drill the remainder of the build section. The Baker 2° bent housing motor drilled from 2,811' to 3,165' at an average penetration rate of $18.2'$ /hr. Only one siltstone stringer was encountered during the motor run. The motor built inclination at an average rate of $9^{\circ}/100'$.

The estimated inclination at the end of the build section was 68° . The drilling plan had called for stopping the build section at 71° . However, the build rate experienced with the rotary assembly in the tangent section was $1.34^{\circ}/100'$. The slant section was supposed to be built at $0.5^{\circ}/100'$. Since the slant section was at a higher inclination in a softer formation, it was assumed that the rotary assembly would build at a lower rate; between 0.5 and $1^{\circ}/100'$. This rate would be slightly higher than the planned rate; therefore, the slant section was started at a lower inclination to compensate for the anticipated higher build rates.

4. SLANT SECTION

The slant section was drilled from 3,165' to a total depth of 4,833'. Basically, the rotary assembly that was used to drill the tangent section was also used to drill the slant section. On the first run, the rotary assembly drilled to a measured depth of 3,785'. The rotary assembly had begun to walk to the left at about $1.5^{\circ}/100'$. At this rate, the wellbore would have been too close to the lease line at the end of the target interval. Since the assembly had walked to the right in the tangent section, it had been assumed that it would walk the same in the slant section. Therefore, no right hand lead had been set at the end of the build section.

The Baker 2° bent housing motor was used to turn the wellbore back to the right with the tool face set 70° to the right of high side. After drilling only 70' (to 3,855'), the steering tool indicated that the motor was not only turning the wellbore to the

right but it was also dropping inclination rapidly. The motor was pulled to prevent the wellbore from dropping too much inclination.

The exact reason the motor assembly dropped inclination is not known. Initially, the key in the mule shoe sub was thought to have been knocked out with the steering tool. When trying to seat the steering tool, it continually stopped at the top of the drill collars (change in internal diameter). To overcome the problem, the steering tool was run at a higher velocity than normal. Later inspection of the mule shoe sub in the daylight showed that there was no damage to the key. The tool was also seated properly because the weight indicator showed that the latch in assembly pins sheared when the tool was pulled from the hole. Calibration of the steering tool after the motor run indicated the tool was still working properly. Surveys showed the motor had dropped 7° and turned 6° to the right in the 70' that it had drilled. Because of problems associated with hole cleaning (see Appendix G) and budget constraints, additional motor runs to bring the inclination back up were aborted.

While making the motor run, a discrepancy between the steering tool and singleshot survey data was noted. The singleshot continually had a three degree difference in hole direction due to magnetic interference. The discrepancy was noted both at the end of the build section and at the beginning of the motor run in the slant section. The steering tool is a more accurate instrument (electronic versus compass) so the singleshot data was adjusted three degrees. The first survey to be corrected was at a measured depth of 3,187'. All subsequent singleshot data was corrected.

After the motor run, the motor-drilled hole was reamed with a rotating bottomhole assembly. One day was spent circulating to clean the hole and drying out the hole before drilling continued to total depth (TD).

The lower inclination experienced after the motor run caused the wellbore to drop out of the target zone earlier than had been planned. The wellbore dropped below a TVD of 3,400' at approximately 4,400' MD. Drilling continued until no more shows were encountered. The last mud log show was at 4,674' MD. Total measured depth was 4,833'. The coordinates at TD are 3,570.90' TVD; 1,325.35' S; and 1643.47' E.

After logging, 113 joints of 5 1/2", 17#/ft, N-80, LT&C casing was run and set at 4787' KB. A total of 60 rigid centralizers (manufactured by Gemeco) were run with a spacing of one centralizer per joint. The top centralizer was at 2,316'. A latch down collar was placed in the top of the first joint. The 5 1/2" casing was cemented as follows:

Two barrels water; 40 barrels water with 3 ppb gel; 5 barrels water; 20 barrels CW-100; 10 barrels water; 605 sacks 50/50 poz with 2% calcium chloride, 10% salt, 10 pps kolite, 1% D-60, 0.25% D-46, and 1/8 pps celloflake. Cement was mixed at 13.8 ppg with a yield of 1.46 cubic feet per sack. The cement was displaced with 112 barrels fresh water. The plug was bumped with 1,380 psi and the float held OK.

The drilling rig was then rigged down and moved out. The casing tally can be found in Appendix B.

5. LOGGING

Logging runs were attempted using conventional wireline techniques. The first log attempted was with a TV camera by Young Wireline. The TV camera fell to a depth of 1,630' where it stopped on a ledge on the low side of the hole.

Schlumberger was rigged up and made several logging runs with conventional logging techniques; none of which made it to TD. The logging runs and depth reached are as follows in Table 1.

Table 1. Logs and Logged Intervals - Conventional Logging

LOG RUN #	LOGS	DEPTH LOGGED
1	Temp, LDT, NGT	3131'
2	Same as #1 with extra weight	3154'
3	Same as #2 with teflon guides	3078'
4	Induction Log	3210'
5	SNP with rubber nose guide	3138'

Schlumberger then rigged up their TLC (Tough Logging Conditions) drill pipe conveyed logging system. Table 2 lists the logs run and intervals logged with the TLC equipment.

Table 2. Drill Pipe - Conveyed Logs and Logged Intervals

LOG RUN #	LOGS	DEPTH LOGGED
6	LDT, NGT, Induction	4833'
7	Temp, and SNP	4833'

After running Schlumberger's TLC equipment, Young Wireline was rigged up and a TV camera was run from 2,847' to 4,833' using drill pipe and a side entry sub. The drill pipe tallies for each logging run can be found in Appendix C.

III. COMPLETION AND STIMULATION

Four intervals were selected for completion and stimulation based on mud log shows and analysis of the aforementioned log suite. Based upon pre-stimulation

data, the best of the shows were well below the bottom of the target zone as presented in Figure 4. Offset well data had suggested that the best zone(s) should be expected near the top of the target zone. Moreover, the deeper zones were not even encountered in the offset vertical wells. These factors combined suggest the targeted fracture system to be more complex than interpretations of vertical well control had predicted.

Four separate hydraulic fracturing treatments were performed. Stimulation treatments are summarized by completion stage in Table 3. In Figure 7, principle gas show intervals are bounded, top and bottom, with X-symbols plotted directly on the wellbore trajectory. Completion stages are indicated by numbered sub-horizontal bars above the wellbore trajectory. Completion stage numbers in Figure 7 correspond to those in Table 3.

Table 3. Summary of Stimulation Treatments

<u>Stage</u>	<u>Perforated Interval (MD)</u>	<u>Length</u>	<u>Nitrogen Volume</u>	<u>Flow Rate</u>
1	4,618'-4,624'	6'	1,303 MCF	30-35 MCF/D
2	4,416'-4,563'	147'	1,465 MCF	45-54 MCF/D
3	4,144'-4,356'	212'	1,170 MCF	40-45 MCF/D
4	3,466'-4,036'	570'	1,800 MCF	80 MCF/D

The stimulated intervals ranged from 6 to 570 feet long. All intervals were treated with straight nitrogen, as were the vertical wells in the field. Nitrogen volumes ranged from 1,170,000 to 1,800,000 standard cubic feet, with injection rates ranging from 70,000 to 80,000 standard cubic feet per minute. Each zone was broken down ahead of the nitrogen with 400 to 500 gallons of 7.5% acid. Individual intervals were isolated with a retrievable bridge plug. Perforating was performed via wireline-conveyed hollow carrier guns using a set of specially designed rollers.

Production for each stage was measured after the nitrogen volume had dropped below 10%. Measurements were made through an orifice runaway and back pressure regulator to simulate line pressures of 40 to 45 psig. Flow rates (see Table 3) were monitored against simulated line pressure for several weeks in order to establish stabilized flow rates for each zone. Stabilized flow rates for the four zones summed to a total of 195 MCF/D but were not sustainable at that level under producing conditions. Much shorter duration measurements, meant to approximate open flows as measured at offset wells, summed to a total of 1.4 MMCF/D for the four zones. Both measurements suggested an apparent three-fold improvement over the average vertical well in the area.

IV. RESERVOIR PROPERTIES

Testing of reservoir properties was limited to the six-foot interval completed in stage 1. Prior to the 1,303 MCF nitrogen frac listed in Table 3, completion stage number 1

VERTICAL VIEW

BOGGS #1240 AZIMUTH = 128.88

Figure 7. Borehole Trajectory and Target Area with Mud Log Shows and Completed Intervals

received 500 gallons of 7.5% HCl acid and, unlike stages 2 through 4, also received a 386 MCF nitrogen breakdown treatment. Testing of reservoir properties by Reuben Graham, Inc. (GRI) began immediately after breakdown with a series of flow/shut-in periods. Results of the final flow period indicated the six-foot perforated interval was able to deliver between 8 and 9 MCF/D; and approximately 0.5 BBL of oil was swabbed each day.

Following the last flow period, a 358.4-hour pressure build-up test was performed. Analysis of this pressure build-up test by S.H. Holdich & Associates, via conventional type-curve and semi-log "Horner" analysis, found a permeability-thickness product (kh) of only 0.2 md-ft. Assuming a net pay of 26 feet, an average post-breakdown permeability of 0.0076 md and an apparent skin factor of -2.1 were calculated; and an initial reservoir pressure of 981 psia was estimated. Assuming a net pay of 5 feet, however, suggests a permeability of 0.04 md and a skin factor of -2.8. Based on these results, it was concluded that the zone was stimulated by the 386 MCF breakdown treatment, but that the breakdown treatment failed to connect the borehole with any significant natural fracture system (Graham, 1991). S.H. Holdich's analysis of reservoir properties can be found in Appendix I.

V. PRODUCTION

Production history and projections for the Glada Boggs 1240 are presented in Figure 8. Thus far, gas deliverability has been far lower than had been expected. Unexpected oil production of approximately 1 barrel per day has had a substantial detrimental effect on gas deliverability. Operational aspects of gas production have been complicated, and gas deliverability reduced, by the periodic buildup of hydrostatic pressure due to accumulation of oil in the wellbore. Moreover, gas flow into the wellbore may be significantly curtailed due to relative permeability of the reservoir rock to oil and gas.

Initially, both gas and oil were produced through the well's production tubing string. Typically, the well was taken off-line about once per month, and the gas vented to the atmosphere to clear the tubing of accumulated oil. Under these operating conditions, gas production ranged from a high on the order of 60 MCF/D to lows on the order of 10 MCF/D with average gas and oil production of approximately 15 to 16 MCF/D and 0.95 BBL/D respectively. Problems with this operating mode were (1) low average gas deliverability, and (2) loss of gas vented to the atmosphere.

Initial indications were that incremental production increases from an artificial lift system probably would not support incremental expenses. Instead, in July 1991, it was decided to produce gas through the casing with periodic swabbing of oil through the tubing. This mode of operation would permit more continuous production of gas, prevent loss of gas to the atmosphere, and it was hoped, would raise average gas and oil production rates by reducing the average hydrostatic pressure on the reservoir. Insufficient production data has been compiled to test this hypothesis completely. However, preliminary indications are that gas production has increased by more than 20% to an average of 19 to 20 MCF/D. A similar increase has not been seen in oil production which has remained at about 1 BBL/D. This increase in gas deliverability is the justification for shifting the gas projection up as shown in Figure 8.

Figure 8

Cumulative production for the period September 1990 through August 1991 totalled 5,750,000 cubic feet of gas and 493 barrels of oil. In contrast, production of near-offset vertical wells ranged from 5,200,000 to 53,500,000 cubic feet of gas, and no oil, during an equivalent 12-month period. Oil production is thought to be coming from the zone at 4,622 feet measured depth, completed in stage 1; a zone which apparently was not encountered in any of the near-offset vertical wells.

Production data compiled to date suggests that sustained gas deliverability on the order of 60 MCF/D may be possible if problems associated with low-volume oil production could be solved. Future operations work will explore the possibility of squeezing-off the deeper completion in hopes of realizing this potential.

VI. PROJECT COST

The total actual cost of the Glada Boggs 1240 well is \$726,123. The total projected cost per the project AFE was \$655,666. This gives a total variance for the project of (\$70,457) or (10.75%); very close to the AFE cost for a well of this type. Actual and AFE costs and variances are presented on a line-item basis in Figure 9.

VII. PROJECT ECONOMICS

A histogram of ultimate recoverable reserves for 36 vertical wells offsetting the Boggs 1240 is presented in Figure 10. On the horizontal axis is projected ultimate recovery in MMCF. On the vertical axis is the number of wells in each of the reserves categories. Reserves were estimated via decline curve analysis of individual wells. Individual production histories were fitted and declined for a total (historical + projected) of 35 years. This differs from the statistically derived type-curve approach presented in the earlier paper (Muncey, 1989a), but has led to essentially identical conclusions regarding drilling economics.

An important insight from the revised reserves analysis is that it is now more clear that the distribution of reserves is actually bimodal. A high-reserves population and a low-reserves population are now apparent. Both populations appear to exhibit log-normality. It is also interesting to note that at least two of the three wells which make up the high-reserves population are apparently associated with the northwest structural trend which is evident in Figure 3. Assuming a log-normal distribution, average reserves for the total population are 68 MMCF per well. Averages for the low-reserves and high-reserves populations are 47 MMCF and 640 MMCF respectively.

Economic modeling presented in Figure 11 suggests that, at today's gas prices and cost structure, vertical wells with ultimate recoveries of less than about 250 MMCF are uneconomical to drill, even with the Section-29 tax credit. Selected economic assumptions underlying the minimum economic reserves figure are listed in Table 4. The form of production decline is derived from type-curve analysis of the 36 offsetting vertical wells. Minimum reserves were estimated by iteratively scaling the initial production rate of the type-curve until the minimum rate of return (20% before Federal income tax) was converged upon. It should be noted that the minimum (vertical well) economic reserves figure has increased substantially, from the 150 MMCF figure used in Muncey, 1989a, to reflect current conditions in the gas market and revised price expectations arising from those conditions.

PROJECT COST - AFE vs ACTUAL

EXPENSE CATEGORY	AFE	ACTUAL	% ACTUAL	VARIANCE	% VARIANCE
Casing - Protection	29,394.00	28,431.54	3.92%	\$962.46	3.27%
Casing - Surface	5,600.00	5,640.50	0.78%	(\$40.50)	(0.72%)
Liner Hanger & Equipment	5,000.00	0.00	0.00%	\$5,000.00	100.00%
Miscellaneous/Trucking	1,000.00	0.00	0.00%	\$1,000.00	100.00%
Well Head Equipment	5,000.00	3,828.59	0.53%	\$1,171.41	23.43%
Casing - Production	36,360.00	46,355.24	6.38%	(\$9,995.24)	(27.49%)
Heater Treater & Separator	3,225.00	6,210.26	0.86%	(\$2,985.26)	(92.57%)
Installation Cost	2,000.00	7,032.00	0.97%	(\$5,032.00)	(251.60%)
Tank Battery	4,500.00	868.38	0.12%	\$3,631.62	80.70%
Tubing	18,060.00	22,272.90	3.07%	(\$4,212.90)	(23.33%)
Administrative Overhead	12,857.00	17,505.50	2.41%	(\$4,648.50)	(36.16%)
Directional Tool & Service	110,000.00	81,989.37	11.29%	\$28,010.63	25.46%
Drilling Daywork	60,000.00	58,968.75	8.12%	\$1,031.25	1.72%
Drilling Footage	29,670.00	26,108.00	3.60%	\$3,562.00	12.01%
Engineering/Supervision (drilling)	10,000.00	29,909.41	4.12%	(\$19,909.41)	(199.09%)
Fuel, Power & Water	7,500.00	5,520.00	0.76%	\$1,980.00	26.40%
Legal & Abstract	2,000.00	2,752.00	0.38%	(\$752.00)	(37.60%)
Location & Road	21,000.00	20,794.36	2.86%	\$205.64	0.98%
Miscellaneous	5,000.00	3,754.79	0.52%	\$1,245.21	24.90%
Mud & Chemicals	10,000.00	16,257.06	2.24%	(\$6,257.06)	(62.57%)
Mud Logger/Gas Protector	10,000.00	9,644.00	1.33%	\$356.00	3.56%
Permit & Fees	450.00	985.00	0.14%	(\$535.00)	(118.89%)
Retal Equipment	10,000.00	220.00	0.03%	\$9,780.00	97.80%
Rig Mobilization & Demobil	4,200.00	4,773.50	0.66%	(\$573.50)	(13.65%)
Supplies - Bits	16,000.00	19,942.36	2.75%	(\$3,942.36)	(24.64%)
Engineering Surveys & Eleva	1,500.00	0.00	0.00%	\$1,500.00	100.00%
Wireline Serv - Open Hole	38,500.00	62,862.98	8.66%	(\$24,362.98)	(63.28%)
Casing Crew & Equipment	2,000.00	1,202.00	0.17%	\$798.00	39.90%
Cement Service & Equipment	25,000.00	32,545.87	4.48%	(\$7,546)	(30.18%)
Completion Rig	24,000.00	41,360.47	5.70%	(\$17,360.47)	(72.34%)
Engineering/Supervision (comple	25,000.00	50,898.41	7.01%	(\$25,898.41)	(103.59%)
Location - Damages	10,850.00	7,821.74	1.08%	\$3,028.26	27.91%
Stimulation, Frac, Acid	90,000.00	99,333.79	13.68%	(\$9,333.79)	(10.37%)
Wireline Serv - Cased Hole	10,000.00	3,100.01	0.43%	\$6,899.99	69.00%
Wireline Serv - Perforating	10,000.00	7,234.50	1.00%	\$2,765.50	27.66%
Total	655,666.00	726,123.28	100.00%	(\$70,457.28)	(10.75%)

Figure 9. Project Cost - AFE vs. Actual

PROJECTED ULTIMATE RECOVERY (MMCF)

Figure 10. Histogram of Projected Ultimate Recovery for 36 Vertical Wells Offsetting the Glada Boggs 1240

DATE: 10/23/91
TIME: 13:22:06
PAGE: 3

PrimeEnergy Corporation
Estimated Reserves and Economics
AS OF AUG 1, 1990

PF:FINRPT 7
EVAL #: 7
ALTKY:USA

PROFITABILITY INDICATORS
PAYOUT : 4.0 YRS BTAX
DCFROR : 20.0% BTAX
RI-BTAX: 3.3 TO 1 DISC
NPV 10.0% 100.216 BTAX
NPV 15.0% 38.554 BTAX
NPV 20.0% -0.177 BTAX
NPV 25.0% -26.404 BTAX
NPV 30.0% -45.158 BTAX

ID CODE : MIN RSVS VERT WELL
NAME : MODEL STUDY
FIELD :
CNTY, STATE: ROANE, WV
FORMATION : DEVONIAN SHALE
OPERATOR : PRIMEENERGY

MINIMUM VERTICAL WELL RESERVES

FISCAL AUG	NUMBER	GROSS PROD OIL + COND	GROSS GAS PRODUCTION	DATE	GRI	WELL COUNT	BEG-PRICES	END-PRICES	AVG-PRICES	OIL (MMBLS)	GAS (MMCF)	NET GAS VOLUME	NET O+C PRICE	EFFECTIVE GAS PRICE	EFFECTIVE GAS PRICE	NET REV OIL + COND	NET GAS REVENUE	NET TOTAL REVENUE	BTAX CASHFLOW	CLM BTAX CASHFLOW
1991	1.0	0.000	12.791	JAN 1990	87.50000	0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1992	1.0	0.000	16.778			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1993	1.0	0.000	14.652			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1994	1.0	0.000	13.177			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1995	1.0	0.000	12.074			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1996	1.0	0.000	11.209			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1997	1.0	0.000	10.507			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1998	1.0	0.000	9.922			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1999	1.0	0.000	9.417			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2000	1.0	0.000	8.947			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2001	1.0	0.000	8.499			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2002	1.0	0.000	8.074			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2003	1.0	0.000	7.671			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2004	1.0	0.000	7.287			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2005	1.0	0.000	6.923			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
SUB TOTAL	1.0	0.000	157.927			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
REMAINDER	1.0	0.000	93.937			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOT 39.4 YR	1.0	0.000	251.865			0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1991	1.217	1.293	0.960			2.400	12.112	32.095	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1992	1.430	1.696	0.960			2.400	16.506	43.932	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1993	1.211	1.514	0.982			2.454	14.992	39.103	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1994	1.143	1.429	1.031			2.577	14.022	36.427	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1995	1.100	1.375	1.082			2.705	13.562	34.601	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1996	1.072	1.340	1.136			2.840	12.901	33.318	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1997	1.055	1.319	1.193			2.982	12.576	32.409	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1998	1.033	1.291	1.236			3.091	12.351	31.524	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1999	1.010	1.262	1.273			3.183	12.191	30.707	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2000	0.988	1.235	1.312			3.279	12.043	29.932	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2001	0.967	1.208	1.351			3.377	11.898	29.165	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2002	0.946	1.182	1.391			3.478	11.755	28.406	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2003	0.926	1.157	1.433			3.582	4.856	20.898	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2004	0.906	1.132	1.476			3.690	0.000	15.438	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2005	0.886	1.108	1.520			3.800	0.000	14.840	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
SUB TOTAL	15.891	19.542	18.336			45.840	161.564	452.795	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
REMAINDER	16.601	20.751	55.189			137.973	0.000	184.510	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOT 39.4 YR	32.491	40.293	73.525			183.813	161.564	637.304	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Figure 11. Reserves and Economics - Minimum Economic Vertical Well

The most important thing to note in Figure 10, however, is that the success rate implied by the sample population is very low; only on the order of 10%. We can conclude from this that the width and spacing of the fractured zones which characterize the reservoir are such that they make extremely risky targets for conventional vertically-drilled wells.

Figure 12 presents economics of the minimum acceptable slant well. Net revenue interest, operating cost, gas price, tax and discount rate assumptions are identical to those presented in Table 4. A non-research completed well cost of \$500,000 is assumed. The form of production decline is identical to the projection in Figure 8. Again, minimum reserves were estimated by iteratively scaling the initial production rate until the minimum rate of return was converged upon.

The results presented in Figure 12 suggest that, in this particular project area, slant wells would have to produce approximately 635 MMCF of gas on average, or roughly 9 times the 68 MMCF reserve average for our 36-well population, to constitute an economically viable investment. This means that the mean value of a slant well reserves distribution would have to be roughly 9 times that of the distribution illustrated in Figure 10.

Table 4. Selected Economic Assumptions

Gas Price	\$2.31/MCF; Flat prices for 2 years, Escalated @ 5% per year for 5 years, 3% per year thereafter
Operating Expenses	\$280 Per Month; Flat for 2 years, Escalated @ 5% per year for 5 years, 3% per year thereafter
Net Revenue Interest	87.5%
Taxes	Economics are before Federal Income Tax Tax Credit Per Section 29 of U.S. Tax Code treated as element of operating income
Discount Rate	Minimum acceptable pre-tax return = 20%
Well Cost	\$185,000 Through Completion

Projected economics and reserves for the Glada Boggs 1240 are presented in Figure 13. Oil and gas production history and projections are illustrated in Figure 8. This economic evaluation differs from the minimum vertical and slant well evaluations in that the well produces oil. Oil prices are assumed constant for two years, then are escalated at 5% per year for five years; then 3% thereafter. All other assumptions are identical to those outlined in Table 4. Given the economic assumptions, the Glada Boggs well is projected to cum 1,706 BBLS of oil and 58 MMCF of gas over a projected economic life of 13 years. The well will never payout, and the estimated net present value at the assumed pre-tax discount rate of 20% is about -\$424,000.

PF:FINRPT
EVAL #: 6
ALTKY:USA

PrimeEnergy Corporation
Estimated Reserves and Economics
AS OF AUG 1, 1990

DATE: 10/23/91
TIME: 13:21:43
PAGE: 2

PROFITABILITY INDICATORS
PAYOUT : 4.9 YRS BTAX
DCFROR : 20.0% BTAX
RI-BTAX: 4.0 TO 1 UNDISC 4.0 TO 1 DISC
NPV 10.0% 292.822 BTAX
NPV 15.0% 110.157 BTAX
NPV 20.0% -0.015 BTAX
NPV 25.0% -73.026 BTAX
NPV 30.0% -124.578 BTAX

MINIMUM SLANT WELL RESERVES

ID CODE : MIN RSVS SLANT WELL

NAME : MODEL STUDY
FIELD :
CNTRY, STATE: ROANE, WV
FORMATION : DEVONIAN SHALE
OPERATOR : PRIMEENERGY

VI	OR1	GRI	DATE	WELL COUNT	BEG-PRICES	END-PRICES	AVG-PRICES	GROSS RESERVES
100.00000	87.50000	87.50000	JAN 1990	NET	OIL 0.30	0.00	0.00	CUMULATIVE REMAINING
				GROSS	GAS 2.31	3.44	6.61	0.000
				0				0.000
				0				634.979

FISCAL AUG	NUMBER	GROSS PROD	GROSS GAS	NET VOLUME	NET GAS	EFFECTIVE	EFFECTIVE	NET REV	NET GAS	NET TOTAL
		OIL + COND	PRODUCTION	OIL + COND	VOLUME	O-C PRICE	GAS PRICE	OIL + COND	REVENUE	REVENUE
		MBBLS	MMCF	MBBLS	MMCF	\$/BBL	\$/MCF	MM\$	MM\$	MM\$
1991	1.0	0.000	32.247	0.000	28.217	0.00	2.31	0.000	65.178	65.178
1992	1.0	0.000	42.299	0.000	37.012	0.00	2.31	0.000	85.497	85.497
1993	1.0	0.000	36.939	0.000	32.322	0.00	2.36	0.000	76.319	76.319
1994	1.0	0.000	33.220	0.000	29.068	0.00	2.48	0.000	72.068	72.068
1995	1.0	0.000	30.440	0.000	26.635	0.00	2.60	0.000	69.335	69.335
1996	1.0	0.000	28.259	0.000	24.727	0.00	2.73	0.000	67.582	67.582
1997	1.0	0.000	26.489	0.000	23.178	0.00	2.87	0.000	66.512	66.512
1998	1.0	0.000	25.015	0.000	21.888	0.00	2.97	0.000	65.107	65.107
1999	1.0	0.000	23.742	0.000	20.775	0.00	3.06	0.000	63.646	63.646
2000	1.0	0.000	22.555	0.000	19.736	0.00	3.16	0.000	62.276	62.276
2001	1.0	0.000	21.427	0.000	18.749	0.00	3.25	0.000	60.934	60.934
2002	1.0	0.000	20.356	0.000	17.812	0.00	3.35	0.000	59.622	59.622
2003	1.0	0.000	19.338	0.000	17.156	0.00	8.15	0.000	58.338	58.338
2004	1.0	0.000	18.371	0.000	7.156	0.00	0.00	0.000	57.082	57.082
2005	1.0	0.000	17.453	0.000	0.000	0.00	0.00	0.000	55.853	55.853
SUB TOTAL	1.0	0.000	398.152	0.000	307.275	0.00	3.21	0.000	985.349	985.349
REMAINDER	1.0	0.000	236.826	0.000	0.000	0.00	0.00	0.000	1046.322	1046.322
TOT 39.4 YR	1.0	0.000	634.978	0.000	307.275	0.00	6.61	0.000	2031.671	2031.671

FISCAL AUG	NET SEV	NET ADVL	NET LOE	NET G2A	DEV SHALE	NET OPER	NET ABAND	NET TOTAL	BTAX	CUM BTAX
	TAXES	TAXES	(FIX + VAR)	MBBLS	TAX CREDIT	REVENUE	& SALVAGE	INVESTMENT	CASHFLOW	CASHFLOW
	MM\$	MM\$	MM\$	MM\$	MM\$	MM\$	MM\$	MM\$	MM\$	MM\$
1991	3.069	3.259	0.960	2.400	30.535	86.025	0.000	500.000	-413.974	-413.974
1992	3.606	4.275	0.960	2.400	41.614	115.870	0.000	0.000	115.870	-298.104
1993	3.053	3.816	0.982	2.454	37.796	103.810	0.000	0.000	103.810	-194.294
1994	2.883	3.603	1.031	2.577	35.351	97.325	0.000	0.000	97.325	-96.969
1995	2.773	3.467	1.082	2.705	33.688	92.995	0.000	0.000	92.995	-3.973
1996	2.703	3.379	1.136	2.840	32.524	90.047	0.000	0.000	90.047	86.074
1997	2.660	3.326	1.193	2.982	31.705	88.056	0.000	0.000	88.056	174.130
1998	2.604	3.255	1.236	3.091	31.137	86.057	0.000	0.000	86.057	260.188
1999	2.546	3.182	1.273	3.183	30.734	84.195	0.000	0.000	84.195	344.383
2000	2.491	3.114	1.312	3.279	30.463	82.443	0.000	0.000	82.443	426.826
2001	2.437	3.047	1.351	3.377	29.996	80.719	0.000	0.000	80.719	507.545
2002	2.385	2.981	1.391	3.478	29.634	79.021	0.000	0.000	79.021	586.566
2003	2.334	2.917	1.433	3.582	29.242	60.314	0.000	0.000	60.314	646.880
2004	2.283	2.854	1.476	3.690	12.242	46.779	0.000	0.000	46.779	693.659
2005	2.234	2.793	1.520	3.800	0.000	45.505	0.000	0.000	45.505	739.164
SUB TOTAL	40.062	49.267	18.336	45.840	407.320	1239.164	0.000	500.000	739.164	1475.054
REMAINDER	41.853	52.316	55.189	137.973	0.000	758.990	23.101	0.000	758.889	1475.054
TOT 39.4 YR	81.915	101.584	73.525	183.813	407.320	1998.154	23.101	500.000	1475.053	1475.054

Figure 12. Reserves and Economics - Minimum Economic Slant Well

PE:FINRPT 1
 EVAL #: 1
 ALTKY:USA

PrimeEnergy Corporation
 Estimated Reserves and Economics
 AS OF AUG 1, 1990

DATE: 10/23/91
 TIME: 13:21:19
 PAGE: 1

ID CODE : SWABBING @ 20 MCF/DAY										PROFITABILITY INDICATORS									
NAME : GLADA BOGGS (SDPC 1240)										PAYOUT : * YRS BTAX									
FIELD : STATE: ROANE, WV										DCFROR : * % BTAX									
FORMATION : DEVONIAN SHALE										RI-BTAX: 0.3 TO 1 UNDISC 0.3 TO 1 DISC									
OPERATOR : PRIMEENERGY										NPV 10.0% -403.473 BTAX									
										NPV 15.0% -413.022 BTAX									
										NPV 20.0% -419.429 BTAX									
										NPV 25.0% -423.698 BTAX									
										NPV 30.0% -426.483 BTAX									
PROJECTED PERFORMANCE										GROSS RESERVES									
WELL COUNT										AVG-PRICES									
GROSS NET										END-PRICES									
OIL GAS										OIL (MBBLS)									
0 0.00 0.00 0.00										GAS (MMCF) 1.716									
0 0.00 0.00 0.00										58.037									
FISCAL AUG										FISCAL AUG									
NUMBER										NET VOLUME									
GROSS WELLS										OIL + COND									
GROSS PROD										GROSS GAS									
OIL + COND										PRODUCTION									
MBBLS										MMCF									
1.0										5.143									
0.419										0.367									
0.209										5.903									
0.182										0.182									
0.160										5.891									
0.133										0.140									
0.117										4.636									
0.105										0.117									
0.097										4.855									
0.090										4.507									
0.084										4.225									
0.080										3.990									
0.076										3.787									
0.072										3.597									
0.068										3.417									
0.066										3.247									
0.064										3.084									
0.062										3.025									
0.060										0.000									
1.0										49.007									
1.716										21.62									
0.000										0.000									
1.716										49.007									
FISCAL AUG										FISCAL AUG									
NET ADVL										NET LOE									
TAXES										(FIX + VAR)									
NET SEV										NET									
TAXES										G&A									
MB										MB									
0.836										2.200									
0.769										6.775									
0.623										7.628									
0.552										6.817									
0.535										6.323									
0.512										5.997									
0.499										5.773									
0.488										5.615									
0.477										5.506									
0.467										5.428									
0.457										5.360									
0.432										5.295									
0.408										5.231									
0.384										5.161									
0.360										5.091									
0.336										5.024									
0.312										4.958									
0.288										4.892									
0.264										4.826									
0.240										4.760									
0.216										4.694									
0.192										4.628									
0.168										4.562									
0.144										4.496									
0.120										4.430									
0.096										4.364									
0.072										4.298									
0.048										4.232									
0.024										4.166									
0.000										4.100									
0.000										4.034									
0.000										3.968									
0.000										3.902									
0.000										3.836									
0.000										3.770									
0.000										3.704									
0.000										3.638									
0.000										3.572									
0.000										3.506									
0.000										3.440									
0.000										3.374									
0.000										3.308									
0.000										3.242									
0.000										3.176									
0.000										3.110									
0.000										3.044									
0.000										2.978									
0.000										2.912									
0.000										2.846									
0.000										2.780									
0.000										2.714									
0.000										2.648									
0.000										2.582									
0.000										2.516									
0.000										2.450									
0.000										2.384									
0.000										2.318									
0.000										2.252									
0.000										2.186									
0.000										2.120									
0.000										2.054									
0.000										1.988									
0.000										1.922									
0.000										1.856									
0.000										1.790									
0.000										1.724									
0.000										1.658									
0.000										1.592									
0.000										1.526									
0.000										1.460									
0.000										1.394									
0.000										1.328									
0.000										1.262									
0.000										1.196									
0.000										1.130									
0.000										1.064									
0.000										1.000									
0.000										0.934									
0.000										0.868									
0.000										0.802									
0.000										0.736									
0.000										0.670									
0.000										0.604									
0.000										0.538									
0.000										0.472									
0.000										0.406									
0.000										0.340									
0.000										0.274									
0.000										0.208									
0.000										0.142									
0.000										0.076									
0.000										0.010									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0.000										0.000									
0																			

VIII. SUMMARY AND CONCLUSIONS

This paper presents the final results of a directionally-drilled Devonian Shale well in Roane County, West Virginia. Drilling operations resulted in a wellbore which meets virtually all design criteria. Funds budgeted for the project totaled \$655,666. Total funds expended for the project are approximately \$726,123; a budget variance of (10.75%). Based on the above it is clear that the project has successfully demonstrated the technological feasibility of slant well drilling and must, therefore, be considered an engineering success.

Unfortunately, the project well cannot be considered an economic success, nor can it be considered a geological success. Lower-than-expected gas deliverability suggests that neither the high-angle drilling nor subsequent hydraulic fracturing treatments were successful at connecting the borehole with the natural fracture system(s) encountered in nearby high-deliverability vertical wells. This, combined with a borehole which met virtually all of its design criteria, suggests that the vertical-well-based reservoir model failed to adequately predict fracture distribution within the reservoir. Furthermore, the apparent absence of fractures predicted by the vertical-well-based reservoir model suggests that Devonian Shale fracture systems, at least in the study area, may not exhibit sufficient continuity along strike and depth for directional drilling to deliver an economic benefit.

Analysis of production histories of 36 nearby vertical wells suggests that the average vertical well in the project area will ultimately produce only about 68 MMCF of gas. Economic modeling has shown that, on average, slant wells in the area would have to recover 635 MMCF, or about 9 times the gas reserves of the average vertical well in the area, for such drilling to be considered economically viable.

Analysis of one year of production history suggests that, under current mode of operation, the project well will produce only about 85% as much gas as the average vertical well in the study area. However, the production data also suggest that sustained gas deliverability could be increased by roughly a factor of three (from 20 MCF/D to 60 MCF/D) if operational problems associated with low-volume oil production could be solved. Future work will explore the possibility of squeezing-off the deepest completion (completion stage 1), or installation of a gas-lift system, in hopes of realizing this potential. It should be noted, however, that full realization of this potential will not materially change the economic outcome of the project well.

Notwithstanding the economic failure of this project well, it should be emphasized that directional drilling as a development strategy for the Devonian Shale cannot be tested with one well. A more accurate assessment of directional drilling results and additional insight into the question of fracture system continuity will be revealed only as additional wells are drilled.

SELECTED REFERENCES

Caramanica, Frank P. 1988. A Geologic Model of Gas Production From the Lower Huron: Eastern Devonian Gas Shales Technology Review. Gas Research Institute, Volume 5, Numbers 2 and 3, pp. 4-16.

Graham, Reuben L. 1991. Topical Well Report, Boggs #1240 - Deviated Well, Sterling Drilling and Production Company: Exploration - Production Studies in Newly Drilled Devonian Shale Gas Wells. Gas Research Institute. Contract No. 5090-213-2016.

Lowery, Patrick H., Terence Hamilton-Smith, and R. Michael Peterson. 1988. Gas Production Controlled By Geological Features: GRI CSW No. 2 Area. Eastern Devonian Gas Shales Technology Review. Gas Research Institute. Volume 5, Numbers 2 and 3, pp. 17-27.

Muncey, Gery, 1990. PrimeEnergy/DOE/GRI Slant Well: A Directional Drilling Case History, Proceedings of the Natural Gas R&D Contractors Review Meeting, eds R.D. Malone, H.D. Shoemaker, C.W. Byrer, DOE/METC-91/6117 (Conf-901117).

Muncey, Gery. 1989a. Upcoming Plans for the DOE/Sterling/GRI/Columbia Slant Well Project. Proceedings of the Natural Gas R&D Contractors Review Meeting, eds C.A. Komar, R.D. Malone, and C.W. Byrer, DOE/METC-89/6103 (Conf-890492).

Muncey, Gery, Richard Carden. 1989b. Additional Field Experiments II: Cooperative Slant Well Research. Presented at the Gas Research Institute Devonian Gas Shales Workshop and Short Courses, September 26 and 27.

Sweeny, Joe. 1986. Oil and Gas Report and Maps of Wirt, Roane, and Calhoun Counties, West Virginia. Bulletin B-40, West Virginia Geological and Economic Survey, pp. 1-102.

Yost, Albert B., II, R. Carden, J.G. Muncey, W.E. Stover, and R.J. Scheper. 1990. Air Drilling and Multiple Hydraulic Fracturing of a 72 Degree Slant Well in Devonian Shale. Presented at the SPE Eastern Regional Conference and Exhibition, Columbus, Ohio, October 31 - November 2.

Appendix A

DAILY DRILLING REPORTS

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/11/89 REPORT TIME: 7:00 am
 DEPTH: 165 FOOTAGE: 165 ACTIVITY: Drilling
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 1

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Out	Foot- Age	Ft/ Hr	Wt	Rpm	Condition
1	17 1/2	F3J	Smith	MB3191	0		165	17.8	2-15	70	

AIR RATE: 2100scfm MIST RATE: BBLS/HR PRESSURE: 100
 ADDITIVES:

BHA: Bit, X-0, 2-8" DC'S, 3-6" DC'S
 SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 4:15 pm	9 1/4	Move in and rig up drilling rig (Exeter #53)
4:15	- 7:15 pm	3 1/2	Drill rat hole and mouse hole
7:45	- 10:00 pm	2 1/4	Spud at 7:45 pm 7/10/89. Drilling
10:00	- 12:00 mid	2	Work on compressors. Pull bit and remove jets. Pick up 8" drill collars.
12:00	- 7:00 am	7	Drilling. Hit water at 75'

DWC 16,038 CWC 16,038

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/12/89 REPORT TIME: 7:00 am
 DEPTH: 394 FOOTAGE: 229 ACTIVITY: Nipple up
 FORMATION: Shale HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 2

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
1	17 1/2	F3J	Smith	MB3193	0	394	22.2	15	70	1-3-I	

AIR RATE: 2100' scfm MIST RATE: BBLS/HR PRESSURE: 150
 ADDITIVES:

BHA: Bit, X-0, 2-8" DC's, X-0, 10-6" DC's
 SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 7:30	1 1/2	Service rig and air
7:30	- 4:00	8 1/2	Drilling to 394' KB
4:00	- 4:45	3/4	Circulate and condition hole
4:45	- 5:45	1	TOOH
5:45	- 7:15	1 1/2	Rig up and run 9fts 13 3/8", 54.5#/ft casing Landed casing at 371.75' GL, 381.75' KB.
7:15	- 9:00	1 3/4	Cement w/ 20 bbls 6% gel containing 2.5 ppb celloflake, 10 bbls water, 260 sxs Class "A" cement w/2% CaCl ₂ and 1/8 pps celloflake mixed at 15.6 ppg. Displaced w/59.5 bbls water. Bumped plug with 480 pls.
9:00	- 5:00	8	WOC
5:00	- 7:00	2	Nipple up

DWC 6,794 CWC 22,832

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/13/89 REPORT TIME: 7:00 am
 DEPTH: 1160 FOOTAGE: 766 ACTIVITY: Drilling
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 3

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
2	12 1/4	F-2	Smith	XF8405	394		766	46.4	40	80	

AIR RATE: 2100 scfm MIST RATE: BBLs/HR PRESSURE: 100
 ADDITIVES:

BHA: Bit, Y-0, 2-8" DC's, X-0, 15-6 " DC's
 SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 8:30	1 1/2	Wait on welder
8:30	- 11:00	2 1/2	Finish nipping up
11:00	- 12:00	1	TIH
12:00	- 1:00	1	Drill out
1:00	- 5:45	4 3/4	Dry out hole and drill
5:45	- 7:15	1 1/2	Rig repair
7:15	- 7:00	11 3/4	Drilling

DWC 9,745 CWC 32,577

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/14/89 REPORT TIME: 7:00 am
 DEPTH: 1650 FOOTAGE: 490 ACTIVITY: Drilling
 FORMATION: Salt sand HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 4

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot- Age	Ft/ Hr	Wt	Rpm	Condition
2	12 1/4	F-2	Smith	XF8405	394	1359	965	47.1	45	70	5-8-1/4
3	12 1/4	F-2	Smith	XH3806	1359		291	29.1	45	60	

AIR RATE: 2100 scfm MIST RATE: 10 BBLS/HR PRESSURE: 150
 ADDITIVES:

BHA: Same
 SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: Gas show at 1420'

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 7:30	1/2	Service rig and air
7:30	- 11:30	4	Drilling
11:30	- 3:45	4 1/4	Tirp for bit
3:45	- 8:00	4 1/4	Wash and ream 880' Soaping
8:00	- 2:30	6 1/2	Drilling
2:30	- 3:30	1	Repair drive chain
3:30	- 7:00	3 1/2	Drilling

DWC 14,121 CWC 46,698

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/15/89 REPORT TIME: 7:00 am
 DEPTH: 2010 FOOTAGE: 360 ACTIVITY: Trip
 FORMATION: Shale HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 5

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
3	12 1/4	F-2	Smith	XH3806	1359	1848	489	27.9	45	60	4-6-1/4
4	12 1/4	HP625	Reed	EB1134	1848	2010	162	32.4	35	60	

AIR RATE: 2100 scfm MIST RATE: 10 BBLS/HR PRESSURE: 150
 ADDITIVES:

BHA: Same
 SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	Comments
7:00	- 7:30	1/2	Service Rig
7:30	- 3:00	7 1/2	Drilling
3:00	- 4:15	1 1/4	Circulate to clean hole and unload Eastmon truck
4:15	- 8:15	4	Trip for bit
8:15	- 12:15	4	Ream 268' to bottom
12:15	- 5:15	5	Drlg to 2010'
5:15	- 6:15	1	Circulate
6:15	- 7:00	3/4	TOOH for casing

Base of Injun at 1915

DWC 8,786 CWC 55,484

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/16/89 REPORT TIME: 7:00 am
 DEPTH: 2010 FOOTAGE: 0 ACTIVITY: Waiting on flange
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 6

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot- Age	Ft/ Hr	Wt	Rpm	Condition
-------	------	------	-------	----------	----------	-----------	-----------	--------	----	-----	-----------

AIR RATE: MIST RATE: BBLs/HR PRESSURE:
 ADDITIVES:

BHA:
 SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
------	----	-----	----------

7:00	-	8:30	1 1/2	TOOH Lay down 2-7 "DC's"
8:30	-	9:30	1	Nipple down. Rig up to run 9 5/8" casing.
9:30	-	12:00	2 1/2	Run 45 jts 9 5/8" 36#J-55 sttc casing. Landed casing at 1988.90' KB,
12:00	-	2:00	2	Rig up Dowell. Cement with 5 bbls water, 20 bbls 6% gel, 11 bbls water, 384 sxs 50/50 poz w/2% CaCl ₂ and 1/8 pps celloflake, 100 sxs Class "A" cement w/2% CaCl ₂ and 1/8 pps celloflake. Displaced with 154 bbls water. Bumped plug at 2 pm w/850 psi. Good returns while cementing.
2:00	-	2:00	12	WOC
2:00	-	7:00	5	Wait on flange to nipple up BOP

DWC 19,981 CWC 66,465 DMC 2,815 CMC 2,815

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/17/89 REPORT TIME: 7:00 am
 DEPTH: 2150 FOOTAGE: 140 ACTIVITY: Rig up steering tool
 FORMATION: Shale HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 7

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
5	8 3/4	F3H	Smith	KD4958	2010	2150	140	93.3	20	70	
6	8 1/2	F4	Smith	KH2634	2150						

AIR RATE: 2100 scfm MIST RATE: BBLS/HR PRESSURE: 100
 ADDITIVES:

BHA:

SURVEYS: 1°, N60°E°, @ 2097'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 9:15	2 1/4	Wait on flange
9:15	- 10:15	1	Nipple up BOP
10:15	- 3:30	5 1/4	Strap in hole blowing water out of casing
3:30	- 5:30	2	Drill cement & shoe. Blow hole dry
5:30	- 7:00	1 1/2	Drill to KOP of 2150'
7:00	- 8:30	1 1/2	Rig up slick line and survey
8:30	- 11:30	3	TOOH Lay down 5 DC's. Pick up Eastman motor.
11:30	- 3:00	3 1/2	Wait on X-0 sub
3:00	- 5:30	2 1/2	Make up UBHO sub & TIH
5:30	- 7:00	1 1/2	Rig up steering tool

DWC 10,090 CWC 76,555 DMC 0 CMC 2,815

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/18/89 REPORT TIME: 7:00 am
 DEPTH: 2345 FOOTAGE: 195 ACTIVITY: Drilling
 FORMATION: Siltstone & sand HLU: 7,000 HLD: 66,000 TORQUE:
 ROTATING WEIGHT: DAY: 8

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Foot- Age	Ft/ Hr	Wt	Rpm	Condition
6	8 1/2	F4	Smith	KH2634	2150	195	11.8	2-7	150-200	

AIR RATE: 1637 scfm MIST RATE: 10 BBLS/HR PRESSURE: 500
 ADDITIVES: Soda Ash, Poly pac, gel, RCI, soap

BHA: Bit, mtr, X-0, X-0, FS, MSS, X-0, monel, monel, X-0, 9-6" DC's, X-0
 SURVEYS: 3.2°, 575°, @ 2160' 6.3°, 570E°, @ 2190' 13.2°, 570E°, @ 2251'
 15.6°, 566E°, @ 2282'

GAS: C1: 0 , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: 3 units at 2288'

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 11:00	4	Rig up steering tool and side entry sub
11:00 am-	8:00 pm	8 1/2	Drilling 1/2 connection
8:00	- 8:30	1/2	Service air and rig
8:30	- 10:30	2	Work on soap pumps
10:30	- 7:00	8	Drilling 1/2 connection

Coordinates @ 2282' 1.74'N 37.14E Clos 37.17 87.31°

DWC 14,380 CWC 90,935 DMC 2,741 CMC 5,556

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/19/89 REPORT TIME: 7:00 am
 DEPTH: 2485 FOOTAGE: 140 ACTIVITY: Drilling
 FORMATION: Shale & siltstone HLU: 73,000 HLD: 64,000 TORQUE:
 ROTATING WEIGHT: DAY: 9

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
6	8 1/2	F4	Smith	KH2634	2150	2362	212	10.6	2-8	150	2-2-1
RR6	8 1/2	F-4	Smith	KH2634	2362		123	12.9	2-10	140	
				13-13-B							

AIR RATE: 1637 scfm MIST RATE: 9 BBLS/HR PRESSURE: 530
 ADDITIVES: Same

BHA: Bit 2° bit motor, FS, MSS, X-0, 2-6 1/2 monels, X-0, 9-6" DC's, X-0 Total 354.15
 SURVEYS: 18.4°, 565.25E°, @ 2304' 22.7°, 562.25E°, @ 2348' 25°, 558.25E°, @ 2378'
 27.3°, 553.25E°, @ 2411'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	-	10:30	3 1/2 Drilling w/motor
10:30	-	11:00	1/2 Circ. to clean hole. Motor drilling very slow
11:00	-	3:00	4 TOOH & service DOT tool. Bit in good shape
3:00	-	4:00	1 Lay Eastman motor down
4:00	-	5:15	1 1/4 Unload foam products and load out compressor
5:15	-	8:30	3 1/4 Make up Baker 2° BH motor & TIH
8:30	-	9:00	1/2 Run DOT tool and break circ. 15' fill
9:00	-	7:00	9 1/2 Drilling 1/2 connection.

Coordinates @ 2411' TVD 2399.05 21.98's 79.51'E
 Closure 82.49' s 74.55 E

DWC 17,748 CWC 108,683 DMC 2,650 CMC 8,206

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/20/89 REPORT TIME: 7:00 am
 DEPTH: 2548 FOOTAGE: 63 ACTIVITY: Reaming
 FORMATION: Siltstone HLU: 80,000 HLD: 60,000 TORQUE:
 ROTATING WEIGHT: DAY: 10

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
RR6	8 1/2	F-4	Smith	KH2364	2362	2548	186	9.8	2-10	140	5-4-1/8
7	8 1/2	4GT	Smith	LZ3192							

AIR RATE: 3-750's 1400 MIST RATE: 5 BBLS/HR PRESSURE: 120
 ADDITIVES: Same

BHA: Bit, FS, 6pt, 2-monels, X-0, 9 DC's, X-0

SURVEYS: 28.5°, 545.25°E, @ 2440' 30.9°, 543.25°E, @ 2471' 33.5°, 544.25°E, @ 2492'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	-	5:00	9 1/2 Drilling 1/2 connection
5:00	-	7:00	2 Start out of hole. Lay down steering tool and rig down wireline.
7:00	-	10:30	2 1/2 TOOH. Lay down 10 jts drill pipe
10:30	-	12:00	1 1/2 Lay down motor. Pick up new BHA
12:00	-	1:00	1 Cut drilling line
1:00	-	2:30	1 1/2 TIH
2:30	-	3:00	1/2 Rig up soap pump and start air
3:00	-	7:00	4 Reaming directional hole from 2150' to 2390'

DWC 22,051 CWC 130,734 DMC 3,683 CMC 11,889

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/21/89 REPORT TIME: 7:00 am
 DEPTH: 2811 FOOTAGE: 263 ACTIVITY: Rig up steering tool
 FORMATION: 70% shale 30% siltstone HLU: 100,000 HLD: 45,000 TORQUE: 1/2 turn
 ROTATING WEIGHT: 55,000 DAY: 11

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
7	8 1/2	4GA	Smith	Lz3191	2548	2811	263	45.7	25	80	1-2-I
8	8 1/2	F-4	Smith	KJ4166	2811						

AIR RATE: 2600 MIST RATE: BBLS/HR PRESSURE: 110
 ADDITIVES:

BHA: Bit 2° motor, FS, MSS, X-0, 2-monels, X-0, --DC, XO
 SURVEYS: 33.5°, 546E°, @ 2490' 32.5°, 546E°, @ 2553' 32.75°, 547E°, @ 2615'
 33.75°, 547E°, @ 2667' 350, 546E @ 2738

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: 4 units at 2759' (siltstone)

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 7:30	1/2	Service rig and air
7:30	- 9:30	2	Ream to 2548' KB
9:30	- 10:30	1	Drying hole
10:30	- 12:30	2	Drilling
12:30	- 1:30	1	Change rotating head rubber
1:30	- 2:00	1/2	Drilling
2:00	- 4:00	2	Wait on survey line and rig up same
4:00	- 4:45	3/4	Run 3 surveys
4:45	- 6:00	1 1/4	Drilling
6:00	- 6:45	3/4	Circ & survey
6:45	- 8:15	1 1/2	Drilling
8:15	- 9:30	1 1/4	Circ & survey
9:30	- 10:00	1/2	Drilling
10:00	- 1:30	3 1/2	Circ & TOOH. Lay down 8 DC's
1:30	- 3:00	1 1/2	Pu Baker 2° BH motor
3:00	- 4:30	1 1/2	TIH
4:30	- 7:00	2 1/2	Rig up steering tool

Coordinates @ 2738' 2675' TVD 142's 207'E 251'VS

DWC 14,900 CWC 145,635 DMC 0 CMC 11,889

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/22/89 REPORT TIME: 7:00 am
 DEPTH: 3120 FOOTAGE: 309 ACTIVITY: Drilling
 FORMATION: Shale HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 12

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
8	8 1/2	F-4	Smith	KJ4166	2811		309	19.3	5-7	140	

AIR RATE: 1768 MIST RATE: 9 BBLs/HR PRESSURE: 520
 ADDITIVES:

BHA: Same

SURVEYS: 37°, 546E°, @ 2830' 42°, 546E°, @ 2890' 47.4°, 547E°, @ 2950'
 53°, 549E°, @ 3012'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: 3 units at 3000'

TIME BREAKDOWN AND COMMENTS:

FROM TO HRS

7:00	-	9:30	2 1/2	Rig up and run steering tool
9:30	-	10:00	1/2	Omont motor steering tool failed
10:00	-	10:30	1/2	Circ to get returns w/foaming
10:30	-	1:30	3	Pull & repair steering tool. Probe failed. Run same.
1:30	-	7:00	16	Drilling 1 1/2 connections

No fill on connections

Coordinates at 3012' 2878'TVD 267's 339'E 432'VS

Est. TD 7/27/89

DWC 11,893 CWC 157,528 DMC 0 CMC 11,889

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/23/89 REPORT TIME: 7:00 am
 DEPTH: 3165 FOOTAGE: 45 ACTIVITY: Trip
 FORMATION: Shale HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 13

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
8	8 1/2	F-4	Smith	KJ4166	2811		309	19.3	5-7	140	
RR7	8 1/2	4GA	Smith	LZ3192	3165						

AIR RATE: 1700 MIST RATE: 11 BBLS/HR PRESSURE: 150
 ADDITIVES: Same

BHA: Bit, 6pt, FS, 2 monels, X-0, DC, X-0
 SURVEYS: 58.9°, 548E°, @ 3074'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: None

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	-	10:30	3 1/2 Drilling to 3165' Est. Inc. 68°
10:30	-	3:15	4 3/4 TOOH. Tight after 2 stands. Circulate 4 joints out of hole. Pull island tight again. Circulate 1 hour to clean hole
3:15	-	4:15	1 Lay down steering tool and side entry sub
4:15	-	7:30	3 1/4 TOOH. Lay down BHA. Motor still looks good
7:30	-	9:15	1 3/4 Pick up 6 pt reamer and TIH
9:15	-	10:00	3/4 Break circulation
10:00	-	4:00	6 Ream directional hole from 2811' to 3080'
4:00	-	5:30	1 1/2 Trying to ream. Could not make any progress
5:30	-	7:00	1 1/2 TOOH

Coordinates @ 3074' TVD 2913' 301'S 378'E 483' Vertical Sec.

EST TO 7/27/89

DWC 12,009 CWC 169,627 DMC 0 CMC 11,889

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/24/89 REPORT TIME: 7:00 am
 DEPTH: 3207 FOOTAGE: 42 ACTIVITY: Drilling
 FORMATION: Shale HLU: 75,000 HLD: 54,000 TORQUE:
 ROTATING WEIGHT: DAY: 14

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot- Age	Ft/ Hr	Wt	Rpm	Condition
RR7	8 1/2	4GA	Smith	LZ3192	3165		42	42	20	70	

AIR RATE: 1539 MIST RATE: 0 BBLS/HR PRESSURE: 100
 ADDITIVES:

BHA: Bit, 6pt, FS, 2 monels, X-0, DC, X-0
 SURVEYS: 58.9°, 548E°, @ 3074'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: None

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	-	7:30	1/2 TOO. Left bit 6pt and float sub in hole
7:30	-	1:30	6 Wait on fishing tools
1:30	-	5:00	3 1/2 Make up overshot & jars. TIH
5:00	-	5:30	1/2 Break circulation & fish
5:30	-	10:00	4 1/2 POOH slowly. Lay down fish and fishing tool
10:00	-	11:00	1 Repairing derrick board
11:00	-	11:30	1/2 Pick up BHA
11:30	-	2:00	2 1/2 TIH
2:00	-	2:45	3/4 Break circulation and service rig
2:45	-	4:00	1 1/4 Ream 90' to bottom
4:00	-	6:00	2 Circ to clean hole. Hook up air dryer and blow hole dry
6:00	-	7:00	1 Drilling and drying hole

Fst TD 7/28/89

DWC 10,993 CWC 180,620 DMC 0 CMC 11,889

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/25/89 REPORT TIME: 7:00 am
 DEPTH: 3785 FOOTAGE: 578 ACTIVITY: Trip
 FORMATION: Shale HLU: 98,000 HLD: 42,000 TORQUE: 1rd
 ROTATING WEIGHT: 65,000 DAY: 15

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
RR7	8 1/2	4GA	Smith	LZ3192	3165	3785	620	33.5	20	60-80	

AIR RATE: 1539 MIST RATE: BBLS/HR PRESSURE: 100
 ADDITIVES:

BHA: Same

SURVEYS: 67 1/4°, 548E°, @ 3187' 68°, 548E°, @ 3249' 68 1/2°, 548E°, @ 3310'
 70°, 550E°, @ 3497' 71 1/2°, 552E°, @ 3620' 72°, 553E°, @ 3744'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: 3615 3u, 3670 18 u, 3728 8u, 3734 7u, 3774 9u

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS
7:00	- 12:15	3 3/4 Drig
		1 1/2 Survey
12:15	- 1:15	1 Change rotating rubber
1:15	- 5:45	13 3/4 Drilling
		2 3/4 Survey
5:45	- 6:15	1/2 Circ to clean hole
6:15	- 7:00	3/4 Survey

Coordinates @ 3744' 3156' TVD 704'S, 853'E 1106' VS

Est. TD 7/29/89

DWC 6,458 CWC 187,077 DMC 0 CMC 11,889

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/26/89 REPORT TIME: 7:00 am
 DEPTH: 3855 FOOTAGE: 70 ACTIVITY: Circulate
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY: 16

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
RR7	8 1/2	4GA	Smith	LZ3192	3165	3785	620	33.5	20	60-80	
RR8	8 1/2	F-4	Smith	RJ4166	3785		70	17.5			

AIR RATE: 1400 MIST RATE: 15 BBLs/HR PRESSURE: 460
 ADDITIVES:

BHA: Bit, 20 BH mtr, FS, MSS, X-0, 2 monels, X-0, DC, X-0
 SURVEYS: 72°, 553E°, @ 3751' 69.4°, 551E°, @ 3804'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT: 2 units
 SHOWS: 3848' 8-9 units

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	-	10:30	3 1/2 TOCH to make motor correction Hole tight 11 stds off bottom
10:30	-	12:00	1 1/2 Pick up Baker 2° BH motor. Pump through motor. Rune OK
12:00	-	1:15	1 1/4 TIH. Tight 12 1/2 std off bottom
1:15	-	3:45	2 1/2 Install rotating head. Transfer foam mixture to soad tanks
3:45	-	5:15	1 1/2 Break circ. and wash through 70'
5:15	-	6:00	3/4 TIH. 130' fill on bottom
6:00	-	9:15	3 1/4 Rig up and run steering tool
9:15	-	11:00	1 3/4 Break circulation and wash to bottom
11:00	-	4:30	4 Drilling
		1/2	Connections
4:30	-	5:30	1 Steering tool indicated inclination was droppin Tool may not be seated properly. TOH to check steering tool. Pulled 2 stds. Hole tight
5:30	-	7:00	1 1/2 Circulate to clean hole

Est TD 7/30/89

DWC 13,570 CWC 200,647 DMC 4,409 CMC 16,298

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/26/89 REPORT TIME: 7:00 am
 DEPTH: 3908 FOOTAGE: 53 ACTIVITY: Drlg
 FORMATION: Shale HLU: 90,000 HLD: 45,000 TORQUE: 1rd
 ROTATING WEIGHT: 66,000 DAY: 16

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
RR8	8 1/2	F-4	Smith	KJ4166	3785	3855	70	17.5	5	140	2-5-1/8
9	8 1/2	F-4	Smith	KF2972	3885		53	53	20	70	

AIR RATE: 1450 MIST RATE: BBLs/HR PRESSURE: 120
 ADDITIVES:

BHA: Bit, FS, 6pt, 2 monels, X-0, DC, X-0
 SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: 3882' 6u, 3920 4u

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 7:30	1/2	Circulate to clean hole
7:30	- 10:30	3	Pull steering tool
10:30	- 3:00	4 1/2	TOOH. Had to pump out 13 stands
3:00	- 4:30	1 1/2	Finish TOOH. Lay down motor
4:30	- 7:30	3	Pick up BHA. TIH
7:30	- 11:30	4	Wash to 3785'
11:30	- 4:30	5	Ream directional hole to 3855'
4:30	- 5:00	1/2	Drilling
5:00	- 6:30	1 1/2	Drying hole
6:30	- 7:00	1/2	Drilling

7/29/89 Est. TD

DWC 11,502 CWC 212,547 DMC 225 CMC 16,523

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/28/89 REPORT TIME: 7:00 am
 DEPTH: 4160 FOOTAGE: 252 ACTIVITY: Survey
 FORMATION: Shale HLU: 95,000 HLD: 45,000 TORQUE: 1rd
 ROTATING WEIGHT: 66,000 DAY: 18

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
9	8 1/2	F-4	Smith	KF2972	3885		305	46.0	20	65	

AIR RATE: 2300 MIST RATE: 0 BBLS/HR PRESSURE: 160
 ADDITIVES:

BHA: Same

SURVEYS: 65 1/4⁰, 548E⁰, @ 3897' 66 1/4⁰, 550E⁰, @ 4117'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: 3920 5u, 3950 9u, 3960 10u, 4016 7u, 4046 14u, 4044 14u, 4052 20u,
 4080 12u

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 8:45	1 3/4	Drlg & trying to dry hole. No returns
8:45	- 9:30	3/4	Pull 120' & become tight. Could not work up the hole
9:30	- 11:30	2	Circulate w/foam
11:30	- 12:30	1	POOH w/7 stands & circ to clean hole
12:30	- 2:00	1 1/2	TIH & wash 3 its to bottom
2:00	- 3:45	1 3/4	Circ. & survey
3:45	- 4:45	1	Circ & condition hole w/foam
4:45	- 6:45	2	Circulate w/air to dry hole
6:45	- 9:30	2 3/4	Drilling & trying to dry hole
9:30	- 11:00	1 1/2	Change air rig up to increase air volume from 1500 to 2300 scfm
11:00	- 1:00	2	Pulled 7 joints. Worked pipe & got circ.
1:00	- 3:30	2 1/2	Ream back to bottom cleaning hole
3:30	- 4:30	1	Drilling
4:30	- 6:30	2	Circulate
6:30	- 7:00	1/2	Survey

Coordinates at 4117' 3302' TVD, 926'S, 1114'E, 1449' VS

Est TD 7/29/89

DWC 9,471 CWC 222,017 DMC 0 CMC 16,523

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/29/89 REPORT TIME: 7:00 am
 DEPTH: 4681 FOOTAGE: 526 ACTIVITY: Drilling
 FORMATION: Shale & Siltstone HLU: 130,000 HLD: 30,000 TORQUE: 2rds
 ROTATING WEIGHT: 66,000 DAY: 19

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
9	8 1/2	F-4	Smith	KF2972	3885		826	30.0	20	60-70	

AIR RATE: 2150 MIST RATE: 0 BBLS/HR PRESSURE: 160
 ADDITIVES:

BHA: Same

SURVEYS: 67 1/4°, 552E°, @ 4321' 68 1/4°, 553E°, @ 4544'

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: 4206 30u, 4245 12u, 4256 14u, 4268 12u, 4272 13u, 4306 16u, 4314 18u, 4318 16u, 4344 12u, 4356 12u, 4367 12u, 4416 12u, 4420 12u, 4428 12u, 4437 16u, (Background increased from 10 to 13 units) 4504 21u, 4510 24u, 4552 12u, 4563 16u, 4598 17u, 4622 48u, (Background increased to 19u) 4654 20u, 4659 21u, 4674 29units

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 7:30	1/2	Survey
7:30	- 3:00	7 1/2	Drilling
3:00	- 3:30	1/2	Survey
3:30	- 6:15	2 3/4	Drilling
6:15	- 7:15	1	Replace rotating head rubber
7:15	- 3:00	7 3/4	Drilling
3:00	- 4:00	1	Circulate and survey
4:00	- 7:00	3	Drilling

Coordinates @ 4544' 3467'TVD 1170'S 1423'E 1842'VS

DWC 6,557 CWC 228,574 DMC 0 CMC 16,523

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 7/30/89 REPORT TIME: 7:00 am
 DEPTH: 4833 FOOTAGE: 152 ACTIVITY: Logging
 FORMATION: Siltstone & shale HLU: 140,000 HLD: 30,000 TORQUE: 2 1/4 rds
 ROTATING WEIGHT: 66,000 DAY: 20

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
9	8 1/2	F-4	Smith	KF2972	3885	4833	978	29.0	20	60-70	1-3-1

AIR RATE: 2085 MIST RATE: 0 BBLS/HR PRESSURE: 160
 ADDITIVES:

BHA: Same

SURVEYS: 69 1/4°, 556E°, @ 4789

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS: 4681 24u, 4686 22u, 4690 22u

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	-	7:15	1/4 Service R
7:15	-	1:30	6 1/4 Drilling to D
1:30	-	4:00	2 1/2 Circulate to clean hole
4:00	-	5:30	1 1/2 Survey and check gas rate
5:30	-	10:30	5 TOOH. LD drill collars
10:30	-	11:15	3/4 Rig up Young Wireline
11:15	-	1:00	1 3/4 Run TV camera to 2630'. Stopped on a ledge on the low side of hole
1:00	-	7:00	6 Wait on Schlumberger

Coordinates @ 4833' 3571'TVD, 1235'S 1643'E 2111'VS

DWC 9,819 CWC 238,392 DMC 0 CMC 16,523

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 8/1/89 REPORT TIME: 7:00 am
 DEPTH: FOOTAGE: ACTIVITY: Log w/TV camera
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY:

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot-Age	Ft/Hr	Wt	Rpm	Condition
-------	------	------	-------	----------	----------	-----------	----------	-------	----	-----	-----------

AIR RATE: MIST RATE: BBLS/HR PRESSURE:
 ADDITIVES:

BHA:
 SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 11:30	4 1/2	Finish logging w/2DT, NGT and induction
11:30	- 1:00	1 1/2	Change logging tools
1:00	- 5:00	4	Log run #7. Logges temperature log into hole
5:00	- 9:15	4 1/4	Log out of hole with SNP
9:15	- 11:00	1 3/4	Lay down logging tools. RD Schlumberger. Rig up Young wireline
11:00	- 4:00	5	TIH 46 std. Run TV camera to btm of drill pipe at 2847'. Install side entry sub
4:00	- 7:00	3	Log run #8. Logging w/TV camera
DWC 4,900		CWC 248,588	DMC 0 CMC 16,523

STERLING DRILLING & PRODUCTION

WELL NAME: Boggs #1240 DATE: 8/2/89 REPORT TIME: 7:00 am
 DEPTH: 4833 FOOTAGE: 0 ACTIVITY: Rig down Rotary Tools
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT: DAY:

BIT RECORD:

Bit #	Size	Type	Manuf	Serial #	Depth In	Depth Out	Foot- Age	Ft/ Hr	Wt	Rpm	Condition
-------	------	------	-------	----------	----------	-----------	-----------	--------	----	-----	-----------

AIR RATE: MIST RATE: BBLS/HRPRESSURE:
 ADDITIVES:

BHA:
 SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
7:00	- 7:30	1/2	Log in with camera
7:30	- 7:45	1/4	Service rig
7:45	- 9:45	2	Log out of hole with TV camera
9:45	- 12:00	2 1/4	Pull camera out of drill pipe. Hung up going back inside pipe. Rig down wireline
2:00	- 6:00	6	Lay down drill pipe
6:00	- 11:30	5 1/2	Run 113jts 5 1/2", 17#, N-80, LT&C casing. Set at 4787'KB. Run 60 rigid centralizers. One/joint
11:30	- 1:00	1 1/2	Cement with 2 bbls water, 40 bbls 3% gel water, 5 bbls water, 20 bbls CN-100, 10 bbls water, 605 sacks 50/50 poz w/2% gel, 10% salt, 2% CaCl ₂ , 10 pps Kolite, 1% D60, 0.25% D46, and 1/8 pps poly flake. Mixed at 13.8 ppg and 1.46 ft 3/sx. Displaced with 112 bbls fresh water. bumped plug with 1380 psi. Float held ok. Plug down at 1:00 am.
1:00	- 7:00	6	Rig down rotary tools
DWC	110,530	CWC	359,118
DMC	0	CMC	16,523

Appendix B

CASING TALLIES

13 3/8" CASING TALLY 7/11/89

13 3/8", 54.5#/FT, ST&C

JOINT NUMBER	LENGTH	JOINT NUMBER	LENGTH
SHOE	1.50		
1	40.65	26	
2	41.35	27	
3	43.35	28	
4	36.25	29	
5	42.35	30	
6	39.15	31	
7	44.30	32	
8	40.55	33	
9	42.30	34	
10		35	
11		36	
12		37	
13		38	
14		39	
15		40	
16		41	
17		42	
18		43	
19		44	
20		45	
21		46	
22		47	
23		48	
24		49	
25		50	
SUBTOT	371.75	SUBTOT	0.00
TOTAL	371.75		
Total length		371.75	
Landed below KB		10.00	
Setting depth		381.75 KB	
		371.75 GL	

9 5/8" CASING TALLY 7/14/89

9 5/8", 36#/FT, J55, ST&C

JOINT NUMBER	LENGTH	JOINT NUMBER	LENGTH
SHOE	1.00		
1	44.45	26	45.00
2	43.95	27	43.35
3	44.75	28	42.20
4	44.90	29	45.05
5	43.35	30	43.55
6	43.60	31	45.20
7	45.05	32	44.65
8	44.70	33	43.50
9	43.65	34	43.50
10	44.70	35	43.60
11	43.45	36	44.15
12	44.90	37	44.50
13	44.75	38	45.00
14	44.85	39	43.55
15	44.85	40	44.00
16	40.40	41	43.40
17	44.75	42	45.00
18	44.75	43	43.45
19	43.65	44	43.45
20	44.70	45	44.80
21	43.50	46	43.60 out
22	44.85	47	44.75 out
23	44.80	48	43.40 out
24	43.45	49	
25	36.25	50	

SUBTOT 1098.00 SUBTOT 1012.65

TOTAL 2110.65

Total length 2110.65
3 joints out 131.75
Landed below KB 10.00

Setting depth 1988.90

CASING TALLY 5 1/2", 170, W-80, LT&C - RUN 8/1/89

JOINT NUMBER	LENGTH	CUM.	JOINT NUMBER	LENGTH	CUM.	JOINT NUMBER	LENGTH	CUM.	JOINT NUMBER	LENGTH	CUM.	JOINT NUMBER	LENGTH	CUM.
SHOE	0.92	0.92												
1	14.45	15.37	26	42.15	1070.37	51	42.00	2092.32	76	42.30	3146.67	101	42.15	4196.62
2	42.30	57.67	27	42.05	1112.42	52	42.05	2134.37	77	41.80	3188.47	102	42.15	4232.77
3	42.20	99.87	28	42.15	1154.57	53	42.20	2176.57	78	41.95	3230.42	103	42.35	4275.12
4	42.15	142.02	29	42.15	1196.72	54	42.10	2218.67	79	42.20	3272.62	104	42.20	4317.32
5	42.35	184.37	30	42.20	1238.92	55	41.50	2260.17	80	42.15	3314.77	105	40.35	4357.67
6	42.15	226.52	31	42.15	1281.07	56	42.00	2302.17	81	42.40	3357.17	106	42.15	4399.82
7	42.20	268.72	32	42.20	1323.27	57	42.05	2344.22	82	42.20	3399.37	107	42.35	4442.17
8	42.30	311.02	33	42.15	1365.42	58	42.35	2386.57	83	41.90	3441.27	108	42.20	4484.37
9	42.25	353.27	34	42.20	1407.62	59	42.15	2428.72	84	42.35	3483.62	109	42.20	4526.57
10	42.40	395.67	35	42.15	1449.77	60	42.25	2470.97	85	41.95	3525.57	110	42.15	4568.72
11	42.30	437.97	36	42.10	1491.87	61	42.35	2513.32	86	42.35	3567.92	111	42.25	4610.97
12	42.25	480.22	37	42.15	1534.02	62	42.20	2555.52	87	34.10	3602.02	112	42.15	4653.12
13	42.25	522.47	38	42.15	1576.17	63	41.35	2596.87	88	42.20	3644.22	113	42.00	4695.12
14	42.10	564.57	39	42.15	1618.32	64	42.20	2639.07	89	42.20	3686.42	114	42.15	4737.27
15	42.25	606.82	40	41.75	1660.07	65	41.75	2680.82	90	42.20	3728.62	115	41.90	4779.17
16	42.25	649.07	41	42.15	1702.22	66	42.30	2723.12	91	42.20	3770.82	116	41.90	4821.07 out
17	42.05	691.12	42	42.15	1744.37	67	42.45	2765.57	92	42.15	3812.97	117	42.00	4863.07 out
18	42.15	733.27	43	14.60	1758.97	68	42.40	2807.97	93	42.20	3855.17	118	42.20	4905.27 out
19	42.05	775.32	44	42.15	1801.12	69	42.40	2850.37	94	42.20	3897.37	119	41.75	4947.02 out
20	42.05	817.37	45	42.10	1843.22	70	42.15	2892.52	95	42.30	3939.67	120		
21	42.10	859.47	46	42.10	1885.32	71	42.35	2934.87	96	42.20	3981.87	121		
22	42.30	901.77	47	42.15	1927.47	72	42.20	2977.07	97	42.20	4024.07	122		
23	42.20	943.97	48	42.05	1969.52	73	42.40	3019.47	98	40.10	4064.17	123		
24	42.10	986.07	49	42.15	2011.67	74	42.40	3061.87	99	42.15	4106.32	124		
25	42.15	1028.22	50	38.65	2050.32	75	42.50	3104.37	100	42.15	4148.47	125		
SUBTOT	1028.22		SUBTOT	1022.10		SUBTOT	1054.05		SUBTOT	1044.10		SUBTOT	798.55	
TOTAL	4947.02													
Total length		4947.02												
4 joints out		167.85												
Landed below KB		8.00												
Setting depth		4787.17												

Appendix C

DRILL PIPE TALLIES

DRILL PIPE TALLY LOGGING RUN #6 7/31/89

STAND NUMBER	LENGTH	CUM.	STAND NUMBER	LENGTH	CUM.	STAND NUMBER	LENGTH	CUM.	STAND NUMBER	LENGTH	CUM.
0		4848.41									
1	62.35	4786.06	26	61.60	3249.81	51	61.90	1698.61	76	62.35	151.66
2	61.60	4724.46	27	61.65	3188.16	52	61.95	1636.66	77	62.50	89.16
3	60.40	4664.06	28	61.85	3126.31	53	60.20	1576.46	78		
4	62.05	4602.01	29	59.95	3066.36	54	61.90	1514.56	79		
5	60.45	4541.56	30	62.70	3003.66	55	61.80	1452.76	80		
6	61.65	4479.91	31	61.30	2942.36	56	63.50	1389.26	81		
7	62.05	4417.86	32	63.15	2879.21	57	62.90	1326.36	82		
	60.50	4357.36	SE SUB	6.50	2872.71	58	61.70	1264.66	83		
9	61.40	4295.96	33	61.95	2810.76	59	62.25	1202.41	84		
10	60.50	4235.46	34	61.65	2749.11	60	61.55	1140.86	85		
11	61.05	4174.41	35	61.70	2687.41	61	62.55	1078.31	86		
12	62.35	4112.06	36	62.75	2624.66	62	62.05	1016.26	87		
13	62.55	4049.51	37	61.65	2563.01	63	60.25	956.01	88		
14	62.35	3987.16	38	60.95	2502.06	64	61.50	894.51	89		
15	61.90	3925.26	39	63.20	2438.86	65	61.15	833.36	90		
16	61.50	3863.76	40	61.80	2377.06	66	61.80	771.56	91		
17	61.85	3801.91	41	63.10	2313.96	67	62.85	708.71	92		
18	62.70	3739.21	42	60.55	2253.41	68	60.95	647.76	93		
19	61.35	3677.86	43	59.60	2193.81	69	62.40	585.36	94		
20	61.30	3616.56	44	62.30	2131.51	70	62.30	523.06	95		
21	61.95	3554.61	45	62.00	2069.51	71	62.20	460.86	96		
22	61.30	3493.31	46	62.40	2007.11	72	61.35	399.51	97		
23	59.50	3433.81	47	62.10	1945.01	73	61.55	337.96	98		
24	61.50	3372.31	48	60.20	1884.81	74	61.90	276.06	99		
25	60.90	3311.41	49	61.55	1823.26	75	62.05	214.01	100		
			50	62.75	1760.51						
SUBTOT	1537.00		SUBTOT	1550.90		SUBTOT	1546.50		SUBTOT	124.85	
TOTAL		4759.25									
LOGGING TOOLS		89.16									
TOTAL		4848.41									

DRILL PIPE TALLY - LOGGING RUN #7 7/31/89

STAND NUMBER	LENGTH	CUM.	STAND NUMBER	LENGTH	CUM.	STAND NUMBER	LENGTH	CUM.	STAND NUMBER	LENGTH	CUM.
0		4752.75									
1	62.35	4690.40	26	61.60	3154.15	51	61.90	1609.45	76	62.35	62.50
2	61.60	4628.80	27	61.65	3092.50	52	61.95	1547.50	77	62.50	0.00
3	60.40	4568.40	28	61.85	3030.65	53	60.20	1487.30	78		
4	62.05	4506.35	29	59.95	2970.70	54	61.90	1425.40	79		
5	60.45	4445.90	30	62.70	2908.00	55	61.80	1363.60	80		
6	61.65	4384.25	31	61.30	2846.70	56	63.50	1300.10	81		
7	62.05	4322.20	32	63.15	2783.55	57	62.90	1237.20	82		
8	60.50	4261.70	SE SUB	0.00	2783.55	58	61.70	1175.50	83		
9	61.40	4200.30	33	61.95	2721.60	59	62.25	1113.25	84		
10	60.50	4139.80	34	61.65	2659.95	60	61.55	1051.70	85		
11	61.05	4078.75	35	61.70	2598.25	61	62.55	989.15	86		
12	62.35	4016.40	36	62.75	2535.50	62	62.05	927.10	87		
13	62.55	3953.85	37	61.65	2473.85	63	60.25	866.85	88		
14	62.35	3891.50	38	60.95	2412.90	64	61.50	805.35	89		
15	61.90	3829.60	39	63.20	2349.70	65	61.15	744.20	90		
16	61.50	3768.10	40	61.80	2287.90	66	61.80	682.40	91		
17	61.85	3706.25	41	63.10	2224.80	67	62.85	619.55	92		
18	62.70	3643.55	42	60.55	2164.25	68	60.95	558.60	93		
19	61.35	3582.20	43	59.60	2104.65	69	62.40	496.20	94		
20	61.30	3520.90	44	62.30	2042.35	70	62.30	433.90	95		
21	61.95	3458.95	45	62.00	1980.35	71	62.20	371.70	96		
22	61.30	3397.65	46	62.40	1917.95	72	61.35	310.35	97		
23	59.50	3338.15	47	62.10	1855.85	73	61.55	248.80	98		
24	61.50	3276.65	48	60.20	1795.65	74	61.90	186.90	99		
25	60.90	3215.75	49	61.55	1734.10	75	62.05	124.85	100		
			50	62.75	1671.35						
SUBTOT	1537.00		SUBTOT	1544.40		SUBTOT	1546.50		SUBTOT	124.85	
TOTAL		4752.75									
LOGGING TOOLS		0.00									
TOTAL		4752.75									

DRILL PIPE TALLY - LOGGING RUN #8 8/1/89

STAND NUMBER	LENGTH	CUM.	STAND NUMBER	LENGTH	CUM.	STAND NUMBER	LENGTH	CUM.	STAND NUMBER	LENGTH	CUM.
1	62.50	62.50	26	61.95	1609.45	51	61.65	3160.65	76	61.60	4696.90
2	62.35	124.85	27	61.90	1671.35	52	61.60	3222.25	77	62.35	4759.25
3	62.05	186.90	28	62.75	1734.10	53	60.90	3283.15	78		
4	61.90	248.80	29	61.55	1795.65	54	61.50	3344.65	79		
5	61.55	310.35	30	60.20	1855.85	55	59.50	3404.15	80		
6	61.35	371.70	31	62.10	1917.95	56	61.30	3465.45	81		
7	62.20	433.90	32	62.40	1980.35	57	61.95	3527.40	82		
8	62.30	496.20	33	62.00	2042.35	58	61.30	3588.70	83		
9	62.40	558.60	34	62.30	2104.65	59	61.35	3650.05	84		
10	60.95	619.55	35	59.60	2164.25	60	62.70	3712.75	85		
11	62.85	682.40	36	60.55	2224.80	61	61.85	3774.60	86		
12	61.80	744.20	37	63.10	2287.90	62	61.50	3836.10	87		
13	61.15	805.35	38	61.80	2349.70	63	61.90	3898.00	88		
14	61.50	866.85	39	63.20	2412.90	64	62.35	3960.35	89		
15	60.25	927.10	40	60.95	2473.85	65	62.55	4022.90	90		
16	62.05	989.15	41	61.65	2535.50	66	62.35	4085.25	91		
17	62.55	1051.70	42	62.75	2598.25	67	61.05	4146.30	92		
18	61.55	1113.25	43	61.70	2659.95	68	60.50	4206.80	93		
19	62.25	1175.50	44	61.65	2721.60	69	61.40	4268.20	94		
20	61.70	1237.20	45	61.95	2783.55	70	60.50	4328.70	95		
21	62.90	1300.10	46	63.15	2846.70	71	62.05	4390.75	96		
22	63.50	1363.60	SE SUB	6.50	2853.20	72	61.65	4452.40	97		
23	61.80	1425.40	47	61.30	2914.50	73	60.45	4512.85	98		
24	61.90	1487.30	48	62.70	2977.20	74	62.05	4574.90	99		
25	60.20	1547.50	49	59.95	3037.15	75	60.40	4635.30	100		
			50	61.85	3099.00						
SUBTOT	1547.50		SUBTOT	1551.50		SUBTOT	1536.30		SUBTOT	123.95	
TOTAL		4759.25									
LOGGING TOOLS		0.00									
TOTAL		4759.25									

LOGGED FROM TOP DOWN WITH VIDEO CAMERA

Appendix D

MOTOR PERFORMANCE AND BOTTOM HOLE ASSEMBLIES

The first motor to be run was the Eastman double bend, Mach I with two stabilizers. The motor drilled from 2150' to 2362' (212') in 20 hours and was pulled because of low penetration rate. The average penetration rate was 10.6 ft/hr with a low of 3 ft/hr and a high of 20 ft/hr. Originally, it was thought that there was a problem with the motor or the bit, but the low penetration rate was caused by siltstone stringers in the formation.

For a period of time, the Eastman motor was run at 1600 scfm with 25 barrels per hour (BPH) of mist. The rig's mist pump was not capable of pumping less than 25 BPH at the required pressure. The standpipe pressure while pumping 25 BPH was approximately 800 psi. A replacement pump was rigged up and the mist rate dropped to 10 BPH. The standpipe pressure fell to approximately 600 psi with the same air volume.

The equivalent flow rate through the motor while drilling was 340 gallons per minute. There were no problems running the motor and Eastman indicated that no repairs were necessary. The motor was functioning properly when pulled.

The averaged dogleg severity generated by the Eastman motor was 10.5°/100'. The system was designed to build at 8.6°/100'. Because of the higher than anticipated build rate, the Baker motor was run next.

The Baker bent housing motor had the bend in the motor set at 2 degrees. The motor drilled from 2362' to 2548' (186') in 19 hours and was pulled because of low penetration rate. The average penetration rate was 9.8 ft/hr with a low of 2 ft/hr and a high of 20 ft/hr. Again, the low penetration rate was due to formation effects.

The motor was run with a little over 1600 scfm and 10 BPH of mist. The equivalent flow rate through the motor was calculated to be 346 gpm. No problems were experienced in running the motor and the motor was still functioning properly when it was pulled. The Baker bent housing motor created an average dogleg severity of 9.5°/100'. A longer tangent section was planned to compensate for the higher build rate.

The third motor run was made with the same Baker bent housing motor with the bend set at 2 degrees. The motor drilled from 2811' to 3165' (354') in 19.5 hours. The average penetration rate was 18.2 ft/hr. There was only one short section that drilled at less than 3 ft/hr. The rest of the motor run drilled at approximately 20 ft/hr. The motor was pulled because the build section had been completed. There were no problems running the motor and the motor was functioning properly when pulled.

The fourth motor run was made to make a direction change in the slant section of the hole. Again, the same Baker motor was run with the bend set at 2 degrees. The motor drilled from 3785' to 3855' (70') in four hours. The average penetration rate was 17.5 ft/hr. The motor was pulled because the hole had unexpectedly started dropping inclination. The flow rate through the motor was 1400 scfm and 15 BPH of mist. The mist rate had been increased to aid in hole cleaning. The standpipe pressure was 470 psi and the equivalent flow rate through the motor was 305 gpm.

No problems were encountered in running either the Eastman or the Baker motors. The motors started shortly after the air was turned into the drill pipe even after

connections. The motors did stall several times but it was due to excess weight being placed on the motor. A maximum weight of 12,000 lbs was run on the motors while drilling the harder siltstones at less than four feet per hour. The maximum weight that could be run on the motors while drilling shale at 20 ft/hr was approximately 6,000 lbs before the motor would stall.

Neither the Baker motor nor the Eastman motor showed any excessive wear when torn down and inspected. The Eastman motor drilled for 20 hours and the Baker motor drilled for a total of 42.5 hours in three runs. The Baker motor also had an additional 11.25 hours circulating off bottom to clean the hole. Most of that time (8.75 hours) was at the end of the last run in the slant section. Total hours (circulating and drilling) on the Baker motor was 53.75 hours.

Running the motors on high pressure air definitely increased motor life. No motor failures were experienced even circulating for long periods of time off bottom. No rig time was spent tripping failed motors or trying to restart a motor after a connection. The savings in rig time more than offset the additional cost associated with renting the high pressure air package.

One directional, rotary assembly was used to drill the Boggs #1240. The assembly consisted of a bit, float sub, six point reamer, and two nonmagnetic drill collars. The float sub was run below the six point on BHA number 4 and 9, and above the six point on BHA number 6 and 7. Other than that, the bottomhole assemblies were the same. Each assembly is listed in **Appendix E**.

The tangent section was drilled with the bottomhole assembly that was planned to be used in the slant section. The intention was to collect data that could be used to fine tune the assembly for the slant section and to compensate for bit walk.

Bottomhole assembly number four drilled the tangent section from 2548' to 2811' (263'). The average penetration rate was 45.7 ft/hr with 25,000 lbs of bit weight and 80 rpm. The assembly built $1.34^{\circ}/100'$ and walked $0.30^{\circ}/100'$ to the right as calculated from the surveys between 2553' and 2799'.

The planned build rate in the slant section was $0.5^{\circ}/100'$. It was assumed that the assembly would build slower at the higher inclinations in the slant section but not as slow as $0.5^{\circ}/100'$. Therefore, the float sub was also moved to the top of the six point to reduce the building tendency.

The Eastman "Predict" program indicated that assembly would still build inclination at approximately $0.75^{\circ}/100'$. To compensate for the higher build rate, the build section was stopped at 68° instead of the planned 71° .

Bottomhole assembly number six twisted off while reaming the motor-drilled hole. Bottomhole assembly number seven (with the float sub above the six point) drilled from 3165' to 3785' (620'). The average penetration rate was 33.5 ft/hr with 20,000 lbs bit weight and 70 rpm. The assembly was pulled because it was walking to the left and the well would have ended up too close to the lease line. A motor was run to turn the well back to the right.

The rotary assembly built inclination at a rate of $0.85^{\circ}/100'$ and walked $1.00^{\circ}/100'$ to the left. The build rate was close to the predicted value; however, the bit walked in the opposite direction of that predicted in the tangent section.

Bottomhole assembly number nine was run after the motor run. The motor had unexpectedly dropped inclination so the float sub was placed below the six point to increase build tendency. The assembly drilled from 3855' to 4833' (978'). The average penetration rate was 29.0 ft/hr with 20,000 lbs bit weight and 60-70 rpm.

The assembly built inclination at a rate of $0.45^{\circ}/100'$ and walked $0.89^{\circ}/100'$ to the left. Apparently, the float sub below the bit actually slowed the build rate. Build and walk rates for each assembly can be found in Appendix F.

Appendix E

BOTTOM HOLE ASSEMBLY DATA

BHA #1	7/16/89	LENGTH	DEPTH IN	DEPTH OUT
BIT		1.00		
FLOAT SUB		1.15	2010'	2150'
MONEL		27.50		
MONEL		29.45		
CROSS OVER		1.35		
DRILL COLLAR		59.65		
DRILL COLLAR		58.75		
DRILL COLLAR		58.10		
DRILL COLLAR		59.20		
DRILL COLLAR		59.25		
DRILL COLLAR		60.10		
DRILL COLLAR		60.00		
CROSS OVER		1.00		
TOTAL		476.50		

BHA #2	7/17/89	LENGTH	DEPTH IN	DEPTH OUT
BIT (F-4) 13-13-B		1.00		
EASTMAN MOTOR		29.23	2150'	2362'
CROSS OVER		0.80		
CROSS OVER		1.20		
FLOAT SUB		1.15		
UBHO SUB		2.30		
CROSS OVER		1.55		
MONEL		27.50		
MONEL		29.45		
CROSS OVER		1.35		
DRILL COLLAR		58.75		
DRILL COLLAR		58.10		
DRILL COLLAR		59.20		
DRILL COLLAR		59.25		
DRILL COLLAR		28.80		
CROSS OVER		1.50		
TOTAL		361.13		

BHA #3	7/18/89	LENGTH	DEPTH IN	DEPTH OUT
BIT (F-4) 13-13-B		1.00		
2 DEG BH MOTOR		23.15	2362'	2548'
FLOAT SUB		1.15		
UBHO SUB		2.30		
CROSS OVER		1.55		
MONEL		27.50		
MONEL		29.45		
CROSS OVER		1.35		
DRILL COLLAR		58.75		
DRILL COLLAR		58.10		
DRILL COLLAR		59.20		
DRILL COLLAR		59.25		
DRILL COLLAR		28.80		
CROSS OVER		1.50		
TOTAL		353.05		

BHA #4	7/19/89	LENGTH	DEPTH IN	DEPTH OUT
BIT (4GA)		1.00		
FLOAT SUB		1.15	2548'	2811'
6 POINT REAMER		9.02		
MONEL		27.50		
MONEL		29.45		
CROSS OVER		1.35		
DRILL COLLAR		58.75		
DRILL COLLAR		58.10		
DRILL COLLAR		59.20		
DRILL COLLAR		59.25		
DRILL COLLAR		28.80		
CROSS OVER		1.50		
TOTAL		335.07		

BHA #5	7/21/89	LENGTH	DEPTH IN	DEPTH OUT
BIT (F-4) 13-13-B		1.00		
2 DEG BH MOTOR		23.15	2811'	3165'
FLOAT SUB		1.15		
UBHO SUB		2.30		
CROSS OVER		1.55		
MONEL		27.50		
MONEL		29.45		
CROSS OVER		1.35		
DRILL COLLAR		29.05		
CROSS OVER		1.50		
TOTAL		118.00		

BHA #6	7/22/89	LENGTH	DEPTH IN	DEPTH OUT
BIT (4GA)		1.00		
6 POINT REAMER		9.02		
FLOAT SUB		1.15		
MONEL		27.50		
MONEL		29.45		
CROSS OVER		1.35		
DRILL COLLAR		29.05		
CROSS OVER		1.50		
TOTAL		100.02		
TWISTED OFF				

BHA #7	7/23/89	LENGTH	DEPTH IN	DEPTH OUT
BIT (4GA)		1.00		
6 POINT REAMER		9.02		
FLOAT SUB		1.20		
MONEL		27.50		
MONEL		29.45		
CROSS OVER		1.35		
DRILL COLLAR		29.30		
CROSS OVER		1.50		
TOTAL		100.32		

BHA #8	7/25/89	LENGTH	DEPTH IN	DEPTH OUT
BIT (F-4) 13-13-B		1.00		
2 DEG BH MOTOR		23.15		
FLOAT SUB		1.20		
UBHO SUB		2.30		
CROSS OVER		1.55		
MONEL		27.50		
MONEL		29.45		
CROSS OVER		1.35		
DRILL COLLAR		29.30		
CROSS OVER		1.50		
TOTAL		118.30		

BHA #9	7/26/89	LENGTH	DEPTH IN	DEPTH OUT
BIT (F-4)		1.00		
FLOAT SUB		2.00		
6 POINT REAMER		9.02		
MONEL		27.50		
MONEL		29.45		
CROSS OVER		1.35		
DRILL COLLAR		29.30		
CROSS OVER		1.50		
TOTAL		101.12		

Appendix F

BUILD AND WALK RATE DATA

STERLING DRILLING AND PROD.

BOGGS NO. 1240

BUILD AND WALK RATE

MEASURED DEPTH FEET	DRIFT ANGLE DEGREES	DRIFT AZIMUTH DEGREES	COURSE LENGTH FEET	BUILD RATE DEG/100	WALK RATE DEG/100	BOTTOMHOLE ASSEMBLY
0.00	0.00	60.00	0.00	0.00	0.00	
2097.00	1.00	60.00	2097.00	0.05	0.00	ROTARY
2128.00	1.30	104.75	31.00	0.97	144.35	ROTARY
2160.00	3.20	104.75	32.00	5.94	0.00	ROTARY AND EASTMAN MOTOR
2190.00	6.30	109.75	30.00	10.33	16.67	EASTMAN MOTOR
2220.00	9.80	109.75	30.00	11.67	0.00	EASTMAN MOTOR
2251.00	13.20	109.75	31.00	10.97	0.00	EASTMAN MOTOR
2282.00	16.30	113.75	31.00	10.00	12.90	EASTMAN MOTOR
2304.00	18.40	114.75	22.00	9.55	4.55	EASTMAN MOTOR
2348.00	22.70	117.75	44.00	9.77	6.82	EASTMAN MOTOR
2378.00	25.00	121.75	30.00	7.67	13.33	EASTMAN AND BAKER MOTOR
2411.00	27.30	126.75	33.00	6.97	15.15	BAKER MOTOR
2440.00	28.50	132.75	29.00	4.14	20.69	BAKER MOTOR
2471.00	30.90	134.75	31.00	7.74	6.45	BAKER MOTOR
2490.00	33.50	133.75	19.00	13.68	-5.26	BAKER MOTOR
2553.00	32.50	134.00	63.00	-1.59	0.40	BAKER MOTOR AND ROTARY
2615.00	32.75	133.00	62.00	0.40	-1.61	ROTARY
2677.00	33.75	133.00	62.00	1.61	0.00	ROTARY
2738.00	35.00	134.00	61.00	2.05	1.64	ROTARY
2799.00	35.80	134.75	61.00	1.31	1.23	ROTARY
2830.00	37.00	133.75	31.00	3.87	-3.23	ROTARY AND BAKER MOTOR
2861.00	39.80	134.75	31.00	9.03	3.23	BAKER MOTOR
2890.00	42.00	133.75	29.00	7.59	-3.45	BAKER MOTOR
2921.00	44.80	133.75	31.00	9.03	0.00	BAKER MOTOR
2950.00	47.40	132.75	29.00	8.97	-3.45	BAKER MOTOR
3012.00	53.00	130.75	62.00	9.03	-3.23	BAKER MOTOR
3074.00	58.90	132.00	62.00	9.52	2.02	BAKER MOTOR
3187.00	67.25	132.00	113.00	7.39	0.00	BAKER MOTOR AND ROTARY
3249.00	68.00	132.00	62.00	1.21	0.00	ROTARY
3310.00	68.50	132.00	61.00	0.82	0.00	ROTARY
3497.00	70.00	130.00	187.00	0.80	-1.07	ROTARY
3620.00	71.50	128.00	123.00	1.22	-1.63	ROTARY
3744.00	72.00	127.00	124.00	0.40	-0.81	ROTARY
3751.00	72.20	127.00	7.00	2.86	0.00	ROTARY
3804.00	69.40	129.00	53.00	-5.28	3.77	ROTARY AND BAKER MOTOR
3897.00	65.25	132.00	93.00	-4.46	3.23	ROTARY AND BAKER MOTOR
4117.00	66.25	130.00	220.00	0.45	-0.91	ROTARY
4321.00	67.25	128.00	204.00	0.49	-0.98	ROTARY
4544.00	68.25	127.00	223.00	0.45	-0.45	ROTARY
4789.00	69.25	124.00	245.00	0.41	-1.22	ROTARY
4833.00	69.25	124.00	44.00	0.00	0.00	ROTARY

Appendix G
HOLE CLEANING

Hole cleaning was the primary problem in drilling the Boggs #1240. It was expected that cleaning would be a problem while misting with the motors at high inclinations. When dry air was used, cleaning was generally not a problem. To alleviate hole cleaning problems, the well was drilled with dry air as much as possible; however, it is not possible to drill with motors on dry air. Instead, a stiff foam was used to aid in hole cleaning. The recommended foam mixture and the mud (foam) reports can be found in Appendix H.

Initially, the foam was pumped at a rate of 10 BPH and no hole cleaning problems were noted until the end of the third motor run at 3,165'. There were no problems while drilling, but there were problems pulling the pipe out of the hole during a trip. A total of 4.75 hours were spent circulating and pulling pipe until it came free. The inclination at the end of the build section was 67°. The pipe came free above an inclination of 45°. The measured air rate while drilling with the downhole motor was 1,768 scfm at 520 psi. The foam was injected at a rate of 9 BPH.

At the end of the build section, the hole was dried out and dusted to the next motor run. The air rate while drilling was 1,539 scfm at 100 psi. No cleaning problems were noted with dry air; however, there was 130 feet of fill on bottom on the next trip in the hole.

The next motor run was made at 3,785' and the inclination was 72°. Again, there were problems pulling the motor out of the hole after drilling only 70'. The hole became tight after pulling only two stands of pipe (124'). A total of 7.5 hours were spent circulating to clean the hole and pulling pipe while circulating. The air rate for this motor run was 1,400 scfm and the foam rate was 15 BPH. The foam rate had been increased to aid in hole cleaning.

After the motor was pulled, the rotary assembly was run back in the hole. This time it was difficult to dry the well out. A total of 24 hours were spent trying to clean the well with foam and then dry it out. The daily reports dated 7/27/89 and 7/28/89 detail the efforts. Increasing the air rate to 2,300 scfm finally dried the well out and drilling continued to TD.

In order to achieve the 2300 scfm, the compressor system plumbing had to be changed. The single stage booster could not handle more than 1,500 scfm with four 750's as the primary. The air system was switched so that the four 750's were sent through the two stage booster and a 1,050 was sent through the single stage booster. This configuration produced only 1,750 scfm. The two stage booster would not pump any more than 800 scfm as a two stage or with the valves open as a single stage. The primaries were again switched to where the four 750's were sent to the single stage and the 1,050 was sent to the two stage. The result was 2,300 scfm of air. Without orifice meters on both the inlet and outlet of the boosters, it would not have been possible to determine how to rig up the compressors to get the maximum air rate. In all cases, there was 4,050 scfm worth of rated air entering the boosters. The efficiency of each booster made a significant difference in actual air rates.

The 2,300 scfm was still a minimum required to clean the slant section of the well. Though no problems were encountered while drilling, the TV camera showed there was still a significant amount of dust in the well.

The total foam mixed and pumped was 1,375 barrels at a total cost of \$16,523. The foam cost \$12.02 per barrel including mixing costs and transportation. All indications are that the stiff foam accomplished very little over using a simple mist. The obvious solution to the hole cleaning problem with mist is to use higher air volumes. Unfortunately, higher air volumes will be detrimental to the life of downhole motors unless a partial bypass can be devised. The higher volumes required at high pressure would also require more than one two stage booster; a significant additional cost.

Hole cleaning is a problem because of the additional time required (and therefore cost) and the possibility of sticking the drill string. To prevent the latter, additional float valves were placed in the drill string. A hammer float was placed on top of the bit with rotary and downhole motor assemblies. A second float valve was placed in the float sub. With motor runs, a third float was placed above the side entry sub to keep the drill string exhausting through the motor during connections.

As experienced previously in the RET #1 well, sticking the drill string was possible when the pipe became plugged. As long as the pipe could be circulated, it could always be pulled from the hole. The additional float valves in the Boggs #1240 were used to prevent any possible plugging of the pipe. There was no indication that the drill string even started to plug; therefore, the extra float valves worked as desired.

Appendix H
DRILLING MUD REPORTS (FOAM DATA)

Magcohar/Dresser Drilling Mud Report #1
Magcohar Engineer Bill Orrison

Date 7/15/89
Spud date 7/10/89
Depth 2010
Present Activity WOC
Operator Sterling Drlg & Prod. Co.
Drilling Contractor Exeter

Rig # 53
Well Name and Boggs 1240
Field or Block N Newton
Cty, Par, Offsho Roane
State or Provinc WV
Mud Type mud mist

Products	#1	#2
Soda Ash	2	1
Poly Pac	2	1
MI Gel	13	6
Potassium	47	21

Remarks	
Air	2200
Batch #1	foam mix 225 BBLs
Batch #2	foam mix 125 BBLs

Daily Cost \$2,195.20

Mud Properties	#1	#2
Sample from	pit	pit
Time sample taken	3:15 PM	6:30 PM
Depth	2010	2010
Weight (ppg)	8.6	8.6
Funnel visc. (sec/qt)	32	32
Plastic visc. (cP)	3	3
Yield Pt. (lb/100sq ft)	2	2
Gel Strength (lb/100sq ft)	111	111
Filtrate API (cubic cm/30 min)	12.8	10.8
API HTHP Filtrate (cubic cm/30 min)	N/A	N/A
cake thkns (32nd in. API/HTHP)	film	film
Solids Content (CALCD)	1%	1%
Liquid (%water by volume)	99%	Nil
Sand content (% by volume)	Nil	10.0
PH (strip)	10.0	N/A
Alkalinity mud (Pm)	N/A	1
Alkalinity filtrate (Pf/Mf)	1	1
Alternate Alkalinity (P1/P2)	18,000	19,000
Chloride (mg/L)	60	40
Total Hardness as Calcium (mg/L) (K)	15750	15750

Magcobar/Dresser Drilling Mud Report #2
Magcobar Engineer Bill Orrison

Date 7/17/89 **Rig #** 53
Spud date 7/10/89 **Well Name and No.** Boggs 1240
Depth 2010 **Field or Block No.** Newton
Present Activity Drlg. **Cty, Par, Offshore** Roane
Operator Sterling Drlg & Prod. Co. **State or Province** WV
Drilling Contractor Exeter **Mud Type** mud mist

	Batch	
	#3	#4
Mud Properties		
Sample from	PIT	PIT
Time sample taken	7:30p.m.	9:30 p.m.
Depth	2276	2284
Weight (ppg)	8.6	8.6
Funnel visc. (sec/qt)	32	32
Plastic visc. (cP)	3	3
Yield Pt. (lb/100sq ft)	2	2
Gel Strength (lb/100sq ft)	1/1	1/1
Filtrate API (cubic cm/30 min)	14.6	14.4
API HTHP Filtrate (cubic cm/30 min)	N/A	N/A
cake thkns (32nd in. API/HTHP)	Film	Film
Solids Content (CALCD)	2%	2%
Liquid (%water by volume)	198	198
Sand content (% by volume)	Nil	Nil
PH (strip)	10.0	10.0
Alkalinity mud (Pm)	N/A	N/A
Alkalinity filtrate (Pf/Mf)	1	1
Alternate Alkalinity (P1/P2)	1	1
Chloride (mg/L)	20,000	21,000
Total Hardness as Calcium (mg/L)	40	40
(K)	15750	16000

Products

Soda Ash	2	2
Poly Pac	2	2
MI Gel	13	13
Potassium	47	47

Remarks

Foam Height - 475
Stability - 2.30'
Quality - .82 - .86

Daily Cost \$2,966.90

Magcobar/Dresser Drilling Mud Report #3
Magcobar Engineer Bill Orrison

Date 7/18/89
Spud date 7/10/89
Depth 2375
Present Activity Drlg
Operator Sterling Drlg & Prod. Co.
Drilling Contractor Exeter

Rig # 53
Well Name and No. Boggs 1240
Field or Block No. Newton
Cty, Par, Offshore Roane
State or Province WV
Mud Type Stable Foam

Mud Properties		Batch
		Foam

Sample from		
Time sample taken	9:50p.m.	
Depth	2375	

Weight (ppg)	
Funnel visc. (sec/qt)	
Plastic visc. (cP)	
Yield Pt. (lb/100sq ft)	
Gel Strength (lb/100sq ft)	
Filtrate API (cubic cm/30 min)	
API HTHP Filtrate (cubic cm/30 min)	
cake thkns (32nd in. API/HTHP)	
Solids Content (CALCD)	
Liquid (%water by volume)	
Sand content (% by volume)	
PH (strip)	9.5
Alkalinity mud (Pm)	
Alkalinity filtrate (Pf/Mf)	
Alternate Alkalinity (PI/P2)	
Chloride (mg/L)	20,000
Total Hardness as Calcium (mg/L)	40
(K)	15750

Products	Batch
----------	-------

Air Foam	4
----------	---

Remarks

Try to control Injection rate at 10-12 bbls per hour
 Foam HT - 450 cc
 Stability - 2.20 sec
 Quality - .81

Daily Cost \$1,897.00

Magcobar/Dresser Drilling Mud Report #4
Magcobar Engineer Bill Orrison

Date 7/19/89 **Rig #** 53
Spud date 7/10/89 **Well Name and No.** Boggs 1240
Depth 2520 **Field or Block No.** Newton
Present Activity Drlg **Cty, Par, Offshore Area** Roane
Operator Sterling Drlg & Prod. Co. **State or Province** WV
Drilling Contractor Exeter **Mud Type** Stable Foam

	Batch	
	#5	#6
Mud Properties		
Sample from		
Time sample taken	12:00 p.m	2:20 p.m.
Depth	2520	
Weight (ppg)	8.5	8.4
Funnel visc. (sec/qt)	32	32
Plastic visc. (cP)	3	3
Yield Pt. (lb/100sq ft)	2	2
Gel Strength (lb/100sq ft)	1/1	1/1
Filtrate API (cubic cm/30 min)	11.8	12.0
API HTHP Filtrate (cubic cm/30 min)	N/A	N/A
cake thkns (32nd in. API/HTHP)	Film	Film
Solids Content (CALCD)	2%	2%
Liquid (%water by volume)	98	98
Sand content (% by volume)	Nil	Nil
PH (strip)	10.5	10.0
Alkalinity mud (Pm)	N/A	N/A
Alkalinity filtrate (Pf/Mf)	1	1
Alternate Alkalinity (P1/P2)	1	1
Chloride (mg/L)	18,000	20,000
Total Hardness as Calcium (mg/L)	40	40
(K)	115750	15870

	Batch	
	#5	#6
Products		
Soda Ash		
Poly Pac	2.5	1.5
MI Gel	13	7
Potassium	47	23
Air Foam B		1

Remarks

Batch #5 - 225
Batch #6 - 125
Try to control Injection rate at 9 -12 bbls per hour
Foam HT - 475 - NI
Stability - 2'20 Sec
Quality - .82

Daily Cost \$2,770.50

Magcobar/Dresser Drilling Mud Report #5
Magcobar Engineer Bill Orrison

Date 7/25/89 **Rig #** 53
Spud date 7/10/89 **Well Name and No.** Boggs 1240
Depth 3785 **Field or Block No.** Newton
Present Activity Trip **Cty, Par, Offshore Area** Roane
Operator Sterling Drlg & Prod. Co. **State or Province** WV
Drilling Contractor Exeter **Mud Type** Stable Foam

Mud Properties **Batch #7**

Sample from 10:30 a.m.
Time sample taken 3785
Depth 8.5
Weight (ppg) 32
Funnel visc. (sec/qt) 3
Plastic visc. (cP) 2
Yield Pt. (lb/100sq ft) 1/1
Gel Strength (lb/100sq ft) 12.8
Filtrate API (cubic cm/30 min) N/A
API HTHP Filtrate (cubic cm/30 min) Film
cake thkns (32nd in. API/HTHP) 2%
Solids Content (CALCD) 98
Liquid (%water by volume) Nil
Sand content (% by volume) 10.5
PH (strip) N/A
Alkalinity mud (Pm) 1
Alkalinity filtrate (Pf/Mf) 1
Alternate Alkalinity (P1/P2) 20,000
Chloride (mg/L) 40
Total Hardness as Calcium (mg/L) 115750
(K)

Products **Batch #7**

Soda Ash 2
Poly Pac 2
MI Gel 13
Potassium 47
Air Foam B 5

Remarks

Batch #7 - 225 bbls
Injecting 14.5 bbls per hour
Foam Height - 475 ml
Stability - 2.30 sec
Quality - .82

Daily Cost \$3,655.70

Appendix I
PRESSURE BUILD-UP ANALYSIS

S. A. Holditch & Associates, Inc.
PETROLEUM ENGINEERING CONSULTANTS

900 SOUTHWEST PARKWAY EAST, SUITE 200
COLLEGE STATION, TEXAS 77840
(409) 764-1122
TWX 510 892 7324

July 13, 1990

Mr. David Hill
Gas Research Institute
8600 West Bryn Mawr
Chicago, Illinois 60631

Re: Pressure Buildup Analysis
Boggs Well No. 1240
Roane County, WV
Test Date: December 18, 1989 to January 2, 1990
Perforated Interval: 4,618 to 4,624 ft (MD)

Dear David:

Please find attached a final analysis of the pressure buildup test conducted on the Boggs Well No. 1240 from December 18, 1989 to January 2, 1990. In a letter dated January 26, 1990, we issued a preliminary analysis of this data along with our recommendations for stimulation. After looking at the data more closely, our analysis and conclusions really didn't change.

Essentially, the perforated interval from 4,618 to 4,624 ft has a permeability-thickness product of 0.2 md-ft. If we assume a formation height of 26 ft is contributing to production, the calculated average permeability is 0.0076 md with an apparent skin factor of -2.1. This indicates the 386 Mscf nitrogen breakdown treatment did stimulate the well, allowing the wellbore to be in good communication with the reservoir. Extrapolating the pressure data, we estimate the initial reservoir pressure was 981 psia.

In February 1990, this interval was stimulated further with 1.3 MMscf of straight nitrogen. Whenever it becomes feasible, we would like to run another pressure buildup test on this interval to see the effects of the larger nitrogen treatment.

If you have any questions about this well or analysis, please call.

Sincerely,

A handwritten signature in black ink, appearing to read "John E. Jochen". The signature is fluid and cursive, with the first and last names being clearly legible.

John E. Jochen
Senior Petroleum Engineer, P.E.

JEJ/dd

cc: Attached Distribution List

**PRESSURE BUILDUP ANALYSIS
STERLING DRILLING & PRODUCTION COMPANY
BOGGS WELL NO. 1240
ROANE COUNTY, WV**

Date: December 18, 1989 to January 2, 1990
Perfs: 4,618 to 4,624 ft (MD)

Introduction

The Boggs Well No. 1240 is a slanted well with an average inclination through the Devonian Shale interval of approximately 70°. It was perforated on September 24, 1989 in a six foot interval from 4,618 to 4,624 ft (MD) or 3,494 to 3,496 ft (TVD) with four shots per foot. On September 28, 1989, the zone was treated with 368,000 scf of nitrogen and 500 gal of 7-1/2% HCl acid. Fig. 1 is a wellbore schematic containing pertinent information at the time the well was perforated. Testing began immediately with a series of flow/shut-in periods. During the final flow period, the well demonstrated the ability to maintain a rate of about 8 to 9 Mscf/D with about a half barrel of oil swabbed out each day. Following this last flow period, a final pressure buildup test was conducted from December 18, 1989 to January 2, 1990. The buildup test lasted 358.4 hours. The flowing bottomhole pressure at shut-in was 110 psia, and by the end of the buildup test, the bottomhole pressure had increased to 911 psia.

Post-Breakdown/Pre-Stimulation Well Test Analysis

S. A. Holditch & Associates, Inc. (SAH) has analyzed the pre-stimulation well test data on the Sterling Drilling & Production Boggs Well No. 1240. The purpose of our analysis was to determine reservoir properties such as permeability, skin, and initial reservoir pressure.

SAH analyzed the well test data provided to us by Reuben L. Graham, Inc. using conventional techniques (type curve and semi-log "Horner" analysis). We determined that the well did not produce long enough to get past the effects of wellbore storage; therefore, the correct semi-log straight line does not exist on the Horner plot. However, we were able to obtain a good match using type curves, and, therefore, we could determine permeability and skin. We then constructed a straight line on the semi-log plot through the last data point with a slope that would yield the same permeability as that determined from type curves. Extrapolating this straight line to an adjusted Horner time of 1 (i.e., infinite shut-in time), we estimated the initial reservoir pressure.

Fig. 2 shows the pressure buildup data plotted on a log-log scale and matched with the Gringarten *et al.* type curves. This match results in a permeability-thickness product, kh , of 0.197 md-ft. Assuming that 26 ft of net pay are contributing to production, the average permeability for this interval is 0.0076 md with a calculated apparent skin factor of -2.1. Fig. 3 shows the same pressure buildup data plotted on a semi-log scale. As can be seen from Fig. 3, it is not clear when the correct semi-log straight line begins, indicating the data is still being distorted by wellbore storage. The correct semi-log straight line is characteristic of the middle time region (MTR) on a Horner graph indicating the pressure transient has moved into the undamaged formation. Using the kh determined with type curves, a straight line was drawn on Fig. 3 and extrapolated to an adjusted Horner time of 1 resulting in an estimated initial reservoir pressure of 981 psia. A detailed printout of the well test data and analysis are attached at the end of this report.

In general, the pressure drop around the wellbore of a deviated well will be less than that of an equivalent vertical well because the deviated well has more wellbore exposed to the formation. In addition, a well that is not perforated across the entire producing formation (partially completed) will have a greater pressure drop near the wellbore than that of an equivalent fully completed well. Both of these situations exist in the Boggs Well No. 1240. Normally, the apparent skin factor should be corrected for the effects of inclination and partial completion; however, previous research in these areas generally concentrated on damaged formations with little attention to their effects on a stimulated formation.

Since the Boggs Well No. 1240 was broken-down with 368 Mscf of nitrogen, a relatively large treatment for the size of interval completed, the formation should not be damaged. In fact, it should be somewhat stimulated. Analysis of the pressure buildup test results in an apparent skin factor of -2.1, indicating stimulation. Since previous research did not study the effects of inclination and partial completion on apparent skin factor for a stimulated formation and it was not in the scope of this project to conduct such research, we did not correct the calculated apparent skin factor for the effects of a slanted, partially completed wellbore. Although it might have some effect, we do not believe the effect would change the overall conclusion that the formation was stimulated by the nitrogen breakdown treatment.

STERLING DRILLING & PRODUCTION COMPANY
BOGGS NO. 1240
ROANE COUNTY, WEST VIRGINIA

SPUD: 7-10-89
KICK OFF: 7-16-89
T.D.: 7-29-89
PERF: 9-24-89
BREAK-DOWN: 9-28-89 w/ 368 Mscf N₂
+ 500 gal 7½% HCl

Fig. 1 - Schematic of the Boggs No. 1240 illustrating conditions of the wellbore during initial tests from September 1989 to January 1990.

Fig. 2 - Type curve plot of the pre-fracture pressure buildup on the Boggs No. 1240.

Fig. 3 - Horner plot of the pre-fracture pressure buildup on the Boggs No. 1240.

WELL TEST ANALYSIS

Gas Well Analysis

Buildup Test

Test period preceded by one rate

Operator : Sterling Drilling & Production Company PBU26.DA
Well : Boggs No. 1240
Location : Roane County, West Virginia
Formation : Devonian Shale

Perforated Interval : 4618-4624 (MD) or 3487-3493 (TVD)

Analyst : jej

Test Date : 12/18/89 to 01/02/90

Remarks : adjusting producing time for variable producing rates
TOTAL INTERVAL = 26 ft (TVD) = 72 ft (MD)

RESERVOIR PARAMETERS

Net pay (ft)	26.00
Wellbore radius (ft)	.3500
Porosity (fraction)	.0410

Gas saturation (fraction)	.3200
Oil saturation (fraction)	.0000
Water saturation (fraction)	.6800
Formation compressibility (1/psi)	.0000071
Total compressibility (1/psi)	.0007028

RESERVOIR FLUID PROPERTIES

Bottom hole temperature (deg F)	100.00
Separator gas gravity	.6800
Mole percent hydrogen sulfide (%)	.0000
Mole percent carbon dioxide (%)	.0000
Mole percent nitrogen (%)	.0000
Gas-condensate ratio (scf/STB)	10000.0
Condensate gravity (Deg API)	40.00
Gas equivalent of condensate (scf/STB)	615.048
Wet gas specific gravity	.9970
Water compressibility (1/psi)	.0000026

PRODUCTION PARAMETERS

Input pressure at $t = 0$ (psig)	86.94
Initial drainage area pressure (psia)	1000.00
Corrected pressure at $t = 0$ (psia)	110.64
Adjusted initial drainage area pressure (psia)	901.47
Adjusted pressure at $t = 0$ (psia)	10.06

Pressure Corrections

Pressure bomb depth (ft)	3430.00
Mid-perforation depth (ft)	3490.00
Pressure datum depth (ft)	3490.00
Fluid gradient in wellbore (psi/ft)	.1500
Fluid gradient in reservoir (psi/ft)	.0000
Atmospheric pressure correction (psi)	14.70
Total pressure correction (psi)	23.70
Time correction (sec)	.0000

FLUID PROPERTIES AT AVERAGE PRESSURE

Average pressure (psia)	555.32
Gas viscosity (cp)	.01057
Total compressibility (1/psi)	.0007028
Z-Factor	.83779
Gas formation volume factor (RB/Mcf)	4.25367
Pressure adjustment factor (cp/psia)	.79710E-05
Time adjustment factor (cp/psia)	.74261E-05

SEMI-LOG ANALYSIS

Semi-log slope (psi/cycle)	-275.96
Permeability (md)	.0076
Permeability thickness, kh (md-ft)	.20
Skin factor	-2.117
Adjusted pressure at an adjusted time of one hour (psia)	75.60
Pressure at an adjusted Horner time ratio of one, p^* (psia)	980.57
Start of middle time region (hr)	584.825
Radius of investigation (ft)	
End of test	96.9
End of production	122.8
At pointer	96.9
Start of middle-time region	123.8

TYPE CURVE ANALYSIS - RADIAL FLOW WITH WELLBORE STORAGE AND SKIN

Log(CDe2s) curve	.8482
Permeability (md)	.0076
Permeability thickness, kh (md-ft)	.20
Dimensionless wellbore storage coefficient	486.60
Skin factor	-2.117
Start of middle time region (hr)	584.825
Radius of investigation (ft)	
End of test	96.9
End of production	122.8
At pointer	96.9
Start of middle-time region	123.8
MATCH POINT	
Dimensionless pressure	4.173
Dimensionless time	.1100
Adjusted Pressure Change (psi)	1000.
Equivalent Adjusted Time (hr)	1.000

RATE DATA

Input Rates		Calculated	
Cumulative Time (hr)	Gas Rate (Mscf/D)	Adjusted Cumulative Time (hr)	Gas Rate (Mscf/D)
-----	-----	-----	-----
1 450.00	7.0000	575.03	7.4305

TIME AND PRESSURE DATA

Time (hr)	Pressure (psia)	Equivalent Adjusted Time (hr)	Adjusted Pressure (psia)	Adjusted Pressure Change (psi)
-----	-----	-----	-----	-----
1 .30003E-02	110.88	.78398E-03	10.103	.45987E-01
2 .90003E-02	111.04	.23545E-02	10.135	.78143E-01
3 .15000E-01	111.28	.39277E-02	10.181	.12413
4 .21000E-01	111.49	.55040E-02	10.221	.16447
5 .27000E-01	111.72	.70834E-02	10.267	.20968
6 .33000E-01	111.93	.86657E-02	10.307	.25001
7 .39000E-01	112.10	.10251E-01	10.342	.28490
8 .45000E-01	112.32	.11838E-01	10.384	.32718
9 .51000E-01	112.51	.13429E-01	10.420	.36304
10 .57000E-01	112.73	.15022E-01	10.463	.40630
11 .63000E-01	112.90	.16618E-01	10.496	.43884
12 .69000E-01	113.12	.18216E-01	10.540	.48308
13 .75000E-01	113.27	.19817E-01	10.568	.51153
14 .87000E-01	113.73	.23027E-01	10.659	.60214

15	.99000E-01	114.09	.26249E-01	10.729	.67191
16	.11100	114.49	.29481E-01	10.806	.74869
17	.12300	114.93	.32724E-01	10.892	.83560
18	.13500	115.32	.35979E-01	10.968	.91101
19	.14700	115.71	.39244E-01	11.045	.98837
20	.16500	116.32	.44162E-01	11.162	1.1055
21	.18300	116.88	.49104E-01	11.273	1.2164
22	.20100	117.52	.54071E-01	11.398	1.3407
23	.21900	118.10	.59062E-01	11.511	1.4537
24	.24300	118.90	.65755E-01	11.666	1.6092
25	.26700	119.69	.72491E-01	11.820	1.7630
26	.29100	120.47	.79269E-01	11.972	1.9156
27	.32100	121.49	.87803E-01	12.181	2.1239
28	.35100	122.44	.96403E-01	12.382	2.3253
29	.38700	123.64	.10681	12.640	2.5829
30	.42300	124.81	.11716	12.890	2.8335
31	.46500	126.16	.12919	13.179	3.1219
32	.50700	127.49	.14133	13.463	3.4065
33	.55500	129.07	.15536	13.800	3.7430
34	.60300	130.63	.16955	14.134	4.0772
35	.65700	132.37	.18570	14.513	4.4564
36	.71700	134.28	.20388	14.957	4.9004
37	.78300	136.33	.22415	15.435	5.3780
38	.85500	138.65	.24660	15.975	5.9181
39	.93300	141.15	.27131	16.557	6.4998
40	1.0100	143.77	.29838	17.183	7.1257
41	1.1000	146.63	.32790	17.901	7.8444
42	1.2030	149.69	.35999	18.672	8.6150
43	1.3110	153.07	.39680	19.523	9.4664
44	1.4250	156.60	.43648	20.461	10.404
45	1.5510	160.52	.48131	21.526	11.469
46	1.6890	164.79	.53157	22.680	12.623
47	1.8390	169.42	.58757	24.022	13.965
48	2.0010	174.36	.64963	25.455	15.398
49	2.1750	179.66	.71809	27.063	17.006
50	2.3670	185.48	.79578	28.862	18.805
51	2.5710	191.60	.88076	30.844	20.787
52	2.7930	198.23	.97605	33.029	22.972
53	3.0330	205.33	1.0823	35.501	25.444
54	3.2970	213.05	1.2030	38.265	28.208
55	3.5850	221.42	1.3391	41.368	31.311
56	3.8970	230.42	1.4918	44.855	34.798
57	4.2330	239.94	1.6621	48.714	38.657
58	4.5990	250.23	1.8543	53.058	43.001
59	4.9950	261.15	2.0701	57.876	47.820
60	5.4270	272.84	2.3142	63.264	53.207
61	5.9160	285.75	2.6010	69.486	59.429
62	6.4260	298.99	2.9116	76.203	66.147
63	7.0040	313.53	3.2772	83.945	73.889
64	7.6160	328.52	3.6791	92.296	82.239
65	8.2960	344.74	4.1427	101.82	91.764
66	9.0100	361.39	4.6477	112.06	102.01
67	9.7920	379.06	5.2211	123.52	113.46
68	10.642	397.70	5.8673	136.21	126.15
69	11.560	417.07	6.5909	150.10	140.04
70	12.580	437.71	7.4243	165.72	155.66
71	13.668	458.64	8.3445	182.40	172.35
72	14.858	480.35	9.3838	200.60	190.55

73	16.150	502.43	10.547	220.05	209.99
74	17.544	524.37	11.836	240.32	230.26
75	19.074	546.79	13.283	261.94	251.88
76	20.740	569.22	14.890	284.48	274.42
77	22.542	591.23	16.659	307.48	297.42
78	24.480	610.53	18.589	328.41	318.35
79	26.588	627.92	20.713	347.84	337.78
80	28.900	645.57	23.064	368.18	358.12
81	31.382	662.85	25.607	388.67	378.61
82	34.102	679.70	28.413	409.21	399.15
83	37.026	695.59	31.444	429.08	419.03
84	40.222	710.64	34.765	448.40	438.34
85	43.690	724.89	38.373	467.06	457.00
86	47.464	738.24	42.294	484.93	474.88
87	51.545	750.07	46.522	501.09	491.03
88	55.965	761.44	51.078	516.87	506.81
89	60.793	772.17	56.021	532.01	521.96
90	66.029	781.83	61.331	545.82	535.76
91	71.707	790.48	67.019	558.33	548.27
92	77.861	798.68	73.099	570.33	560.27
93	84.559	806.69	79.613	582.16	572.11
94	91.835	814.25	86.569	593.41	583.35
95	100.01	822.77	94.231	606.25	596.19
96	108.69	830.26	102.20	617.64	607.58
97	118.04	838.10	110.59	629.65	619.59
98	128.40	843.66	119.65	638.25	628.19
99	139.42	850.24	129.03	648.50	638.44
100	151.51	856.61	139.03	658.48	648.43
101	164.54	862.79	149.45	668.27	658.21
102	178.90	868.23	160.55	676.91	666.85
103	194.34	874.16	172.05	686.42	676.36
104	211.04	879.90	184.01	695.65	685.59
105	229.41	885.22	196.61	704.29	694.24
106	249.35	890.43	209.68	712.78	702.72
107	270.73	895.28	223.02	720.75	710.69
108	294.18	900.45	236.93	729.27	719.21
109	319.56	904.99	251.17	736.81	726.75
110	347.02	909.72	265.70	744.68	734.63
111	358.38	911.32	271.46	747.36	737.30

END

**DATE
FILMED**

9 / 14 / 92