DOE/PC/89857--T2, 1, 1 h

DOE/PC/89857--T2

DE92 018514

**U.S. DEPARTMENT OF ENERGY
PITTSBURGH ENERGY TECHNOLOGY CENTER**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

**DIRECT COAL LIQUEFACTION
BASELINE DESIGN
AND
SYSTEM ANALYSIS**

CONTRACT NO. DEAC22 90PC89857

QUARTERLY REPORT

OCTOBER - DECEMBER

Received CSTI
JUL 24 1992

**MARCH, 1992
PITTSBURGH, PENNSYLVANIA**

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

TABLE OF CONTENTS

1. INTRODUCTION	1
2. SUMMARY	3
3. TECHNICAL PROGRESS (BY TASKS)	
3.1 TASK I	7
3.2 TASK II	8
3.2.1 Status Update	8
3.3 TASK III	16
3.3.1 Capital Cost Estimate	16
3.3.2 Coal Liquefaction Product Valuation Utilizing Process Industry Modeling Systems (PIMS) Software	16
3.4 TASK IV	23
3.4.1 Status of Task IV	23
3.4.1.1 Summary	25
3.4.1.2 Overview of Results	27
3.5 TASK V	28
3.6 TASK VI	29
4. KEY PERSONNEL STAFFING REPORT	30

LIST OF TABLES

<u>TABLE NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
3.2.1	Table of Contents, Task II Volume I	9
3.2.2	Table of Contents, Task II Volume II	13
3.3.1	PIMS Model Solution Summary Report	18
3.4.1	Table of Contents, Task IV	24
3.4.2	Task IV Description	26
4.1	Key Personnel Staffing Report	30

1. INTRODUCTION

Effective May 16, 1990, Bechtel with Amoco as subcontractor, initiated a study to develop a computer model for a base line direct coal liquefaction design for the U.S. Department of Energy's (DOE) Pittsburgh Energy Technology Center (PETC). The project was initially for a duration of 18 months with an approved budget of \$2 MM. Later, the project was extended to mid-May 1992. This study is under DOE contract No. DE-AC22 90PC89857.

The primary objective of the study is to develop a computer model for a base line direct coal liquefaction design based on two stage direct coupled catalytic reactors. This primary objective is to be accomplished by completing the following:

- A base line design based on previous DOE/PETC results from Wilsonville pilot plant and other engineering evaluations
- A cost estimate and economic analysis
- A computer model incorporating the above two steps over a wide range of capacities and selected process alternatives
- A comprehensive training program for DOE/PETC Staff to understand and use the computer model
- A thorough documentation of all underlying assumptions for baseline economics, and
- A user manual and training material which will facilitate updating of the model in the future

The progress made during any particular quarter is published in a quarterly report following the duration of the quarter. The report consists of the following four sections:

- Introduction
- Summary
- Technical Progress Report (By Tasks)
- Key Personnel Staffing Report.

Introduction (Continued)

Any confidential information will be presented in the quarterly report as a separate section under the heading "confidential". As agreed upon by DOE/PETC, information included in the confidential section will be treated confidential by DOE/PETC and its contractors.

This report is Bechtel's fifth quarterly progress report and covers the period of September 16, 1991 through December 22, 1991.

2. SUMMARY

Effective May 16, 1990, Bechtel initiated this study, with Amoco as subcontractor, as an assignment from the U.S. Department of Energy (DOE)'s Pittsburgh Energy Technology Center (PETC). The objective of the study is to develop a computer model for a baseline direct coal liquefaction design based on two stage direct coupled catalytic reactors. The study was for a period of 18 months which was extended later to mid-May, 1992 with an approved total budget of \$2MM.

This is Bechtel's sixth quarterly progress report and covers the period (as requested and approved by DOE/PETC) of September 16, 1991 through December 22, 1991. This reporting period was previously covered by three already published monthly status reports.

The report contains accomplishments made during this time period in all the Tasks scheduled for the period i.e., Tasks I through VI. As per schedule, the major focus, however, was on Task II, III, IV and V. Therefore, the accomplishments included in this report are predominantly for these four tasks.

The accomplishments are presented in the report on Task by Task basis for all the Tasks covered during this reporting period.

In Task I (which defines the project) the Project Management Plan Draft Report was completed and subsequently updated incorporating the comments and suggestions of DOE/PETC and their contractors. The final version was sent to DOE/PETC for their approval and subsequently published in August, 1990. The approved copy was the deliverable for the Task.

Project Management Plan report covers the overall scope of work, the methodology of managing the cost and schedule of the project (configuration management), program administration, the deliverables during various phases of work and the definition of the baseline configuration.

In Task II the following activities were accomplished:

- During this reporting period reforming of naphtha product stream was completed as an option to the baseline study. Initiation of this work is a result of the scope change recently approved by DOE/PETC.
- The six identified options included in the scope of this study were completed. Incorporation of the results for various options was also completed as Volume 3 of Task 2 topical draft report. This volume of the draft topical report of Task 2 will be issued mid-January, 1992.

- Volumes 1 and 2 of the Task 2 Final Topical Report were issued in December, 1991.

Task III

- The preliminary capital cost estimates for the direct coal liquefaction complex have been presented to DOE/PETC on October 10, 1991 in Pittsburgh. The recommendation and comments obtained in that meeting are being addressed to come up with the final estimates.

Task IV

- This task was completed and final report issued in September, 1991.

Task V

- Continued validation of the model versus the Task II report. Provisions were added to the block models for calculating the number of operators as a function of the number of trains in a plant.
- Documentation of the FORTRAN block models is being prepared for the Task 5 report.
- SSI has completed the elemental balance model. A complete version 8 of ASPEN/SP with the new features is yet to be delivered by SSI.
- As part of SSI's subcontract, two subroutines for retrieving and loading pseudocomponent properties from the internal ASPEN storage for transfer from one process module to another are being developed. These routines should be complete in early January, and will then be integrated into various FORTRAN block models.
- The economic model is essentially complete. Finalization is awaiting firming up some data.
- During this reporting period the kinetic model is continued to be integrated with ASPEN. The two-stage model has been implemented and it was tested out successfully for a single base case reactor train. The model needs to be extended to include more extensive reactor sizing and number of train calculations. The kinetic model parameters are being revised to include data from Wilsonville Run 261. In this run, the use of an interstage separator allowed for a detailed estimate of the first-stage liquid yields. This modification should improve calculations for resid concentration at the first-stage outlet.

Task VI.

- An ASPEN training course which was scheduled for November, has been postponed to early 1992, at DOE's request. The training course has not yet been rescheduled.

3. TECHNICAL PROGRESS (BY TASKS)

In order to carry out this Study efficiently, the Study has been divided in seven major tasks. Task I defines the project. Task II develops the baseline design. Task III develops the capital, operating and maintenance costs. Task IV develops the mathematical model necessary for the process computer simulation model. Task V develops and verifies the process simulation model. Task VI documents the process simulation model and training. Task VII is a level of effort task for project management, technical coordination and other miscellaneous support functions.

During this reporting period (September 16, 1992 through December 22, 1991) several accomplishments were made in Tasks II, III, IV and VI. These accomplishments are included in this report task by task.

Task I was completed during the first quarterly reporting period. The accomplishment of Task I was documented in the Project Management Plan published in August, 1990. It was also presented in the first quarterly report, covering the period of May 16, 1990 through August 19, 1990).

3.1 TASK I

Task I defines the scope and the methodology of accomplishing the project. It sets the objectives of the project and defines the paths to accomplish those objectives.

As mentioned earlier in Section 3, Task I was completed during the first quarterly reporting period and accomplishments were documented in the Project Management Plan issued in August, 1990.

The Project Management Plan report is comprised of the following 9 sections:

- Executive Summary
- Background/Introduction
- Study Objective
- Overall Scope Of Work
- Configurational Management
- Program Administration
- Deliverables
- Baseline Configuration
- Appendix/Project Procedure Booklet
List Of Contents

The report completing Task 1 was published on time schedule. Detailed accomplishments of Task I were included in the first quarterly report (May 16, 1990 through August 19, 1990) of the project.

3.2 TASK II

Task II concerns the development of the baseline design of the liquefaction facility. This part of the study includes the acquisition of process licensors information, incorporation of various processing options into the design, and developing the design of the on-site processing units and offsite facilities (including storage and loading, utilities, and waste handling).

In this task certain plants are handled as packaged plants (or blocks) with an overall heat and material balance only.

3.2.1 STATUS UPDATE

The final Topical/Task Report for Task II is divided into three volumes. Volumes I and II pertain to the baseline design while Volume III covers the options (alternates). During this reporting period Volumes I and II were published.

The 42 Sections of the baseline design (Volume I & II) present information on 11 process facilities plants and 20 support facilities Plants. They have been subdivided into two volumes of approximately equivalent size. Volume I presents design information on all process plants plus the overall design considered, overall plant configuration and overall material and utility balances for the whole complex (process facilities and support facilities). Volume II, however, presents design information on all support facilities plus overall site plan, overall staffing plan, and overall Hydrogen flow, steam flow, and water flow distributions. It also contains the environmental strategy/plan for achieving environmental compliance.

For each process and support facilities plant, the following information is provided:

- Design basis, criteria and consideration
- Process description and block/process flow diagram
- Material balance
- Major Equipment List
- Utility summary
- Water summary (if applicable)

The Table of Contents for these two volumes of Task II report are shown in Tables 3.2.1 and 3.2.2.

TASK II REPORT
Table Of Contents

VOLUME I, SECTIONS 1 - 23

1.	Introduction	1-1
2.	Executive summary	2-1
3.	Overall Considerations	3-1
3.1	Overall Plant Capacity and Equipment Design Criteria	
3.2	Plant Numbering System	
3.3	Plant Site Information	
3.4	Product and By-Product Specifications	
3.5	Baseline	
3.6	Options To Baseline	
3.7	Overall Execution Methodology	
4.	Overall Plant Configuration	4-1
5.	Overall Material and Utility Balances	5-1
5.1	Material Balance	
5.2	Utility Balance	
6.	Plant 1 (Coal Cleaning and Handling)	6-1
6.0	Design Basis, Criteria And Considerations	
6.1	Process Description, Block and Process Flow Diagrams	
6.2	Material Balance	
6.3	Major Equipment List	
6.4	Utility Summary	
6.5	Water Summary	

7.	Plant 1.4 (Coal Grinding and Drying)	7-1
7.0	Design Basis, Criteria and Considerations	
7.1	Plant Description and Block Flow Diagram	
7.2	Major Equipment List	
7.3	Utility Summary	
8.	Plant 2 (Coal Liquefaction)	8-1
8.0	Design Basis, Criteria and Considerations	
8.1	Process Description and Process Flow Diagram	
8.2	Material Balance	
8.3	Major Equipment List	
8.4	Utility Summary	
8.5	Water Summary	
8.6	HRI's Report on Liquefaction Reactor Design	
9.	Plant 3 (Gas Plant)	9-1
9.0	Design Basis, Criteria and Considerations	
9.1	Process Description and Process Flow Diagram	
9.2	Material Balance	
9.3	Major Equipment List	
9.4	Utility Summary	
9.5	Water Summary	
10.	Plant 4 (Naphtha Hydrotreater)	10-1
10.0	Design Basis, Criteria and Considerations	
10.1	Process Description and Process Flow Diagram	
10.2	Material Balance	
10.3	Major Equipment List	
10.4	Utility Summary	
10.5	Water Summary	
11.	Plant 5 (Gas Oil Hydrotreater)	11-1
11.0	Design Basis, Criteria and Considerations	
11.1	Process Description and Process Flow Diagram	
11.2	Material Balance	
11.3	Major Equipment List	
11.4	Utility Summary	
11.5	Water Summary	

12.	Plant 6 (Hydrogen Purification)	12-1
12.0	Design Basis, Criteria and Considerations	
12.1	Process Description and Process Flow Diagram	
12.2	Material Balance	
12.3	Major Equipment List	
12.4	Utility Summary	
12.5	Water Summary	
13.	Plant 8 (Critical Solvent Deashing Unit, ROSE-SR)	13-1
13.0	Design Basis, Criteria and Considerations	
13.1	Process Description and Process Flow Diagram	
13.2	Overall Material Balance	
13.3	Major Equipment List	
13.4	Utility Summary	
13.5	Water Summary	
14.	Plant 9 (Hydrogen Production By Coal Gasification)	14-1
14.0	Design Basis, Criteria and Considerations	
14.1	Process Description and Process Flow Diagram	
14.2	Material Balance	
14.3	Major Equipment List	
14.4	Utility Summary	
14.5	Water Summary	
15.	Plant 10 (Air Separation)	15-1
15.0	Design Basis, Criteria and Considerations	
15.1	Process Description and Process Flow Diagram	
15.2	Overall Material Balance	
15.3	Major Equipment List	
15.4	Utility Summary	
15.5	Water Summary	
16.	Plant 11 (By-Product Sulfur Recovery)	16-1
16.0	Design Basis, Criteria and Considerations	
16.1	Process Description and Process Flow Diagram	
16.2	Material Balance	
16.3	Major Equipment List	
16.4	Utility Summary	
16.5	Water Summary	

17.	Plant 19 (Relief and Blowdown Facilities)	17-1
17.0	Design Basis, Criteria and Considerations	
17.1	Plant Description and Diagram	
17.2	Major Lines List	
18.	Plant 20 (Tankage)	18-1
18.0	Design Basis, Criteria and Considerations	
18.1	Plant Description and Block Flow Diagrams	
18.2	Major Equipment List	
18.3	Utility Summary	
19.	Plant 21 (Interconnecting Piping Systems)	19-1
19.0	Design Basis, Criteria and Considerations	
19.1	Plant Description	
19.2	Major Equipment List and Major Lines Summary	
20.	Plant 22 (Product Shipping)	20-1
20.0	Design Basis, Criteria and Considerations	
20.1	Plant Description	
20.2	Major Equipment List	
20.3	Utility Summary	
21.	Plant 23 (Tank Car/Tank Truck Loading)	21-1
21.0	Design Basis, Criteria and Considerations	
21.1	Plant Description	
21.2	Major Equipment List	
21.3	Utility Summary	
22.	Plant 24 (Coal Refuse and Ash Disposal)	22-1
22.0	Design Basis, Criteria and Considerations	
22.1	Plant Description	
22.2	Major Equipment List	
22.3	Utility Summary	
23.	Plant 25 (Catalyst and Chemical Handling)	23-1
23.0	Design Basis, Criteria and Considerations	
23.1	Plant Description	
23.2	Major Equipment List	
23.3	Utility Summary	
23.4	Catalyst and Chemical Summary	

VOLUME II, SECTIONS 24-42

24.	Plant 30 (Electrical Distribution System)	24-1
24.0	Design Basis, Criteria and Considerations	
24.1	Plant Description	
24.2	One Line Diagram	
24.3	Major Equipment List	
25.	Plant 31 (Steam and Power Generation)	25-1
25.0	Design Basis, Criteria and Considerations	
25.1	Plant Description	
25.2	Utility Summary	
25.3	Water Summary	
26.	Plant 32 (Raw, Cooling and Potable Water Systems)	26-1
26.0	Design Basis, Criteria and Considerations	
26.1	Plant Description	
26.2	Water Balance	
26.3	Major Equipment List	
26.4	Utility Summary	
27.	Plant 33 (Fire Protection Systems)	27-1
27.0	Design Basis, Criteria and Considerations	
27.1	Plant Description	
27.2	Major Equipment List	
28.	Plant 34 (Sewage and Effluent Water Treatment)	28-1
28.0	Design Basis, Criteria and Considerations	
28.1	Coal Storage Pile (CSP) Run off Treatment	
28.2	Oily Water Treatment	
28.3	Deoiled Wastewater Treatment	
28.4	Stripped/Dephenoled Wastewater Treatment	
28.5	Solids Dewatering	
28.6	Sanitary Sewage Treatment	
28.7	Major Equipment List	
28.8	Utility Summary	

29.	Plant 35 (Instrument and Plant Air Facilities)	29-1
29.0	Design Basis, Criteria and Considerations	
29.1	Plant Description	
29.2	Major Equipment List	
29.3	Utility Summary	
30.	Plant 36 (Purge and Flush Oil System)	30-1
30.0	Design Basis, Criteria and Considerations	
30.1	Plant Description	
31.	Plant 37 (Solid Waste Management)	31-1
31.0	Design Basis, Criteria and Considerations	
31.1	Plant Description	
31.2	Major Equipment List	
32.	Plant 38 (Ammonia Recovery)	32-1
32.0	Design Basis, Criteria and Considerations	
32.1	Process Description and Process Flow Diagram	
32.2	Material Balance	
32.3	Major Equipment List	
32.4	Utility Summary	
33.	Plant 39 (Phenol Recovery)	33-1
33.0	Design Basis, Criteria and Considerations	
33.1	Process Description and Process Flow Diagram	
33.2	Material Balance	
33.3	Major Equipment List	
33.4	Utility Summary	
34.	Plant 40 (General Site Preparation)	34-1
34.0	Design Basis, Criteria and Considerations	
34.1	Facility Description	
35.	Plant 41 (Buildings)	35-1
35.0	Design Basis, Criteria and Considerations	
35.1	Facility Description	
35.2	Building List	
35.3	Control Systems List	

36.	Plant 42 (Telecommunications Systems)	36-1
36.0	Design Basis, Criteria and Considerations	
36.1	Facility Description	
36.2	Equipment/Systems List	
37.	Overall Site Plan	37-1
38.	Overall Staffing Plan	38-1
39.	Overall Hydrogen Flow Distribution	39-1
40.	Overall Steam Flow Distribution	40-1
41.	Overall Water Flow Distribution	41-1
42.	Environmental Compliance Strategy/Plan	42-1
42.1	National Environmental Policy Act (NEPA)	
42.2	Air Pollution Control Regulations	
42.3	Solid and Hazardous Waste Regulations	
42.4	Water Pollution Control Regulations	
42.5	Toxic Substances Control Act	
42.6	Occupational Safety and Health Act (OSHA)	
42.7	Noise Regulations	
42.8	Federal Aviation Administration (FAA) Policies	

3.3 TASK III

Task III concerns the development of the cost estimate and economics for the base-line design and the alternates for the coal liquefaction facility. This part of the study includes the compilation of equipment and utilities summaries, development of scaling factors for equipment sizes and plant costs, and development of the estimates for capital cost, working capital, and owner's costs. Work to perform the economic analyses includes the workup of the manpower requirements and operating costs for the baseline design and for the alternates and the completion of sensitivity studies.

In this task plants are handled as packaged plants or blocks for the purpose of capital investment, and operating costs as well as overall capacity scale-up.

3.3.1 Capital Cost Estimate

The preliminary results on 1) estimated overall cost summary for the coal liquefaction complex, 2) proposed owner's cost, 3) capital cost savings by elimination of spare train and 4) major equipment cost for coal liquefaction plant (Plant 2) are included in Table A-1, A-2, A-3, and A-4 respectively of the confidential section of this report, Appendix 1.

3.3.2 Coal Liquefaction Product Valuation Utilizing Process Industry Modeling Systems (PIMS) Software

During this reporting period product valuation of coal liquefaction product was carried out utilizing Bechtel's software, Process Industry Modeling Systems (PIMS). Several cases were evaluated. The salient points for various cases are discussed below and the summary results are reported in Table 3.3.1. These results will be utilized in determining Syncrude premium.

- Case 1 is for a typical PAD 2 refinery handling only petroleum crude (no coal liquid) with a maximum processing capacity of 130 MBPD of average PAD 2 crude mix and 20 MBPD of Alaskan North Slope Crude. In this case the refinery product make is allowed to float up to the maximum market requirement level.
- Case 1A is same as case 1 with the exception of floating the product slate as well as the feed composition.

The following cases are with various fractions of coal liquids available to the refinery. For this case study it is assumed that the naphtha fraction of the coal liquid (C5-350) is sent to the reforming unit, the light distillate fraction (350-450) is for blending (diesel and fuel oil), the heavy distillate fraction (450-650) is for diesel and fuel oil blending and also used as FCCU feed, and the vacuum gas oil (650-850) is used as fuel oil blending stock and FCCU feed.

- Case 2A is for changing the feed to the typical PAD 2 refinery with 100% of coal liquids (61.94 MBPD) being available with corresponding amount of petroleum feed being backed out. There is not enough degrees of freedom in this case and consequently the case is infeasible. (Note: Case 7A resolves this infeasibility.)
- Case 2B is same as Case 2A; however, the coal liquid is available at 50% of its production rate (having the same composition). This is a feasible case and the value per BBL of coal liquid mix (with the same product slate as the baseline coal liquidfaction complex produces) is \$19.04.
- Case 2C is same as case 2B with coal liquid available at 25% production rate instead of 50%. The value per BBL of coal liquid mix is \$19.06.
- Case 2D simulates the case where the coal liquid addition to refinery is very small (1 MBPD), first drop to refinery. The value of Coal liquid mix is \$19.27 per BBL.
- Cases 7A, 7B, 7C and 7D are similar to cases 2A, 2B, 2C and 2D respectively with the exception that the refining product slates for these cases have been floated. For these relaxed cases the values of the respective coal liquids have increased to \$20.63, \$22.45, \$22.84 and \$22.90 per BBL respectively.
- Cases 3A, 4A, 5A and 6A are for 100% naphtha (C5-350), 100% light distillate (350-450), 100% heavy distillate (450-650) and 100% gas oil (650-850) respectively entering the refinery with other conditions remaining same as in case 1. The values of the respective fractions of the coal liquids are \$18.65, \$12.80, \$19.21 and \$16.26. Note that the maximum value is achievable for heavy distillate.
- Cases 3B, 4B, 5B and 6B are similar to Cases 3A, 4A, 5A and 6A respectively with the exception that in each of these cases the respective coal liquid addition to refinery was kept at a minimum level of 1 MBPD. The value of the fractions increased to \$19.24, \$18.78, \$19.66 and \$18.77 respectively.

TABLE 3.3.1

Pims Model Solution Summary Report

HDC HV DIST TO FCCO

CASE NO.	1A	2A	2B	2C	2D	7A	7B	7C	7D	3A	4A	5A	6A	3B	4B	5B	6B
COAL LIQUIDS	ZERO	100 % MIX	50% MIX	25% MIX	1 MBPO MIX	100 % MIX	50% MIX	25% MIX	1 MBPO MIX	100% MNC MAPNTNA LT DIST MAX	100% LDC LT DIST MAX	100% HNC LT DIST MAX	100% LVC LT VCO LT VCO	1 MBPO MNC MAPNTNA LT DIST MAX	1 MBPO LDC LT DIST MAX	1 MBPO HNC LT DIST MAX	1 MBPO LVC LT VCO LT VCO
PRODUCT SLATE	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX	MAX
OBJ FUNCTION, MB/DAY	623.46	708.95	1213.26	918.66	642.73	1986.76	1404.24	1062.70	731.84	981.41	723.37	1039.17	839.84	642.70	642.23	643.12	642.23
FEEDSTOCK PURCHASES																	
PD2 AVG PAD2 CRUDE MIX	MBPO 126.900	MBPO 130.000	MBPO 92.157	MBPO 109.469	MBPO 125.706	MBPO 108.862	MBPO 130.000	MBPO 130.000	MBPO 130.000	MBPO 102.783	MBPO 110.312	MBPO 103.588	MBPO 102.862	MBPO 125.646	MBPO 125.788	MBPO 125.712	MBPO 125.836
HMS ALASKAN NORTH SLOPE	1.239	20.000	1.822	1.239	1.239	1.239	20.000	20.000	20.000	4.395	1.239	1.239	1.239	1.239	1.239	1.239	1.239
HIC4 MORRAL BUTANE	0.778	0.699	0.000	1.296	0.821	2.215	1.441	1.274	0.737	0.000	0.000	0.000	0.986	0.865	0.813	0.783	0.782
PGS M2 PLT FEED GAS, FOE	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
IC4 ISOBUTANE	2.041	2.041	2.041	2.041	2.041	2.041	2.041	2.041	2.041	1.260	2.041	1.542	2.041	2.041	2.041	2.041	2.041
MNC C5-350 COAL MAPNTNA	0.000	0.000	9.598	4.799	0.310	19.195	9.598	4.799	0.310	19.195	0.000	0.000	0.000	0.000	0.000	0.000	0.000
LDC 350-450 COAL LT DIST	0.000	0.000	3.902	1.951	0.126	7.803	3.902	1.951	0.126	7.803	0.000	0.000	0.000	0.000	0.000	0.000	0.000
MOC 450-650 COAL HV DIST	0.000	0.000	10.818	5.409	0.349	10.818	5.409	0.349	0.349	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
LVC 650-850 COAL LVCO	0.000	0.000	6.655	3.328	0.215	13.310	6.655	3.328	0.215	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
TOTAL FEEDSTOCKS	130.958	152.740	128.230	129.530	130.806	176.301	184.434	168.801	153.778	129.800	122.148	129.208	128.438	130.791	136.881	130.775	130.899
PRODUCT SALES																	
LPG	4.078	4.834	3.248	3.639	4.054	4.205	4.898	5.097	4.852	3.285	3.789	3.772	3.191	4.046	4.072	4.057	4.020
UNLEADED REGULAR	46.284	37.284	46.284	46.284	46.284	22.950	35.647	34.847	37.069	46.284	44.714	46.284	46.284	46.284	46.284	46.284	46.284
UNLEADED PREMIUM	19.836	42.120	19.836	19.836	19.836	65.166	54.670	53.473	42.921	19.836	19.836	19.836	19.836	19.836	19.836	19.836	19.836
LEADED REGULAR	6.614	0.000	6.614	6.614	6.614	0.000	0.000	0.000	0.000	6.614	0.000	6.614	6.614	6.614	6.614	6.614	6.614
KERO/JET	12.497	22.567	12.497	12.497	12.497	5.357	27.447	22.754	22.567	12.497	12.497	12.497	12.497	12.497	12.497	12.497	12.497
DIESEL	29.133	24.149	29.133	29.133	29.133	61.801	34.597	27.911	24.592	29.133	29.133	29.133	23.464	29.133	29.133	29.133	29.133
LOW SULFUR FUEL OIL	0.117	0.000	0.600	0.333	0.043	0.527	0.648	0.525	0.034	0.000	0.000	0.600	0.600	0.000	0.082	0.058	0.184
HIGH SULFUR FUEL OIL	2.736	5.256	2.151	2.439	2.736	2.632	9.965	7.487	5.400	2.197	2.736	2.306	2.736	2.736	2.736	2.736	2.736
ASPHALT	6.216	11.931	6.216	6.216	6.216	10.056	11.931	11.931	11.931	6.216	6.216	6.216	6.216	6.216	6.216	6.216	6.216
COKE, TONS	0.649	0.762	0.450	0.549	0.643	0.528	0.762	0.762	0.762	0.532	0.558	0.520	0.538	0.642	0.643	0.643	0.643
SULFUR, LTONS	0.059	0.067	0.037	0.048	0.058	0.042	0.059	0.063	0.066	0.051	0.050	0.050	0.044	0.058	0.058	0.058	0.058
FUEL TO FLARE, FOEB	0.035	0.105	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
TOTAL PRODUCTION	127.512	148.141	126.578	126.991	127.415	172.694	179.803	164.025	149.166	126.062	119.521	127.258	118.243	127.362	127.470	127.432	127.520
LIG RECOVERY, %	97.4	97.9	98.7	98.9	97.4	98.0	97.5	97.2	97.0	97.1	97.8	98.3	98.2	97.4	97.4	97.4	97.4

TABLE 3.3.1 - continued

CAPACITY UTILIZATION																1	1A	2A	2B	2C	2D	7A	7B	7C	7D	3A	4A	5A	6A	3B	4B	5B	6B
MBPO #1	110,890	130,000	76,787	93,761	109,729	90,101	130,000	130,000	130,000	90,936	95,195	88,734	91,834	109,699	109,796	109,728	109,762																
CRUDE UNIT #1	17,249	20,000	16,609	16,946	17,216	20,000	20,000	20,000	20,000	16,243	16,357	16,093	12,267	17,187	17,231	17,223	17,313																
CRUDE UNIT #2	49,675	58,105	34,532	42,019	49,156	40,272	58,105	58,105	58,105	41,040	42,549	39,772	41,046	49,143	49,186	49,156	49,171																
VAC UNIT #1	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000	0,000																
VAC UNIT #2	9,215	10,240	6,707	7,957	9,129	7,913	10,240	10,240	10,240	7,609	8,018	7,532	7,480	9,125	9,135	9,129	9,138																
C5/C6 ISOL	29,378	33,788	17,143	23,083	29,082	19,096	28,910	33,600	33,788	19,118	25,836	24,176	24,168	28,802	29,463	28,813	29,010																
NAPH HYDROTRT	30,497	34,910	27,995	29,069	30,509	39,400	39,400	39,400	35,212	39,400	27,348	25,271	24,682	30,964	30,634	29,981	30,074																
LOW-P REFORMER	0,000	6,000	0,000	0,000	0,000	6,000	6,000	6,000	6,000	0,000	0,000	0,000	6,000	0,000	0,000	0,000	0,000																
KERO HYDROTRT	2,971	3,454	0,608	1,636	2,940	2,394	3,454	3,454	3,454	2,503	1,199	2,382	2,440	2,938	2,662	2,693	2,941																
DIST HYDROT	42,303	45,079	47,400	45,007	42,361	53,300	53,300	51,262	45,478	33,308	36,557	53,300	46,382	41,749	42,148	43,075	42,882																
CAT CRACKER	9,001	9,594	9,158	9,096	8,993	10,197	10,513	10,320	9,641	6,708	8,264	9,130	9,219	8,917	8,988	9,073	9,051																
SULF ACID ALKY	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500	7,500																
HYDROCK-DIST	0,025	0,028	0,019	0,022	0,025	0,025	0,029	0,029	0,028	0,020	0,022	0,021	0,022	0,025	0,025	0,025	0,025																
M2 PLANT	13,928	16,252	9,665	11,787	13,783	11,266	16,252	16,252	16,252	11,601	11,901	11,159	11,480	13,780	13,792	13,783	13,787																
DILC	0,059	0,067	0,037	0,048	0,058	0,042	0,059	0,063	0,066	0,051	0,050	0,050	0,044	0,058	0,058	0,058	0,058																
SULFUR PLT	47,759	52,974	45,171	46,475	47,642	53,834	57,717	57,057	53,262	41,602	42,307	48,326	46,487	47,410	47,599	47,844	47,833																
N LTO	1,099	1,204	1,066	1,083	1,098	1,245	1,318	1,298	1,210	0,974	0,997	1,076	1,061	1,095	1,098	1,101	1,100																
KRM IN SUIT	13,449	14,523	13,167	13,315	13,431	15,154	15,793	15,588	14,595	11,449	12,316	13,136	13,169	13,378	13,433	13,484	13,467																
SUFLR PLT	256,208	286,511	244,489	250,328	255,780	292,343	317,172	311,267	288,814	241,230	228,814	231,701	242,224	255,441	255,661	256,107	255,915																

ECONOMIC SUMMARY ANALYSIS

[illegible]

TABLE 3.3.1 - continued

UTILITY PURCHASES	1	1A	2A	2B	2C	2D	7A	7B	7C	7D	3A	4A	5A	6A	3B	4B	5B	6
TEL TEL	0.03	0.00		0.03	0.03	0.03	0.00	0.00	0.00	0.00	0.03	0.00	0.03	0.01	0.03	0.03	0.03	0.03
CUC CAT/CHEM DOLLARS	12.03	13.40		11.84	11.93	12.03	14.37	14.90	14.71	13.48	11.14	10.66	12.56	11.92	11.98	12.01	12.05	12.05
SFA SULF ACID HLBS	0.21	0.22		0.21	0.21	0.21	0.24	0.25	0.24	0.23	0.16	0.19	0.21	0.21	0.21	0.21	0.21	0.21
PLR HV POWER KWH	1145.29	1270.37		1083.23	1114.51	1142.49	1290.99	1364.09	1368.28	1276.78	997.64	1014.55	1158.90	1114.80	1136.92	1141.46	1147.34	1147.07
RIV RIVER H2O M-GAL	1.58	1.73		1.53	1.56	1.58	1.79	1.90	1.87	1.74	1.40	1.64	1.55	1.53	1.58	1.58	1.59	1.58
GAS PURCH GAS MM-BTU	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2.03	0.00	0.00	0.00	0.00	0.00	0.00

TABLE 3.3.1 - continued

• TABLE BUY

	TEXT	MIN	MAX	FIX	COST
PO2	AVG PAD2 CRUDE MIX		130		\$18.00
ANS	ALASKAN NORTH SLOPE	1.239			\$18.50
NC4	NORMAL BUTANE	0	3.795		\$18.90
PGS	N2 PLT FEED GAS, FOE	0			\$9.08
IC6	ISO BUTANE		2.041		\$25.20
MNC	C5-350 COAL LIQ	0	19.195		
LDC	350-450 COAL LT DIST	0	7.803		
HDC	450-650 COAL HYY DIS	0	21.635		
LVC	650-850 COAL LVGO	0	13.31		

TABLE 3.3.1 - continued

* TABLE SELL		PRODUCT SALES		
	TEXT	MIN	MAX	PRICE
LPG	LPG	4.268		\$14.00
URG	UNLEADED REGULAR	46.28		\$26.00
UPR	UNLEADED PREMIUM	19.83		\$27.00
LRG	LEADED REGULAR	6.614		\$25.00
JET	KERO/JET	12.49		\$24.00
DSL	DIESEL	29.13		\$22.00
LSF	LOW SULFUR FUEL OIL	0.6		\$14.50
HSF	HIGH SULFUR FUEL OIL	2.736		\$14.00
ASP	ASPHALT	6.216		\$20.00
CKE	COKE, TONS			\$20.00
SUL	SULFUR, LTONS			\$120.00

3.4 TASK IV

Task IV concerns the development of the mathematical algorithms and models for equipment sizing, scale-up, costing, and train duplication for incorporation into the ASPEN/SP process simulation model being developed in Task V.

3.4.1 Status of Task IV

The final topical/task report for Task IV was published during this reporting period. The table of contents for this report is included in Table 3.4.1. The summary of this report and the overview of the results are presented in Sections 3.4.1.1 and 3.4.1.2 respectively.

TABLE 3.4.1

**TASK IV: ALGORITHMS FOR EQUIPMENT SIZING,
COSTING, AND TRAIN DUPLICATION**

TABLE OF CONTENTS

	<u>PAGE</u>
1. INTRODUCTION	1-1
2. EXECUTIVE SUMMARY	2-1
3. DISCUSSION OF RESULTS	3-1
3.1 Overview	3-1
3.2 Plant 2 Equipment Sizing Algorithms	3-2
3.3 Equations for Capital Cost Estimation	3-3
3.4 Multiple Train Requirements	3-4
3.5 Fortran User Block Model Implementation	3-5
3.6 ASPEN/SP Implementation	3-10
 APPENDICES	
A. EQUIPMENT SIZE SCALING EQUATIONS	A-1
B. FORTRAN SUBROUTINE FOR GENERATING AND REPORTING EQUIPMENT SIZES FOR PLANT 2	B-1
C. SAMPLE EQUIPMENT SIZING OUTPUT	C-1
D. ASPEN/SP COST MODEL USERS INSTRUCTIONS	D-1

3.4.1.1 SUMMARY

This report presents the Task IV topical report. Task IV concerns the development of the mathematical algorithms and models for equipment sizing, scale-up, costing, and train duplication for incorporation into the ASPEN/SP process simulation model being developed in Task V. Table 3.4.2 contains a description of the individual subtasks as detailed in the Task I Management Plan. Task IV was done in parallel with the process model development work of Task V.

Subtasks 4010 and 4020 called for a review of the existing ASPEN/SP equipment sizing equations for the major pieces of process equipment. This presumed that the simulation program would calculate the cost of each plant section by building it up from the costs of the individual pieces of major equipment. However, in line with conventional industrial practice, DOE/PETC agreed to a costing philosophy which involves a combination of individual equipment costing and factored costs based upon either the capacity of an entire plant or the capacity of an individual plant sub-section (see the topical report for Task III). The costing algorithms that are being implemented in the simulation model parallel this philosophy and eliminate the need for using the ASPEN/SP equipment sizing equations for costing purposes. Costing equations based on individual plant capacity or on individual plant subsections (Plant 2) are presented and discussed herein.

Since the coal liquefaction plant is the only plant in the entire complex that is being modeled in detail, equipment sizing equations were developed only for this plant. As discussed, these equipment sizes are not used directly for plant costing purposes.

Subtask 4030 deals with incorporating equipment size limitations in the process simulation model. Algorithms were developed which control the maximum train size of Plant 2 so as to keep the equipment sizes developed in the baseline design for Plant 2 below the maximum size limitation. This is reflected in the equipment sizing/scaling equations developed for Plant 2. Maximum size limits for the Plant 2 reactor diameter are handled in the kinetic model and are described in the topical report for Task V.

Subtask 4040 deals with the equations to handle multiple train requirements within a process unit. These equations were developed, and for flexibility, incorporate a train duplication parameter tailored to the particular plant. The number of trains may be supplied by the user as an input parameter. If the number of trains is not specified, the model will calculate the number of duplicate plants from the specified maximum and minimum plant capacities.

Subtasks 4050 and 4060 deal with the preparation and issuance of this document, the topical report for Task IV.

TABLE 3.4.2**TASK IV DESCRIPTION**

Task IV concerns the development of the mathematical algorithms and models for equipment sizing, scale-up, costing, and train duplication for incorporation into the ASPEN/SP process simulation program that is being developed in Task V. Task IV has been done in parallel with Task V.

Following is a description of the individual subtasks of Task IV.

Subtask Number	Subtask Title	Description
4010	Review ASPEN equations	Review of existing ASPEN equipment sizing equations for major equipment
4020	Develop supplementary scale-up equations	Develop equations and algorithms, as required, to scale major equipment items
4030	Incorporate equipment size limitations	Incorporate major equipment size limits (reactor diameter, etc.) into scale-up equations
4040	Incorporate multiple train requirements	Incorporate into equipment scaling equations a means to handle multiple trains within a process unit. Philosophy may vary with process unit
4050	Draft topical report for Task 4	Report covering development of equations for equipment sizing, scaling, size limitations, and train requirements will be prepared
4060	Review of draft topical report for Task 4	The draft topical report for Task 4 will be reviewed with PETC prior to issue

3.4.1.2 Overview of Results

Task IV concerns the development of the mathematical algorithms and models for costing and train duplication for all plants, and for sizing of the major equipment in the coal liquefaction section (Plant 2). These equations are to be incorporated into the ASPEN/SP computer simulation model that is being developed in Task V.

For Plant 2, common equipment scaling algorithms were used to scale the sizes of the major pieces of process equipment. The scaling of the coal liquefaction reactors were not done using this basis, but are being sized by the kinetic model. This is described in the Task V report.

For all plants, the capital costs are being scaled from the baseline design case cost by a commonly used cost scaling equation that has been extended to allow for multiple trains.

All plants, other than the coal liquefaction plant, are being modeled by black box Fortran user block models. These models incorporate the capital cost scaling equation to predict the cost of each plant as a function of plant capacity and the number of duplicate plants.

The ASPEN/SP model also has been modified to utilize these cost scaling equations to predict the cost of individual pieces or groups of processing equipment as a function of capacity, where required.

3.5 TASK V

Task V concerns the development of the ASPEN process simulation model of the baseline design. The model will produce complete heat and material balances, elemental balances around each plant and the entire process complex, a major equipment list and outline specifications for Plant 2, utility requirements, capital cost for all plants, and a discounted cash flow economic model for the total complex. The model will be suitable for studying technology advances and options in a case study approach. The model will not include optimization capabilities.

During this reporting period several accomplishments were made in this task. These accomplishments are listed below.

- Continued validation of the model versus the Task II report. Provisions were added to the block models for calculating the number of operators as a function of the number of trains in a plant.
- Documentation of the FORTRAN block models is being prepared for the Task 5 report.
- SSI has completed the elemental balance model. We are awaiting the delivery of a complete version 8 of ASPEN/SP with the new features.
- As part of SSI's subcontract, two subroutines for retrieving and loading pseudocomponent properties from the internal ASPEN storage for transfer from one process module to another are being developed. These routines should be complete in early January, and will then be integrated into various FORTRAN block models.
- The economic model is essentially complete. Finalization is awaiting firming up some data.
- During this reporting period the kinetic model is continued to be integrated with ASPEN. The two-stage model has been implemented and it was tested out successfully for a single base case reactor train. The model needs to be extended to include more extensive reactor sizing and number of train calculations. The kinetic model parameters are being revised to include data from Wilsonville Run 261. In this run, the use of an interstage separator allowed for a detailed estimate of the first-stage liquid yields. This modification should improve calculations for resid concentration at the first-stage outlet.

3.6 TASK VI

Task 6 concerns the development of a training manual and a training course for the process simulation model. The training course will include an overview of the system, modification of the reporting system, interfacing user models, modification of chemical properties, use of the cost and economics modules, specifying flowsheets, streams, components, properties, and convergence. Trainees will be instructed through the use of case study example problems.

Aspen training which was scheduled for November, 1991, has been postponed to early 1992 at DOE/PETC's request.

4. KEY PERSONNEL STAFFING REPORT

Key Personnel staffing report for this reporting period (September 16, 1991 through December 22, 1991) as required by DOE/PETC is included in Table 4-1 shown below.

Table 4-1
Key Personnel Staffing Report

Duration of Quarter		From September 16, 1991 to December 22, 1991
<u>Name of Key Person</u>	<u>Function</u>	<u>% Time Spent*</u>
<u>Bechtel:</u>		
S. N. Habash	Project Manager	72
S. K. Poddar	Technical/Project Coordinator	89
T. J. Reynolds	Project Secretary	77
<u>Amoco:</u>		
A. B. Schachtschneider	Project Manager	8
S. J. Kramer	Principal Investigator	57
Arun Basu	Principal Investigator	1

* (Number of hours spent/total available working hours
for September 16, 1991 through December 22, 1991) x 100.

END

**DATE
FILMED
9/22/92**