AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 1

DLF/PC/90258-75

00007

Quarterly Technical Report
for the Period
November 1, 1987 to January 31, 1988

TABLE OF CONTENTS

	Page Number
1.0 INTRODUCTION AND BACKGROUND	1
2.0 OBJECTIVES AND SCOPE OF WORK.	4
2.1 Contract Objectives	4
2.2 Contract Scope of Work	4
2.3 Task 1 Objectives.	4
2.4 Task 2 Objectives.	5
2.5 Task 3 Objectives.	6
3.0 EXECUTIVE SUMMARY	7
4.0 TASK 1 - ANALYSIS OF FUEL NEEDS	9
4.1 Subtask 1.1 Project Management	9
4.2 Subtask 1.2 Coal Selection	9
5.0 TASK 2 - CHARACTERIZATION OF COAL-BASED FUELS	10
Subtask 2.1 Deep Cleaning of Coal	10
Subtask 2.2 Washability Studies	12
Subtask 2.3 Dravo Pilot Plant Reagent Optimization Study . . .	12
6.0 TASK 3 - FUEL SUPPLY.	19
6.1 Production Facilities	19
6.1.1 Deep Cleaned Coal	19
6.1.1.1 Reblending	19
6.1.1.2 Screw Conveyor	20
6.1.1.3 Dryer Maintenance	21
6.1.2 Dry Pulverized/Micronized Coal	21
6.2 Fuel Production	21
6.2.1 Deep Cleaned Coal	21
6.2.2 Dry Powder.	23
6.2.3 Coal Water Fuels.	24
6.3 Shipments.	24
7.0 FUTURE PLANS.	26
8.0 APPENDICES.	27
8.1 Fuel Delivery Schedule	28

MASTER

ACKNOWLEDGMENT

Contributors to this report include: Daniel F. Petrunak and Christopher F. Welsh of Dravo Engineers, Inc.; Raymond M. Henry, Russell C. Maxwell, Burl E. Davis and Ronald W. Genser of Energy International, Inc.

DISCLAIMER

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness or any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, mark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PATENT STATUS

This technical report is being transmitted in advance of DOE patent clearance and no further dissemination or publication shall be made of the report without prior approval of the DOE Patent Counsel.

TECHNICAL STATUS

This technical report is being transmitted in advance of DOE review, and no further dissemination or publication shall be made of the report without prior approval from the DOE Program/Project Manager.

TABLE OF CONTENTS (Cont'd.)

	Page Number
8.2 Sample Shipment Log.	33
8.3 Dravo Froth Flotation Circuit.	38
8.4 List of Flotation Reagents	40

1.0 INTRODUCTION & BACKGROUND

Under the Department of Energy's Advanced Combustor Technology Program, approximately 11 combustor contractors (under 13 contracts) are developing combustion systems (during 1987-1989) for use in residential, commercial, light industrial and industrial retrofit markets. Sufficient quantities of well-characterized, coal-based fuels possessing specific, appropriate specifications are required by the contractors for their developmental test programs. Fuels may be dry pulverized coal or coal liquid fuels. In support of these equipment development efforts, the team of Energy International and Dravo Engineers is providing such fuels (under DOE Contract DE-AC22-86PC90258 within the PETC Alternate Energy Program).

Nearly a third of the total energy use in the U.S. is in the residential, commercial, and light industrial sectors. Of this, about half of the energy is supplied by the direct consumption (not including electricity) of conventional oil and gas resources. Thus, there is a significant energy use component for which coal is not currently a viable user option.

For coal to significantly penetrate this important market sector, it must be demonstrated that:

- o Premium coal-based fuels can be made, combusted, and used in low maintenance, automatic use systems to which such users are accustomed, i.e., by a direct replacement for conventional fuels and require only simple installation changes.
- o Advanced coal fuel combustion systems can effectively combust coal based fuels while meeting economic, environmental, and performance standards.
- o Coal fuels, combustion systems and service support are well matched, reliable, cost effective, and are anticipated to be available over the projected lifetime of the installations.

The key to the development of fuel and combustor technologies for future application to the use of premium coal-based fuels in these market sectors is to make representative coal fuels available for developmental testing. Current coal cleaning and processing technologies in early development stages offer the promise to meet the market, the performance and the environmental acceptability that are expected to be required. They are not economically competitive now and production facilities are presently limited to experimental and pilot-scale operations which do not offer the economy of scale to reduce costs to the minimum. This is not likely to change with the current plentiful supplies of relatively low cost fuels.

The developmental testing of advanced combustion equipment systems requires fuels for testing; test experience and performance measures are needed to identify cost competitiveness in the market and specific market niches for early commercialization; and, commercial market opportunities are needed to justify and specify the development and installation of advanced fuels facilities for supplying the developmental testing needs.

The capability to produce significant quantities of coal based fuels cannot be supported in the current economic and energy use situation. Once these pieces of experience and information begin to fall into place, the market driven needs will more clearly identify the suite of coals that will satisfy the markets and the performance requirements (i.e., cost, maintenance, energy efficiency, environmental). For now, it is important to provide sufficient quantities of surrogate fuels to enable development testing to proceed. To serve as surrogate fuels, the fuels should have chemical and physical characteristics (ash, sulfur, volatiles, fusion temperature, heat content, particle size distribution, slurry formulation, etc.) that are consistent with projected performance and environmental standards. In addition, these surrogates are to be produced using readily available conventional types of cleaning and processing so as to not promote a particular fuel technology or create a reliability on an uncertain fuel technology.

While the definitions of market and performance are not finalized nor quantitatively fixed and the eventual, economically acceptable fuel processes are not yet determined, it is possible to make use of current understanding of coal resources, markets, combustor and environmental requirements and specific available coal properties and characteristics to make reasonable selections of coals for fuels representative of future advanced fuels. With selected coals, conventional beneficiation methods can be used to prepare current versions of advanced premium coal-based fuels. The associated excessive grinding, special processing, low energy recoveries, and process economics are not expected to be acceptable for eventual commercial operations. However, these current advanced premium fuels can meet the needs of developmental testing with acceptable costs at this time.

The analysis of fuel needs, the selection of candidate coals, the characterization and supply in this contract are to be accomplished with the above in mind. The best choices of those available have been made based upon the available information, coal and processes. This will at least provide the developmental test fuels that will enable the DOE-PETC advanced combustion and fuels program to move forward. Following the fuels and combustor development activities that this supply contract will support, it is expected that additional optional candidate coals will become evident based on the new experience. In the meantime, these coal fuels will enable the program to proceed.

During the fifth quarter of this contract (November 1, 1987 through January 31, 1988) the primary activities were involved with:

- o Revision of the fuel production plan, cost plan and delivery plan due to major changes in the program at the request of PETC.
- o Test cleaning of the Upper Elkhorn #3 coal by Amax R&D Laboratories in Golden, CO and by EPRI at their coal cleaning test facilities in Homer City, PA.
- o Bench-scale froth flotation cleaning studies to optimize the yield of specification grade coal using the Upper Elkhorn #3 coal.
- o Processing and evaluation of the centrifugal washability data generated under Task 2 activities to determine its reliability and accuracy.
- o Continuation of the coal procurement, cleaning, fuel preparation and delivery activities.

2.0 OBJECTIVES AND SCOPE OF WORK

2.1 Contract Objectives

Contract objectives are as follows:

- o Develop fuel specifications to serve combustor requirements.
- o Select coals having appropriate compositional and quality characteristics as well as an economically attractive reserve base.
- o Provide quality assurance for both the parent coals and the fuel forms.
- o Deliver premium coal-based fuels to combustor developers as needed for their contract work.

2.2 Contract Scope of Work

Energy International/Dravo will perform the following:

- o From information obtained both from the combustor PRDA and from the combustor contractors, develop fuel specifications and schedule.
- o Using published reports and databases, perform a market assessment and a resource assessment in order to identify acceptable coals within reasonable proximity to markets. In other words, determine the availability and applicability of a wide range of coals in order to produce premium coal-based fuels for specific markets.
- o From all coal ranks and all domestic resources select coals which satisfy the requirements of combustion systems being developed.
- o Procure premium coals having the ability to be processed to contain <0.8 lb ash per million Btu and <0.5 lbs sulfur per million Btu.
- o Procure coals and produce coal liquid mixtures or dry pulverized coal and deliver these premium fuels to combustor contractors.

2.3 Task 1 Objectives

The objectives of Task 1, "Analysis of Fuels Needs", are as follows:

- o To provide analyses, information and evaluation of coal resources, coal properties, and market opportunities to support the selection of coals for characterization, processing and supply.

- o To assure that coals used in developmental testing are representative of future potential coal used in those applications and are:
 - o Available as U.S. domestic resource in sufficient quantity
 - o Geographically proximate to the regional markets
 - o Capable of being processed into premium coal-based fuels that have the properties to satisfy the combustor needs and market constraints (such as environmental)
- o To evaluate, interpret and assess the available information on coal reserves, market opportunities, performance requirements, environmental acceptability, coal properties and specific characteristics to provide guidance in the selection of candidate coals for characterization and supply for developmental testing of advanced combustors for residential, commercial and light industrial applications.
- o To collect, review and evaluate information about specific, currently available coals that can be procured from existing mining operations to provide contracted quantities of development test fuels that satisfy the reserves, market, geographic, property, performance and environmental criteria.
- o To recommend candidate coals and then select specific coals to be purchased, processed into coal-based premium fuels, and supplied to DOE users.
- o To coordinate the performance requirements of combustor developers under DOE-PETC contract and in-house efforts with the selection and supply of coals.

2.4 Task 2 Objectives

The objectives of Task 2, "Characterization of Coal Based Fuels", are as follows:

- o To procure representative samples of the coals selected in Task 1 and prepare them for characterization studies.
- o To obtain baseline analytical data for each of the parent coals.
- o To carry out bench-scale froth flotation cleaning test on each of the candidate coals to determine the yield of specification coal attainable from each.

- o To carry out detailed washability studies for each coal to determine the effect of particle size reduction on mineral matter liberation as well as the coal yield as a function of the specific gravity of the separation.
- o Using the available results of the characterization studies, to select a coal or suite of coals suitable for the preparation of the fuels to meet the specifications of the combustor contractors.

2.5 Task 3 Objectives

The objectives of Task 3, "Fuel Supply", are as follows:

- o To arrange for the capability, availability, and operation of suitable deep-cleaning coal wash circuit, coal/water slurry preparation plant, and micronizing/grinding facilities.
- o To purchase and arrange for the delivery of the appropriate coals for fuel preparation.
- o To clean the coals to meet the specifications necessary for the specific fuel needs, i.e., quality categories, such as slagging, non-slagging, industrial retrofit, residential/commercial.
- o To prepare the coal based fuels according to the specifications of the PRDA and as modified or requested by the combustor contractors.
- o To deliver the fuel to the combustor contractor on schedule.
- o To characterize each fuel prior to shipment to assure that the specifications are being met.

3.0 EXECUTIVE SUMMARY

Under the Department of Energy's Combustor Technology Program, approximately thirteen (13) contractors are developing atomizers and combustor systems (during 1986-1988) for use in residential, commercial, light industrial and industrial retrofit markets. Sufficient quantities of well-characterized coal-based fuels possessing appropriate specifications are required by the contractors for their developmental test programs. Fuels may be dry powdered coal or coal-liquid fuels. In support of these equipment development efforts, the team of Energy International and Dravo Engineering Companies is providing such fuels under DOE Contract No. DE-AC22-86PC90258.

During the fifth quarter of this contract (November 1, 1987 through January 31, 1988) the primary activities were involved with:

- o Revision of the fuel production plan, the cost plan, and the delivery plan due to major changes in the program instituted by PETC.
- o Test cleaning of the Upper Elkhorn #3 coal by Amax R&D Laboratories in Golden, CO and by EPRI at their coal cleaning test facilities in Homer City, PA.
- o Bench-scale froth flotation cleaning studies to optimize the yield of specification grade coal using the Upper Elkhorn #3 coal.
- o Processing and evaluation of the centrifugal washability data generated under Task 2 activities to determine its reliability and accuracy.
- o Continuation of the coal procurement, cleaning, fuel preparation and delivery activities.

A brief summary of these activities is as follows:

During this quarter a major review of the combustor contractors' current and projected fuel needs was conducted by PETC. This led to significant changes in the fuel amounts, the specifications and delivery schedules of the coal-based fuels required under this contract. The reduction in the amount of fuel and the relaxation of the ash specification for some major fuel users resulted in a reduction not only of the total quantity of fuel required but a sharp reduction in the amount of deep-cleaned coal needed. Also, some of the program activities external from this contract were delayed into the next fiscal year causing significant changes in the delivery schedules. Therefore, major changes in the fuel production and delivery schedules were carried out.

In an effort to determine if the cost of obtaining deeply cleaned coal could be reduced, a number of different companies with advanced coal cleaning facilities were contacted. Of those contacted, the Amax R&D Center in Golden, CO, the Iowa State University in Ames, Iowa, and the EPRI Coal Cleaning Test Facility at Homer City, PA were selected for further discussion. Samples of the Upper Elkhorn #3 coal were sent to both Amax and to EPRI for test cleaning. Complete test results have not yet been received

but verbal reports from both places indicate that EPRI only obtained industrial grade specification coal (1.3 - 1.5% ash) using their conventional circuitry while Amax obtained less than 0.9% ash using a combination of heavy media separation and two-stage froth flotation with additional grinding of the product between flotation stages.

Because of the cost projections associated with preparing deep-cleaned coal for the combustor contractors, Energy International authorized Dravo to perform bench-scale froth flotation studies to determine if improvements in pilot scale recovery could be achieved by using either alternative frothing reagents and/or changes in flotation operation conditions and thereby reduce the cost of producing deep-cleaned coal. In January 1988 it was learned that if additional flotation capacity could be added along with a change in flotation reagents that the yield of specification grade coal could be increased from the present 30-40% to above 60%. Final cost projections based on this new data have not yet been completed.

It was learned during the work-up of the washability data collected over the last several months that very inconsistent results were obtained for the fine coal fractions for which centrifugal washability was used to obtain separation. Almost all of the samples in the 200 x 270, 270 x 400 and 400 x 0 mesh size ranges would sink at 1.30 specific gravity and show little or no float at specific gravities of 1.30, 1.275 or 1.250. Currently, several different centrifugal washability methods described in the literature are being tried to determine if the washability data can be improved.

4.0 TASK 1 - ANALYSIS OF FUEL NEEDS

4.1 Subtask 1.1 Project Management

During this quarter, a major review of the combustor contractors' current and projected fuel needs was conducted by PETC. This led to significant changes in the amount, specifications and delivery schedules of the coal-based fuels required under this contract. The reduction in the amount of fuel and the relaxation of the ash specification for some major fuel users resulted in a reduction not only of the total quantity of fuel required but a sharp reduction in the amount of deep-cleaned coal needed. Also, some of the program activities external from our contract were delayed into the next fiscal year causing significant changes in the delivery schedules.

The original fuel production requirements and delivery schedule of deep-cleaned coal required the pilot plant to operate continuously May through November 1987 in order to reduce the potential production backlog which would occur during the second quarter of FY 1988. Upon notification of the change in clean coal requirements, the pilot plant was shut down in mid-November and remains shut down. The continuous plant operation generated over 76 tons deep-cleaned coal including over 200 drums of cleaned coal stockpile by mid-November. Fuel demand for deep-cleaned coal will be satisfied from this stockpile in the foreseeable future.

Because of the significant changes in the fuel supply program, revisions of the cost plan and delivery schedule were made. The revised fuel delivery schedule is shown in Appendix 8.1.

4.2 Subtask 1.2 - Coal Selection

Because of the changes and delays in the fuel procurement schedule, final selections of the coals for Vortec, TRW and the University of Tennessee Space Institute, discussed in last quarter's report, have been delayed. SAIC's requirement for a subbituminous coal was satisfied by sending one ton sample of a pulverized (80% minus 200 mesh) Kemmerer coal. In special arrangements with the University of North Dakota's Energy and Mineral Research Center (UNDEMRC) a coal-water-methanol slurry fuel will be prepared for AVCO Research by Amax R&D Center using a lignite coal (Buelah-Zap) cleaned to <1% ash. They had received permission from inventor-patent holder Leonard Keller to employ his coal-methanol water technology.

5.0 TASK 2 - CHARACTERIZATION OF COAL-BASED FUELS

Subtask 2.1 - Deep Cleaning of Coal

As discussed in the previous quarterly report, a number of institutions with deep coal cleaning capabilities were contacted to determine if the cleaning costs could be reduced. Of those contacted three were selected for further discussions. They were Amax R&D Center, Golden, CO, EPRI's Coal Cleaning Test Facilities in Homer City, PA, and the Ames Laboratory at Iowa State University in Ames, Iowa.

Four drums of the Upper Elkhorn #3 coal were shipped to Amax for test cleaning. Two drums were the washed run-of-mine (WRM) coal from Westmoreland Coal Company's Wentz cleaning plant in Wise County, Virginia and contained 2.5% ash. The other two drums were the deep-cleaned coal from Dravo's froth flotation (f.f.) circuit on Neville Island and contained about 1.3% ash. Amax cleaned the washed run-of-mine coal by heavy media separation and by froth flotation to compare the two techniques. Since the pre-cleaned coal was too fine for heavy media treatment, it was cleaned by froth flotation only. The summary of the tests are shown in Table 5.1.1.

Table 5.1.1

CLEANING TRIALS OF THE UPPER ELKHORN #3 COAL BY AMAX R&D CENTER

Feedstock		Method	Products	
Type	Ash (Wt %)		Ash (Wt %)	Recovery (%)
As-Received (WRM)	2.50	Float	0.91	58
Pre-cleaned (f.f.)	1.25	Float	0.85	82
As Received (WRM)	2.50	HMS*	1.25	45
As Received (WRM)	2.50	HMS/Float	0.87	57

* HMS = heavy media separation

It can be seen that by froth flotation cleaning ash levels of less than 1% were achieved for both the as-received and the precleaned samples with an almost 60% recovery of product in the case of the as-received sample. A combination of heavy media and froth flotation cleaning gave a product with the lowest ash content (0.87%) and a yield of nearly 60%. A standard acid leach was performed on the clean coal containing 1.25% ash. The acid leaching reduced the ash to 0.9% and also increased the ash fusion temperature. The effect of cleaning and acid leaching on the ash fusion temperatures is shown in Table 5.1.2.

Table 5.1.2

EFFECT OF CLEANING ON THE ASH FUSION TEMPERATURES
OF THE UPPER ELKHORN #3 COAL

Sample		Temperatures, °F			
		<u>Initial</u>	<u>Softening</u>	<u>Hemispher.</u>	<u>Fluid</u>
As Received,	Oxidizing	2640	+2700	+2700	+2700
	Reducing	2275	2575	2605	+2700
Float	Oxidizing	2410	2490	2515	2590
	Reducing	2260	2300	2360	2525
Float/Leach	Oxidizing	2630	+2700	+2700	+2700
	Reducing	2250	2430	560	+2700

Two truck loads of the Upper Elkhorn #3 coal were sent to the EPRI Coal Cleaning Test Facility at Homer City, PA for test cleaning in their facilities. One truckload (20 tons) was a sample of the feed (ROM) to the Wentz wash plant. Both samples were crushed to 1/4" x 0 and put through the conventional heavy media cleaning circuit. The preliminary results are illustrated in Table 5.1.3.

Table 5.1.3

CLEANING TRIALS OF THE UPPER ELKHORN #3 COAL
AT EPRI'S COAL CLEANING TEST FACILITY

Wentz Wash Plant Product (WRM):	<u>As Received</u>	<u>Cleaned</u>
% Ash	2.84	1.71
% Total Sulfur	0.63	0.55
Calorific Value (Btu/Lb)	15096	15298
Wentz Wash Plant Feed (ROM):	<u>As Received</u>	<u>Cleaned</u>
% Ash	43.40	1.56
% Total Sulfur	0.48	0.62
Calorific Value (Btu/Lb)	7816	15222

EPRI reported no yield values nor the specific gravity of separation used. It can be seen, however, that specification coal was not obtained using the conventional heavy media cleaning circuits. More complete data is to be furnished by EPRI.

Again, because of the drastic change in the fuel requirements and specifications, there is enough deep cleaned coal available for the remainder of the program as currently planned. Efforts to obtain a less expensive source of deep-cleaned coal were discontinued.

Subtask 2.2 - Washability Studies

Evaluation of the washability studies continued with mathematically recombining the 400 x 0 mesh fraction into the gravity separated fractions for determining liberation effects. However, it was discovered during these exercises that very inconsistent results had been obtained for the fine fractions for which centrifugal separation had been used. That is, almost all of the samples in the 200 x 270, 270 x 400, and 400 x 0 mesh size range would sink at 1.30 specific gravity and show little or no float at specific gravities of 1.30, 1.275 or 1.25 when centrifugal separations were used. It is well known that it is difficult to get good reproducible centrifugal washabilities and that no method has yet been accepted as a standard method. Therefore, additional studies were begun using different methods, which are described in the literature, to determine if a better separation technique could be used. The results of these tests and the completion of the Task 2 washability studies for the five coals should be accomplished during the next quarter.

Subtask 2.3 - Dravo Pilot Plant Reagent Optimization Study

Dravo was authorized to carry out bench-scale froth flotation studies to determine if improvements in pilot scale recovery could be achieved by using either alternative frothing reagents and/or changes in flotation operating conditions. Based on previous experience that the bench-scale test results show excellent correlation to the pilot circuit performance, any savings achieved due to reduction in reagent costs, reduction in operating costs and/or increased yield should be directly applicable to the pilot circuit and result in an overall project cost reduction.

This series of tests was warranted because less than two months into the contract earlier than expected fuel demands from several of the combustion contractors precipitated the need for Dravo to quickly identify the processing steps and procedures required to produce RCLI quality fuel. A highly selective flotation reagent with known frothing properties at specific optimum operating conditions was tested with the initial two drum test samples received from each feedstock supplier. From the list of six candidate feedstocks for the program, (determined and justified in Task 1.0 - Resource Study), only one feedstock, namely, Upper Elkhorn #3, showed the potential for being able to produce the desired quality level of less than 1.25% ash at greater than 60% yield. To meet the primary fuel demands, larger quantities of this feedstock were ordered and processing began immediately, duplicating the bench-scale operating conditions and producing the quality specification fuel. Since the feedstock shipments contained higher as-received ash levels than observed with the two drum test sample of Upper Elkhorn #3 coal, the resultant lower recovery levels which were being achieved with the pilot circuitry were expected.

From the onset of the project, Dravo vigorously attempted to improve production, and succeeded in upgrading the circuit capacity from 300 to 600 pounds per hour. Also, with the inclusion of the auxiliary set of flotation cells adapted to the circuit in late October 1987 yield at ash levels less than 1.10% were significantly improved. (Pilot production flowsheets illustrating the most recent circuit upgrade are exhibited in Appendix 8.3.

Circuit evaluation with relation to bench-scale test results showing potential improvement became a key concern. Because of the constantly fluctuating feedstock analysis, proportional trends in circuit recoveries resulted. This led to the belief that even though it might be proven that using specific technique and frother combination could achieve higher recoveries on a bench-scale basis, questions were raised as to whether comparable yield improvements could be realized with pilot scale equipment. To account for these concerns and also variations resulting from differences in liberation/grind, it was determined to test actual feed slurry as prepared by the pilot circuit. Washed ROM coal from shipment UE3-164-WRM-A was used as the circuit feedstock. The majority of this coal shipment had previously been deep-cleaned in the pilot circuit, therefore, direct yield at ash comparisons were easily established. A four-hour pilot test run was carried out in early January collecting fifty-five gallons of flotation feed for the bench studies.

The initial bench tests were run using duplicate pilot operating conditions including both standard reagent selection and dosage. Comparative results showed approximately 40% yield for both the pilot and bench processes. This confirmed the conceptual approach of the test program and further justified continuing the comparative reagent performance tests. Fifty-one bench-scale tests were performed in all using either the standard described flotation feed, bench ground coal from shipment UE3-165-WRM-A, or coarse circuit reject. Using the standard operating conditions with the typical feed and only varying reagent selection and dosage, the first 26 tests evaluated nine commercially available frothers, representing four reagent categories; namely alcohols, alcohol based, glycols and blends. Several of the frother reagents, representing all but the alcohols, showed only minimal yield improvement of less than five percentage points (corresponding to a 45 percent total overall yield) over the standard reagent selection used for production runs. The alcohol frothers due to low solubility in the coal water slurry could not achieve similar results. The results shown on Table 5.1 display the frother performance tests. The values shown were derived from statistical curve fitting interpretation of the actual data points. Each of the selected frothers were identified by one alphabetic character (A or B....I). Identification of the reagents is provided in Appendix 8.4. Note: These reagents are not proprietary; however because the study program objective was focused toward yield improvement potential as related to the Dravo facility and since the study was specifically designed around the Dravo pilot circuit, the results are applicable only to the stated operating conditions under which the circuit was engineered and therefore cannot be generalized.

Table 5.1

<u>Frother Reagent</u>	<u>Percent Cumulative Ash</u>			
	1.2	1.3	1.4	1.5
A	40.26	60.95	76.97	88.32
B	58.64	74.30	84.95	90.59
E	56.04	70.51	77.66	87.0*
F	51.08	62.67	74.25	85.84
G	61.57	73.82	83.41	90.35
I	56.88	71.5*	80.5*	88.0*

Note: * represents graphical versus mathematical interpolation

This type of curve fitting evaluation at equivalent ash points averages the test values to minimize the effect of a single data point and provide a more realistic viewpoint of the reagent's performance. Those reagents tested but not listed on Table 5.1 indicate that only a single test was performed resulting in a data point which closely resembled a typical poor performance reagent category and therefore was not further evaluated. Figures 5.1 and 5.2 show a comparative view of all tests performed on the typical flotation feed. As shown, the data point spread accounts for a yield differential of nearly thirty-five percentage points throughout the specified ash range for the reagents tested. These graphs also emphasize the need to run this series of optimization tests to select the highest performance frother for the specific coal feed type.

A second series of tests using a selected conditioner, identified as "J", was added prior to the frother reagent and found to further improve recovery levels at equivalent ash contents. Both the alcohol-based reagents and the reagent blends showed more significant yield improvements with the addition of this selected conditioner. Even though the alcohol reagents also tended to show yield improvement with the conditioner, these improvements were less than that achieved with the standard reagent. The tested glycol reagent was detrimentally affected by the conditioner.

Tests were then run to evaluate the optimum dosage of the selected conditioner with the two reagent types that had shown improved performance. These results showed that at incremental dosages above 0.1 lbs. per ton of feed, the ash versus recovery curve was shifted such that quality control could be a primary concern. This discovery limited further testing to be run with only 0.1 lbs. per ton conditioner. The alcohol based frother "E" in combination with 0.1 lbs. per ton conditioner "J" showed the best yield improvement in the range of 35 percent over standard operating practice, which corresponds to an overall yield of 54.0 percent.

Two additional approaches were attempted in order to further improve flotation performance. These included manipulating cell retention and percent feed solids. Mixed results were concluded. Maximum performance efficiency was found to be achieved at higher cell retentions with lower reagent dosages. This negated the probability of increasing reagent dosage for improved yield performance while simultaneously reducing the amount of time allotted for froth collection in order to control quality levels. As shown on Figure 5.3, this concept proved ineffective and is not considered viable. However, the study of the affect of percent solids together with the

selected reagent combination did indicate a potential increase of 6 percentage points of yield over maximum yield achieved only using the "E" + "J" combination, which relates to an overall yield of 60 percent. This additional yield can be realized but, either circuit production would have to be reduced to 410 lbs. per hour feed or 31 gallons of flotation cell capacity would have to be added to the circuit. For maximum cost benefit the latter would be more economical.

The developed reagent combination technique at the standard percent feed solids was also applied to two additional feeds, namely primary reject and feedstock UE3-165-WRM-A. The UE3-165-WRM-A sample represented the subsequent feedstock shipment of Upper Elkhorn #3 to Dravo from the supplier. Laboratory analysis showed this sample, having a 3.00 as-received ash content, to be more representative to that experienced with since the beginning of deep cleaned production in April 87. Results showed similar yield improvements of nearly 16.5 additional percentage points with this feed over the average obtained during the production runs.

Processing the primary reject sample, which represents coarser material not crushed to minus 1/8 inch by either the hammer or ball mill and corresponds to only three percent of the circuit feed, using the developed technique resulted with between 30-40 percent yield at RCLI quality. This coarser material, which is generally rejected and analyzed at a higher ash content, if reprocessed as a latter secondary step could increase the overall yield an additional 1-1.5 percent at residential quality levels.

In summary, a maximum yield improvement of nearly 54 percent or a 61.5 percent yield is possible with the Dravo pilot circuit at RCLI quality if minimal circuit modifications including added flotation capacity and changes in reagents/dosages, are implemented. If costs prohibit the installation of additional banks of flotation cells or if the units were not readily available, then even at the higher feed rate with only modifications regarding reagents/dosages, an overall improved yield of 55.5 percent could be realized at Dravo. Because similar improvement results were achieved with the higher ash feedstock, these improvement potentials are not feedstock limited, but should be able to be applied to the overall production scenario significantly reducing production costs.

FIGURE 5.1
CLEANER STAGE FLOTATION DATA BY TEST NO.

FIGURE 5.2
CLEANER STAGE FLOTATION DATA BY REAGENT

TIME STUDY CLEANER- 2

6.0 TASK 3.0 FUEL SUPPLY

6.1 Production Facilities

The matrix of fuel requirements as shown in Table 6-1 had set into motion several contracted facilities to supply the desired fuel forms. No single organization has yet been found or is expected, to provide deep cleaning capabilities, dry pulverizing, dry micronizing and coal slurring technology unless a new plant is constructed with a primary goal of supplying fuel for this contract. Specific selections of contractors used to date and facilities are described.

Table 6-1

BITUMINOUS COAL FUEL FORMS REQUIRED FOR THIS PROJECT

	Dry Coals		Coal-Water Fuels	
	<u>Pulverized</u>	<u>Micronized</u>	<u>Pulverized</u>	<u>Micronized</u>
Deep-Cleaned	X	X	X	X
Standard	X	X	X	X

6.1.1 Deep Cleaned Coal

Following DOE approval on February 6, 1987, Dravo initiated the design, modification and operation of their pilot facilities for the production of deep cleaned coal meeting the low ash and low sulfur requirements of between 0.8 and 1.0 lbs. ash per million Btu's and 0.6 to 0.8 lbs. sulfur per million Btu's. The basic circuit consists of a four phase operation including grinding, classification, beneficiation, and drying.

The Dravo pilot circuit was idled, because of project changes and lack of demand by combustion contractors, for about 2 1/2 weeks during the month of November and idled for both December and January with the exception of the four hour test run on January 6, 1988 to supply feed coal slurry for the flotation optimization study. During the quarter prior to November 6, 1987 the circuitry had operated on single and double shift bases.

6.1.1.1 Reblending

It was observed that since July 23, with the start-up of the thermal disc processor, 12 drums of generated deep cleaned product did not meet the specified quality level. This, added to the unforeseen project delays due to redirected needs of several of the combustor contractors, initiated the technique of "reblending" to improve productivity. The procedure, essentially dealt with reslurrying a combination of "spec" and "non-spec" product drums in a batch mixing tank, surface dewatering the slurry on a disc filter, and thermally drying the filter cake in the Bethlehem disc processor. Identified potential drums which could utilize this supplemental technique included (1) over-specification ash levels, (2) higher than the desired moisture level of 3.5 percent for the production of dry micronized fuels, and (3) cooldown drums. The latter category included composites of partially dried

product, produced during the required 45 minutes per day cooldown cycle of the thermal disc processor. Additional feed to the processor was necessary during this period to (1) prevent over-oxidation and ignition of residual coal in the dryer upon shutdown and (2) rapidly reduce the temperature of the dryer from 410 to a safer level of 250 degrees Fahrenheit. Fifteen drums of product were generated by reblending processing five cooldown, four over ash specification and the remainder having moisture levels in excess of 5 percent.

6.1.1.2 Screw Conveyor

Inconsistent deep cleaned product moisture levels were reported by Schutz-O'Neil a division of Jacobson, Inc. (responsible for dry micronizing) during October. Upon investigation, it was determined that condensate was forming inside the plastic drum liners and after storage settling to the exterior bottom portion of the product drums. Apparently, the moisture was due to the temperature differential between the heated coal and drums. This moisture level was consequently wetting the coal surfaces and resulting in inconsistent grinding. Microtrac analysis was performed on the resultant products confirming the postulation.

During in-house discussions at Dravo, a method was devised utilizing a conventional screw conveyor to pre-cool the coal surfaces. By increasing the non-heated particle retention time prior to discharging into the drum additional heat could be dissipated. A screw conveyor unit with transition adapter for the Bethlehem unit was ordered and received by late October for testing. The unit was installed onto the dryer and electrically serviced upon arrival. Unit purchase was contingent upon a performance warranty, based solely at the discretion of Dravo to determine if the unit would meet the specific application requirements.

Initial on-line testing, to define temperature reduction efficiency, showed a forty degree differential; but, after allowing the screw conveyor to reach a temperature equilibrium condition, the differential was reduced to only 20-25 degrees Fahrenheit. To increase the temperature reduction differential efficiency, the existing cover plate was removed and replaced with a redesigned and in-house fabricated cover plate, modified with (4) two inch diameter negative pressure vents for heat displacement to the facilities dust collector system. Modifications and final installation were completed by November 16, with the lack of scheduled production and existing stockpile of deep cleaned coal, final testing was not attempted until January 7, 1988.

Because of the necessity to operate the pilot circuit producing feed slurry for the flotation optimization tests (Section 5.0), the opportunity was also taken at the same time to test the modified screw conveyor. However, because an insufficient quantity of froth concentrate was produced during the test run to adequately test the screw conveyor performance, the batched feed to the dryer was supplemented with reblended slurry. On January 7, the unit was fed with dryer product for a period of four hours. After reaching equilibrium, a differential temperature between the discharges of the dryer and screw conveyor was consistently measured at 100 degrees Fahrenheit. With a 140 degree temperature of deep clean fine coal loading into the product drums no condensate was observed. Even after complete cooldown of 12-24 hours no condensate was detected. This unit would eliminate

the problem of "caking" and therefore it was purchased in preparation of future demands of dried deep-cleaned coal for micronized fuel.

6.1.1.3 Dryer Maintenance

The Bethlehem thermal disc processor, received and put into operation at Dravo by August 1, 1987 performed remarkably well for nearly 1.5 months until it was noted that the bearings supporting the disc mounted shafts and the hot oil supply pump required servicing. Because of the component arrangement on the pilot unit, access was limited and imposed restraints. During the quarter, six of the ten bearings were replaced due to excessive wear. The remaining four located near the center of the unit appeared to be in operable condition.

The hot oil recirculating pump was removed from the dryer during September due to leaks at the mechanical seals, dismantled, and seals replaced by the pump manufacturer's vendor. These steps were necessary because of the close tolerances required during realignment. During October after being reinstalled, the pump continued to show signs of minor leakage. Under agreement with the vendor, he proposed to realign the pump without charge. During November, because the unit was not currently being operated due to the current clean coal inventory and lessened demand by the combustion contractors, the pump was again removed from service and submitted to the vendor. A seven day turn-around resulted. During December, the hot oil pump was again reinstalled.

Since the pilot plant was not operated until January, 1988 with the four hour test run, Dravo had anticipated that the pump was fully repaired. Unfortunately, after start-up apparently due to a chronic mis-alignment problem, the unit continued to leak oil for a period of nearly one week after shutdown.

6.1.2 Dry Pulverized/Micronized Coal

A purchase order was issued to Jacobson Inc. (of which Schutz O'Neill is a division) by Dravo in July, 1987 to supply micronizing services for the DOE fuel supply project. During this reporting quarter, Jacobson had produced nearly 7.4 tons of micronized coal from the deep cleaned coal generated by Dravo. Prior to the reductions in the amount of coal required by the combustion contractors, Jacobson had stated their desire to work with EI/Dravo in modifying their discharge system for direct loadout into tank trucks in order to satisfy the needs of TRW for their dry micronized fuel supply. Jacobson is supposedly investigating the cost estimates associated with the required modifications, but to date have not yet replied.

6.2 Fuel Production

6.2.1 Deep Cleaned Coal

During the quarter, only shipment UE3-165-WRM-A of the Upper Elkhorn #3 coal from Westmoreland Coal Company's Wentz Plant was shipped to Dravo for use in the preparation of deep cleaned coal. It was received at Dravo in early November. That shipment has not yet been processed because of diminished and rescheduled demands. Also, about three tons of washed ROM shipment UE3-164-WRM-A, delivered in late October, was also awaiting processing.

During the quarter, the Dravo pilot circuit had only been operated three full shifts producing a total of 17 drums or approximately 1.7 tons of deep cleaned coal. The dry ash content of the combined product averaged 1.16 percent. This production rate, assuming 45 minutes cooldown per shift for the Bethlehem thermal dryer, calculates to 156 lbs. per hour. It is to be noted that this production value is only an estimate based on full shift operation, not including unscheduled downtime, and therefore should not be associated with a yield or recovery value.

Average Quarterly Values

	<u>Production Rate</u>	<u>% Ash</u>
April 87 - July 87	124	1.33
August 87 - October 87	146	1.35
November 87	156	1.16

As shown in the above table, the production rate of clean coal was increased and the quality of the product improved by reduction of ash. The notable change occurred following installation of the auxiliary set of flotation cells in late October. These improvements might also be attributed to the feedstock coal shipment. The coal used during that period was lower in ash content as delivered from the Wentz plant to the Dravo pilot plant (UE3-164-WRM-A).

Analysis of the last full stream continuous production run during November, had shown calculated yields for two of the three days of approximately 40 percent at an average dry ash content of 1.12 percent. Third day performance yielded an average ash content of 1.29 percent.

After November 6 via "reblending", an additional 11 drums or 1.1 tons of deep cleaned coal were generated from over-specification product drums. The reblended product averaged 1.32 percent dry ash. All produced coal during the quarter met the RCLI specification of less than 1 lb. ash content per million Btu's.

Deep cleaned coal production was not attempted during December 1987 or January because the clean coal inventory exceeded 200 drums during entire period and because the next future shipment was not scheduled until late January 1988. The only exception to this was the four hour test run in January for the production of feed slurry prepared for the flotation optimization study.

Analysis of the samples collected during the tests run showed recoveries of premium quality deep cleaned coal at approximately 39 percent. The average quality level of this production was 1.02 percent dry ash. After mixing the froth concentrate produced during the four hour test run with the reblended slurry the resultant three drum product averaged 1.31 percent dry ash.

During January a clean coal drum inventory was made of all production on site at Dravo Research Center on Neville Island-Pittsburgh. Several distinct grades were identified and classified according to their ash and moisture contents as follows:

53 drums of 1.21% ash and 1.72% moisture coal, useful for preparation of a residential grade micronized coal.

103 drums of 1.38% ash and 2.12% moisture coal, useful for preparation of a commercial grade micronized fuel.

90 drums of a 1.20% ash and 7.16% moisture coal useful for the production of residential grade coal-water slurry.

45 drums varying in ash content from 1.29 to 2.50% ash and various moisture levels.

Deep cleaned coal production since April, 1987 through January 1988 is 76.4 tons.

6.2.2 Dry Powder

During November, Jacobson Inc. received 4 drums of deep-cleaned coal from Dravo for the production of dry micronized fuel. One-half of the total production was scheduled for AVCO Research and the other for TECOGEN. This residential quality coal (i.e. less than 0.8 lbs. ash per million Btu's) was micronized to specification and delivered to Tecogen and AVCO (2 drums each) in mid-December. Prior to shipment from Jacobson, aliquot samples were collected from each and shipped to Dravo for microtrac analysis. Both samples exhibited grind levels well within specifications having mean grain sizes less than 8 microns. In addition, 5 tons of deep cleaned coal produced for the PETC in-house program will be reground to a topsize of 12 microns. These shipments were delivered the first week of January, 1988.

In addition, 5 tons of deep cleaned coal produced for the PETC in-house combustor program was requested. Comparatively, the desired fuel form would be significantly finer than previously received, having a topsize of 22 versus 38 microns. Also, the desired fuel would be 90 percent minus 12 versus 90 percent minus 22 micron as previously shipped. Prior to the receipt of this request, 5 tons were already micronized to the original specification, therefore to achieve the desired grind, a regrind was necessary.

Discussions between Dravo, EI, and Jacobson led to the thinking that a finer grind level may be achieved by including the oversize recirculating loop but would represent the maximum achievable particle reduction capabilities by Jacobson. Initially however, a test run with two drums was made through the micronizing circuit without a recirculating load. A test sample was prepared from the run and microtrac analysis at Dravo confirmed that this attempt only achieved a mean grain size reduction of 9 percent passing 16 microns. After discussing this potential product with Wan Fu of PETC, an agreement was reached. Mr. Fu stated that even though the grind was slightly coarser than desired, a sufficient difference was noted between the previous tested micronized product exhibiting a characteristic grain size of 90 percent passing 22 microns and the proposed tested product to warrant the

additional combustion testing. He then approved shipment. A subsequent test sample, prepared midway during the production process, and a composite sample were also analyzed for verification. These samples showed 15.0 and 14.8 microns respectively at the 90 percent passing level.

Final shipment was delivered to PETC by the first week of January 1988.

6.2.3 Coal Water Fuels

No coal-water slurry fuels were prepared or shipped during this quarter.

6.3 Shipments

During the month of November, the following coal shipments were shipped from Dravo to the identified users:

- o UE3-166-WRM-D 2 drums approximately 500 lbs. of as-received washed ROM Upper Elkhorn #3 coal to AMAX
- o UE3-167-DCC-D 475 lbs. 1.075% avg. dry ash to Schutz-O'Neill for AVCO
- o UE3-168-DCC-D 472 lbs. 1.185% avg. dry ash to Schutz-O'Neill for Tecogen
- o UE3-173-DCC-D 11 drums (2382 lbs.) commercial/light industrial grade deep cleaned coal (1.55 average ash content) was shipped to OXCE for production of slurry for Tecogen and ARC

During the month of November the following fuel shipments were made to the DOE combustor contractors:

- o KMR-159-ROM-N 10 gallons of western subbituminous Kemmerer coal was shipped from UNDERC to EI
- o KMR-160-PCO-N 1 ton and 5 gallons of pulverized 80% minus 200 mesh processed Kemmerer coal was shipped from UNDERC to SAIC and EI

During the month of November the following coal shipments were made directly from the Westmoreland Coal Company's Wentz mine and cleaning plant in Wise County, Virginia to the EPRI coal cleaning facility in Homer City, PA.

- o UE3-011-ROM-A 20 tons of high ash ROM coal from the Wentz #1 mine.
- o UE3-012-WRM-A 20 tons of washed (3.5% ash) coal from the Wentz cleaning plant.

During the month of December the following fuel shipments were made to the DOE combustor contractors:

- o UE3-169-MCO-S 2 drums of residential grade deep cleaned micronized coal averaging 1.075 percent ash was shipped from Jacobson to AVCO

- o UE3-170-MCO-S 2 drums of residential grade deep cleaned micronized coal averaging 1.85 percent ash was shipped from Jacobson to Tecogen

During the month of January the following fuel shipment was made to the DOE combustor contractors:

- o UE3-172-DCC-D 3 drums (661 lbs.) of minus 100 mesh pulverized commercial/light industrial grade coal averaging 1.49% ash was shipped from Dravo to Catholic University for their modeling studies

During the month January the following fuel shipment was made to the fuel producer:

- o UE3-173-DCC-D 11 drums (2382 lbs.) commercial or light industrial grade coal (1.55% average ash content) was shipped to OXCE for the production for slurry for Tecogen and Atlantic Research Corporation.

An updated sample shipment log is given in Appendix 8.2.

7.0 FUTURE PLANS

Due to a substantial reduction in the required amounts and associated revised fuel specifications of the coal-based fuels, Dravo's processing subcontract was terminated. During the month of February, management meetings were held to establish finalization procedures for contract closeout deliverables. This included items such as raw coal, stockpiled deep cleaned coal, parent coals, outstanding laboratory analyses, production logs, coal inventories and finalization of reports. In addition, termination orders were issued to Jacobson Inc. previously used for dry pulverization services and to Dravo Lime Company for dismantling the pilot circuit, returning government property and leased equipment, and general facility clean-up. A closeout estimate was submitted to EI covering all of the above items.

By request of Energy International, the stockpiled twenty-three ton shipment of washed run-of-mine Wentz coal, from Westmoreland Coal Co.'s cleaning plant, delivered to Dravo on November 3, 1987 and identified as UE3-165-WRM-A, was crushed to minus 1/8 inch then stored in lined drums, inerted with nitrogen, weighed, banded and labeled for shipment to EI.

A complete Dravo inventory of both the deep cleaned coal production since April 1987 and the crushed raw coal production was submitted to EI in both hard and soft copy form aiding in future revision capability.

8.0 APPENDICES

8.1 FUEL DELIVERY SCHEDULE

SCHEDULE OF DELIVERIES of COAL S L U R R I E S
(including quantity and properties as of 1-25-88)

RWG 1-28-88
filisiry0178
pg 1 of 2

COMBUSTION CONTRACTOR (Application)	COAL WATER SLURRY PROPERTIES	Notes	ACTUAL DELIVERIES				FY 88				FY 89	
			FY 87 & FY 88				JANUARY	FEBRUARY	MARCH	Third Quarter	Fourth Quarter	12 months
AVCO Research Lab (residential) (pulp combustor)	lignite, VMSX, 30HX20 <1% ash, 0.31% S, 41 AFT 10000 Btu, FC45X, 701 solids, low vis, top 10u revised Jun 23, Nov 18	specs & schedule per letter Feb 9	1000 lbs lignite-methanol-water fuel from UND-EMRC mid Feb. delivery	none	none	none	none	none	none	none	none	none
COMBUSTION ENGINEERING (Industrial retro)	3 to 4% ash, 150u 2600 AFT, .71% S, 57% FC 13500Btu; 44% solids >301u, <2.2FR	revised schedule UE3-139-UCH-F Sept 11, 7500 gallons to be used at MIT 99% -3u topsize UE3-138-CWF-F Oct 27, 1200 gal to be used at MIT standard grind ((149u) CWF	none	none	none	7500gal 3-4% ash, <15u topz	15,000gal 3-4% ash (<149u topz	??	??	20,000gal	??	??
ENERGY & ENVIRONMENTAL RESEARCH, Inc. (residential)	70% solids, 5u NP8 40u top, vis 1000cp 1% ash, 0.5% S, 45% VM	per ltr Apr 3 UE3-116-UCH-F, Jun 18, 55 gal UE3-120-CWF-F(MTC) Nov 11, 1 drum UE3-121-UCH-F(MTC) Nov 11, 1 drum	none	none	none	none	none	none	none	200 gal MCM	??	??
MTCI (residential)	<1% ash, micronized 10u seass, 30u topz	65-70% solids UE3-116-UCH-F, Jun 18, 220 gal	none	none	none	none	none	none	none	2000 lb 30u topz 10u seass (res. Nov. 1 delivery	2000 lb 30u topz 10u seass (res. Nov. 1 delivery	2000 lb 30u topz 10u seass (res. Nov. 1 delivery
(Industrial)	<1% ash, micronized 10u seass, 30u topz	65-70% solids slagging combustor UE3-121-UCH-F, Jun 29, 600 gal	none	none	none	7,500 lb 30u topz, 10 seass (indus.) April 1 delivery	10 seass	10 seass	10 seass	2000 lb 149u topz 30u seass (res. Nov. 1 delivery	2000 lb 149u topz 30u seass (res. Nov. 1 delivery	2000 lb 149u topz 30u seass (res. Nov. 1 delivery
(residential)	<1% ash, pulverized 30u seass, 149u topz	65-70% solids UE3-120-CWF-F, July 27, 600 gal	none	none	none	none	none	none	none	2000 lb 149u topz 30u seass (res. Nov. 1 delivery	2000 lb 149u topz 30u seass (res. Nov. 1 delivery	2000 lb 149u topz 30u seass (res. Nov. 1 delivery
(Industrial)	<1% ash, pulverized 30u seass, 149u topz	65-70% solids slagging combustor UE3-121-UCH-F, Jun 29, 600 gal	none	none	none	none	none	none	none	2000 lb 149u topz 30u seass (res. Nov. 1 delivery	2000 lb 149u topz 30u seass (res. Nov. 1 delivery	2000 lb 149u topz 30u seass (res. Nov. 1 delivery
NAVY/CU at NCEL in CA (commercial) (combustor develop.)	70% solids, (2000cps 250 recip sec ultrafine coal)	awaiting written specs & schedule NCEL in CA	none	none	none	none	none	none	none	2000 lb 149u topz 30u seass (res. Nov. 1 delivery	2000 lb 149u topz 30u seass (res. Nov. 1 delivery	2000 lb 149u topz 30u seass (res. Nov. 1 delivery
NAVY/CATHOLIC UNIVERSITY (commercial - modeling)	3-7% ash, low sulfur	Wash.D.C specs & schedule per ltr 11-30-87 drum quantities	none	none	none	none	none	none	300 gal UE3-CWF March thru August	1500gal LMF Sept 88 to Dec 89	1500gal LMF Sept 88 to Dec 89	1500gal LMF Sept 88 to Dec 89
PETC 1H-HOUSE (BILBERT/COMMONWEALTH) (Industrial & commercial boilers)	eastern bituminous <0.4% S, >50% solids 500-700cp 100% -100 mesh	ELC-108-CWF-F, April 16, 350 gal UE3-117-CWF-F, May 27, 2000 gal UE3-120-CWF-F, July 27, 110 gal UE3-137-CWF-F, Aug 19, 2000 gal	none	none	none	none	none	none	300 gal UE3-CWF March thru August	1500gal LMF Sept 88 to Dec 89	1500gal LMF Sept 88 to Dec 89	1500gal LMF Sept 88 to Dec 89
TECOSEN (residential)	>55% solids, <1% ash <1% S, 5u seass, 20u topz >2350 AFT	letter 4-29-87 used at ~1 gallon/hr	none	none	none	200 gal UE3-MCM	200 gal UE3-MCM	200 gal UE3-MCM	200 gal UE3-MCM	600 gal UE3-MCM	600 gal UE3-MCM	600 gal UE3-MCM

SCHEDULE OF DELIVERIES of COAL S L U R R I E S
(Including quantity and properties as of 1-25-88)

RNG 1-28-88
fllslslr0128
pg 2 of 2

COMBUSTION CONTRACTOR (Application)	COAL WATER SLURRY PROPERTIES	Notes	FY87 & FY88				FY 88				12 months
			ACTUAL DELIVERIES	JANUARY	FEBRUARY	MARCH	Third Quarter	Fourth Quarter			
TRW (Industrial)		NO SLURRY									
Vortec (sub BCKL)	1 to 8% ash Iron is concern	slurry next year needs coal specs now								1000 gallons	
ATLANTIC RESEARCH	Residential grade				55 gal res. grade UE3-HCN same as Tecogen						

SCHEDULE OF DELIVERIES of C O A L
(including quantity and properties as of Jan 25)

RMB/1-28-88
1111coal0128
page 1 of 2
(---FY 89 ---)

COMBUSTION CONTRACTOR (Application)		Actual deliveries		FEBRUARY		MARCH		THIRD QTR		FOURTH QTR		12 months	
		Notes	COAL PROPERTIES		JANUARY								
AMCO Research Lab (residential)		letter Feb 9 specs; schedule revised June 25 & August 6 & Nov 13	lignite < 0.5% ash 0.35 10,000 Btu/lb 35 micron topsize 12u screensize		1000 lbs. ligatite via UMD EMC (chea. cleaned therm. dried & micronized) old Feb. delivery	none	none	none	none	none	none	none	none
			subbituminous MCO same specs		deleted on Nov 13								
COMBUSTION ENGINEERING (Industrial) (Sorbent add'n 1.8t/hr during injection).		same coal as for slurry; CE to grind it at their expense to 10u RMD	dry micronized <6% ash (UE3 Coal)		none	none	none	70 ton UE3, same coal as CUF May 1 delivery	none	none	none	none	none
			high volatile A bituminous 40u topsize 10u screensize v2700 ash fus. temp. 8 <0.5% <2% ash		UE3 & UE2 are acceptable	none	none	none	none	none	none	none	none
ENERGY & ENVIRONMENTAL RESEARCH, Inc. (residential)					UE2-126-MCO-C June 8, 220 lbs. UE3-133-MCO-C June UE3-143-MCO-S Sept 9, 220 lbs. UE3-153-MCO-S Sept 23, 650 lbs. 90% -20u	none	none						
						none	none						
MTC (residential) & Industrial)			< 1% ash dry micronized 30u topsize, 10u screensize		UE3-123-MCO-C July 22, 5412 lbs.	none	none	5000 lb Industrial DCC <30u topsize, 10u screensize June 1 delivery to CA	none	2000 lb residential DCC <30u topsize, 10u screensize Oct 1 delivery to CA	none	2000 lb residential DCC <30u topsize, 10u screensize Oct 1 delivery to CA	2000 lb residential DCC <30u topsize, 10u screensize Oct 1 delivery to CA
						none	none						
NAVY at NCEL in CA (commercial) (combustion development)			<1% ash dry pulverized 149 topsize, 30u screensize		UE3-113-PCO-C May 12, 2000 lbs. UE3-133-PCO-C July 16, 6000 lbs.	none	none	5000 lb Industrial DCC <149u topsize, 30u screensize June delivery to CA	none	2000 lb residential DCC <149u topsize, 30u screensize Oct 1 delivery to CA	none	2000 lb residential DCC <149u topsize, 30u screensize Oct 1 delivery to CA	2000 lb residential DCC <149u topsize, 30u screensize Oct 1 delivery to CA
			bituminous <18 ash/RM Btu 2 to 4 RM Btu/hr (0.38 S/White, >2600° AFT 40u topsize) 100% -400 mesh 14000 Btu/lb			none	none						
CATHOLIC UNIV. at Wash. D.C. bituminous 1-10% ash (commercial - modeling studies)		see ltr. 11-30-87			UE3-172-MCO-S Jan 26, 500 lbs.	none	none	1500 lbs. PCO UE3-MRM	1500 lbs. PCO UE3-MRM	15,000 lbs PCO, UE3-MRM Sept. thru August	none	15,000 lbs PCO, UE3-MRM Sept. thru August	15,000 lbs PCO, UE3-MRM Sept. thru August
						none	none						
PETC IN-HOUSE & (GILBERT/COMBUSTION HEALTH) (Industrial boiler)		UE2 acceptable. Sept. want same coal used by combust. contract.	low % ash micronized bituminous		UE2-114-MCO-C May 4, 5 tons UE2-126-MCO-C June 11, 5 tons UE2-125-MCO-C June 24, 5 tons UE3-143-MCO-C Sept 2, 8.8 tons UE3-143-MCO-C Sept 9, 4.4 tons UE3-152-MCO-S Jan 12, 10135 lbs	none	none	none	none	none	none	none	none
						none	none						
Science Applications IC & (wet oxidation)		2 coals PC (80% <200 mesh) M2 inserted in bags in dress	lignite/subbituminous PC (80% <200 mesh) M2 inserted in bags in dress		B7P-117-PCO-M Aug 19, 1 ton KMR-160-PCO-M Nov 11, 1 ton	none	none	none	none	none	none	none	none
						none	none						
Trocen & (residential)			bituminous <1.5% ash ash in bag		UE3-154-MCO-S Sept 23, 240 lbs. UE3-170-MCO-S Oct 1, 240 lbs.	none	none	none	none	none	none	none	none
						none	none						

SCHEDULE OF DELIVERIES of C O A L
(Including quantity and properties as of Jan 25)

(-----FYs 87 & 88-----) (-----FY 88-----)

CONTRACTOR (Location)	COAL PROPERTIES	Notes	Actual deliveries	JANUARY	FEBRUARY	MARCH	THIRD QTR	FOURTH QTR	12 months
Space Institute (trial) (not injection)	eastern bituminous, 2.5-3.0% sulfur, 5-10% ash T250 = 2400-2500 deg. low to high slagers	awaiting firm schedule		none	none	none	none	40 to 50 tons over 5 months maybe in pneumatic discharge tracts	
Space Institute (trial) (not injection)	subbitu's & bituminous low ash (11), 7% typ AFT 2400 non-slagger	need to confirm if DCC access.	UES-150-MCO-5 Oct 5, 2 tons for shakedown run 853-22u	none	none	none	46 tons deep (?) cleaned bituminous over 7 months	4 tons subbituminous	
Space Institute (trial) (not injection)	eastern bituminous 1 to 8% ash, 5-10% iron 70% - 200 mesh; probably PA coal not deep cleaned	coal not yet identified		none	none	none	10 tons	10 tons	10 tons

8.2 SAMPLE SHIPMENT LOG

Table 1

Serial No.	Sample I.D.	Previous Sample I.D.	From	To	Quantity	Description	P.O.#	Date Shipped	Hauler
000-010	unassigned								
011	UE3-011-WRH-A	RMH coal	Westmoreland Coal Co.	EPRI	~20 tons	high ash RMH coal for cleaning trials at Homer City	EI-282	10/20/87	Five Star
012	UE3-012-WRH-A	parent	Westmoreland Coal Co.	EPRI	~20 tons	cleaned coal from Wentz prep plant	EI-282	10/20/87	Five Star
013	UE3-013-WRH-H	parent	EPRI	Bravo	small samp.	for analytical check			
014	UE3-014-WRH-H	parent	EPRI	EI	small samp.	for analytical check			
015-068	unassigned								
089	UE2-089-WRH-A	parent	Central Coal Co.	Bravo	11 tons	Off-spec, Lower Cedar Grove, Virginia Energy mine #1085	EI-125	2/19/87	
090	LEL-090-WRH-A	parent	MAPCO	Bravo	2 drums	Pond Creek Coal, Pontiki plant			
091	LEL-091-WRH-A	LEI-090-WRH-A	Bravo	E.I.	5 gal	Pond Creek Coal, Pontiki plant, 1/8x0 for washability studies			
092	CB0-092-WRH-A	parent	Westmoreland Coal	Bravo	2 drums	Colorado, Coal Bed D			
093	CB0-093-WRH-A	CB0-092-WRH-A	Bravo	E.I.	5 gal	Colorado, Coal Bed D, 1/8x0 for washability studies			
094	UE2-094-WRH-A	parent	Central Coal Co.	Bravo	11 ton	ZI ash, Lower Cedar Grove, Virginia Energy mine #1085			
095-099	unassigned								
100	UE3-100-WRH-A	parent	Westmoreland Coal	Bravo	2 drums	Taggart Seam			
101	UE3-101-WRH-B	UE3-100-WRH-A	Bravo	E.I.	5 gal	Taggart Seam, 1/8x0 for washability studies			
102	UE1-102-WRH-A	parent	Old Ben Coal Co.	Bravo	2 drums	Alsea Seam			
103	UE1-103-WRH-B	UE1-102-WRH-A	Bravo	E.I.	5 gal	Alsea Seam, 1/8x0 for washability studies			
104	UE2-104-WRH-A	parent	Beth Energy Coal Co.	Bravo	2 drums	Lower Cedar Grove			
105	UE2-105-WRH-B	UE2-104-WRH-A	Bravo	E.I.	5 gal	Lower Cedar Grove, 1/8x0 for washability studies			
106	UE3-106-WRH-A	parent	Westmoreland Coal	Bravo	20 ton	3.5% ash coal, Wentz plant, Taggart seam (1st shipment)	EI-118	4/13/87	
107	ELC-107-WRH-F	parent				Elk Creek Coal from DICE			
108	ELC-108-WRH-F	ELC-107-WRH-F	DICE	PETC	350 gal	Std. grind slurry	EI-151	4/16/87	
109	UE3-109-WRH-A	parent	Westmoreland Coal	Bravo	23 tons	~3.5% ash, Taggart Seam, Wentz Plant	EI-162	5/1/87	
110	UE3-110-WRH-A	parent	Westmoreland Coal	Bravo	26 tons	<6% ash, Taggart Seam, Holton Plant	EI-167	5/7/87	

Table 1 (Cont.)

Update: 15-Apr-88

file:lst4a

Serial No.	Sample I.D.	Previous Sample I.D.	From	To	Quantity	Description	P.O.#	Date	
								Shipped	Hauler
111	UE3-111-WRN-B	UE3-110-WRN-B	Dravo	OICE	26 tons	From UE3-110-WRN-A	EI-168	5/11/87	
112	UE3-112-DCC-B	UE3-106-WRN-A	Dravo	Penn Rilliton	2000 lbs	Deep cleaned UE3-106-WRN-A	Dravo	5/6/87	
113	UE3-113-PCB-C	UE3-112-DCC-B	Penn Rilliton	MTCI	2000 lbs	Pulverized UE3-112-DCC-B	EI-176	5/8/87	
114	UE2-114-MCD-C	UE2-094-WRN-A	PRS	PETC	5 ton	Micronized UE2-094-WRN-A	EI-158	5/4/87	
115	UE3-115-DCC-B	UE3-106-WRN-A	Dravo	OICE	28 drums/5040 lbs	Filter cake from deep cleaned UE3-109-WRN-A	EI-179	5/13/87	
116	UE3-116-UCW-F	UE3-115-DCC-B	OICE	EER, MTCI, Tec	6 drums	Ultrafine slurry from filter cake UE3-115-DCC-B	EI-175	6/22/87	
117	UE3-117-CMF-F	UE3-111-WRN-B	OICE	PETC	2000 gal	Std grind slurry from UE3-111-WRN-B	EI-171	5/27/87	
118	UE3-118-WRN-A	parent	Westmoreland Coal	Dravo	23 tons	*3.5% ash, Taggart Seam, Wentz Plant	EI-182	5/22/87	
119	UE3-119-DCC-B	UE3-109-WRN-A	Dravo	OICE	56 drums/10865 lbs	From UE3-109-WRN-A, 1.3-1.5% ash	EI-190	5/28/87	
120	UE3-120-CMF-F	UE3-119-DCC-B	OICE	MTCI/PETC	600 gal/110 gal	Std. grind slurry, 1.2% ash, from UE3-119-DCC-B	EI-191	7/27/87	
121	UE3-121-UCW-F	UE3-119-DCC-B	OICE	MTCI	600 gal/11 drums	Ultrafine slurry, 1.2% ash, from UE3-119-DCC-B	EI-192	6/23/87	
122	UE3-122-DCC-B	UE3-118-WRN-A	Dravo	PRS	15 drums	Cleaned to 1.7% to 2.25% ash, from UE3-118-WRN-A	EI-202	6/11/87	
123	UE3-123-MCD-C	UE3-122-DCC-B	PRS	MTCI	24 drs/5412 lbs	From UE3-122-DCC-B	EI-231	7/22/87	Preston
124	UE2-124-WRN-B	UE2-089-WRN-A	Dravo	PRS	70 drums	From UE2-089-WRN-A	EI-194	6/11/87	
125	UE2-125-MCD-C	UE2-124-WRN-B	PRS	PETC	5 tons	From UE2-124-WRN-B	EI-211	6/24/87	Carlucci
126	UE2-126-MCD-C	UE2-094-WRN-A	PRS	PETC	39 drums/9615 lbs	From UE2-094-WRN-A	EI-205	6/11/87	Carlucci
127	UE3-127-WRN-A	parent	Westmoreland Coal	Dravo	25 tons	Stoker Coal, Taggart seam, 3.5% ash, Wentz plant	EI-195	6/3/87	Five Star
128	UE2-128-MCD-C	UE2-089-WRN-B	PRS	EER	55 gal drum	Air freighted (from UE2-089-WRN-B) same as UE2-126-MCD-C	Dravo	6/8/87	
129	UE3-129-DCC-B	UE3-118 & 127	Dravo	PRS	13 drums	Blend of deep cleaned UE3-118 & UE3-127	EI-211	6/22/87	Carlucci
130	UE3-130-DCC-B	UE3-129-DCC-B	Dravo	OICE	47 drums/8640 lbs	1.3-1.5% ash - same as UE3-129	EI-226	7/10/87	Preston
131	UE3-131-WRN-A	parent	Westmoreland Coal	OICE	4 1/2 tons	Taggart Seam, Wentz plant	EI-212	6/26/87	Five Star
132	UE3-132-WRN-A	parent	Westmoreland Coal	Dravo	22 tons	Taggart Seam, Wentz plant	EI-212	6/25/87	Five Star
133	UE3-133-MCD-C	UE3-122-DCC-B	PRS	EER	55 gal drum	Micronized from UE3-122	Dravo	6/24/87	Aer Air
134	UE3-134-DCC-B	UE3-127/132	Dravo	Penn Rilliton	20 drums	Deep cleaned coal	EI-229	7/15/87	Carlucci

Table 1 (Cont.)

Serial		Previous	From		To	Quantity	Description	P.O.#	Date
No.	Sample I.D.	Sample I.D.							Shipped Hauler
135	UE3-135-PCD-C	UE3-134-DCC-D	Penn Rilton	HTCI	20 drums/2 tons		Pulverized coal	EI-232	7/16/87 Preston
136	UE3-136-WRM-A	parent	Westmoreland Coal Co.	Bravo	23 tons		Stoker Coal (~3.5% ash), Taggart Seam, Wentz Plant	EI-233	7/20/87 Five Star
137	UE3-137-CWF-F	UE3-130-DCC-D	DICE	PETC	1870 gal		same spec as UE3-120-CWF-F	EI-240	8/19/87 Leanan
138	UE3-138-CWF-F	UE3-131-WRM-A	DICE	C-E	1200 gal		heatable to 150 deg. C	EI-238	9/11/87
139	UE3-139-WCD-F	UE3-131-WRM-A	DICE	C-E	7500 gal		heatable to 150 deg. C	EI-241	10/27/87
140	LEI-140-WCD-E	LEI-091-WRM-A	EI	United Tech	one pound		Micronized "as received" Lower Elkhorn	--	8/3/87 US Mail
141	LEI-141-WCD-E	LEI-140-WCD-E	EI	United Tech	one pound		Deep Cleaned LEL-140-WCD-E (froth flotation)	--	8/3/87 US Mail
142	UE3-142-DCC-D	UE3-132-WRM-A	Bravo	Schutz/D'Neill	46 drums/4.6 tons		Deep Cleaned	EI 246	7/31/87 Smith
143(1)	UE3-143-WCD-C	UE3-142/145	Schutz/D'Neill	PETC	88 drums			EI 265	9/1/87 Inway
143(2)	UE3-143-WCD-C	UE3-142/145	Schutz/D'Neill	PETC/EER	44 drums/1 drum			EI 268	9/9/87 Smith
144	UE3-144-DCC-D	UE3-132-WRM-A	Bravo	DICE	21 drums			EI-248	8/5/87 Smith
145	UE3-145-DCC-D	UE3-132/136	Bravo	Schutz/D'Neill	70 drums/7 tons		Deep cleaned dried filter cake	EI-251	8/24/87 Preston
146	BIP-146-WRM-N	parent	UNDERC	EI	10 gal		Western lignite coal	UNDERC	8/6/87 RPS
147	BIP-147-PCD-N	BIP-146-WRM-N	UNDERC	SATC/EI	1 ton/5 gal		Pulverized Buelah Zap lignite coal	UNDERC	8/3/87 RPS
148	UE3-148-DCC-D	UE3-149-WRM-A	Bravo	Schutz/D'Neill	75 drums/7.5 tons		for 25 ton shipment of micronized coal for PETC	EI-267	9/8/87 Smith
149	UE3-149-WRM-A	parent	Westmoreland Coal Co.	Bravo	23 tons		Taggart Seam, Wentz plant stoker coal	EI-261	8/24/87 Five Star
150	BIP-150-RDM-N	parent	UNDERC	ANAI	~2000 lbs		Buelah-Zap lignite coal	EI 278	12-17 RPS
151	BIP-151-DCC-N	BIP-150-RDM-N	ANAI	UNDERC	~2000 lbs		Deep cleaned lignite coal	EI 278	RPS
152	UE3-152-WCD-C	UE3-148-DCC-D	Schutz/D'Neill	PETC	10,000 lbs			EI 352	1/6/88 Yellow
153	UE3-153-DCC-D	UE3-149/156	Bravo		~95 drums		Light industrial grade held in storage (for micronizing)	Bravo	9/23/87 Yellow
154	UE3-154-WCD-B	UE3-153-DCC-D	Schutz/D'Neill	Tacogen	1 drum			Bravo	9/23/87 Yellow
155	UE3-155-WCD-B	UE3-153-DCC-D	Schutz/D'Neill	EER	3 drums			EI-272	9/25/87 Five Star
156	UE3-156-WRM-A	parent	Westmoreland Coal Co.	Bravo	23 tons		Bravo began using Oct B, 1987	EI-278	2/15/88 est.
157	BIP-157-CWF-N	BIP-176-WCD-B	UNDERC	Arco/EI	1000 lbs/5 gal		Coal-methanol-water slurry prepared from lignite coal		

8.3 DRAVO FROTH FLOTATION CIRCUIT

DRAVO RESEARCH CENTER SMALL PILOT PLANT-WITH AUXILIARY CELLS

REV. 3

8.4 LIST OF FLOTATION REAGENTS

LIST OF FLOTATION REAGENTS

<u>Reagent</u>	<u>Manufacturer</u>	<u>I.D. No.</u>
A	Nalco	8836
B	Nalco	8839
C	Sherex	2057
D	Ashland Oil	MBC
E	Nalco	058
F	Calgon	1170
G	Sherex	164A
H	Sherex	168
I	Dow	252
J	Ashland Oil	No. 2 Fuel Oil

**DATE
FILMED**

8 / 20 / 93

END