PNL---7999

DE92 017553

OBSERVATIONAL APPROACH IMPLEMENTATION
GUIDANCE: YEAR-END REPORT

J. D. Smyth^(a)
J. P. Kohlman
M. S. Peffers

June 1992

Prepared for
U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Richland, Washington 99352

(a) CH2M Hill
Richland, Washington 99352

MASTER

SUMMARY

It is generally recognized that the Remedial Investigation/Feasibility Study (RI/FS) process can be time-consuming and costly. To expedite the process, the Environmental Protection Agency, through the National Contingency Plan and Office of Solid Waste and Emergency Response (OSWER) Directives,¹ has promoted "streamlining" the RI/FS. The concept of streamlining is directly applicable to Resource Conservation and Recovery Act (RCRA) Remedial Facility Investigation/Corrective Measure Study (RFI/CMS) as well.

The U.S. Department of Energy's (DOE's) environmental restoration process promises to be lengthy and expensive; therefore, the Office of Environmental Restoration (EM-40) believes that it is important to incorporate streamlining into RI/FS and RFI/CMS efforts across the DOE complex. The Office of Program Support (EM-43) has asked Pacific Northwest Laboratory (PNL) to provide presentations and workshops on streamlining concepts, including tenets of the "observational approach" at DOE environmental restoration sites around the complex. This report summarizes the FY91 activities that were conducted at PNL as part of this effort.

¹"RI/FS Improvements Phase II, Streamlining Recommendations" (OSWER Directive #9355.3-06), and "Considerations in Ground Water Remediation at Superfund Sites" (OSWER Directive #9355.4-03).

CONTENTS

SUMMARY	iii
1.0 INTRODUCTION	1
1.1 PURPOSE	1
1.2 REPORT STRUCTURE	1
2.0 ACTIVITIES SUMMARY	3
2.1 OBSERVATIONAL APPROACH OVERVIEW	3
2.1.1 Observational Approach Tenets	3
2.1.2 Implementation Background	4
2.2 PROJECT HISTORY	7
2.3 SITE-SPECIFIC IMPLEMENTATION	9
2.4 REGULATORY PARTICIPATION	13
3.0 LESSONS LEARNED FOR DOE FACILITIES	15
3.1 WORKSHOP LESSONS	15
3.2 FIELD NEEDS	16
4.0 NEXT STEPS	19
4.1 OBSERVATIONAL APPROACH/DATA QUALITY OBJECTIVE INTEGRATION	19
4.2 RI/FS IMPLEMENTATION GUIDANCE	20
5.0 REFERENCES	21
APPENDIX A - MEMORANDUM: STREAMLINING REMEDIAL INVESTIGATION/FEASIBILITY STUDIES (RI/FS)	A.1
APPENDIX B - STREAMLINED APPROACH - GENERAL CASE EXAMPLES LANL INSTALLATION WORK PLAN	B.1

FIGURES

2.1	Structure of the Observational Approach in the CERCLA Process	6
2.2	Decision Framework	6
2.3	DOE's Interest in the Observational Approach	7
2.4	INEL--Observational Approach Workshop Agenda	12

TABLES

2.1	Site-Specific Implementation Assistance	10
-----	---	----

1.0 INTRODUCTION

The U.S. Department of Energy (DOE) is committed to completing environmental restoration of its facilities by 2019 (DOE 1991). To achieve this, DOE must ensure that its restoration activities are both effective and efficient. A key aspect of fulfilling this commitment is recognizing and managing the uncertainty that is inherent in waste-site clean-up actions. The DOE Office of Environmental Restoration (DOE-ER) requested Pacific Northwest Laboratory (PNL)² to investigate the applicability and implementation of what is known as the "observational approach" (OA) to better address these needs.

PNL, supported by CH2M HILL and Jacobs Engineering, has been providing implementation guidance to DOE field offices on observational approach fundamentals, implementation, and application to waste-site remediation as a part of DOE's efforts to streamline the environmental restoration process.

1.1 PURPOSE

The purpose of this report is to

- summarize FY91 activities conducted as a part of this effort
- identify lessons learned during these activities
- discuss the next steps required in providing streamlining implementation guidance to the field.

1.2 REPORT STRUCTURE

This report is organized consistently with its purposes. Section 2.0 contains the "Activities Summary," which provides an overview of the observational approach, project history, field activities, and results. The valuable experience that was gathered while performing these activities is captured in Section 3.0, "Lessons Learned," which includes effective methods of conveying implementation information to the field, field needs, and obstacles to implementing streamlining techniques. Interacting with field

²Pacific Northwest Laboratory is operated for the U.S. Department of Energy by Battelle Memorial Institute.

offices and their contractors while providing observational approach guidance has provided the opportunity to identify useful "next steps" to further promote streamlining. Section 4.0 summarizes these potential next steps in this evolving effort. Section 5.0 contains the report's references. Appendix A shows a copy of the June 1990 memo that was offered to DOE for implementation guidance on the observational approach. Appendix B contains a portion of Los Alamos National Laboratory's draft installation-wide workplan, which illustrates how the observational approach could be used.

2.0 ACTIVITIES SUMMARY

This section provides an overview of the observational approach, project history, field activities, and results.

2.1 OBSERVATIONAL APPROACH OVERVIEW

The foundation of the observational approach to environmental restoration stems from the *observational method*--a technique used by geotechnical engineers to manage uncertainty in subsurface designs. The technique was first taught by Karl Terzaghi (Peck 1969; Dunnycliff and Deere 1984). The transfer and application of the observational method to waste remediation have also been discussed in the literature (Wallace 1988; Duplanic and Buckle 1989). More recently, discussions of the observational method as the *observational approach* have appeared in literature discussing DOE waste-site remediation (Myers and Gianti 1989; Steffen and Ferguson 1991; Smyth and Quinn 1991). Endorsements advocating a streamlined, flexible approach to waste-site remediation are available (U.S. National Research Council 1989). Specifically, the DOE has endorsed the concept for application to environmental restoration in its 1990 Environmental Restoration and Waste Management Five-Year Plan (DOE 1990). The U.S. Environmental Protection Agency (EPA) has similarly endorsed a streamlining approach equivalent to the observational approach in OSWER Directives 9355.3-06 (EPA 1989a) and 9355.4-03 (EPA 1989b) as part of the remedial investigation and feasibility studies (RI/FS) improvements project.

2.1.1 Observational Approach Tenets

The essence of the observational approach to waste-site remediation is that remedial action can and should be initiated without full characterization of the nature and extent of contamination. The philosophy of the approach includes the following ideas:

- Uncertainties are inherent in waste-site remediation and cannot be completely eliminated regardless of characterization attempts.
- Lengthy investigations and characterization studies do little to reduce inherent uncertainties at waste sites.

- Confidence in any remediation effort is achieved only through field verification and monitoring of the waste site during and following remediation.

Consistent with its philosophy, the observational approach provides a logical framework through which planning, design, and implementation of remedial actions can proceed with increased confidence. The basic ingredients of the approach are as follows:

- Conduct sufficient characterization (investigation, modeling, etc.) to provide a general understanding of probable conditions and reasonable deviations; the level of site characterization depends on both the site itself and the general response actions.
- Evaluate remedial alternatives based on probable site conditions.
- Conduct site characterization until reasonable deviations can be accommodated by remedial alternatives (i.e., technical data sufficiency reached).
- Select waste-site physical and chemical parameters used in monitoring for probable conditions and reasonable deviations.
- Calculate or estimate values of waste-site physical and chemical parameters (e.g., hydraulic conductivity and contaminant concentrations) expected during remediation of both probable conditions and reasonable deviations.
- Select a remedial alternative based on probable conditions; plan for and design contingency plans to address reasonable deviations.
- Construct and implement the remedial design based on probable conditions.
- Monitor the selected physical and chemical parameters to observe reasonable deviations; the name "*observational approach*" is derived from observing parameters during implementation.
- Modify the remedial action according to prepared contingency plans in response to the occurrence of reasonable deviations.

2.1.2 Implementation Background

PNL and its subcontractors have investigated implementing the observational approach in the DOE's environmental restoration activities under both the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) and the Resource Conservation and Recovery Act (RCRA) corrective action programs. The observational approach is consistent with both regulatory frameworks. The National Contingency Plan (NCP) (55 FR 8666) and

the draft Subpart B Corrective Action Guidelines (55 FR 30798) support the observational approach tenets by encouraging focused data gathering, streamlining the process, and a bias for action.

Under a "traditional" clean-up approach, only probable conditions are explicitly determined and included in the design. The observational approach follows this tactic, but also incorporates the concepts of data sufficiency, identification of reasonable deviations, preparation of contingency plans, observation of the system for deviations, and implementation of contingency plans (Figure 2.1).

One of the key advantages the observational approach offers is a decision framework (Figure 2.2). The iterative steps of site characterization, developing and refining a conceptual model, and identifying uncertainties in the conceptual model are similar in both the traditional and observational approaches. The concept of addressing uncertainties as reasonable deviations is unique to the observational approach and offers a qualitative description of data sufficiency for proceeding with site remediation. Data sufficiency is a site-specific issue. The process of identifying this point is probably best addressed by a combination of professional judgment and accepted quantitative techniques. Certainly, communication and cooperation throughout the process are keys to successful implementation.

The observational approach is only a framework; to realize successful implementation of the framework, tools are required that optimize the use of available information (e.g., expert judgment, numerical models, statistical techniques). These tools are necessary to provide decision makers with the information they need to define, identify, and assess the impact of reasonable deviations. These tools will vary with site-specific conditions.

One tool that is beginning to get much visibility within the DOE complex is called the data quality objectives (DQO) process (Neptune et al. 1990). The DQO process uses statistical and numerical techniques to help define data

FIGURE 2.1. Structure of the Observational Approach in the CERCLA Process

FIGURE 2.2. Decision Framework

collection needs. DOE's efforts to integrate the DQO process as a tool within the observational approach framework are discussed in more detail in Sections 3.1 and 4.0.

2.2 PROJECT HISTORY

Figure 2.3 illustrates the evolution of the effort to implement the observational approach. Investigating the applicability of the observational approach as a means of streamlining DOE waste-site remediation began under the DOE Office of Environmental Guidance (EH-23) in 1989 to determine if it had merits for DOE. The advantages and disadvantages of the observational approach were identified and discussed using a combination of Westinghouse Hanford Company (WHC) and PNL engineers and scientists in a workshop format (Myers and Gianti 1989). The panel concluded that the observational approach provided a useful central framework for streamlining DOE's environmental restoration process.

A briefing on the results of the EH-funded study was given to top EH and EM management in April 1990 to provide them with an opportunity to assess the observational approach as it pertains to DOE efforts. A related objective was evaluating the benefits of disseminating the observational approach philosophy to DOE field offices. Both management teams endorsed the observational approach as a "smart way of doing business" (DOE 1990). PNL was tasked to

FIGURE 2.3. DOE's Interest in the Observational Approach

communicate the fundamentals of the observational approach to the field. As the focus of the project moved into implementation issues in the summer of 1990, management was transferred to EM-43. Close coordination between EM-43 and EH-23 has continued throughout the project's history. EM-43's and EH-23's cooperative effort has been key to the effective communication and coordination of the observational approach to the field. Field implementation guidance has three components:

- A formal presentation is given, describing the need for the observational approach in environmental restoration, how it can be incorporated in the CERCLA/RCRA remedial process, and brief case histories.
- Guidance is provided through informal technical sessions where site-specific applications are discussed and hypothetical case studies are worked through as a group exercise.
- Site-specific applications are initiated through workplan scoping activities.

Implementation guidance on the observational approach was offered to DOE facilities through a memo distributed in June 1990 (see Appendix A), which resulted in the following DOE field offices and facilities requesting presentations: Los Alamos National Laboratory (LANL), Idaho Falls (DOE-ID), Idaho National Engineering Laboratory (INEL), Richland (DOE-RL), Savannah River (DOE-SR), Nevada (DOE-NV), Albuquerque (DOE-AL), Oak Ridge (DOE-OR), Oak Ridge National Laboratory (ORNL), Rocky Flats (DOE-RF), and Sandia National Laboratory (SNL). Two briefings were also provided to DOE Headquarters. The formal presentation consisted of three elements: observational approach background and relevance to DOE's environmental restoration effort; implementation under CERCLA and RCRA Corrective Action; and case histories of observational approach application at Whittier Narrows (Mark et al. 1989) or Weldon Spring Quarry (Steffen and Ferguson 1991).

In addition to the presentation, informal technical sessions were held at DOE-ID, INEL, DOE-SR, DOE-AL, DOE-OR, ORNL, DOE-RF, DOE-NV and SNL. The objective was to provide more implementation-focused guidance than the formal presentation contained. The technical session was formatted as a group exercise and worked through an actual groundwater remediation project. The participants helped to identify probable conditions and discern between reasonable deviations and further data needs. The exercise included

discussing possible contingency plans and the parameters that could be observed to monitor the system's behavior. Because the group exercise was based on an actual remediation project, participants received feedback on how their decisions affected remediation activities.

The workshops continued to evolve and focus more on site-specific implementation as field offices requested follow-on guidance support for their contractors. As a part of the implementation focus, workplan scoping assistance has been provided to LANL, INEL, ORNL, SNL, and RF. Table 2.1 provides detail on specific assistance provided to facilities for workplan scoping.

2.3 SITE-SPECIFIC IMPLEMENTATION

Workplan scoping assistance provided to LANL, INEL, ORNL, SNL, and RF included developing hypothetical examples, formulating detailed outlines for strategy papers, and other similar efforts. The overall goal of these sessions was to transfer the understanding of the observational approach framework to the facility staff responsible for conducting environmental restoration activities. To do this, the following standard objectives were set:

- Provide sufficient guidance to allow project managers to develop specific plans using the observational approach focusing on their site's needs.
- Develop a tangible and specific product (e.g., strategy paper, outline, etc.) as a result of the workshop that formed a part of the facility's environmental restoration activities.

To accomplish these objectives, the PNL team developed a workshop format that centered on site-specific knowledge provided by a project manager intimately involved with the waste site. The workshop consisted of two meetings: a planning meeting and the actual working session.

At the planning meeting, all the background work necessary for a successful workshop was performed; this typically included establishing realistic objectives for the work session, reviewing waste-site information (e.g., existing data, regulatory framework, compliance agreement specifics,

TABLE 2.1. Site-Specific Implementation Assistance

Facility	Site	Regulatory Framework	Objective	Product	Status
LANL	Site-wide	RCRA, corrective action	Develop example streamlining strategy	Appendix in Site-Wide Workplan	Workplan received tentative approval from EPA Region VI.
ORNL	Waste Area Grouping 5	CERCLA	Develop RI/FS streamlining strategy	Presentation to regulators responsible for workplan approval and DOE-OR	Strategy received endorsement from EPA Region IV, Tennessee regulators, and DOE-OR.
INEL	Technical Area North	CERCLA	Develop streamlining strategy described in a scope of work to facilitate conversion from RCRA to CERCLA	Detailed outline for scope of work	Scope of work received tentative regulatory approval. IRA, focusing on Treatability Study & LFI proposed to begin Spring of '92.
SNL	Technical Area-2	RCRA, corrective action	Supplement existing interim workplan with streamlining strategy	Strategy outline, identify data needs	Interim workplan proceeding.
RF	Operable Unit 2	CERCLA	Develop streamlining strategy for ground-water interim action	Interim action outline	EPA Region VIII and Colorado Department of Health briefed. Interim workplan proceeding developed.

etc.) that could influence remedial activities, and finalizing an agenda for the workshop. After the planning meeting, the background information was relayed to the rest of the workshop team.

A typical work session agenda is shown in Figure 2.4. The agenda was developed to walk through the observational approach steps as outlined in Section 2.1 and to apply them to the specific site needs. The PNL team facilitated an interactive discussion with the site project team. The size of the site project team varied from a single project manager (LANL) to 30 staff representing regulators, DOE, contractors, and subcontractors (ORNL). A prerequisite of the observational approach workshop was that the waste site be in the scoping stage of the RI/FS (or RCRA Facility Investigation/Corrective Measure Study). Because of this prerequisite, goals of the work session generally focused on developing a strategy or plan for conducting the environmental restoration activities. Products resulting from the workshops ranged from an appendix for LANL's installation-wide workplan illustrating how the observational approach could be used (Appendix B) to an RFI strategy outline developed for SNL.

Feedback on the workshop products has been positive. The results of the ORNL workshop have been particularly good, resulting in a presentation of a strategy for RI/FS activities at waste-area-grouping (WAG) 5 based on the observational approach. The strategy was endorsed by DOE-OR as well as the State of Tennessee and EPA Region IV regulators, who are responsible for oversight of environmental restoration activities at ORNL. The regulators and DOE-OR have since requested that all ORNL workplans be modeled on a strategy similar to that developed for WAG 5.

The workshops also appear to have been successful in the overall objective of communicating an understanding of the observational approach framework. The most concrete evidence of this is ORNL's planned strategy and LANL's use of the observational approach in their facility-wide workplan. Specific ideas that facilitated the transfer and communication of the concept are detailed in Section 3.0, "Lessons Learned."

AGENDA

Tuesday, June 11

- 8:00 am Introduction
 Observational Approach Overview
 TAN Overview
 - Existing data, plans, assumptions
- 10:00 am Break
- 10:15 am Conceptual Model Development
- 11:45 am Lunch
- 1:00 pm Technical Approach
 - Probable conditions
 - Uncertainties/deviations
 - General response actions/alternatives
 - Data needs
- 4:30 pm Wrap-up and discussion

Wednesday, June 12

- 8:00 am Review
- 8:30 am Statement of Work Outline
 - Technical approach
 - Schedule
 - Assumptions/deviations
 - Contingency plans
- 11:30 am Wrap-up and Conclusion

FIGURE 2.4. INEL--Observational Approach Workshop Agenda

2.4 REGULATORY PARTICIPATION

In addition to the workshop at ORNL, regulatory staff have participated in observational approach presentations and workshops at most facilities. The EPA's Federal Facility regional staff (and the respective DOE facility) attending the presentations included Region X (Hanford), Region IV (Savannah River Site, ORNL), and Region VI (Nevada Test Site). State regulatory staff included representatives from Washington, Tennessee, South Carolina, Colorado, New Mexico, and Nevada.

Reaction has generally been very positive; at a minimum, interest in gaining additional knowledge has resulted. In addition, EPA's Federal Facility regional staff in Region X (Bonneville Power Administration, Hanford, INEL) and Region IV (ORNL) have requested that the observational approach be considered by contractors. The sole negative reaction was encountered during the first presentation at ORNL, when some Tennessee regulators voiced negative feelings. After further discussion, it became apparent that the adverse reaction was directed toward DOE in general, not the concepts presented during the observational approach presentation. Tennessee regulators at the subsequent working session voiced strong support for the WAG 5 strategy using the observational approach framework.

3.0 LESSONS LEARNED FOR DOE FACILITIES

This section reviews the lessons learned while providing observational approach presentations and workshops to the field. The lessons learned in the first category, entitled "Workshop Lessons," can be transferred to other efforts attempting to relay information to the field. The second category of lessons learned, entitled "Field Needs," discusses issues that are related to the broader topic of DOE's environmental restoration effort. Many of these broader issues are beyond the scope of this summary, but are identified here as a basis for further investigation and study.

Specifically, providing implementation guidance to field offices and contractors offered opportunities to identify

- important links in communicating implementation guidance to the field
- field needs and obstacles to implementing streamlining measures.

3.1 WORKSHOP LESSONS

One of the objectives of the observational approach effort was to provide guidance for implementing the observational approach to working-level staff and contractors. While disseminating the observational approach to field offices, experience was gained in the areas of communicating effectively with the field, developing key components of presentation and workshop format, and conducting a successful workshop by focusing on essential elements. These elements include the importance of the following:

- **Effective communication among HQ, field office and contractor staff, and the workshop team.** Because several organizations are involved in providing the observational approach workshops, it was critical that communication was effective and consistent among all parties. The various elements of communication that proved to be important to this effort included 1) the initial memo from EH-23 announcing workshop availability, 2) the coordination of the workshop schedules and information by the DOE project manager, which resulted in effective communication with the field office, 3) use of the presentation to communicate the fundamentals of the observational approach to the field office, and 4) the use of workshop planning meetings as a forum to initiate communication between the workshop team and contractor staff to establish realistic workshop expectations (site-specific goals and workshop objectives).

- **DOE-HQ support.** DOE-HQ funding was a key element in the initial coordination of the workshops and in the ability to consistently provide observational approach workshops to the field. The alternative funding mechanism would depend upon individual field office contractual vehicles and thus affect DOE's ability to effectively and efficiently communicate a consistent observational approach message to the field. DOE-HQ's support has provided continuity in guidance for implementing the observational approach to all field offices, and has allowed the feedback of knowledge gained from the workshops to be provided to other field offices and DOE-HQ.
- **Field office workshop "ownership."** To establish credibility of the workshop team, it was critical for the field office to claim ownership of the workshop. Within this framework, it was important for a local DOE representative to take responsibility for coordinating the workshop at the field office level. This consisted of announcing the workshop time and place to contractors and conveying the workshop's importance and the need for contractor participation. In the absence of these activities, the success of the workshops would be greatly impaired.
- **Illustration of the generic observational approach framework and its adaptability to the field office's immediate site-specific issues.** Field office staff are focused on solving problems that exist today. To illustrate the value and utility of the observational approach, it was essential to demonstrate how it could help them address their immediate specific needs. A focused method to accomplish this was provided through the presentation and workshop formats.
- **Complimentary implementation tools.** A related issue is providing sites with examples of tools that can be used at their sites to implement the observational approach framework (see Section 2.1.2). Identifying appropriate tools and providing examples of their application would increase field office staff understanding of how specific tools are used to implement the observational approach framework. One such tool that has gained visibility within the DOE-ER community is the DQO process (Neptune et al. 1990), which provides a planning process for collecting data of specified level (e.g., quality) within specified constraints. Throughout the assessment and remediation effort, other quantitative and qualitative tools will be appropriate to realize full potential from observational approach implementation.

3.2 FIELD NEEDS

In addition to gaining experience that will enhance the effectiveness of future workshops, the interactive workshop format provided a forum for identifying issues germane to environmental restoration but not technically related to the observational approach. Regulatory, legal, and contractual issues were often raised during the workshop as potential obstacles to

conducting a consistent and efficient environmental restoration program.

These issues include the following:

- **Effective interaction with regulators.** DOE and its contractors need to develop technical strategies for conducting environmental restoration activities and to be able to effectively communicate them to the appropriate regulators. Frequent interaction with regulators is a productive way to develop and communicate strategies. The observational approach workshop at ORNL provided an example of how regulator interaction during the development of a technical strategy can help communicate and obtain concurrence on a defensible approach.
- **Identification of flexible contracting strategies.** A major issue raised at most field offices was using the appropriate contracting mechanism during implementation of the observational approach. A flexible contracting strategy is important in maximizing observational approach benefits and is being addressed independently by different entities. For example, the Weldon Spring Remedial Action Project is in the process of identifying a contracting strategy to use during remediation. Additionally, HQ is developing a contracting strategy for use with the proposed Environmental Restoration Management Contracts.

Closely related to contracting flexibility is the issue of contingency funding. To realize contractual flexibility, access to additional funds (i.e., contingency funds) must be available in case "deviations" occur (see Section 2.1). Without access to contingency funds, cost estimating will probably be conducted on an unrealistically conservative (worst-case) basis, leading to extremely high costs.

- **Impact of DOE orders on maintaining flexibility in ER activities.** Regulators and DOE field office staff have identified DOE Orders dealing with procurement as a potential obstacle to conducting environmental restoration activities. There may be other potential conflicts between efficient environmental restoration activities and DOE Orders developed for other purposes because of the unique aspects of environmental restoration.
- **Field testing of streamlining techniques.** The ability to point to "real-life" applications as test cases assists in the field accepting new techniques. Initially, a test case was planned to demonstrate the observational approach as a framework for conducting effective and efficient environmental restoration activities at DOE waste sites. As the project evolved, it became evident that case histories would complement the workshops to illustrate the use of the observational approach. However, also evident was that if a methodology (like the observational approach) makes intuitive sense to the field offices they will incorporate it into their efforts regardless of previous use.

Ultimately, an observational approach "test case" was not pursued. One reason for this was that a number of field offices began implementing the observational approach without waiting for a test case. Additionally, implementing the observational approach framework varies according to site-specific conditions. Thus, while a test case provides useful insight, it would only prove to be successful for the specific test case conditions. Because of field office initiative, test cases were essentially being provided by environmental restoration activities under way. The Weldon Spring Site also provided a test case in their RI/FS, Record of Decision (ROD), and Remedial Design/Remedial Action (RD/RA) activities.

Therefore, based on field offices' immediate need for a framework to provide a bias for action and the limited utility of a focused "test case," PNL, EM-43, and EH-23 opted to focus on providing implementation guidance to field offices. The use of the observational approach by field offices became, in essence, multiple test cases negating the use of a single demonstration test case.

Some of the topics discussed above are being proposed for investigation as part of PNL's FY92 activities. Others are being addressed by field offices as they independently pursue environmental restoration activities.

4.0 NEXT STEPS

The purpose of this section is to provide insight into future related efforts for implementing the observational approach to environmental restoration. Disseminating the fundamentals of the observational approach to field offices has been highly successful. Seven of the nine field offices have requested presentations and workshops for selected facilities. These workshops have resulted in the observational approach being incorporated in at least five scoping efforts during development of workplans. Regulatory reaction to using the observational approach as a framework for conducting environmental restoration has been positive and encouraging.

With the objective of continuing to provide effective implementation guidance to field offices, it is important to begin considering options that will optimize the use of the observational approach framework. Investigating some options began in FY91. The specific options include two efforts:

- integrating DQOs (see Section 3.1) within the observational approach framework
- developing a RI/FS implementation guidance document that incorporates streamlining techniques.

4.1 OBSERVATIONAL APPROACH/DATA QUALITY OBJECTIVE INTEGRATION

An outgrowth of the observational approach workshops was the identified need to integrate complementary tools into the observational approach framework (see Section 3.1). Work was initiated in FY91 by EH-23 to develop a formalized concept of how one tool, termed the "DQO process," can be integrated to facilitate efficient data collection within the observational approach framework. The initial effort (OA/DQO process integration) has included participants from DOE, PNL, Argonne National Laboratory (ANL), EPA and CH2M HILL. Meetings were held in January and July of 1991 to discuss the merits of using the two approaches to develop initial integration concepts. The meetings resulted in a draft concept paper describing the initial integration results.

Future efforts in OA/DQO process integration will be closely coordinated between EM-43 and EH-23. Work is anticipated to begin in the near future on

developing a new workshop to describe the integrated OA/DQO process methodology. The basis for the new workshop will be the draft paper produced as a result of the initial EH-23 integration efforts. The new OA/DQO process workshop will be provided to field offices in a system similar to that used with the OA workshop. Many of the lessons learned from the original observational approach effort will be incorporated into the OA/DQO workshop effort. In addition, PNL will take an active role in fostering the exchange of information among field practitioners of the observational approach through such forums as conferences and technical information exchange meetings.

4.2 RI/FS IMPLEMENTATION GUIDANCE

This effort, also jointly funded and coordinated by EM-43 and EH-23, focuses on developing an implementation guidance document for streamlining the RI/FS process at DOE facilities. The document will consist of four main components or modules: 1) RI/FS guidance, 2) detailed information on observational approach and DQO process concepts, 3) case histories of observational approach and DQO process applications, and 4) an example decision document illustrating streamlining concepts. The guidance document effort began in July 1991 and will continue through May 1992. In addition to PNL and CH2M HILL, staff from EPA, ANL, ICF and Jacobs Engineering Group are involved.

The guidance document will be developed to provide additional information for field offices to complement the observational approach and OA/DQO process integration workshops.

5.0 REFERENCES

- 55 FR 30798. July 27, 1990. "Corrective Action for Solid Waste Management Units (SMVs) at Hazardous Waste Management Facilities: Proposed Risk." Federal Register.
- 55 FR 8666. March 8, 1990. U.S. Environmental Protection Agency, "National Oil & Hazardous Substances Pollution Contingency Plan: Final Rule." Federal Register.
- Dunnicliff, J., and D. U. Deere. 1984. Judgement in Geotechnical Engineering - The Professional Legacy of Ralph B. Peck. John Wiley & Sons, New York, New York.
- Duplanc, N., and G. Buckle. 1989. "Hazardous Data Explosion." Civil Engineering V59(12):68-70.
- Mark, D. L., L. A. Holm and N. L. Ziemba. 1989. "Application of the Observational Method to an Operable Unit Feasibility Study - A Case Study." In Proceedings of Superfund '89. Washington, D.C.
- Myers, R. S., and S. J. Gianti. 1989. "The Observational Approach for Site Remediation at Federal Facilities." In Proceedings of Superfund '89. Washington, D.C.
- Neptune, D. E., E. P. Brantly, M. J. Messner and D. I. Michael. 1990. "Quantitative Decision Making in Superfund: A Data Quality Objectives Case Study." Hazardous Materials Control 2(3):19-27.
- Peck, R. B. 1969. "Ninth Rankine Lecture, Advantages and Limitations of the Observational Method in Applied Soil Mechanics." Geotechnique 19(2):171-187.
- Smyth, J. D., and R. D. Quinn. 1991. "The Observational Approach in Environmental Restoration." In Proceedings of the ASCE National Conference of Environmental Engineering. Reno, Nevada.
- Steffen, D. E., and R. D. Ferguson. 1991. "Remedial Action Program for the Weldon Spring Quarry." Hazardous Materials Control 4(2):40-45.
- U.S. Department of Energy. 1991. Environmental Restoration and Waste Management Five-Year Plan Fiscal Years 1993-1997. DOE/S-0090P, Washington, D.C.
- U.S. Department of Energy. 1990. Environmental Restoration and Waste Management Five-Year Plan Fiscal Years 1992-1996. DOE/S-0078P, Washington, D.C.
- U.S. Environmental Protection Agency. 1989a. "RI/FS Improvements Phase II, Streamlining Recommendations." OSWER Directive No. 9355.3-06, Washington, D.C.

U.S. Environmental Protection Agency. 1989b. "Considerations in Ground Water Remediation at Superfund Sites." Directive No. 9355.4-03, Washington, D.C.

U.S. National Research Council. 1989. "Commission on Engineering and Technical Systems, The Geotechnical Board." In Geotechnology - Its Impact on Economic Growth, the Environment, and National Security. National Academy Press, Washington, D.C.

Wallace, W. A. 1988. "Engineering Under Uncertainty: A New Perspective on the Cleanup of Hazardous Waste Sites." In Proceedings of the Joint CSCE-ASCE National Conference of Environmental Engineering. Vancouver, British Columbia, Canada.

APPENDIX A

MEMORANDUM: STREAMLINING REMEDIAL
INVESTIGATION/FEASIBILITY STUDIES

United States Government

Department of Energy

memorandum

DATE: OCT 25 1990

REPLY TO
ATTN OF: EH-231

SUBJECT: Streamlining Remedial Investigation/Feasibility Studies (RI/FS)

TO: Distribution

It is generally recognized that the RI/FS process can be time-consuming and costly. In order to expedite the process, the Environmental Protection Agency (EPA), through the National Contingency Plan (NCP) and Office of Solid Waste and Emergency Response (OSWER) Directives¹ has promoted "streamlining" the RI/FS. This concept of streamlining is directly applicable to RCRA Facility Investigation/Corrective Measures Studies (RFI/CMS) as well.

The RCRA/CERCLA Division (EH-231) has worked with Pacific Northwest Laboratories and CH₂M Hill to develop detailed presentations on streamlining, including tenets of the "observational approach" to environmental restoration. The Office of Environmental Restoration (EM-40) believes that it is important to incorporate streamlining into RI/FS and RFI/CMS efforts across the DOE complex; therefore, the Program Support Division (EM-43) will sponsor presentations on streamlining concepts at DOE environmental restoration sites around the complex. To date, presentations have been made to DOE-RL and Hanford contractors, EPA Region IX and Washington Ecology, and DOE-AL, Los Alamos Area Office and Los Alamos National Laboratory (LANL). In addition to the presentations, the "streamlining team" may be able to help individual sites with RI/FS and RFI/CMS workplan development or review to ensure incorporation of streamlining fundamentals. Currently, LANL is working in these areas with the streamlining team.

In order to get most benefit out of the streamlining presentations and possible workplan development/review, environmental restoration project managers (ERPMS) should be near the beginning of workplan preparation. Additionally, ERPMS that anticipate requesting help with workplan development should be prepared to present basic information on their specific environmental restoration sites (i.e., type/size of site, qualitative/quantitative contaminant data, affected media, etc.) to the streamlining team.

To request a presentation on the concepts of streamlining, or for additional information on this subject, contact Richard Dailey of my staff at 202-586-7117 or FTS 896-7117.

Thomas T. Traceski
Director, RCRA/CERCLA Division
Office of Environmental Guidance

¹RI/FS Improvement, Phase II, Streamlining Recommendations (OSWER Directive #9355.3-06) & Considerations in Ground Water Remediation at Superfund Sites (OSWER Directive #9355.4-03).

APPENDIX B

STREAMLINED APPROACH - GENERAL CASE EXAMPLES LANL INSTALLATION WORK PLAN

INTRODUCTION

PURPOSE AND SCOPE OF THIS APPENDIX

This appendix provides a general overview and summary of the application of the Streamlined Approach (also found in literature as the Observational Method or Observational Approach) to the Environmental Restoration (ER) Program at the Los Alamos National Laboratory (LANL).

The appendix briefly overviews the tenants of the Streamlined Approach and elaborates on two hypothetical case examples. The two case examples were developed based on limited data and information. The examples are necessarily hypothetical because they were developed from the viewpoint of having completed site remediation. In other words, these two examples look back upon how the Streamlined Approach might have been used. The application of the Streamlined Approach with the use of all available data will be incorporated into the actual work plans and implementation of RCRA tasks for each of LANL facilities or operable units.

These case examples are not intended for use as a guidance document for implementation of the Streamlined Approach at LANL; nor are they intended as a prescriptive "how-to" guide for remedial planning and implementation. Rather, the case examples are intended to illustrate the philosophy, general approach, and thought processes necessary for developing the application of the Approach at LANL facilities.

OVERVIEW OF THE STREAMLINED APPROACH

The basis of the Streamlined Approach to environmental restoration is the Observational Method, a technique used by geotechnical engineers to manage uncertainty in subsurface designs. The Observational Method was first formalized by Karl Terzaghi (Peck 1969; Dunncliff and Deere 1984). More recently, the transfer and application of the Observational Method to waste remediation has been discussed in the literature (Wallace 1987, 1988; Sturges et al. 1988; Mark et al. 1989; Myers and Gianti 1989; Duplancic and Buckle 1989). In addition, endorsements advocating a streamlined, flexible approach to waste site remediation are available (U.S. National Research Council 1989). Specifically, the Department of Energy (DOE) has endorsed the concept in application to ER in its recent Environmental Restoration and Waste Management 5 Year Plan (DOE 1990). Also, the Environmental Protection Agency (EPA) as part of its remedial investigation and feasibility studies (RI/FS) improvements project, has endorsed the Streamlining Approach in OSWER Directive 9355.3-06 (EPA 1989).

The essence, or philosophy, of the Streamlined Approach to waste remediation is that remedial action can and should be initiated without "full" characterization of the nature and extent of contamination. The basic philosophy of the approach includes the following ideas:

DRAFT

- Inherent uncertainties in waste remediation cannot be completely eliminated.
- Protracted investigations and characterization studies do little to reduce inherent uncertainties at waste sites.
- Confidence in any remediation effort is achieved only through field verification and monitoring the waste site during and following remediation.

Consistent with its philosophy, the Streamlined Approach provides a logical method through which planning, design, and implementation of remedial actions can proceed with increased confidence. The basic ingredients of the approach are as follows:

- Conducting sufficient characterization (investigation, modelling, etc.) to provide a general understanding of probable conditions and reasonable deviations. The level of site characterization depends on both the site itself and the general response actions.
- Evaluation of remedial alternatives based on probable site conditions
- Site characterization conducted until reasonable deviations can be accommodated by remedial alternatives (i.e., data sufficiency reached).
- Selection of waste site physical and chemical parameters used to monitor for probable conditions and reasonable deviations.
- Calculation or estimation of the value of waste site physical and chemical parameters (e.g., hydraulic conductivity and contaminant concentrations) expected during remediation of BOTH probable conditions and reasonable deviations.
- Selection of a remedial alternative based on the probable conditions, and planning and design of contingency plans to address reasonable deviations.
- Construction and implementation of the remedial design based on probable conditions.
- Monitoring of the selected physical and chemical parameters to identify reasonable deviations.
- Modification of the remedial action according to prepared contingency plans in response to the occurrence of reasonable deviations.

DRAFT

OVERVIEW OF THE GENERAL CASE EXAMPLES

The two hypothetical case examples described here, provide an illustration of the possible application of the Streamlined Approach in LANL's environmental restoration efforts. Consistent with these efforts, the regulatory basis used is the draft RCRA Subpart S - Corrective Action for Solid Waste Management Units (FR V55(145)).

The relationship between the RCRA Corrective Action Program (CAP) and the Streamlined Approach is illustrated in Figure 1. The Generalized Decision Diagram defines the steps in the corrective action process when the Streamlined Approach is used. The CAP components (i.e., RCRA Facility Assessment, RCRA Facility Investigation, Corrective Measure Study, and Corrective Measure Implementation) are shown with the approximate corresponding portions of the decision diagram. Although they appear as discrete units, the CAP components actually are interrelated and should not be treated as discrete components during remediation. The interrelationship of the components is shown in the decision diagram. For example, obtaining site characterization data is typically thought of as part of the RFA/RFI. However, additional site characterization data could be required in any part of the corrective action program. Indeed, in using the RCRA Streamlined Approach, action is initiated as soon as there is sufficient data available. Additional data is expected to be collected in other stages of the corrective action process.

In this appendix, the hypothetical case examples are analyzed according to the process illustrated by the generalized decision diagram. The examples represent two remediation cases that illustrate some of the remedial alternatives anticipated to be implemented at LANL. The examples begin with a description of a conceptual model based on existing information and progress through the corrective action process as described by the decision diagram. Each case example is organized into sections that approximately correspond to the RCRA CAP components. The components are combined as section headings (e.g., RCRA Facility Assessment/RCRA Facility Investigation, RCRA Facility Investigation/Corrective Measure Study, etc.) to emphasize the continuous nature of the RCRA corrective action program.

Measurable and visible benefits of using the Streamlined Approach to waste-site remediation at LANL will vary considerably, depending on site-specific conditions (i.e., media contaminated, type of contaminants, etc.). For instance, decommissioned firing sites are examples of when using the Streamlined Approach with corrective action may not look any different from how the corrective action would have been implemented without the Approach. It is important to realize the intangible benefits that are inherent in the application of the Approach. Among the intangible benefits is the thought process (i.e., recognizing uncertainty exists, obtaining sufficient data, identifying probable conditions and reasonable deviations, etc.) advocated by the Approach. The thought process is important to use in every case of waste-site remediation regardless of whether or not potential visible benefits exist. Without the use of the Approach, data sufficiency is undefined, deviations are not identified nor their impact evaluated, and most importantly no framework exists that can be used to decide if contingency plans are required to respond to the deviations.

DRAFT

The two cases provide hypothetical examples of remediation that vary in complexity. The first case is an example of possible surface soil contamination by radioactive and hazardous metals at a decommissioned firing site. Although the remediation process appears to be straightforward, this case is used to illustrate the benefit of using the Streamlined Approach thought process to proceed with any remediation, complex or not, with a bias for action. The second case is a more complex problem of subsurface contamination by organics, corrosive gasses, and solid radioactive mixed waste at a material disposal area. Types of uncertainty are greater, therefore possible deviations are more numerous. This case illustrates the use of the Streamlined Approach to identify, anticipate, and prepare for deviations. Together these cases form a picture of two possible applications of the streamlined approach to remediate Solid Waste Management Units (SWMUs). Although the general examples are representative of general scenarios known to occur at LANL, they are hypothetical and are not intended to represent specific solid waste management units.

DRAFT

GENERAL CASE EXAMPLE 1 CLEAN TO ACCEPTABLE LEVELS

This general case example illustrates potential application of the Streamlined Approach to remedial planning and implementation for a LANL facility that may be remediated and restored to acceptable levels of contamination. An example of this type of facility at LANL would include the decommissioned firing areas. This hypothetical case example describes the remediation effort at a specific decommissioned firing site. Many of the details in the actual operations of these sites are classified. This hypothetical example is therefore limited in detail about the facility operations.

RCRA FACILITY ASSESSMENT/RCRA FACILITY INVESTIGATION

Facility Description

The decommissioned firing areas at LANL vary in their history of operation and physical configuration. The hypothetical site used in this example is an inactive firing site that has been designated a RCRA Solid Waste Management Unit (SWMU). The SWMU is located on top of a mesa. The mesa top soil primarily consists of low-permeability, fractured, welded tuff. Groundwater is generally on the order of 1000 ft beneath the mesa top. LANL experiences precipitation events of short duration during the summer, primarily due to thermal convection storms (i.e., thunder showers). These high intensity events are known to cause periods of significant surface runoff from the mesa tops, that provides the opportunity for overland transport of surface soils. In the adjacent canyon there is a surface water drainage course. Groundwater is present at considerable depth (more than 1000 feet) below the site.

Operations at this SWMU involved detonation of approximately 100 chemical explosive devices. The period of time the site was in use is not known. Surface soil within the detonation area is believed to be contaminated with radioactive mixed waste include uranium, beryllium, thorium, barium, mercury, boron, cadmium, and lead. During operations, the detonation area was periodically cleared by grading, and the accumulation of rubble formed a talus bench adjacent to the area. Detonations were accomplished without airborne particulate controls, potentially resulting in particulate deposition within a 1500-foot radius of site, including the canyon.

Contaminants of concern include uranium, beryllium, thorium, barium, mercury, boron, cadmium, and lead. Although this site has been designated a SWMU, it is not known if any contaminants are present above the levels defined in the draft RCRA Subpart S as that require corrective action to be taken (i.e., action levels). It is believed that levels of some contaminants will exceed action levels at this site. The SWMU is believed to pose a relatively low threat to health and the environment at LANL. Because under the

DRAFT

RCRA CAP SWMUs are prioritized for remediation based on their threat to health and the environment, the SWMU is believed to not be an EPA priority for corrective action. Because a threat does exist and remediation is assumed to be straightforward at this site, it was decided to pursue a voluntary corrective action (VCA) rather than wait for EPA to designate this site as a Corrective Action Management Unit (CAMU).

Conceptual Model Development

As illustrated in the Generalized Decision Diagram (Figure 1), a conceptual model should be defined early in the planning process and be used as a basis to:

- Visualize the **nature and extent** of contamination (contaminated media, pathways, and receptors)
- Identify potentially viable **general response actions**
- Understand overall **uncertainties** associated with the site as well as specific uncertainties associated with particular media, pathways, and/or general response actions
- Identify those uncertainties for which **sufficient information** exists to reasonably predict probable conditions and reasonable deviations
- Identify those uncertainties for which **additional data** gathering efforts are necessary to allow prediction of probable conditions and reasonable deviations.

Figure 2 illustrates a conceptual model of the decommissioned firing area. The model considers the detonation zone as the source, and the major release mechanisms (prior to decommissioning) to have been airborne particulates release and direct contamination of surface and shallow soils in the detonation zone.

Information gained from the literature indicated that the explosions resulted in contamination that probably decreased with distance from the source. Numerical simulation of the detonation and particle trajectory also indicated similar contaminant deposition patterns. The conceptual model developed is based on the assumption that the contaminants were dispersed radially outward from the source. Probable conditions at the firing site identified using the conceptual model included:

- The surface soil was contaminated with both hazardous (metals) and radioactive wastes.
- The contamination is greatest at the detonation location, and

DRAFT

decreases with outward radial distance.

- Contaminants were probably deposited in the adjacent canyon during detonation of devices, and after clearing of the area (i.e., when forming the talus bench). However, historic environmental monitoring records have not shown any evidence of any migration of contaminants down the adjacent stream.

Deviations from the probable conditions were identified by assessing the conceptual model and the identified probable conditions. These deviations include the following:

- Action levels are not exceeded for both hazardous and radioactive contaminants.
- Due to directed blasts and the periodic clearing of detonation debris from the firing site, the contamination distribution may be discontinuous and not radially dispersed.
- Contaminants may have migrated down the canyon wall to the stream.

RCRA FACILITY INVESTIGATION/CORRECTIVE MEASURE STUDY

Screen Viable General Response Actions

Response actions considered for remediation of inactive firing sites included the following:

- Institutional control (deed control, fencing or other barrier)
- Containment (capping, slurry walls)
- Removal and treatment (excavation/solidification and subsequent landfill)
- In-situ treatment (In situ vitrification, vapor extraction, stabilization, etc.).

In situ treatments were eliminated from consideration because they were not considered appropriate for the surface contamination at this site. Containment (capping) and removal (excavation/solidification and landfill) were considered the two most appropriate response actions based on the probable conditions.

DRAFT

Sampling and Action Plans

For this firing site, data needs are 1) confirmation of the probable conditions, and 2) data to enable the preferred corrective action to be identified from the general response actions. The choice between the potential corrective actions will be distinguished by evaluating the primary areas of uncertainty in the conceptual model. For this discussion, because contamination is limited to surface soils, surface area is considered equivalent to volume. The areas of uncertainty to be evaluated include the following:

- The volume of contaminated soil - large volumes would favor capping as a corrective action.
- The type of contaminants present - some contaminants (organics) are not amenable to solidification.
- The assumed spatial distribution of contaminants - if the contaminants are located in isolated spots over a large area, it may be more effective to identify the overall extent of contamination and cap, rather than to sample extensively for each isolated contaminant spot and excavate.

The sampling plan was designed to provide sufficient data to address these uncertainties, not to intensively characterize the firing site. The sampling plan was performed in two phases. The first phase was designed to provide a reconnaissance (coarse) sampling to provide data for confirming or refining the conceptual model. The objectives were as follows:

- Identifying the probable extent of contamination - The objective was to roughly identify the boundary of the area above action levels. Also of concern was the possibility of contamination in the canyon.
- Verifying the presence of expected contaminants
- Providing calibration samples for field equipment - To expedite corrective action, real time sampling to identify areas above action levels will be conducted; to ensure the accuracy of the measurements, calibration of the field equipment is required.

Following the first phase of sampling, the corrective actions will be evaluated again. The second phase of sampling will differ according to the results of this evaluation.

DRAFT

Results of Reconnaissance Sampling

Reconnaissance sampling indicated the following:

- The contamination was radially distributed.
- The approximate volume and depth of contamination was amenable to excavation.
- The levels of contaminants found of radioactive and hazardous contaminants were above action levels.
- No organics were detected.
- Contamination appears to be present on the side of the adjacent canyon. The steepness of the canyon wall created very difficult, and dangerous sampling conditions. Although the samples that were taken had contaminants above action levels, no samples providing the extent of contamination were able to be taken.
- Field instruments were able to be calibrated.

Conceptual Model Revisions

The conceptual model was revised to reflect the results of the reconnaissance sampling. The additional data appeared to support the previously identified probable conditions. The data also confirmed that action levels had been exceeded at the firing site. Because the data suggested the canyon also had contamination exceeding action levels, LANL requested that the firing site and the canyon wall be designated as a CAMU by the EPA.

The data also provided enough information to address most of the possible deviations. The remaining uncertainty is primarily associated with the extent and level of contamination of soils in the canyon. Further data will be difficult to gather due to the steep slopes.

The possibility of contamination in the canyon is of concern if 1) it is above action levels, and 2) moves off-site via the stream. While considering the reasonable deviations, it was discovered that a sediment monitoring station is currently maintained at the mouth of the canyon as a part of routine environmental surveillance at LANL. No historical evidence of contaminant migration has been found; however, monitoring of the sediments from the canyon will be conducted to confirm this. The existing sediment monitoring station will be relied on to identify any off-site migration of contaminants from the canyon wall. The contingency plan for this deviation will be to notifying the regulatory authorities and initiating an investigation of the release. This was considered

DRAFT

an appropriate contingency plan based on the distance between the CAMU's sediment monitoring station and the lab boundary at the canyon mouth. The distance was considered adequate to allow the deviation to be assessed and addressed. Addressing the possible migration of canyon wall contamination as a deviation allows the evaluation of possible corrective action to occur without delays for more sampling.

CORRECTIVE MEASURE STUDY/CORRECTIVE MEASURE IMPLEMENTATION

Corrective Action Evaluation

Following the reconnaissance sampling, sufficient data existed to allow evaluation and selection of the corrective measure. The evaluation was based on criteria specified in RCRA Subpart S. Types of information evaluated included 1) the extent of treatment provided by the general response action, and 2) evaluation of cost versus volume. For large volumes of contaminated soil, capping is more cost effective than excavation. Conversely, if the extent of contamination is small enough, excavation is preferred.

Based on the types of contaminants and volume of material expected, excavation/solidification and subsequent landfill is the preferred corrective action. The second phase of sampling was used to provide real-time data for guidance during excavation of the firing site. The real-time sampling and monitoring will allow the remediation to be expedited. It should be noted that the bias for action initiated in this hypothetical example is possible because of the thought process conducted when using the Streamlined Approach. After identifying probable conditions and selecting a preferred corrective action, the ramification of reasonable deviations occurring was assessed. Because the impact of the reasonable deviations occurring had no effect on the effectiveness of the preferred remediation, the implementation of the remediation was possible without further delay. Instead, real-time sampling during excavation was possible at this site.

Consistent with the preference for expediting corrective measure actions as described in Subpart S, the second sampling phase was designed to provide data during implementation of the corrective measure. During excavation and solidification it was necessary to refine the delineation of the contaminated area requiring excavation (i.e., above action levels). Field instruments (e.g., XRF probe, surface radiation survey) calibrated during the reconnaissance sampling were used to provide real-time definition of the required excavation area and depth. An on-site lab was also used to provide short-time turn around of sample analysis for verifications and calibration of the field equipment.

CORRECTIVE MEASURE IMPLEMENTATION/MONITORING

During implementation of the second phase, monitoring at the canyon mouth was continued in order to detect any migration of contamination above action levels. Excavation proceeded in conjunction with the real time monitoring until the site was remediated to acceptable levels. Samples were then taken to confirm that the soil

DRAFT

contamination in the area was below remediation levels. The remedy was considered complete under the guidelines specified in RCRA Subpart S and subsequently corrective action was terminated.

DRAFT

CASE EXAMPLE 2 IN SITU CONTAINMENT

This general case example is intended to illustrate potential application of the Streamlined Approach for remedial planning and implementation at LANL facilities using containment technology. Examples of this type of facility at LANL include material disposal areas and landfills.

RCRA FACILITY ASSESSMENT/RCRA FACILITY INVESTIGATION

Facility Description

Material disposal areas (MDAs) at LANL typically contain a wide range of hazardous wastes and low-level radioactive wastes (LLW) (i.e., mixed wastes). Both solid and liquid wastes were disposed of in pits, trenches, adsorption beds and shafts at MDAs. In general, LANL sited the MDAs on mesa tops adjacent to technical areas.

The hypothetical MDA examined in this case example was identified as a Solid Waste Management Unit (SWMU) during the LANL RCRA Facility Assessment (RFA). The MDA covers about 5 acres and is located on a mesa top (Figure 3). The soil on the mesa top primarily consists of low-permeability, fractured, welded tuff. Groundwater is approximately 1000 ft beneath the mesa top. Precipitation during the summer is primarily due to thermal convection storms (i.e., thunder showers). These storms result in high intensity precipitation events known to cause periods of significant surface runoff from the mesa tops resulting in overland transport of surface soils. In addition, the southern edge of the mesa top is also experiencing persistent erosion of surface soils. The eroded soil from the southern edge, and possibly soil suspended in runoff could be transported into the adjacent canyon. Environmental monitoring records indicate that the canyon has intermittent streamflow during thunder storms.

Laboratory records show that the MDA was used as a landfill in the late 1940's to dispose of radioactive solid waste and hazardous liquid and corrosive gas chemical waste. The MDA consists of a pit and trenches that have received different wastes during their use. It is not clear if the pit is actually a series of distinct and separate pits, or one large pit that was expanded as necessary. The pit comprises the majority of the MDA's surface area. The western portion of the MDA (which included some of the inactive pit area) was leased to the county in the 1960's and subsequently paved with asphalt for use as parking space. Wastes buried in the pits are thought to consist primarily of solid low-level radioactive waste (LLW) generated during ordinary lab operations (e.g., contaminated clothing, pumps, etc.). Solid waste known to be disposed of includes one truck contaminated with fission products and various radionuclides of plutonium, polonium, uranium, americium, curium, and actinium. An unknown number and size of trenches are thought to be located along the eastern edge of the MDA. Bottles disposed of in the trenches are thought to contain various mixtures of unknown volatile organic chemicals and corrosive gasses.

There is not any indication that contaminant migration has occurred at the MDA. No knowledge exists of surface contamination, nor is there any indication of any groundwater contamination.

The RFA determined that the SWMU constituted a release to the environment as defined by RCRA Draft Subtitle S. During the RFA portions of the MDA were found to have volatile organic concentrations in the soil that exceeded action levels. Assessment of the level of other possible mixed waste contaminants was not possible due to lack of data. However, because action levels were exceeded for the volatile organics, a Corrective Measures Study (CMS) will probably be required by EPA following the RCRA Facility Investigation (RFI). Anticipating this, LANL requested and received from EPA the designation of the entire MDA as a corrective action management unit (CAMU).

Conceptual Model Development

Using existing knowledge, a conceptual model of the CAMU was developed to identify possible contaminant sources, release mechanisms, contaminated media, migration pathways, and receptors. During development of the conceptual model, sources, pathways, and contaminated media that were determined to not be reasonable were screened out. The resulting conceptual model (Figure 4) identifies the expected probable conditions at the site based on available data, information, and technical judgment at that time.

The conceptual model of the MDA identified three possible contaminant sources: the pit(s) used for solid waste, trenches for bottled liquids and corrosive gases, and the paved portion of the MDA. Probable release mechanisms from these sources include unsaturated flow and transport, volatilization of organics, and erosion of surface soils. These release mechanisms may result in contamination of biota, vadose zone soils, surface soils, and air. Migration of the contaminants can occur through the vadose zone soils, surface soils, overland runoff, and air. The contamination could reach human and environmental receptors through direct dermal contact with soil, biota, and air; ingestion of soil, biota, and air; and inhalation of air. Contaminant migration to the groundwater is assumed to not be a concern because of the more than 1000 ft depth to the water table.

Using the conceptual model, the probable conditions have been identified as including the following:

- Contamination of vadose zone soils above action levels with volatile organics
- Contamination above action levels of the southern mesa edge from overland flow during storm events
- Limited migration of the solid waste - Because of the

DRAFT

extremely dry ambient soil moisture condition, there is little opportunity for the solid waste to migrate. Evidence at other MDA sites enforces this assumption.

- Contaminant concentration levels in the air below action levels
- No migration of contaminants to the groundwater - The distance to the water table is so great that this is not a realistic pathway.
- A very complex and dangerous source term covering a large area - The source-term probably includes organic liquids, volatilized organics, corrosive gasses and LLW (e.g., clothing, metal, pumps, trucks).

Major uncertainties in the conceptual model are as follows:

- The extent of lateral and vertical movement of the volatile organics
- The extent of contamination of the mesas' southern edge and canyon
- The nature of chemicals
- The volume of liquid in the sources.

RCRA FACILITY INVESTIGATION/CORRECTIVE MEASURE STUDY

Screen Viable Response Actions

Even though there are uncertainties in the conceptual model that must be addressed, preliminary screening of general response actions was possible. Following RCRA Subpart S guidelines, it is appropriate to identify response actions that are probable based on existing data. The following are general response actions that are technically feasible and appropriate for use in MDAs:

- Institutional control (fencing, deed control)
- Removal (excavation to RCRA landfill)
- Containment (capping, slurry walls)
- In-situ treatment (vapor extraction, in-situ vitrification, stabilization)

Because of the level of physical hazard that could be associated with sampling the

DRAFT

source-term, the ability to perform a corrective action without needing this sampling was considered a primary screening item. For instance, removal and some in situ treatments (e.g., in-situ vitrification) require more extensive knowledge of the source-term. These general response actions were eliminated from further consideration.

In this case, preferred general response actions will probably consist of a combination of response actions (i.e., institutional control in conjunction with containment and in-situ treatment).

Sampling and Action Plans

The goal of the sampling plan is to identify the appropriate combination of corrective actions. Refinement of the conceptual model was required in order to do this.

Uncertainties in the conceptual model exist that including the location, size, and number of pits and trenches, and the types of contaminants. Further evaluation of the general response actions can be conducted until these uncertainties are reduced. The goal is to reduce the uncertainties to a sufficient level so that the probable conditions can be identified, reasonable deviations predicted, and contingency plans prepared. To do this, data requirements include the following:

- Identification of the probable location and size of the sources (i.e., pit and trenches). Characterization of the source-term is not necessary for the response actions under consideration. However knowledge of the extent of the source is required to evaluate corrective actions. Specific factors include the distance from the sources to the boundaries of the MDA and the mesa edge.
- Better identification of the type and extent of contaminant migration. The specific parameters include lateral and vertical migration of volatile and solid contaminants.

The sampling plan to gather these data includes the following actions:

- Using surface geophysical techniques to identify the location of the pits and trenches
- Conducting surface contamination surveys
- Using soil gas surveys to identify the extent of volatile contaminant migration. Because volatiles are much more mobile than solutes, the extent of volatile contaminant migration will be used as an indication of the maximum extent of contaminant migration.

DRAFT

- Drilling slant boreholes under the sources to confirm the probable condition (i.e., that vertical migration of contaminants is negligible).

Results of Reconnaissance Sampling

The data gathered in the reconnaissance sampling is illustrated in Figure 5. Specifically the data indicated that:

- The MDA consists of one large pit covering approximately 2.5 acres in the fenced portion and under the paved portion of the MDA; and two trenches, 40 feet in length, 2-3 feet wide approximately 200 feet from the southern edge of the mesa.
- No surface contamination was found.
- Soil gas surveys indicated limited migration of volatiles. Samples found migration a maximum of 5 feet laterally from the outside boundary of the trenches. The volatile migration appears to be discontinuous and isolated. Between the southern edge of the mesa and the trenches, the migration also appears to be limited to 5 feet.
- Slant borehole samples did not reveal any indication of downward vertical movement of contaminants.

Conceptual Model Revisions

Using the newly acquired data, the probable conditions were revised to reflect the following:

- No contamination of the surface soils or the southern mesa edge
- Downward vertical migration to groundwater is negligible
- Limited lateral and vertical migration of volatiles
- Negligible lateral and vertical migration of solutes.

Uncertainties still exist as to the amount of organic and mixed liquids and corrosive gases remaining in the trenches. Two possibilities exist; 1) either the liquids and gasses are still

contained in their original containers in the trenches and haven't migrated yet, or 2) the organic liquids have volatilized and were previously released with the corrosive gases.

Characterization of the source-term could establish the existence of organic liquids and corrosive gases in the trenches, or their presence could also be addressed as a deviation. Because a physical hazard still exists with source characterization efforts, corrective actions will be evaluated with the possible presence of organic liquids and corrosive gasses attempted to be addressed as a reasonable deviation.

CORRECTIVE MEASURE STUDY/CORRECTIVE MEASURE IMPLEMENTATION

Corrective Action Evaluation and Contingency Plan Preparation

Following the criteria specified in RCRA Subpart S, 40 CFR Part 264.525 (a,b) possible corrective actions were evaluated. Specifically, the possible corrective actions were evaluated to determine if they allowed the presence of organic liquids and corrosive gases to be handled as a reasonable deviation. As previously noted, a combination of corrective actions were assumed to be most appropriate for the MDA. An evaluation of the data gathered during the reconnaissance sampling supported combining corrective actions.

The following information was used to evaluate the corrective actions:

- The extent of the MDA (pit and trenches)
- The danger involved in establishing further source characterization
- The ability of the corrective actions to address the presence of liquids and gases as a reasonable deviation.

Based on these criteria, a combination of institutional control and containment were selected as the preferred corrective action. The paved portion of the MDA will be reacquired by the DOE, and a fence established around the entire CAMU. A modified cap was identified as a corrective action to establish containment of the source, and to address the reasonable deviation of organic liquids and corrosive gasses existing in the trench. The cap will be designed to inhibit infiltration of water, and erosion of the soil covering the CAMU. It will also be designed to divert surface runoff around the CAMU.

In order to determine what level of detail was required for the contingency plans, cost, technical feasibility, and impact of the reasonable deviation were evaluated. In order to monitor for the for the deviation a series of soil gas monitors were installed under the cap. Another part of the contingency plan is how to respond to the deviation. Even

DRAFT

though the initial cost is greater, the cap was designed to include a network of pipes to capture the volatilized organics and corrosive gasses as the move out of the soil surface. This was determined to be more technically feasible than attempting soil gas extraction through the installed cap. If migration of the contaminants is detected, a air-stripping treatment train will be established to treat the off-gas removed via the pipe-network in built in the cap.

The level of detail required for the contingency plan varies. The soil gas monitors and pipe network will be designed and installed with the construction of the cap. The treatment train (i.e., air stripper, activated carbon filter, etc) will be designed, but not built. The monitoring system will allow advanced notice of migration movement to allow the treatment train to be constructed.

Corrective Measure Implementation/Monitoring

The corrective actions were implemented as designed. Monitoring of the soil gas between the cap and the trenches was initiated and is continuing. Monitoring for a deviation will continue for the length of time specified in the closure permit.

REFERENCES

- Dunnicliff, J., and Deere, D. U. (1984), Judgement in Geotechnical Engineering - The Professional Legacy of Ralph B. Peck, John Wiley & Sons, New York, NY.
- Duplanic, N., and Buckle, G., 1989, Hazardous Data Explosion, Civil Engineering, V59(12) pp 68-70. Washington, D.C.
- Mark, D. L., L.A. Holm, N.L. Ziemba. 1989, Application of the Observational Method to an Operable Unit Feasibility Study - A Case Study, Superfund '89 Proceedings of the 10th National Conference, November 27-28, Washington, D.C.
- Myers, R. S. and Gianti, S. J. 1989. The Observational Approach for Site Remediation at Federal Facilities, Superfund '89 Proceedings of the 10th National Conference, November 27-28, Washington, D.C.
- Peck, R. B. (1969), Ninth Rankine Lecture, Advantages and Limitations of the Observational Method in Applied Soil Mechanics, Geotechnique, 19, No.2, pp 171-187.
- Sturges, S. G., J.A. Martinsen, P.E. McBeth, Jr., 1988. Managing Uncertain Conditions during Hazardous Waste Remedial Action - Experiences at the United Chrome Site, AICE Summer National Meeting. Denver, CO.
- U.S. Department of Energy 1990. Environmental Restoration and Waste Management Five-Year Plan Fiscal Years 1992-1996, DOE/S-0078P, Washington, D.C.
- U.S. Environmental Protection Agency (1989), RI/FS Streamlining, OSWER Directive No. 9355.3-06, Washington, D.C.
- U.S. National Research Council (1989), Commission on Engineering and Technical Systems, The Geotechnical Board, Geotechnology - Its Impact on Economic Growth, the Environment, and National Security, National Academy Press, Washington, D.C.
- Wallace, W. A. (1987), The Cleanup of Hazardous Waste Sites in the United States: Positioning for Least Cost, Proceedings of the World Conference on Hazardous Waste, Budapest, Hungary, Elsevier Science Publishers, B.V.
- Wallace, W. A. (1988), Engineering Under Uncertainty: A New Perspective on the Cleanup of Hazardous Waste Sites, Joint CSCE-ASCE National Conference of Environmental Engineering, Vancouver, B.C., Canada.
- Wallace, W. A. and Lincoln D. R. (1989), How Scientists Make Decisions About Groundwater and Soil Remediation, National Research Council Water Science and Technology Board Colloquium, April 20-21, Washington, D.C.

FIGURE 1. Generalized Decision Diagram

FIGURE 2. Conceptual Model of Decommissioned Firing Area (Case Example 1)

FIGURE 3. Plan View of the Material Disposal Area (not to scale)

FIGURE 4. Conceptual Model of Material Disposal Area (Case Example 2)

FIGURE 5. Results of Reconnaissance Sampling (plan view, not to scale)

DISTRIBUTION

No. of
Copies

No. of
Copies

OFFSITE

12 DOE/Office of Scientific and
Technical Information

2 Bartlesville Project Office
P.O. Box 1395
220 N. Virginia
Bartlesville, OK 74005
ATTN: A. Crawley
T. Wesson

E. Bean
Kansas City Area Office
P.O. Box 410202
Kansas City, MO 64141-0202

J. Bellows
Los Alamos Area Office
528 35th St.
Los Alamos, NM 87544

S. Blacker
Mac Tec
8310 Centerbrook Place
Alexandria, VA 22308

3 Bonneville Power
Administration
P.O. Box 3621
Portland, OR 97208
ATTN: A. Morrell
S. Sander
B. Sherer

John Cochran
Sandia National Labs
Albuquerque, NM 87115

Jack Craig
FEMP
P.O. Box 398704
Cincinnati, OH 45239-8704

5 S. J. Gianti
CH2M Hill
P.O. Box 4400
Reston, VA 22090

K. Hull
Mac Tec
8418 Zuni Rd., SE
Albuquerque, NM 87108

W. Jamison
U.S. Department of Energy
Western Area Power
Administration
P.O. Box 3402
Golden, CO 80401

G. Johnson
Pinellas Area Office
P.O. Box 2900
Largo, FL 34649

B. Kaiser
U.S. Department of Energy
Nevada Operations Office
Yucca Mountain Project Office
P.O. Box 98518
Las Vegas, NV 89193-8518

J. Keller
Naval Petroleum Reserves in
California
P.O. Box 11
Tupman, CA 93276

M. Keller
Pittsburgh Energy Technology
Center
P.O. Box 10940
Pittsburgh, PA 15236-0940

Distr.1

No. of
Copies

No. of
Copies

D. McCollum
Morgantown Energy Technology
Center
P.O. Box 880
3610 Collins Ferry Rd.
Morgantown, WV 26507-0880

W. R. Miller
Morgantown Energy Technology
Center
P.O. Box 880
3610 Collins Ferry Road
Morgantown, WV 26507-0880

J. Morley
U.S. Department of Energy
Dayton Area Office
P.O. Box 66
Mearnesburg, OH 45342-0066

Dean Neptune
U.S. Environmental Protection
Agency
QAMS
401 M Street, SW
Washington, DC 20460

D. Newquist
Naval Petroleum Reserves in
California
800 Werner Ct, Suite 342
Casper, WY 82601

P. Ramey
U.S. Department of Energy
Amarillo Area Office
P.O. Box 30030
Amarillo, TX 79120-0030

Remedial Action Program
Information Center
Building 200
P.O. Box 2008
Oak Ridge, TN 37831-6050

A. Seepo
Schenectady Naval Reactors
Office
P.O. Box 1069
Schenectady, NY 12301

E. Shollenberger
Pittsburgh Naval Reactors
Office
P.O. Box 109
W. Mifflin, PA 15122-0109

R. Sleeman
U.S. Department of Energy
Environmental Restoration
Division
Oak Ridge, TN 37831

5 J. D. Smyth
CH2M Hill
1933 Jadwin, Suite 225
Richland, WA 99352

2 Southwestern Power
Administration
P.O. Box 1619
Tulsa, OK 74101
ATTN: D. Hayes
J. Lloyd

Strategic Petroleum Reserve
Project Office
Project Management Office
900 Commerce Road E.
New Orleans, LA 70123

5 U.S. Department of Energy
Albuquerque Operations Office
P.O. Box 5400
Albuquerque, NM 87115
ATTN: J. Bickel
A. Chernoff
D. Krenz
R. Sena
J. Themelis

No. of
Copies

No. of
Copies

2 U.S. Department of Energy
Albuquerque Operations Office
Uranium Mill Tailings Remedial
Actions Project Offices
P.O. Box 5400
Albuquerque, NM 87115
ATTN: M. Matthews, Jr.
T Plessinger

3 U.S. Department of Energy
Chicago Operations Office
9800 South Cass Avenue
Chicago, IL 60439
ATTN: B. Fritz
J. Haugen
J. Kennedy

75 U.S. Department of Energy
1000 Independence Ave.
Washington, DC 20585
ATTN: T. Barbosa, EM-431
R. Berube, EH-20
C. Billips, EH-8.2
D. Bottrell, EM-51
C. Bradley, NE-33
R. Bradley, S-1
S. Brocoum, RW-22
J. Coleman, EM-35
S. Cowan, EM-30
R. Dailey, EH-231
H. Delaplane, FE-421
W. Dennison, GC-11
G. Dicerbo, EH-231
J. Disbrow, EI-531
C. Ebbecke, NP-20
R. Englehart, NP-50
J. Farley, ER-8.2
J. Fiore, EM-42
J. Fisher, CP-40
R. Fleming, EM-431
J. Ford, DP-63
B. Fortune, EH-231
C. Frank, EM-50
S. Frank, NP-54
M. Frei, EM-34
H. Garson, NP-1
R. Gisch, NE-60
K. Goodwin, DP-161

P. Grimm, EM-2
C. Halsted, DP-13
S. Hanna, PA-3
L. Harmon, EM-53
D. Isbell, EM-431
D. Jewett, FE-222
R. Jones, EH-41
A. Joseph, ER-40
J. Knight, DP-12
R. Langum, EM-431
L. Lawson, EM-431
R. Lightner, EM-45
D. Lillian, EM-51
J. Longton, CR-14
J. Lytle, EM-30
C. Magnuson, EM-431
S. Mann, EM-44
W. Mess, ER-20
R. Moore, EI-23.1
D. Moses, PE-70
H. Myers, CE-64
G. Parker, RW-333
F. Peters, RW-2
R. Peterson, DP-222
H. Pettengill, EH-40
T. Pflaum, DP-3
S. Richardson, DP-60
P. Ritzcovam, NP-52
R. Scott, EM-20
B. Shackelford, EM-33
R. Sharma, NE-47
D. Shelor, RW-30
G. Sherwood, NE-12
D. Silawsky, FE-441
D. Smith, EM-6
K. Sprangle, DP-52
P. Strider, EM-431
D. Swink, FE-4
L. Taylor, EM-433
T. Traceski, EH-231
G. Turi, EM-433
J. Turi, EM-33
R. P. Whitfield, EM-40
W. Wisenbaker, EM-43
F. Wolff, DP-161
R. Wood, ER-74
J. Yates, ER-42

No. of
Copies

- 5 U.S. Department of Energy
Idaho Operations Office
785 DOE Place
Idaho Falls, ID 83402
ATTN: J. Barry
P. Hinman
J. Lyle
W. Sato
J. Zimmerman (INEL)
- 4 U.S. Department of Energy
Nevada Operations Office
P.O. Box 98518
Las Vegas, NV 89193-8518
ATTN: B. Church
D. Elle
J. Fiore
S. Mellington
- 6 U.S. Department of Energy
Oak Ridge Operations Office
P.O. Box 2001
Oak Ridge, TN 37831
ATTN: S. Garland (ORNL/ER)
P. Gross
H. W. Hibbitts
R. Nelson
A. Perkins, MS-6317
R. Sleeman
- 6 U.S. Department of Energy
Rocky Flats Office
P.O. Box 928
Golden, CO 80402-0928
ATTN: S. Grace
J. Hartman
F. Lockhart
T. Lukow
R. Nelson, Jr.
R. Schassburger

No. of
Copies

- 4 U.S. Department of Energy
San Francisco Operations
Office
1333 Broadway
Oakland, CA 94612
ATTN: J. Cullen
J. Davis
J. Juettan
M. Kamiya
- 4 U.S. Department of Energy
Savannah River Operations
Office
P.O. Box A
Aiken, SC 29802
ATTN: L. Goidell
T. Heenan
L. Sjostrum
S. Wright
- 2 U.S. Department of Energy
Waste Isolation Pilot Plant
Project Office (WIPP)
P.O. Box 3090
Carlsbad, NM 88221
ATTN: A. Hunt
J. Newhinney
- B. Vocke
Los Alamos National Laboratory
HSE/DO/ER MS K481
P.O. Box 1665
Los Alamos, NM 87545
- R. Waldman
U.S. Department of Energy
Alaska Power Administration
P.O. Box 020050
Juneau, AK 99802-0050

No. of
Copies

ONSITE

6 DOE Richland Operations Office

E. A. Bracken, A5-19
R. M. Carosino, A4-52
R. D. Freeberg, A5-19
R. G. Holt, A5-15
R. D. Izatt, A5-15
L. E. Little, A5-22

4 Battelle Washington Office

W. E. Fallon
J. D. Longstreth
R. D. Quinn
J. E. Shorett

3 Environmental Management
Operations (EMO)

J. April
J. Hartly
T. Page

5 Westinghouse Hanford Company

M. R. Adams, H4-55
J. G. Fidds, H4-55
K. Leonard, B2-19
T. Wincest, H4-55
J. G. Woolard, H4-55

15 Pacific Northwest Laboratory

R. C. Adams, K6-52
J. P. Amaya, K6-55
S. Q. Bennett, K7-90
G. R. Bilyard, K6-58
J. F. Keller, K1-51
T. L. Kuusinen, K6-58
M. S. Peffers, K7-94
M. R. Siegel, K6-58
M. B. Triplett, K7-90
Publishing Coordination
Technical Report Files (5)

END

**DATE
FILMED
9/01/92**