DOE/MC/22194--T8

DE92 017715

**DEVELOPMENT OF METAL-COATED CERAMIC ANODES
MOLTEN CARBONATE FUEL CELLS**

First Interim Technical Progress Report

September 30, 1985 - December 31, 1985

By

D. W. Richerson and A. Khandkar

January 1986

Work Performed Under Contract No: DE-AC21-85MC22194

For

U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
Morgantown, WV 26505

By

Ceramatec, Inc.
163 West 1700 South
Salt Lake City, UT 84115

**TECHNICAL INFORMATION CENTER
OFFICE OF SCIENTIFIC AND TECHNICAL INFORMATION
UNITED STATES DEPARTMENT OF ENERGY**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

045

7/28/82

MASTER

TABLE OF CONTENTS

INTRODUCTION.....	1
PROGRAM MANAGEMENT PLAN.....	1
TASK 2.3 TEST PLAN.....	1
APPENDIX A.....	A-1
Introduction.....	A-1
Task 2.3 Develop, Fabricate, and Test Anodes.....	A-3
Task 2.3.1a Fabricate Anodes.....	A-3
Task 2.3.1b Test Anodes Out-of-Cell...	A-3
Task 2.3.2 Test Anodes In-Cell.....	A-6
Task 2.3.2a Fabricate Anodes.....	A-6
Task 2.3.2b Test Anodes In-Cell.....	A-6
Task 2.3.3 Analyze Anodes Post-Test.....	A-12

INTRODUCTION

This report identifies activities conducted during the first three months of the program:

1. Preparation of Management Plan.
2. Implementation of major subcontract at Institute of Gas Technology (IGT).
3. Review of GE program and prior literature.
4. Preparation of Anode Development Goals Document.
5. Preliminary Cost Estimate Document.
6. Preparation of Task 2.3 "Anode Development, Fabrication and Test" Plan.
7. Procurement of chemicals, materials and hardware to conduct anode development.

The Management Plan, Anode Development Goals Document and Preliminary Cost Estimate Document were submitted previously. A Task 2.3 Test Plan based upon the proposed program work statement is included as part of this interim report. However, this plan may change based upon telephone recommendations from Ceramatec to DOE/METC. The general concerns and recommended change will be discussed later in this report.

PROGRAM MANAGEMENT PLAN

The Management Plan was submitted in October and described the responsibilities of key personnel and identified how the program will be managed and implemented. Figure 1 is a network diagram which shows the flow of the program and identifies tasks, responsibilities and milestones. Figure 2 shows the schedule and Table 1 lists the milestones.

TASK 2.3 TEST PLAN

The Task 2.3 "Anode Development, Fabrication and Test" Plan is attached as Appendix A. It details the test plan essentially as it was originally outlined in the proposal and identifies development concerns. Of particular concern are the following:

1. Very little information is available on nickel or copper coating of LiAlO_2 or other potential ceramic anode materials, especially regarding wettability, coating coverage and adhesion.
2. LiAlO_2 has been reported to hydrolyze in water, which may cause problems when attempting to coat with metals by electroless plating.

2

FIGURE 1. (CONTINUED)

FIGURE 1. (CONTINUED)

FIGURE 2. SCHEDULE

DOE Form CR435
(1-78)

U.S. DEPARTMENT OF ENERGY

MILESTONE SCHEDULE AND STATUS REPORT

PAGE 1 OF 2

FORM CR435
OCT 1978 EDITION

1. Contract Identification		2. Reporting Period		3. Contract Number																						
DEVELOPMENT OF METAL-COATED ANODES FOR MOLTEN CARBONATE FUEL CELLS		through		DE-AC21-85MC22194																						
4. Contractor (name, address)				5. Contract Start Date																						
CERAMATEC, INC. 163 W. 1700 South Street Salt Lake City, Utah 84115				October 1, 1985																						
7. Identification Number				6. Contract Completion Date																						
				September 1987																						
8. Reporting Category (e.g., contract line item or work breakdown structure element)		9. Fiscal Years and Months												10. Percent Complete												
		O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	a) Planned	b) Actual
1	Management Plan																									
2.1	Anode Development Goals																									
2.2	Task 2.3 Test Plan																									
2.3.1a	Fabricate Anodes																									
2.3.1b	Test Anodes Out-of-cell																									
2.3.2a	Fabricate Anodes																									
2.3.2b	Test Anodes In-Cell																									
2.3.3	Post Test Analyses																									
3.1	Task 3.2 Test Plan																									
3.2.1	Fabricate Anodes																									
3.2.2	Test Anodes out-of-cell																									
3.2.3	Test Anodes in-cell																									
3.2.4	Post Test Analyses																									
4	Samples																									

11. Remarks

12. Signature of Contractor's Project Manager and Date

13. Signature of Government Technical Representative and Date

PAGE 2 OF 2

MILESTONE SCHEDULE AND STATUS REPORT

U.S. DEPARTMENT OF JUSTICE

[illegible]

11. Remarks

112. Signature of Contractor's Project Manager and Date

113. Signature of Government Technical Representative and Date

TABLE 1

MILESTONE LOG

<u>I.D. No.</u>	<u>Description</u>	<u>Planned Completion Date</u>	<u>Actual Completion Date</u>
1	Management Plan Submitted	11/8/85	
2	Anode Development Goals Document Submitted	11/22/85 latest	
3	Preliminary Cost Estimate Document	12/31/85	
4	Management Plan Approved	11/30/85	
5	Test Plan (Task 2.3) Submitted	12/31/85	
6	Decision by COTR to continue Roll compaction	2/15/86	
7	Choose Metal loading level & Plating method	2/28/86	
8	Decision to begin Task 2.3	3/3/86	
9	Begin Out-of-cell testing on Task 2.3.1b	3/15/86	
10	Begin In-cell testing on Task 2.3	7/1/86	
11	Submit test plan Document for Task 3.2	11/1/86	
12	Submit up-dated Management Plan	9/30/86	
13	Management Plan Approved by COTR	10/31/86	
14	Submit Annual Report to COTR	10/31/86	
15	Ribbed Anodes Meet Goals	12/5/86 (approx.)	
16	Begin Delivery of Flat Anodes to IGT for Task 3.2.2	1/1/87	
17	Ribbed Anode Performance Adequate	2/5/87 (approx.)	

Milestone Log Continued

18	Complete Post Test Analysis Task 3.2.3	8/15/87
19	Complete Detailed Cost Report	8/1/87
20	Submit Final Report to COTR	8/31/87
21	Submit Anode Samples to COTR	8/31/87

3. LiAlO_2 and the various conductive ceramics are high cost and will be difficult to reduce to a cost compatible with the long range anode goals; Al_2O_3 represents a low cost alternative, but it is not chemically stable in molten lithium carbonate and would require complete protective coating of nickel or copper. The chemical stability of the conductive ceramics in molten carbonates is also in question.

Ceramatec and IGT recommend that the program be modified to conduct a more thorough development and evaluation of metal coating of LiAlO_2 , Al_2O_3 and SrTiO_3 early in the program before anode is fabricated for out-of-cell and in-cell tests. This effort would involve (1) development of coating and inspection procedures to assure complete coating of the ceramic particles, (2) evaluation of wetting characteristics to assure that the ceramic remains coated during sintering and to assure adequate coating adhesion and (3) immersion corrosion exposures of coated powder and sintered coated powder in molten carbonate with combustion gas products present.

Ceramatec is currently assessing which of these recommended tasks fit into the current work statement and which would require a change in work plan, schedule or budget. This can be discussed at the program review meeting at METC on February 4, 1986. In the meantime, Ceramatec is proceeding with metal coating trials as defined in the current work statement.

APPENDIX A

TASK 2.3 TEST PLAN

INTRODUCTION

Ceramatec and IGT proposed testing of four different compositions of ceramic-metal anodes. They included:

<u>Support Ceramic</u>	<u>Metal Coating</u>
LiAlO ₂	50 Ni/50 Cu
LiAlO ₂	30 Ni/70 Cu
LiAlO ₂	100 Cu
Conductive Ceramic	50 Ni/50 Cu

Each of these compositions will be tested in two types of tests, according to the following general matrix:

1. Out-of-Cell Creep Tests, ~150 hours (Task 2.3.1b)

<u>No. of Ceramic/Metal Compositions</u>	<u>No. of Porosities</u>	<u>No. of Test Pressure/Temperature Combinations</u>	<u>Total No. of Creep Tests</u>
4	2	5	40

2. In-Cell 94-cm² Fuel Cell Tests, ~750 hours (Task 2.3.2b)

<u>No. of Compositions</u>	<u>No. of Porosities</u>	<u>No. of Tests Each</u>	<u>Total No. of In-Cell Tests</u>
4	2	2	16

Each of the above compositions will be fabricated by Ceramatec to 45% and 60% porosities; yielding eight "composition/porosity" anode combinations. Each of these eight anodes will be out-of-cell creep tested (Subtask 2.3.1b) for ~150 hours at five different pressure/temperature combinations -- for a total of 40 creep tests. Each of these eight anodes will also be tested, in duplicate, in 94-cm² bench-scale molten carbonate fuel cells (Subtasks 2.3.2b) for a total of 16 in-cell tests.

One finding of the preliminary anode specification analyses may impact on the current test plan. Based on the specification goals for metal coated ceramic anodes established last month, the target anode materials cost of \$10 for 1 m² electrodes, 30 mils thick, was found to be "unrealistic if LiAlO₂ is the

substrate material."¹ Ceramatec estimated the materials costs to be \$13 to \$17 per m², depending on the unit cost and type of ceramic substrate. Thus, low-cost ceramic particles such as Al₂O₃ should be evaluated as an alternative.

Another development concern² that has arisen is the compatibility of copper in an MCFC anode. GE found that copper platings were necessary as part of the fabrication procedures for metal coated ceramic particles. Copper improved the sinterability of the powder. This has been verified by IGT in their own limited efforts to evaluate metal-coated ceramic anodes. With regards to the copper compatibility question, IGT has found that except for the sheet metal separator plate composition/design specification, no other major cell package modification would be needed for a copper-based anode. Moreover, copper-clad stainless steel sheet metal (as well as copper based anodes) should be more economical than the current nickel-clad stainless steel sheet metal concepts.

A further concern is the fact that LiAlO₂ (and Li salts in general) hydrolyzes in contact with water. This poses some very challenging problems as far as coating such materials with electroless Ni and/or Cu in aqueous media is concerned. Ceramatec will pursue the option of coating LiAlO₂. However, should this option prove to be difficult to pursue, Ceramatec will request permission from DOE to pursue the alternative option of coating Al₂O₃, which does not hydrolyze in water.

Efforts will be continued, in parallel, to coat LiAlO₂. Ceramatec has several approaches to tackle the problem of hydrolysis, and will try these without departing significantly from the work statement.

Therefore, investigations into low cost ceramic substrates and the effect of Ni/Cu ratio for metal-coated ceramic anodes is warranted. Specifically, if a low cost ceramic such as Al₂O₃ could be successfully coated with metal, the tests originally planned for the 100 Cu/LiAlO₂ anode will be substituted with tests of this "low-cost" anode.

Overall, the program follows an anode development/testing pattern which is sequentially executed in both Subtasks 2.3.1 for out-of-cell evaluations and Subtask 2.3.2 for in-cell evaluations. Reports on IGT's work in Subtasks 2.3.1b and 2.3.2b will emphasize: test procedures and set-up, testing status/data, performance results/evaluations when combined with post-test materials analyses (of Subtask 2.3.3), and recommendations.

Subtask 2.3.3 Analyze Anodes Post-Test will serve as the central data cumulation, review, and materials characteristics projections point for pre- and post-test materials analyses for both, Subtask 2.3.1b (out-of-cell) and Subtask 2.3.2b (in-cell) testing. Ceramatec will perform the necessary pre-test quality control analyses of as-fabricated anodes to ensure compliance with the anode specifications prior to delivery to IGT. This will facilitate timely execution of the testing schedules. IGT will also perform internally consistent pre- and post-test analyses to ensure accurate assessments of anode characteristic changes as a result of creep and in-cell testing.

¹Task 2.1, Develop and Submit Anode Development Goals Document, Development of Metal-Coated Ceramic Anodes for MCFC.

²Letter from F. Gmeindl to P. Lessing, 11/25/85.

The test plan for IGT's work efforts in Task 2.3 is described below under the specific tasks.

Task 2.3 Develop, Fabricate, and Test Anodes

Subtask 2.3.1a Fabricate Anodes

Ceramtec will develop and fabricate and pre-test analyze for compliance with anode specifications flat porous metal-coated ceramic anodes to complete the in-cell and out-of-cell tests outlined in Tasks 2.3.1b and 2.3.2b. They will produce four different compositions, namely,

1. 50 Ni-50 Cu on LiAlO_2
2. 30 Ni-70 Cu on LiAlO_2
3. Cu on LiAlO_2
4. 50 Ni-50 Cu on conductive ceramic particles.

Each composition will be fabricated to two porosities 45% and 60%; with a target pore size of 3μ for all. Ceramtec will determine the metal loading based upon their coating experience. Ideally, the metal loading is adjusted so that all anodes possess the same coating thickness.

Ceramtec will also investigate the coating characteristics of low-cost Al_2O_3 . If successful, 50 Ni-50 Cu on Al_2O_3 anodes will be fabricated and supplied to IGT for testing instead of the Cu on LiAlO_2 composition.

Ceramtec will provide IGT the out-of-cell test coupons in a timely manner for IGT to meet the test schedule described in Task 2.3.1b.

Subtask 2.3.1b Test Anodes Out-of-Cell

The porous anodes fabricated by Ceramtec under Task 2.3.1a will be tested at IGT in creep test rigs as shown in Figure A-1. Ceramtec will supply IGT enough anode material to conduct five creep tests for each of the eight anode composition/porosity combinations described in Task 2.3.1a. These tests will be conducted under different compressive-pressure/temperature combinations :

1. 25 psi at 650°C
2. 50 psi at 600°C
3. 50 psi at 650°C
4. 50 psi at 700°C
5. 100 psi at 650°C

A total of 40 out-of-cell tests will be conducted. Each of these 40 composition/porosity-by-test condition combinations is illustrated in Table A-1's test matrix.

To assure materials inventory for the out-of-cell testing, Subtask 2.3.1b and anode analyses, Subtask 2.3.3, Ceramtec will supply IGT with sufficient anode material to yield seven 1-in diameter cut-out test coupons for each anode composition/porosity combination. The thickness requirement for these test coupons are not stringent, but should be in the range of 27-32 mils.

A85050380

FIGURE A-1. CREEP TEST APPARATUS

TABLE A-1. SUBTASK 2.3.1b OUT-OF-CELL TEST MATRIX

No.	Metal Wt % / Wt %	Ceramic	Porosity %	$\frac{P}{T}$	1	2	3	4	5
					$\frac{25 \text{ psi}}{650^\circ\text{C}}$	$\frac{50 \text{ psi}}{600^\circ\text{C}}$	$\frac{50 \text{ psi}}{650^\circ\text{C}}$	$\frac{50 \text{ psi}}{700^\circ\text{C}}$	$\frac{100 \text{ psi}}{650^\circ\text{C}}$
1	50 Ni / 50 Cu	LiAlO ₂	45		X	X	X	X	X
2	50 Ni / 50 Cu	LiAlO ₂	60		X	X	X	X	X
3	30 Ni / 70 Cu	LiAlO ₂	45		X	X	X	X	X
4	30 Ni / 70 Cu	LiAlO ₂	60		X	X	X	X	X
5	100 Cu	LiAlO ₂	45		X	X	X	X	X
6	100 Cu	LiAlO ₂	60		X	X	X	X	X
7	50 Ni / 50 Cu	Conductive Ceramic	45		X	X	X	X	X
8	50 Ni / 50 Cu	Conductive Ceramic	60		X	X	X	X	X

Due to time limitations, each creep test will be conducted for a maximum of 145 hours. The anodes will be preloaded with sufficient carbonate to fill 20% of its pores. The compressive load will then be applied and the thickness change will be monitored continuously. The creep data will be curve-fitted to predict long-term stability under Task 2.3.3.

A tentative schedule of the out-of-cell tests (based on a series of three 144 hour tests run simultaneously) has been developed and is shown in Table A-2.

This table tracks four key times:

1. Required receipt date of anode material from Ceramatec.
2. Out-of-Cell test start date.
3. Out-of-Cell test end-date.
4. Completion date of a group of pre- and post-test analyses.

This is a very "tight" schedule. It presumes general anode pre-test specification conformance and is totally dependent on receipt of anode material in the quantity cited above for at least three composition/porosity-by-test condition combinations (Table A-1) by the dates listed in Column 2 of Table A-2. Additionally, a very demanding 1 day turn around is allowed for three shutdowns and three test startups. Also, this initial test schedule does not allow for unplanned equipment failures or maintenance. Should these unplanned events occur, they will be reported and their affect on the test schedule will be specified. The schedule is based on a March test start time and depends on receiving the first series of parts from Ceramatec on February 28, 1986, or before. Fourteen test series for the 40 tests are scheduled to be completed in the early part of June, 1986.

Task 2.3.2 Test Anodes In-Cell

Task 2.3.2a Fabricate Anodes

Ceramatec will fabricate, pre-test analyze for compliance with 94-cm² anode specifications, and deliver to IGT two anode plaques for each of the eight composition/porosity combinations described in Subtask 2.3.1a. These plaques must have a square planar area of 5 x 5 inches and a thickness of 30±1 mils. As with the out-of-cell testing, the porosity levels will be 45% and 60%. The mean pore size target will be 3 μ.

Ceramatec will provide IGT the anode plaques in such a timely manner for IGT to meet the time schedule described in Task 2.3.2b.

Task 2.3.2b Test Anodes In-Cell

The eight anode composition/porosity combinations described in Task 2.3.1a will be tested in duplicate at IGT in 94-cm² fuel cells. The schematic diagram of such a fuel is shown in Figure A-2. Four test stands will be available and each test will be conducted for about 750 hours. Table A-3 illustrates the test matrix for this subtask.

TABLE A-2. SUBTASK 2.3.1b OUT-OF-CELL TEST SCHEDULE

- Dates based on 144 hours per test series with a 1 day setup between tests
- Each test series consists of three simultaneous tests.

1	2	3	4	5	6	7	8	9
<u>Test Series</u>	<u>Receive Anode Material By</u>	<u>Day of Week</u>	<u>Start Date</u>	<u>Day of Week</u>	<u>Test Ends</u>	<u>Day of Week</u>	<u>Completion of Pre and Post-test Analysis</u>	<u>Day of Week</u>
1st	02/28/86	Fri.	03/04/86	Tues.	03/10/86	Mon.	04/09/86	Wed.
2nd	03/07/86	Fri.	03/11/86	Tues.	03/17/86	Mon.	04/09/86	Wed.
3rd	03/14/86	Fri.	03/18/86	Tues.	03/24/86	Mon.	04/09/86	Wed.
4th	03/21/86	Fri.	03/25/86	Tues.	03/31/86	Mon.	05/01/86	Thurs.
5th	03/28/86	Fri.	04/01/86	Tues.	04/07/86	Mon.	05/01/86	Thurs.
6th	04/04/86	Fri.	04/08/86	Tues.	04/14/86	Mon.	05/01/86	Thurs.
7th	04/11/86	Fri.	04/15/86	Tues.	04/21/86	Mon.	05/21/86	Wed.
8th	04/18/86	Fri.	04/22/86	Tues.	04/28/86	Mon.	05/21/86	Wed.
9th	04/25/86	Fri.	04/29/86	Tues.	05/05/86	Mon.	05/21/86	Wed.
10th	05/02/86	Fri.	05/06/86	Tues.	05/12/86	Mon.	06/11/86	Wed.
11th	05/09/86	Fri.	05/13/86	Tues.	05/19/86	Mon.	06/11/86	Wed.
12th	05/16/86	Fri.	05/20/86	Tues.	05/26/86	Mon.	06/11/86	Wed.
13th	05/23/86	Fri.	05/27/86	Tues.	06/02/86	Mon.	07/02/86	Wed.
14th	05/30/86	Fri.	06/03/86	Tues.	06/09/86	Mon.	07/02/86	Wed.

A76122778

FIGURE A-2. SCHEMATIC DIAGRAM OF THE FURNACE AND CELL ASSEMBLY
OF AN ATMOSPHERIC PRESSURE TESTING STATION

TABLE A-3. SUBTASK 2.3.2b IN-CELL TEST MATRIX

<u>No.</u>	<u>Metal Wt % / Wt %</u>	<u>Ceramic</u>	<u>Porosity %</u>	<u>Test I</u>	<u>Duplicate Test II</u>
1	50 Ni / 50 Cu	LiAlO ₂	45	X	X
2	50 Ni / 50 Cu	LiAlO ₂	60	X	X
3	30 Ni / 70 Cu	LiAlO ₂	45	X	X
4	30 Ni / 70 Cu	LiAlO ₂	60	X	X
5	100 Cu	LiAlO ₂	45	X	X
6	100 Cu	LiAlO ₂	60	X	X
7	50 Ni / 50 Cu	Conductive Ceramic	45	X	X
8	50 Ni / 50 Cu	Conductive Ceramic	60	X	X

Besides the metal-coated ceramic anode, other cell components include: a 70 mil hot-pressed tile containing 60% vol % of 62 mole % Li_2CO_3 /38 mole % K_2CO_3 electrolyte and 40 vol % LiAlO_2 ; a NiO in-situ oxidized cathode; a perforated stainless steel cathode current collector; a perforated nickel anode current collector; a machined, stainless steel cathode compartment flange; and a machined, stainless steel anode compartment flange. The cathode flanges will be pre-machined as fabricated cathodes become available. The anode flanges will be pre-machined, allowing for a 30 ± 1 mil electrode lip, according to the anode thickness tolerances noted above. The test conditions will be:

Average Cell Temperature:	925K
Pressure:	Ambient, Balanced Between Electrodes Within 5-Inch H_2O
Average Current Density:	200 mA/cm ²
Fuel Composition:	
H_2	48%
CO_2	32%
H_2O	20%
Oxidant Composition:	
O_2	14%
CO_2	29%
N_2	54%
H_2O	3%
Fuel Utilization:	85%
Oxidant Utilization:	50%

Electrochemical data (OCV, mV at 200 mA/cm²), cell temperature, and gas flow rates will be recorded and monitored on a daily basis. Cell resistance, polarization curves, gas crossover, wet seal efficiencies, and anode outlet gas analysis will be measured weekly. Within the time and costs constraints of the program, we will attempt to monitor displacement and/or changes in overall cell component thickness. These will be related to pre-test and post-test values and, in the case of the anode, to out-of-cell results.

A tentative schedule of testing is shown in Table A-4. This schedule is likewise "tight", presumes pre-test conformance to in-cell anode specifications and geometry, and is totally dependent on receiving 5" x 5" anodes from Ceramtec by June 26, 1986. Column 1 of Table A-4 lists the latest possible receipt dates of four sets of composition/porosity-by-test number samples, as per the test matrix of Table A-3. This test schedule is especially dependent on receiving the anodes to the 30 ± 1 mil thickness specification mentioned earlier. If this thickness tolerance can be consistently met, then the stainless steel anode compartment flanges can be pre-machined; allowing for this electrode lip thickness. If, on the other hand, the delivered anode thicknesses were to vary over a range larger than 29 mils < t < 31 mils (where t = thickness), then machining of the anode flanges must await delivery of each anode series (a set of four as per Table A-4) so that the flange's electrode lip could be "custom-cut". This would add at least 1 week per anode flange, or 4 weeks per test series to the test schedule of Table A-4; resulting in an extension of the final test end-date by 16 weeks. Also, this test schedule does not allow for unplanned equipment and/or cell

TABLE A-4. SUBTASK 2.3.2b IN-CELL TEST SCHEDULE

Ceramatec 4x4 Cell Tests

- For 16-~750 hour tests
- Each series will consist of four cells run simultaneously.

1 Receive Anode Material	2	3 Date	4 Day of Week	5 Test Ends Date	6 Day of Week	7 Test Hours	8 Complete Post-Test Analyses	9 Day of Week
06/26/86 Thursday	Start 1st Test Series (Test #1)	06/30	Mon.	07/31	Thurs.	744	08/21/86	Thurs
	Start Test #2, Series 1	07/01	Tues.	08/01	Fri.	744	08/22/86	Fri.
	Start Test #3, Series 1	07/02	Wed.	08/04	Mon.	792	08/25/86	Mon.
	Start Test #4, Series 1	07/03	Thurs.	08/04	Mon.	768	08/25/86	Mon.
07/31/86 Thursday	Start 2nd Test Series (Test #1)	08/04	Mon.	09/04	Thurs.	744	09/25/86	Thurs
	Start Test #2, Series 2	08/05	Tues.	09/05	Fri.	744	09/26/86	Fri.
	Start Test #3, Series 2	08/06	Wed.	09/08	Mon.	792	09/29/86	Mon.
	Start Test #4, Series 2	08/07	Thurs.	09/08	Mon.	768	09/29/86	Mon.
09/04/86 Thursday	Start 3rd Test Series (Test #1)	09/08	Mon.	10/09	Thurs.	744	10/30/86	Thurs
	Start Test #2, Series 3	09/09	Tues.	10/10	Fri.	744	10/31/86	Fri.
	Start Test #3, Series 3	09/10	Wed.	10/13	Mon.	792	11/03/86	Mon.
	Start Test #4, Series 3	09/11	Thurs.	10/13	Mon.	768	11/03/86	Mon.
10/09/86 Thursday	Start 4th Test Series (Test #1)	10/13	Mon.	11/13	Thurs.	744	12/04/86	Thurs
	Start Test #2, Series 4	10/14	Tues.	11/14	Fri.	744	12/05/86	Fri.
	Start Test #3, Series 4	10/15	Wed.	11/17	Mon.	792	12/08/86	Mon.
	Start Test #4, Series 4	10/17	Fri.	11/17	Mon.	768	12/08/86	Mon.

test failures. Should these unplanned events occur, they will be reported and their effect on the test schedule will be specified. The tentative end-date of the last test is November 17, 1986.

Task 2.3.3 Analyze Anodes Post-Test

Eight different anode composition/porosity combinations will be tested out-of-cell and in-cell. Although Ceramtec characterized the as-fabricated anodes to ensure compliance with target characteristics, IGT will also perform their own pre-test and post-test anode characterizations to obtain an accurate, internally consistent basis for evaluation of any observed changes in anode characteristics and to ensure confidence in stability and life projections. The routine pre-test anode analyses will include:

1. Chemical composition by atomic absorption and X-ray diffraction.
2. Thickness uniformity.
3. Density.
4. Porosity and pore spectrum.
5. Surface area.
6. Scanning electron microscopy (SEM) and elemental mapping of metal and ceramic constituents by energy dispersive X-ray (EDX).

We will also investigate the use of secondary Ion Mass Spectrometry (SIMS) in determining the coating uniformity at the submicron level. With SIMS, elemental composition is monitored as the sample is being etched by an ion beam, thereby establishing a depth profile for various elements. This technique has been suggested by McCrone Research Associates who are experienced in various microscopy techniques. However, because of the cost involved, only selected samples will be analyzed by SIMS. Alternatively, specially mounted samples may be used with SEM for coating uniformity analysis.

For the in-cell and out-of-cell tested anodes the following analyses and measurements will be performed:

1. Thickness measurements.
2. Chemical composition by atomic absorption and X-ray diffraction.
3. Density, surface area and pore spectrum of carbonate-free (i.e., "washed") anodes.
4. SEM and elemental mapping by EDX.
5. SIMS, as judged necessary.

To save analytical time, analysis will be scheduled monthly to test several samples at a time (e.g., Column 9 of Table A-2). Therefore, sample analyses will generally be completed the next month after the respective anode tests.

The analyses described above, combined with the creep test and cell test data from Subtasks 2.3.1b and 2.3.2b, will be used to evaluate stability mechanisms such as:

1. Metal phase restructuring such as sintering that leads to neck growth at the expense of surface coating.
2. Creep by particle rearrangement.
3. Creep by metal deformation at particle necks.
4. Reaction between ceramic particles and molten carbonate.
5. Change in pore structure as a result of above instabilities.
6. Change in fuel cell performance as a result of the above instabilities.

The out-of-cell creep tests at elevated pressures and temperatures were designed not only as accelerated tests but also to estimate activation energies to aid in characterizing mechanistic rates at given conditions. They should enable us to project long-term anode stabilities under realistic fuel cell conditions. They should enable us to project long-term anode stabilities under realistic fuel cell conditions. Stability data from cell tested anodes will then be superimposed over the generated out-of-cell data to validate the long-term predictions.

Anodes with the potential for meeting the target goals of performance, life, and strength will be identified for continued testing under Task 3. Recommendations to improve anode stability and to lower cost will be submitted.

END

**DATE
FILMED
9 / 3 / 92**