JUN 15 1992

**SUPERCLEAN COAL-WATER SLURRY COMBUSTION
TESTING IN AN OIL-FIRED BOILER**

Semiannual Technical Progress Report
for the Period 08/15/1991 to 02/15/1992

DOE/PC/88697--T5

DE92 018325

By

Bruce G. Miller, Co-Principal Investigator
Roger L. Poe, Research Assistant
Joel L. Morrison, Research Assistant
Jianyang Xie, Graduate Research Assistant
Peter M. Walsh, Faculty Associate
Harold H. Schobert, Co-Principal Investigator
Alan W. Scaroni, Project Manager

May 29, 1992

Work Performed Under Cooperative Agreement No. DE-FC2289PC88697

For
U.S. Department of Energy
Pittsburgh Energy Technology Center
Pittsburgh, Pennsylvania

By
The Combustion Laboratory
The Pennsylvania State University
University Park, Pennsylvania

WALSH

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by the United States Government. Neither the United States Government nor the United States Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	1
2.0 PHASE I: DESIGN, PERMITTING, AND TEST PLANNING	2
2.1 Task 3. Identify Operating Procedures	3
3.0 PHASE II: CONSTRUCTION AND START UP.....	6
3.1 Task 1. Host Site Readiness/Boiler Retrofit	6
3.2 Task 2. SCCWS Preparation	6
3.3 Task 3. Performance Prediction.....	7
3.4 Task 4. Shakedown Testing	7
3.4.1 Equipment Shakedown	7
3.4.2 Baseline Testing Firing Natural Gas	10
4.0 PHASE III: DEMONSTRATION AND EVALUATION	11
4.1 Task 1. Test Burn	11
4.1.1 Subtask 1a. SCCWS Combustion Performance	11
4.1.2 Subtask 1b. Slagging/Fouling Propensity; Corrosion Characteristics	12
4.1.3 Subtask 1c. Erosion Characteristics	13
4.1.4 Subtask 1d. Fuel Transport, Storage, and Handling Characteristics	20
5.0 PHASE IV: ADVANCED SYSTEM TESTS	22
6.0 MISCELLANEOUS ACTIVITIES	22
7.0 NEXT SEMIANNUAL PERIOD ACTIVITIES	22
8.0 REFERENCES	23
9.0 ACKNOWLEDGMENTS.....	24

1.0 INTRODUCTION

The Pennsylvania State University is conducting a superclean coal-water slurry (SCCWS) program for the United States Department of Energy (DOE) and the Commonwealth of Pennsylvania with the objective of determining the capability of effectively firing SCCWS in an industrial boiler designed for oil. Penn State has entered into a cooperative agreement with DOE to determine if SCCWS (a fuel containing coal with less than 3.0 wt.% ash and 0.9 wt.% sulfur) can effectively be burned in an oil-designed industrial boiler without adverse impact on boiler rating, maintainability, reliability, and availability. The project will provide information on the design of new systems specifically configured to fire these clean coal-based fuels. The project consists of four phases: (1) design, permitting, and test planning, (2) construction and start up, (3) demonstration and evaluation (1,000-hour demonstration), and (4) program expansion (additional 1,000 hours of testing). The boiler testing will determine if the SCCWS combustion characteristics, heat release rate, fouling and slagging behavior, corrosion and erosion limits, and fuel transport, storage, and handling characteristics can be accommodated in an oil-designed boiler system. In addition, the proof-of-concept demonstration will generate data to determine how the properties of SCCWS and its parent coal affect boiler performance. Economic factors associated with retrofitting and operating boilers will be identified to assess the viability of future oil-to-coal retrofits.

The project consists of four phases as previously mentioned. Following is an outline of the project tasks that comprise the four phases:

Phase I: Design, Permitting, and Test Planning

Task 1. Design

Task 2. Permitting

Task 3. Test Planning

Phase II: Construction and Start Up

Task 1. Host Site Readiness/Boiler Retrofit

Task 2. SCCWS Preparation

Task 3. Performance Prediction

Task 4. Shakedown Testing

Phase III: Demonstration and Evaluation

Task 1. Test Burn

Subtask 1.a. SCCWS combustion performance

Subtask 1.b. Slagging/fouling propensity; corrosion characteristics

Subtask 1.c. Erosion characteristics

Subtask 1.d. Fuel transport, storage, and handling characteristics

Task 2. Evaluate Retrofit Economics

Task 3. Project Report

Phase IV: Advanced System Tests

Task 1. Burner/Superheater Procurement/Installation

Task 2. SCCWS Preparation Facility

Task 3. 500-Hour Test

Task 4. Project Report

Task 5. Flue Gas Treatment System

Task 6. 500-Hour Test

Task 7. Final Report

Penn State began a coal-water fuel (CWF) research and development program in 1984 with the ultimate goal of facilitating the replacement of petroleum-based fuels with coal-based fuels in oil-fired (designed) boilers. The Pennsylvania legislature appropriated funds in 1984 for the construction of a demonstration CWF boiler with a capacity of approximately 15,000 lbs steam/h on the main campus of Penn State at University Park. The project goal was to conduct a demonstration of the use of CWF, derived from Pennsylvania coal, in an environmentally acceptable manner, while evaluating the effects on boiler performance of long-term firing with CWF. From a commercialization viewpoint, the motivation for the project was to demonstrate the technical feasibility of retrofitting existing oil-fired units to burn CWF, particularly in the commercial and light-industrial sectors. Funding each year since 1984 has allowed for fuel procurement and the installation of a nominally rated 1,000 lb steam/h (maximum firing rate of 2 million Btu/h) Cleaver-Brooks A-frame watertube boiler [1] to investigate: the effect of boiler operating parameters on combustion performance [2]; automation of the firing of slurry fuels, particularly with respect to start up and shutdown procedures but also for optimizing boiler performance [3]; testing candidate CWFs; and [4] providing the necessary research support and training prior to start up of the demonstration unit. The SCCWS demonstration program is being conducted on the 15,000 lb steam/h demonstration boiler.

Accomplishments this period are presented in Sections 2.0, 3.0, 4.0, 5.0, and 6.0 for Phases I, II, III, IV, and miscellaneous activities, respectively. Section 7.0 outlines the activities planned for the next semiannual period. References are contained in Section 8.0 and acknowledgments are given in Section 9.0. The status of the project schedule is given in Figures 1 through 5, with a description of the milestones contained in Table 1.

2.0 PHASE I: DESIGN, PERMITTING, AND TEST PLANNING

Phase I has been completed with the exception of identifying operating procedures (a portion of Task 3).

2.1 Task 3. Identify Operating Procedures

Work was initiated this semiannual period on preparing system operating manuals. Procedures were developed for SCCWS handling and storage and for maintaining proper boiler water chemistry. These will be incorporated into a system operating manual which is being prepared for the boiler and auxiliaries.

The procedure to start up the boiler is contained in the following subsections.

Preignition Panel Configurations

Baghouse Control Panel Configuration

- 1) Power switch..... ON
- 2) System clean switch..... ON

Motor Control Center

- 1) Feedwater pump..... ON
- 2) Slurry feed pump..... ON
- 3) Forced draft fan..... ON
- 4) Induced draft fan..... ON

Main Control Panel

- 1) Power switch..... ON
 - A) Silence alarm on main control panel
 - B) Silence alarm on baghouse control panel
- 2) Slurry transfer pump..... ON
- 3) Baghouse control system..... AUTO
- 4) Slurry burner pump..... OFF
- 5) Mastermind computer switch..... ON
- 6) Gas firing rate switch..... HAND
- 7) Gas valve control switch..... HAND
- 8) Slurry control switch..... HAND
- 9) Drum level control switch..... AUTO
- 10) Induced draft control switch..... PHOTOHELIC
- 11) Manual firing rate potentiometer..... 0%
- 12) Gas trim switch..... CENTER
- 13) Slurry firing potentiometer..... 0%
- 14) Feedwater control potentiometer..... 0%
- 15) Circular chart recorders..... ON
- 16) Oxygen analyzer..... ON
- 17) Emergency shutdown switch..... OUT
- 18) Photohelic setpoint..... -2" H₂O

Keeler Control Panel

- 1) Breaker switch ON
- 2) Burner control switch OFF
- 3) Forced draft switch AUTO
- 4) Fuel selector switch GAS
- 5) Coal slurry switch OFF
- 6) Duct burner switch OFF

Startup of Boiler

Mechanical Items

- 1) Open both gas valves on the side of the boiler
- 2) Open the gas valve at the burner
- 3) Pull the slurry gun back to the light-off position
- 4) Verify that the atomizing air valve to the gun is closed
- 5) Verify that the slurry valve to the gun is closed
- 6) If the steam pressure is less than 150 psig, see cold startup
- 7) If the steam pressure is 150 psig or greater, proceed to control items

Control Items

- 1) Set control items as listed on control configuration
- 2) Verify that water column has proper level
- 3) Verify that the forced draft fan is running
- 4) Verify that the induced draft fan is running
- 5) Verify that the feedwater pump is running
- 6) Verify a minimum draft of -0.1" H₂O at the photohelic

Lighting the Burner

- 1) Turn the burner control switch to ON
- 2) Safety limit light will illuminate BLUE
- 3) Operating limit light will illuminate GREEN
- 4) Forced draft damper will begin to open
- 5) Maxon gas valve will begin to open
- 6) Purge light will illuminate WHITE
- 7) Purge light will remain on for 60 SECONDS
- 8) Purge light will illuminate GREEN
- 9) Forced draft damper will return to original position
- 10) Maxon gas valve will return to original position 1
- 11) Ignition will hold 10 seconds while draft equalizes
- 12) Ignition on light will illuminate with pilot BLUE

- 13) Gas light will illuminate with ignition of main flame..... BLUE
- 14) Ignition on light will go out BLUE
- 15) The burner is now on line

NOTE: If the burner fails to light two audio alarms will sound. One alarm will be at Keeler's control panel, the other at the main control panel. To silence the alarm at Keeler's control panel, the burner switch must be reset. To silence the alarm at the main control panel, push the illuminated alarm acknowledge button on the upper right side of the panel. When the alarms are silenced, the burner can be lighted according to the above procedure. If the burner does not light after three attempts, check the preignition configuration of valves and switches and try again. If the burner still fails to light, shut down the boiler and contact the designated person prior to opening any of the control panels.

Cold Startup of Boiler

Mechanical Items

- 1) Open both gas valves on the side of the boiler
- 2) Open the gas valve at the burner
- 3) Pull the slurry gun back to the light-off position
- 4) Verify that the atomizing air valve to the gun is closed
- 5) Verify that the slurry valve to the gun is closed
- 6) If the steam pressure is zero, the steam drum must be vented
- 7) To vent the steam drum, open both gate valves on the top of the drum

CAUTION: Some steam will exit valves

Control Items

- 1) Set control items as listed on control configuration
- 2) Verify that water column has proper level
- 3) Verify that the forced draft fan is running
- 4) Verify that the induced draft fan is running
- 5) Verify that the feedwater pump is running
- 6) Verify a minimum draft of -0.1" H₂O at the photohelic

NOTE: Steam will vent from valves at steam drum

Lighting the Burner

- 1) Turn the burner control switch to..... ON
- 2) Safety limit light will illuminate BLUE
- 3) Operating limit light will illuminate..... GREEN
- 4) Forced draft damper will begin to open
- 5) Maxon gas valve will begin to open
- 6) Purge light will illuminate WHITE

- 7) Purge light will remain on for..... 60 SECONDS
- 8) Purge light will illuminate GREEN
- 9) Forced draft damper will return to original position
- 10) Maxon gas valve will return to original position..... 1
- 11) Ignition will hold 10 seconds while draft equalizes
- 12) Ignition on light will illuminate with pilot BLUE
- 13) Gas light will illuminate with ignition of main flame..... BLUE
- 14) Ignition on light will go out BLUE
- 15) The burner is now on line
- 16) After fifteen minutes at low fire, shut the burner down
- 17) Wait fifteen minutes and then relight the burner
- 18) When the steam pressure is 5 psig, close the vent valves
- 19) Repeat #16 and 17 until pressure reaches 150 psig
- 20) At 150 psig, the burner can remain on
- 21) The firing rate can now be increased

NOTE: Do not increase the firing rate more than 10% at any time. Doing so will result in high boiler water alarms.

3.0 PHASE II: CONSTRUCTION AND START UP

3.1 Task 1. Host Site Readiness/Boiler Retrofit

The building addition (boiler room) to the East Campus Steam Plant was completed and the majority of the equipment was delivered and installed during the previous two reporting periods [4,5]. Details of the boiler and auxiliary equipment have been given elsewhere [4,6]. Figure 6 is an isometric drawing of the boiler system (not to scale).

The remaining items that were delivered and/or installed this reporting period include: baghouse insulation; SCCWS piping insulation and heat tracing; shelter to protect the double-diaphragm slurry handling pump from the elements, primarily to guard against freezing; electric hookup for the fly ash conveying system (to transport the ash from the ash storage hopper located below the baghouse ash hopper to a truck); safety railings on the 16,000-gallon SCCWS storage tank and boiler house roof; safety ladders for access to the boiler house roof and the top of the 16,000-gallon storage tank; and the auxiliary in-duct natural gas burner. This completes the facility construction task.

3.2 Task 2. SCCWS Preparation

This section summarizes the activities to clean coal and prepare SCCWS during this reporting period. Details of the coal company, coal cleaning facility, and SCCWS preparation facility have been previously reported [5].

Preparation of the Clean Coal Feedstock

A total of 367 tons of Brookville seam coal was cleaned at the Reddinger Coal Company wash facility. The average yield was 51.2 % which provided approximately 189 tons of clean coal feedstock. Table 2 contains a history of the raw coal shipments to Reddinger Coal Company and the cleaned coal to Kennedy Van Saun Company (KVS). Table 3 summarizes the coal quality from the last cleaning run.

Slurry Procurement

KVS prepared approximately 120 tons of coal-water slurry and Tables 4 to 8 summarize the solids loading, particle size distribution, viscosity, pH, coal feed rates, and additive dosages for the production runs. The SCCWS was transported from KVS to Penn State via 5,600 gallon single compartment stainless steel tankers. Six tankers were received this reporting period and unloaded into the 16,000-gallon storage tank upon arrival. The tankers were received over a six week period. Table 9 contains the SCCWS delivery history.

3.3 Task 3. Performance Prediction

One aspect of the project is to predict the performance of the boiler firing SCCWS. Burns & Roe Services Corporation has developed a model to predict the performance of a multifuel industrial boiler and applied it to the Penn State system. Details of the model are contained elsewhere [7].

The model was compared with experimental data obtained when operating the boiler firing natural gas and during preliminary shakedown with SCCWS (see Sections 3.4.2 and 4.1.1, respectively, for details of the testing). Figure 7 compares the predicted values for the flue gas outlet temperature from the heat pipe heat exchanger with the measured data, obtained when firing the boiler with natural gas, as a function of firing rate. Figure 8 shows the corresponding boiler exit gas temperatures. As shown in both Figures 7 and 8, the predicted values follow the same trends as the experimental data and the agreement is good given the uncertainties in some of the input variables (*i.e.*, flame and cold surface emissivities). In general, for the above experiments, the predicted values are lower than the measured data with a maximum difference of about 30°F.

Figure 9 shows the boiler outlet gas temperature for the case of dual fuel firing (SCCWS and natural gas). The predicted boiler exit gas temperature varies from 520 to 580°F depending on the amount of gas cofired with SCCWS.

This preliminary comparison indicates a high level of confidence in the model. However, more data are needed to fully validate the model. This will be done as more data become available.

3.4 Task 4. Shakedown Testing

3.4.1 Equipment Shakedown

Construction of the facility was completed during the previous reporting period (Spring of 1991), followed by equipment shakedown and preliminary testing. The sequence of events was:

the natural gas burner set-up and equipment shakedown firing natural gas were conducted during the summer of 1991; baseline data firing natural gas were generated in September 1991; preliminary natural gas and SCCWS cofiring data were generated in October 1991; further equipment shakedown and boiler performance testing were conducted in January 1992 firing SCCWS; and boiler performance and stack (emissions) testing were conducted in January 1992 as partial requirement for an operating permit from the Pennsylvania Department of Environmental Resources. Several operational/mechanical problems were encountered during this period and a brief summary of these problems and their solutions are provided.

Balancing the Draft in the System

The Tampella Power Corporation DS-15 oil and gas-fired package boiler is typically installed with a forced draft system since particulate control is not of concern. Consequently, difficulty was encountered in integrating the operation of the boiler, the forced draft fan/air damper, and the induced draft fan. This was the responsibility of the system controls contractor, Industrial Controls, Inc. (ICI). Initially, the movement of the forced draft and induced draft dampers was not synchronized during the purge cycle and pilot flame ignition, resulting in excessive pressure swings in the boiler. This caused rumbling in the ductwork, difficulty in igniting the pilot flame, an unstable pilot flame when it could be ignited, and overpressurization of the boiler. Although ICI and Tampella Power install balanced draft boilers and control systems, this was the prototype installation of a balanced draft control system on a boiler designed for forced draft only. This issue was solved by programming delays into the timing cycle to eliminate the lead/lag problem of the dampers.

Baghouse Hopper Ash Level Sensor Failure

The boiler was operated cofiring natural gas and SCCWS in October 1991 to begin generating SCCWS data. The boiler was fired intermittently during an equipment shakedown period which was followed by 2-3 days of continuous operation. Details of the preliminary testing are presented in Section 4.4.1.

The testing was prematurely terminated because the baghouse hopper ash level sensor failed and the baghouse filled with ash and unburned carbon. Ash was being removed from the baghouse hopper into an ash storage hopper which was located directly below the baghouse hopper. The problem of excessive ash build-up in the baghouse was not detected because the high ash level sensor failed, there was no change in the baghouse pressure drop, and ash was visually observed being removed from the baghouse. The first indication of problems was the formation of a black plume from the stack. Initially it was thought that a bag had become detached in the pulse-jet baghouse or a bag had developed a hole. Shortly thereafter the baghouse outlet temperature began to rise and the testing was terminated.

A door on the side of the baghouse hopper was opened and it was discovered that the baghouse was filled with ash/unburned carbon. The material was removed and the baghouse inspected for damage. It was found that all the bags and many of the cages and venturiers needed to be replaced as did a portion of the plenum which had warped. The system was down for approximately one month while the plenum was repaired and the replacement parts were received and installed.

Several changes were made to the system to ensure that a similar incident will not recur. The lower ash hopper was removed and replaced with a conditioning screw that mixes water with the ash and discharges the mixture onto the back of a truck. The rotary valve at the bottom of the hopper is set at a speed that overcompensates for ash production so that there is no buildup of ash in the hopper. Three ash level sensors have been installed in the baghouse ash hopper to ensure that ash accumulation in the hopper will be detected. Some operating time firing SCCWS for boiler optimization and stack testing has been achieved with the modifications and the system has performed satisfactorily.

Boiler Optimization on SCCWS

The boiler performance guarantees specified in the bidding package state that the boiler must be capable of producing ~15,000 lb saturated steam/h with a steam quality of $\geq 99.5\%$ and provide a burner turndown of 10:1 when firing natural gas. The guaranteed steam production rate is slightly less than the design rate of 15,000 lb/h because Tampella Power Corporation removed two rows of tubes from the convective pass to allow for the insertion of erosion and deposition probes (and a superheater probe in the future). The boiler must also be able to fire natural gas and SCCWS singly or in any combination either manually or automatically. Turndown of the burner firing SCCWS must be 4:1.

The boiler performance guarantees have been met firing natural gas; but to date, Tampella Power Corporation has not been able to fire SCCWS solely. The boiler can be operated manually but the automatic control has not yet been fully tested.

The mechanical contractor, KirCon-Breco (details of contractors and their responsibilities are contained in references [8] and [9]) and Tampella Power Corporation used several different nozzle combinations in order to improve atomization and carbon burnout and eliminate natural gas support. This optimization work was conducted in January 1992. A summary of the operating conditions is contained in Section 4.1.1. The highest carbon burnout achieved was ~80% with 32% (on a thermal input basis) natural gas support. Tampella Power Corporation maintains that the solids content of 50 to 58 wt.% in the SCCWS (solids content decreased due to settling) is too low to fire 100% SCCWS. As a result, Penn State recommended to the Pennsylvania Department of General Services (which is responsible for management of the construction project) that the contractor be relieved of this performance guarantee.

A plan has been implemented to improve the carbon burnout and decrease/eliminate natural gas support. One option, the use of SCCWS preheat, was being evaluated when problems were encountered with the forced draft damper. The flame from the auxiliary in-duct gas burner was impinging on, and warped, the damper causing it to seize during operation. Two solutions are being investigated: shortening the in-duct gas burner flame length by reducing the gas pressure and installing an impingement plate; and turning the in-duct burner 90° to fire into the flow of the incoming combustion air stream rather than towards the boiler (damper) cocurrent with the combustion air stream.

Additionally, the atomization air pressure will be increased to ~200 psig, high-pressure atomizing steam (~210 psig) will be used, and various atomizers will be tested in conjunction with the Faber burner. Both internal- and external-mix atomizers will be used. Additional modifications being considered include replacing the existing burner with either a high-swirl burner/atomizer combination or a refractory-lined (quench) burner assembly.

3.4.2 Baseline Testing Firing Natural Gas

Preliminary testing conducted this reporting period consisted of generating baseline data firing natural gas and cofiring natural gas with SCCWS. The testing was conducted as part of the equipment shakedown process and to determine system performance. The results of the natural gas-fired baseline testing is presented in this section and the SCCWS/natural gas cofiring results are presented in Section 4.1.1.

Baseline data were obtained on two occasions firing natural gas. The first was used to measure the performance of the combustion air/flue gas heat pipe heat exchanger while the second was used to verify the performance guarantee of the boiler. A summary of the baseline performance firing natural gas in the boiler is presented in Table 10.

The testing in September was conducted for ABB Air Preheater Inc. (API) to collect gas-fired performance data for the Q-Pipe® Air Preheater. The heat pipe heat exchanger preheats the combustion air by extracting heat from the flue gas. API installed over 100 thermocouples on the heat pipes and collected continuous temperature readings using a computerized data acquisition system. The objective of the testing was twofold: to collect baseline gas-fired temperatures and gas velocities with clean heat pipes (prior to any SCCWS, and hence ash, being introduced) to assist in future heat exchanger design and to determine heat pipe fouling factors when firing coal-based fuels in the boiler. The air preheater bulk gas temperatures are shown in Table 10.

Testing was conducted in January by KuCon-Breco and Tampella Power Corporation as part of the boiler performance guarantee. A summary of these results are given in Table 10. The boiler met the performance guarantees firing natural gas. Performance items of primary concern that were met included: 10:1 turndown, 14,900 lb saturated steam/h at 250 psig, and steam quality >99.5%.

4.0 PHASE III: DEMONSTRATION AND EVALUATION

4.1. Task 1. Test Burn

4.1.1 Subtask 1a. SCCWS Combustion Performance

Preliminary Results Cofiring SCCWS and Natural Gas

Baseline data firing SCCWS were collected on two occasions. The first, occurring in October 1991, consisted of 66.5 hours of testing (35 hours of steady-state) and was conducted following equipment installation and initial shakedown to further debug the system. The second, occurring in January 1992, consisted of 26 hours of testing of which 10 hours were part of the boiler performance verification test. The SCCWS analysis and a summary of the test results are contained in Tables 11 and 12, respectively. The coal ash content from which the SCCWS was produced was 4.3 wt.%, which is greater than that of the cleaned coal produced at Reddinger Coal Company (3.4 wt.% in Table 4). This discrepancy is probably due to an unrepresentative sample being collected at Reddinger Coal Company prior to shipping to KVS.

The October test was conducted after the equipment had been installed and served as a systematic check of the components. The testing was terminated when the baghouse hopper ash level sensor failed (see p. 8). The SCCWS preheater and in-duct auxiliary gas-fired burner were not operated and Tampella Power Corporation had not begun their optimization tests during which atomizer nozzles and plugs were interchanged to select the best combination. It became apparent early in the testing that combustion efficiency was very poor (~82%).

The system was operated again in January 1992 at which time Tampella Power Corporation conducted their optimization tests. The tests were performed firing the in-duct burner to gain additional combustion air preheat; however, the SCCWS preheater was not used. After Tampella Power Corporation identified their best atomizer nozzle/plug combination, the boiler performance and emissions tests were conducted. The combustion efficiency of the SCCWS was still very poor (78%) and the boiler efficiency was only about 70%. The baghouse efficiency was >99%.

The SCCWS that was used for the January test experienced settling and the solids content was around 50 wt.% at the time of this test. Fly ash particle size analysis of the material discharged from the baghouse indicated poor atomization. Table 13 lists the fly ash particle size distribution of samples collected every hour during the January emissions testing. The volumetric mean diameter, $D(v, 0.5)$, increased from 85 to 188 μm over the duration of the testing as compared to the targeted atomized slurry droplet $D(v, 0.5)$ of $\leq 80 \mu\text{m}$. In addition, the top size in many of the samples was >564 μm . As previously discussed, further testing is planned to improve the boiler performance.

4.1.2 Subtask 1b. Slagging/Fouling Propensity: Corrosion Characteristics

Bench-Scale Testing

Bench-scale testing on corrosion and deposition was initiated this reporting period. The objective of the bench-scale testing is to develop a model to predict deposition in the 15,000 lb steam/h boiler. The five alloys identified for preliminary bench-scale testing were grades 316, 321, 304, 347, and 800H steel. Samples of the alloys, of dimensions 1.0" by 1.0" by 0.5", were prepared from bar-stock rounds. Cylindrical pieces were cut from the bar-stock using a band saw and shaped using a milling machine. Samples were ground using a disc sander with 80 grit paper, after which they were ground on a wheel sander using 100, 240, 320, 400, and 600 grit silicon carbide papers. The samples were then thoroughly cleaned and de-greased with acetone. The weights of the samples were recorded prior to testing. Figure 10 shows the metallographic characterization of the five alloys.

Ash was recovered from test firings of the SCCWS in the 1,000 lb steam/h watertube research boiler. Details of the research boiler have been presented elsewhere [1,2]. The analysis of the ash is contained in Table 14. Each sample was placed in a ceramic crucible containing 10 grams of the ash so that the specimens were completely submerged. The crucibles were then placed in a Rapid Heating Furnace and heated to 1,000°C for a period of 48 hours under inert conditions by flushing the furnace with nitrogen gas.

The samples were removed from the crucibles after cooling and were examined for corrosion. The samples appeared to have a thick crust of bonded deposits. Photographs and scanning electron microscope (SEM) photomicrographs of the deposit surface on each of the specimens were taken (Figures 11 and 12). The samples were then exposed to a descaling treatment after which the weight loss of each coupon was recorded. The procedure for the descaling treatment was:

Step 1

- Boil in water for 5 minutes
- Drain
- Cool
- Rinse with hot running water
- Boil for 10 minutes to remove the balance of the soluble deposit
- Dry

Step 2

- Boil for 15 minutes in 20% NaOH solution
- Rinse in hot running hot water

Step 3

- Boil 15 minutes in 15% nitric acid
- Cool, rinse

Step 4

- Repeat steps 2 and 3
- Rinse, dry, and examine

The weight loss experienced by the specimens is listed in Table 15 and illustrated in Figure 13. Photographs and SEM photomicrographs of the descaled specimens were recorded (Figures 14 and 15).

Future Research

A laboratory simulation of the corrosion environment in a boiler has been set up, where coupons of the alloys will be exposed to a simulated flue gas at different test temperatures for a test period of 48 hours. The coupons removed after exposure will be subjected to metallographic characterization and weight loss data will provide a quantitative estimate of the corrosion rate under accelerated conditions. Before exposure to the simulated flue gas, the coupons will be covered with a layer of ash recovered from the tube banks of the demonstration boiler.

4.1.3 Subtask 1c. Erosion Characteristics

In order to make a connection between the measurements of erosion using the probe developed for this program, which are accelerated by increasing the gas velocity, and the erosion expected in a boiler under normal operating conditions, a model for erosion under both sets of conditions is needed. Details of the probe and experimental results have been previously reported [5,10].

A model has been developed for the calculation of metal wastage at high temperature in oxidizing atmospheres. Individual model parameters were obtained for carbon steel, based on available experimental results in the literature. Calculations of erosion rate as a function of the following variables are presented in this section; particle impingement angle, metal temperature, particle velocity, particle diameter, and particle concentration.

Erosion Model

Most metals and alloys used in high-temperature applications are exposed to environments in which they are chemically unstable. In the majority of cases, the most stable species are metal oxides. Oxide-forming reactions are of course, favored by the presence of oxidants in the gas stream at high temperature. The corrosive conversion of metals to oxides is an important step affecting the subsequent erosion mechanism.

Sundararajan, 1991 [11] has presented an excellent review of the literature on erosion of metals at elevated temperatures. Unfortunately, current knowledge of the relationships between erosion rate and temperature is, at best, qualitative. One approach to the prediction of erosion in an

oxidizing atmosphere, accounting for oxide spalling on each particle impact, is presented by Wright and Sethi, 1991 [12]. This approach is suitable for conditions under which the bonding of the surface oxide to the metal substrate is less strong than the internal bonding of the oxide, and where the scale thickness is neither extremely thick nor thin. When the scale thickness is large, the effect of particle impact is limited in the oxide layer; and when the scale layer is thin, the impacting particle can directly attack the metal substrate. In both those cases, the distinction between spalling and nonspalling of oxides is of less importance.

The present erosion model is intended for conditions under which surface erosion and oxidation occur at comparable rates. The impacting particles are allowed to interact with the growing oxide scale in various ways. Depending upon the severity of the particle impact with the surface, the thickness of the oxide scale, and the properties of the alloy substrate, the erosion event may lead to the removal of fragments of the oxide scale, to shedding or spalling of the oxide at the oxide-metal interface, or to the removal of substrate metal.

The growth rate of the oxide scale on a metal surface by oxidation is given by:

$$\frac{dx}{dt} = \frac{k_o}{x^z} \quad (1)$$

Thus, the scale thickness attained in a time interval t_i , between successive particle impacts, can be obtained from equation (1) as:

$$x_i = \left[(z+1) k_o t_i \right]^{\frac{1}{z+1}} \quad (2)$$

where x is the thickness of oxide scale; z is the order of the oxidation kinetics ($z=0$, linear kinetics; $z=1$, parabolic kinetics), and k_o is the oxidation rate constant, usually having the form:

$$k_o = A \exp (- \Delta G / RT) \quad (3)$$

where A is the frequency factor, ΔG is the activation energy of the rate-controlling step in the oxidation process, R is the Universal Gas constant, and T is the reaction temperature.

In most common cases, the impinging particles are suspended in the fluid and their physical parameters are measurable. If a specific type of particle is present and a uniform flow field is assumed, the mathematical expression for the impact time interval t_i is:

$$t_i = \frac{d_p}{v_p} \sqrt[3]{\frac{\pi \rho_p}{6 C_p}} \quad (4)$$

and the number of impacts over a surface area S is:

$$N = \eta \frac{S}{d_p^2} \sqrt[3]{\left(\frac{6 C_p}{\pi \rho_p}\right)^2} \quad (5)$$

where η is the coefficient of particle impact on the target surface, C_p is the concentration of particles with units of mass per unit of gas volume, v_p , ρ_p , and d_p are the velocity, the density, and the diameter of particles, respectively.

If each particle upon impact penetrates the growing oxide scale and reaches the metal substrate, erosion losses are most likely to consist of both the oxide and the metal. Levy, 1983 [13] indicated that the presence of the ductile metal substrate does not appear to have a major effect on the way that the brittle scale is eroded, so the combined erosion of the ductile metal and the brittle oxide will contribute to the losses from the surface material. A reverse rule of mixtures was found to be in good agreement with a series of erosion processes where one component is first removed before the second is eroded [14]. Using this rule for the erosion of the oxide/metal composite, the total loss of surface volume is given by:

$$\frac{1}{E_t} = \frac{1-f}{E_d} + \frac{f}{E_b} \quad (6)$$

where f is the volume fraction of the oxide scale in the eroded mixture; E_d and E_b are, respectively, the erosion losses of the ductile metal and the brittle oxide by the same impact. This equation represents a linear combination of the erosion resistances from metal and oxide.

The volume of the oxide scale eroded by a number of particle impacts, N , on a surface area, S , is $(x_i S)$, and the volume fraction, f , is:

$$f = \frac{\left(\frac{x_i S}{N}\right)}{E_t} = \left(\frac{x_i S}{N}\right) \left(\frac{1-f}{E_d} + \frac{f}{E_b}\right) \quad (7)$$

or

$$f = \frac{\left(\frac{x_i S}{N}\right) \frac{1}{E_d}}{1 + \left(\frac{x_i S}{N}\right) \left(\frac{1}{E_d} - \frac{1}{E_b}\right)} \quad (8)$$

The total erosion-oxidation loss of metal volume by each impact is:

$$E_m = \frac{x_i S}{N} \frac{1}{c} + \left(E_t - \frac{x_i S}{N}\right) \quad (9)$$

where c is a metal system constant, the ratio of the volume of the oxide formed to the volume of the metal consumed.

In the case where the particle does not penetrate the growing oxide scale, a continuous oxide layer will be present, the thickness of which balances the competing rates of oxidation and oxide erosion:

$$\frac{dx}{dt} = \frac{k_o}{x^2} - \frac{E_b N}{S} \quad (10)$$

With an increase in the scale thickness, x , the growth rate, dx/dt , decreases. Finally a stable scale thickness will be formed under steady state conditions:

$$x_{ss} = \frac{k_o S}{E_b N} \quad (11)$$

Since all material removed in this case is surface oxide, f is equal to one in equation (6), and E_t is equal to E_b , the loss of fragments of the oxide scale by micro-chipping.

In the special case that the oxide scale has poor adherence to the metal substrate, and the potential oxide scale (thickness) is not enough to prevent particle impact at the interface between the metal and the oxide, the material removal by each particle impact may be completely due to the spalling of the oxide scale over a large area. In this case, E_t is the loss of oxide due to spalling, which depends entirely on the oxidation rate ($E_t = x_i S/N$) rather than on the brittle chipping of the oxide scale, E_b . Therefore the metal loss by oxide spalling is simply given by the first term in equation (8).

A critical thickness of oxide deformation, as suggested by Sundararajan, 1991 [15], has been used to estimate the potential range of oxide spalling:

$$x_c = \beta d_p \rho_p^{1/3} v_p^{2/3} H_t^{-1/3} \quad (12)$$

where β is a constant of the order of unity, H_t is the hardness of the oxide, d_p , ρ_p , and v_p are the particle diameter, density, and velocity, respectively. Beyond this critical thickness, the erosive deformation is limited to the oxide scale, and no spalling of the oxide occurs.

Determination of of Model Parameters

Many studies have been made of the rate of oxidation of iron at elevated temperature. It is generally agreed that the growth of oxide scales on iron follows a parabolic rate law, while considerable disagreement exists in the literature about which species of oxide are stable in the temperature range of interest. The discussion here will be concerned only with temperatures below 570°C, and magnetite is assumed to be the major component of the oxide scale. At such conditions, a parabolic rate constant has been obtained from the experimental result of Davies et al, 1951 [16]:

$$k_o = 1.8466 \times 10^{42} \exp\left(-\frac{780,000}{R T}\right) \text{ m}^2/\text{s} \quad (13)$$

Although the study of the interaction between metal erosion and oxidation has only recently been pursued, the fundamental nature of metal erosion at room temperature has long been distinguished from that of oxide erosion. If the erosion of ductile metal is characterized by two mechanisms: cutting and repeated yield deformation, the erosion rate can be expressed as the sum of the following two terms, (Neilson and Gilchrist, 1968 [17]):

$$E_d = \begin{cases} \frac{\frac{1}{2} m_p (v_p^2 \cos^2 \alpha) \sin(n\alpha)}{\sigma_C} + \frac{\frac{1}{2} m_p (v_p \sin \alpha - v_i)^2}{\sigma_D} & (\alpha \leq \alpha_0) \\ \frac{\frac{1}{2} m_p (v_p^2 \cos^2 \alpha)}{\sigma_C} + \frac{\frac{1}{2} m_p (v_p \sin \alpha - v_i)^2}{\sigma_D} & (\alpha > \alpha_0) \end{cases} \quad (14)$$

where α is the angle of particle impingement, α_0 equals $\pi/2n$, n is a parameter which characterizes the maximum erosion at a certain α value, v_i is the particle velocity at incipient erosion, σ_C and σ_D are the erosion resistances of the material from the two mechanisms separately.

Based on a theoretical estimation by Engel, 1978 [18], the value of the threshold velocity v_i is negligible relative to the value of v_p of interest. The erosion tests carried out in argon by Shida and Fujikawa, 1985 [19] showed that the erosion rate of carbon steel was maximized at a 30° angle, corresponding to an n value of 2. At normal impact, the erosion rates of the different steels were nearly the same, and appeared insensitive to temperature at elevated temperatures. Hence, a value for the constant σ_D , of $1.5833 \times 10^{13} \text{ J m}^{-3}$ in equation (14) was obtained. The variation is

the erosion rate at oblique angles with temperature at elevated temperatures has been correlated by σ_c as a function of temperature:

$$\sigma_c = 9.8213 \times 10^{17} T^{-1.82} \exp\left(-\frac{5800}{RT}\right) \text{ J m}^{-3} \quad (15)$$

For oxide erosion, a distinguishing feature is the maximum erosion rate at normal incidence. The following equation is an approximation based on the work of Sheldon, 1970 [20] on the Hertzian contact cone and indentation impression:

$$E_b \propto \frac{E^{0.8}}{s_b^2} d_p^3 \rho_p^{1.2} (v_p \sin \alpha)^{2.4} \quad (16)$$

where E and σ_b are the modulus of elasticity and the flexural strength of the target material, respectively; and d_p , ρ_p and $v_p \sin \alpha$ are the diameter, density, and normal velocity component of the abrasive particle. According to Evans, 1979 [21] for plastic impact response, the strength of the target σ_b would be diminished by the formation of radial and lateral cracks under particle impact:

$$\sigma_b \propto \frac{k_t^{1.4}}{(v_p \sin \alpha)^{0.5} d_p^{0.8}} \quad (17)$$

where k_t is the fracture toughness of the target material. Combining this equation with the previous erosion equation (16), the erosion rate can be expressed as:

$$E_b = C_b d_p^{4.6} \rho_p^{1.2} (v_p \sin \alpha)^{3.4} \quad (18)$$

where $C_b \propto E^{0.8}/k_t^{2.8}$ is a property parameter of the target material. For the oxide scale formed on carbon steel, C_b is estimated to be $1.8163 \times 10^{-7} \text{ kg}^{0.5} \text{ m}^{-1} \text{ J}^{-1.7}$ from the erosion rate provided by Sethi et al 1989 [22], when the rate of carbon steel removed by particles of velocity 2.7 m/s in an oxidizing gas at a temperature of 836 K was confirmed to be in the oxide erosion regime.

Comparison of Model Calculation and Experimental Results

For both spalling and adherent (or nonspalling) oxides formed on a metal surface, the erosion rates of carbon steel have been calculated by the present model. Figure 16 shows the results as compared to Sethi et al's experimental values [22]. The prediction of adherent oxide is close to the experimental values in both Figures 16 (a) and (b), corresponding to particle velocities

of 2.7 m/s and 4.7 m/s respectively, while the prediction from spalling oxide is several orders of magnitude larger than the measured value. However, the temperatures for the formation of critical scale thickness, beyond which no spalling will occur, are 722 K and 732 K for the conditions in Figures 16 (a) and (b), respectively. These temperatures are near the transition temperatures at which the experimental erosion rates begin to decrease with increasing temperature. So the erosion of oxide could be the combined result of partial spalling at the oxide-metal interface and micro-chipping of the oxide.

Effects of Erosion Variables

Particle Impact Angle

It is generally believed that metal loss is maximized at a 30° impact angle. However, at high temperature, under oxidizing conditions, the impact of a particle at higher impingement angles may result in severe erosion. Figure 17 shows the effect of particle impact angle on the erosion rate. In the range from 30° to 90°, the erosion rate has almost no dependency on impact angle. Only when the angle is smaller than 30°, does the erosion rate of adherent oxide decrease.

Metal Temperature

As shown in Figure 18, the effect of metal temperature on the erosion rate of carbon steel increases dramatically at temperatures above 600 K. For an increase in temperature from 600 to 650 K, the erosion rate increases by an order of magnitude. Above 650 K, the erosion rate tends to be a constant value. However, as reported in recent work [23], the complicated actions of deposition and oxide spalling occur over large areas. Hence, it is recommended that the use of carbon steel be limited to temperatures less than 600-650 K for the conditions of the calculation.

Particle Velocity

In most coal-fired boilers, the flue gas velocity in the convective section is between 10 and 18 m/s. In order to increase heat transfer rates and to reduce the size of the back of the boiler, one common design feature is that the flue gas velocity near the economizer is about 30-50% larger than that in the superheater or reheater. As shown in Figure 19, this variation has a very negative effect on the life of the economizer, since a change in velocity from 10 to 20 m/s is in the region in which the erosion rate of the adherent oxide increases rapidly.

Particle Concentration

As shown in Figure 20, erosion rate is a linear function of particle concentration. Therefore, when the ash content is high, the flue gas velocity should be limited to lower values.

Particle Diameter

At a given particle concentration, the erosion rate of metal without oxidation appears to be independent of particle size (Figure 21). For the erosion of the adherent oxide, an increase in particle size from 50 to 100 μm , increased the erosivity of the particles by an order of magnitude. The decrease in erosion rate following the maximum is due to the increase in the interval time

between successive impacts, and the rate of oxide formation during this interval will decrease, following a parabolic rate, therefore less oxide or metal is removed on impact by the same mass of particles.

Summary

The erosion rate of metals with adherent oxide was found to be nearly one order of magnitude larger than that for metals without oxidation. Therefore, any change in conditions which affects the conversion of metal to the oxide will change the erosion rate, and the erosion rate is maximized under conditions where the oxide can be continuously removed from the metal surface as it forms.

Metal temperature and particle velocity are two important parameters which dominate the life of a heat exchanger tube. Small particle size is preferred for the purpose of extending tube life. The present model provides a guide for the optimum design and operation of boilers from an erosion viewpoint.

Two possible effects which have not been accounted for in the present model are differences in erosivities of ash particles and the acceleration of oxidation in the presence of sulfur. However, the model will be refined in future work. The model parameters which should be used for the ash particles produced from the combustion of SCCWS will be established during future erosion testing.

4.1.4 Subtask 1d. Fuel Transport, Storage, and Handling

Characteristics

The SCCWS storage and handling system was originally designed such that a portable double-diaphragm pump and hoses were used to unload slurry from a tanker into the 16,000-gallon storage tank. The storage tank was hard piped to the 2,000-gallon day tank. After receiving several shipments of slurry for shakedown testing during the summer (1991), it became apparent that the design was too manpower intensive and of limited versatility. Therefore, the SCCWS unloading station was modified and now contains the following attributes. The entire system is hard piped using 2.5" schedule 40 pipe, heat traced, and insulated. A 3" double-diaphragm pump is mounted on a concrete pad with a header system that provides the following capabilities:

- unloading of SCCWS from the tanker into the storage tank or directly into the day tank;
- pumping of SCCWS from the storage tank into the day tank;
- pumping of SCCWS from the storage tank into the tanker;
- purging of any line or the tanker with water;
- recirculation of the SCCWS in the storage tank; and
- introduction of compressed air into the bottom of the storage tank to assist in breaking up any hardpack that might be formed.

A shelter was constructed over the pump and header system and electric heaters installed to protect them from the elements, primarily to guard against freezing. The system was tested by unloading several tanker-shipments of slurry into the storage tank and subsequently pumping the SCCWS into the day tank.

Slurry settling was experienced on two occasions during the equipment shakedown and preliminary testing period. The slurry was formulated to achieve $\geq 80\%$ penetration after 21 days of quiescent storage (based on a Pfizer technique to monitor slurry stability); however, because of long down periods due to ordering, installing, and repairing equipment, SCCWS stability problems were encountered. (Details of the coal supply and slurry formulation, production, and delivery have been discussed previously [9]). Solids settled in the storage tank on two occasions when the SCCWS was stored for more than 8 weeks, despite intermittent tank recirculation.

On one occasion during the fall of 1991, the hardpack was removed after the remaining slurry was fired in the boiler. The hardpack formed when the slurry was fired intermittently to shake down the system and generate preliminary data. Although settling occurred ($< 1'$ of settling in the tank with a diameter of 14' and a height of , the tank outlet was open and the slurry was removed using the double-diaphragm pump. The outlet is located on the side of the tank and is a 3" diameter opening $\sim 5.0'$ to the centerline from the bottom of the tank. The settled material was removed manually through a manhole on top of the tank and burned in the University's stoker-fired steam plant.

The second episode of settling occurred in January 1992 after the SCCWS was received in November 1991 for final equipment shakedown and boiler performance and emissions testing. Extensive delays combined with the production of slightly off-specification SCCWS resulted in settling. On this occasion a less manpower intensive approach was used to remove the slurry from the tank. Because the settled material blocked the tank outlet, it was necessary to remove it through the top of the tank. A centrifugal submersible pump, called a 'trash pump', was used to remove the majority of the slurry through the top of the tank, load it into tankers, and haul it to a permitted coal refuse facility. The trash pump was used until the remaining material became very viscous, at which point hot water ($\sim 210^\circ\text{F}$) from the deaerator tank was pumped into the storage tank. This allowed for the removal of most of the sediment from the bottom of the tank by the double-diaphragm pump. A layer of sediment remained on the bottom of the tank, opposite the outlet, which will be removed using hot water and a mixer. A mixer was ordered in November 1991 and delivered and installed in January 1992. The hot water/mixer combination will be used to remove the remaining sediment before receiving the next shipment of SCCWS, scheduled to arrive in March 1992.

Prior to the plugging of the tank outlet with hardpack, compressed air was used to keep the opening clear and the slurry agitated. The results were encouraging and an air sparge system is

being designed and will be installed in the bottom of the tank to allow periodic air bubbling to combat future settling.

5.0 ADVANCED SYSTEM TESTS

The program was expanded during the current reporting period. Upon the conclusion of the 1,000-hour demonstration, the system will be modified prior to conducting a second 1,000-hours of testing in which the effect of the ash in SCCWS on high temperature tube metal erosion/deposition (a superheater tube will be installed in one of the convective section cavities) will be investigated. In addition, a high-efficiency, low- NO_x burner will be installed, and an emissions control system will be added to a slipstream of the flue gas to investigate SO_2 and NO_x removal. The SCCWS for the second 1,000 hours of testing will be made from a mid-West or Western coal (to be identified in conjunction with DOE) at a slurry preparation facility to be constructed at Penn State. Construction of the slurry preparation facility is in an early engineering and design phase.

6.0 MISCELLANEOUS ACTIVITIES

Three papers and a poster presentation were prepared for the 17th International Conference on Coal and Slurry Technologies, Clearwater, Florida, April 28-May 1, 1992. Authors and titles are:

- Bruce G. Miller, and Alan W. Scaroni, "Penn State's Superclean Coal-Water Slurry Demonstration Program;"
- Peter M. Walsh, Jiangyang Xie, John T. Elston, Bruce G. Miller, and Alan W. Scaroni, "Erosion of a Tube by a High Velocity Jet in the Presence of Ash from Coal-Water Slurry Combustion;"
- Xie, Jiangyang, Peter M. Walsh, Alan W. Scaroni, and Bruce G. Miller, "Erosion of Metal at High Temperature In Oxidizing Atmosphere (poster presentation);" and
- Massood Ramezan, John Lagomarsino, Sarma V. Pisupati, Bruce G. Miller, and Alan W. Scaroni, "Performance Predictions of a Multifuel Industrial-Type Boiler."

7.0 NEXT SEMIANNUAL PERIOD ACTIVITIES

As previously mentioned, the final equipment components to be checked prior to demonstration testing are the SCCWS preheater, in-duct burner/FD damper system, and automatic control when firing SCCWS. This will be done in conjunction with optimizing atomization and combustion performance by systematically testing various nozzles, increasing the atomization air pressure, using high-pressure steam as the atomizing medium, increasing the SCCWS preheat temperature, and possibly replacing the existing burner assembly. The optimization work will be part of the first 1,000-hour demonstration and will begin in March 1992. This demonstration will also evaluate the deposition, corrosion, and erosion characteristics of the SCCWS. Laboratory-scale evaluations of deposition/corrosion will also continue.

Upon the conclusion of the 1,000-hour demonstration, the system will be modified prior to the second 1,000-hours of testing which will investigate the effect of the ash in SCCWS on high temperature tube metal erosion/deposition (a superheater tube will be installed in one of the convective section cavities). In addition, a high-efficiency, low-NO_x burner will be installed, and an emissions control system will be added to a slipstream of the flue gas to investigate SO₂ and NO_x removal.

8.0 REFERENCES

- [1] Kinneman, W.P., R.T. Wincek, B.G. Miller, A.W. Scaroni, and R.G. Jenkins, "Conversion of a 1000 lb/h Steam Boiler to Fire Coal Water Slurry Fuel," *Thirteenth Int. Conf. on Coal and Slurry Tech.*, Denver, Colorado, p.725 (April 12-15, 1988).
- [2] Miller, B.G., R.T. Wincek, A.W. Scaroni, W.P. Kinneman, and R.G. Jenkins, "Combustion of CWSF in a 1000 lb Steam/h Watertube Boiler," *Thirteenth Int. Conf. on Coal and Slurry Tech.*, Denver, Colorado, p. 119 (April 12-15, 1988).
- [3] Wincek, R.T., W.P. Kinneman, B.G. Miller, A.W. Scaroni, D. Shefet, and F. Kal, "Combustion Control System for a Coal-Water Slurry Fuel-Fired Boiler," *AIChE Spring National Meeting*, Houston, Texas (April 2-6, 1989).
- [4] Miller, B.G., J.L. Morrison, J.T. Elston, P.M. Walsh, H.H. Schobert, and A.W. Scaroni, "Superclean Coal-Water Slurry Combustion Testing in an Oil-Fired Boiler," Semiannual Technical Progress Report for the Period 08/15/1990 to 02/15/1991, Pittsburgh Energy Technology Center, Pittsburgh, Pennsylvania, May 15, 1991, DE-FC2289PC88697.
- [5] Miller, B.G., J.L. Morrison, J. Xie, P.M. Walsh, H.H. Schobert, and A.W. Scaroni, "Superclean Coal-Water Slurry Combustion Testing in an Oil-Fired Boiler," Semiannual Technical Progress Report for the Period 02/15/1991 to 08/15/1991, Pittsburgh Energy Technology Center, Pittsburgh, Pennsylvania, October 1, 1991, DE-FC2289PC88697.
- [6] Miller, B.G., and Alan W. Scaroni, "Superclean Coal-Water Slurry Combustion Testing in an Oil-Fired Boiler," *6th Annual Coal Preparation, Utilization, and Environmental Control Contractors Conference*, Pittsburgh, Pennsylvania, p. 81 (August 6-9, 1990).
- [7] Ramezan, M., J. Lagomarsino, S.V. Pisupati, B.G. Miller, and A.W. Scaroni, "Performance Predictions of a Multifuel Industrial-Type Boiler," *17th Int. Conf. on Coal and Slurry Tech.*, Clearwater, Florida, (April 28-May 1, 1992).
- [8] Miller, B.G., A.W. Scaroni, and J.T. Elston, "An Update of Penn State's Superclean Coal-Water Slurry Demonstration Program," *16th Int. Conf. on Coal and Slurry Tech.*, Clearwater, Florida, p. 587 (April 22-25, 1991).
- [9] Miller, B.G., J.L. Morrison, and A. W. Scaroni, "Superclean Coal-Water Slurry Combustion Testing in an Oil-Fired Boiler," *7th Annual Coal Prep., Util., and Environ. Control Contractors Conf.*, Pittsburgh, Pennsylvania, p. 10 (July 15-18, 1991).

- [10] Miller, B.G., P.M. Walsh, H.H. Schobert, and A.W. Scaroni, "Superclean Coal-Water Slurry Combustion Testing in an Oil-Fired Boiler," Semiannual Technical Progress Report for the Period 02/15/1990 to 08/15/1990, Pittsburgh Energy Technology Center, Pittsburgh, Pennsylvania, September 28, 1990, DE-FC2289PC88697.
- [11] G.Sundararajan, "The Solid Particle Erosion of Metallic Materials at Elevated Temperatures", Proceedings: Corrosion-Erosion-Wear of Materials at Elevated Temperatures, p. 11-1, (1991).
- [12] I. G. Wright, V. K. Sethi and V. Nagarajan, Transactions of the ASME, 113, 616 (1991).
- [13] A. V. Levy, Conf. , Corrosion-Erosion-Wear of Materials in Emergent Fossil Energy Systems, ed. A. V. Levy, p. 209, Berkeley, CA, NACE, (1983).
- [14] S. K. Hovis, J. E. Talia and R. O. Scattergood, Wear, 108, 139 (1986).
- [15] G. Sundararajan, Wear, 145, 251 (1991).
- [16] M. H. Davies, M. T. Simnad, and C. E. Birchenall, Journal of Metals, Transactions, AIME, 889 (1951).
- [17] J.H.Neilson and A.Gilchrist, Wear, 11, 111 (1968).
- [18] Engel, P.A., Impact Wear of Materials, Elsevier Scientific Publication Company, (1978).
- [19] Y. Shida and H. Fujikawa, Wear, 103, 281 (1985).
- [20] G. L. Sheldon, Journal of Basic Engineering, Trans. ASME, 92, 619 (1970).
- [21] A. G. Evans, M. E. Gulden, G. E. Eggun and M. Rosenblatt: Report, No.SC5023.9TR, Rockwell International Science Center, Thousand Oaks, CA, (1976).
- [22] V. K. Sethi and I. G. Wright, Corrosion and Particle Erosion at High Temperatures, ed. V. Srinivasan and K. Vedural, The Minerals, Metals and Materials Society, p. 245, (1989).
- [23] Peter M. Walsh, Jianyang Xie, John T. Elston, Bruce G. Miller, and Alan W. Scaroni, "Erosion of a Tube by a High Velocity Jet in the Presence of Ash from Coal-Water Slurry Combustion", *17th Int. Conf. on Coal and Slurry Tech.*, Clearwater, Florida, (April 28-May 1, 1992).

8.0 ACKNOWLEDGMENTS

The authors wish to acknowledge the following personnel for their contributions to the project during this reporting period:

- David Clark - Undergraduate Assistant
- Scott Britton - Research Technologist
- William P. Kinneman - Research Assistant
- Carl Martin - Laboratory Mechanic
- Sarma V. Pisupati - Research Associate
- Suneeta Shamanna - Graduate Research Assistant
- Ronald S. Wasco - Wage Payroll Assistant

- Ronald T. Wincek - Research Assistant

FIGURE 1. 1989 Milestone Schedule (First 1,000-h Demonstration)

FIGURE 2. 1990 Milestone Schedule (First 1,000-h Demonstration)

FIGURE 3. Phase I and II 1991 and 1992 Milestone Schedule (First 1,000-h Demonstration)

FIGURE 4. Phase III 1991 and 1992 Milestone Schedule (First 1,000-h Demonstration)

FIGURE 5. Phase IV Milestone Schedule

Figure 6. Penn State's SCCWS-Fired Boiler System

Figure 7. Comparison of Air Preheater Outlet Temperature as Predicted by the Model and Experimental Data during Gas Firing as a Function of Firing Rate

Figure 8. Comparison of Boiler Exit Gas Temperature as Predicted by the Model and Experimental Data during Gas Firing as a Function of Firing Rate

Figure 9. Comparison of Boiler Exit Gas Temperature as Predicted by the Model and Experimental Data during Cofiring CWS and Natural Gas as a Function of the Level of Gas Support

(A) Type 347

(B) Type 304

Figure 10. Metallographic characterization of the alloys, Mag 100x

(C) Alloy 800H

(D) Type 316

Figure 10 (Cont.). Metallographic characterization of the alloys, Mag 100x

(E) Type 321

Figure 10 (Cont.). Metallographic characterization of the alloys, Mag 200x

Figure 11. Photographs of the deposits on the coupons

Alloy 800H, 1000°C, 48 hrs

Type 304, 1000°C, 48 hrs

Figure 12. SEM photographs of the deposit morphology on the coupons

Type 316, 1000°C, 48 hrs

Type 321, 1000°C, 48 hrs

Figure 12 (Cont.). SEM photographs of the deposit morphology on the coupons

Type 347, 1000°C, 48 hrs

Figure 12 (Cont.). SEM photographs of the deposit morphology on the coupons

Figure 13. Weight Loss Data on Corrosion Coupons After Descaling Treatment

Figure 14. Photographs of descaled coupons

Type 316

Type 304

Figure 15. Photomicrographs of descaled coupons showing general corrosion
Mag 100x

Type 321

Alloy 800H

Figure 15 (Cont.). Photomicrographs of descaled coupons showing general corrosion
Mag 100x

Type 347

Figure 15 (Cont.). Photomicrographs of descaled coupons showing general corrosion
Mag 100x

Figure 16. Comparison of Model Calculation and Experimental Results

Figure 17. Erosion Rate as a Function of Particle Impact Angle

Figure 18. Erosion Rate as a Function of Metal Temperature

Figure 19. Erosion Rate as a Function of Particle Velocity

Figure 20. Erosion Rate as a Function of Particle Concentration

Figure 21. Erosion Rate as a Function of Particle Diameter

TABLE 1
MILESTONE DESCRIPTION (FIRST 1,000-h DEMONSTRATION)

<u>Phase I</u>	<u>Description</u>	<u>Planned Completion Date</u>	<u>Actual Completion Date</u>
Task 1, No. 1	Identify equipment and diagnostic instrumentation	09/15/89	09/15/89
Task 2, No. 1	Review present permit	09/15/89	09/15/89
Task 3, No. 1	Develop SCCWS specifications, identify operating procedures, prepare detailed test plan	10/15/89	
<u>Phase II</u>			
Task 1, No. 1	Building/boiler construction and installation let for bids	10/18/89	10/18/89
Task 1, No. 2	Building/boiler construction and installation awarded	12/31/89	03/23/90
Task 1, No. 3	Prepare site, install boiler and auxiliary equipment	04/01/91	
Task 2, No. 1	Identify coal for SCCWS preparation	09/30/90	09/30/90
Task 2, No. 2	Prepare SCCWS for demonstration	04/01/91	
Task 3, No. 1	Predict boiler performance	06/15/91	02/01/92
Task 4, No. 1	Shakedown boiler and auxiliary equipment	04/31/91	01/31/92
Task 4, No. 2	Generate baseline data on gas	05/31/91	09/30/91
<u>Phase III</u>			
Task 1, No. 1	Perform demonstration	03/01/92	
Subtask 1a, No. 1	300-hour demonstration milestone	07/31/91	
Subtask 1a, No. 2	600-hour demonstration milestone	09/30/91	
Subtask 1a, No. 3	1000-hour demonstration milestone	11/30/91	
Subtask 1a, No. 4	Redefine SCCWS specifications	01/15/92	
Subtask 1b, No. 1	Develop deposition and corrosion test plan	10/15/89	10/15/89
Subtask 1b, No. 2	Design suction pyrometer	06/01/90	08/01/90
Subtask 1b, No. 3	Construct suction pyrometer	10/01/90	10/01/90
Subtask 1b, No. 4	Deposition characterization equipment design and specification	01/01/91	02/15/91
Subtask 1b, No. 5	Acquisition of baseline data for spectroscopic analysis of deposits; acquisition of baseline data for corrosion of tubes by ash components	08/31/91	
Subtask 1b, No. 6	Accelerated corrosion testing; coupon testing in boiler	11/30/91	
Subtask 1b, No. 7	On-line deposition analysis	12/31/91	
Subtask 1b, No. 8	Complete deposition testing (auxiliary spectroscopic testing); complete corrosion modeling; complete deposition modeling	01/15/92	
Subtask 1c, No. 1	Develop erosion test plan	10/15/89	10/15/89
Subtask 1c, No. 2	Complete research boiler erosion evaluation	08/01/90	08/01/90
Subtask 1c, No. 3	Full-scale erosion technique decision	10/01/90	10/01/90
Subtask 1c, No. 4	Design probe for full-scale erosion study	01/01/91	02/15/91
Subtask 1c, No. 5	Construct erosion probe	05/01/91	10/15/91
Subtask 1c, No. 6	Complete erosion modeling	01/15/92	
Subtask 1d, No. 1	Identify viscometer	10/15/89	10/15/89
Subtask 1d, No. 2	Complete preliminary viscosity and stability tests	08/15/90	09/15/90
Subtask 1d, No. 3	Complete viscosity and stability tests	01/15/92	
Task 2, No. 1	Complete economic evaluation	01/15/92	
Task 3, No. 1	Complete project report	03/01/92	

TABLE 1 (Cont.)

<u>Phase IV</u>	<u>Description</u>	<u>Planned Completion Date</u>	<u>Actual Completion Date</u>
Task 1, No. 1	Procure and install burner and superheater	07/01/92	
Task 2, No. 1	Complete construction of SCCWS preparation facility	09/01/92	
Task 3, No. 1	Complete 500-h test	11/01/92	
Task 4, No. 1	Complete project report	03/01/93	
Task 5, No. 1	Install flue gas treatment system	08/01/93	
Task 6, No. 1	Complete 500-h test	10/01/93	
Task 7, No. 1	Complete final report	03/01/94	

Table 2. History of Raw Coal Shipment and Washed Coal Shipment.

Date Shipped	Perry Brothers Coal		Reddinger Coal		Yield ^a	Ash	Sulfur	Volatile Matter
	Date Shipped	Tonnage	Date Cleaned	Tonnage Shipped				
07/09/91		111.70	7/10/91	~ 62.0	55.5	--	--	--
10/01/91		273.72	10/3/91	142.05	51.9	3.8	--	--
10/23/91		93.34	10/25/91	47.15	50.5	3.4	0.7	34.7

^a Yield is calculated by: (tons of coal shipped by Reddinger Coal Company/tons of coal shipped by Perry Brothers Coal Company)x(100)

Table 3. Analysis of SCCWS Feedstock (10/23/91 Production Run)

Proximate Analysis, % wt (dry basis)

Volatile Matter	34.7
Fixed Carbon	61.9
Ash	3.4

Ultimate Analysis, % wt. (dry basis)

Carbon	78.5
Hydrogen	4.8
Nitrogen	1.5
Sulfur	0.7
Oxygen	11.1
Ash	3.4

Higher Heating Value, Btu/lb	13,844
------------------------------	--------

Table 4. KVS SCCWS Production Run for October 16, 1991

Time	Solids Loading (wt. %)	Particle Size Distribution		Viscosity (cp)	pH	Ball Mill Operating Conditions		
		-50 mesh	-200 mesh			Dry Coal	A-23M	4800C
0910 System start up								
1500	59.79	99.73	84.93	940	7.13	2215	1.02	0.046
1600	60.01	99.73	83.76	1000	7.00	2049	1.12	0.020
1700	60.85	99.69	85.62	880	6.95	2146	1.05	
1800	60.32	99.73	83.48	1080	6.88	2242	0.89	0.072
1900	59.23	99.65	82.70	820	6.72	2402	1.37	0.049
2000	59.02	99.64	82.95	752	6.69	2320	1.17	0.044
2100	58.80	99.73	87.18	720	6.59	2211	1.11	0.044
2200	58.84	99.69	85.60	768	6.65	2320	1.02	0.046
2300	58.89	99.71	83.80	692	6.57	2214	1.29	0.047
2400	58.72	99.84	86.49	700	6.58	2410	0.99	0.039

Comments: All of the data summarized above has been supplied by KVS.

- a) Solids loading were determined using a Harry W. Dietart Company moisture teller .
- b) Particle size distributions were determined by wet sieving.
- c) Viscosities were determined using a Brookfield "RVT" viscometer (spindle #5 at 100 rpm after 3 minutes)
- d) pH measurements using an Orion pH meter.
- e) Ball mill conditions

Dry coal feed rate expressed in lbs/hr

Dispersant (A-23M) and stabilizer (Flocon 4800 C) concentrations expressed as wt.% active solids/dry coal basis

Table 5. KVS SCCWS Production Run for October 17, 1991

Time	Solids Loading (wt. %)	Particle Size Distribution		Viscosity (cp)	pH	Ball Mill		
		-50 mesh	-200 mesh			Dry Coal	A-23M	4800C
0100	58.61	99.75	89.53	736	6.67	2382	0.84	0.040
0200	58.49	99.67	88.53	764	6.73	2466	0.94	0.042
0300	58.53	99.71	87.41	740	6.79	2326	0.97	0.045
0400	58.19	99.70	84.67	600	6.91	2233	1.10	0.043
0500	58.12	99.83	89.68	696	6.92	2261	1.06	0.039
0600	57.77	99.68	83.75	600	7.07	2206	1.04	0.045
0700	58.13	99.67	86.18	588	7.17	2316	1.00	0.040
0800						2316		
0900	59.83	99.67	83.83	740	7.09	2178	1.03	0.049

Comments: All of the data summarized above has been supplied by KVS.

a) Solids loading were determined using a Harry W. Dietart Company moisture teller .

b) Particle size distributions were determined by wet sieving.

c) Viscosities were determined using a Brookfield "RVT" viscometer (spindle #5 at 100 rpm after 3 minutes)

d) pH measurements using an Orion pH meter.

e) Ball mill conditions

Dry coal feed rate expressed in lbs/hr

Dispersant (A-23M) and stabilizer (Flocon 4800 C) concentrations expressed as wt. % active solids/dry coal basis

Table 6. KVS SCCWS Production Run for October 28, 1991

Time	Solids Loading (wt. %)	Particle Size Distribution		Viscosity (cp)	pH	Ball Mill		
						Dry Coal	Operating Conditions A-23M	4800C
1115 System start up								
1300	58.36	99.72	86.61	568	7.18	2281	1.43	0.052
1400	58.82	99.72	87.84	676	7.35	2463	1.18	0.041
1500	60.00	99.60	84.70	784	7.36	2292	0.95	0.037
1600	59.51	99.75	85.50	784	6.99	2213	1.08	0.034
1700	59.86	99.69	87.91	776	7.31	2310	0.94	0.043
1800	59.51	99.75	85.50	784	6.99	2102	1.04	0.048
1900	59.63	99.77	85.92	812	6.87	2144	1.05	0.052
2000	59.71	99.71	85.95	864	6.64	2213	0.88	0.046
2100	59.80	99.73	86.11	896	6.69	2213	0.49	0.044
2200	59.85	99.73	85.72	916	6.75	2240	1.26	0.043

Comments: All of the data summarized above has been supplied by KVS.

a) Solids loading were determined using a Harry W. Dietart Company moisture teller .

b) Particle size distributions were determined by wet sieving.

c) Viscosities were determined using a Brookfield "RVT" viscometer (spindle #5 at 100 rpm after 3 minutes)

d) pH measurements using an Orion pH meter.

e) Ball mill conditions

Dry coal feed rate expressed in lbs/hr

Dispersant (A-23M) and stabilizer (Flocon 4800 C) concentrations expressed as wt. % active solids/dry coal basis

Table 7. KVS SCCWS Production Run for November 25, 1991

Time	Solids Loading (wt. %)	Particle Size Distribution		Viscosity (cp)	pH	Ball Mill		
		-50 mesh	-200 mesh			Dry Coal	A-23M	4800C
0838	System start up							
1000	55.55	99.63	85.91	176	6.49	2268	1.07	0.072
1100	56.52	99.69	83.28	824	6.87	2296	0.91	0.038
1200	56.76	99.56	84.40	776	6.86	2144	1.17	0.086
1300	56.95	99.72	81.36	696	6.75	2199	0.99	0.063
1400	57.84	99.70	84.19	776	6.68	2337	1.25	0.061
1500	58.64	99.68	85.60	876	6.69	2287	1.10	0.062
1600	58.49	99.62	82.30	900	6.75	2393	0.99	0.060
1700	58.58	99.69	83.26	972	6.69	2268	1.34	0.061
1800	58.92	99.63	84.67	976	6.73	2216	1.18	0.064
1900	58.71	99.63	82.83	944	6.76	2230	1.26	0.059
2000	58.41	99.62	82.37	976	6.65	2216	0.88	0.069
2100	59.43	99.71	84.17	904	6.50	2369	0.92	0.054
2200	58.47	99.64	85.24	920	6.64	2374	0.92	0.056
2300	58.59	99.59	80.97	996	6.74	2276	1.01	0.067
2400	58.87	99.62	83.60	1052	6.72	2276	0.96	0.063

Comments: All of the data summarized above has been supplied by KVS.

a) Solids loading were determined using a Harry W. Dietart Company moisture teller .

b) Particle size distributions were determined by wet sieving.

c) Viscosities were determined using a Brookfield "RV" viscometer (spindle #5 at 100 rpm after 3 minutes)

d) pH measurements using an Orion pH meter.

e) Ball mill conditions

Dry coal feed rate expressed in lbs/hr

Dispersant (A-23M) and stabilizer (Flocon 4800 C) concentrations expressed as wt. % active solids/dry coal basis

Table 8. KVS SCCWS Production Run for November 26, 1991

Time	Solids Loading (wt. %)	Particle Size Distribution		Viscosity (cp)	pH	Ball Mill		
		-50 mesh	-200 mesh			Dry Coal	A-23M	4800C
0100	58.74	99.64	81.75	1044	6.80	2220	0.98	0.064
0200	58.44	99.49	83.29	1036	6.71	2357	1.05	0.065
0300	58.70	99.68	82.03	948	6.78	2343	0.93	0.057
0400	58.49	99.66	82.74	980	6.81	2426	0.94	0.055
0500	58.39	99.63	81.49	900	6.79	2399	0.95	0.047
0600	59.09	99.73	81.03	868	6.97	2382	0.91	0.045
0700	59.13	99.69	82.40	984	7.02	2270	1.11	0.056
0800	59.70	99.58	81.09	764	7.03	2340	0.84	0.033
0900	59.73	99.63	83.25	836	6.98	2396	1.00	0.060
1000	59.43	99.67	83.95	948	6.97	2331	1.04	0.059
1100	59.12	99.72	83.36	788	6.95	2473	1.06	0.049
1200	58.70	99.67	79.53	764	6.86	2247	1.17	0.057
1300	57.99	99.64	81.68	648	6.89	2289	1.05	0.060
1400	57.20	99.56	80.14	720	6.99	2104	1.19	0.080
1500	56.44	99.72	84.14	580	7.01	2244	1.02	0.059

Comments: All of the data summarized above has been supplied by KVS.

a) Solids loading were determined using a Harry W. Dietart Company moisture teller .

b) Particle size distributions were determined by wet sieving.

c) Viscosities were determined using a Brookfield "RVT" viscometer (spindle #5 at 100 rpm after 3 minutes)

d) pH measurements using an Orion pH meter.

e) Ball mill conditions

Dry coal feed rate expressed in lbs/hr

Dispersant (A-23M) and stabilizer (Flocon 4800 C) concentrations expressed as wt.% active solids/dry coal basis

Table 9. SCCWS Delivery History

Date	Tanker ID	Approximate Weight (lbs)
10/16/91	D-608	35,588
10/17/91	D-607	42,972
10/28/91	SN 2472	42,719
11/25/91	D-607	39,203
11/26/91	D-608	39,471
11/26/91	SN 2472	39,400

Table 10. Summary of Natural Gas-Fired Testing

Test Date	September 1991					January 1992
Firing Rate (MM Btu/h)	6.0	9.6	12.0	16.4	16.9	18.5
Air Preheater Temperatures (°F)						
Comb. Air Inlet	146	93	93	93	97	87
Comb. Air Outlet	332	327	335	348	352	347
Flue Gas Inlet	445	484	507	541	548	567
Flue Gas Outlet	277	281	301	331	339	342
Steam Flow (lb/h)	N.M. ^a	N.M.	N.M.	N.M.	N.M.	14,700
Boiler Efficiency (%)	N.D. ^b	N.D.	N.D.	N.D.	N.D.	82.4
Flue Gas Composition (dry basis)						
O ₂ (%)	7.5	5.2	4.6	4.1	4.2	1.4
CO (ppm)	86	95	98	100	100	124
CO ₂ (%)	8.4	9.6	9.9	10.2	10.1	11.4

^aNot Measured^bNot Determined

Table 11. SCCWS Analysis

<u>Proximate Analysis, wt. % (dry basis)</u>		<u>Ultimate Analysis, wt. % (dry basis)</u>	
Volatile Matter	35.2	Carbon	80.3
Fixed Carbon	60.5	Hydrogen	5.3
Ash	4.3	Nitrogen	1.7
		Sulfur	0.9
		Oxygen	7.5
		Ash	4.3

Higher Heating Value, Btu/lb (dry basis)	14,263
--	--------

Solids Loading:	58.5 wt. %
-----------------	------------

Particle Size:	
D (v, 0.5) ^a	20-25 μm
-74 μm	80-85 wt. %

Viscosity (Bohlin Viscometer):	
@ 50/sec	675 cp
@ 100/sec	625 cp

Additives:	
Dispersant (A-23M), 1.0 wt.% active solids (dry coal basis)	
Stabilizer (Flocon 4800 C), 0.04 wt.% active solids (dry coal basis)	

^aParticle size where 50% of the particles, by volume, are less than the indicated particle size.

Table 12. Summary of SCCWS-Fired Testing

Test Date	October 1991	January 1992
Length of SCCWS Firing (hours)		
Total	66.5	26
Steady-state/performance verification test ^a	35	10
Firing Rate (MM Btu/h)		
Natural Gas	4.4	5.6
SCCWS	14.2	11.7
Total	18.6	17.2
Gas Support (%)	23.7	32.6
Air Preheater Temperatures (°F)		
Combustion Air Inlet	73	82
Combustion Air Outlet	342	348
Flue Gas Inlet	536	533
Flue Gas Outlet	319	326
Combustion Air Temperature (°F) ^b	330	467
Steam Flow (lb/h)	11,162	11,300
Boiler Efficiency (%)	71.7	71.3
Carbon Conversion (%) ^c	~82	78
Atomizing Air Pressure (psig)	92	104
SCCWS Temperature (°F)	78	66
Baghouse		
Pressure Drop (inches water column)	1.05	1.24
Inlet Temperature (°F)	313	324
Outlet Temperature (°F)	269	295
Collection Efficiency (%)	N.M. ^d	99.68
Flue Gas Composition (dry basis)		
O ₂ (%)	2.8	2.2
CO (ppm)	285	333
CO ₂ (%)	14.5	14.5
SO ₂ (ppm)	452	446
NO _x (ppm)	336	390

^aOctober tests consisted of 35 hours of steady-state operation; January test consisted of 10 hours of performance testing

^bMeasured at windbox, after in-duct auxiliary gas burner; in-duct burner was not operational during October 1991 testing

^cCarbon conversion of SCCWS; 100% combustion efficiency assumed with natural gas

^dNot Measured

Table 13. Particle Size Distribution (μm) of Fly Ash Samples Collected During January Testing^a

Time Sampled	D (v, 0.9)	D (v, 0.5)	D (v, 0.1)	Top Size	Percent in Top Size Band
11:30	258.7	85.0	24.5	>564.0	0.4
12:00	146.4	79.6	23.2	291.0	----
13:00	288.2	87.9	26.2	>564.0	0.6
14:00	245.5	169.9	43.6	>564.0	0.5
15:00	178.7	87.9	27.3	291.0	----
16:00	220.4	96.0	26.3	>564.0	0.3
17:00	233.8	104.4	31.0	>564.0	0.5
18:00	313.1	188.4	45.5	>564.0	1.0
19:00	367.8	183.4	50.6	>564.0	1.5

^aParticle sizes were measured using a Malvern 2600C Droplet and Particle Analyzer using the 300 mm lens. D (v, 0.9), D (v, 0.5), D (v, 0.1), are the particles sizes where, respectively, 90%, 50%, and 10% of the particles are less than the indicated particle size. Percent in top size band gives an indication of the quantity of fly ash >564.0 μm .

Table 14. Spectrochemical Analysis of the Ash Used in the Bench-Scale Testing

Component	Wt. %
SiO ₂	15.65
Al ₂ O ₃	9.19
Fe ₂ O ₃	4.94
TiO ₂	0.40
MgO	0.40
CaO	7.52
P ₂ O ₅	<0.28
Na ₂ O	0.23
K ₂ O	0.59
SO ₃	3.29

Table 15. Weight Loss Data on Corrosion Coupons After Descaling Treatment

Grade	Weight Before Treatment (g)	Weight After Treatment (g)	Weight Loss (g)
304	55.4183	55.3173	0.1010
347	53.9268	53.7355	0.1913
800H	53.8571	52.1262	1.7309
316	53.3428	52.4099	0.9329
321	51.5958	49.9083	1.6875

END

**DATE
FILMED**

9 / 1 / 92