DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

**A NOVEL CARBON-BASED PROCESS
FOR FLUE GAS CLEANUP**

DOE/PC/91345---T6

DE92 040656

**Fourth Quarterly Technical Progress Report
April 1 to June 30, 1992**

**Contract No. DE-AC21-91PC91345
Ms. Diane Revay Madden: DOE COR**

Submitted to:

**U.S. Department of Energy
Pittsburgh Energy Technology Center
P.O. Box 10940, Pittsburgh, PA 15236**

**S.K. Gangwal, Project Manager
Research Triangle Institute
Research Triangle Park, NC 27709
(919) 541-8033**

**P.L. Silveston, Co-Principal Investigator
University of Waterloo
Waterloo, Ontario, Canada N2L3G1
(519) 885-1211, Ext. 2534**

July 1992

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

TABLE OF CONTENTS

Section		Page
	List of Tables and Figures	ii
	Abstract	iii
1.0	INTRODUCTION	1
1.1	Objective	1
1.2	Process Description	1
1.3	Background	1
1.4	Project Scope/Schedule	4
1.5	Measures of Success	6
2.0	WORK COMPLETED IN PREVIOUS QUARTERS	7
3.0	WORK COMPLETED IN PRESENT QUARTER	8
3.1	Accomplishments	8
3.2	SO ₂ Removal	8
3.2.1	SO ₂ Removal Experiments at 21 °C	8
3.2.2	SO ₂ Removal Experiments at Higher Temperatures	8
3.3	NO _x Removal	9
3.4	Process Economic Evaluation	12
4.0	WORK PLANNED FOR NEXT QUARTER	13
4.1	SO ₂ Removal	13
4.2	NO _x Removal	13
4.3	Publications	13
5.0	REFERENCES	14
6.0	APPENDIX	15

LIST OF TABLES

Table 1	Advantages of Process	2
Table 2	SO ₂ Removal Test Results (37.22 g of MCCI, 80 °C, 1,475 scc/(cc·h) Flue Gas Containing 2,550 ppm SO ₂ , 450 ppm NO, 10% CO ₂ , 10% H ₂ O, 5% O ₂ , and Balance N ₂)	10
Table 3	Modified Carbon Catalyst II (MCCII) NO _x Removal Performance	11
Table 4	Modified Carbon Catalyst III (MCCIII) NO _x Removal Performance	11
Table 5	Cost of SO ₂ /NO _x Removal (Mid 1991 \$)	12

LIST OF FIGURES

Figure 1	Flue gas cleanup process concept	1
Figure 2	Multistage activated carbon scrubbing process with pulsed liquid flow and cooling of the feed gas and reheating of the off-gas by heat recovery	3

ABSTRACT

The objective of this project is to demonstrate the preliminary technical and economic feasibility of a novel carbon-based process for removal of at least 95% SO_2 and at least 75% NO_x from coal combustion flue gas. In the process, flue gas leaving the electrostatic precipitator (ESP) is passed through a trickle bed of activated carbon catalyst employing a periodic flush of low strength sulfuric acid. The SO_2 is oxidized to SO_3 and removed as medium strength sulfuric acid. The SO_2 -free flue gas is then mixed with NH_3 , and the NO_x in the gas is subjected to selective catalytic reduction (SCR) to N_2 over a fixed bed of activated carbon catalyst.

The project is being carried out over 14 months (June 4, 1991, to July 31, 1992). The experimental work is divided between Research Triangle Institute (RTI) and the University of Waterloo (Waterloo). RTI will conduct the NO_x removal studies, whereas Waterloo will conduct the SO_2 removal studies. The ultimate goal of the project is to demonstrate that the process can reduce the cost of electricity by 20% over conventional SCR/flue gas desulfurization (FGD) processes.

In the previous three quarters, a detailed project management plan was prepared describing the experimental setup, work plan, and test plan. The experimental system was completed for SO_2 conversion at Waterloo and for NO_x conversion at RTI. Shakedown experiments were completed. Scoping studies at Waterloo with the BPL carbon showed that periodic flushing could only achieve up to 40% SO_2 removal with one bed. The SO_2 removal factorial experiments were begun at Waterloo with the BPL carbon at 21 °C. SO_2 removal was also tested at RTI on two catalysts at 80 °C. It was shown that the BPL carbon could remove over 95% SO_2 at 21 °C but would require several beds at a space velocity in each bed of about 1500 scc/(cc·h) to reduce SO_2 from 2,500 ppm to 100 ppm. A modified carbon catalyst (MCCI) tested at RTI showed 99% SO_2 removal at 80 °C and 1,400 scc/(cc·h). The modified carbon catalyst also demonstrated removal of more than 80% NO_x at around 140 °C and 1,400 scc/(cc·h).

In the present quarter, the NO_x removal performance of two additional modified carbon catalysts (MCCII and MCCIII) was studied. MCCII showed NO_x removal efficiency which was similar to that observed for MCCI. However, MCCIII was considerably less active for NO_x removal. SO_2 removal experiments with NO present in the feed gas were performed with MCCI. SO_2 removal efficiency was consistently about 98% over each of 10 cycles and was very similar to that observed earlier with no NO present in the feed. Finally, a preliminary economic evaluation of the process was performed and a project review meeting was held. The economic evaluation showed that the RTI-Waterloo process was competitive with SCR/FGD and other combined SO_2/NO_x removal processes.

Work in the next quarter will include further tests of MCCI for SO_2 removal with NO in the feed gas at higher reactor temperature. Also, the effect of nominally 100 ppm SO_2 in the feed gas on NO removal efficiency for MCCI will be studied. A paper will be presented at the AIChE meeting in Minneapolis and the Contractor's Review Meeting in Pittsburgh.

1.0 INTRODUCTION

1.1 OBJECTIVE

The objective of this project is to demonstrate the preliminary technical and economic feasibility of a novel carbon-based process for removal of at least 95% SO_2 and at least 75% NO_x from coal combustion flue gas. The process is based on the demonstrated ability of activated carbons to catalyze SO_2 oxidation and NO_x reduction below 150 °C.

1.2 PROCESS DESCRIPTION

The process concept is shown in Figure 1. The hot flue gas leaves the electrostatic precipitator (ESP) at ~150°C and enters a recuperative gas-gas heat exchanger, employing a bed of ceramic balls, to cool the flue gas for SO_2 removal and simultaneously heat the cold flue gas for NO_x removal. The gas leaving the exchanger enters a series of two to three activated carbon trickle-bed catalytic reactors at approximately 100 °C to remove the SO_2 and convert it to medium strength sulfuric acid. The essentially SO_2 -free gas from the last trickle bed goes through the exchanger to the NO_x converter. The required amount of NH_3 , (typically in an NO_x/NH_3 mol ratio of 1) is mixed with the flue gas prior to the activated carbon catalyst bed. The advantages of the proposed process concept compared to currently available SO_2/NO_x processes are summarized in Table 1.

Figure 1. Flue gas cleanup process concept.

Table 1. Advantages of Process

SO₂ Removal

● Easier retrofit	- Downstream of ESP where space is more readily available
● No waste product	- Sulfuric acid is potentially marketable
● Low temperature	- Reduced equipment stress, nonenergy intensive, no hazards including carbon combustion
● Simple regeneration	- No carbon loss
● Periodic operation	- Low pressure drop, concentrated sulfuric acid

NO_x Removal

● High catalyst life	- Low temperature operation in the absence of SO ₂ and particles significantly increases catalyst life
● Low salt/SO ₃ formation	- Due to complete SO _x removal upstream, the acid dew point of the gas is very low and salt formation is avoided
-

1.3 BACKGROUND

The SO₂ removal process proposed herein is based on the well-known low-temperature catalytic properties of activated carbon, but uses a novel periodically flushed Table 5 trickle bed to produce a strong acid and a low level of SO₂ in the gas discharge. Hartman et al. (1971) and Hartman and Coughlin (1972) provide a detailed description of the mechanism of SO₂ oxidation [$\text{SO}_2 + (1/2)\text{O}_2 \rightarrow \text{SO}_3$ or $\text{SO}_2 + (1/2)\text{O}_2 + \text{H}_2\text{O} \rightarrow \text{H}_2\text{SO}_4$] over activated carbon. The SO₃ formed does not desorb spontaneously at low temperature. It is desorbed with water as sulfuric acid. Sulfuric acid, however, suppresses the ionization of dissolved sulfur dioxide and solubility of oxygen so that countercurrent contacting must be used to continue the reaction at an appreciable rate. Acid formation is accomplished in our process by periodic flushing, which results in a lower pressure drop and more concentrated sulfuric acid than achievable by continuous flushing.

Work in the co-principal investigator's laboratory at the University of Waterloo (Waterloo) (Haure et al., 1989) has shown the feasibility of the process. With a single bed and periodic water flushing (0.9 min water flow in every 90-min cycle), a time averaged acid concentration of nearly 0.2 molar was achieved. Based on this result, a conceptual process employing acid recycle to produce medium strength sulfuric acid is shown in Figure 2. SO_2 is absorbed from the gas phase and converted into sulfuric acid by two to three in-line periodically liquid-pulsed beds of carbon. Typically water, dilute strength acid or medium strength acid flows through them for 2 to 4 min in every 30- to 40-min cycle. The gas phase flows through the beds continuously. Co-current flow is employed so that high superficial velocities can be used without flooding. Two to three in-line, co-current trickle beds of sufficient depth should provide complete removal of SO_2 . The recycling arrangement passes the strongest acid through the bed, treating the richest gas, and thereby produces medium strength acid as a product. The gas-gas heat exchanger brings the flue gas leaving the third bed to the desired temperature for catalytic NO_x removal, which is the second part of our process, as shown previously in Figure 1.

Figure 2. Multistage activated carbon scrubbing process with pulsed liquid flow and cooling of the feed gas and reheating of the off-gas by heat recovery.

NO_x is reduced in a separate reactor at 120 °C using NH_3 after the SO_2 has been removed, and the N_2 and H_2O are vented to the stack. One possible reaction is $4\text{NH}_3 + 4\text{NO} + \text{O}_2 \rightarrow 4\text{N}_2 + 6\text{H}_2\text{O}$, although many others are possible. Many catalysts for the NH_3 - NO reaction are reported in the literature (commercially practiced in selective catalytic reduction (SCR) technology using vanadium-based catalysts). However, many of these catalysts are inactive at 120 °C. A comprehensive unpublished review of the literature by the principal investigators indicated that activated carbon or "coke" catalysts are the only catalysts with the potential to carry out the reaction at 120 °C. Such catalysts are commercially used in the Mitsui process, which claims some 85% NO_x removal at 130 °C. A number of studies (Kusakabe et al., 1988; Kuehl et al., 1986; Seki et al., 1975; U.S. Patent 4,194,373; Kareko et al., 1988) corroborate that activated carbons are active low temperature catalysts for the NO - NH_3 - O_2 and NO - NH_3 reactions. These studies further suggest that activated carbons promoted with very small quantities of group VIII transition metals (particularly platinum) should be considered.

1.4 PROJECT SCOPE/SCHEDULE

The novel carbon-based process to be studied has the potential to provide a technically sound and economically attractive solution to flue gas cleanup. The SO_2 removal experiments will be carried out in the apparatus of Haure et al. (1989) at Waterloo, modified to handle dilute to medium strength sulfuric acid and temperatures up to 100 °C. The questions to be addressed in the research include:

- What acid concentrations are attainable by periodic pulsing and acid recycle?
- What is the pressure drop as a function of time during a cycle of no liquid flow to liquid flow?
- What is the optimum size of the granular activated carbon?
- What is the optimum pulse length to prevent poisoning (as occurring in steady-state operation) of the activated carbon?
- What is the optimal temperature of operation?
- What will be the effect and fate of NO_x ?

The experimental parameters investigated will include carbon type, size, bed depth, gas composition, liquid composition, gas velocity, liquid velocity, cycle time, flush time and gas temperature. To reduce the number of variables, the carbon used will be the BPL carbon (Calgon Corporation) which was found to be the most active in the previous study. Because the experiments are expected to be short, a large number of parametric experiments will be carried out to prove feasibility and obtain data to permit a process evaluation.

The NO_x removal experiments will be carried out at Research Triangle Institute (RTI). The experiments will be geared toward demonstrating > 75 % NO_x removal from off-gases expected from the activated carbon SO₂ conversion process. The principle variables considered will include carbon type (BPL carbon, 0.1 to 1 % Pt on carbon, and three others), temperature (100 to 150 °C), and space velocity [5,000 to 20,000 scf/(cf·h)]. A proper N₂ balance will be carried out in each experiment and slip of NH₃ and NO/NO_x in the reaction products will be measured. The effect of traces of SO₂ up to 250 ppmv on NO_x conversion will be examined.

Based on the experimental data, technical and economic evaluation of the process for 1 MW and 100 MW plants will be carried out. The technical evaluation shall determine the degree of SO₂ and NO_x removal that may be achieved in full-scale plants using the data collected in the controlled laboratory experiments. Economic evaluation will determine the cost of our process on unit power generation basis. The predicted cost will be compared with the cost of the conventional limestone fluid gas desulfurization (FGD)/SCR system. If cost is at least 20% less for our process, our process will be considered for scaleup in future investigations.

The work to be carried out is divided into the following tasks:

<u>Task</u>	<u>Schedule</u>
Task 1: Program Definition (RTI and Waterloo)	June 4, 1991, to July 31, 1991
Task 2: Experimental	August 1, 1991, to February 28, 1993
2.1: SO ₂ Removal (Waterloo)	
2.2: NO _x Removal (RTI)	
Task 3: Process Evaluation (RTI)	May 1, 1992, to April 30, 1993

Task 1 (Program Definition) entails preparation of a detailed Project Management Plan describing a detailed work plan for the entire project and detailed test plans describing the experimental work. In Task 2 (Experimental), facilities will be constructed and experiments will be carried out per the approved Project Management Plan. SO₂ removal experiments will be carried out at Waterloo under the supervision of Dr. P.L. Silveston. NO_x removal experiments will be carried out at RTI under the supervision of Dr. S.K. Gangwal. In Task 3 (Process Evaluation), technical and economic evaluation of the process for 1 MW and 100 MW plants will be carried out by RTI.

It will be important to maintain a high degree of communication between Waterloo and RTI to ensure success of the project. The communication will be maintained by weekly conference calls. Also, an RTI investigator will travel to Waterloo at least twice during the

project to review their experimental progress. Similarly, a Waterloo investigator will travel to RTI at least twice during the project.

1.5 MEASURES OF SUCCESS

The targets that we hope to achieve during the course of our experiments are:

- 95% or greater removal of SO_2 ,
- Production of at least 2 molar sulfuric acid,
- Pressure drop of at most 30 in. in the SO_2 removal process,
- 75% or greater removal of NO_x , and
- 25 ppmv or less NH_3 slip.

The experimental data would also indicate how to achieve further improvements in the above targets. The project is designed to prove the technical and economic feasibility of the process and provide sufficient data to permit a preliminary process evaluation. The ultimate test of the success of the project will be whether the process can reduce the cost of electricity over conventional FGD/SCR processes by 20%.

2.0 WORK COMPLETED IN PREVIOUS QUARTERS

The accomplishments in the previous quarters were as follows:

- A paper was published and presented at the Seventh Annual Coal Preparation, Utilization, and Environmental Control Contractors' Conference sponsored by the U.S. Department of Energy/Pittsburgh Energy Technology Center (DOE/PETC);
- Task 1 was completed. A detailed Project Management Plan was prepared describing the work plan, experimental apparatus, experimental test plan/sequence, milestone schedule, cost plan, key personnel plan, project management structure, and measures of success;
- Task 2 was begun. The assembly of experimental apparatus and shakedown tests at Waterloo and RTI were completed with the exception of the installation of a continuous SO₂ analyzer.
- Sufficient catalysts were procured for the SO₂ removal experiments at Waterloo and for the NO_x removal experiments at RTI.
- A number of catalyst screening tests were completed for SO₂ and NO_x conversion. It was shown that 75% NO_x conversion was possible on selected carbon catalysts.
- A continuous SO₂ analyzer system was commissioned at Waterloo and SO₂ removal factorial experiments with BPL carbon at 21 °C began.
- SO₂ removal was also tested at RTI on a modified carbon catalyst and a CarboTech carbon at a higher temperature (80 °C).
- NO_x removal was tested at RTI on a number of carbon-based catalysts.
- The modified carbon catalyst tested at RTI consistently removed 99% SO₂ over multiple cycles at 80 °C and 1,400 scc/(cc · h).
- The modified carbon catalyst also demonstrated removal of more than 80% NO_x at about 140 °C and 1,400 scc/(cc · h).

3.0 WORK COMPLETED IN PRESENT QUARTER

3.1 ACCOMPLISHMENTS

The accomplishments in the present quarter are as follows:

- The NO_x removal performance of two additional modified carbon catalysts (MCCII and MCIII) was studied.
- Modified carbon catalyst II (MCCII) which had been exposed to nitric oxide and ammonia was tested for SO₂ removal.
- Modified carbon catalyst I (MCCI) was tested over 10 cycles for SO₂ removal at 80 °C while also being exposed to a nominal 500 ppm of nitric oxide.
- A preliminary economic evaluation of the process was prepared.

3.2 SO₂ REMOVAL

3.2.1 SO₂ Removal Experiments at 21°C

See Appendix 1.

3.2.2 SO₂ Removal Experiments at Higher Temperatures

A modified carbon catalyst (MCCII) which had previously been exposed to nitric oxide and ammonia was tested for SO₂ removal. Before the first cycle, the bed was flushed with distilled water. At a space velocity of 1454 scc/(cc·h) and a temperature of 80 °C, the reactor was left on-line for 1.63 hours before 5% breakthrough of the 2505 ppm SO₂ feed concentration was observed.

After flushing the reactor with 200cc of 4.32 N sulfuric acid, it was placed back on-line at 80 °C. The highest conversion observed during a 2 hour period was 76%.

After flushing the reactor again with 4.32 N sulfuric acid, it was placed on-line and heated to 105 °C. The highest conversion observed was 63.9%.

These test results showed that MCCII does not maintain a high SO₂ conversion over several cycles compared with MCCI, which demonstrated over 97% SO₂ removal over 10-cycles of exposure and flushing (see Third Quarterly Technical Progress Report).

SO₂ removal tests of MCCI were performed in which the feed gas contained nominally 2,500 ppm SO₂, 500 ppm NO, 10% CO₂, 5% O₂, and 10% steam. These tests

were performed to determine the effect of nitric oxide on SO_2 removal, using a proven catalyst for SO_2 removal. The results for 10-cycles of exposure and flushing are given in Table 2.

These results show consistent SO_2 removal and capacity and no decay in catalyst performance. Also, about the same breakthrough time was measured as in earlier tests of the same catalyst without nitric oxide present. There was one difference observed in the performance of MCCI under these test conditions. In previous tests, with no NO in the feed, the SO_2 conversion reached greater than 95% within a few minutes after the reactor was placed on-line and remained high until beginning breakthrough. With NO present in the feed, the conversion initially was greater than 95%, but would decrease to about 40% and then return to greater than 95% over a 1 - 2 hour period, before beginning to breakthrough. The cause of this behavior (believed primarily to be a drop in downstream temperature due to evaporation) will be investigated in future experiments. A different vendor batch of the same catalyst was used and may have caused this. It is believed that operations at around 130 °C will solve this problem. Operation at this higher temperature will also eliminate the heat exchanger and reduce capital cost.

It should be noted that no acid strength data is given for the flushing liquid in Table 2. This is because the previous method of measuring sulfuric acid concentration by determining the solution density is not reliable when nitric acid could also be present in the flushing liquid. An alternate technique for determining sulfuric acid concentration will be investigated.

3.3 NO_x REMOVAL

The NO_x removal performance of a modified carbon catalyst (MCCII) was studied as a function of space velocity, temperature, and NH_3/NO mole ratio. The results are shown in Table 3.

NO conversions were above 75% for all the conditions studied. At the lower space velocity, NH_3 slip was very low. When space velocity was increased by nearly a factor of 2.5, NH_3 slip increased but conversion did not drop. This indicates that both $\text{NH}_3\text{-NO}$ reaction to N_2 and $\text{NH}_3\text{-O}_2$ reaction to N_2 takes place, and the latter reaction is slower. Thus unreacted NH_3 remains at higher space velocity. NH_3 slip also increased when temperature was reduced from 135 °C to 130 °C at 1717 scc/(cc·h) space velocity. Thus the $\text{NH}_3\text{-O}_2$ reaction also appears to be temperature sensitive.

The NO_x removal performance of a third modified carbon catalyst (MCCIII) was also tested. The results are shown in Table 4.

At the higher space velocity, a temperature of 158 °C was needed to achieve greater than 75% conversion of NO . At the lower space velocity, a temperature of 155 °C was needed for greater than 75% NO conversion. The activity of this catalyst was somewhat poorer than that observed for either MCCI or MCCII. However, all three catalysts are excellent candidates for low temperature NO_x removal.

Table 2. SO₂ removal test results (37.22 g of MCCI, 80 °C, 1,475 sec/(cc·h)
Flue gas containing 2,550 ppm SO₂, 450 ppm NO, 10% CO₂, 10% H₂O, 5% O₂,
and balance N₂)

Cycle	Breakthrough time (h) ^a	Percent SO ₂ Removal	SO ₂ Converted, (g) ^b	Breakthrough Extent (%)	Cold Flushing Liquid (200 cc)
1	0.6	99.7	1.39	5	4.32 N H ₂ SO ₄
2	8.95	99.4	20.62	5	4.32 N H ₂ SO ₄
3	3.22	97.4	7.27	5	4.32 N H ₂ SO ₄
4	3.42	97.7	7.74	5	4.32 N H ₂ SO ₄
5	2.83	93.9	5.93	5	4.32 N H ₂ SO ₄
6	2.92	97.1	6.35	5	4.32 N H ₂ SO ₄
7	3.17	97.8	7.03	5	4.32 N H ₂ SO ₄
8	3.30	98.6	7.21	5	4.32 N H ₂ SO ₄
9	3.33	98.1	7.24	5	4.32 N H ₂ SO ₄
10	3.25	98.3	7.24	5	4.32 N H ₂ SO ₄

^a 5% breakthrough

^b Per 100 g carbon at 5% breakthrough.

^c At liquid flush.

Table 3. Modified Carbon Catalyst II (MCCII) NO_x Removal Performance

Temp., (°C)	Space Velocity scc/hr·cc	Inlet NH ₃ /NO	NO Conversion, (%)	NH ₃ Slip (ppm)
140	1412	1.36	85.9	0.2
150	1414	1.36	87.9	0.2
130	1408	1.26	77.8	4.0
135	1408	1.26	81.5	0.8
135	1717	1.41	88.0	6.2
130	1717	1.41	83.0	121
140	3354	1.42	92.9	77.6
135	3354	1.42	87.9	220

Table 4. Modified Carbon Catalyst III (MCCIII) NO_x Removal Performance

Temp., °C	Space Velocity scc/hr·cc	Inlet NH ₃ /NO	NO Conversion, Percent	NH ₃ Slip, ppm
140	3301	1.17	46.9	NA
140	3342	1.33	46.9	NA
140	3367	1.43	46.9	NA
150	3367	1.43	71.4	NA
158	3367	1.43	89.8	NA
140	1683	1.09	35.6	NA
140	1720	1.35	35.6	NA
150	1720	1.35	71.1	NA
160	1720	1.35	90.4	NA
155	1720	1.35	84.6	42.5

3.4 Process Economic Evaluation

Based on the results to date, a preliminary evaluation of the RTI-Waterloo process was conducted for a 100 MW electric power plant burning a 2.8% sulfur coal. The Electric Power Research Institute (EPRI) technical assessment guide was used for the calculations. The economic results obtained for the RTI-Waterloo process are compared in Table 5 to those of several processes based on data obtained from a recent EPRI-sponsored study. The comparison in Table 5 shows that the RTI-Waterloo process is competitive with several combined SO₂/NO_x removal processes.

Table 5. Cost of SO₂/NO_x Removal (Mid 1991 \$)

Process	Capital cost (\$/kW)	Levelized cost (Mills/kWh)
Conventional FGD/SCR	200	8.8
Advanced FGD/SCR	170	7.8
NOXSO	215-300	8-17
SNO _x	330-430	8.8-13
E-beam	310-440	9-15
RTI-Waterloo	162-179	6.8-8.2

Estimates except for RTI/Waterloo process from Cichanowicz et al., 1991.

4.0 WORK PLANNED FOR NEXT QUARTER

4.1 SO₂ Removal

Further tests will be performed with MCCI at 130 °C to assess whether the long time delay in reaching 95% SO₂ removal, observed at 80 °C, can be eliminated. Effect of flushing with higher acid concentrations up to 15% normal at these higher temperatures will be investigated.

4.2 NO_x Removal

The effect of nominally 100 ppm SO₂ in the feed gas on NO_x conversion on the MCCI catalyst will be tested at various conditions of temperature and space velocity.

4.3 Publications

Papers will be presented at the Contractor's Review Meeting and the Minneapolis AIChE Meeting.

5.0 REFERENCES

- Hartman, M., and R.W. Coughlin. 1972. *Chem. Eng. Sci.* 127:867-880.
- Harman, M., J. Polek, and R.W. Coughlin. 1971. *Chem. Eng. Prog. Symp. Ser.*, No. 115, 67:7-22.
- Haure, P., R.R. Hudgins, and P.L. Silveston. 1989. *AIChE Journal*, 35:1437.
- Kareko, K., Y. Nakahigashi, and K. Nagata. 1988. *Carbon*, 26(3):327-333.
- Keuhl, H., E. Richter, K. Knoblauch, and H. Juentgn. 1986. *Carbon '86, Bergan-Forschung*, Essen, Germany, pp. 351-353.
- Kusakube, K., M. Karhima, S. Morook, and K. Shigeharu. 1988. *Fuel*, 67(5):714-718.
- Seki, M., Y. Sakurai, and K. Yoshida. 1975. *Am. Chem. Soc. Div. Eng. Chem. Reprints*: 15(2), Chicago Meeting, August 24-29, pp. 28-31.

APPENDIX 1

UNIVERSITY OF WATERLOO
QUARTERLY REPORT

1.0 WORK COMPLETED IN PRESENT QUARTER

1.1 ACCOMPLISHMENTS

- Completed half of first set of factorial design

1.2 SO₂ Removal Experiments at 21 C

These experiments were carried out at the University of Waterloo. The equipment was run at 21 C with a gas mixture of 2500 ppm SO₂, 5% O₂, 15% CO₂, and the balance N₂.

A factorial design method was started this quarter to determine which of the five operating variables would most effect SO₂ removal, pressure drop and maximum acid strength. Table 1 shows the range and the variables to be studied. A total of 16 experiments are required for this design with 8 replicates in order to estimate the experimental variance. The resolution for this factorial design is 5. This means that single factor interactions are confounded with four factor interactions, and two factor and three factor interactions are confounded.

It should be noted that the flushing medium (deionized water, 2.0 N sulfuric acid) is a blocked variable for convenience.

Table 1: Levels of Variables studied in Factorial Experiments

Variables	Low Value "--"	High Value "+"
1-Space Velocity	1000 cc/cc hr	2900 cc/cc hr
2-Liquid Velocity (superficial)	0.2 cm/s ²	1.0 cm/s
3-Cycle Length	5 minutes	30 minutes
4-Flush Duration	0.5 minutes	3 minutes
5-Flush Liquid	Deionized Water	2.0 N H ₂ SO ₄

Table 2: Conditions for each experiment

	Variables 1	2	3	4	5
Expt # Block A					
F1BA1	+	+	+	-	-
F1BA2	-	+	+	+	-
F1BA3	-	-	+	-	-
F1BA4	-	+	-	-	-
F1BA5	+	-	-	-	-
F1BA6	+	-	-	-	-
F1BA7	+	+	-	+	-
F1BA8	-	+	-	-	-
F1BA9	+	-	+	+	-
F1BA10	-	-	+	-	-
F1BA11	-	+	+	+	-
F1BA12	-	-	-	+	-
Block B					
F1BB1	+	+	+	+	+
F1BB2	+	-	+	-	+
F1BB3	-	+	+	-	+
F1BB4	-	+	+	-	+
F1BB5	-	-	-	-	+
F1BB6	-	-	+	+	+
F1BB7	+	-	+	-	+
F1BB8	-	-	+	+	+
F1BB9	+	-	-	+	+
F1BB10	+	+	+	+	+
F1BB11	-	+	-	+	+
F1BB12	+	+	-	-	+

At this time only the first block of 12 experiments using deionized water as the flushing liquid have been completed. A preliminary examination of the results has been done but with a reduction in the factorial resolution to 3. This means that single factor interactions are confounded with three factor interactions and two factor interactions are confounded with other two factor interactions.

Results for SO_2 removal and maximum sulfuric acid concentration indicate that all factors are significant. This result is meaningless at this time because of the lack of experimental resolution. It is unclear which two factor interactions are important or if three factor interactions have any significance. However, these issues may be cleared up after the next block of experiments is completed.

Another important parameter we looked at was SO_2 conversion. It was determined that the only significant factor was the liquid flushing duration. This indicated to us that what we are seeing is poisoning effect with the BPL activated carbon. During a flush we are not removing all the SO_2 formed on the catalyst surface. Consequently, only by increasing the flush duration can we remove additional SO_2 , opening up more active sites for oxidation to take place and hence increasing SO_2 conversion. We are not sure however if this is due to a problem with the catalyst or the low operating temperatures we are using.

With the completion of the second block of experiments in the next two weeks the effect of the operating variables should become clearer. The results of the individual experiments are reported in Table 3.

Table 3: Individual Experimental Results

	P_{NLF} H ₂ O	P_{LF} H ₂ O	Removal %	H ₂ SO ₄ 10 ⁻³ mol/L	H ₂ SO ₃ 10 ⁻² mol/L	Conversion %
F1BA1	0.5	2.1	7.24	.56	.23	5.10
F1BA2	0.5	1	38.67	.13	.09	23.60
F1BA3	0.5	1	16.57	2.68	.21	15.39
F1BA4	0.5	1	48.55	.09	.19	15.95
F1BA5	1	2.1	10.24	.53	.46	5.53
F1BA6	1	1.6	10.66	.55	.47	5.77
F1BA7	1	4.8	68.34	.07	.14	21.78
F1BA8	0.5	1	49.36	.13	.15	22.84
F1BA9	0.5	2.1	11.32	.83	.18	9.33
F1BA10	0.5	1	13.38	2.09	.21	12.13
F1BA11	0.5	1	35.44	.11	.10	18.51
F1BA12	0.5	1	72.86	.10	.25	20.72

P_{NLF} - indicates pressure drop across reactor with no liquid flow

P_{LF} - indicates pressure drop across reactor with liquid flow

4.0 WORK PLANNED FOR NEXT QUARTER

4.1 SO₂ Removal

After completion of the current factorial design we will run experiments at higher temperatures (80 C) using the BPL to see if there is an improvement in removal, conversion and sulfuric acid concentration. We will also test the CarboTech carbon at the higher temperature for extended periods to see if there is any reduction in removal as seen in the BPL Carbon at low temperatures.

END

**DATE
FILMED**

11 / 3 / 92