AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 1

DOE/PC/90258--T3

1987

CHARACTERIZATION & SUPPLY OF COAL BASED FUELS

Quarterly Report for the Period
May 1, 1987 to July 31, 1987

Energy International, Inc.
135 William Pitt Way
Pittsburgh, PA 15238

September 1987

Prepared For:

U.S. Department of Energy
Pittsburgh Energy Technology Center

Under Contract No. DE-AC22-86 PC90258

MASTER
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

ACKNOWLEDGMENT

Contributors to this report include: Daniel F. Petrunak and Christopher F. Welsh of Dravo Engineers, Inc.; Raymond M. Henry, Russell C. Maxwell, Burl E. Davis and Ronald W. Genser of Energy International, Inc.

DISCLAIMER

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness or any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, mark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PATENT STATUS

This technical report is being transmitted in advance of DOE patent clearance and no further dissemination or publication shall be made of the report without prior approval of the DOE Patent Counsel.

TECHNICAL STATUS

This technical report is being transmitted in advance of DOE review, and no further dissemination or publication shall be made of the report without prior approval from the DOE Program/Project Manager.

CHARACTERIZATION & SUPPLY OF COAL BASED FUELS

Quarterly Technical Report
for the Period
May 1 through July 31, 1987

TABLE OF CONTENTS

	Page Number
1.0 INTRODUCTION & BACKGROUND.....	1
2.0 OBJECTIVES AND SCOPE OF WORK.....	3
2.1 Contract Objectives.....	3
2.2 Contract Scope of Work.....	3
2.3 Task 1 Objectives.....	3
2.4 Task 2 Objectives.....	4
2.5 Task 3 Objectives.....	5
3.0 EXECUTIVE SUMMARY.....	6
4.0 TASK 1 - ANALYSIS OF FUEL NEEDS.....	8
5.0 TASK 2 - CHARACTERIZATION OF COAL BASED FUELS.....	8
6.0 TASK 3 - FUEL SUPPLY.....	19
6.1 Production Facilities.....	19
6.1.1 Deep Cleaned Coal.....	19
6.1.2 Coal-Water Fuels.....	21
6.1.3 Dry Ground Coal.....	21
6.2 Production.....	22
6.2.1 Deep Cleaned Coal.....	22
6.2.2 Dry Powder.....	25
6.2.3 Coal Water Fuels.....	25
6.3 Quality Assurance Plan.....	26
6.3.1 Sample Identification.....	26
6.3.2 Sampling Scheme.....	26
6.3.3 Sample Analysis.....	27
6.3.4 Data Logging.....	31
6.3.5 Sample Shipment Log.....	31
7.0 FUTURE PLANS.....	31
8.0 APPENDICES.....	31
8.1 Sample Data Sheets.....	36
8.2 Sample Shipment Log.....	77
8.3 Production Log.....	81

1.0 INTRODUCTION & BACKGROUND

Under the Department of Energy's Advanced Combustor Technology Program, approximately 11 combustor contractors (under 13 contracts) are developing combustion systems (during 1987-1989) for use in residential, commercial, light industrial and industrial retrofit markets. Sufficient quantities of well-characterized, coal-based fuels possessing specific, appropriate specifications are required by the contractors. Fuels may be dry pulverized coal or coal liquid fuels. In support of these equipment development efforts, the team of Energy International and Dravo Engineers will provide such fuels (under DOE Contract No. DE-AC22-86PC90258 within the PETC Alternate Energy Program).

Nearly a third of the total energy use in the U.S. is in the residential, commercial, and light industrial sectors. Of this, about half of the energy is supplied by the direct consumption (not including electricity) of conventional oil and gas resources. Thus, there is a significant energy use component for which coal is not currently a viable user option.

For coal to significantly penetrate this important market sector, it must be demonstrated that:

- o Premium coal-based fuels can be made, combusted, and used in low maintenance, automatic use systems to which such users are accustomed, i.e., be a direct replacement for conventional fuels and require only simple installation changes.
- o Advanced coal fuel combustion systems can effectively combust coal based fuels while meeting economic, environmental, and performance standards.
- o Coal fuels, combustion systems and service support are well matched, reliable, cost effective, and are anticipated to be available over the projected lifetime of the installations.

The key to development of fuel and combustor technologies for future application to the use of premium coal-based fuels in the residential, commercial and light industrial energy use sectors is to make available representative coal fuels for developmental testing. Current technologies in early development stages offer the promise to meet the market, the performance and the environmental acceptability that are expected to be required. However, the developmental testing of advanced combustion equipment systems requires fuels for testing; test experience and performance measures are needed to identify cost competitiveness in the market and specific market niches for early commercialization; and, commercial market opportunities are needed to justify and specify the development and installation of advanced fuels facilities for supplying the developmental testing needs.

The capability to produce significant quantities of coal based fuels cannot be supported in the current economic and energy use situation. Once these pieces of experience and information begin to fall into place, the market driven needs will more clearly identify the suite of coals that will satisfy the markets and the performance requirements (i.e., cost, maintenance, energy efficiency, environmental). For now, it is important to provide sufficient quantities of surrogate fuels to enable development testing to proceed. While the definitions of market and performance are not finalized nor quantitatively fixed and the eventual, economically acceptable fuel processes are not yet determined, it is possible to make use of current understanding of coal resources, markets, combustor and environmental requirements and specific available coal properties and characteristics to make reasonable selections of coals for fuels representative of future advanced fuels. With current versions of advanced premium coal-based fuels even though the associated excessive grinding, special processing, low energy recoveries, and process economics would not be acceptable for eventual commercial operations.

The analysis of fuel needs, the selection of candidate coals, the characterization and supply in this contract are to be accomplished with the above in mind. The best choices of those available will be made based upon the available information, coal and processes. This will at least provide the developmental test fuels that will enable the DOE-PETC advanced combustion and fuels program to move forward. Following the fuels and combustor development activities that this supply contract will support, it is expected that additional optional candidate coals will become evident based on the new experience. In the meantime, these coal fuels will enable the program to proceed.

During the third quarter of this contract (May 1 through July 31, 1987) the primary activities were involved with:

- o Completion and submission for approval by the DOE of the topical report describing the market survey, the coal selection and the fuel specification methodologies used in carrying out Task 1.
- o The determination of the washability of the first five coals selected in Task 1.
- o Upgrading and improvement of the pilot wash circuit to improve both the product quality and yield.
- o Initiation of a data base survey to select an appropriate coal for the Vortec contract.
- o Continuation of the coal procurement, cleaning, fuel preparation and delivery activities.

The progress on the above activities is reported in the following sections of this report.

2.0 OBJECTIVES AND SCOPE OF WORK

2.1 Contract Objectives

Contract objectives are as follows:

- o Develop fuel specifications to serve combustor requirements.
- o Select coals having appropriate compositional and quality characteristics as well as an economically attractive reserve base.
- o Provide quality assurance for both the parent coals and the fuel forms.
- o Deliver premium coal-based fuels to combustor developers as needed for their contract work.

2.2 Contract Scope of Work

Energy International/Dravo will perform the following:

- o From information obtained both from the combustor PRDA and from the combustor contractors, develop fuel specifications and schedule.
- o Using published reports and databases, perform a market assessment and a resource assessment in order to identify acceptable coals within reasonable proximity to markets. In other words, determine the availability and applicability of a wide range of coals in order to produce premium coal-based fuels for specific markets.
- o From all coal ranks and all domestic resources select eight coals which satisfy the requirements of combustion systems being developed.
- o Procure premium coals having the ability to be processed to contain <0.8 lb ash per million Btu and <0.5 lbs sulfur per million Btu.
- o Procure coals and produce coal liquid mixtures or dry pulverized coal and deliver these premium fuels to combustor contractors.

2.3 Task 1 Objectives

The objectives of Task 1, "Analysis of Fuels Needs", are as follows:

- o To provide analyses, information and evaluation of coal resources, coal properties, and market opportunities to support the selection of coals for characterization, processing and supply.

- o To assure that coals used in developmental testing are representative of future potential coal used in those applications and are:
 - Available as U.S. domestic resource in sufficient quantity
 - Geographically proximate to the regional markets
 - Capable of being processed into premium coal-based fuels that have the properties to satisfy the combustor needs and market constraints (such as environmental)
- o To evaluate, interpret and assess the available information on coal reserves, market opportunities, performance requirements, environmental acceptability, coal properties and specific characteristics to provide guidance in the selection of candidate coals for characterization and supply for developmental testing of advanced combustors for residential, commercial and light industrial applications.
- o To collect, review and evaluate information about specific, currently available coals that can be procured from existing mining operations to provide contracted quantities of development test fuels that satisfy the reserves, market, geographic, property, performance and environmental criteria.
- o To recommend candidate coals and then select specific coals to be purchased, processed into coal-based premium fuels, and supplied to DOE users.
- o To coordinate the performance requirements of combustor developers under DOE-PETC contract and in-house efforts with the selection and supply of coals.

2.4 Task 2 Objectives

The objectives of Task 2, "Characterization of Coal Based Fuels", are as follows:

- o To procure representative samples of the eight coals selected in Task 1 and prepare them for characterization studies.
- o To obtain baseline analytical data for each of the parent coals.
- o To carry out bench-scale froth flotation cleaning test on each of the candidate coals to determine the yield of specification coal attainable from each.
- o To carry out detailed washability studies for each coal to determine the effect of particle size reduction on mineral matter liberation as well as the coal yield as a function of the specific gravity of the separation.

- o Based on the results of the characterization studies, to select a coal or suite of coals suitable for the preparation of the fuels to meet the specifications of the combustor contractors.

2.5 Task 3 Objectives

The objectives of Task 3, "Fuel Supply" are as follows:

- o To design, construct, and operate a 2.5 ton/hr coal wash circuit.
- o To design, construct, and operate a coal/water slurry preparation plant, if required.
- o To purchase and arrange for the delivery of the appropriate coals for fuel preparation.
- o To clean the coals to meet the specifications necessary for the specific fuel, i.e., slagging versus non-slagging, industrial versus residential, etc.
- o To prepare the coal based fuels according to the specifications of the PRDA and as modified or requested by the combustor contractors.
- o To deliver the fuel to the combustor contractor on schedule.
- o To characterize each fuel prior to shipment to assure that the specifications are being met.

3.0 EXECUTIVE SUMMARY

Under the Department of Energy's Combustor Technology Program, approximately 11 combustor contractors (under 13 contracts) are developing combustor systems (during 1987-1989) for use in residential, commercial, light industrial and industrial retrofit markets. Sufficient quantities of well-characterized, coal-based fuels processing specific, appropriate specifications are required by the contractors. Fuels may be dry pulverized coal or coal-water fuels. In support of these equipment development efforts, the team of Energy International and Dravo Engineering Companies will provide such fuels under DOE Contract No. DE-AC22-86PC90258.

During the third quarter of this contract (May 1 through July 31, 1987) the primary activities were involved with:

- o Completion and submission for approval by the DOE of the topical report describing the market survey, coal selection and fuel specification methodologies used in carrying out Task 1.
- o The determination of the washability of the first five coals selected in Task 1.
- o Upgrading and improvement of the pilot wash circuit to improve both the product quality and yield.
- o Initiation of a data base survey to select an appropriate coal for the Vortec contract.
- o Continuation of the coal procurement, cleaning, fuel preparation and delivery activities.

A brief summary of these activities is as follows.

A preliminary part of Task 1 was completed with the writing of a report detailing the market survey, coal selection process and the establishment of fuel specifications was completed. It was submitted to DOE's Program Manager for approval. Task 1 will continue with further selections of coals for new requirements, and Task 1 Project Management and Administration will continue.

Under Task 2 washability studies on the five candidate coals selected earlier this year (Task 1) were completed for the 1/8" x 0 and the 28 x 0 mesh particle size fractions at specific gravities of 1.3, 1.275 and 1.3. The analytical data for each sink-float fraction (proximate analysis only) were obtained and tabulated. Data are presented in this report.

Under Task 3 several major improvements were made to the froth flotation cleaning circuit. In order to reduce plugging in the cyclone feed and discharge lines the 3" cyclone was replaced with a 4" classifying cyclone having a larger diameter inlet and outlet lines. This not only eliminated the plugging problem but, after rebalancing the circuit, increased the maximum feed rate capabilities of the wash circuit from 300 to 450 lbs/hr. A variable speed piston pump was installed for reagent feeding. This resulted in better control of the reagent dosage and, as a result, a more consistent product ash is being obtained.

In conversations with Vortec concerning their fuel needs it became evident that the criteria we had established for the other combustor contractors was not applicable to Vortec's needs. Their prime concern was the ash fusion temperature and the mineral matter composition, primarily the iron content. Therefore, an additional search (under Task 1) was begun to find a suitable coal for their application.

4.0 TASK 1 - ANALYSIS OF FUEL NEEDS

A data base review was initiated to find coal suitable for use by Vortec. The criteria used for the original coal selection process (performed earlier in FY 87 under Task 1) was primarily the ability of the coal to be cleaned to the desired ash and sulfur levels. However, the important criteria for use in the Vortec process is the ash fusion temperature and the iron content of the coal. The investigators at Vortec would like to have a coal with an ash content of 5-10% whose fluid ash temperature was <2450°F and whose ash iron oxide content is below 10%. None of the five previous selected coals would meet both criteria; so a search for a suitable coal was begun.

5.0 TASK 2 - CHARACTERIZATION OF COAL BASED FUELS

Washability studies of the five candidate coals selected in Task 1 continued. The coals selected were (1) Upper Elkhorn #1 (coal bed No. 157), (2) Upper Elkhorn #2 (coal bed No. 154), (3) Upper Elkhorn #3 (coal bed No. 151), (4) Lower Elkhorn (coal bed No. 168), and (5) Colorado Coal Bed D (coal bed No. 755). To date the washability data for the five coals ground to 1/8" x 0 and 28 x 0 mesh and sink/floated at specific gravities of 1.25, 1.275 and 3.0 have been completed. The data obtained thus far are shown in Tables 5.1a and 5.1b for the Upper Elkhorn #1, 5.2a and 5.2b for the Upper Elkhorn #2, 5.3a and 5.3b for the Upper Elkhorn #3, 5.4a and 5.4b for the Lower Elkhorn and 5.5a and 5.5b for the Colorado Coal Bed D. When the data for the other sizes (i.e., 100 x 0 and 200 x 0 mesh) are obtained complete washability curves will then be constructed.

Table 5.1a

```

COAL1 UPPER ELKHORN #1, ALMA SEAM      % NSH      =      5.10
COAL ID: UE1-103-WRM-D                 % S         =      (1.00)
SCREENED FROM 1/8" NO GROUND COAL      BTU/LB      =     14501

```

file:15714
update:00/03/07

Screen analysis			Analysis of Screened Fractions							
Fraction	Weight	Wt.	Each Fraction (Dry Basis)		BTU	Wt.	Cumulative		BTU	
			%ash	%Sul			%ash	%Sul		
90+20	573.00	45.57	6.13	0.95	14060	45.57	6.13	0.85	14060	
20+100	421.15	33.50	5.06	0.88	13997	79.07	5.60	0.85	14033	
10+200	111.79	8.89	5.67	0.91	14004	87.96	5.60	0.86	14030	
10+270	26.73	2.13	6.17	0.93	14100	90.09	5.69	0.86	14032	
170+400	35.94	2.94	7.62	0.99	13843	93.02	5.75	0.86	14028	
100+40	87.72	6.98	11.91	0.90	12990	100.00	6.10	0.87	13954	
TOTAL	1257.33	100.00								

[illegible][illegible][illegible][illegible][illegible]

-10-
Table 5.1b

CONL UPPER ELKHORN #1, ALMA SEAM %ASH = 5.18
CONL 101 UE1-103-ARM-D %S = 0.80
SCREENED FROM 200H MESH GROUND CONL BTU/LB = 14261

file:sfue1b
update:10/03/87

Screen analysis - Analysis of Screened Fractions									
Each Fraction (Dry Basis)									
Fraction	Weight	%wt.	%ash	%sul	BTU	%wt.	%ash	%sul	BTU
1/8W20									
20W100	367.95	71.33	5.72	0.82	14260	71.33	5.72	0.82	14260
100W200	53.29	10.33	4.28	0.85	14419	81.66	5.54	0.82	14287
200W270	19.68	3.81	5.34	0.84	14231	85.47	5.53	0.82	14284
270W400	18.35	3.56	0.00	0.00	0	89.03	5.31	0.79	13714
400W0	56.60	10.97	9.75	0.90	13179	100.00	5.80	0.80	13655
TOTAL	515.87	100.00							

Size: 20W100 mesh fraction									
Float / Sink Analysis									
Each Fraction (Dry Basis)									
Cum. Recovery (Float)									
Cum. Reject (Sink)									
Sink Float	Weight	%wt.	%ash	%sul	BTU	%BTU	%wt.	%ash	%sul
BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU
1.25	52.69	14.93	1.02	0.63	15193	15.89	14.93	1.02	0.63
1.25 W 1.275	115.44	32.70	1.20	0.65	15062	34.52	47.63	1.14	0.64
1.275 W 1.30	100.68	28.52	1.96	0.74	14804	29.59	76.15	1.45	0.68
1.30	84.18	23.85	19.37	1.25	11958	19.99	100.00	5.72	0.82
TOTAL	352.99	100.00							

Size: 100W200 mesh fraction									
Float / Sink Analysis									
Each Fraction (Dry Basis)									
Cum. Recovery (Float)									
Cum. Reject (Sink)									
Sink Float	Weight	%wt.	%ash	%sul	BTU	%BTU	%wt.	%ash	%sul
BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU
1.25	2.58	6.31	1.10	0.65	na	0.00	6.31	1.10	0.65
1.25 W 1.275	8.32	20.35	0.94	0.66	15121	22.85	26.86	0.98	0.66
1.275 W 1.30	22.83	55.94	1.37	0.70	14882	61.17	82.00	1.24	0.69
1.30	7.36	18.00	18.10	1.58	11958	15.98	100.00	4.28	0.85
TOTAL	40.89	100.00							

Size: 200W270 mesh fraction									
Float / Sink Analysis									
Each Fraction (Dry Basis)									
Cum. Recovery (Float)									
Cum. Reject (Sink)									
Sink Float	Weight	%wt.	%ash	%sul	BTU	%BTU	%wt.	%ash	%sul
BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU
1.25	1.13	5.84	0.97	0.61	na	0.00	5.84	0.97	0.66
1.25 W 1.275	6.00	31.02	0.95	0.66	14971	34.77	34.87	0.95	0.66
1.275 W 1.30	7.79	40.28	1.45	0.70	14900	44.93	77.15	1.21	0.68
1.30	4.42	22.85	19.27	1.46	11860	20.29	100.00	5.34	0.86
TOTAL	19.34	100.00							

Size: 270W400 mesh fraction									
Float / Sink Analysis									
Each Fraction (Dry Basis)									
Cum. Recovery (Float)									
Cum. Reject (Sink)									
Sink Float	Weight	%wt.	%ash	%sul	BTU	%BTU	%wt.	%ash	%sul
BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU	BTU
1.25	0.31	1.74	0.00	0.00	0	ERR	1.74	0.00	0.00
1.25 W 1.275	0.32	1.79	0.00	0.00	0	ERR	3.53	0.00	0.00
1.275 W 1.30	11.53	64.59	0.00	0.00	0	ERR	68.12	0.00	0.00
1.30	5.69	31.88	0.00	0.00	0	ERR	100.00	0.00	0.00
TOTAL	17.85	100.00							

file:sfue2a
update:08/03/07

[illegible]

COAL: UPPER ELKHORN, #2 LOWER CEDAR GROVE	% ASH	=	5.52
COAL ID: UE2-106-WRM-D	% S	=	0.52
SCREENED FROM 20#0 MESH GROUND COAL	BTU/LB	=	14331

file:1#fu+2b
update:100/03/87

Screen analysts

Analyses of Screened Fractions

Fraction	Weight	Sht.	Each Fraction (Dry Basis)			Cumulative			
			Moist	XSul	NU	Sht.	Moist	XSul	NU
1/6428									
28H100	353.12	72.33	5.24	0.55	14039	72.33	5.24	0.55	14039
100H200	50.88	10.42	0.00	0.00	0	82.75	4.58	0.48	12271
200H270	14.66	3.04	0.00	0.00	0	85.80	4.42	0.46	11636
270H400	17.36	3.56	0.00	0.00	0	89.35	4.24	0.44	11366
400H6	51.97	10.65	6.14	0.50	15431	100.00	4.66	0.45	11585
TOTAL	488.19	100.00							

Size: 20x100 mesh; fraction

Float /Sink Analysis

[illegible]

Size: 100+200 mesh fraction

Float / Sink Analysis

[illegible]

Size: 200x270 mesh fraction

Float / Slick Analysis

[illegible]

Size: 270x400 mesh fraction

Float /Sink Analysis

[illegible]

file:rfue3b
update:08/03/87

Analysis of Screened Fractions

Fraction	Weight	Wt.	Each Fraction Cur Basis			Cumulative			
			Wt.	Wt.	BTU	Wt.	Wt.	Wt.	BTU
1/8W20									
20W100	325.10	74.33	1.97	0.60	15056	74.33	1.97	0.60	15056
100W200	44.17	10.10	2.17	0.61	14952	84.43	1.99	0.60	15043
200W270	16.24	3.71	2.55	0.62	14963	90.14	2.02	0.61	15040
270W400	9.48	2.17	3.01	0.64	15156	99.31	2.04	0.61	15043
400W0	42.40	9.69	4.72	0.65	14130	100.00	2.30	0.61	14954
TOTAL	437.47	100.00							

Float /Sink Analysis

[illegible]

Float / Sink Analysis

[illegible]

Float /Sink Analysis

[illegible]

Float /Sink Analysis

[illegible]

-15-
Table 5.4a

COAL: LOWER ELMHORN, FORD CREEK SEAM 2, A5H = 6.90
COAL ID: LEL-091-URM-0 % S = 0.57
SCREENED FROM 1/8" MO GROUND COAL BTU/LB = 13763

file:lefile
update:108/03/87

Screen Analysis									
Analysis of Screened Fractions									
Fraction	Weight	Wgt.	Each Fraction (Dry Basis)		BTU	Wgt.	Cumulative		
			%ash	%sul			%ash	%sul	BTU
1/8H20	810.20	67.04	6.15	0.55	13200	67.04	6.15	0.55	13200
20H100	222.64	18.46	5.97	0.59	13157	86.70	6.11	0.56	13191
100H200	59.56	4.94	5.61	0.65	13140	91.24	6.09	0.56	13180
200H270	19.45	1.61	6.34	0.77	13298	92.85	6.09	0.57	13190
270H400	20.08	1.66	6.16	0.73	13289	94.51	6.09	0.57	13192
400H0	66.18	5.49	11.78	0.61	12176	100.00	6.40	0.57	13136
TOTAL	1206.09	100.00							

Size: 1/8"H20 mesh fraction									
Float / Sink Analysis									
Sink Float	Weight	Wgt.	Each Fraction (Dry Basis)		BTU	Wgt.	Cum. Recovery (Float)		
			%ash	%sul			%ash	%sul	BTU
1.25	158.13	25.76	1.18	0.53	13905	27.13	25.76	1.18	0.53
1.25 M 1.275	212.68	34.64	2.01	0.52	13835	36.31	60.40	1.66	0.52
1.275 M 1.30	95.48	15.55	5.62	0.51	13388	15.75	75.95	2.47	0.52
1.30	147.66	24.05	17.79	0.64	11422	20.81	100.00	6.15	0.55
TOTAL	613.95	100.00							

Size: 20H100 mesh fraction									
Float / Sink Analysis									
Sink Float	Weight	Wgt.	Each Fraction (Dry Basis)		BTU	Wgt.	Cum. Recovery (Float)		
			%ash	%sul			%ash	%sul	BTU
1.25	41.60	19.82	1.1	0.55	14012	21.11	19.82	1.10	0.55
1.25 M 1.275	44.22	21.07	1.33	0.56	13710	21.95	40.88	1.22	0.56
1.275 M 1.30	64.68	30.81	2.32	0.53	13737	32.17	71.70	1.69	0.54
1.30	59.41	29.30	16.81	0.72	11517	24.77	100.00	5.97	0.59
TOTAL	209.91	100.00							

Size: 100H200 mesh fraction									
Float / Sink Analysis									
Sink Float	Weight	Wgt.	Each Fraction (Dry Basis)		BTU	Wgt.	Cum. Recovery (Float)		
			%ash	%sul			%ash	%sul	BTU
1.25	0.32	0.57	na	na	na	0.00	0.57	na	na
1.25 M 1.275	7.21	12.90	1.01	0.59	13983	13.62	13.48	0.97	0.56
1.275 M 1.30	28.82	51.58	1.31	0.55	13702	54.12	65.06	1.24	0.55
1.30	19.52	34.94	13.74	0.82	11986	32.06	100.00	5.61	0.65
TOTAL	55.87	100.00							

Size: 200H270 mesh fraction									
Float / Sink Analysis									
Sink Float	Weight	Wgt.	Each Fraction (Dry Basis)		BTU	Wgt.	Cum. Recovery (Float)		
			%ash	%sul			%ash	%sul	BTU
1.25	0.08	0.45	na	0.67	na	0.00	0.45	na	0.67
1.25 M 1.275	0.25	1.41	na	0.60	na	0.00	1.66	na	0.62
1.275 M 1.30	10.67	60.15	1.22	0.58	14074	64.93	62.01	1.18	0.58
1.30	6.74	37.99	14.76	1.09	12032	35.07	100.00	6.34	0.77
TOTAL	17.74	100.00							

Size: 270H400 mesh fraction									
Float / Sink Analysis									
Sink Float	Weight	Wgt.	Each Fraction (Dry Basis)		BTU	Wgt.	Cum. Recovery (Float)		
			%ash	%sul			%ash	%sul	BTU
1.25	0.08	0.42	na	0.65	na	0.00	0.42	na	0.65
1.25 M 1.275	0.50	2.65	na	0.56	na	0.00	3.08	na	0.57
1.275 M 1.30	5.03	26.67	1.01	0.55	14015	29.07	29.75	0.91	0.55
1.30	13.25	70.25	8.38	0.80	12982	70.93	100.00	6.15	0.73
TOTAL	18.86	100.00							

file:fileb
update:00/03/07

Analyses of Screened Fractions

[illegible]

Float /Sink Analysis

[illegible]

Float /Sink Analysis

[illegible]

file:isfcbda
update:100/03/07

[illegible]

file1sfcbdb
update100/03/07

Analyses of Screened Fractions

[illegible]

Float /Sink Analysis

[illegible]

Float /Sink analysis

[illegible]

Float /Sink Analysis

[illegible]

6.0 TASK 3 - FUEL SUPPLY

6.1 Production Facilities

The matrix of fuel requirements as shown in Table 6.1.1 has set into motion several contract facilities to supply the desired fuel forms. No single organization has yet been found or is expected to provide deep cleaning capabilities, dry pulverizing, dry micronizing and coal slurring technology unless a new plant is constructed with a primary goal of supplying fuel for this contract. Specific selections of contractors used to date and facilities are described below.

Table 6.1.1

BITUMINOUS FUEL FORMS REQUIRED FOR THIS PROJECT

	Dry Coal		Coal Water Coals	
	<u>Pulverized</u>	<u>Micronized</u>	<u>Pulverized</u>	<u>Micronized</u>
Deep Cleaned	X	X	X	X
Standard	X	X	X	X

6.1.1 Deep Cleaned Coal

Following DOE approval of February 6, 1987, Dravo initiated the design, modification and operation of their pilot facilities for the production of deep cleaned coal meeting the low ash and sulfur requirements of between 0.8 and 1.0 lbs ash per million Btu's and 0.5 to 0.8 lbs sulfur per million Btu's. The process consists of a four-phase operation including grinding, classification, beneficiation, and drying.

As of April 30, three phases of the four phase operation excluding drying, were successfully operated at a production rate of 300 lb/hr using an Upper Elkhorn No. 3 feedstock. Drying was accomplished as a 600 lb batch operation in a thermostatically controlled BLUE M oven.

This Upper Elkhorn #3 coal was chosen as the parent or baseline fuel on the basis of its proven deep cleaning potential as previously reported and its unique washability characteristics which enhance recoveries. The unique washing characteristics of this coal results in less impurities in the coarser size fractions thus providing a lower ash feed stock for the deep cleaning operation. Therefore, by selecting the wash plant stoker fraction (i.e., 1" x 1/4"), higher recoveries can be obtained thereby reducing the amount of feed coal required and consequently lowering the cost of the deep cleaned coal.

In early May, during pilot operation it was determined that due to classifying cyclone configuration and operating parameters an inordinate amount of "plugging" was occurring in the cyclone feed and discharge lines. To resolve the problem, the existing 3" diameter cyclone was replaced with a 4" classifying cyclone having a feed inlet of 1.25 sq. inches and a .75 inch diameter Vortex finder. These changes ultimately required a higher volumetric throughput at a lower pressure drop to achieve similar classification efficiencies. Consequently, the higher thruput affected the grinding circuit recirculating load and mandated additional feed solids to achieve the desired grind. After proper circuit rebalancing the end result allowed an additional 50% operating circuit capacity for a total of 450 lb/hr feed rate. These changes increased the feed solids concentration to the flotation cell from 7% to 9%, but had no detrimental effect on product quality.

The second major improvement made to the DRAVO pilot circuitry was the purchase and installation of a variable speed piston reagent metering pump. Prior to the purchase, frother dosage was controlled with a gravity fed "IV" bottle, but due to fluctuations in head pressure and inaccuracy of the throttling valve, reagent dosage had to be continuously monitored to achieve near desirable results. The new piston pump has precise supply capabilities of between 0.5 and 1.0 milliliters per minute. After installation consistent product ash results were dramatically improved.

The pilot circuit had been originally designed to use a continuous supply of tap water for processing; however, due to discharge effluents exceeding the existing waste water disposal capacity with regard to pounds of solids per minute it became necessary by the end of May to modify the circuitry with a water clarification and redistribution system. Installation of a sump pump in the wash down water sump with a return line to the refuse thickener and a clarified water process sump with overflow and head tank combination provided a means of reprocessing all plant discharges with only clarified water leaving the circuit. All process water modifications were completed by June 8, 1987.

Also, two pieces of leased equipment have added to the production capability. These include a 36" diameter Eimco drum filter and Learco Bethlehem dryer. Due to a combination of product recoveries and reprocessing spills from the wash down sump, it became imperative to include a separate unit operation for refuse dewatering prior to disposal. Before the drum filter was leased the normal mode of operation was to store the fine refuse in a 2000 gallon thickener and re-utilize the existing clean coal two-disc, 24-inch diameter vacuum filter. This practice became burdensome and time consuming especially when clean coal recoveries fell below 40%. The drum filter arrived on June 26 and after minor equipment problems involving the vacuum pump, became operational by the end of June.

Because of the limiting capabilities of the batched oven process, increasing demand for micronized fuels and the inability of selected micronizing contractors to dry coal prior to micronizing, it became necessary to include a continuous fine coal dryer in the circuit. Of the two comparable and commercially available units, the Bethlehem disc processor was selected due to "immediate" availability. By the end of June, the new dryer unit arrived from Learco; however, not until July 23 was the disc processor ready for operation. Several problems associated with the design

of the feed system from the existing clean coal vacuum disc filter, circulation of hot oil, and design and fabrication of an exhaust hood to remove gaseous vapors of steam, coal dust and volatiles delayed unit operation from the anticipated scheduling. By the end of July the disc processor performance was optimized with an evaporation capability of drying coal to less than 5% total moisture at a continuous feed rate of 200 dry lbs/hr.

6.1.2 Coal-Water Fuels

As described in the previous Quarterly Report (February - April, 1987), after an extensive survey of potential slurry manufacturers, OXCE Fuel Company of Windsor, CT has been selected as the coal-water fuel supplier for this contract. They have the experience, facilities and technical expertise needed to prepare the fuels. They also gave assurances of their intention and commitment to perform during the length of this prime contract.

6.1.3 Dry Ground Coal

Two dry coal subcontractors were used during the third quarter of the contract: Penn Rilton Company and Particle Reduction Services. Early production of dry (i.e., <5.0% moisture) fine deep cleaned coal from the DRAVO facility required the use of a thermal oven for batched drying. Even though the product that is produced from the pilot circuitry is standard grind coal with 100% passing a 150 mesh screen opening, the oven procedure resulted in dried clumps of compacted coal. Therefore, to redistribute the coal into fine discrete particles required the use of a screen/crusher combination. Penn Rilton Company, Division of Whitehead Brothers of West Elizabeth, PA was selected for reasons of close proximity and equipment capable of handling bulk tonnages. By feeding the coal into a hammermill afixed with a 28 mesh screen deck guaranteed the desired particle separation. Penn Rilton also has the capability of hydraulically conveying the ground coal particles with a forced air system thus enabling even further drying.

Particle Reduction Services Corporation (PRS) of Illinois was also selected as an interim micronizer until the final determination of a long term pulverizer/micronizer subcontractor was made. This procedure became necessary because of the immediate needs of several of the combustor contractors requesting dry micronized fuel prior to and continuing after May 1987. The procedure used by PRS was an air swept high energy type mill utilizing particle on particle bombardment at a feed rate of 100 lb/hr. Quality specification assurance was achieved with test runs prior to a new feed stock and aliquot samples obtained during production runs with Microtrac^(R) analysis performed on all samples by Dravo Corporation.

The limiting capabilities of PRS based on production rate reaffirmed the need to establish a long-term subcontractor through FY 1988. By the end of June a commitment was made by Schutz-O'Neill Company of Roseville, Minnesota to supply micronized fuels to the combustion contractors based on the demand exhibited by the most up-to-date schedule available. Documents for procurement approval were prepared and subsequently a subcontractor agreement was signed by the end of July 1987.

6.2 Production

6.2.1 Deep Cleaned Coal

During this period of May through July the following bulk shipments of Upper Elkhorn #3 were made from the mine wash plant to the Dravo Research Center:

UE3-109-WRM-A - 23 tons < 3.5% ash
UE3-110-WRM-A - 26 tons > 6.0% ash
UE3-118-WRM-A - 23 tons < 3.5% ash
UE3-127-WRM-A - 25 tons < 3.5% ash
UE3-132-WRM-A - 22 tons < 3.5% ash
UE3-136-WRM-A - 23 tons < 3.5% ash

All of the shipments except UE3-110 were feedstock for the pilot circuit. Shipment UE3-110 was inadvertently shipped to DRAVO then forwarded to OXCE Fuel Company for manufacture of CWF for PETC. From these shipments a total of 299 drums of deep cleaned product were prepared not including those clean product coals produced from shipment UE3-136 which was received at the end of the quarter. The DRAVO shipment inventory shown in Appendix 8.3 details date of manufacture, specification quality, gross drum weight and shipment identification. In total, eight shipments amounting to 25.0 tons of deep cleaned coal, identified in Appendix 8.3, was shipped from Dravo to subcontractors for final processing.

As shown on Appendix 8.3 quality analysis is performed on a per drum basis and each time drum contents are reprocessed in one form or another. In addition, hourly production samples are obtained from the process circuitry to determine if the ash content is meeting the desired specifications and at what production rate, which is calculated by collecting timed samples and analyzing for percent solids. Also routinely on a daily basis ash balances are determined around the flotation circuitry and compared to the material balance calculations. These analyses provide a continuous means of monitoring production and quality specifications. Table 6.2.1 shows the ash balance relationships. A balanced flowsheet provided in Figure 6.2.1 graphically illustrates a normal production run during the period of 5/87 to 7/87.

Table 6.2.1

ASH BALANCE RELATIONSHIPS

Date	Feed Ash	Primary		Secondary		System Recovery
		Product	Tails	Product	Tails	
5/1	2.69	1.70	6.59	1.23	2.94	57.83
5/14	3.00	1.85	4.52	1.30	3.31	41.35
5/15	2.36	1.97	7.50	1.58	6.76	85.95
5/18	3.10	2.62		1.60	2.62	0.00*
5/19	3.06	1.94	3.82	1.26	4.54	32.04
5/20(FAG)	3.37	1.76	8.86	1.03	21.01	74.50
5/21	3.12	1.73	4.90	1.25	2.30	30.48
5/22	2.97	1.82	4.49	1.27	2.35	27.94
5/27	3.02	1.70	4.51	1.20	2.34	29.77
6/8	3.10	1.86	8.92	1.54	9.48	79.11
6/11	2.85	1.60	4.88	1.28	2.75	48.42
6/12	2.75	1.79	7.94	1.38	3.10	64.27
6/16	2.84	1.66	3.81	1.21	2.26	25.78
6/19		1.47	3.43	1.12	2.10	20.99*
6/24	2.76	1.68	4.81	1.29	2.94	50.02
7/1	2.72	1.71	4.21	1.26	2.68	40.71
7/2	2.69	1.87	5.43	1.26	2.58	41.40
7/8	2.48	1.74	3.42	1.18	2.53	32.74
7/9	2.57	1.60	4.02	1.15	2.42	38.69
7/10	2.52	1.58	3.88	1.21	2.28	38.68
7/13	2.50	1.65	4.27	1.19	2.31	39.81
7/14	2.42	1.47	4.10	1.11	2.34	45.18
7/16	2.83		4.07	1.64	23.73	53.43*
7/28	2.49	1.75	5.51	1.41	2.73	59.63
AVG.	2.79	1.76	5.12	1.29	4.77	44.11

*Calculation based on average for missing parameter.

Figure 6.2.1

DRAVO RESEARCH CENTER SMALL PILOT PLANT

REV. 1

LEGEND

# COAL/HR	# WATER/HR
-----------	------------

6.2.2 Dry Powder

The following shipments were made from pulverizer/micronizer sub-contractors to DOE combustor contractors:

- UE3-112-PCO-C - 2000# pulverized deep cleaned coal <1.5% ash from Penn Rilton to MTCI
- UE3-123-MCO-C - 24 drums (5412 lbs) micronized deep cleaned coal at 1.16% ash from PRS to MTCI
- UE2-125-MCO-C - 5 tons micronized 2.0% ash mine-site-prepared coal from PRS to PETC
- UE2-126-MCO-C - 5 tons micronized 2.0% ash mine-site-prepared coal from PRS to PETC
- UE3-128-MCO-C - 200# micronized 2.0% ash mine-site-prepared coal from PRS to EER
- UE3-133-MCO-C - 200# micronized deep cleaned coal at 1.2% ash from PRS to EER
- UE3-135-PCO-C - 20 drums pulverized deep cleaned coal at 1.28% ash from Penn Rilton to MTCI

6.2.3 Coal-Water Fuels

The following coal-water fuels were prepared and shipped to the combustor contractors by OXCE Fuel Company during the third quarter of the contract period.

- ELC-108-CWF-F - 350 gallons of a standard grind slurry prepared from Elk Creek coal which OXCE had on hand.
- UE3-116-UCW-F - Six drums (350 gallons) of a micronized slurry prepared from deep cleaned (1.3% ash) coal. Four drums for MTCI and one drum each for EER and Tecogen.
- UE3-117-CWF-F - 2000 gallons of a standard grind slurry prepared from 6% ash coal for PETC.
- UE3-120-CWF-F - 720 gallons of a standard grind slurry prepared from deep cleaned (1.3% ash) coal. 600 gallons for MTCI and 120 gallons for PETC.
- UE3-121-UCW-F - 600 gallons of a micronized slurry from a deep cleaned (1.3% ash) coal for MTCI.

6.3 Quality Assurance Plan

In order to assure that specification fuel is being produced and that the coal samples used in the fuel preparation can, if necessary, be traced back to the mine mouth, a quality control plan has been established for the fuel supply contract being carried out by Energy International, Inc.

The plan developed consists of the following elements:

1. Sample identification
2. Sampling scheme
3. Sample analyses
4. Data logging
5. Sample shipping log

Details of each element are described below.

6.3.1 Sample Identification

The sample identification scheme is shown in Figure 6.3.1 and the identified tables. The sample number consists of 10 characters which will identify the coal bed from which the sample came; what type of coal or fuel it is; the origin of the sample, and the sequential sample number. Thus, if a sample is identified as UE3-200-CWF-F it means it is a standard grind coal water fuel (CWF) prepared by OXCE Fuel Company (F) from an Upper Elkhorn #3 coal (UE3) and is the 200th sample shipped under this contract. The three digit number can be considered a serial number. The other possible designations for the sample identification are shown in Tables 6.3.1, 6.3.2 and 6.3.3.

6.3.2 Sampling Scheme

The points at which samples are to be taken during the movement of the coal from the mine through the various processing steps until reaching the combustor are shown in Figure 6.3.2. The coal obtained from the mine wash plant is shipped either to Dravo or, in cases where no cleaning is necessary, to the fuel makers. The coal is sampled at this point (sampling point 1). In order to obtain the ultraclean coal required by most of the combustor contractors the coal is cleaned by Dravo by froth flotation. Hourly samples are taken for quality control of the process (sampling point 2). Generally only ash values are obtained. For shipment of the deep cleaned coal to OXCE for coal-water fuel preparation the wet filter cake is removed batchwise and placed in drums so it is impossible to obtain a representative sample of the deep cleaned coal at the cleaning plant. A representative coal analysis is obtained, however, by taking a sample of the finished slurry fuel and isolating the coal from it and submitting it for analyses (sampling point 6). Meanwhile, OXCE samples the slurry for themselves (sampling point 3) and determines certain physical and rheological properties. An additional representative sample of the slurry is taken by OXCE (sampling point 4) and sent to Energy International to confirm the analyses and to carry out storage stability tests. A portion of this sample

is sent to Dravo for the coal isolation and analysis as described earlier. Finally, if the deep cleaned coal is used for preparation of pulverized or micronized coal a representative sample of the fuel is obtained by Dravo from the micronizer (sampling point 5) and submitted for analyses.

This sampling procedure along with the sample identification scheme should insure that the right coal is obtained and processed to obtain the correct specifications for the individual needs of each combustor.

6.3.3 Sample Analysis

The samples obtained at the various points of the process are analyzed as described below.

Sample No. 1 - A representative sample of each lot of coal purchased is obtained by Dravo and submitted for the following analyses:

- Proximate Analysis
- Ultimate Analysis
- Ash Fusion Temperatures
- Ash Chemistry
- Hardgrove Grindability
- Free Swelling Index

Sample No. 2 - Hourly samples taken for ash analysis during the cleaning process as a means of process control.

Sample No. 3 - This sample is taken for analysis by the slurry manufacturer, in this case, OXCE Fuel Company. They carry out and report the following analyses:

- % Solids
- Density
- pH
- Particle Size Distribution
- Viscosity as a Function of Shear Rate
- Temperature Stability

Sample No. 4 - A sample of the slurry is sent to Energy International where a rapid analysis is carried out to confirm the analysis furnished by OXCE. In addition, a long-term (two month) storage stability test is carried out. This consists of determining the amount and quality (hard pack, soft pack, etc.) of any settlement occurring in the slurry. The other slurry analyses performed by EI are:

- % Solids
- Density
- pH
- Screen Analysis
- Particle Size Distribution
- Viscosities at 100 and 200 sec⁻¹ and 70°F

FIGURE 6.3.1

Sample Identification Scheme

Table 6.3.1

Coal Bed Abbreviation

<u>Abbreviation</u>	<u>Coal Name</u>
UE1	Upper Elkhorn #1
UE2	Upper Elkhorn #2
UE3	Upper Elkhorn #3
LEL	Lower Elkhorn
CBD	Coal Basin D
ELC	Elk Creek
LBT	Lower Bakerstown
UFR	Upper Freeport
UBN	Upper Banner
WYD	Wyodak
CBE	Coal Basin E
BLC	Black Creek
ANW	Anderson Wyodak
LR3	Laramie #3
2GS	#2 Gas
BZP	Beulah-Zap
ADA	Adaville

Table 6.3.2

Coal or Fuel Form

<u>Abbreviation</u>	<u>Meaning</u>
ROM	Run of Mine
WRM	Washed ROM
PCO	Pulverized Coal
DCC	Deep Cleaned Coal
MCO	Micronized Coal
CWF	Standard Grind Coal-Water Fuel
MCW	Micronized Grind Coal-Water Fuel

Table 6.3.3

Sample Origin

<u>Abbreviation</u>	<u>Meaning</u>
A	Coal supplier
B	Beneficiator
C	Size Reduction Firm
D	Dravo
E	Energy International
F	OXCE Fuel Company
G	AMAX
N	University of North Dakota Energy Research Center (UNDERC)
P	Penn Rilton - Pulverizer
S	Schutz-O'Neill - Micronizer

FIGURE 6.3.2

SAMPLING SCHEME

(#) SAMPLING POINTS

Sample No. 5 - A sample of the micronized coal is obtained from the pulverizer by Dravo. If the fuel was prepared from a deeply cleaned coal then a sample is submitted for the following analyses:

- Proximate
- Ultimate
- Ash Fusion Temperature
- Ash Chemistry
- Particle Size Distribution
- Free Swelling Index

If the coal is a washed run-of-mine coal, (i.e., not deep cleaned) then only a particle size distribution analyses is carried out. The parent coal analyses will suffice for the fuel analysis.

Sample No. 6 - If the coal used in the fuel was deep cleaned, a sample of the slurry received by Energy International is sent to Dravo for isolation of the coal and its analysis. The analyses carried out by Dravo are:

- Proximate
- Ultimate
- Ash Fusion Temperature
- Ash Chemistry
- Free Swelling Index

As before, if washed run-of-mine coal was used for the fuel preparation then the parent coal analyses is sufficient for the fuel analysis.

6.3.4 Data Logging

All the analytical data obtained on all coals and fuels are sent to Energy International. A data sheet is then compiled for each sample. Examples of the data sheets and the information contained therein are shown in Figures 6.3.3, 6.3.4 and 6.3.5. Figure 6.3.3 is the data sheet for the coal samples and Figure 6.3.4 and 6.3.5 for the slurry fuels and the solid micronized (or pulverized) coals respectively. The data sheets prepared for all samples shipped thus far are given in Appendix 8.1.

6.3.5 Sample Shipping Log

Finally, a master log of all sample shipments is kept. The log identifies each shipment by its sample identification number, the date and amount shipped, from and to whom shipped, along with Energy International's purchase order number covering the transaction. The current sample shipping log is shown in Appendix 8.2. This format, which is updated weekly, allows the Manager to determine the sample shipment status at a glance and prevents the assignment of the same serial number to two different samples.

7.0 FUTURE PLANS

During the next quarter the washability and characterization of the five candidate coals will be completed and washability curves prepared. Coal cleaning, fuel preparation and fuel shipment will be carried out to meet the needs of the combustor contractors.

Planned deliveries of specific fuels are shown in Table 7.1, "Schedule for Deliveries of Coals" and Table 7.2, "Schedule for Deliveries of Coal Water Slurries". Quantities for future years are estimates which will be confirmed approximately three to four months prior to production.

Table 7.1

SCHEDULE OF DELIVERIES OF COAL
(Including quantity and properties)

BMS/7-30-87
fillercoal/230

				FY 87		FY 88				FY 89	
CONSTRUCTION CONTRACTOR (Application)	COAL PROPERTIES	Notes	Actual deliveries	JULY	AUGUST	SEPT	FIRST QTR	SECOND QTR	THIRD QTR	FOURTH QTR	12 months
AVCO Research Lab 8 (residential)	lignite < 0.5% ash 0.3-5 10,000 Btu/lb 35 micron topsize	letter Feb 9 specs; schedule revised June 25					2000 lbs.				
COMBUSTION ENGINEERING 8 (industrial)	dry micronized (61 ash UES Coal)	still awaiting specs & schedule Sorbent add'n 1.8L/hr during injection.						70 tons same coal as CMF			
ENERGY & ENVIRONMENTAL RESEARCH, Inc. 8 (residential)	bituminous 40u topsize +2700 ash fus. temp. 5 (0.5 UES & UE2)	UE2-128-MCD-C June 8 250 lbs. UE3-133-MCD-C June 24 250 lbs.									
ATCI (residential)	< 1% ash dry micronized	UE3-123-MCD-C July 22, 5412 lbs.	6000 lbs < 30u					2000 lbs < 30u 20000 lb C30u M.J.			
(industrial)	< 1% ash dry pulverized	UE3-113-PD-C May 12, 2000 lbs. UE3-135-PD-C July 16, 6000 lbs.	4000 lbs < 149u					2000 lbs < 149u 20000 lb C149u M.J.			
NAVY/CATHOLIC UNIVERSITY (residential)		still awaiting specs & schedule for 2 programs									
PEIC IN-HOUSE 8 (GILBERT/COMMERCIAL TH) (industrial boiler)	low 2 ash micronized bituminous	UE2-114-MCD-C May 4, 5 tons UE3-126-MCD-C June 11, 5 tons UE2-125-MCD-C June 24, 5 tons	25 tons C1.5% ash				10 tons C1.5% ash	10 tons C1.5% ash	10 tons C1.5% ash	10 tons C1.5% ash	
Science Applications IC 8 (wet oxidation)	lignite-subbituminous PC, M2 inerted		1 ton lignite 80% C200mesh								
TRW (sorbent, indust'l)		still awaiting specs & schedule									
UTS (expect contract in Aug)	subbitum's low ash < 60mesh bituminous < 1% ash (400 mesh	letter April 16 specs & schedule									
Vortex (sub REEL) 8 (industrial)	1 to 8% ash, pulverized 1 bitum. coals, 5-10% iron 70% -200mesh										

Note: 8 means "under contract"

Table 7.2

SCHEDULE OF DELIVERIES OF COAL WATER SLURRIES
(including quantity and properties as 7-30-87)

RMS 7-30-87
fil:slurry720

COMBUSTION CONTRACTOR (Application)	COAL WATER SLURRY PROPERTIES	Notes	ACTUAL DELIVERIES	FY 87				FY 88				12 months	
				JULY	AUGUST	SEPT	FIRST QTR	SECOND QTR	THIRD QTR	FOURTH QTR			
AVCO (residential)	lignite, WMSZ, 302M20 <12 ash, 0.315, 41 AFT 10000 Btu, FCA5Z, 70Z solids, low vis, top 10u revised Jun 23	specs & schedule per letter Feb 9						2000 lbs.					
COMBUSTION ENGINEERING & (industrial retro)	3 to 42 ash, 150u 2800 AFT, .72 S, 574 FC & spec June 22 13500Btu; 341Z solids 3302VM, 2.25Z	revised schedule & spec June 22			7500 gal MC 99Z 40u 1100 gal std grind CMF 149 4	7500g 3-42ASH <45u	15,000gal						20,000gal
ENERGY & ENVIRONMENTAL RESEARCH, Inc. & (residential)	70Z solids, 5u NP9 40u top, vis 1000cp 11 ash, 0.5 S, 45Z VM	per ltr Apr 3	UE3-116-UCB-F, Jun 18, 55 gal			100g							
HTCI (residential)	<12 ash micronized 10u NP9, 30u topsize		UE3-116-UCB-F, Jun 18, 220 gal					2000 lb <30u top 10u NP9					
(industrial)	<12 ash, micronized 10u NP9, 30u topsize		UE3-121-UCB-F, Jun 29, 600 gal						30,000 lb 10u NP9 in MJ				
(residential)	<12 ash, pulverized 30u NP9 149u topsize		UE3-120-CMF-F, July 27, 600 gal					2000lbs 30u NP9					
(industrial)	<12 ash, pulverized 30u NP9 149u topsize								30,000 lb <30u in MJ				
MAV/CATHOLIC UNIVERSITY (commercial)	70Z solids, <2000cps 2)50 recip sec ultrafine coal	still awaiting specs & schedule											
PETC IH-HOUSE (GILBERT/COMMUNALTH)	eastern bituminous <0.61 S, >50Z solids & 500-700cp commercial boilers/ 100Z-100 ash		ELC-108-CMF-F, April 16, 350 gal UE3-117-CMF-F, May 27, 2000 gal	2000g <1.5Z ash				2000g 5-10Zash					2000g 5-10Zash
TECOEN & (residential)	>55Z solids, <12 ash <125, 5u NP9, 20u topsize >2350 AFT	letter 4-29-87 only CMF	UE3-116-UCB-F, Jun 18, 55gal		500 gal	1000 gal		1500 gal	1000 gal				1000 gal
TOW (industrial) (land-sewer contract)		still awaiting specs & schedule											
Univ. Tenn. Space Inst. (industrial)		still awaiting specs & schedule											
Vertec (ash BCR)	1 to 8Z ash	slurry next year											1000 gallons

(-----est. 10-100 TMS 77
<40u topsize, 100Z-400 mesh (38u)

B.O APPENDICES

8.1 SAMPLE DATA SHEETS

file:coalid
09/03/87

Sample Identification No.: UE2-089-WRM-A

No.: 089

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #2
Bed No.: 154
Local Name: Lower Cedar Grove
Mining Co.: Central Coal Co.
Mine Name: V.E. Mine No. 1085
Wash Plant:
State:
County:
Amount: 11 tons
Date Shpd: 2/18/87 to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

ASH FUSION TEMP.: REDUCING

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX:

HARDGROVE GRINDABILITY:

Comment: Coal originally shipped to
micronizer but found to be
off spec. So was shipped to
Dravo. They screened it to
produce UE2-124-WRM-D

B/A Ratio:

T-250 TEMP. deg. F

file:coalid'
09/03/87

Sample Identification No.: LEL-090-WRM-A

No.:090

SAMPLE INFORMATION

Bed Name: Lower Elkhorn
Bed No.: 168
Local Name:Pond Creek
Mining Co.:MAPCO Coal Co.
Mine Name: Pontiki
Wash Plant:Pontiki
State: Kentucky
County: Martin
Amount: 2 drums
Date Shpd: to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 35.12 %
Fixed Carbon 57.98 %
Ash 6.90 %
Sulfur 0.57 %
Btu/lb 13763

ULTIMATE ANALYSIS

Carbon 75.46 %
Hydrogen 4.81 %
Nitrogen 1.63 %

ASH CHEMISTRY

SiO2 51.03 %
Al2O3 30.81 %
TiO2 2.18 %
Fe2O3 6.32 %
CaO 2.92 %
MgO 0.88 %
K2O 2.22 %
Na2O 0.69 %
SO3 2.54 %
P2O5 0.07 %
SrO 0.19 %
BaO 0.15 %
Mn3O4 0.00 %
B/A Ratio: 0.16
T-250 TEMP. 2832 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2560 deg. F
Softening 2670 deg. F
Fluid 2760 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 44

file:coalid
09/03/87

Sample Identification No.: LEL-091-WRM-D

No.:091

SAMPLE INFORMATION

Bed Name: Lower Elkhorn
Bed No.: 168
Local Name:Pond Creek
Mining Co.:MAPCO Coal Co.
Mine Name: Pontiki
Wash Plant:Pontiki
State: Kentucky
County: Martin
Amount: 5 gal bucket, 1/8"x0
Date Shpd: from Dravo to EI

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 35.12 %
Fixed Carbon 57.98 %
Ash 6.90 %
Sulfur 0.57 %
Btu/lb 13763

ULTIMATE ANALYSIS

Carbon 75.46 %
Hydrogen 4.81 %
Nitrogen 1.63 %

ASH CHEMISTRY

SiO2 51.03 %
Al2O3 30.81 %
TiO2 2.18 %
Fe2O3 6.32 %
CaO 2.92 %
MgO 0.88 %
K2O 2.22 %
Na2O 0.69 %
SO3 2.54 %
P2O5 0.07 %
SrO 0.19 %
BaO 0.15 %
Mn3O4 0.00 %
B/A Ratio: 0.16
T-250 TEMP. 2832 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2560 deg. F
Softening 2670 deg. F
Fluid 2760 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 44

file:coalid'
09/03/87

Sample Identification No.: CBD-092-WRM-A

No.: 092

SAMPLE INFORMATION

Bed Name: Coal Basin D
Bed No.: 756
Local Name:
Mining Co.: Westmoreland Coal Co.
Mine Name: Orchard Valley
Wash Plant:
State: Colorado
County: Delta
Amount: 2 drums
Date Shpd: to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 39.60 %
Fixed Carbon 53.80 %
Ash 6.60 %
Sulfur 0.53 %
Btu/lb 12945

ULTIMATE ANALYSIS

Carbon 72.8 %
Hydrogen 4.78 %
Nitrogen 1.68 %

ASH CHEMISTRY

SiO2 61.95 %
Al2O3 21.21 %
TiO2 0.82 %
Fe2O3 5.47 %
CaO 2.39 %
MgO 1.06 %
K2O 1.34 %
Na2O 3.12 %
SO3 1.29 %
P2O5 0.69 %
SrO 0.22 %
BaO 0.29 %
Mn3O4 0.00 %

B/A Ratio: 0.16

T-250 TEMP. >2900 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2200 deg. F
Softening 2310 deg. F
Fluid 2440 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 51

file:coalid'
09/03/87

Sample Identification No.: CBD-093-WRM-D

No.:093

SAMPLE INFORMATION

Bed Name: Coal Basin D
Bed No.: 756
Local Name:
Mining Co.:Westmoreland Coal Co.
Mine Name: Orchard Valley
Wash Plant:
State: Colorado
County: Delta
Amount: 5 gal bucket, 1/8x0
Date Shpd: from Dravo to EI

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 39.60 %
Fixed Carbon 53.80 %
Ash 6.60 %
Sulfur 0.53 %
Btu/lb 12945

ULTIMATE ANALYSIS

Carbon 72.8 %
Hydrogen 4.78 %
Nitrogen 1.68 %

ASH CHEMISTRY

SiO2 61.95 %
Al2O3 21.21 %
TiO2 0.82 %
Fe2O3 5.47 %
CaO 2.39 %
MgO 1.06 %
K2O 1.34 %
Na2O 3.12 %
SO3 1.29 %
P2O5 0.69 %
SrO 0.22 %
BaO 0.29 %
Mn3O4 0.00 %

B/A Ratio: 0.16

T-250 TEMP. >2900 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2200 deg. F
Softening 2310 deg. F
Fluid 2440 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 51

file:coalid'
09/03/87

Sample Identification No.: UE2-094-WRM-A

No.: 094

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #2
Bed No.: 154
Local Name: Lower Cedar Grove
Mining Co.: Central Coal Co.
Mine Name: V.E. Mine No. 1085
Wash Plant:
State:
County:
Amount: 11 tons
Date Shpd:

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 35.00 %
Fixed Carbon 62.93 %
Ash 2.07 %
Sulfur 0.58 %
Btu/lb 15015

ULTIMATE ANALYSIS

Carbon 83.82 %
Hydrogen 5.37 %
Nitrogen 1.52 %

ASH CHEMISTRY

SiO2 50.45 %
Al2O3 26.93 %
TiO2 1.71 %
Fe2O3 8.05 %
CaO 2.97 %
MgO 0.78 %
K2O 1.49 %
Na2O 2.78 %
SO3 2.27 %
P2O5 0.15 %
SrO 0.64 %
BaO 0.69 %
Mn3O4 0.06 %

B/A Ratio: 0.2

T-250 TEMP. 2715 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2300 deg. F
Softening 2425 deg. F
Fluid 2540 deg. F

FREE SWELLING INDEX: 8.0

HARDGROVE GRINDABILITY: NA

Comment: Analysis assumed to be the
the same as UE2-114-MCO-C

file:coalid'
09/03/87

Sample Identification No.: UE3-100-WRM-A

No.:100

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz
Wash Plant: Wentz
State: Virginia
County: Wise
Amount: 2 drums
Date Shpd: to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 35.97 %
Fixed Carbon 64.03 %
Ash 2.25 %
Sulfur 0.62 %
Btu/lb 14829

ULTIMATE ANALYSIS

Carbon 83.23 %
Hydrogen 5.14 %
Nitrogen 1.51 %

ASH CHEMISTRY

SiO2 45.27 %
Al2O3 30.17 %
TiO2 1.40 %
Fe2O3 13.26 %
CaO 2.56 %
MgO 1.06 %
K2O 1.82 %
Na2O 1.57 %
SO3 1.75 %
P2O5 0.14 %
SrO 0.33 %
BaO 0.24 %
Mn3O4 0.26 %

B/A Ratio: 2599

T-250 TEMP. deg. F

ASH FUSION TEMP.: REDUCING

Initial 2560 deg. F
Softening 2692 deg. F
Fluid 2700 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 58

file:coalid'
09/03/87

Sample Identification No.: UE3-101-WRM-D

No.:101

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz
Wash Plant: Wentz
State: Virginia
County: Wise
Amount: 5 gal, 1/8"x0
Date Shpd: to EI

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 35.97 %
Fixed Carbon 64.03 %
Ash 2.25 %
Sulfur 0.62 %
Btu/lb 14829

ULTIMATE ANALYSIS

Carbon 83.23 %
Hydrogen 5.14 %
Nitrogen 1.51 %

ASH CHEMISTRY

SiO2 45.27 %
Al2O3 30.17 %
TiO2 1.40 %
Fe2O3 13.26 %
CaO 2.56 %
MgO 1.06 %
K2O 1.82 %
Na2O 1.57 %
SO3 1.75 %
P2O5 0.14 %
SrO 0.33 %
BaO 0.24 %
Mn3O4 0.26 %

B/A Ratio: 2599

T-250 TEMP. deg. F

ASH FUSION TEMP.: REDUCING

Initial 2560 deg. F
Softening 2692 deg. F
Fluid 2700 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 58

file:coalid.
09/09/87

Sample Identification No.: UE -102-WRM-A

No.:102

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #1

Bed No.: 157

Local Name:Alma Seam

Mining Co.:Old Ben Coal Co.

Mine Name: Mine #20

Wash Plant:

State: West Virginia

County: Mingo

Amount: 2 drum

Date Shpd: to Dravo

PROXIMATE ANALYSIS

Moisture %

Volatile Matter 34.13 %

Fixed Carbon 59.69 %

Ash 6.18 %

Sulfur 0.83 %

Btu/lb 14381

ULTIMATE ANALYSIS

Carbon 80.79 %

Hydrogen 4.76 %

Nitrogen 1.46 %

ASH CHEMISTRY

SiO2 48.86 %

Al2O3 27.82 %

TiO2 1.50 %

Fe2O3 12.24 %

CaO 2.38 %

MgO 1.13 %

K2O 2.35 %

Na2O 0.74 %

SO3 2.40 %

P2O5 0.12 %

SrO 0.22 %

BaO 0.14 %

Mn3O4 0.00 %

B/A Ratio: 0.24

T-250 TEMP. 2640 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2350 deg. F

Softening 2470 deg. F

Fluid 2600 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 53

file:coalid
09/08/87

Sample Identification No.: UE1-103-WRM-D

No.:103

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #1

Bed No.: 157

Local Name:Alma Seam

Mining Co.:Old Ben Coal Co.

Mine Name: Mine #20

Wash Plant:

State: West Virginia

County: Mingo

Amount: 5 gal, 1/8"x0

Date Shpd: to EI

PROXIMATE ANALYSIS

Moisture %

Volatile Matter 34.13 %

Fixed Carbon 59.69 %

Ash 6.18 %

Sulfur 0.83 %

Btu/lb 14381

ULTIMATE ANALYSIS

Carbon 80.79 %

Hydrogen 4.76 %

Nitrogen 1.46 %

ASH CHEMISTRY

SiO2 48.86 %

Al2O3 27.82 %

TiO2 1.50 %

Fe2O3 12.24 %

CaO 2.38 %

MgO 1.13 %

K2O 2.35 %

Na2O 0.74 %

SO3 2.40 %

P2O5 0.12 %

SrO 0.22 %

BaO 0.14 %

Mn3O4 0.00 %

B/A Ratio: 0.24

T-250 TEMP. 2640 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2350 deg. F

Softening 2470 deg. F

Fluid 2600 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 53

file:coalid
09/08/87

Sample Identification No.: UE2-104-WRM-A

No.:104

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #2
Bed No.: 154
Local Name: Lower Cedar Grove
Mining Co.: Beth Energy
Mine Name: Damron
Wash Plant: Plant 29
State: Kentucky
County:
Amount: 2 drums
Date Shpd: to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 35.50 %
Fixed Carbon 58.98 %
Ash 5.52 %
Sulfur 0.52 %
Btu/lb 14331

ULTIMATE ANALYSIS

Carbon 80.58 %
Hydrogen 4.81 %
Nitrogen 1.49 %

ASH CHEMISTRY

SiO2 54.61 %
Al2O3 29.71 %
TiO2 1.61 %
Fe2O3 7.49 %
CaO 1.61 %
MgO 0.91 %
K2O 2.37 %
Na2O 0.29 %
SO3 0.88 %
P2O5 0.18 %
SrO 0.26 %
BaO 0.18 %
Mn3O4 0.00 %
B/A Ratio: 0.15
T-250 TEMP. 2872 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2580 deg. F
Softening 2690 deg. F
Fluid 2780 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 44

file:coalid.
09/09/87

Sample Identification No.: UE2-105-WRM-D

No.:105

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #2
Bed No.: 154
Local Name: Lower Cedar Grove
Mining Co.: Beth Energy
Mine Name: Damron
Wash Plant: Plant #29

State: Kentucky
County: Jenkins (town)
Amount: 5 gal, 1/8"x0
Date Shpd: to EI

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 35.50 %
Fixed Carbon 58.98 %
Ash 5.52 %
Sulfur 0.52 %
Btu/lb 14331

ULTIMATE ANALYSIS

Carbon 80.58 %
Hydrogen 4.81 %
Nitrogen 1.49 %

ASH CHEMISTRY

SiO2 54.61 %
Al2O3 29.71 %
TiO2 1.61 %
Fe2O3 7.49 %
CaO 1.61 %
MgO 0.91 %
K2O 2.37 %
Na2O 0.29 %
SO3 0.88 %
P2O5 0.18 %
SrO 0.26 %
BaO 0.18 %
Mn3O4 0.00 %

B/A Ratio: 0.15

T-250 TEMP. 2872 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2580 deg. F
Softening 2690 deg. F
Fluid 2780 deg. F

FREE SWELLING INDEX: NA

HARDGROVE GRINDABILITY: 44

file:coalid.
09/09/87

Sample Identification No.: UE3-106-WRM-A

No.:106

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 20 tons
Date Shpd: 4/13/87 to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

ASH FUSION TEMP.: REDUCING

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX:

HARDGROVE GRINDABILITY:

B/A Ratio:

T-250 TEMP. deg. F

file:coalid-
09/09/87

Sample Identification No.: ELC-107-WRM-F

No.:107

SAMPLE INFORMATION

Bed Name: Elk Creek Coal

Bed No.:

Local Name:

Mining Co.:

Mine Name:

Wash Plant:

State:

County:

Amount: Coal on hand at OXCE

Date Shpd:

PROXIMATE ANALYSIS

Moisture %

Volatile Matter 35.18 %

Fixed Carbon 59.34 %

Ash 5.48 %

Sulfur 0.68 %

Btu/lb 14273

ULTIMATE ANALYSIS

Carbon 80.88 %

Hydrogen 4.73 %

Nitrogen 1.45 %

ASH CHEMISTRY

SiO2 53.71 %

Al2O3 30.04 %

TiO2 1.76 %

Fe2O3 8.39 %

CaO 1.12 %

MgO 0.67 %

K2O 1.63 %

Na2O 0.67 %

SO3 0.59 %

P2O5 0.18 %

SrO 0.20 %

BaO 0.22 %

Mn3O4 0.00 %

B/A Ratio: 0.13

T-250 TEMP. 2872 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2640 deg. F

Softening 2760 deg. F

Fluid +2800 deg. F

FREE SWELLING INDEX: 8.0

HARDGROVE GRINDABILITY: NA

Comment: Coal specifications were acceptable to user although coal not a selected parent coal.

file:cwfid .

Sample Identification No.: ELC-108-CWF-F

No.:108

Sample

Description Standard OXCE slurry from Elk Creek Coal

Parent

Coal I.D.: ELC-107-WRM-F

PROXIMATE ANALYSIS

Bed Name: Elk Creek Coal

Bed No.:

Local Name:

Mining Co.:

Mine Name:

Wash Plant:

State:

County:

Moisture 30.93 %

Volatile Matter 35.18 %

Fixed Carbon 59.34 %

Ash 5.48 %

Sulfur 0.68 %

Btu/lb 14273

Btu/lb

(as Received)

ULTIMATE ANALYSIS

Carbon 80.88 %

Hydrogen 4.73 %

Nitrogen 1.45 %

ASH CHEMISTRY

SiO2 53.71 %

Al2O3 30.04 %

TiO2 1.76 %

Fe2O3 8.39 %

CaO 1.13 %

MgO 0.67 %

K2O 1.63 %

Na2O 0.67 %

SO3 0.59 %

P2O5 0.18 %

SrO 0.20 %

BaO 0.22 %

Mn3O4 0.00 %

ASH FUSION: REDUCING

Initial 2640 deg. F

Softening 2760 deg. F

Fluid >2800 deg. F

FREE SWELLING INDEX 8.0

HARDGROVE GRINDABILITY NA

Pase Acid Ratio: 0.13

T-250 TEMP. 2872 deg. F

Coal Water Fuel Analysis

% Solids = 68.03

Density = 1.28

pH = 6.90

Viscosity = 795 cps @100/sec, 70 deg F

Particle Size Analysis

Wt. % <100 mesh = 99.81

Mean Part. Size = 26.0 um

From: OXCE

Amount: 350 gal

Date: 4/16/87

To: Pittsburgh Energy Technology Center

file:coalid'
09/03/87

Sample Identification No.: UE3-109-WRM-A

No.:109

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 23 tons
Date Shpd: 5/1/87 to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

ASH FUSION TEMP.: REDUCING

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX:

HARDGROVE GRINDABILITY:

B/A Ratio:

T-250 TEMP. deg. F

file:coalid'
09/03/87

Sample Identification No.: UE3-110-WRM-A

No.:110

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Holton
Wash Plant: Holton (Bullitt) Plant
State: Virginia
County: Wise
Amount: 26 tons
Date Shpd: 5/7/87 to Dravo

PROXIMATE ANALYSIS

Moisture - %
Volatile Matter 38.00 %
Fixed Carbon 56.09 %
Ash 5.91 %
Sulfur 0.75 %
Btu/lb 14192

ULTIMATE ANALYSIS

Carbon 80.03 %
Hydrogen 4.77 %
Nitrogen 1.42 %

ASH CHEMISTRY

SiO2 49.34 %
Al2O3 31.43 %
TiO2 1.26 %
Fe2O3 8.18 %
CaO 2.75 %
MgO 0.96 %
K2O 2.47 %
Na2O 0.85 %
SO3 1.05 %
P2O5 0.24 %
SrO 0.30 %
BaO 0.24 %
Mn3O4 0.00 %

B/A Ratio: 0.81

T-250 TEMP. 2747 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2480 deg. F
Softening 2600 deg. F
Fluid 2720 deg. F

FREE SWELLING INDEX: 6.5

HARDGROVE GRINDABILITY: NA

file:coalid-
09/04/87

Sample Identification No.: UE3-111-WRM-D

No.:111

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Holton
Wash Plant: Holton (Bullitt) Plant
State: Virginia
County: Wise
Amount: 26 tons
Date Shpd: 5/11/87 to OXCE

PROXIMATE ANALYSIS

Moisture - %
Volatile Matter 38.00 %
Fixed Carbon 56.09 %
Ash 5.91 %
Sulfur 0.75 %
Btu/lb 14192

ULTIMATE ANALYSIS

Carbon 80.03 %
Hydrogen 4.77 %
Nitrogen 1.42 %

ASH CHEMISTRY

SiO2 49.34 %
Al2O3 31.43 %
TiO2 1.26 %
Fe2O3 8.18 %
CaO 2.75 %
MgO 0.96 %
K2O 2.47 %
Na2O 0.85 %
SO3 1.05 %
P2O5 0.24 %
SrO 0.30 %
BaO 0.24 %
Mn3O4 0.00 %

B/A Ratio: 0.81

T-250 TEMP. 2747 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2480 deg. F
Softening 2600 deg. F
Fluid 2720 deg. F

FREE SWELLING INDEX: 6.5

HARDGROVE GRINDABILITY: NA

file:coalid'
09/03/87

Sample Identification No.: UE3-112-DCC-D

No.:112

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant

State: Virginia

County: Wise

Amount: 2000 lbs

Date Shpd: 5/6/87 to Penn Rillton

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 35.98 %
Fixed Carbon 62.68 %
Ash 1.34 %
Sulfur 0.61 %
Btu/lb 15031

ULTIMATE ANALYSIS

Carbon 84.356 %
Hydrogen 5.14 %
Nitrogen 1.54 %

ASH CHEMISTRY

SiO2 50.27 %
Al2O3 29.57 %
TiO2 1.69 %
Fe2O3 8.02 %
CaO 2.75 %
MgO 0.68 %
K2O 1.44 %
Na2O 2.70 %
SO3 1.35 %
P2O5 0.20 %
SrO 0.58 %
BaO 0.43 %
Mn3O4 0.06 %

B/A Ratio: 0.19

T-250 TEMP. 2720 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2200 deg. F
Softening 2330 deg. F
Fluid 2440 deg. F

FREE SWELLING INDEX: 8.5

HARDGROVE GRINDABILITY: NA

file:scfid .

Sample Identification No.: UE3-113-PCO-C

No.:113

Sample

Description Pulverized Coal Prepared by Penn Rillton

Parent

Coal I.D.: UE3-112-DCC-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz
State: Virginia
County: Wise

Moisture	0.68 %
Volatile Matter	35.98 %
Fixed Carbon	62.68 %
Ash	1.34 %
Sulfur	0.61 %
Btu/lb	15031

ULTIMATE ANALYSIS

Carbon	84.35 %
Hydrogen	5.14 %
Nitrogen	1.54 %

ASH CHEMISTRY

SiO2	50.27 %
Al2O3	29.57 %
TiO2	1.69 %
Fe2O3	8.02 %
CaO	2.75 %
MgO	0.68 %
K2O	1.44 %
Na2O	2.70 %
SO3	1.35 %
P2O5	0.20 %
SrO	0.58 %
BaO	0.43 %
Mn3O4	0.06 %

ASH FUSION: REDUCING

Initial	2200 deg. F
Softening	2330 deg. F
Fluid	2440 deg. F

FREE SWELLING INDEX 8.5

HARDGROVE GRINDABILITY NA

Base Acid Ratio: 0.19

T-250 TEMP. 2720 deg. F

Solid Coal Fuel Analysis

Particle Size Distribution

MICRO-TRAC Analysis

Mean Particle Diameter	38.8 um
%<100 mesh(149 um)	98
%<400 mesh(38 um)	60

From: Penn Rillton

Amount: 2000 lbs

Date: 5/8/87

To: Management and Technical Consultants, Inc

file:scfid

Sample Identification No.: UE2-114-MCO-C

No.: 114

Sample

Description Micronized coal prepared from as received UE2-094-WRM-A

Parent

Coal I.D.: UE2-094-WRM-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #2
Bed No.: 154
Local Name: Lower Cedar Grove
Mining Co.: Central Coal Co.
Mine Name: V.E. Mine No. 1085
Wash Plant:
State:
County:

Moisture	1.26 %
Volatile Matter	35.00 %
Fixed Carbon	62.93 %
Ash	2.07 %
Sulfur	0.58 %
Btu/lb	15015

ULTIMATE ANALYSIS

Carbon	83.82 %
Hydrogen	5.37 %
Nitrogen	1.52 %

ASH CHEMISTRY

SiO ₂	50.45 %
Al ₂ O ₃	26.93 %
TiO ₂	1.71 %
Fe ₂ O ₃	8.05 %
CaO	2.97 %
MgO	0.78 %
K ₂ O	1.49 %
Na ₂ O	2.78 %
SO ₃	2.27 %
P ₂ O ₅	0.15 %
SrO	0.64 %
BaO	0.69 %
Mn ₃ O ₄	0.06 %

ASH FUSION: REDUCING

Initial	2300 deg. F
Softening	2425 deg. F
Fluid	2540 deg. F

FREE SWELLING INDEX 8.0

HARDGROVE GRINDABILITY NA

Base Acid Ratio: 0.20

T-250 TEMP. 2715 deg. F

Solid Coal Fuel Analysis

Particle Size Distribution

MICRO-TRAC Analysis

Mean Particle Diameter	10.5 um
%<100 mesh (149 um)	100
%<400 mesh (38 um)	98

From: Particle Reduction Services

Amount: 5 ton

Date: 5/4/87

To: Pittsburgh Energy Technology Center

file:coalid'
09/03/87

Sample Identification No.: UE3-115-DCC-D

No.:115

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 24 drums
Date Shpd: 5/13/87 to OXCE

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 38.22 %
Fixed Carbon 60.43 %
Ash 1.35 %
Sulfur 0.58 %
Btu/lb 15056

ULTIMATE ANALYSIS

Carbon 84.3 %
Hydrogen 5.47 %
Nitrogen 1.44 %

ASH CHEMISTRY

SiO2 41.22 %
Al2O3 29.57 %
TiO2 2.15 %
Fe2O3 15.89 %
CaO 3.28 %
MgO 0.73 %
K2O 1.41 %
Na2O 1.57 %
SO3 1.50 %
P2O5 0.58 %
SrO 0.48 %
BaO 0.45 %
Mn3O4 0.02 %

B/A Ratio: 0.31

T-250 TEMP. 2522 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2120 deg. F
Softening 2300 deg. F
Fluid 2410 deg. F

FREE SWELLING INDEX: 8.5

HARDGROVE GRINDABILITY: NA

file:cwfid .

Sample Identification No.: UE3-116-UCW-F

No.:116

Sample

Description Ultra-fine grind coal-water fuel

Parent

Coal I.D.: UE3-115-DCC-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise

Moisture	35.15 %
Volatile Matter	38.22 %
Fixed Carbon	60.43 %
Ash	1.35 %
Sulfur	0.58 %
Btu/lb	15056
Btu/lb (as received)	9762

ULTIMATE ANALYSIS

Carbon	84.30 %
Hydrogen	5.47 %
Nitrogen	1.44 %

ASH CHEMISTRY

SiO2	41.22 %
Al2O3	29.57 %
TiO2	2.15 %
Fe2O3	15.89 %
CaO	3.28 %
MgO	0.73 %
K2O	1.41 %
Na2O	1.57 %
SO3	1.50 %
P2O5	0.58 %
SrO	0.48 %
BaO	0.45 %
Mn3O4	0.02 %

ASH FUSION: REDUCING

Initial	2120 deg. F
Softening	2300 deg. F
Fluid	2410 deg. F

FREE SWELLING INDEX 8.5

HARDGROVE GRINDABILITY NA

Base Acid Ratio: 0.31

T-250 TEMP. 2522 deg. F

Coal Water Fuel Analysis

% Solids = 65.26 Viscosity = 290 cps @100/sec, 70 deg F
Density = 1.168
pH = 6.90

Particle Size Analysis

Wt. % <+100 mesh = 99.99
Mean Part. Size = 7.70 um

From: OXCE

Amount: 6 drums Date: 6/22/87

To: EER, MTCI 1 drum each, Tecogen 4 drums

file:cwfid .

Sample Identification No.: UE3-117-CWF-F

No.:117

Sample

Description Standard grind coal water slurry from as received coal

Parent

Coal I.D.: UE3-111-WRM-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart
Mining Co.: Westmoreland Coal Co.
Mine Name: Holton
Wash Plant: Holton (Bullitt) Plant
State: Virginia
County: Wise

Moisture 32.85 %
Volatile Matter 38.00 %
Fixed Carbon 56.09 %
Ash 5.91 %
Sulfur 0.75 %
Btu/lb 14192
Btu/lb (as Received) 9530

ULTIMATE ANALYSIS

Carbon 80.03 %
Hydrogen 4.77 %
Nitrogen 1.42 %

ASH CHEMISTRY

SiO2 49.34 %
Al2O3 31.43 %
TiO2 1.26 %
Fe2O3 8.18 %
CaO 2.75 %
MgO 0.96 %
K2O 2.47 %
Na2O 0.85 %
SO3 1.05 %
P2O5 0.24 %
SrO 0.30 %
BaO 0.24 %
Mn3O4 0.00 %

ASH FUSION: REDUCING

Initial 2480 deg. F
Softening 2600 deg. F
Fluid 2720 deg. F
FREE SWELLING INDEX 6.5

HARDGROVE GRINDABILITY NA

Base Acid Ratio: 0.81

T-250 TEMP. 2747 deg. F

Coal Water Fuel Analysis

% Solids = 68.76 Viscosity = 992 cps @100/sec, 70 deg F
Density = 1.192
pH = 6.66

Particle Size Analysis

Wt. % <100 mesh = 96.72
Mean Part. Size = 41.8 um

From: OXCE

Amount: 2000 gal Date: 5/27/87

To: Pittsburgh Energy Technology Center

file:coalid'
09/03/87

Sample Identification No.: UE3-118-WRM-A

No.:118

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 20 tons
Date Shpd: 5/22/87 to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

ASH FUSION TEMP.: REDUCING

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX:

HARDGROVE GRINDABILITY:

B/A Ratio:

T-250 TEMP. deg. F

file:coalid'
09/03/87

Sample Identification No.: UE3-119-DCC-D

No.:119

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 50 drums
Date Shpd: 5/28/87 to OXCE

PROXIMATE ANALYSIS

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

ASH FUSION TEMP.: REDUCING

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX:

HARDGROVE GRINDABILITY:

B/A Ratio:

T-250 TEMP. deg. F

file:cwfid .

Sample Identification No.: UE3-120-CWF-F

No.:120

Sample

Description Standard grind slurry from deep cleaned coal

Parent

Coal I.D.: UE3-119-DCC-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb
Btu/lb
(as Received)

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

ASH FUSION: REDUCING

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX

HARDGROVE GRINDABILITY

Base Acid Ratio:

T-250 TEMP. deg. F

Coal Water Fuel Analysis

% Solids = 68.04 Viscosity = 839 cps @100/sec, 70 deg F
Density = 1.180
pH = 6.61 Particle Size Analysis

Wt. % +100 mesh = 0.10
Mean Part. Size = 28.0 um

From: OXCE

Amount: 710 gal Date: 7/27/87

To: 600 gal MTCI, 110 gal PETC

file:cwfid .

Sample Identification No.: UE3-121-UWF-F

No.: 121

Sample

Description Ultrafine grind slurry from deep cleaned coal

Parent

Coal I.D.: UE3-119-DCC-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb
Btu/lb
(as Received)

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

ASH FUSION: REDUCING

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX

HARDGROVE GRINDABILITY

Base Acid Ratio:

T-250 TEMP. deg. F

Coal Water Fuel Analysis

% Solids = 65.61 Viscosity = 282 cps @100/sec, 70 deg F
Density = 1.163
pH = 6.86 Particle Size Analysis

Wt. % <100 mesh = 99.960
Mean Part. Size = 8.05 um

From: OXCE

Amount: 600 gal

Date: 6/23/87

To: Management and Technical Consultants

file:coalid'
09/03/87

Sample Identification No.: UE3-122-DCC-D

No.:122

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 15 drums
Date Shpd: 6/11/87 to FRS

PROXIMATE ANALYSIS

Moisture - %
Volatile Matter 36.06 %
Fixed Carbon 62.78 %
Ash 1.16 %
Sulfur 0.69 %
Btu/lb 15016

ULTIMATE ANALYSIS

Carbon 85.19 %
Hydrogen 5.14 %
Nitrogen 1.57 %

ASH CHEMISTRY

SiO2 40.30 %
Al2O3 27.80 %
TiO2 1.65 %
Fe2O3 18.30 %
CaO 3.45 %
MgO 0.77 %
K2O 1.52 %
Na2O 1.52 %
SO3 2.40 %
P2O5 1.52 %
SrO 0.48 % est.
BaO 0.45 % est.
Mn3O4 0.02 % est.

B/A Ratio: 0.37

T-250 TEMP. 2450 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2090 deg. F
Softening 2230 deg. F
Fluid 2370 deg. F

FREE SWELLING INDEX: 6.5

HARDGROVE GRINDABILITY: NA

file:scfid .

Sample Identification No.: UE3-123-MCO-C

No.:123

Sample

Description Micronized deep cleaned Upper Elkhorn #3 coal

Parent

Coal I.D.: UE3-122-DCC-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise

Moisture 1.92 %
Volatile Matter 36.06 %
Fixed Carbon 62.78 %
Ash 1.16 %
Sulfur 0.69 %
Btu/lb 15016

ULTIMATE ANALYSIS

Carbon 85.19 %
Hydrogen 5.14 %
Nitrogen 1.57 %

ASH CHEMISTRY

SiO2 40.30 %
Al2O3 27.80 %
TiO2 1.65 %
Fe2O3 18.30 %
CaO 3.45 %
MgO 0.77 %
K2O 1.52 %
Na2O 1.52 %
SO3 2.40 %
P2O5 1.52 %
SrO 0.48 % est.
BaO 0.45 % est.
Mn3O4 0.02 % est.

ASH FUSION: REDUCING

Initial 2090 deg. F
Softening 2230 deg. F
Fluid 2370 deg. F
FREE SWELLING INDEX 6.5

HARDGROVE GRINDABILITY NA

Base Acid Ratio: 0.37

T-250 TEMP. 2450 deg. F

Solid Coal Fuel Analysis

Particle Size Distribution

MICRO-TRAC Analysis

Mean Particle Diameter 7.05 um
%<100 mesh(149 um) 100
%<400 mesh(38 um) 100

From: Particle Reduction Services

Amount: 24 drs/5412 lbs

Date: 7/15/

To: Management and Technical Consultants, Inc.

file:coalid'
09/03/87

Sample Identification No.: UE2-124-WRM-D

No.:124

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #2
Bed No.: 154
Local Name: Lower Cedar Grove
Mining Co.: Central Coal Co.
Mine Name: V.E. Mine No. 1085
Wash Plant:
State:
County:
Amount: 11 tons (70 drums)
Date Shpd: 6/1/87 to PRS

PROXIMATE ANALYSIS

Moisture %
Volatile Matter 34.99 %
Fixed Carbon 63.11 %
Ash 1.90 %
Sulfur 0.67 %
Btu/lb 15038

ULTIMATE ANALYSIS

Carbon 83.18 %
Hydrogen 5.01 %
Nitrogen 1.47 %

ASH CHEMISTRY

SiO2 46.77 %
Al2O3 27.20 %
TiO2 1.60 %
Fe2O3 11.58 %
CaO 4.10 %
MgO 0.80 %
K2O 1.62 %
Na2O 3.10 %
SO3 2.42 %
P2O5 0.15 %
SrO 0.67 %
BaO 0.66 %
Mn3O4 0.05 %

B/A Ratio: 0.28

T-250 TEMP. 2570 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2150 deg. F
Softening 2330 deg. F
Fluid 2470 deg. F

FREE SWELLING INDEX: 7.5

HARDGROVE GRINDABILITY: NA

Comment: Prepared by screening
UE2-089-WRM-A

file:scfid .

Sample Identification No.: UE2-125-MCO-C

No.:125

Sample

Description Micronized coal prepared by Particle Reduction Services

Parent

Coal I.D.: UE2-124-WRM-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #2
Bed No.: 154
Local Name: Lower Cedar Grove
Mining Co.: Central Coal Company
Mine Name: V.E. Mine No. 1085
Wash Plant:
State:
County:

Moisture	1.05 %
Volatile Matter	34.99 %
Fixed Carbon	63.11 %
Ash	1.90 %
Sulfur	0.67 %
Btu/lb	15038

ULTIMATE ANALYSIS

Carbon	83.16 %
Hydrogen	5.01 %
Nitrogen	1.47 %

ASH CHEMISTRY

SiO2	46.77 %
Al2O3	27.20 %
TiO2	1.60 %
Fe2O3	11.58 %
CaO	4.10 %
MgO	0.80 %
K2O	1.62 %
Na2O	3.10 %
SO3	2.42 %
P2O5	0.15 %
SrO	0.67 %
BaO	0.66 %
MnCO4	0.05 %

ASH FUSION: REDUCING

Initial	2150 deg. F
Softening	2330 deg. F
Fluid	2470 deg. F
FREE SWELLING INDEX	7.5

HARDGROVE GRINDABILITY NA

Base Acid Ratio: 0.28

T-250 TEMP. 2570 deg. F

Solid Coal Fuel Analysis

Particle Size Distribution

MICRO-TRAC Analysis

Mean Particle Diameter	16.4 um
%<100 mesh(149 um)	100
%<400 mesh(38 um)	90

From: Particle Reduction Services

Amount: 5 ton

Date: 6/11/87

To: Pittsburgh Energy Technology Center

file:scfid .

Sample Identification No.: UE2-126-MCO-C

No.:126

Sample

Description Micronized coal from as received UE2-094-WRM-D

Parent

Coal I.D.: UE2-094-WRM-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #2
Bed No.: 154
Local Name: Lower Cedar Grove
Mining Co.: Central Coal Co.
Mine Name: Damron
Wash Plant: Plant #29
State: Kentucky
County: Jenkins (town)

Moisture	0.61 %
Volatile Matter	36.45 %
Fixed Carbon	61.53 %
Ash	2.02 %
Sulfur	0.57 %
Btu/lb	14900

ULTIMATE ANALYSIS

Carbon	83.72 %
Hydrogen	4.99 %
Nitrogen	1.42 %

ASH CHEMISTRY

SiO2	40.76 %
Al2O3	28.42 %
TiO2	1.78 %
Fe2O3	7.77 %
CaO	2.67 %
MgO	0.70 %
K2O	1.40 %
Na2O	2.92 %
SO3	1.64 %
P2O5	0.14 %
SrO	0.70 %
BaO	0.63 %
Mn3O4	0.05 %

ASH FUSION: REDUCING

Initial	2250 deg. F
Softening	2420 deg. F
Fluid	2565 deg. F

FREE SWELLING INDEX 8.0

HARDGROVE GRINDABILITY NA

Base Acid Ratio: 0.82

T-250 TEMP. 2735 deg. F

Solid Coal Fuel Analysis

Particle Size Distribution

MICRO-TRAC Analysis

Mean Particle Diameter	11.7 um
%<100 mesh(149 um)	100
%<400 mesh(38 um)	95

From: Particle Reduction Services

Amount: 5 ton

Date: 6/11/87

To: Pittsburgh Energy Technology Center

file:coalid
09/03/87

Sample Identification No.: UE3-127-WRM-A

No.:127

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 25 tons
Date Shpd: 6/3/87 to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

ASH FUSION TEMP.: REDUCING

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX:

HARDGROVE GFINDABILITY:

B/A Ratio:

T-250 TEMP. deg. F

file:scfid .

Sample Identification No.: UE2-128-MCQ-C

No.:128

Sample

Description Micronized coal prepared by Particle Reduction Services

Parent

Coal I.D.: UE2-124-WRM-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #2
Bed No.: 154
Local Name: Lower Cedar Grove
Mining Co.: Central Coal Company
Mine Name: V.E. Mine No. 1085
Wash Plant:
State:
County:

Moisture 1.05 %
Volatile Matter 34.99 %
Fixed Carbon 63.11 %
Ash 1.90 %
Sulfur 0.67 %
Btu/lb 15038

ULTIMATE ANALYSIS

Carbon 83.16 %
Hydrogen 5.01 %
Nitrogen 1.47 %

ASH CHEMISTRY

SiO2 46.77 %
Al2O3 27.20 %
TiO2 1.60 %
Fe2O3 11.58 %
CaO 4.10 %
MgO 0.80 %
K2O 1.62 %
Na2O 3.10 %
SO3 2.42 %
P2O5 0.15 %
SrO 0.67 %
BaO 0.66 %
Mn3O4 0.05 %

ASH FUSION: REDUCING

Initial 2150 deg. F
Softening 2330 deg. F
Fluid 2470 deg. F

FREE SWELLING INDEX 7.5

HARDGROVE GRINDABILITY NA

Base Acid Ratio: 0.28

T-250 TEMP. 2570 deg. F

Solid Coal Fuel Analysis

Particle Size Distribution

MICRO-TRAC Analysis

Mean Particle Diameter 16.4 um
%<100 mesh(149 um) 100
%<400 mesh(38 um) 90

From: Particle Reduction Services Amount: 55 gal Date: 6/8/87

To: Energy and Environmental Research

file:coalid.
09/03/87

Sample Identification No.: UE3-129-DCC-D

No.:129

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 13 drums
Date Shpd: 6/22/87 to PRS

PROXIMATE ANALYSIS

Moisture - %
Volatile Matter 36.06 %
Fixed Carbon 62.78 %
Ash 1.16 %
Sulfur 0.69 %
Btu/lb 15016

ULTIMATE ANALYSIS

Carbon 85.19 %
Hydrogen 5.14 %
Nitrogen 1.57 %

ASH CHEMISTRY

SiO2 40.30 %
Al2O3 27.80 %
TiO2 1.65 %
Fe2O3 18.30 %
CaO 3.45 %
MgO 0.77 %
K2O 1.52 %
Na2O 1.52 %
SO3 2.40 %
P2O5 1.52 %
SrO 0.48 % est.
BaO 0.45 % est.
Mn3O4 0.02 % est.

B/A Ratio: 0.37

T-250 TEMP. 2450 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2090 deg. F
Softening 2230 deg. F
Fluid 2370 deg. F

FREE SWELLING INDEX: 6.5

HARDGROVE GRINDABILITY: NA

file:coalid
09/03/87

Sample Identification No.: UE3-130-DCC-D

No.:130

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 47 drums/8640 lbs
Date Shpd: 7/10/87 to OXCE

PROXIMATE ANALYSIS

Moisture - %
Volatile Matter 36.06 %
Fixed Carbon 62.78 %
Ash 1.16 %
Sulfur 0.69 %
Btu/lb 15016

ULTIMATE ANALYSIS

Carbon 85.19 %
Hydrogen 5.14 %
Nitrogen 1.57 %

ASH CHEMISTRY

SiO2 40.30 %
Al2O3 27.80 %
TiO2 1.65 %
Fe2O3 18.30 %
CaO 3.45 %
MgO 0.77 %
K2O 1.52 %
Na2O 1.52 %
SO3 2.40 %
P2O5 1.52 %
SrO 0.48 % est.
BaO 0.45 % est.
Mn3O4 0.02 % est.

B/A Ratio: 0.37

T-250 TEMP. 2450 deg. F

ASH FUSION TEMP.: REDUCING

Initial 2090 deg. F
Softening 2230 deg. F
Fluid 2370 deg. F

FREE SWELLING INDEX: 6.5

HARDGROVE GRINDABILITY: NA

file:coalid-
09/03/87

Sample Identification No.: UE3-131-WRM-A

No.: 131

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 44 tons
Date Shpd: 6/26/87 to DXCE

PROXIMATE ANALYSIS

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

ASH FUSION TEMP.: REDUCING

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX:

HARDGROVE GRINDABILITY:

B/A Ratio

T-250 deg. F

file:coalid.
09/03/87

Sample Identification No.: UE3-132-WRM-A

No.:132

SAMPLE INFORMATION

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz #1
Wash Plant: Wentz Plant
State: Virginia
County: Wise
Amount: 22 tons
Date Shpd: 6/25/87 to Dravo

PROXIMATE ANALYSIS

Moisture %
Volatile Matter %
Fixed Carbon %
Ash %
Sulfur %
Btu/lb

ULTIMATE ANALYSIS

Carbon %
Hydrogen %
Nitrogen %

ASH CHEMISTRY

SiO2 %
Al2O3 %
TiO2 %
Fe2O3 %
CaO %
MgO %
K2O %
Na2O %
SO3 %
P2O5 %
SrO %
BaO %
Mn3O4 %

ASH FUSION TEMP.: REDUCING

Initial deg. F
Softening deg. F
Fluid deg. F

FREE SWELLING INDEX:

HARDGROVE GRINDABILITY:

B/A Ratio:

T-250 TEMP. deg. F

file:scfid . Sample Identification No.: UE3-133-MCO-C No.:133

Sample
Description Micronized deep cleaned coal

Parent
Coal I.D.: UE3-129-DCC-D

PROXIMATE ANALYSIS

Bed Name: Upper Elkhorn #3
Bed No.: 151
Local Name: Taggart Seam
Mining Co.: Westmoreland Coal Co.
Mine Name: Wentz
Wash Plant: Wentz Plant
State: Virginia
County: Wise

Moisture	1.92 %
Volatile Matter	36.06 %
Fixed Carbon	62.78 %
Ash	1.16 %
Sulfur	0.69 %
Btu/lb	15016

ULTIMATE ANALYSIS

Carbon	85.19 %
Hydrogen	5.14 %
Nitrogen	0.02 %

ASH CHEMISTRY

SiO2	40.30 %
Al2O3	27.80 %
TiO2	1.65 %
Fe2O3	18.30 %
CaO	3.45 %
MgO	0.77 %
K2O	1.52 %
Na2O	1.52 %
SO3	2.40 %
P2O5	1.52 %
SrO	0.48 %
BaO	0.45 %
Mn3O4	0.02 %

ASH FUSION: REDUCING

Initial	2090 deg. F
Softening	2230 deg. F
Fluid	2370 deg. F
FREE SWELLING INDEX	6.5

HARDGROVE GRINDABILITY NA

Base Acid Ratio: 0.37

T-250 TEMP. 2450 deg. F

Solid Coal Fuel Analysis

Particle Size Distribution

MICRO-TRAC Analysis

Mean Particle Diameter	7.05 um
%<100 mesh(149 um)	100
%<400 mesh(38 um)	100

From: Particle Reduction Services Amount: 225 lbs Date: 6/24/87

To: Energy and Environmental Research

8.2 SAMPLE SHIPPING LOG

Table 1

filelist4

Update: 02-Sep-87

Serial No.	Sample I.D.	Previous Sample I.D.	From	To	Quantity	Description	P.O.#	Date Shipped	Hauler
000-088	unassigned								
089	UE2-089-WRH-A	parent	Central Coal Co.	Bravo	11 tons	Off-spec, Lower Cedar Grove, Virginia Energy mine #1085	EI-125	2/19/87	
090	LEL-090-WRH-A	parent	NAPCO	Dravo	2 drums	Pond Creek Coal, Pontiki plant			
091	LEL-091-WRH-D	LEL-090-WRH-A	Dravo	E.I.	5 gal	Pond Creek Coal, Pontiki plant, 1/8x0 for washability studies			
092	CBD-092-WRH-A	parent	Westmoreland Coal	Dravo	2 drums	Colorado, Coal Bed D			
093	CBD-093-WRH-D	CBD-092-WRH-A	Dravo	E.I.	5 gal	Colorado, Coal Bed D, 1/8x0 for washability studies			
094	UE2-094-WRH-A	parent	Central Coal Co.	Dravo	11 ton	21 ash, Lower Cedar Grove, Virginia Energy mine #1085			
095	Unassigned								
096	Unassigned								
097	Unassigned								
098	Unassigned								
099	Unassigned								
100	UE3-100-WRH-A	parent	Westmoreland Coal	Dravo	2 drums	Taggart Seam			
101	UE3-101-WRH-D	UE3-100-WRH-A	Dravo	E.I.	5 gal	Taggart Seam, 1/8x0 for washability studies			
102	UE1-102-WRH-A	parent	Old Ben Coal Co.	Dravo	2 drums	Alma Seam			
103	UE1-103-WRH-D	UE1-102-WRH-A	Dravo	E.I.	5 gal	Alma Seam, 1/8x0 for washability studies			
104	UE2-104-WRH-A	parent	Beth Energy Coal Co.	Dravo	2 drums	Lower Cedar Grove			
105	UE2-105-WRH-D	UE2-104-WRH-A	Dravo	E.I.	5 gal	Lower Cedar Grove, 1/8x0 for washability studies			
106	UE3-106-WRH-A	parent	Westmoreland Coal	Dravo	20 ton	3.5X ash coal, Wentz plant, Taggart seam (1st shipment)	EI-148	4/13/87	
107	ELC-107-WRH-F	parent				Elt Creek Coal from DICE	-	-	
108	ELC-108-CMF-F	ELC-107-WRH-F	DICE	PEIC	350 gal	Std. grind slurry	EI-151	4/16/87	
109	UE3-109-WRH-A	parent	Westmoreland Coal	Dravo	23 tons	~3.5X ash, Taggart Seam, Wentz Plant	EI-162	5/1/87	
110	UE3-110-WRH-A	parent	Westmoreland Coal	Dravo	26 tons	~6X ash, Taggart Seam, Holton Plant	EI-167	5/7/87	
111	UE3-111-WRH-D	UE3-110-WRH-A	Dravo	DICE	26 tons	From UE3-110-WRH-A	EI-168	5/11/87	
112	UE3-112-DCC-D	UE3-106-WRH-A	Dravo	Penn Rilliton	2000 lbs	Deep cleaned UE3-106-WRH-A	Dravo	5/6/87	
113	UE3-113-PCD-C	UE3-112-DCC-D	Penn Rilliton	MTCI	2000 lbs	Pulverized UE3-112-DCC-D	EI-176	5/8/87	

Table 1 (Cont.)

File:1ist4a

Update: 02-Sep-87

Serial No.	Sample I.D.	Previous Sample I.D.	From	To	Quantity	Description	P.O.#	Date Shipped	Hauler
114	UE2-114-MCO-C	UE2-094-WRM-A	PRS	PETC	5 ton	Micronized UE2-094-WRM-A	EI-158	5/4/87	
115	UE3-115-DCC-D	UE3-106-WRM-A	Dravo	OICE	28 drums/5040 lbs	Filter cake from deep cleaned UE3-106-WRM-A	EI-179	5/13/87	
116	UE3-116-UCW-F	UE3-115-DCC-D	OICE	EER, MICI, Tec	6 drums	Ultrafine slurry from filter cake UE3-115-DCC-D	EI-175	6/22/87	
117	UE3-117-CMF-F	UE3-111-WRM-D	OICE	PETC	2000 gal	Std grind slurry from UE3-111-WRM-D	EI-171	5/7/87	
118	UE3-118-WRM-A	parent	Westmoreland Coal	Dravo	20 tons	3.5% ash, Taggart Seam, Wentz Plant	EI-182	5/22/87	
119	UE3-119-DCC-D	UE3-109-WRM-A	Dravo	OICE	56 drums/10865 lbs	From UE3-109-WRM-A, 1.3-1.5% ash	EI-190	5/28/87	
120	UE3-120-CMF-F	UE3-119-DCC-D	OICE	MICI/PETC	600 gal/110 gal	Std. grind slurry, 1.2% ash, from UE3-119-DCC-D	EI-191	7/27/87	
121	UE3-121-UCW-F	UE3-119-DCC-D	OICE	MICI	600 gal/11 drums	Ultrafine slurry, 1.2% ash, from UE3-119-DCC-D	EI-192	6/23/87	
122	UE3-122-DCC-D	UE3-118-WRM-A	Dravo	PRS	15 drums	Cleaned to 1.75 to 2.25% ash, from UE3-118-WRM-A	EI-202	6/11/87	
123	UE3-123-MCO-C	UE3-122-DCC-D	PRS	MICI	24 drs/5412 lbs	From UE3-122-DCC-D	EI-231	7/22/87	
124	UE2-124-WRM-D	UE2-089-WRM-A	Dravo	PRS	70 drums	From UE2-089-WRM-A	EI-194	6/1/87	
125	UE2-125-MCO-C	UE2-124-WRM-D	PRS	PETC	5 tons	From UE2-124-WRM-D	EI-211	6/24/87	
126	UE2-126-MCO-C	UE2-094-WRM-A	PRS	PETC	39 drums/9615 lbs	From UE2-094-WRM-A	EI-205	6/11/87	Five Star
127	UE3-127-WRM-A	parent	Westmoreland Coal	Dravo	25 tons	Stoker Coal, Taggart seam, 3.5% ash, Wentz plant	EI-195	6/3/87	
128	UE2-128-MCO-C	UE2-089-WRM-D	PRS	EER	55 gal drum	Air freighted (from UE2-089-WRM-D) same as UE2-126-MCO-C	Dravo	6/8/87	
129	UE3-129-DCC-D	UE3-118 & 127	Dravo	PRS	13 drums	Blend of deep cleaned UE3-118 & UE3-127	EI-211	6/22/87	
130	UE3-130-DCC-D	UE3-129-DCC-D	Dravo	OICE	47 drums/8640 lbs	1.3-1.5% ash - same as UE3-129	EI-226	7/10/87	Preston
131	UE3-131-WRM-A	parent	Westmoreland Coal	OICE	44 tons	Taggart Seam, Wentz plant	EI-212	6/26/87	Five Star
132	UE3-132-WRM-A	parent	Westmoreland Coal	Dravo	22 tons	Taggart Seam, Wentz plant	EI-212	6/25/87	Five Star
133	UE3-133-MCO-C	UE3-129-DCC-D	PRS	EER	55 gal drum	Micronized from UE3-122	Dravo	6/24/87	Amer Air
134	UE3-134-DCC-D	UE3-127/132	Dravo	Penn Rilliton	20 drums	Deep cleaned coal	EI-229	7/15/87	Carlucci
135	UE3-135-PCO-C	UE3-134-DCC-D	Penn Rilliton	MICI	20 drums	Pulverized coal	EI-232	7/16/87	Preston
136	UE3-136-WRM-A	parent	Westmoreland Coal Co.	Dravo	20 tons	Stoker Coal (3.5% ash), Taggart Seam, Wentz Plant	EI-233	7/20/87	Five Star
137	UE3-137-CMF-F	UE3-130-DCC-D	OICE	PETC	2000 gal	same spec as UE3-120-CMF-F	EI-240	8/19/87	Leaman

Table 1 (Cont.)

file: list4b

Update: 02-Sep-87

Serial No.	Sample I.D.	Previous Sample I.D.	From	To	Quantity	Description	P.O.#	Date Shipped	Hauler
138	UE3-138-CNF-F	UE3-131-WRM-A	OTCE	C-E	1200 gal		EI-238	8/28/87	
139	UE3-139-MCV-F	UE3-131-WRM-A	OTCE	C-E	7500 gal		EI-241	9/9/87	
140	LEL-140-MCO-E	LEL-091-WRM-A	EI	United Tech	one pound	Micronized "as received" Lower Elkhorn		8/3/87	US Mail
141	LEL-141-MCO-E	LEL-140-MCO-E	EI	United Tech	one pound	Deep Cleaned UE3-140-MCO-E		8/3/87	US Mail
142	UE3-142-DCC-D	UE3-132-WRM-A	Dravo	Shultz/DNeil	100 drums	Deep cleaned	EI 246	7/31/87	
143	UE3-143-MCO-C	UE3-143-DCC-D	Shultz/D'Neil	PETC	88 drums		EI 265	9/1/87	Inmay
144	UE3-144-DCC-D	UE3-132-WRM-A	Dravo	OTCE	21 drums		EI-248	8/5/87	Smith
145	UE3-145-DCC-D		Dravo	Shultz/DNeil					Preston
146	BTP-146-WRM-N	parent	UNDERC	SAIC/EI	1 ton/10 gal		UNDERC		
147	BTP-147-PCO-N	BPT-146-WRM-N	UNDERC	SAIC/EI	1 ton/5 gal	pulverized	UNDERC		
148	UE3-148-DCC-D		Dravo	Shultz/DNeil	10 ton	for 25 ton shipment of micronized coal for PETC			
149	UE3-149-WRM-A	parent	Westmoreland Coal Co.	Dravo	23 tons	Taggart Sea, Wentz plant stoker coal			
150	BTP-150-PCO-N								
151	BTP-151-CNF-N								
152									
153									
154									
155									
156									
157									
158									
159									
160									
161									

8.3 PRODUCTION LOG

DRAGO SHIPMENT DRUM LOG

DRUM #	% ASH	% MOIST	SHIP TO	DATE	WT.	SHIPMENT ID	COMMENTS
A B C	D	E	F	G	H		
4-21- 1	1.71						
4-21- 2	1.71						
4-21- 3	1.33						
4-21- 4	1.60						
4-22- 1	1.24	6.53	PENN RILTON	5-07-87	291	112	
4-22- 2	1.33	6.07	PENN RILTON	5-07-87	246	112	
4-22- 3	1.23	11.36	OYCE	7-10-87	237	130	RECORE 11.67% Moist
4-23- 1	1.27	14.46	OYCE	5-28-87	244	119	
4-23- 2	1.28	8.04	PENN RILTON	5-07-87	227	112	
4-23- 3	1.20	3.54	PENN RILTON	5-07-87	246	112	
4-23- 4	1.36	5.02	PENN RILTON	5-07-87	257	112	
4-23- 5	1.27	6.73	PENN RILTON	5-07-87	240	112	
4-23- 6	1.38	8.25	OYCE	5-28-87	228	119	
4-24- 1	1.39	20.19	OYCE	5-28-87	284	119	
4-24- 2	1.37	11.51	OYCE	5-28-87	245	119	
4-24- 3	1.33	11.13	OYCE	5-12-87		115	
4-24- 4	1.25	19.13	OYCE	5-12-87		115	
4-27- 1	1.48	13.23	OYCE	5-28-87	275	119	
4-27- 2	1.35	18.49	OYCE	5-12-87		115	
4-27- 3	1.31	18.85	OYCE	5-12-87		115	
4-27- 4	1.29	18.07	OYCE	5-12-87		115	
4-27- 5	1.33	19.97	OYCE	5-12-87		115	
4-27- 6	1.38	23.33	OYCE	5-28-87	262	119	
4-27- 7	1.27	23.74	OYCE	5-28-87	274	119	
4-27- 8	1.23	15.61	OYCE	5-12-87		115	
4-27- 9	1.26	24.40	OYCE	7-10-87	260	130	RECORE 21.37% Moist.
4-27- 10	1.19	13.20	OYCE	5-12-87		115	
4-27- 11	1.18	19.11	OYCE	5-12-87		115	
4-27- 12	1.11	21.16	OYCE	5-12-87		115	
4-27- 13	1.08	15.91	OYCE	5-12-87		115	
4-28- 1	1.12	21.67	OYCE	5-12-87		115	
4-28- 2	1.76	11.46	OYCE	5-28-87	262	119	
4-28- 3	1.19	23.66	OYCE	5-28-87	267	119	
4-28- 4	1.37	25.00	OYCE	7-10-87	231	130	RECORE 24.03% Moist. @ 1.36% ASH
4-28- 5	1.32	11.87	OYCE	5-12-87		115	
4-28- 6	1.21	11.08	OYCE	5-12-87		115	
4-28- 7	1.30	16.30	OYCE	5-28-87	260	119	
4-29- 1	1.25	22.51	OYCE	7-10-87	242	130	RECORE 21.64% Moist.
4-29- 2	1.33	12.58	OYCE	5-12-87		115	
4-29- 3	1.30	3.10	OYCE	5-12-87		115	
4-29- 4	1.17	15.62	OYCE	5-28-87	268	119	
4-29- 5	1.18	7.78	OYCE	5-12-87		115	
4-29- 6	1.23	15.34	OYCE	5-12-87		115	
4-29- 7	1.29	16.40	OYCE	5-12-87		115	
4-29- 8	1.22	28.45	OYCE	5-12-87		115	
4-29- 9	1.25	17.45	OYCE	5-12-87		115	
4-29- 10	1.26	14.04	OYCE	5-28-87	269	119	
4-29- 11	1.20	13.46	OYCE	5-12-87		115	
4-29- 12	1.16	12.58	OYCE	7-10-87	218	130	REDRY 7.63% Moist. @ 1.18% ASH
4-29- 13	1.26	16.17	OYCE	5-28-87	280	119	
4-30- 1	1.22	18.49	OYCE	7-10-87	247	130	RECORE 14.82% Moist. @ 1.35% ASH

DRAVO SHIPMENT DRUM LOG

DRUM #	% ASH	% MOIST	SHIP TO	DATE	WT.	SHIPMENT ID
4-30- 2	1.35	16.27	OXCE	5-28-87	250	119
4-30- 3	1.34	7.27	OXCE	5-12-87		115
4-30- 4	1.31	7.68	PENN RILTON	5-07-87	250	112
4-30- 5	1.75	6.97	PENN RILTON	5-07-87	220	112
4-30- 6	1.32	5.27	PENN RILTON	5-07-87	226	112
4-30- 7	1.51	11.29	OXCE	5-28-87	269	119
4-30- 8	1.39	10.22	OXCE	5-28-87	229	119
4-30- 9	1.28	20.14	OXCE	5-28-87	258	119
4-30- 10	1.33	4.53	PENN RILTON	5-07-87	241	112
4-30- 11	1.33	2.19	OXCE	5-28-87	256	119
4-30- 12	1.25	4.71	OXCE	5-12-87		115
5-01- 1	1.34	6.81	OXCE	5-28-87	255	119
5-01- 2	1.42	18.50	OXCE	5-28-87	263	119
5-01- 3	1.37	1.36	OXCE	5-28-87	234	119
5-01- 4	1.57	10.82				REDRY 7.07% Moist @
5-01- 5	1.40	12.31	OXCE	5-28-87	266	119
5-01- 6	1.27	13.07	OXCE	5-28-87	228	119
5-01- 7	1.25	19.19	OXCE	5-12-87		115
5-01- 8	1.33	17.75	OXCE	5-12-87		115
5-01- 9	1.15	0.63	OXCE	5-28-87	246	119
5-01- 10	1.23	9.46	OXCE	5-28-87	252	119
5-04- 1	1.24	4.75	OXCE	5-28-87	236	119
5-04- 2	1.23	4.78	OXCE	5-28-87	247	119
5-04- 3	1.29	8.36	OXCE	5-28-87	272	119
5-04- 4	1.38	19.89	OXCE	5-28-87	253	119
5-04- 5	1.30	12.08	SCHUTZ O'	8-14-87	252	145
5-04- 6	1.32	14.92	OXCE	5-28-87	296	119
5-04- 7	1.31	4.84	OXCE	5-28-87	274	119
5-04- 8	1.36	0.86	PENN RILTON	7-14-87	247	134
5-04- 9	1.35	16.98	OXCE	5-28-87	298	119
5-04- 10	1.28	10.44	OXCE	5-12-87		115
5-04- 11	1.26	19.15	OXCE	5-12-87		115
5-05- 1	1.13	18.76	OXCE	5-28-87	279	119
5-05- 2	1.42	17.94	OXCE	5-28-87	274	119
5-05- 3	1.37	15.26	OXCE	5-28-87	271	119
5-05- 4	1.33	12.25	OXCE	5-28-87	320	119
5-05- 5	1.41	14.91	OXCE	5-28-87	260	119
5-05- 6	1.34	14.56	OXCE	5-28-87	263	119
5-05- 7	2.00	14.33				RECORE 12.70 % Moist
5-05- 8	2.46	15.21				
5-05- 9	2.50	3.15				
5-05- 10	1.61	14.09				
5-06- 1	1.72	12.56				
5-06- 2	1.88	13.22				
5-11- 1	1.61	3.83				
5-11- 2	1.58	17.99				
5-12- 1	1.48	4.69				
5-12- 2	1.73	9.91				
5-12- 3	1.62	9.76				
5-12- 4	1.65	10.97				
5-12- 5	1.66	4.93				

DRAVO SHIPMENT DRUM LOG

DRUM #	% ASH	% MOIST	SHIP TO	DATE	WT.	SHIPMENT ID
5-12- 6	1.37	11.93				
5-12- 7	1.37	8.89 OXCE		5-28-87	286	119
5-12- 8	1.38	13.26 OXCE		5-28-87	311	119
5-12- 9	1.32	18.04 OXCE		5-28-87	263	119
5-12- 10	1.32	11.12 OXCE		5-28-87	257	119
5-13- 1	1.42	10.91 OXCE		5-28-87	300	119
5-13- 2	1.34	8.58 OXCE		5-28-87	259	119
5-13- 3	1.44	14.53 OXCE		5-28-87	266	119
5-13- 4	1.37	5.40 OXCE		5-28-87	240	119
5-13- 5	1.34	16.40 OXCE		5-28-87	271	119
5-13- 6	1.33	15.30 OXCE		5-28-87	286	119
5-13- 7	1.34	12.82 OXCE		7-10-87	269	130
5-13- 8	1.29	15.17 OXCE		5-28-87	286	119
5-13- 9*	1.33	5.75 OXCE?		5-28-87	252	119?129
5-14- 1	1.36	1.20 PRS		6-22-87	243	129
5-14- 2	1.48	1.78 SHUTZ 0'		7-31-87	258	142 RECORE 2.37% Moist @ 1.49% Ash
5-14- 3	1.40	3.86 SHUTZ 0'		7-31-87	235	142 RECORE 1.93% Moist @ 1.41% Ash
5-14- 4	1.37	1.05 PRS		6-22-87	241	129
5-14- 5	1.18	4.93 PRS		6-22-87	243	129
5-15- 1	1.24	15.10 OXCE		7-10-87	228	130
5-15- 2	1.35	6.44 PRS		6-22-87	240	129
5-15- 3	1.39	18.58 OXCE		7-10-87	264	130
5-15- 4	1.38	15.60 OXCE		7-10-87	268	130
5-15- 5	1.39	15.93 OXCE		7-10-87	267	130 RECORE 12.17% Moist @ 1.28% Ash
5-15- 6	1.32	18.42 OXCE		5-28-87	281	119
5-15- 7	1.31	12.04 OXCE		5-28-87	266	119
5-15- 8	1.35	13.37 OXCE		5-28-87	244	119
5-15- 9	1.48	10.93 OXCE		5-28-87	246	119
5-15- 10	1.57	11.09				
5-15- 11	1.53	17.22				
5-15- 12	1.50	15.03 OXCE		8-05-87	254	144
5-18- 1	1.29	15.51 OXCE		5-28-87	248	119
5-18- 2	1.41	PENN RILTON		7-15-87	226	134 RECORE 0.76% Moist @ 1.31% Ash
5-18- 3	1.28	11.92 OXCE		7-10-87	245	130
5-18- 4	1.37	0.89 PRS		6-22-87	?	129
5-18- 5	1.54	8.50				
5-18- 6	1.48	4.72 OXCE		8-05-87	246	144
5-18- 7	1.46	14.22 OXCE		7-10-87	265	130
5-18- 8	1.44	7.97 OXCE		7-10-87	245	130
5-18- 9	1.45	11.49 OXCE		7-10-87	243	130
5-18- 10	1.40	17.87 OXCE		5-28-87	267	119
5-18- 11	1.29	SCHUTZ 0'		8-14-87	249	145 RECORE 10.07% Moist @ 1.41% Ash REDRY 0.19% @ 1.36% ASH
5-18- 12	1.50	14.76				
5-19- 1	1.34	16.95 OXCE		7-10-87	233	130
5-19- 2	1.29	10.84 OXCE		7-10-87	213	130
5-19- 3	1.44	11.74 OXCE		7-10-87	270	130
5-19- 4	1.43	13.05 OXCE		7-10-87	205	130
5-19- 5	1.43	16.35 OXCE		7-10-87	246	130
5-19- 6	1.47	16.41 OXCE		7-10-87	284	130
5-19- 7	1.25	18.08 OXCE		7-10-87	199	130
5-19- 8	1.26	13.19 OXCE		7-10-87	210	130

DRAVO SHIPMENT DRUM LOG

DRUM #	% ASH	% MOIST	SHIP TO	DATE	WT.	SHIPMENT ID	
5-20- 1	1.52	11.60					
5-20- 2	1.48	7.31					
5-20- 3	1.52	19.41					
5-20- 4	1.54	15.28					
5-20- 5	1.43	14.59	OYCE	7-10-87	237	130	
5-20- 6	1.43	14.32	OYCE	7-10-87	247	130	
5-20- 7	1.37	12.55	OYCE	7-10-87	240	130	
5-20- 8	1.34	17.95	OYCE	7-10-87	275	130	
5-20- 9	1.38	11.86	OYCE	7-10-87	230	130	
5-20- 10	1.36	15.79	OYCE	7-10-87	243	130	
5-20- 11	1.38	10.84	OYCE	7-10-87	265	130	
5-20- 12	1.40	8.93	OYCE	7-10-87	260	130	
5-20- 13							
5-21- 1	1.56	5.70					
5-21- 2	1.48	0.48	PENN RILTON	7-15-87	211	134	RECORE 0.48% MOIST @ 1.54% ASH
5-21- 3	1.49	3.06	SCHUTZ 0'	7-31-87	268	142	
5-21- 4	1.47	3.48	SCHUTZ 0'	7-31-87	245	142	
5-21- 5	1.39	6.15	SCHUTZ 0'	8-14-87	230	145	REDRIED 4.68% MOIST @ 1.34% ASH
5-21- 6	1.26	7.18	PRS	6-02-87	258	122	
5-21- 7	1.24	4.22	PRS	6-02-87	241	122	
5-21- 8	1.48	17.39	OYCE	7-10-87	221	130	
5-21- 9	1.29	11.30	OYCE	7-10-87	230	130	
5-21- 10	1.29	15.82	OYCE	7-10-87	279	130	
5-21- 11	1.26	13.95	OYCE	7-10-87	250	130	
5-22- 1	1.56		PENN RILTON	7-15-87	265	134	RECORE 2.55% MOIST @ 1.21% ASH
5-22- 2	1.39	1.56	PRS	6-02-87	259	122	
5-22- 3	1.32	16.89	OYCE	7-10-87	278	130	
5-22- 4	1.22	12.31	OYCE	7-10-87	277	130	
5-22- 5	1.25	7.53	PRS	6-02-87	233	122	
5-22- 6	1.14	8.95	OYCE	7-10-87	238	130	
5-22- 7	1.18	2.62	PRS	6-02-87	296	122	
5-22- 8	1.26	4.35	PRS	6-22-87	272	129	
5-22- 9	1.23	4.20	PRS	6-22-87	?	129	
5-22- 10	1.15	13.56	OYCE	7-10-87	265	130	
5-27- 1	1.39	0.64	PRS	6-02-87	257	122	
5-27- 2	1.22	9.61	OYCE	7-10-87	235	130	
5-27- 3	1.31	3.95	PRS	6-02-87	224	122	
5-27- 4	1.23	0.22	PRS	6-02-87	243	122	
5-27- 5	1.26	10.68	OYCE	7-10-87	221	130	
5-27- 6	1.23	6.19	PRS	6-22-87	236	129	
5-27- 7	1.24	8.21	PRS	6-02-87	240	122	
5-28- 1	1.23	6.91	PRS	6-02-87	239	122	
5-28- 2	1.26	6.32	PRS	6-02-87	253	122	
5-28- 3	1.25					1	
5-28- 4	1.23		PRS	6-02-87	270	122	
5-28- 5	1.13	9.82	OYCE	7-10-87	258	130	
5-28- 6	1.16	2.50	PRS	6-02-87	251	122	
5-28- 7	1.20	0.71	PRS	6-02-87	243	122	
5-28- 8	1.22	4.35	PRS	6-02-87	236	122	
5-28- 9	1.26	8.35	OYCE	7-10-87	275	130	
6-09- 1	1.46	1.94	SCHUTZ 0'	7-31-87	248	142	

DRAVO SHIPMENT DRUM LOG

DRUM #	% ASH	% MOIST	SHIP TO	DATE	WT.	SHIPMENT ID	
6-09- 2	1.49	2.61	SCHUTZ O'	7-31-87	201	142	
6-09- 3	1.51	3.35	SCHUTZ O'	8-14-87	??	145	
6-09- 4	1.53	8.45					
6-10- 1	1.47		SCHUTZ O'	7-31-87	255	142	RECORE 3.78% MOIST
6-10- 2	1.31	3.63	PENN RILTON	7-15-87	226	134	
6-10- 3	1.29	2.51	PRS	6-22-87	193	129	
6-11- 1	1.27	**				1	IGNITION
6-11- 2	1.26	1.03				1	MISSING
6-11- 3	1.33	**				1	IGNITION
6-11- 4	1.35		PENN RILTON	7-15-87	247	134	RECORE 1.08% MOIST @ 1.42% ASH
6-12- 1	1.35	1.71	SCHUTZ O'	7-31-87	238	142	
6-12- 2	1.45	1.94	SCHUTZ O'	7-31-87	233	142	
6-12- 3	1.44	2.34	SCHUTZ O'	7-31-87	255	142	
6-12- 4	1.43	2.48	PENN RILTON	7-15-87	248	134	
6-12- 5	1.44	5.17	PENN RILTON	7-15-87	239	134	
6-15- 1	1.38	9.27	OXCE	7-10-87	250	130	REDRIED 2.49% MOIST @ 1.28% ASH
6-15- 2	1.44	5.25	SCHUTZ O'	8-14-87	273	145	REDRIED 2.90% MOIST @ 1.55% ASH
6-15- 3	1.62	3.62					
6-15- 4	1.34	12.89	OXCE	7-10-87	235	130	
6-15- 5	1.32	12.02	OXCE	7-10-87	244	130	
6-15- 6	1.28	2.06	PRS	6-22-87	233	129	
6-16- 1	1.49						SAMPLE 1695 9.64% MOIST @ 1.72 % ASH
6-16- 2*	1.26	5.04	PRS	6-22-87	255	129	
6-16- 3	1.50	4.27	SCHUTZ O'	7-31-87	236	142	
6-16- 4	1.21	2.76	PRS	6-22-87	205	129	
6-16- 5	1.21	7.59	PRS	6-22-87	218	129	
6-17- 1	1.16	6.59	PRS	6-22-87	246	129	
6-17- 2	1.29						RECORE 6.21% MOIST @ 1.38% ASH ALSO 8.29% M @ 1.25% ASH
6-17- 3	1.24	13.46					REDRIED 2.90% MOIST
6-17- 4	1.49	6.28	OXCE	8-05-87	227	144	REDRIED 0.75% MOIST @ 1.35% ASH
6-17- 5	1.44		SCHUTZ O'	7-31-87	254	142	RECORED 1.11% MOIST @ 1.45% ASH
6-17- 6	1.35		SCHUTZ O'	7-31-87	258	142	RECORED 1.08% MOIST @ 1.39% ASH
6-17- 7	1.32		SCHUTZ O'	8-14-87	221	145	RECORED 12.57%M @ 1.14% ASH
6-17- 8	1.21	9.98	SCHUTZ O'	8-14-87	192	145	SAMPLE 1694 15.27% MOIST @ 1.85% ASH
6-19- 1	1.29					1	MISSING
6-19- 2	1.29					1	MISSING
6-19- 3	1.28					1	MISSING
6-19- 4	1.19	1.03	PENN RILTON	7-15-87	243	134	
6-19- 5	1.11	1.15	PENN RILTON	7-15-87	255	134	
6-19- 6	1.14	1.31	PENN RILTON	7-15-87	212	134	
6-19- 7	1.05	1.69	PENN RILTON	7-15-87	228	134	
6-19- 8	1.05	1.94	PENN RILTON	7-15-87	217	134	EXTRA ANALYSIS 1.74% MOIST
6-19- 9	1.21		PENN RILTON	7-15-87	239	134	RECORED 1.89% MOIST @ 1.31% ASH
6-22- 1							
6-24- 1	1.40	3.04	SCHUTZ O'	7-31-87	266	142	
6-24- 2	1.52	0.15	SCHUTZ O'	7-31-87	240	142	
6-24- 3	1.42		SCHUTZ O'	8-14-87	268	145	RECORED 0.23% MOIST @ 1.52% ASH
6-24- 4	1.83						RECORED 0.11%M @ 1.68% ASH
6-24- 5	1.69	0.68					
6-24- 6	1.74	3.22					
6-24- 7	1.69	5.54					

DRAGO SHIPMENT DRUM LOG

DRUM #	% ASH	% MOIST	SHIP TO	DATE	WT.	SHIPMENT ID	
6-24- 8							
6-25- 1	1.35		SCHUTZ O'	8-14-87	282	145	REDRIED 0.58% MOIST @ 1.42% ASH
6-25- 2	1.07	0.98	SCHUTZ O'	8-14-87	277	145	RECORE^ 1.04%M @ 1.34% ASH ALSO 1.14%M @ 1.31 % ASH
6-25- 3	1.41	4.86	SCHUTZ O'	7-31-87	245	142	
6-25- 4	1.47	3.35	SCHUTZ O'	8-14-87	262	145	RECORED 3.48%M @ 1.34% ASH
6-25- 5	1.49						
6-25- 6	1.45	0.95	SCHUTZ O'	8-14-87	248	145	REDRIED 0.14% MOIST @ 1.48% ASH (0.18%M @ 1.49% ASH)
6-25- 7	1.48		SCHUTZ O'	8-14-87	253	145	REDRIED 3.30% MOIST @ 1.45% ASH
6-25- 8	1.24	0.78	SCHUTZ O'	7-31-87	275	142	
6-25- 9	1.26	0.66	SCHUTZ O'	7-31-87	250	142	
6-25- 10	1.32	4.25	SCHUTZ O'	7-31-87	239	142	
6-25- 11		3.77	SCHUTZ O'	7-31-87	103	142	
6-29- 1							REDRIED 9.87% MOIST @ 1.30% ASH
6-30- 1			SCHUTZ O'	8-14-87	317	145	REDRIED 1.72% MOIST @ 1.29% ASH
7-01- 1	1.26		SCHUTZ O'	8-14-87	249	145	
7-01- 2	1.26	1.65	SCHUTZ O'	7-31-87	257	142	
7-01- 3	1.26	13.33	SCHUTZ O'	8-14-87	232	145	REDRIED 0.55% MOIST @ 1.21% ASH
7-01- 4	1.23	8.13	OICE	8-05-87	200	144	REDRIED 9.65% MOIST @ 1.47% ASH
7-01- 5	1.17	8.66	SCHUTZ O'	8-14-87	??	145	REDRIED 5.12% MOIST @ 1.19% ASH
7-01- 6	1.25	4.35	PENN RILTON	7-14-87	210	134	
7-01- 7	1.20	11.03	SCHUTZ O'	8-14-87	213	145	REDRIED 4.83% MOIST @ 1.16% ASH
7-01- 8	1.23	0.61	PENN RILTON	7-14-87	237	134	
7-01- 9		6.00	SCHUTZ O'	8-14-87	212	145	REDRIED 0.82% MOIST @ 1.26% ASH
7-02- 1	1.23	0.49	OICE	8-05-87	258	144	
7-02- 2	1.26	1.71	PENN RILTON	7-14-87	227	134	
7-02- 3	1.26	?	PENN RILTON	7-14-87	267	134	
7-02- 4	1.35	7.95	OICE	8-05-87	204	144	RECORED 7.95%M @ 1.26% ASH
7-02- 5	1.28	10.05	SCHUTZ O'	8-14-87	243	145	RECORE 8.35%M @ 1.24% ASH REDRIED 4.62% MOIST @ 1.33% ASH
7-02- 6	1.22	5.59	OICE	8-05-87	209	144	ALSO PENN RILTON 7-14-87 247#
7-02- 7	1.24	1.38	PENN RILTON	7-14-87	209	134	
7-02- 8	1.25	6.65	SCHUTZ O'	8-14-87	226	145	REDRIED 1.63% MOIST @ 1.24% ASH
7-06- 1	1.26	7.73	SCHUTZ O'	8-14-87	199	145	REDRIED 8.47% MOIST @ 1.30% ASH
7-06- 2	1.21					1	MISSING
7-06- 3	1.18	1.10	SCHUTZ O'	7-31-87	234	142	RECORED 1.50%M @ 1.18% ASH
7-06- 4	1.24	0.53	SCHUTZ O'	7-31-87	243	142	
7-06- 5	1.34	17.17					REDRIED 7.26% MOIST @ 1.30% ASH
7-06- 6	1.29	16.77					REDRIED 9.76% MOIST @ 1.27% ASH
7-06- 7	1.28	3.72	SCHUTZ O'	7-31-87	238	142	
7-06- 8	1.18	11.08	OICE	8-05-87	214	144	REDRIED 16.25% MOIST @ 1.11 % ASH
7-06- 9	1.46		SCHUTZ O'	8-14-87	261	145	REDRIED 2.08% MOIST @ 1.20% ASH
7-07- 1	1.27	0.22	SCHUTZ O'	7-31-87	282	142	
7-07- 2	1.18	0.98	SCHUTZ O'	7-31-87	248	142	
7-07- 3	1.16	0.84	SCHUTZ O'	7-31-87	227	142	
7-07- 4	1.14	1.58	SCHUTZ O'	7-31-87	225	142	
7-08- 1	1.32	8.17	SCHUTZ O'	7-31-87	252	142	
7-08- 2	1.19	0.76	SCHUTZ O'	7-31-87	243	142	
7-08- 3	1.48	3.06	SCHUTZ O'	7-31-87	222	142	
7-08- 4	1.24	2.00	SCHUTZ O'	7-31-87	252	142	
7-08- 5	1.17	7.02	OICE	8-05-87	214	144	
7-08- 6	1.13	11.86	OICE	8-05-87	191	144	REDRIED 9.28% MOIST @ 1.05% ASH
7-08- 7	1.08	12.41	SCHUTZ O'	8-14-87	204	145	REDRIED 2.36% MOIST @ 1.89% ASH

DRAVO SHIPMENT DRUM LOG

DRUM #	% ASH	% MOIST	SHIP TO	DATE	WT.	SHIPMENT ID	
7-08- 8	1.08	2.40	SCHUTZ O'	7-31-87	240	142	
7-08- 9		1.80	SCHUTZ O'	7-31-87	228	142	RECORDED 3.29% MOIST
7-09- 1	1.22	1.66	SCHUTZ O'	7-31-87	220	142	
7-09- 2	1.18	3.49	SCHUTZ O'	7-31-87	243	142	
7-09- 3	1.22	2.29	SCHUTZ O'	7-31-87	227	142	
7-09- 4	1.23	2.07	SCHUTZ O'	7-31-87	236	142	
7-09- 5	1.20	1.39	SCHUTZ O'	7-31-87	235	142	
7-09- 6	1.21	0.92	SCHUTZ O'	7-31-87	225	142	
7-09- 7	1.20	7.14	OXCE	8-05-87	238	144	
7-09- 8	1.21	5.74	OXCE	8-05-87	236	144	
7-10- 1	1.43	1.44	SCHUTZ O'	7-31-87	245	142	
7-10- 2	1.52	1.57	SCHUTZ O'	7-31-87	234	142	
7-10- 3	1.50	2.70	SCHUTZ O'	7-31-87	219	142	RECORDED 3.34% @ 1.38% ASH ALSO 2.79% @ 1.26% ASH
7-10- 4	1.43	2.54	SCHUTZ O'	7-31-87	198	142	
7-10- 5	1.39	6.16					REDRIED 7.01% (8.44)MOIST @ 1.38% (1.37)ASH
7-10- 6	1.32	5.47	SCHUTZ O'	8-14-87	205	145	REDRIED 0.21% (0.29)MOIST @ 1.31% (1.31)ASH
7-10- 7	1.27	0.73	SCHUTZ O'	7-31-87	179	142	
7-10- 8	1.25	1.22	SCHUTZ O'	7-31-87	224	142	
7-10- 9	1.25	0.41	SCHUTZ O'	7-31-87	217	142	
7-10- 10	1.28						
7-10- 11	1.28	1.69	SCHUTZ O'	7-31-87	210	142	
7-10- 12	1.24	1.32	SCHUTZ O'	7-31-87	231	142	
7-10- 13							
7-13- 1	1.17	2.60	SCHUTZ O'	7-31-87	197	142	
7-13- 2	1.17	2.18	SCHUTZ O'	7-31-87	226	142	
7-13- 3	1.21	1.31	SCHUTZ O'	7-31-87	232	142	
7-13- 4	1.31	7.28	SCHUTZ O'	8-14-87	234	145	REDRIED 5.12% MOIST @ 1.30% ASH
7-13- 5	1.21	8.24	SCHUTZ O'	8-14-87	243	145	RECORDED 8.24% @ 1.10% ASH REDRIED 0.88% MOIST @ 1.31% ASH
7-13- 6			SCHUTZ O'	8-14-87	207	145	
7-14- 1	1.14	1.40	SCHUTZ O'	7-31-87	267	142	
7-14- 2	1.16	5.78	OXCE	8-05-87	208	144	REDRIED 6.95% MOIST @ 1.19% ASH
7-14- 3	1.20	1.29	SCHUTZ O'	7-31-87	229	142	
7-14- 4	1.14	1.00	SCHUTZ O'	7-31-87	235	142	
7-14- 5	1.16	7.16	SCHUTZ O'	8-14-87	210	145	REDRIED 1.19% MOIST @ 1.23% ASH
7-14- 6	1.29	8.21	SCHUTZ O'	8-14-87	192	145	REDRIED 3.82% MOIST @ 1.23% ASH
7-14- 7			SCHUTZ O'	7-31-87	215	142	
7-15- 1	1.22	6.88	SCHUTZ O'	7-31-87	199	142	
7-15- 2	1.31						
7-15- 3	1.30						
7-15- 4	1.30						
7-15- 5	1.31	11.37	SCHUTZ O'	8-14-87	210	145	REDRIED 4.99% MOIST @ 1.24% ASH
7-15- 6	1.21	6.02	SCHUTZ O'	8-14-87	221	145	REDRIED 0.82% MOIST @ 1.28% ASH
7-15- 7	1.36	9.78	SCHUTZ O'	8-14-87	217	145	REDRIED 0.31% (4.01) MOIST @ 1.22% ASH
7-15- 8							REDRIED 0.84% MOIST @ 1.24% ASH
7-16- 1	1.35	5.42	SCHUTZ O'	8-14-87	213	145	REDRIED +0.57% MOIST @ 1.10% ASH
7-16- 2	1.28	9.00	OXCE	8-05-87	235	144	REDRIED 6.65% MOIST @ 1.27% ASH
7-16- 3	1.18	7.08	SCHUTZ O'	7-31-87	187	142	REDRIED +0.07% MOIST @ 1.32% ASH (4.34% @ 1.45% ASH)
7-16- 4	1.23		SCHUTZ O'	7-31-87	247	142	RECORDED 0.29% @ 1.25% ASH
7-16- 5	1.28	0.53	SCHUTZ O'	7-31-87	244	142	
7-16- 6	1.24	0.71	SCHUTZ O'	7-31-87	159	142	
7-16- 7	1.23		SCHUTZ O'	8-14-87	88	145	REDRIED 0.31% @ 1.22% ASH

DRAGO SHIPMENT DRUM LOG

DRUM #	% ASH	% MOIST	SHIP TO	DATE	WT.	SHIPMENT ID	
7-16- 8	1.38	7.77	SCHUTZ O'	8-14-87	232	145	
7-17- 1							
7-17- 2			SCHUTZ O'	8-14-87	275	145	REDRIED 0.84%M @ 1.24% ASH
7-28- 1	1.27	9.25	SCHUTZ O'	7-31-87	189	142	REDRIED 0.00%M @ 1.32% ASH
7-28- 2	1.32	9.26	SCHUTZ O'	8-14-87	230	145	REDRIED 0.14%M @ 1.37% ASH
7-28- 3	1.38	10.88	SCHUTZ O'	7-31-87	194	142	REDRIED 4.71%M @ 1.38% ASH
7-28- 4	1.33	10.64	SCHUTZ O'	8-14-87	203	145	REDRIED 0.00%M @ 1.35% ASH
7-28- 5	1.35	6.40	SCHUTZ O'	7-31-87	202	142	REDRIED 2.31%M @ 1.37% ASH
7-28- 6	1.29	4.59	SCHUTZ O'	8-14-87	204	145	REDRIED 5.86% MOIST @ 1.27% ASH (5.31%M @ 1.36% ASH)
7-28- 7	1.27	4.54	SCHUTZ O'	8-14-87	230	145	RECORDED 4.51% MOIST @ 1.27% ASH
7-29- 1	1.33	9.21					
7-29- 2	1.28	7.79					
7-29- 3			OICE	8-05-87	214	144	RECORDED 5.17% MOIST @ 1.23% ASH
7-30- 1							
8-04- 1	1.25	12.72	OICE	8-05-87	215	144	
8-04- 2	1.23	8.18	OICE	8-05-87	231	144	
8-04- 3	1.23	5.51	OICE	8-05-87	239	144	
8-04- 4	1.37	8.30	OICE	8-05-87	219	144	
8-04- 5	1.35	4.91	OICE	8-05-87	228	144	
8-04- 6	1.28	8.28	OICE	8-05-87	249	144	
8-04- 7	1.26	10.06	SCHUTZ O'	8-14-87	213	145	REDRIED 1.18%M @ 1.29% ASH
8-04- 8	1.29	8.77				1	REDRIED 0.98%M @ 1.30% ASH "IGNITION"
8-04- 9	1.29	10.45				1	IGNITION
8-04- 10	1.39	6.49	SCHUTZ O'	8-14-87	230	145	REDRIED 3.78%M @ 1.31% ASH
8-04- 11	1.47	8.16	SCHUTZ O'	8-14-87	222	145	REDRIED 1.88%M @ 1.40% ASH
8-04- 12	1.42	5.76	SCHUTZ O'	8-14-87	237	145	REDRIED 0.84%M @ 1.46% ASH
8-04- 13	1.49	5.35	SCHUTZ O'	8-14-87	239	145	REDRIED 0.75%M @ 1.27% ASH
8-05- 1A	1.29	10.66	SCHUTZ O'	8-14-87	127	145	
8-05- 2A	1.24	5.77	SCHUTZ O'	8-14-87	226	145	
8-06- 1	1.61	4.28	SCHUTZ O'	8-14-87	259	145	
8-06- 2	1.27	10.10	SCHUTZ O'	8-14-87	232	145	
8-06- 3	1.24	6.37	SCHUTZ O'	8-14-87	218	145	
8-06- 4	1.29	5.40	SCHUTZ O'	8-14-87	152	145	
8-07- 1	1.29	6.80	SCHUTZ O'	8-14-87	210	145	
8-07- 2	1.29	6.37	SCHUTZ O'	8-14-87	179	145	
8-07- 3	1.71	4.40	SCHUTZ O'	8-14-87	225	145	
8-07- 4	1.28	8.66					
8-07- 5	1.31	5.75	SCHUTZ O'	8-14-87	233	145	
8-07- 6	1.33	9.85	SCHUTZ O'	8-14-87	202	145	
8-07- 7	1.33	4.05	SCHUTZ O'	8-14-87	232	145	
8-07- 8	1.31	7.32	SCHUTZ O'	8-14-87	233	145	
8-07- 9	1.30	6.85	SCHUTZ O'	8-14-87	184	145	
8-07- 10	1.25	4.17	SCHUTZ O'	8-14-87	235	145	
8-07- 11	1.27	3.88	SCHUTZ O'	8-14-87	223	145	
8-07- 12	1.29	4.15					
8-07- 13	1.25	2.13	SCHUTZ O'	8-14-87	241	145	
8-10- 1	1.69	4.21	SCHUTZ O'	8-14-87	218	145	
8-10- 2	1.72	7.21					
8-10- 3	1.58	8.51					
8-10- 4	1.32	9.10					
8-10- 5			SCHUTZ O'	8-14-87	249	145	

8-11- 1	1.44	2.16	SCHUTZ O'	8-14-87	245	145
8-11- 2	1.39	2.86	SCHUTZ O'	8-14-87	249	145

DRAGO SHIPMENT DRUM LOG

DRUM #	% ASH	% MOIST	SHIP TO	DATE	WT.	SHIPMENT ID
8-11- 3			SCHUTZ O'	8-14-87	224	145
8-11- 4						
8-12- 1	1.33	1.91	SCHUTZ O'	8-14-87	236	145
8-12- 2						
8-12- 3	1.29	0.38	SCHUTZ O'	8-14-87	253	145
8-12- 4	1.71	0.44	SCHUTZ O'	8-14-87	244	145
8-12- 5	1.49	2.56	SCHUTZ O'	8-14-87	247	145
8-12- 6	1.39	3.65	SCHUTZ O'	8-14-87	259	145
8-12- 7	1.37	1.79	SCHUTZ O'	8-14-87	248	145
8-12- 8	1.32	2.21	SCHUTZ O'	8-14-87	224	145
8-12- 9	1.28	2.64	SCHUTZ O'	8-14-87	209	145
8-12- 10	1.31	3.39	SCHUTZ O'	8-14-87	230	145
8-12- 11	1.39	1.69	SCHUTZ O'	8-14-87	243	145
8-12- 12	1.38	1.73	SCHUTZ O'	8-14-87	228	145
8-12- 13	1.37	3.27	SCHUTZ O'	8-14-87	243	145
8-12- 14	1.32	3.06	SCHUTZ O'	8-14-87	240	145
8-12- 15	1.26	3.04	SCHUTZ O'	8-14-87	253	145
8-12- 16			SCHUTZ O'	8-14-87	273	145
8-13- 1	1.25	0.65	SCHUTZ O'	8-14-87	270	145
8-13- 2	1.36	0.73	SCHUTZ O'	8-14-87	262	145
8-13- 3	1.31	0.66	SCHUTZ O'	8-14-87	84	145
8-18- 1	1.30	1.14				
8-18- 2	1.39	0.77				
8-18- 3	1.34	0.70				
8-18- 4	1.30	1.01				
8-18- 5	1.33	6.99				
8-18- 6	1.31	8.80				
8-19- 1	1.30	1.25				
8-19- 2	1.33	0.84				
8-20- 1	1.35	1.21				
8-20- 2	1.35	1.29				
8-20- 3	1.33	2.31				
8-20- 4	1.36	1.06				
8-20- 5	1.34	0.74				
8-20- 6	1.29	1.65				
8-24- 1						
8-24- 2						
8-24- 3						
8-24- 4						
8-25- 1						
8-25- 2						
8-25- 3						
8-25- 4						
8-25- 5						
8-25- 6						

**DATE
FILMED**

8 / 5 / 93

END