DATA QUALIFICATION SUMMARY FOR 1985 L-AREA AC FLOW TESTS (U)

by T. B. Edwards, et al.

Westinghouse Savannah River Company
Savannah River Site
Aiken, South Carolina 29808

D. A. Eghbali
M. L. Liebmann
E. P. Shine

RECEIVED
JUN 23 1993
OSTI

This paper was prepared in connection with work done under Contract No. DE-AC09-89SR18035 with the U. S. Department of Energy. By acceptance of this paper, the publisher and/or recipient acknowledges the U. S. Government's right to retain a nonexclusive, royalty-free license in and to any copyright covering this paper, along with the right to reproduce and to authorize others to reproduce all or part of the copyrighted paper.

DISPATCHED FOR DEPARTMENT OF ENERGY
JUN 23 1993

NRTSC
Nuclear Reactor Technology
And Scientific Computations

WSRC-TR-92-134
Task 91-033-1

**Data Qualification Summary
for 1985 L-Area AC Flow Tests (U)**

by

**T. B. Edwards
D. A. Eghbali
M. L. Liebmann*
E. P. Shine**

Issued: March, 1992

Authorized Derivative Classifier

* M.L. Liebmann, a member of the task team, made significant contributions to this study, but left WSRC before the preparation of this document.

SRL

Savannah River Laboratory, Aiken, SC 29802
Westinghouse Savannah River Company

Prepared by the U. S. Department of Energy under Contract DE-AC09-88SR18035

MASTER

Document: WSRC-TR-92-134

Title: Data Qualification Summary
for 1985 L-Area AC Flow Tests (U)

Task Number: 91-033-1

Approvals

T. B. Edwards 3-10-92
T. B. Edwards, Author Date

D. A. Eghbali 3-11-92
D. A. Eghbali, Author Date

E. P. Shine 3-10-92
E. P. Shine, Author Date

C. P. Reeve 3/13/92
C. P. Reeve, Technical Reviewer Date

J. R. Pelfrey 3-13-92
J. R. Pelfrey, Responsible Manager Date

M. R. Buckner 3-17-92
M. R. Buckner, Level 3 Manager Date

J. D. Menna 3-13-92
J. D. Menna, Customer Date

TABLE OF CONTENTS

Section	Page
1.0 Executive Summary.....	1
2.0 Introduction	1
3.0 Overview of the 1985 L-Area AC Flow Tests ...	1
4.0 Data Acquisition and Instrumentation	2
5.0 Description of Important Data	5
6.0 Measurement Uncertainties	7
7.0 Description of Data Keying and Verification	9
8.0 Raw Data Adjustments and Derived Parameters	9
9.0 Overview of the Data Qualification Process	11
10.0 Explanation of the Data Qualification Methods	14
11.0 Data Integrity Review	17
12.0 Conclusions	22
13.0 References	23
14.0 Tables	25

Listing of Tables

Table		Page
Table 1	1985 L-Area AC Flow Test Configurations	25
Table 2	Plenum Pressure Measurements	26
Table 3	ScaniValve Positions and Loop Pressure Tap Locations	27
Table 4	Test Sequence and Ultrasonic Flowmeter Placement	28
Table 5	ACDATA3	29
Table 6	PLENUM2 for Test A	32
Table 7	PLENUM2 for Test B	35
Table 8	PLENUM2 for Test C	38
Table 9	PLENUM2 for Test D	41
Table 10	PLENUM2 for Test E	44
Table 11	PLENUM2 for Test F	47
Table 12	PLENUM2 for Test G	50
Table 13	PLENUM2 for Test H	53
Table 14	PLENUM2 for Test I	56
Table 15	PLENUM2 for Test J	59
Table 16	PLENUM2 for Test K	62
Table 17	Test A: Results of Data Qualification of 1985 L-Area AC Flow Tests	65
Table 18	Test B: Results of Data Qualification of 1985 L-Area AC Flow Tests	70
Table 19	Test C: Results of Data Qualification of 1985 L-Area AC Flow Tests	75
Table 20	Test D: Results of Data Qualification of 1985 L-Area AC Flow Tests	80
Table 21	Test E: Results of Data Qualification of 1985 L-Area AC Flow Tests	85
Table 22	Test F: Results of Data Qualification of 1985 L-Area AC Flow Tests	90
Table 23	Test G: Results of Data Qualification of 1985 L-Area AC Flow Tests	95
Table 24	Test H: Results of Data Qualification of 1985 L-Area AC Flow Tests	100
Table 25	Test I: Results of Data Qualification of 1985 L-Area AC Flow Tests	105

Listing of Tables (continued)

Table		Page
Table 26	Test J: Results of Data Qualification of 1985 L-Area AC Flow Tests	110
Table 27	Test K: Results of Data Qualification of 1985 L-Area AC Flow Tests	115

1.0 Executive Summary

An extensive study of the data from the 1985 L-Area AC Flow Tests was recently completed [1]. The purpose of that study was to provide corroborating technical information as to the quality, fitness for use, of these experimental data. This report provides highlights from that study: an overview of the tests and their data, a description of the instrumentation used, an explanation of the data qualification methods employed to review the data, and the important conclusions reached from the study.

2.0 Introduction

This report summarizes the results of the recently completed, formal, technical review of the data from the 1985 L-Area AC Flow Tests as detailed in document SCS-CMAS-910045 [1]. The purpose of that review was to provide corroborating technical information as to the quality (fitness for use) of these experimental data. Reference [1] required three volumes to fully document the results of that Data Qualification process. This report has been prepared to provide the important conclusions from that process in a manageable and understandable format. Consult reference [1] if any additional information or detail is needed.

3.0 Overview of the Tests

The 1985 L-Area AC Flow Tests were conducted to provide an extended data base for upgrading the reactor system models employed in predicting normal process water flows [2]. To span a reasonable range of system flows and temperatures, these tests consisted of 11 different steady-state and simulated-LOCA configurations, including:

1. normal operation,
2. operation with septifoil system isolated,
3. operation with one (of two) heat exchangers isolated in each loop,
4. operation with one pump off and the loop in backflow (simulates LOCA),

5. operation with three pumps off and the rotovalves isolated in each of the loops.

The tests were run at "cold" (~ 22 degrees Celsius) and "warm" (~ 60 degrees Celsius) to evaluate the effects of temperature on flow. The test conditions and naming conventions are provided in Table 1. For all of the tests, the reactor moderator tank was at overflow conditions with no helium blanket gas present and vented to the process room through the vacuum breakers and normal blanket gas piping.

The AC Flow tests data were originally reduced and released in [3].

4.0 Data Acquisition and Instrumentation

The instrumentation and data acquisition systems used during the 1985 L-Area AC Flow Tests are fully described in reference [1]. The original measurements as recorded on paper tapes and data sheets, the special procedure and authorization for the tests, photos, figures and other pertinent information were all reviewed during the Data Qualification process to provide a description of how the data from the tests were acquired.

During the test runs, data were acquired at selected intervals by three Acurex Dataloggers. Two of these (Model Ten/10) were located at the reactor room station (the 0' elevation) and the third one (Model Ten/30) was located on the heat exchanger level (the -20' elevation data station). For many of the critical system pressures, impulse lines were routed to a multi-position scanning valve ("Scanivalve") that was connected to a pressure gauge ("Heise Gauge") and one of these data loggers.

The outputs from the dataloggers, which were provided on paper tapes, were the primary source of raw data for the tests. For each of the 11 tests, the first datalogger, located at the process room level, provided a paper tape with plenum pressures and locations (44 point averaging), as shown in Table 2. The paper tape from the second datalogger, located on the heat exchanger level provided the loop locations and pressures (15 point averaging), as shown in Table 3. The printout frequency for both dataloggers was approximately 1 per minute. Thus, each plenum pressure location, designated by an on-line computer (OLC) number,

was sampled about every 48 minutes, each pump suction location every 7 minutes and all other loop locations every 21 minutes.

Additional measurements were recorded manually using seven data sheets, which were numbered 1 through 7. Data Sheet #1 was used to record pump suction temperature every 15 minutes, by which the approach to steady-state process water temperature was observed and maintained. Data Sheet #2 was used to record pump differential pressure, plenum inlet temperature, pump suction temperature, and plenum centerline pressure every 30 minutes. Data Sheet #3 was used to record barometric pressure at the heat exchanger bay data station every hour and flow rate using ultrasonic flowmeters every 30 minutes. Data Sheet #4 was used to record pressure at tank bottom centerline (Automatic Incident Action (AIA) positions in Gang 1), low pressure header, and three Mark 60B taps at the -40' elevation data station. The other data sheets (#5-#7), which were used to record and monitor information including Caterpillar diesel engine performance, process water temperature, reactor level, and cooling water temperature, were not involved in the Data Qualification process.

A more detailed review of the instrumentation is now provided by measurement type.

Loop Temperatures:

Process water temperatures were measured using existing plant Resistance Temperature Devices (RTD's) at pump suction and plenum inlet for all six loops.

Loop Pressures:

Measurements of pressure at pump suction and discharge, and heat exchanger inlet and discharge were performed using the datalogger Ten/30 located at the -20' elevation along with two 48-port Scanivalves and two Heise digital pressure gauges. The 0-30 psia Heise gauge was used at pump suction. The other loop pressures used the 0-300 psig Heise gauge. The pump differential pressures were recorded on the data sheets.

Loop Flows:

A number of devices were used to provide measurements of loop flows during these tests.

- 1) A Laser Doppler Anemometer (LDA) was used at system or loop 1 to measure the loop flow. Data from the LDA, which were collected on floppy disks, were not considered in the DQ study.
- 2) Pitot tubes were inserted (2.5" inside pipe) at the heat exchanger inlet for all six loops. These tubes were fabricated at Savannah River Laboratory (SRL) and were not calibrated prior to use. The differential pressure readings provided by the pitot tubes, which were collected using the datalogger at the -20' elevation data station, were not considered in the DQ study.
- 3) Three Controlotron System 480 Wide-Beam Clamp-On Ultrasonic Transit Time (UTT) flowmeters were used to measure the pump flow during the AC tests. One of UTTs was mounted on system or loop 1 while the other two UTTs were placed on various systems (see Table 4).

The two System 484 Flow Display Computers (A&B), which were used to convert the transducers' signals to flow in kgpm, were stored in the Heat Transfer Laboratory (HTL) after the testing was completed.

Plenum Pressures:

Ninety modified assembly plenum shield plugs were fabricated to replace the normal plenum shield plugs for the positions (OLC locations) of interest. Each plug employed a feed-through pressure tube which dipped into the coolant. Pressure tubing connected the outside end of the feed-through to two 48-port Scanivalves. The impulse tubing from half of the plugs (Series "A" plugs on the paper tape) was connected to one 48-port Scanivalve while the tubing from the other half (Series "B" plugs on the paper tape) was connected to the other automatically by synchronized steppers. The output tubing from each Scanivalve was connected to an electric Heise digital pressure gauge. Signals from the Heise gauges were recorded by one of the Ten/10 dataloggers located in the reactor room station. The 0-200 psig Heise gauge was used for the plenum pressure measurements.

Assembly Flows:

Assembly flows were measured in up to six fuel assemblies at selected buckle-zone positions using special high-flow venturimeters installed above the assemblies in the sleeve housing. Each venturimeter was complete with a housing shield plug through which two nylon pressure tubes passed. The venturi assemblies replaced the normal reactor shield plugs. These venturimeters were assembled and calibrated in the HTL prior to use. These data were not considered during the DQ study.

Septifoil Flows:

A Controlotron ultrasonic (UTT) flowmeter was installed on the far-side septifoil intersection to measure the septifoil flow. These data were not considered in the DQ study.

Monitor Pin Differential Pressures:

All monitor pin differential pressures were measured using the existing plant instrumentation, but these data were not considered in the DQ study.

Emergency Coolant System (ECS) Injection Point Pressures:

ECS injection point pressure was measured using the 0-300 psig Heise gauge as described above for the loop pressures.

Plenum Centerline Pressures:

The plenum centerline pressure was measured using existing instrumentation, System "A" and "B" on the control computer.

Moderator Tank Bottom Pressures:

The 0-50 psig Heise gauge was used to measure tank bottom pressures at five locations: GANG 1 AIA, Low Pressure Header, and three Mark 60B OLC locations.

5.0 Description of Important Data

A significant amount of data was collected during the 1985 L-Area AC Flow Tests, this section describes the data that were considered for qualification.

Loop Water Temperatures:

Three temperature data streams were recorded for each test: pump suction water temperature using Data Sheets #1 and #2 and plenum inlet water temperature at two locations (usually) in each loop. These data streams were investigated in order to determine an appropriate process water temperature which was used in the adjustment of pressures and calculation of flows.

Barometric Pressure:

The barometric pressure was used in the conversion from gauge to absolute pressure. An atmospheric pressure of 1013.15 millibars was used as the conversion for 14.696 psia. The maximum expected variation of barometric pressure was considered to have negligible effect on these pressure conversions.

Loop Pressures:

These pressures outlined in Table 3 are a critical part of the data that was reviewed. The pump differential pressures, recorded on Data Sheet #2, were not reviewed since few of these measurements were taken.

Plenum Pressures:

Detailed in Table 2, these data streams were reviewed as part of the DQ study.

Loop Flows:

Of the data on loop flows, only the three UTT flowmeters were reviewed as part of the DQ process.

Plenum Centerline Pressures:

The plenum centerline pressure measurements were recorded in two places: the Bailey System "B" (central control room recorder) using Data Sheet #2 and the Heise Gauge System "A" using a datalogger.

Tank Bottom Pressures:

The low pressure header pressure is composed of six common pressure taps located at the tank bottom in the gas port positions. Therefore, these pressures should provide a good comparison to the Mark 60B measurements. During the asymmetric tests, a

larger difference between the average and individual measurements was expected because the Mark 60B locations were clustered in the adjacent loop 1 and 6 sectors.

The AIA GANG 1 pressure measurements were derived from pressure taps near the tank center that were part of the absolute and differential pressure sources for tank level indication to the AIA system. No additional information was found on the specific instrumentation. The 0-50 psig Heise gauge was used for these measurements.

A secondary experimental measurement from the 1985 tests that was provided in reference [3] was the manometer temperature. This temperature could not be found on any data sheet or in any logbook. Test personnel could not recall where the temperature originated. It is used to adjust the static head for the instrument pressure lines and therefore, the temperature should be approximately process room temperature. Values of 25 degrees and 40.5 degrees Celsius were used for all of the cold and warm tests, respectively.

Variations in manometer temperature were determined to have little effect on the pressure adjustments as demonstrated in [4].

6.0 Measurement Uncertainty

The uncertainties of the measurements from the instruments used in the L-Area 1985 AC Flow Tests were difficult to determine. An attempt was made as part of the DQ study to estimate the potential bias or systematic error for the measurements.

The following table presents the Heise digital pressure gauges that were used during the 1985 L-Area AC Flow Tests:

Type	Model	Serial #	Range	Unit
Heise	710A	S7-18478	0-30	psia
Heise	710A	S7-18457	0-50	psig
Heise	710A	S7-18456	0-100	psig
Heise	710A	S7-18455	0-200	psig
Heise	710A	S7-18454	0-300	psig

Calibration sheets [5] and manufacturer's information [6] were available to assist in the following uncertainty analysis for bias for the pressure measurements from the Heise gauges:

Source	Heise Gauge			
	30 psia	50 psig	200 psig	300 psig
Data Reduction (Round-Off)	.01	.01	.01	.01
Instrument Bias	.1	.1	.4	.6
Datalogger	.04	NA	.04	.04
Total Bias (Root Sum Square)	<u>.11</u>	<u>.10</u>	<u>.40</u>	<u>.60</u>

NA - Not Appropriate

The estimates of instrument bias used were at least twice those quoted by the Heise gauge manufacturer [6]. Sources of variation such as linearity, hysteresis, and temperature were considered insignificant [6]. The bias from the datalogger was estimated from periodic checks made against the Heise gauge output during the tests that were recorded in [7 & 8].

The investigation into RTDs used for taking water temperatures provided calibration and uncertainty information on instruments similar to those used in the 1985 tests [9]. No calibration information traceable to National Institute of Standards and Technology (NIST) could be found for the instruments used in this test. A bias estimate for these instruments could not be determined.

The uncertainty provided by the manufacturer of the Controlotron Ultrasonic Transit Time Flowmeters was used to estimate the bias at 3% [10]. The UTTs were calibrated by the manufacturer.

The plenum centerline pressures were recorded with existing System "A" and System "B" instrumentation. Reference [11] estimated a total System "A" uncertainty of $\pm 1.1\%$ of 150 psig span or ± 1.65 psig and a System "B" uncertainty of $\pm 0.9\%$ of 100 psig span or ± 0.9 psig. These uncertainties were considered as conservative limits on the bias for these measurements.

7.0 Description of Data Keying and Verification

The data manipulation for the DQ process began with the test data in their original form, on paper tapes and data sheets. These data were manually keyed into the MicroSoft EXCEL software package on an Apple Macintosh personal computer. Data from twenty-two paper tapes and from data sheets 1 through 4 for all eleven tests were keyed into EXCEL. Eleven of the paper tapes recorded the loop pressures and eleven recorded the plenum pressures.

Since reference [3] provided many of the measurement averages computed from the 1985 test data, this document was used as an independent verification of the EXCEL data. Other methods used to verify the correctness of the EXCEL data were documented in reference [1].

8.0 Raw Data Adjustments and Derived Parameters

A formal review of adjustments to and some parameters derived from the raw data was included within the scope of the DQ study. This was done for two reasons. First, the adjusted and derived values were often used to facilitate the DQ process. Secondly, these values have many applications and are, therefore, of interest in their own right.

The origin of these adjustments and derived parameters can be traced back to two programs, PLENUM and ACDATA2, which were presented in [3]. PLENUM was used to convert the raw pressure measurements from

inside the universal sleeve housing (USH) and to calculate the assembly flow from the pressure. ACDATA2 provided a conversion of the raw pressure measurements from around the loops and adjusts them to the actual tap locations, accounting for the hydrostatic pressure difference between the taps and gauges. ACDATA2 also determined a loop flow from the corrected pump differential pressure.

Incorporated into the DQ task was the technical review of these two programs [4, 12,& 13]. Several changes resulted from this technical review and from corrections made by the author (noted as "LDK corrections") of reference [3] subsequent to its release. These changes are shown below:

ACDATA3 corrections to original ACDATA2 program

- Add density correlation for input process and manometer temperatures,

LDK Corrections

- Change tank bottom from -20' to -19.25' elevation,
- Add elevation difference between pump suction and discharge pressure taps to pump head calculation.

PLENUM2 corrections to original PLENUM program

- Change density correlation,
- Change viscosity correlation,
- Adjust measured plenum pressure to account for tap-to-gauge elevation,
- Adjust head in USH for actual weir elevation below 0' elevation,

LDK Correction

- Change sign for plenum-to-tank elevation adjustment in USH head calculation.

As indicated in the above tables, the revised programs were renamed ACDATA3 and PLENUM2 during the DQ study. This was to distinguish them from the original versions. They were applied to the 1985 L-Area AC Flow Tests data. See references [1, 4, 12, & 13] for more details on the evaluation of the impact of these program changes on the resulting values.

ACDATA3 adjusted the measured loop and tank bottom pressures from the transducer locations to the actual pressure tap locations, accounting for hydrostatic pressures in the lines between the taps and gauges. ACDATA3 also accounted for density changes due to process system and process room (for pressure tap to transducer lines) temperature. The program calculated the loop forward flows by converting the adjusted flow using the cubic pump curve from reference [14]. Table 5 provides the results for ACDATA3 calculations.

PLENUM2 provided the conversion of the raw (measured) pressures inside the USH to corrected pressures outside the USH, at the top of the plenum. The relationship between flow and pressure loss from the outside to inside of the USH was based on adjusted A-tank test measurements. The program also accounted for viscosity and density changes with temperature to encompass the warm and cold tests. PLENUM2 calculated the assembly flows using the Newton-Raphson technique, first determining the head inside the USH from the plenum pressure measurements and then iterating to find the corresponding flow. Then using a flow equation based on head between the plenum and tank bottom [15] and K-factors derived from the fuel assembly hydraulic manuals, the head and pressure outside the USH were calculated. Tables 6 through 16 provide the results for these PLENUM2 calculations.

9.0 Overview of the Data Qualification Process

Data Qualification is the process of verifying that the measurement data from an experiment represent the system under the experimental conditions.

An important aspect of the 1985 L-Area AC Flow Tests, in formulating the methods for the DQ process, was that most of the test data were to

be recorded after the processing reached steady-state conditions for each test configuration. All data streams were recorded during hold-point conditions with two exceptions - the data streams for water temperature and barometric pressure. As stated earlier, water temperature was monitored during the testing to identify and maintain the steady-state condition for each test. Operator intervention maintained the water temperature within an acceptable range for each test. Steady-state processing offered special opportunities for checking the quality of the resulting data streams. These opportunities are investigated below.

The data qualification process consisted of methods for investigating:

1. Range
This was a reasonableness check to make sure that the data from an instrument were within the expected operational range for that instrument.
2. Stability
Each data stream should have shown evidence of a stable process and instrumentation as a result of the testing being conducted at steady-state conditions.
3. Consistency
The behavior of the measurements in relation to the sequence of events of the testing were reviewed for consistency.
4. Precision
Precision is the agreement of the data in a data stream among themselves. It is the repeatability of the measurements in a single data stream. An estimate of the precision is provided by the standard deviation of the data stream. The standard deviations of data streams over the 11 tests were investigated for consistent behavior.
5. Accuracy
The accuracy of the data from an instrument is the closeness of the data to the true value of the system under the conditions being tested. Accuracy was investigated by studying data streams that were expected to behave similarly.

For these techniques, instrument readings, computational models, associated uncertainties, and assumptions regarding measurement relationships which depend on engineering and other expert judgment are required. The DQ methods, which are more fully developed below, were applied to each measurement data set (the data stream for a single instrument) for each test. Engineering and experimental insight provided much of the information necessary to identify behavior that should be demonstrated in the data. The statistical aspects of these investigations led to descriptions of the data stream which were then reviewed for practical importance from engineering and experimental aspects. The final decision on the quality of the data was a joint decision based upon the best efforts of the DQ team.

Each of these data streams were assigned a label (QUALIFIED, CONDITIONALLY QUALIFIED, or FAILED) as a result of the investigation. If the data set was not FAILED, a mean and standard deviation were provided as representative of this process measurement. Other labelling schemes have been used in previous DQ efforts [16]. The labels used in this study are defined below.

The label "QUALIFIED" was to be assigned to the data if the above areas of investigation revealed no problems and the necessary uncertainties could be determined and evaluated.

If uncertainties were incomplete or not available, if the traceability of instrument calibrations could not be verified, or if the accuracy of data streams could not be confirmed, then the label CONDITIONALLY QUALIFIED was assigned to the measurements.

The FAILED label was to be used if an instrument failure was detected, or no useful information was retrievable, or if there were significant problems with the data.

The CONDITIONALLY QUALIFIED label should not be confused with the CONDITIONAL label used by Idaho National Engineering Laboratory (INEL) on an interim basis during their qualification of the 1989 L-Area tests [16].

10.0 Explanation of the Data Qualification Methods

In the sections below, each of the areas of investigation mentioned earlier is discussed in more detail. The methods used for the investigation are also provided.

Measurements within Range

The range check was used to verify that data streams were within feasible limits and to identify out-of-range conditions for each instrument. The out-of-range check for each of the instruments utilized the manufacturer's stated operating range or the calibrated range for the instrument. The range check entailed a manual review of time charts for each of the data streams. All measurements in a data stream were verified to be within this operating range as part of this check. The range check was passed if no outliers were detected. If some out-of-range measurements were detected, then this condition was investigated to determine if it was process or instrument related. If the outlier was due to the data collection system, for example a transcription error, the outlying measurement was deleted or adjusted. The impact of any remaining outliers was examined and reported.

Process and Instrument Stability

Process and instrument stability should be demonstrated in the measurement data acquired under steady-state conditions. Under these conditions, an instrument's data stream should reveal no trend over time, a constant mean level, and constant variation. Identification of outliers and dropouts was also a part of this examination.

Stability of a data stream was reviewed by examining plots of the data streams versus time. The number of observations for some of these data sets was very small, but a significant amount of time usually elapsed between observations providing snap shots over a relatively long period of time.

Charts were based on a single data stream or pooled information for several streams if possible. If no trend or pattern was

identified, the stability test was passed. An explanation was sought for any trend or pattern found in the data. For example, temperature data streams were not expected to be stable. If a trend existed, it was determined whether the trend was sufficiently large, based on engineering principles, to impact results.

Measurement Consistency

Consistency checks are an investigation into the relationships among test conditions and data streams. The impact of various test conditions on the resulting measurements were examined. Certain behaviors were predictable over the sequence of events for the tests and these should be demonstrated in the data, usually through the arithmetic averages of the measurement data streams.

Plots of the measurement averages for the various groups of instruments over the eleven tests were developed. Some tables were prepared comparing the results of paired tests - experiments whose test conditions differed only in temperature. Models were also developed to estimate the effects of the test conditions on the measurement data streams. These models provided an empirical consistency check. For each of these approaches, the results were reviewed to determine if the results demonstrated behavior that was consistent with engineering or other scientific principles.

The residuals (the differences between the actual and predicted values) were studied in order to find data streams that exhibit atypical behavior. If the residual could be explained there was no problem. If not, then the consistency check was not passed for data stream.

Measurement Precision

As an experiment is planned, the question of adequate instrument precision or repeatability is answered by uncertainty analyses, MT&E information for this instrument class, and/or by expert opinion.

A measure of repeatability of a data stream is provided by the standard deviation of the measurements under stable conditions. This variability may be examined for consistency across various test conditions such as temperatures, loops, etc. The method used to examine instrument precision began with the calculation of the standard deviation for each data stream. These statistics were manually reviewed for consistency and compared to the expected results from the uncertainty analyses.

Measurement Accuracy

The determination of the accuracy of a data stream is an important part of the evaluation of any experimental result. One of the best accuracy checks is a test of the instrument against nature under process conditions, such as an in situ calibration. Instrument redundancy is valuable when each instrument cannot be directly tested against nature under experimental conditions to judge its accuracy or, the reverse, its degree of bias. Instruments may fall into different redundancy groups; no redundancy, redundancy of similar instruments, and redundancy based on different first principles. Detection of many of the causes that affect instrument bias can be shown to be related to this structure. If an instrument has no redundancy, then any cause may lead to an undetected bias. If two similar instruments are redundant, then only causes that systematically affect both remain undetected. An example would be a faulty calibration procedure applied to all instruments of the same type or an impurity that interferes with an assay. If two instruments are redundant and behave according to different first principles, then the class of possibly undetected biases is shrunk to those that are systematic across instrument classes. Two assays methods based on different first principles may both suffer the same bias if both are calibrated with the same incorrectly labeled standard. The result of this grouping offers a rationale for increasing confidence that no bias is present, when each instrument cannot be directly tested against nature.

Some redundancies were available for the 1985 results. The qualified data from AC4 Modified (Hold-point 19) in the 1989 L-

Reactor hydraulic tests was used as an historical redundancy [17]. This test which was qualified by INEL was conducted under the same conditions as Test B of 1985 L-Reactor tests. Therefore the loop measured parameters for these tests were compared directly for redundancy purpose. The plenum pressure distributions of these tests could not be directly compared due to the impact that different fuel charges have on plenum pressure distributions. The fuel charges for 1989 L-Reactor tests were Mark 22 while the fuel charges for 1985 L-Reactor tests were a combinations of Marks 16, 31B, and 60B. Other redundancies available for the 1985 results are discussed below.

The comparison of redundant data streams involved the investigation of the difference(s) of the means of the data streams. The significance of their difference(s) was judged from two perspectives, engineering importance and statistical uncertainty. Situations where the difference was sufficiently large from the engineering perspective to warrant concern and/or the difference exceeded the uncertainty limits for the difference, merit additional attention. If an explanation other than the phenomenon being studied caused the anomaly, then the test was passed. If not, the test was failed.

11.0 Data Integrity Review

The data qualification methods were applied to the data streams by measurement type. The results of the checks for range, stability, consistency, precision and accuracy for each measurement type were presented in detail in reference [1].

Tables 17 through 27 provide the final results from this process. For each test, each data stream is identified, its average (from the raw measurements) is given, an estimate of precision (twice the standard deviation) is provided, the bias is estimated (for QUALIFIED data), and the quality label is assigned.

Comments pertinent to the label assignment for each measurement type are summarized in this section.

Process Water Temperature

Process water temperatures were recorded at pump suction and in each of the two heat exchanger outlet pipes for each loop. The temperatures from the outlet pipes are the plenum inlet water temperatures for that loop. In each loop, one of three different RTDs measured each of these three temperatures. The pump suction water temperatures were recorded on Data Sheet #1 and #2 and the plenum inlet water temperatures were recorded on Data Sheet #2.

Pump suction water temperatures were controlled and maintained within a specified range for "cold" versus "warm" tests to establish steady-state processing. Patterns of behavior in the data stream reflected this fact.

These measurements were reviewed together and were used to estimate process water temperature for each test. These temperature estimates were needed to make the ACDATA3 and PLENUM2 adjustments. The pump suction water temperatures from Data Sheet #1 were used as the process water temperature for all tests except for Test K. The data for Test K on Data Sheet #1 included only one value for each loop. The pump suction water temperatures from Data Sheet #2 had more values and were used to determine a process water temperature for Test K.

These water temperatures were assigned the label **CONDITIONALLY QUALIFIED** (except in situations where no measurements were recorded, these data streams were **FAILED**). The "conditional" reflects the fact that no uncertainty information or calibration information corresponding to the RTD's used for the 1985 tests was available.

Barometric Pressure

These data were used to adjust gauge pressure measurements to pounds per square inch absolute. They were not truly steady-state data since these data streams could only be monitored during the testing. The review of these data revealed no problems such as recording errors or outliers. However, no

information was available regarding the instrumentation used for these measurements; thus, these data have been assigned the label "CONDITIONALLY QUALIFIED."

Ultrasonic Flowmeter Measurements

Three ultrasonic flowmeters were used during these tests. One remained in loop 1 for all eleven tests while the other two were placed in other loops for each of the tests. Table 4 provides the details of these placements as well as zero offset values which were recorded in the laboratory notebook during the testing [7].

All five of the DQ checks were applied to these data including comparisons to flow data from the the L-Area tests conducted in 1989. The comparisons provided a limited opportunity for accuracy checks. No problems were found in areas where appropriate checks could be identified. Since no specific calibration information was available for the flowmeters used during these tests, the uncertainty in the measurements could not be adequately estimated. For these reasons the flow data streams were assigned the "CONDITIONALLY QUALIFIED" label.

Plenum Centerline Pressures

Two plenum centerline pressure data streams were recorded for each test - one on the paper tape from System "A" and one on the data sheets from System "B." More measurements were taken on the paper tapes, but the data from the data sheets were adequate for review.

All DQ checks were applied and no problems found. In fact, since two instruments were involved in the measuring process, a comparison of the average data sheet pressure versus the average paper tape pressure provided a very good accuracy check for each test. These results lead to the assignment of "QUALIFIED" for the plenum centerline pressures.

Tank Bottom Pressures

Five tank bottom pressure data streams were recorded for each test: one data stream for LPH readings, one for GANG1 readings, and one for each of three OLC locations.

No problems were discovered in the application of the DQ checks. The accuracy check was facilitated by a tank level test that was conducted during the testing and documented in the logbook [8]. These results lead to the "QUALIFIED" label being assigned to these data streams.

Pump Suction Pressures

All of the DQ checks were applied to these data. Some minor trends were revealed in the time plot of the data streams for some tests, but these slight stability problems were considered to be of little practical concern. A redundancy to qualified 1989 L-Area data for Test B and consistency of the 1985 tests were confirmed by the other DQ checks. Also, pre-test information including a calibration traceable to an NIST standard for the Heise gauge used for these measurements were documented. The "QUALIFIED" label was assigned to these data streams.

Pump Discharge Pressures

The stability check for these data revealed a common pattern of behavior across all loops for tests G and J. These patterns were found to be similar to those demonstrated by water temperatures and were believed to reflect actual system conditions. No instrument problems were involved. Pre-test information including a calibration traceable to NIST standards was available. An historical redundancy to the qualified 1989 L-Area data and consistency results across the 1985 tests allowed for assignment of a "QUALIFIED" label.

Heat Exchanger Inlet Pressures

The stability checks for these data revealed a pattern for tests G and J. These pressure measurements were demonstrating behavior similar to that seen in the pump discharge pressures.

Once again, these patterns were not considered to be a problem with the instrumentation, but to reflect actual operating conditions.

All the other DQ checks revealed no problems and the calibration information for the Heise gauge providing the measurements was available. The "QUALIFIED" label was assigned.

Heat Exchanger Discharge Pressures

All five of the DQ checks were made on these data. No problems were discovered. Pre-test information including a calibration traceable to NIST standards were available for the Heise gauge providing these measurements. Redundancy to qualified 1989 data and consistency of results across the 1985 tests allowed for assignment of the "QUALIFIED" label.

ECS Pressures

Checks for range, stability, consistency and precision revealed no problems for these data. However, no accuracy check was identified for these data streams. Although calibration information is available for the Heise gauge used for these measurements, the "CONDITIONALLY QUALIFIED" label is assigned since no accuracy check could be made.

Plenum Pressures

The ninety data streams providing plenum pressures for each test were reviewed extensively. The range, stability and precision checks were quickly applied without any problems being discovered except for OLC 487. The measurements for OLC 487 demonstrated significant problems for some tests and those data streams have been FAILED.

The checks for consistency and accuracy were difficult. This was because of the complexity of behaviors of the pressures in the plenum. Numerous comparisons among the tests were attempted with some success. Tests whose processing conditions differed only by temperature produced pressure facemaps that were

similar. Quantitative models based on an analysis of variance approach for the symmetric tests (A,B,C,G,H & I) provided evidence of consistency of measurements, but a pattern in the residual plots for these was also revealed. These patterns suggested that the plenum pressure behavior was more complex than these models were capable of estimating. A comparison of facemaps plots of these residuals revealed similar behavior in the residuals from tests that differed only by temperature (A-G, B-H and C-I). The patterns in the residuals were related to positional differences.

The only accuracy check available for these data streams was to compare the derived plenum centerline pressure from PLENUM2 to that measured with System "B." The comparisons, which could be made at only two OLC's, 1 and 6, for each test, provided good but limited results.

Information for calibration and uncertainties was available for the Heise gauge used for these measurements. However, since accuracy checks were possible for only 2 OLC's for each test, these data streams (except where noted for OLC 487) were assigned the label "CONDITIONALLY QUALIFIED."

12.0 Conclusions

The Data Qualification process was a formal evaluation of the test data based on evidence provided by the data themselves using engineering and statistical principles. Overall these results provide corroborating technical information that the data from the 1985 tests were representative of the processes being tested.

13.0 References

- [1] Edwards, T.B., D.A. Eghbali, M.L. Liebmann, & E.P. Shine, "Data Qualification for 1985 L-Area AC Flow Tests," SCS-CMAS-910045, December 31, 1991.
- [2] Special Procedure No. SP-2363 (TA 1-2200), "AC Process Flow Test," February 14, 1985.
- [3] L. D. Koffman, et. al., "TRAC Calculations of the Initial Flow Decay in L-1.1," DPST-87-737, December 18, 1987.
- [4] M. L. Liebmann, "Technical Review ACDATA2 and PLENUM Programs," Task 91-033-1, July 23, 1991.
- [5] Dresser Industrial Instrument Operations, "Calibration Certification Report," Serial Nos. S7-18478, S7-18457, S7-18456, S7-18455 & S7-18455, February 18, 1985 (included with Invoice No. 3GH-L1919 and Purchase Requisition T42596).
- [6] "Heise Installation and Operating Instructions for Series 7 Digital Pressure Indicators," Dresser Industries, May, 1983.
- [7] Laboratory Notebook No. E37297, pages 1 through 31.
- [8] Laboratory Notebook No. E37312, pages 1 through 57.
- [9] D.A. Eghbali, "Pump Suction and Plenum Inlet Temperature Measurement Uncertainties (U)," NES-ETH-910479, September 16, 1991.
- [10] Controlotron Instruction Manual, 480IM-4a, "Series 480 Clamp-On Flowmeter, " January 23, 1984.
- [11] S. M. Mertz, "Plenum Pressure Measurement Uncertainties (U)," WSRC-TR-90-42-121, January 2, 1991.
- [12] Memorandum, L. D. Koffman to T. B. Edwards, "Comments on NES-ART-910216," NES-CDG-910132, July 30, 1991.

- [13] Memorandum, N. M. Askew to T.B. Edwards, "Corrections to the PLENUM2 Spreadsheet," NES-ART-910341, August 20, 1991.
- [14] L. L. Hamm and M. A. McClain, "New Bingham Pump Head Curves," DPST-85-906 (DRAFT), August 19, 1985.
- [15] L. D. Koffman, "TRAC Core Generator," DPST-88-642, August 11, 1988.
- [16] R. P. Evans, et. al., "Savannah River Laboratory Qualification Manual," EG&G Idaho, Inc., May 1990 (Draft).
- [17] Memorandum, D. A. Eghbali to T. B. Edwards, "1989 L Reactor Qualified Data," NES-ETH-910230, April 15, 1991.

14.0 Tables

TABLE 1

1985 L-Area AC Flow Test Configurations

<u>Test</u>	<u>Pumps On (Loops)</u>	<u>Septifoil Position</u>	<u>Rotovalves Open</u>	<u>Process Temp</u>
A	1 - 6	off	A only	cold
B	1 - 6	off	A and B	cold
C	1 - 6	on	A and B	cold
D	1 - 5	off	A and B	cold
E	2 - 6	off	A and B	cold
F	1,3,5	off	A and B	cold
G	1 - 6	off	A only	warm
H	1 - 6	off	A and B	warm
I	1 - 6	on	A and B	warm
J	2 - 6	off	A and B	warm
K	1,3,6	off	A and B	warm

TABLE 2
PLENUM PRESSURE MEASUREMENTS
OLC Location and Scani Valve Position

Flow Zone	Fuel Ass'y	OLC #	X Coordi nates	Y	Scani Valve A Pos'n	Flow Zone	Fuel Ass'y	OLC #	X Coordi nates	Y	Scani Valve B Pos'n
0	NOFLOW	539	31	3	1	4	MK16B	432	17	15	1
0	NOFLOW	542	27	3	2	3	MK16B	280	35	15	2
0	NOFLOW	524	49	21	3	9	MK31A	406	43	21	3
0	NOFLOW	559	7	21	4	7	MK31A	161	29	21	4
0	NOFLOW	562	5	27	5	7	MK31A	295	23	21	5
0	NOFLOW	520	51	27	6	7	MK31A	177	17	27	6
0	NOFLOW	512	55	51	7	1	MK16B	148	38	30	7
0	NOFLOW	510	54	54	8	7	MK31A	71	31	33	8
0	NOFLOW	508	53	57	9	7	MK31A	83	21	33	9
0	NOFLOW	506	53	63	10	7	MK31A	313	12	36	10
0	NOFLOW	504	52	66	11	7	MK31A	263	46	36	11
0	NOFLOW	579	4	66	12	1	MK16B	182	17	39	12
0	NOFLOW	502	51	69	13	1	MK16B	26	26	42	13
0	NOFLOW	500	50	72	14	7	MK31A	15	34	42	14
0	NOFLOW	582	6	72	15	7	MK31A	135	43	45	15
0	NOFLOW	499	49	75	16	4	MK16B	450	7	45	16
0	NOFLOW	498	48	78	17	1	MK16B	34	22	48	17
0	NOFLOW	496	45	81	18	7	MK31A	1	29	51	18
0	NOFLOW	497	47	81	19	1	MK16B	6	27	51	19
0	NOFLOW	495	44	84	20	1	MK16B	59	36	54	20
0	NOFLOW	593	15	87	21	7	MK31A	129	42	54	21
0	NOFLOW	493	41	87	22	3	MK16B	248	48	54	22
0	NOFLOW	494	43	87	23	10	MK31A	509	52	54	23
0	NOFLOW	492	40	90	24	6	MK16B	507	52	60	24
0	NOFLOW	490	38	90	25	7	MK31A	243	46	60	25
0	NOFLOW	488	36	90	26	1	MK16B	198	12	60	26
0	NOFLOW	596	20	90	27	1	MK16B	106	25	63	27
0	NOFLOW	595	18	90	28	7	MK31A	47	29	63	28
0	NOFLOW	592	13	87	29	1	MK16B	124	39	63	29
0	NOFLOW	597	21	93	30	4	MK16B	382	48	66	30
0	NOFLOW	598	23	93	31	2	MK16B	238	43	69	31
0	NOFLOW	599	25	93	32	3	MK16B	236	46	72	32
0	NOFLOW	600	27	93	33	7	MK31A	115	36	72	33
0	NOFLOW	482	29	93	34	1	MK16B	110	32	72	34
0	NOFLOW	484	31	93	35	1	MK16B	214	24	72	35
0	NOFLOW	486	33	93	36	1	MK16B	210	20	72	36
10	MK31A	487	34	90	37	3	MK16B	230	41	75	37
10	MK31A	491	39	87	38	10	MK31A	377	44	78	38
20	PLUG				39	20	PLUG				39
5	MK16B	367	35	87	40	4	MK16B	472	17	81	40
9	MK31A	363	31	87	41	3	MK16B	354	19	81	41
4	MK16B	361	27	87	42	2	MK16B	358	23	81	42
3	MK16B	360	23	87	43	7	MK31A	221	27	81	43
10	MK31A	475	19	87	44	2	MK16B	218	31	81	44
9	MK31A	471	16	84	45	8	MK31A	223	35	81	45
6	MK16B	373	42	84	46	8	MK31A	372	39	81	46
20	PLUG				47	20	PLUG				47
20	PLUG				48	20	PLUG				48

TABLE 3
SCANI VALVE POSITIONS AND LOOP PRESSURE TAP LOCATIONS

<u>Scani Valve A</u>		<u>Scani Valve B</u>	
<u>Position Number</u>	<u>Tap Location</u>	<u>Position Number</u>	<u>Tap Location</u>
1	PD1	1	PS1
2	PD2	2	PS2
3	PD3	3	PS3
4	PD4	4	PS4
5	PD5	5	PS5
6	PD6	6	PS6
7	HI1		
8	HD1		
9	HI2		
10	HD2		
11	HI3		
12	HD3		
13	HI4		
14	HD4		
15	HI5		
16	HD5		
17	HI6		
18	HD6		
19	ECS1		
20	ECS4		

<u>KEY</u>	
HD	heat exchanger discharge
HI	heat exchanger inlet
ECS	ECS line
PS	pump suction
PD	pump discharge
#	loop/system number

Table 4

Test Sequence & Ultrasonic Flowmeter Placement

Ultrasonic - a Ultrasonic - b Ultrasonic - c

<u>Test Sequence</u>	L O O P S					
	1	2	3	4	5	6
B	a	-	-	-	b (-635)	c
A	a	-	-	-	b (-635)	c
D	a	-	-	c (-260)	b	-
E	a	-	-	c (-260)	b	-
F	a	-	c (-250)	-	b	-
C	a	-	c (-250)	-	-	b (-980)
G	a	-	c (-250)	-	-	b (-980)
H	a	-	c (-250)	-	-	b (-980)
I	a	-	c (-250)	-	-	b (-980)
J	a	-	c (-250)	-	-	b (-980)
K	a	-	c (-250)	-	-	b (-980)

(zero offset)
gpm

Table 5 --- ACDATA3

Measurements	Test A	Test B	Test C	Test D	Test E	Test F	Test G	Test H	Test I	Test J	Test K
PS1 - psia	17.473	14.767	14.669	13.393	22.778	12.208	17.324	14.688	14.376	22.636	12.286
PS2 - psia	17.604	15.059	14.640	13.818	13.760	21.890	17.317	14.664	14.343	13.609	21.753
PS3 - psia	17.853	14.940	14.644	13.607	13.606	11.978	17.467	14.503	14.103	13.174	11.998
PS4 - psia	18.051	15.493	15.045	14.327	14.307	21.904	17.720	15.019	14.706	14.009	21.821
PS5 - psia	18.199	15.702	15.210	14.578	14.561	13.286	17.843	15.213	14.870	14.148	21.771
PS6 - psia	17.750	15.079	14.736	22.798	13.789	21.891	17.410	14.694	14.327	13.274	12.223
PD1 - psig	226.309	194.475	191.786	181.061	41.034	162.881	220.007	188.494	184.838	46.442	159.718
PD2 - psig	227.245	194.019	191.159	181.346	181.320	7.916	220.488	187.577	183.744	174.081	7.755
PD3 - psig	226.986	190.542	188.486	178.133	178.227	157.632	220.151	183.908	180.046	170.171	147.930
PD4 - psig	230.976	200.187	197.632	188.410	188.790	7.918	224.879	194.182	190.540	181.492	7.744
PD5 - psig	232.071	199.927	197.373	187.687	188.277	168.867	225.566	194.003	190.205	180.678	7.728
PD6 - psig	225.054	191.314	188.677	41.158	176.859	7.894	218.264	185.154	181.416	168.933	154.261
HI1 - psig	220.915	185.933	182.904	171.160	43.593	151.042	214.586	179.752	175.755	48.824	148.258
HI2 - psig	221.821	185.475	182.283	171.557	171.525	7.888	215.106	179.029	174.872	164.105	7.830
HI3 - psig	224.375	186.027	183.856	173.166	173.241	151.510	217.761	179.702	175.710	165.265	141.953
HI4 - psig	225.968	191.873	189.089	178.988	179.449	7.896	219.692	185.812	181.806	171.823	7.813
HI5 - psig	226.949	191.595	188.732	178.061	178.693	157.237	220.359	185.561	181.456	170.850	7.811
HI6 - psig	220.090	183.017	180.121	42.981	167.137	7.884	213.055	176.609	172.545	158.814	143.283
HD1 - psig	68.963	108.761	104.076	81.047	65.464	46.982	69.745	108.092	103.131	66.297	57.035
HD2 - psig	69.463	109.608	105.219	84.218	84.040	47.954	70.412	108.838	104.001	84.226	49.670
HD3 - psig	66.452	102.491	97.856	76.748	76.880	38.940	67.217	101.849	97.198	76.458	38.762
HD4 - psig	70.001	109.342	104.829	83.650	84.451	48.233	71.047	109.121	104.208	84.544	43.193
HD5 - psig	70.389	110.650	105.847	83.960	85.038	46.380	71.522	110.777	105.631	85.268	45.856
HD6 - psig	65.300	102.060	97.811	64.479	72.636	46.005	65.884	101.465	96.884	72.281	48.223
ECS1 - psig	66.623	104.707	100.292	76.226	65.712	41.458	67.351	104.032	99.128	66.596	51.453
ECS4 - psig	69.058	107.104	102.741	80.999	81.787	48.222	70.061	106.767	101.877	81.674	43.208
TB-LPH-psig	16.740	16.480	16.420	16.490	16.500	16.800	16.550	16.300	16.250	16.300	16.630
TB-GANG1-psig	17.410	17.580	17.520	17.400	17.420	17.290	17.290	17.470	17.420	17.290	17.140

Measurements	Test A	Test B	Test C	Test D	Test E	Test F	Test G	Test H	Test I	Test J	Test K
Manometer Temp - C	25	25	25	25	25	25	40.5	40.5	40.5	40.5	40.5
Process Water Temp - C	21.87	25.16	22.51	22.32	22.3	23.02	59.93	59.84	59.99	59.19	58.26
Barometric Pressure - psia	14.63	14.73	14.64	14.61	14.57	14.6	14.76	14.76	14.74	14.76	14.76
Density-gauge - lb(m)/ft3	68.9963	68.9963	68.9963	68.9963	68.9963	68.9963	68.6233	68.6233	68.6233	68.6233	68.6233
Density-process-lb(m)/ft3	69.0612	68.9929	69.0482	69.0521	69.0525	69.0378	68.0341	68.0372	68.0321	68.0591	68.0901

Table 5 --- ACDATA3

Adjusted (psia)	Test A	Test B	Test C	Test D	Test E	Test F	Test G	Test H	Test I	Test J	Test K
PS1a	25.084	22.378	22.280	21.004	30.389	19.819	24.894	22.258	21.946	30.206	19.856
PS2a	25.215	22.670	22.251	21.429	21.371	29.501	24.887	22.234	21.913	21.179	29.323
PS3a	25.464	22.551	22.255	21.218	21.217	19.589	25.037	22.073	21.673	20.744	19.568
PS4a	25.662	23.104	22.656	21.938	21.918	29.515	25.290	22.589	22.276	21.579	29.391
PS5a	25.810	23.313	22.821	22.189	22.172	20.897	25.413	22.783	22.440	21.718	29.341
PS6a	25.361	22.690	22.347	30.409	21.400	29.502	24.980	22.264	21.897	20.844	19.793
PD1a	247.387	215.653	212.874	202.119	62.052	183.929	241.181	209.668	205.992	67.616	180.892
PD2a	248.323	215.197	212.247	202.404	202.338	28.964	241.662	208.751	204.898	195.255	28.929
PD3a	248.064	211.720	209.574	199.191	199.245	178.680	241.325	205.082	201.200	191.345	169.104
PD4a	252.234	221.545	218.900	209.648	209.988	29.146	246.231	215.534	211.872	202.844	29.096
PD5a	253.149	221.105	218.461	208.745	209.295	189.915	246.740	215.177	211.359	201.852	28.902
PD6a	246.132	212.492	209.765	62.216	197.877	28.942	239.438	206.328	202.570	190.107	175.435
HI1a	231.353	196.471	193.352	181.578	53.971	161.450	225.176	190.342	186.325	59.414	158.848
HI2a	232.298	196.052	192.770	182.014	181.942	18.335	225.736	189.659	185.482	174.735	18.460
HI3a	234.852	196.604	194.343	183.623	183.658	161.957	228.391	190.332	186.320	175.895	152.583
HI4a	236.391	202.396	199.522	189.391	189.812	18.289	230.267	196.387	192.361	182.398	18.388
HI5a	237.426	202.172	199.219	188.518	189.110	167.684	230.989	196.191	192.066	181.480	18.441
HI6a	230.547	193.574	190.588	53.418	177.534	18.311	223.665	187.219	183.135	169.424	153.893
HD1a	81.442	121.340	116.565	93.506	77.883	59.431	82.365	120.712	115.731	78.917	69.655
HD2a	81.922	122.167	117.688	96.657	96.439	60.383	83.013	121.439	116.582	96.827	62.271
HD3a	78.951	115.090	110.365	89.227	89.319	51.409	79.857	114.489	109.818	89.098	51.402
HD4a	82.495	121.936	117.333	96.124	96.885	60.697	83.682	121.756	116.823	97.179	55.828
HD5a	82.858	123.219	118.326	96.409	97.447	58.819	84.133	123.388	118.222	97.879	58.467
HD6a	77.794	114.654	110.315	76.953	85.070	58.469	78.519	114.100	109.499	84.916	60.858
ECS1a	79.097	117.281	112.776	88.680	78.126	53.902	79.967	116.648	111.724	79.212	64.069
ECS4a	81.547	119.693	115.240	93.468	94.216	60.681	82.691	119.397	114.487	94.304	55.838
Tank-LPH	23.444	23.284	23.134	23.174	23.144	23.474	23.427	23.177	23.107	23.177	23.507
Tank-GANG1	24.114	24.384	24.234	24.084	24.064	23.964	24.167	24.347	24.277	24.167	24.017

Table 5 --- ACDATA3

Derived Values	Test A	Test B	Test C'	Test D	Test E	Test F	Test G	Test H	Test I	Test J	Test K
Pump DP1 - psi	222.963	193.934	191.253	181.774	0.000	164.769	216.936	188.059	184.695	0.000	161.686
Pump DP2 - psi	223.768	193.186	190.655	181.634	181.626	0.000	217.424	187.166	183.634	174.725	0.000
Pump DP3 - psi	223.260	189.828	187.978	178.632	178.687	159.750	216.937	183.658	180.176	171.250	150.186
Pump DP4 - psi	227.051	198.920	196.723	188.189	188.549	0.000	221.414	193.418	190.069	181.738	0.000
Pump DP5 - psi	227.999	198.451	196.299	187.215	187.782	169.677	221.976	193.043	189.568	180.783	0.000
Pump DP6 - psi	221.431	190.461	188.077	0.000	177.136	0.000	215.107	184.713	181.322	169.912	156.292
Pump Head1 - ft	466.276	406.148	400.234	380.444	1.375	345.053	460.538	399.400	392.309	1.375	343.315
Pump Head2 - ft	467.954	404.587	398.987	380.152	380.133	1.375	461.571	397.510	390.063	371.060	1.375
Pump Head 3 - ft	466.895	397.578	393.404	373.892	374.004	334.584	460.540	390.085	382.744	363.708	318.994
Pump Head 4 - ft	474.426	416.180	411.266	393.447	394.195	1.000	469.640	410.366	403.308	385.522	1.000
Pump Head 5 - ft	476.776	415.576	410.757	391.791	392.971	355.290	471.206	409.949	402.624	383.878	1.375
Pump Head 6 - ft	463.081	398.899	393.610	1.375	370.770	1.375	456.667	392.318	385.170	360.877	331.907
Flow rate 1 - gpm	19.347	24.764	25.190	26.524	0.000	28.628	19.981	25.249	25.740	0.000	28.724
Flow rate 2 - gpm	19.155	24.878	25.278	26.542	26.544	0.000	19.869	25.381	25.892	27.113	0.000
Flow rate 3 - gpm	19.276	25.377	25.665	26.938	26.931	29.196	19.981	25.890	26.375	27.558	30.002
Flow rate 4 - gpm	18.383	24.008	24.384	25.662	25.611	0.000	18.959	24.451	24.970	26.194	0.000
Flow rate 5 - gpm	18.089	24.055	24.422	25.775	25.695	28.051	18.773	24.483	25.019	26.302	0.000
Flow rate 6 - gpm	19.704	25.284	25.651	0.000	27.131	0.000	20.391	25.739	26.217	27.726	29.337

Table 6 --- PLENUM2 for Test A

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	45.92	46.89	97.07	179.24	47.06
6	43.86	46.67	92.78	313.57	46.84
15	45.67	46.63	96.55	178.73	46.80
26	44.27	47.10	93.63	315.06	47.28
34	43.76	46.56	92.57	313.21	46.74
47	45.32	46.27	95.81	178.01	46.44
59	44.32	47.16	93.74	315.24	47.33
71	45.72	46.68	96.65	178.83	46.85
83	45.10	46.05	95.36	177.57	46.22
106	42.84	45.59	90.65	309.85	45.76
110	45.62	48.54	96.44	319.90	48.71
115	48.87	49.89	103.21	185.12	50.06
124	43.19	45.95	91.38	311.12	46.13
129	45.50	46.45	96.18	178.37	46.62
135	45.48	46.44	96.16	178.34	46.61
148	44.65	47.50	94.41	316.41	47.68
161	46.86	47.84	99.03	181.13	48.02
177	45.57	46.52	96.34	178.52	46.70
182	43.55	46.34	92.13	312.44	46.51
198	45.76	48.69	96.74	320.41	48.86
210	42.71	45.44	90.37	309.36	45.62
214	43.10	45.86	91.19	310.80	46.04
218	47.24	50.26	99.83	325.64	50.44
221	47.17	48.16	99.67	181.75	48.33
223	52.72	53.50	111.24	161.33	53.68
230	50.70	53.37	107.04	305.29	53.54
236	48.33	50.88	102.09	297.97	51.05
238	43.71	46.51	92.46	313.02	46.68
243	46.14	47.10	97.52	179.67	47.28
248	43.50	45.80	92.03	282.53	45.98
263	47.02	48.01	99.37	181.46	48.18
280	49.81	52.43	105.18	302.56	52.61
295	45.77	46.73	96.75	178.92	46.90
313	49.21	50.24	103.93	185.79	50.41
354	44.04	46.36	93.14	284.28	46.54
358	43.69	46.49	92.42	312.96	46.66
360	44.70	47.06	94.53	286.43	47.23
361	47.11	49.33	99.54	277.38	49.50

Table 6 --- PLENUM2 for Test A

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	53.15	53.67	112.15	129.44	53.84
367	53.92	55.08	113.74	198.22	55.26
372	54.28	55.09	114.50	163.77	55.26
373	57.73	58.49	121.70	158.17	58.66
377	56.15	56.43	118.40	94.82	56.60
382	44.49	46.59	94.09	269.50	46.77
406	54.28	54.80	114.50	130.82	54.98
432	45.21	47.35	95.59	271.70	47.52
450	52.22	54.68	110.21	292.20	54.85
471	48.02	48.48	101.44	122.95	48.66
472	43.88	45.95	92.81	267.61	46.12
475	51.33	51.58	108.34	90.66	51.76
482	57.86	57.86	121.96	0.00	58.03
484	58.66	58.66	123.64	0.00	58.84
486	60.14	60.14	126.72	0.00	60.31
487	-	-	-	-	-
488	57.21	57.21	120.61	0.00	57.39
490	60.79	60.79	128.06	0.00	60.96
491	58.31	58.59	122.89	96.63	58.77
492	60.54	60.54	127.54	0.00	60.71
493	59.43	59.43	125.23	0.00	59.60
494	60.67	60.67	127.82	0.00	60.84
495	60.08	60.08	126.59	0.00	60.26
496	57.61	57.61	121.44	0.00	57.78
497	60.63	60.63	127.74	0.00	60.81
498	60.15	60.15	126.74	0.00	60.32
499	57.97	57.97	122.19	0.00	58.14
500	56.63	56.63	119.40	0.00	56.80
502	57.37	57.37	120.94	0.00	57.55
504	55.52	55.52	117.09	0.00	55.70
506	53.28	53.28	112.41	0.00	53.45
507	48.45	49.09	102.35	144.98	49.27
508	53.88	53.88	113.67	0.00	54.06
509	50.99	51.24	107.64	90.36	51.42
510	54.80	54.80	115.58	0.00	54.98
512	55.73	55.73	117.51	0.00	55.90
520	58.24	58.24	122.76	0.00	58.42
524	59.42	59.42	125.21	0.00	59.59

Table 6 --- PLENUM2 for Test A

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	57.79	57.79	121.82	0.00	57.97
542	57.67	57.67	121.57	0.00	57.85
559	58.55	58.55	123.39	0.00	58.72
562	60.65	60.65	127.78	0.00	60.83
579	58.52	58.52	123.34	0.00	58.69
582	58.46	58.46	123.22	0.00	58.64
592	56.68	56.68	119.50	0.00	56.85
593	55.47	55.47	116.98	0.00	55.64
595	54.63	54.63	115.22	0.00	54.80
596	53.76	53.76	113.42	0.00	53.94
597	51.94	51.94	109.62	0.00	52.12
598	53.32	53.32	112.49	0.00	53.49
599	56.25	56.25	118.61	0.00	56.43
600	57.38	57.38	120.97	0.00	57.56

Table 7 --- PLENUM2 for Test B

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	75.45	77.03	158.80	232.33	77.20
6	71.99	76.55	151.58	403.99	76.73
15	75.07	76.63	158.00	231.71	76.81
26	72.52	77.12	152.68	405.51	77.29
34	71.61	76.15	150.79	402.91	76.33
47	74.34	75.89	156.47	230.54	76.06
59	72.48	77.07	152.59	405.38	77.24
71	75.13	76.70	158.13	231.82	76.88
83	73.95	75.49	155.66	229.90	75.67
106	70.29	74.75	148.03	399.10	74.92
110	74.79	79.53	157.43	411.96	79.71
115	79.97	81.64	168.23	239.49	81.82
124	71.24	75.76	150.01	401.84	75.93
129	74.79	76.35	157.42	231.27	76.53
135	74.37	75.93	156.55	230.59	76.10
148	72.97	77.59	153.61	406.78	77.76
161	77.23	78.84	162.51	235.17	79.02
177	74.65	76.21	157.13	231.04	76.38
182	70.81	75.30	149.10	400.58	75.47
198	74.84	79.58	157.52	412.08	79.76
210	69.35	73.75	146.06	396.35	73.92
214	70.11	74.55	147.65	398.56	74.73
218	77.45	82.35	162.96	419.36	82.53
221	77.24	78.85	162.53	235.18	79.03
223	86.60	87.88	182.06	208.36	88.05
230	82.37	86.65	173.24	390.86	86.83
236	78.54	82.62	165.24	381.51	82.80
238	71.26	75.78	150.05	401.89	75.95
243	75.69	77.27	159.29	232.71	77.44
248	71.20	74.91	149.92	362.94	75.08
263	77.71	79.33	163.51	235.93	79.51
280	81.72	85.96	171.88	389.28	86.14
295	75.24	76.81	158.36	231.99	76.99
313	80.97	82.66	170.32	241.05	82.84
354	71.77	75.51	151.11	364.42	75.68
358	71.69	76.23	150.94	403.12	76.41
360	73.24	77.06	154.18	368.20	77.23
361	77.60	81.20	163.28	357.33	81.37

Table 7 --- PLENUM2 for Test B

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	87.54	88.37	184.02	166.83	88.55
367	88.71	90.59	186.48	254.47	90.76
372	88.99	90.30	187.05	211.30	90.48
373	94.07	95.27	197.65	201.89	95.44
377	91.98	92.43	193.30	121.55	92.61
382	73.75	77.17	155.24	348.23	77.35
406	89.93	90.79	189.02	169.14	90.96
432	74.28	77.73	156.35	349.50	77.91
450	86.07	90.05	180.95	376.60	90.22
471	79.14	79.89	166.49	158.50	80.07
472	71.81	75.15	151.20	343.56	75.32
475	84.35	84.77	177.37	116.37	84.94
482	95.61	95.61	200.88	0.00	95.79
484	96.35	96.35	202.41	0.00	96.52
486	98.52	98.52	206.95	0.00	98.70
487					
488	94.49	94.49	198.53	0.00	94.66
490	99.25	99.25	208.46	0.00	99.42
491	95.73	96.20	201.11	124.01	96.37
492	99.39	99.39	208.76	0.00	99.56
493	97.35	97.35	204.50	0.00	97.52
494	99.33	99.33	208.63	0.00	99.50
495	98.13	98.13	206.13	0.00	98.30
496	94.88	94.88	199.34	0.00	95.05
497	98.28	98.28	206.45	0.00	98.46
498	98.21	98.21	206.29	0.00	98.38
499	95.11	95.11	199.84	0.00	95.29
500	92.63	92.63	194.65	0.00	92.81
502	95.15	95.15	199.92	0.00	95.33
504	94.21	94.21	197.96	0.00	94.39
506	90.56	90.56	190.34	0.00	90.74
507	80.63	81.71	169.70	186.99	81.89
508	91.74	91.74	192.79	0.00	91.91
509	83.63	84.04	175.87	115.87	84.22
510	91.01	91.01	191.28	0.00	91.19
512	94.21	94.21	197.96	0.00	94.39
520	95.79	95.79	201.25	0.00	95.96
524	98.01	98.01	205.88	0.00	98.18

Table 7 --- PLENUM2 for Test B

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	95.54	95.54	200.72	0.00	95.71
542	94.04	94.04	197.60	0.00	94.22
559	94.69	94.69	198.94	0.00	94.86
562	98.22	98.22	206.31	0.00	98.39
579	96.20	96.20	202.10	0.00	96.37
582	96.42	96.42	202.57	0.00	96.60
592	94.87	94.87	199.32	0.00	95.04
593	91.52	91.52	192.34	0.00	91.70
595	89.81	89.81	188.76	0.00	89.98
596	86.82	86.82	182.53	0.00	87.00
597	84.65	84.65	178.00	0.00	84.83
598	87.19	87.19	183.30	0.00	87.37
599	92.39	92.39	194.15	0.00	92.56
600	94.25	94.25	198.04	0.00	94.43

Table 8 --- PLENUM2 for Test C

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	71.94	73.44	151.34	226.43	73.61
6	68.69	73.04	144.56	394.15	73.22
15	71.49	72.99	150.42	225.70	73.16
26	68.87	73.24	144.95	394.69	73.42
34	68.52	72.86	144.21	393.65	73.04
47	70.92	72.41	149.23	224.76	72.58
59	69.19	73.58	145.61	395.61	73.75
71	71.54	73.03	150.52	225.78	73.21
83	70.56	72.03	148.47	224.16	72.21
106	66.96	71.21	140.97	389.07	71.39
110	71.32	75.84	150.05	401.78	76.01
115	76.24	77.83	160.31	233.39	78.00
124	67.96	72.27	143.05	392.01	72.45
129	71.35	72.84	150.11	225.46	73.01
135	71.00	72.49	149.40	224.90	72.66
148	69.86	74.29	147.02	397.58	74.47
161	73.71	75.25	155.05	229.33	75.43
177	71.17	72.66	149.75	225.17	72.83
182	67.76	72.06	142.64	391.43	72.24
198	71.58	76.12	150.61	402.55	76.30
210	66.25	70.45	139.47	386.93	70.63
214	67.10	71.36	141.26	389.48	71.54
218	73.71	78.39	155.05	408.63	78.56
221	73.76	75.30	155.15	229.41	75.48
223	82.56	83.78	173.49	203.16	83.95
230	78.64	82.74	165.33	381.53	82.91
236	75.10	79.02	157.95	372.70	79.19
238	68.12	72.44	143.38	392.48	72.62
243	72.14	73.65	151.77	226.77	73.83
248	67.98	71.52	143.08	354.29	71.70
263	74.11	75.66	155.87	229.97	75.83
280	78.15	82.21	164.29	380.31	82.39
295	71.84	73.34	151.14	226.27	73.51
313	77.10	78.71	162.11	234.76	78.88
354	68.47	72.04	144.11	355.59	72.22
358	68.27	72.60	143.69	392.92	72.77
360	69.82	73.47	146.94	359.15	73.64
361	73.67	77.09	154.95	347.82	77.26

Table 8 --- PLENUM2 for Test C

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	83.36	84.15	175.16	162.64	84.33
367	84.31	86.10	177.15	247.94	86.28
372	84.81	86.07	178.20	205.99	86.24
373	89.69	90.84	188.37	197.05	91.02
377	87.22	87.65	183.21	118.29	87.82
382	70.22	73.49	147.77	339.49	73.66
406	85.80	86.62	180.25	165.04	86.79
432	70.69	73.98	148.74	340.63	74.15
450	81.95	85.75	172.22	367.13	85.92
471	75.49	76.21	158.75	154.65	76.39
472	68.37	71.55	143.90	334.91	71.72
475	80.34	80.73	168.86	113.50	80.91
482	91.09	91.09	191.30	0.00	91.27
484	91.71	91.71	192.57	0.00	91.88
486	93.71	93.71	196.76	0.00	93.89
487	87.80	87.80	184.43	0.00	87.98
488	89.63	89.63	188.24	0.00	89.80
490	94.48	94.48	198.36	0.00	94.65
491	90.86	91.31	190.81	120.74	91.48
492	94.51	94.51	198.41	0.00	94.68
493	92.68	92.68	194.60	0.00	92.85
494	94.57	94.57	198.54	0.00	94.74
495	93.62	93.62	196.55	0.00	93.79
496	89.81	89.81	188.62	0.00	89.99
497	93.75	93.75	196.82	0.00	93.92
498	93.55	93.55	196.41	0.00	93.72
499	90.39	90.39	189.83	0.00	90.57
500	88.25	88.25	185.36	0.00	88.42
502	90.80	90.80	190.69	0.00	90.98
504	89.21	89.21	187.38	0.00	89.39
506	86.08	86.08	180.83	0.00	86.25
507	76.70	77.69	161.27	182.25	77.87
508	86.72	86.72	182.17	0.00	86.89
509	79.92	80.31	167.98	113.20	80.49
510	86.66	86.66	182.05	0.00	86.84
512	89.52	89.52	188.01	0.00	89.69
520	91.51	91.51	192.16	0.00	91.68
524	93.53	93.53	196.37	0.00	93.70

Table 8 --- PLENUM2 for Test C

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	91.03	91.03	191.16	0.00	91.20
542	89.61	89.61	188.20	0.00	89.79
559	90.65	90.65	190.36	0.00	90.82
562	93.58	93.58	196.48	0.00	93.75
579	91.64	91.64	192.44	0.00	91.82
582	91.62	91.62	192.40	0.00	91.80
592	90.19	90.19	189.42	0.00	90.37
593	87.09	87.09	182.93	0.00	87.26
595	85.37	85.37	179.37	0.00	85.55
596	83.01	83.01	174.43	0.00	83.18
597	80.91	80.91	170.05	0.00	81.08
598	83.26	83.26	174.95	0.00	83.43
599	88.64	88.64	186.17	0.00	88.81
600	89.82	89.82	188.64	0.00	90.00

Table 9 --- PLENUM2 for Test D

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	49.11	50.14	103.74	185.63	50.32
6	46.81	49.80	98.93	324.13	49.97
15	49.82	50.86	105.20	187.00	51.03
26	47.64	50.68	100.67	327.06	50.86
34	46.50	49.47	98.28	323.04	49.64
47	49.38	50.41	104.30	186.15	50.59
59	46.35	49.32	97.98	322.54	49.49
71	51.16	52.23	108.00	189.60	52.40
83	48.67	49.69	102.82	184.76	49.87
106	47.32	50.35	100.01	325.96	50.52
110	47.64	50.68	100.66	327.06	50.86
115	48.28	49.29	102.00	183.99	49.47
124	44.88	47.75	94.91	317.28	47.92
129	48.89	49.92	103.28	185.19	50.09
135	50.51	51.57	106.65	188.35	51.74
148	51.68	54.98	109.10	340.91	55.15
161	53.79	54.91	113.49	194.61	55.09
177	50.86	51.92	107.37	189.02	52.09
182	46.32	49.28	97.92	322.43	49.46
198	51.77	55.07	109.27	341.19	55.24
210	47.48	50.51	100.33	326.51	50.69
214	47.08	50.08	99.49	325.09	50.26
218	48.07	51.14	101.57	328.57	51.32
221	48.61	49.63	102.69	184.64	49.80
223	50.23	50.97	106.06	157.40	51.15
230	47.20	49.69	99.75	294.46	49.86
236	47.47	49.97	100.32	295.31	50.15
238	43.28	46.05	91.58	311.50	46.23
243	50.24	51.29	106.09	187.83	51.47
248	48.12	50.65	101.66	297.33	50.82
263	55.12	56.27	116.26	197.10	56.45
280	59.36	62.47	125.10	330.71	62.64
295	51.60	52.68	108.93	190.46	52.86
313	54.93	56.08	115.88	196.76	56.26
354	48.56	51.11	102.58	298.71	51.29
358	46.76	49.74	98.82	323.96	49.92
360	46.83	49.30	98.98	293.29	49.48
361	47.40	49.63	100.16	278.26	49.80

Table 9 --- PLENUM2 for Test D

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	50.81	51.30	107.28	126.53	51.48
367	49.93	51.02	105.45	190.78	51.19
372	49.72	50.46	105.00	156.58	50.63
373	49.39	50.04	104.32	146.38	50.22
377	53.46	53.72	112.80	92.53	53.90
382	49.03	51.34	103.57	283.08	51.51
406	66.56	67.20	140.12	145.07	67.37
432	51.84	54.27	109.42	291.13	54.44
450	60.53	63.36	127.54	314.87	63.53
471	50.92	51.42	107.51	126.67	51.59
472	49.15	51.46	103.82	283.42	51.64
475	50.84	51.09	107.34	90.23	51.26
482	52.08	52.08	109.92	0.00	52.25
484	51.95	51.95	109.65	0.00	52.12
486	51.32	51.32	108.34	0.00	51.50
487	-	-	-	-	-
488	51.52	51.52	108.77	0.00	51.70
490	50.97	50.97	107.61	0.00	51.14
491	50.34	50.59	106.30	89.79	50.76
492	52.95	52.95	111.75	0.00	53.13
493	50.91	50.91	107.48	0.00	51.08
494	52.43	52.43	110.65	0.00	52.60
495	53.66	53.66	113.23	0.00	53.84
496	50.82	50.82	107.31	0.00	51.00
497	53.12	53.12	112.09	0.00	53.29
498	60.86	60.86	128.23	0.00	61.03
499	64.17	64.17	135.14	0.00	64.34
500	63.36	63.36	133.45	0.00	63.54
502	68.35	68.35	143.85	0.00	68.52
504	71.15	71.15	149.69	0.00	71.32
506	69.08	69.08	145.38	0.00	69.26
507	58.62	59.39	123.56	159.39	59.56
508	67.43	67.43	141.94	0.00	67.61
509	58.57	58.85	123.45	96.85	59.03
510	69.50	69.50	146.26	0.00	69.68
512	66.13	66.13	139.22	0.00	66.30
520	69.00	69.00	145.20	0.00	69.17
524	73.80	73.80	155.22	0.00	73.98

Table 9 --- PLENUM2 for Test D

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	71.95	71.95	151.37	0.00	72.13
542	70.44	70.44	148.21	0.00	70.61
559	71.18	71.18	149.76	0.00	71.36
562	73.55	73.55	154.70	0.00	73.73
579	71.30	71.30	150.01	0.00	71.48
582	63.58	63.58	133.91	0.00	63.76
592	45.27	45.27	95.72	0.00	45.44
593	52.94	52.94	111.71	0.00	53.11
595	51.66	51.66	109.06	0.00	51.84
596	52.04	52.04	109.84	0.00	52.21
597	51.27	51.27	108.25	0.00	51.45
598	51.77	51.77	109.29	0.00	51.95
599	51.63	51.63	108.99	0.00	51.80
600	51.79	51.79	109.32	0.00	51.96

Table 10 --- PLENUM2 for Test E

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	48.65	49.67	102.78	184.72	49.84
6	46.84	49.84	99.01	324.27	50.01
15	48.80	49.82	103.09	185.02	50.00
26	46.81	49.80	98.94	324.16	49.98
34	47.81	50.87	101.02	327.66	51.04
47	48.63	49.65	102.74	184.68	49.83
59	47.41	50.43	100.18	326.25	50.61
71	48.20	49.21	101.83	183.82	49.38
83	49.50	50.53	104.54	186.38	50.71
106	46.10	49.05	97.46	321.64	49.22
110	45.49	48.40	96.18	319.46	48.57
115	48.35	49.36	102.15	184.12	49.54
124	46.88	49.88	99.08	324.40	50.05
129	48.71	49.73	102.89	184.83	49.90
135	49.30	50.33	104.12	185.99	50.50
148	47.47	50.50	100.32	326.47	50.68
161	51.50	52.58	108.71	190.26	52.75
177	52.23	53.32	110.24	191.66	53.50
182	49.49	52.65	104.53	333.47	52.83
198	53.74	57.17	113.39	347.76	57.34
210	46.41	49.37	98.09	322.73	49.55
214	45.79	48.71	96.80	320.52	48.89
218	44.64	47.50	94.42	316.43	47.67
221	49.74	50.78	105.05	186.86	50.96
223	49.64	50.38	104.84	156.46	50.56
230	48.92	51.50	103.34	299.84	51.67
236	48.46	51.01	102.37	298.40	51.18
238	47.35	50.37	100.05	326.03	50.54
243	48.63	49.65	102.73	184.68	49.82
248	47.25	49.74	99.85	294.60	49.91
263	52.81	53.91	111.44	192.75	54.08
280	56.90	59.89	119.99	323.71	60.06
295	50.67	51.73	106.98	188.66	51.90
313	58.17	59.38	122.62	202.69	59.58
354	47.98	50.51	101.38	296.91	50.68
358	46.73	49.72	98.78	323.88	49.89
360	47.69	50.20	100.76	295.98	50.37
361	50.36	52.72	106.33	286.91	52.90

Table 10 --- PLENUM2 for Test E

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	54.75	55.28	115.50	131.41	55.46
367	48.54	49.60	102.55	188.12	49.77
372	49.70	50.45	104.97	156.56	50.62
373	49.62	50.27	104.80	146.71	50.45
377	51.57	51.83	108.87	90.88	52.00
382	46.03	48.20	97.32	274.20	48.38
406	64.38	65.00	135.58	142.65	65.18
432	52.73	55.20	111.28	293.65	55.38
450	63.26	66.22	133.25	321.99	66.39
471	55.50	56.03	117.05	132.31	56.21
472	48.90	51.20	103.29	282.67	51.37
475	57.85	58.14	121.96	96.26	58.31
482	66.75	66.75	140.52	0.00	66.93
484	64.09	64.09	134.97	0.00	64.26
486	62.09	62.09	130.80	0.00	62.26
487	-	-	-	-	-
488	51.32	51.32	108.33	0.00	51.49
490	53.77	53.77	113.45	0.00	53.95
491	50.50	50.74	106.62	89.92	50.92
492	49.99	49.99	105.56	0.00	50.16
493	50.55	50.55	106.74	0.00	50.73
494	51.80	51.80	109.34	0.00	51.97
495	51.06	51.06	107.79	0.00	51.23
496	51.62	51.62	108.96	0.00	51.79
497	51.83	51.83	109.40	0.00	52.01
498	51.70	51.70	109.13	0.00	51.88
499	52.30	52.30	110.37	0.00	52.47
500	52.11	52.11	109.98	0.00	52.28
502	51.95	51.95	109.65	0.00	52.12
504	51.91	51.91	109.58	0.00	52.09
506	52.37	52.37	110.53	0.00	52.55
507	49.68	50.33	104.91	146.80	50.51
508	52.16	52.16	110.09	0.00	52.33
509	50.81	51.06	107.27	90.20	51.23
510	52.32	52.32	110.43	0.00	52.49
512	48.37	48.37	102.19	0.00	48.55
520	65.85	65.85	138.63	0.00	66.02
524	72.12	72.12	151.72	0.00	72.30

Table 10 --- PLENUM2 for Test E

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	71.05	71.05	149.47	0.00	71.22
542	70.87	70.87	149.10	0.00	71.04
559	70.21	70.21	147.72	0.00	70.38
562	74.60	74.60	156.90	0.00	74.78
579	73.50	73.50	154.59	0.00	73.67
582	69.14	69.14	145.49	0.00	69.31
592	62.00	62.00	130.62	0.00	62.18
593	65.08	65.08	137.04	0.00	65.26
595	69.27	69.27	145.77	0.00	69.45
596	66.52	66.52	140.05	0.00	66.70
597	66.46	66.46	139.92	0.00	66.64
598	66.61	66.61	140.22	0.00	66.78
599	69.17	69.17	145.57	0.00	69.35
600	69.54	69.54	146.33	0.00	69.71

Table 11 --- PLENUM2 for Test F

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	26.78	27.34	57.18	135.67	27.52
6	25.74	27.42	55.01	239.52	27.59
15	26.55	27.11	56.70	135.07	27.28
26	25.54	27.20	54.59	238.57	27.38
34	25.50	27.16	54.52	238.41	27.34
47	26.53	27.09	56.66	135.03	27.27
59	25.85	27.53	55.24	240.04	27.71
71	26.69	27.25	56.99	135.44	27.43
83	26.47	27.03	56.53	134.86	27.20
106	25.18	26.82	53.84	236.87	26.99
110	26.68	28.42	56.98	243.90	28.59
115	28.22	28.81	60.17	139.37	28.98
124	25.08	26.71	53.63	236.39	26.88
129	26.48	27.04	56.56	134.89	27.21
135	26.88	27.44	57.39	135.93	27.62
148	26.68	28.41	56.97	243.89	28.59
161	27.39	27.97	58.46	137.26	28.14
177	26.47	27.03	56.54	134.87	27.20
182	25.51	27.17	54.54	238.45	27.35
198	26.52	28.24	56.63	243.12	28.41
210	25.34	26.99	54.18	237.64	27.16
214	25.09	26.72	53.65	236.45	26.90
218	27.93	29.74	59.59	249.59	29.92
221	27.46	28.04	58.59	137.43	28.21
223	31.11	31.57	66.20	123.27	31.75
230	29.03	30.58	61.87	230.49	30.76
236	27.59	29.07	58.87	224.69	29.25
238	23.95	25.51	51.27	230.97	25.68
243	26.94	27.50	57.50	136.08	27.68
248	25.40	26.76	54.29	215.55	26.94
263	27.63	28.21	58.95	137.87	28.39
280	29.85	31.45	63.58	233.75	31.62
295	26.55	27.11	56.69	135.06	27.28
313	29.02	29.63	61.85	141.39	29.80
354	25.47	26.84	54.44	215.85	27.01
358	25.26	26.90	54.00	237.25	27.08
360	25.25	26.61	53.99	214.93	26.79
361	27.76	29.10	59.23	212.71	29.27

Table 11 --- PLENUM2 for Test F

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	31.23	31.53	66.45	99.00	31.70
367	32.38	33.09	68.85	153.82	33.27
372	31.95	32.43	67.96	124.95	32.60
373	31.66	32.08	67.35	117.46	32.26
377	32.76	32.91	69.64	72.48	33.09
382	24.64	25.83	52.71	200.38	26.00
406	33.21	33.54	70.60	102.12	33.71
432	26.57	27.85	56.75	208.11	28.03
450	31.48	32.99	66.99	226.54	33.16
471	28.08	28.35	59.88	93.86	28.52
472	25.90	27.14	55.33	205.43	27.32
475	29.24	29.38	62.31	68.51	29.56
482	34.41	34.41	73.09	0.00	34.59
484	34.01	34.01	72.26	0.00	34.19
486	34.03	34.03	72.29	0.00	34.20
487	33.24	33.24	70.65	0.00	33.41
488	33.78	33.78	71.77	0.00	33.95
490	33.77	33.77	71.76	0.00	33.95
491	33.20	33.36	70.56	72.96	33.53
492	34.50	34.50	73.27	0.00	34.67
493	32.96	32.96	70.06	0.00	33.13
494	33.25	33.25	70.68	0.00	33.43
495	33.72	33.72	71.66	0.00	33.90
496	32.29	32.29	68.67	0.00	32.46
497	33.54	33.54	71.29	0.00	33.72
498	36.30	36.30	77.03	0.00	36.47
499	37.08	37.08	78.66	0.00	37.26
500	35.34	35.34	75.03	0.00	35.51
502	35.91	35.91	76.22	0.00	36.08
504	33.35	33.35	70.88	0.00	33.52
506	28.16	28.16	60.06	0.00	28.33
507	25.92	26.27	55.38	106.45	26.44
508	30.23	30.23	64.37	0.00	30.41
509	28.00	28.13	59.71	67.04	28.30
510	28.33	28.99	61.80	0.00	29.17
512	24.27	24.27	51.94	0.00	24.44
520	36.78	36.78	73.04	0.00	36.95
524	36.12	36.12	73.66	0.00	36.29

Table 11 --- PLENUM2 for Test F

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	38.30	38.30	81.21	0.00	38.48
542	36.48	36.48	77.41	0.00	36.65
559	36.97	36.97	78.42	0.00	37.14
562	36.72	36.72	77.91	0.00	36.89
579	37.69	37.69	79.93	0.00	37.86
582	35.45	35.45	75.27	0.00	35.63
592	24.94	24.94	53.34	0.00	25.12
593	29.47	29.47	62.78	0.00	29.64
595	30.53	30.53	64.99	0.00	30.70
596	31.28	31.28	66.57	0.00	31.46
597	31.98	31.98	68.03	0.00	32.16
598	34.59	34.59	73.47	0.00	34.77
599	35.20	35.20	74.74	0.00	35.37
600	34.83	34.83	73.96	0.00	35.00

Table 12 --- PLENUM2 for Test G

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	46.77	47.02	98.83	182.04	47.20
6	43.89	46.68	94.22	317.21	46.85
15	45.74	46.69	98.14	181.37	46.86
26	44.05	46.85	94.56	317.80	47.02
34	43.84	46.63	94.11	317.03	46.80
47	45.39	46.33	97.40	180.65	46.51
59	44.34	47.16	95.16	318.85	47.33
71	45.84	46.79	98.34	181.56	46.96
83	45.16	46.09	96.90	180.16	46.27
106	42.91	45.64	92.14	313.59	45.81
110	45.49	48.38	97.60	323.03	48.55
115	49.12	50.13	105.28	188.19	50.31
124	43.18	45.93	92.72	314.60	46.10
129	45.65	46.60	97.94	181.18	46.77
135	45.41	46.35	97.42	180.67	46.52
148	44.50	47.33	95.50	319.43	47.50
161	46.99	47.96	100.77	183.91	48.13
177	45.55	46.49	97.73	180.97	46.67
182	43.25	46.00	92.85	314.84	46.17
198	45.90	48.81	98.46	324.50	48.98
210	42.36	45.06	90.98	311.54	45.23
214	42.77	45.49	91.84	313.06	45.66
218	47.11	50.10	101.03	328.85	50.28
221	47.24	48.22	101.30	184.42	48.39
223	53.71	54.50	115.01	164.86	54.67
230	51.06	53.73	109.40	309.63	53.90
236	48.44	50.97	103.86	301.49	51.15
238	43.48	46.25	93.35	315.71	46.42
243	46.28	47.24	99.27	182.46	47.41
248	43.47	45.74	93.32	285.40	45.92
263	46.98	47.95	100.75	183.89	48.12
280	49.89	52.49	106.91	306.00	52.66
295	45.83	46.78	98.31	181.54	46.95
313	49.79	50.82	106.70	189.53	50.99
354	44.06	46.36	94.57	287.35	46.54
358	43.56	46.34	93.53	316.01	46.51
360	44.73	47.07	96.00	289.57	47.25
361	47.31	49.51	101.44	280.82	49.68

Table 12 --- PLENUM2 for Test G

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	54.02	54.53	115.67	131.87	54.71
367	54.97	56.14	117.67	201.88	56.31
372	55.05	55.86	117.85	166.95	56.04
373	58.58	59.33	125.32	160.64	59.51
377	56.87	57.15	121.70	96.30	57.32
382	44.65	46.73	95.82	272.74	46.91
406	55.21	55.73	118.18	133.33	55.91
432	45.31	47.42	97.21	274.77	47.59
450	52.76	55.21	112.98	296.72	55.38
471	48.23	48.69	103.41	124.52	48.86
472	43.84	45.89	94.11	270.24	46.06
475	52.07	52.32	111.54	92.14	52.49
482	58.98	58.98	126.15	0.00	59.15
484	59.72	59.72	127.72	0.00	59.89
486	61.84	61.84	132.20	0.00	62.01
487	57.37	57.37	122.75	0.00	57.54
488	58.13	58.13	124.36	0.00	58.30
490	61.89	61.89	132.31	0.00	62.06
491	59.13	59.41	126.48	98.19	59.59
492	61.55	61.55	131.60	0.00	61.72
493	60.49	60.49	129.36	0.00	60.66
494	61.86	61.86	132.26	0.00	62.04
495	61.04	61.04	130.52	0.00	61.21
496	58.55	58.55	125.24	0.00	58.72
497	61.52	61.52	131.54	0.00	61.70
498	60.93	60.93	130.28	0.00	61.10
499	58.86	58.86	125.90	0.00	59.03
500	56.98	56.98	121.93	0.00	57.16
502	58.07	58.07	124.23	0.00	58.25
504	56.50	56.50	120.92	0.00	56.68
506	53.98	53.98	115.57	0.00	54.15
507	48.64	49.27	104.27	146.45	49.44
508	54.50	54.50	116.67	0.00	54.67
509	51.38	51.62	110.06	91.52	51.79
510	55.73	55.73	119.28	0.00	55.91
512	56.63	56.63	121.19	0.00	56.81
520	59.03	59.03	126.26	0.00	59.20
524	60.20	60.20	128.75	0.00	60.38

Table 12 --- PLENUM2 for Test G

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	58.94	58.94	126.08	0.00	59.12
542	58.38	58.38	124.89	0.00	58.56
559	59.93	59.93	128.17	0.00	60.10
562	61.74	61.74	131.99	0.00	61.91
579	59.74	59.74	127.76	0.00	59.91
582	59.43	59.43	127.10	0.00	59.60
592	57.78	57.78	123.61	0.00	57.95
593	56.17	56.17	120.22	0.00	56.35
595	55.57	55.57	118.93	0.00	55.74
596	54.63	54.63	116.94	0.00	54.80
597	52.74	52.74	112.96	0.00	52.92
598	54.16	54.16	115.96	0.00	54.33
599	57.17	57.17	122.33	0.00	57.35
600	58.16	58.16	124.43	0.00	58.34

Table 13 --- PLENUM2 for Test H

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	74.19	75.73	158.34	233.23	75.90
6	70.58	75.05	150.71	404.10	75.22
15	73.74	75.27	157.38	232.49	75.44
26	70.84	75.31	151.25	404.84	75.49
34	70.57	75.03	150.67	404.05	75.20
47	73.12	74.64	156.08	231.48	74.81
59	71.12	75.61	151.84	405.65	75.78
71	73.73	75.27	157.37	232.49	75.44
83	72.82	74.33	155.44	230.98	74.51
106	69.04	73.40	147.43	399.55	73.57
110	72.92	77.53	155.66	410.89	77.70
115	78.48	80.11	167.41	240.17	80.28
124	69.97	74.39	149.40	402.29	74.56
129	73.59	75.12	157.08	232.26	75.29
135	72.96	74.47	155.73	231.21	74.65
148	71.57	76.09	152.79	406.96	76.26
161	76.16	77.74	162.50	236.44	77.91
177	73.13	74.65	156.10	231.49	74.82
182	69.22	73.60	147.83	400.11	73.77
198	74.52	79.23	159.04	415.46	79.40
210	67.74	72.03	144.70	395.71	72.20
214	68.61	72.95	146.54	398.30	73.12
218	75.21	79.96	160.50	417.42	80.13
221	75.78	77.35	161.70	235.82	77.52
223	85.83	87.09	182.99	209.70	87.26
230	81.48	85.70	173.77	392.51	85.87
236	77.73	81.75	165.83	383.21	81.92
238	70.42	74.88	150.37	403.63	75.05
243	74.59	76.14	159.20	233.90	76.32
248	69.91	73.53	149.28	363.11	73.71
263	75.28	76.85	160.66	235.02	77.02
280	80.81	84.99	172.35	390.86	85.16
295	73.83	75.36	157.57	232.64	75.53
313	79.88	81.55	170.39	242.40	81.72
354	70.38	74.03	150.28	364.36	74.20
358	69.80	74.21	149.05	401.80	74.39
360	71.98	75.72	153.67	368.55	75.89
361	76.17	79.68	162.53	357.33	79.86

Table 13 --- PLENUM2 for Test H

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	87.26	88.08	186.01	168.17	88.26
367	88.25	90.09	188.10	255.86	90.27
372	88.20	89.50	188.00	212.66	89.67
373	93.38	94.56	198.96	202.69	94.73
377	91.49	91.93	194.96	122.24	92.10
382	72.77	76.13	155.33	349.15	76.30
406	89.03	89.87	189.76	169.89	90.04
432	72.96	76.33	155.73	349.62	76.50
450	85.78	89.73	182.87	379.53	89.90
471	78.11	78.85	166.64	158.97	79.02
472	70.45	73.70	150.42	343.47	73.88
475	83.89	84.29	178.87	117.02	84.47
482	94.98	94.98	202.35	0.00	95.15
484	96.20	96.20	204.92	0.00	96.37
486	99.23	99.23	211.35	0.00	99.41
487	92.18	92.18	196.42	0.00	92.36
488	93.95	93.95	200.15	0.00	94.12
490	98.75	98.75	210.32	0.00	98.92
491	95.09	95.55	202.58	124.63	95.72
492	99.32	99.32	211.52	0.00	99.49
493	96.75	96.75	206.09	0.00	96.92
494	98.78	98.78	210.39	0.00	98.95
495	97.83	97.83	208.38	0.00	98.01
496	94.85	94.85	202.07	0.00	95.02
497	97.02	97.02	206.65	0.00	97.19
498	96.75	96.75	206.09	0.00	96.92
499	94.41	94.41	201.13	0.00	94.58
500	90.89	90.89	193.69	0.00	91.07
502	94.49	94.49	201.31	0.00	94.67
504	94.29	94.29	200.89	0.00	94.47
506	90.48	90.48	192.81	0.00	90.65
507	79.71	80.72	170.03	187.29	80.89
508	93.21	93.21	198.60	0.00	93.38
509	82.29	82.69	175.49	115.90	82.86
510	91.00	91.00	193.92	0.00	91.17
512	94.36	94.36	201.02	0.00	94.53
520	94.51	94.51	201.34	0.00	94.68
524	97.62	97.62	207.93	0.00	97.79

Table 13 --- PLENUM2 for Test H

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	95.07	95.07	202.53	0.00	95.24
542	93.44	93.44	199.09	0.00	93.62
559	94.37	94.37	201.04	0.00	94.54
562	98.18	98.18	209.11	0.00	98.35
579	96.38	96.38	205.30	0.00	96.55
582	96.18	96.18	204.89	0.00	96.35
592	94.66	94.66	201.66	0.00	94.83
593	90.82	90.82	193.54	0.00	90.99
595	88.47	88.47	188.55	0.00	88.64
596	84.64	84.64	180.45	0.00	84.81
597	82.86	82.86	176.69	0.00	83.03
598	85.44	85.44	182.15	0.00	85.61
599	91.34	91.34	194.64	0.00	91.51
600	93.39	93.39	198.98	0.00	93.56

Table 14 --- PLENUM2 for Test I

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	70.46	71.93	150.47	227.07	72.10
6	67.16	71.41	143.48	394.00	71.58
15	69.98	71.44	149.45	226.26	71.61
26	67.26	71.52	143.69	394.30	71.69
34	66.95	71.18	143.02	393.35	71.35
47	69.49	70.93	148.40	225.43	71.10
59	67.54	71.82	144.29	395.14	71.99
71	70.04	71.50	149.57	226.36	71.67
83	69.14	70.58	147.67	224.84	70.75
106	65.68	69.84	140.35	389.55	70.01
110	69.15	73.52	147.69	399.91	73.70
115	74.66	76.21	159.35	234.02	76.38
124	66.23	70.42	141.50	391.19	70.59
129	69.95	71.40	149.38	226.20	71.57
135	69.35	70.79	148.10	225.19	70.96
148	67.81	72.09	144.84	395.92	72.27
161	72.31	73.81	154.37	230.15	73.98
177	69.51	70.96	148.46	225.47	71.13
182	65.91	70.08	140.83	390.23	70.25
198	70.77	75.24	151.11	404.65	75.41
210	64.26	68.33	137.34	385.22	68.50
214	65.22	69.34	139.36	388.13	69.51
218	71.61	76.14	152.90	407.12	76.31
221	71.97	73.46	153.65	229.58	73.63
223	81.41	82.60	173.64	204.09	82.77
230	77.41	81.42	165.17	382.43	81.59
236	73.77	77.60	157.47	373.19	77.77
238	66.82	71.05	142.75	392.97	71.22
243	70.79	72.26	151.17	227.62	72.44
248	66.42	69.86	141.90	353.80	70.04
263	71.66	73.15	153.00	229.07	73.32
280	76.76	80.74	163.80	380.81	80.91
295	70.20	71.65	149.90	226.62	71.83
313	75.83	77.41	161.83	235.93	77.58
354	66.87	70.34	142.85	355.01	70.51
358	66.42	70.62	141.90	391.76	70.79
360	68.29	71.84	145.87	358.84	72.01
361	72.43	75.77	154.62	348.34	75.94

Table 14 --- PLENUM2 for Test I

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	82.80	83.58	176.58	163.75	83.75
367	83.93	85.69	178.98	249.52	85.86
372	83.85	85.07	178.79	207.20	85.25
373	88.67	89.79	189.00	197.52	89.96
377	86.89	87.31	185.23	119.11	87.48
382	69.07	72.27	147.53	340.07	72.44
406	84.59	85.38	180.36	165.54	85.55
432	69.36	72.57	148.14	340.79	72.74
450	81.35	85.10	173.51	369.48	85.27
471	74.25	74.94	158.47	154.93	75.12
472	67.00	70.10	143.13	334.85	70.27
475	79.62	80.01	169.86	114.00	80.18
482	90.52	90.52	192.91	0.00	90.69
484	91.40	91.40	194.79	0.00	91.58
486	94.47	94.47	201.27	0.00	94.64
487	87.42	87.42	186.36	0.00	87.60
488	89.22	89.22	190.17	0.00	89.39
490	94.00	94.00	200.29	0.00	94.17
491	90.38	90.82	192.63	121.50	90.99
492	94.27	94.27	200.86	0.00	94.44
493	92.09	92.09	196.24	0.00	92.26
494	93.81	93.81	199.89	0.00	93.99
495	92.92	92.92	198.00	0.00	93.09
496	90.18	90.18	192.19	0.00	90.35
497	92.11	92.11	196.29	0.00	92.29
498	92.11	92.11	196.28	0.00	92.28
499	89.67	89.67	191.11	0.00	89.84
500	86.40	86.40	184.19	0.00	86.57
502	89.77	89.77	191.33	0.00	89.94
504	89.18	89.18	190.09	0.00	89.35
506	85.45	85.45	182.19	0.00	85.63
507	75.64	76.60	161.43	182.46	76.78
508	87.70	87.70	186.95	0.00	87.87
509	78.52	78.89	167.51	113.20	79.07
510	86.07	86.07	183.50	0.00	86.24
512	89.24	89.24	190.20	0.00	89.41
520	90.03	90.03	191.88	0.00	90.20
524	93.16	93.16	198.50	0.00	93.33

Table 14 --- PLENUM2 for Test I

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	90.38	90.38	192.61	0.00	90.55
542	88.68	88.68	189.02	0.00	88.85
559	89.72	89.72	191.23	0.00	89.90
562	93.35	93.35	198.91	0.00	93.52
579	91.62	91.62	195.24	0.00	91.79
582	91.40	91.40	194.79	0.00	91.58
592	90.01	90.01	191.84	0.00	90.19
593	86.30	86.30	183.98	0.00	86.47
595	84.32	84.32	179.79	0.00	84.49
596	81.13	81.13	173.03	0.00	81.30
597	78.52	78.52	167.53	0.00	78.70
598	81.31	81.31	173.42	0.00	81.48
599	86.84	86.84	185.12	0.00	87.01
600	88.90	88.90	189.49	0.00	89.07

Table 15 --- PLENUM2 for Test J

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	48.10	49.10	103.09	186.11	49.35
6	46.18	49.11	99.03	325.44	49.36
15	48.29	49.29	103.48	186.48	49.54
26	46.11	49.04	98.89	325.20	49.29
34	47.18	50.18	101.15	329.01	50.43
47	48.06	49.06	103.00	186.02	49.30
59	46.82	49.79	100.38	327.72	50.04
71	47.41	48.40	101.63	184.72	48.64
83	48.72	49.73	104.39	187.34	49.97
106	45.42	48.31	97.42	322.70	48.55
110	44.80	47.64	96.10	320.45	47.89
115	47.90	48.89	102.66	185.70	49.14
124	46.06	48.98	98.76	324.99	49.23
129	48.10	49.09	103.08	186.10	49.34
135	48.95	49.97	104.90	187.81	50.22
148	46.49	49.44	99.68	326.54	49.69
161	50.99	52.05	109.21	191.84	52.30
177	51.49	52.56	110.26	192.81	52.81
182	48.43	51.51	103.80	333.43	51.76
198	53.67	57.08	114.88	351.32	57.32
210	45.59	48.48	97.77	323.31	48.73
214	44.80	47.65	96.11	320.47	47.90
218	43.81	46.60	94.01	316.84	46.84
221	48.86	49.87	104.69	187.62	50.12
223	49.32	50.04	105.67	157.76	50.29
230	48.70	51.24	104.36	302.21	51.49
236	47.76	50.25	102.36	299.24	50.50
238	46.25	49.19	99.18	325.70	49.44
243	47.88	48.88	102.63	185.67	49.13
248	46.50	48.93	99.71	295.24	49.18
263	52.32	53.40	112.01	194.41	53.65
280	56.97	59.93	121.85	327.20	60.18
295	50.00	51.03	107.10	189.88	51.28
313	58.09	59.29	124.22	205.28	59.54
354	47.33	49.80	101.46	297.89	50.05
358	45.87	48.79	98.37	324.33	49.04
360	46.76	49.21	100.26	296.07	49.46
361	50.16	52.50	107.45	289.18	52.74

Table 15 --- PLENUM2 for Test J

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	54.65	55.17	116.95	132.61	55.41
367	48.44	49.47	103.81	189.50	49.72
372	49.56	50.29	106.18	158.15	50.54
373	49.59	50.23	106.24	147.83	50.48
377	51.66	51.90	110.62	91.75	52.15
382	44.98	47.08	96.50	273.71	47.33
406	64.26	64.87	137.28	143.95	65.11
432	52.21	54.63	111.78	295.08	54.88
450	63.69	66.64	136.07	326.29	66.89
471	54.69	55.21	117.03	132.66	55.45
472	48.30	50.55	103.51	283.71	50.80
475	57.68	57.96	123.36	96.96	58.20
482	66.91	66.91	142.88	0.00	67.16
484	64.30	64.30	137.35	0.00	64.54
486	62.26	62.26	133.04	0.00	62.50
487	50.49	50.49	108.14	0.00	50.74
488	51.52	51.52	110.33	0.00	51.77
490	53.45	53.45	114.41	0.00	53.70
491	50.54	50.78	108.26	90.75	51.03
492	50.02	50.02	107.14	0.00	50.26
493	50.46	50.46	108.09	0.00	50.71
494	51.61	51.61	110.51	0.00	51.86
495	51.00	51.00	109.23	0.00	51.25
496	51.64	51.64	110.58	0.00	51.89
497	51.82	51.82	110.95	0.00	52.07
498	51.78	51.78	110.87	0.00	52.03
499	52.34	52.34	112.06	0.00	52.59
500	52.06	52.06	111.47	0.00	52.31
502	51.96	51.96	111.26	0.00	52.21
504	51.67	51.67	110.64	0.00	51.92
506	52.26	52.26	111.89	0.00	52.51
507	49.11	49.74	105.23	147.12	49.99
508	51.90	51.90	111.14	0.00	52.15
509	50.24	50.48	107.62	90.48	50.73
510	51.92	51.92	111.16	0.00	52.16
512	47.75	47.75	102.35	0.00	48.00
520	66.06	66.06	141.09	0.00	66.31
524	72.31	72.31	154.32	0.00	72.56

Table 15 --- PLENUM2 for Test J

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	71.52	71.52	152.65	0.00	71.77
542	70.73	70.73	150.98	0.00	70.98
559	70.71	70.71	150.93	0.00	70.96
562	75.37	75.37	160.78	0.00	75.61
579	73.97	73.97	157.82	0.00	74.22
582	69.37	69.37	148.09	0.00	69.62
592	62.13	62.13	132.78	0.00	62.38
593	65.53	65.53	139.96	0.00	65.78
595	69.76	69.76	148.92	0.00	70.01
596	66.90	66.90	142.87	0.00	67.15
597	66.25	66.25	141.48	0.00	66.49
598	67.35	67.35	143.82	0.00	67.60
599	69.41	69.41	148.18	0.00	69.66
600	69.66	69.66	148.71	0.00	69.91

Table 16 --- PLENUM2 for Test K

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
1	24.89	25.40	53.96	132.35	25.58
6	24.04	25.59	52.15	233.81	25.76
15	24.55	25.06	53.24	131.41	25.23
26	24.02	25.57	52.12	233.73	25.74
34	23.93	25.48	51.93	233.30	25.65
47	24.11	24.61	52.30	130.20	24.78
59	23.40	24.91	50.80	230.66	25.08
71	24.78	25.29	53.73	132.05	25.47
83	25.07	25.59	54.34	132.84	25.76
106	22.89	24.37	49.72	228.12	24.54
110	26.60	28.31	57.58	246.04	28.48
115	30.70	31.34	66.24	147.45	31.51
124	23.66	25.19	51.36	231.96	25.36
129	25.39	25.92	55.02	133.72	26.09
135	25.16	25.68	54.53	133.09	25.86
148	25.00	26.62	54.20	238.49	26.79
161	26.16	26.70	56.64	135.77	26.87
177	25.10	25.62	54.40	132.91	25.79
182	23.68	25.21	51.40	232.07	25.38
198	23.84	25.38	51.74	232.84	25.55
210	24.49	26.07	53.12	236.03	26.25
214	22.72	24.19	49.37	227.29	24.36
218	30.51	32.46	65.84	263.66	32.64
221	27.66	28.23	59.82	139.73	28.41
223	37.29	37.84	80.18	136.70	38.01
230	35.92	37.81	77.27	259.05	37.98
236	33.83	35.62	72.87	251.37	35.79
238	26.79	28.52	57.98	246.94	28.69
243	28.05	28.63	60.64	140.74	28.80
248	24.80	26.12	53.77	215.09	26.30
263	27.04	27.60	58.50	138.10	27.77
280	29.92	31.51	64.60	236.31	31.68
295	25.06	25.58	54.33	132.82	25.76
313	25.39	25.91	55.01	133.69	26.08
354	24.38	25.68	52.89	213.27	25.86
358	25.51	27.15	55.26	240.90	27.32
360	24.73	26.05	53.63	214.79	26.22
361	25.42	26.63	55.08	205.47	26.80

Table 16 --- PLENUM2 for Test K

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
363	38.64	39.01	83.04	111.27	39.18
367	40.86	41.73	87.73	174.04	41.91
372	40.52	41.11	87.01	142.62	41.29
373	45.41	46.00	97.36	141.48	46.17
377	43.07	43.27	92.40	83.75	43.44
382	24.13	25.28	52.36	200.21	25.46
406	34.19	34.52	73.63	104.62	34.69
432	24.12	25.27	52.32	200.13	25.44
450	26.09	27.33	56.49	208.13	27.50
471	28.77	29.04	62.17	95.94	29.22
472	25.34	26.54	54.90	205.12	26.71
475	30.20	30.34	65.20	70.19	30.52
482	44.37	44.37	95.16	0.00	44.55
484	46.23	46.23	99.08	0.00	46.40
486	49.14	49.14	105.24	0.00	49.31
487	43.80	43.80	93.94	0.00	43.97
488	44.78	44.78	96.02	0.00	44.95
490	49.34	49.34	105.67	0.00	49.51
491	46.10	46.32	98.81	86.65	46.49
492	48.87	48.87	104.68	0.00	49.05
493	47.37	47.37	101.50	0.00	47.54
494	49.11	49.11	105.18	0.00	49.28
495	48.25	48.25	103.36	0.00	48.42
496	46.09	46.09	98.78	0.00	46.26
497	48.79	48.79	104.49	0.00	48.96
498	48.84	48.84	104.61	0.00	49.01
499	45.51	45.51	97.58	0.00	45.69
500	41.49	41.49	89.06	0.00	41.66
502	40.16	40.16	86.26	0.00	40.34
504	36.96	36.96	79.47	0.00	37.13
506	29.27	29.27	63.22	0.00	29.44
507	25.38	25.71	55.00	106.14	25.89
508	31.68	31.68	68.32	0.00	31.85
509	27.95	28.07	60.42	67.54	28.24
510	29.39	29.39	63.47	0.00	29.56
512	22.22	22.22	48.32	0.00	22.40
520	37.92	37.92	81.50	0.00	38.09
524	39.96	39.96	85.84	0.00	40.14

Table 16 --- PLENUM2 for Test K

OLC	Measured Pressure Inside USH (psig)	Corrected Pressure Outside USH (psig)	Corrected Head Outside USH (ft)	Calculated Assembly Flow (gpm)	Adjusted Plenum C-L Pressure (psig)
539	38.88	38.88	83.55	0.00	39.06
542	34.88	34.88	75.09	0.00	35.06
559	27.21	27.21	58.86	0.00	27.38
562	30.22	30.22	65.23	0.00	30.40
579	28.91	28.91	62.46	0.00	29.08
582	28.27	28.27	61.11	0.00	28.44
592	24.65	24.65	53.44	0.00	24.82
593	30.28	30.28	65.35	0.00	30.45
595	32.54	32.54	70.14	0.00	32.72
596	31.41	31.41	67.76	0.00	31.59
597	24.25	24.25	52.60	0.00	24.42
598	29.35	29.35	63.39	0.00	29.52
599	38.01	38.01	81.71	0.00	38.19
600	42.02	42.02	90.19	0.00	42.20

Table 17 Test A: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	Notes	
Plenum Inlet Temp 2 L1	C	A	21.80	0.11		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L2	C	A	22.37	0.12		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L3	C	A	22.00	0.13		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L4	C	A	21.73	0.15		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L5	C	A	21.77	0.09		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L6	C	A	21.98	0.09		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L1	C	A	22.04	0.07		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L2	C	A	22.55	0.10		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L3	C	A	21.89	0.12		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L4	C	A	21.82	0.14		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L5	C	A	21.74	0.09		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L6	C	A	22.03	0.10		CONDITIONALLY QUALIFIED		
Pump Suction Temp 1	C	A	21.89	0.27		CONDITIONALLY QUALIFIED		
Pump Suction Temp 2	C	A	22.23	0.30		CONDITIONALLY QUALIFIED		
Pump Suction Temp 3	C	A	21.91	0.28		CONDITIONALLY QUALIFIED		
Pump Suction Temp 4	C	A	21.67	0.27		CONDITIONALLY QUALIFIED		
Pump Suction Temp 5	C	A	21.66	0.26		CONDITIONALLY QUALIFIED		
Pump Suction Temp 6	C	A	21.88	0.27		CONDITIONALLY QUALIFIED		
Barometric Pressure	PSA	A	14.63	0.03		CONDITIONALLY QUALIFIED		
PS1	PSA	A	17.47	0.10	0.11	QUALIFIED		
PS2	PSA	A	17.60	0.07	0.11	QUALIFIED		
PS3	PSA	A	17.85	0.06	0.11	QUALIFIED		
PS4	PSA	A	18.05	0.08	0.11	QUALIFIED		
PS5	PSA	A	18.20	0.05	0.11	QUALIFIED		
PS6	PSA	A	17.75	0.05	0.11	QUALIFIED		
PD1	PSG	A	226.31	0.12	0.60	QUALIFIED		
PD2	PSG	A	227.25	0.08	0.60	QUALIFIED		
PD3	PSG	A	226.99	0.10	0.60	QUALIFIED		
PD4	PSG	A	230.98	0.14	0.60	QUALIFIED		
PD5	PSG	A	232.07	0.12	0.60	QUALIFIED		
PD6	PSG	A	225.05	0.09	0.60	QUALIFIED		
HI1	PSG	A	220.92	0.21	0.60	QUALIFIED		

Table 17 Test A: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
H2	PSG	A	221.82	0.17	0.60	QUALIFIED
H3	PSG	A	224.38	0.15	0.60	QUALIFIED
H4	PSG	A	225.97	0.16	0.60	QUALIFIED
H5	PSG	A	226.95	0.11	0.60	QUALIFIED
H6	PSG	A	220.09	0.18	0.60	QUALIFIED
HD1	PSG	A	68.96	0.10	0.60	QUALIFIED
HD2	PSG	A	69.46	0.10	0.60	QUALIFIED
HD3	PSG	A	66.45	0.08	0.60	QUALIFIED
HD4	PSG	A	70.00	0.12	0.60	QUALIFIED
HD5	PSG	A	70.39	0.12	0.60	QUALIFIED
HD6	PSG	A	65.30	0.16	0.60	QUALIFIED
ECS1	PSG	A	66.62	0.07		CONDITIONALLY QUALIFIED
ECS4	PSG	A	69.06	0.09		CONDITIONALLY QUALIFIED
Ultrasonic - Loop 1	GFM	A	19665	57.62		CONDITIONALLY QUALIFIED
Ultrasonic - Loop 5	GFM	A	19043	53.57		CONDITIONALLY QUALIFIED
Ultrasonic - Loop 6	GFM	A	18444	41.19		CONDITIONALLY QUALIFIED
Tank - LPH	PSG	A	16.74	0.02	0.10	QUALIFIED
Tank - GANG1	PSG	A	17.41	0.01	0.10	QUALIFIED
M60B-OLC493	PSG	A	17.09	0.02	0.10	QUALIFIED
M60B-OLC500	PSG	A	16.81	0.02	0.10	QUALIFIED
M60B-OLC600	PSG	A	16.82	0.02	0.10	QUALIFIED
PCL Pressure (System A)	PSG	A	47.24	0.07	1.65	QUALIFIED
PCL Pressure (System B)	PSG	A	46.78	0.27	0.90	QUALIFIED
OLC1	PSG	A	45.92	0.07		CONDITIONALLY QUALIFIED
OLC6	PSG	A	43.86	0.05		CONDITIONALLY QUALIFIED
OLC15	PSG	A	45.67	0.09		CONDITIONALLY QUALIFIED
OLC26	PSG	A	44.27	0.03		CONDITIONALLY QUALIFIED
OLC34	PSG	A	43.76	0.08		CONDITIONALLY QUALIFIED
OLC47	PSG	A	45.32	0.07		CONDITIONALLY QUALIFIED
OLC59	PSG	A	44.32	0.06		CONDITIONALLY QUALIFIED
OLC71	PSG	A	45.72	0.11		CONDITIONALLY QUALIFIED
OLC83	PSG	A	45.10	0.06		CONDITIONALLY QUALIFIED

Table 17							Test A: Results of Data Qualification of 1965 L-Area AC Flow Tests						

Table 17							Test A: Results of Data Qualification of 1985 L-Area AC Flow Tests			
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	Notes			
OLC373	PSG	A	57.73	0.22		CONDITIONALLY QUALIFIED				
OLC377	PSG	A	56.15	0.15		CONDITIONALLY QUALIFIED				
OLC382	PSG	A	44.49	0.12		CONDITIONALLY QUALIFIED				
OLC406	PSG	A	54.28	0.09		CONDITIONALLY QUALIFIED				
OLC432	PSG	A	45.21	0.04		CONDITIONALLY QUALIFIED				
OLC450	PSG	A	52.22	0.13		CONDITIONALLY QUALIFIED				
OLC471	PSG	A	48.02	0.14		CONDITIONALLY QUALIFIED				
OLC472	PSG	A	43.88	0.15		CONDITIONALLY QUALIFIED				
OLC475	PSG	A	51.33	0.08		CONDITIONALLY QUALIFIED				
OLC482	PSG	A	57.86	0.08		CONDITIONALLY QUALIFIED				
OLC484	PSG	A	58.66	0.16		CONDITIONALLY QUALIFIED				
OLC486	PSG	A	60.14	0.14		CONDITIONALLY QUALIFIED				
OLC487	PSG	A				FAILED				
OLC488	PSG	A	57.21	0.18		CONDITIONALLY QUALIFIED				
OLC490	PSG	A	60.79	0.18		CONDITIONALLY QUALIFIED				
OLC491	PSG	A	58.31	0.27		CONDITIONALLY QUALIFIED				
OLC492	PSG	A	60.54	0.17		CONDITIONALLY QUALIFIED				
OLC493	PSG	A	59.43	0.24		CONDITIONALLY QUALIFIED				
OLC494	PSG	A	60.67	0.29		CONDITIONALLY QUALIFIED				
OLC495	PSG	A	60.08	0.06		CONDITIONALLY QUALIFIED				
OLC496	PSG	A	57.61	0.14		CONDITIONALLY QUALIFIED				
OLC497	PSG	A	60.63	0.20		CONDITIONALLY QUALIFIED				
OLC498	PSG	A	60.15	0.18		CONDITIONALLY QUALIFIED				
OLC499	PSG	A	57.97	0.18		CONDITIONALLY QUALIFIED				
OLC500	PSG	A	56.63	0.24		CONDITIONALLY QUALIFIED				
OLC502	PSG	A	57.37	0.22		CONDITIONALLY QUALIFIED				
OLC504	PSG	A	55.52	0.15		CONDITIONALLY QUALIFIED				
OLC506	PSG	A	53.28	0.26		CONDITIONALLY QUALIFIED				
OLC507	PSG	A	48.45	0.14		CONDITIONALLY QUALIFIED				
OLC508	PSG	A	53.88	0.21		CONDITIONALLY QUALIFIED				
OLC509	PSG	A	50.99	0.09		CONDITIONALLY QUALIFIED				
OLC510	PSG	A	54.80	0.31		CONDITIONALLY QUALIFIED				

Table 17		Test A: Results of Data Qualification of 1985 L-Area AC Flow Tests					
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes
OLC512	PSG	A	55.73	0.29		CONDITIONALLY QUALIFIED	
OLC520	PSG	A	58.24	0.16		CONDITIONALLY QUALIFIED	
OLC524	PSG	A	59.42	0.23		CONDITIONALLY QUALIFIED	
OLC539	PSG	A	57.79	0.18		CONDITIONALLY QUALIFIED	
OLC542	PSG	A	57.67	0.17		CONDITIONALLY QUALIFIED	
OLC559	PSG	A	58.55	0.08		CONDITIONALLY QUALIFIED	
OLC562	PSG	A	60.65	0.23		CONDITIONALLY QUALIFIED	
OLC579	PSG	A	58.52	0.11		CONDITIONALLY QUALIFIED	
OLC582	PSG	A	58.46	0.11		CONDITIONALLY QUALIFIED	
OLC592	PSG	A	56.68	0.26		CONDITIONALLY QUALIFIED	
OLC593	PSG	A	55.47	0.11		CONDITIONALLY QUALIFIED	
OLC595	PSG	A	54.63	0.34		CONDITIONALLY QUALIFIED	
OLC596	PSG	A	53.76	0.88		CONDITIONALLY QUALIFIED	
OLC597	PSG	A	51.94	0.21		CONDITIONALLY QUALIFIED	
OLC598	PSG	A	53.32	0.15		CONDITIONALLY QUALIFIED	
OLC599	PSG	A	56.25	0.12		CONDITIONALLY QUALIFIED	
OLC600	PSG	A	57.38	0.22		CONDITIONALLY QUALIFIED	

Table 18							Test B: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	Notes						
Plenum Inlet Temp 2 L1	C	B				FAILED							
Plenum Inlet Temp 2 L2	C	B				FAILED							
Plenum Inlet Temp 2 L3	C	B				FAILED							
Plenum Inlet Temp 2 L4	C	B				FAILED							
Pk num Inlet Temp 2 L5	C	B				FAILED							
Pk num Inlet Temp 2 L6	C	B				FAILED							
Pk num Inlet Temp 1 L1	C	B	24.81	0.38		CONDITIONALLY QUALIFIED							
Pk num Inlet Temp 1 L2	C	B	25.09	0.41		CONDITIONALLY QUALIFIED							
Pk num Inlet Temp 1 L3	C	B	25.10	0.36		CONDITIONALLY QUALIFIED							
Pk num Inlet Temp 1 L4	C	B	25.09	0.39		CONDITIONALLY QUALIFIED							
Pk num Inlet Temp 1 L5	C	B	24.98	0.37		CONDITIONALLY QUALIFIED							
Pk num Inlet Temp 1 L6	C	B	25.06	0.31		CONDITIONALLY QUALIFIED							
Pump Suction Temp 1	C	B	25.00	0.40		CONDITIONALLY QUALIFIED							
Pump Suction Temp 2	C	B	25.24	0.43		CONDITIONALLY QUALIFIED							
Pump Suction Temp 3	C	B	25.27	0.38		CONDITIONALLY QUALIFIED							
Pump Suction Temp 4	C	B	25.17	0.41		CONDITIONALLY QUALIFIED							
Pump Suction Temp 5	C	B	25.11	0.38		CONDITIONALLY QUALIFIED							
Pump Suction Temp 6	C	B	25.18	0.33		CONDITIONALLY QUALIFIED							
Barometric Pressure	PSIA	B	14.73	0.00		CONDITIONALLY QUALIFIED							
PS1	PSIA	B	14.77	0.06	0.11	QUALIFIED							
PS2	PSIA	B	15.06	0.05	0.11	QUALIFIED							
PS3	PSIA	B	14.94	0.07	0.11	QUALIFIED							
PS4	PSIA	B	15.49	0.05	0.11	QUALIFIED							
PS5	PSIA	B	15.70	0.07	0.11	QUALIFIED							
PS6	PSIA	B	15.08	0.07	0.11	QUALIFIED							
PD1	PSG	B	194.47	0.21	0.60	QUALIFIED							
PD2	PSG	B	194.02	0.18	0.60	QUALIFIED							
PD3	PSG	B	190.54	0.18	0.60	QUALIFIED							
PD4	PSG	B	200.19	0.21	0.60	QUALIFIED							
PD5	PSG	B	199.93	0.21	0.60	QUALIFIED							
PD6	PSG	B	191.31	0.15	0.60	QUALIFIED							
H1	PSG	B	185.93	0.17	0.60	QUALIFIED							

Table 18								Test B: Results of Data Qualification of 1985 L-Area AC Flow Tests							

Table B: Results of Data Qualification of 1985 L-Area AC Flow Tests							
Test B:				Precision			
	Unit	Test	Average	2*Std Dev	Bias (Unit)	Label	Notes
Measurement Type							
OL C106	PSG	B	70.29	0.32		CONDITIONALLY QUALIFIED	
OL C110	PSG	B	74.79	0.61		CONDITIONALLY QUALIFIED	
OL C115	PSG	B	79.97	0.10		CONDITIONALLY QUALIFIED	
OL C124	PSG	B	71.24	0.10		CONDITIONALLY QUALIFIED	
OL C129	PSG	B	74.79	0.05		CONDITIONALLY QUALIFIED	
OL C135	PSG	B	74.37	0.16		CONDITIONALLY QUALIFIED	
OL C148	PSG	B	72.97	0.27		CONDITIONALLY QUALIFIED	
OL C161	PSG	B	77.23	0.25		CONDITIONALLY QUALIFIED	
OL C177	PSG	B	74.65	0.23		CONDITIONALLY QUALIFIED	
OL C182	PSG	B	70.81	0.20		CONDITIONALLY QUALIFIED	
OL C198	PSG	B	74.84	0.04		CONDITIONALLY QUALIFIED	
OL C210	PSG	B	69.35	0.20		CONDITIONALLY QUALIFIED	
OL C214	PSG	B	70.11	0.26		CONDITIONALLY QUALIFIED	
OL C218	PSG	B	77.45	0.47		CONDITIONALLY QUALIFIED	
OL C221	PSG	B	77.24	0.09		CONDITIONALLY QUALIFIED	
OL C223	PSG	B	86.60	0.13		CONDITIONALLY QUALIFIED	
OL C230	PSG	B	82.37	0.20		CONDITIONALLY QUALIFIED	
OL C236	PSG	B	78.54	0.20		CONDITIONALLY QUALIFIED	
OL C238	PSG	B	71.26	0.13		CONDITIONALLY QUALIFIED	
OL C243	PSG	B	75.69	0.32		CONDITIONALLY QUALIFIED	
OL C248	PSG	B	71.20	0.15		CONDITIONALLY QUALIFIED	
OL C263	PSG	B	77.71	0.25		CONDITIONALLY QUALIFIED	
OL C280	PSG	B	81.72	0.32		CONDITIONALLY QUALIFIED	
OL C295	PSG	B	75.24	0.11		CONDITIONALLY QUALIFIED	
OL C313	PSG	B	80.97	0.11		CONDITIONALLY QUALIFIED	
OL C354	PSG	B	71.77	0.14		CONDITIONALLY QUALIFIED	
OL C358	PSG	B	71.69	0.01		CONDITIONALLY QUALIFIED	
OL C360	PSG	B	73.24	0.17		CONDITIONALLY QUALIFIED	
OL C361	PSG	B	77.60	0.11		CONDITIONALLY QUALIFIED	
OL C363	PSG	B	87.54	0.08		CONDITIONALLY QUALIFIED	
OL C367	PSG	B	88.71	0.13		CONDITIONALLY QUALIFIED	
OL C372	PSG	B	88.99	0.13		CONDITIONALLY QUALIFIED	

Table 18 Test B: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	Notes	
Ol C373	PSG	B	94.07	0.17		CONDITIONALLY QUALIFIED		
Ol C377	PSG	B	91.98	0.91		CONDITIONALLY QUALIFIED		
Ol C382	PSG	B	73.75	0.14		CONDITIONALLY QUALIFIED		
Ol C406	PSG	B	89.93	0.22		CONDITIONALLY QUALIFIED		
Ol C432	PSG	B	74.28	0.14		CONDITIONALLY QUALIFIED		
Ol C450	PSG	B	86.07	0.40		CONDITIONALLY QUALIFIED		
Ol C471	PSG	B	79.14	0.16		CONDITIONALLY QUALIFIED		
Ol C472	PSG	B	71.81	0.04		CONDITIONALLY QUALIFIED		
Ol C475	PSG	B	84.35	0.18		CONDITIONALLY QUALIFIED		
Ol C482	PSG	B	95.61	0.31		CONDITIONALLY QUALIFIED		
Ol C484	PSG	B	96.35	0.11		CONDITIONALLY QUALIFIED		
Ol C486	PSG	B	98.52	0.47		CONDITIONALLY QUALIFIED		
Ol C487	PSG	B				FAILED		
Ol C488	PSG	B	94.49	0.46		CONDITIONALLY QUALIFIED		
Ol C490	PSG	B	99.25	0.09		CONDITIONALLY QUALIFIED		
Ol C491	PSG	B	95.73	0.57		CONDITIONALLY QUALIFIED		
Ol C492	PSG	B	99.39	0.26		CONDITIONALLY QUALIFIED		
Ol C493	PSG	B	97.35	0.31		CONDITIONALLY QUALIFIED		
Ol C494	PSG	B	99.33	0.08		CONDITIONALLY QUALIFIED		
Ol C495	PSG	B	98.13	0.46		CONDITIONALLY QUALIFIED		
Ol C496	PSG	B	94.88	1.01		CONDITIONALLY QUALIFIED		
Ol C497	PSG	B	98.28	0.41		CONDITIONALLY QUALIFIED		
Ol C498	PSG	B	98.21	0.18		CONDITIONALLY QUALIFIED		
Ol C499	PSG	B	95.11	0.45		CONDITIONALLY QUALIFIED		
Ol C500	PSG	B	92.63	0.18		CONDITIONALLY QUALIFIED		
Ol C502	PSG	B	95.15	0.13		CONDITIONALLY QUALIFIED		
Ol C504	PSG	B	94.21	0.37		CONDITIONALLY QUALIFIED		
Ol C506	PSG	B	90.56	0.39		CONDITIONALLY QUALIFIED		
Ol C507	PSG	B	80.68	0.08		CONDITIONALLY QUALIFIED		
Ol C508	PSG	B	91.74	0.06		CONDITIONALLY QUALIFIED		
Ol C509	PSG	B	83.63	0.29		CONDITIONALLY QUALIFIED		
Ol C510	PSG	B	91.01	0.21		CONDITIONALLY QUALIFIED		

Table 18 Test B: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
OL C512	PSG	B	94.21	0.63		CONDITIONALLY QUALIFIED
OL C520	PSG	B	95.79	0.11		CONDITIONALLY QUALIFIED
OL C524	PSG	B	98.01	0.24		CONDITIONALLY QUALIFIED
OL C539	PSG	B	95.54	0.18		CONDITIONALLY QUALIFIED
OL C542	PSG	B	94.04	0.19		CONDITIONALLY QUALIFIED
OL C559	PSG	B	94.69	0.60		CONDITIONALLY QUALIFIED
OL C562	PSG	B	98.22	0.18		CONDITIONALLY QUALIFIED
OL C579	PSG	B	96.20	0.30		CONDITIONALLY QUALIFIED
OL C582	PSG	B	96.42	0.55		CONDITIONALLY QUALIFIED
OL C592	PSG	B	94.87	0.17		CONDITIONALLY QUALIFIED
OL C593	PSG	B	91.52	0.16		CONDITIONALLY QUALIFIED
OL C595	PSG	B	89.81	0.35		CONDITIONALLY QUALIFIED
OL C596	PSG	B	86.82	0.14		CONDITIONALLY QUALIFIED
OL C597	PSG	B	84.65	0.23		CONDITIONALLY QUALIFIED
OL C598	PSG	B	87.19	0.18		CONDITIONALLY QUALIFIED
OL C599	PSG	B	92.39	0.28		CONDITIONALLY QUALIFIED
OL C600	PSG	B	94.25	0.39		CONDITIONALLY QUALIFIED

Table 19 Test C: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
Plenum Inlet Temp 2 L1	C	C	22.45	0.23		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L2	C	C	23.00	0.20		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L3	C	C	22.93	0.19		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L4	C	C	22.61	0.20		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L5	C	C	22.41	0.23		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L6	C	C	22.51	0.23		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L1	C	C	21.81	0.23		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L2	C	C	22.72	0.21		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L3	C	C	22.05	0.20		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L4	C	C	21.97	0.20		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L5	C	C	21.52	0.24		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L6	C	C	21.84	0.24		CONDITIONALLY QUALIFIED		
Pump Suction Temp 1	C	C	22.37	0.22		CONDITIONALLY QUALIFIED		
Pump Suction Temp 2	C	C	22.92	0.22		CONDITIONALLY QUALIFIED		
Pump Suction Temp 3	C	C	22.70	0.19		CONDITIONALLY QUALIFIED		
Pump Suction Temp 4	C	C	22.44	0.25		CONDITIONALLY QUALIFIED		
Pump Suction Temp 5	C	C	22.18	0.22		CONDITIONALLY QUALIFIED		
Pump Suction Temp 6	C	C	22.44	0.80		CONDITIONALLY QUALIFIED		
Barometric Pressure	PSIA	C	14.64	0.06		CONDITIONALLY QUALIFIED		
PS1	PSIA	C	14.67	0.10	0.11	QUALIFIED		
PS2	PSIA	C	14.64	0.09	0.11	QUALIFIED		
PS3	PSIA	C	14.64	0.11	0.11	QUALIFIED		
PS4	PSIA	C	15.05	0.09	0.11	QUALIFIED		
PS5	PSIA	C	15.21	0.11	0.11	QUALIFIED		
PS6	PSIA	C	14.74	0.11	0.11	QUALIFIED		
PD1	PSG	C	191.79	0.20	0.60	QUALIFIED		
PD2	PSG	C	191.16	0.11	0.60	QUALIFIED		
PD3	PSG	C	188.49	0.16	0.60	QUALIFIED		
PD4	PSG	C	197.63	0.17	0.60	QUALIFIED		
PD5	PSG	C	197.37	0.12	0.60	QUALIFIED		
PD6	PSG	C	188.68	0.19	0.60	QUALIFIED		
HI1	PSG	C	182.90	0.16	0.60	QUALIFIED		

Table 19 Test C: Results of Data Qualification of 1985 L-Area AC Flow Tests							
				Precision			
Measurement Type	Unit	Test	Average	2*Std Dev	Bias (Unit)	Label	Notes
H12	PSG	C	182.28	0.16	0.60	QUALIFIED	
H13	PSG	C	183.86	0.09	0.60	QUALIFIED	
H14	PSG	C	189.09	0.14	0.60	QUALIFIED	
H15	PSG	C	188.73	0.15	0.60	QUALIFIED	
H16	PSG	C	180.12	0.13	0.60	QUALIFIED	
HD1	PSG	C	104.08	0.14	0.60	QUALIFIED	
HD2	PSG	C	105.22	0.19	0.60	QUALIFIED	
HD3	PSG	C	97.86	0.13	0.60	QUALIFIED	
HD4	PSG	C	104.83	0.10	0.60	QUALIFIED	
HD5	PSG	C	105.85	0.18	0.60	QUALIFIED	
HD6	PSG	C	97.81	0.12	0.60	QUALIFIED	
EC51	PSG	C	100.29	0.24		CONDITIONALLY QUALIFIED	
EC54	PSG	C	102.74	0.14		CONDITIONALLY QUALIFIED	
Ultrasonic - Loop 1	GPM	C	24848	41.63		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset
Ultrasonic - Loop 3	GPM	C	24493	45.02		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset
Ultrasonic - Loop 6	GPM	C	23598	46.33		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset
Tank - LPH	PSG	C	16.42	0.03	0.10	QUALIFIED	
Tank - GANG1	PSG	C	17.52	0.01	0.10	QUALIFIED	
M60B-OLC493	PSG	C	17.03	0.01	0.10	QUALIFIED	
M60B-OLC500	PSG	C	16.55	0.00	0.10	QUALIFIED	
M60B-OLC600	PSG	C	16.55	0.03	0.10	QUALIFIED	
PCL Pressure (System A)	PSG	C	73.62	0.12	1.65	QUALIFIED	
PCL Pressure (System B)	PSG	C	73.28	0.31	0.90	QUALIFIED	
OLC1	PSG	C	71.94	0.09		CONDITIONALLY QUALIFIED	
OLC6	PSG	C	68.69	0.08		CONDITIONALLY QUALIFIED	
OLC15	PSG	C	71.49	0.15		CONDITIONALLY QUALIFIED	
OLC26	PSG	C	68.87	0.10		CONDITIONALLY QUALIFIED	
OLC34	PSG	C	68.52	0.10		CONDITIONALLY QUALIFIED	
OLC47	PSG	C	70.92	0.14		CONDITIONALLY QUALIFIED	
OLC59	PSG	C	69.19	0.18		CONDITIONALLY QUALIFIED	
OLC71	PSG	C	71.54	0.06		CONDITIONALLY QUALIFIED	
OLC83	PSG	C	70.56	0.14		CONDITIONALLY QUALIFIED	

Table 19 Test C: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
OLC106	PSG	C	66.96	0.12		CONDITIONALLY QUALIFIED
OLC110	PSG	C	71.32	0.28		CONDITIONALLY QUALIFIED
OLC115	PSG	C	76.24	0.38		CONDITIONALLY QUALIFIED
OLC124	PSG	C	67.96	0.18		CONDITIONALLY QUALIFIED
OLC129	PSG	C	71.35	0.11		CONDITIONALLY QUALIFIED
OLC135	PSG	C	71.00	0.10		CONDITIONALLY QUALIFIED
OLC148	PSG	C	69.86	0.28		CONDITIONALLY QUALIFIED
OLC161	PSG	C	73.71	0.17		CONDITIONALLY QUALIFIED
OLC177	PSG	C	71.17	0.19		CONDITIONALLY QUALIFIED
OLC182	PSG	C	67.76	0.29		CONDITIONALLY QUALIFIED
OLC198	PSG	C	71.58	0.09		CONDITIONALLY QUALIFIED
OLC210	PSG	C	66.25	0.14		CONDITIONALLY QUALIFIED
OLC214	PSG	C	67.10	0.18		CONDITIONALLY QUALIFIED
OLC218	PSG	C	73.71	0.36		CONDITIONALLY QUALIFIED
OLC221	PSG	C	73.76	0.26		CONDITIONALLY QUALIFIED
OLC223	PSG	C	82.56	0.36		CONDITIONALLY QUALIFIED
OLC230	PSG	C	78.64	0.53		CONDITIONALLY QUALIFIED
OLC236	PSG	C	75.10	0.24		CONDITIONALLY QUALIFIED
OLC238	PSG	C	68.12	0.24		CONDITIONALLY QUALIFIED
OLC243	PSG	C	72.14	0.12		CONDITIONALLY QUALIFIED
OLC248	PSG	C	67.98	0.07		CONDITIONALLY QUALIFIED
OLC263	PSG	C	74.11	0.35		CONDITIONALLY QUALIFIED
OLC280	PSG	C	78.15	0.40		CONDITIONALLY QUALIFIED
OLC295	PSG	C	71.84	0.14		CONDITIONALLY QUALIFIED
OLC313	PSG	C	77.10	0.36		CONDITIONALLY QUALIFIED
OLC354	PSG	C	68.47	0.13		CONDITIONALLY QUALIFIED
OLC358	PSG	C	68.27	0.24		CONDITIONALLY QUALIFIED
OLC360	PSG	C	69.82	0.05		CONDITIONALLY QUALIFIED
OLC361	PSG	C	73.67	0.36		CONDITIONALLY QUALIFIED
OLC363	PSG	C	83.36	0.33		CONDITIONALLY QUALIFIED
OLC367	PSG	C	84.31	0.12		CONDITIONALLY QUALIFIED
OLC372	PSG	C	84.81	0.23		CONDITIONALLY QUALIFIED

Table 19								Test C: Results of Data Qualification of 1985 L-Area AC Flow Tests				
Measurement Type	Unit	Test	Average	Precision	2*Std Dev	Bias (Unit)	Label	Notes				
OLC373	PSG	C	89.69		0.19		CONDITIONALLY QUALIFIED					
OLC377	PSG	C	87.22		0.63		CONDITIONALLY QUALIFIED					
OLC382	PSG	C	70.22		0.42		CONDITIONALLY QUALIFIED					
OLC406	PSG	C	85.80		0.19		CONDITIONALLY QUALIFIED					
OLC432	PSG	C	70.69		0.20		CONDITIONALLY QUALIFIED					
OLC450	PSG	C	81.95		0.32		CONDITIONALLY QUALIFIED					
OLC471	PSG	C	75.49		0.23		CONDITIONALLY QUALIFIED					
OLC472	PSG	C	68.37		0.12		CONDITIONALLY QUALIFIED					
OLC475	PSG	C	80.34		0.29		CONDITIONALLY QUALIFIED					
OLC482	PSG	C	91.09		0.56		CONDITIONALLY QUALIFIED					
OLC484	PSG	C	91.71		0.28		CONDITIONALLY QUALIFIED					
OLC486	PSG	C	93.71		0.32		CONDITIONALLY QUALIFIED					
OLC487	PSG	C	87.80		0.27		CONDITIONALLY QUALIFIED					
OLC488	PSG	C	89.63		0.19		CONDITIONALLY QUALIFIED					
OLC490	PSG	C	94.48		0.39		CONDITIONALLY QUALIFIED					
OLC491	PSG	C	90.86		0.48		CONDITIONALLY QUALIFIED					
OLC492	PSG	C	94.51		0.39		CONDITIONALLY QUALIFIED					
OLC493	PSG	C	92.68		0.20		CONDITIONALLY QUALIFIED					
OLC494	PSG	C	94.57		0.08		CONDITIONALLY QUALIFIED					
OLC495	PSG	C	93.62		0.27		CONDITIONALLY QUALIFIED					
OLC496	PSG	C	89.81		0.83		CONDITIONALLY QUALIFIED					
OLC497	PSG	C	93.75		0.45		CONDITIONALLY QUALIFIED					
OLC498	PSG	C	93.55		0.11		CONDITIONALLY QUALIFIED					
OLC499	PSG	C	90.39		0.15		CONDITIONALLY QUALIFIED					
OLC500	PSG	C	88.25		0.25		CONDITIONALLY QUALIFIED					
OLC502	PSG	C	90.80		0.19		CONDITIONALLY QUALIFIED					
OLC504	PSG	C	89.21		0.52		CONDITIONALLY QUALIFIED					
OLC506	PSG	C	86.08		0.56		CONDITIONALLY QUALIFIED					
OLC507	PSG	C	76.70		0.37		CONDITIONALLY QUALIFIED					
OLC508	PSG	C	86.72		0.56		CONDITIONALLY QUALIFIED					
OLC509	PSG	C	79.92		0.20		CONDITIONALLY QUALIFIED					
OLC510	PSG	C	86.66		0.39		CONDITIONALLY QUALIFIED					

Table 19 Test C: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OIC512	PSG	C	89.52	0.31		CONDITIONALLY QUALIFIED		
OIC520	PSG	C	91.51	0.24		CONDITIONALLY QUALIFIED		
OIC524	PSG	C	93.53	0.30		CONDITIONALLY QUALIFIED		
OIC539	PSG	C	91.03	0.18		CONDITIONALLY QUALIFIED		
OIC542	PSG	C	89.61	0.22		CONDITIONALLY QUALIFIED		
OIC559	PSG	C	90.65	0.62		CONDITIONALLY QUALIFIED		
OIC562	PSG	C	93.58	0.40		CONDITIONALLY QUALIFIED		
OIC579	PSG	C	91.64	0.26		CONDITIONALLY QUALIFIED		
OIC582	PSG	C	91.62	0.27		CONDITIONALLY QUALIFIED		
OIC592	PSG	C	90.19	0.34		CONDITIONALLY QUALIFIED		
OIC593	PSG	C	87.09	0.29		CONDITIONALLY QUALIFIED		
OIC595	PSG	C	85.37	0.25		CONDITIONALLY QUALIFIED		
OIC596	PSG	C	83.01	0.48		CONDITIONALLY QUALIFIED		
OIC597	PSG	C	80.91	0.53		CONDITIONALLY QUALIFIED		
OIC598	PSG	C	83.26	0.70		CONDITIONALLY QUALIFIED		
OIC599	PSG	C	88.64	0.47		CONDITIONALLY QUALIFIED		
OIC600	PSG	C	89.82	0.35		CONDITIONALLY QUALIFIED		

Table 20 Test D: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	Notes	
Plenum Inlet Temp 2 L1	C	D	22.40	0.04		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L2	C	D	22.90	0.06		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L3	C	D	22.84	0.06		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L4	C	D	22.59	0.04		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L5	C	D	22.40	0.03		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L6	C	D	22.13	0.03		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L1	C	D	21.93	0.03		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L2	C	D	22.67	0.04		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L3	C	D	22.04	0.04		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L4	C	D	22.00	0.06		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L5	C	D	21.69	0.04		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L6	C	D	22.10	0.09		CONDITIONALLY QUALIFIED		
Pump Suction Temp 1	C	D	22.27	0.04		CONDITIONALLY QUALIFIED		
Pump Suction Temp 2	C	D	22.77	0.02		CONDITIONALLY QUALIFIED		
Pump Suction Temp 3	C	D	22.58	0.06		CONDITIONALLY QUALIFIED		
Pump Suction Temp 4	C	D	22.35	0.02		CONDITIONALLY QUALIFIED		
Pump Suction Temp 5	C	D	22.11	0.05		CONDITIONALLY QUALIFIED		
Pump Suction Temp 6	C	D	21.84	0.03		CONDITIONALLY QUALIFIED		
Barometric Pressure	PSIA	D	14.62	0.01		CONDITIONALLY QUALIFIED		
PS1	PSIA	D	13.39	0.05	0.11	QUALIFIED		
PS2	PSIA	D	13.82	0.06	0.11	QUALIFIED		
PS3	PSIA	D	13.61	0.15	0.11	QUALIFIED		
PS4	PSIA	D	14.33	0.05	0.11	QUALIFIED		
PS5	PSIA	D	14.58	0.06	0.11	QUALIFIED		
PS6	PSIA	D	22.80	0.07	0.11	QUALIFIED		
PD1	PSIG	D	181.06	0.14	0.60	QUALIFIED		
PD2	PSIG	D	181.35	0.10	0.60	QUALIFIED		
PD3	PSIG	D	178.13	0.10	0.60	QUALIFIED		
PD4	PSIG	D	188.41	0.21	0.60	QUALIFIED		
PD5	PSIG	D	187.69	0.10	0.60	QUALIFIED		
PD6	PSIG	D	41.16	0.09	0.60	QUALIFIED		
H11	PSIG	D	171.16	0.22	0.60	QUALIFIED		

Table 20 Test D: Results of Data Qualification of 1985 L-Area AC Flow Tests									
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes		
H12	PSG	D	171.56	0.19	0.60	QUALIFIED			
H13	PSG	D	173.17	0.08	0.60	QUALIFIED			
H14	PSG	D	178.99	0.13	0.60	QUALIFIED			
H15	PSG	D	178.06	0.15	0.60	QUALIFIED			
H16	PSG	D	42.98	0.14	0.60	QUALIFIED			
HD1	PSG	D	81.05	0.18	0.60	QUALIFIED			
HD2	PSG	D	84.22	0.13	0.60	QUALIFIED			
HD3	PSG	D	76.75	0.18	0.60	QUALIFIED			
HD4	PSG	D	83.65	0.11	0.60	QUALIFIED			
HD5	PSG	D	83.96	0.13	0.60	QUALIFIED			
HD6	PSG	D	64.48	0.12	0.60	QUALIFIED			
ECS1	PSG	D	76.23	0.15		CONDITIONALLY QUALIFIED			
ECS4	PSG	D	81.00	0.15		CONDITIONALLY QUALIFIED			
Ultrasonic - Loop 1	GFM	D	262.08	86.49		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset		
Ultrasonic - Loop 4	GFM	D	252.34	57.62		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset		
Ultrasonic - Loop 5	GFM	D	268.98	16.73		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset		
Tank - LPH	PSG	D	16.49	0.01	0.10	QUALIFIED			
Tank - GANG1	PSG	D	17.40	0.00	0.10	QUALIFIED			
M60B-OLC493	PSG	D	17.10	0.01	0.10	QUALIFIED			
M60B-OLC500	PSG	D	16.53	0.00	0.10	QUALIFIED			
M60B-OLC600	PSG	D	17.17	0.00	0.10	QUALIFIED			
PCL Pressure (System A)	PSG	D	50.74	0.12	1.65	QUALIFIED			
PCL Pressure (System B)	PSG	D	50.48	0.57	0.90	QUALIFIED			
OLC1	PSG	D	49.11	0.04		CONDITIONALLY QUALIFIED			
OLC6	PSG	D	46.81	0.11		CONDITIONALLY QUALIFIED			
OLC15	PSG	D	49.82	0.25		CONDITIONALLY QUALIFIED			
OLC26	PSG	D	47.64	0.07		CONDITIONALLY QUALIFIED			
OLC34	PSG	D	46.50	0.09		CONDITIONALLY QUALIFIED			
OLC47	PSG	D	49.38	0.02		CONDITIONALLY QUALIFIED			
OLC59	PSG	D	46.35	0.07		CONDITIONALLY QUALIFIED			
OLC71	PSG	D	51.16	0.15		CONDITIONALLY QUALIFIED			
OLC83	PSG	D	48.67	0.09		CONDITIONALLY QUALIFIED			

Table 20 Test D: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OLC106	PSG	D	47.32	0.07		CONDITIONALLY QUALIFIED		
OLC110	PSG	D	47.64	0.06		CONDITIONALLY QUALIFIED		
OLC115	PSG	D	48.28	0.08		CONDITIONALLY QUALIFIED		
OLC124	PSG	D	44.88	0.08		CONDITIONALLY QUALIFIED		
OLC129	PSG	D	48.89	0.04		CONDITIONALLY QUALIFIED		
OLC135	PSG	D	50.51	0.12		CONDITIONALLY QUALIFIED		
OLC148	PSG	D	51.68	0.25		CONDITIONALLY QUALIFIED		
OLC161	PSG	D	53.79	0.04		CONDITIONALLY QUALIFIED		
OLC177	PSG	D	50.86	0.09		CONDITIONALLY QUALIFIED		
OLC182	PSG	D	46.32	0.01		CONDITIONALLY QUALIFIED		
OLC198	PSG	D	51.77	0.10		CONDITIONALLY QUALIFIED		
OLC210	PSG	D	47.48	0.05		CONDITIONALLY QUALIFIED		
OLC214	PSG	D	47.08	0.16		CONDITIONALLY QUALIFIED		
OLC218	PSG	D	48.07	0.08		CONDITIONALLY QUALIFIED		
OLC221	PSG	D	48.61	0.23		CONDITIONALLY QUALIFIED		
OLC223	PSG	D	50.23	0.02		CONDITIONALLY QUALIFIED		
OLC230	PSG	D	47.20	0.17		CONDITIONALLY QUALIFIED		
OLC236	PSG	D	47.47	0.26		CONDITIONALLY QUALIFIED		
OLC238	PSG	D	43.28	0.15		CONDITIONALLY QUALIFIED		
OLC243	PSG	D	50.24	0.03		CONDITIONALLY QUALIFIED		
OLC248	PSG	D	48.12	0.15		CONDITIONALLY QUALIFIED		
OLC263	PSG	D	55.12	0.18		CONDITIONALLY QUALIFIED		
OLC280	PSG	D	59.36	0.32		CONDITIONALLY QUALIFIED		
OLC295	PSG	D	51.60	0.12		CONDITIONALLY QUALIFIED		
OLC313	PSG	D	54.93	0.45		CONDITIONALLY QUALIFIED		
OLC354	PSG	D	48.56	0.07		CONDITIONALLY QUALIFIED		
OLC358	PSG	D	46.76	0.24		CONDITIONALLY QUALIFIED		
OLC360	PSG	D	46.83	0.18		CONDITIONALLY QUALIFIED		
OLC361	PSG	D	47.40	0.19		CONDITIONALLY QUALIFIED		
OLC363	PSG	D	50.81	0.11		CONDITIONALLY QUALIFIED		
OLC367	PSG	D	49.93	0.14		CONDITIONALLY QUALIFIED		
OLC372	PSG	D	49.72	0.08		CONDITIONALLY QUALIFIED		

Table 20 Test D: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OLC373	PSG	D	49.39	0.13		CONDITIONALLY QUALIFIED		
OLC377	PSG	D	53.46	0.05		CONDITIONALLY QUALIFIED		
OLC382	PSG	D	49.03	0.20		CONDITIONALLY QUALIFIED		
OLC406	PSG	D	66.56	0.09		CONDITIONALLY QUALIFIED		
OLC432	PSG	D	51.84	0.11		CONDITIONALLY QUALIFIED		
OLC450	PSG	D	60.53	0.33		CONDITIONALLY QUALIFIED		
OLC471	PSG	D	50.92	0.33		CONDITIONALLY QUALIFIED		
OLC472	PSG	D	49.15	0.19		CONDITIONALLY QUALIFIED		
OLC475	PSG	D	50.84	0.10		CONDITIONALLY QUALIFIED		
OLC482	PSG	D	52.08	0.14		CONDITIONALLY QUALIFIED		
OLC484	PSG	D	51.95	0.28		CONDITIONALLY QUALIFIED		
OLC486	PSG	D	51.32	0.22		CONDITIONALLY QUALIFIED		
OLC487	PSG	D				FAILED		
OLC488	PSG	D	51.52	0.16		CONDITIONALLY QUALIFIED		
OLC490	PSG	D	50.97	0.11		CONDITIONALLY QUALIFIED		
OLC491	PSG	D	50.34	0.27		CONDITIONALLY QUALIFIED		
OLC492	PSG	D	52.95	0.19		CONDITIONALLY QUALIFIED		
OLC493	PSG	D	50.91	0.07		CONDITIONALLY QUALIFIED		
OLC494	PSG	D	52.43	0.05		CONDITIONALLY QUALIFIED		
OLC495	PSG	D	53.66	0.18		CONDITIONALLY QUALIFIED		
OLC496	PSG	D	50.82	0.18		CONDITIONALLY QUALIFIED		
OLC497	PSG	D	53.12	0.22		CONDITIONALLY QUALIFIED		
OLC498	PSG	D	60.86	0.34		CONDITIONALLY QUALIFIED		
OLC499	PSG	D	64.17	0.23		CONDITIONALLY QUALIFIED		
OLC500	PSG	D	63.36	0.28		CONDITIONALLY QUALIFIED		
OLC502	PSG	D	68.35	0.19		CONDITIONALLY QUALIFIED		
OLC504	PSG	D	71.15	0.19		CONDITIONALLY QUALIFIED		
OLC506	PSG	D	69.08	0.06		CONDITIONALLY QUALIFIED		
OLC507	PSG	D	58.62	0.14		CONDITIONALLY QUALIFIED		
OLC508	PSG	D	67.43	0.19		CONDITIONALLY QUALIFIED		
OLC509	PSG	D	58.57	0.07		CONDITIONALLY QUALIFIED		
OLC510	PSG	D	69.50	0.08		CONDITIONALLY QUALIFIED		

Table 20 Test D: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
OLC512	PSG	D	66.13	0.35		CONDITIONALLY QUALIFIED
OLC520	PSG	D	69.00	0.29		CONDITIONALLY QUALIFIED
OLC524	PSG	D	73.80	0.31		CONDITIONALLY QUALIFIED
OLC539	PSG	D	71.95	0.14		CONDITIONALLY QUALIFIED
OLC542	PSG	D	70.44	0.23		CONDITIONALLY QUALIFIED
OLC559	PSG	D	71.18	0.30		CONDITIONALLY QUALIFIED
OLC562	PSG	D	73.55	0.41		CONDITIONALLY QUALIFIED
OLC579	PSG	D	71.30	0.08		CONDITIONALLY QUALIFIED
OLC582	PSG	D	63.58	0.22		CONDITIONALLY QUALIFIED
OLC592	PSG	D	45.27	0.31		CONDITIONALLY QUALIFIED
OLC583	PSG	D	52.94	0.14		CONDITIONALLY QUALIFIED
OLC595	PSG	D	51.66	0.25		CONDITIONALLY QUALIFIED
OLC596	PSG	D	52.04	0.13		CONDITIONALLY QUALIFIED
OLC597	PSG	D	51.27	0.41		CONDITIONALLY QUALIFIED
OLC598	PSG	D	51.77	0.17		CONDITIONALLY QUALIFIED
OLC599	PSG	D	51.63	0.25		CONDITIONALLY QUALIFIED
OLC600	PSG	D	51.79	0.13		CONDITIONALLY QUALIFIED

Table 21 Test E: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
Plenum Inlet Temp 2 L1	C	E	22.21	0.05		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L2	C	E	22.58	0.05		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L3	C	E	22.77	0.03		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L4	C	E	22.60	0.04		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L5	C	E	22.51	0.05		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L6	C	E	22.46	0.06		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L1	C	E	22.36	0.05		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L2	C	E	22.39	0.05		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L3	C	E	21.97	0.04		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L4	C	E	22.00	0.04		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L5	C	E	21.70	0.06		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L6	C	E	21.87	0.06		CONDITIONALLY QUALIFIED		
Pump Suction Temp 1	C	E	21.96	0.38		CONDITIONALLY QUALIFIED		
Pump Suction Temp 2	C	E	22.52	0.30		CONDITIONALLY QUALIFIED		
Pump Suction Temp 3	C	E	22.41	0.46		CONDITIONALLY QUALIFIED		
Pump Suction Temp 4	C	E	22.49	0.72		CONDITIONALLY QUALIFIED		
Pump Suction Temp 5	C	E	22.21	0.06		CONDITIONALLY QUALIFIED		
Pump Suction Temp 6	C	E	22.24	0.14		CONDITIONALLY QUALIFIED		
Barometric Pressure	PSIA	E	14.57	0.02		CONDITIONALLY QUALIFIED		
PS1	PSIA	E	22.78	0.05	0.11	QUALIFIED		
PS2	PSIA	E	13.76	0.05	0.11	QUALIFIED		
PS3	PSIA	E	13.61	0.13	0.11	QUALIFIED		
PS4	PSIA	E	14.31	0.06	0.11	QUALIFIED		
PS5	PSIA	E	14.56	0.06	0.11	QUALIFIED		
PS6	PSIA	E	13.79	0.06	0.11	QUALIFIED		
PD1	PSIG	E	41.03	0.05	0.60	QUALIFIED		
PD2	PSIG	E	181.32	0.14	0.60	QUALIFIED		
PD3	PSIG	E	178.23	0.10	0.60	QUALIFIED		
PD4	PSIG	E	188.79	0.15	0.60	QUALIFIED		
PD5	PSIG	E	188.28	0.05	0.60	QUALIFIED		
PD6	PSIG	E	176.86	0.08	0.60	QUALIFIED		
HI1	PSIG	E	43.59	0.05	0.60	QUALIFIED		

Table 21 Test E: Results of Data Qualification of 1985 L-Area AC Flow Tests									
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes		
H#2	PSG	E	171.52	0.09	0.60	QUALIFIED			
H#3	PSG	E	173.24	0.23	0.60	QUALIFIED			
H#4	PSG	E	179.45	0.09	0.60	QUALIFIED			
H#5	PSG	E	178.69	0.11	0.60	QUALIFIED			
H#6	PSG	E	167.14	0.07	0.60	QUALIFIED			
HD1	PSG	E	65.46	0.20	0.60	QUALIFIED			
HD2	PSG	E	84.04	0.24	0.60	QUALIFIED			
HD3	PSG	E	76.88	0.17	0.60	QUALIFIED			
HD4	PSG	E	84.45	0.21	0.60	QUALIFIED			
HD5	PSG	E	85.04	0.10	0.60	QUALIFIED			
HD6	PSG	E	72.64	0.18	0.60	QUALIFIED			
ECS1	PSG	E	65.71	0.06		CONDITIONALLY QUALIFIED			
ECS4	PSG	E	81.79	0.07		CONDITIONALLY QUALIFIED			
Ultrasonic - Loop 1	GFM	E	-11945	26.00		CONDITIONALLY QUALIFIED			Not Adjusted for Zero Offset
Ultrasonic - Loop 4	GFM	E	25208	30.00		CONDITIONALLY QUALIFIED			Not Adjusted for Zero Offset
Ultrasonic - Loop 5	GFM	E	26813	37.86		CONDITIONALLY QUALIFIED			Not Adjusted for Zero Offset
Tank - LPH	PSG	E	16.50	0.00	0.10	QUALIFIED			
Tank - GANG1	PSG	E	17.42	0.01	0.10	QUALIFIED			
M608-OLC493	PSG	E	17.08	0.03	0.10	QUALIFIED			
M608-OLC500	PSG	E	17.22	0.00	0.10	QUALIFIED			
M608-OLC600	PSG	E	16.54	0.00	0.10	QUALIFIED			
PCL Pressure (System A)	PSG	E	50.97	0.16	1.65	QUALIFIED			
PCL Pressure (System B)	PSG	E	50.36	0.78	0.90	QUALIFIED			
OLC1	PSG	E	48.65	0.06		CONDITIONALLY QUALIFIED			
OLC6	PSG	E	46.84	0.28		CONDITIONALLY QUALIFIED			
OLC15	PSG	E	48.80	0.04		CONDITIONALLY QUALIFIED			
OLC26	PSG	E	46.81	0.08		CONDITIONALLY QUALIFIED			
OLC34	PSG	E	47.81	0.14		CONDITIONALLY QUALIFIED			
OLC47	PSG	E	48.63	0.06		CONDITIONALLY QUALIFIED			
OLC59	PSG	E	47.41	0.07		CONDITIONALLY QUALIFIED			
OLC71	PSG	E	48.20	0.22		CONDITIONALLY QUALIFIED			
OLC83	PSG	E	49.50	0.14		CONDITIONALLY QUALIFIED			

Table 21 Test E: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OLC106	PSG	E	46.10	0.12		CONDITIONALLY QUALIFIED		
OLC110	PSG	E	45.49	0.05		CONDITIONALLY QUALIFIED		
OLC115	PSG	E	48.35	0.06		CONDITIONALLY QUALIFIED		
OLC124	PSG	E	46.88	0.14		CONDITIONALLY QUALIFIED		
OLC129	PSG	E	48.71	0.03		CONDITIONALLY QUALIFIED		
OLC135	PSG	E	49.30	0.05		CONDITIONALLY QUALIFIED		
OLC148	PSG	E	47.47	0.11		CONDITIONALLY QUALIFIED		
OLC161	PSG	E	51.50	0.11		CONDITIONALLY QUALIFIED		
OLC177	PSG	E	52.23	0.13		CONDITIONALLY QUALIFIED		
OLC182	PSG	E	49.49	0.31		CONDITIONALLY QUALIFIED		
OLC198	PSG	E	53.74	0.35		CONDITIONALLY QUALIFIED		
OLC210	PSG	E	46.41	0.07		CONDITIONALLY QUALIFIED		
OLC214	PSG	E	45.79	0.11		CONDITIONALLY QUALIFIED		
OLC218	PSG	E	44.64	0.02		CONDITIONALLY QUALIFIED		
OLC221	PSG	E	49.74	0.02		CONDITIONALLY QUALIFIED		
OLC223	PSG	E	49.64	0.06		CONDITIONALLY QUALIFIED		
OLC230	PSG	E	48.92	0.12		CONDITIONALLY QUALIFIED		
OLC236	PSG	E	48.46	0.08		CONDITIONALLY QUALIFIED		
OLC238	PSG	E	47.35	0.24		CONDITIONALLY QUALIFIED		
OLC243	PSG	E	48.63	0.06		CONDITIONALLY QUALIFIED		
OLC248	PSG	E	47.25	0.06		CONDITIONALLY QUALIFIED		
OLC263	PSG	E	52.81	0.25		CONDITIONALLY QUALIFIED		
OLC280	PSG	E	56.90	0.36		CONDITIONALLY QUALIFIED		
OLC295	PSG	E	50.67	0.12		CONDITIONALLY QUALIFIED		
OLC313	PSG	E	58.17	0.44		CONDITIONALLY QUALIFIED		
OLC354	PSG	E	47.98	0.07		CONDITIONALLY QUALIFIED		
OLC358	PSG	E	46.73	0.03		CONDITIONALLY QUALIFIED		
OLC360	PSG	E	47.69	0.09		CONDITIONALLY QUALIFIED		
OLC361	PSG	E	50.36	0.26		CONDITIONALLY QUALIFIED		
OLC363	PSG	E	54.75	0.03		CONDITIONALLY QUALIFIED		
OLC367	PSG	E	48.54	0.30		CONDITIONALLY QUALIFIED		
OLC372	PSG	E	49.70	0.07		CONDITIONALLY QUALIFIED		

Table 21 Test E: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OLC373	PSG	E	49.62	0.15		CONDITIONALLY QUALIFIED		
OLC377	PSG	E	51.57	0.03		CONDITIONALLY QUALIFIED		
OLC382	PSG	E	46.03	0.14		CONDITIONALLY QUALIFIED		
OLC406	PSG	E	64.38	0.14		CONDITIONALLY QUALIFIED		
OLC432	PSG	E	52.73	0.11		CONDITIONALLY QUALIFIED		
OLC450	PSG	E	63.26	0.30		CONDITIONALLY QUALIFIED		
OLC471	PSG	E	55.50	0.12		CONDITIONALLY QUALIFIED		
OLC472	PSG	E	48.90	0.03		CONDITIONALLY QUALIFIED		
OLC475	PSG	E	57.85	0.12		CONDITIONALLY QUALIFIED		
OLC482	PSG	E	66.75	0.34		CONDITIONALLY QUALIFIED		
OLC484	PSG	E	64.09	0.35		CONDITIONALLY QUALIFIED		
OLC486	PSG	E	62.09	0.12		CONDITIONALLY QUALIFIED		
OLC487	PSG	E				FAILED		
OLC488	PSG	E	51.32	0.14		CONDITIONALLY QUALIFIED		
OLC490	PSG	E	53.77	0.43		CONDITIONALLY QUALIFIED		
OLC491	PSG	E	50.50	0.20		CONDITIONALLY QUALIFIED		
OLC492	PSG	E	49.99	0.26		CONDITIONALLY QUALIFIED		
OLC493	PSG	E	50.55	0.20		CONDITIONALLY QUALIFIED		
OLC494	PSG	E	51.80	0.25		CONDITIONALLY QUALIFIED		
OLC495	PSG	E	51.06	0.24		CONDITIONALLY QUALIFIED		
OLC496	PSG	E	51.62	0.17		CONDITIONALLY QUALIFIED		
OLC497	PSG	E	51.83	0.14		CONDITIONALLY QUALIFIED		
OLC498	PSG	E	51.70	0.18		CONDITIONALLY QUALIFIED		
OLC499	PSG	E	52.30	0.09		CONDITIONALLY QUALIFIED		
OLC500	PSG	E	52.11	0.33		CONDITIONALLY QUALIFIED		
OLC502	PSG	E	51.95	0.21		CONDITIONALLY QUALIFIED		
OLC504	PSG	E	51.91	0.21		CONDITIONALLY QUALIFIED		
OLC506	PSG	E	52.37	0.19		CONDITIONALLY QUALIFIED		
OLC507	PSG	E	49.68	0.12		CONDITIONALLY QUALIFIED		
OLC508	PSG	E	52.16	0.38		CONDITIONALLY QUALIFIED		
OLC509	PSG	E	50.81	0.14		CONDITIONALLY QUALIFIED		
OLC510	PSG	E	52.32	0.25		CONDITIONALLY QUALIFIED		

Table 21		Test E: Results of Data Qualification of 1985 L-Area AC Flow Tests					
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	Notes
OLC512	PSG	E	48.37	0.26		CONDITIONALLY QUALIFIED	
OLC520	PSG	E	65.85	0.42		CONDITIONALLY QUALIFIED	
OLC524	PSG	E	72.12	0.22		CONDITIONALLY QUALIFIED	
OLC539	PSG	E	71.05	0.10		CONDITIONALLY QUALIFIED	
OLC542	PSG	E	70.87	0.33		CONDITIONALLY QUALIFIED	
OLC559	PSG	E	70.21	0.49		CONDITIONALLY QUALIFIED	
OLC562	PSG	E	74.60	0.32		CONDITIONALLY QUALIFIED	
OLC579	PSG	E	73.50	0.14		CONDITIONALLY QUALIFIED	
OLC582	PSG	E	69.14	0.27		CONDITIONALLY QUALIFIED	
OLC592	PSG	E	62.00	0.21		CONDITIONALLY QUALIFIED	
OLC593	PSG	E	65.08	0.30		CONDITIONALLY QUALIFIED	
OLC595	PSG	E	69.27	0.57		CONDITIONALLY QUALIFIED	
OLC596	PSG	E	66.52	0.18		CONDITIONALLY QUALIFIED	
OLC597	PSG	E	66.46	0.28		CONDITIONALLY QUALIFIED	
OLC598	PSG	E	66.61	0.19		CONDITIONALLY QUALIFIED	
OLC599	PSG	E	69.17	0.07		CONDITIONALLY QUALIFIED	
OLC600	PSG	E	69.54	0.16		CONDITIONALLY QUALIFIED	

Table 22 Test F: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
Plenum Inlet Temp 2 L1	C	F	22.33	0.20		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L2	C	F	22.94	0.23		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L3	C	F	22.74	0.23		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L4	C	F	23.25	0.32		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L5	C	F	22.44	0.19		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L6	C	F	23.16	0.32		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L1	C	F	21.88	0.19		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L2	C	F	23.10	0.54		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L3	C	F	22.03	0.22		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L4	C	F	23.23	0.33		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L5	C	F	21.71	0.20		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L6	C	F	23.21	0.46		CONDITIONALLY QUALIFIED
Pump Suction Temp 1	C	F	22.16	0.18		CONDITIONALLY QUALIFIED
Pump Suction Temp 2	C	F	24.00	1.18		CONDITIONALLY QUALIFIED
Pump Suction Temp 3	C	F	22.42	0.20		CONDITIONALLY QUALIFIED
Pump Suction Temp 4	C	F	23.36	0.13		CONDITIONALLY QUALIFIED
Pump Suction Temp 5	C	F	22.10	0.17		CONDITIONALLY QUALIFIED
Pump Suction Temp 6	C	F	24.09	1.04		CONDITIONALLY QUALIFIED
Barometric Pressure	PSIA	F	14.60	0.01		CONDITIONALLY QUALIFIED
PS1	PSIA	F	12.21	0.29	0.11	QUALIFIED
PS2	PSIA	F	21.89	0.05	0.11	QUALIFIED
PS3	PSIA	F	11.98	0.16	0.11	QUALIFIED
PS4	PSIA	F	21.90	0.09	0.11	QUALIFIED
PS5	PSIA	F	13.29	0.17	0.11	QUALIFIED
PS6	PSIA	F	21.89	0.08	0.11	QUALIFIED
PD1	PSIG	F	162.88	0.11	0.60	QUALIFIED
PD2	PSIG	F	7.92	0.03	0.60	QUALIFIED
PD3	PSIG	F	157.63	0.15	0.60	QUALIFIED
PD4	PSIG	F	7.92	0.04	0.60	QUALIFIED
PD5	PSIG	F	168.87	0.13	0.60	QUALIFIED
PD6	PSIG	F	7.89	0.04	0.60	QUALIFIED
HI1	PSIG	F	151.04	0.12	0.60	QUALIFIED

Table 22								Test F: Results of Data Qualification of 1985 L-Area AC Flow Tests							
Measurement Type		Unit	Test	Average	Precision	Bias (Unit)	Label							Notes	
H12		PSG	F	7.89	0.03	0.60	QUALIFIED								
H13		PSG	F	151.51	0.10	0.60	QUALIFIED								
H14		PSG	F	7.90	0.03	0.60	QUALIFIED								
H15		PSG	F	157.24	0.10	0.60	QUALIFIED								
H16		PSG	F	7.88	0.02	0.60	QUALIFIED								
HD1		PSG	F	46.98	0.07	0.60	QUALIFIED								
HD2		PSG	F	47.95	0.08	0.60	QUALIFIED								
HD3		PSG	F	38.94	0.07	0.60	QUALIFIED								
HD4		PSG	F	48.23	0.06	0.60	QUALIFIED								
HD5		PSG	F	46.38	0.06	0.60	QUALIFIED								
HD6		PSG	F	46.01	0.07	0.60	QUALIFIED								
ECS1		PSG	F	41.46	0.07		CONDITIONALLY QUALIFIED								
ECS4		PSG	F	48.22	0.05		CONDITIONALLY QUALIFIED								
Ultrasonic - Loop 1		GFM	F	28470	104.49		CONDITIONALLY QUALIFIED							Not Adjusted for Zero Offset	
Ultrasonic - Loop 3		GFM	F	29319	112.37		CONDITIONALLY QUALIFIED							Not Adjusted for Zero Offset	
Ultrasonic - Loop 5		GFM	F	29312	56.17		CONDITIONALLY QUALIFIED							Not Adjusted for Zero Offset	
Tank - LPH		PSG	F	16.80	0.01	0.10	QUALIFIED								
Tank - GANG1		PSG	F	17.29	0.01	0.10	QUALIFIED								
M60B-OLC493		PSG	F	17.09	0.02	0.10	QUALIFIED								
M60B-OLC500		PSG	F	16.47	0.01	0.10	QUALIFIED								
M60B-OLC600		PSG	F	17.12	0.01	0.10	QUALIFIED								
PCL Pressure (System A)		PSG	F	27.85	0.05	1.65	QUALIFIED								
PCL Pressure (System B)		PSG	F	27.41	0.17	0.90	QUALIFIED								
OLC1		PSG	F	26.78	0.03		CONDITIONALLY QUALIFIED								
OLC6		PSG	F	25.74	0.03		CONDITIONALLY QUALIFIED								
OLC15		PSG	F	26.55	0.05		CONDITIONALLY QUALIFIED								
OLC26		PSG	F	25.54	0.08		CONDITIONALLY QUALIFIED								
OLC34		PSG	F	25.50	0.08		CONDITIONALLY QUALIFIED								
OLC47		PSG	F	26.53	0.06		CONDITIONALLY QUALIFIED								
OLC59		PSG	F	25.85	0.06		CONDITIONALLY QUALIFIED								
OLC71		PSG	F	26.69	0.06		CONDITIONALLY QUALIFIED								
OLC83		PSG	F	26.47	0.07		CONDITIONALLY QUALIFIED								

Table 22 Test F: Results of Data Qualification of 1985 L-Area AC Flow Tests							
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes
OLC106	PSG	F	25.18	0.05		CONDITIONALLY QUALIFIED	
OLC110	PSG	F	26.68	0.07		CONDITIONALLY QUALIFIED	
OLC115	PSG	F	28.22	0.06		CONDITIONALLY QUALIFIED	
OLC124	PSG	F	25.08	0.09		CONDITIONALLY QUALIFIED	
OLC129	PSG	F	26.48	0.06		CONDITIONALLY QUALIFIED	
OLC135	PSG	F	26.88	0.13		CONDITIONALLY QUALIFIED	
OLC148	PSG	F	26.68	0.18		CONDITIONALLY QUALIFIED	
OLC161	PSG	F	27.39	0.06		CONDITIONALLY QUALIFIED	
OLC177	PSG	F	26.47	0.12		CONDITIONALLY QUALIFIED	
OLC182	PSG	F	25.51	0.20		CONDITIONALLY QUALIFIED	
OLC198	PSG	F	26.52	0.14		CONDITIONALLY QUALIFIED	
OLC210	PSG	F	25.34	0.15		CONDITIONALLY QUALIFIED	
OLC214	PSG	F	25.09	0.11		CONDITIONALLY QUALIFIED	
OLC218	PSG	F	27.93	0.11		CONDITIONALLY QUALIFIED	
OLC221	PSG	F	27.46	0.05		CONDITIONALLY QUALIFIED	
OLC223	PSG	F	31.11	0.10		CONDITIONALLY QUALIFIED	
OLC230	PSG	F	29.03	0.09		CONDITIONALLY QUALIFIED	
OLC236	PSG	F	27.59	0.11		CONDITIONALLY QUALIFIED	
OLC238	PSG	F	23.95	0.07		CONDITIONALLY QUALIFIED	
OLC243	PSG	F	26.94	0.09		CONDITIONALLY QUALIFIED	
OLC248	PSG	F	25.40	0.10		CONDITIONALLY QUALIFIED	
OLC263	PSG	F	27.63	0.11		CONDITIONALLY QUALIFIED	
OLC280	PSG	F	29.85	0.12		CONDITIONALLY QUALIFIED	
OLC295	PSG	F	26.55	0.08		CONDITIONALLY QUALIFIED	
OLC313	PSG	F	29.02	0.14		CONDITIONALLY QUALIFIED	
OLC354	PSG	F	25.47	0.08		CONDITIONALLY QUALIFIED	
OLC358	PSG	F	25.26	0.12		CONDITIONALLY QUALIFIED	
OLC360	PSG	F	25.25	0.06		CONDITIONALLY QUALIFIED	
OLC361	PSG	F	27.76	0.22		CONDITIONALLY QUALIFIED	
OLC363	PSG	F	31.23	0.12		CONDITIONALLY QUALIFIED	
OLC367	PSG	F	32.38	0.23		CONDITIONALLY QUALIFIED	
OLC372	PSG	F	31.95	0.10		CONDITIONALLY QUALIFIED	

Table 22 Test F: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
OLC373	PSG	F	31.66	0.08		CONDITIONALLY QUALIFIED
OLC377	PSG	F	32.76	0.08		CONDITIONALLY QUALIFIED
OLC382	PSG	F	24.64	0.15		CONDITIONALLY QUALIFIED
OLC406	PSG	F	33.21	0.11		CONDITIONALLY QUALIFIED
OLC432	PSG	F	26.57	0.10		CONDITIONALLY QUALIFIED
OLC450	PSG	F	31.48	0.08		CONDITIONALLY QUALIFIED
OLC471	PSG	F	28.08	0.06		CONDITIONALLY QUALIFIED
OLC472	PSG	F	25.90	0.11		CONDITIONALLY QUALIFIED
OLC475	PSG	F	29.24	0.06		CONDITIONALLY QUALIFIED
OLC482	PSG	F	34.41	0.11		CONDITIONALLY QUALIFIED
OLC484	PSG	F	34.01	0.18		CONDITIONALLY QUALIFIED
OLC486	PSG	F	34.03	0.17		CONDITIONALLY QUALIFIED
OLC487	PSG	F	33.24	0.13		CONDITIONALLY QUALIFIED
OLC488	PSG	F	33.78	0.21		CONDITIONALLY QUALIFIED
OLC490	PSG	F	33.77	0.19		CONDITIONALLY QUALIFIED
OLC491	PSG	F	33.20	0.18		CONDITIONALLY QUALIFIED
OLC492	PSG	F	34.50	0.23		CONDITIONALLY QUALIFIED
OLC493	PSG	F	32.96	0.18		CONDITIONALLY QUALIFIED
OLC494	PSG	F	33.25	0.18		CONDITIONALLY QUALIFIED
OLC495	PSG	F	33.72	0.13		CONDITIONALLY QUALIFIED
OLC496	PSG	F	32.29	0.09		CONDITIONALLY QUALIFIED
OLC497	PSG	F	33.54	0.18		CONDITIONALLY QUALIFIED
OLC498	PSG	F	36.30	0.12		CONDITIONALLY QUALIFIED
OLC499	PSG	F	37.08	0.11		CONDITIONALLY QUALIFIED
OLC500	PSG	F	35.34	0.13		CONDITIONALLY QUALIFIED
OLC502	PSG	F	35.91	0.17		CONDITIONALLY QUALIFIED
OLC504	PSG	F	33.35	0.21		CONDITIONALLY QUALIFIED
OLC506	PSG	F	28.16	0.15		CONDITIONALLY QUALIFIED
OLC507	PSG	F	25.92	0.11		CONDITIONALLY QUALIFIED
OLC508	PSG	F	30.23	0.21		CONDITIONALLY QUALIFIED
OLC509	PSG	F	28.00	0.09		CONDITIONALLY QUALIFIED
OLC510	PSG	F	28.99	0.12		CONDITIONALLY QUALIFIED

Table 22		Test F: Results of Data Qualification of 1985 L-Area AC Flow Tests					
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes
OL C512	PSG	F	24.27	0.20		CONDITIONALLY QUALIFIED	
OL C520	PSG	F	36.78	0.19		CONDITIONALLY QUALIFIED	
OL C524	PSG	F	36.12	0.16		CONDITIONALLY QUALIFIED	
OL C539	PSG	F	38.30	0.18		CONDITIONALLY QUALIFIED	
OL C542	PSG	F	36.48	0.17		CONDITIONALLY QUALIFIED	
OL C559	PSG	F	36.97	0.18		CONDITIONALLY QUALIFIED	
OL C562	PSG	F	36.72	0.24		CONDITIONALLY QUALIFIED	
OL C579	PSG	F	37.69	0.28		CONDITIONALLY QUALIFIED	
OL C582	PSG	F	35.45	0.25		CONDITIONALLY QUALIFIED	
OL C592	PSG	F	24.94	0.22		CONDITIONALLY QUALIFIED	
OL C593	PSG	F	29.47	0.13		CONDITIONALLY QUALIFIED	
OL C595	PSG	F	30.53	0.11		CONDITIONALLY QUALIFIED	
OL C596	PSG	F	31.28	0.08		CONDITIONALLY QUALIFIED	
OL C597	PSG	F	31.98	0.23		CONDITIONALLY QUALIFIED	
OL C598	PSG	F	34.59	0.08		CONDITIONALLY QUALIFIED	
OL C599	PSG	F	35.20	0.23		CONDITIONALLY QUALIFIED	
OL C600	PSG	F	34.83	0.22		CONDITIONALLY QUALIFIED	

Table 23 Test G: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
Plenum Inlet Temp 2 L1	C	G	58.70	4.08		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L2	C	G	61.47	1.61		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L3	C	G	60.56	6.72		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L4	C	G	60.43	2.02		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L5	C	G	63.00	0.57		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 2 L6	C	G	62.11	0.58		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L1	C	G	59.40	2.82		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L2	C	G	61.07	2.26		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L3	C	G	60.52	3.07		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L4	C	G	60.02	2.45		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L5	C	G	61.35	2.91		CONDITIONALLY QUALIFIED
Plenum Inlet Temp 1 L6	C	G	61.41	2.94		CONDITIONALLY QUALIFIED
Pump Suction Temp 1	C	G	59.65	2.62		CONDITIONALLY QUALIFIED
Pump Suction Temp 2	C	G	60.81	2.32		CONDITIONALLY QUALIFIED
Pump Suction Temp 3	C	G	60.49	2.94		CONDITIONALLY QUALIFIED
Pump Suction Temp 4	C	G	60.11	2.36		CONDITIONALLY QUALIFIED
Pump Suction Temp 5	C	G	61.14	2.71		CONDITIONALLY QUALIFIED
Pump Suction Temp 6	C	G	61.17	2.71		CONDITIONALLY QUALIFIED
Barometric Pressure	PSIA	G	14.76	0.02		CONDITIONALLY QUALIFIED
PS1	PSIA	G	17.32	0.13	0.11	QUALIFIED
PS2	PSIA	G	17.32	0.07	0.11	QUALIFIED
PS3	PSIA	G	17.47	0.09	0.11	QUALIFIED
PS4	PSIA	G	17.72	0.09	0.11	QUALIFIED
PS5	PSIA	G	17.84	0.07	0.11	QUALIFIED
PS6	PSIA	G	17.41	0.07	0.11	QUALIFIED
PD1	PSG	G	220.01	0.42	0.60	QUALIFIED
PD2	PSG	G	220.49	0.45	0.60	QUALIFIED
PD3	PSG	G	220.15	0.59	0.60	QUALIFIED
PD4	PSG	G	224.88	0.46	0.60	QUALIFIED
PD5	PSG	G	225.57	0.45	0.60	QUALIFIED
PD6	PSG	G	218.26	0.61	0.60	QUALIFIED
Ht1	PSG	G	214.59	0.40	0.60	QUALIFIED

Table 23								Test G: Results of Data Qualification of 1985 L-Area AC Flow Tests							
Measurement Type		Unit	Test	Average	Precision	2*Std Dev	Blas (Unit)	Label	Notes						
H12		PSG	G	215.11		0.44	0.60	QUALIFIED							
H13		PSG	G	217.76		0.58	0.60	QUALIFIED							
H14		PSG	G	219.69		0.42	0.60	QUALIFIED							
H15		PSG	G	220.36		0.51	0.60	QUALIFIED							
H16		PSG	G	213.05		0.50	0.60	QUALIFIED							
HD1		PSG	G	69.74		0.14	0.60	QUALIFIED							
HD2		PSG	G	70.41		0.11	0.60	QUALIFIED							
HD3		PSG	G	67.22		0.10	0.60	QUALIFIED							
HD4		PSG	G	71.05		0.12	0.60	QUALIFIED							
HD5		PSG	G	71.52		0.15	0.60	QUALIFIED							
HD6		PSG	G	65.88		0.13	0.60	QUALIFIED							
ECS1		PSG	G	67.35		0.11		CONDITIONALLY QUALIFIED							
ECS4		PSG	G	70.06		0.11		CONDITIONALLY QUALIFIED							
Ultrasonic - Loop 1		GFM	G	21880		247.18		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset						
Ultrasonic - Loop 3		GFM	G	20783		159.06		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset						
Ultrasonic - Loop 6		GFM	G	18663		130.10		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset						
Tank - LPH		PSG	G	16.55		0.01	0.10	QUALIFIED							
Tank - GANG1		PSG	G	17.29		0.01	0.10	QUALIFIED							
M508-OLC493		PSG	G	16.95		0.01	0.10	QUALIFIED							
M508-OLC500		PSG	G	16.65		0.01	0.10	QUALIFIED							
M508-OLC600		PSG	G	16.65		0.01	0.10	QUALIFIED							
PCL Pressure (System A)		PSG	G	47.47		0.08	1.65	QUALIFIED							
PCL Pressure (System B)		PSG	G	47.16		0.29	0.90	QUALIFIED							
OLC1		PSG	G	46.07		0.06		CONDITIONALLY QUALIFIED							
OLC6		PSG	G	43.89		0.04		CONDITIONALLY QUALIFIED							
OLC15		PSG	G	45.74		0.11		CONDITIONALLY QUALIFIED							
OLC26		PSG	G	44.05		0.10		CONDITIONALLY QUALIFIED							
OLC34		PSG	G	43.84		0.08		CONDITIONALLY QUALIFIED							
OLC47		PSG	G	45.39		0.20		CONDITIONALLY QUALIFIED							
OLC59		PSG	G	44.34		0.19		CONDITIONALLY QUALIFIED							
OLC71		PSG	G	45.84		0.10		CONDITIONALLY QUALIFIED							
OLC83		PSG	G	45.16		0.04		CONDITIONALLY QUALIFIED							

Table 23 Test G: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OLC106	PSIG	G	42.91	0.24		CONDITIONALLY QUALIFIED		
OLC110	PSIG	G	45.49	0.36		CONDITIONALLY QUALIFIED		
OLC115	PSIG	G	49.12	0.13		CONDITIONALLY QUALIFIED		
OLC124	PSIG	G	43.18	0.49		CONDITIONALLY QUALIFIED		
OLC129	PSIG	G	45.65	0.15		CONDITIONALLY QUALIFIED		
OLC135	PSIG	G	45.41	0.08		CONDITIONALLY QUALIFIED		
OLC148	PSIG	G	44.50	0.25		CONDITIONALLY QUALIFIED		
OLC161	PSIG	G	46.99	0.16		CONDITIONALLY QUALIFIED		
OLC177	PSIG	G	45.55	0.11		CONDITIONALLY QUALIFIED		
OLC182	PSIG	G	43.25	0.20		CONDITIONALLY QUALIFIED		
OLC198	PSIG	G	45.90	0.36		CONDITIONALLY QUALIFIED		
OLC210	PSIG	G	42.36	0.17		CONDITIONALLY QUALIFIED		
OLC214	PSIG	G	42.77	0.13		CONDITIONALLY QUALIFIED		
OLC218	PSIG	G	47.11	0.35		CONDITIONALLY QUALIFIED		
OLC221	PSIG	G	47.24	0.15		CONDITIONALLY QUALIFIED		
OLC223	PSIG	G	53.71	0.82		CONDITIONALLY QUALIFIED		
OLC230	PSIG	G	51.06	0.56		CONDITIONALLY QUALIFIED		
OLC236	PSIG	G	48.44	0.22		CONDITIONALLY QUALIFIED		
OLC238	PSIG	G	43.48	0.23		CONDITIONALLY QUALIFIED		
OLC243	PSIG	G	46.28	0.11		CONDITIONALLY QUALIFIED		
OLC248	PSIG	G	43.47	0.11		CONDITIONALLY QUALIFIED		
OLC263	PSIG	G	46.98	0.26		CONDITIONALLY QUALIFIED		
OLC280	PSIG	G	49.89	0.34		CONDITIONALLY QUALIFIED		
OLC295	PSIG	G	45.83	0.07		CONDITIONALLY QUALIFIED		
OLC313	PSIG	G	49.79	0.20		CONDITIONALLY QUALIFIED		
OLC354	PSIG	G	44.06	0.06		CONDITIONALLY QUALIFIED		
OLC358	PSIG	G	43.56	0.18		CONDITIONALLY QUALIFIED		
OLC360	PSIG	G	44.73	0.21		CONDITIONALLY QUALIFIED		
OLC361	PSIG	G	47.31	0.31		CONDITIONALLY QUALIFIED		
OLC363	PSIG	G	54.02	0.41		CONDITIONALLY QUALIFIED		
OLC367	PSIG	G	54.97	0.44		CONDITIONALLY QUALIFIED		
OLC372	PSIG	G	55.05	0.18		CONDITIONALLY QUALIFIED		

Table 23 Test G: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OLC373	PSG	G	58.58	0.20		CONDITIONALLY QUALIFIED		
OLC377	PSG	G	56.87	0.21		CONDITIONALLY QUALIFIED		
OLC382	PSG	G	44.65	0.28		CONDITIONALLY QUALIFIED		
OLC406	PSG	G	55.21	0.27		CONDITIONALLY QUALIFIED		
OLC432	PSG	G	45.31	0.14		CONDITIONALLY QUALIFIED		
OLC450	PSG	G	52.76	0.18		CONDITIONALLY QUALIFIED		
OLC471	PSG	G	48.23	0.16		CONDITIONALLY QUALIFIED		
OLC472	PSG	G	43.84	0.12		CONDITIONALLY QUALIFIED		
OLC475	PSG	G	52.07	0.16		CONDITIONALLY QUALIFIED		
OLC482	PSG	G	58.98	0.15		CONDITIONALLY QUALIFIED		
OLC484	PSG	G	59.72	0.28		CONDITIONALLY QUALIFIED		
OLC486	PSG	G	61.84	0.38		CONDITIONALLY QUALIFIED		
OLC487	PSG	G	57.37	0.22		CONDITIONALLY QUALIFIED		
OLC488	PSG	G	58.13	0.19		CONDITIONALLY QUALIFIED		
OLC490	PSG	G	61.89	0.18		CONDITIONALLY QUALIFIED		
OLC491	PSG	G	59.13	0.22		CONDITIONALLY QUALIFIED		
OLC492	PSG	G	61.55	0.17		CONDITIONALLY QUALIFIED		
OLC493	PSG	G	60.49	0.25		CONDITIONALLY QUALIFIED		
OLC494	PSG	G	61.86	0.18		CONDITIONALLY QUALIFIED		
OLC495	PSG	G	61.04	0.18		CONDITIONALLY QUALIFIED		
OLC496	PSG	G	58.55	0.68		CONDITIONALLY QUALIFIED		
OLC497	PSG	G	61.52	0.11		CONDITIONALLY QUALIFIED		
OLC498	PSG	G	60.93	0.24		CONDITIONALLY QUALIFIED		
OLC499	PSG	G	58.86	0.27		CONDITIONALLY QUALIFIED		
OLC500	PSG	G	56.98	0.20		CONDITIONALLY QUALIFIED		
OLC502	PSG	G	58.07	0.22		CONDITIONALLY QUALIFIED		
OLC504	PSG	G	56.50	0.33		CONDITIONALLY QUALIFIED		
OLC506	PSG	G	53.98	0.43		CONDITIONALLY QUALIFIED		
OLC507	PSG	G	48.64	0.13		CONDITIONALLY QUALIFIED		
OLC508	PSG	G	54.50	0.17		CONDITIONALLY QUALIFIED		
OLC509	PSG	G	51.38	0.15		CONDITIONALLY QUALIFIED		
OLC510	PSG	G	55.73	0.26		CONDITIONALLY QUALIFIED		

Table 23 Test G: Results of Data Qualification of 1985 L-Area AC Flow Tests							Notes
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	
OLC512	PSG	G	56.63	0.27		CONDITIONALLY QUALIFIED	
OLC520	PSG	G	59.03	0.23		CONDITIONALLY QUALIFIED	
OLC524	PSG	G	60.20	0.19		CONDITIONALLY QUALIFIED	
OLC539	PSG	G	58.94	0.21		CONDITIONALLY QUALIFIED	
OLC542	PSG	G	58.38	0.31		CONDITIONALLY QUALIFIED	
OLC559	PSG	G	59.93	0.15		CONDITIONALLY QUALIFIED	
OLC562	PSG	G	61.74	0.20		CONDITIONALLY QUALIFIED	
OLC579	PSG	G	59.74	0.26		CONDITIONALLY QUALIFIED	
OLC582	PSG	G	59.43	0.19		CONDITIONALLY QUALIFIED	
OLC592	PSG	G	57.78	0.39		CONDITIONALLY QUALIFIED	
OLC593	PSG	G	56.17	0.24		CONDITIONALLY QUALIFIED	
OLC595	PSG	G	55.57	0.32		CONDITIONALLY QUALIFIED	
OLC596	PSG	G	54.63	0.49		CONDITIONALLY QUALIFIED	
OLC597	PSG	G	52.74	0.26		CONDITIONALLY QUALIFIED	
OLC598	PSG	G	54.16	0.35		CONDITIONALLY QUALIFIED	
OLC599	PSG	G	57.17	0.32		CONDITIONALLY QUALIFIED	
OLC600	PSG	G	58.16	0.24		CONDITIONALLY QUALIFIED	

Test H: Results of Data Qualification of 1985 L-Area AC Flow Tests							
				Precision			
			Average	2*Std Dev			
Measurement Type	Unit	Test			Bias (Unit)	Label	Notes
Plenum Inlet Temp 2 L1	C	H				FAILED	
Plenum Inlet Temp 2 L2	C	H				FAILED	
Plenum Inlet Temp 2 L3	C	H				FAILED	
Plenum Inlet Temp 2 L4	C	H				FAILED	
Plenum Inlet Temp 2 L5	C	H				FAILED	
Plenum Inlet Temp 2 L6	C	H				FAILED	
Plenum Inlet Temp 1 L1	C	H	59.19	0.31		CONDITIONALLY QUALIFIED	
Plenum Inlet Temp 1 L2	C	H	60.88	0.67		CONDITIONALLY QUALIFIED	
Plenum Inlet Temp 1 L3	C	H	60.54	0.72		CONDITIONALLY QUALIFIED	
Plenum Inlet Temp 1 L4	C	H	59.83	0.46		CONDITIONALLY QUALIFIED	
Plenum Inlet Temp 1 L5	C	H	59.75	0.64		CONDITIONALLY QUALIFIED	
Plenum Inlet Temp 1 L6	C	H	58.83	0.32		CONDITIONALLY QUALIFIED	
Pump Suction Temp 1	C	H	59.24	0.42		CONDITIONALLY QUALIFIED	
Pump Suction Temp 2	C	H	60.90	0.92		CONDITIONALLY QUALIFIED	
Pump Suction Temp 3	C	H	60.63	0.99		CONDITIONALLY QUALIFIED	
Pump Suction Temp 4	C	H	59.83	0.70		CONDITIONALLY QUALIFIED	
Pump Suction Temp 5	C	H	59.64	0.18		CONDITIONALLY QUALIFIED	
Pump Suction Temp 6	C	H	58.81	0.37		CONDITIONALLY QUALIFIED	
Barometric Pressure	PSIA	H	14.76	0.02		CONDITIONALLY QUALIFIED	
PS1	PSIA	H	14.69	0.08	0.11	QUALIFIED	
PS2	PSIA	H	14.66	0.06	0.11	QUALIFIED	
PS3	PSIA	H	14.50	0.10	0.11	QUALIFIED	
PS4	PSIA	H	15.02	0.06	0.11	QUALIFIED	
PS5	PSIA	H	15.21	0.08	0.11	QUALIFIED	
PS6	PSIA	H	14.69	0.08	0.11	QUALIFIED	
PD1	PSIG	H	188.49	0.21	0.60	QUALIFIED	
PD2	PSIG	H	187.58	0.17	0.60	QUALIFIED	
PD3	PSIG	H	183.91	0.28	0.60	QUALIFIED	
PD4	PSIG	H	194.18	0.19	0.60	QUALIFIED	
PD5	PSIG	H	194.00	0.12	0.60	QUALIFIED	
PD6	PSIG	H	185.15	0.12	0.60	QUALIFIED	
H1	PSIG	H	179.75	0.11	0.60	QUALIFIED	

Table 24 Test H: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
HI2	PSG	H	179.03	0.25	0.60	QUALIFIED
HI3	PSG	H	179.70	0.14	0.60	QUALIFIED
HI4	PSG	H	185.81	0.15	0.60	QUALIFIED
HI5	PSG	H	185.56	0.14	0.60	QUALIFIED
HI6	PSG	H	176.61	0.12	0.60	QUALIFIED
HD1	PSG	H	108.09	0.22	0.60	QUALIFIED
HD2	PSG	H	108.84	0.23	0.60	QUALIFIED
HD3	PSG	H	101.85	0.27	0.60	QUALIFIED
HD4	PSG	H	109.12	0.11	0.60	QUALIFIED
HD5	PSG	H	110.78	0.25	0.60	QUALIFIED
HD6	PSG	H	101.47	0.14	0.60	QUALIFIED
ECS1	PSG	H	104.03	0.27		CONDITIONALLY QUALIFIED
ECS4	PSG	H	106.77	0.36		CONDITIONALLY QUALIFIED
Ultrasonic - Loop 1	GFM	H	26797	86.35		CONDITIONALLY QUALIFIED
Ultrasonic - Loop 3	GFM	H	25870	159.01		CONDITIONALLY QUALIFIED
Ultrasonic - Loop 6	GFM	H	23925	70.78		CONDITIONALLY QUALIFIED
Tank - LPH	PSG	H	16.30	0.01	0.10	QUALIFIED
Tank - GANG1	PSG	H	17.47	0.05	0.10	QUALIFIED
M60B-OLC493	PSG	H	16.89	0.01	0.10	QUALIFIED
M60B-OLC500	PSG	H	16.41	0.03	0.10	QUALIFIED
M60B-OLC600	PSG	H	16.42	0.01	0.10	QUALIFIED
PCL Pressure (System A)	PSG	H	75.99	0.14	1.65	QUALIFIED
PCL Pressure (System B)	PSG	H	75.51	0.50	0.90	QUALIFIED
OLC1	PSG	H	74.19	0.07		CONDITIONALLY QUALIFIED
OLC6	PSG	H	70.58	0.12		CONDITIONALLY QUALIFIED
OLC15	PSG	H	73.74	0.20		CONDITIONALLY QUALIFIED
OLC26	PSG	H	70.84	0.17		CONDITIONALLY QUALIFIED
OLC34	PSG	H	70.57	0.08		CONDITIONALLY QUALIFIED
OLC47	PSG	H	73.12	0.12		CONDITIONALLY QUALIFIED
OLC59	PSG	H	71.12	0.17		CONDITIONALLY QUALIFIED
OLC71	PSG	H	73.73	0.17		CONDITIONALLY QUALIFIED
OLC83	PSG	H	72.82	0.16		CONDITIONALLY QUALIFIED

Table 24 Test H: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	Notes	
OLC106	PSG	H	69.04	0.16		CONDITIONALLY QUALIFIED		
OLC110	PSG	H	72.92	0.07		CONDITIONALLY QUALIFIED		
OLC115	PSG	H	78.48	0.23		CONDITIONALLY QUALIFIED		
OLC124	PSG	H	69.97	0.32		CONDITIONALLY QUALIFIED		
OLC129	PSG	H	73.59	0.14		CONDITIONALLY QUALIFIED		
OLC135	PSG	H	72.96	0.06		CONDITIONALLY QUALIFIED		
OLC148	PSG	H	71.57	0.71		CONDITIONALLY QUALIFIED		
OLC161	PSG	H	76.16	0.07		CONDITIONALLY QUALIFIED		
OLC177	PSG	H	73.13	0.16		CONDITIONALLY QUALIFIED		
OLC182	PSG	H	69.22	0.11		CONDITIONALLY QUALIFIED		
OLC198	PSG	H	74.52	0.38		CONDITIONALLY QUALIFIED		
OLC210	PSG	H	67.74	0.11		CONDITIONALLY QUALIFIED		
OLC214	PSG	H	68.61	0.31		CONDITIONALLY QUALIFIED		
OLC218	PSG	H	75.21	0.32		CONDITIONALLY QUALIFIED		
OLC221	PSG	H	75.78	0.09		CONDITIONALLY QUALIFIED		
OLC223	PSG	H	85.83	0.12		CONDITIONALLY QUALIFIED		
OLC230	PSG	H	81.48	0.31		CONDITIONALLY QUALIFIED		
OLC236	PSG	H	77.73	0.08		CONDITIONALLY QUALIFIED		
OLC238	PSG	H	70.42	0.34		CONDITIONALLY QUALIFIED		
OLC243	PSG	H	74.59	0.13		CONDITIONALLY QUALIFIED		
OLC248	PSG	H	69.91	0.08		CONDITIONALLY QUALIFIED		
OLC263	PSG	H	75.28	0.30		CONDITIONALLY QUALIFIED		
OLC280	PSG	H	80.81	0.56		CONDITIONALLY QUALIFIED		
OLC295	PSG	H	73.83	0.42		CONDITIONALLY QUALIFIED		
OLC313	PSG	H	79.88	0.49		CONDITIONALLY QUALIFIED		
OLC354	PSG	H	70.38	0.21		CONDITIONALLY QUALIFIED		
OLC358	PSG	H	69.80	0.64		CONDITIONALLY QUALIFIED		
OLC360	PSG	H	71.98	0.52		CONDITIONALLY QUALIFIED		
OLC361	PSG	H	76.17	0.16		CONDITIONALLY QUALIFIED		
OLC363	PSG	H	87.26	0.15		CONDITIONALLY QUALIFIED		
OLC367	PSG	H	88.25	0.23		CONDITIONALLY QUALIFIED		
OLC372	PSG	H	86.20	0.25		CONDITIONALLY QUALIFIED		

Table 24		Test H: Results of Data Qualification of 1985 L-Area AC Flow Tests					
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes
01C373	PSG	H	93.38	0.24		CONDITIONALLY QUALIFIED	
01C377	PSG	H	91.49	0.27		CONDITIONALLY QUALIFIED	
01C382	PSG	H	72.77	0.19		CONDITIONALLY QUALIFIED	
01C406	PSG	H	89.03	0.25		CONDITIONALLY QUALIFIED	
01C432	PSG	H	72.96	0.06		CONDITIONALLY QUALIFIED	
01C450	PSG	H	85.78	0.25		CONDITIONALLY QUALIFIED	
01C471	PSG	H	78.11	0.04		CONDITIONALLY QUALIFIED	
01C472	PSG	H	70.45	0.12		CONDITIONALLY QUALIFIED	
01C475	PSG	H	83.89	0.27		CONDITIONALLY QUALIFIED	
01C482	PSG	H	94.98	0.47		CONDITIONALLY QUALIFIED	
01C484	PSG	H	96.20	0.22		CONDITIONALLY QUALIFIED	
01C486	PSG	H	99.23	0.39		CONDITIONALLY QUALIFIED	
01C487	PSG	H	92.18	0.04		CONDITIONALLY QUALIFIED	
01C488	PSG	H	93.95	0.61		CONDITIONALLY QUALIFIED	
01C490	PSG	H	98.75	0.08		CONDITIONALLY QUALIFIED	
01C491	PSG	H	95.09	0.29		CONDITIONALLY QUALIFIED	
01C492	PSG	H	99.32	0.31		CONDITIONALLY QUALIFIED	
01C493	PSG	H	96.75	0.10		CONDITIONALLY QUALIFIED	
01C494	PSG	H	98.78	0.12		CONDITIONALLY QUALIFIED	
01C495	PSG	H	97.83	0.29		CONDITIONALLY QUALIFIED	
01C496	PSG	H	94.85	0.20		CONDITIONALLY QUALIFIED	
01C497	PSG	H	97.02	0.31		CONDITIONALLY QUALIFIED	
01C498	PSG	H	96.75	0.21		CONDITIONALLY QUALIFIED	
01C499	PSG	H	94.41	0.33		CONDITIONALLY QUALIFIED	
01C500	PSG	H	90.89	0.10		CONDITIONALLY QUALIFIED	
01C502	PSG	H	94.49	0.40		CONDITIONALLY QUALIFIED	
01C504	PSG	H	94.29	0.47		CONDITIONALLY QUALIFIED	
01C506	PSG	H	90.48	0.08		CONDITIONALLY QUALIFIED	
01C507	PSG	H	79.71	0.08		CONDITIONALLY QUALIFIED	
01C508	PSG	H	93.21	0.40		CONDITIONALLY QUALIFIED	
01C509	PSG	H	82.29	0.20		CONDITIONALLY QUALIFIED	
01C510	PSG	H	91.00	0.59		CONDITIONALLY QUALIFIED	

Table 24		Test H: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OL C512	PSG	H	94.36	0.81		CONDITIONALLY QUALIFIED		
OL C520	PSG	H	94.51	0.80		CONDITIONALLY QUALIFIED		
OL C524	PSG	H	97.62	0.41		CONDITIONALLY QUALIFIED		
OL C539	PSG	H	95.07	0.26		CONDITIONALLY QUALIFIED		
OL C542	PSG	H	93.44	0.29		CONDITIONALLY QUALIFIED		
OL C559	PSG	H	94.37	0.35		CONDITIONALLY QUALIFIED		
OL C562	PSG	H	98.18	0.50		CONDITIONALLY QUALIFIED		
OL C579	PSG	H	96.38	0.04		CONDITIONALLY QUALIFIED		
OL C582	PSG	H	96.18	0.47		CONDITIONALLY QUALIFIED		
OL C592	PSG	H	94.66	0.42		CONDITIONALLY QUALIFIED		
OL C593	PSG	H	90.82	0.47		CONDITIONALLY QUALIFIED		
OL C595	PSG	H	88.47	0.63		CONDITIONALLY QUALIFIED		
OL C596	PSG	H	84.64	1.02		CONDITIONALLY QUALIFIED		
OL C597	PSG	H	82.86	1.08		CONDITIONALLY QUALIFIED		
OL C598	PSG	H	85.44	0.76		CONDITIONALLY QUALIFIED		
OL C599	PSG	H	91.34	0.24		CONDITIONALLY QUALIFIED		
OL C600	PSG	H	93.39	0.46		CONDITIONALLY QUALIFIED		

Table 25 Test I: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
Pk num Inlet Temp 2 L1	C	I				FAILED
Pk num Inlet Temp 2 L2	C	I				FAILED
Pk num Inlet Temp 2 L3	C	I				FAILED
Pk num Inlet Temp 2 L4	C	I				FAILED
Pk num Inlet Temp 2 L5	C	I				FAILED
Pk num Inlet Temp 2 L6	C	I				FAILED
Pk num Inlet Temp 1 L1	C	I	59.45	0.37		CONDITIONALLY QUALIFIED
Pk num Inlet Temp 1 L2	C	I	60.92	0.35		CONDITIONALLY QUALIFIED
Pk num Inlet Temp 1 L3	C	I	60.68	0.34		CONDITIONALLY QUALIFIED
Pk num Inlet Temp 1 L4	C	I	60.10	0.35		CONDITIONALLY QUALIFIED
Pk num Inlet Temp 1 L5	C	I	60.17	0.36		CONDITIONALLY QUALIFIED
Pk num Inlet Temp 1 L6	C	I	59.26	0.36		CONDITIONALLY QUALIFIED
Pump Suction Temp 1	C	I	59.42	0.38		CONDITIONALLY QUALIFIED
Pump Suction Temp 2	C	I	60.74	0.35		CONDITIONALLY QUALIFIED
Pump Suction Temp 3	C	I	60.60	0.33		CONDITIONALLY QUALIFIED
Pump Suction Temp 4	C	I	59.95	0.33		CONDITIONALLY QUALIFIED
Pump Suction Temp 5	C	I	59.94	0.37		CONDITIONALLY QUALIFIED
Pump Suction Temp 6	C	I	59.26	0.34		CONDITIONALLY QUALIFIED
Barometric Pressure	PSIA	I	14.74	0.00		CONDITIONALLY QUALIFIED
PS1	PSIA	I	14.38	0.07	0.11	QUALIFIED
PS2	PSIA	I	14.34	0.05	0.11	QUALIFIED
PS3	PSIA	I	14.10	0.15	0.11	QUALIFIED
PS4	PSIA	I	14.71	0.05	0.11	QUALIFIED
PS5	PSIA	I	14.87	0.07	0.11	QUALIFIED
PS6	PSIA	I	14.33	0.07	0.11	QUALIFIED
PD1	PSIG	I	184.84	0.12	0.60	QUALIFIED
PD2	PSIG	I	183.74	0.16	0.60	QUALIFIED
PD3	PSIG	I	180.05	0.11	0.60	QUALIFIED
PD4	PSIG	I	190.54	0.07	0.60	QUALIFIED
PD5	PSIG	I	190.20	0.13	0.60	QUALIFIED
PD6	PSIG	I	181.42	0.10	0.60	QUALIFIED
HI1	PSIG	I	175.76	0.10	0.60	QUALIFIED

Table 25 Test I: Results of Data Qualification of 1985 L-Area AC Flow Tests									
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes		
HL1	PSG	I	174.87	0.20	0.60	QUALIFIED			
HL3	PSG	I	175.71	0.14	0.60	QUALIFIED			
HL4	PSG	I	181.81	0.16	0.60	QUALIFIED			
HL5	PSG	I	181.46	0.12	0.60	QUALIFIED			
HL6	PSG	I	172.55	0.08	0.60	QUALIFIED			
HL1	PSG	I	103.13	0.15	0.60	QUALIFIED			
HL2	PSG	I	104.00	0.10	0.60	QUALIFIED			
HL3	PSG	I	97.20	0.19	0.60	QUALIFIED			
HL4	PSG	I	104.21	0.07	0.60	QUALIFIED			
HL5	PSG	I	105.63	0.18	0.60	QUALIFIED			
HL6	PSG	I	96.88	0.20	0.60	QUALIFIED			
ECS1	PSG	I	99.13	0.21		CONDITIONALLY QUALIFIED			
ECS4	PSG	I	101.88	0.26		CONDITIONALLY QUALIFIED			
Ultrasonic - Loop 1	GPM	I	27325	98.36		CONDITIONALLY QUALIFIED			Not Adjusted for Zero Offset
Ultrasonic - Loop 3	GPM	I	26940	0.00		CONDITIONALLY QUALIFIED			Not Adjusted for Zero Offset
Ultrasonic - Loop 6	GPM	I	24410	56.57		CONDITIONALLY QUALIFIED			Not Adjusted for Zero Offset
Tank - LPH	PSG	I	16.25	0.01	0.10	QUALIFIED			
Tank - GANG1	PSG	I	17.42	0.00	0.10	QUALIFIED			
M60B-OLC493	PSG	I	16.90	0.02	0.10	QUALIFIED			
M60B-OLC500	PSG	I	16.40	0.00	0.10	QUALIFIED			
M60B-OLC600	PSG	I	16.40	0.01	0.10	QUALIFIED			
PCL Pressure (System A)	PSG	I	72.24	0.11	1.65	QUALIFIED			
PCL Pressure (System B)	PSG	I	71.85	0.60	0.90	QUALIFIED			
OLC1	PSG	I	70.46	0.07		CONDITIONALLY QUALIFIED			
OLC6	PSG	I	67.16	0.10		CONDITIONALLY QUALIFIED			
OLC15	PSG	I	69.98	0.07		CONDITIONALLY QUALIFIED			
OLC26	PSG	I	67.26	0.12		CONDITIONALLY QUALIFIED			
OLC34	PSG	I	66.95	0.10		CONDITIONALLY QUALIFIED			
OLC47	PSG	I	69.49	0.08		CONDITIONALLY QUALIFIED			
OLC59	PSG	I	67.54	0.13		CONDITIONALLY QUALIFIED			
OLC71	PSG	I	70.04	0.14		CONDITIONALLY QUALIFIED			
OLC83	PSG	I	69.14	0.08		CONDITIONALLY QUALIFIED			

Table 25 Test 1: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OL C106	PSG	I	65.68	0.15		CONDITIONALLY QUALIFIED		
OL C110	PSG	I	69.15	0.27		CONDITIONALLY QUALIFIED		
OL C115	PSG	I	74.66	0.38		CONDITIONALLY QUALIFIED		
OL C124	PSG	I	66.23	0.18		CONDITIONALLY QUALIFIED		
OL C129	PSG	I	69.95	0.13		CONDITIONALLY QUALIFIED		
OL C135	PSG	I	69.35	0.10		CONDITIONALLY QUALIFIED		
OL C148	PSG	I	67.81	0.35		CONDITIONALLY QUALIFIED		
OL C161	PSG	I	72.31	0.28		CONDITIONALLY QUALIFIED		
OL C177	PSG	I	69.51	0.16		CONDITIONALLY QUALIFIED		
OL C182	PSG	I	65.91	0.16		CONDITIONALLY QUALIFIED		
OL C198	PSG	I	70.77	0.30		CONDITIONALLY QUALIFIED		
OL C210	PSG	I	64.26	0.12		CONDITIONALLY QUALIFIED		
OL C214	PSG	I	65.22	0.40		CONDITIONALLY QUALIFIED		
OL C218	PSG	I	71.61	0.33		CONDITIONALLY QUALIFIED		
OL C221	PSG	I	71.97	0.19		CONDITIONALLY QUALIFIED		
OL C223	PSG	I	81.41	0.32		CONDITIONALLY QUALIFIED		
OL C230	PSG	I	77.41	0.37		CONDITIONALLY QUALIFIED		
OL C236	PSG	I	73.77	0.11		CONDITIONALLY QUALIFIED		
OL C238	PSG	I	66.82	0.33		CONDITIONALLY QUALIFIED		
OL C243	PSG	I	70.79	0.26		CONDITIONALLY QUALIFIED		
OL C248	PSG	I	66.42	0.21		CONDITIONALLY QUALIFIED		
OL C263	PSG	I	71.66	0.11		CONDITIONALLY QUALIFIED		
OL C280	PSG	I	76.76	0.21		CONDITIONALLY QUALIFIED		
OL C295	PSG	I	70.20	0.03		CONDITIONALLY QUALIFIED		
OL C313	PSG	I	75.83	0.28		CONDITIONALLY QUALIFIED		
OL C354	PSG	I	66.87	0.17		CONDITIONALLY QUALIFIED		
OL C358	PSG	I	66.42	0.20		CONDITIONALLY QUALIFIED		
OL C360	PSG	I	68.29	0.19		CONDITIONALLY QUALIFIED		
OL C361	PSG	I	72.43	0.31		CONDITIONALLY QUALIFIED		
OL C363	PSG	I	82.80	0.08		CONDITIONALLY QUALIFIED		
OL C367	PSG	I	83.93	0.10		CONDITIONALLY QUALIFIED		
OL C372	PSG	I	83.85	0.37		CONDITIONALLY QUALIFIED		

Table 25		Test 1: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OL C373	PSG	I	88.67	0.26		CONDITIONALLY QUALIFIED		
OL C377	PSG	I	86.89	0.21		CONDITIONALLY QUALIFIED		
OL C382	PSG	I	69.07	0.12		CONDITIONALLY QUALIFIED		
OL C406	PSG	I	84.59	0.22		CONDITIONALLY QUALIFIED		
OL C432	PSG	I	69.36	0.37		CONDITIONALLY QUALIFIED		
OL C450	PSG	I	81.35	0.08		CONDITIONALLY QUALIFIED		
OL C471	PSG	I	74.25	0.13		CONDITIONALLY QUALIFIED		
OL C472	PSG	I	67.00	0.14		CONDITIONALLY QUALIFIED		
OL C475	PSG	I	79.62	0.17		CONDITIONALLY QUALIFIED		
OL C482	PSG	I	90.52	0.27		CONDITIONALLY QUALIFIED		
OL C484	PSG	I	91.40	0.18		CONDITIONALLY QUALIFIED		
OL C486	PSG	I	94.47	0.27		CONDITIONALLY QUALIFIED		
OL C487	PSG	I	87.42	0.16		CONDITIONALLY QUALIFIED		
OL C488	PSG	I	89.22	0.14		CONDITIONALLY QUALIFIED		
OL C490	PSG	I	94.00	0.38		CONDITIONALLY QUALIFIED		
OL C491	PSG	I	90.38	0.29		CONDITIONALLY QUALIFIED		
OL C492	PSG	I	94.27	0.38		CONDITIONALLY QUALIFIED		
OL C493	PSG	I	92.09	0.36		CONDITIONALLY QUALIFIED		
OL C494	PSG	I	93.81	0.15		CONDITIONALLY QUALIFIED		
OL C495	PSG	I	92.92	0.11		CONDITIONALLY QUALIFIED		
OL C496	PSG	I	90.18	0.41		CONDITIONALLY QUALIFIED		
OL C497	PSG	I	92.11	0.46		CONDITIONALLY QUALIFIED		
OL C498	PSG	I	92.11	0.31		CONDITIONALLY QUALIFIED		
OL C499	PSG	I	89.67	0.06		CONDITIONALLY QUALIFIED		
OL C500	PSG	I	86.40	0.37		CONDITIONALLY QUALIFIED		
OL C502	PSG	I	89.77	0.26		CONDITIONALLY QUALIFIED		
OL C504	PSG	I	89.18	0.21		CONDITIONALLY QUALIFIED		
OL C506	PSG	I	85.45	0.43		CONDITIONALLY QUALIFIED		
OL C507	PSG	I	75.64	0.45		CONDITIONALLY QUALIFIED		
OL C508	PSG	I	87.70	0.60		CONDITIONALLY QUALIFIED		
OL C509	PSG	I	78.52	0.14		CONDITIONALLY QUALIFIED		
OL C510	PSG	I	86.07	0.33		CONDITIONALLY QUALIFIED		

Table 25		Test 1: Results of Data Qualification of 1985 L-Area AC Flow Tests					
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes
OL 512	PSIG	I	89.24	0.29		CONDITIONALLY QUALIFIED	
OL 520	PSIG	I	90.03	0.36		CONDITIONALLY QUALIFIED	
OL 524	PSIG	I	93.16	0.29		CONDITIONALLY QUALIFIED	
OL 539	PSIG	I	90.38	0.49		CONDITIONALLY QUALIFIED	
OL 542	PSIG	I	88.68	0.38		CONDITIONALLY QUALIFIED	
OL 559	PSIG	I	89.72	0.30		CONDITIONALLY QUALIFIED	
OL 562	PSIG	I	93.35	0.24		CONDITIONALLY QUALIFIED	
OL 579	PSIG	I	91.62	0.24		CONDITIONALLY QUALIFIED	
OL 582	PSIG	I	91.40	0.12		CONDITIONALLY QUALIFIED	
OL 592	PSIG	I	90.01	0.26		CONDITIONALLY QUALIFIED	
OL 593	PSIG	I	86.30	0.18		CONDITIONALLY QUALIFIED	
OL 595	PSIG	I	84.32	0.66		CONDITIONALLY QUALIFIED	
OL 596	PSIG	I	81.13	0.13		CONDITIONALLY QUALIFIED	
OL 597	PSIG	I	78.52	0.19		CONDITIONALLY QUALIFIED	
OL 598	PSIG	I	81.31	0.95		CONDITIONALLY QUALIFIED	
OL 599	PSIG	I	86.84	0.53		CONDITIONALLY QUALIFIED	
OL 600	PSIG	I	88.90	0.23		CONDITIONALLY QUALIFIED	

Table 26		Test J: Results of Data Qualification of 1985 L-Area AC Flow Tests					

Table 26 Test J: Results of Data Qualification of 1985 L-Area AC Flow Tests									
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	Notes		
HL	PSG	J	163.99	0.72	0.60	QUALIFIED			
HL	PSG	J	165.11	0.71	0.60	QUALIFIED			
HL	PSG	J	171.68	0.76	0.60	QUALIFIED			
HL	PSG	J	170.74	0.75	0.60	QUALIFIED			
HL	PSG	J	158.71	0.76	0.60	QUALIFIED			
HD1	PSG	J	66.29	0.18	0.60	QUALIFIED			
HD2	PSG	J	84.24	0.27	0.60	QUALIFIED			
HD3	PSG	J	76.45	0.06	0.60	QUALIFIED			
HD4	PSG	J	84.50	0.25	0.60	QUALIFIED			
HD5	PSG	J	85.28	0.15	0.60	QUALIFIED			
HD6	PSG	J	72.27	0.19	0.60	QUALIFIED			
EC1	PSG	J	66.61	0.14		CONDITIONALLY QUALIFIED			
EC4	PSG	J	81.63	0.15		CONDITIONALLY QUALIFIED			
Ultrasonic - Loop 1	GFM	J	-12074	63.19		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset		
Ultrasonic - Loop 3	GFM	J	27970	284.86		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset		
Ultrasonic - Loop 6	GFM	J	26974	133.07		CONDITIONALLY QUALIFIED	Not Adjusted for Zero Offset		
Tank - LPH	PSG	J	16.30	0.06	0.10	QUALIFIED			
Tank - GANG1	PSG	J	17.29	0.02	0.10	QUALIFIED			
M60B-OLC493	PSG	J	16.92	0.02	0.10	QUALIFIED			
M60B-OLC500	PSG	J	17.08	0.03	0.10	QUALIFIED			
M60B-OLC600	PSG	J	16.36	0.03	0.10	QUALIFIED			
PCL Pressure (System A)	PSG	J	50.51	0.23	1.65	QUALIFIED			
PCL Pressure (System B)	PSG	J	50.04	0.55	0.90	QUALIFIED			
OLC1	PSG	J	48.10	0.12		CONDITIONALLY QUALIFIED			
OLC6	PSG	J	46.18	0.23		CONDITIONALLY QUALIFIED			
OLC15	PSG	J	48.29	0.06		CONDITIONALLY QUALIFIED			
OLC26	PSG	J	46.11	0.30		CONDITIONALLY QUALIFIED			
OLC34	PSG	J	47.18	0.18		CONDITIONALLY QUALIFIED			
OLC47	PSG	J	48.06	0.06		CONDITIONALLY QUALIFIED			
OLC59	PSG	J	46.82	0.11		CONDITIONALLY QUALIFIED			
OLC71	PSG	J	47.41	0.17		CONDITIONALLY QUALIFIED			
OLC83	PSG	J	48.72	0.21		CONDITIONALLY QUALIFIED			

Table 26								Test J: Results of Data Qualification of 1985 L-Area AC Flow Tests							

Table 26 Test J: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Blas (Unit)	Label	Notes	
OLC373	PSG	J	49.59	0.12		CONDITIONALLY QUALIFIED		
OLC377	PSG	J	51.66	0.24		CONDITIONALLY QUALIFIED		
OLC382	PSG	J	44.98	0.20		CONDITIONALLY QUALIFIED		
OLC406	PSG	J	64.26	0.15		CONDITIONALLY QUALIFIED		
OLC432	PSG	J	52.21	0.19		CONDITIONALLY QUALIFIED		
OLC450	PSG	J	63.69	0.23		CONDITIONALLY QUALIFIED		
OLC471	PSG	J	54.69	0.19		CONDITIONALLY QUALIFIED		
OLC472	PSG	J	48.30	0.26		CONDITIONALLY QUALIFIED		
OLC475	PSG	J	57.68	0.12		CONDITIONALLY QUALIFIED		
OLC482	PSG	J	66.91	0.26		CONDITIONALLY QUALIFIED		
OLC484	PSG	J	64.30	0.70		CONDITIONALLY QUALIFIED		
OLC486	PSG	J	62.26	0.18		CONDITIONALLY QUALIFIED		
OLC487	PSG	J	50.49	0.15		CONDITIONALLY QUALIFIED		
OLC488	PSG	J	51.52	0.34		CONDITIONALLY QUALIFIED		
OLC490	PSG	J	53.45	0.53		CONDITIONALLY QUALIFIED		
OLC491	PSG	J	50.54	0.21		CONDITIONALLY QUALIFIED		
OLC492	PSG	J	50.02	0.19		CONDITIONALLY QUALIFIED		
OLC493	PSG	J	50.46	0.13		CONDITIONALLY QUALIFIED		
OLC494	PSG	J	51.61	0.21		CONDITIONALLY QUALIFIED		
OLC495	PSG	J	51.00	0.39		CONDITIONALLY QUALIFIED		
OLC496	PSG	J	51.64	0.18		CONDITIONALLY QUALIFIED		
OLC497	PSG	J	51.82	0.21		CONDITIONALLY QUALIFIED		
OLC498	PSG	J	51.78	0.25		CONDITIONALLY QUALIFIED		
OLC499	PSG	J	52.34	0.23		CONDITIONALLY QUALIFIED		
OLC500	PSG	J	52.06	0.34		CONDITIONALLY QUALIFIED		
OLC502	PSG	J	51.96	0.12		CONDITIONALLY QUALIFIED		
OLC504	PSG	J	51.67	0.18		CONDITIONALLY QUALIFIED		
OLC506	PSG	J	52.26	0.53		CONDITIONALLY QUALIFIED		
OLC507	PSG	J	49.11	0.16		CONDITIONALLY QUALIFIED		
OLC508	PSG	J	51.90	0.32		CONDITIONALLY QUALIFIED		
OLC509	PSG	J	50.24	0.09		CONDITIONALLY QUALIFIED		
OLC510	PSG	J	51.92	0.23		CONDITIONALLY QUALIFIED		

Table 26		Test J: Results of Data Qualification of 1985 L-Area AC Flow Tests					
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes
OL C512	PSG	J	47.75	0.26		CONDITIONALLY QUALIFIED	
OL C520	PSG	J	66.06	0.43		CONDITIONALLY QUALIFIED	
OL C524	PSG	J	72.31	0.20		CONDITIONALLY QUALIFIED	
OL C539	PSG	J	71.52	0.21		CONDITIONALLY QUALIFIED	
OL C542	PSG	J	70.73	0.44		CONDITIONALLY QUALIFIED	
OL C559	PSG	J	70.71	0.47		CONDITIONALLY QUALIFIED	
OL C562	PSG	J	75.37	0.24		CONDITIONALLY QUALIFIED	
OL C579	PSG	J	73.97	0.40		CONDITIONALLY QUALIFIED	
OL C582	PSG	J	69.37	0.15		CONDITIONALLY QUALIFIED	
OL C592	PSG	J	62.13	0.23		CONDITIONALLY QUALIFIED	
OL C593	PSG	J	65.53	0.40		CONDITIONALLY QUALIFIED	
OL C595	PSG	J	69.76	0.18		CONDITIONALLY QUALIFIED	
OL C596	PSG	J	66.90	0.25		CONDITIONALLY QUALIFIED	
OL C597	PSG	J	66.25	0.30		CONDITIONALLY QUALIFIED	
OL C598	PSG	J	67.35	0.32		CONDITIONALLY QUALIFIED	
OL C599	PSG	J	69.41	0.08		CONDITIONALLY QUALIFIED	
OL C600	PSG	J	69.66	0.12		CONDITIONALLY QUALIFIED	

Table 27 Test K: Results of Data Qualification of 1985 L-Area AC Flow Tests								
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
Plenum Inlet Temp 2 L1	C	K	60.46	1.47		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L2	C	K	59.42	2.47		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L3	C	K	61.47	2.93		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L4	C	K	54.09	2.51		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L5	C	K	60.34	2.83		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 2 L6	C	K	61.62	2.36		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L1	C	K	60.34	1.45		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L2	C	K	59.32	2.51		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L3	C	K	61.27	3.01		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L4	C	K	54.20	2.38		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L5	C	K	60.35	3.06		CONDITIONALLY QUALIFIED		
Plenum Inlet Temp 1 L6	C	K	61.52	2.56		CONDITIONALLY QUALIFIED		
Pump Suction Temp 1	C	K	60.33	1.38		CONDITIONALLY QUALIFIED		
Pump Suction Temp 2	C	K	55.04	4.70		CONDITIONALLY QUALIFIED		
Pump Suction Temp 3	C	K	61.46	2.00		CONDITIONALLY QUALIFIED		
Pump Suction Temp 4	C	K	56.06	2.78		CONDITIONALLY QUALIFIED		
Pump Suction Temp 5	C	K	55.32	2.03		CONDITIONALLY QUALIFIED		
Pump Suction Temp 6	C	K	61.37	2.17		CONDITIONALLY QUALIFIED		
Barometric Pressure	PSIA	K	14.77	0.01		CONDITIONALLY QUALIFIED		
PS1	PSIA	K	12.29	0.15	0.11	QUALIFIED		
PS2	PSIA	K	21.75	0.08	0.11	QUALIFIED		
PS3	PSIA	K	12.00	0.17	0.11	QUALIFIED		
PS4	PSIA	K	21.82	0.07	0.11	QUALIFIED		
PS5	PSIA	K	21.77	0.07	0.11	QUALIFIED		
PS6	PSIA	K	12.22	0.14	0.11	QUALIFIED		
PD1	PSIG	K	159.72	0.28	0.60	QUALIFIED		
PD2	PSIG	K	7.75	0.01	0.60	QUALIFIED		
PD3	PSIG	K	147.93	0.40	0.60	QUALIFIED		
PD4	PSIG	K	7.74	0.02	0.60	QUALIFIED		
PD5	PSIG	K	7.73	0.01	0.60	QUALIFIED		
PD6	PSIG	K	154.26	0.58	0.60	QUALIFIED		
HI1	PSIG	K	148.26	0.30	0.60	QUALIFIED		

Table 27								Test K: Results of Data Qualification of 1985 L-Area AC Flow Tests							

Table 27 Test K: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label
OL C106	PSG	K	22.89	0.09		CONDITIONALLY QUALIFIED
OL C110	PSG	K	26.60	0.20		CONDITIONALLY QUALIFIED
OL C115	PSG	K	30.70	0.21		CONDITIONALLY QUALIFIED
OL C124	PSG	K	23.66	0.23		CONDITIONALLY QUALIFIED
OL C129	PSG	K	25.39	0.14		CONDITIONALLY QUALIFIED
OL C135	PSG	K	25.16	0.14		CONDITIONALLY QUALIFIED
OL C148	PSG	K	25.00	0.18		CONDITIONALLY QUALIFIED
OL C161	PSG	K	26.16	0.08		CONDITIONALLY QUALIFIED
OL C177	PSG	K	25.10	0.04		CONDITIONALLY QUALIFIED
OL C182	PSG	K	23.68	0.11		CONDITIONALLY QUALIFIED
OL C198	PSG	K	23.84	0.20		CONDITIONALLY QUALIFIED
OL C210	PSG	K	24.49	0.11		CONDITIONALLY QUALIFIED
OL C214	PSG	K	22.72	0.13		CONDITIONALLY QUALIFIED
OL C218	PSG	K	30.51	0.24		CONDITIONALLY QUALIFIED
OL C221	PSG	K	27.66	0.51		CONDITIONALLY QUALIFIED
OL C223	PSG	K	37.29	0.15		CONDITIONALLY QUALIFIED
OL C230	PSG	K	35.92	0.21		CONDITIONALLY QUALIFIED
OL C236	PSG	K	33.83	0.35		CONDITIONALLY QUALIFIED
OL C238	PSG	K	26.79	0.27		CONDITIONALLY QUALIFIED
OL C243	PSG	K	28.05	0.17		CONDITIONALLY QUALIFIED
OL C248	PSG	K	24.80	0.09		CONDITIONALLY QUALIFIED
OL C263	PSG	K	27.04	0.12		CONDITIONALLY QUALIFIED
OL C280	PSG	K	29.92	0.19		CONDITIONALLY QUALIFIED
OL C295	PSG	K	25.06	0.13		CONDITIONALLY QUALIFIED
OL C313	PSG	K	25.39	0.19		CONDITIONALLY QUALIFIED
OL C354	PSG	K	24.38	0.13		CONDITIONALLY QUALIFIED
OL C358	PSG	K	25.51	0.07		CONDITIONALLY QUALIFIED
OL C360	PSG	K	24.73	0.64		CONDITIONALLY QUALIFIED
OL C361	PSG	K	25.42	0.94		CONDITIONALLY QUALIFIED
OL C363	PSG	K	38.64	0.15		CONDITIONALLY QUALIFIED
OL C367	PSG	K	40.86	0.44		CONDITIONALLY QUALIFIED
OL C372	PSG	K	40.52	0.28		CONDITIONALLY QUALIFIED

Table K: Results of Data Qualification of 1985 L-Area AC Flow Tests							
Table 27							
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes
OL C373	PSG	K	45.41	0.42		CONDITIONALLY QUALIFIED	
OL C377	PSG	K	43.07	0.32		CONDITIONALLY QUALIFIED	
OL C382	PSG	K	24.13	0.42		CONDITIONALLY QUALIFIED	
OL C406	PSG	K	34.19	0.10		CONDITIONALLY QUALIFIED	
OL C432	PSG	K	24.12	0.08		CONDITIONALLY QUALIFIED	
OL C450	PSG	K	26.09	0.10		CONDITIONALLY QUALIFIED	
OL C471	PSG	K	28.77	0.22		CONDITIONALLY QUALIFIED	
OL C472	PSG	K	25.34	0.16		CONDITIONALLY QUALIFIED	
OL C475	PSG	K	30.20	0.41		CONDITIONALLY QUALIFIED	
OL C482	PSG	K	44.37	0.26		CONDITIONALLY QUALIFIED	
OL C484	PSG	K	46.23	0.23		CONDITIONALLY QUALIFIED	
OL C486	PSG	K	49.14	0.27		CONDITIONALLY QUALIFIED	
OL C487	PSG	K	43.80	0.37		CONDITIONALLY QUALIFIED	
OL C488	PSG	K	44.78	0.59		CONDITIONALLY QUALIFIED	
OL C490	PSG	K	49.34	0.22		CONDITIONALLY QUALIFIED	
OL C491	PSG	K	45.10	0.15		CONDITIONALLY QUALIFIED	
OL C492	PSG	K	48.87	0.24		CONDITIONALLY QUALIFIED	
OL C493	PSG	K	47.37	0.14		CONDITIONALLY QUALIFIED	
OL C494	PSG	K	49.11	0.18		CONDITIONALLY QUALIFIED	
OL C495	PSG	K	48.25	0.12		CONDITIONALLY QUALIFIED	
OL C496	PSG	K	46.09	0.46		CONDITIONALLY QUALIFIED	
OL C497	PSG	K	48.79	0.16		CONDITIONALLY QUALIFIED	
OL C498	PSG	K	48.84	0.16		CONDITIONALLY QUALIFIED	
OL C499	PSG	K	45.51	0.20		CONDITIONALLY QUALIFIED	
OL C500	PSG	K	41.49	0.30		CONDITIONALLY QUALIFIED	
OL C502	PSG	K	40.16	0.05		CONDITIONALLY QUALIFIED	
OL C504	PSG	K	36.96	0.27		CONDITIONALLY QUALIFIED	
OL C506	PSG	K	29.27	0.20		CONDITIONALLY QUALIFIED	
OL C507	PSG	K	25.38	0.12		CONDITIONALLY QUALIFIED	
OL C508	PSG	K	31.68	0.17		CONDITIONALLY QUALIFIED	
OL C509	PSG	K	27.95	0.10		CONDITIONALLY QUALIFIED	
OL C510	PSG	K	29.39	0.05		CONDITIONALLY QUALIFIED	

Table 27		Test K: Results of Data Qualification of 1985 L-Area AC Flow Tests						
Measurement Type	Unit	Test	Average	Precision 2*Std Dev	Bias (Unit)	Label	Notes	
OL 5512	PSG	K	22.22	0.12		CONDITIONALLY QUALIFIED		
OL 5520	PSG	K	37.92	0.21		CONDITIONALLY QUALIFIED		
OL 5524	PSG	K	39.96	0.07		CONDITIONALLY QUALIFIED		
OL 5539	PSG	K	38.88	0.30		CONDITIONALLY QUALIFIED		
OL 5542	PSG	K	34.88	0.35		CONDITIONALLY QUALIFIED		
OL 5559	PSG	K	27.21	0.18		CONDITIONALLY QUALIFIED		
OL 5562	PSG	K	30.22	0.07		CONDITIONALLY QUALIFIED		
OL 5579	PSG	K	28.91	0.16		CONDITIONALLY QUALIFIED		
OL 5582	PSG	K	28.27	0.16		CONDITIONALLY QUALIFIED		
OL 5592	PSG	K	24.65	0.38		CONDITIONALLY QUALIFIED		
OL 5593	PSG	K	30.28	0.14		CONDITIONALLY QUALIFIED		
OL 5595	PSG	K	32.54	0.42		CONDITIONALLY QUALIFIED		
OL 5596	PSG	K	31.41	0.50		CONDITIONALLY QUALIFIED		
OL 5597	PSG	K	24.25	0.20		CONDITIONALLY QUALIFIED		
OL 5598	PSG	K	29.35	0.12		CONDITIONALLY QUALIFIED		
OL 5599	PSG	K	38.01	0.39		CONDITIONALLY QUALIFIED		
OL 5600	PSG	K	42.02	0.05		CONDITIONALLY QUALIFIED		

END

**DATE
FILMED**

8 / 5 / 93