4th quarter
DE-AC22-90PC90156-05

1991

DOE/PC/90156--5

DE93 001720

**DEVELOPMENT AND TESTING OF A COMMERCIAL-SCALE
COAL-FIRED COMBUSTION SYSTEM - PHASE III**

**Quarterly Technical Progress Report No. 5
Report Period: October 1, 1991 to December 31, 1991**

By A.F. Litka and R.W. Breault

May 1992

Work Performed Under Contract No. DE-AC22-90PC90156

**Tecogen Inc.
45 First Avenue
P.O. Box 9046
Waltham, Massachusetts 02254-9046**

OST
JUL 24 1992

MASTER

MASTER *DM*

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

"This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof."

This report has been reproduced directly from the best available copy.

Available from the National Technical Information Service, U.S. Department of Commerce, Springfield, Virginia 22161.

Price: Printed Copy A02
Microfiche A01

**DEVELOPMENT AND TESTING OF A COMMERCIAL-SCALE
COAL-FIRED COMBUSTION SYSTEM - PHASE III**

**Quarterly Technical Progress Report No. 5
Report Period: October 1, 1991 to December 31, 1991**

**By
A.F. Litka and R.W. Breault**

May 1992

Work Performed Under Contract No. DE-AC22-90PC90156

**Prepared for
PETC Project Manager: Mr. Douglas Gyorke
Pittsburgh Energy Technology Center
U.S. Department of Energy
P.O. Box 10940
Pittsburgh, Pennsylvania 15236-0940**

**Prepared by
Tecogen Inc.
45 First Avenue
P.O. Box 9046
Waltham, Massachusetts 02254-9046**

TABLE OF CONTENTS

1. INTRODUCTION	1
2. PROJECT STATUS	6
2.1 SYSTEM INTEGRATION	6
2.2 SLURRY PRODUCTION	6
2.3 SYSTEM TESTS	6
2.3.1 Variable-Spray-Angle (VSA) Atomizer	6
2.3.2 Combustor Tests	15
2.3.3 Integrated System Tests	15
3. PLANNED ACTIVITIES	22
4. SUMMARY	23

LIST OF ILLUSTRATIONS

1.1	Process Flow Diagram	3
1.2	Work Breakdown Structure for Entire Project	5
2.1	Schematic of System Test Configuration	7
2.2	Plan and Elevation Views of Major System Components	8
2.3	Integrated Coal-Water Slurry Fired Space Heating System	9
2.4	Slurry Production Facility Flow Schematic	10
2.5	Particle Size Distribution – Kentucky Coal (300 lb/hr Coal Feed Rate)	11
2.6	Kentucky Hazard CWS Viscosity	14
2.7	Slurry Flow Rate – Test 12/3	16
2.8	Combustor Upper Chamber Gas Temperature – Test 12/3	17
2.9	Boiler Entrance Gas Temperature – Test 12/3	18
2.10	Boiler Exdt Gas Temperature – Test 12/3	19
2.11	Measured and Projected NO _x Performance	21

LIST OF TABLES

1.1	Performance Goals	2
2.1	Kentucky Hazard Prince Mine Coal Analysis	12
2.2	Typical Slurry Properties	13

1. INTRODUCTION

Coal is the most plentiful energy resource in the United States, and in 1987 it provided approximately one third of the quads of total energy consumed in the United States. Its use, however, has been largely restricted to utility power generation since World War II for environmental and economic reasons.

Within the commercial sector, oil and natural gas are the predominant fuels used to meet the space-heating needs of schools, office buildings, apartment complexes, and other similar structures. In general, these buildings require firing rates of 1 to 10 million Btu/hr. The objective of this program is to demonstrate the technical and economic viability of a coal-fired combustion system for this sector.

The development program includes all aspects of the process, from fuel selection and preparation to pollution control and waste disposal. In attempting to restore coal to small users such as residential and commercial space heating, it is important to recognize that fuel form is an important consideration because of its impact on handling and emissions. Ease of handling is an important criterion at the small sizes since complex equipment will add greatly to the overall system costs. Furthermore, manpower is not available to perform manual functions or keep complex equipment working. Emission levels, if not currently regulated, can be expected to be regulated at low levels in the future. The levels considered acceptable will be reduced over time, following the current environmental trends. Preparation and use of a coal-water slurry fuel can aid in meeting these criteria. Coal-water slurry use eliminates the need for dry pulverized coal with its attendant handling and dusting problems as well as its explosive potential. In addition, coal-water slurry is amenable to coal washing since coal cleaning technologies are generally water-based processes requiring fine grinding of the coal. For these reasons, the program objective will be met through the development of a coal-water slurry fired system.

Although the coal-water slurry fuel in commercial practice will be manufactured by coal companies or fuel suppliers at regional facilities and transported to the user much as is done today with oil, the program includes the construction of a slurry production facility. In this way, all aspects of the fuel's use - from coal selection to combustion properties - can be evaluated and an economic evaluation of the process can be carried out.

The commercial-scale coal-water slurry (CWS)-fired space heating system will be a scale-up of a CWS-fired residential warm-air heating system developed by Tecogen under contract to the Department of Energy, Pittsburgh Energy Technology Center. This system included a patented nonslagging combustor known as IRIS, for Inertial Reactor with Internal Separation. This combustion technology, which has demonstrated high combustion efficiency using CWS fuels at input rates of 100,000 Btu/hr, will be scaled to operate at 2 to 5 million Btu/hr. Along with the necessary fuel storage and delivery, heat recovery, and control equipment, the system will include pollution control devices to meet targeted values of NO_x , SO_2 , and particulate emissions. In general, the system will be designed to match the reliability, safety, turndown, and ignition performance of gas or oil-fired systems. Table 1.1 summarizes the performance goals of the system. Figure 1.1 is a process flow diagram for the system.

TABLE 1.1
PERFORMANCE GOALS

• Thermal Input	- 4 million Btu/hr
• Thermal Efficiency	- >80%
• Combustion Efficiency	- >99%
• Emissions	- 1.2 lb SO ₂ /MMBtu
0.3 lb NO _x /MMBtu
0.03 lb Part./MMBtu
• Turndown	- 3:1
• Ignition	- Fully automatic startup with system purge and Ignition verification
• Reliability/Safety	- Comparable to oil-fired commercial boilers
• Ash Removal	- Dust free and automatic or semi-automatic
• Routine Maintenance	- Less than one manhour per day and an additional two manhours per week
• Service Life	- >20 years

Figure 1.1 Process Flow Diagram

The successful development and future marketability of the heating system require a strong, dedicated team with expertise in a broad range of areas including coal-water slurry preparation, coal combustion, pollution control, component manufacture, and systems integration. Such a team has been assembled and includes the following organizations: Tecogen, Donlee Technologies, AMAX Coal, and Southern Illinois University.

Tecogen is the prime contractor and is responsible for overall program management, combustor development, and integration of the subsystem components and installation of the system at the field test site. AMAX has extensive experience in coal-water slurry preparation and serves as the principal coal supplier. Donlee Technologies is responsible for the boiler/heat exchanger design and manufacture. Donlee has over 70 years' experience in the commercial boiler business and is a potential commercializer of the technology. Southern Illinois University is the host for the field test portion of the program. The heating system will provide space heating at the SIU Coal Research Center.

The development program has been divided into 3 stages covering a time span of 39 months. During the first stage, which covers 14 months, the program will focus on component development. The second stage, which covers a 10-month period, will focus on proof-of-concept testing. The final stage covers a 15-month period and will focus on testing all the components as an integrated system in an actual installation. Figure 1.2 gives the work breakdown structure for the program.

This report documents the work carried out in the fifth quarter of the program. During this period, integration of the major system components was completed (Subtask 1.3 - System Integration), and preliminary system testing was initiated (Subtask 2.2 - System Tests). Construction of the slurry production facility was also completed, and slurry production was initiated using Kentucky Hazard Prince Mine coal.

Before this fifth quarter work, activities were focused on the design, construction, and assembly of the major system components. As part of the system design, component design testing of the combustor and slurry delivery system, including various atomizers, was conducted to verify combustor scale-up.

Figure 1.2 Work Breakdown Structure for Entire Project

2. PROJECT STATUS

During the fifth quarter of this program, system integration was completed and preliminary system tests were performed. These tests were aimed at providing a preliminary evaluation of component and system performance, identifying key operating variables and their ranges, and establishing appropriate operating conditions for future proof-of-concept testing.

2.1 SYSTEM INTEGRATION

Integration of the major system components was completed with the installation of interconnecting piping, auxiliary systems, and controls. For the component development system tests, the boiler was configured to vent to atmosphere with combustor cooling water temperature maintained by means of an air-cooled radiator. A schematic of the test setup is shown in Figure 2.1. Figure 2.2 shows the layout and relative sizes of the major system components, and Figure 2.3 is a photograph of the integrated system.

2.2 SLURRY PRODUCTION

Installation of the slurry preparation facility was completed and slurry production has been initiated. A schematic of the final slurry facility configuration is shown in Figure 2.4. Dry grinding is utilized, and the ground coal is separated from the conveying air stream by primary and secondary cyclones. Both cyclones are operated dry with the ground coal discharged into the mixing tank through rotary air locks. The bulk of the ground material (more than 99 percent) is collected in the first-stage cyclone. The conveying system is a closed-loop system with a system bleed that discharges through a fabric filter and water trap to control fugitive dust emissions. The system is operated in a batch mode with batches of approximately 175 gallons produced.

At a coal throughput of 300 lb/hr, pulverized coal with a mass mean diameter of 20 to 30 microns is obtained. A plot of a typical particle size distribution is given in Figure 2.5. Eastern Kentucky Hazard Prince Mine coal, a low-ash, low-sulfur coal, has thus far been utilized for the system tests. Proximate and ultimate analyses for this coal are given in Table 2.1.

Desired slurry properties have been attained at coal solids loading of approximately 60 percent with 1000-ppm dispersant and 700-ppm stabilizer added on a coal weight basis. The dispersant being used is a sulfonated naphthalene condensate, ammonium salt produced by Henkel Corporation, and the stabilizer is a xanthan gum produced by Pfizer Chemical. Table 2.2 lists the typical coal-water slurry properties. A plot of the slurry viscosity versus shear rate is given in Figure 2.6. The slurry is stored in 1000-gallon storage tanks equipped with propeller mixers.

2.3 SYSTEM TESTS

2.3.1 Variable-Spray-Angle (VSA) Atomizer

The variable-spray-angle (VSA) atomizer developed under this program and described in Quarterly Technical Progress Report No. 4 was used for combustor

TF90-592

Figure 2.1 Schematic of System Test Configuration

Figure 2.2 Plan and Elevation Views of Major System Components

TF92-592

Figure 2.3 Integrated Coal-Water Slurry Fired
Space Heating System

Figure 2.4 Slurry Production Facility Flow Schematic

TF94-592

Figure 2.5 Particle Size Distribution - Kentucky Coal
(300 lb/hr Coal Feed Rate)

TABLE 2.1
KENTUCKY HAZARD PRINCE MINE COAL ANALYSIS

Proximate Analysis			Ultimate Analysis		
	As Received	Dry Basis		As Received	Dry Basis
% Moisture	2.69	xxxxx	% Moisture	2.69	xxxxx
% Ash	3.62	3.72	% Carbon	78.91	81.09
% Volatile	35.93	36.92	% Hydrogen	5.25	5.39
% Fixed Carbon	<u>57.76</u>	<u>59.36</u>	% Nitrogen	1.63	1.67
	100.00	100.00	% Sulfur	0.74	0.76
Btu/lb	14144	14535	% Ash	3.62	3.72
% Sulfur	0.74	0.76	% Oxygen (diff.)	<u>7.16</u>	<u>7.37</u>
MAF Btu		15097		100.00	100.00
Alk. as Sodium Oxide	0.07	0.07			

TF102-592

TABLE 2.2
TYPICAL SLURRY PROPERTIES

Coal	Kentucky
Coal Loading	59%
Particle Size (mmd)	20 to 35 μm
Specific Gravity	1.14 to 1.16
A23 (dry mass coal)	10,000 ppm
Flocon	700 ppm
Viscosity	200 cP at 80 1/sec
Heating Value	8,500 Btu/lb

Figure 2.6 Kentucky Hazard CWS Viscosity

testing. Steady, reliable CWS combustion was achieved with plug-free operation and no detectable component wear. Slurry droplet size, although not quantified, appeared smaller than with the modified fuel oil nozzle tested previously, as evidenced by much smaller particles in the upper regions of the combustor. Varying the axial atomizing air allowed the slurry spray pattern to be changed sufficiently to direct the slurry to the desired regions of the combustor and thereby maintain gas temperatures in the upper section of the combustor even as primary air flow was increased at high thermal input. Fuel oil for system warm-up was introduced solely through the VSA atomizer, and sufficiently high upper chamber gas temperatures could be maintained. At full load the atomizer air to slurry ratio was 0.33 (weight basis).

2.3.2 Combustor Tests

A series of tests were conducted with the combustor/transition chamber operating independent of the boiler and baghouse by means of a water quench exhaust system to demonstrate reliable and steady operation of the unit prior to full system integration. Three slurries were utilized: a 67-percent loaded Upper Elkhorn parent coal slurry, a 52-percent loaded, oil agglomeration cleaned, Illinois No. 6 parent coal slurry, and a 59-percent loaded Kentucky Hazard No. 5 parent coal slurry. The Kentucky coal slurry was prepared in the slurry preparation facility described above. With all fuels, combustor operation was steady, and high upper chamber temperatures were at loads ranging from 1.5 to 4 MMBtu/hr. These short tests of one to three hours' duration established acceptable setpoints for key operating variables, provided further verification of correct combustor scale-up, and demonstrated that the combustion system could be operated safely in conjunction with the boiler and baghouse without damage to this equipment.

2.3.3 Integrated System Tests

Combustor testing was followed by several integrated system tests. In all tests, a 58-percent loaded Kentucky coal water slurry, produced by Tecogen, was utilized. Figures 2.7, 2.8, 2.9 and 2.10 show the slurry flow rate, the upper chamber temperature, the transition chamber gas temperature, and the boiler exhaust gas exit temperature for one of the tests. With a slurry heating value of 8,500 Btu/lb and a slurry input of 475 lb/hr, the thermal input for this test was the design input of 4 MMBtu/hr. This input level was maintained for over four hours.

As can be seen in Figure 2.10, a slight increase in boiler exit temperature was realized at the steady firing rate condition due to ash deposition. This increase in boiler exit temperature corresponds to a drop-off in system thermal efficiency of approximately 4 percentage points - from 84 percent to 80 percent. The material deposited on the heat transfer surfaces was very light and was easily removed by mechanical cleaning. To fully evaluate the impact of ash deposition on boiler performance, long-term testing will be required. Compressed-air soot-blowing will be evaluated as a means of controlling ash accumulation on the heat transfer surfaces.

All system components have operated reliably. Accumulation of char/ash in the upper section of the combustor has been problematic, however. The amount, location, and elapsed time before this material accumulation has affected

Figure 2.7 Slurry Flow Rate - Test 12/3

Figure 2.8 Combustor Upper Chamber Gas Temperature - Test 12/3

TF98-592

Figure 2.9 Boiler Entrance Gas Temperature - Test 12/3

TF99-592

Figure 2.10 Boiler Exit Gas Temperature - Test 12/3

combustor operation has varied substantially with thermal input, combustion air staging, atomizer spray angle, and atomization quality. Additional testing will be performed to further evaluate both the operating changes and the design changes that could eliminate the material accumulation.

NO_x emissions during initial system tests have averaged approximately 0.5 lb/MMBtu at design thermal input, which exceeds the program goal of 0.3 lb/MMBtu. The higher than anticipated NO_x levels are in large part a result of the reactor gas and wall temperatures, which were higher than those realized in the residential-scale unit. It is predicted that targeted NO_x levels can be reached by increasing combustion zone residence time and/or combustor heat extraction. Figure 2.11 compares the NO_x emission levels of the commercial-scale and residential-scale combustors.

Figure 2.11 Measured and Projected NO_x Performance

3. PLANNED ACTIVITIES

A series of tests will be conducted to evaluate the mechanisms for material accumulation in the combustor and boiler and to assess the efficacy of operating and/or design changes implemented to eliminate the build-up.

The key design and operating parameters to be evaluated to control material deposits in the combustor are:

- Combustor temperature
- Wall material
- Partition location and size
- Inlet air velocity and staging, and
- Atomizer spray angle.

For each of the changes made to the combustor geometry and corresponding operating conditions, combustion efficiency and NO_x production will be evaluated.

Boiler fouling and the requirements for boiler tube ash removal will also be evaluated. Since changes in combustor operation, especially as related to fly ash particle size and quantity, will directly affect boiler fouling characteristics, boiler ash deposition will be investigated further. In particular, the ability to clean the boiler tubes with compressed-air soot-blowing will be evaluated.

4. SUMMARY

During the fifth quarter of the program, major system component integration was completed and preliminary system tests were conducted. The integrated system operated reliably and either met or can be expected to meet system design goals with minor modifications or improvements. In particular, ash accumulation in the combustor and boiler has limited system performance and must be eliminated or controlled in subsequent testing.

The variable-spray-angle atomizer was tested and proved quite successful in providing a fine slurry droplet size at reasonable atomizing air consumption with plug-free operation. The atomizer's ability to provide "on-line" adjustment of the spray angle was demonstrated and has proven to be a valuable operating parameter.

The installation of the slurry preparation facility was completed, and slurry production was initiated. Slurry made from Kentucky Hazard Prince Mine coal has been produced and meets design requirements for loading, viscosity, and stability.

Additional tests will be conducted to evaluate component and system performance. Key design and operating parameters will be evaluated to control material deposits in the combustor.

DATE
FILMED
12/28/92