2/

WSRC-OS-93-009

RECEIVED

JUN 25 1993

OSTI

**ATTACHMENT 3 RLCA CALCULATION NO. P191-1/3 REVIEW
OF 105K REACTOR TANK EXPANSION RING (U)**

by

Westinghouse Savannah River Company
Savannah River Site
Aiken, South Carolina 29808

Robert L. Cloud Associates, Inc.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report was prepared in connection with work done under Contract No. DE-AC09-89SR18035 with the U.S. Department of Energy. By acceptance of this report, the publisher and/or recipient acknowledges the U.S. Government's right to retain a nonexclusive, royalty-free license in and to any copyright covering this report, along with the right to reproduce and to authorize others to reproduce all or part of the copyrighted report.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED *EB*

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 52, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

[REDACTED]

Attachment 3

RLCA Calculation No. P191-1/3
Review of 105K Reactor Tank Expansion Ring
Revision 0

DOES NOT CONTAIN
UNCLASSIFIED CONTROLLED
NUCLEAR INFORMATION

Reviewing *Carl W. Whist*
Official: *mgr. Safety Policy*
Date: *9/87/91*

[REDACTED]

Robert L. Cloud and Associates, Inc.

RLCA

FINAL
ENGINEERING DOCUMENTATION PACKAGE

PROJECT NUMBER:

P191-1

RECORD NUMBER:

P191-1/3

DESCRIPTION:

REVIEW OF 105 K REACTOR TANK EXPANSION RING

KEYWORDS: REACTOR TANK, EXPANSION RING

COMPUTER PROGRAMS USED, IF ANY:

NONE

REV. NUMBER	CHANGES (INCLUDE REVISION LOG IF NECESSARY)	TOTAL PAGES	ORIGINATING ENGINEER	DATE	CHECKER & DATE	TECH. REVIEW & DATE	PROJ. MGR. & DATE
△ 0	ORIGINAL ISSUE	23	H. Loey	2/29/90	<i>P. Smith</i> 3/7/90	<i>P. Smith</i> 3-16-90	<i>J. Hand</i> 4/3/90
△							
△							
△							
△							

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Leey DATE 1/4/90
CHKD. BY [Signature] DATE 3/5/90

SANANNAN RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 1 OF 23
PROJ. NO. P191-1

TABLE OF CONTENTS

	<u>Page No.</u>
1.0 Introduction	2
2.0 Methodology	3
3.0 Analysis	5
4.0 Results Evaluation	18
5.0 Conclusions	21
6.0 References	22

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Wiley DATE 1/3/90
CHKD. BY RE DATE 3/7/90

SAVANNAH RIVER SITE
CALC. No. P191-1/3

PAGE NO. 2 OF 23
PROJ. NO. P191-1

1.0 INTRODUCTION

This analysis package reviews the adequacy of the expansion plate ring for the reactor tank. This review utilizes the results of an existing stress analysis and incorporates the results of a RLCA seismic analysis of the reactor tank shell.

The existing analysis (Ref. 1, by Quadrex) was performed using displacements for the L-Reactor tank. The seismic differential displacement calculated by RLCA (Reference 2) was compared to the the Reference 1 input value to evaluate the adequacy of the K-Reactor expansion ring. The Reference 2 analysis used more recent seismic inputs to calculate differential displacement.

The updated seismic expansion ring stresses will be evaluated relative to the combined stresses (which include other loads, i.e., thermal, pressure, etc.) reported in the Ref. 1 analysis. This calculation package reviews only the changes due to updated seismic inputs only.

In addition, this review employs ASME Section III (Ref. 9), whereas the Reference 1 calculation applies criteria from ASME Section VIII.

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Wey DATE 1/3/90
CHKD. BY P/O DATE 3/2/90

SAVANNAH RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 3 OF 23
PROJ. NO. P191-1

2.0 METHODOLOGY

The Reference 1 analysis includes the effects of horizontal seismic differential displacement (between top and bottom of the ring), an approximate vertical seismic displacement, gas and hydrostatic pressure, and thermal expansion. Maximum and minimum principal stresses as well as maximum shear stress results were summarized for each load case.

For this review, the seismically induced stresses in the Reference 1 analysis were evaluated relative to the seismic displacements calculated in RLCA calculation package RLCA P191-1/11 (Reference 2).

The combined stresses reported in Reference 1 were then reviewed, considering the contribution from the updated seismic stresses and the revised criteria associated with a 'Faulted Condition' evaluation.

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Wray DATE 1/30/90
CHKD. BY BJS DATE 3/17/90

SAVANNAH RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 4 OF 23
PROJ. NO. P191-1

The following assumptions were made for this analysis:

1. It is assumed that there is no practical way to determine the current as-built condition. For this reason and for the purposes of this confirmatory calculation, the analysis is based on the as-designed condition.
2. Following from the above assumption, it is assumed that the expansion ring is essentially stress free as installed and not affected by factors other than those considered in this analysis and the Quodrex (Ref. 1) analysis.
- * 3. Support displacements, as assumed for this analysis, were based on currently available information. This analysis should be reviewed and updated following completion of the evaluations for the reactor tank supports.

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Wey DATE 1/30/90
CHKD. BY BFB DATE 3/2/90

SAVANNAH RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 5 OF 23
PROJ. NO. P191-1

3.0 ANALYSIS AND COMPARISON

Tank Shell Inertial Horizontal Displacement

Extract displacement from top of tank shell at the expansion joint as represented by Node 11 in the IMAGES model in RLCR Calculation P191-1/11 (Ref. 2 Appendix A - Output).

$\delta = 3.556 \times 10^{-3}$ in. orthogonal x and z horiz. directions

$$SRSS = [(2)(3.556 \times 10^{-3})^2]^{1/2} = \underline{\underline{0.0050 \text{ in}}}$$

The Ref. 2 analysis conservatively uses enveloped seismic inputs for Elevations -20 ft and 0.0 ft.

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Wee DATE 2/25/90
CHKD. BY RS DATE 3/7/90

SAVANNAH RIVER SITE
Calc No. P191-1/3

PAGE NO. 6 OF 23
PROJ. NO. P191-1

Building Horizontal Differential Movements

Calculate applicable building inter-story horizontal displacements based on Reference 3, URS/JAB 6193.06, at the tank location. Apply first mode frequency and mode shape for determining maximum deflection.

Building Fundamental Frequencies (Ref. 3, Table 2)

N-S: 6.93 Hz = 43.54 rad/sec
E-W: 9.53 Hz = 59.88 rad/sec

Building Floor Spectra ZPA's (Ref. 3, R.G. 1.60 Spectra)

	JAB Table No.	Elev. (ft.)	ZPA (g)	ZPA (m/s ²) (x)
N-S:	C1	-20.0	0.2355	91.00
	C2	0.0	0.2457	94.94
E-W:	C13	-20.0	0.2391	92.39
	C14	0.0	0.2514	97.14

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Lee DATE 2/20/90
CHKD. BY AB DATE 3/5/90

SAVANNAH RIVER SITE
Calc. No. P191-1/3

PAGE NO. 7 OF 22
PROJ. NO. P191-1

Determine displacements based on $| \ddot{x} | = \omega^2 x$,
and relative displacements based on
 $| \Delta x | = | x_{0.0} | - | x_{-20} |$ since applying the
building fundamental frequency implies
first mode deflection shape.

$$N-S: \quad x_{-20} = \frac{91.00}{(43.54)^2} = 0.0480 \text{ in}$$

$$- \left[x_{0.0} = \frac{94.94}{(43.54)^2} = 0.0501 \text{ in} \right]$$

$$| \Delta x_{N-S} | = \underline{\underline{0.0021 \text{ in}}}$$

$$E-W: \quad x_{-20} = \frac{92.39}{(59.88)^2} = 0.0258 \text{ in}$$

$$- \left[x_{0.0} = \frac{97.14}{(59.88)^2} = 0.0271 \text{ in} \right]$$

$$| \Delta x_{E-W} | = \underline{\underline{0.0013 \text{ in}}}$$

Calculate the resultant deflection for the circular
geometry ring (conservatively assumes maximum
displacement in the two analysis directions
occurs simultaneously).

$$SRSS \text{ Disp} = \left[(0.0021)^2 + (0.0013)^2 \right]^{1/2} = \underline{\underline{0.0025 \text{ in}}}$$

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Loey DATE 2/26/90
CHKD. BY AB DATE 3/7/90

SAVANNAH RIVER SITE
CALC. No. P191-1/3

PAGE NO. 8 OF 23
PROJ. NO. P191-1

Tank Support Gap Movement

Due to the configuration of the upper and lower reactor tank supports, the potential for relative lateral motion due to the support gaps must be considered. The following drawings document the support gap conditions (Ref. 8)

Lower Support: W133481, Rev. 0

Upper Support: W133631, Rev. 2

From the Reference 7 RLCA Calculation Package, the maximum plausible movement of the reactor tank base relative to the building reference point was determined to be 0.0100 in.

Supports are assumed centered in the gaps since the keys are fitted with the proper clearances after the bottom tubesheet and bearing ring are installed (with expansion ring in essentially free state).

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Wey DATE 2/26/90
 CHKD. BY [Signature] DATE 3/1/90

SAVANNAH RIVER SITE
 Calc. No. P191-1/3

PAGE NO. 9 OF 23
 PROJ. NO. P191-1

Of the twelve support locations in the upper support, three of the supports are installed with 0.008 in. clearances through use of fitted keys to provide lateral mechanical restraint. These three keyed supports are 120° apart.

Determine possible deflection for two support orientations relative to the direction of motion:

Deflection for this orientation = 0.0092 in.

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Lee DATE 2/29/90
CHKD. BY JB DATE 3/7/90

SAVANNAH RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 10 OF 23
PROJ. NO. P191-1

For motion in the following direction:

Maximum Upper Support Deflection = 0.016 in.

Total Relative Deflection for Lower and Upper Support:

$$\begin{aligned} \text{Disp} &= 0.0100 + 0.0160 \text{ in} \\ &= \underline{0.0260 \text{ in.}} \end{aligned}$$

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Lee DATE 2/26/90
CHKD. BY AB DATE 3/2/90

SAVANNAH RIVER SITE
CALC. No. P191-1/3

PAGE NO. 11 OF 23
PROJ. NO. P191-1

Total Possible Horizontal Relative Displacement

$$\begin{aligned}\text{Disp.} &= \text{Tank Inertia} + \text{Building Interstar-1 SAM} + \text{Supp. Gaps} \\ &= 0.0050 + 0.0025 + 0.0260 \\ &= \underline{0.0335 \text{ in}}\end{aligned}$$

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Loey DATE 1/19/90
 CHKD. BY AB DATE 3/7/90

SAVANNAH RIVER SITE
 CALC No. P191-1/3

PAGE NO. 12 OF 23
 PROJ. NO. P191-1

Vertical Displacement

The vertical relative displacement applied by Quodrex, $(2/3)(\text{horiz. disp.}) = 0.0154 \text{ in}$ (Ref. 1, pp. 3-3, 4) is judged to be overly conservative.

The $2/3$ factor is normally applied to calculate vertical response from floor response spectra.

The Quodrex horizontal displacement was obtained from the lumped mass building and tank model. Applying the horizontal displacement to derive the vertical displacement is conservative but not necessarily meaningful.

Per Reference 4 Tables 4-1 and 4-3 (pp. 4-3, 4-6) the building vertical frequency (17.9 Hz) is greater than three times the lowest horizontal fundamental frequency (5.49 Hz). It is unlikely that the stiffer vertical direction would have such a large vertical relative displacement between -20 ft and 0.0 ft.

$$\begin{aligned}\ddot{x} &= \omega^2 x = [(17.9)(2\pi)]^2 (0.0154) \\ &= 194.8 \text{ in/s}^2 \Rightarrow 0.50 g \\ &\text{(not reasonable for vertical since horiz. EPA} \approx 0.25g\text{)}\end{aligned}$$

The tank itself will have negligible vertical inertial displacement.

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Wee DATE 2/25/90
CHKD. BY MB DATE 2/21/90

SAVANNAH RIVER SITE
CALC. No. P191-1/3

PAGE NO. 13 OF 23
PROJ. NO. P191-1

Determine the relative building inter-story displacement as follows: Calculate relative vertical acceleration based on $2/3$ of the horizontal acceleration. Use the Reference 4 vertical building frequency since Reference 3 does not include a vertical model or analysis. Assume the Ref. 4 vertical frequency is correct ($17.9 \text{ Hz} = 112.5 \text{ rad/s}$).

Using the maximum $\Delta \ddot{x}$, 4.75 m/s^2 (E-W)

$$\begin{aligned} \text{Relative } \Delta y_{20\%} &= \frac{\left(\frac{2}{3}\right)(4.75 \text{ m/s}^2)}{(112.5 \text{ rad/s})^2} \\ &= \underline{0.00025 \text{ m}} \end{aligned}$$

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. L. Loney DATE 1/3/90
CHKD. BY RLC DATE 3/7/90

SAVANNAH RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 14 OF 23
PROJ. NO. P191-1

Seismic Stress Comparison

From Reference 1, Pg. 3-7, Table 3-1, the maximum seismically induced stresses are:

<u>Quadrex</u>	<u>Displacement (in)</u>	<u>(ksi)</u>		
		<u>σ_1</u>	<u>σ_2</u>	<u>τ_{max}</u>
Horiz. Seismic	0.0231	12.05	-13.57	11.98
Vertical Seismic	0.0154	1.59	-1.55	0.59

Based on the calculated displacements, scale the stresses above:

<u>Updated Values</u>	<u>Displacement (in)</u>	<u>(ksi)</u>		
		<u>σ_1</u>	<u>σ_2</u>	<u>τ_{max}</u>
Horiz. Seismic	0.0335	17.48	(-)19.68	17.37
Vertical Seismic	0.00025	0.03 ~0	(-)0.03 ~0	~0

Based on the revised stress results tabulated above, the total expansion ring seismic stresses are not significantly changed when the revised horiz. and vertical seismic displacements are considered. Ref. 1 shows seismic stresses as the dominant stress (Table 3-1), hence

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Wey DATE 1/30/90
CHKD. BY MB DATE 3/7/90

SAVANNAH RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 15 OF 23
PROJ. NO. P191-1

the combined Code stresses as tabulated in
Ref. 1 Table 4-1 will be reduced.

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Lee DATE 2/25/90
CHKD. BY WJS DATE 3/7/90

SAVANNAH RIVER SITE
CALC. No. P191-1/3

PAGE NO. 16 OF 23
PROJ. NO. P191-1

Allowable Stresses

The Reference 4 analysis employed ASME Section VIII criteria to establish allowable stress. Stress intensities were calculated as:

$$\text{Ref. 4: } P_m \leq k S_m = 24.0 \text{ ksi}$$

$$P_L \text{ or } P_L + P_B \leq 1.5 k S_m = 36 \text{ ksi}$$

$$P_L + P_B + Q \leq 3 S_m = 60 \text{ ksi}$$

(using $k = 1.2$)

However, for the evaluation being performed here, the applicable criteria has been defined as the ASME Code, Section III, 1974 Edition, with W74 Addenda (Reference 9). In addition, for the seismic evaluation, defined as the Faulted Condition, go to the Winter 1976 Addenda also. The W76 Addenda defines $k = 2.0$ for the Faulted condition.

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Lee DATE 2/25/90
CHKD. BY AS DATE 3/7/90

SAVANNAH RIVER SITE
CALC. No. P191-1/3

PAGE NO. 17 OF 23
PROJ. NO. P191-1

For a Section III Faulted Condition evaluation (per Winter 76 Addenda) Secondary stresses need be evaluated only for Level A and B Limits (NC-3217.1)

Thus, the resulting design criteria per NC-3217 are (using $K=2.0$ per Table NC-3217-1 for the Faulted Condition) as follows. Use $S_m = 20.0$ ksi, as per Reference 9, for 304 Stainless Steel.

$$P_m \leq K S_m = (2.0)(20.0) = 40.0 \text{ ksi}$$

$$P_L \leq 1.5 K S_m = (1.5)(2.0)(20.0) = 60.0 \text{ ksi}$$

$$(P_m \text{ or } P_L) + P_b \leq 1.5 K S_m = 60.0 \text{ ksi}$$

ROBERT L. CLOUD & ASSOCIATES, INC.

BY A. Hays DATE 2/27/90
CHKD. BY RFJ DATE 3/1/90

SAVANNAH RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 18 OF 23
PROJ. NO. P191-1

4.0 RESULTS EVALUATION

Stress results from the Quadrex Reference 1 analysis were tabulated for each load case and for combined stress intensities. The stress summary tables from the Quadrex analysis have been reproduced on the next page.

As discussed previously in this package, this review is performed for the Section III Faulted Design Condition. Hence, the allowable stresses and required load combinations required for this review will vary from those applied in the Quadrex analysis. Namely, thermal loading (secondary stresses) will not be considered for the Faulted evaluation, and the allowable stress intensity for P_L and $(P_m \text{ or } P_L) + P_B$ is increased to 60.0 ksi.

Based on the above considerations alone, the margins for the Faulted Condition are increased beyond those calculated in

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Loe DATE 2/27/90
CHKD. BY [Signature] DATE 3/1/90

SAVANNAH RIVER SITE
CALC. No. P191-1/3

PAGE NO. 19 OF 23
PROJ. NO. P191-1

Tables from Reference 1

Table 3-1
Maximum Stresses Due To Individual Load Case

Load Case Description	Maximum Principal Stress (ksi)	Minimum Principal Stress (ksi)	Maximum Shear Stress (ksi)
Horizontal Seismic	12.05	-13.57	11.98
Vertical Seismic	1.59	- 1.55	0.59
Gas Pressure (5.0 psi)	5.01	- 5.03	2.93
Thermal	1.26	- 1.30	0.51

TABLE 4-1

Maximum Stress Intensity Summary For
105-L Expansion Plate Ring

Stress (1) Category	Computed Value (ksi)	Allowable Value (ksi)
P_L	24.06	36.0
$P_L + P_b$	25.01	36.0
$P_L + P_b + Q$	25.22	60.0

ROBERT L. CLOUD & ASSOCIATES, INC.

BY H. Wey DATE 2/27/80
CHKD. BY AB DATE 3/5/80

SAVANNAH RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 20 OF 23
PROJ. NO. P191-1

Reference 1 for their identified criteria.

The change in the seismic differential deflections appear to have relatively insignificant impact on the stress intensity results. It is recognized that the exact methodology for combining element/nodal component stresses in Reference 1 have not been described in detail. Hence, based on the maximum stress results in Table 3-1 of Reference 1, it is not possible to determine an exact revised stress intensity result using the updated maximum seismic stresses.

However, it is observed that the reduction in vertical seismic stress partially offsets the increase in horizontal seismic stress (which considers support gaps). The net increase in seismic stress does not represent a significant change in the combined stresses. This trend, combined with the different Faulted allowables and load combination, lead to the conclusion that the expansion ring stresses will meet allowable criteria.

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Loey DATE 11/30/90
CHKD. BY AD DATE 3/7/96

SAVANNAH RIVER SITE
CALC. NO. P191-1/3

PAGE NO. 21 OF 23
PROJ. NO. P191-1

5.0 CONCLUSIONS

Seismic stresses calculated in an existing Quadrex analysis for the expansion ring have been reviewed to account for current (updated) seismic movements. The magnitudes of the seismic stresses were reviewed relative to the combined stress results calculated in the existing analysis.

The review showed that the revised seismic stresses are comparable to those in the existing calculation. In addition, use of a Faulted Condition evaluation approach leads to the conclusion that safety margins previously reported by Quadrex actually increase. Thus, the expansion ring will still meet Code requirements based on the case examined.

This analysis should be reviewed when support displacements are finalized in the reactor tank support evaluations.

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Loey DATE 1/3/90
CHKD. BY BTS DATE 3/1/90

SAVANNAH RIVER SITE
Calc. No. P191-1/3

PAGE NO. 22 OF 23
PROJ. NO. P191-1

S.O REFERENCES

1. Quadrex Report QUAD-1-89-007, Seismic Analysis and Evaluation of Expansion Plate Ring for 10S-L, K, and P Reactor Tanks, Rev. 0, 5/25/89, as contained in SEWS # K-PWS-0-03.
2. RLCA Calculation Package P191-1/11 Rev. 1.
3. URS/JAB 6193.06, Floor Acceleration Response Spectra For Updated DBE And Reg. Guide 1.60 Seismic Input: Building 10SK, Savannah River Plant, URS/J. A. Blume, Rev. 0, January 1989.
4. DPST-86-256, 3/10/86, including Quadrex Report QUAD-1-85-016, Seismic Analysis of 'L' Area Buildings At The Savannah River Plant Site, Rev. 0, 11/22/85, Volume 1.
5. Drawings: W133628, Rev. 10, Main Tank Shell & Bearing Ring
W133388, Rev. 27, Tank Btm Tube Sheet

ROBERT L. CLOUD ASSOCIATES, INC.

BY H. Coey DATE 11/30/90
CHKD. BY B/C DATE 3/17/95

SAVANNAH RIVER SITE
CALC. No. P191-1/3

PAGE NO. 23 OF 23
PROJ. NO. P191-1

6. Marks' Standard Handbook for Mechanical Engineers, Baumeister, et. al., McGraw-Hill, 8th Edition, 1978.
7. RLCA Calculation Package RLCA P191-1/7, Rev. 0.
8. Drawings: W133481, Rev. 0, Main Tank Btm Bearing Plates
W133583, Rev. 52, Main Tank Support
W133584, Rev. 41, Main Tank Support
W133631, Rev. 2, Main Tank Top Bearing Ring...
W134405, Rev. 14, Main Tank Casing
W134406, Rev. 3, Main Tank Casing
9. ASME Boiler and Pressure Vessel Code, Section III, 1974 Edition, with Winter 1974 and Winter 1976 Addenda as applicable.

END

DATE
FILMED
9 / 7 / 193