1 of 1

POE/CE/15510--T8

TECHNICAL REPORT OILWELL POWER CONTROLLER (OPC UNIT)

General Equipment Information

Double M Electric, Inc. in Watford City, ND is finalizing the testing of its OPC Prototype Unit. This device can be used as a rod pump controller and it can also monitor, record and store power usage, temperature and pressure data. The unit also has the capability to measure the rod string weight, therefore it can be used as a dynamometer. Work is in progress to send the data recorded by the OPC Unit via radio signal and telephone lines to the office. Preliminary test results appear to be very promising.

Implementation of The OPC Prototype Unit Tests

A total of 10 OPC Units were assembled and installed on oilwells pumped with rod pumps in the Central and Western United States. Data from these wells was analyzed and forwarded to the participating oil companies.

General Statement of the Cost Savings

The cost savings realized by each OPC Unit in the test varied considerably. When the OPC Unit was used to improve the downhole pump efficiency, the cost savings were higher. Cost savings due to preventing downhole problems will also be realized by slowing pumping units down, but the length of the test time was not long enough to calculate an exact dollar amount.

The following pages list the actual costs that were reduced by using data obtained with several of the OPC Units.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MASTER

CASE NO. 1 Blue Buttes Madison Unit K206
Texaco, Inc. Watford City, North Dakota

Prior to Installation of OPC Unit

Pumping Unit on 24 Hour Continuous Run Time Cycle.
Pumping Unit Speed was 10 SPM.
Sucker Rod Pump Efficiency was 22%.

Results After OPC Installation

Pumping Unit Speed Decreased to 6.6 SPM.
45% Decrease in Demand KW from 18 KW to 10 KW.
45% Decrease in KWH Usage.
Sucker Rod Pump Efficiency is 34%.
Production Remained at 25 BOPD.
Power Cost Lowered \$460/Month.
Payout of \$3000 OPC Equipment Cost Occurred in 6.5 Months.

USE OF DEMAND KW TO DETERMINE MAXIMUM PUMPING UNIT RUN TIME

Prior to slowing the pumping unit down, it was put on a pumping time clock schedule of 14 Hours On and 10 Hours Off. Example A is a plot of Demand KW recorded by the OPC Unit. It shows that the well was pumped dry in an average of 10 Hours at 10.2 SPM.

USE OF DEMAND KW TO DETERMINE PROPER PUMPING SPEED

Example B is a plot of the Demand KW when the pumping unit was on a 24 Hour Continuous Run Rime Cycle at a speed of 10.2 SPM. The plot shows that the well was being pumped dry; there was not enough pressure head on the sucker rod pump for it to operate properly.

When demand is down to 15 KW, the rod pump is doing less work because it is not pumping any fluid. The pump is empty because it pumped out fluid faster than the reservoir fed fluid into the pump. When power is at a maximum in the cycle, the pump is pumping fluid because it has enough pressure head on it for it to work properly.

As a result of pumping the well dry, the rods are slammed together violently and they part, as indicated by the plot in Example B. The plot shows the pumping unit impact switch has shut the motor off. When the oil company personnel turn the pumping unit back on, the OPC unit indicates there is a downhole failure. The motor is using less energy because the pumping unit is lifting less weight, i.e. no fluid and less rod weight.

Example C shows the result of slowing the pumping unit down. The demand dropped 45% from 18 to 10 KW. This eliminated the pump-off situation and leveled the power usage.

DEMAND POWER AND RUN TIME DATA

CASE NO. 1
EXAMPLE A

TEXACO INC
BBMU K206

USE OF DEMAND KW TO DETERMINE MAX. PUMP RUN TIME

IN THIS SITUATION THE OILWELL WAS ORIGINALLY ON A 24HR. CONT. RUN CYCLE. THE PUMP EFF. WAS DETERMINED TO BE VERY LOW SO THE WELL WAS PUT ON A 14HR. CONTINUOUS RUN, 10HR. OFF. THIS HELPED TO DECIDE THE MAX PUMP TIME AS THE WELL SHOWS SIGNS OF PUMP OFF IN LESS THAN 10 HRS.

CASE NO. 2
EXAMPLE A

PRESIDIO OIL COMPANY
STATE 34-16

IN THIS CASE THE OILWELL WAS ORIGINALLY ON A TIME CYCLE OF 12 HOURS TOTAL. UPON INSTALLATION OF THE OPC UNIT THE KW DATA WAS GATHERED ON A 11HR. CONT. ON & 13HR. OFF CYCLE. THE INITIAL PERCENTAGE TIME WAS THEN SET INTO THE OPC TIME CONTROL. THE WELL IS PRESENTLY ON A 13MIN.ON-26MIN OFF TIME CYCLE. (DOWN 35%)

DEMAND KW AND PUMP OFF INDICATION THE IMPORTANCE OF PROPER PUMPING SPEED

TEXACO INC. BBMU K206

AMPLE A
SE NO. 1

EXAMPLE A SHOWS HOURLY DEMAND KW ON A OILWELL THAT IS INDICATING A SEVERE PUMP OFF. THE HOURLY KW SHOULD BE FAIRLY STEADY.

AS A RESULT OF THE IMPROPER PUMPING THE RODS PARTED. UPON RESTART THE OPC THEN INDICATED A UNDERLOAD FOR PUMP FAILURE TO THE PERSONNEL.

TEXACO INC. BBMU K206

AMPLE B
SE NO. 1

AFTER REVIEW OF GRAPH (B) DATA THE PUMPING UNIT SPEED WAS SLOWED SIGNIFICANTLY. THIS HAS ELIMINATED THE PUMP OFF SITUATION. NOTE THE 45% DECREASE IN ELECTRICAL KW. THE OIL PRODUCTION REMAINED THE SAME AS AT PRIOR SPEED.

CASE NO. 2 State 34-16
 Presidio Exploration Inc. Plaza, North Dakota

Prior to Installation of OPC Unit

Pumping Unit Time Cycle: 12 Hours On and 12 Hours Off.

Results After OPC Installation

Pumping Unit Time Cycle: 13 Minutes On and 26 Minutes Off.
20% Decrease in Demand KW from 18 KW to 11 KW.
35% Decrease in KWH Usage.
Power Cost Lowered \$90/Month.
Payout of \$3000 OPC Equipment Cost Occurred in 33 Months.

USE OF DEMAND KW TO DETERMINE MAXIMUM PUMPING UNIT RUN TIME

The OPC Unit was used to determine the percentage of On Time required by the pumping unit to pump the well dry. The plot of Demand KW in Example A shows that the well was pumped dry in 5 hours and required a pump schedule where the pumping unit was on approximately 33% of the time. The final pump schedule is 13 Minutes On and 26 Minutes Off.

DYNAMOMETER DATA

The OPC unit can also be used in conjunction with a load cell to record rod weight data just as a dynamometer does. The dynamometer is a device used by the petroleum industry to diagnosis downhole equipment problems on rod pumped wells. In Examples A and B the OPC unit records the weight that a load cell measures at the top of the rod string. On the pumping unit downstroke the weight of the rods is recorded. The combined weight of the rods and produced fluid are recorded on the upstroke.

Examples B and C are two dynamometer cards from the well in Case #2. They show how fluid weight can effect the weight of the rods recorded by the OPC Unit. Example B was taken at the beginning of the on time cycle and Example C was taken when the well was being pumped dry just prior to the off cycle. In Example C no fluid is being pumped by the downhole pump. The weight of the fluid which was picked up by the rods and pump at the beginning of the downstroke is constant and it is not changing because gas is being compressed in the pump.

It is interesting to note that there is a slight increase in pumping unit speed recorded by the OPC Unit in Example C. This is because the pumping unit is doing less work as a result of pumping less fluid, thus it can operate faster.

Rod weight data recorded by the OPC Unit can be downloaded into any software used for dynamometer analysis to calculate pump intake pressure and to calculate a downhole pump dynamometer card.

DYNAMOMETER DATA

CASE NO.2 EXAMPLE B

PRESIDIO EXPLORATION

STATE 34-16

DATE: 5/25/93
TIME*: 1:10PM.
RUN CYCLE: 13on-26off
UNIT SPEED: 8.16spm

***ONE MINUTE AFTER
START OF ON CYCLE**

PRESIDIO OIL

STATE 34-16

DATE: 5/25/93
TIME*: 1:21PM.
RUN CYCLE: 13on-26off
UNIT SPEED: 8.23spm*

***ONE MINUTE PRIOR
TO THE OFF CYCLE**

THE ABOVE (2) SURFACE DYNAMOMETER CARDS SHOW THE EFFECT OF THE ROD WEIGHT FROM PUMPING FLUID IN THE TOP CARD TO A PUMP OFF SITUATION IN THE BOTTOM CARD. THE BOTTOM CARD SHOWS THE COMPRESSION ON THE DOWNSTROKE. NOTE THE SLIGHT INCREASE IN UNIT SPEED (spm).

CASE NO. 3 Otto Boss A-1
Texaco Inc. Watford City, North Dakota

Prior To Installation of OPC Unit

Pumping Unit on 24 Hour Continuous Run Time Cycle.

Results After OPC Installation

OPC Unit used for Demand Load Control by Power Company Via
Radio Signal.

Pumping Unit Time Cycle: 22 Minutes On and 6 Minutes Off.

50% Decrease in Demand Charge Because of Load Control.

25% Decrease in KWH Usage from 17500 KWH/month to 13133.

Power Cost Lowered \$160/Month.

Payout of \$3000 OPC Equipment Cost Occurred in 19 Months.

Case No. 4 Hartsoch 3-13
 Armstrong Operating Dickinson, North Dakota

Prior to Installation of OPC Unit

Pumping Unit on 24 Hour Continuous Run Time Cycle.
Sucker Rod Pump Efficiency 17%.
Pumping Unit Speed 7.7 SPM.

Results After OPC Installation

Pumping Unit Speed 6 SPM.
Sucker Rod Pump Efficiency 23%.
21% Decrease in Demand from 12 KW to 9.5 KW.
21% Decrease in Power Usage.
Power Cost Lowered \$400/Month.
Payout of \$3000 OPC Equipment Cost Occurred in 13 Months.

Work is still in progress to slow pumping unit down and
optimize pumping schedule.

CASE NO. 5 Hamre 14-1
Amax Oil and Gas, Inc. Williston, North Dakota

Prior to Installation of OPC Unit

Pumping Unit on 24 Hour Continuous Run Time Cycle.
Pumping Unit Speed was 8.5 SPM.
Sucker Rod Pump Efficiency was 56%.

Results After OPC Installation

Pumping Unit Speed Decreased to 7.3 SPM.
17.5% Decrease in Demand from 20 KW to 16.5 KW.
17.5% Decrease in Power KWH Usage.
Sucker Rod Pump Efficiency is 64.5%.
Production Remained at 30 BOPD.
Power Cost Lowered \$180/Month
Payout of \$3000 OPC Equipment Cost Occurred in 16.7 Months.

USE OF DEMAND KW TO TROUBLESHOOT DOWNHOLE PROBLEMS

Example A is a plot of the Demand KW as recorded by the OPC Unit on the Hamre 14-1. When a hole in the tubing occurred, the demand power reading dropped dramatically and the OPC Unit showed an Underload Condition.

CASE NO. 6 H. D. Landy 1-30
Flying J Oil Inc. Vernal, Utah

Prior to Installation of OPC Unit

Hot oil treatments for paraffin removal were done on a scheduled basis.

Results After OPC Installation

Hot oil treatments were done when Demand KW (as recorded by OPC Unit) showed that they were required.

USE OF DEMAND POWER TO DETERMINE SCHEDULING OF HOT OIL TREATMENTS

Example A shows the effect of paraffin build-up on the Demand KW as recorded by the OPC Unit. As paraffin coats the rods and inside of the tubing, friction pressure increases for two reasons. As paraffin coats the rods, it drags on the tubing while the coating on the inside of the tubing creates a smaller flow path for the produced fluid. Both of these cause the pumping unit motor to work harder and raise the Demand Power from 24 KW to 29 KW.

After hot oil is pumped into the casing to melt paraffin, the Demand returns to 23 KW but it gradually increases again.

CASE NO. 7 Otto Boss 18
 Texaco, Inc. Watford City, North Dakota

Prior to Installation of OPC Unit

Hot Oil and Dispersant Chemical Treatments for paraffin removal were done on a scheduled basis.

Results After OPC Installation

Work is in progress to Optimize Treating Schedule and do Hot Oil and Dispersant Chemical Treatments when Demand KW (as recorded by OPC Unit) show that they are required.

USE OF DEMAND KW TO SCHEDULE PARAFFIN DISPERSANT TREATMENTS

Example A shows how pumping a paraffin dispersant into the wellbore effects the Demand Power of the pumping unit. As the chemical is produced with the oil, it disperses the paraffin in the produced fluids and prevents it from coating the rods and tubing. When all of the chemical is produced from the wellbore, the paraffin starts coating the equipment and the Demand Power increases.

Work is also in progress to slow down the pumping unit to improve the efficiency of the downhole pump. Current pump efficiency is 49% at a production of 146 BOPD and 44 BWPD.

PARAFFIN TREATMENT DATA

CASE NO. 6 EXAMPLE A

FLYING J OIL INC
H.D. LANDY 1-30

FLYING J OIL INC
H.D. LANDY 1-30

EXAMPLE NO. 1

THIS GRAPH SHOWS THE EFFECT OF THE HOT OIL TREATMENT FOR REMOVAL OF PARAFFIN WAX ON THE AMOUNT OF DEMAND KW USED BY THE ELECTRIC DRIVER MOTOR. THE DEMAND NUMBERS ARE A 24 HR AVERAGE. NOTE THE GRADUAL INCREASE IN DRAG ON MOTOR OVER A MONTH PERIOD AND THEN THE RESULT AFTER TREATMENT. THE COST OF THE TREATMENT IS OFFSET BY THE ENERGY SAVINGS. THIS TYPE OF TREATMENT LESSENS THE CHANCE OF ROD FAILURE AND ALSO USUALLY HELPS OIL PRODUCTION.

CASE NO. 7
EXAMPLE A

TEXACO, INC
OTTO BOSS 18

EXAMPLE NO. 2

THIS GRAPH SHOWS THE EFFECT OF WEEKLY CHEMICAL BATCH TREATMENTS ON THE USAGE OF ENERGY. THE CHEMICAL WORKS WHILE IT IS PRESENT IN THE WELL

REAL TIME DATA STORAGE

EGGT

Page No. 6

04-26-1992

* * DPL RUNNING HISTORY * *

Date	Time	UL	OL	Steno	Fluid Temp	Press	APPS	HLPR	HLTIME	OPWR	RTIME
02792	1815	40	30	65	63	20	235	0	0	6.55	623.1
02792	1915	40	30	64	64	22	249	0	0	6.558	623.6
02792	2015	40	30	63	61	24	243	0	0	6.556	624.1
02792	2205	40	30	61	52	21	251	0	0	6.781	625.1
02792	2305	40	30	49	55	22	303	0	0	6.807	626.6
02892	5	40	30	47	52	21	271	0	0	6.696	626.2
02892	105	40	30	46	53	26	279	0	0	6.849	626.7
02892	205	40	30	46	50	20	259	0	0	6.627	627.1
02892	305	40	30	46	46	22	230	0	0	6.848	627.6
02892	405	40	30	43	43	21	303	0	0	6.723	628.1
02892	505	40	30	41	59	26	303	0	0	6.83	628.6
02892	605	40	30	40	44	21	293	0	0	6.66	629.1
02892	705	40	30	40	41	20	238	0	0	6.87	629.6
02892	805	40	30	40	46	21	230	0	0	6.7	630.2
02892	905	40	30	42	46	20	233	0	0	6.834	630.7
02892	1005	40	30	46	57	20	262	0	0	6.929	631.1
02892	1105	40	30	53	64	20	233	0	0	6.85	631.6
02892	1205	40	30	53	70	19	306	0	0	6.661	632.1
02892	1305	40	30	59	72	21	263	0	0	6.702	632.6
02892	1405	40	30	63	73	21	302	0	0	6.617	633.1
02892	1505	40	30	64	75	20	290	0	0	6.659	633.6
02892	1605	40	30	65	74	20	269	0	0	6.468	634.2
02892	1705	40	30	65	70	20	266	0	0	6.579	634.7
02892	1805	40	30	64	69	19	296	0	0	6.511	635.1
02892	1905	40	30	63	62	22	248	0	0	6.616	635.6
02892	2005	40	30	59	60	20	257	0	0	6.564	636.1
02892	2105	40	30	55	55	21	300	0	0	6.593	636.6
02892	2205	40	30	50	56	23	270	0	0	6.647	637.1
02892	2305	40	30	48	49	21	307	0	0	6.571	637.6
02892	5	40	30	46	53	21	238	0	0	6.565	638.2
02892	105	40	30	45	47	19	303	0	0	6.562	638.7
02892	205	40	30	40	55	22	298	0	0	6.764	639.1
02892	305	40	30	33	42	19	289	0	0	6.702	639.6
02892	405	40	30	37	52	20	286	0	0	6.764	640.1
02892	505	40	30	37	55	21	306	0	0	6.694	640.6
02892	605	40	30	33	54	23	264	0	0	6.817	641.1
02892	705	40	30	38	39	21	262	0	0	6.636	641.6
02892	805	40	30	38	59	27	288	0	0	6.815	642.2
02892	905	40	30	42	45	19	306	0	0	6.723	642.7
02892	1005	40	30	50	60	26	302	0	0	6.765	643.1
02892	1105	40	30	51	53	19	241	0	0	6.706	643.6
02892	1205	40	30	54	53	22	272	0	0	6.731	644.1
02892	1305	40	30	53	61	21	301	0	0	6.675	644.6
02892	1405	40	30	63	63	22	247	0	0	6.67	645.1
02892	1505	40	30	64	64	21	295	0	0	6.521	645.6
02892	1605	40	30	67	65	21	291	0	0	6.75	646.2
02892	1705	40	30	61	60	20	287	0	0	6.496	646.7
02892	1805	40	30	62	62	20	237	0	0	6.655	647.1
02892	1905	40	30	59	53	20	306	0	0	6.472	647.6
02892	2005	40	30	56	60	24	265	0	0	6.609	648.1
02892	2105	40	30	50	50	20	233	0	0	6.411	648.6

UL = Underload % (KW)
OL = Overload % (KW)
Steno = Site Temperature (°F)

SHOWN ABOVE IS A SAMPLE PRINTOUT OF REAL TIME DATA AVAILIABLE FROM THE OPC UNIT. THE OPC WILL STORE HOURLY TIME, DATE, REAL TIME, OVERLOAD & UNDERLOAD PERCENTAGE SETTINGS, SITE TEMPERATURE, FLUID TEMPERATURE, FLUID PRESSURE, CASING OR AIR PRESSURE, OVERLOAD OR UNDERLOAD FAULT TIME OF OCCURRANCE, DEMAND KW, AND ACTUAL UNIT RUN TIME.

THE OPC IS CAPABLE OF UP TO 60 DAYS STORAGE AND CAN BE DOWN-LOADED VIA ANY IBM COMPATIBLE LAPTOP COMPUTER. THE DATA CAN THEN BE PRINTED, VIEWED, OR GRAPHED BY VARIOUS PROGRAMS AVAILIABLE.

CONCLUSION

The OPC Unit can be used on sucker rod pumping units to:

1. Determine if a well is being pumped dry.
2. Determine the proper pumping speed.
3. Trouble shoot down-hole mechanical and productivity problems.
4. Optimize the timing of hot oil and chemical treatments for paraffin removal.
5. Control Demand Load by the utility companies.
6. Work in conjunction with a load cell to record rod weight data used in dynamometer analysis.

**DATE
FILMED**

10/04/93

END