PRESSURIZED FLUIDIZED-BED HYDRORETORTING OF EASTERN OIL SHALES

Progress Report for the Period September-November 1991

By
F. S. Lau
M. C. Mensinger
M. J. Roberts
D. M. Rue

December 1991

Work Performed Under Contract No.: DE-AC21-87MC11089

For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
Morgantown, West Virginia 26505

By
Institute of Gas Technology
Chicago, Illinois 60616

APPROVED FOR RELEASE OR
PUBLICATION - O.R. PATENT GROUP
BY *Den* DATE *7/28/92*

**TECHNICAL INFORMATION CENTER
OFFICE OF SCIENTIFIC AND TECHNICAL INFORMATION
UNITED STATES DEPARTMENT OF ENERGY**

MASTER

ok
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Printed in the United States of America

Available from

**National Technical Information Service
U.S. Department of Commerce
5285 Port Royal Road
Springfield, VA 22161**

NTIS price codes

Printed copy: A03

Microfiche copy: A01

PRESSURIZED FLUIDIZED-BED HYDRORETORTING OF EASTERN OIL SHALES

Progress Report for the Period September-November 1991

By
F. S. Lau
M. C. Mensinger
M. J. Roberts
D. M. Rue

December 1991

Work Performed Under Contract No.: DE-AC21-87MC11089

For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26505

By
Institute of Gas Technology
IIT Center, 3424 S. State Street
Chicago, Illinois 60616

EXECUTIVE SUMMARY

This report presents the work performed during the program quarter from September 1 through November 30, 1991, under U.S. Department of Energy (DOE) Contract No. DE-AC21-87MC11089 for the project "Pressurized Fluidized-Bed Hydroretorting (PFH) of Eastern Oil Shales." The Institute of Gas Technology (IGT) is the prime contractor for the overall program extension to expand the PFH data base to beneficiated shales. Four universities are working with IGT as subcontractors; their responsibilities and achievements in the program are discussed below in the appropriate tasks.

Some of the tasks in the original program were not continued in the current program extension. The task achievements discussed below represent the active tasks of the program.

In Subtask 3.7 (Innovative Reactor Concept Testing), IGT completed the construction of the cracking-combustion unit. Shakedown tests in this laboratory-scale batch unit will be initiated next quarter.

In Subtask 3.8 (Niche Market Studies), all of the equipment necessary for characterizing asphalts produced from PFH processing of beneficiated shale have been ordered and received. IGT will begin the asphalt screening tests next quarter.

The University of Alabama Mineral Resources Institute (MRI) is responsible for the work being conducted in Task 4 (Beneficiation Research).

In Subtask 4.1.4 (Grinding-Flotation Circuit Design), MRI continued work on determining methods for reducing stirred ball mill grinding costs. As part of this effort, MRI ground several hundred kilograms of Alabama shale to -100, -200, and -460 mesh for the tests. Also, hydrocycloning tests were conducted on these samples of shale. The results of these tests showed that, for several feed solids concentrations, the d_{50} of the cyclone overflow product can be in the 11 to 12 μm range, thus reducing the quantity of material reporting as stirred ball mill feedstock. However, the cyclone underflow products would require thickening to yield stirred ball mill feedstock in the 45 to 50 percent solids range required.

In Subtask 4.4 (Integrated Grinding and Flotation), the University of Kentucky Center for Applied Energy Research (UK-CAER) conducted column flotation tests in the 5.1-cm (2-inch) diameter 6.1-m high (20-ft) Ken-Flote column. Among the operating conditions tested were the froth height, slurry feed rate, wash water addition rate, and refloating the rougher concentrate. Fuel oil and pine oil were also tested to determine their effect on organic carbon recovery. In the rougher stage, the recovery of carbon was 54.7 percent with a concentrate grade of 47.8 percent carbon. Cleaner flotation of this product yielded 54.8 percent carbon recovery with a concentrate grade of 56.8 percent carbon. The overall recovery for this two-stage process was 30.0 percent with a final grade of 56.8 percent carbon. These results show that a cleaner flotation can increase the carbon content of the final product, however, the overall recovery was poor. This test was conducted using the static sparger for fine bubble generation with a concentration of 1 kg of pine oil

per metric ton of shale. To improve the overall recovery it would be necessary to significantly increase the recovery in the rougher flotation stage.

In Subtask 4.5. (Evaluation of Different Grinding Media), MRI conducted stirred ball mill tests with the Molinex Option with sand, and the John Option with sand and steel media. Both types of media were 1.1 mm in diameter. The results show that for ultra-fine grinding to a d_{90} of 6 μm or less, sand media requires less energy than steel media. For a smaller size reduction ratio, in which the product d_{90} is between 6 and 9 μm , steel media requires less energy.

In Subtask 4.6.1. (Oil Agglomeration and Pelletizing), MRI conducted shale agglomeration tests with different chemicals, such as n-pentane. The results show that agglomerate formation has not yet been achieved.

In Subtask 4.6.2 (Bioflocculation of Kerogen), the University of Nevada, Reno (UN) conducted tests to determine the effects of pH and microorganism concentration on flocculation. The flocculation and settling rate of kerogen increases with the addition of Mycobacterium phlei. At a pH of 4.6, no significant difference in the settling rate was observed after 5 minutes with and without organisms. However, for settling times of less than 5 minutes, bacterial addition has a positive effect on initial flocculation and settling.

In Task 5 (Operation of PFH on Beneficiated Shale), IGT completed equipment modifications to the bench-scale fluidized-bed unit. These improvements include the addition of new feed and residue screw controllers and counters, modification of the residue screw flights, and modification of the environmental sampling train to ensure that only Teflon[®]-coated surfaces come in contact with the acid and base scrubs. Bench-scale tests with beneficiated shale will begin next quarter.

In Subtask 6.2.2 (Wastewater Treatability), Tennessee Technological University (TTU) continued acclimating microorganisms to 4-methyl pyridine. Biological treatability studies continued with phenol and methyl ethyl ketone (MEK). In batch treatability studies with phenol, biological stabilization of phenol began within 10 hours and was completed for reactors containing as much as 450 mg/L within 58 hours. In the batch treatability studies with MEK, biodegradation began within the first 4 hours of the experiment and was completed for reactors containing as much as 250 mg/L within about 32 hours.

In Subtask 6.4.3. (Plant Energy Optimization), TTU focused on the detailed exergy analysis of the PFH plant and initiated the thermoeconomic evaluation. A preliminary analysis of the PFH plant design showed an overall exergetic efficiency of 84.9 percent for the total plant. TTU also initiated development of the computer software, the cost balances, and the equations required to complete the thermoeconomic evaluation.

In Task 7 (Sample Procurement, Preparation, and Characterization), MRI collected about 9 tons of shale from a site in Alabama for use by the program participants. This bulk sample was shipped to Michigan Technological University and beneficiated in MTU continuous equipment. Portions of the beneficiated shale have been shipped to IGT, UK-CAER, and MRI.

In Task 8 (Project Management and Reporting), IGT personnel visited the campuses of TTU, UK-CAER, and MRI during the quarter. IGT continued to monitor the progress and activities of the subcontractors working in the program via telephone and written reports. Also, several papers were presented by IGT personnel at the 1991 Eastern Oil Shale Symposium (held November 12-14 in Lexington, Kentucky) on various project-related topics. Papers were also presented by MRI, TTU, and UN on project activities.

TABLE OF CONTENTS

	<u>Page</u>
INTRODUCTION	1
ACHIEVEMENTS	2
Task 3. Testing of Process Improvement Concepts	2
Task 4. Beneficiation Research	4
Task 5. Operation of PFH on Beneficiated Shale	25
Task 6. Environmental Data and Mitigation Analyses	25
Task 7. Sample Procurement, Preparation, and Characterization	37
Task 8. Project Management and Reporting	43
FUTURE PLANS	43
ACKNOWLEDGMENTS	43
Appendix A. Results of the Preliminary Exergetic Evaluation of the PFH Process Plant by Tennessee Technological University	A-1
Table A-1. Thermodynamic Properties of Streams in the PFH Plant	A-3
Table A-2. Heat Loss, Power Supplied, Exergy Destruction Flow Rate, Exergy Destruction Ratio, Exergy Destruction to Shale Exergy Ratio, and Exergetic Efficiency for Plant Components	A-11
Table A-3. Steam Generation/Consumption: (positive values mean steam generation, negative values mean steam consumption)	A-13
Appendix B. Development of Thermoeconomic Factors for the PFH Plant by Tennessee Technological University	B-1

LIST OF FIGURES

<u>Figure No.</u>		<u>Page</u>
4-1	Effect of Cyclone Pressure and Feed Size at High Feed Solids (27 to 31 Percent)	6
4-2	Effect of Cyclone Pressure and Feed Size at Medium Feed Solids (12.5 to 15 Percent)	8
4-3	Effect of Cyclone Pressure and Feed Size at Low Feed Solids (4.8 to 6.8 Percent)	8
4-4	Continuous Grinding and Sizing Circuit	11
4-5	Effect of Media Type on the Shape of Particle Size Distribution at Similar Product Median Size	15
4-6	Effect of Mill Type on the Shape of Particle Size Distribution at Similar Product Median Size	16
4-7	Effect of Media Type on the Shape of Particle Size Size Distribution at Similar Median Product Size	17
4-8	Alternative Oil Agglomeration and Pelletizing Schemes	18
4-9	Settling Characteristics of Beneficiated Alabama Shale (1.0 wt % solids, pH 7.3, <u>M. phlei</u> = 70 ppm)	20
4-10	Settling Characteristics of Beneficiated Alabama Shale (1.0 wt % solids, pH 4.6, <u>M. phlei</u> = 70 ppm)	21
4-11	Settling Characteristics of Beneficiated Alabama Shale (1.0 wt % solids, pH 9.4 <u>M. phlei</u> = 70 ppm)	22
4-12	Effect of pH on Settling Characteristics of Beneficiated Alabama Shale (10 min settling time, <u>M. phlei</u> = 70 ppm, 1.0 wt % solids)	23
4-13	Scanning Electron Micrograph of Kerogen With <u>Mycobacterium phlei</u>	24
4-14	Effect of pH on Settling Characteristics of Freshly Prepared Beneficiated Alabama Shale (5 min settling time, <u>M. phlei</u> = 100 ppm, 0.5 wt % solids)	26
6-1	COD and Phenol vs. Time For Phenol Batch Experiment 6 (The Initial Phenol Concentrations were 50, 100, and 250 mg/L)	29

LIST OF FIGURES (continued)

<u>Figure No.</u>		<u>Page</u>
6-2	COD and Phenol vs. Time For Phenol Batch Experiment 6 (The Initial Phenol Concentration was 100 mg/L)	30
6-3	COD and Phenol vs. Time for Phenol Batch Experiment 6 (The Initial Phenol Concentration was 250 mg/L)	31
6-4	COD and Phenol vs. Time For Phenol Batch Experiment 6 (The Initial Phenol Concentration was 450 mg/L)	32
6-5	MEK vs. Time For MEK Batch Experiment 1 (The Initial MEK Concentrations were 50, 100, and 250 mg/L)	33
6-6	Flow Diagram of the PFH Plant	35
6-7	Flow Diagram of the Hydrogen Plant	36
7-1	Carbon:Density:Oil, MTU Column Cell vs. MRI Mechanical Cell Data	40
7-2	Flowsheet for Continuous Processing of Alabama Oil Shale at MTU	41

LIST OF TABLES

<u>Table No.</u>		<u>Page</u>
4-1	Size Consist of Coarse-Grinding Circuit Discharges (Stirred Ball Mill Feed)	6
4-2	Cycloning -100 Mesh Alabama Shale and Recleaning the Cyclone Underflow Product	9
4-3	Effect of Cyclone Feed Solids at 20 psig	9
4-4	Effect of Cyclone Feed Pressure at 6.1% Feed Solids	9
4-5	Prediction of Grinding Energy Required Based on Modified Charles Relationships for Various Media Combinations With Alabama Shale Rougher Concentrate	13
4-6	Product d_{50} Values for Mill-Media System	14
6-1	Comparison of Phenol Batch Experiments 2 Through 6	28
7-1	Analyses of Alabama Oil Shale Head Samples	38
7-2	Comparison of Flotation Results on MTU Sample Ground to 3 Different Size Consists	38
7-3	Summary of MTU Flotation Results Based on Density Analyses of Samples	42
7-4	Average Material Balances for the MTU Packed Column Cell and the Deister Column Cell	42
7-5	Analysis of Head Sample of Total Concentrate Produced at MTU	42

INTRODUCTION

The Devonian oil shales of the Eastern United States are a significant domestic energy resource. The overall objective of the multi-year program, initiated in October 1987 by the U. S. Department of Energy (Contract No. DE-AC21-87MC11089), is to perform the research necessary to develop the pressurized fluidized-bed hydroretorting (PFH) process for producing oil from Eastern oil shales. The program also incorporates research on technologies in areas such as raw shale preparation, beneficiation, product separation, and waste disposal that have the potential of improving the economics and/or environmental acceptability of recovering oil from oil shales using the PFH process. The program is divided into the following active* tasks:

- Task 3. Testing of Process Improvement Concepts
- Task 4. Beneficiation Research
- Task 5. Operation of PFH on Beneficiated Shale
- Task 6. Environmental Data and Mitigation Analyses
- Task 7. Sample Procurement, Preparation, and Characterization
- Task 8. Project Management and Reporting.

In order to accomplish all the program objectives, the Institute of Gas Technology (IGT), the prime contractor, is working with four other institutions; the University of Alabama/Mineral Resources Institute (MRI), University of Kentucky Center for Applied Energy Research (UK-CAER) the University of Nevada (UN), and Tennessee Technological University (TTU).

This report presents the work performed during the program quarter from September 1 through November 30, 1991.

* Some of the tasks in the original program were not continued in the current program extension. The task achievements discussed below represent the active tasks of the program.

ACHIEVEMENTS

Task 3. Testing of Process Improvement Concepts

The objective of this task is to obtain data on novel process concepts that have the potential for improving the overall economics of PFH processing with Eastern oil shales. This task is divided into three subtasks corresponding to the concepts being tested: 3.6. Combustion of Hydroretorted Beneficiated Shales, 3.7. Innovative Reactor Concept Testing, and 3.8. Niche Market Studies.

Subtask 3.6. Combustion of Hydroretorted Beneficiated Shales

The overall objective of this subtask is to evaluate the combustion of hydroretorted shale for energy recovery prior to disposal. This subtask is comprised of two subtasks: 3.6.1. Combustion Characterization and 3.6.2. Combustion Tests.

Subtask 3.6.1. Combustion Characterization

The objective of this subtask is to determine the combustion characteristics of hydroretorted beneficiated shale.

Discussion

The combustion characteristics of hydroretorted shale will be determined in a series of thermogravimetric tests in an existing high-pressure thermobalance unit. The unit senses and records the instantaneous weight of a sample undergoing reaction at temperatures and pressures up to 982°C and 7.0 MPa (1800°F and 1000 psig).

Thermobalance tests are planned to be conducted as well as determinations of calorific value and elemental composition of the feed and residue samples. The shale will be heated at a low rate to permit determination of the temperature at which combustion is initiated. The effect of pressure on shale combustion characteristics will also be determined.

This task was not active during the quarter. Tests will be initiated next quarter.

Subtask 3.6.2. Fluidized-Bed Combustion Tests

The objective of this subtask is to demonstrate the combustion of hydroretorted beneficiated shale in a fluidized-bed reactor. Laboratory-scale tests will be conducted at various temperatures, pressures, and shale residence times to evaluate combustion characteristics, attrition, and reactivity. Emissions from the tests will be monitored for environmental purposes as well as for performing overall and elemental material balances.

Discussion

Laboratory-scale fluidized-bed combustion tests will be conducted in an existing 5.1-cm (2-inch) diameter fluidized-bed reactor. Tests will be performed using hydrotreated beneficiated shale generated in Subtask 5.2. The tests will be conducted at pressures of 0.1 and 1.48 MPa (15 and 215 psia) and combustion temperatures and shale residence times based on the results of Subtask 3.6.1.

This task was not active during the quarter. Tests will be initiated next quarter.

Subtask 3.7. Innovative Reactor Concept Testing

The objective of this subtask is to demonstrate the technical feasibility of generating hydrogen by cracking the by-product hydrocarbon gases on spent shale and combusting the carbon produced by the cracking reactions. Work is divided into two subtasks: 3.7.1. Cracking Tests and 3.7.2. Cracking-Combustion Tests. A laboratory-scale reactor will be designed and built for the tests to be conducted in this subtask.

Subtask 3.7.1. Cracking Tests

The objective of this subtask is to demonstrate the generation of hydrogen by cracking by-product hydrocarbon gases.

Discussion

During the quarter, IGT completed construction of the cracking-combustion unit. The reactor is 35.6 mm (1.4 inch) in internal diameter (ID) by 61 cm (24 inch) long and is capable of operating up to 1204°C and 7.0 MPa (2200°F and 1000 psig). Ancillary equipment includes pressure and temperature controllers and indicators, gas feed and sampling systems, and a data logging recorder. All system components, except the reactor, are constructed from 316 stainless steel. The reactor is constructed from 309 stainless steel, which has better high-temperature properties.

The panel board was constructed and the process instrumentation was mounted. The instrumentation, tubing, electrical supply, and wiring were installed. Electrical connections needed for the furnace, furnace controllers, and relays were made. The tubing and wiring connections, thermocouple placement, furnace and reactor installation, instrument calibration, and pressure testing were completed. Shakedown testing of the unit will begin next quarter.

Subtask 3.7.2. Cracking-Combustion Tests

The objective of this subtask is to demonstrate the combustion of carbon produced by the cracking of hydrocarbon gases.

Discussion

The same test unit constructed for the cracking tests in Subtask 3.7.1 will be used for the cracking-combustion tests. In the tests planned for this subtask, carbon will be deposited on hydroretorted beneficiated shale at conditions determined in Subtask 3.7.1. A combustion cycle will then be performed on each sample to determine the conditions for removing the deposited carbon by combustion. One of the tests will consist of multiple cracking-combustion cycles and will be conducted to determine the effects of recycling on the shale and its reactivity.

No cracking-combustion tests were performed this quarter. These tests will be conducted after completion of the cracking tests in Subtask 3.7.1.

Subtask 3.8. Niche Market Studies

The objective of this subtask is to determine the potential for producing hydroretorted shale oil co-products, such as asphalt additives. Tests will be performed to characterize hydroretorted shale oil asphalts and pavements containing these asphalts.

Discussion

Niche market studies will focus on the production and characterization of asphalt additives produced by the PFH processing of beneficiated Eastern oil shale. A series of screening tests will be conducted in an existing batch PFH unit to find the hydroretorting conditions for producing the highest yield of asphalt additive. An asphaltic fraction to be used as an additive will be separated from the product oil generated in Subtask 5.2. This asphalt additive and briquette samples containing this asphalt, will be characterized by standard methods including viscosity, penetration, ductility, thin-film oven testing, and water susceptibility. The characteristics of the asphalt with the shale oil additive will be compared with the properties of a typical petroleum asphalt.

During the quarter all of the equipment, including viscometer and high-temperature bath, laboratory oven, and penetrometer were received. The base plates for the water susceptibility tests were prepared. The bulk sample of pelletized, beneficiated shale was delivered to IGT and a representative sample was collected for use in the asphalt screening tests.

Asphalt screening tests will begin next quarter.

Task 4. Beneficiation Research

The objective of this task is to test several novel and advanced grinding and beneficiation concepts, which have shown promising results with coal, for processing Eastern shales. This task is divided into four subtasks: 4.1. Grinding Studies (Subtask 4.1.4. Grinding Circuit Design), 4.4. Integrated Grinding and Flotation, 4.5. Evaluation of Different Grinding Media, and 4.6. Evaluation of Concentrate Preparation Techniques (Subtasks 4.6.1. Oil Agglomeration and Pelletizing and 4.6.2. Bioflocculation of Kerogen).

Discussion

The overall responsibility for this task is assumed by the Mineral Resources Institute (MRI) of the University of Alabama. One of the subtasks (4.4) is being conducted by the University of Kentucky Center for Applied Energy Research (UK-CAER), as a subcontractor to MRI. Subtask (4.6.2) is being conducted by the University of Nevada, Reno (UN), also as a subcontractor to MRI. The achievements made during the quarter are described below.

Subtask 4.1. Grinding Studies

Subtask 4.1.4. Grinding-Flotation Circuit Design

During the quarter, MRI continued work on determining methods for reducing stirred ball mill grinding costs. Because of the high capital and operating costs of stirred ball milling, the focus of this work was on removing material already ground to flotation size from the feedstock to minimize the quantity of material that must be ball milled. MRI assumed that a coarse grinding circuit would produce stirred ball mill feedstock in the size ranges of either -100, -200, or -460 mesh and prepared quantities of these feed consists for testing.

To obtain these feedstocks, MRI ground several hundred pounds of Alabama shale to -100 mesh in a continuous 0.9 x 1.37 m (3 x 1.5 ft) ball mill at 50 weight percent solids. Hydrocycloning tests were then conducted on the -100 mesh sample using a 5.1-cm (2-inch) cyclone. When these tests were completed, the separated samples were combined and reconstituted, and then wet screened to -200 mesh to separate that fraction for the stirred ball mill feed. After hydrocyclone tests were completed on the -200 mesh feedstock, the separated samples were again combined and reconstituted, and then wet screened to -460 mesh to represent a finely ground stirred ball mill feedstock. The particle size distributions of these feedstocks are shown in Table 4-1.

Table 4-1 shows that a coarse-grinding circuit producing a -200 mesh discharge, rather than a -100 mesh discharge, would require about 20 percent additional primary grinding capacity. Similarly, a coarse grinding circuit with a -460 mesh discharge would require about 38 percent additional primary grinding capacity compared to that with a -100 mesh discharge. MRI will determine the additional capital and operating costs required to produce a coarse grinding circuit discharge of -200 and -460 mesh for comparison with those required to produce a -100-mesh discharge. MRI will also determine the effect of reducing the top size of the feed on the operating costs of stirred ball milling.

Hydrocyclone Tests. MRI conducted hydrocyclone tests on each of the three coarse grinding circuit discharges mentioned above (Table 4-1) to reduce the quantity of shale reporting as stirred ball mill feed. In each case, the d_{50} of the cyclone overflow and the quantity of the cyclone overflow were determined to evaluate the effect of cyclone feed solids and cyclone feed pressure. It is desirable to remove the maximum amount of flotation-size material in the hydrocyclone overflow product, while producing a cyclone underflow pro-

duct sufficiently high in solids (45 to 55 percent) to go directly to stirred ball milling without subsequent thickening. Figure 4-1 shows the results of

Table 4-1. SIZE CONSIST OF COARSE-GRINDING CIRCUIT DISCHARGES (Stirred Ball Mill Feed)

Feed Size, mesh	Weight	Size Distribution			Size	
		+24	-24+12	-12	d ₉₀	d ₅₀
		wt %			μm	
-100	100.0	41.9	19.5	38.3	56.0	25.1
-200	80.0	33.0	22.3	44.1	46.3	8.7
-460	62.3	18.7	27.1	53.6	33.8	10.8

Figure 4-1. EFFECT OF CYCLONE PRESSURE AND FEED SIZE AT HIGH FEED SOLIDS (27 to 31 Percent)

hydrocycloning tests with the three feedstocks at high solids (27 to 31 percent) which, in all cases, gave cyclone underflows in the range desired for stirred ball mill feedstock; however, none of the conditions investigated gave cyclone overflows in the d_{90} range required for flotation feed; i.e., 10 micrometers (μm). The lowest d_{90} obtained in these high solids cyclone feed studies was 14.6 μm at a weight recovery of 18 percent.

Other hydrocyclone tests conducted on the three feedstocks at feed solids concentrations in the ranges of 12 to 15 and 5 to 7 percent yielded the results shown in Figures 4-2 and 4-3. The results show that the d_{90} of the cyclone overflow product can be in the 11 to 12 μm range, thus reducing the quantity of material reporting as stirred ball mill feedstock. However, the cyclone underflow products produced in the lower cyclone feed solids ranges would require thickening to yield stirred ball mill feedstock in the 45 to 50 percent solids range required. The data indicate that as feed size decreases, weight recovery of the cyclone overflow increases at a constant d_{90} .

Hydrocyclone studies were conducted to determine if re-treating a primary cyclone underflow product one or two additional times would significantly increase the recovery of flotation-sized material. The results (Table 4-2) show that the hydrocyclone is relatively inefficient in recovering the -12 μm fraction of the cyclone feed. Re-treatment of the cyclone underflow two times yielded a 52 percent recovery of the -12 μm fraction in the cyclone feed at a d_{90} of 14.5 μm .

MRI also conducted hydrocyclone tests on a sample of low-grade flotation concentrate (22.2% carbon and 9.6% sulfur with a d_{90} of 27 μm) in a 5.1-cm cyclone to determine if there was a significant difference in the cyclone overflow and underflow products. The cyclone feed pressure was held constant at 239 kPa (20 psig) and the feed solids were varied from 25 to 5.8 percent solids. The results (Table 4-3) show that the solids content of the cyclone feed had only a small effect on the carbon grade in the cyclone overflow product; however, there was a reduction in the sulfur content of cyclone overflow product.

Since the presence of sulfur increases hydrogen consumption in the PFH process, additional hydrocyclone studies were made of this low-grade concentrate to determine the effect of increased cyclone feed pressure on the sulfur content of the cyclone overflow product. In these studies, a Dorr-Oliver cluster cyclone, containing four 10-mm cyclones, was used to obtain pressures as high as 584 kPa (70 psig). The solids content of the cyclone feed was held constant at 6.1 percent. The results of these tests (Tables 4-3 and 4-4) indicate that low weight recoveries and only small increases in carbon content can be expected when cycloning a low-grade concentrate. The results also indicate the potential for reducing pyritic sulfur in higher grades of concentrate by cycloning.

Grinding Circuit Tests. MRI established a continuous grinding and sizing circuit to produce sufficient material for future grinding and column cell flotation studies. The circuit (Figure 4-4) was initially operated at a shale feed rate of 0.9 kg per hour (2 lb/h) at 50 percent solids. After circuit shakedown, the plant operated about one hour before electrical problems

Figure 4-2. EFFECT OF CYCLONE PRESSURE AND FEED SIZE AT MEDIUM FEED SOLIDS (12.5 to 15 Percent)

Figure 4-3. EFFECT OF CYCLONE PRESSURE AND FEED SIZE AT LOW FEED SOLIDS (4.8 to 6.8 Percent)

Table 4-2. CYCLONING -100 MESH ALABAMA SHALE AND
RECLEANING THE CYCLONE UNDERFLOW PRODUCT

Product	Pass	Pressure psig	Feed Solids	Weight	Size Fraction			Distribution			Size	
					+24	-24+12	-12	+24	-24+12	-12	d ₉₀	d ₅₀
					wt %						μm	
Cyclone Overflow	1	20	13.7	13.2	0.4	10.9	88.0	Tr*	7.4	30.4	13.0	4.7
	2	30	10.0	7.2	2.0	13.8	84.3	0.3	5.1	16.1	14.9	5.1
	3	30	10.0	<u>3.1</u>	4.8	19.9	74.6	<u>0.4</u>	<u>3.2</u>	<u>6.1</u>	19.8	6.8
Overflow	1-3	--	--	23.6	1.5	13.0	85.1	0.8	15.7	52.6	14.5	5.1
Underflow	3	30	--	<u>76.4</u>	53.7	21.5	23.7	<u>99.2</u>	<u>84.3</u>	<u>47.4</u>	94.3	22.2
Feed (-100 mesh)				100.0	41.4	19.5	38.2	100.0	100.0	100.0	75.5	18.2

* Trace.

Table 4-3. EFFECT OF CYCLONE FEED SOLIDS AT 20 psig

Feed Solids, wt %	Cyclone Overflow Recovery, wt %	Sample Analysis, wt %		Fraction of Element in Overflow, wt %	
		Carbon	Sulfur	Carbon	Sulfur
25	39.2	27.8	7.24	49.1	29.6
12.9	29.1	28.5	6.65	37.3	20.2
5.8	25.1	28.6	6.22	32.8	16.6

Table 4-4. EFFECT OF CYCLONE FEED PRESSURE AT 6.1% FEED SOLIDS

Feed Pressure, psig	Cyclone Overflow Recovery, wt %	Analysis, wt %		Distribution, wt %	
		Carbon	Sulfur	Carbon	Sulfur
30	15.1	28.9	5.39	19.7	8.5
50	13.9	29.4	5.24	18.3	7.8
70	12.7	29.5	5.13	16.9	6.8

forced a shutdown. The particle size analysis of the hydrocyclone overflow product produced prior to shutdown gave a d_{90} of 15.1 μm . The particle size analysis of the Derrick screen undersize showed a d_{90} of 29 μm . Because of the short running time, no effort was made to balance the weight recoveries of the individual products.

The electrical problem in the grinding and sizing circuit has been isolated and repaired, the operation will be resumed next quarter. Several hundred kilograms of shale will be ground in the circuit to produce feedstock for column cell flotation and stirred ball mill studies.

Subtask 4.4. Integrated Grinding and Flotation

The objectives of this subtask are to determine the column flotation characteristics of Eastern shale and to investigate the application of a novel integrated grinding and column flotation technique in a single-stage operation. The University of Kentucky Center for Applied Energy Research (UK-CAER) is evaluating the advanced Ken-Flote column flotation technique in conjunction with the BDR Mill column to obtain a high grade (125.2 L/metric ton; >30 gallons per ton [GPT]) oil shale at more than 90 percent carbon recovery. The BDR Mill column utilizes a single-stage grinding/cleaning system that avoids overgrinding the shale. The goals of the project are to remove up to 90 percent of the inorganic minerals using minimum grinding energy.

During the quarter, UK-CAER conducted column flotation tests in the 5.1-cm (2-inch) diameter 6.1-m high (20-ft) Ken-Flote column. Betz M252 was used as a frother. The effects of wash water addition rate and froth height on grade and recovery of organic carbon was evaluated. The wash water addition rate was varied from 0.2 to 0.6 L/min, while the air flow, feed rate, and froth height were maintained at 3 L/min, 1 L/min, and 1.2 m (4 feet), respectively. The highest organic carbon recovery achieved was 56 percent at a grade of 61.8 percent with a wash water rate of 0.4 L/min.

Froth height was varied from 0.6 to 1.8 m (2 to 6 feet) and the optimum was determined to be 1.2 m (4 feet). A few tests were also conducted to study the effect of dispersant (sodium hexametaphosphate) addition. At up to 2.5 kg/metric ton (5 lb/ton) addition, the dispersant did not improve grade or recovery of organic carbon.

UK-CAER also conducted some tests with pine oil added to the slurry at 0.45, 0.67, and 0.90 kg/metric ton (1, 1.5, and 2.0 lb/ton of shale). The flow rate of air to the column was varied between 2 and 3 liter/minute (4.2 to 6.41 ft^3/h). The results showed that at an air flow rate of 3 L/min and a pine oil addition of 0.90 kg/metric ton, a recovery of 73 percent was achieved. The concentrate from this test contained 43 percent organic carbon. Reducing the air flow rate to 2 L/min, resulted in a concentrate with 52.5 percent organic carbon and a recovery of 65 percent.

Figure 4-4. CONTINUOUS GRINDING AND SIZING CIRCUIT

The effect of adding fuel oil to the feed slurry was also determined. The results showed that with a constant pine oil addition of 0.67 kg/metric ton, increasing the fuel oil concentration from 0.67 to 2.2 kg/metric ton, decreased the organic carbon content of the product from 47 to 42 percent.

The effect of slurry feed rate was also determined. For these tests, the column operating conditions were kept constant at 2 L/min air flow rate, 0.4 L/min wash water, and 0.67 kg/metric ton pine oil. As the feed rate was reduced from 1 to 0.5 L/min, the recovery increased from 50.9 to 59.9 percent; however, the grade of the organic carbon content of the concentrate decreased from 47.4 to 39.7 percent.

In another series of tests, UK-CAER obtained a rougher concentrate in the first stage and floated again in a cleaner stage to improve the grade of the column flotation froth product. In the rougher stage, the recovery of carbon was 54.7 percent with a concentrate grade of 47.8 percent carbon. Cleaner flotation of this product yielded 54.8 percent carbon recovery with a concentrate grade of 56.8 percent carbon. The overall recovery for this two-stage process was 30.0 percent with a final grade of 56.8 percent carbon. These results show that a cleaner flotation can increase the carbon content of the final product, however, the overall recovery is poor. This test was conducted using the static sparger for fine bubble generation with a concentration of 1 kg of pine oil per metric ton of shale. To improve the overall recovery it would be necessary to significantly increase the recovery in the rougher flotation stage.

Additional column flotation tests were conducted using the foam jet bubble generating device. Increasing the pine oil concentration from 1 to 5 kg/metric ton increased carbon recovery from 36.8 to 56.0 percent, while decreasing the concentrate grade from 45.4 to 33.8 percent carbon. Varying the concentration of fuel oil from 0.5 to 2.5 kg/metric ton (M252 frother added at 0.75 kg/metric ton) improved the recovery from 42.8 to 95.8 percent. However, the concentrate grade decreased from 40.7 to 18.2 percent carbon over the same concentration range. These results show that for single-stage flotation, fuel oil and M252 frother provide significantly higher recovery than pine oil when the foam jet is used for bubble generation. However, the grade of the concentrate obtained with pine oil is much higher than that obtained with fuel oil and M252.

Next quarter, UK-CAER will conduct additional tests in the Ken-Flote column with the foam jet bubble generating system. Their work will focus on the addition of wash water and on cleaning with a cleaner flotation stage to improve the concentrate grade without sacrificing recovery.

Subtask 4.5. Evaluation of Different Grinding Media

The components of stirred ball milling costs are power, media consumption, and capital (installed equipment). Previous studies by MRI have focused on minimization of power consumption in a stirred ball mill using steel media (2-mm and 1.1-mm diameter balls) and the John Option stirring device. These studies have shown that smaller grinding media is more efficient in producing -10 μ m product. However, the cost of 1.1-mm steel media is substantially

higher than that of the 2-mm media. Thus, the power savings are offset by the higher media consumption costs.

In order to compare grinding efficiency of steel and sand media, a single, large batch of Alabama shale rougher concentrate having a d_{50} of 27.3 and d_{30} of 10.3 μm at 41 percent solids was used in all grinding experiments. The John Option was tested with sand and steel media; the Molinex Option was tested with sand only. Equal size of steel and sand media (1.1 mm) at 85 percent loading was used. The grinding data was collected by varying feed rates and rotor speed. Subsequently, modified Charles size reduction energy relationships were developed as follows:

$$E = 2.3157 \times 10^4 \times d_{50,p}^{(-3.2796)} \quad \text{Molinex-Sand media}$$

$$E = 1.0708 \times 10^5 \times d_{50,p}^{(-4.2853)} \quad \text{John-Sand media}$$

$$E = 6.2950 \times 10^5 \times d_{50,p}^{(-5.2654)} \quad \text{John-Steel media}$$

An energy efficiency evaluation of these mill media combination can be done by simulation. The simulated values of (E versus d_{50}) are shown in Table 4-5. The data show that for ultra-fine grinding to a d_{50} of 6 μm or less, sand media requires less energy than steel media. For a smaller size reduction ratio, in which the product d_{50} is between 6 and 9 μm , steel media requires less energy.

Table 4-5. PREDICTION OF GRINDING ENERGY REQUIRED BASED ON MODIFIED CHARLES RELATIONSHIPS FOR VARIOUS MEDIA COMBINATIONS WITH ALABAMA SHALE ROUGHER CONCENTRATE

Product Median Size, $d_{50,p}$, μm	Mill-Media Combination		
	1.1-mm Sand		1.1-mm Steel
	John Opt.	Molinex Opt.	John Option
	E (kWh/t)		
3	966.2	630.8	1935.4
4	281.8	245.6	425.5
5	108.2	118.1	131.4
6	49.6	65.0	50.3
7	25.6	39.2	22.3
8	14.4	25.3	11.1
9	8.7	17.2	6.0
10	5.6	12.2	3.4

It is also of interest to see whether the characteristic shape of the product shale distribution produced is different for steel and sand media. A reasonable way to compare this will be at equal values of product d_{50} . Table 4-6 lists the product d_{50} obtained in sand and steel media runs. A meaningful comparison of the effect of media will be had by comparing sample 5 with sample 13 and sample 7 with sample 11. A strict comparison on the effect of mill type cannot be made; however, a close approximation can be made by comparing sample 2 with sample 4 and 8. These comparisons are shown in Figures 4-5 through 4-7. The shape of the size distribution is similar for both media and mill comparisons.

Table 4-6. PRODUCT d_{50} VALUES FOR MILL-MEDIA SYSTEM

<u>Mill-Media Combination</u>	<u>Sample No.</u>	<u>Product d_{50}, μm</u>
Molindex-Sand	1	5.8
	2	5.0
	3	5.4
John-Sand	4	5.1
	5	4.8
	6	4.3
	7	4.7
	8	4.9
John-Steel	9	4.6
	10	5.0
	11	4.7
	12	4.2
	13	4.8

Subtask 4.6 Evaluation of Concentrate Preparation Techniques

Subtask 4.6.1 Oil Agglomeration and Pelletizing

Beneficiation of Eastern shales by column flotation results in a product of superior chemical composition (ie., ~40 GPT), which requires further processing. The concentrate is obtained as a dilute (>95 percent water) slurry of fine kerogen ($d_{50} > 10 \mu\text{m}$). A potential treatment scheme would consist of thickening, pressure filtration, briquetting, and thermal drying.

The objective of this task is to investigate other techniques that have the potential to reduce the cost of preparing concentrate for the PFH process, such as oil agglomeration. The potential advantages of oil agglomeration are that filtration is not required and, because the agglomerating oil tends to fill the interstices between kerogen grains, only surface moisture must be removed by thermal drying.

MRI produced batches of agglomerates by the method illustrated in Figure 4-8 (Flowsheet 1). While this sequence of process steps is satisfactory for laboratory-scale application, it would not likely be the sequence selected for large-scale production. Three alternative process flowsheets, also shown in Figure 4-8, have been selected for study in this program. Flowsheets 2 and 3 are oil agglomeration techniques and Flowsheet 4 is a standard pelletizing approach. MRI has focused their efforts on the conditioning step which appears in all three phases. Samples of concentrate slurry, thickened to about 25 percent solids, were conditioned for 1 minute in a high speed blender with additions of 5 percent asphalt. The asphalt was added as a fatty acid-stabilized emulsion. After conditioning, the sample showed substantial air entrainment but no discernible phase separation. Further, microscopic examination revealed no agglomeration or flocculation. Filtration tests

Figure 4-5. EFFECT OF MEDIA TYPE ON THE SHAPE OF PARTICLE SIZE DISTRIBUTION AT SIMILAR PRODUCT MEDIAN SIZE

Figure 4-6. EFFECT OF MILL TYPE ON THE SHAPE OF PARTICLE SIZE DISTRIBUTION AT SIMILAR PRODUCT MEDIAN SIZE

Figure 4-7. EFFECT OF MEDIA TYPE ON THE SHAPE OF PARTICLE SIZE DISTRIBUTION AT SIMILAR MEDIAN PRODUCT SIZE

Flowsheet 1

Flowsheet 2

Flowsheet 3

Flowsheet 4

Figure 4-8. ALTERNATIVE OIL AGGLOMERATION AND PELLETIZING SCHEMES

showed the conditioned samples filtered at the same rate as unconditioned samples and were about equal in moisture content. The filter cake from the conditioned samples however did appear to be more cohesive than that formed from concentrate without added asphalt.

One concentrate sample was conditioned with the addition of 20 milliliters of n-pentane/100 grams of concentrate. This sample showed a strong phase separation along with a high level of air entrainment. The n-pentane evaporated rapidly and the residue was not cohesive.

In a parallel, separately funded study of coal agglomeration a factorial experiment on the same conditioning step was conducted. Four factors were studied: asphalt concentration, conditioning speed, conditioning time, and solids content. The size distribution of the coal was measured before and after conditioning. It was found that conditioning time was the most important factor causing an increase in particle size (agglomeration). Asphalt concentration while a factor was much less important. MRI will extend these results to oil shale concentrate.

Next quarter, MRI will conduct oil agglomeration tests using extended periods of agitation. The vessel in which the conditioning step is conducted is being modified to minimize the level of entrainment during conditioning. Air entrainment, while aiding phase separation, appears to retard agglomeration. Conditioning tests will also include higher slurry densities and higher asphalt concentration.

Subtask 4.6.2. Bioflocculation of Kerogen

The objective of this subtask is to use hydrophobic microorganisms to selectively flocculate kerogen from enriched flotation concentrate to produce an ultrahigh grade product and simultaneously enhance subsequent dewatering of the concentrate. Another objective of the subtask is to use hydrophobic microorganisms as precursors for oil-assisted spherical agglomeration to produce oil enriched-water repellent kerogen agglomerates. This subtask is being conducted by the University of Nevada, Reno (UN).

During the quarter, UN conducted flocculation tests to investigate the effects of pH and microorganism concentration. The predried solids concentrate (containing 26 percent organic carbon) was suspended in water for 30 minutes and the slurry was mixed at 90 rpm for 10 minutes. After 10 minutes of mixing, the slurry was diluted and dispersed again with ultrasonic treatment. Initial experiments with the diluted slurry containing 1 weight percent solids showed that the critical concentration of microorganisms for flocculation should be about 70 ppm or more. As a result, most of the flocculation experiments were conducted at that concentration. Flocculation and settling rates of kerogen concentrate for various pH values are given in Figures 4-9 through 4-12. The flocculation and settling rate of kerogen is increased with the addition of Mycobacterium phlei. Good pyrite and ash rejection was noticed in an alkaline pH. Elemental analysis showed that the organic carbon content in the sediments was in the range of 32 to 35 percent compared to the original feed, which had 26 percent carbon. At an acidic pH of 4.6, no significant difference in the settling rate was observed after 5 minutes with

Figure 4-9. SETTLING CHARACTERISTICS OF BENEFICIATED ALABAMA SHALE (1.0 wt % solids, pH 7.3, M. phlei = 70 ppm)

Figure 4-10. SETTLING CHARACTERISTICS OF BENEFICIATED ALABAMA SHALE (1.0 wt % solids, pH 4.6, M. phlei = 70 ppm)

Figure 4-11. SETTLING CHARACTERISTICS OF BENEFICIATED ALABAMA SHALE (1.0 wt % solids, pH 9.4, M. phlei = 70 ppm)

Figure 4-12. EFFECT OF pH ON SETTLING CHARACTERISTICS OF BENEFICIATED ALABAMA SHALE (10 min settling time, M. phlei = 70 ppm, 1.0 wt % solids)

and without organisms. However, for a settling time of less than 5 minutes, bacterial addition had a positive effect on the initial flocculation and settling. As reported earlier, the inherent flocculation of kerogen in an acidic pH was due to the aggregation of kerogen particles near the isoelectric point. Optical microscopic examination showed that the size of the flocs with the addition of organisms was large and held strongly by bacterial adhesion and bridging. A scanning electron micrograph of flocculated kerogen with M. phlei is shown in Figure 4-13. The organism is strongly attached to the kerogen particles. Under similar conditions, M. phlei was not attached either to pyrite or to clay particles.

Figure 4-13. SCANNING ELECTRON MICROGRAPH OF
KEROGEN WITH Mycobacterium phlei

The flocculation and settling of freshly prepared flotation concentrate (prepared by conventional flotation at UN) is presented in Figure 4-14 as a function of pH. Flocculation characteristics of the freshly prepared sample were slightly different from that of the dry sample. However, in both cases, improved carbon content was noticed in the sediments. These preliminary results suggest that initial flocculation with organisms in a moderately alkaline pH and subsequent flocculation by pH adjustment to 3 to 4 will improve both the quality of the product and settling rate. Although preliminary in nature, it is estimated that more than 80 percent of the water present in the slurry can be recycled and/or recovered in a very short time by using conventional thickener with addition of M. phlei. It was determined that the recycled water (decanted) did not have any deleterious effect on the subsequent flotation of kerogen.

Next quarter, UN will evaluate the filtration rate of flocculated sediments and the effect of recycled water on flotation performance.

Task 5. Operation of PFH on Beneficiated Shale

The objectives of this task are to expand the PFH data base by conducting laboratory- and bench-scale tests with beneficiated Alabama shale, and characterize the effluent streams from these tests. This task is divided into two subtasks: 5.2.1. (Laboratory-Scale Tests) and 5.2.2. (Bench-Scale Continuous Tests), which will be performed by IGT.

Discussion

During the quarter, work was completed on several equipment modifications planned for the AMRR (advanced multipurpose research reactor), which will be used for bench-scale testing of beneficiated shale. These improvements include the addition of new feed and residue screw controllers and counters, modification of the residue screw flights, and modification of the EST (environmental sampling train) to ensure that only Teflon[®]-coated surfaces come in contact with the acid and base scrubs. Tests in the bench-scale unit will begin next quarter.

Task 6. Environmental Data and Mitigation Analyses

The overall objectives of Task 6 are to obtain environmental data relating to PFH and shale beneficiation, and also to analyze the potential environmental impact of the integrated PFH process. This task is divided into four subtasks: 6.1. Characterization of Processed Shales, 6.2.2 Wastewater Treatability, 6.4.1. PFH Process Analyses, and 6.4.3. Plant Energy Optimization.

Subtask 6.1. Characterization of Processed Shales

The objective of this subtask is to determine the effects of PFH processing on the physical and chemical characteristics of raw and spent beneficiated shale.

Figure 4-14. EFFECT OF pH ON SETTLING CHARACTERISTICS OF FRESHLY PREPARED BENEFICIATED ALABAMA SHALE (5 min settling time, M. phlei = 100 ppm, 0.5 wt % solids)

Discussion

This subtask will be initiated next quarter when appropriate samples of hydrotreated shale are available from the laboratory- and bench-scale units.

Subtask 6.2. Water Availability and Treatment Studies

Subtask 6.2.2. Wastewater Treatability

The objective of this subtask is to determine suitable techniques for treating wastewater generated during shale processing. Tennessee Technological University (TTU) is conducting the work on this subtask.

Discussion

During the quarter, TTU continued evaluating the use of gas chromatography (GC) as an analytical tool for determining the concentration of the four organic compounds present in the PFH process water. Problems were encountered in analyzing for some of the compounds using a packed column. Therefore, a capillary column was installed and testing of this column was initiated.

Acclimation procedures with 4-methyl pyridine also continued during the quarter. An evaluation of this compound as a nitrogen source for microorganisms utilizing one of the other compounds of interest as a carbon source was initiated.

Biological treatability studies continued with phenol and MEK. Five additional experiments were conducted with phenol and one with MEK. All of the experiments used 1.5-liter reactors with varying concentrations of the compounds.

In the phenol experiments, both the change in COD (chemical oxygen demand) and phenol with time were determined. Phenol experiments 2 through 6 were performed using initial phenol concentrations of 100, 250, and 450 mg/L. Figure 6-1 shows the stabilization of the chemical oxygen demand with time for each of these concentrations for experiment 6. Stabilization began within 10 hours and was completed for reactors containing 100 and 250 mg/L after about 35 hours, and about 58 hours for 450 mg/L. A comparison of the results from tests 2 through 6 is presented in Table 6-1. As the data in the table show, experiment 6 maintained the initiation and completion times, for the removal of COD, that were observed in experiments 4 and 5. The differences observed are considered to be within reasonable limits for heterogeneous biological populations. The differences between experiments 2 and 3, and 4, 5, and 6 are attributed to continuing acclimation of the microorganisms to the phenol.

Comparative plots of the phenol and the COD concentrations for experiment 6 are shown in Figures 6-2 through 6-4. These figures, along with similar data from experiments 2, 3, 4, and 5, indicate that the change in COD can be attributed to the biodegradation of the phenol. From the batch experiments for phenol that have been conducted to date, the following conclusions can be drawn.

Table 6-1. COMPARISON OF PHENOL BATCH EXPERIMENTS 2 THROUGH 6						
Reactor	Phenol - 100 mg/L		Phenol - 250 mg/L		Phenol - 450 mg/L	
Experiment	Start (hrs)	Complete (hrs)	Start (hrs)	Complete (hrs)	Start (hrs)	Complete (hrs)
2	30	75	30	90	30	120
3	20	80	20	80	20	130
4	15	40	15	55	15	40
5	10	41	10	41	10	41
6	10	35	10	35	10	58

1. In a batch aerobic environment with an excess of nutrients, buffered at a neutral pH, and phenol as the only carbon source, phenol was found to be biodegradable over a range of concentrations up to 450 mg/L.
2. A stable growth of microorganisms was achieved with the phenol as the only carbon source within a few days, but complete acclimation of the organisms to the phenol took approximately 60 days.
3. Gas chromatography, through the use of a packed column, can be used effectively for the determination of phenol concentrations in a filtered sample.

In the batch treatability studies with MEK, the initial concentrations used were 50, 100, and 250 mg/L. The change in COD with time for batch experiment 1 is presented in Figure 6-5. The biodegradation of the MEK began within the first 4 hours of the experiment and was completed for reactors containing 50, 100 and 250 mg/L within about 32 hours.

Next quarter, studies involving the biological treatability of MEK will be completed. Studies to determine the use of 4-methyl pyridine as a nitrogen source by microorganisms utilizing one of the other compounds as a source of carbon will continue.

Subtask 6.4.3 Thermoeconomic Evaluation

The objective of this subtask is to provide an initial evaluation of the PFH plant design from thermodynamic and economic viewpoints. The goals of this study are to identify thermodynamic losses, to assist in developing cost-effective solutions to reduce those losses, to improve the understanding of the cost/benefit tradeoffs in the design, and to facilitate future optimization studies. This subtask is also being conducted by TTU.

During the quarter, TTU focused on the detailed exergy analysis of the PFH plant and initiated the thermoeconomic evaluation. In addition, TTU continued development of computer subroutines to simulate the performance of plant components.

Figure 6-1. COD vs. TIME FOR PHENOL BATCH EXPERIMENT 6
(The Initial Phenol Concentrations were 100, 250, and 450 mg/L)

Figure 6-2. COD AND PHENOL vs. TIME FOR PHENOL BATCH EXPERIMENT 6
(The Initial Phenol Concentration was 100 mg/L)

Figure 6-3. COD AND PHENOL vs. TIME FOR PHENOL BATCH EXPERIMENT 6
(The Initial Phenol Concentration was 250 mg/L)

Figure 6-4. COD AND PHENOL vs. TIME FOR PHENOL BATCH EXPERIMENT 6
(The Initial Phenol Concentration was 450 mg/L)

Figure 6-5. MEK vs. TIME FOR MEK BATCH EXPERIMENT 1

Exergy Analysis

A preliminary exergy analysis of the PFH plant design, shown in Figures 6-6 (total plant) and 6-7 (hydrogen plant), was performed. The results are presented in Tables A-1, A-2, and A-3 in Appendix A. Table A-1 shows the mass flow rates, temperatures, pressures and the flow rates of enthalpy, entropy and exergy of the material streams in the plant. For each plant component, Table A-2 shows the heat loss, power supplied, exergy destruction flow rate, the exergy destruction ratio (exergy destruction in the component being considered divided by the sum of exergy destruction in the total plant), the ratio between the exergy destruction in the component being considered and the exergy of raw shale supplied to the PFH plant, and, finally, the component exergetic efficiency, which represents the real thermodynamic efficiency of the component. Table A-3 summarizes the mass and heat balances in the steam/water system.

Based on the results presented in Table A-2, several observations can be made. The excessive heat loss in the raw shale preheating indicates that either the temperature of stream 6 must be higher or the temperature of stream 4 must be lower. Either temperature correction will reduce the exergy destruction and will increase the exergetic efficiency of shale preheating. The significant heat loss (148.7 MW) and exergy destruction (almost 75 MW) in the desalting and hydrotreating unit will be explained after a more detailed flow diagram of this unit is available.

The relatively high exergy destruction in the reformer furnace (150.6 MW) is mainly caused by irreversibilities in (a) the combustion of methane, (b) the heat transfer from the combustion gases to the steam and gas to be reformed, and (c) the chemical reactions during the reforming process. Part of the sensible heat of the flue gas leaving the reformer furnace (stream 160) and the fired heater (stream 159) could be used for producing low-pressure steam and for feed water preheating.

The addition of steam (stream 115) to stream 101 in the hydrogen plant should occur after stream 101 has been preheated in the first heat exchanger. This change would reduce the surface area of this heat exchanger and, thus, the total investment costs. The total exergy destruction will not be affected by this change.

In the hydrogen plant, the two heat exchangers where stream 102/103 is preheated and stream 108/109 is cooled could be combined into one heat exchanger. This change will reduce the total investment costs.

The exergy destruction in the water quenching of stream 106 at the outlet of the reformer furnace is significant (20.4 MW). The thermoeconomic analysis should determine if using an advanced heat exchanger to cool stream 106/107 and steam addition to stream 108 in lieu of the water quenching would improve the overall economics of the PFH plant.

The estimated overall power consumption in the plant is about 100 MW. The design and operation of the gas compressors should be optimized from the thermoeconomic viewpoint. In addition, the overall plant economics should be

Figure 6-7. FLOW DIAGRAM OF THE HYDROGEN PLANT

improved through combination of the PFH plant with a combined-cycle power plant (or with an intercooled steam-injected gas turbine), which would use the net steam generated in the plant (Table A-3) and would provide the required electric power.

The overall exergetic efficiency of 84.9 percent shown in Table A-2 for the total plant indicates that the overall plant design is thermodynamically efficient. Some potential, however, still exists for improving the overall efficiency and reducing the costs of the final products.

Thermoeconomic Evaluation

During the quarter, TTU initiated development of the computer software, the cost balances and the equations required to complete the thermoeconomic evaluation. The development of the equations that TTU will use in the thermoeconomic evaluation is presented in Appendix B.

Next quarter, a first thermoeconomic evaluation will be presented. In addition, work to complete the PFH plant design and to study the effect of important plant parameters on the overall efficiency and costs of the final products will be initiated.

Task 7. Sample Procurement, Preparation, and Characterization

The objective of this task is to procure, prepare, and characterize raw and beneficiated Eastern oil shale samples for all of the experimental tasks of the program extension.

MRI completed all of the components of this task during the quarter. Chemical analyses of selected products produced during the pilot plant operations at Michigan Technological University (MTU) were completed. The analyses of a head sample, taken by MTU, from the 6 tons of shale shipped from Madison County, Alabama to MTU are presented in Table 7-1. The results show that the sample sent to MTU was significantly lower in Fischer Assay (FA) oil yield than the sample subsequently sent to UK-CAER and that retained by MRI. Analyses of the latter two samples are also shown in Table 7-1.

The difference in the analyses result from the sampling procedure. A 3-ton sample was taken and returned to MRI for preparation for the MRI and UK-CAER studies. This sample was wet screened at 1/4 inch to remove mud and hand picked to remove rock fragments not associated with the in-place shale. The slight differences in the UK-CAER and MRI samples can be attributed to large sample mixing problems.

In order to confirm past analytical procedures relating density to carbon content and oil yield, on the MTU head sample returned to MRI, three flotation tests were conducted at 3 different rod mill grinding times for subsequent correlation of these values. No effort was made in those mechanical cell flotation studies to produce high kerogen recovery because of the necessity of producing flotation products with widely varying densities, carbon contents and oil yields. The results of these studies are shown in Table 7-2.

Table 7-1. ANALYSES OF ALABAMA OIL SHALE HEAD SAMPLES

Sample	----- Shipped to -----		
	MTU	UK-CAER	MRI
Moisture Content, wt %	NA*	1.18	1.36
Ultimate Analysis, wt %			
Carbon	13.27	16.46**	15.11+
Hydrogen	1.59	NA	1.78
Nitrogen	0.47	NA	0.41
Sulfur	7.19	8.20	8.15
Ash	77.30	72.80	74.57
Fischer Assay, GPT	10.5	14.6	12.0
* Not analyzed.			
** Organic carbon.			
+ Total carbon.			

Evaluation of the carbon-density ratios of all the products produced in this test series gave carbon values ranging from 2.37 (underflow samples) to 37.8 percent and density values ranging from 1.87 to 2.83 g/ml. FA of the flotation concentrates, combined middlings, and tailings products from these tests ranged from 32.4 to 0.6 GPT. Calculated FA for the flotation feed in the three tests showed a reduction in oil yield of about 15 percent from the 30-minute grind to the 120-minute grind, as shown in Table 7-2.

Table 7-2. COMPARISON OF FLOTATION RESULTS ON MTU
SAMPLE GROUND TO 3 DIFFERENT SIZE CONSISTS

Grinding Time, min	Size, μ m		Weight %	FA, GPT	Analysis, wt %		Density, g/ml	Distribution, %		
	d ₉₀	d ₅₀			Carbon	Sulfur		oil	C	S
30	36	12	40.6	21.3	23.8	13.1	2.17	81.3	75.9	72.0
60	23	8	28.2	26.5	30.1	15.1	2.06	69.6	65.2	57.4
120	17	6	18.3	32.4	37.8	15.5	1.87	65.5	55.3	39.2

Calculated feed FA, 30 min = 10.6, 60 min = 10.8, 120 min = 9.0 GPT

Analyses of selected flotation feed, concentrate and tailings samples taken by MTU personnel during their continuous grinding and column cells flotation studies; wherein, they were using product densities as the primary process control, have been completed. The MTU studies were two fold in that (1) MTU would produce 1 ton of flotation concentrate for subsequent compaction and sizing prior to PFH studies, and (2) MTU personnel would make comparative studies of data obtained from a MTU packed column flotation cell and a Deister column flotation cell, operating from a common flotation feed. Analyses of these flotation products for carbon and sulfur have been correlated with density measurements furnished by MTU and compared, in straight line plots, with the carbon, sulfur and oil yield data generated from MRI studies. These data (Figure 7-1) show that the density to carbon ratios of the two sets of data are close but not equal which may indicate some difference in the 10-kg

head sample returned to MRI and the tonnage sample treated at MTU. However, the relationship of density to carbon, as well as density to oil, held true for this lower grade sample.

Figure 7-1 also shows the relationship of the response of sulfur, or pyrite, to the flotation conditions. In the case of the MTU sulfur analyses, these data were generated from shale ground to an average d_{90} of about 12 μm ; whereas, the MRI sulfur analyses were generated from shale ground only to a d_{90} range of 36 to 17 μm . Previous column cell versus mechanical cell test data had indicated that the lower sulfur analyses normally found in column cell concentrates might be a function of column froth height and/or wash water volume; however, recent mechanical cell concentration of Alabama oil shale ground to a d_{90} of 11 μm have yielded concentrates containing about 7 percent sulfur. On the basis of these results, the pyrite liberation point is indicated to be in the 10 to 12 μm range.

Comparison of types of column cells

Neither of the large column cells at MTU were able to reproduce the results of MRI studies. The MRI studies utilized a small 4-inch diameter, 63-inch tall continuous laboratory-scale column cell, and generated data relating grade to density. A flowsheet (Figure 7-2) shows the system used to produce the feed to the column cells, as well as the disposition of the concentrate and tails from the flotation cells.

Table 7-3 shows a summary of the operating results of the flotation circuit based on density samples taken during the course of the pilot plant campaign. Concentrate weight recoveries are also given in this table. The average concentrate weight recoveries should be fairly representative of the overall pilot plant campaign; whereas, the weight recoveries shown for the high and low density measurements indicate that such concentrate weight recoveries could have occurred based on the available density of data.

Using the average density values, the average concentrate weight recoveries and determining the carbon content based on a point midway between the MTU and MRI density to carbon values shown in Figure 7-1, material balances for the two column cells are given in Table 7-4. The results show that, under the test conditions, neither of the column cells was effective in yielding high recovery of the kerogen. On an average the MTU packed column gave a higher grade concentrate than was obtained from the Deister column cell. This data also indicated that the overall analyses for the sample treated at MTU was significantly higher than the head sample returned to MRI. The head sample returned to MRI (Table 7-1) contained 13.27 percent carbon and 10.5 GPT of oil compared with the indicated 14.75 percent carbon and 12 GPT of oil shown in Table 7-4.

Because of the low kerogen recovery during this pilot plant campaign only 680 kg (1500 lb) net weight of concentrate was produced. A head sample of this concentrate, shipped to MRI, gave the results shown in Table 7-5.

Figure 7-1. CARBON:DENSITY:OIL, MTU COLUMN CELL
vs. MRI MECHANICAL CELL DATA

Figure 7-2. FLOWSHEET FOR CONTINUOUS PROCESSING OF ALABAMA OIL SHALE AT MTU

Table 7-3. SUMMARY OF MTU FLOTATION RESULTS
BASED ON DENSITY ANALYSES OF SAMPLES

Product	No. of Samples	Density, g/ml			Conc. Weight, %		
		Avg.	High	Low	Avg.	High	Low
Column Cell Feed	11	2.41	2.46	2.35	--	--	--
MTU Cell Conc.	12	1.79	1.92	1.62	20.5	26.0	15.1
MTU Cell Tails	12	2.57	2.65	2.48	--	--	--
Deister Cell Conc.	13	2.00	2.12	1.97	22.6	34.6	13.5
Deister Cell Tails	13	2.53	2.64	2.49	--	--	--
Final Concentrate	10	1.90	1.97	1.82	--	--	--

Table 7-4. AVERAGE MATERIAL BALANCES FOR THE MTU
PACKED COLUMN CELL AND THE DEISTER COLUMN CELL

<u>Flotation Product</u>	<u>wt %</u>	FA, <u>GPT</u>	<u>Carbon. %</u>	<u>Distribution, wt %</u>	
				<u>Oil</u>	<u>Carbon</u>
MTU Packed Column Cell					
Concentrate	20.5	33.5	38.0	55	52
Tails	<u>79.5</u>	7.0	9.0	<u>45</u>	<u>48</u>
Feed	100.0	12.4	14.9	100	100
Deister Column Cell					
Concentrate	22.6	26.0	30.5	50	47
Tails	<u>77.4</u>	7.5	10.0	<u>50</u>	<u>53</u>
Feed	100.0	11.7	14.6	100	100

Table 7-5. ANALYSIS OF HEAD SAMPLE OF
TOTAL CONCENTRATE PRODUCED AT MTU

FA, GPT	Density, g/mL	Analysis, %			
		Carbon	Hydrogen	Nitrogen	Sulfur
25.4	1.99	30.65	3.33	1.03	8.46

Task 8. Project Management and Reporting

The objective of this task is to coordinate all aspects of the program among DOE, IGT, and the various subcontractors to insure that a cohesive program is maintained.

Discussion

During the quarter, IGT personnel prepared project status reports for June, July, and August. Also, IGT presented three papers at the 1991 Eastern Oil Shale Symposium on various project-related topics. Papers were also presented by IGT subcontractors MRI, TTU, and UN. The symposium was held November 12-14, in Lexington, Kentucky.

FUTURE PLANS

Work on the scheduled tasks will continue as planned.

ACKNOWLEDGMENTS

IGT acknowledges the significant work being conducted on this project by the individual subcontractors, their principal investigators, and colleagues -

MRI:	Dr. C. W. Schultz
UK-CAER:	Dr. B. K. Parekh
UN:	Professor M. Misra
TTU:	Professor W. P. Bonner

Appendix A.

Results of the Preliminary Exergetic Evaluation of the PFH Proces Plant by Tennessee Technological University

Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT

Table A-2: HEAT LOSS, POWER SUPPLIED, EXERGY DESTRUCTION FLOW
RATE, EXERGY DESTRUCTION RATIO, EXERGY DESTRUCTION TO SHALE
EXERGY RATIO, AND EXERGETIC EFFICIENCY FOR PLANT COMPONENTS

Table A-3. STEAM GENERATION/CONSUMPTION (Positive values mean
steam generation, negative values mean steam consumption)

Appendix A.

RESULTS OF THE PRELIMINARY EXERGETIC EVALUATION OF THE
PFH PROCESS PLANT BY TENNESSEE TECHNOLOGICAL UNIVERSITY

Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT

Table A-2: HEAT LOSS, POWER SUPPLIED, EXERGY DESTRUCTION FLOW
RATE, EXERGY DESTRUCTION RATIO, EXERGY DESTRUCTION TO SHALE
EXERGY RATIO, AND EXERGETIC EFFICIENCY FOR PLANT COMPONENTS

Table A-3. STEAM GENERATION/CONSUMPTION (Positive values mean
steam generation, negative values mean steam consumption)

**Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT
(Part 1)**

Stream No.	m [lb/hr]	T [F]	P [psia]	H [MMBtu/hr]	S [Mbtu/hrR]	E [MMBtu/hr]
A	2051416	60.0	1.0	-5059.50	642.53	19311.60
W	37951	60.0	1.0	-260.15	34.03	0.04
B	2014142	600.0	1.0	-4859.24	1025.70	19344.65
C	1080822	900.0	1.0	-4016.67	571.87	4051.22
D	1080822	650.0	1.0	-4119.66	480.95	3995.47
1A	160446	600	43.3	-57.25	874.06	4061.41
1	160446	180	620.0	-143.68	770.43	4028.84
2	563750	1400	620.0	451.78	3530.92	14684.37
3	724195	1232.0	620.0	394.53	4429.70	18732.92
4	1733417	900.0	615.0	-592.52	5393.55	33699.63
5	0	0.0	0.0	0.00	0.00	0.00
6	1808642	600.0	610.0	-1407.78	5196.17	33548.46
7	563749	510.7	651.9	-268.52	2985.74	14205.74
10	563749	180.0	661.9	-504.48	2686.05	14125.52
16	1439753	460.4	600.0	-1614.65	4630.55	26877.78
17	1853	460.4	590.0	-4.37	4.70	23.92
19	1437899	460.4	595.0	-1610.29	4627.80	26852.84
20	1437899	130.0	590.0	-2150.91	3882.51	26699.53
21	1050352	100.0	575.0	-996.89	3473.67	22860.45
22	3845	100.0	570.0	-10.15	4.26	14.26
23	1194	100.0	570.0	-0.72	2.29	25.63
24	1040956	100.0	570.0	-956.34	3463.76	22820.2

**Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT
(Part 2)**

Stream No.	m [lb/hr]	T [F]	P [psia]	H [MMBtu/hr]	S [Mbtu/hrR]	E [MMBtu/hr]
25	1853	460.4	590.0	-4.37	4.70	23.92
26	364020	100.0	30.0	-92.47	314.93	6474.34
27	6723	470.2	30.0	-4.15	10.51	110.32
30	15840	100.0	100.0	-11.19	27.12	315.14
31	115894	100.0	20.0	-20.99	117.06	2100.14
32	126097	100.0	19.5	-22.70	124.63	2277.82
33	132820	107.7	19.5	-27.57	134.64	2387.66
34	115894	158.5	100.0	-18.91	114.47	2103.57
35	14692	100.0	90.0	-10.47	25.52	304.57
36	900004	100.0	560.0	-932.90	3333.97	20279.61
37	918	100.0	20.0	-6.26	0.89	0.00
38	1083	100.0	20.0	-0.22	1.31	22.22
39	124903	100.0	19.5	-21.98	121.79	2252.48
40	91	90.0	100.0	-0.62	0.09	0.00
41	1302	100.0	90.0	-1.25	1.71	10.65
42	27153	100.0	18.0	-38.80	38.80	189.27
43	875234	100.0	550.0	-901.61	3300.47	20100.91
44	726	90.0	90.0	-4.96	0.60	0.00
45	355	90.0	560.0	-2.42	0.34	0.00
46	25124	100.0	550.0	-33.80	29.59	180.95
47	0	100.0	18.0	0.00	0.00	0.00
48	26426	36.9	90.0	-35.05	33.53	190.44

**Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT
(Part 3)**

Stream No.	m [lb/hr]	T [F]	P [psia]	H [MMBtu/hr]	S [Mbtu/hrR]	E [MMBtu/hr]
51	25258	99.7	14.7	0.10	6.18	202.64
52	37822	99.7	14.7	-50.47	54.28	272.09
53	10670	100.0	14.7	-11.67	15.16	82.99
54	14676	99.7	14.7	-100.02	14.24	0.04
55	14676	99.7	14.7	-100.02	14.24	0.04
56	10492	99.7	14.7	-40.86	12.76	1.45
60	2706	100.0	100.0	-0.96	3.38	55.40
61	3789	100.0	20.0	-1.18	4.87	77.53
62	690516	100.0	14.7	-529.94	597.40	13335.11
63	60715	193.3	2041.2	-51.57	392.29	1918.50
64	51001	100.0	100.0	-90.31	118.91	849.95
65	30751	100.0	14.7	-102.30	55.01	160.66
67	1083	100.0	20.0	-0.22	1.31	22.22
68	495	100.0	250.0	-3.38	0.48	0.00
69	78846	297.7	64.7	-449.72	195.46	26.00
70	78846	297.7	64.7	-521.60	100.53	3.44
71	222829	120.8	14.7	-1405.87	250.92	161.63
72	10813	100.0	214.7	-12.45	26.03	93.66
73	205191	130.0	25.0	-1392.15	209.86	1.16
74	177402	130.5	20.0	-1203.55	181.59	0.97
75	192078	128.2	14.7	-1303.57	195.85	1.00
77	55882	100.0	320.0	-111.89	134.37	1247.98

**Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT
(Part 4)**

Stream No.	m [lb/hr]	T [F]	P [psia]	H [MMBtu/hr]	S [Mbtu/hrR]	E [MMBtu/hr]
78	1691323	60.0	14.7	-6.85	2769.75	1.53
79	1691323	90.5	17.4	5.62	2773.42	12.10
80	97050	100.0	320.0	-194.31	233.35	2167.36
81	348343	100.0	550.0	-358.84	1313.59	8000.16
82	123892	100.0	214.7	-100.74	939.92	3693.29
83	223015	100.0	16.7	-249.93	467.83	4256.36
84	526891	100.0	550.0	-542.77	1986.88	12100.75
85	526891	137.5	661.9	-523.75	1995.79	12115.14
86	123892	246.5	680.0	-66.46	917.15	3739.41
87	1436	250.0	20.0	-7.99	3.60	0.42
88	650784	171.7	661.9	-590.20	2924.74	15848.29
89	38169	100.0	320.0	-76.42	91.77	752.40
90	2999	100.0	320.0	-6.01	7.21	66.98
91	237644	100.0	16.7	-260.39	495.68	4559.70
92	192370	100.0	16.7	-210.79	401.25	3691.03
93	192370	242.4	320.0	-197.86	376.20	3716.98
94	73412	100.0	250.0	-74.74	532.68	2276.98
95	73412	226.8	679.9	-57.86	522.30	2299.26
96	45273	100.0	16.7	-49.61	94.43	868.67
97	60715	100.0	250.0	-61.81	440.55	1883.19
98	130281	488.8	614.7	-834.86	197.58	16.36
99	724195	180.0	661.9	-648.06	3450.52	18145.70

**Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT
(Part 5)**

Stream No.	m [lb/hr]	T [F]	P [psia]	H [MMBtu/hr]	S [Mbtu/hrR]	E [MMBtu/hr]
100	130281	488.8	614.7	-739.92	297.66	59.28
101	195369	239.8	320.0	-203.87	383.71	3783.79
102	747971	401.7	320.0	-3342.31	1719.63	3997.02
103	747971	470.8	310.0	-3292.99	1777.84	4016.09
104	747971	800.0	300.0	-3151.09	1911.63	4088.46
105	747971	1535.0	300.0	-2804.50	2129.87	4321.64
106	748129	1535.0	300.0	-2174.24	2591.83	4702.69
107	894880	1099.2	300.0	-3168.35	2878.57	4634.04
108	894880	841.7	290.0	-3310.25	2783.41	4541.59
109	894880	760.0	280.0	-3354.28	2752.90	4513.42
110	895042	900.0	280.0	-3357.20	2764.84	4512.04
111	895042	300.0	270.0	-3785.46	2319.94	4314.98
112	780239	100.0	260.0	-3375.73	1668.72	4222.58
113	525638	100.0	255.0	-1640.83	1423.33	4221.27
114	134127	100.0	250.0	-136.55	973.23	4160.17
115	552602	488.8	614.7	-3138.44	1262.56	251.44
116	146751	140.0	300.0	-994.11	152.52	1.10
117	254601	100.0	255.0	-1734.89	247.08	0.83
118	391015	100.0	250.0	-1503.55	403.99	82.97
119	0	0.0	0.0	0.00	0.00	0.00
120	38169	85.2	17.4	-76.42	105.37	845.33
121	172126	130.0	580.0	-1167.60	175.96	1.22

Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT
(Part 6)

Stream No.	m [lb/hr]	T [F]	P [psia]	H [MMBtu/hr]	S [Mbtu/hrR]	E [MMBtu/hr]
122	4358	100.0	575.0	-29.69	4.23	0.02
123	176484	129.3	575.0	-1197.29	180.20	1.23
124	177402	130.5	20.0	-1203.55	181.59	0.97
125	114803	300.0	270.0	-759.16	146.70	5.16
126	1060805	3674.6	17.4	-108.67	2471.69	899.91
127	127156	297.7	64.7	-725.27	315.22	41.92
128	127156	297.7	64.7	-841.20	162.13	5.54
129	64105	488.8	614.7	-364.08	146.46	29.17
130	64105	488.8	614.7	-410.79	97.22	8.05
131	54110	60.0	14.7	-0.22	88.61	0.05
132	104175	240.0	614.7	-695.17	124.34	2.95
133	93757	488.8	614.7	-532.48	214.21	42.66
134	10417	488.8	614.7	-66.76	15.80	1.31
135	38587	488.8	614.7	-219.15	88.16	17.56
136	38587	488.8	614.7	-247.27	58.52	4.84
137	21592	297.7	64.7	-123.16	53.53	7.12
138	21592	297.7	64.7	-142.84	27.53	0.94
139	1004932	90.0	17.4	3.21	1647.65	7.18
140	55882	85.2	17.4	-111.89	154.27	1237.64
141	1726911	90.0	614.7	-11783.00	1644.51	6.36
142	1726911	397.4	614.7	-11242.38	2423.73	142.04
143	2012317	60.0	14.7	-13793.88	1804.18	2.16

**Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT
(Part 7)**

Stream No.	m [lb/hr]	T [F]	P [psia]	H [MMBtu/hr]	S [Mbtu/hrR]	E [MMBtu/hr]
144	2012317	94.0	14.7	-13725.57	1931.51	4.30
145	67678	488.8	614.7	-384.37	154.63	30.79
146	67678	488.8	614.7	-433.69	102.64	8.50
147	60413	488.8	614.7	-387.13	91.62	7.58
148	60413	488.8	614.7	-343.11	138.03	27.49
149	469712	297.7	64.7	-3107.39	598.92	20.47
150	469712	297.7	64.7	-2679.13	1164.41	154.86
151	304551	60.0	14.7	-2087.61	273.05	0.33
152	304551	264.0	14.7	-1738.18	802.09	74.83
153	1265773	130.0	580.0	-983.30	3710.43	26697.31
154	1045994	100.0	575.0	-967.11	3469.61	22860.60
155	780239	300.0	270.0	-3026.30	2173.24	4309.83
156	1060805	854.0	17.4	-1085.52	2081.01	126.09
157	686391	90.0	17.4	2.19	1125.38	4.90
158	724554	3674.6	17.4	-74.23	1688.22	614.66
159	724554	600.0	17.4	-794.53	1376.48	56.36
160	1060805	542.8	17.4	-1180.46	1998.60	73.98
216	368890	460.4	600.0	-29.09	408.86	6578.94
217	368890	460.4	590.0	-29.09	408.86	6578.94
221	215422	100.0	575.0	-54.72	186.37	3831.41
223	215422	100.0	570.0	-54.72	186.37	3831.41
225	368890	460.4	590.0	-29.09	408.86	6578.94

**Table A-1: THERMODYNAMIC PROPERTIES OF STREAMS IN THE PFH PLANT
(Part 8)**

Stream No.	m [lb/hr]	T [F]	P [psia]	H [MMBtu/hr]	S [Mbtu/hrR]	E [MMBtu/hr]
226	364020	100.0	30.0	-92.47	314.93	6474.34
232	231470	100.0	19.5	-58.80	200.26	4116.85
233	231470	107.7	19.5	-58.08	201.54	4116.90
238	246395	100.0	20.0	-62.59	213.17	4382.29
239	16049	100.0	19.5	-4.08	13.88	285.44
254	215422	100.0	575.0	-54.72	186.37	3831.41
260	97348	100.0	100.0	-24.73	84.22	1731.39
261	707763	100.0	20.0	-179.80	612.32	12588.02
262	690516	100.0	14.7	-529.94	597.40	13335.11
267	610415	100.0	20.0	-155.07	528.10	10856.62

Table A-2: HEAT LOSS, POWER SUPPLIED, EXERGY DESTRUCTION FLOW RATE, EXERGY DESTRUCTION RATIO, EXERGY DESTRUCTION TO SHALE EXERGY RATIO, AND EXERGETIC EFFICIENCY FOR PLANT COMPONENTS

COMPONENT	HEAT LOSS [MW]	POWER [MW]	EXERGY DESTR. [MW]	EXD RATIO [%]	EXD/ EShale [%]	EXERG. EFFIC. [%]
1 Preheat	104.00	0.00	34.63	5.46	0.61	21.83
2 Retort	50.59	8.24	104.00	16.39	1.84	97.68
3 Cooling	4.86	0.00	6.79	1.07	0.12	58.43
4 Mixing 1A+2-3	0.00	0.00	3.77	0.59	0.07	99.93
5 Heat Exchanger	0.00	0.00	3.37	0.53	0.06	87.45
6 Gas-Oil Separator	0.00	0.00	0.30	0.05	0.01	100.00
7 Gas Cooler I	0.00	0.00	5.17	0.81	0.09	88.50
8 Knock-Out Drum I	0.00	0.00	0.29	0.05	0.01	100.00
9 Gas Cooler II	0.00	0.00	0.97	0.15	0.02	39.28
11 3-Phase Separator	0.00	0.00	0.08	0.01	0.00	100.00
12 Lean Oil Scrubber	0.77	0.00	0.81	0.13	0.01	99.99
13 Lean Oil Stripper	16.94	1.96	8.13	1.28	0.14	99.58
14 Acid Gas Removal	34.37	0.75	11.41	1.80	0.20	99.81
15 Gas Compressor 31/34	1.22	1.93	0.92	0.15	0.02	52.11
16 Knock-Out Drum III	5.27	0.00	0.48	0.08	0.01	99.92
19 Claus & Scot Units	13.61	1.31	14.76	2.33	0.26	82.96
20 Heavy Oil Flash Drum	18.51	0.00	5.34	0.84	0.09	99.72
21 Hydrogen Recovery	0.00	0.00	14.68	2.31	0.26	99.37
22 Rec. Gas Compr. 82/86	10.05	21.16	7.64	1.20	0.13	63.89
23 Rec. Gas Compr. 84/85	0.00	5.87	1.65	0.26	0.03	71.87
24 Rec. Gas Compr. 94/95	5.10	10.57	4.05	0.64	0.07	61.73
25 Compr. to H2 Plant 92/93	7.63	12.02	4.42	0.70	0.08	63.26
26 Mixing with Nat. Gas	0.00	0.00	0.05	0.01	0.00	100.00
27 Steam Addition 115	0.00	0.00	11.20	1.76	0.20	99.05

Table A-2: HEAT LOSS, POWER SUPPLIED, EXERGY DESTRUCTION FLOW RATE, EXERGY DESTRUCTION RATIO, EXERGY DESTRUCTION TO SHALE EXERGY RATIO, AND EXERGETIC EFFICIENCY FOR PLANT COMPONENTS (Continued)

COMPONENT	HEAT LOSS [MW]	POWER [MW]	EXERGY DESTR. [MW]	EXD RATIO [%]	EXD/ EShale [%]	EXERG. EFFIC. [%]
28 Heat Exchanger 102/103	0.00	0.00	0.95	0.15	0.02	85.52
29 Feed Prod Heat Exchanger	0.00	0.00	5.88	0.93	0.10	78.29
30 Reformer Furnace	0.00	0.00	150.55	23.72	2.66	56.13
31 Quench Water	0.00	0.00	20.44	3.22	0.36	98.52
32 Heat Exchanger 108/109	0.00	0.00	2.42	0.38	0.04	70.65
33 Shift Conversion	0.86	0.00	0.40	0.06	0.01	99.97
34 Heat Exchanger 110/111	0.00	0.00	18.37	2.89	0.32	68.20
35 Knock-Out Drum IV	0.00	0.00	0.00	0.00	0.00	100.00
36 Heat Exchanger 111/112	0.00	0.00	3.73	0.59	0.07	85.40
37 Knock-Out Drum V	0.00	0.00	0.14	0.02	0.00	99.99
38 Absorber/ Regenerator	22.85	1.01	1.21	0.19	0.02	99.90
39 Compr. to Des. & Hydr.	15.92	19.92	9.57	1.51	0.17	51.96
40 Desalting & Hydrotreating	148.71	5.10	74.95	11.81	1.32	98.23
41 Sour Water & NH3 Recover	3.57	3.50	2.94	0.46	0.05	94.66
42 Natural Gas Throttling	0.00	0.00	5.10	0.80	0.09	99.17
43 Fired Heater	0.00	0.00	92.39	14.56	1.63	60.29
44 Air Fan 78/79	0.00	3.85	0.75	0.12	0.01	80.49
45 Sum	464.83	97.19	634.69	100.00	11.21	---
46 Exergy Losses	---	---	113.95	---	---	---
47 Total Plant	464.87	97.19	748.63	---	---	84.86

Table A-3. STEAM GENERATION/CONSUMPTION (Positive values mean steam generation, negative values mean steam consumption)

Component	Heat Transfer [MMBtu/hr]	Mass Flow Rate [lb/hr]
HP STEAM		
Claus & Scot Units 132/133	95.9	93757.1
Reformer Furnace	94.9	130281.5
Heat Exchanger 108/109	44.0	60413.3
Claus & Scot Units 135/136	-28.1	-38587.0
Lean Oil Stripper	-46.7	-64104.9
Heat Exchanger 102/103	-49.3	-67678.3
Totals	110.7	114081.7
LP STEAM		
Heat Exchanger 110/111	428.3	469712.4
Acid Gas Removal	-115.9	-127156.4
Claus & Scot Units 137/138	-19.7	-21592.1
Absorber/Regenerator	-71.9	-78845.7
Totals	220.7	242118.3
FEED WATER PREHEATING		
Gas Cooler I	540.6	1726910.6
COOLING WATER		
Gas Cooler II	68.3	2012316.9
Heat Exchanger 111/112	349.4	304550.9

Appendix B.

DEVELOPMENT OF THERMOECONOMIC FACTORS FOR THE PFH
PLANT BY TENNESSEE TECHNOLOGICAL UNIVERSITY

Tennessee Technological University is conducting an initial thermo-economic evaluation of the PFH plant. The goals of this study are to identify thermodynamic losses, to assist in developing cost-effective solutions to reduce those losses, to improve the understanding of the cost/benefit tradeoffs in the design, and to facilitate future PFH process optimization studies.

The variables to be used for the evaluation of each plant component will be based upon the following variables:

1. The cost of exergy destruction in the k-th system. In this study, this cost will be calculated from the following relationship:

$$\dot{D}_k = c_{F,k} \dot{E}_{D,k} \quad (1)$$

$\dot{E}_{D,k}$ is the rate of exergy destruction in the k-th system and $\dot{D}_k$ represents the cost of the fuel used to cover the exergy destruction in the system.

2. The relative cost difference (d_k) between average cost per exergy unit of product and average cost per exergy unit of fuel is

$$d_k = \frac{c_{P,k} - c_{F,k}}{c_{F,k}} = \frac{\dot{D}_k + \dot{Z}_k}{c_{F,k} \dot{E}_{P,k}} = \frac{1 - \zeta_k}{\zeta_k} + \frac{\dot{Z}_k}{c_{F,k} \dot{E}_{P,k}} \quad (2)$$

This equation reveals the real cost sources in the k-th system, which are (a) the capital costs ($\dot{Z}_k$) and (b) the exergy destruction in the system, as expressed by the first term on the right side of the equation. In general, the higher the relative cost difference d_k , the more attention should be paid to the k-th system.

3. The thermoeconomic factor f_k is

$$f_k = \frac{\dot{Z}_k}{\dot{Z}_k + \dot{D}_k} \quad (3)$$

which expresses the contribution of the capital costs ($\dot{Z}_k$) to the relative cost difference d_k .

4. For the evaluation of heat exchangers from the thermoeconomic viewpoint, the variable r_k defined by

$$r_k = \frac{Z_k}{E_{p,k}} \quad (4)$$

is used in addition to the other variables discussed above. This variable states the capital costs required to transfer a unit of exergy to the cold stream of the heat exchanger.

All these variables will be used to determine the changes in the PFH plant structure or in a design variable (temperature, pressure, etc.) which could lead to a decrease in the costs of the final products.

END

**DATE
FILMED**

9 / 4 / 92