AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910

301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 8

DISTRIBUTION SHEET

To	From	Page 1 of 1
Distribution	Solid Waste Projects	Date 3/21/94
Project Title/Work Order		EDT No. 601084
Advanced Conceptual Design Report, Solid Waste Retrieval Facility, Phase 1, Project W113		ECN No.

Name	MSIN	Text With All Attach.	Text Only	Attach./Appendix Only	EDT/ECN Only
D. E. Ball	G6-46	X			
R. B. Bendixson	H4-70	X			
S. R. Briggs	G6-47	X			
T. L. Erickson	H5-33	X			
✓ R. M. Irwin	T4-03	X			
✓ D. M. Johnson	H5-33	X			
V. P. Ocampo	G6-46	X			
✓ S. L. Peterson	H4-66	X			
✓ K. E. Smith	G6-47	X			
Information Release Administration	A3-36	X			
WRAP DMC	G6-51	X			

Central Files

1804 2

MASTER

2. To: (Receiving Organization) Solid Waste Projects	3. From: (Originating Organization) Solid Waste Projects	4. Related EDT No.:
5. Proj./Prog./Dept./Div.: W-113	6. Cog. Engr.: KE Smith	7. Purchase Order No.:
8. Originator Remarks: This EDT releases the Advanced Conceptual Design Report for Project W-113 to Distribution.		9. Equip./Component No.:
11. Receiver Remarks:		10. System/Bldg./Facility:
		12. Major Assm. Dwg. No.:
		13. Permit/Permit Application No.:
		14. Required Response Date:

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Impact Level	Reason for Transmittal	Originator Disposition	Receiver Disposition
1	WHC-SD-W113-ACDR-001	--	0	Advanced Conceptual Design Report, Solid Waste Retrieval Facility, Phase 1, Project W-113	N/A	2		

16. KEY					
Impact Level (F)		Reason for Transmittal (G)			Disposition (H) & (I)
1, 2, 3, or 4 (see MRP 5.43)		1. Approval	4. Review	1. Approved	4. Reviewed no/comment
		2. Release	5. Post-Review	2. Approved w/comment	5. Reviewed w/comment
		3. Information	6. Dist. (Receipt Acknow. Required)	3. Disapproved w/comment	6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Impact Level for required signatures)										(G)	(H)
Reason	Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN	Reason	Disp.
2	1	Cog.Eng. KE Smith	<i>KE Smith</i>	3/21/94	G6-47						
2	1	Cog. Mgr. SR Briggs	<i>SR Briggs</i>	3/21/94	G6-47						
		QA									
		Safety									
		Env.									
2	1	D.M. Johnson	<i>D.M. Johnson</i>								
2	1	T.L. Erickson	<i>T.L. Erickson</i>								

18. Signature of EDT Originator <i>KE Smith</i> 3/21/94	19. Authorized Representative Date for Receiving Organization _____	20. Cognizant/Project Engineer's Manager <i>SR Briggs</i> 3/21/94	21. DOE APPROVAL (if required) Ltr. No. ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments
--	--	--	---

INSTRUCTIONS FOR COMPLETION OF THE ENGINEERING DATA TRANSMITTAL

(USE BLACK INK OR TYPE)

BLOCK	TITLE	
(1)*	EDT	● Pre-assigned EDT number.
(2)	To: (Receiving Organization)	● Enter the individual's name, title of the organization, or entity (e.g., Distribution) that the EDT is being transmitted to.
(3)	From: (Originating Organization)	● Enter the title of the organization originating and transmitting the EDT.
(4)	Related EDT No.	● Enter EDT numbers which relate to the data being transmitted.
(5)*	Proj./Prog./Dept./Div.	● Enter the Project/Program/Department/Division title or Project/Program acronym or Project Number, Work Order Number or Organization Code.
(6)*	Cognizant Engineer	● Enter the name of the individual identified as being responsible for coordinating disposition of the EDT.
(7)	Purchase Order No.	● Enter related Purchase Order (P.O.) Number, if available.
(8)*	Originator Remarks	● Enter special or additional comments concerning transmittal, or "Key" retrieval words may be entered.
(9)	Equipment/Component No.	● Enter equipment/component number of affected item, if appropriate.
(10)	System/Bldg./Facility	● Enter appropriate system, building or facility number, if appropriate.
(11)	Receiver Remarks	● Enter special or additional comments concerning transmittal.
(12)	Major Assm. Dwg. No.	● Enter applicable drawing number of major assembly, if appropriate.
(13)	Permit/Permit Application No.	● Enter applicable permit or permit application number, if appropriate.
(14)	Required Response Date	● Enter the date a response is required from individuals identified in Block 17 (Signature/Distribution).
(15)*	Data Transmitted	
	(A)* Item Number	● Enter sequential number, beginning with 1, of the information listed on EDT.
	(B)* Document/Drawing No.	● Enter the unique identification number assigned to the document or drawing being transmitted.
	(C)* Sheet No.	● Enter the sheet number of the information being transmitted. If no sheet number, leave blank.
	(D)* Rev. No.	● Enter the revision number of the information being transmitted. If no revision number, leave blank.
	(E) Title or Description of Data Transmitted	● Enter the title of the document or drawing or a brief description of the subject if no title is identified.
	(F)* Impact Level	● Enter the appropriate Impact Level (Block 15). Also, indicate the appropriate approvals for each item listed, i.e., SQ, ESQ, etc. Use NA for non-engineering documents.
	(G) Reason for Transmittal	● Enter the appropriate code to identify the purpose of the data transmittal (see Block 16).
	(H) Originator Disposition	● Enter the appropriate disposition code (see Block 16).
	(I) Receiver Disposition	● Enter the appropriate disposition code (see Block 16).
(16)	Key	● Number codes used in completion of Blocks 15 (G), (H), and (I), and 17 (G), (H) (Signature/Distribution).
(17)	Signature/Distribution	
	(G) Reason	● Enter the code of the reason for transmittal (Block 16).
	(H) Disposition	● Enter the code for the disposition (Block 16).
	(J) Name	● Enter the signature of the individual completing the Disposition 17 (H) and the Transmittal.
	(K)* Signature	● Obtain appropriate signature(s).
	(L)* Date	● Enter date signature is obtained.
	(M)* MSIN	● Enter MSIN. Note: If Distribution Sheet is used, show entire distribution (including that indicated on Page 1 of the EDT) on the Distribution Sheet.
(18)	Signature of EDT Originator	● Enter the signature and date of the individual originating the EDT (entered prior to transmittal to Receiving Organization). If the EDT originator is the cognizant engineer, sign both Blocks 17 and 18.
(19)	Authorized Representative for Receiving Organization	● Enter the signature and date of the individual identified by the Receiving Organization as authorized to approve disposition of the EDT and acceptance of the data transmitted, as applicable.
(20)*	Cognizant Manager	● Enter the signature and date of the cognizant manager. (This signature is authorization for release.)
(21)*	DOE Approval	● Enter DOE approval (if required) by letter number and indicate DOE action.

* Asterisk denote the required minimum items check by Configuration Documentation prior to release; these are the minimum release requirements.

ORIGINAL

Date Received: 4-14-94 CW		INFORMATION RELEASE REQUEST		Reference: WHC-CM-3-4		
Complete for all Types of Release						
Purpose ☐ Speech or Presentation ☐ Full Paper (Check only one suffix) ☐ Summary ☐ Abstract ☐ Visual Aid ☐ Speakers Bureau ☐ Poster Session ☐ Videotape			Reference ☐ Technical Report ☐ Thesis or Dissertation ☐ Manual ☐ Brochure/Flier ☐ Software/Database ☐ Controlled Document ☐ Other			
ID Number (include revision, volume, etc.) WHC-SD-W113-ACDR-001, Rev. 0			List attachments.			
Date Release Required						
Title Solid Waste Retrieval Facility, Phase 1, Project W-113			Unclassified Category UC-721		Impact Level N/A	
New or novel (patentable) subject matter? ☒ No ☐ Yes If "Yes", has disclosure been submitted by WHC or other company? ☐ No ☐ Yes Disclosure No(s).			Information received from others in confidence, such as proprietary data, trade secrets, and/or inventions? ☒ No ☐ Yes (Identify)			
Copyrights? ☒ No ☐ Yes If "Yes", has written permission been granted? ☐ No ☐ Yes (Attach Permission)			Trademarks? ☒ No ☐ Yes (Identify)			
Complete for Speech or Presentation						
Title of Conference or Meeting			Group or Society Sponsoring			
Date(s) of Conference or Meeting		City/State	Will proceedings be published?		☐ Yes ☐ No	
			Will material be handed out?		☐ Yes ☐ No	
Title of Journal						
CHECKLIST FOR SIGNATORIES						
Review Required per WHC-CM-3-4		Yes	No	Reviewer - Signature Indicates Approval		
				Name (printed)	Signature Date	
Classification/Unclassified Controlled Nuclear Information		☐	☒	SW Berglin	<i>[Signature]</i>	4/13/94
Patent - General Counsel		☒	☐	SW Berglin	<i>[Signature]</i>	
Legal - General Counsel		☒	☐			
Applied Technology/Export Controlled Information or International Program		☐	☒			
WHC Program/Project		☒	☐	JA Swenson	<i>[Signature]</i> for JAS	4/8/94
Communications		☐	☒			
RL Program/Project		☒	☐	RE Bley	<i>[Signature]</i>	4/11/94
Publication Services		☒	☐	F. Gray	<i>[Signature]</i> for JAS	4/29/94
Other Program/Project		☐	☒			
Information conforms to all applicable requirements. The above information is certified to be correct.						
References Available to Intended Audience		Yes	No	INFORMATION RELEASE ADMINISTRATION APPROVAL STAMP		
☒		☐	Stamp is required before release. Release is contingent upon resolution of mandatory comments.			
Transmit to DOE-HQ/Office of Scientific and Technical Information		☒	☐
Author/Requestor (Printed/Signature)		Date				
KE Smith <i>[Signature]</i>		4/7/94				
Intended Audience						
☐ Internal ☐ Sponsor ☒ External						
Responsible Manager (Printed/Signature)		Date				
SR Briggs						
Date Cancelled		Date Disapproved				

SUPPORTING DOCUMENT		1. Total Pages <u>7/7</u>
2. Title Advanced Conceptual Design Report, Solid Waste Retrieval Facility, Phase 1, Project W-113	3. Number WHC-SD-W113-ACDR-001	4. Rev No. 0
5. Key Words W-113 Drum Venting Retrieval NDE/NDA Overpacks Gas Sampling Trench Enclosure	6. Author Name: KE Smith <i>KE Smith</i> Signature Organization/Charge Code W24950/A8114	
7. Abstract Project W-113 will provide the equipment and facilities necessary to retrieve suspect transuranic (TRU) waste from Trench 04 of the 218W-4C burial ground. The ACDR documents studies performed during FY93 to optimize the equipment and facilities provided in relation to other SWOC facilities and to provide additional design information for Definitive Design.		
8. PURPOSE AND USE OF DOCUMENT - This document was prepared for use within the U.S. Department of Energy and its contractors. It is to be used only to perform, direct, or integrate work under U.S. Department of Energy contracts. This document is not approved for public release until reviewed. PATEM STATUS - This document copy, since it is transmitted in confidence of patent clearance, is made available in confidence solely for use in performance of work under contracts with the U.S. Department of Energy. This document is not to be published nor its contents otherwise disseminated or used for purposes other than specified above before patent approval for such release or use has been secured, upon request, from the Patent Counsel, U.S. Department of Energy Field Office, Richland, WA. DISCLAIMER - This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.		10. RELEASE STAMP <div style="border: 1px solid black; padding: 5px; text-align: center;"> OFFICIAL RELEASE (23) BY WHC DATE JUN 13 1994 <i>Ita #10</i> </div>
9. Impact Level N/A		

APPROVED FOR
PUBLIC RELEASE
ew
4/29/94

WHC-SD-W113-ACDR-001
Rev. 0
Page i

ADVANCED CONCEPTUAL DESIGN REPORT
SOLID WASTE RETRIEVAL FACILITY, PHASE 1
Project W-113

TABLE OF CONTENTS

<u>Title</u>	<u>Page</u>
1.0 Introduction	i
2.0 Summary	i
3.0 Advanced Conceptual Design Studies	2
3.1 Drum Venting and Head Gas Sampling System (Appendix A)	2
3.2 Waste Characterization (Appendix B)	2
3.3 Trench Weather Enclosure Key Drivers (Appendix C)	2
3.4 Solid Waste Projects Nondestructive Assay/ Nondestructive Examination Review (Appendix D)	3
3.5 NDE/NDA Equipment Design Requirements (Appendix E)	3
3.6 Box Overpack Design Criteria (Appendix F)	4
3.7 Support Building Consolidation (Appendix G)	4
3.8 ACDR Cost Estimate (Appendix H)	4
4.0 Impacts of Advanced Conceptual Studies on Project Design	4
5.0 Outstanding Issues	5
5.0 References	6
Appendix A	7
Appendix B	74
Appendix C	463
Appendix D	498
Appendix E	526
Appendix F	552
Appendix G	572
Appendix H	578

ADVANCED CONCEPTUAL DESIGN REPORT
SOLID WASTE RETRIEVAL FACILITY, PHASE 1
Project W-113

1.0 INTRODUCTION

Project W-113 will provide the equipment and facilities necessary to retrieve suspect transuranic (TRU) waste from Trench 04 of the 213-W-4C burial ground. As part of the retrieval process, waste drums will be assayed, overpacked, vented, head-gas sampled, and x-rayed prior to shipment to the Phase V storage facility in preparation for receipt at the Waste Receiving and Processing Facility (WRAP).

A Conceptual Design Report (CDR) (WHC-SD-W113-CDR-002, Rev.0) was completed in September of 1992 which outlined the equipment and facilities necessary to retrieve the wastes and provided project cost and schedule baselines. After completion of the CDR, a number of items were identified that warranted further investigation and presented potential opportunities for cost savings. An Advanced Conceptual Design Workplan (WHC-SD-W113-WP-001) was written to document the studies to be performed prior to starting definitive design. Studies which were completed during FY93 include the following:

1. Drum Venting and Head Gas Sampling System
2. Waste Characterization
3. Trench Weather Enclosure Key Drivers
4. Solid Waste Projects Nondestructive Assay/Nondestructive Examination (NDE/NDA) Review
5. NDE/NDA Equipment Design Requirements
6. Box Overpack Design Criteria
7. Support Building Consolidation

This Advanced Conceptual Design Report (ACDR) provides a brief summary of these studies and their impacts to the conceptual design. The full text of each study is found in the Appendices. Also included is a revised project cost estimate reflecting modifications to the conceptual design based on the results and recommendations of the studies and based on changes made to the Functional Design Criteria (FDC) via revision 2.

2.0 SUMMARY

Advanced Conceptual Design (ACD) studies focused on project items warranting further definition prior to Title I design and areas where the potential for cost savings existed. A review of the W-113 NDE/NDA design with respect to the other Solid Waste Operations Complex (SWOC) facilities resulted in a significant reduction in the NDE/NDA equipment and deletion of the NDE/NDA facility required for Project W-113. Other studies covering the box overpack design criteria and support building sizing recommended changes that will yield substantial cost savings. In addition to cost saving design changes, important design detail was established in reports on the drum venting system and the NDE/NDA equipment. A revised project cost estimate reflecting the changes

recommended by the ACD studies, along with changes resulting from a revision to the FDC, shows an \$8.3 million dollar reduction in total estimated cost.

3.0 ADVANCED CONCEPTUAL DESIGN STUDIES

3.1 Drum Venting and Head Gas Sampling System (Appendix A)

The Drum Venting and Head Gas Sampling System Engineering Study (WHC-SD-W113-ES-003) was performed to define system requirements, review venting systems of other Department of Energy (DOE) sites, define system development tasks, and recommend an implementation method for definitive design. The existing Westinghouse Hanford Company (WHC) Container Venting System (CVS) developed for the pilot retrieval effort was reviewed for application to W-113, as well as venting designs at Idaho National Engineering Laboratory (INEL) and Los Alamos National Laboratory (LANL). The study recommends the existing Hanford CVS equipment be retrofitted as required to gain on-line gas sampling capability and to permit automatic drum filter installation. The retrofitted system will be tested for reliability, operability, and maintainability with test results feeding the definitive design equipment performance specification. Final equipment design and fabrication will be based on this performance specification.

3.2 Waste Characterization (Appendix B)

The Waste Characterization study is a compilation of existing data and information on waste sources, dose rates, fissile loadings and locations of the drums and boxes in Trench 04. This information will be useful in determining shielding requirements, performing safety analyses and criticality assessments, and planning retrieval operations. The majority of data was extracted from the Solid Waste Information and Tracking System (SWITS) data base, burial records, and burial ground drum location sheets. A description of each trench module was prepared that consists of a summary sheet outlining significant contents of the module, color-coded representations of each tier within the module, and selected burial records representative of the data available from the waste generators.

3.3 Trench Weather Enclosure Key Drivers (Appendix C)

In response to an Independent Cost Estimate (ICE) review concern regarding the necessity for weather protection during retrieval, a study was initiated to examine the key drivers for weather protection and determine whether adequate justification exists to retain the enclosure in the project design. Los Alamos Technical Associates (LATA) examined the regulatory, safety, production, and economic drivers associated with the enclosure, and concluded that while regulatory and safety considerations are not justifiable drivers, production and economic drivers do justify weather protection at a life cycle cost of \$1,850,000. The life cycle

cost value was calculated by comparing year round retrieval costs without an enclosure, which included work stoppage due to weather interruptions, to retrieval costs with an enclosure. Winds above 15 mph, temperatures below 35°F and above 100°F, and measurable precipitation were used as conditions which would stop the retrieval operations. The study also concluded that a weather enclosure mitigates production risk by minimizing the impact of inclement weather that is worse than normal.

The cost of the trench enclosure included in the CDR exceeds the \$1.85M benefit level, primarily due to the HEPA filtration, negative air pressure capability, airlocks, and foundation suitable for a gantry crane. As these criteria are being removed in the FDC Revision 2 (see Section 4.0), it is believed that an enclosure which focuses on the functional requirements of weather protection can be procured within the life cycle cost figure.

3.4 Solid Waste Projects Nondestructive Assay/Nondestructive Examination Review (Appendix D)

A letter report was prepared to review the NDA/NDE functions of each facility within the SWOC to determine where gaps exist between requirements and capabilities and where duplications or unnecessary capabilities exist. With regard to Project W-113, the report recommends that the fixed NDE/NDA facility be eliminated in favor of mobile NDE/NDA equipment located in the trench. Since the present scope includes retrieval from only a single trench, the expense of a permanent NDE/NDA facility could not be justified. In addition, the report recommends the deletion of the gamma energy analysis (GEA) assay equipment from the retrieval project based on the passive-active neutron (PAN) assay's capability to provide the required information to meet the drum shipping criteria as well as WRAP 1 incoming waste requirements. Justification for retaining the retrieval-based real time radiography (RTR) equipment is based on meeting RCRA storage waste characterization criteria and WRAP 1 safety documentation requirements for waste entering the facility.

3.5 NDE/NDA Equipment Design Requirements (Appendix E)

Based on the results of the NDE/NDA examination review discussed in 3.4 above, the project functional design criteria (FDC) was revised to include a PAN assay system to perform TRU/LLW waste segregation and confirm gram loadings are within the drum shipping limitations and RTR equipment to provide preliminary characterization sufficient to meet acceptance criteria for the storage and WRAP 1 facilities. Detailed design requirements for this equipment were documented in this study in support of the W-113 Supplemental Design Requirements Document (SDRD). Since this equipment will be similar to the WRAP 1 NDE/NDA equipment, much of the study was taken from the work already completed on the WRAP 1 design. The study includes equipment safety requirements, system control and interface requirements, detection capabilities, and shielding and throughput requirements.

3.6 Box Overpack Design Criteria (Appendix F)

The purpose of the box overpack design criteria document is to provide criteria for the analysis and design of packaging for the transport of retrieved metal boxes and 110-gallon drums from the trench to the interim storage facility. This criteria will be used for developing an appropriate procurement and/or design specification. The materials of construction, fabrication methods, packaging dimensions, weights, containment requirements, and testing requirements are detailed in the study. While the box overpacks are not required to be certified by the NRC or DOE as Type B packages per 10 CFR 71, an equivalent degree of safety must be demonstrated as required by RL Order 5480.1. A concerted effort was made to realistically assess the normal conditions of transport anticipated from the retrieval trench to Phase V storage to minimize overpack costs while still satisfying prescriptive requirements.

3.7 Support Building Consolidation (Appendix G)

ICF Kaiser Hanford Company revisited the conceptual design of the general office building and change building based on FDC changes which reduced the number of personnel working in the retrieval operations. Recommendations included combining the lunch/conference area of the two buildings and reducing the size of the change building. The study recommended that both buildings be sized such that double wide trailers (28'w x 60'l) can be used, which facilitates movement of these buildings to future trenches. Recommended sizing of the trench operations support building was deferred until Title I design when placement of the NDE equipment will be determined.

3.8 ACDR Cost Estimate (Appendix H)

Cost Estimate

4.0 IMPACTS OF ADVANCED CONCEPTUAL STUDIES ON PROJECT DESIGN

A number of project design modifications are proposed based on the results of the ACD studies and reports. Included are the following:

1. Deletion of the NDE/NDA Building and conversion of the NDE/NDA equipment to mobile systems operating in the trench.
2. Reduction in the quantity of NDE/NDA equipment from two process lines to a single line and deletion of the drum gamma energy analysis equipment and box assay equipment.
3. Resizing of the retrieval staff change building to a double wide trailer.
4. Simplification of the box overpack design.

Further changes to the project conceptual design are proposed as a result of a post-CDR revision (Rev. 2) to the Functional Design Criteria. Included are the following:

1. Removal of HEPA filtration and negative pressure capability from the trench enclosure. The 6430.1A leak tightness requirement previously referenced in the FDC was inappropriate; the intent is to convey a nominal degree of tightness against rain, snow and blowing dust. Further, based on the Preliminary Safety Evaluation and subsequent evaluations of specific operational accident scenarios, it has been determined that there is no nuclear safety driver for any form of confinement or containment. The dual ventilation exhausters with HEPA filters and the airlocks can be deleted from the conceptual design.
2. Deletion of the truck scales for box weighing. Box weights are recorded for all Trench 04 boxes on the respective burial records. With the deletion of the central NDE/NDA facility, the truck scales (if required for future retrieval or other purposes) should be located at or near a more central facility, such as Phase 5 storage.
3. Adding a second drum venting machine due to the retrieval rate increasing from 8 drums/day to 16 drums/day. A second venting machine will be necessary to meet the higher daily throughput requirements.
4. Replacing the trench enclosure gantry crane with a diesel forklift for box removal only. A safety analysis showed that use of a diesel-powered forklift to handle boxes would not present an unacceptable risk. The forklift will be restricted to box handling only and have limited fuel on board. This change represents a cost savings by eliminating the large foundation required by the gantry crane and allowing the option to delete the sheet piling in favor of sloping the trench walls.
5. Adding an electric motor operated jib crane or similar equipment for removing drums from the modules. With the deletion of the gantry crane, the less expensive jib crane will be used for lifting drums from the modules to the trench floor.

A revised project cost estimate (Appendix H) has been prepared that reflects the changes noted above. The total estimated project cost has been reduced from \$28.4 million to \$20.2 million.

5.0 OUTSTANDING ISSUES

A Value Engineering session was held during FY93 to review the trench enclosure building and the method of removing drums and boxes from the trench. Recommendations from the session included excavating the soil along the drum sides to the required angle of repose in place of using sheet piling and considering a fabric structure spanning the excavated trench width in lieu of a pre-engineered building. The final

determination on the type of trench enclosure (pre-engineered metal building vs. fabric over metal frame structure), the optimum length of the enclosure, and the most cost effective shoring method will be made during Title I design.

Another issue potentially affecting the project cost relates to the ongoing construction/procurement of the WRAP 1 facility and equipment. Initial construction proposals received for WRAP 1 exceeded the construction budget. One recovery plan entails deleting the NDE/NDA equipment from WRAP 1 that is dedicated to final certification of the retrieved wastes. As the need for this equipment is tied to the retrieved wastes, Project W-113 would supply the equipment for installation at the WRAP 1 facility at the time the retrieval facilities are constructed. In this way, WRAP 1 would not be providing equipment that may not be necessary should the retrieval project be delayed or canceled. If this recovery plan is implemented, the W-113 total estimated cost would increase by about \$3.0 million.

6.0 REFERENCES

KEH, 1992, "Project W-113, Solid Waste Retrieval Facility, Phase 1 Conceptual Design Report," WHC-SD-W113-CDR-002, Kaiser Engineers Hanford, Richland, Washington

Smith, K.E., 1992, "Advanced Conceptual Design Workplan, Project W-113 - Solid Waste Retrieval Facility Phase 1," WHC-SD-W113-WP-001, Westinghouse Hanford Company, Richland, Washington

Johnson, D.M., 1993, "Functional Design Criteria, Solid Waste Retrieval Facility Phase 1, Project W-113," WHC-SD-FDC-001 Revision 2, Westinghouse Hanford Company, Richland, Washington

APPENDIX A

Project W-113 Drum Venting
and Head Gas Sampling Systems Engineering
(Reference WHC-SD-W113-ES-003, Rev. 0)

THIS PAGE INTENTIONALLY LEFT BLANK

CONTENTS

1.0	OBJECTIVE	10
1.1	SCOPE	10
1.2	BACKGROUND	10
1.3	PURPOSE AND NEED	11
2.0	SUMMARY	11
2.1	DEFINITION OF SYSTEM REQUIREMENTS	11
2.2	REVIEW OF EXISTING CVS DESIGNS	12
2.2.1	WHC Pilot Retrieval Demonstration Project	12
2.2.2	Idaho National Engineering Laboratory (INEL)	13
2.2.3	Los Alamos National Laboratory (LANL)	13
2.2.4	WHC Project W113 CVS Conceptual Design	14
2.2.5	Other WHC Drum Venting/Opening Activities	14
2.3	DEFINITION OF DEVELOPMENTAL TASKS	15
2.4	IMPLEMENTATION OF DEFINITIVE DESIGN	16
3.0	RECOMMENDATIONS	17
3.1	WHC PILOT RETRIEVAL CVS MODIFICATIONS	17
3.2	HYDROGEN GAS MONITORING INSTRUMENTATION	17
3.3	VOCs GAS ANALYZERS	19
3.3.1	VOCs Continuous Gas Monitor	19
3.3.2	Gas Chromatograph	20
3.4	GAS MIXTURES FLAMMABILITY TEST	21
3.5	VENT GASES MONITORING INSTRUMENTATION	22
3.5.1	Stack Gas Sampling	22
3.5.2	Radionuclides Monitoring	22
3.5.3	Record Sample Filter Analysis	22
3.5.4	Workplace Monitoring	22
3.6	DRUM HANDLING SYSTEM INTERFACE SAFETY ISSUES	23
4.0	UNCERTAINTIES	23
5.0	DISCUSSIONS	25
5.1	DISCUSSION OF SUBSYSTEMS FUNCTIONAL REQUIREMENTS	25
5.1.1	VOCs Gas Sample Transport Lines	25
5.1.2	Hydrogen Gas Monitoring System	25
5.1.3	Drum VOC Gases Sampling System	26
5.1.4	Drum Vent Gas System	26
5.1.5	Drum Purging System	27
5.1.6	Drum Gas Mixtures Flammability Testing	28
5.1.7	Drum filter and Method of Installation	28
5.1.8	Gas Sampling/Analysis Room	28
5.1.9	NEC Hazardous Area Classification	28
5.1.10	NFPA 77 Guidelines: Prevention of Static Electricity Generation	29
5.1.11	WHC Safety Classification	29
5.1.12	Process Control Logic	30
5.2	ASSUMPTIONS USED	32
5.3	DISCUSSION OF ALTERNATIVE HYDROGEN & VOCs GAS ANALYSIS INSTRUMENTATION SYSTEM	34
5.3.1	WHC SAS Instrumentation Proposal	34
5.3.2	Combined Gas Chromatograph/Mass Spectrometer	36

6.0	REVIEW OF CVS EQUIPMENT DESIGNS	37
6.1	WHC PILOT RETRIEVAL DEMONSTRATION PROJECT CVS EQUIPMENT . . .	37
6.2	IDAHO NATIONAL ENGINEERING LABORATORY (INEL)	41
6.3	LOS ALAMOS NATIONAL LABORATORY (LANL)	42
6.4	WHC PROJECT W-113 CVS CONCEPTUAL EQUIPMENT DESIGN	42
6.5	SAVANNAH RIVER LABORATORY (SRL)	43
7.0	DISCUSSION OF ALTERNATIVE SYSTEMS	43
7.1	WHC PILOT RETRIEVAL CVS "AS-IS" DESIGN	43
7.2	WHC PILOT RETRIEVAL CVS "MODIFIED" DESIGN	44
7.3	WHC ONSITE MOBILE "GRAB SAMPLE" ANALYTICAL LABORATORY	44
8.0	REFERENCES	45
	APPENDIX A: SKETCHES	46
	APPENDIX B: CALCULATIONS	61
	APPENDIX C: ENGINEERING DEVELOPMENT WORK ESTIMATES	63
	APPENDIX D: OTHER DATA	64

PROJECT W-113 DRUM VENTING AND HEAD GAS SAMPLING SYSTEM

1.0 OBJECTIVE

1.1 SCOPE

The scope of this Project W-113 engineering study with respect to the drum venting and head gas sampling system will include:

1. definition of system requirements
2. discussion of WHC/other DOE sites existing systems
3. definition of system developmental tasks
4. method of implementation of definitive design

1.2 BACKGROUND

Project W-113 will retrieve solid waste drums suspected of containing transuranic (TRU) radionuclide material in Trench 4C-04 of the 200W burial grounds. The retrieval, drum venting and head gas sampling process as described in the following paragraphs represents the system as described in the Conceptual Design Report, WHC-SD-W-113-CDR-002, Rev.0. It is subject to modification and change of operational sequence, none of which would have negative impact on the drum venting and head gas sampling system.

After the overburden is removed from one module of drums, a portable shoring will be installed to prevent the pile from falling, should a design basis earthquake (DBE) or an accident occur during waste retrieval. A gantry crane with a drum grappling attachment will be used to remove drums from the pile. The drums will be inspected by a person in the aerial platform prior to attaching the grapple to a drum. The gantry crane will then remove the drum from the module for further inspection, bar code application, and insertion into an 85 gallon overpack drum.

The overpacked 55-gallon drum with its top exposed will be placed inside a heavy-walled venting enclosure, that will mitigate the effects of any drum explosion, should it occur during the drum venting and head gas sampling operation. The drum venting and head gas sampling equipment will then puncture the top of the 55-gallon waste drum, perform an on-line gas analysis, and grab one gas sample for archive purposes. Then the drum will be purged with nitrogen gas as required and a filter will be installed.

After removal from the sampling station, a similar filter will also be installed on overpack drum lid. The overpacked 55-gallon drum will then be placed on a trailer by the crane or a forklift for further processing. It is expected to process one (1) drum per hour, assuming the drum VOCs concentration exceeds 600 ppm. Processing time could be two (2) drums per hour, assuming the drum VOCs concentration is less than 500 ppm. There is a small number of boxes and other containers that will not be vented or sampled for flammable gases or VOCs and existing characterization shows no mixed waste in these containers.

1.3 PURPOSE AND NEED

The purpose of this engineering study is to define the performance requirements, operations, maintenance, safety and environmental concerns, etc. of the drum venting and head gas sampling equipment for use in Project W-113, Phase I and Phase II retrieval.

There is a need to define the equipment design requirements and system interfaces to a level of detail that WHC central engineering or an off-site A/E can use to initiate definitive design of the drum venting and head gas sampling equipment. NOTE: A CVS System Hazard Analysis Report shall be completed in time for the Project W-113 to incorporate findings of the analysis in the Project W-113 CVS equipment requirements and interfaces. Also, the completion of the CVS development to meet Project W-113 needs should be accomplished by an integrated efforts by W-113 projects with WHC Central Engineering and Solid Waste Management.

The following equipment design requirements and system interfaces will require an in-depth analysis as discussed in this engineering study report:

1. Equipment design requirements on the following:
 - a. on-line hydrogen gas monitor
 - b. on-line VOCs gas mixtures monitor/analyzer
 - c. VOCs gas mixtures flammability test equipment
 - d. sampling, controlling, monitoring and disposal of the drum vent gases
2. Design interface requirements on the following:
 - a. the drum handling equipment
 - b. the drum filter and method of installation on the drum lid
 - c. the overall process control logic
 - d. the non-sparking drum head penetrator (punch, drill or rotary saw)
 - e. the inert gas purging system
 - f. the drum venting enclosure
3. Additional design features required based on the following:
 - a. the NEC hazardous area classification
 - b. the NFPA 77 guidelines for the prevention of static electricity generation
 - c. WHC Safety Class 2 classification

2.0 SUMMARY

2.1 DEFINITION OF SYSTEM REQUIREMENTS

The following are the basic drum venting and head gas sampling system functional requirements per WHC-SD-W113-FDC-001, that should be followed in the definitive design:

1. It shall have the capabilities for venting and purging the 55-gallon drums within the 85-gallon overpack drums, collecting discrete gas samples for archiving, analyzing the gas samples on a real time basis and controlling air emissions for both hazardous and radionuclide constituents.

2. After the inert gas purging, a filter shall be automatically installed in the drum lid, which will provide adsorption of volatile organic compounds and particulates but will permit the passage of hydrogen and other inorganic gases.
3. Data obtained during the gas sampling will be processed into a waste management data base. Additionally, hard copies of the data will be provided with the transfer of the overpacked 55-gallon drums. **NOTE:** Coordinate with the data management study.
4. It shall be in an enclosure with the capability of preventing the release of radioactive material/fire and personnel injury in the worst case of a drum explosion during the venting operation.
5. The following structure/system/component associated with the drum and head gas sampling system are to be designed based on the following WHC Safety Class designations:
 - a. enclosure for venting drums.....Safety Class 2
 - b. drum venting equipment.....Safety Class 2
 - c. VOCs gas sampler.....Safety Class 3
 - d. gantry crane.....Safety Class 3, qualified to Safety Class 2
 - e. trench enclosure building.....Safety Class 3, qualified to Safety Class 2
6. The design shall incorporate maintainability techniques such as the following:
 - a. access for visual inspection
 - b. provisions for in-place adjustment, repair, or replacement of defective part or subsystem equipment components
 - c. use of standard tools for maintenance

2.2 REVIEW OF EXISTING CVS DESIGNS

There are several existing designs of the Container Venting System (CVS) equipment from WHC and other DOE sites which have some design features suitable for use in Project W-113. However, these design features are not all available in one existing design due to the different operating conditions on each DOE sites. Each of the designs will require some modifications in order to meet Project W-113 specific requirements.

2.2.1 WHC Pilot Retrieval Demonstration Project

NOTE: Refer to Appendix A, Sketches #11 and #12, from Reference Material, SRL-MNT-91373.

Some of the design limitations are:

1. Presently, there is no provision for the following: **NOTE:** Pilot Retrieval Project do have plans to incorporate Items 1(a), 1(b), 1(c), 1(d) and Item (#2) at a later date. However, Items 1(e) and 1(f), per the Pilot Retrieval Project requirements are satisfactory for their project.
 - a. on-line analysis of the drum head gas
 - b. sampling, monitoring and disposal of drum vent gases
 - c. hydrogen gas monitoring
 - d. gas mixtures flammability testing
 - e. automatic installation of the drum lid filter
 - f. heavy-walled enclosure for containing explosion hazards

2. Only one (1) gas sample port is used for the sequential operation of the gas sampling, venting and purging process.
3. The drilling bit produces metal chips which could possibly block/contaminate the vacuum lines.
4. The drum piercing assembly can be used only to lift vertically stored drums.
5. The drum piercing assembly clamping on lifting corroded or damaged drums could present some problems.
6. There is a chance of contaminating exterior of drum when piercing tool is removed from drum.

Some of the good design features are:

1. Portability.
2. The drum piercing assembly is also used as a lifting device for removing drums from storage location.

2.2.2 Idaho National Engineering Laboratory (INEL)

NOTE: Refer to Appendix A, Sketches #4, #5 and #6, from Reference Material, SRL-MNT-91373.

Some of the design limitations are:

1. Hydraulic fluid leakage may cause cleanup problems.
2. Uses a much larger drum venting enclosure.
3. Only one (1) gas sample port is used for the sequential operation of the gas sampling, venting and purging process.
4. The drum exterior may become contaminated when the head punch is removed.
5. Proper alignment needs to be maintained for the head punch and the filter insertion head.
6. When the head punch and the filter insertion head change position the seal on the penetrated drum is not maintained.
7. Presently, there is no provision for the following:
 - a. gas mixtures flammability testing
 - b. on-line analysis of the drum head gases

Some of the good design features are:

1. 15,000 drums as of FY 91 have been vented by INEL with this drum venting system.
2. The drum filter used is already DOT qualified.
3. Filter insertion is done automatically under precision control.

2.2.3 Los Alamos National Laboratory (LANL)

NOTE: Refer to Appendix A, Sketches #7, #8, #9 and #10, from Reference Material, SRL-MNT-91373.

Some of the design limitations are:

1. Presently, there is no provision for the following:
 - a. on-line analysis of the drum head gas

- b. sampling, controlling, monitoring and disposal of drum vent gases to the environment
 - c. hydrogen gas monitoring
 - d. gas mixtures flammability testing
 - e. heavy-walled enclosure for containing explosion hazards
2. Only one (1) gas sample port is used for the sequential operation of the gas sampling, venting and purging process.
3. It does not use an already DOT qualified drum filter.

Some of the good design features are:

1. Contamination of the drum exterior is minimized because piercing tool is never removed from the drum.
2. With the filter built-in to the punch head, the seal on the drum is maintained throughout the entire operation.

2.2.4 WHC Project W113 CVS Conceptual Design

NOTE: Refer to Appendix A, Sketch #14, from Reference Material, WHC-SD-W113-CDR-002.

Some of the design limitations are:

1. Presently, there is no provision for the following:
 - a. clamping and sealing cylinders to assure a good vacuum seal
 - b. aftercooler or an instrument air dryer on the compressed air system to assure instrument air quality is provided
 - c. sealing gasket on the detachable head punch to assure a good vacuum seal
2. An operator is still required after each process cycle to manually:
 - a. replace the filter
 - b. replace the detachable head punch
3. A prefabricated detachable head punch is required to be made for each drum.
4. Proper alignment needs to be maintained for the punch tool head and the filter insertion head.
5. It does not use an already DOT qualified drum filter.

Some of the good design features are:

1. It is trailer-mounted for portability.
2. Contamination of the drum exterior is minimized because piercing tool is never removed from the drum.

2.2.5 Other WHC Drum Venting/Opening Activities

Project W-113 recommends the use of the Pilot Retrieval Project prototype CVS equipment as a demonstration equipment for evaluation with WHC drum venting/opening activities at Hanford: 183-H Basin Drums at CWC, HAZMAT Response Team Venting of Bulged, Laundry Opening of PEDF Problem Drums, Backlog Drums Opening at T-Plant and Inspection and Repackaging Unit for CWC. It will give a better actual on-site experience to document the hazard analyses and integration study of existing approaches/equipment used by WHC for venting solid waste containers.

The conditions, safety approach and equipment based on the demonstration testing in the shop of the Pilot Retrieval Project CVS needs to be compared to the listed WHC activities. The two (2) key conditions for using it are existing: the drums are there and the prototype CVS is just about ready for operational testing.

2.3 DEFINITION OF DEVELOPMENTAL TASKS

The engineering development task during Title I design that will be required to determine their reliability, operability and maintainability with respect to the specific requirements of Project W-113 are:

- a. mockup and testing of the recommended instrumentation systems
- b. mechanical design of the drum penetrator and filter

It will make use of the existing WHC pilot retrieval demonstration project CVS equipment retrofitted as required for the mockup and testing of the recommended instrumentation systems. **NOTE:** The CVS equipment should be made available to the Project W-113 in 1994 for the required retrofits.

The following work elements will be part of the development tasks efforts: **NOTE:** See Appendix C, Engineering Development Cost Estimates, for the information regarding cost and schedules for design, development and procurement for Project W-113.

1. Develop an overall P & ID of the drum venting and head gas sampling into an H-2-XXXXX drawing which will serve as the design control point of the engineering development task.
2. Develop the engineering design of the drum venting penetrator (drill, punch, or rotary saw) best suited to accomplish drum lid penetration because of the following operational requirements and uncertainties:
 - a. Some drum lids might have corroded to the point that a clean cut hole cannot be made into the drum lid.
 - b. The screwed-in type filter should be easily installed and seal tight on the drum hole created by the drum penetrator.
 - c. The non-sparking aspect of the method of drum penetration is a critical requirement which will require that the drum lid penetrator material of construction be non-sparking. However, commercially available non-sparking materials such as Ampco metal, beryllium copper, manganese bronze or aluminum alloys are not normally used for off-the-shelf drills, punches, or rotary saws. **NOTE:** The commercial coating material used for drill bits is to harden the drill bit to maintain sharpness which will keep the drill bit temperature low, but not for non-sparking applications.
3. Develop the engineering design of the filter and method of installation best suited to accomplish the following operational requirements and uncertainties:
 - a. Project W-112 will require to get another head gas sample without removing the filter installed in Project W-113.

- b. WRAP 1 will require that the filter installed in Project W-113 installed on the drum lid will not interfere with the drum handling equipment used for the gloveboxes.
- c. Project W-113 requires that the filter shall provide adsorption of volatile organic compounds but will allow the passage of hydrogen and other inorganic gases. Since the inert gas proposed to be used is also an inorganic gas, it has to be determined if sufficient purging gas is being released while at the same time hydrogen or volatile organic compound gases are being regenerated. This may require that there is total evacuation of the drum head gases prior to nitrogen purging to assure that the drum is still completely purged, even there is loss of inert gas through the filter.
- 4. Develop H-2-XXXXX drawings for the fabrication and assembly required for the engineering design developed in Item #2 and #3 for the drum penetrator and filter.
- 5. Procurement of the instrumentation systems is required for component testing to verify their performance with respect to accuracy, repeatability, sensitivity and temperature stability, since there is no guarantee that drum head gases of the drum next to be vented and sampled will be similar to the preceding drum that was just vented and sampled.

NOTE: Repeatability is defined as the closeness with which an analyzer repeats indications when measuring identical values of the measured variable under the same conditions.

Sensitivity is defined as the smallest change in a variable capable of causing a measurable corresponding change in the output signal.

Also, there is a need to verify simplicity or complexity of the calibration procedure, corrosion resistance and the sample conditioning system of the instrumentation system.

- 6. Shop fabrication and assembly is required for the mockup and testing required to verify system performance.
- 7. Mockup and testing is required to verify overall system performance measured against the Project W-113 requirements specifically to the time required to process one (1) drum.
- 8. Test results report/recommendations will be required to document and incorporate deficiencies and improvements noted during the mockup and testing to be incorporated in the definitive design.
- 9. Performance specification documentation is required for the definitive design and fabrication of the CVS for Project W-113 use.

2.4 IMPLEMENTATION OF DEFINITIVE DESIGN

The recommended method of implementation of definitive design is to use existing CVS mechanical designs modified to suit Project W-113 specific requirements and to procure and assemble the recommended instrumentation systems required for mockup and testing. The drum venting and head gas sampling equipment will then be tested as a whole system to ensure its

reliability, operability and maintainability prior to definitive design and fabrication.

The results of the system mockup and testing will supplement the definitive design requirements. Then, a performance specification will be written for the definitive design and fabrication of the equipment. It is recommended that the equipment be a WHC design and built for Project W-113 use.

3.0 RECOMMENDATIONS

3.1 WHC PILOT RETRIEVAL CVS MODIFICATIONS

NOTE: Refer to Appendix A, Sketch # 1 for the System Process Diagram and Section 6.1, for other recommended design modifications.

NOTE: See Appendix C, Engineering Development Work Estimates for using the recommended HNU instrumentation systems. Engineering development work cost estimate is \$174,000.00 and activities will be from October 1992 to April 1996.

1. Remove the following solenoid valves:
 - a. sample valve (SV-2)
 - b. reference valve (RV-1)
 - c. vent valve (VV-1)
2. Add/modify the following new process lines:
 - a. a purge line from the inert gas cylinders valving manifold to the drum head
 - b. a gas recirculating line from the on-line gas analyzing system vent to the drum piercing containment enclosure
 - c. a vacuum line from the vent gases record sampling manifold to the intake line of the vacuum pump
 - d. the gas vent line will be extended up to the inlet duct of the thick-walled enclosure exhaust fan, upstream of the venting enclosure's exhaust stack's filtering system
3. Add the following solenoid valves:
 - a. sample return valve (SV-4)
 - b. sample vent valve (SV-5)
 - c. sample bypass valve (SV-3)
 - d. gas chromatograph inlet valve (SV-2)
4. Add one (1) extra inert gas cylinder.
5. Add trailer-mounting of the equipment for portability.
6. Modify the CVS control panel graphics.

3.2 HYDROGEN GAS MONITORING INSTRUMENTATION

An electrochemical hydrogen monitoring system which provides primary monitoring for hydrogen concentration in percent of volume is recommended to be used. The system components are: **NOTE:** Refer to Appendix A, Sketch #2 for the System Block Diagram.

1. **% Hydrogen Sensor:** The hydrogen sensor/cell is an electrochemical type cell that generates an electrical signal as a function of gas partial pressure. This millivolt signal is then converted by the electronics to a visual and electrical indication in volume percent.
2. **% Hydrogen Transmitter:** A programmable transmitter accepts the mV output signal from the sensor and provides an analog 4-20 mA dc output signal to a strip chart recorder for local recording and to a terminal block for remote data acquisition access. The percent volume concentration of hydrogen is digitally displayed.
3. **Intrinsic Safety Barrier:** An intrinsic safety barrier is installed between the electrochemical cell and the indicating transmitter to limit any voltage or current reaching the electrochemical cell due to an electrical failure in the % hydrogen transmitter.

An 800 Series monitoring system, manufactured by Whittaker Electronic Resources Division, consisting of the following components is recommended to be used:

- a. a panel mounted signal conditioning unit
- b. a surface mounted hydrogen sensor assembly with 1/4 NPT inlet and outlet ports and 1/4 inch tube stub for the calibration gas inlet
- c. a pressure transducer 1/4 NPT threads for installation into the sample stream piping

Some of the maintenance and serviceability features are:

- a. calibration frequency: once every 90 days
- b. sensor operating life: one (1) year

ADVANTAGES

1. Hydrogen monitoring is made inherently safe by:
 - a. the use of an intrinsically safe barrier
 - b. no measurable heat generated during the electro-chemical reaction
 - c. no stored energy in the electro-chemical cell
2. Direct reading indication of the % by volume concentration of hydrogen, which is the common unit of flammability or explosiveness.

DISADVANTAGES

1. Not set up to monitor hydrogen concentration in ppm which is the required unit of measurement per the Project W-113 functional design requirement. **NOTE:** % Volume can be converted back to ppm by the following conversion factor: 1 % Volume = 10,000 ppm.

3.3 VOCs GAS ANALYZERS

3.3.1 VOCs Continuous Gas Monitor

A continuous gas monitor is normally used for measurement of process gas streams for concentration in ppm without requiring any further analysis on the constituents.

A continuous gas monitor utilizing a photoionization detector, HNU Model 201, manufactured by HNU Systems, Inc is proposed to be used which will give a direct reading in terms of parts per million concentration of the VOCs gases.

It has basically two (2) moving parts: the meter and the sample pump. Estimated cost of the unit is between \$10,000.00 - \$12,000.00, which includes training and start-up assistance cost. It is available either as a NEMA 4 wall mountable unit or a rack mountable unit suitable for use in general purpose areas only. This continuous gas monitor uses a photoionization detection system (PID).

The following standard features are included in the basic unit:

1. choice of photoionization detector lamps for selectivity
2. teflon coated flow system for corrosive samples
3. bypass flow system for long term stability
4. meter readout directly in ppm with ranges of 0 - 20/200/2000 ppm
5. built-in sample filter with three (3) replacements
6. heated detector to prevent condensation or adsorption
7. dual set point meter, adjustable 0 - FSD, DPDT contacts
8. gold-plated ion chamber for use in corrosive sampling
9. vacuum detector system for high humidity levels and/or extended linearity

Several optional features can be added to the basic unit, if required:

1. strip chart recording
2. 4-20 mA output for remote data acquisition
3. explosion-proof housings:
 - Type "Z" purging for use in Class 1 Div.II, NEC Group C and D areas
 - Type "X" purging for use in Class 1 Div.I, NEC Group C and D areas

Some of the maintenance and serviceability features are:

1. A routine periodic replacement of a cartridge type filter is required.
2. Cleaning of the light source window, if and when the sensitivity begins to decline is required.
3. The components are adequately spaced so that they are easily accessible for repair or replacement.
4. Zeroing is done by switching off the UV lamp. The calibration does not change when the UV lamp is turned on after zeroing.
5. No zero calibration gas is required.

ADVANTAGES

1. There is a direct readout of total VOC ppm for quick determination if equal to 500 ppm, greater than 500 ppm, or greater than 600 ppm.
2. The effluent gas may also be fed directly to a gas chromatograph or mass spectrometer, only if the VOC exceeds 600 ppm, for further quantitative analysis of the constituents.
3. Zeroing is done by switching off the UV lamp. The calibration does not change when the UV lamp is turned on after zeroing.
4. No zero calibration gas is required.

DISADVANTAGES

1. It does not provide quantitative analysis of the VOC constituents.
2. It requires a separate gas chromatograph or mass spectrometer to provide quantitative analysis of the VOC constituents.

3.3.2 Gas Chromatograph

If the VOC concentrations equals or exceeds 600 ppm as measured by the HNU Model 201 continuous gas monitor, the effluent gas from the continuous gas monitor will be fed directly to the inlet port of a HNU Model 321-00 gas chromatograph for further quantitative analysis. This gas chromatograph equipment uses a photoionization detection system (PID).

This would be the preferred method, since no further analysis on the VOC constituents is required as long as the VOC concentrations is less than 600 ppm. Total anticipated analysis time is between (15) - (20) minutes for the number of VOCs listed. Analysis time will be considerably reduced by the experience gained during the actual operations and if not all the listed VOCs are present in the gas mixtures sample. It is specifically design as a compact GC with research capability for easy programming and editing of methods.

The estimated cost of the unit will be about \$15,000.00, which includes the cost for the manufacturer's field engineer's initial installation, start-up and training services.

ADVANTAGES

1. It is more sensitive than a flame ionization detection system FID. Parts per billion (PPB) is common in many analyses.
2. Photoionization detector-based gas chromatographs don't require a hydrogen flame, making them safer to run in high risk areas.
3. Degree of selectivity if needed, can be done by choosing one of four different interchangeable detector lamps. **NOTE:** Refer to Appendix D listing on the VOCS and head gases ionization potential.
4. There is no response to the inorganic head gases listed for Project W-113.

DISADVANTAGES

1. Total anticipated analysis time is between (15) - (20) minutes for the number of VOCs listed for Project W-113.

3.4 GAS MIXTURES FLAMMABILITY TEST

This is the Project W-113 suggested method using the ASTM E681-85 Test Apparatus: The gas mixture will be ignited in the closed vessel. The flammable component concentration is varied until the composition is determined which will just sustain propagation of the flame is determined. The lower and upper limit of flammability is computed from the minimum concentration and maximum concentration respectively of the gas mixtures which will just sustain propagation of the flame. Calculations can become complex.

Instead of using the test instrument set-up and method as described in the ASTM Method E681-85, the following test instrumentation and method are recommended to be used: **NOTE:** Refer to Appendix A, Sketch #1 for the System Block Diagram.

A sensor-activated bunsen burner, similar to a Cole-Parmer Instrument Co., Cat.#L-03010-70, which has the following operational features:

1. Only when the touch sensitive hand pad or optional foot switch is depressed that the flame ignites and burns.
2. Permits startup only with the optional foot switch.
3. A built-in timer can be set for 10-60 minutes of continuous operation if hand-pad activated.
4. Automatic shutdown occurs by shutting off gas supply itself, if flame goes out, overheats, or power fails. An alarm light flashes to warn of unsafe condition.
5. Three (3) gas jets for use with butane/propane, natural, or town gas are included.
6. Separate valves located on the instrument's front panel are used for control and adjustment of the gas/air mixture.
7. Unit measures 8"L x 4"W x 4"H and has a 10 mm OD hose for gas connection.

If VOCs concentration is equal or greater than 500 PPM as indicated by the on-line gas monitor, the gas mixtures will be directed to the bunsen burner by opening solenoid valve (SV-3) and manual valve (MV-1), to determine its flammability. If the gas mixtures burn, then it will be considered as flammable.

Also, the purged gas mixtures can be directed later on to the bunsen burner to determine its flammability. If the gas mixtures burn, then the inert gas purging is not yet complete. When the gas mixtures does not burn anymore, then inert gas purging is complete and satisfactory.

3.5 VENT GASES MONITORING INSTRUMENTATION

3.5.1 Stack Gas Sampling

The stack gas sampling system provides a real-time indication of radiation particle concentration using isokinetic air volume measurements and a gamma detector. NOTE: Refer to Appendix A, Sketch #3 for the System Block Diagram.

A Series 4200 continuous automatic isokinetic stack sampling system as manufactured by Kurz Instruments Inc, is recommended to be used as a part of the vent gases monitoring instrumentation system.

The Series 4200 continuous automatic isokinetic stack sampling system consists of the following:

1. an IK-Bar 12 isokinetic probe with one (1) withdrawal sampling rake
2. a 151RM signal conditioning, linearization and multipoint averaging electronics
3. a 730 electric rotary ramp valve
4. a 191RM power supply
5. a 4200 isokinetic controller module
6. a 505RM sample rate mass flowmeter
7. a 193 system enclosure
8. a 101SRM resettable flow totalizer
9. a 132RM isolated 4-20 mA output module
10. a ETIRM elapsed time indicator module

3.5.2 Radionuclides Monitoring

The gamma detector to be provided for monitoring radionuclides release to the environment will be an Eberline Model #DA1-X and #RMS II respectively or a WHC certified equal.

3.5.3 Record Sample Filter Analysis

The record sampler collects representative stack exhaust particulates on a filter paper. This filter is to be periodically removed for laboratory type analysis on the collected particulates, measured for concentration of the various contaminants. The record sample filter paper will be sent to an onsite WHC laboratory for the required analysis. NOTE: No analytical instrumentation for this type of analysis is included in this engineering study report.

3.5.4 Workplace Monitoring

A portable gas leakage detector that will be required per OSHA 29 CFR 1910.120 to monitor the workplace around the drum venting heavy-walled enclosure for workers health and safety, shall be approved for Class I, Division 2 usage. A portable industrial hygiene analyzer, HNU Model PI-101, certified to be use in Class 1, Division 2 areas may be considered for the workplace monitoring. It is designed to detect and measure a wide range of volatile organic compounds. NOTE: Refer to Appendix D, PERMISSIBLE EXPOSURE LIMITS.

3.6 DRUM HANDLING SYSTEM INTERFACE SAFETY ISSUES

There are safety issues that need to be resolved with respect to the handling of the drum while it is being retrieved in the trench and before/after it is placed inside the drum venting and head gas sampling equipment heavy walled enclosure.

Some of the safety issues are:

1. The advance conceptual design report (ACDR) on the overpack drum should include a design feature such that the movement and handling of the overpacked 55-gallon drum will not cause the 55-gallon drum to bang back and forth against the 85-gallon overpack drum, potentially creating sparks from metal to metal contact.
2. The drum could possibly drop from the drum handling equipment: gantry crane or the forklifts.
3. The drum grappling equipment may not grasp the drum during violent movement, such as that encountered during an earthquake.
4. Corrosion has weakened the structural integrity of the drum including the drum lid.
5. The drum piercing containment enclosure should be purged during the time 55-gallon drum lid is to be penetrated.
6. The assignment of a WHC Safety Class 2 to both the drum venting equipment and the heavy-walled enclosure shall be reviewed and confirmed.
7. Design provisions for operating the CVS with a 55-gallon drum that is already inside an overpacked drum without removing the overpacked drum lid.

4.0 UNCERTAINTIES

There are several uncertainties encountered during this engineering study which may have to be considered during the equipment development phase and definitive design phase of the Project W-113 CVS equipment, and prior to completing the demonstration testing and operational use of the Pilot Retrieval Project CVS:

1. Additional modification to the existing CVS equipment design might be required based on the Bureau of Mines (Pittsburgh) explosion hazards testing. **NOTE:** The test results will determine the extent of the built-in design provisions to minimize explosion hazards and whether to use the drilling or punching concept for drum lid penetration.
2. Project W-113 requires that for gas mixtures that are in the flammable or explosive range, the drum will be purged with an inert gas to reduce the oxygen content in the drum to a level of not more than 5% by volume or to 50% of the minimum concentration of oxygen required to form a flammable mixture, whichever is lower. **NOTE:** This will involve hand calculations to determine the 50% lower explosive limit of the gas mixture which can be either a simple or a complex gas mixture. Refer to Appendix D, CALCULATIONS OF GAS MIXTURES INFLAMMABILITY.

3. The non-sparking aspect is a critical requirement which will require that the drum lid penetrator material of construction used shall be non-sparking. However, commercially available non-sparking materials such as Ampco metal, beryllium copper, manganese bronze or aluminum alloys are not normally used for off-the-shelf drills or punches. **NOTE:** The commercial coating material used for drill bits is to harden the drill bit to maintain sharpness which will keep the drill bit temperature low, but not for non-sparking applications.
4. Another uncertainty is whether the head gases are of a uniform mixture since hydrogen gas is the lightest among the head gases listed. Methane is the second lightest and carbon monoxide is the third lightest after hydrogen among the head gases listed. **NOTE:** Based on air having a specific gravity of one (1), the following listed head gases are heavier than air: ethane and propane. The design is impacted by the additional requirement for a gas recirculating line from the on-line gas analyzing system vent to the drum piercing containment enclosure, in order to achieve a uniform head gas mixture. As an alternate method, argon gas may be used instead of nitrogen gas as the inert gas to be used for purging.
5. For designing the heavy-walled venting enclosure, until a less conservative approach can be developed, the explosion shall be based on a stoichiometric mixture of hydrogen and oxygen at 20 psig internal pressure in an otherwise empty drum. **NOTE:** Explosion source term is not yet fully defined and is not a part of this engineering study. See Appendix B, CALCULATIONS.
6. A very significant design parameter which will affect the instrumentation used will be the uncertainty of the presence of corrosive gases and water vapor. **NOTE:** Refer to Appendix D for a listing of corrosive liquids and fumes. The presence of any corrosive liquids or fumes plus water vapor cannot be determined prior to drum venting. Any carry-over of condensable vapors or suspended particles would very probably change the calibration of the instrument over some period of time due to deposition on the detecting element and causing it to degrade. This would result in unsatisfactory operation on otherwise feasible application for the instrumentation system selected. Therefore, recalibrations will be required regularly should there be excessive corrosive gases and water vapor present.
7. Adequate shielding around the bunsen burner must be provided to prevent injury in the event of energetic explosions that might occur. **NOTE:** The gas mixtures flammability test is made without knowing if the gas mixtures sample is within its flammable range, that is between the lower explosive limit (LEL) and the upper explosive limit (UEL).
8. Safety Class 2 procured items will be from qualified suppliers or designated as Safety Class 2 commercial grade items (CGI), however, some other pertinent QA requirements might imposed procurement delays. **NOTE:** Most if not all the components to be used for the drum venting and head gas sampling equipment are commercial grade items.

5.0 DISCUSSIONS

5.1 DISCUSSION OF SUBSYSTEMS FUNCTIONAL REQUIREMENTS

There are significant functional requirements and other criteria that were used for the evaluation of the recommended instrumentation systems. However, a system mockup and testing is still required to determine their actual performance with respect to Project W-113. Results of the system mockup and testing might introduce more requirements. All these functional requirements shall be included in the performance specification.

5.1.1 VOCs Gas Sample Transport Lines

1. It shall have provisions for the following:
 - a. sample tap connection(s) for batch gas archive sample, flammability test and VOCs constituent analysis
 - b. filter(s)/differential pressure indicator(s), pressure reducing regulator(s), flow regulating valve(s) and flow monitor(s)
 - c. flexible stainless steel or flexible Teflon (trademark) or other highly corrosion-resistant material
 - d. electrical heat tracing and low point liquid drain(s) to avoid condensation of moisture and/or hydrocarbons
 - f. venting the sampled gas to the drum venting enclosure's exhaust ventilation duct upstream of the HEPA filter with the exhaust fan installed after the HEPA filter system and provide differential pressure gauges for the drum enclosure ventilation system HEPA filter
 - g. avoiding significant changes in the composition of the gas sample as it passes through the sampling, cleaning and conditioning system caused by air infiltration into the lines
 - h. regular maintenance and inspection of the sampling lines and periodic leak tests

5.1.2 Hydrogen Gas Monitoring System

1. It shall monitor specifically for hydrogen gas in the drum head space atmosphere and not affected by the presence (but not limited to) unknown quantities of air, oxides of nitrogen, water vapor, carbon dioxide, carbon monoxide, and other gaseous constituents.
2. Electronic instruments installed in classified hazardous locations must meet applicable safety standards.
3. It shall have provisions for:
 - a. a 4-20 mA dc signal interface to either a local or remote data acquisition system
 - b. a local readout display and a local strip chart recorder as a backup recording system
 - c. automatic temperature, pressure compensation and insensitivity to flow rate to make analysis independent of sample conditions
 - d. an accuracy equal to or better than the absolute value of $\pm 0.25\%$ hydrogen in the 0-5% LEL hydrogen range
 - e. a repeatability equal to or better than $\pm 1.0\%$ of full scale

- f. a minimum detection range capability of 0 to 5% LEL hydrogen
 - g. a temperature stability better than or equal ± 0.005 % hydrogen per deg.F
4. The instrument output shall be capable of reaching 90% of the final value in two minutes or less after applying a step increase or decrease of at least 25%, but not to exceed 100% of the instrument full scale.

5.1.3 Drum VOC Gases Sampling System

- 1. An archive gas sample shall be obtained from each drum that is processed through the system.
- 2. An on-line VOCs gases monitoring and analyzing system shall be provided to make the following determination:
 - a. If the VOCs gases concentration is less than 500 ppm, no further gas testing will be necessary.
 - b. If the VOCs gases concentration equals or exceeds 500 ppm, a gas mixtures flammability test should be performed.
 - c. If the VOCs gases are then determined to be flammable, the gases shall be quantitatively analyzed.
 - d. If the VOC concentrations equals or exceeds 600 ppm, both the flammability test and gas analysis shall be required.
- 3. Gas sampling data obtained during the gas sampling will be processed into a waste management data base.
- 4. Additionally hard copies of the data will be with the data management center when the overpacked 55-gallon drums are shipped.
- 5. Analyzers to be provided shall:
 - a. meet a NEC Class 1, Division II classification, unless the analyzer is located in a non-hazardous atmosphere
 - b. operate within $\pm 10\%$ and ± 2 Hz of the AC power supply voltage and frequency, respectively
 - c. reproducibility shall be $\pm 1\%$ of span or better
 - d. reproducibility shall be demonstrated continuously for a period of eight (8) hours using a standard sample
 - e. sensitivity shall be $\pm 1/2\%$ of full span

5.1.4 Drum Vent Gas System

- 1. A method of controlling both chemical and radiological emissions from the drum venting/sampling unit shall be provided after the last emission control.
- 2. The system shall:
 - a. be able to function properly in the chemical environment of the exhaust
 - b. provide alarms (high radiation, instrument failure and loss of electrical power) both locally and remotely in the central control room computer
 - c. remain functional during loss of building power
 - d. collect stack record air samples at an optimum flow rate of 2 cfm for a minimum of 1 week or 168 hours running time
- 3. Flow rate meter(s) and flow volume totalizer(s) shall be provided and installed downstream of the sample collection point of the record sampling system shall be routinely cleaned and calibrated.

4. A primary calibration of the sampling system including the flow totalizer and other associated sampling equipment shall be completed when installed and at least annually thereafter.
5. The average record sample flow rate shall be at least 2.2 CFM.
6. The sample head and probe shall:
 - a. be installed facing upstream into the direction of flow
 - b. be detachable for ease of maintenance and decontamination
7. A flow rate indicator and regulator shall be provided for each sample head, downstream of the sample filter.
8. A compression ring designed to press the perimeter of the filter against the backing support of the sample filter holder shall be provided to ensure an airtight seal.
9. A running time meter shall be provided for indication of accumulated stack operating time.
10. The venting enclosure's exhaust fan shall be electrically interlocked with the record sampling line vacuum pump, such that it will prevent a sample from being taken when the exhaust fan is shutdown.
11. The sample probe location shall be at least five (5) duct diameters downstream and two (duct) diameters upstream of any major flow disturbance.
12. Sufficient vacuum pump capacity shall be provided to maintain a minimum flow of two (2) cfm through the record sample filter. A line loss study will have to be performed to determine sample line size and optimum flow rate for a semi-isokinetic sample.
13. The stack exhaust fan blade shall be constructed of non-sparking material to minimize the possibility of sparking.
14. The sampling line shall be designed, such that:
 - a. length of the line between the sampling probe and the sample filter holder should be as short as possible
 - b. horizontally run lines should be minimized
 - c. the number and angle of bends should be minimized
 - d. bends should have a radius of at least ten (10) times the inside diameter of sample transport line
 - e. use of piping or tubing fittings between the sample probe and the sample filter holder should be minimized
 - f. thermostatically controlled electrical heat tracing should be used, where condensation is a potential problem
15. Sampling and monitoring instrumentation systems shall be designed to be placed as near as possible to the exhaust stack.

5.1.5 Drum Purging System

1. If the drum headspace gas mixtures is in the flammable or explosive range, the drum will be purged with inert gas until the gas mixtures is no longer flammable based on the flammability test.
2. The flow rate of purge gas shall be sufficient to ensure adequate mixing so that release of a flammable gas or vapor is limited.
3. Precautions shall be taken to protect the drum from excessive pressure of the purge supply.

5.1.6 Drum Gas Mixtures Flammability Testing

1. A flashback arrestor constructed to perform the following safety function shall be installed between the sampling line and the gas mixtures flammability test equipment:
 - a. stop and extinguish a flashback with a sintered high-flow filter
 - b. stop the backflow of gases with a non-return valve
 - c. prevent the further supply of gas following a flashback with a pressure activated positive valve lock

NOTE: An alternative safer method will be to get an extra gas grab sample for the gas mixtures flammability. The gas mixtures flammability testing will be done with the bunsen burner not plumbed in to the bypass gas sampling line.

5.1.7 Drum filter and Method of Installation

1. After the inert gas purging, a filter with the following design requirements shall be installed in the 55-gallon drum lid:
 - a. provide adsorption of volatile organic compounds and particulates but will permit the passage of hydrogen and other inorganic gases
 - b. coordinate filter size and material with the method used for drum penetration
 - c. the filter design shall be a DOT approved design
 - d. coordinate design with Project W-112 requirement that another gas sample will be taken out prior to shipment to WIPP

5.1.8 Gas Sampling/Analysis Room

1. It shall be provided with:
 - a. adequate ventilation to adequately dilute any internal release of flammable gases or vapor
 - b. a viewing window to allow the operator to view the venting operations
 - c. venting, sampling and purging controls
 - d. analysis instrumentation system racks and work bench
2. Alarms shall be displayed on the control panel.
3. The analysis equipment shall be plumbed directly to the drum venting equipment to eliminate the possibility of a mix-up with previous samples.
4. Process piping entering the room shall be provided with shutoff valves for emergency isolation.
5. Process piping within the room shall be kept to a minimum.
6. False ceilings and floors shall not be used in this room.
7. Provide HVAC in the gas sampling/analysis instrumentation room.

5.1.9 NEC Hazardous Area Classification

The drum venting and head gas sampling process area is to be considered as a Class I, Division 2 location per the NEC based on the following criteria:

1. The volatile flammable liquids or gases are normally confined within the drum or the heavy-walled drum venting enclosure. They can escape only during the venting process, accidental rupture, structural breakdown of the drum or the heavy-walled drum venting enclosure.
2. Ignitable concentrations of gases within the heavy-walled enclosure will be normally prevented by the enclosure's exhaust fan, provided, there is no failure or abnormal operation of the exhaust fan.
3. Ignitable concentrations of gases within the Trench Enclosure Building will be normally prevented by the two (2) portable exhausters, provided, there is no failure or abnormal operation of the portable exhausters.

5.1.10 NFPA 77 Guidelines: Prevention of Static Electricity Generation

Because of the low electroconductivity of some of the gases (such as ethane, methane, 1,1-Dichloroethane) and flow or agitation is inherent to the drum venting and gas sampling process, the following safety design features should be considered:

1. Bonding/grounding wires with either a C-clamp or electrical terminal lugs on both ends of the bonding/grounding wires should be used to connect metal parts required to be electrically connected to assure electrical conductivity between the parts and connect the drum directly to ground or through an intermediate conductor.

5.1.11 WHC Safety Classification

The assignment of Safety Class 2 for the drum venting equipment and heavy-walled enclosure will require the following WHC imposed design/analysis requirements to be considered in the design:

1. nonsafety items design requirements as defined in DOE Order 6430.1A
2. the additional requirements as determined by the Project W-113 facility safety analysis
3. the following mandatory additional requirements for WHC classified Safety Class 2 structures, systems and components:
 - a. **Natural phenomena hazards:** Design and analysis for natural phenomena hazards shall be per SDC 4.1 of the Hanford Plant Standards.
 - b. **Environmental qualifications:**
 - Environmental conditions such as temperature, pressure, humidity, radiation and chemicals will not affect its safety function performance.
 - Periodic testing and surveillance shall be part of a regularly scheduled maintenance program.
 - c. **Single Failure:** Redundancy requirements shall be imposed, if a single, active, detectable component failure can cause

unacceptable onsite consequences. **NOTE:** A documented risk analysis assessments may be substituted for the redundancy requirements.

- Sufficient separation of redundant components shall be provided to prevent common failure.
- d. **Fire protection systems:** Fire detection and suppression system, if required, shall meet NFPA standards.
- e. **Backup power:** Backup electrical power, if required, shall be provided.
- f. **QA requirements:** Safety Class 2 procured items will be from qualified suppliers or designated as Safety Class 2 commercial grade items (CGI).

5.1.12 Process Control Logic

The drum venting and head gas sampling system process which will be under the control of the industrial programmable controller in conjunction with the operator's action shall have the following features:

1. Provide the following standard color indication for the following:
 - a. a solenoid valve in the "closed" position: "green"
 - b. a solenoid valve in the "open" position: "red"
 - c. a motor "stopped" but with "power on": "green"
 - d. a motor "running": "red"
2. Incorporate sampling sequence logic for archive gas sampling, gas mixtures flammability test, VOC sampling and inert gas purging.
NOTE: Refer to Appendix A, Sketch #1 for the valve line-up designations as described below. Valving line-up could change depending on the final designed configuration of the drum venting and head gas sampling system.
 - a. During archive gas sampling, the following solenoid valves position shall be as follows:
 - chamber valve (CV-1) open
 - solenoid valve (SV-1) open & on-line gas monitor on
 - solenoid valves (SV-3, -4) open
 - manual valves (MV-2, -7) open
 - manual valves (MV-4, -8,) open & vacuum pump on
 - line valve (LV-2) open
 - solenoid valves (SV-2, -5) closed
 - manual valves (MV-1, -3) closed
 - line valve (LV-1) closed
 - purge valve (IV-1) closed
 - b. During VOC monitoring (ppm is less than 500 ppm, no further gas testing will be necessary) the following solenoid valves position shall be as follows:
 - chamber valve (CV-1) open
 - solenoid valve (SV-1) open & on-line gas monitor on
 - solenoid valve (SV-4) open

- manual valves (MV-4, -8) open & vacuum pump on
 - line valve (LV-2) open
 - solenoid valves (SV-2, -3, -5) closed
 - manual valves (MV-1, -2, -3) closed
 - line valve (LV-1) closed
 - purge valve (IV-1) closed
- c. During VOC monitoring (ppm concentration equals or exceeds 500 ppm a flammability test should be performed) the following solenoid valves position shall be:
- chamber valve (CV-1) open
 - solenoid valve (SV-1) open & on-line gas monitor on
 - solenoid valves (SV-3, -4) open
 - manual valves (MV-1, -7) open
 - manual valves (MV-4, -8) open & vacuum pump on
 - line valve (LV-2) open
 - solenoid valves (SV-2, -5) closed
 - manual valves (MV-2, -3) closed
 - line valve (LV-1) closed
 - purge valve (IV-1) closed
- d. During VOC analysis (ppm concentration equals or exceeds 500 ppm and the gases are then determined to be flammable, the gases shall be further analyzed to determine the constituents and their relative concentrations) the following solenoid valves position shall be as follows:
- chamber valve (CV-1) open
 - solenoid valve (SV-1) open & on-line gas monitor on
 - solenoid valves (SV-2, -4) open
 - manual valves (MV-3, -7) open
 - manual valves (MV-4, -8) open & vacuum pump on
 - line valve (LV-2) open
 - solenoid valve (SV-5) closed
 - manual valves (MV-1, -2) closed
 - line valve (LV-1) closed
 - purge valve (IV-1) closed
- e. If the VOC concentrations equals or exceeds 600 ppm, both the gas flammability test and VOC gas analysis will be required.
- do flammability test first, manual valve (MV-1) open and manual valves (MV-2, -3) close, and then
 - do VOC analysis afterwards, manual valves (MV-1, -2) close and (MV-3) open
- f. During inert gas purging, the following solenoid valve positions shall be as follows:
- chamber valve (CV-1) open
 - purge valve (IV-1) open
 - line valves (LV-1, -2) open
 - manual valves (MV-4, -8) open & vacuum pump on
 - solenoid valves (SV-1, -2, -3, -4, -5) closed
 - manual valves (MV-1, -2, -3, -7) closed

- g. During the verification process to determine when to stop gas purging (do flammability testing of purged gas mixtures), the following solenoid valve positions shall be as follows:
- chamber valve (CV-1) open
 - solenoid valve (SV-1) open & on-line gas monitor on
 - solenoid valves (SV-3, -5) open
 - manual valves (MV-1, -7) open
 - manual valves (MV-4, -8) open & vacuum pump on
 - line valve (LV-2) open
 - solenoid valves (SV-2, -4) closed
 - manual valves (MV-2, -3) closed
 - line valve (LV-1) closed
 - purge valve (IV-1) closed
3. Incorporate control logic for automatically inserting the filter after drum purging.
4. Incorporate control logic for automatically starting the drum venting and head gas sampling enclosure's exhaust fan as soon as the enclosure entry door is closed.
5. Incorporate interlocks that will prevent drum venting if the following conditions exists:
- a. heavy-walled enclosure door is open
 - b. drum is not properly positioned for venting
 - c. heavy-walled enclosure exhaust fan is not operational
 - d. Trench Enclosure Building portable exhausters are not operational
 - e. the drum lid is not properly clamped and sealed
 - f. emergency stop button is activated by the process operator
6. Alarm and abnormal warning pilot light(s) activated through the programmable controller shall be provided on the graphic display panel. **NOTE:** Example of some process conditions that may be considered for alarm indications are loss of vacuum and venting enclosure's exhaust fan not operational.
7. Additional control interfaces required for system operation and surveillance such as the following shall be provided:
- a. control switch for the heavy-walled enclosure exhaust fan
 - b. differential pressure gauge(s) for the HEPA filter located upstream of the exhaust fan
8. During the sequence of operations, additional flashing lights are to be used as visual aids to the operator that some other action may be needed, before the next operation indicated by the other flashing lights is done. **NOTE:** Most of these actions refer to subsystem equipment that are not included in the programmable controller logic, but are hard-wired to the electrical power source, such as the system vacuum pump and the air compressor.

5.2 ASSUMPTIONS USED

The engineering study report recommendations as stated in Section 3.0 are based on the following assumptions:

1. Ambient temperature, moisture and corrosiveness of the gases inside the drums are within commercially available instrumentation

- operating environment capability. NOTE: All the instrumentation systems proposed to be used for the mockup/testing are based on available data from Project W-113 existing documents. The characterization efforts by the WHC pilot retrieval project should verify the nature of the drum head gases with respect to moisture content, pH number and the ambient temperature inside the drums.
2. The accuracy of the gas analyzer and monitor is not affected by the presence of other gases, for which the instrument is not specifically designed to analyze or monitor. NOTE: Refer to Appendix D for some typical gas interference data.
 3. The gas mixture on the head space of the drums is not homogeneous, such that recirculation of the gas mixture is needed, in order to get a truly representative gas sample. NOTE: See Appendix D for the head gases specific gravity. Only carbon monoxide, hydrogen, nitrogen and methane are lighter than air.
 4. Gases subject to interference by other gases will be minimal. Most application problems are due to interference by other gases. NOTE: See Appendix D for some typical gas interference data.
 5. Total expected hydrogen gas concentration by volume is within the 0 to 5% range. NOTE: If hydrogen gas concentration by volume exceeds the 0 to 5% range, then hydrogen gas sensor and the instrumentation will be changed to the optional 0 to 100 % range.
 6. Total expected VOCs gases concentration is within a maximum of 2000 ppm. NOTE: See equivalent weight in mg/drum or mg/l for each listed VOC @2000 ppm in Appendix D.
 7. Total expected normal VOCs gases concentration is less than 500 ppm. NOTE: See equivalent weight in grams/drum or grams per liter for each listed VOC @500 ppm in Appendix D.
 8. Total expected number of VOCs gases present when concentration exceeds 600 ppm is within the thirty-one (31) listed VOCs, the on-line gas chromatograph is initially programmed to detect. NOTE: See equivalent weight in mg/drum or mg/liter for each listed VOC @600 ppm in Appendix D.
 9. The gas sample collected is in the range of 40 to 60 mg/l, since the lower flammable limits of most organic chemicals are in this range. NOTE: See equivalent ppm for each listed VOC to be within the lower flammable limits range guidelines in Appendix D.
 10. Sufficient grounding and bonding provisions as per the NFPA 77 design guidelines have been included in the design. NOTE: Where a static spark and a flammable vapor-air mixture may occur simultaneously, suitable preventive measures are required to prevent ignition.
 11. The flammable liquids vapor-air mixture flammability inside the drums can be too lean to burn, more likely to be flammable, or too rich to burn depending on the flash points of the flammable liquids that may be present compared to the ambient temperature inside the Trench Enclosure Building where these drums are handled.
 12. The gases do not have metallic oxides or scale particles and the sampling flow rate is not fast enough to cause electrification. NOTE: This data should be noted during the WHC pilot retrieval demonstration project efforts to characterize the waste drums.
 13. The gas sample to the monitoring/analyzing instruments can be made free of suspended particles by appropriate filtering and provisions are made to eliminate possible carry-over of

condensable vapors without considerable or elaborate sample conditioning systems. NOTE: Any carry-over of condensable vapors or suspended particles would very probably change the calibration of the instrument over some period of time due to deposition on the detecting element. This would result in unsatisfactory operation on otherwise feasible application for the instrumentation system selected.

14. The drum venting enclosure stack would be considered a new emission source that will require the proper notification to the State of Washington.

5.3 DISCUSSION OF ALTERNATIVE HYDROGEN & VOCs GAS ANALYSIS INSTRUMENTATION SYSTEM

5.3.1 WHC SAS Instrumentation Proposal

This alternative VOCs gas analysis instrumentation system would be located inside a mobile trailer laboratory which is located outside the Trench Operation Building. An umbilical cord will connect the drum venting equipment to the mobile trailer laboratory. Operation of the laboratory will be manned and supported by the WHC Special Analytical Studies (SAS) personnel.

An informal proposal for the drum head space analysis instrumentation system proposed by the WHC Analytical Studies group is as follows:

1. **Instrumentation System:** Vapors from the drum headspace are to be drawn into two (2) cells. One will be a long path length gas cell for the Fourier Transform Infrared Spectrometer (FTIR). The other much smaller gas cell is for the Raman spectrometer. The chambers into which the vapors were originally drawn will be pumped out and the sampling line will be purged with dry nitrogen. The sampling line temperature will momentarily be elevated during the nitrogen purge to removed any condensed vapors.

This cleaning period will probably take about three (3) minutes, after which the system can receive the next drum's vapor sample.

2. **Raman Spectrometer:** The Raman spectrometer will be used to determine the amount of homonuclear diatomic compounds that are present in the drum headspace. Gases that are analyzable with this instrument includes hydrogen, nitrogen, oxygen, etc. to the low part per million levels. Estimated cost of the unit is \$25,000.00.
3. **Fourier Transform Infrared Spectrometer (FTIR):** The FTIR will be used to analyze for volatile organic compounds listed to be monitored by Project W-113 and is capable for as many as 100 different compounds. Estimated cost of the unit is \$75,000.00.

Presently, INEL are in the various stages of developing on-line gas analyzing capability using a Fourier Transform Infrared Spectrometer (FTIR) of different manufacturer's. The time required for a complete gas analysis is an important criteria to their process, since the drums are already in a conveyor belt system leading to the silo building, where the drum venting equipment is

located. Performance testing of the different manufacturer's FTIRs, they have tested so far indicates an analysis time of (5) - (10) minutes for at least (20) - (40) compounds. A preliminary feasibility report on the use of a specific manufacturer's FTIR is scheduled to be completed March 1993. After the equipment is purchased, they will still do actual operations performance testing for at least another year, before finalizing the on-line gas sampling system instrumentation.

4. Estimates of System Costs

a.	Combined FTIR/Raman (2).....	\$200,000.00
b.	Sampling Hardware.....	\$ 50,000.00
c.	Data System.....	\$ 50,000.00
d.	Trailer.....	\$ 50,000.00
e.	Miscellaneous.....	\$ 50,000.00

TOTAL EST. COST.....\$400,000.00

NOTE: See Appendix C, Engineering Development Work Estimates for using the SAS proposed FTIR/RAMAN (hydrogen gas monitoring and VOCs gas analyzing instrumentation only) and WHC Central Engineering doing the development work. Engineering development work cost estimate is \$239,000.00 and activities will be from October 1992 to April 1996.

5. Method of Design Implementation

SAS personnel will perform the following with the corresponding personnel cost estimates:

- a. The selection of instrumentation, design of the vapor handling apparatus, and the specification of the trailer to house this instrumentation will require (4) man-months for \$35,000.00.
- b. Build/purchase system will require (8) man-months for \$65,000.00.
- c. Calibrate/test/repair equipment and check/report/archive data will require (8) man-months/year for \$65,000.00.

ADVANTAGES

1. Performance testing of different FTIRs by INEL indicates an analysis time of (5)-(10) minutes for at least (20)-(40) compounds is faster than a gas chromatograph.
2. SAS taking over the operation, calibration, testing, checking, reporting, and archiving the data for \$100,000.00 per year is reasonable operating cost for the facility.

DISADVANTAGES

1. Hydrogen gas concentration will be indicated in parts per million instead of % volume, using the Raman spectrometer.
2. Flammability of the gas mixtures will be require calculations based on the % volume concentration of the VOCs present including

the nitrogen inert gas. PPM readings have to be converted back to % volume.

3. This has the potential of an increase in the Project W-113 project scope and cost. **NOTE:** Engineering cost is \$100K just for the hydrogen gas monitoring, VOCs gas analyzing system and the trailer housing and another \$400K for equipment cost. These excludes any cost associated to the drum venting and head gas equipment modifications required for Project W-113 use.

5.3.2 Combined Gas Chromatograph/Mass Spectrometer

A Hewlett-Packard gas chromatograph/mass spectrometer is presently used in WHC analytical labs for full scale gas analysis wherein grab samples are injected manually into the unit. The unit can cost between \$60,000.00 to \$100,000.00 depending on the optional features required. It is more suitable for laboratory type analysis capability for a much larger number of compounds and gases. This gas chromatograph equipment uses flame ionization detection system (FID).

The basic system can be set up on a five (5) foot work bench and consists of the following equipment:

1. MS ChemStation (DOS series) : personal computer station with keyboard and monitor and the MS windows 3.0 based GC/MS software
2. HP 5890 series II GC gas chromatograph
3. HP 5971A MSD mass selective detector

NOTE: See Appendix C, Engineering Development Work Estimates for using the Hewlett Packard's VOCs gas analyzing instrumentation only) and WHC Central Engineering doing the development work. Engineering development work cost estimate is \$229,000.00 and activities will be from October 1992 to April 1996.

The proposed Hewlett-Packard gas chromatograph/mass spectrometer system is set up to operate in the following manner:

1. A vacuum pump provided by others will draw the gas sample and pass it to a gas sampling valve and a switching valve. **NOTE:** The vacuum pump is part of the continuous gas monitor and the gas sampling valve and the switching valve are the solenoid valves (SV-1) and (SV-2) respectively from the previously discussed HNU system.
2. The switching valve is normally set up to direct the gas sample to the FID for a quick scan to determine if VOCs gases concentration exceeds the 600 ppm limit. A hard copy report will not be printed.
3. If the VOCs gases concentration exceeds the 600 ppm limit, the switching valve will direct the gas sample to the analysis column for analyzing the compounds present. A hard copy report will be printed.

ADVANTAGES

1. The flame ionization detector is highly sensitive to hydrocarbons, but will not detect carrier gases such as nitrogen and oxygen, or

- manual valve (MV-7) open highly oxidized materials such as carbon dioxide, carbon monoxide, sulfur dioxide and water.

DISADVANTAGES

1. Uses hydrogen gas for burning the toxic or combustible gas molecules and may present a safety hazard in case of leakage due to component failure.

6.0 REVIEW OF CVS EQUIPMENT DESIGNS

A review of existing WHC and other DOE sites drum venting and head gas sampling systems was done in order to make use of existing designs that meet the specific requirements of Project W-113.

6.1 WHC PILOT RETRIEVAL DEMONSTRATION PROJECT CVS EQUIPMENT

The WHC pilot retrieval demonstration project CVS equipment will be used to remove drums from various burial trenches for examination. Information gained during this effort will support the Project W113 definitive design activities.

NOTE: The CVS method (disclosed in invention disclosure #ARW 92-26) to pierce the drum lid, obtain a gas sample and remove the drum from storage and the determination of the void volume in a closed container (disclosed in invention disclosure #ARW 92-49) are presently in patent committee review at Westinghouse Hanford Company.

The following recommended modifications to the WHC Pilot Retrieval Demonstration Project CVS design has to be considered in the definitive design of the Project W-113 CVS:

1. PROCESS CONTROL LOGIC

- a. **NOTE:** Refer to Section 5.1.12 for the recommended design modifications.

2. COMPRESSED AIR SYSTEM

- a. If water carry-over in the compressed air system becomes a problem, an instrument air dryer should be provided. The instrument air dryer will process the compressed air beyond the aftercooler and receiver to further reduce moisture content. **NOTE:** Some of the problems to be noted, if they occur during actual operations are:
 - washing away of the required lubrication
 - increase in wear and maintenance
 - sluggish and inconsistent operation of solenoid valves and pneumatic cylinders
 - freezing in exposed lines during cold weather

- b. Provision for draining and disposal of the condensate from the air receiver and the in-line filter separator should be included.

3. VACUUM SYSTEM

- a. The solenoid valve (CV-1) should be closed on loss of vacuum.
- b. Recheck the vacuum pump capacity to include its use as the vacuum source for the stack exhaust gases radionuclide monitoring system. **NOTE:** A separate vacuum pump which is a component part of the continuous gas monitor will be used for drum head gas sampling and VOCs monitoring.
- c. Revise the vacuum pump controls accordingly, such that venting of the drum head gases will be upstream of the venting enclosure's exhaust stack HEPA filter.

4. PURGING SYSTEM

- a. Add an additional nitrogen bottle for a quick manual switchover from the other nitrogen bottle that becomes empty.
- b. The gas mixtures including the inert gas should be subjected to a flammability test. If no longer flammable, inert gas purging is complete.

5. ELECTRICAL POWER SUPPLY SYSTEM

- a. Electrical power should come from any one of the 480 V welding receptacles installed inside the Trench Enclosure Building.
- b. The voltage meter range should be changed to 480 Vac and frequency meter should be retained and will be used to monitor the incoming electrical power from the 480 V welding power receptacle used to supply power to the equipment.
- c. A single-phase 480-120/240 Vac step-down transformer and a single-phase 120/240 Vac distribution panelboard will be required on the portable trailer to provide the 120 Vac power, control and instrumentation requirements.

6. DRUM PIERCING CLAMPING SYSTEM

- a. Recheck the clamping cylinders bore sizes for the maximum force expected for drum explosion. **NOTE:** See Appendix B, CALCULATIONS.

7. DRUM PIERCING CLAMPING SYSTEM

- a. Recheck the sealing cylinders bore sizes for the maximum force expected for drum explosion. **NOTE:** See Appendix B, CALCULATIONS.

8. DRILL PRESS ASSEMBLY

- a. Separate gas ports each for gas sampling and gas recirculation/purging to the drum piercing containment enclosure should be provided.
- b. There are several options for the drill press assembly modifications to achieve drum penetration and insertion of the drum lid filter:
 - Use the design concept shown on the Project W-113 conceptual design drawing # ES-113-L8, except the drum penetration will be on-center. **NOTE:** Refer to Appendix A, Sketch #14, from Reference Material, WHC-SD-W113-CDR-002.
 - Use the INEL design, except convert the hydraulic system to a pneumatic system. Also, the drum penetration will be on-center. The drum position clamping mechanism and no conveyor system will be required. **NOTE:** Refer to Appendix A, Sketch #5 and Sketch #6, from Reference Material, SRL-MNT-91373.
 - Use the LANL design of having the filter built-in to the drum penetrating tool. **NOTE:** Refer to Appendix A, Sketch #7, Sketch #8, Sketch #9, and Sketch #10, from Reference Material, SRL-MNT-91373.
 - Use the WHC pilot retrieval design, except with the following modifications:
 - . Provide another pneumatic drill motor except, it is to be used for filter insertion of the INEL DOT approved filter.
 - . Use only (1) pneumatic drill assembly, except the operator will replace the drill bit with the filter holder assembly prior to the filter insertion cycle.
 - . Instead of having the operator replacing the drill bit with the filter holder assembly, design a combined filter and drill penetrating device using the INEL DOT approved filter at one end and a rotary boring drill or a drill bit at one end. The two ends will be connected by a hollow cylindrical tube with holes to allow gases to escape to the filter after its insertion in the drum lid. **NOTE:** Refer to Appendix A, Sketch #13.

9. SAMPLE BOTTLES

- a. The sample bottles and the corresponding solenoid valves should be relocated to the gas sampling/analysis room.
- b. The solenoid valves should be closed (de-energized) on loss of vacuum.
- c. The solenoid valves electrical enclosure should be of the explosion-proof type.
- d. Use one (1) liter sample bottles.
- e. The flow through the sample bottles should be manually controlled with flow control valves and measured with flow

indicators for a specified period of time to ensure ample gas samples have been collected.

- f. The reference valve (RV-1) and its associated equipment/hardware will not be used and should be removed.

10. LIFTING FRAME SYSTEM

- a. The lifting frame should be removed, since it will not be used as a means for lifting the drum from the burial trench.
- b. Provide the clamping and sealing cylinders framing supports attachment to the heavy-walled enclosure structure.

11. PRESSURE TRANSDUCERS

- a. None. Retain in service, however, pressure transducers may be replaced to have ranges in either inches or mm Hg instead of Torr.

12. PRESSURE GAUGES

- a. None. Retain in service, however, pressure gauges may be replaced to have ranges in either in or mm Hg instead of torr. Pressure gauge for monitoring the inert gas purging pressure will read in psig.

13. UMBILICAL ASSEMBLY

- a. Add extra gas lines to the umbilical cord assembly for the gas recirculation, inert gas purging and venting of the gases.
- b. Provide an extra set of umbilical cord assembly for a quick changeover, in case of failure of the umbilical cord being used.

14. CVS STAND ASSEMBLY

- a. None. It can still be used as a stand when doing maintenance work on the drum piercing assembly.

15. CVS ENCLOSURE ASSEMBLY

- a. A heavy-walled enclosure will be needed to contain drum explosion.
- b. The heavy-walled enclosure shall have the following design features:
 - material used is not likely to be damaged by a drum explosion
 - operator's viewing window shall not only be shatter-proof material but must be at least equal in strength to the materials used for the construction of the heavy-walled enclosure. Materials such as lexan and lesgard, which are used for explosive shields, can provide this strength.

- interior surfaces shall be coated with a high-gloss epoxy based paint that can be easily decontaminated
- c. Electrical devices located inside the heavy-walled enclosure shall be designed for installation in a Class 1, Division 2 hazardous area.

6.2 IDAHO NATIONAL ENGINEERING LABORATORY (INEL)

The INEL's existing CVS equipment drum punching and insertion of filter is all done by hydraulic cylinders. Two (2) canisters are provided, before and after the sampling line filter, where grab gas samples are taken. The grab gas samples are then sent to the Argonne Laboratory for gas analysis.

The filter design was developed by Nuclear Filter Technology in Golden, Colorado, telephone number (303-987-2020). It is a screwed type filter measuring one (1) inch diameter by one (1) inch long.

Presently, they are in the various stages of developing on-line gas analyzing capability using a Fourier Transform Infrared Spectrometer (FTIR). However, performance of this instrumentation is still to be tested, scheduled for FY 93.

The filter assembly, as shown in Appendix A, Sketch #5, allows continuous aspiration of internally generated gases while containing radioactive particulates inside the drum.

The punching and filter insertion machine is a hydraulically powered dual sliding head assembly that punctures and inserts a filter in each drum. An adjustable drum clamping mechanism holds either a 30-, 55-, or a 83-gallon drum in place for punching and filter insertion.

The punch head assembly, as shown in Appendix A, Sketch #6, has a hydraulically powered spindle that punches the drum and inner liner lid for venting the drum interior. To eliminate any sparking potential, the punching mechanism downward travel rate is limited and controlled. An outer sealing mechanism seals the bottom of the punch with the drum lid during the puncture and then lifts away from the drum after venting. A sample port line at the punch head mechanism leads Any off-gas discharged during the venting are led by a sample port line to the suction inlet of the HEPA filtered recirculation ventilation system.

After the spindle punches the drum and retracts, the tapping/filter insertion head assembly retrieves a filter assembly from the filter feeder. A hydraulically powered collet then clamps the base of the filter. The dual head assembly positions and moves downward the tapping/filter insertion head over the punctured drum.

A hydraulic motor causes the filter to advance downward the drum lid puncture hole until it stalls at a preset torque value. A timer signals the completion of the filter insertion. The collet the unclamps the filter. The tapping/filter insertion head reset and reposition for the next drum venting cycle.

The punching and filter insertion machine programmable controller is equipped with battery backup power supplies thus retaining its memory during a power outage. The proper operational sequence resumes without requiring a total system reset when power is restored.

Programmed interlocks are also provided that which will prevent drum venting under the following conditions:

- a. any of the containment silo access doors are open
- b. a drum is not positioned at the vent station
- c. any of the containment silo ventilation systems are not operating

The following control interfaces are also provided:

- a. an emergency stop button
- b. ventilation system fans control switches
- c. ventilation system HEPA filters differential pressure gauges
- d. a graphic display panel with operational status indicating lights

6.3 LOS ALAMOS NATIONAL LABORATORY (LANL)

Los Alamos National Laboratory in a joint venture with Sandia are in the process of developing a portable drum venting and head gas sampling equipment. They do have an stationary drum venting system at present and the operational sequence is as described in the following paragraphs.

A drum is placed on the drum lift which elevates the drum such that the drum lid seals against the gasket of the sealed containment unit. The filter insertion assembly is then lowered until it seals into the sealed containment unit and before the filter makes contact on the drum lid. The sealed containment unit is then evacuated through the sample/purge line.

After the sealed containment unit is evacuated, the filter insertion assembly is then lowered again such that the filter will pierce the drum lid and liner. With the filter partially inserted in the drum, the gases in the drum headspace and liner are then sampled. The drum's free volume is evacuated if hydrogen is present. It is then backfilled with nitrogen until the hydrogen is removed.

After purging, the self-tapping filter is screwed into the drum lid to a specified torque value. The filter insertion machine then releases the filter and travels back to its raised position.

6.4 WHC PROJECT W-113 CVS CONCEPTUAL EQUIPMENT DESIGN

The trailer-mounted drum venting and head gas sampling system will be located in the trench near the module being retrieved. The drum venting equipment will consist of a drum enclosure, drum piercing and sampling devices, and gas filtering assemblies.

The drum enclosure will be heavy-walled to contain a design basis explosion. A sliding, rotating table will move out to accept a drum which will be put in place by a forklift. The table will then pushed back into the

enclosure. The sampling process will then begin as soon as the drum enclosure door is closed and locked.

The drum enclosure ventilation system will activate and pull any gases that come from the drum. The gases will pass through a charcoal and HEPA filtered ventilation system before being discharged into the Trench Enclosure Building. This will assure that the VOCs gases and particulates discharges conforms to regulatory levels. All gases will be monitored by an alpha CAM, a beta CAM, and a gamma detector before discharge.

The insertion of the drum head non-sparking metal punch into the drum is done by a pneumatic cylinder, in order to reduce sparking dangers. The gas sample will be drawn through the head punch to the gas analysis equipment.

If the gas mixture as determined by analysis is flammable, the drum will be purged with an inert gas until the gas mixture is below its lower flammability limit. After purging, the drum head punch is retracted, leaving the head punch behind. The drum is then rotated 90 degrees in order to insert the filter cartridge into the head punch.

The gas analysis room will be a closed, ventilated room but a window in the wall over looking the drum venting equipment will allow the operator to view the venting operations. The venting and sampling controls along with the analysis equipment will be inside this room. The analysis equipment will be plumbed directly to the drum venting equipment to eliminate the possibility of a mix-up with previous samples.

The system will be computer controlled with minimal operator assistance. Process monitoring and alarms will be displayed on the control panel. One archive sample will be drawn and put in storage. All data will be recorded in a computer data base for inclusion in SWITS.

6.5 SAVANNAH RIVER LABORATORY (SRL)

The Savannah River DOE site are in the initial stages of developing their drum venting and gas sampling equipment. Some of their engineers came to see the demonstration of the existing WHC pilot retrieval project CVS equipment operation last December 8, 1992. There is not enough available information with regards to the SRL drum venting and head gas sampling equipment that can be discussed in this engineering study report.

7.0 DISCUSSION OF ALTERNATIVE SYSTEMS

These are some of the alternative drum venting and head gas sampling systems that were considered for determining the method of implementation of definitive design:

7.1 WHC PILOT RETRIEVAL CVS "AS-IS" DESIGN

This alternative system design will make used of the existing design "as-is" with only the addition of an on-line VOCs gas monitor for determining

qualitatively the VOCs concentration, if it equals or exceeds 500 ppm. Flammability testing will also be included.

1. Make provision only for collecting archive gas samples in cylinders and send samples to an off-site laboratory for further analysis, when the VOCs concentration equals or exceeds 600 ppm.

NOTE: Possible consequences of using this alternative:

- a. This has the potential of causing a process bottleneck in the retrieval process.
- b. Also, there is the possibility of gas samples having the following composition which may deteriorate with time if stored in a cylinder:
 - hydrogen in the gas sample
 - moisture in the gas sample
 - samples with components present in amounts less than 20 ppm
2. Make provision only for manually inserting the filter after the gas purging and the overpacked 55-gallon drum already outside the heavy-walled enclosure. **NOTE:** This has the potential of exposing the operator to the toxic gases that might still be present, since there is no requirement for total evacuation of the toxic gases prior to the inert gas purging.

7.2 WHC PILOT RETRIEVAL CVS "MODIFIED" DESIGN

This alternative system design will incorporate existing design features of the various DOE sites and the Project W-113 conceptual design into the WHC pilot retrieval project CVS design. A performance specification will be then written for the fabrication of the equipment with most of the instrumentations systems to be government furnished equipment GFE. Fabrication may be by WHC or contracted to off-site manufacturer. **NOTE:** This is the preferred alternative method of definitive design for the Project W-113 drum venting and head gas sampling equipment. Completion of the CVS development to meet W-113 needs should be accomplished by an integrated efforts by W-113 projects with WHC Central Engineering and Solid Waste Management.

7.3 WHC ONSITE MOBILE "GRAB SAMPLE" ANALYTICAL LABORATORY

This alternative system design will make use of a mobile analytical laboratory, similar to the ones recently purchased by the WHC Mobile Environmental Lab Project. Locate it nearby the Trench Enclosure Building. Grab samples will be taken to this laboratory for further analysis. Its similar in concept to Alternative #7.1, except the laboratory is on-site and consists of the following: **NOTE:** This has the potential of an increase in Project W-113 project scope and cost, mainly, on the support utilities that needs to be brought to the on-site laboratory facility.

1. Sample Preparation Lab: Samples to be analyzed are tagged and logged into the laboratory information management system which keeps track of tests done to a particular sample and the

corresponding results. The lab can also store data in the Hanford Environmental Information System. The samples undergo a radiation screening to detect any alpha, beta or gamma radiation. Next, they're broken down into subsamples for the various analytical analyses.

2. Analytical Lab: The subsamples from the sample preparation lab are then taken to the analytical lab for more in-depth analysis.
3. Lunchroom/Change Room Facility: Used by the laboratory personnel.

8.0 REFERENCES

Kent's Mechanical Engineer's Handbook Power Volume, 12th Edition,
December 1962

NFPA 77, *Recommended Practices on Static Grounding*, 1988 Edition.

SRL-MNT-91373, *TRU Waste Drum Recovery Alternative Design for Vent/Purge & Drum Opening*, November 21, 1991.

U.S. Department of Health and Human Services, *NIOSH Pocket Guide to Chemical Hazards*, June 1990.

WHC-SD-W113-CDR-002, *Conceptual Design Report For Solid Waste Retrieval Facility, Project W113*, Rev. 0, October 9, 1992.

WHC-SD-W113-FDC-001, *Solid Waste Retrieval Project W113 Functional design Criteria*, Rev 1, April 13, 1992.

APPENDIX A: SKETCHES

- Sketch #1: Proposed Project W-113 Drum Venting and Head Gas Sampling System Process Diagram**
- Sketch #2: Proposed Project W-113 Hydrogen Gas Monitoring System**
- Sketch #3: Proposed Project W-113 Vent Gases Monitoring System**
- Sketch #4: INEL Drum Venting System**
- Sketch #5: INEL Filter Assembly Design**
- Sketch #6: INEL Punch Head Assembly**
- Sketch #7: LANL Drum Venting System**
- Sketch #8: LANL Filter Insertion Assembly Detail**
- Sketch #9: LANL Alternate Piercing Filter Designs**
- Sketch #10: LANL Pressure Vessel Containment**
- Sketch #11: WHC Pilot Retrieval Demonstration Drum Venting System**
- Sketch #12: WHC Pilot Retrieval Demonstration Drum Venting System**
- Sketch #13: Proposed Project W-113 Drum Piercing Device**
- Sketch #14: Project W-113 CVS Conceptual Design**

[illegible]

Sketch #2: Proposed Project W-113 Hydrogen Gas Monitoring System

Sketch #3: Proposed Project W-113 Vent Gases Monitoring System

Sketch #4: INEL Drum Venting System

INEL FILTER INSERTION MACHINE (modified)

Sketch #5: INEL Filter Assembly Design

Carbon-bonded filter assembly.

Sketch #6: INEL Punch Head Assembly

Sketch #7: LANL Drum Venting System

Sketch #8: LANL Filter Insertion Assembly Detail

LANL FILTER INSERTION ASSEMBLY DETAIL
(SHOWN DURING SAMPLE/PURGE OPERATION)

Sketch #9: LANL Alternate Piercing Filter Designs

SELF TAPPING FILTER

RIVET TYPE FILTER

LANL ALTERNATE PIERCING FILTER DESIGNS

Sketch #10: LANL Pressure Vessel Containment

Sketch #11: WHC Pilot Retrieval Demonstration Drum Venting System

HANFORD CONTAINER VENTING SYSTEM

Sketch #12: WHC Pilot Retrieval Demonstration Drum Venting System

Sketch #13: Proposed Project W-113 Drum Piercing Device

Sketch #14: Project W-113 CVS Conceptual Design

APPENDIX B: CALCULATIONS

The heavy-walled enclosure shall be capable of containing a worst case explosion of a drum during the venting operation, on a stoichiometric mixture of hydrogen and oxygen at 20 psig internal pressure in an otherwise empty drum.

The drum can be considered as a thin-walled cylinder, since the ratio of the thickness to the internal diameter (t/D) of the cylinder is small in the ratio of (1/10) or less.

Two (2) types of stresses, with directions perpendicular to each other exists in the drum:

1. hoop or tangential stress (St), due to the internal pressure (p) acting on the walls of the drum
2. transverse or longitudinal stress (Sl), due to the internal pressure (p) acting on the ends of the drum

NOTE: The dimensions of a 55-gallon drum are:

- a. inside diameter (D) = 22.5 inches
- b. overall height (L) = 34.185 inches
- c. Thickness (t) = #16 Gauge = 0.0533 inches

HOOP OR TANGENTIAL STRESS: The force (F) tending to separate two (2) halves of the drum is equal to the internal (p) times the internal diameter (D) times the overall height (L), therefore:

$$\begin{aligned}(F) &= (p) * (D) * (L) \\ &= (20) * (22.5) * (34.185) \\ (F) &= 15,383 \text{ lbs.}\end{aligned}$$

This force is resisted by the tangential stress (St) acting uniformly over the stressed area, therefore:

$$\begin{aligned}(p) * (D) &= (2) * (t) * (St) \\ (St) &= (p * D) / (2 * t) \\ &= (20 * 22.5) / (2 * 0.0533) \\ (St) &= 4,221 \text{ psi}\end{aligned}$$

Tensile yield strength of A36 carbon steel = 36,000 psi

Allowable working yield strength = 60% of 36000 psi = 21,600 psi

TRANSVERSE OR LONGITUDINAL STRESS: The force (F) acting on the two (2) ends of the drum is equal to the internal pressure (p) times the projected area (A) of the ends which is equal to $((3.14) * (\text{square of internal diameter } (D) / 4))$, therefore:

$$\begin{aligned}(F) &= (20) * ((3.14 * 22.5 * 22.5) / (4)) \\ &= (20) * (397) \\ (F) &= 7940 \text{ lbs}\end{aligned}$$

NOTE: Each of the pneumatic clamping and sealing cylinders should have the capacity of resisting a force equal to $(F) = (7940/7) = 1135 \text{ lbs.}$ Pneumatic cylinders based on their bore size have a listed push force factor, which if multiplied by the air line pressure of 90 psig will

give the push exerted in pounds. The pneumatic cylinder bore size calculated push exerted in pounds should not be less than 1135 lbs.

This force (F) is equated to the longitudinal stress (St) times the area (A), over which it acts which is equal to $((3.14) * \text{internal diameter (D)} * \text{thickness (t)})$, therefore

$$\begin{aligned}(S1) &= (p * D) / (4 * t) \\&= ((20 * 22.5) / (4 * 0.0533)) \\&= (450) / (0.2132) \\(S1) &= 2120 \text{ psi}\end{aligned}$$

Tensile yield strength of A36 carbon steel = 36,000 psi

Allowable working yield strength = 60% of 36000 psi = 21,600 psi

NOTE: The results of the calculations indicates that a 55-gallon drum without any structural defect could withstand the explosion based on a stoichiometric mixture of hydrogen and oxygen at 20 psig internal pressure in an otherwise empty drum. However, the top lid could possibly be blown upward without the clamping and sealing cylinders.

APPENDIX C: ENGINEERING DEVELOPMENT WORK ESTIMATES**COST ESTIMATES**

The total estimated cost breakdown required to develop the drum venting and gas sampling system for the mock and testing as described in this engineering study report are:

1. HNU INSTRUMENTATION

a.	CVS Equipment Modifications.....	\$ 10,000.00
b.	Hydrogen Gas Monitoring Instrumentation.....	\$ 10,000.00
c.	VOCs Gas Analyzing Instrumentation.....	\$ 25,000.00
d.	Gas Mixtures Flammability Test Equipment.....	\$ 1,000.00
e.	Vent Gases (GAMMA) Monitoring Instrumentation.....	\$ 8,000.00
f.	Engineering Design.....	\$ 50,000.00
g.	Shop Fab./Assembly on a Skid Only (No Trailer).....	\$ 50,000.00
h.	Mockup/Testing Demonstration.....	\$ 10,000.00
i.	Test Report/Recommendations.....	\$ 10,000.00

GRAND TOTAL.....\$174,000.00

2. HEWLETT PACKARD INSTRUMENTATION

a.	Change Item "c" to.....	\$80,000.00
----	-------------------------	-------------

GRAND TOTAL.....\$229,000.00

3. FTIR/RAMAN INSTRUMENTATION

a.	Change Item "c" to.....	\$100,000.00
----	-------------------------	--------------

b.	Delete Item "b".....	(-) \$10,000.00
----	----------------------	-----------------

GRAND TOTAL.....\$239,000.00

SCHEDULE**ACTIVITY:****SCHEDULE:**

1.	Definition of design requirements.....	October 1992 - March 1993
2.	Procurement of Instrumentation Systems....	July - September 1994
3.	Fabrication/Modification.....	October - December 1994
4.	System Mockup Testing.....	January - March 1995
5.	System Performance Specification.....	April - July 1995
6.	Design/Built.....	August 1995 - January 1996
7.	Final System Testing.....	February - April 1996

APPENDIX D: OTHER DATA

LOWER AND UPPER EXPLOSIVE LIMITS IN AIR, % BY VOLUME (AT ROOM TEMPERATURE, UNLESS NOTED OTHERWISE)

1. HEAD GASES

- a. Carbon Monoxide: 12.5% LEL, 74% UEL, flammable gas
- b. Hydrogen: 4.00% LEL, 74% UEL, combustible gas
- c. Methane: 5.00% LEL, 15% UEL, flammable gas
- d. Ethane: 3.10% LEL, 12.5% UEL, flammable gas
- e. Propane: 2.1% LEL, 9.5% UEL, flammable gas

2. VOLATILE ORGANIC COMPOUNDS

- a. Acetone: 2.5% LEL, 13% UEL, Class 1B flammable liquid
- b. Benzene: 1.3% LEL, 7.9% UEL, Class 1B flammable liquid
- c. Bromoform: (NA)% LEL, (NA)% UEL, noncombustible liquid
- d. Butanol: 1.4% LEL, 11.2% UEL, Class 1C flammable liquid
- e. 2-Butanone: 1.4% LEL @200 deg.F, 11.4% UEL @200 deg.F, Class 1B flammable liquid
- f. Carbon tetrachloride: (NA)% LEL, (NA)% UEL, noncombustible liquid
- g. Chlorobenzene: 1.3% LEL, 9.6% UEL, Class 1C flammable liquid
- h. Chloroform: (NA)% LEL, (NA)% UEL, noncombustible liquid
- i. Cyclohexane: 1.3% LEL, 8% UEL, Class 1A flammable liquid
- j. 1,1-Dichloroethane: 5.6% LEL, 16% UEL, Class 1B flammable liquid
- k. 1,2-Dichloroethane: 6.2% LEL, Class 1B flammable liquid
- l. 1,1-Dichloroethene: 6.5% LEL, 15.5% UEL
- m. cis-1,2-Dichloroethene: 5.6% LEL, 12.8% UEL, Class 1B flammable liquid
- n. Ethyl benzene: 1.0% LEL, 6.7% UEL, Class 1B flammable liquid
- o. Ethyl ether: 1.9% LEL, 36% UEL, Class 1A flammable liquid
- p. Methanol: 6.0% LEL, 36% UEL, Class 1B flammable liquid
- q. Methylene chloride: 14% LEL, 22% UEL, combustible liquid
- r. 4-Methyl-2-pentanone: 1.2% LEL @200 deg.F, 8.0% UEL @200 deg.F Class 1B flammable liquid
- s. Nitro benzene: 1.8% LEL (@200F), (?) % UEL, Class IIIA combustible liquid
- t. 1,1,2,2-Tetrachloroethane: (NA) % LEL, noncombustible liquid
- u. Tetrachloroethane: (NA) % LEL, noncombustible liquid
- v. Toluene: 1.2% LEL, 7.1% UEL, Class 1B flammable liquid
- w. 1,1,2-Trichloroethane: (NA) % LEL, noncombustible liquid
- x. Trichloroethylene: 8% LEL (@77F), 10.5% UEL (@77F), Class 1C flammable liquid
- y. 1,1,2-Trichloro-1,2,2-Trifluoroethane: (NA) % LEL, noncombustible liquid at ordinary temperature
- z. 1,3,5-Trimethylbenzene: (NA) % LEL
- z1. 1,2,4-Trimethylbenzene: 0.9 % LEL, 6.4% UEL
- z2. m-Xylene: 1.00% LEL, 7.0% UEL, Class 1C flammable liquid
- z3. o-Xylene: 1.10% LEL, 7.0% UEL, Class 1B flammable liquid
- z4. p-Xylene: 1.10% LEL, 7.0% UEL, Class 1C flammable liquid

THE FOLLOWING OSHA CRITERIA (29 CFR 1910.106) WERE USED TO CLASSIFY FLAMMABLE OR COMBUSTIBLE LIQUIDS

- a. Class 1A flammable liquids: Fl.P. at 73 deg.F and B.P. below 100 deg.F
- b. Class 1B flammable liquids: Fl.P. at 73 deg.F and B.P. at or above 100 deg.F
- c. Class 1C flammable liquids: Fl.P. at or above 73 deg.F and B.P. below 100 deg.F.
- d. Class II combustible liquids: Fl.P. at or above 100 deg.F and B.P. below 140 deg.F.
- e. Class IIIA combustible liquids: Fl.P. at or above 140 deg.F and below 200 deg.F.
- f. Class IIIB combustible liquids: Fl.P. at or above 200 deg.F.

Permissible Exposure Limit (PEL) Per 1989 Air Contaminants (Title 29 Code of Federal Regulations Part 1910.1000)**1. HEAD GASES**

Carbon Monoxide: 25 - 40 ppm; Hydrogen: NA; Methane: NA; Ethane: NA;
Propane: 1000 - 1800 ppm

2. VOLATILE ORGANIC COMPOUNDS

Acetone: 750 - 1800 ppm; Benzene: 1 - 3 ppm; Bromoform: 0.5 - 5 ppm;
Butanol: 100 - 300 ppm; 2-Butanone: 200 - 590 ppm; Carbon tetrachloride:
2 - 12.6 ppm; Chlorobenzene: 75 - 350 ppm; Chloroform: 2 - 9.78 ppm;
Cyclohexane: 300 - 1050 ppm; 1,1-Dichloroethane: 100 - 400 ppm; 1,2-
Dichloroethane: 50 - 202 ppm; 1,1-Dichloroethene: (???) ppm; cis-1,2-
Dichloroethene: 200 - 790 ppm; Ethyl benzene: 100 ppm; Ethyl ether: 400
- 1200 ppm; Methanol: 200 ppm; Methylene chloride: 500 - 1740 ppm; 4-
Methyl-2-pentanone: 50 - 205 ppm; Nitro benzene: 1 - 5 ppm; 1,1,2,2-
Tetrachloroethane: 1 - 7 ppm; Tetrachloroethane: Carcinogen; Toluene:
100 - 375 ppm; 1,1,2-Trichloroethane: 10 - 45 ppm; Trichloroethylene :
50 - 270 ppm; 1,1,2-Trichloro-1,2,2-Trifluoroethane : 1000 - 7600 ppm;
1,3,5-Trimethylbenzene: 25 - 35 ppm; 1,2,4-Trimethylbenzene:(???)ppm; m-
Xylene : 100 - 435 ppm; o-Xylene: 100 - 435 ppm; p-Xylene: 100 - 435 ppm

CORROSIVE LIQUIDS AND FUMES

Acetone; Butanol; Carbon Dioxide; Carbon Tetrachloride;
Methanol; Hydrocarbons (Aliphatic: Ethane & Methane); Methylene Chloride;
Nitrobenzene; Trichloroethylene; Hydrocarbons (Aromatic): o-Xylene; m-
Xylene; p-Xylene; Ethyl benzene; Terachloroethylene; Toluene;
Trichloroethane

HEAD GAS LISTING BY eV NUMBERS**1. HEAD GASES**

Carbon Monoxide : 14.01 eV; Hydrogen: 15.4 eV; Methane: 12.98 eV;
Ethane: 11.06 eV; Propane : 11.07 eV

VOCs listing by Ionization Potential Number**1. HALOCARBONS METHANOL AND OTHER SINGLE C COMPOUNDS: 11.7 eV to 10.2 eV, for greater selectivity a 11.7 eV PID lamp is recommended**

Carbon tetrachloride: 11.47 eV; Chloroform: 11.42 eV; 1,1-Dichloroethane: 11.06 eV; 1,2-Dichloroethane: 11.05 eV; Methanol: 10.84 eV; Methylene chloride: 11.32 eV; 1,1,2,2-Tetrachloroethane: 11.10 eV; 1,1,2-Trichloroethane: 11.00 eV; 1,1,2-Trichloro-1,2,2-Trifluoroethane: 11.99 eV

2. VINYL CHLORIDE MEK MIBK TCE AND OTHER 2-4C COMPOUNDS: 10.2 eV to 9.5 eV, for greater selectivity a 10.2 eV PID lamp is recommended

Bromoform: 10.48 eV; Butanol: 10.04 eV; Ethyl ether: 9.53 eV; 2-Butanone: 9.54 eV; Cyclohexane: 9.88 eV; Acetone: 9.69 eV; Nitro benzene: 9.92 eV; 1,1-Dichloroethene (1,1-Dichloroethylene): 9.65 eV; cis-1,2-Dichloroethene (1,2-Dichloroethylene): 9.65 eV

3. AROMATICS AND LARGE MODULES: 9.5 eV and below, for greater selectivity a 9.5 eV PID lamp is recommended

m-Xylene: 8.56 eV; o-Xylene: 8.56 eV; p-Xylene: 8.44 eV; Toluene: 8.82 eV; Trichloroethylene : 9.45 eV; Tetrachloroethane: 9.32 eV; Chlorobenzene: 9.07 eV; 4-Methyl-2-pentanone: 9.30 eV; Ethyl benzene: 8.76 eV; Benzene : 9.24 eV; Nitrogen Oxides: 9.27 eV; 1,2,4-Trimethylbenzene: 9.24 eV; 1,3,5-Trimethylbenzene: 9.24 eV

4. None of the listed VOCs has an eV of 8.3 or below.**PPM CALCULATIONS BASED ON DRUM FREE VOLUME**

NOTE: Drum free volume based on a 55-gallon drum , 23" dia. x 34" high =
0.208 cu.m = 0.272 cu.yd = 208 liters = 7.35 cu.ft

1. HEAD GASES

COLUMN #1: 55-gallon drum

COLUMN #2: 75 ml sample bottle

Carbon Monoxide: 1PPM = 1.83 mg/cu.m = 0.24 mg/drum = 0.00008 mg/bottle

500 PPM = 120 mg/drum (0.58 mg/l)

500 PPM = 0.04 mg/bottle

600 PPM = 144 mg/drum (0.70 mg/l)

600 PPM = 0.05 mg/bottle

2000 PPM = 480 mg/drum (2 mg/l)

2000 PPM = 0.15 mg/bottle

Hydrogen: 1PPM = 0.045 mg/cu.m = 0.009 mg/drum = 0.000004 mg/bottle

500 PPM = 0.045 mg/drum (0.0003 mg/l)	500 PPM = 0.00002 mg/bottle
600 PPM = 0.054 mg/drum (0.0003 mg/l)	600 PPM = 0.00002 mg/bottle
2000 PPM = 18 mg/drum (0.1 mg/l)	2000 PPM = 0.008 mg/bottle

Methane: 1PPM = 0.714 mg/cu.m = 0.15 mg/drum = 0.00005 mg/bottle

500 PPM = 75 mg/drum (0.35 mg/l)	500 PPM = 0.03 mg/bottle
600 PPM = 90 mg/drum (0.42 mg/l)	600 PPM = 0.032 mg/bottle
2000 PPM = 300 mg/drum (1.4 mg/l)	2000 PPM = 0.11 mg/bottle
7000 PPM = 1.05 g/drum (4.9 mg/l)	7000 PPM = 0.38 mg/bottle
60000 PPM = 9 g/drum (42 mg/l)	60000 PPM = 3.15 mg/bottle

Ethane: 1PPM = 1.34 mg/cu.m = 0.28 mg/drum = 0.000075 mg/bottle

500 PPM = 140 mg/drum (0.5 mg/l)	500 PPM = 0.0375 mg/bottle
600 PPM = 168 mg/drum (0.6 mg/l)	600 PPM = 0.045 mg/bottle
2000 PPM = 560 mg/drum (2 mg/l)	2000 PPM = 0.015 mg/bottle
4000 PPM = 1.12 g/drum (4 mg/l)	4000 PPM = 0.3 mg/bottle
40000 PPM = 11.2 g/drum (40 mg/l)	40000 PPM = 3.0 mg/bottle

Propane: 1PPM = 1.83 mg/cu.m = 0.38 mg/drum = 0.00015 mg/bottle

500 PPM = 190 mg/drum (0.91 mg/l)	500 PPM = 0.068 mg/bottle
600 PPM = 228 mg/drum (1.09 mg/l)	600 PPM = 0.082 mg/bottle
2000 PPM = 760 mg/drum (4 mg/l)	2000 PPM = 0.30 mg/bottle
3000 PPM = 1.14 g/drum (6 mg/l)	3000 PPM = 0.45 mg/bottle

VOLATILE ORGANIC COMPOUNDS

COLUMN #1: 55-gallon drum

COLUMN #2: 75 ml sample bottle

Acetone: 1PPM = 2.42 mg/cu.m = 0.50 mg/drum = 0.00014 mg/bottle

500 PPM = 250 mg/drum (1.2 mg/l)	500 PPM = 0.071 mg/bottle
600 PPM = 300 mg/drum (1.44 mg/l)	600 PPM = 0.101 mg/bottle
2000 PPM = 1 g/drum (4 mg/l)	2000 PPM = 0.28 mg/l
20000 PPM = 10 g/drum (40 mg/l)	20000 PPM = 3.00 mg/l

Benzene: 1PPM = 3.25 mg/cu.m = 0.68 mg/drum = 0.0002 mg/bottle

500 PPM = 338 mg/drum (1.63 mg/l)	500 PPM = 0.0114 mg/bottle
600 PPM = 406 mg/drum (1.96 mg/l)	600 PPM = 0.137 mg/bottle
2000 PPM = 1.36 g/drum (6 mg/l)	2000 PPM = 0.42 mg/bottle
15000 PPM = 10.2 g/drum (45 mg/l)	15000 PPM = 3.38 mg/bottle

Bromoform: 1PPM = 10.51 mg/cu.m = 2.18 mg/drum = 0.0007 mg/bottle

500 PPM = 1.09 g/drum (5.25 mg/l)	500 PPM = 0.368 mg/bottle
600 PPM = 1.31 g/drum (6.3 mg/l)	600 PPM = 0.441 mg/bottle
2000 PPM = 4.36 g/drum (20 mg/l)	2000 PPM = 1.4 mg/bottle
4000 PPM = 8.72 g/drum (40 mg/l)	4000 PPM = 3.00 mg/bottle

Butanol: 1PPM = 3.08 mg/cu.m = 0.64 mg/drum = 0.0002 mg/bottle

500 PPM = 320 mg/drum (1.53 mg/l)
600 PPM = 384 mg/drum (1.84 mg/l)
2000 PPM = 1.28 g/drum (6 mg/l)
15000 PPM = 9.6 g/drum (45 mg/l)

500 PPM = 0.107 mg/bottle
600 PPM = 0.037 mg/bottle
2000 PPM = 0.42 mg/bottle
15000 PPM = 3.38 mg/bottle

2-Butanone: 1PPM = 3.00 mg/cu.m = 0.624 mg/drum = 0.070 mg/bottle

500 PPM = 312 mg/drum (1.5 mg/l)
600 PPM = 374 mg/drum (1.8 mg/l)
2000 PPM = 1.25 g/drum (6 mg/l)
15000 PPM = 9.38 g/drum (45 mg/l)

500 PPM = 0.105 mg/bottle
600 PPM = 0.126 mg/bottle
2000 PPM = 0.42 mg/bottle
15000 PPM = 3.38 mg/bottle

Carbon tetrachloride: 1PPM = 6.39 mg/cu.m = 1.33 mg/drum = 0.0004 mg/bottle

500 PPM = 665 mg/drum (3.2 mg/l)
600 PPM = 798 mg/drum (3.8 mg/l)
1000 PPM = 1.33 g/drum (6 mg/l)
2000 PPM = 2.66 g/drum (12 mg/l)
8000 PPM = 10.64 g/drum (48 mg/l)

500 PPM = 0.0224 mg/bottle
600 PPM = 0.0076 mg/bottle
1000 PPM = 0.42 mg/bottle
2000 PPM = 0.84 mg/bottle
8000 PPM = 3.6 mg/bottle

Chlorobenzene: 1 PPM = 4.68 mg/cu.m = 0.97 mg/drum = 0.00035 mg/bottle

500 PPM = 486 mg/drum (2.34 mg/l)
600 PPM = 583 mg/drum (2.8 mg/l)
1200 PPM = 1.17 g/drum (5.6 mg/l)
8000 PPM = 7.76 g/drum (40 mg/l)

500 PPM = 0.01638 mg/bottle
600 PPM = 0.196 mg/bottle
1200 PPM = 0.392 mg/bottle
8000 PPM = 2.8 mg/bottle

Chloroform: 1PPM = 4.96 mg/cu.m = 1.03 mg/drum = 0.00038 mg/bottle

500 PPM = 516 mg/drum (2.48 mg/l)
600 PPM = 619 mg/drum (2.98 mg/l)
1000 PPM = 1.03 g/drum (5 mg/l)
2000 PPM = 2.060 g/drum (10 mg/l)
8000 PPM = 8.24 g/drum (40 mg/l)

500 PPM = 0.19 mg/bottle
600 PPM = 0.22 mg/bottle
1000 PPM = 0.38 mg/bottle
2000 PPM = 0.75 mg/bottle
8000 PPM = 3.0 mg/bottle

Cyclohexane: 1PPM = 3.50 mg/cu.m = 0.73 mg/drum = 0.0003 mg/bottle

500 PPM = 364 mg/drum (1.75 mg/l)
600 PPM = 436 mg/drum (2.1 mg/l)
1500 PPM = 1.09 g/drum (5.25 mg/l)
2000 PPM = 1.46 g/drum (8 mg/l)
10000 PPM = 7.3 g/drum (40 mg/l)

500 PPM = 0.13 mg/bottle
600 PPM = 0.16 mg/bottle
1500 PPM = 0.39 mg/bottle
2000 PPM = 0.60 mg/bottle
10000 PPM = 3.00 mg/bottle

1,1-Dichloroethane: 1PPM = 4.12 mg/cu.m = 0.86 mg/drum = 0.0003 mg/bottle

500 PPM = 428 mg/drum (2.06 mg/l)
600 PPM = 514 mg/drum (2.5 mg/l)
1500 PPM = 1.29 g/drum (6 mg/l)
2000 PPM = 1.72 g/drum (8 mg/l)
10000 PPM = 8.6 g/drum (40 mg/l)

500 PPM = 0.15 mg/bottle
600 PPM = 0.19 mg/bottle
1500 PPM = 0.45 mg/bottle
2000 PPM = 0.60 mg/bottle
10000 PPM = 3.00 mg/bottle

1,2-Dichloroethane: 1PPM = 4.11 mg/cu.m = 0.86 mg/drum = 0.0003 mg/bottle

500 PPM = 428 mg/drum (2.06 mg/l)	500 PPM = 0.15 mg/bottle
600 PPM = 514 mg/drum (2.5 mg/l)	600 PPM = 0.19 mg/bottle
1500 PPM = 1.29 g/drum (6 mg/l)	1500 PPM = 0.45 mg/bottle
2000 PPM = 1.72 g/drum (8 mg/l)	2000 PPM = 0.6 mg/bottle
10000 PPM = 8.6 g/drum (40 mg/l)	10000 PPM = 3.00 mg/bottle

1,1-Dichloroethene: 1PPM = 4.03 mg/cu.m = 0.84 mg/drum = 0.0003 mg/bottle

500 PPM = 420 mg/drum (2 mg/l)	500 PPM = 0.15 mg/bottle
600 PPM = 504 mg/drum (2.4 mg/l)	600 PPM = 0.18 mg/bottle
1500 PPM = 1.26 g/drum (6 mg/l)	1500 PPM = 0.45 mg/bottle
2000 PPM = 1.68 g/drum (8 mg/l)	2000 PPM = 0.60 mg/bottle
10000 PPM = 8.4 g/drum (40 mg/l)	10000 PPM = 3.00 mg/bottle

1,2-Dichloroethene: 1PPM = 4.03 mg/cu.m = 0.84 mg/drum = 0.0003 mg/bottle

500 PPM = 420 mg/drum (2 mg/l)	500 PPM = 0.15 mg/bottle
600 PPM = 504 mg/drum (2.4 mg/l)	600 PPM = 0.12 mg/bottle
1500 PPM = 1.26 g/drum (6 mg/l)	1500 PPM = 0.45 mg/bottle
2000 PPM = 1.68 g/drum (8 mg/l)	2000 PPM = 0.60 mg/bottle
10000 PPM = 8.4 g/drum (40 mg/l)	10000 PPM = 3.00 mg/bottle

Ethyl benzene: 1PPM = 4.41 mg/cu.m = 0.92 mg/drum = 0.0003 mg/bottle

500 PPM = 459 mg/drum (2.2 mg/l)	500 PPM = 0.17 mg/bottle
600 PPM = 551 mg/drum (2.64 mg/l)	600 PPM = 0.20 mg/bottle
1500 PPM = 1.38 g/drum (6 mg/l)	1500 PPM = 0.45 mg/bottle
2000 PPM = 1.84 g/drum (8 mg/l)	2000 PPM = 0.60 mg/bottle
10000 PPM = 9.2 g/drum (40 mg/l)	10000 PPM = 3.00 mg/bottle

Ethyl ether: 1PPM = 3.08 mg/cu.m = 0.64 mg/drum = 0.0002 mg/bottle

500 PPM = 320 mg/drum (1.54 mg/l)	500 PPM = 0.12 mg/bottle
600 PPM = 384 mg/drum (1.85 mg/l)	600 PPM = 0.14 mg/bottle
2000 PPM = 1.28 g/drum (6 mg/l)	2000 PPM = 0.45 mg/bottle
12000 PPM = 7.68 g/drum (45 mg/l)	12000 PPM = 3.38 mg/bottle

Methanol: 1PPM = 1.33 mg/cu.m = 0.28 mg/drum = 0.00008 mg/bottle

500 PPM = 138 mg/drum (0.66 mg/l)	500 PPM = 0.05 mg/bottle
600 PPM = 166 mg/drum (0.8 mg/l)	600 PPM = 0.06 mg/bottle
2000 PPM = 560 mg/drum (2 mg/l)	2000 PPM = 0.15 mg/bottle
4000 PPM = 1.12 g/drum (4 mg/l)	4000 PPM = 0.3 mg/bottle
40000 PPM = 11.2 g/drum (40 mg/l)	40000 PPM = 3.00 mg/bottle

Methylene chloride: 1PPM = 3.53 mg/cu.m = 0.73 mg/drum = 0.0003 mg/bottle

500 PPM = 367 mg/drum (1.77 mg/l)	500 PPM = 0.13 mg/bottle
600 PPM = 440 mg/drum (2.12 mg/l)	600 PPM = 0.16 mg/bottle
1500 PPM = 1.1 g/drum (6 mg/l)	1500 PPM = 0.45 mg/bottle
2000 PPM = 1.46 g/drum (8 mg/l)	2000 PPM = 0.60 mg/bottle
10000 PPM = 7.3 g/drum	10000 PPM = 3.00 mg/bottle

4-Methyl-2-pentanone: 1PPM = 4.17 mg/cu.m = 0.87 mg/drum = 0.0003 mg/bottle

500 PPM = 434 mg/drum (2.08 mg/l)	500 PPM = 0.16 mg/bottle
600 PPM = 521 mg/drum (2.5 mg/l)	600 PPM = 0.19 mg/bottle
1500 PPM = 1.31 g/drum (6 mg/l)	1500 PPM = 0.45 mg/bottle
2000 PPM = 1.74 g/drum (8 mg/l)	2000 PPM = 0.60 mg/bottle
10000 PPM = 8.7 g/drum (40 mg/l)	10000 PPM = 3.00 mg/bottle

Nitro benzene: 1PPM = 5.12 mg/cu.m = 1.06 mg/drum = 0.0004 mg/bottle

500 PPM = 532 mg/drum (2.56 mg/l)	500 PPM = 0.192 mg/bottle
600 PPM = 638 mg/drum (3.07 mg/l)	600 PPM = 0.23 mg/bottle
1000 PPM = 1.06 g/drum (5 mg/l)	1000 PPM = 0.38 mg/bottle
2000 PPM = 2.12 g/drum (10 mg/l)	2000 PPM = 0.75 mg/bottle
8000 PPM = 4.24 g/drum (40 mg/l)	8000 PPM = 3.00 mg/bottle

1,1,2,2-Tetrachloroethane: 1PPM = 7.00 mg/cu.m = 1.5 mg/drum = 0.0005 mg/bottle

500 PPM = 728 mg/drum (3.5 mg/l)	500 PPM = 0.03 mg/bottle
600 PPM = 874 mg/drum (4.2 mg/l)	600 PPM = 0.32 mg/bottle
1000 PPM = 1.5 g/drum (7 mg/l)	1000 PPM = 0.53 mg/bottle
2000 PPM = 3 g/drum (14 mg/l)	2000 PPM = 1.05 mg/bottle
6000 PPM = 9 g/drum (42 mg/l)	6000 PPM = 3.15 mg/bottle

Tetrachloroethane: 1PPM = 6.89 mg/cu.m = 1.43 mg/drum = 0.0005 mg/bottle

500 PPM = 716 mg/drum (3.5 mg/l)	500 PPM = 0.26 mg/bottle
600 PPM = 859 mg/drum (4.2 mg/l)	600 PPM = 0.32 mg/bottle
1000 PPM = 1.430 g/drum (7 mg/l)	1000 PPM = 0.53 mg/bottle
2000 PPM = 2.86 g/drum (14 mg/l)	2000 PPM = 1.05 mg/bottle
6000 PPM = 8.58 g/drum (42 mg/l)	6000 PPM = 3.15 mg/bottle

Toluene: 1PPM = 3.83 mg/cu.m = 0.8 mg/drum = 0.0002 mg/bottle

500 PPM = 398 mg/drum (1.92 mg/l)	500 PPM = 0.14 mg/bottle
600 PPM = 478 mg/drum (2.30 mg/l)	600 PPM = 0.17 mg/bottle
1500 PPM = 1.2 g/drum (4.5 mg/l)	1500 PPM = 0.30 mg/bottle
2000 PPM = 1.6 g/drum (6 mg/l)	2000 PPM = 0.45 mg/bottle
15000 PPM = 12 g/drum (45 mg/l)	15000 PPM = 3.38 mg/bottle

1,1,2-Trichloroethane: 1PPM = 5.55 mg/cu.m = 1.15 mg/drum = 0.0005 mg/bottle

500 PPM = 577 mg/drum (2.8 mg/l)	500 PPM = 0.21 mg/bottle
600 PPM = 692 mg/drum (3.4 mg/l)	600 PPM = 0.26 mg/bottle
1000 PPM = 1.15 g/drum (6 mg/l)	1000 PPM = 0.45 mg/bottle
2000 PPM = 2.3 g/drum (12 mg/l)	2000 PPM = 0.9 mg/bottle
8000 PPM = 9.2 g/drum (48 mg/l)	8000 PPM = 3.6 mg/bottle

Trichloroethylene: 1PPM = 5.46 mg/cu.m = 1.14 mg/drum = 0.0004 mg/bottle

500 PPM = 568 mg/drum (2.7 mg/l)	500 PPM = 0.20 mg/bottle
600 PPM = 682 mg/drum (3.2 mg/l)	600 PPM = 0.24 mg/bottle
1000 PPM = 1.14 g/drum (5 mg/l)	1000 PPM = 0.38 mg/bottle
2000 PPM = 2.28 g/drum (10 mg/l)	2000 PPM = 0.75 mg/bottle

8000 PPM = 9.12 g/drum (40 mg/l)

8000 PPM = 3.00 mg/bottle

1,1,2-Trichloro-1,2,2-Trifluoroethane: 1PPM = 7.79 mg/cu.m = 1.62 mg/drum = 0.0006 mg/bottle

500 PPM = 810 mg/drum (3.9 mg/l)

500 PPM = 0.29 mg/bottle

600 PPM = 972 mg/drum (4.7 mg/l)

600 PPM = 0.35 mg/bottle

1000 PPM = 1.62 g/drum (8 mg/l)

1000 PPM = 0.6 mg/bottle

2000 PPM = 3.24 g/drum (16 mg/l)

2000 PPM = 1.2 mg/bottle

5000 PPM = 8.1 g/drum (40 mg/l)

5000 PPM = 3.00 mg/bottle

1,3,5-Trimethylbenzene: 1PPM = 3.25 mg/cu.m = 0.68 mg/drum = 0.0002 mg/bottle

500 PPM = 338 mg/drum (1.63 mg/l)

500 PPM = 0.12 mg/bottle

600 PPM = 406 mg/drum (1.96 mg/l)

600 PPM = 0.15 mg/bottle

1500 PPM = 1.02 g/drum (4.5 mg/l)

1500 PPM = 0.34 mg/bottle

2000 PPM = 1.36 g/drum (6 mg/l)

2000 PPM = 0.45 mg/bottle

12000 PPM = 10.2 g/drum (45 mg/l)

12000 PPM = 3.38 mg/bottle

1,2,4-Trimethylbenzene: 1PPM = 3.25 mg/cu.m = 0.68 mg/drum = 0.0002 mg/bottle

500 PPM = 338 mg/drum (1.63 mg/l)

500 PPM = 0.12 mg/bottle

600 PPM = 406 mg/drum (1.96 mg/l)

600 PPM = 0.15 mg/bottle

1500 PPM = 1.02 g/drum (4.5 mg/l)

1500 PPM = 0.34 mg/bottle

2000 PPM = 1.36 g/drum (6 mg/l)

2000 PPM = 0.45 mg/bottle

12000 PPM = 10.2 g/drum (45 mg/l)

12000 PPM = 3.38 mg/bottle

m-Xylene: 1PPM = 4.41 mg/cu.m = 0.92 mg/drum = 0.0003 mg/bottle

500 PPM = 458 mg/drum (2.2 mg/l)

500 PPM = 0.165 mg/bottle

600 PPM = 550 mg/drum (2.6 mg/l)

600 PPM = 0.20 mg/bottle

1500 PPM = 1.38 g/drum (6 mg/l)

1500 PPM = 0.45 mg/bottle

2000 PPM = 1.84 g/drum (8 mg/l)

2000 PPM = 0.60 mg/bottle

10000 PPM = 9.2 g/drum (40 mg/l)

10000 PPM = 3.00 mg/bottle

o-Xylene: 1PPM = 4.41 mg/cu.m = 0.92 mg/drum = 0.0003 mg/bottle

500 PPM = 458 mg/drum (2.2 mg/l)

500 PPM = 0.165 mg/bottle

600 PPM = 550 mg/drum (2.6 mg/l)

600 PPM = 0.20 mg/bottle

1500 PPM = 1.38 g/drum (6 mg/l)

1500 PPM = 0.45 mg/bottle

2000 PPM = 1.84 g/drum (8 mg/l)

2000 PPM = 0.60 mg/bottle

10000 PPM = 9.2 g/drum (40 mg/l)

10000 PPM = 3.00 mg/bottle

p-Xylene: 1PPM = 4.41 mg/cu.m = 0.92 mg/drum = 0.0003 mg/bottle

500 PPM = 458 mg/drum (2.2 mg/l)

500 PPM = 0.165 mg/bottle

600 PPM = 550 mg/drum (2.6 mg/l)

600 PPM = 0.20 mg/bottle

1500 PPM = 1.38 g/drum (6 mg/l)

1500 PPM = 0.45 mg/bottle

2000 PPM = 1.84 g/drum (8 mg/l)

2000 PPM = 0.60 mg/bottle

10000 PPM = 9.2 g/drum (40 mg/l)

10000 PPM = 3.00 mg/bottle

HEAD GASES AND VOC LISTING BY SP.GR., VAPOR PRESSURE AND FLASH POINT**1. HEAD GASES**

Carbon Monoxide: S.G. = 0.97; Hydrogen: S.G. = 0.07; Methane: S.G. = 0.56; Ethane: S.G. = 1.05; Propane: S.G. = 1.55

2. VOLATILE ORGANIC COMPOUNDS

NOTE: Based on a conversion factor of one (1) atmosphere = 760 torr = 760 mm Hg or one (1) Torr = 0.00132 atmosphere = 0.04 in Hg = 1.0 mm Hg

Acetone: S.G. = 0.79; V.P. = 180 mm; Fl.P. = 0 deg.F
Benzene: S.G. = 0.88; V.P. = 75 mm; Fl.P. = 12 deg.F
Bromoform: S.G. = 2.89; V.P. = 5 mm; Fl.P. = NA
Butanol: S.G. = 0.81; V.P. = 6 mm; Fl.P. = 99 deg. F
2-Butanone: S.G. = 0.81; V.P. = 71 mm; Fl.P. = 16 deg.F
Carbon tetrachloride: S.G. = 1.59; V.P. = 91 mm; Fl.P. = NA
Chlorobenzene: S.G. = 1.11; V.P. = 12 mm @ 77 deg.F; Fl.P. = 85 deg.F
Chloroform: S.G. = 1.48; V.P. = 160 mm; Fl.P. = NA
Cyclohexane: S.G. = 0.78; V.P. = 98 mm @ 77 deg.F; Fl.P. = 0 deg.F
1,1-Dichloroethane: S.G. = 1.18; V.P. = 230 mm @ 77 deg.F; Fl.P. = 22 deg.F
1,2-Dichloroethane: S.G. = 1.24; V.P. = 64 mm
1,1-Dichloroethene: S.G. = 1.21; V.P. = 495 mm @ 20 deg.C
cis-1,2-Dichloroethene: S.G. = 1.27; V.P. = 180 - 264 mm
Ethyl benzene: S.G. = 0.87; V.P. = 10 mm @ 79 deg.F; Fl.P. = 55 deg.F
Ethyl ether: S.G. = 0.71; V.P. = 440 mm; Fl.P. = (-) 49 deg.F
Methanol: S.G. = 0.79; V.P. = 92 mm; Fl.P. = 52 deg.F
Methylene chloride: S.G. = 1.33; V.P. = 350 mm; Fl.P. = (??) deg.F
4-Methyl-2-pentanone: S.G. = 0.80; V.P. = 16 mm; Fl.P. = 64 deg.F
Nitro benzene: S.G. = 1.20; V.P. = 1 mm @ 112 deg.F; Fl.P. = 190 deg.F
1,1,2,2-Tetrachloroethane: S.G. = 1.59; V.P. = 9 mm @ 86 deg.F
Tetrachloroethane: S.G. = 1.46; V.P. = 58 mm; Fl.P. = 90 deg.F
Toluene: S.G. = 0.87; V.P. = 0.01 mm @ 77 deg.F; Fl.P. = 40 deg.F
1,1,2-Trichloroethane: S.G. = 1.44; V.P. = 19 mm; Fl.P. = NA
1,1,2-Trichloro-1,2,2-Trifluoroethane: S.G. = 1.56; V.P. = 54 mm; Fl.P. = (??) deg.F
1,3,5-Trimethylbenzene: S.G. = 0.86; V.P. = 1.86 mm @ 20 deg.C; Fl.P. = 115 deg.F
1,2,4-Trimethylbenzene: S.G. = 0.899; V.P. = 7 mm @ 44.4 deg.C; Fl.P. = 120 deg.F
m-Xylene: S.G. = 0.86; V.P. = 9 mm; Fl.P. = 84 deg.F
o-Xylene: S.G. = 0.88; V.P. = 7 mm; Fl.P. = 63 deg.F
p-Xylene: S.G. = 0.86; V.P. = 9 mm; Fl.P. = 81 deg.F

METHOD OF CALCULATION FOR % LEL OF SIMPLE OR COMPLEX GAS MIXTURES**1. INFLAMMABILITY OF SIMPLE GAS MIXTURES**

The lower and upper limits of inflammability of simple mixtures can be calculated by means of LeChatelier's mixture law, expressed by the equation:

$$L = (100) / ((V1/L1) + (V2/L2) + (V3/L3) + (V4/L4) + \text{etc}))$$

- where V1, V2, V3, V4, etc. are the proportions of each combustible gas (free from air and inerts) expressed in percentage by volume with the sum = 100
- L1, L2, L3, L4, etc are the lower and upper limits of inflammability as the case maybe of each combustible in air and expressed in percentage by volume
- L is the lower and upper limit of the inflammability as the case maybe of the mixture in air

2. INFLAMMABILITY OF COMPLEX GAS MIXTURES

Complex gas mixtures with inert gases can be calculated in which the inerts are combined with the combustible components and the inflammable limits of these combinations are used in place of the limits of the pure gases. Then compute "L" per the equation for simple gas mixtures.

$$L = (100) / ((V1a/L1a) + (V2b/L2b) + (V3c/L3c) + (V4d/L4d) + \text{etc}))$$

- where V1a, V2b, V3c, V4d, etc. are the proportions of each combustible gas present in the mixture plus the inert gas, such that the sum = 100.
- L1a, L2b, L3c, L4d, etc are the sum of the lower and upper limits of inflammability of the inert gas and each combustible in air as the case maybe
- L is the lower and upper limit of the inflammability as the case maybe of the mixture in air.

TYPICAL GAS INTERFERENCE DATA

NOTE: Based on the interference data of a certain manufacturer of gas sensors, for example, 20000 parts of methane will change the sensor detection for hydrogen by one part hydrogen.

1. Acetone: Butanol....8:1; Cyclohexane....2.5:1; Methanol....1:1; Toluene....25:1; Hydrogen....1:1 (%LEL); Methylene chloride....25:1 (%LEL)
2. Benzene: Carbon monoxide....4:1; Hydrogen....1.3:1; Toluene....2.5:1; Xylene....50:1; Methane....100:1; Propane....2:1
3. Toluene: Benzene....1:1; Cyclohexane....1:1; Butanol....2:1; Methylene chloride....800:1; trichloroethylene....8:1; Xylene....2:1
4. Trichloroethylene: Hydrogen....2.5:1; Carbon monoxide....150:1; Methane....20:1
5. Hydrogen: Acetone....2:1; Trichloroethylene....25:1; Benzene....3:1; Carbon monoxide....25:1; Methane....20,000:1
6. Methane: Benzene....16:1; Hydrogen....2:1; Methanol....1.2:1; Toluene....no effect; Xylene.....no effect

APPENDIX B

Waste Characterization

WHC-SD-W113-ACDR-001

Rev. 0

Page 74A

THIS PAGE INTENTIONALLY LEFT BLANK

1.0 GENERAL DESCRIPTION

Project W-113 consists of the equipment, systems and facilities to retrieve the waste containers stored in Burial Ground 218 W-4C, Trench 04, stored as retrievable TRU waste. This trench is located in the 200 West Area running east from Dayton Avenue along the Hanford Site Coordinate North 40070 ft. The waste is contained in units, or modules, generally 12 drums wide, 12 drums long, stacked on the asphalt trench bottom four drums high, with each tier of drums covered with plywood and the sides and the top of the module covered with polyvinyl tarpaulin. There are nineteen modules in this trench in a single row each contiguous with the adjacent modules. The trench was backfilled, and the top of the modules has an overburden of approximately four feet of native soil.

The containers stored in this trench hold waste generated on-site and off-site in the general time frame of early 1978 (the first waste was placed in April) through 1984, with the final four drums placed in March of 1985.

The Hanford generators from whom waste was received in 4C-T04 and the quantities of drums (approximate) and boxes received are:

J.A. Jones	5 Metal Boxes
WHC-308 Bldg	1 Metal Box
324	85 Drums
325	760 "
340	4 Metal Boxes
	210 Drums
PNL-324	15 "
325	330 "
325 A	5 "
340	125 "
209 E	20 "
231 Z	220 "
RHO-202 A	295 "
202 AL	6 "
222 S	7 "
233 S	35 "
234-5 Z	57 L-10 containers (110 gallon drums)
	6575 Drums
2WTF	6 "

Received from off-site generators:

GE-VAL	1 FRP Box
	53 Drums
WEC-WARD	27 Metal Boxes
	349 Drums
BABCOCK	685 "
BATCO	42 "
ESG	49 "
EXXON	1 "

2.0 RADIOLOGICAL DESCRIPTION

It is believed that of all the Hanford waste in the Phase 1 Retrieval trench, only the waste from 202A/AL and 234-5Z received at the trench during 1984 could possibly be contaminated with Pu from N-Reactor spent fuel discharged after the 1972 Purex shutdown (reprocessed after the 1983 PUREX restart). There should be no Pu from 1983 reprocessing (or later) in any of the other waste in the trench. The waste from the Babcock & Wilcox facility at Apollo, PA where mixed oxide cores for the FFTF were fabricated using PuO_2 produced at PFP should contain only pre 1972 reprocessed Pu. Therefore, rather than the majority of the waste being contaminated with plutonium from reprocessed fuel used for power generation (typically about 12% ^{240}Pu), waste will contain contamination from weapons grade plutonium (6% ^{240}Pu) as well as fuels grade plutonium from both N Reactor reprocessed fuel and from reprocessed Al clad slugs from K-Basin, etc.

By the start of Project W-113, circa 1998, the Hanford Plutonium to be retrieved, except possibly the 1984 PUREX or PFP waste receipts, will have aged a minimum of 26 years since "purification" through reprocessing. The "cool down" period from reprocessing for the Plutonium in Trench 4C-04 probably ranges from weeks for fuels reprocessed before PUREX shutdown in 1972 to about 12 years for the waste contaminated with Pu from processing after restart which may have wound up in Trench 04. This is significant mainly for decay of the 15 year half-life ^{241}Pu prior to starting buildup to the current level of its daughter product, ^{241}Am - which was removed when the spent fuel was reprocessed.

N Reactor changed operations from co-generation in 1970 to straight power generation. According to the published fuels reprocessing history for PUREX, none of this fuel was reprocessed prior to the 1972 shutdown. Prior to this period, the reactor was operated for production of fuel grade Pu or for power production (both operations producing Pu with about 12% ^{240}Pu) with the spent fuel stored until PUREX restart. As noted above we assume that only the 1984 waste receipts from PUREX and PFP could contain significant quantities of this 12% ^{240}Pu .

Prior to 1972, among the fuels reprocessed at PUREX were enriched metals and oxides as well as mixed oxide scrap, resulting in a variety of Pu isotopics. Some of these are located in the Phase 1 trench, 4C-04. Waste from PFP containing concentrations by weight of over 12.9% ^{240}Pu (taken from the records of ^{240}Pu greater than 12%) are listed in the storage modules summaries that follow. To date no further breakdowns have been identified for PFP or PUREX.

The 231Z facility (PNL) normal Pu consisted of 6.3% ^{240}Pu and 0.6% ^{241}Pu . The characterization report (WHC-EP-0659) shows that special AEC lease Plutonium (at 22.35% ^{240}Pu and 4.21% ^{241}Pu) and PuO_2 for production of cubes (some also containing high 240 and 241) existed in the facility. The waste from these, however, would have mostly been generated from 1960-1971, with a small amount in 1974. By 1978 none of the waste contaminated with anything other than the normal Pu should exist in anything but the FRP burial boxes containing the equipment used for the earlier operations with the high 240 isotopics. None of these are located in Trench 4C-04. Figure 1 is included to show the

timeline of major Hanford events related to the characterization of Trench 4C-04 wastes.

Because of the various roles of support to the FFTF fuels development and the Breeder Reactor Program from the 300 Area facilities (308, 324, 325, and 340 Buildings), it is assumed that the waste in Trench 4C-04 from these facilities are nominally 12% ^{240}Pu .

The 209E facility (PNL) produced Pu contaminated waste with 9% ^{240}Pu .

The 233S facility waste was from D & D operations in 1979 with plutonium contamination probably from weapons grade material.

It is a reasonable assumption that the remainder of the Hanford waste in the trench, PUREX or PFP related, is a half and half mix of 6% and 12% ^{240}Pu except where specifically noted.

Assuming that all off-site waste in this trench is related to Breeder Reactor fuel production, testing, etc, it should be nominally 12% ^{240}Pu .

About 92% of the containers in Trench 4C-04 were one mrem/hr, or less, surface dose when placed in the trench. Another 5% were 5 mrem/hr. Of the remainder, 2% (213 drums) were between 5 and 25 mrem/hr and there was one drum reading 75 mr/hr with 25 between 100 and 200 mrem/hr (5 at or close to 200 mrem/hr).

Many of the lower readings probably reflect background rather than drum contents, especially for PFP, where investigation has shown that the gamma emitters in the waste are not fission/activation products other than a very small buildup of fission products from spontaneous fission.

For almost all waste from PFP and most waste from PUREX, the gamma radiation should be almost totally from the ingrowth of ^{241}Am as the daughter product from the decay of ^{241}Pu . It is possible that some waste from PFP could be contaminated entirely by Americium from separations processing, and it is probable that some waste from PUREX will be from materials contaminated by direct or indirect contact with liquids or slurries containing fission and activation products as well as Pu. Other on-site and off-site waste containing fission product activity are from hot cell activities in facilities such as the 324 Building at Hanford; the waste consists of contaminated tools, fixtures, cuttings (non-fuel), cladding pieces, and other items associated with irradiated materials examinations, etc.

Nine of the higher dose drums contain lead and concrete shielding.

For the drums containing unmeasurable Pu, it is reasonable to assume that any ingrowth of ^{241}Am will be negligible with respect to increased gamma dose. For drums with high loadings of TRU an increase of a couple mrem/hr surface dose might be expected by the time the drums are retrieved. For drums with the higher dose rates initially, it appears the major contributors to the dose would be fission/activation products, or separated americium. These activities will have been decaying since placement in the trench, and the decay impact on drum dose rates should be greater than ingrowth of americium or fission/activation products from spontaneous fission.

3.0 MODULE DESCRIPTIONS

The following pages contain summaries of each module with data culled from the SWITS data base, the old RSWIMS data, burial records, and burial ground drum location sheets. An attempt was made to reconcile a number of noticeable differences between these sources. However, there still remains an amount of uncertainty concerning duplication of identification numbers, PIN entries with no matching records, locations with more than one drum PIN, and locations with no drum PIN at locations where it is known that drums are located. These are summarized in Appendix A in accordance with the status at the time of preparation of this report. As will be noted in these summary sheets, there are a number of missing data entries that can be made and errors that can be corrected, which will enhance the usability of SWITS as the base planning tool relative to waste location.

In instances where various total TRU quantities from SWITS are significantly less than the quantities derived from RSWIMS and burial records, the RSWIMS data is used. Accordingly, the totals used herein will be generally unverifiable by existing database, but should present a more accurate estimate of the TRU and drum totals. The SWITS data base is assumed to present a mostly accurate compilation of the burial location sheets for the drums included. Although lacking completeness, it provides a good foundation for forthcoming additions and corrections to the data to be garnered during retrieval.

Included with the following module summaries are color coded representations of SWITS data for each module, sketches of each tier of each module showing drum and box arrangements, and selected burial records representative of the data available from the several generators and several unique records of interest. Burial records are also included for all of the boxed waste and waste in 110 gallon drums (L-10 Containers).

Also shown in the Appendix is a compilation for each module showing the number of containers with various ranges of TRU gram loadings. This was taken from SWITS so that the totals tend to fall short due to missing entries in the data base but the percentages should be reasonable for statistical application.

MODULE 1 (West coordinates 77482 to 77509)

Module 1 is the easternmost module in Trench 04 in 218W-4C and will be the last uncovered and retrieved.

Module 1 consists of 720 spaces for 55-gallon drums stacked in a 12 by 12 by 5 high configuration with a partial extra row of eight drums stacked four high on the west face of the module. Module 1 was built during May of 1978 and all drums are assumed to be painted steel.

The burial records show that 234-5Z (Rockwell) Facility generated 573 of the drums of waste in this module containing 1737 grams of plutonium. The 325 Building (WHC) generated 77 drums containing 666 grams of plutonium, 1732 grams of depleted uranium, 5553 grams of natural uranium, 574 grams of enriched uranium, and 1531 grams of thorium. The 325 Building (PNL) generated 16 drums containing 16 grams of plutonium. The 231-Z (PNL) Facility generated 48 drums containing 5 grams of plutonium. The 222-S (Rockwell) Facility generated 4 drums containing 4 grams of plutonium.

The recorded data shows no measurable amount of plutonium (potential TRU only and most of these might actually be non-TRU) for one drum from 222-S, four drums from 325 (Rockwell), 42 drums from 231-Z, and 451 drums from 234-5Z. This makes a total of 498 drums with no measurable quantity of plutonium. There are no hazardous wastes recorded in drums within this Module.

This module contains about 2430 grams plutonium, 1,310 grams uranium, and 1530 grams of thorium. The drum located at position F12 in Tier 5 contains the highest plutonium loading (94 grams).

Recorded contact dose rates vary from a high of 13 mrem/hr for a drum from the 325 Bldg. and 3 mrem/hr for 5 drums, with the rest recorded as 1 mrem/hr or less.

THIS PAGE INTENTIONALLY LEFT BLANK

000000

 $\frac{d}{dt} \Gamma$

十一

20

5

4

11

7

35

1

NO
AL
LL
T
F

1

LL

LL

LL

LL

(1)

110 11000 11000 11000

111

(111)

(111)

(111)

111

(111)

(111)

(111)

(111)

111

(111)

(111)

(111)

(111)

111

(111)

(111)

(111)

(111)

(111)

111

(111)

(111)

(111)

(111)

(111)

111

(111)

(111)

(111)

(111)

111

(111)

(111)

(111)

111

(111)

(111)

(111)

(111)

(111)

TRENCH 4 MODULE 1 TIER 1

1108.501

AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

2 of 8

TRENCH 4 MODULE 1 TIER 2

TRENCH 4 MODULE 1 TIER 3

TRENCH.

MODULE

1

TIER 4

4

TRENCH 4 MODULE 1 TIER 5

TYPICAL WASTE DRUMS

ROCKWELL

234-5Z BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

1 - C 6-NH-Comb C (49)

SOLID WASTE BURIAL RECORD 200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - ERDA BY ATLANTIC RICHFIELD HANFORD COMPANY	<h1 style="font-size: 2em;">#530</h1>
--	---------------------------------------

DISPOSAL SITE THIS SECTION OF FORM TO BE COMPLETED BY ADDED REPRESENTATIVE AT DISPOSAL SITE		ORIGINATOR 234-5-RH0-78-001-12	
AREA 200-W	BURIAL GARDEN NO. 4C	TRENCH NO. 4	PACKAGE NO. Hutchinson
CAISSON NO. Modatic 1	RECORD COORDINATES 46000 = 77508		ERDA AUTHORIZATION NO.
SECTION 1-2	COORDINATES 46000 = 77482		COMPANY Rockwell
REMARKS 40070		BUILDING 234-5	AREA 20020
		ADDRESS (OFF SITE)	
DATE 4-24-78	TIME	I CERTIFY THAT NO CAPITAL PROPERTY IS INCLUDED IN THIS BURIAL RECORD DOCUMENTED BY A PROPERTY DISPOSAL REQUEST AND DESCRIBED BELOW.	
SIGNATURE R W. Cook		SIGNATURE D. Black	11/15/77

PHYSICAL DESCRIPTION

MATERIAL CONTENTS NOTE ANY SPECIAL CONDITIONS (E.G., DISSOLVED, PUMP, SAMPLES OR LABORATORY PAPER WASTE, TIMBER, DEBRIS, INCLUDE THE NUMBERS AND PROPERTY CONTROL NUMBERS)							
55 Gallon waste drums containing bags, plastic, metal, room waste.							
7.77-1A 3101 + 3098 + 3104 + 3103 + 3108 + 3111 + 3106 + 3107							
3109 + 3110 + 3112 + 3102							
B7042 30102 + 30103 + 30104 + 30105 + 30106 + 30107							
CONTAINER	BOX	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD CARDBOARD	
	DRUM	NO. AND SIZE					
	OTHER	NO. AND SIZE 12 - 55 Gallon					
	TOTAL VOLUME (ft³) 88.8						

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPIES SUCH AS Pu, Co, Sr, Cs; USED FISSILE PRODUCTS; ACTIVATION PRODUCTS)			
PK			
PLUTONIUM	URANIUM	ACTIVITY OF Pu OR U. ONLY ENTER IN GRAMS (MICROGRAMS)	
GRAMS	GRAMS	MICROGRAMS	
DOSE RATE		CURIES	
1		☐ DRYFOSS ☐ IRRADIATED ☐ FREE	
DISTRIBUTION	BY SHIPPER	BY ARMC	
WHITE	WITH SHIPPER	WHITE - 5000, 22-2	
YELLOW		YELLOW - DUE TO MATERIALS, 2704-2	
PUR		PUR - RETURN TO SHIPPER	
COLORS - DETAIL			

CB-1-2.4-150 = D-2.1 14 = 2.1 2.1-5-R40-78-001

#630 (49)

Rockwell Hanford Operations					TRANSURANIC DRY WASTE STORAGE				
NON-COMBUSTIBLE MATERIALS					COMBUSTIBLE MATERIALS				
DRUM NO.	GRAMS PU	MEASUREMENT METHOD	OPERATOR	TRENCH	DRUM NO.	GRAMS PU	MEASUREMENT METHOD	OPERATOR	TRENCH
A-3091-0	0	NAI	MEK	C-1	A-3091-0	0	NAI	MEK	D-1-1
A-3092-0	0			C-2	A-3092-0	0			D-1-1
A-3097-0	0			C-3	A-3104-0	0			D-1-1
A-3099-0	0			C-4	A-3103-0	0			D-1-1
A-3092-0	0			C-5	A-3102-0	0			D-1-2
A-3115-0	0			C-6	A-3111-0	0			D-1-1
					7-A-3106-0	0			D-1-2
					8-A-3107-0	0			D-1-1
					9-A-3109-0	0			D-1-1
					10-A-3110-0	0			D-1-1
					11-A-3112-0	0			D-1-1
					12-A-3102-1	1			D-1-1
TRANSFERRED TO ANOTHER									
SHEET # 530A									
CERTIFIED BY: <i>J. Black</i>					DATE: 11/15/77				
DISPOSAL SITE:					DISPOSAL SITE:				
AREA	BURIAL GARDEN NO.	TRENCH NO.			AREA	BURIAL GARDEN NO.	TRENCH NO.		
					200-W	4C	4		
CAISSON NO.	COORDINATES				CAISSON NO.	COORDINATES			
	NORTH:	WEST:			Module 1	NORTH: 4667G	WEST: 77568		
REMARKS:					REMARKS:				
					Serial 1+2 4667G 77568				
SIGNATURE					SIGNATURE				
<i>A. H. Carter</i>					<i>A. W. Carter</i>				
DATE					DATE				
11-15-77					11-15-77				
DRUMS ARE ACCEPTED PER SOP 300.8					DISTRIBUTION:				
SIGNATURE					ALL ACCOMPANY SHIPMENT IF COMPLETED				
<i>A. H. Carter</i>					PINK TO BE RETURNED				
DATE					WHITE & YELLOW WITH SHIPMENT IF NO RETURNED COPY				
11-15-77					DES. REQ.				

TYPICAL DRUMS

ROCKWELL

222-S LABORATORY

THIS PAGE INTENTIONALLY LEFT BLANK

NONE

Combustible 2225 RHT 1902 (44) 4

Atlantic Richfield Hanford Company				ARHCO SOLID WASTE BURIAL RECORD 100 AREA PLATEAU			
DISPOSAL SITE THIS PORTION OF FORM TO BE COMPLETED BY ARHCO REPRESENTATIVE AT DISPOSAL SITE				SHIPPER <u>E 65730</u>			
200-W		BURIAL GARDEN NO. <u>4-C</u>	TRENCH NO. <u>4</u>	SHIPMENT NO. <u>R-78-1, 78-2, 78-3, 78-4</u>		BUILDING <u>222-5</u>	
COORDINATES <u>E 46070 N 77482</u>		F. 72565		COMPANY <u>R.H.O.</u>		ATLANTIC RICHFIELD HANFORD COMPANY	
REMARKS <u>46070</u>				SUBSECTION <u>222-5 LAB</u>		AREA <u>200-W</u>	
SIGNATURE <u>A. E. Fender</u>				DATE <u>5-16-78</u>		SIGNATURE <u>A. E. Schelmer</u>	
DATE				DATE		DATE	
PHYSICAL DESCRIPTION				ACTIVITY			
MATERIAL CONTENTS: IS G. DISSOLVED, PUMP, PROCESS OR LAB WASTE, WASTE, TIMBERS				ACTIVITY DESCRIPTION: IS G. LONG LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs, MILD FISSION PRODUCTS			
<u>Pu. Misc DRY WASTE DRUMS</u>				<u>Pu</u>			
<u>R-78-1, R-78-2, R-78-3, R-78-4</u>							
VOLUME: (SEE BACK FOR FT ³ TABLE)							
CONTAINER	UNIT VOLUME (FT ³)	X	NUMBER	=	TOTAL VOLUME (FT ³)		
222-5 LAB CARDBOARD 10" X 10" X 28"	(1.0)	X		=			
SMALL STD CARDBOARD 16" X 16" X 16"	(2.0)	X		=			
LARGE STD CARDBOARD 16" X 16" X 24"	(4.0)	X		=			
10 GALLON NON DRUM	(6.1)	X		=			
17 GALLON NON DRUM	(8.3)	X		=			
15 GALLON NON DRUM	(7.4)	X	<u>4</u>	=	<u>29.4</u>		
FILL FRACTION							
222-4 LOAD LUGGER	(130)	X		=			
222-5 LOAD LUGGER	(130)	X		=			
221-7 LOAD LUGGER	(204)	X		=			
OTHER (DESCRIBE)							
GROSS VOLUME (FT ³) = <u>29.60</u>							
ACTIVITY LEVEL: (SEE INSTRUCTIONS ON BACK)							
C.P. WINDOW CLOSED READINGS AT SURFACE (2") AT 3 FT							
IDENTIFY CONTAINER BY VOLUME ABOVE EACH COLUMN							
<u>7.4 FT³</u>	<u>FT³</u>	<u>FT³</u>	<u>FT³</u>	<u>FT³</u>	<u>FT³</u>		
<u>1 MP/HR @ 2" (1x10⁻³ Ci)</u>							
<u>1 MP/HR @ 2" (1x10⁻³ Ci)</u>							
<u>1 MP/HR @ 2" (1x10⁻³ Ci)</u>							
<u>1 MP/HR @ 2" (1x10⁻³ Ci)</u>							
TOTAL MP/HR TOTAL MP/HR TOTAL MP/HR TOTAL MP/HR TOTAL MP/HR							
TOTAL MP/HR	X	FACTOR	=	CURIES			
<u>1 MP/HR</u>	X	<u>1x10⁻³</u>	=	<u>1x10⁻³ Ci</u>			
<u>1 MP/HR</u>	X	<u>1x10⁻³</u>	=	<u>1x10⁻³ Ci</u>			
<u>1 MP/HR</u>	X	<u>1x10⁻³</u>	=	<u>1x10⁻³ Ci</u>			
<u>1 MP/HR</u>	X	<u>1x10⁻³</u>	=	<u>1x10⁻³ Ci</u>			
GROSS ACTIVITY (CURIES) = <u>4x10⁻³ Ci</u>							
PLUTONIUM <u>2225</u> GRAMS							
URANIUM <u>0</u> GRAMS <u>0</u> ENRICHMENT							

THIS PAGE INTENTIONALLY LEFT BLANK

TYPICAL DRUMS

HEDL

325 BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

None

Comb. S.F. 616

(34)

SOLID WASTE BURIAL RECORD

100 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - ERDA
BY ATLANTIC RICHFIELD HANFORD COMPANY

WH 679

DISPOSAL SITE

THIS PORTION OF FORM TO BE COMPLETED BY
ADDED REPRESENTATIVE AT DISPOSAL SITE

ORIGINATOR 325-WHC-78-021-40

AREA <u>200 W</u>	BURIAL GARDEN NO. <u>4C</u>	TRENCH NO. <u>A 4</u>
DESHEDS COORDINATED <u>Module L</u>	DESHEDS COORDINATED <u>5 4072</u>	DESHEDS COORDINATED <u>6 22508</u>
INDICE COORDINATED <u>9 40176</u>	INDICE COORDINATED <u>8 22483</u>	
REMARKS <u>4007C</u>		
DATE <u>5-4-78</u>		
SIGNATURE <u>Mr. W. Carter</u>		

PACKAGE NO.	ERDA AUTHORIZATION NO.
COMPANY <u>HEDL</u>	
BUILDING <u>325</u>	AREA <u>300</u>
ADDRESS (OFF SITE)	
I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and that the contents are packaged in ARHCO approved containers per ARH 3072 Rev.	
SIGNATURE <u>[Signature]</u>	DATE <u>11/18/78</u>

PHYSICAL DESCRIPTION

MATERIAL CONTENTS NOTE ANY SPECIAL CONDITIONS (E.G., DISSOLVED, PUMP, SAMPLING IN LABORATORY PAKED WASTE, TUBES, POTS)
(INCLUDE FOR NUMBERS AND PROPERTY CONTROL NUMBERS)Lab Waste, Drum # WH 77-964, 974, 957, 910, 989, 988, WH 78-990, 998, 999, 991, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10Shipping & Receiving Report # WM 78-25/WM 78-26

BOX	NO.	LENGTH	WIDTH	HEIGHT	HANFORD STANDARD	CANOGARD
DRUM	NO. AND SIZE	20-55 gal. R.R.				
CONTAINER	NO. AND SIZE					
OTHER						
TOTAL VOLUME (cu ft)		150.0 cu ft		Gross Weight		2600
						Pounds Kilograms

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs; WASTE FISSILE PRODUCTS; ACTIVATION PRODUCTS)

RU

PLUTONIUM <u>62.38</u> grams	URANIUM <u>3.37</u> grams	ACTIVITY (IF Pu OR U, ONLY UNITS IN GRAMS REQUIRED)
DOSE RATE <u>26</u> mR/hr	DOSE RATE <u>3</u> mR/hr	
DISTRIBUTION:		BY ARHCO
WHITE		WHITE - 50 WH 222.0
YELLOW		YELLOW - NUCLEAR WASTE ALB. 2700.0
PINK		PINK - RETURN TO SHIPPER
GOLDENROD - RETURN		

NON-COMBUSTIBLE MATERIALS					COMBUSTIBLE MATERIALS				
DRUM NO.	GRAMS PU	MEASUREMENT METHOD	OPERATOR	TRENCH	DRUM NO.	GRAMS PU	MEASUREMENT METHOD	OPERATOR	TRENCH
					WH 77-				
				21	964	3.53	ASSAY	✓	18.1530.76
				22	974	3.96	ASSAY	✓	18.17.11.88
				23	957	.69	ASSAY	✓	18.17.2.07
				24	910	2.72	ASSAY	✓	18.17.8.16
				25	989	19.70	ASSAY	✓	18.17.4.17
				26	988	8.63	ASSAY	✓	18.17.25.89
					WH 78		ASSAY		
				27	990	2.18	ASSAY	✓	17.6.11
				28	999	✓	EST	✓	
				29	999	✓	EST	✓	
				30	WH 78	✓	EST	✓	
				31	2	✓	EST	✓	10+
				32	3	✓	EST	✓	10+
				33	4	✓	EST	✓	10+
				34	5	✓	EST	✓	10+
				35	6	✓	EST	✓	10+
				36	7	✓	EST	✓	10+
				37	8	✓	EST	✓	10+
				38	9	✓	EST	✓	10+
				39	10	✓	EST	✓	10+
				40	991	✓	EST	✓	10+
					Total - 6238				

CERTIFIED BY: [Signature]

DISPOSAL SITE:

AREA: 200-N BURIAL GARDEN NO.: 4C TRENCH NO.: 4

COORDINATES: NORTH: 40070 WEST: 77508

REMARKS: REMOVED 8 77482
40070

DATE: 1/18/78

SIGNATURE: [Signature] DATE: 5-4-78

DRUMS ARE ACCEPTED PER SOP 300.8

SIGNATURE: [Signature] DATE: 1-18-78

DISPOSITION: ALL ACCOMPANY SHIPMENT IF COMPLETED
RISK TO BE RETURNED
WHITE & YELLOW WITH SHIPMENT IF NO RETURNED COPY
DELIVERED

325-WNC-78-02

HUA-VRA-20
Page 3

<u>Drum No.</u>	<u>Location Bldg/Rm</u>	<u>Cost Code</u>	<u>Wt/Lb</u>	<u>Pu in Grams</u>
910	308/219	VB4130	94	2.72
957	308/219	VB4130	107	.69
964	308/113	VB2110	133	3.53
974	308/113	VB2110	112	3.96
988	325/307	VB4110	127	8.63
989	325/307	VB4110	126	19.70
990	325/307	VB4110	150	23.15

325-WAC-78-02

۱۴۵

PROJECT 1411

<u>Drum No.</u>	<u>DU</u>	<u>EU</u>	<u>Pu</u>	<u>MU</u>	<u>Th</u>
910			2.72 @ 12%	8.16	
957			.69 @ 12%	2.07	
964	1693.47 @ .22		3.53 @ 12%	5,041.51 10.59	1,530.76
974			3.96 @ 12%	11.88	
988			8.63 @ 12%	25.89	
989			19.70 @ 12%	4.14	
990		3.37 at 86.17%	23.15 @ 12%	66.11	
	<u>1,693.47</u>	<u>3.37</u>	<u>62.38</u>	<u>5,174.35</u>	<u>1,530.76</u>

TYPICAL DRUMS
PNL
325 BUILDING

WHC-SD-W113-ACDR-001

Rev. 0

Page 100A

THIS PAGE INTENTIONALLY LEFT BLANK

Atlantic Richfield Montreal Company

CB 1 2 4 15
Dec 3 15 TRAN

TRANSURANIC DRY WASTE STORAGE

DSBNW-78-2

CERTIFIED BY : SUPERVISOR :

D. C. M^r Carr

DATE _____

1/18/78

DISPOSAL SITE:

DISPOSAL SITE:

AREA	SURVIVAL GARDEN NO	TRENCH NO	AREA	SURVIVAL GARDEN NO	TRENCH NO.
			2cc N	7c	4
CAISSON NO.	COORDINATES		COORDINATES	COORDINATES	
	NORTH	WEST	11-14/5 1	11-14/5 1	WEST: 77561

REMARKS:

*****:

RTTC B 22484
4667C

SIGNATURE

1948

SIGNATURE

1 DAY

5.4.78

COLUMS ARE ACCEPTED PER SQ INCH

DISCUSSION

Bäcker:

21410-104:

ALL ACCURACY INQUIRY IF COMPLETED
SHOULD BE RE-OPENED

REF ID: A66608

TYPICAL DRUMS

PNL

231-Z BUILDING

WHC-SD-W113-ACDR-001

Rev. 0

Page 103A

THIS PAGE INTENTIONALLY LEFT BLANK

+ 2 Non Comb 2

Combustible

⑤

SOLID WASTE BURIAL RECORD 200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - AEC BY ATLANTIC RICHFIELD HANFORD COMPANY	No 0016
---	---------

DISPOSAL SITE THIS PORTION OF FORM TO BE COMPLETED BY ARMED REMEDIATION AT DISPOSAL SITE AREA <u>200-W</u> BURIAL GARDEN NO. <u>4C</u> TRENCH NO. <u>H</u> COORDINATES <u>E 27500</u> <u>E 27500</u> REMARKS <u>B 774R</u> <u>F N 40070</u> <u>D N 40070</u>		ORIGINATOR <u>231Z-BNW-78-02-20</u> PACKAGE NO. <u>BNW</u> COMPANY <u>BNW</u> BUILDING <u>231-Z</u> AREA <u>200 W</u> ADDRESS (OFF SITE)	
DATE <u>5-8-78</u> TIME SIGNATURE <u>A. W. Carter</u>		DATE <u>2-6-78</u> SIGNATURE <u>Joe B. Webb</u>	

PHYSICAL DESCRIPTION MATERIAL CONTENTS (NOTE ANY SPECIAL CONDITIONS) E.G., DISSOLVER, DUMP, SAMPLING OR LABORATORY PAPER WASTE, TIMBERS, ETC. <u>Glove Box + Lab Waste in 55 gal drums</u> <u>With plaster lining. For 20 yr. retrievable</u> <u>Storage + 231Z-1-78-2 + 3 + 4 + 5 + 6 - 7-8-9-11</u> <u>231Z-78-1-10 + 12</u>						
CONTAINER	BOX	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD CARDBOARD
	DRUM	NO. AND SIZE	<u>(2) 9-55 gal drums DOT-17H</u>			
	OTHER	NO. AND SIZE				
	TOTAL VOLUME (FY) <u>88.8</u> <u>66.4</u>					

ACTIVITY DESCRIPTION GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS PU, CO, SF, COLIMED FISSILE PRODUCTS, ACTIVATION PRODUCTS) <u>PH</u>			
PLUTONIUM <u>PU-239</u>	URANIUM <u>U-235</u>	ACTIVITY (IF PU OR U, ONLY WRITE IN GRAMS REQUIRED) <u>6</u> GRAMS	
DOSE RATE		☒ SURFACE ☐ INSIDE ☐ FEET	
DISTRIBUTION: WHITE - BY ORIGINATOR YELLOW - <u>ARMED</u> PINK - <u>ARMED</u> SOLID - <u>ARMED</u>		BY ARMED - SIGN AND FORWARD TO: WHITE - <u>ARMED</u> SUPERVISOR OF BURIAL GROUP YELLOW - <u>ARMED</u> WASTE DISPOSAL COORDINATOR	

CB-1-7.7-150, 231-Z 2317-BKW-78-04 UO16

SC-4808-074 (116-731)

MODULE 2 (West coordinates 77482 to 77509)

Module 2 consists of 720 spaces for 55-gallon drums stacked in a 12 by 12 by 5 configuration. Module 2 was built from July 1978 through May of 1979 and is assumed to consist entirely of painted steel drums.

According to burial records the 234-5Z Facility generated 394 drums of the waste containing 198 grams of plutonium. 338 of these drums had no measurable amounts of plutonium. The 325 (PNL) Facility generated 27 drums containing 33 grams of plutonium, 7 drums had no measurable plutonium. The 325A (PNL) Facility generated an additional 5 drums containing 5 grams of plutonium. The 325 (WHC) Facility generated 214 drums containing 2250 grams of plutonium, 3785 grams of uranium, and 1000 grams of thorium. There were 36 drums that had no measurable plutonium. The BATCO (OHO) Facility generated 42 drums containing 115 grams of plutonium, and 233 grams of uranium. The 202A (WHC) Facility generated 10 drums containing 20 grams of plutonium. The 222S (WHC) Facility generated 3 drums containing 1 gram of plutonium, 2 drums had no measurable plutonium. The 231-Z (PNL) Facility generated 24 drums containing 5 grams of plutonium, 4 drums had no measurable plutonium.

The Module totals include about 2630 grams of plutonium, 4020 grams of uranium, and 1000 grams of thorium. There were 386 drums that had no measurable plutonium. The highest plutonium loaded drum is 179.0 grams from a 325 (WHC) drum located in position L-6 of Tier 3. The highest dose rate recorded was only 6.0 mrem/hr from one 325 (WHC) drum, and the rest were essentially 1 mrem/hr or less.

THIS PAGE INTENTIONALLY LEFT BLANK

TIER 1

218W4C
Trench 4
Module 2

⊞ No known data

○ < .01 g Pu & < 1mR

⊙ Yellow # = Dose Rate

⊖ White # = grams Pu

WHC-SD-W113-ACDR-001
Rev. 0
Page 107

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TIER 2

218W4C
Trench 4
Module 2

No more

218W4C

218W4C

218W4C

L K J I H G F E D C B A

TIER 3

218W4C
Trench 4
Module 2

Rate
PU

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TIER 4

218W4C
Trench 4
Module 2

L K J I H G F E D C B A

2 3 4 5 6 7 8 9 10 11 12

TIER 5

218W4C
 Trench 4
 Module 2

NO KEY

Rate
 1000
 1000
 1000

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TRENCH
 MODULE
 TIER

TRENCH 4 MODULE 2 TIER 2

TRENCH 4 MODULE 2 TIER 3

TIER 4

TRENCH 4 MODULE 2 TIER 5

TYPICAL DRUMS
BATTELLE COLUMBUS LABORATORIES
COLUMBUS

THIS PAGE INTENTIONALLY LEFT BLANK

SOLID WASTE BURIAL RECORD
200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - ERDA
By Rockwell Hanford Operations

1918

DISPOSAL SITE This portion of form to be completed by Rockwell Representative at Disposal Site.		ORIGINATOR	
AREA 200-12	BURIAL GARDEN NO. 40	TRENCH NO. 4	PACKAGE NO. RRM #1918
Modals 2	DESCENDING COORDINATES = 40070 = 22535		ERDA AUTHORIZATION NO
SECTION 1	ASCENDING COORDINATES = 40070 = 22509		COMPANY BATTELLE COLUMBUS LABORATORIES
REMARKS			BUILDING: AREA:
DATE 10-29-78	TIME		ADDRESS (OFF SITE) 505 KING AVE. COLUMBUS, OHIO 43201
SIGNATURE R.W. Parker			I certify that no special property is included in this burial unless documented by a Property Disposal Request, and that the contents are packaged in Rockwell approved containers as per ARH-3033 Rev.
			SIGNATURE 6/13/78

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (NOTE ANY SPECIAL CONDITIONS: E.G., DISSOLVED, PUMP, SAMPLING OR LABORATORY WASTE, THICKNESS, RESIDUE
INCLUDE FOR NUMBERS AND PROPERTY CONTROL NUMBERS)

R & D Laboratory waste generated during the performance of DOE Contract programs.

Waste consist of glove box wipings, small contaminated equipment and tools, box
gloves, and other misc. contaminated items normally associated with R & D operations.
All waste drums in this shipment contain some enriched uranium in quantities varying
from <0.5 grams U-235 to 16 grams U-235.

CONTAINER	BOX	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD CARDBOARD	
	DRUM	NO. AND SIZE 42 DOT-17C and 17H 55 gal. drums.					
	OTHER	NO. AND SIZE					
TOTAL VOLUME (FT ³)			315	Gross Weight 2150 (42 drums)			☒ Pounds Kilograms

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, FALLOUT FISSION PRODUCTS, ACTIVATION PRODUCTS)

All drums contain Pu-239 (Quantities ranging from <0.5 gram to 8 gram) and enriched
uranium (Quantities ranging from <0.5 gram to 16 gram U-235). All waste is un-irradiated

PLUTONIUM 84	GRAMS	URANIUM (E1, WE)	38.462	GRAMS	276	ACTIVITY (IF Pu OR U, ONLY UNITS IN COMPO REQUIRED)
DOSE RATE		mR/hr		3		COOSES ☐ SURFACE ☐ INTERIO ☒ FEET
DISTRIBUTION:		BY SHIPPER		BY ROCKWELL		
WHITE		WHITE		WHITE		- 5 & 10 222.0
YELLOW		YELLOW		YELLOW		- YELLOW MATERIALS, 2 FOR 2
PINK		PINK		PINK		- RETURN TO SHIPPER
COLORLESS - RETAIN						

THIS PAGE INTENTIONALLY LEFT BLANK

TYPICAL DRUMS
ROCKWELL
202-A (PUREX) PLANT

THIS PAGE INTENTIONALLY LEFT BLANK

2/1-03-78-PPR 10 drums P.M.

Non Combustible Process LCU (55)

Blackwell Hanford Operations

TRANSURANIC DRY WASTE STORAGE 202A-RH-79-1

NON-COMBUSTIBLE MATERIALS					Non-Combustible Materials				
DRUM NO.	GRAMS PU	MEASUREMENT METHOD	OPERATOR	TRENCH	DRUM NO.	GRAMS PU	MEASUREMENT METHOD	OPERATOR	TRENCH
1 ✓	01 26 0	Geo Weirich	4-1-1		26 0 38	4-1-1			
2 ✓	02 26	Grams Pu			27 0 29				
3 ✓	03 26	✓ 28	0	4-1-1	28 0 30				
4 ✓	04 26	✓ 39	26	4-1-1	29 0 31				
5 ✓	05 26	✓ 30		4-1-1	30 0 32				
6 ✓	06 26	✓ 31	26	4-1-1	31 0 33				
7 ✓	07 26	✓ 32	26	4-1-1	32 0 34				
8 ✓	10	✓ 09		4-1-1					
9 ✓	11	✓ 08		4-1-1					
10 ✓	12			4-1-1					
11 ✓	13			4-1-1					
12 ✓	14 26			4-1-1					
13 ✓	15 26			4-1-1					
14 ✓	16 26			4-1-1					
15 ✓	17 26			4-1-1					
16 ✓	18 26			4-1-1					
17 ✓	19 26			4-1-1					
18 ✓	20 26			4-1-1					
19 ✓	21			4-1-1					
20 ✓	22			4-1-1					
21 ✓	23			4-1-1					
22 ✓	24			4-1-1					
23 ✓	25			4-1-1					
24 ✓	26			4-1-1					
25 ✓	27			4-1-1					

CERTIFIED BY (SUPERVISOR)

L. Spidman

DATE

3-28-78

DISPOSAL SITE:

AREA

JCO-W

BURIAL GARDEN NO.

4C

TRENCH NO.

4

COORDINATES

Module 4

COORDINATES

NORTH: 40070 WEST: 77586

REMARKS:

40070 W-77561

DISPOSAL SITE:

AREA

JCO-W

BURIAL GARDEN NO.

4C

TRENCH NO.

4

COORDINATES

Module 4

COORDINATES

NORTH: 40070 WEST: 77586

REMARKS:

N-40070 W 77561

SIGNATURE

A. W. Carter

DATE

5-18-79

SIGNATURE

A. W. Carter

DATE

5-18-79

DRUMS ARE ACCEPTED PER SOP 300.8

SIGNATURE:

L. Spidman

DATE:

5-18-79

INSTRUCTIONS:

ALL ACCOMPANYING SHIPMENT IF COMPLETED
SHOULD BE RETURNED

WHITE YELLOW WITH SHIPMENT IF NO RETURNED COPY

Non-Combustible

SOLID WASTE BURIAL RECORD

200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - ERDA
By Rockwell Hanford Operations

102-15

(55)

DISPOSAL SITE

This portion of form is to be completed by
Rockwell Representative at Disposal site.

AREA <u>200-W</u>	BURIAL GARDEN NO. <u>4C</u>	TRENCH NO. <u>4</u>
ORIGINATOR <u>Module 4</u>	DESIGNING COORDINATES N <u>40070</u> - <u>77588</u> Easting COORDINATES N <u>40070</u> - <u>77561</u>	
REMARKS		
DATE <u>5-18-77</u>		
SIGNATURE <u>B.W. Carter</u>		

ORIGINATOR 202A-RH0-79-33-47

PACPAGE NO.	ERDA AUTHORIZATION NO.
COMPANY <u>Rockwell</u>	
BUILDING <u>202-A</u>	AREA <u>200E</u>
ADDRESS (OFF SITE)	
I certify that no special property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents are packaged in Rockwell approved containers per ARH-3032 Rev.	
SIGNATURE <u>L. L. Bismore</u>	<u>6-1-78</u>

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (NOTE ANY SPECIAL CONDITIONS: E.G., DISSOLVER, PUMP, SAMPLING OR LABORATORY WASTE, TIMBERS, RESIN
INCLUDE FOR NUMBERS AND PROPERTY CONTROL NUMBERS)Septimus shipping containers in 55 gal drums202-A-78-C1 + C2 + C3 + C4 + C5 + C6 + C7 + C8202-A-78-09 + C10 + C11 + C12 + C13 + C14 + C15

CONTAINER	BOX	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD CARDBOARD	
	DRUM	NO. AND SIZE <u>15 - 55 gal</u>					
	OTHER	NO. AND SIZE					
	TOTAL VOLUME (FT ³) <u>111.1</u>						
Gross Weight <u>2500</u>						☒ Pounds ☐ Kilograms	

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, U, Sr, FOLLOWED FROM PRODUCT OF ACTIVATION PRODUCT)

Fixed fissile products & Pu

PLUTONIUM <u>0</u> GRAMS	URANIUM <u>1</u> GRAMS	ACTIVITY (IF Pu OR U, ONLY UNITS IN GRAMS REQUIRED)
DOSE RATE <u>21</u> mR/hr	ENRICHMENT <u>50%</u>	EXPOSURE ☐ SURFACE ☐ INSIDE ☐ FEET

DISTRIBUTION:

BY SHIPPER

WHITE	} WITH SHIPMENT
YELLOW	
PINK	
SOLUBLE - DETAIN	

BY ROCKWELL

WHITE	- 50 mR 22-0
YELLOW	- NUCLEAR MATERIALS, 2700-E
PINK	- RETURN TO SHIPPER

24.9

1.032

MODULE 3 (West coordinates 77536 to 77563)

Module 3 consists of 576 spaces for 55-gallon drums stacked in a 12 by 12 by 4 high configuration. Module 3 was built during the late Winter and Spring (February through May) of 1979 and the drums are assumed to be painted steel.

According to the burial records the 234-5Z Facility generated 464 drums of the waste in Module 3. 126 of these drums contain 4469 grams of plutonium. The other 338 drums contain no measurable plutonium. The 325 (WHC) Facility generated 49 drums containing 750 grams of plutonium, 10,505 grams of uranium, and 990 grams of thorium. There were 23 of these 49 drums that contained no measurable plutonium. The 325 (PNL) facility generated 39 drums containing no plutonium but containing 190 grams of uranium and 0.5 grams of americium. The 231-Z Facility generated 14 drums containing 1.0 gram of plutonium and one drum with no measurable plutonium.

The Module totals about 5220 grams of plutonium, 10,700 grams of uranium, 990 grams of thorium, and 0.5 grams of americium. There were 399 drums that contained no measurable plutonium. The highest plutonium loaded drum is 189 grams from 234-5Z located in position J8, Tier 4. There were 19 drums that contained over 100 grams plutonium. The highest recorded dose rate was 1.0 mrem/hr or less.

THIS PAGE INTENTIONALLY LEFT BLANK

TIER 1

218W4C
 Trench 4
 Module 3

1000

Close Rate

1000

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

Page 126

218W4C
Trench 4
Module 3

65

7

U.S. DEPT. OF AGRICULTURE

ams Pu

23456789101112

LKJ IHGFEDCBA

TIER 3

218W4C
 Trench 4
 Module 3

218

218

Dose Rate
 grams Pu

2 3 4 5 6 7 8 9 10 11 12

L K J I H G F E D C B A

TIER 4

218W4C
 Trench 4
 Module 3

116

mR

RECORD # = Dose Rate

WATER # = Claims Pu

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TRENCH 4 MODULE 3 TIER 1

TRENCH 4 MODULE 3 TIER 1

TRENCH

MODULE

TIER

TRENCH 4 MODULE 3 TIER 4

MODULE 4 (West coordinate 77563 to 77590)

Module 4 consists of 576 spaces for 55-gallon drums stacked in a 12 by 12 by 4 high configuration. Module 4 was built in mid 1979 while mostly painted steel drums were in use for the TRU solid waste.

The 202-A (WHC) Facility generated 66 drums of waste containing 27 grams of plutonium, 47 drums had no measurable plutonium. The 325 (WHC) Facility generated 100 drums containing 2676 grams of plutonium and eight of those drums contain no measurable plutonium. The 202-AL (WHC) generated 6 drums with no measurable plutonium. The 340 (WHC) facility provided 24 drums with 318 grams plutonium. The 231-Z (PNL) Building generated 95 drums containing 242 grams of plutonium, and a drum with 0.09 gram plutonium had 3000 grams of depleted uranium. One drum had no measurable plutonium but 79 drums are recorded to contain 10 milligrams each, which should assay as LLW. The 234-5Z (WHC) Facility generated 311 drums containing 1503 grams plutonium, 169 of these drums had no measurable plutonium.

The module totals include 4766 grams of plutonium and 3000 grams depleted uranium. There were 231 drums that had no measurable plutonium content. The above data from RSWIMS shows 26 more drums in this module than there are spaces. SWITS however, has no entries for 24 locations, duplicate entries in another 24 locations, and 36 entries with no records. The highest plutonium loaded drum is a 150 gram drum from 325 (WHC) located in position K6 of tier 3. Dose rate values were all 1 mrem/hr or less.

THIS PAGE INTENTIONALLY LEFT BLANK

L K J H G F E D C B A

2 3 4 5 6 7 8 9 10 11 12

TIER 1

218W4C
Trench 4
Module 4

[illegible]

TIER 2

218W4C
 -rench 4
 Module 4

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

1mR
 Dose Rate
 rads Pu

TIER 3

218W4C
 trench 4
 module 4

MR

Use Rate

MS DU

2 3 4 5 6 7 8 9 10 11 12

HGFEDCBA

TIER 4

218W4C.
Trench 4
Module 4

ms

Rate

ms Pu

2 3 4 5 6 7 8 9 10 11 12

L K J I H G F E D C B A

TRENCH 4 MODULE 4 TIER 1

TRENCH 4
 MODULE 1
 TIER 2

TRENCH 4 MODULE 4 TIER 3

TRENCH 4 MODULE 4 TIER 4

TYPICAL DRUMS
ROCKWELL
202-AL LABORATORY

THIS PAGE INTENTIONALLY LEFT BLANK

B-12550-2

56

PREF. Lab-161

[illegible]

DATE: 4-14-78

DISPOSAL SITE:		
Area	Burial Garden N ^o	Trench N ^o
Caisson N ^o	Coordinates North West	
Remarks		
Signature		Date

R. W. Casler 4-14-78
Signature

JULY 1972

MODULE 5 (West coordinate 77590 to 77616)

Module 5 consists of 576 spaces for 55-gallon drums stacked in a 12 by 12 by 4 high configuration. Module 5 was built in the summer of 1979 while mostly painted steel drums were being used for the TRU solid wastes.

The 234-5Z (WHC) facility generated 356 drums of waste containing 34,083 grams of plutonium, and 2000 grams of uranium. There were 205 drums that had no measurable quantities of plutonium. The 325 (PNL) Facility generated 119 drums containing 428 grams of plutonium and 74 drums had no measurable plutonium. The 325 (WHC) Facility generated 87 drums containing 452 grams of plutonium, 9187 grams of uranium, and 492 grams of thorium. There were 36 drums with no measurable plutonium. The 233-S Facility generated 11 drums with no measurable plutonium.

The Module totals include 34,960 grams of plutonium, 11,190 grams of uranium, and 490 grams of thorium. There were 323 drums that had no measurable plutonium. There were 31 drums un-identified. The highest plutonium loaded drum is 198 grams from 234-5Z located in position D6 of Tier 3. There were 73 drums each containing over 100 grams of plutonium. The highest dose rate was 6 mrem/hr for 2 drums from the 325 Building.

This module contains most of the waste from PFP contaminated with Plutonium containing greater than 12.99% ^{240}Pu . There are nine drums containing an unspecified quantity of both 23.1% and 8.1% ^{240}Pu . The identification of these and the grams of TRU recorded in each are:

PC-11	185 grams	PC-12	187 grams
PC-13	179	PC-14	185
PC-15	182	PC-16	198
PC-17	185	PC-18	172
PC-19	193	PC-79-060	111
		PC-79-061	85

The remainder are all recorded as 23.1% ^{240}Pu :

PC-79-027	163 grams	PC-79-028	169 grams	PC-79-029	169 grams
PC-79-030	166	PC-79-031	168	PC-79-033	162
PC-79-034	182	PC-79-035	166	PC-79-036	174
PC-79-037	165	PC-79-039	163	PC-79-040	163
PC-79-041	165	PC-79-042	171	PC-79-043	174
PC-79-044	168	PC-79-045	167	PC-79-046	149
PC-79-047	166	PC-79-048	164	PC-79-049	172
PC-79-050	176	PC-79-051	167	PC-79-052	172
PC-79-053	176	PC-79-054	173	PC-79-055	166
PC-79-056	162	PC-79-057	167	PC-79-058	174
PC-79-059	130				

WHC-SD-W113-ACDR-001
Rev. 0
Page 145A

THIS PAGE INTENTIONALLY LEFT BLANK

TIEB-1

218W4C
Trench 4
Module 5

11

Dose Rate
Grams Pu

K J H G F E D C B A

2 3 4 5 6 7 8 9 0 1 2

L K H G F E D C B A

213W4C
Trench 4

3

Use Rate

Dr. Smith

2 3 4 5 6 7 8 9 10 11 12

WHC-SD-W113-ACDR-001
Rev. 0
Page 148

TIER 4

213W40
Trend:

L K J H G F E D C B A

1
2
3
4
5
6
7
8
9
10
11
12

Date:

1mR

Dose Rate

grams Pu

TRENCH 4 MODULE 5 TIER 1

TRENCH 4 MODULE 5 TIER 2

TRENCH 4 MODULE 5 TIER 3

TRENCH 4 MODULE 5 TIER 4

TYPICAL DRUMS
ROCKWELL
233-S BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

COMBUSTIBLE

WHC-SD-W113-ACDR-001

Rev. 0

Page 155

SOLID WASTE BURIAL RECORD

200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL DOE
By Rockwell Hanford Operations

DISPOSAL SITE		This portion of form to be completed by Rockwell Representative at Disposal site.		ORIGINATOR 233 S-RHO-79-1-11	
AREA 200-W	BURIAL BURDEN NO. HC	TRENCH NO. 34		PACKAGE NO.	EROS AUTHORIZATION NO.
CAISSON NO. MIDDLE 5	COORDINATES N 40070	E 27414		COMPANY H. H. C.	
SECTION-3+4	COORDINATES N 40070	E 27588		BUILDING 33-5	AREA 200 W
REMARKS				ADDRESS (OFF SITE)	
DATE 8-11-79				TIME	
SIGNATURE R. W. Carter				SIGNATURE J. C. Cund	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (NOTE ANY SPECIAL CONDITIONS) E.G., DISSOLVED, PUMP, SAMPLING OR LABORATORY WASTE, TIMBERS, RESIN INCLUDE PRO NUMBERS AND PROPERTY CONTROL NUMBERS							
4 bags chlorine, 12 bags, Paper (Combustible)							
D-79-06-A-1+2+3+4-5 RAAS 85%							
D-79-06-A-6+7+8+9+10+11 PLASTIC 5%							
PAPER 10%							
CONTAINER	BOX	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD CARDBOARD	
	DRUM	NO. AND SIZE 11 55 gal. - 11 BBL.					
	OTHER	NO. AND SIZE					
TOTAL VOLUME (FT ³)			82.5		Gross Weight	1230 Pounds	

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)						
Pu						
PLUTONIUM		URANIUM		ACTIVITY (IF Pu OR U, ONLY UNITS IN GRAMS REQUIRED)		
Isotopes		Isotopes		Isotopes		
DOSE RATE		25 mR/hr		SURFACE ☒ INCHES ☐ FEET ☐		
DISTRIBUTION:		BY SHIPPER		BY ROCKWELL		
WHITE		WITH SHIPMENT		WHITE - S & WH, 222.0		
YELLOW				YELLOW - NUCLEAR MATERIALS, 2700.1		
PINK				PINK - RETURN TO SHIPPER		
GOLDENROD - RETAIN						

54-3000-581 (3-78)

(57)

NON-COMBUSTIBLE MATERIALS					COMBUSTIBLE MATERIAL				
DRUM NO	GRAMS PU	MEASUREMENT METHOD	OPERATOR	TRENCH	DRUM NO	GRAMS PU	MEASUREMENT METHOD	OPERATOR	TRENCH
				1	D-77-LA-7	0	NDH	0	PCL
				2	D-77-LA-8	0		0	PCL
				3	D-77-LA-9	0		0	PCL
				4	D-77-LA-10	0		0	PCL
				5	D-77-LA-11	0		0	PCL
				6	D-77-LA-12	0		0	PCL
				7	D-77-LA-13	0		0	PCL
				8	D-77-LA-14	0		0	PCL
				9	D-77-LA-15	0		0	PCL
				10	D-77-LA-16	0		0	PCL
				11	D-77-LA-17	0		0	PCL

CERTIFIED BY (SUPERVISOR)

J. L. Carter

DATE

11-6-29-79

DISPOSAL SITE:

AREA: BURIAL GARDEN NO: TRENCH NO:

CAISSON NO: COORDINATES: NORTH: WEST:

REMARKS:

DISPOSAL SITE:

AREA: BURIAL GARDEN NO: TRENCH NO:

CAISSON NO: COORDINATES: NORTH: WEST:

REMARKS:

SIGNATURE

DATE

SIGNATURE

DATE

DRUMS ARE ACCEPTED PER SDP 300 B

SIGNATURE:

DATE:

SIGNATURE:

ALL APPROPRIATE DOCUMENTS IF COMPLETED
MUST BE RETURNED
WHILE IN YELLOW BAGS IF NOT RETURNED COPY

DISTRIBUTION: White - Research
Blue - Research Associates Accounting
Green - Physical Control
Canary - Shipper
Pink - Receiver

Pink - Receiver
GOLDENROD - WORKING COPY FOR PENCIL DRAFT

ESS MATERIAL ITEM TRANSFER

Rockwell Hanford Operations										SS MATERIAL ITEM TRANSFER														
1 From Blk 2 From Nm 3 From Hood					4 Shipper's Signature					7 To Bldg 8 To Room 9 To Hood					10 Proc									
12 M/P Ratio					13 Material Description					14 Balance DOE Number					15 Balance DOE Number									
233-5 0-1					233-5 D+D OPERATIONS					6/27/79 Ground N/A					N/A									
720					Radioactive Contaminated Waste from					233-5 D+D OPERATIONS					N/A									
REQUIRED ENTRY					SEAL					WEIGHT					WEIGHTS									
16					17					18					19					20				
Material Identity					From To					Number					Date					Can No				
D-79-6-A-1					N/A					5818					6-29-79					N/A				
D-79-6-A-2					N/A					5919					6-29-79					N/A				
D-79-6-A-3					N/A					6020					6-29-79					N/A				
D-79-6-A-4					N/A					6121					6-29-79					N/A				
D-79-6-A-5					N/A					6222					6-29-79					N/A				
D-79-6-A-6					N/A					6323					6-29-79					N/A				
D-79-6-A-7					N/A					6424					6-29-79					N/A				
D-79-6-A-8					N/A					6525					6-29-79					N/A				
D-79-6-A-9					N/A					6626					6-29-79					N/A				
D-79-6-A-10					N/A					6727					6-29-79					N/A				
D-79-6-A-11					N/A					6828					6-29-79					N/A				
D-79-6-A-12					N/A					6929					6-29-79					N/A				
D-79-6-A-13					N/A					7030					6-29-79					N/A				
D-79-6-A-14					N/A					7131					6-29-79					N/A				

TOTALS

一

RECEIVED

THIS PAGE INTENTIONALLY LEFT BLANK

MODULE 6 (West coordinate 77616 to 77642)

Module 6 consists of 576 spaces for 55-gallon drums stacked in a 12 by 12 by 4 high configuration. Module 6 was built in late 1979 and early 1980 which was still prior to switching from painted steel drums to galvanized steel.

The 234-5Z (WHC) Facility generated 308 drums of waste containing 165 grams of plutonium, 290 drums had no measurable plutonium. The 325 (WHC) Facility generated 104 drums containing 378 grams of plutonium, 436 grams of uranium, and 393 grams of thorium. There were 30 drums that had no measurable plutonium. The 325 (PNL) Facility generated 86 drums containing 96 grams of uranium, and 8.0 grams of americium, but no plutonium. The 231-Z (PNL) Facility generated 14 drums containing 0.14 grams of plutonium. The 233-S (WHC) Building generated 7 drums containing 14 grams of plutonium.

The Module totals include 560 grams of plutonium, 1400 grams of uranium, 390 grams of thorium, and 8.0 grams of Americium. There were 404 drums that had no measurable plutonium. There were 56 drums un-identified. The highest plutonium loaded drum was 94 grams from 325 (WHC) located in position 89 of Tier 2. The plutonium content of most drums was very low. The highest dose rate value was 10 mrem/hr recorded for 41 drums, the rest are recorded to have been 1 mrem/hr or less.

WHC-SD-W113-ACDR-001
Rev. 0
Page 158A

THIS PAGE INTENTIONALLY LEFT BLANK

L K J I H G F E D C B A

2
3
4
5
6
7
8
9
10
11
12

TIER 1

218W4C
Trench 4
Module

data
 $P_{0.3} < 1\text{mR}$
= Dose Rate
grams Pu

TIER 2

218W4C
Trench 4
Module 6

218

W4C4

Jose Rate
grams Pu

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TIER 3

218W4C
French 4
Coulie 6

L K J H G F E D C B A

10	10	10
2	10	10
3	10	10
1	2	10
2	10	10
2	2	1
10	10	10
2	2	10

2 3 4 5 6 7 8 9 10 11 12

Dose Rate
grams PU

TIER 4

18W4C
T-0004

L K J I H G F E D C B A

2 3 4 5 6 7 8 9 10 11 12

File
Date

TRENCH 4 MODULE 6 TIER 1

AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

3 of 8

TRENCH 4 MODULE 6 TIER 2

TIER 3

TIER 4

MODULE 7 (West coordinate 77642 to 77668)

Module 7 consists of 576 spaces for 55-gallon drums stacked in a 12 by 12 by 4 high configuration. Module 7 was built in the first half of 1980 and is assumed to contain mostly painted steel drums.

The 234-5Z (WHC) Facility generated 518 drums of waste containing 14,273 grams of plutonium and 8035 grams of uranium. There were 293 drums that had no measurable plutonium. The 2WTF (WHC) Facility generated 6 drums of soil that had no measurable plutonium. The 231-Z (PNL) Facility generated 8 drums containing 14 grams of plutonium. The 325 (WHC) Building generated 27 drums containing 563 grams of plutonium, 275 grams of uranium, and 7.0 grams of thorium. One drum had no measurable plutonium. The 325 (PNL) Facility generated 17 drums containing 5.4 grams of plutonium, and 6260 grams of uranium. There were 15 drums that had no measurable plutonium.

The Module totals include 14,860 grams of plutonium, 14,570 grams of uranium, and 7.0 grams of thorium. There were 315 drums that had no measurable plutonium. The highest plutonium loaded drum was 219 grams from 234-5Z located at position L2 of Tier 2. Of the other drums that were heavily loaded with TRU in Module 7, two drums had greater than 200 grams and 59 drums had over 100 grams. The highest dose rate value was 6 mrem/hr.

This module contains six drums from 234-5Z with greater than 12.99% ^{240}Pu . One of these, Z-PC80105, is recorded as having an unspecified mix of 8% and 22% ^{240}Pu . This drum contains 150 grams TRU. Two others are shown as 18% ^{240}Pu , Z81732248 and Z81732250, containing 64 and 73 grams TRU respectfully. Drum numbers Z-PC80104 (94 grams), Z-PC80106 (85 grams), and Z81743103 (74 grams) each are shown to contain 22% ^{240}Pu .

THIS PAGE INTENTIONALLY LEFT BLANK

TIER 1

218W4C
 Trench 4
 Module

Base Rate

Base Rate

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

Page 169

218W40
Trench

19

100% = Dose Rate
100% = 100% P

L K J I H G F E D C B A

2 3 4 5 6 7 8 9 10 11 12

TIER 3

218W40
Trench 4
1000 14

L K J I H G F E D C B A

1315

8 mR

Dose Rate
grams Pu

2
3
4
5
6
7
8
9
10
11
12

TIER 4

218W40
Trench 1

L K J I H G F E D C B A

2
3
4
5
6
7
8
9
10
11
12

100 mR
Dose Rate
Pu

TRENCH 4 MODULE 7 TIER 1

TRENCH 4
 MODULE 7
 TIER 7

TRENCH 4 MODULE 7 TIER 3

TRENCH 4 MODULE 7 TIER 4

TYPICAL HIGH Pu DRUMS (INCLUDES 2 OVER 200 grams)

ROCKWELL

234-5Z BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

Combustible # 784

4554

SOLID WASTE BURIAL RECORD

200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL DOE
By Rockwell Hanford Operations

DISPOSAL SITE		ORIGINATOR	
200-W		234-5-245-1	
AREA	BURIAL GROUND NO.	PACKAGE NO.	DOE Authorization No. (RRM)
200-W	40		
SIGNING COORDINATES		COMPANY	
NADWIE 7		Rockwell	
SEC710x2		BUILDING: 234-5	
N 40070 - 77467		AREA: 200W	
N 40070 - 77641		ADDRESS (OFF SITE)	
REMARKS		I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below, and that the contents meet RHO-MA-222 requirements and are packaged in Rockwell approved containers per RHO-MA-222.	
DATE 4-24-80		SIGNATURE	
SIGNATURE		1-2-79	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions: E.G., Sorbed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, etc.)
(Include PDR numbers and Property Control numbers)

Combustible PH WASTE FROM 234-5 IN 55 GAL PBI
 2-79-12-A-5957 + 5958 + 5965 + + 2-79-08-A-5485 + 5532
 2-79-01-A-308 + + 4029.

Container		Vol. % Combustible	
All Containers Must be Approved by Rockwell Hanford Operations		Vol. % Noncombustible	
BOX	NO.		
DRUM	NO. AND SIZE		
OTHER	NO. AND SIZE		
44.4		F33	
Approval Number		TOTAL VOLUME (ft ³)	
		Gross Weight	
		Pounds	
		Kilograms	

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS PU, CO, SF, CE, MIXED FISSION PRODUCTS, ACTIVATION PRODUCTS)

Plutonium		TRU other than Pu	
947	Grams		Grams
Fissile Content		ACTIVITY (if TRU or U, only units in Grams required)	
	Grams	1567.7	
DOSE RATE		CURIES	
5 mR/hr at 3			
DISTRIBUTION:		BY SHIPPER	
WHITE		BY ROCKWELL	
YELLOW		- SEE 2780-E	
PIRE		- ALL LAB MATERIALS, 2704-E	
GOLDENROD - RETAIN		- RETURN TO SHIPPER	

Combustible # 724

[illegible]

* Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet!

Certified By: Supervisors

Date _____

DISPOSAL SITE:

DISPOSAL SITE.

Area	Burial Ground No	Trench No.
------	------------------	------------

Area	Burial Ground No.	Trench No.
------	-------------------	------------

Caisson No.	Coordinates
	North: West:

Version No.	Coordinates
Module/E 7	North: 40020 West: 22667

Remarks:

Remarks:

Signature _____

Date _____

Signature _____

Date _____

DRUGS ARE ACCEPTED PER SOP

Distribution:

Signature _____

Date _____

All Assembly Spomenik Categories:

Pink - To Be Returned

White & Yellow - With Shipment of 40 Returned Cows Desired.

DISTRIBUTION: White - Back of
Blue - Back of
Green - Physical
Canary - Shipper
Pink - Receiver

GOLDENROD WORKING COPY 10-1-82

Combustible

Rockwell Hanford Operations

SS MATERIAL ITEM TRANSFER

784

1 From Item 2 From Item 3 From Item 4 Proc	5 Shipper's Signature	6 Date	7 To Bldg	8 To Room	9 To Hood	10 Proc	11 Receiver's Signature
12 10-20 Ratio	13 Material Description	14 Balances DOE Numbers					

Waste Drums

15	16		17		18		19		20		21		22		23		24		25		26		27		28		29		30	
	From	To	From	To	Number	SEAL	Date	Can No	Qty	Alt Code	Wt %	Mid	Gross	Net	Alt Code	Wt %	Mid	Gross	Net	Alt Code	Wt %	Mid	Gross	Net	Alt Code	Wt %	Mid	Gross	Net	Alt Code
					2904																									
					2908																									
					2912																									
					6876																									
					6556																									
					6295																									

31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

FOUR COPY RECEIVED

Combustible 805

SOLID WASTE BURIAL RECORD

DOG AREA PLATEAU DISPOSAL SITE OPERATED FOR RL-008
By Rockwell Hanford Operations*MIT-4636*
805 (49)

DISPOSAL SITE		This portion of form to be completed by Rockwell Representative at Disposal Site.		ORIGINATOR <i>2345-240-222-23-11</i>	
AREA <i>200-W</i>	BURIAL GROUND NO. <i>4C</i>	TRENCH NO. <i>4</i>		PACKAGE NO.	DOE Authorization No. (RRM)
<i>Module 7</i>	BEGINNING COORDINATES <i>N 40070 E 77667</i>		COMPANY <i>Rockwell</i>		
<i>Section 2</i>	ENDING COORDINATES <i>N 40070 E 77641</i>		BUILDING: <i>234-5</i> AREA: <i>200W</i>		
REMARKS			ADDRESS (OFF SITE)		
DATE <i>1-18-80</i>			TIME <i>4-14-80</i>		
SIGNATURE <i>R.W. L. [Signature]</i>			SIGNATURE <i>[Signature]</i> <i>1/18/80</i>		
PHYSICAL DESCRIPTION					
WATER AL CONTENTS (NOTE any special conditions) E.G., Gelled, Solid, Unsoluble, Pumps, Sampling or Laboratory Order Waste, Timbers, Resin. (Include PDR numbers and Property Control numbers)					

*COMBUSTIBLE - E-79-03-A-3602 + E-79-77-08-463**E-77-10-A-2873 + E-77-11-A-3105 + E-77-12-A-3249**E-78-01-A-3486 + E-77-15-A-2924*

Container		NO.	LENGTH	WIDTH	HEIGHT	Vol. % Combustible
All Containers Must be Approved by Rockwell Hanford Operations	BOX					
	DRUM	NO. AND SIZE <i>7</i>	<i>55 GAL.</i>			Vol. % Noncombustible
	OTHER	NO. AND SIZE				
Approval Number(s)		TOTAL VOLUME (FT ³)		Gross Weight		Pounds Kilograms
		<i>51.1</i>				

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs mixed with or without products; ACTIVATION PRODUCTS)

PH

Plutonium		TRU other than Pu		ACTIVITY (if TRU or U, only units in Grams required)	
<i>506</i> Grams	<i>506</i> Grams	<i>440</i> Grams	<i>440</i> Grams	<i>757</i> Grams	<i>757</i> Grams
Fissile Content		URANIUM		ENRICHMENT	
<i>440</i> Grams		<i>440</i> Grams		<i>757</i> Grams	
DOSE RATE		mR/hr at		SURFACE INCHES FEET	
<i>15</i>		<i>3</i>		<i>3</i>	
DISTRIBUTION:		BY SHIPPER		BY ROCKWELL	
WHITE YELLOW PINK GOLDENROD - RETAIN		WITH SHIPMENT		WHITE - SEE 2750-6 YELLOW - N. CLEAR WATER ONLY 2750-6 PINK - RETURN TO SHIPPER	

MIT 4631
SWR 305

COMBUSTIBLE 805

Rockwell Hanford Operations TRANSURANIC DRY WASTE STORAGE

3452-240-80-30

Non-Combustible Materials*					Combustible Materials*				
Drum No.	Grams Fitted Material	Measurement Method	Operator	Trench	Drum No.	Grams Fitted Material	Measurement Method	Operator	Trench
220	25402	30			220	25402	30		
225	19-77-05	127			225	19-77-05	127		
232	2-77-10	137			232	2-77-10	137		
233	2-77-11	1219			233	2-77-11	1219		
229	2-77-12	111			229	2-77-12	111		
225	2-77-04	46			225	2-77-04	46		
226	2-77-10	128			226	2-77-10	128		

*Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet

Continued By (Supervisor)

Date

1/15/80

DISPOSAL SITE			DISPOSAL SITE:		
Area	Burial Ground No.	Trench No.	Area	Burial Ground No.	Trench No.
			20. W	4C	4
Caisson No.	Coordinates		Caisson No.	Coordinates	
	North: West:		Module 7	North: 40020 West: 77667	
Remarks:			Remarks:		
			SECTION 2	40020	WEST 77664
Signature	Date		Signature	Date	
			R. W. Carter	7-14-80	
DRUMS ARE ACCEPTED PER SOP			Distribution		
Signature	Date		All Accompany Shipment if Completed Pink - To Be Returned White & Yellow - With Shipment if No Returned Copy Desired.		
K. W. Liden	1-18-80				

DRUMS WITH SOIL

ROCKWELL

2WTF (TANK FARM)

THIS PAGE INTENTIONALLY LEFT BLANK

COMBUSTIBLE #1

SOLID WASTE BURIAL RECORD			43C		#12	
200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL-DOE By Rockwell Hanford Operations						
DISPOSAL SITE			ORIGINATOR 2 WTF-RHO-80-23-28			
AREA	BURIAL GROUND NO.	TRENCH NO.	PACKAGE NO.	DOE AUTHORIZATION No. (RHO)		
200-W	4C	4	#1			
Module 7	= 40070 - 77667		COMPANY			
SECTION 1	= 40070 - 77641		Rockwell			
REMARKS			BUILDING: 361-B5 Rockwell AREA: 200-E			
			ADDRESS (OFF SITE)			
DATE			I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RHO-MA-222 requirements and are packaged in Rockwell approved containers per RHO-MA-222.			
SIGNATURE			SIGNATURE			
R. W. Carter			12-12-79			

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions: F.G., Sealed liquid, Disolver, Pump, Sampling or Laboratory paper waste, Tumblers, Reels. Include POC numbers and Property Control numbers)						
CONTAMINATED SOIL IN PLASTIC BAGS.						
P5-79-08-001 + 002 + 003 + 004 + 005 + 006						
Vol. % Combustible						
80%						
Vol. % Noncombustible						
20%						
Container	BOX	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD CARDBOARD
All Containers Must be Approved by Rockwell Hanford Operations	DRUM	NO. AND SIZE				B5-79-08-001
		6 55 GAL BARRELS				
	OTHER	NO. AND SIZE				
Approval Number(s)		TOTAL VOLUME (FT ³)		Gross Weight		☐ Pounds ☐ Kilograms
		44.4				

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (N.E. Long-lived isotopes such as Pu, Co, Sr, Cs mixed fission products; activation products)						
Pu, Am, Cs, Sr						
Plutonium		TRU other than Pu				
* Grams		* Grams				
Fission Content		Uranium		ACTIVITY (N TRU or U, only units in Grams required)		
* Grams		* Grams		* Curies		
DOSE RATE		R/R/h		* Curies		
3				☒ SURFACE ☐ INDOOR ☐ FEET		
DISTRIBUTION:		BY SHIPPER		BY ROCKWELL		
WHITE		DATE SHIPPED		WHITE - 000, 2700-E		
YELLOW				YELLOW - 000, 2700-E		
RED				RED - 000, 2700-E		
COLORS - 000, 2700-E						

43C

ALL ACCOMPANYING SHIPMENT IF COMPLETED
 WITH YELLOW SHIPMENT IF NO RETURNED COPY
 WITH YELLOW SHIPMENT IF NO RETURNED COPY

MODULE 8 (West coordinate 77668 to 77694)

Module 8 consists of 576 spaces for 55-gallon drums stacked in a 12 by 12 by 4 high configuration. Module 8 was built in April through Oct. of 1980. Starting in mid 1980 galvanized drums were specified for TRU waste storage. However, the existing inventory of painted drums continued in use for a part of the waste generated after mid-1980 due to a shortage of galvanized drums. Also a number of previously generated painted drums continued to be transferred to the trenches for at least another year.

The 325 (WHC) Facility generated 53 drums containing 596 grams of plutonium, and 77 grams of uranium. There were 30 drums that had no measurable plutonium. The 234-5Z (WHC) Facility generated 457 drums of waste containing 24,504 grams of plutonium, 26,023 grams of uranium, and 1000 grams of thorium. There were 97 drums that had no measurable plutonium. The 209E (PNL) Facility generated 9 drums containing 21.0 grams of plutonium. The 233S (WHC) Facility generated 27 drums containing 36 grams of plutonium, six drums had no measurable plutonium. The 340 (WHC) Facility generated 24 drums containing 279 grams of plutonium, 8287 grams of uranium, and 912 grams of thorium. There were 8 drums that had no measurable plutonium. The 340 (PNL) Facility generated 15 drums containing 1300 grams of uranium, and 300 grams of thorium, but no plutonium. Up to eight of the drums from the 340 Bldg contain animal waste.

The Module totals include 25,440 grams of plutonium, 35,690 grams of uranium, and 2210 grams of thorium. The records for this module show about ten more drums than there are spaces. There were 155 drums that had no measurable plutonium. The highest plutonium loaded drums were two from 234-5Z located in position A12 Tier 2, and A5 Tier 3. There were 96 drums that contained more than 100 grams of plutonium. The maximum dose rate recorded was 6 mrem/hr.

It is planned to remove a sample of 59 drums from this module for inspection and characterization from rows E, F, G, and H positions 1, 2, 3, and 4 in Tiers 2, 3, and 4; from rows E, G, H, positions 1, 2, 3 in Tier 1; and from row F positions 1 and 2, also in Tier 1. This will delete about 3,254 grams TRU from the module total. Included will be two drums of high ²⁴⁰Pu (12.99%) containing 270 grams TRU.

There are six drums of 234-5Z TRU waste containing Plutonium with ²⁴⁰Pu content higher than 12.99%:

LC800701	7.2/7.7/8/9.99/11/12.9/22.6%	164 grams
LC800702	8/11/12/ 21.962%	110
11740254	17.999%	192
2774-117	15.999%	157
2774-125	"	91
2774-0391	"	161

THIS PAGE INTENTIONALLY LEFT BLANK

TIER 1

218W4C
Trench 4
Module 8

No known data

$\mu_{\text{H}} > 1 \text{ mR}$

Yellow # = Dose Rate
White # = grams Pu

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TIER 2

218W4C
French

L K J I H G F E D C B A

Dose-Rate
Pu

2
3
4
5
6
7
8
9
10
11
12

K J H G F E D C B A

TIER 3

218W40

Trend:

mmR

Dose Rate

Rate

2
3
4
5
6
7
8
9
10
11
12

018W:4C

ZC

 α

Use Rate

15

HGFEDCBA

2 3 4 5 6 7 8 9 10 11 12

TRENCH 4
 MODULE 8
 TIER 1

TRENCH 4 MODULE 8 TIER 2

TRENCH 4 MODULE 8 TIER 3

TRENCH 4 MODULE 8 TIER 4

TYPICAL DRUM
PNL
340 BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

COMBUSTIBLE # B 881

(13)

SOLID WASTE BURIAL RECORD 200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE By Rockwell Hanford Operations	B-881
--	--------------

DISPOSAL SITE This portion of form to be completed by Rockwell Representative at Disposal site.		ORIGINATOR 340-PNL-80-80-1-8	
AREA 200-W	BURIAL GROUND NO. 4C	TRENCH NO. 4	PACKAGE NO. DOE Authorization No (RRM) B-881
MOD. 15 8 SECTION-3	DESIGNED COORDINATES = 40000 = 77694 COINED COORDINATES = 40000 = 77668		COMPANY BNW
REMARKS		BUILDING 340	AREA 300
DATE 7-16-80		ADDRESS (OFF SITE)	
SIGNATURE B.W. Conner		SIGNATURE Jan C. M. S. C.	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Barbed liquid, Discolor, Pumps, Sampling or Laboratory glass waste, Tumors, Rusts. (Include PDR numbers and Property Control numbers)						
Paper 15% DRUG # BN 80-609-610-614-613-615-						
Plastic 35% 616-617, 618						
Metal 10%						
Waste 25%						
Criminal Waste 15% S.F.R.F. 7693768, 7697						
Container All Containers Must be Approved by Rockwell Hanford Operations	BOX NO. AND SIZE	LENGTH	WIDTH	HEIGHT	WEIGHT	Vol. % Combustible 50% Vol. % Radioactive 0% ☐ HANFORD STANDARD CARDS
	DRUM NO. AND SIZE 8 55gal drums.					
	OTHER					
Approval Number(s)		TOTAL VOLUME (FT ³) 6000		Gross Weight 1000		☒ Pounds ☐ Kilograms

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., Low-lived isotopes such as Pu, Co, Sr, Cs, mixed fission products, activation products)						
Pu Pu						
Plutonium 3.5 Grams TRU other than Pu ☒ Grams						
Fission Content 15.81 Grams		Uranium 1300 Grams		Activity (in TRU or U, only units in Grams required) 917		Dose Rate <6 mR/hr
Distribution:						
BY SHIPPER						
BY ROCKWELL						
Date: 7-16-80 Tel: 7-16-80 PDR: 7-16-80 Collection: 7-16-80						

Rockwell Hanford Operations		COMBUSTIBLE DRY WASTE STORAGE	
(13)		B-881 SWIFT B-881	
NON-COMBUSTIBLE MATERIALS		COMBUSTIBLE MATERIALS B-881	
DATE NO	LEADS NO	DATE NO	LEADS NO
ESTIMATE	ESTIMATE	ESTIMATE	ESTIMATE
OPERATION	OPERATION	OPERATION	OPERATION
REMARK	REMARK	REMARK	REMARK
1 - 609	EST	0	EST
2 - 610	EST	0	EST
3 - 613	EST	0	EST
4 - 614	3.5	4554	24-150
5 - 615	EST	0	EST
6 - 616	EST	0	EST
7 - 617	EST	0	EST
8 - 618	EST	0	EST
B-881			
DISPOSAL SITE:			
DATE: 6/12/80		DISPOSAL SITE:	
ESTIMATE: 210.2		ESTIMATE: 210.2	
LEADS NO: 4000		LEADS NO: 4000	
OPERATION: 27668		OPERATION: 27668	
REMARK: 27668		REMARK: 27668	
DATE: 6/12/80		DATE: 6/12/80	
ESTIMATE: 210.2		ESTIMATE: 210.2	
LEADS NO: 4000		LEADS NO: 4000	
OPERATION: 27668		OPERATION: 27668	
REMARK: 27668		REMARK: 27668	

TYPICAL DRUM
ROCKWELL
233-S BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

COMBUSTIBLE

SOLID WASTE BURIAL RECORD

200 AREA PLATRAU DISPOSAL SITE OPERATED FOR RL - DOE
By Rockwell Hanford Operations 2335-CH-8-8

M-8 M-9
S-4 S-1
N-44C N-44C

002-103

DISPOSAL SITE This portion of form to be completed by Rockwell Representative at Disposal Site. ORIGINATOR 20 21-31

AREA 300-W	BURIAL GROUND NO. 4C	TRENCH NO. 4	DOE Authorization No (RRM) 44C + 4
Module 8	DESIGNING COORDINATES 40070 - 77694	385	PROPERTY P.H.O.
SECTION 4	LOCUS COORDINATES 40070 - 77668	411	BUILDING 233-S
Module 9	40070	77696	AREA 200 W
SECTION 1	40070	77721	ADDRESS (OFF SITE)
DATE 10-10-80	TIME	I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RMO-MA-222 requirements and are packaged in Rockwell approved containers per RMO-MA-222.	
SIGNATURE R.W. Carls	SIGNATURE J.C. Cund		DATE 9/11/80

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Sealed liquid, Disolver, Pump, Sampling or Laboratory paper waste, Timbers, Ream. (Include PDR numbers and Property Control numbers)

Metal from Load out Hood in Plastic, Decan White, Paper Bags, in TRU DEUM. From 233-S in 55 gal BBI METAL 5 = PIN 31 PAPER 32 C104 32

UC-233-S-80-8-3 + 4 + 5 + 6 + 7 + 8 - 9

UC-233-S-80-8-14 + 15 + 16 + 18

Container	BOX	NO.	LENGTH	WIDTH	HEIGHT	Vol. & No. Containers
All Containers Must be Approved by Rockwell Hanford Operations	DRUM	55 gal. BBI.				95
	OTHER					05

Approval Number(s) **USAC-80-059** TOTAL VOLUME (FT³) **87.4** Gross Weight **3500**

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., Long-lived isotopes such as Pu, Co, Sr, Cs; mixed fission products; activation products)

PH

Plutonium 13 Grams	TRU other than Pu Grams	
Fission Content Grams	URANIUM Grams	ACTIVITY (if TRU or U, only units in Grams required)
DOSE RATE 11 mR/hr		EXPOSURE ☒ SURFACE ☐ INSIDE ☐ FEET

DISTRIBUTION:	BY SHIPPER	BY ROCKWELL
WHITE	WITH SHIPMENT	WHITE - SEE 2700-2
YELLOW		YELLOW - NUCLEAR MATERIALS, 2700-2
PUR		PUR - RETURN TO SHIPPER
SOLENDOR - RETURN		

AC 6800 076 (A-4.79)

MODULE 9 (West coordinate 77694 to 77720)

Module 9 consists of 562 spaces for 55 gallon drums stacked in a 12 by 12 by 4 high configuration. The other 14 spaces that would be normally occupied by 55 gallon drums contain seven L-10 containment systems for which the outer container consists of two 55 gallon drums welded together, end-to-end. Module 9 was built during the last quarter of 1980 and the first quarter of 1981 so it is assumed that the drums are still mostly painted steel but with galvanized drums appearing in greater number.

Module 9 contains 398 drums generated by the 234-5Z Facility with 6107 grams of plutonium; however, 303 drums had no measurable plutonium and many of these are probably non-transuranic (non-TRU). The 340 (PNL) Facility generated 61 drums containing 422 grams of plutonium, 3252 grams of uranium, and 391 grams of thorium. There were 17 of these drums that exhibited no measurable TRU. The 340 (WHC) Facility generated 24 drums containing 188 grams of plutonium with 8 drums containing no measurable plutonium. The ESG (CAN) generated 40 drums containing 169 grams of plutonium and 477 grams of uranium. The WARD (WEC) Facility generated 52 drums containing 86 grams of plutonium and 229 grams of uranium. The Exxon (ENC) operation generated a drum with 56 grams of plutonium and 837 grams of uranium. The 231-Z (PNL) Building generated a drum containing 1.0 gram of plutonium. In total the module contains known drums containing 7030 grams of plutonium, 4800 grams of uranium, and 390 grams of thorium. There were 353 drums that had no measurable plutonium.

The highest plutonium content drum contains 197 grams and is located in tier 2, position A 12. The highest dose rate recorded was 6 mrem/hr for several drums.

The module contains two drums from 234-5Z with 19.99% ^{240}Pu :

2775-4571	117 grams
2775-4572	73

The drum from EXXON is 18% ^{240}Pu , the ESG (Canoga Park) drums are a little less than 12% ^{240}Pu , and the WARD waste appears to be about 12%.

The L-10 containers occupy positions C-3 through C-9 in tiers 3 and 4 and contain a total of 74 grams TRU.

THIS PAGE INTENTIONALLY LEFT BLANK

2
3
4
5
6
7
8
9
10
11
12

mR

Rate

2.

TIER 2

218W-40
Trench -

L K J I H G F E D C B A

2
3
4
5
6
7
8
9
10
11
12

L K I H G F E D C B A

TIER 3

218W4C

Trench -

2
3
4
5
6
7
8
9
10
11
12

L K J I H G F E D C B A

TIER 4

218W4C
Trench 4

2
3
4
5
6
7
8
9
10
11
12

TRENCH 4 MODULE 9 TIER 1

TRENCH 4 MODULE 9 TIER 2

TRENCH 4 MODULE 9 TIER 3

TRENCH 4 MODULE 9 TIER 4

L10/10L CONTAINERS

ROCKWELL

234-5Z BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

10-L CONTAINERS

COMBUSTIBLE 1040

WHC-SD-W113-ACDR-001

Rev. 0

Page 211

SOLID WASTE BURIAL RECORD			1040 (49C) OK	
200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE By Rockwell Hanford Operations				
DISPOSAL SITE		This portion of form to be completed by Rockwell Representative at Disposal site.		
AREA 200-W	BURIAL GROUND NO. 4C	TRENCH NO. 4	ORIGINATOR 23452-RHO-81-14	DOE Authorization No (RRM) 650
Medium 9	BEGINNING COORDINATES N 40070 W 77696-333		COMPANY ROCKWELL	
SECTION 3	ENDING COORDINATES N 40070 W 77721-358		BUILDING 234-5	AREA 200 W
REMARKS			ADDRESS (OFF SITE)	
DATE 4-9-81			TIME	
SIGNATURE R.W. Carter			SIGNATURE [Signature] 1/8/81	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Sorbed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Fibers, Resin.
(Include PDR numbers and Property Control numbers)

10 L's CONTAINING 10L bottles FROM 234-5
R-266, 464, 460, 501, 515, 292, 517

Container		NO.	LENGTH	WIDTH	HEIGHT	Vol. % Combustible
All Containers Must be Approved by Rockwell Hanford Operations	BOX					
	DRUM	NO. AND SIZE				Vol. % Noncombustible
	OTHER	NO. AND SIZE				50
Approval Number(s) HWS-10242		TOTAL VOLUME (FT ³) 102.2		Gross Weight 2185		☒ Pounds ☐ Kilograms

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)

Pu Pu

Plutonium 7446 Grams	TRU other than Pu Grams	ACTIV (If TRU or U, only units in Grams required)
Fissile Content 6840 Grams	URANIUM Grams	ENRICHMENT 91%
DOSE RATE 10 mR/hr at 3		☐ SURFACE ☐ INCHES ☒ FEET
DISTRIBUTION:		BY ROCKWELL
WHITE } WITH SHIPMENT YELLOW } PINK } GOLDENROD - RETAIN		WHITE - SWS-2700-E YELLOW - NUCLEAR MATERIALS, 2700-E PINK - RETURN TO SHIPPER

WHC-SD-W113-ACDR-001

Rev. 0

Page 211A

THIS PAGE INTENTIONALLY LEFT BLANK

TYPICAL DRUMS
ENERGY SYSTEM GROUP (ESG)
ROCKWELL INTERNATIONAL
CANOGA PARK

THIS PAGE INTENTIONALLY LEFT BLANK

CANOGA PARK
COMBUSTIBLE RRM-3309

M-9
S-1
N-47C

TU	SOLID WASTE BURIAL RECORD	(67)
	200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL-DOE By Rockwell Hanford Operations	

DISPOSAL SITE		This portion of form to be completed by Rockwell Representative at Disposal Site		ORIGINATOR <u>ESG-CAN-80-1-19 OK</u>	
AREA <u>200-W</u>	BURIAL GROUND NO. <u>4C</u>	TRENCH NO. <u>4</u>	PACKAGE NO. <u>CANOGA PARK RC-19-3309</u>	RRM	DOE Authorization No. (RRM) <u>3309-47C</u>
COMBUSTIBLE <u>1000/L 9</u>	DECOMPOSITION COORDINATES <u>N 40070 - 77694 30</u>		COMPANY <u>Energy Systems Group</u> <u>Rockwell International</u>		
SECTION <u>L</u>	COORDINATES <u>N 40070 - 77721 35</u>		BUILDING <u>T064</u> AREA <u>Santa Susana</u>		
REMARKS			ADDRESS (OFF SITE) <u>8900 DeSoto</u> <u>Canoga Park, California 91304</u>		
DATE <u>10-13-80</u>			TIME		
SIGNATURE <u>R. W. Cordier</u>			SIGNATURE <u>9/12 Schaubert</u> 9-12-80		

PHYSICAL DESCRIPTION					
MATERIAL CONTENTS (Note any special conditions) E.G., Solvent, Heavy, Disposer, Pump, Sampling or Laboratory paper waste, Tins, Resin, (Include PDR numbers and Property Control Numbers)					
PU-EU WASTE: 19 ea. combustible, 21 ea. non-combustible (8 solidified liquid, 2 chem line, 7 equipment, 4 meatl etc). Solidified liquid in plastic bottles inside 4"x8" sphincter cans. Combustible and non-combustible inside same type cans. Cans packaged two or three per poly bag packaged inside tape sealed 12 mil polyvinyl-chloride bage inside					
drums. Plastic 25 Rubber 25				Vol. 2 Combustible <u>40</u>	Vol. 2 Noncombustible <u>60</u>
Container	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD CARDBOARD
All Containers Must be Approved by Rockwell Hanford Operations	BOX	NO. AND SIZE			
DRUM	NO. AND SIZE				
OTHER		<u>RRM-3309</u> <u>23 + 24 + 25 + 26 + 27 + 28 + 29 + 30 + 31 + 32 + 33 + 34 + 35</u>			
Approval Number(s)		TOTAL VOLUME (FT ³)		Gross Weight	
		<u>200 - 176.6</u>		☐ Pounds ☐ Kilograms	

ACTIVITY DESCRIPTION					
GENERAL ACTIVITY DESCRIPTION (E.G., Low-lived isotopes such as Pu, Co, Sr, Cesium fission products; activation products)					
Primarily mixed Pu-Eu @ 72% U-235 (18 grams depleted U 419 grams @ 72%)					
58 grams @ min enrichment					
Plutonium (50.1%)	TRU other than Pu				
<u>169</u> Grams	☒ Grams				
Plutonium Content	URANIUM 18 grams U and 477 Grams 72% enrichment	ACTIVITY (in TRU or U, only units in Grams required)			
		CURIES			
DOSE RATE		☒ SURFACE ☐ INGESTED ☐ INJECTED			
<u>1</u> R/hr					
DISTRIBUTION:		BY SHIPPER		BY ROCKWELL	
WHITE		WHITE		WHITE - 200, 2700-E	
YELLOW		YELLOW		YELLOW - NUCLEAR MATERIALS, 2700-E	
PINK		PINK		PINK - RETURN TO SHIPPER	
SOLIDIFIED - OCEAN					

ESG-CAN-00-1

67

TYPICAL ADVANCED FUEL WASTE BARREL

ESG-CAN-80-1

(67)

Page 1 of 2

All gamma-scanned waste and chem line waste is contained in 4-inch-diameter x 8-inch sphincter cans packaged 2 or 3 cans to poly bag and placed in 1 poly bag in a 55-gallon 17H container. Approximately 50 cans per 17H drum.

Contaminated equipment is bagged in poly and placed in a poly-lined 55-gallon 17H container.

$$Ci = 1.82 Ci / gram Pu$$

Gamma-Scanned Waste									
Drum No.	Seal No.	Material	gms U	U-235	gms	U-235	gms	U-235	gms
P-01	10605	Combustible Waste-1	10.48	72.000	7.55	4.45	83.161	3.92	3.1
P-09	10695	Noncombustible Waste	4.45	72.000	3.21	2.69	83.161	2.37	1.4
P-10	10361	Combustible Waste-2	12.25	72.000	8.82	5.97	83.161	5.27	10.9
P-11	10663	Combustible Waste 12500-3	10.99	72.000	7.91	4.42	83.161	3.90	8.0
P-13	10697	Noncombustible Waste	3.91	72.000	2.82	1.95	83.161	1.72	3.6
P-14	10698	Solidified Liquid Waste	49.74	69.458	34.55	13.81	83.161	16.66	34.2
P-15	10662	Solidified Liquid Waste 12443	41.00	72.000	29.82	29.11	83.161	28.11	57.7
P-16	10365	Combustible Waste-4	5.00	72.000	3.60	1.20	83.161	1.11	2.3
P-18	10692	Solidified Liquid Waste	2.40	72.000	1.73	0.78	83.161	0.69	1.4
P-19	10683	Combustible Waste-5	10.00	72.000	7.20	4.07	83.161	3.59	7.4
P-20	10693	Solidified Liquid Waste	1.06	72.000	0.78	0.51	83.161	0.45	0.9
P-21	10689	Combustible Waste-6	12.17	72.000	8.76	4.11	83.161	3.62	7.6
P-22	10690	Combustible Waste-7	9.71	72.000	6.99	3.13	83.161	2.76	5.7
P-23	10687	Combustible Waste-8	6.24	72.000	4.49	2.66	83.161	1.82	3.7
P-24	10238	Combustible Waste-9	1.63	72.000	1.17	0.52	83.161	0.46	0.9
P-25	10237	Combustible Waste-10	3.11	72.000	2.24	1.74	83.161	1.53	3.2
P-26	10227	Combustible Waste-11	2.56	72.000	1.94	2.98	83.161	2.63	5.4
P-27	10225	Combustible Waste-12	5.43	72.000	3.91	3.39	83.161	2.99	6.2
P-28	10873	Combustible Waste-13	4.95	72.000	3.57	2.02	83.161	1.78	3.7
P-29	10879	Combustible Waste-14	6.51	72.000	4.69	2.69	83.161	2.37	4.9
P-30	10380	Combustible Waste-15	3.73	72.000	2.69	0.92	83.161	0.81	1.7
P-31	11681	Combustible Waste-16	3.47	72.000	2.53	0.93	83.161	0.81	1.7
P-32	11684	Noncombustible Waste	11.43	72.000	8.24	4.88	83.161	3.90	8.0
		O ₂ Waste from GB-18	15.05	24.252	3.65	1.77	83.161	1.56	3.2
		Noncombustible Carbon Waste	30.37	72.000	21.87	7.82	83.161	6.89	14.3
		Carbon Waste from GB-18	48.82	63.068	30.79	11.22	83.161	9.94	20.5
		Carbon Waste from GB-18	18.35	0.204	0.04	-	-	-	-
P-33	11685	Combustible Waste-17	7.36	72.000	1.70	0.92	83.161	0.81	1.7
P-34	11686	Combustible Waste-18	5.89	72.000	4.24	3.70	83.161	3.26	6.7

Seal # on drums P-11 + P-15 did not coincide with shipment records. Contacted VJ. Schaubert at Rockwell International Energy System Group, Fontana Park Calif. Seals were broken when truck was loaded, and seals were replaced but paper work was not changed. Cummins was given by VJ Schaubert to change seal numbers on paper. 2 Putman

Page 2 of 2

ES6-CAN-PD-1

(67)

Gamma-Scanned Waste			U-235		Pu 239 & 241		Calculated Ci	
Drum No.	Seal No.	Material	gms U	gms	gms Pu	gms		
P-35	11687	Solidified Liquid Waste	2.44	72.000	1.76	88.161	1.47	3.0
P-36	11688	Solidified Liquid Waste	5.47	72.000	3.94	88.161	2.76	5.7
P-37	11690	Solidified Liquid Waste	2.47	72.000	1.78	88.161	1.44	3.0
P-39	13103	Combustible Waste	2.43	72.000	1.75	88.161	1.32	2.7
P-40	13102	Solidified Liquid Waste	1.79	72.000	1.29	88.161	0.71	1.5
P-38	13101	Non-Combustible Waste	1.30	72.000	0.94	88.161	0.65	1.3
Total Gamma-Scanned Waste			Enr. 340.61	232.46	138.44	122.59		
			Dep. 18.35	0.04				

Solidified Chem. Line Waste								
P-12	10264	Chemistry Waste	20.88	11.111	2.32	88.161	1.09	2.2
		Chemistry Waste	1.52	17.105	.26	88.161	.08	0.2
		Chemistry Waste	3.69	72.000	2.66	88.161	1.26	2.6
P-17	10517	Chemistry Waste	60.63	72.000	43.66	88.161	14.89	30.7
		Chemistry Waste	22.20	9.009	2.00	88.161	3.66	7.6
		Chemistry Waste	13.76	23.416	3.91	88.161	1.26	2.6
Total Solidified Chem. Line Waste			122.08	54.81	25.25	22.24		

Contaminated Equipment								
P-02	10372	Contaminated Equipment	1.50	72.000	1.09	88.161	.47	1.0
P-03	10373	Contaminated Equipment	1.01	72.000	.73	88.161	.20	0.4
P-04	10374	Contaminated Equipment	.14	72.000	.10	88.161	.01	0.001
P-05	10370	Contaminated Equipment	3.06	72.000	2.20	88.161	1.73	3.6
P-06	10371	Contaminated Equipment	1.96	72.000	1.41	88.161	.51	1.1
P-07	10375	Contaminated Equipment	.94	72.000	.68	88.161	.17	0.3
P-08	10269	Contaminated Equipment	5.57	72.000	4.01	88.161	1.60	3.3
Total Contaminated Equipment			14.18	10.21	5.30	4.62		

Total Waste for Disposal			Enr. U 477.47	237.48	169.09	149.51		
			Dep. U 18.35	0.04				

COMB 42118.91

SINGLE DRUM
EXXON NUCLEAR
RICHLAND

THIS PAGE INTENTIONALLY LEFT BLANK

COMBUSTIBLE

M-9
S-4
H-320

SOLID WASTE BURIAL RECORD 200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL DOE By Rockwell Hanford Operations		738 (74) 5
--	--	------------

DISPOSAL SITE <small>This portion of form is to be completed by Rockwell Representative at Disposal site.</small>		ORIGINATOR Exxon-EXC-M-1 220-OK	
AREA 200-W	BURIAL GROUND NO. 4C	TRENCH NO. 4	PACKAGE NO. RRM-3421-22-3
DESCRIPTORS Module 7 SECTION 4		DESCRIPTORS = 40020 - 27696 383 = 40020 - 27721 358 77721	DOE Authorization No (RRM) 3421
REMARKS		COMPANY Exxon Nuclear Co.	BUILDING HO Building
DATE 4-22-81		AREA Horn Rapids	
SIGNATURE <i>R. W. Carter</i>		ADDRESS (OFF SITE) 2101 Horn Rapids Road Richland, Washington	
TIME		SIGNATURE <i>R. W. Carter</i>	
TIME		DATE 1/29/81	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions: E.G., Solids liquid, Discolor, Pump, Sampling or Laboratory paper waste, Timbers, Rods, etc.) (Include PQR numbers and Property Control numbers)						
Drum Assay Standards - PuO ₂ blended with wood chips and packaged in plastic bottles in metal cans; polyethylene liner used in drums.						
Vol. % Combustible 95%						Vol. % Noncombustible 5%
Container All Containers Must be Approved by Rockwell Hanford Operations						☐ HANFORD STANDARD CARDBOARD
BOX	NO.	LENGTH	WIDTH	HEIGHT	☐ POUNDS ☐ KILOGRAMS	
DRUM	NO. AND SIZE 1 - 17 C 55 Gallon Drum					
OTHER	NO. AND SIZE					
Approval Number(s)	TOTAL VOLUME (FT³) 7.4	Gross Weight 165			☒ POUNDS ☐ KILOGRAMS	

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPE SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)			
Plutonium Oxide <i>Pu</i>			
Plutonium 56.47 Grams	TRU other than Pu Grams	ACTIVITY (If TRU or U, only units in Grams required) 337.356	
Fission Content 45.6 Grams	URANIUM 0 Grams	ENRICHMENT 0	SUBS ☒ SURFACE ☐ INSIDE ☐ FEET
DOSE RATE 6 m R/hr			
DISTRIBUTION:		BY SHIPPER	
WHITE } WITH SHIPMENT YELLOW } PINK } COLORLESS - RETAIN		BY ROCKWELL WHITE - ONE, 2700-1 YELLOW - NUCLEAR MATERIALS, 2700-1 PINK - RETURN TO SHIPPER	

14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.000000	14.0
-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	------

[illegible]

THIS PAGE INTENTIONALLY LEFT BLANK

TYPICAL DRUMS
WESTINGHOUSE ADVANCED REACTOR DIVISION (WARD)
CHESWICK

THIS PAGE INTENTIONALLY LEFT BLANK

COMBUSTIBLE FRA 3389-3 M-4
S-4

<p>SOLID WASTE BURIAL RECORD</p> <p>200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL-DOE By Rockwell Hanford Operations</p>		<p>N-21-0</p> <p>686 (73) OK</p>
--	--	----------------------------------

<p>DISPOSAL SITE This portion of form to be completed by Rockwell Representative at Disposal Site.</p>		<p>ORIGINATOR <u>WARD-WEC-Pi-F-23 210</u></p>	
<p>AREA <u>200-W</u></p>	<p>BURIAL GROUND NO. <u>4C</u></p>	<p>TRENCH NO. <u>4</u></p>	<p>PACKAGE NO. <u>6 Model 6272 W/M-II bin</u></p>
<p>CONTAINER <u>Module 9</u></p>	<p>DESCRIPTIVE COORDINATES <u>-40070 - 77696</u></p>	<p>DOE AUTHORIZATION NO. (RRM) <u>3389-3</u></p>	<p>COMPANY <u>Westinghouse Electric Corporation</u></p>
<p>SECTION <u>4</u></p>	<p>COORDINATES <u>-40070 - 77721</u></p>	<p>ADVANCED REACTOR DIVISION</p>	<p>BUILDING</p>
<p>REMARKS</p>		<p>ADDRESS (OFF SITE) <u>Cheswick Avenue</u> <u>Cheswick, PA. 15024</u></p>	
<p>DATE <u>4-21-81</u></p>	<p>TIME</p>	<p>I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RMO-MA 222 requirements and are packaged in Rockwell approved drums for RMO-MA-222.</p>	
<p>SIGNATURE <u>B. W. Carter</u></p>		<p>SIGNATURE <u>D. J. Petard</u></p>	<p>DATE <u>1-20-81</u></p>

<p>PHYSICAL DESCRIPTION</p>					
<p>MATERIAL CONTENTS (Note any special conditions: E.G., Sealed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Resin. (Include PDR numbers and Property Control numbers))</p>					
<p>Six Argonne M-III bins each containing 8 DOT 17C steel drums totalling 48 drums for burial: 4 are painted, 44 are galvanized. Waste volume %'s are as follows: 42.86% scrap metal & equipment, 23.30% plastic, 19.25% paper, 11.81% rubber, 0.50% glass, 1.21% granite, 0.26% wood, 0.41% clean absorbant, 0.11% in-solution, & 0.05% rags.</p>					
<p>Container</p>	<p>BOX</p>	<p>NO.</p>	<p>LENGTH</p>	<p>WIDTH</p>	<p>HEIGHT</p>
<p>Drum <u>23</u></p>	<p>DRUM</p>	<p>SIZE <u>DOT 17C</u></p>	<p>55-Gallon Steel Drums</p>	<p>MANFORD STANDARD CARDBOARD</p>	<p>Vol. % Composites <u>47.9</u></p>
<p>OTHER</p>	<p>72.5</p>	<p>2951.0</p>	<p>369.43</p>	<p>7.678</p>	<p>Vol. % Noncomposites <u>52.1</u></p>
<p>Approval Number(s) <u>3389-3-1 thru 48</u></p>	<p>TOTAL VOLUME (FT³)</p>	<p>Gross Weight</p>	<p>POUNDS</p>	<p>Kilograms</p>	

<p>ACTIVITY DESCRIPTION</p>					
<p>GENERAL ACTIVITY DESCRIPTION (E.G., Long-lived isotopes such as Pu, Co, Sr, Cs; fission products; activation products)</p>					
<p>All materials listed in the physical description section are contaminated with the following radio-nuclides: <u>238, 239, 240, 241, 242 Pu</u> except drum A-028 which also includes <u>232 Th</u></p>					
<p>Plutonium <u>92</u></p>	<p>TRU other than Pu</p>	<p>Grams <u>190 g @ 79.3, 29 Kg @ .7, and 2 Kg @ .22</u></p>	<p>ACTIVITY (if TRU or U, only units in Grams required)</p>	<p>COEFFICIENT</p>	<p>COEFF</p>
<p>Fission Content <u>239</u></p>	<p>URANIUM</p>	<p>Grams</p>	<p>DOSE RATE (M-III B.A.S.) (For drums, see other documents)</p>	<p>DOSE RATE</p>	<p>DOSE RATE</p>
<p>DOSE RATE (M-III B.A.S.) <u>≤ 0.2</u></p>	<p>DOSE RATE</p>	<p>DOSE RATE</p>	<p>DOSE RATE</p>	<p>DOSE RATE</p>	<p>DOSE RATE</p>
<p>DISTRIBUTION:</p>	<p>BY SHIPPER</p>	<p>BY ROCKWELL</p>	<p>WHITE - 800, 2700-2</p>	<p>YELLOW - NUCLEAR MATERIALS, 2700-2</p>	<p>DOSE - RETURN TO SHIPPER</p>

RM-3389-3

COMBUSTIBLE PMA-3337-3400-WFC-11-1

Rockwell Hanford Operations					TRANSURANIC DRY WASTE STORAGE					Check One: ☒ Combustible ☐ Non-Combustible	
Non-Combustible Materials*					Combustible Materials*					21-D	
Drum No.	Grams Free Material	Measurement Method	Operator	Trench	Drum No.	Grams Free Material	Measurement Method	Operator	Trench		
34=	3.957			1	80-A-051	<1	7	NDA	578	9.4.21D	
17=	604.22			2	80-A-050	Ø		NDA	578	9.4.21D	
23=	41.652			3	80-A-052	Ø		NDA	578	9.4.21D	
19=	.001			4	80-A-111	Ø		NDA	578	9.4.21D	
				5	80-A-048	6	7	NDA	578	9.4.21D	
				6	80-A-108	Ø		NDA	578	9.4.21D	
				7	80-A-107	Ø		NDA	578	9.4.21D	
				8	80-A-105	Ø		NDA	578	9.4.21D	
				9	80-A-104	Ø		NDA	578	9.4.21D	
				10	80-A-103	Ø		NDA	578	9.4.21D	
				11	80-A-049	5	7	NDA	578	9.4.21D	
				12	80-A-102	Ø		NDA	578	9.4.21D	
				13	80-A-047	Ø		NDA	578	9.4.21D	
				14	80-A-040	18	7	NDA	578	9.4.21D	
				15	80-A-047	Ø		NDA	578	9.4.21D	
				16	80-A-042	14	7	NDA	578	9.4.21D	
				17	80-A-114	Ø		NDA	578	9.4.21D	
				18	80-A-119	1	7	NDA	578	9.4.21D	
				19	80-A-116	Ø		NDA	578	9.4.21D	
				20	80-A-117	Ø		NDA	578	9.4.21D	
				21	80-A-046	1	7	NDA	578	9.4.21D	
				22	80-031	22	7	NDA	578	9.4.21D	
				23	80-A-113	3	7	NDA	578	9.4.21D	

* Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet

Certified By (Supervisor)

J. B. Pinner

Date

1-20-81

DISPOSAL SITE:				DISPOSAL SITE:			
Area	Barrel Ground No.	Trench No.		Area	Barrel Ground No.	Trench No.	
				21D-W	4C	4	
Carton No.	Coordinates	North:	West:	Carton No.	Coordinates	North:	West:
				Module 9		4412D	77696
Remarks:				Section 4		4007D	77224
Signature				Signature			
Date				Date			
				4-21-87			
DRUMS ARE ACCEPTED PER SOP				Distribution:			
Signature				All Accompanying Shipment if Completed			
Date				Fins - To Be Returned			
				White & Yellow - With Shipment if Not Returned Case Desired.			
J. W. Carls							
4-20-81							

MODULE 10 (West coordinate 77720 to 77746)

Module 10 consists of 535 painted steel and galvanized 55 gallon drums stacked in a 12 by 12 by 4 high configuration and an 8' by 11.5' by 5.5' high box, weighing 15,000 pounds, from the 308 Bldg. The box is located on the bottom two tiers in the northeast corner of the module. Module 10 was built during 1981.

The 234-5Z Facility generated 262 drums containing 4554 grams of plutonium; 188 of those drums did not have any accountable plutonium (potential transuranic only). The WARD (WEC) Facility generated 48 drums containing 95 grams of plutonium, and 156 grams of uranium. The Babcox (APA) Facility generated 142 drums containing 2105 grams of plutonium, 4559 grams of uranium, and 3.43 grams of americium. The Vallecitos (GE) Facility generated 69 drums of waste containing 205 grams of plutonium, and 18,519 grams of uranium. The 340 (WHC) Facility generated 22 drums containing 120 grams of plutonium, and 25,900 grams of uranium. The 308 Building generated the box which contains less than 0.5 grams of plutonium and 1.0 gram of uranium. The 231-Z (PNL) Building generated a drum of waste with no measurable quantity of plutonium or uranium.

The totals show 544 drums of record containing 7080 grams of plutonium, 49,130 grams of uranium, and 3.43 grams of americium. The drum exhibiting the highest plutonium loading is 191 grams, located at tier 2, position L-2. The highest measured dose rate was 150 mrem/hr from four drums generated at the 234-5Z plant facility. Except for a number of other drums at 10 mrem/hr the rest are single digit dose rates.

The module contains waste from 234-5Z in drum # 2774-2391 with 178 grams of TRU with 19.99% ²⁴⁰Pu and drum # 797391-655 with 176 grams of 14.78% ²⁴⁰Pu.

The box is recorded as containing 75% metal and 25% plastic. The metallic contents are a Kemp dryer, two vacuum pumps, four Callahan welders, two furnaces, a centrifugal pump, a microscope, a Mettler balance, a Carver press, and a vacuum cleaner.

GE-VAL reports four drums containing copper, 17 with oil, and 30 with antifreeze and oil. WARD reports 39 drums containing oil and 9 drums with organics.

THIS PAGE INTENTIONALLY LEFT BLANK

L K J I H G F E D C B A

TIER 1

218W4C

Trench 4

Module 10

Site

mR

Dose Rate

h/s Pu

2
3
4
5
6
7
8
9
10
11
12

2
3
4
5
6
7
8
9
10
11
12

1112

Cost Rate

 

218VV4C
Trench 4
Trench 4

H G F E D C B A

3
4
5
6
7
8
9
10
11
12

WHC-SD-W113-ACDR-001
Rev. 0
Page 227

TIER 4

218W 40
Trend 4

L K J I H G F E D C B A

1
2
3
4
5
6
7
8
9
10
11
12

Use Rate
100%

TRENCH 4 MODULE 10 TIER 1

TRENCH 4 MODULE 10 TIER 2

TRENCH 4 MODULE 10 TIER 3

TRENCH 4 MODULE 10 TIER 4

TYPICAL DRUMS
GE VALECITOS
PLEASANTON

THIS PAGE INTENTIONALLY LEFT BLANK

Combustible 1379-3597-1

SOLID WASTE BURIAL RECORD 200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL-003 By Rockwell Hanford Operations			M-12 (69) 1379 N-E2
DISPOSAL SITE This portion of form is to be completed by Rockwell Representative at Disposal Site.		ORIGINATOR <i>GE-Vol-fi-1-38</i> OK	
AREA 200-W	BURIAL GROUND NO. 4C	TRENCH NO. 4	PACKAGE NO. N55#1
BEGINNING COORDINATES N 40070 = 777-22 358'		DOE Authorization No (RRM) 22M-3597-1	
ENDING COORDINATES N 40070 = 777-28 358'		COMPANY General Electric Co. (Advanced Fuels Lab)	
REMARKS		BUILDING: 102 AREA: C	
DATE 7-20-81		ADDRESS (OFF SITE) P.O. Box 460 Pleasanton, CA 94566	
SIGNATURE <i>R. W. Carter</i>		SIGNATURE <i>Richard A. Holtz</i>	

PHYSICAL DESCRIPTION MATERIAL CONTENTS (Note any special conditions: E.G., Serbed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Resin. (include PDR numbers and Property Control numbers))					
COMBUSTIBLES: 5% wood, rubber, oil, 10% paper, 20% cotton (padding, wipes, etc.) and 55% plastic (plexiglass, etc.) NON-COMBUSTIBLES: 1% molybdenum (furnace boats), marble slabs, carborundum (frinding wheels), 3% sand, 4% diatomaceous earth (to absorb oil/water) 5% misc (cement, other metals, etc.) 10% copper wiring, ceramic insulation, glass vessels, 20% Spn. Srl. & carbon steel tools, 15% aluminum.					
Vol. % Combustible					35%
Vol. % Noncombustible					65%
Container All Containers Must be Approved by Rockwell Hanford Operations	BOX NO. N/A	LENGTH N/A	WIDTH N/A	HEIGHT N/A	☐ HANFORD STANDARD CARDBOARD
	DRUM NO. AND SIZE Thirty-eight (38) 55-gallon (17H and/or 17C)				
	OTHER NO. AND SIZE N/A				
Approval Number(s)	TOTAL VOLUME (FT ³) 285	Gross Weight 11,030	☒ Pounds ☐ Kilograms		

ACTIVITY DESCRIPTION GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)					
Pu238, 239, 240, 241 & 242; U234, 235, 236 & 238; Np237					
Plutonium 91.73 Grams	TRU other than Pu N/A Grams				
Fissile Content 80.85 Grams	URANIUM 199.53 Grams	.7110 ENRICHMENT	ACTIVITY (If TRU or U, only units in Grams required) 144.45 Ci		
DOSE RATE < 0.1 mR/hr		☐ SURFACE ☐ INTERIOR ☒ FEET			
DISTRIBUTION:		BY SHIPPER			
WHITE YELLOW PINK GOLDENROD - RETAIN		WITH SHIPMENT			
		BY ROCKWELL			
		WHITE - GWS, 2700-6 YELLOW - NUCLEAR MATERIALS, 2700-6 PINK - RETURN TO SHIPPER			

Recovery Letter #
PSL April 21 - PSL-90-22

COMBUSTIBLE RRM-3597-2

APRIL

Q-90-1304

M-10
S-1+2
N E4

SOLID WASTE BURIAL RECORD 200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL-DOE By Rockwell Hanford Operations		69 29-22
--	--	-------------

DISPOSAL SITE This portion of form to be completed by
Rockwell Representative at Disposal Site.

AREA <u>900-W</u>	BURIAL GROUND NO. <u>4C</u>	TRENCH NO. <u>4</u>
Module ID <u>SECTION 1+2</u>	RECORDING COORDINATES <u>- 40070 - 77722</u> RECORDING COORDINATES <u>- 40070 - 77748</u>	
REMARKS <u>SURVEY No# 1609</u>		
DATE <u>7-22-81</u>	TIME	
SIGNATURE <u>R.W. Carter</u>		

ORIGINATOR GE-Ud-M-7 EL

PACKAGE NO. <u>N5512</u>	DOE AUTHORIZATION by (RWM) <u>RM-3597-2</u> <u>CA</u>
COMPANY <u>General Electric Company</u>	
BUILDING <u>102</u>	AREA <u>C</u>
ADDRESS (OFF SITE) <u>P.O. Box 460</u> <u>Pleasanton, CA 94566</u>	
I certify that no capital property is included in this burial unless docu- mented by a Property Document Register, and that the contents meet RM-3597-2 requirements and are packaged in Rockwell approved containers per RM-3597-2.	
SIGNATURE <u>Judith A. Harty</u>	<u>5/18/81</u>

PHYSICAL DESCRIPTION

MATERIAL CONTENTS Note any special conditions (e.g., Sealed liquid, Disposer, Pump, Sampling or Laboratory paper waste, Timbers, Ropes,
Include PDR numbers and Property Control numbers)

→ COMBUSTIBLE: 45% plastic, 15% cotton, 10% paper, 20% oil, 4% anti-freeze, 4% wood, 2% misc.

NON-COMBUSTIBLE: 23% carbon steel, 23% diatomaceous earth, 22% stainless steel, 8% aluminum

NEW 6% glass, 5% misc. (other metals, metal-x fire extinguisher powder, grind-
RECORD 1/2 wheels, etc.) 4% copper, 1% molybdenum

Vol. % Combustible	<u>29%</u>
Vol. % Noncombustible	<u>80%</u>

Container	BOX	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD CARDBOARD	
All Containers Must be Approved by Rockwell Hanford Operations	DRUM	NO. AND SIZE <u>31</u>	<u>OR</u> <u>Thirty-eight (38) 55-gallon drums (17B and/or 17C)</u>				
	OTHER	NO. AND SIZE <u>N/A</u>					
Approved Number(s)	TOTAL VOLUME (FT ³)		<u>295</u>		Gross Weight	<u>10214</u>	

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (e.g., LEACHING, ISOTOPE SUCH AS Pu, Co, Sr, Cs; WIRE FISHING PRODUCT; ACTIVATION PRODUCT)

Pu 238, 239, 240, 241 & 242; U234, 235, 236 & 238

PURCHASE	TRU OTHER THAN Pu		
<u>113.25</u> Grams	<u>N/A</u> Grams		
PURCHASE	URANIUM	ACTIVITY (If TRU or U, only write in Grams, if required)	
<u>95.80</u> Grams	<u>18,319.99</u> Grams	<u>.7110</u> Curie/gram	<u>175.20</u> Curie
DOSE RATE	<u><0.5</u> mR/hr		<u>3</u>

DISTRIBUTION:

BY SHIPPER

WHITE } WITH SHIPPER
 YELLOW }
 PINK }
 GREEN - RETAIN

BY ROCKWELL

WHITE - ONE, 2700-E
 YELLOW - ONE, 2700-E
 PINK - RETURN TO SHIPPER

TYPICAL DRUMS/DRUMS WITH ORGANICS

WARD

CHESWICK

THIS PAGE INTENTIONALLY LEFT BLANK

COMBUSTIBLE PRM-3389-5

1000 1-
3 1+2
N 4E

SOLID WASTE BURIAL RECORD			1320 (73)	
250 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL-DOE By Rockwell Hanford Operations			4E OK	
DISPOSAL SITE			ORIGINATOR WARD-WEC-21-50-89	
AREA	BURIAL GROUND NO.	TRENCH NO.	PACKAGE NO.	DOE AUTHORIZATION NO. (RRM) 3389-5
200-W	4C	4	6-MOD-272 w/ M-III bin	
Module 10	DESIGN TO COORDINATES		COMPANY WESTINGHOUSE ELECTRIC CORP. ADVISED RECTOR DIVISION	
	= 40070 = 27722		BUILDING: AREA:	
SECTION 1+2	EXISTING COORDINATES		ADDRESS (OFF SITE)	
	= 40070 = 2742		Cheswick Avenue Cheswick, PA 15024	
REMARKS			I certify that no data to property is included in this burial unless documented by a Property Disposal Receipt, and described below; and that the contents meet RMO-MA-272 requirements and are packaged in Rockwell approved containers per RMO-MA-227.	
DATE	TIME		SIGNATURE	
7-20-8			D. Patara 5/15/81	
SIGNATURE				
B. W. Carter				

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions: E.G., Solids, Liquid, Disposal, Pump, Sampling or Laboratory paper waste, Timbers, Poles, etc.)
Include PDR numbers and Property Control numbers)

Six Argonne M-II bins each containing 8 DOT 17C steel drums (48 total) for burial.
Waste description volume %'s are: 32.03% metal, 24.95% paper, 24.25% plastic, 4.40% absorbent, 11.10% rubber, 1.60% wood, 1.17% oil, 0.33% rags, 0.15% stone, 0.02% glass. DRUMS A-064, A-015, A-018, A-022, A-054, & A-056
contain: ABSORBED ORGANIC MATERIAL, FLASH POINT RANGE 440-460°F

Container	NO.	LENGTH	WIDTH	HEIGHT	MAINFORD STANDARD
All Containers	BOX				CARDBOARD
Mult. or Approved by Rockwell Hanford Operations	OR 30	NO. AND SIZE	DOT 17C, 55 gallon steel drums, 6 are painted, 42 are galvanized		
OTHER		NO. AND SIZE			
Approved Number (s)	TOTAL VOLUME (FT ³)		Gross Weight		8 Pounds
3389-5-1 Box 48	360.43		2,917		Kilograms

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., Long-lived isotopes such as Pu, Co, Sr, Ce, mixed fission products, activation products)

All materials listed in the physical description section are contaminated with the following radionuclides: ²³⁴U, ²³⁵U, ²³⁶U, ²³⁸U, ²³⁸Pu, ²³⁹Pu, ²⁴⁰Pu, ²⁴¹Pu, ²⁴²Pu.

Factor	TRU other than Pu	Activity (if TRU or U, only units in G or mg required)	COEFF
11.7 54.11 Grams	16g @ 79.3, 77g @ 26.0, 12g @ 52.0, 65g @ 56.5, 44g @ 5.7	52.7	8 POUNDS
222 Grams			1000 G
DOSE RATE (M-III BINS)	12049		3
≤ 0.1			
DISTRIBUTION:		BY SHIPPER	
WHITE	WHITE	WHITE	
YELLOW	YELLOW	YELLOW	
PINK	PINK	PINK	
SELECTED - RETAIN		BY ROCKWELL	
		WHITE - ONE, 2700-E	
		YELLOW - NUCLEAR MATERIALS, 2700-E	
		PINK - RETURN TO SHIPPER	

1339-5 Combustible RRU-3288-5

Barwell Handled Operations			TRANSURANIC DRY WASTE STORAGE				Check One Combustible Non-Combustible	
Wt	PK	U	Drum No	Grams Fissile Material	Measurement N/A	Operator	Trench A-B-C	
118	.02	.06	56 ARD-9-EA-152	<1	NDA	SPD	10-2-E4	
128	.04	.05	57 " A-150	<1	NDA	SPD	10-2-E4	
153	.95	1.31	58 " A-47	2	NDA	SPD	10-2-E4	
131	.13	.08	59 " A-141	<1	NDA	SPD	10-2-E4	
99	.5	0	60 " A-153	1	NDA	SPD	10-2-E4	
145	.48	.15	61 " A-155	1	NDA	SPD	10-2-E4	
135	.05	.06	62 " A-121	<1	NDA	SPD	10-2-E4	
139	1.5	2.6	63 " A-116	5	NDA	SPD	10-2-E4	
122	0	0	64 " A-124	-0-	NDA	SPD	10-2-E4	
123	.09	.05	65 " A-130	<1	NDA	SPD	10-2-E4	
130	.01	0	66 " A-138	<1	NDA	SPD	10-2-E4	
125	.21	.1	67 " A-136	<1	NDA	SPD	10-2-E4	
115	.86	.45	68 " A-134	1	NDA	SPD	10-2-E4	
212	3.45	7.3	69 " A-064	10	NDA	SPD	10-2-E4	
132	0	.03	70 " A-126	<1	NDA	SPD	10-2-E4	
139	.03	.04	71 " A-131	<1	NDA	SPD	10-2-E4	
113	9.9	32.9	72 ARD-80-043	43	NDA	SPD	10-2-E4	
99	.16	30.2	73 ARD-80-039	46	NDA	SPD	10-2-E4	
154	.02	.06	74 ARD-80-A-018	<1	NDA	SPD	10-2-E4	
169	.01	.02	75 " A-015	<1	NDA	SPD	10-2-E4	
147	.17	.12	76 " A-122	<1	NDA	SPD	10-2-E4	
155	0	.07	77 " A-084	<1	NDA	SPD	10-2-E4	
109	0	.02	78 " A-085	<1	NDA	SPD	10-2-E4	
125	1.35	2.29	78 " A-088	3	NDA	SPD	10-2-E4	

be Material - no more - use another sheet

Signature: J. R. Carlson Date: 5-15-81

DISPOSAL SITE:			DISPOSAL SITE:		
Area	Burial Ground No	Trench No.	Area	Burial Ground No	Trench No.
210 W	4C	4	210 W	4C	4
Coordinates		North: 40070 West: 77722	Coordinates		North: 40070 West: 77722
Remarks		SE 7111-241	Remarks		41120 77748
Signature: J. E. Carlson Date: 7.20.81			Signature: J. W. Corbin Date: 7.20.81		
DRUMS ARE ACCEPTED PER SOP TO-100-322			Distribution:		
Signature: J. E. Carlson Date: 7.20.81			All Accompanying Shipment if Completed Pink - To Be Returned White & Yellow - With Shipment if No Returned Copy Desired.		

Rockwell Hanford Operations

TRANSURANIC DRY WASTE STORAGE

Line 113

Combustible (15)

Non-Combustible

Rockwell Hanford Operations			TRANSURANIC DRY WASTE STORAGE					
WT	PU	U	Drum No.	Trench	Grams Fission Material	Measurement	Operator	Trench
117	12.6	36.4	79	ARD-20-012	48	NDA	5/8	10-1-E4
141	.05	.02	80	ARD-8-90	A-022	<1	NDA	10-1-E4
147	.05	.16	81	"	A-093	<1	NDA	10-2-E4
95	5.63	5.8	82	"	A-094	12	NDA	10-1-E4
142	.03	.18	83	"	A-054	<1	NDA	10-1-E4
142	0	.02	84	"	A-056	<1	NDA	10-1-E4

*Accepted
Original*

* Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet

Certified By: (Supervisor)

D. B. Puckett

Date

5-15-81

DISPOSAL SITE:			DISPOSAL SITE:		
Area	Burial Ground No.	Trench No.	Area	Burial Ground No.	Trench No.
			200-W	4C	4
Careton No.	Coordinates		Careton No.	Coordinates	
	North:	West:	Module 10	North: 40070	West: 77722
Remarks:			Remarks:		
			Section - 122 40070 77748		
Signature			Signature		
Date			Date		
			<i>D. W. Carls</i>		
OR THIS ARE ACCEPTED PER SOP			Distribution:		
Signature			All Accompanying Shipment if Completed		
Date			Pins - To Be Returned		
<i>J. E. Puckett</i>			White & Yellow - With Shipment if No Returned Copy Desired.		
69.00			5-14-81		

COMBUSTIBLE 3389-8-8

6-29-81

SOLID WASTE BURIAL RECORD			MA 10 S-3 H A-1	
200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL DOE By Rockwell Hanford Operations			1427	
DISPOSAL SITE			ORIGINATOR	
This portion of form to be completed by Rockwell Representative at Disposal site.			WARD WEC-A1-4 RI	
AREA	BURIAL GROUND NO.	TRENCH NO.	PACKAGE NO.	DOE Authorization No (ARM) 3389-8
J00-W	4C	4	MII Bins in Mtn 172	
CONTAINER NO.	DEBRIS COORDINATES		COMPANY WESTINGHOUSE ELECTRIC CORP.	
Module 10	- 4007D - 77722		ADVANCED REACTOR DIVISION	
SECTION 3	- 4007D - 77748		BUILDINGS	
REMARKS			ADDRESS (OFF SITE)	
			CHESWICK AVE. CHESWICK, PA 15024	
DATE 7-23-81			I certify that no capital property is included in this burial unless docu- mented by a Property Disposal Request, and described below, and that the contents meet RHO MA 222 requirements and are packaged in Rockwell approved containers per RHO-MA-222.	
SIGNATURE B. W. Carter			SIGNATURE D. J. TRAFER 6/25/81	
PHYSICAL DESCRIPTION				
MATERIAL CONTENTS (Note any special conditions) E.G., Sealed liquid, Disolver, Pump, Sampling or Laboratory paper waste, Tumblers, Resin. (Include PDR numbers and Property Control numbers)				
24 - 55 gallon drums and 3 - MII steel bins for burial. Waste description volume %s are as follows 33.33% metal, 29.70% plastic, 15.69% paper, 7.22% cement, 7.00% rubber 2.97% absorbent, 1.92% rags, 0.99% oil and 0.29% wood. DRUMS A-061, A-076, A-083 contain: ABSORBENT GRANULE MATERIAL, FLASH POINT RANGE: 440-440°F				
Container	BOX	LENGTH	WIDTH	HEIGHT
All Containers Must be Approved by Rockwell Hanford Operations	DRUM	NO AND SIZE RRM 3389-B-1 through 24		
	NOTE	NO AND SIZE RRM 3389-B-25 through 27		
	OTHER	3 - MII steel bins, 24 x 5 x 5 ~125 ft ³ each		
		18 BB1		
Approval Number(s)	TOTAL VOLUME (FT ³)	Gross Weight	Pounds	
3389-8-1 thru 27	555 / 135.0	10,633	2283	
ACTIVITY DESCRIPTION				
GENERAL ACTIVITY DESCRIPTION (E.G., Long-lived isotopes such as Pu, Co, Sr, Cesium fission products, activation products)				
All materials listed in the physical description section are contaminated with the following radionuclides: ²³⁴ Pu, ²³⁵ Pu, ²³⁸ Pu, ²³⁹ Pu, ²⁴⁰ Pu, ²⁴¹ Pu, ²⁴² Pu, ²⁴³ Pu, ²⁴⁴ Pu, ²⁴⁵ Pu, ²⁴⁶ Pu, ²⁴⁷ Pu, ²⁴⁸ Pu, ²⁴⁹ Pu, ²⁵⁰ Pu, ²⁵¹ Pu, ²⁵² Pu, ²⁵³ Pu, ²⁵⁴ Pu, ²⁵⁵ Pu, ²⁵⁶ Pu, ²⁵⁷ Pu, ²⁵⁸ Pu, ²⁵⁹ Pu, ²⁶⁰ Pu, ²⁶¹ Pu, ²⁶² Pu, ²⁶³ Pu, ²⁶⁴ Pu, ²⁶⁵ Pu, ²⁶⁶ Pu, ²⁶⁷ Pu, ²⁶⁸ Pu, ²⁶⁹ Pu, ²⁷⁰ Pu, ²⁷¹ Pu, ²⁷² Pu, ²⁷³ Pu, ²⁷⁴ Pu, ²⁷⁵ Pu, ²⁷⁶ Pu, ²⁷⁷ Pu, ²⁷⁸ Pu, ²⁷⁹ Pu, ²⁸⁰ Pu, ²⁸¹ Pu, ²⁸² Pu, ²⁸³ Pu, ²⁸⁴ Pu, ²⁸⁵ Pu, ²⁸⁶ Pu, ²⁸⁷ Pu, ²⁸⁸ Pu, ²⁸⁹ Pu, ²⁹⁰ Pu, ²⁹¹ Pu, ²⁹² Pu, ²⁹³ Pu, ²⁹⁴ Pu, ²⁹⁵ Pu, ²⁹⁶ Pu, ²⁹⁷ Pu, ²⁹⁸ Pu, ²⁹⁹ Pu, ³⁰⁰ Pu, ³⁰¹ Pu, ³⁰² Pu, ³⁰³ Pu, ³⁰⁴ Pu, ³⁰⁵ Pu, ³⁰⁶ Pu, ³⁰⁷ Pu, ³⁰⁸ Pu, ³⁰⁹ Pu, ³¹⁰ Pu, ³¹¹ Pu, ³¹² Pu, ³¹³ Pu, ³¹⁴ Pu, ³¹⁵ Pu, ³¹⁶ Pu, ³¹⁷ Pu, ³¹⁸ Pu, ³¹⁹ Pu, ³²⁰ Pu, ³²¹ Pu, ³²² Pu, ³²³ Pu, ³²⁴ Pu, ³²⁵ Pu, ³²⁶ Pu, ³²⁷ Pu, ³²⁸ Pu, ³²⁹ Pu, ³³⁰ Pu, ³³¹ Pu, ³³² Pu, ³³³ Pu, ³³⁴ Pu, ³³⁵ Pu, ³³⁶ Pu, ³³⁷ Pu, ³³⁸ Pu, ³³⁹ Pu, ³⁴⁰ Pu, ³⁴¹ Pu, ³⁴² Pu, ³⁴³ Pu, ³⁴⁴ Pu, ³⁴⁵ Pu, ³⁴⁶ Pu, ³⁴⁷ Pu, ³⁴⁸ Pu, ³⁴⁹ Pu, ³⁵⁰ Pu, ³⁵¹ Pu, ³⁵² Pu, ³⁵³ Pu, ³⁵⁴ Pu, ³⁵⁵ Pu, ³⁵⁶ Pu, ³⁵⁷ Pu, ³⁵⁸ Pu, ³⁵⁹ Pu, ³⁶⁰ Pu, ³⁶¹ Pu, ³⁶² Pu, ³⁶³ Pu, ³⁶⁴ Pu, ³⁶⁵ Pu, ³⁶⁶ Pu, ³⁶⁷ Pu, ³⁶⁸ Pu, ³⁶⁹ Pu, ³⁷⁰ Pu, ³⁷¹ Pu, ³⁷² Pu, ³⁷³ Pu, ³⁷⁴ Pu, ³⁷⁵ Pu, ³⁷⁶ Pu, ³⁷⁷ Pu, ³⁷⁸ Pu, ³⁷⁹ Pu, ³⁸⁰ Pu, ³⁸¹ Pu, ³⁸² Pu, ³⁸³ Pu, ³⁸⁴ Pu, ³⁸⁵ Pu, ³⁸⁶ Pu, ³⁸⁷ Pu, ³⁸⁸ Pu, ³⁸⁹ Pu, ³⁹⁰ Pu, ³⁹¹ Pu, ³⁹² Pu, ³⁹³ Pu, ³⁹⁴ Pu, ³⁹⁵ Pu, ³⁹⁶ Pu, ³⁹⁷ Pu, ³⁹⁸ Pu, ³⁹⁹ Pu, ⁴⁰⁰ Pu, ⁴⁰¹ Pu, ⁴⁰² Pu, ⁴⁰³ Pu, ⁴⁰⁴ Pu, ⁴⁰⁵ Pu, ⁴⁰⁶ Pu, ⁴⁰⁷ Pu, ⁴⁰⁸ Pu, ⁴⁰⁹ Pu, ⁴¹⁰ Pu, ⁴¹¹ Pu, ⁴¹² Pu, ⁴¹³ Pu, ⁴¹⁴ Pu, ⁴¹⁵ Pu, ⁴¹⁶ Pu, ⁴¹⁷ Pu, ⁴¹⁸ Pu, ⁴¹⁹ Pu, ⁴²⁰ Pu, ⁴²¹ Pu, ⁴²² Pu, ⁴²³ Pu, ⁴²⁴ Pu, ⁴²⁵ Pu, ⁴²⁶ Pu, ⁴²⁷ Pu, ⁴²⁸ Pu, ⁴²⁹ Pu, ⁴³⁰ Pu, ⁴³¹ Pu, ⁴³² Pu, ⁴³³ Pu, ⁴³⁴ Pu, ⁴³⁵ Pu, ⁴³⁶ Pu, ⁴³⁷ Pu, ⁴³⁸ Pu, ⁴³⁹ Pu, ⁴⁴⁰ Pu, ⁴⁴¹ Pu, ⁴⁴² Pu, ⁴⁴³ Pu, ⁴⁴⁴ Pu, ⁴⁴⁵ Pu, ⁴⁴⁶ Pu, ⁴⁴⁷ Pu, ⁴⁴⁸ Pu, ⁴⁴⁹ Pu, ⁴⁵⁰ Pu, ⁴⁵¹ Pu, ⁴⁵² Pu, ⁴⁵³ Pu, ⁴⁵⁴ Pu, ⁴⁵⁵ Pu, ⁴⁵⁶ Pu, ⁴⁵⁷ Pu, ⁴⁵⁸ Pu, ⁴⁵⁹ Pu, ⁴⁶⁰ Pu, ⁴⁶¹ Pu, ⁴⁶² Pu, ⁴⁶³ Pu, ⁴⁶⁴ Pu, ⁴⁶⁵ Pu, ⁴⁶⁶ Pu, ⁴⁶⁷ Pu, ⁴⁶⁸ Pu, ⁴⁶⁹ Pu, ⁴⁷⁰ Pu, ⁴⁷¹ Pu, ⁴⁷² Pu, ⁴⁷³ Pu, ⁴⁷⁴ Pu, ⁴⁷⁵ Pu, ⁴⁷⁶ Pu, ⁴⁷⁷ Pu, ⁴⁷⁸ Pu, ⁴⁷⁹ Pu, ⁴⁸⁰ Pu, ⁴⁸¹ Pu, ⁴⁸² Pu, ⁴⁸³ Pu, ⁴⁸⁴ Pu, ⁴⁸⁵ Pu, ⁴⁸⁶ Pu, ⁴⁸⁷ Pu, ⁴⁸⁸ Pu, ⁴⁸⁹ Pu, ⁴⁹⁰ Pu, ⁴⁹¹ Pu, ⁴⁹² Pu, ⁴⁹³ Pu, ⁴⁹⁴ Pu, ⁴⁹⁵ Pu, ⁴⁹⁶ Pu, ⁴⁹⁷ Pu, ⁴⁹⁸ Pu, ⁴⁹⁹ Pu, ⁵⁰⁰ Pu, ⁵⁰¹ Pu, ⁵⁰² Pu, ⁵⁰³ Pu, ⁵⁰⁴ Pu, ⁵⁰⁵ Pu, ⁵⁰⁶ Pu, ⁵⁰⁷ Pu, ⁵⁰⁸ Pu, ⁵⁰⁹ Pu, ⁵¹⁰ Pu, ⁵¹¹ Pu, ⁵¹² Pu, ⁵¹³ Pu, ⁵¹⁴ Pu, ⁵¹⁵ Pu, ⁵¹⁶ Pu, ⁵¹⁷ Pu, ⁵¹⁸ Pu, ⁵¹⁹ Pu, ⁵²⁰ Pu, ⁵²¹ Pu, ⁵²² Pu, ⁵²³ Pu, ⁵²⁴ Pu, ⁵²⁵ Pu, ⁵²⁶ Pu, ⁵²⁷ Pu, ⁵²⁸ Pu, ⁵²⁹ Pu, ⁵³⁰ Pu, ⁵³¹ Pu, ⁵³² Pu, ⁵³³ Pu, ⁵³⁴ Pu, ⁵³⁵ Pu, ⁵³⁶ Pu, ⁵³⁷ Pu, ⁵³⁸ Pu, ⁵³⁹ Pu, ⁵⁴⁰ Pu, ⁵⁴¹ Pu, ⁵⁴² Pu, ⁵⁴³ Pu, ⁵⁴⁴ Pu, ⁵⁴⁵ Pu, ⁵⁴⁶ Pu, ⁵⁴⁷ Pu, ⁵⁴⁸ Pu, ⁵⁴⁹ Pu, ⁵⁵⁰ Pu, ⁵⁵¹ Pu, ⁵⁵² Pu, ⁵⁵³ Pu, ⁵⁵⁴ Pu, ⁵⁵⁵ Pu, ⁵⁵⁶ Pu, ⁵⁵⁷ Pu, ⁵⁵⁸ Pu, ⁵⁵⁹ Pu, ⁵⁶⁰ Pu, ⁵⁶¹ Pu, ⁵⁶² Pu, ⁵⁶³ Pu, ⁵⁶⁴ Pu, ⁵⁶⁵ Pu, ⁵⁶⁶ Pu, ⁵⁶⁷ Pu, ⁵⁶⁸ Pu, ⁵⁶⁹ Pu, ⁵⁷⁰ Pu, ⁵⁷¹ Pu, ⁵⁷² Pu, ⁵⁷³ Pu, ⁵⁷⁴ Pu, ⁵⁷⁵ Pu, ⁵⁷⁶ Pu, ⁵⁷⁷ Pu, ⁵⁷⁸ Pu, ⁵⁷⁹ Pu, ⁵⁸⁰ Pu, ⁵⁸¹ Pu, ⁵⁸² Pu, ⁵⁸³ Pu, ⁵⁸⁴ Pu, ⁵⁸⁵ Pu, ⁵⁸⁶ Pu, ⁵⁸⁷ Pu, ⁵⁸⁸ Pu, ⁵⁸⁹ Pu, ⁵⁹⁰ Pu, ⁵⁹¹ Pu, ⁵⁹² Pu, ⁵⁹³ Pu, ⁵⁹⁴ Pu, ⁵⁹⁵ Pu, ⁵⁹⁶ Pu, ⁵⁹⁷ Pu, ⁵⁹⁸ Pu, ⁵⁹⁹ Pu, ⁶⁰⁰ Pu, ⁶⁰¹ Pu, ⁶⁰² Pu, ⁶⁰³ Pu, ⁶⁰⁴ Pu, ⁶⁰⁵ Pu, ⁶⁰⁶ Pu, ⁶⁰⁷ Pu, ⁶⁰⁸ Pu, ⁶⁰⁹ Pu, ⁶¹⁰ Pu, ⁶¹¹ Pu, ⁶¹² Pu, ⁶¹³ Pu, ⁶¹⁴ Pu, ⁶¹⁵ Pu, ⁶¹⁶ Pu, ⁶¹⁷ Pu, ⁶¹⁸ Pu, ⁶¹⁹ Pu, ⁶²⁰ Pu, ⁶²¹ Pu, ⁶²² Pu, ⁶²³ Pu, ⁶²⁴ Pu, ⁶²⁵ Pu, ⁶²⁶ Pu, ⁶²⁷ Pu, ⁶²⁸ Pu, ⁶²⁹ Pu, ⁶³⁰ Pu, ⁶³¹ Pu, ⁶³² Pu, ⁶³³ Pu, ⁶³⁴ Pu, ⁶³⁵ Pu, ⁶³⁶ Pu, ⁶³⁷ Pu, ⁶³⁸ Pu, ⁶³⁹ Pu, ⁶⁴⁰ Pu, ⁶⁴¹ Pu, ⁶⁴² Pu, ⁶⁴³ Pu, ⁶⁴⁴ Pu, ⁶⁴⁵ Pu, ⁶⁴⁶ Pu, ⁶⁴⁷ Pu, ⁶⁴⁸ Pu, ⁶⁴⁹ Pu, ⁶⁵⁰ Pu, ⁶⁵¹ Pu, ⁶⁵² Pu, ⁶⁵³ Pu, ⁶⁵⁴ Pu, ⁶⁵⁵ Pu, ⁶⁵⁶ Pu, ⁶⁵⁷ Pu, ⁶⁵⁸ Pu, ⁶⁵⁹ Pu, ⁶⁶⁰ Pu, ⁶⁶¹ Pu, ⁶⁶² Pu, ⁶⁶³ Pu, ⁶⁶⁴ Pu, ⁶⁶⁵ Pu, ⁶⁶⁶ Pu, ⁶⁶⁷ Pu, ⁶⁶⁸ Pu, ⁶⁶⁹ Pu, ⁶⁷⁰ Pu, ⁶⁷¹ Pu, ⁶⁷² Pu, ⁶⁷³ Pu, ⁶⁷⁴ Pu, ⁶⁷⁵ Pu, ⁶⁷⁶ Pu, ⁶⁷⁷ Pu, ⁶⁷⁸ Pu, ⁶⁷⁹ Pu, ⁶⁸⁰ Pu, ⁶⁸¹ Pu, ⁶⁸² Pu, ⁶⁸³ Pu, ⁶⁸⁴ Pu, ⁶⁸⁵ Pu, ⁶⁸⁶ Pu, ⁶⁸⁷ Pu, ⁶⁸⁸ Pu, ⁶⁸⁹ Pu, ⁶⁹⁰ Pu, ⁶⁹¹ Pu, ⁶⁹² Pu, ⁶⁹³ Pu, ⁶⁹⁴ Pu, ⁶⁹⁵ Pu, ⁶⁹⁶ Pu, ⁶⁹⁷ Pu, ⁶⁹⁸ Pu, ⁶⁹⁹ Pu, ⁷⁰⁰ Pu, ⁷⁰¹ Pu, ⁷⁰² Pu, ⁷⁰³ Pu, ⁷⁰⁴ Pu, ⁷⁰⁵ Pu, ⁷⁰⁶ Pu, ⁷⁰⁷ Pu, ⁷⁰⁸ Pu, ⁷⁰⁹ Pu, ⁷¹⁰ Pu, ⁷¹¹ Pu, ⁷¹² Pu, ⁷¹³ Pu, ⁷¹⁴ Pu, ⁷¹⁵ Pu, ⁷¹⁶ Pu, ⁷¹⁷ Pu, ⁷¹⁸ Pu, ⁷¹⁹ Pu, ⁷²⁰ Pu, ⁷²¹ Pu, ⁷²² Pu, ⁷²³ Pu, ⁷²⁴ Pu, ⁷²⁵ Pu, ⁷²⁶ Pu, ⁷²⁷ Pu, ⁷²⁸ Pu, ⁷²⁹ Pu, ⁷³⁰ Pu, ⁷³¹ Pu, ⁷³² Pu, ⁷³³ Pu, ⁷³⁴ Pu, ⁷³⁵ Pu, ⁷³⁶ Pu, ⁷³⁷ Pu, ⁷³⁸ Pu, ⁷³⁹ Pu, ⁷⁴⁰ Pu, ⁷⁴¹ Pu, ⁷⁴² Pu, ⁷⁴³ Pu, ⁷⁴⁴ Pu, ⁷⁴⁵ Pu, ⁷⁴⁶ Pu, ⁷⁴⁷ Pu, ⁷⁴⁸ Pu, ⁷⁴⁹ Pu, ⁷⁵⁰ Pu, ⁷⁵¹ Pu, ⁷⁵² Pu, ⁷⁵³ Pu, ⁷⁵⁴ Pu, ⁷⁵⁵ Pu, ⁷⁵⁶ Pu, ⁷⁵⁷ Pu, ⁷⁵⁸ Pu, ⁷⁵⁹ Pu, ⁷⁶⁰ Pu, ⁷⁶¹ Pu, ⁷⁶² Pu, ⁷⁶³ Pu, ⁷⁶⁴ Pu, ⁷⁶⁵ Pu, ⁷⁶⁶ Pu, ⁷⁶⁷ Pu, ⁷⁶⁸ Pu, ⁷⁶⁹ Pu, ⁷⁷⁰ Pu, ⁷⁷¹ Pu, ⁷⁷² Pu, ⁷⁷³ Pu, ⁷⁷⁴ Pu, ⁷⁷⁵ Pu, ⁷⁷⁶ Pu, ⁷⁷⁷ Pu, ⁷⁷⁸ Pu, ⁷⁷⁹ Pu, ⁷⁸⁰ Pu, ⁷⁸¹ Pu, ⁷⁸² Pu, ⁷⁸³ Pu, ⁷⁸⁴ Pu, ⁷⁸⁵ Pu, ⁷⁸⁶ Pu, ⁷⁸⁷ Pu, ⁷⁸⁸ Pu, ⁷⁸⁹ Pu, ⁷⁹⁰ Pu, ⁷⁹¹ Pu, ⁷⁹² Pu, ⁷⁹³ Pu, ⁷⁹⁴ Pu, ⁷⁹⁵ Pu, ⁷⁹⁶ Pu, ⁷⁹⁷ Pu, ⁷⁹⁸ Pu, ⁷⁹⁹ Pu, ⁸⁰⁰ Pu, ⁸⁰¹ Pu, ⁸⁰² Pu, ⁸⁰³ Pu, ⁸⁰⁴ Pu, ⁸⁰⁵ Pu, ⁸⁰⁶ Pu, ⁸⁰⁷ Pu, ⁸⁰⁸ Pu, ⁸⁰⁹ Pu, ⁸¹⁰ Pu, ⁸¹¹ Pu, ⁸¹² Pu, ⁸¹³ Pu, ⁸¹⁴ Pu, ⁸¹⁵ Pu, ⁸¹⁶ Pu, ⁸¹⁷ Pu, ⁸¹⁸ Pu, ⁸¹⁹ Pu, ⁸²⁰ Pu, ⁸²¹ Pu, ⁸²² Pu, ⁸²³ Pu, ⁸²⁴ Pu, ⁸²⁵ Pu, ⁸²⁶ Pu, ⁸²⁷ Pu, ⁸²⁸ Pu, ⁸²⁹ Pu, ⁸³⁰ Pu, ⁸³¹ Pu, ⁸³² Pu, ⁸³³ Pu, ⁸³⁴ Pu, ⁸³⁵ Pu, ⁸³⁶ Pu, ⁸³⁷ Pu, ⁸³⁸ Pu, ⁸³⁹ Pu, ⁸⁴⁰ Pu, ⁸⁴¹ Pu, ⁸⁴² Pu, ⁸⁴³ Pu, ⁸⁴⁴ Pu, ⁸⁴⁵ Pu, ⁸⁴⁶ Pu, ⁸⁴⁷ Pu, ⁸⁴⁸ Pu, ⁸⁴⁹ Pu, ⁸⁵⁰ Pu, ⁸⁵¹ Pu, ⁸⁵² Pu, ⁸⁵³ Pu, ⁸⁵⁴ Pu, ⁸⁵⁵ Pu, ⁸⁵⁶ Pu, ⁸⁵⁷ Pu, ⁸⁵⁸ Pu, ⁸⁵⁹ Pu, ⁸⁶⁰ Pu, ⁸⁶¹ Pu, ⁸⁶² Pu, ⁸⁶³ Pu, ⁸⁶⁴ Pu, ⁸⁶⁵ Pu, ⁸⁶⁶ Pu, ⁸⁶⁷ Pu, ⁸⁶⁸ Pu, ⁸⁶⁹ Pu, ⁸⁷⁰ Pu, ⁸⁷¹ Pu, ⁸⁷² Pu, ⁸⁷³ Pu, ⁸⁷⁴ Pu, ⁸⁷⁵ Pu, ⁸⁷⁶ Pu, ⁸⁷⁷ Pu, ⁸⁷⁸ Pu, ⁸⁷⁹ Pu, ⁸⁸⁰ Pu, ⁸⁸¹ Pu, ⁸⁸² Pu, ⁸⁸³ Pu, ⁸⁸⁴ Pu, ⁸⁸⁵ Pu, ⁸⁸⁶ Pu, ⁸⁸⁷ Pu, ⁸⁸⁸ Pu, ⁸⁸⁹ Pu, ⁸⁹⁰ Pu, ⁸⁹¹ Pu, ⁸⁹² Pu, ⁸⁹³ Pu, ⁸⁹⁴ Pu, ⁸⁹⁵ Pu, ⁸⁹⁶ Pu, ⁸⁹⁷ Pu, ⁸⁹⁸ Pu, ⁸⁹⁹ Pu, ⁹⁰⁰ Pu, ⁹⁰¹ Pu, ⁹⁰² Pu, ⁹⁰³ Pu, ⁹⁰⁴ Pu, ⁹⁰⁵ Pu, ⁹⁰⁶ Pu, ⁹⁰⁷ Pu, ⁹⁰⁸ Pu, ⁹⁰⁹ Pu, ⁹¹⁰ Pu, ⁹¹¹ Pu, ⁹¹² Pu, ⁹¹³ Pu, ⁹¹⁴ Pu, ⁹¹⁵ Pu, ⁹¹⁶ Pu, ⁹¹⁷ Pu, ⁹¹⁸ Pu, ⁹¹⁹ Pu, ⁹²⁰ Pu, ⁹²¹ Pu, ⁹²² Pu, ⁹²³ Pu, ⁹²⁴ Pu, ⁹²⁵ Pu, ⁹²⁶ Pu, ⁹²⁷ Pu, ⁹²⁸ Pu, ⁹²⁹ Pu, ⁹³⁰ Pu, ⁹³¹ Pu, ⁹³² Pu, ⁹³³ Pu, ⁹³⁴ Pu, ⁹³⁵ Pu, ⁹³⁶ Pu, ⁹³⁷ Pu, ⁹³⁸ Pu, ⁹³⁹ Pu, ⁹⁴⁰ Pu, ⁹⁴¹ Pu, ⁹⁴² Pu, ⁹⁴³ Pu, ⁹⁴⁴ Pu, ⁹⁴⁵ Pu, ⁹⁴⁶ Pu, ⁹⁴⁷ Pu, ⁹⁴⁸ Pu, ⁹⁴⁹ Pu, ⁹⁵⁰ Pu, ⁹⁵¹ Pu, ⁹⁵² Pu, ⁹⁵³ Pu, ⁹⁵⁴ Pu, ⁹⁵⁵ Pu, ⁹⁵⁶ Pu, ⁹⁵⁷ Pu, ⁹⁵⁸ Pu, ⁹⁵⁹ Pu, ⁹⁶⁰ Pu, ⁹⁶¹ Pu, ⁹⁶² Pu, ⁹⁶³ Pu, ⁹⁶⁴ Pu, ⁹⁶⁵ Pu, ⁹⁶⁶ Pu, ⁹⁶⁷ Pu, ⁹⁶⁸ Pu, ⁹⁶⁹ Pu, ⁹⁷⁰ Pu, ⁹⁷¹ Pu, ⁹⁷² Pu, ⁹⁷³ Pu, ⁹⁷⁴ Pu, ⁹⁷⁵ Pu, ⁹⁷⁶ Pu, ⁹⁷⁷ Pu, ⁹⁷⁸ Pu, ⁹⁷⁹ Pu, ⁹⁸⁰ Pu, ⁹⁸¹ Pu, ⁹⁸² Pu, ⁹⁸³ Pu, ⁹⁸⁴ Pu, ⁹⁸⁵ Pu, ⁹⁸⁶ Pu, ⁹⁸⁷ Pu, ⁹⁸⁸ Pu, ⁹⁸⁹ Pu, ⁹⁹⁰ Pu, ⁹⁹¹ Pu, ⁹⁹² Pu, ⁹⁹³ Pu, ⁹⁹⁴ Pu, ⁹⁹⁵ Pu, ⁹⁹⁶ Pu, ⁹⁹⁷ Pu, ⁹⁹⁸ Pu, ⁹⁹⁹ Pu, ¹⁰⁰⁰ Pu, ¹⁰⁰¹ Pu, ¹⁰⁰² Pu, ¹⁰⁰³ Pu, ¹⁰⁰⁴ Pu, ¹⁰⁰⁵ Pu, ¹⁰⁰⁶ Pu, ¹⁰⁰⁷ Pu, ¹⁰⁰⁸ Pu, ¹⁰⁰⁹ Pu, ¹⁰¹⁰ Pu, ¹⁰¹¹ Pu, ¹⁰¹² Pu, ¹⁰¹³ Pu, ¹⁰¹⁴ Pu, ¹⁰¹⁵ Pu, ¹⁰¹⁶ Pu, ¹⁰¹⁷ Pu, ¹⁰¹⁸ Pu, ¹⁰¹⁹ Pu, ¹⁰²⁰ Pu, ¹⁰²¹ Pu, ¹⁰²² Pu, ¹⁰²³ Pu, ¹⁰²⁴ Pu, ¹⁰²⁵ Pu, ¹⁰²⁶ Pu, ¹⁰²⁷ Pu, ¹⁰²⁸ Pu, ¹⁰²⁹ Pu, ¹⁰³⁰ Pu, ¹⁰³¹ Pu, ¹⁰³² Pu, ¹⁰³³ Pu, ¹⁰³⁴ Pu, ¹⁰³⁵ Pu, ¹⁰³⁶ Pu, ¹⁰³⁷ Pu, ¹⁰³⁸ Pu, ¹⁰³⁹ Pu, ¹⁰⁴⁰ Pu, ¹⁰⁴¹ Pu, ¹⁰⁴² Pu, ¹⁰⁴³ Pu, ¹⁰⁴⁴ Pu, ¹⁰⁴⁵ Pu, ¹⁰⁴⁶ Pu, ¹⁰⁴⁷ Pu, ¹⁰⁴⁸ Pu, ¹⁰⁴⁹ Pu, ¹⁰⁵⁰ Pu, ¹⁰⁵¹ Pu, ¹⁰⁵² Pu, ¹⁰⁵³ Pu, ¹⁰⁵⁴ Pu, ¹⁰⁵⁵ Pu, ¹⁰⁵⁶ Pu, ¹⁰⁵⁷ Pu, ¹⁰⁵⁸ Pu, ¹⁰⁵⁹ Pu, ¹⁰⁶⁰ Pu, ¹⁰⁶¹ Pu, ¹⁰⁶² Pu, ¹⁰⁶³ Pu, ¹⁰⁶⁴ Pu, ¹⁰⁶⁵ Pu, ¹⁰⁶⁶ Pu, ¹⁰⁶⁷ Pu, ¹⁰⁶⁸ Pu, ¹⁰⁶⁹ Pu, ¹⁰⁷⁰ Pu, ¹⁰⁷¹ Pu, ¹⁰⁷² Pu, ¹⁰⁷³ Pu, ¹⁰⁷⁴ Pu, ¹⁰⁷⁵ Pu, ¹⁰⁷⁶ Pu, ¹⁰⁷⁷ Pu, ¹⁰⁷⁸ Pu, ¹⁰⁷⁹ Pu, ¹⁰⁸⁰ Pu, ¹⁰⁸¹ Pu, ¹⁰⁸² Pu, ¹⁰⁸³ Pu, ¹⁰⁸⁴ Pu, ¹⁰⁸⁵ Pu, ¹⁰⁸⁶ Pu, ¹⁰⁸⁷ Pu, ¹⁰⁸⁸ Pu, ¹⁰⁸⁹ Pu, ¹⁰⁹⁰ Pu, ¹⁰⁹¹ Pu, ¹⁰⁹² Pu, ¹⁰⁹³ Pu, ¹⁰⁹⁴ Pu, ¹⁰⁹⁵ Pu, ¹⁰⁹⁶ Pu, ¹⁰⁹⁷ Pu, ¹⁰⁹⁸ Pu, ¹⁰⁹⁹ Pu, ¹¹⁰⁰ Pu, ¹¹⁰¹ Pu, ¹¹⁰² Pu, ¹¹⁰³ Pu, ¹¹⁰⁴ Pu, ¹¹⁰⁵ Pu, ¹¹⁰⁶ Pu, ¹¹⁰⁷ Pu, ¹¹⁰⁸ Pu, ¹¹⁰⁹ Pu, ¹¹¹⁰ Pu, ¹¹¹¹ Pu, ¹¹¹² Pu, ¹¹¹³ Pu, ¹¹¹⁴ Pu, ¹¹¹⁵ Pu, ¹¹¹⁶ Pu, ¹¹¹⁷ Pu, ¹¹¹⁸ Pu, ¹¹¹⁹ Pu, ¹¹²⁰ Pu, ¹¹²¹ Pu, ¹¹²² Pu, ¹¹²³ Pu, ¹¹²⁴ Pu, ¹¹²⁵ Pu, ¹¹²⁶ Pu, ¹¹²⁷ Pu, ¹¹²⁸ Pu, ¹¹²⁹ Pu, ¹¹³⁰ Pu, ¹¹³¹ Pu, ¹¹³² Pu, ¹¹³³ Pu, ¹¹³⁴ Pu, ¹¹³⁵ Pu, ¹¹³⁶ Pu, ¹¹³⁷ Pu, ¹¹³⁸ Pu, ¹¹³⁹ Pu, ¹¹⁴⁰ Pu, ¹¹⁴¹ Pu, ¹¹⁴² Pu, ¹¹⁴³ Pu, ¹¹⁴⁴ Pu, ¹¹⁴⁵ Pu, ¹¹⁴⁶ Pu, ¹¹⁴⁷ Pu, ¹¹⁴⁸ Pu, ¹¹⁴⁹ Pu, ¹¹⁵⁰ Pu, ¹¹⁵¹ Pu, ¹¹⁵² Pu, ¹¹⁵³ Pu, ¹¹⁵⁴ Pu, ¹¹⁵⁵ Pu, ¹¹⁵⁶ Pu, ¹¹⁵⁷ Pu, ¹¹⁵⁸ Pu, ¹¹⁵⁹ Pu, ¹¹⁶⁰ Pu, ¹¹⁶¹ Pu, ¹¹⁶² Pu, ¹¹⁶³ Pu, ¹¹⁶⁴ Pu, ¹¹⁶⁵ Pu, ¹¹⁶⁶ Pu, ¹¹⁶⁷ Pu, ¹¹⁶⁸ Pu, ¹¹⁶⁹ Pu, ¹¹⁷⁰ Pu, ¹¹⁷¹ Pu, ¹¹⁷² Pu, ¹¹⁷³ Pu, ¹¹⁷⁴ Pu, ¹¹⁷⁵ Pu, ¹¹⁷⁶ Pu, ¹¹⁷⁷ Pu, ¹¹⁷⁸ Pu, ¹¹⁷⁹ Pu, ¹¹⁸⁰ Pu, ¹¹⁸¹ Pu, ¹¹⁸² Pu, ¹¹⁸³ Pu, ¹¹⁸⁴ Pu, ¹¹⁸⁵ Pu, ¹¹⁸⁶ Pu, ¹¹⁸⁷ Pu, ¹¹⁸⁸ Pu, ¹¹⁸⁹ Pu, ¹¹⁹⁰ Pu, ¹¹⁹¹ Pu, ¹¹⁹² Pu, ¹¹⁹³ Pu, ¹¹⁹⁴ Pu, ¹¹⁹⁵ Pu, <				

IRM 3389-8 AC

Combustible WARD-4-4 (73)

Backfill Material Quantities
CB-75 2.278 2.550

TRANSURANIC DRY WASTE STORAGE

Class One
Combustible
Non-Combustible

Combustible Materials 3389-8 AC-B1

145 2.278 2.550
127
131
109
151
120
116
115
124
134
127
128
137
131
109
128
129
122

Drum No.	Grains Filled Material	Measurement Method	Operator	Trench			
85 -	+	*	A-061	<1	NDA	5/8	10-3-81
86 -	+	+	A-149	2	NDA	5/8	10-3-81
87 -	+		A-178	3	NDA	5/8	10-3-81
88 -	+		A-170	<1	NDA	5/8	10-3-81
89 -	+		A-177	3	NDA	5/8	10-3-81
90 -	+	*	A-076	<1	NDA	5/8	10-3-81
91 -	+		A-174	<1	NDA	5/8	10-3-81
92 -	X		A-164	<1	NDA	5/8	10-3-81
93 -	X		A-165	1	NDA	5/8	10-3-81
94 -	+		A-176	1	NDA	5/8	10-3-81
95 -	+		A-179	3	NDA	5/8	10-3-81
96 -	+		A-180	6	NDA	5/8	10-3-81
97 -	+	*	A-083	<1	NDA	5/8	10-3-81
98 -	+		A-161	<1	NDA	5/8	10-3-81
99 -	+		A-158	3	NDA	5/8	10-3-81
100 -	+		A-162	3	NDA	5/8	10-3-81
101 -	+		A-166	6	NDA	5/8	10-3-81
102 -	+		A-163	3	NDA	5/8	10-3-81

AND TOTAL 23 NDA 5/8

R.I.K. IS STORED OVER GROUND
IN - BY-48 - TRENCH - 7
* ABSORBED ORGANIC MATERIAL
FLASH POINT RANGE: 440-460 °F

* Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet

Certified By (Supervisor)

D. R. Bishop

Date

6-25-81

DISPOSAL SITE:			DISPOSAL SITE:		
Area	Burial Ground No.	Trench No.	Area	Burial Ground No.	Trench No.
			200-W	42	4
Casson No.	Coordinates		Casson No.	Coordinates	
	North	West	Mod-1610	North 40070	West 77722
Remarks:			Remarks:		
			SECTION 3 40070 77749		
Signature			Signature		
Date			Date		
			R. W. Carter 7-23-81		
DRUMS ARE ACCEPTED PER SOP			Distribution		
Signature			All Accompanying Shipments if Completed		
Date			Pink - To Be Returned		
R. W. Carter 6-25-81			White & Yellow - With Shipment if No Returned Copy Desired.		

THIS PAGE INTENTIONALLY LEFT BLANK

AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

4 of 8

BOXED WASTE

HEDL

308 BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

N-340

Combsville

200 AREA PLATEAU DISPOSAL SITE OPERATED FOR HL . DOE
By Restricted Hazardous Operations

WH1253

725

This portion of form to be completed by
Rental Representative or Operator only.

308-44C-21-2

PACKAGE NO.		DOE Authorization No (RAd)	
COMPANY HEDL			
BUILDING: 308		AREA 300	
ADDRESS (OFF SITE)			
I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RHO-MA-222 requirements and are packaged in Rockwell approved containers per RHO-MA-222.			
SIGNATURE Donna Brinkman		10-29-80	

MATERIAL CONTENTS (Note any special conditions) E.G., Sealed liquid, Disinfectant, Pump, Sampling or Laboratory paper waste, Yimburs, Resin.
(Include PDA numbers and Property Control numbers)

Мел. 75% 1 Выход Корма - 2 мешка прироста 4 Саломана Шелва
Р. 25% 2 Формасы - 1 Селитры прироста - 1 Кипящего -
1 Селитры прироста - 1 Селитры прироста - 1 мешка прироста

~~FD-#s WHC 77-236, 238; WH 80-226, 227;~~

PNL # 0-53,126

Vol. 3, Comput. 340

957

Vol. 15 Noncommutative

752

CONTAINER	BOX	1	LENGTH	11'6"	WIDTH	8'	DEPTH	5'6"	☐ HANFORD STANDARD CARDBOARD
All Containers Must be Approved by Rockwell Hanford Operations	ORIGIN	NO. AND SIZE							
	OTHER	NO. AND SIZE							

Approval Number (a) <u>15231</u>	TOTAL VOLUME (FT ³) <u>506</u>	Gross Weight <u>15,000</u>	☒ Pounds ☐ Kilograms
-------------------------------------	---	----------------------------	---

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)

Ри, к

Plutonium <u>2.5</u> Grams		TRU other than Pu <u>0</u> Grams			
Fissile Content <u>2.5</u> Grams		URANIUM <u>51</u> Grams <u>NH</u> ENRICHMENT		ACTIVITY (if TRU or U, only units in Grams required) <u>6.006</u> Curies	
DOSE RATE <u>2.6</u> mR/hr at <u>3</u> ☐ SURFACE ☐ INCHES ☒ FEET					
DISTRIBUTION:		BY SHIPPER		BY ROCKWELL	
WHITE } YELLOW } PINK }		WITH SHIPMENT		WHITE - ENG. 2704-2 YELLOW - NUCLEAR MATERIALS, 2704-2 PINK - RETURN TO SHIPPER	
COLORED - DETAIL					

THIS PAGE INTENTIONALLY LEFT BLANK

MODULE 11 (West coordinate 77746 to 77776)

Module 11 consists of 476 spaces for 55-gallon drums stacked in a 12 by 12 by 4 high configuration. Module 11 was built in Aug. through Nov. of 1981 and is expected to contain about half painted-half galvanized drums. The module also includes fifty L-10 containers (occupying 100 standard drum spaces).

The Babcox and Wilcox (APA) Facility generated 256 drums containing 3466 grams of plutonium, 10,015 grams of uranium, and 6.31 grams of americium. There were 4 drums that had no measurable plutonium present. The 340 (WHC) Facility generated 34 drums containing 380 grams of plutonium, and 10,756 grams of uranium. Two of the drums had no measurable plutonium. The 234-5Z (WHC) Facility generated 171 drums (50 L-10s) containing 602 grams of plutonium, 99 drums had no measurable plutonium. The WARD (WEC) Facility generated 26 drums containing 27 grams of plutonium, and 47 grams of uranium. There were 18 drums that had no measurable plutonium. The 209E (PNL) Facility generated 13 drums containing 247 grams of plutonium. The 340 (PNL) Facility generated 23 drums containing 3.6 grams of plutonium, 15 drums had no measurable plutonium. The 231Z (PNL) facility generated two drums with 3.1 grams plutonium.

The Module totals include 4,730 grams of plutonium, 20,820 grams of uranium, and 6.31 grams of americium. There were 138 drums that had no measurable plutonium. The highest plutonium loaded drum is 140 grams from 209E (PNL) located in Position 15 Tier 4. The maximum dose rate values were 36 mrem/hr from two 234-5Z drums.

The L-10 containers occupy Rows C through H, Positions 3 through 10, Tiers 3 and 4 plus Positions I-9 and I-10. These 50 containers hold 423 grams of TRU included above in the waste from "Z" Plant. The L-10 drums (110 gallon) typically contain ten liter poly bottles comprising the 10L containers, plastic tubing, and metal inserts which are a part of the container system design. The inner containers are designed with vents and the L-10 lid is designed to not seal.

The 13 drums from 209E (PNL) are reported to contain solvents.

THIS PAGE INTENTIONALLY LEFT BLANK

THE

218W4C
Trench 4
Module

L K J I H G F E D C B A

15

159

2 3 4 5 6 7 8 9 10 11 12

TIER 2

218W4C
Trench 4
Module 11

L K J I H G F E D C B A

1
2
3
4
5
6
7
8
9
10
11
12

L K J I H G F E D C B A

TIER 3

218W4C

Trench 4

Module 1

Unit 1

Unit 2 3 4 5 6 7 8 9 10 11 12

Unit 1 = Dose Rate
Unit 2 = Grams Pu

1
2
3
4
5
6
7
8
9
10
11
12

TIER 4

218W4C
Trench 4
Module 11

L K J I H G F E D C B A

5	10		10	5	5	15.31	15.25	15.23	15.23	15.13	15.13
				8							
						15.14	15.23	15.59	15.26	15.11	15.23
			33	36	8	8					
					2	22				15.06	15.13
5	2		5	33	8						
					8	DBL		DBL	15.2	15.1	
			36	36	8						
					7	4			15.22	15.1	
			5	36	36	8					
				47	2	6			15.23	14.5	
				36		8					
			40	1		10	14		15.17	14.55	
			10	36	8	8					
				10	34	9	13	12	5	15.29	14.53
			36	36	8	8	8	8			
					21	25	32	13		15.03	15.13
	10	10		33		8	8	8			
11.42	5					30	5	12	DBL	15.14	15.25
15.15	15.16	15.26	11.53	15.22		15.25	15.23	15.23	15.29	15.2	15.23
15.27		14.5	12.08		15.04	15.27	15.31	15.18	14.82	15.2	15.2

1
2
3
4
5
6
7
8
9
10
11
12

Module 11
Dose Rate
grams Pu

TRENCH 4 MODULE 11 TIER 1

TRENCH 4 MODULE 11 TIER 2

TRENCH 4 MODULE 11 TIER 3

TRENCH 41 MODULE 11 TIER 4

DRUMS

PNL

209E BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

Combustible 8162.

WHC-SD-W113-ACDR-001
Rev. 0
Page 254

SOLID WASTE BURIAL RECORD
200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE
By Rockwell Hanford Operations

414 | 8162 (6)

DISPOSAL SITE This portion of form to be completed by Rockwell Representative at Disposal Site.

AREA <u>200-W</u>	BURIAL GROUND NO. <u>4C</u>	TRENCH NO. <u>4</u>
Module 11 + SECTION 4-B	BEGINNING COORDINATES <u>N 40070 - 77750 - 329</u>	
	ENDING COORDINATES <u>N 40070 - 77776 - 303</u>	
REMARKS <u>Module 12 N 40070 W 77799 230</u>		
<u>SECTION 3 N 40070 W 77775 - 304</u>		
DATE <u>3-19-82</u>	TIME	
SIGNATURE <u>R.W. Lander</u>		

ORIGINATOR 209-PNL 82-1-4 OK

PACKAGE NO. <u>74, 75, 77, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90</u>	DOE AUTHORIZATION NO. (ARM) <u>N.A.</u>
COMPANY <u>PNL</u>	
BUILDING <u>209</u>	AREA <u>200E</u>
ADDRESS (OFF SITE)	
I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RHO MA 222 requirements and are packaged in Rockwell approved containers per RHO MA 222.	
SIGNATURE <u>J.H. LAUBY J.H. Lauby 11/21/81</u>	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Sorbed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Tumors, Resin (Include PDR numbers and Property Control numbers)

Drum #15

74, 75, 88, 89 - Combustible glove box waste (70% strip coat, 25% rubber, 5% plastic)

77, 79 thru 87 - Combustible lab waste (75% paper, 21% rubber, 4% plastic)

~~80 - Non-combustible lab waste (striking jacketing gloves, canister, and gloves)~~

NUMBERS 74 + 75 + 77 + 79 - 80 + 81 + 82 + 83 +

84 + 85 + 86 + 87 + 88 + 89

Container	NO.	LENGTH	WIDTH	HEIGHT	WEIGHT
All Containers Must be Approved by Rockwell Hanford Operations	BOX				
	DRUM	<u>14 - 55 gallon (7.42)</u>			
	OTHER				
<u>103.6</u>					
Approval Number(s) <u>HCS 042-001-01</u>	TOTAL VOLUME (FT ³) <u>103.6</u>	Gross Weight <u>905</u>	☐ Pounds ☒ Kilograms		

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., Long-lived isotopes such as Pu, Co, Sr, Cs; mixed fission products; activation products)

Plutonium Pu

Plutonium <u>261</u> Grams	TRU other than Pu <u>0</u> Grams												
Fissile Content <u>256</u> Grams	URANIUM <u>0</u> Grams												
ACTIVITY (if TRU or U, only units in Grams required) <u>44</u> Curies													
DOSE RATE <u><1</u> mR/hr at													
☒ SURFACE ☐ INCHES ☐ FEET													
DISTRIBUTION: <table border="0"> <tr> <td>WHITE</td> <td rowspan="4">} WITH SHIPMENT</td> <td>WHITE</td> <td>- SMC, 2700-E</td> </tr> <tr> <td>YELLOW</td> <td>YELLOW</td> <td>- UNCLE SAM MATERIALS, 2700-E</td> </tr> <tr> <td>PINK</td> <td>PINK</td> <td>- RETURN TO SHIPPER</td> </tr> <tr> <td>GOLDENROD</td> <td>- RETURN</td> </tr> </table>		WHITE	} WITH SHIPMENT	WHITE	- SMC, 2700-E	YELLOW	YELLOW	- UNCLE SAM MATERIALS, 2700-E	PINK	PINK	- RETURN TO SHIPPER	GOLDENROD	- RETURN
WHITE	} WITH SHIPMENT	WHITE		- SMC, 2700-E									
YELLOW		YELLOW		- UNCLE SAM MATERIALS, 2700-E									
PINK		PINK		- RETURN TO SHIPPER									
GOLDENROD		- RETURN											

٢

1. The first two are the same: the first is the same as the second.

2001 02 6. \$22.00

2

E. H. Clayton

10-21-81

DISPOSAL SITE				DISPOSAL SITE			
Area	Burial Ground No.	Trench No.		Area	Burial Ground No.	Trench No.	
Caution No.	Coordinates	North	West	Caution No.	Coordinates	North	West
Remarks				Caution No.	Coordinates	North	West
				Module 11		40070	77750
				Section - 4		40070	77776
				Module - 12		40070	77799
				Section - 3		40070	77775
Signature	Date			Signature	Date		
				R. H. Pender	3 17 82		

ORDERS ARE ACCEPTED PER SOP *Ta-100-370*

Signature

Date _____

R. W. Carter

10. 2791

As Allegory Shipment if Completed
Is - To Be Returned
as to a Value - With Shipment if he Returned Case Desired.

TYPICAL DRUMS
BABCOCK & WILCOX
APOLLO

THIS PAGE INTENTIONALLY LEFT BLANK

COMBUSTIBLE 3536-7

AN-11
3 142
N 18A

SOLID WASTE BURIAL RECORD			70	
200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL-DOE By Rockwell Hanford Operations				
TO			BACX-APA-51-9 2100	
DISPOSAL SITE	THIS PORTION OF FORM IS TO BE COMPLETED BY Rockwell Hanford Operations		ORIGINATOR	32V-18A OK
AREA	SERIAL GROUP NO.	TRENCH NO.	PACKAGE NO.	DOE AUTHORIZATION NO. (RPM)
200-W	4C	4	Reference BC-4500-076	3536-7
Module 11	RECORDS COMPLETED = 40072 = 22253 349		Company	
Section-1+2	= 40076 = 22276 203		Babcock & Wilcox Co.	
REMARKS			BUILDING	AREA
			Plutonium Plant	
			ADDRESS OFF SITE	
			609 NORTH WARREN AVENUE APOLLO, PA. 15613	
DATE			I certify that no liquid or gaseous material is included in this list of wastes except materials that are Property of Federal, State, and local governments, and that the contents meet RCRA 262 requirements and are packaged in accordance with applicable requirements for RCRA 262.	
10-22-81			W. J. ROSS WJF/ESS/EL/yna 9/2/81	
SIGNATURE			SIGNATURE	
R. L. Carter				

PHYSICAL DESCRIPTION

WATER AL CONTENTS: Note any special conditions, e.g., Solids, Liquid, Gaseous, Pumps, Sampling or Laboratory order forms, Tonnage, Pallets.
(Include PCN numbers and Property Control numbers)

Combustible glovebox generated waste in 17-H and 17-C,
55 gallon drums; 67 drums - Plastic 66.73%; Paper
18.49%; Gloves 0.37%; Filters 13.09%; Wood 0.82%.

Outer Shipping container Type N-55

Overpacks (To be returned)

Container	Box	Size	Height	Weight	Material
All Containers	Box	42 AND SIZE			WATERPROOF STANDARD
Must be	Box	42 AND SIZE			CARDBOARD
Approved	Box	23 Drums 17-C Type, 55 Gallon Capacity			
By	Box	44 Drums 17-H Type, 55 Gallon Capacity			
Rockwell	Box				
Hanford	Box				
Operations	Box				

Approved Number W
BIA-263

TOTAL VOLUME (FT³) 502.5 P₂ 3 Gross Weight 7,005

8 Pounds
Kilograms

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs, UNDETERMINED MIXTURES) ACTIVATION PRODUCTS

TRU-glovebox waste from FETC Ceres 3 and 4 production			
Pu-238, Pu-239, Pu-240, Pu-241, Pu-242, + Am-241 Pu			
Plutonium	TRU other than Pu		
831.67 gms	2.90 gms		
Fissile Content	URANIUM	ACTIVITY (IN TRU or U, only units in Grams per hour)	
734.55 gms	2.495 gms 0.2%		
DOSE RATE		CURIES	
14 mR/hr = Contact		☐ SURFACE ☐ INSIDE ☐ FEET	
DISTRIBUTION:		BY SHIPPER	
WHITE YELLOW PINK UNCLASSIFIED - OTHER		WHITE - 100% STONE YELLOW - 100% STONE PINK - 100% STONE UNCLASSIFIED - OTHER	

COMBUSTIBLE 3536-7 01-1-10-9 23

Rockwell Hanford Operations

TRANSURANIC DRY WASTE STORAGE

3536-7-A-10
M. P. DEDO
11-1-10-9

Draw No	WT	CL	Trench	Draw No	WT	CL	Trench	Draw No	WT	CL	Trench
92	14.35	37.23	23	224	15.36-7-3	12.67	NDA	225	15.36-7-4	13.17	NDA
94	14.92	37.23	23	226	15.36-7-5	10.79	NDA	227	15.36-7-6	13.34	NDA
89	12.23	37.23	23	228	15.36-7-7	13.25	NDA	229	15.36-7-8	11.57	NDA
92	15.11	37.23	23	230	15.36-7-9	10.75	NDA	231	15.36-7-10	10.43	NDA
88	15.01	37.23	23	232	15.36-7-11	10.25	NDA	233	15.36-7-12	10.15	NDA
96	13.13	37.23	23	234	15.36-7-13	13.09	NDA	235	15.36-7-14	13.51	NDA
96	12.18	37.23	23	236	15.36-7-15	11.02	NDA	237	15.36-7-16	11.97	NDA
92	11.82	37.23	23	238	15.36-7-17	12.09	NDA	239	15.36-7-18	13.33	NDA
98	11.61	37.23	23	240	15.36-7-19	13.51	NDA	241	15.36-7-20	13.31	NDA
90	11.50	37.23	23	242	15.36-7-21	13.44	NDA	243	15.36-7-22	10.89	NDA
74	14.83	37.23	23	244	15.36-7-23	10.78	NDA	245	15.36-7-24	10.80	NDA
78	15.31	37.23	23	246	15.36-7-30	9.84	NDA	247	15.36-7-31	10.11	NDA
72	12.49	37.23	23								
74	13.56	37.23	23								
68	13.70	37.23	23								
70	15.10	37.23	23								
80	15.31	37.23	23								
82	15.02	37.23	23								
80	15.23	37.23	23								
78	12.34	37.23	23								
78	12.21	37.23	23								
88	12.24	37.23	23								
102	11.14	37.23	23								
78	11.45	37.23	23								

M. P. DEDO *M. P. DEDO* 9-15-81

DISPOSAL SITE	DISPOSAL SITE
Area	Area
Build Ground No.	Build Ground No.
Trench No.	Trench No.
Cell No.	Cell No.
Coordinates	Coordinates
Remarks	Remarks

To 100-050
Signature *R. W. Carder* Date 9-24-81
ORUMS ARE ACCEPTED PER SOP
Signature *R. W. Carder* Date 9-24-81
At Accompanying Shipment If Completed
P.O. - To Be Returned
When & With Shipment If No Returned Copy Desired.

COMBUSTIBLE 3536-7-1292-10-A-7 (70)

Rockwell Hanford Operations

TRANSURANIC DRY WASTE STORAGE

Check One
☒ Combustible
☐ Non-Combustible

Rockwell Hanford Operations			TRANSURANIC DRY WASTE STORAGE			Combustible Materials 3536-7-A-10		
Drum No.	Weight	Ac	Trench	Drum No.	Grms	Measurement	Operator	Trench
					Fill Material	No. 1		
114	13.13	37.239	248	+3536-7-32	11.59	NDA	P. Schuchert	11-2-10A
92	10.26		249	+3536-7-34	9.06	NDA	P. Schuchert	11-2-10A
100	11.07		250	+3536-7-35	10.14	NDA	P. Schuchert	11-2-10A
78	15.22		251	+3536-7-36	13.43	NDA	P. Schuchert	11-2-10A
80	15.26		252	+3536-7-37	13.47	NDA	P. Schuchert	11-2-10A
72	11.39		253	+3536-7-38	10.06	NDA	P. Schuchert	11-2-10A
82	11.18		254	+3536-7-39	5.87	NDA	P. Schuchert	11-2-10A
84	12.21		255	+3536-7-40	10.78	NDA	P. Schuchert	11-2-10A
88	12.86		256	+3536-7-41	11.36	NDA	P. Schuchert	11-2-10A
90	10.54		257	+3536-7-42	9.30	NDA	P. Schuchert	11-2-10A
110	11.42		258	+3536-7-43	10.08	NDA	P. Schuchert	11-2-10A
84	10.59		259	+3536-7-44	9.35	NDA	P. Schuchert	11-2-10A
159	15.31		260	+3536-7-45	13.51	NDA	P. Schuchert	11-2-10A
202	13.60		261	+3536-7-46	12.00	NDA	P. Schuchert	11-2-10A
146	10.71		262	+3536-7-47	9.45	NDA	P. Schuchert	11-2-10A
130	14.94		263	+3536-7-48	13.19	NDA	P. Schuchert	11-2-10A
132	10.52		264	+3536-7-49	9.28	NDA	P. Schuchert	11-2-10A
144	8.15		265	+3536-7-50	7.46	NDA	P. Schuchert	11-2-10A
145	8.78		266	+3536-7-51	7.75	NDA	P. Schuchert	11-2-10A
138	9.83		267	+3536-7-52	8.68	NDA	P. Schuchert	11-2-10A
144	9.62		268	+3536-7-53	8.49	NDA	P. Schuchert	11-2-10A
139	9.69		269	+3536-7-54	8.56	NDA	P. Schuchert	11-2-10A
122	12.29		270	+3536-7-55	10.85	NDA	P. Schuchert	11-2-10A
116	12.07		271	+3536-7-56	10.65	NDA	P. Schuchert	11-2-10A

* Use form for

all no mixing - use another sheet

Signature of Shipper

M. P. DEDO

Date

9-18-81

DISPOSAL SITE

DISPOSAL SITE:

Area	Box & Ground No.	Trench No.	Area	Box & Ground No.	Trench No.
200-W	4C	4	200-W	4C	4
Coordinates	Coordinates	Coordinates	Coordinates	Coordinates	Coordinates
North: 40070	West: 77750	North: 40070	West: 77750	North: 40070	West: 77750
Remarks	Remarks	Remarks	Remarks	Remarks	Remarks

Ti-100-50

Signature	Date	Signature	Date
		P. W. Carder	10-22-81

CRUUS ARE ACCEPTED PER SOP

Distribution:

Signature	Date	Signature	Date
P. W. Carder	9-21-81		

AN Accompanying Shipment if Completed
 Pink - To Be Returned
 White & Yellow - With Shipment if No Returned Copy Desired.

COMBUSTIBLE 3536-7-1-9

(70)

TRANSURANIC DRY WASTE STORAGE						Check One: ☒ Combustible ☐ Non-Combustible	
Area: 1		Trench: 01		Combinable Materials: 3536-7-1-10			
Operator	Trench	Drum No.	Grams Filled Material	Measurement Method	Operator	Trench	
CB-7.4							
272	+	3536-7-57	11.22	NDA	D. Schuchert	11-2-10A	
273	+	3536-7-58	12.90	NDA	D. Schuchert	11-2-10A	
274	+	3536-7-59	12.24	NDA	D. Schuchert	11-2-10A	
275	+	3536-7-60	12.60	NDA	D. Schuchert	11-1-10A	
276	+	3536-7-61	9.66	NDA	D. Schuchert	11-2-10A	
277	+	3536-7-62	9.60	NDA	D. Schuchert	11-1-10A	
278	+	3536-7-63	9.81	NDA	D. Schuchert	11-1-10A	
279	+	3536-7-64	7.51	NDA	D. Schuchert	11-2-10A	
280	+	3536-7-65	6.96	NDA	D. Schuchert	11-2-10A	
281	+	3536-7-66	13.33	NDA	D. Schuchert	11-2-10A	
282	+	3536-7-67	12.68	NDA	D. Schuchert	11-2-10A	
283	+	3536-7-68	13.03	NDA	D. Schuchert	11-2-10A	
284	+	3536-7-69	12.28	NDA	D. Schuchert	11-2-10A	
285	+	3536-7-70	10.48	NDA	D. Schuchert	11-2-10A	
286	+	3536-7-71	11.22	NDA	D. Schuchert	11-2-10A	
287	+	3536-7-72	11.37	NDA	D. Schuchert	11-2-10A	
288	+	3536-7-73	11.38	NDA	D. Schuchert	11-2-10A	
289	+	3536-7-74	6.79	NDA	D. Schuchert	11-2-10A	
290	+	3536-7-75	7.00	NDA	D. Schuchert	11-2-10A	

wt 01 23 37.234

02 12.71

126 14.61

120 13.87

124 14.27

118 10.94

124 10.87

122 11.11

120 8.51

118 7.88

120 15.10

126 14.36

126 14.76

122 13.92

108 11.87

94 12.71

105 12.88

86 12.89

120 7.69

78 7.93

* Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet

Certified By (Supervisor)

M. P. DEDO

Date

9-18-81

DISPOSAL SITE:

DISPOSAL SITE:

Area: Burial Ground No.: Trench No.:

Area: Burial Ground No.: Trench No.:

Container No.: Coordinates: North: West:

Container No.: Coordinates: North: 40070 West: 77750

Remarks:

Remarks: Section 1+2 40070 77776

70-100-50

Signature: Date:

Signature: Date:

DRUMS ARE ACCEPTED PER SOP

Distribution:

Signature: Date:

All Accompanying Shipment If Completed
Pink - To Be Returned
White & Yellow - With Shipment If No Returned Copy Desired.

10L/L10 CONTAINERS

ROCKWELL

234-5Z BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

M-11 Rev. 0
 5-3 Page 262
 N-A14

L10 CONTAINERS

Combustible 1147

SOLID WASTE BURIAL RECORD			2130 1147	
200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE By Rockwell Hanford Operations				
DISPOSAL SITE			ORIGINATOR 23452-R-40-27-46 OK	
AREA	BURIAL GROUND NO	TRENCH NO.	PACKAGE NO.	DOE Authorization No (RRM)
200-W	4E	4	E46705	A-14
Module 11	BEGINNING COORDINATES		COMPANY	
SECTION 3	ENDING COORDINATES		ROCKWELL	
	249		BUILDING: 234-5	
	323		AREA: 200W	
REMARKS			ADDRESS (OFF SITE)	
DATE 10-27-81			I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RHO-MA-222 requirements and are packaged in Rockwell approved containers per RHO-MA-222.	
SIGNATURE G. W. Corb			SIGNATURE Melvin D. Smith 8-25-81	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Sorbed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Resin (Include PDR numbers and Property Control numbers)

1 - L10 # 13 10L Containers containing combustible 10 liter poly bottles & plastic tubing. Contain metal inserts which are part of container design.

Z81-BA-R-322 + 473 + 532 + 293 + 398 + 522 + 447
 332 + 406 + 316 + 437 + 410 + 485 + 049

Vol. % Combustible 60%

Vol. % Noncombustible 40%

Container	NO.	LENGTH	WIDTH	HEIGHT	MANFORD STANDARD
BOX					
All Containers Must be Approved by Rockwell Hanford Operations	NO. AND SIZE				
DRUM	14 ea 10L / L10 CONTAINERS				
OTHER					
Approval Number(s)	TOTAL VOLUME (FT ³)	Gross Weight		Pounds	
HC5-001-05-01 HC5-01A-204-00	207.2	4900		Kilograms	

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)

Pu 239

Pu

Plutonium	Grams	TRU other than Pu	Grams	ACTIVITY (If TRU or U, only units in Grams required)
129		N/A		
Fissile Content	Grams	URANIUM	Grams	ENRICHMENT
112		N/A		
DOSE RATE				
Highest reading 500 mR/hr at Contact				
DISTRIBUTION:		BY SHIPPER		
WHITE		WITH SHIPMENT		
YELLOW				
PINK				
GOLDENROD - RETAIN				
		BY ROCKWELL		
		WHITE - GWS, 2780-E		
		YELLOW - NUCLEAR MATERIALS, 2704-E		
		PINK - RETURN TO SHIPPER		

COMBUSTIBLE 1141

10 L CONTAINERS 11-11 3-344 H-A20

SOLID WASTE BURIAL RECORD			200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE By Rockwell Hanford Operations	
DISPOSAL SITE			ORIGINATOR	
This portion of form to be completed by Rockwell Representative at Disposal site.			2345Z-RHO-81-48	
AREA	BURIAL GROUND NO.	TRENCH NO.	PACKAGE NO.	DOE Authorization No (RRM)
200-W	4C	4	E46705	A-20
Module - 11	COORDINATES		COMPANY	
	+40070	-77750 329	ROCKWELL	
Sections 3+4	COORDINATES		BUILDING	AREA
	+40070	-77776 203	234-5	200W
REMARKS			ADDRESS (OFF SITE)	
DATE			I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below, and that the contents meet RHO-MA-222 requirements and are packaged in Rockwell approved containers per RHO-MA-222.	
10-28-81			SIGNATURE	
SIGNATURE			8/17/81	
R. W. Parker			J. A. W. R. K.	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions: E.G., Sealed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Resin. Include PDR numbers and Property Control numbers)

all containers contain some plastic and/or 10 L Poly bottles. all material in containers is plastic and combustible PH WASTE FROM 234-5 IN-10K CONTAINERS.

R-270+307+408+419+479+502+506+511+497+394

418+303+318+337+375+384+255+507+210+205

Container	BOX	NO.	LENGTH	WIDTH	HEIGHT	MANFORD STANDARD CARDBOARD
All Containers Must be Approved by Rockwell Hanford Operations	DRUM	NO. AND SIZE	20 EA 10 L CONTAINERS			
	OTHER	NO. AND SIZE				
Approval Number(s)	TOTAL VOLUME (FT ³)	Gross Weight				
HCS-011-005-01	292 295 7000	4350 LB				

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPIES SUCH AS Pu, Co, Sr, Fissionable products, activation products)			
P 239 PH			
Plutonium	TRU other than Pu		
274	NA		
278 LB	NA		
Fissile Content	URANIUM	ACTIVITY (if TRU or U, only units in Grams required)	
230	NA	NA 447DK	
242 LB	NA		
DOSE RATE	mR/hr	SURFACE	
150			
DISTRIBUTION:	BY SHIPPER	BY ROCKWELL	
WHITE	WITH SHIPMENT	WHITE - SMC, 2700-E	
YELLOW		YELLOW - NUCLEAR MATERIALS, 2704-E	
PINK		PINK - RETURN TO SHIPPER	
GOLDENROD - RETAIN			

1st CONTAINERS

COMBUSTIBLE

1142

M-11

S-3+4 Double BB1

N 16A

SOLID WASTE BURIAL RECORD 200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL-DOE By Rockwell Hanford Operations		2149 1142 X 19C
--	--	-----------------------

DISPOSAL SITE <small>This portion of form to be completed by Rockwell Representative at Disposal site.</small>		ORIGINATOR 23452 RHO-21-79-0K	
AREA 200-W	BURIAL GROUND NO. 4C	TRENCH NO. 4	PACKAGE NO. E46705
Module 11 SECTION 3+4	BEGINNING COORDINATES N 40070 - 77750 229 ENDING COORDINATES N 40070 - 77776 303		DOE AUTHORIZATION No (RAM) 16A
REMARKS Double BB		COMPANY Rockwell	
DATE 10-28-81		BUILDING 234-5	
SIGNATURE R. W. Carls		ADDRESS (OFF SITE) 780 W	
		I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below, and that the contents meet RHO MA 222 requirements and are packaged in Rockwell approved containers per RHO-MA-222.	
		SIGNATURE [Signature] 8/17/81	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions: E.G., Sealed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Resin. Include PDR numbers and Property Control numbers)						
there containers have as contents plastic and poly bottles which are Combustible, Combustible Pu WASTE FROM 334-5 IN 10L CONTAINERS						
R-274+387+431+389+346+215+413+330 H-004+034+048+058						Vol. % Combustible 100%
						Vol. % Noncombustible
Container All Containers Must be Approved by Rockwell Hanford Operations	BOX NO AND SIZE 12 ea 10L or L10 CONTAINERS	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD ☐ CARDBOARD
APPROVED BY: [Signature] TOTAL VOLUME (FT ³) 175.2 Gross Weight 4200						
APPROVED BY: [Signature]						

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPIES SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)			
Pu 239 PU			
Plutonium 22 Grams	TRU other than Pu N/A Grams		
Fission Content 19 Grams	URANIUM N/A Grams	ACTIVITY (If TRU or U, only units in Grams required) N/A	
DOSE RATE 15 mR/hr		☒ SURFACE ☐ INCHES ☐ FEET	
DISTRIBUTION:		BY ROCKWELL	
WHITE YELLOW PINK GOLDENROD - DEVEN		WHITE - ENG. 2700-E YELLOW - NUCLEAR MATERIALS, 2704-E PINK - RETURN TO SHIPPER	

THIS PAGE INTENTIONALLY LEFT BLANK

MODULE 12 (West coordinate 77772 to 77798)

Module 12 consists of 256 55-gallon drums stacked in a 12 by 12 by 4 high configuration along with three 6'x 6'x 7' metal boxes (DWG # H-2-91888) 5,500 pounds each; one 12'x 6'x 7'1" high metal box 16,000 pounds; and four 11'x 7'8"x 5'5" high 15,000 pounds each. Module 12 was built in late 1981 and early 1982. It is assumed that most of the drums by this time were galvanized.

The BABCOX (APA) Facility generated 61 drums of waste containing 891 grams of plutonium, and 2637 grams of uranium. The 234-5Z (WHC) Facility generated 137 drums containing 522 grams of plutonium, 120 drums had no measurable plutonium. The 200W (JAJ) Facility generated the 5 long boxes which are recorded to contain 166 grams of plutonium. The 340 (PNL) Facility generated 8 drums containing 0.35 grams plutonium and 749 grams of uranium. Five of the drums had no measurable plutonium. The Vallecitos (GE) Facility generated 32 drums containing 55 grams of plutonium, and 854 grams of uranium. The 340 (WHC) Facility generated 17 drums containing 90 grams of plutonium, 3874 grams of uranium, and 640 grams of thorium; and three metal boxes with 17.4 grams Pu. One drum had no measurable plutonium.

The Module totals include 1740 grams of plutonium, 8120 grams of uranium, and 640 grams of thorium. There were 126 drums that had no measurable plutonium. The highest plutonium loaded drum is 82 grams in position I-11, Tier 3 from the 234-5Z Facility. The maximum dose rate is 10 mrem/hr and several drums have that value recorded.

Four of the boxes occupy Rows E through L, Positions 1 through 12 in Tiers 1 and 2. The remaining boxes occupy Tiers 3 and 4 in Positions 1 through 6 Rows I through L; and positions 1 through 3, 5 through 8, and 10 through 12 in Rows E through H.

The waste contained in the boxes generated by J.A. Jones consist of metal ductwork, plastic, rags, filter boxes, and barrels. The boxes from the 340 Bldg are recorded to contain 98% metal-2% plastic.

Oil is listed in the contents of 31 drums from GE-VAL and a drum from 209E (PNL) contains solvents.

THIS PAGE INTENTIONALLY LEFT BLANK

L K J I H G F E D C B A

TIER 1

218W4C
Trench 4
Module 12

1
2
3
4
5
6
7
8
9
10
11
12

Dose Rate
Pu

TIER2

218W4C
 Trench 2

Rate

20

1 2 3 4 5 6 7 8 9 10 11 12

L K J I H G F E D C B A

TIER 3

218W4C
Trench 4
Module 12

mR

Rate

Pu

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TIER 4

218W4C
 Trench 4
 Module 2

MR

Rate

Rate

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TRENCH 4 MODULE 12 TIER 1

TRENCH 4 MODULE 12 TIER 2

3

TRENCH 4 MODULE 12 TIER 4

BOXED WASTE

HEDL

340 BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

COMBUSTIBLE WH 1379

SOLID WASTE BURIAL RECORD

200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE
By Rockwell Hanford Operations

WH-1379

DISPOSAL SITE		This portion of form to be completed by Rockwell Representative at Disposal site.		ORIGINATOR		340-WHC-82-2 15-12 OK	
AREA	BURIAL GROUND NO.	TRENCH NO.		PACKAGE NO.	DOE Authorisation No (RWH)		
200-W	4C	4		WH-1379	8.22-		
Module 12	DESIGNATION COORDINATES		COMPANY				
	= 40070 = 727299		HEOL				
Section 8+V	EODING COORDINATES		BUILDING				
	= 40070 = 72725		340				
REMARKS				AREA			
				300			
				ADDRESS (OFF SITE)			
				I certify that no special property is included in this set of waste documents by a Property Control Number, and that the contents meet RHO MA-222 requirements and are packaged in Rockwell approved containers per RHO MA-222.			
DATE				SIGNATURE			
3-2-82				Cathy Hofmeister 9-9-81			
SIGNATURE				A.W. Carle-			
PHYSICAL DESCRIPTION							
MATERIAL CONTENTS (Indicate any special conditions: E.G. Solids, Liquids, Disposal, Pumps, Sampling or Laboratory paper waste, Tins, etc. Also use PDR numbers and Property Control numbers)							
Indol-98%				PDR # WHC-81-227			
CLASTIC-2%				WHC-81-226			
SEAL 14511+13555 14512+14513+13551+13552							
Container # S-WH-81-500, 501, 502				Vol. % Combustible			
SRR # WM-81-79				98%			
Container	BOX	NO.	LENGTH	WIDTH	HEIGHT	MANIPULATED STANDARD CARDBOARD	
A Container	DRUM	NO. AND SIZE					
MUST BE APPROVED BY ROCKWELL HANFORD OPERATIONS	OTHER	NO. AND SIZE	3 TRU Retractable Sterilizer Containers @ 252ft ³				
			each, Dues # H-2-91885, size 6'x6'x7'				
Approval Number(s)	TOTAL VOLUME (FT ³)	Gross Weight	Pounds				
KSD-3227	756	16,500	Kilograms				

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G. LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)							
Pu							
Pu							
Plutonium	TRU other than Pu						
17.4 Grams	0 Grams						
Fission Content	URANIUM	ACTIVITY (in TRU or U, only units in Grams required)					
17.4 Grams	0 Grams	N/A					
DOSE RATE		SURFACE					
20.5 mR/hr		INHERENT					
		FEET					
DISTRIBUTION:		BY SHIPPER			BY ROCKWELL		
		WHITE - ONE, 2700-E			WHITE - ONE, 2700-E		
		YELLOW - WITH SHIPMENT			YELLOW - NUCLEAR WASTE, 2700-E		
		PINK - RETURN TO SHIPPER			PINK - RETURN TO SHIPPER		
		GOLDENROD - RETAIN					

COMBUSTIBLE WIT 1379 BHC-81-2

Rockwell Hanford Operations					TRANSURANIC DRY WASTE STORAGE				
Non-Combustible Materials					Combustible Materials				
Drum No.	Grams Fissile Material	Measurement Method	Operator	Trench	Drum No.	Grams Fissile Material	Measurement Method	Operator	Trench
					WH-81		Estim.	LARSON	
				15	500	5.80			12-1-A39
				16	501	5.80			12-2-A39
				17	502	5.80			12-3-A39

*Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet

Checked By: Supervisor <i>Calley S. Hognester</i>				Date 9-9-81	
DISPOSAL SITE:			DISPOSAL SITE:		
Area	Burial Ground No.	Trench No.	Area	Burial Ground No.	Trench No.
			200-W	4C	4
Case No.	Coordinates		Case No.	Coordinates	
	North:	West:	Module E 12	North: 40070	West: 77799
Remarks:			Section 2-4	40070	77775
Signature			Signature		
			<i>P. W. Carls</i>		
Date			Date		
			3-2-82		
DRUMS ARE ACCEPTED PER SOP			Distribution:		
Signature			All Accompany Shipment if Completed		
<i>E. L. Tyler</i>			Pink - To Be Returned		
Date 9/9/81			White & Yellow - With Shipment if No Returned Copy Desired.		

BOXED WASTE

J A JONES

234-5Z BUILDING

WMC-SD-W113-ACDR-001
Rev. 0
Page 277A

THIS PAGE INTENTIONALLY LEFT BLANK

Combustible # 1165

N-A 30 (2)

SOLID WASTE BURIAL RECORD 200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL DOE By Rockwell Hanford Operations	285 1165285
--	----------------

DISPOSAL SITE		THIS portion of form to be completed by Rockwell Representative at Disposal site.		ORIGINATOR 200W-JAJ-82-1	
AREA 200-W	BURIAL GROUND NO. 4C	TRENCH NO. 4	PACKAGE NO. X-17890	DOE Authorization No (RRM) OK	
CAISSON NO. Module 12	Easting (COORDINATES) 40070 = 77799 280'		COMPANY JA JONES		
SECTION 1+2	Easting (COORDINATES) 40070 = 77775 300'		BUILDING: 234-52	AREA: 200 W	
REMARKS			ADDRESS (OFF SITE)		
DATE 3-2-82			TIME		
SIGNATURE R. W. Carter			SIGNATURE J. U. Cotton 10/15/81		

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Sorbed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Resin. (Include PDR number and Property Control numbers)						
50% Dust Work						
30% Plastic						
20% Paper						
						Vol. % Combustible 50
						Vol. % Noncombustible 50
Container	BOX	NO. 355 In. 2350-6	LENGTH 11 ft.	WIDTH 7 ft 8 in	HEIGHT 5 ft 5 in	☐ HANFORD STANDARD CARDBOARD
All Containers Must be Approved by Rockwell Hanford Operations	DRUM	TK-1 = 460 = 15000				
	OTHER					
Approval Number(s) HCS-041-001-00	TOTAL VOLUME (FT ³) 460		Gross Weight 15,000		☒ Pounds ☐ Kilograms	

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Rb, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)			
P. U.			
Plutonium 70 Grams	TRU other than Pu Grams		
Fissile Content 70 Grams	URANIUM Grams	ACTIVITY (If TRU or U, only units in Grams required) 105	
DOSE RATE < 1 m R/hr	☒ SURFACE ☐ INTERIOR ☐ FEET		
DISTRIBUTION:		BY SHIPPER	
WHITE } WITH SHIPMENT YELLOW } PINK } GOLDENROD - RETAIN		BY ROCKWELL WHITE - SWG, 2700-2 YELLOW - NUCLEAR MATERIALS, 2704-2 PINK - RETURN TO SHIPPER	

Combustible 116.5 + 116.6 + 116.7 + 116.8 + 116.9 + 117.0 200W-TAT-A2-1 (2)

Rockwell Hanford Operations					TRANSURANIC DRY WASTE STORAGE					Check One ☒ Combustible ☐ Non-Combustible	
Non-Combustible Materials*					Combustible Materials*						
Drum No.	Grams Fissile Material	Measurement Method	Operator	Trench	Drum No.	Grams Fissile Material	Measurement Method	Operator	Trench	M.S.N.	
					2350-3	52	VDA	RA JONES	12-5-A20		
					2350-4	15			12-5-A20		
					2350-5	8			12-5-A20		
					2350-6	70			12-5-A20		
					See H 116	0					

* Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet

Certified By (Supervisor) <i>W. Cotton</i>				Date 10/15/81		
DISPOSAL SITE:				DISPOSAL SITE:		
Area	Burial Ground No.	Trench No.		Area	Burial Ground No.	Trench No.
				200-W	4C	4
Carton No.	Coordinates			Module 12	Coordinates	
	North:	West:		North 40020	West 77799	
Remarks:				Remarks		
				SECTION - 12 40020 77775		
Signature				Signature		Date
				<i>W. Cotton</i>		3-2-82
DRUMS ARE ACCEPTED PER SOP				Distribution		
Signature:				All Accompany Shipment if Completed		
<i>P. Stunk</i>				Pink - To Be Returned		
Date				White & Yellow - With Shipment if No Returned Copy Desired.		
10/16/81						

Combustible #1166

IMPORTANT: Use Black Ball Point Pen Where Handwritten Entries Are Required

M-14
S-1+2
N-A20

(2)

SOLID WASTE BURIAL RECORD

200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE
By Rockwell Hanford Operations

1166

286-1-280

DISPOSAL SITE

This portion of form is to be completed by
Rockwell Representative at Disposal Site.

ORIGINATOR

200W-JA582-2

OK

AREA 200-W	BURIAL GROUND NO. 4C	TRENCH NO. 4
SECTION MADE 1E12	BEGINNING COORDINATES N 40070 - 77799	
SECTION 1+2	ENDING COORDINATES N 40070 - 77775	
REMARKS THESE ARE BOTA AND THEY TAKE UP TOP SECTION		
DATE 3-2-82		TIME
SIGNATURE G.W. Cook		

PACKAGE NO. X-17890	DOE Authorization No (RAM) N-A20
COMPANY J.A. JONES	
BUILDING 234-57	AREA 200 W
ADDRESS (OFF SITE)	
I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below, and that the contents meet RHO MA 222 requirements and are packaged in Rockwell approved containers per RHO MA 222.	
SIGNATURE J.A. Jones	

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Sealed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Resin.
(Include PDR numbers and Property Control numbers)**7090 Duct Work**
1070 Plastic

Container		NO. 354	LENGTH	WIDTH	HEIGHT	Vol. % Combustible 10
All Containers Must be Approved by Rockwell Hanford Operations	BOX	2350-3	114"	74 3/4"	54 5/8"	Vol. % Noncombustible 90
	DRUM	NO. AND SIZE				HANFORD STANDARD CARDBOARD
	OTHER	NO. AND SIZE				
Approval Number(s) HCS-641-001-00		TOTAL VOLUME (FT ³) 460		Gross Weight 15000		☒ Sounds ☐ Kilo grams

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION IS G. LONG-LIVED ISOTOPES SUCH AS Pu, Pa, Sr, Fission products, activation products

Pu

Plutonium 52	Grams	TRU other than Pu Grams	
Fissile Content 52	Grams	URANIUM Grams	ACTIVITY (if TRU or U, only units in Grams required) 28
DOSE RATE <1		mR/hr at Contact	
DISTRIBUTION:		BY SHIPPER	
WHITE YELLOW PINK GOLDENROD - DETAIL		BY ROCKWELL	
		WHITE - ONE, 2750-1 YELLOW - NUCLEAR WATER-ALS, 2750-2 PINK - RETURN TO SHIPPER	

Rockwell Hanford Operations

TRANSURANIC DRY WASTE STORAGE

Check ☒ Non-Combustible ☐ High-Combustible

Non-Combustible Materials					Combustible Materials				
Drum No.	Grams Filled Material	Measurement Method	Operator	Trench	Drum No.	Grams Filled Material	Measurement Method	Operator	Trench
					② 2350-3	52	WDA	RAJONES	12-1-A20
					2350-4	15			12-1-A20
					2350-5	8			12-1-A20
					2350-6	70			12-1-A20
					SEP 116	0			
THESE ARE BOXES 11'x7'8" x 5'5"									
AND THEY TAKE UP THOSE SECTIONS									
TWO									

* Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet

Certified By: <i>1/11 Cotton</i>			Date: <i>10/15/81</i>		
DISPOSAL SITE:			DISPOSAL SITE:		
Area	Burial Ground No.	Trench No.	Area	Burial Ground No.	Trench No.
			<i>2002</i>	<i>4C</i>	<i>4</i>
Cation No.	Coordinates	Notes	Cation No.	Coordinates	Notes
	North:	West:	<i>Model 12</i>	North: <i>40070</i>	West: <i>77297</i>
Remarks:			<i>SECTION 142</i>	<i>40070</i>	<i>77275</i>
Signature: <i>O. H. H. H.</i>			Signature: <i>R. W. Carter</i>		
Date: <i>10/16/81</i>			Date: <i>3-2-82</i>		
FORMS ARE ACCEPTED PER SOP <i>10-100-370</i>			Distribution		
			An Accompanying Shipment If Completed Pink - To Be Returned White & Yellow - With Shipment If No Return Copy Desired.		

IMPORTANT: Use Black Ball Point Pen Where Handwritten Entries Are Required

700 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE
By Rockwell Maryland Operations

287

DISPOSAL SITE		This portion of form is to be completed by Rosenberg Representative at Crematorium.		ORIGINATOR <u>200-JAI-12-3</u>	
AREA <u>200-W</u>	BURIAL GROUNDS <u>4C</u>	TRENCH NO. <u>4</u>	PACKAGE NO. <u>V-17890</u>	DOE Authorization No (PRM)	
Module - 12	Sequence Coordinates <u>40070</u>	<u>77799</u>	Company <u>J. A. JONES</u>		
Section - 142	Series Coordinates <u>40070</u>	<u>77775</u>	BUILDING: <u>234-5</u>	AREA: <u>200 W</u>	
REMARKS			ADDRESS (OFF SITE)		
DATE <u>3-2-82</u>			TIME		
SIGNATURE <u>[Signature]</u>			SIGNATURE <u>[Signature]</u>		

WATER A. CONTAINS: There are several small fish. E.G., Sunfish, Catfish, Dredge, Pump, Sampling in laboratory paper waste, Timbers, Rebar.
(line use for numbers and possibly Control numbers)

EO 7c filter Box
10 7c Pinstu
10 7c Rays

Consider		Vol. % Compressed
A. Containers		100
Must be	100	Vol. % Rencorruptible
Approved	100	
by	100	
Rockwell:	100	
Manford	100	
Operations	100	
OTHER	100	
TOTAL VOLUME (ST)		15000
Gross Weight		15000
Net Weight		15000
Net Weight		15000

GENERAL APPLICABILITY DESCRIPTION: U.S. LUGGAGE AND BAGGAGE D.C.M. AS PER (U.S.F.) WHEEL PROBLEM ONLY; ACTIVATION CODE: 00000000

REV

Photocopy		TRU other than P ₀			
<u>15</u>	Grams	<u> </u>	Grams		
Frame Contents		URANIUM		ACTIVITY (if TRU or U, only units in Grams required)	
<u>15</u>	Grams	<u> </u>	Grams	<u> </u>	<u>22.5</u>
GROSS RATE				CURIES	
<u> </u>		<u> </u>		☒ SURFACE ☐ INSIDE ☐ FEET	
<u>< 1</u>		<u> </u>		<u> </u>	
DISTRIBUTION:		BY SHIPPER		BY ROCKWELL	
WHITE YELLOW ORANGE BLUE/GREEN - 25%		WHITE YELLOW ORANGE BLUE/GREEN - 25%		WHITE - ONE 1" SLE YELLOW - 0.1" FOR WATER ALB, 2750.0 ORANGE - 0.1" FOR 1" SLE	

BC 6800 076 (A-4.79)

Classified Material ☐ Yes ☒ No Special Nuclear Material ☒ Security Escort Required ☒		ONSITE RADIOACTIVE SHIPMENT RECORD (Instructions For Completion On Back)		200W-0110-1 10030	
DOE CONTRACTOR: ☐ PNL ☐ MEDL ☒ ETHO ☐ UNC					
NAME		CONTRACTOR AND COMPONENT		BUILDING AND AREA	PHONE
To: OSCAR STRUNK		RHO B-46300		224U-200W	3-2376
From: HU COLTON		RHO B 46630		234-52 200W	3-2327
Carrier: J.A. Jones				Vehicle No. 68F 9328	
COMPLETE DESCRIPTION OF RADIOACTIVE CONTENTS: Radionuclide(s): <u>PLUTONIUM 239</u> Estimated Activity (Curies)/Container: <u>2.25</u> Grams Fissile/Container: <u>1.5</u> Total Grams Fissile/Shipment: <u>15</u> Total Curies/Shipment: <u>22.5</u>			DETAILED PACKAGING DESCRIPTION: <u>80% FILTER BOXES</u> <u>10% RAQS - COMBUSTIBLE</u> <u>10% PLASTIC</u> <u>RADIO ACTIVE MATERIAL FISSILE. N.D.S.</u> <u>SEALED IN BURIAL BOX 2350-6</u>		
Container Approval Document(s): Shipment Number (when applicable):			Container(s) ☒ Single Trip ☐ Reusable Absorbent Material Required ☐ Yes ☒ NA Container(s) Free of Deterioration and/or Damage ☒ Yes Required Labels and/or Placards Affixed ☒ Yes Accountable Nuclear Material Transfer Documents Prepared ☒ Yes ☐ NA		
EXTERNAL RADIATION (mrem/hr) Package: At Contact <u>< 1 mR/hr</u> At 3 Feet: <u>< 1 mR/hr</u> Vehicle: At Side: <u>< 1 mR/hr</u> At 6 Feet: <u>< 1 mR/hr</u> In Cab: <u>< 1 mR/hr</u>			REMOVABLE CONTAMINATION (d/m / 100 cm²) Smears of Outer Container X <u>≤ 2200</u> or <u>< 2200</u> d/m Beta-Gamma Y <u>≤ 220</u> or <u>< 220</u> d/m Alpha		
List Other Pertinent Information:					
RM Escort Required ☒ Yes ☐ No RM Supervisor Review Required ☐ Yes ☐ No Surveyed by: <u>Robert H. Colley</u> <u>10-13-81</u> Reviewed by: _____ Date: <u>10-13-81</u> Radiation Monitor					
INSTRUCTIONS 1. Speed Limit Restricted To: <u>25</u> MPH. Never exceed posted limits. 2. Do not leave shipment unattended between pick up and drop off points. 3. In case of an accident or spill notify RM immediately. Phone <u>3-2564</u> 4. Shipments during hazardous road conditions and/or congested traffic should be avoided. 5. Tie down or restrain package to prevent shifting or loss of packages during transport. 6. Declare material and present shipment record at each patrol check point. 7. Obtain RM release of transport vehicle after delivery of radioactive materials. 8. Obtain Receiver's Signature: Received by <u>O Strunk</u> Date <u>10-16-81</u>					
NOTE: Person authorizing shipment must not transport it.					
CERTIFICATION This/These package(s) has/have been prepared for onsite shipment in accordance with DOE-RL and Contractor Shipping Requirements:					
<u>H.D. Colton</u> Shipping Organization Rep.		<u>HU COLTON</u> Print Name		<u>10/8/81</u> Date	
Patrol Checkpoint	☐ In ☐ Out Area	☐ In ☐ Out Area	☐ In ☐ Out Area	☐ In ☐ Out Area	☐ In ☐ Out Area
Time/Date					
Patrolman Number					

(DISTRIBUTION - See Back For Instructions)

54-3000-609 (R-7-81)

Combustible 11/68

IMPORTANT: Use Black Ball Point Pen Where Handwritten Entries Are Required

SOLID WASTE BURIAL RECORD
200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE
By Rockwell Hanford Operations

1168
283

DISPOSAL SITE

This portion of form to be completed by
Rockwell Representative at Disposal site.

ORIGINATOR

200W-JAI-82-4

AREA 200-W	BURIAL GROUND NO. 4C	TRENCH NO. 4
Module 12	DESIGNING COORDINATES N 40070 - 72799 281 FT	
Section 1+2	ENDING COORDINATES N 40070 - 72275 - 364 FT	
REMARKS		
DATE 3-2-84		
SIGNATURE R. W. Carter		

PACKAGE NO. X-17890	DOE Authorization No (RAM)
COMPANY JA JONES	
BUILDING 234-52	AREA 200LU
ADDRESS (OFF SITE)	
I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below, and that the contents meet RMO MA 222 requirements and are packaged in Rockwell approved containers per RMO-MA-222.	
SIGNATURE JL Cotton	DATE 10/15/81

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Sorbed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Resin.
(Include PQR numbers and Property Control numbers)

20% DUCT WORK

30% PLASTIC

50% BURNED

		Vol. % Combustible 50	
		Vol. % Noncombustible 50	
Container	BOX	NO. 347	LENGTH
All Containers Must be Approved by Rockwell Hanford Operations	DRUM	SEL. NO. 3350-5	11 FT.
	OTHER	NO. AND SIZE	
		NO. AND SIZE	
		WIDTH	HEIGHT
		7 1/2 in	5 1/2 in
		TK = 1 - 460 - 1500	
Approval Number(s)	TOTAL VOLUME (FT ³)		Gross Weight
ACS-AM-001-00	400		15000
			☒ Pounds ☐ Kilograms

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION IS A. LONG-LIVED ISOTOPES SUCH AS Pu, Cm, Sp, F, MIMES FISSION PRODUCTS, ACTIVATION PRODUCTS

Pu

Plutonium	Grams	TRU other than Pu	Grams
8		1	
Fission Content	Grams	URANIUM	Grams
8		1	
DOSE RATE	mR/hr	ACTIVITY (in TRU or U, only units in Grams required)	Curies
<1		12	
		☒ SURFACE	
		☐ INTERIOR	
		☐ FEET	
DISTRIBUTION:		BY SHIPPER	
		WHITE - 2750-E	
		YELLOW - 2750-E	
		PINK - 2750-E	
		GREEN - 2750-E	

Rockwell Hanford Operations					TRANSURANIC DRY WASTE STORAGE				
Non-Combustible Materials*					Combustible Materials*				
Drum No.	Grams Fissile Material	Measurement Method	Operator	Trench	Drum No.	Grams Fissile Material	Measurement Method	Operator	Trench
					2350-3	52	VD.A	RA JONES	12-1/2-A2
					2350-4	15			12-1/2-A2
					2350-5	8			12-1/2-A2
					2350-6	70			12-1/2-A2
					SEP# 116	0			

*Use form for either Non-Combustible or Combustible Materials - no mixing - use another sheet

Certified By (Supervisor)

W. Cotton

Date

10/15/81

DISPOSAL SITE:

Area: Burial Ground No.: Trench No.:

Casson No.:

Coordinates

North:

West:

Remarks:

DISPOSAL SITE:

Area: Burial Ground No.: Trench No.:

Casson No.:

Coordinates

North: 40070

West: 777.99

Remarks:

SECTION 1+2

40070

777.75

Signature

Date

DRUMS ARE ACCEPTED PER SOP

Signature:

O. Shank

Date

10/14/81

Signature

R. W. Parker

Date

3.2.82

Distribution

All Accompany Shipments if Completed

Pink - To Be Returned

White & Yellow - With Shipment if No Returned Copy Desired.

IMPORTANT: Use Black Ball Point Pen Where Handwritten Entries Are Required

M-12
S. 200
A. A 5-

②

200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE
By Rockwell Hanford Operations

1170
~~1158~~ 477

DISPOSAL SITE

The portion of form 10 to be completed by
Ruggs will be submitted as Disposed also.

CRISINATOR

200W-JAT-2-5

55

AREA 200-W	BURIAL CROUND NO. 4C	TRENCH NO. 4
MOD-12	MEASURED COORDINATES	
	- 40070	- 77799
SECTION-3	ENDING COORDINATES	
	- 40070	- 77775

DOE ADOPTION
No. (P.M.) A 54

J.A. JONES

BUILDING: 73447 AREA: 73447

APPROX. 1968 DATE

950495

DATE	3-30-81	TIME
------	---------	------

SIGNATURE B. W. Carter

157, C. 1/2	10/15/81
-------------	----------

PHYSICAL DESCRIPTION

MATERIAL CONTENTS: Indicate any special conditions. E.G., Sealed, Liquid, Drier, Pump, Sampling or Laboratory paper waste, Timers, Resin
 (Include PQR numbers and Property Control numbers.)

817 FUTURE LOSS

104: Diet Lick

10 9. Plastic

234-5 25R - 16-81-3

Vol. 5 Continued

22

234 -5 -Z

22

82

Container	QTY	SIZE	LENGTH	WIDTH	HEIGHT	REMARKS
All Containers	521	SEC #114	17 FT	6 FT	7 1/2 FT	HANFORD STANDARD CARDBOARD
Approved by	SP-8	QTY AND SIZE	TL = 1 = 511 - 16000			
Rockwell Hanford Operations	OT-ER	QTY AND SIZE				

ADDENDUM NUMBER 15: TOTAL VOLUME (BT) 500 2000 WEIGHT 16.000

ACTIVITY DESCRIPTION

GENERAL ACTIVITY INFORMATION: U.S. AIRCRAFT - 103-1987214 S-6H AS

21

 $c_1 = 2$

Plutonium 0 Grams	TRU other than Pu 0 Grams	
----------------------	------------------------------	--

Filling Contents	Weight	ACTIVITY (if TRU or U, only units in Grams required)
<u>0</u> Grams	<u>0</u> Grams	<u>0</u> seconds*
		Charges

DATE DATE 41 INCHES 2 inches

DISTRIBUTION:		<u>BY SHIPPER</u>		<u>BY ROCKWELL</u>	
WHITE	} BY SHIPPER	WHITE	- 500,270-0		
YELLOW		YELLOW	- 4,200,000 WHITE GLS, 270-0		
BLUE		BLUE	- 007,000 "B" GLASS		
GLASS 0023	- 007,000				

02 4823 274 • 04 791

MODULE 13 West coordinate 77798 to 77824)

Module 13 consists of 533 spaces for 55-gallon drums stacked in a 12 by 12 by 4 high configuration and one 16'x 7'x 12' high box weighing 29,100 pounds. Module 13 was built in the spring and summer of 1982 so that most of the drums will be galvanized steel.

The 234-5Z Facility generated 185 drums of waste containing 253.0 grams of plutonium, 151 drums had no measurable plutonium. The Vallecitos (GE) Facility generated 35 drums containing 106 grams of plutonium, and 243 grams of uranium. Two drums had no measurable plutonium. The 340 (WHC) Facility generated 33 drums containing 586 grams of plutonium, 21,239 grams of uranium, and 0.48 grams of americium; and the large box containing 7.2 grams Pu and 15,000 Ci of ¹⁴⁷Pm, which has about a 2.6 year half life, so if the box is retrieved in about 1999 the Pm activity will be about 170 curies. The 340 (PNL) Facility generated 10 drums containing 15 grams of long-lived plutonium, and 1.25 grams of plutonium-238. The WARD (WEC) Facility generated 107 drums containing 88 grams plutonium, and 839 grams of uranium. Twelve drums contain no measurable Pu. The 202A Facility generated 144 drums, but only one drum contained measurable plutonium and it had 6.0 grams. The BABCOX (APA) Facility generated 8 drums containing 112 grams of plutonium, 292 grams of uranium, and 0.39 grams of americium. The 231Z (PNL) facility generated 11 drums with 2.3 grams.

The module totals include about 1180 grams of long-lived plutonium, one drum containing 1.25 grams of plutonium-238, 22,900 grams of uranium, and 0.87 grams of americium. There were 308 drums that had no measurable plutonium. The highest plutonium loaded drum was one generated by 340 (WHC) that had 72.5 grams located in position L4 tier 4. The maximum dose rate recorded was 10 mrem/hr from primarily WARD waste containers. The box contents are primarily metal (90%) with 5% plastic and 5% glass. The box displaces a two tier (upper tiers) three by seven array of drums (three rows) on the southwest corner of the module.

Organics are listed for 58 of the WARD drums and two drums from GE-VAL contain oil.

THIS PAGE INTENTIONALLY LEFT BLANK

TIER 1

HGFEDCBA

8W4C
5001

2 3 4 5 6 7 8 9 10 11 12

L K J H G F E D C B A

TIER 2

218W4C
Trench 4
Module 13

NO 40

mR

Rate
Pu

1
2
3
4
5
6
7
8
9
10
11
12

TIER 3

218W4C
 Trench 4
 0041613

218W4C

0041613

Loss Rate
 0.000000

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TIER 4

18W 4C
Trench 4
Module 15

L K J I H G F E D C B A

2
3
4
5
6
7
8
9
10
11
12

TRENCH 4 MODULE 13 TIER 1

TRENCH 4 MODULE 13 TIER 2

TRENCH 4 MODULE 13 TIER 3

TRENCH 4

MODULE 13

TIER 4

BOXED WASTE

HEDL

340 BUILDING

THIS PAGE INTENTIONALLY LEFT BLANK

200-W 200 W 4 200
Module 13 "H0070" 77794-56
Section 2/4 "H0070" 77823

COMPANY: MEG
BUILDING: 340
ADDRESS: OFF SITE
AREA: 300

certify that no capital property is included in this burial unless docu-
mented by a Property Disposal Request, and described below, and
that the containers meet RMC-MA-222 requirements and are labeled
in Rockwell approved containers only RMC-MA-222.

metal - 90%
plastic - 5%
glass - 5%

PDR# PDL-81-177 (Item #2)
#WNE-81-233

Box # WH-81-503
S-RR WH-81-80

VOL. 1000000
5%
VOL. 4 Nonconformities
95%

Container: 30X
NO. AND SIZE
ADDITIONAL: 30X
BY: 30X
REMARKS: 30X

THE FOLLOWING STORAGE CONTAINERS
13440 29,100

Serial Number
17164-R

ACTIVITY DESCRIPTION: Metal Box - 7X12X16

GENERAL ACTIVITY DESCRIPTION: Promethium 147

PK

Plutonium
Grains
Grains
Grains
Grains

15,000
BY SHIPPER
BY ROCKWELL

DISPOSITION:
WHITE
YELLOW
BLACK

WHITE - 100%
YELLOW - 100%
BLACK - 100%

9-23-64

DISPOSAL SITE

Area	Survey Duration	Time
200. m	4E	
200. m		
Ad. d. m/e	13	4070 7790
200. m		
SE-710 m	3-4	4070 7790

— { —
חברת זיו

[illegible]

14. 1. 1991

MODULE 14 (West coordinate 77824 to 77850)

Module 14 consists of 500 mostly-galvanized 55-gallon drums, one 4960 lb FRP box 12.5' long, 4.25' wide and 3.833' high; and six metal boxes 4'x 5'x 6' weighing from 1587 lb to 2786 lb. It is stacked in a 12 by 12 by 4 high configuration. Module 14 was built from May 1982 to April 1983 (1 year).

The 202A (WHC) Facility generated 51 drums of waste containing 53 grams of plutonium, 37 drums had no measurable plutonium. The BABCOX (APA) Facility generated 84 drums containing 364 grams in 38 drums, 46 drums having no measurable quantity of Pu. Also recorded were 869 grams of uranium, and 37 grams of americium. The 234-5Z (WHC) Facility generated 303 drums. Sixty-eight of these contain 2762 grams of plutonium with the remaining 235 drums containing no measurable plutonium. The 340 (PNL) Facility generated 18 drums containing 17 grams of plutonium, 1.14 grams of uranium-233, 11 grams of americium, 1.14 grams of neptunium, and 4.11 grams of curium. There were 12 drums that had no measurable plutonium. The 340 (WHC) Facility generated 11 drums containing 188 grams of plutonium, and 744 grams of uranium. There is one drum that had no measurable plutonium. The WARD (WEC) Facility generated 32 drums and six 4'x 5'x 6' metal boxes containing 118 grams of plutonium, and 1344 grams of uranium. There were 16 drums that had no measurable plutonium. The FRP box was generated by GE VAL and contains about a third of a gram of Pu and one gram of Uranium.

The Module totals include 3560 grams of TRU and 2960 grams of uranium. There were 347 drums that had no accountable plutonium. The highest plutonium loaded drum or container was 193.0 grams from a drum generated by the 234-5Z Facility located in position K1 of Tier 2. The maximum dose rate recorded was 200 mrem/hr from a BABCOX drum.

The contents of the FRP box consist of a metal furnace in polyurethane packing foam. The metal boxes contain mostly metal ranging from 50% to 92%, by volume, with the remaining contents including varying percentages of plastic, paper, glass, rubber, wood, rags, stone, and absorbent.

The FRP box is located in the top tier in spaces in Rows I and J, positions 4 through 9. The other boxes are located in the top two tiers in Rows A through H, positions 5 through 8.

Three drums from WARD (A-061, A-076, and A-083) are listed as containing absorbed organic material with 440-460F flashpoint range.

THIS PAGE INTENTIONALLY LEFT BLANK

TIER 1

218W4C
Trench 4
Module 1 -

L K J I H G F E D C B A

2 3 4 5 6 7 8 9 10 11 12

Page 308

epc 4

2 3 4 5 6 7 8 9 10 11 12

$$\frac{1.5}{56}$$

5

218W4C
Trench 4
Module 1-

L
K
J
I
H
G
F
E
D
C
B

2 3 4 5 6 7 8 9 10 11 12

WHC-SD-W113-ACDR-001
Rev. 0
Page 309

Rev. 0

Page 309

TIER 4

218W4C
Trench 4
Model -

ata

 $\lambda < 1 \text{ mR}$

$\text{Velocity} = \text{Dose Rate}$
 $\text{Velocity} = \text{Dose Rate}$

2 3 4 5 6 7 8 9 10 11 12

L K J I H G F E D C B A

See Tier 3	See Tier 3	See Tier 3
See Tier 3	See Tier 3	See Tier 3

TRENCH 4 MODULE 14 TIER 1

TRENCH 4 MODULE 14 TIER 2

TRENCH 4 MODULE 14 TIER 4

BOXED WASTE
GE-VALECITOS
PLEASANTON

THIS PAGE INTENTIONALLY LEFT BLANK

IMPORTANT: Use Black Ball Point Pen Where Handwritten Entries Are Required

SOLID WASTE BURIAL RECORD

200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL - DOE
By Rockwell Hanford Operations

844 M-14
S-4
N-92

1795
Super Tiger 11
(69)

DISPOSAL SITE		ORIGINATOR	
This portion of form to be completed by Rockwell Representative at Disposal site.			
AREA 200-W	BURIAL GROUND NO. 4C	TRENCH NO. 4	PACKAGE NO. S.T. 01
REMARKS MODULE 14 SECTION - 4			DOE Authorization A-33 No (RRM) 3597-8
DESCRIPTIVE COORDINATES N 40070 - 77823 - 356			COMPANY General Electric Company
INDEX COORDINATES N 40070 - 77848 - 331			BUILDING: 102
			AREA: C
			ADDRESS (OFF SITE) P.O. Box 460 Pleasanton, CA 94566
DATE (4-6-83) 3-2-83			I certify that no essential property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RMO-MA-222 requirements and are packaged in Rockwell approved containers per RMO-MA-222.
TIME			
SIGNATURE R W Carter			SIGNATURE Judi Holtz

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Serbed liquid, Dissolver, Pumps, Sampling or Laboratory paper waste, Timbers, Rods, (Include PDR numbers and Property Control numbers)

COMBUSTIBLE: 49% Polyurethane packing foam

NON-COMBUSTIBLE: 51% metal furnace

						Vol. % Combustible 49%
						Vol. % Noncombustible 51%

Container <small>All Containers Must be Approved by Rockwell Hanford Operations</small>	FRP BOX	NO.	LENGTH	WIDTH	HEIGHT	☐ HANFORD STANDARD CARDBOARD
		14	150"	51"	46"	
	DRUM	NO. AND SIZE				
	OTHER	NO. AND SIZE				

Approval Number(s) **16110-R1-XREF15973**

TOTAL VOLUME (FT³) **204**

Gross Weight **4960 lbs**

☒ Pounds ☐ Kilograms

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPIES SUCH AS PU, CO, ZP, FIMISHED FISSION PRODUCTS, ACTIVATION PRODUCTS)

Pu238, 239, 240, 241 & 242; U234, 235, 236 & 238

Plutonium 329 Grams	TRU other than Pu N/A Grams		
Fission Content 291 Grams	URANIUM 1.05 Grams	ACTIVITY (If TRU or U, only units in Grams required) 7110 (microcuries) 500 mCi	
DOSE RATE 20.5 mR/hr		☒ SURFACE ☐ INSIDE ☐ FEET	

DISTRIBUTION:	BY SHIPPER
WHITE	WITH SHIPMENT
YELLOW	
RED	
BY ROCKWELL	
WHITE - ONE, 2700-6	
YELLOW - NUCLEAR MATERIALS, 2700-2	
RED - RETURN TO SHIPPER	

3/4 - 383 (07)

HC 4500-076 (A-4.79)

BOXED WASTE

WARD

CHESWICK

THIS PAGE INTENTIONALLY LEFT BLANK

Noncombustible 3389-2-2-A 7329
SOLID WASTE BURIAL RECORD
300 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL DOE
By Rockwell Hanford Operations
M-14
S-4
N-A-4
73
3389-2-2-A

DISPOSAL SITE This portion of form to be completed by Rockwell Representative at Disposal site.
ORIGINATOR WARD-WEC-83-6 140 OK
AREA 200-W BURIAL GROUND NO 4 TRENCH NO. 4
PACKAGE NO. 6-Model 6272 M-III bin DOE Authorization No (RRM) 3389-2
COMPANY Westinghouse Electric Corporation Advanced Reactor Division
BUILDING: AREA:
ADDRESS (OFF SITE) Cheswick Avenue Cheswick, PA 15024
I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RMO 11A 222 requirements and are packaged in Rockwell approved containers per RMO-MA 222.
DATE 12-13-82 TIME
SIGNATURE A.W. Carter D.J. Petrucci 12/11/80

PHYSICAL DESCRIPTION
MATERIAL CONTENTS (Note any special conditions) E.G., Sealed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Reels. (Include PDR numbers and Property Control numbers)
ONE
6- M-III steel bins for burial. The contents of bins RRM 3389-2-1, -2-3, -2-4, -2-5, and -2-6 are non-combustible. Waste description volume %'s are as follows: 92.27 % metal, 375 % plastic, 2.57 % paper, 1.01 % glass, 0.32 % rubber, and 0.01 % wood. The contents of bin RRM 3389-2-2 is combustible. Waste description volume %'s are as follows: 11.0 % plastic, 19.3 % paper, and 9.7 % wood.
Vol. % Combustible 16.7
Vol. % Noncombustible 83.3
Container BOX NO. LENGTH WIDTH HEIGHT
A. Containers Must be Approved by Rockwell Hanford Operations
DRUM NO. AND SIZE
OTHER 6- M-III steel bins, RRM 3389-2-1 through RRM 3389-2-6. ~4' x ~5' x ~6', volume: 125 cu. ft. each
Approval Number(s) RRM 3389-2, 1 thru 6 TOTAL VOLUME (FT³) 125 Gross Weight 2786
Pounds
Kilograms

ACTIVITY DESCRIPTION
GENERAL ACTIVITY DESCRIPTION IS A. LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS
All materials listed in the physical description section are contaminated with the following radionuclides: ²³⁴U, ²³⁵U, ²³⁸U, ²³⁸Pu, ²³⁹Pu, ²⁴⁰Pu, ²⁴¹Pu, ²⁴²Pu
Plutonium 67.0 Grams TRU other than Pu 0 Grams 120 gms. @ 79.3 cpm, 2 gms. @ 93.16 cpm
Fission Content 164 Grams URANIUM 0 Grams
DOSE RATE <0.3 mR/hr 3
CURIES
SURFACE
INERT
for all bins
DISTRIBUTION: BY SHIPPER BY ROCKWELL
WHITE - ONE, STOW-E
YELLOW - SULLIED MATERIALS, STOW-E
RED - RETURN TO SHIPPER
64-3000-001 (R-4-79)

3359-1-2-30901-1
C.A.M.B.A.T.A.I.E
3359-1-2-30901-1

Rockwell Hanford Operations
TRANSURANIC DRY WASTE STORAGE
Check One
Non-Combustible
Combustible

Non-Combustible Materials
Combustible Materials
BIN
Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

Drum No. 140
Gross Weight 36.30 NDA 16.50
Net Weight 14.40
Trench No. 14-4-06

SOLID WASTE BURIAL RECORD
200 AREA PLATIAU DISPOSAL SITE OPERATED FOR RL DOE
By Rockwell Hanford Operations

M - 14
S - 4
N - A-5 141

2330

DISPOSAL SITE This portion of form is to be completed by Rockwell Representative at Disposal Site.

ORIGINATOR WARE-WEST 527

AREA 200-N BURIAL GROUND NO. 4 C TRENCH NO. 4

Package NO. 4-M III Bins in Mod 422 Japack DOE Authorization No (RRM) 3389-6

Company WESTINGHOUSE ELECTRIC CORP. ADVANCED REACTOR DIVISION

Building: AREA:

Address (off site) Cheswick Ave Cheswick, PA 15024

I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RHO-MA-222 requirements and are packaged in Rockwell approved containers per RHO-MA-222.

DATE 12-13-82 TIME

SIGNATURE R. W. Carter

SIGNATURE D J Petrarca 5/27/81

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions: E.G., Solid, Liquid, Dissolved, Pump, Sampling or Laboratory paper waste, Timbers, Rock, etc.) (Include PDR numbers and Property Control numbers)

Six M-III Steel bins for burial. Waste description volume %'s are as follows: 81.98 % metal, 7.47 % paper, 6.65 % plastic, 2.73 % rubber, 0.99 % wood, 0.10 % stone, 0.03 % rags, 0.03 % glass, 0.02 % absorbent.

Vol. % Combustible 16.67

Vol. % Noncombustible 88.33

Container	BOX	NO.	LENGTH	WIDTH	HEIGHT
All Containers Must be Approved by Rockwell Hanford Operations	DRUM	NO AND SIZE			
	OTHER	NO AND SIZE			
	1-M-III steel bins, RRM 3389-6-1 thru 3389-6-6, ~4'x~5'x~6' Volume: ~125 ft ³ each				

Approval Number(s) 3389-6-1 thru 6 TOTAL VOLUME (FT³) 750 (125) Gross Weight 16,338 (1726) ☒ Pounds ☐ Kilograms

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Cs; MIXED FISSION PRODUCTS; ACTIVATION PRODUCTS)

All materials listed in the physical description section are contaminated with the following radionuclides: U²³⁴, U²³⁵, U²³⁶, U²³⁸, Pu²³⁸, Pu²³⁹, Pu²⁴⁰, Pu²⁴¹, Pu²⁴²

Plutonium	TRU other than Pu	Grams	Activity (if TRU or U, only units in Grams required)
28 5.95		35, @ 79.3, 23, @ 52.0, 15, @ 37.0, 8, @ 40.0, 1, @ 12.0	

Dose Rate < 1 29.23 mR/hr or 3 ☐ Surface ☐ Internal ☒ Feet for all bins

DISTRIBUTION: BY SHIPPER BY ROCKWELL

WHITE - GMS, 2700-1
YELLOW - NUCLEAR MATERIALS, 2700-1
PINK - RETURN TO SHIPPER

AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

5 of 8

Rockwell Hanford Operations		TRANSURANIC DRY WASTE STORAGE		Check One: ☒ Combustible ☐ Non-Combustible	
Non-Combustible Materials*		Combustible Materials*			
Drum No.	Grams Fissile Material	Measurement Method	Operator	Trench	
M1	400-3665 -023	29 lb	NDA	13 S	14-4-
		173	1000		
	DV= 125-172 L		DTAL	1	
			18	= .01	

*Use form for either Non-Communist or Communist Material - no mixing - use another sheet

Date: <i>5-27-81</i>	
Disposal Site:	
Area: <i>200-W</i>	Burial Ground No.: <i>4C</i>
Trench No.: <i>4</i>	Coordinates: <i>North 4007D West 77843</i>
Casson No.: <i>4</i>	Remarks: <i>4007D 77843</i>
Signature: <i>J. R. Bishop</i>	Date: <i>5-27-81</i>
DRUMS ARE ACCEPTED PER SOP <i>70-100-050</i>	Signature: <i>J. R. Bishop</i>
Date: <i>5-27-81</i>	Date: <i>5-27-81</i>

2331

4-7-8

RRM-3389-7.

44-38861-10473

PRM - 3389-2

$$19 = .005$$

.....

Date 6-10-81

Model/E	14	Coordinates	North 45071	West 77823
Serial	5527154		40070	77848

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
DATE 8-20-2008 BY 60322 UCBAW

Combination 3389-8AC7
6-29-81
BIN 032
M^{II} Bin (73)
2332

SOLID WASTE BURIAL RECORD BY 48
200 AREA PLATEAU DISPOSAL SITE OPERATED FOR RL DOE
By Rockwell Hanford Operations

DISPOSAL SITE This portion of form to be completed by Rockwell Representative at Disposal site.

AREA 210-W	BURIAL GROUND NO. 4C	TRENCH NO. 4
Module 14	DESIGNER COORDINATES + 40070 - 72822	250'
Section 4	ENGINEER COORDINATES + 40070 - 72848	231'

REMARKS

DATE 12.13.82 TIME

SIGNATURE R. W. Casler

ORIGINATOR WAFD-WEC-82-9

PACKAGE NO. 6-MII Bins in M ^{II} 1275	DOE Authorization No (RRM) 3389-8
COMPANY WESTINGHOUSE - ELECTRIC CORP. ADVANCED REACTOR DIVISION	
BUILDING:	AREA:
ADDRESS (OFF SITE) CHESWICK AVE. CHESWICK, PA 15024	
I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below; and that the contents meet RMO-MA-222 requirements and are packaged in Rockwell approved containers per RMO-MA-222.	
SIGNATURE D.J. PETRARCA	6/25/81

PHYSICAL DESCRIPTION

MATERIAL CONTENTS (Note any special conditions) E.G., Sorbed liquid, Dissolver, Pump, Sampling or Laboratory paper waste, Timbers, Reels, (Include PCR numbers and Property Control numbers)

24 - 55 gallon drums and 3 - MII steel bins for burial. Waste description volume %s are as follows: 33.33% metal, 29.90% plastic, 15.69% paper, 7.22% cement, 7.69% rubber, 2.97% absorbent, 1.92% rags, 0.99% oil and 0.29% wood. DRUMS A-061, A-076, A-083 contain: ABSORBED ORGANIC MATERIAL, FLASH POINT RANGE: 440-460 °F

Vol. % Combustible	46.8%
Vol. % Noncombustible	53.2%

Container	BOX	LENGTH	WIDTH	HEIGHT	MANFORD STANDARD CARDBOARD
All Containers Must be Approved by Rockwell Hanford Operations	DRUM	NO. AND SIZE RRM 3389-8-1 THROUGH 24			
		1 - painted 55 gal. DOT 17C, 5 painted 55 gal. DOT 17H, 18 galvanized 55 gal. DOT 17C			
		NO. AND SIZE RRM 3389-8-25 THROUGH 27			
		3 - MII steel bins			
		1 - MII Bin RRM - 316045-032			

Approval Number(s): 3389-8-1 thru 125 1702

ACTIVITY DESCRIPTION

GENERAL ACTIVITY DESCRIPTION (E.G., LONG-LIVED ISOTOPES SUCH AS Pu, Co, Sr, Ce, mixed fission products, activation products)

All materials listed in the physical description section are contaminated with the following radionuclides: ²³⁴U, ²³⁵U, ²³⁶U, ²³⁸U, ²³⁸Pu, ²³⁹Pu, ²⁴⁰Pu, ²⁴¹Pu, ²⁴²Pu

Plutonium	Grams	TRU other than Pu	Grams	ACTIVITY (If TRU or U, only units in Grams required)
620				40, 079.3, 13, 62.0, 11, 37.0, 6, 40.0
Fission Content	Grams	URANIUM	Grams	
107				

DOSE RATE MII BINS 10.5 m R/hr at 3

DISTRIBUTION: BY SHIPPER BY ROCKWELL

WHITE	WITH SHIPMENT	WHITE	- END, 2706-6
YELLOW		YELLOW	- NUCLEAR MATERIALS, 2704-6
PINK		PINK	- RETURN TO SHIPPER
GOLDENROD	- RETAIN		

Rockwell Hanford Operations TRANSURANIC DRY WASTE STORAGE

Check One
☒ Combustible
☐ Non-Combustible

Non-Combustible Materials					Combustible Materials				
Drum No.	Grams Fissile Material	Measurement Method	Operator	Trench	Drum No.	Grams Fissile Material	Measurement Method	Operator	Trench
			-	+ *	A-061	<1	NDA	5/8	14-5.4
			-	+	A-169	2	NDA	5/8	
			-	+	A-178	3	NDA	5/8	
			-	+	A-170	<1	NDA	5/8	
			-	+	A-177	3	NDA	5/8	
			-	+	A-076	41	NDA	5/8	
			-	+	A-174	<1	NDA	5/8	
			-	X	A-164	<1	NDA	5/8	
			-	X	A-165	1	NDA	5/8	
			-	+	A-176	1	NDA	5/8	
			-	+	A-179	3	NDA	5/8	
			-	+	A-180	6	NDA	5/8	
			-	+	A-083	<1	NDA	5/8	
			-	+	A-161	<1	NDA	5/8	
			-	+	A-158	3	NDA	5/8	
			-	+	A-162	3	NDA	5/8	
			-	+	A-166	6	NDA	5/8	
			-	+	A-168	3	NDA	5/8	
			-	+	A-032	2313	NDA	10.5/8	14-4.81

145 ARD-36045 032 2313 NDA 10.5/8

Bin M¹⁰ STORER TEMP. 24

TRENCH 7 - BIN 48 Dose .5

DV = 125 = 1702 M = .005

* ABSORBED ORGANIC MATERIAL

FLASH POINT RANGE: 440-460 °F

* Use form for either Non-Combustible or Combustible Material - no mixing - use another sheet

Signature: *D. R. Bishop* Date: 6-25-81

DISPOSAL SITE			DISPOSAL SITE		
Area	Burial Ground No.	Trench No.	Area	Burial Ground No.	Trench No.
			JOB. 10	HC	4
Cannon No.	Coordinates		Section No.	Coordinates	
	North	West	Module 14	North 40070	West 77823
Remarks			SEC 7100	4	40070 77846

Signature: *R. W. Carter* Date: 12/13/82

ORIGINS ARE ACCEPTED PER SOP T.O. 100-050

Signature: *R. W. Carter* Date: 6.27.84

Distribution:

All Accompanying Shipment If Completed
Pink - To Be Returned
White & Yellow - With Shipment If No Returned Copy Desired.

1618

64-3886-972 (4-97)

THIS PAGE INTENTIONALLY LEFT BLANK

MODULE 15 (West coordinate 77850 to 77876)

Module 15 consists 385 galvanized 55-gallon drums stacked in a 12 by 12 by 4 high configuration incorporating ten 7'x 6'x 6' high metal boxes. These boxes weigh from 3170 pounds to 5664 pounds. Module 15 was built in March through August of 1983.

The BABCOX (APA) Facility generated 29 drums containing 44.0 grams of plutonium, 132 grams of uranium, and 0.14 grams of americium. There were 23 of the drums that contained no measurable plutonium. The 340 (PNL) Facility generated 8 drums containing 32.5 grams of plutonium, 0.09 grams of uranium, 0.24 grams of americium, 0.045 grams of neptunium, and 2.1 grams of californium. The 340 (WHC) facility generated 15 drums with 144 grams Pu and 1108 grams Uranium. The 234-5Z (WHC) Facility generated 244 drums containing 880 grams of plutonium, 191 drums had no measurable plutonium. The WARD (WEC) Facility generated 68 drums containing 59.0 grams of plutonium, and 673 grams of uranium. There were 44 drums that had no measurable plutonium. The ten boxes from WARD each with one gram or less of Pu and a total of 349 grams Uranium in the ten boxes. The 324 (WHC) Facility generated 19 drums containing 487 grams plutonium, 30,979.22 grams of uranium, and 635.3 grams of thorium. The 202A (WHC) generated two drums containing no plutonium nor uranium.

The Module totals include 1660 grams of TRU, 33,240 grams of uranium and 645 grams of thorium. There were 271 drums that had no measurable plutonium. The highest plutonium loaded drum was a 117.0 gram drum from 234-5Z located in position E5 of Tier 2.

The contents of two of the boxes are listed as plastic and wood (91%-19% and 72%-28% plastic to wood). The remaining boxes are recorded to contain metal and plastic ranging from 13% to 87% metal. Eight of the boxes occupy all four tiers in Rows G, H, and I across all positions, 1 through 12. The other two boxes occupy Rows C through F, Positions 4 through 9, Tiers 3 and 4.

WHC-SD-W113-ACDR-001
Rev. 0
Page 328A

THIS PAGE INTENTIONALLY LEFT BLANK

L K J I H G F E D C B A

TIER 1

218W4C

Trench 4

Module 10

Test Data

Test Point 4 JmR

Test Point 4 Use Rate

Test Point 4 Pu

2
3
4
5
6
7
8
9
10
11
12

TIER 2

218W41
Trend
Module

L K J I H G F E D C B A

2 3 4 5 6 7 8 9 10 11 12

TIER 3

18W4C

Pench 4

10W5 15

K J H G F E D C B A

2
3
4
5
6
7
8
9
10
11
12

Rate
P.

L K J I H G F E D C B A

TIER 4

218W4C
Trench 4
Module 15

190

2.5
38

35

25

8
32

70

9

2
3
4
5
6
7
8
9
10
11
12

See Tier 3

See Tier 3

Base Rate
Base Pu

TRENCH 4 MODULE 15 TIER 1

TRENCH 4 MODULE 15 TIER 2

TRENCH 4 MODULE 15 TIER 3

TRENCH 4 MODULE 15 TIER 4

BOXED WASTE

WARD

CHESWICK

THIS PAGE INTENTIONALLY LEFT BLANK

1398 1632
- TRANSURANIC (73)

5642 is Metal; 43 58% Plastic

$(b) = 35$

Commodity	Unit & Measurement	Total Estimated Quantity
43 SP 9.	56.429.	

SS Galion Dum	Access Number(s) 17125 R-1	Material of Construction Steel TA?	Nuclear Transaction No. XOT-VRA #22	Property Disposal Request No. —
Length ~7'	Width ~6'	Height ~6'	Diameter —	Total Vol (cu ft) 227
Gross Weight 566.4				☒ Pounds ☐ Kilograms

Container Number	Measurement Method	Gross			TRU L. Not Included			Surface Dose (microsieverts/hr)	Seal Numbers	Tag #
		Pu	U	Empty	Weight	TRU	Current Cell			
66-5-2	Ge	1	96/07	1	—	—	—	60.1	5864/5865	15-344-BAL
						</				

TOTALS	1	96	6.7	1	-	-	Assembly Performed By J. L. Sholders
--------	---	----	-----	---	---	---	--------------------------------------

Number, Title of Project, Activity Description 234, 235, 236, 238 JS; 238, 239, 240, 241, 242 Pn.

ROCKWELL White SWSOT, 2750E
Yellow - Nuclear Material, 2704Z
Pink - Return to Shopper

94-3000-673 (4-821)

Rockwell Hanford Operations		SOLID WASTE BURIAL RECORD		TRANSURANIC						
USE BLACK BALL POINT PEN OR TYPE				SWSDT RECORD NO: <u>WARD-WEC-83450</u>						
DISPOSAL SITE		This portion of form to be completed by Rockwell Representative at Disposal Site		ORIGINATOR Check One ☒ Combustible ☐ Non Combustible						
200-N		Burial Ground No. <u>4C</u>	Trench No. <u>4</u>	End Function Shipment No. <u> </u>	DCE Authorization No. (RAM) <u>4266-5</u>					
Container No. <u>-</u>	Module No. <u>15</u>	Beginning Coordinates N <u>40070</u> W <u>77872 207</u>	Company <u>Westinghouse Electric Corp</u>							
		Ending Coordinates N <u>40070</u> W <u>77872 231</u>	Nuclear Fuel Div							
Remarks <u>M-15 S-3+4 N-B16</u>			Address Phone <u>Cheswick Ave</u> <u>Cheswick PA 15024</u> <u>412-963-5000</u>							
Signature: <u>[Signature]</u> Date <u>15-6-83</u>			I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below, and that the container meets RMO-MA 222 requirements and are packaged in Rockwell approved containers per RMC MA 222.							
Signature: <u>[Signature]</u> Date <u>16/9/83</u>										
Approved Per SOP No. <u>TC-100-050</u>			Signature: <u>[Signature]</u> Date <u>5/6/83</u>							
PHYSICAL DESCRIPTION			I certify that the waste package description below is complete based on an internally approved inspection system and that the waste package conforms to RMO-MA 222 and is approved for shipment.							
Material Contents <u>91.33% Plastic, 8.67% Wood</u>			Signature: <u>[Signature]</u> Date <u>5/6/83</u>							
			Method of Inspection/Rev No. <u>Original Review 10/0-17</u>							
<div style="display: flex; justify-content: space-between;"> (CSB#33) Vol. % Combustible <u>100</u> Vol. % Noncombustible <u> </u> Toxic/Hazardous Materials <u> </u> </div>										
CONTAINER INFORMATION										
55 Gallon ☐ Drum ☒		Approval Number <u>17125 R-1</u>		Material of Construction <u>Steel TM</u>						
Nuclear Transaction No. <u>XOT-VRA#22</u>		Property Disposal Request No. <u> </u>								
Length <u>~7'</u>	Width <u>~6'</u>	Height <u>~6'</u>	Diameter <u> </u>	Total Volume (ft ³) <u>227</u>	Gross Weight <u>3302</u> ☒ Pounds ☐ Kilograms					
Container Number	Measurement Method	Grams				TP - U - Not Included		Surface Dose (micro R/hr)	Seal Number	Tag # - S-A
		Pu	U	Free	TRU	Curies (Ci)	Isotopes			
<u>4266-S-1</u>	<u>60</u>	<u>11</u>	<u>10/0.7</u>	<u>41</u>	<u> </u>	<u> </u>	<u> </u>	<u>20.1</u>	<u>5837/1835</u>	<u>15-3+4-316</u>
TOTALS		<u>41</u>	<u>10/0.7</u>	<u>41</u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>	Analyzed Performed By <u>JL. Shaw/days</u>	
General TRU or Fricable Activity Description: <u>734, 235, 236, 238 V; 239, 239, 240, 241, 242 Pu.</u>										

SOLID WASTE BURIAL RECORD -

SWSDT RECORD NO. *WARD-WEC-84-1*

DISTRIBUTION S- PPER White } With Shipment
 Ye om }
 Pink }
 Coloured Return

ROCKWELL White SWSDT, 27508
 Ye om Nuclear Motor Co., 2706Z
 Pink Return to Shipper

SA-3000-673 (4-82)

202 1634

Rockwell Hanford Operations			SOLID WASTE BURIAL RECORD - TRANSURANIC (73)		
USE BLACK BALL POINT PEN OR TYPE			SWDWT RECORD NO. <u>WARD-WEC-842</u>		
DISPOSAL SITE This portion of form to be completed by Rockwell Representative at Disposal Site			ORIGINATOR Check One ☒ Combustible ☐ Non Combustible		
200-W	Burial Ground No. <u>4C</u>	Trench No. <u>4</u>	End Function Shipment No.		DOE Authorization No. (ARM) <u>4266-6</u>
Container No. <u>—</u>	Module No. <u>15</u>	Beginning Coordinates <u>N 40070</u> <u>W 27872</u> <u>207</u>	Company <u>Westinghouse Electric Corp</u>		
		Ending Coordinates <u>N 40070</u> <u>W 27848</u> <u>231</u>	Building <u>Nuclear Fuel Div</u>		
Remarks <u>S-3+4 N-1319</u>			Address Phone <u>Cheswick Ave</u> <u>Cheswick Pa 15044</u> <u>412-963-5000</u>		
Signature: Acceptance <u>SH Y...</u> Date <u>6-70-83</u>			I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below and that the contents meet RMO MA 222 requirements and are disposed in Rockwell approved containers per RMO MA 222.		
Signature: Storage Mode <u>Y...</u> Date <u>11-12-84</u>					
Acceptance Per SOP No. <u>TC-100-052</u>			Signature: <u>J. L. Shaw</u> Date <u>4/6/83</u>		
PHYSICAL DESCRIPTION			I certify that the waste package description below is complete based on an internally approved inspection system and that the waste package complies with RMO MA 222, and the approval authorization.		
Material Contents <u>86.94% Plastic, 13.06 Metal</u>			Signature: <u>J. L. Shaw</u> Date <u>4/6/83</u>		
			Method of Inspection <u>See RMO MA 222</u>		
(158437)					
86.94 13.06					
CONTAINER INFORMATION					
SS 304 or 316		ASTM Number <u>17125 R-1</u>	Material of Construction <u>Steel DV</u>	Nuclear Transaction No. <u>ADT-VRA #23</u>	Property Disposal Request No.
Length <u>27'</u>	Width <u>26'</u>	Height <u>26'</u>	Weight <u>227</u>	Net Weight <u>3170</u> Pounds	Kilograms
Container Number	Module Number	Grams	TRU	Not Included	Surface Dose
		U-235	Plutonium	TRU	See Numbers
<u>4266-2</u>	<u>Ge</u>	<u>21</u>	<u>34/67</u>	<u>21</u>	<u>LC-1</u>
					<u>SE75/82</u>
					<u>15-304-B7</u>
TOTALS <u>21</u> <u>34/67</u> <u>21</u> <u>—</u> <u>—</u> <u>—</u>					
Approved By <u>J. L. Shaw/dave</u>					
Container TRU of RMO MA 222, 234, 235, 236, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000					

DISTRIBUTION

SWDWT

White

Yellow

Pink

Green/Red Return

With Shipment

ROCKWELL

White SWDWT, 27506

Yellow Nuclear Materials, 27062

Pink Return to Shipper

14-3000-423 (4-87)

UNIT PEN OR TYPE

DISPOSAL SITE 200-W

This portion of form to be completed by
Authorized Representative of Disposal Site

Carton No. 15 Module No. 4C Trench No. 4

Beginning Coordinates N 40070 W 27872 207
Ending Coordinates N 40070 W 27848 231

Remarks S-1+02. N-1319

Signature [Signature] Date 11-12-84

Signature of Shipper [Signature] Date 11-12-84

Accepted by SOP No. 11-12-84

PHYSICAL DESCRIPTION

Material Contents 53.40% Plastic, 46.60% Metal

ORIGINATOR WDRD-WEC-84-3

Eng Function Shipment No. 1 Combustible Non Combustible

Company Westinghouse Electric Corp DOE Authorization No. 4266-8

Building Nuclear Fuel Div

Address Cheswick Ave
Cheswick Pa 15024
412-963-5000

ADDITIONAL INFORMATION

I certify that no other property is included in this burial unless clearly marked as a property of the Department and described below and that the contents meet 40 CFR 222 requirements and are packaged in accordance with 40 CFR 222.

I certify that the waste package description below is complete based on the information provided and that the waste package complies with 40 CFR 222 and is approved for shipment.

Signature [Signature] Date 6/15/85

Signature [Signature] Date 6/15/85

Signature [Signature] Date 6/15/85

(CSB#40)

53.40 46.60

CONTAINER INFORMATION

SS Code 17125 R-1 Material of Construction Steel

Length 27' Width 26' Height 26' Diameter 227

Container Number 4266-8.2 Material Gr

Weight 4374 pounds

Surface Area 10.1 sq ft

Serial Number 5919

Tag M-S-N

General Remarks 234, 235, 236, 238, 239, 240, 241, 242

Signature J.L. Shoulters

Signature [Signature]

Signature [Signature]

DISTRIBUTION

SHIPPER

TO: SWSD 27508

FROM: SWSD 27508

DATE: 11-12-84

REMARKS: 234, 235, 236, 238, 239, 240, 241, 242

54-3000-673 (4-82)

94-3000-623 (4-62)

Vol. & Co-ordinate		Topic
17.76	82.24	—

DISTRIBUTION SWINPER WHITE } WITH SHIPMENT
YELLOW }
PINK }
GREEN/RED RETURN

ROCKWELL WHITE SWSOT, 2750E
YELLOW NUCLEAR MATERIAL, 2704Z
PINK - RETURN TO SHIPPER

54-38864-23 (4-87)

CSB #38

94-3008-423 (492)

<u>DISTRIBUTION</u>	SHIPPER	WHITE	ROCKWELL	WHITE - SWSQT, 27508
		Yellow } With Shipment		Yellow Nuclear Material, 27062
		Pink } With Shipment		Pink Return to Shipper
		Green } Return		

MODULE 16 (West coordinate 77876 to 77902)

Module 16 consists of 336 galvanized 55-gallon drums and 10 steel metal boxes (7'x 6'x 6' high each) from WARD. The burial records indicate an eleventh box was placed in the trench which doesn't agree with the location sheets or the available space based on drum records. The other box was received however, and is assumed to be in Trench 04, BG 218W-4C, most likely at the bottom of the ramp into the trench just to the west of Module 19. Module 16 was built in the latter half of 1983.

The 234-5Z (WHC) Facility generated 245 drums of waste containing 441.0 grams of plutonium, 207 drums had no measurable plutonium. The WARD (WEC) facility generated 80 containers (10 metal boxes and 70 drums). The containers held 58 grams of plutonium and 454 grams of uranium; there were 21 drums that had no measurable plutonium. The 324 (WHC) Facility generated 16 drums containing 139 grams of plutonium, 1696 grams of uranium, and 0.06 grams of americium. The 324 (PNL) facility generated 1 drum containing 7.9 grams of conventional plutonium and 1.4 grams of plutonium-238. This drum also contains beryllium. The 231-Z (PNL) Facility generated 4 drums containing 0.7 grams of plutonium.

The Module totals include 650 grams of TRU (including 1.4 grams of ²³⁸Pu) and 2150 grams of uranium. There were 228 drums that had no measurable plutonium. The highest plutonium loaded drum was 77.0 grams of plutonium generated by 234-5Z Facility and is located in position F3 in Tier 1. The maximum dose rate is 20 mrem/hr recorded for a 234-5Z drum.

The differing contents of the boxes in this module include metal/plastic, wood/paper/metal, metal/wood/paper/rubber, and 100% metal for the box in question as to location. The boxes occupy all of Tiers 3 and 4 except for the northeast corner to D-6.

THIS PAGE INTENTIONALLY LEFT BLANK

TIER 1

216W4C
Punch 4

L K J I H G F E D C B A

2 3 4 5 6 7 8 9 10 11 12

MR

Rate

PU

TIER 2

8W4C
-ench 4

L K J I H G F E D C B A

20
49

6
3173 333

6 9 85

1
1

31
3

1
31

1
1

1
31

1
1

1
1

1
1

1
1

1
1

1
1

1
1

1
1
1
1

1
1

1
1

1
1

1
1

1
1

1
1

2

3

4

5

6

7

8

9

10

11

12

imR

Use Rate
m Pu

TIER 3

218W4C
Trench 4

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

mR

Rate

PU

L K J I H G F E D C B A

TIER 4

218W40
Trench

1
2
3
4
5
6
7
8
9
10
11
12

mmR

se Rate

Pj

TRENCH 4 MODULE 16 TIER 1

TRENCH 4 MODULE 16 TIER 2

TRENCH 4 MODULE 16 TIER 3

TRENCH 4 MODULE 16 TIER 4

BOXED WASTE

WARD

CHESWICK

THIS PAGE INTENTIONALLY LEFT BLANK

Rockwell Hanford Operations		SOLID WASTE BURIAL RECORD - TRANSURANIC (73)	
USE BLACK BALL POINT PEN OR TYPE		SWEDT RECORD NO. <u>WARD-WEC-M-1230</u>	
DISPOSAL SITE <small>This portion of form is to be completed by Rockwell Representative at Disposal Site</small> Site <u>200-West</u> Burial Ground No. <u>2184-4C</u> Tranche No. <u>4</u> Calendar No. <u>—</u> Measure No. <u>16</u> Beginning Coordinates <u>N 40070 W 27848</u> Ending Coordinates <u>N 40070 W 27824</u> Remarks <u>T-3+4 N-A5</u> Signature: <u>[Signature]</u> Date: <u>7-9-93</u> Signature: <u>[Signature]</u> Date: <u>2-14-94</u> Accepted For SDP No. <u>TG-100-050</u>		ORIGINATOR Check One ☒ Combustible ☐ Non Combustible Eng Function Shipment No. <u>DOE authorization No. 426-10</u> Company <u>Westinghouse Electric Corp</u> <u>Nuclear Fuel Div</u> Building <u> </u> Area <u> </u> Address Phone <u>Cheswick Ave</u> <u>Cheswick, Pa 15024</u> <u>412-963-5000</u> I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and described below and that the contents meet SDG MA 222 requirements and are packaged in Rockwell approved containers per SDG MA 222. <u>[Signature]</u> <u>7/25/93</u> Signature Date I certify that the waste package description below is correct and based on an internally approved inspection system and that the waste package conforms to SDG MA 222 and the approval authorization. <u>[Signature]</u> <u>7/25/93</u> Signature Date Independent Reviewer: <u> </u> SDG 222 Inspection S. No. <u>Document Ref. MW10-22</u>	
PHYSICAL DESCRIPTION Material Contents <u>71.88% Wood 20.98% Paper 7.14% Metal</u>			

[illegible]

~~4-3889-23 (4-87)~~

ALL INFORMATION CONTAINED
HEREIN IS UNCLASSIFIED
DATE 08-01-2001 BY SP-10

Rockwell Hanford Operations

SOLID WASTE BURIAL RECORD - TRANSURANIC

(73)

USE BLACK BALL POINT PEN OR TYPE

SWSDT RECORD NO. WARD-WRC-84-32

DISPOSAL SITE		This portion of form is to be completed by Rockwell Representative at disposal site		ORIGINATOR Check One ☐ Combustible ☒ Non Combustible	
200-West		Burial Ground No. 218W-4C Trench No. 4		End Function Shipment No. DOE Authorization No. 4266-15	
Container No.	Module No.	Beginning Coordinates		Company	
—	16	N 40070 W 77849		Westinghouse Electric Corp.	
		Ending Coordinates		Building	
		N 40070 W 77824		Area	
Remarks		Address Phone		Date	
T-3+4 N-A5		Cheswick Ave		9/16/83	
Signature - Acceptance		Cheswick PA 15024		Date	
Signature - Storage Area		412-963-5000		Date	
Accepted For SDT No. T-16-100-050		I certify that no capital property is included in this burial unless documented as Property Disposal Request, and described below, and that the contents meet RCMA 222 requirements and are packaged in Rockwell approved containers per RCMA 222.		Date	
PHYSICAL DESCRIPTION		Identify that the waste package description below is complete based on an internally approved inspection system and that the waste package complies with RCMA 222 and the approved authorization.		Date	
Material Contents:		5.12-10		Date	
100.00% Metal		5.12-10		Date	
		Material of inspection File No. Decontamination NOIC-24		Date	

Vol. % Combustible Vol. % Noncombustible Toxic Hazardous Materials

— 0 — 100 —

CONTAINER INFORMATION

— 55 Gallon Drum	Approval Number: 17125 R-1	Material of Construction: Steel	Nuclear Transaction No. XOT-URA#32	Property Disposal Request No.							
Length: 7'	Width: 6'	Height: 6'	Diameter: —	Total Volume (ft ³): 227							
Gross Weight: 3415 Pounds			Net Weight: 227 Kilograms								
Container Number	Measurement Method	Grams					TRU or Not Included		Surface Dose (mrem/hr)	Seal Numbers	Tier
		A	U	Enrichment	Fissile	TRU	Curies (Ci)	Isotopes			
42-15-11	GC	21	4	0.7	21	—	—	—	20.1	292	16-314
TOTALS		21	4	0.7	21	—	—	—	Assay Performed By J.L. Shou/doors		
General TRU or Fissile Activity Description 234, 235, 236, 238 V; 238, 239, 240, 241, 242 R.											

DISTRIBUTION

SHIPPER

White } With Shipment
Yellow }
Pink }
Colored - Return

ROCKWELL

White - SWSDT, 2750E
Yellow - Nuclear Materials, 2700-Z
Pink - Return to Shipper

64-3008-473 (4-82)

340 1656

Rockwell Hanford Operations

SOLID WASTE BURIAL RECORD - TRANSURANIC (73)

USE BLACK BALL POINT PEN OR TYPE

SWSOT RECORD NO. WARD-WEC-34-H 71

DISPOSAL SITE		This portion of form to be completed by Rockwell Representative at disposal site		ORIGINATOR Check One ☒ Combustible ☐ Non Combustible	
200 West		Burial Ground No. 218W-4C	Trench No. 4	End Function Shipment No. DOE Authorization No. 426-15	
Container No. —	Module No. 16	Beginning Coordinates 40070 N 77848	Company Westinghouse Electric Corp	Building Area	
		Ending Coordinates 40070 N 77824	Nuclear Fuel Div		
Remarks T-3+4 N-A5			Address Phone Cheswick Ave Cheswick PA 15024 412-963-5000		
Signature - Acceptance [Signature]		Date 10-10-83	I certify that no credit property is included in this burial unless duly marked by a Property Disposal Request, and described below, and that the contents meet RCMA 222 requirements and are packaged in Rockwell approved containers per RCMA 222.		
Signature - Storage Mode [Signature]		Date 12-14-84	[Signature] 9/16/85		
Accepted For SOW No. —			[Signature] 9/16/85		
PHYSICAL DESCRIPTION					
Material Contents 70.68" Wood 22.19% Paper 7.12% Metal					
I certify that the waste package description above is complete based on externally approved inspection system and that the waste package conforms to RCMA 222 and the approved authorization [Signature] 9/16/85					
Methods of inspection RCMA 222 Document RCMA NC10-24					

92.87 7.12

CONTAINER INFORMATION

SS 304		Accession Number 17125 R-1	Material of Construction Steel	Nuclear Classification No. XOT-VRA 32	Property Disposal Request No.
Length 7'	Width 6'	Height 6'	Diameter	Total Volume cu ft 227	Gross Weight 3615 Pounds
Container Number 426-15-2	Measurement Method Ge	Net Weight 306.7	TRU	Surface Data	Seal Numbers 6294
TOTALS 41 306.7 41 — — — — —					
General TRU or FAS Activity Data of 234, 235, 236, 238, 239, 240, 241, 242 Pa					

DISTRIBUTION SHIPPER White Yellow Pink } With Shipment
ROCKWELL White SWSOT, 27502
Yellow Nuclear Materials, 2704.2
Pink Return to Shipper

1657

SOLID WASTE BURIAL RECORD - TRANSURANIC

SWSOT RECORD NO WGRD-WEC-24-4973-T3

DISPOSAL SITE		This portion of form is to be completed by Rockwell Representative at Disposal site		ORIGINATOR Check One ☒ Combustible ☐ Non Combustible	
200-West		Burial Ground No. 218W-4C	French No. 4	End Function Shipment No. DOE Authorization No. IRRM 4244-16	
Cellar No. -	Module No. 16	Beginning Coordinates N 40070 W 77848		Company Weymann Electric Co-P Dubois Fuel Div	
		Ending Coordinates N 40070 W 77824		Building Area	
Remarks T-3+4 N-A5				Address-Phone Cheswick Ave Cheswick Pa 15024 412-963-5000	
Signature - Acceptance J. Clanton		Date 9-26-83		I certify that no capital property is included in this burial unless docu- mented by a Property Disclosure Request, and described below, and that the contents meet 40 C.F.R. 261.22 requirements and are packaged in Rockwell approved containers by RMO MA-222. <u>J. J. Shoultz</u> 9/23/83 Signature Date	
Signature - Storage Man J. Clanton		Date 2-14-84			
Accepted Per SOP No. TC-100-CSC					
PHYSICAL DESCRIPTION					
Material Contents 42.91 % Metal, 30.79 % Wood, 26.30 % Paper					
I certify that the waste package description below is complete based on a thoroughly approved inspection system and that the waste package com- forms to RMO MA-222 and the approved authorization. <u>J. J. Shoultz</u> 9/23/83 Signature Independent Reviewer Date Method of Report: RMO MA-222					

Vol % Combustible	Vol % Noncombustible	Toxic Hazardous Materials
97.09	42.91	—

CONTAINER INFORMATION

55 Gallon Drum	Approval Number 17125 R-1	Manufacturer's Construction SSK-1	Manufacturer's Product No. XDT-VRA #33	Product, Disposal Request No. —
Length ~7'	Width ~6'	Height ~6'	Total Volume 454	Gross Weight 7488 ³ / ₄ POUNDS Kilograms

Container Number	Measurement Method	Grams						Surface Dose (mrem/hr)	Seal Numbers	Type
		SI No.	U ²³⁸ / Pb-206	Pb-210	TRU	Curies	Microns			
72A266-16-1	Gc	41	51 0.7	41	—	—	—	<0.1	6296 6297	16-3W-4S
73A266-16-2	Gc	41	59 0.7	41	—	—	—	<0.1	6298 6299	16-3W-4S
TOTALS		41	110 0.7	41	—	—	—		Asse. Performed By J. L. Shaw/Htc	

21	110	0.7
----	-----	-----

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
DATE 08-01-2001 BY J.L. SHY/HRS

General TRU or Frigate Activity Desc of 234, 235, 236, 238 U 238 239 240, 241 242, P

ROCKWELL White SWSOT 27504
Yellow Nuclear Motors, 2706-2
RAB Return to Shooter

54-3000-423 (4-82)

54-3000-623 (4-62)

347 1663

Rockwell Hanford Operations

SOLID WASTE BURIAL RECORD - TRANSURANIC (73)

USE BLACK BALL POINT PEN OR TYPE

SWSOT RECORD NO. WAFR-WEC-24-106-107

DISPOSAL SITE		This portion of form is to be completed by Rockwell Representative at Disposal Site		ORIGINATOR		Check One ☒ Combustible ☐ Non Combustible	
200-West		218W-4C		Burial Ground No. 4		DOE Authorization No. 2266-20	
Container No.	Module No.	Beginning Coordinates		Company		Wesmag Nuclear Electric Corp	
-	16	N 40070 W 77848		Nuclear Fuel Division			
		Ending Coordinates		Building		Area	
		N 40070 W 77824					
Remarks		T-3+4 N-A5		Address		Cheswick, Pa 15024	
Signature - Acceptance		Date		Cheswick, Pa 15024		412-963-5000	
Signature - Storage Maint		Date		I certify that no capital property is included in this burial unless documented by a Property Disposal Request, and that the contents meet RMO MA 222 requirements and are packaged in Rockwell approved casks per RMO MA 222.		10/17/83	
Accepted for SOW No. TC-100				J. L. Shelders		Date	
PHYSICAL DESCRIPTION				I certify that the waste package description below is complete based on an approved inspection system and that the waste package conforms to RMO MA 222 and the approval authorization.			
Material Contents				10/17/83			
AS 36.4 Metal, 35.90% Wood, 274% Paper				Date			
				Method of Inspection See No. Disposal Rec. NCIC-27			

Combustible Non Combustible Toxic Hazardous Materials

56.4 43.36 227= 3798

CONTAINER INFORMATION

SS Class	Additional Number	Material of Construction	Nuclear Transaction No.	Property Disposal Request No.		
2-1	17125 R-1	Steel	XDT-URAF 36			
Height	Width	Weight	Total Volume	Gross Weight		
27'	26'	26'	454	7596 3 pounds		
Container Number	Measurement Method	Grams	TRU	Surface Contamination	Seal Numbers	Tag
200-20-1	GC	41 33 0.71	—	—	6387 6388	16-34-45
200-20-2	GC	41 26 0.71	—	—	6389 6390	16-34-45
TOTALS		41 53 0.1	—	—	Assay Performed By J. L. Shelders	
Cask No. TRU or Fission Act. or Decay Date 234, 235, 236, 238, 239, 240, 241, 242 R.						

DISTRIBUTION SHIPPER

White } With Shipment
Yellow }
Pink }
Goldened Retain

ROCKWELL

White SWSOT, 27508
Yellow Nuclear Materials, 2706-2
Pink Return to Shipper

342 1673

94-38864-23 (4421)

MODULE 17 (West coordinate 77902 to 77928)

Module 17 consists of 576 spaces for 55 gallon drums stacked in a 12 by 12 by 4 high configuration. Module 17 was built the last quarter of 1983 and the first quarter of 1984.

The 234-5Z Facility generated 477 drums of waste containing 1905 grams of plutonium, 369 drums had no measurable plutonium. The WARD (WEC) Facility generated 50 drums containing 87 grams of plutonium, and 259 grams of uranium. There were 17 drums that had Uranium and/or total beta/gamma recorded, but no plutonium. The 324 (PNL) Facility generated 3 drums containing 4.2 grams of plutonium. The 209E (PNL) Facility generated 10 drums containing 560 grams of plutonium. The 324 (WHC) Facility generated 20 drums containing 245 grams of plutonium, 10,604 grams of uranium, and 457 grams of thorium. The 202A (WHC) Facility generated 12 drums containing 56 grams of plutonium, 4 drums had only beta/gamma recorded (0.001 Ci each).

The Module totals include about 2860 grams of plutonium, 10,860 grams of uranium, and 460 grams of thorium. There were 387 drums that had no measurable plutonium. The highest plutonium loaded drum was 148.0 grams from the 209E Facility, located in position K-5, Tier 3. The maximum dose rate was 90 mrem/hr from a 209E drum. A WARD drum also had a dose rate of 80 mrem/hr.

The records show that three drums in this module from 234-5Z contain asbestos.

THIS PAGE INTENTIONALLY LEFT BLANK

TIER I

218W+0
Trend -

L K J I H G F E D C B A

2 3 4 5 6 7 8 9 10 11 12

TIER 2

8W40
5001-
0005

Rate

Rate

Rate

2 3 4 5 6 7 8 9 10 11 12

H G F E D C B A

L K

L K J I H G F E D C B A.

218W4C
Trend
Mod

55
56
57
58

2007

① $\text{Dose Rate} = \frac{1}{\text{Time}}$

2 3 4 5 6 7 8 9 10 11 12

WHC-SD-W113-ACDR-001
Rev. 0
Page 369

TIER 4

218W 4C
 Trench 1
 Module 1

1mR

Yellow # Dose Rate

3ms BU

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TRENCH

TRENCH 4 MODULE 18 TIER 2

TRENCH 4 MODULE 18 TIER 3

TRENCH 4 MODULE 18 TIER 4

DRUMS IRRADIATED FUEL WASTE

ESG

CANOGA PARK

WMC-SD-W113-ACDR-001
Rev. 0
Page 375A

THIS PAGE INTENTIONALLY LEFT BLANK

Rockwell Hanford Operations

SOLID WASTE BURIAL RECORD - TRANSURANIC 67T

USE BLACK BALL POINT PEN OR TYPE

SWSOT RECORD NO WDR-26 ESG-CHN-84-1-9

DISPOSAL SITE		This portion of form to be completed by Rockwell Representative at Disposal Site		ORIGINATOR Check One ☒ Combustible ☐ Non Combustible	
200-L		Burial Ground No. 4C Trench No. 4		Site Function Shipment No. DOE Authorization No. (RRM) 4672-15	
Container No. N/A	Module No. 18	Beginning Coordinates N 40070 W 77921		Company Energy Systems Group	
		Ending Coordinates N 40070 W 77947		Rockwell International	
Remarks		3 drums in module 19		Building T022	
Signature - Acceptance		Date 15-1-84		Address/Phone Santa Susana Test Site	
Signature - Storage Made		Date 1-20-84		Near Chatsworth, California	
Accepted Per SOP No. TC-100-030				818-700-4439, 5556	
PHYSICAL DESCRIPTION		I certify that no critical property is included in this burial unless documented by a Property Disposal Worksheet, and that the contents meet RMO MA 222 requirements and are packaged in Rockwell approved containers per RMO MA 222.			
Material Contents		Signature of Independent Reviewer Date 4/27/84			
Cardboard tubes with metal end caps,		I certify that the waste package description below is complete based on an internally approved inspection system and that the waste package conforms to RMO MA 222 and the approval authorization.			
electropolish hardware, lead and concrete		Signature of Independent Reviewer Date 4-27-84			
shielding.		Method of Inspection, File No			
Concrete (38%), lead (9%), Cardboard (36%), plastic (5%), metal (12%)					

91 % Combustible Vol % Noncombustible Toxic/Hazardous Materials
100 Lead

CONTAINER INFORMATION

55 Gallon Drum Approval Number: 284-1506 Material of Construction: steel, galvanized Nuclear Transaction No: N/A Property Disposal Request No: N/A
Length Width Height Diameter Total Volume (Ft³) 56.6 Gross Weight 6236 Pounds Kilograms

Container Number	Measurement Method	Grams					TRU U - Not Included		Surface Dose (mrem/hr)	Seal Numbers	Tier
		Pu	U	Enrichment	Fissile	TRU	Curies (Ci)	Isotopes			
15-1	Gamma scan	<1	—	—	—	<.001	0.31	MFP (Cs ¹³⁷)	22	N/A	10-1
15-2	3 NMM	<1	—	—	—	—	0.21	—	25	—	15-1
15-3	control	<1	—	—	—	—	0.35	—	25	—	15-1
15-4	records	<1	—	—	—	—	0.35	—	120	—	15-3
15-5	↓	<1	—	—	—	—	0.57	—	120	—	15-3
15-6	↓	<1	—	—	—	—	0.37	—	95	—	15-3
15-7	↓	<1	—	—	—	—	0.14	—	180	—	15-3
15-8	↓	<1	—	—	—	—	0.10	—	180	—	15-3
15-9	↓	<1	—	—	—	—	0.07	↓	140	↓	15-3
TOTALS		<1				<.001	2.47	Assay Performed By D. Harrison			
General TRU or Fissile Activity Description: Irradiated mixed oxides [(Pu - DU) O ₂] . Americium, MFP (Primarily Cs ¹³⁷ , Co ⁶⁰)											

General TRU or Fissile Activity Description: Irradiated mixed oxides [(Pu - DU) O₂], Americium, MFP (Primarily Cs¹³⁷, Co⁶⁰)

DISTRIBUTION: SHIPPER

White } With Shipment
Yellow }
Pink }
Gold/Red Return

ROCKWELL

White - SWSOT, 27518
Yellow - Nuclear Materials, 27042
Pink - Return to Shipper

WHC-SD-W113-ACDR-001
Rev. 0
Page 376A

THIS PAGE INTENTIONALLY LEFT BLANK

MODULE 18 (West coordinate 77928 to 77954)

Module 18 consists of 576 spaces for 55-gallon drums stacked in a 12 by 12 by 4 configuration. Module 18 was built April through August of 1984.

The 234-5Z (WHC) Facility generated 522 drums of waste containing 2947 grams of plutonium, 420 drums had no measurable plutonium. 202A (WHC) Facility generated 9 drums containing 361.4 grams of plutonium. The 324 (PNL) Facility generated 11 drums containing 24.1 grams of plutonium, 0.03 grams of americium, and 0.01 gram curium. One drum had no measurable plutonium. The 324 (WHC) Facility generated 27 drums containing 564.97 grams of plutonium, 9141.91 grams of uranium, and 731.9 grams of thorium. The ESG (CAN) Facility generated 6 drums containing 6.0 grams of plutonium.

The Module totals include 3900 grams of TRU, 9140 grams of uranium, and 730 grams of thorium. There were 421 drums that had no measurable plutonium. The highest plutonium loaded drum was 187.0 grams generated by 234-5Z Facility, it is located at position I9, Tier 4. There were six drum containing more than 100 grams of plutonium per container. The maximum dose rate was 180 mrem/hr on a drum from ESG (CAN), also another ESG drum had a recorded dose rate of 140 mrem/hr.

All six drums from ESG contain lead, with recorded weights of about 690 pounds each.

The records show one drum from 234-5Z contains asbestos.

THIS PAGE INTENTIONALLY LEFT BLANK

TIER 1

218W40
Trench

L K J I H G F E D C B A

2
3
4
5
6
7
8
9
10
11
12

Base Rate

TIER 2

218W4C
Trench 4
Module 18

mmR

Use Rate
1000 PU

2 3 4 5 6 7 8 9 10 11 12

L K J H G F E D C B A

TIER 3

218W4C

French 4

10/10/10

3014

B 3 1mR

Dose Rate

1000000

L K J I H G F E D C B A

1 2 3 4 5 6 7 8 9 10 11 12

TIER 4

218W4C
Trench
Module

L K J I H G F E D C B A

2 3 4 5 6 7 8 9 10 11 12

TRENCH 4 MODULE 18 TIER 1

TRENCH 4 MODULE 18 TIER 2

TRENCH 4 MODULE 18 TIER 4

DRUMS IRRADIATED FUEL WASTE

ESG

CANOGA PARK

THIS PAGE INTENTIONALLY LEFT BLANK

Rockwell Hanford Operations

SOLID WASTE BURIAL RECORD - TRANSURANIC 67 T

USE BLACK BALL POINT PEN OR TYPE

SWSOT RECORD NO: WDR-25 ESG-CHN-84-1-9

DISPOSAL SITE		This portion of form is to be completed by Rockwell Representative at Disposal Site		ORIGINATOR Check One ☒ Combustible ☐ Non Combustible							
Burial Ground No. 200-LW		Tranche No. 4C 4		SCE Authorization No. (ARM) 1679-15							
Container No. N/A	Module No. 18	Beginning Coordinates N 40070 W 77921		Company Energy Systems Group Rockwell International							
		Ending Coordinates N 40070 W 77947		Building T022							
Remarks None 3 drums in module 19				Address/Phone Santa Susana Test Site Near Chatsworth, California 818-700-4439, 5556							
Signature - Acceptance		Date 15-1-84		I certify that no control property is included in this burial unless documented by a Property Disposal Request, and that the contents meet RHO MA 222 requirements and are packaged in Rockwell approved containers per RHO MA 222.							
Signature - Storage Mode		Date 1-20-84		Signature of <i>[Signature]</i> Date 4/21/84							
Accepted Per SOP No. TC-100-030				I certify that the waste package description below is complete based on an internally approved inspection system and that the waste package conforms to RHO MA 222 and the approval authorization.							
PHYSICAL DESCRIPTION				Signature of <i>[Signature]</i> Date 4-27-84							
Material Contents:				Method of Inspection: File No							
Cardboard tubes with metal end caps, electropolish hardware, lead and concrete shielding.											
Concrete (38%), lead (9%), Cardboard (36%), plastic (5%), metal (12%)											
Of % Combustible		Vol % Noncombustible 100		Toxic/Hazardous Materials Lead							
CONTAINER INFORMATION											
55 Gallon Drum	Approval Number R84-1505	Material of Construction steel, galvanized		Nuclear Transaction No. N/A	Property Disposal Request No. N/A						
Length	Width	Height	Diameter	Total Volume (Ft ³) 66.6	Gross Weight 6236 ☒ Pounds ☐ Kilograms						
Container Number	Measurement Method	Grams					TRU U - Not Included		Surface Date (mm/dd/yy)	Seal Numbers	Tier
		Pu	U	Enrichment	Fissile	TRU	Curies (Ci)	Isotopes			
15-1	Gamma scan	<1	—	—	—	<.001	0.31	MFP (Cs ¹³⁷)	22	N/A	10-
15-2	3 NMM	<1	—	—	—	—	0.21	—	25	—	19-1
15-3	control	<1	—	—	—	—	0.35	—	25	—	19-1
15-4	records	<1	—	—	—	—	0.35	—	120	—	19-3
15-5	—	<1	—	—	—	—	0.57	—	120	—	19-3
15-6	—	<1	—	—	—	—	0.37	—	95	—	19-3
15-7	—	<1	—	—	—	—	0.14	—	180	—	19-3
15-8	—	<1	—	—	—	—	0.10	—	180	—	19-3
15-9	—	<1	—	—	—	—	0.07	—	140	—	19-3
TOTALS		<1	—	—	—	<.001	2.47	—	Assay Performed By D. Harrison		
General TRU or Fissile Activity Description: Irradiated mixed oxides [(Pu - DU) O ₂], Americium, MFP (Primarily Cs ¹³⁷ , Co ⁶⁰)											

DISTRIBUTION: SHIPPER
White } With Shipment
Yellow }
Pink }
Goldened Retain

ROCKWELL
White - SWSOT, 27518
Yellow - Nuclear Materials, 2704-Z
Pink - Return to Shipper

54-3000-423 (4-82)

WHC-SD-W113-ACDR-001
Rev. 0
Page 387A

THIS PAGE INTENTIONALLY LEFT BLANK

MODULE 19 (West coordinate 77954 to 77966)

Module 19 consists of an incomplete module of 289 galvanized 55-gallon galvanized drums nominally stacked in a 12 by 5 by 4 high configuration. Module 19 was built from August through November of 1984 with four drums placed in March of 1985. This is the westernmost module (half module) and will be the first retrieved.

The 234-SZ Facility generated 285 drums of waste containing 179.0 grams of plutonium, 223 of the drums had no measurable plutonium. The ESG (CAN) Facility generated 3 drums with 3.0 grams of plutonium. The 324 (WHC) Facility generated 1 drum with 128 grams of plutonium and 420 grams of uranium.

The Module totals include 310 grams of plutonium and 420 grams of uranium for the half module. There were 223 drums that had no measurable plutonium. The highest plutonium loaded drum was 127.9 grams from the 324 (WHC) Facility and was located in position E4 of Tier 4. The maximum dose rate recorded was 25 mrem/hr from two ESG drums, the third ESG drum was 23 mrem/hr.

The three drums from ESG each contain lead and weigh about 690 lb each.

WMC-SD-W113-ACDR-001

Rev. 0

Page ~~388A~~

THIS PAGE INTENTIONALLY LEFT BLANK

TIER 1

218W4C
Tender

FEDCBA

2 3 4 5 6 7 8 9 10 11 12

TIER 2

FEDCBA

218W4C

rendh 4
Module 19

data

$\mu \leq 1mR$

$\mu = \text{Dose Rate}$

PU

1 2 3 4 5 6 7 8 9 10 11 12

TIER 3

218W4C
Trench 4

FEDCBA

MR

Base Rate

1 2 3 4 5 6 7 8 9 10 11 12

TIER 4

F E D C B A

218W4C

Trench 4

Module 4

218W4C Dose Rate

218W4C Pu

1
2
3
4
5
6
7
8
9
10
11
12

TRENCH 4 MODULE 19 TIER 1

TRENCH 4 MODULE 19 TIER 2

TRENCH 4 MODULE 19 TIER 3

TRENCH 4 MODULE 19 TIER 4

REFERENCES

- WHC-EP-0621 *Characterization of Past and Present Solid Waste Streams from the Plutonium Finishing Plant* D. R. Duncan, B.A. Mayancsik; Westinghouse Hanford Company. J.A. Pottmeyer, E.J. Vevoda, J.A. Reddick, K.M. Sheldon, M.I. Weyens; Los Alamos Technical Associates: February 1993
- WHC-EP-0646 *Characterization of Past and Present Solid Waste Streams from the Plutonium-Uranium Extraction Plant* J.A. Pottmeyer, M.I. Weyns, D.S. Lorenzo, E.J. Vevoda; Los Alamos Technical Associates, Incorporated. D.R. Duncan, Westinghouse Hanford Company: April 1993
- WHC-EP-0659 *Characterization of Past and Present Solid Waste Streams from 231-Z* J.A. Pottmeyer, D.S. Delorenzo, M.I. Weyns-Rollosen, D.E. Berkwitz, E.J. Vevoda; Los Alamos Technical Associates, Incorporated. D.R. Duncan, Westinghouse Hanford Company: June 1993
- 87320-93-EPM-020 *Characterization of Past and Present Solid Waste Streams from General Electric-Vallecitos Nuclear Center* Los Alamos Technical Associates, REVIEW DRAFT May 1993
- 87320-93-EPM-030 *Characterization of Past and Present Solid Waste Streams from the 325 Radiochemistry Building* Los Alamos Technical Associates, REVIEW DRAFT June 1993
- R-SWIMS (Richland Solid Waste Information and Management System) Retrievably Stored TRU Data Base Report for Burial Ground 4C Trench 04 dated 9/22/88
- SWITS (Solid Waste Information and Tracking System)
- SD-CP-TI-105 REV 1 *ORIGEN-II Calculations of N Fuel*
- MICROSHIELD for Westinghouse Hanford Company Serial, 197

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX A

TRU GRAM QUANTITY RANGES
BY MODULES

THIS PAGE INTENTIONALLY LEFT BLANK

213W4C TRENCH 04
MODULE 1

RL Range grams	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	421	51.540	51.540
$>.0001$ to $\leq .001$	13	1.903	53.543
$>.001$ to $\leq .01$	35	5.124	58.667
$>.01$ to $\leq .1$	1	.146	58.813
$>.1$ to ≤ 1.0	85	12.445	81.258
>1.0 to ≤ 10.0	59	8.638	89.896
>10.0 to ≤ 25	38	5.564	95.460
>25 to ≤ 50	21	3.075	98.535
>50 to ≤ 75	3	1.171	99.706
>75 to ≤ 100	1	.146	99.852
>100 to ≤ 125	1	.146	99.998
>125 to ≤ 150	0	0	
>150 to ≤ 175	0	0	
>175 to ≤ 200	0	0	
>200 to ≤ 225	0	0	
Totals	583	100.0	

Maximum container = 104.2 grams
Bin-weighted average = 4.2 grams
95% (i.e., only 5% of containers exceed this value, = <25 grams
Onsite Receptor = 100 m east

218W4C TRENCH 04
MODULE 2

TRU Range grams	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	375	55.119	55.119
$>.0001$ to $\leq .001$	1	.149	55.268
$>.001$ to $\leq .01$	18	2.687	58.955
$>.01$ to $\leq .1$	1	.149	59.104
$>.1$ to ≤ 1.0	126	18.806	77.910
>1.0 to ≤ 10.0	106	15.821	93.731
>10.0 to ≤ 25	22	3.293	97.014
>25 to ≤ 50	13	1.940	98.954
>50 to ≤ 75	1	.149	99.103
>75 to ≤ 100	1	.149	99.252
>100 to ≤ 125	1	.149	99.401
>125 to ≤ 150	3	.448	99.849
>150 to ≤ 175	0	0	99.849
>175 to ≤ 200	1	.149	99.998
>200 to ≤ 225	0	0	
Totals	670		

Maximum container = 179 grams
Bin-weighted average = 5.0 grams
95% (i.e., only 5% of containers exceed this value) = <25 grams
Onsite receptor = 108.2 m east

218W4C TRENCH 04
MODULE 3

Weight Range (grams)	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	39	69.772	69.772
$>.0001$ to $\leq .001$	1	.176	69.948
$>.001$ to $\leq .01$	12	2.109	72.057
$>.01$ to $\leq .1$	0	0	72.057
$>.1$ to ≤ 1.0	37	6.503	78.560
>1.0 to ≤ 10.0	55	9.666	88.226
>10.0 to ≤ 25	18	3.163	91.389
>25 to ≤ 50	19	3.339	94.728
>50 to ≤ 75	6	1.054	95.782
>75 to ≤ 100	3	.527	96.309
>100 to ≤ 125	3	.527	96.836
>125 to ≤ 150	5	.879	97.715
>150 to ≤ 175	1	.176	97.891
>175 to ≤ 200	12	2.109	100.000
>200 to ≤ 225	0		
Totals	569		

Maximum container = 189 grams

Bin-weighted average = 11.3 grams

95% (i.e., only 5% of containers exceed this value) = 52.35 grams

Onsite receptor = 116.5 m east

218W4C TRENCH 04
MODULE 4

RL Range (grams)	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	219	44.377	44.377
$>.0001$ to $\leq .001$	1	.205	45.082
$>.001$ to $\leq .01$	74	15.164	60.246
$>.01$ to $\leq .1$	0	0	60.246
$>.1$ to ≤ 1.0	50	10.246	70.492
>1.0 to ≤ 10.0	78	15.984	86.476
>10.0 to ≤ 25	32	6.557	93.033
>25 to ≤ 50	11	2.225	95.258
>50 to ≤ 75	15	3.071	98.332
>75 to ≤ 100	5	1.229	99.561
>100 to ≤ 125	1	.205	99.766
>125 to ≤ 150	1	.205	99.971
>150 to ≤ 175	0		
>175 to ≤ 200	0		
>200 to ≤ 225	0		
Totals	488		

Maximum container = 150 grams

Bin-weighted average = 3.6 grams

95% (i.e., only 5% of containers exceed this value) = <50 grams

Onsite receptor = 124.7 m east

AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

6 of 8

218W4C TRENCH 04
MODULE 5

TRU Range (grams)	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	321	59.007	59.007
$>.0001$ to $\leq .001$	0	0	59.007
$>.001$ to $\leq .01$	0	0	59.007
$>.01$ to $\leq .1$	7	1.287	60.294
$>.1$ to ≤ 1.0	27	4.963	65.257
>1.0 to ≤ 10.0	68	12.500	77.757
>10.0 to ≤ 25	17	3.125	80.882
>25 to ≤ 50	14	2.573	83.455
>50 to ≤ 75	8	1.471	84.926
>75 to ≤ 100	10	1.838	86.764
>100 to ≤ 125	7	1.287	88.051
>125 to ≤ 150	5	.919	88.970
>150 to ≤ 175	36	6.613	95.583
>175 to ≤ 200	24	4.412	100.000
>200 to ≤ 225	0		
Totals	544		

Maximum container = 198 grams

Bin-weighted average = 29.7 grams

95% (i.e., only 5% of containers exceed this value) = 173 grams

Onsite receptor = 132.9 m east

218W4C TRENCH 04
MODULE 5

TRU Range grams	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	391	75.969	75.969
$>.0001$ to $\leq .001$	0	0	75.969
$>.001$ to $\leq .01$	12	2.362	79.331
$>.01$ to $\leq .1$	24	4.724	84.055
$>.1$ to ≤ 1.0	41	8.071	92.126
>1.0 to ≤ 10.0	24	4.724	96.850
>10.0 to ≤ 25	11	2.165	99.015
>25 to ≤ 50	3	.591	99.606
>50 to ≤ 75	1	.197	99.803
>75 to ≤ 100	1	.197	100.000
>100 to ≤ 125	0		
>125 to ≤ 150	0		
>150 to ≤ 175	0		
>175 to ≤ 200	0		
>200 to ≤ 225	0		
Totals	508		

Maximum container = 94.29 grams
Bin-weighted average = 1.7 grams
95% (i.e., only 5% of containers exceed this value) = <10 grams
Onsite receptor = 140.3 m east

213W4C TRENCH 04
MODULE 7

TRU Range grams	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	314	54.789	54.779
$>.0001$ to $\leq .001$	0	0	54.779
$>.001$ to $\leq .01$	3	.524	55.323
$>.01$ to $\leq .1$	0	0	55.323
$>.1$ to ≤ 1.0	37	6.457	61.780
>1.0 to ≤ 10.0	47	8.202	69.982
>10.0 to ≤ 25	21	3.665	73.647
>25 to ≤ 50	44	7.679	81.326
>50 to ≤ 75	30	5.236	86.562
>75 to ≤ 100	15	2.613	89.180
>100 to ≤ 125	14	2.493	91.623
>125 to ≤ 150	18	3.141	94.764
>150 to ≤ 175	17	2.967	97.731
>175 to ≤ 200	11	1.920	99.651
>200 to ≤ 225	2	.349	100.000
Totals	573		

Maximum container = 219 grams

Bin-weighted average = 29.3 grams

95% (i.e., only 5% of containers exceed this value) = 154 grams

Onsite receptor = 148.3 m east

218W4C TRENCH 04
MODULE 3

TRU Range grams	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	162	30.740	30.740
$>.0001$ to $\leq .001$	0	0	30.740
$>.001$ to $\leq .01$	0	0	30.740
$>.01$ to $\leq .1$	0	0	30.740
$>.1$ to ≤ 1.0	21	3.985	34.725
>1.0 to ≤ 10.0	48	9.108	43.833
>10.0 to ≤ 25	42	7.970	51.803
>25 to ≤ 50	90	17.073	68.881
>50 to ≤ 75	49	9.298	78.179
>75 to ≤ 100	33	6.292	84.441
>100 to ≤ 125	25	4.744	89.185
>125 to ≤ 150	20	3.795	92.980
>150 to ≤ 175	20	3.795	96.775
>175 to ≤ 200	17	3.226	100.001
>200 to ≤ 225	0		
Totals	527		

Maximum container = 199 grams

Bin-weighted average = 49.4 grams

95% (i.e., only 5% of containers exceed this value) = 163 grams

Onsite receptor = 156.7 m east

Arithmetic average = 42.7 grams

213W4C TRENCH 04
MODULE 9

TRU Range grams	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	355	53.290	53.290
$>.0001$ to $\leq .001$	0	0	53.290
$>.001$ to $\leq .01$	1	.178	53.458
$>.01$ to $\leq .1$	0	0	53.458
$>.1$ to ≤ 1.0	52	9.269	72.727
>1.0 to ≤ 10.0	68	12.121	84.848
>10.0 to ≤ 25	17	3.030	87.878
>25 to ≤ 50	17	3.030	90.908
>50 to ≤ 75	10	1.733	92.691
>75 to ≤ 100	13	2.317	95.008
>100 to ≤ 125	7	1.248	96.256
>125 to ≤ 150	7	1.248	97.504
>150 to ≤ 175	10	1.783	99.287
>175 to ≤ 200	1	.713	100.000
>200 to ≤ 225	0		
Totals	561		

Maximum container = 197 grams

Bin-weighted average = 15.2 grams

95% (i.e., only 5% of containers exceed this value) = 100 grams

Onsite receptor = 164.6 m east

218W4C TRENCH 04
MODULE 10

Weight Range (grams)	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	134	35.317	35.317
$>.0001$ to $\leq .001$	0	0	35.317
$>.001$ to $\leq .01$	2	.384	35.701
$>.01$ to $\leq .1$	10	1.919	37.620
$>.1$ to ≤ 1.0	57	10.940	48.560
>1.0 to ≤ 10.0	89	17.083	65.643
>10.0 to ≤ 25	148	28.407	94.050
>25 to ≤ 50	3	.576	94.626
>50 to ≤ 75	0	0	94.626
>75 to ≤ 100	4	.768	95.394
>100 to ≤ 125	3	.576	95.970
>125 to ≤ 150	7	1.341	97.314
>150 to ≤ 175	3	.536	98.850
>175 to ≤ 200	6	1.152	100.002
>200 to ≤ 225	0		
Totals	321		

Maximum container = 193 grams

Bin-weighted average = 17.7 grams

95% (i.e., only 5% of containers exceed this value) = <100 grams

Onsite receptor = 172.5 m east

218W4C TRENCH 04
MODULE 11

TC Range grams	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	134	25.475	25.475
$>.0001$ to $\leq .001$	0	0	25.475
$>.001$ to $\leq .01$	0	0	25.475
$>.01$ to $\leq .1$	3	.570	26.045
$>.1$ to ≤ 1.0	30	5.703	31.748
>1.0 to ≤ 10.0	100	19.011	50.759
>10.0 to ≤ 25	245	46.578	97.337
>25 to ≤ 50	10	1.901	99.238
>50 to ≤ 75	1	.190	99.428
>75 to ≤ 100	2	.380	99.808
>100 to ≤ 125	0	0	99.808
>125 to ≤ 150	1	.190	99.988
>150 to ≤ 175	0	0	
>175 to ≤ 200	0	0	
>200 to ≤ 225	0		
Totals	526		

Maximum container = 140 grams

Bin-weighted average = 15.4 grams

95% (i.e., only 5% of containers exceed this value) = <25 grams

Onsite receptor = 180.5 m east

218W4C TRENCH 04
MODULE 12

TRU Range (grams)	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	127	48.473	48.473
$>.0001$ to $\leq .001$	0	0	48.473
$>.001$ to $\leq .01$	9	3.435	51.908
$>.01$ to $\leq .1$	4	1.527	53.435
$>.1$ to ≤ 1.0	20	7.634	61.067
>1.0 to ≤ 10.0	28	10.687	71.756
>10.0 to ≤ 25	64	24.427	96.183
>25 to ≤ 50	3	1.145	97.328
>50 to ≤ 75	3	1.145	98.473
>75 to ≤ 100	1	1.527	100.000
>100 to ≤ 125	0		
>125 to ≤ 150	0		
>150 to ≤ 175	0		
>175 to ≤ 200	0		
>200 to ≤ 225	0		
Totals	262		

Maximum container = 83 grams

Bin-weighted average = 10.2 grams

95% (i.e., only 5% of containers exceed this value) = <25 grams

Onsite receptor = 188.4 m east

218W4C TRENCH 04
MODULE 13

TRU Range (grams)	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	165	31.309	31.309
$>.0001$ to $\leq .001$	75	14.231	45.540
$>.001$ to $\leq .01$	63	11.954	57.494
$>.01$ to $\leq .1$	16	3.036	60.530
$>.1$ to ≤ 1.0	104	19.734	80.264
>1.0 to ≤ 10.0	71	13.472	93.736
>10.0 to ≤ 25	27	5.123	98.859
>25 to ≤ 50	1	.759	99.618
>50 to ≤ 75	1	.190	99.808
>75 to ≤ 100	1	.190	99.998
>100 to ≤ 125	0		
>125 to ≤ 150	0		
>150 to ≤ 175	0		
>175 to ≤ 200	0		
>200 to ≤ 225	0		
Totals	527		

Maximum container = 75 grams

Bin-weighted average = 3.5 grams

95% i.e., only 5% of containers exceed this value = ≤ 25 grams

Onsite receptor = 196.3 m east

218W4C TRENCH 04
MODULE 15

Weight Range (grams)	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	173	43.173	43.173
$>.0001$ to $\leq .001$	97	24.619	69.792
$>.001$ to $\leq .01$	3	.761	70.553
$>.01$ to $\leq .1$	6	1.523	72.076
$>.1$ to ≤ 1.0	31	7.868	79.944
>1.0 to ≤ 10.0	47	11.929	91.873
>10.0 to ≤ 25	8	2.030	93.903
>25 to ≤ 50	15	3.807	97.710
>50 to ≤ 75	5	1.269	98.979
>75 to ≤ 100	2	.508	99.487
>100 to ≤ 125	1	.254	99.741
>125 to ≤ 150	1	.254	100.000
>150 to ≤ 175	0		
>175 to ≤ 200	0		
>200 to ≤ 225	0		
Totals	394		

Maximum container = 146 grams
Bin-weighted average = 5.3 grams
95% (i.e., only 5% of containers exceed this value) = <50 grams
Onsite receptor = 212.2 m east

218W4C TRENCH 04
MODULE 16

TRU Range grams	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	0	0	0
$>.0001$ to $\leq .001$	206	66.238	66.238
$>.001$ to $\leq .01$	0	0	66.238
$>.01$ to $\leq .1$	3	.965	67.203
$>.1$ to ≤ 1.0	62	19.936	87.139
>1.0 to ≤ 10.0	23	7.395	94.534
>10.0 to ≤ 25	9	2.894	97.428
>25 to ≤ 50	6	1.929	99.357
>50 to ≤ 75	1	.322	99.679
>75 to ≤ 100	1	.322	100.001
>100 to ≤ 125	0		
>125 to ≤ 150	0		
>150 to ≤ 175	0		
>175 to ≤ 200	0		
>200 to ≤ 225	0		
Totals	311		

Maximum container = 77 grams

Bin-weighted average = 3.2 grams

95% (i.e., only 5% of containers exceed this value) = <10 grams

Onsite receptor = 220.1 m east

218W4C TRENCH 04
MODULE 17

TRU Range (grams)	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	0	0	0
$>.0001$ to $\leq .001$	375	68.307	68.307
$>.001$ to $\leq .01$	0	0	68.307
$>.01$ to $\leq .1$	0	0	68.307
$>.1$ to ≤ 1.0	59	10.825	79.633
>1.0 to ≤ 10.0	43	7.890	87.523
>10.0 to ≤ 25	35	6.422	93.945
>25 to ≤ 50	19	3.486	97.431
>50 to ≤ 75	6	1.101	98.532
>75 to ≤ 100	3	.550	99.082
>100 to ≤ 125	3	.550	99.632
>125 to ≤ 150	1	.183	99.815
>150 to ≤ 175	1	.183	99.998
>175 to ≤ 200	0		
>200 to ≤ 225	0		
Totals	545		

Maximum container = 165 grams
Bin-weighted average = 5.9 grams
95% M.E., only 5% of containers exceed this value = <50 grams
Onsite receptor = 228.0 m east

219W4C TRENCH 04
MODULE 18

TRU Range grams	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	0	0	0
$>.0001$ to $\leq .001$	426	74.087	74.087
$>.001$ to $\leq .01$	1	.174	74.261
$>.01$ to $\leq .1$	5	.870	75.131
$>.1$ to ≤ 1.0	37	6.435	81.566
>1.0 to ≤ 10.0	49	8.522	90.088
>10.0 to ≤ 25	10	1.739	91.827
>25 to ≤ 50	12	2.087	93.914
>50 to ≤ 75	15	2.609	96.523
>75 to ≤ 100	8	1.391	97.914
>100 to ≤ 125	9	1.565	99.479
>125 to ≤ 150	0	0	99.479
>150 to ≤ 175	2	.348	99.827
>175 to ≤ 200	1	.174	100.001
>200 to ≤ 225	0		
Totals	575		

Maximum container = 187 grams

Bin-weighted average = 3.7 grams

95% (i.e., only 5% of containers exceed this value) = <75 grams

Onsite receptor = 235.9 m east

218W4C TRENCH 04
MODULE 19

TRU Range (grams)	No. of Containers	Percent of Containers	Cumulative percentage of containers
$\leq .0001$	0	0	0
$>.0001$ to $\leq .001$	223	76.897	76.897
$>.001$ to $\leq .01$	0	0	76.897
$>.01$ to $\leq .1$	0	0	76.897
$>.1$ to ≤ 1.0	51	17.586	94.483
>1.0 to ≤ 10.0	13	4.483	98.966
>10.0 to ≤ 25	0	0	98.966
>25 to ≤ 50	2	.690	99.656
>50 to ≤ 75	0	0	99.656
>75 to ≤ 100	0	0	99.656
>100 to ≤ 125	0	0	99.656
>125 to ≤ 150	1	.345	100.001
>150 to ≤ 175	0		
>175 to ≤ 200	0		
>200 to ≤ 225	0		
Totals	290		

Maximum container = 127.9 grams

Bin-weighted average = 1.5 grams

95% (i.e., only 5% of containers exceed this value) = 410 grams

Onsite receptor = 244.9 m east

APPENDIX B

MISCELLANEOUS SUPPORTING INFORMATION

THIS PAGE INTENTIONALLY LEFT BLANK

FROM: Waste Forms Application
PHONE: 6-1778
DATE: August 12, 1993
SUBJECT: Updater: Burial Ground 40 Trench 4. Container location verifications

TO: D.R. Duncan H5-33

cc: W.O. Greenalgh H5-31
D.M. Johnson H5-33
M.L. Sheriff H5-31

Per your request a review was made of the current container locations, as entered in the SWITS data base, to try and correct any location deficiencies in the data base. The information was reviewed and the findings are attached to this letter. The following is a brief summary of recommendations to correct the deficiencies found.

Section 1: No records can be found in SWITS for these containers. No action at this time. A further investigation of these locations should be done after all the corrections listed in other sections have been completed.

Section 2: The entries in Section 2 include locations which were entered incorrectly or not entered at all. The correct locations are listed and should be entered into the SWITS data base.

3/12/93 Note: Corrections have been made to the SWITS database to correct or enter the data listed in Section 2.

Section 3: These containers have multiple entries on the field sheets or the data base or both. Further evaluations will have to be made on how to handle these entries.

Section 4: These containers currently have no complete location entry in SWITS. However SWITS data indicates they are in Trench 1 not Trench 4. The field location sheets indicate that these containers are in Trench 4 and at the locations listed in Section 4. A decision must be made on which set of data is most likely to be correct. If the field sheets are considered correct then the listed locations and corrected Trench number need to be entered into SWITS. If the current Trench location is deemed correct, then no further action is needed at this time.

Section 5: These container PIN's were incorrectly identified when the summary sheets for the burial records were made up. This information is what was originally entered into the RSWIMS records and later transferred to the SWITS data base. A search of the records revealed what should have been the correct PIN's and these are identified in section 5. Because these numbers show up in both the SWITS data and on the microfilmed records a decision needs to be made on which to use. The locations need to be entered no matter which set of numbers it is decided to use.

3/12/93 Note: Corrections have been made to the SWITS database to correct the errors noted in Section 5.

Section 6: This section contains locations at which either no entry was made on the field location sheets or the entry was incorrect and could not be interpreted correctly. No action at this time is required.

Section 7: The field location sheet for the locations shown in Section 7 have 2 PIN's at each location. Discussion may be required to decide actions for these containers.

If you have any questions please contact me on 6-1778.

John W. Biglin

2-25-93

BURIAL GROUND 4C TRENCH 4
DRUM LOCATION VERIFICATION

Section 1: The drum positions noted in this section consist of those positions which on the field location sheets give a PIN # for a drum. However no records for these drums can be found in the SWITS database. The PIN numbers were manipulated into various combinations in an attempt to locate the records but the attempt was unsuccessful.

The problem in determining the correct PIN as entered into the SWITS database is a result of the methods used when first collecting the data for entry into the database. The numbers on the field sheets were apparently taken from the drums or the original paperwork when they were put into the trench. The numbers as entered into the database were taken off the paperwork at a later date. The person entering the data was limited at that time to a nine character field and therefore had to be creative in entering a PIN # which would reflect the proper identification. Also as there was no preset identifier for each of the generators, the data entry clerk (or their supervisor) had to use whatever was on the paperwork, whether it properly identified the generator or not.

Another problem with locating unknown PIN's is that the data base is locked in as to the position of any character in the PIN, no matter what it is. Example: Z78-A3365, Z78A-3365, A3365, Z78A3365 are all different ways a single PIN might have been entered into the database. To search the SWITS data base all of the above combinations have to be searched out. A search was made using the wild card notations to try and locate any combinations which might be used.

The PIN's shown in the following table were taken off the field sheets, and a search made of the SWITS data base failed to locate any records which could be checked to compare against. The location shown is where the field sheet shows that drum to be.

The following is an explanation of the status table abbreviations:

- (x) EOFLS - x number of entries appear on the Field Locate Sheets (FLS)
- (x) EODS - x number of entries on SWIMS data sheets
- NEODS - No entry found on the SWIMS data sheets
- SHBE - Data should have been entered but was not
- *ERROR - Error in data entry

<u>PIN #</u>	<u>RECORD #</u>	<u>STATUS</u>
Z78-A3348		M1 T2 L2 NEODS
Z78-A3898		M2 T1 D1 NEODS
BNW78-63		M2 T1 G2 NEODS
BN78-30		M2 T2 G9 NEODS
BN78-32		M2 T2 I10 NEODS
Z79-A4735	790792	M2 T4 K4 FLS has no entry for this location. Location data for this PIN should be deleted.

<u>PIN #</u>	<u>RECORD #</u>	<u>STATUS</u>
WH78-270	325 / 790030	ERROR IN DATA ENTRY CORRECT LOCATION UNKNOWN DELETE CURRENT LOCATION DATA.
RS-79-1-3		ERROR NEODS. DELETE CURRENT LOCATION DATA.
RS-79-90		M3 T3 D10 NEODS
Z79-A7561		M3 T4 D12 NEODS
Z79-A7542		M3 T4 K2 NEODS
BN78-H81		M4 T1 A1
BN78-H70		M4 T1 A3
BN78-H90		M4 T1 A4
BN78-H204		M4 T1 A5
BN78-H84		M4 T1 A6
BN78-H64		M4 T1 A9
BN78-H55		M4 T1 A10
BN78-H74		M4 T1 A12
BN78-H59		M4 T1 B1
BN78-H94		M4 T1 B2
BN78-H67		M4 T1 B3
BN78-H223		M4 T1 B4
BN78-H234		M4 T1 B5
BN78-H66		M4 T1 C4
BN78-H224		M4 T1 C5
BN78-H69		M4 T1 C6
BN78-H121		M4 T1 C7
BN78-H51		M4 T1 C8
BN78-H85		M4 T1 C9
BN78-H205		M4 T1 D10
BN78-H41		M4 T1 D11
BN78-H76		M4 T1 D10
BN78-H201		M4 T1 D11
BN78-H194		M4 T1 D12
BN78-35		M4 T1 F3 NEODS
Z-77-13		M4 T1 K6 NEODS
Z3-78-4		M4 T2 F1 NEODS
Z3-78-3		M4 T2 F2 NEODS
Z77-A5206		M4 T2 H5 NEODS
BN78-H911		M4 T2 L1 NEODS
Z12-77-1		M4 T2 K2 NEODS
Z78-A4064		M4 T3 E10 NEODS
BNW-H001		M4 T3 F7 NEODS
BNW-H46		M4 T3 G12 NEODS
WH78-189		M4 T4 E9 NEODS
Z79-A7414		M4 T4 J4 NEODS
BN79-444		M5 T4 C4 NEODS
BN79-487.B	325 / 790143	M5 T4 H7 DELETE DATA
BN79-486		M5 T4 H7 NEODS
WH79-259.A	325 / 790348	M5 T4 I4 DELETE DATA
WH79-257		M5 T4 I4 NEODS
WH79-279		M5 T4 J4 NEOD

PIN #	RECORD #	STATUS
19-5-3	2311	M6 T4 13
19-5-3	2311	M6 T1 15
19-5-2	2311	M6 T1 11
19-5-17	2311	M6 T1 13
Z79A-5888		M7 T1 D10 NEEDS
ANL-246B		M9 T1 E7 NEEDS
ARD80-013		M9 T2 H1 NEEDS
ARD80A103		M10 T2 L9 NEEDS
79731901A	2345Z / 810354	M10 T2 L1
231Z-9-81-1		M10 T4 K12 NEEDS
231Z-3-81-2		M10 T4 L12 NEEDS
WH81-976		M11 T1 E3 NEEDS
3536-7-90		M11 T1 L1 NEEDS
????		M14 T2 L3 12-79-2 111
Z83A-9694		M16 T4 A5 NEEDS
Z84A10150		M17 T2 E1 NEEDS
Z84A10148		M17 T2 E7 NEEDS
Z84A10151		M17 T2 F9 NEEDS
Z84A10149		M17 T2 G10 NEEDS

Section 2 : The PIN's and locations listed in this section were either not entered for some unknown reason or had some part of thier location entry entered wrong. The locations for these PIN's need to be entered or corrected on the SWITS database.

<u>PIN =</u>	<u>RECORD =</u>	<u>STATUS</u>
Z78-A3458		M1 T3 E9 *ERROR
Z78-A3461		M1 T3 F1 SHBE
Z78-A3679		M1 T4 I2 SHBE
Z78-A3681		M1 T4 J6 SHBE
Z78-A3682		M1 T4 J7 SHBE
Z78-A3683		M1 T4 J8 SHBE
Z78-A3684		M1 T4 J9 SHBE
Z78-A3685		M1 T4 J10 SHBE
Z78-A3686		M1 T4 J11 SHBE
Z78-A3687		M1 T4 J12 SHBE
Z78-A3688		M1 T4 K1 SHBE
Z78-A3689		M1 T4 K2 SHBE
Z78-A3690		M1 T4 K3 SHBE
Z78-A3691		M1 T4 K4 SHBE
Z78-A3692		M1 T4 K5 SHBE
Z78-A3693		M1 T4 K6 SHBE
WH-H97		M2 T1 G11 *ERROR
WH-H302		M2 T1 G12 *ERROR
Z78-A4027		M2 T2 L9 *ERROR
BN78-332		M2 T3 J3 SHBE
WH78-968		M2 T5 F4
WH78-332		M2 T5 K1 *ERROR
11-78-5		M3 T1 F5 *ERROR
BN78-365		M3 T1 K3 *ERROR
BN78-366		M3 T1 K12 *ERROR
Z79-A4940		M3 T1 B6 *ERROR
Z79-A4941		M3 T1 B5 *ERROR
WH79-189		M3 T1 T11 *ERROR
202A-18		M4 T1 F5 *ERROR
202A-17.A		M4 T1 B6 *ERROR
WH-H345		M4 T1 F3 SHBE
Z1-78-12		M4 T2 B2 *ERROR
Z1-78-10		M4 T2 B9 *ERROR
Z79-A4888		M4 T3 F10 *ERROR
Z79-A3900		M4 T3 H4 *ERROR
Z79-A4793		M4 T4 J6 SHBE
Z79-A7553		M5 T1 L6 *ERROR
Z79-A7563	790821/790337	M5 T2 A8 2 RECORD ENTRIES
Z-A4853-1		M5 T2 D8 SHBE
Z-A4853-2		M5 T2 D10 SHBE
Z79-A5144		M5 T2 K11 *ERROR
D79-6-A14		M5 T4 C12

<u>PIN #</u>	<u>RECORD #</u>	<u>STATUS</u>
179-46425	M6 T1 17	*ERROR
179-46425	M6 T1 19	*ERROR
130A-6000	M7 T1 11	*ERROR
Z80A-6130	M7 T3 09	*ERROR
1172-6578	M9 T1 J7	*ERROR
Z80A-6928	M9 T2 E3	*ERROR
Z80A-7199	M9 T2 H9	DELETE DATA SEE Z80A-7177
Z80A-7177	M9 T2 H9	CORRECTION
Z80A-7019	M9 T3 A12	*ERROR
Z80A-7028	M9 T3 E1	*ERROR
WH81-448	M9 T3 E4	*ERROR
Z80A-7018.B	M9 T3 F11	*ERROR
Z80A-6972	M9 T3 I2	*ERROR
Z80A-7044	M9 T3 L3	SHBE
Z81A-7955	M9 T4 14	*ERROR
0-1132	M10 T1 G3	*ERROR
1175	M10 T1 L7	(RRM 3597-1 71 310070)
1174	M10 T1 L9	(RRM 3597-1 70)
1177	M10 T2 A12	(RRM 3597-2 72)
1182	M10 T2 B10	(RRM 3597-2 75)
1179	M10 T2 09	(RRM 3597-2 73)
1180	M10 T2 09	(RRM 3597-2 74)
1187	M10 T2 012	(RRM 3597-2 76)
1085	M10 T2 C9	*ERROR
3536-1-41	M10 T2 F12	SHBE
30-A-103	M10 T2 L9	
107509706	M10 T3 A9	*ERROR
Z79A-48121	M10 T3 B10	*ERROR
Z81A-8182	M10 T3 C4	*ERROR
Z81A-8175	M10 T3 F3	*ERROR
ARD-A165	M10 T3 G8	SHBE
3536-4-69	M10 T4 E3	*ERROR
9-81-1	M10 T4 K12	
3536-5-5	M11 T1 G4	*ERROR
3536-7-60	M11 T1 L10	*ERROR
ARD80A120	M11 T2 J3	*ERROR
202A98132	M11 T2 K5	*ERROR
3536-8-8	M11 T3 I7	*ERROR
3536-9-43	M11 T4 C2	*ERROR
H-004	M11 T4 C3	SHBE
H-049	M11 T4 C4	SHBE
H-048	M11 T4 C5	SHBE
H-034	M11 T4 C6	SHBE
H-058	M11 T4 C7	SHBE
R-274	M11 T4 C8	SHBE
R-215	M11 T4 C9	SHBE
R-389	M11 T4 D3	SHBE

<u>PIN =</u>	<u>RECORD =</u>	<u>STATUS</u>
R-330	M11 T4 D1	SHBE
R-413	M11 T4 D5	SHBE
R-246	M11 T4 D6	SHBE
R-413	M11 T4 D7	SHBE
R-387	M11 T4 D8	SHBE
R-355	M11 T4 D9	SHBE
R-308	M11 T4 D10	SHBE
R-375	M11 T4 E3	SHBE
R-506	M11 T4 E4	SHBE
R-394	M11 T4 E5	SHBE
R-307	M11 T4 E6	SHBE
R-408	M11 T4 E7	SHBE
R-497	M11 T4 E8	SHBE
R-384	M11 T4 E9	SHBE
R-205	M11 T4 E10	SHBE
R-502	M11 T4 F3	SHBE
R-337	M11 T4 F4	SHBE
R-317	M11 T4 F5	SHBE
R-527	M11 T4 F6	SHBE
R-418	M11 T4 F7	SHBE
R-210	M11 T4 F8	SHBE
R-479	M11 T4 F9	SHBE
R-318	M11 T4 F20	SHBE
R-332	M11 T4 G3	SHBE
R-329	M11 T4 G4	SHBE
R-322	M11 T4 G5	SHBE
R-473	M11 T4 G6	SHBE
R-305	M11 T4 G7	SHBE
R-511	M11 T4 G8	SHBE
R-270	M11 T4 G9	SHBE
R-414	M11 T4 G10	SHBE
R-406	M11 T4 H3	SHBE
R-437	M11 T4 H4	SHBE
R-398	M11 T4 H5	SHBE
R-522	M11 T4 H6	SHBE
R-485	M11 T4 H7	SHBE
R-532	M11 T4 H8	SHBE
R-293	M11 T4 H9	SHBE
R-447	M11 T4 H10	SHBE
R-316	M11 T4 I9	SHBE
R-410	M11 T4 I10	SHBE
353610-51	M12 T2 A11	*ERROR
0-1223	M13 T1 D10	*ERROR
0-1193	M13 T1 E3	*ERROR
231Z82-1	M13 T2 C6	*ERROR
NFD-002	M13 T2 H11	*ERROR
NFD-192	M13 T2 H12	*ERROR
Z82A-8700	M13 T3 B7	*ERROR
NFD-101	M13 T3 D11	*ERROR
NFD-202	M13 T3 E1	SHBE

PIN #	RECORD #	STATUS
NFD-132		M13 T3 E2 *ERROR
Z02A-100		M13 T3 E10 SHBE
Z02A-39		M13 T3 E12 *ERROR
Z32A-3296		M13 T1 E5 *ERROR
Z92A-3295		M13 T1 E6 *ERROR
NFD-159		M13 T4 F1 SHBE
Z82A-8869		M13 T4 K1 *ERROR
NFD-254		M14 T1 C12 *ERROR
Z83A-9169		M14 T2 J6 *ERROR
ARD-028		M14 T3 A5 SHBE
ARD-023		M14 T3 A7 SHBE
ARD-032		M14 T3 C5 SHBE
ARD-026		M14 T3 C7 SHBE
ARD-024		M14 T3 F5 SHBE
ARD305-12		M14 T3 F7 SHBE
JH1		M14 T4 I4 SHBE
4242-3-6	BABCX 330068	M14 T4 K1 SHBE
4256-11-2		M15 T3 L11 *ERROR
425612-7		M16 T2 D1 *ERROR
Z83-A9694		M16 T4 A5
33031		M17 T1 K3 *ERROR
Z83-A9995		M17 T2 C9 *ERROR
Z84A10046		M17 T4 B8 SHBE
Z84A11143	3414A3	M18 T4 L1
Z84A11134	341395	M18 T4 L4
Z84A11142	341403	M19 T1 A12

SECTION 3: The PIN's in this section have multiple entries either on the field location sheets, the SWITS database or both. Many of these are actually multiple drums having the same PIN number but are designated by -A, -B, -1, -2 etc. The individual drum identifier designations are shown on the SWITS data but were not recorded on the field location sheets. It is therefore impossible to determine which drum is in which location. Drums with multiple designations are identified as A & B or 1 & 2.

Drums statused with designation 1 EODS have only one entry in the SWITS database but multiple locations on the field sheets.

<u>PIN #</u>	<u>RECORD #</u>	<u>STATUS</u>
Z77-A3108	M1 T1 A5	M1 T1 F1 2 EODS & DS A & B
Z77-A3106	M1 T1 A7	M1 T1 F2 2 EODS & DS A & B
Z77-A3181	M1 T1 H12	T5 A1
Z77-A3160	M1 T1 I5	T5 A2
Z77-A3215	M1 T1 J9	T5 A3
Z77-A3158	M1 T1 J1	T5 A4
Z77-A3154	M1 T1 G6	T5 A5
Z77-A3209	M1 T1 J4	T5 A6
Z77-A3146	M1 T1 G2	T5 A7
Z77-A3149	M1 T1 G12	T5 A8
Z77-A3155	M1 T1 F11	T5 A9
Z77-A3152	M1 T1 G7	T5 A10
Z77-A3148	M1 T1 H11	T5 A11
Z77-A3129	M1 T1 G8	T5 A12
Z77-A3177	M1 T1 I3	T5 B1
Z77-A3166	M1 T1 I10	T5 B2
Z77-A3175	M1 T1 I7	T5 B3
Z77-A3144	M1 T1 G11	T5 B4
Z77-A3136	M1 T1 H6	T5 B5
Z77-A3140	M1 T1 H2	T5 B6
Z77-A3200	M1 T1 H8	T5 B7
Z77-A3133	M1 T1 H5	T5 B8
Z77-A3134	M1 T1 H4	T5 B9
Z77-A3143	M1 T1 F12	T5 B10
Z77-A3150	M1 T1 G5	T5 B12
Z77-A3190	M1 T1 H1	T5 C1
Z77-A3142	M1 T1 G1	T5 C2
Z77-A3167	M1 T1 I4	T5 C3
Z77-A3147	M1 T1 H7	T5 C4
Z77-A3163	M1 T1 I6	T5 C5
Z77-A3139	M1 T1 G9	T5 C12
Z77-A3169	M1 T1 I12	T5 D1
Z77-A3128	M1 T1 G3	T5 D2
Z77-A3130	M1 T1 G4	T5 D12
Z77-A3201	M1 T1 H9	T5 E1
Z77-A3202	M1 T1 H10	T5 E12
Z77-A3153	M1 T1 G10	T5 F1
Z77-A3137	M1 T1 H3	T5 H1

PIN =	RECORD =	STATUS
278-A3637		M1 T1 G6 M1 T4 F9 2 EOFLS 1 EODS
WH78-49		M1 T5 I3 1 EOFLS 2 EODS A & B
278-A3787		M1 T5 I10 M1 T4 K9 2 EOFLS 1 EODS
278-A3719		M1 T5 I11 M1 T5 I12 2 EOFLS 1 EODS
BCL-88A	730022.23	M2 T2 E9 1 EODS (see section 5 - BCL-374)
BN78-334		M2 T4 E9 M2 T1 C12 2 EOFLS 1 EODS
WH78-143		M2 T5 G1 / M2 T5 G9 3 EOFLS & 2 EODS A & B
WH78-147		M2 T5 K1 / M1 T5 L4 2 EOFLS & DS A & B
WH78-137		M2 T5 A6 / I10 2 EOFLS & DS A & B
Z79-A5000		M3 T4 C12 / M5 T2 B10 2 EOFLS & DS A & B
HEDL-7887		M4 T1 L5 / L9 2 EOFLS 1 EODS
Z2-78-4	790033/28	M4 T2 C10 1 EOFLS 2 EODS A & B
Z77-A3151	79088	M4 T2 H2 / M4 T2 H7 2 EOFLS & 1 EODS
Z78-A3728	790517	M4 T2 K6 / M4 T2 K11 2 EOFLS & 1 EODS
Z78-A3781	790562	M4 T2 K4 / M4 T2 J11 2 EOFLS & 1 EODS
202A78601		M4 T3 C1 / D4 2 EOFLS 1 EODS
Z78-A4140	730804	M4 T4 A1 / M2 T3 H6 2 EOFLS 1 EODS
Z78-A4482		M4 T4 H2 / H6 2 EOFLS 1 EODS
Z78-A4496		M4 T4 H5 / H9 2 EOFLS 1 EODS
Z-A4883		M5 T1 A2 / A4 2 EOFLS 2 EODS 1 & 2
Z-A4404		M5 T1 A7 / B3 B6 3 EOFLS 3 EODS 1, 2, & 3
Z-A4806		M5 T1 A8 / F9 2 EOFLS 2 EODS 1 & 2
Z-A4583		M5 T1 A10 B2 2 EOFLS & DS 1 & 2
Z-A4400		M5 T1 A11 F11 2 EOFLS & DS 1 & 2
Z-A4009		M5 T1 A12 B1 2 EOFLS & DS 1 & 2
Z-A4693		M5 T1 B4 B10 2 EOFLS
Z-A4401		M5 T1 B9 B11 2 EOFLS & DS 1 & 2
Z79-A5217		M5 T2 F8 M5 T3 F3 2 EOFLS
Z79-A5385	791248	M5 T3 G2 / M6 T1 B6 2 EOFLS 1 EODS
D79-6-A-7		M5 T4 B11 B12 2 EOFLS 1 EODS
WH79-276		M5 T4 C1 L1 2 EOFLS 2 EODS WH-276 & HEDL-276
BN79-513		M6 T2 B3 H6 2 EOFLS & DS A & B
Z79-A5624		M6 T3 F1 / H2 2 EOFLS 1 EODS
Z80A-6905		M9 T1 J5 / L8 2 EOFLS 1 EODS
ARD80-030	WARD / 810054	M9 T2 G2 / M9 T3 A2 2 EOFLS 1 EODS
ARD880A31		M9 T2 F4 / H3 2 EOFLS 1 EODS
Z80A-7079		M9 T2 H5 / L4 2 EOFLS 1 EODS
353610-45		M12 T1 A12 / D11 2 EOFLS 1 EODS
202A82153		M13 T2 E2 / M13 T3 E1 2 EOFLS 1 EODS
202A48239		M13 T2 L11 / M13 T3 I7 2 EOFLS 1 EODS
NFD-219		M13 T3 E5 / M13 T4 H5 2 EOFLS & 1 EODS
202A82123		M13 T4 E1 / E2 2 EOFLS 1 EODS
Z83A-9652		M16 T2 A2 / A3 2 EOFLS 1 EODS
Z83-A9921		M17 T2 A10 / A9 2 EOFLS 1 EODS

SECTION 4: Field locate sheets show these PIN's are in Trench 4 however the current data on SWITS says that they are in another trench.

PIN = RECORD = STATUS

SWITS entries show that the following are in Trench 4.

R-77-39		M1 T4 M6
R-77-40		M1 T4 M7
R-77-41		M1 T4 M8
Z79-A5743		M6 T4 G3
Z79-A5748		M6 T4 G4
Z79-A5735		M6 T4 G5
Z79-A5744		M6 T4 G6
Z79-A5737		M6 T4 G7
Z79-A5745		M6 T4 H2
Z79-A5747		M6 T4 H5
Z79-A5738		M6 T4 H6
Z79-A5742		M6 T4 H10
Z79-A5750		M6 T4 G9
242T-79-1	2WTF / 300001	M6 T4 F3
242T-79-2	2	M6 T4 F5
-3	3	M6 T4 F1
-4	4	M6 T4 E9
-5	5	M6 T4 F1
-6	6	M6 T4 E2
-7	7	M6 T4 E6
-8	8	M6 T4 E5
-9	9	M6 T4 E12
242T-7910	10	M6 T4 E11
-7911	11	M6 T4 F3
-7912	12	M6 T4 E4
-7913	13	M6 T4 E2
-7914	14	M6 T4 F10
-7915	15	M6 T4 F9
-7916	16	M6 T4 G1
-7917	17	M6 T4 F7
-7918	18	M6 T4 E7
-7919	19	M6 T4 F12
-7920	20	M6 T4 F6
-7921	21	M6 T4 E8
-7922	22	M6 T4 E10
WH79-305	325 / 800018	M6 T4 H1
Z79-A5746	800008	M6 T4 H3
WH79-292	325 / 800006	M6 T4 H4
D79-10A38	233S / 800001	M6 T4 H7
D79-10A43	233S / 800003	M6 T4 H8
WH79-287	325 / 800001	M6 T4 H10
WH79-306	325 / 800019	M6 T4 I1
WH79-307	325 / 800020	M6 T4 I2

<u>PIN =</u>	<u>RECORD/BLOG</u>	<u>STATUS</u>
WH79-289	325 300003	M6 T1 T1
WH79-303	325 300017	M6 T1 T6
WH79-300	325 300014	M6 T1 T7
WH79-296	325 300010	M6 T1 T9
WH79-288	325 / 800002	M6 T1 J1
WH79-293	325 / 800007	M6 T1 J4
WH79-301	325 / 800015	M6 T4 J5
WH79-294	325 / 800008	M6 T4 J6
WH79-290	325 / 800004	M6 T4 J8
WH79-297	325 / 800011	M6 T4 K1
WH79-291	325 / 800005	M6 T4 K2
WH79-298	325 / 800012	M6 T4 K3
WH79-295	325 / 800009	M6 T4 L1
WH79-302	325 / 800016	M6 T4 L2

SECTION 5 : PIN'S THAT WERE MISIDENTIFIED DURING THE INITIAL DATA ENTRY.
CORRECTED PIN'S ARE SHOWN. DATA WAS VERIFIED BY SEARCH OF THE
WASTE RECORDS.

<u>CORRECT PIN S</u>	<u>RECORD #</u>	<u>POSITION</u>	<u>PIN'S AS ENTERED IN SWITS</u>
WH73-3	730032	M1 T2 B3	WH77-3
WH78-19	730049	M1 T4 B5	WH79-19
WH78-20	780050	M1 T4 B6	WH79-20
WH78-42	780067	M1 T5 L4	WH67-42
Z78-A3838	780613	M2 T1 D11	2 EOS CONFIRM WITH REC #
Z78-A3828	780591	M2 T1 C1	Z78-3838
BCL-88A	780023	M2 T2 E9	2 EOS CONFIRM WITH REC #
BCL-87A	780022	M2 T2 K1	BCL-88A
Z78-A3998	780768	M2 T2 K12	Z78-A4998 2 EOS C R=
Z78-A4075	780768	M2 T3 L5	Z37-A4075
Z79-A4898	790668	M3 T4 A6	Z79-A4873 2 EOS C R=
Z78-A4259	791045	M4 T4 B10	Z78-A4249
Z79-A5145	790506	M5 T2 L3	Z79-A4805
Z79-A5255	791161	M5 T3 L12	Z79-A4255
Z81A-7850	810191	M9 T4 L4	Z91A-7880
Z81A-8088	910383	M10 T1 J11	Z78A-8088
3536-4-49	310127	M10 T4 F1	3436-4-49
3536-6-52	310217	M11 T1 K0	3536-6-52
3536-7-19	310240	M11 T2 A1	3537-7-19
Z82A-9079	330005	M14 T3 F9	Z38A-9079 C. R=
Z84A10592		M18 T2 B2	Z85A10592
Z84A10601		M18 T2 B3	Z85A10601
Z84A10591		M18 T2 C4	Z85A10591
Z84A10599		M18 T2 C2	Z85A10599
Z84A10590		M18 T4 A2	Z85A10590
Z84A10594		M18 T4 A6	Z85A10594
Z84A10593		M18 T4 B6	Z85A10593
Z84A10598		M18 T4 C8	Z85A10598

SECTION 6: FIELD LOCATIONS WHICH DO NOT HAVE AN ENTRY OR HAVE AN ENTRY WHICH FOR SOME REASON CANNOT BE PROPRITLY IDENTIFIED.

LOCATION	STATUS
M2 T3 L11	NO ENTRY
M2 T3 L12	NO ENTRY
M2 T4 K1 TO K8	NO ENTRIES
M2 T4 L1 TO L8	NO ENTRIES
M3 T1 H6	Z78-A440? POSSIBLE INCOMPLETE ENTRY
M3 T4 A2	Z79-A???? INCOMPLETE ENTRY
M4 T1 F9	WH78-?? INCOMPLETE ENTRY
M4 T1 G5	WH78-?? INCOMPLETE ENTRY
M4 T2 C11	Z78-???? INCOMPLETE ENTRY
M4 T2 E9	NO ENTRY
M4 T2 E12	NO ENTRY
M4 T2 I6	Z78-A378? INCOMPLETE ENTRY
M4 T2 I11	NO ENTRY
M4 T3 A3	Z78-3926 INCOMPLETE ENTRY
M4 T3 I9 TO I12	NO ENTRIES
M4 T3 K8 TO K12	NO ENTRIES
M4 T3 L1 TO L12	NO ENTRIES
M9 T2 L12	NO ENTRY
M9 T4 C3 TO C9	UNCLEAR ENTRIES
M11 T4 C3 TO C10	NO ENTRIES ON FIELD LOCATE SHEETS
D3 TO D10	
E3 TO E10	
F3 TO F10	
G3 TO G10	
H3 TO H10	
I9 TO I10	
M12 T2 F9	UNIDENTIFIABLE ENTRY
M12 T3 L12	NO ENTRY

Section 7: The field locate sheets for these locations show a split entry (2 PIN numbers at each location) on the sheet.

79731901A	2345Z / 810354	M10 T2 L1
3536-1-44	BABCX / 810040	M10 T2 L1
Z78A45122	2345Z / 810353	M10 T2 L2
3536-1-58	BABCX / 810053	M10 T2 L2
3536-1-56	BABCX / 810051	M10 T2 L3
3536-1-30	BABCX / 810027	M10 T2 L3
ARD80A122	WARD / 810076	M10 T2 L4
ARD80A085	WARD / 81077A	M10 T2 L4

MEMO
Letter no. WCG-PT-001

FROM: Waste Form Applications/WO Greenhagh
PHONE: 6-7616
DATE: March 18, 1993
SUBJECT: Burial Ground 4C Trench 4, Waste Generator Information

TO: D. R. Duncan HS-33

cc: JW Biglin LS-31
JA Hunter LS-31
~~XXXXXXXXXXXXXXXXXXXX~~
ML Sheriff HS-31
JA Demiter LS-31

Task A111H was established to define and characterize the TRU waste contained in trench 4. The memo from JW Biglin dated Mar. 17, 1993 contained location corrections based upon a review of the trench data. This memo will address characterization data about the waste itself from generator sources to upgrade the information available on the SWITS data base.

ML Sheriff provided a list of recorded generators and the number of drums they submitted for storage. The largest volume generators are listed below:

- o 234-5Z Building - 6032 drums
- o 325 Building - 1017 drums
- o Babcock and Wilcox mfg. company - 625 drums
- o Westinghouse Advanced Reactor Division WARD - 349 drums & 26 boxes
- o 340 Complex - 321 drums & 4 boxes
- o 202A PUPSEX - 294 drums
- o 331-2 Building - 219 drums

The 234-5Z plant waste is well characterized and has been described in alot of detail by LATA. (Ref. 1) The volumes of TRU and non-TRU generated for each particular year is listed. The definition for non-TRU waste is that waste containing less than 100 nCi/gm transuranic radionuclides. The only significant question that was posed was whether the TRU and non-TRU waste generated had any appreciable fission or activation product material. The answer to that question is "no" to our best knowledge. Several process engineer types that worked in Z plant in the mid and late seventies (approx. date waste was generated) said there was no fission product (FP) type activity at Z plant. Effluent studies on the plant confirm that the gaseous and liquid effluents did not contain any trace FP type contamination (Ref 2, 3, 4). In addition, recent assay data on actual waste drums show no appreciable FP activity according to PNL counting information. The Appendix contains a summary copy of the assay information. In addition, the Appendix contains a letter (Letter no. 4) that summarizes results of a low-level plutonium counter called MEGAS. This counter showed that a lot of the waste, mostly room waste (rather than glove-box material) was non-TRU and had little appreciable activity. The TRU waste with Z plant plutonium is practically all defense grade with a nominally 5% Pu-240 content (low dose rate).

The 325 Building generated TRU waste is quite varied. A chart based on mid-seventy waste assay data in my own personal file and in some released documents is given in Table 1, 2, and 3 (Ref. 5, & 6). This shows the average plutonium levels in the drums plus some information on the high plutonium drums. The isotopic levels of the plutonium is not listed, but most is consistent with the FFTF core 1 and 2 fuel material upon which alot of the work at that time was based. This plutonium had a isotopic content of about 11.7 to 11.8 % Pu-240. (Ref 7) In fact, the plutonium assay equipment for the 300 Area was set-up (calibrated) for the FFTF (11.7%) fuel material. There was still probably some defense type plutonium (6% Pu-240) as well as some higher exposure material (19.2 and 24% Pu-240) that was generated on occasion (Ref. 8), but it is expected that 90% or better was typically 12% Pu-240. Some dose rate measurements for high exposure fuel is given in personnel dosimetry program results for 1960. (Ref. 9)

The 340 waste material probably came from other 300 Area type facilities such as 308 rather than being generated at the 340 Complex. The 340 Complex was established to handle the storage and shipping of 300 Area liquid waste which was limited to less than 15 grams per 20,000 gallon of liquid non-TRU, therefore the only source of TRU would be equipment decontamination work and that normally wouldn't amount to more than 1 to 3 drums of waste. Assuming the 340 waste to be that of other 300 Area buildings then Tables 2, 3, and 4 give a good idea of the TRU waste characteristics. Plutonium isotopes would be consistent with listed for the 325 Building.

The third largest generator for trench 4 was Babcox and Wilcox who was under contract to provide fuel for FFTF. Bradley and Clark (Ref. 10) put together a document describing the the waste generated during the fabrication of FFTF fuel for cores 1 and 2. Typically, production plants runs the same way after a day with the exception of process improvements. Assuming little or no process improvement from 1972-75 time frame to 1978, then the solid waste descriptions included in the document should describe the variety of waste in trench 4 from Babcox and Wilcox. The fuel delivery times and the material involved is listed below: (Ref. 11) The isotopic content of cores 3 and 4 were also nominally 12 % Pu-240. Later cores (5 and 6) were 19 and 24% respectively, but waste from the higher Pu-240 would not be expected in Trench 4.

Cores 1 and 2

Delivered Dec. 72 - Oct. 75

Cores 3 and 4

Delivered Aug. 76 - June 80

During the production period, 3.7 metric tons of fuel was produced. The waste generated for retrievable storage amounted to 385.3 cu. meters or 92% of the total solid waste generated. The waste consisted of 53.7 vol.% dry drum waste, 15.0 vol.% crated dry waste, and 21.3 vol.% drummed liquid waste. The mixed oxide fuel consists of 75% normal or depleted uranium dioxide blended to less than 0.3% U-235. The plutonium is the 11.7 or 11.8% Pu-240 isotopic for this fuel. The pellets resulting from their processing is 0.1945 inches in diameter and has an oxide to metal ratio of 1.94 rather than the 2.00 theoretical or higher. Highly contaminated waste and scrap materials are recycled. Lower contaminated levels (< 25 g/drum Pu) are classified as waste.

The waste sources and characteristics are given in Tables 4, 5, 6, and 7. The liquid wastes generated were immobilized by adsorption on Speedi-Dri a

vermiculite absorbent material. Details on the other solid wastes are included in the text. In addition, Table B provides some information on later MTR fuel (Ref 12).

Information on the other large waste generators is still being collected.

REFERENCES:

1. "Characterization of Past and Present Solid Waste Streams from the Plutonium Finishing Plant", prepared by Los Alamos Technical Associates (LATA), DRAFT, July 15, 1992.
2. LF Lust, "Plutonium Finishing Plant Chemical Sewer Flowsheet", PFD-1-120-00006 (Dec. 1986).
3. WD Greenhaigh & RD Keck, "The Plutonium Finishing Plant Liquid Effluent Monitoring Plan", SD-CP-SMF-001 (Aug. 12, 1988).
4. DR Einar, "The Plutonium Finishing Plant Gaseous Effluent Monitoring Plans", SD-CP-SMF-002 (Aug. 12, 1988).
5. "Report on Waste Management and Transportation Programs for July 1974", TC-115-2, p. 6, (July 1974).
6. "Commercial Alpha Waste Program Quarterly Progress Report January - March 1975", HEDL-TME 75-37.
7. DN Jackson, Jr. & Paul Boris, "Plutonium Waste Drum Monitor", HEDL-TME TC-10, p. 22 (Jan. 1973).
8. JN Strode & RC Smith, "Gamma Dose Rates for MTR Fuel Pins, Storage Casks, and Fuel Pin Storage and Transport Box Designs", HEDL-TME TC-31, p. 11 (May 1975).
9. RC Smith, "Personel Dosimetry and Shielding Program Progress Report", HEDL-TME 82-16, p. 11 (July-Dec. 1980).
10. JG Bradley & DE Clark, "Waste Generated During Fabrication of Mixed Oxide Fuels", HEDL-TME 78-71 (Oct. 1978).
11. Marjory Serier, "Private Communication", March 23, 1993.
12. JG Bradley, "Sorting of Wastes Generated During Fabrication of Mixed Oxide Nuclear Fuels", HEDL-TME 79-77, p. 17 (April 1980).

Table 1: TRANSURANIC WASTE SHIPPED TO TRU WASTE STORAGE
FROM THE 325 BUILDING

Organization	No. of Drums Shipped	Waste Weight (lbs)	Waste Weight (Average lbs per drum)	Total Waste Volume (cu ft)	No. of Drums Assayed for Plutonium*	Total Plutonium Assay* (gms)	Plutonium Content (average gms* per drum)	Comments
CY - 1974 (WMC) (BNW)	69 20	8556 No Data	124 No Data	517.5 157.5	36 0	756.6 No Data	21.0 No Data	Note: (CY-1974) Only 52% of the WMC drums were assayed. Highest Pu content was 109 gram.
Total:	89		124	675.0	36	756.6	21.0	
CY - 1975 1 ST Quarter (WMC) 2 ND Quarter 3 RD Quarter 4 TH Quarter	21 No Data No Data 22	2425 No Data No Data 2429	115.4 No Data No Data 112.5	157.5 No Data No Data 165.0	21 No Data No Data 22	286.6 No Data No Data 155.9	13.6 No Data No Data 7.0	High Pu 75.0
CY - 1976 1 ST Half (WMC) 2 ND Half	26 19	3457 2359	133 124.2	195 142.5	26 19	175.2 409.47	7.0 21.55	
CY - 1977 (WMC) • Suspect Comdistible • Regular Comdistible • Non Comdistible (BNW)	8 40 1 vault 2 concrete drums 10	645 (6 only) 5142 1200 1000 No Data	107.5 128.6 1200 500 No Data	60 500 27 15 75	0 40 0 0 0	0 818.0 No Data <1g est. <1g est.	0 20.4 No Data No Data No Data	High Pu 73.92g
Total:	61 Containers	9200 est		477	46	818.0	17.8	

February 22, 1993

Table 2: Transuranic Waste Shipped by HHL Waste Management
(October 1, through December 31, 1974)

Organization	No. of Drums Shipped	Waste Weight (avg. lbs per drum)	Total Waste Volume (cu ft)	No. of Drums Assayed for Plutonium*	Total Plutonium Assay* (gms)	Plutonium Content (avg. gms* per drum)	Building Source
HEDL DRUMS							
Rad. Mat'l's Processing	2	260	15	2	25.3	12.7	325
Post-Irradiation Testing	24 (1 dbl)	117 (12 avg)	187.5	no assay because of high beta activity			327
Process Dev. & Demo.	4	130	30	4	49.2	12.3	308
308 Building Management	2	155	15	2	19	9.5	308
Applied Chem. & Anal.	15	121 (14 avg)	112.5	14	216.7	15.5	325
Radiochemistry	1	116	7.5	1	0.5	0.5	325
Microstructural Analysis	1	106	7.5	1	75	75.0	308
Sub Assembly Dev.	1	114	7.5	1	0	0	308
Advanced Fuels Technology	3	127	22.5	3	10.1	3.4	308
Component Fabrication	1	108	7.5	1	4.8	4.8	308
TOTALS	54	131	412.5	29	400.6	13.8	---

BNW DRUMS

Chemical Technology Dept.	10 (1 dbl)	106	82.5	0	---		325/324 (1)
7 avg. w/o drum of concrete (400 lbs)							
Biology Dept.	4	131	30	0	---		331
TOTALS	14	115	112.5	0	---		---

Table 5: Transuranic Waste Shipped by HLOI Waste Management
(July 1, Through September 30, 1974)

Organization	No. of Drums Shipped	Waste Weight (avg. lbs per drum)	Total Waste Volume (cu ft)	No. of Drums Assayed for Plutonium*	Total Plutonium Assay* (gms)	Plutonium Content (avg. gms* per drum)	Building Source
<u>HLOI DRUMS</u>							
Rad. HLL's Reprocessing	1		7.5	0	---	0	325
Post Irradiation Testing	23(1 30 gal)	147	169.8	0	---		327/324(2)
Process Development & Demo.	4	168	80.0	3	29(1 drum had 10 "0")		308
308 Building Management	1	106	7.5	1	0	0	308
Applied Chemistry	1	concrete (~400 lbs)	7.5	1	109	109	325
Radiochemistry	0				---		325
Microstructural Analysis	0				---		325
Sub Assembly Dev.	0				---		308
Advanced Fuels Tech	11	184	82.5	11	37.8	3(9 drums had <0.5 gm)	308
Component Fabrication	0				---		
Reactor Instrument Dev.	1		7.5	1	<0.1	<0.1	326
TOTALS	42	165 w/o concrete	312.3	17	176	4 w/o drum with 109 gms	

Table 4: Transuranic Waste Shipped by HDBL Waste Management
(Jan. 1, through June 30, 1974)

Organization	No. of Drums Shipped	Waste Weight (avg. lbs per drum)	Total Waste Volume (cu ft)	No. of Drums Assayed for Plutonium*	Total Plutonium Assay* (gms.)	Plutonium Content (avg. gms* per drum)	Building Source
HEDL DRUMS							
Rad. Mat'ls. Processing	5	147	37.5	4	105.7	26.4	325 (Radiochemistry)
Postirradiation Testing	44	80	330	0	Assay not possible because of high beta/gamma activity		327
Process Dev. & Demo.	12	84	90	5	57.2	11.4	308 (Mixed Oxide Fabrication)
308 Building Management	42	194	315	12	62.5	5.2	308
		Floor tile was in 24 of the drums					
Applied Chem. & Anal.	24	113	180	9	203.8	22.6	325
		Three of the drums were concreted					
Radiochemistry	15	126	112.5	3	17.6	5.9	325
Microstructural Anal.	5	48	37.5	2	78.0	37.0	325/308
Subassembly Dev.	6	79	45	4	52.5	13.7	308
Advance Fuels Tech.	21	113	157.5	17	145.9	8.5	308
Bldg. Management	6	208	45	0			308
TOTALS	180	127 avg	1350	56	723.2	12.9	
		23,010 net wt.					
BWG DRUMS							
Chemical Tech. Dept.	10	89	75				325
Biology Dept.	4	102	30				311
Radiological Chemistry	2	65	15				329
Fuels & HCLs. Dept.	2	90	15				308
TOTALS	18	92 avg	135				
		1656 net wt.					

*NOTE: Drums are assayed for plutonium content by either gross neutron or gross gamma counting. Total Pu content based on average of the number of drums assayed.

Table 5: Waste Generated at the Baccos-Wilcox Fuel Plant

NET WEIGHTS OF WASTE DRUM CONTENTS

Drummed Waste Type	Drums No.	Net Wt.		Bulk Density, lb/cu ft
		lb.	kg.	
Non-Compacted Contents				
Line	131	14281	6477.7	0.1719
Non-Line	140	3130	3637.7	0.1265
HEPA Filters	106	3630	1646.3	0.0746
Scrap and Mixed	26	960	430.3	0.0766
Scrap Equipment	11	716	324.3	0.1413
Speedi-Drill Drill	10	3160	379.3	0.4706
Speedi-Drill Ad	7	1663	760.1	0.6161
Sub-Total Avg.	481	31626	14239.3	0.1403
Compacted Contents				
Non-Blowbox	33	3113	1412.0	0.0666
HEPA Filters	1	135	61.3	0.0943
Sub-Total Avg	34	3248	1473.3	0.0831
TOTAL Avg.	515	34773	15712.7	0.1271

Notes to Table

Table 62: Debris Office Waste

WHC-SD W113 ACDR 001
Rev. 0
Page 441

WASTE SHIPPED TO RETRIEVABLE STORAGE, m³,
AND INCREMENTAL % OF Pu LOSS (X.XX)

ORIGIN OF WASTE INCREMENT	PROCESS TESTS		PRODUCTION OPERATIONS			TOTAL TO RETRIEVABLE STORAGE
	1972	1973	1973	1974	1975	
Line and Laboratory	14.91 (4.71)		27.66 (13.70)	31.14 (14.41)	35.39 (26.61)	109.10 (59.41)
Non-Line	2.98 (0.01)		12.78 (0.16)	24.12 (1.09)	33.82 (5.08)	73.70 (6.34)
HEPA Filters & Jet Mill Bags	2.70 (0.69)		8.47 (1.86)	12.87 (1.90)	18.84 (2.75)	42.88 (11.20)
Scrap and Mixed	1.63 (0.05)		6.91 (0.40)	5.36 (1.44)	6.30 (2.86)	20.20 (6.76)
Spent HEPA Filters			4.02 (0.09)	9.02 (0.20)	10.42 (0.23)	23.46 (0.52)
Scrap and Mixed				15.89 (0.47)	18.35 (0.53)	34.24 (1.00)
Scrap Recovery (SR) Liquids & Sludge			10.67 (0.64)	23.94 (1.42)	27.64 (1.63)	62.25 (1.68)
Analytical Laboratory	0.54 (0.68)		1.23 (1.60)	2.75 (1.57)	3.18 (4.12)	7.70 (9.97)
Non-SR Liquids			4.54 (0.00)	13.58 (1.10)	23.89 (0.00)	41.01 (1.10)
Volume Shipped, m ³	22.76		75.28	138.67	177.83	414.54
Pu in Period, % of Total Loss	(6.13)		(20.42)	(29.64)	(43.81)	(100.00)

Table 7: Halcos White Waste

VOLUME AND DISPOSITION OF GENERATED WASTES

ORIGIN OF WASTE INCREMENT AND TYPE OF CONTAINER	GENERATED WASTE VOLUME, m ³ PER YEAR						SCRAP RECOVERY	DISPOSAL TO RETRIEVABLE STORAGE	SHALLOW LAND COVER
	1972	1973	1974	1975	1976	TOTAL			
Drummed Dry Wastes									
Line and Laboratory	11.45	30.40	30.61	34.77	4.16	111.39	2.29	109.10	
Non-Line	7.29	13.12	23.32	12.89	7.08	73.70		73.70	
HEPA Filters & Jet Mill Bags	7.08	8.95	11.33	19.36	0.81	47.53	1.67	42.88	
Scrap and Mixed	1.25	7.29	3.33	4.58	4.37	20.82	0.62	20.20	
Crated Dry Wastes									
Spent HEPA Filters		1.59		11.37	8.50	21.46		21.46	
Scrap and Mixed			13.17	5.41	15.63	34.21		34.21	
Drummed Liquid Wastes(a)									
Scrap Recovery (SR) Liquids & Sludge	Non-Operating Period			46.64	15.61	62.25		62.25	
Analytical Laboratory	0.47	1.37	1.12	1.67	0.62	7.27		7.27	
Non-SR Liquids		0.83	7.50	16.86	15.82	41.01		41.01	28.73
TOTALS	17.49	64.05	94.38	175.58	62.62	419.12	4.58	385.94	28.73

Notes

(a) Liquid wastes are immobilized prior to shipment

Table B: Babcock Wilcox Waste

PLUTONIUM CONCENTRATION IN GENERATED WASTES, g/m³

ORIGIN OF WASTE INCREMENT	g/m ³ , BY YEAR						Pu, g/m ³ ^(a)	SHIPPED TO
AND TYPE OF CONTAINER	1972	1973	1974	1975	1976	AVERAGE	SCRAP RECOVERY	RETRIEVABLE STORAGE
<u>Drummed Dry Wastes</u>								
Line and Laboratory	42.27	78.19	95.50	143.03	123.07	101.45	765.07	87.52
Non-Line	0.00	2.06	7.41	24.75	2.40	13.83		13.83
HEPA Filters & Jet Mill Bags	30.77	74.54	97.15	62.65	2.41	72.75	862.87	41.98
Scrap and Mixed	1.70	9.60	14.41	45.85	253.55	69.16	569.45	53.91
<u>Crated Dry Wastes</u>								
Spent HEPA Filters		6.92		0.52	7.65	3.54		1.54
Scrap and Mixed			0.00	0.00	10.30	4.70		4.70
<u>Drummed Liquid Wastes^(b)</u>								
Scrap Recovery (SR) Liquids & Sludge	Non-Operating Period			5.32	21.97	9.49		9.49
Analytical Laboratory	188.69	241.13	198.08	202.40	187.10	208.05		208.05
Non-SR Liquids		0.00	23.47	0.00	0.00	4.29		14.37
<u>TOTALS</u>								
	36.08	56.25	55.77	44.44	34.19	46.80	224.24	41.65

Notes

- (a) All immobilized liquid waste shipped to shallow land cover assayed as 0g/m³.
(b) Liquid wastes are immobilized prior to shipment.

Table P: MEGAS Counting Assay of Baccor-Wilcox JPL Waste

Type of Waste	No. of Containers		Pu Content g	Volume m ³
	Can	Pu		
Drummed Wastes	17	47*	1062.30	9.795
Whole Filters	0	1	340.33	0.333
Filter Media or Bags	0	0	0	0
Subtotal	17	51	1402.33	10.618
Analytical Laboratory	0	3	180.00	0.525
Line Waste	3	21	512.32	4.372
Packaged and LGBW**	0	12	504.34	2.707
Compacted	0	0	0	0
Subtotal	3	34	1116.36	7.079
General Use & Scrap Equipment	30	30	21.38	6.662
Non-Line Wastes	10	10	0.0	0.082
Assay LSA	24	24	0.00	4.997
MEGAS Assay LSA	0	0	0	0
Subtotal	34	34	0.0	7.079
Scrap Recovery (Forecast)	0***	53***	104.4***	11.035***
TOTAL DRUMMED	34	107	2924.97	43.098
Crated Wastes	0	2	25.55	15.764
TOTAL GENERATED	0	0	2950.52	59.862

Assays, other than those identified as MEGAS-related or calculated were made, as appropriate, using NWCC, Geiger or Drum Counter equipment. Some of these generated wastes were designated as intended feed increments to subsequent scrap recovery processing.

*Twelve large (24 in. x 24 in. x 20 in.) HEPA filters, after sectioning, were packaged at one per drum among these drums. All other whole filters were 12 in. x 12 in. x 18 in. primary filters.

**Large glovebox wastes (LGBW) were increments too large for containment within 1-1/2 gal cans.

***Calculated values are based on the ratio of Pu in scrap recovery inventory at the end of the test period to scrap recovery experience reported in Reference 1.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX MATERIAL

THIS PAGE INTENTIONALLY LEFT BLANK

MEMO
Letter No. WDC-PC-000

FROM: Waste Forms Applications AC Greenhalgh
PHONE: 5-2610
DATE: March 30, 1993
SUBJECT: Burial Ground AC Trench 4, Waste Generator Update

TO: D. R. Duncan H5-33

cc: JW Biglin L5-31
JA Hunter L5-31
~~DM Johnson L5-31~~
ML Sheriff L5-31
JA Demiter L5-31

The 231-I Bldg in the late sixties and seventies had a complex of glove boxes (see fig. 1,2). The primary mission of the facility was a military one. In 1969 (Ref. 1), work was 80 to 85% under the sponsorship of Military Applications, 10% USAEC Div. of Research, and 5 to 10% other work. The TFL contaminated waste generated by the facility was probably best represented by 90% defense or defense related waste and 10% other. The defense or defense related work would represent plutonium with a Pu-240 content of 5 or less. In fact many plutonium criticality standards used today are still based upon criticality measurements made with 5% Pu-240 material. (Ref. 2)

In January 1975, the Div. of Military Application notified the facility that the weapons work would be cancelled, but that the military would make a commitment to decontaminate and restore the 231-I facility for use as a non-plutonium laboratory. This work was performed in the late seventies and the defense glove-boxes were removed. A phosphoric acid electropolishing decontamination facility was established by Battelle-Northwest in 1978. (Ref. 3,4) Later decontamination work by the decontamination facility included the clean-up and decontamination of at least 10 of the original 231-I glove boxes. Though a lot of the decontamination work would be varied, most of it still was with defense type equipment. Therefore, most of the contaminated waste generated by the facility was still plutonium with an isotopic content of <6% Pu-240. Solid Wastes generated would include sectioned glove boxes in box and metal containers, and solidified liquid waste in drums. The solidified waste included a low temp. salt melt solid, absorbed liquid, and some drums of urea formaldehyde matrices.

REFERENCES:

1. CS Powers, "Safety Analysis Report 231-I Building", BNWL-CC-1924, p. 1 (March 1969).
2. LC Davenport, "Safety Analysis Report", Sup. 4 for the 231-I Bldg., BNWL-CC-1924 SUP 4, pp 11-20 (Aug. 1972).
3. RR King, VC Asmund, & HL Butts, "Detailed Plan for the Decontamination and Restoration of the 231-I Facility", BNWL-B-479 (March 1975).

1. M. Platt & J. Powell, Nuclear Waste Management Quarterly Progress Report
January Through March 1978, Section 17 August 1978.

Figure 1: 231-Z Building Operations

WMC-SD-M113-HUN-00.
Rev. 0
Page 448A

THIS PAGE INTENTIONALLY LEFT BLANK

UNCLASSIFIED

Figure 2: Glove-box Layouts for 231-Z Facility

THIS PAGE INTENTIONALLY LEFT BLANK

MEMO
(Letter No. WOG-93-006)

FROM: Waste Form Applications WO Greenhain
PHONE: 6-9615
DATE: May 10, 1993
SUBJECT: Burial Ground 40 Trench 4. Waste Generator Information

TO: D. R. Duncan H5-33
D. M. Johnson H5-33

cc: JW Biglin L5-31
JA Hunter L5-31
ML Sheriff H5-31
JA Demiter L5-31

The task to better characterize Trench 4 continues. Babcox and Wilcox only worked on 3 cores of FFTF fuel. Kerr McGee did one core and Babcox and Wilcox did the other 3 cores that made up Cores I, II, III, and IV. The plutonium in all four cores was nominally 12% Pu-240 (actually 11.3%). The material that went to Trench 4 was right near the end of the fuel fabrication work. The waste probably includes the typical fuel fab waste listed in letter WOG-93-001 as well as some D&D (decontamination & decommissioning) waste materials such as glove-boxes, fuel fabrication equipment (presses, ball mills, blenders, etc.). However, the plutonium contamination would still be nominally 12% Pu-240 material.

The early (1974) TRU waste generated from GE Vallecitos is shown in Table 1. It shows that most of the material is 3.3% Pu-240 isotopic content. This corresponds to the same isotopic as the PRTR reactor. I don't know if there was any connection. There was also some 7 and a little bit of 10% Pu-240. In addition, the waste also had several uranium isotopes. Five shipments totalled just under 7 kg's of uranium; average enrichment varied from a low of 9.4% U-235 to a high of 68.7% although most drums contained normal or depleted uranium and sometimes both. LATA (Judy Pottmeyer) just completed a trip to Vallecitos to collect data on the later TRU waste material.

[15] From: Wilbur O Greenhalgh at -WHC220 5/7/93 11:33AM (808
To: Dale M Johnson at -WHC288, Darrel R Duncan at -WHC177
Subject: Purex Waste Characteristics

----- Message Contents -----

Jim Hilliard is the present Waste Coordinator for Purex. We are currently looking at what records he has available. The Pu-240 isotopics is primarily 6 or 12%. Most of the waste appears to be 6% material from N reactor when its mission was to make defense plutonium. The balance is 12% (actually 12.9%) also from N when the emphasis was on power production! Most of the early material appears to be defense plutonium and the later fuel appears to have alot of the power material.

[12] From: Wilbur O Greenhalgh at -WHC220 5/3/93 12:56PM (.
To: Dale M Johnson at -WHC288, Darrel R Duncan at -WHC177, James A (Jim) Demiter
at -WHC288, James A (Jim) Hunter
Subject: Fuel Questions

----- Message Contents -----

Here is a follow-on note about N-Reactor fuel. As I mentioned on the phone, the reactor was placed on cold-standby on Oct. 1989. However, production of plutonium was terminated in 1987. The oldest N-fuel received at Purex for processing was removed from the reactor on Jan. 14, 1987!

Note on the Isotopic Content of GE Vallecitos Waste: The waste material received from Vallecitos during the 1974 time frame had the following characteristics if the records I have are complete: The waste had a total Pu content of about 5235 grams of which 4773 (91%) was designated as Pu-239. About 73% of the plutonium material was 8.3% Pu-240 isotopic content, 6% was 10.0% and 21% was 7.0% Pu-240 content. The 8.3% plutonium corresponds with the isotopic content typically used at the PRTR reactor in the 300 Area. The Plutonium Recycle Test Reactor (PRTR) was in operation from 1960 until at least mid 1967, but I don't know what if any connection/association there was between the facilities.

[27] From: Wilbur O Greenhalgh at -WHC220 5/18/93 1:54PM
 To: Darrel R Duncan at -WHC177, Dale M Johnson at -WHC288, John W Biglin,
 James A (Jim) Hunter, Marnelle L Sheriff at -WHC288, James A (Jim) Demiter at
 -WHC288

Subject: Trench 4 Characteristics Update-Letter No. WOG-93-008

----- Message Contents -----

Ed Veyvoda of LATA visited GE Vallecitos last week and
 picked up the TRU waste generating data from the late
 seventies and early eighties. A summary table is given
 below with all of the wide varieties of Pu-240 isotopes:

GE Vallecitos TRU Waste Summary
 (1979-1984)

Pu Content (g)	Pu-239 Content (g)	Pu-240 Isotopic %	% of Total
150	138	7.00	2.4%
1613.52	1436.37	10	26.0
2793	2458	12	44.9
1262.99	1113.35	15.5	20.3
115.12	37.96	23.5	1.9
25	12	47	0.4
41	20	49	0.7
29	15	55	0.5
144	93	70	2.3
44	27	60	0.7
6217.63	5401.13	13.1	100.1 Totals

Most of the plutonium material was 12% Pu-240 or below.
 However, there are some quantities of high exposure
 material. In addition to plutonium there was also uranium
 present including depleted, normal, and enriched uranium
 fractions. This information can be made available if
 needed. In addition, a file with the Trench 4 generators
 and the approx. time of shipments is included to help
 assimilate generator information.

Thanks

Wilbur

Pacific Northwest Laboratories
Bartlett Boulevard
P.O. Box 399
Richland, Washington 99352
Telephone 509/ 376-0405

February 2, 1993

Wilbur O. Greenalgh
Westinghouse Hanford Company
P. O. Box 1970
Mail Stop L5-31
Richland, WA 99352

Dear Mr. Greenalgh:

FISSION/ACTIVATION PRODUCTS IN 234-5Z BARRELS USING PNL BARREL ASSAY SYSTEM

The PNL Barrel Assay System employs high-resolution (HPGe) segmented gamma-ray scanning and passive neutron counting to characterize the contents of 55-gal (208-L) waste drums. A total of 452 waste drums were analyzed at the 234-5Z Plant during the period of August 18 through September 12, 1991. Typically, the only β - and γ -emitting non-transuranic (TRU) radionuclides seen were ^{60}Co , ^{137}Cs , and ^{154}Eu . The levels of activity were usually below background (as measured with an empty drum) so that only upper-limit values were reported.

However, an occasional drum contained measurable fission and/or activation products. Enclosed are summaries of information on waste drums that contained levels of ^{60}Co , ^{137}Cs , and/or ^{154}Eu in excess of background. The measured value, in units of $\mu\text{Ci/g}$, is highlighted.

The concentrations of ^{60}Co , ^{137}Cs , and ^{154}Eu reported in the enclosed tables are all extremely low and of several potential origins. First, ^{60}Co concentrations of this order are frequently encountered in new, empty steel drums. Most post-atomic age steel contains measurable ^{60}Co introduced in the steelmaking process. Another potential source of the ^{60}Co is from activation of cobalt in metal forms contained in the drums. If the drums contain scrap metals from equipment which was in proximity to significant quantities of plutonium for extended periods of time, the neutrons emitted in spontaneous fission of ^{240}Pu and other plutonium isotopes, or from (α, n) reactions on light isotopes, could have activated enough cobalt in the metals to produce these measurable quantities.

The reported values for ^{137}Cs are likely due to some combination of three possible sources. Many of the reported numbers are likely either wholly or in part artifacts of the presence of ^{241}Am . The major high-energy gamma ray present in the decay of ^{241}Am is at the same energy as the only gamma ray from ^{137}Cs . Since the concentrations of ^{241}Am in these drums exceeds that of ^{137}Cs by as much as six orders of magnitude, a very small error in the assignment of gamma-ray peak intensities by the software used for data reduction can result in residuals erroneously reported as ^{137}Cs . Another contributor to the presence of ^{137}Cs is worldwide fallout from nuclear weapons testing and the Chernobyl accident. Finally, some of the ^{137}Cs present is undoubtedly due to

W. O. Greenhalgh

Page 2

February 2, 1993

accumulation of spontaneous fission product activity from old sources of ^{240}Pu . This is clearly demonstrated by the two drums which contain measurable quantities of ^{134}Eu . These two drums contain gram quantities of plutonium, and the ^{134}Eu in these drums is certainly an accumulation of spontaneous fission product activity during the significant time lapse following the last purification of the plutonium.

For the drums reported in the enclosed summary sheets, the WHC drum identification was provided at the time of counting. A unique PNL run number and the net weights are also provided on the enclosed summary sheet.

The summaries are divided into three classes: 1) barrels that contained no detectable TRU activity, 2) barrels in which only ^{241}Am was detectable, and 3) barrels that contained detectable Am and Pu. The following table summarizes the number of barrels containing fission and/or activation products that were identified in the three classes of barrels:

Barrel Classification	Total No. of Barrels in Class	No. of Barrels with Fission/Activation Products
No Detectable TRU	150	4
Only ^{241}Am Detected	171	19
Barrels With No. Am. Pu	131	17
Totals	452	40

Any questions may be directed to me at Mail Stop P8-08, by cc:Mail, by FAX at 376-2329, or by phone at 376-0405.

Sincerely,

Richard J. Arthur
Sr. Research Scientist

Enclosures (3)

cc w/enclosures:
RL Brodzinski, P8-07
DE Robertson, P8-01
File /LB

234-5Z Barrels With No Detectable TRU

WHC Drum ID	RHZ-110-A20832	RHZ-112-A21727	RHZ-211-A21180	RHZ-211-A20989
PNL Run #	91091123	91090902	91090923	91083005
Net wt. (kg)	22.7	27.2	37.2	40.3
Co-60 (pCi/g)	12	0.7	0.7	3.2
Cs-137 (pCi/g)	< 1.3	< 1.3	< 1.2	< 1.0
Eu-154 (pCi/g)	< 10	< 5	< 5	< 5

234-5Z Barrels With Detectable Am-241 Only

WHC Drum ID	RHZ-211-A21199	RHZ-211-A20087	RHZ-211-A21134	RHZ-211-A21326
PNL Run #	91090803	91090906	91090920	91090924
Net wt. (kg)	16.3	24.3	30.7	42.6
Co-60 (pCi/g)	3.2	4	0.7	0.6
Cs-137 (pCi/g)	< 1.1	< 1.1	< 0.5	< 0.7
Eu-154 (pCi/g)	< 10	< 7	< 4	< 3

WHC Drum ID	RHZ-211-A21140	RHZ-211-A13179	RHZ-211-A21717	RHZ-211-A20263
PNL Run #	91091117	91091140	91091216	91090431
Net wt. (kg)	33.6	34	38.1	27.2
Co-60 (pCi/g)	1	< 1.1	3.5	1.3
Cs-137 (pCi/g)	2.4	2.7	< 0.9	< 1.0
Eu-154 (pCi/g)	< 6	< 6	< 6	< 7

WHC Drum ID	RHZ-212-A19924	RHZ-212-A21837	RHZ-212-A21345	RHZ-212-A21915
PNL Run #	9108203	91082215	91082101	91082110
Net wt. (kg)	15.9	24.3	22.7	29
Co-60 (pCi/g)	1.2	< 1.4	4.6	9.2
Cs-137 (pCi/g)	< 1.5	4.5	< 1.3	< 1.0
Eu-154 (pCi/g)	< 10	< 7	< 3	< 3

WHC Drum ID	RHZ-212-A21350	RHZ-212-A21674	RHZ-212-A21344	RHZ-220-A20366
PNL Run #	91082113	91082115	91082121	91090402
Net wt. (kg)	20	17.2	54.4	29
Co-60 (pCi/g)	4.3	10	< 0.7	2
Cs-137 (pCi/g)	3.5	< 1.3	0.9	< 1.0
Eu-154 (pCi/g)	< 9	< 10	< 3	< 6

WHC Drum ID	RHZ-211-A20085	RHZ-220-A13816	RHZ-220-A13857
PNL Run #	91090408	91090411	91090301
Net wt. (kg)	27.7	35.3	29
Co-60 (pCi/g)	4.5	11	11
Cs-137 (pCi/g)	< 1.0	< 1.3	3.3
Eu-154 (pCi/g)	< 7	< 7	< 3

234-5Z Barrels With Detectable Pu & Am

WHC Drum ID	RHZ-212-A13526	RHZ-241-A13014	RHZ-211-A21710	RHZ-213-A21684
PNL Run #	91091035	91091036	91091123	91091207
Net Wt. (kg)	34	32.2	56.2	52.5
Co-60 (pCi/g)	9.4	< 0.3	< 0.3	9.5
Cs-137 (pCi/g)	< 1.2	10	3.2	< 1.1
Eu-154 (pCi/g)	< 3	< 3	< 3	< 3

WHC Drum ID	RHZ-211-A21731	RHZ-212-A21723	RHZ-213-A21738	RHZ-220-A13382
PNL Run #	91090806	91090808	91090901	91090908
Net Wt. (kg)	40.3	19.1	38.1	33.5
Co-60 (pCi/g)	< 0.7	1.7	1.6	< 1.3
Cs-137 (pCi/g)	1.2	< 1.4	< 0.9	1.9
Eu-154 (pCi/g)	< 6	< 9	< 7	< 7

WHC Drum ID	RHZ-211-A21541	RHZ-212-A13810	RHZ-211-A21542	RHZ-212-A13547
PNL Run #	91090502	91083009	91083013	91090206
Net Wt. (kg)	104.3	29.9	106.1	33.1
Co-60 (pCi/g)	< 0.3	6.2	< 0.3	1.9
Cs-137 (pCi/g)	2.3	5.2	2	1.3
Eu-154 (pCi/g)	2.4	< 3	< 4	< 7

WHC Drum ID	RHZ-220-A13443	RHZ-211-A21531	RHZ-212-A21755	RHZ-212-A21401
PNL Run #	91090208	91090306	91090312	91082017
Net Wt. (kg)	39.9	73.9	72.1	39.3
Co-60 (pCi/g)	1.5	< 0.4	< 1.2	< 1
Cs-137 (pCi/g)	< 0.9	0.7	< 1.4	2
Eu-154 (pCi/g)	< 5	< 4	6.4	< 10

WHC Drum ID	RHZ-213-A21543
PNL Run #	91082013
Net Wt. (kg)	22.2
Co-60 (pCi/g)	< 2
Cs-137 (pCi/g)	2.3
Eu-154 (pCi/g)	< 10

Battelle

Pacific Northwest Laboratories
Battelle Boulevard
P.O. Box 399
Richland, Washington 99352
Telephone (509) 375-0405

March 18, 1990

Wilbur O. Greenhalgh
Westinghouse Hanford Company
P. O. Box 1970
Mail Stop L5-31
Richland, WA 99352

Dear Mr. Greenhalgh:

FISSION/ACTIVATION PRODUCTS IN 234-5Z BARRELS USING PNL BARREL ASSAY SYSTEM

This letter is a follow-up to one previously sent on February 2, 1990, regarding the presence of fission and activation products in waste barrels from the 234-5Z Plant. As mentioned before, the PNL Barrel Assay System employs high-resolution HPGe segmented gamma-ray scanning and passive neutron counting to characterize the contents of 55-gal 208-g waste drums.

Several waste drums and HEPA filters have been assayed since the Barrel Assay System was implemented in 1988. In going over past data summaries, however, it appears that TRU content, as measured with the passive neutron counter, was of greater concern than gamma-ray activity, so that we are unable to provide you with much additional information.

I was able, however, to find gamma-ray data on a series of 3 drums analyzed at the 234-5Z Plant on October 2, 1989. There were no indications of the presence of fission or activation products, such as ^{60}Co , ^{137}Cs , and/or ^{137}Ba .

Please feel free to direct any further questions to me at Mail Stop P8-08, by FAX at 375-2329, or by phone at 375-0405.

Sincerely,

Richard J. Arthur
Sr. Research Scientist

cc:
RL Brodzinski, P8-07
DE Robertson, P8-01
File /LB

Battelle

Rev. 0

Page 460

Pacific Northwest Laboratories
Battelle Boulevard
P.O. Box 399
Richland, Washington 99352
Telephone (509) 376-0405

March 22, 1993

Albour J. Greenhalgh
Westinghouse Hanford Company
P.O. Box 1970
Mail Stop L5-31
Richland, WA 99352

Dear Mr. Greenhalgh:

FISSION/ACTIVATION PRODUCTS IN 234-5Z BARRELS USING PNL BARREL ASSAY SYSTEM

This letter is a follow-up to two previous letters regarding the presence of fission and activation products in waste barrels from the 234-5Z Plant: the first letter was sent on February 2, 1993, and the second was sent March 13, 1993.

I located a memo dated August 1, 1988, from Ron Brodzinski to Grady Cox regarding "234-5 Waste Drums Analyzed 7/15-31/88". The memo describes the transuranic (TRU) content of 29 waste barrels, of which 7 were also counted by high-resolution germanium spectroscopy. Only 3 of the 7 contained positive photopeaks from TRU isotopes. No evidence of fission or activation products were indicated.

Please feel free to direct any further questions to me at Mail Stop P8-08, by FAX at 376-2329, or by phone at 376-0405.

Sincerely,

Richard J. Arthur
Sr. Research Scientist

cc:
RL Brodzinski, P8-07
DE Robertson, P8-01
File /LB

From: Engineering Demonstration
Phone: 3-1583/234-SZ Trl. #4
Date: January 28, 1981
Subject: I-PLANT WASTE VS MEGAS

Hanford Engineering Development Laboratory

Letter 4

WHC-SD-W113-ACDR-001
Rev. 0
Page 461

To: J. P. Allen

cc: J. Berglund
R. G. Cowan
J. A. Demiter
P. C. Ely
W. O. Greenhalgh
R. E. Larch
MDC/File/L3

Over the past several years, I-Plant has sent about 20 drums/wk to TRU retrievable storage. About half of this is either noncombustible, "old waste" (several years), or is material from other sites that was sent to Hanford for storage. None of this is suitable for MEGAS in its present form. Based on their records of the last 3 months, the remaining half has the following breakdown:

331 drums measuring 10" PL
20 drums measuring 12" PL
45 drums measuring 2' or more g PL
446 drums total

The averages are:

1.23 shipments/wk
3.41 drums/shipment
1.98 drums/wk
1.19 drums of 10" shipment
3.13 drums of 10" wk
1.28 drums of 2' or more g PL shipment
1.66 drums of 2' or more g PL week

Examination of the MEGAS log for the last 3 months of its life revealed 134 boxes counted of which only 9 showed above 10 nCi/g. That is an average of 4.39% so 95% of the combustibles seem suitable for non TRU landfill. One could use 90% for this figure to be very conservative. A little computation gives the following table:

Basis. 1 week and 95% of "0" drums are <10 nCi/g. (xxx) indicate amounts > 90% of "0" drum are <10 nCi/g.

From I-Plant to MEGAS

3.03 drum reading "0" g Pu
1.66 drum reading "1 or more" g Pu

4.69 drum total

From MEGAS

non TRU
landfill

to RACTU

3.33 drums 1.66 (1.66) drums of "1 or more" g Pu
0.46 (0.93) drums >10 nCi/g Pu

(3.36) drums 2.12 (2.59) drums total

This indicates that it would take several months to accumulate enough I-Plant waste for a run. Specifically, we ran the equivalent of about 5 drums/day. I am assuming that the drums they send to burial are about twice the density of the boxes they send to us, so 10 weeks of MEGAS operation would give us about enough for a 5 day run. There is one kicker in the situation. They do occasionally "19 out of 449" have drums over 20g of Pu, in fact, up to the 100-150g range. As long as we are an isolated facility, it would be difficult for us to accept these.

In conclusion, it would appear that we would easily handle all the I-Plant newly generated combustible waste without undue strain on our resources. Most could be screened by the MEGAS and sent to "landfill" and the remainder easily processed in RACTU on an occasional run basis. We must also take care to clearly define to those outside our group exactly what waste we are capable of processing thru MEGAS, RACTU.

M. D. Gribben
Engineering Demonstration

kgm

WMC-SD-M113-ACDR-001
Rev. 0
Page 462A

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX C

Weather Enclosure Key Drivers

THIS PAGE INTENTIONALLY LEFT BLANK

Westinghouse Hanford Company
Solid Waste Operations Complex
W-113 - Solid Waste Retrieval Facility
(Phase 1)
Weather Enclosure Key Drivers

Letter Report
Revision 1a
17 July, 1993

Robin K. Hicks
Christopher F. Haecker

Los Alamos Technical Associates

THIS PAGE INTENTIONALLY LEFT BLANK

Introduction

The Solid Waste Retrieval Phase I (W-113) is a Westinghouse Hanford Company (WHC) planned pilot program to retrieve suspect transuranic (TRU) waste retrievably stored at the Hanford Site 200 West Solid Waste Burial Ground (SWBG). Trench 04 of burial ground 218-W-4C has 19 "modules" and contains ten thousand 55-gallon drums, fifty seven 110-gallon drums, and thirty-eight boxes. The planned retrieval rate is about three thousand drums per year. The retrieval operation consists of: removal of overburden from the trench and storage modules, retrieval of stored containers, collection of drum head gas samples, overpacking of retrieved containers, examination of the overpacked containers by assay and x-ray, coding, storage of characterization data generated, and preparation of the retrieved suspect TRU waste packages for transport.

The Functional Design Criteria (FDC) calls for a weather enclosure structure to be constructed over the trench after the main overburden removal. The justification for this weather enclosure has been questioned in the project funding review, and several studies have been conducted to determine its necessity. Regulatory, safety, production and economics have been put forth in previous studies and documents as justification for a trench enclosure. When the FDC was prepared there were many unknowns, and an effort was made to cover all contingencies. It was not then known whether or not the spread of contamination would be an issue, and there were provisions for a containment enclosure as well as an operations enclosure. In several instances the earlier positions are moot due to subsequent developments, such as the decision to remove the nondestructive assay/nondestructive examination (NDA/NDE) facility and place the NDA/NDE with the drum venting operations at the trench.

Objective

The objective of this letter report is to review and rationalize key drivers for a weather enclosure over the retrieval trench in Project W-113. This report examines the information presented in previous studies and evaluates the need for a weather enclosure based on proposed operations. Information presented in the source documents is not repeated herein unless absolutely necessary for clarity.

Regulatory Drivers

Federal Safety regulations, as well as State, local and WHC rules and requirements, do not require any enclosure for this type of operation.

There are, however, very specific requirements that may have to be followed if the enclosure is designed as a building structure. These requirements are contained in several Federal Standards including 29 CFR 1910 (OSHA) and DOE 6430.1A and include not only safety but design requirements that can have a substantial impact on overall costs. A waiver from DOE 6430.1A may be sought on the basis that the weather enclosure should be categorized the same as a temporary construction shelter.

Safety Drivers

One safety issue is the spread of contamination and the impact of this contamination on the public and the environment. A Preliminary Safety Evaluation has determined that a containment structure is not required.

Another safety issue involves the personal safety of the workers in the trench during retrieval operations. Field personnel have a preference for using a weather enclosure and feel that it will improve industrial safety performance. This is a fairly subjective area and is difficult to evaluate. The premise here appears to be that if the workers are in a climate controlled environment they will work more safely. This has merit but is not quantified. The safety hazards created by the use of an enclosure also should be considered. The limitations placed on the workers inside the trench because of the physical constraints of the enclosure itself and the inability to freely operate their equipment could have a negative impact on worker safety.

Limitations on the retrieval operation due to the presence of an enclosure are to be considered in the design of the enclosure. From a safety standpoint, the advantage of operating in the open is the ability to move materials in a smooth flow and unobstructed manner. There is also the freedom to move equipment around the perimeter rim of the trench without the safety restrictions required for safe clearances between the enclosures walls and ceiling. It now has been decided that diesel fueled heavy equipment such as 20 ton fork trucks can be operated on a limited basis in the trench, thereby eliminating the necessity of a gantry crane for large box retrieval. This reduces the complexity of safe equipment access and material handling during normal retrieval operations.

Weather conditions that have an impact on the safety of the workers have already been incorporated in the criteria that limits workable shifts. These conditions are described in Appendix B.

Based on protection of the public and environment, and the safety of the occupational worker, sufficient justification is not available to support the use of the weather enclosure.

Production Drivers

Four production alternates that have been fully evaluated in this report.

	MONTHS	SHIFTS	ENCLOSURE	HEAT
B	All	Day	None	None
D	May-October	Graveyard Day	None	None
F	All	Day	Weather	None
G	All	Day	Weather	35°F minimum

Alternates B, D, F and G are developed fully in Appendix A, Weather Data Analysis. The normal year round day shift baseline is compared to the most productive open air alternate, a work schedule of graveyard and day shifts from May through October, as well as operating a year round day shift in unheated and heated enclosures in the chart below. These retrieval rates are based on a 7 day work week using a flexible

shift schedule. If a 7 day work week cannot be staffed the retrieval rates must be downgraded proportionately. The average drum retrieval rate is assumed to be 16 drums per 8 hour shift. The impact of box retrieval on drum retrieval rates was not considered, however, the impact will be proportional to all of the alternates.

The normal weather scenario is an average based on the analysis of 31 years of actual weather data by Pacific Northwest Laboratories (PNL). The poor and good weather scenarios are described in detail in Appendix A and are intended to demonstrate the impact of abnormal weather.

A heated or unheated weather enclosure would not eliminate all weather disruption to the production schedule, although this factor is not taken into account in the retrieval rate comparison. The weather enclosure is not proposed for the initial overburden removal part of the retrieval effort and this activity may be difficult to accomplish during the winter. Many of the inclement weather days also may impact other operations on the Hanford Site and, even though operations may be able to continue under the enclosure, the retrieval operation may still be impacted due to the inability to move the drums out of the enclosure.

Drum venting and NDA/NDE operations are no longer considered constraints on drum retrieval rates.

A weather enclosure for the trench retrieval activity mitigates production risk by minimizing the impact of inclement weather that is worse than normal, similar to that occurring during the summer and winter of 1992. A weather enclosure would allow the acceleration of the retrieval schedule if other parts of the drum handling and treatment system are able to handle the larger annual throughput rates.

Economics

The underlying assumptions are that shifts are scheduled and staffed on a systematic basis and that the shift labor cost is incurred regardless of whether or not the shift is workable. As labor utilization decreases due to weather shutdowns the actual direct labor cost is proportionately increased. The NDA/NDE and drum venting personnel (6 per shift) are included in the economic evaluation because no buffer accumulation is included that would allow these activities to continue without concurrent drum retrieval.

An average shift cost of \$6,000 for direct labor, based on a crew size of 15, including NDA/NDE and drum venting, equates to a theoretical average direct labor cost of \$500 per drum if the retrieval is done in an unsheltered environment. This is based on working 2 shifts from May through October. Working a conventional 1 shift (day) schedule in an unsheltered environment results in an average direct labor cost of \$635 per drum. Providing unheated weather shelter decreases the average to \$452 and providing heat to the workers drops the average to \$377.

Using the normal weather scenario shown in the figure above, the economic benefit of an unheated weather enclosure is \$1,830,000 based on the reduction in direct labor cost from \$635/drum to \$452/drum for 10,000 drums. The economic benefit of providing 35°F minimum heating for the workers in the enclosure is \$750,000 taking credit for the further reduction from \$452/drum to \$377/drum.

If Alternate D, retrieving on day and graveyard shifts May - October, can be effected at the same shift crew size and cost and without additional operating cost for other Solid

Waste Operating Complex facilities, the economic benefit of an unheated weather enclosure is \$510,000 based on the reduction in direct labor cost from \$503/drum to \$452/drum for 10,000 drums. The economic benefit of providing 35°F minimum heating for the workers in the enclosure is also \$750,000.

Conclusions and Recommendations

Regulatory requirements and safety considerations are not justifiable drivers for a weather enclosure. Any weather enclosure utilized must be designed such that equipment access and clearances and material handling and staging are accommodated without creating safety hazards.

Production and economics drivers do justify some degree of weather protection for the trench retrieval operations. A weather enclosure will reduce production rate risk and direct labor cost risk attributable to the impact of seasonal weather patterns that are much worse than the 31 year averages. It is recommended that a weather enclosure be funded at a life cycle cost of \$1,330,000 and that a worker heating system be funded at a life cycle cost of \$750,000.

These economic benefit levels are substantially less than the funding required for the FDC trench enclosure building. Value engineering of an enclosure should prove these amounts to be adequate if the functional requirements are kept to the basics of preventing wind speeds in the retrieval trench of greater than 15 miles per hour, excluding visible precipitation from the work face area, and heating the work face area to 35 °F. The enclosure does not have to be dust and water tight and should be easily transportable.

Source documents

This letter report is based on information found in the following source documents:

- Independent Cost Estimate, Foster Wheeler Enviresponse, November, 1992
- WHC-SD-W113-ES-002, Engineering Study
- WHC-SD-W113-FDC-001, Functional Design Criteria
- WHC-SD-W113-HC-002, Hazard Classification
- Engineering Study, "Solid-Waste Retrieval Facility, Phase 1," Project W-113, 1991, Kaiser Engineers Hanford
- Engineering Report, "Weather Enclosure Life Cycle Cost Analysis", Project-W-236, 1992, Kaiser Engineers Hanford
- Draft Unpublished Report, "Evaluation of Need for a Weather Enclosure for Removal of TRU Drums from Trench 4", J. A. Teal, WHC, July 10, 1993
- Letter, R. J. Roberts, WHC to J. M. Hennig, RL, "Review of Solid Waste Operations Complex (SWOC) Phase I (Project W-306)", 9302467B R1, March 31, 1993
- Independent Review of the Westinghouse Hanford Company Solid Waste Operations Complex Review, MAC Technical Services, April 19, 1993
- WHC-SD-W113-PSE-001, Rev. 0, ECN 173277 and ECN 173298, Preliminary Safety Evaluation

APPENDIX A
WEATHER DATA ANALYSIS

Data extracted from the PNL weather data sort source listing is used for spreadsheet analysis and graphic representation. The 4-hour rejection criteria data is used as the baseline input. The 1-hour rejection criteria eliminates shifts that may, in reality, be mostly workable.

The initial objective of the data analysis is to identify the most productive seasonal and shift alternate for working in the opening without any weather enclosure. This best alternate is then compared to production and direct labor costs for unheated weather enclosure and heater weather enclosure alternates.

The PNL reject numbers are first converted into pass numbers and percentages for presentation as a graphic "radar chart". The Workable Shift plots for Graveyard, Day and Swing Shifts on pages 3-5 illustrate the seasonal influence of the wind, temperature and moisture elements. It is obvious, for example, that wind speed is the major inhibitor to workable conditions for the swing shift (1600-2400) the spring and summer. It is also obvious that winter is the least workable period due primarily to temperature and moisture. No great revelation to those readers that live in the Hanford climate, but an affirmation of the general validity of the PNL data.

Workable shifts, drum retrieval rates and direct labor cost per drum on an annualized basis are tabulated for seven alternates on pages 5-12. Retrieval is assumed to be sixteen (16) drums per workable shift (with or without enclosure). Shift cost is assumed to be \$6,000 based on a crew size of fifteen (15) and a fully burdened labor rate of \$50/hr. Workable and Manned shifts are computed on the basis of a 365 day year, 7 day week, assuming retrieval staff can be scheduled on a flexible shift basis.

The seven alternates considered are:

	MONTHS	SHIFTS	ENCLOSURE	HEAT
A	All	Graveyard	None	None
B	All	Day	None	None
C	All	Swing	None	None
D	May-October	Graveyard Day	None	None
E	Apr-October Nov-Mar	Graveyard Day	None	None
F	All	Day	Weather	None
G	All	Day	Weather	35°F minimum

Alternate D, working two "fair weather" shifts during the May-October period, shows the highest annual retrieval rate and lowest direct labor cost of the five open air environment schedules considered. Alternate B, working the day shift year round, is the most productive non-flexible schedule in an unsheltered environment. Annual drum retrieval rates and direct labor costs are summarized in charts presented on page 13.

The charts on pages 14-18 present direct labor costs and annual retrieval rates in a three scenario sensitivity analysis. Poor and good weather scenarios are postulated for comparison to the "normal" weather year, which is based on the 31 year average conditions. Specific assumptions on the poor and good weather scenarios are described with the tables and charts.

GRAVEYARD	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
Total Shifts	1147	1045	1147	1110	1147	1110	1147	1147	1110	1147	1110	1147
4 Hr. Wind Speed Reject	160	156	214	237	259	245	252	153	170	143	158	182
4 Hr. Temperature Reject	358	300	340	51	0	0	0	0	0	77	329	337
4 Hr. Moisture Reject	400	255	125	72	35	54	22	34	41	107	459	494
4 Hr. Non-Workable Shifts	1045	341	361	373	345	301	290	192	221	329	791	1059
4 Hr. Wind Speed Pass	987	889	933	873	888	865	895	994	940	1004	942	965
4 Hr. Temperature Pass	289	445	807	1059	1147	1110	1147	1147	1110	1070	73	310
4 Hr. Moisture Pass	747	790	1022	1038	1062	1056	1125	1113	1069	1040	351	653
4 Hr. Workable Shifts	102	204	486	737	802	809	867	954	889	813	313	83
4 Hr. Wind Speed Pass	36%	35%	31%	79%	77%	73%	78%	87%	35%	38%	35%	34%
4 Hr. Temperature Pass	25%	43%	70%	95%	100%	100%	100%	100%	100%	93%	70%	27%
4 Hr. Moisture Pass	65%	76%	89%	94%	93%	95%	98%	97%	96%	91%	59%	57%
4 Hr. Workable Shifts	9%	20%	42%	66%	70%	73%	76%	83%	80%	71%	29%	3%

WORKABLE SHIFTS GRAVEYARD 2400 - 0800

DAY	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
Total Shifts	1147	1045	1147	1110	1147	1110	1147	1147	1110	1147	1110	1147
4 Hr. Wind Speed Reject	211	253	366	362	295	258	205	178	238	249	251	223
4 Hr. Temperature Reject	300	199	29	0	2	5	58	40	0	6	17	577
4 Hr. Moisture Reject	283	152	31	55	7	47	21	28	35	56	233	406
4 Hr. Non-Workable Shifts	365	542	458	422	366	320	286	243	259	314	565	388
4 Hr. Wind Speed Pass	936	792	781	748	852	842	942	969	872	898	859	924
4 Hr. Temperature Pass	547	846	1119	1110	1145	1105	1089	1107	1110	1141	939	570
4 Hr. Moisture Pass	864	893	1066	1054	1075	1063	1126	1119	1075	1091	877	741
4 Hr. Workable Shifts	282	503	689	688	781	790	861	904	841	833	545	261
4 Hr. Wind Speed Pass	82%	75%	68%	67%	74%	76%	82%	84%	79%	78%	75%	81%
4 Hr. Temperature Pass	48%	81%	98%	100%	100%	100%	95%	97%	100%	99%	85%	50%
4 Hr. Moisture Pass	75%	85%	93%	95%	94%	96%	98%	98%	97%	95%	79%	65%
4 Hr. Workable Shifts	25%	48%	60%	62%	68%	71%	75%	79%	76%	73%	49%	23%

WORKABLE SHIFTS
DAY 0800 - 1600

SWING	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Total Shifts	1147	1045	1147	1110	1147	1110	1147	1147	1110	1147	1110	1147
4 Hr. Wind Speed Reject	202	220	362	489	597	542	567	569	370	250	210	190
4 Hr. Temperature Reject	758	393	1071	3	2	3	3	3	3	12	339	757
4 Hr. Moisture Reject	296	150	30	46	50	47	21	30	39	75	219	369
4 Hr. Non-Workable Shifts	379	373	564	558	547	587	599	598	412	331	358	399
4 Hr. Wind Speed Pass	945	825	785	621	550	568	580	578	740	897	900	957
4 Hr. Temperature Pass	389	652	1040	1107	1145	1110	1147	1147	1110	1135	1110	1190
4 Hr. Moisture Pass	361	895	1067	1064	1097	1063	1126	1117	1071	1071	891	1110
4 Hr. Workable Shifts	168	367	583	552	500	423	448	549	698	816	452	143
4 Hr. Wind Speed Pass	92%	79%	68%	56%	48%	42%	42%	50%	67%	78%	81%	83%
4 Hr. Temperature Pass	34%	62%	91%	100%	100%	100%	100%	100%	100%	99%	99%	94%
4 Hr. Moisture Pass	75%	86%	93%	96%	96%	96%	98%	97%	96%	93%	80%	68%
4 Hr. Workable Shifts	15%	35%	51%	50%	44%	38%	39%	48%	63%	71%	41%	13%

WORKABLE SHIFTS
SWING 1600 - 2400

ALTERNATE A												
Graveyard Shift	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
Workable Shifts	3	5	13	20	22	22	23	25	24	22	31	31
Manned Shifts	31	28	31	30	31	30	31	31	30	31	30	31
Total Workable Shifts	31											
Retrieved Drums	3059											
Labor Cost/Drum	57.61											

ALTERNATE A
YEAR ROUND GRAVEYARD SHIF
NO ENCLOSURE

ALTERNATE 3													
Day Shift	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	
Workable Shifts	3	13	19	19	21	21	23	24	23	23	15	7	
Manned Shifts	31	29	31	30	31	30	31	31	30	31	30	31	
Total Workable Shifts	2161												
Retrieved Drums	3448												
Labor Cost/Drum	3635												

ALTERNATE 3
YEAR ROUND DAY SHIFT
NO ENCLOSURE

ALTERNATE C													
Swing Shift	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	
Workable Shifts	5	10	16	13	14	11	12	15	19	22	12	4	
Manned Shifts	31	29	31	30	31	30	31	31	30	31	30	31	
Total Workable Shifts	154												
Retrieved Drums	2465												
Labor Cost/Drum	\$888												

ALTERNATE C
YEAR ROUND SWING SHIFT
NO ENCLOSURE

ALTERNATE D													
2 Shifts/Summer	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	
Workable Graveyard Shifts	01	01	01	01	22	22	23	25	24	22	01	01	
Workable Day Shifts	01	01	01	01	21	21	23	24	23	23	01	01	
Workable Shifts	01	01	01	01	43	43	47	50	47	45	01	01	
Manned Shifts	01	01	01	01	62	60	62	62	60	62	01	01	
Total Workable Shifts	374												
Retrieved Drums	4389												
Labor Cost/Drum	\$503												

ALTERNATE D
GRAVEYARD AND DAY SHIFTS
SUMMER ONLY
NO ENCLOSURE

ALTERNATE E												
Seasonal Shift Change	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Workable Grave Shifts	0	0	0	20	22	22	23	25	24	22	0	0
Workable Day Shifts	3	13	19	0	0	0	0	0	0	0	15	7
Workable Shifts	3	13	19	20	22	22	23	25	24	22	15	7
Manned Shifts	31	29	31	30	31	30	31	31	30	31	30	31
Total Workable Shifts	220											
Retrieved Drums	3525											
Labor Cost/Drum	3621											

ALTERNATE E
SEASONALLY ADJUSTED
GRAVEYARD SHIFT SUMMER
DAY SHIFT WINTER
NO ENCLOSURE

ALTERNATE F													
Day Shift/Unheated Encl.	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	
Workable Shifts	9	20	31	30	31	30	30	30	30	31	21	31	
Manned Shifts	31	29	31	30	31	30	31	31	30	31	30	31	
Total Workable Shifts	302												
Retrieved Drums	4840												
Labor Cost/Drum	\$452												

ALTERNATE F
YEAR ROUND DAY SHIFT
UNHEATED ENCLOSURE

ALTERNATE G

Day Shift/Heated Encl.	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
Workable Shifts	31	28	31	30	31	30	30	30	30	31	30	31
Manned Shifts	31	28	31	30	31	30	31	31	30	31	30	31
Total Workable Shifts	363											
Retrieved Drums	5808											
Labor Cost/Drum	5977											

ALTERNATE G
YEAR ROUND DAY SHIFT
HEATED ENCLOSURE

The annual drum retrieval rates and direct labor costs are summarized below.

Alternates B (year round day shift), D (day and graveyard shifts during summer only), F (day shift in an unheated enclosure) and G (day shift in a heated enclosure) are considered in further evaluation.

The following sensitivity analysis looks at the impact of abnormal seasonal weather patterns. The normal weather year is based on the 31 year averages of actual weather history. The production and cost tables for the four alternates have been previously presented.

The impacts on production rates and direct labor costs of both poor and good weather scenarios are presented next.

The poor weather year approximates a hot, windy summer and a cold, snowy winter by assuming an arbitrary 80% of the normal weather year workable shifts for Alternates B and D (open air climates, year round day shift or summer day and swing shifts respectively). Alternate F downgrades the winter workable shifts to 80% of normal and deducts 8 shifts in the summer to account for higher temperature (wind is not a factor due to the enclosure). Alternate G downgrades the normal summer workable shifts by 8 to account for higher temperature (wind and low winter temperature are not factors due to the heated enclosure).

ALTERNATE B

Day Shift	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Workable Shifts	31	11	15	15	17	17	19	20	19	19	12	9
Manned Shifts	31	29	31	30	31	30	31	31	30	31	30	31
Total Workable Shifts	172											
Retrieved Drums	2758											
Labor Cost/Drum	\$794											

ALTERNATE D

2 Shifts/Summer	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Workable Shifts	0	0	0	0	34	35	37	40	37	36	0	0
Manned Shifts	0	0	0	0	62	60	62	62	60	62	0	0
Total Workable Shifts	219											
Retrieved Drums	3511											
Labor Cost/Drum	\$629											

ALTERNATE F

Day Shift/Unheated Encl.	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Workable Day Shifts	31	16	31	30	31	30	26	26	30	31	17	7
Manned Shifts	31	29	31	30	31	30	31	31	30	31	30	31
Total Workable Shifts	283											
Retrieved Drums	4526											
Labor Cost/Drum	\$484											

ALTERNATE G

Day Shift/Heated Encl.	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Workable Day Shifts	31	29	31	30	31	30	29	29	30	31	30	31
Manned Shifts	31	29	31	30	31	30	31	31	30	31	30	31
Total Workable Shifts	359											
Retrieved Drums	5744											
Labor Cost/Drum	\$381

The good weather year approximates a cool, mild summer with reduced winds and a relatively warm, dry winter by assuming an arbitrary 120% of the normal weather year workable shifts for Alternates B and D (open air climates, year round day shift or summer day and swing shifts respectively). Alternate F upgrades the normal winter workable shifts to 120% of and adds 4 shifts in the summer to account for milder temperature (wind is not a factor due to the enclosure). Alternate G upgrades the normal summer workable shifts by 2 to account for milder temperature.

ALTERNATE B

Day Shift	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Workable Shifts	31	36	22	22	25	25	28	39	27	27	18	3
Manned Shifts	31	28	31	30	31	30	31	31	30	31	30	31
Total Workable Shifts	259											
Retrieved Drums	4138											
Labor Cost/Drum	\$529											

ALTERNATE D

2 Shifts/Summer	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Workable Shifts	0	0	0	0	51	52	56	60	56	54	31	31
Manned Shifts	0	0	0	0	62	60	62	62	60	62	31	31
Total Workable Shifts	329											
Retrieved Drums	5267											
Labor Cost/Drum	\$419											

ALTERNATE F

Day Shift/Unheated Encl.	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Workable Day Shifts	11	24	31	30	31	30	31	31	30	31	25	11
Manned Shifts	31	28	31	30	31	30	31	31	30	31	30	31
Total Workable Shifts	317											
Retrieved Drums	5069											
Labor Cost/Drum	\$432											

ALTERNATE G

Day Shift/Heated Encl.	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
Workable Day Shifts	31	28	31	30	31	30	31	31	30	31	30	31
Manned Shifts	31	28	31	30	31	30	31	31	30	31	30	31
Total Workable Shifts	365											
Retrieved Drums	5840											
Labor Cost/Drum	\$375

APPENDIX B
SOURCE LISTING
WEATHER DATA SORT

Historical weather data collected by PNL at the 200W Area Weather Station between 1955 and 1991 was sorted using exclusionary criteria to identify the average number of workable shifts per month.

Shifts were rejected (not workable) if any one of the following criteria were not met for 1 continuous hour and 4 continuous hours during the shift period:

Wind Speed	maximum 15 miles per hour
Temperature	minimum 35 °F maximum 100 °F
Moisture	no measurable precipitation

AIIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIIM STANDARDS
BY APPLIED IMAGE, INC.

7 of 8

Month: January

Rejected Shift = 1 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave 2400-0800	1147	940	615	359	23
Day 0800-1600	1147	799	520	391	75
Swing 1600-2400	1147	350	499	402	45
TOTALS	3441	2589	1634	1152	143

Month: February

Rejected Shift = 1 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave 2400-0800	1045	719	443	371	49
Day 0800-1600	1045	402	349	453	209
Swing 1600-2400	1045	534	315	442	130
TOTALS	3135	1655	1107	1271	388

Month: March

Rejected Shift = 1 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave 2400-0800	1147	517	278	535	172
Day 0800-1600	1147	72	264	612	399
Swing 1600-2400	1147	242	205	691	270
TOTALS	3441	831	747	1838	841

Month: April

Rejected Shift = 1 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1110	163	187	581	323
Day					
0800-1600	1110	1	226	648	415
Swing					
1600-2400	1110	23	191	810	251
TOTALS	3330	187	604	2039	990

Month: May

Rejected Shift = 1 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	12	168	646	424
Day					
0800-1600	1147	5	213	632	459
Swing					
1600-2400	1147	3	201	370	233
TOTALS	3441	20	582	2148	1121

Month: June

Rejected Shift = 1 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1110	0	148	655	396
Day					
0800-1600	1110	26	164	610	455
Swing					
1600-2400	1110	15	161	884	203
TOTALS	3330	41	473	2149	1054

Month: July

Rejected Shift = 1 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	0	92	702	414
Day					
0800-1600	1147	151	80	533	499
Swing					
1600-2400	1147	118	72	396	213
TOTALS	3441	269	244	2131	1131

Month: August

Rejected Shift = 1 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	0	109	599	507
Day					
0800-1600	1147	113	96	463	571
Swing					
1600-2400	1147	75	95	320	294
TOTALS	3441	188	300	1382	1372

Month: September

Rejected Shift = 1 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1110	5	125	446	592
Day					
0800-1600	1110	3	110	469	599
Swing					
1600-2400	1110	1	112	637	445
TOTALS	3330	9	347	1552	1636

Month: October

Shift	Total Shifts	Hour(s) Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	176	263	383	451
Day					
0800-1600	1147	11	184	431	615
Swing					
1600-2400	1147	52	194	489	528
TOTALS	3441	239	641	1303	1594

Month: November

Shift	Total Shifts	Hour(s) Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1110	570	544	371	107
Day					
0800-1600	1110	309	422	422	283
Swing					
1600-2400	1110	455	407	433	139
TOTALS	3330	1334	1373	1226	529

Month: December

Shift	Total Shifts	Hour(s) Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	914	688	367	12
Day					
0800-1600	1147	756	620	386	70
Swing					
1600-2400	1147	851	598	382	31
TOTALS	3441	2521	1906	1135	113

Month: January

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	858	400	160	102
Day					
0800-1600	1147	600	283	211	282
Swing					
1600-2400	1147	758	286	202	168
TOTALS	3441	2216	969	573	552

Month: February

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1045	600	255	156	204
Day					
0800-1600	1045	199	152	253	503
Swing					
1600-2400	1045	393	150	220	367
TOTALS	3135	1192	557	639	1074

Month: March

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	340	125	214	486
Day					
0800-1600	1147	28	81	366	689
Swing					
1600-2400	1147	107	80	362	583
TOTALS	3441	475	286	942	1758

Month: April

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1110	51	72	237	737
Day					
0800-1600	1110	0	56	362	588
Swing					
1600-2400	1110	3	46	489	552
TOTALS	3330	54	174	1088	1977

Month: May

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	0	85	259	302
Day					
0800-1600	1147	1	71	295	781
Swing					
1600-2400	1147	2	50	597	500
TOTALS	3441	4	206	1151	2083

Month: June

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1110	0	54	245	809
Day					
0800-1600	1110	5	47	268	790
Swing					
1600-2400	1110	0	47	642	423
TOTALS	3330	5	148	1155	2022

Month: July

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	0	22	252	367
Day					
0800-1600	1147	58	21	205	361
Swing					
1600-2400	1147	0	21	567	448
TOTALS	3441	58	64	1124	2176

Month: August

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	0	34	153	954
Day					
0800-1600	1147	40	28	173	904
Swing					
1600-2400	1147	0	30	569	548
TOTALS	3441	40	92	900	2407

Month: September

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1110	0	41	170	889
Day					
0800-1600	1110	0	35	238	841
Swing					
1600-2400	1110	0	39	370	598
TOTALS	3330	0	115	778	2428

Month: October

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	77	107	143	313
Day					
0800-1600	1147	6	56	249	333
Swing					
1600-2400	1147	12	76	250	316
TOTALS	3441	95	239	642	2467

Month: November

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1110	459	329	163	319
Day					
0800-1600	1110	171	233	251	545
Swing					
1600-2400	1110	339	219	210	452
TOTALS	3330	969	731	539	1315

Month: December

Rejected Shift = 4 Rejected Hour(s)

Shift	Total Shifts	Shifts Rejected Temperature	Shifts Rejected Moisture	Shifts Rejected Wind Speed	Good Shifts
Grave					
2400-0800	1147	837	494	182	88
Day					
0800-1600	1147	577	406	223	261
Swing					
1600-2400	1147	757	369	190	148
TOTALS	3441	2171	1269	595	497

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX D

Solid Waste Projects
Nondestructive Assay/Nondestructive Examination Review

THIS PAGE INTENTIONALLY LEFT BLANK

Westinghouse
Hanford Company

*Kim, what was the
what was the
drive - for Revision 2?*

WHC-SD-W113-ACDR-001
Rev. 0
Page 499

From: Restoration Projects
Phone: 372-1443 H5-33
Date: July 28, 1993
Subject: SOLID WASTE PROJECTS NONDESTRUCTIVE ASSAY/NONDESTRUCTIVE EXAMINATION
REVIEW

87330-93 WPG-026
REVISION 2

To: J. G. Riddelle H5-33

cc: D. E. Ball G6-45
S. R. Briggs G6-47
W. H. Hamilton, Jr. N3-10
M. D. LeClair H1-60
D. R. Lucas G6-46
R. D. Pierce N3-13
R. J. Roberts N3-13
J. A. Swenson G6-45
J. R. Weidert G6-45
J. L. Westcott N3-13
Restoration Projects H5-33
WPG File/LB

The purpose of this letter is to document the results of the review of drum Nondestructive Assay (NDA) (acronyms are defined in attachment 1) and Nondestructive Examination (NDE) functions planned for solid waste programs to determine where gaps exist between requirements and capabilities and where duplications or unnecessary capabilities exist. The 85-gallon salvage drum and its Safety Analysis Report for Packaging (SARP) requirements were also considered. Since so little capability to perform NDA and NDE of boxes is required, this report addresses that subject only as it becomes involved with drum NDA decisions.

Summary

The various solid waste projects were reviewed for chemical and radionuclide information requirements; the sources which provide this information; whether they are adequate and what simplifications might be made.

The following projects were reviewed:

- W-113, Transuranic (TRU) Waste Retrieval
- W-112, Phase V Storage
- Waste Receiving and Processing (WRAP) 1
- WRAP 2A
- WRAP-2B
- Thermal Treatment Facility

Information requirements associated with the use of the 85-gallon salvage drum were also considered.

J. G. Riadelle
Page 2
July 28, 1993

87330-93-WPG-026
REVISION 2

Conclusions and Recommendations

The fixed NDE/NDA facility proposed for W-113 should be eliminated and replaced with mobile systems to use at the point of retrieval. The present scope of Project W-113 involves the retrieval of only a single trench and the expense of a permanent NDE/NDA facility cannot be justified. Mobile versions of the WRAP 1 Passive Active Neutron (PAN) NDA and Real Time Radiography (RTR) NDE systems will provide the information to satisfy project W-112 as well as WRAP 1 incoming waste requirements. The mobile PAN system will determine fissile loading of drums and satisfy the requirements of the 85-gallon drum SARP. The mobile PAN system, will also make TRU/Low Level Waste (LLW) determinations and will permit the option of leaving LLW drums in the trench. Gamma Energy Analysis (GEA) capability is not required at retrieval and can be eliminated completely. The cost saving in going from the fixed facility to mobile systems is of the order of \$4M.

WRAP 1 and W-113 have duplicate capability for the NDE and NDA of incoming retrieved waste. Since WRAP 1, the 85-gallon drum and Phase V storage all place NDA and NDE requirements on W-113, the duplication exists in WRAP 1 PAN and RTR capability. WRAP 1 will no longer be required to perform NDE or PAN NDA on incoming retrieved drums. Since the current time and motion study shows more than one shift per day required, this reduction in WRAP 1 requirements is insufficient to permit elimination of any existing capability. Incoming retrieved TRU drums, with more than about 10 grams of fissile equivalent, will still require WRAP-1 GEA NDA to help in making decisions to divide the contents of these more heavily loaded drums. Figure 1 Depicts Retrieval/Storage/WRAP 1 drum flow as presently planned and as proposed. A more detailed breakdown of resulting throughput requirements for WRAP 1 is contained on page 3 of Attachment 2.

Any and all information requirements for incoming WRAP-2A waste are satisfied by earlier certification/verification functions. No processing decisions require inline NDA or NDE. Classification of the output drums as MLLW 1 or MLLW 3 can be performed using data from the incoming containers. NDA to determine classification of these drums is, therefore, no longer necessary and the planned capability for WRAP 2A should be deleted.

New regulatory requirements may dictate output container contents verification using sampling and NDE/NDA. These functions can be performed using WRAP-1 capability. With WRAP-2A's output of about 10,000 drums per year, as many as 1,000 would have to pass through WRAP-1 NDA and NDE. This number of drums can be handled either by blending into normal operations or by off-shift campaigns. For the few drums that exceed the WRAP-1 thousand pound drum limit, the Box Waste Assay System will be used.

J. G. Riddelle
Page 3
July 28, 1993

87330-93-WPG-026
REVISION 2

WRAP 2B design is far too immature to define all of the NDA and NDE requirements. It is clear that outgoing NDA for Remotely Handled (RH) containers is required. Outgoing NDA for contact handled TRU drums may be satisfied by WRAP 1 capabilities. There is some uncertainty in the adequacy of the information that may be available for retrieved RH waste. The ongoing WRAP 2B work will define the requirements more fully and determine which existing capabilities can and should be used.

The Thermal Treatment Facility (TTF), as presently conceived, assumes NDA. Given the homogeneity of the ash and the fact that it must be characterized, drum contents can simply be calculated and NDA may be unnecessary. As the TTF conceptual design proceeds this issue will be resolved and it will be determined which existing capabilities can and should be used.

As future and presently planned solid waste projects evolve, rigorous evaluation of the requirements and needs for NDA and NDA capabilities will continue.

Figure 1 depicts drum flow as planned and as proposed.

The first attachment translates the acronyms used.

The second attachment documents the major aspects of the work that led to the above conclusions.

The third attachment provides a brief summary of the capabilities of the NDA and NDE systems addressed in this letter and in attachment 2.

W. P. Gilles, Principal Engineer
Restoration Projects

pss

Attachments 4

THIS PAGE INTENTIONALLY LEFT BLANK

Attachment 1 to Internal Memo, 87330-93-WPG-026 REVISION 2

**SOLID WASTE PROJECTS NONDESTRUCTIVE
ASSAY/NONDESTRUCTIVE EXAMINATION REVIEW**

Pages 1 through 1

THIS PAGE INTENTIONALLY LEFT BLANK

Attachment 1

Acronyms

DR	Digital Radiography
EPA	Environmental Protection Agency
FDC	Functional Design Criteria
GEA	Gamma Energy Analysis
MLLW	Low Level Mixed Waste
LLW	Low Level Waste
MW	Mixed Waste
NDA	Non Destructive Assay
NDE	Non Destructive Examination
NG	Newly Generated
PAN	Passive Active Neutron
PSAR	Preliminary Safety Analysis Report
RTR	Real Time Radiography
SAR	Safety Analysis Report
SARP	Safety Analysis Report for Packaging
TRU	Transuranic
TRUPACT	Transuranic Package for Transport
TSD	Treatment, Storage or Disposal
TTF	Thermal Treatment Facility
WAC	Waste Acceptance Criteria
WIPP	Waste Isolation Pilot Plant
WRAP	Waste Receiving and Processing
W-112	Phase V storage Project
W-113	Solid Waste Retrieval Facility. Phase 1

WHC-SD-W113-ACDR-001
Rev. 0
Page 503A

THIS PAGE INTENTIONALLY LEFT BLANK

Attachment 2 to Internal Memo, 87330-93-WPG-026 REVISION 2

**SOLID WASTE PROJECTS NONDESTRUCTIVE
ASSAY/NONDESTRUCTIVE EXAMINATION REVIEW**

Pages 1 through 15

THIS PAGE INTENTIONALLY LEFT BLANK

Attachment 2

Documentation of NDA/NDE Study

INTRODUCTION

The evaluation of the requirements for NDA and NDE for drum waste was performed in several steps. The first step in the study was to define the information required by solid waste projects as they treat, store and dispose of drums of waste. From this set of information requirements and the sources of those requirements, the necessity for NDA and NDE was developed. Planned solid waste programs and their inter-relationships were then reviewed. The planned NDA and NDE capabilities for each project were then compared and gaps and redundancies identified. Finally, recommendations were developed.

1.0 Information Requirements

Information describing the contents of radwaste container is required:

- To meet requirements as defined in the SARP when using the 85-gallon salvage drum or other waste shipping container

- To meet incoming storage facility requirements as defined in the facility SAR and WAC for storage location decisions

- To meet incoming processing facility requirements as defined in the facility SAR and by the need to make informed processing decisions

- To meet outgoing shipping/disposal requirements as defined in the shipping container SARP and Hanford WAC and WIPP-WAC for disposal

The required information is broken into four categories because different types of NDA, NDE or other tests are generally required to provide it. These categories are:

- Fissile gram loading:

 - At the low end, in terms of the 10 nCi/g and 100 nCi/g levels to define whether a waste is TRU or possibly LLW1 or LLW3.

 - For gram quantities and more for criticality safety considerations.

- Fission and activation product inventory which is required to determine whether a container of low level waste is to be classified as Category 1, 3 or >3.

- Dangerous content to identify if there is a potential for explosion or fire when a drum is handled, opened or emptied

- Hazardous content to identify if EPA regulated materials are present

2.0 Sources of Required Information

For waste coming into Hanford TSD facilities, this information comes from:

- Generator certification data for newly generated waste

- PAN NDA, NDE and in-trench head gas sampling, prior to placing a drum in an overpack for shipping

- NDA & NDE as required for process decisions in WRAP and TTF facilities

For newly generated waste which originates in WRAP and the TTF facilities:

- Certification of container contents for all outgoing waste is provided by the use of characterization information and:

 - Calculation of contents for homogeneous wastes

 - NDA & NDE for inhomogeneous wastes

3.3 Solid Waste Projects and NDA & NDE Capabilities

3.3.1 W-113 Retrieval

While W-113 in itself does not set any requirements for NDA or NDE, it does provide those services in response to the requirements of the 85-gallon drum SARP, W-112 and WRAP-1. Presently, W-113 provides an NDE/NDA facility with PAN and GEA NDA and RTR NDE for drums and portable NDA for boxes. Uncertainty in being able to correlate drums with burial records and limits on fissile gram loading for the 85-gallon drum tend to push for NDA prior to a drum being removed from the trench. The W-112 SAR requires knowledge of the hazardous and dangerous content of an incoming drum, as well as its fissile loading. The PAN NDA, RTR NDE and head gas sampling provide this information. Current safety requirements as addressed in the WRAP-1 PSAR, do not permit drums which have not been NDE'd, or previously certified by the waste generator, to enter the facility. This, then requires W-113 to perform NDE of drums.

While GEA systems are more accurate where fissile loadings exceed 10 grams, there are problems with mobile systems. Alignment of detectors, collimators and transmission sources is very important to maintaining accuracy and mobility causes much additional time to be spent in setup and verification. In addition, where low fissile loadings are encountered the gamma background in the trench will make low level measurements more difficult. Since 31,000 of the 38,000 drums contain less than 10 grams each of TRU, these drums would benefit from PAN NDA which does not have the critical alignment problems of the GEA systems. PAN systems all have significant shielding and the measurement process is relatively insensitive to neutron background in the trench. Although optimized to quantify TRU in the milligram region, PAN systems (in the passive mode) are able to make reasonable measurements at the higher loadings expected for the remaining 7,000 drums. Performing PAN NDA in the trench has the added potential benefit of determining that a drum is LLW and leaving it in the trench. This could result in the elimination of 40% or more of the drums that would otherwise be retrieved and processed in WRAP-1, another significant cost reduction.

The elimination of GEA NDA results in very little fission and activation product knowledge for poorly characterized drums. When some benefit can be shown, for batching or other reasons, GEA NDA can still be selectively performed in WRAP-1.

The cost of the presently conceived W-113 NDE/NDA facility is of the order of \$7M. The cost of mobile PAN and RTR systems to satisfy the requirements would not exceed about \$3M.

Head gas sampling is already done in the trench. Mobile drum PAN and RTR systems are current technology. The mobile drum PAN and RTR systems will be ruggedized versions of the same systems we plan for WRAP-1. The NDA system for retrieved boxes will be deleted. Rescoping of the W-113 project leaves only very well characterized boxes with incoming W-112 information requirements being met from existing records.

3.2 85-gallon Drum

Knowledge of the fissile gram loading of a drum is required before it is placed in the 85-gallon drum to prevent exceeding the SARP limits. Retrieved drums which exceed this limit (expected to be about 200 grams) must be handled on a case-by-case basis.

Table 1 lists the sources of the required information.

TABLE 1. Information Required to Permit Loading of 85-Gallon Salvage Drum

	Type of Information and its Source							
	TRU/Fissile Content		Fission & Activation Products		Physical Contents		Hazardous Materials	
	Req'd By	Source of info	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.
Incoming Retrieved Waste	SARP	In-Trench W-113 PAN NDA	Not Req'd	---	Not Req'd	In-Trench W-113 NDE	Not Req'd	---
Incoming N G Waste	SARP	Generator Certification	Not Req'd	---	Not Req'd	Generator Certification	Not Req'd	---
Process Decisions for Retrieved Waste	Not Applicable; No Processes Involved		Not Applicable; No Processes Involved		Not Applicable; No Processes Involved		Not Applicable; No Processes Involved	
Process Decisions for N G Waste								
Certification of Outgoing Waste	Not Applicable		Not Applicable		Not Applicable		Not Applicable	

3.3 W-112 Storage

The SAR for W-112 requires the following information about retrieved or newly generated drums prior to being brought in for storage:

- Fissile gram loading
- Potentially explosive content
- Hazardous content
- Identity of LLW 3+

For newly generated waste, the Hanford WAC (WHC-EP-0063) require the identification of LLW 1, LLW 3 and LLW 3+. Generator certification provides this information. The requirement to identify LLW 3+ in retrieved waste must be done using existing records, since, without prior characterization, NDA cannot provide this information.

Table 2 lists the sources of the required information.

TABLE 2. Information Required By W-112 to Accept or Ship Incoming/Outgoing Drums of Waste

	Type of Information and its Source							
	TRU/Fissile Content		Fission & Activation Products		Physical Contents		Hazardous Materials	
	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.
Incoming Retrieved Waste	SAR	In-Trench W-113 PAN NDA	Not Req'd	Not Applicable	SAR	In-Trench W-113 NDE	SAR	In-trench Head Gas Sampling
Incoming N G Waste	SAR	Generator Certification	WAC EP0063	Generator Certification	SAR	Generator Certification	SAR	Generator Certification
Process Decisions for Retrieved Waste	Not Applicable; No Processes Involved		Not Applicable; No Processes Involved		Not Applicable; No Processes Involved		Not Applicable; No Processes Involved	
Process Decisions for N G Waste								
Certification of Outgoing Waste	SARP & WAC	Generator Certification	SAR & WAC	Generator Certification	SAR & WAC	Generator Certification	SAR & WAC	Gen Cert + Head Gas Sample for TRU to WIPP

3.4 WRAP-1

Present project safety limitations require certification that potentially explosive waste such as unvented compressed gas cylinders is not being brought into the facility. For retrieved waste, this requirement can only be met using RTR NDE. In addition, criticality safety limits and the WRAP-1 SAR require knowledge of the fissile content of a drum before entry.

Processing decisions are based on knowledge of TRU, fission & activation product and hazardous contents of retrieved or newly generated drums prior to processing.

The Hanford WAC, the WIPP-WAC and the TRUPACT II SARP require knowledge of the TRU, fission & activation product and hazardous contents of processed drums prior to shipping.

Table 3 lists the sources of the required information.

At this time, WRAP-1 cannot accept drums without prior knowledge of fissile or dangerous contents. Therefore, NDA and NDE are required at retrieval. PAN NDA and RTR NDE at retrieval perform these functions and reduce the requirements for incoming WRAP-1 requirements. Incoming (to WRAP-1) retrieved drums which contain more than about 10 grams of fissile equivalent (about 17% of the total) are candidates for being split into two or more drums. These drums will still require GEA NDA to corroborate the passive neutron assay made in the trench. Outgoing NDA and NDE requirements for processed retrieved waste remain unaffected. The summary below compares the current WRAP-1 design basis (in drums per year) with what would result with NDE and NDA at retrieval.

<u>WRAP Function</u>	<u>SDRD Basis</u>	<u>Retrieval NDE/NDA</u>
NDE (RTR)	9071	6446
NDA (GEA)	9889	7710 (includes 17% of retrieved drums with >10g Pu)
NDA (PAN)	9889	7264

If the initiative to leave drums, determined to be LLW, in the trench is successful, at least 40% of the total retrieved drums will be eliminated from the incoming WRAP-1 waste stream.

Incoming retrieved drums will not have had GEA NDA performed. If batching or other considerations will benefit from this additional information, GEA NDA can still be performed as needed in WRAP-1.

Should the restriction on bringing potentially dangerous drums into WRAP-1 be removed in the future, it might be reasonable to eliminate retrieval NDE and meet W-112 requirements by performing NDE in WRAP-1. This would exacerbate the throughput problem that currently exists.

TABLE 3. Information Required by WRAP-1 Before Accepting, Processing or Shipping Drums of Waste

	Type of Information and its Source							
	TRU/Fissile Content		Fission & Activation Products		Physical Contents		Hazardous Materials	
	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.
Incoming Retrieved Waste	SAR, Crit. Safety	In-Trench W-113 PAN NDA	Not Req'd		PSAR	In-Trench W-113 NDE	Not Req'd	In-Trench Head Gas Sampling
Incoming N G Waste	SAR	Generator Certification	Not Req'd	Generator Certification	PSAR	Generator Certification	Not Req'd	Generator Certification
Process Decisions for Retrieved Waste	Proc. Reqt's	W-113 PAN NDA Plus WRAP-1 GEA NDA	Proc. Reqt's	Char. Data & W-113 PAN NDA	Proc. Reqt's	W-113 NDE	Proc. Reqt's	In-Trench Head Gas Sampling
Process Decisions for N G Waste	Proc. Reqt's	WRAP-1 PAN/GEA NDA	Proc. Reqt's	WRAP-1 PAN/GEA NDA	Proc. Reqt's	WRAP-1 NDE	Proc. Reqt's	Generator Certification
Certification of Outgoing Waste	SARP & WAC	WRAP-1 PAN/GEA NDA	SARP & WAC	WRAP-1 PAN/GEA NDA	SARP & WAC	WRAP-1 Process Control Plus 10% WRAP-1 NDE	SARP & WAC	WRAP-1 Process Control

3.5 WRAP-2A

The WRAP-2A SAR sets the requirements for the knowledge that is required of contents of retrieved or newly generated drums prior to being brought in for processing. TRU, fission & activation product and hazardous content must be provided, either by generator certification or by prior characterization and NDA & NDE.

To meet the Hanford disposal WAC, TRU, fission & activation product and hazardous content must be certified for processed drums prior to shipping.

PAN and GEA NDA were planned to permit certifying the contents of product drums and determining whether they are MLLW 1 or MLLW 3. However, WRAP-2A incoming waste is well characterized and inventoried, with ten percent of all newly generated containers already having been NDA'd and NDE'd in WRAP-1. Information available with incoming waste is sufficient to support any processing decisions that might be required. Unless application of the "Debris Rule" changes the character of the waste (and there is no reason to think it should), there is no NDA issue for WRAP-2A. It is also practical to calculate the inventory of output drums from the incoming information. If need be, the classification of a container as Category 1 or 3 can also be performed by calculation. Therefore no real requirements for NDA or NDE capabilities exist for WRAP-2A. Deletion of these NDA functions saves several million dollars.

New regulatory requirements may dictate that up to ten percent of the outgoing containers undergo verification NDE/NDA. Any NDA and NDE requirements for the type of waste produced in WRAP-2A can be satisfied by the existing capability of WRAP-1 equipment. With WRAP-2A's output of about 10,000 drums per year, as many as 1,000 would have to pass through WRAP-1 NDA and NDE. The initiative to perform NDE and NDA at the time of retrieval results in a reduction in WRAP-1 throughput requirements of at least 2,000 drums annually. Thus, the requirement for the NDE or NDA of 1,000 WRAP-2A drums might be handled by simply blending into normal WRAP-1 operation or, at least, in off-shift campaigns. Should the number of output drums from WRAP-2A double (to 20,000) WRAP-1 NDA and NDE (then required to handle 2,000 additional drums) would still be within the current SDRD design base. Where drums exceed the WRAP-1 limit of 1,000 pounds, the Box Waste Assay System, with its 10,000 pound capability, will be used.

Table 4 summarizes the requirements and sources of the required information.

TABLE 4. Information Required by WRAP-2A Before Accepting, Processing or Shipping Drums of Waste

	Type of Information and its Source							
	TRU/Fissile Content		Fission & Activation Products		Physical Contents		Hazardous Materials	
	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.
Incoming Retrieved Waste	SAR	WRAP-1, WRAP-2B Cert.	SAR	WRAP-1, WRAP-2B Cert.	SAR	WRAP-1, WRAP-2B Cert.	SAR	WRAP-1, WRAP-2B Cert.
Incoming N G Waste	SAR	WRAP-1, WRAP-2B Cert.	SAR	WRAP-1, WRAP-2B Cert.	SAR	WRAP-1, WRAP-2B Cert.	SAR	WRAP-1, WRAP-2B Cert.
Process Decisions for Retrieved Waste	Not Req'd	---	Not Req'd	---	Not Req'd	---	Not Req'd	---
Process Decisions for N G Waste	Not Req'd	---	Not Req'd	---	Not Req'd	---	Not Req'd	---
Certification of Outgoing Waste	SARP & WAC	Previous Certs Plus Calculation (Plus?) WRAP-1 NDA	SARP & WAC	Previous Certs Plus Calculation (Plus?) WRAP-1 NDA	SARP & WAC	Previous Certs (Plus?) WRAP-1 NDE	SARP & WAC	Previous Certs (Plus?) WRAP-1 NDE

3.6 WRAP-2B

At this time it is not clear what knowledge is required of the contents of retrieved or newly generated CH or RH drums prior to being brought in for processing. It is assumed that fissile gram loading of drums will be required. Otherwise, probably nothing else is necessary because of the assumed hazardous nature of incoming drums.

Processing decisions will require some knowledge of the contents of incoming retrieved or newly generated CH or RH drums. This knowledge will probably have to be provided by in-house NDA for RH drums and will provide estimates of the TRU and fission & activation product contents.

The Hanford WAC, the WIPP-WAC and the TRUPACT II SARP require knowledge of the TRU, fission & activation product and hazardous contents of processed drums prior to shipping. For CH drums WRAP 1 NDA and NDE capabilities might be useable on an off-shift basis. Further study is required to determine if such an approach is cost effective. RH drums and canisters will require NDA within the WRAP 2B facility.

Table 5 lists the sources of the required information.

It should be noted that large containers and most retrieved RH waste will not have the types of information available that are required for entrance into other facilities. Ongoing work is defining the requirements.

TABLE 5. Information Required by WRAP-2B Before Accepting, Processing or Shipping Drums of Waste

	Type of Information and its Source							
	TRU/Fissile Content		Fission & Activation Products		Physical Contents		Hazardous Materials	
	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.
Incoming Retrieved Waste	Not Req'd?	None-- Possible NDA of Calissons	Not Req'd	None-- Not Required	Not Req'd	None-- Not Required	Not Req'd	None-- Not Required
Incoming N G Waste	Not Req'd?	Generator Cert.	Not Req'd	Avail. From Gen. Cert.	Not Req'd	Avail. From Gen. Cert.	Not Req'd	Avail. From Gen. Cert.
Process Decisions for Retrieved Waste	Proc. Reqt's	In-Process NDA	Proc. Reqt's	In-Process NDA	Proc. Reqt's	None-- No NDE Performed	Proc. Reqt's	None-- No NDE Performed
Process Decisions for N G Waste	Proc. Reqt's	Generator Cert.	Proc. Reqt's	Generator Cert.	Proc. Reqt's	Generator Cert.	Proc. Reqt's	Generator Cert.
Certification of Outgoing Waste	SARP & WAC	In-Process NDA	SARP & WAC	In-Process NDA	SARP & WAC	Sample & Calculation of Content	SARP & WAC	Sample & Calculation of Content

Notes:

1. Shaded areas highlight lack of required information

3.7 Thermal Treatment Facility

The SAR for the TTF will undoubtedly require knowledge of the fissile contents of retrieved or newly generated CH or RH drums prior to being brought in for processing.

While generator certifications provide knowledge of the TRU, fission & activation product and hazardous contents of retrieved or newly generated CH or RH drums, processing decisions do not depend on it.

To meet the Hanford WAC, TRU, fission & activation product and hazardous content must be certified for processed drums prior to shipping to another facility for final packaging and disposal.

Table 6 lists the sources of the required information.

The site-specific engineering study includes undefined NDA in the TTF concept.

However, all incoming drums are effectively "newly generated" and as such, will have generator certification of their content. This means that incoming NDA is not required. Furthermore, all product of the TTF must be characterized by sampling and analysis. Considering the homogeneity of the TTF product, it should be sufficient to simply calculate the radionuclide content using the newly developed characterization data and the weight of the outgoing drum. Therefore it would appear that NDA will not be required in the TTF. The FDC, which is presently being prepared will reflect the final determination.

TABLE 6. Information Required by Thermal Treatment Facility Before Accepting, Processing or Shipping Drums of Waste

	Type of Information and its Source							
	TRU/Fissile Content		Fission & Activation Products		Physical Contents		Hazardous Materials	
	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.	Req'd By	Source of Info.
Incoming Retrieved Waste	SAR	WRAP-2B Certification	SAR?	WRAP-2B Certification	SAR	WRAP-2B Certification	SAR	WRAP-2B Certification
Incoming N G Waste	SAR	WRAP-2B Certification	SAR	WRAP-2B Certification	SAR	WRAP-2B Certification	SAR	WRAP-2B Certification
Process Decisions for Retrieved Waste	Not Req'd	WRAP-2B Certification	Not Req'd	WRAP-2B Certification	Not Req'd	WRAP-2B Certification	Not Req'd	WRAP-2B Certification
Process Decisions for N G Waste	Not Req'd	WRAP-2B Certification	Not Req'd	WRAP-2B Certification	Not Req'd	WRAP-2B Certification	Not Req'd	WRAP-2B Certification
Certification of Outgoing Waste	SARP & WAC	Sample & Calculation of Content	SARP & WAC	Sample & Calculation of Content	SARP & WAC	Sample & Calculation of Content	SARP & WAC	Sample & Calculation of Content

WMC-SD-W113-ACDR-001
Rev. 0
Page 519A

WMC-SD-W113-ACDR-001

Attachment 3 to Internal Memo, 87330-93-WPG-026 REVISION 2

**SOLID WASTE PROJECTS NONDESTRUCTIVE
ASSAY/NONDESTRUCTIVE EXAMINATION REVIEW**

Pages 1 through 3

MHC-SD-W113-ACCR-001
Rev. 3
Page 5ZCA

403 2482 0707004-1 11-11-2000

Attachment 3

NDA and NDE Descriptions

NDA

Nondestructive assay (NDA) refers to the measurement of the fission and activation product as well as the actinide contents of solid radioactive waste. Nondestructive means that the waste is not altered as it would be if a physical sample were to be taken for chemical or other analysis. For NDA to be successful, the waste must be characterized.

Characterization for radionuclides involves the determination of the quantity of each radionuclide present in a particular waste stream and the development of ratios of the values obtained (for alpha and beta emitters as well) to the one or two radionuclides actually measured. NDA cannot perform characterization.

The method of performing NDA is to measure the radiation from a few key radionuclides in the waste and then to calculate the quantities of all others present from previously developed characterization information.

Radioactive materials emit alpha and beta particles as well as gammas and neutrons. It is not practical, however, to measure alpha or beta emissions since they do not penetrate the walls of a typical steel waste container. NDA must, therefore, rely on gamma and neutron measurements.

NDA by Gamma Energy Analysis (GEA)

NDA using GEA for fission and activation products typically requires the measurement of ^{137}Cs and ^{60}Co and subsequently the calculation of all the other radionuclides present from the ratios previously determined during characterization, with the ratios of fission product quantities to the cesium and activation products to the cobalt measurements being calculated.

NDA using GEA for the actinides involves, again, measuring only the strongest and highest energy emitters. Practically speaking, because of their short range of penetration through waste matrices and container walls, gammas with energies less than 100KeV are not easily measured. The only TRU radionuclides with significant emissions above this level are ^{235}U , ^{237}Np , ^{239}Pu , ^{242m}Am , ^{243}Cm and ^{245}Cm . They are the only actinides that can be reliably identified, when present in significant quantities, by GEA. The quantities of the other actinides present are calculated by using previously determined characterization information.

With respect to making measurements of gamma emitters, some practical limitations apply:

Gammas with energies lower than 100 KeV are greatly attenuated by steel or heavy-walled containers and therefore, cannot reliably be measured, especially when the quantities of these emitters are small.

Gamma energy peaks less than about 2 KeV apart cannot readily be resolved and peaks that differ in amplitude by a factor of 100 cannot be measured without great difficulty.

GEA is not practical for making the LLW/TRU determination because the quantity of plutonium present is typically in the milligram region and too few gammas are emitted to be accurately measured. GEA measurements for TRU, using a segmented gamma scanner, are best made when the TRU quantity is greater than 1.0 gram.

NDA by Neutron Measurements

The second technique measures the neutrons coming from spontaneous or induced fission. The Passive-Active-Neutron (PAN) system makes these kinds of measurements. Typically the even numbered TRU isotopes show relatively large spontaneous fission activity. Neutrons from spontaneous fissions are what are measured during passive counting. The active phase of counting involves injecting a cloud of neutrons into a container of waste. This causes fission (in proportion to their respective fission cross-sections) in the odd numbered TRU isotopes. The number of neutrons counted during passive or active counting is proportional to the quantity of each isotope present and its spontaneous fission activity or its fission cross-section, respectively.

Neutrons, however, cannot be identified as to source. Certain isotopes, their chemical form and the makeup of the waste matrix can cloud the issue because large numbers of α, n reactions occur and increase the passive count. The number of α, n neutrons can be inferred by comparing passive total counts to passive coincidence total counts.

Neutron measurements are used for the determination of whether a container of waste is LLW or TRU ($< 100\text{nCi/g}$); but, passive neutron counting alone is typically inadequate; passive-active-neutron (PAN) assay is required. Active interrogation counts neutrons resulting from the induced fission of ^{239}Pu . The combination of both techniques, using the PAN approach, provides the best estimate of the amount of TRU present at the LLW/TRU levels. PAN measurements are also required at the 10 nCi/g level to make the LLW Category 1 vs 3 determination.

Since the source of neutrons cannot be readily identified, neutron assaying requires prior knowledge (characterization) of the waste to permit calculating the relative contributions of all the TRU contents to the neutron measurements made. Then, a figure for the total TRU and fissile content of a container can be developed.

With respect to the measurement of neutron emitters some practical considerations apply:

Neutrons in waste originate from spontaneous and induced fission and from alpha-neutron reactions. Individual neutrons cannot reasonably be distinguished from one another as to source, but coincidence counting can help to separate neutrons originating from fission from those which result from α, n reactions.

NDE

Non destructive examination in this application refers to the use of various X-ray techniques to examine the contents of a container without opening it. The purpose of NDE is to minimize the chances that a drum contains undetected free liquids, powders, potentially explosive pressurized gas cylinders or other non compliant items.

Real time radiography (RTR) applies X-ray fluoroscopy to the imaging of drums of waste. The output of an X-ray source is passed through a drum and onto a fluoroscopic screen. The resulting image is observed in real time as the drum is rotated and incremented vertically past the source. An image intensifier is used to provide better contrast and brightness. The operator is able to "jog" the drum by starting and stopping the rotation. This permits the viewing of free liquids as they slosh about. A video tape of the scanning process is provided along with voice annotation as a permanent record. These image intensifier based fluoroscopy RTR systems provide high resolution and penetration capability.

Linear-array digital radiography (DR) augments the RTR systems. A linear array of solid state detectors provide a digital image of a "slice" of a drum. In this case a drum is rotationally fixed and scanned in vertical increments with the linear digital images being stored. After scanning is complete, a complete picture of a cross-section of the drum is assembled and displayed. Two DR views, 90 degrees apart, with suspect areas annotated, serve as a "road-map" for more extensive examination using the RTR capability.

The combined RTR/DR NDE inspection systems provide the following benefits:

Assurance that 100% of the contents of the waste drums are inspected via full drum images

Traditional RTR inspection to aid in the identification of liquids (DR techniques also facilitate the identification of liquids)

THIS PAGE INTENTIONALLY LEFT BLANK

Attachment 4 to Internal Memo, 37330-93-WPG-026 REVISION 2

**SOLID WASTE PROJECTS NONDESTRUCTIVE
ASSAY/NONDESTRUCTIVE EXAMINATION REVIEW**

Pages 1 through 1

THIS PAGE INTENTIONALL LEFT BLANK

CURRENT RETRIEVAL/STORAGE/WRAP-1 NDA/NDE DRUM FLOW

PROPOSED RETRIEVAL/STORAGE/WRAP-1 NDA/NDE DRUM FLOW

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX E

NDE/NDA Equipment Design Requirements

THIS PAGE INTENTIONALLY LEFT BLANK

DRUM PASSIVE-ACTIVE ASSAY SYSTEM

GENERAL

A. SCOPE

This section established the functional requirements for Drum Passive-Active Assay (PAN) equipment.

The PAN equipment shall make the necessary measurements in order to determine the radionuclide contents of 55 gallon and 85 gallon solid waste drums and to certify them as Low Level Waste (LLW) or Transuranic waste (TRU).

B. GLOSSARY

1. Assay Isotopics - Determination, by assay, of the relative concentrations of those radionuclides which exhibit measurable neutron emissions.
2. Low Level Waste - All waste from a nuclear facility with alpha contamination levels less than those stipulated for TRU waste.
3. Partial Characterization - Full characterization of waste is the determination of the absolute values of all radionuclides in a drum together with other non-radiometric information. Within the context of NDA, "partial characterization" is the determination of the ratios of all radionuclide concentrations necessary to fulfill the reporting requirements dictated by the regulatory agencies.
4. Process Knowledge - Within the context of NDA, process knowledge refers to information on the radionuclide content of a waste stream or drum, which may have come from knowledge of the operations taking place which generate that waste, or from analysis of a sample of that waste stream. Process knowledge is necessary to determine the absolute values of all radionuclides required for reporting purposes.
5. Total Measurement Uncertainty (TMU)
 - a. The "Total Measurement Uncertainty" of a measurement (sometimes abbreviated to TMU) is an estimate of the overall error associated with that measurement. Unless otherwise stated, the TMU will be considered to be the one sigma value.

- b. For the purposes of this requirement, the Total Measurement Uncertainty is defined to be composed of two components, (1) the measurement precision derived from propagated counting statistics data and (2) credible limits of assay accuracy. For the purposes of this specification, although the measurement accuracy is known not to be a Gaussian distribution phenomenon, it will be treated as one, and the Total Measurement Uncertainty will be calculated as a "Square Root of the Sum of the Squares" function of the measurement precision and measurement accuracy as defined in the following sections.
1. **Measurement Precision** - The magnitude of random errors originating from statistical fluctuations in the counts observed during the measurement. Statistical error is usually represented in terms of standard deviations.
 2. **Measurement Accuracy** - The term accuracy is used to describe the systematic errors which are not reduced by repeated measurements. For NDA, measurement accuracy is used to quantify those errors which arise due to differences in individual measurement conditions and the calibration conditions. Factors which affect accuracy include:
 - a) Matrix (positional) variation in source
 - b) Density variations
 - c) composition variations
 - d) Background variations
6. **Transuranic Waste** - Waste contaminated with alpha-emitting TRU radionuclides with half lives greater than 20 years and in concentrations greater than 100 Nci/g of the waste matrix at the time of the assay. TRU radionuclides are those having an atomic number greater than 92 plus additional radium sources and U-233.
7. **Waste Matrix Definition** - The following definitions are provided to define acceptance criteria (in conjunction with other data). No assumptions shall be made about all waste always fitting into one of these categories. Waste form parameters are defined in Article 2.03 A.
- a. **Lab Waste** - Low density (up to 6 lb/ft³) waste containing such things as paper, rags, rubber gloves and some glass, but without chlorinated plastics or other neutron absorbers or high atomic number materials.

- b. Moderate Absorber - Medium density (6-12 lb/ft³) waste consisting of such things as wood, construction materials and other relatively light weight materials but without chlorinated plastics or other neutron moderators or high atomic number materials.
- c. Heavy Matrix - High density (12-100 lb/ft³) waste consisting of such things as concrete, soil, steel, lead, depleted uranium and failed equipment.

II SYSTEM DESCRIPTION

A. EQUIPMENT FUNCTION

- 1. The Drum NDA Equipment shall fulfill the following functional requirements:
 - a. PAN - Passive/Active Neutron interrogation

B. EQUIPMENT DESCRIPTION

- 1. A drum Passive/Active Neutron Interrogation Station (Mobile Unit) shall be provided to combine active and passive neutron counting methods to detect and measure the quantity of U, Pu, Np, Cm, Am and Cf isotopes. The unit shall determine low-level/TRU activity of 55 and 85 gallon drums. The active neutron assay primarily provides the information used to sort and categorize the waste as either TRU (> 100 Nci/g) or LLW (≤ 100 Nci/g). The active portion of the PAN system shall utilize a neutron generator to provide short (5-10 sec) bursts of thermal neutrons to "interrogate" the waste. The thermal neutrons induce fissions of fissile isotopes such as Pu-239 and Am-241, resulting in a burst of fission spectrum neutrons being emitted by each fissioning nucleus. Cadmium shielded detectors shall be provided to reject the thermal neutrons, but detect about 10% of all fission spectrum neutrons. A set of thermal flux monitors (one cadmium shielded the other bare) shall also be located in the assay chamber, and are used to determine the Absorption Index of the waste. The passive portion of the PAN system shall use high-efficiency neutron detectors and coincidence counting techniques to quantify the number of time related neutrons being emitted by spontaneous fissioning isotopes such as Pu-240. This side of the counting equipment shall be utilized for those drums which are determined by active neutron interrogation to be TRU waste, and will produce a "Pu-240 equivalent" value which can then be combined with the Pu isotopic ratio determined from characterization data to give a total Pu content.

2. The PAN assay unit shall be provided in a trailer mounted enclosure capable of providing protection for the equipment from blowing dust, snow, and water leakage. The environment within the trailer shall be capable of being controlled to within 30 - 50% relative humidity and 55 - 90 °F during equipment operations.

The unit shall be designed to be rugged enough or easily secured for transport and shall be capable of being stored or operated on site in the open.

The unit shall also be designed to accept and present 55 gallon drums or 85 gallon drum overpacks at loading and/or overloading station(s) such that either a crane or fork lift fitted with drum handlers can be used to place or receive them.

C. MATERIALS

Any decontamination required for the PAN equipment and provided by others will consist of mainly dry wiping type decontamination methods. Therefore, the PAN equipment materials of construction shall be the standard materials that are compatible with the design conditions specified.

III EQUIPMENT

A. WASTE FORM PARAMETERS

This section specifies the waste form parameters that characterize the LLW/TRU solid waste that will be assayed by the NDA system. These parameters are not restricted to wastes to be removed by Project W-113, but are representative of the entire inventory of retrievably stored waste. The PAN equipment shall be designed to handle the full spectrum of the waste form parameters specified.

1. Physical contents: Typical types of materials contained in a drum will include contaminated paper, plastic, glass, concrete, soil, steel, wood, failed equipment and dewatered sludges. Drums may contain only one type of these materials or mixtures of several types. Some drums may contain small shielded containers. A typical waste form matrix representing this material is shown in Figure 1.

FIGURE 2
WASTE DRUM CONFIGURATION 55 GALLON
DRUM CONTAINED IN AN 85 GALLON RETRIEVAL OVERPACK DRUM

TABLE 1
ISOTOPIC DISTRIBUTION FOR TRANSURANIC WASTE
FROM 1970 TO DECEMBER 31, 1988²

Isotope	Gram Quantity	Curie Quantity (Ci)	Specific Activity (Ci-g)	Activity (%)	Weight (%)
²⁴¹ Am	1.836E+02	6.304E+02	3.433E+00	--	--
²⁴³ Am	5.276E+01	9.761E+02	1.850E-01	--	--
¹⁴ C	--	1.600E+00	--	--	--
¹⁴¹ Ce	3.509E-08	1.000E-03	2.850E+04	--	--
¹⁴⁴ Ce, ¹⁴⁴ Pr (3)	1.662E+01	5.302E+04	3.190E+03	4.0	--
²³² Ce	2.000E+00	1.290E+03	6.450E+02	0.1	--
²⁴⁵ Cm	4.822E+01	7.566E+00	1.569E-01	--	--
⁶⁰ Co	1.973E+00	2.232E+03	1.131E+03	0.2	--
¹³⁷ Cs, ¹³⁷ Ba (3)	1.941E+02	1.679E+04	8.650E+01	1.3	--
¹⁵⁵ Eu	8.192E-02	3.310E+01	4.651E+02	--	--
³ H	7.057E-04	6.803E+00	9.640E+03	--	--
⁸⁵ Kr	9.506E+00	3.730E+03	3.924E+02	0.3	--
Li	5.900E+00	5.900E+00	1.000E+00	--	--
Mixed fission products(3)	--	8.826E+05	--	66.5	--
²³⁷ Nd	3.537E+02	2.493E+00	7.049E-03	--	--
¹⁴⁷ Pm (3)	4.339E+01	4.023E+04	9.271E+02	3.0	--
²³⁸ Pu (3)	5.293E+03	1.657E+04	1.740E+01	6.9	--
²³⁹ Pu (3)	4.417E+05	2.712E+04	6.140E-02	2.0	2.2
²⁴⁰ Pu	2.702E+04	6.457E+03	2.390E-01	0.5	0.1
²⁴¹ Pu (3)	1.599E+03	1.791E+05	1.120E+02	13.5	--
²⁴² Pu	9.413E+01	3.671E-01	3.900E-03	--	--
¹⁰⁶ Ru, ¹⁰⁶ Rh	1.581E+00	5.291E+03	3.346E+03	0.4	--
⁹⁰ Sr, ⁹⁰ Y (3)	1.191E+02	1.554E+04	1.389E+02	1.2	--
Th	6.151E+05	6.748E-01	1.097E-06	--	3.1
U-D	1.450E+07	4.876E-01	3.362E-06	--	72.8
U-E	3.568E+05	7.714E-00	2.162E-05	--	1.8
U-N	3.966E+06	2.729E+00	6.880E-07	--	19.9
²³⁵ U	8.293E+03	7.994E+01	9.639E-02	0.1	--
Totals	1.993E+07	1.021E+06	--	--	--

(1) Source Document: Contact-Handled Transuranic Waste Characterization based on Existing Records WHC-EP-0225 Table 4-22.

(2) Not including 12 drums of high ²³⁸Pu content from 234-5Z.

(3) Nuclides contribution > 1%.

FIGURE 1
TYPICAL WASTE FORM MATRIX

- #1 Solid Plastic
- #2 Plastic Pellets
- #3 Plastic Powder
- #4 Glass Vials of Plastic Sliver and Powder

FIGURE 2
WASTE DRUM CONFIGURATION
55 GALLON DRUM

DRUM FORM No. 1-55
 GALLON DRUM

DIMENSION

DIAMETER OUTER ROLLING HOOPS
 DIAMETER OVER FALSE WIRE
 OVERALL HEIGHT
 HEIGHT, COVER OFF
 ALL OTHER HEIGHT DIMENSIONS
 CONVEXITY OF TOP HEAD
 CONVEXITY OF BOTTOM HEAD
 ALL OTHER DIMENSIONS

TOLERANCES

$23\frac{27}{32}$ in ± 0.0015
 $23\frac{1}{2}$ in ± 0.0015
 $24\frac{13}{16}$ in ± 0.0015
 $24\frac{3}{8}$ in ± 0.0015
 $3\frac{1}{8}$ in
 $\frac{3}{8}$ in ± 0.0015
 $\frac{3}{8}$ in ± 0.0015
 $2\frac{1}{16}$ in

2. Weight Distribution: Average weight characteristics for 55 gallon drums are the following:

Gross Weight Range (Lbs)	Density (g/cc)	Number (Drums)	Number (%)
0 - 100	0.11	520	1.4
100 - 200	0.32	33,153	88.5
200 - 300	0.54	1,888	5.0
300 - 400	0.76	832	2.2
400 - 500	0.97	412	1.1
500 - 600	1.19	226	0.6
600 - 700	1.40	267	0.7
700 - 800	1.62	128	0.3
800 - 900	1.84	15	0.0
900 - 1000	2.05	25	0.1
Maximum: 1000 Lbs 2.05 g/cc			
Mean: 170 Lbs 0.37 g/cc			

3. Dose Rate Data: The maximum surface dose rate for the drums is 200 mrem/hr. The weighted average surface exposure from the drums is 10 mrem/hr. A summary of the exposure data is as follows:
- Maximum: 200 mrem/hr
 - Mean: 10 mrem/hr
 - 95th Percentile: 20 mrem/hr
4. Surface Contamination: Contamination on the surface of a drum will not exceed:
- 450 pCi/100cm² for Beta-Gamma contamination
 - 50 pCi/100cm² for Alpha contamination

5. TRU Content: The expected TRU contents for the drums are as follows.
- a. Maximum: 350 g
 - b. Mean: 11 g
 - c. 95th Percentile: 75 g
 - d. The TRU content of a drum may range from milligram to gram quantities in the presence of kilograms of uranium, which can be "depleted", "natural" or several percent "enriched." There is no specification or universal definition for the term "depleted" uranium and the isotopes it may contain except that there will be less than the naturally occurring percentage of ^{235}U (0.7%). Process knowledge may provide more precise data.
6. Radionuclide contents: The radionuclide contents of drums include the following which may appear in any combination:
- a. Activation products including at least ^3H , ^{14}C , ^{55}Fe , ^{60}Co , ^{63}Ni , ^{95}Zr , ^{94}Nb , ^{119}Sn and ^{125}Sb .
 - b. The full spectrum of fission products, resulting from the production of fuels and weapons grade plutonium but with ^3H , ^{90}Y , ^{106}Ru , ^{134}Cs , ^{137}Cs , $^{137\text{m}}\text{Ba}$, ^{144}Ce , ^{144}Pr , ^{147}Pm , ^{152}Eu , and ^{154}Eu as the principal sources of activity.
 - c. Actinides typical of those resulting from producing fuels and weapons grade plutonium or uranium. This includes ^{232}Th , ^{233}U , ^{235}U , ^{238}U , ^{238}Pu , ^{239}Pu , ^{240}Pu , ^{241}Pu , ^{242}Pu , ^{241}Am , ^{243}Am , ^{245}Cm and ^{252}Cf and their decay products.
 - d. Table 1 provides a total inventory of TRU waste isotopic distribution. This table is provided for guidance only and no assumptions shall be made regarding this distribution of the listed radionuclides in any particular drum.
7. Waste Drum Configurations: Waste drums to be processed by the NDA system consist of; a) waste contained in 55 gallon drums (Figure 2); b) waste contained in 55 gallon drums and overpacked in 85 gallon drums (Figure 3).

B. PAN MEASUREMENT REQUIREMENTS

1. General Requirements

- a. The system shall determine the TRU quantity, thorium and uranium radionuclides present by direct measurement and by using the relative abundances transmitted from the Data Management System (DMS) for each drum being assayed.
- b. The "active" technology shall be the differential die-away method developed by Los Alamos National Laboratory (LANL).
- c. Techniques are required to mitigate the effects of matrix inhomogeneity and non-uniform distribution of radionuclides.
- d. The PAN system shall adjust its scanning program to account for both 55 and 85 gallon drums.

2. Passive/Active Assay Methodology

- a. During the passive mode, the PAN system shall make coincidence measurements to be able to differentiate between neutrons generated from fissions and those from α , n reactions. Coincidence counting electronics shall be of the shift register type (or equivalent).
- b. Using the differential die-away technique, the PAN system shall be able to differentiate between neutrons generated from spontaneous and from induced fissions.

3. Measurement Sensitivity

- a. The lower limit of detection for TRU measurement shall be sufficient to enable LLW categorization to be carried out. From Table 2, which defines the LLW categorization limits, it can be seen that it is necessary to determine whether a drum contains greater or less than 10 nCi/g TRU.
- b. The system shall be able to detect the presence of ^{235}U in concentrations as low as 1.0 nCi/g, in a heavy matrix, in the presence of millicuries of fission and/or activation products, with an average background of less than $50\mu\text{rem/hr}$ and within the assay time duration (see paragraph B.10).
- c. The system shall be able to detect the presence of ^{239}Pu in concentrations as low as 1.0 nCi/g, in a heavy matrix, in the presence of millicuries of fission and/or activation products, with a background

not exceeding 50 μ rem/hr and within the assay time duration (see paragraph B.10).

- d. To "detect" is defined as being able to determine that the net counts exceed three times the one sigma background.
- e. "Heavy matrix" and "Lab waste" are defined in Section I-7.
- f. The system shall have an upper assay limit of 500 grams of fissile material.

4. Measurement Repeatability

- a. At least 67% of the measured PU-239 values shall be within $\pm 5\%$ of the mean value of all measurements when repeatedly assaying a single drum containing 100 mg of plutonium in laboratory waste. Repeated assay operations shall include loading and unloading the drum from the measurement system.

5. Measurement Uncertainty

- a. The following are the TMU requirements for the system:

Measurement Method	Measurand Concentration	Waste Contents	TMU
TRU Active	100nCi/g (Pu)	Lab Waste	± 40 nCi/g
TRU Active	10nCi/g (Pu)	Lab Waste	± 4 nCi/g
TRU Active	400g (Pu)	Moderate Absorber	± 75 g
TRU Passive	10g (Pu)	Lab Waste	± 4 g

- b. The conditions for meeting these requirements are: Uniformly distributed radionuclides in drums of homogeneous waste of either "moderate absorber" or "lab waste" content.

6. Radionuclide Quantity Calculations

- a. For both passive and active assays, the system shall calculate, and record, the actinide contents, in curies and grams, of a drum by using the relative abundances and their uncertainties that are calculated in paragraph B.9.

7. Information Provided by the Retrieval Data Management System

- a. The retrieval data management system will supply the following information to the PAN system for each drum to be assayed:

- 1) Drum identification, drum size and drum weight.

TABLE 2
RADIONUCLIDE CONCENTRATION LIMITS

Radionuclide	Category 1 ⁽¹⁾	Category 3 ⁽²⁾
H-3	5 E+00	no limit
Co-60	3 E+02	no limit
Ni-63	2 E+00	7 E+02
Ni-63 am ⁽³⁾	2 E+01	7 E+03
Sr-90	5 E-03	7 E+03
Cs-137	2 E-02	4.6 E+03
C-14	6 E-04	8 E+00
C-14 am	6 E-04	8 E+01
Ni-59 am	3 E+00	2.2 E+02
Nb-94	8 E-04	2 E-01
Tc-99	7 E-03	3 E+00
I-129	1 E-03	8 E-02
Se-79	7 E-03	7 E-02
Pu-241	50 Nci/g	3,500 Nci/g
Cm-242	2,000 Nci/g	20,000 Nci/g
Total alpha emitting TRU > 5 yr half life	10 Nci/g	100 Nci/g
<p>(1) Source Document: Hanford Site Radioactive Solid Waste Acceptance Criteria WHC-EP-0063-3 Table 4-1</p> <p>(2) Concentration units: Ci/m³</p> <p>(3) am denotes listed isotope in activate metal</p>		

- 2) Ratio of the curies of each actinide to the curies of ^{235}U or ^{239}Pu , and the uncertainties in each of the ratios.

3. Radionuclide Abundance Updating

- a. The abundance supplied (ref paragraph B.6) shall have been corrected by the retrieval data management system to take into account the decay rates of the respective radionuclides involved between the date of the original determination and the date of the assay. These "updated" abundances shall be used as the reference for all computations and comparisons.

9. Total Radionuclide Measurement Uncertainty

- a. The system shall propagate TMU's as well as the retrieval data management system supplied radionuclide abundance uncertainties throughout the process of developing the final assay values. A best estimate of the total measurement uncertainty shall be developed for each radionuclide and shall be reported.

10. Assay Time Duration

- a. The total average available time to assay a waste drum shall be ten (10) minutes, subject to a maximum time of 15 minutes based on the TRU content distribution. This shall include time required to load drum into the mobile NDA unit drum cavity, perform system checks and measurements, and remove the waste drum from the mobile NDA unit.

- C. OPERATIONAL REQUIREMENTS

1. Local Control Operations

- a. The normal means of operating the drum NDA system shall be via local controls provided with the mobile unit interfacing with a retrieval data management system. The system basically consists of a data management computer whose function includes keeping track of all SWTTS data associated with trench stored waste and data obtained during retrieval to augment the existing data in SWTTS.
- b. All normal operations associated with the NDA components shall be via the PCS terminal located in the mobile unit. This terminal will also have access to the retrieval data management system. The operator at this terminal will ensure that the drum's database has been adequately prepared prior to drum assay.
- c. The objective of the system is to minimize direct interfaces between the operator and NDA equipment for normal measurement and verification

requirements . For example, inputs required by the NDA equipment such as drum type, drum contents and characterization data shall be entered by a data link interface. Outputs from the PAN equipment shall be transferred by data link to the retrieval data management system. Abnormal activities such as diagnostic searches, system reconfiguration and general maintenance shall be carried out using a local console supplied as part of the NDA system. The retrieval data management system is supplied by others.

2. Assay Report Preparation

- a. The PAN system shall prepare the following information and shall transmit it to the retrieval data management system.
 - 1) All the calculated radionuclide concentrations.
 - 2) Measurement uncertainties for each of the radionuclides.
 - 3) Raw data for revisit purposes.

3. Data Storage

- a. The system shall transmit all raw data to the retrieval data management system.

4. Availability

- a. The PAN unit (including the local controller and all associated equipment shall have an operational availability of 0.96 or greater. The 0.96 minimum operational availability requirement includes all unplanned periods of downtime when the unit is not operational. Scheduled maintenance such as verification, background and calibration drum checks and diagnostic checks are excluded from the downtime figure. Operational availability is defined as:

$$A_o = \frac{MTBM}{MTBM + MTTM}$$

Where:

Ao = Operational availability
MTBM = Mean-time-between-maintenance (unplanned)
MTTM = Mean-time-to-maintain clock hours to restore to full operations
(assuming no administrative delays)

- b. Target values for MTBM and MTTM should be:

- 1) MTBM: Not less than 300 hours
- 2) MTTM: Not more than 9.5 hours

DRUM NON-DESTRUCTIVE EXAMINATION SYSTEM

I. GENERAL

A. SCOPE

This section establishes the functional requirements for the Drum Non-Destructive Examination (NDE) system.

B. GLOSSARY

1. Radioscopy - The electronic production of a radiological image that follows very closely the changes with time of the object being imaged.
2. Single-mode Failure Concept - In the context of this specification, "single-mode failure concept" signified that the component must fail to the safe condition, i.e. alarms should fail on and radiation generating devices should fail off.

II. SYSTEM DESCRIPTION

A. EQUIPMENT FUNCTION

1. The primary function of Drum Non-Destructive Examination System is to examine the physical contents of retrieved waste drums using penetrating radiation in order to verify and augment the burial records and/or data base (SWITS) and to qualify the drums for transport and storage. A secondary function is to provide "intelligence" of the contents for the purpose of container processing and nuclear assay measurements.

B. EQUIPMENT DESCRIPTION

1. A drum Non-Destructive Examination (NDE) System, including mobile real-time radioscopy (RTR) and line array (digital radiography) imaging station shall be provided to perform X-ray examination of unopened drums in order to check for non-compliant items such as particulate material, free liquids, aerosol cans, explosives, compressed gas containers or other items requiring special processing. Drum NDE stations will examine 55-gallon drums as retrieved or in 85-gallon drum overpacks. The unit will be equipped with shielding doors on the inlet to protect personnel in the vicinity from radiation emitted from the NDE equipment.
2. The system shall consist of a shielded enclosure (vault), a manipulation system, a single, highly stabilized 450 kV X-ray source, high resolution X-ray image intensifier, digital line array, optical coupling, and monochrome closed circuit TV system.

3. When the drum is in position inside the enclosure and the entrance door is closed, the drum is scanned in a synchronized movement. A system of interlock switches and alarms prevents X-ray generation before the enclosure is completely closed. Interlocks shall be fail-safe. The image intensifier and drum movement systems shall be designed and manufactured in order to permit the following controls: up, down, rotate and transverse sideways (to the edge/tangent of the drum). In particular, the control system shall have the capability to "jog" the drums in order to facilitate the identification of free liquids in the waste matrix. The manipulation scanning and drum movement shall feature variable speeds. A feature shall be provided to enable the operator to properly align the drum with the imaging system. The movement variability and control of both the imaging system and the drum shall ensure optimum inspection results.

4. The image acquired by NDE shall be transferred to optical storage media employing Write-Once-Read-Many (WORM) Technology, located with the Data and Material Management function in the W-112 office complex.

5. The entire system shall be housed in a trailer-mounted enclosure capable of providing protection for the equipment from blowing dust, snow, and water leakage. The environment within the trailer shall be capable of being controlled between 55° and 85°F during equipment operations.

The unit shall be designed to be rugged enough or easily secured for transport and shall be capable of being stored on site in the open.

The unit shall also be designed to accept and present 55-gallon drums or 35-gallon drum overpacks at a loading and/or unloading station so that either crane or fork lift fitted with drum handlers can be used to place or receive them.

III. EQUIPMENT

A. Waste Form Parameters: This section specifies the waste form parameters that characterize the LLW/TRU solid waste that will be routed to the NDE system for assay. The NDE equipment shall be designed to handle the full spectrum of the waste form parameters as specified below:

1. Waste Form: Average characterization of the waste drums to be examined are the following. A typical waste form matrix representing this material is show in Figure 1.

FIGURE 1
TYPICAL WASTE FORM MATRIX

- #1 Solid Plastic
- #2 Plastic Pellets
- #3 Plastic Powder
- #4 Glass Vials of Plastic Sliver and Powder

<u>Waste Form</u>	<u>Percent (Vol.)</u>
Metal	22%
Lead	trace
Dirt	4%
Filters	1%
Wood	2%
Concrete	2%
Glass	2%
Absorbent	1%
Subtotal hard waste	33%
Rubber	8%
Plastic	27%
Paper	20%
Cloth	6%
Subtotal soft waste	61%
Other	6%
TOTAL	100%

2. Weight Distribution: Average weight characteristics for 55-gallon drums are the following:

<u>Gross Weight Range</u> <u>(lbs)</u>	<u>Density</u> <u>(g/cc)</u>	<u>Number</u> <u>(drums)</u>	<u>Number</u> <u>(%)</u>
0 - 100	0.11	520	1.4
100 - 200	0.32	33,153	88.5
200 - 300	0.54	1,888	5.0
300 - 400	0.76	332	2.2
400 - 500	0.97	412	1.1
500 - 600	1.19	226	0.6
600 - 700	1.40	267	0.7
700 - 800	1.62	128	0.3
800 - 900	1.84	15	0.0
900 - 1000	2.05	25	0.1

Maximum: 1000 lbs 2.05 g/cc

Mean: 170 lbs 0.37 g/cc

3. Dose Rate Data: The maximum surface dose rate for the drums is 200 mrem/hr. The average surface exposure from the drums is 10 mrem/hr. A summary of the exposure data is as follows:

- a. Maximum: 200 mrem/hr
- b. Average 10 mrem/hr
- c. 95th Percentile: 20 mrem/hr

4. Waste Drum Configurations: Waste drums sent to the NDE system generally consist of retrieved waste contained in 55-gallon drums, overpacked in 85-gallon drums. The system must also be able to handle

newly packaged waste from the retrieval operation contained in new 55-gallon drums. Figures 2 and 3 define the 55-gallon and 95-gallon drum sizes.

3. Examination Equipment Measurement Requirements: The NDE equipment shall perform the following determinations:

1. Overview:

a. Examination of the physical contents of overpacked retrieved waste drums in order to verify and augment the burial records and/or data base (SWITS), to qualify the drums for transport and storage, and/or to provide "intelligence" of the contents for the purpose of container processing and nuclear assay measurements.

b. Provision of a reliable archive recording of images for permanent, traceable record purposes.

c. Facilitation of examination data into the retrieval data management system.

2. Newly generated or newly processed drums shall be screened to ensure compliance with storage requirements which necessitates the identification of the following non-compliant items.

a. Lead (bricks, sheets, gloves)

b. Free liquids (typically in polypropylene containers, plastic bags, aerosol cans, pumps, paint cans or at base of drum)

c. Unpunctured aerosol cans

d. Gas cylinders

e. HEPA filters

f. Pyrophoric materials

g. Explosives (e.g. rifle cartridges)

h. Certain "listed" metals (mercury, cadmium, etc.)

i. Other items that might accidentally or purposely conceal non-compliant items (e.g. lead containers, concrete)

3. Identification of containers containing particulates.

4. Retrieved drummed waste requires "intelligence" relating to the contents of a drum prior to being opened. An early warning of the contents of a drum will allow any special production activities to be pre-scheduled.

5. NDE information may be used to identify dense waste items (e.g. concrete or lead) that might impact on NDA measurement accuracy. This

FIGURE 2
DRUM CONFIGURATION
55 GALLON DRUM CONTAINED IN AN 85 GALLON RETRIEVAL OVERPACK DRUM

Technical drawing of a 1-gallon drum form, showing dimensions and tolerances.

Dimensions:

- CLAMP BAND: 24 1/2
- DRUM LID: 24", 23-11/16, 3/8
- DRUM BODY: 23-1/2, 3, 3-1/16, 3, 34-3/8, 24-13/16, 23-27/32, 22-1/2, 3/8, 3/4, 11-11/16

DRUM FORM No. 1-55

GALLON DRUM

DIMENSION	TOLERANCES
DIAMETER OUTER ROLLING HOOPS	23-27/32 in ± 0.015 in
DIAMETER OVER FALSE WIRE	23-1/2 in $\pm 1/16$ in
OVERALL HEIGHT	34-13/16 in $\pm 1/8$ in
HEIGHT, COVER OFF	34-3/8 in $\pm 1/8$ in
ALL OTHER HEIGHT DIMENSIONS	$\pm 1/8$ in
CONVEXITY OF TOP HEAD	3/8 in $\pm 1/16$ in
CONVEXITY OF BOTTOM HEAD	3/8 in $\pm 1/16$ in
ALL OTHER DIMENSIONS	$\pm 1/16$ in

DIMENSION

DIAMETER OUTER ROLLING HOOPS
DIAMETER OVER FALSE WIRE
OVERALL HEIGHT
HEIGHT, COVER OFF
ALL OTHER HEIGHT DIMENSIONS
CONVEXITY OF TOP HEAD
CONVEXITY OF BOTTOM HEAD
ALL OTHER DIMENSIONS

TOLERANCES

$23-27/32$ $n = 0/16$
 $23-1/2$ $n = 1/16$ n
 $34-13/16$ $n = 1/9$ n
 $34-3/9$ $n = 1/9$ n
 $21/9$ n
 $3/8$ $n = 2/16$ n
 $3/9$ $n = 1/16$ n
 $21/16$ n

information may then be used to alter the selection of measurement algorithms utilized by the NDA instruments or simply to amend the reported accuracy of the measurement.

C. Resolution and Penetration Power Requirements

1. The resolution and penetration of the examination system using the Image Intensifier shall be assessed using the ASTM penetrometer in accordance with ASTM-E-94. The acceptance criterium shall be the visibility of an ASTM penetrometer of 2-2T sensitivity through a steel thickness of 2.5 inches on the live video monitor (no image processing or enhancement).

D. Radiation Shielding and Safety Requirements

1. General Considerations

a. The maximum allowable dose rate at any accessible area 5 cm from the outside surface of the enclosure shall not exceed 0.5 mrem/hr.

b. The dose rate limits shall be based on the operation of the x-ray device at those combinations of x-ray tube potential, current, beam orientation, and conditions of scatter radiation which will produce the maximum x-ray exposure at the external surface of the enclosure.

c. Reliable safety interlocks shall be provided to prevent access to the enclosure during irradiation.

E. NDE System Control and Interface Requirements

1. The NDE equipment shall be supplied as a packaged mobile unit complete with all the local and remote instrumentation and logic controllers necessary to perform the required local functions including manipulation (e.g. drum rotate, detector raise and lower, self-checks, etc). The NDE equipment shall interface with other drum retrieval systems including:

a. Drum transfers to and from the NDE equipment.

b. The retrieval facility power supply.

2. Mechanical Interface: The NDE units shall interface with retrieval transfer by crane or by forklift fitted with drum handlers.

3. Control System Interface: The drum NDE equipment shall be required to interface to the Retrieval Control System via discrete I/O. The quantity of these signals shall be kept to an absolute minimum. Examples of signal inputs to the NDE equipment are "drum ready for receipt" while typical outputs will be "NDE finished".

4. Control Room interfaces: The normal means of operating the Drum NDE equipment will be from the Mobile Unit Control consoles.

F. Time Constraints

1. The total available time to load a drum on and off the assembly, scan all points of interest, carry out any system checks and return comments to the data management system shall be 12 minutes or less on average.
2. The total available time to load the drum after delivery into the vault, close the vault door, open the vault door, and transfer the drum back from the vault for pick up is 60 seconds.

G. Availability

1. The overall drum NDE equipment shall demonstrate an operational availability of 0.96 or greater. The 0.96 minimum operational availability requirement includes all periods of downtime when the unit is not operational. Schedule maintenance and calibration is excluded from this downtime figure. Operational availability is defined as:

$$Ao = \frac{MTBM}{MTBM + MTTM}$$

Where:

Ao = Operational availability

MTBM = Mean-time-between-maintenance (unplanned)

MTTM = Mean-time-to-maintain clock hours to restore full operations assuring no administrative delays.

2. Target values for MTBM and MTTM should be:

MTBM: Not less than 300 hours

MTTM: Not more than 9.5 hours

THIS PAGE INTENTIONALL LEFT BLANK

APPENDIX =

Packaging Design Criteria W-113 Retrieval Package
(Reference WHC-SD-TP-PDC-014, Rev. 0-A)

THIS PAGE INTENTIONALL LEFT BLANK

Ref. WHC-SD-TP-PDC-014

Rev. 0

TABLE OF CONTENTS

1.0	INTRODUCTION	555
1.1	BACKGROUND	556
1.2	PURPOSE	556
1.3	JUSTIFICATION	556
2.0	PACKAGE CONTENTS	556
2.1	PHYSICAL DESCRIPTION	556
2.1.1	Chemical Constituent Source Term	556
2.1.2	Radioisotopic Constituent Source Term	556
2.2	TRANSPORTATION CLASSIFICATION	557
2.3	DISPOSAL CLASSIFICATION	557
3.0	FACILITY OPERATIONS	557
3.1	ORIGINATING FACILITY	557
3.2	RECEIVING FACILITY	558
4.0	PACKAGING/TRANSPORT SYSTEM DESIGN CRITERIA	559
4.1	GENERAL	559
4.2	PACKAGING DESIGN CRITERIA	560
4.2.1	Packaging Specification	560
4.2.2	Packaging Dimensions	561
4.2.3	Weight of Contents	561
4.2.4	Maximum Gross Weight	561
4.2.5	Venting	562
4.2.6	Lifting Attachments	562
4.2.7	Tiedown Attachments	562
4.2.8	Closure Design	563
4.2.10	Shielding	563
4.2.11	Service Life	563
4.2.12	Decontamination	563
4.3	TRANSPORT SYSTEM	563
4.3.1	General	563
4.3.2	Transport Vehicle	564
4.3.3	Tiedown System	564
5.0	GENERAL REQUIREMENTS	565
5.1	TRANSPORTATION SAFETY	565
5.1.1	Normal Conditions of Transfer	566
5.1.2	Accident Events	569
5.2	ALARA	569
5.3	QUALITY ASSURANCE	570
5.4	DESIGN FORMAT	570
5.5	ENVIRONMENTAL COMPLIANCE	570
6.0	REFERENCES	571

Ref. WHC-SD-TP-PDC-014 Rev. 0

FIGURE

Figure 1. Conceptual View of Loading Operation 552

TABLE

Table 1 552

Ref. WHC-SD-TP-PDC-014

Rev. 0

PACKAGING DESIGN CRITERIA, PROJECT W-113 RETRIEVAL PACKAGE

1.0 INTRODUCTION

1.1 BACKGROUND

Project W-113 is a pilot project for the retrieval of solid waste suspected of containing transuranic (TRU) radionuclide contaminated material. The suspect TRU waste was packaged prior to burial in drums and boxes and deposited in Trench 04 of the 218-W-4C burial ground located in the 200 West Area. There are approximately 10,000 galvanized or painted 55-gallon drums, 57 110-gallon drums, and 38 metal boxes of various sizes. These containers were deposited in the trench between 1980 and 1985.

The 55-gallon drums retrieved from the trench will be overpacked in 85-gallon drum overpacks. The remaining 110-gallon drums and boxes of varying sizes will be removed from the trench and packaged in suitable retrieval packagings for transport to an interim storage facility and/or transport to the Waste Retrieving and Processing (WRAP) Facility in the 200 West Area.

1.2 PURPOSE

The purpose of this Packaging Design Criteria (PDC) document is to provide criteria for the analysis and design of reusable W-113 Retrieval Package packagings for the transport of the metal boxes and 110-gallon drums retrieved from the trench. Five different size packagings will be required to facilitate the efficient retrieval of the boxes and drums.

The W-113 Retrieval Packages will be approved for use as onsite, intra-area Type B packages in accordance with the U.S. Department of Energy, Richland Operations Office (RL) Order 5480.1, Change 1, Chapter III (RL 1982), as implemented by the *Hazardous Material Packaging and Shipping*, WHC-CM-2-14. A combination of packaging performance (as demonstrated by analysis and/or testing) and risk analysis will be used to demonstrate the safety of the transfers. Additionally, this PDC will provide the criteria to be used for developing an appropriate procurement and/or design specification.

1.3 JUSTIFICATION

Because the contents of the 110-gallon drums and boxes in the 218-W-4C trench will be radioactively contaminated, the integrity of the drums and boxes is unknown, and the containers were not previously evaluated to meet current onsite transportation requirements, transfer and storage of these containers will require appropriately designed packagings. From the

Ref. WHC-SD-TP-PDC-014 Rev. 0

Project W-113, Solid Waste Retrieval Facility, Phase 1 Conceptual Design Report, WHC-SD-W113-CDR-002 (WHC 1992a) it is required that bottom-loading packagings of suitable size be procured for this retrieval operation.

Currently, no existing designs meet this criteria and the onsite requirements of the RL Order 5480.1 (RL 1982). Due to the large size of several of the boxes to be retrieved, providing certified packagings for the transport operation is impracticable. Not only would costs be prohibitive (\$1-2 million per package), the design and certification process would involve 4-5 years or more. Based on the criteria in this PDC, and the operational controls imposed by the Safety Analysis Report for Packaging (SARP), onsite transport of the intended contents can be demonstrated to be not only safe, but cost-effective and timely when compared to certified packagings.

2.0 PACKAGE CONTENTS

2.1 PHYSICAL DESCRIPTION

From Solid Waste Burial Records, a wide variety of solids were placed in the drums and boxes. Vacuum pumps, centrifugal pumps, duct work, plastic, rags, filter boxes, scrap metal, glass, wood, packaging foam, metal furnaces, paper, rubber, stone, and absorbants are listed as inventory. Additionally, small amounts of absorbed organics were placed in some of the containers.

2.1.1 Chemical Constituent Source Term

Burial records do not indicate that other hazardous materials were placed in the packages; however, the W-113 Retrieval Packages shall be handled as mixed TRU/radioactive waste in accordance with the *Hazardous Material Packaging and Shipping*, WHC-CM-2-14 if retrieved package marking and labeling, or existing records indicate that hazardous materials, as defined in the Code of Federal Regulations (CFR), 49 CFR 171.8 (DOT 1992), are present in addition to the radioactive contents. Approximately $\frac{1}{2}$ of the contents inventory is considered combustible.

2.1.2 Radioisotopic Constituent Source Term

Plutonium oxides and their daughter products, and uranium oxides are the primary contaminants existing in the drums and boxes in Trench 218-W-4C. An inventory of the radionuclides listed at present consists of the following:

Ref. WHC-SD-TP-PDC-014

Rev. 0

Radionuclide	
^{238}Pu	^{241}Am
^{239}Pu	^{234}U
^{240}Pu	^{235}U
^{241}Pu	^{238}U
^{242}Pu	

For the purpose of performing dose consequence, radiological, and thermal analyses, a limiting source term is given in Table 1. The source is derived from the *Radioisotopic Characterization of Retrievably Stored Transuranic Waste at the Hanford Site*, WHC-SD-WM-TI-517 (WHC 1992b) for 20 year aged, 12% plutonium fuel.

The total amount of TRU material allowed in a W-113 Retrieval Package shall be 500 g. The total amount of natural uranium shall be limited to 1000 g (0.7% enrichment value). Enriched uranium may be allowed provided the total activities do not exceed the values listed for the uranium isotopes in Table 1.

2.2 TRANSPORTATION CLASSIFICATION

The transportation classification for the W-113 Retrieval Packages shall be Type B, Fissile, and Highway Route Controlled Quantity (HRCQ).

2.3 DISPOSAL CLASSIFICATION

The WHC-SD-W113-CDR-002 Conceptual Design Report lists the waste as suspect TRU. Disposal classification of the package contents shall be determined after future characterization and prior to disposal.

3.0 FACILITY OPERATIONS

3.1 ORIGINATING FACILITY

Packaging of the retrieved drums and boxes will take place at Trench 04 of the 218-W-04 Burial Ground. Retrieved containers will be placed on the base of the retrieval package while on the transport vehicle with appropriate dunnage and/or blocking and bracing material. The top and side wall portion

Ref. WHC-SD-TP-PDC-014 Rev. 0

Table 1.

Radionuclide	Activity (Ci)	Mass (g)
^{238}Pu	1.37×10^3	0.403 g
^{239}Pu	5.20×10^3	419.4 g
^{240}Pu	2.94×10^0	63.9 g
^{241}Pu	1.13×10^2	5.13 g
^{242}Pu	1.17×10^{-4}	0.15 g
^{241}Am	5.99×10^0	9.38 g
^{234}U	3.34×10^{-4}	0.05 g
^{235}U	1.51×10^{-5}	7.20 g
^{238}U	3.34×10^{-4}	1012 g
Total Activity (Ci)	1.29×10^2	-----
Total Decay Heat	2.52 W	-----

of the packagings will then be lifted over the containers and secured to the base of the retrieval packages. Figure 1 depicts a conceptual view of the operation.

Because the gross weight of the containers to be packaged is known, weighing of the packages prior to transfer is not required.

3.2 RECEIVING FACILITY

Retrieved boxes and drums will be transported to an interim storage facility located near the WRAP modules. There, the entire W-113 Retrieval Package, with its contents, will be off-loaded from the transporter for indefinite storage pending the opening of the WRAP facilities for processing of the contents.

Off-loading equipment shall meet the requirements of the *Hanford Hoisting and Rigging Manual* (RL 1993).

Figure 1. Conceptual View of Loading Operation.

4.0 PACKAGING/TRANSPORT SYSTEM DESIGN CRITERIA

4.1 GENERAL

The W-113 Retrieval Package packagings shall be approved for use as onsite, intra-area packagings for transferring up through Type B, HRCQ of radioactive material (DOT 1992) in accordance with the *Hazardous Material Packaging and Shipping*, WHC-CM-2-14. A combination of packaging performance and risk analysis will be used to demonstrate the safety of the transfer operations.

Evaluations shall be performed to address the ability of the packagings to provide containment, shielding, and nuclear sub-criticality for conditions normally incident to transport and for credible accidents. A combination of packaging performance by design analysis and/or testing, operational controls, and a risk assessment with dose consequence analysis will be used in the evaluation process.

The above evaluations shall be based on the design criteria listed in this PDC to ensure that adequate protection is provided for operating personnel, the public, and the environment as required by the *Hazardous Material Packaging and Shipping*, WHC-CM-2-14, and the *Environmental Compliance*, WHC-CM-7-5.

Ref. WHC-SD-TP-PDC-014

Rev. 0-A

4.2 PACKAGING DESIGN CRITERIA

4.2.1 Packaging Specification

The W-113 Retrieval Packages shall be designed as reusable, single containment packagings. The packaging system shall be bottom loading; i.e., it is intended that the materials to be packaged be placed on the base of the packagings, after which the remainder of the packagings shall be placed onto the base and secured with leak testable, gasketed closure systems. The side walls and top of the packagings shall be fabricated such that, when completed, the entire assemblies are one piece.

4.2.1.1 Materials of Construction

The W-113 Retrieval Package base, sides, and top shall be manufactured of American Society for Testing and Materials (ASTM), ASTM A36 carbon steel, or stronger. The steel shall be certified per ASTM.

The most cost-effective materials shall be chosen to meet packaging safety requirements. All other fabrication materials of the W-113 Retrieval Packages and ancillary devices (i.e., tiedowns, dunnage, lifting equipment, closure tools, etc.) shall be certified as meeting an appropriate nationally recognized specification (i.e., ASTM, AISI, etc.), and/or shall meet the requirements that are consistent with the applicable Westinghouse Hanford Company (WHC) Quality Category in Section 5.3 of this PDC. Material specifications shall, as a minimum, describe the chemical composition, minimum yield strength, and ultimate strength. Vendor supplied materials such as gaskets or mechanical components shall be traceable to valid manufacturer's data or performance specifications.

Further, all components of the packagings shall be evaluated to ensure that the possibility of brittle fracture does not preclude the use of the packaging at temperatures ranging from -23 °C (-10 °F) to 46 °C (115 °F).

4.2.1.2 Fabrication Methods

All welds and welders shall be qualified per the American National Standards Institute (ANSI)/American Welding Society (AWS), D1.1. Welds shall be inspected and qualified per ANSI/AWS D1.1.

The interior and exterior surfaces and corners shall be sufficiently rounded and smooth to enable easy decontamination. Consideration shall be given in the design to avoid potential contamination traps to the greatest extent practicable.

Ref. WHC-SD-TP-PDC-014

Rev. 0

4.2.1.3 Paint

All interior and exterior surfaces of the W-113 Retrieval Packages shall be painted. Painting application methods for carbon steel structures shall be in accordance with the Steel Structures Painting Council's (SSPC), Steel Structures Painting Manual, Volume 2.

4.2.2 Packaging Dimensions

In order to minimize void space and provide efficient packaging of the contents of the burial trench, five different size packagings are required. Sizes are identified in the following table.

Size of Box to be Packaged (Length x Width x Height)
16 ft x 7 ft x 12 ft
12 ft x 8 ft x 7 ft, 1 in.
12 ft, 6 in. x 4 ft, 3 in. x 3 ft, 10 in.
7 ft x 6 ft x 6 ft
6 ft x 6 ft x 7 ft

4.2.3 Weight of Contents

For each size packaging the design weight of the contents is listed below in the following table.

Size of Box to be Packaged	Contents weight (lb)
16 ft x 7 ft x 12 ft	29,500
12 ft x 8 ft x 7 ft, 1 in.	16,500
12 ft, 6 in. x 4 ft, 3 in. x 3 ft, 10 in.	5,000
7 ft x 6 ft x 6 ft	6,000
6 ft x 6 ft x 7 ft	6,000

4.2.4 Maximum Gross Weight

The maximum gross weight for any package shall not exceed 75,000 lb.

Ref. WHC-SD-TP-PDC-014

Rev. 0

4.2.5 Venting

The packages shall be tapped and plugged in two places (opposite sides, opposing corners, upper section) to accommodate installation of two NucFit Model 013 filtered vents.

4.2.6 Lifting Attachments

Any lifting attachment that is a structural part of the W-113 Retrieval Packages shall be designed with a minimum safety factor of three to the yield strength, and five to the ultimate strength. Stresses over the entire structure shall be considered. The design of the lifting device(s) shall be such that failure of any lifting device under excessive load will not impair the ability of the W-113 Retrieval Packages to meet other requirements of this PDC. Any other part of the W-113 Retrieval Packages which could be used for lifting must be capable of being rendered inoperable for lifting the W-113 Retrieval Packages during transfer, or must be designed with strength equivalent to that required for the lifting attachments.

If lifting attachments are incorporated into the packaging design for lifting of the lid only, and not the entire package with its contents, they shall be either designed such that they cannot be used for lifting the entire package with its contents, or the design shall require that the lid-only lifting attachments be appropriately marked to prevent attempts at lifting the entire package with its contents.

4.2.7 Tiedown Attachments

Tiedown attachments which are a structural part of the W-113 Retrieval Package must be capable of withstanding, without generating stress in any material of the W-113 Retrieval Package in excess of yield strength, a static force applied to the center of gravity of the W-113 Retrieval Package having a vertical component of two times the weight of the W-113 Retrieval Package with its contents, a horizontal component along the direction in which the vehicle travels of ten times the weight of the W-113 Retrieval Package with its contents, and a horizontal component in the transverse direction of five times the weight of the W-113 Retrieval Package with its contents.

Any other structural part of the W-113 Retrieval Package which could be used for tiedown must be capable of being rendered inoperable for tying down the W-113 Retrieval Package during transfer, or must be designed with strength equivalent to that required for the tiedown attachments.

Each tiedown attachment which is a structural part of the W-113 Retrieval Package must be designed so that failure of the attachment under excessive load would not impair the ability of the W-113 Retrieval Package to meet other requirements of this PDC.

Ref. WHC-SD-TP-PDC-014

Rev. 0-A

4.2.3 Closure Design

The W-113 Retrieval Package must include a gasketed containment system securely closed by a positive fastening system which cannot be opened unintentionally.

4.2.9 Containment

The W-113 Retrieval Package shall be designed such that during normal transfer operations, the conditions for which are specified in Section 5.1.1, there is no visible loss of contents, less than a 20% increase in external radiation levels, and no loss of criticality control.

4.2.10 Shielding

No special shielding devices are required for the W-113 Retrieval Package.

4.2.11 Service Life

The W-113 Retrieval Package shall be designed for a minimum service life of 20 years. Communication labels and markings shall have a 20 year life expectancy in a non-climatically controlled building on the Hanford Site. Gasket material used for closure shall be demonstrated to maintain its integrity at a constant temperature of 70 °C (158 °F).

4.2.12 Decontamination

The general features of the package shall lend themselves to easy decontamination.

4.3 TRANSPORT SYSTEM

4.3.1 General

The transport operation involves loading the retrieved boxes and drums onto the base of the W-113 Retrieval Package while it is on the transporter. Once the retrieved package is on the base of the W-113 Retrieval Package, the remainder of the W-113 Retrieval Package is lowered onto the base, where the package is subsequently sealed with a gasketed closure and tied down for transport.

Transport of the W-113 Retrieval Package with its contents is from the Trench 04 of the 218-W-4C Burial Ground to a storage facility near the WRAP Facility. Total loaded transport distance is approximately $\frac{1}{4}$ mile, the majority of which is on paved Hanford Site roadway.

At the receiving facility, the entire W-113 Retrieval Package with its contents will be removed from the transporter.

Ref. WHC-SD-TP-PDC-014

Rev. 0

4.3.2 Transport Vehicle

The transport vehicle shall be a tractor-trailer using either a flatbed or lowboy style trailer. The transport vehicle shall have a manufacturer's rated load capacity of a minimum of 75,000 lb. Consideration shall be given to the bed dimensions and structural configuration of the trailer to ensure adequate tiedown of the W-113 Retrieval Package per the requirements of Section 4.3.3.

4.3.3 Tiedown System

An engineered tiedown system shall be used to secure the W-113 Retrieval Package to the transport vehicle(s) and shall be in accordance with the requirements of the following criteria.

4.3.3.1 Securement Systems

(a) *Application and scope of the rules in this section.* The rules in this section apply to tiedown assemblies (including chains, cables, steel straps, and fiber webbing), other securement devices, and attachment or fastening devices used in conjunction therewith, which are used to secure cargo to motor vehicles in transit. All devices which are used to secure cargo to the transporter must conform to the rules in this section.

(b) *Tiedown assemblies.* The aggregate static breaking strength of the tiedown assemblies used to secure an article against movement in any direction must be at least $1\frac{1}{2}$ times the weight of the article. Chain used as a component of a tiedown assembly must conform to the requirements of the November 1975 edition of the National Chain Specifications, applicable to all types of chain. Steel strapping used as a component of the tiedown assembly must conform to the requirements of Federal Specification No. QQ-S-781 (1969). Steel strapping that is 1 in. wide or wider must have at least two pairs of crimps in each seal and, when end-over-end laps are formed, must be sealed with at least two seals.

(c) *Load binders and hardware.* The strength of the load binders and hardware that are part of, or used in conjunction with, a tiedown assembly must be equal to, or greater than the minimum strength specified for that tiedown assembly in paragraph (b) of this section.

(d) *Attachments to the vehicle.* The hook, bolt, weld, or other connector by which a tiedown assembly is attached to a vehicle, and the mounting place and means of mounting the connector, must be at least as strong as the tiedown assembly when that connector is loaded in any direction in which the tiedown assembly may load it.

(e) *Winches or other fastenings.* The anchorages of a winch or other fastening device mounted on a vehicle and used in conjunction with a tiedown assembly must have a combined tensile strength equal to, or greater than, the strength of the tiedown assembly.

Ref. WHC-SD-TP-PDC-014

Rev. 0

(f) *Adjustability.* A tiedown assembly and its associated connectors and attachment devices must be designed, constructed, and maintained so that the driver of an in-transit vehicle can tighten them. However, the rules in this paragraph do not apply to a securement system in which the tiedown assembly consists of steel strapping or to a tiedown assembly which is not required by the rules in this section.

4.3.3.2 Blocking and Bracing

(a) *Protection against longitudinal movement.* The cargo must be secured so that, when the vehicle decelerates at a rate of 20 ft/s/s, the cargo will remain on the vehicle and will not penetrate the vehicle's front-end structure.

(b) *Protection against lateral movement.* The cargo must either be securely blocked or braced against the side, sideboards, or stakes of the vehicle or be secured by devices that conform to either of the following:

- (1) The vehicle must have at least one tiedown assembly that meets the requirements of Section 4.3.3.1 for each 10 linear feet of lading or fraction thereof.
- (2) The vehicle must have other means of preventing shifting or falling cargo which are similar to, and at least as effective as, the requirement specified in (1).

4.3.3.3 Additional Tiedown Requirements

Consideration shall be given to tiedown methods (such as remote operations or permanent systems integral to the packaging and transport vehicle) to maximize the distance and/or minimize the time spent near the payload.

5.0 GENERAL REQUIREMENTS

5.1 TRANSPORTATION SAFETY

Because the W-113 Retrieval Packages will not be packages certified by the U.S. Nuclear Regulatory Commission (NRC) or the U.S. Department of Energy (DOE) as Type B packagings per the requirements of the Code of Federal Regulations (CFR), 10 CFR 71 (NRC 1992), the safety of onsite transport of the intended contents must be demonstrated to be equivalent to certified packagings as required by the RL Order 5480.1, Change 1, Chapter III (RL 1982). This safety shall be documented in a SARP, as required by the *Hazardous Material Packaging and Shipping*, WHC-CM-2-14.

Ref. WHC-SD-TP-PDC-014

Rev. 0-A

The safety of transfers utilizing the W-113 Retrieval Packages shall be demonstrated by a combination of packaging performance by design analysis and/or testing, operational controls, and a probabilistic risk assessment based on accident frequency and dose consequence analysis. The approved SARP shall provide the documentation for these evaluations and exist as the controlling document for all operational controls required.

5.1.1 Normal Conditions of Transfer

For conditions normally incident to transport, the SARP shall evaluate the packaging design for its ability to maintain containment, shielding, and nuclear criticality control when subjected to the following.

5.1.1.1 Containment

The W-113 Retrieval Packages must be designed, constructed, and prepared for shipment so that when subjected to the following conditions and tests, there will be no visible loss or dispersal of radioactive contents, no significant increase in external radiation levels, and no substantial reduction in the effectiveness of the packagings.

For conditions normally incident to transport, the W-113 Retrieval Packages shall be evaluated, either by testing or analysis, to meet the containment criteria listed above under the following conditions:

(a) Heat

An ambient temperature of 38 °C (100 °F) in still air, and insolation according to the following table:

Form and Location of Surface	Total Insolation for a 12-Hour Period (g cal/cm ²)
Flat surface transported horizontally - Base - Other Surfaces	None 800
Flat surfaces not transported horizontally	200
Curved surfaces	400

(b) Cold

An ambient temperature of -40 °C (-40 °F) in still air and shade.

Ref. WHC-SD-TP-PDC-014

Rev. 0-A

(c) Vibration

Vibration normally incident to transport.

The W-113 Retrieval Packages shall be evaluated to demonstrate containment when transported from the burial ground, over the roadway to the receiving facility. This evaluation shall include analysis for fatigue failure.

(d) Penetration

Impact of the hemispherical end of a vertical steel cylinder of 3.2 cm (1½ in.) diameter and 6 kg (13 lb) mass, dropped from a height of 1 m (40 in.) onto the exposed surface of the package which is expected to be most vulnerable to puncture. The long axis of the cylinder must be perpendicular to the package surface.

(e) Free Drop

A free drop through a distance specified below onto a flat, horizontal concrete surface in a position for which maximum damage is expected.

Package Weight		Free Drop Distance	
Kilograms	Pounds	Meters	Feet
5,000 or less	(11,000)	1.2	(4)
5,000 to 10,000	(11,000 to 22,000)	0.9	(3)
10,000 to 15,000	(22,000 to 33,000)	0.6	(2)
More than 15,000	(more than 33,000)	0.3	(1)

5.1.1.2 Chemical and Galvanic Reactions

The W-113 Retrieval Packages and dunnage must be of materials and construction which assure that there will be no significant chemical, galvanic, or other reaction among the packaging components or between packaging components and the contents, including possible inleakage from water to the maximum credible extent.

Ref. WHC-SD-TP-PDC-014

Rev. 0-A

5.1.1.3 Surface Contamination

During transfer operations, removable contamination on the exterior surfaces of the packages shall not exceed the following limits:

- 220 dpm/100 cm² for alpha contamination.
- 2,200 dpm/100 cm² for beta-gamma contamination.

5.1.1.4 Thermal

Analysis of the containment during transfer and storage shall consider the effects of a Hanford environment temperature range of -33 °C (-27 °F) to 46 °C (115 °F). Decay heat shall be limited such that seal temperatures remain below 70 °C (158 °F) at the maximum Hanford environment temperature and solar insolation.

The W-113 Retrieval Packages shall be designed, constructed, and loaded so that in still air at 38 °C (110 °F) and in the shade, no accessible surface of the packages will have a temperature exceeding 50 °C (122 °F) during transfer and storage.

5.1.1.5 Shielding

Burial records indicate that the drums and boxes to be retrieved and packaged in the W-113 Retrieval Packages have a very low dose rate (< 1 mrem/h). No additional shielding shall be incorporated into the packaging design. Dose rates shall be limited to 200 mrem/h on the surface of the packages and 10 mrem/h when measured at 2 m from the packages.

5.1.1.6 Criticality

Only one W-113 Retrieval Package shall be on the transport vehicle per shipment. However, it is possible that several drums and boxes from the trench will be loaded into a W-113 Retrieval Package at one time. Therefore, the total number of retrieved drums and boxes that may be loaded into a W-113 Retrieval Package shall be limited to no greater than 20% of the number determined to meet the following criteria:

The contents shall remain subcritical for any arrangement of retrieved drums and boxes, assuming also:

- The most reactive credible configuration consistent with the chemical and physical form of the allowed packaged material.
- Clustering of the contents and close reflection of the contents array by water on all sides.

Ref. WHC-SD-TP-PDC-014

Rev. 0

5.1.2 Accident Events

During the preparation of the SARP, a risk assessment shall be performed on the proposed transfer to determine credible and probable events. Credible events, probable events, and incredible events with a frequency exceeding 10^{-7} per year and with an offsite dose consequence exceeding 25 rem effective dose equivalent (EDE) shall be addressed in the SARP. Incredible events with a dose to an offsite individual of less than 25 rem EDE do not require evaluation. In addition, the W-113 Retrieval Package shall be capable of retaining its contents and limiting radiation exposure under unplanned credible and probable events during transfer in accordance with the following criteria.

5.1.2.1 Incredible Events

Any unplanned event which has a probability less than 10^{-6} per year is considered incredible. Such events exceeding an accident frequency of 10^{-7} per year shall not result in an offsite dose consequence of greater than 25 rem EDE.

5.1.2.2 Credible Events

An unplanned event which has a probability of between 10^{-6} and 10^{-3} per year shall not lead to a radiation exposure of greater than 5000 mrem EDE to the maximum exposed onsite individual, or 500 mrem EDE to an offsite individual. These unplanned events are considered credible.

5.1.2.3 Probable Events

An unplanned event that has a calculated frequency greater than 1×10^{-3} per year shall not lead to a radiation dose greater than 200 mrem EDE to an individual onsite, or 10 mrem EDE offsite. Any unplanned event that has an unknown frequency that cannot be shown to be less than 1×10^{-6} per year shall be conservatively considered probable (i.e., frequency greater than 1×10^{-3} per year).

5.2 ALARA

The design features of the W-113 Retrieval Packages shall be consistent with the requirements of the *ALARA Program Manual*, WHC-CM-4-11. Exposure of personnel to radiological and other hazardous materials associated with the loading, closure, tiedown, transport, off-loading, and any other operation associated with handling the W-113 Retrieval Packages shall be minimized. Cost benefit analysis shall be performed as needed, to determine the best balance between exposure and economical design.

Ref. WHC-SD-TP-PDC-014

Rev. 0

5.3 QUALITY ASSURANCE

The packaging design and/or the SARP shall specify inspection and testing requirements. All inspections and tests shall be documented. Inspection during fabrication of the W-113 Retrieval Packages shall include normal verification of dimensions and visual inspection of materials and workmanship. Design, fabrication, testing, and verification activities shall be in accordance with the *Quality Assurance Manual*, WHC-CM-4-2.

A graded approach for the Quality Assurance requirements shall be used. All packaging components shall be assigned a Quality Category appropriate to its impact on packaging safety. The three Quality Categories are as follows:

(a) Quality Category A

Critical Impact - Includes items and activities that could directly impact the public radiological health and safety. This classification includes items and activities for which omission, error, or failure could result in consequences exceeding the requirements specified in or based on applicable Federal Regulations. All material used in fabrication and fabrication welding shall be certified and documented.

(b) Quality Category B

Major Impact - Includes items and activities for which failure could indirectly impact public radiological health and safety. This classification encompasses items and activities whose failure could adversely impact the performance of Category A items. Fabrication material used shall be procured in such a manner that it is verifiable to be as specified in drawings.

(c) Quality Category C

Minor Impact - Includes items for which failure is unlikely to result in a significant adverse impact on public radiological health and safety. Materials should be of standard commercial grade or better.

5.4 DESIGN FORMAT

Development of design drawings, design changes, and other design documentation shall be in accordance with the *Standard Engineering Practices*, WHC-CM-6-1, and the *Drafting Standards Manual*, WHC-CM-6-3.

5.5 ENVIRONMENTAL COMPLIANCE

Actions and conditions for the protection of the environment during transfer and storage of the W-113 Retrieval Packages shall comply with the requirements of the *Environmental Compliance*, WHC-CM-7-5.

AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

8 of 8

Ref. WHC-SD-TP-PDC-014 Rev. 0

6.0 REFERENCES

- DOT, 1992, "Protection Against Shifting or Falling Cargo." Title 49. *Code of Federal Regulations*, Part 393. U.S. Department of Transportation. Washington, D.C.
- NRC, 1992, "Packaging and Transportation of Radioactive Materials." Title 10. *Code of Federal Regulations*, Part 71, U.S. Nuclear Regulatory Commission. Washington D.C.
- RL, 1982, "Safety Requirements for the Packaging of Fissile and Other Radioactive Material," *Environmental Protection, Safety, and Health Protection Program for RL*, RL 5480.1, Chapter III, Change 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- RL, 1993, *Hanford Site Hoisting and Rigging Manual*, DOE-RL-93-36, U.S. Department of Energy, Richland Operations Office, Richland, Washington, January 1993.
- WHC-CM-2-14, *Hazardous Material Packaging and Shipping*, Westinghouse Hanford Company, Richland, Washington.
- WHC-CM-4-2, *Quality Assurance Manual*, Westinghouse Hanford Company, Richland, Washington.
- WHC-CM-4-11, *ALARA Program Manual*, Westinghouse Hanford Company, Richland, Washington.
- WHC-CM-6-1, *Standard Engineering Practices*, Westinghouse Hanford Company, Richland, Washington.
- WHC-CM-6-3, *Drafting Standards Manual*, Westinghouse Hanford Company, Richland, Washington.
- WHC-CM-7-5, *Environmental Compliance*, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1992a, *Project W-113, Solid Waste Retrieval Facility, Phase 1 Conceptual Design Report*, WHC-SD-W113-CDR-002, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1992b, *Radioisotopic Characterization of Retrievably Stored Transuranic Waste at the Hanford Site*, WHC-SD-WM-TI-517, Westinghouse Hanford Company, Richland, Washington.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX 3

Support Building Consolidation

THIS PAGE INTENTIONALLY LEFT BLANK

Work Order No. ER3258

LETTER REPORT

W-113 SUPPORT BUILDINGS OPTIMIZATION WORK ORDER NO. ER3258

INTRODUCTION

The W-113 Functional Design Criteria (FDC) has been revised since the Conceptual Design Report (CDR) was written. These changes affect the support buildings, among others. The support buildings consist of the Trench Operations Building, the Retrieval Staff Change Building, the NDE/NDA Building, and the General Office Building. This letter report examines those changes and their consequences.

SUMMARY CONCLUSIONS, AND RECOMMENDATIONS

Due to the FDC change of making the NDE/NDA equipment mobile, the NDE/NDA building can be eliminated completely. The Retrieval Staff Change Building (Sketch 1) can be changed from the size shown in the CDR to a 28' wide x 60' long double-wide trailer. There is no further need for separate facilities for changing into "Blues" and "SWP's". The General Office Building (Sketch 2) can be rearranged to incorporate the combined lunch-conference room, manager's office, WRAM office and bay areas for the secretary and technical offices. The size of the General Office Building will not change from that in the CDR. The Trench Operation Building can be revised by removing the office. Due to the decrease in lag storage requirements, the size of the building can probably be decreased, but that will depend upon the NDE equipment size and if it will be located in the trench.

APPROACH/EVALUATION

This study was based on the new FDC, WHC-SD-W113-FDC-001, Rev. 2, dated July, 1993. The FDC changed many of the requirements for the buildings. The NDE/NDA equipment will be mobile and the operations will take place in either the trench, if there is room, or in the Trench Operations Building. This eliminated the NDE/NDA building and any people working in "blues". With no "blues" there is no need for segregation of the dressing areas. The number of people working in and supporting retrieval were decreased. The lag storage requirements for drums and boxes were reduced.

The Retrieval Staff Change Building (Sketch 1) no longer requires decontamination showers or the space for as many people to change. The Change Building is based on a 28' wide x 60' long, modular double-wide trailer. This will enable it to be relocated with a minimum of effort. The step-off line has been reduced from two lines to one line.

The General Office Building (Sketch 2) has been rearranged from the CDR effort to incorporate a larger lunch room that is also designed to serve as the conference room. The manager's office is still located in this building and the HPT office has been moved and will serve as a WRAM office for retrieval

operations at the trench. There are open bay areas that will serve as the secretary's office and the technical staff's offices. The General Office Building can also incorporate the control and communications rooms in the open areas as needed.

UNCERTAINTIES AND RECOMMENDATIONS FOR FURTHER STUDY

The size of the Trench Operations Building is dependent on final determination of the NDE equipment location. A study to analyze operations within the trench enclosure would be beneficial in determining whether the NDE activity can be performed in the trench or whether space constraints restrict this operation from the trench.

APPENDICES

Appendix A

WMC-SD-W113-ACDR-001
Rev. 0
Page 575

Work Order No. ER3253

APPENDIX A

SKEETCHES

THIS PAGE INTENTIONALLY LEFT BLANK

RETRIVAL STATE CHANGE BUILDING
FLOOR PLAN

SKETCH 1

THIS PAGE INTENTIONALLY LEFT BLANK

Work Order No. E33252

GENERAL OFFICE BUILDING FLOOR PLAN

(BUILDING UTILIZES 2 11' 0" WIDE X 66' 0" LONG TRAILERS)

SKETCH 2

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX H

ACDR Cost Estimate

WHC-SD-W113-ACDR-001

Rev. 0

Page 578A

THIS PAGE INTENTIONALL LEFT BLANK

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359
FILE NO. W113BAA1

**** TEST - INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R01 - PROJECT COST SUMMARY

PAGE 1 OF 12
DATE 01/27/94 09:24:32
BY KLR/LGH/DEA/DLM

COST CODE =====	DESCRIPTION =====	ESCALATED TOTAL COST =====	CONTINGENCY % =====	TOTAL =====	TOTAL DOLLARS =====
000	ENGINEERING	3,100,000	18	550,000	3,650,000
460	IMPROVEMENTS TO LAND	380,000	20	80,000	460,000
501	BUILDINGS	3,530,000	25	880,000	4,410,000
600	UTILITIES	590,000	25	150,000	740,000
700	SPECIAL EQUIP/PROCESS SYSTEMS	8,760,000	24	2,070,000	10,830,000
900	OTHER PROJECT COST	19,070,000	0	0	19,070,000
	(ADJUSTED TO MEET DOE 5100.4)	70,000		-30,000	40,000
PROJECT TOTAL		35,500,000	11	3,700,000	39,200,000

TYPE OF ESTIMATE	CONCEPTUAL ESTIMATE	JANUARY 27, 1994
ARCHITECT ENGINEER		
OPERATING CONTRACTOR		

REMARKS: ESTIMATE REFLECTS CHANGES REQUESTED IN WMC LOI #9360548 DATED DECEMBER 9, 1993.

THIS ESTIMATE IS TO BE USED FOR COMPARISON ONLY WITH CONCEPTUAL ESTIMATE DATED SEPT 9, 1992.

THIS ESTIMATE DOES NOT INCLUDE CURRENT LABOR OR ESCALATION RATES AND SHOULD NOT BE USED FOR BUDGET.

(ROUNDED/ADJUSTED TO THE NEAREST " 10,000 / 100,000 " - PERCENTAGES NOT RECALCULATED TO REFLECT ROUNDING)

WMC-SD-W113-ACDR-001
Rev. 0
Page 579

PAGE 2 OF 12
DATE 01/27/94 09:24:38
BY KLR/LGN/DEA/DLM

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R02 - WORK BREAKDOWN STRUCTURE SUMMARY

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359
FILE NO. W113AA1

WBS	DESCRIPTION	ESTIMATE SUBTOTAL	ONSITE INDIRECTS	SUB TOTAL	ESCALATION %	SUB TOTAL	CONTINGENCY %	TOTAL DOLLARS
111100	GENERAL	195072	0	195072	12.22	23838	15	251744
111101	SITE PLAN	252620	0	252620	12.22	30869	15	326013
111102	GENERAL OFFICE BUILDING	74706	0	74706	12.22	9129	15	96411
111103	RETRIAL STAFF CHANGE BUILDING	80370	0	80370	12.22	9821	20	108229
111104	TRENCH ENCLOSURE/OPER. BLDGS	539968	0	539968	12.22	65986	20	727142
SUBTOTAL 1111	DESIGN - CATEGORY 1	1142736	0	1142736	12.22	139643	18	1509539
111200	GENERAL	320119	0	320119	12.22	39119	15	413124
111201	SITE PLAN	32026	0	32026	12.22	3914	20	43127
111202	GENERAL OFFICE BUILDING	1420	0	1420	12.25	174	15	1833
111203	RETRIAL STAFF CHANGE BUILDING	7952	0	7952	12.22	972	20	10708
111204	TRENCH ENCLOSURE/OPER. BLDGS.	28139	0	28139	12.22	3438	25	39472
111210	PROJECT SUPPORT	377832	0	377832	12.22	46173	15	487603
SUBTOTAL 1112	DESIGN - CATEGORY 2	767488	0	767488	12.22	93790	16	995867
SUBTOTAL 11	DEFINITIVE DESIGN (OFFSITE)	1910224	0	1910224	12.22	233433	17	2505406
120001	ENGINEERING DURING CONST.	315027	0	315027	26.00	81907	20	476319
120002	ENG/INSP. SUPPORT	447575	0	447575	26.00	116371	20	676732
SUBTOTAL 12	CONST ENG/INSP (OFFSITE A/E)	762602	0	762602	26.00	191278	20	1153051
SUBTOTAL 1	ENGINEERING	2672826	0	2672826	16.15	431711	18	3658457
200000	PROCUREMENT (E/C CONTRACTOR)	5863511	0	5863511	19.08	1118758	25	8727836
SUBTOTAL 2	PROCUREMENT	5863511	0	5863511	19.08	1118758	25	8727836
320002	TRENCH ENCLOSURE BLDG./TRUCK LOCK	1932801	309247	2242048	19.66	440786	25	3353544
320003	TRENCH OPERATION BUILDING	266982	42718	309700	19.66	60886	25	463232
320004	STAFF CHANGE & GENERAL OFFICE BLDG	680815	108931	789746	19.66	155264	25	1181262
320005	SITE GRADING & LEVELING	53912	8626	62538	19.66	12295	20	89799
320006	ROADS & PARKING	95505	15281	110786	19.66	21780	20	159080
320007	FENCING	25909	4145	30054	19.66	5909	20	43156
320008	STABILIZATION	98893	15823	114716	19.66	22553	20	164723

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359
FILE NO. W113BAA1

**** TEST - INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R02 - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 3 OF 12
DATE 01/27/94 09:24:38
BY KLR/LGH/DEA/DLM

WBS	DESCRIPTION	ESTIMATE SUBTOTAL	ONSITE INDIRECTS	SUB TOTAL	ESCALATION % TOTAL	SUB TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS
320009	WATERLINES	216495	34639	251134	19.66	49373	25	375634
320010	SITE ELECTRICAL & INSTRUMENTATION	180338	28854	209192	19.66	41127	25	312899
	SUBTOTAL 32 FIXED PRICE CONSTRUCTION	3551650	568264	4119914	19.66	809973	25	6143329
330000	PLANT FORCES CONSTRUCTION	3675	0	3675	25.61	941	25	5770
	SUBTOTAL 3 CONSTRUCTION	3555325	568264	4123589	19.67	810914	25	6149099
400000	PROJECT INTEGRATION/MGMT. (O/C)	1346000	0	1346000	0.00	0	16	1561360
500000	OTHER PROJECT COST	19070000	0	19070000	0.00	0	0	19070000
PROJECT TOTAL		32,507,662	568,264	33,075,926	7.14	2,361,383	11	39,166,752

** KAISER ENGINEERS INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R03 - ESTIMATE BASIS SHEET

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER2359
FILE NO. W113BAA1

1. DOCUMENTS AND DRAWINGS

DOCUMENTS: WHC-SD-W113-CDR-002 REV. 0

DRAWINGS: PRELIMINARY SKETCHES

2. MATERIAL PRICES

UNIT COSTS REPRESENT CURRENT PRICES FOR SPECIFIED MATERIAL.

3. LABOR/LIQUIDATION RATES

CURRENT KEN BASE CRAFT RATES AS ISSUED BY KEN FINANCE (EFFECTIVE 10-28-91) INCLUDE FRINGE BENEFITS, LABOR INSURANCE, TAXES AND TRAVEL WHERE APPLICABLE. PER HANFORD SITE STABILIZATION AGREEMENT, APPENDIX A (EFFECTIVE 9-2-91). ED & I HOURLY RATES ARE BASED ON THE 1992 FISCAL YEAR BUDGET LIQUIDATION RATES AS ISSUED BY KEN FINANCE (EFFECTIVE 10-28-91).

4. GENERAL REQUIREMENTS/TECHNICAL SERVICES

8.) FIXED PRICE CONTRACTOR OVERHEAD, PROFIT, BOND AND INSURANCE COSTS HAVE BEEN APPLIED AT THE FOLLOWING PERCENTAGES AND ARE REFLECTED IN THE "OH&P / B & I" COLUMN OF THE ESTIMATE DETAIL:
20% LABOR, 10% MATERIAL & 5% SUBCONTRACTS

5. ESCALATION

ESCALATION CALCULATED BY THE HANFORD MATERIAL & LABOR ESCALATION STUDY, FEBRUARY, 1992.

6. ROUNDING - LINE ITEMS:

U.S. DEPARTMENT OF ENERGY - DOE ORDER 5100.4 PAGE J-2 SUBPARAGRAPH (M), REQUIRES ROUNDING OF A COST ESTIMATE TO \$10,000 FOR ITEM COST AND \$100,000 FOR TOTAL COST. REFERENCE: DOE 5100.4, FIGURE 1-11, DATED 10-31-84.

7. REMARKS

A.) EFFECTIVE OCTOBER 28, 1991, A THREE PER CENT (3%) CHARGE HAS BEEN APPLIED TO THE CONTRACT ADMINISTRATION FACTOR FOR SUBCONTRACT ADMINISTRATION TO COVER THE GENERAL AND ADMINISTRATIVE COST. THIS COST APPEARS IN THE ADMINISTRATION TOTAL COLUMN OF THE "ONSITE INDIRECT COSTS BY WBS" REPORT. (KEHR07)

B.) NDA/NDE BUILDING

* PLUMBING PRICE WAS DERIVED BY PER EACH FIXTURE ON ESTIMATED QUANTITY.
* FIRE PROTECTION SYSTEM WAS PRICED PER SQUARE FOOT.
* ASSUME BUILDING TO BE INSULATED.
* ESTIMATE INCLUDES SPECIAL PROTECTIVE FLOOR COATING INSIDE BUILDING.
* NDA/NDE EQUIPMENT PROVIDED BY WMC.
NOTE: THE NDA/NDE BUILDING HAS BEEN DELETED IN THIS ESTIMATE.

** KAISER ENGINEERS INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R03 - ESTIMATE BASIS SHEET

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER2359
FILE NO. W1138AA1

- C.) TRENCH ENCLOSURE BUILDING
* ASSUME SHEET PILING TO BE USED WILL BE 30' DEPTH.
* FIRE PROTECTION IS PRICED OUT AS A PER SQUARE FOOT ALLOWANCE.
- D.) TRENCH OPERATION BUILDING
* HVAC TO BE PROVIDED IN OFFICE AREA ONLY.
* FLOOR OF BUILDING TO BE 6" THICK CONCRETE WITH CURBS.
- E.) GENERAL OFFICE & CHANGE ROOM
* PRICE FOR OFFICE BUILDING WAS PROVIDED BY VENDOR FROM PAST ACTUAL COST ON SIMILAR FACILITIES.
* ASSUME OFFICE MODULARS TO BE CONSTRUCTED TO STANDARD LENGTHS & WIDTHS
* CHANGE ROOM BUILDING TO BE MODULAR OR TRAILER.
- F.) SITE GRADING & LEVELING
* AN ALLOWANCE WAS USED FOR QUANTITIES REQUIRED TO LEVEL SITE.
- G.) PROJECT INTEGRATION AND OTHER PROJECT COSTS
* PRICES FOR THESE ACTIVITIES WERE PROVIDED BY WMC AND INCLUDE ESCALATION.
- H.) THE DEFINITIVE DESIGN PORTION OF THIS ESTIMATE (WBS 11) REPRESENTS THE COST FOR THE OFFSITE A/E TO COMPLETE THIS EFFORT, AND WAS PREPARED, BASED ON PLANNING SHEETS & HISTORICAL DATA PROVIDED BY THE ENGINEER/CONSTRUCTOR DESIGN TEAM. SEE "STATEMENT OF WORK", PROJECT W-113 SOLID WASTE RETRIEVAL FACILITY PHASE 1, DATED SEPTEMBER 02, 1992 FOR DELIVERABLES, RISKS, UNCERTAINTIES AND ASSUMPTIONS RELATED TO THIS PLANNING EFFORT.
- I.) ENGINEERING/INSPECTION DURING CONSTRUCTION HAS BEEN MANLOADED BASED ON HISTORICAL DATA COMPILED FROM PROJECTS SIMILAR IN NATURE TO THIS PROJECT.
- J.) HOURS HAVE BEEN ADDED TO THE PROJECT MANAGER'S ACCOUNT FOR THE PREPARATION TIME OF A TITLE 1 DESIGN REPORT AT 40 HOURS PER DISCIPLINE.
- K.) ESTIMATE ASSUMES PROJECT TO BE ISSUED AS THREE BID PACKAGES.

GENERAL:

- =====
- * ITEMS THAT SHOW UP IN SUBCONTRACTS COLUMN OF ESTIMATE ARE UNIT PRICE AND INCLUDE CONTRACTORS OVERHEAD AND PROFIT.
 - * ASSUME ALL AREAS DISTURBED DURING CONSTRUCTION TO BE STABILIZED WITH 3" LAYER OF CRUSHED ROCK.
 - * THE ELECTRICAL ESTIMATE IS BASED ON UNIT COST DATA FROM MEANS FOR SIMILAR TYPE CONSTRUCTION. THIS WAS NECESSARY DUE TO THE PRESENT LEVEL OF DESIGN.
 - * ASSUME NO ESCORTS

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER2359
FILE NO. W113BAA1

**** KAISER ENGINEERS INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R03 - ESTIMATE BASIS SHEET

PAGE 6 OF 12
DATE 01/12/94 05:25:44
BY KLR/DEA

RE: DOE 4700.1A

TOTAL PROJECT COST: TPC INCLUDES ALL GENERIC RESEARCH AND DEVELOPMENT (R&D), OPERATING, PLANT AND CAPITAL EQUIPMENT COSTS, SPECIFICALLY ASSOCIATED WITH PROJECT CONSTRUCTION UP TO THE POINT OF ROUTINE OPERATIONS, WHICH WILL INCLUDE BUT NOT BE LIMITED TO:

- * TOTAL ESTIMATED CONSTRUCTION COSTS.
- * PRE-TITLE 1 ACTIVITIES, SUCH AS:
 - CONCEPTUAL CDR
 - PRELIMINARY SAFETY ANALYSIS REPORT, IF INITIATED AND PREPARED AS PART OF THE CDR.
 - PREPARATION OF CONSTRUCTION PROJECT DATA SHEETS, DESIGN CRITERIA, NATIONAL ENVIRONMENTAL POLICY ACT (NEPA) DOCUMENTATION, AND FORMULATIONS OF QUALITY ASSURANCE CRITERIA.
- * R&D NECESSARY FOR FABRICATION, TESTING, AND REWORK OF PROTOTYPE EQUIPMENT.
- * R&D (SCALE-UP OR DEMONSTRATION PLANTS OF HIGH-RISK TECHNOLOGY) REQUIRED PRIOR TO START OF CONSTRUCTION.
- * ONE-TIME COSTS RELATED TO START-UP \, OPERATOR TRAINING, AND COMMISSIONING.
- * INITIAL INVENTORIES AND SPARE PARTS.
- * PROJECT SUPPORT BY THE OPERATING CONTRACTOR (OC) FROM OC'S NON-DEDICATED PERSONNEL.
- * ECONOMIC ESCALATION.

WMC-SD-W113-ACDR-001
Rev. 0
Page 584

PAGE 1 OF 1
DATE 01/27/94 09:24:45
BY KLR/LGH/DEA/DLM

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R04 - COST CODE ACCOUNT SUMMARY

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359
FILE NO. W113BAA1

COST CODE/UBS	DESCRIPTION	ESTIMATE SUBTOTAL	ONSITE INDIRECTS	SUB TOTAL	ESCALATION %	SUB TOTAL	CONTINGENCY %	TOTAL DOLLARS
000	ENGINEERING	195072	0	195072	12.22	23838	15	251744
111100	GENERAL	252620	0	252620	12.22	30869	15	326013
111101	SITE PLAN	74706	0	74706	12.22	9129	15	96411
111102	GENERAL OFFICE BUILDING	80370	0	80370	12.22	9821	20	108229
111103	RETRIVAL STAFF CHANGE BUILDING	539968	0	539968	12.22	65986	20	727142
111104	TRENCH ENCLOSURE/OPER. BLDGS	320119	0	320119	12.22	39119	15	413124
111200	GENERAL	32026	0	32026	12.22	3914	15	43127
111201	SITE PLAN	1420	0	1420	12.25	174	20	1833
111202	GENERAL OFFICE BUILDING	7952	0	7952	12.22	972	20	10708
111203	RETRIVAL STAFF CHANGE BUILDING	28139	0	28139	12.22	3438	25	39472
111204	TRENCH ENCLOSURE/OPER. BLDGS.	377832	0	377832	12.22	46173	15	487603
111210	PROJECT SUPPORT	315027	0	315027	26.00	81907	20	476319
120001	ENGINEERING DURING CONST.	447575	0	447575	26.00	116371	20	676732
120002	ENG/INSP. SUPPORT	2672826	0	2672826	16.15	431711	18	3658457
460	IMPROVEMENTS TO LAND	53912	8626	62538	19.66	12295	20	89799
320005	SITE GRADING & LEVELING	95505	15281	110786	19.66	21780	20	159080
320006	ROADS & PARKING	25909	4145	30054	19.66	5909	20	43156
320007	FENCING	98893	15823	114716	19.66	22553	20	164723
320008	STABILIZATION	274219	43875	318094	19.66	62537	20	456758
501	BUILDINGS	1622946	259670	1882616	19.66	370122	25	2815924
320002	TRENCH ENCLOSURE BLDG./TRUCK LOCK	266982	42718	309700	19.66	60886	25	463232
320003	TRENCH OPERATION BUILDING	653095	104496	757591	19.66	148942	25	1133166
320004	STAFF CHANGE & GENERAL OFFICE BLDG	2543023	406884	2949907	19.66	579950	25	4412322
600	UTILITIES							

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359
FILE NO. W113BAA1

**** IEST - INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R04 - COST CODE ACCOUNT SUMMARY

PAGE 8 OF 12
DATE 01/27/94 09:24:45
BY KLR/LGH/DEA/DLM

COST CODE/WBS	DESCRIPTION	ESTIMATE SUBTOTAL	ONSITE INDIRECTS	SUB TOTAL	ESCALATION %	TOTAL	SUB TOTAL	CONTINGENCY %	TOTAL	TOTAL DOLLARS
320004	STAFF CHANGE & GENERAL OFFICE BLDG	27720	4435	32155	19.66	6322	38477	25	9619	48096
320009	WATERLINES	216495	34639	251134	19.66	49373	300507	25	75127	375634
320010	SITE ELECTRICAL & INSTRUMENTATION	180338	28854	209192	19.66	41127	250319	25	62580	312899
330000	PLANT FORCES CONSTRUCTION	3675	0	3675	25.61	941	4616	25	1154	5770
TOTAL 600	UTILITIES	428228	67928	496156	19.70	97763	593919	25	148480	742399
700	SPECIAL EQUIP/PROCESS SYSTEMS									
200000	PROCUREMENT (E/C CONTRACTOR)	5863511	0	5863511	19.08	1118758	6982269	25	1745567	8727836
320002	TRENCH ENCLOSURE BLDG./TRUCK LOCK	309855	49577	359432	19.66	70664	430096	25	107524	537620
400000	PROJECT INTEGRATION/MGMT. (O/C)	1346000	0	1346000	0.00	0	1346000	16	215360	1561360
TOTAL 700	SPECIAL EQUIP/PROCESS SYSTEM	7519366	49577	7568943	15.71	1189422	8758365	24	2068451	10826816
900	OTHER PROJECT COST									
500000	OTHER PROJECT COST	19070000	0	19070000	0.00	0	19070000	0	0	19070000
TOTAL 900	OTHER PROJECT COST	19070000	0	19070000	0.00	0	19070000	0	0	19070000
PROJECT TOTAL		32,507,662	568,264	33,075,926	7.14	2,361,383	35,437,312	11	3,729,457	39,166,752

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359
FILE NO. W113BAA1

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R05 - ESTIMATE SUMMARY BY CSI DIVISION

Rev. 0
Page 587

PAGE 9 OF 12
DATE 01/27/94 09:24:51
BY KLR/IGH/DEA/DLM

CSI DESCRIPTION		ESTIMATE SUBTOTAL	ONSITE INDIRECTS	SUB TOTAL	ESCALATION % TOTAL	SUB TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS
*****		*****	*****	*****	*****	*****	*****	*****
ENGINEERING								
		174823	0	174823	13.59	23761	198584	231223
21	CIVIL	36352	0	36352	15.88	5774	42126	49052
22	ENVIRON ENGRG	97480	0	97480	17.14	16707	114187	136490
23	ARCHITECTUAL	111044	0	111044	13.74	15253	126297	148733
24	STRUCTURAL	407050	0	407050	14.69	59809	466859	559650
25	NUCLEAR EQUIP	171409	0	171409	15.94	27316	198725	236864
26	FIRE PROT/SAFTY	106108	0	106108	13.35	14170	120278	139400
28	HVAC	243376	0	243376	14.98	36452	279828	327894
29	INSTRUMENTATION	354465	0	354465	15.26	54106	408571	479644
31	ELECTRICAL	87685	0	87685	14.06	12330	100015	116511
32	SPECIF	99258	0	99258	15.35	15240	114498	133096
35	DESIGN ADMIN	25800	0	25800	12.22	3153	28953	33296
36	DESIGN SAFETY ANALYSIS	126560	0	126560	12.22	15466	142026	163329
40	PROJECT MANAGER	9296	0	9296	12.72	1182	10478	12071
41	WORD PROCESSING	20410	0	20410	18.19	3712	24122	28297
42	QUALITY ENGINEERING	126160	0	126160	24.58	31011	157171	187875
44	ACCEPTNCE INSPECTION	118014	0	118014	13.04	15391	133405	153859
45	PROJECT PLANNING	113778	0	113778	17.74	20189	133967	156935
46	ESTIMATES	73552	0	73552	25.51	18766	92318	110634
49	SUB/PROC	5280	0	5280	12.22	645	5925	6814
61	CM ADMINISTRATION	1600	0	1600	12.25	196	1796	2065
62	SURVEY	7140	0	7140	19.52	1394	8534	10051
65	RECORDS MGMT/TURNOVER	150686	0	150686	25.89	39016	189702	227576
66	AS-BUILDING	3500	0	3500	12.23	428	3928	4517
70	WORK ORDER	2000	0	2000	12.20	244	2244	2581
74	TRAVEL		0					
TOTAL ENGINEERING		2,672,826	0	2,672,826	16.15	431,711	3,104,537	3,658,457
CONSTRUCTION								
00	TECHNICAL SERVICES	19070000	0	19070000	0.00	0	19070000	19070000
02	SITWORK	1263470	202155	1465625	19.66	288142	1753767	2173178
03	CONCRETE	67249	10760	78009	19.66	15336	93346	116682
05	METALS	50925	8148	59073	19.66	11614	70687	88358
07	MOISTURE AND THERMAL	595	95	690	19.57	135	826	1032
08	DOORS, WINDOWS AND G	47885	7662	55547	19.66	10921	66467	83083
09	FINISHES	12441	1990	14431	19.66	2837	17269	21586

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359
FILE NO. W113BAA1

*** IEST - INTERACTIVE ESTIMATING ***
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R05 - ESTIMATE SUMMARY BY CSI DIVISION

PAGE 10 OF 12
DATE 01/27/94 09:24:51
BY KLR/LGH/DEA/DLM

CSI	DESCRIPTION	ESTIMATE SUBTOTAL	ONSITE INDIRECTS	SUB TOTAL	ESCALATION %	TOTAL	SUB TOTAL	CONTINGENCY %	TOTAL	TOTAL DOLLARS
11	EQUIPMENT	6173366	49577	6222943	19.11	1189422	7412365	25	1853091	9265456
13	SPECIAL CONSTRUCTION	715230	114437	829667	19.66	163112	992779	25	248195	1240974
15	MECHANICAL	119043	19047	138090	19.66	27148	165238	25	41310	296548
16	ELECTRICAL	968632	154393	1123025	19.68	221005	1344031	25	336008	1680038
19	PROJECT MANAGEMENT	1346000	0	1346000	0.00	0	1346000	16	215360	1561360
TOTAL CONSTRUCTION		29,834,836	568,264	30,403,100	6.35	1,929,672	32,332,775	10	3,175,523	35,508,295
PROJECT TOTAL		32,507,662	568,264	33,075,926	7.14	2,361,383	35,437,312	11	3,729,457	39,166,752

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER2359
FILE NO. W113BAA1

**** KAISER ENGINEERS INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R06 - CONTINGENCY ANALYSIS BASIS SHEET

PAGE 11 OF 12
DATE 01/27/94 05:25:47
BY KLR/DEA

REFERENCE: ESTIMATE BASIS SHEET
COST CODE ACCOUNT SUMMARY

PAGE 4, 5 & 6 OF 12
PAGE 7 & 8 OF 12

THE U.S. DEPARTMENT OF ENERGY - RICHLAND ORDER 5700.3 "COST ESTIMATING, ANALYSIS AND STANDARDIZATION" DATED 3-27-85, PROVIDES GUIDELINES FOR ESTIMATE CONTINGENCIES. THE GUIDELINE FOR A CONCEPTUAL ESTIMATE SHOULD HAVE AN OVERALL RANGE OF 15 TO 25%.

CONTINGENCY IS EVALUATED AT THE THIRD COST CODE LEVEL AND SUMMARIZED AT THE PRIMARY AND SECONDARY COST CODE LEVEL OF THE DETAILED COST ESTIMATE.

ENGINEERING
WBS 1.1 AND 1.2
COST CODE 000

AN OVERALL CONTINGENCY OF 18% WAS APPLIED TO ENGINEERING BY EACH DISCIPLINE TO COVER UNKNOWNNS AND UNFORESEEN POSSIBLE SCOPE OR REGULATION CHANGES.

AVERAGE ENGINEERING CONTINGENCY 18%

CONSTRUCTION
WBS 2.0 COST CODE 700

A CONTINGENCY OF 25% WAS APPLIED DUE TO: THE POSSIBILITY OF MODIFICATION OR ADDITIONAL SUPPORT SYSTEMS REQUIRED TO MAKE THIS SPECIALIZED EQUIPMENT FULLY FUNCTIONAL.

WBS 3.2 COST CODE 460

A CONTINGENCY OF 20% WAS USED DUE TO: UNKNOWN FINISH ELEVATIONS OF BUILDINGS & ROADWAYS. ALLOWANCES WERE MADE TO BRING SITE TO PROPER ELEVATION AND THE AMOUNT OF AREA DISTURBED DURING CONSTRUCTION THAT WOULD REQUIRE GRAVEL STABILIZATION.

COST CODE 501

A CONTINGENCY OF 25% WAS USED ON ALL BUILDINGS BECAUSE DETAILED INFORMATION WAS LIMITED FOR THIS CONCEPTUAL EFFORT WITH HIGH POSSIBILITY OF BLDG. MODIFICATIONS. AS MORE DETAILED INFORMATION BECOMES AVAILABLE THIS PERCENTAGE WILL BE LOWERED.

COST CODE 600

A CONTINGENCY OF 25% WAS USED DUE TO: THE POSSIBILITY OF ENCOUNTERING EXISTING UNKNOWN UNDERGROUND UTILITIES THAT COULD CAUSE REMOVAL OF EXISTING OR REROUTING OF NEW LINES.

COST CODE 700

A CONTINGENCY OF 24% WAS USED TO COVER THE POSSIBILITY OF ANY ITEMS OVERLOOKED OR NOT IDENTIFIED THAT WOULD BE CRUCIAL IN THE INSTALLATION AND OPERATION OF THIS SPECIALIZED EQUIPMENT.

WBS 4.0 COST CODE 700

A CONTINGENCY OF 16% WAS ADDED TO THE PROJECT INTEGRATION COSTS BASED ON THE EARLY STAGE OF THE PROJECT AND TO COVER POSSIBLE CHANGES TO THE SCHEDULE DUE TO CHANGING ENVIRONMENTAL REGULATIONS.

AVERAGE CONSTRUCTION CONTINGENCY 25%

AVERAGE PROJECT CONTINGENCY 11%

WMC-SD-W113-ACDR-001
Rev. 0
Page 589

PAGE 12 OF 12
DATE 01/27/94 09:24:56
BY KLR/LGH/DEA/DLM

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R07 - ONSITE INDIRECT COSTS BY WBS

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359
FILE NO. W113BAA1

WBS	DESCRIPTION	ESTIMATE SUBTOTAL	CONTRACT %	ADMINISTRATION TOTAL	BID PACK PREP.	OTHER INDIRECTS	TOTAL INDIRECTS
111100	GENERAL	195072	0.00	0	0	0	0
111101	SITE PLAN	252620	0.00	0	0	0	0
111102	GENERAL OFFICE BUILDING	74706	0.00	0	0	0	0
111103	RETRIVAL STAFF CHANGE BUILDING	80370	0.00	0	0	0	0
111104	TRENCH ENCLOSURE/OPER. BLDGS	539968	0.00	0	0	0	0
111200	GENERAL	320119	0.00	0	0	0	0
111201	SITE PLAN	32026	0.00	0	0	0	0
111202	GENERAL OFFICE BUILDING	1420	0.00	0	0	0	0
111203	RETRIVAL STAFF CHANGE BUILDING	7952	0.00	0	0	0	0
111204	TRENCH ENCLOSURE/OPER. BLDGS.	28139	0.00	0	0	0	0
111210	PROJECT SUPPORT	377832	0.00	0	0	0	0
120001	ENGINEERING DURING CONST.	315027	0.00	0	0	0	0
120002	ENG/INSP. SUPPORT	447575	0.00	0	0	0	0
200000	PROCUREMENT (E/C CONTRACTOR)	5863511	0.00	0	0	0	0
320002	TRENCH ENCLOSURE BLDG./TRUCK LOCK	1932801	16.00	309247	0	0	309247
320003	TRENCH OPERATION BUILDING	266982	16.00	42718	0	0	42718
320004	STAFF CHANGE & GENERAL OFFICE BLDG	680815	16.00	108931	0	0	108931
320005	SITE GRADING & LEVELING	53912	16.00	8626	0	0	8626
320006	ROADS & PARKING	95505	16.00	15281	0	0	15281
320007	FENCING	25909	16.00	4145	0	0	4145
320008	STABILIZATION	98893	16.00	15823	0	0	15823
320009	WATERLINES	216495	16.00	34639	0	0	34639
320010	SITE ELECTRICAL & INSTRUMENTATION	187338	16.00	28854	0	0	28854
330000	PLANT FORCES CONSTRUCTION	3675	0.00	0	0	0	0
400000	PROJECT INTEGRATION/MGMT. (O/C)	1346000	0.00	0	0	0	0
500000	OTHER PROJECT COST	19070000	0.00	0	0	0	0

PROJECT TOTAL 32,507,662 568,264 0 568,264

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

DATE 01/27/94 09:25:02
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	HANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
=====	=====	=====	=====	=====	=====	=====	=====	=====	=====	=====	=====
111100	GENERAL										
111100.2261004	REGULATORY REVIEW	000	1 LS	24	1704	0	0	0	0	0	1704
111100.2261006	MEETINGS	000	1 LS	40	2840	0	0	0	0	0	2840
111100.2261010	DESIGN & SPEC INPUT	000	1 LS	30	2130	0	0	0	0	0	2130
111100.2261012	LEAD ENGINEER COORD	000	1 LS	80	5680	0	0	0	0	0	5680
111100.2421010	CONSTRUCTION SPECIFICATION	000	1 LS	120	8520	0	0	0	0	0	8520
111100.2441012	TRADE-OFF STUDIES	000	1 LS	43	3053	0	0	0	0	0	3053
111100.2442012	TRADE-OFF STUDIES	000	1 LS	117	6903	0	0	0	0	0	6903
111100.2561002	DESIGN SUPPORT	000	1 LS	300	21300	0	0	0	0	0	21300
111100.2561004	VENDOR INTERFACE	000	1 LS	80	5680	0	0	0	0	0	5680
111100.2562004	VENDOR INTERFACE	000	1 LS	20	1180	0	0	0	0	0	1180
111100.2661002	MEETINGS	000	1 LS	44	3124	0	0	0	0	0	3124
111100.2661010	PROJECT DOC/CODE REVIEW	000	1 LS	44	3124	0	0	0	0	0	3124
111100.2665006	LEAD ENGINEER COORD	000	1 LS	88	6248	0	0	0	0	0	6248
111100.2811018	DRAWING CHECK	000	1 LS	30	2130	0	0	0	0	0	2130
111100.2811022	INCRP CLIENT COMMENTS DRAWINGS	000	1 LS	20	1420	0	0	0	0	0	1420
111100.2821014	CONSTRUCTION SPECIFICATION HVAC	000	1 LS	60	4260	0	0	0	0	0	4260
111100.2821016	CONSTRUCTION SPECIFICATION PLUMBING	000	1 LS	30	2130	0	0	0	0	0	2130
111100.2821020	SPECIFICATION CHECK	000	1 LS	10	710	0	0	0	0	0	710
111100.2821024	INCRP CLIENT COMMENTS SPECIFICATIONS	000	1 LS	10	710	0	0	0	0	0	710
111100.2911002	DRAWING CHECK	000	1 LS	280	19880	0	0	0	0	0	19880
111100.2921002	CONSTRUCTION SPECIFICATION	000	1 LS	40	2840	0	0	0	0	0	2840
111100.2921004	PROCUREMENT SPECIFICATION	000	1 LS	120	8520	0	0	0	0	0	8520
111100.2921006	CEM SPECIFICATION	000	1 LS	40	2840	0	0	0	0	0	2840
111100.3111002	LIGHTING FIXTURE SCHEDULE	000	1 LS	20	1420	0	0	0	0	0	1420
111100.3111004	PANEL SCHEDULE	000	1 LS	20	1420	0	0	0	0	0	1420
111100.3111006	WIRE RUN LIST	000	1 LS	30	2130	0	0	0	0	0	2130
111100.3111012	ELECT ONE-LINE	000	1 LS	20	1420	0	0	0	0	0	1420
111100.3112002	LIGHTING FIXTURE SCHEDULE	000	1 LS	60	3540	0	0	0	0	0	3540
111100.3112004	PANEL SCHEDULE	000	1 LS	70	4130	0	0	0	0	0	4130
111100.3112006	WIRE RUN LIST	000	1 LS	70	4130	0	0	0	0	0	4130
111100.3112012	ELECT ONE-LINE	000	1 LS	60	3540	0	0	0	0	0	3540
111100.3121010	CONSTRUCTION SPECIFICATION	000	1 LS	10	710	0	0	0	0	0	710
111100.3122010	CONSTRUCTION SPECIFICATION	000	1 LS	20	1180	0	0	0	0	0	1180
111100.3151014	CALCULATIONS	000	1 LS	125	8875	0	0	0	0	0	8875
111100.3152014	CALCULATIONS	000	1 LS	75	4425	0	0	0	0	0	4425
111100.3161016	CHECKING	000	1 LS	100	7100	0	0	0	0	0	7100

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

**** TEST - INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 2
DATE 01/27/94 09:25:02
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111100.3211002	MEETINGS	000	1 LS	10	710	0	0	0	0	0	710
111100.3211014	PROCUREMENT SPECS	000	1 LS	376	26696	0	0	0	0	0	26696
111100.4111002	WORD PROCESSING	000	1 LS	240	6720	0	0	0	0	0	6720
				2,976	195,072	0	0	0	0	0	195,072
TOTAL WBS 111100 GENERAL											

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 5
DATE 01/27/94 09:25:02
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111101	SITE PLAN										
111101.2111002	OVERALL SITE PLAN & DWG LIST (2 SHEETS)	000	1 LS	72	5112	0	0	0	0	0	5112
111101.2111004	SITE PLAN, SNS/SW & BURIED UTILITIES (1 SHEET)	000	1 LS	72	5112	0	0	0	0	0	5112
111101.2111006	TRENCH SITE PLAN & SHEET PILE (2 SHEETS)	000	1 LS	144	10224	0	0	0	0	0	10224
111101.2111008	DETAILS (3 SHEETS)	000	1 LS	216	15336	0	0	0	0	0	15336
111101.2111010	ROAD SECT/PROFILE (2 SHEETS)	000	1 LS	144	10224	0	0	0	0	0	10224
111101.2112002	OVERALL SITE PLAN & DWG LIST (2 SHEETS)	000	1 LS	84	4956	0	0	0	0	0	4956
111101.2112004	SITE PLAN, SNS/SW & BURIED UTILITIES (1 SHEET)	000	1 LS	84	4956	0	0	0	0	0	4956
111101.2112006	TRENCH SITE PLAN & SHEET PILE (2 SHEETS)	000	1 LS	168	9912	0	0	0	0	0	9912
111101.2112008	DETAILS (3 SHEETS)	000	1 LS	252	14868	0	0	0	0	0	14868
111101.2112010	ROAD SECT/PROFILE (2 SHEETS)	000	1 LS	168	9912	0	0	0	0	0	9912
111101.2121012	CONSTRUCTION SPECIFICATION	000	1 LS	180	12780	0	0	0	0	0	12780
111101.2151016	CALC/CHECK - SHEET PILING	000	1 LS	100	7100	0	0	0	0	0	7100
111101.2151018	CALC/CHECK - ROAD	000	1 LS	80	5680	0	0	0	0	0	5680
111101.2151020	CALC/CHECK - SITE GRADING	000	1 LS	80	5680	0	0	0	0	0	5680
111101.2151022	CALC/CHECK - SNS/SW	000	1 LS	60	4260	0	0	0	0	0	4260
111101.2621004	UG FIRE MAIN SPEC	000	1 LS	28	1988	0	0	0	0	0	1988
111101.2661002	ENG COORDINATION W/CIVIL	000	1 LS	60	4260	0	0	0	0	0	4260
111101.2661006	CHECKING	000	1 LS	16	1136	0	0	0	0	0	1136
111101.2661012	FINAL COMMENT/INCRP	000	1 LS	16	1136	0	0	0	0	0	1136
111101.2811004	SITE PLAN - K3 DWG	000	1 LS	80	5680	0	0	0	0	0	5680
111101.2812004	SITE PLAN - K3 DWG	000	1 LS	40	2360	0	0	0	0	0	2360
111101.2911002	TELE COMMUNICATIONS ROUTING	000	1 LS	10	710	0	0	0	0	0	710
111101.2911004	DATA FLOW	000	1 LS	10	710	0	0	0	0	0	710
111101.2911006	PAGING SYSTEM WIREING	000	1 LS	60	4260	0	0	0	0	0	4260
111101.2912002	TELE COMMUNICATIONS ROUTING	000	1 LS	10	590	0	0	0	0	0	590
111101.2912004	DATA FLOW	000	1 LS	10	590	0	0	0	0	0	590
111101.2912006	PAGING SYSTEM WIREING	000	1 LS	100	5900	0	0	0	0	0	5900
111101.3111002	SITE PLAN	000	1 LS	60	4260	0	0	0	0	0	4260
111101.3111004	POLE LINE DETAILS	000	1 LS	100	7100	0	0	0	0	0	7100
111101.3111006	PLAN AND PROFILE	000	1 LS	40	2840	0	0	0	0	0	2840
111101.3111008	UNDER GROUND RACEWAY PLAN	000	1 LS	20	1420	0	0	0	0	0	1420
111101.3111010	RACEWAY SECTIONS AND DETAILS	000	1 LS	40	2840	0	0	0	0	0	2840
111101.3111012	GROUNDING DETAILS	000	1 LS	20	1420	0	0	0	0	0	1420
111101.3112002	SITE PLAN	000	1 LS	140	8260	0	0	0	0	0	8260

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 4
DATE 01/27/94 09:25:02
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111101.3112004	POLE LINE DETAILS	000	1 LS	500	29500	0	0	0	0	0	29500
111101.3112006	PLAN AND PROFILE	000	1 LS	120	7080	0	0	0	0	0	7080
111101.3112008	UNDER GROUND RACEWAY PLAN	000	1 LS	80	4720	0	0	0	0	0	4720
111101.3112010	RACEWAY SECTIONS AND DETAILS	000	1 LS	160	9440	0	0	0	0	0	9440
111101.3112012	GROUNDING DETAILS	000	1 LS	60	3540	0	0	0	0	0	3540
111101.3151014	SAG CALCULATIONS	000	1 LS	40	2840	0	0	0	0	0	2840
111101.3161016	CHECKING	000	1 LS	128	9088	0	0	0	0	0	9088
111101.3211010	CONST SPEC - CF SITE WORK	000	1 LS	40	2840	0	0	0	0	0	2840
TOTAL WBS 111101 SITE PLAN				3,892	252,620	0	0	0	0	0	252,620

WHC-SD-W113-ACDR-001
Rev. 0
Page 584

*** TEST - INTERACTIVE ESTIMATING ***
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

DATE 01/27/94 09:25:02
BY KLR/LGH/DEA/DLM

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	ON&P / B & I	TOTAL DOLLARS
111102	GENERAL OFFICE BUILDING										
111102.2311002	FLOOR PLAN	000	1 LS	6	426		0	0	0	0	426
111102.2311004	ELEVATIONS	000	1 LS	6	426		0	0	0	0	426
111102.2311006	CROSS SECTION	000	1 LS	12	852		0	0	0	0	852
111102.2311008	REFLECTED CEILING PLAN	000	1 LS	12	852		0	0	0	0	852
111102.2311010	INTERIOR ELEVATIONS	000	1 LS	6	426		0	0	0	0	426
111102.2311012	SCHEDULES	000	1 LS	12	708		0	0	0	0	708
111102.2312002	FLOOR PLAN	000	1 LS	12	708		0	0	0	0	708
111102.2312004	ELEVATIONS	000	1 LS	16	944		0	0	0	0	944
111102.2312006	CROSS SECTION	000	1 LS	16	944		0	0	0	0	944
111102.2312008	REFLECTED CEILING PLAN	000	1 LS	16	944		0	0	0	0	944
111102.2312010	INTERIOR ELEVATIONS	000	1 LS	12	708		0	0	0	0	708
111102.2312012	SCHEDULES	000	1 LS	30	2130		0	0	0	0	2130
111102.2321014	PROCUREMENT SPECIFICATION	000	1 LS	8	568		0	0	0	0	568
111102.2361018	CHECKING	000	1 LS	30	2130		0	0	0	0	2130
111102.2411002	FOUNDATION DETAILS	000	1 LS	70	4130		0	0	0	0	4130
111102.2412002	(1 SHEET)	000	1 LS	60	4260		0	0	0	0	4260
111102.2451014	CALC/CHECK - STRUCTURE	000	1 LS	140	9940		0	0	0	0	9940
111102.2811006	GENERAL OFFICE BLDG - K4 DWG	000	1 LS	20	1420		0	0	0	0	1420
111102.2911002	TELECOM & COMPUTER WIRING	000	1 LS	20	1420		0	0	0	0	1420
111102.2911004	EQUIPMENT LOCATION	000	1 LS	20	1180		0	0	0	0	1180
111102.2912002	TELECOM & COMPUTER WIRING	000	1 LS	20	1180		0	0	0	0	1180
111102.2912004	EQUIPMENT LOCATION	000	1 LS	20	1420		0	0	0	0	1420
111102.3111002	LIGHTING PLAN	000	1 LS	30	2130		0	0	0	0	2130
111102.3111004	EQUIP/RCVY/COMM PLAN	000	1 LS	20	1420		0	0	0	0	1420
111102.3111006	RACEWAY DETAILS	000	1 LS	20	1420		0	0	0	0	1420
111102.3111008	ELEMENTARY DIAGRAM	000	1 LS	60	3540		0	0	0	0	3540
111102.3112002	LIGHTING PLAN	000	1 LS	70	4130		0	0	0	0	4130
111102.3112004	EQUIP/RCVY/COMM PLAN	000	1 LS	80	4720		0	0	0	0	4720
111102.3112006	RACEWAY DETAILS	000	1 LS	80	4720		0	0	0	0	4720
111102.3112008	ELEMENTARY DIAGRAM	000	1 LS	32	2272		0	0	0	0	2272
111102.3161010	CHECKING	000	1 LS	166	11786		0	0	0	0	11786
111102.3211004	CONST SPEC - FP PRE ENGR	000	1 LS				0	0	0	0	
111102.3211006	GEN OFFICE BLDG	000	1 LS				0	0	0	0	

TOTAL WBS 111102 GENERAL OFFICE BUILDING 1,134 74,706 0 0 0 74,706

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 6
DATE 01/27/94 09:25:02
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111103	RETRIVAL STAFF CHANGE BUILDING										
111103.2311002	FLOOR PLAN & REFLECTED CEILING PLAN	000	1 LS	40	2840	0	0	0	0	0	2840
111103.2312002	FLOOR PLAN & REFLECTED CEILING PLAN	000	1 LS	100	5900	0	0	0	0	0	5900
111103.2321014	INPUT TO SPECIFICATIONS	000	1 LS	40	2840	0	0	0	0	0	2840
111103.2361018	CHECKING	000	1 LS	20	1420	0	0	0	0	0	1420
111103.2451014	CALC/CHECK - STRUCTURE	000	1 LS	120	8520	0	0	0	0	0	8520
111103.2811008	RETRIEVAL STAFF CHANGE BLDG K5 DWG	000	1 LS	100	7100	0	0	0	0	0	7100
111103.2812008	RETRIEVAL STAFF CHANGE BLDG K5 DWG	000	1 LS	40	2360	0	0	0	0	0	2360
111103.2911002	TELECOM & COMPUTER WIRING	000	1 LS	40	2840	0	0	0	0	0	2840
111103.2911004	CONTROL ROOM LAYOUT	000	1 LS	20	1420	0	0	0	0	0	1420
111103.2911006	ALARM/DATA LISTING	000	1 LS	10	710	0	0	0	0	0	710
111103.2911008	EQUIPMENT LOCATION	000	1 LS	20	1420	0	0	0	0	0	1420
111103.2911010	INSTALLATION DETAILS	000	1 LS	40	2840	0	0	0	0	0	2840
111103.2912002	TELECOM & COMPUTER WIRING	000	1 LS	40	2360	0	0	0	0	0	2360
111103.2912004	CONTROL ROOM LAYOUT	000	1 LS	20	1180	0	0	0	0	0	1180
111103.2912006	ALARM/DATA LISTING	000	1 LS	10	590	0	0	0	0	0	590
111103.2912008	EQUIPMENT LOCATION	000	1 LS	20	1180	0	0	0	0	0	1180
111103.3111002	INSTALLATION DETAILS	000	1 LS	60	3540	0	0	0	0	0	3540
111103.3111004	EQUIP/RCWY/COMM PLAN	000	1 LS	20	1420	0	0	0	0	0	1420
111103.3111006	RACEWAY DETAILS	000	1 LS	30	2130	0	0	0	0	0	2130
111103.3111008	ELEMENTARY DIAGRAM	000	1 LS	20	1420	0	0	0	0	0	1420
111103.3112002	LIGHTING PLAN	000	1 LS	60	3540	0	0	0	0	0	3540
111103.3112004	EQUIP/RCWY/COMM PLAN	000	1 LS	70	4130	0	0	0	0	0	4130
111103.3112006	RACEWAY DETAILS	000	1 LS	80	4720	0	0	0	0	0	4720
111103.3112008	ELEMENTARY DIAGRAM	000	1 LS	32	2272	0	0	0	0	0	2272
111103.3211008	CONST SPEC - FP STAFF CHANGE	000	1 LS	78	5538	0	0	0	0	0	5538

TOTAL WBS 111103 RETRIEVAL STAFF CHANGE BUILDING 1,230 80,370 0 0 0 80,370

** IEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY UBS / COST CODE

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-1113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111104	TRENCH ENCLOSURE/OPER. BLDGS										
111104.2311002	FLOOR PLAN	000	1 LS	20	1420	0	0	0	0	0	1420
111104.2311004	ELEVATIONS	000	1 LS	20	1420	0	0	0	0	0	1420
111104.2311006	CROSS SECTIONS	000	1 LS	20	1420	0	0	0	0	0	1420
111104.2311008	SCHEDULE & DETAILS	000	1 LS	40	2840	0	0	0	0	0	2840
111104.2312002	FLOOR PLAN	000	1 LS	80	4720	0	0	0	0	0	4720
111104.2312004	ELEVATIONS	000	1 LS	60	3540	0	0	0	0	0	3540
111104.2312006	CROSS SECTIONS	000	1 LS	60	3540	0	0	0	0	0	3540
111104.2312008	SCHEDULE & DETAILS	000	1 LS	60	3540	0	0	0	0	0	3540
111104.2321010	PROCUREMENT SPECIFICATION	000	1 LS	20	1420	0	0	0	0	0	1420
111104.2321012	CONSTRUCTION SPECIFICATION	000	1 LS	10	710	0	0	0	0	0	710
111104.2361016	CHECKING	000	1 LS	12	852	0	0	0	0	0	852
111104.2411002	FOUNDATION AND BLDG DETAILS	000	1 LS	144	10224	0	0	0	0	0	10224
111104.2412002	(2 SHEETS) FOUNDATION AND BLDG DETAILS	000	1 LS	168	9912	0	0	0	0	0	9912
111104.2451014	CALC/CHECK - STRUCTURE	000	1 LS	120	8520	0	0	0	0	0	8520
111104.2451016	STRUCTURE DYNAMIC ANALYSIS	000	1 LS	160	11360	0	0	0	0	0	11360
111104.2511006	DRAWINGS	000	1 LS	165	11715	0	0	0	0	0	11715
111104.2512006	DRAWINGS	000	1 LS	3180	187620	0	0	0	0	0	187620
111104.2512018	DRAWING	000	1 LS	308	18172	0	0	0	0	0	18172
111104.2521010	SPECIFICATIONS	000	1 LS	580	41180	0	0	0	0	0	41180
111104.2521022	SPECIFICATION CHECK	000	1 LS	58	4118	0	0	0	0	0	4118
111104.2551008	CALCULATIONS	000	1 LS	318	22578	0	0	0	0	0	22578
111104.2551020	CLACULATION CHECK	000	1 LS	37	2627	0	0	0	0	0	2627
111104.2611002	SPRINKLER DRAWINGS	000	1 LS	80	5680	0	0	0	0	0	5680
111104.2612002	FIRE ALARM DRAWINGS	000	1 LS	100	7100	0	0	0	0	0	7100
111104.2612006	FIRE ALARM DRAWINGS	000	1 LS	440	25960	0	0	0	0	0	25960
111104.2621010	SPRINKLER SYS SPECIFICATION	000	1 LS	480	28320	0	0	0	0	0	28320
111104.2621012	FIRE ALARM SPECIFICATION	000	1 LS	36	2556	0	0	0	0	0	2556
111104.2621022	SPRINKLER SYS SPECIFICATION	000	1 LS	48	3408	0	0	0	0	0	3408
111104.2651002	SPRINKLER SYS HYDRAULIC	000	1 LS	40	2840	0	0	0	0	0	2840
111104.2661016	CALCS	000	1 LS	30	2130	0	0	0	0	0	2130
111104.2661022	CHECKING	000	1 LS	15	1065	0	0	0	0	0	1065
111104.2662016	CLIENT COMMENT INCORP	000	1 LS	30	1770	0	0	0	0	0	1770
111104.2662022	CHECKING	000	1 LS	21	1239	0	0	0	0	0	1239
111104.2911002	CLIENT COMMENT INCORP	000	1 LS	40	2840	0	0	0	0	0	2840
111104.2911004	RADIATION MONITOR WIRING & INSTALLATION	000	1 LS	20	1420	0	0	0	0	0	1420
111104.2911006	EQUIPMENT LOCATION	000	1 LS	20	1420	0	0	0	0	0	1420
111104.2911008	TELECOM & COMPUTER WIRING	000	1 LS	20	1420	0	0	0	0	0	1420

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE ROB - ESTIMATE DETAIL BY WBS / COST CODE

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111104.2911008	BAR CODE READER/TRANSMITTER WIRING	000	1 LS	10	710	0	0	0	0	0	710
111104.2911010	GAS CHROMATOGRAPH INSTALL & WIRING	000	1 LS	20	1420	0	0	0	0	0	1420
111104.2911012	HVAC MONITORING/WIRING	000	1 LS	80	5680	0	0	0	0	0	5680
111104.2911014	WIRE RUN/CONDUIT LIST	000	1 LS	40	2840	0	0	0	0	0	2840
111104.2912002	RADIATION MONITOR WIRING & INSTALLATION	000	1 LS	80	4720	0	0	0	0	0	4720
111104.2912004	EQUIPMENT LOCATION	000	1 LS	20	1180	0	0	0	0	0	1180
111104.2912006	TELECOM & COMPUTER WIRING	000	1 LS	20	1180	0	0	0	0	0	1180
111104.2912008	BAR CODE READER/TRANSMITTER WIRING	000	1 LS	10	590	0	0	0	0	0	590
111104.2912010	GAS CHROMATOGRAPH INSTALL & WIRING	000	1 LS	60	3540	0	0	0	0	0	3540
111104.2912012	HVAC MONITORING/WIRING	000	1 LS	80	4720	0	0	0	0	0	4720
111104.3111002	WIRE RUN/CONDUIT LIST	000	1 LS	60	3540	0	0	0	0	0	3540
111104.3111004	RECP/LTG/RCWY PLAN POS 1	000	1 LS	20	1420	0	0	0	0	0	1420
111104.3111006	RECP/LTG/RCWY PLAN POS 2	000	1 LS	20	1420	0	0	0	0	0	1420
111104.3111008	RACEWAY SECTIONS	000	1 LS	40	2840	0	0	0	0	0	2840
111104.3111010	COMMUNICATION PLAN	000	1 LS	20	1420	0	0	0	0	0	1420
111104.3111012	ELEMENTARY DIAGRAM	000	1 LS	40	2840	0	0	0	0	0	2840
111104.3111014	TRENCH & FACILITY PLAN	000	1 LS	20	1420	0	0	0	0	0	1420
111104.3112002	RECP/LTG/RCWY PLAN POS 1	000	1 LS	80	4720	0	0	0	0	0	4720
111104.3112004	RECP/LTG/RCWY PLAN POS 2	000	1 LS	80	4720	0	0	0	0	0	4720
111104.3112006	RACEWAY SECTIONS	000	1 LS	160	9440	0	0	0	0	0	9440
111104.3112008	COMMUNICATION PLAN	000	1 LS	80	4720	0	0	0	0	0	4720
111104.3112010	ELEMENTARY DIAGRAM	000	1 LS	260	15340	0	0	0	0	0	15340
111104.3112012	TRENCH & FACILITY PLAN	000	1 LS	80	4720	0	0	0	0	0	4720
111104.3112014	CHECKING	000	1 LS	80	5680	0	0	0	0	0	5680
111104.3211006	CONST SPEC - FP TRENCH ENCL BUILDINGS	000	1 LS	112	7952	0	0	0	0	0	7952

TOTAL WBS 111104 TRENCH ENCLOSURE/OPER. BLDGS				8,612	539,968	0	0	0	0	0	539,968

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111200	GENERAL										
111200.2211016	30 X REVIEW	000	1 LS	46	3266		0	0	0	0	3266
111200.2211018	90 X REVIEW	000	1 LS	56	3976		0	0	0	0	3976
111200.2211020	FINAL REVIEW & SIGN OFF	000	1 LS	28	1988		0	0	0	0	1988
111200.2261002	DESIGN CRITERIA REVIEW	000	1 LS	24	1704		0	0	0	0	1704
111200.2261008	FEILD TRIPS	000	1 LS	8	568		0	0	0	0	568
111200.2261008	FEILD TRIPS	000	1 LS	40	2840		0	0	0	0	2840
111200.2265014	ADMIN SUPPORT	000	1 LS	300	21300		0	0	0	0	21300
111200.2461018	DESIGN SUPPORT	000	1 LS	60	4260		0	0	0	0	4260
111200.2661008	ENG SAFETY CONSULTANT	000	1 LS	20	1420		0	0	0	0	1420
111200.2661012	FIELD TRIPS	000	1 LS	80	5680		0	0	0	0	5680
111200.2661020	SAFETY REVIEW	000	1 LS	44	3124		0	0	0	0	3124
111200.2665004	SUPERVISION	000	1 LS	300	21300		0	0	0	0	21300
111200.2861002	DESIGN SUPPORT	000	1 LS	525	37275		0	0	0	0	37275
111200.2861004	ENERGY CONSERVATION REPORT	000	1 LS	390	27690		0	0	0	0	27690
111200.2931002	ATPS	000	1 LS	600	42600		0	0	0	0	42600
111200.2961002	DESIGN SUPPORT	000	1 LS	180	12780		0	0	0	0	12780
111200.2961004	PROCUREMENT SUPPORT	000	1 LS	20	1420		0	0	0	0	1420
111200.2961006	CONSTRUCTION SUPPORT	000	1 LS	60	4260		0	0	0	0	4260
111200.2965008	ADMINISTRATION	000	1 LS	40	2840		0	0	0	0	2840
111200.3131008	ATPS	000	1 LS	40	2360		0	0	0	0	2360
111200.3132008	ATPS	000	1 LS	220	15620		0	0	0	0	15620
111200.3161020	DESIGN SUPPORT	000	1 LS	80	4720		0	0	0	0	4720
111200.3162020	DESIGN SUPPORT	000	1 LS	288	20448		0	0	0	0	20448
111200.3211016	ATPS	000	1 LS	860	61060		0	0	0	0	61060
111200.3511002	PRINCIPAL LEAD ENGINEER	000	1 LS	220	15620		0	0	0	0	15620
111200.3512004	COST ACCOUNT MANAGER	000	1 LS								
TOTAL WBS 111200 GENERAL					4,529	320,119	0	0	0	0	320,119

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_ROB - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 10
DATE 01/27/94 09:25:03
BY KLR/LGH/OEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111201	SITE PLAN										
111201.2141014	TRADE-OFF STUDIES	000	1 LS	48	3408	0	0	0	0	0	3408
111201.2142014	TRADE-OFF STUDIES	000	1 LS	112	6608	0	0	0	0	0	6608
111201.2160024	DESIGN SUPPORT	000	1 LS	300	21300	0	0	0	0	0	21300
111201.2661008	INTERDISCIPLINE REVIEW	000	1 LS	6	426	0	0	0	0	0	426
111201.2661010	INPUT TO ESTIMATING	000	1 LS	4	284	0	0	0	0	0	284
TOTAL WBS 111201 SITE PLAN				470	32,026	0	0	0	0	0	32,026

WHC-SD-W113-ACDR-001
Rev. 0
Page 590

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 11
DATE 01/27/94 09:25:03
BY KLR/LGH/OEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	ON&P / B & I	TOTAL DOLLARS
111202	GENERAL OFFICE BUILDING										
111202.2361016	DESIGN SUPPORT	000	1 LS	20	1420	0	0	0	0	0	1420

TOTAL WBS 111202 GENERAL OFFICE BUILDING				20	1,420	0	0	0	0	0	1,420

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 12
DATE 01/27/94 09:25:03
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111203	RETRIVAL STAFF CHANGE BUILDING									
111203.2361016	DESIGN SUPPORT	000	1 LS	112	7952	0	0	0	0	7952

TOTAL WBS 111203 RETRIVAL STAFF CHANGE BUILDING				112	7,952	0	0	0	0	7,952

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

**** TEST - INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 13
DATE 01/27/94 09:25:03
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111204	TRENCH ENCLOSURE/OPER. BLDGS.										
111204.2361014	DESIGN SUPPORT	000	1 LS	48	3408	0	0	0	0	0	3408
111204.2531012	ATPs	000	1 LS	46	3266	0	0	0	0	0	3266
111204.2531024	APT CHECK	000	1 LS	5	355	0	0	0	0	0	355
111204.2541014	ALARA STUDY	000	1 LS	100	7100	0	0	0	0	0	7100
111204.2541016	TRADE-OFF STUDIES	000	1 LS	100	7100	0	0	0	0	0	7100
111204.2631014	FIRE ALARM ATP	000	1 LS	60	4260	0	0	0	0	0	4260
111204.2661008	30 % DESIGN REVIEW	000	1 LS	16	1136	0	0	0	0	0	1136
111204.2661018	INTERDISCIPLINE REVIEW	000	1 LS	10	710	0	0	0	0	0	710
111204.2661020	INPUT TO ESTIMATING	000	1 LS	8	568	0	0	0	0	0	568
111204.2662008	30 % DESIGN REVIEW	000	1 LS	4	236	0	0	0	0	0	236
TOTAL WBS 111204 TRENCH ENCLOSURE/OPER. BLDGS.				397	28,139	0	0	0	0	0	28,139

WHC-SD-W113-ACDR-001
Rev. 0
Page 593

** IEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
111210	PROJECT SUPPORT										
111210.3611002	DESIGN SAFETY ANALYSIS	000	1 LS	430	25800	0	0	0	0	0	25800
111210.4011002	PROJECT MANAGER	000	1 LS	1720	120400	0	0	0	0	0	120400
111210.4019002	PH CLERICAL	000	1 LS	220	6160	0	0	0	0	0	6160
111210.411002	WORD PROCESSING	000	1 LS	80	2240	0	0	0	0	0	2240
111210.4211002	QUALITY ASSURANCE	000	1 LS	178	11570	0	0	0	0	0	11570
111210.4411002	ACCEPTANCE/INSPECTION	000	1 LS	200	13000	0	0	0	0	0	13000
111210.4511002	PROJECT CONTROLS	000	1 LS	2176	110976	0	0	0	0	0	110976
111210.4611002	ESTIMATING	000	1 LS	1082	68166	0	0	0	0	0	68166
111210.4911002	SUBCONTRACTS & PROCUREMENT	000	1 LS	40	2320	0	0	0	0	0	2320
111210.4941002	SUBMITTALS DOC CONTROL	000	1 LS	10	280	0	0	0	0	0	280
111210.6111002	CM ADMINISTRATION	000	1 LS	80	5280	0	0	0	0	0	5280
111210.6211002	SURVEY/SCANNING	000	1 LS	40	1600	0	0	0	0	0	1600
111210.6511002	RECORDS MANAGEMENT	000	1 LS	120	3360	0	0	0	0	0	3360
111210.6612002	AS-BUILDING	000	1 LS	20	1180	0	0	0	0	0	1180
111210.7000002	OTHER COSTS	000	1 LS	0	0	0	0	1000	0	0	1000
111210.7020002	REPRODUCTION	000	1 LS	0	0	0	0	2500	0	0	2500
111210.7400002	TRAVEL	000	1 LS	0	0	0	0	2000	0	0	2000

TOTAL WBS 111210 PROJECT SUPPORT				6,396	372,332	0	0	5,500	0	0	377,832

PAGE 15
DATE 01/27/94 09:25:03
BY KLR/IGH/DEA/DLM

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	ON&P / B & I	TOTAL DOLLARS
120001	ENGINEERING DURING CONST.										
120001.2100002	CIVIL ENGINEERING	000	245 HR	245	17395	0	0	0	0	0	17395
120001.2300002	ARCHITECTURAL	000	490 HR	490	34790	0	0	0	0	0	34790
120001.2400002	STRUCTURAL	000	172 HR	172	12212	0	0	0	0	0	12212
120001.2500002	MECHANICAL	000	1029 HR	1029	73059	0	0	0	0	0	73059
120001.2600002	FIRE PROTECTION	000	515 HR	515	36565	0	0	0	0	0	36565
120001.2800002	HVAC	000	123 HR	123	8733	0	0	0	0	0	8733
120001.2900002	INSTRUMENTATION	000	686 HR	686	48706	0	0	0	0	0	48706
120001.3100002	ELECTRICAL	000	1103 HR	1103	78313	0	0	0	0	0	78313
120001.3200002	SPECIFICATIONS	000	74 HR	74	5254	0	0	0	0	0	5254
-----											315,027
TOTAL WBS 120001 ENGINEERING DURING CONST.											315,027
-----											0
TOTAL WBS 120001 ENGINEERING DURING CONST.											315,027

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE ROB - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 16
DATE 01/27/94 09:25:03
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
120002	ENG/INSP. SUPPORT										9656
		000	136 HR	136	9656	0	0	0	0	0	9656
120002.2200002	ENVIRONMENTAL	000	136 HR	136	9656	0	0	0	0	0	6461
120002.2630002	SAFETY REVIEW	000	91 HR	91	6461	0	0	0	0	0	19312
120002.3200002	SPECIFICATIONS	000	272 HR	272	19312	0	0	0	0	0	3266
120002.3510002	PLE	000	46 HR	46	3266	0	0	0	0	0	336
120002.3520002	CAM	000	12 HR	12	336	0	0	0	0	0	8840
120002.4100002	WORD PROCESSING	000	136 HR	136	8840	0	0	0	0	0	113160
120002.4200002	QA	000	1886 HR	1886	113160	0	0	0	0	0	7038
120002.4400002	ACCEPTANCE INSPECTION	000	138 HR	138	7038	0	0	0	0	0	45612
120002.4500002	COST & SCHEDULE	000	724 HR	724	45612	0	0	0	0	0	70952
120002.4600002	ESTIMATING	000	2534 HR	2534	70952	0	0	0	0	0	3220
120002.4910002	SUBMITTALS	000	115 HR	115	3220	0	0	0	0	0	560
120002.6510002	DOCUMENT CONTROL	000	20 HR	20	560	0	0	0	0	0	149506
120002.6520002	RECORD TURNOVER	000	2534 HR	2534	149506	0	0	0	0	0	
120002.6600002	AS-BUILDING	000									
				8,780	447,575	0	0	0	0	0	447,575
TOTAL WBS 120002 ENG/INSP. SUPPORT											

** TEST - INTERACTIVE ESTIMATING **
 SOLID WASTE RETRIEVAL FACILITY PHASE 1
 CONCEPTUAL ESTIMATE
 DOE ROB - ESTIMATE DETAIL BY WBS / COST CODE

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. V-113/ER-2359

[illegible]

TEST - INTERACTIVE ESTIMATING ##
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
ESTIMATE DETAIL BY VBS / COST CODE

Kaiser Engineers Hanford
Westinghouse Hanford Company
Job No. W-1113/ER-2359

ACCOUNT NUMBER	DESCRIPTION
1000	1000
1001	1001
1002	1002
1003	1003
1004	1004
1005	1005
1006	1006
1007	1007
1008	1008
1009	1009
1010	1010
1011	1011
1012	1012
1013	1013
1014	1014
1015	1015
1016	1016
1017	1017
1018	1018
1019	1019
1020	1020
1021	1021
1022	1022
1023	1023
1024	1024
1025	1025
1026	1026
1027	1027
1028	1028
1029	1029
1030	1030
 
1070	1070
1071	1071
1072	1072
1073	1073
1074	1074
1075	1075
1076	1076
1077	1077
1078	1078
1079	1079
1080	1080
1081	1081
1082	1082
1083	1083
1084	1084
1085	1085
1086	1086
1087	1087
1088	1088
1089	1089
1090	1090
1091	1091
1092	1092
1093	1093
1094	1094
1095	1095
1096	1096
1097	1097
1098	1098
1099	1099

[illegible]

WBS 320002
(ESCALATION 19.66% - CONTINGENCY 25.00 %)

[illegible]

	MOISTURE	AND	THERMAL		
SUBTOTAL	77			93	0
					0
					7
					192

SALES TAX	7.80 %	
OWEP (OW MARKUPS ONLY)		
		0
		0

	3	0	100	0	202
TOTAL					
COST CODE 50107					
WBS 320002					
DECONTAMINATION 19.64% - CONTINGENCY 25.00 %					

[illegible]

	0	20,100	0	32,688
	16	400	0	187
SUBTOTAL	16	400	0	32,688
DOORS, WINDOWS AND G		2,400	0	187

SALES TAX	7.80 %	
CHRG (ON MARKUPS ONLY)		
		18

	16	0	2,587	28,160	0	1,148	32,893
TOTAL							
COST CODE 50108							
WBS 320002							
(ESCALATION 19.66% - CONTINGENCY 25.00 %)							

FINISHES	2 EA	0	0	0	80	0	4
320002.09	501						84
320002.0900002 PAINT DOORS							443
320002.0900004 PAINT OVERHEAD DOORS	501	704 SF	0	0	422	0	21
							25

502	0	0	527
502	0	0	527
SUBTOTAL FINISHES			

	0	0	0	0	502	25	527
TOTAL							
COST CODE 50109							
WBS 320002							
10 644 - CONTINGENCY 25.00 %)							

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	PRICE	TOTAL	TAX	DISCOUNT	NET TOTAL
1	ESCALATION	19.00%						
2	EQUIPMENT							
3	20002	11						

** IEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE R08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 21
DATE 01/27/94 09:25:04
BY KLR/LGH/DEA/DLM

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

**** TEST - INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE

DOE R08 - ESTIMATE DETAIL BY WBS / COST CODE
CONCEPTUAL ESTIMATE
DOE R08 - ESTIMATE DETAIL BY WBS / COST CODE[illegible]

** IEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
320002.1643010	- CONDUIT/WIRING RADIATION MONITOR, ALPHA CAM (INSTALLED)	501	6 EA	0	0	0	0	45000	0	2250	47250
320002.1643020	RADIATION MONITOR, BETA CAM (INSTALLED)	501	6 EA	0	0	0	0	45000	0	2250	47250
320002.1643030	RADIATION MONITOR, GAMMA, AREA (INSTALLED)	501	6 EA	0	0	0	0	30000	0	1500	31500
320002.1643040	FIXED HEAD AIR SAMPLING SYSTEM (INSTALLED)	501	2 EA	0	0	0	0	3000	0	150	3150
320002.1643050	AIR SAMPLING SYSTEM,	501	1 EA	80	2493	0	35000	0	0	3999	41492
320002.1644010	GROUNDING SYSTEM	501	1 LS	0	0	0	0	1000	0	50	1050
320002.1660010	MINI-POWER CENTER, 5KVA, (INSTALLATION)	501	36 EA	0	0	0	0	54000	0	2700	56700

SUBTOTAL	ELECTRICAL			80	2,493	0	35,000	288,910	0	18,445	344,848
							2730		0	273	2730

TOTAL	COST CODE 50116 WBS 320002 (ESCALAT ON 19.66% - CONTINGENCY 25.00 %)			80	2,493	0	37,730	288,910	0	18,718	347,851

TOTAL	WBS 320002 TRENCH ENCLOSURE BLDG./TRUCK LOCK			762	20,802	0	335,196	1,465,830	0	110,973	1,932,801

**** TEST - INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE ROB - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 23
DATE 01/27/94 09:25:04
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB-CONTRACT	EQUIPMENT	OH&P / B & I	TOTAL DOLLARS
320003	TRENCH OPERATION BUILDING										
320003.02	SITWORK	501	500 LF	0	0	0	0	2500	0	125	2625
320003.0200004	FOOTING EXCAV & BACKFILL										
				0	0	0		2,500	0	125	2,625
SUBTOTAL	SITWORK			0	0	0	0	2,500	0	125	2,625
TOTAL	COST CODE 50102 WBS 320003 (ESCALATION 19.66% - CONTINGENCY 25.00 %)			0	0	0	0	2,500	0	125	2,625
320003.03	CONCRETE	501	320 LF	26	664	0	288	0	0	162	1114
320003.0300004	FORM SOG	501	440 SF	35	894	0	396	0	0	218	1508
320003.0300006	FORM FOOTINGS	501	900 SF	108	2757	0	810	0	0	632	4199
320003.0300008	FORM WALLS	501	1660 SF	33	732	0	249	0	0	171	1152
320003.0300010	STRIP & OIL	501	20 CY	16	408	0	1040	0	0	186	1634
320003.0300012	CONCRETE FOOTINGS	501	15 CY	17	434	0	780	0	0	165	1379
320003.0300014	CONCRETE WALLS	501	4340 SF	22	488	0	65	0	0	104	657
320003.0300016	CURING	501	5700 LBS	57	1631	0	1995	0	0	526	4152
320003.0300018	REBAR	501	60 CY	48	1225	0	3120	0	0	557	4902
320003.0300020	CONCRETE SOG										
				362		0		0		2,721	20,697
SUBTOTAL	CONCRETE				9,233		8,743		0		681
	SALES TAX 7.80 % OH&P (ON MARKUPS ONLY)						681		0	68	68
TOTAL	COST CODE 50103 WBS 320003 (ESCALATION 19.66% - CONTINGENCY 25.00 %)			362	9,233	0	9,424	0	0	2,789	21,447
320003.07	MOISTURE AND THERMAL	501	440 SF	6	153	0	176	0	0	48	377
320003.0700006	PERIMETER INSULATION										
				6		0		0		48	377
SUBTOTAL	MOISTURE AND THERMAL				153		176		0		13
	SALES TAX 7.80 % OH&P (ON MARKUPS ONLY)						13		0	1	1
TOTAL	COST CODE 50107 WBS 320003			6	153	0	189	0	0	49	392


```

** IEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE R08 - ESTIMATE DETAIL BY WBS / COST CODE

```

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

PAGE 24
DATE 01/27/94 09:25:04
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
=====											
(ESCALATION 19.66% - CONTINGENCY 25.00 %)											
320003.08	DOORS, WINDOWS AND G										9408
320003.0800002	OVERHEAD DOOR	501	224 SF	0	0	0	0	8960	0	448	3120
320003.0800004	3/0 EXTERIOR DOOR W/HARDWARE	501	2 EA	16	400	0	2400	0	0	320	2120
320003.0800006	3/0 INTERIOR DOOR W/HARDWARE	501	2 EA	12	300	0	1600	0	0	220	
SUBTOTAL				28	700			8,960		988	14,648
SALES TAX 7.80 %											
OH&P (ON MARKUPS ONLY)											
COST CODE 50108											
WBS 320003											
(ESCALATION 19.66% - CONTINGENCY 25.00 %)											
TOTAL				28	700		4,312	8,960	0	1,019	14,991
=====											
FINISHES											
320003.09	STEEL STUD WALLS SHEETROCK	501	370 SF	0	0	0	0	925	0	46	977
320003.0900002	2 SIDES OFFICE AREA	501	270 SF	0	0	0	0	486	0	24	510
320003.0900004	1 SIDES OFFICE AREA	501	1010 SF	0	0	0	0	404	0	20	424
320003.0900006	PAINT WALLS	501	4 EA	0	0	0	0	160	0	8	168
320003.0900008	PAINT DOORS	501	3000 SF	0	0	0	0	9000	0	450	9450
320003.0900010	CONCRETE SPC	501	170 SF	0	0	0	0	238	0	12	250
320003.0900012	SUSPENDED CEILING	501	224 SF	0	0	0	0	134	0	7	141
320003.0900014	PAINT OVERHEAD DOOR	501									
SUBTOTAL				0	0	0	0	11,347	0	567	11,914
=====											
FINISHES											
COST CODE 50109											
WBS 320003											
(ESCALATION 19.66% - CONTINGENCY 25.00 %)											
TOTAL				0	0	0	0	11,347	0	567	11,914
=====											
SPECIAL CONSTRUCTION											
320003.13	PRE-ENGINEERED STEEL BLDG.	501	3000 SF	0	0	0	0	45000	0	2250	47250
320003.1300002	50 X 60 X 25	501	5 EA	0	0	0	0	1250	0	63	1313
320003.1300004	FIRE EXTINGUISHERS	501									
SUBTOTAL				0	0	0	0	46,250	0	2,313	48,563
=====											
SPECIAL CONSTRUCTION											
COST CODE 50113											
WBS 320003											
TOTAL				0	0	0	0	46,250	0	2,313	48,563

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** IEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 26
DATE 01/27/94 09:25:05
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
320003.1641020	AIR LOCK CONTROL SYSTEM - CONTROL BOX/IND. LIGHTS - WARNING BUZZER - CONDUIT/WIRING	501	1 EA	0	0	0	0	1500	0	75	1575
320003.1641050	TERMINAL CABINET BOX (INSTALLED)	501	1 EA	0	0	0	0	750	0	38	788
320003.1642010	FIRE ALARM SYSTEM - FACP - RFAR W/ANTENNA & LIGHT - DETECTORS (10EA) - FA BELL (2EA) - PULL STATION (1EA) - SPRINKLER SYSTEM ELECT. - CONDUIT/WIRING	501	3000 SF	0	0	0	0	3750	0	188	3938
320003.1644010	GROUNDING SYSTEM - 3EA TRANSFORMER, 167KVA, POLE MTD, 13.8KV-480/277V	501	1 LS	0	0	0	0	2500	0	125	2625
320003.1660010	BUILDING SERVICE - 3EA TRANSFORMER, 167KVA, POLE MTD, 13.8KV-480/277V	501	1 LS	0	0	0	0	65000	0	3250	68250
320003.1660011	OIL FILLED - POLE LINE INSTALLATION - METERING INSTALLATION - DISTRIBUTION PANELBOARD, 600AF/600AT, 480/277V	501	0	0	0	0	0	0	0	0	0
320003.1660012	- TRANSFORMER, 75KVA, DRY TYPE 480-208/120V, 3PH, 4W - PANELBOARD, 225A MBKR, 208/120V	501	0	0	0	0	0	0	0	0	0
320003.1660013	- TRANSFORMER, 225KVA, DRY TYPE 480-208/120V, 3PH, 4W - PANELBOARD, 600A MBKR, 208/120V	501	0	0	0	0	0	0	0	0	0
320003.1660014	- TRANSFORMER, 15KVA, DRY TYPE 480-208/120V, 3PH, 4W - PANELBOARD, 100A MBKR, 208/120V	501	0	0	0	0	0	0	0	0	0
320003.1660015	- DISC SW, 60A, 3P -2EA - MOTOR STARTER, SIZE 1	501	0	0	0	0	0	0	0	0	0
320003.1660016	- FEEDER CONDUIT/WIRING - EXCAVATION/BACKFILL	501	2 EA	4	125	0	0	100	0	30	255
320003.1660020	DISCONNECT SWITCH (OH DOOR)	501	1 EA	0	0	0	0	6000	0	300	6300
320003.1660021	PC COMPUTER W/PRINTER	501	1 EA	0	0	0	0	6000	0	300	6300
320003.1660022	FIBER OPTICS MUX (INSTALLED)	501	1 EA	0	0	0	0	6000	0	300	6300

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

**** TEST - INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_ROB - ESTIMATE DETAIL BY WBS / COST CODE

WHC-SD-W113-ACDR

Rev. 0

Page 607

PAGE 27
DATE 01/27/94 09:25:05
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS

				4	125	0	0	118,850	0	5,970	124,945

SUBTOTAL	ELECTRICAL			4	125	0	0	118,850	0	5,970	124,945

TOTAL	COST CODE 50116 WBS 320003 (ESCALATION 19.66% - CONTINGENCY 25.00 %)			4	125	0	0	118,850	0	5,970	124,945

TOTAL WBS 320003 TRENCH OPERATION BUILDING				400	10,211	0	13,926	228,007	0	14,837	266,982

PAGE 2Y
DATE 01/27/94 09:25:05
BY KLR/LGH/DEA/DLM** TEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODEKAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
320004.1641044	TELECOMMUNICATIONS CONTROL SYSTEM UNGERMAN BASS ACCESS	501	1 EA	0	0	0	0	100000	0	5000	105000
320004.1641050	TERMINAL CABINET BOX (INSTALLED)	501	3 EA	0	0	0	0	2250	0	113	2363
320004.1643040	FIXED HEAD AIR SAMPLING SYSTEM (INSTALLED)	501	1 EA	0	0	0	0	1500	0	75	1575
320004.1644010	GROUNDING SYSTEM	501	1 LS	0	0	0	0	500	0	25	525
320004.1660010	OFFICE BUILDING SERVICE	501	1 LS	0	0	0	0	8000	0	400	8400
320004.1660011	- TRANSFORMER, 75KVA, DRY TYPE 480-208/120V, 3PH, 4W	501	0	0	0	0	0	0	0	0	0
	- PANELBOARD, 225A MBKR, 208/120V	501	0	0	0	0	0	0	0	0	0
320004.1660012	- FEEDER CONDUIT/WIRING	501	0	0	0	0	0	12000	0	600	12600
320004.1660020	- EXCAVATION/BACKFILL	501	1 LS	0	0	0	0	0	0	0	0
320004.1660021	STAFF/CHANGE BLDG SERVICE	501	0	0	0	0	0	0	0	0	0
	- TRANSFORMER, 225KVA, DRY TYPE 480-208/120V, 3PH, 4W	501	0	0	0	0	0	0	0	0	0
	- PANELBOARD, 600A MBKR, 208/120V	501	0	0	0	0	0	0	0	0	0
320004.1660022	- FEEDER CONDUIT/WIRING	501	0	0	0	0	0	0	0	0	0
320004.1680010	- EXCAVATION/BACKFILL INSTRUMENTATION - DECON HOLDING TANK (LE/LT/LI, LDE/LDA)	501	1 LS	40	1246	0	0	3500	0	424	5170

SUBTOTAL	ELECTRICAL		40			0	0	295,550	0	15,027	311,823

TOTAL	COST CODE 50116 WBS 320004 (ESCALATION 19.66% - CONTINGENCY 25.00 %)		40			0	0	295,550	0	15,027	311,823

TOTAL WBS 320004	STAFF CHANGE & GENERAL OFFICE BLDG		40			0	0	646,970	0	32,599	680,815

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

**** TEST - INTERACTIVE ESTIMATING ****
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE ROB - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 30
DATE 01/27/94 09:25:05
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	OH&P / B & I	TOTAL DOLLARS
320005	SITE GRADING & LEVELING										
320005.02	SITWORK							5000	0	250	5250
320005.0200002	CLEAR & GRUB	460	2500 CY	0	0	0	0	16620	0	831	17451
320005.0200004	EXCAVATION	460	8310 CY	0	0	0	0	6225	0	311	6536
320005.0200006	FINE GRADING	460	24900 SY	0	0	0	0	6000	0	300	6300
320005.0200008	HAUL OFF WASTE	460	1200 CY	0	0	0	0	7500	0	375	7875
320005.0200010	WATER FOR CONSTRUCTION	460	1250 MG	0	0	0	0	10000	0	500	10500
320005.0200012	SURVEY (ALLOWANCE)	460	1 LS	0	0	0	0				
				0		0		51,345	0	2,567	53,912
SUBTOTAL	SITWORK				0		0				
				0		0		51,345	0	2,567	53,912
TOTAL	COST CODE 46002 WBS 320005 (ESCALATION 19.66% - CONTINGENCY 20.00 %)										
				0		0		51,345	0	2,567	53,912
TOTAL WBS 320005	SITE GRADING & LEVELING										
				0		0		51,345	0	2,567	53,912

** IEST - INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE_R08 - ESTIMATE DETAIL BY WBS / COST CODE

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

PAGE 31
DATE 01/27/94 09:25:05
BY KLR/LGH/DEA/DLM

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP- MENT	ON&P / B & I	TOTAL DOLLARS
320006	ROADS & PARKING										
320006.02	SITEWORK	460	0	0	0	0	0	0	0	0	0
320006.020002	ROADS										
320006.020004	CLEAR & GRUB	460	1200 CY	0	0	0	0	2400	0	120	2520
320006.020006	EXCAVATION	460	3460 CY	0	0	0	0	6920	0	346	7266
320006.020008	FINE GRADING	460	10400 SY	0	0	0	0	4160	0	208	4368
320006.020010	4" BASE COURSE	460	1685 TON	0	0	0	0	20220	0	1011	21231
320006.020012	2" LEVELING COURSE	460	985 TON	0	0	0	0	11820	0	591	12411
320006.020014	1-1/2" CL-B ASPHALT	460	450 TON	0	0	0	0	18000	0	900	18900
320006.020016	WATER FOR CONSTRUCTION	460	520 MG	0	0	0	0	3640	0	182	3822
320006.020018	STRIPING & SIGNING	460	1 LS	0	0	0	0	1500	0	75	1575
320006.020020	HAUL OFF WASTE	460	600 CY	0	0	0	0	3000	0	150	3150
320006.020022	MOBE/DEMONE	460	1 LS	0	0	0	0	1500	0	75	1575
320006.020024	PARKING LOT	460	0	0	0	0	0	0	0	0	0
320006.020026	FINE GRADING	460	1790 SY	0	0	0	0	716	0	36	752
320006.020028	4" BASE COURSE	460	400 TON	0	0	0	0	4800	0	240	5040
320006.020030	2" TOP COURSE	460	200 TON	0	0	0	0	2400	0	120	2520
320006.020032	1-1/2" CL-B ASPHALT	460	165 TON	0	0	0	0	6600	0	330	6930
320006.020034	WATER FOR CONSTRUCTION	460	90 MG	0	0	0	0	630	0	32	662
320006.020036	STRIPING	460	1 LS	0	0	0	0	750	0	38	788
320006.020038	HANDICAP SIGN & SYMBOLS	460	1 LS	0	0	0	0	500	0	25	525
320006.020040	CONCRETE PARKING BUMPERS	460	40 EA	0	0	0	0	1400	0	70	1470

SUBTOTAL			0	0	0	0	0	90,956	0	4,549	95,505

TOTAL			0	0	0	0	0	90,956	0	4,549	95,505

TOTAL WBS 320006 ROADS & PARKING			0	0	0	0	0	90,956	0	4,549	95,505

COST CODE 46002
WBS 320006
(ESCALATION 19.66% - CONTINGENCY 20.00 %)

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** TEST INTERACTIVE ESTIMATING **
 SOLID WASTE RETRIEVAL FACILITY PHASE 1
 CONCEPTUAL ESTIMATE
 DOE KOB - ESTIMATE DETAIL BY URS / COST CODE

PAGE 52
DATE 01/27/94 09:25:05
BY NLR/TGJ/DLA/DIM

[illegible]

Kaiser Engineers Hanford
Westinghouse Hanford Company
Job No. W-113/ER-2359

** TEST INTERACTIVE ESTIMATING **
 SOLID WASTE RETRIEVAL FACILITY PHASE 1
 CONCEPTUAL ESTIMATE
 DUE ROB - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 33
DATE 01/27/96 09:25:05
BY N1R1GH/DLA/DLM

[illegible]

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

*** TEST - INTERACTIVE ESTIMATING ***
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE ROB - ESTIMATE DETAIL BY WBS / COST CODE

PAGE 54
DATE 01/27/94 09:25:05
BY AIN/IGH/DEA/DIM

ACCOUNT NUMBER	DESCRIPTION	LOST CODE	QUANTITY	HANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP MENI	ORHP / B & I	TOTAL DOLLARS
320009	WATERLINES										
320009.02	SITWORK										
320009.0200002	12" C-900 PVC PIPE	600	2420 LF	0	0	0	0	43560	0	2178	45738
320009.0200004	8" CL-50 DI PIPE	600	1800 LF	0	0	0	0	27000	0	1350	28350
320009.0200006	6" CL-50 DI PIPE	600	200 LF	0	0	0	0	2600	0	130	2730
320009.0200008	4" CL-50 DI PIPE	600	140 LF	0	0	0	0	1400	0	70	1470
320009.0200010	2" SCH 40 GALV PIPE	600	100 LF	0	0	0	0	1000	0	50	1050
320009.0200012	TRENCH EXCAVATION	600	4660 LF	0	0	0	0	18640	0	932	19572
320009.0200014	TRENCH BACKFILL	600	4660 LF	0	0	0	0	16310	0	816	17126
320009.0200016	PIPE BEDDING	600	4660 LF	0	0	0	0	4660	0	233	4893
320009.0200018	LOCATE TAPE	600	4660 LF	0	0	0	0	1165	0	58	1223
320009.0200020	ROADWAY X-INGS	600	2 EA	0	0	0	0	7000	0	350	7350
320009.0200022	FIRE HYDRANTS	600	11 EA	0	0	0	0	12100	0	605	12705
320009.0200024	THRUST BLOCKS	600	48 EA	0	0	0	0	3840	0	192	4032
320009.0200026	GUARD POSTS	600	128 EA	0	0	0	0	16000	0	800	16800
320009.0200028	VALVE BOXES	600	14 EA	0	0	0	0	1120	0	56	1176
320009.0200030	12" POST INDICATOR VALVE	600	10 EA	0	0	0	0	21000	0	1050	22050
320009.0200032	12" X 10" REDUCER	600	2 EA	0	0	0	0	560	0	28	588
320009.0200034	12" MJ CAPS	600	2 EA	0	0	0	0	250	0	13	263
320009.0200036	12" FL TEE	600	4 EA	0	0	0	0	1520	0	76	1596
320009.0200038	12" MJ 90	600	2 EA	0	0	0	0	600	0	30	630
320009.0200040	12" MJ X FL ADPT	600	2 EA	0	0	0	0	350	0	18	368
320009.0200042	12 X 8 MJ X FL TEE	600	3 EA	0	0	0	0	1125	0	56	1181
320009.0200044	12 X 6 MJ X FL TEE	600	6 EA	0	0	0	0	2250	0	113	2363
320009.0200046	12 X 4 MJ X FL TEE	600	2 EA	0	0	0	0	750	0	38	788
320009.0200047	12 X 8 REDUCER	600	1 EA	0	0	0	0	280	0	14	294
320009.0200048	12 X 2 DOUBLE STRAP SADDLE	600	1 EA	0	0	0	0	280	0	14	294
320009.0200050	8" POST INDICATOR VALVE	600	11 EA	0	0	0	0	13750	0	688	14438
320009.0200052	8" MJ CAP	600	7 EA	0	0	0	0	595	0	30	625
320009.0200054	8" MJ 90	600	1 EA	0	0	0	0	150	0	8	158
320009.0200056	8" MJ 45	600	2 EA	0	0	0	0	300	0	15	315
320009.0200058	8" FL TEE	600	2 EA	0	0	0	0	350	0	18	368
320009.0200060	8" MJ X FL TEE	600	1 EA	0	0	0	0	210	0	11	221
320009.0200062	8" MJ X FL ADPT	600	1 EA	0	0	0	0	100	0	5	105
320009.0200064	8 X 6 MJ X FL TEE	600	5 EA	0	0	0	0	1050	0	53	1103
320009.0200066	6" MJ X FL GATE VALVE	600	11 EA	0	0	0	0	3300	0	165	3465
320009.0200068	4" GATE VALVE	600	2 EA	0	0	0	0	460	0	23	483
320009.0200070	4" MJ CAP	600	2 EA	0	0	0	0	110	0	6	116
320009.0200072	2" BLOW OFF ASSY.	600	1 EA	0	0	0	0	275	0	14	289
320009.0200074	2" GATE VALVE	600	1 EA	0	0	0	0	150	0	8	158
320009.0200076	2" CAP	600	1 EA	0	0	0	0	20	0	1	21

PAGE 36
DATE 01/27/94 09:25:06
BY AIR/IGH/DEA/DIM

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

INTERACTIVE ESTIMATING **
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DOE RUB - ESTIMATE DETAIL BY WBS / COST CODE

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	HOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP MENT	DISP / B & I	TOTAL DOLLARS
320010	SITE ELECTRICAL & INSTRUMENTATION										
320010.16	ELECTRICAL	600	1 IS	0	0	0	0	65000	0	5250	68250
320010.1620010	COMMUNICATIONS SYSTEM (HLAN/SWITS/GTE/CONTROL)										
	- CONDUIT/EXCAVATION										
	- CABLE	600	3 EA	0	0	0	0	10500	0	525	11025
320010.1630090	PARKING LOT LIGHTING, 480V - LIGHT POLE, SINGLE ARM	600									
	- CONDUIT/WIRING	600	15 EA	0	0	0	0	26250	0	1515	27563
320010.1630092	ROADWAY LIGHTING, 480V - WOOD LIGHT POLE										
	- SINGLE ARM FIXTURE										
	- CONDUIT/WIRING	600	1 IS	0	0	0	0	5000	0	250	5250
320010.1630094	REMOVE POLE LIGHTING, 2,400V	600									
320010.1660010	SITE SERVICE, 13.8 KV - OH LINE WORK	600	1 IS	0	0	0	0	65000	0	5250	68250
	- UNDERGROUND DISTRIBUTION										
SUBTOTAL	ELECTRICAL				0	0	0	171,750	0	8,588	180,338
TOTAL	COST CODE 60016 WBS 320010 (ESCALATION 19.66% - CONTINGENCY 25.00 %)				0	0	0	171,750	0	8,588	180,338
TOTAL WBS 320010	SITE ELECTRICAL & INSTRUMENTATION				0	0	0	171,750	0	8,588	180,338

** TEST - INTRACTIVE ESTIMATING **
 SOLID WASTE RETRIEVAL FACILITY PHASE 1
 CONCEPTUAL ESTIMATE
 DOE KOB - ESTIMATE DETAIL BY WBS / COST CODE

RAISER ENGINEERS HANFORD
TESTINGHOUSE HANFORD COMPANY
R NO. W-113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB-CONTRACT	EQUIP REHT	ORHP / U & I	TOTAL DOLLARS
50000	PLANT FORCES CONSTRUCTION										
30000.16	ELECTRICAL		1 IS	0	0	0	0	3500	0	175	3675
30000.1699000	HV TIE-IN'S & HI-POT TESTING	600								175	
				0			0	3,500	0		3,675
SUBTOTAL	ELECTRICAL									175	
				0	0	0	0	3,500	0		3,675
TOTAL	COST CODE 60016 WBS 330000 (ESCALATION 25.61% - CONTINGENCY 25.00 X)										
				0	0	0	0	3,500	0	175	3,675
TOTAL WBS 330000 PLANT FORCES CONSTRUCTION				0	0	0	0	3,500	0		3,675

PAGE 58
DATE 01/27/94 09:25:06
BY KIK/IGU/DEA/DLM

AA TEST INTERACTIVE ESTIMATING AA
SOLID WASTE RETRIEVAL FACILITY PHASE 1
CONCEPTUAL ESTIMATE
DUE RUB - ESTIMATE DETAIL BY UBS / COST CODE

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	HANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB- CONTRACT	EQUIP MENT	ORAP / B & I	TOTAL DOLLARS
400000	PROJECT INTEGRATION/MGMT. (U/C)										
400000.19	PROJECT MANAGEMENT	700	1 IS	0	0	0	0	1346000	0	0	1346000
400000.19000002	WHC PROJECT MANAGEMENT			0	0	0	0	1,346,000	0	0	1,346,000
	SUBTOTAL PROJECT MANAGEMENT							0			
	TOTAL							1,346,000	0	0	1,346,000
	COST CODE 70019										
	WBS 400000										
	(ESCALATION 0.00X - CONTINGENCY 16.00 X)										
	TOTAL WBS 400000 PROJECT INTEGRATION/MGMT. (U/C)							1,346,000	0	0	1,346,000

RAISER ENGINEERS HANFORD
TESTINGHOUSE HANFORD COMPANY
JOB NO. W-113/ER-2359

** ILSI - INTERACTIVE ESTIMATING **
 SOLID WASTE RETRIEVAL FACILITY PHASE 1
 CONCEPTUAL ESTIMATE
 DUE FOR - ESTIMATE DETAIL BY VBS / COST CODE

PAGE 39
DATE 01/27/94 09:25:06
BY KIR/LGH/DEA/DIH

ACCOUNT NUMBER	DESCRIPTION	COST CODE	QUANTITY	MANHOURS	LABOR	EQUIP USAGE	MATERIAL	SUB-CONTRACT	EQUIP REHT	UNIT / U & I	TOTAL DOLLARS
00000	OTHER PROJECT COST										
00000.00	TECHNICAL SERVICES										
00000.00000002	OTHER PROJECT COST (EXPENSE)	900	1.15	0	0	0	0	19070000	0	0	19070000
	PROJECT SUPPORT, ENVIR. Q/A										
	SAFETY, OPERATIONS, START-UP										
	, ENGINEERING DEVELOPMENT										
	SUBTOTAL TECHNICAL SERVICES							19,070,000	0	0	19,070,000
	TOTAL							19,070,000	0	0	19,070,000
	COST CODE 90000										
	WBS 500000										
	(ESCALATION 0.00% - CONTINGENCY 0.00 %)										
	TOTAL WBS 500000 OTHER PROJECT COST							19,070,000	0	0	19,070,000

**DATE
FILMED**

9/29/94

END