**Collection of VLE Data for
Acid Gas - Alkanolamine Systems
Using Fourier Transform Infrared Spectroscopy**

**Phase 2 Report
for Period October 1, 1991 - September 30, 1992**

Jerry A. Bullin and Richard E. Frazier

**Texas Engineering Experimental Station
Texas A & M University
College Station, TX 77843-3577**

Prepared for

**THE U. S. DEPARTMENT OF ENERGY
AGREEMENT NO. DE-FC02-90CE40938**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

NOTICE

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed or represents that its use would not infringe privately-owned rights.

Table of Contents

List of Figures.....	ii
Abstract.....	1
Introduction.....	1
Scope of Investigation.....	4
Significant Results.....	5
Accomplishments.....	5
Compliance with Agreement Requirements	7
Project Economic Update	14
References.....	15

List of Tables

Table 1	Completion Dates for the Measurable Objectives.....	5
Table 2	DOE Milestone Plan for Project DE-FC02-90CE40938.....	25

List of Figures

Figure 1	Alkanolamine Purification Process.....	16
Figure 2	Hydrogen Sulfide Spectrum Over Calibration Frequency Range.....	17
Figure 3	Carbon Dioxide Spectrum Over Calibration Frequency Range.....	18
Figure 4	Water Spectrum Over Calibration Frequency Range.....	19
Figure 5	Hydrogen Sulfide Calibration Curve at 15 psia Total Pressure.....	20
Figure 6	Carbon Dioxide Calibration Curve at 15 psia Total Pressure.....	21
Figure 7	Carbon Dioxide Solubility in Water	22
Figure 8	Hydrogen Sulfide Solubility in Water	23
Figure 9	Hydrogen Sulfide Solubility in 2.0 N Diethanolamine at 50 °C	24

Abstract

The industrial standard process for the purification of natural gas is to remove acid gases, mainly hydrogen sulfide and carbon dioxide, by the absorption and reaction of these gases with alkanolamines. Inadequate data for vapor - liquid equilibrium (VLE) hinder the industry from converting operations to more energy efficient amine mixtures and conserving energy. Some energy reductions have been realized in the past decade by applying such amine systems as "hindered" amines, methyldiethanolamine (MDEA), and MDEA based amine mixtures. However, the lack of reliable and accurate fundamental VLE data impedes the commercial application of these more efficient alkanolamine systems. The first project objective is to improve the accuracy of vapor - liquid equilibrium measurements at low hydrogen sulfide concentrations. The second project objective is to measure the VLE for amine mixtures. By improving the accuracy of the VLE measurements on MDEA and mixtures with other amines, energy saving can be quickly and confidently implemented in the many existing absorption units already in use. If about 25% of the existing 95.3 billion SCFD gas purification capacity is converted to these new amine systems, the energy savings are estimated to be about 3×10^{14} BTU/yr.

Introduction

The industrial standard process for the purification of natural gas is to remove acid gases, mainly hydrogen sulfide (H_2S) and carbon dioxide (CO_2), by the absorption and reaction of these gases with alkanolamines. Monoethanolamine (MEA) and diethanolamine (DEA) are the predominate alkanolamines used by natural gas processors, refiners, ammonia producers, and synthetic gas producers. The gas stream contaminated with acid gases, called a sour gas stream, is fed to an absorber column where it is contacted countercurrently with a solution of alkanolamine and water. This process is sketched in Figure 1. After the acid gases are absorbed, the reacted alkanolamine, or rich amine, is sent to a regeneration or stripper column. The chemical reaction is reversed and the acid gases are stripped from the solution by adding heat. Since the regenerator is operated at elevated temperature, the lean amine stream is

cross-exchanged with the rich amine stream for heat recovery. Excessive pumping energy and reboiler duty are consumed when these gas purification units are operated within equilibrium pinch zones where there is a lack of accurate VLE data for acid gas - alkanolamine mixtures. Inadequate models for VLE, kinetics, and mass transport hinder the industry from converting operations to more energy efficient amine mixtures and conserving energy. In addition to energy waste, the inefficient gas purification operations result in the combustion of additional fossil fuel, primarily natural gas, to produce the energy required for the purification process. Thus the wasted energy also results in the release of additional CO_2 , CO , and NO_x combustion byproducts into the atmosphere.

Some energy reductions have been realized in the past decade by applying such amine systems as "hindered" amines, methyldiethanolamine (MDEA), or MDEA based amine mixtures.^[4,5,7] MDEA based amines have demonstrated greater solvent capacity and selective absorption for H_2S in many applications now serviced by MEA and DEA. Additional advantages for MDEA amine systems are an improved corrosion performance, a lower heat of reaction, a higher solution concentration, and an improved solution stability. Designs that incorporate these advantages of MDEA based amines can reduce the pumping energy and reboiler duty of amine operations from 25 to 60%. However, the lack of reliable and accurate fundamental VLE data impedes the commercial application of these more efficient alkanolamine systems. The most critically deficient area for VLE data occurs in the lean amine equilibrium pinch zones in the bottom of the stripper and top of the absorber. The lean pinch zones typically have H_2S partial pressures less than 0.1 psia and loadings less than 0.01 mol/mol of amine. Other important areas include the high temperature pinch zones within the absorber and the rich amine equilibrium pinch zone in the bottom of the absorber. The rich pinch zones can have extremely high acid gas partial pressures but usually less than 200 psia.

Natural gas processors and petroleum refiners are the two major industries using alkanolamine purification. The amount of gas processed by these industries is about 95.3 billion standard cubic feet per day (BSCFD). MDEA based amines have the potential of saving energy in more than 28 BSCFD of this total processed volume. Without new accurate amine VLE

data for MDEA based amine mixtures, 25 BSCFD of this processed gas will not realize the full potential energy savings. The energy savings potential for the conversion of 25 BSCFD capacity to these more efficient amines is estimated to be about 3×10^{14} BTU/yr. At current gas prices, this amount of energy is equivalent to about \$500 million a year.

Scope of Investigation

The overall project has two major objectives. The first is to improve the accuracy of vapor - liquid equilibrium measurements at low hydrogen sulfide concentrations. The second is to measure the VLE for amine mixtures. The objectives are pursued in three phases each lasting about one year. Phase I will develop and demonstrate the application of quantitative infrared spectroscopy to VLE measurements of acid gas - DEA systems. The infrared technique will improve the accuracy of conventional methods in the low hydrogen sulfide concentration range. The technique also allows a more thorough analysis of the liquid phase reaction products. Phase II will then expand the technique to include MDEA. Phase II equilibrium measurements will include MDEA and a mixture of MDEA - DEA. Once the technique for mixtures of two amines is developed in Phase II, the technique will be used in Phase III for measurements of MEA and MDEA - MEA amine mixtures.

Significant Results

The following measurable objectives were cited in the original proposal and scheduled to be completed by the end of Phase II on September 31, 1992.

1. A technical paper describing the equilibrium equipment and infrared measurement technique.
2. A set of equilibrium data for H_2S - CO_2 - DEA which will demonstrate the accuracy of the infrared technique.
3. A set of equilibrium data for H_2S - CO_2 - MDEA.
4. A set of equilibrium data for H_2S - CO_2 - MDEA - DEA.
5. A technical paper describing the MDEA VLE data.
6. A technical paper describing the MDEA - DEA VLE data.
7. A report for the Department of Energy summarizing the work completed during Phase II

Measurable objectives #1 & 2 were uncompleted objectives brought forward from Phase I. Delays in the construction of the equipment resulted in objectives #1 - 6 being rescheduled. The rescheduled completion dates for objectives #1 - 6 are presented in Table 1. Measurable objective #7 is this report. Measureable objectives are cross referenced with the Milestone Plan last revised in October 1992. The Milestone Plan is presented in Table 2. For convenience, Table 1 also includes the current cross-referenced milestone numbers.

Table 1
Completion Dates for the Measureble Objectives

Objective Number	Description	Completion	Milestone Number
1	FTIR Journal Article	12/92	8
2	DEA Data Set	10/92	6
3	MDEA Data Set	02/93	13
4	DEA/MDEA Data Set	02/94	16
5	MDEA Journal Article	04/93	14
6	DEA/MDEA Journal Article	04/94	17

Accomplishments

1. The first major accomplishment during Phase II was the initial successful pressure test of the entire equipment system.

2. The second major accomplishment was the simultaneous alignment of each of the infrared analytical cells. This includes the multipass transmittance cell, the short path transmittance cell, and the liquid CIR cell. The analytical devices were then permanently positioned to the equipment framework.

3. The third major accomplishment was the identification of each component frequency range for the quantitative analysis. The gas phase component spectra of H₂S, CO₂, and H₂O were each measured and then evaluated for quantitative response. The spectra were taken at 2.0 cm⁻¹ resolution. This moderate resolution was used because the spectra revealed each component could be measured without interferences from the other components and likely impurities. All the calibrations relate the integrated area under the spectrum to the component partial pressure. The calibration frequency range for H₂S is 2732.7 to 2633.4 cm⁻¹. Figure 2 is a typical spectrum for the H₂S frequency range. This frequency range is baseline corrected using seven baseline points. The baseline points used were 2732.7, 2719.9, 2708.4, 2701.8, 2683.4, 2668.9, and 2633.4. The calibration frequency range for CO₂ is 2390.4 to 2283.3 cm⁻¹. Figure 3 is a typical spectrum for the CO₂ frequency range. This frequency range is baseline corrected using the two end points of the range. The calibration frequency range for H₂O is 5359.4 to 5323.7 cm⁻¹. Figure 4 is a typical spectrum for the H₂O frequency range. Like the H₂S baseline correction the H₂O frequency range is baseline corrected using seven baseline points. The baseline points used were 5359.4, 5351.6, 5347.8, 5342.0, 5335.2, 5330.4, and 5323.7.

4. The fourth major accomplishment was the calibration of the infrared frequency response with the partial pressures of CO₂ and H₂S. The calibrations are based on the integrated area under the component spectrum after baseline corrections. The calibration curve for H₂S is shown in Figure 5. The calibration curve for CO₂ is shown in Figure 6. The calibration curve for H₂O is not completely defined.

5. The fifth major accomplishment was reproducing literature VLE data for a CO₂ - H₂O system and an H₂S - H₂O system. The gas phase partial pressures were determined by ideal gas calculations and the liquid phase compositions were determined by gas chromatography. Gravimetrically determined standards of each acid gas in an aqueous diethanolamine solution were used in the calibration of the gas

chromatograph. The experimental results for the CO₂ - H₂O system are compared with literature values and shown in Figure 7. The experimental results for the H₂S - H₂O system are compared with literature values and shown in Figure 8.

6. The sixth major accomplishment was the VLE measurement of an H₂S - DEA - H₂O system. The infrared calibration curves were used to determine the gas phase acid gas concentration. The liquid phase concentration was determined by gas chromatography. Gravimetric standards were used to calibrate the gas chromatograph just as in the acid gas - water systems. The experimental results obtained to date are compared with other literature values and shown in Figure 9.

Compliance with Agreement Requirements

Phases I & II were divided into the following tasks, subtasks and milestones. These subdivisions were derived from the original proposal and subsequent milestone plan. A summary for each task, subtask, and milestone is given. Each summary describes whether the task is complete, what problems have arisen, and any schedule corrections. The subdivisions are listed by the milestone number of the current Milestone Plan last revised in October 1992. In addition, the subtask will be cross referenced to the original proposal tasks and subtasks by a roman numeral Phase number, a period, and an arabic numeral subtask number.

Task I.1:

Technique Development

Compliance/Failure: In the original proposal, this task was divided into four subtasks. Since that time, this task has been divided into seven milestones (Milestone #1 - 7). Three of the seven milestones have been completed and two more are in progress. Thus, the overall task has not been completed. Further details for each milestone are provided below.

Problems: The major problem in completing this Task is maintaining a leak free equipment system. A leak tight system is necessary to provide accurate and reproducible results. Small leaks develop most often and are the most difficult to locate. Finding a leak requires that insulation and heating tapes be removed to expose the numerous tubing fittings. Leak testing often results in several days of downtime. After the leak is found

and repaired, the equipment must again be reassembled with the heating tapes and insulation. Then, the interrupted experiment is restarted

Schedule update: The projected completion date for this task is now April 1, 1993.

Milestone 1: (Task I.1a)

Identification of the Unique Spectrum Frequencies for Each of the System Components

The infrared spectra of each system component; water, diethanolamine, hydrogen sulfide, and carbon dioxide; will be recorded at a resolution of 0.5 cm^{-1} wavenumbers. The observed frequencies will be catalogued as pure component frequencies or impurity component frequencies. Impurity identification will be attempted with a gas chromatographic separation and subsequent infrared analysis.

Compliance/Failure: This task was completed in July 1992. The original procedure was changed slightly to accelerate the technique development.

Problems: The high resolution requirement of 0.5 cm^{-1} wavenumbers requires much more computer time and memory than the lower resolution of 2.0 cm^{-1} wavenumbers. Inspection of the infrared component spectra revealed that the high resolution was not required to isolate individual frequency bands for each component. Thus, the lower resolution of 2.0 cm^{-1} wavenumbers was chosen to accelerate the data acquisition and reduce the computational resources necessary to analyze the data.

Milestone 2:

Pressure Test of the Equilibrium Equipment

After construction, the equilibrium apparatus must be tested to verify the integrity of the apparatus. The apparatus must be able to confine all the system components under pressure for the time period of an experimental run. The test is a 24 hour 100 psig nitrogen pressure test of the entire apparatus. The test is successful if no pressure loss is detected within the 0.2 psig detectability limit of the test pressure gauge.

Compliance/Failure: This task was completed in October 1991.

Problems: Several small obscure system leaks were difficult to locate and eliminate. The two leaks which resulted in the longest delays were the infrared window seals on the multipass cell and the thermocouple wiring in the multipass cell. The first troublesome leak, the multipass cell window

leaks, was the result of small fractures in the window material. The cracks were produced when the windows were stressed during installation. The problem, once discovered, was solved when the gasket material was changed to neoprene and the stresses were more evenly distributed over the window surface. The second troublesome leak was discovered in the thermocouple wiring. The first thermocouples used in the multipass cell had exposed wire to the process streams. The pressure tests eventually revealed that the gas was escaping through an insulation layer between the wire and the polymer wire coating. The thermocouples were then replaced with stainless steel sheathed probes.

Maintaining the leak free system continues to be the major operational problem.. Leaks develop with system use. The unexpected leaks often interrupt experiments and result in days of downtime to locate and repair the leaks.

Milestone 3:

Align and Optimize the Analytical Measurement Cells

Compliance/Failure: This milestone was added during Phase II and was completed in December 1991.

Milestone 4: (Task L1b)

Calibration of the FTIR Response for Each of the Component Concentrations

The relationship between infrared absorbance and the component concentration must be established for each component. The calibration effort includes identifying whether the relationship between concentration and absorbance is linear or non-linear and determining the relative ratio between component frequencies at several sets of operating conditions.

Compliance/Failure: This task was initially completed in July 1992. The calibrations were successfully tested against two known gas mixtures with less than 10% error. The H₂S and CO₂ calibration curves are complete. Testing of the water calibration indicates more data will be needed to define the calibration curve. This additional work is shown on the revised milestone plan.

Problems: A compromise is made when using the lower resolution of 2.0 cm⁻¹ wavenumbers for the component calibrations. The infrared frequencies for the components are not fully resolved and this results in a

calibration curve that is also a function of total pressure. The experimental consequence is that a reference total pressure must be chosen and used to operate all the experiments. Thus, the desired component partial pressures are charged to the equipment and then the equipment is loaded with an inert gas such as nitrogen to reach the chosen reference pressure. The current reference pressure is 15.0 psia.

Schedule Update: The additional experiments needed to define the water calibration will be completed by November 1, 1992.

Milestone 5: (Task L1c)

Demonstration of the Quantitative Response of the System Mixture

A well studied system mixture of H_2S - CO_2 - DEA will be tested to confirm the additive properties of the individual components. Reaction products also will be identified as possible. The system mixture will be of a compositional range which is accurately measured using gas chromatography. Chromatographic analysis will be used to confirm the accuracy of the infrared technique.

Compliance/Failure: This task is in progress. The results of the data collected thus far is described as Accomplishment 6 in the Significant Results Section.

Schedule Update: This task will be completed in October 1992.

Milestone 6: (Task 2)

Technique Authentication for DEA

Determine vapor - liquid equilibrium data for a H_2S - CO_2 - DEA system different from the one used in Subtask 1c. The DEA system will be used to authenticate the infrared technique. The new DEA system will be within a compositional range suitable for gas chromatographic analysis.

Compliance/Failure: This task is not complete. This task was originally included in case there were non-ideal interactions to consider in the analysis of the gas phase. The calibration tests of milestone # 4 indicates that this task will not be necessary.

Schedule Update: This task will likely be dropped from the work plan in October 1992.

Milestone 7: (Task L1d)

Determination of Temperature and Pressure Limits for the System Mixtures

The system will be developed within a typical pressure and temperature range for gas sweetening operation. However, it is not presently known if the infrared technique will work in the extremely high temperature and pressure ranges of some sweetening operations. A series of experiments will determine the operational limits of this new technique. The upper bounds of interest are about 250°F and 500 psia.

Compliance/Failure: This task is not complete.

Problems: The gas circulation pump required to increase the maximum operational pressure is commercially available, but not within our budget. Affordable circulating gas pumps may be custom built. One prototype unit has been designed and built. The pump will be installed before Jan. 1, 1993. This milestone will proceed after the new equipment is installed.

Schedule Update: This task will be completed by April 1, 1993.

Milestone 8: (Task 3)

Submission of a Journal Article Describing the Infrared Equipment and Technique

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by Jan. 1, 1993.

Milestone 9:

Submission of a Journal Article for DEA VLE Measurements

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by Feb. 1, 1993.

Task II.1:

Technique Development for MDEA Solutions

Compliance/Failure: In the original proposal, this task was divided into three subtasks. Since that time, this task has been further divided into four milestones (Milestone #10 - #13). The task has not been completed. Further details are provided for each milestone.

Problems: The task has not been started. This work sequentially follows the DEA VLE experiments. The delays of the previous DEA work have postponed this work.

Schedule Update: This task will be completed by Jan. 1, 1993.

Milestone 10: (Task II.1a)

Identification of the unique spectrum frequencies for MDEA

The liquid and vapor spectra of MDEA must be identified and cataloged.

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by Dec. 1, 1992.

Milestone 11: (Task II.1b)

Calibration of the FTIR response for each of the new component concentrations

The relationship between infrared absorbance and concentration must be established for MDEA. The reaction products of MDEA with H_2S and CO_2 will also be identified as possible. The DEA work indicates that this milestone can be accomplished simultaneously with the Milestone # 10 work.

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by Jan. 1, 1993.

Milestone 12: (Task II.1c)

Demonstration of the quantitative response of the system mixture

A well studied system mixture of H_2S - CO_2 - MDEA will be tested to confirm the additive properties of the individual components. The system mixture will be of a compositional range which is accurately measured using gas chromatography. Chromatographic analysis will be used to confirm the accuracy of the infrared technique.

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by Jan. 1, 1993.

Milestone 13: (Task II.2)

Technique Authentication for MDEA

Determine vapor - liquid equilibrium data for a H_2S - CO_2 - MDEA system different from the one used in Phase II, Task 1, Subtask c. The MDEA system will be used to authenticate the infrared technique. The new MDEA system will be within a compositional range suitable for gas chromatographic analysis. Again, the compositional range will be extended into the low H_2S concentrations, beyond the range of accurate

chromatographic analysis. The DEA work indicates that this milestone can be accomplished simultaneously with the Milestone # 12 work.

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by Mar. 1, 1993.

Milestone 14: (Task II.5)

Submission of a Journal Article for MDEA VLE Measurements

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by May 1, 1993.

Milestone 15: (Task II.3)

Technique Development for MDEA - DEA Solutions.

A mixture of MDEA and DEA will be tested to confirm the additive properties of the individual amines in various ratios.

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by Jan. 1, 1994.

Milestone 16: (Task II.4)

Technique Authentication for MDEA - DEA

Determine vapor - liquid equilibrium data for a H_2S - CO_2 - MDEA - DEA system.

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by Mar. 1, 1993.

Milestone 17: (Task II.5)

Submission of a Journal Article for MDEA - DEA VLE Measurements

Compliance/Failure: This task is not complete.

Schedule Update: This task will be completed by May 1, 1993.

Task II.6

Presentation of Technique and Results at a National Conference

This task will be scheduled after completion of the DEA VLE experiments and submission of the DEA technical paper.

Task II.7

Revision of Project Economics

The last revision has been reviewed. The economics of the last revision are still current. The last Project Economic Update has been reprinted below.

Project Economic Update

The economic impact presented in the original proposal was based on energy estimates by Don Ballard^[1] and our own estimate of the gas purification capacity in the U.S. The original estimate was 3×10^{14} BTU's saved in the year 2010. Several updates have been made in an attempt to more strongly substantiate this energy savings estimate. Two major industries, natural gas processing and petroleum refining, were targeted for substantiating the capacity estimate. The Oil and Gas Journal^[6] reports the 1989 capacity for U.S. gas processors is 66×10^9 SCFD. We have obtained a refinery operations estimate by taking published refinery capacity figures and operating figures from the Amoco Refining Co. in Texas City, TX.^[2,3] We have estimated the total amount of gas processed in refineries at 29.3×10^9 SCFD. The calculations are outlined in letter dated July 15, 1991 and sent to Mr. Norm Swift. The amount of gas processed by these industries is about 95.3 billion standard cubic feet per day (BSCFD). MDEA based amines have the potential of saving energy in more than 28 BSCFD of this total processed volume. Our original estimate was based on the conversion of only 25 BSCFD of this volume. Our best estimates of the energy impact this project will have on the U.S. energy consumption is between 1 and 3.5×10^{14} BTU's saved in the year 2010.

References

- 1 Ballard, Don; *Energy Progress*, 1986, vol. 6, no. 2, p. 112.
- 2 Corbett, Richard A.; "Capacity Rise Reflects Return to Better Times for U.S. Refiners", *Oil & Gas Journal*, vol. 87, mar. 20, 1989, p. 49+
- 3 Lucas, Kathleen; Amoco Refining, Texas City, TX, personal communication, Jul. 1991
- 4 Miessner, R. E. III, *Energy Progress*, 1984, vol. 4, no. 1, p.17.
- 5 Schendel, R. L. , *Oil & Gas J*, 1982, vol 80, no. 43, p. 158.
- 6 True, Warren R.; "Worldwide Gas-processing Growth Slows", *Oil & Gas Journal*, Jul. 9, 1990
- 7 United Gas Pipe Line Co., *Oil & Gas J*, 1984, vol 82, no. 2, p 87.

Figure 1

Alkanolamine Purification Process

Figure 2
Hydrogen Sulfide Spectrum Over Calibration
Frequency Range

Figure 3
Carbon Dioxide Spectrum Over Calibration
Frequency Range

Figure 4
Water Spectrum Over Calibration
Frequency Range

Figure 5

Hydrogen Sulfide Calibration Curve
at 15 psia Total Pressure

Figure 6

Figure 7

Carbon Dioxide Solubility in Water

Figure 8

Figure 9

Hydrogen Sulfide Solubility
in 2.0 N Diethanolamine at 50 °C

DOE Milestone Plan for Project DE-FC02-9C

25

DOE Milestone Plan for Project DE-FC02-90CE40938

[illegible]

**DATE
FILMED
01/08/93**