LA-UR- 94-1511

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Los Alamos
NATIONAL LABORATORY

Title: ENGINEERING STUDY
RADIOACTIVE LIQUID WASTE TREATMENT PLANT
REFURBISHMENT

Author(s): ICF Kaiser, Inc. and University of California
Los Alamos National Laboratory
Isaac L. Suazo, CST-7

Submitted to: U. S. Department of Energy
Defense Nuclear Facilities Safety Board

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Los Alamos National Laboratory, an affirmative action/equal opportunity employer, is operated by the University of California for the U.S. Department of Energy under contract W-7405-ENG-36. By acceptance of this article, the publisher recognizes that the U.S. Government retains a nonexclusive, royalty-free license to publish or reproduce the published form of this contribution, or to allow others to do so, for U.S. Government purposes. The Los Alamos National Laboratory requests that the publisher identify this article as work performed under the auspices of the U.S. Department of Energy.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

Engineering Study

RADIOACTIVE LIQUID WASTE TREATMENT
PLANT REFURBISHMENT

Los Alamos
National Laboratory

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

JP

October 29, 1993
ENG-3-FS-94-002

Feasibility Study
for
Radioactive Liquid Waste Treatment Plant(RLWTP)
Refurbishment
at TA-50

Project Identification 10411

Prepared by
ICF Kaiser Engineers, Inc.
and
University of California
Los Alamos National Laboratory
Facilities Engineering Division
Los Alamos, NM 87545

EM-7 Program Manager

Design Team Leader

RLW Project Manager

Radioactive Liquid Waste Treatment Plant Refurbishment Index

I.	Executive Summary	I-1 - I-2
II.	Objective	II-1
III.	Environment, Safety, & Health	III-1 - III-2
IV.	Security	IV-1
V.	Current Operation	V-1 - V-4
VI.	Facility Deficiencies	VI-1 - VI-3
VII.	Design Concept	
	A. General Description	VII-1 - VII-2
	B. Treatment Process	VII-3 - VII-7
	C. Environmental	VII-8 - VII-12
	D. Utilities	VII-13 - VII-15
	E. Civil	VII-16
	F. Structural	VII-17 - VII-20
	G. Architectural	VII-21 - VII-25
	H. Mechanical	VII-26 - VII-32
	I. Electrical	VII-33 - VII-39
VIII.	Estimate	
IX.	Drawings	
X.	Supporting Information	
	A. Mission Need Statement	
	B. Comparison Matrix	
	C. Table B	

X. Supporting Information

D. Exhibit C

E. Calculations

F. Schedule

I. EXECUTIVE SUMMARY

This feasibility study will investigate the opportunities, restrictions and cost impact to refurbish the existing Radioactive Liquid Waste Treatment Plant (RLWTP) while utilizing the same basic criteria that was used in the development of the new Radioactive Liquid Waste Treatment Facility (RLWTF). The objective of this study is to perform a more in-depth analysis of refurbishing the existing than has been done in the past so as to provide a basis for comparison between refurbishing the existing or constructing a new .

The existing plant is located at Technical Area 50 (TA-50) within the Los Alamos National Laboratory (LANL). The initial structure was built in 1963. Over the ensuing years, the building has been modified and several additions have been constructed. In 1966, laboratories, ion exchange and pretreatment functions were added. The decontamination and decommissioning activities and ventilation equipment were added in 1984. The existing facility occupies approximately 47,500 square feet on three levels; basement, first floor, and penthouse. The RLWTP treats the radioactive liquid generated at the LANL, by concentrating and removing contaminants from the liquid stream. The RLWTP is operated by the Waste Management Group (EM-7). The Waste Management Group also operates the decontamination and decommissioning (D&D) activities within the facility. The analytical laboratory, which is operated by the Environmental Chemistry Group (EM-9), occupies a portion of the building. Maintenance and engineering support personnel also work in and around the facility. The refurbished facility will provide for space and equipment for these functions. Additional space will be provided for a new entry lobby, change rooms, analytical chemistry laboratory, mechanical equipment space, storage tanks, warehousing, and truck airlock.

The following assumptions are the basic parameters considered in the development of a design concept to refurbish the RLWTP :

- Allow continued operation of the during retrofit construction.
- Design the necessary expansion within the site constraints.
- Satisfy National Pollutant Discharge Elimination System (NPDES) and National Emission Standards for Hazardous Air Pollutants (NESHAPS) permit conditions and other environmental regulations.
- Comply with present DOE Orders and building code requirements.

The refurbishment concept is a phased demolition and construction process. Initial activities include remediation of SWMU sites, demolition and decontamination of existing process equipment; extensive site work to accommodate new storage tanks, the cold warehouse and roadways. Initial construction will include mechanical and electrical facilities which will be in place and operating to allow demolition of existing equipment in the building. A portion of the storage tankage will be in place and operating to allow for continuous operation of the facility. Final activities include construction of the analytical chemistry laboratories, entry lobby, change room additions, and warehouses.

There is high risk associated with refurbishing the existing plant due to the required phased construction approach, the extent of contamination from leaking tanks and pipes is unknown, environmental remediation work will be required before and during construction, and construction activities will occur concurrent with operations activities. A comparison matrix is included in Section X, Supporting Information, which compares refurbishing the existing plant to constructing a new facility. It also identifies the impact and risks associated with a number of functions common to both options.

A Risk and Contingency Analysis was prepared in an effort to allow for cost impacts resulting from such a high risk construction project. However, the cost and schedule impacts associated with such a complicated retrofit project cannot be fully determined. Therefore, the potential for repeated interruption or even complete loss of liquid treatment services to waste generators as well as significant cost overages and schedule slippage is a strong possibility.

An overall schedule was also developed for the refurbishment project. The schedule includes the new pretreatment plant as some of the decontamination and remediation activities cannot begin until the new pretreatment plant begins operations. The schedule shows that refurbishment construction activities would not begin until February, 2000 and would not conclude until October, 2007. The refurbished plant would be fully operational by March, 2009. A copy of the schedule is included in Section X, Supporting Information.

The cost to refurbish the existing process plant, including refurbishment of existing office space, remediation of SWMU's, site work, construction of new storage tank areas, chemistry laboratories, warehouses, vehicle airlock/truck D&D area, change rooms and lobby, mechanical/HVAC and electrical is estimated to cost \$175,009,168.

Due to the high risk, the high cost, and the extremely long schedule, refurbishment of the existing Radioactive Liquid Waste Treatment Plant is not considered a viable project.

II. OBJECTIVE

The objectives for a project to refurbish the existing Radioactive Liquid Waste Treatment Plant are identical to those as stated in the Mission Need Statement (MNS) for a new Radioactive Liquid Waste Treatment Facility. A copy of the MNS for the new facility is included in Section XI, Supporting Information.

The objective of this engineering study is to determine the feasibility of refurbishing the existing plant using the same assumptions and project objectives used in the development of the replacement facility.

III. ENVIRONMENT, SAFETY, AND HEALTH

A. Environmental Considerations

The project design will include those measures necessary to ensure compliance with Executive Order 12088, the National Environmental Policy Act (NEPA), current DOE policies, and State of New Mexico environment regulations.

Ten Solid Waste Management Units (SWMU's), containing 26 potential SWMU subunits have been identified within the facilities at TA-50. SWMU's associated with and/or located in areas which may be locations for proposed buildings or structures have also been identified.

The facility will be designed to preclude emitting toxic, hazardous, or polluting waterborne effluents or airborne emissions above environmentally permissible concentrations during normal operation.

Since this is a refurbishment of an existing facility, a survey of historical sites or a survey of endangered species will not be required.

RLWTP construction activities will be planned to minimize negative environmental effects on air and water quality and on land use. Site grading and paving for the new facility will include standard erosion prevention features. Construction activities will involve routine and nominal environmental disturbance of a temporary nature.

There are no known or identified potential conflicts with county, state, or regional plans and programs.

The refurbished will reuse its current sanitary sewer waste lines.

B. Safety and Health Considerations

1. Safety Analysis

A draft Preliminary Safety Analysis Report (PSAR) has been prepared by LANL and H&R Technical Associates dated January 1993.

2. Building Occupancy/Type

The new facility will be designed to meet the requirements of UBC occupancy classification B-2 and construction Type I-FR.

3. Fire Protection

The likelihood of fire at the proposed RLWTP is that associated with a liquid waste treatment plant. An automatic fire alarm and suppression system (wet pipe automatic sprinklers) will be included in the design. Fire extinguishers will be located in conformance with NFPA codes.

4. Identification and Impact of Potential Hazards

The operating group will supply a list of chemicals and chemical processes involved in the process area and in the analytical chemistry support areas. Potential exposures will be identified and controlled through design of the building and operating systems.

The concentration of the radioactive liquid waste processed in the facility is in the low-level category. An accident scenario would be an earthquake, tank breached containment breached, and wall and floor breached before liquid escapes the building. Higher radioactive concentrations are associated with the process sludge. This sludge is not easily dispersed and will be handled away from any energy sources. The isolation, handling, and containment of radioactive materials will be included in the facility and process design.

IV. SECURITY

The refurbished facility will provide industrial type security. This security level will include fences and heavy duty hardware. A central entry and control point will be provided in the refurbished design.

Construction activities and general access to the RLWTP can be done by uncleared personnel. Site training will be required of all persons working at the building.

V. CURRENT OPERATION

A. The Radioactive Liquid Waste Treatment Plant at TA-50 currently consists of the following operations:

1. Radioactive liquid waste operations.
2. Pretreatment of acid and caustic wastes.
3. Analytical chemistry laboratories.
4. Decommissioning and decontamination operations.
5. Technical support.

B. Treatment Process

The liquid wastes received at the Radioactive Liquid Waste Treatment Plant are processed in a batch mode in quantities that provide processing approximately four hours per day at an average rate of 125 gallons per minute. The wastewater is first treated with iron and lime in order to remove the bulk of the heavy metals present, including radioactive species. Subsequent to flocculation, the precipitants are dewatered with a vacuum filter. The dewatered sludge is then packed in lined drums and transported to an on-site radioactive waste storage area.

After initial treatment with chemical flocculation/precipitation, the wastestream is gravity filtered through anthracite/sand filtration beds to remove any remaining suspended particles. The treated wastewater then flows to storage tanks where the gross alpha particle concentration is monitored. The stored liquid is discharged to Effluent Canyon via NPDES permitted outfall #051, or recycled for further treatment depending on the radioactive level.

The process train contains two unit operations that are not routinely used in normal processing. These are (1) an ion exchange operation consisting of two strong cation units and two weak cation units, and (2) a vertical wiped film evaporator. The ion exchange units are designed to remove positively charged metal ions such as plutonium, americium, cesium and strontium and have the capability of being regenerated.

The wiped film evaporator is designed to reduce the volume of regenerate fluids or waste effluent from a pretreatment process that handles TA-55 plutonium wastewater. The wiped film evaporator is designed to operate with a direct gas-fired boiler.

The individual components of the current main treatment process consists of the following equipment:

1. Holding tanks.
2. pH adjustment tank (Room 116) replacing the function of the grit chamber.
3. Caustic storage tanks (Room 116).
4. Ion exchange columns, four (Room 60B).
5. Primary filters, two (Room 72A).
6. Polishing filter (Room 61).
7. Acid dilution tank (Room 16).
8. Wiped film evaporator (Room 71).
9. Evaporator heater (Room 72).
10. Evaporator feed tank (Room 70).
11. Flash mixers (Room 116).
12. Dry chemical feeders, five (Room 116).
13. Clariflocculators, two (Room 116).
14. Gravity filter (Room 116).
15. Rotary drum vacuum filter (Room 116B).

C. Pretreatment Process

Influent tank (Room 61).

Flash mixer (Room 60).

Proportioning pump (Room 60).

Clarifier (Room 60).

Filter unit (Room 60).

Effluent tank (Room 60).

Sludge tank (Rooms 60 and 60A).

Drum tumbler (Room 60A).

Metering tank (Room 60A).

Decant tank (Room 61).

D. Holding Tanks

Six underground concrete holding tanks are located south of the treatment building at TA-50-2. These tanks hold raw influent, sludge from clariflocculators, treated wastewater, and D&D liquid wastes. This structure also contains a "pump alley" with equipment that serves the storage tanks.

The underground, concrete vault (TA-50-66) contains two 2,600 gallon tanks (TA-50-67, TA-50-68) which hold untreated acid and caustic waste from TA-55. These tanks feed the pre-treatment equipment in Rooms 60 and 60A.

A 4,000 gallon stainless steel tank (TA-50-5) is situated on concrete saddles on the north side of TA-50-1. This tank currently holds nitric acid.

A 100,000 gallon above ground steel tank (TA-50-90) holds influent radioactive waste. This tank is to be replaced by four smaller tanks under a separate project. This study anticipates the new tanks will be in place before refurbishment of the RLWTP is implemented.

E. Current Space Allocations and Personnel Numbers

Building TA-50-1 is a three level, 47,500 sq. ft. building which currently houses a radioactive wastewater treatment process, decontamination and decommissioning section, laboratories, administrative (technical) support personnel and EM-9 (Environmental Chemistry) personnel. A description of the current space allocations and personnel numbers follows.

F. Analytical Chemistry Laboratories

The October 26, 1989 space audit listed a total of 9,560 sq. ft. as laboratory space, of that total 6,520 sq. ft. allocated to EM-9. The remaining space is attributed to common areas.

An estimated 23-33 persons staff the laboratories, process plant, and decontamination areas. Up to five persons are assigned to research and development at TA-50-1.

The Environmental Chemistry Group (EM-9) currently operates analytical laboratories in TA-50-1, Rooms 34, 124, 130, and 131. This group also operates laboratories in Rooms 1, 10, 11, 123, and 123A.

G. Decommissioning and Decontamination (D&D)

The D&D unit conducts its operations within TA-50-1 in Rooms 34B, 35, 36, 38, 41, and 49. The unit cleans and processes vehicles and equipment for safe reuse.

H. Technical Support

The existing technical support operation consists of general office facilities. Included are section offices with section leader and deputy leader areas. Staff offices, technical support offices, training/conference and library room, support area for the Local Area Network (LAN), secretarial support, receptionist, and photocopier areas are provided.

Space on the basement and ground floor is allocated to technical support functions. A space audit, conducted by ICF Kaiser Engineers showed an approximate total of 6,574 sq. ft. designated for technical support use. This includes EM-9 group space (380 sq. ft.), library (336 sq. ft.), shipping room (281 sq. ft.), lunch room (381 sq. ft.), change rooms (666 sq. ft.), computer space (342 sq. ft.), and an exercise room (343 sq. ft.). The remaining space is attributed to common areas and general office space. An estimated 23-33 people are involved in technical support activities at TA-50-1.

I. Process Area

The radioactive wastewater treatment process occupies an estimated 15,860 sq. ft. This area also includes some shop/maintenance area, and a vehicle decontamination area (1,920 sq. ft.).

Personnel operating the process plant laboratories and decontamination area fluctuate between 20-25 in number.

J. Shop and Maintenance

The October 26, 1989 space audit detailed 1,640 sq. ft. as mechanical space. Other shops/maintenance areas exist within the general process plant area and are included in the estimate of that area. Two to four people are assigned to the shops/maintenance areas.

K. Other

Approximately 1,067 sq. ft. of space in the penthouse of TA-50-1 is currently utilized as a chemical storage area. An additional 650 sq. ft. on the ground floor provides a miscellaneous use area and 411 sq. ft. if utilized as a storage area.

A 6 ton liquid CO₂ dewar unit (TA-50-42) is located on the north side of project building. This unit supplies CO₂ gas to the waste stream.

VI. FACILITY DEFICIENCIES

Many of the requirements of DOE Order 6430.1A, "General Design Criteria" especially division 1323 for Radioactive Liquid Waste Facilities cannot be met at the existing facility. Design requirements not being met include: Zoned ventilation, inspectable storage and treatment tanks, classification of waste tanks, real time instrumentation and monitoring, safety class stack monitors, primary radiation control and confinement and secondary containment of waste lines.

A. Process

The existing process and process equipment is in various stages of its useful life. The grit chamber has been taken out of service due to leakage and the influent is being redirected into a new neutralization tank. The concrete clariflocculator tanks are part of the original equipment and appear to be leaking. These tanks sit directly on the slab with no means of inspection below the tanks. The existing piping system throughout the process area are original installations. Some of the piping is single wall construction and is not inspectable. Containment of a leak may be difficult, if not impossible, to accomplish. The underground storage tanks (TA-50-2) are original single containment concrete tanks. There is major concern associated with the leak integrity of these 30 year old, unmonitored tanks and their piping. Leaks have been detected from tanks of similar construction and age. The instrumentation and controls serving the system consist of original equipment and replacement items installed over the years. The waste stream processing, as it currently exists, will not meet future requirements.

B. Civil

The existing site consists of a two level topography. All of the site is usable, currently all of the flat ground is fully utilized. The areas to the north and southwest of TA-50-1 are sloping but usable after considerable "cut" of the existing slope. Stormwater runoff appears not to be a problem at this time, however, no ponding or retention of runoff is currently provided. Parking and truck access around this facility are limited. Further expansion of the facility will eliminate parking and general accessibility around the building.

C. Structural

The structure at TA-50-1 does not meet current seismic building code requirements. It is a reinforced concrete frame structure, irregular in plane, with reinforced masonry walls. The structure is not detailed for ductile type behavior and does not conform to current building codes, standards, and criteria as required by DOE Order 6430.1A, "General Design Criteria". The pre-engineered additions attached to the original structure do not meet DOE Order 6430.1A. Removal of these structures will be required.

D. Architectural

The architectural features of Building TA-50-1 exhibit a complex mix of uses, some of which create inappropriate relationships of activities. The required air locks separating "cold" and "hot" areas do not exist. Open windows in areas requiring containment of air and protection from projectiles exist. General circulation within the space is random and is not isolated by air lock and change rooms.

The security and control of entry is lacking in coverage and occurrence. The building is insufficiently insulated, the walls have no insulation and the original drawings show approximately 4" of rigid insulation on the roof. The architectural finishes have been replaced over time, nevertheless, the ceiling, carpet, walls, etc., are showing wear and age.

E. Mechanical

The existing building's mechanical system was not designed and is not functioning in accordance with current health and safety requirements for heating, ventilation, and air conditioning (HVAC) standards as set forth by the Los Alamos National Laboratory engineering design standards, DOE Order 6430.1A "General Design Criteria", Uniform Mechanical Code, and Uniform Plumbing Code for non-reactor nuclear facility.

The mechanical room is approximately 1640 sq. ft. This room houses supply air systems, building exhaust system (combining zone one and zone two exhaust), natural gas fired boilers and associate pumping systems. The natural gas fired boilers within the building is a major violation of safety issues identified in DOE 6430.1A.

The current facility does not have adequate space for renovation of the mechanical system.

F. Electrical

The existing electrical system suffers from problems centered around its age and NFPA code violations. The major electrical components are the products of several manufacturers making replacement of parts and maintenance difficult. The electrical switchgear installed when the facility was constructed have exceeded their useful life by ten years; the original manufacturer no longer makes replacement parts. Physical space within panelboards and Motor Control Centers (MCC's) preclude any additional circuits being added.

National Fire Protection Association (NFPA) code violations are evident. Several of the MCC's and panelboards have restricted frontal access and vertical clearance which violate current codes.

VII. DESIGN CONCEPT

A. General Description

The design concepts outlined in this study incorporate the current standards set forth by the Occupational Safety and Health Administration (OSHA); Department of Energy General Design Criteria 6430.1A; Uniform Building Code (UBC); Uniform Plumbing Code (UPC); Uniform Mechanical Code (UMC); National Electric Code (NEC); National Fire Protection Association 70 (NFPA); American National Standards Institute (ANSI); National Electrical Safety Code (NESC); Life Safety Code; National Pollutant Discharge Elimination System (NPDES); and National Emission Standards for Hazardous Air Pollutants (NESHAPS). The design requirements stated in the LANL "Facilities Engineering and Construction Standards" shall apply.

The overall design concept for this study is based on the reuse and renovation of the existing structure and treatment process area. The design concept includes new facilities, i.e., tank storage and buildings, mechanical rooms, entry lobby and change rooms, analytical chemistry laboratory, new and replacement equipment in the process area.

The following presents an outline approach to construction and operation sequencing during the refurbishment project. The bar chart (Exhibit A, attached at Section XI, Supporting Information) presents a graphic representation of the construction sequence.

1. Remediate SWMU's within and around the project building that are affected by refurbishment or expansion of the facility.
2. Construct new influent and effluent collection system including tank storage and provisions for continuous monitoring for leakage.
3. Construct HVAC mechanical building and equipment. This work to be complete before initiating demolition of existing HVAC equipment.
4. Decontaminate and construct one-half of the treatment process equipment and associated piping.
5. Refurbish existing technical support space. Demolish structures on the site that do not meet seismic qualification.
6. Reinforce the existing structures that are to remain to meet seismic requirements.
7. Construct building super structure which will contain the new HVAC fans filters and ductwork. Construct the building portions that will contain the laboratory, entry, and change room.
8. Decontaminate and construct the remaining one-half of the treatment process equipment and associated piping.

9. Construct the warehouse areas and the vehicle air lock.
10. Apply architectural finishes in all areas.
11. Test for operational readiness.

B. Treatment Process

The RLW process at TA-50 receives and treats radioactive liquid waste from throughout the Los Alamos National Laboratory site. Included in this waste is the effluent from the TA-55 pre-treatment plant. The existing TA-50 process plant receives rad waste and treats it through a mixer/settler process from which clarified effluent is discharged through NPDES outfall 051. Precipitated sludge is drummed for disposal.

New and impending regulatory requirements, Table B, attached at Section XI, Supporting Information, are such that this scheme is no longer adequate. The process scheme described below is designed to build upon the current process through added evaporation and ion exchange unit operations. Flow Diagram 8 illustrates the process in block flow format. The process and equipment selection has been chosen so as to take advantage of existing facilities and equipment where possible and to allow conversion from existing to new operations without requiring alteration of LANL's normal operation.

The design basis for the refurbished is 20 gallons per minute of influent, equalization through influent storage, seven days per week continuous operation, contaminant removal, and a 9 day quarantine period for effluent quality determination prior to discharge. Twenty gallons per minute is adequate to handle the volume of waste water based on the production of August 1991, the month of most waste water generation in that year, and a 90 percent on stream factor. It does not include any allowance for growth. Continuous 24 hour operation is required because of the nature of the process operations selected, especially evaporation, and due to the limited space within the existing facility which dictated the physical size of the process equipment. Quarantine of the effluent for 9 days provides the necessary time of analysis for Strontium 90.

This plant will be operated and controlled by a distributed computer control system. Automatic flow proportional samplers will sample influent, product, and intermediate process streams. The plant flexibility will be such that if a tank of effluent should fail to meet the effluent standards, the entire 9 days of storage can be recycled while the problem is solved.

Solid waste consisting of mixer/settler sludge and evaporator concentrate will be mixed with the appropriate solidification agent to form cemented solids for disposal. Provisions for both TRU waste from sludge and non TRU waste from evaporation concentrate will be provided.

As a pretreatment step, this plant will provide a mild oxidation for destroying the dispersion or chelating characteristics of any organic constituents of the influent waste water. For purposes of this study, the oxidation step is assumed adequate for its purpose without having been actually demonstrated in this service. Likewise the consequence of potentially precipitating organics for subsequent inclusion in concrete blocks forming mixed waste, has not been evaluated.

Redundant equipment will be provided where appropriate. Additionally, pumps that are in the primary process flow scheme will be provided on line spares. This study is based on the current LANL operations. No provision for growth or changes in influent waste characterization from new additional lab operations have been included.

The plant will be equipped with process vent gas collection and treatment capability. The extent of treatment will depend upon the production of off gas, especially in the oxidation step. No gas production has been assumed for this study based on the mild oxidant chosen.

1. Process Description

The following process description refers to the process flow diagram drawings 6 and 7 of Section X. Waste from the LANL Rad Waste drain system and effluent from the TA-55 pretreatment plant are received in TK-1, a 13,000 gallon tank. The pH in the receiving tank will be adjusted to fall between 7.5 and 8. Both acidic and caustic wastestream are possible. Both acid and caustic addition will be provided for pH control purposes. This pH is compatible with mild steel construction in the tank farm and is optimum for the oxidation step. From here the waste will be pumped to one of four 75,000 gallon equalization and holding tanks, TK-5 through TK-8. From storage, the waste will be pumped to one of three 75,000 gallon feed and conditioner tanks, TK-2 through 4. Tanks TK-2 through TK-4 are operated sequentially with one being filled, one being conditioned with mild oxidation of chelating agents, and the third acting as a feed tank to the on going process.

A dry oxidant will be added in the feed conditioning tanks to destroy chelating agents and thus free up heavy radioactive containments so that they may be removed from solution in a subsequent precipitation step. For purposes of this study, the dry oxidant to be used is assumed to be Oxone^R monopersulfate compound manufactured by DuPont. No actual test to verify this choice has been made. Oxone^R is a triple salt, the active component of which is potassium monopersulfate. As of 1987 the USDOT did not classify the material as hazardous; however, it is slightly unstable and slowly decomposes exothermally with the evolution of oxygen. Therefore, care will be required in handling and storage. Oxone^R is sold in 55 pound moisture proof bags and cannot be stored in compact units of greater size than a 4 foot cube. The quantity of Oxone^R required has not been determined but for illustration purposes, at an addition rate of 0.1 percent by weight, a 9 day supply could be stored in a compact unit.

From the feed conditioning tank the waste will be pumped to the flash mix tanks where lime, iron sulfate, and any required flocculating agents are added. From the mix tanks the waste will flow to the mixer settlers, MS-1A and MS-1B, where the waste stream is clarified by gravity settling of the flocculated solids. The clarified liquid is collected in TK-25 from where it will be pumped through filter FIL-1A and B. FIL-1A and B are cross flow sintered metal filters which will remove the bulk of any solids entrained in the clarified liquid. Solids collected on the filter will be removed by a continuous scouring cross flow of a portion of the feed.

These solids will be recycled to the mixer settler system. The filtrate will be placed in interim storage tanks, TK-9 through TK-11.

From the interim storage the waste will be pumped to one of two 3 effect evaporators where 90 percent of the water will be evaporated. Energy for evaporation will be supplied by 80 psig steam. Vapor from the third effect will be used to preheat the feed. A steam jet thermo-recompressor will incorporate the excess vapor from the third evaporation effect. Thermo-recompression of the product vapor stream will minimize energy costs. Thermo-recompression essentially increases the efficiency of the three effect evaporator to that of a four effect evaporator by eliminating this component, a decrease "the energy efficiency occurs. However, because this technique mixes primary steam with product vapor, primary condensate cannot be recycled to the boiler. Thus a trade off between energy and boiler feed water costs exists. This trade off has not been evaluated.

The distilled water condensate from the evaporator is collected in TK-21 and TK-22, the ion exchange feed tanks.

Organic compounds collected in the condensate will be removed by activated carbon absorption prior to the condensate being treated by ion exchange. The condensate is processed through a mixed bed ion exchange, IX, column where any residual containments will be removed. Redundant columns are provided so that one may be taken off line for regeneration while the other is on line. After ion exchange, the effluent product will pass through a cartridge type filter, FIL-2A and 2B, where any fines which may have escaped the ion exchange beds will be captured. Other types of filters, especially mixed media filters, need to be evaluated prior to final process selection.

Following filtration the effluent is stored in effluent holding tanks, TK-15 through TK-20. Each tank will collect two days of effluent product which will be held for nine days pending Laboratory confirmation of meeting discharge specifications. The cycle of tank operations of fill, test, and empty is illustrated in Exhibit C.

Off specification product will be recycled to tanks TK-12 through TK-14. During processing of recycled product the will process 15 gpm of recycle and 10 gpm of fresh feed. Excess waste influent will collect in the equalization tanks during this period.

Sludge from the bottom of the mixer/settler will be pumped to the gravity thickener TH-1. Additional clarified water from the thickener will be added to the filter feed tank. Thickened sludge will be transferred to the cementing facility where it will be mixed with the appropriate solidification mixture for forming cement blocks as a permanent waste form. Alternately, the cement may be solidified in plastic lined drums for disposal.

Concentrate from the evaporator, EV-1, will be transferred to concentrator EV-2 where additional water will be removed to produce a product with the maximum total solids suspended and dissolved, allowable for disposal as cement. This concentrator will be a wiped film evaporator.

The current operation procedures approximately 300 drums of sludge per year. Converting this to cement will result in an increase in volume by the addition of 100 to 200 pounds of the pozzolan mixture per drum. Based on a total suspended solids content of 6000 gpm for classified waste fed to the evaporator unit, another 1000 to 1500 drums per year of cementation solids may be expected. A more accurate estimate of these quantities requires a treatability study and confirmation of disposal specifications.

From Table C, attached at Section XI, Supporting Information, the required average decontamination factor, DF, of the facility is expected to be three to four 9's, or 0.9999 removed. However, based on maximum plutonium and americium influent of 330 and 630 nano ci/l respectively, the must be capable of producing 0.99999 fraction removed. This facility should produce two nines in the mixer settler, two nines in the evaporator, and the final 9 in the ion exchange column. Actually, better performance than this is anticipated based on current performance with clarification only, and the ion exchange unit is available to assure compliance during off spec operation.

2. Process Transition

One of the requirements of refurbishing the RLWTP at TA-50 is that it continue to serve LANL during construction and installation of equipment. The following installation scheme was devised to allow continuous operation with down time limited in duration to that which may be accommodated with equalization storage.

Figure D, attached at Section XI, Supporting Information, contains a matrix of activities versus operating units during the several transition phases. Note that this figure does not account for the facility upgrade itself but is limited to the change out of process and storage units. This scheme assumes that the 13,000 gallon receiving tank TK-1 and the three 25,000 gallon storage tanks, TK-2 through TK-4, have previously been installed in a prior project and may be treated as existing for purposes of this discussion.

The initial phase in the transition will be the construction of the four equalization tanks TK-5 through TK-8 and interim storage tanks TK-9, TK-10, and TK-11. During this construction the plant will continue to run in its current configuration.

The next phase will be the construction of those facilities which will be outside the main process building. Included in this phase will be the new process boiler and chilled water units. Construction of the effluent holding tanks TK-15 through TK-20 and recycle tanks TK-12 through TK-14 will begin.

The third phase will include removal of existing equipment not now being used and not scheduled for use in the refurbished process and the installation of the evaporator and concentrator and non-TRU cementing units. During this period the plant will operate in its existing configuration with the new equalization tanks in service. The three 25,000 gallon tanks, TK-2 through TK-4 will be by-passed to allow their conversion to oxidation reactors. This will require the installation of the oxidant addition equipment and valving to provide for rotating the three tanks through the 3 modes of operation; fill, oxidize, and empty. In order to accomplish this, the construction activities will be scheduled so that plant down time for removal or installation of equipment is limited to no more than one week. During this week, the influent waste water will be stored using the four equalization tanks, TK-5 through TK-8. Following periods of shutdown for construction, operation of the plant using two shifts will be required to "catch up" with the stored liquid waste. The large storage tanks begun earlier will be connected.

The next phase will consist of installing the ion exchange unit and converting the existing ion columns into feed tanks TK-21 and TK-22, regeneration system, and product filter. During this phase the existing clarifiers will be in operation along with the evaporator, concentrator and non-TRU cementing unit. The condensate discharge from the evaporators will be stored in the effluent holding tanks and discharged to NPDES outfall #051. During this period, the sludge thickener TH-11 and TRU cementing unit will be constructed and commissioned for operation.

The final phase of the transition will include the replacement of the existing clarifiers with new clarifiers. During this phase, one of the clarifiers will be left in service while the other is decontaminated and removed and the new one installed. At this time, operation of the plant will be on a 24 hour basis so that one of the existing clarifiers will be able to handle the total throughput. After the first replacement clarifier is in service, the second clarifier will be replaced in a similar manner. At the completion of the clarifier replacement, the process transition will be complete, the automatic samplers will be in place, and operation on a continuous basis with quarantine of effluent pending lab certification of discharge quality will begin.

Early in the refurbishing project the new control system will be put in place so it can be utilized as new equipment is placed in service. Additionally, it may be necessary at times during various transition phases to install temporary piping and pumps while permanent locations and systems are constructed.

C. Environmental

1. Solid Waste Management Units (SWMUs)

Ten SWMUs, containing 26 potential SWMU subunits, have been identified as a part of the treatment facilities at TA-50. SWMUs located in the Radioactive Liquid Waste Treatment Plant (Building 1) are discussed below. In addition, SWMUs associated with and/or located in areas which may impact proposed additions to Building 1 are also identified and discussed in this section accordingly. A map shown as General Location of SWMUs is attached at Section XI, Supporting Information.

2. Radioactive Liquid Waste Treatment

SWMUs 50-001(a) is a radioactive liquid waste treatment plant that covers 15,860 square feet of a total 47,500 square feet in Building 1. This SWMU consists of a wiped film evaporator located in Room 71, two clariflocculators located in Room 116, a pH adjustment tank located in Room 16, an evaporator storage tank located in Room 70A, a decant storage tank located in Room 61, a rotary drum vacuum filter located in Room 116B, two gravity filtration devices located in Room 116, a 100,000 gal. steel emergency holding tank designated as structure TA-50-90, and two waste mixers located in Room 116.

SWMU 50-001(b) is the underground waste line system through which liquid waste is transferred to the RLWTP from many of the active technical areas. Manhole TA-50-72 is the central collection area for most of the industrial liquid waste that is treated at the treatment .

SWMU 50-003(a) is a greater-than-90-day storage area located in Room 60D in the northeast corner of the east wing of Building 1.

SWMU 50-003(b) is a storage cabinet in Room 130 of Building 1. There is no known source of contaminant release associated with this SWMU; consequently, no further action has been recommended for this SWMU.

3. Proposed Addition 1 - Aboveground Holding Tanks Located on the North End of Building 1

SWMU 50-002(d) is an aboveground 4000-gal. stainless steel nitric acid storage tank designated as Structure TA-50-5. It is located adjacent to the north wall of Room 60D of Building 1. The proposed holding tank addition would be situated in the vicinity of SWMU 50-002(d).

4. Proposed Addition 2 - Change Room and Lobby

SWMU 50-001(b) - The proposed change room and lobby addition would be situated above a branch of SWMU 50-001(b). As discussed in a previous section, 50-001(b) is the underground waste line system through which waste is transferred to the RLWTP from many of the active technical areas. This branch is networked to Manhole TA-50-72 which is a central collection point for the radioactive waste line system.

5. Proposed Addition 3 - Analytical Laboratory

SWMU 50-001(b) - The proposed analytical laboratory would be situated above three branches of SWMU 50-001(b), the underground waste line system through which waste is transferred to the RLWTP. The three branches are networked to Manhole TA-50-7 which is located north of Structure TA-50-77.

SWMU 50-002(b) and 50-002(c) are underground tanks which hold acid and caustic wastes, respectively. The tanks are contained in a vault (Structure TA-50-66) approximately 18 ft x 16 ft x 14 ft. The west wall of the proposed analytical laboratory would be located beyond or very close to the east wall of the underground vault.

SWMU 50-004(b) was an underground vault (Structure TA-50-3) that contained three stainless-steel lined concrete tanks used to store waste from the Omega West Reactor and other sources. These tanks were removed in 1989. Soil adjacent to the outside walls of the vault was removed and the entire structure, with the tanks inside, was transported to Area G for disposal. The soil around and underneath the vault was screened for radioactive and chemical constituents and found to be below cleanup levels. The excavation was then backfilled with clean soil. The west wall of the proposed analytical laboratory would be located beyond or very close to the eastern extent of this SWMU.

SWMU 50-011(b) is an active septic system that was installed in 1983. Effluent lines exit from the southwest and northwest corners of Building 1 and drain to lift stations. The proposed analytical laboratory addition would be situated above the southwest lateral drainline that is networked to the south lift station for this system.

6. Proposed Addition 4 - Vehicle Airlock

SWMU 50-001(b) - The proposed vehicle airlock addition would be situated above several branches of SWMU 50-001(b), the underground drainline system that manages the transfer of waste to the RLWTP. The branches are networked to the Building 2 tank farm. Liquid waste and sludge is then transferred from Building 1 to Building 2 via a system of 17 drainlines.

SWMU 50-003(c) consists of two temporary storage areas (less-than-90-day). One of the storage areas is of concern with regards to the proposed vehicle airlock addition. This storage area is located between the north wall of the Vehicle Decontamination Facility and the south wall of the east wing of Building 1 (which is a asphalted area). Mixed wastes generated from several technical areas is temporarily stored in this storage area until the waste is processed in Building 1. There have been no documented contaminant releases from this storage area; consequently, a no further action recommendation has been made for this 50-003(c) subunit. The proposed vehicle airlock addition would be situated in require the area that is occupied currently by this subunit.

SWMU 50-003(d) consists of two greater-than-90-day storage areas, primarily acidic waste generated at the ICON Facility. One of the two storage areas is of concern with regards to the proposed vehicle airlock addition. This storage area is in a canvas building (approximately 12 ft wide x 14 ft deep) located against the south wall of the east wing of Building 1 (which is a asphalted area). There have been no documented contaminant releases from this storage area; consequently, a no further action recommendation has been made for this 50-003(d) subunit. The proposed vehicle airlock addition would be situated in the area that is occupied currently by this subunit.

7. Proposed Addition 5 - Hot Warehouse

SWMU 50-001(b) - The proposed hot warehouse would be situated above several branches of SWMU 50-001(b), the underground waste line system which transfers waste to the radioactive treatment plant. The branches are networked to the Building 2 tank farm.

SWMU 50-003(c) - This is the same SWMU subunit described under Proposed Addition 4. The west wall of the proposed hot warehouse addition would be situated in the immediate vicinity of the eastern extent of this subunit.

SWMU 50-003(d) - This is the same SWMU subunit described under Proposed Addition 4. The north portion of the west wall of the proposed hot warehouse addition would be situated in the vicinity of this subunit. SWMU 50-003(d) is located immediately west of the SWMU 50-003(c) subunit discussed above.

8. Proposed Addition 6 - Cold Warehouse

SWMU 50-002(a) is an underground vault containing an equipment room bounded on three sides by five concrete process tanks: two 25,000-gal tanks on the east, one 25,000-gal. tank and one 75,000-gal. tank on the west, and one 25,000-gal.tank on the south. Two of the tanks handle the influent or raw waste, one is for sludge, and the other two are for storing treated liquid waste prior to discharge. Liquid waste and sludge is then transferred from TA-50-1 to TA-50-2 via a system of 17 drainlines. The proposed cold warehouse facility would be situated immediately southeast of SWMU 50-002(a).

SWMU 50-011(a) is the original (now removed) septic system that was installed about 1964 at the south end of Building 1 and the existing tank farm. The entire system, with the exception of the section of pipe line between the septic tank the leach field, was removed in 1983. Currently, the leach field and a section of the effluent line between the septic tank and the field are the only portions of the old system that remain. The proposed cold warehouse facility would be situated above the eastern portion of the leach field.

9. Proposed Addition 7 - Aboveground Holding Tanks Located on South End of Building 1

There are no SWMUS located in the area of this addition that might impact the construction of this addition.

10. Proposed Addition 8 - Mechanical Building

There are no SWMUs located in the area of this addition that might impact the construction of this addition.

11. Proposed Addition 9 - Emergency Generator

There are no SWMUs located in the area of this addition that might impact the construction of this addition.

12. Proposed Addition 10 - Cooling Tower

There are no SWMUs located in the area of this addition that might impact the construction of this addition.

13. Liquid Effluents

The 1991 DOE Tiger Team Assessment (DOE-EH-0204) identified a number of deficiencies at the Radioactive Liquid Waste Treatment Plant with regards to compliance with DOE Regulations and RCRA Part B Permits Hazardous and Solid Waste Amendments (HSWA Module) requirements promulgated by the EPA. One deficiency is in reference to the latter RCRA Part B Permit requirements. This deficiency is in regards to the sediments traps in Effluent Canyon. The Radioactive Liquid Waste Treatment Plant has one NPDES permitted outfall (Outfall 051) that discharges to Effluent Canyon. Sediment is transported by the effluent from this outfall and by rain events to three sediment traps which are designed to contain approximately 29 acre/feet of sediment. According to the 1991 Tiger Team Assessment, these sediment traps are not monitored, maintained, and controlled to minimize the spread of contamination. A second deficiency is in reference to DOE 5400.5. This deficiency is with regards to the lack of a BAT analysis for the treatment facility. DOE 5400.5 requires that a BAT analysis be performed when liquid waste discharged to surface waters contains radionuclides greater than specified concentration guide values. A review

of discharge records indicates that radiologically contaminated liquid effluents to Effluent Canyon are, on an average annual basis, above concentration guide values, therefore requiring a BAT analysis.

In addition, the 1991 LANL Self Assessment Report states that "There is a violation of DOE 5400.5 if it is determined that the continued discharge of effluents (from Outfall 051) to Effluent Canyon constitutes a discharge to an effective natural soil column". A final determination by the DOE concerning this issue has not yet been made.

14. Air Effluents

The 1991 DOE Tiger Team Assessment (DOE-EH-0204) identified one deficiency at the Radioactive Liquid Waste Treatment Plant with regards to compliance with DOE Regulations (i.e., DOE 5400.1 and DOE/EH-0173T) and the National Emission Standards for Hazardous Air Pollutant promulgated by the EPA. Stacks associated with Buildings 1 and 37 at TA-50 do not have real-time stack effluent monitoring equipment. Real-time stack effluent monitoring should be incorporated for facilities with the potential for exceeding a large fraction of the emission standard.

D. Utilities

1. Existing Utilities

The TA-50 site contains numerous utility runs. The following list shows utility lines and their functions. The utility lines are broken down into areas of new construction depicting lines which will have to be relocated or removed. A map showing existing utilities is attached at Section XI, Supporting Information.

a. Tank Storage Area #1 (See plans)

- 1) 2" 100# gas line and prv station
- 2) 1" 100# gas line and prv station
- 3) 6" water line
- 4) 2" water line
- 5) 6" fire water line, fire hydrant #4-717, piv #1404, fire department connection
- 6) 1-way elect. ductbank, TA-50-4 substation, and 750 kVA transformer and concrete pad
- 7) Fire alarm box #1526

b. Tank Storage Area #2

- 1) 1" 20# gas
- 2) 6" sanitary sewer and lift station with associated electrical
- 3) 4" 2-207 NE and N line
- 4) 6" 2-92 NE line
- 5) 1" CA-125 line
- 6) 12" cmp storm drain

c. Pre-Treatment

- 1) TA-50-66, 67 and 68 acid and caustic pit and process tanks
1 1/2" caustic waste line

- 1 1/2" acid waste line
- 2" spare
- 2" industrial water line
- 2) 6" sanitary sewer line
- d. Chemical Labs
 - 1) TA-50-3 acid holding tank
 - 1" acid waste line
 - 3" acid waste line
 - 2) TA-50-7, manhole
 - 3) 1 - 3"/6" P.E. line to TA-50-78, manhole
 - 4) 6" foundation drain
 - 5) 10" roof drain
 - 6) 4" drain line
 - 7) Catch basin
 - 8) 1 1/2" water line and yard hydrant
- e. HVAC Central Plant
 - 1) TA-50-72 acid waste manhole
 - 1 - 3"/6" P.E. line
 - 1 - 6"/10" P.E. line
 - 1 - 8"/12" P.E. line
 - 1 - 4" acid waste line
 - 1 - 10" main acid waste line from manhole WM-72 to TA-50-1
 - 2) 6" sanitary sewer line
 - 3) 1 1/2" water line

f. Change Rooms

- 1) Main acid waste line from manhole #72 to treatment
- 2) Air intake chase #2 (concrete)
- 3) Air intake chase #1 (concrete)

g. Lobby

- 1) 2" telephone conduit
- 2) Telephone manhole
- 3) Fire alarm box #1525, pedestal mounted

E. Civil

1. Earthwork

Earthwork will include excavation, embankments, and site-grading required for building additions, mechanical/electrical utility building, and site drainage. Preliminary geotechnical investigations indicate that all of the material to be excavated is either soil backfill or volcanic tuff. Both of these materials can be ripped and removed with commonly available earthmoving equipment.

2. Drainage

Drainage work will include surface drainage control, consisting of graded sheet flow, swales, valleys and ditches. Rip-rap, concrete, asphalt or other erosion control materials will be provided where flow will cause erosion in ditches and valleys.

3. Paving

A paved access area to the utility building will be constructed.

4. Native Grass Seeding and Landscaping

Areas disturbed during construction and susceptible to erosion will be seeded with native grasses and/or landscaped with southwestern-type landscaping.

F. Structural

1. Description of Existing Structural Systems

ICF Kaiser Engineers has reviewed the design drawings and calculations for the original, TA-50-1. The facility was designed in the early sixties by Black and Veatch Consulting Engineers, Kansas City, Missouri. The documents make reference to the 1952 Uniform Building Code as the code used for design.

The original structure (WM-1, TA-50) is "Tee-shaped" in plan and divided into three rectangular elements by expansion joints. The structure consists of three levels (basement, first level, and roof with penthouse). The basement floor slab is supported directly on earth. Basement walls are of concrete construction below grade. A reinforced concrete frame with masonry in-fill supports the roof. The reinforced concrete frame columns are supported by spread footings bearing on earth. The first floor is constructed of reinforced concrete slabs and beams. The roof is constructed of a concrete-filled steel deck on steel joists. Two large clariflocculators (20 ft. diameter by 16 ft. depth) are located at the basement level and extend to and support the first level.

The plant has been modified by numerous small additions. Generally these were constructed as three-sided addition with masonry, steel joists and concrete foundations. The vehicle decommission and decontamination area addition is a three-sided pre-engineered metal building. These type of additions to the facility will be removed as part of the refurbishment.

Vertical load is resisted by a moment resisting reinforced concrete space frame. The roof is supported by a concrete-filled steel deck on steel joists. The second level is supported by reinforced concrete slabs and beams. The basement/first level is supported directly on earth. The reinforced concrete space frame columns are supported by spread footings on earth.

No formal lateral load resisting system that will perform in a predictable manner is apparent in the structure. The design assumed that the vertical load resisting system (reinforced concrete space frame) would resist lateral load with stresses remaining below the allowable level for wind and seismic loads (33% increase in allowable stress). The analysis performed by H and R Technical Associates, Inc., showed that the building columns are overstressed by as much as 600% in some cases, when analyzed in accordance with UCRL-15910 criteria for a low hazard category facility.

The lateral force system for the structure consists of a reinforced concrete space frame that transfers forces to the foundation. The roof and floors function as horizontal diaphragms transferring forces to the concrete space frame.

2. Deficiencies

The building's structural systems are not adequately reinforced and attached to each other to transfer lateral loads to the foundation before their failure. The design calculation for the structure contain no lateral analysis of load through the structural element nor do the construction drawings indicate details for their connection (example: steel deck to steel joist to concrete beam, etc.). The building's main structural system (reinforced concrete space frame) lacks proper reinforcing details to behave in a ductile manner (continuity of longitudinal top and bottom steel in horizontal members, and adequate confinement of vertical column reinforcement).

The design calculations do not consider the interaction of the concrete frame and the masonry infill walls. The forces transmitted to the concrete frame where masonry infill walls occur can be considerably greater than forces calculated not considering the masonry infill walls.

The "Seismic Safety Guide", Lawrence Berkeley Laboratory (LBL-9143) considers this type of construction as particularly hazardous and generally requiring rehabilitation for earthquake safety.

3. Structural Design Criteria

The refurbished Radioactive Liquid Waste Treatment Plant will conform to the structural guidelines in DOE Order 6430.1A (General Design Criteria) for an Important or Low Hazard classification.

DOE Order 6430.1A specifies that general earthquake forces be determined in accordance with the procedures contained in UCRL-15910, "Design and Evaluation Guidelines for Department of Energy Facilities Subject to Natural Phenomena Hazards" and the UBC, "Uniform Building Code" with the provisions of TM5-809-10, "Seismic Design for Buildings". The detailing of structural elements shall conform to the requirements of the UBC for seismic zone 2b and to UCRL-CR-106554, "Structural Concepts and Details for Seismic Design".

Wind loads will be determined in accordance with UCRL-15910 and with methods given in ASCE 7, "Minimum Design Loads for Buildings and Other Structures". Shelter from changes in ground elevation and the height of other buildings will be disregarded.

Snow loads will be determined in accordance with ASCE 7, with no reduction in ground snow load. The snow load will include drift load, unbalanced loadings and rain-on-snow and potential ponding effects. The design ground snow load to be used for design is 30 psf.

The minimum building design live loads, and dead loads, loads will be determined in accordance with the latest edition of ASCE 7, "Minimum Design Loads for Buildings and Other Structures," and UCRL-15910 with an additional future dead load of 10 psf for all floors and roofs.

Load combinations for steel design will conform to ASCE 7. Load combinations for concrete design will conform to American Concrete Institute, ACI 318. Dynamic loading will be combined with dead load plus equipment load only. The load combinations listed in UCRL 15910 will also be considered. The most stringent requirements will govern.

4. Structural Modifications to the Existing Plant

The existing structure will be refurbished to comply with DOE Order 6430.1A for a structure classified as Important or Low Hazard. The existing nonductile concrete frame lateral force resisting system will be replaced with a ductile shear wall system. The following structural modifications will be made to incorporate the shear wall system:

- a) Redesign the existing structure to include a symmetrical shear wall (box) lateral force system.
- b) Provide adequate connection of structural elements designed to resist seismic forces.
- c) Strengthen diaphragms, reduce the tributary areas of diaphragms and/or install horizontal trusses to transfer horizontal forces.
- d) Remove (as required) existing masonry walls and replace them with reinforced concrete shear walls.
- e) Strengthen foundations at shear wall by placing transfer grade beams with drilled-in-place piers adjacent to existing foundations.

With these structural modifications, the existing moment resisting reinforced concrete space frame would resist vertical gravity loads.

Lateral load would be resisted by the shear walls transferring forces to the foundation. The roof and first floor level horizontal diaphragms would function to transfer forces to the shear walls.

5. New Construction Structural Systems

The existing RLWTP will be expanded as part of the refurbishment. The expansion will include space for a mechanical penthouse, tank farm, analytical chemistry laboratory, entry, lobby, and change room. A new cold warehouse and HVAC central plant will also be constructed. The additions to the and new buildings will be classified as an Important or Low Hazard.

The vertical load system will be steel beams supported by steel columns. The roof will be supported by a steel deck while the elevated floor will be supported by a composite concrete filled steel deck.

The ground level floor will be a concrete slab-on-grade. The foundation will be reinforced concrete spread footings and grade beams supported on welded tuff.

The steel structure lateral force system will be a braced frame system transferring forces to the foundation. The roof and floors function as horizontal diaphragms transferring forces to lateral force resisting elements.

6. Nonstructural Elements and Equipment

The Radioactive Liquid Waste Treatment Plant is classified as an Important or Low Hazard Facility (UBC essential facility). Department of Energy Order, DOE 6430.1A, requires engineered anchorage for equipment and nonstructural components in Important or Low Hazard facilities. Nonstructural elements are portions of structure not having structural function, such as suspended ceilings and computer floors. Equipment consists of mechanical, plumbing, and electrical assemblies including but not limited to items such as chimneys, stacks, machinery, boilers, heat exchangers, vessels, tanks, pumps, motors, air handling units, transformers, switchgear, control panels, emergency power equipment, piping, conduit, and ducting.

The draft SAR (Safety Analysis Report) prepared by H&R Technical Associates, Inc. identify the ventilation system, the fire suppression system, and the radiation monitoring instrumentation as safety systems.

DOE Order 6430.1A, General Design Criteria, specifies that general earthquake forces be determined in accordance with the procedures contained in the UBC, "Uniform Building Code" and UCRL-15910, "Design and Evaluation Guidelines for Department of Energy Facilities Subject To Natural Phenomena Hazards" and with the provisions of TM 5-809-10, "Seismic Design For Buildings". With the exception of safety systems the UBC and UCRL-15910 primary focus is on attachment of equipment and nonstructural elements to the structure and not that equipment and components be designed for seismic forces. The UBC and UCRL-15910 also permit, with limitations, the use of approved national standards or approval test data as a basis for the earthquake - resistant design.

G. Architectural

1. The Radioactive Liquid Waste Treatment Plant contains the process system to treat a designated waste stream. In support of this activity, the following functions are housed at RLWTP.
 - a. Process Plant
 - b. Decontamination and decommissioning
 - c. Analytical chemistry laboratory
 - d. Technical support (engineering and office support)
 - e. Maintenance
 - f. Shipping, receiving, and storage
 - g. Soil laboratory (does not directly support RLWTP)
2. The architectural aspects of this study are divided in two activity groups:
 - a. Refurbishment, demolition (see table G 1)
 - b. New construction (see table G 2)
3. Architectural refurbishment activities, for the following:
 - a. Process Plant, 1st Floor

Demolish of existing windows and window frames. Opening at windows to be filled in with concrete block. Floor and wall finishes to be cleaned of contaminants, new finishes to be applied. The process equipment will be removed and replaced or decontaminated and reused where possible.
 - b. Process Plant, Basement

Reconfigure access into this area is required to provide security from unauthorized entry. Incorporate air locks is required to provide access between "cold" and "hot" areas. Decontaminate walls, floors and equipment will be required.

c. Technical Support, Basement and 1st Floor

This area will be refurbished including replacement of the suspended ceiling, floor coverings, carpet or vinyl. Energy efficient windows and glazing will replace existing single pane steel frame windows. Circulation patterns to incorporate the proposed entry/lobby, change rooms and laboratory will be improved.

d. Decontamination and Decommissioning, Office and Laboratory Space

The D&D area refurbishment will include replacement of laboratory equipment. The flooring, ceiling and wall finishes will be replaced. Energy efficient windows will replace existing single pane windows and steel frames. Minor layout changes will be made to allow circulation to the adjacent analytical chemistry laboratory.

e. Control Room and Computer Room

This area will continue to serve its existing function. The control and computing equipment will be replaced with state of the art technology. Construction of air-locks will be required to separate "cold" and "hot" areas. Architectural finishes including the suspended ceiling, flooring and wall finishes will be replaced.

f. Soil Lab

The soil laboratory will remain in its current condition. This function does not directly support the RLWTP, therefore, is not included in the refurbishment project. Due to the replacement of HVAC equipment, this space will benefit by receiving its conditioned air from the new equipment.

4. Architectural construction, for the expanded plant areas, include the following:

a. Tank Storage

This function consists of two additions, one at the southwest corner and one at the northeast corner of the TA-50-1 Building. These buildings will be 40' high post and beam structures to provide covered facilities for 20 steel tanks. This structure will be industrial in its appearance and finishes.

b. Hot Warehouse

This warehouse space will be located adjacent to the processing plant. It will be isolated by airlock, from the clean areas. The floors will be sealed concrete and the foundation will be configured to provide containment of fluids. This structure will be industrial in its appearance. Openings in walls will be kept to a minimum to prevent air infiltration and provide control of entry and egress.

c. Cold Warehouse

The cold warehouse will be remote from the main structure. The existing structure TA-50-83 will be demolished and the proposed cold warehouse will be built in the same southeast corner of the site. This structure will be a pre-engineered structure, industrial in its appearance.

d. Entry/Lobby

This addition to the west side of the existing structure will create an entry and lobby. It will provide an entry and security monitoring station. Architecturally, the entry lobby will provide an entrance focus and provide improved circulation.

e. Change Rooms

This addition will provide a facility for use and storage of anti-c clothing. It will provide locker space, storage, showers and access to the process area, and to the analytical chemistry laboratory.

f. Analytical Chemistry Laboratory

This laboratory will provide analytical support for this facility and other testing requirements for other users within LANL. The architectural aspects of this facility will reflect the activities within, secured entry, high wall windows, glass block.

g. Truck Airlock and Vehicle Decontamination and Decommissioning

The existing vehicle D&D Building is a pre-engineered structure which does not meet seismic requirements. Demolition of this structure will be required. Due to restrictive site space, this addition will be a combined function of the vehicle D&D and truck airlock. Vehicle decontamination work will be conducted in part of the building and a vehicle airlock serving the hot warehouse will be located in part of the building. This building will be a steel post and beam facility. A portion of the HVAC penthouse will be constructed as the second floor.

h. Mechanical Penthouse

A "second floor" mechanical penthouse will be located over the existing building and on top of the new portions of the building. This space will be industrial in its appearance. The HVAC fans, filter banks and ductwork will be contained in this space. This portion of the facility will be industrial in its appearance and finish.

i. HVAC Central Plant

This will be the main mechanical equipment plant containing boilers, chillers, and major electrical equipment. This structure will be a pre-engineered building, industrial in its appearance.

Space Analysis Table G 1 - (Refurbished Space)

Process Area	18,450 sq. ft.
Tech. Support	11,600 (first floor)
Tech. Support	11,443 (basement)
D&D Area (Office/Lab)	3,699
Computer/Control Room	1,295
Soil Lab	<u>1,015</u>
	47,500 sq. ft.

Building Analysis Table G 2 - (New Construction)

Tank Storage	22,083 sq. ft.
Hot Warehouse	2,500
Cold Warehouse	4,489
Entry/Lobby	1,379
Change Rooms	3,186
Chemistry Lab	4,450
D&D Area & Truck Airlock	1,867
Mechanical Penthouse	<u>46,086</u>
	86,040 sq. ft.

This space analysis is based on the feasibility drawings contained in this study. For clarity, some activities are combined into a block of space defined by function.

H. Mechanical

1. Description of Existing Mechanical Systems.

a. HVAC

The existing Heating, Ventilation and Air Conditioning (HVAC) systems consists of forced air handling units with 100% outside air, hot water preheating, heating coils, fan coil units and perimeter finned tubed radiation. In 1989, the air-handling units were replaced and preheating coil piping modified to prevent freezing. Higher efficient filters were installed. Gas fired hot water boilers provide hot water for heating. Hot water unit heaters are used for spot heating. There are seven (7) supply air units with 86,115 cfm and eight (8) exhaust fans with 101,130 cfm. The difference is provided by infiltration (SAR 12-23-92).

Room air is exhausted through fume hoods and exhaust registers. Fume hood face velocity is adjusted for 125 fpm $\pm$ 10%. The main exhaust air is ducted to one of two fan/filter plenums in the basement. The exhaust air is filtered with 99.97% efficient type filters. The exhaust fans discharge through exhaust stacks, typical of two systems.

The Control Room is provided with a direct expansion, electric refrigeration, split system with an air handling unit and air cooled condensing unit for cooling. The Decontamination and Respiration Laundry is provided with a gas fired rooftop make-up air unit for heating and 100% outside air ventilation. Room air is exhausted through 99.97% efficient type filters by a rooftop exhaust fan and stack combination.

The process area is exhausted by a propeller fan with 99.97% efficient filters. The Chlorine room has a wall exhaust fan near the floor and is exhausted direct to atmosphere.

b. Plumbing and piping systems

1) The existing plumbing system and piping consist of the following:

Potable hot, cold, and recirculating hot water piping serve the lavatories, mop sink, water closets, urinal, shower and electric water coolers. Non-potable hot and cold water is piped to laboratory sinks and emergency showers.

Medium and high pressure natural gas piping, gas meter and pressure regulating station supply natural gas for firing hot water boilers, heating potable hot water and general lab use. This equipment and piping is located within the building.

Hot water heating supply and return piping provides heating water to air-handling units, unit heaters, radiators, etc.

Soil, waste, and vent piping are used for sanitary sewage.

Distilled water is provided by a still.

Compressed air is provided to laboratories.

Vacuum pump and piping is used to provide a vacuum system for the laboratories and air monitor systems.

Acid waste piping serves laboratory sinks and fume hoods.

Roof drains and piping transfer storm water away from building.

Deionized water and piping is used in the laboratories.

Methane, oxygen, and hydrogen bottled gas and piping are used in the laboratories.

c. Fire Protection.

Automatic wet type fire protection sprinkler system was installed in 1988. A halon fire suppression system provides fire protection for the Control Room. The building has a 16-alarm zone sprinkler system that consists of sprinkler heads set to activate at 212⁰F.

d. Energy Conservation

The energy management control system has been abandoned in place.

e. Deficiencies

The filtration requirements are not met in accordance with current LANL criteria and standards such as spark arresters, fire suppression system, demisters, two stages of testable HEPA filters (minimum). The stack velocities are 1800 FPM and 1700 FPM respectively at maximum air flow which is less than the required 3200 FPM. The building has ventilation only, therefore, room temperature can vary above comfort and laboratory standard temperatures.

Natural gas piping is routed throughout the building to labs, hot water heater, boilers, make up air units and rooftop furnaces. No backflow prevention is provided between potable water and non-potable water serving laboratory sinks.

The automatic wet type fire protection sprinkler system was not provided with supports and sway bracing for a seismic event.

The energy management control system never worked and is abandoned in place.

Each TA-50-1 stack that passes filtered exhaust is equipped with a single isokinetic sampler but requires two monitoring systems each.

2. Description of New Mechanical Systems

a. General

Compliance with the current codes, standards and DOE design criteria requires upgrading the existing HVAC, plumbing and piping systems and providing new HVAC, plumbing, and piping systems for the additional facilities. Chilled water cooling is required for the refurbished facility except for the warehouses and the HVAC central plant. The increased number of mechanical systems and equipment result in the need for a large mechanical space. A second floor mechanical room will be provided that covers most of the existing and additional spaces. The second floor will be designed for a seismic event and will be self supporting. A separated HVAC central plant building will also be provided. The following is a detailed discussion of the mechanical systems that will serve the refurbished RLWTP. Redundancy for safety is not required by low hazard classification. Stand-by equipment has been provided for ease of maintenance.

b. Demolition of Existing Systems

The following existing HVAC systems will be removed in their entirety: supply, return and exhaust ductwork; supply and return grills; hot water heating supply and return piping, finned tube radiators, exhaust stacks, exhaust plenums, and fume hoods.

Specific HVAC equipment that will be removed include the following: two hot water boilers, seven heating and ventilating units, hot water pumps, two expansion tanks, one hot water storage tank, gas fired water heater, one hot water circulator, two exhaust fans, three air compressors, three air receivers, 3 after coolers, one vacuum pump and vacuum tank, one DX air conditioning unit, four centrifugal wall exhaust fans, two unit horizontal unit heaters, two propeller exhaust fans, and one vertical unit heater.

The following piping systems, plumbing systems, and equipment will be removed: Distilled water system, potable hot and cold water system, PRV regulator, compressed air piping system, vacuum piping system, acid waste piping system, sanitary sewer piping system, roof drains and roof drain piping system, deionized water system, refrigerant liquid and suction piping.

c. HVAC

1) HVAC Central Plant

The following HVAC systems and equipment will be located in the HVAC Central Plant. Heating hot water for the refurbished RLWTP will be provided by three gas fired, tube type, hot water boilers with capacities of 40%, 60% and 60%. Chilled water will be provided by two centrifugal, electrical driven, water cooled chiller units with capacities of 75% and 75%. Auxiliary equipment that will be located in the HVAC Central Plant include: The hot water heating primary boiler circulating pumps (3), secondary hot water circulating pumps (2), chilled water primary circulating pumps (2), secondary chilled water circulating pumps (2), plate and frame heat exchangers between the chilled water and cooling tower water for free cooling, process chilled water plate and frame exchanger, three 125 psig high pressure steam boilers for process heating, with duplex feedwater water pumps and tanks. HVAC System #6 will serve the HVAC Central Plant. It will consist of rooftop exhaust fans and filtered/dampened outside air intakes thermostatically controlled for summer ventilation. A ventilation unit will provide minimum tempered outside air during the heating season. Winter heating of the building will be provided by hot water unit heaters.

The Technical Support Areas will be served by System #1 which will be a variable air volume system comprised of 30% prefilters, 40-45% final filters, preheating coils, chilled water coils, variable supply air and return air fans, variable air volume terminal units with heating coils, outside air damper, return air damper and relief air damper. Supply air and return air will be ducted to and from diffusers and return air grilles. Room air will be exhausted from toilet areas, showers, and conference rooms. An economizer cycle will also be provided.

The Process Plant Areas will be served by System #2 which will be a constant air volume system compromised of prefilters, heat recovery coils, HEPA filters, preheat coils with face and bypass dampers, chilled water coils, constant volume supply and return air fans, terminal heating coils, ducted supply and return air, diffusers, return/exhaust air grilles. System #2 will provide 6 air changes per hour of supply air which will be made up of 3 air changes per hour of outside air and 3 air changes per hour of recirculated air during normal operation. The entire return/exhaust air stream will pass through an initial HEPA filter train which will include 40-45% prefilters, spark suppression system, spark arrester screen, 99.97% nuclear grade HEPA filters and test sections. After passing through the initial HEPA filter train, the return/exhaust air stream will be equally split with 3 air changes per hour routed to the return air

inlet of the air handling unit and 3 air changes per hour routed to the zone two exhaust system. The return air stream will be pulled through a second HEPA filter-train containing 99.97% nuclear grade HEPA filters and test sections and a heat recovery coil by an exhaust fan. This stream will then be routed to the zone two stack exhaust system. During emergency operations, 100% of the air supplied to the process area will be routed to the zone two exhaust system. The stacks will be sized for 3200 fpm at 100% emergency operation.

In addition to the Zone Two general exhaust systems, a Zone One exhaust air system will also be provided for tank and process equipment for the Process Plant Areas. The Zone One exhaust will be ducted from tanks and process equipment to a HEPA filter train which will include spark arrester, spark suppression system, demister, prefilter, two stages of carbon adsorbers with test sections, two stages of the 99.97% nuclear grade, HEPA filters with test sections, variable air volume exhaust fan and exhaust stack.

The Analytical Chemistry Labs/Change Rooms will be served by System #9 which is the same as the Process Area System #2 except that no carbon adsorbers will be provided for Zone One exhaust. Zone One exhaust is for fume hoods and laboratory equipment in lieu of tanks and process equipment.

The Hot Shop Area, Decontamination and Decommissioning Areas Systems #3 are the same as system #9.

The Cold Warehouse HVAC System #7 is the same as HVAC Central Plant HVAC System #6.

The Control Room HVAC System #8 will be the same as the Process Area HVAC System #2 except that no Zone One exhaust system will be provided.

The second floor mechanical room HVAC Systems #4 and 5 will be the same as System #3 except there will not be any Zone One exhaust.

Fire dampers will be provided at fire barriers.

Process cooling will be provided and will consist of cooling loop heat exchanges, isolation heat exchanger, cooling tower and finishing chiller, with two sets of pumps (4).

Process heating will be provided and will consist of 125 psi steam boilers, isolation steam-to-steam heat exchanger, steam and condensate piping and feed water pumps.

d. Plumbing and piping systems

- 1) The installation of new plumbing and piping systems will consist of the following:

Potable hot and/or cold water piping will be provided for the lavatories, mop sink, water closets, urinal, showers, emergency shower/eyewash and electric water coolers. Building water pressure reducing valves and backflow preventers will also be provided .

Natural gas piping for heating and laboratory use.

Heating hot water distribution piping be will provided.

Soil, waste, and vent piping for sanitary sewage piping will be provided.

Circulating pump for potable hot water will be provided.

Gas meter and pressure regulating valve station will be provided.

Distilled water, deionized water, compressed air, vacuum and acid waste piping systems will be provided in the laboratory areas. The acid waste will be piped to holding tank with a sample valve and pump.

A compressed air system will be provided for the process and HVAC controls.

Roof drains and piping will be provided.

Backflow preventers will be provided for non-potable water to laboratory sinks, fume hoods, boilers, chillers and cooling towers.

Plate and frame heat exchangers will be provided for process chilled water.

Shell and tube heat exchangers will be provided between high pressure process steam and high pressure steam from the HVAC Central Plant.

e. Fire Protection

The existing automatic wet type fire protection sprinkler system will be modified for the new partition layout and new facility areas. Each floor will be provided with a zone alarm indication by a flow switch on fire protection piping. Additional supports and sway bracing will be provided for a seismic event. The existing fire protection 6" riser alarm valve will be

removed. A new 6" riser will be installed near the exterior of the new additions. As much of the existing system will be reused, new piping and sprinklers will be added for new additions.

Two additional fire protection alarm risers and wet type fire sprinkler systems will be installed to provide protection for the new building additions to the main plant. A wet type fire protection system will be provided for the HVAC Central Plant and for the cold warehouse.

f. Energy Conservation Features

A liquid heat recovery run-around loop will be incorporated to temper outside air with exhaust air waste energy.

Outside air temperature reset for the heating hot water system will be provided.

A chilled water reset load analyzer will be utilized to minimize system cooling energy use.

Night set back control and an economizer cycle for the office areas.

Temperature control of potable hot water recirculating pump.

Multi-boilers, chillers, and cooling towers will be utilized to provide staging, backup capabilities and to allow equipment to operate at its most efficient point.

Plate and frame heat exchanger between the cooling tower water and chilled water will be provided to take advantage of evaporative cooling.

I. Electrical Systems

1. Power Distribution System

- a. Description of existing system: Electrical power is presently served to Building TA-50-1 at a primary distribution voltage of 13.2 kV via circuit S-9 which originates from substation TA-0-324 ETA (Eastern Technical Area). Circuit S-9 is routed in underground ductbank to a 15 kV rated padmounted switching station 50-146 located approximately 100 feet north of the building near manhole 50-110. The 15 kV switch no. 1762 then serves a nearby outdoor unit substation "SUB-A" composed of an oil-filled 750 kVA transformer, a 15 kV primary fused switch, and a 1200 A secondary circuit breaker. The transformer contains polychlorinated biphenyls (PCB's) and is scheduled to be replaced in April 1993 by a unit of identical size and free of PCB's. Unit substation "SUB-A" serves a 480 V, 3-wire switchboard "SWB-A" located in the basement of building TA-50-1. Switchboard "SWB-A" then feeds a 208/120 V, 4-wire switchboard "SWB-1" also located in the basement. Each of these switchboards distributes 3 phase power at its respective voltage level directly to several motor control centers (MCC's) located in the basement and in the control room on the first floor. The MCC's serve not only motor loads associated with the RLWTP but also all of the building's other loads via lighting and power panelboards located throughout the building.
- b. Deficiencies: An investigation of the basement and control room electrical switchgear revealed three significant problems. The first problem involves the age of some of the equipment and its overall lack of uniformity of design and construction. The switchboards "SWB-A" and "SWB-1", the low voltage power circuit breakers, and the MCC's were manufactured by four different manufacturers and installed at different times between 1963 and 1991. The problem with the aging equipment is the likelihood of procuring replacement parts decreases while the probability of equipment failure increases. Also, having switchgear in service that was designed and fabricated by four different manufacturers results in complications with servicing and operating the equipment as well as increases the cost and time required to procure replacement parts.

The second problem is related to NFPA code violations in regard to the installations of the main and secondary power distribution equipment. The MCC and a lighting panelboard installed in the control room have inadequate frontal working clearances as required by NFPA 70 Article 110-16. Also, the MCC is in violation of NFPA 70 Article 384-4 since mechanical piping and ductwork pass directly above the equipment with only 2 to 3 feet vertical clearance. The switchgear located in the basement switchgear room are also in violation of NFPA 70 Article 384-4 with respect to vertical clearance. Both "SWB-A" and "SWB-1" have large

potable water piping passing above them within approximately 3 to 4 feet, several fire sprinkler pipes are routed above the switchboards and MCC's, and a large ventilation duct passes above a number of wall mounted control cabinets and at least one panelboard.

The third problem concerns a shortage of space within specific equipment such as panelboards and MCC's. Circuit breaker space in most panelboards at 208/120 V, especially 20 A, single pole breakers, is critical or nonexistent. Also, some new electronic sensing equipment critical to life safety has been combined with other noncritical loads on the same circuit, as there are no available spare circuits in the existing panelboards. This could result in a noncritical load tripping the circuit breaker off at the panelboard while also shutting down critical loads connected to the same circuit.

- c. Description of new system: The preliminary load estimate indicates that a new unit substation with a capacity of 3,000 kVA will be required to serve the RLWTP expansion. The new substation will consist of an outdoor mineral oil-filled type transformer connected 13.2 kV delta to 480/277 V wye, with a primary fused switch and a secondary circuit breaker. The existing primary circuit S-9 presently serving TA-50-1 from substation TA-0-324 ETA will be adequate to serve the expanded plant. Likewise, the existing 15 kV rated padmounted switching station 50-146 now serving the will be available for tapping the 13.2 kV line for primary service to the new 3,000 kVA unit substation. The new unit substation will be installed as soon as possible in the construction phase so that it can be used as an alternate source of power. To minimize the cost of lengthy secondary cable, the new substation will be located as near to the major load centers within the expanded as possible, specifically in proximity to the new main switchboard.

The new main switchboard bus will be rated for 4,000 A at 480/277 V and will serve MCC's and distribution transformers and panelboards located throughout the expanded plant. The MCC's and other distribution service equipment will also be centrally located in proximity to the loads each will serve to minimize construction cost and optimize operation. Distribution voltage levels will be at 480/277 V and 208/120 V, depending on the load size and service requirements (see preliminary load estimate in Section XI, Supporting Information, for voltage levels and load magnitudes). Metering and ground fault protective relaying will be required for the expanded plant and will be located in the new main switchboard.

- d. Demolition: All of the existing power distribution system serving TA-50-1, including the unit substation "SUB-A" and all distribution equipment being served by it, will require demolition. Since the existing unit substation lies within the planned tank storage area and the transformer capacity is only 25% of what is required for the planned expansion, it will require complete removal. Also, complete demolition of all distribution equipment will be required because the bus ratings are inadequate to serve the plant expansion, the existing installations do not meet current NFPA codes, the present locations are in conflict with the refurbishment and expansion of the plant, and the useful life of the main switchgear has been exceeded. In addition, all existing feeders and branch circuit wiring and conduit will require complete removal commensurate with the complete architectural and structural refurbishment.

2. Emergency/Standby Power Systems

- a. Description of existing system: The RLWTP presently has no single dedicated emergency/standby power system which would include an on-site permanent generator set. However, a formal engineering study is currently underway which will make a preliminary determination of the size, type, installation requirements, and cost for a generator set to serve the total TA-50-1 load through the year 1997.
- b. Deficiencies: Assuming that the permanent generator set currently under study is installed at TA-50-1 by 1994 and that it will be sized to serve the present total TA-50-1 load of 750 kVA, the unit should be adequate to serve the expanded plant as well.
- c. Description of new system: Emergency/standby power will be required to serve the critical loads per DOE 6430.1A and NFPA 110. The sources will take two forms, one being an on-site permanent diesel generator and the other being one or more uninterruptible power supplies (UPS). The generator would serve standby power to large and medium critical loads such as pumps and other loads associated with the treatment process, and systems critical to life safety such as emergency lighting. The UPS would provide on line emergency power to smaller critical loads that require a high degree of continuous power. Such loads would include process control and instrumentation including a distributed control system (DCS), computers, air monitoring devices, and the emergency evacuation paging system. Since the UPS loads would likely be decentralized, it may be more feasible to install smaller multiple units throughout the facility at each load center rather than provide a single large unit to serve all loads. The preliminary load estimate for the RLWTP refurbishment and expansion indicates that a generator set with a minimum capacity of 400 kW would be required. Assuming the installation of multiple decentralized UPS's, the largest unit required would not likely exceed 15 kVA.

- d. Demolition: Assuming that a permanent generator set as described above is installed at TA-50-1 by 1994, the demolition required for such a unit would involve disassembly of the generator set components, such as the fuel system, removal of the concrete foundation, and relocation of the unit either at the RLWTP site or at another site.
3. Telephone/Communications System
- a. Description of existing system: The existing main telephone/communications line consists of a 200-pair cable routed underground in a 3" rigid galvanized steel conduit to TA-50-1. The main service is then distributed inside the building to individual telephone stations by telephone termination boards located throughout the facility.
 - b. Deficiencies: The only deficiency with this system appears to be its limited potential for increasing transmission and distribution capacity.
 - c. Description of new system: It is assumed that the refurbishment and expansion of the RLWTP would necessitate increasing the capacity and capability beyond what presently exists at TA-50-1 approximately 150%. Given this assumption, the tie in for the new main telephone/communications system would tap the existing main underground line in the nearest existing manhole. A new underground ductbank consisting of a minimum of two 4" PVC conduits, one with a new 300 pair cable (or fiber optics cable if in accordance with LANL site-wide program) and the other a spare, would then be routed from the existing manhole to a new telephone manhole to be installed just north of the proposed HVAC Central Plant, and then to a main distribution telephone terminal backboard and communications cabinet located in a dedicated communications room within the proposed HVAC Central Plant electrical room. From the main terminal board, the services would then be distributed throughout the facility to individual telephone stations and computer communications ports via distribution cabinets in each of the main areas. In addition to telephone, the communications system would also have the capability and capacity to support a local area network (LAN), facsimile, and a multitude of other data link services. The feasibility of using cable trays rather than conduits for distribution of the telecommunications cables from the main terminal board to local distribution centers should be assessed in the preliminary design for probable cost advantages and to facilitate the addition of cables in the future.
 - d. Demolition: Complete demolition of the interior telephone/communications distribution system, including termination equipment, raceway, and wiring will be necessary due to architectural and structural refurbishment requirements.

4. Lighting Systems

- a. Description of existing systems: Existing lighting systems for TA-50-1 consist of the following types of fixtures:
- 1) Standard "lay in" type fluorescent fixtures in office areas
 - 2) Standard "turret" type fluorescent fixtures in low ceiling industrial areas
 - 3) Incandescent "downlight" fixtures in interior corridors
 - 4) High bay HID fixtures in high ceiling industrial areas
 - 5) Standard battery pack emergency ("lunchbox") fixtures for emergency egresses
 - 6) Standard battery pack exit lights at exits
 - 7) Exterior HID wallmounted type fixtures located around the building periphery
 - 8) Standard pole-mounted HID type fixtures for limited street lighting
 - 9) The lighting systems are served at 480 V, 277 V, and 120 V.
- b. Deficiencies: One deficiency of the existing lighting systems is that they are served at three different voltage levels. This is a result of numerous separate upgrades over the past 30 years and indicates probable unavailability of spare circuits in existing panelboards. A second and more significant deficiency appears to be insufficient emergency lighting with respect to NFPA 101 minimum footcandle requirements for emergency egresses. A third deficiency is the age of most fixtures throughout the facility and the use of incandescent fixtures where fluorescent fixtures would serve better in regard to energy conservation, lamp life, and reduced maintenance.
- c. Description of new system: New lighting systems including fixtures, switches, and controls will be required throughout the refurbished and expanded plant. The table below presents preliminary design criteria for illumination in accordance with the recommendations of the Illuminating Engineers Society (IES), and gives a general description of lighting types to be used in various areas.

<u>Room/Area</u>	<u>Fixture Type</u>	<u>Minimum Average Foot Candles</u>
Entry/Lobby	2'x4' fluorescent troffer, lay in, 2 lamp	30
D&D Truck Airlock	4' length, 2 lamp, wet location industrial fluorescent	30
Cold Warehouse	low bay industrial lighting, high pressure sodium	30
Hot Warehouse	4' length, 2 lamp, wet location industrial fluorescent	75
Control/Computer	2'x4' 3 lamp parabolic troffer, air handling, lay in	75
Change Rooms	4' length, 3 lamp, fluorescent wrap around, surface mount	30
Chemistry Lab	2'x4' 3 lamp parabolic troffer, air handling, lay in	100
Tank Storage	high-bay industrial lighting, high pressure sodium	30
D&D Area (Office/Lab)	2'x4' fluorescent troffer, lay in, 3 lamp	75
Technical Support	2'x4' fluorescent troffer, lay in, 3 lamp	75
Soil Lab	2'x4' 3 lamp parabolic troffer, air handling, lay in	100
Process Area	4' length, 2 lamp, wet location industrial fluorescent	50
Mechanical Penthouse	low bay industrial lighting, high pressure sodium	30
Mechanical Room	low bay industrial lighting, high pressure sodium	30

- d. Demolition: Complete demolition of the interior lighting systems, including removal of fixtures, switches, controls, branch circuit wiring, and conduit will be necessary due to architectural and structural refurbishment and the need to correct deficiencies and improve performance.

5. Special Systems

- a. Description of existing systems: Existing special systems consist of fire alarm, lightning protection, emergency evacuation paging, and radiation monitoring equipment. The fire alarm system was upgraded in 1980 to replace aging equipment, add signalling devices, and bring it up to compliance with then current NFPA codes and DOE regulations.
- b. Deficiencies: These systems are for the purpose of life safety and are therefore generally adequately maintained and current with NFPA codes and DOE regulations. Some of the equipment is old, however, and aging equipment is more likely to fail than new equipment. For example, the audio distribution system was installed in 1967 and is now in its 26th year of operation. Although the fire alarm system was upgraded in 1980, there is a possibility it may require additional modifications since many changes have been made to those codes in the past 13 years. However, no major code deficiencies are known with respect to any of the existing special systems.
- c. Description of new systems: It is assumed that new special systems required for the expanded plant will comprise essentially the same systems that are now existing, but superior with respect to reliability and capability, and of course more expansive to serve all areas of the refurbished and expanded plant. These systems would include fire alarm, lightning protection, emergency evacuation paging (PA), security, and radiation monitoring equipment. In addition, the installations of these systems will be required to comply with the latest editions of the applicable NFPA codes, DOE orders, and IEEE standards for a safety class III nuclear facility.
- d. Demolition: Complete removal of all special systems will be necessary to allow total refurbishment. Reuse of some of the existing equipment may be possible; however, a certain amount of new equipment will be required for each system in any event since the net increase in square footage for the refurbished plant will be significant.

VIII. ESTIMATE

**RADIOACTIVE LIQUID WASTE TREATMENT PLANT
REFURBISHMENT**

COST SUMMARY

I.	ENGINEERING DESIGN & INSPECTION	\$8,039,538
II.	CONSTRUCTION	
	IMPROVEMENTS TO LAND & SITE WORK	\$138,079
	BUILDINGS	
	EXISTING PLANT	
	BUILDING CONSTRUCTION	\$10,498,083
	MECHANICAL	\$22,904,415
	ELECTRICAL	\$6,214,781
	PRE-TREATMENT PLANT	\$6,138,075
	INDUSTRIAL WASTE LINE & TUNNEL	\$5,024,818
	UTILITIES	\$253,945
	DEMOLITION & DECONTAMINATION	\$10,472,854
III.	EQUIPMENT	
	STANDARD EQUIPMENT	\$174,880
	SPECIAL FACILITIES EQUIPMENT	\$10,303,423
IV.	PROJECT MANAGEMENT	\$5,479,088
V.	ESCALATION @ 42.1% AVE.	\$36,098,571
VI.	CONTINGENCY @ 43.8% AVE.	<u>\$53,268,618</u>
	TOTAL ESTIMATED COST (TEC)	\$175,009,168

*Sherry
Connors*

*J. Smazo
2/1/91.*

COST AND TIME ESTIMATE

DECONTAMINATION AND DECOMMISSIONING

**TA-50, WASTE MANAGEMENT
FACILITY**

Decontamination and Decommissioning

Time and Cost Estimate

for TA-50, Buildings 1 and 2

WM-3, WM-66 ?

GOALS

The goal of the TA-50 Liquid Waste Disposal Facility decommissioning project is to decommission the facility safely and cost-effectively.

SCOPE

The D&D will consist of the removal of all Liquid waste processing equipment, flocculator, ion exchange columns and associated piping. Selected hoods and drains will also require removal. The remainder of Building 1 will be decontaminated. Building 2 and the tank farm will be excavated and removed. Solid wastes will be treated as required in AR 10-2 and 10-3 of the Laboratory Environmental Safety, and Health Manual.

Let's,
even,
area.

Building 1 and surrounding areas will be decontaminated for unrestricted use according to the ALARA Principle in effect at that time.

DESCRIPTION OF THE SITE

The TA-50, Liquid Waste Disposal Site was constructed in 1963, with several upgrades completed in 1984. Building one is constructed of reinforced concrete and concrete reinforced masonry walls with steel joists for roof support. The storage buildings and Room 34B are

pre-engineered metal frame type. Building 2 consists of a pump station and underground waste holding tanks.

TIME AND COST ESTIMATE

The time cost estimate are assuming work would start January 1, 1991, using the present regulations and cost scale.

Change in regulations and inflation will increase the estimate (see attachments for cost and schedule).

1991

COST BY WORK ELEMENTS \$K DOLLARS

WORK ELEMENTS	COST BASE LINE
1.0 PLANNING (APPEN. A&C)	
1.1 CHARACTERIZATION	
1.2 ENGINEERING	
1.3 ENVIROMENTAL COMPLIANCE	
1.4 REPORTING SYSTEM DEVE.	
1.5 PROCEDURE PREP.	
1.6 PREPARE FOR OPERATION	
1.7 READINESS REVIEW	

1.0 TOTAL \$980.

ED&I \$980,000

2.0 OPERATIONS (APPEN.B&C)

2.1 PROJECT SUPPORT	937
2.2 CONST SUPPORT B	500
2.3 D&D B	454
2.4 WASTE DISPOSAL (APPEN.D)	375
2.5 HEALTH PHYSICS	538
2.6 CERTIFICATION AND VER.	N/C

937
500
3454
375
538

5,804

2.0 TOTAL \$5,804.

3.0 CLOSEOUT (APPEN C)

3.0 TOTAL \$500

500.00

4.0 ~~MANAGER FUND~~ ^{Contingency} AND TAX (APPEN E)

~~4.0 TOTAL \$1,825~~

500
4

~~GRAND TOTAL \$9,109.~~

7,289.00

Cost Breakdown Structure

(Thousands \$)

Project Total = \$9109

TA-50 D&D

Time Estimate

Project Total = 2.4 yrs.

TA-50, D&D

[illegible]

Philip

MP-A-

Pg 1

ELEMENT DESCRIPTIONS

PHASE I PLANNING

- 1.1 CHARACTERIZATION- Data collection & documentation required to provide a thorough physical, chemical and radiological assessment.
- 1.2 ENGINEERING- Design and evaluation of the decommissioning project is termed engineering.
- 1.3 ENVIRONMENTAL COMPLIANCE- Demonstration of adherence to all applicable Federal and State laws and regulations.
- 1.4 REPORTING SYSTEM DEVELOPMENT- Reporting mechanisms necessary to provide the data essential to project management.
- 1.5 PROCEDURE PREPERATION- Technical specifications for performing Decontamination & Decommissioning.
- 1.6 PREPARE FOR OPERATION- Initiate documentation to start operation.
- 1.7 READINESS REVIEW- To ensure that all necessary activities have been completed and documented.

PHASE 2 OPERATION

- 2.1 PROJECT SUPPORT- The administration and management of Deconn & Decomm. operations.
- 2.2 CONSTRUCTION SUPPORT-The field mangement of the crafts daily operations.
- 2.3 DECONN - Those process which reduce radiation levels of components, systems and structures by removal of adherent contamination.
DECOMM -Those activities required to disassemble and remove systems and structures from their installed positions.
- 2.4 WASTE DISPOSAL- Those activities required to place contaminated items in the appropriate location per applicable regulations.
- 2.5 HEALTH PHYSICS- Establishing and maintaining a radiation protection program.

~~2.6 RESTORATION- After deconn & decomm activities the facility is restored as previously agreed upon.~~

2. ~~6~~ CERTIFICATION & VERIFICATION- An independent verification contractory surveys the facility to verify that radiological guidelines established for the project are met.

~~3.0~~ CLOSEOUT- Includes the post-remedial action report final LA report, and the final hazardous chemical + mixed waste survey.

4.0 MANAGEMENT RESERVE

FIAN - 10%

CLOSEOUT 10%

4.1 CONTINGENCY- ~~10% of total project cost~~

oper. 20%

4.2 ~~NEW EQUIPMENT & MATERIALS - Decommissioning equipment and materials required to assist in the reduction or removal of radioactive contamination.~~

TAX - 6%

~~2020-2021~~

NOTE:DPW D&D TOOK 3 YRS AT A CRAFT AND SUPPLY COST OF \$2,758.2K (1980 DOLLARS). TOTAL AREA PROCESSED 57,350 SQFT.

TA-50 LIQ. WASTE PROCESSING PLANT D&D IS SIMILAR TO BLBG.2
DPW. BLDG 2 REQUIRED 36% OF THE TIME SPENT AT DP OR \$993.K
BLDG. 2 WAS 11,000 SQFT IN SIZE. OR \$90/SQFT.

LIQ. WASTE PLANT PORTION OF TA-50 IS 13,760 SQFT.

$$13,760 \times 90 = \$1,238.4K$$

INFLATION RATE 5%/YR FOR 10 YEARS=\$778.8K

1991 TOTAL= \$2,017.2K (\$146/SOFT.)

NOTE: REMAINDER OF DPW, 46,350 SQFT COST \$1,519.8K
OR \$33/SQFT.

THE REST OF TA-50 IS SIMILAR, 23,661 SQFT X \$33=\$780.8K

INFLATION RATE 5%/YR FOR 10YRS=\$491.1K

1991 TOTAL=\$1271.9K

NOTE: TANKS REMOVED DURING AWL REMOVAL ARE SIMILAR TO TA-50 STORAGE TANKS. AWL AVE \$265/ CUM (1986). PIPE REMOVAL AVE \$64/LN FT.

STORAGE TANKS AND PUMP STATION, TA-50=1200 CUM

@\$265/CUM=\$318K ADD INFLATION RATE 5%/YR FOR 4 YEARS OF
\$68.5K = 1991 TOTAL \$386K. (\$322/CUM)

PIPE (ONLY PIPE FROM TA50-1 TO TA50-2 AND 100,000GAL TANK)

1200 LNFT X \$64 =\$128K ADD UNF.RATE 5%~~FOR~~ 4YEARS=20.5K

1991 TOTAL= \$148.5K (74/LNFT)

100,000 GAL TANK 400CUM X \$322 =128.8K

SUMMARY CRAFTS ONLY 1991 DOLLARS:

PLANT AREA	\$2,017.2K
------------	------------

REST OF BLDG	\$1,271.9K
--------------	------------

STORAGE TANKS \$ 386.5K

100,000 TANK	\$ 128.8K
--------------	-----------

PIPE REMOVAL	\$ 148.5K
--------------	-----------

TOTAL = \$3,953.9K

53, 454

Com. suppl. - 500K
Cn. / H 83454
\$ 3,944

LH5

PERS. REQUIRMENTS BY PHASE
(TA50PER)

1. PLANNING

1/11.5

- .5 HSE-8 SM
- .5 " TECH
- .5 HSE-1 TECH (COUNT RM.)
- 1.0 " " (MONITOR)
- .25 " SM
- .25 ENG -CPA
- 1.0 " -1
- 1.0 REPORTING SYS. TECH
- 1.0 CLERK TECH
- 1.0 HSE-7 SM

~~2. PLANNING - APPROX. 15 MONTHS~~

2. OPERATIONS - APPROX. 15 MONTHS

DRIFTS

- 1.0 HSE-7 TECH @TA-54
(1/2-OPER, 1/2 FIELD)
- 3.0 HSE-1 (MONITORS)
- .5 " " SM
- .5 " " TECH (COUNT RM)
- 1.0 HSE-7 TECH
- 1.0 ENG-1
- .25 ENG-DO (CPA)
- 1.0 TOTAL FTE SM (HSE DO SUPPORT)
- 1.0 HSE-7 TECH (D&D SUPPORT)
- 1.0 SECT. TECH

- 1.0 SUPERVISOR
- 1.0 CLERK/SEA
- 1.0 PRINT PERSON
- 8.0 LABORS
- 2.0 TEAMSTERS
- 2.0 OPERATORS
- 1.0 ELEC.
- 1.0 RIGGER
- 1.0 FITTER
- 4.0 JANITORS

3. CLOSEOUT - APPROX. 6 MONTHS

- 1.0 SM
- 1.0 SECT. TECH
- 2.0 HSE-1 TECH (MONITORS)
- .25 HSE-1 SM
- .25 HSE-8 SM
- .5 ENG-1

~~4. PLANNING - APPROX. 6 MONTHS~~

~~4. UTILITY~~

~~CONTINGENCY 10% FOR PLANNING
10% FOR CLOSEOUT
25% FOR OPERATIONS~~

~~ADD 5% FOR TAX.~~

2272
only

MGT. FUND AND TAX APP.E

4.1 CONTINGENCY PLANNING 10% = \$98K
CLOSEOUT 10% = \$50K
OPERATIONS 20% = \$1,161
TOTAL = \$1,309K

980,000
500,000
580,000

4.2 TAX 6% PLANNING TOT. = \$980K
OPERATIONS TOT. = \$5,804
CLOSEOUT TOT. = \$500K
MGER. FUND TOT. = 1,309
TOTAL = \$5,593K
6% = \$516K
PROJECT TOTAL = \$9,109K

2,142
 9,109
 6,967

994
 80
 42
 872.

Cont -

6,572.
 395
 6,967
 5,578
 994
 800

525 - 40

Close out

982 - 180

1st Planning

4,358
~~4,13~~
 325
 2,183
 500
 937

538 - 125
 375 - 50
 3,454 - 1,271
~~500~~
 - same

2.0 Office
 2.1 Proj. sup
 2.2 Cons su
 2.3 Bids
 2.4 Waste
 2.5 AD

all

H.K. Balla

Plot only

WASTE DESCRIPTION ~~APPEN. D~~

LOC	LLW	WASTE CUM MIX	TRU	CONTAINER NU	COST
PLANT	195	6	16	8	\$93K
LABS	80	51		23	\$50
TANK FARM	290	140		700	\$63
100K TANK	94				
PIPE	12	4		20	2
TOTALS=	700	200	20	751	200 <i>1208K</i>
EXTRA WORK & MONITORING					50
TOTAL=					\$250 <i>258K</i>

NOTE:

COST FOR SIZE REDUCTION (FITTING IN BOXS AND
BBLs.INCLUDED)
SOIL SAMPLING COST ADDED TO OTHER ELEMENTS.
TANKS THAT REQUIRE FLUSHING AND SAMPLING,SAMPLING COST
INCLUDED.

University of California
Los Alamos National Laboratory
ESCALATION SUMMARY BY WBS

PROJECT TITLE: RADIOACTIVE LIQUID WASTE PLANT REFURBISHMENT
 JOB NUMBER: 10411
 ESTIMATOR: JOHN P. BUTLER
 DATE: 20-Aug-93

Current DRI Escalation Rates by Year

1993	1994	1995	1996	1997
2.4%	3.1%	3.5%	3.7%	3.8%
1998	1999	2000	2001	2002
3.8%	3.8%	3.8%	3.8%	3.8%

WBS	ACTIVITY	ESCAL ACTIVITY					ESCAL	
		BASE	START	END	MID-	POINT	RATE	RATE
		DATE	DATE	DATE	DATE	DATE		
A	ENGINEERING, DESIGN & INSPECTION	Jul-93	Jan-97	Oct-2007	May-2002	May-2002	37.1%	
C1	IMPROVEMENTS TO LAND, EXISTING TREATMENT FACILITY	Jul-93	Feb-2000	Aug-2000	May-2000	May-2000	27.2%	
C2	RLW TREATMENT FACILITY, BUILDING CONSTRUCTION	Jul-93	May-2000	Oct-2007	Jan-2004	Jan-2004	45.9%	
C3	RLW PRE-TREATMENT FACILITY, BUILDING CONSTRUCTION	Jul-93	Jul-99	Dec-2000	Mar-2000	Mar-2000	26.4%	
C4	UTILITIES, EXISTING TREATMENT FACILITY	Jul-93	Feb-2000	Jan-2001	Jul-2000	Jul-2000	28.0%	
C6	DECONTAMINATION & DEMOLITION, EXISTING FACILITY	Jul-93	Mar-2002	Nov-2005	Jan-2004	Jan-2004	45.9%	
D1	STANDARD EQUIPMENT, EXISTING FACILITY	Jul-93	Jun-2007	Oct-2007	Aug-2007	Aug-2007	66.7%	
D2	SPECIAL FACILITIES EQUIPMENT, EXISTING FACILITY	Jul-93	Nov-2000	Nov-2006	Nov-2003	Nov-2003	45.0%	
E1	PROJECT MANAGEMENT, EXISTING FACILITY	Jul-93	Jan-97	Feb-2009	Jan-2003	Jan-2003	40.5%	

University of California
Los Alamos National Laboratory
CONTINGENCY RATE AND ALLOWANCE SUMMARY

PROJECT TITLE: RADIOACTIVE LIQUID WASTE PLANT REFURBISHMENT
JOB NUMBER: 10411
ESTIMATOR: JOHN BUTLER

DATE: 0
PROGRAM CODE: 0

WBS Item	Element of Cost	Direct Cost, Cont Mark-up, Escalation, Project Management, and ED&I	. . . Contingency. . . Rate	Allowance
A	ED&I	\$0.00	54.00%	\$0.00
B	Land & Land Rights	\$0.00	0.00%	\$0.00
C	Construction			
C1	Improvements to Land	\$0.00	37.00%	\$0.00
C2	RLW Treatment Facility	\$0.00	45.00%	\$0.00
C3	RLW Pre-Treatment Facility	\$0.00	33.00%	\$0.00
C4	Utilities	\$0.00	37.00%	\$0.00
C6	Decontamination & Demolition	\$0.00	48.00%	\$0.00
D	Equipment			
D1	Standard Equipment	\$0.00	19.00%	\$0.00
D2	Special Facilities Equipment	\$0.00	34.00%	\$0.00
E	Project management			
E1	Project Management	\$0.00	48.00%	\$0.00
E2		\$0.00	0.00%	\$0.00
E3		\$0.00	0.00%	\$0.00
E4		\$0.00	0.00%	\$0.00
E5		\$0.00	0.00%	\$0.00
E6		\$0.00	0.00%	\$0.00
	TOTAL CONSTRUCTION COST	\$0		
Z	TOTAL CONTINGENCY		ERR	\$0
::				

University of California
Los Alamos National Laboratory
RISK AND CONTINGENCY ANALYSIS

PROJECT TITLE: RADIOACTIVE LIQUID WASTE PLANT REFURBISHMENT
JOB NUMBER: 000000
ESTIMATOR: JOHN BUTLER

DATE: 20-Aug-83
PROGRAM CODE: 0

NORMAL MAXIMUM ESTIMATE
CONTINGENCY RATES

ENTER
ESTIMATE TYPE

Feasibility 35%
Conceptual 25%
Title I 20%
Title II 15%
Construction 10%

FEASIBILITY

COLUMN HEADING LEGEND

RW = Relative Weight (0=Not Applicable; 5=Important)
CL = Confidence Level (1=Low Risk; 5=High Risk)
WS = Weighted Score

RISK ASSESSMENT ITEM	A ED&I			B Land & Land Rights			C1 Improvements to Land			C2 RLW Treatment Facility			C3 RLW Pre-Treatment Facility		
	RW	CL	WS	RW	CL	WS	RW	CL	WS	RW	CL	WS	RW	CL	WS
DESIGN ELEMENTS															
TOTAL POSSIBLE SCORE (total relative weights x 5)		355			0			210			315			300	
SCORE RATIO (weighted score total/total possible score)	288 /	355 =	0.811	0 /	0 =	0.000	159 /	210 =	0.757	288 /	315 =	0.851	193 /	300 =	0.643
BASE CONTINGENCY RATE (Score Ratio X Normal Max. Contingency)	0.811 x	35% =	28.4%	0.000 x	35% =	0.0%	0.757 x	35% =	26.5%	0.851 x	35% =	29.8%	0.643 x	35% =	22.5%
BASE CONTINGENCY RATE			28.4%			0.0%			26.5%			29.8%			22.5%
OTHER CONSIDERATIONS															
Quality Assurance Level I, II, III; (+0 to 10%) (Quality Assurance Level IV = no addition.)			0.0%			0.0%			0.0%			0.0%			0.0%
Underground Lines not clearly defined, (+0 to 5%)			5.0%			0.0%			0.0%			0.0%			0.0%
* Environmental Considerations (describe) (+0 to 10%)			10.0%			0.0%			10.0%			10.0%			10.0%
* Other Special Requirements (describe) (+ %)			10.0%			0.0%			0.0%			0.0%			0.0%
* Design Uncertainty (explain) (+ %)			0.0%			0.0%			0.0%			0.0%			0.0%
* Construction Uncertainty (explain) (+ %)			0.0%			0.0%			0.0%			5.0%			0.0%
TOTAL ITEM CONTINGENCY RATE			53.4%			0.0%			36.5%			44.8%			32.5%
ROUND TO			54.0%			0.0%			37.0%			45.0%			33.0%
ESTIMATED CONSTRUCTION COST ---->			\$0.00			\$0.00			\$0.00			\$0.00			\$0.00
ITEM CONTINGENCY ALLOWANCE			\$0.00			\$0.00			\$0.00			\$0.00			\$0.00

* NOTES & EXPLANATIONS

ADDITIONAL CONTINGENCY PERCENTAGES ARE INCLUDED IN THE "OTHER CONSIDERATIONS"
CATEGORY OF ED&I TO ALLOW FOR PHASED DEMOLITION/CONSTRUCTION AND INCREASED COORDINATION
THAT WILL BE REQUIRED TO KEEP THE PLANT ON LINE DURING REFURBISHMENT.

PROJECT TITLE: RADIOACTIVE LIQUID WASTE PLANT REFURBISHMENT
 JOB NUMBER: 000000
 ESTIMATOR: JOHN BUTLER

University of California
 Los Alamos National Laboratory
 RISK AND CONTINGENCY ANALYSIS

DATE: 20-Aug-83
 PROGRAM CODE: 0

NORMAL MAXIMUM ESTIMATE
 CONTINGENCY RATES

ENTER
 ESTIMATE TYPE

Feasibility	35%	FEASIBILITY
Conceptual	25%	
Title I	20%	
Title II	15%	
Construction	10%	

COLUMN HEADING LEGEND

RW = Relative Weight (0=Not Applicable; 5=Important)
 CL = Confidence Level (1=Low Risk; 5=High Risk)
 WS = Weighted Score

WORKBREAKDOWN ITEM/DESCRIPTION -->	C4 Utilities			C6 Decontamination & Demolition			D1 Standard Equipment			D2 Special Facilities Equipment			E1 Project Management		
	RW	CL	WS	RW	CL	WS	RW	CL	WS	RW	CL	WS	RW	CL	WS
DESIGN ELEMENTS															
TOTAL POSSIBLE SCORE (total relative weights x 5)		200			285			140			420			370	
SCORE RATIO (weighted score total/total possible score)	150 /	200 =	0.750	265 /	285 =	0.930	78 /	140 =	0.543	405 /	420 =	0.964	340 /	370 =	0.919
BASE CONTINGENCY RATE (Score Ratio X Normal Max. Contingency)	0.750 x	35% =	26.3%	0.930 x	35% =	32.5%	0.543 x	35% =	19.0%	0.964 x	35% =	33.8%	0.919 x	35% =	32.2%
BASE CONTINGENCY RATE			26.3%			32.5%			19.0%			33.8%			32.2%
OTHER CONSIDERATIONS															
Quality Assurance Level I, II, III; (+0 to 10%) (Quality Assurance Level IV = no addition)			0.0%			0.0%			0.0%			0.0%			0.0%
Underground Lines not clearly defined, (+0 to 5%)			0.0%			5.0%			0.0%			0.0%			5.0%
* Environmental Considerations (describe) (+0 to 10%)			10.0%			10.0%			0.0%			0.0%			0.0%
* Other Special Requirements (describe) (+ %)			0.0%			0.0%			0.0%			0.0%			10.0%
* Design Uncertainty (explain) (+ %)			0.0%			0.0%			0.0%			0.0%			0.0%
* Construction Uncertainty (explain) (+ %)			0.0%			0.0%			0.0%			0.0%			0.0%
TOTAL ITEM CONTINGENCY RATE			36.3%			47.5%			19.0%			33.8%			47.2%
ROUND TO			37.0%			48.0%			19.0%			34.0%			48.0%
ESTIMATED CONSTRUCTION COST -->			\$0.00			\$0.00			\$0.00			\$0.00			\$0.00
ITEM CONTINGENCY ALLOWANCE			\$0.00			\$0.00			\$0.00			\$0.00			\$0.00

* NOTES & EXPLANATIONS

ADDITIONAL CONTINGENCY PERCENTAGES ARE INCLUDED IN THE "OTHER CONSIDERATIONS" CATEGORY OF PROJECT MANAGEMENT TO ALLOW FOR PHASED DEMOLITION/CONSTRUCTION THAT WILL BE REQUIRED TO KEEP THE PLANT ON LINE DURING REFURBISHMENT.

ICF Kaiser Engineers
Los Alamos, NM

PROJECT FACTORS FILE LISTING

PF File Name: RLW.PRF 14:36:33 9/17/93

HEADER INFORMATION

Job Number: 10411 Chng Order Number:
Title: RADIOACTIVE LIQUID WASTE PLANT REFURBISHMENT
Estimator: JOHN BUTLER Abbrev: RLW1
Location: LOS ALAMOS TO Reference Date: 03/04/93

DEFAULT BURDEN RATES

Cntrct Direct Markups	Labor: 0.0000	Material: 0.0350
	Const Equip: 0.0400	Subcontract: 0.0500
Cntrct General Markups	Overhead: 0.0730	Profit: 0.0400
	Gross Receipts Tax: 0.0606	Bond: 0.0125
Project Markups	Escalation: 0.0000	Proj Mngmnt: 0.0000
	ED&I: 0.0000	Contingency: 0.0000

Notes File Name: RLW.PFN

NOTES

1. THE ESTIMATE IS BASED ON THE RADIOACTIVE LIQUID WASTE TREATMENT PLANT ENGINEERING STUDY AND SUBSEQUENT CONTENTS AND DRAWINGS CONTAINED WITHIN THE SCOPE OF THIS STUDY.
2. THIS COST ESTIMATE ASSUMES THAT THE CONSTRUCTION WILL BE PERFORMED UNDER A CONTRACT BY A GENERAL CONTRACTOR AS A RESULT OF COMPETITIVE BIDDING.
3. THE ESTIMATED COSTS FOR THE TA-55 TO TA-50-1 RLW TUNNEL AND LINES WAS TAKEN FROM SNML TITLE I ESTIMATE.
4. MOST ESTIMATED COSTS IN THE TAKEOFF COST ANALYSIS REPORT ARE BASED ON 1993 MEANS COST DATA. ALL REMAINING ESTIMATED COSTS WERE ACQUIRED FROM VENDER QUOTES.
5. CONTINGENCY RATES FOR EACH MAJOR WBS WAS CALCULATED FROM A RISK AND CONTINGENCY ANALYSIS. THIS ANALYSIS PRECEEDS THE COST ESTIMATE.
6. NO COSTS ARE INCLUDED FOR OVERTIME, LABOR DISPUTES, OR UNUSUAL WEATHER CONCERNS.
7. ESCALATION IS CALCULATED FOR THE MIDPOINT OF EACH MAJOR WBS. START AND END DATES FOR EACH MAJOR WBS WAS TAKEN FROM THE PROJECT SCHEDULE. REFER TO THE ESCALATION SUMMARY PRECEEDING THE COST ESTIMATE.
8. ED&I WAS CALCULATED BY TAKING THE \$6,549,694.00 FIGURE FROM THE RLWTF ABBREVIATED CDR AND ADDING \$1,030,342.00 FOR ED&I ON SPECIAL FACILITIES EQUIPMENT. A 10% FACTOR WAS ASSUMED FOR SFE ED&I.
9. PROJECT MANAGEMENT WAS CALCULATED AS FOLLOWS:

PROJECT CONTROLS @ 2% OF FACILITY COST	= \$1,136,925.00
FACILITIES PROJECT MANAGEMENT @ 6%	= \$3,410,775.00
SFE PROJECT MANAGEMENT @ 6%	= \$ 618,205.00
TOTAL	= \$5,165,905.00
10. THE COST FOR DECON WORK WAS TAKEN FROM EARLIER DECON ESTIMATE PREPARED BY THE LABORATORY FOR TA-50-1. A COPY OF THIS DOCUMENT IS INCLUDED IN THIS SECTION OF THE STUDY.

ICF Kaiser Engineers
Los Alamos, NM

PROJECT FACTORS FILE LISTING

PF File Name: RLW.PRF

14:36:33

9/17/93

Work Breakdown Structure 1

4 Character Strings

44 Strings Defined

Character String	Category Title	Escalation	Proj Mngmt	ED&I	Contingency	Funds Expended Amount	Expend Date	Charac Value	Dimen Unit
	Default Values	0.0000	0.0000	0.0000	0.0000				0
C1	IMPROVEMENTS TO LAND	0.2720	0.0000	0.0000	0.3700				
C1A	IMPROVEMENTS TO LAND	0.2720	0.0000	0.0000	0.3700				
C2	RLW TREATMENT PLANT REFURBISHMENT	0.4590	0.0000	0.0000	0.4500				
C2A	GENERAL CONDITIONS	0.4590	0.0000	0.0000	0.4500				
C2B	BUILDING SITEWORK	0.4590	0.0000	0.0000	0.4500				
C2C	CONCRETE	0.4590	0.0000	0.0000	0.4500				
C2D	MASONRY	0.4590	0.0000	0.0000	0.4500				
C2E	METALS	0.4590	0.0000	0.0000	0.4500				
C2F	WOOD & PLASTIC	0.4590	0.0000	0.0000	0.4500				
C2G	MOISTURE & THERMAL CONTROL	0.4590	0.0000	0.0000	0.4500				
C2H	DOORS, WINDOWS, GLASS	0.4590	0.0000	0.0000	0.4500				
C2I	FINISHES	0.4590	0.0000	0.0000	0.4500				
C2J	SPECIALTIES	0.4590	0.0000	0.0000	0.4500				
C2K	SPECIAL CONSTRUCTION	0.4590	0.0000	0.0000	0.4500				
C2L	CONVEYING SYSTEMS	0.4590	0.0000	0.0000	0.4500				
C2M	MECHANICAL & HVAC	0.4590	0.0000	0.0000	0.4500				
C2N	ELECTRICAL	0.4590	0.0000	0.0000	0.4500				
C3	RLW PRE-TREATMENT PLANT	0.2640	0.0000	0.0000	0.3300				
C4	UTILITIES	0.2800	0.0000	0.0000	0.3700				
C4A	GAS LINES	0.2800	0.0000	0.0000	0.3700				
C4B	SANITARY SEWER	0.2800	0.0000	0.0000	0.3700				
C4C	WATER SUPPLY	0.2800	0.0000	0.0000	0.3700				
C4D	STEAM SUPPLY/DISTRIBUTION	0.2800	0.0000	0.0000	0.3700				
C4E	TELEPHONE/INTERCOM	0.2800	0.0000	0.0000	0.3700				
C4F	FIRE ALARM	0.2800	0.0000	0.0000	0.3700				
C4G	ELECTRIC SUBSTATION	0.2800	0.0000	0.0000	0.3700				
C4H	ELECTRIC DISTRIBUTION	0.2800	0.0000	0.0000	0.3700				
C4I	INDUSTRIAL WASTE LINE TA55-50	0.2800	0.0000	0.0000	0.3700				
C6	DECONTAMINATION AND DEMOLITION	0.4590	0.0000	0.0000	0.4800				
C6A	DEMO EXISTING RLW TREATMENT PLANT	0.4590	0.0000	0.0000	0.4800				
C6B	DECON EXISTING RLW PLANT	0.4590	0.0000	0.0000	0.4800				

ICF Kaiser Engineers
Los Alamos, NM

PROJECT FACTORS FILE LISTING

PF File Name: RLW.PRF 14:36:33 9/17/93

Character String	Category Title	Work Breakdown Structure 1		4 Character Strings		44 Strings Defined	
		Escalation	Proj Mngmt	ED&I	Contingency	Funds Expended Amount	Charac Dinen Value Unit
	Default Values	0.0000	0.0000	0.0000	0.0000		0
D	EQUIPMENT	0.0000	0.0000	0.0000	0.0000		
D1	STANDARD EQUIPMENT	0.6670	0.0000	0.0000	0.1900		
D1A	OFFICE FURNITURE & E	0.6670	0.0000	0.0000	0.1900		
D1B	QUIPMENT	0.6670	0.0000	0.0000	0.1900		
D2	LAB BENCHES, CABINET S & COUNTERS	0.4500	0.0000	0.0000	0.3400		
D2A	SPECIAL FACILITIES E	0.4500	0.0000	0.0000	0.3400		
D2B	QUIPMENT	0.4500	0.0000	0.0000	0.3400		
E	RLW TREATMENT EQUIPM	0.4500	0.0000	0.0000	0.3400		
F	ENT	0.4500	0.0000	0.0000	0.3400		
C1B	LAB EQUIP--FUME HOOD S GLOVE BOXES ETC-	0.4050	0.0000	0.0000	0.4800		
C	PROJECT MANAGEMENT	0.0000	0.0000	0.0000	0.0000		
B	CONTINGENCY	0.0000	0.0000	0.0000	0.0000		
A1	RLW PRE-TREATMENT PL	0.0000	0.0000	0.0000	0.0000		
	ANT	0.0000	0.0000	0.0000	0.0000		
	CONSTRUCTION	0.0000	0.0000	0.0000	0.0000		
	LAND AND LAND RIGHTS	0.0000	0.0000	0.0000	0.0000		
	ENGINEERING, DESIGN & INSPECTION	0.3710	0.0000	0.0000	0.5400		

ICF Kaiser Engineers
Los Alamos, NM

PROJECT FACTORS FILE LISTING

PF File Name: RLW.PRF

14:36:33

9/17/93

Markup Breakdown

2 Digit Markup Tags

4 Tags Defined

Tag	Contractor	Labor	Mat	Equip	Sub Cntrct	Overhead	Profit	GRTax	Bond	Funds Expended Amount Date
	Default Markups	0.0000	0.0350	0.0400	0.0500	0.0730	0.0400	0.0606	0.0125	
01	NO MARKUP	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	
02	JOHNSON CONTROLS	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	
03	PRIME MARKUP ON SUBCONTRACTS	0.0000	0.0000	0.0000	0.0500	0.0000	0.0000	0.0606	0.0125	
04	GROSS RECPTS. TAX	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0606	0.0000	

PF File: rlw.PRF
TO File: rlw.TAK

ICF Kaiser Engineers
Los Alamos, NM
GENERAL COST SUMMARY

Sorted by WBS 1 Summarized on 4 Characters
Secondary Subtotals on 0 Characters

Job Number: 10411 Change Order Number: 13:41:43 9/17/93
Project Title: RADIOACTIVE LIQUID WASTE PLANT REFURBISHMENT Checked By:
Estimator: JOHN BUTLER Abbrev: RLW1 Location: LOS ALAMOS

Character String	Brkdwn Category Title	Rates				Category Direct Cost	Category Cntrct Markup	Escl	PM	Project Markups Subtotal	ED&I	Cont	Category Total Cost
		Escl	PM	ED&I	Cont								
A1	ENGINEERING,DESIGN & INSPECTION	0.3710	0.0000	0.0000	0.5400	7580000.	459538.	2982669	0	11022207.	0	5951992	16974199.
C1A	IMPROVEMENTS TO LAND	0.2720	0.0000	0.0000	0.3700	41272.	9889.	13916	0	65077.	0	24078	89155.
C2B	BUILDING SITEWORK	0.4590	0.0000	0.0000	0.4500	71080.	15838.	39895	0	126813.	0	57066	183879.
C2C	CONCRETE	0.4590	0.0000	0.0000	0.4500	1021187.	233186.	575757	0	1830130.	0	823559	2653689.
C2E	METALS	0.4590	0.0000	0.0000	0.4500	3476943.	803075.	1964528	0	6244546.	0	2810046	9054592.
C2F	WOOD & PLASTIC	0.4590	0.0000	0.0000	0.4500	28000.	6476.	15824	0	50300.	0	22635	72935.
C2G	MOISTURE & THERMAL C ONTROL	0.4590	0.0000	0.0000	0.4500	1406459.	302947.	784617	0	2494023.	0	1122310	3616333.
C2H	DOORS, WINDOWS, GLASS	0.4590	0.0000	0.0000	0.4500	84685.	19821.	47968	0	152474.	0	68613	221087.
C2I	FINISHES	0.4590	0.0000	0.0000	0.4500	2468286.	609270.	1412598	0	4490154.	0	2020569	6510723.
C2L	CONVEYING SYSTEMS	0.4590	0.0000	0.0000	0.4500	30000.	7748.	17326	0	55074.	0	24783	79857.
C2M	MECHANICAL & HVAC	0.4590	0.0000	0.0000	0.4500	18484851.	4419564.	10513126	0	33417541.	0	15037893	48455434.
C2N	ELECTRICAL	0.4590	0.0000	0.0000	0.4500	5130106.	1084675.	2852584	0	9067365.	0	4080314	13147679.
C3	RLW PRE-TREATMENT PLANT	0.2640	0.0000	0.0000	0.3300	4878240.	1259835.	1620452	0	7758527.	0	2560314	10318841.
C4A	GAS LINES	0.2800	0.0000	0.0000	0.3700	1265.	278.	432	0	1975.	0	731	2706.
C4B	SANITARY SEWER	0.2800	0.0000	0.0000	0.3700	50063.	11358.	17198	0	78619.	0	29089	107708.
C4C	WATER SUPPLY	0.2800	0.0000	0.0000	0.3700	27054.	6139.	9294	0	42487.	0	15720	58207.
C4E	TELEPHONE/INTERCOM	0.2800	0.0000	0.0000	0.3700	5080.	1097.	1730	0	7907.	0	2926	10833.

Character String	Brkdwn Category Title	Rates				Category Direct Cost	Category Cntrct Markup	Escl	PM	Project Markups Subtotal	ED&I	Cont	Category Total Cost
		Escl	PM	ED&I	Cont								
C4G	ELECTRIC SUBSTATION	0.2800	0.0000	0.0000	0.3700			39385	0		0	66616	
						113651.	27008.			180044.			246660.
C4H	ELECTRIC DISTRIBUTIO	0.2800	0.0000	0.0000	0.3700			3067	0		0	5187	
	N					9030.	1922.			14019.			19206.
C4I	INDUSTRIAL WASTE LIN	0.2800	0.0000	0.0000	0.3700			1406949	0		0	2379754	
	E TASS-50					4116352.	908466.			6431767.			8811521.
C6A	DEMO EXISTING RLW TR	0.4590	0.0000	0.0000	0.4800			217040	0		0	331149	
	EATMENT PLANT					392690.	80164.			689894.			1021043.
C6B	DECON EXISTING RLW P	0.4590	0.0000	0.0000	0.4800			4590000	0		0	7003200	
	LANT					10000000.	0.			14590000.			21593200.
D1B	LAB BENCHES, CABINET	0.6670	0.0000	0.0000	0.1900			116645	0		0	55390	
	S, & COUNTERS					141000.	33880.			291525.			346915.
D2A	RLW TREATMENT EQUIPM	0.4500	0.0000	0.0000	0.3400			4475800	0		0	4903487	
	ENT					7983669.	1962553.			14422022.			19325509.
D2B	LAB EQUIP--FUME HOOD	0.4500	0.0000	0.0000	0.3400			160740	0		0	176100	
	S,GLOVE BOXES, ETC.					288000.	69201.			517941.			694041.
E	PROJECT MANAGEMENT	0.4050	0.0000	0.0000	0.4800			2219031	0		0	3695097	
						5165905.	313183.			7698119.			11393216.
						=====	=====	=====	=====	=====	=====	=====	=====
Project Total Cost						72994868.	12647111.	36098571	0	121740550.	0	53268618	175009168.

PF File: rlw.PRF
TO File: rlw.TAK

ICF Kaiser Engineers
Los Alamos, NM

TAKE-OFF EXTENSION

Sort: WBS1

Subtotal: 4 characters

Job Number: 10411

Change Order Number:

13:51:51

9/17/93

Project Title: RADIOACTIVE LIQUID WASTE PLANT REFURBISHMENT

Checked By:

Estimator: JOHN BUTLER

Abbrev: RLW1

Location: LOS ALAMOS

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c t r c t	A c t i v i t y	Take-Off Item Description	Quantity Unit	Labor		Material Rate Ext'd Cost	Const Equip Rate Ext'd Cost	Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate Ext'd Cost				
909 A1					0	4	ENGINEERING, DESIGN, & INSPECTION	1.0 LOT		0.00	0.00	0.00		
										0.	0.	0.	7580000.	7580000.
A1							Category Direct Cost			0.	0.	0.	7580000.	7580000.
351 C1A					0	0	SITE IMPROVEMENTS ASPHALT PAVEMENT	444.0 SY	0.046	19.24 393.	10.22 4538.	10.00 4440.	0.	9371.
352 C1A					0	0	SITE IMPROVEMENTS FENCING	600.0 LF	0.128	15.48 1189.	5.30 3180.	0.00	0.	4369.
353 C1A					0	0	SITE IMPROVEMENTS SIGNAGE	1.0 LS		0.00 0.	0.00 0.	0.00	500.	500.
354 C1A					0	0	SITE IMPROVEMENTS GUARD POSTS	20.0 EA	4.000	15.48 1238.	60.00 1200.	0.00	10000.	12438.
355 C1A					0	0	SITE IMPROVEMENTS GUARD RAILS	400.0 LF	0.720	15.48 4458.	10.00 4000.	0.48 192.	0.	8650.
356 C1A					0	0	EROSION CONTROL SEEDING	1.0 LS		0.00 0.	0.00 0.	0.00	3000.	3000.
357 C1A					0	0	EROSION CONTROL RIP RAP	1.0 LS		0.00 0.	0.00 0.	0.00	2000.	2000.
358 C1A					0	0	EROSION CONTROL GUNNITE	1500.0 SF	0.024	18.71 674.	0.18 270.	0.00	0.	944.
C1A							Category Direct Cost			7952.	13188.	4632.	15500.	41272.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn Structure				J o c	A Cntrct Markup	Take-Off Item	Quantity	- - - - L a b o r - - - -			Material		Const Equip		Sub	Item
Item	1	2	3	4	Trd b ID F	c Tag Description	Unit	Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost	Cntrct Cost	Direct Cost
325	C2B				0	0	EARTHWORK	2650.0	0.184	22.99	0.00		4.12			
							MASS EXCAVATION	CY		11210.	0.		10918.		0.	22128.
326	C2B				0	0	EARTHWORK	480.0	0.148	22.99	0.00		0.95			
							FDN. EXCAVATION	CY		1633.	0.		456.		0.	2089.
327	C2B				0	0	EARTHWORK	250.0	0.080	22.99	0.00		1.38			
							TRENCHING	CY		460.	0.		345.		0.	805.
328	C2B				0	0	EARTHWORK	1000.0	0.008	22.99	0.00		0.31			
							MASS BACKFILL AND COMPACTION	CY		184.	0.		310.		0.	494.
329	C2B				0	0	EARTHWORK	300.0	0.120	22.99	0.00		0.72			
							FINE BACKFILL AND COMPACTION	CY		828.	0.		216.		0.	1044.
330	C2B				0	0	EARTHWORK	62.0	0.388	22.99	18.00		0.72			
							TRENCH SAND BEDDING	CY		553.	1116.		45.		0.	1714.
331	C2B				0	0	SITE CONCRETE	40.0	7.090	21.93	116.00		75.00			
							RETAINING WALLS	CY		6219.	4640.		3000.		0.	13859.
332	C2B				0	0	SITE CONCRETE	30.0	1.180	21.93	102.00		5.90			
							RETAINING WALL BASE	CY		776.	3060.		177.		0.	4013.
333	C2B				0	0	SITE CONCRETE	40.0	0.040	21.93	0.91		0.00			
							SIDEWALKS	SF		35.	36.		0.		0.	71.
334	C2B				0	0	SITE CONCRETE	64.0	2.580	21.93	76.00		8.60			
							EQUIPMENT PADS	CY		3621.	4864.		550.		0.	9035.
335	C2B				0	0	SITE CONCRETE	4.0	7.090	21.93	116.00		4.82			
							MISC. DRAINAGE STRUCT.	CY		622.	464.		19.		0.	1105.
336	C2B				0	0	SITE CONCRETE	4.0	1.500	19.24	20.00		100.00			
							MANHOLES	EA		115.	80.		400.		0.	595.
337	C2B				0	0	SITE CONCRETE	10.0	4.000	19.24	90.00		8.50			
							MISC. CONC.	CY		770.	900.		85.		0.	1755.
338	C2B				0	0	SITE CONCRETE	30.0	7.090	19.24	116.00		4.82			
							STEPS	CY		4092.	3480.		145.		0.	7717.
349	C2B				0	0	STORM S., CSP	200.0	0.175	15.48	17.75		0.00			
								LF		542.	3550.		0.		0.	4092.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c t r c t I D F	A c M a r k u p t a g	Take-Off Item Description	Quantity Unit	L a b o r			Material Rate Ext'd Cost	Const Equip Rate Ext'd Cost	Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost				
350	C2B				0	0	STORM S. END SECTION	8.0 EA	2.550	15.48	316.	30.90 247.	0.00 0.	0.	563.
C2B							Category Direct Cost			31976.		22438.	16666.	0.	71080.
359	C2C				0	0	HVAC CENTRAL PLANT FOUNDATION GRADE BEAMS	48.0 CY	6.000	18.71	5388.	136.00 6528.	10.60 509.	0.	12425.
360	C2C				0	0	HVAC CENTRAL PLANT FOUNDATION FOOTINGS	14.0 CY	2.580	18.71	676.	102.00 1428.	8.60 120.	0.	2224.
361	C2C				0	0	HVAC CENTRAL PLANT FOUNDATION PEDESTALS	13.0 CY	11.740	18.71	2856.	235.00 3055.	21.00 273.	0.	6184.
362	C2C				0	0	HVAC CENTRAL PLANT FOUNDATION FLOORS	155.0 CY	0.731	18.71	2120.	102.00 15810.	3.66 567.	0.	18497.
363	C2C				0	0	HVAC CENTRAL PLANT FOUNDATION EQUIP. PADS	80.0 CY	2.580	18.71	3862.	102.00 8160.	8.60 688.	0.	12710.
364	C2C				0	0	HVAC CENTRAL PLANT FOUNDATION CONC. WALL TO EARTH	48.0 CY	6.000	18.71	5388.	136.00 6528.	10.55 506.	0.	12423.
365	C2C				0	0	HVAC CENTRAL PLANT FOUNDATION FINISH	7632.0 SF	0.015	21.93	2511.	1.01 7708.	0.14 1068.	0.	11287.
368	C2C				0	0	STRENGTHEN EXISTING STRUCTURE GRADE BEAMS	72.0 CY	6.800	21.93	10737.	110.00 7920.	24.00 1728.	0.	20385.
369	C2C				0	0	STRENGTHEN EXISTING STRUCTURE - DRILLED IN PLACE PIERS	480.0 LF	0.604	21.93	6358.	17.82 8554.	7.50 3600.	0.	18512.
375	C2C				0	0	COLD WRHSE.- STRUCT. FOUNDATION - GRADE BEAMS	37.0 CY	6.000	21.93	4868.	136.00 5032.	10.60 392.	0.	10293.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	o c		Cntrct		Take-Off	Item	Quantity	Unit	- - - - L a b o r - - - -			Material		Const Equip		Sub	Item
Item	1	2	3	4	ID	F	t	Tag	Markup					Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd		
										Description						Cost		Cost		Cost	Cost	Direct
376	C2C							0	0	COLD WRHSE.- STRUCT.		12.0		2.580	21.93		102.00		8.60			
										FOUNDATION - FOOTIN		CY				679.		1224.		103.	0.	2006.
										GS												
377	C2C							0	0	COLD WRHSE.- STRUCT.		10.0		11.740	21.93		235.00		21.00			
										FOUNDATION - PED.'S		CY				2575.		2350.		210.	0.	5135.
378	C2C							0	0	COLD WRHSE.- STRUCT.		92.0		0.731	21.93		102.00		3.66			
										FOUNDATION - FLOOR		CY				1475.		9384.		337.	0.	11196.
										SLAB												
380	C2C							0	0	COLD WRHSE.- PRE-ENG		4480.0		0.056	21.93		4.50		1.05			
										METAL BUILDING		SF				5502.		20160.		4704.	0.	30366.
381	C2C							0	0	HOT WAREHOUSE FNDTN.		25.0		6.600	21.93		136.00		10.60			
										GRADE BEAM		CY				3618.		3400.		265.	0.	7283.
382	C2C							0	0	HOT WAREHOUSE FNDTN.		12.0		2.580	21.93		102.00		8.60			
										FOOTINGS		CY				679.		1224.		103.	0.	2006.
383	C2C							0	0	HOT WAREHOUSE FNDTN.		12.0		11.740	21.93		235.00		21.00			
										PEDESTALS		CY				3089.		2820.		252.	0.	6161.
384	C2C							0	0	HOT WAREHOUSE FNDTN.		118.0		1.100	21.93		83.00		3.66			
										8" FLOOR SLAB		CY				2847.		9794.		432.	0.	13072.
385	C2C							0	0	HOT WAREHOUSE FNDTN.		4367.0		0.015	21.93		1.01		0.14			
										FINISH		SF				1437.		4411.		611.	0.	6459.
386	C2C							0	0	HOT WAREHOUSE FNDTN.		4.0		9.000	21.93		170.00		75.00			
										PITS		CY				789.		680.		300.	0.	1769.
399	C2C							0	0	STEEL STACKS		565.0		1.900	24.68		115.00		6.35			
										FOUNDATION		CY				26494.		64975.		3588.	0.	95057.
										MAT FTG. W/R-STEEL												
646	C2C							0	0	STRUCTURAL STEEL		56700.0		0.022	21.93		1.04		0.20			
										FLOOR		SF				27355.		58968.		11340.	0.	97663.
										CONCRETE												
713	C2C							0	0	TANK STORAGE 1		1700.0		1.900	21.93		115.00		6.35			
										MAT FOUNDATION CONC.		CY				70834.		195500.		10795.	0.	277129.
714	C2C							0	0	TANK STORAGE 1		110.0		6.000	21.93		135.00		11.05			
										WALLS		CY				14474.		14850.		1216.	0.	30539.
715	C2C							0	0	TANK STORAGE 1		18.0		11.740	21.93		235.00		21.00			
										PEDESTALS		CY				4634.		4230.		378.	0.	9242.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	o c Cntrct		Take-Off Item	Quantity	- - - - L a b o r - - - -			Material	Const Equip		Sub	Item
Structure				Trd	b	c	Markup			Factor	Rate	Ext'd		Rate	Ext'd	Cntrct	
Item	1	2	3	4	ID	F	t	Tag	Unit			Cost	Rate	Ext'd	Cost	Cost	Cost
716	C2C						0	0	TANK STORAGE 1	124.0	0.670	21.93	12.85	0.00			
									A.B. COLUMNS	EA		1822.	1593.	0.		0.	3415.
717	C2C						0	0	TANK STORAGE 1	144.0	0.670	21.93	12.85	0.00			
									A.B. TANKS	EA		2116.	1850.	0.		0.	3966.
718	C2C						0	0	TANK STORAGE 2	765.0	1.900	21.93	115.00	6.35			
									MAT FOUNDATION CONC.	CY		31875.	87975.	4858.		0.	124708.
719	C2C						0	0	TANK STORAGE 2	50.0	6.000	21.93	135.00	11.05			
									WALLS	CY		6579.	6750.	553.		0.	13882.
720	C2C						0	0	TANK STORAGE 2	7.0	11.740	21.93	235.00	21.00			
									PEDESTALS	CY		1802.	1645.	147.		0.	3594.
721	C2C						0	0	TANK STORAGE 2	92.0	0.670	21.93	12.85	0.00			
									A.B. COLUMNS	EA		1352.	1182.	0.		0.	2534.
722	C2C						0	0	TANK STORAGE 2	48.0	0.670	21.93	12.85	0.00			
									A.B. TANKS	EA		705.	617.	0.		0.	1322.
723	C2C						0	0	PROCESS & TECH. SUP.	1320.0	0.384	21.93	34.00	5.95			
									DRILLED-IN-PLACE	LF		11116.	44880.	7854.		0.	63850.
									PIERS								
724	C2C						0	0	PROCESS & TECH. SUP.	148.0	6.000	21.93	136.00	10.60			
									GRADE BEAM	CY		19474.	20128.	1569.		0.	41171.
725	C2C						0	0	PROCESS & TECH. SUP.	218.0	0.731	21.93	63.00	3.66			
									SLAB ON GRADE	CY		3495.	13734.	798.		0.	18027.
726	C2C						0	0	PROCESS & TECH. SUP.	11781.0	0.015	21.93	1.01	0.14			
									SLAB ON GRADE -	SF		3875.	11899.	1649.		0.	17424.
									FINISH								
727	C2C						0	0	PROCESS & TECH. SUP.	264.0	0.670	21.93	12.85	0.00			
									A.B.	EA		3879.	3392.	0.		0.	7271.
C2C									Category Direct Cost			299335.	660339.	61513.		0.	1021187.
366	C2E						0	0	HVAC CENTRAL PLANT	7632.0	0.056	29.12	4.50	1.05			
									PRE-ENGINEERED MTL	SF		12446.	34344.	8014.		0.	54803.
									BUILDING								
367	C2E						0	0	STRENGTHEN EXISTING	260.0	6.680	21.93	152.00	58.00			
									STRUCTURE	CY		38088.	39520.	15080.		0.	92688.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o b I D F	A c t Tag	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
370	C2E				0	0	STRENGTHEN EXISTING STRUCTURE - STEEL ANGLES	9400.0 LBS	0.570	29.12	156025.	0.78	7332.	0.06	564.	0.	163921.
371	C2E				0	0	STRENGTHEN EXISTING STRUCTURE - STEEL PLATE	1200.0 LBS	0.220	29.12	7688.	0.75	900.	0.03	36.	0.	8624.
372	C2E				0	0	STRENGTHEN EXISTING STRUCTURE - PREP. & FIELD WELD	336.0 LF	0.666	29.12	6516.	0.40	134.	5.35	1798.	0.	8448.
373	C2E				0	0	STRENGTHEN EXISTING STRUCTURE - EXPAN. ANCHORS	100.0 EA	0.123	29.12	358.	3.58	358.	0.00	0.	0.	716.
379	C2E				0	0	COLD WRHSE.- STRUCT. FOUNDATION - FINISH	4480.0 SF	0.015	21.93	1474.	1.01	4525.	0.14	627.	0.	6626.
387	C2E				0	0	HOT WRHSE - STR. STL COLUMNS (W8X31)	240.0 LF	0.051	29.12	356.	17.50	4200.	0.97	233.	0.	4789.
388	C2E				0	0	HOT WRHSE - STR. STL BEAMS	360.0 LF	0.063	29.12	660.	12.50	4500.	1.60	576.	0.	5736.
389	C2E				0	0	HOT WRHSE - STR. STL BEAMS	720.0 LF	0.093	29.12	1950.	7.00	5040.	1.75	1260.	0.	8250.
390	C2E				0	0	HOT WRHSE - STR. STL BRACING	200.0 LF	0.063	29.12	367.	12.50	2500.	1.60	320.	0.	3187.
391	C2E				0	0	HOT WRHSE - STR. STL BASE PLATES	480.0 LBS	0.008	29.12	112.	0.44	211.	0.00	0.	0.	323.
392	C2E				0	0	HOT WRHSE - STR. STL GIRTS	480.0 LF	0.093	29.12	1300.	10.00	4800.	1.60	768.	0.	6868.
393	C2E				0	0	STEEL STACKS STRUCTURAL STL. PLATE - 3/8	96.0 TON	11.640	29.12	32540.	1625.00	156000.	230.00	22080.	0.	210620.
394	C2E				0	0	STEEL STACKS STRUCTURAL STIFF & BASE PL	16.0 TON	11.640	29.12	5423.	1625.00	26000.	120.00	1920.	0.	33343.
395	C2E				0	0	STEEL STACKS STRUCTURAL ANCHOR BOLTS	288.0 EA	0.670	29.12	5619.	12.85	3701.	0.00	0.	0.	9320.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c ID F	A c t Tag	Take-Off Description	Quantity Unit	- - - - L a b o r - - - -		Material Rate Ext'd Cost	Const Equip Rate Ext'd Cost	Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate Ext'd Cost				
396 C2E					0	0	HOT WAREHOUSE STRUCTURAL STEEL DECK	4367.0 SF	0.007	29.12 890.	0.73 3188.	0.01 44.	0.	4122.
397 C2E					0	0	STEEL STACKS STRUCTURAL PLATE FORMS	32.0 TONS	10.540	29.12 9822.	1200.00 38400.	150.00 4800.	0.	53022.
398 C2E					0	0	STEEL STACKS STRUCTURAL LADDER W/CAGE	800.0 LF	0.640	29.12 14909.	43.00 34400.	2.60 2080.	0.	51389.
450 C2E					0	0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. FRAM. PARTIONS-INT	750.0 SF	0.019	23.68 337.	0.31 233.	0.00 0.	0.	570.
451 C2E					0	0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. FRAM. WALLS - EXT	3750.0 SF	0.019	23.68 1687.	0.31 1163.	0.00 0.	0.	2850.
452 C2E					0	0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. INT METAL LINER PNL	3520.0 SF	0.031	23.68 2584.	2.85 10032.	0.00 0.	0.	12616.
636 C2E					0	0	STRUCTURAL STEEL FLOOR COLUMNS	390.0 TONS	11.640	29.12 132193.	1625.00 633750.	120.00 46800.	0.	812743.
637 C2E					0	0	STRUCTURAL STEEL FLOOR BASE PL	80.0 TONS	11.640	29.12 27117.	1625.00 130000.	120.00 9600.	0.	166717.
638 C2E					0	0	STRUCTURAL STEEL FLOOR BRACING	80.0 TONS	16.000	29.12 37274.	1625.00 130000.	120.00 9600.	0.	176874.
639 C2E					0	0	STRUCTURAL STEEL FLOOR GIRDERS (W21x83)	60.0 TONS	16.000	29.12 27955.	1625.00 97500.	120.00 7200.	0.	132655.
640 C2E					0	0	STRUCTURAL STEEL FLOOR 3/4" STUDS	650.0 EA	0.016	29.12 303.	0.43 280.	0.41 267.	0.	849.
641 C2E					0	0	STRUCTURAL STEEL FLOOR BEAMS (W10x19)	120.0 TONS	11.640	29.12 40675.	1625.00 195000.	120.00 14400.	0.	250075.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	o c Cntrct		Take-Off Item Description	Quantity Unit	- - - - L a b o r - - - -			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
Item	1	2	3	4	ID	F	t			Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
642	C2E						0 0	STRUCTURAL STEEL FLOOR STUDS	11400.0 EA	0.016	29.12	5311.	0.43	4902.	0.41	4674.	0.	14887.
643	C2E						0 0	STRUCTURAL STEEL FLOOR TRUSSES	145.0 TONS	7.270	29.12	30697.	1250.00	181250.	110.00	15950.	0.	227897.
644	C2E						0 0	STRUCTURAL STEEL FLOOR MISC STEEL	36.0 TONS	11.640	29.12	12202.	1625.00	58500.	120.00	4320.	0.	75022.
645	C2E						0 0	STRUCTURAL STEEL FLOOR STEEL DECK	566676.0 SF	0.009	29.12	148514.	0.90	510008.	0.02	11334.	0.	669856.
647	C2E						0 0	STRUCTURAL STEEL ROOF JOIST	100.0 TONS	5.330	29.12	15521.	700.00	70000.	81.00	8100.	0.	93621.
648	C2E						0 0	STRUCTURAL STEEL ROOF JOIST GIRDERS	44.0 TONS	6.150	29.12	7880.	925.00	40700.	93.00	4092.	0.	52672.
649	C2E						0 0	STRUCTURAL STEEL ROOF STEEL DECK	56676.0 SF	0.008	29.12	13203.	0.81	45908.	0.02	1134.	0.	60244.
C2E								Category Direct Cost				799997.		2479278.		197668.	0.	3476943.
555	C2F						0 0	COMPUTER/CONTROL RM. AREA WOODWORK	1.0 LS	1.000	1000.00	1000.	2000.00	2000.	0.00	0.	0.	3000.
564	C2F						0 0	LOBBY/ENTRY/CHNG RM. AREA WOODWORK	1.0 LS	1.000	5000.00	5000.	20000.00	20000.	0.00	0.	0.	25000.
C2F								Category Direct Cost				6000.		22000.		0.	0.	28000.
441	C2G						0 0	MECHANICAL PENTHOUSE ROOF INSULATION	46086.0 SF	0.006	13.59	3758.	0.60	27652.	0.00	0.	0.	31409.
442	C2G						0 0	MECHANICAL PENTHOUSE SINGLE PLY ROOFING	46086.0 SF	0.172	13.59	107725.	2.95	135954.	0.00	0.	0.	243679.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J A	o c		Cntrct		- - - - L a b o r - - - -				Material		Const Equip		Sub		Item	
Structure				Trd b	c	Markup	Take-Off	Item	Quantity	Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd	Cntrct	Direct		
Item	1	2	3	4	ID	F	t	Tag	Description	Unit		Cost		Cost		Cost	Cost	Cost		Cost
443	C2G				0	0			MECHANICAL PENTHOUSE	46086.0	0.216	13.59		1.73		0.00				
									VAPOR BARRIER	SF		135283.		79729.		0.	0.			215011.
444	C2G				0	0			MECHANICAL PENTHOUSE	56144.0	0.008	33.26		0.39		0.00				
									BATT INSULATION	SF		14939.		21896.		0.	0.			36835.
445	C2G				0	0			MECHANICAL PENTHOUSE	56144.0	0.020	23.68		0.45		0.00				
									EXTERIOR FRAMING	SF		26590.		25265.		0.	0.			51855.
446	C2G				0	0			MECHANICAL PENTHOUSE	1.0		0.00		0.00		0.00		4000.		4000.
									SEALANTS	LS		0.		0.		0.				
447	C2G				0	0			MECHANICAL PENTHOUSE	10.0	10.700	23.68		205.00		0.00				
									DOORS	LS		2534.		2050.		0.	0.			4584.
448	C2G				0	0			MECHANICAL PENTHOUSE	10.0	1.000	23.68		120.00		0.00				
									HARDWARE	EA		237.		1200.		0.	0.			1437.
449	C2G				0	0			MECHANICAL PENTHOUSE	1381.0	0.010	13.59		7.00		0.00				
									FLASHING - PARAPET	LF		188.		9667.		0.	0.			9855.
458	C2G				0	0			D&D AREA, TRUCK AIRL	4320.0	0.148	23.68		4.50		0.00				
									OCK AND HOT WREHS.	SF		15140.		19440.		0.	0.			34580.
									EXT. INSL. FIN. SYS.											
460	C2G				0	0			D&D AREA, TRUCK AIRL	3750.0	0.216	23.68		1.73		0.00				
									OCK AND HOT WREHS.	SF		19181.		6488.		0.	0.			25668.
									VAPOR BARRIER											
461	C2G				0	0			D&D AREA, TRUCK AIRL	3750.0	0.008	33.26		0.39		0.00				
									OCK AND HOT WREHS.	SF		998.		1463.		0.	0.			2460.
									BATT INSULATION											
462	C2G				0	0			D&D AREA, TRUCK AIRL	1.0		0.00		0.00		0.00				
									OCK AND HOT WREHS.	LS		0.		0.		0.	0.	1000.		1000.
									SEALANTS											
495	C2G				0	0			PROCESS AREA BSMNT	1.0		0.00		0.00		0.00				
									SEALANTS	LS		0.		0.		0.	0.	5000.		5000.
505	C2G				0	0			PROCESS AREA 1st FLR	1.0		0.00		0.00		0.00				
									SEALANTS	LS		0.		0.		0.	0.	5000.		5000.
560	C2G				0	0			LOBBY/ENTRY/CHNG RM.	5085.0	0.008	33.26		0.39		0.00				
									INSULATION BATTS	SF		1353.		1983.		0.	0.			3336.
561	C2G				0	0			LOBBY/ENTRY/CHNG RM.	4565.0	0.216	23.68		1.73		0.00				
									VAPOR BARRIOR	SF		23349.		7897.		0.	0.			31247.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdw Structure				J ID	A F	o c	c Mark	c Tag	Take-Off Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4								Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
562	C2G						0	0		LOBBY/ENTRY/CHNG RM. ROOF INSULATION 9"	4565.0 SF	0.006	33.26	911.	0.60	2739.	0.00	0.	0.	3650.
563	C2G						0	0		LOBBY/ENTRY/CHNG RM. SINGLE PLY ROOF	4565.0 SF	0.172	13.59	10671.	2.95	13467.	0.00	0.	0.	24137.
565	C2G						0	0		LOBBY/ENTRY/CHNG RM. SEALANTS	1.0 LS	1.000	2000.00	2000.00	2000.00	2000.	0.00	0.	0.	4000.
588	C2G						0	0		CHEMISTRY LAB INSULATION BATTS	4260.0 SF	0.008	33.26	1134.	0.39	1661.	0.00	0.	0.	2795.
589	C2G						0	0		CHEMISTRY LAB VAPOR BARRIOR	4450.0 SF	0.216	23.68	22761.	1.73	7699.	0.00	0.	0.	30460.
590	C2G						0	0		CHEMISTRY LAB ROOF INSULATION 9"	4450.0 SF	0.006	33.26	888.	0.60	2670.	0.00	0.	0.	3558.
591	C2G						0	0		CHEMISTRY LAB SINGLE PLY ROOFING	4450.0 SF	0.172	13.59	10402.	2.95	13128.	0.00	0.	0.	23529.
613	C2G						0	0		TANK STORAGE 1 & 2 ROOF INSULATION	22100.0 SF	0.006	33.26	4410.	0.60	13260.	0.00	0.	0.	17670.
614	C2G						0	0		TANK STORAGE 1 & 2 SINGLE PLY ROOF	22100.0 SF	0.172	13.59	51658.	2.95	65195.	0.00	0.	0.	116853.
615	C2G						0	0		TANK STORAGE 1 & 2 VAPOR BARRIOR	22100.0 SF	0.216	23.68	113039.	1.73	38233.	0.00	0.	0.	151272.
616	C2G						0	0		TANK STORAGE 1 & 2 BATT INSULATION	32960.0 SF	0.008	33.26	8770.	0.39	12854.	0.00	0.	0.	21624.
619	C2G						0	0		TANK STORAGE 1 & 2 SEALANTS	7200.0 LF	1.580	20.75	236052.	1.50	10800.	0.00	0.	0.	246852.
623	C2G						0	0		TANK STORAGE 1 & 2 FLASHING PARAPET	825.0 LF	0.010	23.68	195.	7.00	5775.	0.00	0.	0.	5970.
624	C2G						0	0		TANK STORAGE 1 & 2 SKYLIGHTS	28.0 EA	2.670	23.68	1770.	300.00	8400.	0.00	0.	0.	10170.
628	C2G						0	0		COLD WAREHOUSE VAPOR BARRIOR	4490.0 SF	0.216	23.68	22966.	1.73	7768.	0.00	0.	0.	30734.
629	C2G						0	0		COLD WAREHOUSE ROOF INSULATION	4490.0 SF	0.006	33.26	896.	0.60	2694.	0.00	0.	0.	3590.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J A		Take-Off Item Description	Quantity Unit	Labor			Material Rate Ext'd Cost	Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4	o	c			Factor	Rate	Ext'd Cost		Rate	Ext'd Cost		
630	C2G				0	0	COLD WAREHOUSE BATT INSULATION	4020.0 SF	0.008	33.26 1070.		0.39 1568.	0.00 0.		0.	2637.
	C2G						Category Direct Cost				840866.		550593.	0.	15000.	1406459.
454	C2H				0	0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. OVRHD DOORS - EXT	4.0 EA	10.670	23.68 1011.		1185.00 4740.	0.00 0.		0.	5751.
455	C2H				0	0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. MAIN DOORS - EXT	4.0 EA	1.070	23.68 101.		205.00 820.	0.00 0.		0.	921.
456	C2H				0	0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. INT. DOORS	6.0 EA	1.070	23.68 152.		205.00 1230.	0.00 0.		0.	1382.
457	C2H				0	0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. DOOR HARDWARE	14.0 EA	1.000	23.68 332.		120.00 1680.	0.00 0.		0.	2012.
459	C2H				0	0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. DOOR FRAME	10.0 EA	2.460	23.68 583.		176.00 1760.	0.00 0.		0.	2343.
480	C2H				0	0	TECH. SUPPORT AREA DOORS - WOOD	50.0 EA	1.230	23.68 1456.		58.00 2900.	0.00 0.		0.	4356.
481	C2H				0	0	TECH. SUPPORT AREA DOORS - EXT	6.0 EA	1.070	23.68 152.		205.00 1230.	0.00 0.		0.	1382.
482	C2H				0	0	TECH. SUPPORT AREA WINDOWS & FRAMES	15.0 EA	1.600	23.68 568.		770.00 11550.	0.00 0.		0.	12118.
484	C2H				0	0	TECH. SUPPORT AREA HARDWARE	56.0 EA	1.000	23.68 1326.		120.00 6720.	0.00 0.		0.	8046.
491	C2H				0	0	PROCESS AREA BSMNT DOORS - METAL	4.0 EA	1.070	23.68 101.		205.00 820.	0.00 0.		0.	921.
503	C2H				0	0	PROCESS AREA 1st FLR DOORS - METAL	4.0 EA	1.070	23.68 101.		205.00 820.	0.00 0.		0.	921.
506	C2H				0	0	PROCESS AREA 1st FLR DOOR HARDWARE	8.0 EA	1.000	23.68 189.		120.00 960.	0.00 0.		0.	1149.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o I D F	A c t Tag	C ntrct Markup	Take-Off Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4						Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
553	C2H						0 0	COMPUTER/CONTROL RM. DOORS	2.0 EA	1.230	23.68	58.	58.00	116.	0.00	0.	0.	174.
554	C2H						0 0	COMPUTER/CONTROL RM. DOOR HARDWARE	2.0 EA	1.000	23.68	47.	120.00	240.	0.00	0.	0.	287.
566	C2H						0 0	LOBBY/ENTRY/CHNG RM. INTERIOR DOORS	15.0 EA	1.230	23.68	437.	58.00	870.	0.00	0.	0.	1307.
567	C2H						0 0	LOBBY/ENTRY/CHNG RM. EXTERIOR DOORS	4.0 EA	1.070	23.68	101.	205.00	820.	0.00	0.	0.	921.
568	C2H						0 0	LOBBY/ENTRY/CHNG RM. DOORS HARDWARE	19.0 EA	1.000	23.68	450.	120.00	2280.	0.00	0.	0.	2730.
569	C2H						0 0	LOBBY/ENTRY/CHNG RM. STOREFRONT (ENTRY)	160.0 SF	0.139	23.68	527.	20.50	3280.	0.00	0.	0.	3807.
570	C2H						0 0	LOBBY/ENTRY/CHNG RM. WINDOWS	250.0 SF	0.080	23.68	474.	15.50	3875.	0.00	0.	0.	4349.
592	C2H						0 0	CHEMISTRY LAB INTERIOR DOORS	25.0 EA	1.230	23.68	728.	58.00	1450.	0.00	0.	0.	2178.
593	C2H						0 0	CHEMISTRY LAB EXTERIOR DOORS	5.0 EA	1.070	23.68	127.	205.00	1025.	0.00	0.	0.	1152.
594	C2H						0 0	CHEMISTRY LAB DOOR HARDWARE	19.0 EA	1.000	23.68	450.	120.00	2280.	0.00	0.	0.	2730.
595	C2H						0 0	CHEMISTRY LAB WINDOWS	500.0 SF	0.080	23.68	947.	15.50	7750.	0.00	0.	0.	8697.
620	C2H						0 0	TANK STORAGE 1 & 2 DOORS	4.0 EA	1.070	23.68	101.	205.00	820.	0.00	0.	0.	921.
621	C2H						0 0	TANK STORAGE 1 & 2 OVERHEAD DOORS	4.0 EA	10.670	23.68	1011.	1185.00	4740.	0.00	0.	0.	5751.
622	C2H						0 0	TANK STORAGE 1 & 2 DOOR HARDWARE	4.0 EA	1.000	23.68	95.	120.00	480.	0.00	0.	0.	575.
632	C2H						0 0	COLD WAREHOUSE DOORS	2.0 EA	1.580	23.68	75.	205.00	410.	0.00	0.	0.	485.
633	C2H						0 0	COLD WAREHOUSE OVERHEAD DOORS	2.0 EA	10.670	29.12	621.	1185.00	2370.	0.00	0.	0.	2991.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdw Structure				J o ID	A c F	c t Tag	Take-Off Item Description	Quantity Unit	- - - - L a b o r - - - -			Material Rate Ext'd Cost	Const Equip Rate Ext'd Cost	Sub Cntrct Cost	Item Direct Cost
	1	2	3	4						Factor	Rate	Ext'd Cost				
634	C2H						0 0	COLD WAREHOUSE DOOR HARDWARE	2.0 EA	1.000	23.68	47.	120.00 240.	0.00 0.	0.	287.
635	C2H						0 0	COLD WAREHOUSE WINDOWS	5.0 EA	1.600	23.68	189.	770.00 3850.	0.00 0.	0.	4039.
C2H								Category Direct Cost				12559.	72126.	0.	0.	84685.
374	C2I						0 0	STRENGTHEN EXISTING STRUCTURE - PATCH CONC. FLOOR	8.0 CY	1.100	21.93	193.	65.00 520.	5.50 44.	0.	757.
453	C2I						0 0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. PLASITE PAINT FLOOR	4367.0 SF	0.062	20.75	5618.	0.95 4149.	0.00 0.	0.	9767.
463	C2I						0 0	D&D AREA, TRUCK AIRL OCK AND HOT WREHS. PAINT MISC.	1500.0 SF	0.007	20.75	218.	0.09 135.	0.00 0.	1500000.	1500353.
471	C2I						0 0	TECH. SUPPORT AREA 5/8" GYP BOARD PARTITIONS	2000.0 SF	0.017	23.68	805.	0.31 620.	0.00 0.	0.	1425.
472	C2I						0 0	TECH. SUPPORT AREA FRAMING PARTITIONS	2000.0 SF	0.019	23.68	900.	0.31 620.	0.00 0.	0.	1520.
473	C2I						0 0	TECH. SUPPORT AREA FRAMING EXT WALLS	8480.0 SF	0.019	23.68	3815.	0.31 2629.	0.00 0.	0.	6444.
474	C2I						0 0	TECH. SUPPORT AREA GYP BOARD EXT WALLS	8480.0 SF	0.017	23.68	3414.	0.26 2205.	0.00 0.	0.	5619.
475	C2I						0 0	TECH. SUPPORT AREA SUSPENDED CEILING	19784.0 SF	0.021	23.68	9838.	0.86 17014.	0.00 0.	0.	26852.
476	C2I						0 0	TECH. SUPPORT AREA CARPET	1099.0 SY	0.140	23.68	3643.	20.80 22859.	0.00 0.	0.	26503.
477	C2I						0 0	TECH. SUPPORT AREA VCT	9890.0 SF	0.035	23.68	8197.	1.30 12857.	0.00 0.	0.	21054.
478	C2I						0 0	TECH. SUPPORT AREA BASE	2800.0 LF	0.025	23.68	1658.	0.50 1400.	0.00 0.	0.	3058.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o I D	A c F	C t r a g	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4						Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
479	C2I					0	0	TECH. SUPPORT AREA PAINT	56000.0 SF	0.007	20.75		0.09		0.00			13174.
483	C2I					0	0	TECH. SUPPORT AREA WINDOWS COVERINGS	375.0 SF	0.018	23.68		0.40		0.00	0.	0.	310.
485	C2I					0	0	TECH. SUPPORT AREA WOODWORK	1.0 LS	1.000	3000.00		5000.00		0.00	0.	0.	8000.
486	C2I					0	0	TECH. SUPPORT AREA REFINISH STAIRS	1.0 LS	1.000	1000.00		1000.00		0.00	0.	0.	2000.
492	C2I					0	0	PROCESS AREA BSMNT PAINT - PLACITE	29675.0 SF	0.062	20.75		0.95		0.00	0.	0.	66368.
500	C2I					0	0	PROCESS AREA 1st FLR PREP FOR PAINT	9100.0 SF	0.009	20.75		0.14		0.00	0.	0.	2973.
501	C2I					0	0	PROCESS AREA 1st FLR FILL IN WINDOWS	1.0 LS	1.000	1400.00		0.00		0.00	0.	0.	1400.
502	C2I					0	0	PROCESS AREA 1st FLR PAINT - PLACITE	9100.0 SF	0.062	20.75		0.95		0.00	0.	0.	20352.
546	C2I					0	0	COMPUTER/CONTROL RM. INTERIOR PARTITION	260.0 SF	0.017	23.68		0.31		0.00	0.	0.	185.
547	C2I					0	0	COMPUTER/CONTROL RM. INTERIOR FRAMING	260.0 SF	0.019	23.68		0.31		0.00	0.	0.	198.
548	C2I					0	0	COMPUTER/CONTROL RM. FRAMING EXT. WALLS	200.0 SF	0.019	23.68		0.31		0.00	0.	0.	152.
549	C2I					0	0	COMPUTER/CONTROL RM. GYP BOARD EXT. WALL	200.0 SF	0.017	23.68		0.26		0.00	0.	0.	133.
550	C2I					0	0	COMPUTER/CONTROL RM. SUSPENDED CEILING	1010.0 SF	0.021	23.68		0.86		0.00	0.	0.	1371.
551	C2I					0	0	COMPUTER/CONTROL RM. VCT	1010.0 SF	0.035	23.68		1.30		0.00	0.	0.	2150.
552	C2I					0	0	COMPUTER/CONTROL RM. PAINT	1440.0 SF	0.007	20.75		0.09		0.00	0.	0.	339.
556	C2I					0	0	COMPUTER/CONTROL RM. BASE	140.0 LF	0.025	23.68		0.50		0.00	0.	0.	153.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J A	o c		Markup		Take-Off Item	Description	Quantity	Unit	L a b o r			Material		Const Equip		Sub	Item
Item	1	2	3	4	Trd	b	c	Tag					Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd		
					ID	F	t								Cost		Cost		Cost	Cntrct	Direct
557	C2I				0	0				COMPUTER/CONTROL RM.	1.0	LS	1.000	200.00		0.00		0.00			
										FILL IN WINDOW				200.		0.		0.		0.	200.
558	C2I				0	0				LOBBY/ENTRY/CHNG RM.	5085.0	SF	0.148	23.68		4.50		0.00			
										EXTERIOR WALLS EIFS				17821.		22883.		0.		0.	40704.
559	C2I				0	0				LOBBY/ENTRY/CHNG RM.	5085.0	SF	0.020	23.68		0.45		0.00			
										EXTERIOR FRAMING				2408.		2288.		0.		0.	4697.
571	C2I				0	0				LOBBY/ENTRY/CHNG RM.	6350.0	SF	0.019	23.68		0.31		0.00			
										FRAMING - INT				2857.		1969.		0.		0.	4825.
572	C2I				0	0				LOBBY/ENTRY/CHNG RM.	12700.0	SF	0.017	23.68		0.31		0.00			
										GYP BOARD PARTITION				5113.		3937.		0.		0.	9050.
										(5/8")											
573	C2I				0	0				LOBBY/ENTRY/CHNG RM.	12700.0	SF	0.007	20.75		0.09		0.00			
										PAINT WALLS				1845.		1143.		0.		0.	2988.
574	C2I				0	0				LOBBY/ENTRY/CHNG RM.	1.0	LS	1.000	1000.00		200.00		0.00			
										PAINT MISC.				1000.		200.		0.		0.	1200.
575	C2I				0	0				LOBBY/ENTRY/CHNG RM.	3185.0	SF	0.087	23.68		3.25		0.00			
										CERAMIC TILE FLOOR				6562.		10351.		0.		0.	16913.
576	C2I				0	0				LOBBY/ENTRY/CHNG RM.	2000.0	SF	0.084	23.68		2.15		0.00			
										CERAMIC TILE WALLS				3978.		4300.		0.		0.	8278.
577	C2I				0	0				LOBBY/ENTRY/CHNG RM.	635.0	LF	0.025	23.68		0.50		0.00			
										BASE				376.		318.		0.		0.	693.
578	C2I				0	0				LOBBY/ENTRY/CHNG RM.	800.0	SF	0.133	23.68		2.90		0.00			
										QUARRY TILE				2520.		2320.		0.		0.	4840.
579	C2I				0	0				LOBBY/ENTRY/CHNG RM.	65.0	SY	0.140	23.68		20.80		0.00			
										CARPET				215.		1352.		0.		0.	1567.
580	C2I				0	0				LOBBY/ENTRY/CHNG RM.	4565.0	SF	0.021	23.68		0.86		0.00			
										ACOUSTICAL CEILING				2270.		3926.		0.		0.	6196.
581	C2I				0	0				LOBBY/ENTRY/CHNG RM.	1000.0	SF	0.017	23.68		0.75		0.00			
										VINYL WALL COVERING				403.		750.		0.		0.	1153.
582	C2I				0	0				LOBBY/ENTRY/CHNG RM.	1.0	LS	1.000	1000.00		4000.00		0.00			
										TOILET PARTITION				1000.		4000.		0.		0.	5000.
583	C2I				0	0				LOBBY/ENTRY/CHNG RM.	1.0	LS	1.000	500.00		2000.00		0.00			
										TOILET ACCESORIES				500.		2000.		0.		0.	2500.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdw Structure				J ID	A F	o t	c Tag	c Markup	c Take-Off	Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4									Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
584	C2I							0	0		LOBBY/ENTRY/CHNG RM. SPECIALITIES	1.0 LS	1.000	1000.00		5000.00	5000.	0.00	0.	0.	6000.
585	C2I							0	0		LOBBY/ENTRY/CHNG RM. SIGNAGE	1.0 LS	1.000	750.00	750.	2000.00	2000.	0.00	0.	0.	2750.
586	C2I							0	0		CHEMISTRY LAB EXTERIOR WALLS EIFS	4260.0 SF	0.148	23.68	14930.	4.50	19170.	0.00	0.	0.	34100.
587	C2I							0	0		CHEMISTRY LAB EXTERIOR FRAMING	4260.0 SF	0.020	23.68	2018.	0.45	1917.	0.00	0.	0.	3935.
596	C2I							0	0		CHEMISTRY LAB FRAMING INT.	5580.0 SF	0.019	23.68	2511.	0.31	1730.	0.00	0.	0.	4240.
597	C2I							0	0		CHEMISTRY LAB GYP BOARD 5/8"	11160.0 SF	0.017	23.68	4493.	0.31	3460.	0.00	0.	0.	7952.
598	C2I							0	0		CHEMISTRY LAB PAINT WALLS	11160.0 SF	0.007	20.75	1621.	0.09	1004.	0.00	0.	0.	2625.
599	C2I							0	0		CHEMISTRY LAB PAINT MISC.	1.0 LS	1.000	1000.00	1000.	200.00	200.	0.00	0.	0.	1200.
600	C2I							0	0		CHEMISTRY LAB CERAMIC TILE FLOOR	1800.0 SF	0.087	23.68	3708.	3.25	5850.	0.00	0.	0.	9558.
601	C2I							0	0		CHEMISTRY LAB CERAMIC TILE WALLS	800.0 SF	0.084	23.68	1591.	2.15	1720.	0.00	0.	0.	3311.
602	C2I							0	0		CHEMISTRY LAB VCT	3650.0 SF	0.035	23.68	3025.	1.30	4745.	0.00	0.	0.	7770.
603	C2I							0	0		CHEMISTRY LAB BASE	600.0 LF	0.025	23.68	355.	0.50	300.	0.00	0.	0.	655.
604	C2I							0	0		CHEMISTRY LAB RAISED FLOOR	1200.0 SF	0.032	23.68	909.	11.00	13200.	0.00	0.	0.	14109.
605	C2I							0	0		CHEMISTRY LAB ACOUSTICAL CEILING	4450.0 SF	0.021	23.68	2213.	0.86	3827.	0.00	0.	0.	6040.
606	C2I							0	0		CHEMISTRY LAB LAB EQUIPMENT BASE, WALL	295.0 LF	0.889	23.68	6210.	200.00	59000.	0.00	0.	0.	65210.
609	C2I							0	0		CHEMISTRY LAB TOILET ACCESSORIES	1.0 LS	1.000	500.00	500.	1000.00	1000.	0.00	0.	0.	1500.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdw Structure				J o c t r a c t	A c c o u n t	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
610 C2I					0	0	CHEMISTRY LAB	1.0	1.000	500.00		2000.00		0.00			
							TOILET PARTITIONS	LS		500.		2000.		0.		0.	2500.
612 C2I					0	0	CHEMISTRY LAB	1.0	1.000	750.00		200.00		0.00			
							SIGNAGE	LS		750.		200.		0.		0.	950.
617 C2I					0	0	TANK STORAGE 1 & 2	32960.0	0.020	23.68		0.45		0.00			
							EXTERIOR FRAMING	SF		15610.		14832.		0.		0.	30442.
618 C2I					0	0	TANK STORAGE 1 & 2	32960.0	0.040	29.12		10.65		0.77			
							EXTERIOR PANEL, PRECAST	SF		38392.		351024.		25379.		0.	414795.
631 C2I					0	0	COLD WAREHOUSE	4020.0	0.031	30.29		2.85		0.00			
							METAL LINER	SF		3775.		11457.		0.		0.	15232.
C2I							Category Direct Cost				260527.		682336.		25423.	1500000.	2468286.
493 C2L					0	0	PROCESS AREA BSMNT	1.0		0.00		0.00		0.00			
							NEW ELEVATOR	LS		0.		0.		0.		30000.	30000.
C2L							Category Direct Cost				0.		0.		0.	30000.	30000.
1 C2M					0	0	374 TON CHILLER.	2.0	950.000	29.96		100000.00		0.00			
								EA		56924.		200000.		0.		0.	256924.
2 C2M					0	0	CRANE TO SET 374 TON CHILLER.	2.0	8.000	22.99		0.00		75.00#			
								EA		368.		0.		1200.		0.	1568.
3 C2M					0	0	CHILLER CIRC. PUMPS (900 GPM, 35 FT. HEAD, 15 HP)	4.0	14.200	29.96		2210.00		0.00			
								EA		1702.		8840.		0.		0.	10542.
4 C2M					0	0	468 TON COOLING TOWER, 1130 GPM, 7.5 HP	2.0	150.000	29.96		21050.00		0.00			
							FAN	EA		8988.		42100.		0.		0.	51088.
5 C2M					0	0	PRIMARY CWS PUMP, 1200 GPM, 55 FT HEAD, 25 HP	2.0	16.000	29.96		2925.00		0.00			
								EA		959.		5850.		0.		0.	6809.
6 C2M					0	0	COOLING TOWER PUMP, 1130 GPM, 70 FT HEAD, 40 HP	2.0	36.000	29.96		6375.00		0.00			
								EA		2157.		12750.		0.		0.	14907.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J ID	A F	o b	c t	c Markup	Take-Off Item Description	Quantity	Unit	Labor			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4									Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
7	C2M						0	0		BOILER CIRC. PUMP, 4 60 GPM, 9 FT HEAD, 3 HP	1.0	EA	8.000	29.96	240.	955.00	955.	0.00	0.	0.	1195.
8	C2M						0	0		BOILER CIRC. PUMP, 6 80 GPM, 9 FT HEAD, 3 HP	2.0	EA	8.000	29.96	479.	955.00	1910.	0.00	0.	0.	2389.
9	C2M						0	0		PRIMARY HWS PUMP, 11 40 GPM, 68 FT HEAD, 40 HP	2.0	EA	36.000	29.96	2157.	6375.00	12750.	0.00	0.	0.	14907.
10	C2M						0	0		SUPPLY AIR FAN, 34,0 00 CFM, 2.98 TSP, 10 0 HP, CLASS II	1.0	EA	35.000	30.29	1060.	19000.00	19000.	0.00	0.	0.	20060.
11	C2M						0	0		R.A. FAN 32,000 CFM .66 TSP, 100 HP, CLA SS II	2.0	EA	35.000	30.29	2120.	18250.00	36500.	0.00	0.	0.	38620.
12	C2M						0	0		SUPPLY AIR FANS, 65, 000 CFM, 5.6 TSP, 100 HP, CLASS II	0.0			0.00	0.	0.00	0.	0.00	0.	0.	0.
13	C2M						0	0		R.A. FANS, 32,500 CF M, 6.9 TSP, 100 HP, CLASS II	3.0	EA	35.000	30.29	3180.	18250.00	54750.	0.00	0.	0.	57930.
14	C2M						0	0		EXH. FANS 65,000 CFM , 6.9 TSP, 100 HP, C LASS II	2.0	EA	55.000	30.29	3332.	19900.00	39800.	0.00	0.	0.	43132.
15	C2M						0	0		EXH. FANS 16,000 CFM , 9.7 TSP, 40 HP, CL ASS II	1.0	EA	24.000	30.29	727.	9450.00	9450.	0.00	0.	0.	10177.
16	C2M						0	0		SUPPLY AIR FAN, 14,0 00 CFM, 5.6 TSP, 20 HP, CLASS II	1.0	EA	16.000	30.29	485.	4450.00	4450.	0.00	0.	0.	4935.
17	C2M						0	0		R.A. FAN, 7,000 CFM, 6.9 TSP, 10 HP, CLA SS II	1.0	EA	16.000	30.29	485.	3700.00	3700.	0.00	0.	0.	4185.
18	C2M						0	0		R.A. FAN, 7,000 CFM, 9.7 TSP, 10 HP, CLA SS III	1.0	EA	16.000	30.29	485.	4950.00	4950.	0.00	0.	0.	5435.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	c Cntrct		Take-Off Item	Quantity	- - - - L a b o r - - - -			Material		Const Equip		Sub	Item
Item	1	2	3	4	Trd	b	c			Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd	Cntrct	
					ID	F	t	Tag	Unit			Cost		Cost		Cost	Cost	Cost
19	C2M						0	0 SUPPLY FAN, 76,000 CFM, 5.6 TSP, 100 HP, CLASS II	1.0 EA	62.000	30.29	1878.	21450.00	21450.	0.00	0.	0.	23328.
20	C2M						0	0 EXH & RETURN FAN, 76,000 CFM, 6.9 TSP, 125 HP, CLASS II	2.0 EA	62.000	30.29	3756.	21450.00	42900.	0.00	0.	0.	46656.
21	C2M						0	0 SUPPLY AIR FAN, 77,000 CFM, 5.6 TSP, 100 HP, CLASS II	1.0 EA	62.000	30.29	1878.	21450.00	21450.	0.00	0.	0.	23328.
22	C2M						0	0 RETURN AIR FAN, 38,000 CFM, 6.9 TSP, 75 HP, CLASS II	1.0 EA	35.000	30.29	1060.	21450.00	21450.	0.00	0.	0.	22510.
23	C2M						0	0 EXHAUST FAN, 77,000 CFM, 6.9 TSP, 100 HP, CLASS II	1.0 EA	62.000	30.29	1878.	21450.00	21450.	0.00	0.	0.	23328.
24	C2M						0	0 ROOF TOP EXHAUST FAN, 5100 CFM, 0.52 TSP, 1 HP, CLASS II	10.0 EA	6.700	30.29	2029.	1230.00	12300.	0.00	0.	0.	14329.
25	C2M						0	0 UNIT HEATERS, 33,000 BTUH HWS 1/8 HP	16.0 EA	2.130	30.29	1032.	400.00	6400.	0.00	0.	0.	7432.
26	C2M						0	0 A/C UNIT, 2500 CFM, 0.5 TSP, 7 1/2 TON	1.0 EA	60.000	30.29	1817.	14900.00	14900.	0.00	0.	0.	16717.
27	C2M						0	0 LOUVER - 264 S.F., 3 FT X 8 FT	264.0 SF	0.200	30.29	1599.	35.40	9346.	0.00	0.	0.	10945.
29	C2M						0	0 HEATING COIL - 112 S.F.	1.0 EA	51.660	29.96	1548.	6027.00	6027.	0.00	0.	0.	7575.
30	C2M						0	0 DIFFUSERS - 400 CFM, 12" X 12" NECK	165.0 EA	0.667	30.29	3334.	52.25	8621.	0.00	0.	0.	11955.
31	C2M						0	0 COOLING COIL - 132 S.F.	1.0 EA	140.000	29.96	4194.	10752.00	10752.	0.00	0.	0.	14946.
32	C2M						0	0 EXHAUST AIR REGISTER - 800 CFM, 24" X 12"	83.0 EA	0.471	30.29	1184.	34.80	2888.	0.00	0.	0.	4073.
36	C2M						0	0 LOUVER - 528 SF 66' X 8'	528.0 SF	0.200	30.29	3199.	35.40	18691.	0.00	0.	0.	21890.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdw Structure				J A	o c Cntrct		Take-Off Item Description	Quantity Unit	- - - - L a b o r - - - -			Material Rate Ext'd Cost	Const Equip Rate Ext'd Cost	Sub Cntrct Cost	Item Direct Cost
Item	1	2	3	4	Trd ID	b F	c t Tag		Factor	Rate	Ext'd Cost				
38	C2M				0	0	HEATING COIL - SIZE = 220 SF	1.0 EA	124.000	29.96	3715.	8500.00	0.00		
39	C2M				0	0	COOLING COIL - SIZE = 264 SF	1.0 EA	400.000	29.96	11984.	20275.00	0.00	0.	12215.
40	C2M				0	0	DIFFUSERS - 12" X 12 " NECK	330.0 EA	0.667	30.29	6667.	52.25	0.00	0.	32259.
41	C2M				0	0	EXHAUST AIR REGISTER	166.0 EA	0.471	30.29	2368.	34.80	0.00	0.	23910.
44	C2M				0	0	LOUVER - 56 SF 14" X 4'	56.0 EA	0.200	30.29	2368.	35.40	0.00	0.	8145.
46	C2M				0	0	COOLING COIL - 28 SF	1.0 EA	40.000	29.96	339.	3072.00	0.00	0.	2322.
47	C2M				0	0	EXHAUST AIR REGISTER - 24" X 12"	18.0 EA	0.471	30.29	1198.	34.80	0.00	0.	4270.
49	C2M				0	0	LOUVER 304 SF 38' X 8'	304.0 LF	0.200	30.29	257.	35.40	0.00	0.	883.
50	C2M				0	0	HEATING COIL 127 SF	1.0 EA	51.660	29.96	1842.	6027.00	0.00	0.	12603.
51	C2M				0	0	COOLING COIL 152 SF	1.0 EA	140.000	29.96	1548.	10752.00	0.00	0.	7575.
52	C2M				0	0	DIFFUSER - 12" X 12"	190.0 EA	0.667	30.29	4194.	52.25	0.00	0.	14946.
53	C2M				0	0	EXHAUST AIR REGISTER - 24" X 12"	95.0 EA	0.471	30.29	3839.	34.80	0.00	0.	13766.
55	C2M				0	0	LOUVER - 304 SF - 38 ' X 8'	304.0 LF	0.200	29.96	1355.	35.40	0.00	0.	4661.
56	C2M				0	0	BOILER - 7,200 MBH O UTPUT	2.0 EA	160.000	29.96	1822.	24000.00	0.00	0.	12583.
57	C2M				0	0	BOILER - 4,800 MBH O UTPUT	1.0 EA	160.000	29.96	9587.	18500.00	0.00	0.	57587.
58	C2M				0	0	PROCESS BOILER 2884 MBH OUTPUT	3.0 EA	160.000	29.96	4794.	13917.00	0.00	0.	23294.
											14381.	41751.	0.	0.	56132.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o b I D	A c t i v e	C n t r a c t	M a r k u p	Take-Off Item Description	Quantity	Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4								Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
59	C2M						0	0	ROOF DRAIN PIPE - 8"	240.0	LF	0.464	29.96	3336.	14.21	3410.	0.00	0.	0.	6747.
60	C2M						0	0	ROOF DRAIN PIPE - 6"	400.0	LF	0.304	29.96	3643.	8.62	1134.	0.00	0.	0.	7091.
61	C2M						0	0	ROOF DRAIN PIPE - 4"	700.0	LF	0.276	29.96	5788.	4.57	3199.	0.00	0.	0.	8987.
62	C2M						0	0	DEIONIZED WATER - 3/4"	140.0	LF	0.235	29.96	986.	8.10	1134.	0.00	0.	0.	2120.
63	C2M						0	0	DEIONIZED WATER - 1/2"	42.0	LF	0.182	29.96	229.	6.30	265.	0.00	0.	0.	494.
64	C2M						0	0	REFRIGERANT LIQUID - 1/2"	120.0	LF	0.080	29.96	288.	0.86	103.	0.00	0.	0.	391.
65	C2M						0	0	REFRIGERANT SUCTION - 1-1/8"	120.0	LF	0.144	29.96	518.	2.46	295.	0.00	0.	0.	813.
66	C2M						0	0	2-1/2" BLACK STEEL NATURAL GAS PIPE	405.0	LF	0.320	29.96	3883.	4.78	1936.	0.00	0.	0.	5819.
67	C2M						0	0	2" BLACK STEEL NATURAL GAS PIPE	132.0	LF	0.250	29.96	989.	2.91	384.	0.00	0.	0.	1373.
68	C2M						0	0	1-1/2" BLACK STEEL NATURAL GAS PIPE	35.0	LF	0.200	29.96	210.	2.17	76.	0.00	0.	0.	286.
69	C2M						0	0	1-1/4" BLACK STEEL NATURAL GAS PIPE	20.0	LF	0.180	29.96	108.	1.85	37.	0.00	0.	0.	145.
70	C2M						0	0	1" BLACK STEEL NATURAL GAS PIPE	187.0	LF	0.151	29.96	846.	1.49	279.	0.00	0.	0.	1125.
71	C2M						0	0	3/4" BLACK STEEL NATURAL GAS PIPE	530.0	LF	0.131	29.96	2080.	1.06	562.	0.00	0.	0.	2642.
72	C2M						0	0	1-1/2" COPPER - COMPRESSED AIR	378.0	LF	0.200	29.96	2265.	3.76	1421.	0.00	0.	0.	3686.
73	C2M						0	0	1-1/4" COPPER - COMPRESSED AIR	20.0	LF	0.180	29.96	108.	2.72	54.	0.00	0.	0.	162.
74	C2M						0	0	1" COPPER - COMPRESSED AIR	555.0	LF	0.151	29.96	2511.	1.88	1043.	0.00	0.	0.	3554.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn Structure				J o c	A c t	Take-Off Item		Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
Item	1	2	3	4	Trd ID	b F	c Markup Tag		Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
75	C2M						0 0 3/4" COPPER - COMPER SSED AIR	211.0 LF	0.131	29.96	828.	1.35	285.	0.00	0.		1113.
76	C2M						0 0 VACUUM COPPER 2"	176.0 LF	0.182	29.96	960.	5.73	1008.	0.00	0.		1968.
77	C2M						0 0 VACUUM COPPER - 3/4"	577.0 LF	0.103	29.96	1781.	1.35	779.	0.00	0.		2560.
78	C2M						0 0 ACID WASTE GLASS - 4 "	450.0 LF	0.533	29.96	7186.	18.64	8388.	0.00	0.		15574.
79	C2M						0 0 ACID WASTE GLASS - 3 "	384.0 LF	0.410	29.96	4717.	10.56	4055.	0.00	0.		8772.
80	C2M						0 0 ACID WASTE GLASS - 2 "	510.0 LF	0.364	29.96	5562.	7.72	3937.	0.00	0.		9499.
81	C2M						0 0 SANITARY SEWER - 4"	840.0 LF	0.400	29.96	10067.	19.06	16010.	0.00	0.		26077.
82	C2M						0 0 SANITARY SEWER - 3"	384.0 LF	0.276	29.96	3175.	10.59	4067.	0.00	0.		7242.
83	C2M						0 0 SANITARY SEWER - 2"	1095.0 LF	0.182	29.96	5971.	5.73	6274.	0.00	0.		12245.
84	C2M						0 0 1" POLY - DISTILLED WATER	75.0 LF	0.258	29.96	580.	9.60	720.	0.00	0.		1300.
85	C2M						0 0 3/4" POLY - DISTILLE D WATER	435.0 LF	0.235	29.96	3063.	8.10	3524.	0.00	0.		6586.
86	C2M						0 0 1/2" POLY - DISTILLE D WATER	385.0 LF	0.182	29.96	2099.	6.30	2426.	0.00	0.		4525.
87	C2M						0 0 2-1/2" COPPER (SCH 4 0) - HOT WATER	126.0 LF	0.250	29.96	944.	8.05	1014.	0.00	0.		1958.
88	C2M						0 0 2" COPPER (SCH 40) - HOT WATER	64.0 LF	0.182	29.96	349.	5.73	367.	0.00	0.		716.
89	C2M						0 0 1-1/2" COPPER (SCH 4 0) - HOT WATER	680.0 LF	0.148	29.96	3015.	3.76	2557.	0.00	0.		5572.
90	C2M						0 0 1" COPPER (SCH 40) - HOT WATER	741.0 LF	0.133	29.96	2953.	1.88	1393.	0.00	0.		4346.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J A		Take-Off Item Description	Quantity	Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4	Trd b ID F	c Markup Tag				Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
91 C2M					0	0	3/4" COPPER (SCH 40) - HOT WATER	515.0	LF	1.030	29.96	15892.	1.35	695.	0.00	0.	0.	16588.
92 C2M					0	0	3" COPPER (SCH 40) - COLD WATER	110.0	LF	0.276	29.96	910.	10.59	1165.	0.00	0.	0.	2074.
93 C2M					0	0	2-1/2" COPPER (SCH 40) - COLD WATER	117.0	LF	0.250	29.96	876.	8.05	942.	0.00	0.	0.	1818.
94 C2M					0	0	2" COPPER (SCH 40) - COLD WATER	110.0	LF	0.182	29.96	600.	5.73	630.	0.00	0.	0.	1230.
95 C2M					0	0	1-1/2" COPPER (SCH 40) - COLD WATER	96.0	LF	0.148	29.96	426.	3.76	361.	0.00	0.	0.	787.
96 C2M					0	0	1-1/4" COPPER (SCH 40) - COLD WATER	1240.0	LF	0.133	29.96	4941.	2.72	3373.	0.00	0.	0.	8314.
97 C2M					0	0	1" COPPER (SCH 40) - COLD WATER	1454.0	LF	0.114	29.96	4966.	1.88	2734.	0.00	0.	0.	7700.
98 C2M					0	0	3/4" COPPER (SCH 40) - COLD WATER	660.0	LF	0.103	29.96	2037.	1.35	891.	0.00	0.	0.	2928.
512 C2M					0	0	FIRE PROTECTION 6" RISERS	5.0	EA	45.000	29.96	6741.	2561.00	12805.	0.00	0.	0.	19546.
513 C2M					0	0	FIRE SPRINKLER, ORDINARY HAZARD	101762.0	SF	0.030	29.96	91464.	0.27	27476.	0.00	0.	0.	118939.
514 C2M					0	0	SEWAGE EJECTOR FOR FLOOR DRAINS	1.0	EA	21.000	29.96	629.	2050.00	2050.	0.00	0.	0.	2679.
516 C2M					0	0	COMPRESSOR 90 SCFM 125 PSI	4.0	EA	40.000	29.96	4794.	11100.00	44400.	0.00	0.	0.	49194.
517 C2M					0	0	INSULATION PIPE/DUCT (10% OF MECH EXCLUDING FILTER	1.0	LS		0.00	0.	213634.00	213634.	0.00	0.	0.	213634.
518 C2M					0	0	FIRE DAMPERS	1.0	LS		0.00	0.	5500.00	5500.	0.00	0.	0.	5500.
519 C2M					0	0	HOT WATER CIRC PUMPS 1 HP	2.0	EA	4.000	29.96	240.	1715.00	3430.	0.00	0.	0.	3670.
520 C2M					0	0	STERILLIZATION	1.0	LS		0.00	0.	5000.00	5000.	0.00	0.	0.	5000.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o b I D F	A c t i v e	C n t r c t	M a r k u p	T a k e - O f f	I t e m	D e s c r i p t i o n	Q u a n t i t y	U n i t	L a b o r			M a t e r i a l		C o n s t E q u i p		S u b C n t r c t C o s t	I t e m D i r e c t C o s t
	1	2	3	4										F a c t o r	R a t e	E x t ' d C o s t	R a t e	E x t ' d C o s t	R a t e	E x t ' d C o s t		
521	C2M						0	0			EXPANSION TANKS	2.0	EA	3.200	29.96	192.	550.00	1100.	0.00	0.	0.	1292.
522	C2M						0	0			AIR ELIMINATORS	3.0	EA	4.000	29.96	360.	500.00	1500.	0.00	0.	0.	1860.
523	C2M						0	0			MISC VALVES AND FITTINGS	1.0	LS		0.00	0.	30000.00	30000.	0.00	0.	0.	30000.
524	C2M						0	0			TEST AND BALANCE	1180.0	EA	0.500	30.29	17871.	40.00	47200.	0.00	0.	0.	65071.
525	C2M						0	0			BOILER WATER TREATMENT	1.0	LS		0.00	0.	5000.00	5000.	0.00	0.	0.	5000.
526	C2M						0	0			ACID WASTE TANK 1000 GAL	1.0	EA	12.000	29.96	360.	4980.00	4980.	0.00	0.	0.	5340.
527	C2M						0	0			ACID WASTE PUMP 1 HP	1.0	EA	7.000	29.96	210.	1320.00	1320.	0.00	0.	0.	1530.
528	C2M						0	0			STEAM AND CONDENSATE PIPING	400.0	LF	0.774	29.96	9276.	21.94	8776.	0.00	0.	0.	18052.
529	C2M						0	0			PRESSURE TEST	1.0	LS		0.00	0.	5000.00	5000.	0.00	0.	0.	5000.
530	C2M						0	0			MERCURY TEST	1.0	LS		0.00	0.	5000.00	5000.	0.00	0.	0.	5000.
531	C2M						0	0			POTABLE WATER BACKFLOW PREVENTOR	1.0	EA	8.000	29.96	240.	2900.00	2900.	0.00	0.	0.	3140.
532	C2M						0	0			STEAM TO STEAM HEAT EXCHANGER (PROCESS)	1.0	EA	120.000	29.96	3595.	30000.00	30000.	0.00	0.	0.	33595.
533	C2M						0	0			HEAT EXCHANGER (PROCESS WATER)	3.0	EA	20.000	29.96	1798.	6000.00	18000.	0.00	0.	0.	19798.
534	C2M						0	0			PROCESS CHILLER 399 TONS	2.0	EA	950.000	29.96	56924.	100000.00	200000.	0.00	0.	0.	256924.
535	C2M						0	0			PROCESS COOLING TOWER 959 GPM	1.0	EA	150.000	29.96	4494.	21050.00	21050.	0.00	0.	0.	25544.
536	C2M						0	0			CWS PUMP 25 HP	2.0	EA	16.000	29.96	959.	2925.00	5850.	0.00	0.	0.	6809.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c ID F	A c t Tag	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
537	C2M				0	0	PUMP COOLING TOWER (PROCESS) 40 HP	2.0 EA	72.000	29.96	4314.	6375.00	12750.	0.00	0.	0.	17064.
538	C2M				0	0	HEPA FILTERS 3X6 BANK WITH STAINLESS STEEL HOUSING	82.0 BANK	8.000	30.29	19870.	32190.00	2639580.	0.00	0.	0.	2659450.
539	C2M				0	0	TEST SECTIONS 3X6 BANK	302.0 BANK	8.000	30.29	73181.	33618.00	10152636.	0.00	0.	0.	10225817.
540	C2M				0	0	PRE FILTERS 3X6 BANK	82.0 BANK	2.000	30.29	4968.	200.00	16400.	0.00	0.	0.	21368.
541	C2M				0	0	SPARK ARRESTER 3X6 BANK	64.0 BANK	4.000	30.29	7754.	14800.00	947200.	0.00	0.	0.	954954.
542	C2M				0	0	CHARCOAL FILTERS 3X6 BANK WITH STAINLESS STEEL HOUSING	6.0 BANK	10.000	30.29	1817.	35962.00	215772.	0.00	0.	0.	217589.
543	C2M				0	0	DEMISTER 3X6 BANK	64.0 BANK	4.000	30.29	7754.	14800.00	947200.	0.00	0.	0.	954954.
544	C2M				0	0	ROOF DRAIN MAIN LINE 10"	60.0 LF	0.525	29.96	944.	22.88	1373.	0.00	0.	0.	2317.
545	C2M				0	0	ROOF DRAINS	11.0 EA	2.000	29.96	659.	165.00	1815.	0.00	0.	0.	2474.
867	C2M				0	0	PLATE & FRAME HEAT EXCHANGERS FOR CHILLED WATER	2.0 EA	40.000	29.96	2397.	38000.00	76000.	0.00	0.	0.	78397.
868	C2M				0	0	PLATE & FRAME HEAT EXCHANGERS FOR PROCESS COOLING	3.0 EA	20.000	29.96	1798.	14000.00	42000.	0.00	0.	0.	43798.
869	C2M				0	0	HOT WATER HEATER - 9 BGPM, 95 GAL	4.0 EA	5.800	29.96	695.	810.00	3240.	0.00	0.	0.	3935.
870	C2M				0	0	VAV TERMINAL - 1000 CFM	155.0 EA	10.000	30.29	46950.	700.00	108500.	0.00	0.	0.	155450.
871	C2M				0	0	VACUUM PUMP - 30 HP	2.0 EA	40.000	29.96	2397.	15100.00	30200.	0.00	0.	0.	32597.
872	C2M				0	0	GAS PRESSURE REDUCING STATION - HIGH TO MEDIUM	1.0 EA	8.000	29.96	240.	1000.00	1000.	0.00	0.	0.	1240.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c t r a c t	A c c o u n t	Markup	Take-Off	Item Description	Quantity	Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4								Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
873	C2M				0	0	0	0	GAS PRESSURE REDUCIN G STATION - MEDIUM T O LOW	2.0	EA	8.000	29.96	479.	1430.00	2860.	0.00	0.	0.	3339.
874	C2M				0	0	0	0	POTABLE WATER PRESSU RE REGULATING STATIO N	1.0	EA	4.000	29.96	120.	800.00	800.	0.00	0.	0.	920.
875	C2M				0	0	0	0	3-WAY CONTROL VALVES - 3/4"	155.0	EA	2.000	29.96	9288.	210.00	32550.	0.00	0.	0.	41838.
876	C2M				0	0	0	0	CONTROLS FOR FANS	1.0	LS	320.000	30.29	9693.	165326.00	165326.	0.00	0.	0.	175019.
877	C2M				0	0	0	0	GAS METER - 2" TURBI NE	1.0	EA	6.000	29.96	180.	2100.00	2100.	0.00	0.	0.	2280.
878	C2M				0	0	0	0	FLOOR DRAIN SYSTEM - DOUBLE CONTAINMENT, 4", TRENCH & BKFILL	1.0	LS		29.96	0.	0.00	0.	0.00	0.	160332.	160332.
879	C2M				0	0	0	0	FLOOR DRAIN SYSTEM - DOUBLE CONTAINMENT, 3", TRENCH & BKFILL	1.0	LS		29.96	0.	0.00	0.	0.00	0.	150000.	150000.
880	C2M				0	0	0	0	HEAT RECOVERY COILS, 80 SF, 6 ROWS	12.0	LS	80.000	29.96	28762.	6144.00	73728.	0.00	0.	0.	102490.
881	C2M				0	0	0	0	COOLING TOWER, 2 WAY CONTROL VALVE 8"	2.0	EA	8.000	29.96	479.	5300.00	10600.	0.00	0.	0.	11079.
882	C2M				0	0	0	0	14" STAINLESS STEEL DUCT, FUME HOODS	205.0	LBS	0.145	30.29	900.	2.78	570.	0.00	0.	0.	1470.
883	C2M				0	0	0	0	CONTROLS - INSTALLED	1.0	LS		0.00	0.	0.00	0.	0.00	0.	180000.	180000.
884	C2M				0	0	0	0	VARIABLE VOLUME DRIV ES - 100 HP	2.0	EA	10.000	30.29	606.	16700.00	33400.	0.00	0.	0.	34006.
885	C2M				0	0	0	0	CHARCOAL FILTERS - 3 x6 BANK	6.0	BANK	3.000	30.29	545.	1832.00	10992.	0.00	0.	0.	11537.
886	C2M				0	0	0	0	HEPA FILTERS (ADDITI ONAL SET 3x6 BANK)	82.0	BANK	2.000	30.29	4968.	400.00	32800.	0.00	0.	0.	37768.
887	C2M				0	0	0	0	PRE FILTERS (ADDITIO NAL SET 3x6 BANK)	82.0	BANK	2.000	30.29	4968.	200.00	16400.	0.00	0.	0.	21368.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c Trd b ID F	A c Markup Tag	Take-Off Item Description	Quantity Unit	Labor			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
C2M Category Direct Cost									734673.		17258646.		1200.		490332.		18484851.
28	C2N				0	0	MAIN SWBD., 4000A, W /METERING & GF PRO., 65K AIC, MCSS C.B.s	1.0 EA	246.400	29.55	7281.	53600.00	53600.	0.00	0.	0.	60881.
34	C2N				0	0	MCC-A, 800 A	1.0 EA	73.600	29.55	2175.	6500.00	6500.	0.00	0.	0.	8675.
35	C2N				0	0	MCC-B, 800A	1.0 EA	62.600	29.55	1850.	12000.00	12000.	0.00	0.	0.	13850.
37	C2N				0	0	MCC-C, 600A	1.0 EA	32.000	29.55	946.	8500.00	8500.	0.00	0.	0.	9446.
42	C2N				0	0	MCC-D, 600A	1.0 EA	95.600	29.55	2825.	12000.00	12000.	0.00	0.	0.	14825.
43	C2N				0	0	MCC-E, 1200A	1.0 EA	84.200	29.55	2488.	18000.00	18000.	0.00	0.	0.	20488.
45	C2N				0	0	MCC-F, 600A	1.0 EA	27.200	29.55	804.	6500.00	6500.	0.00	0.	0.	7304.
48	C2N				0	0	EMCC-A, 600A	1.0 EA	139.800	29.55	4131.	18000.00	18000.	0.00	0.	0.	22131.
54	C2N				0	0	PANELBOARD, 480Y/277 A, W/MB	13.0 EA	34.300	29.55	13176.	1400.00	18200.	0.00	0.	0.	31376.
650	C2N				0	0	LIGHTING INDOOR HID 400 WATT	88.0 EA	3.480	29.55	9049.	460.00	40480.	0.00	0.	0.	49529.
651	C2N				0	0	LIGHTING INDOOR HID 1,000 WATT	14.0 EA	4.000	29.55	1655.	700.00	9800.	0.00	0.	0.	11455.
652	C2N				0	0	LIGHTING INDOOR 2'x4' PREMIUM TRAFFER 3LAMP	366.0 EA	1.600	29.55	17304.	65.00	23790.	0.00	0.	0.	41094.
653	C2N				0	0	LIGHTING INDOOR 2'x4' PARABOLIC TRAFFER 3LAMP	126.0 EA	1.600	29.55	5957.	140.00	17640.	0.00	0.	0.	23597.
654	C2N				0	0	LIGHTING INDOOR 11'x4' WRAPAROUND 3LAMP	24.0 EA	2.400	29.55	1702.	43.00	1032.	0.00	0.	0.	2734.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c Trd b ID F	A c Markup Tag	Take-Off Item Description	Quantity Unit	Labor			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
656	C2N					0 0	15KVA UPS	2.0 EA	200.000	29.55		15500.00		500.00			
658	C2N					0 0	OUTDOOR LIGHTING HPS 100 WATT	75.0 EA	2.000	29.55		120.00		0.00		0.	43820.
659	C2N					0 0	PANELBOARD, 208Y/120 V, 400A, W/MB	3.0 EA	80.000	29.55		1050.00		0.00		0.	10242.
660	C2N					0 0	PANELBOARD, 208Y/120 V, 400A, MLO	3.0 EA	72.000	29.55		650.00		0.00		0.	8333.
661	C2N					0 0	PANELBOARD, 208Y/120 V, 225A, W/MB	13.0 EA	64.000	29.55		900.00		0.00		0.	36286.
662	C2N					0 0	PANELBOARD, 208Y/120 V, 225A, MLO	2.0 EA	64.000	29.55		500.00		0.00		0.	4782.
663	C2N					0 0	STANDBY GEN., DIESEL , 400KW, W/ATS, MUFF LER, BAT CHRGR., TNK	1.0 EA	300.000	29.55		67200.00		550.00		0.	76615.
664	C2N					0 0	TRANSFORMER, DRY TYP E, NEMA 1, 30KVA	5.0 EA	48.000	29.55		1620.00		0.00		0.	15192.
665	C2N					0 0	TRANSFORMER, DRY TYP E, NEMA 1, 45KVA	4.0 EA	52.000	29.55		2430.00		0.00		0.	15866.
666	C2N					0 0	TRANSFORMER, DRY TYP E, NEMA 1, 75KVA	7.0 EA	60.000	29.55		3350.00		0.00		0.	35861.
667	C2N					0 0	DISCONNECT SWITCH, 6 00V, 3P, NEMA 12, 40 OA	1.0 EA	24.000	29.55		1260.00		0.00		0.	1969.
668	C2N					0 0	DISCONNECT SWITCH, 6 00V, 3P, NEMA 12, 20 OA	13.0 EA	16.000	29.55		500.00		0.00		0.	12646.
669	C2N					0 0	DISCONNECT SWITCH, 6 00V, 3P, NEMA 12, 10 OA	10.0 EA	10.000	29.55		370.00		0.00		0.	6655.
670	C2N					0 0	DISCONNECT SWITCH, 6 00V, 3P, NEMA 12, 60 A	4.0 EA	8.000	29.55		260.00		0.00		0.	1986.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c	A c	Trd b c	Markup	Take-Off	Item Description	Quantity	Unit	- - - L a b o r - - -			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4									Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
671	C2N				0	0				DISCONNECT SWITCH, 600V, 3P, NEMA 12, 30 A	62.0	EA	6.000	29.55	10993.	200.00	12400.	0.00	0.	0.	23393.
672	C2N				0	0				DISCONNECT SWITCH, 240V, 2P, NEMA 12, 30 A	16.0	EA	6.000	29.55	2837.	150.00	2400.	0.00	0.	0.	5237.
673	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 1HP	10.0	EA	2.000	29.55	591.	3.20	32.	0.00	0.	0.	623.
674	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 3HP	28.0	EA	2.000	29.55	1655.	3.20	90.	0.00	0.	0.	1744.
675	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 5HP	13.0	EA	2.000	29.55	768.	3.40	44.	0.00	0.	0.	813.
676	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 7-1/2 HP	4.0	EA	2.000	29.55	236.	3.40	14.	0.00	0.	0.	250.
677	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 10 HP	2.0	EA	2.000	29.55	118.	3.40	7.	0.00	0.	0.	125.
678	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 15 HP	4.0	EA	2.500	29.55	296.	4.50	18.	0.00	0.	0.	314.
679	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 20 HP	1.0	EA	2.660	29.55	79.	5.40	5.	0.00	0.	0.	84.
680	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 25 HP	2.0	EA	2.660	29.55	157.	5.40	11.	0.00	0.	0.	168.
681	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 40 HP	5.0	EA	3.200	29.55	473.	10.00	50.	0.00	0.	0.	523.
682	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 50 HP	5.0	EA	3.200	29.55	473.	10.75	54.	0.00	0.	0.	527.
683	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 75 HP	3.0	EA	4.600	29.55	408.	20.25	61.	0.00	0.	0.	469.
684	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 100HP	8.0	EA	6.400	29.55	1513.	28.40	227.	0.00	0.	0.	1740.
685	C2N				0	0				MOTOR CONNECTIONS, 460V, 3PH, 125HP	2.0	EA	8.000	29.55	473.	30.00	60.	0.00	0.	0.	533.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c t r d b c t a g	A c t r c t t a g	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
686	C2N				0	0	CHILLER CONNECTIONS, 460V, 3PH, 185KW	2.0 EA	10.000	29.55	591.	52.00	104.	0.00	0.	0.	695.
687	C2N				0	0	CHILLER CONNECTIONS, 460V, 3PH, 150KW	1.0 EA	9.000	29.55	266.	45.00	45.	0.00	0.	0.	311.
688	C2N				0	0	UNIT HEATERCONNECTIO NS 120V, 1PH	16.0 EA	1.000	29.55	473.	2.00	32.	0.00	0.	0.	505.
698	C2N				0	0	P.A. & TELE. SYSTEM P.A. SYSTEM, CONVEN . OFFICE SPEAKER	80.0 EA	3.000	29.55	7092.	70.00	5600.	0.00	0.	0.	12692.
699	C2N				0	0	P.A. & TELE. SYSTEM CABINET W/WOOD BKBRD (72"Hx60"Wx12"D)	1.0 EA	10.600	29.55	313.	1134.00	1134.	0.00	0.	0.	1447.
700	C2N				0	0	P.A. & TELE. SYSTEM CABINET W/WOOD BKBRD (36"Hx30"Wx6"D)	3.0 EA	6.400	29.55	567.	260.00	780.	0.00	0.	0.	1347.
703	C2N				0	0	P.A. & TELE. SYSTEM TELE. RECPT.'S, 20ft . OF 4/C PHONE WIRE	80.0 EA	0.616	29.55	1456.	5.50	440.	0.00	0.	0.	1896.
704	C2N				0	0	DUPLEX RECEPTACLES	250.0 EA	0.600	29.55	4433.	4.50	1125.	0.00	0.	0.	5558.
705	C2N				0	0	P.A. & TELE. SYSTEM BOXES FOR P.A. 12"Wx12"Hx4"D	3.0 EA	2.600	29.55	230.	15.00	45.	0.00	0.	0.	275.
706	C2N				0	0	LIGHT SWITCHES	120.0 EA	0.200	29.55	709.	1.75	210.	0.00	0.	0.	919.
708	C2N				0	0	480V RECPT. 60 AMP	6.0 EA	1.800	29.55	319.	38.00	228.	0.00	0.	0.	547.
709	C2N				0	0	P.A. & TELE. SYSTEM AVE RUN TELEPHONE #22-4C	15000.0 CLF	0.400	29.55	177300.	14.70	220500.	0.00	0.	0.	397800.
710	C2N				0	0	P.A. & TELE. SYSTEM HANDSETS FOR P.A.	12.0 EA	4.000	29.55	1418.	153.00	1836.	0.00	0.	0.	3254.
711	C2N				0	0	P.A. & TELE. SYSTEM #16 AWG FOR P.A.	2400.0 CLF	1.230	29.55	87232.	5.90	14160.	0.00	0.	0.	101392.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdw Structure				J o c c t r a c t	A c c o u n t	Take-Off Item Description	Quantity Unit	- - - L a b o r - - -			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
712 C2N					0	0	P.A. & TELE. SYSTEM 1/2" C FOR P.A.	800.0 LF	0.940	29.55	22222.	0.33	264.	0.00	0.	0.	22486.
731 C2N					0	0	SEC. ELEC. FEEDER CONDUIT, 4" PVC DIR ECT BURIED BELOW SLB	400.0 LF	0.400	29.55	4728.	5.00	2000.	0.00	0.	0.	6728.
732 C2N					0	0	SEC. ELEC. FEEDER CABLE, 600V, XHHW, 500 MCM	1600.0 LF	0.120	29.55	5674.	5.00	8000.	0.00	0.	0.	13674.
733 C2N					0	0	SEC. ELEC. FEEDER CABLE, 600V, XHHW, #1/0	400.0 LF	0.080	29.55	946.	1.10	440.	0.00	0.	0.	1386.
734 C2N					0	0	SWITCHBOARD FEEDERS 800A, TO MCC-A, RGS CONDUIT, 4"	530.0 LF	1.000	29.55	15662.	12.30	6519.	0.00	0.	0.	22181.
735 C2N					0	0	SWITCHBOARD FEEDERS 800A, TO MCC-A, THW N, #500 MCM, CU	2120.0 LF	10.000	29.55	626460.	4.50	9540.	0.00	0.	0.	636000.
736 C2N					0	0	SWITCHBOARD FEEDERS 800A, TO MCC-A, THW N, #1/0 CU.	530.0 LF	0.060	29.55	940.	1.20	636.	0.00	0.	0.	1576.
737 C2N					0	0	SWITCHBOARD FEEDERS 800A, TO MCC-B, RGS CONDUIT, 4"	400.0 LF	0.620	29.55	7328.	12.30	4920.	0.00	0.	0.	12248.
738 C2N					0	0	SWITCHBOARD FEEDERS 800A, TO MCC-B, THW N, #500 MCM, CU.	1600.0 LF	0.120	29.55	5674.	4.50	7200.	0.00	0.	0.	12874.
739 C2N					0	0	SWITCHBOARD FEEDERS 800A, TO MCC-B, THW N, #1/0 CU.	400.0 LF	0.060	29.55	709.	1.20	480.	0.00	0.	0.	1189.
740 C2N					0	0	SWITCHBOARD FEEDERS 600A, TO MCC-C, RGS CONDUIT, 3"	600.0 LF	0.600	29.55	10638.	8.20	4920.	0.00	0.	0.	15558.
741 C2N					0	0	SWITCHBOARD FEEDERS 600A, TO MCC-C, THW N, #350 MCM, CU.	2400.0 LF	0.100	29.55	7092.	3.30	7920.	0.00	0.	0.	15012.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J A		Take-Off Item Description	Quantity	Unit	L a b o r			Material		Const	Equip	Sub	Item
	1	2	3	4	o	c				Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost	Cntrct Cost	Direct Cost
742	C2N				0	0	SWITCHBOARD FEEDERS 600A, TO MCC-C, THW N, #1/0 CU.	600.0	LF	0.060	29.55	1064.	1.20	720.	0.00	0.	0.	1784.
743	C2N				0	0	SWITCHBOARD FEEDERS 600A, TO MCC-D, RGS CONDUIT, 3"	400.0	LF	0.800	29.55	9456.	8.20	3280.	0.00	0.	0.	12736.
744	C2N				0	0	SWITCHBOARD FEEDERS 600A, TO MCC-D, THW N, #350 MCM, CU.	1600.0	LF	0.100	29.55	4728.	3.30	5280.	0.00	0.	0.	10008.
745	C2N				0	0	SWITCHBOARD FEEDERS 600A, TO MCC-D, THW N, #1/0 CU	400.0	LF	0.060	29.55	709.	1.20	480.	0.00	0.	0.	1189.
746	C2N				0	0	SWITCHBOARD FEEDERS 1200A, TO MCC-E, RG S CONDUIT, 3"	400.0	LF	0.800	29.55	9456.	8.20	3280.	0.00	0.	0.	12736.
747	C2N				0	0	SWITCHBOARD FEEDERS 1200A, TO MCC-E, TH WN, #350 MCM, CU.	1600.0	LF	0.100	29.55	4728.	3.30	5280.	0.00	0.	0.	10008.
748	C2N				0	0	SWITCHBOARD FEEDERS 1200A, TO MCC-E, TH WN, #1/0 CU.	400.0	LF	0.800	29.55	9456.	1.20	480.	0.00	0.	0.	9936.
749	C2N				0	0	SWITCHBOARD FEEDERS 600A, TO MCC-F, RGS CONDUIT, 3"	130.0	LF	0.800	29.55	3073.	8.20	1066.	0.00	0.	0.	4139.
750	C2N				0	0	SWITCHBOARD FEEDERS 600A, TO MCC-F, THW N #350 MCM, CU.	520.0	LF	0.100	29.55	1537.	3.30	1716.	0.00	0.	0.	3253.
751	C2N				0	0	SWITCHBOARD FEEDERS 600A, TO MCC-F, THW N #1/0 CU.	130.0	LF	0.060	29.55	230.	1.20	156.	0.00	0.	0.	386.
752	C2N				0	0	SWITCHBOARD FEEDERS 600A, TO ATS-A, RGS CONDUIT, 4"	720.0	LF	1.000	29.55	21276.	12.30	8856.	0.00	0.	0.	30132.
753	C2N				0	0	SWITCHBOARD FEEDERS 600A, TO ATS-A, THW N, #500 MCM, CU	2880.0	LF	0.120	29.55	10212.	4.50	12960.	0.00	0.	0.	23172.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o ID	A c F	Cntrct b t	Take-Off Item Description	Quantity Unit	Labor			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4						Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
754 C2N					0	0		SWITCHBOARD FEEDERS 600A, TO ATS-A, THW N, #1/0 CU	720.0 LF	1.000	29.55	21276.	1.20	864.	0.00	0.	0.	22140.
755 C2N					0	0		SWITCHBOARD FEEDERS ATS-A TO EMCC-A, RG S CONDUIT 3"	200.0 LF	0.800	29.55	4728.	8.20	1640.	0.00	0.	0.	6368.
756 C2N					0	0		SWITCHBOARD FEEDERS ATS-A TO EMCC-A, TH WN, #350 MCM, CU	800.0 LF	0.100	29.55	2364.	3.30	2640.	0.00	0.	0.	5004.
757 C2N					0	0		SWITCHBOARD FEEDERS ATS-A TO EMCC-A, TH WN, #1/0 CU	200.0 LF	0.060	29.55	355.	1.20	240.	0.00	0.	0.	595.
758 C2N					0	0		SWITCHBOARD FEEDERS GEN. TO ATS-S, RGS CONDUIT, 3"	10.0 LF	0.800	29.55	236.	8.20	82.	0.00	0.	0.	318.
759 C2N					0	0		SWITCHBOARD FEEDERS GEN. TO ATS-S, THWN , #350 MCM, CU	80.0 LF	0.100	29.55	236.	3.30	264.	0.00	0.	0.	500.
760 C2N					0	0		SWITCHBOARD FEEDERS GEN. TO ATS-S, THWN , #1/0 CU	10.0 LF	0.060	29.55	18.	1.20	12.	0.00	0.	0.	30.
761 C2N					0	0		SWITCHBOARD FEEDERS 225A TO LP-A, RGS C ONDUIT, 2-1/2"	200.0 LF	0.600	29.55	3546.	6.20	1240.	0.00	0.	0.	4786.
762 C2N					0	0		SWITCHBOARD FEEDERS 225A TO LP-A, THWN, #4/0 CU	800.0 LF	0.080	29.55	1891.	2.40	1920.	0.00	0.	0.	3811.
763 C2N					0	0		SWITCHBOARD FEEDERS 225A TO LP-A, THWN, #4 CU	200.0 LF	0.032	29.55	189.	0.50	100.	0.00	0.	0.	289.
764 C2N					0	0		SWITCHBOARD FEEDERS 225A TO LP-B, RGS C ONDUIT, 3"	310.0 LF	0.800	29.55	7328.	8.20	2542.	0.00	0.	0.	9870.
765 C2N					0	0		SWITCHBOARD FEEDERS 225A TO LP-B, THWN, #350 MCM, CU	12.4 CLF	9.000	29.55	3298.	316.00	3918.	0.00	0.	0.	7216.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c Trd b ID F	A c Cntrct Markup Tag	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
766	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-B, THWN, #4 CU	3.1 CLF	3.200	29.55	293.	42.00	130.	0.00	0.	0.	423.
767	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-C, RGS C ONDUIT, 2-1/2"	170.0 LF	0.400	29.55	2009.	5.80	986.	0.00	0.	0.	2995.
768	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-C, THWN, #4/0, CU	6.8 CLF	8.000	29.55	1608.	204.00	1387.	0.00	0.	0.	2995.
769	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-C, THWN, #4 CU	1.7 CLF	3.200	29.55	161.	42.00	71.	0.00	0.	0.	232.
770	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-D, RGS C ONDUIT 2-1/2"	260.0 LF	0.400	29.55	3073.	5.80	1508.	0.00	0.	0.	4581.
771	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-D, THWN, #4/0 CU	10.4 CLF	8.000	29.55	2459.	204.00	2122.	0.00	0.	0.	4580.
772	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-D, THWN, #4 CU	2.6 CLF	3.200	29.55	246.	42.00	109.	0.00	0.	0.	355.
773	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-E, RGS C ONDUIT 3"	320.0 LF	0.600	29.55	5674.	7.30	2336.	0.00	0.	0.	8010.
774	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-E, THWN, #350 MCM CU	12.8 CLF	9.000	29.55	3404.	316.00	4045.	0.00	0.	0.	7449.
775	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-E, THWN, #4 CU	3.2 CLF	3.200	29.55	303.	42.00	134.	0.00	0.	0.	437.
776	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-F, RGS C ONDUIT 3"	420.0 LF	0.600	29.55	7447.	7.30	3066.	0.00	0.	0.	10513.
777	C2N				0	0	SWITCHBOARD FEEDERS 225A TO LP-F, THWN, #350 MCM CU	16.8 CLF	9.000	29.55	4468.	316.00	5309.	0.00	0.	0.	9777.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c t r b t ID F	A c k r p t Tag	Take-Off Item Description	Quantity Unit	- - - - L a b o r - - - -			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
778 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-F, THWN, #4 CU	4.2 CLF	3.200	29.55	397.	42.00	176.	0.00	0.	0.	574.
779 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-G, RGS C ONDUIT, 2-1/2"	100.0 LF	0.400	29.55	1182.	5.80	580.	0.00	0.	0.	1762.
780 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-G, THWN, #4/0, CU	4.0 CLF	8.000	29.55	946.	204.00	816.	0.00	0.	0.	1762.
781 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-G, THWN, #4 CU	1.0 CLF	3.200	29.55	95.	42.00	42.	0.00	0.	0.	137.
782 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-H, RGS C ONDUIT 2-1/2"	140.0 LF	0.400	29.55	1655.	5.80	812.	0.00	0.	0.	2467.
783 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-H, THWN, #4/0, CU	5.6 CLF	8.000	29.55	1324.	204.00	1142.	0.00	0.	0.	2466.
784 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-H, THWN, #4 CU	1.4 CLF	3.200	29.55	132.	42.00	59.	0.00	0.	0.	191.
785 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-1, RGS C ONDUIT, 2-1/2"	200.0 LF	0.400	29.55	2364.	5.80	1160.	0.00	0.	0.	3524.
786 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-1, THWN, #4/0 CU	8.0 CLF	8.000	29.55	1891.	204.00	1632.	0.00	0.	0.	3523.
787 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-1, THWN, #4 CU	2.0 CLF	3.200	29.55	189.	42.00	84.	0.00	0.	0.	273.
788 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-J, RGS C ONDUIT, 2-1/2"	160.0 LF	0.400	29.55	1891.	5.80	928.	0.00	0.	0.	2819.
789 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-J, THWN, #4/0 CU	6.4 CLF	8.000	29.55	1513.	204.00	1306.	0.00	0.	0.	2819.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c ID b c F t	A c Markup Tag	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
790 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-J, THWN, #4 CU	1.6 CLF	3.200	29.55	151.	42.00	67.	0.00	0.	0.	218.
791 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-K, RGS C ONDUIT, 2-1/2"	30.0 LF	0.400	29.55	355.	5.80	174.	0.00	0.	0.	529.
792 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-K, THWN, #4/0 CU	1.2 CLF	8.000	29.55	284.	204.00	245.	0.00	0.	0.	528.
793 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-K, THWN, #4 CU	0.3 CLF	3.200	29.55	28.	42.00	13.	0.00	0.	0.	41.
794 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-L, RGS C ONDUIT, 2-1/2"	210.0 LF	0.400	29.55	2482.	5.80	1218.	0.00	0.	0.	3700.
795 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-L, THWN, #4/0 CU	8.4 CLF	8.000	29.55	1986.	204.00	1714.	0.00	0.	0.	3699.
796 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-L, THWN, #4 CU	2.1 CLF	3.200	29.55	199.	42.00	88.	0.00	0.	0.	287.
797 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-M, RGS C ONDUIT, 2-1/2"	260.0 LF	0.400	29.55	3073.	5.80	1508.	0.00	0.	0.	4581.
798 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-M, THWN, #4/0 CU	10.4 CLF	8.000	29.55	2459.	204.00	2122.	0.00	0.	0.	4580.
799 C2N					0	0	SWITCHBOARD FEEDERS 225A TO LP-M, THWN, #4 CU	2.6 CLF	3.200	29.55	246.	42.00	109.	0.00	0.	0.	355.
800 C2N					0	0	MCC MOTOR FEEDERS MCC-A (3#1/0 & 1#6 IN 1-1/2 RGSx8@100')	800.0 LF	0.200	29.55	4728.	2.70	2160.	0.00	0.	0.	6888.
801 C2N					0	0	MCC MOTOR FEEDERS MCC-A THWN, #1/0 CU	24.0 CLF	5.000	29.55	3546.	117.00	2808.	0.00	0.	0.	6354.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	o c Cntrct		L a b o r				Material		Const Equip		Sub		Item	
Structure				Trd b	c	Markup	Take-Off	Item	Quantity	Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd	Cntrct	Direct	
Item	1	2	3	4	ID	F	t	Tag	Description	Unit							Cost	Cost	
802	C2N							0 0	MCC MOTOR FEEDERS	8.0		3.000	29.55	6.90		0.00			
									MCC-A THWN, #6 CU	CLF			709.	55.		0.	0.	764.	
803	C2N							0 0	MCC MOTOR FEEDERS	700.0		0.200	29.55	2.70		0.00			
									MCC-B RGS, 1-1/2"	LF			4137.	1890.		0.	0.	6027.	
804	C2N							0 0	MCC MOTOR FEEDERS	21.0		5.000	29.55	117.00		0.00			
									MCC-B THWN, #1/0 CU	CLF			3103.	2457.		0.	0.	5560.	
805	C2N							0 0	MCC MOTOR FEEDERS	7.0		3.000	29.55	700.00		0.00			
									MCC-B THWN, #6 CU	CLF			621.	4900.		0.	0.	5521.	
806	C2N							0 0	MCC MOTOR FEEDERS	300.0		0.400	29.55	3.30		0.00			
									MCC-C RGS, 2"	LF			3546.	990.		0.	0.	4536.	
807	C2N							0 0	MCC MOTOR FEEDERS	9.0		6.400	29.55	165.00		0.00			
									MCC-C THWN, #3/0 CU	CLF			1702.	1485.		0.	0.	3187.	
808	C2N							0 0	MCC MOTOR FEEDERS	3.0		2.600	29.55	6.90		0.00			
									MCC-C THWN, #6 CU	CLF			230.	21.		0.	0.	251.	
809	C2N							0 0	MCC MOTOR FEEDERS	1500.0		0.200	29.55	1.93		0.00			
									MCC-D RGS, 1-1/4"	LF			8865.	2895.		0.	0.	11760.	
810	C2N							0 0	MCC MOTOR FEEDERS	45.0		4.000	29.55	75.00		0.00			
									MCC-D THWN, #2 CU	CLF			5319.	3375.		0.	0.	8694.	
811	C2N							0 0	MCC MOTOR FEEDERS	15.0		2.000	29.55	19.50		0.00			
									MCC-D THWN, #8 CU	CLF			887.	293.		0.	0.	1179.	
812	C2N							0 0	MCC MOTOR FEEDERS	100.0		0.600	29.55	7.30		0.00			
									MCC-E RGS, 3"	LF			1773.	730.		0.	0.	2503.	
813	C2N							0 0	MCC MOTOR FEEDERS	3.0		8.000	29.55	109.00		0.00			
									MCC-E THWN, #500 MC	CLF			709.	327.		0.	0.	1036.	
									M, CU										
814	C2N							0 0	MCC MOTOR FEEDERS	1.0		4.000	29.55	75.00		0.00			
									MCC-E THWN, #2, CU	CLF			118.	75.		0.	0.	193.	
815	C2N							0 0	MCC MOTOR FEEDERS	180.0		0.200	29.55	1.60		0.00			
									MCC-E RGS, 1"	LF			1064.	288.		0.	0.	1352.	
816	C2N							0 0	MCC MOTOR FEEDERS	5.4		3.200	29.55	42.00		0.00			
									MCC-E THWN, #4 CU	CLF			511.	227.		0.	0.	737.	
817	C2N							0 0	MCC MOTOR FEEDERS	1.8		2.000	29.55	19.50		0.00			
									MCC-E THWN, #8 CU	CLF			106.	35.		0.	0.	141.	

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c Trd b ID F	A c Markup Tag	Cntrct Take-Off Item Description	Quantity Unit	L a b o r			Material Rate Ext'd Cost	Const Equip Rate Ext'd Cost	Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost				
818	C2N				0	0	MCC MOTOR FEEDERS	90.0	0.200	29.55	10.55	0.00			
							MCC-F RGS, 3/4"	LF		532.	950.	0.	0.	1481.	
819	C2N				0	0	MCC MOTOR FEEDERS	3.6	2.000	29.55	10.55	0.00			
							MCC-F THWN, # 12 CU	CLF		213.	38.	0.	0.	251.	
820	C2N				0	0	MCC MOTOR FEEDERS	60.0	0.200	29.55	1.93	0.00			
							MCC-F RGS, 1-1/4"	LF		355.	116.	0.	0.	470.	
821	C2N				0	0	MCC MOTOR FEEDERS	1.8	4.000	29.55	75.00	0.00			
							MCC-F THWN, #2 CU	CLF		213.	135.	0.	0.	348.	
822	C2N				0	0	MCC MOTOR FEEDERS	0.6	1.600	29.55	19.50	0.00			
							MCC-F THWN, #8 CU	CLF		28.	12.	0.	0.	40.	
823	C2N				0	0	MCC MOTOR FEEDERS	50.0	0.600	29.55	7.30	0.00			
							EMCC-A RGS, 3"	LF		887.	365.	0.	0.	1252.	
824	C2N				0	0	MCC MOTOR FEEDERS	1.5	8.000	29.55	109.00	0.00			
							EMCC-A THWN, #500 CU	CLF		355.	164.	0.	0.	518.	
825	C2N				0	0	MCC MOTOR FEEDERS	0.5	4.000	29.55	75.00	0.00			
							EMCC-A THWN, #2 CU	CLF		59.	38.	0.	0.	97.	
826	C2N				0	0	MCC MOTOR FEEDERS	2000.0	0.200	29.55	1.20	0.00			
							EMCC-A RGS, 3/4"	LF		11820.	2400.	0.	0.	14220.	
827	C2N				0	0	MCC MOTOR FEEDERS	80.0	2.000	29.55	10.55	0.00			
							EMCC-A THWN, . #12 CU	CLF		4728.	844.	0.	0.	5572.	
828	C2N				0	0	MCC MOTOR FEEDERS	20.0	0.200	29.55	1.20	0.00			
							EMCC-A RGS, 3/4"	LF		118.	24.	0.	0.	142.	
829	C2N				0	0	MCC MOTOR FEEDERS	0.6	1.600	29.55	19.50	0.00			
							EMCC-A THWN, #8 CU	CLF		28.	12.	0.	0.	40.	
830	C2N				0	0	MCC MOTOR FEEDERS	0.2	1.600	29.55	15.00	0.00			
							EMCC-A THWN, #10 CU	CLF		9.	3.	0.	0.	12.	
831	C2N				0	0	FEEDERS FROM LP'S TO	405.0	0.200	29.55	1.93	0.00			
							X-FRMS (75KVA) - RG	LF		2394.	782.	0.	0.	3175.	
							S, 1-1/4"								
832	C2N				0	0	FEEDERS FROM LP'S TO	12.2	4.000	29.55	75.00	0.00			
							X-FRMS (75KVA) - TH	CLF		1436.	911.	0.	0.	2347.	
							WN, #2 CU								

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn Structure				J o c	A ntrct	Trd b c Markup	Take-Off Item	Quantity	Labor			Material	Const Equip	Sub	Item	
Item	1	2	3	4	ID	F	t Tag Description	Unit	Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost	
833	C2N						0 0 FEEDERS FROM LP'S TO X-FRMS (75KVA) - THWN, #6 CU	4.0 CLF	2.000	29.55	239.	10.50	43.	0.00	0.	282.
834	C2N						0 0 FEEDERS FROM LP'S TO X-FRMS (45KVA) - RGS, 1"	40.0 LF	0.200	29.55	236.	1.60	64.	0.00	0.	300.
835	C2N						0 0 FEEDERS FROM LP'S TO X-FRMS (45KVA) - THWN, #4 CU	1.2 CLF	3.200	29.55	113.	42.00	50.	0.00	0.	164.
836	C2N						0 0 FEEDERS FROM LP'S TO X-FRMS (45KVA) - THWN, #8 CU	0.4 CLF	1.600	29.55	19.	19.50	8.	0.00	0.	27.
837	C2N						0 0 FEEDERS FROM LP'S TO X-FRMS (30KVA) - RGS, 3/4"	40.0 LF	0.200	29.55	236.	1.20	48.	0.00	0.	284.
838	C2N						0 0 FEEDERS FROM LP'S TO X-FRMS (30KVA) - THWN, #8, CU	1.2 CLF	1.600	29.55	57.	19.50	23.	0.00	0.	80.
839	C2N						0 0 FEEDERS FROM LP'S TO X-FRMS (30KVA) - THWN, #10, CU	0.4 CLF	1.600	29.55	19.	15.00	6.	0.00	0.	25.
840	C2N						0 0 FEEDERS FROM X-FRMS TO PP's FOR 75KVA - RGS, 2-1/2"	30.0 LF	0.400	29.55	355.	5.80	174.	0.00	0.	529.
841	C2N						0 0 FEEDERS FROM X-FRMS TO PP's FOR 75KVA - THWN, #250 MCM, CU	1.2 CLF	8.000	29.55	284.	240.00	288.	0.00	0.	572.
842	C2N						0 0 FEEDERS FROM X-FRMS TO PP's FOR 75KVA - THWN, #4 CU	0.3 CLF	3.200	29.55	28.	42.00	13.	0.00	0.	41.
843	C2N						0 0 FEEDERS FROM X-FRMS TO PP's 225A 75KVA - RGS, 2-1/2"	40.0 LF	0.400	29.55	473.	5.80	232.	0.00	0.	705.
844	C2N						0 0 FEEDERS FROM X-FRMS TO PP's 225A 75KVA - THWN #4/0 CU	1.6 CLF	8.000	29.55	378.	204.00	326.	0.00	0.	705.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	o c		Trd b		c Markup		Take-Off Item		Quantity	Unit	- - - - L a b o r - - - -		Material		Const Equip		Sub	Item	
Structure				ID	F	t	Tag	c		c		Description				Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost	Cntrct Cost	Direct Cost
Item	1	2	3	4																				
845	C2N					0	0					FEEDERS FROM X-FRMS TO PP's 225A 75KVA - THWN #4 CU		0.4	CLF	3.200	29.55	38.	42.00	17.	0.00	0.	0.	55.
846	C2N					0	0					FEEDERS FROM X-FRMS TO PP's 45KVA - RGS, 1-1/2"		40.0	LF	0.200	29.55	236.	2.70	108.	0.00	0.	0.	344.
847	C2N					0	0					FEEDERS FROM X-FRMS TO PP's 45KVA - THWN , #1/0 CU		1.6	CLF	5.000	29.55	236.	117.00	187.	0.00	0.	0.	424.
848	C2N					0	0					FEEDERS FROM X-FRMS TO PP's 45KVA - THWN , #6 CU		0.4	CLF	3.000	29.55	35.	6.90	3.	0.00	0.	0.	38.
849	C2N					0	0					FEEDERS FROM X-FRMS TO PP's 30KVA - RGS, 1-1/4"		50.0	LF	0.200	29.55	296.	1.93	97.	0.00	0.	0.	392.
850	C2N					0	0					FEEDERS FROM X-FRMS TO PP's 30KVA - THWN , #2 CU		2.0	CLF	4.000	29.55	236.	75.00	150.	0.00	0.	0.	386.
851	C2N					0	0					FEEDERS FROM X-FRMS TO PP's 30KVA - THWN , #8 CU		0.5	CLF	1.600	29.55	24.	19.50	10.	0.00	0.	0.	33.
852	C2N					0	0					BRANCH CIRCUITS FROM LP's - IMC, 3/4"		29250.0	LF	0.200	29.55	172868.	1.15	33638.	0.00	0.	0.	206505.
853	C2N					0	0					BRANCH CIRCUITS FROM LP's - THHN, #12 CU		877.5	CLF	1.600	29.55	41488.	7.20	6318.	0.00	0.	0.	47806.
854	C2N					0	0					BRANCH CIRCUITS FROM PP's - IMC, 3/4"		31500.0	LF	0.200	29.55	186165.	1.15	36225.	0.00	0.	0.	222390.
855	C2N					0	0					BRANCH CIRCUITS FROM PP's - THHN, #12 CU		945.0	CLF	1.600	29.55	44680.	7.20	6804.	0.00	0.	0.	51484.
856	C2N					0	0					GROUNDING - #4/0 TO BLDG STEEL COLUMN		130.0	EA	3.600	29.55	13829.	6.10	793.	0.00	0.	0.	14622.
857	C2N					0	0					GROUNDING - ELECTROL YTIC GRND ROD		1.0	EA	10.200	29.55	301.	410.00	410.	0.00	0.	0.	711.
858	C2N					0	0					GROUNDING - BENTONIT E CLAY PER 10' ROD		1.0	EA	1.500	29.55	44.	27.00	27.	0.00	0.	0.	71.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn Structure					J A		o c Cntrct		Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
Item	1	2	3	4	ID	F	t	Tag			Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
859	C2N						0	0	GROUNDING - GRND PLATE	1.0 EA	36.000	29.55	1064.	200.00	200.	0.00	0.	0.	1264.
860	C2N						0	0	GROUNDING - SINGLE POINT GRND NEUTRAL	0.1 CLF	4.800	29.55	21.	57.00	9.	0.00	0.	0.	30.
861	C2N						0	0	GROUNDING - GRND ROD	40.0 EA	5.400	29.55	6383.	16.20	648.	0.00	0.	0.	7031.
862	C2N						0	0	GROUNDING - CADWELD #4/0 TO GRND RODS	40.0 EA	3.600	29.55	7.75	4255.	310.	0.00	0.	0.	4565.
863	C2N						0	0	GROUNDING - SRG #6 AWG	25.9 CLF	3.000	29.55	2298.	27.00	700.	0.00	0.	0.	2998.
864	C2N						0	0	GROUNDING - CONN. FOR SRG	324.0 EA	2.100	29.55	20106.	7.30	2365.	0.00	0.	0.	22471.
865	C2N						0	0	GROUNDING - CONN. TO WATER PIPE	3.0 EA	3.900	29.55	346.	27.00	81.	0.00	0.	0.	427.
866	C2N						0	0	GROUNDING - SINGLE POINT GRND WATER PIPE	0.4 CLF	4.800	29.55	57.	57.00	23.	0.00	0.	0.	80.
897	C2N						0	0	P.A./TELE. SYSTEM #22-100 PAIR	300.0 LF	0.200	29.55	1773.	1.00	300.	0.00	0.	0.	2073.
898	C2N						0	0	STREET LIGHTS	15.0 EA	2.000	29.55	887.	130.00	1950.	0.00	0.	0.	2837.
899	C2N						0	0	LIGHTNING PROTECT'N SYSTEM - 56,286 SQ. FT.	1.0 LOT	2700.000	29.55	79785.	38400.00	38400.	0.00	0.	0.	118185.
900	C2N						0	0	FIRE ALARM PROTECT'N SYSTEM	1.0 LOT	2200.000	29.55	65010.	41399.00	41399.	0.00	0.	0.	106409.
901	C2N						0	0	CONTROL RM. DCS COMPUTER, CONTROL PNLS & ANNUNCIATORS	1.0 LOT	9000.000	29.55	265950.	240000.00	240000.	0.00	0.	0.	505950.
902	C2N						0	0	CONTROL RM. DCS SOFTWARE & PROGRAMMING	1.0 LOT	24000.000	29.55	709200.	80000.00	80000.	0.00	0.	0.	789200.
903	C2N						0	0	CONTROL RM. DCS TESTING	1.0 LOT	6770.000	29.55	200054.	0.00	0.	0.00	0.	0.	200054.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J A Trd b ID F	o c c Markup t Tag	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
904	C2N					0 0	WIRING & CONDUIT FRM DCS TO INST'S, CNTL VLVS, PUMPS, ETC	1.0 LOT	8960.000	29.55	264768.	240000.00	240000.	0.00	0.	0.	504768.
905	C2N					0 0	DISCONNECT & REMOVE STREET AND EXTERIOR LIGHTS	1.0 LOT	474.000	29.55	14007.	0.00	0.	0.00	0.	0.	14007.
906	C2N					0 0	LOAD & HAUL STREET AND EXTERIOR LIGHTS	1.0 LOT	80.000	17.15	1372.	0.00	0.	11.00	11.	0.	1383.
	C2N						Category Direct Cost				3528722.		1599823.		1561.	0.	5130106.
910	C3					0 0	CONSTRUCT RLW PRE-TR EATMENT PLANT	1.0 LOT		0.00	0.	0.00	0.	0.00	0.	4878240.	4878240.
	C3						Category Direct Cost				0.		0.		0.	4878240.	4878240.
343	C4A					0 0	SITE UTILITIES-GAS PRV STA.	1.0 EA	8.000	29.96	240.	450.00	450.	0.00	0.	0.	690.
344	C4A					0 0	SITE UTILITIES-GAS 2" DIA. PIPE	200.0 LF	0.066	29.96	395.	0.90	180.	0.00	0.	0.	575.
	C4A						Category Direct Cost				635.		630.		0.	0.	1265.
345	C4B					0 0	SITE UTIL. SS LIFT STATION	1.0 EA	500.000	29.96	14980.	32000.00	32000.	0.00	0.	0.	46980.
347	C4B					0 0	SITE UTIL. SS CLEAN OUTS	4.0 EA	1.000	29.96	120.	16.00	64.	0.00	0.	0.	184.
348	C4B					0 0	SITE UTIL. SS MANHOLE	1.0 EA	30.000	29.96	899.	2000.00	2000.	0.00	0.	0.	2899.
	C4B						Category Direct Cost				15999.		34064.		0.	0.	50063.
339	C4C					0 0	SITE UTILITIES FIRE HYDRANT	2.0 EA	8.000	29.96	479.	450.00	900.	0.00	0.	0.	1379.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c t	A c t r c t	Take-Off Item Description	Quantity Unit	L a b o r			Material Rate Ext'd Cost	Const Equip Rate Ext'd Cost	Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost				
340	C4C				0	0	SITE UTILITIES PIV	5.0 EA	10.000	29.96	1498.	1500.00	7500.	0.00	8998.
341	C4C				0	0	SITE UTILITIES 8" CAST IRON PIPE	400.0 LF	0.259	29.96	3104.	10.90	4360.	0.00	7464.
342	C4C				0	0	SITE UTILITIES 4" & SMALLER PIPE	600.0 LF	0.116	29.96	2085.	6.50	3900.	0.00	5985.
346	C4C				0	0	SITE UTIL. SS 6" DIA. PIPING	150.0 LF	0.068	29.96	306.	1.22	183.	0.00	489.
889	C4C				0	0	SITE UTILITIES 6" CAST IRON PIPE	200.0 LF	0.190	29.96	1138.	8.00	1600.	0.00	2738.
C4C							Category Direct Cost				8611.		18443.	0.	27054.
702	C4E				0	0	P.A. & TELE. SYSTEM NEW 200 PR CABLE FRM EXIT MH-NEW MH-SWBD	300.0 LF	0.200	29.55	1773.	1.50	450.	0.00	2223.
707	C4E				0	0	P.A. & TELE. SYSTEM TELEPHONE MANHOLE	1.0 EA	40.000	29.55	1182.	1675.00	1675.	0.00	2857.
C4E							Category Direct Cost				2955.		2125.	0.	5080.
33	C4G				0	0	SUBSTA., 3000 KVA OI L-FILLED X-FMR W/PRI LB SWITCH SEC. C.B.	1.0 EA	242.000	29.55	7151.	106500.00	106500.	0.00	113651.
C4G							Category Direct Cost				7151.		106500.	0.	113651.
729	C4H				0	0	PRI. ELEC. FEEDER DUCTBANK, 2-4" PVC, CONC. ENC.	200.0 LF	0.600	29.55	3546.	6.00	1200.	0.00	4746.
730	C4H				0	0	PRI. ELEC. FEEDER CABLE, 15 KV, MV-90 #1/0 COPPER	800.0 LF	0.100	29.55	2364.	2.40	1920.	0.00	4284.
C4H							Category Direct Cost				5910.		3120.	0.	9030.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J A	o c Cntrct				- - - - L a b o r - - - -			Material		Const Equip		Sub		Item	
Structure				Trd b	c	Markup	Take-Off	Item	Quantity		Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd	Cntrct	Direct
Item	1	2	3	4	ID	F	t	Tag	Description	Unit			Cost		Cost		Cost	Cost	Cost
913	C4I					0	0		INDUSTRIAL WASTE LINE TA55-50 8' TUNNEL	12800.0 SF	1.000	151.34 1937152.		162.00 2073600.		8.25 105600.		0.	4116352.
	C4I								Category Direct Cost			1937152.		2073600.		105600.		0.	4116352.
99	C6A					0	0		PLUMBING DEMOLITION - DISTILLED WATER - 1"	75.0 LF	0.080	29.96 180.		0.00 0.		0.00 0.		0.	180.
100	C6A					0	0		PLUMBING DEMOLITION - DISTILLED WATER - 3/4"	150.0 LF	0.080	29.96 360.		0.00 0.		0.00 0.		0.	360.
101	C6A					0	0		PLUMBING DEMOLITION - DISTILLED WATER - 1/2"	290.0 LF	0.080	29.96 695.		0.00 0.		0.00 0.		0.	695.
102	C6A					0	0		PLUMBING DEMOLITION - HOT WATER - 2-1/2"	126.0 LF	0.106	29.96 400.		0.00 0.		0.00 0.		0.	400.
103	C6A					0	0		PLUMBING DEMOLITION - HOT WATER - 2"	64.0 LF	0.080	29.96 153.		0.00 0.		0.00 0.		0.	153.
104	C6A					0	0		PLUMBING DEMOLITION - HOT WATER - 1-1/2"	130.0 LF	0.080	29.96 312.		0.00 0.		0.00 0.		0.	312.
105	C6A					0	0		PLUMBING DEMOLITION - HOT WATER - 1-1/4"	35.0 LF	0.080	29.96 84.		0.00 0.		0.00 0.		0.	84.
106	C6A					0	0		PLUMBING DEMOLITION - HOT WATER - 1"	191.0 LF	0.080	29.96 458.		0.00 0.		0.00 0.		0.	458.
107	C6A					0	0		PLUMBING DEMOLITION - HOT WATER - 3/4"	240.0 LF	0.080	29.96 575.		0.00 0.		0.00 0.		0.	575.
108	C6A					0	0		PLUMBING DEMOLITION - COLD WATER - 3"	110.0 LF	0.106	29.96 349.		0.00 0.		0.00 0.		0.	349.
109	C6A					0	0		PLUMBING DEMOLITION - COLD WATER - 2-1/2 "	117.0 LF	0.106	29.96 372.		0.00 0.		0.00 0.		0.	372.
110	C6A					0	0		PLUMBING DEMOLITION - COLD WATER - 2"	110.0 LF	0.080	29.96 264.		0.00 0.		0.00 0.		0.	264.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c Trd b ID F	c Cntrct Markup Tag	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
111	C6A					0 0	PLUMBING DEMOLITION - COLD WATER - 1-1/2"	96.0 LF	0.080	29.96	0.00	0.00					
							"	LF		230.	0.	0.	0.	0.	0.		230.
112	C6A					0 0	PLUMBING DEMOLITION - COLD WATER - 1-1/4"	200.0 LF	0.080	29.96	0.00	0.00					
							"	LF		479.	0.	0.	0.	0.	0.		479.
113	C6A					0 0	PLUMBING DEMOLITION - COLD WATER - 1"	414.0 LF	0.080	29.96	0.00	0.00					
							"	LF		992.	0.	0.	0.	0.	0.		992.
114	C6A					0 0	PLUMBING DEMOLITION - COLD WATER - 3/4"	140.0 LF	0.080	29.96	0.00	0.00					
							"	LF		336.	0.	0.	0.	0.	0.		336.
115	C6A					0 0	PLUMBING DEMOLITION - NATURAL GAS PIPE - 2-1/2"	120.0 LF	0.106	29.96	0.00	0.00					
							"	LF		381.	0.	0.	0.	0.	0.		381.
116	C6A					0 0	PLUMBING DEMOLITION - NATURAL GAS PIPE - 2"	75.0 LF	0.080	29.96	0.00	0.00					
							"	LF		180.	0.	0.	0.	0.	0.		180.
117	C6A					0 0	PLUMBING DEMOLITION - NATURAL GAS PIPE - 1-1/2"	35.0 LF	0.080	29.96	0.00	0.00					
							"	LF		84.	0.	0.	0.	0.	0.		84.
118	C6A					0 0	PLUMBING DEMOLITION - NATURAL GAS PIPE - 1-1/4"	20.0 LF	0.080	29.96	0.00	0.00					
							"	LF		48.	0.	0.	0.	0.	0.		48.
119	C6A					0 0	PLUMBING DEMOLITION - NATURAL GAS PIPE - 1"	130.0 LF	0.080	29.96	0.00	0.00					
							"	LF		312.	0.	0.	0.	0.	0.		312.
120	C6A					0 0	PLUMBING DEMOLITION - NATURAL GAS PIPE - 3/4"	340.0 LF	0.080	29.96	0.00	0.00					
							"	LF		815.	0.	0.	0.	0.	0.		815.
121	C6A					0 0	PLUMBING DEMOLITION - COMPRESSED AIR PIPE - 1-1/2"	245.0 LF	0.080	29.96	0.00	0.00					
							"	LF		587.	0.	0.	0.	0.	0.		587.
122	C6A					0 0	PLUMBING DEMOLITION - COMPRESSED AIR PIPE - 1-1/4"	20.0 LF	0.080	29.96	0.00	0.00					
							"	LF		48.	0.	0.	0.	0.	0.		48.
123	C6A					0 0	PLUMBING DEMOLITION - COMPRESSED AIR PIPE - 1"	270.0 LF	0.080	29.96	0.00	0.00					
							"	LF		647.	0.	0.	0.	0.	0.		647.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdw				J A	o c Cntrct		Take-Off Item	Quantity	- - - L a b o r - - -			Material		Const Equip		Sub	Item
Item	1	2	3	4	Trd b	c Markup			Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd	Cntrct	
					ID F	t Tag	Description	Unit			Cost		Cost		Cost	Cost	Direct
124	C6A				0	0	PLUMBING DEMOLITION - COMPRESSED AIR PIPE E - 3/4"	135.0 LF	0.080	29.96	324.	0.00	0.	0.00	0.	0.	324.
125	C6A				0	0	PLUMBING DEMOLITION - VACUUM PIPE - 1-1/ 2"	110.0 LF	0.080	29.96	264.	0.00	0.	0.00	0.	0.	264.
126	C6A				0	0	PLUMBING DEMOLITION - VACUUM PIPE - 1-1/ 4"	100.0 LF	0.080	29.96	240.	0.00	0.	0.00	0.	0.	240.
127	C6A				0	0	PLUMBING DEMOLITION - VACUUM PIPE - 1"	235.0 LF	0.080	29.96	563.	0.00	0.	0.00	0.	0.	563.
128	C6A				0	0	PLUMBING DEMOLITION - VACUUM PIPE - 3/4"	165.0 LF	0.080	29.96	395.	0.00	0.	0.00	0.	0.	395.
129	C6A				0	0	PLUMBING DEMOLITION - ACID WASTE LINES - 4"	375.0 LF	0.106	29.96	1191.	0.00	0.	0.00	0.	0.	1191.
130	C6A				0	0	PLUMBING DEMOLITION - ACID WASTE LINES - 3"	190.0 LF	0.106	29.96	603.	0.00	0.	0.00	0.	0.	603.
131	C6A				0	0	PLUMBING DEMOLITION - ACID WASTE LINES - 2"	275.0 LF	0.080	29.96	659.	0.00	0.	0.00	0.	0.	659.
132	C6A				0	0	PLUMBING DEMOLITION - ACID WASTE LINES - 1-1/2"	170.0 LF	0.080	29.96	407.	0.00	0.	0.00	0.	0.	407.
133	C6A				0	0	PLUMBING DEMOLITION - SANITARY SEWER - 6 "	225.0 LF	0.320	29.96	2157.	0.00	0.	0.00	0.	0.	2157.
134	C6A				0	0	PLUMBING DEMOLITION - SANITARY SEWER - 4 "	220.0 LF	0.106	29.96	699.	0.00	0.	0.00	0.	0.	699.
135	C6A				0	0	PLUMBING DEMOLITION - SANITARY SEWER - 3 "	70.0 LF	0.106	29.96	222.	0.00	0.	0.00	0.	0.	222.
136	C6A				0	0	PLUMBING DEMOLITION - SANITARY SEWER - 2 "	50.0 LF	0.080	29.96	120.	0.00	0.	0.00	0.	0.	120.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn					J A	o c Cntrct		Take-Off Item		Quantity		L a b o r		Material		Const Equip		Sub	Item
Structure					Trd b	c Markup	c	Tag	Description	Unit	Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost	Cntrct Cost	Direct Cost
Item	1	2	3	4	ID F	t													
137	C6A					0	0		PLUMBING DEMOLITION	70.0	0.320	29.96		0.00		0.00			
									- ROOF DRAINS - 8"	LF			671.		0.		0.	0.	671.
138	C6A					0	0		PLUMBING DEMOLITION	100.0	0.320	29.96		0.00		0.00			
									- ROOF DRAINS - 6"	LF			959.		0.		0.	0.	959.
139	C6A					0	0		PLUMBING DEMOLITION	170.0	0.320	29.96		0.00		0.00			
									- ROOF DRAINS - 4"	LF			1630.		0.		0.	0.	1630.
140	C6A					0	0		PLUMBING DEMOLITION	50.0	0.106	29.96		0.00		0.00			
									- ROOF DRAINS - 3"	LF			159.		0.		0.	0.	159.
141	C6A					0	0		PLUMBING DEMOLITION	50.0	0.080	29.96		0.00		0.00			
									- ROOF DRAINS - 2"	LF			120.		0.		0.	0.	120.
142	C6A					0	0		PLUMBING DEMOLITION	100.0	0.080	29.96		0.00		0.00			
									- DEIONIZED WATER - 3/4"	LF			240.		0.		0.	0.	240.
143	C6A					0	0		PLUMBING DEMOLITION	30.0	0.080	29.96		0.00		0.00			
									- DEIONIZED WATER - 1/2"	LF			72.		0.		0.	0.	72.
144	C6A					0	0		PLUMBING DEMOLITION	40.0	0.080	29.96		0.00		0.00			
									- REFRIGERANT LIQUID - 1/2"	LF			96.		0.		0.	0.	96.
145	C6A					0	0		PLUMBING DEMOLITION	20.0	0.080	29.96		0.00		0.00			
									- REFRIGERANT SUCTION - 1-1/8"	LF			48.		0.		0.	0.	48.
146	C6A					0	0		PLUMBING DEMOLITION	20.0	4.000	29.96		0.00		0.00			
									- PLUMBING FIXTURES	EA			2397.		0.		0.	0.	2397.
147	C6A					0	0		PLUMBING DEMOLITION	1.0	240.000	15.48		0.00		0.00			
									- LOAD DEMOLISHED ITEMS & HAUL TO DUMP	LS			3715.		0.		0.	0.	3715.
148	C6A					0	0		TRUCK & DRIVER TO HAUL DEMOLISHED PLUMBING ITEMS TO DUMP	1.0	80.000	18.82		0.00		11.00#			
										LS			1506.		0.		880.	0.	2386.
149	C6A					0	0			0.0		0.00		0.00		0.00			
												0.		0.		0.		0.	0.
150	C6A					0	0		HVAC DEMOLITION - 24" DIA. DUCT GA 205	2481.0	0.009	29.96		0.00		0.00			
									LF	LBS			661.		0.		0.	0.	661.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdw				J	A	o c Cntrct		Take-Off Item	Description	Quantity	Unit	L a b o r			Material	Const Equip	Sub	Item
Structure				Trd	b	c	Markup					Factor	Rate	Ext'd	Rate	Rate	Cntrct	Direct
Item	1	2	3	4	ID	F	t	Tag						Cost	Ext'd	Ext'd	Cost	Cost
151 C6A					0	0			HVAC DEMOLITION - 22 " DIA. DUCT GA 370 LF	3848.0	LBS	0.009	29.96	1025.	0.00	0.00	0.00	1025.
152 C6A					0	0			HVAC DEMOLITION - 18 " DIA. DUCT GA 410 LF	3403.0	LBS	0.009	29.96	906.	0.00	0.00	0.00	906.
153 C6A					0	0			HVAC DEMOLITION - 75 " X 30" DUCT GA 380 LF	11590.0	LBS	0.009	29.96	3087.	0.00	0.00	0.00	3087.
154 C6A					0	0			HVAC DEMOLITION - 33 " X 24" DUCT GA 350 LF	5005.0	LBS	0.009	29.96	1333.	0.00	0.00	0.00	1333.
155 C6A					0	0			HVAC DEMOLITION - 14 " X 14" DUCT GA 125 LF	287.0	LBS	0.009	29.96	76.	0.00	0.00	0.00	76.
156 C6A					0	0			HVAC DEMOLITION - 8" X 4" DUCT GA 36 LF	50.0	LBS	0.009	29.96	13.	0.00	0.00	0.00	13.
157 C6A					0	0			HVAC DEMOLITION - HO T WATER HEATING S&R - 6"	160.0	LF	0.160	29.96	767.	0.00	0.00	0.00	767.
158 C6A					0	0			HVAC DEMOLITION - HO T WATER HEATING S&R - 4"	100.0	LF	0.053	29.96	159.	0.00	0.00	0.00	159.
159 C6A					0	0			HVAC DEMOLITION - HO T WATER HEATING S&R - 3"	130.0	LF	0.053	29.96	206.	0.00	0.00	0.00	206.
160 C6A					0	0			HVAC DEMOLITION - HO T WATER HEATING S&R, 2-1/2"	460.0	LF	0.053	29.96	730.	0.00	0.00	0.00	730.
161 C6A					0	0			HVAC DEMOLITION - HO T WATER HEATING S&R - 2"	566.0	LF	0.040	29.96	678.	0.00	0.00	0.00	678.
162 C6A					0	0			HVAC DEMOLITION - HO T WATER HEATING S&R, 1-1/2"	516.0	LF	0.040	29.96	618.	0.00	0.00	0.00	618.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J ID	A F	o b	c t	c Tag	Take-Off Item Description	Quantity	Unit	Labor			Material		Const Rate	Equip Ext'd Cost	Sub Cntrct Cost	Item Direct Cost
	1	2	3	4									Factor	Rate	Ext'd Cost	Rate	Ext'd Cost				
163	C6A						0	0		HVAC DEMOLITION - HOT WATER HEATING S&R, 1-1/4"	228.0	LF	0.040	29.96	273.	0.00	0.00	0.00	0.00	0.	273.
164	C6A						0	0		HVAC DEMOLITION - HOT WATER HEATING S&R - 1"	358.0	LF	0.040	29.96	429.	0.00	0.00	0.00	0.00	0.	429.
165	C6A						0	0		HVAC DEMOLITION - HOT WATER HEATING S&R - 3/4"	72.0	LF	0.040	29.96	86.	0.00	0.00	0.00	0.00	0.	86.
166	C6A						0	0		HVAC DEMOLITION - HOT WATER HEATING S&R - 1/2"	120.0	LF	0.040	29.96	144.	0.00	0.00	0.00	0.00	0.	144.
167	C6A						0	0		HVAC DEMOLITION - TRUCK & DRIVER TO HAUL TO DUMP	1.0	EA	80.000	18.82	1506.	0.00	11.00#	880.	0.	2386.	
168	C6A						0	0		HVAC DEMOLITION - LOAD AND HAUL TO DUMP	1.0	EA	240.000	15.48	3715.	0.00	0.00	0.00	0.00	0.	3715.
169	C6A						0	0		EQUIPMENT DEMOLITION - HOT WATER BOILER	2.0	EA	12.000	29.96	719.	0.00	0.00	0.00	0.00	0.	719.
170	C6A						0	0		EQUIPMENT DEMOLITION - H&V UNITS	5.0	EA	8.000	29.96	1198.	0.00	0.00	0.00	0.00	0.	1198.
171	C6A						0	0		EQUIPMENT DEMOLITION - HOT WATER PUMPS	7.0	EA	1.000	29.96	210.	0.00	0.00	0.00	0.00	0.	210.
172	C6A						0	0		EQUIPMENT DEMOLITION - EXPANSION TANKS	2.0	EA	1.000	29.96	60.	0.00	0.00	0.00	0.00	0.	60.
173	C6A						0	0		EQUIPMENT DEMOLITION - HOT WATER STORAGE TANK	1.0	EA	3.000	29.96	90.	0.00	0.00	0.00	0.00	0.	90.
174	C6A						0	0		EQUIPMENT DEMOLITION - GAS FIRED WATER HEATER	1.0	EA	5.000	29.96	150.	0.00	0.00	0.00	0.00	0.	150.
175	C6A						0	0		EQUIPMENT DEMOLITION - HOT WATER CIRCULATOR	1.0	EA	2.000	29.96	60.	0.00	0.00	0.00	0.00	0.	60.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J A	o c Cntrct		Quantity Unit	- - - - L a b o r - - - -			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4	Trd b ID F	c Markup Tag	Take-Off Description		Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
176	C6A					0	0	EQUIPMENT DEMOLITION	5.0	2.000	29.96	0.00	0.00				
								- EXHAUST FANS	EA		300.	0.	0.	0.	0.		300.
177	C6A					0	0	EQUIPMENT DEMOLITION	3.0	3.000	29.96	0.00	0.00				
								- AIR COMPRESSOR	EA		270.	0.	0.	0.	0.		270.
178	C6A					0	0	EQUIPMENT DEMOLITION	3.0	1.000	29.96	0.00	0.00				
								- AIR RECEIVERS	EA		90.	0.	0.	0.	0.		90.
179	C6A					0	0	EQUIPMENT DEMOLITION	3.0	1.000	29.96	0.00	0.00				
								- AFTER COOLERS	EA		90.	0.	0.	0.	0.		90.
180	C6A					0	0	EQUIPMENT DEMOLITION	1.0	1.000	29.96	0.00	0.00				
								- VACUUM PUMPS	EA		30.	0.	0.	0.	0.		30.
181	C6A					0	0	EQUIPMENT DEMOLITION	1.0	1.000	29.96	0.00	0.00				
								- VACUUM TANK	EA		30.	0.	0.	0.	0.		30.
182	C6A					0	0	EQUIPMENT DEMOLITION	1.0	3.000	29.96	0.00	0.00				
								- AIR CONDITIONER U	EA		90.	0.	0.	0.	0.		90.
								NIT									
183	C6A					0	0	EQUIPMENT DEMOLITION	4.0	6.000	29.96	0.00	0.00				
								- CENTRIFUGAL WALL	EA		719.	0.	0.	0.	0.		719.
								EXHAUST FAN									
184	C6A					0	0	EQUIPMENT DEMOLITION	2.0	2.000	29.96	0.00	0.00				
								- HORIZONTAL UNIT H	EA		120.	0.	0.	0.	0.		120.
								EATER									
185	C6A					0	0	EQUIPMENT DEMOLITION	2.0	6.000	29.96	0.00	0.00				
								- PROPELLER EXHAUST	EA		360.	0.	0.	0.	0.		360.
								FANS									
186	C6A					0	0	EQUIPMENT DEMOLITION	1.0	2.000	29.96	0.00	0.00				
								- VERTICAL UNIT HEA	EA		60.	0.	0.	0.	0.		60.
								TER									
187	C6A					0	0	REMOVE AND REPLACE S	1.0	20.000	29.96	0.00	0.00				
								EWAGE LIFT STATION	EA		599.	0.	0.	0.	0.		599.
188	C6A					0	0	EQUIPMENT DEMOLITION	18.0	2.000	29.96	0.00	0.00				
								- UNIT HEATERS	EA		1079.	0.	0.	0.	0.		1079.
189	C6A					0	0	EQUIPMENT DEMOLITION	1.0	64.000	29.96	0.00	0.00				
								- LOAD AND HAUL TO	LS		1917.	0.	0.	0.	0.		1917.
								DUMP									

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J A	o c Cntrct		- - - L a b o r - - -			Material		Const Equip		Sub	Item
Structure				Trd b	c Markup	Take-Off Item	Quantity	Factor	Rate Ext'd	Rate Ext'd	Rate Ext'd	Rate Ext'd	Cost	Cntrct	Direct
Item	1	2	3	4	ID F	t Tag Description	Unit		Cost	Cost	Cost	Cost		Cost	Cost
190	C6A				0	0 EQUIPMENT DEMOLITION - TRUCK AND DRIVER TO HAUL TO DUMP	1.0 LS	16.000	18.82 301.	0.00 0.	75.00# 1200.	0.	1501.		
191	C6A				0	0 ELECTRICAL DEMOLITIO N, INTERIOR LIGHTS - 8' LONG, 2 LAMP	155.0 EA	0.600	29.55 2748.	0.00 0.	0.00 0.	0.	2748.		
192	C6A				0	0 ELECTRICAL DEMOLITIO N, INT. LIGHTS - 8' LONG, 2 LAMP W/RELAY	54.0 EA	1.000	29.55 1596.	0.00 0.	0.00 0.	0.	1596.		
193	C6A				0	0 ELECTRICAL DEMOLITIO N, INT. LIGHTS - 4' LONG, 2 LAMP	7.0 EA	0.500	29.55 103.	0.00 0.	0.00 0.	0.	103.		
194	C6A				0	0 ELECTRICAL DEMOLITIO N, INT. LIGHTS - INC ANDESCENT	119.0 EA	0.500	29.55 1758.	0.00 0.	0.00 0.	0.	1758.		
195	C6A				0	0 ELECTRICAL DEMOLITIO N, EXT. LIGHTS - 1st FLOOR & BASEMENT	6.0 EA	1.000	29.55 177.	0.00 0.	0.00 0.	0.	177.		
196	C6A				0	0 ELECTRICAL DEMOLITIO N, BATTERY BACKUP LI GHTS-1st FLR & BSMT	11.0 EA	1.000	29.55 325.	0.00 0.	0.00 0.	0.	325.		
197	C6A				0	0 ELECTRICAL DEMOLITIO N - CDD-1, 30 AMP, 3 PH	1.0 EA	1.000	29.55 30.	0.00 0.	0.00 0.	0.	30.		
198	C6A				0	0 ELECTRICAL DEMOLITIO N - CDD-2, 60 AMP, 3 PH	1.0 EA	2.000	29.55 59.	0.00 0.	0.00 0.	0.	59.		
199	C6A				0	0 ELECTRICAL DEMOLITIO N - CDD-3, 125 AMP, 3PH	1.0 EA	2.000	29.55 59.	0.00 0.	0.00 0.	0.	59.		
200	C6A				0	0 ELECTRICAL DEMOLITIO N - CDD-4, 125 AMP, 3PH	1.0 EA	2.000	29.55 59.	0.00 0.	0.00 0.	0.	59.		
201	C6A				0	0 ELECTRICAL DEMOLITIO N - DUPLEX RECEPTACL ES	211.0 EA	0.100	29.55 624.	0.00 0.	0.00 0.	0.	624.		

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J A	o c Cntrct		L a b o r		Material		Const Equip		Sub		Item	
Structure				Trd b	c	Markup	Take-Off	Item	Quantity	Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd
Item	1	2	3	4	ID	F	t	Tag	Description	Unit		Cost	Cost	Cost	Cost	Cost
202	C6A						0	0	ELECTRICAL DEMOLITIO	16.0	0.100	29.55	0.00	0.00		
									N - 30 AMP, 3PH RECE	EA		47.	0.	0.	0.	47.
									PTACLES							
203	C6A						0	0	ELECTRICAL DEMOLITIO	55.0	0.100	29.55	0.00	0.00		
									N - SWITCHES	EA		163.	0.	0.	0.	163.
204	C6A						0	0	ELECTRICAL DEMOLITIO	25.0	0.500	29.55	0.00	0.00		
									N - CLOCKS	EA		369.	0.	0.	0.	369.
205	C6A						0	0	ELECTRICAL DEMOLITIO	13.0	0.200	29.55	0.00	0.00		
									N - PUSHBUTTONS	EA		77.	0.	0.	0.	77.
206	C6A						0	0	ELEC. DEMOLITION, PA	8.0	3.300	29.55	0.00	0.00		
									NELBOARDS - 208Y/120	EA		780.	0.	0.	0.	780.
									V AC,3PH,4W,100 AMP							
207	C6A						0	0	ELEC. DEMOLITION, PA	9.0	3.300	29.55	0.00	0.00		
									NELBOARDS - 208Y/120	EA		878.	0.	0.	0.	878.
									V AC,1PH,3W,100 AMP							
208	C6A						0	0	ELEC. DEMOLITION, PA	18.0	6.670	29.55	0.00	0.00		
									NELBOARDS - 208Y/120	EA		3548.	0.	0.	0.	3548.
									V AC,3PH,4W,225 AMP							
209	C6A						0	0	ELEC. DEMOLITION, PA	2.0	6.670	29.55	0.00	0.00		
									NELBOARDS - 208Y/120	EA		394.	0.	0.	0.	394.
									V AC,3PH,4W,200 AMP							
210	C6A						0	0	ELEC. DEMOLITION, PA	1.0	3.300	29.55	0.00	0.00		
									NELBOARDS - 208Y/120	EA		98.	0.	0.	0.	98.
									V AC,3PH,4W,150 AMP							
211	C6A						0	0	ELEC. DEMOLITION, PA	1.0	6.670	29.55	0.00	0.00		
									NELBOARDS - 208Y/120	EA		197.	0.	0.	0.	197.
									V AC,3PH,4W,375 AMP							
212	C6A						0	0	ELEC. DEMO., PANELBO	1.0	10.000	29.55	0.00	0.00		
									ARDS PP-C 480V AC,3	EA		296.	0.	0.	0.	296.
									PH,3W,250 AMP,36CKTS							
213	C6A						0	0	ELEC. DEMO., PANELBO	1.0	10.000	29.55	0.00	0.00		
									ARDS PP-A 480V AC,3	EA		296.	0.	0.	0.	296.
									PH,3W,250 AMP,28CKTS							
214	C6A						0	0	ELEC. DEMO., PNL BRD	1.0	10.000	29.55	0.00	0.00		
									S PP-B 480Y/277V AC,	EA		296.	0.	0.	0.	296.
									3PH,4W,225 AMP,30CKT							

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c Trd b ID F	A c Markup Tag	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
215	C6A				0	0	ELEC. DEMO., PNL BRD S PP-A 480Y/277V AC, 3PH,4W,100 AMP,34CKT	1.0 EA	10.000	29.55	0.00	0.00					
										296.	0.	0.	0.			0.	296.
216	C6A				0	0	ELEC. DEMO., PNL BRD S PP-1 208Y/120V AC, 3PH,4W,225 AMP	1.0 EA	10.000	29.55	0.00	0.00				0.	296.
										296.	0.	0.	0.			0.	
217	C6A				0	0	ELEC. DEMO., DISCONN ETION OF SAFETY DISC ONNECT SWITCHES	80.0 EA	0.750	29.55	0.00	0.00				0.	1773.
										1773.	0.	0.	0.			0.	
218	C6A				0	0	ELEC. DEMO., REMOVAL OF SAFETY DISCONN EC T SWITCHES	80.0 EA	0.750	29.55	0.00	0.00				0.	1773.
										1773.	0.	0.	0.			0.	
219	C6A				0	0	ELEC. DEMO., 5 HP MO TOR DISCONNECTION	79.0 EA	0.500	29.55	0.00	0.00				0.	1167.
										1167.	0.	0.	0.			0.	
220	C6A				0	0	ELEC. DEMO., 10 HP M OTOR DISCONNECTION	10.0 EA	0.500	29.55	0.00	0.00				0.	148.
										148.	0.	0.	0.			0.	
221	C6A				0	0	ELEC. DEMO., 25 HP M OTOR DISCONNECTION	17.0 EA	1.000	29.55	0.00	0.00				0.	502.
										502.	0.	0.	0.			0.	
222	C6A				0	0	ELEC. DEMO., 30 HP M OTOR DISCONNECTION	5.0 EA	1.000	29.55	0.00	0.00				0.	148.
										148.	0.	0.	0.			0.	
223	C6A				0	0	ELEC. DEMO., 15 KW H EATER DISCONNECTION	2.0 EA	0.500	29.55	0.00	0.00				0.	30.
										30.	0.	0.	0.			0.	
224	C6A				0	0	ELEC. DEMO., 20 KW H EATER DISCONNECTION	6.0 EA	0.500	29.55	0.00	0.00				0.	89.
										89.	0.	0.	0.			0.	
225	C6A				0	0	ELEC. DEMO., 30 KW H EATER DISCONNECTION	2.0 EA	0.500	29.55	0.00	0.00				0.	30.
										30.	0.	0.	0.			0.	
226	C6A				0	0	ELEC. DEMO., 45 KW H EATER DISCONNECTION	1.0 EA	0.500	29.55	0.00	0.00				0.	15.
										15.	0.	0.	0.			0.	
227	C6A				0	0	ELEC. DEMO., 50 KW H EATER DISCONNECTION	4.0 EA	0.500	29.55	0.00	0.00				0.	59.
										59.	0.	0.	0.			0.	
228	C6A				0	0	ELEC. DEMO., 54 KW H EATER DISCONNECTION	1.0 EA	0.500	29.55	0.00	0.00				0.	15.
										15.	0.	0.	0.			0.	
229	C6A				0	0	ELEC. DEMO., TOPAZ P OWER CONDITIONERS - 208Y/120V AC	2.0 EA	12.000	29.55	0.00	0.00				0.	709.
										709.	0.	0.	0.			0.	

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn Structure				J A	o c Cntrct		Take-Off Item Description	Quantity Unit	- - - - L a b o r - - - -			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
Item	1	2	3	4	Trd b ID F	c Markup t Tag			Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
230	C6A					0 0	ELEC. DEMO., SWITCHBOARD - SWB-A 480V AC, 3PH, 3W, 2000A BUS	1.0 EA	12.000	29.55	355.	0.00	0.	0.00	0.	0.	355.
231	C6A					0 0	ELEC. DEMO., SWITCHBOARD - SWB-1 208Y/120V AC, 3PH, 4W, 600A	1.0 EA	12.000	29.55	355.	0.00	0.	0.00	0.	0.	355.
232	C6A					0 0	ELEC. DEMO., SUBSTATION - SUS-A, 480V AC, 3PH, 3W, 600AMP	1.0 EA	40.000	29.55	1182.	0.00	0.	0.00	0.	0.	1182.
233	C6A					0 0	ELEC. DEMO., 750 KVA TRANSFORMER REMOVAL	1.0 EA	40.000	29.55	1182.	0.00	0.	0.00	0.	0.	1182.
234	C6A					0 0	ELEC. DEMO., EQUIPMENT RENTAL FOR TRANSFORMER REMOVAL	1.0 LS		29.55	0.	0.00	0.	1000.00	1000.	0.	1000.
235	C6A					0 0	ELEC. DEMO., REMOVE/DEMOLISH TRANSFORMER PAD	1.0 EA	16.000	15.48	248.	0.00	0.	0.00	0.	0.	248.
236	C6A					0 0	ELEC. DEMO., HAUL DEMOLISH TRANSFORMER PAD TO HAZ. DISPOSAL	1.0 EA	8.000	18.82	151.	0.00	0.	75.00#	600.	0.	751.
237	C6A					0 0	ELEC. DEMO., MCC-A, 480V AC, 3PH, 3W, 600 AMP, 43 CU	1.0 EA	43.000	29.55	1271.	0.00	0.	0.00	0.	0.	1271.
238	C6A					0 0	ELEC. DEMO., MCC-C, 480V AC, 3PH, 3W, 600 AMP, 26 CU	1.0 EA	26.000	29.55	768.	0.00	0.	0.00	0.	0.	768.
239	C6A					0 0	ELEC. DEMO., MCC-3, 208Y/120V AC, 3PH, 4W, 600 AMP, 11 CU	1.0 EA	11.000	29.55	325.	0.00	0.	0.00	0.	0.	325.
240	C6A					0 0	ELEC. DEMO., MCC-4, 208Y/120V AC, 3PH, 4W, 600 AMP, 12 CU	1.0 EA	12.000	29.55	355.	0.00	0.	0.00	0.	0.	355.
241	C6A					0 0	ELEC. DEMO., MCC-5, 208Y/120V AC, 3PH, 4W, 600 AMP, 5 CU	1.0 EA	5.000	29.55	148.	0.00	0.	0.00	0.	0.	148.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	o c Cntrct		Take-Off Item	Quantity	L a b o r			Material		Const Equip		Sub	Item
Structure				Trd b	ID F	c Markup	t Tag			Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd		
Item	1	2	3	4	ID F	t Tag	Description	Unit				Cost	Cost	Cost	Cost	Cost	Cost	Direct
242	C6A					0 0	ELEC. DEMO., MCC-2, 208Y/120V AC, 3PH, 4 W, 600 AMP, 5 CU	1.0 EA	5.000	29.55		148.	0.00	0.	0.00	0.	0.	148.
243	C6A					0 0	ELEC. DEMO., MCC-B, 480V AC, 3PH, 3W, 60 0 AMP, 41 CU	1.0 EA	41.000	29.55		1212.	0.00	0.	0.00	0.	0.	1212.
244	C6A					0 0	ELEC. DEMO., MCC-A, 480V AC, 3PH, 3W, 60 0 AMP, 31 CU	1.0 EA	31.000	29.55		916.	0.00	0.	0.00	0.	0.	916.
245	C6A					0 0	ELEC. DEMO., GMC-A, 480V AC, 3PH, 3W, 10 0 AMP, 4 CU	1.0 EA	4.000	29.55		118.	0.00	0.	0.00	0.	0.	118.
246	C6A					0 0	ELEC. DEMO., TR-3, 3 0KVA, 3PH, 480 TO 20 8Y/120V AC, 5.6% Z	1.0 EA	5.000	29.55		148.	0.00	0.	0.00	0.	0.	148.
247	C6A					0 0	ELEC. DEMO., TR-4, 3 0KVA, 3PH, 480 TO 20 8Y/120V AC, 5.6% Z	1.0 EA	5.000	29.55		148.	0.00	0.	0.00	0.	0.	148.
248	C6A					0 0	ELEC. DEMO., TR-1, 1 5KVA, 3PH, 480 TO 20 8Y/120V AC, 2.8% Z	1.0 EA	4.000	29.55		118.	0.00	0.	0.00	0.	0.	118.
249	C6A					0 0	ELEC. DEMO., TR-2, 4 5KVA, 3PH, 480 TO 20 8Y/120V AC, 3.5% Z	1.0 EA	5.000	29.55		148.	0.00	0.	0.00	0.	0.	148.
250	C6A					0 0	ELEC. DEMO., TR-5, 4 5KVA, 3PH, 480 TO 20 8Y/120V AC, 5.3% Z	1.0 EA	5.000	29.55		148.	0.00	0.	0.00	0.	0.	148.
251	C6A					0 0	ELEC. DEMO., TR-?, 1 00VA, 1PH, 480 TO 20 8Y/120V AC	1.0 EA	1.000	29.55		30.	0.00	0.	0.00	0.	0.	30.
252	C6A					0 0	ELEC. DEMO., TR-1, 3 00KVA, 3PH, 480 TO 2 08Y/120V AC ??? Z	1.0 EA	12.000	29.55		355.	0.00	0.	0.00	0.	0.	355.
253	C6A					0 0	ELEC. DEMO., TR-6, 7 .5KVA, 3PH, 208Y/120 V AC ??? Z	1.0 EA	4.000	29.55		118.	0.00	0.	0.00	0.	0.	118.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J A	o c Cntrct		Take-Off Item	Quantity	- - - - L a b o r - - - -			Material		Const Equip		Sub	Item
Structure				Trd b	c Markup	c Tag			Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd	Cntrct	
Item	1	2	3	4	ID F	t	Description	Unit			Cost		Cost		Cost	Cost	Direct
254	C6A				0	0	ELEC. DEMO., TR-1, 1 5KVA, 1PH, 480 TO 20 8Y/120V, 1.5% Z	1.0 EA	2.000	29.55	59.	0.00	0.	0.00	0.	0.	59.
255	C6A				0	0	ELEC. DEMO., TR-1, 3 0KVA, 3PH, 480 TO 20 8Y/120V, 5.6% Z	1.0 EA	5.000	29.55	148.	0.00	0.	0.00	0.	0.	148.
256	C6A				0	0	ELEC. DEMO., TR-??, 3KVA, 3PH, 480 TO 20 8Y/120V	1.0 EA	2.000	29.55	59.	0.00	0.	0.00	0.	0.	59.
257	C6A				0	0	ELEC. DEMO., TR-??, 3KVA, 3PH, 480 TO 20 8Y/120V	1.0 EA	2.000	29.55	59.	0.00	0.	0.00	0.	0.	59.
258	C6A				0	0	ELEC. DEMO., TR-??, 3KVA, 3PH, 480 TO 20 8Y/120V	1.0 EA	2.000	29.55	59.	0.00	0.	0.00	0.	0.	59.
259	C6A				0	0	ELEC. DEMO., TR-??, 3KVA, 3PH, 480 TO 20 8Y/120V	1.0 EA	2.000	29.55	59.	0.00	0.	0.00	0.	0.	59.
260	C6A				0	0	ELEC. DEMO., CNTL XF MR 0.25KVA, 1PH, 480 TO 240/120	1.0 EA	1.000	29.55	30.	0.00	0.	0.00	0.	0.	30.
261	C6A				0	0	ELEC. DEMO., XS-A, 1 00 AMP, 480V RECP.	1.0 EA	0.500	29.55	15.	0.00	0.	0.00	0.	0.	15.
262	C6A				0	0	ELEC. DEMO., XS-B, 6 0 AMP, 480V RECP.	1.0 EA	0.500	29.55	15.	0.00	0.	0.00	0.	0.	15.
263	C6A				0	0	ELEC. DEMO., XFER SW ITCHES - 100 A	1.0 EA	1.800	29.55	53.	0.00	0.	0.00	0.	0.	53.
264	C6A				0	0	ELEC. DEMO., XFER SW ITCHES - 60 A	1.0 EA	1.400	29.55	41.	0.00	0.	0.00	0.	0.	41.
265	C6A				0	0	ELECTRIC DEMO. - FIRE DETECTORS	125.0 EA	0.600	29.55	2216.	0.00	0.	0.00	0.	0.	2216.
266	C6A				0	0	ELECTRIC DEMO. - MANUAL PULL STATIONS	16.0 EA	2.000	29.55	946.	0.00	0.	0.00	0.	0.	946.
267	C6A				0	0	ELECTRIC DEMO. - EVACUATION HORNS	21.0 EA	1.000	29.55	621.	0.00	0.	0.00	0.	0.	621.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdw Structure				J o c t r c t	A c t i v e	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
268 C6A					0	0	ELECTRIC DEMO. - PRESSURE SWITCH	2.0 EA	1.000	29.55	59.	0.00	0.	0.00	0.	0.	59.
269 C6A					0	0	ELECTRIC DEMO. - POST INDICATOR VALVE	3.0 EA	1.000	29.55	89.	0.00	0.	0.00	0.	0.	89.
270 C6A					0	0	ELECTRIC DEMO. - MASTER FIRE ALARM	1.0 EA	2.000	29.55	59.	0.00	0.	0.00	0.	0.	59.
271 C6A					0	0	ELECTRIC DEMO. - SUPERVISORY TRANS.	1.0 EA	1.000	29.55	30.	0.00	0.	0.00	0.	0.	30.
272 C6A					0	0	ELECTRIC DEMO. - JURISDICTIONAL TERMINAL BOX	1.0 EA	4.000	29.55	118.	0.00	0.	0.00	0.	0.	118.
273 C6A					0	0	ELECTRIC DEMO. - RIGID GALV. CONDUIT	2480.0 LF	0.033	29.55	2418.	0.00	0.	0.00	0.	0.	2418.
274 C6A					0	0	ELECTRIC DEMO. - #16 WIRE	49.6 CLF	0.123	29.55	180.	0.00	0.	0.00	0.	0.	180.
275 C6A					0	0	ELECTRIC DEMO. - J-BOX	11.0 EA	0.100	29.55	33.	0.00	0.	0.00	0.	0.	33.
276 C6A					0	0	ELECTRIC DEMO. - FIRE ALARM PANEL	1.0 EA	8.000	29.55	236.	0.00	0.	0.00	0.	0.	236.
277 C6A					0	0	ELECTRIC DEMO. - LOW AIR SWITCH	1.0 EA	1.000	29.55	30.	0.00	0.	0.00	0.	0.	30.
278 C6A					0	0	ELECTRIC DEMO. - RGC AVE. 1" DIA	10686.0 LF	0.033	29.55	10420.	0.00	0.	0.00	0.	0.	10420.
279 C6A					0	0	ELECTRIC DEMO. - WIRE	326.0 CLF	0.145	29.55	1397.	0.00	0.	0.00	0.	0.	1397.
280 C6A					0	0	ELECTRIC DEMO. - WIRE #12	228.0 CLF	0.145	29.55	977.	0.00	0.	0.00	0.	0.	977.
281 C6A					0	0	ELECTRIC DEMO. - WIRE #8 AWG	80.0 CLF	0.198	29.55	468.	0.00	0.	0.00	0.	0.	468.
282 C6A					0	0	ELECTRIC DEMO. - WIRE #2 AWG	26.0 CLF	0.359	29.55	276.	0.00	0.	0.00	0.	0.	276.
283 C6A					0	0	ELECTRIC DEMO. - WIRE 350 MCM	44.8 CLF	0.889	29.55	1177.	0.00	0.	0.00	0.	0.	1177.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdwn Structure				J o c ID F	A c t Tag	Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
284 C6A					0	0	ELECTRIC DEMO. - WIRE #4 AWG	13.0 CLF	0.302	29.55	116.	0.00	0.	0.00	0.	0.	116.
285 C6A					0	0	ELECTRIC DEMO. - WIRE #4/0 AWG	42.0 CLF	0.727	29.55	902.	0.00	0.	0.00	0.	0.	902.
286 C6A					0	0	ELECTRIC DEMO. - WIRE #1/0 AWG	6.0 CLF	0.482	29.55	85.	0.00	0.	0.00	0.	0.	85.
287 C6A					0	0	ELECTRIC DEMO. - WIRE #3/0 AWG	2.0 CLF	0.640	29.55	38.	0.00	0.	0.00	0.	0.	38.
288 C6A					0	0	ELECTRIC DEMO. - CONDUIT 3/4"	6300.0 LF	0.033	29.55	6143.	0.00	0.	0.00	0.	0.	6143.
289 C6A					0	0	ELECTRIC DEMO. - CONDUIT 1"	2000.0 LF	0.033	29.55	1950.	0.00	0.	0.00	0.	0.	1950.
290 C6A					0	0	ELECTRIC DEMO. - CONDUIT 1-1/4"	750.0 LF	0.040	29.55	887.	0.00	0.	0.00	0.	0.	887.
291 C6A					0	0	ELECTRIC DEMO. - CONDUIT 2-1/2"	1050.0 LF	0.053	29.55	1644.	0.00	0.	0.00	0.	0.	1644.
292 C6A					0	0	ELECTRIC DEMO. - CONDUIT 3	800.0 LF	0.053	29.55	1253.	0.00	0.	0.00	0.	0.	1253.
293 C6A					0	0	ELECTRIC DEMO. - EQUIPMENT RENTAL	1.0 DAY	1.000	0.00	0.	0.00	0.	500.00	500.	0.	500.
294 C6A					0	0	CIVIL DEMO UTIL SEWAGE LIFT STATION	2.0 EA	120.000	15.48	3715.	0.00	0.	0.00	0.	0.	3715.
295 C6A					0	0	CIVIL DEMO UTIL SEWAGE LIFT STATION	2.0 EA	40.000	22.99	1839.	0.00	0.	1500.00	3000.	0.	4839.
296 C6A					0	0	CIVIL DEMO UTIL 6" VCP SEWER PIPE	450.0 LF	0.160	19.24	1385.	0.00	0.	0.50	225.	0.	1610.
297 C6A					0	0	CIVIL DEMO UTIL 4" VCP SEWER PIPE	150.0 LF	0.100	19.24	289.	0.00	0.	0.50	75.	0.	364.
298 C6A					0	0	CIVIL DEMO UTIL PIV	1.0 EA	3.400	29.96	102.	0.00	0.	0.00	0.	0.	102.
299 C6A					0	0	CIVIL DEMO UTIL FIRE HYDRANT	2.0 EA	3.400	29.96	204.	0.00	0.	0.00	0.	0.	204.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdw Structure				J o	A c	Cntrct		Take-Off Item Description	Quantity Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
Item	1	2	3	4	Trd ID	b F	c t	Markup Tag		Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
300	C6A						0	0	CIVIL DEMO UTIL 6" CAST IRON WATER PIPE	200.0 LF	0.160	19.23 615.	0.00 0.	0.50 100.		0.	0.	715.
301	C6A						0	0	CIVIL DEMO UTIL 6" TREATED WATER PIPE	600.0 LF	0.160	19.23 1846.	0.00 0.	0.50 300.		0.	0.	2146.
302	C6A						0	0	CIVIL DEMO UTIL 8" TREATED WATER PIPE	500.0 LF	0.160	19.23 1538.	0.00 0.	0.50 250.		0.	0.	1788.
303	C6A						0	0	CIVIL DEMO UTIL 2" STEEL & SMALLER PIPE	350.0 LF	0.040	19.23 269.	0.00 0.	0.00 0.		0.	0.	269.
304	C6A						0	0	CIVIL DEMO UTIL GAS PRV STA.	4.0 EA	5.200	29.96 623.	0.00 0.	0.00 0.		0.	0.	623.
305	C6A						0	0	CIVIL DEMO UTIL 2" GAS PIPE	260.0 LF	0.400	19.24 2001.	0.00 0.	0.00 0.		0.	0.	2001.
306	C6A						0	0	CIVIL DEMO UTIL 1.5" GAS PIPE	300.0 LF	0.400	19.24 2309.	0.00 0.	0.00 0.		0.	0.	2309.
307	C6A						0	0	CIVIL DEMO UTIL 1" GAS PIPE	100.0 LF	0.400	19.24 770.	0.00 0.	0.00 0.		0.	0.	770.
308	C6A						0	0	CIVIL DEMO UTIL CMP	200.0 LF	0.130	19.24 500.	0.00 0.	0.00 0.		0.	0.	500.
309	C6A						0	0	CIVIL DEMO UTIL CATCH BASIN - STORM WATER	4.0 EA	1.850	19.24 142.	0.00 0.	14.00 56.		0.	0.	198.
310	C6A						0	0	CIVIL DEMO UTIL ASPHALT PAVING	450.0 SY	0.057	19.24 494.	0.00 0.	1.56 702.		0.	0.	1196.
311	C6A						0	0	CIVIL DEMO UTIL MISC. CONC. PADS - 6" THICK	400.0 SF	0.062	19.24 477.	0.00 0.	0.16 64.		0.	0.	541.
312	C6A						0	0	CIVIL DEMO UTIL MISC. GUARD POSTS	50.0 EA	2.000	19.24 924.	0.00 0.	2.50 125.		0.	0.	2049.
313	C6A						0	0	CIVIL DEMO UTIL FENCING	500.0 FT	0.051	15.48 395.	0.00 0.	0.00 0.		0.	0.	395.

Work Brkdwn Structure				J o c Cntrct	Take-Off Item	Quantity	L a b o r			Material		Const Equip		Sub	Item		
Item	1	2	3	4	Trd b c Markup	Tag	Description	Unit	Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost	Cntrct Cost	Direct Cost
314	C6A				0 0		CIVIL DEMO UTIL CLARIFLOCCULATORS	2.0 EA			0.00	0.00		0.00			
315	C6A				0 0		CIVIL DEMO UTIL EQUIP. PADS	30.0 EA			0.00	0.00		0.00		8000.	8000.
316	C6A				0 0		CIVIL DEMO UTIL GRIT CHAMBER	1.0 EA			0.00	0.00		0.00		1500.	1500.
317	C6A				0 0		CIVIL DEMO UTIL FILTER HOUSING	1.0 EA			0.00	0.00		0.00		500.	500.
318	C6A				0 0		CIVIL DEMO UTIL MISC. EQUIP. FDN.	1.0 LOT			0.00	0.00		0.00		1000.	1000.
319	C6A				0 0		CIVIL DEMO UTIL MONORAIL CRANES	4.0 EA			0.00	0.00		0.00		500.	500.
320	C6A				0 0		CIVIL DEMO UTIL CMU BLK. WALLS	1000.0 SF			0.00	0.00		0.00		400.	400.
321	C6A				0 0		CIVIL DEMO UTIL CONC. UTILITY TRENCH	50.0 LF			0.00	0.00		0.00		2000.	2000.
322	C6A				0 0		CIVIL DEMO UTIL MISC. CONC. ITEMS	1.0 LOT			0.00	0.00		0.00		600.	600.
323	C6A				0 0		CIVIL DEMO UTIL BUILDING STEPS	1.0 LOT			0.00	0.00		0.00		1000.	1000.
324	C6A				0 0		CIVIL DEMO UTIL EMBEDDMENT	1.0 LOT			0.00	0.00		0.00		500.	500.
464	C6A				0 0		DEMOLITION OF EXISTING D&D AREA - PRE-ENGINEERED BUILDING	28005.0 CF	0.003	22.53	635.	0.00		0.02		200.	200.
465	C6A				0 0		DEMOLITION OF TECH SUPPORT AREA GYPSUM WALLS	1920.0 SF	0.022	15.48	295.	0.00		0.00		0.	654.
466	C6A				0 0		DEMOLITION OF TECH SUPPORT AREA CEILING	19784.0 SF	0.022	15.48	305.	0.00		0.00		0.	6738.
467	C6A				0 0		DEMOLITION OF TECH SUPPORT AREA FLOORING	19784.0 SF	0.022	15.48	305.	0.00		0.00		0.	6738.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	o c		Cntrct		Take-Off Item	Quantity	Unit	L a b o r			Material		Const Equip		Sub	Item
Item	1	2	3	4	ID	F	b	c	Markup				Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd		
									Tag	Description					Cost		Cost		Cost	Cost	Cost
468 C6A								0	0	DEMOLITION OF TECH SUPPORT AREA WINDOWS & FRAMES	15.0	EA	0.889	15.48	206.	0.00	0.	0.00	0.	0.	206.
469 C6A								0	0	DEMOLITION OF TECH SUPPORT AREA DOORS	6.0	EA	0.667	15.48	62.	0.00	0.	0.00	0.	0.	62.
470 C6A								0	0	DEMOLITION OF TECH SUPPORT AREA INTERIOR DOORS	50.0	EA	0.400	15.48	310.	0.00	0.	0.00	0.	0.	310.
487 C6A								0	0	PROCESS AREA BSMNT DEMO EXTERIOR DOORS	4.0	EA	0.667	15.48	41.	0.00	0.	0.00	0.	0.	41.
488 C6A								0	0	PROCESS AREA BSMNT DEMO EXISTING ELEVAT OR	1.0	LS		0.00	0.	0.00	0.	0.00	0.	10000.	10000.
489 C6A								0	0	PROCESS AREA BSMNT PREP FOR PAINT	29675.0	SF	0.009	15.48	4134.	0.14	4155.	0.00	0.	0.	8289.
490 C6A								0	0	PROCESS AREA BSMNT MISC DEMO	1.0	LS	1.000	5000.00	5000.	0.00	0.	0.00	0.	0.	5000.
496 C6A								0	0	PROCESS AREA 1st FLR DEMO WALLS	600.0	SF	0.022	15.48	204.	0.00	0.	0.00	0.	0.	204.
497 C6A								0	0	PROCESS AREA 1st FLR DEMO FLOORING	1600.0	SF	0.011	15.48	272.	0.00	0.	0.00	0.	0.	272.
498 C6A								0	0	PROCESS AREA 1st FLR DEMO DOORS	4.0	EA	0.400	15.48	25.	0.00	0.	0.00	0.	0.	25.
499 C6A								0	0	PROCESS AREA 1st FLR DEMO STEEL WINDOWS	7.0	EA	0.889	15.48	96.	0.00	0.	0.00	0.	0.	96.
507 C6A								0	0	COMPUTER/CONTROL RM DEMO INT PARTITION	760.0	SF	0.022	15.48	259.	0.00	0.	0.00	0.	0.	259.
508 C6A								0	0	COMPUTER/CONTROL RM DEMO WINDOWS & FRAM E	1.0	EA	0.889	15.48	14.	0.00	0.	0.00	0.	0.	14.
509 C6A								0	0	COMPUTER/CONTROL RM DEMO CEILING SYSTEM S	1010.0	SF	0.022	15.48	344.	0.00	0.	0.00	0.	0.	344.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	o c Cntrct		Take-Off Item	Quantity	L a b o r			Material		Const Equip	Sub		Item
Structure				Trd	b	c	Mark			Factor	Rate	Ext'd	Rate	Ext'd	Rate	Ext'd	Cntrct	
Item	1	2	3	4	ID	F	t	Tag	Unit			Cost		Cost		Cost	Cost	Direct
510	C6A						0	0	COMPUTER/CONTROL RM	1010.0	0.011	15.48	0.00		0.00			
									DEM FLOORING	SF		172.	0.	0.			0.	172.
511	C6A						0	0	COMPUTER/CONTROL RM	2.0	0.400	15.48	0.00		0.00			
									DEM DOORS	EA		12.	0.	0.			0.	12.
626	C6A						0	0	COLD WAREHOUSE	36000.0	0.200	22.53	0.00		0.01			
									DEM EXISTING BLDG	CF		162216.	0.	360.			0.	162576.
									83									
627	C6A						0	0	COLD WAREHOUSE	2400.0	0.471	15.48	0.00		0.10			
									DEM SLAB	SF		17499.	0.	240.			0.	17739.
696	C6A						0	0	DEM DOOR CHIMES	3.0	1.500	29.55	0.00		0.00			
										EA		133.	0.	0.			0.	133.
697	C6A						0	0	ELEC. DEMOLITION	1.0	10.000	29.55	0.00		0.00			
									PP-2, 208Y/120V AC,	EA		296.	0.	0.			0.	296.
									3PH, 4W, 225 AMP									
907	C6A						0	0	LOAD & HAUL STREET	1.0	80.000	17.15	0.00		11.00			
									AND EXTERIOR LIGHTS	LOT		1372.	0.	11.			0.	1383.
C6A Category Direct Cost												351208.	4155.		11128.		26200.	392690.
728	C6B						0	1	DECON. & DECOMM.	1.0		0.00	0.00		0.00			
									EXISTING FACILITY	LS		0.	0.		0.		10000000.	10000000.
C6B Category Direct Cost												0.	0.		0.		10000000.	10000000.
608	D1B						0	0	CHEMISTRY LAB	3000.0		0.00	47.00		0.00			
									MISC LAB FURNISHING	SF		0.	141000.		0.		0.	141000.
									S									
D1B Category Direct Cost												0.	141000.		0.		0.	141000.
400	D2A						0	0	TANK-1 WASTE WATER	1.0		0.00	0.00		0.00			
									RECEIVING	EA		0.	0.		0.		0.	0.
401	D2A						0	0	TANK-2,3 & 4 PH ADJ	3.0		0.00	0.00		0.00			
									& OXIDANT ADDITION	EA		0.	0.		0.		0.	0.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn				J	A	o c Cntrct		Take-Off Item	Quantity	L a b o r			Material		Const Equip		Sub	Item
Structure				Trd b	c	Markup	Factor			Rate	Ext'd	Rate	Ext'd	Rate	Ext'd	Cntrct		
Item	1	2	3	4	ID	F	t	Tag	Description	Unit			Cost	Cost	Cost	Cost	Cost	Cost
402	D2A					0	0		TANK-5,6,7 & 8 WASTE	4.0			0.00	0.00	0.00			
									WATER FEED STORAGE	EA			0.	0.	0.		304000.	304000.
403	D2A					0	0		TANK-9,10 & 11 INTER	3.0			0.00	0.00	0.00			
									M PROCESS STORAGE	EA			0.	0.	0.		210000.	210000.
404	D2A					0	0		TANK-12,13,&14 PRODU	3.0			0.00	0.00	0.00			
									CT RECYCLE	EA			0.	0.	0.		210000.	210000.
405	D2A					0	0		TANK-15,16,&17,18,19	6.0			0.00	0.00	0.00			
									&20 EFFLUENT STORAGE	EA			0.	0.	0.		420000.	420000.
406	D2A					0	0		TANK-21 22 1 X FEED	2.0			0.00	0.00	0.00			
										EA			0.	0.	0.		0.	0.
407	D2A					0	0		TANK-23 ACID FEED PH	1.0	6.000	29.96	3000.00	35.00				
									ADJUST	EA			180.	3000.	35.		0.	3215.
408	D2A					0	0		TANK-24 CAUSTICFEED	1.0	6.000	29.96	3000.00	35.00				
									PH ADJUST	EA			180.	3000.	35.		0.	3215.
409	D2A					0	0		TANK-25 CLARIFIED WA	1.0	4.000	29.96	1800.00	35.00				
									TER CATCH TANK	EA			120.	1800.	35.		0.	1955.
410	D2A					0	0		TANK-26 CONDENSATE C	1.0	4.000	29.96	1800.00	35.00				
									ATCH TANK	EA			120.	1800.	35.		0.	1955.
411	D2A					0	0		TANK-27 TRU CEMENT F	1.0	6.000	29.96	3000.00	35.00				
									EED TANK	EA			180.	3000.	35.		0.	3215.
412	D2A					0	0		TANK-28 1 X REGENER	1.0	10.000	29.96	5000.00	35.00				
									ATION RECEIVER	EA			300.	5000.	35.		0.	5335.
413	D2A					0	0		TANK-29 1 X ELUTION	1.0	10.000	29.96	5000.00	35.00				
									ACID PREP	EA			300.	5000.	35.		0.	5335.
414	D2A					0	0		TANK-30 1 X REGENER	1.0	10.000	29.96	5000.00	35.00				
									ATE PREP	EA			300.	5000.	35.		0.	5335.
415	D2A					0	0		TANK-31 CEMENT FEED	2.0	10.000	29.96	5000.00	35.00				
									TANK	EA			599.	10000.	70.		0.	10669.
416	D2A					0	0		P-1A,B TRANSFER PUMP	2.0	10.000	29.96	2100.00	35.00				
									S	EA			599.	4200.	70.		0.	4869.
417	D2A					0	0		P-2A,B MIXER/SETTLER	2.0	8.000	29.96	1750.00	35.00				
									FEED PUMPS	EA			479.	3500.	70.		0.	4049.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Work Brkdwn Structure				J A	o c		Cntrct		Quantity	Unit	L a b o r			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
Item	1	2	3	4	Trd b	ID F	t	Markup	Take-Off	Description	Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
418 D2A							0	0	P-3A,B	SLUDGE PUMPS	2.0	8.000	29.96	4000.00	0.00				
									EA				479.		8000.		0.	0.	8479.
419 D2A							0	0	P-4	SLUDGE PUMP	1.0	8.000	29.96	2000.00	0.00				
									EA				240.		2000.		0.	0.	2240.
420 D2A							0	0	P-5A,B	FILTER FEED P	2.0	8.000	29.96	1850.00	0.00				
									UMPS				479.		3700.		0.	0.	4179.
421 D2A							0	0	P-6A,B	FILTER FEED P	2.0	8.000	29.96	1850.00	0.00				
									UMPS				479.		3700.		0.	0.	4179.
422 D2A							0	0	PROCESS PIPING	(316 STAINLESS)	300.0	0.216	29.96	15.68	0.00				
									1-1/2"	LF			1941.		4704.		0.	0.	6645.
423 D2A							0	0	PROCESS PIPING	(316 STAINLESS)	300.0	0.184	29.96	10.17	0.00				
									1"	LF			1654.		3051.		0.	0.	4705.
424 D2A							0	0	P-7A,B	CONDENSATE TR	2.0	8.890	29.96	1800.00	0.00				
									ANSFER PUMPS	EA			533.		3600.		0.	0.	4133.
425 D2A							0	0	P-8A,B	1 X FEED PUMP	2.0	8.890	29.96	2100.00	0.00				
									S	EA			533.		4200.		0.	0.	4733.
426 D2A							0	0	P-9A,B	PROCESS FEED	2.0	8.890	29.96	1850.00	0.00				
									PUMPS	EA			533.		3700.		0.	0.	4233.
427 D2A							0	0	P-10A,B	RECYCLE PUMP	2.0	8.890	29.96	1850.00	0.00				
									S	EA			533.		3700.		0.	0.	4233.
428 D2A							0	0	P-11A,B	EFFLUENT DIS	2.0	8.890	29.96	3000.00	0.00				
									CHARGE PUMPS	EA			533.		6000.		0.	0.	6533.
429 D2A							0	0	P-12	1 X REGENERATIO	1.0	8.890	29.96	3750.00	0.00				
									N PRODUCT CYCLE	EA			266.		3750.		0.	0.	4016.
430 D2A							0	0	P-13	CAUSTIC REGENER	1.0	8.890	29.96	3750.00	0.00				
									ATION CIRCULATION PU	EA			266.		3750.		0.	0.	4016.
431 D2A							0	0	P-14	ACID REGENERATI	1.0	8.890	29.96	3750.00	0.00				
									ON CIRCULATION PUMP	EA			266.		3750.		0.	0.	4016.
432 D2A							0	0	P-15	SLURRY/CONCENTR	1.0	8.890	29.96	1800.00	0.00				
									ATE PUMP	EA			266.		1800.		0.	0.	2066.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdw Structure				J o c ID F	A c t Tag	Take-Off Item Description	Quantity Unit	- - - - L a b o r - - - -			Material		Const Equip		Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost	Rate	Ext'd Cost	Rate	Ext'd Cost		
433 D2A					0	0	EV-1 PRIMARY EVAPORA TOR	2.0 EA	120.000	29.96	7190.	450000.00	900000.	0.00	0.	0.	907190.
434 D2A					0	0	PROCESS SYSTEM INSTR UMENTATION	1.0 LS		29.96	0.	106468.00	106468.	0.00	0.	0.	106468.
435 D2A					0	0	PROCESS SYSTEM CARBO N STEEL PIPING - 3"	286.0 LF	0.372	29.96	3188.	6.19	1770.	0.00	0.	0.	4958.
436 D2A					0	0	PROCESS SYSTEM CARBO N STEEL PIPING - 2"	3588.0 LF	0.250	29.96	26874.	2.91	10441.	0.00	0.	0.	37315.
437 D2A					0	0	PROCESS SYSTEM CARBO N STEEL PIPING 1-1/2"	1650.0 LF	0.200	29.96	9887.	2.17	3581.	0.00	0.	0.	13467.
438 D2A					0	0	PROCESS SYSTEM CARBO N STEEL PIPING 1"	682.0 LF	0.151	29.96	3085.	1.49	1016.	0.00	0.	0.	4102.
439 D2A					0	0	PROCESS SYSTEM CARBO N STEEL PIPING 3/4"	500.0 LF	0.131	29.96	1962.	1.06	530.	0.00	0.	0.	2492.
440 D2A					0	0	PROCESS SYSTEM CARBO N STEEL PIPING 1/2"	500.0 LF	0.127	29.96	1902.	0.90	450.	0.00	0.	0.	2352.
494 D2A					0	0	PROCESS AREA BSMNT CONSTRUCT AIR LOCK	1.0 LS		0.00	0.	0.00	0.	0.00	0.	12000.	12000.
504 D2A					0	0	PROCESS AREA 1st FLR CONSTRUCT AIRLOCK	1.0 LS		0.00	0.	0.00	0.	0.00	0.	12000.	12000.
515 D2A					0	0	STACK MONITORING SYS TEMS	16.0 EA	80.000	30.29	38771.	250000.00	4000000.	0.00	0.	0.	4038771.
611 D2A					0	0	CHEMISTRY LAB SPECIALITIES	1.0 LS	1.000	1000.00	1000.	5000.00	5000.	0.00	0.	0.	6000.
625 D2A					0	0	TANK STORAGE 1 & 2 AIRLOCK	4.0 EA	1.000	2000.00	8000.	2000.00	8000.	0.00	0.	0.	16000.
689 D2A					0	0	PROCESS EQUIPMENT CEMENT MIXER (2 REQ'D)	1.0 LS		0.00	0.	0.00	0.	0.00	0.	135000.	135000.
690 D2A					0	0	ABSORBERS & TX COLUM NS (4 REQ'D)	1.0 LS		0.00	0.	0.00	0.	0.00	0.	270000.	270000.

[Items with '#' have been adjusted by Job Factor and/or Equip Factor]

Item	Work Brkdw Structure				J o c t r a c t	A c t i v i t y	Take-Off Item Description	Quantity Unit	L a b o r			Material Rate Ext'd Cost	Const Equip Rate Ext'd Cost	Sub Cntrct Cost	Item Direct Cost
	1	2	3	4					Factor	Rate	Ext'd Cost				
691 D2A					0	0	MOTOR VALVES W/O ACTUATORS (100 REQ'D)	1.0 LS		0.00	0.	0.00	0.	150000.	150000.
692 D2A					0	0	MISC. VALVES (200 REQ'D)	1.0 LS		0.00	0.	0.00	0.	60000.	60000.
693 D2A					0	0	GRAVITY THICKENER (1 REQ'D)	1.0 LS		0.00	0.	0.00	0.	70000.	70000.
694 D2A					0	0	HEAT EXCHANGER (2 REQ'D)	1.0 LS		0.00	0.	0.00	0.	24000.	24000.
695 D2A					0	0	CONCENTRATOR EU-2 (1 REQ'D)	1.0 LS		0.00	0.	0.00	0.	150000.	150000.
908 D2A					0	0	PROCESS EQUIPMENT HOOKUP	1.0 LOT		0.00	0.	0.00	0.	700000.	700000.
D2A							Category Direct Cost			114218.		5141961.	490.	2727000.	7983669.
607 D2B					0	0	CHEMISTRY LAB FUME HOODS	16.0 EA		0.00	0.	18000.00 288000.	0.00 0.	0.	288000.
D2B							Category Direct Cost			0.		288000.	0.	0.	288000.
911 E					0	4	PROJECT MANAGEMENT	1.0 LOT		0.00	0.	0.00	0.	5165905.	5165905.
E							Category Direct Cost			0.		0.	0.	5165905.	5165905.
Project Direct Cost										=====		=====		=====	=====
										8966445.		31174363.	425882.	32428177.	72994867.

IX. DRAWINGS

RADIOACTIVE LIQUID WASTE TREATMENT PLANT REFURBISHMENT

ARCHITECTURAL CIVIL SITE PLAN

1

LEGEND:

PROPOSED PROCESS EQUIPMENT

PROPOSED CONSTRUCTION

EXISTING CONSTRUCTION

RADIOACTIVE LIQUID WASTE TREATMENT PLANT REFURBISHMENT

BASEMENT FLOOR PLAN

2

Los Alamos

Los Alamos National Laboratory
Los Alamos, New Mexico 87545

PROJECT ID NO. 10411-50

ENG-PL 4104

FIRST FLOOR PLAN

SCALE: 1/16" = 1'-0"

10 0 10 20 30 40

scale feet

LEGEND:

PROPOSED PROCESS EQUIPMENT

PROPOSED CONSTRUCTION

EXISTING CONSTRUCTION

RADIOACTIVE LIQUID
WASTE TREATMENT
PLANT REFURBISHMENT

FIRST FLOOR PLAN

3

Los Alamos

PROJECT ID NO. 10411-50

Los Alamos National Laboratory
Los Alamos, New Mexico 87546
ENG-PL 4104

SECOND FLOOR
MECHANICAL PENTHOUSE

RADIOACTIVE LIQUID WASTE TREATMENT PLANT REFURBISHMENT

SECOND FLOOR MECHANICAL PENTHOUSE
AND PRELIMINARY EQUIPMENT LAYOUT

4

Los Alamos

Los Alamos National Laboratory
Los Alamos, New Mexico 87545
ENG-PL 4104

PROJECT ID NO. 10411-50

WEST
SCALE: 1/7

NOTE: ELEVATION OF CENTRAL PLANT AND PRETREATMENT
PLANT NOT SHOWN FOR CLARITY.

ELEVATION
= 1'-0"

RADIOACTIVE LIQUID WASTE TREATMENT PLANT REFURBISHMENT

ELEVATION

5

Los Alamos

Los Alamos National Laboratory
Los Alamos, New Mexico 87545
ENG-PL 4104

PROJECT ID NO. 10411-50

TK-1
RECEIVING TANK
- 13,000 GALLONS
- (EXISTING)
- STIRRED

P-1A,B
TRANSFER PUMPS
- CENTRIFUGAL
- 50 GPM
- 60 FT. HEAD

TK-23
NITRIC ACID
- 1,000 GALLONS

TK-24
CAUSTIC
- 1,000 GALLONS

HQ
DRY OXIDA
- STAR
- 1,00
- TAPE

TK-5 TO 8
EQUALIZATION
- 75,000 GALLONS
- STIRRED

P-9A,B
FEED PUMPS
- CENTRIFUGAL
- 25 GPM
- 50 FT. HEAD

P-11
ACID METER PUMP

P-12
CAUSTIC METERING PUMP

TK-2 TO 4
OXIDATION REACTOR
- 25,000 GALLONS
- STIRRED

P-
MIX/SETTLE
- CEN
- 50
- 60

S-1
SAMPLER
- 4 GAL/B HRS
- PROPORTIONAL TO FLOW

TK-12
- RECY
- 80,00
- STIRRED

NOTES:

○ STREAM NUMBERS

PROCESS SYSTEM FOR TANKS AND CONDENSERS NOT SHOWN.

	MS-1A,B MIXER SETTLER - 15 FT. Ø	P-10A,B RECYCLE PUMPS - 25 GPM - 80 FT. HEAD	P-5A,B FILTER FEED - 25 GPM	FIL-1A,B FEED FILTER - SINTERED METAL - CROSSFLOW
	P-3A,B SLUDGE PUMP - EXISTING		TK-9 TO 11 INTERIM STORAGE - 80,000 GALLONS	
	TH-1 GRAVITY THICKENER - 8 FT. Ø - 20 FT. HEIGHT - TAPERED BOTTOM	P-4 SLUDGE PUMP - ADVANCING GAVITY	P-6A,B EVAPORATOR - 25 GPM - 50 FT. HEAD

RADIOACTIVE LIQUID WASTE TREATMENT PLANT REFURBISHMENT

PROCESS FLOW DIAGRAM
SHEET 1

6

IX-1A,B
ION EXCHANGE
- MIXED BED
- 4' Ø
- 10' TALL TOTAL
- 6' BED DEPTH

TK-28
PRIMARY CONDENSATE
- 200 GALLONS

P-18
CONDENSATE RETURN
- 10 GPM

REGENERATION WASTE
- 5,000 GALLONS

P-12
REGEN RECYCLE
- 10 GPM

AD-1A,B
AC ADSORBERS
- 4' Ø
- 10' TALL
- 6' BED DEPTH

CAUSTIC
- 3,000 GALLONS

P-13
CAUSTIC
- 20 GPM

TK-26
CONDENSATE TANK
- 1,000 GALLONS

ACID
- 3,000 GALLONS

P-14
ACID
- 20 GPM

HX-4
COOLER

IX FEED TANK
- EXISTING

P-8A,B
IX FEED PUMP
- 25 GPM
- 100 FT. HEAD

EV-2
CONCENTRATOR
- 3 GPM
- WIPED FILM

3 EFFECT EVAPORATOR SKID (1 OF 2)

MATCH LINE
SHEET 1

EV-1A,B
EVAPORATOR
- 25 GPM
- 3 EFFECTS
- THERMORECOMPRESSION

HX-1
EVAPORATOR PREHEAT

HX-2
CONDENSER

P-15
CONCENTRATE PUMP
- 1 GPM

TK-27
SLUDGE HOLDING
- 1000 GALLONS

P-16
SLUDGE CIRCULATION

HX-3
STEAM GENERATOR
- 3750 lb/HR

MX-1
CEMENT MIXER

P-17
CEMENT CIRCULATION

S-2
SAMPLER
- 4 GAL/8 HR
- PROPORTIONAL
TO FLOW RATE

FIL-2A,B?
TK-15 TO 20
EFFLUENT HOLDING TANKS
- 60,000 GALLONS

P-11A,B
EFFLUENT DISCHARGE
- 75 GPM
- 60 FT. HEAD

RADIOACTIVE LIQUID
WASTE TREATMENT
PLANT REFURBISHMENT
PROCESS FLOW DIAGRAM
SHEET 2

Los Alamos
PROJECT ID NO. 10411-50
Los Alamos National Laboratory
Los Alamos, New Mexico 87545
ENG-PL 4104

RADIOACTIVE LIQUID
WASTE TREATMENT
PLANT REFURBISHMENT
FLOW DIAGRAM

8

SYSTEM #2. PROCESS

NOT TO SCALE

RADIOACTIVE LIQUID WASTE TREATMENT PLANT REFURBISHMENT MECHANICAL ONE-LINE

SYSTEM #3 - HOT SHOP/D & D
NOT TO SCALE

SYSTEM #4 & #5-2ND FLOOR MECHANICAL ROOM

NOT TO SCALE

PROCESS & D&D
EQUIPMENT

RADIOACTIVE LIQUID WASTE TREATMENT PLANT REFURBISHMENT

MECHANICAL ONE-LINE DIAGRAM

Los Alamos

PROJECT ID NO. 10411-50

Los Alamos National Laboratory
Los Alamos, New Mexico 87546
ENG-PL 4104

10

SYSTEM #6-HVAC CENTRAL PLANT
SYSTEM #7-COLD WAREHOUSE
 NOT TO SCALE

SYSTEM #8 - CONTROL ROOM

NOT TO SCALE

SYSTEM #9 - ANALYTICAL CHEMISTRY/CHANGE ROOMS

NOT TO SCALE

HEPA FILTERS

PRE-FILTERS AND DEMISTER

SPARK SUPPRESSION SYSTEM

SPARK ARRESTER SCREEN

RETURN AIR REGISTER (TYP)

AIRLOCK

TO PROCESS AREA

RADIOACTIVE LIQUID WASTE TREATMENT PLANT REFURBISHMENT

MECHANICAL ONE-LINE
DIAGRAM

Los Alamos Los Alamos National Laboratory
Los Alamos, New Mexico 87545
PROJECT ID NO. 10411-50 ENG-PL 4104

11

HVAC CENTRAL PLANT FLOW DIAGRAM
NOT TO SCALE

PROCESS STEAM & COOLING WATER
NOT TO SCALE

FLOW DIAGRAM

RADIOACTIVE LIQUID WASTE TREATMENT PLANT REFURBISHMENT

MECHANICAL ONE-LINE
DIAGRAMS

12

MAJOR ELECTRICAL EQUIPMENT LOCATION KEY

EQUIPMENT	LOCATION
NEW SUBSTATION	N.W. CORNER OF HVAC CENTRAL PLANT(OUTDOORS)
MAIN SWITCHBOARD "SWB-A"	NORTH END OF HVAC CENTRAL PLANT ELECTRICAL ROOM
STANDBY GENERATOR	EAST SIDE OF MECHANICAL PENTHOUSE ABOVE PROCESS AREA
MCC-A	MECHANICAL PENTHOUSE - SUPPLY AIR SIDE
MCC-B	MECHANICAL PENTHOUSE - SUPPLY AIR SIDE
MCC-C	MECHANICAL PENTHOUSE - EXHAUST SIDE
MCC-D	MECHANICAL PENTHOUSE - EXHAUST SIDE
MCC-E	HVAC CENTRAL PLANT CHILLER ROOM
MCC-F	HVAC CENTRAL PLANT BOILER ROOM
EMCC-A	PROCESS AREA IN BASEMENT

X. SUPPORTING INFORMATION

A. MISSION NEED STATEMENT

Los Alamos

Los Alamos National Laboratory
Los Alamos, New Mexico 87545

DATE: March 18, 1993
IN REPLY REFER TO: ADO/93-245-U
MAIL STOP: A120
TELEPHONE: (505) 667-9390

Joe Vozella
U.S. Department of Energy
Los Alamos Area Office
35th Street, MS A316
Los Alamos, NM 87544

Dear Mr. Vozella:

Please find enclosed the Mission Need Statement (MNS) for the FY96 Line Item, the Radioactive Liquid Waste Treatment Facilities Project. This MNS will be one of the briefing requirements at HQ for Key Decision-0 as outlined in the Siebach to Morton memo dated December 22, 1992.

If you have questions or comments please contact Ross Garcia or Jerry Buchholz at 5-2327.

Sincerely,

Allen J. Tiedman
Associate Director for
Operations

AT/AD:dp

Enc.: a/s

Cy: T. Gunderson, EM-DO, w/enc., MS J591
A. Drypolcher, EM-7, w/enc., MS E517
EM-7/RLWPO File, w/o enc., MS K572
ENG-DO-93-CRLW File, w/o enc., MS E584 (2)

Los Alamos

Los Alamos National Laboratory
Los Alamos, New Mexico 87545

memorandum

TO: Allen Tiedman, ADO, MS A120
THRU: Tom Gunderson, EM-DO, J591
FROM: Anthony Drypolcher, EM-7
DATE: February 16, 1993
MAIL STOP/TELEPHONE: E517/7-7391
SYMBOL: ENG-DO/MPO-93-CRLW-030
SUBJECT: **RADIOACTIVE LIQUID WASTE TREATMENT FACILITIES (RLWTF)**

The "Mission Need Statement" (MNS) has been prepared for the subject project in order to gain DOE/HQ approval (Key Decision 0) to proceed with the Conceptual Design. Approval of the MNS constitutes endorsement of project need, technical objectives, management approach, and authorizes the expenditure of funds for the Conceptual Design phase of the project. The project justification and feasibility have been established and the team is ready to proceed with Conceptual Design.

The existing Radioactive Liquid Waste Treatment Plant at TA-50-1 is 30 years old and was constructed to Uniform Building Codes before many of the requirements for Nuclear Containment. The risk of failure of the existing plant increases with time, putting the DOE and Laboratory missions in jeopardy. It is important that the RLWTF project be maintained as a FY96 Line Item. Even then operation of the new facility would not start until the year 2002. Delays in the project would only add to uncertainties about the reliability of future radioactive and industrial liquid waste management at LANL.

Please transmit the MNS to Joe Vozella if you find it acceptable. If you have questions or comments please contact Ross Garcia or Jerry Buchholz at 5-2327.

AD/JB:dp

Attachment: Mission Need Statement

Cy: Jim Shipley, EE-AETO, w/att., MS F643
Harold Christensen, CM-MPO, w/att., E584
JP. Dave Post, EM-DO, w/att., MS J591
JB. Ross Garcia, ENG-DO/MPO, w/o att., MS K572
Jerry Buchholz, EM-7/RLWPO, w/o att., MS K572
EM-7/RLWPO File, w/att., MS K572
ENG-DO/MPO-93-CRLW File, w/att., MS E584 (2)

March 15, 1993

**RADIOACTIVE
LIQUID WASTE
TREATMENT
FACILITIES
(RLWTF)
PROJECT**

MISSION NEED STATEMENT

**LOS ALAMOS
NATIONAL
LABORATORY**

and

**DOE Office of
ENVIRONMENTAL
RESTORATION
&
WASTE
MANAGEMENT**

CONTENTS

	Page
1.0 PROGRAM MISSION GOAL	1
1.1 Project Need	2
1.2 Alternatives	3
1.2.1 No Action for this Project	3
1.2.2 Refurbish Existing Plant Using Line Item Funds	3
1.2.3 New Facility	3
1.3 Basis for Best Alternative	3
1.3.1 Disadvantages of the No Action Alternative	3
1.3.2 Disadvantages of the Refurbishment Alternative	4
1.3.3 New Facility Advantages	4
1.4 Consequence of Inaction	4
1.5 Appropriateness of Project in View of Current Technology	5
2.0 PROJECT OBJECTIVES	5
2.1 Technical Objectives	5
2.1.1 Specific Technical Objectives	5
2.1.2 Basis for Achieving Technical Objectives	6
2.1.3 Relationship of Technical Objective to Similar Activities	6
2.1.4 Impact on Program of Not Meeting Technical Objectives	6
2.2 Cost Objectives	6
2.2.1 Preconceptual Design Costs to Key Decision (KD) - 0	7
2.2.2 Conceptual Design and Documentation Costs Required for KD-1	7
2.2.3 Environmental, Safety and Health Costs	7
2.2.4 Schedule for Developing Project Baseline Costs	7
2.3 Schedule Objectives	8
2.3.1 Impact on the Program of Not Meeting the Schedule Dates	8
3.0 ORGANIZATION	9
4.0 RISK ASSESSMENT	10
5.0 REFERENCES	10
6.0 APPROVALS	11

March 15, 1993

Los Alamos National Laboratory
US Department of Energy
RLWTF Project - Mission Need Statement

MISSION NEED STATEMENT

1.0 PROGRAM MISSION GOAL

DOE Mission

The mission and statutory responsibility of the DOE is to carry out programs in the support of the nuclear weapons stockpile, energy research and development, basic research, and nuclear materials production. The Waste Management (WM) Program managed by Environmental Management (EM) of the DOE is a major program that supports the DOE's overall mission.

Environmental Management Program Mission

The EM program mission, which supports the DOE mission is stated in the Environmental Restoration/Waste Management (ER/WM) 5-Year Plan; "manage waste operations and environmental restoration activities to achieve full compliance with applicable laws, regulations, and agreements aimed at protecting human health and the environment; make compliance with the letter and spirit of environmental laws, regulations, and requirements an integral function of operating DOE facilities; and reduce the generation of new waste."

Waste Management Goals and Objectives

The WM program mission, which supports the DOE mission above, as described in the ER/WM 5-Year Plan is; "The Waste Management Program's major goal is to manage waste safely until final disposal is implemented by ensuring that the public, workers, and the environment are protected from the hazards associated with the waste materials; minimization of future waste, conducting all activities in accordance with applicable Federal, State, and local regulations; and comply with terms and conditions of all compliance agreements." Additionally, waste management's goal is to provide adequate treatment, storage, and disposal capacity to safely accommodate both currently stored waste and future generated waste.

The LANL Mission - LANL Institutional Plan

"The Los Alamos National Laboratory is dedicated to developing world-class science and technology and applying them to the nation's security and well being. The Laboratory will continue its special role in defense, particularly in nuclear weapons technology, and will increasingly use its multidisciplinary capabilities to solve important civilian problems."

March 15, 1993

Los Alamos National Laboratory
US Department of Energy
RLWTF Project - Mission Need Statement

LANL Mission Assignments - LANL Institutional Plan

The DOE has assigned the Laboratory several specific mission assignments identified in the LANL institutional Plan. One specific mission assignment is "environmental R&D, including storing and managing radioactive waste, handling hazardous waste, and investigating new technologies to address problems associated with waste characterization and cleanup, ozone depletion, clean air, and basic environmental science." Additionally, DOE is assigning to LANL the "Lead Laboratory Role" for maintaining technical competence in five of nine nuclear weapons technologies. LANL is expected to have the lead role for maintaining and developing plutonium processing technologies.

Project Goals

The goal of this project is to develop and execute a comprehensive strategy to manage liquid wastes in support of DOE and LANL missions. The project will provide facilities by 2002 for managing liquid wastes in full compliance with regulations and DOE Orders well into the next century.

1.1 Project Need

While performing mission assignments for DOE, the Laboratory generates radioactive and industrial liquid wastes that must be treated before release to the environment. This treatment must be conducted in an environmentally sound and effective manner that complies with requirements that protect the employee, the public, and the environment.

The existing plant used to treat the radioactive and industrial waste has deficiencies that can be divided into two categories:

- o Clean Water Act (CWA) requirements that could result in civil or criminal penalties.

Effluent quality does not meet parameters certified by the New Mexico Environment Department in the proposed National Pollutant Discharge Elimination System (NPDES) permit. Another is the inability to monitor for unpermitted discharges from the many direct buried pipes and tanks in the existing plant.

o **DOE Order requirements.**

Substantial problems have been identified at the existing plant pertaining to worker and public safety, nuclear containment, and environmental protection. Concentrations of radionuclides in the effluent from the existing plant exceed the guidelines in DOE Order 5400.5. Open tanks, windows, lack of containment, and improperly filtered air do not comply with acceptable nuclear facility design criteria in DOE Order 6430.1A.

If these deficiencies are not corrected, they could result in interruption of radioactive and industrial liquid waste treatment and failure to meet LANL mission assignments.

1.2 Alternatives

1.2.1 No Action for this Project

Use operating, General Plant Project (GPP) and capital equipment funds to correct deficiencies in the existing plant. Depend on waste minimization efforts to reduce contaminants and nuclear safety source terms to acceptable risks.

1.2.2 Refurbish Existing Plant Using Line Item Funds

Determine the appropriate deficiencies to be fixed in the existing plant by performing risk and cost to benefit analysis during Conceptual Design. Use waste minimization to reduce the liquid waste streams where practical.

1.2.3 New Facility

Use Line Item funding to construct new facilities, start new operations, and to decontaminate and decommission the existing plant.

1.3 Basis for Best Alternative

1.3.1 Disadvantages of the No Action Alternative

Compliance with the CWA and nuclear facility safety requirements is unlikely using GPP funds. GPP projects are limited to \$1.2M each and legally cannot be "stacked" to accomplish a construction goal. It is not technically and economically feasible to use waste minimization to achieve safe levels of influent contaminants for the existing plant; DOE/LANL missions would be disrupted if this alternative is chosen.

1.3.2 Disadvantages of the Refurbishment Alternative

The extent of contamination due to leaking tanks and pipes at the existing facility is unknown. The environmental remediation required before and during construction, makes firm estimates of cost and schedules difficult. Planning estimates indicate greater cost and extended schedules. Refurbishment of the existing plant would pose a high risk of interrupted liquid treatment service to waste generators. The lack of available space limits future expansion at the existing site.

1.3.3 New Facility Advantages

A new facility at a new site provides the best prospect for meeting the goals of the project and fully supporting the DOE and LANL missions.

1.4 Consequence of Inaction

The continued success of DOE/LANL missions cannot be ensured with the existing facilities. If the existing plant is shut down for not meeting the margin of safety demanded by federal or state authorities, or for not meeting effluent regulations, key DOE/LANL programs will be disrupted for an unknown period of time; possibly permanently. Examples of missions that could be disrupted:

- o Research design, development, engineering, and testing of nuclear warheads for the nation's stockpile; maintenance and enhancement of the technology base that is the foundation of the weapons program; and maintenance of the Laboratory's capabilities for nuclear tests and the execution of such tests;
- o Basic research in defense and energy related disciplines, including atomic and molecular physics, bioscience, chemistry, computational science and applied mathematics, geoscience, space science, astrophysics, materials science, nuclear and particle physics fluids, particle beams, and applied science and engineering.
- o Nuclear materials R&D directly related to the nuclear weapons program, and fabrication development and transfer of technology to the DOE production complex, and plutonium recovery from scrap generated by the DOE complex.
- o R&D on inertial confinement fusion, including fusion target physics, laser-target interaction experiments, target design and fabrication, and high energy laser development.

1.5 Appropriateness of Project in View of Current Technology

Maintenance costs for the 30-year old plant are high; its reliability is low; available processes do not produce an effluent that meets existing regulations; and the work environment in the 30-year old facility does not meet requirements of DOE Orders. The technology for treating Radioactive Liquid Waste (RLW) to levels acceptable to the DOE and the EPA while protecting the environment, public, and workers is available, has been demonstrated at other DOE sites, and will be applied and/or improved as appropriate during this project.

2.0 PROJECT OBJECTIVES

2.1 Technical Objectives

The technical objectives for the Radioactive Liquid Waste Treatment Facilities (RLWTF) project are to design and construct facilities that will:

- o Ensure that LANL's future treatment of radioactive and industrial liquid waste is environmentally sound and effective and complies with environmental laws and regulations that protect the employee, public health, and the environment;
- o Have an effective design lifetime of 30-40 years;
- o Have the flexibility to meet future radioactive or industrial liquid waste generator's needs; and
- o Protect the employees and the public from excessive radiation exposure and meet the true spirit of "as low as reasonably achievable" (ALARA).

2.1.1 Specific Technical Objectives

- o Effluent will meet the requirements of DOE Order 5400.5 and the proposed CWA/NPDES permit.
- o The facilities will meet the design and construction requirements of DOE Order 6430.1A, anticipated draft orders on non-reactor nuclear facilities, and appropriate codes and standards.
- o Requirements of the Resource Conservation and Recovery Act and the National Emission Standards for Hazardous Air Pollutants act will be met.

2.1.2 Basis for Achieving Technical Objectives

- A best demonstrated available technology (BDAT) study is being performed for radioactive liquid waste treatment at LANL by the Ralph M. Parsons/C. T. Main.
- Use demonstrated, commercially available process equipment that is certified by the Ralph M. Parsons/C. T. Main to benchmark BDAT.
- Benchmark process technology that has been demonstrated at other DOE sites such as Savannah River. Incorporate technology that improves on benchmark where practicable.

2.1.3 Relationship of Technical Objectives to Similar Activities

The Savannah River Plant has operated successfully since 1988. The Rocky Flats Plant has operated since 1979. Hanford is using a design similar to that in the proposed action.

2.1.4 Impact on Program of Not Meeting Technical Objectives

Fines could be levied on DOE and Laboratory management. Critical DOE/LANL programs could be abruptly terminated if technical objectives are not met. Programs impacted would include nuclear energy, environmental restoration & waste management, defense, energy, civilian radioactive waste management, arms control & nonproliferation, reimbursable programs, and industrial applications and technology transfer.

2.2 Cost Objectives

During the preparation of the Conceptual Design Authorization Request¹ (CDAR), a planning estimate for this project was made. Although not adequate for a baseline, the total estimated construction cost is between \$135M and \$150M, corresponding to a total project cost between \$160M and \$175M. These indicate that this project will be a Major System Acquisition (MSA).

March 15, 1993

Los Alamos National Laboratory
US Department of Energy
RLWTF Project - Mission Need Statement

2.2.1 Preconceptual Design Costs Preceding Key Decision (KD) - 0

Approximately \$2.0M

2.2.2 Conceptual Design and Documentation Costs Required for KD-1

Approximately \$5.0M

2.2.3 Environmental, Safety and Health Costs

Environmental Impact Statement (EIS)	\$3.0M
Preliminary Safety Analysis Report (PSAR)	\$600K
Final Safety Analysis Report (FSAR)	\$500K

2.2.4 Schedule for Developing Project Baseline Costs

The Conceptual Design Plan (CDP) provides a detailed schedule. Conceptual Design is currently scheduled to begin in April 1993. Milestones are as follows:

CD begins	05/93
30% CD meeting	06/93
60% CD meeting	09/93
100% CD meeting	12/93

Preliminary project baseline costs will be available in the 09/93-12/93 time frame. Final baseline costs will be in the Conceptual Design Report (CDR) scheduled for final submission in 04/94.

March 15, 1993

Los Alamos National Laboratory
US Department of Energy
RLWTF Project - Mission Need Statement

2.3 Schedule Objectives

The activities described in Table I and Table II are scheduled to maintain this project as a FY96 Line Item. The planning schedule objectives are shown in Table I. The corresponding schedule for the ES&H documentation efforts are shown in Table II.

SCHEDULE OBJECTIVE TO KD-1	
TASK NAME	DATE
CDAR Preparation	03/92
Mission Need Preparation	03/93
DOE-AL KD-0 Concurrence	04/93
DOE-HQ KD-0	05/93
Start Conceptual Design	05/93
30% CD Meeting	06/93
60% CD Meeting	10/93
90% CD Meeting	12/93
100% CD Meeting	01/94
Final CDR Submittal to HQ	04/94
KD-1	06/94

Table I. Pre-Title I Schedule Objectives.

ENVIRONMENT SAFETY AND HEALTH (ES & H) SCHEDULE OBJECTIVES	
TASK NAME	SCHEDULED FINISH
DOE Environmental Checklist	06/92
EIS	04/96
PSAR	04/94

Table II. ES&H Schedule Objectives.

2.3.1 Impact on the Program of Not Meeting the Schedule Dates

If the project start continues to slip, increased overall costs and risk of program mission failure will result. Planning must continue. Conceptual Design must bound the problem and define the appropriate solution.

March 15, 1993

Los Alamos National Laboratory
US Department of Energy
RLWTF Project - Mission Need Statement

3.0 ORGANIZATION

The preliminary plan for organizational involvement from DOE/HQ to the RLWTF project office is shown in Fig. 1.

The RLWTF Project organization is shown in Fig. 2. DOE Order 4700.1A, Project Management System, will be followed for this project. Laboratory personnel will be assigned to support the project organizational structure presented in Figures 1 and 2.

Figure 1. Organizational Relationships between the RLWTF Project Office and DOE.

March 15, 1993

Los Alamos National Laboratory
US Department of Energy
RLWTF Project - Mission Need Statement

Figure 2. RLWTF Project Organization (KD-0 - KD-1).

4.0 RISK ASSESSMENT

The alternatives identified above will be evaluated during the Conceptual Design (CD) and the most appropriate will be validated. Demonstrated engineering and construction practices will be followed and the best available technologies will be used. This will ensure that the project will be accomplished within the proposed budget and schedule and fully achieve its mission. The requirements from current and anticipated DOE Orders and other appropriate regulations will be followed. A preliminary draft PSAR will be prepared during the CD development, and a Draft PSAR will be prepared during Title I. The final PSAR will be developed during Title II design. The Final Safety Analysis Report will be prepared and presented for DOE approval before the facility becomes operational.

5.0 REFERENCES

- 1) FY96 Conceptual Design Authorization Request for Radioactive Liquid Waste Treatment Facilities, "RLWTF Project," LANL Project Identification Number (PI) 10411, Los Alamos National Laboratory (June 1992).

March 15, 1993

Los Alamos National Laboratory
US Department of Energy
RLWTF Project - Mission Need Statement

6.0 APPROVALS

JUSTIFICATION OF MISSION NEED APPROVAL SIGNATURE SHEET MAJOR SYSTEM ACQUISITION

SUBMITTED BY:

EM-32 Program Manager

Date

You are hereby authorized to begin or continue activities as stated herein. Approval of this Justification of Mission Need will constitute endorsement of the stated project needs, technical objectives, and management approach. It will not constitute approval of project costs, schedules, or technical baselines and does not give approval of procurement actions or funding commitments beyond those authorized.

APPROVED:

S-3, Under Secretary, Acquisition Executive

Date

Note: AE approval may be provided in an ESAAB Key Decision Memorandum.

B. COMPARISON MATRIX

COMPARISON MATRIX RLWTF PROJECT		
	Line Item New Facility (TA-63)	Line Item Refurbish (TA-50)
Scope	Scope can be well defined. Probability of meeting cost and schedule is high.	Many unknowns, which may lead to high costs and severe schedule impacts. Will still have many "old-facility" problems. Will have severe design constraints.
Cost	Planning Cost Estimate: \$150M TEC. Minimum risk with maximum control.	Planning Cost Estimate: \$175M (TEC). Based on the same construction requirements (6430.1A) as the new facility, the cost is high and the risk is high.
Schedules	Easy to minimize risk. All construction is at a clean site and schedules will not be impacted by ongoing operations or stringent worker and environmental government regulations.	High risk due to unknowns, schedule conflicts with operations personnel, and coordination problems with operations. The schedule is much longer because of these impacts.
Impact on Existing Operations	Minimal, the only impact on the existing operation will be when the pipeline is extended through TA-50 to the new site and when the waste stream is diverted to the new facility.	Severe impact with high risk. Existing operations will be frequently interrupted while construction proceeds.
Site Size	Approximately 9.2 acres TA-63 is presently an undeveloped site. Controlled development of the site is planned to fully optimize use of the area. The area is large enough to accommodate all proposed traffic and parking into the foreseeable future. Several sites were identified and evaluated. The TA-63 site received the highest ranking based on the siting criteria matrix. The facility will be adjacent to other waste management operations.	TA-50 is a fully developed site with very limited area to develop for expansion. If something is added, then something must be removed.

COMPARISON MATRIX RLWTF PROJECT		
	Line Item New Facility (TA-63)	Line Item Refurbish (TA-50)
Facility Size	The facility size is not constrained by the availability of developable space at TA-63. Planning estimates show a need for about 100,000 ft ² of floor space to house tanks, equipment, and personnel at the new facility.	Additional buildings to house additional tanks, equipment, and personnel are severely constrained by the availability of developable space. The approximately 47,500 ft ² of space in the present facility is fully utilized.
Pretreatment Facility	The primary site for the pretreatment facility is at TA-50. The alternate site is at TA-63 with the second alternate north of TA-50. If either alternate site was utilized, the lines between TA-50 and the chosen location would be needed.	See TA-63 comments.
Radioactive Pipeline Extensions	Pipelines will need to be extended from TA-50 to TA-63 a distance of approximately 2240 feet. A new pipeline, about 2700 feet, is required to carry treated effluent from TA-63 to the NPDES Outfall 051 for discharge to the environment.	Several feet of underground pipe inside the building and between buildings will need to be replaced to meet double containment and monitoring requirements.
Access and Parking	Emergency egress, traffic flow, and sufficient parking are all included in the site development plan.	Parking is presently a severe problem at TA-50. This problem will only grow as space is sacrificed for storing equipment during construction and for new construction. The proposed building expansion eliminates on-site parking.

COMPARISON MATRIX RLWTF PROJECT		
	Line Item New Facility (TA-63)	Line Item Refurbish (TA-50)
Site Utilization	The new facility will be adjacent to other planned waste management facilities. Long-range plans for TA-63 will allow for optimum utilization of the available space.	The TA-50 site is presently shared between the Radioactive Liquid Waste Treatment Plant, the Size Reduction Facility, the Controlled Air Incineration Facility, the Group Office functions, and the various support functions. The utilization of available space is greater than 100%.
Future Expansion	The 9.2 acre site allows for future expansion.	The available area at TA-50 will severely limit future expansion. Parking areas will be sacrificed for new construction during the refurbishment.
Utilities	All utilities exist either on or adjacent to the site.	All utilities exist on the site. If capacities need to be increased, additional costs may be incurred.
Ease of Construction	Construction schedule and cost scenarios will follow normal practices.	Supplied air, respirators, special clothing, special entry procedures, and special training will be required for much of the work. Schedule and cost is at high risk.
Environmental Permitting	The project will require an Environmental Impact Statement.	Special permitting may be required if past operations have contaminated the environment. Special permitting and sampling/remediation plans will need to be written and approved. This could severely impact costs and schedules.
Environmental Hazards	A storm-water run-off containment system that will be designed and constructed for the Hazardous Waste Management Facilities will be utilized at TA-63.	No provisions have been considered for containing storm water run-off from the TA-50 area.

COMPARISON MATRIX RLWTF PROJECT		
	Line Item New Facility (TA-63)	Line Item Refurbish (TA-50)
Public Hazards	A 100' setback is provided. Pajarito road is south and west of the site.	A 100' setback is provided. Pajarito road is south of the existing facility.
Employee Hazards	Employees will not be endangered during construction.	Construction personnel and site operations personnel will be sharing change rooms and areas within the building where construction is taking place. This will cause a significant contamination risk to the operations personnel.
SWMU's	TA-63 is an undeveloped site and contains no identified SWMU's. It avoids SWMU's.	TA-50 contains 10 SWMU's with 26 subunits in the 10 SWMU's. They have not been characterized. Their impact on construction in the area cannot be determined.
Safety and Health	New construction at a clean site has minimum health and safety problems.	Significant construction hazards will be presented during work with an old highly contaminated facility. The risk of worker contamination is high. Phased construction will cause SAR and ORR problems.
Seismic	TA-63 has been fully certified by Woodward-Clyde Federal Services to meet the seismic requirements of 40 CFR 270.14	Since TA-50 is located near the Guaje Mountain fault, extensive Paleoseismic trenching analysis would need to be performed before the site could be certified to meet the requirements of 40 CFR 270.14. Considerable structural bracing of the existing facility is needed to meet seismic criteria. Some structures may require demolition.

C. TABLE B

TABLE B

Removal Ratios Required (Average)

mg/l

Constituent	Influent Quality mg/l	Effluent Spec. mg/l	Required Removal Ratio
Arsenic	.003	.074	-23.7*
Barium	<0.5	---	---
Cadmium	.010	.0005	.95
Calcium	40	---	---
Chloride	500	---	---
Chromium	0.25	.00023	.9991
Copper	0.30	.0002	.9993
Cyanide	0.60	.008	.987
Fluoride	8	---	---
Iron	1.0	---	---
Lead	.01	.0045	.550
Magnesium	4	---	---
Mercury	.005	.00003	.994
Nickel	1.0	.0131	.987
Ammonia (N)	10.0	0.1	.990
Nitrate (N)	1.0	---	---
Nitrate (N)	980.0	10	.990
Phosphate	4.0	---	---
Potassium	240	---	---
Selenium	1.0	.0086	.991
Silica	50	---	---
Silver	.005	.0001	.980
Sodium	1508	---	---
Sulfate	25.0	---	---
Zinc	.002	.0036	-0.8
COD	51	125	-1.45
TDS	6200	---	---
TSS	145	---	---
Beryllium	---	.052	X
Aluminum	---	5.0	X
Boron	---	0.075	X
Cobalt	---	0.05	X
Vanadium	0.06	0.05	.167

TABLE B - continued

Constituents	Influent Quality nano ci/l	Effluent Spec. nano ci/l	Required Removal Ratio
Tritium	---	.02	X
Radium (226422)	---	30 pci/L	X
Plutonium (239)	100	20 pci/L	.9998
Americium (241)	20	20 pci/L	.9990
Cesium (137)	11	1.0	-90.0
Strontium (90)	3.4	500 pci	.853
Cobalt (60)	0.8	3.0	.625
Sodium (22)	0.96	6.0	-5.25
Strontium (85)	0.75	7.0	-93,000
Niobium (95)	0.9	30	-33,000
Yttrium (88)	13	10	-768
Zirconium (88)	6.0	50	-4,000
pH	7.3	6-9	---

* - A negative number indicates the waste influent already meets discharge specifications.

** - An X indicates no discharge specification available.

D. EXHIBIT C

EXHIBIT C
EFFLUENT HOLDING TANK SEQUENCE

KEY

0 = Empty
1 = 1/2 Full
2 = Full

S = Sample to Lab
QN = Quarantine (Day N)

<u>Tank</u>	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>
End of Day						
0	0	-	-	-	-	-
1	1	-	-	-	-	-
2	2S	-	-	-	-	-
3	2Q1	1	-	-	-	-
4	2Q2	2S	-	-	-	-
5	2Q3	2Q1	1	-	-	-
6	2Q4	2Q2	2S	-	-	-
7	2Q5	2Q3	2Q1	1	-	-
8	2Q6	2Q4	2Q2	2S	-	-
9	2Q7	2Q5	2Q3	2Q1	1	-
10	2Q8	2Q6	2Q4	2Q2	2S	-
11	2Q9	2Q7	2Q5	2Q3	2Q1	1
12	0	2Q8	2Q5	2Q4	2Q2	2S
13	1	2Q9	2Q7	2Q5	2Q3	2Q1
14	2S	0	2Q8	1Q6	2Q4	2Q2
15	2Q1	1	2Q9	2Q7	2Q5	2Q2
16	2Q2	2S	0	2Q8	2Q6	2Q4
17	2Q3	2Q1	1	2Q9	2Q7	2Q5
18	2Q4	2Q2	2S	0	2Q8	2Q6

E. CALCULATIONS

ICF KAISER ENGINEERS

750 Samson Drive
32 Alamos New Mexico 87544

DESIGN CALCULATION INDEX

JOB NUMBER 10411-50

AREA OR BUILDING

CALCULATION DESCRIPTION

RLW PLANT REFURBISHMENT TA-50

MECHANICAL

1 OF 1

DISCIPLINE

MECH

CALCULATIONS APPLY TO DRAWINGS AND REVISIONS SHOWN

DRAWING	REV	DRAWING	REV	DRAWING	REV	DRAWING	REV
DESIGN ENGINEER <u>Chris Puerto</u> 3/16/93 (SIGNATURE) (DATE)				JOB ENGINEER _____ (SIGNATURE) (DATE)			
CALCULATIONS CHECKED <u>Theresa Pluta</u> 5/16/93 (SIGNATURE) (DATE)				DESIGN SUPERVISOR _____ (SIGNATURE) (DATE)			
CALCULATIONS AGREE WITH DESIGN CRITERIA (SIGNATURE) (DATE)				CALCULATIONS AGREE WITH APPVD. VENDOR DWGS. (SIGNATURE) (DATE)			
CALCULATION KEYS		DATES		DATES		DATES	
REVISION DESCRIPTION							
DESIGN ENGINEER							
DESIGN SUPERVISOR							
STATUS		PRELIMINARY		FINAL		CHECKED	
REASON FOR VOID OR HOLD							

INDEX

SHEET NO.

DESCRIPTION

1 THRU 3	ZONE & SYSTEM LAYOUT
4 THRU 16	U-VALUE CALCULATIONS
17 THRU 28	HEAT GAIN HEAT LOSS CALCULATIONS
29 THRU 45	SYSTEM EQUIPMENT SELECTION AND SIZES.
46 THRU 52	SYSTEM STATIC PRESSURE CALCULATIONS
53 THRU 56	TYPICAL SYSTEM UNIT SIZES.
57 THRU 59	CHILLER SELECTIONS
60 THRU 65	COOLING TOWER SELECTIONS
66 THRU 69	BOILER SELECTIONS
70	HEAT EXCHANGER
71, 72	CENTRAL PLANT VENTILATION; UNIT HEATER SELECTION
73, 74	COLD WAREHOUSE " " " "
75	COMPUTER ROOM A/C UNIT
76	STACK DESIGN
77 THRU 84	MAIN LINE SIZING
85 THRU 89	PROCESS STEAM HEAT EXCHANGER.

MECHANICAL ROOM

NOT TO SCALE

PROCESS
AREA
ROOM 13
ZONE 13
SYSTEM 2
AREA 2,906 SQFT
53.91 X 53.91
VENTILATION 6 AC/HR
COOLING 72°F
HEATING 68°F

- NOTE: 1. ASSUMED 3 WATTS/SQFT
LIGHTING LOAD AND 2
WATTS/SQFT MISC LOAD
FOR ALL ZONES.
2. 1 OF PEOPLE WAS DETERMINED BY
OF OFFICES.
PEOPLE SEATED AT REST 255 BTUH SENSIBLE
255 BTUH LATENT.
3. ROOM TEMPERATURES REQUESTED BY USER.

COMPUTER & CONTROL ROOM
ROOM 18
ZONE 18
SYSTEM 8
AREA 1,310 SQFT
36.19 X 36.19
VENTILATION 6 AC/HR
COOLING 72°F
HEATING 68°F
PEOPLE 2

TECHNICAL SUPPORT
ROOM 12
ZONE 12
SYSTEM 1
AREA 9,137 SQFT
95.59 X 95.59
VENTILATION 15% O.A.
COOLING 75°F
HEATING 72°F
PEOPLE 12

LOBBY/ENTRY
ROOM 11
ZONE 11
SYSTEM 1
AREA 1,379 SQFT
37.13 X 37.13
VENTILATION 15 O.A.
COOLING 72°F
HEATING 68°F

CHANGE ROOM
ROOM 10
ZONE 10
SYSTEM 9
AREA 3,186 SQFT
56.44 X 56.44
VENTILATION 6 AC/HR
COOLING 72°F
HEATING 68°F

GLASS 3/16"X2 W/ 1/2"
AIR SPACE 256 SQFT

SOIL LAB
ROOM 9
ZONE 9
SYSTEM 9
AREA 800 SQFT
28.28 X 28.28
VENTILATION 15% O.A.
COOLING 72°F
HEATING 72°F

CHEM. LAB
ROOM 8
ZONE 8
SYSTEM 9
AREA 4,450 SQFT
66.71 X 66.71
VENTILATION 3 AC/HR
COOLING 72°F
HEATING 68°F

GLASS 3/16"X2 W/ 1/2"
AIR SPACE 320 SQFT

HVAC CENTRAL PLANT
ROOM 16
ZONE 16
SYSTEM 6
AREA 7,632 SQFT
53 X 144
VENTILATION 15% O.A.
COOLING 78°F
HEATING 68°F

FIRST FLOOR

NOT TO SCALE

"U" VALUE CALCULATIONS

4 of 89

JOB NAME: RLW REFURBISHMENT STUDY

JOB# 88180-173

BUILDING: BLDG 1 TA-50

SHEET 1 OF 1

DESIGNED: CLQ DATE: 10-Feb-93

CHECKED: DATE:

NEW ROOF

	R VALUE	
OUTSIDE AIR FILM	0.17	
SINGLE PLY ROOF (ARCH GRAPHIC STANDARDS 8TH EDITION PAGE 748)	0.50	
3.5" RIGID INSULATION (SWEETS 07220)	26.30	
3" LIGHT WT CONCRETE (ARCH GRAPHIC STANDARDS 8TH EDITION (PAGE 748 (0.86/INCH X 3 INCHES)	2.58	
INSIDE AIR FILM	0.61	
	<hr/>	
	2	
R TOTAL	30.16 hft	deg F/btu U=1/R TOTAL
		U= 0.0332

PROCESS AREA & MECH ROOM WALLS

OUTSIDE AIR FILM	0.17	
3" PORCELIN PANEL (SWEETS 07410 U-VAL = .067 R = 1/U-VAL =)	14.90	
INSIDE AIR FILM	0.68	
	<hr/>	
	2	
R TOTAL	15.75 hft	deg F/btu U=1/R TOTAL
		U= 0.0635

ENTRY AND CHANGE ROOM WALLS

OUTSIDE AIR FILM	0.17	
2" EIFS (SWEETS 07240)	8.7	
5/8" GYPBOARD (ASHRAE 1985 FUNDAMENTALS TABLE 3A pg. 23.6)	0.56	
6" BATT INSUL (ARCH GRAPHICS STANDARDS 8TH EDITION P.748)	19	
5/8" GYPBOARD (ASHRAE 1985 FUNDAMENTALS TABLE 3A pg. 23.6)	0.56	
INSIDE AIR FILM	0.68	
	<hr/>	
	2	
R TOTAL	29.67 hft	deg F/btu U=1/R TOTAL
		U= 0.0337

EXISTING WALLS

OUTSIDE AIR FILM	0.17	
8" CMU (ARCH GRAPHICS STANDARDS 8TH EDITION P.748)	2.18	
INSIDE AIR FILM	0.68	
	<hr/>	
	2	
R TOTAL	3.03 hft	deg F/btu U=1/R TOTAL
		U= 0.330

PERIMETER INSULATION 2" THICK (SWEETS 07200) R-VAL = 10 U = 1/R-VAL

----- U= 0.100 -----

GLASS 3/16" THICK DOUBLE GLAZE 1/2" AIR SPACE (ASHRAE 1985 FUNDAMENTALS TABLE 33)

----- U= 0.450 -----

SHADING COEFFICIENTS INSULATING GLASS (ASHRAE 1985 FUNDAMENTALS TABLE 29)

----- 0.880 -----

THERMAL VALUES OF MATERIALS

MATERIAL & DESCRIPTION	DENSITY (lb per cu ft)	RESISTANCE (R) ^a	
		Per inch thickness (1/k)	For thickness listed (1/C)
BUILDING BOARDS, PANELS, FLOORING, ETC.			
Gypsum or plaster board 3/8 in.	50	—	0.32
Gypsum or plaster board 1/2 in.	50	—	0.45
Plywood 3/4 in.	34	0.04	—
Sheathing, fiberboard 1/2 in.	18	—	1.32
25/32 in.	18	—	2.06
	22	2.44	—
	25	2.28	—
Wood fiberboard, lam or homogeneous	30	2.00	—
	50	1.37	—
Particleboard 3/8 in.	40	—	0.82
Wood subfloor 3/4 in.	—	—	0.44
BUILDING PAPER			
Vapor-permeable felt	—	—	0.06
Vapor-seal, 2 layers of mopped 15 lb felt	—	—	0.12
Vapor-seal, plastic film	—	—	Negl.
FINISH FLOORING MATERIALS			
Carpet and fibrous pad	—	—	2.08
Carpet and rubber pad	—	—	1.23
Hardwood 25/32 in.	—	—	0.71
Terrazzo 1 in.	—	—	0.08
Tile-asphalt, linoleum, vinyl, rubber	—	—	0.05
INSULATING MATERIALS			
Blanket and Batt ^b			
Mineral wool, fibrous form processed from rock, slag, or glass			
1-3 in.		4.16	—
3-4 in.	0.3-2.0	—	11.0
5 1/2-8 1/2 in.		—	19.0
9-10 in.		—	30.0
Wood fiber			
Boards and slabs			
Cellular glass	8.5	2.86	—
Glass fiber	4-9	4.00	—
Expanded rubber (rigid)	4.5	4.55	—
Expanded polyurethane (R-11 blown) (Thickness 1 in. & greater)	1.5	6.25	—
Expanded polystyrene, extruded			
Cut cell surface	1.8	4.00	—
Smooth skin surface	1.8-3.5	5.00	—
Expanded polystyrene, molded beads	1.0	3.85	—
Mineral fiber with resin binder	15	3.45	—
Mineral fiberboard, wet felted			
Core or roof insulation	16-17	2.94	—
Acoustical tile	18	2.86	—
Acoustical tile	21	2.70	—
Mineral fiberboard, wet molded			
Acoustical tile ^c	23	2.38	—
Wood or cane fiberboard			
Acoustical tile ^c 1/2 in.	—	—	1.19
Acoustical tile ^c 3/4 in.	—	—	1.78
Interior finish (plank, tile)	15	2.86	—
Cement fiber slabs (shredded with portland cement boards)	25.0-27.0	2.00	—
Loose Fill			
Mineral fiber			
(glass, slag, or rock)			
5 in.	0.6-2.0	—	11.00
6 1/2-8 3/4 in.	0.6-2.0	—	19.00
10 1/4-13 3/4 in.	0.6-2.0	—	30.00
Vermiculite (exfoliated)			
	4.0-6.0	2.27	—
	7.0-8.2	2.13	—
Perlite (expanded)			
	2.0-4.1	3.50	—
	4.1-7.4	3.00	—
	7.4-11.0	2.60	—
Wood fiber, softwoods	2.0-3.5	3.33	—
MASONRY MATERIALS—CONCRETES			
Cement mortar	116	0.20	—
Gypsum-fiber concrete,			
87 1/2% gypsum, 12 1/2% wood chips	51	0.60	—
Lightweight aggregates including	120	0.19	—
expanded shale, clay or slate;	100	0.28	—
expanded slags; cinders; pumice;	80	0.40	—
perlite; vermiculite; also	60	0.59	—
cellular concretes	40	0.86	—
	30	1.11	—
	20	1.43	—
Sand & gravel or stone aggregate (oven dried)	140	0.11	—
Sand & gravel or stone aggregate (not dried)	140	0.08	—
Stucco	116	0.20	—

THERMAL VALUES OF MATERIALS

5 of 89

MATERIAL & DESCRIPTION	DENSITY (lb per cu ft)	RESISTANCE	
		Per inch thickness (1/k)	For thickness listed (1/C)
MASONRY UNITS			
Brick, common ^d	120	0.20	—
Brick, face ^e	130	0.11	—
Clay tile, hollow:	—	—	—
1 cell deep	3 in.	—	—
1 cell deep	4 in.	—	—
2 cells deep	6 in.	—	—
2 cells deep	8 in.	—	—
Concrete blocks, three oval core:	—	—	—
Sand & gravel aggregate	4 in.	—	—
	8 in.	—	—
	12 in.	—	—
Cinder aggregate	3 in.	—	—
	4 in.	—	—
	8 in.	—	—
	12 in.	—	—
Lightweight aggregate	3 in.	—	—
(expanded shale, clay, slate	4 in.	—	—
or slag; pumice)	8 in.	—	—
	12 in.	—	—
Concrete blocks, rectangular core:	—	—	—
Sand & gravel aggregate	—	—	—
2 core, 8 in. 36 lb.	—	—	—
Lightweight aggregate (expanded	—	—	—
shale, clay, slate or slag; pumice)	—	—	—
3 core, 6 in. 19 lb.	—	—	—
→ 2 core, 8 in. 24 lb.	—	—	—
3 core, 12 in. 38 lb.	—	—	—
Granite, marble	150-175	0.05	—
Stone, lime or sand	—	0.08	—
METALS			
Aluminum	171	0.0007	—
Brass, red	524-542	0.0010	—
Brass, yellow	524-542	0.0012	—
Copper, cast rolled	550-555	0.0004	—
Iron, gray cast	438-445	0.0030	—
Iron, pure	474-493	0.0023	—
Lead	704	0.0041	—
Steel, cold drawn	490	0.0032	—
Steel,	—	—	—
stainless, type 304	—	0.0055	—
Zinc, cast	—	0.0013	—
PLASTERING MATERIALS			
Cement plaster,	—	—	—
sand aggregate	116	0.20	—
Sand aggregate	1/2 in.	—	—
Sand aggregate	3/4 in.	—	—
Gypsum plaster:	—	—	—
Lightweight aggregate	1/2 in.	45	—
Lightweight aggregate	3/4 in.	45	—
Lightweight aggregate,	—	—	—
on metal lath	3/4 in.	—	—
Perlite aggregate	45	0.67	—
Sand aggregate	105	0.18	—
Sand aggregate	1/2 in.	105	—
Sand aggregate	3/4 in.	105	—
Sand aggregate,	—	—	—
on metal lath	3/4 in.	—	—
Vermiculite aggregate	45	0.59	—
ROOFING			
1-ply membrane	0.048 in.	83	—
Asphalt roll roofing	—	70	—
Asphalt shingles	—	70	—
Built-up roofing	3/8 in.	70	—
Slate	1/2 in.	—	—
SIDING MATERIALS			
(On Flat Surface)			
Shingles:	—	—	—
Wood, 16 in., 7 1/2 in. exposure	—	—	—
Wood, double, 16 in.,	—	—	—
12 in. exposure	—	—	—
Wood, plus insul. backer board, 1/2 in.	—	—	—
Siding:	—	—	—
Aluminum (hollow backed	—	—	—
over sheathing)	—	—	—
Vinyl (hollow backed	—	—	—
over sheathing)	0.04 in.	—	—
Cedar shakes	1/2 in.	—	—
	3/4 in.	—	—
Wood, drop, 1 x 8 in.	—	—	—
Wood, bevel, 1/2 x 8 in., lapped	—	—	—
Wood, bevel, 3/4 x 10 in., lapped	—	—	—
Architectural glass	—	—	—

MULTI-MAX® II

Roof Insulation for Fully Adhered Single Ply Systems

6 OF 89
07220/RMA
BuyLine 4892

Product Description and Uses.

Rmax Multi-Max II is a highly efficient thermal insulation board composed of a rigid closed cell polyisocyanurate foam core bonded to nonasphaltic coated glass fiber facers. Multi-Max II is designed to be used as an insulation material for a variety of single ply membrane systems. Multi-Max II is suitable for new roof constructions over non-combustible and steel decks and for most reroof applications.

Compliances.

FEDERAL SPECIFICATION — HH-1-1972/GEN

FACTORY MUTUAL — FM Class I Approval for fully adhered single ply systems subject to the conditions of FM Reports J.I. 1J2A8 AM and J.I. 1M1A5AM. Meets FM Standard 4450. See the current FM Approval Guide.

UNDERWRITERS LABORATORIES — UL Class A component of Class A single ply systems.

Advantages.

Rmax Multi-Max II with the nonasphaltic coated glass fiber facers is suitable for use under all types of single ply membranes. PVC, EPDM, CPE, or Hypalon, mechanically attached, loose laid ballasted, and especially the fully adhered single ply systems. Multi-Max II does not require an overlayment prior to applying the fully adhered system. Refer to Rmax "General Notes," form TR-0101A on the use of and specific installation requirements for Multi-Max II.

Fully Adhered Single Ply Systems.

Attach the Multi-Max II to the roof deck with FM approved mechanical fasteners using one (1) fastener every two (2) square feet of insulation board for both I-60 and I-90 wind uplift ratings. Refer to Factory Mutual "Loss Prevention Code" sheet 1-28" for special considerations at perimeters and corners of roof. Apply the fully adhered single ply membrane according to the membrane supplier's specifications.

Mechanically Attached Single Ply Systems.

Attach the Multi-Max II to the roof deck with a minimum of four (4) FM approved mechanical fasteners per four foot by eight foot (4' x 8') sheet of insulation. Additional fasteners in the insulation may be required by the membrane supplier. Apply the mechanically attached membrane according to the membrane supplier's specifications.

Loose Laid Ballasted Single Ply Systems.

Multi-Max II is in position on the roof deck without fastening or otherwise securing the insulation. The membrane and ballast are then installed according to the membrane supplier's specifications. Ballast, placed at the specified rate, restrains the entire roof system.

Standard Sizes and Packaging.

- WIDTH: 48" • LENGTH: 48" OR 96"
- THICKNESSES: Refer to Thermal Properties Data below

Bundles, approximately 48" high, are banded and covered in plastic bags for easy handling. NOTE: All Rmax products must be tarped, placed on skids, and kept completely dry before and throughout construction.

Typical Physical Properties:

Property	Test Method	Typical Results
Compressive Strength	ASTM D 1621	Greater than 16 psi
Moisture Vapor Transmission	ASTM E 96	Less than 1 perm
Density, Overall	ASTM D 1622	2.0 lbs / cu ft (nominal)
Flame Spread, Core	ASTM E 84	25 or less
Service Temperatures	—	-40°F to +250°F
Dimensional Stability	ASTM D 2126	7 days 158°F 35% RH < 2% Change

Note: The physical properties shown are based on data obtained under controlled conditions and are subject to normal manufacturing tolerances.

WARNING

Polyisocyanurate is an organic material which will burn when exposed to an ignition source of sufficient heat and intensity and may contribute to flames spreading.

NOTE:

Rmax does not assume any responsibility or liability for the performance of any products other than those manufactured by Rmax.

THERMAL PROPERTIES & PRODUCT DATA

"R" means resistance to heat flow. The higher the R-value, the greater the insulating power.

Nominal Thickness	Thermal Value ¹		Wt. Per Sq. (lbs.)	48" x 96"				Flute Spanability
	C	R		Bundle		Truckload		
				Pieces	Sq. Ft.	Pieces	Sq. Ft.	
1.3'	12	8.3	22	36	1,152	792	25,344	3 "
1.5	10	10.0	25	32	1,024	704	22,528	3 ³ / ₈ "
1.6	09	11.1	27	30	960	660	21,120	3 ⁷ / ₈ "
1.8	08	12.5	30	26	832	572	18,304	3 ³ / ₄ "
2.0	075	13.3	34	24	768	528	16,896	3 ³ / ₈ "
2.1	07	14.3	35	22	704	484	15,488	3 ³ / ₄ "
2.3	06	16.7	38	20	640	440	14,080	3 ³ / ₈ "
2.6	052	19.2	42	18	576	396	12,672	3 ⁵ / ₈ "
2.7	05	20.0	43	17	544	374	11,968	3 ⁵ / ₈ "
3.3	04	25.0	55	14	448	308	9,856	3 ⁵ / ₈ "
3.5	038	26.3	59	13	416	286	9,152	3 ⁵ / ₈ "

¹ Thermal values may vary for West Coast shipping zone, consult Rmax for latest information.

² Thermal values are determined by using the ASTM C518 test method at 75 degrees F mean temperature on material conditioned according to RIC/TIMA Conditioning Procedure 281-1. The 1 3/4" thickness is approved for the FM Class I-60 wind uplift, not Class I-90.

FOAMWALL

7 OF 89

Backed by 24 Years
Experience

SHEETS 07410

FOAMWALL offers one of the best insulated wall systems available today. Typical still air U-Values are 0.067 (moving air 0.069) for 2" thick FOAMWALL Panels. It is a wall of insulation, rather than an insulated wall.

The amount of heating and cooling energy required can be less when compared to other types of construction, such as brick and block construction whose U-Values range around 0.330.

FOAMWALL should be used by all designers and owners who are interested in long term Life Cycle Costing Programs because of the potential savings for heating and cooling. In addition, the inherent rigidity and strength of this system permits reduction of overall construction costs through elimination of unnecessary steel girt supports. Erection costs are also lower, because the wide single component panels permit a shorter erection time interval with the added benefit of faster client "move-in."

FOAMWALL Panels provide virtually no heat loss due to air infiltration. One of the most important factors in any wall is the side lap system. Many systems insulate well but permit thermal losses at panel joints. When tested by ANSI/ASTM E 283-73 Test Procedure, FOAMWALL's side lap joint results in virtually no measurable air infiltration.

A basic requirement of any wall system is to resist water infiltration. FOAMWALL, when tested by ANSI/ASTM E 331-70 (Reapproved 1975) Test Procedure for side lap joint condition, results in virtually no water penetration at better than 20 psf wind force.

FOAMWALL Panels have undergone 1.5 million cycles of positive to negative deflection cycling, which means the system will perform scores of years with no concern for delamination due to normal wind loads.

High humidity and temperature evaluation, as related to the bonding ability of the insulating foam to the metal skins, is a necessary requirement for a foamed-in-place product. FOAMWALL has been tested under these severe environmental conditions with little or no effect on the metal-foam interface strength.

FOAMWALL, manufactured with recently developed urethane foam is equal to or better than existing model building code requirements. Listed below are a few of the tests FOAMWALL has undergone.

UNDERWRITERS' LABORATORIES

TUNNEL TEST, UL GUIDE BLBT. Subject 723 — The finished panel shall have a Flame Spread of 10" and a Smoke Developed Rating of 110-145

NFPA 259, Potential Heat Content Test—results in compliance with Model Building Codes.

FACTORY MUTUAL

4411 TEST—Automatic Sprinkler Protection May Not Be Required. The fire hazard of the approved construction has been evaluated for fuel contribution, surface flame spread, vertical flame spread within the core and susceptibility to radiant heat. Approved wall panels, including foamed plastic insulated walls not exceeding 30 feet (9m) in height, are considered Class I panels of limited combustibility, not requiring automatic sprinkler protection of themselves when faced with the specified facing materials.

ASTM

ASTM D 1929-77—Ignition Temperature Test (Details and results are available on request).

ASTM D 2015-77—Fuel Content Test—results in compliance with Model Building Codes.

RESEARCH REPORTS

ICBO—See International Conference of Building Officials Research Report No. PFC3620.

SBCCI—See Southern Building Code Congress International Compliance Report No. 8488.

BOCA—See Building Officials and Code Administrators Research Report No. 84-38.

COMBUSTIBILITY AND SAFETY

*This numerical flame spread rating is not intended to reflect hazards by this material or any other material under actual fire conditions.

Approved diversified tests such as a corner test, enclosed room

under simulated fire conditions. The core material in this product is cellular plastic and, as such, is combustible. Consequently, should not be exposed to open flames, excessive heat, or high temperatures. The use of this product also may be restricted by local fire codes and regulations. Authorities will

FOAMWALL
AVAILABLE
Produce
develop
experien
proved p
criteria a
productic

STAN

- An
- Low
- Cur
- Low
- Long
- Ther
- Forr
- Hori
- Long
- Fast

CORNER
WALL
TEST

See U

CUS
SPECIALI

CUSTOM FOAMWALL
Products who w
for their clie
be applied to
features mak
choice for wa

CUSTO

- Fade-
- Variab
- Variab
- Increa
- Swedd
- Curved

FIRE RESISTIN
OR SPECIAL
COMPLIANCE

FOAMWALL has qu
DESIGN U029
Assembl
Restrictive
Unrest

Two Economical Exterior Wall Insulation and Finish Systems Featuring Owens-Corning Glas-Lath® Fiberglass Insulation Board.

(SWEETS 07240)

Exsulation . . . A "One-Step" System Offering On The Wall Savings

Exsulation is a system jointly developed by Dryvit®, the pioneer in the manufacture of Exterior Wall Insulation and Finish Systems, and Owens-Corning Fiberglas® Corporation, the recognized leader in the development and manufacture of insulation and quality building materials.

The System incorporates Owens-Corning Glas-Lath Fiberglass Insulation Board in combination with Dryvit Genesis™ Base Coat, a 100% acrylic polymer based coating and a broad range of Dryvit finish options.

Glas-Lath is a semi-rigid fiberglass insulation board that can be applied over open wood or steel framing or a variety of substrates such as painted masonry, plywood or textured wood in a simple one-step application with corrosion resistant mechanical fasteners. The Glas-Lath Insulation Board can serve as its own sheathing, and the reinforcing mesh is bonded at the factory. These two features alone greatly reduce on the wall labor costs.

Choose Exsulation Plus or Exsulation

Exsulation Plus consists of an ultra-smooth Genesis Base Coat, Glas-Lath and any one of Dryvit's standard textures — Quarzputz®, Freestyle® or Sandblast® — in any of 21 colors or in a custom color to order. Dryvit Carrara, a genuine marble aggregate finish, may also be used.

Exsulation is a high quality more economical system with a textured finish Genesis Base Coat and Dryvit Demandit® coating, either spray or roller applied.

For Cost-Competitive Jobs. Residential, Commercial, Industrial

Exsulation is an exterior wall system for the developer, architect or builder seeking a design structure with a "luxurious look" on a limited construction budget.

The mechanically fastened Exsulation System is also ideal for rehab of older structures to improve both the appearance of the building and its energy efficiency.

Fast On-Site Application

The System is "fast track". Once framing is in place, wall areas are completed quickly, particularly since the Glas-Lath insulation is its own sheathing. The reinforcing mesh is bonded at the factory, minimizing labor costs at the job site.

R-Values Are Excellent

The Glas-Lath Insulation Board in all thicknesses offers energy efficient R-values. 1" — 4.35, 1½" — 6.50, 2" — 8.7. In addition, the resiliency of the board protects against impact damage.

Table 3A Thermal Properties of Typical Building and Insulating Materials—Design Values^a

Description	Density lb/ft ³	Conduc- tivity ^b λ Btu·in./ h·ft ² ·F	Conduc- tance (C) Btu/h· ft ² ·F	Resistance ^c (R)		Specific Heat Btu/lb · deg F
				Per inch thickness (1/λ) h·ft ² · F/Btu	For thick- ness listed (1/C) h·ft ² · F/Btu	
BUILDING BOARD						
Boards, Panels, Subflooring, Sheathing						
Woodboard Panel Products						
Asbestos-cement board.....	120	4.0	—	0.25	—	0.24
Asbestos-cement board..... 0.125 in.	120	—	33.00	—	0.03	—
Asbestos-cement board..... 0.25 in.	120	—	16.50	—	0.06	—
Gypsum or plaster board..... 0.375 in.	50	—	3.10	—	0.32	0.26
Gypsum or plaster board..... 0.5 in.	50	—	2.22	—	0.45	—
Gypsum or plaster board..... 0.625 in.	50	—	1.78	—	0.56	—
Plywood (Douglas Fir) ^o	34	0.80	—	1.25	—	0.29
Plywood (Douglas Fir)..... 0.25 in.	34	—	3.20	—	0.31	—
Plywood (Douglas Fir)..... 0.375 in.	34	—	2.13	—	0.47	—
Plywood (Douglas Fir)..... 0.5 in.	34	—	1.60	—	0.62	—
Plywood (Douglas Fir)..... 0.625 in.	34	—	1.29	—	0.77	—
Plywood or wood panels..... 0.75 in.	34	—	1.07	—	0.93	0.29
Vegetable Fiber Board						
Sheathing, regular density..... 0.5 in.	18	—	0.76	—	1.32	0.31
Sheathing, regular density..... 0.78125 in.	18	—	0.49	—	2.06	—
Sheathing intermediate density..... 0.5 in.	22	—	0.82	—	1.22	0.31
Nail-base sheathing..... 0.5 in.	25	—	0.88	—	1.14	0.31
Shingle backer..... 0.375 in.	18	—	1.06	—	0.94	0.31
Shingle backer..... 0.3125 in.	18	—	1.28	—	0.78	—
Sound deadening board..... 0.5 in.	15	—	0.74	—	1.35	0.30
Tile and lay-in panels, plain or acoustic.....	18	0.40	—	2.50	—	0.14
Tile and lay-in panels, plain or acoustic..... 0.5 in.	18	—	0.80	—	1.25	—
Tile and lay-in panels, plain or acoustic..... 0.75 in.	18	—	0.53	—	1.89	—
Laminated paperboard.....	30	0.50	—	2.00	—	0.33
Homogeneous board from repulped paper.....	30	0.50	—	2.00	—	0.28
Hardboard						
Medium density.....	50	0.73	—	1.37	—	0.31
High density, service temp. service underlay.....	55	0.82	—	1.22	—	0.32
High density, std. tempered.....	63	1.00	—	1.00	—	0.32
Particleboard						
Low density.....	37	0.54	—	1.85	—	0.31
Medium density.....	50	0.94	—	1.06	—	0.31
High density.....	62.5	1.18	—	0.85	—	0.31
Underlayment..... 0.625 in.	40	—	1.22	—	0.82	0.29
Wood subfloor..... 0.75 in.	—	—	1.06	—	0.94	0.33
BUILDING MEMBRANE						
Vapor—permeable felt.....	—	—	16.70	—	0.06	—
Vapor—seal, 2 layers of mopped 15-lb felt.....	—	—	8.35	—	0.12	—
Vapor—seal, plastic film.....	—	—	—	—	Negl.	—
FINISH FLOORING MATERIALS						
Carpet and fibrous pad.....	—	—	0.48	—	2.08	0.34
Carpet and rubber pad.....	—	—	0.81	—	1.23	0.33
Cork tile..... 0.125 in.	—	—	3.60	—	0.28	0.48
Terrazzo..... 1 in.	—	—	12.50	—	0.08	0.19
Tile—asphalt, linoleum, vinyl, rubber.....	—	—	20.00	—	0.05	0.30
vinyl asbestos.....	—	—	—	—	—	0.24
ceramic.....	—	—	—	—	—	0.19
Wood, hardwood finish..... 0.75 in.	—	—	1.47	—	0.68	—
INSULATING MATERIALS						
Blanket and Batt ^d						
Mineral Fiber, fibrous form processed from rock, slag, or glass						
approx. ^e 3–4 in.....	0.3–2.0	—	0.091	—	11 ^d	—
approx. ^e 3.5 in.....	0.3–2.0	—	0.077	—	13 ^d	—
approx. ^e 5.5–6.5 in.....	0.3–2.0	—	0.053	—	19 ^d	—
approx. ^e 6–7.5 in.....	0.3–2.0	—	0.045	—	22 ^d	—
approx. ^e 9–10 in.....	0.3–2.0	—	0.033	—	30 ^d	—
approx. ^e 12–13 in.....	0.3–2.0	—	0.026	—	38 ^d	—

AMOFAM®-CM is a square edge extruded polystyrene insulation recommended for masonry wall and foundation systems. AMOFAM-CM is available in 2' x 8' and 4' x 8' rigid boards in a variety of thicknesses, including 1/2" thick 2' x 8' AMOFAM-CM, which is widely used as residing underlayment.

AMOFAM®-SL features shiplap edges to help reduce air infiltration. AMOFAM-SL is recommended as an exterior sheathing and residing underlayment.

The product's shiplap edges fit together with more ease than tongue and groove designs. Shiplap edges are as good or better than tongue and groove designs in reducing air infiltration (according to independent testing).

AMOFAM-SL is available in 1/2", 5/8", 3/4", 1", 1-1/2", and 2" thicknesses, in 2' x 8', 4' x 8', and 4' x 9' rigid boards. The 4' x 9' size provides insulation and air infiltration protection for the box sill and crawl space area without horizontal butt joints.

AMOFAM®-SB is scored 16" and 24" on center, and is designed primarily for masonry wall and foundation systems. The scoring enables the boards to be cleanly broken at the job site to meet concrete forming and wall-tie requirements. AMOFAM-SB is available in 4' x 8' rigid boards in 1", 1-1/2" and 2" thicknesses.

AMOFAM® Insulation R-values

Thickness (in.)	R-value @ 75°F
1/2	2.8
5/8	3.1
3/4	3.8
1	5.0
1 1/2	7.5
2	10

PP/Product Presentation

AMOCOR® Fanfold Products

AMOCOR® brand Fanfold Products feature a unique composition of extruded polystyrene foam sandwiched between two high impact plastic capsheets. This composition provides additional strength and rigidity and also facilitates scoring and folding of the 4' x 50' (two square) products.

The plastic capsheets are perforated or non-perforated as necessary for moisture and water vapor control. AMOCOR Fanfold Products are also available with a highly reflective aluminized plastic surface on one side to increase R-value in wall systems with a parallel dead air space.

AMOCOR®-PB4 protects waterproofing membranes.

AMOCOR-P14 & FP14 (1 4"), and AMOCOR-P38 & FP38 (3 8") are yellow colored extruded polystyrene foam products sandwiched between two perforated plastic capsheets. AMOCOR-FP14 and FP38 differ from AMOCOR-P14 and P38 in that they feature a perforated, reflective aluminized plastic capsheet on one side. The reflective capsheet can increase the R-value of a wall cavity if applied as part of a system using a 1/2" minimum dead air space.

These products are recommended for use as an underlayment for replacement siding. Their fanfold design provides excellent continuous protection against the energy robbing effects of air infiltration, and offers a smooth level surface for hanging new siding.

AMOCOR-PB4 (1 4") and AMOCOR-PB6 (3 8") are aqua colored extruded polystyrene foam products sandwiched between two durable high impact plastic capsheets. These plastic capsheets are not perforated to give substantially more impact strength. Each sheet is 4' x 50' (two square) fanfolded every two feet.

AMOCOR-PB4 and AMOCOR-PB6 are designed for use as a protection course for most sheet and liquid applied waterproofing systems and are an economical alternative to conventional asphalt impregnated fiberboard and beadboard materials. Each two square bundle of AMOCOR-PB4 and AMOCOR-PB6 weigh about 16 and 20 pounds, respectively, and minimize installation time and cost.

AMOCOR-PB4 and AMOCOR-PB6 are recommended for perimeter/vertical concrete or masonry walls where waterproofing membrane protection during backfill is the primary concern.

AMOCOR-PB4 and AMOCOR-PB6 can also be used as a recovery board for single-ply roof membranes to protect the membrane from puncture damage.

AMOCOR-PB6 is recommended for post-frame agricultural buildings as a condensation panel to prevent roof corrosion and in side walls to reduce air infiltration and moisture migration. If any portion of a building is to be used for any purpose other than the storage of produce or housing of livestock or poultry, it is recommended that an adequate fire barrier, such as 1/2" gypsum board, cover the foam on the interior wall side. Consult local insurance authorities for regulations.

The plastic sandwich composition of AMOCOR-PB4 and AMOCOR-PB6 resists damage and breakage, and is extremely lightweight, economical and easy to install.

Fig. 22 Design Thicknesses for Annealed Glass

through the fenestration; they act as an absorber for sound that does penetrate. Table 31 lists average sound transmission losses for various types of glass. These averages apply for the frequency range of 125 to 4000 hertz and were determined using ASTM E 90-70.²³ For further details, see Chapter 32 of the 1984 SYSTEMS VOLUME.

Strength/Safety. In addition to its functions thermally, visually and aesthetically, glass for building exteriors must also be designed for structural performance. Wind loads are specified in most building codes and these requirements may be adequate for many structures. It is suggested, however, that detailed wind tunnel tests be run for tall or unusually shaped buildings and for buildings where the surroundings may create unusual wind patterns. Alternative loading conditions should be chosen and provided for in developing design specifications when wind load tests suggest wind loading conditions different from those used in Fig. 22. All manufacturers are not in agreement on the values presented here; for specific information, consult the glass manufacturer.

Figure 22 shows the relationship between size, thickness and strength of annealed glass using a design factor of 2.5 (average breaking pressure divided by 2.5). The graphs are based on actual tests to destruction in which the glass was exposed to uniform loads increased in increments and held static for one minute. Figure 22 applies to rectangular lights of glass, with length-to-width ratios not more than 5:1, firmly supported on all four edges. To determine the uniform load of nonannealed glass held on four sides, use the appropriate multiplying factor listed in Table 32.

Tinted and reflective-type glasses are especially vulnerable to thermal stress. Consult the manufacturer's recommendations concerning thermal stress performance.

Glass safety requirements must also be considered. Building codes may require glass in certain positions to perform with certain breakage characteristics, which can be satisfied by tempered, laminated or wired glass. In this case, specify glass that meets Federal Standard 16 CRF 1201²⁶ or other appropriate breakage performance requirements.

Life Cycle Costs. Compare each viable alternative building shell system to assure satisfactory energy utilization and total energy budget compliance, if required. To do this, a life cycle cost model should be developed for each system considered (see Chapter 42 of the 1984 SYSTEMS VOLUME).

FACTORS INFLUENCING THE CHOICE OF PLASTIC MATERIALS FOR GLAZING

Generally, the factors outlined for glass apply also to glazing materials such as acrylic or other plastic panels (Table 33). If the properties of solar transmittance, absorptance and reflectance are known, a Shading Coefficient can be calculated in the same way it is for glass. These properties can be obtained from the manufacturer or determined by simple laboratory tests. Both ASHRAE and ASTM have developed standards for performing these tests.

Table 34 lists solar optical properties of typical plastic materials. Plastic panels are available with transmittance values from 10% to 92% and reflectance values from 4% to over 60%. Emittances for acrylic, polystyrene and polycarbonate glazings all range between 0.88 and 0.92. Plastics are available in translucent and transparent form; some are corrugated. Many tints (colors) are also available.

Table 32 Multiplying Factor for Glass Other than Annealed

Type of Glass	Multiplying Factor*
Tempered	4.0
Heat Strengthened	2.0
Double-Glazed	1.5
Rough Plate	1.0
Laminated	0.6
Wired	0.5

*Sandblasting will significantly weaken glass, and can reduce its strength by 60% or more. Sandblasted glass should not be used for exterior glazing.

Table 33 Overall Coefficient of Heat Transmission (U -Factor, $\text{Btu/h} \cdot \text{ft}^2 \cdot \text{F}$) for Transparent Acrylic and Polycarbonate Sheeting of Vertical Windows

Thickness, in.	U -Factor for Winter Heat Loss ^a				
	1/8 in.	3/16 in.	1/4 in.	3/8 in.	1/2 in.
Single-Glazed ^c	1.07	1.01	0.96	0.88	0.81
Reflective ^d	—	—	0.88	—	—
Double-Glazed ^c	—	—	—	—	—
1/4-in. air space	0.54	0.51	0.49	—	—
Double-Glazed ^c	—	—	—	—	—
5/8-in. air space	0.47	0.45	0.43	—	—
Thickness, in.	U -Factor for Summer Heat Gain ^b				
	1/8 in.	3/16 in.	1/4 in.	3/8 in.	1/2 in.
Single-Glazed ^c	0.95	0.91	0.88	0.82	0.76
Reflective ^d	—	—	0.83	—	—
Double-Glazed ^c	—	—	—	—	—
1/4-in. air space	0.56	0.53	0.51	—	—
Double-Glazed ^c	—	—	—	—	—
1/2-in. air space	0.50	0.48	0.46	—	—

^a 15 mph wind velocity.

^b 7.5 mph wind velocity.

^c Hemispherical emittance = 0.86.

^d Aluminum metallized polyester film on plastic.

Fenestration

Table 28 Coefficients for DSA Glass for Use in Computer Calculation of Transmittance and Absorptance^a

i	a_i	t_i
0	0.01154	-0.00885
1	0.77674	2.71235
2	-3.94657	-0.62062
3	8.57881	-7.07329
4	-8.38135	9.75995
5	3.01188	-3.89922

^aFor other types of glass, contact manufacturer.

other dates can be obtained by interpolation. The transmission and absorption coefficients for DSA glass are given in Table 28. The absorption or transmission of direct solar radiation incident at an angle θ is:

$$\alpha_D = \sum_{j=0}^5 a_j \cos^j \theta$$

$$\tau_D = \sum_{j=0}^5 t_j \cos^j \theta$$

Note that this calculation procedure, using data in Table 28, gives a normal transmittance for DSA glass of 0.88 which is slightly higher than values used elsewhere in this chapter.

Tables 19 through 27 are based on a ground reflectance ρ_g of 0.2 and a heat transfer factor, inward flow fraction N_i of 0.267.

Equations:

Hour Angle (deg)	$H = 0.25$ (min of time from local solar noon)
Solar Altitude β	$\sin \beta = \cos L \cos \delta \cos H + \sin L \sin \delta$
Solar Azimuth ϕ	$\cos \phi = (\sin \beta \sin L - \sin \delta) / (\cos \beta \cos L)$ $0 \text{ deg} \leq \phi \leq 90 \text{ deg}$ if $\cos \phi \geq 0$ $90 \text{ deg} < \phi \leq 180 \text{ deg}$ if $\cos \phi < 0$
Surface-Solar Azimuth γ	$\gamma = \phi - \psi$ am $\gamma = \phi + \psi$ pm
Incident Angle θ	$\cos \theta_v = \cos \beta \cos \gamma$ vertical surface $\cos \theta_H = \sin \beta$ horizontal surface
Direct Normal Intensity I_{DN}	$I_{DN} = A \exp(-B / \sin \beta)$
Direct Intensity I_D	$I_D = I_{DN} \cos \theta$ if $\cos \theta > 0$ $I_D = 0$ otherwise
Ratio of Sky Diffuse on Vertical Surface to Sky Diffuse on Horizontal Surface Y	If $\cos \theta > -0.2$ $Y = 0.55 + 0.437 \cos \theta + 0.313 \cos^2 \theta$ otherwise, $Y = 0.45$
Diffuse Intensity I_d	
Horizontal	$I_d = C I_{DN}$
Vertical	$I_d = [CY + 0.5 \rho_g (C + \sin \beta)] I_{DN}$
Solar Heat Gain Transmitted Component	$= I_D \sum_{j=0}^5 t_j \cos^j \theta$ $+ I_d 2 \sum_{j=0}^5 t_j / (j+2)$

$$\begin{aligned} \text{Absorbed Component} &= I_D \sum_{j=0}^5 a_j \cos^j \theta \\ &+ I_d 2 \sum_{j=0}^5 a_j / (j+2) \end{aligned}$$

$$\text{Solar Heat Gain Factor} = \frac{\text{Energy Transmitted through} + N_i \cdot \text{Energy Absorbed}}{\text{Energy Incident}}$$

Values of SC given in Table 29 are based on an incident solar radiation equivalent to a SHGF of 216 Btu/h·ft² that in Tables 19 through 27 correspond approximately with the SHGF for July 21 through September 21 for a west oriented window at 1600 suntime for north latitudes from 16 to 40 degrees. The angles of incidence for these times and latitudes are 36, 32, and 30 degrees for July 21, August 21 and September 21, respectively. These low incidence angles permit use of normal incidence solar properties of the fenestration without adjustment for angular effects. See Fig. 12 for the variation of solar optical properties of glasses with angle of incidence.

Furthermore, the values of SC given in Table 29 are based on still air (natural convection) at the inner surface of the fenestration and 7.5 mph wind at the outer surface. For these conditions h_i is about 1.46 Btu/h·ft²·F (see Table 16 for specific values) and h_o is 4.0 Btu/h·ft²·F, so the inward flowing fraction of absorbed heat for single glazing is:

$$N_i = h_i / (h_i + h_o) = 1.46 / 5.46 = 0.267 \quad (39)$$

(Resistance of the glass plate is neglected.)

For other indoor and outdoor conditions, the surface coefficients will vary over a considerable range, and N_i will also change. The variation in SC that results from these changes in surface coefficients is shown in Fig. 16. For comparison, Table 29 also lists SC for $h_o = 3.0$. The designer should be aware of the possible variations upward and downward in the SC for any fenestration when the surface conditions vary from still air and 7.5 mph wind at the inner and outer surfaces, respectively.

The SC for any fenestration will rise above the tabulated values when the inner surface coefficient is increased because of forced air flow over that surface, and when the outer surface coefficient is decreased by lower wind velocity. Conversely, the SC will fall somewhat below the tabulated values when the air at the inner surface is still and the wind velocity rises above 7.5 mph.

Table 29 Shading Coefficients for Single Glass and Insulating Glass^a

A. Single Glass				
Type of Glass	Minimal Thickness ^b	Solar Trans. ^b	Shading Coefficient $h_o=4.0$	$h_o=3.0$
Clear	1/8 in.	0.86	1.00	1.00
	1/4 in.	0.78	0.94	0.95
	3/8 in.	0.72	0.90	0.92
	1/2 in.	0.67	0.87	0.88
Heat Absorbing	1/8 in.	0.64	0.83	0.85
	1/4 in.	0.46	0.69	0.73
	3/8 in.	0.33	0.60	0.64
	1/2 in.	0.24	0.53	0.58
B. Insulating Glass				
Clear Out, Clear In	1/8 in. ^c	0.71 ^e	0.88	0.88
Clear Out, Clear In	1/4 in.	0.61	0.81	0.82
Heat Absorbing ^d Out, Clear In	1/4 in.	0.36	0.55	0.58

^aRefers to factory-fabricated units with 3/16, 1/4 or 1/2-in. air space or to prime windows plus storm sash.

^bRefer to manufacturer's literature for values.

^cThickness of each pane of glass, not thickness of assembled unit.

^dRefers to gray, bronze and green tinted heat-absorbing float glass.

^eCombined transmittance for assembled unit.

12 OF 89
27.29

14 OF

NEW CEILING

NEW WALLS AT
ENTRY, CHANGEROOMS &
LABORATORY

2/4/93

2/4/93

17 OF 89

Trane Air Conditioning Economics
By: Trane Customer Direct Service Network

V 60
PAGE 1

**
**
**
**
**
**
**

TRACE 600 ANALYSIS

by Trane Customer Direct Service Network

RADIOACTIVE LIQUID WASTE TREATMENT FAC
LOS ALAMOS, NEW MEXICO
LOS ALAMOS NATIONAL LABS
C. QUARTIERI
REFURBISHMENT OF EXISTING BLDG 1, TA-50

Weather File Code: LAWTR1
Location:
Latitude: 36.0 (deg)
Longitude: 106.0 (deg)
Time Zone: 7
Elevation: 7,500 (ft)
Barometric Pressure: 22.1 (in. Hg)

Summer Clearness Number: 1.10
Winter Clearness Number: 1.05
Summer Design Dry Bulb: 89 (F)
Summer Design Wet Bulb: 60 (F)
Winter Design Dry Bulb: 5 (F)
Summer Ground Relectance: 0.20
Winter Ground Relectance: 0.20

Air Density: 0.0560 (Lbm/cuft)
Air Specific Heat: 0.2444 (Btu/lbm/F)
Density-Specific Heat Prod: 0.8211 (Btu-min./hr/cuft/F)
Latent Heat Factor: 3,614.5 (Btu-min./hr/cuft)
Enthalpy Factor: 3.3592 (Lb-min./hr/cuft)

Design Simulation Period: June To November
System Simulation Period: January To December
Cooling Load Methodology: TETD/Time Averaging

Time/Date Program was Run: 11: 0:18 3/10/93
Dataset Name: 173RLWR2 .TM

AIRFLOW - ALTERNATIVE 1

----- S Y S T E M S U M M A R Y -----
(Design Airflow Quantities)

System Number	System Type	----- Main -----					Auxil. Supply	Room Exhaust
		Outside Airflow (Cfm)	Cooling Airflow (Cfm)	Heating Airflow (Cfm)	Return Airflow (Cfm)	Exhaust Airflow (Cfm)	Airflow (Cfm)	Airflow (Cfm)
1 SZ		4,738	31,585	31,585	31,585	4,738	0	4,738
2 SZ		110,135	129,529	129,529	129,529	110,135	0	110,135
3 SZ		6,551	13,094	13,094	13,094	6,551	0	6,551
4 SZ		70,837	84,584	84,584	84,584	70,837	0	70,837
5 SZ		12,934	86,227	86,227	86,227	12,934	0	12,934
6 SZ		3,585	23,898	23,898	23,898	3,585	0	3,585
7 SZ		3,367	14,497	14,497	14,497	3,367	0	3,367
8 SZ		1,965	2,064	2,064	2,064	1,965	0	1,965
9 SZ		6,364	34,079	34,079	34,079	6,364	0	6,364
Totals		220,475	419,556	419,556	419,556	220,475	0	220,475

CAPACITY - ALTERNATIVE 1

----- S Y S T E M S U M M A R Y -----
(Design Capacity Quantities)

System Number	System Type	----- Cooling -----				----- Heating -----						
		Main Sys. Capacity (Tons)	Aux. Sys. Capacity (Tons)	Opt. Vent Capacity (Tons)	Cooling Totals (Tons)	Main Sys. Capacity (Btuh)	Aux. Sys. Capacity (Btuh)	Preheat Capacity (Btuh)	Reheat Capacity (Btuh)	Humidif. Capacity (Btuh)	Opt. Vent Capacity (Btuh)	Heating Totals (Btuh)
1 SZ		57.4	0.0	0.0	57.4	-516,508	0	0	0	0	0	-516,508
2 SZ		93.1	0.0	0.0	93.1	-5,328,245	0	-5,448,958	0	0	0	-5,328,245
3 SZ		22.1	0.0	0.0	22.1	-379,881	0	-291,294	0	0	0	-379,881
4 SZ		159.9	0.0	0.0	159.9	-3,834,199	0	-3,357,115	0	0	0	-3,834,199
5 SZ		126.8	0.0	0.0	126.8	-866,107	0	-355,789	0	0	0	-866,107
6 SZ		36.7	0.0	0.0	36.7	-250,742	0	-79,913	0	0	0	-250,742
7 SZ		8.9	0.0	0.0	8.9	-218,186	0	-138,453	0	0	0	-218,186
8 SZ		4.6	0.0	0.0	4.6	-101,797	0	-78,661	0	0	0	-101,797
9 SZ		41.1	0.0	0.0	41.1	-362,717	0	-49,764	0	0	0	-362,717
Totals		550.5	0.0	0.0	550.5	11,858,381	0	-9,799,947	0	0	0	-11,858,382

19 OF 89

Trane Air Conditioning Economics
By: Trane Customer Direct Service Network

V 600
PAGE 3

ENGINEERING CHECKS - ALTERNATIVE 1

----- ENGINEERING CHECKS -----

System Number	Main/ Auxiliary	System Type	Percent Outside Air	----- Cooling -----				--- Heating ---		Floor Area Sq Ft
				Cfm/ Sq Ft	Cfm/ Ton	Sq Ft /Ton	Btuh/ Sq Ft	Cfm/ Sq Ft	Btuh/ Sq Ft	
1	Main	SZ	15.00	1.42	550.1	388.4	30.90	1.42	-23.16	22,300
2	Main	SZ	85.03	3.54	1,391.1	393.3	30.51	3.54	-145.51	36,617
3	Main	SZ	50.03	3.00	593.6	198.0	60.61	3.00	-86.99	4,367
4	Main	SZ	83.75	2.99	529.1	177.2	67.71	2.99	-135.32	28,335
5	Main	SZ	15.00	3.04	680.3	223.5	53.68	3.04	-30.57	28,335
6	Main	SZ	15.00	3.13	651.4	208.0	57.69	3.13	-32.85	7,632
7	Main	SZ	23.22	3.23	1,625.8	503.4	23.84	3.23	-48.60	4,489
8	Main	SZ	95.17	1.58	450.5	285.8	41.99	1.58	-77.72	1,310
9	Main	SZ	18.67	4.04	829.5	205.3	58.44	4.04	-43.00	8,435

V 600
PAGE 4

Peaked at Time ==>	Mo/Hr: 7/17	*	Mo/Hr: 6/20	*	Mo/Hr: 13/ 1
Outside Air ==>	OADB/WB/HR: 85/ 58/ 56.0	*	OADB: 78	*	OADB: 5

-----HEATING COIL SELECTION-----					-----AIRFLOWS (cfm)-----			--ENGINEERING CHECKS--		--TEMPERATURES (F)---		
	Capacity	Coil Airfl	Ent	Lvg	Type	Cooling	Heating	Clg % OA	15.0	Type	Clg	Htg
	(Mbh)	(cfm)	Deg F	Deg F	Vent	4,738	4,738	Clg Cfm/Sqft	1.42	SADB	53.5	81.9
Main Htg	-516.5	31,585	61.9	81.9	Infil	0	0	Clg Cfm/Ton	550.06	Plenum	75.0	72.0
Aux Htg	0.0	0	0.0	0.0	Supply	31,585	31,585	Clg Sqft/Ton	388.37	Return	75.2	72.0
Preheat	-0.0	31,585	62.0	49.7	Mincfm	0	0	Clg Btuh/Sqft	30.90	Ret/OA	76.8	61.9
Reheat	0.0	0	0.0	0.0	Return	26,847	31,585	No. People	24	Runarnd	75.0	72.0
idif	0.0	0	0.0	0.0	Exhaust	0	4,738	Htg % OA	15.0	Fn MtrTD	0.9	0.0
Exh Vent	0.0	0	0.0	0.0	Rm Exh	4,738	0	Htg Cfm/SqFt	1.42	Fn BldTD	0.7	0.0
	-516.5				Auxil	0	0	Htg Btuh/SqFt	-23.16	Fn Frict	2.1	0.0

stem 2 Peak SZ - SINGLE ZONE

***** COOLING COIL PEAK ***** CLG SPACE PEAK ***** HEATING COIL PEAK *****

Peaked at Time ==> Mo/Hr: 7/15 * Mo/Hr: 6/19 * Mo/Hr: 13/ 1
Outside Air ==> OADB/WB/HR: 87/ 60/ 63.0 * OADB: 81 * OADB: 5

	Space	Ret. Air	Ret. Air	Net	Perct		Space	Perct		Space Peak	Coil Peak	Perct
	Sens.+Lat.	Sensible	Latent	Total	Of Tot		Sensible	Of Tot		Space Sens	Tot Sens	Of Tot
	(Btuh)	(Btuh)	(Btuh)	(Btuh)	(%)		(Btuh)	(%)		(Btuh)	(Btuh)	(%)
Envelope Loads												
Skylite Solr	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Skylite Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Roof Cond	5,541	0		5,541	0.50	*	2,737	0.35	*	-3,505	-3,505	0.07
Glass Solar	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Glass Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Wall Cond	106,942	0		106,942	9.57	*	148,007	19.08	*	-203,788	-203,788	3.82
Partition	0			0	0.00	*	0	0.00	*	0	0	0.00
Exposed Floor	0			0	0.00	*	0	0.00	*	-3,910	-3,910	0.07
Infiltration	0			0	0.00	*	0	0.00	*	0	0	0.00
Sub Total==>	112,483	0		112,483	10.07	*	150,745	19.44	*	-211,203	-211,203	3.96
Internal Loads						*			*			
Lights	374,924	0		374,924	33.56	*	374,924	48.34	*	0	0	0.00
People	0			0	0.00	*	0	0.00	*	0	0	0.00
Misc	249,949	0	0	249,949	22.37	*	249,949	32.23	*	0	0	0.00
Sub Total==>	624,873	0	0	624,873	55.93	*	624,873	80.56	*	0	0	0.00
Ceiling Load	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Outside Air	0	0	0	177,319	15.87	*	0	0.00	*	0	-5,117,042	96.04
.. Fan Heat				202,642	18.14	*		0.00	*		0	0.00
.. Fan Heat		0		0	0.00	*		0.00	*		0	0.00
Duct Heat PkUp		0		0	0.00	*		0.00	*		0	0.00
OV/UNDR Sizing	1			1	0.00	*	1	0.00	*	0	0	0.00
Exhaust Heat		0	0	0	0.00	*		0.00	*		0	0.00
Terminal Bypass		0	0	0	0.00	*		0.00	*		0	0.00
Grand Total==>	737,357	0	0	1,117,318	100.00	*	775,618	100.00	*	-211,203	-5,328,245	100.00

-----COOLING COIL SELECTION-----

	Total Capacity	Sens Cap.	Coil Airfl	Entering DB/WB/HR	Leaving DB/WB/HR	Gross Total	Glass (sf)	(%)
	(Tons)	(Mbh)	(cfm)	Deg F Deg F Grains	Deg F Deg F Grains	Floor		
Main Clg	93.1	1,117.3	2,078.9	84.8 59.1 60.6	64.8 55.7 75.3	Part	36,617	
Aux Clg	0.0	0.0	0.0	0.0 0.0 0.0	0.0 0.0 0.0	ExFlr	0	
Opt Vent	0.0	0.0	0.0	0.0 0.0 0.0	0.0 0.0 0.0	Roof	692	
Totals	93.1	1,117.3				Wall	876	0 0
							29,005	0 0

-----AREAS-----

-----HEATING COIL SELECTION-----

	Capacity	Coil Airfl	Ent	Lvg	Type	Cooling	Heating	Clg % OA	85.0	Type	Clg	Htg
	(Mbh)	(cfm)	Deg F	Deg F	Vent	110,135	110,135	Clg Cfm/Sqft	3.54	SADB	66.8	64.5
Main Htg	-5,328.2	129,529	14.4	64.5	Infil	0	0	Clg Cfm/Ton	1391.15	Plenum	72.0	68.0
Aux Htg	0.0	0	0.0	0.0	Supply	129,529	129,529	Clg Sqft/Ton	393.27	Return	72.0	62.5
Preheat	-5,449.0	129,529	13.6	64.8	Mincfm	0	0	Clg Btuh/Sqft	30.51	Ret/OA	84.8	14.4
Reheat	0.0	0	0.0	0.0	Return	19,394	129,529	No. People	0	Runarnd	72.0	68.0
Humidif	0.0	0	0.0	0.0	Exhaust	0	110,135	Htg % OA	85.0	Fn MtrTD	0.5	0.0
Vent	0.0	0	0.0	0.0	Rm Exh	110,135	0	Htg Cfm/Sqft	3.54	Fn BldTD	0.4	0.0
	-5,328.2				Auxil	0	0	Htg Btuh/Sqft	-145.51	Fn Frict	1.1	0.0

-----AIRFLOWS (cfm)-----

-----ENGINEERING CHECKS-----

-----TEMPERATURES (F)-----

22 OF 89

Trane Air Conditioning Economics
By: Trane Customer Direct Service Network

V 600
PAGE 6

stem 3 Peak SZ - SINGLE ZONE

***** COOLING COIL PEAK ***** CLG SPACE PEAK ***** HEATING COIL PEAK *****

Peaked at Time ==> Mo/Hr: 7/15 * Mo/Hr: 6/14 * Mo/Hr: 13/ 1
Outside Air ==> OADB/WB/HR: 87/ 60/ 63.0 * OADB: 89 * OADB: 5

	Space Sens.+Lat. (Btuh)	Ret. Air Sensible (Btuh)	Ret. Air Latent (Btuh)	Net Total (Btuh)	Percnt Of Tot (%)		Space Sensible (Btuh)	Percnt Of Tot (%)		Space Peak Space Sens (Btuh)	Coil Peak Tot Sens (Btuh)	Percnt Of Tot (%)
Envelope Loads												
Skylite Solr	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Skylite Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Roof Cond	11,334	0		11,334	4.28	*	11,666	10.85	*	-7,469	-7,469	1.97
Glass Solar	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Glass Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Wall Cond	20,287	0		20,287	7.66	*	21,322	19.83	*	-32,744	-32,744	8.62
Partition	0			0	0.00	*	0	0.00	*	0	0	0.00
Exposed Floor	0			0	0.00	*	0	0.00	*	-800	-800	0.21
Infiltration	0			0	0.00	*	0	0.00	*	0	0	0.00
Sub Total==>	31,621	0		31,621	11.95	*	32,988	30.68	*	-41,014	-41,014	10.80
Internal Loads												
Lights	44,715	0		44,715	16.89	*	44,715	41.59	*	0	0	0.00
People	0			0	0.00	*	0	0.00	*	0	0	0.00
Misc	29,810	0	0	29,810	11.26	*	29,810	27.73	*	0	0	0.00
Sub Total==>	74,525	0	0	74,525	28.16	*	74,525	69.32	*	0	0	0.00
Ceiling Load	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Outside Air	0	0	0	90,136	34.05	*	0	0.00	*	0	-338,867	89.20
Coil Fan Heat				26,071	9.85	*		0.00	*		0	0.00
Coil Fan Heat		42,340		42,340	16.00	*		0.00	*		0	0.00
Duct Heat PkUp		0		0	0.00	*		0.00	*		0	0.00
OV/UNDR Sizing	0			0	0.00	*	0	0.00	*	0	0	0.00
Exhaust Heat		0	0	0	-0.00	*		0.00	*		0	0.00
Terminal Bypass		0	0	0	0.00	*		0.00	*		0	0.00
Grand Total==>	106,146	42,340	0	264,692	100.00	*	107,513	100.00	*	-41,014	-379,881	100.00

-----COOLING COIL SELECTION-----										-----AREAS-----		
	Total Capacity (Tons)	Sens Cap. (Mbh)	Coil Airfl (cfm)	Entering DB/WB/HR			Leaving DB/WB/HR			Gross Total	Glass (sf)	(%)
				Deg F	Deg F	Grains	Deg F	Deg F	Grains	Floor		
Main Clg	22.1	264.7	233.7	13,094	85.4	58.9	58.4	63.6	50.7	54.0	Part	4,367
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	ExFlr	127
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Roof	1,867
Totals	22.1	264.7									Wall	1,575

-----HEATING COIL SELECTION-----					-----AIRFLOWS (cfm)-----			--ENGINEERING CHECKS--		--TEMPERATURES (F)---		
	Capacity (Mbh)	Coil Airfl (cfm)	Ent Deg F	Lvg Deg F	Type	Cooling	Heating	Clg % OA	50.0	Type	Clg	Htg
					Vent	6,551	6,551	Clg Cfm/Sqft	3.00	SADB	66.0	71.8
Main Htg	-379.9	13,094	36.5	71.8	Infil	0	0	Clg Cfm/Ton	593.60	Plenum	76.0	68.0
Aux Htg	0.0	0	0.0	0.0	Supply	13,094	13,094	Clg Sqft/Ton	197.99	Return	83.9	68.0
Preheat	-291.3	13,094	36.5	63.6	Mincfm	0	0	Clg Btuh/Sqft	60.61	Ret/OA	85.4	36.5
Reheat	0.0	0	0.0	0.0	Return	6,543	13,094	No. People	0	Runarnd	76.0	68.0
Midif	0.0	0	0.0	0.0	Exhaust	0	6,551	Htg % OA	50.0	Fn MtrTD	0.6	0.0
Vent	0.0	0	0.0	0.0	Rm Exh	6,551	0	Htg Cfm/Sqft	3.00	Fn BldTD	0.5	0.0
!	-379.9				Auxil	0	0	Htg Btuh/Sqft	-86.99	Fn Frict	1.4	0.0

Trane Air Conditioning Economics
By: Trane Customer Direct Service Network

V 600
PAGE 7

System 4 Peak SZ - SINGLE ZONE

***** COOLING COIL PEAK ***** CLG SPACE PEAK ***** HEATING COIL PEAK *****

Peaked at Time ==> Mo/Hr: 7/15 * Mo/Hr: 6/15 * Mo/Hr: 13/ 1
Outside Air ==> OADB/WB/HR: 87/ 60/ 63.0 * OADB: 90 * OADB: 5

	Space	Ret. Air	Ret. Air	Net	Percnt		Space	Percnt		Space Peak	Coil Peak	Percnt
	Sens.+Lat.	Sensible	Latent	Total	Of Tot		Sensible	Of Tot		Space Sens	Tot Sens	Of Tot
	(Btuh)	(Btuh)	(Btuh)	(Btuh)	(%)		(Btuh)	(%)		(Btuh)	(Btuh)	(%)
Envelope Loads												
Skylite Solr	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Skylite Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Roof Cond	172,010	0		172,010	8.97	*	179,567	25.85	*	-113,354	-113,354	2.96
Glass Solar	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Glass Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Wall Cond	30,800	0		30,800	1.61	*	31,427	4.52	*	-56,407	-56,407	1.47
Partition	0			0	0.00	*	0	0.00	*	0	0	0.00
Exposed Floor	0			0	0.00	*	0	0.00	*	0	0	0.00
Infiltration	0			0	0.00	*	0	0.00	*	0	0	0.00
Sub Total==>	202,810	0		202,810	10.57	*	210,994	30.38	*	-169,761	-169,761	4.43
Internal Loads						*			*			
Lights	290,122	0		290,122	15.12	*	290,122	41.77	*	0	0	0.00
People	0			0	0.00	*	0	0.00	*	0	0	0.00
Misc	193,415	0	0	193,415	10.08	*	193,415	27.85	*	0	0	0.00
Sub Total==>	483,537	0	0	483,537	25.20	*	483,537	69.62	*	0	0	0.00
Ceiling Load	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Outside Air	0	0	0	974,716	50.81	*	0	0.00	*	0	-3,664,437	95.57
.. Fan Heat				168,416	8.78	*		0.00	*		0	0.00
.. Fan Heat		88,955		88,955	4.64	*		0.00	*		0	0.00
Duct Heat Pkup		0		0	0.00	*		0.00	*		0	0.00
OV/UNDR Sizing	0			0	0.00	*	0	0.00	*	0	0	0.00
Exhaust Heat		0	0	0	0.00	*		0.00	*		0	0.00
Terminal Bypass		0	0	0	0.00	*		0.00	*		0	0.00
Grand Total==>	686,347	88,955	0	1,918,434	100.00	*	694,531	100.00	*	-169,761	-3,834,199	100.00

-----COOLING COIL SELECTION-----

	Total Capacity	Sens Cap.	Coil Airfl	Entering DB/WB/HR			Leaving DB/WB/HR			Gross Total	Glass (sf)	(%)
	(Tons)	(Mbh)	(Mbh)	(cfm)	Deg F	Deg F	Grains	Deg F	Deg F	Grains	Floor	
Main Clg	159.9	1,918.4	1,583.5	84,584	86.5	59.8	61.5	63.6	50.7	54.0	Part	0
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	ExFlr	0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Roof	28,335
Totals	159.9	1,918.4									Wall	14,100

-----AREAS-----

-----HEATING COIL SELECTION-----

	Capacity	Coil Airfl	Ent	Lvg	Type	Cooling	Heating	Clg % OA	83.7	Type	Clg	Htg
	(Mbh)	(cfm)	Deg F	Deg F	Vent	70,837	70,837	Clg Cfm/Sqft	2.99	SADB	66.0	70.4
Main Htg	-3,834.2	84,584	15.2	70.4	Infil	0	0	Clg Cfm/Ton	529.08	Plenum	76.0	68.0
Aux Htg	0.0	0	0.0	0.0	Supply	84,584	84,584	Clg Sqft/Ton	177.24	Return	83.9	68.0
Preheat	-3,357.1	84,584	15.2	63.6	Mincfm	0	0	Clg Btuh/Sqft	67.71	Ret/OA	86.5	15.2
Reheat	0.0	0	0.0	0.0	Return	13,746	84,584	No. People	0	Runarnd	76.0	68.0
Humidif	0.0	0	0.0	0.0	Exhaust	0	70,837	Htg % OA	83.7	Fn MtrTD	0.6	0.0
Orn Vent	0.0	0	0.0	0.0	Rm Exh	70,837	0	Htg Cfm/SqFt	2.99	Fn BldTD	0.5	0.0
	-3,834.2				Auxil	0	0	Htg Btuh/SqFt	-135.32	Fn Frict	1.4	0.0

-----AIRFLOWS (cfm)-----

-----ENGINEERING CHECKS-----

-----TEMPERATURES (F)-----

24 OF 89

Trane Air Conditioning Economics
By: Trane Customer Direct Service Network

V 600
PAGE 8

System 5 Peak SZ - SINGLE ZONE

***** COOLING COIL PEAK ***** CLG SPACE PEAK ***** HEATING COIL PEAK *****

Peaked at Time ==> Mo/Hr: 7/15 * Mo/Hr: 6/16 * Mo/Hr: 13/ 1
Outside Air ==> OADB/WB/HR: 87/ 60/ 63.0 * OADB: 89 * OADB: 5

	Space	Ret. Air	Ret. Air	Net	Perct		Space	Perct		Space Peak	Coil Peak	Perct
	Sens.+Lat.	Sensible	Latent	Total	Of Tot		Sensible	Of Tot		Space Sens	Tot Sens	Of Tot
	(Btuh)	(Btuh)	(Btuh)	(Btuh)	(%)		(Btuh)	(%)		(Btuh)	(Btuh)	(%)
Envelope Loads												
Skylite Solr	0	0		0	0.00		0	0.00		0	0	0.00
Skylite Cond	0	0		0	0.00		0	0.00		0	0	0.00
Roof Cond	172,010	0		172,010	11.31		170,031	24.01		-113,354	-113,354	13.09
Glass Solar	0	0		0	0.00		0	0.00		0	0	0.00
Glass Cond	0	0		0	0.00		0	0.00		0	0	0.00
Wall Cond	41,571	0		41,571	2.73		54,454	7.69		-83,673	-83,673	9.66
Partition	0			0	0.00		0	0.00		0	0	0.00
Exposed Floor	0			0	0.00		0	0.00		0	0	0.00
Infiltration	0			0	0.00		0	0.00		0	0	0.00
Sub Total==>	213,581	0		213,581	14.04		224,485	31.71		-197,027	-197,027	22.75
Internal Loads												
Lights	290,122	0		290,122	19.07		290,122	40.98		0	0	0.00
People	0			0	0.00		0	0.00		0	0	0.00
Misc	193,415	0	0	193,415	12.72		193,415	27.32		0	0	0.00
Sub Total==>	483,537	0	0	483,537	31.79		483,537	68.29		0	0	0.00
Driving Load	0	0		0	0.00		0	0.00		0	0	0.00
Outside Air	0	0	0	177,971	11.70		0	0.00		0	-669,080	77.25
Coil Fan Heat				171,687	11.29			0.00			0	0.00
Coil Fan Heat		474,286		474,286	31.18			0.00			0	0.00
Duct Heat PkUp		0		0	0.00			0.00			0	0.00
OV/UNDR Sizing	0			0	0.00		0	0.00		0	0	0.00
Exhaust Heat		0	0	0	0.00			0.00			0	0.00
Terminal Bypass		0	0	0	0.00			0.00			0	0.00
Grand Total==>	697,118	474,286	0	1,521,062	100.00		708,021	100.00		-197,027	-866,107	100.00

-----COOLING COIL SELECTION-----

	Total Capacity	Sens Cap.	Coil Airfl	Entering DB/WB/HR	Leaving DB/WB/HR	Gross Total	Glass (sf)	(%)
	(Tons)	(Mbh)	(cfm)	Deg F Deg F Grains	Deg F Deg F Grains	Floor		
Main Clg	126.8	1,521.1	1,459.9	86,227 84.3 58.0 55.2	63.6 50.7 54.0	28,335		
Aux Clg	0.0	0.0	0.0	0 0.0 0.0 0.0	0.0 0.0 0.0	0		
Opt Vent	0.0	0.0	0.0	0 0.0 0.0 0.0	0.0 0.0 0.0	0		
Totals	126.8	1,521.1				28,335		

-----AREAS-----

-----HEATING COIL SELECTION-----					-----AIRFLOWS (cfm)-----			--ENGINEERING CHECKS--		--TEMPERATURES (F)---		
Capacity	Coil Airfl	Ent	Lvg	Type	Cooling	Heating	Clg % OA	15.0	Type	Clg	Htg	
(Mbh)	(cfm)	Deg F	Deg F	Vent	12,934	12,934	Clg Cfm/Sqft	3.04	SADB	66.0	70.8	
Main Htg	-866.1	86,227	58.5	70.8	Infil	0	0	Clg Cfm/Ton	680.26	Plenum	76.0	68.0
Aux Htg	0.0	0	0.0	0.0	Supply	86,227	86,227	Clg Sqft/Ton	223.54	Return	83.9	68.0
Preheat	-355.8	86,227	58.5	63.6	Mincfm	0	0	Clg Btuh/Sqft	53.68	Ret/OA	84.3	58.5
Reheat	0.0	0	0.0	0.0	Return	73,293	86,227	No. People	0	Runarnd	76.0	68.0
idif	0.0	0	0.0	0.0	Exhaust	0	12,934	Htg % OA	15.0	Fn MtrTD	0.6	0.0
Opt Vent	0.0	0	0.0	0.0	Rm Exh	12,934	0	Htg Cfm/Sqft	3.04	Fn BldTD	0.5	0.0
!	-866.1				Auxil	0	0	Htg Btuh/Sqft	-30.57	Fn Frict	1.4	0.0

stem 6 Peak SZ - SINGLE ZONE

***** COOLING COIL PEAK ***** CLG SPACE PEAK ***** HEATING COIL PEAK *****

Peaked at Time ==> Mo/Hr: 7/15 * Mo/Hr: 6/15 * Mo/Hr: 13/ 1
 Outside Air ==> OADB/WB/HR: 87/ 60/ 63.0 * OADB: 90 * OADB: 5

	Space	Ret. Air	Ret. Air	Net	Perct		Space	Perct		Space Peak	Coil Peak	Perct
	Sens.+Lat.	Sensible	Latent	Total	Of Tot		Sensible	Of Tot		Space Sens	Tot Sens	Of Tot
	(Btuh)	(Btuh)	(Btuh)	(Btuh)	(%)		(Btuh)	(%)		(Btuh)	(Btuh)	(%)
Envelope Loads												
Skylite Solr	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Skylite Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Roof Cond	46,331	0		46,331	10.52	*	48,366	24.65	*	-30,532	-30,532	12.18
Glass Solar	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Glass Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Wall Cond	16,647	0		16,647	3.78	*	17,620	8.98	*	-32,269	-32,269	12.87
Partition	0			0	0.00	*	0	0.00	*	0	0	0.00
Exposed Floor	0			0	0.00	*	0	0.00	*	-2,507	-2,507	1.00
Infiltration	0			0	0.00	*	0	0.00	*	0	0	0.00
Sub Total==>	62,977	0		62,977	14.30	*	65,986	33.63	*	-65,308	-65,308	26.05
Internal Loads						*			*			
Lights	78,144	0		78,144	17.75	*	78,144	39.82	*	0	0	0.00
People	0			0	0.00	*	0	0.00	*	0	0	0.00
Misc	52,096	0	0	52,096	11.83	*	52,096	26.55	*	0	0	0.00
Sub Total==>	130,240	0	0	130,240	29.58	*	130,240	66.37	*	0	0	0.00
Ceiling Load	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Outside Air	0	0	0	49,324	11.20	*	0	0.00	*	0	-185,434	73.95
Outside Fan Heat				66,276	15.05	*		0.00	*		0	0.00
Outside Fan Heat		131,447		131,447	29.86	*		0.00	*		0	0.00
Duct Heat PkUp		0		0	0.00	*		0.00	*		0	0.00
OV/UNDR Sizing	0			0	0.00	*	0	0.00	*	0	0	0.00
Exhaust Heat		0	0	0	-0.00	*		0.00	*		0	0.00
Terminal Bypass		0	0	0	0.00	*		0.00	*		0	0.00
Grand Total==>	193,217	131,447	0	440,264	100.00	*	196,226	100.00	*	-65,308	-250,742	100.00

-----COOLING COIL SELECTION-----

	Total Capacity	Sens Cap.	Coil Airfl	Entering DB/WB/HR			Leaving DB/WB/HR			Gross Total	Glass (sf)	(%)
	(Tons)	(Mbh)	(Mbh)	(cfm)	Deg F	Deg F	Grains	Deg F	Deg F	Grains	Floor	
Main Clg	36.7	440.3	423.3	23,898	84.3	58.0	55.2	62.6	50.4	54.0	Part	0
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	ExFlr	398
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Roof	7,632
Totals	36.7	440.3									Wall	9,850

-----AREAS-----

-----HEATING COIL SELECTION-----

	Capacity	Coil Airfl	Ent	Lvg	Type	Cooling	Heating	Clg % OA	15.0	Type	Clg	Htg
	(Mbh)	(cfm)	Deg F	Deg F	Vent	3,585	3,585	Clg Cfm/Sqft	3.13	SADB	66.0	71.3
Main Htg	-250.7	23,898	58.6	71.3	Infil	0	0	Clg Cfm/Ton	651.36	Plenum	76.0	68.0
Aux Htg	0.0	0	0.0	0.0	Supply	23,898	23,898	Clg Sqft/Ton	208.02	Return	83.9	68.0
Preheat	-79.9	23,898	58.6	62.6	Mincfm	0	0	Clg Btuh/Sqft	57.69	Ret/OA	84.3	58.6
Reheat	0.0	0	0.0	0.0	Return	20,313	23,898	No. People	0	Runarnd	76.0	68.0
Humidif	0.0	0	0.0	0.0	Exhaust	0	3,585	Htg % OA	15.0	Fn MtrTD	0.8	0.0
Vent	0.0	0	0.0	0.0	Rm Exh	3,585	0	Htg Cfm/SqFt	3.13	Fn BldTD	0.6	0.0
:	-250.7				Auxil	0	0	Htg Btuh/SqFt	-32.85	Fn Frict	1.9	0.0

-----AIRFLOWS (cfm)-----

-----ENGINEERING CHECKS-----

-----TEMPERATURES (F)-----

stem 7 Peak SZ - SINGLE ZONE

***** COOLING COIL PEAK ***** CLG SPACE PEAK ***** HEATING COIL PEAK *****

Peaked at Time ==> Mo/Hr: 7/15 * Mo/Hr: 6/16 * Mo/Hr: 13/ 1
 Outside Air ==> OADB/WB/HR: 87/ 60/ 63.0 * OADB: 89 * OADB: 5

	Space	Ret. Air	Ret. Air	Net	Perct		Space	Perct		Space Peak	Coil Peak	Perct
	Sens.+Lat.	Sensible	Latent	Total	Of Tot		Sensible	Of Tot		Space Sens	Tot Sens	Of Tot
	(Btuh)	(Btuh)	(Btuh)	(Btuh)	(%)		(Btuh)	(%)		(Btuh)	(Btuh)	(%)
Envelope Loads												
Skylite Solr	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Skylite Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Roof Cond	27,536	0		27,536	25.73	*	27,222	22.87	*	-17,958	-17,958	8.23
Glass Solar	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Glass Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Wall Cond	13,117	0		13,117	12.26	*	15,206	12.77	*	-24,376	-24,376	11.17
Partition	0			0	0.00	*	0	0.00	*	0	0	0.00
Exposed Floor	0			0	0.00	*	0	0.00	*	-1,688	-1,688	0.77
Infiltration	0			0	0.00	*	0	0.00	*	0	0	0.00
Sub Total==>	40,653	0		40,653	37.99	*	42,429	35.64	*	-44,023	-44,023	20.18
Internal Loads												
Lights	45,963	0		45,963	42.96	*	45,963	38.61	*	0	0	0.00
People	0			0	0.00	*	0	0.00	*	0	0	0.00
Misc	30,642	0	0	30,642	28.64	*	30,642	25.74	*	0	0	0.00
Sub Total==>	76,605	0	0	76,605	71.59	*	76,605	64.36	*	0	0	0.00
Ceiling Load	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Outside Air	0	0	0	-10,256	-9.58	*	0	0.00	*	0	-174,163	79.82
.. Fan Heat				0	0.00	*		0.00	*		0	0.00
.. Fan Heat		0		0	0.00	*		0.00	*		0	0.00
Duct Heat PkUp		0		0	0.00	*		0.00	*		0	0.00
OV/UNDR Sizing	0			0	0.00	*	0	0.00	*	0	0	0.00
Exhaust Heat		0	0	0	0.00	*		0.00	*		0	0.00
Terminal Bypass		0	0	0	0.00	*		0.00	*		0	0.00
Grand Total==>	117,258	0	0	107,002	100.00	*	119,033	100.00	*	-44,023	-218,186	100.00

-----COOLING COIL SELECTION-----											-----AREAS-----		
	Total Capacity	Sens Cap.	Coil Airfl	Entering DB/WB/HR			Leaving DB/WB/HR				Gross Total	Glass (sf)	(%)
	(Tons)	(Mbh)	(Mbh)	(cfm)	Deg F	Deg F	Grains	Deg F	Deg F	Grains	Floor		
Main Clg	8.9	107.0	150.4	14,497	77.8	61.0	82.2	65.0	58.3	88.2	Part	0	
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	ExFlr	268	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Roof	4,489	0 0
Totals	8.9	107.0									Wall	6,700	0 0

-----HEATING COIL SELECTION-----					-----AIRFLOWS (cfm)-----			--ENGINEERING CHECKS--		--TEMPERATURES (F)--		
	Capacity	Coil Airfl	Ent	Lvg	Type	Cooling	Heating	Clg % OA	23.2	Type	Clg	Htg
	(Mbh)	(cfm)	Deg F	Deg F	Vent	3,367	3,367	Clg Cfm/Sqft	3.23	SADB	65.0	71.7
Main Htg	-218.2	14,497	53.4	71.7	Infil	0	0	Clg Cfm/Ton	1625.76	Plenum	75.0	68.0
Aux Htg	0.0	0	0.0	0.0	Supply	14,497	14,497	Clg Sqft/Ton	503.43	Return	75.0	68.0
Preheat	-138.5	14,497	53.4	65.0	Mincfm	0	0	Clg Btuh/Sqft	23.84	Ret/OA	77.8	53.4
Reheat	0.0	0	0.0	0.0	Return	11,130	14,497	No. People	0	Runarnd	75.0	68.0
Humidif	0.0	0	0.0	0.0	Exhaust	0	3,367	Htg % OA	23.2	Fn MtrTD	0.0	0.0
Vent	0.0	0	0.0	0.0	Rm Exh	3,367	0	Htg Cfm/SqFt	3.23	Fn BldTD	0.0	0.0
'	-218.2				Auxil	0	0	Htg Btuh/SqFt	-48.60	Fn Frict	0.0	0.0

System 8 Peak SZ - SINGLE ZONE

***** COOLING COIL PEAK ***** CLG SPACE PEAK ***** HEATING COIL PEAK *****

Peaked at Time ==> Mo/Hr: 7/15 * Mo/Hr: 6/15 * Mo/Hr: 13/ 1
Outside Air ==> OADB/WB/HR: 87/ 60/ 63.0 * OADB: 90 * OADB: 5

	Space	Ret. Air	Ret. Air	Net	Percnt		Space	Percnt		Space Peak	Coil Peak	Percnt
	Sens.+Lat.	Sensible	Latent	Total	Of Tot		Sensible	Of Tot		Space Sens	Tot Sens	Of Tot
	(Btuh)	(Btuh)	(Btuh)	(Btuh)	(%)		(Btuh)	(%)		(Btuh)	(Btuh)	(%)
Envelope Loads												
Skylite Solr	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Skylite Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Roof Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Glass Solar	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Glass Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Wall Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Partition	0			0	0.00	*	0	0.00	*	0	0	0.00
Exposed Floor	0			0	0.00	*	0	0.00	*	0	0	0.00
Infiltration	0			0	0.00	*	0	0.00	*	0	0	0.00
Sub Total==>	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Internal Loads												
Lights	13,410	0		13,410	24.39	*	13,410	55.83	*	0	0	0.00
People	1,020			1,020	1.85	*	510	2.12	*	0	0	0.00
Misc	8,940	0	0	8,940	16.26	*	8,940	37.22	*	0	0	0.00
Sub Total==>	23,370	0	0	23,370	42.50	*	22,860	95.17	*	0	0	0.00
Ceiling Load	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Outside Air	0	0	0	24,090	43.81	*	0	0.00	*	0	-101,628	100.00
Room Fan Heat				5,725	10.41	*		0.00	*		0	0.00
Supply Fan Heat		646		646	1.17	*		0.00	*		0	0.00
Duct Heat PkUp		0		0	0.00	*		0.00	*		0	0.00
OV/UNDR Sizing	1,161			1,161	2.11	*	1,161	4.83	*	0	0	0.00
Exhaust Heat		0	0	0	0.00	*		0.00	*		0	0.00
Terminal Bypass		0	0	0	0.00	*		0.00	*		0	0.00
Grand Total==>	24,532	646	0	54,993	100.00	*	24,022	100.00	*	0	-101,628	100.00

-----COOLING COIL SELECTION-----										-----AREAS-----		
	Total Capacity	Sens Cap.	Coil Airfl	Entering DB/WB/HR			Leaving DB/WB/HR			Gross Total	Glass (sf)	(%)
	(Tons)	(Mbh)	(cfm)	Deg F	Deg F	Grains	Deg F	Deg F	Grains	Floor		
Main Clg	4.6	55.0	2,064	86.7	60.1	63.0	54.5	49.3	62.5	Part	0	
Aux Clg	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	ExFlr	0	
Opt Vent	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Roof	0	0 0
Totals	4.6	55.0								Wall	0	0 0

-----HEATING COIL SELECTION-----					-----AIRFLOWS (cfm)-----			--ENGINEERING CHECKS--		--TEMPERATURES (F)--		
Capacity	Coil Airfl	Ent	Lvg	Type	Cooling	Heating		Clg % OA		Type	Clg	Htg
(Mbh)	(cfm)	Deg F	Deg F					Clg Cfm/Sqft				
Main Htg	-101.8	2,064	8.0	Infil	1,965	0	0	450.47	95.2	SADB	57.8	68.1
Aux Htg	0.0	0	0.0	Supply	2,064	2,064	0	285.79	1.58	Plenum	72.0	68.0
Preheat	-78.7	2,064	8.0	Mincfm	0	0	0	41.99		Return	79.9	68.0
Reheat	0.0	0	0.0	Return	100	2,064	0	2		Ret/OA	86.7	8.0
idif	0.0	0	0.0	Exhaust	0	1,965	0	Htg % OA	95.2	Runrnd	72.0	68.0
.. Vent	0.0	0	0.0	Rm Exh	1,965	0	0	Htg Cfm/SqFt	1.58	Fn MtrTD	0.8	0.0
!	-101.8			Auxil	0	0	0	Htg Btuh/SqFt	-77.72	Fn Frict	1.9	0.0

Trane Air Conditioning Economics
By: Trane Customer Direct Service Network

V 600
PAGE 12

Item 9 Peak SZ - SINGLE ZONE

***** COOLING COIL PEAK ***** CLG SPACE PEAK ***** HEATING COIL PEAK *****

Peaked at Time ==>		Mo/Hr: 7/15		*		Mo/Hr: 6/17		*		Mo/Hr: 13/ 1		
Outside Air ==>		OADB/WB/HR: 87/ 60/ 63.0		*		OADB: 87		*		OADB: 5		
				*				*				
	Space	Ret. Air	Ret. Air	Net	Perct	*	Space	Perct	*	Space Peak	Coil Peak	Perct
	Sens.+Lat.	Sensible	Latent	Total	Of Tot	*	Sensible	Of Tot	*	Space Sens	Tot Sens	Of Tot
	(Btuh)	(Btuh)	(Btuh)	(Btuh)	(%)	*	(Btuh)	(%)	*	(Btuh)	(Btuh)	(%)
Envelope Loads						*			*			
Skylite Solr	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Skylite Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Roof Cond	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Glass Solar	89,280	0		89,280	18.11	*	116,352	41.58	*	0	0	0.00
Glass Cond	4,323	0		4,323	0.88	*	4,448	1.59	*	-19,005	-19,005	5.24
Wall Cond	10,597	0		10,597	2.15	*	15,074	5.39	*	-13,153	-13,153	3.63
Partition	0			0	0.00	*	0	0.00	*	0	0	0.00
Exposed Floor	0			0	0.00	*	0	0.00	*	0	0	0.00
Infiltration	0			0	0.00	*	0	0.00	*	0	0	0.00
Sub Total==>	104,200	0		104,200	21.14	*	135,874	48.56	*	-32,158	-32,158	8.87
Internal Loads						*			*			
Lights	86,371	0		86,371	17.52	*	86,371	30.87	*	0	0	0.00
People	0			0	0.00	*	0	0.00	*	0	0	0.00
Misc	57,580	0	0	57,580	11.68	*	57,580	20.58	*	0	0	0.00
Sub Total==>	143,951	0	0	143,951	29.20	*	143,951	51.44	*	0	0	0.00
Ceiling Load	0	0		0	0.00	*	0	0.00	*	0	0	0.00
Outside Air	0	0	0	128,815	26.13	*	0	0.00	*	0	-330,559	91.13
Outside Fan Heat				104,205	21.14	*		0.00	*		0	0.00
Inside Fan Heat		11,825		11,825	2.40	*		0.00	*		0	0.00
Duct Heat PkUp		0		0	0.00	*		0.00	*		0	0.00
OV/UNDR Sizing	0			0	0.00	*	0	0.00	*	0	0	0.00
Exhaust Heat		0	0	0	-0.00	*		0.00	*		0	0.00
Terminal Bypass		0	0	0	0.00	*		0.00	*		0	0.00
						*			*			
Grand Total==>	248,151	11,825	0	492,996	100.00	*	279,825	100.00	*	-32,158	-362,717	100.00

-----COOLING COIL SELECTION-----

	Total Capacity	Sens Cap.	Coil Airfl	Entering DB/WB/HR			Leaving DB/WB/HR			Gross Total	Glass (sf)	(%)
	(Tons)	(Mbh)	(Mbh)	(cfm)	Deg F	Deg F	Grains	Deg F	Deg F	Grains	Floor	
Main Clg	41.1	493.0	441.8	34,079	75.2	53.9	49.9	58.3	47.5	48.6	Part	0
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	ExFlr	0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Roof	0
Totals	41.1	493.0									Wall	3,780
												576
												15

-----HEATING COIL SELECTION-----

Capacity	Coil Airfl	Ent	Lvg	Type	Cooling	Heating	Clg % OA	18.7	Type	Clg	Htg
(Mbh)	(cfm)	Deg F	Deg F	Vent	6,364	6,364	Clg Cfm/Sqft	4.04	SADB	62.0	69.5
Main Htg	-362.7	34,079	56.5	69.5	Infil	0	Clg Cfm/Ton	829.51	Plenum	72.0	68.0
Aux Htg	0.0	0	0.0	0.0	Supply	34,079	Clg Sqft/Ton	205.33	Return	72.5	68.3
Preheat	-49.8	34,079	56.5	58.3	Mincfm	0	Clg Btuh/Sqft	58.44	Ret/OA	75.2	56.5
Reheat	0.0	0	0.0	0.0	Return	27,715	No. People	0	Runarnd	72.0	68.0
Indif	0.0	0	0.0	0.0	Exhaust	0	Htg % OA	18.7	Fn MtrTD	0.9	0.0
Vent	0.0	0	0.0	0.0	Rm Exh	6,364	Htg Cfm/SqFt	4.04	Fn BldTD	0.7	0.0
!	-362.7				Auxil	0	Htg Btuh/SqFt	-43.00	Fn Frict	2.1	0.0

-----AIRFLOWS (cfm)-----

-----ENGINEERING CHECKS-----

-----TEMPERATURES (F)-----

SYSTEM #1 - SUPPLY AIR

DESIGNED BY CLP DATE 3/9/93

CHECKED BY TJT DATE 3/15/93

AIR FLOW IS 31,585 CFM

1. DUCT SIZE @ 500 FPM ; 31,585 CFM
= 64 SF FACE AREA X 2 = 128 SF

2. FILTERS SIZE AT 300 FPM ; 31,585 CFM =
105 SF OR 26 24" X 24" X 2" A FILTER BANK 3 HIGH X
9 WIDE

3. PRE HEAT COIL SIZE @ 600 FPM ; 31,585 = 53 SF

4. COOLING COIL SIZE AT 500 FPM 31,585 = 64 SF

5. SUPPLY AIR FAN SIZE @ 31,585 CFM 2.98" TSP
@ SEA LEVEL OR 2.1" TSP @ 7500 FT - BUFFALO
TYPE BL-1080

6. VAV TERMINAL - ESTIMATE 1000 CFM EACH ; @
31,585 CFM : ESTIMATED # = 31 UNITS WITH
HEATING COIL.

7. DIFFUSER - ESTIMATE 400 CFM EACH ; @
31,585 CFM - ESTIMATED # = 79 DIFFUSERS
12" X 12" EA.

SYSTEM # 1 - RETURN AIR

DESIGNED BY CLP

DATE 3/9/93

CHECKED BY TT

DATE 3/15/93

1. RETURN AIR REGISTERS - ESTIMATE 800 CFM
EACH : AT 31,585 CFM ESTIMATED # = 42
REGISTERS 24" X 12".

2. RETURN AIR PAN - SIZE FOR 31,585 CFM
AT .66" TSP @ SEA LEVEL OR .46 TSP
@ 7500 FT. BUFFALO TYPE BL-980

SYSTEM #2. - SUPPLY AIR

DESIGNED BY

TJT

DATE 2/13/84

CHECKED BY

CLD

DATE 3/14/84

AIR FLOW IS 130,000 CFM WHICH IS TWICE
THE AIR FLOW OF SYSTEM #1.

1. LOUVER SIZE = $2 \times 264.5F = 528.5F$

2. FILTERS SIZE = $55 \times 2 = 110 = 24" \times 24" \times 12"$

TWO FILTER BANKS OF 5 HIGH & 11 WIDE.

3. HEATING COIL SIZE = $2 \times 110.5F = 220.5F$

4. COOLING COIL SIZE = $2 \times 132.5F = 264.5F$

5. SUPPLY AIR FAN SIZE AT 130,000

CFM & 7.37" TSP AT SEA LEVEL

OR 5.60" TSP AT 7500 FT.

SELECT TWO - 65,000 CFM

BUFFALO TYPE BL-1320

6. DIFFUSERS - 2×165 DIFFUSER

= 330 DIFFUSERS 12" X 12" NK

7. Foul Heat Recovery Coils SIZE FOR 700 PPM
@ 65,000 CFM = 925F ea

SYSTEM #2 - EXHAUST AIR
ZONK #2

DESIGNED BY TJ

DATE 2/13/9

CHECKED BY CLD

DATE 3/19/9

1. EXHAUST AIR REGISTER - 2 X 83 REGISTER
= 166 REGISTER.

2. CLEAN AIR FILTER TRAIN 1ST STAGE
2 X 72 = 144 FILTER TOTAL
EIGHT BANKS 3 HIGH X 6 WIDE

3. CLEAN AIR FILTER TRAIN 2ND STAGE
SAME AS "2" ABOVE

4. CLEAN AIR FILTER TRAIN 2ND STAGE
RETURN AIR - 1/2 OR FOUR FILTER
BANKS 3 HIGH X 6 WIDE
TOTAL OF 72 HEPA FILTERS,

5. RETURN AIR FAN SIZE FOR
FOR 65,000 CFM AT 9.09" TSP
AT SEA LEVEL OR 6.9" TSP AT 7500 FT
BUFFALO TYPE BL-1320

6. STACK SIZE AT 130,000 CFM
AT 3200 FPM = 86" DIAMETER.

7. EXHAUST AIR FAN SIZE FOR 130,000 CFM
AT 9.28" TSP AT SEA LEVEL OR 6.9" TSP

SYSTEM #2 - EXHAUST AIR
ZONE #1

DESIGNED BY TJ

DATE 2/13/72

CHECKED BY CLQ

DATE 3/14/72

1. ESTIMATE TANK & PROCESS EQUIPMENT NEEDS 16,000 CFM EXHAUST AIR
2. CLEAN AIR TRAIN ZONE #1, 1ST STAGE
16,000 CFM USE 18-24" X 24" X 12"
HEPA FILTERS
3. CLEAN AIR TRAIN ZONE #1, 2ND STAGE
SAME AS "2" ABOVE.
4. EXHAUST AIR FAN SIZE FOR 16,000 CFM
AT 12.75" TSP AT SEA LEVEL
OR 9.7" TSP AT 7500 FT.
BUFFALO TYPE BL-730

5. STACK SIZE AT 16,000 CFM AT
3200 RPM = 30 DIAMETER ✓
OR 42" DIAMETER FOR 32,000 CFM. ✓

SYSTEM #3 - SUPPLY AIR

DESIGNED BY TTT DATE 2/14/99

CHECKED BY CLQ DATE 3/16/99

1. LOUVER SIZE AT 500 FPM $\frac{1}{2}$ 14,000 CFM
= 28 SF FREE AREA X 2 = 56 SF

2. FILTERS SIZE AT 300 FPM $\frac{1}{2}$
14,000 CFM = 47 SF OR 12-24" X 24"
A FILTER BANK 3 HIGH X 4 WIDE
OR 6' HIGH X 8' WIDE ✓

3. HEATING COIL SIZE AT 600 FPM $\frac{1}{2}$
14,000 CFM = 24 SF ✓

4. COOLING COIL SIZE AT 500 FPM
14,000 CFM = 28 SF ✓

5. SUPPLY AIR FAN SIZE AT 14,000 CFM
 $\frac{1}{2}$ 7.37" TSP AT SEA LEVEL OR
5.60" TSP AT 7500 FT.
BUFFALO TYPE BL-730

6. VAV TERMINAL - ESTIMATE 1000 CFM
EACH $\frac{1}{2}$ AT 14,000 CFM - ESTIMATED
NUMBER = 14 UNITS WITH
HEATING COIL ✓

7. DIFFUSER - ESTIMATE 400 CFM EACH
 $\frac{1}{2}$ AT 14,000 CFM - ESTIMATED
NUMBER = 35 DIFFUSERS 12" X 12" EA. ✓

8. 2-HEAT RECOVERY COILS SIZE FOR 700 FPM @
14000 CFM 20 SF.

SYSTEM #3 - EXHAUST AIR
ZONE #2

DESIGNED BY TJT

DATE 2/15/4

CHECKED BY CLP

DATE 3/14/4

1. EXHAUST AIR REGISTER - ESTIMATE
800 CFM EACH $\frac{1}{2}$ AT 14,000 CFM
ESTIMATED NUMBER = 18 REGISTERS
24" X 12" ✓

2. CLEAN AIR FILTER TRAIN 1ST STAGE
14,000 CFM $\frac{1}{2}$ 1,000 CFM EACH HEPA
- ESTIMATED NUMBER = 14 - 24" X 24" X 12"
FILTER IN ONE FILTER BANK
3 HIGH X 5 WIDE ✓

ONE BANK 3 HIGH X 5 WIDE

3. CLEAN AIR FILTER TRAIN 2ND STAGE
EXHAUST AIR - SAME AS "2" ABOVE ✓

4. CLEAN AIR FILTER TRAIN 2ND RETURN
AIR - EQUAL TO 1/2 OR
ONE FILTER BANK 2 HIGH $\frac{1}{2}$ 4 WIDE ✓

SYSTEM #3 - EXHAUST AIR (cont)
ZONE #2

DESIGNED BY TJ1

DATE 2/18/93

CHECKED BY CL4

DATE 3/14/93

5. RETURN AIR FAN - SIZE FOR
7,000 CFM AT 9.28" TSP AT SEA
LEVEL OR 6.9" TSP AT 7500 FT
BUFFALO TYPE BL-400

6. STACK SIZE AT 14,000 CFM
AT 3200 RPM = 28" DIAMETER ✓

7. EXHAUST AIR FAN SIZE FOR 14,000
CFM AT 9.06" TSP AT 7500 FT
OR 6.9" TSP AT SEA LEVEL. ✓
BUFFALO TYPE BL-730

SYSTEM # 3 - EXHAUST AIR
ZONE # 1

DESIGNED BY TJT DATE 2/13/93

CHECKED BY CLQ DATE 3/14/93

1. ESTIMATE PROCESS & D&D EQUIPMENT
NEED, 7000 CFM EXHAUST AIR.
2. CLEAN AIR TRAIN ZONE # 1, 1ST
STAGE 7,000 CFM. USE 8'-24" x 24" x 12"
HEPA FILTER ✓
3. CLEAN AIR TRAIN ZONE # 1, 2ND
STAGE. SAME AS "2" ABOVE.
4. EXHAUST AIR PAN SIZE FOR
7,000 CFM AT 12.75" TSP AT
SEA LEVEL OR 9.7" TSP AT
7500 FT. BUFFALO TYPE BL-400
5. STACK SIZE AT 7,000 CFM @ 3200 FPM =
20" DIAMETER ✓

SYSTEM #4 - SUPPLY AIR

DESIGNED BY TJ

DATE 2/13/2

CHECKED BY CLK

DATE 3/14/93

1. LOUVER SIZE AT 500 FPM $\frac{1}{4}$ 76,000 CFM
= 152 SF FREE AREA X 2 = 304 SF ✓

2. FILTERS SIZE AT 300 FPM $\frac{1}{4}$ 76,000
CFM = 254 SF OR 64-24" X 24" IN
A FILTER BANK OF 5 HIGH X 13 WIDE
OR 10' HIGH X 26' WIDE ✓

3. HEATING COIL SIZE AT 600 FPM
 $\frac{1}{4}$ 76,000 CFM = 127 SF ✓

4. COOLING COIL SIZE AT 76,000 CFM
500 FPM = 152 SF ✓

5. SUPPLY AIR FAN SIZE AT
76,000 CFM $\frac{1}{4}$ 4,29" TSP AT
SEA LEVEL OR 3.25" TSP AT 7500 FT.
BUFFALO TYPE BL-1320

6. VAV TERMINAL - ESTIMATE 1,000 CFM
EACH $\frac{1}{4}$ 76,000 CFM - ESTIMATED
NUMBER = 76 UNITS WITH HEATING
COILS ✓

7. DIFFUSER - ESTIMATE 400 CFM EACH
 $\frac{1}{4}$ AT 76,000 CFM - ESTIMATED NUMBER
= 190 DIFFUSER 12" X 12" NL, ✓

8. 2- HEAT RECOVERY COILS SIZE @ 700 FPM @
76,000 CFM = 109 SF EA

SYSTEM # 1 - EXHAUST AIR
ZONE # 2

DESIGNED BY TT DATE 2/13/95

CHECKED BY CLQ DATE 3/18/95

1. EXHAUST AIR REGISTER - ESTIMATE 800 CFM EACH @ AT 76,000 CFM - ESTIMATED NUMBER = 95 REGISTERS 24" X 12" ✓

2. CLEAN AIR FILTER TRAIN 1ST STAGE
76,000 CFM @ 1000 CFM EACH HEPA
- ESTIMATED NUMBER = 76 - 24" X 24" X 12"
HEPA FILTERS IN SIX FILTER BANKS ✓
3 HIGH X 5 WIDE.

3. CLEAN AIR FILTER TRAIN 2ND STAGE
EXHAUST AIR - SAME AS "2" ABOVE ✓

4. CLEAN AIR FILTER TRAIN 2ND STAGE
RETURN AIR - EQUAL TO 1/2 OR
THREE FILTER BANKS 3 HIGH X 5 WIDE

SYSTEM #4 - EXHAUST AIR (CONT)
ZONE #2

DESIGNED BY TJT DATE 2/13/93

CHECKED BY LLQ DATE 3/14/93

5. EXHAUST AIR FAN SIZE FOR 76,000
CFM AT 9.28" TSP AT SEALEVEL OR
6.9" TSP AT 7500 FT. BUFFALO
TYPE BL-1320

6. STACK SIZE AT 76,000 CFM AT
3200 RPM = 64" DIAMETER. ✓

SYSTEM # 5 - SUPPLY AIR

DESIGNED BY TJ DATE 2/13/9

CHECKED BY CLP DATE 3/14/9

1. LOUVER SIZE AT 500 FPM & 77,000 CFM
USE SAME SIZE AS SYSTEM # 4.

ALL ITEMS ARE IDENTICAL TO SYSTEM # 4.

ICF KAISER
ENGINEERS

System # B - SVPLT AIR
Exhaust Air

DESIGNED BY JT

DATE 3/15/93

CHECKED BY

DATE

SHEET 41A OF 89

Job No. 88180-173

AIR FLOW = 2064 CFM

1. LOUVER SIZE AT 500 FPM AT 2064 CFM
= 4 SF FREE AREA $\times 2 = 8$ SF LOUVER
SIZE

2. FILTERS SIZE AT 300 FPM $\frac{1}{2}$ 2064 CFM
= 7 SF OR $4 - 24'' \times 24'' \times 2''$

FILTER BANK (2 WIDE $\times$ 2 HIGH)

3. HEATING COIL SIZE AT 600 FPM =
4 SF

4. COOLING COIL AT 500 FPM = 4 SF

6. HEPA FILTERS IN LET AT 1000 CFM/FILTER
= 2 FILTER, USE 4 SF FILTER
BANK (1 HIGH $\times$ 2 WIDE)

7. RETURN AIR FILTERS AT 1000 CFM/FILTER
= 1 FILTER, USE 2 SF FILTER
BANK (1 HIGH $\times$ 1 WIDE)

8. EXHAUST AIR FILTERS SAME
AS 6 ABOVE - FILTER BANK

1 HIGH $\times$ 2 WIDE

9. EXHAUST FAN SIZE FOR 2000 CFM
AT 12.75 TSP AT S.L. BUFFALO TYPE
BL - 245

SYSTEM # 8 SUPPLY AIR
& EXHAUST AIR

DESIGNED BY J

DATE 3/15/2

CHECKED BY

DATE

10. SUPPLY AIR FAN SIZE FOR
2000 CFM $(7.37" + 9.09") = 16.46"$
BUFFALO SIZE 25 MW

11. STACK SIZE AT 2000 CFM
AT 3200 FPM = 11" DIAMETER.

SYSTEM #2 - SUPPLY A.R.

DESIGNED BY CLP DATE 3/9/92

CHECKED BY TTT DATE 3/15/92

1. LOUVER SIZE AT 500 FPM $\frac{1}{4}$ 34,079 CFM
= 69 SF FREE AREA X 2 = 138 SF
2. FILTERS SIZE AT 300 FPM $\frac{1}{4}$ 34,079 CFM
= 114 SF OR 11 - 2' X 2" IN
A FILTER BANK OF 5 HIGH $\frac{1}{4}$ 11 WIDE
OR 10' HIGH X 22' WIDE
3. HEATING COIL SIZE AT 600 FPM $\frac{1}{4}$ 34,079 CFM = 57 SF
4. COOLING COIL SIZE AT 500 FPM $\frac{1}{4}$ 34,079 CFM = 68 SF.
5. SUPPLY AIR FAN SIZE AT 34,079 CFM $\frac{1}{4}$ 2.37" TSP AT SEA LEVEL
OR 5.60" TSP AT 7500 FT
BUFFALO TYPE "BL", MODEL 1200
CLASS II
6. VAV TERMINAL - ESTIMATE 1000 CFM EACH $\frac{1}{4}$ AT 34,079 CFM - ESTIMATED NUMBER = 34 UNITS WITH HEATING COIL
7. DIFFUSER - ESTIMATE 400 CFM EACH $\frac{1}{4}$ AT 34,079 CFM - ESTIMATED NO = 85 DIFFUSERS 12" X 12" NK
8. 2- HEAT RECOVERY COIL SIZE @ 700 FPM @ 34,079 CFM = 48 SF ED, 6 ROW COIL.

SYSTEM #9 - EXHAUST AIR
ZONE #2

DESIGNED BY UQ DATE 3/4/4

CHECKED BY TT DATE 3/15/5

1. EXHAUST AIR REGISTER - ESTIMATE 800
CFM EACH @ AT 34,079 CFM -
ESTIMATED NUMBER = 43. REGISTERS
24" X 12"

2. CLEAN AIR FILTER TRAIN 1ST STAGE

34,079 CFM @ 1,000 CFM EACH HEPA
- ESTIMATED NUMBER = 34 - 24" X 24" X 12"
HEPA FILTERS IN A FOUR FILTER BANKS

3 HIGH X 6 WIDE
X 5' X 12' X 5'

TWO BANKS
3 HIGH X 6 WIDE
TOTAL 36 FILTERS
HEPA

3. CLEAN AIR FILTER TRAIN 2ND STAGE
EXHAUST - SAME AS "2" ABOVE

4. CLEAN AIR FILTER TRAIN 2ND STAGE

RETURN AIR - EQUAL TO 1/2 OR

TWO FILTER BANKS 3 HIGH @ 6 WIDE

X 5' X 12' X 5' X

ONE BANK
3 HIGH @ 6 WIDE
TOTAL OF 18 FILTERS
HEPA.

SYSTEM #9 EXHAUST AIR (CONT)
ZONE #2

DESIGNED BY CLK DATE 3/9/93

CHECKED BY TTT DATE 3/15/93

5. RETURN AIR FAN SIZE FOR 17,000
CFM AT 9.09" TSP AT SEA LEVEL
OR 6.9" TSP AT 7500 FT.
BUFFALO TYPE BL-730

6. STACK SIZE AT 34,009 CFM
AT 3200 RPM = 44" DIAMETER

7. EXHAUST AIR FAN SIZE FOR
34,079 CFM AT 9.06" TSP AT
SEA LEVEL OR 6.9" TSP AT 7500
FT.

SYSTEM # 9 - EXHAUST AIR
ZONE # 1

DESIGNED BY CLL DATE 3/9/93

CHECKED BY TJT DATE 3/15/94

1. FUME HOODS - ESTIMATE 10 FUME HOODS
AT 1600 CFM EACH OR 16,000 CFM
EXHAUST.

2. CLEAN AIR TRAIN ZONE #1 EXH. 1ST STAGE
16,000 CFM $\div$ 1000 CFM EACH HEPA
- ESTIMATED NUMBER = 16 - 24" X 24"
X 12" FILTER IN A FILTER BANK
3 HIGH X 6 WIDE OR 6' HIGH
X 12' WIDE. USE 18 - 24" X 24" X 12"
FILTERS HEPA.

3. CLEAN AIR TRAIN ZONE #1 EXH. 2ND STAGE
SAME AS "2" ABOVE.
USE 18 - 24" X 24" X 12" FILTERS HEPA

4. EXHAUST AIR FAN SIZE FOR
16,000 CFM AT 12.75" TSP AT SEA
LEVEL OR 9.7" TSP AT 7500 FT.
BUFFALO TYPE BL - 730

5. STACK SIZE AT 16,000 CFM AT 3200
FPM = 30" DIAMETER.

SUPPLY AIR FAN
RETURN AIR FAN
PRESSURE DROPS

DESIGNED BY LLP DATE 3/2/15

CHECKED BY JT DATE 3/15/9

SYSTEM #1
TECH AREAS

SUPPLY FAN	1" WG
PREFILTERS (40%)	0.40
FILTERS (65%)	0.40
PREHEAT COIL	0.20
COOLING COIL	0.60
DIFFUSER	0.10
DUCTWORK (75 F x 1.5 x 0.1/100 FT)	0.11
VAV BOX	0.5
HEATING COIL	0.2
INTAKE LOUVER	0.1
EXHAUST AIR LOUVER	0.1

SUBTOTAL 2.71
10% SF 0.27

SUPPLY AIR FAN @ SEA LEVEL = 2.98

RETURN FAN

RETURN AIR REGISTER	0.10
PREFILTER (40%)	0.40
DUCTWORK (75 F x 1.5 x 0.1/100 FT)	0.10

SUBTOTAL = 0.60
10% SF = 0.06

RETURN AIR FAN @ SEA LEVEL = 0.66

SUPPLY AIR FAN &
RETURN AIR FAN STATIC
PRESSURE DROPS

DESIGNED BY JT DATE 2/9/23

CHECKED BY CLY DATE 3/14/24

SYSTEM NO 3, 4, 5 & 2

DESCRIPTION

SUPPLY AIR FAN

"WG

INTAKE LOUVER

0.10

PRE FILTERS (40%)

0.40

FILTER HEPA (99.97%)

3.00

HEAT RECOVERY COIL

0.40

HEATING COIL

0.20

COOLING COIL

0.60

DIFFUSER

0.10

DUCTWORK (200 FT X 1.5 X 0.4" / 100)

1.20

VAV TERMINAL BOX

0.50

TERMINAL HEATING COIL

0.20

SUBTOTAL = 6.70

10% SF 0.67

SUPPLY FAN AT SEA LEVEL

7.37" ✓

RETURN AIR FAN

RETURN AIR REGISTER

0.10

SPARK ARRESTER SCREEN

0.06

SPARK SUPPRESSION SYSTEM

0.00

DEMISTER

0.40

PRE FILTER (40%)

0.40

TEST SECTION

0.25

HEPA FILTER (99.97%)

3.00

TEST SECTION

0.25

TEST SECTION

0.25

HEPA FILTER

3.00

TEST SECTION

0.25

DUCTWORK (200 FT X 1.5 X 0.4" / 100)

0.30

SUBTOTAL = 8.26

10% SF = 0.83

RETURN AIR FAN AT SEA LEVEL = 9.09" ✓

SYSTEM NO 3, 4, 5 & 2

DESCRIPTION

EXHAUST FAN (ZONE 2)

"UG

EXHAUST REGISTER

0.10

SPARK ARRESTER SCREEN

0.06

SPARK SUPPRESSION SYSTEM

0.00

DEMISTER

0.50

PRE-FILTER (40%)

0.40

TEST SECTION

0.25

HEPA FILTER (99.97%)

3.00

TEST SECTION

0.25

TEST SECTION

0.25

HEPA FILTER (99.97%)

3.00

TEST SECTION

0.25

DUCTWORK (250 FT X 1.5 X 0.1' / 100)

0.38

SUBTOTAL = 8.44
10% SF
0.84
= 9.28
EXHAUST FAN (ZONE 2)
AT 364 LEVEL

ICF KAISER
ENGINEERS

JOB NO. 88180-173
SHEET 48 OF 89

DESIGNED BY JT DATE 2/9/92
CHECKED BY CLP DATE 3/14/92

EXHAUST FAN STATIC DROP

EXHAUST FAN STATIC
PRESSURE DROP

DESIGNED BY TJT DATE 2/13/90

CHECKED BY CLK DATE 3/14/90

SYSTEM NO 3, 4, 5.

EXHAUST FAN (ZONE 1)

FUME HOOD	1.00
SPARK ARRESTER SCREEN	0.06
SPARK SUPPRESSION SYSTEM	0.00
DE MISTER	0.50
PRE FILTER (90%)	0.40
TEST SECTION	0.25
HEPA FILTER (99.97%)	3.00
TEST SECTION	0.25
DUCTWORK (150 FT X 1.5 X 0.1"/100 FT)	0.23

SUBTOTAL = 5.69

10% SF = 0.57

EXHAUST FAN (ZONE 1) = 6.26 ✓
AT SEA LEVEL

ICF KAISER
ENGINEERS

JOB NO. 88180-173

SHEET 50 OF 89

EXHAUST FAN STATIC

Pressure Drop.

DESIGNED BY

11

DATE 2/9/72

CHECKED BY

QAC

DATE 3/14/75

SYSTEM NO. 2.

DESCRIPTION

EXHAUST FAN (ZONE 1)

PROCESS EQUIPMENT

SPARK ARRESTOR SCREEN

SPARK SUPPRESSION SYSTEM

DEMISTER

PA FILTER (40%)

TEST SECTION

CHARCOAL FILTERS

TEST SECTION

CHARCOAL FILTER

TEST SECTION

HEPA FILTERS (99.97%)

TEST SECTION

HEPA FILTERS (99.97%)

TEST SECTION

DUSTWORK (250 FT X 1.5 X 0.1" / 100 FT)

0.38

0.25

3.00

0.25

3.00

0.25

1.00

0.25

1.00

0.25

0.4

0.50

0.00

0.06

1.00

SUBTOTAL

11.59

1070 SF

1.16

EXHAUST FAN (ZONE 1) ASL =

12.75

ICF KAISER
ENGINEERS

JOB NO. 88130-173
SHEET 51 OF 89

DESIGNED BY TH DATE 2/9/89
CHECKED BY CLG DATE 3/14/89

SUPPLY AIR FAN &
RETURN AIR FAN STATIC
PRESSURE LOSS

SYSTEM NO 8
CONTROL ROOM

DESCRIPTION

SUPPLY FAN

PRE FILTERS (40%)

FILTERS (65%)

HEAT COIL

COOLING COIL

DIFFUSER

DUCTWORK (75 FT X 11.5 X 0.1/100 FT)

INTAKE LOUVER

EXHAUST AIR LOUVER

0.10

0.10

0.11

0.10

0.60

0.20

0.40

0.40

11 WG

SUBTOTAL = 2.01

1070 SF = 0.20

SUPPLY AIR FAN ASL 2.21

SUPPLY FAN &
RETURN FAN STATIC
PRESSURE DROPS.

DESIGNED BY TJT DATE 2/9/93
CHECKED BY CLK DATE 3/12/93

SYSTEM NO 9 TECHNICAL SUPPORT

DESCRIPTION	DROP "WG
SUPPLY FAN	
PRE FILTER (30%)	0.40
FILTERS HEPA	3.00
HEAT RECOVERY COIL	0.40
HEATING COIL	0.40
COOLING COIL	0.60
VAV. TERMINAL BOX	0.50
TERMINAL HEATING COIL	0.20
DUCTWORK (200 FT X 1.5 X 0.4"/100)	1.20
INTAKE LOUVER	0.10
DIFFUSER	0.10
SUBTOTAL	= 6.70"
10% SF	= .67

SUPPLY FAN AT SEA LEVEL = 7.37"

RETURN AIR FAN

RETURN AIR REGISTER	0.10
DUCTWORK (200 FT X 1.5 X 0.1"/100)	= 0.30
SPARK ARRESTOR SCREEN	= 0.00
SPARK ARRESTOR SYSTEM	= 0.00
DEMI-STER	= 0.40
PRE FILTER 40%	= 0.40
TEST SECTION	= 0.25
HEPA FILTER (99.97%)	= 3.00
TEST SECTION	= 0.25
TEST SECTION	= 0.25
HEPA FILTER (99.97%)	= 3.00
TEST SECTION	= 0.25

SUBTOTAL = 8.26"
10% SF = 0.83

RETURN AIR FAN AT
SEA LEVEL = 9.09"

TYPICAL SUPPLY AIR
SYSTEM.

DESIGNED BY TJT DATE 3/3/89

CHECKED BY CLQ DATE 3/10/89

**TYPICAL RETURN AIR
SYSTEM**

DESIGNED BY CLP DATE 3/14/93

CHECKED BY _____ DATE _____

TYPICAL ZONE # 1
EXHAUST SYSTEM
(PROCESS)

DESIGNED BY CLC DATE 3/16/91

CHECKED BY _____ DATE _____

**TYPICAL ZONE #2
EXHAUST SYSTEM**

DESIGNED BY CLP DATE 3/16/9

CHECKED BY _____ DATE _____

SELECTION OF CHILLERS

DESIGNED BY TT DATE 2/14/9

CHECKED BY CLQ DATE 3/14/9

A. SUMMARY OF CHILLED WATER LOAD

SYSTEM #1.

TECHNICAL SUPPORT, LOBBY

= 57.4 TONS

SYSTEM #2

PROCESS AREA

= 93.1 TONS

SYSTEM #3

HOT SHOP & DED

= 22.1 TONS

SYSTEM #4

MECHANICAL PENTHOUSE EXHAUST = 142.9 TONS

SYSTEM #5

MECHANICAL PENTHOUSE SUPPLY = 113 TONS

SYSTEM #6

HVAC CENTRAL PLANT

NO CHILLED WATER REQUIREMENT = 0

SYSTEM #7

COLD WAREHOUSE - NO CHILLED

WATER REQUIREMENT = 0

SYSTEM #8

CONTROL ROOM

= 4.6 TONS

SYSTEM #9

ENV LAB, SOIL LAB, CHANGE ROOM

= 4.1

ESTIMATED PROCESS EQUIPMENT

CHILLED WATER LOADS

= 25 TONS

TOTAL CHILLER LOAD = 499.2 TONS ✓

4. CONDENSER FLOW = $898 \text{ GPM} \times 1.25$
TWO PASS = 1123 GPM ✓

MODEL CVHE-400-3CE, 25 FT DROP
FOR EVAPORATOR, $\frac{1}{3}$ CONDENSER.
403 HP, 537 RLA, 3560 LRA, 480V,
3 PHASE, 60 HZ, TWO PASS ✓

3. SELECT TWO (2) - TRANE CENTRIFUGAL
CHILLERS, 10°F TEMP RISE, 898 GPM,
440F EWT, ✓

$$= 898 \text{ GPM} \checkmark$$

$$2. \text{ GPM} = \frac{394 \text{ TONS} \times 12000 \text{ BTU/TON}}{100 \text{ F} \times 500} = 94.56 \text{ GPM}$$

1.5% EACH CHILLER FOR 75% OF
THE LOAD = $499.2 \text{ TONS} \times 75\% = 374.4 \text{ TONS} \checkmark$

TOTAL CHILLER LOAD = 499.2 TONS

B. CHILLER SELECTION

ICF KAISER
ENGINEERS

SELECTION OF CHILLERS
PRELIMINARY

DESIGNED BY HT

CHECKED BY CLP

JOB NO. 88180-173
SHEET 58 OF 89

DATE 2/10/12

DATE 3/1/12

HVAL CENTRAL PLANT
CHILLED WATER PUMP

DESIGNED BY TJ

DATE 3/21/93

CHECKED BY CU

DATE 3/18/93

A. CHILLER NO 1 & 2 = 374 TONS & 898 GPM EA

1. CWS & CWR PRESSURE DROP

2 CHILLER

FT HEAD

25.0

b. PIPING (110 FT X 4' / 100' X 1.5)

6.6

SUBTOTAL = 31.6 FT ✓

10% SF

3.2

TOTAL

34.8 ✓

c. SELECT PUMP 1, 2, 3 & 4 900 GPM
AT 35 FT.

B. PRIMARY CHILLED WATER PUMPS NO 5 & 6
500 TONS & 1200 GPM

1. CWS & CWR PRESSURE DROP

2. PIPING (520 FT X 1.5 X 4' / 100')

31.2

b. THREE-WAY VALVE

10.0

c. COOLING COIL

10.0

SUBTOTAL = 51.2' ✓

10% SF = 5.1'

TOTAL = 56.3' ✓

d. SELECT PUMP NO 5 & 6 1200 GPM
AT 56 FT. ✓

SELECTION OF COOLING
TOWERS

DESIGNED BY JT DATE 2/14/12

CHECKED BY _____ DATE _____

A. CHILLER LOAD = 499.2 TONS

B. TWO CHILLERS WERE SELECTED
FOR 75% OF LOAD OR = $75\% \times 499.2$
= 374.4 TONS
EACH

C. SELECT TWO COOLING TOWERS

FOR A CHILLED WATER LOAD OF
374.4 TONS, WITH A 75°F INLET
TEMPERATURE & 85°F OUTLET
TEMPERATURE FOR THE CONDENSER.

$$\text{GPM} = 374.4 \text{ TONS} \times 3 \text{ GPM/TON} \\ = 1123.2 \text{ GPM}$$

USE 65°F EWB, FOR A RANGE (85 - 75 = 10°F)
(APPROACH = 75°F - 65°F = 10°F)
SELECTION FACTOR = 4.8-4.9

D. SELECT TWO COOLING TOWERS

BALTIMORE AIR COIL MODEL 3400:

$$1.5 \text{ HP FAN, } 1123.2 \text{ GPM, STATIC} \\ \text{LIFT PUMP HP} = \frac{(1123.2 \text{ GPM})(9 \text{ FT LIFT})}{(3.76 \text{ GPM FT/HP})(0.85 \text{ EFF})} \\ = 3.0 \text{ HP. STATIC LIFT.}$$

480V, 3 PHASE, 60 HZ, 13,710 LBS
OPER. WT.,

RIES 3000 SELECTION CHART

ENTERING WET BULB °F

80° 82° 84° 86° 88° 90° 92° 94° 96° 98° 100° 102° 104°

RANGE OF

5°

6°

7°

8°

9°

10°

11°

12°

13°

14°

15°

16°

18°

20°

22°

24°

26°

28°

30°

STEP-BY-STEP PROCEDURE FOR SELECTING A SERIES 3000 COOLING TOWER

GPM _____ Water In _____ °F Water Out _____ °F Wet Bulb _____ °F
*Do not exceed 120°F

1. Determine Range Water In _____ °F - Water Out _____ °F = _____ °F - Range

2. Determine Approach Water Out _____ °F - Water Bulb _____ °F = _____ °F - Approach

3. Determine Selection Factor

Entering at the design Wet Bulb temperature, project a line vertically downward to intersect the Range determined above. From this point project a horizontal line to the right intersecting the Approach curve at that temperature determined above. Then project a line vertically downward to intersect the design Wet Bulb line. Read the Selection Factor at this point.

Selection Factor = _____

4. Select Unit

Turn to the Series 3000 Capacity Tables on page 10 which tabulate the tower capacities in USGPM for Selection Factors ranging from 0.50 to 9.00. To select a tower, enter the table and read across the Selection Factor line to a factor EQUAL TO OR JUST LESS THAN the factor determined in Step 3. Read down the column until reaching a flow rate EQUAL TO OR GREATER THAN the design flow. Read the tower model number from the column on the left. If desired, the exact flow capacity can be found by interpolating directly between listed selection factors.

If the required flow rate exceeds all values shown in Table 1 (single cell units) for the appropriate Selection Factor, repeat the procedure using Table 2 (Double Cell units). Selection of three or more cells can be obtained by dividing the required flow rate by the number of cells required and utilizing Table 1.

FINAL SELECTION IS 1800DL

4.8-4.9
SELECTION FACTOR

NOTE: CTI STD-201 ap with enterin 125°F or less of 4°F or more approaches bulbs below

Baltin

110-89
03-01-1993 13:08
505 253 1329

THERMAL PERFORMANCE CERTIFIED BY THE COOLING TOWER INSTITUTE (CTI)

62 OF 89

ENGINEERING DATA

Do not use for construction. Refer to factory certified dimensions.

This brochure includes data current at time of publication which should be reconfirmed at the time of purchase.

Double Cell Units

* 3535-2 thru 31055-2 — 4"

** 3586-2 thru 31055-2 — 2"11"

*** 3586-2 thru 31055-2 ship in two sections per cell (four in all) the top section is the heaviest.

Heights are: 3586-2 thru 3585-2 — 7'2 1/2"
3707-2 thru 31055-2 — 6'10 1/4"

MODEL NO.	NOMINAL TONS ¹	MOTOR HP	CPM	WEIGHTS (LBS.)			DIMENSIONS												INLET CONN. SIZE	OUTLET CONN. SIZE
				OPERATING	SHIPPING	HIGHEST SECTION	L	W	H	A	B	C	D	E	F	G	J			
3130-2	280	(2)5	74,000	20,900	8,280	4,140	12'6"	17'11"	8'10"	7'11"	8'6"	7'4"	3'8 1/2"	7'1 1/2"	7'7 1/2"	9'0"	5 1/4"	8"	6"	
3150-2	300	(2)7.5	84,700	20,980	8,340	4,170	12'6"	17'11"	8'10"	7'11"	8'6"	7'4"	3'8 1/2"	7'1 1/2"	7'7 1/2"	9'0"	5 1/4"	8"	6"	
3180-2	330	(2)10	93,100	20,980	8,380	4,180	12'6"	17'11"	8'10"	7'11"	8'6"	7'4"	3'8 1/2"	7'1 1/2"	7'7 1/2"	9'0"	5 1/4"	8"	6"	
3184-2	368	(2)15	106,800	21,120	8,500	4,250	12'6"	17'11"	8'10"	7'11"	8'6"	7'4"	3'8 1/2"	7'1 1/2"	7'7 1/2"	9'0"	5 1/4"	8"	6"	
3186-2	370	(2)10	107,900	21,080	9,020	4,510	12'6"	17'11"	10'2"	8'3 1/2"	8'6"	7'4"	3'8 1/2"	7'1 1/2"	7'7 1/2"	9'0"	7 1/4"	8"	6"	
3206-2	410	(2)15	122,400	21,800	9,180	4,590	12'6"	17'11"	10'2"	8'3 1/2"	8'6"	7'4"	3'8 1/2"	7'1 1/2"	7'7 1/2"	9'0"	7 1/4"	8"	6"	
3213-2	428	(2)7.5	128,200	28,080	10,880	5,480	18'0 1/2"	18'0 1/2"	10'2"	8'3 1/2"	8'0 1/2"	8 1/2"	3'7 1/2"	7'7"	8'0 1/2"	8'5 1/2"	7 1/4"	8"	8"	
3236-2	470	(2)10	141,600	28,100	10,940	5,470	18'0 1/2"	18'0 1/2"	10'2"	8'3 1/2"	8'0 1/2"	8 1/2"	3'7 1/2"	7'7"	8'0 1/2"	8'5 1/2"	7 1/4"	8"	8"	
3260-2	538	(2)16	161,500	28,340	11,080	5,540	18'0 1/2"	18'0 1/2"	10'2"	8'3 1/2"	8'0 1/2"	8 1/2"	3'7 1/2"	7'7"	8'0 1/2"	8'5 1/2"	7 1/4"	8"	8"	
3284-2	588	(2)20	178,800	28,280	11,120	5,580	18'0 1/2"	18'0 1/2"	10'2"	8'3 1/2"	8'0 1/2"	8 1/2"	3'7 1/2"	7'7"	8'0 1/2"	8'5 1/2"	7 1/4"	8"	8"	
3318-2	630	(2)25	190,000	28,380	11,230	5,610	18'0 1/2"	18'0 1/2"	10'2"	8'3 1/2"	8'0 1/2"	8 1/2"	3'7 1/2"	7'7"	8'0 1/2"	8'5 1/2"	7 1/4"	8"	8"	
3341-2	682	(2)16	198,800	28,080	14,180	7,080	18'6"	20'0 1/2"	10'2"	8'3 1/2"	10'0 1/2"	8 1/2"	3'7 1/2"	8'7"	8'0 1/2"	10'7"	8 1/4"	10"	10"	
3370-2	748	(2)20	217,400	28,080	14,200	7,100	18'6"	20'0 1/2"	10'2"	8'3 1/2"	10'0 1/2"	8 1/2"	3'7 1/2"	8'7"	8'0 1/2"	10'7"	8 1/4"	10"	10"	
3400-2	800	(2)25	233,100	28,180	14,300	7,150	18'6"	20'0 1/2"	10'2"	8'3 1/2"	10'0 1/2"	8 1/2"	3'7 1/2"	8'7"	8'0 1/2"	10'7"	8 1/4"	10"	10"	
3434-2	848	(2)30	247,100	28,200	14,340	7,170	18'6"	20'0 1/2"	10'2"	8'3 1/2"	10'0 1/2"	8 1/2"	3'7 1/2"	8'7"	8'0 1/2"	10'7"	8 1/4"	10"	10"	
3437-2	854	(2)30	248,900	21,340	16,880	8,410	23'10"	20'8 1/2"	10'2"	8'3 1/2"	10'3 1/2"	8 1/2"	3'7 1/2"	8'10"	8'3 1/2"	10'10"	10 1/4"	10"	10"	
3480-2	918	(2)25	268,800	21,440	18,980	8,480	23'10"	20'8 1/2"	10'2"	8'3 1/2"	10'3 1/2"	8 1/2"	3'7 1/2"	8'10"	8'3 1/2"	10'10"	10 1/4"	10"	10"	
3486-2	970	(2)30	284,400	21,480	18,980	8,480	23'10"	20'8 1/2"	10'2"	8'3 1/2"	10'3 1/2"	8 1/2"	3'7 1/2"	8'10"	8'3 1/2"	10'10"	10 1/4"	10"	10"	
3614-2	1028	(2)30	287,800	22,980	18,340	8,170	23'10"	20'8 1/2"	11'8"	10'7 1/2"	10'3 1/2"	10 1/4"	3'8 1/2"	8'10"	8'3 1/2"	10'10"	10 1/4"	12"	12"	
3680-2	1120	(2)40	315,100	23,280	18,880	8,430	23'10"	20'8 1/2"	11'8"	10'7 1/2"	10'3 1/2"	10 1/4"	3'8 1/2"	8'10"	8'3 1/2"	10'10"	10 1/4"	12"	12"	
3880-2	1172	(2)30	332,100	21,210	24,000	8,410	23'10"	22'0 1/2"	13'8 1/2"	12'0 1/2"	11'0 1/2"	10 1/4"	7'8 1/2"	8'7"	10'0 1/2"	10'8 1/2"	11 1/4"	12"	12"	
3443-2	1284	(2)40	343,800	21,730	24,220	8,670	23'10"	22'0 1/2"	13'8 1/2"	12'0 1/2"	11'0 1/2"	10 1/4"	7'8 1/2"	8'7"	10'0 1/2"	10'8 1/2"	11 1/4"	12"	12"	
3886-2	1370	(2)50	380,000	21,880	24,840	8,730	23'10"	22'0 1/2"	13'8 1/2"	12'0 1/2"	11'0 1/2"	10 1/4"	7'8 1/2"	8'7"	10'0 1/2"	10'8 1/2"	11 1/4"	12"	12"	
3787-2	1414	(2)40	367,800	28,280	28,340	7,570	23'10"	22'0 1/2"	18'1 1/2"	14'8 1/2"	11'0 1/2"	10 1/4"	8'2 1/2"	8'7"	10'0 1/2"	10'8 1/2"	11 1/4"	12"	12"	
3786-2	1518	(2)50	415,900	28,440	28,480	7,630	23'10"	22'0 1/2"	18'1 1/2"	14'8 1/2"	11'0 1/2"	10 1/4"	8'2 1/2"	8'7"	10'0 1/2"	10'8 1/2"	11 1/4"	12"	12"	
3883-2	1808	(2)50	440,000	28,780	28,780	7,780	23'10"	22'0 1/2"	18'1 1/2"	14'8 1/2"	11'0 1/2"	10 1/4"	8'2 1/2"	8'7"	10'0 1/2"	10'8 1/2"	11 1/4"	12"	12"	
3613-2	1828	(2)40	443,100	28,980	28,980	7,850	23'10"	22'0 1/2"	18'8 1/2"	17'4 1/2"	11'0 1/2"	10 1/4"	10'10 1/2"	8'7"	10'0 1/2"	10'8 1/2"	11 1/4"	12"	12"	
3688-2	1720	(2)50	470,000	28,900	28,900	7,810	23'10"	22'0 1/2"	18'8 1/2"	17'4 1/2"	11'0 1/2"	10 1/4"	10'10 1/2"	8'7"	10'0 1/2"	10'8 1/2"	11 1/4"	12"	12"	
3338-2	1870	(2)50	510,800	22,330	33,780	8,880	28'0 1/2"	24'0 1/2"	18'8 1/2"	17'4 1/2"	12'0 1/2"	10 1/4"	18'10 1/2"	10'7"	11'0 1/2"	11'8 1/2"	13 1/4"	14"	14"	
3888-2	1980	(2)60	541,400	22,840	34,040	8,010	28'0 1/2"	24'0 1/2"	18'8 1/2"	17'4 1/2"	12'0 1/2"	10 1/4"	18'10 1/2"	10'7"	11'0 1/2"	11'8 1/2"	13 1/4"	14"	14"	
31888-2	2110	(2)75	580,100	22,740	34,140	8,080	28'0 1/2"	24'0 1/2"	18'8 1/2"	17'4 1/2"	12'0 1/2"	10 1/4"	18'10 1/2"	10'7"	11'0 1/2"	11'8 1/2"	13 1/4"	14"	14"	

BASE IS BASE WITH A 78°F AIRTEMPERATURE.

63 OF 89

SERIES 3000 CAPACITY TABLES

THERMAL PERFORMANCE
CERTIFIED BY THE COOLING
TOWER INSTITUTE (CTI) IN
ACCORDANCE WITH CTI
STANDARD STD-001

TABLE 1—SINGLE CELL SELECTIONS

MODEL NUMBER	SELECTION FACTOR																	
	0.5	1.0	1.5	2.0	2.5	3.0	3.5	4.0	4.5	5.0	5.5	6.0	6.5	7.0	7.5	8.0	8.5	9.0
3130	N.A.	217	234	251	270	291	313	337	362	390	420	451	486	523	562	605	651	701
3150	234	251	270	291	313	336	362	389	418	450	484	521	560	602	648	697	749	806
3165	257	277	298	320	344	370	398	428	460	495	532	572	616	662	712	766	823	885
3184	289	311	334	360	387	416	447	480	516	555	597	641	689	741	797	857	921	989
3185	290	311	335	360	387	416	447	480	516	555	597	641	689	741	796	856	920	989
3205	322	346	372	400	429	461	496	533	572	615	661	710	763	820	881	947	1017	1093
3213	335	360	387	415	446	480	515	554	595	639	687	738	793	851	915	983	1056	1135
3235	371	398	426	459	493	530	569	611	656	705	757	813	874	938	1008	1082	1162	1249
3269	426	457	491	527	566	608	652	700	752	807	866	930	998	1072	1151	1235	1326	1424
3294	467	501	538	577	620	665	714	766	822	882	947	1016	1090	1170	1256	1347	1446	1552
3315	502	538	577	620	665	713	765	821	881	945	1014	1088	1167	1252	1343	1441	1546	1659
3341	546	585	627	673	722	774	830	890	954	1023	1097	1176	1261	1353	1450	1555	1668	1789
3373	599	642	688	738	791	848	909	974	1044	1119	1199	1286	1378	1477	1582	1695	1817	1950
3400	644	690	740	793	849	910	975	1045	1120	1200	1286	1378	1477	1582	1695	1817	1947	2086
3424	684	733	786	842	901	966	1035	1108	1187	1272	1363	1460	1564	1675	1795	1923	2060	2207
3427	684	733	786	843	904	969	1039	1114	1195	1281	1374	1473	1579	1692	1814	1944	2084	2234
3458	736	788	845	906	971	1041	1116	1196	1282	1374	1473	1579	1692	1814	1944	2084	2234	2395
3485	781	837	896	961	1030	1103	1182	1267	1358	1455	1559	1671	1791	1919	2056	2204	2361	2531
3514	832	891	954	1022	1094	1172	1255	1344	1440	1542	1651	1769	1894	2029	2173	2327	2492	2669
3560	910	974	1042	1116	1195	1279	1369	1466	1569	1680	1799	1925	2061	2207	2362	2529	2707	2898
3586	909	984	1063	1147	1235	1330	1429	1533	1643	1758	1879	2006	2138	2274	2416	2564	2718	2876
3642	1001	1082	1169	1260	1357	1460	1568	1681	1801	1926	2057	2194	2337	2486	2640	2800	2968	3137
3685	1072	1158	1251	1348	1451	1560	1675	1795	1922	2055	2194	2339	2490	2648	2811	2981	3156	3337
3707	1063	1157	1256	1361	1472	1590	1713	1843	1979	2121	2269	2423	2583	2748	2918	3094	3273	3457
3758	1145	1245	1351	1463	1582	1708	1839	1978	2123	2274	2432	2595	2765	2940	3121	3307	3497	3691
3803	1218	1324	1436	1554	1680	1812	1951	2097	2250	2409	2575	2747	2925	3109	3296	3494	3693	N.A.
3813	1178	1289	1407	1533	1665	1806	1953	2108	2270	2439	2614	2796	2983	3175	3372	3573	N.A.	N.A.
3860	1251	1368	1493	1626	1766	1914	2069	2232	2403	2580	2764	2954	3151	3352	3558	N.A.	N.A.	N.A.
3938	1369	1496	1632	1775	1927	2087	2255	2431	2614	2805	3003	3207	3418	3634	3855	4080	4308	N.A.
3990	1458	1591	1734	1885	2046	2214	2391	2576	2769	2970	3178	3393	3613	3840	4071	4308	N.A.	N.A.
31055	1560	1703	1855	2016	2186	2365	2553	2749	2953	3165	3385	3611	3844	4082	4326	N.A.	N.A.	N.A.

TABLE 2—DOUBLE CELL SELECTIONS

MODEL NUMBER	SELECTION FACTOR																	
	0.5	1.0	1.5	2.0	2.5	3.0	3.5	4.0	4.5	5.0	5.5	6.0	6.5	7.0	7.5	8.0	8.5	9.0
3130-2	N.A.	434	468	502	540	582	626	674	724	780	840	902	972	1048	1124	1210	1302	1402
3150-2	468	502	540	582	626	674	724	778	836	900	968	1042	1120	1204	1296	1394	1498	1612
3165-2	514	554	596	640	688	740	796	856	920	990	1064	1144	1232	1324	1424	1532	1648	1770
3184-2	578	622	668	720	774	832	894	960	1032	1110	1194	1282	1380	1482	1594	1714	1842	1980
3185-2	580	622	670	720	774	832	894	960	1032	1110	1194	1282	1378	1482	1592	1712	1840	1978
3205-2	644	692	744	800	858	922	992	1066	1144	1230	1322	1420	1526	1640	1762	1894	2034	2186
3213-2	670	720	774	830	892	960	1030	1108	1190	1278	1374	1478	1586	1702	1830	1966	2112	2270
3235-2	742	796	856	918	986	1060	1138	1222	1312	1410	1514	1626	1748	1876	2016	2164	2324	2498
3269-2	852	914	982	1054	1132	1216	1304	1400	1504	1614	1732	1860	1996	2144	2302	2470	2652	2848
3294-2	934	1002	1076	1154	1240	1330	1428	1532	1644	1764	1894	2032	2180	2340	2512	2694	2892	3104
3315-2	1004	1076	1154	1240	1330	1428	1530	1642	1762	1890	2026	2176	2334	2504	2686	2882	3092	3318
3341-2	1092	1170	1254	1348	1444	1548	1660	1780	1908	2046	2194	2352	2522	2706	2900	3110	3336	3576
3373-2	1198	1284	1376	1476	1582	1696	1818	1948	2088	2238	2398	2572	2758	2954	3166	3394	3638	3900
3400-2	1288	1380	1480	1586	1698	1820	1950	2090	2240	2400	2572	2758	2954	3166	3394	3638	3894	4172
3424-2	1368	1468	1572	1684	1802	1932	2070	2218	2374	2544	2726	2920	3128	3350	3590	3846	4120	4414
3427-2	1368	1468	1572	1686	1808	1938	2078	2228	2390	2562	2748	2946	3158	3386	3632	3894	4174	4478
3458-2	1472	1576	1690	1812	1942	2082	2232	2392	2564	2748	2946	3158	3386	3632	3894	4174	4478	4790
3485-2	1562	1674	1792	1922	2060	2208	2364	2534	2718	2910	3118	3342	3582	3838	4112	4406	4722	5062
3514-2	1684	1782	1908	2044	2188	2344	2510	2688	2880	3084	3302	3538	3788	4058	4348	4654	4984	5338
3560-2	1820	1948	2084	2232	2390	2558	2738	2932	3138	3360	3598	3850	4122	4414	4724	5056	5414	5796
3586-2	1818	1968	2126	2294	2472	2660	2858	3068	3286	3518	3758	4010	4272	4548	4832	5128	5436	5752
3642-2	2002	2164	2338	2520	2714	2920	3136	3362	3602	3852	4114	4388	4674	4972	5280	5600	5932	6274
3685-2	2144	2316	2502	2696	2902	3120	3350	3590	3844	4110	4388	4678	4980	5296	5622	5962	6312	6674
3707-2	2126	2314	2512	2722	2944	3180	3428	3686	3958	4242	4538	4846	5166	5496	5838	6188	6546	6914
3758-2	2290	2490	2702	2928	3164	3416	3678	3958	4246	4548	4864	5190	5530	5880	6242	6614	6994	7382
3803-2	2436	2648	2872	3108	3360	3624	3902	4194	4500	4818	5150	5494	5850	6218	6596	6988	7386	N.A.
3813-2	2356	2578	2814	3066	3330	3612	3906	4216	4540	4878	5228	5592	5966	6350	6744	7148	N.A.	N.A.
3860-2	2502	2736	2986	3252	3532	3828	4136	4454	4806	5160	5528	5908	6302	6704	7116	N.A.	N.A.	N.A.
3938-2	2736	2992	3264	3550	3854	4174	4510	4862	5228	5610	6006	6414	6836	7268	7710	8160	8618	N.A.
3990-2	2912	3182	3468	3770	4092	4428	4782	5152	5538	5940	6356	6786	7226	7680	8142	8612	N.A.	N.A.
31055-2	3120	3408	3710	4032	4372	4730	5106	5498	5906	6330	6770	7222	7688	8164	8652	N.A.	N.A.	N.A.

ENGINEERING DATA

Do not use for construction. Refer to factory certified dimensions.

This brochure includes data current at time of publication which should be reconfirmed at the time of purchase.

Single Cell Units

* 3035 thru 31055 — 1/2"
 ** 3555 thru 31055 — 2'11"
 *** 3555 thru 31055 ship in two sections per cell,
 the top section is the heaviest.
 Heights are: 3555 thru 3555 — 7'2 1/2"
 3707 thru 31055 — 8'10 1/2"

MODEL NO.	NOMINAL TONS ¹	MOTOR HP	CFM	WEIGHTS (LBS.)			DIMENSIONS										INLET CONN. SIZE	OUTLET CONN. SIZE
				OPERATING	SHIPPING	HIGHEST SECTION	L	W	H	A	B	C	D	E	F	G		
3136	130	8	37,300	10,480	4,140	4,140	8'1 1/4"	17'1 1/4"	8'10"	7'11 1/4"	8'8 1/4"	7'4 1/4"	3'8 1/4"	7'1 1/4"	7'7 1/4"	8'0"	5 1/4"	6"
3150	150	7.5	42,250	10,480	4,170	4,170	8'1 1/4"	17'1 1/4"	8'10"	7'11 1/4"	8'8 1/4"	7'4 1/4"	3'8 1/4"	7'1 1/4"	7'7 1/4"	8'0"	5 1/4"	6"
3165	168	10	48,540	10,480	4,180	4,180	8'1 1/4"	17'1 1/4"	8'10"	7'11 1/4"	8'8 1/4"	7'4 1/4"	3'8 1/4"	7'1 1/4"	7'7 1/4"	8'0"	5 1/4"	6"
3184	184	15	52,800	10,540	4,230	4,250	8'1 1/4"	17'1 1/4"	8'10"	7'11 1/4"	8'8 1/4"	7'4 1/4"	3'8 1/4"	7'1 1/4"	7'7 1/4"	8'0"	5 1/4"	6"
3185	168	10	53,800	10,830	4,310	4,510	8'1 1/4"	17'1 1/4"	10'2"	8'3 1/4"	8'8 1/4"	7'4 1/4"	3'8 1/4"	7'1 1/4"	7'7 1/4"	8'0"	7 1/4"	8"
3209	200	15	61,200	10,800	4,580	4,580	8'1 1/4"	17'1 1/4"	10'2"	8'3 1/4"	8'8 1/4"	7'4 1/4"	3'8 1/4"	7'1 1/4"	7'7 1/4"	8'0"	7 1/4"	8"
3244	210	7 1/2	64,100	14,050	5,450	5,450	7'8 1/4"	18'0 1/4"	10'2"	8'3 1/4"	8'0 1/4"	8'4 1/4"	3'7 1/4"	7'7 1/4"	8'0 1/4"	8'5 1/4"	7 1/4"	8"
3235	238	10	70,800	14,050	5,470	5,470	7'8 1/4"	18'0 1/4"	10'2"	8'3 1/4"	8'0 1/4"	8'4 1/4"	3'7 1/4"	7'7 1/4"	8'0 1/4"	8'5 1/4"	7 1/4"	8"
3260	260	15	80,750	14,120	5,540	5,540	7'8 1/4"	18'0 1/4"	10'2"	8'3 1/4"	8'0 1/4"	8'4 1/4"	3'7 1/4"	7'7 1/4"	8'0 1/4"	8'5 1/4"	7 1/4"	8"
3284	294	20	88,300	14,140	5,580	5,580	7'8 1/4"	18'0 1/4"	10'2"	8'3 1/4"	8'0 1/4"	8'4 1/4"	3'7 1/4"	7'7 1/4"	8'0 1/4"	8'5 1/4"	7 1/4"	8"
3315	315	28	95,000	14,180	5,610	5,610	7'8 1/4"	18'0 1/4"	10'2"	8'3 1/4"	8'0 1/4"	8'4 1/4"	3'7 1/4"	7'7 1/4"	8'0 1/4"	8'5 1/4"	7 1/4"	8"
3341	341	15	98,400	19,010	7,080	7,080	8'8 1/4"	20'0 1/4"	10'2"	8'3 1/4"	10'0 1/4"	8 1/4"	3'7 1/4"	8'7"	8'0 1/4"	10'7"	8 1/4"	10"
3372	373	20	108,700	19,030	7,100	7,100	8'8 1/4"	20'0 1/4"	10'2"	8'3 1/4"	10'0 1/4"	8 1/4"	3'7 1/4"	8'7"	8'0 1/4"	10'7"	8 1/4"	10"
3400	400	25	118,550	19,080	7,150	7,150	8'8 1/4"	20'0 1/4"	10'2"	8'3 1/4"	10'0 1/4"	8 1/4"	3'7 1/4"	8'7"	8'0 1/4"	10'7"	8 1/4"	10"
3430	430	30	123,800	19,100	7,170	7,170	8'8 1/4"	20'0 1/4"	10'2"	8'3 1/4"	10'0 1/4"	8 1/4"	3'7 1/4"	8'7"	8'0 1/4"	10'7"	8 1/4"	10"
3457	457	20	124,450	25,870	8,410	8,410	11'8 1/4"	20'8 1/4"	10'2"	8'3 1/4"	10'3 1/4"	8 1/4"	3'7 1/4"	8'10"	8'3 1/4"	10'10"	10 1/4"	10"
3458	458	25	133,450	25,730	8,460	8,460	11'8 1/4"	20'8 1/4"	10'2"	8'3 1/4"	10'3 1/4"	8 1/4"	3'7 1/4"	8'10"	8'3 1/4"	10'10"	10 1/4"	10"
3485	485	30	142,300	25,740	8,480	8,480	11'8 1/4"	20'8 1/4"	10'2"	8'3 1/4"	10'3 1/4"	8 1/4"	3'7 1/4"	8'10"	8'3 1/4"	10'10"	10 1/4"	10"
3514	514	30	143,800	28,430	8,170	8,170	11'8 1/4"	20'8 1/4"	11'8"	10'7 1/4"	10'3 1/4"	10 1/4"	3'8 1/4"	8'10"	8'3 1/4"	10'10"	10 1/4"	12"
3540	560	40	157,550	28,680	8,430	8,430	11'8 1/4"	20'8 1/4"	11'8"	10'7 1/4"	10'3 1/4"	10 1/4"	3'8 1/4"	8'10"	8'3 1/4"	10'10"	10 1/4"	12"
3585	585	30	166,060	30,805	12,000	8,410	11'8 1/4"	22'0 1/4"	13'3 1/4"	12'0 1/4"	11'0 1/4"	10 1/4"	7'8 1/4"	8'7"	10'0 1/4"	10'6 1/4"	11 1/4"	12"
3642	642	40	181,800	30,868	12,280	8,570	11'8 1/4"	22'0 1/4"	13'3 1/4"	12'0 1/4"	11'0 1/4"	10 1/4"	7'8 1/4"	8'7"	10'0 1/4"	10'6 1/4"	11 1/4"	12"
3655	655	50	195,000	30,825	12,330	8,730	11'8 1/4"	22'0 1/4"	13'3 1/4"	12'0 1/4"	11'0 1/4"	10 1/4"	7'8 1/4"	8'7"	10'0 1/4"	10'6 1/4"	11 1/4"	12"
3707	707	40	183,800	34,880	13,170	7,570	11'8 1/4"	22'0 1/4"	16'1 1/4"	14'8 1/4"	11'0 1/4"	10 1/4"	8'2 1/4"	8'7"	10'0 1/4"	10'6 1/4"	11 1/4"	12"
3758	758	50	207,800	34,720	13,230	7,630	11'8 1/4"	22'0 1/4"	16'1 1/4"	14'8 1/4"	11'0 1/4"	10 1/4"	8'2 1/4"	8'7"	10'0 1/4"	10'6 1/4"	11 1/4"	12"
3803	803	60	220,150	34,880	13,280	7,780	11'8 1/4"	22'0 1/4"	16'1 1/4"	14'8 1/4"	11'0 1/4"	10 1/4"	8'2 1/4"	8'7"	10'0 1/4"	10'6 1/4"	11 1/4"	12"
3815	815	50	221,550	38,380	14,340	7,650	11'8 1/4"	22'0 1/4"	16'8 1/4"	17'4 1/4"	11'0 1/4"	10 1/4"	10'10 1/4"	8'7"	10'0 1/4"	10'6 1/4"	11 1/4"	12"
3846	880	80	236,000	38,450	14,800	7,810	11'8 1/4"	22'0 1/4"	16'8 1/4"	17'4 1/4"	11'0 1/4"	10 1/4"	10'10 1/4"	8'7"	10'0 1/4"	10'6 1/4"	11 1/4"	12"
3838	835	30	235,400	46,180	16,880	8,150	13'11 1/4"	24'0 1/4"	18'8 1/4"	17'4 1/4"	12'0 1/4"	10 1/4"	10'10 1/4"	10'7"	11'0 1/4"	11'6 1/4"	13 1/4"	14"
3888	880	80	270,700	46,230	17,030	8,010	13'11 1/4"	24'0 1/4"	18'8 1/4"	17'4 1/4"	12'0 1/4"	10 1/4"	10'10 1/4"	10'7"	11'0 1/4"	11'6 1/4"	13 1/4"	14"
31984	1055	75	290,060	48,370	17,070	8,080	13'11 1/4"	24'0 1/4"	18'8 1/4"	17'4 1/4"	12'0 1/4"	10 1/4"	10'10 1/4"	10'7"	11'0 1/4"	11'6 1/4"	13 1/4"	14"

Notes: 1. Nominal tons are defined as 3 gpm of water per ton, cooled from 95°F to 55°F with a 78°F entering wet bulb temperature.

Unless otherwise indicated, all connections 3" and smaller are MPT. Connections 4" and larger are beveled-for-welding and suitable for grooved connections.

COOLING TOWER PUMP

DESIGNED BY TJ

DATE 2/21/2

CHECKED BY CLP

DATE 3/1/2

- A. COOLING TOWER PUMP NO 7 & 8, 1130 GPM EACH
B. COOLING TOWER WATER PRESSURE DROP.

1. PIPING (200 FT X 1.5 X 4'/100')	12'
2. CONDENSER	25'
3. THREE-WAY VALVE	10'
4. STATIC LIFT	<u>15'</u>

SUBTOTAL = 62'

10% SF = 6

TOTAL 68 FT ✓

- C. SELECT COOLING TOWER PUMP NO
7 & 8 FOR 1130 GPM AT 70 FT
HEAD.

BOILER SELECTION
PRELIMINARY

DESIGNED BY TTT DATE 2/14/72

CHECKED BY CLQ DATE 3/18/72

A. TOTAL LOAD FROM CALCS

$$= 11,347 \text{ MBH}$$

B. SIZE AS PER LANS ENG. STD 206.17.7.2
2/6/92 WITH THREE BOILERS:

40% and 60% WITH STANDBY AT 60%
OF SYSTEM LOAD.

1. AT 40% OF LOAD = $11,347 \text{ MBH} \times .40\% = 4539 \text{ MBH}$

2 AT 60% OF LOAD = $11,347 \text{ MBH} \times 60\% = 6808 \text{ MBH}$

C. SELECT ONE - A-JAX TUBE TYPE

MODEL WGF D-6000, 6,000 MBH
INPUT AT SL & 4,800 MBH OUTPUT
AT 7500 FT., 266 GAL. WATER VOLUME,
674 SF HEATING SURFACE, 14,400
LBS WT, 125 PSI ASME STAMPED.
BLOWER HP, 480V, 3 PHASE, 60 HZ

D. SELECT TWO - A-JAX TUBE TYPE

MODEL WGF D-9000, 9,000 MBH
INPUT AT SL & 7,200 MBH OUTPUT
AT 7500 FT., 335 GAL. WATER VOLUME,
965 SF HEATING SURFACE, 20,600
LBS WT, ASME STAMPED FOR 125 PSI,
BLOWER HP, 480V, 3 PHASE, 60 HZ.

HVAC CENTRAL PLANT
BOILER CIRCULATING PUMP

DESIGNED BY TJT DATE 2/21/88

CHECKED BY CLK DATE 3/15/88

A. BOILER NO 1 460 GPM
BOILER NO 2 680 GPM
BOILER NO 3 680 GPM

B. BOILER HOT WATER PRESSURE DROP

1. PIPING (110 FT X 1.5 X 4' / 100') = 6.6'

2. BOILER = 1.0

SUBTOTAL = 7.6 ✓

10% SF = 0.8

TOTAL = 8.4 ✓

USE = 9' ✓

C. SELECT BOILER CIRCULATING PUMP
NO 9 FOR 460 GPM AT 9 FT HEAD

D. SELECT BOILER CIRCULATING PUMP
NO 10 & NO 11 FOR 680 GPM EACH
AT 9 FT HEAD.

HVAC CENTRAL PLANT
PRIMARY HWS PUMPS

DESIGNED BY TJT

DATE 2/21/3

CHECKED BY CLP

DATE 3/14/6

A. HOT WATER SYSTEM GPM = 1140 GPM

B. HOT WATER PRESSURE DROP

	RT
1. PIPING (520 FT X 1.5 X 4'/100)	31.2
2. THREE WAY VALVE	10.0
3. OUTSIDE AIR TEMP. RESET THREE WAY VALVE	10.0
4. HEATING COIL	10.0

SUBTOTAL = 61.2 ✓

10% SF = 6.1

TOTAL = 67.3 ✓

USE 68 FT

C. SELECT PUMP NO 12 & 13 FOR
1140 GPM AT 68 FT HEAD

**SELECTION OF PROCESS
BOILERS**

DESIGNED BY CZP DATE 3/9/93

CHECKED BY JT DATE 3/15/93

A. ASSUME A LOAD OF 4,732 MBH LOAD AT 125 PSI STEAM SIZE FOR 15% INPUT AS PER LANL STANDARD 206.3.3.2.2. 2/6/92

B. PER LANL ENG STD 206.17.7.2 2/6/92 WITH THREE BOILERS 40% AND 60% WITH STAND BY AT 60% OF SYSTEM LOAD.

1. AT 40% OF LOAD = 1893 MBH

2. AT 60% OF LOAD = 2,839 MBH.

C. SELECT ONE W60XFD-2500, 2,500 MBH INPUT AT SEA LEVEL, 1,923 MBH OUTPUT AT 7500 FT ELEV, 277 SF HEATING SURFACE, 6200 WT, FORCED DRAFT, BLOWER HP, 480 V, 3 PHASE, 60 HZ.

SELECT TWO W60XFD-3750, 3750 MBH INPUT AT SEA LEVEL, 2884 MBH OUTPUT AT 7500 FT ELEV, 430.5 SF HEATING SURFACE, 11,100 LB.WT, FORCED DRAFT, BLOWER HP, 480 V 3 PHASE, 60 HZ.

SELECT HEAT EXCHANGER
PRELIMINARY

DESIGNED BY TT

DATE 2/14/9

CHECKED BY CLD

DATE 3/1/9

PLATE & FRAME HEAT EXCHANGER

BAL # EC12

107" HIGH

51" WIDE

197" LONG

HVAC CENTRAL PLANT
VENTILATION

DESIGNED BY TJJ

DATE 2/14/94

CHECKED BY CJP

DATE 3/14/94

A. AREA = $53' \times 144' = 7,632 \text{ SF}$

B. VOLUME = $7,632 \text{ SF} \times 20 \text{ FT} = 152,640 \text{ CUFT}$

C. VENTILATION AIR FLOW = $12 \text{ AIR CHANGES/HR}$
 $\times 152,640 \text{ CF} \times \text{HR}/60 \text{ min}$
 $= 30,528 \text{ CFM}$

D. FAN PRESSURE DROP

DESCRIPTION	"WG
1. OUTSIDE AIR INTAKE	0.10
2. FILTER (40%)	0.40
3. DAMPER BACK DRAFT	0.10
4. DUCTWORK (10' X 2 X 0.1"/100')	0.02

SUBTOTAL = 0.62

10% SF = 0.06

TOTAL AT 7500 FT
ELEV.

0.68

ALTITUDE CORR. $\div 1.32$

TOTAL AT SL. = 0.52" WG

E. SELECT SIX (6) ROOFTOP EXHAUST FANS
W/ 5,100 CFM EACH AT 0.52" WG
TSP. /

HVAC CENTRAL PLANT
UNIT HEATERS

DESIGNED BY

TJT

DATE 2/21/9

CHECKED BY

CA

DATE 3/14/9

A. BLDG HEAT LOSS = 262,134 BTUH

B. NUMBER OF UNIT HEATERS

8 AT 33,000 BTUH EACH

AND 3.3 GPM ($33,000 \text{ BTUH} / (200 \times 500)$) ✓

C. SELECT EIGHT (8) UNIT HEATERS

WITH 3.3 GPM HWS. ✓

COLD WAREHOUSE
VENTILATION

DESIGNED BY

TJT

DATE 2/21/93

CHECKED BY

CLQ

DATE 3/11/93

A. AREA = $67' \times 67' = 4489 \text{ SF}$

B. VOLUME = $4489 \text{ SF} \times 20 \text{ FT} = 89,780 \text{ CUFT}$

C. VENTILATION AIR FLOW = $12 \text{ AIR CHANGES/HR}$
 $\times 89,780 \text{ CUFT}$
 $\times \text{HR}/60 \text{ min}$
 $= 17,956 \text{ CFM} \checkmark$

D. FAN PRESSURE DROP

DESCRIPTION	"WG
1. OUTSIDE AIR INTAKE	0.10
2. FILTER (40%)	0.40
3. DAMPER (BACK DRAFT)	0.10
4. DUCTWORK (10' X 2 X 0.10"/100')	0.02

SUBTOTAL = 0.62

10% S.F. = 0.06

TOTAL AT 7500 FT = 0.68 $\checkmark$

ALTITUDE CORR. $\div 1.32$

TOTAL AT S.L. 0.52 $\checkmark$

E. SELECT FOUR (4) ROOF TOP EXHAUST
 FANS SAME AS HVAC CENTRAL
 PLANT 5,100 CFM EACH AT
 0.52" WG TSP. $\checkmark$

COLD WAREHOUSE
UNIT HEATERS

DESIGNED BY TJ

DATE 2/8/8

CHECKED BY CL

DATE 3/1/8

A. BLDG HEAT LOSS = 225,952 BTUH

B. NUMBER OF UNIT HEATERS
8 AT 29,000 BTUH EACH USE
SAME UNIT AS HVAC CENTRAL
PLANT 33,000 BTUH EACH WITH
3.3 GPM ✓

C. SELECT EIGHT (8) UNIT HEATERS
WITH 3.3 GPM OF HWS. ✓

COMPUTER ROOM

A/C UNIT

DESIGNED BY JT

DATE 2/21/1

CHECKED BY CLD

DATE 3/14/92

A. COOLING LOAD = 4.6 TONS AT 7500 FT

B. SELECT A/C UNIT $7\frac{1}{2}$ TON

WITH DX COOLING COIL & GAS
FIRE HEATING.

RLW STACK DESIGN

DESIGNED BY CLC DATE 3/15/93

CHECKED BY TJT DATE 3/15/93

H_c = STACK HEIGHT ABOVE BUILDING = $.3(A)^{.5}$ (AS - RAE FUNDAMENTALS 985
CHAPTER 14 P. 14.13)

$$A = L \times W$$

$$L = \text{LENGTH OF BUILDING} = 60'$$

$$W = \text{WIDTH OF BUILDING} = 300'$$

$$A = (60 \times 300) = 18,000 \text{ FE}^2$$

$$H_c = 0.3(18,000 \text{ FE}^2)^{.5}$$

$$= 40'$$

NOTE: STACKS ARE
LOCATED AT EAST SIDE
OF BUILDING.

TOTAL STACK HEIGHTS = 100'

STACK SUMMARY

SYSTEM #2	ZONE #2	86" DIA	100' HIGH
" #2	" #1	30" DIA	100' HIGH
" #3	" #2	28" DIA	100' HIGH
" #3	" #1	20" DIA	100' HIGH
" #4	" #2	64" DIA	100' HIGH
" #5	" #2	64" DIA	100' HIGH
" #9	" #2	44" DIA	100' HIGH
" #9	" #1	30" DIA	100' HIGH
" #8	" #2	11" DIA	100' HIGH

FUME HOOD SERVICES
FOR MAIN SIZING

DESIGNED BY CLQ DATE 3/10/94

CHECKED BY JT DATE 3/15/94

SERVICE			
NATURAL GAS	REPLACE EXISTING	NEW	TOTAL
2 1/2"	120'	285	405
2"	75'	57'	132
1 1/2"	35	0	35
1 1/4"	20	0	20
1"	130	57	187
3/4"	340	190	530
COMPRESSED AIR			
1 1/2"	245	133	378
1 1/4"	20	0	20
1"	270	285	555
3/4"	135	76	211
VACUUM			
2"	176		176
3/4"	197	380	577
HOT WATER			
2 1/2"	126		126
2"	64		64
1 1/2"	130	550	680
1"	91	550	741
3/4"	240	215	515
COLD WATER			
3"	110		110
2 1/2"	117		117
2"	110		110
1 1/2"	96		96
1 1/4"	200	1040	1240
1"	414	1040	1454
3/4"	140	520	660
DISTILLED WATER			
1"	75		75
3/4"	150	285	435
1/2"	210	95	305

FUME HOOD SERVICES
FOR MAIN SIZING

DESIGNED BY CLP DATE 3/10/93

CHECKED BY JT DATE 3/12/93

REPLACE PIPING THAT WAS IN EXISTING BUILDING

NEW PIPING	PIPE WITH FIXTURE	# OF FIXTURES	TO : FE
NATURAL GAS			
2 1/2"	15'	19	285'
2"	3'	1	57'
1 1/2"	2'		0
1 1/4"	1		57'
1"	3'		190'
3/4"	10		
COMP AIR			
1 1/2"	7	19	133'
1 1/4"	0		
1"	15		285'
3/4"	4		76'
VACUUM			
2"	0	19	
3/4"	20		380'
HOT WATER			
2 1/2"	0	55	-
2"	0		-
1 1/2"	10		550
1"	10		550
3/4"	5		275
COLD WATER			
3"	-	104	
2 1/2"	-		
2"	-		
1 1/2"	-		
1 1/4"	-		
1"	10		1040
3/4"	10		1040
	5		520
DISTILLED WATER			
1 1/2"	-	19	
3/4"	15		285

GAS MAIN SIZING

DESIGNED BY CLG DATE 3/15/9

CHECKED BY TTT DATE 3/15/9

CENTRAL PLANT

ITEM	QTY	CFH OF GAS
BOILERS		
WHFD- 6000	1	6000 CFH
WHFD- 9000	2	18000 CFH
WHOFD - 2500	1	2500 CFH
WHOXFD - 3750	2	7500 CFH
WATER HEATERS		
75MAH	4	300 CFS
		<u>TOTAL 34,300 CFH</u>

USE 3" GAS MAIN

**HOT WATER HEATER
SIZING**

DESIGNED BY CLP DATE 3/15/9

CHECKED BY TJT DATE 3/15/9

ITEM	# OF FIXTURES	GPH/FIXTURE	TOTAL GPH
SHOWERS	14	30	420
MOP SINKS	4	10	40
LAVATORIES	10	6	60
LAB SINKS	19	6	114
			<u>634 GPH</u>

GPH VALUES FROM 1991 ASHRAE
APPLICATIONS HANDBOOK TABLE 8
P. 44.14. FOR OFFICE BUILDING

PROBABLE MAXIMUM DEMAND = 634×0.30 (TABLE 8) = 190 gph

HEATER CAPACITY = 190 gph

STORAGE TANK CAPACITY = 190×2.00 (FROM TABLE 8)
= 380 GAL.

SELECT FOUR 48 gph 95 GAL
GAS WATER HEATERS.

CALCULATING FIXTURE UNITS

FOR DRAINING

SIZE WATER MAIN

DESIGNED BY CLP DATE 3/13/95

CHECKED BY TJT DATE 3/15/95

	QTY	FIXTURE UNITS	TOTAL
SHOWERS	14	4	56
EMERGENCY SHOWERS/EYE WASH	15	11	165
WATER CLOSETS	12	5	60
MOP SINKS	4	4	16
LAVATORIES	10	2	20
WATER COOLERS	8	2	16
URINALS	7	5	35
LAB SINKS	19	2	38

TOTAL FIXTURE
UNITS

406

USE A 3" MAIN INTO BUILDING

**SANITARY SEWER & ACID WASTE
PIPE QUANTITIES**

DESIGNED BY CLQ DATE 3/89
CHECKED BY TJT DATE 3/15/95

SANITARY SEWER			
FIXTURE	PIPE LENGTH / SIZE	# OF FIX	TOTAL / FIX
MAIN TRUNK			
• 1 ST FLOOR	504' / 4"	NA	504' OF 4"
• BASEMENT	336' / 4"	NA	336' OF 4"
WATER CLOSET	32' / 3"	12	384' OF 3"
SHOWERS	15' / 2"	14	210' OF 2"
MOP SINKS	15' / 2"	4	60' OF 2"
LAVATORIES	15' / 2"	10	150' OF 2"
EMERGENCY SHOW	18' / 2"	15	225' OF 2"
WATER COOLER	15' / 2"	8	120' OF 2"
EMERGENCY EYE	15' / 2"	15	225' OF 2"
URINALS	15' / 2"	7	105' OF 2"
TOTALS	4" = 840'		
	3" = 384'		
	2" = 1095'		

ACID WASTE			
MAIN TRUNK	450' / 4"		450' OF 4"
	384' / 3"		384' OF 3"
LAB SINKS	26' / 2"	19	510' OF 2"
TOTALS	4" = 450'		
	3" = 384'		
	2" = 1095'		

**CALCULATING FIXTURE UNITS
FOR SANITARY SEWER &
ACID WASTE.**

DESIGNED BY CLP DATE 3/8/93

CHECKED BY TJT DATE 3/15/93

SANITARY SEWER

• BASEMENT

SHOWERS

OF FIXTURES

FIXTURES
UNITS

TOTAL
FIXTURE
UNITS

2

2

4

WATER CLOSETS

4

6

24

MOP SINKS

2

3

6

LAVATORIES

4

2

8

EMERGENCY SHOWERS

7

2

14

WATER COOLERS

4

1

4

EMERGENCY EYE WASH

7

1

7

URNALS

3

2

6

73

• 1ST FLOOR

SHOWERS

12

2

24

WATER CLOSETS

8

6

48

LAVATORIES

6

2

12

EMERGENCY SHOWERS

8

2

16

WATER COOLERS

4

1

4

EMERGENCY EYE WASH.

8

1

8

MOP SINKS.

2

3

6

URNALS

4

2

8

TOTAL SANITARY SEWER

126

ACID WASTE

• BASEMENT

LAB SINKS

6

3

18

• 1ST FLOOR

LAB SINKS

13

3

39

TOTAL ACID WASTE

57

TOTAL FIXTURE UNITS:

SANITARY SEWER = 193

USE 4" MAIN TRUNK LINE.

ACID WASTE = 57.

USE 4" MAIN TRUNK LINE.

ROOF DRAINS 56,676 SF OF ROOF
SIZING MAIN LINE

DESIGNED BY LLQ

DATE 3/10/9

CHECKED BY TTT

DATE 3/15/9

2 INCH RAINFALL IN ONE-HOUR PERIOD (MEET LAUL
STANDARDS 205.10.1.

GPH PER SQFT = 1,247 (FROM LOSAM CATALOG)

$$(1.247)(56,676) = 70,675 \text{ GALS}$$

USE 4" DRAIN AT 1/4" SLOPE WILL HANDLE 110 GPM

$$\# \text{ OF ROOF DRAINS} = \frac{(70,675 \text{ GALS})}{110 \text{ GPM} \times 60 \text{ MIN}} = 10.7$$

USE 11 ROOF DRAINS

1178 TOTAL GPM

USE 10" MAIN.

3/10/99

Cemline Unfired Steam Generators

Dimensional Data-Horizontal

Boyd Engine Supply
Don Nielsen

Approx #25,000⁰⁰
10-12 wks

85 OF 89

Note: Pilot operated valve shown
pneumatic valve dimension are same.

Generate 3600 #/hr steam @ 200th
using 4732 #/hr steam @ 125th

Model Number	Boiler Vessel Size	W	H	L	S	M	I	J	K	P*	A	S
H001USG636	20" x 48"	34"	42"	64"	24"	52"	18"	24"	17"	60"	1 1/4" NPT	1/4"
H120USG672	24" x 63"	38"	46"	79"	28"	65"	18"	24"	17"	60"	1 1/4" NPT	3/4"
H200USG672	30" x 72"	44"	49"	88"	34"	76"	18"	24"	17"	60"	2" NPT	1"
H395USG1096	36" x 96"	60"	52"	112"	40"	100"	12"	20"	20"	84"	3" NPT	1"
H395USG1296	36" x 96"	60"	52"	142"	40"	100"	12"	20"	20"	84"	3" NPT	1"
H670USG14120	42" x 120"	56"	58"	140"	46"	124"	12"	20"	22"	102"	4" FLG	1 1/2"
H860USG16120	48" x 120"	62"	64"	140"	52"	124"	12"	20"	24"	102"	5" FLG	1 1/2"
H860USG18120	48" x 120"	62"	64"	140"	52"	124"	12"	20"	24"	102"	5" FLG	2"
H1330USG20120	60" x 120"	74"	76"	140"	64"	124"	12"	22"	28"	102"	8" FLG	2"
H1330USG24120	60" x 120"	74"	76"	140"	64"	124"	12"	22"	28"	102"	8" FLG	2"

*This dimension is for the longest coil available, shorter coils with a corresponding shorter "P" dimension are available. Consult factory or your Cemline representative.

Capacity in Pounds of Steam Per Hour with 100% Make Up of 40 Deg. F Water			
HTHW Temperature, Deg. F	360	360	360
Boiler Vessel Size	360	360	360
H001USG636	180	180	170
H120USG672	370	360	360
H200USG672	630	620	620
H395USG1096	1390	1370	1360
H395USG1296	2170	2150	2150
H670USG14120	3430	3390	3360
H860USG16120	4510	4460	4460
H860USG18120	5730	5600	5620
H1330USG20120	7670	7560	7530
H1330USG24120	11490	11360	11270

Can also be furnished in vertical. Consult factory or your representative.

86 OF 89

Page 7

Specifications--Steam Fired

Use this specification for an Unfired Steam Generator using steam as primary energy source.

Unfired Steam Generator shall be as manufactured by Cemline Corporation, Cheswick, PA 15024

Unfired Steam Generator shall be furnished as a complete package ready for installation including all necessary components for operation.

Unfired Steam Generator shall be ASME Code constructed and stamped in accordance with Section VII, Division I, for Unfired Steam Generators. Unfired Steam Generators shall be registered with the National Board of Boiler and Pressure Vessel Inspectors, and signed copy of shop inspection report shall be furnished. Unfired Steam Generator shall be built in accordance with Section VIII "Unfired Steam Generators" and shall bear the "UB" stamp.

Unfired Steam Generator and all components subject to steam side shall be carbon steel. OR: Unfired Steam Generator and all components subject to steam side shall be * grade stainless steel. (*Insert 304 or 316)

Unfired Steam Generator shall be insulated with not less than 2" of Fiberglass Insulation, protected by not less than 20 ga. thick enameled steel jacket.

Unfired Steam Generator shall be mounted on a suitable I-Beam support skid which shall be permanently welded to the shell.

Unfired Steam Generator shall have submerged coil of 19 BWG copper tubes expanded into a steel tube sheet with cast iron heads. OR: * grade stainless steel OR: 90:10 cupro-nickel.

Unfired Steam Generator will be furnished with an (air or pilot) operated control valve to modulate the in-coming steam to maintain the desired output of steam pressure ± 2 psi. Control valve shall be suitable for 150 psi at 450°F. Control valve pilot shall monitor output steam pressure and modulate the steam to maintain constant output pressure.

Unfired Steam Generator will be factory supplied with dual float and thermostatic traps, one for the coil and one for the drip before the control valve. Unfired Steam Generator shall have incoming steam strainer.

Unfired Steam Generator shall be furnished with an ASME Code pressure relief valve with a capacity to relieve the total BTU of output of the generator.

Unfired Steam Generator shall be furnished with a vessel steam gauge and inlet pressure vacuum gauge. Unfired Steam Generator shall be furnished with electronic level controller. Water column shall also be furnished with tri cocks. Unfired Steam generator shall be furnished with a blow off valve.

All components for the Unfired Steam Generator shall be factory mounted, piped, and tested and the unit shall be shipped from the factory as a complete unit ready for installation. Unfired Steam Generator shall be furnished with a steam separator.

Unfired Steam Generator shall be Cemline Model _____ designed with an output of _____/hour at _____ psi pressure and feed water of _____°F. when supplied with _____ psi steam before the control valve. Relief valve shall be set at _____ psi.

B7 GF 89
Page 6

Cemline Unfired Steam Generators

Energy Source — Steam

CEMLINE UNFIRED STEAM GENERATORS are completely packaged and ready for use. All components are sized, mounted and piped prior to shipment. These boilers come complete and requires only connections to services.

Shell	Carbon Steel	Stainless Steel
	Cemline Unfired Steam Generators with a carbon steel shell are used where condensate is returned to the boiler and there is little or no make-up.	Cemline Unfired Steam Generators with a stainless steel shell are used in applications requiring stainless steel as discussed on page 2. Stainless steel grades furnished are typically 304 or 316 as required for the application. In a Stainless Steel Unfired Steam Generator, all components in contact with the clean steam are constructed of the grade of stainless specified.

Level Controller/Water Feeder	Carbon Steel	Stainless Steel
	<p>Cemline Unfired Steam Generators are furnished with a level controller/water feeder.</p> <ol style="list-style-type: none"> 1. In a closed system using a return main, a float operated combination feeder cut-off is furnished and sized to match the BTU input of the boiler. 2. For applications where condensate is returned to a condensate receiver tank and pump, a float operated pump controller cut-off is used to cycle the condensate pump to maintain proper generator water level. 3. Where required, a combination float operated pump controller and a separate mechanical feeder can be used in parallel to maintain boiler water level in the event of an electrical interruption, pump failure or another unusual condition. (Not available on stainless steel USG). 	<p>Cemline Unfired Steam Generators are furnished with a level controller/water feeder.</p> <ol style="list-style-type: none"> 1. For systems using a main or 100% make-up, an electrical stainless steel level controller is furnished to maintain proper water level by cycling a stainless steel make-up water valve at the make-up inlet. 2. For Unfired Steam Generators using a condensate receiver tank and pump, a stainless steel electronic level controller will cycle condensate pump.

Energy Source-Steam (Continued)

Page 7

88 OF 89

Submerged Coils	Carbon Steel	Stainless Steel
	Cemline Unfired Steam Generators are furnished with a copper U-Bend heating coil rolled into a steel tube sheet for up to 100 psi incoming steam. With source steam of above 100 psi, 90:10 Cupro-nickel tubes are used.	Cemline Unfired Steam Generators are furnished with a stainless steel U-Bend heating coil rolled into a stainless steel tube sheet for up to 150 psi source steam.

Piping	Carbon Steel	Stainless Steel
	Cemline Unfired Steam Generators are furnished with carbon steel piping.	Cemline Unfired Steam Generators are furnished with stainless steel piping on clean steam side.

**ICF KAISER
ENGINEERS**

STEAM GENERATOR SUMMARY

JOB NO. 88180-173

SHEET 89 OF 89

DESIGNED BY CLG DATE 3/16/8

CHECKED BY JS DATE 3/16/8

FROM SUPPLIER COST \$25,200 USE \$30,000
FOR MATERIAL FOR STEAM TO STEAM
PROCESS HEAT EXCHANGER.

ICF KAISER ENGINEERS

1900 Diamond Drive
LOS ANGELES, NEW MEXICO 87544

DESIGN CALCULATION INDEX

JOB NUMBER 88180-173	AREA OR BUILDING TA-50-1	CALCULATION DESCRIPTION Electrical Load Estimates	DISCIPLINE Elec.
JOB TITLE RLW Refurbishment Feasibility study			

CALCULATIONS APPLY TO DRAWINGS AND REVISIONS SHOWN

DRAWING	REV	DRAWING	REV	DRAWING	REV	DRAWING	REV

DESIGN ENGINEER

(SIGNATURE)

(DATE)

CALCULATIONS CHECKED

(SIGNATURE)

3-17-93

CALCULATIONS AGREE WITH DESIGN CRITERIA

(SIGNATURE)

3-17-93

JOB ENGINEER

(SIGNATURE)

(DATE)

DESIGN SUPERVISOR

(SIGNATURE)

(DATE)

CALCULATIONS AGREE WITH APPROV. VENDOR DWGS.

(SIGNATURE)

(DATE)

CALCULATION KEYS

DATES

DATES

DATES

DATES

REVISION DESCRIPTION

DESIGN ENGINEER

DESIGN SUPERVISOR

STATUS

PRELIMINARY

FINAL

CHECK

VOID

HOLD

OTHER

REASON FOR VOID OR HOLD:

INDEX

SHEET NO.

DESCRIPTION

Load Estimate for Total Facility
Load Estimate for Panelboards

FILE: RLWLE

PROJECT: Radioactive Liquid Waste Treatment Facility Refurbishment

DATE: 3/16/93

LOAD SUMMARY:	FLA (2)	kW	kVA	% OF TOTAL
TOTAL VENTILATION LOAD	1957	1382.9	1626.9	52.1%
TOTAL COOLING/BOILER LOAD (see note 20)	791	559.3	658.0	21.1%
TOTAL HEATING LOAD	8	5.7	6.7	0.2%
TOTAL PROCESS LOAD	443	313.1	368.3	11.8%
TOTAL LIGHTING LOAD	233	165.0	194.1	6.2%
TOTAL RECEPTACLE LOAD	145	102.3	120.3	3.9%
TOTAL MISC. LOAD	181	127.7	150.2	4.8%
	0			0.0%
TOTAL	<u>3758 A</u>	<u>2655.8 kW</u>	<u>3124.5 kVA</u>	<u>100.0%</u>

Substation transformer sizing calculation:

A. Total kVA required for this facility.....	3124.5	kVA
B. Assumed Demand Factor (DF) for this facility.....	66.7%	
C. Total Estimated Demand for this facility.....	2083.0	kVA
D. Assumed Growth Factor of 20%.....	416.6	kVA
E. Contingency of 20%.....	416.6	kVA
F. Total of C + D + E.....	2916.2	kVA
G. Estimated Transformer Size.....	3000	kVA
H. Transformer Full Load Current (FLA) on Secondary Side...	3609	A

FILE: RLWLE

PROJECT: Radioactive Liquid Waste Treatment Facility Refurbishment

DATE: 3/16/93

1	S.A. Fan No. 1 (System 1)	460	3	65	50	44.0	85%	100%	51.8	MCC-A
2	R.A. Fan No. 1 (System 1)	460	3	65	50	44.0	85%	100%	51.8	MCC-A
3	(DELETED)									
4	S.A. Fan No. 2 (System 2)	460	3	124	100	84.0	85%	100%	98.8	MCC-A
5	S.A. Fan No. 3 (System 2)	460	3	124	100	84.0	85%	100%	98.8	MCC-A
6	R.A. Fan No. 2 (System 2)	460	3	65	50	44.0	85%	100%	51.8	MCC-A
7	R.A. Fan No. 3 (System 2)	460	3	65	50	44.0	85%	100%	51.8	MCC-A
8	Exh. Fan No. 2 (System 2)	460	3	124	100	84.0	85%	100%	98.8	MCC-C
9	Exh. Fan No. 3 (System 2)	460	3	124	100	84.0	85%	100%	98.8	MCC-C
10	Exh. Fan No. 4 (System 2)	460	3	52	40	35.2	85%	100%	41.4	MCC-D
11	S.A. Fan No. 4 (System 3)	460	3	27	20	18.3	85%	100%	21.5	MCC-B
12	R.A. Fan No. 4 (System 3)	460	3	14	10	9.5	85%	100%	11.2	MCC-B
13	Exh. Fan No. 5 (System 3)	460	3	14	10	9.5	85%	100%	11.2	MCC-D
14	S.A. Fan No. 5 (System 4)	460	3	124	100	84.0	85%	100%	98.8	MCC-B
15	Exh. Fan No. 6 (System 4)	460	3	156	125	105.6	85%	100%	124.3	MCC-D
16	R.A. Fan No. 5 (System 4)	460	3	156	125	105.6	85%	100%	124.3	MCC-B
17	S.A. Fan No. 6 (System 5)	460	3	124	100	84.0	85%	100%	98.8	MCC-B
18	R.A. Fan No. 6 (System 5)	460	3	96	75	65.0	85%	100%	76.5	MCC-B
19	Exh. Fan No. 6 (System 5)	460	3	124	100	84.0	85%	100%	98.8	MCC-D
20	Roof Top Exh. Fan (System 6)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
20A	S.A. Fan No. 7 (System 9)	460	3	65	50	44.0	85%	100%	51.8	MCC-A
20B	R.A. Fan No. 7 (System 9)	460	3	96	75	65.0	85%	100%	76.5	MCC-A
20C	Exh. Fan No. 7/Zone 1 (System 9)	460	3	124	100	84.0	85%	100%	98.8	MCC-C
20D	Exh. Fan No. 7/Zone 2 (System 9)	460	3	96	75	65.0	85%	100%	76.5	MCC-D

FILE: RLWLE

PROJECT: Radioactive Liquid Waste Treatment Facility Refurbishment

DATE: 3/16/93

21	Roof Top Exh. Fan (System 6)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
22	Roof Top Exh. Fan (System 6)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
23	Roof Top Exh. Fan (System 6)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
24	Roof Top Exh. Fan (System 6)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
25	Roof Top Exh. Fan (System 6)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
26	Unit Heater (System 6)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
27	Unit Heater (System 6)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
28	Unit Heater (System 6)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
29	Unit Heater (System 6)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
30A	Unit Heater (System 6)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
30B	Unit Heater (System 6)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
30C	Unit Heater (System 6)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
30D	Unit Heater (System 6)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
31	Roof Top Exh. Fan (System 7)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
32	Roof Top Exh. Fan (System 7)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
33	Roof Top Exh. Fan (System 7)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
34	Roof Top Exh. Fan (System 7)	460	3	1.8	1	1.2	85%	100%	1.4	MCC-D
35	Unit Heater (System 7)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
36	Unit Heater (System 7)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
37	Unit Heater (System 7)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
38	Unit Heater (System 7)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
39	Unit Heater (System 7)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP
40	Unit Heater (System 7)	120	1	3.5	1/8	0.4	85%	100%	0.4	PP

FILE: RLWLE

PROJECT: Radioactive Liquid Waste Treatment Facility Refurbishment

DATE: 3/16/93

41	Unit Heater (System 7)	120	1	3.5	1/8	0.4	85%	100%	0.4		PP
42	Unit Heater (System 7)	120	1	3.5	1/8	0.4	85%	100%	0.4		PP
43	A/C Unit (System 8 - note 25)	460	3	11.1		7.5	85%	100%	8.8	Note 1	MCC-B
44											PP
45	HVAC Central Plant Chiller	460	3	273.		185.0	85%	100%	217.6		MCC-E
46	HVAC Central Plant Chiller	460	3	273.		185.0	85%	100%	217.6		MCC-E
47											
48											
49	Central Plant Cooling Tower Fan	460	3	11	7.5	7.4	85%	100%	8.8		MCC-E
50	Central Plant Cooling Tower Fan	460	3	11	7.5	7.4	85%	100%	8.8		MCC-E
51											
52											
53	Chiller Circ. Pump No. 1	460	3	21	15	14.2	85%	100%	16.7		MCC-E
54	Standby Pump No. 2 (for #53)	460	3	21	(15)	(14.2)	85%	100%	(16.7)	Note 22	MCC-E
55	Chiller Circ. Pump No. 3	460	3	21	15	14.2	85%	100%	16.7		MCC-E
56	Standby Pump No. 4 (for #55)	460	3	21	(15)	(14.2)	85%	100%	(16.7)	Note 22	MCC-E
57	Primary CWS Pump No. 5	460	3	34	25	23.0	85%	100%	27.1		MCC-E
58											
59	Standby Pump No. 6 (for #57)	460	3	34	(25)	(23.0)	85%	100%	(27.1)	Note 22	MCC-E
60	Cooling Tower Pump No. 7	460	3	52	40	35.2	85%	100%	41.4		MCC-E
61	Cooling Tower Pump No. 8	460	3	52	40	35.2	85%	100%	41.4		MCC-E
62											
63	Boiler Circ. Pump No 9	460	3	4.8	3	3.3	85%	100%	3.8		MCC-F
64	Boiler Circ. Pump No 10	460	3	4.8	3	3.3	85%	100%	3.8		MCC-F
65	Boiler Circ. Pump No 11	460	3	4.8	3	3.3	85%	100%	3.8		MCC-F

FILE: RLWLE

PROJECT: Radioactive Liquid Waste Treatment Facility Refurbishment

DATE: 3/16/93

66	Primary HWS Pump No. 12	460	3	52	40	35.2	85%	100%	41.4		MCC-F
67	Standby Pump No. 13 (for #66)	460	3	52	(40)	(35.2)	85%	100%	(41.4)	Note 22	MCC-F
68											
69											
70											
71	Process Pumps (2)	460	3	11	7.5	14.9	85%	100%	17.5		EMCC-A
72	Process Pumps (13)	460	3	7.6	5	66.9	85%	100%	78.7		EMCC-A
73	Process Pumps (25)	460	3	4.8	3	81.3	85%	100%	95.6		EMCC-A
74	Process Chiller	460	3	221.		150.0	85%	100%	176.5		EMCC-A
75											
76	Ltg/Process Area (note 3)	277	1	104.		24.7	85%	100%	29.1		LP
77	Ltg/Tech Support/F1 (note 4)	277	1	65.9		15.5	85%	100%	18.3		LP
78	Ltg/Tech Support/B (note 5)	277	1	85.0		20.0	85%	100%	23.6		LP
79	Ltg/D&D Area/Office/Lab (note 6)	277	1	19.9		4.7	85%	100%	5.5		LP
80	Ltg/Computer/Control Rm (note 7)	277	1	11.0		2.6	85%	100%	3.1		LP
81	Ltg/Soil Lab (note 8)	277	1	8.66		2.0	85%	100%	2.4		LP
82	Ltg/Tank Storage (note 9)	277	1	79.7		18.8	85%	100%	22.1		LP
83	Ltg/Hot Warehouse (note 10)	277	1	9.02		2.1	85%	100%	2.5		LP
84	Ltg/Cold Warehouse (note 11)	277	1	16.2		3.8	85%	100%	4.5		LP
85	Ltg/Entry/Lobby (note 12)	277	1	9.95		2.3	85%	100%	2.8		LP
86	Ltg/Change Rooms (note 13)	277	1	11.5		2.7	85%	100%	3.2		LP
87	Ltg/Chemistry Lab (note 14)	277	1	48.1		11.3	85%	100%	13.4		LP
88	Ltg/D&D Area/Airlock (note 15)	277	1	13.4		3.2	85%	100%	3.7		LP
89	Ltg/Mech. Penthouse (note 16)	277	1	166.		39.2	85%	100%	46.1		LP
90	Ltg/HVAC Central Plant (note 17)	277	1	29.5		7.0	85%	100%	8.2		LP

FILE: RLWLE

PROJECT: Radioactive Liquid Waste Treatment Facility Refurbishment

DATE: 3/16/93

91	Exterior bldg. lgt. (note 18)	277	1	16.2	3.8	85%	50%	4.5	LP
92	Parking lighting (note 19)	277	1	4.87	1.1	85%	50%	1.4	LP
93									
94									
95									
96	Welding Receptacles (6)	460	3	60.0	40.6	85%	17%	47.8	PP
97	General Purpose Recep. (note 21)	120	1	201.	61.6	85%	30%	72.5	PP
98									
99									
100	Miscellaneous (note 23)	208/120	3	416.	127.7	85%	100%	150.2	PP
TOTAL		<u>480</u>	<u>3</u>	<u>3758</u>	<u>2655.8</u>	<u>85%</u>		<u>3124.5</u>	

FILE: RLWLE

PROJECT: Radioactive Liquid Waste Treatment Facility Refurbishment

DATE: 3/16/93

NOTES:

- (1) Conversion factor used for TONS of refrigeration is 1 TON = 1.0 KW.
- (2) FLA is at 480 volts 3 phase.
- (3) Lighting load is estimated at an average of 2 VA/SF for total area of 14,533 SF.
- (4) Lighting load is estimated at an average of 2 VA/SF for total area of 9,137 SF.
- (5) Lighting load is estimated at an average of 2 VA/SF for total area of 11,784 SF.
- (6) Lighting load is estimated at an average of 2 VA/SF for total area of 2,761 SF.
- (7) Lighting load is estimated at an average of 3 VA/SF for total area of 1,019 SF.
- (8) Lighting load is estimated at an average of 3 VA/SF for total area of 800 SF.
- (9) Lighting load is estimated at an average of 1 VA/SF for total area of 22,083 SF.
- (10) Lighting load is estimated at an average of 1 VA/SF for total area of 2,500 SF.
- (11) Lighting load is estimated at an average of 1 VA/SF for total area of 4,489 SF.
- (12) Lighting load is estimated at an average of 2 VA/SF for total area of 1,379 SF.
- (13) Lighting load is estimated at an average of 1 VA/SF for total area of 3,186 SF.
- (14) Lighting load is estimated at an average of 3 VA/SF for total area of 4,450 SF.
- (15) Lighting load is estimated at an average of 2 VA/SF for total area of 1,867 SF.
- (16) Lighting load is estimated at an average of 1 VA/SF for total area of 46,086 SF.
- (17) Lighting load is estimated at an average of 1 VA/SF for total area of 8,189 SF.
- (18) Assumed a total of 15-100 watt fixtures for security lighting around periphery of buildings.
- (19) Assumed a total of 15-150 watt pole mounted fixtures for parking areas.
- (20) TOTAL COOLING/BOILER LOAD includes HVAC chillers, A/C, and associated fans and pumps.
- (21) General purpose receptacle load, which includes connected appliances, PC's, etc., is estimated at an average of 1.8 VA/SF for a total of 134,263 SF of refurbished and new space.
- (22) Standby pumps are not added to the total load assuming that only one pump of each pair will run at any given time.
- (23) TOTAL MISC. LOAD includes power for controls, computers, fractional HP motors (such as fans), lab/shop equipment, and instrumentation. This load is estimated at an average of 1.5 VA/SF for total applicable area of 100,138 SF.
- (24) TOTAL PROCESS LOAD includes pumps and chiller.
- (25) A/C unit will be located in System 5 (Mechanical Penthouse/Supply Air) to serve the Computer Room located in System 8 (on first floor).

FILE: RLWPNL

PROJECT: Radioactive Liquid Waste Treatment Facility Refurbishment

DATE: 3/11/93

AREA/ROOM	AREA (SF)	EST TOTAL	EST KVA	EST AMPS	EST TOTAL	EST KVA	EST AMPS	SERVED BY	XFMR KVA	UPS KVA
		VA/SF 208Y/120V (NOTE 1)	208Y/120V (NOTE 1)	AT 208V/3PH	VA/SF 480/277V (NOTE 2)	480Y/277V (NOTE 2)	AT 460V/3PH			
Process Area 1/Bsmt	11,627	3.8	44.2	123	2.0	23.3	29	LP-A/PP-1A;	75	15
Process Area 2/1st Floor	2,906	3.8	11.0	31	2.0	5.8	7	PP-1B		
Tech. Support 1st Floor	9,137	3.8	34.7	96	2.0	18.3	23	LP-G/PP-7A;	45	
Tech. Support Area 2A Bsmt	4,676	3.8	17.8	49	2.0	9.4	12	LP-C/PP-3B	75	
Tech. Support Area 2B Bsmt	7,108	3.8	27.0	75	2.0	14.2	18	LP-D/PP-4A	75	
D&D Area 2/Office/Lab	2,761	3.8	10.5	29	2.0	5.5	7	LP-D/PP-4B		
Computer/Control Room	1,019	5.8	5.9	16	3.0	3.1	4	LP-H/PP-8	30	15
Soil Lab	800	4.8	3.8	11	3.0	2.4	3	LP-J/PP-10A	45	
Tank Storage 1	15,198	1.8	27.4	76	1.0	15.2	19	LP-C/PP-3A		
Tank Storage 2	6,885	1.8	12.4	34	1.0	6.9	9	LP-E/PP-5	30	
Hot Warehouse	2,500	1.8	4.5	12	1.0	2.5	3	LP-D/PP-4B		
Cold Warehouse	4,489	1.8	8.1	22	1.0	4.5	6	LP-F/PP-6	30	
Entry/Lobby	1,379	2.8	3.9	11	2.0	2.8	3	LP-G/PP-7B		
Change Rooms	3,186	1.8	5.7	16	1.0	3.2	4	LP-G/PP-7B		
Chemistry Lab	4,450	4.8	21.4	59	3.0	13.4	17	LP-J/PP-10B		
D&D Area 1/Airlock	1,867	1.8	3.4	9	2.0	3.7	5	LP-D/PP-4B		
Mechanical Penthouse	46,086	2.8	129.0	358	1.0	46.1	58	LP-L,M/PP-12,	4-75	
HVAC Central Plant	8,189 ?	2.8	22.9	64	1.0	8.2	10	LP-K/PP-11	45	
Exterior Bldg Ltg (note 3)	(NA)	(NA)	0.0	0	(NA)	9.0	11	Interior LP's		
Parking Lighting (note 3)	(NA)	(NA)	0.0	0	(NA)	7.5	9	Interior LP?		
TOTAL	134,263		393.6			204.8				

NOTES:

(1) Includes total general purpose receptacles, unit heaters, and miscellaneous loads.
See LOAD ESTIMATE for specifics.

(2) Includes 277 V lighting loads only. For specific estimated 460 V, 3 phase loads, see
LOAD ESTIMATE.

(3) Load values for kVA taken from LOAD ESTIMATE.

Radioactive Liquid Waste Collection System

Waste Treatment Facility

Pump

Valve

Truck Transport

TA-13
South Mesa Site

Lab shops

Chemistry
metallurgy
research (CMR)

Weapons Test
Support

Cryogenics

Materials
technology

Unloading
Station

TA-48
Radiochemistry Site

TA-50
Waste
Management
Site

TA-43

TA-16
S Site

TA-35
Ten Site

Dewatered, packaged
precipitate to
burial or storage
at TA-54

TA-3

TA-59
Occupational
Health and
Environment

TA-21
DP Site

Burial at
TA-54
Los Alamos
Canyon

TA-2
Omega Site

TA-55
Plutonium
Processing

TA-50

Meson
Physics
Facility

TA-50-1,
RMs 16 & 116

Treated waste
to Mortandad
Canyon

Lagoon

LEGEND:

---	RADIOACTIVE LIQUID WASTE
---	ELECTRICAL
---	GAS
---	LAB COMMUNICATIONS
---	STORM DRAINS
---	SEWERS
---	TELEPHONE

RADIOACTIVE LIQUID
WASTE TREATMENT
PLANT REFURBISHMENT
EXISTING UTILITIES

F. SCHEDULE

EARLY START	EARLY FINISH	REM DUR	PCT			
				1992	1993	1994
2SEP92		0	0	◇ PROJECT START		
1NOV92	31MAY93	212	0	[] FUNCTIONAL & OPERATIONAL REQUIRE		
20MAR93	19MAR93	0	0	◇ CDR/DESIGN CRITERIA/AE AWARD		
1APR93	30JUN93	91	0	[] CONCEPTUAL DESIGN PLAN		
18APR93	6JUL93	80	0	[] SWMU CHAR/NON-INSTRUSIVE CHAR		
1JUN93	30SEP93	122	0	[] KD#0 ESAAB PROCESS		
1JUN93	30NOV93	183	0	[] SELECT EIS CONTRACTOR		
7JUL93	3MAR94	240	0	[] PERFORM INSTRUS		
7JUL93	3MAR94	240	0	[] PERFORM INTRUSI		
1OCT93	30SEP93	0	0	◇ KD#0 HQ APPROVAL		
1OCT93	30NOV93	61	0	[] MOBILIZE FOR CONCEPT		
1DEC93	30NOV93	0	0	◇ START CONCEPTUAL DES		
1DEC93	30NOV94	365	0	[]		
1DEC93	30SEP96	1035	0	[]		
1MAR94	3MAR94	3	0	[] 30% CD PRESENTA		
4MAR94	2MAY94	60	0	[] PREP VOLUNT		
4MAR94	29OCT94	240	0	[]		
3MAY94	21JUL94	80	0	[] EPA R/A		
1JUN94	3JUN94	3	0	[] 60% CD PR		
1JUN94	5JUN94	5	0	[] VALUE ENG		
5JUN94	31AUG94	88	0	[] INCO		
22JUL94	18NOV94	120	0	[]		
1SEP94	3SEP94	3	0	[] 100%		
1SEP94	31OCT94	61	0	[]		
3SEP94	31OCT94	59	0	[]		
30OCT94	26JUN95	240	0	[]		
1NOV94	30NOV94	30	0	[]		
1DEC94	30NOV94	0	0	[]		
1DEC94	31DEC94	31	0	[]		
1DEC94	28FEB95	90	0	[]		
31DEC94	30DEC94	0	0	[]		
1JAN95	28FEB95	59	0	[]		
1FEB95	15APR95	74	0	[]		

1994	1995	1996	1997	1998
REQUIREMENTS				
VE CHAR				
IS				
CONTRACTOR				
INTRUSIVE STUDY-NEW CONSTRUCTION				
INTRUSIVE STUDIES-EXIST FACILITY				
CONCEPTUAL DESIGN				
TUAL DESIGN				
PSAR (PRELIMINARY DRAFT)				
NEPA PROCESS				
PRESENTATION				
VOLUNTARY CORRECTIVE ACTION PLAN-NEW CONSTR				
PREP CORRECTIVE MEASURES STUDY-EXIST FACILITY				
EPA R/A VOLUNTARY CORRECTIVE ACTION PLAN-NEW CON				
% CD PRESENTATION				
BLUE ENGINEERING SESSION				
INCORPORATE VE PROPOSALS				
PERFORM SWMU VOL CORRECTIVE ACTION PLAN-NEW CONS				
100% CD PRESENTATION/REVIEW SUBMITTAL				
AL CD REVIEW				
CD PEER REVIEW				
EPA R/A CORRECTIVE MEASURES STUDY-EXIST FAC				
INCORPORATE AL REVIEW COMMENTS				
100% CD SUBMITTAL TO AL				
AL/PMD COMPLIANCE REVIEW				
PROJECT PLAN/CHARTER/PMP				
CDR SUBMITTED TO HQ				
ICE REVIEW				
JUSTIFICATION/VALIDATION REVIEWS				

98	1999	2000	2001	2002
----	------	------	------	------

From Milestone Activity:
Project Authorization

EARLY START	EARLY FINISH	REM DUR	PCT	1997											
				DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV
1JAN97	30JUN97	129	0												
1JAN97	30JUN97	129	0												
2JAN97	1SEP97	66	0												
30SEP97	28SEP97	0	0												
15OCT97	15OCT98	262	0												
15OCT97	15OCT98	262	0												
15OCT98	21JAN99	71	0												
1FEB99	29JAN99	0	0												
1MAR99	30JUN99	90	0												
1JUL99	31DEC99	132	0												
1JUL99	1JUN01	383	0												
1JUL99	1JUN01	383	0												
1JUL99	1JUN01	393	0												
1JAN01	28FEB01	43	0												

PEAR DRAFT

TITLE I DES

[illegible]

1FEB95	15APR95	74	0
1MAR95	30JUN95	122	0
1APR95	30APR95	30	0
1JUL95	30NOV95	153	0
31JUL95	30JUL95	0	0
1NOV95	28FEB96	120	0
1MAR96	29FEB96	0	0
1MAR96	31MAR96	31	0
1APR96	31JUL96	122	0
1APR96	30SEP96	183	0
1OCT96	30SEP96	0	0
1JAN97	30SEP97	273	0
1JAN97	30SEP97	273	0
1SEP97	30NOV97	91	0
1JAN98	31DEC97	0	0
15JAN98	15JUN99	517	0
15JAN98	15JUN99	517	0
15JUN99	30SEP99	108	0
1OCT99	30SEP99	0	0
1NOV99	28FEB00	120	0
29FEB00	22MAY00	84	0
29FEB00	14AUG00	168	0
29FEB00	13OCT00	228	0
29FEB00	9OCT07	2780	0
29FEB00	9OCT07	2780	0
1MAR00	28MAR00	28	0
23MAY00	14AUG00	84	0
23MAY00	14AUG00	84	0
15AUG00	6NOV00	84	0
15AUG00	6NOV00	84	0
15AUG00	29JAN01	168	0
15AUG00	23APR01	252	0
15AUG00	16JUL01	336	0
14OCT00	5JAN01	84	0
14OCT00	11JAN01	90	0
14OCT00	22JUN01	252	0
14OCT00	22JUN01	252	0
7NOV00	5JAN01	60	0
7NOV00	6MAR01	120	0
6JAN01	22JUN01	168	0

ICE REVIEW

☐ JUSTIFICATION/VALIDATION REVIEWS

☐ KD#1 ESAAB PROCESS

☐ HQ REVIEWS VALIDATION SHEETS

☐ HQ VALIDATION CONFIRMATION

◇ KD#1 HQ APPROVAL

☐ OMB DEVELOPMENT

◇ CONGRESSIONAL APPROVAL

☐ IRB WILL KNOW BUDGET

☐ DESIGN CRITERIA DEVELOPMENT

☐ AE SELECTION

◇ PROJECT AUTHORIZATION/BEGIN PRETREATMENT PLANT

☐ PSAR (DRAFT)

☐ TITLE I DESIGN AND REVI

☐ KD#2 ESAAB PROCESS

◇ KD#2 HQ APPROVAL

☐

☐

JUL99	1JAN01	383	0
1JAN01	28FEB01	43	0
1MAR01	31OCT01	175	0
31OCT01	31JAN02	87	0
15FEB02	14FEB02	0	0
28FEB02	27FEB02	0	0
Plot Date 23JUN93 Data Date 1JAN97 Project Start 1JAN97 Project Finish 27FEB02			
Activity Bar/Entry Date Original Activity Program Bar Milestone/Tag Activity			
[c] Primavera Systems, Inc.			

PLANT ACTIVITIES

D REVIEW

CESS

PROVAL

PSAR (FINAL)

TITLE II DESIGN AND REVIEW

KD#3 ESAAB PROCESS

◇KD#3 HQ APPROVAL

CONTRACTOR BID/AWARD

REMOVE EXIST. SUB-STA. & PROVIDE TEMP. PWR.

PRELIMINARY SITE WORK: EXISTING AND NEW UTILI

SEISMICALLY HARDEN EXIST STRUCTURE/REMEDI.

D&D/FILL EXISTING FEED TANK

PRELIMINARY SITE WORK: CUT AND HAUL

DEMOLISH AND REMOVE BUILDING APPENDAGES

CONSTRUCT NEW TANK FOUNDATIONS SOUTH

CONSTRUCT SUPPORT FOUNDATIONS FOR 2nd FL

CONSTRUCT NEW TANK FOUNDATIONS (NOF

CONSTRUCT COLD WAREHOUSE

CONSTRUCT HVAC CENTRAL PL

CONSTRUCT UTILITY TUNNEL

CONSTRUCT ENTRY/LOBBY AREA

CONSTRUCT HOT WAREHOUSE

CONSTRUCT TRUCK D&D AIRLOC

CONSTRUCT NEW STORAGE TANKS (SOUTH)

CONSTRUCT SUPPORTS FOR 2nd FLOOR

CONSTRUCT CHANGE ROOM AREA

LOS ALAMOS NATIONAL LABORATORY
PRETREATMENT PLANT CONSTR SEQUENCE
ACTIVITY BAR CHART

W UTILITIE
/REMEDIAE

S
UTH
2nd FLOOR
NS (NORTH)
E
TRAL PLANT

OUSE
AIRLOCK
SOUTH)
FLOOR
CM 1.74

FSAR PRETREATMENT

START-UP/OPR PRETREATMENT

KD#4 ES&AS PROCESS PRETREATMENT

KD#4 HQ APPROVAL PRETREATMENT

BEGIN OPERATIONS PRETREATMENT

Page 1 of 1

ICF KAISER ENGINEERS, INC.

Date	Revision	Checked	Approved

To Milestone Activity:
Begin Operations
Pretreatment Plant

FSAR

TITLE III

14OCT00	5JAN01	84	0
14OCT00	11JAN01	90	0
14OCT00	22JUN01	252	0
14OCT00	22JUN01	252	0
7NOV00	5JAN01	60	0
7NOV00	6MAR01	120	0
6JAN01	22JUN01	168	0
6JAN01	20CT01	270	0
30JAN01	28JUL01	180	0
27FEB02	26FEB02	0	0
14MAR02	8DEC02	270	0
9DEC02	4SEP03	270	0
5SEP03	2SEP04	364	0
30CT03	31DEC03	90	0
31OCT03	22JAN04	84	0
3SEP04	17FEB05	168	0
18FEB05	18MAY05	90	0
19MAY05	2NOV05	168	0
3NOV05	31JAN06	90	0
1FEB06	10OCT06	252	0
11OCT06	9OCT07	364	0
20JUN07	9OCT07	112	0
20JUN07	9OCT07	112	0
10OCT07	10DEC07	62	0
11DEC07	8NOV08	334	0
9NOV08	8FEB09	92	0
19FEB09	18FEB09	0	0
1MAR09	28FEB09	0	0

Plot Date 23JUN93
Data Date 2SEP92
Project Start 1SEP92
Project Finish 28FEB09

Activity Bar/Early Dates
Critical Activity
Progress Bar
Milestone/Flag Activity
Remediation Activity

RLWT

(c) Primavera Systems, Inc.

WT

LOS ALAMOS NATIONAL LABORATORY
RLWTF CONSTRUCTION SEQUENCE
ACTIVITY BAR CHART

BY AREA
HOT WAREHOUSE
TRUCK D&D AIRLOCK
GE TANKS (SOUTH)
TS FOR 2nd FLOOR
CHANGE ROOM AREA
STRUCT CHEM LAB AREA
CT NEW STORAGE TANKS (NORTH)
◇ BEGIN OPERATIONS PRETREATMENT PLANT
[REDACTED] DECON GRIT CHAMBER AND REMEDIATE
[REDACTED] DECON/REMEDiate RMS 60/60A (INCLD'S UNDRGR TANK)
[REDACTED] INSTALL PROCESS PIPING AND EQUI
[REDACTED] ERECT BLDG. OVER STORAGE TANKS (NORTH)
[REDACTED] ERECT BLDG. OVER STORAGE TANKS (SOUTH)
[REDACTED] D&D 1st FLOCCULATOR A
[REDACTED] INSTALL 1st REPL
[REDACTED] D&D 2r
[REDACTED]
INSTALL NEW MECH./ELEC. EQUIPMENT
REMOVE AND REPLA
REMOVE AND REPLACE

ANK)
AND EQUIPMENT

H)
ULATOR AND REMEDIATE

1st REPLACEMENT FLOCCULATOR AND CONNECT

D&D 2nd EXISTING FLOCCULATOR AND REMEDIATE

INSTALL 2nd REPLACEMENT FLOCCULATOR AND CONNECT

CONSTRUCT 2nd FLOOR SHELL

EQUIPMENT ON 2nd FLOOR

AND REPLACE MECH./ELEC. IN PLANT AREA

REPLACE MECH./ELEC. IN OFFICE AREAS

SAR

START UP/ORR

KD#4 ESAAB PROCESS

KD#4 HQ APPROVAL ◇

BEGIN OPERATIONS ◇

Sheet 1 of 1

ICF KAISER ENGINEERS, INC.

Date	Revision	Checked	Approved