DISTRIBUTION SHEET

To Analytical Services	From Characterization Support	Page 1 of 1
		Date 8-26-94
Project Title/Work Order Tank 241-AX-102 Tank Characterization Plan (WHC-SD-WM-TP-227)		EDT No. 159070
		ECN No. N/A

Name	MSI N	Text With All Attac h.	Text Only	Attach. / Append ix Only	EDT/E CN Only
------	----------	------------------------------------	--------------	--------------------------------------	---------------------

ONSITE

MACTEC

K. S. Redus	B1-42	X			
-------------	-------	---	--	--	--

Pacific Northwest Laboratories

S. F. Bobrowski	K7-28	X			
S. G. McKinley	P7-22	X			

Westinghouse Hanford Company

H. Babad	S7-30	X			
K. E. Bell	T6-06	X			
D. R. Bratzel	S7-31	X			
B. C. Carpenter	R2-12	X			
J. L. Deichman	H4-19	X			
D. W. Hamilton	S7-03	X			
K. K. Keller	S1-57	X			
J. M. Kier	H4-19	X			
J. G. Kristofzski	T6-06	X			
P. M. Morant	H4-19	X			
R. D. Schreiber (10)	R2-12	X			
T. C. Tribble	S1-57	X			
W. F. Zuroff	S7-12	X			
OSTI (2)	L8-04	X			
Central Files					

STA 4
AUG 26 1994

ENGINEERING DATA TRANSMITTAL

Page 1 of 1
1. EDT 159070

2. To: (Receiving Organization) ANALYTICAL SERVICES		3. From: (Originating Organization) TWSR/CHARACTERIZATION SUPPORT		4. Related EDT No.: N/A				
5. Proj./Prog./Dept./Div.: TWSR ENG/CHAR SUPPORT		6. Cog. Engr.: B. C. CARPENTER		7. Purchase Order No.: N/A				
8. Originator Remarks: N/A				9. Equip./Component No.: N/A				
				10. System/Bldg./Facility: 2750E/200E				
11. Receiver Remarks:				12. Major Assm. Dwg. No.: N/A				
				13. Permit/Permit Application No.: N/A				
				14. Required Response Date: 08-19-94				
15. DATA TRANSMITTED								
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	(F) Approval Impact Level Designator	(G) Reason for Transmittal	(H) Originator Disposition	(I) Receiver Disposition
1	WHC-SD-WM-TP-227		0	TANK 241-AX-102 TANK CHARACTERIZATION PLAN	Q	1		

16. KEY									
Impact Level (F)		Reason for Transmittal (G)				Disposition (H) & (I)			
1, 2, 3, or 4 (see MRP 5.43)		1. Approval 4. Review 2. Release 5. Post-Review 3. Information 6. Dist. (Receipt Acknow. Required)				1. Approved 4. Reviewed no/comment 2. Approved w/comment 5. Reviewed w/comment 3. Disapproved w/comment 6. Receipt acknowledged			
(G)	(H)	17. SIGNATURE/DISTRIBUTION (See Impact Level for required signatures)						(G)	(H)
Reason	Disp.	(J) Name	(K) Signature (M) MSIN	(L) Date	(J) Name	(K) Signature (M) MSIN	(L) Date	Reason	Disp.
1	1	Cog. Eng. B. C. CARPENTER	<i>B. C. Carpenter</i>	8/24	Proj. D. R. BRATZEL	<i>D. R. Bratzel</i>	8/23/94	1	1
1	1	Cog. Mgr. C. S. HALLER	<i>C. S. Haller</i>	8/22	Proj. S. G. MCKINLEY	<i>S. G. McKinley</i>	8/25/94	1	1
1	1	QA T. C. TRIBLE	<i>T. C. Tribble</i>	8/26/94	Proj. D. W. HAMILTON	<i>D. W. Hamilton</i>	8/25/94	1	1
		Safety			Proj. J. G. KRISTOFZSKI	<i>J. G. Kristofzski</i>	8/25/94	1	1
		Env.							

18. B. C. CARPENTER <i>B. C. Carpenter</i> Signature of EDT Date 8/24/94 Originator		19. <i>J. L. Deichman</i> J. L. DEICHMAN Authorized Representative Date 8/24/94 for Receiving Organization		20. <i>C. S. Haller</i> C. S. HALLER Cognizant/Project Date 8/22 Engineer's Manager		21. DOE APPROVAL (if required) Ltr. No. ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments	
---	--	--	--	---	--	--	--

BD-7400-172-2 (07/91) GEF097

BD-7400-172-1 (02/89)

RELEASE AUTHORIZATION

Document Number: WHC-SD-WM-TP-227 REVISION 0

Document Title: TANK 241-AX-102 TANK CHARACTERIZATION PLAN

Release Date: 08-26-94

* * * * *

This document was reviewed following the
procedures described in WHC-CM-3-4 and is:

APPROVED FOR PUBLIC RELEASE

* * * * *

WHC Information Release Administration Specialist:

Jamara John for Chris Willingham

C. WILLINGHAM

(Signature)

08-26-94

(Date)

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

JKE 8/26/94

SUPPORTING DOCUMENT		1. Total Pages 21 22
2. Title TANK 241-AX-102 TANK CHARACTERIZATION PLAN	3. Number WHC-SD-WM-TP-227	4. Rev No. 0
5. Key Words CHARACTERIZATION, DQO, SAFETY SCREENING, QUALITY CONTROL, SINGLE-SHELL TANK, SAMPLING, ANALYSIS, TANK CHARACTERIZATION PLAN <i>1LK 8/26/94</i>	6. Author Name: B. C. CARPENTER <i>Brad Carpenter</i> Signature Organization/Charge Code 7E720/N444Y	
7. Abstract This document is a plan which serves as the contractual agreement between the Characterization Program, Sampling Operations, WHC 222-S Laboratory, and PNL 325 Analytical Chemistry Laboratory. The scope of this plan is to provide guidance for the sampling and analysis of auger samples from tank 241-AX-102.		
8. PURPOSE AND USE OF DOCUMENT - This document was prepared for use within the U.S. Department of Energy and its contractors. It is to be used only to perform, direct, or integrate work under U.S. Department of Energy contracts. This document is not approved for public release until reviewed. PATENT STATUS - This document copy, since it is transmitted in advance of patent clearance, is made available in confidence solely for use in performance of work under contracts with the U.S. Department of Energy. This document is not to be published nor its contents otherwise disseminated or used for purposes other than specified above before patent approval for such release or use has been secured, upon request, from the Patent Counsel, U.S. Department of Energy Field Office, Richland, WA. DISCLAIMER - This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.		10. RELEASE STAMP <div style="border: 1px solid black; padding: 5px; text-align: center;"> OFFICIAL RELEASE BY WHC DATE AUG 26 1994 <i>STA 4</i> </div>
Approval Designator 9. Impact Level Q		

MASTER

WHC-SD-WM-TP-227
Revision 0

Tank 241-AX-102 Tank Characterization Plan

Prepared for the U.S. Department of Energy
Office of Environmental Restoration
and Waste Management

CONTENTS

SAMPLE EVENT A: AUGER SAMPLING IN FISCAL YEAR 1994

LIST OF TABLES	ii
LIST OF FIGURES	ii
LIST OF ACRONYMS	ii
1.0 SPECIFIC TANK CHARACTERIZATION OBJECTIVES	1
1.1 Tank Safety Screening Data Quality Objectives	1
1.2 Relevant Safety Information	2
1.2.1 Tank Status	2
1.2.2 Tank Monitoring Activities	2
2.0 SUMMARY OF HISTORICAL INFORMATION FOR TANK AX-102	3
2.1 Configuration	3
2.2 Process History	3
2.3 Historical Sampling Events	3
3.0 SCHEDULED SAMPLING EVENT	6
3.1 Sample Collection and Transport	6
3.2 Tank-Specific Analytical Procedures	6
3.2.1 Hot Cell Sample Isolation and Analysis Scheme	6
3.2.2 Prioritization of Requested Analyses	10
3.2.3 Analytical Methods	10
4.0 QUALITY ASSURANCE/QUALITY CONTROL	11
4.1 Sampling Operations	11
4.2 Laboratory Operations	11
5.0 ORGANIZATION	14
6.0 EXCEPTIONS, CLARIFICATIONS, AND ASSUMPTIONS	14
6.1 Exceptions to DQO Requirements	14
6.2 Clarifications and Assumptions	14
7.0 DELIVERABLES	15
7.1 Format I Reporting	15
7.2 Format III Reporting	16
8.0 CHANGE CONTROL	16
9.0 REFERENCES	17

LIST OF TABLES

Table 1a. Analytical Results for Tank AX-102 Sludge Samples.	5
Table 1b. Analytical Results for Tank AX-102 Supernatant Samples.	6
Table 2. AX-102 Auger Sample Chemical, Physical, and Radiological Analytical Requirements	13
Table 3: Tank AX-102 Project Key Personnel List.	14

LIST OF FIGURES

Figure 1: Process History of Tank 241-AX-102.	4
Figure 2: Test Plan Flowchart for Tank Safety Screening.	9

LIST OF ACRONYMS

ACL	Analytical Chemistry Laboratory
AX-102	tank 241-AX-102
CASS	Computer Automated Surveillance System
CC	Concentrated Complexant
DNFSB	Defense Nuclear Facility Safety Board
DOE	Department of Energy
DQO	data quality objective
DSC	differential scanning calorimetry
DST	double-shell tank
ICP	inductively-coupled plasma
PUREX	Plutonium-Uranium Extraction
RSST	reactive system screening tool
SST	single-shell tank
TCP	Tank Characterization Plan
TGA	thermogravimetric analysis
TIC	total inorganic carbon
TPA	Tri-Party Agreement
TOC	total organic carbon
TWRS	Tank Waste Remediation System
USQ	unreviewed safety question
WHC	Westinghouse Hanford Company

TANK 241-AX-102 TANK CHARACTERIZATION PLAN

1.0 SPECIFIC TANK CHARACTERIZATION OBJECTIVES

The Defense Nuclear Facilities Safety Board has directed the DOE to concentrate the near-term sampling and analysis activities on identification and resolution of safety issues (Conway 1993). The data quality objective (DQO) process was chosen as a tool to be used to identify sampling and analytical needs for the resolution of safety issues. As a result, a revision in the Federal Facility Agreement and Consent Order (TPA) milestone M-44-00 has been made, which states that "A Tank Characterization Plan (TCP) will also be developed for each DST and SST using the DQO process...Development of TCPs by the DQO process is intended to allow users (e.g., Hanford Facility user groups, regulators) to ensure their needs will be met and that resources are devoted to gaining only necessary information." This document satisfies this requirement for the tank 241-AX-102 (AX-102) fiscal year 1994 safety screening activity.

This Tank Characterization Plan will identify characterization objectives pertaining to sample collection, hot cell sample isolation, and laboratory analytical evaluation and reporting requirements in accordance with the *Tank Safety Screening Data Quality Objective* (Redus and Babad 1994), in addition to reporting the current contents and status of the tank as projected from historical information.

1.1 Tank Safety Screening Data Quality Objectives

There are four Watch List tank classifications with safety issues related to public and worker health that have been associated with the Hanford Site underground storage tanks: ferrocyanide, organic, flammable gas, criticality, high heat, and vapor (Babad 1992). Of the 149 single-shell (SSTs) and 28 double-shell tanks (DSTs), 52 are currently classified on one or more of the watch lists (Hanlon 1994).

The *Tank Safety Screening Data Quality Objective* (Redus and Babad 1994) describes the sampling and analytical requirements that are used to screen waste tanks for unidentified safety issues. Both Watch List and non-Watch List tanks will be sampled and evaluated to identify safety conditions related to the ferrocyanide, organic, flammable gas, and criticality safety issues. Safety screening for high heat tanks has already been completed and the vapor safety issue will be handled by ongoing industrial hygiene programs.

With respect to sampling specifications, this DQO requires that "a vertical profile of the waste be obtained from at least two widely-spaced risers...assuming the quality of the data obtained supports appropriate safety classification of the tank. Such sampling can be done by core drilling, by auger sampling (for shallow tanks) and/or by obtaining liquid supernate samples at several levels" (Redus and Babad 1994). Tank AX-102 contains a shallow depth and high-solids waste that will be sampled for safety screening purposes using the auger sampling method.

The analytical requirements for the safety screening of a tank are concerned with identifying a common set of primary analytes and characteristics of the waste. These analytes are energetics, total alpha activity, moisture and flammable gas concentrations. If a specific criteria level on one of these items is exceeded, further analysis of a secondary set of analytes and a possible Watch-List tank classification would be warranted. Further details of the analytical procedures and criteria to be followed for this tank AX-102 sampling and characterization event are given in Section 3.2.

This Tank Characterization Plan identifies procedures and requirements, in accordance with the safety screening DQO and the Characterization Program, for collecting and characterizing a sample from tank AX-102 by the auger sampling method. The dome-space gas flammability determination is being handled separately by the Tank Vapor Issue Resolution Program.

1.2 Relevant Safety Information

1.2.1 Tank Status

Single-shell tank AX-102 is classified as a Non-Watch List low heat load tank (<40,000 Btu/hr). In 1988 tank AX-102 was identified as an assumed leaker and interim stabilized by supernatant pumping. To prevent further waste additions to the tank, it has been isolated and designated as an Intrusion Prevention tank.

Tank AX-102 is reported as containing approximately ten inches of waste material which consists of 29 thousand gallons of saltcake, seven thousand gallons of sludge, and three thousand gallons of supernatant liquid for a total of 39 thousand gallons (Hanlon 1994). Results obtained from the CASS database are variable and indicate a waste depth of 7.5-14 inches with the most recent reading at 9.5 inches. A 10 inch depth corresponds to a maximum waste volume in tank AX-102 of 27,500 gallons. Its contents are categorized as concentrated complexant waste material (CC).

1.2.2 Tank Monitoring Activities

All 18 thermocouples on the single thermocouple tree in tank AX-102 are positioned above the solids level and in the vapor space. The temperature of the waste from the lowest (in depth) thermocouple in tank AX-102 was recorded at 115°F in January 1994. The waste surface level is measured by a manual tape. Nine active dry wells, installed in 1970, monitor radiation in the surrounding soil (Hanlon 1993).

2.0 SUMMARY OF HISTORICAL INFORMATION FOR TANK AX-102

Included in this section are descriptions of tank AX-102, its process history, and recorded sampling events.

2.1 Configuration

Tank AX-102 is one of 4 single-shell tanks in the 200 East area AX Farm constructed during 1963-64. It is 75 feet in diameter with a flat bottom and has a 1,000 kgal (3,790 m³) tank capacity. Tank AX-102 is passively ventilated and does not cascade with any other of the AX Farm tanks. Ten of the 58 risers are available for use.

2.2 Process History

Tank AX-102 began receiving PUREX high level and organic wash waste in the third quarter of 1966 and continued to receive these wastes until the fourth quarter of 1968, when it was declared a spare tank. In the first quarter of 1969 through the third quarter of 1975, the tank received B Plant high level waste. From the fourth quarter of 1975 to the second quarter of 1976, the tank was sluiced to recover strontium and cesium. From the third quarter of 1976 until the second quarter of 1977, the tank received evaporator feed. In 1977, a P-10 pump was installed to later be used for supernatant pumping. From the third quarter of 1977 to the first quarter of 1978, the tank received residual liquor from the 242-A evaporator. From the second quarter of 1978 to 1980 the tank received either complexant waste or concentrated complexant waste.

In 1980, the tank was declared inactive. During 1982, intrusion prevention status was achieved. A level adjustment was made in the fourth quarter of 1983. In 1988, the tank was declared an assumed leaker from an estimated leak to the surrounding soils of 3,000 gallons and it was immediately interim stabilized by supernatant pumping. Figure 1 summarizes the waste transfer history and waste levels.

2.3 Historical Sampling Events

Historical data is available from five samples retrieved from tank AX-102 in September 1974, July 1977, January 1980, February 1980, and November 1988. The latter two samples are the most complete and occurred after the last waste additions. However, they are supernatant samples and since much of the supernatant has been removed these results are given less significance. The sludge samples taken in 1974 and 1977 have limited data but are viewed to be more closely representative of the present tank contents. The sludge sample results are given in Table 1a.

Table 1a. Analytical Results for
Tank AX-102 Sludge Samples.

Sample Date	1974	1977
Sample Description	Soft Reddish Brown Sludge	Dark Reddish Brown Sludge
Wet Density	1.57 g/ml	
Dry Density	0.9025 g/ml	
Component	Concentration ($\mu\text{g/g}$)	
Ba	100	--
Ca	5,200	--
Mg	700	--
Mn	7,700	--
Fe	91,000	--
Si	22,000	--
Wt% H ₂ O	42.5%	--
Component	Concentration ($\mu\text{Ci/L}$)	
¹³⁷ Cs	4.78E+2	6.5E+5
⁸⁹⁺⁹⁰ Sr ($\mu\text{Ci/L}$)	9.31E+6	1.7E+7
⁶⁰ Co	1.31E+4	nf
¹²⁵ Sb	1.51E+5	6.2E+5
¹⁴⁴ Ce ¹⁴⁴ Pr	2.38E+7	1.4E+6*
¹⁵⁴ Eu	3.51E+5	nf
Pu (g/L)	6.71E-2	8.8E-2

*¹⁴⁴Ce results only.

Results from a supernatant sample taken in August 1988 indicate a high level of sodium, carbonate, organic carbon, nitrate, nitrite, and sulfate (see Table 1b). With the exception of carbonate compounds, these analytes are very soluble and are likely less concentrated in the solids.

Table 1b. Analytical Results for Tank AX-102 Supernatant Samples.

Component	Concentration ($\mu\text{g/g}$)**
pH	1.13E+1
Na	1.70E+5
CO ₃	5.90E+4
TOC	3.70E+4
NO ₃	2.30E+5
NO ₂	6.40E+4
SO ₄	1.60E+4

**These values were converted from molar concentrations by assuming a bulk density of 1 g/ml.

3.0 SCHEDULED SAMPLING EVENT

3.1 Sample Collection and Transport

In fiscal year 1994, tank AX-102 auger samples will be taken from risers 3A and 9E. Eight inches of sludge (approximately 300 g) are expected to be recovered from each auger sample. No drainable liquids are expected to be recovered; however, some liquids may be contained in the waste. A field/trip blank is not required since this sampling event is not in support of any regulatory issues (Zuroff 1994). For specific information concerning sample handling, custody, and transport refer to quality assurance/quality control requirements in Section 4.1. Documents which contain applicable operating procedures and chain of custody requirements for the AX-102 auger sampling activities are procedure TO-080-500 and work package 2E-94-00701.

3.2 Tank-Specific Analytical Procedures

Any decisions, observations, or deviations to this characterization plan made during sample receipt, isolation, and analysis will be documented in the deliverable report.

3.2.1 Hot Cell Sample Isolation and Analysis Scheme

Before sample removal and breakdown begins, H. Babad or another delegate of the Characterization Program should be contacted so that they may be present to observe the sample breakdown. Because of the limited turn-around time for the safety screening analyses, the laboratory will not delay sample breakdown more than 4 hours to accommodate program observers. The sample isolation and breakdown procedure will follow guidelines provided in this Tank Characterization Plan.

A flowchart showing the general safety screening sample breakdown and analysis scheme is presented as Figure 2. The AX-102 auger samples are to be prepared and analyzed in accordance with this scheme, assuming adequate sample exists to perform all the analyses. These analysis requirements are prioritized (see section 3.2.2) and should be performed accordingly if insufficient sample is recovered. If necessary, the laboratory may make modifications to this breakdown. Sample receipt, custody, preparation, and analysis shall be performed in accordance with approved procedures.

- Step 1 Receive auger samples at the performing laboratory.
- Step 2 Isolate and break down auger samples in the hot cell. Record visual observations of physical properties such as sample color, texture, homogeneity, and consistency. Note the color and clarity of any drainable liquid. Take a color photograph or videotape of the isolated samples.
- Step 3A If the auger contains any drainable liquid, proceed to Step 3B. If no drainable liquid is present go to Step 4A.
- Step 3B Separate the drainable liquid from the solids by allowing the liquid to drain into a bottle. Measure and record the volume of liquid. Retain the liquids for further analyses.
- Step 3C Report any visually observed potential organic layers immediately by the early notification system (Format I). Separate and retain the potential organic layer for possible future analysis. Proceed to Step 4A.
- Step 4A Inspect the top portion of the auger sample for a hard, dry layer. If present continue to step 4B, otherwise go to step 5.
- Step 4B Separate the hard, dry layer and retain for analysis. Go to Step 5.
- Step 5 Separate remaining auger sample into two equal subsamples.
- Step 6 Homogenize each subsample individually.
- Step 7 Filter the aqueous sample through a 0.45 micron filter. Retain liquid subsample for safety screening analyses.
- Step 8 Remove aliquots from each homogenized subsample obtained in Steps 3A through 5. Retain enough sample to perform each analysis in Table 2 except RSST adiabatic calorimetry. Secure and retain any remaining subsamples until analyses are complete.
- Step 9 Perform DSC/TGA analysis on each undried solid subsample and liquid sample in duplicate. Perform total alpha analysis in duplicate on a fusion dissolution of each solid aliquot only; total alpha analysis is not required on the liquid aliquot.

- Step 10A Analyze DSC/TGA scans and total alpha results. Do the DSC/TGA results exceed the established safety criteria limits? Do the total alpha results exceed the established safety criteria limits (see Table 2, Notification Limits)? If the answer is no for either question, go to step 10B. If yes to both questions, then proceed to Step 11.
- Step 10B Report results exceeding notification limits as described in the format I reporting deliverable requirements (see Section 7.1). Proceed to the following steps (10C, etc...).
- Step 10C Perform analyses for secondary analytes.
 - If the DSC safety criteria limit was exceeded, perform micro cyanide distillation and hot persulfate TOC analyses on each solid and liquid aliquot in duplicate. In addition, perform RSST adiabatic calorimetry analysis¹.
 - If the total alpha safety criteria limit was exceeded, determine radiological activity due to the presence of ^{239/240}Pu on each solid and liquid aliquot in duplicate. Also, determine Iron, Manganese, and Uranium concentrations by Inductively Coupled Plasma (ICP) analysis.
- Step 10D Are the results of analyses for secondary analytes within safety criteria limits? If not go to step 10E, if the answer is yes proceed to step 11.
- Step 10E Report results for the secondary analytes exceeding notification limits as described in the format I reporting deliverable requirements (see Section 7.1).
- Step 11 Archive remaining sample. Any subsamples remaining from crust/sludge/liquid separations should be archived in separate containers (Bratzel 1994).
- Step 12 Deliver a Format III Report that characterizes the results of the safety screening for primary analytes within 45 days of receipt of the last sample at the laboratory loading dock. Follow the Format III Reporting requirements provided in Section 7.2.
- Step 13 Following the same reporting requirements, deliver a Format III Report that characterizes the results of the safety screening for secondary analytes within 90 days of receipt of the last sample at the laboratory loading dock (required only if any primary analytes exceeded notification limits).

¹ RSST, if necessary, shall be performed at the 222-S Laboratory from an archived subsample which shows a DSC exotherm.

Figure 2: Test Plan Flowchart for Tank Safety Screening.

3.2.2 Prioritization of Requested Analyses

A list of analyses to be performed for tank safety screening is provided in preferential order in Table 2. However, if the amount of sample recovered is found to be insufficient to perform each analyses in Table 2, Characterization Support and Analytical Services shall be notified (for points of contact, see Section 5.0, Table 3). Confirmation of the prioritization levels or revision of sample breakdown procedures will be provided based upon the sample recovery, readily observable physical property distinctions within the sample, and the requested sample breakdown steps provided in section 3.2.1.

PRIORITY LEVEL 1

First, DSC and TGA analyses will be performed to determine a fuel energy value and weight percent moisture. Second, total alpha activity will be determined on a fusion preparation.

PRIORITY LEVEL 2

If the net energetics of the tank waste from the thermal analysis are greater than 125 cal/g on a dry weight basis, or if the alpha activity exceeds 41 $\mu\text{Ci/g}$ (see Section 6.2 for unit conversion guidelines), further analyses to determine concentration levels of total organic carbon (TOC), cyanide (CN), Plutonium 239/240 ($^{239/240}\text{Pu}$), Iron (Fe), Manganese (Mn), and total uranium (U) will be done.

PRIORITY LEVEL 3

If the DSC shows that a net exotherm greater than or equal to 125 cal/g (on a dry weight basis) exists in tank AX-102, and adequate sample is available, personnel at the 222-S Laboratory are directed to perform an adiabatic calorimetry analysis using the Reactive System Screening Tool (RSST) method to characterize the exothermic behavior.

3.2.3 Analytical Methods

Table 2 summarizes the analyses to be performed as well as the corresponding laboratory procedure numbers. All analyses, except RSST adiabatic calorimetry, are requested to be performed in duplicate at the performing laboratory. If the performing laboratory is not the 222-S Laboratory, arrangements shall be made by the performing laboratory for transport of one or more waste samples to the 222-S Laboratory for RSST analysis.

These analyses are based on the *Tank Safety Screening DQO* (Redus and Babad 1994). None of the analyses are being used to support regulatory compliance; therefore, regulatory methods are not required.

Any analyses prescribed by this document, but not performed, shall be identified with justification for non-performance in the appropriate data report. Also in this situation, Characterization Support and Analytical Services personnel shall be contacted (Section 5.0, Table 3).

4.0 QUALITY ASSURANCE/QUALITY CONTROL

4.1 Sampling Operations

Auger samples are to be taken and shipped to the performing laboratory by Sampling Operations in accordance with the Work Package 2E-94-00701. That work package shall also initiate the chain-of-custody form. Approved operating procedures for obtaining an auger sample are provided in procedure TO-080-500 and cask loading and transport procedure TO-080-090.

When a decision is made to perform the sampling activity, Analytical Services Program Management and Integration will designate the performing laboratory based on availability and capacity. The sampling and transportation documentation shall be revised to identify the assignment of the performing laboratory.

The auger samples are to be shipped in a cask and sealed with a waste tank sample seal. All sample shipments are identified by a unique number and labeled with the following information:

WASTE TANK SAMPLE SEAL

Supervisor	Sample No.
Date of Sampling	Time of Sampling
Shipment No.	Serial No.

Sampling Operations should send the samples to the laboratory preferably within one working day, but must send the samples within three working days of removing each sample from the tank. Sampling Operations is responsible for verbally notifying the project coordinator at the 222-S Laboratory at least 24 hours in advance of an expected shipment. If the performing laboratory is the 325 Analytical Chemistry Laboratory (ACL), Sampling Operations shall notify the project manager 72 hours in advance of an expected shipment.

The sampling team is responsible for documenting any problems and procedural changes affecting the validity of the sample in a field notebook in addition to recording this information in the comment section of the chain-of-custody form.

4.2 Laboratory Operations

The sample receipt and control procedures used in the Pacific Northwest Laboratories 325 ACL are reported in the *Quality Assurance Plan for Activity Conducted by the Analytical Chemistry Laboratory (ACL)*, (Kuhl-Klinger 1994). Procedures used in the Westinghouse Hanford 222-S Laboratory are described in LO-090-101.

Analyses and quality assurance/quality control performed at the 325 ACL shall be guided by the 325 Laboratory Quality Assurance Project Plan (Kuhl-Klinger 1994). The 222-S Laboratory has a quality assurance program plan (Meznarich 1994) and a quality assurance project plan (Taylor 1993) that shall provide the quality assurance/quality control requirements for analyzing the tank waste samples.

Method specific quality control such as calibrations and blanks are also found in the analytical procedures. Sample quality control (duplicates, spikes, standards) are identified in Table 2. If no criteria are provided in Table 2, the performing laboratory shall perform to its quality assurance plan(s).

Table 2. AX-102 Auger Sample Chemical, Physical, and Radiological Analytical Requirements

Project Name	AX-102 Auger	CHARGE CODES	ORGANIZATION	COMMENTS	REPORTING FORMATS
Plan Number	WHC-SD-WM-TP-227	ED4599 (PNL)	Pacific Northwest Laboratory	Homogenization Test - Not Required Field Blank - Not Required Hot Cell Blank - Not Required	FORMAT I Early Notify
Tank	AX-102	TBD (WHC)	Laboratory Engineering		FORMAT II Process Control
2 Augers	Augers No. 1 and 2	TBD (WHC)	Program Support		FORMAT III Safety Screen
Program Contact	H. Babad	TBD (WHC)	Laboratory Data Management		FORMAT IV Waste Management
TWRS Contact	R. D. Schreiber	TBD (WHC)	Sample Data and Administration		FORMAT V RCRA Compliance
Lab. Project Coordinator	S. G. McKinley (PNL) J. G. Kristofzski (WHC)	TBD (WHC)	Shift Relief/Data Handling		FORMAT VI Special

ANALYSES					PREPARATION				QUALITY CONTROL ¹				CRITERIA				REPORT FORMAT
METHOD	ANALYTE	WHC PROCEDURE	PNL PROCEDURE	UNITS	ACID	FUS	H ₂ O	OTHER	DUP	SPK/MSD ⁷	BLANK	STD	PRECISION	ACCURACY	NOTIFICATION LIMIT	EXPECTED RANGE	
DSC	energy	LA-514-113	PNL-ALO-508	cal/g				direct	ea smpl	N/A	N/A	ea AB	≤10%	90-110%	>net 125 cal/g (dry)	N/A	1, III
TGA	% water	LA-560-112	PNL-ALO-508	%				direct	ea smpl	N/A	N/A	ea AB	≤10%	90-110%	<17 wt%	28 - 58 wt%	1, III
Alpha Det.	Total α	LA-508-101	PNL-ALO-421 PNL-ALO-423	μCi/g		X			ea smpl	1/mtrx	ea PB	ea AB	≤10%	90-110%	>41 μCi/g ⁶	N/A	1, III
RSST ²	energy	see ⁴	N/A	cal/g				direct	N/A	N/A	N/A	ea AB	≤10%	90-110%	>net 125 cal/g (dry)	N/A	1, III
Microdist. ²	CN	LA-695-102	PNL-ALO-270 PNL-ALO-285	μg/g				direct	ea smpl	1/mtrx	ea AB	ea AB	≤10%	90-110%	>31,000 μg/g (dry)	N/A	1, III
Hot Persulfate ²	TOC	LA-342-100	PNL-ALO-381	μg/g				direct	ea smpl	1/mtrx	ea AB	ea AB	≤10%	90-110%	>30,000 μg/g	N/A	1, III
Sep & α count ³	Pu-239/240	LA-503-156	PNL-ALO-423 PNL-ALO-422	μCi/g		X			ea smpl	1/mtrx ⁵	ea PB	ea AB	≤10%	90-110%	>41 μCi/g ⁶	N/A	1, III
ICP ³	Fe, Mn, U	LA-505-151	PNL-ALO-211	μg/g	X	X			ea smpl	1/mtrx	ea PB	ea AB	≤10%	90-110%	none	5E+4-15E+4 Fe; E+3-E+4 Mn; N/A U (all μg/g)	III

1 ea - each, DUP - duplicate, spk/msd - spike or matrix spike duplicate, PB - preparation batch, AB - analytical batch, NA - not applicable, mtrx - matrix, std - calibration standard.

2 These analyses are performed only if the DSC Measurement indicates an energy content greater than 125 cal/g (dry weight basis).

3 These analyses are performed only if total alpha exceeds 41 μCi/g.

4 The RSST method, yet to be proceduralized, may be found in WHC-SD-WM-TP-104, Rev. 0.

5 Tracer or carrier is used in place of a spike and results corrected for recovery.

6 See assumption in Section 6.2 to convert alpha detection results to curies.

7 Post-digestion spike, except for ICP acid digestion, which shall have a pre-digestion spike.

8 If not specified, notification limits are on wet basis.

5.0 ORGANIZATION

The organization and responsibility of key personnel involved in this tank AX-102 safety screening project are listed in Table 3.

Table 3: Tank AX-102 Project Key Personnel List.

Individual	Organization	Responsibility
S. G. McKinley	325 Analytical Chemistry Laboratory	Project Manager for Tank Waste Characterization
J. G. Kristofzski	222-S Analytical Operations	Program Support Manager of Analytical Operations
R. D. Schreiber	TWRS Characterization Support	AX-102 Tank Characterization Plan Cognizant Engineer
H. Babad	WHC Characterization Program	Characterization Program Point of Contact
J. L. Deichman	Analytical Services	Manager of Analytical Services Program Management and Integration
East Area Shift Operations Manager	Tank Farm Operations	East Tank Farm Point of Contact if Notification Limit is Exceeded (373-2689)

6.0 EXCEPTIONS, CLARIFICATIONS, AND ASSUMPTIONS

6.1 Exceptions to DQO Requirements

At this time no exceptions to the safety screening data quality objective, pertaining to this Tank Characterization Plan, have been identified.

6.2 Clarifications and Assumptions

A number of clarifications and assumptions relating to the notification limits or decision thresholds identified in the applicable DQO efforts need to be made with respect to the analyses in Table 2. Each of these issues are discussed below (Bell 1994).

- Any exotherm determined by differential scanning calorimetry (DSC) must be reported on a dry weight basis as shown in equation (1) using the weight percent water determined from thermal gravimetric analysis.

$$\text{Exotherm (dry wt)} = [\text{exotherm(wet wt)} * 100] / (100 - \% \text{ water}) \quad (1)$$

- Redus and Babad (1994) requires that additional analyses be performed if total α activity measures greater than 1 g/L. Total α activity is measured in $\mu\text{Ci/mL}$ rather than g/L. To convert the notification limit for total α activity into a number more readily usable by the laboratory, two assumptions and calculations are necessary. All alpha decay will be assumed to originate from Pu-239 and a sample density of 1.50 g/mL is assumed. The notification limit then may then be calculated as:

$$1 \text{ g/L limit} * 1 \text{ L/E+3 ml} * 1 \text{ mL/1.5 g} * 0.062 \text{ Ci/g} * \text{E+6 } \mu\text{Ci/Ci} = 41 \mu\text{Ci/g}$$

- The safety screening DQO effort, upon which the analyses are based, does not address the analyses performed on any drainable liquid present. To adequately characterize the tank, all analyses performed on the solids will also be performed on any drainable liquids with the exception of total alpha activity. Results shall be reported by mass/volume ($\mu\text{g/mL}$).
- The DQO efforts also do not address field and hot cell blanks. Since none of the analyses are being performed for regulatory purposes or for trace amounts of analyte, no field or hot cell blanks are required.

7.0 DELIVERABLES

All analyses of tank waste material will be reported as format I or III, as shown in Table 2. The Characterization Program may request progress reports from the laboratory regarding the analyses. However, due to the rapid turn around time required for the safety screening analyses (the laboratories must report the results for primary analytes within 45 days), no special progress reports for this tank characterization project shall be required from the laboratory. All reports generated as part of normal operations (e.g., monthly reports) shall still be done. All data shall be reported by tank or by sample. The data shall be reported in the units given in Table 2. More information regarding reporting formats is found in (Schreiber 1994a).

7.1 Format I Reporting

Table 2 contains the notification limits for each analyte. Analytes that exceed the notification limits defined in the DQO processes shall be reported by calling the East Area Shift Manager of Tank Farm Operations at 373-2689 and the Characterization Program Office (Schreiber 1994b). This verbal communication must be followed within 1 working day by written communication to C. DeFigh-Price, D. R. Bratzel, and H. Babad of the Characterization Program, B. C. Carpenter and R. D. Schreiber of Characterization Support, J. L. Deichman of Analytical Services, and N. W. Kirch of Waste Tank Process Control, documenting the observation(s). A further review of the data, including quality control results and additional analyses for verification of the exceeded analyte, may be contracted between the performing laboratory and the contacts above.

7.2 Format III Reporting

A format III report, involving the results of the primary safety screen analysis, shall be issued to H. Babad, C. DeFigh-Price, D. R. Bratzel, R. D. Schreiber, and N. W. Kirch within 45 days of receipt of the last sample at the laboratory loading dock. Although normally raw data would not be attached to this type of report, the DSC and TGA scans have been requested due to the interpretive nature of the analysis. If analysis for the secondary analytes are required, these results will be provided within 90 days of receipt of the last sample at the laboratory loading dock. No calibration data are requested for these reports. An electronic record of the summary tables shall also be sent to H. Babad. Detailed information regarding the contents of this reporting format are given in (Schreiber 1994a).

8.0 CHANGE CONTROL

Under certain circumstances, it may become necessary for the performing laboratory to make decisions concerning a sample without review of the data by the customer or the Characterization Program. These changes shall be brought to the attention of the project manager and the Characterization Program as quickly as possible and documented accordingly. Changes may be documented through the use of analytical deviation reports or internal characterization change notices for minor, low-impact changes. All significant changes shall be documented by Characterization Support via an Engineering Change Notice to this Tank Characterization Plan. All changes shall also be clearly documented in the final data package.

Additional analysis of sample material from this characterization project at the request of the Characterization Program shall be performed according to a revision of this Tank Characterization Plan.

9.0 REFERENCES

- Anderson, J. D., 1990, *A History of the 200 Area Tank Farms*, WHC-MR-0132, Westinghouse Hanford Company, Richland, Washington.
- Babad, H., 1992, *An Overview of Progress Made Toward Resolving Priority One Safety Issues: Fiscal Year 1992*, WHC-EP-0606, Westinghouse Hanford Company, Richland, Washington.
- Bell, K. E., 1994b, *Tank Waste Remediation System Tank Waste Analysis Plan*, WHC-SD-WM-PLN-077, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- Bell, N. E., 1983, *Pumping of Supernatant from Tanks in B and BX Tank Farm*, (internal letter 65950-83-1664 to R. A. Zinsli, November 30), Rockwell International, Richland, Washington.
- Bratzel, D. R., Letter to S. M. Joyce, "Archiving Requirements", 7E72-94-125, dated June 23, 1994.
- Conway, J. T., Letter to H. R. O'Leary, DOE, "DNFSB Recommendation 93-5 to the Secretary of Energy," 9400070, dated July 19, 1993.
- Hanlon, B. M., 1994, *Tank Farm Surveillance and Waste Status Summary Report for January 1994*, WHC-EP-0182-70, Westinghouse Hanford Company, Richland, Washington.
- Horton, J. E., 1974, *Analysis and Characterization of Sludge Samples Received from Tank 102-AX*, (letter to O. R. H. Rasmussen, September 25), Atlantic Richfield Hanford Company, Richland, Washington.
- Kuhl-Klinger, K. J., 1994, *Quality Assurance Plan for Activity Conducted by the Analytical Chemistry Laboratory (ACL)*, MCS-033, Rev. 1, Pacific Northwest Laboratory, Richland, Washington.
- Redus, K. S., and H. Babad, 1994, *Tank Safety Screening Data Quality Objective*, WHC-SD-WM-SP-004, Westinghouse Hanford Company, Richland, Washington.
- Schreiber, R. D., 1994a, Letter to C. S. Haller, "Revised Interim Tank Characterization Plan Guidance", 7E720-94-121, dated April 13, 1994.
- Schreiber, R. D., 1994b, Letter to J. G. Kristofzski, "Format I Reporting Requirement", 7E720-94-128, dated August 15, 1994.
- Starr, J. L., 1977, *Analysis of Tank 102-AX Sludge*, (internal letter LET-072077 to J. W. Bailey, July 20) Rockwell International, Richland, Washington.
- Taylor, 1993a, *Quality Assurance Project Plan for Chemical Analysis of Highly Radioactive Mixed Waste Samples in Support of Environmental Activities on the Hanford Site*, WHC-SD-CP-QAPP-002 Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Taylor, 1993b, *Analytical Chemistry Services Quality Assurance Plan*, WHC-SD-CP-QAPP-001 Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- Weiss, R. L., 1988, *Analysis of Tank 241-AX-102 Sample*, (internal memo 12712-PCL88-018 to J. A. Eacker, November 14), Westinghouse Hanford Company, Richland, Washington.
- Wheeler, R. E., 1975, *Analysis of Tank Farm Samples: Sample T-4887, Tank 102-B*, (letter to R. L. Walser, October 24), Atlantic Richfield Hanford Company, Richland, Washington.
- Whelan, T. E., 1994, *TWRS Characterization Program Quality Assurance Program Plan*, WHC-SD-WM-QAPP-025, Westinghouse Hanford Company, Richland, Washington.