**SCALEUP TESTS AND SUPPORTING RESEARCH
FOR THE DEVELOPMENT OF DUCT INJECTION TECHNOLOGY**

Topical Report No. 3 - Task 3.2: Scale-Up Testing
Topical Report No. 4 - Task 3.3: Advanced Configurations
Topical Report No. 5 - Task 3.4: Process Controls
Topical Report No. 6 - Task 3.5: Failure Modes
Task 3.6: Waste Characterization

DOE/PC/88851--T4

DE93 008943

Contract DE-AC22-88PC88851

Duct Injection Test Facility
Muskingum River Power Plant
Beverly, Ohio

Prepared by:

Larry G. Felix
John P. Gooch
Randy L. Merritt
of

Southern Research Institute
Post Office Box 55305
Birmingham, AL 35255

and

Michael G. Klett
Atef G. Demian
John E. Hunt
of
Gilbert/Commonwealth, Inc.
Post Office Box 1498
Reading, PA 19603

September 18, 1992
SRI-ENV-92-516-6715-T3

TABLE OF CONTENTS

	<u>Page</u>
Table of Contents	ii
List of Figures	iv
List of Tables	x
 1.0 ABSTRACT	 1-1
2.0 EXECUTIVE SUMMARY	2-1
3.0 INTRODUCTION	3-1
3.1 Project and Task Descriptions	3-1
3.2 Description of the Duct Injection Test Facility (DITF)	3-3
3.3 Documentation	3-6
4.0 SCALE-UP TESTING	4-1
4.1 Coplanar Dry Sorbent Injection	4-1
4.1.1 SO ₂ Removal	4-3
4.2 Slurry Injection	4-9
4.2.1 Parametric Reagent Slurry Injection Tests	4-10
4.2.1.1 Air/Liquid Ratio Tests with Lechler Nozzles	4-32
4.2.1.2 Reagent Slurry Injection with Downstream Humidification	4-36
4.2.2 Injection of Reagent Slurry with Recycle Ash Addition	4-36
4.2.2.1 Coplanar Injection of Dry Recycle Ash with Humidification from Reagent Lime Slurry	4-39
4.2.2.2 Single Pass Reagent Slurry/Recycle Ash Tests	4-39
4.2.2.3 Continuous or Multi-Pass Reagent Slurry/Recycle Ash Tests	4-43
4.2.2.4 Reagent Slurry and Reagent Slurry/Recycle Ash Tests with CaCl ₂ Addition .	4-45
4.2.5 ESP Performance	4-47
4.2.5.1 ESP Performance at Reduced SCA	4-52
4.2.5.2 ESP Performance During Coplanar Reagent Dry Sorbent Injection	4-60
4.2.5.3 ESP Performance During Long-Term Low Ca/S Equilibrium Recycle Tests .	4-73
4.2.5.4 ESP Performance During High Ca/S Equilibrium Recycle Tests	4-93
5.0 ADVANCED CONFIGURATIONS	5-1
5.1 Fabric Filter Evaluations	5-1
5.1.1 Dry Sorbent Injection	5-5
5.1.2 Slurry Injection - Without Recycle	5-5
5.1.3 Slurry Injection - With Recycle	5-9
5.2 Dry Sorbent Reactivation	5-9
5.2.1 Dry Sorbent Injection	5-9
5.2.2 Slurry Injection - Without Recycle	5-12
5.2.3 Slurry injection - With Recycle	5-19
5.3 NO ₂ Capture Across the Fabric Filter	5-25
5.4 Condensables Tests	5-28

TABLE OF CONTENTS (continued)

Page

6.0	PROCESS OPERATION TASKS	6-1
6.1	Process Controls - Task 3.4	6-1
6.1.1	Description of the Process Control System	6-1
6.1.2	Modifications to the Process Control System	6-3
6.1.3	Process Control System Operational Testing	6-5
6.1.3.1	Test Conditions	6-5
6.1.3.2	System Modifications	6-6
6.1.3.3	Testing	6-6
6.1.3.4	Conclusion	6-8
6.2	Failure Modes - Task 3.5	6-8
6.3	Leaching Tests on Duct Injection Ash	6-15
7.0	MAJOR OPERATIONS AND MAINTENANCE EXPERIENCE	7-1
7.1	Major Milestones of Operations	7-1
7.2	Hydrated Lime and Slurry Preparatory Systems	7-1
7.3	Dry and Slurry Sorbet Injection System	7-2
7.3.1	Dry Injection System	7-2
7.3.2	Slurry Injection System	7-2
7.4	Duct Cleaning System	7-5
7.5	ESP Mechanical Performance	7-5
7.6	Ash Collection System	7-5
7.7	Recycle/Slurry Mixing	7-7
8.0	REFERENCES	8-1
APPENDIX A	Heat Balance Calculations for Tests with Dry Sorbent Injection	A-1
APPENDIX B	Heat Balance Calculations for Tests with Reagent Slurry Injection	B-1
APPENDIX C	Heat Balance Calculations for Tests with Reagent Slurry/Recycle Ash Injection	C-1
APPENDIX D	Heat Balance Calculations for Air/Liquid Ratio Tests with Reagent Slurry Injection	D-1
APPENDIX E	Heat Balance Calculations for Chloride Addition Tests	E-1

LIST OF FIGURES

<u>Figure No.</u>	<u>Page</u>
3-1 Schematic of Duct Injection Test Facility	3-5
3-2 Simplified process flow diagram	3-7
3-3 Process control system configuration	3-8
4-1 Schematic diagram of the installation of the coplanar dry injection nozzle in the horizontal test duct at the DITF	4-2
4-2 Percent of SO ₂ removed at the ESP outlet as a function of the approach to saturation. Coplanar dry injection with reagent Ca(OH) ₂	4-6
4-3 Percent of SO ₂ removed at the ESP outlet as a function of the Ca/S ratio at a 25°F approach to saturation. Coplanar dry injection with reagent Ca(OH) ₂ and reagent Ca(OH) ₂ with recycle ash. Earlier non-coplanar dry injection data at a 25°F approach are shown for comparison	4-7
4-4 Percent of SO ₂ removed at the ESP outlet as a function of the Ca/S ratio at a 45°F approach to saturation. Coplanar dry injection with reagent Ca(OH) ₂ and reagent Ca(OH) ₂ with recycle ash	4-8
4-5 Percent of SO ₂ removed at the ESP inlet as measured by the gas sampling system. Summary of all data at all approach temperatures	4-13
4-6 Percent of SO ₂ removed at the ESP inlet as measured by the gas sampling system. Summary of test data for approach temperatures from 19 to 30°F	4-14
4-7 Percent of SO ₂ removed at the ESP inlet as measured by the gas sampling system. Summary of test data for approach temperatures from 31 to 40°F	4-15
4-8 Percent of SO ₂ removed at the ESP inlet as measured by the gas sampling system. Summary of test data for approach temperatures from 41 to 50°F	4-16
4-9 Percent of SO ₂ removed at the ESP inlet as measured by the gas sampling system. Summary of test data for approach temperatures from 51 to 56°F	4-17
4-10 Percent of SO ₂ removed at the ESP outlet as measured by the gas sampling system. Summary of all data at all approach temperatures	4-18
4-11 Percent of SO ₂ removed at the ESP outlet as measured by the gas sampling system. Summary of test data for approach temperatures from 19 to 30°F	4-19
4-12 Percent of SO ₂ removed at the ESP outlet as measured by the gas sampling system. Summary of test data for approach temperatures from 31 to 40°F	4-20

LIST OF FIGURES (continued)

<u>Figure No.</u>	<u>Page</u>
4-13 Percent of SO ₂ removed at the ESP outlet as measured by the gas sampling system. Summary of test data for approach temperatures from 41 to 50°F	4-21
4-14 Percent of SO ₂ removed at the ESP outlet as measured by the gas sampling system. Summary of test data for approach temperatures from 51 to 56°F	4-22
4-15 Percent of sorbent utilized at the ESP inlet and outlet as determined by the gas sampling system. Summary of test data for approach temperatures from 20 to 30°F .	4-23
4-16 Percent of sorbent utilized at the ESP inlet and outlet as determined by the gas sampling system. Summary of test data for approach temperatures from 30 to 40°F .	4-24
4-17 Percent of sorbent utilized at the ESP inlet and outlet as determined by the gas sampling system. Summary of test data for approach temperatures from 40 to 50°F .	4-25
4-18 Percent of sorbent utilized at the ESP inlet and outlet as determined by the gas sampling system. Summary of test data for approach temperatures from 50 to 55°F .	4-26
4-19 Schematic diagram of the installation of the 12 gpm Lechler nozzle in the horizontal test duct at the DITF	4-35
4-20 Percent of SO ₂ removed at the ESP inlet and outlet for approach temperatures from 10 to 45°F. Summary of test data for reagent slurry injection with and without downstream humidification at a Ca/S ratio of 1.8	4-38
4-21 Comparison of sorbent utilization based on gas-phase data from reagent slurry injection tests conducted with and without the addition of recycle ash	4-44
4-22 Percent of SO ₂ removed at the ESP inlet and outlet for chloride levels of up to 2.2% in spent solids. A nominal Ca/S ratio of 2.0 and approach to saturation of 35°F was maintained for these tests	4-49
4-23 Percent of sorbent utilized at the ESP inlet and outlet for SO ₂ model tests conducted with CaCl ₂ addition. Summary of test data for approach temperatures from 20 to 30°F	4-50
4-24 Percent of sorbent utilized at the ESP inlet and outlet for SO ₂ model tests conducted with CaCl ₂ addition. Summary of test data for approach temperatures from 30 to 40°F	4-51
4-25 Current density as a function of applied ESP voltage for Test 33-SL-03, March 6, 1991. The first field of the ESP was deenergized	4-55

LIST OF FIGURES (continued)

<u>Figure No.</u>	<u>Page</u>
4-26 Current density as a function of applied ESP voltage for Test 33-SL-05, March 8, 1991. The first field of the ESP was deenergized	4-56
4-27 Current density as a function of applied ESP voltage for Test 34-SL-03, March 13, 1991. The first two fields of the ESP were deenergized	4-57
4-28 Current density as a function of applied ESP voltage for Test 34-SL-04, March 14, 1991. The first two fields of the ESP were deenergized	4-58
4-29 Resistivity measured in the laboratory as a function of temperature for a composited sample of ESP hopper ash from Test 34-SL-02. Data taken at 10.6% H ₂ O using both ascending and descending temperature	4-59
4-30 Particle size distribution measured at the ESP inlet. Average of measurements made on June 18-19, 1991. Cumulative percent basis	4-63
4-31 Particle size distribution measured at the ESP inlet. Average of measurements made on June 18-19, 1991. Cumulative mass basis	4-64
4-32 Particle size distribution measured at the ESP inlet. Average of measurements made on June 18-19, 1991. Differential mass basis	4-65
4-33 Current density as a function of applied ESP voltage at a 45°F approach to saturation. Test 48-DS-01, June 18, 1991	4-66
4-34 Current density as a function of applied ESP voltage at a 45°F approach to saturation. Test 48-DS-02, June 19, 1991	4-67
4-35 Current density as a function of applied ESP voltage at a 35°F approach to saturation. Test 48-DS-03, June 20, 1991	4-68
4-36 Current density as a function of applied ESP voltage at a 35°F approach to saturation. Test 48-DS-04, June 21, 1991	4-69
4-37 Resistivity measured in the laboratory as a function of temperature for a composited sample of ESP hopper ash from Test 48-DS-02. Data taken at 12.3% H ₂ O using both ascending and descending temperature	4-70
4-38 Averaged hourly opacity for March 11-13, 1992 during week 82 of testing	4-77
4-39 Particle size distribution measured at the ESP inlet. Average of measurements made on February 10, 1992 during slurry/recycle ash testing. Cumulative mass basis	4-78

LIST OF FIGURES (continued)

<u>Figure No.</u>	<u>Page</u>
4-40 Particle size distribution measured at the ESP inlet. Average of measurements made on February 10, 1992 during slurry/recycle ash testing. Differential mass basis	4-79
4-41 Particle size distribution measured at the ESP outlet. Average of measurements made on February 10, 1992 during slurry/recycle ash testing. Cumulative mass basis	4-80
4-42 Particle size distribution measured at the ESP outlet. Average of measurements made on February 10, 1992 during slurry/recycle ash testing. Differential mass basis	4-81
4-43 Particle size distribution measured at the ESP inlet. Average of measurements made on February 12, 1992 during slurry/recycle ash testing. Cumulative mass basis	4-82
4-44 Particle size distribution measured at the ESP inlet. Average of measurements made on February 12, 1992 during slurry/recycle ash testing. Differential mass basis	4-83
4-45 Particle size distribution measured at the ESP outlet. Average of measurements made on February 12, 1992 during slurry/recycle ash testing. Cumulative mass basis	4-84
4-46 Particle size distribution measured at the ESP outlet. Average of measurements made on February 12, 1992 during slurry/recycle ash testing. Differential mass basis	4-85
4-47 Calculated ESP penetration-efficiency from inlet and outlet in-situ impactor measurements made on February 10, 1992 during slurry/recycle ash testing	4-86
4-48 Calculated ESP penetration-efficiency from inlet and outlet in-situ impactor measurements made on February 12, 1992 during slurry/recycle ash testing	4-87
4-49 Current density as a function of applied ESP voltage at a 40°F approach to saturation during slurry/recycle ash testing. Test 82-SR-01, February 11, 1992	4-88
4-50 Current density as a function of applied ESP voltage at a 40°F approach to saturation during slurry/recycle ash testing. Test 82-SR-01, February 12, 1992	4-89
4-51 Resistivity measured in the laboratory as a function of temperature for a composited sample of ESP hopper ash from Test 68-SR-02 on November 5, 1991. Data taken at 12.3% H ₂ O using both ascending and descending temperature	4-90
4-52 Fractional penetration predicted by the SRI ESP model, the SRI model corrected for space charge effects, and the ADA ESP model. The second ADA model input data set shown in Table 4-24 was used to generate the results shown in this figure	4-94
4-53 Current density as a function of applied ESP voltage at a 25°F approach to saturation during slurry/recycle ash testing. Test 68-SR-04, November 7, 1991	4-96

LIST OF FIGURES (continued)

<u>Figure No.</u>	<u>Page</u>
4-54 Current density as a function of applied ESP voltage at a 24°F approach to saturation during slurry/recycle ash testing. Test 69-SR-03, November 15, 1991	4-97
4-55 Average hourly opacity for November 7-15, 1992 during weeks 68 and 69 of testing .	4-99
5-1 Schematic diagram of the Sidestream Fabric Filter Device	5-2
5-2 Comparison of sorbent utilization determined from gas-phase data and from chemical analyses of SSFF hopper samples. Data from tests conducted with dry sorbent injection and with slurry injection	5-4
5-3 SO ₂ removal as a function of Ca/S ratio for a duct approach temperature and SSFF approach temperature of 25°F. Data obtained during slurry injection testing	5-8
5-4 SO ₂ removal averaged over a filtration period in the SSFF as a function of the approach temperature with the SSFF for approach temperatures in the duct of 35°F and 45°F and a Ca/S ratio of 2.0. Data obtained during dry sorbent injection testing	5-13
5-5 SSFF data obtained during slurry tests in which the approach temperature within the SSFF was lowered from 25 to 10°F in two steps. Data shown for duct approach temperature of 45°F	5-14
5-6 SSFF data obtained during slurry tests in which the approach temperature within the SSFF was lowered from 25 to 10°F in two steps. Data shown for duct approach temperature of 25°F	5-15
5-7 SSFF data obtained during slurry tests in which the approach temperature within the SSFF was lowered from 10 to 0°F in two steps. Data shown for duct approach temperature of 25°F	5-16
5-8 SO ₂ removal as a function of Ca/S ratio for a duct approach temperature of 25°F and SSFF approach temperatures of 25 and 10°F. Data obtained during slurry injection testing	5-20
5-9 SO ₂ removal averaged over a filtration period in the SSFF as a function of the approach temperature within the SSFF for three Ca/S ratios at an approach temperature of 25°F in the duct. ESP SO ₂ removal data also shown. Data obtained during slurry injection tests	5-21
5-10 SO ₂ removal averaged over a filtration period in the SSFF as a function of the approach temperature within the SSFF for approach temperatures in the duct of 25°F and 45°F. Data obtained during slurry injection testing	5-22

LIST OF FIGURES (continued)

<u>Figure No.</u>	<u>Page</u>
5-11 SO ₂ removal across the SSFF as a function of Ca/S ratio illustrating the effect of recycle	5-24
6-1 Schematic diagram of the process control system	6-2
6-2 Removal of SO ₂ as a function of time on December 6, 1991	6-9
6-3 Concentration of SO ₂ at the DITF inlet and ESP outlet as a function of time on December 6, 1991	6-10
6-4 Ca/S ratio, removal of SO ₂ , and approach to saturation as a function of time on December 9, 1991	6-11
6-5 Removal of SO ₂ as a function of time on December 11, 1991	6-12
6-6 Removal of SO ₂ as a function of time on December 12, 1991	6-13
6-7 Concentration of SO ₂ at the DITF inlet and ESP outlet as a function of time on December 12, 1991	6-14
7-1 Location of nozzles in small Lechler nozzle array in the horizontal test duct at the DITF	7-3
7-2 Schematic diagram of the installation of the coplanar dry injection nozzle in the horizontal test duct at the DITF	7-4
7-3 Location of soot blowers in the horizontal test duct at the DITF	7-6

LIST OF TABLES

<u>Table No.</u>	<u>Page</u>
3-1 DITF Test Activity, Weeks 29-84 of Testing	3-2
4-1 SO ₂ Removal Data Obtained During Coplanar Dry Sorbent Injection Tests	4-4
4-2 SO ₂ Removal Data Obtained During Coplanar Dry Sorbent Injection Tests with Recycle Ash Alone and Fresh Sorbent plus Recycle Ash	4-5
4-3 Results of Earlier SO ₂ Removal Tests Carried out at the DITF	4-11
4-4 Results of SO ₂ Removal Tests with Reagent Lime Slurry Carried out Since 2/91	4-12
4-5 Results of Solids Analyses Carried out on a Composite ESP Hopper Sample from Test 34-SL-02, 3/12/91	4-28
4-6 Results for Test 54-SL-03, 8/2/91	4-30
4-7 Comparison of Sorbent Utilization from Solids Analysis and from Gas Phase Measurements for Test 54-SL-03, 8/2/91	4-31
4-8 Air/Liquid Ratio Test Summary	4-34
4-9 Results of SO ₂ Removal Tests with Downstream Humidification Provided by a Single Parker-Hannifin Nozzle, 30 ft Downstream of the Point of Slurry Injection	4-37
4-10 Summary of Reagent Slurry/Dry Recycle Ash Tests	4-40
4-11 Results of Single Pass Reagent Slurry/Recycle Ash Tests	4-41
4-12 Comparison of Sorbent Utilization from Chemistry and from Gas Phase Data for Single Pass Reagent Slurry/Recycle Tests	4-42
4-13 Summarized Results for Continuous Reagent Slurry/Recycle Ash Tests	4-46
4-14 Summary of Results for Tests with Ca(Cl) ₂ Addition	4-48
4-15 Summary of ESP Behavior During Tests Conducted at the DITF During March, 1991	4-53
4-16 Summary of ESP Electrical Behavior During Tests Conducted at the DITF During March, 1991	4-54
4-17 Summary of ESP Behavior During Tests Conducted at the DITF During June, 1991 .	4-61

LIST OF TABLES (continued)

<u>Table No.</u>	<u>Page</u>
4-18 Summary of ESP Electrical Behavior During Tests Conducted at the DITF During June, 1991	4-62
4-19 In situ Resistivity Measured at the ESP Inlet During Coplanar Dry Sorbent Injection Tests at a 35 and 45°F Approach, June 18-21, 1991	4-71
4-20 ESP Model Results for Tests Conducted in June, 1991	4-72
4-21 Summary of ESP Behavior During Tests Conducted at the DITF During Test 82-SR-01, February, 1992	4-75
4-22 ESP Operating Parameters, Long-Term ESP Test, 2/11/92 - 2/13/92	4-76
4-23 In situ Resistivity Measured at the ESP Inlet During Slurry/Recycle Tests at a 40 and 35°F Approach, June 18-21, 1991	4-91
4-24 ESP Model Results for Tests conducted in February, 1992	4-92
4-25 ESP Operation and Opacity During the High Continuous Recycle Test, November 7-15, 1991	4-98
4-26 ESP Model Results for Tests conducted in November, 1991	4-100
5-1 SSFF Tests - Dry Sorbent Injection	5-6
5-2 SSFF Tests - Slurry Injection Without Recycle	5-6
5-3 SSFF Tests - Slurry Injection Without Recycle With Two-Stage Humidification	5-7
5-4 SSFF Tests - Slurry Injection with Recycle	5-10
5-5 SSFF/DSR Tests - Dry Sorbent Injection	5-11
5-6 SSFF/DSR Tests - Slurry Injection Without Recycle	5-17
5-7 SSFF/DSR Tests - Slurry Injection Without Recycle With Two-Stage Humidification	5-18
5-8 SSFF/DSR Tests - Slurry Injection with Recycle	5-23
5-9 SSFF NO _x Measurement Results	5-26
5-10 Results of CPM Tests	5-29
6-1 Results of TCLP Leaching Tests on Base Line and Duct Injection Ash Samples	6-16

1.0 ABSTRACT

This document is the third interim report on tests that were conducted at the Duct Injection Test Facility (DITF) operated for the Department of Energy at Unit 5 of the Ohio Power Company's Muskingum River station in Beverly, Ohio. At the DITF dry calcium hydroxide ($\text{Ca}(\text{OH})_2$), an aqueous slurry of $\text{Ca}(\text{OH})_2$ (prepared by slaking quicklime), or a mixture of one of these sorbents with waste ash from earlier tests was injected into a slipstream of flue gas from the Unit 5 boiler to achieve partial removal of SO_2 in the flue gas. Up to 50,000 acfm of flue gas was taken from the inlet to the Unit 5 electrostatic precipitator (ESP) for these tests. Water was injected separately with the dry sorbent or as part of the slurry to cool the flue gas and increase the water vapor content of the flue gas. The addition of water, either as a separate spray or in the slurry makes the reaction between the sorbent and the SO_2 more complete; the presumption is that water is effective in the liquid state when it can physically wet the sorbent particles, and not especially effective in the vapor state.

For all of these tests Lechler supersonic nozzles were used for water or slurry injection. For most of these experiments, an array of six 2.88 gallon per minute (gpm) nozzles was used. A dedicated ESP was used to collect suspended solids (fly ash from the boiler and sorbent from the duct injection process). Cleaned flue gas was returned to the inlet of the Unit 5 ESP.

This report covers experiments conducted between February 5, 1991 and February 27, 1992 when testing at the DITF ended. During that period of time effort was devoted to completing four separate tasks: Task 3.2 - Scale-Up Testing, Task 3.3 - Advanced Configurations, Task 3.4 - Process Controls, and Task 3.5 - Failure Modes. A fifth task, Task 3.6 - Waste Characterization, was completed after testing was concluded at the DITF.

Higher values of calcium utilization were obtained with slurry injection than with dry sorbent injection and humidification. Slurries made from reagent slaked lime, mixtures of reagent slaked lime and recycle ash, and from recycle ash alone were injected through the same nozzles used for humidification. The focus of most of these tests was on the constant addition of recycle ash to reduce the amount of slaked lime required for SO_2 removal (for best economics). Testing was continued until the amount of $\text{Ca}(\text{OH})_2$ in the recycle ash equaled that predicted for equilibrium. Two test cases were evaluated: a low Ca/S ratio (1.0 reagent, 44°F approach) for 50% SO_2 removal and a high Ca/S ratio (1.7 reagent, 24°F approach) for 88% SO_2 removal.

A small side-stream fabric filter (SSFF) was used to evaluate the additional SO_2 removal that could be achieved with a fabric filter downstream of a duct injection process. The results indicated that 5 to 10% more SO_2 removal is obtained across the fabric filter than the ESP for all test conditions that were evaluated. A unique two stage cooling process was used with the SSFF to achieve over 99% SO_2 removal at a reagent Ca/S ratio of 2.0. These high values of SO_2 removal were obtained with a filter cake which cleaned easily from the fabric and which appeared to be free-flowing when removed from the SSFF hopper.

A limited amount of testing was also performed with a single 12 gpm Lechler supersonic nozzle to demonstrate the ability to scale this nozzle up and to investigate the effect of air-to-liquid (A/L) ratio on nozzle performance and SO_2 removal. The tests showed operation with this nozzle was possible at an A/L ratio of 0.5 with no problems with duct deposits and no effect on SO_2 removal.

2.0 EXECUTIVE SUMMARY

This document is the third interim report on tests that were conducted at the Duct Injection Test Facility (DITF) operated for the Department of Energy at Unit 5 of the Ohio Power Company's Muskingum River station in Beverly, Ohio. At the DITF dry calcium hydroxide ($\text{Ca}(\text{OH})_2$), an aqueous slurry of $\text{Ca}(\text{OH})_2$ (prepared by slaking quicklime), or a mixture of one of these sorbents with waste ash from earlier tests was injected into a slipstream of flue gas from the Unit 5 boiler to achieve partial removal of SO_2 in the flue gas. Up to 50,000 acfm of flue gas was taken from the inlet to the Unit 5 electrostatic precipitator (ESP) for these tests. Water was injected separately with the dry sorbent or as part of the slurry to cool the flue gas and increase the water vapor content of the flue gas. The addition of water, either as a separate spray or in the slurry makes the reaction between the sorbent and the SO_2 more complete; the presumption is that water is effective in the liquid state when it can physically wet the sorbent particles, and not especially effective in the vapor state. For all of these tests Lechler supersonic nozzles were used for water or slurry injection. For most of these tests an array of six 2.88 gallon per minute (gpm) nozzles was used. A dedicated ESP was used to collect suspended solids (fly ash from the boiler and sorbent from the duct injection process). Cleaned flue gas was returned to the inlet of the Unit 5 ESP.

This report covers experiments conducted between February 5, 1991 and February 27, 1992 when testing at the DITF ended. During that period of time effort was devoted to completing four separate tasks: Task 3.2 - Scale-Up Testing, Task 3.3 - Advanced Configurations, Task 3.4 - Process Controls, and Task 3.5 - Failure Modes. A fifth task, Task 3.6 - Waste Characterization, was completed after testing was concluded at the DITF. The principle results of this work are summarized below.

Task 3.2 - Scale-Up Testing During these tests both dry and slurried $\text{Ca}(\text{OH})_2$ -based sorbents were evaluated for SO_2 removal and compatibility with electrostatic precipitation. Most of the experimental work was performed with slurry injection because this process mode provided superior SO_2 removal and system operational characteristics compared with dry sorbent injection.

Dry sorbents were injected at a location coplanar with the humidification nozzles. Dry $\text{Ca}(\text{OH})_2$, dry $\text{Ca}(\text{OH})_2$ mixed with dry recycle ash (ash and spent sorbent collected from earlier tests in the DITF ESP), and dry recycle ash alone were injected while approach temperatures were maintained from 25°F to 45°F. Coplanar injection provided 5 to 10% (absolute basis) more SO_2 removal than that obtained with scavenging mode injection when water is injected downstream from the sorbent injection point. Highest SO_2 removals were achieved at a nominal Ca/S ratio of 2.0 and an approach of 25°F: 49% at the ESP outlet and 37% at the ESP inlet. At an approach of 45°F some collection problems were encountered in the ESP. These appear to be resistivity-related because the ESP voltage-current (and collection) characteristics improved at lower approach temperatures (lower ash resistivity). All SO_2 removal data are reported at the ESP exit unless otherwise indicated.

Slurries made from slaked lime, mixtures of fresh slaked lime and recycle ash, and from recycle ash alone were injected through the same nozzles used for humidification. The focus of most of these tests was on the constant addition of recycle ash to reduce the amount of slaked lime required for SO_2 removal (for best economics). Testing was continued until the amount of $\text{Ca}(\text{OH})_2$ in the recycle ash equaled that predicted for equilibrium. Two test cases were evaluated: a low Ca/S ratio (1.0 reagent, 44°F approach) for 50% SO_2 removal and a high Ca/S ratio (1.7 reagent, 24°F

approach) for 88% SO₂ removal. These data illustrate the capability of duct slurry injection to obtain much higher calcium utilization values (50% vs 25% Ca utilization for slurry vs dry at ~50% SO₂ removal.)

During these tests ESP mass collection efficiency was found to exhibit significant variability. At approach temperatures ranging from 34°F to 43°F, collection efficiency ranged from 99.94% (at a 34°F approach) to a low of 99.23% (at a 41°F approach) with a specific collection area of ~390 ft²/1000 acfm. Severe ESP performance degradation was observed at the 25°F approach with the 1.9 Ca/S reagent ratio, while ESP voltage-current characteristics were normal. Under these conditions of low ash resistivity and high inlet mass loading, electrical reentrainment appears to have occurred. At the higher approach temperature ESP performance was still degraded from predictions based on mathematical models, but not to the extent that was observed at the 25°F approach with Ca/S reagent ratio equal to 1.9.

Limited testing was also performed with a 12 gpm Lechler supersonic nozzle to demonstrate the ability to scale this nozzle up and to investigate the effect of air-to-liquid ratio on nozzle performance and SO₂ removal. The motivation for these tests was the finding that it was necessary to operate the 2.88 gpm nozzles used for most of the testing at an air to liquid (A/L) ratio of 0.8 to 1.1 instead of the design value of 0.5. This high A/L ratio is in part an artifact of operating the nozzles at less than rated liquid flow. Tests with the 12 gpm nozzle showed operation with this nozzle was possible at an A/L ratio of 0.5. In general, it was found that when the large Lechler nozzle was operated up to its design flow (an A/L ratio of about 0.5), no problems with duct deposits were encountered and no effect on SO₂ removal (compared with the smaller nozzles) was observed.

Task 3.3 - Advanced Configurations A variety of tests were conducted for this task. Individual tasks included tests with the DOE side stream fabric filter or SSFF (a small pulse-jet cleaned fabric filter) to investigate how alternative control devices affect SO₂ removal for the duct injection process and to develop a new process for dry sorbent reactivation that can increase SO₂ removal to levels that exceed those possible with wet scrubbers. The SSFF was also used for two other short test series, one to investigate NO_x/NO₂ capture and the other to investigate the capture of condensable emissions in dust cakes composed of ash and spent sorbent.

Tests with the SSFF indicated that 5 to 10% more SO₂ removal is obtained across the fabric filter than the ESP for all test conditions. Further experiments were conducted with the SSFF using a unique two-stage cooling process. SRI has a patent application pending on this process. Results from these tests showed that over 99% SO₂ removal could be achieved with the duct operating at a 25°F approach and the SSFF operating at a 10°F approach with a reagent Ca/S of 2.0 and 2000 ppm SO₂ at the spray dryer inlet. The filter cake was easily cleaned from the fabric under these conditions, and ash/sorbent mixtures removed from the SSFF hopper appeared to be dry and presented no handling problems.

A simulation of EPA test method 202 for condensable particulate matter was performed downstream of the SSFF. Results from these measurements indicated only very low concentrations of sulfates and chlorides (1.1 ppm as H₂SO₄, and 3 ppm as HCl) were found in the impinger train downstream of the filter cake which was operating within 25°F of saturation.

Nitrogen dioxide was injected ahead of the SSFF to investigate the effectiveness of the low temperature ash/sorbent filter cake in removing NO₂. These experiments indicated significant NO₂ removal

did occur across the cake, but it was not possible to obtain a material balance for the NO₂ across the SSFF based on analysis of hopper solids and inlet and outlet gas streams. Furthermore, significant NO₂ penetration of the filter cake occurred at inlet NO₂ concentrations of 200-300 ppm.

The final test series performed under this task included tests with CaCl₂ added to reagent slurry/recycle ash mixes to investigate the effect of this additive on SO₂ removal. Levels of chloride of up to 3.6% were measured in the spent ash during these tests. Calcium chloride addition appeared to have the greatest effect at low approach temperatures.

Unfortunately, these tests were some of the last performed at the DITF, during a time when the Unit 5 boiler was frequently off line. Because of this not all of the planned tests with CaCl₂ as an additive could be completed.

Task 3.4 - Process Controls For these tests the Allen Bradley 5/25 programmable logic control (PLC) system used to operate the DITF was configured to control the outlet SO₂ emissions to a predetermined level, and the flue gas sampling system was configured to sample only at the system inlet and outlet. Tests were run at simulated Unit 5 boiler loads of 50, 75, and 100% (inlet SO₂ levels of 1000, 1500, and 2000 ppm, respectively) while SO₂ removal was maintained at approximately 60% and while approach temperature and Ca/S ratio were allowed to vary. The response of the PLC system to process variation was outstanding, in view of the fact the system is designed to control a test facility and not a full-scale commercial system. The tests demonstrated that basic philosophy of outlet SO₂ control is a feasible and effective method of control for a full-scale application of duct injection.

Task 3.5 - Failure Modes Throughout this project tests were occasionally interrupted by process upsets and equipment failures. Some of these interruptions represented failure modes that could be expected to interfere with operation at any level (boiler upsets, loss of compressed air, interruption of slaker flow, loss of electrical power, failure of air or slaker hoses, etc.). Other failures were due to the lack of backup systems that would be part of a normal full-scale installation or were caused by the failure of specialized test equipment. A third mode of failure was caused by operation at test conditions that were known to cause duct deposits. At the DITF the response to these modes of failure was a cessation of testing. Several recommendations are made in this section of the report for future system designs to minimize shutdowns. Among the more critical recommendations are: 1) to utilize a duct wall temperature detection system to alarm for close approach conditions, and 2) provide flow monitoring and control to individual nozzles or nozzle arrays to maintain proper operation.

Task 3.6 - Waste Characterization Samples of ash from the Unit 5 ESP and from the DITF ESP, (taken during recycle testing at the low Ca/S ratio condition) were subjected to the Toxic Characteristic Leaching Procedure (TCLP) to measure the leachability of these samples for heavy metals. The TCLP results suggest that neither the base line ash nor the duct injection ash could be classified as hazardous by virtue of their content of leachable metals.

3.0 INTRODUCTION

3.1 Project and Task Descriptions

Duct injection is being investigated under the auspices of the U.S. Department of Energy as a low cost, retrofit technology for controlling SO₂ emissions from coal-burning electric power stations. This report is one in a series of topical reports that describe the results of one study of this technology that was conducted by Gilbert/Commonwealth Inc. and Southern Research Institute. This study was carried out at the Duct Injection Test Facility (DITF) operated for the Department of Energy at Unit 5 of the Ohio Power Company's Muskingum River station in Beverly, Ohio. The Ohio Power Company is a part of the American Electric Power System.

This Topical Report completes the description of the experimental work performed under DOE Contract DE-AC22-88PC88851 for the contractual requirements of Topical Reports 3, 4, 5, and 6. Earlier test results and a complete description of the DITF were presented in Topical Report No. 2.¹ That report covered only Task 3.1-Evaluation of System Performance (tests carried out over the period from the start of testing on April 30, 1990 through February 4, 1991). This report covers subsequent work performed from February 5, 1991 through February 27, 1992 when testing at the DITF ended. Table 3-1 summarizes test activity at the DITF over this time interval. During this period effort was devoted to completing five separate tasks: Task 3.2 - Scale-Up Testing, Task 3.3 - Advanced Configurations, Task 3.4 - Process Controls, and Task 3.5 - Failure Modes, and Task 3.6 - Waste Characterization. Each task is briefly described below:

- **Task 3.2 - Scale-Up Testing** For this task both dry and slurried Ca(OH)₂-based sorbents were evaluated for SO₂ removal and compatibility with electrostatic precipitation. Dry sorbents were injected at a location coplanar with the six humidification nozzles. Dry Ca(OH)₂, dry Ca(OH)₂ mixed with dry recycle ash (ash and spent sorbent collected from earlier tests in the DITF ESP), and dry recycle ash alone were injected while approach temperatures were maintained from 25°F to 45°F. Slurries made from reagent slaked lime, mixtures of reagent slaked lime and recycle ash, and from recycle ash alone were injected through the same six nozzles used for humidification. Approach temperatures were usually maintained from 25°F to 45°F. Limited testing was also performed with a larger single nozzle to demonstrate the ability to scale the nozzle up and to investigate the effect of air-to-liquid ratio on nozzle performance and SO₂ removal. The focus of most of these tests was on the constant addition of recycle ash to reduce the amount of fresh slaked lime required for SO₂ removal (for best economics). Testing was continued until the amount of Ca(OH)₂ in the recycle ash equaled that predicted for equilibrium.
- **Task 3.3 - Advanced Configurations** A variety of tests were conducted for this task. Individual subtasks included tests with the DOE side stream fabric filter or SSFF (a small pulse-jet cleaned fabric filter) to investigate how alternative control devices affect SO₂ removal for the duct injection process and to develop a new process for dry sorbent reactivation that can increase SO₂ removal to levels that exceed those possible with wet scrubbers. The SSFF was also used for two other short test series, one to investigate NO_x/NO₂ capture and the other to investigate the capture of condensable emissions in dust cakes composed of ash and spent sorbent. The final test series performed under this task included tests with CaCl₂ added to slurry/recycle ash mixes to investigate the effect of this additive on SO₂ removal.

Table 3-1. DITF Test Activity, Weeks 29-84 of Testing

WEEK BEGINNING	WEEK #	ACTIVITY
		Task 3.2, Scale-Up Tests & Task 3.3, Advanced Configurations
4-Feb-91	29	Prepare for Slurry/Recycle Ash Tests
11-Feb-91	30	Continue Slurry/Recycle Testing
18-Feb-91	31	Outage - Air Compressor Motor Failed
25-Feb-91	32	Outage - Air Compressor Motor Failed
4-Mar-91	33	Parametric Slurry & ESP Tests, SSFF Tests (Task 3.3)
11-Mar-91	34	Parametric Slurry & ESP Tests, SSFF Tests (Task 3.3)
18-Mar-91	35	Slurry/Recycle Ash Tests; Equipment Problems
25-Mar-91	36	Slurry/Recycle Ash Tests; Equipment Problems
1-Apr-91	37	Parametric Slurry Tests; SSFF Tests (Task 3.3)
8-Apr-91	38	Parametric Slurry Tests; SSFF Tests (Task 3.3)
15-Apr-91	39	Parametric Slurry Tests; SSFF Tests (Task 3.3)
22-Apr-91	40	No Tests; Equipment Problems
29-Apr-91	41	No Tests; Equipment Problems with Gas Sampling System
6-May-91	42	Long-Term Slurry Tests
13-May-91	43	Begin Dry Sorbent Testing, Coplanar Injection
20-May-91	44	Unit 5 Off-Line; Equipment Problems with DITF Inlet Venturi
27-May-91	45	Continue Dry Sorbent Injection Tests
3-Jun-91	46	Continue Dry Sorbent Injection Tests
10-Jun-91	47	Continue Dry Sorbent Injection Tests
17-Jun-91	48	Long-Term Coplanar Dry Injection Test, SSFF Tests (Task 3.3)
24-Jun-91	49	Limited Dry Injection Testing; Equipment Problems
1-Jul-91	50	Coplanar Dry Injection Recycle Ash Tests
8-Jul-91	51	Resume Slurry Tests; Installed Delumper
15-Jul-91	52	Limited Testing; Problems with Delumper
22-Jul-91	53	Start Slurry/Recycle Ash Tests
29-Jul-91	54	Equipment Problems; Limited Slurry/Recycle Tests
5-Aug-91	55	Equipment Problems; Limited Slurry/Recycle Tests
12-Aug-91	56	Unit 5 Off-Line
19-Aug-91	57	A/W Red, Tests with 6 Lechler Nozzle Array; Operator Injury
26-Aug-91	58	No Testing
2-Sep-91	59	No Testing
9-Sep-91	60	No Testing
16-Sep-91	61	No Testing
23-Sep-91	62	No Testing
30-Sep-91	63	No Testing, Unit 5 Off Line
7-Oct-91	64	No Testing, Unit 5 Off Line
14-Oct-91	65	Resume Testing, Limited Slurry Tests
21-Oct-91	66	Equilibrium Slurry/Recycle Ash Test at Low Ca/S Ratio
28-Oct-91	67	Equilibrium Slurry/Recycle Ash Test at Low Ca/S Ratio
4-Nov-91	68	Equilibrium Slurry/Recycle Ash Tests, Low & High Ca/S Ratio, SSFF Test (Task 3.3)
11-Nov-91	69	Equilibrium Slurry/Recycle Ash Tests, High Ca/S Ratio, SSFF Test (Task 3.3)
18-Nov-91	70	No Testing, Unit 5 Off Line
25-Nov-91	71	12 gpm Lechler Supersonic Nozzle Tests with Slurry Only
		Start Tests for Task 3.5, Failure Modes
2-Dec-91	72	Response to Changes in Boiler Load -Modify PLC and Gas Sampling System
9-Dec-91	73	Response to Process Upsets-Evaluation, Reinstall 3 gpm Lechler Supersonic Nozzles
16-Dec-91	74	In Situ Particle Sizing Tests with Video Droplet Analyzer and Impactors
23-Dec-91	75	No Testing, Rework Gas Sampling System
30-Dec-91	76	Slurry injection with CaCl ₂ Addition-Parametric Test (Task 3.3)
6-Jan-92	77	Slurry injection with CaCl ₂ Addition-Parametric Test (Task 3.3)
13-Jan-92	78	Equipment Problems, Generate Recycle Ash for Future Recycle Tests
20-Jan-92	79	No Testing, Unit 5 Off Line
27-Jan-92	80	No Testing, Unit 5 Off Line
3-Feb-92	81	Start Long-Term ESP Test, Equilibrium Slurry/Recycle Ash Injection at Low Ca/S Ratio
10-Feb-92	82	Conclude Long-Term ESP Test
		Start Task 4, Model Validation Tests
17-Feb-92	83	B&W Model Validation Tests with CaCl ₂ Addition to Slurry, SSFF Tests (Task 3.3)
24-Feb-92	84	B&W Model Validation Tests with CaCl ₂ Addition to Slurry, SSFF Tests (Task 3.3)
-----		----- End of Testing -----

- **Task 3.4 - Process Controls** For these tests the flue gas sampling system was configured to sample only at the system inlet and ESP outlet and the Allen Bradley 5/25 programmable logic control system used to operate the DITF was configured to control the outlet SO₂ emissions to a predetermined level. Tests were run at simulated Unit 5 boiler loads of 50, 75, and 100% (inlet SO₂ levels of 1000, 1500, and 2000 ppm, respectively) while SO₂ removal was maintained at approximately 60% by varying slurry flow.
- **Task 3.5 - Failure Modes** The purpose of this task was to catalog and investigate the various process upsets and equipment failures that affected day to day testing at the DITF. Some of these interruptions represented failure modes that could be expected to interfere with operation at any level (boiler upsets, loss of compressed air, interruption of slaker flow, loss of electrical power, failure of air or slaker hoses, etc.). Other failures were due to the lack of backup systems that would be part of a normal full-scale installation or were caused by the failure of specialized test equipment. A third mode of failure was caused by purposeful operation at test conditions that were known to cause duct deposits or to degrade ESP performance.
- **Task 3.6 - Waste Characterization** Samples of ash from the Unit 5 ESP and from the DITF ESP, (taken during recycle testing at the low Ca/S ratio condition) were subjected to the Toxic Characteristic Leaching Procedure (TCLP) to measure the leachability of these samples for heavy metals.

3.2 Description of the Duct Injection Test Facility (DITF)

The Duct Injection Test Facility of the Department of Energy (DOE), located in Beverly, Ohio, at the Muskingum River power plant of Ohio Power Company, was converted to test alternative duct injection technologies. The technologies tested include slurry sorbent injection of slaked pebble lime with dual fluid nozzles and pneumatic injection of dry hydrated lime with flue gas humidification before or after sorbent injection. The test facility was modified to test a range of flue gas SO₂ concentrations and a range of flue gas temperatures in vertical and horizontal duct test sections. This test program is part of a larger DOE program to fully characterize low cost, retrofittable dry SO₂ removal technologies for application to existing power plants.

Two types of duct injection technologies were tested over the two-year life of this project: (1) slurry sorbent injection of slaked pebble lime, using dual-fluid nozzles; and (2) pneumatic injection of dry hydrated lime, with flue gas humidification before and after sorbent injection. A wide range of flue gas SO₂ concentrations and temperatures were utilized for testing. The purpose of the test program was to:

- Obtain scale-up engineering design data for both slurry and dry sorbent injection.
- Provide scale-up data for humidification and ESP performance.
- Develop and test process-control systems.
- Validate the first and second generation process models developed under other parts of the DOE program.

A complete description of the DITF and its capabilities, operation, control, and gas sampling and data acquisition systems was presented in Topical Report No. 2 for this project.¹ A brief description of the DITF and its capabilities follows.

The DITF operates as a 12 MWe, 50,000 ACFM "slipstream" system on Ohio Power Company, Muskingum River Unit No. 5, in Beverly, Ohio. The boiler is a B&W dry-bottom pulverized coal, front and rear wall-fired Unit, rated at 585 MW (net).

The unit is base-loaded but it can drop to half load during summer months, usually between midnight and morning. Currently, the plant burns local coal with an as-received sulfur content of about 4.2%. The nominal flue gas conditions at the exit of the air preheater (feeding the test facility) are as follows:

N ₂	75.6%
CO ₂	11.9%
H ₂ O	7.5%
O ₂	4.6% (30% excess air)
SO ₂	3200 ppm
Ash	3.4 gr/acf
Molecular Weight	29.46
Temperature	325° F

The slipstream is taken from the existing air preheater discharge, through ductwork with three test stations to the DITF electrostatic precipitator (ESP), then to an induced draft fan, and back to the existing ESP inlet. A provision also exists to bypass the pilot ESP and allow gas to flow through a high-efficiency cyclone. Figure 3-1 is a schematic drawing of the DITF.

The DITF ESP is a weighted-wire design, consistent with the majority of older units for which the sorbent duct injection technology is intended. The ESP has four independent electrical fields and is designed for an SCA of 360 ft²/1000 acfm at a system inlet flow rate of 40,000 acfm at 190° F. Although this design is somewhat larger than most units that are candidates for duct injection technology, it provided additional flexibility for the test program.

The test facility was originally designed to deliver slaked pebble lime slurry to a rotary atomizer in one of three duct locations—one in a vertical duct and two in a horizontal duct. New equipment was designed and installed to test two different types of duct injection technologies: (1) Slurry sorbent injection of slaked pebble lime, using dual fluid nozzles, and (2) Pneumatic injection of hydrated lime, with flue gas humidification before or after sorbent injection. The new equipment consists of:

- Flue gas dilution air heater to vary SO₂ content and temperature of the incoming gas.
- Flue gas steam humidifier.
- Slurry sorbent injection pumps and nozzles.
- Hydrated lime silo and blowers.
- Flue gas humidification nozzles and water pump.

Figure 3-1. Schematic of Duct Injection Test Facility.

- Ash recycle system.
- Compressed air system.
- Duct hoppers and cleaning systems.
- Waste ash silo.
- State-of-the-art programmable logic controller and data acquisition system.

The DITF instrument and control system was developed from a mixture of existing equipment hardware and software and a new Allen-Bradley Programmable Logic Controller (PLC) 5/25 control system. All of the process and equipment control was assigned to the new PLC system while the existing Data Acquisition System (DAS) was upgraded and strictly limited to data acquisition. Figure 3-2 shows a simplified process flow diagram of the facility and Figure 3-3 shows a schematic of the PLC and DAS systems.

As a result of these modifications a great deal of flexibility was designed into the facility to provide the capability of testing over a wide range of process conditions. These capabilities include the following:

- Flue gas velocity of 20-60 ft/s which corresponds to a gas flow of 16,700-50,000 acfm at the inlet conditions.
- Inlet gas temperature 275-320° F.
- Inlet gas SO₂ concentration of 1100-3200 ppmv.
- Sorbent addition at a Ca/S ratio of 1.0-2.0 (nominal limits).
- Duct residence time of 0.5-3.0 s.
- Approach to adiabatic saturation temperature of 20-80° F.
- Recycle of spent sorbent for either slurry or dry sorbent injection.

3.3 Documentation

To date, two topical reports have been prepared on this project. Topical Report No. 1 was a literature review and analysis of duct injection technology,² and Topical Report No. 2 presented the results of Task 3.1, Characterization of System Performance.¹ The first topical report reviewed the state of duct injection technology at the inception of this project and identified the research needs and objectives required to gain a thorough and detailed understanding of the scale-up and design requirements, operational behavior, and limitations of duct injection technology. This topical report also included an annotated bibliography of 94 selected references on SO₂ control and 21 selected references on ESP performance.

SIMPLIFIED PROCESS FLOW DIAGRAM
DUCT INJECTION TEST FACILITY

Figure 3-2. Simplified process flow diagram.

Figure 3-3. Process control system configuration.

The second topical report described the modified DITF and the testing carried out to complete Task 3.1, Characterization of System Performance. The tests carried out to complete this task included: tests with water to evaluate the wall wetting characteristics of the Parker-Hannifin and Lechler nozzles selected for use at the DITF, in situ tests to measure the particle size distribution of water droplets produced by these nozzles downstream of the point of injection, SO₂ removal experiments with the injection of dry sorbent upstream (scavenging mode) and downstream (non-scavenging mode) of the point of flue gas humidification, and SO₂ removal experiments with the injection of slaked lime slurry. These tests lasted from April 30, 1990 when the DITF was first brought on line until February 4, 1991 (the first 29 weeks of testing). During this period the DITF was off line for approximately two and one half months while the Unit 5 boiler underwent a major rebuild. The major finding presented in this report was that compared to dry injection, slurry injection is a superior technology, both in terms of SO₂ removal and process operation. The project goal of SO₂ removal of 50% or greater was easily met with slurry injection.

Two more topical reports and a final report are required to complete the reporting requirements for this project. This Topical Report, which includes Topical Reports 3, 4, 5, and 6, covers the balance of testing carried out at the DITF (Tasks 3.2 through 3.6 as described above). Originally, each project task was to be summarized in a topical report and Tasks 3.2 through 3.6 were to be the subject of Topical Reports 3 through 6. However, because it makes for a more logical ordering, these were combined into this one report with DOE concurrence. Topical Reports Nos. 7 and 8 compares the predictions of existing computer models for SO₂ removal with data obtained at the DITF. The Final Report summarizes all of the research carried out on this project and presents the major conclusions and recommendations that can be drawn from this work.

4.0 SCALE-UP TESTING

Two major test series were completed in this task. The first of these was a test of dry sorbent injection that essentially repeated the dry sorbent tests done earlier but with the sorbent injected in the plane of the humidification nozzles, between the two nozzle lances (coplanar injection). Tests were conducted to measure SO_2 removal with reagent dry $\text{Ca}(\text{OH})_2$ sorbent (Mississippi LimeTM), reagent dry $\text{Ca}(\text{OH})_2$ mixed with dry recycle ash, and with dry recycle ash alone. ESP performance was evaluated, but not during tests with recycle ash injection. The second major series of tests to measure SO_2 removal and ESP performance was conducted with the injection of various slurry mixtures. These slurries included slaked lime slurry, mixtures of slaked lime slurry and recycled waste ash, and a slurry of recycled waste ash alone. For all of these tests the liquid portion of the slurry was water and the slaked lime sorbent was produced on site with a detention-type slaker using a pebble lime feed stock supplied by the Mid Ohio Valley Lime Company of Marietta, OH. The physical properties of the dry and slaked lime sorbents were reviewed in Topical Report No. 2.¹

4.1 Coplanar Dry Sorbent Injection

Earlier at the DITF, dry sorbent injection tests had been performed with upstream humidification and downstream humidification. With upstream humidification (the non-scavenging mode), dry sorbent is injected after water droplets have fully evaporated and the approach temperature has been reached. Thus, the sorbent does not contact (or scavenge) any water droplets present in the flue gas. With downstream humidification (the scavenging mode), dry sorbent is injected upstream of the water sprays, and the sorbent has a chance to react with SO_3 present in the flue gas before humidification and, after humidification, to contact (and become moistened by) water droplets. Because moist sorbent reacts much more readily with SO_2 , the scavenging mode offers the possibility of higher SO_2 removal. Coplanar injection is a variation of the scavenging mode. The sorbent is injected at the point of humidification, typically in a place where it must pass through the water spray before it can disperse throughout the duct. This arrangement should increase SO_2 removal because there is a better chance for more of the sorbent to contact water droplets than with the scavenging mode. The potential disadvantage of this technique is that because the sorbent does not disperse throughout the duct before reaching the humidification zone, the sorbent will have no opportunity to react with SO_3 present in the incoming flue gas. Submicron-sized sulfate aerosols are formed when flue gas containing SO_3 is humidified. Because corona quenching has been observed in the first field of an ESP during duct injection tests where the injected dry sorbent did not scavenge the incoming SO_3 ,² the possibility exists that the gain in SO_2 removal realized from coplanar injection might be offset by degraded ESP performance.

For these tests a coplanar injection nozzle was designed, built, and installed in the horizontal test duct of the DITF. Figure 4-1 shows a schematic drawing of the installation. As Figure 4-1 shows, this 5.75 in. diameter nozzle discharged the dry sorbent approximately 3 in. from the plane defined by the ends of the humidification nozzles. The nozzle was sized so that the exit velocity at the tip of the nozzle would be 60 ft/s (isokinetic to a flue gas flow of 50,000 acfm in the 50 in. wide by 40 in. high duct). The array of humidification nozzles was composed of three nozzles on each of two lances, one above and the other below the point where the dry sorbent was injected. The top lance was depressed 1.25° from the horizontal and the lower lance was elevated 5° from the horizontal. The outer nozzles on each lance were pointed inward by 5°. This arrangement had been determined empirically to minimize wall wetting that occurred in earlier tests with water and slurry as reported

Figure 4-1. Schematic diagram of the installation of the coplanar dry injection nozzle in the horizontal test duct at the DTF.

in Topical Report No. 2.¹ The same Lechler Supersonic nozzles were used for humidification and for slurry injection throughout these tests (2.88 gpm capacity, Model 199.005.23).

These SO₂ removal tests commenced during week 43 of testing and lasted through week 50 of testing (May 14, through July 3, 1991). No tests were conducted during week 44 because of tube leaks at Unit 5 and equipment problems at the DITF. All tests were conducted at a nominal inlet SO₂ concentration of 2000 ppm and system inlet temperature of 300°F.

From weeks 43 through 47, a series of parametric tests to measure SO₂ removal were performed at nominal Ca/S ratios of 1.0, 1.5, and 2.0 at approach temperatures of 25, 35, and 45°F. Also, during week 48, a long-term test was conducted to evaluate ESP performance with dry sorbent injection at a nominal Ca/S ratio of 2.0 and approach temperatures of 45 and 35°F. No recycle ash was injected during these tests. SO₂ removal tests with recycle ash injection were performed during weeks 47, 49, and 50. During week 47 dry recycle ash collected during previous slurry tests was injected. Later, during week 49, recycle ash from dry sorbent injection tests performed during week 48 was injected. Finally, during week 50, reagent dry sorbent was injected along with recycle ash preserved from week 48 of testing.

4.1.1 SO₂ Removal

Tables 4-1 and 4-2 and Figures 4-2 through 4-4 summarize the SO₂ removal data obtained in these tests. The results reported in these tables are usually hourly averages of data made after steady state conditions were reached for the particular test. When possible, these averages were computed during periods that quench probe runs were made so that sorbent utilization based on gas phase removal data could be compared with the results of solids analyses carried out on the quench probe samples and ESP hopper samples taken at the same time as the quench probe samples. The use of a specially designed quench probe to obtain solids samples was discussed in Topical Report No. 2.¹ Heat balance calculations were also made for each of the tests shown in Tables 4-1 through 4-2. These results are shown Appendix A. The method used to make these calculations was also discussed in Topical Report No. 2.¹

As indicated above, nominal approach temperatures of 25, 35, and 45°F were used for these parametric tests. Unfortunately, these tests were approximately 60% complete when it was determined that the J-type thermocouple array at the ESP inlet was reporting an inlet temperature that could be offset from the correct value by as much as 10°F. This problem was quickly corrected and most of the lost temperature information was recovered from other manual measurements of the ESP inlet temperature made for quench probe runs or for ESP inlet mass train measurements. However, much of the intended 35°F approach data turned out to have been closer to 40°F.

The results of experiments with reagent dry sorbent (Mississippi LimeTM Ca(OH)₂) are summarized in Table 4-1 and Figures 4-2 through 4-4. Tests performed with the injection of dry recycle ash from earlier slurry tests, coplanar dry injection tests, or from combined reagent Ca(OH)₂ and dry recycle ash are summarized in Table 4-2 and Figures 4-3 and 4-4. Table 4-1 also presents the results of solids analysis of selected quench probe and ESP hopper samples. Generally, sorbent utilization determined from the analysis of the quench probe samples agrees well with sorbent utilization calculated from the gas phase data. As would be expected, sorbent utilization determined from solids analyses of the ESP inlet hopper samples were higher (usually from one to three percent) than sorbent utilization calculated from the gas phase data.

Table 4-1. SO₂ Removal Data Obtained During Coplanar Dry Sorbent Injection Tests

TEST IDENTIFICATION			GAS PHASE DATA					UTILIZATION FROM ANALYSIS, %			
Test Number	Ca/S Ratio	Approach to Sat, °F.	End of Horiz. Duct	SO ₂ Removal, %	Gas Phase Utilization, %	End of Horiz. Duct	ESP Inlet	ESP Inlet	Q. Probe ESP Inlet	ESP Hoppers Inlet	Outlet
46-DS-03	0.94	21	24	24	30	25	25	28.4		30.6	46.3
46-DS-02	1.43	25	25	33	36	18	23	25.5		27.8	36.7
46-DS-01	1.96	24	33	41	47	17	21	27.6		29.6	40.5
47-DS-03	1.01	37	16	17	21	15	17				
45-DS-03	1.05	39	17	16	21	16	15				
45-DS-03	1.05	38	17	17	20	16	16				
47-DS-02	1.55	37	19	21	28	12	13				
47-DS-01	1.91	35	25	25	33	13	13				
48-DS-03	2.02	37	25	27	35	12	13				
47-DS-01	2.04	39	21	22	29	10	11				
48-DS-04	2.04	35	24	25	33	12	12				
43-DS-04	0.99	44	11	13	17	11	13	15.4	13.2	28.4	28.9
43-DS-04	1.00	44	14	14	19	14	14	15.4	12.6	28.4	28.9
43-DS-02	1.48	45	17	18	23	12	12				
43-DS-03	1.54	43	17	22	23	11	14	14.9	12.0	20.6	36.4
45-DS-02	1.56	47	17	20	25	11	13				
43-DS-03	1.57	43	17	18	25	11	12	14.9	11.8	20.6	36.4
45-DS-02	1.60	47	23	22	27	14	14				
45-DS-01	1.91	45	22	22	30	12	12				
45-DS-01	1.93	45	23	23	31	12	12				
43-DS-01	1.97	40	24	24	32	12	12	13.9	10.6	26.8	31.0
43-DS-01	2.02	40	24	26	35	12	13	13.9	11.4	20.8	31.0
48-DS-01	2.03	44	20	21	30	10	10				
48-DS-02	2.06	45	20	21	31	9	10				

Table 4-2. SO₂ Removal Data Obtained During Coplanar Dry Sorbent Injection Tests
with Recycle Ash Alone and Fresh Sorbent plus Recycle Ash

TEST IDENTIFICATION			GAS PHASE DATA							
Test Number	Source of Recycle Ash	Ca/S Ratio Overall	Recycle Ash	Approach to Sat, °F.	SO ₂ Removal, % End of Horiz. Duct	ESP Inlet	ESP Outlet	End of Horiz. Duct	Gas Phase Utilization, % ESP Inlet	ESP Outlet
Recycle Ash										
50-DSR-02	Dry Sorbent	1.17	1.17	25	25	26	32	22	23	28
49-DR-03	Dry Sorbent	1.09	1.09	36	14	16	21	14	16	21
47-DR-02*	Slurry	1.14	1.14	36	22	24	30	19	21	26
49-DR-01	Dry Sorbent	1.05	1.05	46	11	12	14	11	12	13
49-DR-02	Dry Sorbent	1.18	1.18	46	11	12	14	10	10	13
47-DR-01	Slurry	1.18	1.18	46	19	20	26	16	17	22
Sorbent and Recycle Ash										
50-DSR-02	Dry Sorbent	2.04	0.85	25	36	38	49	18	19	24
50-DSR-03	Dry Sorbent	2.09	0.85	27	35	37	48	17	18	23
50-DSR-01	Dry Sorbent	2.03	0.85	36	29	31	40	14	15	20

- * Analysis of solids samples from this test indicated utilizations of 41.0% for the Quench Probe sample and 43.2, 44.2, and 46.7% for samples from the ESP inlet, middle, and outlet hoppers.

Figure 4-2. Percent of SO_2 removed at the ESP outlet as a function of the approach to saturation. Coplanar dry injection with reagent $\text{Ca}(\text{OH})_2$.

Figure 4-3. Percent of SO₂ removed at the ESP outlet as a function of the Ca/S ratio at a 25°F approach to saturation. Coplanar dry injection with reagent Ca(OH)₂ and reagent Ca(OH)₂ with recycle ash. Earlier non-coplanar dry injection data at a 25°F approach are shown for comparison.

Figure 4-4. Percent of SO₂ removed at the ESP outlet as a function of the Ca/S ratio at a 45°F approach to saturation. Coplanar dry injection with reagent Ca(OH)₂ and reagent Ca(OH)₂ with recycle ash.

At the ESP outlet SO₂ removal data are also shown in Figures 4-2 through 4-4. Figure 4-2 shows how SO₂ removal increases with decreasing approach temperature and increasing Ca/S ratio, for reagent Ca(OH)₂ sorbent. Some of the scatter in these data may be due to the aforementioned inaccuracy in the temperature measurement at the ESP inlet. Figure 4-3 presents SO₂ removal as a function of Ca/S ratio at a nominal 25°F approach and includes data from recycle testing as well as data from earlier tests with reagent Ca(OH)₂ where the sorbent was injected upstream of the humidification nozzles (scavenging mode). Generally, SO₂ removal was unaffected by the type of sorbent used. It should be noted, however, that the recycle ash used for these tests was generated during other coplanar dry sorbent injection tests, and approximately 52% of this material was Ca(OH)₂. Coplanar injection increased SO₂ removal over that obtained when sorbent was injected in the scavenging mode by 5 to 10%, depending on the Ca/S ratio. This is most probably due to the better contact of sorbent and water provided by coplanar injection, especially at lower approach temperatures.

Figure 4-4 presents SO₂ removal as a function of Ca/S ratio at a nominal 45°F approach and includes data from recycle tests (no reagent Ca(OH)₂) conducted with recycle ash preserved from earlier slurry injection (35% Ca(OH)₂ in the recycle ash) and from coplanar dry sorbent injection (52% Ca(OH)₂ in the recycle ash). In this case, the source of the recycle ash affected SO₂ removal. When recycle ash from dry sorbent tests was injected lower amounts of SO₂ were removed than were removed with reagent sorbent. When recycle ash from slurry tests was injected much higher amounts of SO₂ were removed than were removed with reagent sorbent. The reason for these differences is not known. Additional testing would have been required to study the effect, and time was not available in the test program to carry out those tests in view of the relatively low utilizations compared with slurry injection.

4.2 Slurry Injection

As indicated above, parametric testing of the injection of slaked lime slurries and the injection of slurries made from various mixtures of recycled ash and slaked lime slurry was carried out at the DITF as part of the scale-up tests. Also, as part of these slurry injection tests, four other limited series of tests were performed. In the first of these tests, the effect of lower air/liquid ratios on SO₂ removal and wall deposition was evaluated for the six Lechler nozzle array and for a single 12 gpm Lechler nozzle (Model 199.030.23). In the second of these tests, dry recycle ash was injected through the coplanar nozzle while a slaked lime slurry was injected through the Lechler nozzle array. In the third series of tests a single 2.88 gpm Parker-Hannifin nozzle (dual fluid-external mix) was installed on a lance located 30 ft downstream of the array of Lechler nozzles to evaluate the effect of downstream humidification on SO₂ removal. In the fourth series of tests CaCl₂ was added to slaked lime slurries and to mixtures of recycle ash and slaked lime slurry to investigate the effect of this additive on SO₂ removal. Heat balance calculations for these tests are included in Appendices B (slurry tests and downstream humidification tests with the Parker-Hannifin nozzle), C (slurry/recycle tests), D (air-to-liquid ratio tests), and E (CaCl₂ addition tests).

The majority of tests with slaked lime slurry were carried out before testing with dry sorbent injection began (weeks 33-43 of testing). During this time, downstream humidification tests with the Parker-Hannifin nozzle were conducted (week 39 of testing). Later, after the coplanar dry sorbent injection tests were concluded, other tests with slaked lime slurries were performed (weeks 51-54) and air-to-liquid ratio tests were conducted (weeks 57, 68, and 71 of testing). Heat balance calculations for various other slaked lime slurry tests, either preliminary to or in conjunction with

recycle ash addition testing are included in the test summaries below and in Appendix B. Tests with slurries made from mixtures of recycle ash and reagent slaked lime were carried out during weeks 52-54, 66-69, and 81-84. During weeks 82-84 CaCl_2 was added to slaked lime slurry and slaked lime slurry/recycle ash mixtures.

For this report, the results all of the tests were scrutinized and test results were excluded from the data summaries presented here if there were questions as to the accuracy of SO_2 measurements, gas flows or flue gas temperatures. Generally, liquid slurry flow was accurately delivered and measured. However, when humidification water was added to slurry exhausted through the Lechler nozzle array (to maintain a given Ca/S ratio and vary approach temperature) it was found that it was not possible to stabilize humidification water flow because the available flow controller was sized to deliver higher water flows at lower discharge pressures than were used in the slurry pumping system. At the humidification water flows that were typical (< 2 gpm), humidification water flow frequently varied to the point that values recorded by the data acquisition system were incorrect. Many of the heat balance calculations in Appendix A for tests performed from March through May, 1991 (the period when humidification water was in regular use) reflect this inaccuracy by showing a poor heat balance and nonexistent or abnormally low humidification water flow. After May, 1991 when it was realized that metering low water flows was a problem and that the addition of humidification water could also reduce the effective solids content of the slurry to a point where wall wetting could be a problem (because of increased drying times), this practice was halted.

4.2.1 Parametric Reagent Slurry Injection Tests

Tables 4-3 and 4-4 summarize all of the SO_2 removal tests performed with reagent or slaked lime slurry injection that were performed at the DITF. Table 4-3 shows the results of SO_2 removal tests included in Topical Report No. 2¹ and Table 4-4 presents the results of SO_2 removal tests conducted from February, 1991 to the end of testing. Table 4-4 also includes SO_2 removal and gas phase utilization data for both the end of the horizontal duct (1 s of residence time) and for the ESP inlet (1.5 s of residence time). Before February, 1991 SO_2 removal data was not reported at the end of the horizontal duct. The data from Tables 4-3 and 4-4 were also combined in a series of graphs, Figures 4-5 through 4-18. Figure 4-5 summarizes SO_2 removal data at the ESP inlet as a function of Ca/S ratio and Figures 4-6 through 4-9 present the data shown in Figure 4-5 in more detail, showing SO_2 removal at the ESP inlet as a function of Ca/S ratio for four ranges of approach temperature: 20-30°F, 30-40°F, 40-50°F, and 50-55°F. In each figure, SO_2 removal data are further broken down into 5°F increments of approach temperature. SO_2 removal data measured at the ESP outlet are presented in Figures 4-10 through 4-14 and are organized in the same manner as Figures 4-5 through 4-9. Finally, gas phase utilization determined at the ESP inlet and outlet are presented as a function of Ca/S ratio in Figures 4-15 through 4-18. In these figures approach temperature is broken down into increments of 10°F.

Inspection of these figures shows that even though every effort was made to insure that these data were correctly measured there is still some scatter, particularly in SO_2 removal measured at the ESP inlet. For example, at the ESP inlet, data from test 43-SL-01 show much higher SO_2 removals than appear to be consistent with other data at a 20-25°F approach. Because these data clearly conflict with other data taken at different times the results from this particular test should probably be disregarded. Likewise, in the approach range of 30-40°F, there appears to be a difference in SO_2 removal measured from tests 42-SL-04, 43-SL-02, and 54-SL-01 and the rest of the data. During tests 42-SL-04 and 43-SL-02 much higher SO_2 removals were measured than are suggested by the rest

Table 4-3. Results of Earlier SO₂ Removal Tests Carried out at the DITF

Test #	Ca/S Ratio	Approach (°F)	Inlet SO ₂ (ppm)	--- SO ₂ Removal, (%) ---		--- Gas Phase Util. (%) ---	
				ESP Inlet	ESP Outlet	ESP Inlet	ESP Outlet
28-SL-07	1.03	25	1790	46	52	44	51
28-SL-04	1.43	25	1909	54	64	38	45
28-SL-04	1.54	25	1805	56	67	36	44
28-SL-04	1.60	23	1773	58	70	36	44
28-SL-04	1.60	24	1780	57	70	36	44
25-SL-02	3.27	21	1156	78	90	24	27
28-SL-07	0.98	28	1852	45	50	46	51
28-SL-07	1.01	27	1781	45	51	44	51
25-SL-04	1.44	30	2734	50	71	35	50
25-SL-04	1.45	28	2764	52	71	36	49
28-SL-01	2.10	27	1775	62	80	29	38
28-SL-01	2.15	28	1700	60	79	28	37
28-SL-06	0.99	35	1875	43	51	43	51
28-SL-06	1.03	35	1799	44	50	42	49
28-SL-06	1.07	35	1702	44	52	41	49
28-SL-02	1.49	35	1804	45	56	30	38
28-SL-03	1.49	35	1873	49	59	33	40
28-SL-03	1.49	35	1869	52	61	35	41
28-SL-02	1.51	35	1788	46	59	30	39
27-SL-02	1.93	35	1875	55	66	29	34
24-SL-02	1.95	35	1788	54	68	28	35
24-SL-02	2.86	32	1167	60	75	21	26
25-SL-05	1.27	40	2764	44	58	35	46
25-SL-03	1.45	37	2146	48	63	33	43
29-SL-02	1.97	38	1766	53	61	27	31
29-SL-02	2.02	37	1773	56	67	28	33
29-SL-02	2.06	37	1752	55	66	27	32
27-SL-02	2.09	38	1738	53	67	26	32
20-SL-03	2.20	38	1205	49	56	22	26
20-SL-01	2.32	38	1186	51	60	22	26
24-SL-01	2.88	39	1253	56	68	20	24
28-SL-05	1.04	43	1803	37	41	35	40
28-SL-05	1.05	43	1780	36	40	34	38
28-SL-05	1.05	44	1790	37	42	36	40
25-SL-01	1.83	43	1770	49	63	27	34
27-SL-01	2.15	43	1692	49	61	23	29
27-SL-01	2.15	45	1679	47	60	22	28
20-SL-05	2.23	42	1216	51	61	23	27
20-SL-02	2.43	43	1213	50	59	20	24
26-SL-01	1.52	50	1771	36	42	23	28
26-SL-02	1.75	46	1794	45	55	26	32
29-SL-01	1.85	49	1878	47	55	26	30
29-SL-01	1.91	47	1836	50	61	26	32
21-SL-01	1.98	48	1252	50	62	25	32
20-SL-02	2.29	48	1271	47	57	20	25
21-SL-01	2.34	47	1064	49	62	21	27
25-SL-06	1.30	56	2790	36	44	28	34
26-SL-03	1.64	56	1804	41	47	25	29
21-SL-01	2.00	53	1247	45	60	23	30
21-SL-01	2.01	52	1227	48	60	24	30
21-SL-01	2.08	55	1201	48	61	23	29
21-SL-01	2.15	53	1151	49	63	23	29
21-SL-01	2.17	51	1129	50	62	23	29
21-SL-01	2.22	56	1159	52	62	23	28
21-SL-01	2.29	51	1137	55	66	24	29

Table 4-4. Results of SO₂ Removal Tests with Reagent Lime Slurry Carried out Since 2/91

Test #	Ca/S Ratio	Approach (°F)	Inlet SO ₂ (ppm)	SO ₂ Removal, (%)			Gas Phase Utilization, (%)		
				End H Duct	ESP Inlet	ESP Outlet	End H Duct	ESP Inlet	ESP Outlet
35-DSR-04	1.02	23	2112	46	46	56	45	46	55
34-SL-04	1.02	24	1990	47	48	58	46	47	57
38-SL-03	1.29	25	1983	40	41	52	31	32	40
38-SL-01	1.58	23	1991	53	55	71	33	35	45
68-SL-01	1.62	23	3289	--	49	60	--	30	37
39-SL-03	1.78	23	1982	--	58	76	--	33	43
39-SL-01	1.79	24	2009	--	57	72	--	32	40
38-SL-02	1.79	22	1973	56	57	74	31	32	41
38-SL-02	1.82	24	1946	54	57	74	30	31	40
38-SL-04	1.91	26	1992	--	54	67	--	28	35
38-SL-04	1.92	25	1994	--	53	68	--	28	35
34-SL-01	2.00	26	2020	56	57	76	28	28	38
33-SL-03	2.01	27	1350	61	62	74	30	31	37
43-SL-01	2.01	24	1992	61	71	79	30	35	39
43-SL-01	2.05	24	1979	--	75	81	--	37	40
37-SL-02	2.06	22	2095	53	59	75	26	28	36
43-SL-01	2.07	24	1982	--	75	83	--	36	40
43-SL-01	2.08	24	1986	--	75	84	--	36	40
34-SL-02	2.10	25	2007	57	60	79	27	29	38
33-SL-05	2.14	19	1843	57	59	78	27	27	36
37-SL-03	2.15	24	1954	53	57	74	25	26	34
38-SL-03	2.16	25	1990	56	59	76	26	27	35
37-SL-02	2.17	22	2008	56	61	76	26	28	35
77-SL-03	2.22	25	2084	59	61	81	26	27	36
37-SL-04	2.22	22	1978	58	61	75	26	27	34
78-SL-02	2.34	25	2626	55	58	77	23	25	33
37-SL-04	2.41	22	1884	58	62	79	24	26	33
78-SL-01	4.91	26	1077	70	79	92	14	16	19
53-SL-03	1.62	34	1927	43	45	54	27	28	33
68-SL-01	1.70	31	3260	--	47	59	--	28	35
53-SL-01	1.72	37	1964	46	47	57	27	28	33
54-SL-03	1.78	37	2116	44	46	55	25	26	31
54-SL-01	1.80	39	2023	39	40	48	22	22	27
53-SL-02	1.81	34	1978	49	50	60	27	28	33
54-SL-03	1.84	38	2096	44	47	55	24	25	30
51-SL-01	1.85	35	2035	50	52	64	27	28	34
54-SL-03	1.85	36	1989	46	48	58	25	26	32
51-SL-02	1.85	37	2028	52	54	65	28	29	35
42-SL-04	1.92	36	1983	--	60	64	--	31	34
42-SL-04	1.94	36	1977	--	60	65	--	31	33
54-SL-03	1.97	38	1988	47	50	57	24	25	29
57-SL-03	1.98	36	2017	49	51	63	24	26	32
54-SL-03	1.99	39	2008	48	48	57	24	24	29
42-SL-02	1.99	33	1954	--	57	63	--	28	32
42-SL-04	1.99	35	1922	--	60	67	--	30	33
42-SL-02	1.99	34	1981	--	59	66	--	29	33
42-SL-02	2.01	33	1955	--	58	66	--	29	33
57-SL-02	2.02	36	2017	48	49	63	24	24	31
54-SL-03	2.07	40	1958	49	50	59	24	24	28
54-SL-03	2.08	40	1947	51	52	61	24	25	30
54-SL-03	2.08	39	1962	50	50	60	24	24	29
54-SL-03	2.10	32	1875	46	48	58	22	23	28
57-SL-04	2.11	36	2059	51	53	67	24	25	32
52-SL-01	2.13	36	1986	52	53	64	24	25	30
76-SL-01	2.13	39	2071	46	48	63	22	23	30
57-SL-01	2.18	35	2014	50	52	64	23	24	29
65-SL-01	1.49	44	2496	38	40	46	26	27	31
65-SL-02	1.57	49	2396	37	39	47	24	25	30
39-SL-04	1.60	47	2001	--	38	46	--	24	29
65-SL-01	1.66	44	2452	40	41	48	24	25	29
65-SL-01	1.69	43	2458	40	41	49	23	24	29
74-SL-01	1.73	41	2078	39	42	48	23	24	28
34-SL-03	1.82	43	1973	43	46	58	24	25	32
52-SL-03	1.83	42	1943	51	53	62	28	29	34
52-SL-02	1.84	41	1968	49	51	61	27	28	33
33-SL-04	1.93	43	1870	53	52	63	27	27	33
33-SL-04	1.93	47	1882	48	47	58	25	25	30
54-SL-03	2.13	42	1906	50	52	61	23	24	29
33-SL-01	2.21	45	1357	48	51	62	22	23	28
33-SL-02	2.25	45	1263	47	49	58	21	22	26

Figure 4-5. Percent of SO₂ removed at the ESP inlet as measured by the gas sampling system. Summary of all data at all approach temperatures.

Figure 4-6. Percent of SO₂ removed at the ESP inlet as measured by the gas sampling system. Summary of test data for approach temperatures from 19 to 30°F.

Figure 4-7. Percent of SO₂ removed at the ESP inlet as measured by the gas sampling system. Summary of test data for approach temperatures from 31 to 40°F.

Figure 4-8. Percent of SO₂ removed at the ESP inlet as measured by the gas sampling system. Summary of test data for approach temperatures from 41 to 50°F.

Figure 4-9. Percent of SO₂ removed at the ESP inlet as measured by the gas sampling system. Summary of test data for approach temperatures from 51 to 56°F.

Figure 4-10. Percent of SO₂ removed at the ESP outlet as measured by the gas sampling system. Summary of all data at all approach temperatures.

Figure 4-11. Percent of SO₂ removed at the ESP outlet as measured by the gas sampling system. Summary of test data for approach temperatures from 19 to 30° F.

Figure 4-12. Percent of SO₂ removed at the ESP outlet as measured by the gas sampling system. Summary of test data for approach temperatures from 31 to 40°F.

Figure 4-13. Percent of SO₂ removed at the ESP outlet as measured by the gas sampling system. Summary of test data for approach temperatures from 41 to 50°F.

Figure 4-14. Percent of SO₂ removed at the ESP outlet as measured by the gas sampling system. Summary of test data for approach temperatures from 51 to 56°F.

20 - 30°F, GAS SAMPLING DATA

Figure 4-15. Percent of sorbent utilized at the ESP inlet and outlet as determined by the gas sampling system. Summary of test data for approach temperatures from 20 to 30°F.

30 -40°F, GAS SAMPLING DATA

Figure 4-16. Percent of sorbent utilized at the ESP inlet and outlet as determined by the gas sampling system. Summary of test data for approach temperatures from 30 to 40°F.

40 -50°F, GAS SAMPLING DATA

Figure 4-17. Percent of sorbent utilized at the ESP inlet and outlet as determined by the gas sampling system. Summary of test data for approach temperatures from 40 to 50°F.

50 -55°F, GAS SAMPLING DATA

Figure 4-18. Percent of sorbent utilized at the ESP inlet and outlet as determined by the gas sampling system. Summary of test data for approach temperatures from 50 to 55°F.

of the data and during test 54-SL-01 much lower SO_2 removals were measured than are suggested by the rest of the data. Again, because these data clearly conflict with the preponderance of other data in this range of approach temperatures the results of these tests should probably be disregarded.

Sorbent Utilization as a Function of Particle Size During test 34-SL-02 (March 12, 1991) as part of a separate test series devoted to measuring ESP emissions as a function of SCA with reagent slurry injection, a composite ESP hopper sample was prepared for analysis, and a portion of this sample was segregated by size with a BAHCO particle size classifier. Ten size fractions were obtained. Each size fraction, as well as the composite sample, was then analyzed to measure sorbent utilization. The results of these analyses are reported in Table 4-5. As this table shows, much of the mass in the sample was greater than $25\ \mu\text{m}$ in size. This largest size fraction also had the lowest calcium content (and sorbent utilization) suggesting that most of the reagent slurry was $25\ \mu\text{m}$ in size or less. Calcium content appeared to be uniformly distributed throughout the other size fractions with a tendency to increase as particle size decreased. On the other hand, sorbent utilization was greatest in a size range from 2.3 to $7.7\ \mu\text{m}$.

Sorbent Utilization at the ESP Inlet For this report no systematic attempt was made to present the results of laboratory analyses of the solids samples collected from each test with reagent slurry, either from quench probe runs or from ESP hopper samples. This is because it was determined that the discrepancy between sorbent utilization as determined from gas phase measurements and from solids analysis of quench probe samples or ESP hopper samples could be resolved by timely measurement of slurry properties (% solids, $\text{Ca}(\text{OH})_2$ content, density) and accurate knowledge of inlet flue gas flow. It was also found that the water content in the incoming flue gas tended to vary, making accurate knowledge of the water content in the incoming flue gas (to determine adiabatic saturation temperature) imperative.

Temporal variations in slurry composition were normal for tests that lasted long enough to require that the slaker be operated during the test to generate more reagent slurry. $\text{Ca}(\text{OH})_2$ content in the slurry could change from the beginning to the end of the test by as much as 1%. After this was realized, a practice was made of obtaining slurry samples whenever solids samples were taken or during periods of stable operation when it was planned to perform heat balance calculations.

Although the inlet flue gas flow was measured by a calibrated inlet venturi, it was necessary to purge the inlet venturi lines with high pressure air before the start of each test to insure that pressure drop measurements across the inlet venturi were correct. As a quality assurance practice, after it was discovered that inlet venturi flow could be in error if the venturi pressure taps had not been purged, independent flow measurements were made at the bottom of the 60 ft vertical duct before the start of each test. If these measurements did not agree with inlet flow as measured from the venturi, corrective action to reconcile the discrepancy was taken before testing would begin.

Finally, the Servomex PSA 402C water analyzer turned out to be a very useful addition to the DITF gas sampling system because it provided a consistently accurate measurement of the water vapor concentration in the flue gas. Because water vapor concentration in the flue gas from the Unit 5 boiler could change with boiler load or with coal variation (wet coal, in particular), the adiabatic saturation temperature could change and the approach to saturation would rise or fall while the ESP inlet temperature was held constant by the PLC (which controlled the slurry flow rate to meet a desired ESP inlet temperature). As will be shown below, this type of change in adiabatic saturation temperature did occur during testing. As with the quality assurance practice followed for flue gas

Table 4-5. Results of Solids Analyses Carried out on a Composite ESP Hopper Sample from Test 34-SL-02, 3/12/91.¹

Size Cut (μm)	Cumulative Weight %	Δ Weight %	Ca⁺² (%)	SO₃⁻² (%)	Utilization (%)
1.5	1.11	1.11	31.7	20.6	32.5
2.3	3.08	1.97	31.3	22.0	35.2
4.4	10.14	7.06	29.7	21.5	36.2
7.7	19.81	9.67	29.7	21.0	35.4
10.8	28.98	9.17	30.3	19.9	32.9
17.7	42.30	13.32	29.6	18.9	32.0
22.4	48.53	6.23	29.0	18.0	31.1
25.0	51.97	3.44	29.1	18.4	31.7
25 $\leq$ 250	100.00	48.03	16.1	7.5	23.3
> 250 ²			14.2	8.6	30.3
Blend	All		24.0	13.7	28.6
Size Weighted Avg.	All		23.2	13.9	30.0

1. Gas Phase Utilization of 29% at ESP inlet, 38% at the ESP Outlet.
2. Greater than 60 Mesh.

inlet flow measurement, inlet water vapor content was measured whenever an inlet velocity traverse was performed. If a discrepancy was noted between the manual measurement and that provided by the PSA 402C, the problem was corrected before testing began. Fortunately, this rarely happened.

Another possible source of error that could have caused the ESP inlet gas phase utilization values to disagree with those values determined from analysis of quench probe samples was the choice of location where the quench probe samples were taken. Because quench probe samples are taken at one flow rate, traversing with the quench probe (and sampling at the local duct flow rate) was not feasible. Thus, a point in the center of the duct was chosen to obtain the quench probe samples. If this was not a representative point in terms of flue gas flow or mass concentration then quench probe samples would be nonrepresentative.

To determine if the quench probe samples were representative, a series of quench probe runs were planned at different points in the sampling plane at the ESP inlet test location. These tests would also determine if accurate knowledge of flue gas flow and slurry composition would help reconcile the differences in solids and gas phase utilization that have been observed in the past.

During Week 54 of testing (Test 54-SL-03, August 2, 1991), a series of nine quench probe runs were made at the ESP inlet sampling location. Each run was made at one of three sampling ports (top, middle, bottom) and/or traverse points (in, near the far duct wall, midpoint of the duct, or out, close to the near duct wall), making a nine-point grid. During these runs the nominal test conditions were held to a 35°F approach, 2000 ppm of SO₂ at the system inlet, and a Ca/S ratio of 2.0. During each quench probe run ash/sorbent samples were taken from each ESP hopper and a sample of slurry was obtained. Table 4-6 presents the results of this test and Table 4-7 compares the results of sorbent utilization calculated from chemical analyses of the quench probe catches and three selected ESP inlet hopper samples with sorbent utilization calculated from averaged gas phase data. More detailed information on this test can be obtained from the heat balance calculations for each quench probe run in Appendix B.

The data from Table 4-6 show that the water vapor content in the flue gas dropped throughout the day, from 9.9% between 1015 and 1045 hours to 8.2% between 1730 to 1745 hours. Although the ESP inlet temperature was maintained from 168°F to 170°F throughout the day, the change in water vapor content caused the adiabatic saturation temperature to drop by about 5°F over the test. Thus, the nominal 35°F approach temperature increased from 36°F to 42°F by the end of the test. The effect of increasing approach temperature was offset, for the most part, by an increasing Ca/S ratio. Because of changes in the composition of the reagent lime slurry throughout the day, the Ca/S ratio increased from 1.85 to 2.13 by the end of the test.

Table 4-7 presents the results of chemical analyses carried out on the solids samples obtained during this test. Shown in this table are the mass loadings measured for each quench probe run along with sorbent utilization as determined from chemical analyses of the quench probe catch and three selected ESP inlet hopper samples as well as sorbent utilization calculated from gas analysis data recorded during each quench probe run. The agreement between sorbent utilization as determined from chemical analyses and from gas phase data is, with two exceptions, very good. The exceptions are noted in the table in boldface. From the gas sampling data sorbent utilization averaged between 24% and 26% throughout the test. With the exception of the quench probe runs from the middle and bottom sampling ports where the sampling point was as far out as possible sorbent utilization from the quench probe runs also varied from 24% to 26%. In the case of the two quench probe runs

Table 4-6. Results for Test 54-SL-03, 8/2/91.

Time	Ca/S Ratio	Approach (°F)	Inlet SO ₂ (ppm)	Inlet Water (%)	Slurry % Ca(OH) ₂	ESP Inlet -----		ESP Outlet -----	
						Δ SO ₂ (%)	Util. (%)	Δ SO ₂ (%)	Util. (%)
1013-1045	1.85	36	1990	9.9	18.58	48	26	58	32
1114-1130	1.78	37	2120	9.7	18.80	46	26	55	31
1202-1213	1.84	38	2100	9.6	19.22	47	25	55	30
1251-1321	1.97	38	1990	9.3	19.67	50	25	57	29
1357-1427	1.99	39	2010	9.1	19.90	48	24	57	29
1500-1524	2.07	40	1960	8.8	19.89	50	24	59	28
1605-1618	2.08	39	1960	8.5	19.82	50	24	60	29
1648-1705	2.08	40	1950	8.4	19.77	52	25	61	30
1726-1740	2.13	42	1910	8.2	19.70	52	24	61	29

Table 4-7. Comparison of Sorbent Utilization from Solids Analysis and from Gas Phase Measurements for Test 54-SL-93, 8/2/91.

Time	----- Quench Probe Run Data -----			----- Solids Analysis Data -----		----- Gas Phase Data ¹ -----	
	Sample Location Port	Point in Port	Mass Loading (gr/acf)	Quench Probe ² % Utilization	ESP Inlet Hopper % Utilization	ESP Inlet % Utilization	ESP Outlet % Utilization
1605 - 1618	Top	In	5.96	24.2		24.1±0.7	29.0±0.5
1648 - 1705	Top	Middle	4.53	24.8		25.1±0.6	29.6±0.8
1726 - 1740	Top	Out	4.20	24.4	26.4	24.5±1.1	28.9±1.1
1251 - 1321	Middle	In	5.07	24.8		25.3±1.3	28.9±0.6
1357 - 1427	Middle	Middle	5.50	24.0	26.4	24.3±0.8	28.9±0.7
1500 - 1524	Middle	Out	5.03	28.4		24.1±1.3	28.4±0.8
1013 - 1045	Bottom	In	6.43	26.0		26.0±0.7	31.6±0.8
1114 - 1130	Bottom	Middle	5.97	24.8	28.8	25.7±0.7	31.2±0.7
1202 - 1213	Bottom	Out	4.45	28.9		25.4±1.0	30.2±1.1

¹ Data averaged over the time period shown, ± one standard deviation.

² Quench Probe samples obtained at ESP Inlet test station during the time period shown.

that did not agree with the gas phase data, sorbent utilization was from 3.5% to 4.3% less than that determined by solids analysis and was closer to that measured for the ESP inlet hopper samples. In all other tests, quench probe samples were taken at the geometrical midpoint of the duct (the middle point in Table 4-7).

These data suggest that when variations in slurry properties are taken into account it is possible to obtain good agreement between sorbent utilization as determined from gas analysis or from solids analysis of quench probe catches. Thus, in subsequent testing, slurry samples were taken whenever solids samples were taken and/or whenever the system had stabilized so that heat balance calculations would be meaningful. Likewise, in the analysis of previous data, the heat balance calculations shown in the appendices of this report were recalculated, when possible, to reflect the most recent slurry analysis.

These data also suggest that sorbent utilization as determined from inlet ESP hopper samples is somewhat higher than that measured from quench probe catches or for gas phase data. This is certainly reasonable because the ESP inlet field was rapped every 3 minutes so, aside from material that fell out directly into the first ESP hopper, ash and sorbent collected in the first field of the ESP were exposed to flue gas for up to three minutes before being collected in the hopper.

4.2.1.1 Air/Liquid Ratio Tests with Lechler Nozzles

The 2.88 gpm Lechler nozzles used for most of the SO₂ removal tests at the DITF were usually operated at an inlet air pressure of from 70 to 80 psig. Early tests with water at the DITF revealed that high inlet air pressures were required to minimize wall wetting. These Lechler nozzles are designed to reach supersonic (choked) flow at an air pressure of 60 psig, but at flow rates of 9 to 12 gpm (1.5 to 2.0 gpm per nozzle) higher inlet air pressures were required to keep from wetting the duct walls. Operation at such high inlet pressures meant that the air-to-liquid (A/L) ratio for these nozzles averaged from 0.8 to 1.1 instead of the design value of 0.5. These high A/L values were mainly an artifact of operating the nozzles at less than their rated flow. However, concern was expressed on the part of other DOE contractors in the Duct Injection program that nozzles of this type would be unsuitable for full-scale applications because of the energy needed to compress the large volume of air that operation at these A/L ratios requires. Therefore, a series of tests were planned to determine if the Lechler nozzles could function at or near their design A/L ratio. Three separate tests were conducted. During Week 57 of testing (August 19-22), a series of tests were performed where the A/L ratio was reduced to as low as 0.5 by reducing the pressure of the compressed air to the nozzles. Later, during week 68 of testing (November 6), a more realistic test was performed when the slurry flow rate to the nozzles was raised to the point where an A/L ratio of 0.61 was achieved. Finally, during week 71 of testing (November 25-27), a single special 12 gpm Lechler nozzle (Model 199.030.23) was tested at A/L ratios of from 0.48 to 0.61.

2.88 gpm Lechler Nozzles During week 57 of testing SO₂ removal tests were performed with the six Lechler nozzle array at nozzle air pressures of 70, 60, and 50 psig at a nominal Ca/S ratio of 2.0 and an approach temperature of 35°F. These air pressures correspond to A/L ratios of 0.7, 0.6, and 0.5, respectively. These tests were conducted with the standard nozzle configuration: a total of six Lechler supersonic nozzles arranged with three nozzles per lance. The inner and outer nozzle on each lance was canted 5° toward the center of the duct; the upper lance was depressed by 2° and the lower lance was horizontal.

The results of these tests are summarized in Table 4-8. The first test (at a nominal A/L ratio of 0.7) was repeated because an air hose in the duct burst at some point during the test. The SO₂ removal data from Table 4-8 and the fact that there were no deposits in the horizontal duct at the conclusion of the test suggest that the hose burst at the end of the test. For this brief test series the major conclusion that can be reached is that A/L ratio apparently does not affect SO₂ removal or sorbent utilization, at least down to an A/L ratio of 0.5 for Lechler nozzles. Unfortunately, the spray pattern of the Lechler nozzles is apparently affected by air pressure. As indicated above, at an A/L ratio of 0.7 there were no duct deposits of note. However, after testing for a little over four hours at an A/L ratio of 0.6 it was found that the turning vanes at the end of the horizontal duct (1 second of residence time downstream of the nozzles) were about 30% plugged. Still, there was no appreciable deposit of sorbent on the surfaces of the duct itself. At an A/L ratio of 0.5, after testing for slightly over five hours, it was found that the turning vanes at the end of the horizontal duct were approximately 60% plugged. In this case there were heavy sorbent/ash deposits downstream of the turning vanes "growing" on the downstream sides of the vanes themselves. Also, a layer of sorbent and ash approximately 6 in. deep had accumulated on the horizontal duct floor after the first hopper. It appears that the spray pattern of the nozzles becomes more centralized as the air pressure (or A/L ratio) is decreased. In situ particle size distribution tests would be required to confirm this hypothesis.

The above tests addressed the question of A/L ratio by varying air pressure. Later, during week 68 of testing, the slurry flow rate was increased to the point where an A/L ratio of 0.61 was achieved at 80 psig of inlet air pressure (Test 68-SL-01). The results of this test are also presented in Table 4-8. For this test it was necessary to run the DITF without dilution to increase the inlet temperature and flue gas flow to as high as was possible. Although slurry flows of 17.3 gpm were measured (for an A/L ratio of 0.61), the slurry flow rate could have been higher. This is because the flow meter used to measure and control slurry flow was operated at its maximum possible flow (20 mA on a 4-20 mA loop). However, the heat balance calculations for this test indicated that very little additional water would have been required. As far as this brief test can indicate, no effect of A/L ratio on SO₂ removal was observed.

Although these nozzles did operate at a lower A/L ratio than usual (for day-to-day testing), when the horizontal duct was inspected after test 68-SL-01 was concluded a large solids deposit was found on the duct floor between the first and second hopper. It is encouraging that these nozzles did operate at lower A/L ratios at their rated flow but more testing would have been required to determine how to minimize duct deposits under those operating conditions.

12 gpm Lechler Nozzle During week 71 tests with reagent slurry injection were also conducted to demonstrate the ability to scale this nozzle up and to evaluate the behavior of a 12 gpm Lechler nozzle at design flow. Figure 4-19 shows how the single Lechler nozzle was mounted in the horizontal test duct. Externally and internally this nozzle appears to be quite like the smaller 2.88 gpm Lechler nozzle, but considerably larger. These tests showed that the larger Lechler nozzle could be operated at A/L ratios in the neighborhood of 0.5. The results of these tests are shown in Table 4-8. In general, it was found that when the large Lechler nozzle was operated up to its design flow (an A/L ratio of about 0.55) no problems with duct deposits were encountered and no effect on SO₂ removal was observed compared with the smaller nozzle. However, when the design flow was exceeded, duct deposits were created. As with the small Lechler nozzles further tests would have been required to determine if these deposits could be minimized. In particular, it would have been desirable to repeat these tests with a higher solids content recycle ash-slurry mix because higher solids content slurries tend to dry more quickly.

Table 4-8. Air/Liquid Ratio Test Summary.

Test #	Approach (°F)	SO ₂ at Inlet (ppm)	Nozzle Flow (gpm)	Ca/S Ratio Lime Slurry	Air Pressure (psig)	Air/Liquid Ratio	ΔSO ₂ . % ESP Inlet	ΔSO ₂ . % ESP Outlet
57-SL-01 ¹	35	2010	13.0	2.18	70	0.72	52	64
57-SL-02 ¹	36	2020	12.6	2.02	70	0.73	49	63
57-SL-03 ¹	36	2020	12.8	1.98	60	0.63	51	63
57-SL-04 ¹	36	2060	13.5	2.11	50	0.50	53	67
68-SL-01 ²	31	3260	17.3	1.70	80	0.61	47	59
71-SL-01 ³	44	2080	10.9	1.69	80	0.61	45	52
	36	2070	11.8	1.83	80	0.56	51	61
	26	2060	13.4	2.30	80	0.48	60	76
71-SL-02 ³	41	2010	11.6	2.09	80	0.54	52	63
71-SL-03 ³	37	2050	11.5	2.00	80	0.57	51	64

1. Six 2.77 gpm Lechler nozzles.
2. Full flow test for six 2.77 gpm Lechler nozzles.
3. Single 12 gpm Lechler nozzle.

Figure 4-19. Schematic diagram of the installation of the 12 gpm Lechler nozzle in the horizontal test duct at the DITF.

4.2.1.2 Reagent Slurry Injection with Downstream Humidification

In an attempt to investigate modes of operation that would permit low approach temperatures to be reached at low-to-moderate Ca/S ratios, two-stage humidification experiments were conducted during week 39 of testing (April 15-19). In this set of experiments, a single 2.88 gpm Parker-Hannifin nozzle was installed approximately 30 ft downstream of the main nozzle array. Approach temperatures of 35°F and 45°F were maintained at the main nozzle lance, and humidification water was added at the Parker-Hannifin nozzle to reach the desired approach temperature.

These tests were quite successful in that very low approach temperatures were reached and held without wall wetting. During the most strenuous test of this procedure it was possible to operate the main nozzle lance at an approach of 45°F and to use the Parker-Hannifin nozzle to reduce the approach temperature to 10°F. When this was first attempted the approach temperature was maintained at approximately 10°F for over an hour. Subsequent inspection of the duct revealed no duct wall deposits. One disadvantage of this approach is that the Parker-Hannifin nozzles tend to plug whenever even a slight bit debris enters the nozzle in the water line. The humidification water was not filtered, and while it was not potable, it was usually clear. When this experiment was repeated the nozzle plugged almost immediately on startup and the DITF had to be brought off line so that the nozzle could be cleaned.

Table 4-9 and Figure 4-20 summarize the results of these tests. As Figure 4-20 shows, at a nominal Ca/S ratio of 1.8, adding humidification water to reduce the approach to saturation from 45°F to 10°F increases SO₂ removal by approximately 15% at the ESP inlet and by almost 25% at the ESP outlet. Likewise, adding humidification water to reduce the approach to saturation from 45°F to 25°F increases SO₂ removal by approximately 10% at the ESP inlet or outlet. However, if humidification water is added at the main lance rather than downstream, much higher SO₂ removals are possible than with downstream humidification. At a 25°F approach with water added at the main lance to maintain the Ca/S ratio at a nominal value of 1.8, the results of these tests show that the amount of SO₂ removed is essentially the same as is removed when an approach of 10°F is achieved with downstream humidification. Clearly, the more effective method to increase SO₂ removal is to add humidification water at the main lance.

4.2.2 Injection of Reagent Slurry with Recycle Ash Addition

The process of recycling rather than discarding waste sorbent/ash solids as a means of increasing calcium utilization is common practice at spray dryer installations in the utility industry. Recycling spent solids is especially important in the economics of duct injection because slurry droplet size and in-duct residence times tend to lower calcium utilization when compared to conventional spray dryers. However, encouraging results were obtained from experiments conducted at the DITF with reagent slurry/recycle ash mixtures.

Two types of experiments were conducted with reagent slurry/recycle ash mixtures. The first of these were "single pass" experiments in which waste ash from an earlier experiment with reagent slurry was either injected as a dry solid (through the coplanar dry injection nozzle) or was mixed with reagent slurry and injected into the duct. If the recycle ratio, R , is expressed as the ratio of the mass of recycle ash solids to the mass of pebble lime feed, R values ranging from 1.0 to 5.5 were investigated in these tests. The second type of experiments that were conducted were typical of the type of operation that is usual at full-scale spray dryer installations. In these experiments, a constant portion of the spent ash and sorbent collected in the ESP was reintroduced (recycled) into the reagent slurry

Table 4-9. Results of SO₂ Removal Tests with Downstream Humidification Provided by a Single Parker-Hannifin Nozzle, 30 ft Downstream of the Point of Slurry Injection.

Test #	Ca/S Ratio	Approach, (°F) ----		Inlet SO ₂ (ppm)	ESP Inlet -----		ESP Outlet -----	
		Slurry Only	With Added Water		Δ SO ₂ (%)	Util. (%)	Δ SO ₂ (%)	Util. (%)
39-SL-01	1.94	35	23	1970	50	26	65	34
39-SL-02*	1.79	24	--	2010	57	32	72	40
39-SL-02	1.81	45	25	1990	50	28	65	36
39-SL-03*	1.78	23	--	1980	58	33	76	43
39-SL-04	1.75	47	26	1950	48	27	63	36
39-SL-04	1.77	47	10	1920	61	35	80	45
39-SL-05	1.77	45	23	1990	50	28	66	37
39-SL-05	1.76	45	15	2000	59	33	75	43
39-SL-05	1.77	45	9	1990	58	33	75	42

* Humidification water to reach approach added at main lance, no water added downstream.
With reagent slurry flow alone, the approach temperature would have been ~ 45°F.

Figure 4-20. Percent of SO₂ removed at the ESP inlet and outlet for approach temperatures from 10 to 45°F. Summary of test data for reagent slurry injection with and without downstream humidification at a Ca/S ratio of 1.8.

while the rest of the spent ash and sorbent mixture was discarded as would be the case in a continuous or multi-pass operation. These tests were continued until the amount of $\text{Ca}(\text{OH})_2$ in the spent ash and sorbent mixture stabilized.

4.2.2.1 Coplanar Injection of Dry Recycle Ash with Humidification from Reagent Lime Slurry

During week 35 of testing (March 20-21) while work was under way to start slurry/recycle ash injection dry recycle solids (from reagent slurry injection tests) were blown in through a recently fabricated coplanar dry injection nozzle positioned midway between the upper and lower nozzle lances during reagent slurry injection. This coplanar nozzle was later used during the series of dry injection tests reported above.

Two tests were performed (36-SDR-03 at a 45°F approach and 36-SDR-04 at a 25°F approach). During both of these tests reagent slaked lime slurry was first injected and SO_2 removal was measured before dry sorbent was added at the coplanar nozzle. Table 4-10 summarizes the results of these measurements. More detailed information on these tests is available from the heat balance calculations in Appendix C. As might be expected, the result of adding dry recycle ash was greater at an approach of 25°F. At a 45°F approach, SO_2 removal was increased by 3% at the ESP inlet and at the ESP outlet SO_2 removal was increased by 6%. At a 25°F approach SO_2 removal was increased by 5% at the ESP inlet, and at the ESP outlet SO_2 removal was increased by 7%.

4.2.2.2 Single Pass Reagent Slurry/Recycle Ash Tests

From weeks 51 through 54 of testing (July 12-30) single pass reagent slurry/recycle ash tests were conducted at the DITF. As indicated above, spent sorbent and ash from previous tests with reagent lime slurry was mixed with reagent lime slurry and injected into the horizontal test duct. The six Lechler nozzle array was used for all of these tests. Recycle ratios (based on the mass ratio of recycle ash to pebble lime required to generate the reagent slurry) of from 1.0 to 5.5 were tested. The results of these tests are presented in Tables 4-11 and 4-12. Test results in these tables are sorted on approach temperature. Table 4-11 shows that high SO_2 removals were achieved.

Table 4-12 presents the results of chemical analyses (to determine sorbent utilization) performed on ESP hopper samples from recycle slurry tests carried out during weeks 51 through 54 of testing. Most of these analyses were performed on ESP inlet hopper samples but two ESP outlet hopper samples were also analyzed. Table 4-12 also shows the results of sorbent utilization as determined from averaged gas phase data at the inlet and outlet of the ESP for the same tests during the times the solid samples were collected.

Because the mass loading entering the ESP is generally greater for recycle ash/slurry tests than for fresh lime slurry tests, it should be expected that solids samples from the ESP inlet hopper would dominate in the collected ash. Also, because the inlet ESP hopper samples are collected after being exposed to the flue gas for several minutes longer than solids collected from quench probe samples, the results of sorbent utilization measured for the ESP inlet hopper samples should be compared with gas phase sorbent utilization measured at the ESP outlet. When this comparison is made the results generally agree, but with some exceptions. There are at least two reasons for this disagreement. First, the available $\text{Ca}(\text{OH})_2$ in the recycle ash tended to vary significantly from day to day (as much as 7%). It is possible that the percentage of $\text{Ca}(\text{OH})_2$ in the recycle ash varied during the test. Second, as was shown in Section 4.2.1 above, slurry properties can change during a test. Table 4-12

Table 4-10. Summary of Reagent Slurry/Dry Recycle Ash Tests.

Test #	Date Time	Ca/S Ratio Overall	Recycle Ratio	Approach (°F)	Inlet SO ₂ (ppm)	ΔSO ₂ , % ESP Inlet	ESP Outlet
35-DSR-031	3/20/91 1316-1415	1.00	--	49	2000	33	38
35-DSR-032	1600-1700	1.72	0.64	45	2060	36	44
35-DSR-032	1700-1800	1.66	0.61	46	2050	36	44
35-DSR-041	3/21/91 1145-1200	1.02	--	23	2110	46	56
35-DSR-042	1215-1245	1.72	0.65	23	2000	51	63

1. First part of test, slurry only.
2. Second part of test, slurry plus coplanar injection of dry recycle ash.

Table 4-11. Results of Single Pass Reagent Slurry/Recycle Ash Tests.

Test #	---- Ca/S Ratio ----		Approach (°F)	Recycle Ratio	Inlet SO ₂ (ppm)	----- SO ₂ Removal -----	
	Reagent Slurry	Overall				ESP Inlet (%)	ESP Outlet (%)
53-SR-02	0.86	1.59	24	3.3	2000	58	73
53-SR-05	0.69	1.72	26	5.5	1930	55	67
53-SR-01	0.73	1.55	28	3.5	1970	56	70
53-SR-04	0.97	1.66	29	2.0	1900	55	64
53-SR-03	0.62	1.35	33	4.7	2020	50	58
52-SR-01	0.81	1.38	35	3.3	1990	49	56
54-SR-01	1.15	1.44	36	1.0	2000	48	58
54-SR-02	0.85	1.29	37	2.0	2040	46	56
52-SR-02	0.80	1.43	37	3.7	1970	52	62
51-SR-01	0.64	1.03	39	2.2	2010	43	55

Table 4-12. Comparison of Sorbent Utilization from Solids Analyses and from Gas Phase Data for Single Pass Reagent Slurry/Recycle Tests.

Test	----- Ca/S Ratio ----- Reagent Slurry	Overall	Approach (°F)	Recycle Ratio	Utilization at ESP Inlet, % Solids Analysis	Gas Phase*	Utilization at ESP Outlet, % Solids Analysis	Gas Phase*
53-SR-02	0.86	1.59	24	3.3	50.6	36.3±1.6	49.0	46.0±2.1
53-SR-05	0.69	1.72	26	5.5	45.7	31.9±2.7	43.0	39.2±2.1
53-SR-01	0.73	1.55	28	3.5	46.4	36.1±1.9	-	45.1±1.6
53-SR-04	0.97	1.66	29	2.0	35.3	33.1±1.6	-	38.2±1.6
53-SR-03	0.62	1.35	33	4.7	48.5	36.7±1.5	-	43.2±1.7
52-SR-01	0.81	1.38	35	3.3	-	35.5±2.7	-	41.4±2.8
54-SR-01	1.15	1.44	36	1.0	39.2	33.4±1.0	-	40.3±1.2
54-SR-02	0.85	1.29	37	2.0	37.4	35.9±1.6	-	43.3±2.1
52-SR-02	0.80	1.43	37	3.7	46.4	36.2±1.1	-	43.3±1.3
51-SR-01	0.64	1.03	39	2.2	43.6	41.5±3.6	-	53.3±5.4

* Gas phase data were averaged over a time period of approximately one hour and show ± one standard deviation. Solids samples were taken during that period of time.

also shows that there was little change in sorbent utilization (from solids analyses) from the ESP inlet to the ESP outlet which is not reflected in the gas phase data. This disparity may be due to the short duration of these tests (typically four to five hours). The ESP outlet fields are rapped every hour. The combination of an infrequent rapping schedule and overnight operation of the DITF to generate fresh recycle ash may have led to nonrepresentative ash/sorbent residue that remained in the ESP outlet hopper.

To compare sorbent utilization with and without the addition of recycle ash, it is necessary to know how the utilization of $\text{Ca}(\text{OH})_2$ in recycle ash compares to the utilization of $\text{Ca}(\text{OH})_2$ in reagent lime slurry. The available data are shown in Figure 4-21. The utilizations plotted on the vertical axis in this figure are based on ratios of SO_2 removal at the ESP outlet to the total $\text{Ca}(\text{OH})_2$ available to react (the sum of $\text{Ca}(\text{OH})_2$ in reagent lime slurry and $\text{Ca}(\text{OH})_2$ in the recycle ash, if present). The Ca/S ratios on the horizontal axis in the figure are similarly based on the rate of injection of $\text{Ca}(\text{OH})_2$ from reagent lime slurry and the rate of addition of $\text{Ca}(\text{OH})_2$ from recycle ash, if available. There is considerable scatter in these data from any simple algebraic relationship. In principle, part of the scatter might be attributed to variations in the approach temperature (here the range was from 23°F to 40°F), but the points found most distant from the others were not attributable to exceptional approach temperatures. This suggests that at a given value of the Ca/S ratio sorbent utilization is essentially the same, with or without the addition of recycle ash.

An example comparing operation of the DITF with and without recycle is as follows:

Under conditions that typically prevail at the DITF, the injection of a slurry of fresh $\text{Ca}(\text{OH})_2$ at a Ca/S ratio of 1.0, without recycle, will cause an SO_2 removal of 50%, as shown on Figure 4-21. In this instance, the waste sorbent will obviously have a utilization of 50%.

Under the same conditions, except for a recycle ratio of 2.5, the injection of a combination of reagent $\text{Ca}(\text{OH})_2$ and recycled $\text{Ca}(\text{OH})_2$ will produce an overall Ca/S ratio of 1.20, assuming that the utilization of sorbent in each form remains at 50%. However, the removal of SO_2 will increase from 50.0% to 59.9%, and the utilization of sorbent in the discharged waste will also increase to 59.9%. Thus, for a given expenditure of lime, recycle would increase the tonnage of SO_2 removed by the factor of $0.599/0.500$, or about 1.2.

4.2.2.3 Continuous or Multi-Pass Reagent Slurry/Recycle Ash Tests

Two test series were completed in which the DITF was operated in a mode that emulated full-scale operation with continuous recycle ash addition. Test parameters for these two test series were chosen to evaluate conditions under which duct injection could be considered to be competitive at the full scale. Previously, another of DOE's contractors in the area of duct injection technology had identified, on a preliminary basis, conditions under which duct injection could be a competitive SO_2 removal technology at the 50% removal level and at the 90% removal level. At the 50% level of SO_2 removal, an approach of 40°F, reagent Ca/S of 1.0, and recycle ratio of 2.3 was required (a low Ca/S ratio case). At the 90% level of SO_2 removal, an approach of 25°F, reagent Ca/S of 1.8, and recycle ratio of 1.7 were required (a high Ca/S ratio case). These tests were designed to determine if it was possible to operate at these conditions and obtain the necessary levels of SO_2 removal. The economic analyses assumed and the tests were conducted with 2000 ppm of SO_2 at the system inlet.

Figure 4-21. Comparison of sorbent utilization based on gas-phase data from reagent slurry injection tests conducted with and without the addition of recycle ash.

Because the DITF has separate recycle ash and waste ash silos, spent sorbent and ash could be deposited to only one of these silos at a time, and it was not actually possible to continually feed a portion of the recycle ash into the recycle ash silo. Therefore, the amount of recycle ash required for steady state operation was predetermined from mass balance considerations and spent sorbent and ash from the ESP was intermittently fed to the recycle ash silo for a time sufficient to supply the amount needed. Also, in order not to prolong the test, it was desirable to keep the level in the recycle ash silo as low as practically possible. Each test series was continued until the Ca(OH)_2 level in the recycle ash that was mixed with the fresh lime slurry remained constant and equal to the level of Ca(OH)_2 produced in the waste ash.

The low Ca/S test case was performed twice. The first time was during weeks 66 through 68 of testing (October 22 to November 5, 1991). It was decided to use this set of operating conditions again for a long-term ESP test during weeks 81 and 82 of testing (February 3-13, 1992) and during this time the low Ca/S ratio test was repeated. The high Ca/S ratio test case was performed during weeks 68 and 69 of testing (November 7 through 15, 1991).

Table 4-13 presents results for each of these tests. Also in this table are the measured and predicted (based on mass balance considerations) Ca(OH)_2 content in the recycle ash for each test. The predicted value of Ca(OH)_2 content shown in Table 4-13 is the value to which the system would equilibrate if it continued to be operated at the specific overall and reagent Ca/S ratio, approach, and recycle ratio measured during that test. At the beginning of each test series the predicted and measured values of Ca(OH)_2 generally did not agree. This is because the recycle ash stock at the start of each test was left over from previous testing. Generally, a very low level of spent ash and sorbent was kept in the recycle ash silo so that the time to use that ash up (and replace it with more ash from the current test) was kept to a minimum. As the test proceeded the difference between predicted and measured Ca(OH)_2 in the ash tended to decrease.

As Table 4-13 shows, for the low Ca/S ratio case it was possible to obtain better performance than required by the economic analysis. At an approach of 41°F , reagent Ca/S ratio of 1.01, and recycle ratio of 2.07 an SO_2 removal of 55% was measured at the ESP outlet (Test 82-SR-01, February 13). For the high Ca/S ratio case, due to limitations in the amount of ash that could be delivered by the recycle ash weigh belt feeder, it was difficult to maintain a recycle ratio above 1.5. Thus, for this case, at an approach of 24°F , reagent Ca/S ratio of 1.71, and recycle ratio of 1.49 an SO_2 removal of 88% was measured at the ESP outlet. If it had been possible to reach the desired recycle ash ratio, SO_2 removal at the ESP outlet would probably have exceeded 90%.

4.2.2.4 Reagent Slurry and Reagent Slurry/Recycle Ash Tests with CaCl_2 Addition

Two series of tests were performed to evaluate the effect on SO_2 removal of adding CaCl_2 to reagent slurry and reagent slurry/recycle ash mixtures. Various amounts of CaCl_2 were added to the reagent slurry in a holding tank, which was then injected as is or mixed with recycle ash before injection. In this case, the main focus of these tests was to evaluate the effect of added CaCl_2 on SO_2 removal and when recycle ash was mixed with reagent slurry it was used mainly to reach overall Ca/S ratios that

Table 4-13. Summarized Results for Continuous Reagent Slurry/Recycle Ash Tests.

Test #	Date	Approach (°F)	Inlet SO ₂ (ppm)	----- Ca/S Ratio -----		Recycle Ratio	Ca(OH) ₂ in Recycle Ash Measured (%)	Recycle Ash Predicted* (%)	----- ΔSO ₂ -----	
				Overall	Reagent Slurry				ESP Inlet (%)	ESP Outlet (%)
LOW Ca/S										
66-SR-02	10/22/91	37	2030	1.45	0.88	3.57**	22.77	13.7	45	55
66-SR-03	10/23/91	41	2060	1.73	0.94	4.64**	22.77	13.6	46	60
66-SR-04	10/24/91	43	2110	1.46	0.93	3.04**	24.01	15.0	47	56
66-SR-05	10/25/91	45	2080	1.54	1.05	2.12	27.11	18.9	46	56
67-SR-01	10/28/91	39	2040	1.48	1.10	1.92	20.64	18.7	47	60
67-SR-02	10/31/91	44	2060	1.38	1.05	2.05	20.64	20.3	42	53
67-SR-03	11/01/91	43	2020	1.56	1.03	1.83	17.93	19.2	42	54
68-SR-01	11/04/91	44	2090	1.33	1.04	2.09	18.70	20.8	41	51
68-SR-02	11/05/91	29	2000	1.29	1.18	1.88	18.44	-	49	64
81-SR-01	2/3/92	40	2020	1.52	1.06	2.21	31.88	18.4	45	58
82-SR-01	2/4/92	39	2150	1.10	1.05	1.88	19.14	19.3	42	55
	2/10/92	41	2070	1.47	1.10	1.77	16.13	20.9	43	55
	2/11/92	41	2070	1.31	1.00	1.66	16.01	17.1	43	57
	2/12/92	43	2060	1.28	0.97	1.96	16.11	16.5	41	56
Test Case	2/13/92	41	2030	1.31	1.01	2.07	14.75	18.3	42	55
	2/13/92	36	2050	1.34	1.00	1.88	15.29	16.4	44	58
HIGH Ca/S	11/07/91	25	2000	2.15	1.00	2.30	-	20.1	-	50
Test Case	11/07/91	25	2050	2.61	1.88	1.32	23.67	28.0	64	85
68-SR-03	11/07/91	25	2050	2.51	1.98	1.46	23.60	31.8	59	79
69-SR-01	11/12/91	29	2020	2.64	1.97	1.26	22.09	28.4	66	89
69-SR-02	11/14/91	25	2050	2.35	1.71	1.49	23.63	23.6	66	88
69-SR-03	11/15/91	24	2050	2.37	1.80	1.70	-	24.8	-	90

* Ca(OH)₂ content at equilibrium.

** Recycle ash weigh belt feeder malfunctioned and overfed recycle ash.

were otherwise unattainable with straight reagent slurry. Although it was possible to estimate the amount of chlorides in the waste ash from each test the actual amount of chloride was determined by laboratory analysis of ESP hopper samples after each test was completed. Table 4-14 and Figures 4-22 through 4-24 present the results of these tests.

The first series of tests, performed with reagent slurry only, was carried out during weeks 76 and 77 of testing (December 30, 1991 to January 7, 1992). These tests were performed at a nominal Ca/S ratio of 2.0 and an approach to saturation of 35°F. During this series, six tests were conducted, in which up to 2.2% chloride was present in the ESP hopper ash. As Table 4-14 and Figure 4-22 show, at a 35°F approach, sorbent utilization did increase with chloride addition (an increase of 6% at the ESP outlet at 2.2% chloride), but the gain was not probably not significant enough to justify the cost of the additive.

The second series of tests was performed during weeks 83 and 84 of testing. These tests were performed at a variety of Ca/S ratios, approach temperatures, and inlet SO₂ levels. The results of these tests are shown in Table 4-14 and in Figures 4-23 and 4-24. Figure 4-23 shows the gas phase utilization data taken in this series of tests in the range of approach temperatures from 20 to 30°F plotted against a curve fit to previous data taken with reagent slurry injection (without chloride addition) at an inlet SO₂ level of 2000 ppm for the same range of approach temperatures. These data show approximately the same increase in utilization at the ESP exit as was seen in Figure 4-22. Figure 4-24 shows less of an increase in utilization.

These tests suggest that either higher levels of chloride addition or much lower approach temperatures are required to significantly increase sorbent utilization. Unfortunately, it was not possible to explore this effect any further, as testing at the DITF ended on February 27, 1992.

4.2.5 ESP Performance

ESP performance was monitored throughout each test conducted at the DITF, and during selected test series more complete evaluations of ESP performance were carried out. During these test series every effort was made to maintain the test condition for 24 hours a day so that ESP electrical operation and emissions would equilibrate at the particular test condition. When 24 hour-a-day operation was not possible, the ESP was allowed to stabilize for several hours at or near the desired test condition before electrical readings or emissions data were taken.

ESP performance was evaluated during three distinct periods of testing. The first test series was conducted during weeks 33 and 34 of testing (March 5-14, 1991). During this period SO₂ removal tests were conducted at nominal Ca/S ratios of 1.0 (25°F approach) and 2.0 (25 and 45°F approach) with reagent slaked lime slurry injection to investigate the effect of reduced specific collecting area (SCA) on ESP performance (by deenergizing the inlet and second field of the ESP). The second test series was conducted during week 48 of testing (June 18-21, 1991). During this period SO₂ removal tests were conducted with coplanar reagent dry sorbent injection, and ESP performance was evaluated at a nominal Ca/S ratio of 2.0 with approach temperatures of 35° and 45°F. The third test series was conducted during weeks 81 and 82 of operation (February 3-14, 1992). During this period SO₂ removal tests were conducted with a reagent slaked lime slurry/recycle ash mixture and ESP performance was evaluated at a nominal reagent Ca/S ratio of 1.0 (overall Ca/S ratio of 1.4) and nominal approach temperature of 40°F. This was the low Ca/S ratio equilibrium recycle test condition discussed above.

Table 4-14. Summary of Results for Tests with Ca(Cl)₂ Addition.

Test #	Ca/S Ratio		Approach (°F)	Inlet SO ₂ (ppm)	%Chloride in Spent Solids	Recycle Ratio	ESP Inlet		ESP Outlet	
	Overall	Reagent					ΔSO ₂ , %	Utilization, %	ΔSO ₂ , %	Utilization, %
76-SL-01	2.13	2.13	39	2070	<0.35*	0.0	48	23	64	30
76-SL-02	2.28	2.28	35	2080	0.26	0.0	52	23	69	30
76-SL-03	2.38	2.38	37	2040	0.50	0.0	52	22	68	29
76-SL-04	1.97	1.97	35	2060	0.97	0.0	50	25	64	33
77-SL-01	1.97	1.97	34	2080	1.8	0.0	50	26	66	34
77-SL-02	2.20	2.20	35	2040	2.3	0.0	56	26	76	35
83-SR-01	1.20	0.98	25	2080	1.1	1.38	51	43	62	52
83-SR-02	1.08	0.29	35	2750	3.0	3.50	28	26	36	34
83-SR-03	1.26	1.07	27	2070	2.6	1.08	55	44	69	55
84-SR-01	1.49	0.92	25	1190	2.6	2.87	66	44	83	56
84-SR-02	2.38	1.82	35	1140	3.6	1.25	66	28	80	33
84-SL-03	1.68	1.68	37	2050	3.4	0.0	50	30	64	38

* Without Ca(Cl)₂ addition soluble chloride levels in ESP inlet hopper ash ranged from 0.14 to 0.35% on 11/14/91.

Ca/S Ratio	2.13	2.28	2.38	1.97	1.97	2.19
Approach, °F	39	35	37	35	34	35

Figure 4-22. Percent of SO_2 removed at the ESP inlet and outlet for chloride levels of up to 2.2% in spent solids. A nominal Ca/S ratio of 2.0 and approach to saturation of 35°F was maintained for these tests.

Figure 4-23. Percent of sorbent utilized at the ESP inlet and outlet for SO₂ model tests conducted with CaCl₂ addition. Summary of test data for approach temperatures from 20 to 30°F.

Figure 4-24. Percent of sorbent utilized at the ESP inlet and outlet for SO₂ model tests conducted with CaCl₂ addition. Summary of test data for approach temperatures from 30 to 40°F.

ESP performance was briefly evaluated during one other test series. During the high Ca/S ratio equilibrium recycle test (weeks 68 and 69 of testing, November 4-15, 1991) ESP performance became severely degraded with average outlet opacity reaching nearly 80% (referenced to a 25 ft stack). No extensive evaluation of the ESP was planned or performed but ESP performance was documented. This behavior was of particular interest, because while ESP outlet emissions were quite high, ESP electrical operation was normal.

4.2.5.1 ESP Performance at Reduced SCA

During this period of testing the inlet field of the ESP was deenergized (to reach a nominal SCA of 290 ft²/acfm), and at the end of the test the second field of the ESP was deenergized (to reach a nominal SCA of 200 ft²/acfm). Table 4-15 summarizes ESP performance during this test, and Table 4-16 shows the average ESP electrical operating conditions measured at the conclusion of each day of testing. Figures 4-25 through 28 show typical voltage-current curves for the ESP measured during these tests and Figure 4-29 presents the results of a laboratory measurement of the resistivity (ascending and descending temperature method) of a composite ash sample from the ESP inlet, middle, and outlet hoppers obtained during test 34-SL-02 (March 12, 1991).

The mass emission data in Table 4-15 were calculated on a lb/10⁶ Btu basis using the following procedure: 1) the inlet mass concentration of fly ash to the ESP was increased by an amount equal to the dilution of fly ash concentration resulting from the effect of the dilution air injection system. 2) the efficiency of the ESP was used with the adjusted inlet loading to calculate an outlet mass concentration for each condition shown in Table 4-15, and 3) the resulting outlet mass concentrations were converted to lb/10⁶ Btu as if they were measured on a boiler with a flue gas oxygen content of 5.6%. This procedure is necessary because of the excess oxygen introduced by the DITF dilution air injection system. A precipitation rate parameter, ω_p , is shown in Table 4-15 to indicate relative performance. As a point of reference, ω_k values of from 27 to 62 cm/s have been reported for full-scale ESPs collecting ash downstream of spray dryers.³

In only two cases did the overall mass collection efficiency fall below 99%. In both cases (Tests 33-SL-02 and 33-SL-04), testing was terminated because of solids deposits that had accumulated in the horizontal test duct. Because outlet mass emissions measurements require a period of two hours and because operators at the DITF regularly used a small "poke hole" in the horizontal test duct to break up the solids deposits as they formed (to prolong the test so that the outlet emissions measurements could be completed) it is possible that ESP performance was compromised during these two tests. However, as Tables 4-15 and 4-16 and Figures 4-25 through 4-28 show, at lower approach temperatures and at lower values of SCA the ESP appeared to perform well enough to maintain collection efficiency above 99% with the exception of the two previously cited cases. Certainly, the behavior that was observed during the E-SO_x tests at the Burger Station³ was not duplicated. It should be pointed out, however, that the efficiencies reported in Table 4-15 may not be sufficient to avoid violations of mass emission or opacity regulations for some locations.

The laboratory resistivity curve shown in Figure 4-29 is provided to illustrate the rapid manner in which resistivity increases as the temperature of the ash/sorbent mixture increases (in the range of approach temperatures used for these tests) and to provide an example to compare with other laboratory resistivity curves in this report.

Table 4-15. Summary of ESP Behavior During Tests Conducted at the DITF During March, 1991.

Test #	Date	Ca/S Ratio, Approach (°F), Inlet SO ₂ (ppm)	Mass Emissions			Mass Efficiency (%)	ω _k (cm-sec)	SCA (ft ² /kacfm)	Inlet Flow Rate (dscfm)
			Inlet (gr/dscf)	Outlet (gr/dscf)	Outlet (lb/10 ⁶ Btu) ¹				
33-SL-02	3/5/91	2.25, 45, 1260	5.27	0.0640	0.123	98.79	35	285	33380
33-SL-03	3/6/91	2.01, 27, 1350	4.08	0.0096	0.018	99.76	61	304	31100
33-SL-05	3/8/91	2.14, 19, 1840	8.30 ²	0.0293	0.056	99.65 ²	56	290	33740 ³
34-SL-01	3/11/91	2.00, 26, 2020	8.55 ²	0.0618	0.118	99.28	43	286	33150 ³
34-SL-02	3/12/91	2.10, 25, 2010	11.88	0.0576	0.110	99.52	46	317	30640
34-SL-03	3/13/91	1.82, 43, 1970	10.90	0.0925	0.177	99.15	56	208	29860
34-SL-04	3/14/91	1.02, 25, 1990	5.01 ²	0.1000	0.192	98.00	39	199	32060

1. See Text
2. Estimated from previous data.
3. Measured at outlet.

Table 4-16. Summary of ESP Electrical Behavior During Tests Conducted at the DITF During March, 1991.

Test #	Date	Ca/S Ratio, Approach (°F), Inlet SO ₂ (ppm)	INLET FIELD		SECOND FIELD		THIRD FIELD		OUTLET FIELD	
			Voltage (kV)	Current Density (nA/cm ²)	Voltage (kV)	Current Density (nA/cm ²)	Voltage (kV)	Current Density (nA/cm ²)	Voltage (kV)	Current Density (nA/cm ²)
33-SL-02	3/5/91	2.25, 45, 1260	.	.	36.7	56	36.2	78	34.6	81
33-SL-03	3/6/91	2.01, 27, 1350	.	.	45.4	53	43.7	85	40.1	84
33-SL-05	3/8/91	2.14, 19, 1840	.	.	46.5	49	45.6	82	44.5	87
34-SL-01	3/11/91	2.00, 26, 2020	.	.	47.2	45	43.9	85	41.3	85
34-SL-02	3/12/91	2.10, 25, 2010	.	.	47.3	44	46.4	82	44.8	89
34-SL-03	3/13/91	1.82, 43, 1970	.	.	.	.	48.2	60	46.3	82
34-SL-04	3/14/91	1.02, 25, 1990	.	.	.	.	51.7	72	45.2	87

. Transformer-Rectifier set off

TEST 33-SL-03, 3/6/91

Figure 4-25. Current density as a function of applied ESP voltage for Test 33-SL-03, March 6, 1991. The first field of the ESP was deenergized.

TEST 33-SL-05, 3/8/91

Figure 4-26. Current density as a function of applied ESP voltage for Test 33-SL-05, March 8, 1991. The first field of the ESP was deenergized.

TEST 34-SL-03, 3/13/91

Figure 4-27. Current density as a function of applied ESP voltage for Test 34-SL-03, March 13, 1991. The first two fields of the ESP were deenergized.

TEST 34-SL-04, 3/14/91

Figure 4-28. Current density as a function of applied ESP voltage for Test 34-SL-04, March 14, 1991. The first two fields of the ESP were deenergized.

Figure 4-29. Resistivity measured in the laboratory as a function of temperature for a composited sample of ESP hopper ash from Test 34-SL-02. Data taken at 10.6% H₂O using both ascending and descending temperature.

4.2.5.2 ESP Performance During Coplanar Reagent Dry Sorbent Injection

During week 48 of testing at the DITF, SO₂ removal tests were conducted with coplanar injection of dry reagent sorbent. The DITF was operated for 24 hours a day at a nominal Ca/S ratio of 2.0 and approach temperatures of 45°F (June 18 and 19) and 35°F (June 20 and 21). During this time testing was interrupted only once, during the night of June 19, to repair a hole in the horizontal test section duct caused by ash entrained in an air jet from a misaligned soot blower tube located near one of the duct hoppers. Mass concentration measurements were performed at the ESP inlet on June 18-20 and at the ESP outlet on June 19 and 20. In situ particle size distribution measurements (with modified Brink cascade impactors) were conducted at the ESP inlet on June 18-20, and at the ESP outlet on June 19 and 20.

Table 4-17 summarizes ESP performance during this test and Table 4-18 shows the average ESP electrical operating conditions measured at the conclusion of testing on June 19 and 20. The mass emission data in Table 4-17 were calculated on a lb/10⁶ Btu basis using the method described above to correct for the effect of the air dilution system at the DITF. Figures 4-30 through 32 show averaged in situ particle size distribution data measured at the ESP inlet on June 18 and 19. These data were used as part of the input data for ESP model simulations. Figures 4-33 through 36 show typical voltage-current curves for the ESP measured at the end of each day of testing and Figure 4-37 presents the results of a laboratory measurement of the resistivity (ascending and descending temperature method) of a composite ash sample from the ESP inlet, middle, and outlet hoppers obtained during test 48-DS-02 (June 19). In situ resistivity measurements were also performed at the ESP inlet for both approach temperatures. Table 4-19 presents the results of these measurements. Finally, Table 4-20 presents the results of ESP model calculations with input data representative of this test using the standard SRI/EPA model,⁴ a version of this model that has been modified to take into account the effect of space charge,⁵ and the ADA ESP Model.⁶

As Table 4-18 (Test Nos. 48-DS-01 and 48-DS-02) and the voltage-current curves for the ESP taken on June 18 and 19 show, ESP electrical performance at a 45°F approach deteriorated from one day to the next. After about eight hours of operation at a 45°F approach the baseline opacity level became uneven, and by the morning of June 19 the opacity due to rapping puffs had increased by approximately a factor of four. By this time rapping puffs from other sections of the ESP were easily detected. However, the overall opacity was still low. Unfortunately, only after this test was completed was it determined that the opacity monitor required optical realignment, and the values that were recorded during these tests were suitable only for making relative comparisons. The fact that ESP operation deteriorated significantly over a period of two days suggests that some cumulative process was occurring. It is possible that sorbent built up on the inlet field corona wires during the test. If this was so, it apparently dropped off when the DITF was brought down to repair the hole on the horizontal test duct on the night of June 19, because when testing was resumed at a 35°F approach, ESP performance had improved.

On June 20 when the approach temperature was 35°F, ESP electrical performance and emissions were markedly improved, and relative opacity decreased by a factor of two. It is possible that this improvement was due to the lowering of the approach temperature (and subsequent lowering of the resistivity of the ash/sorbent aerosol), but as Table 4-18 shows, ESP electrical performance in fields 3 and 4 deteriorated slightly from June 20 to 21.

Table 4-17. Summary of ESP Behavior During Tests Conducted at the DITF During June, 1991.

Test #	Date	Ca/S Ratio, Approach (°F), Inlet SO ₂ (ppm)	Mass Emissions			Mass Efficiency (%)	ω _k (cm-sec)	SCA (ft ² /kacfm)	Inlet Flow Rate (dscfm)
			Inlet (gr/dscf)	Outlet (gr/dscf)	Outlet (lb/10 ⁶ Btu) ¹				
48-DS-02	6/1991	2.06, 45, 1980	11.78	0.0454	0.087	99.61	45	345	36163
48-DS-03	6/20/91	2.02, 37, 2000	11.69	0.0066	0.013	99.94	83	336	36750

1. See Text

Table 4-18. Summary of ESP Electrical Behavior During Tests Conducted at the DITF During June, 1991.

Test #	Date	Ca/S Ratio, Approach (°F), Inlet SO ₂ (ppm)	INLET FIELD		SECOND FIELD		THIRD FIELD		OUTLET FIELD	
			Voltage (kV)	Current Density (nA/cm ²)	Voltage (kV)	Current Density (nA/cm ²)	Voltage (kV)	Current Density (nA/cm ²)	Voltage (kV)	Current Density (nA/cm ²)
48-DS-01	6/18/91	2.03, 44, 2010	57.8	2 ¹	57.5	171	49.9	74	49.1	82
48-DS-02	6/1991	2.06, 45, 1980	60.0	<1 ¹	52.4	331	45.1	39	42.3	53
48-DS-03	6/20/91	2.02, 37, 2000	69.8	9	58.1	27	54.7	50	53.5	62
48-DS-04	6/21/91	2.04, 35, 2010	70.8	7	61.6	17	51.7	42	45.2	55

1. Spark limited operation.

90% CONFIDENCE LIMITS

DITF DRY SORBENT INJECTION TEST

RHO = 2.31 GM/CC MASS < 0.51 MICRONS INCLUDED IN FIT

Figure 4-30. Particle size distribution measured at the ESP inlet. Average of measurements made on June 18-19, 1991. Cumulative percent basis.

Figure 4-31. Particle size distribution measured at the ESP inlet.
Average of measurements made on June 18-19, 1991.
Cumulative mass basis.

90 % CONFIDENCE LIMITS

DITF DRY SORBENT INJECTION TEST

RHO = 2.31 GM/CC MASS < 0.51 MICRONS INCLUDED IN FIT

Figure 4-32. Particle size distribution measured at the ESP inlet. Average of measurements made on June 18-19, 1991. Differential mass basis.

TEST 48-DS-01, 6/18/91

Figure 4-33. Current density as a function of applied ESP voltage at a 45°F approach to saturation. Test 48-DS-01, June 18, 1991.

TEST 48-DS-02, 6/19/91

Figure 4-34. Current density as a function of applied ESP voltage at a 45° F approach to saturation. Test 48-DS-02, June 19, 1991.

Figure 4-35. Current density as a function of applied ESP voltage at a 35°F approach to saturation. Test 48-DS-03, June 20, 1991.

TEST 48-DS-04, 6/21/91

Figure 4-36. Current density as a function of applied ESP voltage at a 35°F approach to saturation. Test 48-DS-04, June 21, 1991.

Figure 4-37. Resistivity measured in the laboratory as a function of temperature for a composited sample of ESP hopper ash from Test 48-DS-02. Data taken at 12.3% H₂O using both ascending and descending temperature.

Table 4-19. In situ Resistivity Measured at the ESP Inlet During Coplanar Dry Sorbent Injection Tests at a 35 and 45°F Approach, June 18-21, 1991.

	----- In Situ Resistivity, Ohm-Cm -----	
	45°F Approach	35°F Approach
Without Compressing Ash Layer	2.37×10^{11}	8.68×10^{10}
	2.13×10^{11}	1.47×10^{11}
	2.03×10^{11}	1.47×10^{11}
	9.63×10^{10}	1.93×10^{11}
	3.23×10^{11}	8.98×10^{11}
	1.86×10^{11}	1.01×10^{11}
	3.39×10^{11}	1.35×10^{11}
	2.31×10^{11}	
	3.15×10^{11}	
Average	2.38×10^{11}	1.35×10^{11}
With Ash Layer Compressed	2.94×10^{10}	1.41×10^{10}
	3.04×10^{10}	1.29×10^{10}
	4.15×10^{10}	9.86×10^9
Average	3.38×10^{10}	1.23×10^{10}

Table 4-20. ESP Model Results for Tests Conducted in June, 1991

Date	Test Condition	Approach °F	Measured Efficiency, %	Standard SRI Model ¹ Sneakage, σ_g	Efficiency, %	SRI Space Charge Model ¹ Sneakage, σ_g	Efficiency, %	Reentrainment, Sneakage, σ_g	ADA Model Efficiency, %
6-19-91	Dry Sorbent	45	99.61	0.20, 0.25	99.67	0.15, 0.25	99.71	0.70, 0.10, 0.25 0.50, 0.15, 0.25	99.52 99.58
6-20-91	Dry Sorbent	35	99.94	0.10, 0.25	99.96	0.10, 0.25	99.90	0.00, 0.10, 0.25	99.90

1. The SRI sneakage coefficient is defined in the model manuals as a combined factor for gas sneakage and non-rapping reentrainment. σ_g is the normalized standard deviation of the gas velocity distribution.

While the ascending temperature laboratory resistivity measurements shown in Figure 4-37 suggest that lowering the ESP inlet temperature would reduce the ash resistivity by a factor of slightly greater than three (from 8.8×10^{10} to 2.7×10^{10} ohm-cm), this is probably not enough to effect the change in ESP performance that was observed. What is interesting is that the in situ resistivity measurements made at the two approach temperatures also show a decrease in ash resistivity when the approach temperature was reduced by 10° F and that the resistivity measured with the ash layer compressed was close to that measured in the laboratory.

With respect to ESP model calculations, the in situ particle size distribution measured on June 18-19 was used along with ESP operating voltage-current characteristics as input to the standard SRI/EPA ESP model, a version of that model modified to account for the effect of space charge, and the ADA ESP model. The results of these calculations are shown in Table 4-20. For all three models, more non-ideal corrections (reentrainment/sneakage) were required to force a match of measured and computed performance for a 35° F approach than at a 45° F approach. This indicates a performance degradation process was occurring which is not adequately simulated by existing model algorithms.

4.2.5.3 ESP Performance During Long-Term Low Ca/S Equilibrium Recycle Tests

During weeks 81 and 82 of testing the DITF a long-term test was planned. The test condition was chosen to emulate a "real-world" application of duct-injection technology. It was decided to operate the DITF 24 hours a day, use reagent slaked lime slurry with continuous recycling of spent sorbent, and to operate at the low Ca/S ratio condition that had been tested once before during weeks 66 through 68 of testing. For these tests the DITF was operated at a reagent Ca/S ratio of 1.0 (overall Ca/S ratio of 1.4), a nominal approach temperature of 40° F, and an inlet SO₂ level of 2000 ppm. Under these conditions, SO₂ removal at the ESP outlet averaged from 50 to 60%.

Unfortunately, because of a series of boiler tube leaks at the Unit 5 host boiler, this test was limited to a total of seven days of mainly non-consecutive testing. Thus, the goal of a long-term ESP test was not realized. However, during the last two days of testing (February 12 and 13, 1992) it was possible to operate for two extended periods (one period of 14 hours followed by a period of 28 hours). During this whole test, and particularly during the last two periods of testing, the ESP exhibited no unusual electrical behavior, but ESP emissions were observed to depend on the ESP outlet temperature. Whenever slurry injection was started, the opacity at the ESP outlet dropped at roughly the same rate as did the temperature at the exit of the ESP. At the conclusion of testing the approach temperature was reduced by 5° F (to 35° F) and testing was continued long enough to make mass emissions measurements at the ESP inlet and outlet.

During the two extended periods of testing, and during other somewhat shorter periods of testing on February 10 and 11, mass concentration measurements were made at the ESP inlet and ESP outlet, in situ particle size distribution measurements were conducted at the ESP inlet (with modified Brink cascade impactors), in situ particle size distribution measurements were conducted at the ESP outlet (with University of Washington Mark V cascade impactors), and in situ measurements of the electrical resistivity of the ash/sorbent aerosol were performed.

Because of the time required at the ESP outlet to complete a single run with a mass train or cascade impactor, both types of measurements could not be performed on the same day. Thus, mass train runs were performed at the ESP inlet and outlet on February 11 and 13 while cascade impactor

measurements were performed at the ESP inlet and outlet on February 10 and 12. ESP voltage-current characteristics were measured on February 11 and 12.

Table 4-21 summarizes ESP performance during this test and Table 4-22 shows the hourly averages of ESP electrical operating conditions and opacity at the ESP outlet taken from the DAS for the two extended periods of operation on February 12 and 13. The opacity averages shown in Table 4-22 are plotted in Figure 4-38. The mass emission data in Table 4-21 were calculated on a lb/10⁶ Btu basis using the method used in Table 4-15 to correct for the effect of the air dilution system at the DITF.

In situ particle size distribution data are shown in Figures 4-39 through 4-46: Figures 4-39 through 4-42 show in situ particle size distribution data measured at the ESP inlet and outlet on February 10 and Figures 4-43 through 4-46 show in situ particle size distribution data measured at the ESP inlet and outlet on February 12. Figures 4-47 and 4-48 show fractional efficiency-penetration curves for the ESP on February 10 and 12 calculated from the dm/dlogD data obtained at the ESP inlet and outlet for each day.

Figures 4-49 and 50 show typical voltage-current curves for the ESP measured on February 11 and 12 and Figure 4-51 presents the results of a laboratory measurement of the resistivity (ascending and descending temperature method) of a composite ash sample from the ESP inlet, middle, and outlet hoppers obtained during test 68-SR-02 (November 5, 1991).

During this test the DITF was operated at the same conditions as for the long-term ESP test. Thus, the sorbent/ash aerosol produced during the November 5 test should have the same electrical characteristics as that generated during the long-term ESP test. In situ resistivity measurements were also performed at the ESP inlet during each day of testing. Table 4-23 presents the results of these measurements for February 11 and 13. Note that higher values of resistivity are obtained when the probe shield opening is turned about 45° F away from the direction of gas flow. This procedure tends to exclude larger particles, which may have higher residual moisture content and thus lower resistivity values. Finally, Table 4-24 presents the results of ESP model calculations with input data representative of this test using the standard SRI/EPA model, a version of this model that has been modified to take into account the effect of space charge, and the ADA Model.

As Tables 4-21 and 4-22 and Figure 4-38 show, ESP emissions tended to decrease with time. Shortly after testing commenced on February 11, while the ESP outlet temperature was still equilibrating, ESP collection efficiency was measured to be 99.23%. Four hours later the collection efficiency had increased to 99.77%. Likewise, on February 13, after the ESP had been on line for approximately 18 hours, the ESP collection efficiency averaged 99.79%. Table 4-22 and Figures 4-49 and 4-50 show that the ESP electrical voltage-current characteristics were near optimum.

Shortly after the approach temperature was lowered by 5°F on February 13, the average ESP collection efficiency increased to 99.94%. The lowering of the approach temperature appeared to have a beneficial effect on ESP emissions. When the approach temperature was lowered, the opacity due to rapping puffs from the last field of the ESP dropped from approximately 20% to 1% or less. This effect may have been transient, but because the test could not be extended it was not possible to determine if this was the case or not. As Figure 4-51 shows, the ash resistivity was already low and additional lowering gained from a 5°F reduction in the approach temperature would not be expected to have a beneficial effect on collection efficiency. These values are much lower than the in-situ data. Such disagreement between laboratory and in-situ data have been observed previously.³

Table 4-21. Summary of ESP Behavior During Tests Conducted at the DITF During Test 82-SR-01, February, 1992.

Date	Time	Ca/S Ratio, Approach (°F), Inlet SO ₂ (ppm)	Mass Emissions		Mass Efficiency (%)	ω _k (cm-sec)	SCA (ft ² /kacfm)	Inlet Flow Rate (dscfm)
			Inlet (gr/dscf)	Outlet (gr/dscf)				
2/10/92 ²	Averaged	1.4, 40, 2000	11.58	0.0726	0.139	99.37	-	-
2/11/92 ³	1136-1241	1.32, 41, 2050	13.68	0.1050	0.201	99.23	392	30974
	1340-1444	1.33, 43, 2050	18.64	0.0618	0.119	99.67	390	31008
	1528-1633	1.40, 40, 2070	13.72	0.0316	0.061	99.77	398	30970
2/12/92 ²	Averaged	1.4, 40, 2000	13.27	0.0745	0.143	99.44	-	-
2/13/92 ³	0901-1008	1.30, 40, 2070	14.51	0.0268	0.051	99.82	390	30723
	1124-1236	1.34, 42, 2070	13.23	0.0313	0.060	99.76	388	30846
	1410-1518	1.41, 36, 2030	12.61	0.0102	0.012	99.92	391	30693
	1650-1718	1.35, 34, 2060	12.65	0.0079	0.015	99.94	393	30537

1. See Text.

2. Daily average of impactor data.

3. Mass Train Data.

Table 4-22. ESP Operating Parameters, Long-Term ESP Test, 2/11/92 - 2/13/92*

DATE	TIME	INLET FIELD		SECOND FIELD		THIRD FIELD		OUTLET FIELD		OPACITY
		Voltage	Current Density	Voltage	Current Density	Voltage	Current Density	Voltage	Current Density	
		kV	nA/cm ²	kV	nA/cm ²	kV	nA/cm ²	kV	nA/cm ²	
2-11	0934	40.5	34	38.2	56	40.3	81	40.3	86	78.1
	1000	45.9	37	42.1	60	43.6	83	42.5	87	71.5
	1100	46.6	37	45.1	60	46.5	77	45.3	81	7.6
	1200	46.9	37	45.2	55	47.6	71	46.7	75	1.9
	1300	45.5	36	44.7	56	47.0	72	46.7	75	2.7
	1400	46.4	37	45.3	55	47.7	70	47.6	72	0.1
	1500	47.1	37	48.9	53	48.5	67	48.3	69	5.0
	1600	49.0	37	46.5	50	49.3	64	48.9	67	0.1
	1712	48.9	37	46.8	51	49.5	63	49.1	65	0.1
	1800	49.1	37	47.1	53	49.2	65	48.8	66	3.2
	1900	50.3	38	47.7	52	49.5	63	48.9	66	0.1
	2000	49.5	38	47.5	52	49.2	64	48.6	67	1.2
	2100	48.2	37	46.6	53	47.9	69	47.6	71	0.4
	2200	49.2	37	46.7	52	48.2	69	47.7	72	1.3
	2300	49.3	37	46.7	52	48.4	68	47.8	69	0.1
2-12	1300	42.7	34	39.0	57	40.3	82	39.7	85	98.7
	1400	48.0	36	44.6	59	45.3	80	44.2	83	64.2
	1500	47.7	36	45.4	57	46.3	78	45.5	78	14.4
	1600	47.2	36	44.9	60	45.3	80	44.9	80	10.1
	1700	49.0	35	46.7	55	46.7	74	46.2	76	2.2
	1800	50.4	37	48.3	51	48.3	67	47.5	69	1.3
	1900	48.5	36	46.9	55	46.9	71	45.9	70	5.8
	2000	47.8	35	45.2	58	45.6	75	45.3	74	9.4
	2100	48.4	37	46.0	57	45.9	74	46.0	75	3.3
	2200	49.2	37	46.2	57	46.0	73	45.9	75	2.3
2-13	2300	48.5	36	45.4	60	45.2	76	45.3	78	4.0
	0000	49.7	37	46.2	56	46.1	74	45.9	76	2.6
	0100	49.3	37	46.3	56	46.2	73	46.3	75	1.2
	0200	48.4	35	44.8	59	44.8	77	45.1	79	5.3
	0300	49.5	37	46.5	54	46.7	72	46.4	75	0.7
	0400	50.1	38	47.2	53	47.4	69	47.0	72	0.6
	0500	50.4	38	47.2	53	47.3	70	47.0	72	0.6
	0600	50.1	38	47.2	56	47.6	69	47.2	71	2.5
	0700	50.8	38	47.6	53	48.0	68	47.6	70	0.1
	0800	52.1	38	48.5	50	48.7	64	48.4	66	0.1
	0900	52.0	38	48.5	50	48.2	65	48.2	66	0.1
	1000	51.9	38	48.1	52	47.5	68	47.4	69	2.8
	1100	52.0	38	47.9	53	46.9	70	47.0	72	0.1
	1200	52.2	38	47.7	51	47.0	70	46.9	72	1.1
	1300	52.6	38	47.7	46	47.6	69	47.5	71	1.1
	1400	53.7	40	48.3	42	49.4	63	48.7	66	1.2
	1500	54.2	40	48.5	42	50.0	61	49.2	64	0.2
	1600	54.5	40	48.3	42	50.4	59	49.6	64	0.1
	1700	54.9	41	48.4	42	50.2	60	49.5	63	0.1

* Hourly averages from DITF Data Acquisition System

Figure 4-38. Averaged hourly opacity for March 11-13, 1992 during week 82 of testing.

Figure 4-39. Particle size distribution measured at the ESP inlet. Average of measurements made on February 10, 1992 during slurry/recycle ash testing. Cumulative mass basis.

90 % CONFIDENCE LIMITS

BEVERLY LONG-TERM ESP TEST 2/10/92

RHO = 2.30 GM/CC MASS < 0.41 MICRONS INCLUDED IN FIT

Figure 4-40. Particle size distribution measured at the ESP inlet. Average of measurements made on February 10, 1992 during slurry/recycle ash testing. Differential mass basis.

Figure 4-41. Particle size distribution measured at the ESP outlet. Average of measurements made on February 10, 1992 during slurry/recycle ash testing. Cumulative mass basis.

90 % CONFIDENCE LIMITS

BEVERLY LONG-TERM ESP TEST 2/10/92

RHO = 2.50 GM/CC MASS < 0.09 MICRONS INCLUDED IN FIT

Figure 4-42. Particle size distribution measured at the ESP outlet. Average of measurements made on February 10, 1992 during slurry/recycle ash testing. Differential mass basis.

Figure 4-43. Particle size distribution measured at the ESP inlet. Average of measurements made on February 12, 1992 during slurry/recycle ash testing. Cumulative mass basis.

90 % CONFIDENCE LIMITS

BEVERLY LONG-TERM ESP TEST 2/12/92

RHO = 2.50 GM/CC MASS < 0.44 MICRONS INCLUDED IN FIT

Figure 4-44. Particle size distribution measured at the ESP inlet. Average of measurements made on February 12, 1992 during slurry/recycle ash testing. Differential mass basis.

Figure 4-45. Particle size distribution measured at the ESP outlet. Average of measurements made on February 12, 1992 during slurry/recycle ash testing. Cumulative mass basis.

90 % CONFIDENCE LIMITS

BEVERLY LONG-TERM ESP TEST 2/12/92

RHO = 2.50 GM/CC MASS < 0.09 MICRONS INCLUDED IN FIT

Figure 4-46. Particle size distribution measured at the ESP outlet. Average of measurements made on February 12, 1992 during slurry/recycle ash testing. Differential mass basis.

PENETRATION-EFFICIENCY 90 % CONFIDENCE LIMITS

BEVERLY LONG-TERM ESP TEST 2/10/92

$\rho_{\text{HO}} = 2.50 \text{ GM/CC}$

Figure 4-47. Calculated ESP penetration-efficiency from inlet and outlet in-situ impactor measurements made on February 10, 1992 during slurry/recycle ash testing.

PENETRATION-EFFICIENCY 90 % CONFIDENCE LIMITS

BEVERLY LONG-TERM ESP TEST 2/12/92

$\rho_{\text{HO}} = 2.50 \text{ GM/CC}$

Figure 4-48. Calculated ESP penetration-efficiency from inlet and outlet in-situ impactor measurements made on February 12, 1992 during slurry/recycle ash testing.

Figure 4-49. Current density as a function of applied ESP voltage at a 40°F approach to saturation during slurry/recycle ash testing. Test 82-SR-01, February 11, 1992.

TEST 82-SR-01, 2/12/92

Figure 4-50. Current density as a function of applied ESP voltage at a 40°F approach to saturation during slurry/recycle ash testing. Test 82-SR-01, February 12, 1992.

Figure 4-51. Resistivity measured in the laboratory as a function of temperature for a composited sample of ESP hopper ash from Test 68-SR-02 on November 5, 1991. Data taken at 12.3% H₂O using both ascending and descending temperature.

Table 4-23. In situ Resistivity Measured at the ESP Inlet During Slurry/Recycle Tests at a 40 and 35°F Approach, June 18-21, 1991.

Date/Time	Approach (°F)	----- In Situ Resistivity, Ohm-Cm -----	
		45° to Flow	Parallel to Flow
2/11/92			
1200-1220	39		5.50×10^{10}
1255-1355	42	1.11×10^{11}	
1420-1440	42		4.06×10^{10}
1530-1610	40	3.07×10^{11}	
Average	41	2.09×10^{11}	4.78×10^{11}
2/13/92			
0910-0945	42	6.57×10^{11}	
1025-1055	42		5.78×10^{10}
1140-1220	44	3.37×10^{11}	
1300-1330	42		5.53×10^{10}
NA	42		4.35×10^{10}
Average	42	4.97×10^{11}	5.22×10^{10}
1420-1500	37		2.79×10^{10}
NA	36		1.39×10^{10}
1545-1615	36		8.82×10^9
Average	36		1.69×10^{10}

Table 4-24. ESP Model Results for Tests conducted in February, 1992.

Date	Approach °F	Measured Efficiency, %	Standard SRI Model ¹		SRI Space Charge Model ¹		ADA Model	
			Sneakage, σ_g	Efficiency, %	Sneakage, σ_g	Efficiency, %	Reentrainment, Sneakage, σ_g	Efficiency, %
2-13-92	35	99.92	0.20, 0.25	99.94	0.10, 0.25	99.91	0.00, 0.10, 0.25	99.91
2-13-92	40	99.78	0.30, 0.25	99.79	0.15, 0.25	99.75	0.60, 0.10, 0.25 0.20, 0.15, 0.25	99.84 99.74

1. The SRI sneakage coefficient is defined in the model manuals as a combined factor for gas sneakage and non-rapping reentrainment.

The penetration-efficiency curves shown in Figures 4-47 and 48 show the expected decrease in collection efficiency with decreasing particle size below 10 μm in diameter. The decrease in slope of the collection efficiency versus particle diameter curve suggests a reentrainment process for larger particle sizes.

With respect to ESP model calculations, the in situ particle size distribution measured on February 12, along with ESP operating voltage-current characteristics from February 13 was used as input to the standard SRI/EPA ESP model, a version of that model modified to account for the effect of space charge, and the ADA ESP model. The results of these calculations are shown in Table 4-24 and in Figure 4-52. Figure 4-52 shows penetration through the ESP as a function of particle size as predicted by each model. For comparison, the measured penetration curve is also plotted in this graph. Regardless of the model, it is apparent from the input data sets shown in Table 4-24 that lesser values of reentrainment sneaking are required at a 35°F approach than at a 40°F approach. Also, as Figure 4-52 shows, no model predicts the increase in particulate emissions at particle sizes of less than 5 μm .

The failure of all three models to adequately predict fine particle collection efficiency with excellent electrical operating conditions is a further indication that the collection process for sorbent particles is not well simulated by these models. A similar pattern of disagreement in fractional penetration data was observed during a test of the E-SO_x process,³ although at much lower values of overall collection efficiency.

The apparent increase in ESP performance with decreasing temperature appears anomalous, especially in view of the low resistivity observed at these temperatures. A possible cause of this trend is that residual layers of high resistivity calcium compounds on the collection electrodes were still equilibrating with the environment as the temperature was lowered. Such a process would tend to mask the expected increase in reentrainment at low approach temperatures. However, severe reentrainment was induced during one test series with low approach temperatures and high mass loadings, and these data are discussed in the following paragraphs.

4.2.5.4 ESP Performance During High Ca/S Equilibrium Recycle Tests

During weeks 68 and 69 of testing a series of high Ca/S ratio continuous recycle tests were performed. As with the low Ca/S case described above, this test was intended to determine what SO₂ removals could be obtained when a portion of the spent sorbent and ash was continuously mixed with reagent slaked lime slurry. This test was continued until levels of Ca(OH)₂ in the spent sorbent and ash mixture that were mixed with the reagent slaked lime slurry equilibrated to the level of Ca(OH)₂ measured in ash exiting the ESP. For this test the DITF was operated with a nominal overall Ca/S ratio of 2.4 (reagent Ca/S of 2.0) and a 25°F approach to saturation. Under these conditions from 85 to 90% of the SO₂ was removed.

Tests began on November 7, 1991 and continued until November 15. Because the DITF was not operated for 24 hours a day, a series of separate tests was run. During this time it was not intended to perform a detailed evaluation of ESP performance because, in the past, when slaked lime slurry had been injected at low approach temperatures, ESP performance had not been observed to deteriorate.

Figure 4-52. Fractional penetration predicted by the SRI ESP model, the SRI model corrected for space charge effects, and the ADA ESP model. The second ADA model input data set shown in Table 4-24 was used to generate the results shown in this figure.

From an electrical standpoint the ESP operated in an optimal fashion throughout this test, as is shown in Figures 4-53 and 54 and Table 4-25. Figures 4-53 and 54 show voltage-current curves taken at the conclusion of testing on November 7 and 15 and Table 4-25 shows average ESP operating points and average outlet opacity (referenced to a 25 ft stack) from the DAS. These data show no unusual electrical behavior. However, as Table 4-25 shows, the hourly average outlet opacity record suggests that ESP mass emissions were not as low as the electrical behavior would imply. The average opacity values shown in Table 4-25 are plotted in Figure 4-55. Figure 4-28 shows the typical increase in opacity associated with the start of testing (when the DAS was started at the actual beginning of a test this behavior can be seen), but also shown in this figure is a trend toward higher emissions as the test series progressed. Finally, on November 15, emissions rose to the point where the outlet opacity *averaged* about 80% for the last three hours of testing. Though the opacity monitor at the ESP outlet detected a rapping puff virtually every time any field in the ESP was rapped, ESP electrical operation was normal. Because mass emissions were observed to be increasing, mass trains were run at the ESP outlet on two occasions. The results of these measurements are shown in Table 4-25 and on Figure 4-55. These data also show that ESP collection efficiency was severely degraded.

With respect to ESP model calculations, an estimated inlet mass concentration, along with ESP operating voltage-current characteristics and outlet mass concentration measurement from November 14 was used as input to the standard SRI/EPA ESP model, that model modified to account for the effect of space charge, and the ADA ESP model. The results of these calculations are shown in Table 4-26. As the input data sets for these model calculations show, in order to duplicate the collection efficiency measured on November 14, large amounts of reentrainment had to be included.

These results suggest that the same reentrainment mechanism responsible for poor ESP performance observed in testing of the E-SO_x process³ was active here. The reentrainment process results from electrical forces dislodging collected dust layers and deagglomerating particles of slurry residue. Although the conditions which initiate the occurrence of this process are not well understood, it is apparent that the effects on ESP collection efficiency can be severe when the process is under way.

TEST 68-SR-04, 11/7/91

Figure 4-53. Current density as a function of applied ESP voltage at a 25°F approach to saturation during slurry/recycle ash testing. Test 68-SR-04, November 7, 1991.

TEST 69-SR-03, 11/15/91

Figure 4-54. Current density as a function of applied ESP voltage at a 24°F approach to saturation during slurry/recycle ash testing. Test 69-SR-03, November 15, 1991.

Table 4-25. ESP Operation and Opacity During the High Continuous Recycle Test, November 7-15, 1991

Date	Time	Inlet Field		Second Field		Third Field		Outlet Field		Opacity % b.	Opacity % c.	Mass gr./acf
		kV	nA/cm ²	kV	nA/cm ²	kV	nA/cm ²	kV	nA/cm ²			
11-07-91	13:10	47.05	37.7		55.3	43.24	79.6	43.46	85.5	18.7	71.1	
	14:00	52.42	39.6	a.	51.9	46.66	73.1	47.17	81.0	2.3	12.9	
	15:00	52.91	40.1		53.3	46.97	72.4	48.09	77.4	1.2	6.9	
	16:00	52.80	41.7		56.7	46.39	75.8	47.77	78.8	5.7	29.7	
	17:00	52.96	41.2	47.00	56.2	45.89	77.0	47.26	80.1	1.7	10.0	
	18:00	53.55	37.7	47.00	55.3	45.87	79.6	47.19	85.5	0.7	4.3	
11-21-91	12:00	42.55	35.9	41.61	58.3	41.46	76.7	42.55	78.3	20.9	75.3	
	13:00	50.85	38.9	46.74	55.1	46.84	73.1	47.59	80.9	1.6	9.2	
	14:01	51.93	39.6	47.35	53.0	47.21	71.4	48.55	76.8	0.1	0.6	
	15:01	52.72	38.7	47.19	53.3	47.08	73.1	48.58	77.4	0.2	1.3	
	16:00	52.40	39.1	46.74	56.9	46.20	76.8	47.79	80.4	3.3	18.2	0.028
	17:00	53.21	39.5	46.74	56.6	45.73	78.1	47.01	81.0	5.5	28.8	
11-14-91	12:14	44.56	34.4	46.97	57.5	44.45	84.0	45.40	90.2	12.4	54.8	
	13:00	53.08	40.3	48.93	51.5	47.84	69.1	48.81	77.1	0.2	1.4	
	14:00	53.45	39.9	47.04	53.6	47.52	71.2	49.39	75.4	4.8	25.4	
	15:01	53.73	39.4	46.35	58.3	46.08	78.1	48.03	80.9	6.4	32.8	
	16:00	53.87	39.2	46.31	60.4	45.06	81.5	46.90	84.7	6.8	34.5	
	17:01	52.60	38.6	46.25	56.7	45.29	80.4	46.88	84.3	14.7	61.5	
11-15-91	13:39	47.61	35.7	46.46	55.4	44.41	78.0	46.42	81.1	0.6	3.3	
	14:01	53.59	39.1	47.84	50.1	47.70	71.3	49.47	75.9	1.6	9.3	
	15:03	54.09	39.0	46.72	57.0	47.40	73.4	49.77	74.9	10.5	48.6	
	16:00	53.42	40.5	42.69	58.3	44.10	83.1	47.27	85.7	22.5	78.2	
	17:00	53.11	40.3	43.33	58.5	43.04	84.1	46.35	89.1	22.9	78.9	
	18:01	53.83	39.5	44.54	60.2	43.16	84.3	45.83	88.5	22.8	78.8	
a. DAS channel out of service. Last two points taken manually. b. As measured with 4.177 ft. effective path length. c. Calculated for 25 ft. path length.

Figure 4-55. Average hourly opacity for November 7-15, 1992 during weeks 68 and 69 of testing.

Table 4-26. ESP Model Results for Tests conducted in November, 1991

Date	Approach °F	Measured Efficiency, %	Standard SRI Model ¹ Sneakage, σ_g Efficiency, %	SRI Space Charge Model ¹ Sneakage, σ_g Efficiency, %	Reentrainment, Sneakage, σ_g	ADA Model Efficiency, %
11-14-91	25	98.64 ²	0.58, 0.25 98.63	0.28, 0.25 98.60	0.80, 0.25, 0.25	98.67

1. The SRI sneakage coefficient is defined in the model manuals as a combined factor for gas sneakage and non-rapping reentrainment.
2. Based on inlet mass concentration of 9.0 gr/acf calculated from slurry injection rate and slurry solids content.

5.0 ADVANCED CONFIGURATIONS

For most potential applications, a duct injection process must include a particulate control system which maintains emissions of particulate matter at a level no greater than the emission rate without sorbent injection. Since many existing installations include relatively small electrostatic precipitators which cannot meet this requirement, it will be necessary to consider enlarging or replacing such units.

Because of their relatively compact size, pulse jet fabric filters (PJFF) have been receiving increasing attention as a potential means of reducing particulate emissions from utility boilers. It is also recognized that additional sorbent utilization can be achieved in a fabric filter installed downstream of a low-temperature sorbent injection process such as duct injection.

For these reasons, a decision was made to dedicate most of the resources allocated to Testing of Advanced Configurations to a study of a simulated PJFF operating downstream from a duct injection process. Other issues related to the Advanced Configurations Subtask are 1) Testing of CaCl_2 injection, and 2) Testing of a 12 GPM Lechler nozzle. These issues are addressed in the preceding section concerning slurry injection.

5.1 Fabric Filter Evaluations

A fabric filter device was installed and evaluated downstream of the duct injection process at the DITF. For these tests, a portable sidestream fabric filter (SSFF) was used that simulated the operation of a pulse-jet fabric filter. The SSFF allowed evaluation of SO_2 removal efficiencies, fabric pressure drop behavior, fabric cleanability, and particulate collection efficiency.

SRI fabricated the SSFF for the U.S. DOE. This device is a redesigned version of a portable fabric filter originally designed and built for the Electric Power Research Institute. The SSFF has been useful in screening fabrics and evaluating flue gas conditioning agents at several full-scale utility boilers.

A flue gas sample was extracted on a continuous basis and conveyed to a temperature-controlled sample chamber. A circular swatch of fabric (0.67 ft^2) was mounted vertically in the sample chamber opposite the chamber entrance. The flue gas velocity was reduced as it passed through a conical transform, which uniformly distributed the flue gas before it reached the fabric. Taps are located on each side of the fabric to monitor the pressure drop across the fabric. Ash that was removed from the fabric during cleaning or that did not have sufficient momentum to reach the fabric was collected in the ash hopper, which is located beneath the fabric holder.

The flue gas passed through the fabric and entered an inertial cyclone, which collected, with high efficiency, any ash penetrating the fabric. The flow rate through the fabric was measured by an orifice meter located downstream of the cyclone. The flue gas then flowed out of the heated sampling cabinet, through a liquid chiller, desiccant and filter assembly to clean the gas stream prior to being discharged through a vacuum pump and flow setting hardware. A schematic drawing of the SSFF is presented in Figure 5-1.

At the DITF, the SSFF was installed at the inlet to the ESP, approximately 1.5 s of residence time downstream of the point of slurry injection. A heat-traced sampling probe was located in the center

Figure 5-1. Schematic diagram of the Sidestream Fabric Filter Device.

of the duct and was fitted with a nozzle sized to isokinetically extract a continuous sample of gas at a flow rate of 2.7 acfm (an air-to-cloth ratio of 4.0 ft/min). Thermocouples were located at the inlet of the sample chamber and near the surface of the fabric for precise temperature control. For all tests at the DITF, a needle-felted RytonTM fabric was used, typical of fabrics used in full-scale, pulse-jet baghouses. Operation of the SSFF was controlled by a dedicated interactive data acquisition system.

Continuous gas sampling instruments monitored the flue gas downstream of the fabric. A Western Research SO₂ monitor and Servomex oxygen analyzer extracted a continuous sample downstream of the fabric (at the exit of the liquid chiller device). To assure the flue gas stream being sampled by the gas analyzers was free of moisture, an ice-bath condenser was placed downstream of the liquid chiller.

The SSFF can be operated with reverse-gas cleaning or with pulse-jet cleaning. For operation at the DITF, the SSFF was configured to simulate pulse-jet cleaning. This consisted of adding an external reservoir that was pressurized with compressed air and exhausted through a quick-acting solenoid valve. The pulse air was directed through a pipe and was released tangentially at the center of the clean side of the fabric, similar to the geometry in full-scale, pulse-jet baghouses. The SSFF was configured to pulse-clean on a pressure-initiated basis. Cleaning consisted of two consecutive pulses with a duration of 50 ms that were separated by a period of 10 s. In laboratory measurements, similar pulses had been measured to impart fabric accelerations of about 400 g, typical of the upper portions of bags in a full-scale pulse-jet baghouse.

During initial fabric filter operation with the sorbent/ash product, it was found that the fabric cleaned very easily, resulting in an after-cleaning pressure drop of ~1.0 in. H₂O. In a full-scale pulse-jet baghouse, only a small portion of the bags are pulsed during any one cleaning period, and the average pressure drop across the fabric is typically maintained at approximately 5 in. H₂O. Therefore, to simulate full-scale baghouse operation, initiation of on-line cleaning was set to occur at a fabric pressure drop of 9.0 in. H₂O.

Ash samples were collected from the SSFF hopper after each test condition (once or twice per day). Chemical analyses of the ash samples determined the degree of sorbent utilization. Comparison to calculated values of utilization, based on gas-phase data (SO₂ removal and Ca/S ratio), generally showed good agreement between the two techniques as shown in Figure 5-2.

Several experiments and evaluations validated the SO₂ removal results. In addition to the good agreement of sorbent utilization between solid sample and gas-phase analyses, other indications supported these results.

As the fabric pressure drop increased during a filtration cycle (due to the growth of the filter cake), SO₂ concentrations downstream of the fabric filter decreased in a corresponding fashion. This implies that the filter cake was an active component in SO₂ removal.

There was also a predictable relationship between the SO₂ removals across the ESP and the SSFF. In tests with the SSFF and the duct (and ESP) operating at the same approach-to-saturation temperature, SO₂ removal through the SSFF was consistently 5-10% more than the removal across the ESP for all test conditions.

Figure 5-2. Comparison of sorbent utilization determined from gas-phase data and from chemical analyses of SSFF hopper samples. Data from tests conducted with dry sorbent injection and with slurry injection.

An experiment was devised to determine if any significant SO₂ removal could be attributed to losses through the sampling system. With the SSFF operating at an approach-to-saturation temperature of 15°F, and ~0 ppm of SO₂ downstream of the fabric, a constant flow rate of SO₂ from a gas cylinder (the equivalent of 101 ppm in the diluted gas stream) was injected downstream of the fabric at the immediate exit of the heated sample chamber. An SO₂ concentration of 97 ppm was measured at the SO₂ monitor (downstream of the condensers), indicating less than 5% loss of SO₂ through the sampling system.

Results which were obtained with the SSFF are subdivided as follows: a) Sections 5.1.1 through 5.1.3 present data with the SSFF maintained at essentially the same temperature as the duct spray dryer, and b) Sections 5.2 through 5.4 present data with the SSFF cooled with a secondary cooling step to temperatures significantly lower than the duct spray dryer.

5.1.1 Dry Sorbent Injection

The SSFF was operated during tests with dry sorbent injection (hydrated lime) in which the Ca/S ratio was ~2.0 and for approach-to-saturation temperatures in the duct of 35 and 45°F above saturation. A tabular summary of SSFF test results is presented in Table 5-1. Sulfur dioxide removals (and sorbent utilizations) across the SSFF fabric filter for dry sorbent injection tests were considerably lower than comparable slurry injection tests.

5.1.2 Slurry Injection - Without Recycle

The SSFF was operated during tests with slurry injection at a variety of Ca/S ratios (1.1 to 2.3) and for approach-to-saturation temperatures in the duct of 25 to 45°F. The test results discussed in this section were obtained with the duct injection process operated without recycle.

Tables 5-2 and 5-3 list results of SSFF tests performed with slurry injection (without recycle). The data in Table 5-2 were obtained with a single-stage slurry injection process in which the SSFF was maintained at the temperature of the duct. Table 5-3 contains data obtained with slurry injection followed by water injection in the duct to maintain the duct temperature at 10 to 35°F lower than the evaporative cooling provided by water in the slurry. The SSFF was maintained at the duct temperature downstream from the point of second-stage water injection.

Sulfur dioxide removal for the SSFF is presented for the maximum removal attained (at the end of the filtration cycle) and the average removal (averaged over the entire filtration cycle). Although the data reported for SO₂ removal across the SSFF in subsequent graphical presentations are based on the average SO₂ removal, results for full-scale operation are expected to be closer to the maximum values.

Figure 5-3 presents a summary of SSFF data for SO₂ removal as a function of Ca/S ratio at a duct approach temperature of 25°F. Calculations of SO₂ removals are based on the DITF inlet conditions (before slurry injection). A ranking of SO₂ removals for various conditions is shown by the different curve fits. The bottom curve shows the level of SO₂ removal achieved across the duct (up to the inlet of the ESP). The other two curves show the additional SO₂ removal attributable to the particulate control device (ESP or fabric filter). The fabric filter is shown to consistently remove 5 to 10% more SO₂ (absolute basis) than the ESP for the same conditions.

Table 5-1. SSFF Tests - Dry Sorbent Injection

Test ID	Ca/S	ΔT_s Duct	SO ₂ Removal, %			Utilization, % Gas-phase SSFF-avg.
			SSFF	ESP	Duct	
48-DS-01	2.01	44	34	30	21	17
48-DS-03	2.05	37	44	35	27	21

Table 5-2. SSFF Tests - Slurry Injection Without Recycle

Test ID	Ca/S	ΔT_s Duct	SO ₂ Removal, %				Utilization, % Gas-phase SSFF-avg.
			SSFF (max)	SSFF (avg)	ESP	Duct	
38-SL-03	1.13	25	60.7	55.5	49.9	41.1	49.1
38-SL-01	1.42	25	80.2	74.1	57.0	52.7	52.3
38-SL-02	1.72	25	85.4	81.9	72.5	55.9	47.6
38-SL-02	1.74	25	88.7	82.8	71.3	56.5	47.5
39-SL-02	1.76	25	83.1	80.4	70.6	57.9	45.7
34-SL-02	2.07	25	88.2	84.8	73.0	58.7	41.0
37-SL-02	2.10	25	92.0	86.5	76.3	60.7	41.1
37-SL-03	2.11	25	93.0	89.0	76.8	62.4	42.3
37-SL-04	2.20	25	98.7	93.5	77.7	62.1	42.5
37-SL-04	2.21	25	97.5	94.2	80.5	63.4	42.7
37-SL-04	2.23	25	95.2	92.2	81.1	63.4	41.4
33-SL-04	2.00	45	66.2	63.9	64.0	51.8	32.0
33-SL-04	2.00	45	64.0	61.8	63.0	51.2	30.9
33-SL-04	2.00	45	72.1	64.4	58.0	47.8	32.2

Table 5-3. SSFF Tests - Slurry Injection Without Recycle With Two-Stage Humidification

Test ID	Ca/S	ΔT s Duct		SO ₂ Removal, %				Utilization, % Gas-phase SSFF-avg.
		Duct	SSFF	SSFF (max)	SSFF (avg)	ESP	Duct	
39-SL-02	1.77	35/25	25	77.9	69.8	66.2	51.0	39.3
39-SL-01	1.85	35/25	25	83.5	79.0	66.9	50.9	42.8
38-SL-04	1.88	35/25	25	78.4	72.4	64.2	54.1	38.6
39-SL-01	1.89	35/25	25	79.7	74.8	65.4	50.1	39.5
39-SL-04	1.71	45/25	25	75.8	72.5	64.4	50.0	42.5
39-SL-05	1.73	45/10	10	97.7	90.6	74.9	57.9	52.4

Figure 5-3. SO₂ removal as a function of Ca/S ratio for a duct approach temperature and SSFF approach temperature of 25°F. Data obtained during slurry injection testing.

5.1.3 Slurry Injection - With Recycle

The SSFF was operated during tests with reagent slurry plus recycle material injected at similar Ca/S ratios and duct approach temperatures as during the tests without recycle. More discussion concerning slurry with recycle ash is presented in section 4.2.2. Results of the SSFF tests are presented in Table 5-4.

5.2 Dry Sorbent Reactivation

Since SO₂ removals improved significantly when the duct was operated at lower approach-to-saturation temperatures (e.g. 25 versus 45°F), a decision was made to investigate SSFF operation at lower temperatures than duct temperatures. Because of the small scale of the SSFF, it was practical to operate the SSFF at lower temperatures than the duct conditions. The temperature controller set points were lowered for the sample probe and the sample chamber, which provided cooling by as much as 35°F at the fabric, without having "cold spots" in the sample probe or sampling chamber. The SSFF could achieve these lower temperatures by utilizing the sampling probe and heated sample chamber as a passive heat exchanger. This allowed the SSFF to operate at temperatures approximating the adiabatic saturation temperature while the duct was operating at 25°F above the saturation temperature.

It should be noted that cooling the flue gas without the addition of water is not an adiabatic saturation process. Therefore, if the SSFF is cooled, for example, 25°F below the duct temperature to the calculated adiabatic saturation temperature without additional water, the flue gas is actually a few degrees above the true saturation point.

It was found that very high SO₂ removals could be achieved (over 95%) with the duct operating at an approach temperature of 25°F and the SSFF operating at an approach temperature of 10°F for a Ca/S ratio of 2 (without recycle) for an SO₂ concentration of 2000 ppm upstream of duct injection. There were no operational problems at a 25°F approach temperature (in the duct) with the SSFF operating at the saturation temperature. The filter cake remained dry and cleaned normally at the calculated saturation temperature.

The secondary cooling step upstream of the fabric filter, (without the addition of water), reactivated nearly dry sorbent and significantly increased sorbent utilization. In view of the favorable operating characteristics of the fabric filter at the low approach-to-saturation temperatures, and the very high SO₂ removals observed with the unique secondary cooling step, Southern Research Institute has applied for a patent for this process.

This process of using a secondary cooling step downstream of a slurry injection process, and upstream of a fabric filter, has been named Dry Sorbent Reactivation (DSR). A preliminary economic analysis indicates that DSR has the potential to be economically competitive with other high efficiency (90+ % removal) flue gas desulfurization processes.

5.2.1 Dry Sorbent Injection

The SSFF was operated during tests with dry sorbent injection with the SSFF operating over a range of approach-to-saturation temperatures from 2 to 45°F. During these tests, the DITF operated at a Ca/S ratio of ~2.0 and the duct was operated at 35 and 45°F approach-to-saturation temperatures. A summary of the SSFF test results is presented in Table 5-5.

Table 5-4. SSFF Tests - Slurry Injection with Recycle

Test ID	Overall Ca/S	Reagent Ca/S	Recycle Ratio	ΔT_s Duct	SO ₂ Removal, %			Utilization, % Gas-phase SSFF-avg.
					SSFF	ESP	Duct	
68-SR-01	1.33	1.03	2.22	44	61.8	51.0	40.2	60.0
67-SR-02	1.38	1.05	2.05	44	63.0	53.5	43.2	60.0
67-SR-03	1.56	1.03	1.83	44	63.3	54.0	43.3	61.5
68-SR-02	1.29			25	73.8	63.0	51.9	
68-SR-02	1.29	1.18	2.15	28	69.2	63.4	49.2	58.6
68-SR-02	2.45	2.06	1.31	27	96.5	86.0	66.3	46.8
68-SR-03	2.16	1.78	1.44	27	94.4	82.4	63.4	53.0
69-SR-02	2.64	1.98	1.23	25	97.8	88.5	65.4	49.4
69-SR-03	2.45	1.82	1.35	23	97.0	89.8	64.9	53.3

Table 5-5. SSFF/DSR Tests - Dry Sorbent Injection

Test ID	Ca/S	ΔT_s Duct		SO ₂ Removal, %			Utilization, % Gas-phase SSFF-avg.
		Duct	SSFF	SSFF	ESP	Duct	
48-DS-01	2.01	44	45	34	30	21	17
48-DS-01	2.01	44	35	39	30	21	19
48-DS-01	2.01	44	25	44	30	21	22
48-DS-02	2.07	45	20	51	31	21	25
48-DS-02	2.07	45	10	59	31	21	29
48-DS-03	2.05	37	35	44	35	27	21
48-DS-03	2.05	37	20	53	35	27	26
48-DS-03	2.05	37	10	62	35	27	30
48-DS-04	2.01	35	2	79	33	25	30

Figure 5-4 presents SO₂ removal versus approach temperature at the SSFF for the two temperature conditions in the duct. Sulfur dioxide removal across the SSFF increased with lower approach-to-saturation temperatures, although the SO₂ removals were lower than for comparable slurry injection tests. For an approach-to-saturation temperature of 45°F, SO₂ removal for slurry injection test was approximately 25% higher than for dry sorbent injection, as shown in Figure 5-4.

5.2.2 Slurry Injection - Without Recycle

The SSFF was operated during tests with slurry injection at a variety of Ca/S ratios and approach-to-saturation temperatures. Figures 5-5, 5-6, and 5-7 present typical data collected from the SSFF during tests with slurry injection. The figures document the pressure drop across the SSFF fabric, the fraction of SO₂ removed across the SSFF and the fraction of SO₂ removed due to the combined effect of the duct and the SSFF.

These figures illustrate the trend of increasing SO₂ removal through a filtration cycle and the enhancement of SO₂ removal at reduced temperatures for the SSFF (with constant duct temperatures). A complete summary of SSFF test results with slurry injection without recycle are presented in Tables 5-6 and 5-7. To further illustrate the increased SO₂ removal with the secondary cooling step, Tables 5-6 and 5-7 contain data presented in previous tables in which the SSFF was operated at duct temperatures.

In Figure 5-5, the DITF was operated at an approach-to-saturation temperature of 45°F in the duct with a Ca/S ratio of 2.0. The SSFF was operated at different approach-to-saturation temperatures (25, 15, and 10°F). This figure shows that SO₂ removal (and sorbent utilization) increased significantly as the approach temperature at the fabric was reduced. Figure 5-6 shows that enhanced SO₂ removal was achieved for the same test conditions as Figure 5-5, except that the duct was operated at an approach-to-saturation temperature of 25°F instead of 45°F. As shown in Figure 5-6, there was practically 100% SO₂ removal with the SSFF operating at 10°F above the saturation temperature.

In Figure 5-7, the DITF was operated at an approach-to-saturation temperature of 25°F in the duct with a Ca/S ratio of 1.75. The SSFF was operated at approach temperatures of 10, 5, and 0°F. Similar to the previous graph, very high SO₂ removal was measured at low approach temperatures at the fabric. Of particular interest, the data demonstrated that filtration performance was unaffected at low operating temperatures, even at the saturation temperature. The pulse-cleaning easily removed the dustcake at all temperatures. The ash and sorbent product that was removed from the ash hopper at the termination of the 0°F approach-to-saturation temperature test condition was found to be dry and flowed freely. These observations contradict anecdotal reports of dry FGD systems with fabric filters that have suffered excursions below the water dew point that caused bag blinding or otherwise irreversible damage to the filter bags.

The fabric pressure drop curve in Figure 5-7 shows that a baghouse may actually operate at a lower drag (defined as pressure drop divided by gas flow rate) at temperatures very near the saturation temperature. The slope of the fabric pressure drop curve decreased as the temperature decreased from 10°F above saturation to 5°F above saturation, and was significantly lower at the saturation temperature. This suggests that a more porous dustcake was formed as the saturation temperature was approached.

Figure 5-4. SO₂ removal averaged over a filtration period in the SSFF as a function of the approach temperature with the SSFF for approach temperatures in the duct of 35°F and 45°F and a Ca/S ratio of 2.0. Data obtained during dry sorbent injection testing.

SSFF TESTS - CA/S = 2.0
 Inlet SO₂ = 2000 ppm, Duct Approach = 45°F

Figure 5-5. SSFF data obtained during slurry tests in which the approach temperature within the SSFF was lowered from 25 to 10°F in two steps. Data shown for duct approach temperature of 45°F.

SSFF TESTS - CA/S = 2.0
Inlet SO₂ = 2000 ppm, Duct Approach = 25°F

Figure 5-6. SSFF data obtained during slurry tests in which the approach temperature within the SSFF was lowered from 25 to 10°F in two steps. Data shown for duct approach temperature of 25°F.

SSFF TESTS - CA/S = 2.0
 Inlet SO₂ = 2000 ppm, Duct Approach = 25°F

Figure 5-7. SSFF data obtained during slurry tests in which the approach temperature within the SSFF was lowered from 10 to 0°F in two steps. Data shown for duct approach temperature of 25°F.

Table 5-6. SSFF/DSR Tests - Slurry Injection Without Recycle

Test ID	Ca/S	ΔTs Duct		SO ₂ Removal, %				Utilization, % Gas-phase SSFF-avg.
		Duct	SSFF	SSFF (max)	SSFF (avg)	ESP	Duct	
38-SL-03	1.13	25	25	60.7	55.5	49.9	41.1	49.1
38-SL-01	1.42	25	25	80.2	74.1	57.0	52.7	52.3
38-SL-02	1.72	25	25	85.4	81.9	72.5	55.9	47.6
38-SL-02	1.74	25	25	88.7	82.8	71.3	56.5	47.5
39-SL-02	1.76	25	25	83.1	80.4	70.6	57.9	45.7
34-SL-02	2.07	25	25	88.2	84.8	73.0	58.7	41.0
37-SL-02	2.10	25	25	92.0	86.5	76.3	60.7	41.1
37-SL-03	2.11	25	25	93.0	89.0	76.8	62.4	42.3
37-SL-04	2.20	25	25	98.7	93.5	77.7	62.1	42.5
37-SL-04	2.21	25	25	97.5	94.2	80.5	63.4	42.7
37-SL-04	2.23	25	25	95.2	92.2	81.1	63.4	41.4
34-SL-02	2.06	25	15	97.0	93.4	78.0	60.8	43.7
37-SL-04	2.25	25	15	99.9	98.1	78.8	61.3	
37-SL-04	2.25	25	15	99.9	97.8	78.8	62.0	
38-SL-03	1.15	25	10	69.6	63.7	51.8	39.6	55.6
38-SL-01	1.42	25	10	89.2	83.8	70.6	54.4	59.1
38-SL-02	1.73	25	10	95.2	90.9	74.2	56.7	52.5
38-SL-02	1.75	25	10	94.3	92.1	73.4	58.5	52.7
38-SL-02	1.75	25	10	94.6	90.7	73.1	57.0	51.8
39-SL-02	1.75	25	10	95.2	89.8	73.7	57.4	51.5
39-SL-03	1.74	25	10	91.7	85.9	73.0	57.1	49.2
37-SL-03	2.04	25	10	99.5	96.3	74.8	57.9	47.2
37-SL-03	2.10	25	10	97.2	93.1	73.9	57.5	44.4
37-SL-03	2.05	25	10	96.4	92.8	73.6	57.3	45.3
34-SL-02	2.07	25	10	99.9	98.9	78.5	60.6	47.8
39-SL-03	1.75	25	5	99.9	97.3	75.7	58.5	55.6
39-SL-03	1.75	25	0	99.9	99.7	74.1	57.9	57.1
33-SL-04	2.00	45	45	66.2	63.9	64.0	51.8	32.0
33-SL-04	2.00	45	45	64.0	61.8	63.0	51.2	30.9
33-SL-04	2.00	45	25	72.1	64.4	58.0	47.8	32.2
34-SL-03	1.80	45	25	74.2	69.3	56.3	46.0	38.5
34-SL-03	1.80	45	15	86.0	80.3	57.4	46.9	44.6
34-SL-03	1.80	45	10	94.1	88.5	58.2	45.8	49.2

Table 5-7. SSFF/DSR Tests - Slurry Injection Without Recycle With Two-Stage Humidification

Test ID	Ca/S	ΔT_s Duct		SO ₂ Removal, %				Utilization, % Gas-phase SSFF-avg.
		Duct	SSFF	SSFF (max)	SSFF (avg)	ESP	Duct	
39-SL-02	1.77	35/25	25	77.9	69.8	66.2	51.0	39.3
39-SL-01	1.85	35/25	25	83.5	79.0	66.9	50.9	42.8
38-SL-04	1.88	35/25	25	78.4	72.4	64.2	54.1	38.6
39-SL-01	1.89	35/25	25	79.7	74.8	65.4	50.1	39.5
38-SL-04	1.88	35/25	10	88.2	83.7	67.2	53.3	44.4
39-SL-04	1.64	45	25	62.4	57.9	47.4	38.4	35.3
39-SL-04	1.71	45/25	25	75.8	72.5	64.4	50.0	42.5
39-SL-04	1.72	45/25	10	91.7	85.8	62.3	47.4	49.8
39-SL-05	1.74	45/25	10	92.1	88.1	65.8	51.2	50.5
39-SL-05	1.73	45/10	10	97.7	90.6	74.9	57.9	52.4

Figure 5-8 presents a summary of SO₂ removal as a function of Ca/S ratio at a duct approach temperature of 25°F. This graph is a repeat of Figure 5-3 with the addition of the SSFF data using the secondary cooling step. A ranking of SO₂ removals for various conditions is shown by the different curve fits. The bottom curve shows the level of SO₂ removal achieved across the duct (up to the inlet of the ESP). The next two curves show the additional SO₂ removal attributable to the particulate control device (ESP or SSFF fabric filter) operated at a temperature 25°F above saturation. The upper curve shows the additional SO₂ removal across the SSFF achieved by lowering the approach temperature at the fabric from 25 to 10°F.

Figure 5-9 presents SO₂ removal as a function of the approach temperature at the SSFF fabric, with three separate curves showing the dependency on Ca/S ratio over a range of 1.42 to 2.10. These data are shown for the duct at a temperature 25°F above saturation. There is an expected increase in SO₂ removal at higher Ca/S ratios, although this benefit must be weighed against the lower sorbent utilizations realized at the higher Ca/S ratios. For the purposes of comparison, data are shown for ESP operation.

Figure 5-10 presents SO₂ removal as a function of the approach temperature at the SSFF fabric, with a 25 and 45°F approach temperature in the duct. These data are shown for a Ca/S ratio of approximately 1.75. There is an expected increase in SO₂ removal at the lower duct approach temperature in addition to the effect of lower approach temperatures at the SSFF.

5.2.3 Slurry Injection - With Recycle

A series of SSFF tests were conducted with slurry plus recycle material injected at Ca/S ratios and duct approach temperatures similar to those used during tests without recycle ash addition. Results from all SSFF tests for reagent slurry injection with recycle ash addition are presented in Table 5-8.

To illustrate the benefits of recycle, SSFF data obtained with and without recycle are presented in Figure 5-11. This figure shows SO₂ removal versus Ca/S ratio for the SSFF operating without recycle at a 10 and 25°F approach temperature (as shown in Figure 5-8). Sulfur dioxide removal data obtained with recycle ash addition for two test conditions are plotted versus "reagent" and "overall" Ca/S ratios. These test conditions are identified in Table 5-8 by asterisks. The reagent Ca/S ratio is the part of the sorbent mixture which has not yet been exposed to flue gas. The overall Ca/S ratio is from the combination of reagent sorbent and recycle material and is derived from the effective calcium available for reaction.

The data are shown with dotted lines from the SO₂ removal data point to the abscissa at the values of the reagent and overall Ca/S ratio. The difference between the Ca/S values illustrates the economic benefit in terms of the amount of sorbent required to achieve particular levels of SO₂ removal. However, in a full-scale continuous process, somewhat higher values of recycle ratio would be required to achieve the SO₂ removal levels illustrated by the two recycle cases in Figure 5-11. This results from the fact that the recycled sorbent material used for these tests were taken from the ESP hoppers which has more unutilized calcium than would recycle material from a fabric filter with an upstream secondary cooling step.

Figure 5-8. SO₂ removal as a function of Ca/S ratio for a duct approach temperature of 25°F and SSFF approach temperatures of 25 and 10°F. Data obtained during slurry injection testing.

Figure 5-9. SO₂ removal averaged over a filtration period in the SSFF as a function of the approach temperature within the SSFF for three Ca/S ratios at an approach temperature of 25°F in the duct. ESP SO₂ removal data also shown. Data obtained during slurry injection tests.

Figure 5-10. SO₂ removal averaged over a filtration period in the SSFF as a function of the approach temperature within the SSFF for approach temperatures in the duct of 25°F and 45°F. Data obtained during slurry injection testing.

Table 5-8. SSFF/DSR Tests - Slurry Injection with Recycle

Test ID	Overall Ca/S	Reagent Ca/S	Recycle Ratio	ΔT_s Duct		SO ₂ Removal, %			Utilization, % Gas-phase SSFF-avg.
				Duct	SSFF	SSFF	ESP	Duct	
68-SR-01	1.33	1.03	2.22	44	40	61.8	51.0	40.2	60.0
67-SR-02	1.38	1.05	2.05	44	40	63.0	53.5	43.2	60.0
67-SR-03	1.56	1.03	1.83	44	40	63.3	54.0	43.3	61.5
67-SR-03	1.48	1.14	1.72	45	20	72.6	54.3	42.7	63.7
68-SR-01	1.48	1.02	2.12	45	10	76.1	52.0	41.3	74.6
68-SR-02	1.29			25	25	73.8	63.0	51.9	
68-SR-02	1.29	1.18	2.15	28	25	69.2	63.4	49.2	58.6
*68-SR-02	1.64	1.18	2.34	33	10	83.8	63.1	48.9	71.0
68-SR-02	2.45	2.06	1.31	27	25	96.5	86.0	66.3	46.8
68-SR-03	2.16	1.78	1.44	27	25	94.4	82.4	63.4	53.0
68-SR-03	2.54	1.99	1.40	30	20	96.8	82.8	62.8	48.6
69-SR-02	2.64	1.98	1.23	25	20	97.8	88.5	65.4	49.4
69-SR-03	2.45	1.82	1.35	23	20	97.0	89.8	64.9	53.3
*69-SR-03	2.28	1.74	1.46	24	10	99.4	88.3	65.3	57.1

Figure 5-11. SO₂ removal across the SSFF as a function of Ca/S ratio illustrating the effect of recycle.

5.3 NO₂ Capture Across the Fabric Filter

A brief study was conducted to determine the levels of NO₂ capture across the fabric filter at various operating conditions. It was hypothesized that fabric filter operation at low approach-to-saturation temperatures might enhance the capture of NO₂ by reaction with unutilized Ca(OH)₂ in the filter cake. The following disproportionation reaction is the mechanism through which capture of NO₂ is expected to occur:

The fraction of NO_x which exists as NO₂ in flue gas is too small for this mechanism to be of practical interest unless an oxidation process were added upstream of sorbent injection. However, if essentially complete capture of NO₂ could be demonstrated in the filter cake, a combined NO oxidation and low temperature capture process for NO₂ might have practical significance.

Because of the very low levels of NO₂ naturally occurring in the flue gas stream, it was necessary to "spike" the sidestream flue gas being sampled by the SSFF with a known concentration of NO₂ gas (from a gas cylinder bottle). Quantification of the NO₂ removal was provided by injecting NO₂ gas alternately upstream and downstream of the fabric filter. Concentrations of NO/NO_x were continuously monitored with a Thermo Electron Model 10 NO_x analyzer located downstream of the fabric. A quantitative removal efficiency could be determined for a range of NO₂ concentrations when compensation is made for the flue gas dilution by the N₂ carrier of the NO₂ gas. A permeation dryer was used to remove water vapor prior to the NO_x analyzer in an effort to minimize losses of NO₂ in the sampling system.

The concentration of NO₂ contained in the gas bottle was determined to be 530 ppm, following laboratory calibration of the NO_x analyzer with a known concentration of NO gas. Subsequently, the calibration of the NO_x analyzer was set with the NO₂ gas in the NO_x mode. The instrument was rechecked periodically during the sampling period.

In view of the principle of operation of the NO_x analyzer (measurement of light energy produced when NO is oxidized to NO₂), this calibration procedure may not detect inaccuracies in absolute NO₂ values caused by failure of the converter in the instrument to reduce all NO₂ to NO. However, the trends observed in the following experiments should be valid.

Table 5-9 presents a summary of experimental data obtained on February 20 and 25, 1992, at the indicated times. Flow rate variables used in the table headings are defined as follows:

Q-tot = total flow rate through fabric

Q-flue = flow rate of flue gas only

Q-NO₂ = flow rate of bottle gas with 530 ppm NO₂

Using the measured flow rates of flue gas and bottled gas, it is possible to calculate the expected concentration of NO downstream of the filter if no reduction of NO₂ to NO occurred in the system. Similarly, using the concentration of NO₂ in the bottle gas and the gas stream flow rates, it is possible to calculate the expected NO₂ concentration the analyzer should indicate when the bottled gas is injected downstream of the fabric filter, where reduction of NO₂ is not expected to occur.

Table 5-9. SSFF NO_x Measurement Results

Start Time	Q-tot acfm (wet)	Q-flue acfm (wet)	Q-flue acfm (dry)	Q-NO ₂ acfm (dry)	NO ₂ Injection UP/DN*	Measured			Calculated		
						NO ppm	NO _x ppm	NO ₂ ppm	NO ppm	NO _x ppm	NO ₂ ppm
2/20/92 Natural flue gas NO concentrations: 450-460 ppm											
13:00	2.67	2.67	2.38	0.00	—	460	460	0			
13:45	2.66	2.66	2.38	0.00	—	450	450	0			
13:32	2.04	2.04	1.82	0.50	DN	355	450	95	357	471	114
13:41	2.04	2.04	1.82	0.50	DN	340	430	90	357	471	114
14:41	2.06	2.06	1.84	0.50	DN	360	450	90	358	471	113
13:35	2.55	2.05	1.83	0.50	UP	400	400	0			
14:34	2.65	2.15	1.92	0.50	UP	400	400	0			
14:45	2.65	2.15	1.92	0.50	UP	420	430	10			
SSFF Inlet SO ₂ = 870 ppm, SSFF outlet SO ₂ = 160 ppm, Ca/S = 1.3, 12% H ₂ O											
2/25/92 Natural flue gas NO concentrations: 270-280 ppm											
15:12	2.67	2.67	2.38	0.00	—	285	290	5			
15:50	2.67	2.67	2.38	0.00	—	270	275	5			
16:06	2.70	2.70	2.41	0.00	—	288	290	2			
15:55	2.67	2.67	2.38	0.00	—	280	280	0			
15:02	2.16	2.16	1.92	0.50	DN	240	340	100	218	328	109
15:56	2.22	2.22	1.98	0.50	DN	240	320	80	220	326	107
16:30	2.22	2.22	1.98	0.50	DN	245	320	75	220	326	107
14:58	2.69	2.19	1.95	0.50	UP	270	300	30			
15:06	2.69	2.19	1.96	0.50	UP	260	283	23			
15:53	2.69	2.19	1.96	0.50	UP	270	270	0			
16:00	2.70	2.20	1.96	0.50	UP	260	270	10			
16:25	2.67	2.17	1.94	0.50	UP	245	248	3			
16:32	1.84	1.84	1.64	1.00	DN	205	365	160	171	371	201
16:41	1.80	1.80	1.61	1.00	DN	202	368	166	170	373	203
16:38	2.67	1.67	1.49	1.00	UP	215	260	45			
16:45	1.22	1.22	1.09	1.50	DN	160	405	245	116	423	307
16:48	2.67	1.17	1.04	1.50	UP	180	295	115			
16:51	2.67	1.17	1.04	1.50	UP	190	310	120			
16:52	2.66	1.16	1.04	1.50	UP	185	335	150			
17:43	1.37	1.37	1.22	1.38	DN	175	380	205	129	410	281
17:46	2.65	1.27	1.13	1.38	UP	175	220	45			
17:46	2.65	1.27	1.13	1.38	UP	175	230	55			
17:46	2.65	1.27	1.13	1.38	UP	180	250	70			
17:46	2.65	1.27	1.13	1.38	UP	180	265	85			
SSFF inlet SO ₂ = 383 ppm, SSFF outlet SO ₂ = 50 ppm, Ca/S = 1.5, 12% H ₂ O											

*UP = Upstream of SSFF, DN = Downstream of SSFF.

The following observations can be made from the data set obtained on February 20, 1992 as presented in Table 5-9:

- the filter cake reduced the NO_2 concentration from a calculated input value of 113-114 ppm to 0-10 ppm.
- the measured NO_2 value with bottled gas injected downstream of the filter is only about 80% of the expected value, indicating some loss of NO_2 in the sampling system.
- when NO is measured downstream of the fabric with NO_2 bottled gas injected upstream, the value of NO is about 50 ppm higher than the calculated value, suggesting a significant fraction of the apparent NO_2 reduction may have occurred from reduction of NO_2 back to NO. Note that fairly good agreement (352 vs 357 avg ppm) between calculated and measured NO values is obtained when the bottled gas is injected downstream of the filter, suggesting the increase in NO did not occur in the sampling system.

These results were obtained when the DITF was operating with a Ca/S ratio of 1.3. The SSFF was operating within $\sim 10^\circ\text{F}$ of saturation with inlet and outlet SO_2 concentrations of 870 and 160 ppm, respectively.

If the NO_2 disappearance from the gas phase were caused by the reaction with $\text{Ca}(\text{OH})_2$, an equimolar ratio of nitrite and nitrate should be found in the solids removed from the SSFF, in an amount equivalent to the apparent NO_2 reduction. However, analysis of the solids obtained during the period of NO_2 injection on February 20 indicated that less than half of the NO_2 disappearance could be accounted for by the sum of nitrite and nitrate ions found in the SSFF solids.

An additional series of measurements was performed on February 25, 1992, with the SO_2 and NO_x concentrations reduced from the previous set of conditions on February 20, as indicated in Table 5-9. Under these conditions, apparent NO_2 removal with an injected NO_2 concentration of ~ 108 ppm was variable, ranging from 100% to 72% (0 to 30 ppm NO_2 downstream of the fabric). Some anomalies are apparent in the data, however, as indicated by the decrease of measured NO_2 concentration with downstream injection from 100 to 75 ppm during a period the injection rate of NO_2 bottled gas should have produced ~ 108 ppm NO_2 .

For the final series of experiments, the proportion of NO_2 bottled gas injected was increased to produce calculated NO_2 concentrations of ~ 202 , 281, and 307 ppm. For these conditions, NO_2 penetration of the filter cake was significant, rising to 49% (150 ppm) at the 307 ppm injection level.

When the injected NO_2 concentration was calculated to be 307 ppm, the equivalence ratio, defined as moles of unreacted calcium divided by the sum of the moles of SO_2 remaining plus two times the moles of NO_2 at the SSFF inlet, was 0.52. This contrasts with an equivalence ratio of 1.49 when the injected NO_2 concentration was ~ 108 ppm and the SO_2 at the SSFF inlet was 383 ppm. It is interesting to note that a trend of increasing NO_2 penetration with injection time is observed at the lower equivalence ratio values.

It should be noted the final series of experiments also indicates an unexplained loss of NO_2 when the bottled gas is injected downstream of the fabric. A comparison of calculated and measured NO

values indicates NO values significantly higher than expected, which suggests some of the missing NO₂ may have been reduced to NO.

The following conclusions have been derived from this brief series of experiments:

- Reductions in NO₂ concentrations from 91 to 100% were observed across the filter cake when an NO₂ concentration of ~114 ppm was injected upstream of the SSFF.
- Only a small fraction (less than 50%) of the apparent NO₂ reduction could be accounted for by the sum of nitrite and nitrate ions in the collected solids.
- Penetration of NO₂ through the filter cake increased to values as high as 50% when the injected NO₂ concentration was increased to 200-300ppm.

Additional experiments are needed to provide more quantitative results and to better define the mechanism of NO₂ reduction. However, in view of the visibility problems caused by small concentrations of NO₂ in stack gas, any process involving oxidation of NO to NO₂ would need to demonstrate essentially complete capture of NO₂ to be of practical significance.

5.4 Condensables Tests

There are increasing concerns by the utility industry and regulatory agencies about the concentrations of condensable particulate matter (CPM) at the outlet of conventional control devices. EPA test method 202 prescribes the measurement of condensable particulate emissions from stationary sources, for determination of the condensable matter that condenses after passing through an in-stack filter. Fabric filter operation at low approach-to-saturation temperatures with slaked lime slurry injection is expected to enhance the collection of CPMs because the filter cake comprises a medium of active sorbent material. A simulation of a Method 202 test was performed downstream of the SSFF.

An impinger train was set up at the outlet of the fabric filter. The sampling protocol and sample recovery techniques prescribed by the EPA test methods were followed. For each measurement, the SSFF impinger train sampled for 60 minutes at 0.75 acfm yielding 40 cubic feet of gas pulled through the impingers. The samples collected were subsequently analyzed in the laboratory. Table 5-10 presents a summary of test conditions and results for data obtained on January 16 and 17, 1992.

Unfortunately, a significant level of organic material contamination was found in the collected samples which interfered with the intended determination of total mass concentrations. The contamination is believed to be the reason the measured concentrations of total mass are much larger than the sum of the measured chloride and sulfate concentrations. The contamination was suspected to be fuel oil residue from the dilution burner or lubricating oil from the compressed air system.

Table 5-10. Results of CPM Tests

Run ID	SO ₂ ppm SSFF Out	Sulfates		Chlorides		Total Mass mg/m ³
		mg/m ³	ppm H ₂ SO ₄	mg/m ³	ppm HCL	
¹ CPM-2	0	0.265	0.065	0.088	0.06	8.64
² CPM-4	150	4.51	1.1	0.44	0.30	13.4

¹Conditions: Ca/S = 4.0, inlet SO₂ = 1000 ppm, ΔTs = 25°F duct and SSFF.

²Conditions: Ca/S = 2.3, inlet SO₂ = 2800 ppm, ΔTs = 25°F duct and SSFF.

Even though the organic contamination compromised the results of the CPM total mass measurements, the low chloride and sulfate concentrations confirm the expected effectiveness of the low-temperature filter cake in limiting the penetration of condensable chlorides and sulfates through the SSFF.

6.0 PROCESS OPERATION TASKS

6.1 Process Controls - Task 3.4

The contract scope of work for Subtask 3.4 - "Design and Testing of a Process Control System" requires that tests be conducted to demonstrate a viable process control scheme for duct injection technologies. Considerable experience with process control was gained from the continuous ongoing operations of the pilot plant. This experience was considered in establishing the final process controls test program.

The process control system which was designed for the Beverly Test Facility was microprocessor-based so as to facilitate changes in process control strategy. A series of tests was designed and executed to simulate expected disturbances or upsets in boiler and duct injection technology equipment and process conditions and the dynamic response of the duct injection technology/ESP system was recorded. The purpose of these tests was to:

- Identify reliable system control parameters for duct injection technology processes.
- Identify reliable system diagnostic parameters for duct injection technology processes.
- Provide control system design information for scale up of duct injection technology.
- Demonstrate long-term, reliable, controllable and safe operation for the duct injection technology process.

6.1.1 Description of the Process Control System

The DITF instrument and control system was designed using a mixture of existing equipment hardware and software and a new Allen-Bradley Programmable Logic Controller (PLC) 5/25 control system. All of the process and equipment control is assigned to the new PLC system while the existing Data Acquisition System (DAS) was strictly limited to data acquisition. Figure 6-1 shows a schematic of the PLC and DAS system that was operated through the test program. For more detailed description of the process control system, the reader is referred to Topical Report No. 2 for this contract, Section 3.2.

All new equipment start and stop functions are performed via a work station in the control room. The work station consists of a keyboard and CRT and has the capability of displaying the various process loops in real-time. The control scheme for slurry injection is based on setting the slurry feed rate to maintain a desired Ca/S ratio, while slurry concentration is adjusted by dilution water to maintain exit gas approach temperature. For dry sorbent injection, both lime addition and exit gas temperature can be controlled independently. In addition, the capability is present to test the use of SO₂ removal efficiency as the control point by automatically adjusting the lime or slurry feed rate. The PLC system is able to respond to fluctuations in the inlet SO₂ concentration, gas temperature, gas flow rate, and allow the process or equipment upset conditions to be detected and corrected without process shutdown.

Figure 6-1. Schematic diagram of the process control system.

Process control relative to flue gas dilution and temperature is designed to produce a flue gas stream with a specified or test SO₂ concentration, inlet gas temperature, and inlet gas volumetric flow rate. In order to minimize changes to other flue gas parameters, particularly the adiabatic saturation temperature, when diluting the extracted flue gas from Unit 5, the water concentration of the diluting gas must match those of the extracted flue gas from Unit 5. The dilution air is controlled by the desired SO₂ concentration, the duct burner firing by the desired test temperature, and the moisture addition by an algorithm which calculates the required humidity from a typical coal analysis, the measured excess air, and ambient humidity. Moisture is added by a controlled steam flow based on this algorithm.

6.1.2 Modifications to the Process Control System

One of the goals of the process control system design was to produce a flexible, reliable, readily understood, user friendly system that would be easily learned by the operating and maintenance staff on-site at the DITF. As testimony to the achievement of that intent, the on-site staff made a number of modifications to the process control system throughout the nearly two year test period to improve the data acquisition, operation and maintenance of the facility. These modifications were readily made by the on-site staff without any assistance from the original system design team. Problems were identified and effectively resolved on-site.

A number of these system modifications are listed below for illustration:

1. The air compressor control panel input power was removed from the stepdown transformer supplied with the drive motor starter and added to the filtered supply from the PLC. This was done to isolate the control microprocessor from motor drive noise which was causing false alarms and trips of the air compressor.
2. The gas analyzer sample sequence was completely reworked to allow for the addition of a constant flow by-pass pump system. By constantly drawing a flue gas sample through each sample hose and by-passing it to the outside, the time interval between sample readings was greatly reduced. The by-pass system allowed for each sample port to always have a fresh sample of flue gas when it was called for.
3. Three new thermocouple insert cards were added to the remote data acquisition controllers to add 60 additional channels of duct wall temperature measurements. After this modification, all of the vertical and horizontal duct wall thermocouples could be monitored and recorded at the same time. One set of Kurz velocity/temperature probes was removed which made nine more channels available for wall temperature measurements. The DAS program was modified to accomodate this change.
4. In order to obtain a precise measurement of nozzle atomizing air flow, a Foxboro flow computer was added to the vortex flow tube already in the line. This flow computer also required the addition of an absolute pressure transmitter and an air temperature RTD. The output of the absolute pressure transmitter was also used by the control room operator to monitor the air system pressure since there was none provided before.
5. Heater tapes were added to the air compressor pressure control transducers, the fuel oil burner atomizing air lines, and to various other pipes in the slurry injection system as needed.

6. The system ID fan control damper control was moved from the old GE control panel to the PLC. A new PID loop was added to the PLC program so the operator could control system flue gas flow from the Panel Mate.
7. A Δp transmitter and absolute pressure transmitter were installed on new inlet venturi and programmed into the PLC, DAS and Panel Mate.
8. A standpipe was added to the sonic level sensor in the slurry mixing tank because turbulence from the mixer caused false readings.
9. A Δp transmitter was added to the spray lance system to monitor difference in lance air pressure during two stage injection operation.
10. Heaters were added to outdoor control panels to keep the controls dry and unfrozen. These included the A/C Quad III, the A/C motor starter, and the burner control panel.
11. Ammeters were installed on all chain conveyor MCC circuit breakers to monitor chain loading.
12. The steam humidity control scheme was reprogrammed with a permissive from the burner flame-on circuit. This was done so that the steam injection would stop if the burner tripped. The problem was that the steam would condense in the bottom of the burner and cause water damage to the flame scanners and fuel injector.
13. A new equipment rack was added to the DAS to house additional equipment brought in by SRI. Additional wiring was added to the PLC and DAS for a strip chart recorder, a water vapor analyzer, and a new O_2 analyzer.
14. Two new pages were created on the Panel Mate for the convenience of the operator. These pages were titled, "Lime Slurry Injection System Monitor" and "Dry Sorbent Injection System Monitor" and contained all the necessary readouts required by the operator to conduct any given test without constantly changing pages to look for information or change setpoints.
15. An opacity monitor brought on-site from Meridosia was installed on the flue gas outlet duct.
16. A guard was installed around the emergency stop pushbutton to keep it from being accidentally activated.
17. When additional soot blowers were added, an existing unreliable control panel was abandoned in favor of an eight solenoid valve array which is now controlled by the PLC. The sequencing of each of the eight solenoid valves is operated by the PLC which allows for control of the number of puffs, duration of each puff, and the time interval between cycles.
18. A 75 hp motor starter was added to MCC1 to replace the broken variable speed drive used for the dilution fan.
19. An emergency stop push-button switch was added to the lime slaker control system to shut down the unit in case of an emergency.

20. The in-line delumper was wired to the spare circuit breaker on MCC₂ and the control block for it was added to the Panel Mate and PLC.
21. A vibrator was installed and wired on the recycle ash feed chutes to the mixing tank.
22. An air powered exhaustor unit was installed in the slurry mixing tank vent tube to exhaust the dust and steam from the tank outside the building. The steam rising from the slurry caused the recycle ash to plug the chutes and weigh decks.
23. Wiring and programming changes were made to the DAS so that the slurry make-up flow from the holding tank to the mixing tank could be monitored.
24. A programming change was made so that slurry flow could be controlled by the outlet SO₂ concentration from Port No. 5 called "ESP Outlet Control Mode" and function blocks were added to the Panel Mate to operate the system.

6.1.3 Process Control System Operational Testing

In order to evaluate the response of the process control systems to anticipated normal variations in process conditions in a larger scale commercial application (i.e., boiler load), a series of tests were run to demonstrate the capabilities of a proposed control system. Test conditions were selected to simulate boiler load changes and the DITF process control system was reconfigured from its normal testing mode to function as a back feed control system to control the system outlet SO₂ concentration with slurry or slurry/recycle ash injection.

6.1.3.1 Test Conditions

The following conditions were selected to simulate boiler load change:

Conditions	1	2	3
Load, MW	600	450	300
Percent Load	100	75	50
*Gas Flow, acfm	50,000	37,500	25,000
*Inlet Temp., °F	320	300	280
*Inlet SO ₂ , ppm	2,000	1,500	1,000
**Outlet SO ₂ , ppm	800	600	400
*Steam Flow rate, lbs/hr	2,900	2,500	1,900
Inlet % H ₂ O	8.8	7.7	6.9
*Dilution Air Flow, scfm	12,500	13,000	11,500
Adiabatic Sat. Temp. (calculated)	131	126	124
Approach to Sat., °F	45	45	45
**ESP Inlet Temp., °F	176	171	169
*Preset by the operator.			
**Controlled by the PLC slurry back feed control and humidification cascade mode.			

6.1.3.2 System Modifications

In order to demonstrate the response of process control systems to process variations, the gas analysis system, the PLC and the panel mate had to be modified as follows:

SRI arranged the tubing for sample Port Nos. 1 and 5 so that Port 5 was connected to the single point analyzer. This was necessary because Port 5 is the outlet of the ESP sample. Ports 1 and 5 were the only ones sampled and recorded for this mode of testing.

Since Port No. 5 was connected where Port No. 1 had been, the ESP outlet SO₂ concentration value appeared on Panel Mate Page No. 8 in the flue gas SO₂ concentration control block. The output of the flue gas SO₂ control PID block (PID-10), was then rerouted via program changes to the input of the lime slurry nozzle flow control (PID-9). Program changes were then made to the start/stop control to the lime slurry nozzle flow control block found on Panel Mate Page No. 6. This new cascade function enabled the flue gas SO₂ control PID loop to write the needed slurry flow setpoints into the lime slurry nozzle flow PID block.

During initial testing, it was found that the gas analysis system sampling sequence was not adequate for this use. The problem was that the existing sequence sampled each port for only 130 seconds, while the time required for the output concentration of SO₂ at Port No. 5 to change with a given setpoint variance was at least 3 minutes. Because Port No. 5 was being purged so often the flue gas SO₂ control PID could never see a stable concentration value and so could not reach a stable setpoint value. This problem was solved by programming a new sampling sequence into the PLC and Panel Mate programs. The new sampling sequence operated only Port Nos. 1 and 5 and left the other ports closed. The new sequence alternately sampled Ports 1 and 5 every 130 seconds as before, but only purged them every 60 minutes. The purge sequence also purged both Ports 1 and 5 at the same time allowing even more actual on-line sampling stability for both ports. The programming for this new sample sequence kept all the existing programming in place for ease of returning to the normal sampling mode when needed.

Once the flue gas SO₂ control PID output and Port No. 1 had been revised, the dilution air flow which controls inlet SO₂ concentration had to be set manually. A spare controller borrowed from the Meredosia trailer was connected to the output of the multipoint SO₂ analyzer and mounted where the operator could see its display easily. This controller was used to monitor the inlet SO₂ concentration at Port No. 1 so that the dilution air flow control could be set at the necessary level to control the desired inlet concentration.

The control system functioned well, from the standpoint of tuning the PID loops. An improvement in the overall performance of the system could be realized if there was feed-forward function added from the inlet concentration control to the outlet concentration control to smooth out the effects of minor input SO₂ concentration fluctuation. This is again related to the time lag between the time the SO₂ concentration PID loop writes a new setpoint and it is seen by the ESP outlet sample port.

6.1.3.3 Testing

During the period of Dec. 2 to Dec. 12, 1991, the gas analysis system, the PLC, and Panel Mate were modified and the boiler load change testing was completed using both the 12 GPM single Lechler

nozzle and the six small Lechler nozzle array. Plots of the data generated in this test are included in this section.

1. Testing Using The Single Lechler Nozzle:

- **Slurry Injection Only, No Dilution Water**

Initially, the full load test condition was maintained. The slurry back feed control controlled the outlet SO_2 at the desired value of 800 ppm without any problem at ESP inlet temperature of 180°F , and Ca/S of about 2.0. The overall SO_2 removal efficiency was about 56% after correcting for O_2 concentration. After 3 hours of continuous run, condition number 2 was established at 1206 by resetting the gas flow rate to 37,500 and adjusting the dilution air and the steam flow rates to maintain the desired inlet SO_2 and % H_2O , while continuing to inject slurry to control the outlet SO_2 concentration to the new desired value of 600 ppm. This condition was maintained for 3 hours before switching at 1500 to the final condition at gas flow rate of 25,000 acfm. The total duration period for the 3 conditions was 9 hours. The slurry back feed control system worked very nicely and the system stabilized within 15 minutes from the time the test condition has been changed without any major upset to the duct condition, build up. See Figures 6-2 and 6-3, dated 12/6/91.

- **Slurry Injection With Dilution Water**

The three previous conditions were carried out using the same procedure described before except the ESP inlet temperature was controlled at the desired value using the PLC humidification cascade mode while the slurry back feed control controlled the outlet SO_2 concentration. The whole control system behaved nicely at full load condition of 50,000 acfm. However, at the other two conditions, the ESP inlet temperature fluctuated within ± 8 degrees due to the small dilution water flow rate required which the control valve was unable to maintain constantly. Duct deposit was very significant. See Figure 6-4, dated 12/9/91.

- **Slurry/Recycle Ash Injection**

Only one test condition at full load was performed with slurry/recycle ash injection for a period of 4 hours. The recycle ratio was 2.0 with overall Ca/S ratio of 1.4. The control system did not perform very well because of the large fluctuation in slurry loop back pressure. This fluctuation was attributed to the removal of the strainers from the suction side of the pump on the assumption that the large nozzle will not plug by the large particle in the slurry/ash mix. This test was done late in the second shift and no attempt was made to solve this problem. See Figure 6-5, dated 12/11/91.

2. Testing Using the Six Lechler Nozzle Array

The three previous test conditions at 100, 75, and 50% load were repeated the same way using the six Lechler nozzle array with slurry injection only without dilution water. Similar results were obtained including ESP inlet temperature, Ca/S ratio, overall SO_2 efficiency and duct conditions. See Figures 6-6 and 6-7, dated 12/12/92.

6.1.3.4 Conclusion

The DITF PLC system has demonstrated an acceptable capability of controlling normal process variation. Its response to the process variation was outstanding, considering the fact that the system is designed to control a test facility and not a full-scale commercial system. The plotted data presented in Figures 6-2 through 6-7 indicate an approximate 100 ppm shift in outlet SO₂ concentration from the control point of the PLC. This unexplained phenomenon in no way detracts from the fact that the concept can successfully control to a fixed SO₂ concentration. These tests demonstrate that the basic philosophy of outlet SO₂ control will be a feasible and effective way to control Duct Injection in a full scale application.

6.2 Failure Modes - Task 3.5

The contract scope of work for "Subtask 3.5 - Evaluation of Failure Modes" calls for tests to be conducted to simulate equipment or system failures, and strategies be demonstrated to avoid or recover from these failures. Tests were to simulate boiler trip, control system loss of power, excessive duct deposits, sub-dewpoint operation, excessive ESP plate/wire deposits, excessive nozzle pluggage, reagent preparation and delivery equipment failures, loss of atomizing air, excessive particulate emissions, high air infiltration, and ash handling system pluggage.

During the two year testing period no specific tests were conducted solely to demonstrate failure modes. As a matter of normal activities however ample opportunity was realized during normal operation of the DITF to deal with failure modes.

The DITF was designed as a test facility and not as a commercial SO₂ removal system attached to an industrial or utility facility with usual levels of equipment redundancy for uninterrupted operation. As such, the design default for major equipment malfunction at the DITF was shut down of the SO₂ removal system. In the course of normal operation the following major equipment failures occurred which in turn led to DITF system shutdown.

1. Ash handling system malfunctions.
2. Significant duct deposits.
3. ESP hoppers high level tripped ESP transformers.
4. Nozzle pluggage.
5. Merrick weigh belt feeder malfunction (during slurry recycle testing).
6. Failure of the dilution air system burner flame detector.
7. Air compressor failure, loss of atomizing air.
8. Lime slaker system.
9. Incomplete slurry/recycle mixing.

Figure 6-2. Removal of SO₂ as a function of time on December 6, 1991.

Figure 6-3. Concentration of SO₂ at the DITF inlet and ESP outlet as a function of time on December 6, 1991.

Figure 6-4. Ca/S ratio, removal of SO₂, and approach to saturation as a function of time on December 9, 1991.

Figure 6-5. Removal of SO₂ as a function of time on December 11, 1991.

Figure 6-6. Removal of SO₂ as a function of time on December 12, 1991.

Figure 6-7. Concentration of SO₂ at the DITF inlet and ESP outlet as a function of time on December 12, 1991.

In a commercially viable system, complete shutdown of the SO₂ removal facility for the above reasons is not acceptable. In order to accommodate the failure modes referred to above the following recommendations should be considered for system designs.

- a. Utilize duct wall temperature detection systems for dewpoint approach alarm. Wet conditions in the duct almost always result in serious duct deposits.
- b. Provide redundancy in ash handling, compressed air, lime slaking, lime handling systems (i.e., 2-100% or 3-50% capacity components).
- c. Provide redundancy in the spray nozzle system, on-line cleaning system for nozzles, flow monitoring, pressure-drop measurement, and control to individual or groupings of nozzles to maintain availability of these critical components.
- d. Provide flexibility in nozzle placement in the duct with capability to aim the nozzles away from walls where necessary to prevent impingement of spray on the walls. This will provide a means to reduce wall deposition.

In general good engineering practice and currently available technology applied to the design of a commercial installation should accommodate most problems that are anticipated without further development necessary.

6.3. Leaching Tests on Duct Injection Ash

To evaluate the suitability of duct injection ash for landfill disposal a sample of the ash was subjected to the Toxicity Characteristic Leaching Procedure (TCLP). The TCLP is described in the Code of Federal Regulations (40CFR261, Appendix 2, Method 1311) and in the Environmental Protection Agency (EPA) publication "Test Methods for Evaluating Solid Waste," EPA Publication No. SW-846. In the TCLP procedure 100 g of the ash sample is extracted with 2 L of a buffered acetic acid solution for 18 hours. The extract is then filtered and analyzed for various metals and organic constituents using the methods specified in the EPA publication cited above. The TCLP procedure is designed to simulate the leaching that occurs in a landfill when mildly acidic rain water and leachates migrate through the waste material. In the full TCLP procedure the extract is analyzed for eight metals and 31 organic constituents. For the tests of the duct injection ash we omitted the organic analyses, since there was no reason to suspect that a duct injection process would contribute organic constituents to the ash. The extract was analyzed only for the eight metals: arsenic, barium, cadmium, chromium, lead, mercury, selenium, and silver.

To allow a comparison of the duct injection ash to conventional fly ash, the TCLP procedure was also applied to a sample of base line fly ash. The base line ash sample was obtained from the hoppers of the full-scale electrostatic precipitator (ESP) that treats the gas from Unit 5 of the Muskingum River Plant. The duct injection ash was obtained from the hoppers of the pilot-scale ESP that treats the 12-MW slip stream withdrawn from the Unit 5 ducting ahead of the full-scale ESP. The base line ash sample was collected on March 4, 1992, and the duct injection ash sample was collected during Test Weeks 81 and 82 in late February 1992. The duct injection ash was produced during a long-term test of the pilot-scale ESP with lime slurry injection at a fresh reagent ratio (calcium-to-sulfur molar ratio) of 1:1. Ash recycle was used to increase the overall reagent ratio to 1.4:1, resulting in

55% removal of SO₂ at a flue gas temperature that was 40°F above adiabatic saturation. These conditions represent a reasonable operating point for a commercial duct injection process.

The effect of duct injection process conditions on the leaching of the ash is beyond the scope of this study. The University of North Dakota Energy and Environmental Research Center (UNDEERC) has studied the leaching of duct injection ash produced under various process conditions. Their studies have also examined the physical properties, strength, and permeability of duct injection ash, which are additional parameters that must be included in an evaluation of the suitability of duct injection ash for disposal in a landfill. The results of the UNDEERC studies will be published in the "Duct Injection Design Handbook" to be prepared by United Engineers and Constructors (UEC) under Department of Energy (DOE) Contract No. DE-AC22-88PC88852. Publication of the handbook is planned for November 1992. Several other studies of duct injection ash are being conducted under the auspices of the Ohio Coal Development Office (OCDO). These studies are ongoing, and reports are not yet available on their results. Information on these studies may be obtained by contacting the OCDO in Columbus, Ohio.

Table 6-1 compares the TCLP leachate compositions produced from the sample of duct injection ash and from the sample of base line ash described above. The table also includes the regulatory limits specified in the Resource Conservation and Recovery Act (RCRA). These limits serve as the basis for determining when a waste is toxic by virtue of the metals that can be leached from the waste. If the regulatory limit for any of the eight metals is exceeded, the waste is classified as hazardous and is subject to stringent rules for handling and disposal. The metals concentrations in the leachate from the base line ash sample and in the leachate from the duct injection ash sample are well below the regulatory limits. For all eight metals the concentrations in the leachates are at least a factor of 15 below the corresponding regulatory limits. In the base line leachate four of the metals (selenium, barium, silver, and mercury) are present at levels too low to detect by the specified analytical procedures. In the duct injection leachate three of the same metals (selenium, barium, and mercury) are present at levels below the detection limit. In both leachates the concentration of hexavalent chromium, the toxic form of chromium, is below the detection limit. In summary, the TCLP results suggest that neither the baseline ash nor the duct injection ash could be classified as hazardous by virtue of their content of leachable metals. Additional testing would be required to precisely define the requirements for handling and disposal of duct injection ash, but the results of the leaching tests do not suggest any potential problems with disposal in utility landfills.

Table 6-1. Results of TCLP Leaching Tests on Base Line and Duct Injection Ash Samples

Metal	Concentration of Metal in TCLP Leachate, mg/L		
	Base Line Ash	Duct Injection Ash	Regulatory Limit
Arsenic	0.309	0.254	5.0
Barium	<1.0	<1.0	100.0
Cadmium	0.03	0.03	1.0
Chromium (total)	0.19	0.07	5.0
Chromium (hexavalent)	<0.02	<0.02	5.0
Lead	0.03	0.02	5.0
Mercury	<0.005	<0.005	0.2
Selenium	<0.005	<0.005	1.0
Silver	<0.02	0.11	5.0

7.0 MAJOR OPERATIONS AND MAINTENANCE EXPERIENCE

The DITF was staffed to operate continuously, five days per week in three shifts. When required, seven-day-a-week operation was accommodated by the use of overtime. Much of this test series, System Characterization, entailed short term (i.e., 2- to 4-hour) parametric tests. A two shift mode of operation was used for this type of testing with the facility shut down from 12 to 6 A.M. This allowed access to the duct for inspection and cleaning, if necessary.

7.1 Major Milestones of Operations

April 25, 1990 -- Hot flue gas sent through the duct and baseline ESP testing begun.

May 3, 1990 -- Nozzle testing with water begun.

June 1, 1990 -- Construction complete with the flue gas dilution system turned over to the operations staff.

June 20, 1990 -- Dry hydrated lime testing begun.

August 21, 1990 -- Reagent lime slurry testing begun.

August 22, 1990 -- Ohio Power Company outage started.

November 19, 1990 -- Ohio Power Company outage ended.

February 1, 1991 -- Task 3.1 Evaluation of System Performance ended.

February 28, 1992 - Testing Completed

Total Test Hours

Nozzle Testing (Water)	80 hours
Dry Hydrated Lime Testing	471 hours
Reagent lime Slurry Testing	1095 hours
Slurry/Recycle Testing	240 hours
Single Nozzle Testing (12 GPM)	58 hours

7.2 Hydrated Lime and Slurry Preparatory Systems

During initial operation of the hydrated lime system, hydrated lime leaks were observed inside the hydrated lime building. The leaks were fixed by welding a plate beneath the belt feeder and repiping the vent system from the ends of the rotary airlock to the chute above the airlock. The belt feeder redundant slide gates were also removed since they were a source of leakage. A maximum of 1800

lbs/hr on hydrated lime, and 2000 lbs/hr of recycle have been delivered with no problems. Occasionally, the belt enclosure had to be opened and cleaned. The inlet filters for the injection blower tended to get dirtier than expected and were relocated outside the hydrated lime building. In general, the system performed well. The accuracy of the feeding system was confirmed by independent sampling.

The slurry was prepared by mixing Mid Ohio pebble lime with water at a ratio of 1:4 in a detention slaker. There is some difficulty in preparing slurry with a specified solids content since the pebble lime feeder is a volumetric type feeder. The feed rate is estimated based on the feeder speed (RPM) and it is influenced by the bulk density and silo level. A weigh belt feeder is recommended for future installations. However, the slaker seemed to maintain a solids concentration fairly well. Frequent analyses of the slurry were performed during testing. Over all of the tests that are listed in Table 4-4 or in Appendixes B through E (slurry tests) the solids content of the reagent slurry averaged 21.81% $\pm$ 1.81% and the percentage of Ca(OH)_2 averaged 20.40% $\pm$ 1.63%.

7.3 Dry and Slurry Sorbent Injection System

Humidification water for dry injection or slurry sorbent injection was added through two spray lances mounted in the flue gas duct. Each lance is connected to three dual-fluid spray nozzles. The two spray lances are attached to flange connections which are slotted to allow rotation of the lance. Initial nozzle testing showed that the ability to rotate the lance and to aim the nozzles greatly reduced low thermocouple readings, an indication of wall wetting, on the duct walls. Figure 7-1 shows the location of the nozzles in the duct. During testing, the top lance was pointed down by 2.5 degrees and the outer nozzles were pointed in by 5.0 degrees. The majority of the testing was performed at the first horizontal test station designated Test Station 2.

The lances were constructed from Hastelloy to protect against corrosion from the flue gas. There was no indication of corrosion on the lances or nozzles during the testing.

7.3.1 Dry Injection System

The dry duct injection nozzle is a single nozzle which directs the air and solids mixture into the duct. A 4-inch beveled pipe injects the dry sorbent into the center of the duct approximately 2.5 feet upstream of the spray humidification nozzles.

The system ran well after the hydrated lime leakage problem was eliminated. However, because of concerns about good lime mixing, the injection nozzle was extended so that the injection point was in the same plane as the humidification nozzles (Figure 7-2). Co-planar injection improved utilization and reduced stratification, but duct deposits were still a major problem.

7.3.2 Slurry Injection System

An array of six Lechler nozzles was used for the majority of the slurry testing. The internal-mix Lechler nozzles are designed with erosion-resistant silicon-carbide inserts. There was no detectable wear on these inserts after almost 1100 hours of slurry testing and 240 hours of recycle slurry testing.

In general, the slurry injection system operated adequately resulting in insignificant duct deposits under normal operating conditions of 25 to 45°F approach temperatures. Occasionally, the nozzle

LOCATION OF NOZZLES

Figure 7-1. Location of nozzles in small Lechler nozzle array in the horizontal test duct at the DITF.

Figure 7-2. Schematic diagram of the installation of the coplanar dry injection nozzle in the horizontal test duct at the DTF.

air passages became plugged, usually as a result of an air compressor failure. This resulted in significant duct deposits. The nozzles were cleaned in a dilute HCl solution, reinstalled in the duct, and again functioned properly.

The key to maintaining nozzle performance was keeping the nozzles clean by adequate flushing when shutting down, plus periodic inspection. Care has to be taken when cleaning the nozzle inserts. These were damaged at times during removal for cleaning.

A major problem with slurry injection at the DITF occurs when dilute slurries are used (i.e., with less than 20% solids). When dilute slurries are injected, significant deposits occur even at moderate approach temperatures. Duct deposits are minimized only when using concentrated slurries (20% solids or more). Extended tests of up to 120 hours and approaches as close as 25°F were run with concentrated slurries without significant deposits. Extended tests with recycle ash and slurry mixtures were not possible due to recycle/slurry mixing problems discussed in Section 7.7.

In general, for similar test conditions, duct deposits appeared to be less significant with slurry injection than with dry injection. Co-planar dry injection did not improve this performance.

7.4 Duct Cleaning System

The duct cleaning system consists of a sonic horn, three soot blowers, and duct hoppers 10 to 18 feet downstream of the slurry injection points. Since dry deposits are seldom found on the roof or sides of the duct, the need for or effect of the sonic horn is not clear.

The soot blowers appeared to function efficiently only when the duct deposits were dry. Since duct deposits begin on the far end lip of the duct hopper, one of the soot blowers, which were located upstream of the duct hopper, was relocated downstream of the duct hopper blowing against the gas flow. This appeared to hinder the formation of dust deposits on the hopper lip. An additional five soot blowers were installed between the duct hoppers to attempt to minimize duct deposits occurring in this area. (See Figure 7-3)

Deposits can be controlled by these systems at conditions that minimize deposition. However, under conditions which promote depositions, these systems do not control solids buildup in the duct. On these occasions, the DITF must eventually be shut down and cleaned out.

7.5 ESP Mechanical Performance

In general, the ESP mechanically performed very well for approach to saturation temperatures ranging from 50 to 25°F. On one occasion, the collection efficiency degraded at the end of an extended test. An inspection of the ESP revealed that the seals had become detached, resulting in a heavy coating of ash in the penthouse. Further inspection also revealed that large pieces of deposits had formed a bridge between some of the corona support frames and the collection plates. When the penthouse was cleaned, seals repaired, and deposits removed, the ESP collection efficiency returned to normal.

Figure 7-3. Location of soot blowers in the horizontal test duct at the DITF.

7.6 Ash Collection System

This system consists of four drag chain conveyors and rotary air locks. In general, the system performed poorly. On several occasions, the collecting conveyor plugged during unloading of the duct hoppers because of the wet fly ash/sorbent mixture. The major problem with the ash collection system is unloading the duct hoppers continuously. The fly ash/sorbent mixture collected in the hoppers is lumpy and the rotary airlocks cannot break it up.

7.7 Recycle/Slurry Mixing

The recycle/slurry testing was initially postponed because of recycle/slurry mixing problems. The mix appears to agglomerate and cause the strainers (located upstream the Moyno pump) to clog in less than a minute. It was also found that the recycled material contains some particles larger than the 1/8 in. opening in the strainers. A short test was done with the strainers located downstream of the pump. The preliminary results indicated that the Moyno pump was capable of deagglomerating the mix, but the strainers still clogged every 20 minutes, because of the presence of large particles in the recycled material. It was not practical to run long tests under these conditions. To eliminate this problem a pipeline delumper was installed. The delumper cutter teeth attached to a single rotor work the stream and chop large chunks. This device required no maintenance other than cleaning. However, the strainers still needed to be shifted to the clean side every 20 to 60 minutes. The delumper is not the ultimate solution for this mixing problem but it allowed the DITF to operate in the recycle mode.

8.0 REFERENCES

1. Felix, L. G., E. B. Dismukes, J. P. Gooch, M. G. Klett, and A. G. Demian, Scaleup Tests and Supporting Research for the Development of Duct Injection Technology, Topical Report No. 2, Task 3.1: Evaluation of System Performance. U.S. DOE, Pittsburgh Energy Technology Center, Contract DE-AC22-88PC88851, April 20, 1992.
2. Durham, M. D., Ebner, T. G., Holstein, D. B., Fundamental Investigation of Duct/ESP Phenomena, Topical Reports 4 and 5 - 1.7 MW Pilot ESP Testing, Results, and Upgrade Strategies, U.S. DOE, Pittsburgh Energy Technology Center, Contract AC22-99PC88850, U. S. DOE Report No. DOE/PC/88850-T4, DE91013468, March 7, 1991.
3. Marchant, G. H. Jr., J.P. Gooch, and M. G. Faulkner, Effects of E-SO_x Technology on ESP Performance", presented at the Eighth Symposium on the Transfer and Utilization of Particulate Control Technology, San Diego, CA, March 20-23, 1990.
4. Faulkner, M. G., and DuBard, J. L. A Mathematical Model of Electrostatic Precipitation (Revision 3). EPA-600/7-84-069a,b,c. (Volume I, Modeling and Programming: NTIS PB84-212-679; Volume II, User's Manual: NTIS PB84-212-687; FORTRAN Source Code Tape: NTIS PB84-232-990). U. S. Environmental Protection Agency, Research Triangle Park, North Carolina. 1984.
5. Faulkner, M. G., DuBard, J. L., and Hovis, L. S. "A Self-Consistent Deutschian ESP Model," presented at the Seventh Symposium on the Transfer and Utilization of Particulate Control Technology, Nashville, Tennessee, March 22-25, 1988.
6. Holstien, D. B., Rugg, and D. E., Durham, M. D. "Development of an ESP Model for Dry Scrubbing Applications, " Paper 4A-1, presented at the Ninth Particulate Control Symposium, Williamsburg, VA, October 15-18, 1991.

APPENDIX A

Heat Balance Calculations for Tests with Dry Sorbent Injection

Table A-1. Heat Balance Calculations for Dry Sorbent Tests.

TEST:		43-DS-01	43-DS-01	43-DS-02	43-DS-03	43-DS-03
DATE:		5/14/91	5/14/91	5/15/91	5/16/91	5/16/91
TIME:		1447-1514	1535-1600	0900-1000	1003-1029	1110-1136
	Units					
Ca/S Ratio	-	2.02	1.97	1.48	1.54	1.57
Approach	(°F)	40	40	45	43	43
SO ₂ Removal						
End of Horizontal Duct	(%)	24	24	17	17	17
ESP Inlet	(%)	26	24	18	22	18
ESP Outlet	(%)	35	32	23	23	25
Gas Phase Utilization						
End of Horizontal Duct	(%)	12	12	12	11	11
ESP Inlet	(%)	13	12	12	14	12
ESP Outlet	(%)	17	16	15	15	16
GAS IN						
Flue Gas Flow	(acfm)	49840	49800	49875	49903	49882
Flue Gas Temperature	(°F)	299	300	299	300	300
SO ₂	(ppm)	1964	1995	2004	1999	2002
O ₂	(%)	10.9	10.9	10.8	10.7	10.7
CO ₂	(%)	8.1	8.3	8.4	8.4	8.4
H ₂ O	(%)	7.9	7.8	7.9	8.0	7.9
SORBENT/AIR IN						
Dry Sorbent Feed Rate	(lb/h)	1554	1536	1165	1203	1231
% Available Lime	(%)	94.20	94.20	94.20	94.20	94.20
Air In Flow	(scfm)	1269	1272	1302	1320	1309
HUMIDIFICATION WATER						
Humid Water/Air Temperature	(°F)	83	86	64	70	76
Measured Flow	(gpm)	9.4	9.1	9.0	9.2	9.3
END OF HORIZONTAL DUCT						
SO ₂ at Inlet O ₂	(ppm)	1489	1511	1660	1654	1666
ESP INLET						
SO ₂	(ppm)	1369	1439	1547	1470	1531
O ₂	(%)	11.5	11.3	11.4	11.3	11.3
CO ₂	(%)	7.7	7.8	7.9	7.8	8.0
H ₂ O	(%)	11.2	11.2	11.2	11.0	11.3
Flue Gas Temperature	(°F)	167	167	172	170	170
Adiabatic Saturation Temperature	(°F)	127	127	127	127	127
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	1275	1347	1551	1543	1501
Flue Gas Temperature	(°F)	177	179	192	193	183
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	36603.5	36712.0	36665.6	36817.1	36798.2
Ash In	(KCal/min)	195.6	199.3	199.6	200.1	200.4
Air In	(KCal/min)	29.1	43.7	-61.2	-32.4	-3.5
Dry Sorbent In	(KCal/min)	11.3	16.7	-17.3	-9.3	-1.1
Reaction	(KCal/min)	684.9	648.5	480.4	591.3	495.7
ENTHALPY OUT						
Heated Air	(KCal/min)	514.4	515.7	555.3	552.7	548.3
Heated Dry Sorbent	(KCal/min)	245.0	244.3	216.1	216.1	219.2
Vaporization and Heating	(KCal/min)	21575.8	21038.6	20589.2	20966.5	21393.6
Flue Gas	(KCal/min)	14682.8	14658.5	15496.2	15193.6	15185.9
TOTAL IN	(KCal/min)	37524	37620	37267	37567	37490
TOTAL OUT	(KCal/min)	37018	36457	36857	36929	37347
Difference	(KCal/min)	506	1163	410	638	143
HEAT BALANCE						
Extra Flow for Zero Heat Balance	(gpm)	0.22	0.50	0.18	0.28	0.06
Closure	(%)	-1.3	-3.1	-1.1	-1.7	-0.4
Equivalent ΔT	°F	2.8	6.5	2.3	3.5	0.8

Table A-2. Heat Balance Calculations for Dry Sorbent Tests.

TEST:		43-DS-04	43-DS-04	45-DS-01	45-DS-01	45-DS-02
DATE:		5/17/91	5/17/91	5/29/91	5/29/91	5/30/91
TIME:		1024-1049	1117-1143	1459-1525	1557-1622	1244-1309
	Units					
Ca/S Ratio	—	0.99	1.00	1.93	1.91	1.56
Approach	(°F)	44	44	45	45	47
SO ₂ Removal						
End of Horizontal Duct	(%)	11	14	23	22	17
ESP Inlet	(%)	13	14	23	22	20
ESP Outlet	(%)	17	19	31	30	25
Gas Phase Utilization						
End of Horizontal Duct	(%)	11	14	12	11	11
ESP Inlet	(%)	13	14	12	11	13
ESP Outlet	(%)	17	19	16	15	16
GAS IN						
Flue Gas Flow	(acfm)	49775	49919	49899	49938	49946
Flue Gas Temperature	(°F)	299	299	324	325	321
SO ₂	(ppm)	2003	1983	1976	1983	1988
O ₂	(%)	10.8	10.9	10.6	10.6	10.7
CO ₂	(%)	6.3	8.3	8.6	8.7	8.7
H ₂ O	(%)	8.5	8.4	8.8	8.7	9.0
SORBENT/AIR IN						
Dry Sorbent Feed Rate	(lb/h)	773	776	1436	1424	1167
% Available Lime	(%)	94.20	94.20	94.20	94.20	94.20
Air In Flow	(scfm)	1322	1319	1231	1229	1262
HUMIDIFICATION WATER						
Humid Water/Air Temperature	(°F)	74	75	89	91	85
Measured Flow	(gpm)	8.8	8.9	10.4	10.3	10.3
END OF HORIZONTAL DUCT						
SO ₂ at Inlet O ₂	(ppm)	1776	1712	1521	1551	1647
ESP INLET						
SO ₂	(ppm)	1626	1604	1415	1469	1499
O ₂	(%)	11.5	11.5	11.4	11.2	11.3
CO ₂	(%)	7.9	6.7	8.1	8.3	8.3
H ₂ O	(%)	11.7	11.6	11.7	11.7	11.9
Flue Gas Temperature	(°F)	172	172	174	174	177
Adiabatic Saturation Temperature	(°F)	128	128	129	129	130
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	1658	1610	1369	1400	1500
Flue Gas Temperature	(°F)	187	181	189	186	184
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	36412.4	36771.6	39681.9	39834.0	39393.5
Ash In	(KCal/min)	199.6	198.1	219.2	221.0	218.0
Air In	(KCal/min)	-14.4	-8.1	54.0	66.1	36.6
Dry Sorbent In	(KCal/min)	-2.7	-1.5	19.9	24.2	10.7
Reaction	(KCal/min)	344.1	371.9	576.5	554.9	513.9
ENTHALPY OUT						
Heated Air	(KCal/min)	565.6	564.3	538.2	537.5	568.7
Heated Dry Sorbent	(KCal/min)	172.2	172.0	251.1	250.1	227.7
Vaporization and Heating	(KCal/min)	20236.9	20351.5	24026.7	23810.1	23726.9
Flue Gas	(KCal/min)	15396.3	15539.6	15394.7	15389.9	15956.7
TOTAL IN	(KCal/min)	36939	37332	40551	40700	40173
TOTAL OUT	(KCal/min)	36371	36627	40211	39988	40480
Difference	(KCal/min)	568	705	341	713	-307
HEAT BALANCE						
Extra Flow for Zero Heat Balance	(gpm)	0.25	0.31	0.15	0.31	-0.13
Closure	(%)	-1.5	-1.9	-0.8	-1.8	0.8
Equivalent ΔT	°F	3.2	3.9	1.9	4.0	-1.7

Table A-3 Heat Balance Calculations for Dry Sorbent Tests.

TEST:		45-DS-02	45-DS-03	45-DS-03	46-DS-01	46-DS-02
DATE:		5/30/91	5/31/91	5/31/91	6/3/91	6/5/91
TIME:		1345-1401	1320-1356	1427-1503	1300-1500	1200-1400
	Units					
Ca/S Ratio	--	1.60	1.05	1.05	1.96	1.43
Approach	(°F)	47	38	39	24	25
SO ₂ Removal						
End of Horizontal Duct	(%)	23	17	17	33	25
ESP Inlet	(%)	22	17	16	41	33
ESP Outlet	(%)	27	20	21	47	36
Gas Phase Utilization						
End of Horizontal Duct	(%)	14	16	16	17	18
ESP Inlet	(%)	14	16	15	21	23
ESP Outlet	(%)	17	19	20	24	25
GAS IN						
Flue Gas Flow	(acfm)	49866	50897	50866	50913	50663
Flue Gas Temperature	(°F)	323	319	318	317	305
SO ₂	(ppm)	2003	2014	1993	2003	2003
O ₂	(%)	10.6	10.6	10.7	10.5	10.4
CO ₂	(%)	8.9	8.7	8.7	8.7	8.8
H ₂ O	(%)	8.9	9.7	9.3	9.0	8.1
SORBENT/AIR IN						
Dry Sorbent Feed Rate	(lb/h)	1206	809	800	1513	1125
% Available Lime	(%)	94.20	94.20	94.20	94.20	94.20
Air In Flow	(scfm)	1251	1255	1258	1247	1267
HUMIDIFICATION WATER						
Humid Water/Air Temperature	(°F)	87	83	85	76	68
Measured Flow	(gpm)	10.6	10.7	10.3	12.0	11.2
END OF HORIZONTAL DUCT						
SO ₂ at Inlet O ₂	(ppm)	1552	1676	1654	1347	1495
ESP INLET						
SO ₂	(ppm)	1477	1517	1560	1184	1333
O ₂	(%)	11.1	11.5	11.4	11.2	11.2
CO ₂	(%)	8.4	8.0	8.1	8.8	8.7
H ₂ O	(%)	12.1	13.0	12.5	12.6	11.9
Flue Gas Temperature	(°F)	177	170	170	154	153
Adiabatic Saturation Temperature	(°F)	130	132	131	130	128
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	1447	1607	1588	1052	1282
Flue Gas Temperature	(°F)	180	172	172	168	159
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	39588.5	39957.9	39802.8	39698.6	38038.2
Ash In	(KCal/min)	221.1	223.1	219.8	220.2	208.2
Air In	(KCal/min)	45.5	28.7	39.6	-4.3	-44.9
Dry Sorbent In	(KCal/min)	13.8	5.9	7.9	-1.7	-12.6
Reaction	(KCal/min)	580.6	448.2	420.9	1085.2	907.1
ENTHALPY OUT						
Heated Air	(KCal/min)	563.5	526.0	527.3	432.4	433.2
Heated Dry Sorbent	(KCal/min)	232.8	174.9	173.0	208.8	170.8
Vaporization and Heating	(KCal/min)	24511.8	24669.2	23721.2	27368.3	25467.9
Flue Gas	(KCal/min)	15901.8	15173.3	15175.3	12568.0	12522.9
TOTAL IN	(KCal/min)	40449	40664	40491	40998	39096
TOTAL OUT	(KCal/min)	41210	40543	39597	40578	38595
Difference	(KCal/min)	-760	120	894	421	501
HEAT BALANCE						
Extra Flow for Zero Heat Balance	(gpm)	-0.33	0.05	0.39	0.18	0.22
Closure	(%)	1.9	-0.3	-2.2	-1.0	-1.3
Equivalent ΔT	°F	-4.3	0.7	5.0	2.3	2.7

Table A-4. Heat Balance Calculations for Dry Sorbent Tests.

TEST:		46-DS-03	47-DS-01	47-DS-01	47-DS-02	47-DS-03
DATE:		6/5/87	6/9/87	6/10/91	6/11/91	6/12/91
TIME:		1200-1300	1000-1100	1500-1600	1100-1200	1300-1400
	Units					
Ca/S Ratio	—	0.94	1.91	2.04	1.55	1.01
Approach	(°F)	21	35	39	37	37
SO ₂ Removal						
End of Horizontal Duct	(%)	24	25	21	19	16
ESP Inlet	(%)	24	25	22	21	17
ESP Outlet	(%)	30	33	29	28	21
Gas Phase Utilization						
End of Horizontal Duct	(%)	25	13	10	13	15
ESP Inlet	(%)	26	13	11	13	17
ESP Outlet	(%)	32	17	14	18	21
GAS IN						
Flue Gas Flow	(acfm)	50464	50820	50743	50751	50744
Flue Gas Temperature	(°F)	302	300	312	310	308
SO ₂	(ppm)	1985	2022	1967.17	1998	1980
O ₂	(%)	10.5	10.4	10.4	10.6	11.1
CO ₂	(%)	8.7	8.7	8.6	8.6	8.3
H ₂ O	(%)	8.5	8.7	8.1	9.0	8.8
SORBENT/AIR IN						
Dry Sorbent Feed Rate	(lb/h)	734	1526	1568	1200	781
% Available Lime	(%)	94.20	94.20	94.20	94.20	94.20
Air In Flow	(scfm)	1234	1266	1260	1266	1262
HUMIDIFICATION WATER						
Humid Water/Air Temperature	(°F)	69	69	84	75	77
Measured Flow	(gpm)	11.0	10.2	10.2	10.2	9.7
END OF HORIZONTAL DUCT						
SO ₂ at Inlet O ₂	(ppm)	1517	1521	1557	1611	1672
ESP INLET						
SO ₂	(ppm)	1403	1419	1426	1486	1564
O ₂	(%)	11.2	11.1	11.1	11.3	11.6
CO ₂	(%)	8.8	8.7	8.6	8.7	8.3
H ₂ O	(%)	12.0	11.7	11.1	12.3	11.8
Flue Gas Temperature	(°F)	150	165	167	167	167
Adiabatic Saturation Temperature	(°F)	129	130	128	130	130
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	1394	1354	1399	1435	1565
Flue Gas Temperature	(°F)	159	176	170	171	169
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	37537.5	37572.2	38908.4	38736.0	38440.9
Ash In	(KCal/min)	202.8	206.1	211.1	212.5	208.8
Air In	(KCal/min)	-38.3	-42.6	31.6	-10.8	-0.1
Dry Sorbent In	(KCal/min)	-7.2	-16.3	12.4	-3.2	0.0
Reaction	(KCal/min)	644.4	687.2	589.0	554.1	445.6
ENTHALPY OUT						
Heated Air	(KCal/min)	405.3	500.1	510.9	513.2	511.5
Heated Dry Sorbent	(KCal/min)	129.3	239.9	248.0	210.1	164.7
Vaporization and Heating	(KCal/min)	25012.7	23195.5	23493.8	23317.2	22341.0
Flue Gas	(KCal/min)	12028.5	14626.0	14726.8	14788.9	14806.7
TOTAL IN	(KCal/min)	38339	38407	39752	39489	39095
TOTAL OUT	(KCal/min)	37576	38561	38980	38829	37824
Difference	(KCal/min)	763	-155	773	659	1271
HEAT BALANCE						
Extra Flow for Zero Heat Balance	(gpm)	0.34	-0.07	0.34	0.29	0.55
Closure	(%)	-2.0	0.4	-1.9	-1.7	-3.3
Equivalent ΔT	°F	4.2	-0.8	4.3	3.6	7.0

Table A-5. Heat Balance Calculations for Dry Sorbent Tests.

TEST: DATE: TIME:		48-DS-01 6/18/91 1400- 1500	48-DS-02 6/19/91 1200- 1300	48-DS-03 6/20/91 1100-1200	48-DS-04 6/21/91 1200-1300
	Units				
Ca/S Ratio	—	2.03	2.06	2.02	2.04
Approach	(°F)	44	45	37	35
SO ₂ Removal					
End of Horizontal Duct	(%)	20	20	25	24
ESP Inlet	(%)	21	21	27	25
ESP Outlet	(%)	30	31	35	33
Gas Phase Utilization					
End of Horizontal Duct	(%)	10	10	13	12
ESP Inlet	(%)	10	10	13	12
ESP Outlet	(%)	15	15	18	16
GAS IN					
Flue Gas Flow	(acfm)	50971	51120	50999	50908
Flue Gas Temperature	(°F)	307	310	302	313
SO ₂	(ppm)	2006	1982	1998	2012
O ₂	(%)	10.9	11.2	11.2	11.0
CO ₂	(%)	8.8	8.5	8.5	8.5
H ₂ O	(%)	8.9	8.8	8.1	8.4
SORBENT/AIR IN					
Dry Sorbent Feed Rate	(lb/h)	1594	1596	1605	1603
% Available Lime	(%)	94.20	94.20	94.20	94.20
Air In Flow	(scfm)	1247	1246	1238	1224
HUMIDIFICATION WATER					
Humid Water/Air Temperature	(°F)	86	82	81	84
Measured Flow	(gpm)	9.7	9.2	9.9	10.1
END OF HORIZONTAL DUCT					
SO ₂ at Inlet O ₂	(ppm)	1612	1594	1492	1522
ESP INLET					
SO ₂	(ppm)	1489	1437	1381	1408
O ₂	(%)	10.3	11.8	11.7	11.6
CO ₂	(%)	8.8	8.5	8.5	8.5
H ₂ O	(%)	12.0	11.8	11.0	11.6
Flue Gas Temperature	(°F)	175	175	165	165
Adiabatic Saturation Temperature	(°F)	131	130	128	129
ESP OUTLET					
SO ₂ at Inlet O ₂	(ppm)	1412	1360	1291	1340
Flue Gas Temperature	(°F)	179	179	170	168
HEAT BALANCE CALCULATIONS					
ENTHALPY IN					
Flue Gas In	(KCal/min)	38559.5	38992.4	37884.8	39165.6
Ash In	(KCal/min)	211.5	212.4	206.2	217.5
Air In	(KCal/min)	41.0	24.1	18.5	30.9
Dry Sorbent In	(KCal/min)	16.5	9.8	7.6	12.8
Reaction	(KCal/min)	621.5	612.6	738.3	686.8
ENTHALPY OUT					
Heated Air	(KCal/min)	549.5	549.8	489.8	484.4
Heated Dry Sorbent	(KCal/min)	274.6	274.6	247.5	247.8
Vaporization and Heating	(KCal/min)	22327.5	21280.1	22703.3	23157.2
Flue Gas	(KCal/min)	16217.2	16210.9	14620.9	14405.1
TOTAL IN	(KCal/min)	39450	39851	38855	40114
TOTAL OUT	(KCal/min)	39369	38315	38062	38295
Difference	(KCal/min)	81	1536	794	1819
HEAT BALANCE					
Extra Flow for Zero Heat Balance	(gpm)	9.68	9.88	0.35	0.79
Closure	(%)	-0.2	-3.9	-2.0	-4.5
Equivalent ΔT	°F	0.4	8.4	4.3	10.0

Table A-6. Heat Balance Calculations for Dry Recycle Ash Tests.

TEST:		47-DR-01	47-DR-02	49-DR-01	49-DR-02	49-DR-03
DATE:		6/13/91	6/14/91	6/26/91	6/27/91	6/28/91
TIME:		2000-2100	1100-1200	1513-1600	1500-1700	1400-1500
	Units					
Ca/S Ratio	—	1.18	1.14	1.05	1.18	1.09
Approach	(°F)	46	36	46	46	36
SO ₂ Removal						
End of Horizontal Duct	(%)	19	22	11	11	14
ESP Inlet	(%)	20	24	12	12	16
ESP Outlet	(%)	26	30	14	14	21
Gas Phase Utilization						
End of Horizontal Duct	(%)	16	19	11	10	14
ESP Inlet	(%)	17	21	12	10	16
ESP Outlet	(%)	22	26	13	13	21
GAS IN						
Flue Gas Flow	(acfm)	50706	50867	50966	50694	50661
Flue Gas Temperature	(°F)	308	305	309	309	307
SO ₂	(ppm)	1922	1983	1989	1971	1998
O ₂	(%)	11.2	11.2	11.0	11.0	11.0
CO ₂	(%)	8.4	8.3	8.6	8.4	8.7
H ₂ O	(%)	8.3	8.6	8.4	8.6	8.6
SORBENT/AIR IN						
Dry Recycle Ash Feed Rate	(lb/h)	2381	2402	1478	1633	1523
% Available Lime	(%)	35.00	35.00	52.31	52.31	52.31
Air in Flow	(scfm)	1268	1253	1239	1236	1224
HUMIDIFICATION WATER						
Humid. Water/Air Temperature	(°F)	86	72	99	103	97
Measured Flow	(gpm)	8.8	9.5	9.2	9.3	10.4
END OF HORIZONTAL DUCT						
SO ₂ at Inlet O ₂	(ppm)	1558	1544	1766	1754	1718
ESP INLET						
SO ₂	(ppm)	1468	1412	1646	1641	1594
O ₂	(%)	11.7	11.8	11.6	11.6	11.5
CO ₂	(%)	8.4	8.3	8.5	8.4	8.6
H ₂ O	(%)	11.2	11.7	11.0	12.0	12.6
Flue Gas Temperature	(°F)	175	165	175	175	165
Adiabatic Saturation	(°F)	129	129	129	129	129
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	1423	1397	1714	1686	1586
Flue Gas Temperature	(°F)	178	171	179	177	170
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	38387.8	38151.0	38699.8	38529.1	38352.7
Ash In	(KCal/min)	202.6	207.0	211.3	208.6	209.9
Air In	(KCal/min)	44.3	-24.2	104.4	122.1	92.6
Dry Sorbent In	(KCal/min)	26.3	-14.6	39.3	50.9	36.4
Reaction	(KCal/min)	520.2	642.9	358.9	335.3	466.6
ENTHALPY OUT						
Heated Air	(KCal/min)	559.7	495.4	546.8	545.2	484.4
Heated Dry Sorbent	(KCal/min)	362.2	329.8	260.9	277.0	238.3
Vaporization and Heating	(KCal/min)	20352.7	21767.7	21451.2	21603.0	23981.7
Flue Gas	(KCal/min)	16098.5	14531.7	16172.5	16054.7	14439.2
TOTAL IN	(KCal/min)	39181	38962	39414	39246	39158
TOTAL OUT	(KCal/min)	37373	37125	38431	38480	39144
Difference	(KCal/min)	1808	1837	982	766	14
HEAT BALANCE						
Extra Flow for Heat Balance	(gpm)	0.8	0.8	0.4	0.3	0.0
Closure	(%)	-4.6	-4.7	-2.5	-2.0	0.0
Equivalent ΔT	°F	9.9	10.0	5.4	4.2	0.1

Table A-7. Heat Balance Calculations for Dry Sorbent/Recycle Ash Tests.

TEST:		50-DSR-01	50-DSR-02	50-DSR-02	50-DSR-03
DATE:		7/1/91	7/2/91	7/2/91	7/3/91
TIME:		1300 - 1500	1300 - 1400	1433 - 1533	1200 - 1300
	Units				
Ca/S Ratio Overall	--	2.03	1.17	2.04	2.09
Ca/S Ratio from Hydrate	--	0.85	0.0	0.85	0.85
Approach	(°F)	36	25	25	27
SO ₂ Removal					
End of Horizontal Duct	(%)	29	25	36	35
ESP Inlet	(%)	31	26	38	37
ESP Outlet	(%)	40	32	49	48
Gas Phase Utilization					
End of Horizontal Duct	(%)	14	22	18	17
ESP Inlet	(%)	15	23	19	18
ESP Outlet	(%)	20	28	24	23
GAS IN					
Flue Gas Flow	(acfm)	50747	50663	50616	50642
Flue Gas Temperature	(°F)	310	308	307	309
SO ₂	(ppm)	2020	2001	1999	2022
O ₂	(%)	11.0	11.0	10.9	10.9
CO ₂	(%)	8.7	8.6	8.6	8.7
H ₂ O	(%)	8.6	9.0	9.0	9.0
SORBENT/AIR IN					
Dry Sorbent Feed Rate	(lb/h)	675	0	666	714
% Available Lime	(%)	94.20	94.20	94.20	94.20
Dry Recycle Ash Feed Rate	(lb/h)	1662	1630	1655	1662
% Available Lime	(%)	52.31	52.31	52.31	52.31
Air In Flow	(scfm)	1223	1230	1228	1207
HUMIDIFICATION WATER					
Humid Water/Air Temperature	(°F)	93	89	95	87
Measured Flow	(gpm)	10.6	11.2	11.5	11.0
END OF HORIZONTAL DUCT					
SO ₂ at Inlet O ₂	(ppm)	1432	1496	1280	1305
ESP INLET					
SO ₂	(ppm)	1353	1419	1186	1216
O ₂	(%)	11.3	11.4	11.3	11.4
CO ₂	(%)	8.5	8.5	8.5	8.5
H ₂ O	(%)	12.9	13.4	13.6	13.3
Flue Gas Temperature	(°F)	165	155	155	157
Adiabatic Saturation	(°F)	129	130	130	130
ESP OUTLET					
SO ₂ at Inlet O ₂	(ppm)	1210	1356	1132	1042
Flue Gas Temperature	(°F)	168	163	161	164
ENTHALPY IN					
Flue Gas In	(KCal/min)	38755.6	38441.4	38233.9	38578.5
Ash In	(KCal/min)	215.1	210.8	209.0	214.0
Air In	(KCal/min)	71.4	53.9	82.6	45.0
Dry Sorbent In	(KCal/min)	43.1	22.6	49.4	28.0
Reaction	(KCal/min)	910.6	771.2	1115.9	1086.7
ENTHALPY OUT					
Heated Air	(KCal/min)	484.7	451.3	430.9	437.1
Heated Dry Sorbent	(KCal/min)	324.4	211.4	284.9	300.4
Vaporization and Heating	(KCal/min)	24476.4	25552.1	26540.2	25235.4
Flue Gas	(KCal/min)	14426.8	12794.0	12795.6	13177.6
TOTAL IN	(KCal/min)	39996	39500	39681	39952
TOTAL OUT	(KCal/min)	39712	39050	40052	39151
Difference	(KCal/min)	284	401	-371	802
HEAT BALANCE					
Extra Flow for Heat Balance	(gpm)	0.1	0.1	-0.2	0.3
Closure	(%)	-0.7	-1.0	0.9	-2.0
Equivalent ΔT	(°F)	1.5	2.2	-2.0	4.4

APPENDIX B

Heat Balance Calculations for Tests with Reagent Slurry Injection

Table B-1. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		33-SL-01	33-SL-02	33-SL-03	33-SL-04	33-SL-04
DATE:		3/4/91	3/5/91	3/6/91	3/7/91	3/7/91
TIME:		1245-1345	1400-1500	1630-1730	1300-1400	1615-1730
	Units					
Ca/S Ratio	--	2.21	2.25	2.01	1.93	1.93
Approach	(°F)	45	45	27	43	47
SO ₂ Removal						
End of Horizontal Duct	(%)	48	47	61	53	48
ESP Inlet	(%)	51	49	62	52	47
ESP Outlet	(%)	62	58	74	63	58
Gas Phase Utilization						
End of Horizontal Duct	(%)	22	21	30	27	25
ESP Inlet	(%)	23	22	31	27	25
ESP Outlet	(%)	28	26	37	33	30
GAS IN						
Flue Gas Flow	(acfm)	49903	49802	49852	49832	49818
Flue Gas Temperature	(°F)	305	307	308	312	310
SO ₂	(ppm)	1357	1263	1350	1870	1882
O ₂	(%)	13.6	13.9	13.9	11.1	11.2
CO ₂	(%)	6.2	5.9	6.1	8.3	8.1
H ₂ O	(%)	6.3	6.3	6.3	6.3	6.3
SLURRY/AIR IN						
Slurry Flow Rate	(gpm)	8.5	8.8	9.2	11.2	11.3
Lime Slurry Temperature	(°F)	66	80	82	65	71
Solids	(%)	23.98	21.90	20.15	22.12	22.12
Ca(OH) ₂	(%)	22.72	21.01	19.32	20.88	20.88
Density	(gm/cc)	1.1515	1.1371	1.1255	1.1399	1.1399
Air In Flow	(scfm)	1174	1161	1144	1151	1147
HUMIDIFICATION WATER						
Measured Flow	(gpm)	1.4	1.5	2.8	0.0	0.0
END OF HORIZ. DUCT						
SO ₂ at Inlet O ₂	(ppm)	700	668	526	883	975
ESP INLET						
SO ₂	(ppm)	650	634	489	878	961
O ₂	(%)	13.9	14.1	14.2	11.4	11.5
CO ₂	(%)	6.2	6.0	6.1	8.2	8.1
H ₂ O	(%)	10.3	10.1	11.1	10.9	10.9
Flue Gas Temperature	(°F)	169	169	151	167	172
Adiabatic Saturation	(°F)	124	124	124	124	124
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	521	532	351	684	798
Flue Gas Temperature	(°F)	167	169	153	167	169
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	37093.3	37201.2	37310.8	38000.9	37841.7
Ash In	(KCal/min)	139.2	130.3	139.7	196.7	197.0
Air In	(KCal/min)	-43.9	14.0	20.4	-50.9	-27.6
Slurry Solids In	(KCal/min)	-15.6	4.2	5.9	-19.7	-10.8
Reaction	(KCal/min)	933.0	830.3	1132.5	1297.5	1198.9
ENTHALPY OUT						
Heated Air	(KCal/min)	486.6	478.7	382.1	466.5	488.3
Heated Slurry Solids	(KCal/min)	185.0	171.1	137.0	226.0	239.2
Vaporization and Heating	(KCal/min)	20196.7	21462.9	25415.9	22598.8	22891.9
Flue Gas	(KCal/min)	14800.8	14623.0	11843.2	14420.7	15159.5
TOTAL IN	(KCal/min)	38101	38180	38609	39424	39199
TOTAL OUT	(KCal/min)	35669	36736	37778	37712	38779
Difference	(KCal/min)	2432	1444	831	1713	420
HEAT BALANCE						
Extra Flow for Heat Balance	(gpm)	1.1	0.6	0.4	0.8	0.2
Closure	(%)	-6.4	-3.8	-2.2	-4.3	-1.1
Equivalent ΔT	(°F)	13.8	8.2	4.7	9.7	2.4

Table B-2. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		33-SL-05	34-SL-01	34-SL-02	34-SL-03	34-SL-04	35-DSR-04
DATE:		3/8/91	3/11/91	3/12/91	3/13/91	3/14/91	3/21/91
TIME:		1515-1550	1630-1745	1500-1600	1519-1611	1200-1300	1145-1200
	Units						
Ca/S Ratio	--	2.14	2.00	2.10	1.82	1.02	1.02
Approach	(°F)	19	26	25	43	24	23
SO ₂ Removal							
End of Horizontal Duct	(%)	57	56	57	43	47	46
ESP Inlet	(%)	59	57	60	46	48	46
ESP Outlet	(%)	78	76	79	58	58	56
Gas Phase Utilization							
End of Horizontal Duct	(%)	27	28	27	24	46	45
ESP Inlet	(%)	27	28	29	25	47	46
ESP Outlet	(%)	36	38	38	32	57	55
GAS IN							
Flue Gas Flow	(acfm)	49801	49887	49868	49937	49925	49828
Flue Gas Temperature	(°F)	313	316	309	313	310	309
SO ₂	(ppm)	1843	2020	2007	1973	1990	2112
O ₂	(%)	11.3	10.4	10.4	10.5	10.7	10.3
CO ₂	(%)	8.4	8.9	9.0	8.8	8.9	9.3
H ₂ O	(%)	7.0	6.5	6.5	6.5	6.5	6.5
SLURRY/AIR IN							
Slurry Flow Rate	(gpm)	11.4	11.1	12.2	10.4	7.0	9.4
Lime Slurry Temperature	(°F)	74	76	73	69.6	73	92
Solids	(%)	23.41	24.07	23.39	23.35	20.18	16.30
Ca(OH) ₂	(%)	22.03	22.95	22.34	22.20	19.15	15.38
Density	(gm/cc)	1.1451	1.1620	1.1462	1.1467	1.1252	1.0950
Air In Flow	(scfm)	1152	1116	1099	1109	1121	1259
HUMIDIFICATION WATER							
Measured Flow	(gpm)	0.0	0.0	0.0	0.3	4.8	1.6
END OF HORIZ. DUCT							
SO ₂ at Inlet O ₂	(ppm)	793	896	868	1120	1059	1150
ESP INLET							
SO ₂	(ppm)	748	852	767	1042	986	1070
O ₂	(%)	11.4	10.7	10.8	10.8	11.1	10.8
CO ₂	(%)	8.4	8.9	8.9	8.9	8.9	9.3
H ₂ O	(%)	11.7	11.0	11.2	10.7	11.2	10.7
Flue Gas Temperature	(°F)	145	151	149	168	148	148
Adiabatic Saturation	(°F)	126	125	124	125	124	124
ESP OUTLET							
SO ₂ at Inlet O ₂	(ppm)	408	479	428	821	835	937
Flue Gas Temperature	(°F)	152	152	152	167	153	173
HEAT BALANCE CALCULATIONS							
ENTHALPY IN							
Flue Gas In	(KCal/min)	38177.2	38609.6	37786.8	38287.1	37985.4	37852.2
Ash In	(KCal/min)	194.7	216.3	208.6	208.8	208.2	219.7
Air In	(KCal/min)	-13.6	-5.2	-15.1	-30.6	-17.0	72.0
Slurry Solids In	(KCal/min)	-5.7	-2.3	-7.1	-12.2	-3.8	15.2
Reaction	(KCal/min)	1440.0	1531.8	1633.9	1208.8	1290.4	1319.1
ENTHALPY OUT							
Heated Air	(KCal/min)	353.7	373.8	356.4	453.1	358.9	400.4
Heated Slurry Solids	(KCal/min)	180.1	204.9	204.3	230.5	130.5	137.1
Vaporization and Heating	(KCal/min)	22694.0	22350.3	24253.3	21645.9	25148.0	23357.6
Flue Gas	(KCal/min)	10896.1	11879.1	11606.4	14582.9	11440.8	11352.8
TOTAL IN	(KCal/min)	39793	40350	39607	39662	39463	39478
TOTAL OUT	(KCal/min)	34124	34808	36420	36912	37078	35248
Difference	(KCal/min)	5669	5542	3187	2750	2385	4230
HEAT BALANCE							
Extra Flow for Heat Balance	(gpm)	2.5	2.4	1.4	1.2	1.1	1.8
Closure	(%)	-14.2	-13.7	-8.0	-6.9	-6.0	-10.7
Equivalent ΔT	(°F)	32.0	31.4	17.8	15.5	13.4	23.8

Table B-3. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		37-SL-02	37-SL-02	38-SL-03	37-SL-03	38-SL-02
DATE:		4/3/91	4/3/91	4/4/91	4/4/91	4/9/91
TIME:		1330-1430	1500-1600	1400-1500	1700-1800	1200-1300
	Units					
Ca/S Ratio	--	2.17	2.06	2.16	2.15	1.82
Approach	(°F)	22	22	25	24	24
SO ₂ Removal						
End of Horizontal Duct	(%)	56	53	56	53	54
ESP Inlet	(%)	61	59	59	57	57
ESP Outlet	(%)	76	75	76	74	74
Gas Phase Utilization						
End of Horizontal Duct	(%)	26	26	26	25	30
ESP Inlet	(%)	28	28	27	26	31
ESP Outlet	(%)	35	36	35	34	40
GAS IN						
Flue Gas Flow	(acfm)	49866	49823	49862	49896	49922
Flue Gas Temperature	(°F)	316	316	319	317	320
SO ₂	(ppm)	2008	2095	1990	1954	1946
O ₂	(%)	10.5	10.2	10.7	10.7	10.8
CO ₂	(%)	9.0	9.2	8.8	8.7	8.7
H ₂ O	(%)	6.9	6.9	7.0	7.0	7.9
SLURRY/AIR IN						
Slurry Flow Rate	(gpm)	12.6	12.4	12.7	12.4	10.8
Lime Slurry Temperature	(°F)	88	92	100	100	100
Solids	(%)	23.58	23.58	23.18	23.18	22.02
Ca(OH) ₂	(%)	22.11	22.11	21.53	21.53	20.66
Density	(gm/cc)	1.1461	1.1461	1.1422	1.1422	1.1364
Air In Flow	(scfm)	1187	1184	1179	1168	1178
HUMIDIFICATION WATER						
Measured Flow	(gpm)	1.4	1.5	0.1	0.1	0.7
END OF HORIZ. DUCT						
SO ₂ at Inlet O ₂	(ppm)	874	978	884	917	894
ESP INLET						
SO ₂	(ppm)	750	813	793	819	820
O ₂	(%)	10.8	10.8	11.0	10.9	11.0
CO ₂	(%)	9.0	9.3	8.8	8.8	8.7
H ₂ O	(%)	12.0	10.6	11.3	10.7	11.6
Flue Gas Temperature	(°F)	147	148	151	150	152
Adiabatic Saturation	(°F)	126	126	126	126	128
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	474	530	480	516	511
Flue Gas Temperature	(°F)	157	157	159	158	160
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	38660.9	38652.0	38993.1	38824.1	39172.0
Ash In	(KCal/min)	215.2	224.2	216.0	210.8	212.1
Air In	(KCal/min)	50.2	66.6	103.1	101.6	102.4
Slurry Solids In	(KCal/min)	22.7	29.9	46.3	45.2	37.3
Reaction	(KCal/min)	1628.8	1632.0	1560.0	1474.8	1458.1
ENTHALPY OUT						
Heated Air	(KCal/min)	377.0	380.1	392.6	386.4	400.5
Heated Slurry Solids	(KCal/min)	205.6	208.8	212.8	207.4	187.3
Vaporization and Heating	(KCal/min)	28492.7	28270.4	25771.3	25257.6	23795.2
Flue Gas	(KCal/min)	11251.2	11372.8	11736.8	11690.8	12001.0
TOTAL IN	(KCal/min)	40578	40605	40919	40657	40982
TOTAL OUT	(KCal/min)	40326	40232	38113	37542	36384
Difference	(KCal/min)	251	373	2805	3114	4598
HEAT BALANCE						
Extra Flow for Heat Balance	(gpm)	0.1	0.2	1.2	1.4	2.0
Closure	(%)	-0.6	-0.9	-6.9	-7.7	-11.2
Equivalent ΔT	(°F)	1.4	2.1	15.8	17.5	26.0

Table B-4. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		37-SL-04	38-SL-01	38-SL-02	38-SL-03	38-SL-04
DATE:		4/5/91	4/8/91	4/9/91	4/10/91	4/12/91
TIME:		1500-1600	1300-1400	1600-1700	1800-1930	1315-1400
	Units					
Ca/S Ratio	—	2.41	1.58	1.79	1.29	1.91
Approach	(°F)	22	23	22	25	26
SO ₂ Removal						
End of Horizontal Duct	(%)	58	53	—	—	—
ESP Inlet	(%)	62	55	57	41	54
ESP Outlet	(%)	79	71	74	52	67
Gas Phase Utilization						
End of Horizontal Duct	(%)	24	33	—	—	—
ESP Inlet	(%)	26	35	32	32	28
ESP Outlet	(%)	33	45	41	40	35
GAS IN						
Flue Gas Flow	(acfm)	49899	49863	49873	49925	49853
Flue Gas Temperature	(°F)	313	322	323	308	313
SO ₂	(ppm)	1884	1991	1973	1983	1992
O ₂	(%)	11.2	10.7	10.7	10.7	11.3
CO ₂	(%)	8.3	9.0	8.7	8.9	8.9
H ₂ O	(%)	7.8	8.0	7.9	7.0	6.8
SLURRY/AIR IN						
Slurry Flow Rate	(gpm)	12.7	9.3	10.8	11.5	12.1
Lime Slurry Temperature	(°F)	89	105	106	63	83
Solids	(%)	24.54	22.78	22.02	16.17	21.83
Ca(OH) ₂	(%)	22.66	21.20	20.66	14.91	20.37
Density	(gm/cc)	1.1508	1.1396	1.1364	1.0970	1.1317
Air In Flow	(scfm)	1159	1195	1169	1234	1309
HUMIDIFICATION WATER						
Measured Flow	(gpm)	0.1	3.9	1.1	0.18	0.3
END OF HORIZ. DUCT						
SO ₂ at Inlet O ₂	(ppm)	790	942	N/A	N/A	N/A
ESP INLET						
SO ₂	(ppm)	707	876	827	1180	926
O ₂	(%)	11.4	11.0	11.0	10.8	11.2
CO ₂	(%)	8.3	9.0	8.7	8.8	8.6
H ₂ O	(%)	11.6	12.0	11.7	11.8	11.8
Flue Gas Temperature	(°F)	149	151	151	151	151
Adiabatic Saturation	(°F)	128	129	129	125	125
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	399	577	515	960	662
Flue Gas Temperature	(°F)	160	158	160	154	158
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	38358.6	39441.3	39522.4	37788.1	38254.7
Ash In	(KCal/min)	200.0	219.0	217.9	205.8	210.4
Air In	(KCal/min)	53.3	125.9	128.5	-63.7	28.3
Slurry Solids In	(KCal/min)	26.0	40.3	46.9	-16.7	10.2
Reaction	(KCal/min)	1539.0	1419.7	1464.7	1099.0	1436.3
ENTHALPY OUT						
Heated Air	(KCal/min)	377.2	401.4	389.3	409.9	435.7
Heated Slurry Solids	(KCal/min)	214.3	173.4	183.5	155.2	197.2
Vaporization and Heating	(KCal/min)	25363.6	27973.5	24701.2	24311.1	25202.7
Flue Gas	(KCal/min)	11564.6	11815.8	11682.4	11924.9	11844.6
TOTAL IN	(KCal/min)	40177	41246	41380	39012	39940
TOTAL OUT	(KCal/min)	37520	40364	36957	36801	37680
Difference	(KCal/min)	2657	882	4424	2211	2260
HEAT BALANCE						
Extra Flow for Heat Balance	(gpm)	1.2	0.4	1.9	1.0	1.0
Closure	(%)	-6.6	-2.1	-10.7	-5.7	-5.7
Equivalent ΔT	(°F)	14.9	5.0	25.1	12.3	12.6

Table B-5. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		38-SL-04	39-SL-01	39-SL-02	39-SL-02
DATE:		4/12/91	4/15/91	4/16/91	4/16/91
TIME:		1415-1515	1640-1740	1200-1300	1530-1630
	Units		Add Water Downstream	Add water at Main Lance	Add Water Downstream
Ca/S Ratio	--	1.92	1.94	1.79	1.81
Approach					
From Slurry /Water at Main Lance	(°F)	25	~ 35	24	~ 45
From Downstream Humidification	(°F)		23		25
SO ₂ Removal					
ESP Inlet	(%)	53	50	57	50
ESP Outlet	(%)	68	65	72	65
Gas Phase Utilization					
ESP Inlet	(%)	28	26	32	28
ESP Outlet	(%)	35	34	40	36
GAS IN					
Flue Gas Flow	(acfm)	49845	49801	49905	49848
Flue Gas Temperature	(°F)	313	311	314	312
SO ₂	(ppm)	1994	1973	2009	1988
O ₂	(%)	11.1	11.3	10.9	10.9
CO ₂	(%)	8.9	8.8	7.7	7.6
H ₂ O	(%)	6.8	8.0	7.2	7.2
SLURRY/AIR IN					
Slurry Flow Rate	(gpm)	12.2	11.8	10.8	10.8
Lime Slurry Temperature	(°F)	85	72	92	89
Solids	(%)	21.83	22.04	22.69	22.69
Ca(OH) ₂	(%)	20.37	20.58	21.34	21.34
Density	(gm/cc)	1.1317	1.1367	1.1409	1.1409
Air In Flow	(scfm)	1299	1307	1155	1287
HUMIDIFICATION WATER					
Measured Flow	(gpm)	0.3	0.1	0.7	0.2
END OF HORIZ. DUCT					
SO ₂ at Inlet O ₂	(ppm)	N/A	N/A	N/A	N/A
ESP INLET					
SO ₂	(ppm)	935	934	845	938
O ₂	(%)	11.1	11.8	11.2	11.4
CO ₂	(%)	8.6	9.0	7.8	7.7
H ₂ O	(%)	12.0	11.2	11.2	10.8
Flue Gas Temperature	(°F)	150	151	150	151
Adiabatic Saturation	(°F)	125	128	126	126
ESP OUTLET					
SO ₂ at Inlet O ₂	(ppm)	645	689	573	693
Flue Gas Temperature	(°F)	156	164	163	160
HEAT BALANCE CALCULATIONS					
ENTHALPY IN					
Flue Gas In	(KCal/min)	38325.5	38067.3	38308.4	38054.4
Ash In	(KCal/min)	211.2	206.7	213.7	209.8
Air In	(KCal/min)	39.6	-23.6	63.4	56.5
Slurry Solids In	(KCal/min)	14.5	-8.5	24.2	19.4
Reaction	(KCal/min)	1420.6	1304.2	1512.6	1336.5
ENTHALPY OUT					
Heated Air	(KCal/min)	428.2	434.1	381.7	430.7
Heated Slurry Solids	(KCal/min)	196.0	195.1	187.5	189.5
Vaporization and Heating	(KCal/min)	25319.4	24103.2	23475.6	22280.1
Flue Gas	(KCal/min)	11708.9	11851.4	11706.8	11858.9
TOTAL IN	(KCal/min)	40011	39546	40122	39676
TOTAL OUT	(KCal/min)	37652	36584	35752	34759
Difference	(KCal/min)	2359	2962	4371	4917
HEAT BALANCE					
Extra Flow for Heat Balance	(gpm)	1.0	1.3	1.9	2.1
Closure	(%)	-5.9	-7.5	-10.9	-12.4
Equivalent ΔT	(°F)	13.2	16.5	24.7	27.8

Table B-6. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		39-SL-03	39-SL-04	39-SL-04	39-SL-04
DATE:		4/17/91	4/18/91	4/18/91	4/18/91
TIME:		1430-1630	1100-1300	1700-1800	1900-2000
	Units	Add water at Main Lance	Slurry Only	Add Water Downstream	Add Water Downstream
Ca/S Ratio	--	1.78	1.60	1.75	1.77
Approach					
From Slurry /Water at Main Lance	(°F)	23	47	~ 47	~ 47
From Downstream Humidification	(°F)			26	10
SO ₂ Removal					
ESP Inlet	(%)	58	38	48	61
ESP Outlet	(%)	76	46	63	80
Gas Phase Utilization					
ESP Inlet	(%)	33	24	27	35
ESP Outlet	(%)	43	29	36	45
GAS IN					
Flue Gas Flow	(acfm)	49856	49907	49742	49910
Flue Gas Temperature	(°F)	313	295	313	313
SO ₂	(ppm)	1982	2001	1953	1922
O ₂	(%)	10.8	11.0	11.0	11.1
CO ₂	(%)	8.9	9.0	9.0	8.8
H ₂ O	(%)	7.0	7.0	7.0	7.0
SLURRY/AIR IN					
Slurry Flow Rate	(gpm)	10.6	9.7	10.0	10.0
Lime Slurry Temperature	(°F)	91	85	93	93
Solids	(%)	22.80	23.07	23.07	23.07
Ca(OH) ₂	(%)	21.34	21.73	21.73	21.73
Density	(gm/cc)	1.1436	1.1454	1.1454	1.1454
Air In Flow	(scfm)	1151	1275	1371	1355
HUMIDIFICATION WATER					
Measured Flow	(gpm)	1.3	0.1	0.8	3.6
END OF HORIZ. DUCT					
SO ₂ at Inlet O ₂	(ppm)	N/A	N/A	N/A	N/A
ESP INLET					
SO ₂	(ppm)	797	1189	980	707
O ₂	(%)	11.2	11.4	11.4	11.6
CO ₂	(%)	9.0	9.2	9.1	9.0
H ₂ O	(%)	11.6	10.6	11.1	12.2
Flue Gas Temperature	(°F)	148	171	150	135
Adiabatic Saturation	(°F)	125	125	125	125
ESP OUTLET					
SO ₂ at Inlet O ₂	(ppm)	483	1075	722	386
Flue Gas Temperature	(°F)	153	176	157	145
HEAT BALANCE CALCULATIONS					
ENTHALPY IN					
Flue Gas In	(KCal/min)	38305.7	36211.3	38253.2	38323.3
Ash In	(KCal/min)	209.7	195.6	206.3	203.4
Air In	(KCal/min)	61.6	38.0	84.1	80.4
Slurry Solids In	(KCal/min)	23.3	12.1	25.7	24.8
Reaction	(KCal/min)	1540.8	1036.3	1238.8	1577.2
ENTHALPY OUT					
Heated Air	(KCal/min)	369.8	542.1	453.7	353.6
Heated Slurry Solids	(KCal/min)	179.8	227.8	179.4	140.7
Vaporization and Heating	(KCal/min)	24456.4	19845.2	21984.6	28287.5
Flue Gas	(KCal/min)	11418.3	15532.2	11736.4	9274.0
TOTAL IN	(KCal/min)	40141	37493	39808	40209
TOTAL OUT	(KCal/min)	36424	36147	34354	38056
Difference	(KCal/min)	3717	1346	5454	2153
HEAT BALANCE					
Extra Flow for Heat Balance	(gpm)	1.6	0.5	2.4	0.9
Closure	(%)	-9.3	-3.6	-13.7	-5.4
Equivalent ΔT	(°F)	20.9	7.4	30.7	11.9

Table B-7. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		39-SL-05	39-SL-05	39-SL-05
DATE:		4/19/91	4/19/91	4/19/91
TIME:		1430-1600	1616-1715	1748-1833
	Units	Add Water Downstream	Add Water Downstream	Add Water Downstream
Ca/S Ratio	-	1.77	1.77	1.76
Approach				
From Slurry /Water at Main Lance	(°F)	~ 45	~ 45	~ 45
From Downstream Humidification	(°F)	23	9	15
SO ₂ Removal				
ESP Inlet	(%)	50	58	59
ESP Outlet	(%)	66	75	75
Gas Phase Utilization				
ESP Inlet	(%)	28	33	33
ESP Outlet	(%)	37	42	43
GAS IN				
Flue Gas Flow	(acfm)	49892	49925	49893
Flue Gas Temperature	(°F)	311	312	312
SO ₂	(ppm)	1985	1988	2000
O ₂	(%)	10.7	10.6	10.5
CO ₂	(%)	9.2	9.2	9.2
H ₂ O	(%)	7.6	7.6	7.6
SLURRY/AIR IN				
Slurry Flow Rate	(gpm)	10.6	10.6	10.6
Lime Slurry Temperature	(°F)	85	86	88
Solids	(%)	22.74	22.74	22.74
Ca(OH) ₂	(%)	21.15	21.15	21.15
Density	(gm/cc)	1.1439	1.1439	1.1439
Air In Flow	(scfm)	1421	1404	1365
HUMIDIFICATION WATER				
Measured Flow	(gpm)	0.3	3.3	3.9
END OF HORIZ. DUCT				
SO ₂ at Inlet O ₂	(ppm)	N/A	N/A	N/A
ESP INLET				
SO ₂	(ppm)	923	800	804
O ₂	(%)	11.3	11.1	11.0
CO ₂	(%)	9.3	9.3	9.4
H ₂ O	(%)	11.5	12.9	13.1
Flue Gas Temperature	(°F)	150	136	141
Adiabatic Saturation	(°F)	126	126	126
ESP OUTLET				
SO ₂ at Inlet O ₂	(ppm)	684	495	508
Flue Gas Temperature	(°F)	159	153	150
HEAT BALANCE CALCULATIONS				
ENTHALPY IN				
Flue Gas In	(KCal/min)	38197.5	38359.5	38280.1
Ash In	(KCal/min)	208.6	210.1	210.7
Air In	(KCal/min)	42.4	48.0	57.0
Slurry Solids In	(KCal/min)	13.0	14.9	18.2
Reaction	(KCal/min)	1325.0	1527.7	1555.3
ENTHALPY OUT				
Heated Air	(KCal/min)	465.1	371.5	392.8
Heated Slurry Solids	(KCal/min)	183.6	148.6	161.4
Vaporization and Heating	(KCal/min)	22100.8	28756.7	30273.9
Flue Gas	(KCal/min)	11696.8	9432.9	10266.2
TOTAL IN	(KCal/min)	39786	40160	40121
TOTAL OUT	(KCal/min)	34446	38710	41094
Difference	(KCal/min)	5340	1450	-973
HEAT BALANCE				
Extra Flow for Heat Balance	(gpm)	2.3	0.6	-0.4
Closure	(%)	-13.4	-3.6	2.4
Equivalent ΔT	(°F)	29.8	8.0	-5.4

Table B-8. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		42-SL-02	42-SL-02	42-SL-02	42-SL-04	42-SL-04
DATE:		5/8/91	5/8/91	5/8/91	5/10/91	5/10/91
TIME:		1700-1800	1800-1900	1900-2000	1300-1400	1400-1500
	Units					
Ca/S Ratio	--	1.99	2.01	1.99	1.94	1.99
Approach	(°F)	34	33	33	36	35
SO ₂ Removal						
ESP Inlet	(%)	59	58	57	60	60
ESP Outlet	(%)	66	66	63	65	67
Gas Phase Utilization						
ESP Inlet	(%)	29	29	28	31	30
ESP Outlet	(%)	33	33	32	33	33
GAS IN						
Flue Gas Flow	(acfm)	49901	49899	49887	49867	49824
Flue Gas Temperature	(°F)	323	322	322	322	324
SO ₂	(ppm)	1981	1955	1954	1977	1922
O ₂	(%)	11.1	11.2	11.1	11.1	11.1
CO ₂	(%)	8.3	8.3	8.3	8.6	8.3
H ₂ O	(%)	7.6	7.6	7.8	7.3	7.1
SLURRY/AIR IN						
Slurry Flow Rate	(gpm)	12.5	12.4	12.3	12.6	12.5
Lime Slurry Temperature	(°F)	102	102	101	99	100
Solids	(%)	21.37	21.37	21.37	20.72	20.72
Ca(OH) ₂	(%)	20.07	20.07	20.07	19.47	19.47
Density	(gm/cc)	1.1312	1.1312	1.1312	1.1277	1.1277
Air In Flow	(scfm)	1180	1181	1182	1175	1171
HUMIDIFICATION WATER						
Measured Flow	(gpm)	0.1	0.1	0.1	0.1	0.1
END OF HORIZ. DUCT						
SO ₂ at Inlet O ₂	(ppm)	N/A	N/A	N/A	N/A	N/A
ESP INLET						
SO ₂	(ppm)	776	793	816	774	769
O ₂	(%)	11.6	11.5	11.5	11.2	11.2
CO ₂	(%)	8.3	8.3	8.4	8.5	8.5
H ₂ O	(%)	12.5	12.5	12.6	12.2	12.1
Flue Gas Temperature	(°F)	160	160	160	162	160
Adiabatic Saturation	(°F)	126	126	127	126	125
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	671	665	721	696	642
Flue Gas Temperature	(°F)	165	165	165	170	169
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	39432.2	39363.8	39310.5	39347.1	39449.0
Ash In	(KCal/min)	218.6	215.3	214.7	217.5	212.6
Air In	(KCal/min)	108.7	108.8	107.4	95.8	101.0
Slurry Solids In	(KCal/min)	43.9	43.8	42.6	37.8	39.9
Reaction	(KCal/min)	1521.8	1487.5	1446.8	1569.1	1502.1
ENTHALPY OUT						
Heated Air	(KCal/min)	440.5	439.6	442.9	449.8	440.4
Heated Slurry Solids	(KCal/min)	221.9	219.7	219.0	223.2	216.8
Vaporization and Heating	(KCal/min)	25878.2	25737.5	25406.9	26130.6	26121.6
Flue Gas	(KCal/min)	13105.3	13078.2	13170.9	13453.6	13158.6
TOTAL IN	(KCal/min)	41325	41219	41122	41267	41305
TOTAL OUT	(KCal/min)	39646	39475	39240	40257	39937
Difference	(KCal/min)	1679	1744	1882	1010	1367
HEAT BALANCE						
Extra Flow for Heat Balance	(gpm)	0.7	0.8	0.8	0.4	0.6
Closure	(%)	-4.1	-4.2	-4.6	-2.4	-3.3
Equivalent ΔT	(°F)	9.5	9.9	10.6	5.7	7.8

Table B-9. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		42-SL-04	43-SL-01	43-SL-01	43-SL-01	43-SL-01
DATE:		5/10/91	5/13/91	5/13/91	5/13/91	5/13/91
TIME:		1500-1542	1200-1300	1300-1400	1400-1500	1500-1600
	Units					
Ca/S Ratio	--	1.92	2.07	2.05	2.08	2.01
Approach	(°F)	36	24	24	24	24
SO ₂ Removal						
End of Horizontal Duct	(%)	--	--	--	--	61
ESP Inlet	(%)	60	75	75	75	71
ESP Outlet	(%)	64	83	81	84	79
Gas Phase Utilization						
End of Horizontal Duct	(%)	--	--	--	--	30
ESP Inlet	(%)	31	36	37	36	35
ESP Outlet	(%)	34	40	40	40	39
GAS IN						
Flue Gas Flow	(acfm)	49883	49857	49830	49914	49899
Flue Gas Temperature	(°F)	324	327	317	328	318
SO ₂	(ppm)	1983	1982	1979	1986	1992
O ₂	(%)	10.9	10.7	10.7	10.7	10.7
CO ₂	(%)	8.6	8.2	8.2	8.2	8.1
H ₂ O	(%)	7.1	8.0	7.9	7.8	7.6
SLURRY/AIR IN						
Slurry Flow Rate	(gpm)	12.5	12.2	12.2	12.3	12.0
Lime Slurry Temperature	(°F)	101	92	91	91	93
Solids	(%)	20.72	22.43	22.43	22.43	22.43
Ca(OH) ₂	(%)	19.47	21.01	21.01	21.01	21.01
Density	(gm/cc)	1.1277	1.1371	1.1371	1.1371	1.1371
Air In Flow	(scfm)	1170	1160	1155	1149	1118
HUMIDIFICATION WATER						
Measured Flow	(gpm)	0.1	0.6	0.8	0.5	0.3
END OF HORIZ. DUCT						
SO ₂ at Inlet O ₂	(ppm)	N/A	N/A	N/A	N/A	770
ESP INLET						
SO ₂	(ppm)	770	489	494	484	545
O ₂	(%)	11.3	11.0	11.0	11.1	11.1
CO ₂	(%)	8.5	8.2	8.2	8.2	8.1
H ₂ O	(%)	11.9	13.3	13.2	13.0	12.7
Flue Gas Temperature	(°F)	161	151	151	151	147
Adiabatic Saturation	(°F)	125	127	127	127	126
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	710	346	327	327	411
Flue Gas Temperature	(°F)	168	161	150	157	159
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	39506.0	39832.7	38673.3	39978.6	38849.2
Ash In	(KCal/min)	219.4	221.9	212.7	223.5	215.4
Air In	(KCal/min)	107.6	64.0	60.8	62.3	67.6
Slurry Solids In	(KCal/min)	42.4	27.2	25.9	27.0	29.3
Reaction	(KCal/min)	1551.3	1914.3	1942.0	1922.0	1872.9
ENTHALPY OUT						
Heated Air	(KCal/min)	443.0	385.6	384.6	381.5	351.4
Heated Slurry Solids	(KCal/min)	219.8	202.0	202.2	203.0	189.2
Vaporization and Heating	(KCal/min)	25989.8	26056.0	26536.5	26129.1	24875.8
Flue Gas	(KCal/min)	13275.7	11605.9	11765.4	11580.0	11093.1
TOTAL IN	(KCal/min)	41427	42060	40915	42213	41034
TOTAL OUT	(KCal/min)	39928	38249	38889	38294	36510
Difference	(KCal/min)	1498	3811	2026	3920	4525
HEAT BALANCE						
Extra Flow for Heat Balance	(gpm)	0.6	1.7	0.9	1.7	2.0
Closure	(%)	-3.6	-9.1	-5.0	-9.3	-11.0
Equivalent ΔT	(°F)	8.5	21.7	11.4	22.3	25.6

Table B-10. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		51-SL-01	51-SL-02	52-SL-01	52-SL-02	52-SL-03
DATE:		7/9/91	7/10/91	7/15/91	7/16/91	7/17/91
TIME:		1600 - 1700	1900 - 2000	1900 - 2000	1800 - 1900	1900 - 2000
	Units					
Ca/S Ratio	-	1.85	1.85	2.13	1.84	1.83
Approach	(°F)	35	37	36	41	42
SO ₂ Removal						
End of H Duct	(%)	50	52	52	49	51
ESP Inlet	(%)	52	54	53	51	53
ESP Outlet	(%)	64	65	64	61	62
Gas Phase Utilization						
End of H Duct	(%)	27	28	24	27	28
ESP Inlet	(%)	28	29	25	28	29
ESP Outlet	(%)	34	35	30	33	34
GAS IN						
Flue Gas Flow	(acfm)	50212	50157	50147	50173	50168
Flue Gas Temperature	(°F)	314	308	309	309	310
SO ₂	(ppm)	2035	2028	1986	1968	1943
O ₂	(%)	10.7	10.9	11.1	10.9	11.0
CO ₂	(%)	8.8	8.7	8.5	8.5	8.4
H ₂ O	(%)	9.0	8.2	8.2	7.5	6.9
SLURRY/AIR/WATER IN						
Slurry Flow Rate	(gpm)	12.7	13.0	12.9	12.7	12.5
Lime Slurry Temperature	(°F)	96	90	95	103	102
Solids	(%)	20.30	19.92	22.43	19.85	19.85
Ca(OH) ₂	(%)	18.96	18.66	20.92	18.74	18.74
Density	(gm/cc)	1.1240	1.1311	1.1437	1.1210	1.1200
Air In Flow	(scfm)	1078	1176	1177	1151	1146
Humidification Water Flow	(gpm)	0.0	0.0	0.0	0.0	0.0
END OF HORIZ DUCT						
SO ₂ at Inlet O ₂	(ppm)	1012	981	960	1003	948
ESP INLET						
SO ₂	(ppm)	938	902	891	926	892
O ₂	(%)	11.1	11.3	11.5	11.3	11.3
CO ₂	(%)	8.8	8.7	8.5	8.5	8.3
H ₂ O	(%)	13.7	12.9	12.8	12.0	10.2
Flue Gas Temperature	(°F)	166	165	164	168	168
Adiabatic Saturation	(°F)	130	128	128	127	125
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	738	715	724	759	735
ENTHALPY IN						
Flue Gas In	(KCal/min)	38782.3	38067.0	38113.6	38126.4	38091.2
Ash In	(KCal/min)	217.6	211.8	208.0	206.6	204.1
Air In	(KCal/min)	77.4	57.2	80.9	113.3	108.2
Slurry Solids In	(KCal/min)	33.0	22.5	36.0	43.8	41.5
Reaction	(KCal/min)	1530.0	1581.9	1533.8	1457.9	1486.6
ENTHALPY OUT						
Heated Air	(KCal/min)	431.4	467.3	463.2	471.1	468.3
Heated Slurry Solids	(KCal/min)	234.5	234.1	249.6	232.4	228.8
Vaporization.& Heating	(KCal/min)	26378.9	27181.2	26452.6	26431.5	26055.2
Flue Gas	(KCal/min)	14365.5	14330.0	14159.5	14713.5	14661.4
TOTAL IN	(KCal/min)	40640	39940	39972	39948	39932
TOTAL OUT	(KCal/min)	41410	42213	41325	41848	41414
Difference	(KCal/min)	-770	-2272	-1353	-1900	-1482
HEAT BALANCE						
Closure	(%)	1.9	5.7	3.4	4.8	3.7
Equivalent ΔT	(°F)	-4.3	-12.5	-7.5	-10.5	-8.2
Water Flow for Heat Balance	(gpm)	-0.3	-1.0	-0.6	-0.8	-0.6

Table B-11. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		53-SL-01	53-SL-02	53-SL-03	54-SL-01
DATE:		7/23/91	7/24/91	7/26/91	7/31/91
TIME:		1900 - 2000	2100 - 2200	0000 - 0100	0600 - 0700
	Units				
Ca/S Ratio	-	1.72	1.81	1.62	1.80
Approach	(°F)	37	34	34	39
SO ₂ Removal					
End of H Duct	(%)	46	49	43	39
ESP Inlet	(%)	47	50	45	40
ESP Outlet	(%)	57	60	54	48
Gas Phase Utilization					
End of H Duct	(%)	27	27	27	22
ESP Inlet	(%)	28	28	28	22
ESP Outlet	(%)	33	33	33	27
GAS IN					
Flue Gas Flow	(acfm)	50052	50177	50149	49898
Flue Gas Temperature	(°F)	306	308	308	303
SO ₂	(ppm)	1964	1978	1927	2023
O ₂	(%)	11.2	11.4	11.6	11.2
CO ₂	(%)	8.5	8.4	8.3	8.6
H ₂ O	(%)	8.5	9.4	9.4	7.4
SLURRY/AIR/WATER IN					
Slurry Flow Rate	(gpm)	11.8	12.3	11.8	11.8
Lime Slurry Temperature	(°F)	94	83	77	61
Solids	(%)	20.23	19.90	18.50	21.51
Ca(OH) ₂	(%)	18.70	18.77	17.27	20.26
Density	(gm/cc)	1.1199	1.1200	1.1106	1.1267
Air In Flow	(scfm)	1230	1194	1297	1266
Humidification Water Flow	(gpm)	0.0	0.0	0.0	0.0
END OF HORIZ DUCT					
SO ₂ at Inlet O ₂	(ppm)	1058	1017	1097	1227
ESP INLET					
SO ₂	(ppm)	994	947	1018	1144
O ₂	(%)	11.6	11.8	11.9	11.7
CO ₂	(%)	8.6	8.4	8.3	8.7
H ₂ O	(%)	12.8	13.2	13.0	11.2
Flue Gas Temperature	(°F)	165	164	165	165
Adiabatic Saturation	(°F)	129	131	131	126
ESP OUTLET					
SO ₂ at Inlet O ₂	(ppm)	849	791	890	1058
ENTHALPY IN					
Flue Gas In	(KCal/min)	37652.4	38059.7	38064.2	37183.6
Ash In	(KCal/min)	202.3	206.3	201.2	205.4
Air In	(KCal/min)	78.4	28.4	-0.8	-75.7
Slurry Solids In	(KCal/min)	26.8	10.3	-0.2	-27.0
Reaction	(KCal/min)	1352.1	1439.9	1268.8	1185.1
ENTHALPY OUT					
Heated Air	(KCal/min)	490.4	470.3	515.4	499.3
Heated Slurry Solids	(KCal/min)	218.0	219.9	203.2	227.9
Vaporization and Heating	(KCal/min)	24261.0	25282.5	24382.4	23621.6
Flue Gas	(KCal/min)	14394.4	14234.9	14344.2	14252.7
TOTAL IN	(KCal/min)	39312	39745	39533	38471
TOTAL OUT	(KCal/min)	39364	40208	39445	38601
Difference	(KCal/min)	-52	-463	88	-130
HEAT BALANCE					
Closure	(%)	0.1	1.2	-0.2	0.3
Equivalent ΔT	(°F)	-0.3	-2.6	0.5	-0.7
Water Flow for Heat Balance	(gpm)	0.0	-0.2	0.0	-0.1

Table B-12. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST 54-SL-03, 8/2/91	TIME	1013-1045	1114-1130	1202-1213	1251-1321	1357-1427	1500-1524
Sample Port for Quench Probe		Bottom	Bottom	Bottom	Middle	Middle	Middle
Sample Point for Quench Probe		In	Middle	Out	In	Middle	Out
Ca/S Ratio	--	1.85	1.78	1.84	1.97	1.99	2.07
Approach	(°F)	36	37	38	38	39	40
SO ₂ Removal							
End of Horizontal Duct	(%)	46	44	44	47	48	49
ESP Inlet	(%)	48	46	47	50	48	50
ESP Outlet	(%)	58	55	55	57	57	59
Gas Phase Utilization							
End of Horizontal Duct	(%)	25	25	24	24	24	24
ESP Inlet	(%)	26	26	25	25	24	24
ESP Outlet	(%)	32	31	30	29	29	28
GAS IN							
Flue Gas Flow	(acfm)	50188	50135	50156	50337	50223	50272
Flue Gas Temperature	(°F)	312	313	311	312	313	316
SO ₂	(ppm)	1989	2116	2096	1988	2008	1958
O ₂	(%)	10.8	10.6	10.6	11.0	10.9	11.1
CO ₂	(%)	8.8	9.0	8.9	8.5	8.6	8.4
H ₂ O	(%)	9.9	9.7	9.6	9.3	9.1	8.8
SLURRY/SORBENT/AIR IN							
Slurry Flow Rate	(gpm)	12.7	12.7	12.8	12.8	12.8	13.0
Lime Slurry Temperature	(°F)	85	90	94	96	98	100
Solids	(%)	19.70	19.90	20.30	20.70	20.90	20.85
Ca(OH) ₂	(%)	18.58	18.80	19.22	19.67	19.90	19.89
Density	(gm/cc)	1.1180	1.1199	1.1225	1.1265	1.1297	1.1280
Air In Flow	(scfm)	1083	1074	1071	1066	1059	1053
HUMIDIFICATION WATER							
Measured Flow	(gph)	0.0	0.0	0.0	0.0	0.0	0.0
END OF HORIZONTAL DUCT							
SO ₂ at Inlet O ₂	(ppm)	1072	1180	1172	1050	1048	995
ESP INLET							
SO ₂	(ppm)	994	1114	1082	956	1005	961
O ₂	(%)	11.1	10.9	11.0	11.5	11.2	11.4
CO ₂	(%)	8.8	9.1	8.9	8.6	8.6	8.5
H ₂ O	(%)	13.7	13.7	13.4	13.2	12.9	12.8
Flue Gas Temperature	(°F)	168	169	169	169	170	170
Adiabatic Saturation	(°F)	132	132	131	131	131	130
ESP OUTLET							
SO ₂ at Inlet O ₂	(ppm)	825	942	935	856	854	804
Flue Gas Temperature	(°F)	173	174	175	175	177	178
ENTHALPY IN							
Flue Gas In	(KCal/min)	38659	38697	38500	38658	38709	39037
Ash In	(KCal/min)	211	225	222	212	214	212
Air In	(KCal/min)	34	54	67	77	83	89
Slurry Solids In	(KCal/min)	14	23	29	34	37	41
Reaction	(KCal/min)	1245	1260	1279	1304	1272	1284
ENTHALPY OUT							
Heated Air	(KCal/min)	444	445	446	444	443	442
Heated Slurry Solids	(KCal/min)	232	243	247	247	250	252
Vaporization and Heating	(KCal/min)	26177	26402	26453	26416	26457	26987
Flue Gas	(KCal/min)	14782	14921	14999	15035	15017	15023
TOTAL IN	(KCal/min)	40163	40259	40097	40284	40315	40662
TOTAL OUT	(KCal/min)	41636	42011	42145	42141	42167	42704
Difference	(KCal/min)	-1472	-1752	-2049	-1857	-1851	-2042
HEAT BALANCE							
Closure	(%)	3.7	4.4	5.1	4.6	4.6	5.0
Equivalent Delta T	°F	-8.2	-9.7	-11.3	-10.3	-10.3	-11.4
Flow for Heat Balance	(gpm)	-0.6	-0.8	-0.9	-0.8	-0.8	-0.9

Table B-13. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST 54-SL-03, 8/2/91	TIME	1605-1618	1648-1705	1726-1740
Sample Port for Quench Probe		Top	Top	Top
Sample Point for Quench Probe		In	Middle	Out
Ca/S Ratio	-	2.08	2.08	2.13
Approach	(°F)	39	40	42
SO ₂ Removal				
End of Horizontal Duct	(%)	50	51	50
ESP Inlet	(%)	50	52	52
ESP Outlet	(%)	60	61	61
Gas Phase Utilization				
End of Horizontal Duct	(%)	24	24	23
ESP Inlet	(%)	24	25	24
ESP Outlet	(%)	29	30	29
GAS IN				
Flue Gas Flow	(acfm)	50287	50218	50252
Flue Gas Temperature	(°F)	315	317	317
SO ₂	(ppm)	1962	1947	1906
O ₂	(%)	11.1	11.1	11.2
CO ₂	(%)	8.5	8.4	8.3
H ₂ O	(%)	8.5	8.4	8.2
SLURRY/SORBENT/AIR IN				
Slurry Flow Rate	(gpm)	13.2	13.1	13.3
Lime Slurry Temperature	(°F)	101	102	102
Solids	(%)	20.75	20.68	20.60
Ca(OH) ₂	(%)	19.82	19.77	19.70
Density	(gm/cc)	1.1265	1.1255	1.1240
Air In Flow	(scfm)	1050	1052	1051
HUMIDIFICATION WATER				
Measured Flow	(gpm)	0.0	0.0	0.0
END OF HORIZONTAL DUCT				
SO ₂ at Inlet O ₂	(ppm)	981	961	956
ESP INLET				
SO ₂	(ppm)	952	896	888
O ₂	(%)	11.4	11.5	11.5
CO ₂	(%)	8.4	8.5	8.2
H ₂ O	(%)	12.3	12.2	12.0
Flue Gas Temperature	(°F)	169	169	170
Adiabatic Saturation	(°F)	129	129	129
ESP OUTLET				
SO ₂ at Inlet O ₂	(ppm)	779	752	736
Flue Gas Temperature	(°F)	177	177	178
ENTHALPY IN				
Flue Gas In	(KCal/min)	38951	39043	39100
Ash In	(KCal/min)	212	211	207
Air In	(KCal/min)	95	99	99
Slurry Solids In	(KCal/min)	44	45	45
Reaction	(KCal/min)	1300	1337	1311
ENTHALPY OUT				
Heated Air	(KCal/min)	436	437	443
Heated Slurry Solids	(KCal/min)	250	248	251
Vaporization and Heating	(KCal/min)	27417	27218	27507
Flue Gas	(KCal/min)	14852	14825	15032
TOTAL IN	(KCal/min)	40602	40735	40762
TOTAL OUT	(KCal/min)	42955	42728	43233
Difference	(KCal/min)	-2354	-1993	-2471
HEAT BALANCE				
Closure	(%)	5.8	4.9	6.1
Equivalent Delta T	°F	-13.1	-11.1	-13.8
Flow for Heat Balance	(gpm)	-1.0	-0.9	-1.1

Table B-14. Heat Balance Calculations for Parametric Reagent Slurry Injection. Tests

TEST:		65-SL-01	65-SL-01	65-SL-01	65-SL-02
DATE:		10/17/91	10/17/91	10/18/91	10/18/91
TIME:		1700- 1800	1800- 1900	0900- 1000	1400-1500
	Units				
Ca/S Ratio	-	1.66	1.69	1.49	1.57
Approach	(°F)	44	43	44	49
SO ₂ Removal					
End of H Duct	(%)	40	40	38	37
ESP Inlet	(%)	41	41	40	39
ESP Outlet	(%)	48	49	46	47
Gas Phase Utilization					
End of H Duct	(%)	24	23	26	24
ESP Inlet	(%)	25	24	27	25
ESP Outlet	(%)	29	29	31	30
GAS IN					
Flue Gas Flow	(acfm)	50012	49861	50092	49929
Flue Gas Temp	(°F)	339	341	324	332
SO ₂	(ppm)	2452	2458	2496	2396
O ₂	(%)	8.7	8.66	8.9	8.99
CO ₂	(%)	9.8	9.81	10.3	10.08
H ₂ O	(%)	7.8	8.67	9.2	8.91
SLURRY/SORBENT/AIR IN					
Slurry Flow Rate	(gpm)	12.76	12.8	11.77	11.8
Lime Slurry Temp.	(°F)	65	66	46	73
Solids	(%)	21.40	21.40	21.49	21.49
Ca(OH) ₂	(%)	19.89	19.89	19.79	19.79
Density	(gm/cc)	1.13	1.1317	1.13	1.1301
Air In Flow	(scfm)	1096	1084	1102	1059
END OF HORIZ DUCT					
SO ₂ at Inlet O ₂	(ppm)	1480	1481	1535	1498
ESP INLET					
SO ₂	(ppm)	1363	1367	1453	1411
O ₂	(%)	9.3	9.26	9.3	9.44
CO ₂	(%)	9.9	9.93	10.3	10.17
H ₂ O	(%)	13.0	13.21	13.3	12.91
Flue Gas Temp	(°F)	174	175	175	181
Adiabatic Saturation	(°F)	130	132	132	132
ESP OUTLET					
SO ₂ at Inlet O ₂	(ppm)	1284	1251	1352	1264
Flue Gas Temperature	(°F)	199	187	202	187
HEAT BALANCE CALCULATIONS					
ENTHALPY IN					
Flue Gas In	(KCal/min)	41538.6	41738	40121.7	40846
Ash In	(KCal/min)	289.1	292	278.2	275
Air In	(KCal/min)	-48.4	-47	-127.1	-14
Slurry Solids In	(KCal/min)	-21.6	-21	-52.3	-6
Reaction	(KCal/min)	1300.8	1285	1276.4	1189
ENTHALPY OUT					
Heated Air	(KCal/min)	478.2	477	486.3	495
Htd. Slurry Solids	(KCal/min)	284.8	287	276.9	288
Vaporization and Heating	(KCal/min)	25930.6	26016	23637.7	24060
Flue Gas	(KCal/min)	15165.6	15205	15729.8	16401
TOTAL IN	(KCal/min)	43058.5	43248	41497.0	42290
TOTAL OUT	(KCal/min)	41859.2	41985	40130.8	41244
Difference	(KCal/min)	1199.4	1263	1366.2	1046
HEAT BALANCE					
Closure	(%)	-2.8	-2.9	-3.3	-2.5
Equivalent Delta T	°F	6.9	7.3	7.7	6.0
Flow for Zero Heat Balance	(gpm)	0.5	0.55	0.6	0.45

Table B-15. Heat Balance Calculations for Parametric Reagent Slurry Injection Tests.

TEST:		74-SL-01	76-SL-01	77-SL-03	78-SL-01	78-SL-02
DATE:		12/20/91	12/30/91	1/9/92	1/16/92	1/17/92
TIME:		1600-1700	1500-1600	1600-1700	1600-1700	1300-1400
	Units					
Ca/S Ratio	—	1.73	2.13	2.22	4.91	2.34
Approach	(°F)	41.1	38.6	24.5	25.8	25.4
SO ₂ Removal						
End of Horizontal Duct	(%)	39.2	46.1	58.5	70.5	54.6
ESP Inlet	(%)	41.6	48.1	60.8	79.0	58.0
ESP Outlet	(%)	48.4	63.5	80.6	92.1	76.6
Gas Phase Utilization						
End of Horizontal Duct	(%)	22.7	21.6	26.4	14.4	23.3
ESP Inlet	(%)	24.1	22.6	27.4	16.1	24.8
ESP Outlet	(%)	28.0	29.8	36.3	18.8	32.7
GAS IN						
Flue Gas Flow	(acfm)	50068	48753	47674	47786	50037
Flue Gas Temperature	(°F)	308	307	304	304	323
SO ₂	(ppm)	2078	2071	2084	1077	2626
O ₂	(%)	10.40	11.11	10.8	15.3	8.2
CO ₂	(%)	8.97	8.53	8.7	5.0	10.7
H ₂ O	(%)	8.42	8.31	9.4	8.6	8.6
SLURRY/SORBENT/AIR IN						
Slurry Flow Rate	(gpm)	11.3	11.8	12.9	12.8	15.3
Slurry Temperature	(°F)	40.5	40.6	60	60	60
Solids	(%)	22.06	24.63	24.35	26.16	26.81
Ca(OH) ₂	(%)	20.39	22.98	21.38	24.52	24.42
Density	(gm/cc)	1.1350	1.1571	1.1576	1.1723	1.1731
Air In Flow	(scfm)	1176	1115	1063	1099	1055
END OF HORIZONTAL DUCT						
SO ₂ at Inlet O ₂	(ppm)	1264	1117	864	318	1193
ESP INLET						
SO ₂	(ppm)	1153	1037	780	224	1077
O ₂	(%)	10.91	11.45	11.27	15.43	8.44
CO ₂	(%)	9.11	8.59	8.66	4.82	10.66
H ₂ O	(%)	11.98	12.04	13.27	12.44	13.37
Flue Gas Temperature	(°F)	169.8	167.0	151.2	154.4	155.7
Adiabatic Saturation	(°F)	128.7	128.4	130.5	128.6	130.3
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	1072	757	404	85	614
Flue Gas Temperature	(°F)	188.6	171	164	157	163
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	37982	36810	35680	35302	39986
Ash In	(KCal/min)	216	209	202	105	291
Air In	(KCal/min)	-160	-152	-110	-70	-67
Slurry Solids In	(KCal/min)	-61	-73	-60	-40	-48
Reaction	(KCal/min)	1148	1291	1595	1082	1976
ENTHALPY OUT						
Heated Air	(KCal/min)	490	450	355	383	374
Htd Slurry Solids	(KCal/min)	242	261	226	216	317
Vaporization and Heating	(KCal/min)	22492	23161	25346	25035	29629
Flue Gas	(KCal/min)	15082	14237	11546	11920	12594
TOTAL IN	(KCal/min)	39124	38086	37308	36379	42138
TOTAL OUT	(KCal/min)	38307	38110	37473	37554	42914
Difference	(KCal/min)	817	-24	-164	-1174	-776
HEAT BALANCE						
Closure	(%)	-2.1	0.1	0.4	3.2	1.8
Equivalent ΔT	°F	4.5	-0.1	-0.9	-6.8	-4.3
Flow for Zero Heat Balance	(gpm)	0.36	-0.01	-0.06	-0.52	-0.34

APPENDIX C

Heat Balance Calculations for Tests with Reagent Slurry/Recycle Ash Injection

Table C-1. Heat Balance Calculations for Reagent Slurry/Dry Recycle Ash Injection Tests.

TEST:		35-DSR-03	35-DSR-03	35-DSR-04
DATE:		3/20/91	3/20/91	3/21/91
TIME:		1600-1700	1700-1800	1215-1245
	Units	Slurry/Recycle Ash	Slurry/Recycle Ash	Slurry/Recycle Ash
Ca/S Ratio Overall	-	1.72	1.66	1.72
Slurry		1.09	1.04	1.07
Dry Recycle Ash		0.64	0.61	0.65
Approach	(°F)	45	46	23
SO ₂ Removal				
End of Horizontal Duct	(%)	36	36	48
ESP Inlet	(%)	36	36	51
ESP Outlet	(%)	44	44	63
Gas Phase Utilization				
End of Horizontal Duct	(%)	21	22	28
ESP Inlet	(%)	21	22	29
ESP Outlet	(%)	26	27	37
GAS IN				
Flue Gas Flow	(acfm)	49856	49876	49868
Flue Gas Temperature	(°F)	309	309	315
SO ₂	(ppm)	2062	2053	2034
O ₂	(%)	10.4	10.4	10.6
CO ₂	(%)	9.0	9.0	9.0
H ₂ O	(%)	6.5	6.5	6.5
SLURRY/SORBENT/AIR IN				
Slurry Mix Flow Rate	(gpm)	9.5	9.4	9.4
Slurry Mix Temperature	(°F)	88	93	94
Solids	(%)	16.57	15.87	16.30
Ca(OH) ₂	(%)	15.87	15.20	15.38
Density	(gm/cc)	1.1018	1.1018	1.0950
Dry Recycle Ash Feed Rate	(lb/h)	1197	1153	1209
% Available Lime	(%)	40.40	40.40	40.40
Air In Flow	(scfm)	1271	1265	1251
HUMIDIFICATION WATER				
Measured Flow	(gpm)	0.4	0.4	0.9
END OF HORIZONTAL DUCT				
SO ₂ at Inlet O ₂	(ppm)	1313	1313	1054
ESP INLET				
SO ₂	(ppm)	1211	1210	947
O ₂	(%)	11.2	11.2	11.0
CO ₂	(%)	9.1	9.1	9.0
H ₂ O	(%)	10.0	10.0	10.4
Flue Gas Temperature	(°F)	170	170	148
Adiabatic Saturation	(°F)	124	124	125
ESP OUTLET				
SO ₂ at Inlet O ₂	(ppm)	1151	1146	749
Flue Gas Temperature	(°F)	174	174	162
HEAT BALANCE CALCULATIONS				
ENTHALPY IN				
Flue Gas In	(KCal/min)	37878.0	37880.8	38483.9
Ash In	(KCal/min)	215.0	214.0	216.8
Air In	(KCal/min)	52.6	76.3	80.1
Slurry Solids In	(KCal/min)	11.3	15.7	17.1
Dry Sorbent In	(KCal/min)	15.7	22.0	24.4
Reaction	(KCal/min)	989.7	1007.0	1376.4
ENTHALPY OUT				
Heated Air	(KCal/min)	529.9	531.4	402.6
Heated Slurry Solids	(KCal/min)	180.3	177.1	136.5
Heated Dry Sorbent	(KCal/min)	216.8	213.2	167.4
Vaporization and Heating	(KCal/min)	20973.4	21079.0	21963.0
Flue Gas	(KCal/min)	14904.5	15024.0	11403.5
TOTAL IN	(KCal/min)	39162	39216	40199
TOTAL OUT	(KCal/min)	36805	37025	34073
Difference	(KCal/min)	2357	2191	6126
HEAT BALANCE				
Extra Flow for Heat Balance	(gpm)	1.0	0.9	2.7
Closure	(%)	-6.0	-5.6	-15.2
Equivalent ΔT	°F	13.3	12.4	34.7

Table C-2. Results of Single Pass Recycle Slurry Tests.

TEST:		51-SR-01	52-SR-01	52-SR-02	53-SR-01	53-SR-02
DATE:		7/12/91	7/18/91	7/19/91	7/22/91	7/23/91
TIME:		1500 - 1600	1600 - 1700	1430 - 1530	1700 - 1800	1400 - 1500
	Units					
Ca/S Ratio Overall	—	1.03	1.38	1.43	1.55	1.59
Ca/S Ratio from Slurry	—	0.64	0.81	0.80	0.73	0.86
Recycle Ratio	—	2.2	3.3	3.7	3.5	3.3
Approach	(°F)	39	35	37	28	24
SO ₂ Removal						
End of H Duct	(%)	43	46	48	54	53
ESP Inlet	(%)	43	49	52	56	58
ESP Outlet	(%)	55	56	62	70	73
Gas Phase Utilization						
End of H Duct	(%)	42	34	34	35	33
ESP Inlet	(%)	42	35	36	36	36
ESP Outlet	(%)	53	41	43	45	46
GAS IN						
Flue Gas Flow	(acfm)	50183	50219	50173	50208	50159
Flue Gas Temperature	(°F)	308	309	309	309	308
SO ₂	(ppm)	2011	1991	1970	1975	2004
O ₂	(%)	11.0	10.9	11.0	10.9	10.9
CO ₂	(%)	8.5	8.5	8.5	8.6	8.6
H ₂ O	(%)	8.2	8.4	7.6	8.6	8.8
SLURRY/AIR/WATER IN						
Slurry Flow Rate	(gpm)	11.3	12.7	13.1	13.8	14.4
Lime Slurry Temperature	(°F)	87	105	105	102	108
Solids	(%)	20.29	26.77	26.77	28.71	30.67
Ca(OH) ₂	(%)	11.64	13.15	13.15	13.68	12.92
Density	(gm/cc)	1.1480	1.1936	1.1936	1.1803	1.2408
Air In Flow	(scfm)	1152	1172	1163	1125	1083
Humidification Water Flow	(gpm)	0.0	0.0	0.0	0.0	0.0
END OF HORIZ DUCT						
SO ₂ at Inlet O ₂	(ppm)	1140	1072	1016	916	941
ESP INLET						
SO ₂	(ppm)	1116	976	916	842	820
O ₂	(%)	11.4	11.3	11.4	11.2	11.3
CO ₂	(%)	8.5	8.5	8.5	8.6	8.6
H ₂ O	(%)	14.8	15.5	10.9	12.1	12.6
Flue Gas Temperature	(°F)	168	164	165	157	154
Adiabatic Saturation	(°F)	128	129	127	129	129
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	913	876	755	595	541
ENTHALPY IN						
Flue Gas In	(KCal/min)	38053.8	38191.0	38128.9	38206.0	38001.6
Ash In	(KCal/min)	210.1	209.0	206.7	207.2	208.6
Air In	(KCal/min)	44.8	121.3	124.2	104.7	124.9
Slurry Solids In	(KCal/min)	16.2	66.4	70.9	68.6	99.9
Reaction	(KCal/min)	1241.7	1408.5	1472.5	1601.9	1677.4
ENTHALPY OUT						
Heated Air	(KCal/min)	470.2	460.2	463.9	406.8	375.6
Heated Slurry Solids	(KCal/min)	224.2	288.3	298.9	293.6	319.7
Vaporization and Heating	(KCal/min)	23914.1	25811.5	26686.7	26819.1	28712.9
Flue Gas	(KCal/min)	14726.9	14145.5	14333.3	13020.5	12498.4
TOTAL IN	(KCal/min)	39567	39996	40003	40188	40112
TOTAL OUT	(KCal/min)	39335	40706	41783	40540	41907
Difference	(KCal/min)	231	-709	-1780	-352	-1794
HEAT BALANCE						
Closure	(%)	-0.6	1.8	4.4	0.9	4.5
Equivalent ΔT	(°F)	1.3	-3.9	-9.8	-1.9	-9.8
Water Flow for Heat Balance	(gpm)	0.1	-0.3	-0.8	-0.2	-0.8

Table C-3. Results of Single Pass Recycle Slurry Tests.

TEST:		53-SR-03	53-SR-04	53-SR-05	54-SR-01	54-SR-02
DATE:		7/24/91	7/25/91	7/26/91	7/29/91	7/30/91
TIME:		1300 - 1400	1400 - 1500	1330 - 1430	1500 - 1600	1500 - 1600
	Units					
Ca/S Ratio Overall	-	1.35	1.66	1.72	1.44	1.29
Ca/S Ratio from Slurry	-	0.62	0.97	0.69	1.15	0.85
Recycle Ratio	-	4.7	2.0	5.5	1.0	2.0
Approach	(°F)	33	29	26	36	37
SO ₂ Removal						
End of H Duct	(%)	46	52	49	45	45
ESP Inlet	(%)	50	55	55	48	46
ESP Outlet	(%)	58	64	67	58	56
Gas Phase Utilization						
End of H Duct	(%)	34	31	29	31	35
ESP Inlet	(%)	37	33	32	33	36
ESP Outlet	(%)	43	38	39	40	43
GAS IN						
Flue Gas Flow	(acfm)	50142	50159	50242	50174	50083
Flue Gas Temperature	(°F)	307	307	309	308	307
SO ₂	(ppm)	2015	1901	1923	1997	2036
O ₂	(%)	11.2	11.6	11.5	11.2	11.1
CO ₂	(%)	8.6	8.2	8.3	8.5	8.6
H ₂ O	(%)	8.5	9.4	9.0	9.9	9.2
SLURRY/SORBENT/AIR IN						
Slurry Flow Rate	(gpm)	12.7	14.1	14.4	12.2	12.2
Lime Slurry Temperature	(°F)	84	85	84	73	79
Solids	(%)	30.19	26.86	32.67	24.04	23.79
Ca(OH) ₂	(%)	12.77	13.77	13.53	14.59	13.47
Density	(gm/cc)	1.2195	1.1717	1.2292	1.1593	1.1565
Air In Flow	(scfm)	1119	1091	1133	1238	1112
Humidification Water Flow	(gpm)	0.0	0.0	0.0	0.0	0.0
END OF HORIZ DUCT						
SO ₂ at Inlet O ₂	(ppm)	1082	917	973	1093	1127
ESP INLET						
SO ₂	(ppm)	984	820	845	999	1059
O ₂	(%)	11.5	11.9	11.7	11.6	11.4
CO ₂	(%)	8.6	8.3	8.2	8.3	8.6
H ₂ O	(%)	16.0	13.4	13.1	13.5	12.8
Flue Gas Temperature	(°F)	162	159	156	168	167
Adiabatic Saturation	(°F)	129	131	130	132	130
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	839	693	631	840	895
ENTHALPY IN						
Flue Gas In	(KCal/min)	37915.3	37949.9	38201.3	38038.4	37829.8
Ash In	(KCal/min)	209.3	197.7	201.7	207.8	210.5
Air In	(KCal/min)	29.1	31.6	29.1	-17.7	9.3
Slurry Solids In	(KCal/min)	19.3	20.4	23.5	-7.7	4.4
Reaction	(KCal/min)	1451.6	1522.2	1525.7	1392.6	1372.3
ENTHALPY OUT						
Heated Air	(KCal/min)	426.0	404.6	403.3	508.9	451.3
Heated Slurry Solids	(KCal/min)	312.2	288.1	339.5	266.6	262.6
Vaporization and Heating	(KCal/min)	24897.8	27816.8	27271.5	24606.3	24731.7
Flue Gas	(KCal/min)	13755.8	13393.2	12840.4	14890.2	14686.7
TOTAL IN	(KCal/min)	39625	39722	39981	39613	39426
TOTAL OUT	(KCal/min)	39392	41903	40855	40272	40132
Difference	(KCal/min)	233	-2181	-873	-659	-706
HEAT BALANCE						
Closure	(%)	-0.6	5.5	2.2	1.7	1.8
Equivalent ΔT	(°F)	1.3	-12.0	-4.8	-3.6	-3.9
Water Flow for Heat Balance	(gpm)	0.1	-0.9	-0.4	-0.3	-0.3

Table C-4. Results of Low Ca/S Continuous Recycle Tests.

TEST:		66-SR-02	66-SR-03	66-SR-04	66-SR-05	67-SR-01
DATE:		10/22/91	10/23/91	10/24/91	10/25/91	10/28/91
TIME:		1600 - 1700	1530 - 1630	1700 - 1752	1400 - 1500	1600-1700
	Units					
Ca/S Ratio Overall	-	1.45	1.73	1.46	1.54	1.48
Ca/S Ratio from Slaked Lime Slurry		0.88	0.94	0.93	1.05	1.10
Recycle Ratio		3.57	4.64	3.04	2.12	1.92
Approach	(°F)	37	41	43	45	39
SO ₂ Removal						
End of H Duct	(%)	42	43	43	42	45
ESP Inlet	(%)	45	46	47	46	47
ESP Outlet	(%)	57	60	56	56	60
Gas Phase Utilization						
End of H Duct	(%)	29	25	30	27	30
ESP Inlet	(%)	31	27	32	30	32
ESP Outlet	(%)	38	35	39	37	40
GAS IN						
Flue Gas Flow	(acfm)	50067	50136	50155	50184	50112
Flue Gas Temp	(°F)	308	310	315	308	307
SO ₂	(ppm)	2031	2062	2111	2083	2041
O ₂	(%)	10.71	10.48	10.27	10.46	10.79
CO ₂	(%)	8.73	9.07	9.19	8.98	8.79
H ₂ O	(%)	9.22	9.42	9.06	8.68	8.44
SLURRY/SORBENT/AIR IN						
Slurry Mix Flow Rate	(gpm)	12.0	12.6	12.4	11.9	12.6
Slurry Mix Temp.	(°F)	80	80	82	82	69
Solids	(%)	28.01	35.09	31.02	29.79	29.71
Ca(OH) ₂	(%)	14.68	16.03	14.52	15.99	14.37
Density	(gm/cc)	1.2045	1.2688	1.2269	1.2200	1.2177
Slaked Lime Slurry Flow Rate	(gpm)	6.1	7.1	6.7	6.7	7.8
Solids	(%)	22.12	21.08	21.74	21.87	19.93
Ca(OH) ₂	(%)	18.53	18.15	19.73	20.77	16.94
Density	(gm/cc)	1.1358	1.1302	1.1356	1.1401	1.1233
Dry Recycle Ash Feed Rate	(lb/h)	428	1218	1259	1135	1208
Available Lime in Recycle Ash	(%)	22.77	22.77	24.01	27.11	20.64
Air In Flow	(scfm)	1075	1067	1071	1068	1154
END OF HORIZ. DUCT						
SO ₂ at Inlet O ₂	(ppm)	1175	1171	1194	1205	1125
ESP INLET						
SO ₂	(ppm)	1094	1087	1083	1095	1066
O ₂	(%)	10.95	10.69	10.71	10.82	10.86
CO ₂	(%)	8.66	8.89	9.27	8.95	8.64
H ₂ O	(%)	12.89	13.02	12.66	12.12	12.11
Flue Gas Temp	(°F)	167	172	174	174	167.8
Adiabatic Saturation	(°F)	130	131	131	129	128.7
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	904	826	921	910	825
Flue Gas Temp	(°F)	176	180	185	182	178
ENTHALPY IN						
Flue Gas In	(KCal/min)	38015	38340	38961	38125	37906
Ash In	(KCal/min)	211	217	227	218	212
Air In	(KCal/min)	12	13	18	20	-35
Slurry Solids In	(KCal/min)	7	11	13	13	-22
Reaction	(KCal/min)	1198	1255	1287	1258	1287
ENTHALPY OUT						
Heated Air	(KCal/min)	438	457	469	467	472
Htd. Slurry Solids	(KCal/min)	300	404	364	342	328
Vaporization and Heating	(KCal/min)	23885	23832	24174	23592	24561
Flue Gas	(KCal/min)	14696	15071	15703	15836	14780
TOTAL IN	(KCal/min)	39445	39835	40506	39633	39348
TOTAL OUT	(KCal/min)	39318	40164	40710	40236	40141
Difference	(KCal/min)	126	-329	-204	-604	-793
HEAT BALANCE						
Closure	(%)	-0.3	0.8	0.5	1.5	2.0
Equivalent Delta T	°F	0.7	-1.8	-1.1	-3.3	-4.4
Water Flow for Heat Balance	(gpm)	0.06	-0.14	-0.09	-0.26	-0.35

Table C-5. Results of Low Ca/S Continuous Recycle Tests.

TEST:		67-SR-02	67-SR-03	68-SR-01	68-SR-02
DATE:		10/31/91	11/1/91	11/4/91	11/5/91
TIME:		1500-1745	1300-1400	1600-1700	1400-1500
	Units				
Ca/S Ratio Overall	-	1.38	1.56	1.33	1.29
Ca/S Ratio from Slaked Lime Slurry		1.05	1.03	1.04	1.18
Recycle Ratio		2.05	1.83	2.09	1.88
Approach	(°F)	44	43	44	29
SO ₂ Removal					N/A
End of H Duct	(%)	40	47	40	N/A
ESP Inlet	(%)	42	42	41	49
ESP Outlet	(%)	54	54	51	64
Gas Phase Utilization					N/A
End of Horizontal Duct	(%)	29	30	30	N/A
ESP Inlet	(%)	31	27	31	38
ESP Outlet	(%)	39	35	38	49
GAS IN					
Flue Gas Flow	(acfm)	50129	50245	48793	48711
Flue Gas Temperature	(°F)	307	308	307	307
SO ₂	(ppm)	2058	2015	2086	1996
O ₂	(%)	10.85	11.08	10.63	10.93
CO ₂	(%)	8.61	8.39	8.85	8.39
H ₂ O	(%)	7.67	8.83	8.30	8.56
SLURRY/SORBENT/AIR IN					
Slurry Mix Flow Rate	(gpm)	12.2	12.5	11.5	12.5
Slurry Mix Temperature	(°F)	70	64	30	37
Solids	(%)	27.36	33.09	31.15	27.86
Ca(OH) ₂	(%)	14.25	14.69	14.00	12.52
Density	(gm/cc)	1.1963	1.2401	1.2199	1.1664
Slaked Lime Slurry Flow Rate	(gpm)	8.3	8.1	7.3	7.8
Solids	(%)	20.48	22.01	21.30	21.18
Ca(OH) ₂	(%)	17.35	17.80	18.71	18.95
Density	(gm/cc)	1.1244	1.1259	1.1323	1.1311
Dry Recycle Ash Feed Rate	(lb/h)	1298	1011	1280	1247
Available Lime in Recycle Ash	(%)	17.93	17.17	18.70	18.44
Air In Flow	(scfm)	1154	1149	1189	1177
END OF HORIZ DUCT					
SO ₂ at Inlet O ₂	(ppm)	1225	1061	1254	N/A
ESP INLET					
SO ₂	(ppm)	1167	1136	1247	977
O ₂	(%)	11.05	11.05	10.59	11.34
CO ₂	(%)	8.58	8.28	8.39	8.40
H ₂ O	(%)	11.15	12.51	11.60	12.54
Flue Gas Temperature	(°F)	171.4	172.4	172.3	157.6
Adiabatic Saturation	(°F)	126.9	129.6	128.3	128.9
ESP OUTLET					
SO ₂ at Inlet O ₂	(ppm)	956	929	953	723
Flue Gas Temperature	(°F)	185	205	199	166
ENTHALPY IN					
Flue Gas In	(KCal/min)	37880	38092	36869	36742
Ash In	(KCal/min)	214	211	210	201
Air In	(KCal/min)	-30	-55	-208	-175
Slurry Solids In	(KCal/min)	-16	-39	-122	-96
Reaction	(KCal/min)	1166	1129	1103	1264
ENTHALPY OUT					
Heated Air	(KCal/min)	490	493	508	426
Htd. Slurry Solids	(KCal/min)	311	378	335	265
Vap. & Htg.	(KCal/min)	24284	23729	21721	23568
Flue Gas	(KCal/min)	15342	15540	15115	12743
TOTAL IN	(KCal/min)	39213	39337	37766	37937
TOTAL OUT	(KCal/min)	40428	40139	37853	37002
Difference	(KCal/min)	-1215	-803	173	935
HEAT BALANCE					
Closure	(%)	3.1	2.0	-0.5	-2.5
Equivalent Delta T	°F	-6.7	-4.4	1.0	5.3
Water Flow for Heat Balance	(gpm)	-0.53	-0.35	0.08	0.42

Table C-6. Results of High Ca/S Continuous Recycle Tests.

	TEST: DATE: TIME: Units	68-SR-03 11/7/91 1600-1730	69-SR-01 11/12/91 1500 - 1600	69-SR-02 11/14/91 1600 - 1700	69-SR-03 11/15/91 1500 - 1700
Ca/S Ratios					
Overall Ca/S Ratio	--	2.61	2.51	2.64	2.35
Slaked Lime Ca/S Ratio	--	1.88	1.98	1.97	1.71
Recycle Ratio	--	1.32	1.46	1.26	1.49
Approach	(°F)	25.4	29.2	25.0	24.3
SO₂ Removal					
End of Horizontal Duct	(%)	N/A	54.4	N/A	N/A
ESP Inlet	(%)	64.1	59.2	65.5	65.5
ESP Outlet	(%)	85.3	79.0	88.6	88.3
Gas Phase Utilization					
End of Horizontal Duct	(%)	N/A	21.7	N/A	N/A
ESP Inlet	(%)	24.5	23.6	24.8	27.9
ESP Outlet	(%)	32.6	31.6	33.6	37.6
GAS IN					
Flue Gas Flow	(acfm)	49235	46327	48813	49653
Flue Gas Temp	(°F)	308	308	306	305
SO ₂	(ppm)	2045	2021	2051	2045
O ₂	(%)	11.13	11.02	10.80	10.78
CO ₂	(%)	8.60	8.47	8.51	8.61
H ₂ O	(%)	9.51	8.40	8.62	8.63
SLURRY/SORBENT/AIR IN					
Slurry Mix Flow Rate	(gpm)	14.6	13.8	14.5	14.7
Slurry Mix Temp.	(°F)	37.4	39.0	64.2	68.3
Solids	(%)	38.20	34.93	33.58	31.48
Ca(OH) ₂	(%)	19.98	19.77	21.25	19.33
Density	(gm/cc)	1.2986	1.2538	1.2424	1.2238
Slaked Lime Slurry Flow Rate	(gpm)	10.7	11.4	10.7	9.7
Solids	(%)	24.67	23.45	24.54	24.11
Ca(OH) ₂	(%)	21.81	20.50	23.09	22.59
Density	(gm/cc)	1.1588	1.1503	1.1596	1.1526
Dry Recycle Ash Feed Rate	(lb/h)	1425	1562	1437	1492
% Available Lime	(%)	23.67	23.60	22.09	23.63
Air In Flow	(scfm)	1106	1136	1094	1095
END OF HORIZONTAL DUCT					
SO ₂ at Inlet O ₂	(ppm)	N/A	921	N/A	N/A
ESP INLET					
SO ₂	(ppm)	712	798	677	663
O ₂	(%)	11.44	11.32	11.20	10.98
CO ₂	(%)	8.61	8.45	8.51	8.63
H ₂ O	(%)	13.62	12.26	12.71	12.55
Flue Gas Temperature	(°F)	156.6	157.8	154.0	153.2
Adiabatic Saturation	(°F)	131.1	128.7	129.0	128.9
ESP OUTLET					
SO ₂ at Inlet O ₂	(ppm)	301	424	234	239
Flue Gas Temp	(°F)	165	166	162	164
HEAT BALANCE CALCULATIONS					
ENTHALPY IN					
Flue Gas In	(KCal/min)	37350	35115	36759	37312
Ash In	(KCal/min)	209	195	206	209
Air In	(KCal/min)	-164	-161	-53	-36
Slurry Solids In	(KCal/min)	-170	-136	-46	-29
Reaction	(KCal/min)	1690	1470	1739	1767
ENTHALPY OUT					
Heated Air	(KCal/min)	395	412	379	376
Heated Slurry Solids	(KCal/min)	413	357	347	326
Vaporization and Heating	(KCal/min)	26156	25139	27174	27960
Flue Gas	(KCal/min)	12718	12123	12213	12303
TOTAL IN	(KCal/min)	38916	36482	38606	39223
TOTAL OUT	(KCal/min)	39682	38031	40112	40964
Difference	(KCal/min)	-767	-1549	-1507	-1740
HEAT BALANCE					
Closure	(%)	2.0	4.2	3.9	4.4
Equivalent ΔT	°F	-4.2	-9.1	-8.4	-9.6
Extra Flow for Zero Heat Balance	(gpm)	-0.34	-0.69	-0.67	-0.77

Table C-7. Heat Balance Calculations for Long-Term ESP Test.

	TEST:	81-SR-01	81-SR-01	82-SR-01	82-SR-01	82-SR-01	82-SR-01	82-SR-01
	DATE:	2/3/92	2/4/92	2/10/92	2/11/92	2/12/92	2/13/92	2/13/92
	TIME:	1900-2000	1100-1200	1600-1700	1500-1600	1600-1700	1000-1100	1400-1500
Ca/S Ratios								
Overall Ca/S Ratio	--	1.52	1.10	1.47	1.31	1.28	1.31	1.34
Slaked Lime Ca/S Ratio	--	1.06	1.05	1.10	1.00	0.97	1.01	1.00
Recycle Ratio	--	2.21	1.88	1.77	1.66	1.96	2.07	1.88
Approach	(°F)	39.9	38.6	41.1	40.7	42.7	41.0	36.2
SO₂ Removal								
End of Horizontal Duct	(%)	42.4	39.8	41.4	41.5	39.9	40.5	42.1
ESP Inlet	(%)	44.5	41.7	43.3	42.7	40.5	41.6	43.5
ESP Outlet	(%)	58.0	55.1	55.0	56.6	55.6	54.5	58.2
Gas Phase Utilization								
End of Horizontal Duct	(%)	27.8	36.3	28.2	31.8	31.2	30.9	31.4
ESP Inlet	(%)	29.2	38.1	29.5	32.8	31.7	31.7	32.5
ESP Outlet	(%)	38.1	50.2	37.6	43.3	43.6	41.6	43.5
GAS IN								
Flue Gas Flow	(acfm)	49222	49161	49428	49419	50353	49880	49827
Flue Gas Temperature	(°F)	308	306	308	304	308	308	307
SO ₂	(ppm)	2022	2151	2065	2069	2064	2033	2053
O ₂	(%)	10.90	10.62	11.10	10.96	11.04	11.14	10.90
CO ₂	(%)	8.41	8.57	8.45	8.62	8.46	8.41	8.43
H ₂ O	(%)	8.51	9.17	8.93	8.86	8.62	8.97	8.80
SLURRY/SORBENT/AIR IN								
Slurry Mix Flow Rate	(gpm)	11.22	11.20	11.20	11.23	11.41	11.57	11.88
Slurry Mix Temperature	(°F)	49.32	49.74	44.42	42.96	30.39	34.55	43.68
Solids	(%)	28.57	23.77	33.96	34.27	30.37	32.97	30.76
Ca(OH) ₂	(%)	16.28	12.96	15.90	13.88	13.96	13.50	13.65
Density	(gm/cc)	1.2058	1.1561	1.2195	1.25	1.21	1.23	1.22
Slaked Lime Slurry Flow Rate	(gpm)	5.93	5.93	5.90	5.89	5.86	5.89	5.89
Solids	(%)	24.44	25.20	25.65	24.05	24.15	23.76	23.76
Ca(OH) ₂	(%)	22.50	23.37	23.63	21.99	21.70	21.77	21.85
Density	(gm/cc)	1.1527	1.1552	1.1621	1.1515	1.1513	1.1492	1.1464
Dry Recycle Ash Feed Rate	(lb/h)	1352	1200	1139	989	1142	1212	1101
% Available Lime	(%)	31.88	19.14	16.13	16.01	16.11	14.75	15.29
Air In Flow	(scfm)	1098	1103	1248	1175	1180	1168	1171
END OF HORIZONTAL DUCT								
SO ₂ at Inlet O ₂	(ppm)	1165	1295	1211	1210	1240	1208	1189
ESP INLET								
SO ₂	(ppm)	1109	1182	1129	1135	1192	1148	1090
O ₂	(%)	11.02	11.02	11.47	11.38	11.36	11.45	11.32
CO ₂	(%)	8.42	8.56	8.42	8.40	8.42	8.43	8.46
H ₂ O	(%)	11.9	12.5	12.4	12.1	12.2	12.2	12.2
Flue Gas Temperature	(°F)	168.8	168.8	170.9	170.2	172.3	170.9	165.7
Adiabatic Saturation	(°F)	128.9	130.2	129.8	126.2	129.6	129.9	129.5
ESP OUTLET								
SO ₂ at Inlet O ₂	(ppm)	849	967	900	898	914	924	859
Flue Gas Temperature	(°F)	173.1	175.0	174.7	175.0	176.6	171.4	169.0
HEAT BALANCE								
ENTHALPY IN								
Flue Gas In	(KCal/min)	37283	37020	37438	37037	38125	37791	37699
Ash In	(KCal/min)	207	218	212	209	216	211	212
Air In	(KCal/min)	-114	-113	-152	-150	-206	-185	-146
Slurry Solids In	(KCal/min)	-63	-50	-90	-97	-116	-118	-88
Reaction	(KCal/min)	1173	1164	1165	1159	1113	1113	1175
ENTHALPY OUT								
Heated Air	(KCal/min)	453	455	526	492	505	493	466
Htd. Slurry Solids	(KCal/min)	293	255	345	351	326	347	317
Vaporization and Heating	(KCal/min)	21850	22336	20375	20753	21581	21438	22666
Flue Gas	(KCal/min)	14651	14699	15068	15022	15567	15205	14337
TOTAL IN	(KCal/min)	38485	38240	38572	38159	39132	38811	38851
TOTAL OUT	(KCal/min)	37247	37745	36314	36619	37978	37482	37786
Difference	(KCal/min)	1238	495	2258	1540	1154	1329	1065
HEAT BALANCE								
Closure	(%)	-3.2	-1.3	-5.9	-4.0	-2.9	-3.4	-2.7
Equivalent ΔT	°F	7.0	2.8	12.7	8.6	6.4	7.4	5.9
Extra Water Flow for Balance	(gpm)	0.5	0.2	1.0	0.7	0.5	0.6	0.5

APPENDIX D

Heat Balance Calculations for Air/Liquid Ratio Tests with Reagent Slurry Injection

Table D-1. Heat Balance Calculations for Air/Liquid Ratio Tests with Lechler Nozzle Array.

TEST DATE TIME		57-SL-01 8/19/91 1700-1800	57-SL-02 8/20/91 1700-1800	57-SL-03 8/21/91 1200-1300	57-SL-04 8/22/91 1200-1300	68-SL-01 11/6/91 1413-1600	68-SL-01 11/6/91 1600-1830
	Units						
Ca/S Ratio	-	2.18	2.02	1.98	2.11	1.62	1.70
Approach	(°F)	35	36	36	36	22.9	31.1
SO ₂ Removal							
End of Horizontal Duct	(%)	50	48	49	51	N/A	N/A
ESP Inlet	(%)	52	49	51	53	48.9	47.4
ESP Outlet	(%)	64	63	63	67	59.6	58.8
Gas Phase Utilization							
End of Horizontal Duct	(%)	23	24	24	24	N/A	N/A
ESP Inlet	(%)	24	24	26	25	30.3	27.9
ESP Outlet	(%)	29	31	32	32	36.9	34.6
GAS IN							
Flue Gas Flow	(acfm)	50214	50116	50149	50157	53752	53888
Flue Gas Temperature	(°F)	307	306	308	307	354	354
SO ₂	(ppm)	2014	2017	2017	2059	3289	3260
O ₂	(%)	11.0	11.2	11.1	11.0	4.88	5.0
CO ₂	(%)	8.6	8.8	8.5	8.5	13.54	13.4
H ₂ O	(%)	9.5	8.7	9.2	9.1	8.28	8.3
SLURRY/SORBENT/AIR IN							
Slurry Flow Rate	(gpm)	13.0	12.6	12.8	13.5	17.7	17.3
Lime Slurry Temperature	(°F)	73	75	74	86	52.9	53
Solids	(%)	22.96	22.15	21.88	22.22	22.52	23.73
Ca(OH) ₂	(%)	21.28	20.78	19.91	20.53	19.54	20.60
Density	(gm/cc)	1.1462	1.1380	1.1390	1.1370	1.1334	1.1502
Air In Flow	(scfm)	934	922	799	665	1100	1072
Air In Pressure	(psig)	70	70	60	50	80	80
Air/Water Ratio		0.72	0.73	0.63	0.50	0.61	0.61
HUMIDIFICATION WATER							
Measured Flow	(gpm)	0.0	0.0	0.0	0.0	0.0	0.0
END OF HORIZ DUCT							
SO ₂ at Inlet O ₂	(ppm)	1007	1040	1037	1016	N/A	N/A
ESP INLET							
SO ₂	(ppm)	958	1022	979	964	1604	1602
O ₂	(%)	11.1	11.3	11.2	11.1	5.58	5.66
CO ₂	(%)	8.6	8.7	8.5	8.5	13.51	13.43
H ₂ O	(%)	13.2	12.6	13.3	13.2	13.83	13.56
Flue Gas Temperature	(°F)	166	165	167	166	154.8	163.1
Adiabatic Saturation	(°F)	131	129	130	130	131.9	132.0
ESP OUTLET							
SO ₂ at Inlet O ₂	(ppm)	729	750	741	689	1327	1342
Flue Gas Temperature	(°F)	173	171	175	172	182	170
ENTHALPY IN							
Flue Gas In	(KCal/min)	38048	37738	38001	37940	46967.5	47158.6
Ash In	(KCal/min)	210	208	210	214	440.0	438.4
Air In	(KCal/min)	-14	-7	-9	21	-99.2	-97.3
Slurry Solids In	(KCal/min)	-8	-4	-6	17	-64.7	-67.9
Reaction	(KCal/min)	1377	1322	1370	1442	2165.7	2082.9
ENTHALPY OUT							
Heated Air	(KCal/min)	375	364	323	267	384.6	414.7
Heated Slurry Solids	(KCal/min)	262	244	251	262	332.5	377.1
Vaporization and Heating	(KCal/min)	26214	25468	25967	27406	35060.3	34283.0
Flue Gas	(KCal/min)	14576	14297	14611	14510	12977.4	14387.5
TOTAL IN	(KCal/min)	39612	39257	39565	39635	49409	49515
TOTAL OUT	(KCal/min)	41427	40373	41152	42445	48755	49462
Difference	(KCal/min)	-1815	-1117	-1586	-2811	654	52
HEAT BALANCE							
Closure	(%)	4.6	2.8	4.0	7.1	-1.3	-0.1
Equivalent Delta T	°F	-10.0	-6.2	-8.8	-15.6	3.4	0.3
Flow for Heat Balance	(gpm)	-0.8	-0.5	-0.7	-1.2	0.29	0.02

**Table D-2. Heat Balance Calculations for Air/Liquid Ratio Tests with a Single
12 gpm Lechler Supersonic Nozzle, November, 1991.**

	TEST:	71-SL-01	71-SL-01	71-SL-01	71-SL-02	71-SL-03
	DATE:	11/25/91	11/25/91	11/25/91	11/26/91	11/27/91
	TIME:	1226-1326	1330-1431	1443 - 1527	1700 - 1800	1800 - 1900
	Units					
Ca/S Ratio	--	1.69	1.83	2.30	2.09	2.00
Approach	(°F)	44	36	26	41	37
SO ₂ Removal						
End of Horizontal Duct	(%)	44	48	57	49	49
ESP Inlet	(%)	45	51	60	52	51
ESP Outlet	(%)	52	61	76	63	64
Gas Phase Utilization						
End of Horizontal Duct	(%)	26	26	25	23	25
ESP Inlet	(%)	27	28	26	25	26
ESP Outlet	(%)	31	33	33	30	32
GAS IN						
Flue Gas Flow	(acfm)	48072	47947	48019	47573	49942
Flue Gas Temp	(°F)	303	303	303	306	303
SO ₂	(ppm)	2077	2070	2055	2014	2054
O ₂	(%)	10.8	10.8	10.9	11.1	10.9
CO ₂	(%)	8.7	8.7	8.6	8.5	8.7
H ₂ O	(%)	8.6	8.6	8.6	8.5	8.7
SLURRY/SORBENT/Air IN						
Slurry Flow Rate	(gpm)	10.9	11.8	13.4	11.6	11.5
Lime Slurry Temp.	(°F)	85	86	84	85	86
Solids	(%)	23.00	23.00	24.03	24.67	24.40
Ca(OH) ₂	(%)	19.78	19.78	21.43	21.78	22.58
Density	(gm/cc)	1.1397	1.1397	1.1532	1.1530	1.1541
Air In Flow	(scfm)	651	642	629	630	632
Air to Water Ratio	--	0.61	0.56	0.48	0.54	0.57
Humidification Water Flow	(gpm)	0.00	0.00	0.00	0.00	0.00
END OF HORIZONTAL DUCT						
SO ₂ at Inlet O ₂	(ppm)	1165	1073	895	1029	1041
ESP INLET						
SO ₂	(ppm)	1124	979	796	923	968
O ₂	(%)	11.0	11.1	11.1	11.6	11.2
CO ₂	(%)	8.8	8.7	8.7	8.6	8.8
H ₂ O	(%)	12.1	12.4	12.9	12.3	12.3
Flue Gas Temperature	(°F)	173	165	155	169	166
Adiabatic Saturation	(°F)	129	129	129	129	129
ESP OUTLET						
SO ₂ at Inlet O ₂	(ppm)	996	817	489	755	746
Flue Gas Temp	(°F)	210	181	167	179	174
HEAT BALANCE CALCULATIONS						
ENTHALPY IN						
Flue Gas In	(KCal/min)	35894.6	35770.8	35824.1	35833.9	37227.0
Ash In	(KCal/min)	203.1	201.7	200.6	197.6	208.2
Air In	(KCal/min)	-115.7	-113.5	-112.1	-88.9	-71.1
Slurry Solids In	(KCal/min)	-80.8	-86.7	-105.1	-74.0	-57.7
Reaction	(KCal/min)	1188.1	1350.5	1587.2	1315.8	1403.0
ENTHALPY OUT						
Heated Air	(KCal/min)	280.2	253.8	220.1	261.7	252.3
Heated Slurry Solids	(KCal/min)	248.9	240.0	241.1	261.0	252.7
Vaporization and Heating	(KCal/min)	21492.7	23115.8	26147.6	22717.9	22810.3
Flue Gas	(KCal/min)	15053.3	13787.8	12210.2	14290.5	14492.6
TOTAL IN	(KCal/min)	37089	37123	37395	37184	38709
TOTAL OUT	(KCal/min)	37075	37397	38819	37531	37808
Difference	(KCal/min)	14	-275	-1424	-347	901
HEAT BALANCE						
Closure	(%)	0.0	0.7	3.8	0.9	-2.3
Equivalent ΔT	°F	0.1	-1.6	-8.2	-2.0	5.1
Extra Flow for Heat Balance	(gpm)	0.0	-0.1	-0.6	-0.2	0.5

APPENDIX E

Heat Balance Calculations for Chloride Addition Tests

Table E-1. Heat Balance Calculations for Chloride Addition Tests.

	TEST:	76-SL-01	76-SL-02	76-SL-03	76-SL-04	77-SL-01	77-SL-02
	DATE:	12/30/91	12/31/91	1/2/92	1/3/92	1/6/92	1/7/92
	TIME:	1500-1600	1300-1350	1400-1500	1400-1500	1800-1900	1600-1700
	NOTES:	No Cl	0.26% Cl	0.5% Cl	0.97% Cl	1.8% Cl	2.3% Cl
	Units						
Ca/S Ratio	-	2.13	2.28	2.38	1.97	1.97	2.20
Approach	(°F)	38.6	35.2	36.5	35.4	34.2	35.2
SO ₂ Removal							
End of H Duct	(%)	46.1	50.6	49.5	46.9	46.2	52.9
ESP Inlet	(%)	48.1	52.1	51.7	49.8	50.2	56.4
ESP Outlet	(%)	63.5	69.0	67.8	64.2	66.3	76.3
Gas Phase Utilization							
End of H Duct	(%)	21.6	22.1	20.8	23.8	23.5	24.1
ESP Inlet	(%)	22.6	22.8	21.8	25.3	25.6	25.7
ESP Outlet	(%)	29.8	30.2	28.5	32.5	33.7	34.7
GAS IN							
Flue Gas Flow	(acfm)	48753	47970	49296	48283	46573	47774
Flue Gas Temperature	(°F)	307	305	306	303	307	307
SO ₂	(ppm)	2071	2077	2039	2058	2084	2042
O ₂	(%)	11.11	10.95	11.01	11.08	10.90	10.89
CO ₂	(%)	8.53	8.05	8.47	8.18	8.21	8.44
H ₂ O	(%)	8.31	8.57	8.45	8.36	8.92	8.37
SLURRY/SORBENT/AIR IN							
Slurry Flow Rate	(gpm)	11.8	12.0	13.0	11.7	11.8	12.4
Lime Slurry Temperature	(°F)	40.6	37.7	49.5	53.6	36.9	38.3
Solids	(%)	24.63	26.89	25.79	24.28	24.03	25.67
Ca(OH) ₂	(%)	22.98	23.50	22.99	21.27	20.30	21.64
Density	(gm/cc)	1.1571	1.1716	1.1659	1.1558	1.1558	1.1606
Air In Flow	(scfm)	1115	1110	1092	1104	1120	1124
Humidification Water Flow	(gpm)	0	0	0	0	0	0
END OF HORIZ. DUCT							
SO ₂ at Inlet O ₂	(ppm)	1117	1027	1030	1093	1121	961
ESP INLET							
SO ₂	(ppm)	1037	975	962	991	998	857
O ₂	(%)	11.45	11.13	11.25	11.50	11.32	11.27
CO ₂	(%)	8.59	8.06	8.53	8.33	8.17	8.48
H ₂ O	(%)	12.04	12.47	12.37	11.98	12.71	12.20
Flue Gas Temperature	(°F)	167.0	164.0	165.1	163.6	164.0	163.6
Adiabatic Saturation	(°F)	128.4	128.8	128.6	128.2	129.7	128.5
ESP OUTLET							
SO ₂ at Inlet O ₂	(ppm)	757	643	657	738	703	483
Flue Gas Temperature	(°F)	171	168	171	169	169	171
HEAT BALANCE CALCULATIONS							
ENTHALPY IN							
Flue Gas In	(KCal/min)	36810	36003	37075	36006	35175	36053
Ash In	(KCal/min)	209	205	207	202	201	202
Air In	(KCal/min)	-152	-163	-113	-97	-168	-163
Slurry Solids In	(KCal/min)	-73	-88	-64	-45	-78	-85
Reaction	(KCal/min)	1291	1380	1381	1320	1287	1461
ENTHALPY OUT							
Heated Air	(KCal/min)	450	434	433	430	437	437
Heated Slurry Solids	(KCal/min)	261	274	284	246	245	267
Vaporization and Heating	(KCal/min)	23161	23122	25385	23087	23183	24081
Flue Gas	(KCal/min)	14237	13554	14119	13613	13139	13430
TOTAL IN	(KCal/min)	38086	37336	38486	37386	36418	37469
TOTAL OUT	(KCal/min)	38110	37383	40221	37374	37004	38215
Difference	(KCal/min)	-24	-47	-1734	12	-587	-746
HEAT BALANCE							
Closure	(%)	0.1	0.1	4.5	0.0	1.6	2.0
Equivalent ΔT	°F	-0.1	-0.3	-9.7	0.1	-3.5	-4.3
Extra Flow for Heat Balance	(gpm)	-0.01	-0.02	-0.77	0.01	-0.26	-0.33

Table E-2. Heat Balance Calculations for B&W SO₂ Model Tests.

	TEST:	84-SR-01	84-SR-02	83-SR-03	84-SL-03	83-SR-02	83-SR-01
	DATE:	2/25/92	2/26/92	2/20/92	2/27/92	2/19/92	2/18/92
	TIME:	1600-1700	1600-1700	1400-1500	1300-1400	1713-1754	1500-1600
	B&W Test #:	Test #1	Test #2	Test #3	Test #4	Test #6	Test #13
	Solids, % Sol. Cl	2.6	3.6	2.6	3.4	3.0	1.1
Ca/S Ratios							
Overall Ca/S Ratio	-	1.49	2.38	1.26	1.68	1.08	1.20
Slaked Lime Ca/S Ratio	-	0.92	1.82	1.07	1.68	0.29	0.98
Recycle Ratio	-	2.87	1.25	1.08	0.00	3.88	1.38
Approach	(°F)	25.1	35.3	26.5	36.7	34.8	25.1
SO ₂ Removal							
End of Horizontal Duct	(%)	61.8	60.2	53.5	47.8	26.3	48.9
ESP Inlet	(%)	65.9	65.7	55.3	50.3	27.9	51.0
ESP Outlet	(%)	82.6	79.6	69.3	64.0	36.2	61.7
Gas Phase Utilization							
End of Horizontal Duct	(%)	41.7	25.3	42.6	28.4	24.4	41.0
ESP Inlet	(%)	44.4	27.6	44.1	29.9	25.9	42.7
ESP Outlet	(%)	55.6	33.4	55.2	38.1	33.6	51.7
GAS IN							
Flue Gas Flow	(acfm)	52826	51960	50028	52863	50483	50729
Flue Gas Temperature	(°F)	307	304	305	304	306	308
SO ₂	(ppm)	1189	1143	2065	2049	2747	2077
O ₂	(%)	14.96	15.21	11.05	11.18	8.11	11.00
CO ₂	(%)	5.16	4.87	8.39	8.33	10.92	8.44
H ₂ O	(%)	8.3	8.0	9.1	8.4	8.8	9.3
SLURRY/SORBENT/AIR IN							
Slurry Mix Flow Rate	(gpm)	13.0	12.1	13.2	12.1	12.0	13.5
Slurry Mix Temperature	(°F)	51	36	40	43	46	63
Solids	(%)	27.57	32.95	28.82	22.74	21.49	25.97
Ca(OH) ₂	(%)	8.97	14.56	12.34	19.31	15.75	11.96
Density	(gm/cc)	1.1624	1.1775	1.1525	1.1417	1.1506	1.1261
Slaked Lime Slurry Flow Rate	(gpm)	4.4	6.6	6.1	12.1	3.2	6.1
Solids	(%)	22.71	25.40	29.58	22.74	24.76	24.54
Ca(OH) ₂	(%)	16.66	20.80	21.87	19.31	15.47	21.10
Density	(gm/cc)	1.1449	1.1623	1.2097	1.1417	1.1913	1.1605
Dry Recycle Ash Feed Rate	(lb/h)	959	790	685	0	900	818
% Available Lime	(%)	16.73	18.17	14.63	16.00	15.25	15.46
Air In Flow	(scfm)	1166	1169	1167	1153	1184	1142
END OF HORIZONTAL DUCT							
SO ₂ at Inlet O ₂	(ppm)	454	455	961	1069	2025	1061
ESP INLET							
SO ₂	(ppm)	383	365	870	986	1892	969
O ₂	(%)	15.29	15.58	11.60	11.48	8.69	11.45
CO ₂	(%)	5.23	5.05	8.48	8.25	10.92	8.42
H ₂ O	(%)	11.9	11.4	12.9	11.7	12.4	13.1
Flue Gas Temperature	(°F)	153.5	162.9	156.5	165.0	164.2	155.8
Adiabatic Saturation	(°F)	128.4	127.6	130.1	128.3	129.4	130.7
ESP OUTLET							
SO ₂ at Inlet O ₂	(ppm)	207	233	634	737	1754	795
Flue Gas Temperature	(°F)	172.4	170.9	167.9	174.7	213.9	167.1
HEAT BALANCE CALCULATIONS							
ENTHALPY IN							
Flue Gas In	(KCal/min)	39468	38413	37551	39561	38335	38525
Ash In	(KCal/min)	130	121	212	222	286	219
Air In	(KCal/min)	-115	-178	-162	-132	-139	-62
Slurry Solids In	(KCal/min)	-65	-114	-96	-57	-55	-34
Reaction	(KCal/min)	1100	1044	1510	1453	1023	1410
ENTHALPY OUT							
Heated Air	(KCal/min)	401	451	417	456	464	405
Htd. Slurry Solids	(KCal/min)	233	285	281	249	262	259
Vaporization and Heating	(KCal/min)	24669	21425	24285	24012	24337	25431
Flue Gas	(KCal/min)	12958	14364	12952	15138	14415	12955
TOTAL IN	(KCal/min)	40519	39287	39014	41046	39449	40059
TOTAL OUT	(KCal/min)	38260	36525	37935	39856	39477	39049
Difference	(KCal/min)	2258	2761	1079	1191	-29	1009
HEAT BALANCE							
Closure	(%)	-5.6	-7.0	-2.8	-2.9	0.1	-2.5
Equivalent ΔT	°F	12.0	14.9	5.9	6.3	-0.2	5.5
Extra Water Flow for Balance	(gpm)	1.0	1.2	0.5	0.5	0.0	0.4

END

**DATE
FILMED**

4 / 16 / 93