**Integration and Testing of Hot Desulfurization and
Entrained-Flow Gasification for Power Generation Systems,
Phase II, Process Optimization
Volume I -- Program Summary and PDU Operations**

Topical Report

**A.M. Robin
J.S. Kassman
T.F. Leininger
J.K. Wolfenbarger
C.M. Wu
P.P. Yang**

Work Performed Under Contract No.: DE-FC21-87MC23277

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
Texaco Inc.
Montebello Research Laboratory
P.O. Box 400
Montebello, California 90640**

September 1991

ABSTRACT

This second Topical Report describes the work that was completed between January 1, 1989 and December 31, 1990 in a Cooperative Agreement between Texaco and the U.S. Department of Energy that began on September 30, 1987. The Cooperative Agreement is a five year program that is designed to demonstrate the integration of high temperature desulfurization with the Texaco Coal Gasification Process.

During the period that is covered in this report, the development and optimization of in-situ and external desulfurization processes were pursued. The research effort included bench scale testing, PDU scoping tests, process economic studies and advanced instrument testing.

Two bench scale studies were performed at the Research Triangle Institute with zinc titanate sorbent to obtain data on its cycle life, sulfur capacity, durability and the effect of chlorides. These studies quantify sulfur capture during simulated air and oxygen-blown gasification for two zinc titanate formulations.

Eight PDU runs for a total of 20 days of operation were conducted to evaluate the performance of candidate sorbents for both in-situ and external desulfurization. A total of 47 tests were completed with oxygen and air-blown gasification. Candidate sorbents included iron oxide for in-situ desulfurization and calcium based and mixed metal oxides for external desulfurization. Gasifier performance and sorbent sulfur capture are compared for both air-blown and oxygen-blown operation.

Process and economic studies of nine configurations of integrated hot syngas cleanup units have been completed. Improvements in the overall plant heat rates were obtained; however, all of the plants were more expensive to build and operate than the cold gas cleanup base case. In response to this study, we have initiated twelve additional cases that incorporate process modifications that could dramatically reduce the costs.

Four advanced instruments were selected for PDU: a Fiber Optic Alkali Monitor (FOAM), a Classical Scattering Aerosol Spectrometer (CSAS), a Fiber Optic Fluorescence Thermometer (FOFT) and an Inductively Coupled Plasma Spectrometer (ICPS). During the time covered by this topical report, only the FOAM was tested. Total alkali concentrations at the filter inlet and outlet were measured.

ACKNOWLEDGEMENTS

This work was performed under Cooperative Agreement No. DE-FC21-87MC23277.

There are too many people who made significant contributions to this work than can be acknowledged by name, but the contributions of each and every one of them are appreciated.

We thank the operating and maintenance staffs at MRL for the many hours of effort required to modify the PDU and carry out the test program. We also wish to recognize the excellent cooperation and quick turn around provided by the analytical laboratory staff at MRL under the direction of Mr. Jerry Denchfield. In addition, Messrs. A. R. Catena and C. Bugescu deserve special thanks for the high quality and timeliness of their design and engineering work.

We offer special thanks to Dr. Justin Beeson for his help and suggestions as the DOE COTR during most of this phase of the program and to Mr. Sam Sharp for his continuing help and constructive suggestions as the present DOE COTR.

Finally we wish to recognize the excellent research and support provide by the staff at the Texaco Research Center Beacon in Beacon, New York, and by Dr. Santosh Gangwal and his staff at Research Triangle Institute.

Table of Contents

	<u>Page</u>
1. SUMMARY	1
2. INTRODUCTION	8
2.1 Objective	8
2.2 Proposal Basis	8
2.3 Five Year Plan	9
2.4 Summary of Phase I Testing Results	9
2.5 Phase II Work Breakdown	12
2.6 Process Description	14
2.7 Montebello Research Laboratory Facilities	18
2.7.1 Pilot Plant Facilities	18
2.7.2 Analytical Facilities	20
3. PHASE II TEST RESULTS	22
3.1 RTI Bench Scale Zinc Titanate Sorbent Testing	22
3.2 RTI Bench Scale Testing of the Effects of Chloride on Zinc Titanate	24
3.3 PDU Sorbent Testing - Iron Oxide In-situ & Calcium External	25
3.3.1 Pilot Plant Equipment and Procedures	25
3.3.2 Description of Runs	31
3.3.3 Sample and Data Collection	58
3.3.4 Results Achieved	59
3.4 PDU Testing- External Mixed Metal Oxide Sorbents	63
3.4.1 Sorbent Selection	63
3.4.2 Pilot Plant Equipment and Procedures	67
3.4.3 Description of Runs	71
3.4.4 Results Achieved	79
3.4.5 Regenerable Zinc Titanate Reactor Design	84
3.5 Advanced Instrumentation Testing	92
3.5.1 Fiber Optic Alkali Monitor	93
3.5.2 Description of FOAM Test Setup	93
3.5.3 FOAM Test Results Achieved	96
4. PROCESS ECONOMICS STUDIES	101
4.1 Objective	101
4.2 Methodology	101
4.2.1 General	101
4.2.2 Scope of Work	104
4.3 Case Descriptions	109
4.3.1 Case 1: Cold Gas Cleanup Base Case	111
4.3.2 Case 2: Entrained Bed Dolomite Slurry	111
4.3.3 Case 3: In-situ Iron Oxide	112
4.3.4 Case 4: In-situ Iron Oxide (air-blown)	113
4.3.5 Case 5: Fixed Bed Zinc Titanate	113

Table of Contents

	<u>Page</u>
4.3.6 Case 6: In-situ Iron Oxide plus Fixed Bed Zinc Titanate	115
4.3.7 Case 7: Fixed Bed Zinc Titanate (air- blown)	115
4.3.8 Case 8: Entrained Bed Dolomite Slurry plus Fixed Bed Zinc Titanate	116
4.3.9 Case 9: Entrained Bed Dolomite Slurry plus Fixed Bed Zinc Titanate (air- blown)	117
4.4 Results Achieved	117
4.4.1 Plant Efficiency (Heat Rate)	118
4.4.2 Plant Investment Cost	130
4.4.3 Operating and Maintenance Costs	130
4.4.4 Levelized Cost of Electricity	130
5. CONCLUSIONS AND PLANS FOR FUTURE WORK	132
5.1 In-Situ Desulfurization	132
5.2 External Desulfurization	132
5.2.1 Calcium Based Sorbents	132
5.2.2 Mixed Metal Oxide Sorbents	133
5.3 Advanced Instrumentation	134
5.4 Economic Studies	134
5.5 Future Plans	135
5.5.1 Bench Scale testing	135
5.5.2 PDU Testing	135
5.5.3 Process Economic Studies	136
5.5.4 Advanced Instrument Testing	137
REFERENCES	138
APPENDICES	139
Volume II - Study of Zinc Titanate Desulfurization Sorbents	
Volume III - Effect/Fate of Chlorides in the Zinc-Titanate Hot- Gas Desulfurization Process	

List of Tables

	<u>Page</u>
2-1. Texaco Coal Gasification Process Plant Summary	15
2-2. Tests on Pilot Unit Streams	21
3-1. New and Regenerated Zn/Ti Sorbents From RTI Testing	23
3-2. Summary of Phase II Gasification Tests: Key Parameters & Results	34
3-3. Run One In-Situ Desulfurization Test Results	35
3-4. Run 2 Test Results	36
3-5. Run 3 Test Results	37
3-6. Ground Dolomite Analyses	40
3-7. Run 4 Test Results	41
3-8. Dolomite Injection Run 2; Dolomite Deposit Analysis	49
3-9. Leachable Sulfide in Solids	60
3-10. Typical Gasifier Exit Syngas Composition (wet)	63
3-11. Summary of External Sorbent Tests	72
3-12. External Sorbents Run 1	72
3-13. External Sorbents Gas Composition; Run 1	73
3-14. External Sorbents Run 2	75
3-15. External Sorbents Gas Composition Run 2	76
3-16. External Sorbents Run 3	78
3-17. External Sorbents Gas Composition Run 3	78
3-18. Spent Zinc Titanate L-3014 (0.8Zn/Ti) Test Results	80
3-19. Spent Zinc Titanate L-3140 (1.5Zn/Ti) Test Results	81
3-20. Spent Zinc Ferrite L-2465 Test Results	82
3-21. Sulfur Balances for Mixed Metal Oxide Sorbents	84
3-22. Fiber Optic Alkali Monitor (FOAM) Test Results	97
4-1. DOE Process Economics Case Summary	103
4-2. Process Economics Scope of Work for Each Case	104
4-3. Process Economics Technical Criteria	105
4-4. Coal and Air Feed Data Used in Economic Analysis	106
4-5. Process Economics O&M Cost Components	108
4-6. Process Economics Cost of Electricity Components	109
4-7. DOE Economic Cases 1 - 9 Summary of Results	119
4-8. DOE Economics Cases 1 - 9 Power Summary	120
4-9. Plant Investment Summary for Cases 1 - 4	121
4-10. Plant Investment Summary for Cases 5 - 9	122
4-11. O&M Costs for Cases 1 - 4	124
4-12. O&M Costs for Cases 5-9 Assuming a ZnTi Life of 50 Cycles	125
4-13. O&M Costs for Cases 5-9 Assuming a ZnTi Life of 200 Cycles	126
4-14. O&M Costs for Cases 5-9 Assuming a ZnTi Life of 1000 Cycles	127

List of Figures

	<u>Page</u>
2-1. Phase II Gantt Chart	13
2-2. Texaco Coal Gasification Process Flow Diagram	16
2-3. Schematic Diagram of MRL Coal Grinding System	19
3-1. L.P.S.G.U. Process Flow Diagram	26
3-2. Air Preheat System	28
3-3. Radiant Vessel Refractory Sleeve	30
3-4. Dolomite Feed System	32
3-5. L.P.S.G.U. Modified for Dolomite Injection	38
3-6. Dolomite Injector	39
3-7. Radiant Vessel After First Run	42
3-8. Commercial Nozzle Before & After Use	44
3-9. Modified Radiant Vessel	45
3-10. New Dolomite Injection Nozzle	46
3-11. Modified Dolomite Injector	47
3-12. Modified Dolomite Injection Nozzle	48
3-13. Radiant Vessel After Second Dolomite Injection Run	50
3-14. Cold Flow Tester	51
3-15. Dolomite Flow Tube	53
3-16. Radiant Vessel After Third Dolomite Injection Run	54
3-17. Dolomite Fixed Bed	56
3-18. Modified Fixed Bed	57
3-19. Pittsburgh No. 8 Coal Performance Comparison Air-Blown vs Oxygen-Blown Gasification	61
3-20. Comparison of Air Preheat Temperature and CO ₂ /CO Ratio	62
3-21. Mass Balance for Run 1 Period F Powhatan Coal with Iron Oxide, Oxygen-Blown	64
3-22. Mass Balance for Run 2 Period A Pittsburgh No. 8 Coal, Air-Blown	65
3-23. Mass Balance for Run 3 Period A Pittsburgh No. 8 Coal with Iron Oxide, Air-Blown	66
3-24. External Sorbent Beds P&ID	68
3-25. External Sorbent Bed Reactor Details	69
3-26. Mixed Metal Oxides Run 1 H ₂ S Breakthrough Curves	73
3-27. Mixed Metal Oxides Run 2 H ₂ S Breakthrough Curves	74
3-28. Sorbent Beds Loading Run 3	77
3-29. Mixed Metal Oxides Run 3 H ₂ S Breakthrough Curves	79
3-30. Regenerable Sorbent Reactor Design	85
3-31. Regenerable Sorbent Bed P&ID	86
3-32. Fiber Optic Alkali Monitor System Overview	94
3-33. Fiber Optic Alkali PFD	95
4-1. Capital Cost Estimating Methodology	107

1. SUMMARY

This report covers work done during the second phase of a five phase program to develop and test an integrated hot gas cleanup system for use with a Texaco coal gasifier-based IGCC power generation process. The first two phases of the program cover proof of concept and process selection for the integrated system, with the following three phases covering the design, construction and operation of the integrated PDU.

Phase I is complete; the results are summarized in Chapter 2.4 of this report. A detailed description of this work may be found in the Phase I Topical Report (Ref. 1), which was published in 1989.

The objective for Phase II is to optimize the processes selected during Phase I. Completion of the Phase II work has taken longer than initially expected, partly because of difficulties experienced during the PDU tests and partly because the initial scope of work for Phase II has been modified as more has been learned. These modifications have included a significant expansion of the process optimization studies and additional PDU testing. This report describes the Phase II work completed through December 1, 1990.

The work done in Phase II consisted of the following five tasks:

1. Bench Scale Testing
2. PDU Scoping Tests
3. Process Economic Studies
4. Advanced Instrument Testing
5. Phase II Topical Report

Task 1. Bench Scale Testing

At the conclusion of Phase I of this project, the need for additional data on cycle life, sulfur loading and durability of zinc titanate sorbents was identified. These data subsequently were obtained in bench scale testing at the Research Triangle Institute (RTI). Also, the effect of chloride in the syngas on zinc titanate sorbents was investigated in a second study at RTI. A summary of this work is presented in Sections 1 and 2 of Chapter 3. The details of this work are reported in volumes two and three of this topical report.

Two zinc titanate sorbent formulations, made by United Catalyst Incorporated (L-3014 with Zn/Ti = 0.8 and L-3196 with Zn/Ti = 1.5), were tested at RTI during the first study. The results of

these tests indicate that the L-3196 sorbent is superior to the L-3014 sorbent.

The second study found that chloride in syngas does not significantly affect the ability of the 1.5 Zn/Ti zinc titanate (L-3196) to capture sulfur; chloride is removed from the sorbent during regeneration. The use of steam in the regeneration gas during some of these tests appeared to accelerate the loss of zinc from the sorbent.

Task 2. Process Development Unit Scoping Tests

A detailed test program was developed for PDU scoping tests to evaluate the performance of candidate sorbents and their effect on gasifier performance over a range of operating parameters. The test plan was based on information from the Phase 1 theoretical and bench scale testing and results from the Phase 1 scoping tests. The testing included evaluation of in-situ desulfurization sorbents introduced into the gasifier, and external desulfurization sorbents, introduced into the radiant cooler during air-blown and oxygen-blown gasification. Mixed metal oxide sorbents also were evaluated in three parallel downstream fixed bed reactors. To do this testing, several modifications to the PDU were required.

The PDU testing was conducted in two pilot plant units at the Montebello Research Laboratory. One 4-day, one 3-day and five 2-day runs were made at 350 psig, with most of the syngas generated going through the radiant and convective coolers. One 3-day run was made at 550 psig using a radiant cooled diptube with all of the syngas being directly quenched. Pittsburgh No. 8 coal was gasified during all of the 350 psig runs while Powhatan coal was gasified during the 550 psig run. High purity oxygen was used during the 550 psig run and during two of the 2-day runs. Air was used during all of the other runs.

During the eight PDU runs, 26 different gasifier tests were conducted; nine external sorbent tests also were conducted. In-situ desulfurization tests were conducted using iron oxide. External high temperature desulfurization tests were conducted using calcium sorbents and mixed metal oxides. Also, gasification data were obtained with air in order to compare the gasifier efficiency to that obtained with pure oxygen. During these runs, 12 external mixed metal oxide sorbent tests also were done.

Iron oxide was used as an in-situ desulfurization sorbent during oxygen-blown gasification to study the effects of increased residence time on syngas desulfurization, and during air-blown gasification to determine the effectiveness of in-situ desulfurization in that mode of operation. The increased residence time in oxygen-blown syngas did not improve the desulfurization above the nominal 50 percent achieved in the

Phase I testing and had the unexpected and undesired effect of making the slag produced a hazardous waste. This was not a problem in the Phase I testing. The in-situ desulfurization testing in air-blown gasification effected a maximum desulfurization of 27 percent, which is insufficient for commercial application.

Calcium based sorbents were tested at ~1700°F in the radiant cooler of the low pressure solids gasification unit during both air-blown and oxygen-blown gasification. In air-blown gasification, a nominal 63 percent solids dolomite slurry was injected into the radiant vessel using an atomizing nozzle and nitrogen. Unfortunately, the size and geometry of the radiant vessel made entrainment of the dolomite spray difficult, and all of the various attempts resulted in plugging of the radiant vessel with dolomite deposits before steady state operations were achieved. Data from these tests did show that dolomite can remove at least 70 percent of the H₂S in air-blown syngas.

To circumvent the equipment limitations, fixed beds of dolomite and limestone were tested during oxygen-blown gasification. In both of these runs the fixed bed was mounted in the radiant vessel. The fixed bed dolomite run achieved 82 percent desulfurization of the syngas, but plugged with fine ash and char after nine hours of operation. The fixed bed lime run was unsuccessful due to equipment problems.

Because of the difficulties encountered due to equipment limitations, further testing of calcium based external sorbents has been deferred pending the results of the economic studies. If the economic studies indicate that calcium sorbents are economically viable then a dry feed system will be considered to test calcium based external sorbents.

Data on gasifier performance in air-blown and oxygen-blown modes of operation were compared. The comparison revealed that air-blown gasification requires 20 percent more oxygen than oxygen-blown gasification for the same carbon conversion and that the product syngas has less than one third of the heating value of the oxygen-blown syngas. The air feed also had to be preheated to temperatures between 800 and 1000°F to operate the gasifier at temperature necessary for efficient slag removal while minimizing the production of carbon dioxide. These differences have a significant impact on the economics for air-blown gasification in terms of equipment size, number of gasification trains and operating cost.

One additional in-situ run is planned. This run will use both iron oxide and limestone as in-situ additives. Limestone was originally planned for testing as an in-situ additive during Phase I, but bench scale tests showed that the slag produced was too viscous to flow out of the gasifier due to formation of

calcium silicate phases in the slag. More recent theoretical studies indicate that the iron oxide should reduce the slag viscosity enough that, even with the formation of calcium silicates, the slag will flow out of the gasifier.

During the Phase II testing, we evaluated several sorbents produced by United Catalyst Incorporated in single pass sulfidation with air-blown gasification syngas. The sorbents tested were: two zinc titanates with Zn/Ti ratios of 0.8 (L-3014) and 1.5 (L-3140) and a zinc ferrite (T-2465). The L-3140 sorbent has the same formulation as the L-3196, but is an earlier batch. All three sorbents worked well, reducing the H₂S level in the syngas to less than 50 ppm. Problems previously experienced with zinc ferrite exposed to oxygen-blown syngas, such as loss of crush strength due to over-reduction, and high temperature excursions due to the methanation reaction, did not occur. There was a significant amount of water-gas shifting across the beds for all three sorbents tested. Based on the results of the testing in air-blown and oxygen-blown syngas, the 1.5 Zn/Ti zinc titanate sorbent (L-3140) is the best of the sorbents tested for use with Texaco syngas.

The Phase I economic studies showed that cycle life for mixed metal oxide sorbents is a critical factor in determining their commercial viability. After we determined that the 1.5 Zn/Ti zinc titanate was the best sorbent for use with Texaco syngas, a regenerable bed reactor was designed to enable us to obtain multicycle on-line data. This reactor is in the process of being built. We plan to operate the reactor with zinc titanate through 10 to 20 cycles of sulfidation and regeneration during the 1992 fiscal year as part of the ongoing Phase II work.

One additional run in the existing sulfidation only sorbent reactors is scheduled to determine the optimum space velocity for sulfiding the 1.5 Zn/Ti zinc titanate sorbent. In this run, all three sorbent reactors will be loaded with the L-3140 sorbent and each bed will be operated at one of the following space velocities: 2000, 4000, and 8000 hr⁻¹.

Texaco, as a subcontractor to Westinghouse, provided syngas for testing a high temperature ceramic crossflow filter during most of the tests done at 350 psig. The filter was important for the mixed metal oxide sorbent testing, since it removed particulates upstream of the fixed beds. This kept the beds from being plugged with particulates. The filter will provide the same protection for the regenerable bed when it is operated.

Based on the above testing the following conclusions were reached:

- * The in-situ addition of iron oxide as a desulfurization sorbent during oxygen-blown gasification can reduce the H_2S level in the syngas by 50-60 percent, depending on the gasifier temperature and iron oxide dosage.
- * The in-situ addition of iron oxide as a desulfurization sorbent during air-blown gasification is capable of reducing the H_2S level in the syngas by only 27 percent and is probably not worth further development.
- * Injection of dolomite slurry into the hot syngas from air-blown gasification can remove at least 70 percent of the sulfur in the syngas.
- * Dolomite can remove at least 82 percent of the sulfur in syngas when operated as a fixed bed during oxygen-blown gasification.
- * Air-blown gasification requires approximately 20 percent more oxygen than oxygen-blown gasification for the same carbon conversion.
- * Air-blown gasification requires air preheat in the 800°F to 1000°F range to avoid over-conversion, and the resultant loss in efficiency at the temperatures required to remove slag from the gasifier.
- * External regenerable sorbents such as zinc ferrite and zinc titanate are capable of removing more than 99 percent of the sulfur in the syngas.
- * Zinc ferrite is unsuitable for oxygen-blown gasification, because it loses strength and catalyzes the methanation reaction.
- * Zinc titanate is suitable for both oxygen-blown and air-blown gasification.
- * The 1.5 Zn/Ti zinc titanate (L-3140) is the preferred sorbent for use with Texaco syngas due to its superior performance in oxygen-blown syngas and its higher zinc content compared to the 0.8 Zn/Ti zinc titanate (L-3014).
- * Multi-cycle testing of the 1.5 Zn/Ti zinc titanate in true process gases is needed to determine its' cycle life.

Task 3. Process Economic Studies

The Phase 2 process optimization studies were intended to provide guidance for the design of the integrated PDU by revealing those hot gas cleanup configurations having the greatest potential for commercialization as part of a Texaco-based grass roots IGCC plant. To date, nine study cases have been completed. The results of these studies, which were first attempts at integrating hot gas cleanup with Texaco's gasification process, showed that IGCC power plants based on the Texaco gasifier using hot gas cleanup are more efficient than similar plants using conventional cold gas cleanup. Improvements in overall plant heat rates of up to 400 Btu/kWh were calculated. However, all of the plants were more expensive to build and operate than the cold gas cleanup base case.

We had originally hoped that the results of the nine studies would provide clear guidance in selecting an economically viable process configuration to be demonstrated in an integrated PDU at Montebello (i.e. Phases III through V). However, because none of the configurations studied resulted in a plant which was less expensive than the cold gas cleanup base case, we felt that additional studies were necessary.

In order to improve the economics and select the optimum configuration of hot gas cleanup process steps, we initiated twelve additional cases incorporating process modifications which should dramatically reduce the costs. The purpose of these studies is to find the best way to reduce plant costs and still maintain high plant efficiency. This work is ongoing and is expected to be completed along with the remaining Phase II work in early 1992.

Task 4. Advanced Instrument Testing

Four advanced instruments, developed by DOE for fossil energy processes, were selected for testing in the PDU at Montebello: a Fiber Optic Alkali Monitor (FOAM), a Classical Scattering Aerosol Spectrometer (CSAS), a Fiber Optic Fluorescence Thermometer (FOFT) and an Inductively Coupled Plasma Spectrometer (ICPS).

During the time period covered by this topical report, only the FOAM was tested. A high temperature, high pressure, isokinetic sampling train was constructed which allowed hot syngas samples to be continuously extracted from the process piping either upstream or downstream of the high temperature ceramic filter.

The FOAM measured total alkali concentrations in the range of one to 100 ppm at the inlet of the ceramic filter. When the filter was performing well, outlet total alkali concentrations below 20 ppb were measured. This level of alkali is thought to be acceptable for combustion turbines.

Tests are planned on the CSAS, FOFT and ICPS during the continuing Phase II PDU tests.

Task 5. Phase II Topical Report

A written report that assesses the technical progress and potential success of the work efforts under Phase II of the Cooperative Agreement was requested. This topical report fulfills that requirement for the work completed through January 1991.

Future Work

Based on the results summarized above, the following tasks were proposed for the 1992 fiscal year:

1. Complete the Process Optimization Studies
2. Conduct Zinc Titanate Regenerable Fixed Bed PDU Testing
4. Test the Advanced Instruments When Available
5. Prepare a Topical Report

2. INTRODUCTION

2.1 Objective

The overall objective of the project described in this report is to develop and test an improved, high efficiency, integrated coal gasification power generation system on a PDU scale. The work includes investigations of hot desulfurization and hot gas cleanup as applied to the Texaco Coal Gasification Process.

2.2 Proposal Basis

To help achieve the goal of clean, low cost power generation from coal, Texaco submitted an unsolicited proposal in July 1986 to the Morgantown Energy Technology Center (METC) of the Department of Energy (DOE) to develop a high temperature process for sulfur removal in the Texaco Coal Gasification Process (TCGP).

The proposal resulted in a Cooperative Agreement with the DOE that was awarded on September 30, 1987. Texaco then began a 5-year test program with costs shared by Texaco and the U.S. Department of Energy. In this program, Texaco will optimize a high efficiency, low cost power generation system identified by economic studies, and demonstrate all parts of the system from coal grinding through electric power generation in an integrated pilot plant to achieve the following goals:

- * Develop and demonstrate in-situ desulfurization of syngas produced from a high sulfur eastern bituminous coal using the TCGP with oxygen and air.
- * Develop and demonstrate a high efficiency integrated power generating system on a pilot plant scale that includes coal preparation, Texaco coal gasification, high temperature sulfur removal, high temperature and high pressure syngas clean-up and a gas turbine, if available.

In addition, it is also planned to achieve the following secondary goals:

- * Test advanced instruments developed by the DOE for coal conversion processes.
- * Test external high temperature sulfur removal sorbents using a slip stream of syngas generated during pilot plant operations. These tests will provide for backup or polishing for the in-situ desulfurization as required.

2.3 Five Year Plan

The project is subdivided into five phases, with each phase originally corresponding to approximately one year of work. The phases are:

- PHASE I - Preliminary Desulfurization Research
- PHASE II - Process Optimization
- PHASE III - Integrated System Preparation
- PHASE IV - Integrated System Commissioning
- PHASE V - Integrated PDU Tests

The Phase I work was completed in 1988 and reported previously in the Phase I Topical Report that is summarized below.

The Phase II work, which was completed through November 30, 1990, is described in detail in this report. The work is continuing and will include further process economic studies and the design and operation of a regenerable zinc titanate bed. Completion of this phase has taken much longer than the one year originally planned due to operational problems and changes in scope. We expect to complete this phase during fiscal year 1992.

Completion of Phases III through V will depend on identifying a set of process steps in Phase II that yield both a higher efficiency process and a lower cost process than conventional cold gas cleanup.

2.4 Summary of Phase I Testing Results

The preliminary desulfurization research in Phase I consisted of six tasks as follows:

1. Theoretical Studies
2. Bench Scale Testing
3. PDU Scoping Test
4. Advanced Instrumentation Evaluation
5. Continuation Proposal for Phase II
6. Phase I Topical Report

The results of theoretical studies and bench scale testing were used to select both in-situ and external high temperature desulfurization sorbents for evaluation on a process development

unit (PDU) scale. The testing was conducted at three different locations:

1) Montebello Research Laboratory (MRL)

Literature searches and slurry rheology testing with in-situ sorbents added to coal water slurries.

2) Texaco Research Center, Beacon (TRCB)

Bench scale examination of in-situ sorbent/slag systems, and slag viscosity determinations; also a literature search and theoretical calculations.

3) Massachusetts Institute of Technology (MIT)

Bench scale testing of external sorbents, including multicycle testing of sulfidation and regeneration.

Based on the results of the theoretical studies and the bench scale testing, two different in-situ sulfur removal sorbents (iron oxide and sodium carbonate) and four different external sulfur removal sorbents (zinc ferrite/T-2465, zinc ferrite/E-13A, zinc copper ferrite/L-2952, and zinc titanate/L-3014) were selected for PDU testing. Limestone, initially selected for use as an in-situ sorbent, was rejected when the bench scale testing indicated that the calcium would react preferentially with the silica in the slag instead of with the H_2S in the syngas.

The PDU used at MRL was operated at 350 psig using high purity oxygen, with most of the syngas generated going through radiant and convective coolers. The in-situ sorbents were mixed with the coal-water slurry during slurry preparation. The external sorbents were loaded into fixed beds, and up to three beds were run in parallel in the convective cooler using slip streams of syngas.

A 1-day shakedown run and two 3-day screening test runs, using Pittsburgh No. 8 coal (2.1 wt. percent sulfur), and one 3-day run using Powhatan coal (5.1 wt. percent sulfur) were made. The PDU tests showed that a nominal 50 percent reduction of H_2S in the syngas was achievable at a normal gasifier operating temperature with both high and low sulfur containing syngas using Fine-OX (high purity iron oxide) as the in-situ sulfur sorbent. Higher levels of desulfurization were achieved by lowering the gasifier temperature. However, this resulted in lower carbon conversion that produced too much char to be handled during the PDU testing. The slag generated during the tests was stable, and the sulfur in the slag passed the proposed EPA leachability test.

A higher H₂S reduction in the syngas of about 60 percent was achieved at a normal gasifier operating temperature using iron oxide plus a high dosage of soda ash (high purity sodium carbonate), which was added to the Pittsburgh No.8 coal slurry. However, the slag generated was pyrophoric, and there were solids handling and plugging problems due to the extremely small particle size char produced that tended to agglomerate with condensed sodium compounds. A low dosage of sodium carbonate was tested during the Powhatan coal run and showed no improvement in H₂S reduction. Because of these results, further testing of sodium carbonate was abandoned.

The external sulfur removal sorbents were evaluated in single pass sulfidation using a slip stream of 1000-1300°F syngas, with H₂S concentrations between 1,600 and 14,500 ppmv, and space velocities between 900 and 2100 hr⁻¹. The H₂S concentration was constant throughout each run; the variation in H₂S level is a result of the concurrent in-situ sorbent testing and the different coals used. The following conclusions were made based on the performance of the external sorbents:

- * All four sorbents evaluated achieved an H₂S removal of greater than 99.9 percent before breakthrough.
- * The ferrite sorbents evaluated are not suitable for use with the Texaco oxygen-blown syngas because of a severe loss in crush strength that occurred after only a single sulfidation, and the catalyzing of the methanation reaction.
- * Zinc Titanate retained more of its crush strength and had a higher sorbent utilization in sulfidation only testing.
- * The sorbent utilization for zinc titanate was mass transfer rate limited.

Based on the results of the Phase I testing, the following tests were planned for Phase II:

- * Test iron oxide as an in-situ sorbent with increased slag/syngas contact time to achieve a closer approach to equilibrium, during air-blown and oxygen-blown gasification.
- * Test calcium based sorbents (limestone and dolomite) injected down stream of the gasifier reaction chamber at a point after the slag has been separated from the syngas. These tests will be made primarily during air-blown gasification.

- * Test external sorbents during air-blown gasification of Pittsburgh No. 8 and Powhatan coals using a zinc titanate formulation containing more zinc.

2.5 Phase II Work Breakdown

The Phase II research reported in this topical report consists of five tasks as follows:

1. Bench Scale Testing
2. PDU Scoping Tests
3. Process Economic Studies
4. Advanced Instrument Testing
5. Phase II Topical Report

A Gantt chart showing the initiation and completion time of each task and major subtasks is shown in Figure 2-1.

Bench scale testing is being done at the Research Triangle Institute. Two studies have been completed. The first study was a performance comparison of 0.8 and 1.5 Zn/Ti zinc titanate sorbents. The work is summarized in Section 3.1 and reported in full in Volume two of this report. The second study examined the effects of chloride on the 1.5 Zn/Ti zinc titanate sorbent during multiple cycles of both sulfidation and regeneration. This work is summarized in Section 3.2 and reported in full in Volume three of this report.

A third study is planned as part of the on-going Phase II work. This study will investigate the effects of temperature and composition of the reductive regeneration gas on zinc loss for the 1.5 Zn/Ti zinc titanate sorbent. The study will be completed in fiscal 1992 and reported in the next topical report.

Eight Phase II PDU scoping runs have been completed. During these runs, we investigated the use of iron oxide as an in-situ sorbent, and calcium and mixed metal oxides as external sorbents. The differences between air-blown and oxygen-blown gasification also was investigated. This work is reported in Sections 3.3 and 3.4.

Four additional PDU scoping runs are planned for Phase II. During these runs, we will investigate the use of a calcium\iron mixture as an in-situ sorbent and we will evaluate the performance of 1.5 Zn/Ti zinc titanate in a regenerable bed over several cycles of sulfidation and regeneration. These runs will be conducted between January 1991 and March 1992 and will be reported in the next topical report.

Figure 2-1. Phase II Gantt Chart

Nine process economic case studies with several subcases have been completed as part of the Phase II work. The studies are reported in Section four of this report. Based on the results of these case studies, 12 additional cases are planned. These cases will be completed in fiscal 1992 and reported in the next topical report.

Four advanced instruments, developed by DOE, were selected for testing in the PDU at Montebello: a Fiber Optic Alkali Monitor (FOAM), a Classical Scattering Aerosol Spectrometer (CSAS), a Fiber Optic Fluorescence Thermometer (FOFT) and an Inductively Coupled Plasma Spectrometer (ICPS). Only the FOAM has been tested so far during the Phase II work. This testing is reported in Section 3.5. The other three advanced instruments will be tested during the remaining Phase II runs as they become available. That testing will be reported in the next topical report.

This topical report assesses the technical progress and potential success of the work efforts under Phase II of the Cooperative Agreement for the work completed between January 1, 1989 and January 1, 1991. All work completed after December 1, 1990 will be reported in the next topical report.

2.6 Process Description

In the last several years, the Texaco Coal Gasification Process (TCGP) has been widely accepted as a leading second generation coal gasification process. Several commercial scale facilities have been built. These are listed in Table 2-1.

The TCGP is a continuous, entrained flow, pressurized gasification process for converting coal, coal derived materials, or other suitable carbonaceous feedstocks into syngas, which is composed primarily of hydrogen and carbon monoxide.

The solid feedstock is ground and fed as a concentrated water-slurry into a refractory-lined pressure vessel through a special burner, where it is mixed with an oxidant, such as pure oxygen or air, and reacts to form syngas. The amount of oxygen or air is adjusted to obtain a temperature within the gasifier that is above the fluid temperature of the ash contained in the feedstock.

Under these conditions, the gasification reactions occur rapidly, and 90 to 99 percent of the carbon contained in the feedstock is gasified in a few seconds. Hot gases exit the gasifier with molten slag and are cooled in one of two alternate modes: the direct water quench mode, or the gas cooler mode. The schematic flow diagrams for both modes of the Texaco Coal Gasification Process can be seen in Figure 2-2.

Table 2-1. Texaco Coal Gasification Process Plant Summary

<u>Owner</u>	<u>Size</u>	<u>Location</u>	<u>Capacity</u>	<u>Start-up</u>	<u>Heat Recovery</u>	<u>Product</u>
RAG/RCH	Demonstration	W. Germany	165 TPD	1978	Gas Cooler	Oxo-Chemical
DOW	Demonstration	Louisiana	400 TPD	1979	Gas Cooler	Electric Power
TVA	Demonstration	Alabama	190 TPD	1982	Direct Quench	Ammonia
Tennessee-Eastman	Commercial	Tennessee	900 TPD	1983	Direct Quench	Acetic Anhydride
Cool Water Power	Commercial	California	1,000 TPD	1984	Gas Cooler	Electric
Ube Ammonia	Commercial	Japan	1,650 TPD	1984	Direct Quench	Ammonia
SAR	Commercial	W. Germany	800 TPD	1986	D. Q./Gas Cooler	Oxo-Chemical Hydrogen
LuNan	Commercial	China	360 TPD	1992	Direct Quench	Ammonia
Shougang	Commercial	China	900 TPD	1992	Direct Quench	Fuel Gas

In the direct water quench mode, the hot gases containing slag are cooled by direct contact with water in a quench chamber that is maintained at full gasifier pressure. In the quench chamber, the molten slag is rapidly solidified and the hot gases leaving this quench chamber are saturated with water vapor. These hot gases are scrubbed with additional hot water for removal of the last traces of particulate matter and may be passed to a shift converter where the carbon monoxide contained in the gas is converted to additional hydrogen. This mode is particularly attractive for those applications where pure hydrogen is required for ammonia or petrochemical synthesis.

The slag from the coal remains in the water where it settles rapidly and is withdrawn periodically through a water-sealed lockhopper system. Char and some fine particles present in the circulating water are removed by passing the water stream through a settler. Material recovered in the settler may be discarded or recycled to prepare additional slurry feed for the gasifier. The material removed through the lockhopper system can be separated into a coarse and a fine fraction. The coarse slag, which is normally 99 percent or more ash, is removed from the system and discarded. The fine slag, which usually contains some unconverted carbon, may be fed back to the slurry preparation system or discarded with the coarse fraction of the slag.

Figure 2-2. Texaco Coal Gasification Process Flow Diagram

Water recovered from all of the streams is recycled to the process or to slurry preparation, and the only water discharged from the process is that required to maintain an acceptable level of total dissolved solids in the circulating water. The buildup of solids in this water stream is determined by the composition of the non-hydrocarbon material in the coal feed.

In the alternate gas cooler mode, the hot heterogeneous stream leaving the gasifier is directed downward through a radiant syngas cooler where high pressure steam is generated as the hot gases are cooled. This cooler is designed to cool the gases and slag in the gas stream to a temperature well below the softening point of the coal ash. Most particulate matter in this stream is collected in a water-filled chamber at the bottom of the radiant syngas cooler. Hot gases containing a small fraction of the particulate matter are then passed through a convective syngas cooler where additional heat is recovered. At the exit of the convective syngas cooler, the gases are scrubbed with hot water for final particulate removal and the resulting syngas is ready for further treatment, normally sulfur removal. This alternate mode would typically be selected for process sequences in which methanol or fuel gas is the desired end product. The slag, fines and water are handled in the same manner as in the quench mode of operation.

The syngas, after being passed through a wet scrubbing system to remove particulates, is cooled to ambient or lower temperatures prior to any conventional desulfurization. In a Texaco based integrated coal gasification combined cycle (IGCC) electric power generation system, the Cool Water plant for example, the syngas is routed to a Selexol unit for acid gas removal. The acid gas consists primarily of carbon dioxide (CO_2), hydrogen sulfide (H_2S) and carbonyl sulfide (COS). The sulfur constituents are then converted to elemental sulfur in a conventional Claus unit whose tail gas is then treated in a Scot unit for removal of remaining acid gases. The sulfur can be disposed of or sold.

The clean, cool product gas from the Selexol unit is then burned in a conventional combustion turbine to generate electricity after saturation with water for NO_x emissions control. The exhaust gas from the combustion turbine is then used in a conventional heat recovery steam generator (HRSG) to produce steam that is combined with the steam produced by the gasification plant syngas coolers. The combined steam is then used to produce additional electricity with a conventional steam turbine.

2.7 Montebello Research Laboratory Facilities

2.7.1 Pilot Plant Facilities

The Montebello Research Laboratory (MRL) has been the focal point for the research and development work on the Texaco Coal Gasification Process. The research facilities are comprised of three coal gasification pilot plants, two coal grinding units, a syngas cleanup unit and requisite support facilities. The pilot scale gasification plants are relatively large. Each normally gasifies 15 to 20 tons/day of moisture free coal. The size of the pilot units permits testing of commercial type equipment.

One of the three gasification pilot plants is designed to operate at a relatively low pressure of 350 psig and the other two are designed to operate at a maximum pressure of 1200 psig. The two high pressure gasification plants can gasify up to 50 tons/day of moisture free coal at 1200 psig.

Both of the high pressure units utilize direct quench type gasifiers. The syngas generated in these units is cooled by direct contact with water.

The Low Pressure Solids Gasification Unit (LPSGU) is equipped with a syngas cooler in addition to a water quench. For this reason the LPSGU has been used for most of the PDU tests reported here. A developmental Ceramic Cross Flow Filter from Westinghouse has been installed between the radiant and convective coolers and three small fixed bed desulfurization reactors have been installed in the top of the convective cooler. The syngas generated in the low pressure gasifier can be cooled to any temperature between 1800°F and 300°F by using one or more of the following three methods of gas cooling: 1) by direct contact with water in the gasifier quench chamber, 2) by bypassing the direct quench and using both the radiant and the convective cooler, 3) by recycling cold syngas and mixing it with hot syngas at the exit of the radiant cooler. A partial quench also could be simulated by injecting steam at the radiant cooler inlet.

The wet coal grinding unit, which is normally used at MRL, is designed to grind three tons per hour of as-received coal in a rod mill. A process flow diagram of this unit is shown as Figure 2-3.

The syngas generated in the gasification pilot plants is treated for H₂S removal in a Selexol unit and then flared. The sulfur is disposed of by absorbing the H₂S stream from the Selexol unit in caustic, which is discarded after the sulfide is oxidized to a stable form.

Figure 2-3. Schematic Diagram of MRL Coal Grinding System

Most of the units at MRL are operated from a central control building. The operations of the units are supported by a data-processing system. An instrument shop, a welding shop, a machine shop and an electrical shop are all located on-site to provide timely support.

The LPSGU was used for the Phase I and Phase II PDU testing. This unit was used because the syngas cooler made testing of external high temperature sorbents and the Westinghouse Cross Flow Filter possible at minimal cost for unit modifications. The convective syngas cooler dome was replaced with a flange that was modified to support three sorbent beds, and the convective cooling bundle was removed from the cooler to make space for the beds. A tower was build beside the syngas cooler tower to house the cross flow filter and the cyclone that was added later. The cyclone and cross flow filter are connected to the radiant and convective coolers by refractory lined carbon steel pipes.

2.7.2 Analytical Facilities

In addition to the pilot plant facilities mentioned above, MRL has a state-of-the-art analytical laboratory. This laboratory is equipped with instruments that can analyze the solids, liquid and gaseous streams generated in the pilot plants and detect the presence and concentration of trace elements and inorganic compounds that are normally found in coal gasification plants. While some organic analysis can be done, such as for light hydrocarbons in the gas streams, testing for organics, particularly trace quantities, is done in outside laboratories. Table 2-2 summarizes the tests that are normally done at MRL on various pilot unit streams. Tests needed to establish material and energy balances, such as syngas composition, are run periodically, with the frequency set by the length and nature of the pilot plant operations. Tests that define the nature of a stream, such as ash properties or Hardgrove Index, are usually run only once.

Table 2-2. Tests on Pilot Unit Streams

- 1) As Received Coal
Proximate Analysis, Ultimate Analysis, Hardgrove Index
- 2) Coal Slurry (in Slurry Form)
Sieve Analysis, Concentration, pH, Specific Gravity, Viscosity, Miller Number (Dried Sample) Ultimate Analysis, Gross Heating Value, Ash Fusion Temperature, Equilibrium Moisture, Elemental Analysis of Ash
- 3) Raw Syngas and Flash Gas
Gas Chromatograph or Mass Spectrograph Analysis (A, H₂, CO, CO₂, N₂, CH₄, H₂S, COS)
- 4) Waste Water Analysis
pH, NH₄⁺, S=, TSS, TDS, COD, CN⁻, SCN⁻, Na⁺, K⁺, COOH, Br⁻, NO₃⁻, PO₄⁼)
- 5) Clarifier Feed
TSS, TDS, pH
- 6) Clarifier Bottoms
% Solids, Sieve Analysis, Ultimate Analysis, Settling Test, Elemental Analysis of Ash
- 7) Coarse Slag, Slag Fines
% Solids, Ultimate Analysis, Apparent Density, Bulk Density, Sieve Analysis, Fusion Temperature, Settling Rate (Fines Only), Elemental Analysis of Ash
- 8) Slag Fines-Water Slurry
TDS, pH, Cl⁻, S=, NH₄⁺

Tests will be run by ASTM methods if applicable. Supplementary test methods have been developed or adopted by Texaco as necessary.

3. PHASE II TEST RESULTS

3.1 RTI Bench Scale Zinc Titanate Sorbent Testing

Two formulations of zinc titanate were evaluated during five cycles of sulfidation and regeneration in both simulated air-blown and oxygen-blown gasification syngas. A 0.8 Zn/Ti sorbent (batch L-3014) and a 1.5 Zn/Ti sorbent (batch L-3196), both from UCI, were tested. The L-3196 sorbent is similar to the L-3140 sorbent used at MRL. The L-3196 was produced at a later date using the same fabrication method and raw materials as the L-3140 sorbent, to meet the additional sorbent demand. The sulfidations were performed at 350 psig and 1300°F using simulated Texaco syngas and the regenerations were performed at 135 psig and temperatures between 1247°F and 1436°F using nitrogen diluted air. Sorbent L-3196 achieved higher sulfur loadings than sorbent L-3014 due to its higher zinc content. The L-3196 sulfur loading was 18.7 percent higher in simulated oxygen-blown syngas and 28.1 percent higher in simulated air-blown syngas.

The sorbents were returned to Texaco after the fifth regeneration for additional testing. Some of each sorbent was sent to Texaco's Research Laboratory in Beacon, New York for phase analysis and measurement of crush strength and sulfur loading. A summary of these data is shown in Table 3-1.

Zinc titanate in the L-3014 sorbent appears primarily as $2\text{ZnO} \cdot 3\text{TiO}_2$. In the L-3196 sorbent, zinc titanate is in the form of $2\text{ZnO} \cdot \text{TiO}_2$. X-Ray Diffraction data revealed another form of zinc titanate in the sulfided and regenerated samples: $\text{ZnO} \cdot \text{TiO}_2$. This form appeared in the samples from the bottom of the bed (syngas inlet) in both simulated air-blown and simulated oxygen-blown gasification tests. The lower bed samples, where the largest amount of sulfidation normally takes place, had the largest amount of original material converted to $\text{ZnO} \cdot \text{TiO}_2$. The samples from the top of the bed were still in the form of the original sorbent.

Sulfidation of the sorbents normally yields zinc sulfide and titanium oxide. Regeneration of the sorbents would, under optimum conditions, return the sorbents to their original zinc titanate form. A small amount of titanium oxide still existed in the L-3014 sorbent after the five test cycles (none was detected in L-3196). This is not surprising as L-3014 is the sorbent with the higher titanium content.

There appears to be a general reduction in the crush strength from the top to the bottom of the sorbent bed. However, because of the variability in the crush strength measurements, it is difficult to determine the true magnitude of this trend. All of the samples retained their original shape, indicating that after

Table 3-1. New and Regenerated Zn/Ti Sorbents From RTI Testing

<u>Sorbent: L-3014 (Zn/Ti=0.8)</u>						
	<u>Unused</u>	<u>Simulated Air-Blown Syngas</u>			<u>Simulated Oxygen-Blown Syngas</u>	
Sample Bed Section	-	1	3	4	1	5
Relative Phase Concentrations,						
2ZnO·3TiO ₂	3	3	1	1	3	2
2ZnO·TiO ₂	1	0	0	0	0	0
ZnO·TiO ₂	0	1	2	2	0	2
TiO ₂	1	1	1	1	0	1
Crush Strength, lbs.	36.8+	26.1	27.3	15.2	25.5	17.5
Pore Volume, cc/gm	0.396	0.386	0.363	0.325	0.393	0.363
Surface Area, m ² /gm	4.3	4.0	4.1	4.0	3.7	3.0

<u>Sorbent: L-3196 (Zn/Ti=1.5)</u>							
	<u>Unused</u>	<u>Simulated Air-Blown Syngas</u>			<u>Simulated Oxygen-Blown Syngas</u>		
Sample Bed Section	-	2	3	5	1	3	5
Relative Phase Concentrations,							
2ZnO·3TiO ₂	1	1	0	0	1	1	0
2ZnO·TiO ₂	3	3	2	2	3	2	2
ZnO·TiO ₂	0	0	1	2	0	1	2
TiO ₂	0	0	0	0	0	0	0
Crush Strength, lbs.	32.5	32.8	18.9	10.3	39.1	27.1	22.3
Pore Volume, cc/gm	0.385	0.337	0.374	0.342	0.367	0.346	0.333
Surface Area, m ² /gm	2.7	2.7	2.5	2.4	2.9	2.3	2.1

Note: Crush strength is the average of 6 tests. A plus sign after the number indicates there was at least one full scale (50 lbs) reading used in the average.

five cycles, the sorbents still possessed sufficient strength to prevent disintegration. The pore volumes and surface areas exhibit the same trend: a reduction in these values from the top to the bottom of the bed.

The following conclusions are based on the above testing:

1. Both zinc titanate sorbents performed well with simulated air-blown and simulated oxygen-blown syngas.
2. Up to 60 percent of theoretical sulfur capacity was achieved by both sorbents with a bed height to diameter ratio of 5 at a wet gas space velocity of approximately 2000 hr⁻¹.
3. The sorbents did not show a statistically significant decline in either sulfur capacity or crush strength over five cycles.
4. Due to its higher capacity, L-3196 is preferred to L-3014 for commercial application.

The RTI report is published in full as volume two of this report.

3.2 RTI Bench Scale Testing of the Effects of Chloride on Zinc Titanate

There was a concern that ZnO may react with chloride in the syngas to form zinc chloride. This could lead to accelerated zinc loss from the sorbent. To evaluate this possibility a series of three ten-cycle tests was run in a thermogravimetric reactor (TGR) at RTI. The sorbent used in all three tests was the 1.5 Zn/Ti zinc titanate (UCI L-3196). The TGR was loaded with five pellets for each test, one pellet on the balance beam and four off to the side in the reactor. This allowed sorbent sampling at five points during each test.

Simulated oxygen-blown syngas was used in all tests. The TGR was cycled through reduction and oxidation in each cycle. Sulfidation and regeneration were done at 700°C (1292°F). The first test had no HCl in the syngas. The second test had 500 ppm of HCl in both the sulfidation and reductive regeneration gas. The third test was identical to the second test except the regeneration gas composition was changed from two percent O₂ and 98 percent N₂ to two percent O₂, 48 percent N₂, and 50 percent steam.

The following conclusions were drawn from the above testing:

1. A chloride level of 500 ppmv does not appear to have a deleterious effect on the sulfur capacity of zinc titanate sorbent over 10 cycles of testing at 700°C in the presence of simulated Texaco oxygen-blown syngas.
2. Sorbent regeneration removes residual chloride, thus much of the chloride may appear in the regeneration off-gas.

3. The crush strength of the sorbent is not affected at 700°C by chloride.
4. Significant zinc loss from the L-3196 sorbent occurred over 10 cycles at 700°C. The Zn-to-Ti ratio dropped from about 1.4 to 1.2.
5. The sorbent became significantly more reactive in later cycles, presumably due to opening of the porous structure when zinc evaporates. This results in increased effective utilization over 10 cycles in spite of zinc loss.
6. The zinc loss was about 30 percent greater over 10 cycles when the regeneration gas contained 50 percent steam than when it contained no steam.

The RTI report is published in full as volume three of this report.

3.3 PDU Sorbent Testing - Iron Oxide In-situ & Calcium External

3.3.1 Pilot Plant Equipment and Procedures

The Phase II PDU tests were conducted in the MRL Low Pressure Solids Gasifier (LPSGU) and the High Pressure Solids Gasifier II (HPSGUII). The HPSGUII gasifier was used for the extended residence time iron oxide run and the unit is described in the Phase I Topical Report. It is a direct quench gasifier that is capable of operating at pressures to 1200 psig. All of the other runs were done in the LPSGU gasifier and used the syngas cooler and other equipment attached to the low pressure gasifier.

Low Pressure Solids Gasification Unit

The LPSGU is shown schematically in Figure 3-1, including modifications to allow external high temperature desulfurization testing on a slip stream of syngas. The LPSGU normally operates at 350 psig and gasifies 15-20 tons/day of coal. When oxygen (99.75 vol. percent purity) is used as the oxidant, the oxygen is heated to about 250°F to maintain a constant orifice flowmeter temperature. The oxygen is purchased and stored as a liquid, which is pumped up to pressure and vaporized with steam prior to introducing it into the gasifier.

Figure 3-1. L.P.S.G.U. Process Flow Diagram

The slurry, which is made in the coal grinding and slurry preparation unit, is pumped to the gasifier burner where it is mixed with oxygen. The mixture then reacts in the gasifier reaction chamber that is normally preheated to 2000°F to initiate the reactions.

The normal operating procedure is to draw all of the reaction products (syngas, char and slag) after start-up of the LPSGU through the internal quench chamber where they are cooled by direct contact with water. The LPSGU normally reaches steady state four to five hours after start-up. The syngas, which contains very little slag, is then gradually diverted to the syngas coolers. This operation usually takes another four to five hours to reach the target conditions. Therefore, the time needed for the LPSGU to reach specific target conditions will be eight to ten hours after start-up during the PDU testing. Under normal LPSGU operating conditions, approximately 15-20 vol. percent of the total syngas generated is drawn through the internal quench chamber of the gasifier and 80-85 vol. percent of the total syngas generated is drawn through the syngas coolers. However, this distribution can vary, depending on the temperature desired at the inlet to the external sorbent beds.

The operation of the LPSGU in the air-blown gasification mode is substantially the same as in the oxygen-blown gasification mode, with the following exception. The air is preheated to a temperature in the 800 to 1200°F range using a series of three heaters. A schematic of the air feed system designed and built specifically for this project is shown in Figure 3-2. The coal and air feed rates are set so that the same volume of syngas as in oxygen-blown gasification is produced.

The majority of the char and slag that exits the gasifier and part of the syngas are drawn into the water bath in the quench chamber below the gasifier. The slag and char that settle in the internal quench chamber are removed through a lockhopper system. The lockhopper blowdown solids are screened into coarse and fine fractions. The coarse and fine slag are weighed, sampled, and discarded periodically. The internal quenched syngas exits the quench chamber and is subjected to an additional stage of water contact in a scrubbing system to remove substantially all the entrained solids from the product gas. The product gas is then mixed with the quenched syngas from the external quench chamber before being routed to the Selexol unit. In this program all of the high temperature desulfurization is done before the syngas is quenched.

The remainder of the syngas from the gasifier, which normally contains very little slag, is drawn through the horizontal refractory-lined transfer line connecting the gasifier with the slag knock-out pot (SKOP).

Figure 3-2. Air Preheat System

The majority of the small amount of slag and char that is entrained in this syngas stream is separated from the syngas in the SKOP. A small amount of syngas is normally drawn through the bottom quench chamber of the SKOP to help draw any entrained slag out into the quench chamber below the SKOP, where it is collected in water. The bulk of the syngas is directed upwards to the radiant syngas cooler.

The bottom portion of the radiant syngas cooler has a water jacket designed to cool syngas to about 1400°F under normal operating conditions. The syngas exiting the jacketed portion of the radiant syngas cooler goes to the Westinghouse Crossflow Filter or bypasses the filter depending on the bypass valve position. The syngas from the filter or bypass is drawn through the convective syngas cooler where it is further cooled by the water circulating through the water jacket of the convective syngas cooler.

The temperature of the syngas leaving the radiant syngas cooler can be adjusted by varying the syngas throughput or by injecting recycle cooled syngas. The cooling capacity of the radiant cooler has been decreased for this project by shielding 3/5 of the water wall with a refractory sleeve (see Figure 3-3). This enabled us to test the external sorbents at the desired temperature range in the convective vessel with the gas flowrate limits imposed by the Westinghouse Crossflow filter. For the dolomite injection testing, a high temperature cyclone was installed between the radiant vessel and the crossflow filter to handle the increased solids loading in the syngas.

A slip-stream of 1000-1300°F syngas may be fed to each of three parallel fixed sorbent beds for external high temperature desulfurization testing. The three beds, which are installed in the top of the convention syngas cooler, are surrounded by the flowing hot syngas leaving the radiant syngas cooler. This design ensures near isothermal operations.

The syngas from the water jacketed section of the convective syngas cooler is cooled further in the external quench pot by direct contact with quench water. The syngas then is water scrubbed and combined with the internal quenched syngas and the quenched syngas from the SKOP.

The combined syngas is routed to a Selexol unit for further H₂S removal before being flared. The sulfur is disposed of by absorbing the H₂S stream from the Selexol unit in caustic soda, which is discarded after the sulfide is oxidized to thiosulfate.

The circulating cooling water system of the syngas cooler has a surge tank, centrifugal pumps, cooling water supply lines to the syngas cooler, and an air cooler in series with a double-pipe water cooler to cool down all the water heated in the syngas

Figure 3-3. Radiant Vessel Refractory Sleeve

cooler. The cooling water network supplies water to the syngas coolers under nitrogen pressure to prevent boiling.

The internal quench water, which is used for cooling and scrubbing the syngas, exits the internal quench chamber and is combined with the scrubber water, the SKOP blowdown water, the external quench water, and the condensates from the k.o. pots. The combined (total blowdown) water stream is cooled and then routed to a clarifier. The clarifier allows the suspended particulates in the water to settle. This solid material is collected as a sludge from the bottom of the clarifier, weighed, sampled and discarded. The clarifier overhead water stream then flows to the flash tank where dissolved gases, which evolve during depressurization, are removed. These gases exit as the flash gas stream that is metered and burned in the flare. The flash tank water is recycled to the quench chamber and syngas scrubber. Any water not required to maintain the water level in the flash tank is removed from the system as a purge water stream.

Dolomite Injection Feed System

For the dolomite injection runs, dolomite slurries were prepared in two 250 gallon tanks, which were purchased specifically for this program. These tanks are equipped with pneumatic powered agitators to keep the slurry from settling. From the tanks the slurry is fed to centrifugal pumps, which either recycle the slurry to the tank or circulate the slurry through a belt line. A small flow from the belt line feeds the suction of a four plunger Union TX-10 positive displacement pump using 1/2 inch tubing. From this pump, the slurry is fed through 1/4 inch tubing to an atomizing nozzle. The slurry is atomized using recycle syngas or nitrogen and injected into the radiant syngas cooler. A schematic of the dolomite feed system is shown in Figure 3-4.

3.3.2 Description of Runs

The test program was conducted in three parts. The first part was the long residence time iron oxide run using Powhatan coal and oxygen. The second part was the air-blown gasification testing with and without sorbent addition. Sorbents tested in air-blown gasification included iron oxide, added to the coal slurry, and dolomite/limestone, injected into the radiant cooler. All of the air-blown gasification runs were done using Pittsburgh No. 8 coal. The third part was the testing of dolomite/limestone sorbents in a fixed bed mounted in the radiant cooler during oxygen-blown gasification.

The Phase II PDU test program was started in March 1989. This report covers work done from January 1, 1989 through January 1,

1991. During that time, one 4-day, two 3-day and five 2-day runs were completed. All of the runs were conducted in the LLSGU using Pittsburgh No. 8 coal, except one 3-day run that was effected in HPSGUII using Powhatan Coal. The operating conditions selected for the PDU test runs were based on the results of the Phase I testing, bench scale testing, published literature data, our theoretical studies and advice from our consultants.

Approximately 195 tons of Pittsburgh No. 8 coal and 39 tons of Powhatan coal were gasified. A total of 484 hours of on-stream time was accumulated. There were 26 test periods completed, during which the gasifier temperature and sorbent dosage were varied to investigate in-situ desulfurization and the effects of sulfur sorbents on gasifier performance. A summary of the key operating parameters and results for each test period is shown in Table 3-2.

Run 1. Extended Residence Time with Iron Oxide In-situ Sorbent (3 days)

The HPSGUII gasifier was started on March 28, 1989 using Oxygen and Powhatan coal with Fine-Ox (high purity iron oxide) as the in-situ sorbent. The gasifier was operated at 550 psig.

During the run, the coal and oxygen feed rates were varied to determine if gasifier residence time had any effect on sorbent performance. Two different coal feed rates were used that resulted in a normal syngas residence time and a residence time that was one and one half times longer than normal. A radiant cooled diptube was used in this run in place of the normal water-wall diptube to increase the liquid slag residence time at high temperature before the quench. The results from this run are summarized in Table 3-3.

The first two test periods (A & B) were conducted without any Fine-Ox addition to obtain baseline data for syngas H_2S level. The sorbent dosage shown in Table 3-3 for these test periods is the ratio of iron in the sorbent to sulfur in the raw coal. The difference between the two test periods was the coal feed rate; the period A feed rate was $2/3$ the normal feed rate and period B rate was the normal feed rate.

Test periods C, D, E, and F were completed with a Fine-Ox dosage of 2.5 lbs.Fe/lb.S. The Fine-Ox was mixed into the coal slurry when it was prepared. Periods C and D were performed at $T_o^\circ F$ with period D having increased residence time.¹ Periods E and F were completed with increased gasifier residence time and lower

¹ T_o = base operating gasifier temperature.

Table 3-2. Summary of Phase II Gasification Tests: Key Parameters & Results

Run/ Test Period	Length Run/Test Period (hrs.)	Air Preheat Temp. (deg. F)	Gasifier Temp (deg F)	Sorbent Type/ Dosage *	Vol% H ₂ S In Gas	% Reduct. In H ₂ S
1/	67.5/	O ₂		Fine-Ox		
	8.5	N/A	T ₀	-	1.04	-
	7.0	N/A	T ₀	-	1.15	-
C	10.0	N/A	T ₀	2.5	0.61	47
D	11.0	N/A	T ₀	2.5	0.67	42
E	10.0	N/A	T ₀ -100	2.5	0.55	52
G	7.7	N/A	T ₀ -200	2.5	0.56	51
H	11.7	N/A	T ₀ -200	3.5	0.64	44
2/	104/	AIR				
A	35.0	900	T ₀ +150	-	0.26	-
B	15.8	935	T ₀	-	0.26	-
C	17.0	1050	T ₀ -80	-	0.27	-
D	5.3	965	T ₀ -90	0.25	-	-
E	6.0	850	T ₀ -50	0.26	-	-
F	5.5	850	T ₀ +50	0.25	-	-
3/	66/	Air		Fine-Ox		
A	11.5	1050	T ₀	3.5	0.23	11
B	11.5	1050	T ₀ -100	3.5	0.21	19
C	12.1	1050	T ₀ -180	3.5	0.21	19
D	11.5	1050	T ₀ -200	4.5	0.20	23
E	8.2	950	T ₀ -250	4.5	0.19	27
4/	62/	Air		Dolomite		
A	17.0	1050	T ₀ +50	-	0.30	-
B	9.0	1050	T ₀ +50	2.0	0.09	72**
5/	41/	Air		Dolomite		
A	18	800	T ₀ +50	-	0.30	-
B	9	800	T ₀ +50	1.8	***	-
6/	35.5/	Air		Dolomite		
A	28	930	T ₀ +50	-	0.32	-
B	6	930	T ₀ +50	1.8	****	-
7/	11/	O ₂		Dolomite	0.85	-
A	7	N/A	T ₀ +50	Fixed Bed	0.2-0.15	77-82
8/	17/	O ₂		Lime		
A	2	N/A	T ₀ +50	Fixed Bed	*****	

- * Sorbent dosage is in lbs. active sorbent (i.e. Fe or Ca)/lb S in coal feed.
- ** Most of the dolomite from this run was found in the radiant vessel and slag K. O. Pot.
- *** The H₂S level during this test period varied from .1 to .21 percent in a cyclic manner.
- **** The H₂S level in this period initially dropped to .15% then rose back to .29% and stayed there.
- ***** Due to flow difficulties, the run was never completed.

Table 3-3. Run One In-Situ Desulfurization Test Results

Test Period	Duration Each Test Period (hrs.)	Nominal Slurry Flow Rate (% of norm.)	Nominal Gasifier Temp. (deg. F)	Actual Sorbent Dosage (Fe/S lb/lb)	Syngas* Average H ₂ S Level (%)
A	8.5	68	T ₀	0.54	1.04
B	7.0	100	T ₀	0.49	1.15
C	10.0	100	T ₀	2.07	0.61
D	11.0	68	T ₀	2.16	0.67
E	10.0	68	T ₀ -100	2.06	0.55
F	7.7	68	T ₀ -200	2.25	0.56
G	11.7	68	T ₀ -200	2.17	0.64

* H₂S levels were from the on-line mass spectrometer; the H₂S level in period A increased throughout the test and never reached steady-state.

gasifier temperature, 100° and 200°F lower respectively. The lowest H₂S levels achieved during these test periods occurred in periods E and F. The H₂S concentration was 5,500 to 5,600 ppm; this represents 51 to 52 percent desulfurization.

In test period G, additional iron oxide was added to the slurry, but it did not remain in solution; as a result the actual sorbent dosage was slightly less than that in test period F. The gasifier temperature was maintained at T₀-200°F. The H₂S level in this test period was 6,400 ppm, which represented 44 percent desulfurization. There is no clear trend in the above data.

There were no operational problems with the gasifier during this run, which lasted 66 hours.

The H₂S removal achieved in this run was slightly less than that achieved in run four of Phase I and showed no improvement with longer residence time. The desulfurization levels achieved in both of these runs were significantly higher than the desulfurization levels predicted by theoretical studies and bench scale testing.

Runs 2 & 3, Combined Air Gasification Baseline/Fine Ox (7-days)

The LPSGU was started with Pittsburgh No. 8 Coal and air on July 11, 1989. The unit ran without problem for 35 hours. Then the unit was shut down automatically due to low slurry flow. Inspection of the slurry feed pump revealed foreign material in

the slurry. The slurry in the run tank was screened, and the run tank was modified by placing screens on the tank inlets to prevent this problem from happening in the future. Test period A was completed during the 35 hours of operation.

Test period B was completed in a run that lasted 20 hours. The unit was shutdown because a syngas leak developed in the piping to the filter bypass valve.

Additional slurry, containing 3.5 and 4.5 pounds of Fine-Ox per pound of sulfur in the coal, was prepared. The combined air gasification baseline and Fine-Ox run was restarted on August 7 and was shut down after 103 hours of smooth operations when the slurry was depleted. There were nine test periods completed in the run, four periods without any in-situ desulfurization (air baseline run periods C - F) and five periods with Fine-Ox addition (Fine-Ox run periods A-E). The test periods from the air baseline runs are shown in Table 3-4.

Table 3-4. Run 2 Test Results

<u>Test Period</u>	<u>Air Preheat Temp. (deg. F)</u>	<u>Gasifier Temp (deg F)</u>	<u>Relative Carbon Conversion*</u>	<u>Duration of Each Test Period (hrs.)</u>
A	900	T ₀ +150	1.00	35
B	935	T ₀	1.00	16
C	1050	T ₀ -80	.95	17
D	965	T ₀ -90	.96	6
E	850	T ₀ -50	.98	6
F	850	T ₀ +50	.99	6

* The relative carbon conversions were calculated with test period B as the base period.

The purpose of the air gasification baseline run was to gather data on air-blown gasification for use in the economic studies. This information would allow us to compare the cost of air-blown and oxygen-blown gasification with real gasifier performance data for both modes of operation. The conclusions are discussed in Section 3.3.4 and use data collected from all of the air-blown gasification runs.

The results of the Iron Oxide In-situ desulfurization testing are shown in Table 3-5. The data indicate that a maximum reduction

Table 3-5. Run 3 Test Results

Test Period	Air Preheat Temp. (deg.F)	Gasifier Temp. (deg.F)	Actual FineOx Dosage (Fe/S lb/lb)	Vol% H ₂ S In Gas	% Reduct. In H ₂ S*	Duration of Test Period (hrs.)
A	1050	T ₀	3.0	0.23	12	12
B	1050	T ₀ -100	3.0	0.21	19	12
C	1050	T ₀ -180	3.0	0.21	19	12
D	1050	T ₀ -200	3.7	0.20	23	12
E	950	T ₀ -250	3.7	0.19	27	8

* Relative to average H₂S concentration in the air baseline run (0.26%)

of H₂S in the syngas of 27 percent was achieved, and that increasing the sorbent dosage did increase the amount of desulfurization. However, this level of desulfurization is insufficient for use in commercial application, either by itself or in combination with other hot gas desulfurization methods and therefore does not warrant further investigation. The emphasis in future PDU runs was switched to calcium based sorbents, injected down-stream of the gasifier.

Run 4. Dolomite Injection (2 days)

The LPSGU was modified for injection of dolomite/limestone slurries into the bottom of the radiant vessel (see Figure 3-5). This included installation of a high temperature cyclone between the radiant syngas cooler and the Westinghouse Ceramic Cross flow filter to handle the greatly increased solids loading in the syngas to the filter. The cyclone was designed and built by Anderson 2000 Inc. to remove 90 percent of the total particulates. A drawing of the cyclone is in Appendix F.

A high pressure injection system was built to inject the dolomite slurry into the radiant vessel using a commercial swirl atomizing nozzle (Delvon Swirl-Air, model 32163 with a 707-93 cap). The radiant vessel was modified for the injector by mounting a new flange on the vessel and drilling a hole through the refractory below the water wall to allow the insertion of the injector. The injector was inserted so that the nozzle faced straight up at the center of the radiant cooler (see Figure 3-6).

Dolomite slurry was fed to the injector from tanks mounted on scales to record slurry usage. The slurry was fed to the nozzle

Figure 3-5. L.P.S.G.U. Modified for Dolomite Injection

Figure 3-6. Dolomite Injector

using a positive displacement pump; recycle syngas or N₂ was used as the atomizing media (see Figure 3-4 in section 3.3.1). The system automatically switches from nitrogen to syngas, when the recycle syngas pressure exceeds 600 psig. To protect the injector from the hot syngas there is a cooling water coil around the injector and a layer of refractory on the cooling coil.

The dolomite used for this run was ground to two different average particle sizes, 16.0 microns (coarse) and 8.7 microns (fine), by an outside firm. The analysis of the dolomite is shown in Table 3-6. Slurries were prepared with the coarse and fine dolomite with each in its' own tank. Both slurries were made at a concentration of approximately 63 percent solids.

Table 3-6. Ground Dolomite Analyses

Moisture As Received, wt%	0.07	
Avg. Grind Size As Received	8.74/16.05 microns	
Ultimate Analysis (Dry Basis), wt%		
Carbon		12.87
Hydrogen		.04
Nitrogen		.04
Sulfur		-
Ash		52.96
Oxygen (by diff.)		34.09
Ash Analysis By DCP, (wt%)		
	As Element	As Oxide
Sodium	0.03	0.04
Magnesium	24.7	40.95
Aluminum	0.10	0.18
Silicon	0.33	0.71
Potassium	0.02	0.02
Calcium	42.5	59.47
Titanium	0.02	0.03
Iron	0.24	0.34
Manganese	0.04	0.06
Zinc	0.02	0.02
Vanadium	0.01	0.02
Total	74.93	108.24

The first dolomite injection run was started on November 16 and ended on November 19. The gasifier was operated at T_o+100°F throughout the run with the air preheat at 1050°F. The unit was

operated for a total of 62 hours, during which two test periods were completed. The conditions for each test period are shown in Table 3-7.

Table 3-7. Run 4 Test Results

Test Period	Length Test Period (hrs.)	Air Preheat Temp. (deg.F)	Gasifier Temp. (deg.F)	Dolomite Dosage lb/lb S	Avg. Grind Size microns	Vol% H ₂ S In Gas	% Reduct. In H ₂ S
A	17.0	1050	T ₀ +50	-	-	0.30	-
B	9.0	1050	T ₀ +50	2.0	16	0.10	72*

* Most of the dolomite from the run was found in the radiant vessel and slag K. O. Pot.

The first attempt to get the dolomite injection system to work resulted in a plugged line to the injector. After the mixed metal oxide external sorbent testing, which occurred in test period A, was completed, the unit was shut down. The injection system was cleaned, and some piping modifications made. The gasifier was fired again and when the temperature in the slag knock-out pot reached 1750°F, the injector system was started. The dolomite slurry was injected at a rate of approximately 150 lbs./hr. at 64.8 wt. percent solids for the first 6 hours. This gave an approximate Ca/S molar ratio of 1.95. Due to pump problems, this rate dropped during the next three hours to 90 lbs./hr. The H₂S level in the syngas was reduced from 0.315 percent to approximately 0.098 percent, based on the on-line mass spectrometer data. After nine hours of operation on coarse dolomite slurry, the injector feed was switched to the fine dolomite slurry. An hour after this change, the injector pump over-heated and the run was shut down. Nitrogen was used as the injector atomizing gas throughout the run.

A post shutdown inspection showed that less than half of the dolomite injected was carried to the cyclone or beyond. The majority of the dolomite was in the SKOP and the Radiant vessel (see Figure 3-7). This problem resulted from severe erosion of the injector nozzle by the dolomite slurry and low syngas velocity below the injector that allowed the coarse spray formed by the eroded injector to settle downward into the SKOP. The pintle in the nozzle was eroded to the extent that it was no longer attached to the nozzle body and the pintle plate was completely eroded away. The nozzle body opposite the atomizing

Figure 3-7. Radiant Vessel After First Run

gas inlet was eroded through into the support material of the injector (see Figure 3-8).

Several process modifications were made to the unit as a result of the problems during this run. A refractory sleeve was inserted into the radiant vessel below the injector to prevent the injected dolomite from dropping into the SKOP, as it had in the first run, by increasing the syngas velocity (see Figure 3-9). A new injector nozzle that mixes the dolomite slurry and the atomizing gas stream outside the nozzle was developed. The nozzle used eight 45° gas orifices evenly spaced around a central slurry orifice to produce a finely atomized spray with a 30° spray angle (see Figure 3-10). This design reduced the slurry velocity in the injector to less than 10 ft/s to prevent erosion in the injector by the dolomite particles in the slurry.

Run 5. Dolomite Injection (2 days)

The unit was started on January 19, 1990; and 14 hours into the run, dolomite injection was started. The injector worked for two hours before the injector pump stopped. Before repairs on the pump were completed, a syngas leak into the injector cooling coil was detected and the unit was shut down. A post run inspection revealed that the injector cooling coil was heat damaged; this was attributed to the high velocity syngas impinging directly on the injector. The radiant vessel was plugged with dolomite around the injector; this was attributed to the turbulent flow pattern around the injector.

Based on the problems from the January run, the injector was redesigned to protrude only 1 inch into the radiant vessel (see Figure 3-11). Further improvements were made to the injector nozzle to eliminate the problem of a small amount of dolomite slurry not being caught in the atomizing spray and dripping off the end of the injector. These modifications included changing the spacing of the atomizing gas orifices, enlarging the depression around the orifices and changing the slope and height of the wall from the depression to the outer edge of the nozzle (see Figure 3-12).

The second dolomite injection run was restarted on March 19 and ended on March 20. During this time, the gasifier was operated for 27 hours. After bringing the temperatures in the radiant vessel to steady-state, the dolomite injector was operated for nine hours. During this time, 900 lbs. of 63 wt. percent solids coarse dolomite slurry were injected. The amount of desulfurization varied from 30 percent to 67 percent. This variation was probably a function of the temperature out of the radiant vessel and the way the dolomite was packing in the radiant vessel. The run was shut down when flow through the injector stopped. A post run inspection revealed that the dolomite had packed up to the top of the refractory sleeve in the

Figure 3-8. Commercial Nozzle Before and After Use

Figure 3-9. Modified Radiant Vessel

Figure 3-10. New Dolomite Injection Nozzle

Figure 3-11. Modified Dolomite Injector

Figure 3-12. Modified Dolomite Injection Nozzle

radiant vessel (see Figure 3-13). This dolomite was not a hard formation as in the previous run and was broken up using an air lance and vacuumed out. The analysis of the deposit is shown in Table 3-8.

Table 3-8. Dolomite Injection Run 2; Dolomite Deposit Analysis

% Moisture	0.68
ULTIMATE ANALYSIS, Wt%	
CARBON	7.66
HYDROGEN	0.10
NITROGEN	0.06
SULFUR	9.71
ASH	105.84
HHV, Btu/lb	1970
Sieve Analysis	
+8 MESH	17.18
+14 MESH	8.31
+20 MESH	5.45
+40 MESH	6.95
+100 MESH	24.41
+200 MESH	18.26
+325 MESH	7.01
-325 MESH	12.43
TOTAL	100.00

Because of these problems, a cold flow tester was built (see Figure 3-14) and the particulates previously removed from the radiant vessel were used in the tester to determine the velocity required to entrain the dolomite. The testing revealed that a velocity of 5.6 ft./s was required to entrain the particulates. This is equivalent to a velocity of 4.85 ft./s with air blown syngas at 1700°F and 350 psig in the radiant cooler. This value was determined by computation of a force balance for a worst case particle (maximum diameter and density) and incorporating the difference in gas density and viscosity between the air in the tester and syngas in the radiant cooler. Based on the syngas

Figure 3-13. Radiant Vessel After Second Dolomite Injection Run

Figure 3-14. Cold Flow Tester

flow limit of the cross flow filter, the maximum internal diameter of the radiant vessel to achieve enough syngas velocity for particulate entrainment was 8.5 inches. Therefore, an eight inch schedule 10 316 stainless steel tube (ID = 8.3 inches) was placed in the radiant vessel (see Figure 3-15). Several minor changes to the dolomite injector nozzle were required to insure that it was spraying into the inserted tube.

Run 6. Dolomite Injection Run 3 (2 days)

The third dolomite injection run was started on April 20. After nine hours of gasifier operation, the injector was started. The H_2S level in the syngas initially started dropping, but after fifteen minutes, the H_2S level increased to a value slightly below the original concentration and stayed there for the duration of the run. The injector was operated for six hours and then plugged; at this point the gasifier was shut down.

The post run inspection revealed another deposit inside the radiant vessel, both inside and outside of the metal tube; the tube also had moved downward through ten inches of refractory. The poor desulfurization in this run was due to inadequate contacting between the dolomite and the syngas that resulted from the dolomite hitting the metal tube before drying and then packing on the tube. The conditions in the radiant cooler after shutdown are shown in Figure 3-16.

The geometry limitations of the current PDU apparently make the injection of dolomite slurries impractical. To determine the sulfur capture attainable with dolomite and limestone, we decided to test each sorbent in a fixed bed to be installed in the radiant vessel. Two runs were made using syngas from oxygen-blown gasification of Pittsburgh No. 8 coal. Oxygen gasification was used because the process optimization study concluded that oxygen gasification is more economical than air gasification.

Run 7. Fixed Bed Dolomite (2 days)

In this run, the dolomite was suspended in the radiant vessel as a fixed bed. The bed of dolomite was divided into three sections by distributor plates. Each plate supported the one above it using a central support bar and a set of fins at the top of the bar. The bottom plate was attached to a distributor section filled with half inch alumina balls. The distributor section sat on a ring with a refractory gasket that prevented gas flow from going around the distributor along the vessel wall. The ring was supported by three pegs spaced 120° apart around the vessel diameter. The pegs passed through the vessel wall and were attached to the outside of the vessel by flanged fittings.

Figure 3-15. Dolomite Flow Tube

LEGEND

- DOLOMITE

Figure 3-16. Radiant Vessel After Third Dolomite Injection Run

A drawing of the fixed bed system is shown in Figure 3-17. The bed was loaded with dolomite of 3/8 inch nominal rock size.

The fixed bed dolomite run was started on July 10. The gasifier was operated at $T_0 + 50^\circ\text{F}$ throughout the run. The unit was on-line for four hours before gas flow to the fixed bed was started. This time was used to line out the unit and start-up the mass spectrometer (MS). The MS was used to obtain on-line analyses of the internal syngas to determine the baseline H_2S level before being switched to external syngas when the fixed bed was started.

The fixed bed was heated to operating temperature (1700°F) in approximately two hours. Due to a defective thermocouple on the outlet of the bed we could not determine if the bed temperature leveled off as the dolomite was calcined.

During the five hours that the bed was operating at 1700°F or hotter, desulfurization between 77 percent and 82 percent was achieved. The desulfurization level appeared to increase with higher inlet temperature.

The run was terminated after 11 hours when the flow through the bed was reduced due to plugging of the bed with char. Because of the short length of this run, the Westinghouse Crossflow Filter could not be tested.

A post-run inspection revealed that the bottom distributor section of the bed was plugged with char, the dolomite rocks in the bed had crumbled, and the bed structure had partially collapsed.

To reduce these bed plugging problems in the next run, several modifications were made to the bed. These changes included increasing the void space in the distributor section by using screens in place of alumina balls, and increasing the void space in the distributor plates by enlarging the diameter and number of holes. The structural integrity of the bed was improved by changing to thicker plates and stronger inter-plate supports. The new bed design is shown in Figure 3-18.

We decide to switch to lime in the fixed bed for the next run, since we had obtained some performance data on dolomite and wanted data on both materials.

Run 8, Fixed Bed Lime (1 day)

For this run, the bed was loaded with lime instead of limestone to reduce the chance of the sorbent crumbling from off-gassing CO_2 as the sorbent is brought to operating temperature and calcined.

Figure 3-17. Dolomite Fixed Bed

SECTION A - A

Figure 3-18. Modified Fixed Bed

The fixed bed lime run was started on October 30. The lime bed previously was exposed to syngas for five hours in August during an aborted attempt to make this run.

During this run, the gasifier operated for seventeen hours. Several attempts were made to start syngas flow through the fixed bed, but all were unsuccessful. Based on this problem the run was terminated.

A post-run inspection revealed that the bed had hardened into a weak concrete. The material at the bottom of the bed was stronger than that at the top. Samples of this material were sent to Texaco R&D-B for analysis.

The data from Texaco R&D-B showed that the lime had reacted with the CO_2 in the syngas to form CaCO_3 , and that some hydrolysis had occurred. The carbonate was probably formed during both the run in August and the run in October, due to the high partial pressure of CO_2 in the syngas and the bed being below the calcining temperature of limestone.

The hydrolysis probably occurred during the down time between the two runs. Due to the low bed operating temperatures during the August run, water may have condensed out of the syngas onto the bed. This water reacted with the lime while the unit was shut down.

Based on the operational difficulties experienced with dolomite slurry injection and fixed bed testing of dolomite and lime, we decided to defer any further testing of calcium based sorbents downstream of the gasifier until the economic studies are completed. If the studies show a clear economic advantage to calcium based sorbents we will resume testing with a redesigned system, which will inject dry dolomite or limestone. The methods tried above were low cost options that required minimum modifications to existing equipment.

3.3.3 Sample and Data Collection

Process streams were sampled at appropriate times throughout the test runs. These streams included: coal slurry, dolomite slurry, syngas, flash gas, coarse slag, lockhopper fines, clarifier inlet water, clarifier bottoms, and clarifier overhead (waste) water.

Post-shutdown samples of the solids collected from each section of the fixed beds, the cyclone and cross flow filter catch-pots were taken. Also samples of any deposits found in the post shutdown inspections were taken for analyses. The results of the analyses were used in material and energy balances.

Raw Syngas and flash gas bomb samples were taken at appropriate times during each test period. An on-line mass spectrometer was used to analyze gas streams continuously, and the averages were used to prepare material and energy balances. Samples of solids in the syngas to and from the Westinghouse crossflow filter were taken several times a day when the filter was running.

Laboratory analyses of the solids and water streams for each run/test period can be found in Appendix A.

Major process variables such as pressure, temperature, and flow rates for most streams during the PDU testing were collected and averaged by a datalogger. The data were largely duplicated by recorders and other output devices. The output of the datalogger was periodically sent to a computer that prepared reports such as on-line material and energy balances, and process variable log sheets. Operator logsheets were maintained as backups to the computer generated log sheets. Observations made during the runs were recorded in logbooks.

3.3.4 Results Achieved

In-Situ (Fine-Ox) Desulfurization: Air-Blown and Oxygen-Blown Gasification

The PDU test results indicate that a nominal 50 percent reduction of H_2S level in oxygen-blown syngas was achieved at normal gasifier temperatures with Powhatan coal, independent of slag residence time. This result is in agreement with the Phase I results with Powhatan coal and is more than predicted by theoretical studies and bench scale testing.

In air-blown gasification of Pittsburgh No. 8 coal, the maximum level of desulfurization achieved with iron oxide added to the coal slurry was 27 percent. This level also was higher than predicted by theoretical and bench scale testing. However, this level of desulfurization is not sufficient for any commercial use.

Slag from Run 1 was tested for leachable sulfides using the proposed EPA test method (SW-846) (see Table 3-9). The current EPA action level for leachable or reactive sulfide is 500 mg/kg. Based on this, the coarse and fine slags from the Fine-Ox addition periods of the run would have to undergo further processing before disposal in a landfill.

These results are significantly different from those obtained in the Phase I testing, where the coarse and fine slags from the Fine-Ox addition test with Powhatan coal were classified nonhazardous (12-227 ppm reactive sulfides). At this time we do

Table 3-9. Leachable Sulfide in Solids

Run-Test Period	Solids*	Gasifier Temp. (deg.F)	Sorbent (lb/lb S in Coal)	Total Sulfide (ppm)	Leachable Sulfide (ppm)
1-A	CS	To	0.0	760	130
1-A	SF	To	0.0	720	38
1-A	CB	To	0.0	4400	8
1-D	CS	To	2.5	5500	850
1-D	SF	To	2.5	16000	950
1-D	CB	To	2.5	430	12
6-B	RV	To+50	2.5	15000	8000

* CS: coarse slag, SF: slag fines, CB: clarifier bottoms,
RV: radiant vessel

not have an explanation for this difference in results. If the on-going economic studies indicate that in-situ desulfurization with iron oxide is promising, then further testing to determine the factors effecting the leachability of the slag would have to be done. Due to the poor performance of iron oxide in air-blown gasification, the slag from that run was not tested for leachable sulfides.

Dolomite Testing in Air and Oxygen Gasification

While the dolomite testing did not work as planned, lower limits of sorbent performance were determined. For air gasification this level was 72 percent sulfur removal. The theoretical equilibrium in air gasification syngas is 92.7 percent removal. In oxygen gasification, fixed bed testing achieved a removal level of 80 percent H_2S . The thermodynamic limit in oxygen gasification is 93.6 percent desulfurization. Neither of these tests reached steady-state. A sample of the dolomite deposit from run 6 was analyzed for leachable solids (see Table 3-9). As expected, the sulfided dolomite would be classified as hazardous and would have to undergo further processing to oxidize the sulfide to sulfate before disposal.

A dry feed system should achieve higher desulfurization levels than the slurry feed system. If the economic studies indicate that calcium based sorbents are the best method to use, a dry feed injection system will be built and tested.

tests reached steady-state. A sample of the dolomite deposit from run 6 was analyzed for leachable solids (see Table 3-9). As expected, the sulfided dolomite would be classified as hazardous and would have to undergo further processing to oxidize the sulfide to sulfate before disposal.

A dry feed system should achieve higher desulfurization levels than the slurry feed system. If the economic studies indicate that calcium based sorbents are the best method to use, a dry feed injection system will be built and tested.

Differences Between Air-Blown And Oxygen-Blown Gasification

A comparison of air-blown and oxygen-blown gasification efficiency in terms of oxygen consumption versus carbon conversion is shown in Figure 3-19. These data show that air-blown gasification requires approximately 20 percent more oxygen

Figure 3-19. Pittsburgh No. 8 Coal Performance Comparison
Air-Blown vs Oxygen-Blown Gasification

to achieve the same carbon conversion then oxygen-blown gasification. At lower carbon conversions the oxygen requirement in air-blown gasification increases relative to oxygen-blown gasification.

Additionally, the air has to be preheated to the 800 - 1000°F range to maintain appropriate gasifier temperatures for slag removal without resorting to over-conversion. The relationship between air preheat temperature and the CO₂/CO ratio in syngas is shown in Figure 3-20. This graph should be used cautiously, since there are other variables that affect this relationship that are not shown. These variables include gasifier temperature, slurry concentration and the ratio of air/coal in the feed, which accounts for some of the scatter in the data.

Figure 3-20. Comparison of Air Preheat Temperature and CO₂/CO Ratio

Even with the air preheat, the CO₂/CO ratio of the air-blown gasification syngas is almost twice that of the oxygen-blown gasification syngas. Typical syngas compositions and heating

Table 3-10. Typical Gasifier Exit Syngas Composition (wet)

Component	Air-Blown Syngas, vol%	Oxygen-Blown Syngas, vol%
Hydrogen	10.30	30.49
Carbon Dioxide	8.77	10.62
Carbon Monoxide	14.13	40.49
Water	9.82	16.35
Nitrogen	56.01	1.51
Argon	0.70	0.06
Methane	0.01	0.09
Hydrogen Sulfide	0.23	0.36
Carbonyl Sulfide	0.03	0.03
Total	100.00	100.00
HHV, Btu/SCF	78.7	229.5

recoveries for the elements carbon, hydrogen, nitrogen, oxygen and sulfur and for the ash. To close these balances, selected stream flow rates and analyses were varied within their estimated standard errors until closure of the material balances was obtained with a minimum total deviation. The results of the computer balanced material and energy balances for the gasifier are available upon request, on a confidential basis.

3.4 PDU Testing- External Mixed Metal Oxide Sorbents

3.4.1 Sorbent Selection

Four sorbents were selected for testing during this Phase of the program. The sorbents are:

- 1) Zinc Ferrite (T-2465)
This sorbent is from United Catalyst Incorporated (UCI). It was the base sorbent for the Phase I testing. It lost its' crush strength in oxygen-blown gasification syngas, due to the highly reducing nature of the syngas. It performed better in air-blown gasification syngas, which is less reducing.
- 2) Zinc Titanate (L-3014)
This sorbent also is from UCI. It has a Zn/Ti ratio of 0.8. This is the formulation of zinc titanate tested in Phase I that was judged to be the best overall sorbent.

Overall Wt% recovery:

C	99.8
H	102.7
N	109.5
S	77.4
O	98.4
Ash	102.3

Figure 3-21. Mass Balance for Run 1 Period F Powhatan Coal with Iron Oxide, Oxygen-Blown

Overall Wt% recovery:

C	99.4
H	103.3
N	95.2
S	102.1
O	101.0
Ash	100.7

Figure 3-22. Mass Balance for Run 2 Period A Pitt. #8 Coal, Air-Blown

Overall Wt% recovery:

C	102.9
H	100.4
N	99.1
S	103.2
O	99.9
Ash	74.1

Figure 3-23. Mass Balance for Run 3 Period A Pitt. #8 Coal with Iron Oxide, Air-Blown

- 3) Zinc Titanate (L-3140)
This sorbent also is from UCI. It has a Zn/Ti ratio of 1.5. This is an optimized zinc titanate sorbent and was chosen based on the results of testing at RTI. This batch of sorbent was prepared in the same way as UCI zinc titanate sorbent batch L-3196 that was used in the RTI experiments.
- 4) Iron Oxide
This sorbent was selected based on the poor performance of zinc ferrite in the phase I testing as another alternative to zinc ferrite. The sorbent was supplied by METC, but never tested.

3.4.2 Pilot Plant Equipment and Procedures

The external sorbent system, shown schematically in Figure 3-24, consists of three fixed bed reactors mounted in the convective syngas cooler, and downstream gas handling equipment.

By placing the sorbent bed reactors in the convective cooler, the reactors are surrounded by syngas that is at the same temperature as the gas that enters the sorbent. This ensures that the sorbent beds are operated in a near isothermal environment with respect to position. The syngas flow rate through the radiant and convective syngas coolers is controlled to maintain the desired temperature around the sorbent reactor.

Figure 3-25 shows the sorbent reactors in more detail. The reactors are made of four inch schedule 80 Incoloy 800H pipe with one inch thick Incoloy 800H disks at the top and bottom. The top disk is center tapped for a one inch pipe. The bottom disk is held in place by four set screws and is perforated with 16 1/4-inch holes to evenly distribute the gas entering the bed. Each bed is screwed directly to a one inch pipe (schedule 80 Incoloy 800H) that is inserted through a plate welded to a 24 inch A-105 carbon steel flange via a 4 inch schedule 80 Incoloy 800H sleeve.

The sorbent beds are divided into three sections by using 316 stainless steel screens and refractory sponges between the bed sections. A spacer down the middle of the bed is utilized during reactor charging. The spacer is replaced with a thermocouple sheath when the reactors are screwed onto the mounting flange. The amount of sorbent charged to each bed section is pre-weighed, and the bed is lightly tamped to reduce the void space after each section is loaded. To insure that the bed is fully packed, additional sorbent is added to the bottom bed section, the last section loaded, if needed.

The hot syngas passing through the sorbent beds exits out of the one inch pipe to a cooler. There is a thermocouple sheath that runs down through the one inch pipe and the sorbent bed. This sheath contains 10 thermocouples that are spaced two inches

Figure 3-24. External Sorbent Beds P & ID

Figure 3-25. External Sorbent Bed Reactor Details

apart; the first thermocouple is located one inch from the bottom of the sorbent bed. The coolers are designed to cool the hot syngas from a nominal 1400°F to 100°F. The syngas passes through the coolers in 20 feet of 1/4 inch schedule 40 Incoloy 800H pipe that was bent to form 32 coils of 5/8 inch pitch. After the cooler, each of the three syngas streams is split into two streams, with one group of three going to the sampling equipment and the other group of three going to the control equipment and then to the flare.

The streams going to the sample equipment go through 20 feet of 1/2 inch 316 stainless steel tubing; the pressure is then reduced from 350 psig to 55 psig. The gas then flows through 1/4 inch FEP Teflon lines for 40 feet to ground level. These syngas streams then go through flowmeters with needle valves before splitting again. Part of the flow goes through continuous flow sample bombs and then to the flare. This flow is interrupted only when sample bombs are changed. The syngas in the sample bombs is analyzed by laboratory gas chromatograph for eight major components. The other part of the sample streams goes to a continuous Anarad AR-300 ultraviolet H₂S analyzer with an automated sampling system. This system can analyze one stream every minute and cycles between the streams.

The main flow from each bed goes through 50 feet of 1/2 inch 316 stainless steel tubing down the tower to large water knock-out (k.o.) pots. These k.o. pots are constructed with 54 inch lengths of 16 inch diameter XS, A-106B carbon steel pipe with 16 inch A-234 WPB carbon steel weld caps at the top and bottom. These pots were designed to be blown down once per shift. From the k.o. pots, the three syngas streams go through 20 feet of 1-inch schedule 80 A-103 carbon steel pipe to a pressure transducer, then an integral orifice flowmeter, and a research control valve. From the control valve the syngas goes to the flare.

When the sorbent beds are not being tested, but the gasifier is being run, nitrogen is fed through each sorbent bed. The nitrogen purge flows down through the top of each bed and out into the convective syngas cooler. This purge is to prevent syngas from entering the beds and biasing the results. The nitrogen purge is started before gasifier start-up and continued, except when the sorbent bed is being tested, through unit shutdown until the syngas coolers are cool enough for the flange with the sorbent beds to be pulled and the beds removed. At gasifier start-up all equipment downstream of the sorbent beds is blocked-in to reduce the pressure surge volume that includes the sorbent beds. The equipment is brought to pressure with nitrogen before it is put on-line and the sorbent test started.

Part of the sorbent bed start-up procedure is to start the beds shortly after a soot blowing of the radiant cooler. Each soot blowing produces a dust cloud as it cleans the surface of the

water jacket in the radiant syngas cooler. The sorbent beds are always started shortly after a soot blowing so they will have as long a time as possible on-line before the next soot blowing. This minimizes the amount of dust that can be entrained into the sorbent beds and increase the pressure drop across the bed. The soot blowing also affects the temperature of syngas around and entering the sorbent beds. The soot blowing cycle is adjusted to keep this temperature swing under 50°F whenever possible.

3.4.3 Description of Runs

The mixed metal oxide external sorbent test plan originally consisted of two parts. The first part was to be bulk desulfurization of syngas and the second part was to be polishing desulfurization during the dolomite injection test. Due to problems with the dolomite injection testing there were no polishing tests with the external sorbents. Also, two sets of the original six sets of tests were canceled when the calcium based external sorbent tests were switch to fixed bed tests. This was due to the short run times anticipated for the fixed beds of dolomite and lime and the low expected syngas H_2S levels at the entrance to the mixed metal oxide sorbent beds. As a result, the mixed metal oxide sorbent beds were only loaded four times. The sorbents loaded for the fourth run were not sulfided in a controlled test due to the failure of equipment down-stream of the sorbent beds. Key variables for these test are summarized in Table 3-11.

Sorbent Bed Run 1

The first external sorbent bed run was completed during period A of the air baseline run. Both formulations of zinc titanate were tested in this run, along with the zinc ferrite. These tests were not run to breakthrough since the unit was shut down before any of the sorbent beds reached breakthrough. The run data are summarized in Table 3-12. The beds were operated at lower space velocities than originally planed due to the higher than expected pressure drop across the beds. This resulted in lower gas flows through the beds, since the flow controllers for the beds are not pressure compensated.

The H_2S exit concentration for each bed is shown in Figure 3-26. The data for these curves were taken from the on-line Anarad H_2S analyzer, which does not zero well and is only used to produce sorbent bed breakthrough curves. The H_2S concentration before breakthrough is determined by taking several gas bombs and analyzing them on an off-line gas chromatograph. The gas composition into and out of each bed is shown in Table 3-13. The syngas water content is not shown in the table due to the difficulties in analyzing for it with an off-line analyzer. A

Table 3-11. Summary of External Sorbent Tests

Test Run #	1	2	3
H ₂ S to Beds, %	0.28	0.29	0.30
Avg Bed Inlet Temp., °F	1200	1200	1150
External Sorbents tested			
ZnF T-2465	Bed A	Bed A	Bed A
ZnT L-3014	Bed B	Bed B	Bed B
ZnT L-3140	Bed C	Bed C	Bed C
Space Velocities			
Bed A	1416	1637	2798
Bed B	1447	1679	2541
Bed C	1298	1502	2726

Table 3-12. External Sorbents Run 1

Sorbent	<u>ZnFe</u>	<u>0.8ZnTi</u>	<u>1.5ZnTi</u>
Run Time, hrs	16.1	16.1	16.1
t/t*	0.18	0.58	0.28
Inlet H ₂ S, ppmv	2800	2800	2800
Outlet H ₂ S, ppmv	0	0	0
Space Vel., hr ⁻¹	1416	1447	1298
Velocity, ft/s	0.10	0.09	0.10
Avg. T In, °F	1000	1000	1000
Avg. T Out, °F	1070	1050	1040
Bed Exit P, psig	305	330	260

t* = The theoretical time to completely sulfurize the sorbent at the run conditions.

Space Velocity is based on dry gas flow at STP.

significant amount of water gas shifting occurred in all three sorbent beds. The methanation reaction was not catalyzed in any of the beds and as a result there were no temperature excursion in the beds. This had been a problem with the zinc ferrite in oxygen blown syngas.

Figure 3-26. Mixed Metal Oxides Run 1 H₂S Breakthrough Curves

Table 3-13. External Sorbents Gas Composition; Run 1

	Syngas <u>In</u>	Syngas Out <u>ZnFe</u>	Syngas Out <u>0.8ZnTi</u>	Syngas Out <u>1.5ZnTi</u>
H ₂	11.65	14.50	12.35	12.07
CO ₂	10.39	14.94	12.71	11.64
H ₂ S	0.25	0.000	0.000	0.000
COS	0.02	0.000	0.000	0.000
Ar	0.72	0.73	0.74	0.74
N ₂	61.70	61.31	62.58	62.54
CH ₄	0.00	0.002	0.001	0.001
CO	15.27	8.51	11.62	13.01

When the sorbent beds were unloaded after the run there was only a thin film of char on the outside of the reactors. All three sorbents were hard enough that they could not be crushed without mechanical aid. This was an improvement for zinc ferrite, indicating that it is not over-reduced in air-blown gasification

syngas like it was in the oxygen-blown gasification syngas test in Phase I.

Sorbent Bed Run 2

The external sorbent beds were reloaded with fresh sorbents for testing during the continuation of the air baseline run (Zinc Ferrite (ZnFe), 0.8 Zn/Ti Zinc Titanate (0.8ZnTi), and 1.5 Zn/Ti Zinc Titanate (1.5ZnTi)). During the second part of the air baseline run (test period B), the sorbents were tested for seven hours before operational problems with the syngas temperature resulted in the bed inlet temperature dropping down to 400°F over several hours (see Figure 3-27). Each of the sorbents stopped working efficiently as the temperature dropped. The 1.5 Zn/Ti zinc titanate was effective down to a temperature of 500°F, while the zinc ferrite and 0.8 Zn/Ti zinc titanate lost effectiveness at 800°F. The beds were run for several hours at this low inlet temperature until it was concluded that the problem could not be

Figure 3-27. Mixed Metal Oxides Run 2 H₂S Breakthrough Curves

fixed on-line and the run was concluded. During this time the H₂S concentrations indicated on the Anarad analyzer were off-scale high (over 1000 ppm).

The sorbent beds were left in place and restarted during the August 7 continuation of the air baseline run. They were run for an additional eight to 10 hours, depending on when breakthrough was achieved. A summary of the run data is shown in Table 3-14. The average gas analysis at the inlet and outlet of each bed is shown in Table 3-15. Again there was a significant amount of the water-gas shift reaction occurring in the beds. Also, the exit H₂S concentrations were higher than observed in other runs.

Table 3-14. External Sorbents Run 2

Sorbent	<u>ZnFe</u>	<u>0.8ZnTi</u>	<u>1.5ZnTi</u>
Run Time, hrs	22.3	19.7	21.9
t/t*	0.30	0.86	0.46
Inlet H ₂ S, ppmv	3100	3100	3100
Outlet H ₂ S, ppm	0.001	0.001	0.003
Space Vel., hr ⁻¹	1708	1751	1561
Velocity, ft/s	0.11	0.11	0.11
Bed Exit P, psig	315	335	270

t* = The theoretical time to completely sulfurize the sorbent at the run conditions.

Space Velocity is based on dry gas flow at STP.

The 0.8 ZnTi lasted 18 hours and both the 1.5 ZnTi and the ZnF ran for 20 hours. The run time for the sorbents shown on Table 3-14 is the combined time for both runs. When the sorbents were examined after the second run, all three were found to have retained most of their initial crush strength.

Table 3-15. External Sorbents Gas Composition Run 2

	<u>Syngas In</u>	<u>Syngas Out ZnFe</u>	<u>Syngas Out 0.8ZnTi</u>	<u>Syngas Out 1.5ZnTi</u>
H ₂	11.72	14.53	13.77	13.74
CO ₂	9.71	13.20	11.82	12.62
H ₂ S	0.28	0.001	0.001	0.004
COS	0.03	0.000	0.000	0.000
Ar	0.69	0.72	0.72	0.70
N ₂	62.21	61.06	62.72	62.02
CH ₄	0.03	0.013	0.014	0.007
CO	15.34	10.41	11.95	10.90
H ₂	11.49	14.50	12.35	12.07

Note: The time the beds were operating ineffectively due to low temperature was disregarded when the above averages were calculated.

Sorbent Bed Run 3

During this run, in which dolomite was injected up-stream of the external sorbent beds, UCI Zinc Ferrite and two Zinc Titanate (0.8, 1.5 Zn/Ti ratio) sorbents were tested in the external sorbent beds. To insure that there was adequate time for the beds to reach breakthrough while operating in a polishing mode, the reactors only were loaded fifty percent full. The remaining volume in the reactors was filled with packing rings (see Figure 3-28). Since there were problems with the dolomite injector, the beds were operated during a period when no dolomite was being injected. The data from the run are summarized in Table 3-16.

This run went smoothly, except for the high H₂S exit concentration for the 0.8 Zn/Ti zinc titanate bed, as can be seen in the gas analysis in Table 3-17. We believe the high H₂S exit concentration for the 0.8 ZnTi was due to channelling occurring in that sorbent bed.

The H₂S breakthrough curves for all three beds are shown in Figure 3-29. Two of the beds have very similar breakthrough curves, this may have been due to leaking valves in the sampling system for the Anarad Analyzer.

This problem would cause the stream sent to the analyzer for one stream to be a mixture of two or more sample streams. The breakthrough curves from run two indicate that this problem may have started in that run. To prevent this problem in future runs, all of the Anarad sampling valves were replaced with valves that have spring loaded (active) seats to improve valve seating over

Figure 3-28. Sorbent Beds Loading Run 3

Table 3-16. External Sorbents Run 3

Sorbent	<u>ZnFe</u>	<u>0.8ZnTi</u>	<u>1.5ZnTi</u>
Run Time, hrs	16.8	9.5	9.0
t/t*	0.41	0.68	0.37
Inlet H ₂ S, ppmv	3000	3000	3000
Outlet H ₂ S, ppmv	12	129	0
Space Vel., hr ⁻¹	2798	2541	2726
Velocity, ft/s	0.10	0.10	0.09
Avg. T In, °F	1050	1050	1050
Avg. T Out, °F	1100	1120	1100
Bed Exit P, psig	350	345	360

t* = The theoretical time to completely sulfurize the sorbent at the run conditions.

Space Velocity is based on dry gas flow at STP.

Table 3-17. External Sorbents Gas Composition Run 3

	<u>Syngas In</u>	<u>Syngas Out ZnFe</u>	<u>Syngas Out 0.8ZnTi</u>	<u>Syngas Out 1.5ZnTi</u>
H ₂	11.72	13.37	12.50	12.16
CO ₂	9.71	11.64	10.32	9.93
H ₂ S	0.28	0.001	0.013	0.000
COS	0.03	0.002	0.001	0.000
Ar	0.69	0.59	0.59	0.56
N ₂	62.21	62.98	64.39	65.56
CH ₄	0.03	0.018	0.019	0.015
CO	15.34	11.42	12.18	11.78

Figure 3-29. Mixed Metal Oxides Run 3 H₂S Breakthrough Curves

numerous cycles. The original sample valves did not have active seats. Between pre-run equipment calibration and the actual run, each valve in the sampling system cycles approximately 1000 times per run.

3.4.4 Results Achieved

Chemical and physical properties of as-received and spent sorbents were measured at MRL and Texaco R&D-B, including crush strength, sulfur loading, pore volume, surface area, and chemical phases present. The samples sent to R&D-B were screened to remove the fine (-14 mesh) particulates. The fines usually totaled less than one percent of the total bed weight, due to the filters used upstream of the bed and the lack of sorbent degradation.

The results from the testing at R&D-B are summarized in Tables 3-18 through 3-20. The crush strength data show the ZnTi sorbents to be stronger than the zinc ferrite sorbent. For all three sorbents, the pore volume decreased with increasing sorbent sulfidation. The phase analysis done on samples from each bed

Table 3-18. Spent Zinc Titanate L-3014 (0.83n/Ti) Test Results

Bed Position	Run 1			Run 2			Run 3		
	T	M	B	T	M	B	T	M	B
Sample Analysis %S	1.43	12.0	14.3	9.02	12.4	13.1	8.7	8.9	13.8
<u>Phases (Relative Amounts)</u>									
ZnS	1	3	3	4	4	4	3	3	5
2ZnO.3TiO2	3	1	0	3	2	1	2	2	0
2ZnO.TiO2	1	0	0	0	0	0	0	0	0
ZnO	0	0	0	0	0	0	0	0	0
TiO2	1	2	2	1	2	2	2	2	3
%C	0.04	0.08	0.07	0	0.19	0.12	0	0.04	0.07
Crush Strength, lbs.	35.6	41.4+	34.3	36.2+	42.6+	22.5	39.6	41.2	36.3
Pore Volume, cc/gm	0.3690	0.3730	0.2864	0.3747	0.3331	0.1854	0.3296	0.3340	0.2879
Surface Area, m2/gm	4.5	7.7	9.0	4.0	5.7	4.3	4.9	4.7	7.8

T = Top, M = Middle, B = Bottom

Crush Strength is the average of 6 tests. A plus sign after the number indicates there was at least one full scale (50 lbs.) readings.

Table 3-19. Spent Zinc Titanate L-3140 (1.5Zn/Ti) Test Results

<u>Bed Position</u>	<u>Run 1</u>			<u>Run 2</u>			<u>Run 3</u>		
	<u>T</u>	<u>M</u>	<u>B</u>	<u>T</u>	<u>M</u>	<u>B</u>	<u>T</u>	<u>M</u>	<u>B</u>
Sample Analysis %S	0.33	2.17	12.7	5.07	9.48	15.7	7.9	7.9	8.3
<u>Phases (Relative Amounts)</u>									
ZnS	0	1	3	2	3	4	3	3	3
2ZnO.3TiO2	1	1	1	2	2	1	1	1	1
2ZnO.TiO2	3	2	2	3	2	1	3	3	3
ZnO	0	0	0	0	0	0	0	0	0
%C	0.04	0	0	0.07	0.08	0	0.05	0.02	0.05
Crush Strength, lbs.	42.0+	34.9+	33.0+	20.5+	36.3+	50.0+	45.7+	47.3+	40.4+
Pore Volume, cc/gm	0.2627	0.2072	0.1463	0.2157	0.1900	0.1863	0.2074	0.1991	0.1633
Surface Area, m2/gm									

T = Top, M = Middle, B = Bottom

Crush Strength is the average of 6 tests. A plus sign after the number indicates there was at least one full scale (50 lbs.) reading.

Table 3-20. Spent Zinc Ferrite L-2465 Test Results

Bed Position	Run 1			Run 2			Run 3		
	T	M	B	T	M	B	T	M	B
Sample Analysis %S	0.34	0.77	14.3	2.41	6.45	16.6	9.7	9.7	16.1
<u>Phases (Relative Amounts)</u>									
ZnS	0	1	2	1	2	3	2	2	3
2ZnO.3TiO2	2	2	1	2	1	0	1	1	0
Z10.TiO2	3	3	2	0	1	2	2	1	1
ZnO	1	1	0	2	1	1	1	2	1
%C	0.14	0.07	0.08	0.51	0.31	0.41	0.14	0.14	0.11
Crush Strength, lbs.	29.4	22.0	24.0	11.5	10.9	23.8	19.1	18.3	10.9
Pore Volume, cc/gm	0.2933	0.2884	0.2569	0.2677	0.2249	0.1978	0.2467	0.4023	0.2535
Surface Area, m2/gm	2.5	2.1	2.1	5.7	2.8	4.8	2.6	2.7	3.0

T = Top, M = Middle, B = Bottom

Crush Strength is the average of 6 tests. A plus sign after the number indicates there was at least one full scale (50 lbs.) reading.

section was qualitative in nature. The numbers (0 to 3) in the table correspond to the relative amount of that phase present, with larger numbers corresponding to relatively more of that phase present.

The sulfided zinc ferrite is reduced to a mixture of ZnO , Fe_3O_4 , FeO , and $(\text{Zn}, \text{Fe})\text{S}$ [sphalerite and wurtzite] with no elemental iron or iron carbide detected in any of the samples. This is significantly different from the oxygen-blown gasification test where no iron oxides were found in the samples, and large quantities of iron carbide and troilite (a different form of FeS) were detected. This confirms that air-blown syngas is not as reducing as oxygen-blown syngas and explains why the zinc ferrite pellets did not sustain excessive loss in crush strength as happened in oxygen-blown syngas during Phase I.

The sulfided zinc titanate phases were the same as those in oxygen-blown gasification. The 1.5 Zn/Ti zinc titanate contained several phases not present in the 0.8 Zn/Ti zinc titanate, due to its different formulation. The phases are a second form of zinc titanate (Zn_2TiO_4) and the anatase form of titanium dioxide instead of the rutile form.

Sulfur balances for the nine sorbent bed tests are shown in Table 3-21. The numbers reported in the table are the percent of the sulfur entering each bed that was captured. The sulfur captured in the bed is calculated from the weight of the sorbent recovered from the bed times the percent of sulfur. The sulfur into the bed is calculated from the syngas flow leaving the bed and the percent of sulfur in the syngas entering the bed. To account for the mole change due to the water-gas shift reaction in the sorbent bed, the gas flow exiting the bed is multiplied by the ratio of the moles entering the bed to the moles exiting the bed on a dry gas basis. This ratio is calculated by doing an elemental balance across each bed assuming that the sum of $\text{CO} + \text{CO}_2$ and $\text{H}_2 + \text{H}_2\text{O}$ are constant assuming only the water-gas shift reaction is significant.

Sulfur balance values significantly over 100 would indicate poor purging of the sorbent bed during the PDU test when the bed was not being run; due to eddy currents of syngas flowing into the bed and sulfiding some of the sorbent. This was not a problem in these runs (unlike the Phase I testing).

The numbers show that there was some difficulty in obtaining good sulfur balances. A significant portion of this problem may be related to getting accurate sulfur numbers on the solids. An accelerator (vanadium pentoxide) had to be used to get the sorbents to burn in the sulfur analyzer. How well the accelerator is mixed into the sample determines the amount of sulfur in the sample that is burned and recorded by the analyzer. Also, only 20 or so pellets at random from each bed section were

Table 3-21. Sulfur Balances for Mixed Metal Oxide Sorbents

	Percent of Input Sulfur Captured in Each Bed		
	<u>ZnFe</u>	<u>0.8ZnTi</u>	<u>1.5ZnTi</u>
Run 1	77	92	77
Run 2	93	85	93
Run 3	71	86	89

taken as the representative sample for analysis. This may not have been an adequate sample size if considerable variation in sulfur content occurred across each bed section.

3.4.5 Regenerable Zinc Titanate Reactor Design

The durability of zinc titanate sorbent is a critical factor in the economics of hot syngas desulfurization. Recent tests at RTI under simulated process conditions over several cycles demonstrated that zinc titanate has excellent durability in the high temperature desulfurization of simulated syngas from the TCGP. However, questions remain about the durability of zinc titanate under actual process conditions with Texaco syngas from an operating gasifier.

To address these questions, a regenerable zinc titanate sorbent reactor will be constructed, installed, and tested at MRL. The unit will be downstream of the Westinghouse Crossflow Filter in the Low Pressure Solids Gasification Unit. Twenty cycles of sulfidation and regeneration of the sorbent are planned. The sorbent durability data we plan to obtain as a function of the number of cycles includes sulfur capacity, crush strength, zinc loss and sensitivity to trace components in the syngas.

Parts and materials for the project, which have long delivery times, will be ordered and applications for permits will be submitted in the first quarter of 1991. Construction will begin in the second quarter, and a shakedown run is scheduled during the third quarter of 1991.

Process Overview

The proposed process flow diagram and sorbent reactor are shown in Figures 3-30 and 3-31 along with nominal flow rates, compositions, temperatures and pressures. Nominal process conditions have been chosen based on data from RTI reported in Volume II of this report. A single sulfidation cycle is composed

MATERIAL BALANCE (Mmbed Flowrates g-mole/hr)					
Stream #	1	2	3	4	5
Description	Nitrogen Diluent	Regen Air	Regen Feed	Sulfidation Feed	Regen Exhaust
H ₂	0	0	0	1330	1094
H ₂ O	1928	189	2095	15	2065
H ₂ O	0	0	0	354	571
CO	0	0	0	1228	1484
A	0	0	0	2	2
O ₂	0	45	45	0	0
CH ₄	0	0	0	0	0
CO ₂	0	0	0	647	411
H ₂ S	0	0	0	0	18
S ₂	0	0	0	0	0
TOTAL	1928	214	2140	3576	3576
Temp (F)	120	120	1100	1200	1420
P (psia)	350	350	350	350	350

• Multiplied by 0.1336 to convert to SCFH
 • Bedflow column flowrates correspond to the sulfidation cycle,
 and other column flowrates correspond to regeneration.

Figure 3-30. Regenerable Sorbent Bed P & ID

of sulfidation, nitrogen purge, regeneration, and nitrogen purge; a complete cycle is expected to nominally require eight hours. The following two sections briefly describe the sulfidation and regeneration processes.

Sulfidation

A slip stream of filtered syngas, immediately downstream of the Westinghouse Crossflow Filter, will be diverted to the sorbent bed which will have a bed volume of 1.07 cubic feet. Syngas nominal pressure and temperature will be 340 psig and 1300°F; space velocities will range between 2000 hr⁻¹ and 6000 hr⁻¹, and the resulting gas linear velocities will range between 0.33 and 1.0 ft/s. The maximum syngas flow to the sorbent bed will represent less than 10 percent of the total gasifier output. At the anticipated H₂S levels (0.7 percent), a nominal sulfidation time of 3.5 hours is expected.

During sulfidation, block valves CY-61, CY-62, CY-65, CY-68 and CY-69, shown in Figure 3-30, are open while all other block valves are closed. Syngas flow will be controlled by the high temperature flow control valve FCV-602A. If a failure occurs in this severe service valve, then FCV-602B which is exposed to ambient temperatures will take over.

The off-gas from the sorbent bed will pass through a purchased water cooled heat exchanger, an existing knockout pot, and through a Selexol H₂S removal unit before being sent to a flare. H₂S removal by the sorbent bed will be monitored by both an Extrel quadrupole process mass spectrometer and an Anarad H₂S Analyzer downstream of the sorbent bed. Sulfidation will stop and nitrogen purge will begin as soon as H₂S breakthrough is detected, which will nominally be defined at 500 ppm H₂S.

Following H₂S breakthrough, all lines in contact with syngas will be flushed to avoid intimate contact between syngas and air. Valves CY-61 and CY-62 will close, and valves CY-65 and CY-66 will open to allow nitrogen, preheated to 1300°F, to pass through the system. After less than one minute, valve CY-65 will close and valve CY-71 will open to purge the sorbent bed. Hot nitrogen will reduce the amount of thermal shock on the system and limit the potential of polythionic acid attack as described below. All block valve action will be controlled by a Square-D Programmable Logic Controller.

Regeneration

Following the syngas purge, valves CY-68 and CY-71 will close while valves CY-63, CY-70 and CY-67 will open. Gradually, an operator will open valve FCV-604 to increase the O₂ concentration

of the regeneration gas that is flowing through the sorbent bed in the opposite direction of the syngas flow. A zirconium oxide sensing element will closely monitor the O₂ concentration. Oxygen concentrations of approximately two percent will be maintained during regeneration; actual O₂ levels will be used to control the temperatures inside the sorbent bed.

The nominal space velocity, pressure and temperature will be 3000 hr⁻¹, 350 psig and 1300°F respectively. These nominal values will be adjusted during the run to investigate the effects of these process variables along with O₂ concentration on regeneration time. Regeneration will be terminated when the SO₂ level reaches 150 ppm. Based on previous work at RTI, we anticipate that regeneration will last approximately four hours.

The hot nitrogen and sulfur dioxide off-gas will pass through a water cooled heat exchanger before being sent to a flare. The total sulfur dioxide emissions from twenty cycles will be less than 300 lbs. Since this total amount is small, an expensive SO₂ recovery system is not justified and no attempt will be made to recover the sulfur.

Process and Reactor Design Considerations

Important process design and reactor considerations that were addressed include safety, heat effects and mass transfer limitations, analytical needs and process flexibility. The proposed design also addressed ease of operation, reliability and cost.

Safety

Safety considerations focus on preventing intimate contact between syngas and air and on preventing dangerous oxygen levels in the sorbent bed during regeneration. As shown in the process flow diagram, double block valves separate syngas and air during both sulfidation and regeneration to reduce the impact of leaks and potential valve failure. ANSI Class IV shutoff will be maintained between the syngas and air during both sulfidation and regeneration. To provide further safety, a pressurized nitrogen blanket will exist between the double block valves during both sulfidation and regeneration.

The dedicated oxygen analyzer will monitor the inlet oxygen concentration during regeneration to help prevent large temperature excursions. This information along with the sorbent bed temperature data will be sent to a PLC which will terminate the air flow if a dangerous condition is detected. The location of the oxygen analyzer has been chosen so that if an oxygen surge occurs in the feed line, the PLC will receive the information approximately 30 seconds before the excess oxygen reaches the sorbent bed.

Heat Effects

Heat effects due to heat loss from the sorbent bed and heat generation from the exothermic sulfidation, shift, and regeneration reactions are addressed by the proposed design.

The effects of heat loss from the sorbent bed can be reduced by any combination of the following three approaches: 1) electric heaters; 2) insulation; or 3) increased gas flow rate. Electric heaters were avoided in this design because of higher cost and lower reliability, and instead a combination of insulation and increased syngas capacity were chosen. The resulting reactor, shown in the drawings, is a compromise that maintains both small reactor size and acceptable heat losses.

A nominal syngas flow rate of 3000 SCFH in the sorbent bed will be five times greater than the flow rates suggested in the FY91 proposal, but as a result, the syngas temperature is expected to drop by only 50°F in the absence of reaction. If both the sulfidation and shift reactions occur, then the gas temperature is expected to rise 100°F. Here, the magnitude of the shift reaction was estimated from measurements at RTI. Calculations also show that temperatures near the wall of the reactor are sufficiently high to prevent water condensation from the syngas.

A similar situation holds during regeneration, except that the regeneration reaction releases more energy. Bulk adiabatic temperature rises of 350°F can be expected, and depending on heat transfer characteristics in the bed, even higher temperatures will be realized in the pellets and in certain sections of the bed.

Mass Transfer Limitation

The sulfidation reactions are rapid and H_2S transfer from the syngas to the pellet reduces the rate of sulfidation. As a result, axial sulfidation fronts of partially sulfided pellets develop. If the gas phase mass transfer is severe, long sulfidation fronts will develop and lead to premature H_2S breakthrough. Also this resistance may affect the shift reaction and skew the resulting gas compositions.

Previous RTI experiments at 350 psi demonstrated acceptably short sulfidation fronts for a 3 inch diameter x 15 inch cylindrical reactor at space velocities of approximately 2000 hr^{-1} . Calculations show that for a fixed space velocity, reductions in the length of the sulfidation front relative to total reactor length occur when the sorbent bed diameter is increased at constant L/D, and when the L/D is increased at constant sorbent utilization. Since the proposed reactor has both a larger

diameter and L/D when compared to the RTI reactor, the relative length of the sulfidation front should be shorter in comparison with the RTI experiments and closer to commercial practice.

Analytical Considerations

Sufficient data will be taken to perform mass and energy balances, to estimate reaction and diffusion rates, and to monitor sorbent properties.

Gas phase compositions from the sorbent bed inlet and outlet will be continuously monitored by an Extrel quadrapole mass spectrometer. The mass spectrometer will provide the data needed to monitor sulfidation, the shift reaction and SO₂ formation. The mass spectrometer will also monitor gas concentrations from inside the bed at two locations; this can be used to monitor the length of the sulfidation and regeneration fronts and extract kinetic and transport information.

A 1/4 inch diameter multi-point type K thermocouple sheath will pass through the center of the sorbent bed with the thermocouples spaced approximately six inches apart. This will help monitor the regeneration exotherm and provide information on the heat transfer characteristics of the sorbent bed. The temperature of the syngas entering and exiting the sorbent bed will be monitored. Four type J skin thermocouples will be placed on the exterior of the sorbent bed reactor and will help estimate the magnitude of heat loss from the bed.

Additionally, a sample port in the sorbent bed will enable one to remove the sorbent pellets between runs to measure the change in zinc content and crush strength.

Operation

Process operation will be automated with a Square-D Programmable Logic Controller which will actuate all block valves in the process (labelled CY-xx on the process flow diagram) based on inputs from the mass spectrometer, Anarad H₂S Analyzer, and timers. Operators only will need to make small adjustments to the oxygen flow during regeneration. A Kaye DIGI-4S data logger will record all flow rate, temperature and composition data.

Equipment Description

Specifications and descriptions of the equipment that will be purchased or built for this project are described below.

General

All of the equipment is designed to meet the following codes as appropriate: ASME Section VIII Unfired Pressure Vessel Code, ANSI Flange Code B16.5, Ansi Piping Code B31.3, and Class 1 - Division II Area classification. All of the equipment upstream of the coolers is designed for 1500°F and 350 psig.

Material Selection

Stainless steel 316 with controlled carbon content was chosen for the high temperature service, because it satisfies strength and creep properties at a much lower cost than alternative exotic materials such as Incoloy 800, 800H, and 825.

However, based on past experience at MRL, stainless steel 316 is highly susceptible to polythionic acid attack upon cooling. This occurs when the metal sulfides oxidize and combine with water. To eliminate this, all lines and valves that are in contact with hot syngas will be heat traced to eliminate water condensation during cycling and shutdown. Additionally, a hot nitrogen purge will be used during both cycling and shutdown.

Sorbent Bed Reactor

Details of the sorbent bed reactor are shown in Figure 3-30. The sorbent bed is 6.6 inches in diameter and 54 inches long, giving an L/D of 8.2 and a total volume of 1.07 cubic feet. A low iron Harbison and Walker castable refractory with a nominal thermal conductivity of 0.2 W/m/K will be used inside the carbon steel pipe for insulation.

As shown in the drawings, hot syngas will exit through a one inch 316 SS pipe. A six inch thick annular sleeve of castable refractory will protect the carbon steel flanges at the entrance and exit from overheating. Alumina balls above and below the sorbent bed will redistribute the gas flow.

High Temperature Valves

The high temperature valves are labelled in Figure 3-30 as CY-61, CY-62, CY-63, CY-65, CY-66, and FCV-602A. The high temperature valves are made of 316 stainless steel with graphfoil packing and extended bonnets to remove the packing from the high temperature syngas. All valves have a class IV shutoff.

Coolers

Two counter-current shell and tube process coolers will be purchased for this project. Both exchangers are ten feet in length and will reduce the gas temperature to 100°F. The exchangers are designed to withstand 1500°F and 500 psig and are ASME code inspected and stamped. HTR-1, shown in the process flow diagram has a maximum heat duty of 70 kW; HTR-2 has a maximum duty of 45 kW. Inner tubing will be constructed of schedule 80 Incoloy 800H, and the outer shell of carbon steel.

Electric Heater

A 70 kW electric impedance air preheater to preheat the regeneration gas will be purchased. The heater uses a 20 foot schedule 160 Incoloy 800H pipe as the heating element, and the pipe is enclosed in an insulated cabinet. The regeneration gas is heated as it flows through the pipe. The heater will satisfy Class 1, Division 2 area requirements. The electric heater will include an SCR power controller and type K hi-limit thermocouples that are welded to the pipe for over temperature protection.

Oxygen Analyzer

A zinc oxide oxygen analyzer will be purchased to analyze the inlet oxygen concentration of the regeneration gas. The location of the oxygen analyzer has been chosen so that if an oxygen surge occurs in the feed line, then the PLC will receive the information approximately six seconds before the excess oxygen reaches the sorbent bed. The analyzer will need to be calibrated only once per day and has an error of only one percent of full scale.

3.5 Advanced Instrumentation Testing

As part of our Cooperative Agreement with DOE, Texaco has agreed to test selected instruments developed by DOE for coal conversion processes. The tests are intended to extend the base of experience with these instruments from the laboratory to the pilot unit. It is also envisioned that successful application of these instruments to the Texaco PDU will support and enhance the main hot gas cleanup research and development efforts. At present four instruments have been chosen for testing:

- 1) a Fiber Optic Alkali Monitor (FOAM) which uses flame atomic emission spectroscopy to measure sodium and potassium in the syngas,

- 2) an Inductively Coupled Plasma Spectrometer (ICPS) which uses plasma atomic emission spectroscopy to measure trace elements in the syngas,
- 3) a Fiber Optic Fluorescence Thermometer (FOFT) which uses laser stimulated fluorescence to measure gasifier temperature, and
- 4) a Classical Scattering Aerosol Spectrometer (CSAS) which uses laser light scattering to measure syngas particle loadings and size distributions.

3.5.1 Fiber Optic Alkali Monitor

The Fiber Optic Alkali Monitor (FOAM) is a state-of-the-art instrument developed by the U.S. DOE for measuring sodium (Na) and potassium (K) in a gas stream. Measurements of alkali concentrations in syngas are important because it is known that alkali compounds attack combustion turbine blades. While there is virtually no experience with combustion turbines burning syngas from a gasifier employing hot gas cleanup, a limit of 24 wppb total alkali, derived from oil-fired experience, provides a benchmark for coal-based IGCC.

Also, below about 1000-1300°F, most of the alkali material will probably be in the particulate form. Therefore, alkali measurements may provide a convenient method for monitoring the effectiveness of particulate removal devices.

3.5.2 Description of FOAM Test Setup

Figure 3-32 shows a schematic overview of the apparatus employed at MRL to make alkali measurements in the syngas both before and after the Westinghouse ceramic crossflow filter (CXFF). A more detailed PFD is shown in Figure 3-33. The apparatus consists of five parts: the burner/detector, the controller/computer, the heat-traced sample lines, the heater controls and the calibration unit.

In the burner/detector unit, approximately 21 SCFH of syngas sample is burned in a propane and oxygen flame. The flame preheats and vaporizes any alkali particles, atomizes the various compounds and excites the Na and K atoms so that they emit light at their characteristic wavelengths. The optical system consists of a series of lenses, optical filters and detectors which measure the Na and K emissions.

The measured intensities are sent to the FOAM computer which mathematically filters out background emissions, calculates alkali concentrations, displays the results on a screen and stores the data for further analysis.

Figure 3-32. Fiber Optic Alkali Monitor System Overview

Figure 3-33. Fiber Optic Alkali PFD

In order to preserve the integrity of the syngas sample from the sample point to the FOAM burner, a special sample train is used. This sample train has four features. First, it is heat traced in order to preserve the vapor-to-particulate ratio of the sample and to prevent alkali material from condensing on cold sample lines. Second, it is designed to allow isokinetic sampling. By matching the velocity into the sampling probe with the velocity in the process pipe, it is hoped that the particle size distribution in the sample stream will closely resemble that of the main gas flow. Third, it has a 10-micron average pore size Hastelloy X sintered metal filter and a by-pass around the filter. When the filter is used, only vapor phase alkali is measured. When the by-pass is used, total (vapor plus particulate) alkali is measured. Finally, a so-called "double sampling arrangement" is employed in order to avoid the problems associated with taking a small flowrate (21 SCFH) of particle laden gas directly through a large pressure drop (350 psi).

The double sampling arrangement works as follows. Referring to Figure 3-33, a large flowrate (10 times that required for the burner) is drawn through the sample probe and passed through pressure reducing control valve #1 and the primary orifice. Because the flow is large, the trim in the valve and the orifice are large and less likely to plug with particles. Once the pressure is reduced and the volume of gas is expanded, the sizes of valve #2 and the secondary orifice can be increased so that the small flowrate of gas required for the burner can be passed with reduced risk of plugging. Excess gas is cooled and discharged into a low pressure flare line for disposal.

In addition to the above apparatus there is a calibration unit in which a known flowrate of alkali containing solution is atomized and mixed with a known flowrate of nitrogen. The mixture is heated and analyzed by the FOAM. By varying the ratio of solution flowrate to N₂ flowrate, gas rates with various alkali concentrations can be fed to the burner and a calibration curve created.

MRL personnel constructed the special sample train with its heater controls and connected the FOAM equipment when it arrived at the laboratory. Two researchers from Ames National Laboratory, Dr. Bill Haas and Mr. Dave Eckels, performed all of the actual sampling and measurements. They reported this work independently (Ref. 2).

3.5.3 FOAM Test Results Achieved

Approximately 31½ hours of alkali measurements were obtained during two air-blown gasification test runs on 7/27/89 and 8/8-10/89. Table 3-22 contains a summary of the data. Each of

Table 3-22. Fiber Optic Alkali Monitor (FOAM) Test Results

TEST PERIODS			SAMPLE STATUS				SODIUM			POTASSIUM			Na/K ratio		
FOAM	FIER	GASI 1989 Date	Time	(2) CXFF In- let or Outlet	(3)		(4) Total or Vapor Alkali	(5) rough avg. wppb	(6) high wppb	(7) low wppb	(5) rough avg. wppb	(6) high wppb	(7) low wppb	(8) feed sam- ple	(8) FOAM sam- ple
					Gasifier Temp degF										
1	a	7/27	1500-1935	OUT	650-1250	TOTAL	24	110	5.5	5.5	15	75	6.3	0.85	1.60
2	a	7/27	1935-2100	OUT	1250-1300	VAPOR	40	89	7.5	7.5	16	19	9.1	0.85	2.50
3	a	7/27	2100-2210	IN	1250	TOTAL	4000	51000	2400	2400	1600	39000	900	0.85	2.50
4.1	a	8/8	1000-1200	OUT	970-1075	TOTAL	1500	30000	470	470	1000	19000	380	0.85	1.50
4.2	B'	8/8	1200-1800	OUT	1175-1275	TOTAL	4500	84000	190	190	3600	85000	200	0.63	1.25
5.1	B'	8/8	1800-1830	OUT	1275	VAPOR	24	135000	3.5	3.5	20	39000	2.2	0.63	1.20
5.2	c	8/8	1830-1910	OUT	1310	VAPOR	200	35000	6	6	100	17000	2	0.85	2.00
5.3	c	8/8	1910-2000	OUT	1335-1360	VAPOR	0.5	360	0.07	0.07	0.7	170	0.36	0.85	0.71
6	c	8/8	2000-2030	OUT	1325-1345	TOTAL	6000	59000	2100	2100	1800	72000	920	0.85	3.33
7	e	8/9	0845-1110	OUT	1245-1345	TOTAL	1500	70000	310	310	500	10000	190	0.85	3.00
8.1	e	8/9	1110-1145	OUT	1240	VAPOR	9	4600	0.5	0.5	8	1500	0.5	0.85	1.13
8.2	F	8/9	1145-1315	OUT	1200-1240	VAPOR	6	350	0.1	0.1	5	200	0.23	0.58	1.20
9	F	8/9	1315-1600	OUT	1195-1210	TOTAL	4000	69000	7.1	7.1	4000	95000	6.9	0.58	1.00
10	F	8/9	1600-1830	IN	1180-1220	TOTAL	17000	81000	4700	4700	17000	98000	5000	0.58	1.00
11	F	8/9	1830-2000	OUT	1180-1200	TOTAL	5000	69000	3000	3000	8000	90000	3300	0.58	0.63
12	G	8/10	0800-0900	OUT	1115-1180	TOTAL	4000	32000	2800	2800	4000	16000	3000	0.58	1.00
13	G	8/10	0900-1140	IN	1080-1110	TOTAL	14000	66000	3400	3400	9000	80000	2600	0.58	1.56

- See next page of this table for numbered footnotes (f) beneath column headings.

- The gasifier was operated at a nominal 350 psig, and therefore the sample points were at roughly the same pressure.

Table 3-22 (cont'). Numbered Footnotes For Table 3-22

- (1) FOAM test periods are denoted by decimal numbers. Gasifier test periods are denoted by letters. Lower case indicates gasifier slurry feed without Fine Ox addition. Upper case indicates Fine Ox addition, which alters the Na/K ratio in the feed. The slurry in test period B' was a combination of Fine Ox and non-Fine Ox slurry which accidentally got mixed together.
- (2) This column indicates which sample probe was being used. "IN" is the probe immediately preceding the Westinghouse ceramic crossflow filter (CXFF). It provides a sample of dirty, particle laden syngas. "OUT" is the probe immediately downstream of the CXFF. When the CXFF is performing properly it provides a sample of filtered syngas.
- (3) The thermocouple was located at the syngas inlet to the CXFF, between the two sample probe locations. The range of temperatures reflects the varying syngas rate flowing through the radiant syngas cooler.
- (4) This column indicates whether or not the sample stream was being passed through the 10 micron Hastelloy X sintered metal filter. The unfiltered sample would contain alkali species in both the vapor and condensed phases (i.e. "total" alkali), while the filtered sample would contain primarily vapor phase alkali.
- (5) The averages in these columns are "rough" in the sense that they were visually derived by placing a straight edge along a plot of the data. Anomalous high or low data points were ignored, as well as those points occurring during transient phenomena. For example, at the beginning of period 5.1 when the sample was diverted through the sintered metal filter, the Na and K readings remained relatively unchanged from the previous period. After a period of time, however, the readings dropped significantly. This was most likely caused by the development, on the filter, of a "pre-coat" layer which more effectively removed alkali particles from the sample. Only the data points occurring after the drop in readings were included in the average.
- (6) These columns contain the highest data point occurring in each test period.
- (7) These columns contain the lowest data point occurring in each test period.
- (8) The sample feed Na/K ratios were obtained from the mineral analyses of the solids fed to the gasifier during each test period. The FOAM Na/K ratios were obtained by dividing the Na rough averages by the K rough averages.

the FOAM test periods represents a change in conditions, either in the way the sample was handled or in the operation of the gasifier. Figures C-1 through C-20 in Appendix C show all the data points plotted in two hour segments.

In general, the data can be divided into two groups: the data from 7/27, when the CXFF filtered gas had low levels of total alkali, and the data from 8/8 to 8/10, when the CXFF filtered gas had levels of total alkali approaching the level in the filter inlet gas.

The records from the second run indicate that there was difficulty in measuring the CXFF pressure drop during 8/8, and that sometime during the early morning hours on 8/9 the pressure drop fell to zero and remained there for the rest of the run. Following the run, it was discovered that most of the rods holding the filter elements in place were missing and that one element was displaced from its seat. If the sudden decrease in filter pressure drop signalled significant damage to the CXFF internals, then, perhaps, the high level of alkali in the outlet gas as early as 8/8 was an indication that the integrity of the CXFF had already deteriorated.

For a few short hours during FOAM test period 1, the total alkali level was below 24 wppb, which is a limit quoted by combustion turbine manufacturers based on their oil-fired experience. This result is encouraging, because it suggests that a Texaco air-blown gasifier employing a reliable CXFF would not be subject to significant alkali-induced turbine blade corrosion.

The syngas sample stream was filtered with the ten micron filter during test periods 2, 5.1, 5.2, 5.3, 8.1 and 8.2. During test period 2, the filter appeared to make no difference in the alkali levels measured in the CXFF outlet gas. Because the CXFF was performing well in removing all particles from the syngas during that test period, it indicates that the alkali material remaining in the syngas was either in the vapor phase or in the form of particles smaller than ten microns. However, as soon as the 10 micron filter was switched into the sample line during test periods 5.1 and 8.1, the measured alkali levels decreased. Starting with test period 4, the pilot unit operating data suggests that the CXFF suffered some sort of a breach which allowed significant quantities of particles to pass through the filter. This is reflected in the alkali data where the CXFF outlet alkali levels approach the inlet levels beginning with test period 4. Assuming that many alkali particles larger than ten microns passed through the CXFF, this would explain the dramatic decrease in measured alkali levels once the ten micron filter was used in the sample line.

The FOAM requires a constant flowrate of gas which is the same as the rate used during calibration. Several times during the course of the testing it was necessary to readjust the flowrate

into the sample line and the flowrate to the burner in order to compensate for changes in flow in the main process pipe. During vapor-only measurements, reduction in burner sample flow tended to decrease the alkali readings. However, during total alkali measurements, the trend is not so clear because of the very complex heat and mass transfer and vaporization processes occurring within the flame.

An example of the dependence of the measurements on sample flowrate can be seen in test period 5.3 (Figure C-21). Here the rate was reduced at the beginning of the period (at 1910 hours on 8/8), and the alkali readings followed. This period, in particular, shows just how sensitive the FOAM is. Na was measured as low as 70 wppt and K was measured as low as 360 wppt. In any case, it appears that a key to consistent measurements is maintaining a burner flowrate which is the same as that used during calibration.

The sample flowrate was affected not only by adjustment of the sample train flow control valves, but also by feedback from other parts of the PDU. In Figures C-21 through C-23, the data from selected time periods have been replotted with a slightly expanded time scale and with a line joining the sodium data points in order to show the cyclic variation in the magnitude of the alkali readings. This roughly six minute cycle was traced to a six minute cycle in the magnitude of the pressure of the laboratory's low pressure flare line. The FOAM sample train discharged excess sample gas into this flare line, and it appears as though the pressure variations fed back into the FOAM system and affected the measurements.

Finally, Table 3-22 shows that, for all but one test period, the Na/K ratio of the sampled gas differs from that of the gasifier feed. Either the syngas routed to the Westinghouse filter is enriched in Na, or the sample train collected a nonrepresentative sample.

4. PROCESS ECONOMICS STUDIES

4.1 Objective

The overall objective of this cooperative agreement is to develop and demonstrate an improved integrated coal gasification combined cycle power generation process using hot gas cleanup and the commercially proven Texaco Coal Gasification Process (TCGP). This includes PDU testing of various hot gas cleanup steps, with the goal of eventually incorporating the most promising ones into an integrated demonstration PDU. The Phase 2 process optimization studies were intended to provide guidance for the design of the integrated PDU by revealing those hot gas cleanup configurations having the greatest potential for commercialization as part of a Texaco-based grass roots IGCC plant.

4.2 Methodology

4.2.1 General

In order to determine the likelihood of commercialization, the overall plant efficiencies and costs for various hot gas cleanup configurations were compared against the efficiency and costs of a "base case" using conventional cold gas cleanup technology. Plant efficiencies were calculated as heat rates, i.e. total Btu's of energy into the plant per unit time divided by kilowatt-hours of generated electrical energy out of the plant per unit time. The cost numbers which were calculated were total capital cost (dollars per kilowatt), dispatch cost (dollars per kilowatt-hour) and levelized cost of electricity (dollars per kilowatt-hour). A more detailed scope of work is given in section 7.2.2.

The base case is a commercially available, Texaco-based IGCC power plant configuration. The raw syngas is cooled to ambient temperature before 98 percent of the sulfur is recovered in conventional sulfur removal and recovery units. The technology involved has been demonstrated and the costs are well known.

The hot gas cleanup configurations were chosen to evaluate the major high temperature desulfurization steps which are being tested in the PDU. Three different high temperature sulfur removal processes were evaluated, either separately or in combination. These were:

- pulverized iron oxide mixed with the coal-water slurry feed to the gasifier (in-situ desulfurization),

- pulverized dolomite-water slurry injected into the syngas downstream of the gasifier (external desulfurization), and
- fixed beds of zinc titanate located downstream of the gasifier (external desulfurization).

In addition, four methods of sulfur recovery were used. These were:

- fusion of iron sulfide with slag for disposal,
- oxidation of spent dolomite to calcium sulfate for disposal,
- oxidative regeneration of sulfided zinc titanate followed by sulfuric acid manufacture, and
- oxidative regeneration of sulfided zinc titanate followed by elemental sulfur recovery.

The hot gas cleanup cases were designed, wherever possible, as IGCC plants having the same performance as the base case in terms of SO_x and NO_x emissions. This was not possible in the dolomite-only and iron oxide-only cases because these sorbents, by themselves, are incapable of removing enough sulfur. In the case of dolomite-only, the plant was configured as an IGCC plant with only 90 percent sulfur removal. This will allow a crude comparison with competing coal technologies which use in-bed limestone or dolomite to remove only 90 percent of the sulfur. In the case of iron oxide-only, the maximum achievable sulfur removal of 50 percent is most likely going to be well below the level of removal required for new IGCC power plants. However, because an iron oxide feed system should be relatively inexpensive and easy to install, it was decided to investigate the use of iron oxide in-situ desulfurization as part of a gasifier retrofit of a pulverized coal-fired steam boiler. This alternative to flue gas desulfurization would have the advantage of allowing installation of a complete IGCC plant following the eventual retirement of the boiler.

Nine cases were evaluated, including the base case. Several subcases were also done in order to check the sensitivity of the results to certain process variables. The key process variables for all of the cases are summarized in Table 4-1; and detailed descriptions for each case are given in section 4.3.

The work was completed in two stages. Cases 1 through 4 were completed by August 1989. Cases 5 through 9 were completed by May 1990.

Table 4-1. DOE Process Economics Case Summary

Table 4-1. DOE Process Economics Case Summary												
CASE #	TYPE	PRES SYNGAS			DESULFURIZATION				SULFUR		POWER GENERATION	
		OXID	FUEL	PSIG	COOLING	%Fe	%Ca	%ZI	%MD	RECOVERY		TOI
1	IGCC	OXY	P#8	480	RO				98	98	Claus + Tail Gas Treating	2 (GE 7F+Stm)
2	IGCC	OXY	P#8	480	PQ + Ca		90			90	oxidize to CaSO4	2 (advCT+Stm)
3	RFIT	OXY	P#8	750	PQ	50		98		50	slag disposal	xpndr-->boiler
4	RFIT	AIR	P#8	750	PQ	50		98		50	slag disposal	xpndr-->boiler
5a	IGCC	OXY	P#8	480	RO			98		98	WSA2 ---> H2SO4 (O2=1%)	2 (advCT+Stm)
b	IGCC	OXY	P#8	480	RO			48		98	WSA2 ---> H2SO4 (O2=2.5%)	2 (advCT+Stm)
c	IGCC	OXY	P#8	480	RO			48		98	DSRP ---> elemental S	2 (advCT+Stm)
6a	IGCC	OXY	P#8	480	RO	50		48		98	slag + WSA2 ---> H2SO4 (O2=1%)	2 (advCT+Stm)
b	IGCC	OXY	P#8	480	RO	50		98		98	slag + WSA2 ---> H2SO4 (O2=2.5%)	2 (advCT+Stm)
c	IGCC	OXY	P#8	480	RO	50		98		98	slag + DSRP ---> elemental S	2 (advCT+Stm)
7c	IGCC	AIR	P#8	480	RO (HP+SH)			8		98	DSRP ---> elemental S	2 (advCT+Stm)
7d	IGCC	AIR	P#8	480	RO (HP+IP)			16		98	DSRP ---> elemental S	2 (advCT+Stm)
8	IGCC	OXY	P#8	480	PQ + Ca		90			98	oxidize to CaSO4	2 (advCT+Stm)
9	IGCC	AIR	P#8	480	PQ + Ca		82			98	oxidize to CaSO4	2 (advCT+Stm)

SYNGAS COOLING METHODS

- RO = Radiant Syngas Cooler only
- RO (HP+SH) = Radiant Syngas Cooler producing HP (1600 psia) saturated steam and HP superheated steam
- RO (HP+IP) = Radiant Syngas Cooler producing HP saturated steam and IP (400 psia) saturated steam
- PQ + Ca = syngas is cooled by the following processes: 1) partial quench by recycle syngas, 2) vaporization of dolomite slurry water, 3) endothermic calcination reactions, 4) partial quench by water spray prior to particulate removal

DESULFURIZATION

Fe - iron oxide added to coal slurry; Ca - dolomite slurry sprayed into syngas downstream of gasifier; ZT - fixed beds of zinc titanate downstream of gasifier; MD - conventional MDEA acid gas removal technology

SULFUR RECOVERY

WSA2 - Haldor Topsoe Wet Sulfuric Acid Process 2; ZnTi regenerated with N₂ containing either 1% or 2.5% O₂

DSRP - Research Triangle Institute Direct Sulfur Recovery Process

4.2.2 Scope of Work

Table 4-2 shows the scope of work, Table 4-3 lists the major technical criteria and Table 4-4 shows the coal and air compositions assumed for the calculations. The Pittsburgh No. 8 coal used in the calculations had the same properties as the "project" coal used in the PDU tests.

Table 4-2. Process Economics Scope of Work for Each Case

1. Conceptual Designs
 2. Overall Block Flow Diagrams
 3. Unit Process Flow Diagrams - only for those units simulated in detail (developmental units)
 4. Material and Energy Balances - level of detail depended on unit
 5. Performance and Emissions Data
 6. Capital Investment
 7. Operating and Maintenance Costs
 8. Cost of Electricity
-

4.2.3 Process Simulation

A conceptual design and process block flow diagram was made for each case. Each case was simulated on a computer using Texaco proprietary process simulation programs and in-house data. The level of detail for each unit depended upon the extent to which the unit was modified with respect to similar units in commercially available Texaco-based IGCC power plants.

Material and energy balance information for units which differed only in capacity was obtained by capacity factoring in-house data. Units which were completely new, such as the high temperature gas cleanup and sulfur recovery units, were simulated in detail. Detailed process flow diagrams were made for these units; individual pieces of equipment were designed; and material and energy balances were calculated.

Table 4-3. Process Economics Technical Criteria

1. West Virginia site
 2. Pittsburgh No. 8 bituminous coal
 3. Nominal 400 MW plant size
 4. Two GE 7001F advanced gas turbines, or similar - modified for hot gas cases
 5. 1450 psig / 1000°F / 1000°F reheat steam cycle - two 50% turbines each sharing a shaft with one of the gas turbines
 6. Minimum 98% sulfur recovery, wherever possible
 7. 42 ppm NO_x
 8. Proven processes and equipment except for hot gas cleanup processes and equipment integrating with those units
-

In the cases where outside vendor proprietary designs were involved, process designs and performance estimates were obtained from the vendor. The remaining units were simulated using a combination of the above two methods.

Finally, the energy input and output for each process unit was tabulated for the entire plant; and the heat rate was calculated for each case.

4.2.4 Economics Evaluation

Figure 4-1 shows the methodology used to estimate the total capital requirement for each case. The level of cost estimating detail for each unit corresponded to the level of detail in the process simulation described in section 7.2.3 above. For each process unit where conceptual process designs and equipment specifications were developed, individual equipment prices were obtained either from vendor quotes or from Texaco's internally supported design and cost estimating software. The costs for most other units were obtained by the capacity-factored estimating technique.

Table 4-4. Coal and Air Feed Data Used in Economic Analysis

Coal	Pittsburgh No. 8
Moisture (as received)	2.80
Proximate Analysis (dry basis)	
volatile matter	37.37
fixed carbon	56.08
ash	6.55
TOTAL	100.00
Ultimate Analysis (dry basis), wt%	
carbon	78.41
hydrogen	5.13
nitrogen	1.45
sulfur	2.14
ash	6.55
oxygen (by difference)	6.32
TOTAL	100.00
Gross Heating Value, Btu/lb	14092
Ash Fusion Temp., °F	
initial	1995
softening	2195
hemispherical	2280
fluid	2350
<hr/>	
Air Analysis (dry basis), mol%	
oxygen	20.99
nitrogen	78.03
argon	0.98
TOTAL	100.00
Ambient Pressure, psia	14.18
Dry Bulb Temp., °F	88
Wet Bulb Temp., °F	74
Water in wet air at 88°F, mol%	2.35

Figure 4-1. Capital Cost Estimating Methodology

The costs for the slag handling and process water systems, which were slightly modified in the hot gas cleanup cases compared with the cold gas cleanup base case, were obtained by the equipment-factored estimating technique. For these last two estimating techniques, Texaco's in-house proprietary data base was used.

Table 4-5 lists the components of the operating and maintenance cost calculations. In-house data were used for most of the calculations; however, vendor price quotes were obtained for some of the catalysts, feedstocks and by-products. The cost of electricity was calculated using a spreadsheet program developed by EPRI. The assumptions in the calculation are shown in Table 4-6.

Table 4-5. Process Economics O&M Cost Components

FIXED COSTS

- plant staff (overhead, operations, maintenance, O₂ plant)
- property taxes and insurance

VARIABLE COSTS

- contract maintenance labor
 - maintenance materials
 - re-start costs
 - catalysts, sorbents and chemicals
 - slag/spent sorbent disposal
 - ceramic filter element replacements
 - coal cost
 - sulfur/sulfuric acid credit
 - natural gas cost
-

Table 4-6. Process Economics Cost of Electricity Components

- EPRI methodology for cost of electricity (COE)
 - investor-owned utility analysis
 - discount rate for levelizing - return on common equity
 - mid-1990 is base year in which costs are expressed
 - 80% annual capacity factor using coal feed only
 - 6.0%/year general annual inflation rate
 - 6.0%/year PFI annual escalation rate
 - 6.0%/year operating and maintenance annual escalation rate
 - 6.0%/year raw material and by-product annual escalation rate
 - prepaid royalties (3% of unescalated PFI)
 - January 1, 1990 is beginning of construction
 - January 1, 1994 is beginning of commercial operation
 - allocation of PFI over design/construction years
(yr 1 - 15%, yr 2 - 25%, yr 3 - 35%, yr 4 - 25%)
98.3% nonexpensable portion each year
 - plant financing (35% common equity @ 15.3%/yr, 15% preferred stock @ 11.5%/yr, 50% debt @ 11.0%/yr)
 - 30 year book life
 - 20 year tax life (34% Federal, 9.68% State)
 - insurance rate (0.5% of escalated PFI)
 - property tax rate (1.5% of escalated PFI)
-

4.3 Case Descriptions

The plant designs for all of the IGCC-based cases were developed assuming the use of two advanced gas turbines, each of which is coupled to a multi-element reheat steam turbine on the same

shaft. Gas turbine performance for Case 1, the base case, was based on an estimate of performance anticipated using a GE Frame 7F. Gas turbine performance estimates for the remaining IGCC cases were developed assuming performance parameters similar to those used in developing the estimate for the base case. The fuel throughput for each case was set based on a fixed choke limit for the expansion turbine (same as estimated for Case 1), while allowing the compressor design and size to vary.

The temperature of the clean fuel gas delivered to the power cycle is not the same in all cases. In Case 1, the base case, the temperature is approximately 520°F, which is standard for a cold gas cleanup process with a fuel gas saturator/reheater before the combustion turbine. In Case 2, the IGCC case with 90 percent sulfur removal by dolomite, the fuel gas temperature is 1000°F. This value was imposed by what we understood to be the limit of turbine fuel gas control valve technology. In Cases 3 and 4, the PC boiler retrofit cases, the pressure of the hot fuel gas was decreased by expansion through a turbo-expander to a level acceptable by an atmospheric boiler. This expansion process dropped the temperature of the fuel gas to approximately 300°F in both cases.

Subsequent to the completion of the first four cases, and pursuant to conversations with DOE/METC personnel, it was decided to raise the fuel gas temperature to 1350°F in Cases 5 through 9. This was done in order to see how good the hot gas cleanup IGCC cases would look if they were not penalized by existing control valve temperature limits. The thought was that, should one or more of the cases look commercially attractive, then a serious development effort would be mounted to raise the operating temperature limits of turbine fuel gas control valves.

NO_x emissions are controlled in Case 1 by adding water to the fuel gas in a saturator tower. In all of the other IGCC cases, except Case 2, Selective Catalytic Reduction of NO_x in the heat recovery steam generator (HRSG) is used. In Case 2, an ammonia removal catalyst is used upstream of the combustion turbines.

Heat recovered throughout the plant, and from the exhaust of the gas turbines, is used to raise various levels of steam. Some of the steam is used throughout the plant, but most is used to drive two multi-element (1450 psig/1000°F/1000°F) reheat steam turbines. Each steam turbine is coupled to the same shaft as one of the gas turbines. The total nominal output of the combined cycle plant is 400 megawatts.

The two pulverized coal boiler retrofit plants (Cases 3 and 4) are sized to provide the total thermal input required by the 500 megawatt plants cited in EPRI Report AF-1182.

4.3.1 Case 1: Cold Gas Cleanup Base Case

The base case is a commercially available, Texaco-based IGCC power plant configuration. It represents the latest version of Texaco's "standard design" coal-based IGCC. Figure D-1 in Appendix D shows the major features of the process flow. The plant design is similar to that of the Cool Water plant, with the exception that no convective syngas cooler is used. However, it employs all of the advanced features which were developed during the proprietary "Gasification Enhancement Study" done jointly by Texaco and Fluor Daniel. This is the case against which all of the hot gas cleanup cases are compared.

The gasifier is operated in the oxygen-blown mode and desulfurization is done externally using conventional acid gas solvent scrubbing technology. Syngas from the gasifier is first cooled in a radiant syngas cooler before being contacted directly with water in a water pool, a venturi scrubber and a tray scrubber vessel. Virtually all of the particulate matter in the gasifier effluent syngas is removed by the direct water contacting operations. The solids entering the water system are dewatered to 50 percent solids and sent to disposal.

Syngas leaving the tray scrubber is cooled before being scrubbed, at ambient temperature, with an MDEA solvent for removal of sulfur compounds. More than 98 percent of the sulfur and approximately 8 percent of the CO₂ are removed by the solvent. Offgas from regeneration of the solvent is sent to a Claus unit followed by tail gas treating. Sulfur is recovered in the elemental form. Overall sulfur recovery for the entire plant is 98 percent.

Clean fuel gas is saturated with water in a saturator tower and then heated to 520°F before being burned in GE Frame 7F combustion turbines. NO_x emissions are controlled by the water added to the fuel gas. Steam generated in the HRSG, radiant syngas cooler and within the various process units is used to drive steam turbines which share the same shafts with the combustion turbines.

This plant is configured to operate with three 50 percent gasifier, radiant syngas cooling and water scrubbing trains, two 50 percent low temperature gas cooling and MDEA scrubber trains, two 100 percent Claus units, one 100 percent tail gas treating unit, two 50 percent combustion turbine/steam turbine trains, and two 50 percent HRSGs.

4.3.2 Case 2: Entrained Bed Dolomite Slurry

Figures D-2 and D-3 in Appendix D show the major features of this case. Figure D-2 shows the gasifier, high temperature heat

recovery and dolomite-based hot gas cleanup process flow. Figure D-3 shows the spent dolomite regeneration. The gasifier is operated in the oxygen-blown mode, and external desulfurization is done with dolomite, a mineral form of $\text{MgCO}_3 \cdot \text{CaCO}_3$. Approximately 92 percent of the sulfur in the syngas is removed by reaction with the calcium in the dolomite. Greater desulfurization is prevented by chemical thermodynamic equilibrium limitations.

Syngas from the gasifier reaction chamber is passed through a slag disengaging zone before being partially quenched with cool, recycled syngas. The amount of quench cooling is regulated to provide an optimum temperature at the inlet to the entrained bed desulfurizer. In the desulfurizer, a 60 wt percent water slurry of pulverized dolomite (mass mean diameter of 10μ) is injected into the syngas to provide a calcium-to-sulfur ratio of two. The amount of recycled syngas used to atomize the injected slurry is two volumes of gas per volume of slurry, at the process conditions. Ninety percent of the sulfur species in the syngas is removed in the desulfurizer. The spent dolomite (sulfided and unreacted dolomite particles) is removed from the syngas in a cyclone followed by a ceramic cross flow filter. The clean fuel gas is then cooled to 1000°F in heat exchangers before being burned in the combustion turbines.

In the sulfur recovery unit, the spent dolomite particles are converted to CaSO_4 for disposal in a landfill. The conversion takes place at 1800°F in an entrained bed oxidizer where the particles are reacted with hot air extracted from the combustion turbine air compressor. It is assumed that all of the CaS is either converted to CaSO_4 or encapsulated in fully oxidized material. This appears reasonable, given the high oxidizer temperature and the 6-to-1 O_2 to CaS ratio. CaSO_4 particles are removed from the oxidizer offgas by a cyclone and a ceramic cross flow filter before being cooled and returned to the combustion turbine.

This plant is configured to operate with three 50 percent gasifier and hot gas clean up trains, one 100 percent sulfur recovery train, two 50 percent combustion turbine/steam turbine trains, and two 50 percent HRSGs.

4.3.3 Case 3: In-situ Iron Oxide

Case 3 is a non-integrated retrofit case where the gasification plant is sized to provide fuel for a nominal 500 MW pulverized coal fired boiler. Figure D-4 in Appendix D shows the process flow for the gasification and hot gas cleanup units.

The gasifier is operated in the oxygen-blown mode using purchased oxygen. The power station's existing coal handling facilities

are used for coal feed preparation. Sulfur is removed inside the gasifier by adding iron oxide to the coal slurry. Fifty percent of the sulfur in the syngas is captured by the iron oxide; and the resulting iron sulfide is fused with the slag, which exits the gasifier through the lockhopper system.

Syngas from the reaction chamber passes into a slag disengaging zone in the middle of the gasifier and then exits through a refractory lined port at the side of the vessel. Sulfur bearing slag is captured and quenched in a pool of water at the bottom of the gasifier. The 50 percent desulfurized syngas is partially quenched with injected water and then filtered in a ceramic cross flow filter before being expanded to low pressure through a power generating gas turbine. The low pressure gas is exported to the boiler facility where it is burned with air in modified burners. The sulfur bearing slag and filtered fines are sent to disposal. Except for the coal feed preparation facilities, no attempt is made in this case to integrate any of the gasifier systems with the generating facility systems.

4.3.4 Case 4: In-situ Iron Oxide (air-blown)

Case 4 is the same as Case 3 except that air is used instead of oxygen. Figure D-5 in appendix D shows the main features of the case. When this case was evaluated it was assumed that air-blown gasification with in-situ desulfurization would achieve the same level of sulfur removal as in the case of oxygen-blown gasification. Subsequent pilot plant data showed that the level of desulfurization is only 33 percent.

4.3.5 Case 5: Fixed Bed Zinc Titanate

Figures D-6 through D-8 in Appendix D show the major features of this case. Figure D-6 shows the gasifier and hot gas cleanup units, while figures D-7 and D-8 show the sulfur recovery units used in the three subcases.

The gasifier is operated in the oxygen-blown mode, and sulfur is removed using external fixed beds of zinc titanate (ZnTi). The beds are regenerated with dilute streams of O_2 , and the sulfur is recovered either as 98 wt percent sulfuric acid or as elemental sulfur. This case is subdivided into three subcases, depending upon the method used to recover the sulfur. Case 5a uses 1 vol percent O_2 in N_2 to regenerate the beds before recovering 98 wt percent H_2SO_4 in the Wet Sulfuric Acid 2 (WSA2) process developed by Haldor Topsoe. Case 5b is similar to 5a except that 2.5 vol percent O_2 is used. Case 5c uses 1.5 vol percent O_2 to regenerate the beds before recovering elemental sulfur in the Direct Sulfur Recovery Process developed by Research Triangle Institute.

Syngas leaving the gasifier reaction chamber is cooled in a radiant syngas cooler where 1600 psia steam is generated. Slag is separated from the syngas at the bottom of the cooler and is quenched in a water pool before being dewatered and sent to disposal. The syngas cooler exit temperature is selected so that, after the syngas heats up in the ZnTi beds as a result of the shift reaction, the final fuel gas temperature going to the turbine is 1350°F.

Final particulate removal is done by a cyclone and a ceramic cross flow filter before the syngas enters the first of two ZnTi beds. Most of the sulfur is removed in the first (main) bed, with the second one serving as a guard bed. The beds are sized so that, when the outlet sulfur concentration leaving the first bed approaches the inlet concentration, there is still a considerable amount of sulfur absorbing capacity left in the guard bed. The beds are then switched so that the guard bed becomes the main bed, the main bed begins oxidative regeneration as part of the sulfur recovery unit, and the regenerated bed from the sulfur recovery unit becomes the guard bed. When switched into its new position, the guard bed receives essentially sulfur free gas from the main bed and undergoes a reductive regeneration.

Clean fuel gas leaving the guard bed undergoes one last particulate removal polishing step in a ceramic cross flow filter before being sent to the combustion turbine.

Wet Sulfuric Acid - Subcases 5a and 5b

In the wet sulfuric acid plant, regeneration gas for the ZnTi bed is obtained by diluting a small amount of air with a portion of the N₂ vent gas stream from the oxygen plant. The combined stream is first heated by recovering waste heat from the WSA tower and then by a fired heater.

In the regenerating bed, oxygen reacts with ZnS to form ZnO and SO₂. Part of the energy of the very hot regeneration offgas is recovered in raising high pressure steam. The gas is then mixed with enough air to increase the O₂ concentration to 10.5 percent before entering the SO₂ converter where 98 mol percent of the SO₂ is converted to SO₃. The converter offgas passes through two hydration coolers where a portion of the SO₃ reacts with the H₂O (brought in with the air and O₂ plant vent gas) to form H₂SO₄.

After the hydration coolers, the hot gases pass upwards through the WSA2 tower, which consists of a collection of glass tubes cooled on the outside by the incoming air and O₂ plant vent gas streams. As the sulfur bearing gases cool on the inside of the glass tubes, the remainder of the SO₃ reacts to form H₂SO₄, and

all of the H_2SO_4 vapor condenses and collects as 98 wt percent sulfuric acid at the bottom of the tower.

The main difference between subcases 5a and 5b is that the regeneration gas contains 1 vol percent O_2 in 5a and 2.5 vol percent O_2 in 5b. In subcase 5a the compressors are larger than in 5b because of the larger volume of gas which must be compressed. However, no ZnTi bed intercooler is needed as in 5b because the temperature rise in the bed is much smaller.

Direct Sulfur Recovery - Subcase 5c

In the Direct Sulfur Recovery Process, developed by Research Triangle Institute, regeneration gas for the ZnTi bed is obtained by diluting a small amount of air with a recycled portion of the offgas from the unit. Bottled N_2 is used in place of recycled offgas at startup. The combined gas stream is heated in a fired heater prior to regenerating the ZnTi bed.

In the regenerating bed, oxygen reacts with ZnS to form ZnO and SO_2 . The offgas from the regeneration is mixed with an appropriate amount of syngas in order to convert some of the SO_2 into H_2S before entering the two catalyst beds. In the beds, SO_2 and H_2S react via the Claus reaction to form elemental sulfur which is condensed out in the series of coolers after each bed. A small amount of additional air is added to the gas entering the second bed in order to optimize the H_2S -to- SO_2 ratio entering that bed.

4.3.6 Case 6: In-situ Iron Oxide plus Fixed Bed Zinc Titanate

Case 6 is similar to Case 5 except that 50 percent of the sulfur is removed in the gasifier by iron oxide added to the coal slurry. The remaining 48 percent of the sulfur is removed by external fixed beds of ZnTi which are correspondingly smaller than those in Case 5. Case 6 is divided into three subcases paralleling those in Case 5. Process flow diagrams showing the major feature of this case are located in Appendix D. Figure D-9 shows the gasification and hot gas cleanup units. Figures D-10 and D-11 show the sulfur recovery units used in the three subcases.

4.3.7 Case 7: Fixed Bed Zinc Titanate (air-blown)

Figures D-12 through D-14 in Appendix D show the major features of this case. Figure D-12 shows the gasifier and hot gas cleanup units. Figure D-13 shows the extracted air pressure boosting system; and Figure D-14 shows the sulfur recovery unit.

Case 7 is similar to Case 5 except that the gasifier is operated in the air-blown mode. Air-blown operation effects the configuration of the sulfur recovery unit. Because there is no oxygen plant vent gas stream available, some other medium is needed to dilute the O_2 used to regenerate the ZnTi beds if sulfur is to be recovered as sulfuric acid. (The Direct Sulfur Recovery Process uses recycled offgas and is unaffected by air-blown operation.) Several alternative methods of producing dilution gas were investigated, including burning propane and injecting steam. Propane burning was rejected because of the high cost and the deleterious effect on the heat rate. Steam injection was rejected because it was believed that the performance of the Wet Sulfuric Acid plant would be seriously degraded by the presence of large amounts of excess water. Consequently, it was decided to recover sulfur using only the Direct Sulfur Recovery Process.

Case 7 was divided into four subcases: 7c, 7c@, 7d and 7d@. Because the air-blown gasifiers produce such a huge volume of low-Btu syngas which must be cooled in large radiant syngas coolers (RSCs) before entering the zinc titanate beds, more high pressure (HP) saturated steam is produced than can be superheated and reheated in the HRSG. In order to bring the steam system into balance, two different constructions of the RSCs were investigated. The letter "c" subcase designation is for the subcase where the RSC produces HP saturated steam only, followed by a de-rating of some of the steam to intermediate pressure (IP) saturated steam external to the RSC. The letter "d" subcase designation is for the subcase where a portion of the RSC heat exchange surface is modified to produce HP superheated steam directly.

The letter "@" subcase designation indicates that four trains of gasifiers, RSCs and hot gas cleanup units were used instead of seven. The maximum size of the RSC which can be shop fabricated and shipped to a given location is usually the determining factor in deciding how many gasifier trains are needed. In this case, shop fabricated RSCs required seven trains. This was a substantial increase over the three trains used in the oxygen-blown cases. In order to investigate the effect of field fabrication on overall costs, subcases 7c@ and 7d@ used four trains of field fabricated RSCs. Further reduction in the number of trains was limited by gasifier design considerations.

4.3.8 Case 8: Entrained Bed Dolomite Slurry plus Fixed Bed Zinc Titanate

The process flow diagrams in Appendix D show the main features of this case. Figure D-15 shows the gasifier and hot gas cleanup units. Figure D-16 shows the sulfur recovery unit.

Case 8 is similar to Case 2. However, the level of desulfurization is raised to 98 percent by the addition of a fixed bed of zinc titanate downstream of the dolomite entrained bed desulfurizer. The offgas from the ZnTi bed is filtered in a cross flow filter before being sent to the combustion turbine at 1350°F. The sulfur recovery unit is also similar to Case 2, except that the capability to regenerate a ZnTi bed has been added.

The dilute O₂ containing stream for regenerating the ZnTi bed is obtained by mixing a small amount of air with the 99.1 percent N₂ vent gas from the oxygen plant. The dilute SO₂ containing regeneration offgas is sent to the oxidizer to react with unused dolomite and air to form CaSO₄. The CaSO₄ is sent to disposal.

This plant is configured to operate with three 50 percent gasifier and hot gas cleanup trains, one 100 percent sulfur recovery train, two 50 percent combustion turbine/steam turbine trains, and two 50 percent HRSGs.

4.3.9 Case 9: Entrained Bed Dolomite Slurry plus Fixed Bed Zinc Titanate (air-blown)

Case 9 is similar to Case 8 except that the gasifier is operated in the air-blown mode. Figures D-17 and D-18, in appendix D, show the gasification/hot gas cleanup and sulfur recovery units, respectively.

For syngas produced by air-blown gasification, desulfurization with dolomite is limited by chemical thermodynamic equilibrium to 81.5 percent. Consequently, the ZnTi beds are sized to remove 16.5 percent, for a total desulfurization of 98 percent.

The sulfur recovery unit is similar to Case 8. The air feed is extracted from the combustion turbine compressor and is boosted in pressure upstream of the oxidizer.

One other significant difference exists between Cases 9 and 8. There is no oxygen plant to provide a large N₂ rich stream to dilute the O₂ used in regenerating the ZnTi beds. Superheated 400 psia steam is used as a dilution medium instead.

4.4 Results Achieved and Discussion

In order to determine the likelihood of commercialization, the overall plant efficiencies and costs for various hot gas cleanup configurations were compared against the efficiency and costs of a "base case" using conventional cold gas cleanup technology. Plant efficiencies were calculated as heat rates, i.e. total Btu's of energy into the plant per unit time divided by kilowatt-

hours of generated electrical energy out of the plant per unit time. The cost numbers which were calculated were total capital cost (dollars per kilowatt), dispatch cost (dollars per kilowatt-hour) and levelized cost of electricity (dollars per kilowatt-hour).

Table 4-7 summarizes the above efficiencies and costs for all of the cases. Table 4-8 summarizes the power production and use throughout the plant on a unit-by-unit basis for all cases. Tables 4-9 and 4-10 list the plant investment costs; and Tables 4-11 through 4-14 summarize the operating and maintenance costs for each case.

More detailed cost information can be found in Appendix E, where equipment cost data are given, by unit, for each process unit where conceptual process designs and equipment specifications were developed.

4.4.1 Plant Efficiency (Heat Rate)

The major process variables investigated in this series of studies are:

- 1) type of oxidant (O_2 versus air),
- 2) method of high temperature desulfurization (amine scrubbing at ambient temperature, in-situ iron oxide only, entrained bed dolomite only, fixed bed zinc titanate only, in-situ iron oxide plus fixed bed zinc titanate, and entrained bed dolomite plus fixed bed zinc titanate),
- 3) method of sulfur recovery (slag encapsulation, spent dolomite oxidation, sulfuric acid and elemental sulfur), and
- 4) end use of the fuel gas (combined cycle or Rankine cycle only).

The effect of these variables on plant heat rate is discussed below.

Oxidant

The heat rate for the base case is 8929 Btu/kWh. From Table 4-7 it can be seen that Cases 5a, 5b, 5c, 6a, 6b, 6c and 8 all have lower heat rates, i.e. higher efficiencies. All of these cases use oxygen-blown gasifiers. The cases using air-blown gasifiers (4, 7c, 7c@, 7d and 7d@) all have higher heat rates.

The main factors contributing to the higher heat rates of the air-blown cases, despite the elimination of the oxygen plant, are the decreased gasification efficiency and the transfer of a

Table 4-7. DOE Economics Cases 1 - 9 Summary of Results

		DOE1	DOE2	DOE3	DOE4	DOE5a	DOE5b	DOE5c	DOE5d	DOE5e	DOE5f	DOE5g	DOE5h	DOE5i	DOE5j	DOE5k	DOE5l	DOE5m	DOE5n	DOE5o	DOE5p	DOE5q	DOE5r	DOE5s	DOE5t	DOE5u	DOE5v	DOE5w	DOE5x	DOE5y	DOE5z	
HEAT RATE (Btu/kWh)		8929	8921	9960	13903	8861	8554	8710	8733	8578	8659	9227	9227	9227	9146	9146	9146	9146	9146	9227	9227	9227	9227	9227	9227	9227	9227	9227	9227	9227	9227	
INVESTMENT (\$/kW)		1494	1474	254	761	1919	1693	1603	1726	1617	1563	2392	2018	2351	1972	1621	1776															
DISPATCH COSTS (mils/kWh)																																
no. ZT																																
cycles	coal	DOE1	DOE2	DOE3	DOE4	DOE5a	DOE5b	DOE5c	DOE5d	DOE5e	DOE5f	DOE5g	DOE5h	DOE5i	DOE5j	DOE5k	DOE5l	DOE5m	DOE5n	DOE5o	DOE5p	DOE5q	DOE5r	DOE5s	DOE5t	DOE5u	DOE5v	DOE5w	DOE5x	DOE5y	DOE5z	
50		16.1	19.7	29.0	26.3	47.1	45.3	45.6	34.1	33.1	33.5	51.3	50.3	50.7	49.8	21.5	27.0															
		28.2	31.8	42.5	45.1	59.0	56.8	57.3	45.9	44.7	45.2	63.7	62.7	63.0	62.0	33.1	39.8															
200		31.8				25.2	23.2	24.3	23.0	22.0	22.6	28.3	27.3	28.0	27.0	19.6	22.7															
		63.6				37.1	34.7	36.0	34.8	33.6	34.2	40.7	39.7	40.2	39.3	31.2	35.5															
1000		31.8				19.4	17.3	18.7	20.1	19.0	19.7	22.1	21.2	21.9	20.9	19.1	21.5															
		63.6				31.3	28.8	30.3	31.8	30.6	31.3	34.5	33.6	34.2	33.2	30.7	34.3															
LEVELIZED COST OF ELECTRICITY (mils/kWh)																																
no. ZT																																
cycles	coal	DOE1	DOE2	DOE3	DOE4	DOE5a	DOE5b	DOE5c	DOE5d	DOE5e	DOE5f	DOE5g	DOE5h	DOE5i	DOE5j	DOE5k	DOE5l	DOE5m	DOE5n	DOE5o	DOE5p	DOE5q	DOE5r	DOE5s	DOE5t	DOE5u	DOE5v	DOE5w	DOE5x	DOE5y	DOE5z	
50		49.9	55.1	37.1	45.6	88.7	82.7	81.1	71.4	68.4	67.6	104.5	95.0	103.1	93.2	57.3	66.3															
		62.0	67.2	50.6	64.4	100.6	84.3	92.8	83.2	80.0	79.3	116.9	107.3	115.4	105.4	68.8	79.1															
200		31.8				68.7	60.4	59.6	60.2	57.1	58.6	81.3	71.4	80.1	70.1	55.4	61.9															
		63.6				78.5	71.9	71.2	72.0	68.7	68.2	93.6	83.8	92.4	82.4	67.0	74.7															
1000		31.8				60.8	54.4	53.8	57.2	54.1	53.6	75.1	65.2	74.0	64.0	54.9	60.7															
		63.6				72.6	65.9	65.5	69.0	65.7	65.3	87.5	77.6	86.2	76.3	66.4	73.5															

Table 4-8. DOE Economics Cases 1 - 9 Power Summary

UNIT	UNIT NAME	DOE1	DOE2	DOE3	DOE4	DOE5a	DOE5b	DOE5c	DOE5d	DOE5e	DOE5f	DOE5g	DOE5h	DOE5i	DOE5j	DOE5k	DOE5l	DOE5m	DOE5n	DOE5o	DOE5p	DOE5q	DOE5r	DOE5s	DOE5t	DOE5u	DOE5v	DOE5w	DOE5x	DOE5y	DOE5z
12	LIGHTING & A/C	1634.4	1634.4	92.1	92.1	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4	1634.4
16	RIVER WATER INTAKE	139.1	110.8	33.6	36.1	137.6	127.7	136.6	123.3	136.6	123.3	136.6	123.3	136.6	123.3	136.6	123.3	136.6	123.3	136.6	123.3	136.6	123.3	136.6	123.3	136.6	123.3	136.6	123.3	136.6	123.3
21	FUEL OIL SUPPLY	38.1	38.1	0.0	0.0	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1	38.1
23	COAL/DOLOM HANDLING	103.3	101.4	0.0	0.0	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3	93.3
30	AIR BOOST/OXIDATION	0.0	7076.3	0.0	234793.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
31	OXYGEN PLANT	43544.9	42748.0	0.0	0.0	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2	39398.2
41	GRIND & SLURRY PREP	2588.3	2521.4	1000.3	1171.7	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8	2318.8
42	GASIFICATION & HGC	1234.9	2551.5	1448.8	1650.7	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3	1818.3
43	SLAG HANDLING	24.7	24.2	63.6	78.9	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3	22.3
44	SYNGAS SCRUBBING	388.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
45	BLACK WATER SYSTEM	275.8	140.5	710.9	854.9	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5	173.5
46	FINES FILTRATION	117.3	59.8	302.4	363.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8	50.8
51	LOW TEMP GAS COOLING	148.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
52	AGR or WSA2	418.9	0.0	0.0	0.0	20771.7	8725.4	0.0	10214.0	4782.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
53	CLAUS or DSRP	169.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
54	TAIL GAS TREATING	78.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
55	FUEL GAS SATURATION	174.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
61	C.T. GENERATORS	1076.0	1076.0	0.0	0.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0	1076.0
63	S.T. GENERATORS	107.0	103.9	0.0	0.0	122.7	113.6	120.6	108.8	104.4	107.8	108.2	107.8	108.2	107.8	108.2	107.8	108.2	107.8	108.2	107.8	108.2	107.8	108.2	107.8	108.2	107.8	108.2	107.8	108.2	107.8
64	CONDENSATE & BFW	3585.0	2813.0	0.0	0.0	4011.1	3716.0	3945.0	3558.6	3413.5	3523.8	3498.6	3413.5	3523.8	3498.6	3413.5	3523.8	3498.6	3413.5	3523.8	3498.6	3413.5	3523.8	3498.6	3413.5	3523.8	3498.6	3413.5	3523.8	3498.6	3413.5
71	GENERAL MAKEUP H2O	304.2	242.3	73.5	79.0	300.9	279.2	298.8	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7	269.7
72	DEMINERALIZED H2O	247.0	43.8	43.8	47.2	70.9	70.3	72.4	78.2	77.9	78.7	107.2	106.5	107.2	106.5	107.2	106.5	107.2	106.5	107.2	106.5	107.2	106.5	107.2	106.5	107.2	106.5	107.2	106.5	107.2	106.5
73	CIRCULATING H2O	3982.8	4258.6	29.4	363.7	4366.2	4076.5	4305.6	3939.9	3786.7	3922.9	6126.1	3782.8	6126.1	3782.8	6126.1	3782.8	6126.1	3782.8	6126.1	3782.8	6126.1	3782.8	6126.1	3782.8	6126.1	3782.8	6126.1	3782.8	6126.1	3782.8
75	GENERAL WASTEWATER	23.1	27.4	6.6	7.0	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4
76	PROCESS WASTEWATER	327.5	44.0	80.0	95.7	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3	89.3
77	FIRE WATER	102.2	102.2	24.3	26.1	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2	102.2
91	PLANT & INSTR. AIR	404.8	404.8	24.3	24.3	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8	404.8
Total In-Plant Use (MW)		91.7	96.6	3.9	236.7	77.6	65.9	60.1	64.7	59.0	56.1	91.4	81.4	91.4	81.4	91.4	81.4	91.4	81.4	91.4	81.4	91.4	81.4	91.4	81.4	91.4	81.4	91.4	81.4	91.4	81.4
C.T. NET (MW)		314.200	312.334	97.705	232.336	290.015	290.015	288.094	290.239	290.239	289.271	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625	286.625
S.T. NET (MW)		199.220	198.181	474.206	470.830	233.991	216.788	230.136	207.594	199.154	205.553	320.765	325.368	320.765	325.368	320.765	325.368	320.765	325.368	320.765	325.368	320.765	325.368	320.765	325.368	320.765	325.368	320.765	325.368	320.765	325.368
IGCC NET OUTPUT (MW)		451.743	443.894	567.968	463.584	446.448	440.944	458.156	433.105	430.415	438.715	525.989	530.635	525.989	530.635	525.989	530.635	525.989	530.635	525.989	530.635	525.989	530.635	525.989	530.635	525.989	530.635	525.989	530.635	525.989	530.635
DRY COAL RATE (LB/HR)		286219.1	281010.5	431502.7	491609.5	259937.7	259937.7	262859.1	277003.1	277003.1	276904.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8	324533.8
COAL IN (MMBTU/HR - HHV)		4033.4	3990.0	5657.0	6445.0	3649.0	3649.0	3704.2	3631.5	3631.5	3657.8	4573.3	4573.3	4573.3	4573.3	4573.3	4573.3	4573.3	4573.3	4573.3	4573										

Table 4-9. Plant Investment Summary for Cases 1 - 4

	(\$/kWh, mid-90\$)			
	<u>DOE1</u>	<u>DOE2</u>	<u>DOE3</u>	<u>DOE4</u>
Site Work & Buildings	40	41	3	4
Fuel Handling	38	38	0	0
Oxygen Plant/Air Comp	106	106	0	104
Gasification	189	85	71	154
Gas Treat. & Process Strm	60	150	0	0
Power Generation	294	309	48	145
Water Systems	70	61	6	7
Electrical	75	77	6	7
Balance of Plant	30	30	2	3
Boiler Modifications	<u>0</u>	<u>0</u>	<u>19</u>	<u>38</u>
Total Direct Field Costs	902	898	154	462
Total Indirect Field Costs	<u>199</u>	<u>195</u>	<u>34</u>	<u>100</u>
Total Field Costs	1100	1093	188	562
Total Office Costs	194	186	33	98
Sales Tax (6%)	38	37	6	19
Contingency (12%)	<u>162</u>	<u>158</u>	<u>27</u>	<u>82</u>
Plant Facilities Investment	1494	1474	254	761
Plant Net Power (kWh)	451743	443894	567968	463584

Table 4-10. Plant Investment Summary for Cases 5 - 9
Page 1 of 2

(\$/kW, mid-90\$)

UNIT	DESCRIPTION	1	5A	5B	5C	6A	6B
21	Fuel Oil Supply	8.9	9.0	9.1	8.8	9.3	9.3
22	Natural Gas Supply	0.1	0.1	0.1	0.1	0.1	0.1
23	Coal Supply	28.7	27.9	28.2	27.4	29.7	29.9
24	Dolomite Supply	0.0	0.0	0.0	0.0	0.0	0.0
25	Misc. Material Handling	0.3	0.4	0.4	0.3	0.4	0.4
30	Air Compression	0.0	0.0	0.0	0.0	0.0	0.0
31	Oxygen Plant	105.8	104.4	105.8	102.7	105.3	106.0
41	Coal Grinding & Slurry Prep	12.5	11.7	11.8	11.5	13.3	13.4
42	Gasif & Desulfurization	144.7	245.7	248.8	241.1	227.6	229.1
43	Slag Handling	12.8	10.8	10.9	10.6	16.6	16.7
44	Syngas Scrubbing	10.3	0.0	0.0	0.0	0.0	0.0
45	Black Water Handling	3.8	1.6	1.6	1.8	2.6	2.6
46	Fines Filtration	2.4	3.1	3.2	3.1	4.9	4.9
47	Auxiliary Boiler	2.4	2.4	2.5	2.4	2.5	2.5
51	Low Temp Gas Cooling	17.7	0.0	0.0	0.0	0.0	0.0
52	AGR or WSA2	14.0	269.2	120.8	0.0	150.8	78.9
53	Claus or DSRP	8.9	0.0	0.0	93.6	0.0	0.0
54	Tail Gas Treat. or Oxidation	5.3	0.0	0.0	0.0	0.0	0.0
55	Fuel Gas Moisturization	14.3	0.0	0.0	0.0	0.0	0.0
56	Process Steam	0.0	0.0	0.0	0.0	0.0	0.0
61	107F Comb Turb Gen/Strm T-6	208.2	219.6	222.4	214.0	226.4	227.8
63	Steam Generation - HRSG	51.1	48.7	49.3	47.5	50.2	50.5
64	Condensate & BFW	34.6	26.9	26.1	27.4	26.0	25.6
71	General Make-Up Water	8.3	8.3	8.1	8.1	8.0	7.9
72	Demineralized Water	11.6	5.6	5.6	5.5	6.1	6.1
73	Circulating Water	15.9	15.9	15.3	15.4	15.3	15.0
74	Drains & Blowdown	0.2	0.2	0.2	0.2	0.2	0.2
75	General Waste Water Treating	11.9	12.1	12.2	11.8	12.4	12.5
76	Process Waste Water Treat.	16.9	7.9	8.0	7.7	0.0	0.0
77	Fire Water	5.3	5.3	5.4	5.2	5.5	5.5
	ELECTRICAL	75.2	78.1	77.0	74.2	78.4	78.9
	SITE WORK & BUILDINGS	39.9	40.4	40.9	39.4	41.7	41.9
	BALANCE OF PLANT	29.7	30.0	30.4	29.3	30.9	31.1
TOTAL DIRECT FIELD COSTS		902	1,183	1,044	989	1,064	997
INDIRECT FIELD COSTS		199	257	227	215	231	217
TOTAL FIELD COSTS		1,100	1,440	1,271	1,203	1,295	1,214
TOTAL OFFICE COSTS		194	213	188	178	192	180
SALES TAX (6.0%)		38	60	53	50	54	50
CONTINGENCY (12.0%)		162	206	181	172	185	173
PLANT FACILITIES INVESTMENT (\$/kW)		1,494	1,919	1,693	1,603	1,726	1,617

Table 4-10. Plant Investment Summary for Cases 5 - 9
Page 2 of 2

(\$/kW, mid-90\$)								
UNIT	DESCRIPTION	6C	7C	7C@	7D	7D@	8	9
21	Fuel Oil Supply	9.1	7.6	7.6	7.6	7.6	9.2	8.5
22	Natural Gas Supply	0.1	0.1	0.1	0.1	0.1	0.1	0.1
23	Coal Supply	29.4	26.5	26.5	26.2	26.2	28.8	29.2
24	Dolomite Supply	0.0	0.0	0.0	0.0	0.0	14.6	14.8
25	Misc. Material Handling	0.4	0.5	0.4	0.5	0.4	0.4	0.3
30	Air Compression	0.0	174.6	149.5	173.0	148.2	0.0	163.6
31	Oxygen Plant	104.4	0.0	0.0	0.0	0.0	108.2	0.0
41	Coal Grinding & Slurry Prep	13.2	11.8	11.8	11.7	11.7	14.4	15.4
42	Gasif & Desulfurization	225.8	511.0	422.3	494.2	400.8	270.5	313.7
43	Slag Handling	16.5	25.1	14.4	24.9	14.2	11.2	13.3
44	Syngas Scrubbing	0.0	0.0	0.0	0.0	0.0	0.0	0.0
45	Black Water Handling	2.8	4.2	2.4	4.1	2.4	1.7	2.0
46	Fines Filtration	4.8	7.3	4.2	7.2	4.1	3.2	3.8
47	Auxiliary Boiler	2.5	2.1	2.1	2.1	2.1	2.5	2.3
51	Low Temp Gas Cooling	0.0	0.0	0.0	0.0	0.0	0.0	0.0
52	AGR or WSA2	0.0	0.0	0.0	0.0	0.0	0.0	0.0
53	Claus or DSRP	59.3	176.1	144.6	174.5	143.3	0.0	0.0
54	Tail Gas Treat. or Oxidation	0.0	0.0	0.0	0.0	0.0	40.2	46.6
55	Fuel Gas Moisturization	0.0	0.0	0.0	0.0	0.0	0.0	0.0
56	Process Steam	0.0	0.1	0.1	0.1	0.1	0.0	0.0
61	107F Comb Turb Gen/Stm T-6	223.5	186.4	186.4	184.8	184.8	225.9	207.7
63	Steam Generation - HRSG	49.6	42.3	42.3	41.9	41.9	51.2	49.3
64	Condensate & BFW	26.3	28.5	28.5	28.2	28.2	24.6	27.8
71	General Make-Up Water	7.9	8.7	8.7	8.7	8.7	7.8	8.0
72	Demineralized Water	6.0	6.1	6.1	6.0	6.0	1.2	18.7
73	Circulating Water	15.1	27.7	19.8	27.4	19.6	14.9	15.2
74	Drains & Blowdown	0.2	0.3	0.2	0.3	0.2	0.2	0.2
75	General Waste Water Treating	12.3	10.2	10.2	10.1	10.1	12.4	11.4
76	Process Waste Water Treat.	0.0	7.3	7.3	7.3	7.3	0.0	0.0
77	Fire Water	5.4	7.5	5.4	7.4	5.3	5.5	5.0
	ELECTRICAL	77.4	107.4	76.8	106.4	76.1	78.3	72.0
	SITE WORK & BUILDINGS	41.1	57.0	40.8	59.5	40.4	41.6	38.2
	BALANCE OF PLANT	30.5	42.4	30.3	42.0	30.0	30.9	28.4
	TOTAL DIRECT FIELD COSTS	964	1,479	1,248	1,453	1,220	999	1,096
	INDIRECT FIELD COSTS	209	320	270	315	264	217	238
	TOTAL FIELD COSTS	1,173	1,795	1,515	1,765	1,480	1,217	1,334
	TOTAL OFFICE COSTS	174	266	224	261	219	180	197
	SALES TAX (6.0%)	49	74	63	73	61	50	55
	CONTINGENCY (12.0%)	167	256	216	252	211	174	190
	PLANT FACILITIES INVESTMENT (\$/kW)	1,563	2,392	2,018	2,351	1,972	1,621	1,776

Table 4-11. O&M Costs for Cases 1 - 4

COAL:	327417 LB/HR (DRY)	286217	280978	431479	491589
OXIDANT	9536.9 MPH	8782	8621.1	11861.8	75034.0
SULFUR:	88.7 LT/D	64.3	0.0	0.0	0.0
SLAG:	689 T/D (DRY)	264.0	259.9	741.4	896.1

CASE	CASE 1	CASE 2	CASE 3	CASE 4
Rating Temperature (F)	88	88	88	88
Net Plant Output (MW)	451.7	443.9	568.0	463.5
Net Plant Output (kW)	451700	443894	567968	463474
Net Plant Heat Rate (Btu/kWh, HHV)	8929.29	8920.02	9959.51	13905.2
Fuel Consumption (MMBtu/hr, HHV)	4033	3960	5657	6445
Plant Capacity Factor (%)	80	80	80	80
Fuel Efficiency (%)				
Fixed Operating Costs (\$/week)				
Overhead Staffing	22356	22356	29461	33566
Operations Staffing	48430	48430	63822	72713
Maintenance Staffing	39270	39270	51751	58961
Oxygen Plant Staffing	6940	6940	0	2730
Total Fixed Costs (\$/week)	116996	116996	145035	167970
Variable Operating Costs (mills/kWh)				
Contract Maintenance Labor	1.655	1.490	0.360	0.981
Maintenance Materials	1.274	1.146	0.277	0.755
Start-Up Costs (1)	1.500	1.500	1.500	1.500
Catalysts and Chemicals	0.871	0.746	0.776	1.079
Slag Disposal (2)	0.731	0.732	1.632	2.417
Spent Dolomite Cost (6)	0.000	0.838	0.000	0.000
WESCO filters	0.000	0.062	0.036	0.118
Total Variable Operating Costs (mills/kWh)	6.031	6.513	4.582	6.850
Cost of Coal (3)	11.010	10.998	12.280	17.145
Sulfur Credit (4)	0.356	0.000	0.000	0.000
Cost of Oxygen (5)	0.000	0.000	7.936	0.000
Cost of Dolomite (16 \$/ton)	0.000	1.341	0.000	0.000
Cost of Fine-ox (35 \$/ton)	0.000	0.000	0.926	1.034
Total Variable Costs (mills/kWh)	17.396	18.851	25.724	25.030

(1) Estimated at 1.5 mills/kWh
(2) 15 \$/ton (wet, 50% water)
(3) Delivered cost at 1.233 \$/MMBTU (HHV)
(4) 60 \$/long ton
(5) 25 \$/ton
(6) 15 \$/ton - non-hazardous disposal for W.V. site

50 ZT cycles

125

Table 4-13. O&M Costs for Cases 5 - 9 Assuming a ZnTi Life of 200 Cycles

200 ZT cycles												
CASE:	DOE1	DOE5a	DOE5b	DOE5c	DOE6a	DOE6b	DOE6c	DOE7c	DOE7c@	DOE7d	DOE7d@	DOE8
(1) Re-start Costs, mills/kwh:												
(2) Slag Disposal Costs (wet, 50% water), \$/T	1.59											
(3) Spent Dolomite Disposal Costs, \$/T	15.90											
(non-hazardous disposal for W.V. site)												
(4) Delivered Coal Cost, \$/ton	31.80											
Distillate Fuel Oil, \$/MMBtu (HHV)	4.03											
(5) Sulfur Credit, \$/LT	63.00											
(6) Sulfuric Acid (98 wt%) Credit, \$/LT	78.12											
(7) Dolomite Cost, \$/T	16.06											
(8) Fine-Ox Cost, \$/T	37.10											
(9) Natural Gas Cost, \$/MMBtu (HHV)	2.92											
lb/h COAL (dry):	288217	258940	258940	262861	277005	277005	279006	324536	324536	324536	324536	262170
mol/h TOTAL OXIDANT:	8782	7945	7945	8065	7659	7659	7715	61470	61470	61470	61470	8044
LongT/D SULFUR:	64.3	0	0	59.1	0	0	28.6	72.9	72.9	72.9	72.9	0.0
LongT/D SULFURIC ACID:	0	178.0	178.0	0	86.7	86.7	0	0	0	0	0	0.0
T/D SLAG (dry):	264.0	239.5	239.5	243.1	471.5	471.5	474.9	314.2	314.2	314.2	314.2	242.5
lb/h DOLOMITE (dry):	0	0	0	0	0	0	0	0	0	0	0	69433
MMBtu/hr NAT GAS (HHV):	0.0	307.0	122.9	286.4	150.9	60.4	141.0	279.7	279.7	279.7	279.7	9.4
Net Plant Output (kWh/h)	451743	448448	440944	458156	433105	430415	438715	525969	525969	530635	530635	434112
MMBtu/hr COAL (HHV):	4033	3879	3741	3910	3745	3677	3764	4783	4783	4783	4783	3704
Plant Capacity Factor (%)	80	80	80	80	80	80	80	80	80	80	80	80
Fuel Efficiency (%)	38.21	39.27	40.21	39.89	39.48	39.94	39.77	37.52	37.52	37.85	37.85	39.99
Total Fixed Operating Costs (\$/week)	108754	98389	98389	99879	104605	104605	105361	154177	154177	269810	154177	93412
Variable Operating Costs (mills/kWh)												
Contract Maint. Labor	1.756	2.844	2.345	2.051	2.414	2.172	1.988	3.409	2.845	3.336	2.757	2.125
Maintenance Materials	1.351	2.188	1.804	1.578	1.857	1.971	1.529	2.623	2.188	2.567	2.121	1.635
Re-Start Costs (1)	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590
Catalysts and Chemicals	0.923	0.462	0.467	0.457	0.502	0.505	0.499	0.854	0.854	0.847	0.847	0.481
ZT/WSA/DSRP Catalysts	0.000	7.424	7.430	7.258	3.769	3.749	3.733	7.821	7.824	7.753	7.755	0.630
Slag Disposal (2)	0.774	0.711	0.720	0.703	1.442	1.451	1.434	0.792	0.792	0.785	0.785	0.740
Spent Dolomite Cost (3)	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1.272
WESCO filters	0.000	0.098	0.098	0.095	0.101	0.101	0.099	0.193	0.221	0.192	0.219	0.151
Cost of Dolomite (7)	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1.358
Cost of Fine-ox (8)	0.000	0.000	0.000	0.000	0.826	0.832	0.822	0.000	0.000	0.000	0.000	0.000
Total Variable Operating Costs (mills/kWh)	6.395	15.317	14.454	13.732	12.501	12.071	11.694	17.283	16.314	17.069	16.074	9.979
Cost of Coal (4)	10.074	9.222	9.222	9.122	10.169	10.169	10.112	9.811	9.811	9.724	9.724	9.602
Sulfur Credit (5)	-0.377	0.000	0.000	-0.342	0.000	0.000	-0.172	-0.367	-0.367	-0.364	-0.364	0.000
Sulfuric Acid Credit (6)	0.000	-1.298	-1.298	0.000	-0.852	-0.852	0.000	0.000	0.000	0.000	0.000	0.000
Cost of Natural Gas (9)	0.000	2.004	0.812	1.822	1.016	0.409	0.937	1.550	1.550	1.537	1.537	0.063
Dispatch Costs (Tot. Var. Costs, mills/kWh)	16.092	25.245	23.191	24.335	23.034	21.998	22.571	28.276	27.307	27.965	26.971	19.844
												22.666

Table 4-14. O&M Costs for Cases 5 - 9 Assuming a ZnTI Life of 1000 Cycles

1000 ZT cycles																
		1.59														
(1) Re-start Costs, mills/kwh:		15.90														
(2) Slag Disposal Costs (wet, 50% water), \$/T		15.90														
(3) Spent Dolomite Disposal Costs, \$/T		31.80														
(non-hazardous disposal for W.V. site)		4.03														
(4) Delivered Coal Cost, \$/ton		63.60														
Distillate Fuel Oil, \$/MMBtu (HHV)		78.12														
(5) Sulfur Credit, \$/LT		16.96														
(6) Sulfuric Acid (98 wt%) Credit, \$/LT		37.10														
(7) Dolomite Cost, \$/T		2.92														
(8) Fine-Ox Cost, \$/T																
(9) Natural Gas Cost, \$/MMBtu (HHV)																
CASE:	DOE1	DOE5a	DOE5b	DOE5c	DOE5d	DOE6a	DOE6b	DOE6c	DOE7c	DOE7c@	DOE7d	DOE7d@	DOE8	DOE9		
lb/h COAL (dry):	286217	256940	256940	282881	277005	277005	277005	279006	324536	324536	324536	324536	262170	318693		
mol/h TOTAL OXIDANT:	8782	7845	7845	8065	7659	7659	7659	7715	61470	61470	61470	61470	8044	60363		
LongT/D SULFUR:	64.3	0	0	59.1	0	0	0	28.6	72.9	72.9	72.9	72.9	0.0	0.0		
LongT/D SULFURIC ACID:	284.0	178.0	178.0	243.1	178.0	178.0	178.0	178.0	314.2	314.2	314.2	314.2	242.5	308.6		
T/D SLAG (dry):	0	0	0	0	150.9	88	88	141.0	0	0	0	0	69433	84404		
lb/h DOLOMITE (dry):	0	0	0	0	0	0	0	0	279.7	279.7	279.7	279.7	9.4	6.9		
MMBtu/hr NAT GAS (HHV):	0.0	307.0	122.9	286.4	88	88	88	88	525969	525969	530635	530635	434112	472144		
Net Plant Output (kWh/h)	451743	446448	440944	458156	433105	433105	430415	438715	525969	525969	4783	4783	3704	4489		
MMBtu/hr COAL (HHV):	4033	3670	3741	3919	3745	3745	3677	3764	4783	4783	80	80	80	80		
Plant Capacity Factor (%)	80	80	80	80	80	80	80	80	80	80	80	80	80	80		
Fuel Efficiency (%)	38.21	39.27	40.21	39.89	39.46	39.46	39.94	39.77	37.52	37.52	37.85	37.85	39.99	36.05		
Total Fixed Operating Costs (\$/week)	108754	98389	98389	99879	104605	104605	104605	105361	269810	269810	269810	269810	93412	113551		
Variable Operating Costs (mills/kWh)	1.756	2.844	2.345	2.051	2.414	2.414	2.172	1.988	3.409	2.845	3.336	2.757	2.125	2.383		
Contract Maint. Labor	1.351	2.188	1.804	1.578	1.857	1.857	1.671	1.529	2.623	2.188	2.567	2.121	1.635	1.833		
Maintenance Materials	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590	1.590		
Re-Start Costs (1)	0.923	0.462	0.467	0.457	0.502	0.502	0.505	0.499	0.854	0.854	0.847	0.847	0.481	0.480		
Catalysts and Chemicals	0.000	1.598	1.532	1.581	0.811	0.811	0.773	0.813	1.686	1.686	1.671	1.672	0.126	0.290		
ZT/WSA2/DSRP Catalysts	0.774	0.711	0.720	0.703	1.442	1.442	1.451	1.434	0.792	0.792	0.785	0.785	0.740	0.866		
Slag Disposal (2)	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1.272	1.421		
Spent Dolomite Cost (3)	0.000	0.098	0.098	0.095	0.101	0.101	0.101	0.099	0.193	0.221	0.192	0.219	0.151	0.369		
WESCO filters	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1.356	1.516		
Cost of Dolomite (7)	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000		
Cost of Fine-ox (8)	0.000	0.000	0.000	0.000	0.828	0.828	0.832	0.822	0.000	0.000	0.000	0.000	0.000	0.000		
Total Variable Operating Costs (mills/kWh)	6.395	9.491	8.555	8.055	9.543	9.543	9.095	8.775	11.148	10.176	10.987	9.991	9.475	10.729		
Cost of Coal (4)	10.074	9.222	9.222	9.122	10.169	10.169	10.169	10.112	9.811	9.811	9.724	9.724	9.602	10.732		
Sulfur Credit (5)	-0.377	0.000	0.000	-0.342	0.000	0.000	0.000	-0.172	-0.367	-0.367	-0.364	-0.364	0.000	0.000		
Sulfuric Acid Credit (6)	0.000	-1.298	-1.298	0.000	-0.852	-0.852	-0.852	0.000	0.000	0.000	0.000	0.000	0.000	0.000		
Cost of Natural Gas (9)	0.000	2.004	0.812	1.822	1.016	1.016	0.409	0.937	1.550	1.550	1.537	1.537	0.063	0.043		
Dispatch Costs (Tot.Var.Costs, mills/kWh)	16.092	19.419	17.292	18.658	20.077	20.077	19.022	19.651	22.141	21.170	21.884	20.887	19.140	21.504		

higher percentage of energy to the less efficient Rankine cycle than occurs in the O₂-blown cases.

The air-blown cases require 80 to 85 percent more oxygen than the O₂-blown cases to produce an equivalent volume of syngas (H₂ plus CO). Some of this increase, at least, is associated with the greater amount of carbon combusted to CO₂ in order to provide the energy needed to preheat all of the nitrogen in the air. Also, the heat loss in the system is greater because of the larger and more numerous gasifiers required to handle the larger volumes of gas.

In the air-blown IGCC cases employing radiant syngas coolers and ZnTi only (all Case 7 subcases), only 47 percent of the power is produced by the gas turbine. However, in the O₂-blown equivalent (Case 5c), 53 to 56 percent of the power is produced by the gas turbine. In the air-blown IGCC case using dolomite and ZnTi, where recycled quench gas replaces radiant syngas coolers in the high temperature heat recovery section, 58 percent of the power is produced in the gas turbine. But in the O₂-blown equivalent (case 8), the gas turbine produces 62 percent of the power.

Two oxygen-blown cases have heat rates higher than the base case. Case 2 (90 percent sulfur removal with dolomite) has a much less efficient spent dolomite oxidizer system compared with Case 8 (90 percent sulfur removal with dolomite and 8 percent with ZnTi). The compressor which takes air extracted from the combustion turbine and boosts its pressure upstream of the dolomite oxidizer uses no interstage cooling. Instead, the heat of compression is used to preheat this air before it enters the oxidizer. The resulting increased power consumption of this compressor contributes significantly to the higher heat rate.

The higher heat rate of Case 3 is probably attributable to the non-integrated approach chosen in retrofitting an existing pulverized coal-fired steam boiler. The Rankine cycle alone is not as efficient as the combined cycle.

Method of Desulfurization and Sulfur Recovery

The effect of desulfurization method on heat rate is considered together with the method of sulfur recovery because, in some cases, the choice of desulfurization method determines the method of sulfur recovery. The iron oxide only (cases 3 and 4) and dolomite only (case 2) configurations cannot be strictly compared with all of the other cases because their desulfurization performance is below 98 percent. Also, cases 3 and 4 were not IGCC cases.

In the O₂-blown IGCC cases the power consumed in the hot gas cleanup units is greater than the power consumed in the

corresponding cold gas cleanup units in the base case. However, this increased power consumption is more than offset by the more efficient operation of the gas turbine running on hot gas. Approximately 10 percent less fuel gas is required at the higher temperatures, resulting in correspondingly smaller oxygen plants, coal grinding units, gasifiers and radiant syngas coolers. The result is that all of the O_2 -blown IGCC cases have lower heat rates (i.e. are more efficient) than the cold gas cleanup base case. The air-blown IGCC cases all have higher heat rates than the base case. This was discussed in the preceding section.

The cases using in-situ iron oxide in combination with ZnTi (6a, 6b and 6c) save energy in the sulfur recovery units when compared with those cases using only ZnTi (5a, 5b and 5c). However, this savings is offset somewhat by the power consumed in preparing iron oxide and by the less efficient gasification operation. The gasifier must be operated at a lower temperature to ensure adequate sulfur capture by the iron oxide; and this results in lower carbon conversion and lower syngas temperature at the inlet to the radiant syngas cooler.

The heat rates of the plants recovering sulfur as sulfuric acid depend greatly on the concentration of O_2 in the zinc titanate regeneration gas. Cases 5b and 6b both use higher concentrations of O_2 in the regeneration gas compared with cases 5a and 6a. As a direct result, the size of the sulfuric acid unit, and the attendant power consumption, is decreased accordingly.

As shown in Table 4-8, the direct sulfur recovery subcases, 5c and 6c, consume less power in the sulfur recovery unit. However, a slip-stream of syngas is required for the Claus reaction; and this hurts the heat rate. These direct sulfur recovery cases use O_2 concentrations intermediate between those used in the sulfuric acid subcases, so it is difficult to compare them directly. However, by inference from the sulfuric acid cases, it can be concluded that increasing the O_2 concentration in the ZnTi regeneration gas will also help the heat rate of the direct sulfur recovery units. In addition, these units use substantial amounts of natural gas in fired heaters, which is not a good design choice. Elimination of these heaters by better heat integration would also decrease the heat rates.

In case 8, where all sulfur eventually is recovered as $CaSO_4$, the major power consumers are the compressors which supply air to the spent dolomite oxidizer and recycle syngas for quenching and dolomite slurry atomization. Increasing the O_2 concentration in the ZnTi regeneration gas would have little effect in reducing the heat rate because of the lesser amount of ZnTi used in this case.

Fuel Gas End Use

Cases 3 and 4, the two pulverized coal-fired steam boiler retrofits have the highest heat rates of any of the cases, regardless of the oxidant used. The attempt to use the fuel gas in the Rankine cycle alone, coupled with no attempt at system integration, clearly results in an inefficient operation.

4.4.2 Plant Investment Cost

With the exception of cases 2 through 4, which do not remove as much sulfur as the other cases, none of the hot gas cleanup cases are less expensive than the cold gas cleanup base case. The reason for this can be seen by referring to Table 4-10. The Case 1 cold gas cleanup units (44 - syngas scrubbing, 51 - low temperature gas cooling, 52 - acid gas removal, 53 - Claus unit, 54 - tail gas treating, 55 - fuel gas moisturization) cost 70.5 \$/kW. In case 6c, the least expensive hot gas cleanup case, the direct sulfur recovery unit alone costs 59.3 \$/kW. The high temperature sulfur removal steps cost on the order of 80 \$/kW, in addition. Clearly, the hot gas cleanup configurations studied in these cases are substantially more expensive than the cold gas cleanup used in the base case.

4.4.3 Operating and Maintenance Costs

Again, as in the case of total plant investment cost, none of the hot gas cleanup cases had operating and maintenance costs lower than the cold gas cleanup base case. The main reason for this is the purchase, replacement and/or disposal costs of the catalysts and sorbents used in the high temperature desulfurization and sulfur recovery units of the hot gas cleanup cases. See tables 4-11 through 4-14.

One trend which is clearly shown in the above tables is that the assumed number of sulfidation and regeneration cycles which can be obtained from a single batch of sorbent before replacement has a significant impact on plant operating and maintenance costs in the cases where zinc titanate is the sole sulfur sorbent. In those cases a highly durable sorbent would be required for economical operation. However, in combination with another sorbent such as dolomite, the sensitivity to zinc titanate replacement cost is minimized.

4.4.4 Levelized Cost of Electricity

For all of the IGCC hot gas cleanup cases, the plant investment cost and operating and maintenance costs are higher than the base case; and this is directly reflected in the higher levelized cost of electricity for each of these cases.

In the two boiler retrofit cases, the levelized cost of electricity is lower because of the extremely low plant cost. However, these cases are not directly comparable.

5. CONCLUSIONS AND PLANS FOR FUTURE WORK

5.1 In-Situ Desulfurization

The following conclusions were reached in the Phase II in-situ desulfurization work:

- * The in-situ addition of iron oxide as a desulfurization sorbent with oxygen-blown gasification can reducing the H_2S level in the syngas by 50-60 percent, depending on the gasifier temperature and iron oxide dosage.
- * No improvement in desulfurization in oxygen-blown gasification was obtained with iron oxide at longer than normal residence times.
- * The slag produced in the increased residence time in-situ iron oxide desulfurization run had leachable sulfide levels that would require further processing of the slag before disposal in a landfill.
- * The in-situ addition of iron oxide as a desulfurization sorbent with air-blown gasification is capable of reducing the H_2S level in the syngas by only 27 percent, and is probably not worth further development.
- * Air-blown gasification requires approximately 20 percent more oxygen than oxygen gasification for the same carbon conversion.
- * Air-blown gasification also requires air preheat in the 800 to 1000°F range to minimize over-conversion at the temperatures required to efficiently remove slag from the gasifier.

5.2 External Desulfurization

5.2.1 Calcium Based Sorbents

- * Injection of dolomite slurry into the hot syngas from air-blown gasification can remove at least 70 percent of the sulfur in the syngas.
- * Dolomite can remove at least 82 percent of the sulfur in oxygen-blown syngas when operated in a fixed bed.
- * The current PDU would require the addition of a dry feed system for calcium sorbents to determine fully the

desulfurization levels that can be achieved with these sorbents.

5.2.2 Mixed Metal Oxide Sorbents

- * In bench scale test at RTI, zinc titanate sorbent regeneration removed residual chloride, thus much of the chloride may appear in the regeneration off-gas.
- * In bench scale test at RTI, significant zinc loss occurred from the L-3196 zinc titanate sorbent over 10 cycles at 700°C when nitrogen diluted oxygen was used for regeneration. The Zn/Ti ratio dropped from about 1.4 to 1.2. The zinc loss was about 30 percent greater over 10 cycles when the regeneration gas contained 50 percent steam than when it contained no steam.
- * In bench scale test at RTI, the L-3196 zinc titanate sorbent became significantly more reactive in later cycles, presumably caused by opening of porous structure due to zinc evaporation. This resulted in greater effective utilization over 10 cycles in spite of zinc loss.
- * Bench scale tests at RTI showed that the 1.5 Zn/Ti ratio zinc titanate has a significantly higher sulfur loading capacity than the 0.8 Zn/Ti ratio zinc titanate.
- * Further testing should be done to define the zinc loss from 1.5 Zn/Ti zinc titanate.
- * Zinc ferrite and Zinc titanate sorbents are all capable of reducing the H₂S level in syngas to below 50 ppm when used in a fixed bed at 1000 to 1200°F in both air-blown and oxygen-blown syngas.
- * The zinc ferrite (L-2465) sorbent is not overreduced in air-blown gasification syngas and therefore retains its crush strength, unlike its performance in oxygen-blown gasification syngas.
- * Both zinc titanates (L-3140 & L-3014) show no signs of over reduction when used in air-blown or oxygen-blown gasification syngas.
- * The 1.5 Zn/Ti zinc titanate is the preferred sorbent for use with Texaco syngas due to its superior performance in oxygen-blown syngas and its higher zinc content compared to the 0.8 Zn/Ti zinc titanate.
- * Multi-cycle testing of the 1.5 Zn/Ti titanate in true process gases is needed to determine it's cycle life.

5.3 Advanced Instrumentation

- * Air-blown gasification of Pittsburgh No. 8 coal in a Texaco gasifier, configured like the PDU used for these experiments, produces syngas containing low wppm levels of alkali. However, this can be reduced to low wppb levels by filtration using a Westinghouse Ceramic Crossflow Filter (CXFF). Assuming that the reliability of the CXFF can be improved, an air-blown Texaco-based IGCC employing hot gas cleanup would not be expected to suffer significant alkali-induced corrosion.
- * Data obtained when the ceramic cross flow filter was performing well suggest that the alkali material remaining in the filtered syngas was either in the vapor phase or in the form of particulate smaller than 10 microns.
- * The Fiber Optic Alkali Monitor (FOAM) is sensitive to alkali over a very wide range of concentrations. Data covering about six orders of magnitude were obtained.
- * The FOAM also is very sensitive to the flowrate of sample gas to the burner. To ensure consistent measurements, it is important to maintain a constant flow at the same rate that was used during calibration.
- * Because the CXFF operates at a temperature at which most of the alkali are in the particulate phase, the FOAM can be used to monitor the effectiveness of the filter and to function as an early warning system for filter failure.
- * The Na/K ratio in the syngas was higher than that in the gasifier feed.

5.4 Economic Studies

The configurations studied were a first attempt at integrating hot gas cleanup with the Texaco process. Consequently, the calculated efficiencies and costs do not represent what might be obtained in a well optimized plant. While further work could be done to improve the cases, some general observations are worthy of comment.

- * The cases with the greatest bearing on the future integrated demonstration PDU design are cases 5 through 9, the ones removing a comparable amount of sulfur (98 percent) to the base case. This is because it is unlikely that such a demonstration PDU would be built for a configuration removing less sulfur than the ambient temperature base case.
- * The integration of hot gas cleanup with the Texaco process produced significant gains in overall

efficiency. However, the estimated costs for these non-optimized cases were higher than expected.

- * The energy requirements for the air-blown plants were larger than expected. Also, the increased gas volumes involved in air-blown operation required larger equipment and additional gasification trains, which had a significant impact on the costs involved.
- * Increasing the partial pressure of oxygen in the gas used to regenerate sulfided zinc titanate dramatically improved both system efficiency and cost.
- * The assumed number of sulfidation and regeneration cycles which could be obtained from a single batch of sorbent before replacement had a significant impact on plant operating and maintenance costs in the cases where zinc titanate was the sole sulfur sorbent. In those cases a highly durable sorbent would be required for economical operation. However, in combination with another sorbent such as dolomite, the sensitivity to zinc titanate replacement cost was minimized.
- * Based on what was learned during the studies, it is believed that some process configuration changes can be made which will lower the capital and operating costs of these plants without significantly impacting the large gains in efficiency. The areas showing the most promise for cost reduction are high temperature heat recovery, desulfurization reactor design and the sulfur recovery processes.

5.5 Future Plans

5.5.1 Bench Scale testing

The previous bench scale studies showed a need for a better understanding of the effects of temperature and regeneration gas composition on sorbent zinc loss. With this in mind, one additional bench scale study using the 1.5 Zn/Ti zinc titanate is planned at RTI. This study will evaluate the effects of temperature and regeneration gas composition on sorbent zinc loss.

5.5.2 PDU Testing

One additional approach at in-situ desulfurization is planned using a mixture of iron oxide and limestone. The iron oxide should reduce the slag viscosity sufficiently to allow the slag

to flow out of the gasifier even with the expected level of calcium silicates in the slag.

External desulfurization will concentrate on the 1.5 Zn/Ti zinc titanate. To determine the optimum sulfidation cycle space velocity for the 1.5 Zn/Ti zinc titanate sorbent, the sulfidation only beds will be run one more time with L-3140 loaded in all three beds. The beds will be operated at space velocities of 2000, 4000, and 8000 hr⁻¹ respectively.

The regenerable fixed bed at MRL is under construction and will be used to test the 1.5 Zn/Ti zinc titanate over 10 to 20 cycles during three PDU runs. The results of these tests will give some indication of the durability of zinc titanate in syngas produced in a PDU rather than simulated in a laboratory.

5.5.3 Process Economic Studies

Based on what was learned from the process optimization studies, it is clear that additional studies are needed before the integrated demonstration PDU can be designed. The aim of these studies will be to optimize the most promising configurations with respect to cost without significantly impacting the improved efficiencies.

A Continuation Proposal has been submitted to DOE/METC proposing these additional economics studies as well as a modified PDU test plan. The results of the studies will be used to guide the future direction of this program.

None of the hot gas cleanup configurations evaluated as part of the Phase 2 process economics studies were competitive with conventional technology on a cost basis. However, these studies were first attempts and probably do not represent optimized configurations. Nevertheless, a hot gas cleanup case that is cost competitive with conventional technology needs to be developed before there exists a strong incentive for pursuing further development of hot gas cleanup integrated with the Texaco gasifier. Therefore, the design and demonstration of an integrated PDU will be postponed until such a case has been developed. To develop such a case, additional economic studies concentrated on cost reduction are needed. Further, once an economical conceptual hot gas cleanup case is developed, additional experimental work may be needed before an integrated unit can be built.

The process areas showing the most promise for cost reduction are high temperature heat recovery, desulfurization reactor design, sulfur recovery processes, and turbine design. Significant cost reductions will result from the substitution of water partial quench for radiant syngas heat exchangers. The use of

desulfurization reactor designs other than fixed beds may also produce savings, particularly if the alternate designs allow the sorbents to be regenerated with oxygen concentrations higher than those used in the previous studies. Higher oxygen concentrations allow much smaller sulfur recovery plants to be used. In addition, it should be possible to optimize the design of the sulfur recovery plants. Alternative desulfurization methods such as warm gas desulfurization could also improve the cost of desulfurization. The use of a humid air turbine cycle could improve the cost and efficiency of any of the above cases.

5.5.4 Advanced Instrument Testing

The DOE Advanced Instruments (FOFT, CSAS, and ICPS) will be tested during the additional Phase II PDU tests as the instruments become available. The testing of the FOAM has been completed.

REFERENCES

1. Robin, A. M., et. al., 1989, "Integration and Testing of Hot Desulfurization and Entrained Flow Gasification for Power Generation Systems, Phase I Preliminary Desulfurization Research", Texaco Inc., DOE/MC/23277-2731 (DE89011675)
2. Hass, W. J., R. Markuszewski and D. E. Eckels, March 1990, "Fiber Optic Alkali Meter Sampling", in The Proceedings of the Seventh Annual Coal-Fueled Heat Engines and Gas Stream Cleanup Systems Contractors Review Meeting, pp 391-402.

APPENDICES

- Appendix A - Raw Data: PDU Tests
 - Raw Data Analysis [Table A-1 to A-7]
- Appendix B - Raw Data: Mixed Metal Oxide Sorbents
 - Sorbent Ash Analysis [Table B-1 to B-9]
 - Sorbent Specification Sheets [Figure B-1 to B-2]
- Appendix C - Raw Data: Fiber Optic Alkali Monitor
 - Raw Data by 2-hour Segments [Figures C-1 to C-20]
 - Selected Data Showing Large Amplitude Variations [Figures C-21 to C-23]
- Appendix D - Process Economics Data PFDs [Figures D-1 to D-18]
- Appendix E - Unit Level Equipment Cost Data [Tables D-1 to D-19]
- Appendix F - High Temperature Cyclone Details [Figure F-1]

Appendix A

Raw Data: PDU Testing

Table A-1 shows the raw material balance for each test period.

Tables A-2 and A-3 show the analysis of streams that are not shown in table A-1.

Tables A-4 through A-8 show the ash analysis for all solids streams broken down by run and test period..

Table A-1. Raw Material Balances
Page 1 of 3

Run	1	1	1	1	1	1	1	2	2
Test period	A	B	C	D	E	F	G	A	B
Gasifier T, deg F	T0	T0	T0	T0	T0-100	T0-200	T0-200	T+140	T0
Air Temp, deg F	N/A	N/A	N/A	N/A	N/A	N/A	N/A	900	940
Sorbent Dossage lb/lb S	0	0	2.5	2.5	2.5	2.5	3.5	0	0
Slurry Feed rate, lbs/hr	1545	2200	2207	1553	1550	1572	1547	1002	1111
Dry Fuel (wt%)									
C	69.51	69.99	62.85	62.85	63.15	63.37	62.98	77.77	77.32
H	4.97	5.09	4.53	4.53	4.58	4.58	4.35	5.28	5.19
N	1.44	1.44	1.34	1.34	1.43	1.44	1.43	1.39	1.4
S	4.7	4.67	4.18	4.18	4.25	4.15	4.05	2.19	2.2
O	7.41	6.82	6.07	6.07	5.82	5.38	6.12	5.82	6.44
Ash	11.96	11.99	21.03	21.03	20.77	21.08	21.07	7.55	7.45
Oxidant Feed rate, lbs/hr	999	1312	1327	929	873	877	857	3583	3845
Mole % species									
N2	5.20	0.96	1.87	0.45	1.52	0.38	1.46	78.12	78.12
O2	94.56	98.80	97.88	99.30	98.23	99.37	98.30	20.95	20.95
Ar	0.24	0.25	0.25	0.25	0.25	0.25	0.25	0.93	0.93
CO2	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.03	0.03
Total Gas Produced Rate, lbs/hr	1956	2713	2571	1832	1792	1761	1745	4094	4398
wt% of component in									
C	98.4	96.9	101.7	102.0	100.3	99.0	98.5	96.9	93.2
H	58.0	64.7	56.7	61.8	60.4	59.5	59.9	50.3	47.7
N	99.2	103.3	102.8	100.1	97.0	104.7	100.4	96.8	98.5
S	68.0	76.3	46.2	52.4	43.6	28.3	42.9	98.7	104.3
O	71.6	74.4	71.4	73.3	74.0	72.2	72.7	74.8	69.8
Ar	2.8	126.0	57.6	95.1	49.5	49.1	49.1	95.7	119.7
Ash	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Solids Produced rate, lbs/hr	123	151	252	184	177	234	196	62	44
wt% of component in									
C	1.1	0.7	0.7	0.5	1.0	0.9	0.8	2.5	2.0
H	0.3	0.1	0.1	0.1	0.2	0.2	0.2	0.2	0.1
S	7.5	5.7	38.8	40.0	37.0	49.2	44.2	3.3	2.5
Ash	95.6	83.9	75.3	79.1	77.6	102.3	86.3	100.7	63.1
Produced Water rate, lbs/hr	461	581	638	409	406	432	414	352	416
wt% of component in									
H	45.9	40.3	33.6	42.2	41.3	43.0	42.9	52.7	56.1
O	26.1	24.4	19.3	24.4	25.0	26.2	25.6	26.3	28.3
overall wt% recoveries									
C	99.6	97.6	102.4	102.5	101.3	99.8	99.3	99.4	95.2
H	104.2	105.1	90.4	104.1	101.9	102.7	103.0	103.2	103.8
N	99.2	103.3	102.8	100.1	97.0	104.7	100.4	96.8	98.5
S	75.5	82.0	85.0	92.4	80.7	77.4	87.1	102.1	106.9
O	97.7	98.8	90.8	97.7	98.9	98.4	98.3	101.0	98.1
Ar	103.9	126.0	57.6	95.1	49.5	49.1	49.1	95.7	119.7
Ash	95.6	83.9	75.3	79.1	77.6	102.3	86.3	100.7	63.1

Table A-1. Raw Material Balances
Page 2 of 3

Run	2	2	2	3	3	3	3	3
Test period	D	E	F	A	B	C	D	E
Gasifier T, deg F	T0-90	T0-50	T0+50	T0	T0-100	T0-180	T0-200	T0-240
Air Temp, deg F	960	850	850	1050	1050	1050	1050	950
Sorbent Dossage lb/lb S	0	0	0	3.5	3.5	3.5	4.5	4.5
Slurry Feed rate, lbs/hr	1154	1103	1035	1142	1165	1195	1180	1202
Dry Fuel (wt%)								
C	76.89	76.89	76.89	71.61	71.61	71.61	70.67	70.67
H	5.19	5.19	5.19	4.9	4.9	4.9	4.81	4.81
N	1.46	1.46	1.46	1.38	1.38	1.38	1.46	1.46
S	2.2	2.2	2.2	2.03	2.03	2.03	1.95	1.95
O	6.25	6.25	6.25	6.42	6.42	6.42	5.89	5.89
Ash	8.01	8.01	8.01	13.66	13.66	13.66	15.22	15.22
Oxidant Feed rate, lbs/hr	3842	3874	3829	3839	3859	3842	3852	3830
Mole % species								
N2	78.12	78.12	78.38	78.38	78.37	78.38	78.37	78.38
O2	20.95	20.95	20.70	20.70	20.70	20.70	20.70	20.70
Ar	0.93	0.93	0.92	0.92	0.92	0.92	0.92	0.92
CO2	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03
Total Gas Produced Rate, lbs/hr	4495	4483	4513	4528	4429	4499	4480	4298
wt% of component in								
C	90.8	94.6	95.1	101.5	99.2	93.7	94.9	108.0
H	53.7	47.8	48.6	50.1	52.9	52.7	49.5	42.5
N	100.4	99.3	101.4	99.1	95.2	99.2	97.8	94.5
S	101.1	106.3	116.6	88.6	78.5	74.5	76.3	91.1
O	73.0	73.7	74.2	74.7	73.6	71.6	73.8	65.0
Ar	79.1	89.8	103.9	86.5	97.2	97.8	99.9	96.3
Ash	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Solids Produced rate, lbs/hr	77	67	69	83	101	120	120	108
wt% of component in								
C	4.5	3.9	3.2	1.4	2.0	3.4	3.0	4.7
H	0.3	0.2	0.1	0.1	0.2	0.3	0.2	0.3
S	6.0	4.1	2.6	14.6	25.8	32.5	34.4	35.4
Ash	84.1	79.1	98.8	74.1	85.6	92.4	85.3	85.1
Produced Water rate, lbs/hr	374	380	357	369	372	393	382	427
wt% of component in								
H	49.1	52.5	52.5	50.1	49.7	51.0	51.0	50.8
O	25.4	26.2	25.2	25.1	25.1	26.3	25.9	26.6
overall wt% recoveries								
C	95.4	98.5	98.2	102.9	101.2	97.1	97.9	112.6
H	103.2	100.5	101.2	100.4	102.8	104.0	100.7	93.6
N	100.4	99.3	101.4	99.1	95.2	99.2	97.8	94.5
S	107.1	110.3	119.2	103.2	104.3	107.1	110.7	126.5
O	98.4	99.8	99.5	99.9	98.7	98.0	99.7	91.6
Ar	79.1	89.8	103.9	86.5	97.2	97.8	99.9	96.3
Ash	84.1	79.1	98.8	74.1	85.6	92.4	85.3	85.1

Table A-1. Raw Material Balances
Page 3 of 3

Run	4	4	5	6	6	7	8
Test period	A	B	A	0	A	A	
Gasifier T, deg F	T0+100	T0+120	T0	T0	T0+60	T0+30	T0
Air Temp, deg F	1041	1043	800	800	925	N/A	N/A
Sorbent Dosage lb/lb S	2	2	1.8		1.8		
Slurry Feed rate, lbs/hr	1192	1171	1120	1097	1076	2403	
Dry Fuel (wt%)							Balance Not Done
C	76.93	76.93	76.57	76.98	76.22	74.39	
H	5.29	5.29	5.17	5.15	5.12	5.3	
N	0.03	0.03	1.47	1.54	1.52	1.44	
S	2.23	2.23	2.43	2.45	2.42	2.55	
O	8.28	8.28	6.43	5.94	6.67	7.68	
Ash	7.24	7.24	7.93	7.94	8.05	8.63	
Oxidant Feed rate, lbs/hr	995	973	975	993	961	1731	
Mole % species							
N2	78.36	78.37	79.45	78.12	81.39	8.88	
O2	20.71	20.71	19.62	20.95	17.83	90.89	
Ar	0.92	0.92	0.93	0.93	0.80	0.23	
CO2	0.03	0.03	0.03	0.03	0.03	0.00	
Total Gas Produced Rate, lbs/hr	4774	4630	4923	4713	5262	3306	
wt% of component in							
C	93.1	91.5	92.2	99.8	97.5	98.3	
H	53.8	52.6	56.3	51.9	52.2	60.5	
N	99.6	98.7	101.8	99.7	100.4	108.7	
S	61.4	70.8	84.6	95.7	73.5	73.5	
O	73.8	72.4	73.3	74.3	75.7	71.1	
Ar	80.0	100.2	107.4	104.2	110.9	142.5	
Ash	0.0	0.0	0.0	0.0	0.0	0.0	
Total Solids Produced rate, lbs/hr	85	76	54	26	36	199	
wt% of component in							
C	4.7	4.3	2.2	1.5	1.5	7.1	
H	0.2	0.3	0.5	0.5	0.6	0.9	
S	5.1	4.3	0.6	0.5	0.5	0.6	
Ash	101.3	93.4	72.6	32.3	49.9	89.4	
Produced Water rate, lbs/hr	387	395	360	346	350	698	
wt% of component in							
H	48.9	50.7	48.8	47.9	49.9	43.4	
O	24.8	25.8	24.1	23.0	24.0	23.6	
overall wt% recoveries							
C	97.8	95.8	94.4	101.3	99.0	105.4	
H	102.9	103.6	105.6	100.3	102.7	104.8	
N	99.6	98.7	101.8	99.7	100.4	108.7	
S	66.6	75.1	85.2	96.1	75.6	74.1	
O	98.6	98.2	97.5	97.3	99.7	94.7	
Ar	80.0	100.2	107.4	104.2	110.9	142.5	
Ash	101.3	93.4	65.2	32.3	63.3	89.4	

TABLE A-2. CLARIFIER OVERHEAD WATER TEST RESULTS

RUN - TEST PERIOD	1-A 1-B 1-C 1-D 1-E 1-F 1-G 2-A 2-B									
	1-A	1-B	1-C	1-D	1-E	1-F	1-G	2-A	2-B	
S=	365	325	347	381	162	311	483	123	114	
SCN-	25	48	36	26	12	9	NS	54	51	
Ca	1	2	1	<1PPM	<1PPM	<1PPM	1	NS	NS	
Fe	26	25	26	20	22	21	25	NS	NS	
SO4	237	193	197	250	121	107	94	NS	NS	
RUN - TEST PERIOD	2-C 2-D 2-E 3-E 4-A 4-B 5-A 6-A 6-B									
	2-C	2-D	2-E	3-E	4-A	4-B	5-A	6-A	6-B	
S=	154	149	153	70	146	NS	NS	NS	NS	
SCN-	66		25	NS	66	35	NS	NS	NS	
Ca	NS	NS	NS	NS	29	23	NS	NS	NS	
Fe	NS	NS	NS	NS	1	1	NS	NS	NS	
SO4	NS	NS	NS	NS	<1	<1	<1	<1	<1	

NOTES: NS=not sampled, ND=not detected

Table A-3. Ultimate Analysis of Crossflow Filter, Cyclone, and Radiant Vessel Solids

Run	RUN 2-3	Run 4	Run 5	Run 6					
Sample of	Crossflow filter	Radiant Vessel	Cyclone	Crossflow Filter	Radiant Vessel	Cyclone	Crossflow Filter	Cyclone	Crossflow Filter
ULTIMATE ANALYSIS, wt%									
CARBON	54.04	8.34	12.23	15.63	7.66	17.01	14.84	7.98	17.21
HYDROGEN	0.46	0.30	0.23	0.62	0.10	0.87	1.06	0.11	0.91
NITROGEN	0.59	0.04	0.04	0.11	0.06	0.17	0.22	0.20	0.25
SULFUR	2.75	7.01	1.86	3.77	9.71	0.13	3.66	0.23	5.61
CHLORINE									
ASH	44.04	89.36	68.49	76.48	105.84	64.72	71.99	76.02	75.25
GROSS HEATING VALUE									
CALC. GHV Btu/lb	8040.37	765.00	494.00	2058.00	1969.90	1676.21	1978.64	0.00	2657.47
Run	Run 7	Fixed bed analysis			3rd Layer	3rd Layer	4th Layer	Cyclone	
Sample of	1st Layer	1st Layer	2nd Layer	2nd Layer	TOP	BOTTOM	BOTTOM		
	TOP	BOTTOM	TOP	BOTTOM					
ULTIMATE ANALYSIS, wt%									
CARBON	4.87	7.40	4.67	6.21	3.42	3.05	3.07	10.12	
HYDROGEN	0.04	0.03	0.03	0.02	0.03	0.02	0.03	0.79	
NITROGEN									
SULFUR	10.60	3.27	11.10	7.26	14.90	13.50	11.60	0.17	
CHLORINE									
ASH	99.21	77.89	100.71	88.81	111.56	110.30	108.93	61.66	
GROSS HEATING VALUE									
CALC. GHV Btu/lb	1153.97	97.42	1216.03	670.86	1763.64	1514.20	1309.01	127.29	

Table A-4. SLURRY ASH ANALYSIS

Page 1 of 4

RUN - TEST PERIOD METHOD OF ANALYSIS	1-A		1-B		1-C		1-D		1-E		1-F	
	DCP	ELEM.	DCP	ELEM.	DCP	ELEM.	DCP	OXIDE	DCP	OXIDE	DCP	OXIDE
ASH %	11.95	11.95	11.99	11.99	20.14	20.14	21.03	21.03	20.77	20.77	21.08	21.08
Reporting Method, wt%												
SODIUM	0.64	0.86	0.59	0.80	0.39	0.53	0.34	0.46	0.35	0.47	0.34	0.46
MAGNESIUM	0.90	1.49	0.60	0.99	0.50	0.83	0.50	0.83	0.50	0.83	0.50	0.83
ALUMINIUM	8.50	16.06	7.40	13.98	5.70	10.77	5.30	10.01	5.10	9.64	5.20	9.83
SILICON	15.30	32.73	15.60	33.80	10.50	22.46	9.80	20.97	9.50	20.32	9.60	20.54
POTASSIUM	1.37	1.65	1.15	1.39	0.80	0.96	0.82	0.99	0.82	0.99	0.82	0.99
CALCIUM	1.50	2.10	1.20	1.68	1.00	1.40	0.90	1.26	0.90	1.26	0.90	1.26
TITANIUM	0.53	0.88	0.45	0.75	0.32	0.53	0.30	0.51	0.29	0.48	0.30	0.50
CHROMIUM	0.03	0.04	0.02	0.03	0.03	0.04	0.03	0.05	0.03	0.05	0.04	0.05
IRON	21.20	30.31	19.00	27.16	43.50	62.19	43.00	61.48	42.10	60.19	44.30	63.34
SULFUR												
ZINC	0.02	0.03	0.03	0.03	0.04	0.05	0.01	0.02	0.05	0.06	0.08	0.11
VANADIUM	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.00	0.00	0.00	0.00
COPPER	0.05	0.06	0.07	0.08	0.05	0.06	0.05	0.06	0.05	0.06	0.05	0.07
COBALT	0.03	0.03	0.02	0.02	0.01	0.01	0.01	0.01	0.01	0.02	0.01	0.01
NICKEL	0.02	0.03	0.02	0.02	0.02	0.02	0.05	0.06	0.01	0.02	0.01	0.02
BARIUM	0.06	0.07	0.05	0.05	0.03	0.04	0.03	0.04	0.03	0.04	0.03	0.04
STRONTIUM	0.06											
TOTAL	50.22	86.37	46.40	80.82	62.89	99.91	61.17	96.76	59.76	94.43	62.19	98.03

Table A-4. SLURRY ASH ANALYSIS

Page 2 of 4

RUN - TEST PERIOD METHOD OF ANALYSIS	1-G		2-A		2-B		2-C,E,F,G		2-D	
	DCP	ELEM.	DCP	ELEM.	DCP	ELEM.	DCP	ELEM.	DCP	ELEM.
ASH %	21.07	21.07	21.07	21.07	7.54	7.54	7.45	7.45	7.45	8.44
Reporting Method, wt%										
SODIUM	0.31	0.42	0.91	1.23	0.85	0.88	1.19	0.67	1.07	0.01
MAGNESIUM	0.50	0.83	0.60	0.99	2.71	0.50	0.83	2.19	1.57	0.42
ALUMINIUM	4.74	8.96	10.20	19.27	24.74	10.70	20.22	20.08	22.70	9.50
SILICON	8.80	18.83	17.40	37.22	45.77	18.10	38.72	39.33	39.26	16.30
POTASSIUM	0.76	0.92	1.22	1.47	1.26	1.11	1.34	1.18	1.88	0.92
CALCIUM	0.80	1.12	3.30	4.62	4.00	3.10	4.34	3.43	4.15	2.82
TITANIUM	0.28	0.46	0.74	1.23	1.29	0.60	1.00	0.89	1.09	0.55
CHROMIUM	0.03	0.05	0.02	0.03	0.09	0.07	0.11	0.12	0.11	0.06
IRON	41.80	59.76	13.10	18.73	18.03	13.40	19.16	13.04	21.34	20.80
SULFUR				0.00	3.50		0.00	2.61	3.24	0.00
ZINC	0.04	0.05	0.02	0.03	0.33	0.01	0.01	0.01	0.13	0.01
VANADIUM	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
COPPER	0.05	0.06	0.08	0.10	0.04	0.12	0.16	0.05	0.02	0.04
COBALT	0.01	0.01	0.01	0.01		0.01	0.01			0.01
NICKEL	0.02	0.02	0.03	0.04	0.06	0.03	0.03	0.02	0.05	0.01
BARIUM	0.03	0.04	0.09	0.10	0.18	0.09	0.10	0.00	0.03	0.08
STRONTIUM			0.12	0.14	0.29	0.14	0.16	0.13	0.10	0.13
TOTAL	58.17	91.53	47.93	85.36	103.25	48.93	87.48	84.06	96.12	51.76
										89.82

Page 3 of 4

TOTAL

Table A-4. SLURRY ASH ANALYSIS

Page 4 of 4

RUN - TEST PERIOD METHOD OF ANALYSIS	5-B		6-A		6-B		7-A	
	DCP	X-RAY	X-RAY	X-RAY	DCP	X-RAY	DCP	X-RAY
ASH %	7.93	7.93	7.93	7.94	7.94	8.05	8.65	8.65
Reporting Method, wt%	ELEM.	OXIDE	OXIDE	OXIDE	ELEM.	ELEM.	ELEM.	OXIDE
SODIUM	1.00	0.57	0.77	0.66	1.10	0.68	1.31	0.40
MAGNESIUM	0.43	0.52	0.87	0.68	0.60	0.40	0.80	0.47
ALUMINIUM	11.00	10.46	19.76	14.85	10.10	7.97	10.10	11.87
SILICON	19.20	18.49	39.55	32.55	16.10	15.32	18.30	30.09
POTASSIUM	1.16	1.10	1.33	1.32	1.36	1.08	1.18	1.34
CALCIUM	4.80	3.18	4.45	4.47	3.60	3.39	3.70	6.12
TITANIUM	0.62	0.68	1.14	1.16	0.47	0.69	0.60	1.31
CHROMIUM	0.03	0.08	0.11	0.13	0.03	0.07	0.04	0.12
IRON	16.50	14.46	20.68	20.34	12.80	14.44	14.50	23.70
SULFUR		2.94	7.36	7.17		2.93		8.53
ZINC	0.02	0.00	0.01	0.03	0.02	0.01	0.06	0.04
VANADIUM	0.04	0.00	0.00	0.00	0.01	0.00	0.01	0.00
COPPER	0.24	0.10	0.12	0.08	0.14	0.07	0.04	0.11
COBALT	0.03	0.00			ND		0.00	
NICKEL	0.05	0.09	0.11	0.04	0.02	0.03	0.04	0.06
BARIUM	0.10	0.00	0.00	0.00	0.08	0.00	0.10	0.00
STRONTIUM	0.16	0.07	0.08	0.08	0.15	0.07	0.21	0.22
TOTAL	55.44	52.92	96.72	83.56	46.58	47.15	51.42	85.14

Table A-5. Coarse Slag Ash Analysis
Page 1 of 5

RUN - TEST PERIOD		1-A		1-B		1-C		1-D		1-E		1-F	
METHOD OF ANALYSIS		DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP
ASH %		102.55	102.55	103.25	103.25	104.32	104.32	104.40	104.40	104.56	104.56	104.70	104.70
Reporting Method, wt%		ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	ELEMENT
SODIUM		0.57	0.77	0.60	0.81	0.49	0.66	0.42	0.57	0.37	0.50	0.42	0.42
MAGNESIUM		0.60	0.99	0.70	1.16	0.50	0.83	0.50	0.83	0.50	0.83	0.49	0.49
ALUMINIUM		9.00	17.01	9.00	17.01	5.10	9.64	5.00	9.45	4.50	8.50	4.30	4.30
SILICON		17.00	36.37	17.40	37.22	9.90	21.18	8.60	18.40	8.80	18.83	8.60	8.60
POTASSIUM		1.31	1.58	1.45	1.75	0.90	1.08	0.75	0.90	0.71	0.86	0.73	0.73
CALCIUM		1.80	2.52	1.70	2.38	1.00	1.40	0.90	1.26	0.90	1.26	0.56	0.56
TITANIUM		0.53	0.88	0.52	0.87	0.32	0.54	0.30	0.51	0.29	0.48	0.27	0.27
CHROMIUM		0.83	1.21	0.25	0.36	0.36	0.53	0.27	0.39	0.25	0.36	0.18	0.18
IRON		22.10	31.60	21.90	31.31	42.90	61.34	43.20	61.76	46.10	65.91	43.50	43.50
SULFUR													
ZINC		0.03	0.03	0.01	0.01	0.00	0.01	0.00	0.00	0.02	0.03	0.01	0.01
VANADIUM		0.03	0.05	0.00	0.01	0.01	0.02	0.01	0.01	0.01	0.01	0.00	0.00
COPPER		0.02	0.02	0.02	0.02	0.03	0.03	0.04	0.05	0.02	0.03	0.02	0.02
COBALT		0.01	0.01	0.02	0.02	0.01	0.01	0.02	0.02	0.01	0.01	0.01	0.01
NICKEL		0.02	0.03	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
BARIUM		0.06	0.07	0.06	0.07	0.03	0.03	0.04	0.04	0.03	0.04	0.03	0.03
STRONTIUM		0.06	0.07										
TOTAL		53.98	93.23	53.64	93.01	61.57	97.31	60.05	94.20	62.52	97.66	59.14	59.14

Table A-5. Coarse Slag Ash Analysis
Page 2 of 5

RUN - TEST PERIOD		1-G,H		1-PS		2-A		2-B		2-C	
METHOD OF ANALYSIS	DCP	DCP	DCP	DCP	DCP	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY
ASH %	104.83	104.83	105.30	105.30	105.30	99.57	99.57	99.33	99.33	101.36	101.36
Reporting Method,wt%	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	OXIDE	ELEMENT
SODIUM	0.39	0.53	0.39	0.53	0.92	0.97	0.97	0.95	0.51	1.06	0.68
MAGNESIUM	0.50	0.83	0.90	1.49	1.20	2.57	2.57	0.71	0.92	0.67	0.86
ALUMINIUM	4.10	7.75	5.30	10.01	9.90	13.44	13.44	10.30	8.66	10.80	10.82
SILICON	8.00	17.11	9.60	20.54	17.30	32.21	32.21	18.60	16.13	19.60	26.01
POTASSIUM	0.70	0.84	0.71	0.86	1.10	1.12	1.12	0.97	0.98	1.17	1.08
CALCIUM	0.67	0.94	0.90	1.26	3.30	4.58	4.58	4.10	3.96	3.80	4.54
TITANIUM	0.25	0.41	0.28	0.46	0.59	0.86	0.86	0.55	0.56	0.59	0.89
CHROMIUM	0.19	0.28	0.23	0.33	2.91	2.83	2.83	1.02	0.72	0.62	0.91
IRON	44.90	64.19	41.40	59.19	15.10	20.01	20.01	17.90	17.14	15.30	20.70
SULFUR						0.96	0.96		0.40		0.33
ZINC	0.00	0.00	0.03	0.04						0.01	0.00
VANADIUM	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.00
COPPER	0.02	0.03	0.02	0.02	0.02	0.00	0.00	0.02	0.01	0.02	0.00
COBALT	0.01	0.02	0.01	0.01	0.01			0.01		0.01	
NICKEL	0.02	0.03	0.01	0.02	0.02	0.06	0.06	0.00	0.04	0.02	0.05
BARIUM	0.03	0.03	0.03	0.04	0.08	0.09	0.09	0.08	0.04	0.09	0.37
STRONTIUM	0.03	0.03	0.03	0.03	0.12	0.29	0.29	0.13	0.08	0.14	0.30
TOTAL	59.83	93.05	59.85	94.84	52.67	80.23	80.23	55.37	50.33	53.95	67.60
											50.19

Table A-5. Coarse Slag Ash Analysis
Page 3 of 5

RUN - TEST PERIOD		2-E		2-F		3-A		3-B		3-C	
METHOD OF ANALYSIS		DCP	X-RAY	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY
ASH %		103.08	103.08	102.48	102.48	110.06	110.06	108.70	108.70	108.99	108.99
Reporting Method, wt%		ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT
SODIUM		0.96	0.56	1.21	0.63	0.40	0.45	0.70	0.50	0.45	0.51
MAGNESIUM		0.60	0.80	0.60	0.90	0.32	0.19	0.30	0.26	0.18	0.19
ALUMINIUM		10.10	9.33	11.00	10.42	5.24	3.16	4.24	2.69	3.70	2.39
SILICON		17.80	16.89	19.30	18.07	9.50	6.39	8.50	5.78	7.60	5.31
POTASSIUM		0.92	1.05	1.05	1.10	0.24	0.71	0.40	0.63	0.29	0.58
CALCIUM		3.60	3.83	3.50	3.69	1.84	1.96	1.93	1.84	1.54	1.79
TITANIUM		0.54	0.58	0.56	0.62	0.30	0.44	0.29	0.42	0.22	0.40
CHROMIUM		0.21	0.19	0.32	0.25	0.15	0.23	0.15	0.22	0.06	0.18
IRON		19.50	19.51	17.50	17.41	42.00	30.78	46.40	32.43	48.50	32.54
SULFUR			0.34		0.32		1.26		1.12		1.12
ZINC		0.02	0.01	0.02	0.01	0.03	0.00	0.03	0.00	0.02	0.00
VANADIUM		0.01	0.04	0.00	0.05	0.01	0.04	0.01	0.04	0.00	0.04
COPPER											
COBALT											
NICKEL											
BARIUM											
STRONTIUM		0.13	0.08	0.14	0.08	0.08	0.03	0.08	0.03	0.06	0.03
TOTAL		54.54	53.45	55.33	53.75	60.88	45.95	63.44	46.30	63.04	45.45

Table A-5. Coarse Slag Ash Analysis
Page 4 of 5

RUN - TEST PERIOD		3-D		3-E		4-O		4-A&B		5-A		5-B	
METHOD OF ANALYSIS		DCP	DCP	DCP	X-RAY	X-RAY	X-RAY	X-RAY	X-RAY	DCP	X-RAY	DCP	X-RAY
ASH %		109.17	109.92	109.92	109.92	98.69	98.69	99.01	99.01	100.27	100.27	101.60	101.60
Reporting Method, wt%		ELEMENT	ELEMENT	ELEMENT	ELEMENT	OXIDE	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE
SODIUM		0.54	0.50	0.50	4.45	0.53	0.71	0.62	0.83	0.83	1.11	1.10	0.70
MAGNESIUM		0.17	0.17	0.17	0.00	0.28	0.46	0.28	0.47	0.40	0.64	0.52	0.33
ALUMINIUM		3.59	3.63	3.63	2.03	7.65	14.45	7.68	14.52	9.40	10.77	12.50	7.62
SILICON		7.20	7.20	7.20	4.59	14.75	31.55	15.25	32.62	17.90	32.63	22.30	16.20
POTASSIUM		0.31	0.30	0.30	0.56	1.03	1.24	1.03	1.24	0.99	1.33	1.17	1.12
CALCIUM		1.58	1.50	1.50	1.56	4.15	5.81	4.10	5.73	4.40	6.12	6.40	3.91
TITANIUM		0.21	0.22	0.22	0.38	0.57	0.95	0.58	0.97	0.57	1.07	0.68	0.59
CHROMIUM		0.06	0.06	0.06	0.17	0.25	0.37	0.24	0.35	0.03	0.33	0.65	0.56
IRON		49.50	49.40	49.40	31.96	17.16	24.53	16.35	23.37	19.30	27.85	19.70	17.75
SULFUR					1.25	0.44	1.11	0.35	0.88		1.32		0.24
ZINC		0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.06	0.00	0.01	0.00
VANADIUM		0.01	0.00	0.00	0.05	0.00	0.00	0.00	0.00	0.00	0.00	0.04	0.00
COPPER						0.00	0.00	0.00	0.00	0.21	0.01	0.02	0.00
COBALT										0.00		0.03	0.00
NICKEL						0.05	0.06	0.05	0.06	0.02	0.05	0.02	0.05
BARIUM						0.04	0.05	0.06	0.07	0.08	0.03	0.11	0.05
STRONTIUM		0.06	0.06	0.06	0.03							0.05	0.04
TOTAL		63.68	63.48	63.48	47.39	47.18	81.83	46.86	81.64	54.35	83.75	65.49	49.44
													85.85

Table A-5. Coarse Slag Ash Analysis
Page 5 of 5

RUN - TEST PERIOD		6-O		6-A		7-A			
METHOD OF ANALYSIS		X-RAY		DCP		X-RAY		DCP	
ASH %		101.40		101.40		101.82		101.15	
Reporting Method, wt%		OXIDE		ELEMENT		OXIDE		ELEMENT	
SODIUM		1.06		1.03		0.44		1.24	
MAGNESIUM		0.47		1.10		0.41		0.90	
ALUMINIUM		9.51		10.10		9.30		10.60	
SILICON		25.12		16.00		25.45		18.30	
POTASSIUM		1.26		1.30		1.25		1.08	
CALCIUM		4.97		3.40		5.05		3.60	
TITANIUM		0.99		0.47		0.94		0.52	
CHROMIUM		1.87		1.18		2.86		1.85	
IRON		23.91		13.50		23.70		15.50	
SULFUR		0.51				0.67		0.22	
ZINC		0.01		0.00		0.00		0.01	
VANADIUM		0.00		ND		0.00		0.00	
COPPER		0.01		0.03		0.01		0.02	
COBALT				ND				0.00	
NICKEL		0.07		ND		0.06		0.02	
BARIUM		0.02		0.07		0.05		0.08	
STRONTIUM		0.05		0.09		0.10		0.13	
TOTAL				54.05		44.46		74.09	

Table A-6. Fine Slag Ash Analysis
Page 1 of 5

Run-Test Period	1-A		1-B		1-C		1-D		1-E	
METHOD OF ANALYSIS	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP
ASH %	91.33	91.33	96.63	96.63	95.94	95.94	98.76	98.76	99.07	99.07
Reporting Method, wt%	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE
SODIUM	0.55	0.74	0.61	0.82	0.59	0.80	0.44	0.59	0.37	0.50
MAGNESIUM	0.60	0.99	0.80	1.33	0.50	0.83	0.50	0.83	0.70	1.16
ALUMINIUM	9.70	18.33	9.20	17.38	5.40	10.20	5.30	10.01	4.60	8.69
SILICON	18.50	39.58	17.30	37.01	10.40	22.25	9.40	20.11	9.10	19.47
POTASSIUM	1.41	1.70	1.32	1.59	0.89	1.07	0.78	0.94	0.70	0.84
CALCIUM	1.70	2.38	1.50	2.10	1.00	1.40	1.10	1.54	1.00	1.40
TITANIUM	0.56	0.93	0.54	0.89	0.34	0.56	0.32	0.54	0.29	0.49
CHROMIUM	0.07	0.11	0.06	0.09	0.26	0.38	0.17	0.25	0.14	0.20
IRON	21.20	30.31	22.10	31.60	43.90	62.77	47.00	67.20	44.10	63.05
SULFUR										
ZINC	0.17	0.21	0.01	0.02	0.01	0.02	0.01	0.02	0.01	0.01
VANADIUM	0.00	0.00	0.00	0.00	0.01	0.02	0.01	0.01	0.01	0.01
COPPER	0.02	0.02	0.01	0.01	0.03	0.04	0.02	0.02	0.01	0.02
COBALT	0.01	0.02	0.02	0.02	0.01	0.01	0.01	0.01	0.01	0.01
NICKEL	0.02	0.03	0.02	0.03	0.03	0.03	0.02	0.02	0.02	0.02
BARIUM	0.06	0.07	0.04	0.05	0.03	0.03	0.03	0.04	0.03	0.04
STRONTIUM			0.06	0.07						
TOTAL	54.58	95.42	53.60	93.02	63.41	100.42	65.11	102.14	61.09	95.92

Table A-6. Fine Slag Ash Analysis
Page 2 of 5

Run-Test Period	1-F		2-A		2-B		2-C			
	DCP		DCP		DCP		DCP		DCP	
	ELEMENT	99.93	OXIDE	100.12	ELEMENT	40.14	OXIDE	40.14	X-RAY	55.94
METHOD OF ANALYSIS										
ASH %										
Reporting Method, wt%										
SODIUM	0.37	0.50	0.55	1.11	1.50	0.99	1.37	1.19	0.93	1.00
MAGNESIUM	0.60	0.99	0.99	0.50	0.83	2.07	1.33	2.29	0.51	1.96
ALUMINIUM	4.90	9.26	9.07	10.70	20.22	20.72	21.16	19.68	10.50	24.82
SILICON	9.10	19.47	19.25	18.30	39.15	40.59	41.29	40.15	18.50	44.57
POTASSIUM	0.72	0.87	0.90	1.24	1.49	1.27	1.39	1.26	1.02	1.44
CALCIUM	1.20	1.68	1.40	2.50	3.50	3.25	4.06	4.21	2.90	4.74
TITANIUM	0.30	0.50	0.50	0.65	1.08	1.05	1.03	1.03	0.55	1.06
CHROMIUM	0.08	0.12	0.16	0.31	0.45	0.27	0.29	0.24	0.05	0.13
IRON	46.60	66.63	65.62	14.90	21.30	20.07	20.59	21.96	15.80	22.91
SULFUR					0.00	1.37	0.00	1.25		2.50
ZINC	0.03	0.03	0.01	0.05	0.06	0.04	0.06	0.01	0.05	0.06
VANADIUM	0.00	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.03
COPPER	0.01	0.02	0.02	0.07	0.09	0.04	0.05	0.02		
COBALT	0.01	0.02	0.02	0.01	0.01	0.01	0.01	0.01		
NICKEL	0.02	0.02	0.03	0.03	0.04	0.05	0.03	0.05		
BARIUM	0.03	0.04	0.04	0.09	0.10	0.22	0.10	0.09		
STRONTIUM			0.04	0.13	0.15	0.30	0.17	0.39	0.16	0.10
TOTAL	63.98	100.15	98.64	50.69	90.14	92.51	93.02	93.94	51.11	105.57

Table A-6. Fine Slag Ash Analysis
Page 3 of 5

Run-Test Period	2-D			2-E			2-F			3-A			3-B			3-C		
METHOD OF ANALYSIS	FINE SLG			FINE SLG			FINE SLG			FINE SLG			FINE SLG			FINE SLG		
ASH %	DCP	X-RAY	59.11	DCP	X-RAY	58.99	DCP	X-RAY	59.15	DCP	X-RAY	82.66	DCP	X-RAY	86.28	DCP	X-RAY	82.65
Reporting Method, wt%	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT
SODIUM	0.99	1.21	1.31	1.13	1.36	1.27	0.72	0.95	1.02	1.03	0.86	0.86	0.86	0.86	0.86	0.86	0.86	0.86
MAGNESIUM	0.48	1.53	0.49	0.51	1.55	0.40	0.81	0.40	0.98	0.30	0.86	0.86	0.86	0.86	0.86	0.86	0.86	0.86
ALUMINIUM	10.30	21.62	10.80	11.10	23.99	7.10	14.20	6.40	11.96	6.10	22.86	22.86	22.86	22.86	22.86	22.86	22.86	22.86
SILICON	16.50	39.21	18.80	19.40	43.21	11.90	25.60	10.90	21.70	10.40	21.31	21.31	21.31	21.31	21.31	21.31	21.31	21.31
POTASSIUM	1.04	1.46	1.10	1.11	1.45	1.12	1.63	0.96	1.47	0.96	1.46	1.46	1.46	1.46	1.46	1.46	1.46	1.46
CALCIUM	2.90	4.34	2.70	2.90	4.29	1.75	2.94	1.62	2.72	1.77	2.67	2.67	2.67	2.67	2.67	2.67	2.67	2.67
TITANIUM	0.57	1.06	0.56	0.58	1.06	0.43	0.96	0.35	0.87	0.34	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85
CHROMIUM	0.10	0.14	0.04	0.16	0.24	0.08	0.19	0.05	0.19	0.05	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20
IRON	18.50	26.46	15.90	15.90	23.36	32.60	39.24	37.00	42.45	37.70	41.31	41.31	41.31	41.31	41.31	41.31	41.31	41.31
SULFUR		2.36			1.77		2.57		2.57		2.34	2.34	2.34	2.34	2.34	2.34	2.34	2.34
ZINC	0.08	0.03	0.11	0.06	0.04	0.07	0.02	0.04	0.01	0.04	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
VANADIUM	0.00	0.05	0.01	0.01	0.04	0.01	0.05	0.01	0.05	0.01	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05
COPPER																		
COBALT																		
NICKEL																		
BARIUM																		
STRONTIUM	0.14	0.10	0.13	0.14	0.10	0.10	0.06	0.09	0.05	0.09	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05
TOTAL	51.77	99.91	52.09	53.13	102.75	57.14	89.58	59.12	86.81	59.14	95.48	95.48	95.48	95.48	95.48	95.48	95.48	95.48

Table A-6. Fine Slag Ash Analysis
Page 4 of 5

Run-Test Period	3-D FINE SLG		3-E FINE SLG		4-A&B		5-0	
METHOD OF ANALYSIS	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP
ASH %	84.78	84.78	96.49	96.49	55.21	55.21	77.17	77.17
Reporting Method, wt%	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	OXIDE	ELEMENT	OXIDE
SODIUM	1.00	0.87	0.57	0.52	1.23	0.59	0.80	0.79
MAGNESIUM	0.30	0.96	0.40	0.37	0.55	0.46	0.76	0.32
ALUMINIUM	6.30	12.12	4.60	7.02	11.10	10.02	18.93	8.10
SILICON	10.20	22.01	8.40	14.44	20.00	18.08	38.67	24.77
POTASSIUM	0.98	1.55	0.41	0.93	1.13	1.09	1.31	1.16
CALCIUM	1.45	2.52	1.55	2.46	3.60	3.34	4.68	5.13
TITANIUM	0.36	0.89	0.25	0.76	0.69	0.63	1.05	1.06
CHROMIUM	0.06	0.20	0.06	0.24	0.12	0.10	0.15	0.23
IRON	27.20	44.60	48.00	50.34	16.90	14.78	21.13	23.67
SULFUR		2.13		4.84		1.16	2.91	4.79
ZINC	0.05	0.01	0.01	0.00	0.02	0.01	0.01	0.01
VANADIUM	0.01	0.05	0.00	0.05	0.00	0.00	0.00	0.00
COPPER					0.02	0.00	0.00	0.01
COBALT					0.02			
NICKEL				0.05	0.05	0.05	0.06	0.10
BARIUM				0.07	0.11	0.04	0.05	0.00
STRONTIUM	0.09	0.04	0.07	0.03				
TOTAL	48.35	88.65	64.76	82.60	55.67	50.61	90.98	70.75

Table A-6. Fine Slag Ash Analysis
Page 5 of 5

Run-Test Period	5-A		5-B		6-O		6-A		7-A	
METHOD OF ANALYSIS	DCP	X-RAY	X-RAY	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY	X-RAY
ASH %	68.06	68.06	68.06	62.50	60.35	60.35	63.55	63.55	77.10	77.10
Reporting Method, wt%	ELEMENT	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	ELEMENT	OXIDE
SODIUM	1.03	0.76	1.03	1.10	0.61	1.05	0.75	1.00	1.09	0.30
MAGNESIUM	1.00	0.45	0.74	0.70	0.45	0.55	0.48	0.80	0.80	0.02
ALUMINIUM	11.90	8.84	16.71	11.70	13.70	11.00	12.79	10.10	10.20	4.86
SILICON	20.90	17.23	36.86	20.60	32.39	18.00	30.27	16.50	21.20	12.73
POTASSIUM	1.21	1.14	1.37	1.24	1.44	1.51	1.37	1.32	1.16	1.17
CALCIUM	4.20	3.23	4.52	3.80	3.71	2.70	4.28	2.50	3.80	4.30
TITANIUM	0.67	0.64	1.07	0.66	1.12	0.52	1.14	0.49	0.52	0.68
CHROMIUM	0.26	0.24	0.35	0.12	0.18	0.06	0.33	0.17	0.26	0.32
IRON	17.70	16.41	23.46	17.00	22.51	12.80	23.55	12.60	17.00	20.65
SULFUR		1.25	3.13		1.31		2.52			1.20
ZINC	0.02	0.01	0.01	0.03	0.02	0.03	0.02	0.03	0.01	0.01
VANADIUM	0.11	0.01	0.03	0.14	0.00	0.01	0.00	0.01	0.02	0.01
COPPER	0.04	0.01	0.02	0.04	0.03	0.07	0.01	0.03	0.02	0.01
COBALT	0.02	0.00		0.02		ND		ND	0.00	
NICKEL	0.04	0.06	0.07	0.03	0.08	0.05	0.07	0.01	0.00	0.06
BARIUM	0.10	0.03	0.04	0.11	0.00	0.08	0.01	0.08	0.09	0.05
STRONTIUM	0.15	0.09	0.11	0.16	0.10	0.15	0.11	0.14	0.12	0.15
TOTAL	59.45	50.63	89.96	57.55	77.69	46.93	58.58	79.60		

Table A-7. CLARIFIER BOTTOMS ASH ANALYSIS
Page 1 of 6

RUN - TEST PERIOD		1-A		1-B		1-C		1-D		1-E	
METHOD OF ANALYSIS		DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP	DCP
ASH %		71.92	71.92	88.05	88.05	94.01	94.01	82.41	82.41	83.14	83.14
Reporting Method,wt%		ELEM.	OXIDE	ELEMENT	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT
SODIUM		0.86	1.16	0.70	0.94	0.70	0.94	0.53	0.71	0.59	0.80
MAGNESIUM		0.60	0.99	0.80	1.33	0.50	0.83	0.80	1.33	0.60	0.99
ALUMINIUM		9.90	18.71	9.90	18.71	7.10	13.42	8.10	15.30	7.00	13.23
SILICON		17.70	37.87	18.10	38.72	11.80	25.24	12.80	27.38	12.30	26.31
POTASSIUM		1.63	1.96	1.62	1.95	1.62	1.95	1.34	1.61	1.35	1.64
CALCIUM		1.90	2.66	1.50	2.10	1.10	1.54	0.33	0.47	1.10	1.54
TITANIUM		0.60	1.00	0.60	1.00	0.42	0.70	0.52	0.86	0.49	0.82
CHROMIUM		0.04	0.06	0.03	0.05	0.07	0.10	0.05	0.07	0.05	0.07
IRON		21.10	30.17	21.60	30.88	38.90	55.62	35.00	50.04	33.60	48.04
SULFUR											
ZINC		0.08	0.09	0.06	0.07	0.05	0.07	0.06	0.08	0.07	0.08
VANADIUM		0.02	0.04	0.00	0.01	0.00	0.01	0.00	0.00	0.00	0.00
COPPER		0.02	0.02	0.02	0.02	0.01	0.02	0.01	0.02	0.02	0.03
COBALT		0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
NICKEL		0.05	0.06	0.02	0.03	0.02	0.02	0.02	0.03	0.01	0.02
BARIUM		0.07	0.08	0.06	0.07	0.05	0.05	0.05	0.06	0.05	0.05
STRONTIUM		0.08	0.09								
TOTAL		54.67	95.01	55.03	95.90	62.36	100.52	59.64	97.99	57.25	93.64

161

RUN - TEST PERIOD			1-F		2-A		2-B		2-C		2-D	
METHOD OF ANALYSIS			DCP	DCP	DCP	DCP	X-RAY	DCP	X-RAY	DCP	DCP	X-RAY
Reporting Method, wt%			ELEMENT	OXIDE	ELEMENT	ELEMENT	ELEMENT	OXIDE	ELEMENT	ELEMENT	OXIDE	ELEMENT
ASH %			88.44	88.44	20.69	20.69	20.69	27.90	27.90	46.54	46.54	41.41
SODIUM			0.59	0.8	1.26	1.70	1.28	1.20	1.62	1.28	1.67	1.15
MAGNESIUM			0.50	0.83	0.50	0.83	2.72	0.50	0.83	2.72	0.91	0.57
ALUMINIUM			5.40	10.2	11.20	21.16	24.13	11.20	21.16	24.13	21.54	11.30
SILICON			9.80	20.97	18.20	38.94	43.94	18.50	39.58	43.91	40.65	18.50
POTASSIUM			1.38	1.66	1.30	1.57	1.37	1.26	1.52	1.37	1.49	1.11
CALCIUM			1.00	1.4	2.20	3.08	3.39	2.30	3.22	3.39	3.92	2.50
TITANIUM			0.37	0.61	0.72	1.20	1.22	0.67	1.12	1.22	1.22	0.65
CHROMIUM			0.09	0.13	0.08	0.12	0.12	0.03	0.04	0.11	0.04	0.08
IRON			39.80	56.9	13.50	19.30	19.77	13.80	19.73	19.77	16.87	17.00
SULFUR						0.00	1.43		0.00	1.43	0.00	0.74
ZINC			0.04	0.05	0.10	0.12	0.07	0.08	0.10	0.07	0.13	0.03
VANADIUM			0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
COPPER			0.01	0.01	0.10	0.12	0.03	0.06	0.08	0.03	0.07	0.03
COBALT			0.01	0.01	0.01	0.01		0.01	0.02		0.01	0.01
NICKEL			0.02	0.02	0.03	0.04	0.06	0.03	0.04	0.06	0.04	0.01
BARIUM			0.05	0.05	0.10	0.11	0.16	0.09	0.10	0.16	0.12	0.09
STRONTIUM			0.03	0.03	0.13	0.15	0.25	0.14	0.16	0.25	0.20	0.17
TOTAL			59.10	93.71	49.53	88.61	100.25	49.95	89.42	100.21	89.04	53.88

Table A-7. CLARIFIER BOTTOMS ASH ANALYSIS
Page 3 of 6

METHOD OF ANALYSIS	2-E		2-F		3-A		3-B		3-C	
	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY
ASH %	32.01	32.01	49.96	49.96	74.06	74.06	71.29	71.29	70.24	70.24
Reporting Method, wt% ELEMENT	1.20	0.81	1.44	0.85	1.32	0.54	1.06	0.64	1.00	0.64
SODIUM	0.70	0.98	0.70	1.21	0.90	0.60	0.60	0.72	0.50	0.48
MAGNESIUM	11.80	13.04	11.00	13.52	7.80	7.34	6.90	6.95	6.70	6.10
ALUMINIUM	18.80	19.66	17.80	20.30	12.40	11.32	10.80	10.75	10.30	9.71
SILICON	1.15	1.29	1.45	1.30	1.46	1.42	1.21	1.30	1.10	1.23
POTASSIUM	2.90	2.97	2.90	3.07	4.10	2.37	2.10	2.19	1.80	2.07
CALCIUM	0.67	0.68	0.79	0.71	0.50	0.61	0.43	0.58	0.47	0.55
TITANIUM	0.03	0.08	0.10	0.07	0.04	0.12	0.05	0.12	0.05	0.13
CHROMIUM	14.70	14.91	12.60	13.36	31.60	25.77	34.90	27.28	33.30	28.82
IRON		0.79		0.64		0.85		0.86		0.91
SULFUR		0.04		0.06		0.02		0.02		0.02
ZINC	0.05	0.00	0.06	0.00	0.05	0.00	0.03	0.00	0.04	0.00
VANADIUM	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
COPPER	0.04	0.02	0.06	0.02	0.04	0.01	0.05	0.00	0.04	0.00
COBALT	0.01		0.01		0.01		0.01		0.01	
NICKEL	0.01	0.04	0.02	0.05	0.02	0.05	0.02	0.04	0.01	0.04
BARIUM	0.09	0.06	0.11	0.08	0.07	0.02	0.07	0.01	0.06	0.02
STRONTIUM	0.16	0.11	0.20	0.13	0.15	0.06	0.13	0.04	0.11	0.05
TOTAL	52.37	55.61	49.30	55.50	60.66	51.43	58.52	51.82	55.71	51.08

Table A-7. CLARIFIER BOTTOMS ASH ANALYSIS
Page 4 of 6

RUN - TEST PERIOD		3-D		3-E		4-O		4-A	
METHOD OF ANALYSIS		DCP	X-RAY	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY
ASH %		70.38	70.38	67.71	67.71	46.54	51.62	53.62	53.62
Reporting Method, wt%		ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	OXIDE
SODIUM		0.92	0.71	0.95	0.55	1.34	0.55	1.38	0.71
MAGNESIUM		0.50	0.57	0.50	0.54	0.66	0.42	0.92	0.60
ALUMINIUM		6.50	6.21	0.00	6.03	11.10	9.78	10.30	9.18
SILICON		10.60	9.85	6.40	9.55	18.70	17.14	17.50	16.00
POTASSIUM		1.15	1.26	1.05	1.26	1.13	1.12	1.14	0.94
CALCIUM		2.10	2.02	1.90	1.94	3.40	3.45	5.40	5.28
TITANIUM		0.42	0.54	0.38	0.55	0.75	0.67	0.69	0.59
CHROMIUM		0.10	0.14	0.04	0.14	0.04	0.07	0.04	0.06
IRON		36.30	29.91	38.10	31.13	18.00	15.64	16.70	14.98
SULFUR			0.80		0.75		1.56		2.26
ZINC		0.05	0.02	0.03	0.02	0.31	0.03	0.07	0.03
VANADIUM		0.00	0.00	0.00	0.00	0.24	0.13	0.00	0.00
COPPER		0.03	0.00	0.03	0.00	0.03	0.00	0.02	0.00
COBALT		0.01		0.01		0.02		0.05	
NICKEL		0.01	0.04	0.01	0.04	0.09	0.09	0.03	0.06
BARIUM		0.07	0.02	0.07	0.09	0.12	0.06	0.11	0.07
STRONTIUM		0.11	0.04	0.10	0.04	0.16	0.11	0.16	0.11
TOTAL		59.14	52.45	49.90	52.95	56.10	50.98	54.54	51.10
									91.18
									21.42
									5.66
									0.04
									0.00
									0.00
									0.07
									0.08
									0.13
									91.02

Table A-7. CLARIFIER BOTTOMS ASH ANALYSIS

Page 5 of 6

METHOD OF ANALYSIS	4-B		5-A		5-B	
	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY
ASH %	52.69	52.69	68.06	68.06	55.73	55.73
Reporting Method, wt%	ELEMENT	ELEMENT	ELEMENT	OXIDE	ELEMENT	OXIDE
SODIUM	1.26	0.42	1.24	0.73	1.22	0.42
MAGNESIUM	1.60	0.77	0.56	0.33	0.61	0.41
ALUMINIUM	9.80	8.52	9.90	6.68	11.90	8.42
SILICON	16.50	15.03	17.60	15.77	19.50	15.40
POTASSIUM	0.98	0.78	1.15	1.24	1.25	1.19
CALCIUM	7.50	6.86	4.40	3.90	4.00	3.03
TITANIUM	0.60	0.52	0.65	0.71	0.77	0.68
CHROMIUM	0.04	0.06	0.04	0.06	0.08	0.11
IRON	14.10	13.56	17.50	17.85	18.30	16.88
SULFUR		2.89		1.97		1.42
ZINC	0.05	0.02	0.09	0.06	0.18	0.08
VANADIUM	0.00	0.00	0.00	0.00	0.63	0.62
COPPER	0.02	0.00	0.08	0.02	0.08	0.02
COBALT	0.04		0.00	0.00	0.02	0.00
NICKEL	0.05	0.06	0.02	0.04	0.23	0.17
BARIUM	0.10	0.06	0.09	0.01	0.12	0.03
STRONTIUM	0.16	0.10	0.02	0.10	0.18	0.10
TOTAL	52.81	49.86	53.54	49.71	59.24	49.25
						86.95

Table A-7. CLARIFIER BOTTOMS ASH ANALYSIS
Page 6 of 6

METHOD OF ANALYSIS	6-A			6-B			7-A		
	X-RAY	X-RAY	DCP	X-RAY	OXIDE	ELEMENT	DCP	ELEMENT	X-RAY
ASH %	56.27	56.27	56.27	60.15	60.15	60.15	77.35	77.35	77.35
Reporting Method, wt%	OXIDE	ELEMENT	ELEMENT	OXIDE	OXIDE	ELEMENT	ELEMENT	ELEMENT	OXIDE
SODIUM	0.75	0.56	1.21	0.62	0.46	1.27	1.09	0.55	0.74
MAGNESIUM	0.57	0.34	1.00	0.46	0.28	0.72	0.60	0.27	0.44
ALUMINIUM	14.07	7.44	10.50	12.81	6.78	10.20	9.10	5.23	9.88
SILICON	31.68	14.81	16.70	29.08	13.59	15.50	18.50	11.92	25.51
POTASSIUM	1.50	1.24	1.59	1.18	0.98	1.46	1.09	1.16	1.40
CALCIUM	4.29	3.07	2.60	7.50	5.36	5.30	3.60	4.67	6.54
TITANIUM	1.25	0.75	0.53	1.12	0.67	0.54	0.50	0.82	1.37
CHROMIUM	0.14	0.09	0.04	0.11	0.08	0.03	0.02	0.10	0.15
IRON	22.13	15.48	12.20	19.77	13.83	11.20	13.10	19.46	27.82
SULFUR	2.80	1.12		7.16	2.86			1.98	4.96
ZINC	0.11	0.09	0.11	0.08	0.06	0.07	0.03	0.06	0.08
VANADIUM	0.15	0.08	0.11	0.00	0.00	0.02	0.00	0.03	0.05
COPPER	0.04	0.03	0.06	0.03	0.02	0.06	0.09	0.02	0.03
COBALT			ND			ND	0.00		
NICKEL	0.11	0.08	0.03	0.07	0.06	0.04	0.00	0.07	0.09
BARIUM	0.01	0.01	0.09	0.01	0.01	0.09	0.08	0.04	0.05
STRONTIUM	0.13	0.11	0.17	0.13	0.11	0.18	0.18	0.23	0.27
TOTAL	79.58	45.20	46.77	79.99	45.03	46.50	48.23	47.10	80.38

Table A-8. Ash Analysis of Cyclone, Crossflow Filter, and Radiant Vessel
Page 1 of 3

ASH ANALYSIS	Run 3		Run 4		Radiant Vessel		Crossflow Filter		Cyclone	
	Crossflow Filter	Dolomite	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY
METHOD OF ANALYSIS	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY	DCP	X-RAY
ASH %	44.04	44.04	10um	22um	89.36	89.36	76.49	76.49	68.49	68.49
METAL ANALYZED	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT
SODIUM	1.58	0.72	0.03	0.03	0.13	0.56	0.75	0.65	0.88	0.78
MAGNESIUM	0.70	1.27	11.80	11.10	16.80	6.93	11.49	4.38	7.26	6.75
ALUMINIUM	10.30	9.49	0.11	0.11	0.59	0.50	0.94	2.13	4.03	0.66
SILICON	17.70	17.48	0.42	0.26	1.33	1.36	2.92	4.26	9.11	1.80
POTASSIUM	1.44	1.07	0.02	0.04	0.10	0.31	0.37	0.40	0.48	0.31
CALCIUM	3.00	3.38	23.70	23.00	29.70	28.38	39.71	17.22	24.09	29.85
TITANIUM	0.57	0.58	0.03	0.03	0.06	0.02	0.03	0.20	0.33	0.11
CHROMIUM	0.02	2.83	0.00	0.00	0.01	0.01	0.01	0.07	0.10	0.02
IRON	19.00	11.44	0.14	0.15	1.01	0.94	1.34	15.76	22.53	2.12
SULFUR		0.51				9.97	24.92	7.09	17.73	3.35
ZINC	0.02	0.00	0.02	0.01	0.02	0.02	0.02	0.05	0.06	0.02
VANADIUM	0.00	0.00	0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00
COPPER	0.07	0.01	0.00	0.00	0.01	0.00	0.00	0.02	0.02	0.00
COBALT	0.01	0.00	0.01	0.01	0.01	0.00	0.00	0.02	0.02	0.00
NICKEL	0.01	0.04	0.00	0.01	0.05	0.08	0.10	0.09	0.12	0.10
BARIUM	0.08	0.05	0.01	0.00	0.01	0.00	0.00	0.00	0.00	0.00
STRONTIUM	0.15	0.08	0.00	0.00	0.02	0.03	0.03	0.03	0.04	0.03
TOTAL	54.72	49.20	36.30	34.78	49.86	49.09	82.63	52.35	86.78	46.02
								54.29	59.90	71.44

Table A-8. Ash Analysis of Cyclone, Crossflow Filter, and Radiant Vessel
Page 2 of 3

ASH ANALYSIS	Run 5		Run 6		Run 7	
	Dolomite Slurry	Dolomite Slurry	Dolomite Slurry	Radnat Cyclone Vessel	Crossflow Filter	1ST LAIR TP
METHOD OF ANALYSIS	DCP	X-RAY	X-RAY	DCP	X-RAY	DCP
ASH %	NASHE	UNASHED	UNASHED	76.02	67.97	75.25
METAL ANALYZED	ELEMENT	OXIDE	ELEMENT	ELEMENT	OXIDE	ELEMENT
SODIUM	0.08	1.28	0.95	0.08	0.37	0.26
MAGNESIUM	13.00	6.76	4.08	17.53	3.42	3.08
ALUMINIUM	0.04	0.00	0.00	0.05	9.26	1.35
SILICON	0.41	0.41	0.19	0.39	21.61	2.98
POTASSIUM	0.05	0.35	0.29	0.05	0.87	0.37
CALCIUM	28.10	39.75	28.41	20.70	13.78	11.90
TITANIUM	0.03	0.10	0.06	0.00	0.80	0.12
CHROMIUM	<.5	0.00	0.00	0.30	0.12	0.82
IRON	0.19	0.00	0.00	3.83	17.34	17.70
SULFUR		0.00	0.00		10.59	9.86
ZINC	0.01	0.02	0.01	0.02	0.01	0.07
VANADIUM	<.5	0.00	0.00	0.00	0.00	0.01
COPPER	0.00	0.00	0.00	0.03	0.03	0.07
COBALT	<.05			0.00		0.00
NICKEL	0.21	0.09	0.07	0.05	0.11	0.76
BARIUM	<.05	0.00	0.00	0.00	0.01	0.02
STRONTIUM	0.00	0.01	0.01	0.01	0.04	0.01
TOTAL	42.11	48.77	34.07	34.25	78.35	45.34
				63.25	91.66	64.05
				44.98	54.68	
				48.76		

Table A-8. Ash Analysis of Cyclone, Crossflow Filter, and Radiant Vessel
Page 3 of 3

ASH ANALYSIS	Fixed Bed								Cyclone	
	1ST	2ND	2ND	3RD	3RD	4TH				
	LAIR BTM	LAIR TOP	LAIR BTM	LAIR TP	LAIR BTM	LAIR BTM				
METHOD OF ANALYSIS	DCP	DCP	DCP	DCP	DCP	DCP				
ASH %	77.49	100.71	88.81	111.56	110.30	108.93				61.66
METAL ANALYZED	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT				
SODIUM	0.00	0.01	0.01	0.04	0.16	0.30				0.13
MAGNESIUM	20.50	16.40	19.40	15.60	13.50	11.70				12.70
ALUMINIUM	0.18	0.13	0.18	0.28	1.10	2.28				1.77
SILICON	0.46	0.38	0.46	0.74	2.46	3.84				2.25
POTASSIUM	0.02	0.02	0.02	0.06	0.17	0.24				0.09
CALCIUM	45.00	37.00	44.00	35.40	31.10	27.10				36.00
TITANIUM	0.02	0.03	0.02	0.03	0.07	0.22				0.23
CHROMIUM	0.00	0.00	0.02	0.01	0.03	0.68				0.02
IRON	0.36	0.35	0.52	0.79	2.20	3.37				7.30
SULFUR	1.86	8.02	4.48	8.27	7.95	6.75				2.33
ZINC	0.02	0.03	0.03	0.01	0.01	0.08				0.07
VANADIUM	0.00	0.00	0.00	0.00	0.00	0.00				0.00
COPPER	0.02	0.01	0.02	0.02	0.02	0.02				0.03
COBALT	0.00	0.00	0.00	0.00	0.00	0.00				0.00
NICKEL	0.15	0.02	0.02	0.02	0.00	0.00				0.00
BARIUM										
STRONTIUM	0.01	0.00	0.00	0.00	0.00	0.00				0.00
TOTAL	68.59	62.40	69.17	61.27	58.77	56.58				62.92

Appendix B

Raw Data: Mixed Metal Oxide Sorbents

Tables B-1 through B-9 are the ash analysis for each sorbent bed run. The tables are broken down by bed section.

Figures B-1 and B-2 are the UCI sorbent specification sheets for each sorbent tested.

Table B-1. Zinc Ferrite Run 1 Analysis

Bed Position METHOD OF ANALYSIS ASH % METAL ANALYZED, wt%	Top		Top		Middle		Middle		Bottom	
	DCP	101.58	DCP	101.58	DCP	99.29	DCP	99.29	DCP	92.08
	ELEMENT	OXIDE	OXIDE	OXIDE	ELEMENT	OXIDE	OXIDE	OXIDE	ELEMENT	OXIDE
SODIUM	0.08	0.11	0.85		0.06	0.08	1.05		0.08	0.11
MAGNESIUM	0.04	0.07	0.00		0.04	0.07	0.00		0.04	0.07
ALUMINIUM	0.42	0.79	0.62		0.37	0.70	0.58		0.28	0.53
SILICON	0.84	1.80	0.38		0.79	1.69	0.43		0.69	1.48
POTASSIUM	0.04	0.05	0.28		0.04	0.05	0.28		0.04	0.05
CALCIUM	0.05	0.07	0.00		0.07	0.10	0.00		0.07	0.10
TITANIUM	0.04	0.06	0.10		0.12	0.20	0.11		0.03	0.06
CHROMIUM	0.19	0.28	0.35		0.09	0.13	0.35		0.04	0.05
IRON	46.30	66.20	68.35		45.10	64.48	71.27		45.90	65.62
SULFUR		0.00	0.08			0.00	0.12			0.00
ZINC	26.10	32.49	26.03		25.30	31.49	27.37		26.70	33.24
VANADIUM	0.01	0.02	0.10		0.05	0.08	0.10		0.01	0.02
COPPER	0.05	0.07	0.00		0.07	0.08	0.03		0.07	0.08
COBALT	0.01	0.01			0.01	0.01			0.02	0.03
NICKEL	0.03	0.04	0.08		0.01	0.02	0.07		0.03	0.04
BARIUM	0.01	0.01	0.00		0.02	0.02	0.00		0.01	0.01
STRONTIUM	0.01	0.01	0.00		0.01	0.02	0.00		0.01	0.01
TOTAL	74.21	102.09	97.22		72.15	99.22	101.76		74.02	101.48
										100.54

Table B-2. Zinc Titanate (L-3014) Run 1 Analysis

Bed Position	Top		Middle		Bottom	
METHOD OF ANALYSIS	DCP	Top DCP	DCP	Middle DCP	DCP	Bottom DCP
ASH %	96.08	96.08	96.08	93.60	92.90	92.90
METAL ANALYZED, wt%	ELEMENT	OXIDE	OXIDE	OXIDE	ELEMENT	OXIDE
SODIUM	0.10	0.13	0.14	0.19	0.08	1.99
MAGNESIUM	0.07	0.11	0.05	0.08	0.06	0.00
ALUMINIUM	0.34	0.64	0.34	0.64	0.33	0.00
SILICON	0.82	1.75	0.89	1.90	0.80	0.00
POTASSIUM	0.09	0.11	0.10	0.12	0.10	0.04
CALCIUM	0.03	0.04	0.03	0.04	0.03	0.00
TITANIUM	23.20	38.70	23.40	39.03	23.10	55.91
CHROMIUM	0.01	0.02	0.06	0.08	0.01	0.00
IRON	0.16	0.23	0.38	0.54	0.13	0.00
SULFUR		0.00		0.00		0.06
ZINC	46.20	57.51	45.10	56.14	46.20	50.28
VANADIUM	0.01	0.02	0.03	0.06	0.01	0.39
COPPER	0.02	0.03	0.02	0.03	0.02	0.00
COBALT	0.01	0.01	0.01	0.01	0.01	0.01
NICKEL	0.04	0.05	0.01	0.02	0.02	0.03
BARIUM	0.00	0.00	0.01	0.01	0.00	0.02
STRONTIUM	0.01	0.01	0.02	0.02	0.01	0.00
TOTAL	71.11	99.36	70.59	98.92	70.90	108.72

Table B-3. Zinc Titanate (L-3140) Run 1 Analysis

Bed Position	Top	Top	Middle	Middle	Middle	Bottom	Bottom
METHOD OF ANALYSIS	DCP	DCP	DCP	DCP	X-RAY	DCP	X-RAY
ASH %	97.21	97.21	97.21	95.36	95.36	92.23	92.23
METAL ANALYZED, wt%	ELEMENT	OXIDE	ELEMENT	OXIDE	OXIDE	ELEMENT	OXIDE
SODIUM	0.11	0.15	0.14	0.19	2.85	0.10	3.07
MAGNESIUM	0.06	0.10	0.10	0.16	0.00	0.08	0.00
ALUMINIUM	0.23	0.43	0.26	0.49	0.00	0.26	0.00
SILICON	0.57	1.22	0.74	1.58	0.00	0.58	0.00
POTASSIUM	0.14	0.17	0.15	0.18	0.07	0.13	0.07
CALCIUM	0.03	0.05	0.06	0.08	0.00	0.04	0.00
TITANIUM	32.90	54.88	32.90	54.88	37.48	33.50	37.51
CHROMIUM	0.01	0.02	0.01	0.01	0.00	0.01	0.00
IRON	0.26	0.37	0.47	0.67	0.00	0.64	0.00
SULFUR		0.00		0.00	0.00		0.00
ZINC	33.00	41.08	32.30	40.21	68.11	32.70	67.76
VANADIUM	0.01	0.02	0.01	0.00	0.35	0.01	0.38
COPPER	0.03	0.03	0.04	0.05	0.01	0.02	0.01
COBALT	0.01	0.02	0.01	0.01		0.01	
NICKEL	0.03	0.04	0.03	0.03	0.04	0.02	0.07
BARIUM	0.00	0.00	0.01	0.01	0.00	0.00	0.05
STRONTIUM	0.01	0.01	0.02	0.02	0.00	0.01	0.00
TOTAL	67.41	98.59	67.24	98.60	106.91	68.12	108.92

Table B-4. Zinc Ferrite Run 2 Analysis

Bed Position METHOD OF ANALYSIS ASH % METAL ANALYZED, wt%	Top	Middle	Middle	Bottom
	DCP	DCP	DCP	DCP
	81.51	85.04	85.04	75.61
	OXIDE	ELEMENT	OXIDE	ELEMENT
				OXIDE
SODIUM	0.49	1.05	1.42	2.36
MAGNESIUM	0.19	0.21	0.35	0.60
ALUMINIUM	3	3.60	6.80	9.88
SILICON	4.3	5.50	11.77	17.97
POTASSIUM	0.28	0.49	0.59	1.17
CALCIUM	0.67	1.03	1.44	2.52
TITANIUM	0.28	0.30	0.50	0.63
CHROMIUM	2.65	0.34	0.50	1.84
IRON	33.1	28.40	40.60	33.03
SULFUR			0.00	0.00
ZINC	23.6	26.00	32.36	24.40
VANADIUM	0	0.00	0.01	0.01
COPPER	0.27	0.14	0.18	0.30
COBALT	0.02	0.02	0.02	0.02
NICKEL	3.98	0.51	0.65	2.39
BARIUM	0.03	0.05	0.05	0.06
STRONTIUM	0.03	0.06	0.07	0.10
TOTAL	72.90	67.71	97.32	65.15
				97.31

Table B-5. Zinc Titanate (L-3014) Run 2 Analysis

Bed Position	Top	Top	Middle	Middle	Bottom	Bottom
METHOD OF ANALYSIS	DCP	DCP	DCP	DCP	DCP	DCP
ASH %	74.17	74.17	73.89	73.89	67.69	67.69
METAL ANALYZED, wt%	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE
SODIUM	1.26	1.70	1.30	1.75	1.71	2.31
MAGNESIUM	0.30	0.50	0.37	0.61	0.54	0.90
ALUMINIUM	4.80	9.07	5.60	10.58	7.70	14.55
SILICON	8.00	17.11	9.10	19.47	12.10	25.89
POTASSIUM	1.38	1.66	1.36	1.64	1.70	2.05
CALCIUM	1.30	1.82	1.60	2.24	1.98	2.77
TITANIUM	11.60	19.35	12.30	20.52	9.90	16.51
CHROMIUM	2.29	3.35	1.38	2.02	0.47	0.69
IRON	13.70	19.59	12.40	17.73	10.40	14.87
SULFUR		0.00		0.00		0.00
ZINC	15.20	18.92	15.10	18.80	13.50	16.80
VANADIUM	0.00	0.01	0.01	0.01	0.01	0.01
COPPER	0.16	0.21	0.08	0.10	0.08	0.10
COBALT	0.02	0.02	0.02	0.02	0.02	0.02
NICKEL	5.80	7.38	4.26	5.42	1.36	1.73
BARIUM	0.05	0.05	0.05	0.06	0.08	0.09
STRONTIUM	0.07	0.08	0.09	0.11	0.12	0.14
TOTAL	65.94	100.83	65.02	101.08	61.67	99.43

Table B-6. Zinc Titanate (L-3140) Run 2 Analysis

Bed Position	Top	Top	Middle	Middle	Bottom	Bottom
METHOD OF ANALYSIS	DCP	DCP	DCP	DCP	DCP	DCP
ASH %	72.93	72.93	80.37	80.37	71.70	71.70
METAL ANALYZED, wt%	ELEMENT	OXIDE	ELEMENT	OXIDE	ELEMENT	OXIDE
SODIUM	0.56	0.75	0.77	1.04	1.52	2.05
MAGNESIUM	0.19	0.32	0.19	0.32	0.51	0.85
ALUMINIUM	3.20	6.05	3.48	6.58	7.30	13.79
SILICON	5.50	11.77	6.00	12.84	12.00	25.67
POTASSIUM	0.91	1.10	1.16	1.40	1.68	2.02
CALCIUM	0.38	0.53	0.66	0.92	1.99	2.78
TITANIUM	11.90	19.85	13.30	22.19	7.00	11.68
CHROMIUM	1.19	1.74	0.45	0.65	0.29	0.42
IRON	9.20	13.15	4.99	7.13	11.80	16.87
SULFUR		0.00		0.00		0.00
ZINC	33.80	42.07	39.40	49.04	18.40	22.90
VANADIUM	0.00	0.01	0.00	0.01	0.01	0.01
COPPER	0.19	0.23	0.08	0.10	0.08	0.10
COBALT	0.02	0.02	0.02	0.02	0.02	0.02
NICKEL	3.52	4.48	1.34	1.71	0.81	1.03
BARIUM	0.03	0.04	0.04	0.04	0.09	0.10
STRONTIUM	0.04	0.05	0.05	0.06	0.14	0.16
TOTAL	70.64	102.16	71.93	104.05	63.63	100.47

Table B-7. Zinc Ferrite Run 3 Analysis

Bed Position METHOD OF ANALYSIS ASH % METAL ANALYZED, wt%	Top		Top		Top		Middle		Middle		Middle		Bottom		Bottom	
	DCP	ELEMENT	X-RAY	ELEMENT	X-RAY	OXIDE	DCP	ELEMENT	X-RAY	ELEMENT	DCP	ELEMENT	DCP	ELEMENT	X-RAY	OXIDE
SODIUM	0.16		0.70		0.95		0.11		0.69		0.13		0.13		0.70	0.94
MAGNESIUM	0.04		0.00		0.00		0.05		0.00		0.06		0.06		0.00	0.00
ALUMINIUM	0.12		0.15		0.29		0.25		0.29		0.23		0.23		0.30	0.56
SILICON	0.57		0.11		0.24		0.72		0.17		0.68		0.68		0.17	0.36
POTASSIUM	0.11		0.22		0.27		0.05		0.21		0.06		0.06		0.21	0.25
CALCIUM	0.06		0.00		0.00		0.06		0.00		0.06		0.06		0.00	0.00
TITANIUM	0.03		0.09		0.15		0.04		0.08		0.06		0.06		0.08	0.13
CHROMIUM	0.02		0.24		0.35		0.05		0.25		0.05		0.05		0.25	0.36
IRON	46.00		48.77		69.73		48.00		48.23		48.80		48.80		47.84	68.40
SULFUR			0.04		0.09				0.05						0.04	0.10
ZINC	27.60		21.26		26.46		28.40		21.23		29.30		29.30		20.98	26.11
VANADIUM	0.00		0.08		0.11		0.00		0.06		0.00		0.00		0.06	0.11
COPPER	0.04		0.00		0.00		0.06		0.00		0.06		0.06		0.00	0.00
COBALT	0.02		0.00		0.00		0.01		0.00		0.01		0.01		0.00	0.00
NICKEL	0.06		0.06		0.07		0.03		0.06		0.06		0.06		0.07	0.09
BARIUM	0.00		0.00		0.00		0.01		0.00		0.00		0.00		0.04	0.04
STRONTIUM	0.00		0.00		0.00		0.00		0.00		0.00		0.00		0.00	0.00
TOTAL	74.86		71.72		98.74		77.87		71.32		79.57		79.57		70.73	97.47

Table B-8. Zinc Titanate (L-3014) Run 3 Analysis

Bed Position	Top		Top		Top		Middle		Middle		Middle		Bottom		Bottom		Bottom	
METHOD OF ANALYSIS	DCP	X-RAY	X-RAY	X-RAY	X-RAY	DCP	DCP	X-RAY	X-RAY	X-RAY	X-RAY	DCP	DCP	X-RAY	X-RAY	X-RAY	X-RAY	X-RAY
ASH %	95.94	95.94	95.94	95.94	95.94	95.85	95.85	95.85	95.85	95.85	95.85	96.03	96.03	96.03	96.03	96.03	96.03	96.03
METAL ANALYZED, wt%	ELEMENT	ELEMENT	ELEMENT	ELEMENT	OXIDE	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	OXIDE	ELEMENT	ELEMENT	ELEMENT	ELEMENT	ELEMENT	OXIDE	OXIDE
SODIUM	0.21	1.30			1.75	0.21		1.28		1.73		0.20		1.19		1.60		
MAGNESIUM	0.10	0.00			0.00	0.08		0.00		0.00		0.09		0.00		0.00		
ALUMINIUM	0.27	0.00			0.00	0.28		0.00		0.00		0.25		0.00		0.00		
SILICON	0.67	0.00			0.00	0.64		0.00		0.00		0.61		0.00		0.00		
POTASSIUM	0.17	0.01			0.01	0.16		0.01		0.02		0.16		0.01		0.01		
CALCIUM	0.04	0.00			0.00	0.05		0.00		0.00		0.06		0.00		0.00		
TITANIUM	34.90	33.05			55.13	33.30		33.25		55.47		31.80		33.21		55.39		
CHROMIUM	0.00	0.00			0.00	0.01		0.00		0.00		0.01		0.00		0.00		
IRON	0.81	0.00			0.00	0.16		0.00		0.00		0.18		0.00		0.00		
SULFUR		0.00			0.00			0.00		0.00				0.00		0.00		
ZINC	35.90	39.58			49.27	34.20		39.90		49.66		34.40		39.85		49.60		
VANADIUM	0.00	0.00			0.00	0.00		0.00		0.00		0.00		0.00		0.00		
COPPER	0.03	0.00			0.00	0.01		0.00		0.00		0.01		0.00		0.00		
COBALT	0.01	0.00				0.01		0.00		0.00		0.01		0.00		0.00		
NICKEL	0.02	0.00			0.00	0.01		0.00		0.00		0.01		0.00		0.00		
BARIUM	0.00	0.01			0.01	0.00		0.00		0.00		0.09		0.02		0.02		
STRONTIUM	0.00	0.00				0.00		0.00		0.00		0.00		0.00		0.00		
TOTAL	73.13	73.95			106.17	69.14		74.45		106.88		67.90		74.27		106.62		

Table B-9. Zinc Titanate (L-3140) Run 3 Analysis

Bed Position	Top			Middle			Bottom		
METHOD OF ANALYSIS	DCP	X-RAY		DCP	X-RAY		DCP	X-RAY	
ASH %	96.19	96.19		96.53	96.53		95.64	95.64	
METAL ANALYZED, wt%	ELEMENT	ELEMENT	OXIDE	ELEMENT	ELEMENT	OXIDE	ELEMENT	ELEMENT	OXIDE
SODIUM	0.14	1.99	2.68	0.14	2.04	2.75	0.15	2.03	2.74
MAGNESIUM	0.07	0.00	0.00	0.07	0.00	0.00	0.07	0.00	0.00
ALUMINIUM	0.33	0.00	0.00	0.35	0.00	0.00	0.39	0.00	0.00
SILICON	0.87	0.00	0.00	0.85	0.00	0.00	0.91	0.00	0.00
POTASSIUM	0.11	0.02	0.03	0.11	0.03	0.04	0.11	0.02	0.03
CALCIUM	0.03	0.00	0.00	0.04	0.00	0.00	0.03	0.00	0.00
TITANIUM	22.80	22.01	36.71	22.50	22.07	36.81	23.40	21.98	36.67
CHROMIUM	0.01	0.00	0.00	0.01	0.00	0.00	0.01	0.00	0.00
IRON	0.13	0.00	0.00	0.16	0.00	0.00	0.15	0.00	0.00
SULFUR		0.00	0.00		0.00	0.00		0.00	0.00
ZINC	50.10	54.43	67.75	47.70	54.74	68.14	47.00	54.43	67.75
VANADIUM	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
COPPER	0.02	0.00	0.00	0.02	0.00	0.00	0.01	0.00	0.00
COBALT	0.01	0.00	0.00	0.01	0.00	0.00	0.01	0.00	0.00
NICKEL	0.01	0.00	0.00	0.01	0.02	0.02	0.01	0.01	0.01
BARIUM	0.00	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.00
STRONTIUM		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL	74.64	78.46	107.18	71.97	78.90	107.76	72.27	78.48	107.20

Table B-10. T-2465 & L-3014 Sorbents Specifications Sheet

United Catalysts Inc.
Girdler and CCI Catalysts

Post Office Box 32370
Louisville, Kentucky 40232

Telephone 502-634-7200
Telex 204190, 204239
Facsimile 502-637-3732

April 26, 1988

Mr. Jimmy Wu
Texaco Inc.
329 North Durfee Avenue
South El Monte, California 91733

Dear Jimmy:

The three sorbents which you had ordered are being prepared for shipment. These products were found to have the following characterizations:

1. Texaco P.O. HL 514270
Zinc Ferrite (T-2465)
Designated: L-3201
Density 81.5 lbs/CF
DWL Crush Strength 34 lbs
Crush Strength 4.0 lbs/mm
Surface Area 2.6 m²/g
Pore Volume 0.36 cc/g
XRD
 1. Zn Fe₂O₄, mcs > 2000Å
 2. ZnO - small amount
2. Texaco P.O. HL 514269
Zinc Titanate (L-3014)
Designated: L-3199
Density 58 lbs/CF
DWL Crush Strength 30 lbs
Crush Strength 3.4 lbs/mm
Surface Area 3.1 m²/g
Pore Volume 0.40 cc/g
XRD
 1. α-Zn₂TiO₄, mcs 888Å
 2. Zn₂Ti₂O₈, small amount
 3. TiO₂ (rutile), mcs > 2000Å
 4. TiO₂ (anatase), small amount
3. Texaco P.O. HL 514271
Zinc Copper Ferrite (L-2952)
Designated: L-3200
Density 76.5 lbs/CF
DWL Crush Strength 26 lbs
Crush Strength 3.5 lbs/mm
Surface Area 3.8 m²/g
Pore Volume 0.28 cc/g
XRD
 1. Zn Fe₂O₄, mcs > 2000Å
 2. Cu Fe₂O₄ (pattern for this very similar to Zn Fe₂O₄ pattern)

Table B-11. L-3140 Sorbent Specification Sheet

United Catalysts Inc.
Girdler and CCI Catalysts

Post Office Box 32370
Louisville, Kentucky 40232

Telephone 502-634-7200
Telex 204190, 204239
Facsimile 502-637-3732

May 5, 1989

Mr. Jerrold Kassman
Texaco Inc.
329 North Durfee Avenue
South Elmonta, CA 91733

Dear Jerry:

Earlier this month, we shipped to you 150 lbs of zinc titanate. This product was identified with the number L-3140 and is the same formulation as was used to make L-3196.

L-3140 has the following characterization:

Density	82.4 Lbs/CF
DWL Crush Strength	79 Lbs
Crush Strength	5.1 Lbs/mm
Surface Area	2.0 m ² /g
Hg Pore Volume	0.25 cc/g

XRD

1. α -Zn₂TiO₄ (75%) mcs >2000 Å^o
2. Zn₂Ti₃O₈ (25%) mcs >2000 Å^o
3. TiO₂ (anatase)?

A pore size distribution curve for this product also is attached.

Very truly yours,

W. L. Chemerys
Marketing Manager
Special Projects

Appendix C

Raw Data: Fiber Optic Alkali Monitor (FOAM)

Figures C-1 through C-20 are plots of individual sodium and potassium data points obtained with the Fiber Optic Alkali Monitor during testing at the Montebello Research Laboratory in July and August 1989. The test conditions are summarized in Table 3-22.

In Figures C-21 through C-23, the data from selected time periods have been replotted with a slightly expanded time scale and with a line joining the sodium data points in order to show the cyclic variation in the magnitude of the alkali readings. This roughly six minute cycle was traced to a six minute cycle in the magnitude of the pressure of the laboratory's low pressure flare line. The FOAM sample train discharged excess sample gas into this flare line, and it appears as though the pressure variations fed back into the FOAM system and affected the measurements.

Figure C-1. FOAM Data Plot # 1

Figure C-2. FOAM Data Plot # 2

Figure C-3. FOAM Data Plot # 3

Figure C-4. FOAM Data Plot # 4

Figure C-5. FOAM Data Plot # 5

Figure C-6. FOAM Data Plot # 6

Figure C-7. FOAM Data Plot # 7

Figure C-8. FOAM Data Plot # 8

Figure C-9. FOAM Data Plot # 9

Figure C-10. FOAM Data Plot # 10

Figure C-11. FOAM Data Plot # 11

Figure C-12. FOAM Data Plot # 12

Figure C-13. FOAM Data Plot # 13

Figure C-14. FOAM Data Plot # 14

Figure C-16. FOAM Data Plot # 16

Figure C-17. FOAM Data Plot # 17

Figure C-18. FOAM Data Plot # 18

Figure C-19. FOAM Data Plot # 19

Figure C-20. FOAM Data Plot # 20

Figure C-21. FOAM Data Plot # 21

Figure C-22. FOAM Data Plot # 22

Figure C-23. FOAM Data Plot # 23

Appendix D

Process Economics PFDs

Figures D-1 through D-18 are process flow diagrams for the process units which were designed and costed at the equipment level. Each PFD is identified by case number and process unit number.

Figure D-2. Case DOE2 - Unit 42: Gasification and Hot Gas Cleanup

Figure D-3. Case DOE2 - Unit 54: Dolomite Oxidation

Figure D-4. Case DOE3 - Unit 42: Gasification and Hot Gas Cleanup

Figure D-8. Case DOE5c - Unit 53: Direct Sulfur Recovery Process

Figure D-9. Case DOE6 - Unit 42: Gasification and Hot Gas Cleanup

Figure D-10. Cases DOE6a & b - Unit 52: Wet Sulfuric Acid Plant

Figure D-11. Case D0E6c - Unit 53: Direct Sulfur Recovery Process

Figure D-12. Case DOE7 - Unit 42: Gasification & Hot Gas Cleanup

Figure D-13. Case DOE7 - Unit 30: Extraction Air Boost System

Figure D-17. Case DOE9 - Unit 42: Gasification & Hot Gas Cleanup

Appendix E

Process Economics Detailed Cost Data

Tables E-1 through E-19 list cost data, by unit, for each process unit where conceptual process designs and equipment specifications were developed. Individual equipment prices were obtained either from vendor quotes or from Texaco's internally supported design and cost estimating software. The units designed and costed in this way were Unit 42 (gasification & hot gas cleanup), Unit 52 (Wet Sulfuric Acid Plant), Unit 53 (Direct Sulfur Recovery), Unit 54 (Dolomite Oxidation) and, in the case of the air-blown gasifier cases, Unit 30 (Extraction Air Boost System). The equipment labels in these tables correspond to the labels shown on the PFDs in Appendix D.

The costs for most other units were obtained by the capacity-factored estimating technique. The costs for the slag handling and process water systems, which are somewhat simplified in the hot gas cleanup cases compared with the cold gas cleanup base case, were obtained by the equipment-factored estimating technique. The data for equipment in the process units obtained by these last two estimating techniques is considered proprietary to Texaco and, therefore, is not listed in detail. However, the overall unit costs can be found in Tables 4-9 and 4-10 in the main body of the text.

Table E-1. Cases DOE5 A & B - Unit 42 (Gasification & Hot Gas Cleanup) Total Installed Costs
For Equipment Designed & Costed By Individual Item (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	3	334,200		2,082,200	2,416,400	7,249,200	12,863,000
42-E-100	RSC	3	6,618,040			6,618,040	19,854,120	35,229,200
42-V-220	Cyclone	3	88,000	419	335,000	423,000	1,269,000	2,251,700
42-V-221	Cyc Disch Bin	3	18,000	47	38,000	56,000	168,000	298,100
42-V-222	Cyclone L/H	3	18,000	47	38,000	56,000	168,000	298,100
42-F-230	Main CXFF	3				843,000	2,529,000	4,487,500
42-V-232	Main CXFF L/H	3	14,200	25	20,000	34,200	102,600	182,100
42-R-300	ZT Vessel	9	693,100	1808	1,446,000	2,139,100	19,251,900	34,160,600
42-F-330	Guard CXFF	3				843,000	2,529,000	4,487,500
42-V-332	Guard CXFF L/H	3	13,400	19	15,000	28,400	85,200	151,200
42-V-240	Screw Feed Bin	3	18,000	47	38,000	56,000	168,000	298,100
42-E-400	Suction Cooler	1	19,200			19,200	19,200	34,100
42-V-400	Suction KO Pot	1	8,760			8,760	8,760	15,500
42-C-400	Recycle Comp	3	470,200			470,200	1,410,600	1,692,700
42-V-410	Storage Drum	3	83,800			83,800	251,400	446,100
42-SE-24	Screw Cooler	3	2,000			2,000	6,000	10,600
42-RV-1	Rotary Feeder	3	4,300			4,300	12,900	22,900
42-LV-3	Dry L/H Valve	18	37,800			37,800	680,400	1,207,300
42-BV-1	Block Valve	36	81,200			81,200	2,923,200	5,186,900
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	317,000
42-CV-2	Slipstream FCV	0	36,850			36,850	0	0
total mid-1990 \$								103,640,200
42-S-300	1.8ZT Catalyst	9		3548	867,000	867,000	7,803,000	13,845,600

NOTES

- 1) Vessel operating $T < 1500\text{degF}$ - refractory costed @ $\$800/\text{ft}^3$
- 2) Vessel operating $T > 1500\text{degF}$ - refractory costed @ $0.6 \times (\$800/\text{ft}^3) + 0.4 \times (\$3500/\text{ft}^3)$
- 3) 1.8ZT catalyst costed @ $\$4.45/\text{lb}$ and $54.91 \text{ lb}/\text{ft}^3$

1) Quote from Haldor Topsoe for WSA2 tower, SO2 converter and SO2 catalyst FOB Houston, TX plus engineering and licencing

6) Factor = 3.217, including Haldor Topsoe equipment;
factor for compressors = 1.2

Table E-3. Case DOE5 B – Unit 52 (Wet Sulfuric Acid Plant)
Total Installed Costs For Equipment Designed &
Costed By Individual Item (mid-90\$)

Item <u>Tag#</u>	Item <u>Description</u>	TOT <u>QTY</u>	M.E.C. <u>90\$/unit</u>	total MEC <u>90\$</u>	TIC <u>90\$</u>
52-C-100	Vent Gas Comp	3	1,200,200	3,600,600	4,320,700
52-C-200	Air Compressor	3	1,957,800	5,873,400	7,048,100
52-P-100	Acid Pump	3	2,270	6,810	21,900
52-H-100	Fired Heater	3	369,700	1,109,100	3,568,000
52-F-100	HT Bag Filter	3	52,900	158,700	510,500
52-V-110	Filter L/H	3	13,400	40,200	129,300
52-LV-1	Dry L/H Valve	6	18,500	111,000	357,100
52-E-100	Comp Aftercool	3	183,600	550,800	1,771,900
52-E-200	Hot Air Recupr	3	131,300	393,900	1,267,200
52-E-300	ZT Intercooler	3	106,200	318,600	1,024,900
52-E-400	SO2 Cat Preclr	3	334,200	1,002,600	3,225,400
52-E-500	Hydra Cooler 1	3	250,500	751,500	2,417,600
52-E-550	Hydra Cooler 2	3	77,600	232,800	748,900
52-E-600	Acid Cooler 1	3	8,330	24,990	80,400
52-E-650	Acid Cooler 2	3	6,000	18,000	57,900
52-P-700	Shipping Pump	1	12,600	12,600	40,500
<u>52-D-702</u>	<u>Product Tank</u>	<u>1</u>	<u>4,300</u>	<u>4,300</u>	<u>13,800</u>
Total mid-90\$				14,209,900	26,604,100

NOTES:

1) Quote from Haldor Topsoe for WSA2 tower, SO ₂ converter and SO ₂ catalyst FOB Houston,TX plus engineering and licencing fees (all three trains) is:	\$9,000 (\$1000s)
2) Est. cost less licencing fee (3%):	\$8,730 (\$1000s)
3) Est. cost less engineering fee (5%):	\$8,294 (\$1000s)
4) SO ₂ catalyst cost is \$2/liter, or	\$56.64 per ft ³
5) Single train flow into converter is:	2,592,282 SCFH
Assume reactor space velocity (NTP):	2,000 hr-1
Then, catalyst volume per reactor is:	1296 ft ³
And, cataylst cost per train is:	\$73,405
Cataylst cost for all trains is:	\$220,216 <<<<<<<<<
6) Factor = 3.217, including Haldor Topsoe equipment;
factor for compressors = 1.2	

TIC	(\$1000s)	53,284
-----	-----------	--------

Table E-4. Case DOE5 C – Unit 42 (Gasification & Hot Gas Cleanup) Total Installed Costs
For Equipment Designed & Costed By Individual Item (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	3	334,200		2,082,200	2,416,400	7,249,200	12,863,000
42-E-100	RSC	3	6,709,560			6,709,560	20,128,680	35,716,300
42-V-220	Cyclone	3	88,000	419	335,000	423,000	1,269,000	2,251,700
42-V-221	Cyc Disch Bin	3	18,000	47	38,000	56,000	168,000	298,100
42-V-222	Cyclone L/H	3	18,000	47	38,000	56,000	168,000	298,100
42-F-230	Main CXFF	3				843,000	2,529,000	4,487,500
42-V-232	Main CXFF L/H	3	14,200	25	20,000	34,200	102,600	182,100
42-R-300	ZT Vessel	9	693,100	1808	1,446,000	2,139,100	19,251,900	34,160,600
42-F-330	Guard CXFF	3				843,000	2,529,000	4,487,500
42-V-332	Guard CXFF L/H	3	13,400	19	15,000	28,400	85,200	151,200
42-V-240	Screw Feed Bin	3	18,000	47	38,000	56,000	168,000	298,100
42-E-400	Suction Cooler	1	19,300			19,300	19,300	34,200
42-V-400	Suction KO Pot	1	8,800			8,800	8,800	15,600
42-C-400	Recycle Comp	3	470,200			470,200	1,410,600	1,692,700
42-V-410	Storage Drum	3	84,800			84,800	254,400	451,400
42-SE-24	Screw Cooler	3	2,000			2,000	6,000	10,600
42-RV-1	Rotary Feeder	3	4,300			4,300	12,900	22,900
42-LV-3	Dry L/H Valve	18	37,800			37,800	680,400	1,207,300
42-BV-1	Block Valve	36	81,200			81,200	2,923,200	5,186,900
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	317,000
42-CV-2	Slipstream FCV	3	36,850			36,850	110,550	196,200
total mid-1990 \$							104,329,000	
42-S-300	1.8ZT Catalyst	9		3548	867,000	867,000	7,803,000	13,845,600

NOTES:

- 1) Vessel operating T < 1500degF – refractory costed @ \$800/ft3
- 2) Vessel operating T > 1500degF – refractory costed @ 0.6x(\$800/ft3)+0.4x(\$3500/ft3)
- 3) 1.8ZT catalyst costed @ \$4.45/lb and 54.91 lb/ft3

-

Table E-6. Cases DOE5 A & B – Unit 42 (Gasification & HOT Gas cleanup) Total Installed Costs
For Equipment Designed & Costed By Individual Item (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	3	334,200		2,082,200	2,416,400	7,249,200	12,863,000
42-E-100	RSC	3	6,861,920			6,861,920	20,585,760	36,527,400
42-V-220	Cyclone	3	88,000	419	335,000	423,000	1,269,000	2,251,700
42-V-221	Cyc Disch Bin	3	20,900	66	53,000	73,900	221,700	393,400
42-V-222	Cyclone L/H	3	20,900	66	53,000	73,900	221,700	393,400
42-F-230	Main CXFF	3				843,000	2,529,000	4,487,500
42-V-232	Main CXFF L/H	3	15,700	33	26,000	41,700	125,100	222,000
42-R-300	ZT Vessel	9	423,200	1124	899,000	1,322,200	11,899,800	21,115,000
42-F-330	Guard CXFF	3				843,000	2,529,000	4,487,500
42-V-332	Guard CXFF L/H	3	14,200	24	19,000	33,200	99,600	176,700
42-V-240	Screw Feed Bin	3	20,900	66	53,000	73,900	221,700	393,400
42-E-400	Suction Cooler	1	19,300			19,300	19,300	34,200
42-V-400	Suction KO Pot	1	8,880			8,880	8,880	15,800
42-C-400	Recycle Comp	3	470,200			470,200	1,410,600	1,692,700
42-V-410	Storage Drum	3	84,400			84,400	253,200	449,300
42-SE-24	Screw Cooler	3	3,000			3,000	9,000	16,000
42-RV-1	Rotary Feeder	3	6,500			6,500	19,500	34,600
42-LV-3	Dry L/H Valve	18	37,800			37,800	680,400	1,207,300
42-BV-1	Block Valve	36	81,200			81,200	2,923,200	5,186,900
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	317,000
42-CV-2	Slipstream FCV	0	31,020			31,020	0	0
total mid-1990 \$								92,264,800
42-S-300	1.8ZT Catalyst	9		1748	427,000	427,000	3,843,000	6,819,000

NOTES:

- 1) Vessel operating T < 1500degF – refractory costed @ \$800/ft3
- 2) Vessel operating T > 1500degF – refractory costed @ 0.6x(\$800/ft3)+0.4x(\$3500/ft3)
- 3) 1.8ZT catalyst costed @ \$4.45/lb and 54.91 lb/ft3

fees (all three trains) is:	\$11,000	(\$1000s)
2) Est. cost less licencing fee (3%):	\$10,670	(\$1000s)
3) Est. cost less engineering fee (5%):	\$10,137	(\$1000s)
4) SO ₂ catalyst cost is \$2/liter, or	\$56.64	per ft ³
5) Single train flow into converter is:	3,194,847	SCFH
Assume reactor space velocity (NTP):	2,000	hr ⁻¹
Then, catalyst volume per reactor is:	1597	ft ³
And, cataylst cost per train is:	\$90,454	
Catalyst cost for all trains is:	\$271,362	<<<<<<<<<<
6) Factor = 3.217, including Haldor Topsoe equipment;		
factor for compressors = 1.2

1) Quote from Haldor Topsoe for WSA2 tower, SO2 converter and SO2 catalyst FOB Houston,TX plus engineering and licencing fees (all three trains) is: \$4,500

\$4,500 (\$1000s)

\$4,365 (\$1000s)

\$4,147 (\$1000s)

\$56.64 per ft3

1,274,704 SCFH

2,000 hr-1

637 ft3

\$36,080

\$108,239 <<<<<<<<<

factor for compressors = 1.2

Table E-9. Case DOE6 C - Unit 42 (Gasification & Hot Gas Cleanup) Total Installed Costs
For Equipment Designed & Costed By Individual Items (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	3	334,200		2,082,200	2,416,400	7,249,200	12,863,000
42-E-100	RSC	3	6,907,680			6,907,680	20,723,040	36,771,000
42-V-220	Cyclone	3	88,000	419	335,000	423,000	1,269,000	2,251,700
42-V-221	Cyc Disch Bin	3	20,900	66	53,000	73,900	221,700	393,400
42-V-222	Cyclone L/H	3	20,900	66	53,000	73,900	221,700	393,400
42-F-230	Main CXFF	3				843,000	2,529,000	4,487,500
42-V-232	Main CXFF L/H	3	15,700	33	26,000	41,700	125,100	222,000
42-R-300	ZT Vessel	9	423,200	1124	899,000	1,322,200	11,899,800	21,115,000
42-F-330	Guard CXFF	3				843,000	2,529,000	4,487,500
42-V-332	Guard CXFF L/H	3	14,200	24	19,000	33,200	99,600	176,700
42-V-240	Screw Feed Bin	3	20,900	66	53,000	73,900	221,700	393,400
42-E-400	Suction Cooler	1	19,300			19,300	19,300	34,200
42-V-400	Suction KO Pot	1	8,890			8,890	8,890	15,800
42-C-400	Recycle Comp	3	470,200			470,200	1,410,600	1,692,700
42-V-410	Storage Drum	3	84,400			84,400	253,200	449,300
42-SE-24	Screw Cooler	3	3,000			3,000	9,000	16,000
42-RV-1	Rotary Feeder	3	6,500			6,500	19,500	34,600
42-LV-3	Dry L/H Valve	18	37,800			37,800	680,400	1,207,300
42-BV-1	Block Valve	36	81,200			81,200	2,923,200	5,186,900
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	317,000
42-CV-2	Slipstream FCV	3	36,850			36,850	110,550	196,200
total mid-1990 \$								92,704,600
42-S-300	1.8ZT Catalyst	9		1748	427,000	427,000	3,843,000	6,819,000

NOTES:

- 1) Vessel operating $T < 1500\text{degF}$ - refractory costed @ \$800/ft³
- 2) Vessel operating $T > 1500\text{degF}$ - refractory costed @ $0.6 \times (\$800/\text{ft}^3) + 0.4 \times (\$3500/\text{ft}^3)$
- 3) 1.8ZT catalyst costed @ \$4.45/lb and 54.91 lb/ft³

1) Sulfur storage and transfer equipment cost factored from data in EPRI Report CS-3342 vols. 2 & 3 (205.2 T/D Allied-Claus plant); includes 6 concrete lined earth pits providing 7-day storage, steam-traced double-walled transfer line, product shipping equipment, and misc. necessary equipment

Table E-11. Case DOE7 C - Unit 42 (Gasification & Hot Gas Cleanup) Total Installed Costs
For Equipment Designed & Costed By Individual Item (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	7	325,200		2,054,200	2,379,400	16,655,800	29,554,100
42-E-100	RSC	7	8,794,630			8,794,630	61,562,410	109,236,300
42-V-220	Cyclone	7	212,800	1,054	843,000	754,673	5,282,711	9,373,600
42-V-221	Cyc Disch Bin	7	17,900	46	37,000	39,242	274,693	487,400
42-V-222	Cyclone L/H	7	17,900	46	37,000	39,242	274,693	487,400
42-F-230	Main CXFF	7				843,000	5,901,000	10,470,700
42-V-232	Main CXFF L/H	7	14,100	24	19,000	23,659	165,616	293,900
42-R-300	ZT Vessel	21	815,900	1768	1,414,000	1,593,905	33,472,015	59,392,700
42-F-330	Guard CXFF	7				843,000	5,901,000	10,470,700
42-V-332	Guard CXFF L/H	7	13,400	18	14,000	19,585	137,096	243,300
42-V-240	Screw Feed Bin	7	17,900	46	37,000	39,242	274,693	487,400
42-E-400	Suction Cooler	7	29,400			21,015	147,103	261,000
42-V-400	Suction KO Pot	7	14,800			10,579	74,052	131,400
42-C-400	Recycle Comp	7	636,400			454,891	3,184,237	3,821,100
42-V-410	Storage Drum	7	232,300			166,045	1,162,317	2,062,400
42-SE-24	Screw Cooler	7	3,000			2,144	15,011	26,600
42-RV-1	Rotary Feeder	7	6,500			4,646	32,523	57,700
42-LV-3	Dry L/H Valve	42	37,800			37,800	1,587,600	2,817,000
42-BV-1	Block Valve	84	81,200			81,200	6,820,800	12,102,800
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	317,000
42-CV-2	Slipstream FCV	7	36,850			36,850	257,950	457,700
total mid-1990 \$							252,552,200	
42-S-300	1.8ZT Catalyst	21		1887	461,000	461,000	9,681,000	17,178,000

NOTES:

- 1) Vessel operating T < 1500degF - refractory costed @ \$800/ft3
- 2) Vessel operating T > 1500degF - refractory costed @ 0.6x(\$800/ft3)+0.4x(\$3500/ft3)
- 3) 1.8ZT catalyst costed @ \$4.45/lb and 54.91 lb/ft3

Table E-12. Case DOE7 C@ - Unit 42 (Gasification & Hot Gas Cleanup) Total Installed Costs
For Equipment Designed & Costed By Individual Items (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	4	462,300		2,436,100	2,898,400	11,593,600	20,571,700
42-E-100	RSC	4	13,570,050			13,570,050	54,280,200	96,314,800
42-V-220	Cyclone	4	212,800	1,054	843,000	1,055,800	4,223,200	7,493,600
42-V-221	Cyc Disch Bin	4	17,900	46	37,000	54,900	219,600	389,700
42-V-222	Cyclone L/H	4	17,900	46	37,000	54,900	219,600	389,700
42-F-230	Main CXFF	8				843,000	6,744,000	11,966,600
42-V-232	Main CXFF L/H	8	14,100	24	19,000	33,100	264,800	469,900
42-R-300	ZT Vessel	12	815,900	1768	1,414,000	2,229,900	26,758,800	47,480,800
42-F-330	Guard CXFF	8				843,000	6,744,000	11,966,600
42-V-332	Guard CXFF L/H	8	13,400	18	14,000	27,400	219,200	388,900
42-V-240	Screw Feed Bin	4	17,900	46	37,000	54,900	219,600	389,700
42-E-400	Suction Cooler	1	29,400			29,400	29,400	52,200
42-V-400	Suction KO Pot	1	14,800			14,800	14,800	26,300
42-C-400	Recycle Comp	4	636,400			636,400	2,545,600	3,054,700
42-V-410	Storage Drum	4	232,300			232,300	929,200	1,648,800
42-SE-24	Screw Cooler	4	3,000			3,000	12,000	21,300
42-RV-1	Rotary Feeder	4	6,500			5,500	26,000	46,100
42-LV-3	Dry L/H Valve	40	37,800			37,800	1,512,000	2,682,900
42-BV-1	Block Valve	48	81,200			81,200	3,897,600	6,915,900
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	317,000
42-CV-2	Slipstream FCV	4	36,850			36,850	147,400	261,500
total mid-1990 \$								212,848,700
42-S-300	1.8ZT Catalyst	12		3302	807,000	807,000	9,684,000	17,183,300

NOTES:

- 1) Vessel operating T < 1500degF - refractory costed @ \$800/ft3
- 2) Vessel operating T > 1500degF - refractory costed @ 0.6x(\$800/ft3)+0.4x(\$3500/ft3)
- 3) 1.8ZT catalyst costed @ \$4.45/lb and 54.91 lb/ft3

Table E-13. Case DOE7 D - Unit 42 (Gasification & Hot Gas Cleanup) Total Installed Costs
For Equipment Designed & Costed By Individual Items (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	7	325,200		2,054,200	2,379,400	16,655,800	29,554,100
42-E-100	RSC	7	8,269,430			8,269,430	57,886,010	102,712,900
42-V-220	Cyclone	7	212,800	1,054	843,000	754,673	5,282,711	9,373,600
42-V-221	Cyc Disch Bin	7	17,900	46	37,000	39,242	274,693	487,400
42-V-222	Cyclone L/H	7	17,900	46	37,000	39,242	274,693	487,400
42-F-230	Main CXFF	7				843,000	5,901,000	10,470,700
42-V-232	Main CXFF L/H	7	14,100	24	19,000	23,659	165,616	293,900
42-R-300	ZT Vessel	21	815,900	1768	1,414,000	1,593,905	33,472,015	59,392,700
42-F-330	Guard CXFF	7				843,000	5,901,000	10,470,700
42-V-332	Guard CXFF L/H	7	13,400	18	14,000	19,585	137,096	243,300
42-V-240	Screw Feed Bin	7	17,900	46	37,000	39,242	274,693	487,400
42-E-400	Suction Cooler	7	29,400			21,015	147,103	261,000
42-V-400	Suction KO Pot	7	14,800			10,579	74,052	131,400
42-C-400	Recycle Comp	7	636,400			454,891	3,184,237	3,821,100
42-V-410	Storage Drum	7	232,300			166,045	1,162,317	2,062,400
42-SE-24	Screw Cooler	7	3,000			2,144	15,011	26,600
42-RV-1	Rotary Feeder	7	6,500			4,646	32,523	57,700
42-LV-3	Dry L/H Valve	42	37,800			37,800	1,587,600	2,817,000
42-BV-1	Block Valve	84	81,200			81,200	6,820,800	12,102,800
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	317,000
42-CV-2	Slipstream FCV	7	36,850			36,850	257,950	457,700
total mid-1990 \$							246,028,800	
42-S-300	1.8ZT Catalyst	21		1887	461,000	461,000	9,681,000	17,178,000

NOTES:

- 1) Vessel operating $T < 1500\text{degF}$ - refractory costed @ $\$800/\text{ft}^3$
- 2) Vessel operating $T > 1500\text{degF}$ - refractory costed @ $0.6x(\$800/\text{ft}^3)+0.4x(\$3500/\text{ft}^3)$
- 3) 1.8ZT catalyst costed @ $\$4.45/\text{lb}$ and $54.91 \text{ lb}/\text{ft}^3$

Table E-14. Case DOE7 D@ - Unit 42 (Gasification & Hot Gas Cleanup) Total Installed Costs
For Equipment Designed & Costed By Individual Items (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	4	462,300		2,436,100	2,898,400	11,593,600	20,571,700
42-E-100	RSC	4	12,242,100			12,242,100	48,968,400	86,889,500
42-V-220	Cyclone	4	212,800	1,054	843,000	1,055,800	4,223,200	7,493,600
42-V-221	Cyc Disch Bin	4	17,900	46	37,000	54,900	219,600	389,700
42-V-222	Cyclone L/H	4	17,900	46	37,000	54,900	219,600	389,700
42-F-230	Main CXFF	8				843,000	6,744,000	11,966,600
42-V-232	Main CXFF L/H	8	14,100	24	19,000	33,100	264,800	469,900
42-R-300	ZT Vessel	12	815,900	1768	1,414,000	2,229,900	26,758,800	47,480,800
42-F-330	Guard CXFF	8				843,000	6,744,000	11,966,600
42-V-332	Guard CXFF L/H	8	13,400	18	14,000	27,400	219,200	388,900
42-V-240	Screw Feed Bin	4	17,900	46	37,000	54,900	219,600	389,700
42-E-400	Suction Cooler	1	29,400			29,400	29,400	52,200
42-V-400	Suction KO Pot	1	14,800			14,800	14,800	26,300
42-C-400	Recycle Comp	4	636,400			636,400	2,545,600	3,054,700
42-V-410	Storage Drum	4	232,300			232,300	929,200	1,648,800
42-SE-24	Screw Cooler	4	3,000			3,000	12,000	21,300
42-RV-1	Rotary Feeder	4	6,500			6,500	26,000	46,100
42-LV-3	Dry L/H Valve	40	37,800			37,800	1,512,000	2,682,900
42-BV-1	Block Valve	48	81,200			81,200	3,897,600	6,915,900
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	317,000
42-CV-2	Slipstream FCV	4	36,850			36,850	147,400	261,500
total mid-1990 \$							203,423,400	
42-S-300	1.8ZT Catalyst	12		3302	807,000	807,000	9,684,000	17,183,300

NOTES:

- 1) Vessel operating T < 1500degF - refractory costed @ \$800/ft3
- 2) Vessel operating T > 1500degF - refractory costed @ 0.6x(\$800/ft3)+0.4x(\$3500/ft3)
- 3) 1.8ZT catalyst costed @ \$4.45/lb and 54.91 lb/ft3

57,098,020	91,825,100
------------	------------

30,581,600 92,598,700

1) Sulfur storage and transfer equipment cost factored from data in EPRI Report CS-3342 vols. 2 & 3 (205.2 T/D Allied-Claus plant); includes 6 concrete lined earth pits providing 7-day storage, steam-traced double-walled transfer line, product shipping equipment, and misc. necessary equipment

-

Table E-17. Case DOE8 - Unit 42 (Gasification & Hot Gas Cleanup) Total Installed Costs
For Equipment Designed & Costed By Individual Items (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	3	468,500		2,082,200	2,550,700	7,652,100	13,082,000
42-R-200	Desulfurizer	3	160,200	744	1,399,000	1,559,200	4,677,600	7,996,800
42-V-210	Partial Quench	3	204,900	995	1,871,000	2,075,900	6,227,700	10,646,900
42-V-220	Cyclone	3	357,500	500	940,000	1,297,500	3,892,500	6,654,600
42-V-221	Cyc Disch Bin	3	136,300	393	314,000	450,300	1,350,900	2,309,500
42-V-222	Cyclone L/H	3	38,000	110	88,000	126,000	378,000	646,200
42-F-230	Main CXFF	3						4,487,500
42-V-232	Main CXFF L/H	3	43,500	132	106,000	149,500	149,500	255,600
42-E-240	ZT Bed Pre-clr	3	309,000			309,000	927,000	1,584,800
42-R-300	ZT Vessel	9	818,400	1,949	1,559,000	2,377,400	21,396,600	36,579,600
42-F-330	Guard CXFF	3						4,487,500
42-V-332	Guard CXFF L/H	3	41,300	122	98,000	139,300	417,900	714,400
42-V-223	Oxid Feed Bin	1	820,800	1,313	1,050,000	1,870,800	1,870,800	3,198,300
42-E-400	Suction Clr #1	3	591,000			591,000	1,773,000	3,031,100
42-E-401	Suction Clr #2	3	73,200			73,200	219,600	375,400
42-E-402	Suction Clr #3	3	50,500			50,500	151,500	259,000
42-E-403	Suction Clr #4	3	33,300			33,300	99,900	170,800
42-V-400	Suction KO Pot	3	132,600			132,600	397,800	680,100
42-C-400	Recycle Comp	3	1,088,400			1,088,400	3,265,200	5,582,200
42-V-410	Storage Drum	3	373,300			373,300	1,119,900	1,914,600
42-LV-3	Dry L/H Valve	21	37,800			37,800	793,800	1,357,100
42-BV-1	Block Valve	36	81,200			81,200	2,923,200	4,997,500
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	305,400

total mid-1990 \$ 111,316,900

42-S-300	1.8ZT Catalyst	9		4178	1,021,000	1,021,000	9,189,000	15,709,500
----------	----------------	---	--	------	-----------	-----------	-----------	------------

NOTES:

- 1) Vessel operating T < 1500degF - refractory costed @ \$800/ft3
- 2) Vessel operating T > 1500degF - refractory costed @ 0.6x(\$800/ft3)+0.4x(\$3500/ft3)
- 3) 1.8ZT catalyst costed @ \$4.45/lb and 54.91 lb/ft3

Table E-18. Case DOE8 -- Unit 54 (Dolomite Oxidation) Total Installed Costs
Designed & Costed By Individual Item (mid-90\$)

Item Tag#	Item Description	TOT QTY	AlloyCost 90\$/unit	Refract ft3	Refract 90\$/unit	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
54-C-100	Extr Air Comp	2	2,322,700			2,322,700	4,645,400	5,574,500
54-C-200	Vent Gas Comp	2	1,909,300			1,909,300	3,818,600	4,582,300
54-E-200	InterStage Clr	2	182,400			182,400	364,800	437,800
54-H-100	Fired Heater	2	60,400			60,400	120,800	220,200
54-E-100	Ex Air PreClr1	2	1,787,700			1,787,700	3,575,400	6,518,700
54-E-110	Ex Air PreClr2	2	299,200			299,200	598,400	1,091,000
54-E-120	Ex Air PreClr3	2	198,200			198,200	396,400	722,700
54-E-130	Ex Air PreClr4	2	310,100			310,100	620,200	1,130,700
54-RV-1	Rotary Feeder	2	160,533			160,533	321,067	585,400
54-R-100	Oxidizer	2	78,800	243	194,400	273,200	546,400	996,200
54-V-220	Cyclone	2	327,000	500	400,000	727,000	1,454,000	2,650,900
54-V-221	Cyc Disch Bin	2	64,400	213	170,400	234,800	469,600	856,200
54-V-222	Cyclone L/H	2	64,300	213	170,400	234,700	469,400	855,800
54-E-225	CXFF Precooler	2	656,700			656,700	1,313,400	2,394,600
54-F-230	CT Guard CXFF	2						3,095,600
54-V-232	CXFF L/H	2	76,300	258	206,400	282,700	565,400	1,030,800
54-V-240	Screw Feed Bin	1	52,600	564	451,200	503,800	503,800	918,500
54-RV-2	Rotary Feeder	1	160,533			160,533	160,533	292,700
54-SE-24	Screw Cooler	1				32,700	32,700	59,600
54-E-230	Air Interchngr	2	108,700			108,700	217,400	396,400
54-E-240	Return Air Clr	2	861,000			861,000	1,722,000	3,139,600
54-V-250	CXFF Blow Tank	1	18,200			18,200	18,200	33,200
54-CV-30	Waste Conveyor	1				79,600	79,600	145,100
54-V-300	Waste Silo	1	644,200			644,200	644,200	1,174,500
Total mid-90\$								7,793,900
								17,450,600

Table E-19. Case DOE9 - Unit 42 (Gasification & Hot Gas Cleanup) Total Installed Costs
Equipment Designed & Costed By Individual Item (mid-90\$)

Item Tag#	Item Description	TOT QTY	ALLOYcost 90\$/unit	Ref/Cat ft3	Ref/Cat 90\$	M.E.C. 90\$/unit	total MEC 90\$	TIC 90\$
42-R-100	Gasifier	4	632,600		2,436,100	3,068,700	12,274,800	20,985,000
42-R-200	Desulfurizer	4				0	0	0
42-V-210	Partial Quench	4						
42-V-220	Cyclone	4	88,000	419	335,000	423,000	1,692,000	2,892,600
42-V-221	Cyc Disch Bin	4	18,000	47	38,000	56,000	224,000	383,000
42-V-222	Cyclone L/H	4	18,000	47	38,000	56,000	224,000	383,000
42-F-230	Main CXFF	4				843,000	3,372,000	5,764,800
42-V-232	Main CXFF L/H	4	14,200	25	20,000	34,200	136,800	233,900
42-E-240	ZT Bed Pre-clr	4						
42-R-300	ZT Vessel	12	693,100	1808	1,446,000	2,139,100	25,669,200	43,884,100
42-F-330	Guard CXFF	4				843,000	3,372,000	5,764,800
42-V-332	Guard CXFF L/H	4	13,400	19	15,000	28,400	113,600	194,200
42-V-223	Oxid Feed Bin	4	18,000	47	38,000	56,000	224,000	383,000
42-E-400	Suction Clr #1	4	19,200			19,200	76,800	131,300
42-E-401	Suction Clr #2	4						
42-E-402	Suction Clr #3	4						
42-V-400	Suction KO Pot	4	8,760			8,760	35,040	59,900
42-C-400	Recycle Comp	4	470,200			470,200	1,880,800	3,215,400
42-V-410	Storage Drum	4	83,800			83,800	335,200	573,100
42-LV-3	Dry L/H Valve	28	37,800			37,800	1,058,400	1,809,400
42-BV-1	Block Valve	48	81,200			81,200	3,897,600	6,663,300
42-CV-1	Fuel Gas FCV	2	89,320			89,320	178,640	305,400
total mid-1990 \$								93,626,200
42-S-300	1.8ZT Catalyst	9		3548	867,000	867,000	7,803,000	13,340,000

NOTES:

- 1) Vessel operating T < 1500degF - refractory costed @ \$800/ft3
- 2) Vessel operating T > 1500degF - refractory costed @ 0.6x(\$800/ft3)+0.4x(\$3500/ft3)
- 3) 1.8ZT catalyst costed @ \$4.45/lb and 54.91 lb/ft3

Appendix F

High Temperature Cyclone Details

Figure F-1 shows the detail of the high temperature cyclone.

END

**DATE
FILMED**

4 / 16 / 93