DOE/MC/26343--3084

DE92 001270

**Horizontal Devonian Shale Well
Columbia Natural Resources, Inc.'s
Pocohontas Development Corp Well 21747
Martin County, Kentucky**

Final Report

**G. Koziar
M.M. Ahmad
L.L. Friend
M.L. Friend
E.M. Rothman
R.L. Stollar**

Work Performed Under Contract No.: DE-AC21-89MC26343

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
Columbia Gas System Service Corporation
P.O. Box 2318
Columbus, Ohio 43216-2318
and
Columbia Natural Resources, Inc.
900 Pennsylvania Avenue
Charleston, West Virginia 25302**

May 1991

Abstract

Columbia Gas and the United States Department of Energy (DOE) have successfully completed field work on a horizontally drilled Devonian shale well located in Martin County, Kentucky. The objective of this cofunded project is to assess the effectiveness and economic feasibility of applying horizontal drilling and hydraulically fracturing stimulation techniques to enhance the extraction of natural gas from the Devonian shale.

Drilling began June 1, 1990 and ended July 7, 1990. The well is comprised of three segments: a conventional vertical section, an angle build section and a horizontal section. The well reached a measured depth (MD) of 6,263 feet, 3,810 feet true vertical depth (TVD), with a horizontal displacement of 2,812 feet achieved in the desired direction of N10°W. Both air and foam were used as drilling fluids. The vertical, lateral and tangent sections were drilled using conventional rotary drilling methods. Downhole motors were used to build angle.

The Berea Sandstone served as the kickoff horizon with a kickoff point of 3,035 feet MD. The angle build section includes a tangent section 117 feet in length. A rotating Bottom Hole Assembly (BHA) designed to maintain a slight drop through the target interval, drilled the horizontal hole. However, angle continued to build to a maximum angle of 96° at 4,700 feet MD (3,649 feet TVD) before the build tendency could be reversed to drop the well through the target zone.

Mud and geophysical logs provided information for identifying discrete completion intervals. A 5½" production string equipped with five CTC Payzone™ Packers and Halliburton FO Completion Tools established six completion zones. Proceeding from the end of the well uphole, completions are as follows: an openhole slotted liner section (Zone 1); three zones (2, 3 and 4) isolated by the external packers with access to the formation through sliding sleeve completion tools; and, two cemented zones (5 and 6).

Zones 1 and 4 are unstimulated natural flow intervals. The remaining zones (2, 3, 5 and 6) were stimulated with straight nitrogen. A total combined final open flow of 3.1 MMcfd was measured from all zones.

Total well expenditures are approximately \$1,460,000. Of this amount, \$700,000 is directly related to the research and learning curve experience aspects. It is projected that the same horizontal well could be drilled with existing technology for \$700,000. If advances can be made in MWD systems for air drilling environments, wells of this type could be drilled routinely for \$500,000.

It appears that application of horizontal drilling will result in at least acceleration of gas production and possibly the addition of recoverable reserves from the Devonian shale. Production data, necessary to validate this statement, are also required to determine the economics. As we gain experience and technology advances, cost reductions will occur; this will result in economic improvement.

Table Of Contents

1.0 EXECUTIVE SUMMARY	1
2.0 INTRODUCTION	5
3.0 SITE SELECTION AND PREPARATION	6
4.0 DRILLING	8
4.1 Drilling Plan Summary	8
4.2 Drilling Operations	8
4.2.1 Vertical Section	
4.2.2 Build Section	
4.2.3 Lateral Section	
4.3 Directional Control	13
4.3.1 Electromagnetic Measurement While Drilling Tools	
4.3.2 Steering Tool	
4.4 Bottom Hole Assembly/Motor Performance	18
4.4.1 Oriented Mode Performance	
4.4.2 Rotary Mode Performance	
4.5 Drilling Problems/Difficulties	20
5.0 COMPLETION	22
5.1 Production String	22
5.2 Completion Problems	24
6.0 LOGGING OPERATIONS	26
6.1 Mud Logging	26
6.2 Open Hole Geophysical Logging	27
7.0 WELL TESTING	30
7.1 Pressure Buildup and Drawdown Test - Zone 1	30
7.2 Post-Stimulation Buildup and Drawdown Tests - Zone 2	31
7.2.1 Discussion of Zone 2 Well Test Results	
7.3 Communication Test - Zones 1 and 2	32
7.4 Open Flow Results	35
8.0 STIMULATION	38
8.1 Stimulation Rationale	38
8.2 Stimulation Treatments	38
9.0 RESULTS AND ACCOMPLISHMENTS	40
10.0 REFERENCES	41

APPENDIXES

- Appendix 1. Daily Drilling Reports - Kickoff to Total Depth**
- Appendix 2. Bottom Hole Assembly Configurations Report**
- Appendix 3. Directional Control Summary Including Drill Pipe Stresses**
- Appendix 4. Final Well Survey Record**
- Appendix 5. Bottom Hole Assembly Performance Reports**
- Appendix 6. Drilling Parameters**
- Appendix 7. Drilling Well Summary Graphs**
- Appendix 8. Drilling Completion Summary**
- Appendix 9. Inflation of External Casing Packers**
- Appendix 10. FO Completion Tool Operation**
- Appendix 11. Mud Log Show Data**
- Appendix 12. Zone 1 Well Test Analysis - Joshi Technologies International, Inc.**
- Appendix 13. Zone 1 Well Test Analysis Using Garrett Computer Systems Software**
- Appendix 14. Zone 2 Well Test Analysis Using Garrett Computing Systems Software**

List of Tables

1. Open Flow Test Results
2. Summary of Open Hole Geophysical Logging Jobs
3. Formation Tops and Bottoms
5. Post-Stimulation Well Test Results - Zone 2
6. Open Flow Test Results
7. Stimulation Summary

List of Figures

1. Horizontal Well Profile - Well 21747, Martin County, Ky
2. Completion Configuration of Well 21747
3. Regional Structure and Well Location
4. Five Years Cumulative Production Contour Map
5. Bottom Hole Assembly 1
6. Section View - Well 21747
7. Plan View - Well 21747
8. Azimuth - Well 21747
9. Inclination - Well 21747
10. Walk Rate - Well 21747
11. Build Rate - Well 21747
12. Dogley Severity - Well 21747
13. BHA 4 - DAAB Motor Position
14. Completion Configuration - Vertical Hole
15. Completion Configuration - Production Strong
16. Drilling Shows and Connection Gas
17. Pressure Temperature Response - Communication Test
18. Expanded Scale Pressure Response - Communication Test
19. Expanded Scale Pressure Temperature Response - Communication Test
20. Expanded Scale Pressure Temperature Response - Communication Test
21. Pressure Response of Zone 1 to Zone 2 Activities
22. Completion Zones with Regard to Devonian Shale Members.

List of Enclosures

1. Mud Logging Report
2. Vertical Hole Geophysical Logs
3. Free Fall Geophysical Logs
4. Drill Pipe Conveyed Geophysical Logs
5. Stimulation Data Treatment Logs - Zone 2
6. Stimulation Data Treatment Logs - Zones 3-5-6

1.0 EXECUTIVE SUMMARY

Drilling of Columbia's Pocohontas Development Corp. Well 21747 began June 1, 1990 and ended July 7, 1990. The well reached a measured depth (MD) of 6,263 feet, 3,810 feet true vertical depth (TVD). The wellbore has a final inclination of 79° with an azimuth of N10°W. Total horizontal displacement is 2,812 feet.

The Berea sandstone served as the kickoff horizon with a kickoff depth of 3,035 feet. Drilling techniques included the use of downhole motors for the angle build section while the vertical, tangent and lateral sections employed rotary methods. Total drilling time from kickoff to total depth was 119.75 hours. The rate of penetration averaged 23 ft/hr for the build section. The penetration rate averaged 35.1 ft/hr while rotary drilling the tangent and lateral sections.

Initially an electromagnetic measurement while drilling (EMWD) system provided directional control information. After this system mechanically failed, conventional steering tools furnished positional data. The well profile is shown in Figure 1. Angle builds from 0° (vertical) to a maximum of 96° before the well finally drops through the target window.

Figure 1. Horizontal well profile - well 21747, Martin County, Ky.

Thirty-three gas shows were recorded while drilling; measured gas flow exceeded 1 MMcf. Geophysical logs run in both the vertical and deviated portions of the well

consisted of the gamma ray, compensated density, sidewall neutron, temperature and dual induction. Free-fall logging operations occurred up to an angle of approximately 55°. Attempts to run a television camera to view the borehole wall for fractures failed due to severe downhole dusting conditions. Drill pipe conveyed techniques permitted logging of the lateral part of the well. The maximum logging depth reached was 6,088 feet, 175 feet short of the drillers total depth of 6,263 feet.

Figure 2 shows the mechanical configuration of the 5½" production string and identifies six completion zones. The end of the well consists of an openhole section

Figure 2. Completion configuration of well 21747.

preceded by a section of slotted liner, Zone 1. Above this are a series of five CTC Payzone™ Packers and Halliburton FO Completion Tools. Inflation of the CTC packers with water (the element is 10 feet long) provides zonal isolation for Zones 2, 3 and 4. Zones 5 and 6 are cemented.

Short term well testing established that Zones 2, 3 and 5 required stimulation. The treatments consisted of straight nitrogen without any proppant. The final open flow measured from all zones is 3.1 MMcfd. Table 1 summarizes the pre- and post-stimulation open flows for each zone and for the entire well. Because of mechanical difficulties, we were unable to close off Zone 6. As a consequence, it too was treated.

Table 1
Open Flow Test Results
Mcf/d

<u>Zone</u>	<u>Pre-Stimulation</u>	<u>Post-Stimulation</u>
1	605	605*
2	130	580
3	59	--
4	1,000	1,000
5	0	--
6	600	--
3,5,6	--	930
All Zones	--	3,100

* Not Stimulated

Operational difficulties and problems added significantly to the well cost. A few of the more major misfortunes include twisted off drill pipe and backed-off casing. Total well related expenditures are approximately \$1,460,000. Of this amount, \$700,000 directly relates to the research and learning curve experience aspects. We believe that the same horizontal well could be drilled with existing technology for \$700,000. With advances in EMWD systems for air drilling environments, routine drilling for wells of this type should approach \$500,000.

It appears that application of horizontal drilling will result in at least acceleration of gas production and possibly the addition of recoverable reserves from the Devonian shale. Production data, necessary to validate this statement, will ultimately decide the economics. Obviously, as experience grows and technology advances, costs reductions will result in economic improvement.

This well is a technical success and will likely be one of Columbia's best producing Devonian shale wells. This needs to be borne out by future well performance.

The following summarizes the project accomplishments and results achieved on horizontal Devonian shale well 21747:

- The well reached a final total measured depth of 6,263 feet with a true vertical depth of 3,867 feet. Total horizontal displacement is 2,812 feet.
- The maximum angle in the borehole is 96°. The final well inclination is 79° at an azimuth of N10°W.

- The well has six completion zones within the Devonian shale: an openhole slotted liner section; three cased but uncemented sections containing sliding sleeve completion tools isolated by external casing packers; and, two cemented zones.
- Detailed testing of Zones 1 and 2 shows a reservoir pressure of 350 to 370 psia, natural and stimulated formation skin factors of about -4.5 and a permeability of 0.05 to 0.1 md.
- Total well production from two unstimulated and four nitrogen stimulated zones is 3.1 MMcfd.
- Horizontal drilling will likely result in acceleration of gas production and possibly the addition of recoverable Devonian shale reserves.

2.0 INTRODUCTION

The Devonian shale of the Eastern U.S. is characterized as an unconventional reservoir yielding gas in very small amounts, typically between 10 and 50 thousand feet per day (Mcf/d). However, this resource contains vast quantities of natural gas estimated at upwards of 2,500 trillion cubic feet (Tcf). Depending on gas price, estimates of recoverable gas utilizing conventional technology range from only 20 to 60 Tcf -- an insignificant fraction of the gas-in-place. The ability to accelerate and improve ultimate gas recovery from this resource requires the development and application of advanced practices, one of which is horizontal drilling. Successful application of this technology to appropriate Devonian shale environments could not only have a significant economic impact, but could also contribute substantially to U.S. natural gas reserves.

The Devonian shale is naturally fractured in the test area and as a result is an ideal target for horizontal drilling. Whereas the odds of a conventionally drilled vertical well intersecting vertical natural fracture sets are quite small, a horizontal wellbore can be steered in the proper direction to maximize the number of natural fracture intersections.

To assure proper assessment of the technology applied, the well was deliberately located at an advantageous site. The geographic area chosen contains undeveloped acreage surrounded by historic production. Regional geology, reservoir quality, proximity to existing production, undeveloped acreage blocks and access to pipelines were major factors driving selection of a desirable area. Well 21747, located in the Pigeonroost Prospect in southeast Martin County, Kentucky, met the criteria for a favorable Columbia/DOE horizontal well installation site.

This report chronicles all field work and support activities associated with drilling, completing, testing and stimulating of the Columbia/DOE horizontal Devonian shale well 21747. While the primary thrust of this report is documentation, comments and conclusions are provided where appropriate.

Columbia Gas and DOE participated in this cofunded project which was designed to assess the effectiveness of applying horizontal well technology to the Devonian shale. The Columbia/DOE well is the second of three wells in a DOE supported effort entitled Horizontal Wells in The Devonian Shale. The purpose of this project is to evaluate the technical and economic feasibility of inducing hydraulic fractures from a horizontal Devonian shale well.

3.0 SITE SELECTION AND PREPARATION

A brief summary of site selection and preparation follows. Reference 1 contains details of the site selection process.

Well 21747 is located in the Pigeonroost Prospect of Martin County, Kentucky. Three basement related structural features exist near the well. Identified in Figure 3 are the Rome Trough, the Warfield Fault and Anticline, and the Pike County Uplift. These features had a significant impact on the large degree of natural fracturing occurring here.

Figure 3. Regional structure and well location

In the immediate vicinity of the site, little could be discerned in the way of structural or stratigraphic features. Because of this, proximity to a favorable production fairway and the availability of a suitable drilling location formed the basis for site selection (Figure 4).

Gas shows, temperature anomalies and production log data established a target window of 280 feet. This interval contains the bottom 100 feet of the Middle Huron and the entire Lower Huron (180 feet) members of the Devonian shale.

Figure 4. Five years cumulative production contour map

Analysis of the azimuths of induced and natural fractures from oriented core in a nearby Devonian shale well, one and five year cumulative production trends, and surface lineaments established a desired wellbore direction of N12°W. The final well azimuth is N10°W. This direction permitted the well to traverse the production fairway favorably, minimized the anticipated hydraulic fracturing breakdown and treating pressures, and augmented the number of possible intersections between the wellbore and natural fractures.

The location of Well 21747, on a tract of land comprised of over 40,000 acres, eliminated a number of potential problems. Position within the lease removed drilling concerns related to well azimuth and proximity to existing producing shale wells and lease boundaries. All adjacent acreage is under lease by Columbia and consequently, eliminated the need for outside agreements or approvals.

The location dimensions were approximately 100 feet by 200 feet. This is a typical size location for the drilling rig used. A typical Devonian shale well does not require a site of this extent; however, extra room was needed for trailers and parking because of the number of people on location while drilling. The site contained two lined mud pits; the second was available for emergency use.

4.0 DRILLING

This section provides details of all drilling activities performed on horizontal Devonian shale well 21747. Discussion topics include drilling operations, directional control, bottomhole assembly (BHA) performance, downhole motor performance, logging operations and mechanical and operational problems.

4.1 Drilling Plan Summary

Reference 2 contains the specific drilling plan developed for this well. A brief description of the well design follows. The general technical design for drilling Well No. 21747 consisted of the following elements.

- 1) Drill vertically to a kickoff point of 3,010 feet or 54 feet below the top of the Berea sandstone.
- 2) Drill the curve or angle build section at a planned build rate of $9.2^{\circ}/100$ feet to a measured depth (MD) of 3,494 feet and a projected lateral displacement of 665 feet or an inclination of 45° .
- 3) Drill a tangent section of 90 feet to 3,584 feet MD.
- 4) Continue building angle at $9.2^{\circ}/100$ feet to a total inclination of 88° .
- 5) Rotary drill the lateral section to a length of 2,000 holding the inclination at 88° .

Drilling rig requirements included maximum hook loads of 260,000 pounds with a rotary table torque of 12,000 ft-lbs. The vertical, tangent and lateral portions of the hole would use conventional rotary drilling techniques; the angle build section would employ downhole motors.

4.2 Drilling Operations

This section describes drilling operations associated with the vertical, build, and lateral sections of the horizontal well. Appendix 1 contains daily reports from the kickoff point to total depth. The drill string consisted of approximately 6,500 feet of $4\frac{1}{2}$ ", 16.60 lb/ft, grade E drill pipe and 60 feet of 6" nonmagnetic (monel) drill collars. When building angle and drilling laterally, heavy weight drill pipe provided additional weight and helped push tools to bottom. Bit weight was kept below 25,000 lbs. to avoid buckling.

Downhole motors used to drill the angle build section consisted of Eastman's Mach 1 air motor and Baker's Double Angle Adjustable Bent (DAAB) housing motor. The tangent and lateral sections employed conventional rotary drilling practices.

When drilling with downhole motors, adjustment to the bent housing angle(s) determined the rate of build. Controlling the angle while rotary drilling involved proper selection of stabilizers, reamers, etc. and appropriate positioning to obtain the desired results. Interaction between the BHA and downhole conditions determined the actual rate of build. In the lateral section, getting the desired rate of build was essentially a trial and error process.

4.2.1 Vertical Section

After moving in and rigging up the rotary rig on Well No. 21747, drilling commenced on June 1, 1990. A 24" hole drilled to 30 feet KB has 23 feet of 20" conductor casing set at 30 feet KB. After nipping up a rotating head, drilling of the 17 $\frac{3}{8}$ " surface hole proceeded to 828 feet. 13 $\frac{3}{8}$ " casing is set at 791 feet. Cement, circulated to the surface, consisted of 600 sacks Class 'A' with 2% CaCl₂ and $\frac{1}{8}$ pound of Celloflake per sack. Waiting on cement (WOC) was eight hours.

After nipping up the rotating head, drilling started on the 12 $\frac{1}{4}$ " hole. To a depth of 1870 feet, drilling fluids consisted of air, mist, and foam. However, a 7" stream of salt water encountered in the Salt Sand formation necessitated switching the circulating medium from air to brine water. We continued to drill the 12 $\frac{1}{4}$ " hole on salt water to the top of the Berea sandstone at 2972 feet MD. Geophysical logs were obtained over the intermediate hole using Halliburton Logging Services (see Section 6.2 Open Hole Geophysical Logging). 9 $\frac{5}{8}$ " casing is set at 2,954 feet KB.

Cementing of the 9 $\frac{5}{8}$ " casing required two stages to avoid breaking down the Coffee shale which lies directly above the Berea sandstone. A packer collar was placed in the 9 $\frac{5}{8}$ " casing at 2,548 feet KB. The first stage consisted of 110 sacks of Class "A" cement with 2% CaCl₂ and $\frac{1}{4}$ pound of Celloflake per sack. After an "opening bomb" opened the ports and inflated the packer collar, pumping of the second stage followed.

Stage 2 consisted of 585 sacks of Class "A" cement with 2% CaCl₂ and $\frac{1}{4}$ pound of Celloflake per sack. Circulation of gel (ahead of the cement) to the surface indicated that cement was inside the 13 $\frac{3}{8}$ " casing. WOC time was 12 hours.

We next ran an 8 $\frac{3}{4}$ " bit, blowing the hole dry as we tripped in. After drilling out the stage collar and shoe, drilling continued to 3,035 feet KB, the kickoff point.

4.2.2 Build Section

Initial attempts to kickoff the well employed bottom hole assembly (BHA) 1 shown in Figure 5. (BHA schematics and descriptions are in Appendix 2).

Figure 5. Initial bottom hole assembly used to kickoff this well.

BHA 1 consists of an 8 $\frac{3}{4}$ " bit, Eastman-Christensen's Mach I air motor with an 8 $\frac{3}{4}$ " Intrical Blade Stabilizer (IBS), 2° bent housing on bottom, and a 1° bend at the top with an 8 $\frac{3}{4}$ " IBS. Behind the Mach I motor was a compressive service monel collar, two cross-over subs and two monel collars. These collars housed GeoService's Electromagnetic Measurement While Drilling system (EMWD). Above this were a float sub and a Universal Bottom Hole Orienting Sub (UBHO). The UBHO provided a seat for a 120° tri-axis probe to back up the EMWD system in the event of its failure.

Several attempts to get BHA 1 to bottom failed. Due to the extreme bends in the adjustable motor the top IBS lodged and would not go into the 8 $\frac{3}{4}$ " hole. Removal of the top IBS solved this problem (BHA 2, Appendix 2). Drilling advanced from 3,035 feet to 3,083 feet when EMWD problems necessitated a trip out of the hole. The EMWD tool had mechanically failed so we ran the backup EMWD; in short time it too failed. The EMWD problems are covered in Section 4.3 Directional Control.

Eastman-Christensen's DOT 33, 120° tri-axis probe provided orientation information for the remainder of drilling operations. After orienting BHA 3, drilling of the 8¾" hole proceeded from 3,083 feet to 3,122 feet. At this depth inclination was about 10°. The 39 feet of hole drilled at a very slow average rate of penetration (ROP) of only 6.2 feet per hour.

During these initial operations we spent a significant amount of time trying to receive signals from the EMWD tools and changing BHA's. As a result, little drilling occurred. Since air was not circulating during these activities, small amounts of oil and water entering the wellbore from the Berea sandstone kept the hole damp. With time, drying the hole became increasingly difficult. Eventually, the hole had to be soaped before drilling could resume.

After soaping the hole, the Eastman Mach I motor still drilled at a low ROP. So, it was tripped out and BHA 4 run with Baker's Double Angle Adjustable Build (DAAB) motor. The last 20 feet of hole required reaming to get to bottom. The DAAB motor angles were 1½° for the bottom bend and 1° for the top bend.

Drilling resumed at 3,122 with the 8¾" hole drilled to 3,219 feet. This assembly however, was not building angle at the needed rate. After tripping out of hole, the bottom bend of the DAAB motor was increased to 2° and then rerun.

BHA 4 drilled from 3,219 feet to 3,470 feet in seven hours for a much improved average ROP of 35.8 feet per hour. The build angle rate ranged from 10.3° to 12.3° per 100 feet. At an inclination of 45°, rotating BHA 5 was run to drill a tangent section.

While running the rotating assembly, reaming occurred from 3,130 feet to 3,470 feet. Once on bottom, a stable foam was circulated to condition the hole. After drying the hole, drilling on air commenced. The tangent section, drilled from 3,470 feet to 3,587 feet, contains a slight angle build rate of 1.6°/100 feet.

Angle building resumed with the running of BHA 6. Drilling of the second build section, from 3,587 feet to 3,867 feet, took twelve hours. Average ROP was 23.3 feet per hour with an angle build rate ranging from 13.5° to 15.8° per 100 feet. At an inclination of 85.3° drilling ceased and the hole blown clean. Twelve joints of drill pipe had to be worked and blown out of the hole before BHA 6 could be pulled.

We prepared to drill the lateral section with a rotating BHA configured to maintain the current inclination or build angle up to 0.5°/100 feet. As BHA 7 drilled from 3,867 feet to 3,889 feet, the inclination dropped 3°. Subsequent activities established that a second hole had been drilled below the original.

We ran BHA 8 in an attempt to build angle in the second hole. Because of the extreme bend of 2° in the DAAB's housing, the BHA would not drop into hole 2, it would go freely into the original hole. We tripped the assembly out of the hole and adjusted the downhole motor bends to $\frac{1}{2}^{\circ}$ on top and $\frac{1}{4}^{\circ}$ on bottom. BHA 9 easily went into hole 2 building angle from 3,966 feet to 4,154 feet to an inclination of 87.9° . Angle build rates ranged from 6.2° to 8.5° per 100 feet.

4.2.3 Lateral Section

Rotary drilling of the $8\frac{1}{2}$ " lateral hole started with BHA 10. The use of heavy weight drill pipe assured that adequate weight existed at the drill bit. Weight on bit typically ranged between 10,000 lbs and 20,000 lbs during rotary drilling operations while averaging about 4,000 lbs while drilling with downhole motors.

Three distinct segments defined the drill string: standard drill pipe in the lateral part of the hole; heavy weight drill pipe in the angle build to vertical sections; and, standard drill pipe above the heavy weight.

The lateral section was to have been drilled by BHA's designed to hold or drop angle gradually through the target zone. BHA 10 drilled from 4,154 feet to 4,227 feet at an average build rate of $3.61^{\circ}/100$ feet. This build rate was much higher than needed.

BHA 11, designed to maintain the achieved inclination or drop slightly, continued to build angle to about 93° . The next assembly design was identical to that used on the DOE/Cabot Putnam County, West Virginia horizontal Devonian shale well. On that well, angle dropped at a rate of $0.5^{\circ}/100$ feet. On well 21747, BHA 12 drilled from 4,321 feet to 4,537 feet but continued to build angle from 93° to 95° .

Another assembly change to BHA 13 resulted in a decrease in the rate of build with the angle starting to drop slightly. BHA 13 drilled from 4,537 feet to 4,745 feet. Review of positional information during the BHA 13 run determined that a steeper drop rate was necessary to cover the target zone.

BHA 14 drilled from 4,745 feet to 5,025 feet. Angle dropped from 95.15° to 93.45° ; ROP averaged 18.7 feet per hour. This configuration provided a decline rate of $0.8^{\circ}/100$ feet.

To maintain the current angle or a slight declination, we ran BHA 15. It allowed the well to drop through our target interval. BHA 15 drilled from 5,025 feet to a total depth of 6,263 feet. TVD is 3,810 feet with a final inclination of 79° and a final azimuth of $N10^{\circ}W$.

4.3 Directional Control

Initially an electromagnetic measurement while drilling (EMWD) system from GeoServices Inc. provided directional information. The actual survey point was about 61 feet off bottom. This system provided directional information over only 35 feet of hole. Both the primary and backup EMWD tools experienced mechanical failure.

Upon reconfiguration of the BHA and incorporation of a side entry sub into the drill string, a steering tool furnished positional data during the remaining directional drilling operations. With the steering tool, the surveying point was 47 feet off bottom.

During lateral drilling operations, single shot surveys obtained approximately every 200 to 500 feet provided directional information. The infrequency of surveying during lateral drilling is a result of time consuming operations. These include pulling the drill pipe, running the survey tool and drill pipe, taking the survey, pulling the survey tool and drill pipe, and rerunning drill pipe. Upon completion of drilling, a multishot survey recorded directional data over the angle build and lateral sections of the well.

4.3.1 Electromagnetic Measurement While Drilling Tools

Reliable MWD directional surveying systems have been available for use in mud drilled wells since the 1970's. Downhole data is transmitted to the surface through the drilling mud by generating pressure pulses or continuous pressure waves. Positional information includes inclination, direction and tool face (when the drill string is not rotating).

In the Appalachian basin where our primary circulating medium is air, these systems fail. Recent research efforts have led to the development of electromagnetic transmission for use in air drilling environments. GeoServices, which has a commercial EMWD system, was invited to run their EMWD in well 21747.

BHA 1 (see Figure 5) contained this EMWD system. Its position is above Eastman-Christensen's Mach I air motor. The actual survey point is about 61 feet off bottom. Initial attempts to get BHA 1 to bottom failed until the BHA was modified (see 4.2.2 Build Section). During this time the EMWD system was in good operating order but readings were not being received since the tool was still inside the surface casing.

With a change-over to BHA 2 (Appendix 2), drilling of the build section commenced. From the initial orientation information, the EMWD system appeared to be functioning properly. Drilling proceeded only four feet when the EMWD signal was lost. Upon retrieval of BHA 2, we found a severed connection between the power pack and the directional tool.

We ran the back-up tool in the hole and initially it too appeared to be operating successfully. Over the next six hours drilling progressed 44 feet; but, during most of this time we received no EMWD signal. Upon retrieving the tool, we found that the backup tool failed in the connection between the transmitter and the probe.

The EMWD's transmitting system appeared to have been functioning during drilling operations. But the physical construction of the system was not capable of handling the severe downhole conditions of air drilling (large air velocities, vibrations, etc.).

EMWD holds promise for use in air drilling. However, additional tool hardening is necessary for use in the harsh air environment to take advantage of the benefits of EMWD.

4.3.2 Steering Tool

Eastman-Christensen provided the steering tools for this project. Directional Orientation Tool (DOT) 33 tri-axis probe (0-120°) provided continuous real time measurements of hole inclination, direction and tool face while drilling with a downhole motor. With this steering tool, the surveying point was 47 feet off bottom. Three tools were on location with a fourth brought in as a standby after the first two probes failed. Figures 6 through 12 show various views and parameters associated with the well. Appendix 3 contains survey information obtained during drilling operations; it also contains drill pipe stress calculations.

Figure 6. Sectional View of Well 21747.

Figure 7. Plan View of Well 21747.

Figure 8. Azimuth of well 21747.

Figure 9. Inclination of well 21747.

Figure 10. Walk rate of well 21747.

Figure 11. Build rate of well 21747.

Figure 12. Dogleg severity of well 21747.

The first probe, number 1-015, functioned for 65 hours when it began giving inconsistent readings. Replacement probe number 1-240 worked for about 24 hours. The last probe run, number 1-248, operated the final eight hours of curve building.

Inspection of each tool identified a common cause of failure in all three probes - erosion of the contact pin between the probe and the wet connect. The contact pin has since been redesigned to control this problem and to increase the mean time between failures (MTBF).

Eastman's magnetic Mini Multi-shot (MMS) provided a final survey of the entire well at the conclusion of drilling operations. Appendix 4 contains this information.

4.4 Bottom Hole Assembly/Motor Performance

Bottom hole assembly configurations consisted of two types: one containing a downhole motor to drill the build section in an oriented mode; and the other to drill the lateral section in a rotary mode. Appendixes 5, 6, 7 and 8 contain BHA performance reports, drilling parameters, well summary graphs and a drilling completion summary. This section discusses the performance of each mode of operation.

4.4.1 Oriented Mode Performance

The first motor used to build angle was Eastman-Christensen's Mach I air motor, a positive displacement motor that develops high torque at the bit at low speeds. The Mach I motor drilled 39 feet with a ROP of 6.2 feet per hour. The motor began to fatigue after an accumulative operational time of 19.75 hours. Baker's Double Angle Adjustable Build motor (DAAB) replaced the Mach I.

The DAAB motor drilled both the upper and lower build sections. Figure 13 shows the position of the motor within BHA 4. This motor drilled from 3,122

Figure 13. Position of downhole motor in the BHA.

feet KB to 3,470 feet KB (348 feet) in 12.5 hours for a ROP of 24.7 feet per hour. The build rate ranged from about 8° to 12.3° per 100 feet. After rotary drilling a tangent section from 3,470 feet to 3,587 feet with BHA 5, BHA 6 - with the same configuration as BHA 4 - drilled the lower build section of the well. The DAAB motor drilled from 3,587 feet to 3,867 feet (280 feet) in 9.5 hours for an average ROP of 29.5 feet per hour. Build rates ranged from 11.7° to 15.8° per 100 feet.

The DAAB motor accumulated 22 hours drilling and 0.5 hour circulating time in drilling both build sections. SAE-30 weight motor oil provided the only means of lubrication for the motor. Approximately one gallon was poured inside the drill pipe at each connection, every 30 feet.

While reaming to bottom with BHA 7 to rotary drill the lateral section, departure from the original wellbore occurred. The DAAB motor was rerun to build the angle up in the second hole. But, motor fatigue required running the backup DAAB motor.

BHA 9 containing the backup DAAB motor drilled from 3,966 feet to 4,154 feet (188 feet) in six hours for a ROP of 31.3 feet per hour. Build rates ranged from 6.2 to 8.5 degrees per 100 feet. Upon completion of the build section a rotating assembly drilled the lateral section.

The Baker DAAB motor performed quite well in the air environment as the build section drilling statistics indicate. Eastman's Mach I motor did not perform as expected. However, other factors may have contributed to its unimpressive performance. These include nineteen hours spent circulating off bottom, working on the EMWD, cleaning the hole, and trying to get BHA 1 to bottom. Operation under these conditions could have had a detrimental effect on motor life and its performance. Use under more normal operating conditions is necessary to assess the Mach I air motor.

4.4.2 Rotary Mode Performance

Rotary drilling techniques were used in the tangent and lateral portions of the well. Penetration rates were good. ROP for 117 feet of tangent section was 33.4 feet per hour. ROP for 2,107 feet of lateral section was 28.9 feet per hour. The greatest problem encountered in this part of the hole was reversing the tendency of the well to build angle (see section 4.2.3 Lateral Section).

BHA's that have proven to hold or drop angle slightly, continued to build while operating in the rotating mode in this well. While definitive proof is lacking, one theory is that there may be a certain amount of "follow-through" as the drill bit cuts new hole out of the build section. The build section influences the trajectory of the end of the drill string for some finite distance. The hole in effect continues to build angle but at a decreasing rate. Eventually the hole straightens or angle drops. Curved sections with larger build rates will likely produce a more pronounced follow-through.

4.5 Drilling Problems/Difficulties

While drilling the vertical part of the well a 7" stream of salt water began flowing from the Salt Sand. This necessitated drilling with salt water to the intermediate hole casing point 2,954 feet MD. Combined with the larger than normal intermediate hole size of 12¼", drilling progressed quite slowly. We had originally anticipated 6 days to reach the kickoff point. In actuality, 14 days were needed.

At a depth of 4,703 feet MD the drill pipe twisted off. This apparently occurred when tripping the drill string to run a directional survey. The fish left in the hole consisted of 74 feet BHA, 1,054 drill pipe, and 30 feet heavy weight drill pipe.

Failure occurred in the tool joint of the first joint of heavy weight drill pipe (between the first and second joints of heavy weight). Successful recovery of the fish occurred on the first attempt.

5.0 COMPLETION

Figure 14 shows a schematic of horizontal well 21747. 20" conductor casing is set in a 24" hole at 30 feet KB. Surface casing consists of 13 $\frac{3}{8}$ ", 54.5 lbs per foot, K-55 pipe set at 791 feet KB in a 17 $\frac{1}{2}$ " hole drilled to 828 feet KB. The intermediate string is 9 $\frac{5}{8}$ ", 36 lbs per foot, K-55 casing set at 2,954 feet KB in a 12 $\frac{1}{4}$ " hole. This is followed by an 8 $\frac{3}{4}$ " hole drilled to 3,035 feet KB, the kickoff point. Discussion of the production string follows.

Figure 14. Completion configuration of the vertical part of well 21747.

5.1 Production String

To accommodate downhole tools associated with various completion and testing procedures we ran a 5 $\frac{1}{2}$ " production string. Mud and geophysical log information established six discrete completion zones. Production potential and the need for stimulation were among the considerations in choosing these zones. This information, caliper log data and review of offset well logs determined placement positions for downhole hardware. The well contains three types of completions: open hole/slotted casing, external casing packer (ECP) and sliding sleeve, and cemented pipe. Figure 15 shows the completion in detail.

Figure 15. Production string completion configuration.

To reduce drag while running the casing in the open hole, we used 100 bow type centralizers with one placed over each coupling. We used ten rigid centralizers to minimize damage to the ECP's while running through the build section. Each ECP had one rigid centralizer in front and one behind.

Zone 1, at the end of the well, is 725 feet in length and consists of open hole with slotted casing. Columbia's experience with open hole completions is that the shale has a tendency to cave-in over time. Zone 1 has 250 feet of open hole preceded by 475 feet slotted casing.

Zones 2, 3, 4, and 5 were to have been isolated with ECP's with each zone containing a Full Open (FO) sliding sleeve assembly. This would permit zonal isolation for selective treatment, testing, and evaluation.

A Hydraulically Operated Stage (HOS) cementer is directly above ECP 5. Original plans called for inflating ECP 5, with cement, opening the HOS cementer and cementing the production string above ECP 5 and drilling out the closing mechanism of the HOS cementer. Then we were to isolate the individual zones by inflating the ECP's with cement. These plans were changed as discussed in the following section.

5.2 Completion Problems

During completion operations, a variety of problems developed. The difficulties encountered include:

- 5½" casing could not be run to TD
- Failure of ECP 5
- Separated casing
- Lost logging tools
- Operation of the opening tool for the FO Stimulation tool.

Although the well's measured length is 6,263 feet, only 6,013 feet of production casing could be run. This shortage of 250 feet is the result of not having enough weight to slide the casing to TD. Analysis of drag (using a Torque and Drag model) indicated that the string could not slide past a depth of 6,000 feet without additional weight. (One way of doing this is to set a bridge plug in the vertical section and filling the casing with a fluid. We did not attempt this.)

In an attempt to inflate the top ECP, we spotted cement across the packer then increased pressure to inflate the ECP. But, the packer would not inflate. Apparently damage to the packer element occurred while running the casing in the hole. Because of this problem the original completion plan changed. (Appendix 9 contains details of the procedures used to inflate the ECP's). We now had to isolate both Zones 5 and 6 by cementing through the FO tool in Zone 6. This required preparation of the HOS cementer for drilling out.

An opening "bomb" opened the HOS cementer ports. Pumped immediately behind this were a closing "bomb" and wiper plug. This closed the ports. We drilled out the plugs using 2⅞" drill pipe with a bladed junk mill.

We next ran open-ended drill pipe to spot a cement plug across ECP 5 to seal its ports. After setting the cement plug and blowing the hole dry, gas was still present in the casing. (It was present before because of the openhole section). This indicated that there was a leak somewhere above the cement plug.

A temperature log and casing collar locator (CCL) identified gas entry although at different depths. While logging down, a temperature anomaly occurred at 3,380 feet; the CCL indicated pipe separation at 3,388 feet. As we tried to come out of the hole, the logging wireline parted leaving the temperature and CCL tools in the well.

A TV camera log indicated that the separated pipe had unscrewed at 3,388 feet. Because a centralizer lodged between the coupling and pin, the casing would not screw back together. After pulling 3,388 feet of casing, we attached an external casing patch to the bottom of the pipe. We ran 3,390 feet of 5½" casing, set down on top of the pipe in the hole, rotated, and picked up 34,000 pounds over string weight. The casing was successfully reconnected as gas flow ceased. A casing test held 3,500 psig with no leakage. Using fishing tools we then retrieved the logging tools.

We set a bridge plug at the top of the slotted casing and successfully inflated ECP's 1, 2, 3 and 4 with water using a Halliburton Retrievable Testing Treating Squeeze (RTTS) packer. This isolated Zones 1, 2, 3, and 4. After opening the FO tool in Zone 5, the annulus was cemented with 230 sacks Class "A" cement followed by 10 bbls Flo Check.

The FO Stimulation Tool gave us some problems during completion procedures. The opening and closing tool was to have a positive seat, both in the open and closed positions. However, this happened only after tool redesign and an addition of harder metal to the tool shoulders. Another problem occurred when blowing the dry shale well to atmosphere. Shale fines would buildup and settle in the recess of this tool. This necessitated clean out using acid or nitrogen before the tool could be operated.

6.0 LOGGING OPERATIONS

A mud logger was on location during directional drilling operations. Geophysical logging occurred in both the vertical and deviated portions of the well using free-fall and drill pipe conveyed logging methods.

6.1 Mud Logging

Keystone Mudlogging provided mud logging services for well 21747. Keystone's mud log includes a total gas curve, chromatographic (C_1 through C_5) analysis, sample description, drilling rate, percent lithology and sample fluorescence (Enclosure 1). Keystone also provided a washed and dried set of samples from the well. The mud logging unit began operating on June 14, 1990 and completed its services on July 7, 1990.

Appendix 11 contains show and connection gas data for the well. The shows represent increase above background gas. Figure 16 graphically depicts the thirty-three gas shows and connection gas recorded from the Cleveland shale through the Lower Huron shale.

Figure 16. Drilling shows and connection gas.

The graph indicates that gas shows occurred in all shale members. The largest increases appeared in the Three Lick bed (3,265 feet, 401 units), the Middle Huron (3,768 feet, 195 units; 4,870 feet, 200 units; and 4,876 feet, 400

units) and the Lower Huron (4,102 feet, 340 units). The Middle and Lower Huron sections contained largest connection gas shows.

6.2 Open Hole Geophysical Logging

Three runs were necessary to provide geophysical logging coverage of the vertical, build and lateral sections. A summary of the logging runs is shown in Table 2. Geophysical logs are contained in enclosures 2, 3 and 4. Free-fall logging of the build section occurred up to an angle of approximately 55°. Due to unavailability of drill pipe conveyed logging tools, Halliburton Logging Services was unable perform the final logging job; Schlumberger Well Services did the work.

Table 2

Summary of Open Hole
Geophysical Logging Jobs
Well 21747
Martin County, KY

<u>Log Run</u>	<u>Service Company</u>	<u>Date</u>	<u>Logs Run</u>	<u>Logging Interval, (Feet)</u>
1 Intermediate Vertical Hole	Halliburton Logging Service	6-13-90	Gamma-ray, Compensated Density, Epithermal Neutron, Dual Laterlog	787-2,964
2 Free Fall (Build Section)	Halliburton Logging Service	7-8-90	Gamma-ray, Compensated Density, Temperature, Dual Induction	2,951-3,686
3 Drill Pipe Conveyed	Schlumberger Well Service	7-11-90	Gamma-ray, Temperature	3,300-6,088

Table 3 contains a summary of the formation tops and bottoms. The borehole penetrated the Lower Huron shale at 4,044 feet; it went back into the Middle Huron shale at 4,542 feet where the well inclination exceeded 90°. At 5,250 feet, the wellbore penetrated the Lower Huron a second time when the well inclination dropped below 90°.

Both the pipe tally and Schlumberger's wireline odometer provided depth control during the drill pipe conveyed logging run. All measurements took place while pulling the tools out of the hole.

Table 3

**Formation Tops & Bottoms
Well 21747
Martin County, KY**

<u>Formation</u>	<u>Depth</u>
Maxon Sandstone	2,082-2,125
Big Lime	2,174-2,436
Injun Sandstone	2,436-2,464
Berea Sandstone	2,966-3,062
Cleveland Shale	3,062-3,183
Three Lick Bed	3,183-3,316
Upper Huron Shale	3,316-3,414
Middle Huron Shale	3,414-4,044
Lower Huron Shale	4,044-4,542
Middle Huron Shale	4,542-5,250
Lower Huron Shale	5,250-LTD (6,088)

The borehole temperature increased slightly from 3,300 feet to 3,590 feet. From 3,590 feet to 4,150 feet the temperature remains constant. Beyond this depth, the borehole temperature decreases until a depth of 5,660 feet. This indicates gas entry.

The cooling trend begins in the top of the Lower Huron with a large gas entry recorded at 4,895 feet. Below 5,660 feet, the borehole temperature increases to 5,816 feet where gas entry is noted. The maximum temperature recorded in the well was 94.0° F.

The caliper log shows that the hole size varies from 9½" to slightly over 11" from 3,300 feet to 3,820 feet. A large washout exists from 3,820 feet to 3,840 feet. Between 3,840 feet and 4,900 feet, the borehole ranges from 9" to 10". Beyond 4,900 feet, the hole size remains below 9" to the logger's total depth.

The gamma-ray, photoelectric and density values recorded over the lateral section correspond to log values obtained in surrounding vertical wells. Of course, these values are stretched over a much larger distance since the well is contained within the target rather than drilled through it.

The logging tools could only be pushed to 6,088 feet, due to the large amount of drag encountered. As a result, logging of the bottom 175 feet was not possible.

7.0 WELL TESTING

Well tests conducted in the various completion zones consisted of six short term shut-in pressure and open flow tests, one long term pre-stimulation test, one long term post stimulation test, and a zone isolation/communication test.

The pre-stimulation flow (drawdown) test immediately identified the need for stimulation of zones 2, 3 and 5. Post-stimulation open flows indicate the relative improvement resulting from treatment. Analysis of long term pre-stimulation drawdown and buildup data established the native reservoir properties of Zone 1. Detailed post-stimulation testing provided Zone 2 reservoir property data. The zone isolation test was an attempt to determine if communication exists between adjoining zones 1 and 2. Although it would have been desirable to gather detailed test information for each zone along the entire length of the lateral, time and cost constraints prevented this.

7.1 Pressure Buildup and Drawdown Test - Zone 1

Test results were analyzed using both horizontal well analytical techniques and conventional well test analyses. Joshi Technologies, Inc. provided the former analyses while Columbia conducted the latter. Test results are very similar using either approach (Table 4).

Table 4

Well Test Results - Zone 1

Analysis Method	<u>Conventional</u>		<u>Horizontal</u>	
	<u>Buildup</u>	<u>Drawdown</u>	<u>Buildup</u>	<u>Drawdown</u>
Permeability, md	0.076	0.089	0.045	0.045
Skin Factor	-4.6	-4.6	-4.5	-4.3

Pre-stimulation drawdown and buildup tests conducted on Zone 1, the open hole/slotted liner section, identified natural (unstimulated) reservoir properties. The drawdown test, conducted through a critical flow prover using a 3/16" orifice, established an initial reservoir pressure of 350 psia. After 168 hours, the final stabilized flow rate was 200 Mcf/d with a flowing bottomhole pressure of 288 psia. Zone 1 is entirely contained within the Lower Huron member of the shale with a measured length of 725 feet.

Using a downhole pressure gauge set at 3,580 feet MD (3,505 feet TVD), the buildup test final pressure was 348.4 psia at 423 hours. Results show a large negative

skin factor of about -4.5 and an effective permeability of about 0.05 md for both buildup and drawdown tests. Analysis of test data deemed stimulation of Zone 1 as unnecessary.

Table 4 summarizes the test results using conventional and horizontal analytical methods. Appendixes 12 and 13 contain detailed analyses of the buildup and drawdown tests.

7.2 Post-Stimulation Buildup and Drawdown Tests - Zone 2

A short term open flow test conducted on Zone 2 recorded a gas rate of only 103 Mcfd. This indicated that stimulation was necessary. Since a lengthy time period would have been necessary to conduct long term pre-stimulation testing, initial reservoir conditions of Zone 2 are unknown. After nitrogen stimulation, we conducted long term buildup and drawdown tests.

Because of the similarity of the Zone 1 test results using both horizontal and conventional analyses, as well as cost constraints, we used only the conventional analytical methods to evaluate of Zone 2 test data. However, without benefit of a long term pre-stimulation well test, interpretation of the post-stimulation test results may not be entirely accurate. Interpretation is further complicated by the fact that this completion zone is exposed to both the Middle and Lower Huron shale members. Zone 2 has a length of 432 feet. Of this length, 67% is contained within the Lower Huron section and the remaining 33% is within the Middle Huron (proceeding "uphole" from the back of the well).

Table 5
Post-Stimulation
Well Test Results - Zone 2

Analysis Method	<u>MDH</u>		<u>Dual Porosity</u>	
	<u>Buildup</u>	<u>Drawdown</u>	<u>Buildup</u>	<u>Drawdown</u>
Permeability, md		0.852	0.106	0.595
Skin Factor		0.7	-4.8	-1.3

7.2.1 Discussion of Zone 2 Well Test Results

Type curve matching of pressure buildup and drawdown test data resulted in calculated permeability of 0.85 md with slightly positive skin factors. Based on these matches, an impermeable boundary exists 146 feet from the wellbore. This conforms to a hot shale streak near the top of the Middle Huron which could act

as an impermeable barrier or the upper extent of naturally occurring vertical fractures within the Middle Huron.

The above results are significantly different from anticipated results for conventional tests in vertical Devonian shale wells. Typically, reservoir permeability is less than 0.1 md with the skin factor ranging from -5 to -2. One explanation for these differences may be that Zone 2 is in communication with a fracture network and that the permeability is indeed higher than seen in conventional tests. Positive skin may result from either the flow regime present or may be surfacing due to communication around CTC #2.

If Zone 2 is connected with adjacent zones, a likely possibility, the height (length in this case) would increase significantly. Evidence of communication either through the formation or around the external casing packers exists. In the communication test (discussed in the following section) Zone 1 pressure responds to Zone 2 activities. It also appears that communication with Zone 3 exists. Gas analysis identified high nitrogen concentrations in Zone 3. The high nitrogen concentrations are a direct result of gas migration from Zone 2 which was nitrogen stimulated. As a result of the increased length, of some unknown extent, permeability is actually lower (due to the relationship between permeability and height in the transmissibility equation).

Although both type curve and straight line analysis provided suitable matches, the calculated results varied. Analysis assuming dual porosity behavior indicated a permeability of 0.5483 md from the drawdown test and 0.218 md from the buildup test. Respective skin factors are -1.594 and -3.883. When further refined, these values become 0.5948 md with a skin of -1.33 for drawdown and 0.1055 md with a skin of -4.82 for buildup. These results are more in line with typical Devonian shale results for vertical wells and with that of unstimulated Zone 1.

7.3 Communication Test - Zones 1 and 2

At the conclusion of Zone 1 testing, we set a bridge plug just above the slotted casing to isolate Zones 1 and 2. A pressure bomb attached to the bottom of the bridge plug recorded Zone 1 pressures and temperatures for 788 hours. The isolated pressure bomb did respond to events occurring in Zone 2 suggesting some sort of communication. However, a determination of the exact path of communication is open to debate.

Figure 17 shows the pressure and temperature response over the entire isolation period of 788 hours. Pressure perturbations seen here are more readily observed on expanded views shown in Figures 18 through 20. It is apparent that the Zone 1 pressure responds to every event which occurred in Zone 2. Each activity occurring in Zone 2 is labeled on the Zone 1 pressure response curve.

Figure 17. Zone 1 pressure and temperature response to events in zone 2.

Figure 18. Zone 1 pressure response to events in zone 2.

Figure 19. Zone 1 pressure and temperature response to events in zone 2.

Figure 20. Zone 1 pressure and temperature response to events in zone 2.

Figure 21 directly compares the Zone 1 response to the post-stimulation pressure buildup and drawdown tests conducted in Zone 2. Again the pressures recorded in Zone

Figure 21. Pressure response to events in zone 2.

1 clearly react to events in Zone 2. While communication could exist around the ECP, communication through the formation is virtually certain as there are no known vertical barriers that would prevent the lateral migration of gas through the reservoir.

7.4 Open Flow Results

Table 6 summarizes pre- and post-stimulation open flow measurements for the six completion zones and for the entire well. Zones 1 and 4 are natural completions. Low open flow measurements in Zones 2, 3 and 5 established the need for stimulation. Zone 2 was fractured alone. Because of cost and time constraints Zones 3, 5, and 6 were treated simultaneously. (Mechanical difficulties prevented closing FO tool in Zone 6, so it too was treated).

Table 6

Open Flow Test Results
Mcf/d

<u>Zone</u>	<u>Pre-stimulation</u>	<u>Post-Stimulation</u>
1	605	605*
2	130	580
3	59	--
4	1,000	1,000
5	0	--
6	600	--
3,5,6	--	930
All Zones	--	3,100

*Not Stimulated

Based on open flow data, the stimulation of Zone 2 was effective. However, a judgement of the effectiveness of the simultaneous treatment of Zones 3, 5 and 6 is more difficult. This assessment is complicated by treatment of multiple zones contained within multiple shale horizons, completed in different fashions and located in different parts of the well profile. This is shown in Figure 22.

Figure 22. Completion zones with regard to Devonian shale members.

Zone 3 is comprised of the Middle Huron and is isolated from adjacent zones by ECP's. It is in the lateral part of the well. Zone 5, which is cemented, encompasses the Lower Huron (in the lower 20% of the zone) and the Middle Huron. This zone resides in the angle build portion of the well. Zone 6, which is also cemented, covers the Middle and Upper Huron, Three Lick and Cleveland shale members. Zone 6 ranges from the near vertical to low angle build sections of the hole.

Since the three zones had a commingled post-stimulation flow measurement the contribution of each zone is uncertain. However, the small open flow increase from 659 Mcfd to 930 Mcfd suggests that the stimulation was not effective in treating all three zones. It is likely that the treatment was pumped into either Zones 3 or 6 or into both of them while Zone 5 received no stimulation.

Based on pre-stimulation open flows, Zone 6 is best followed by a distant Zone 3. Assuming other reservoir conditions are constant or similar, this implies that Zone 6 has greatest permeability or the least skin damage. Zone 5, with zero flow, is either not actually open to the borehole or has severe damage. Given this situation, Zone 6 would more easily accept the nitrogen treatment than the other zones. Further, assuming that the downhole treating pressure does not buildup to exceed the breakdown pressure of Zone 3, it will go untreated.

Total final open flow from all zones commingled is 3.1 MMcfd. This compares to an average IOF of 747 Mcfd for immediate offset vertical wells. (This number includes two vertical wells with IOF's exceeding 5 and 6 MMcfd). The average IOF of all new shale wells within a 2 mile radius is 300 Mcfd. From an IOF standpoint, horizontal Devonian shale well 21747 is a success.

8.0 STIMULATION

Based upon the project objective, production string mechanical configuration, and stimulation and performance data (IOF) from offset wells, nitrogen emerged as the preferred hydraulic fracturing medium.

8.1 Stimulation Rationale

The basis for preferring nitrogen fracturing in this locale lies in both the nature of the reservoir and current stimulation practices. First, the reservoir contains a high degree of natural fracturing because of three basement related features (see Figure 3). Columbia feels that stimulation here is little more than cleanup of drilling induced formation damage. Treatment with nitrogen can easily establish communication between the wellbore and natural fracture system.

Second, the low reservoir pressure (150-350 psi) and high capillary forces combine to make post-stimulation cleanup of the liquid phase of a stimulation a very long process. Foam fracturing typically requires 10 to 20 days to cleanup with a service rig on site all that time.

Third, the near exclusive use of nitrogen to treat over 40 offset vertical Devonian shale wells permits direct production comparison. Since all wells will be placed on production about the same time, the horizontal and vertical wells will be effectively producing under the same set of reservoir conditions (if local depletion of natural fracture sets is not significant).

8.2 Stimulation Treatments

Short term tests determined the need for stimulating zones 2, 3 and 5. Zone 2 was treated alone while Zones 3, 5 and 6 (because of mechanical problems we were unable to close FO tool in Zone 6) were simultaneously stimulated. Table 7 summarizes treatment parameters for each job. Enclosure 5 contains the treatment data logs.

Table 7

Stimulation Summary

<u>Parameter</u>	<u>Zone 2</u>	<u>Zones 3, 5 & 6</u>
Job Size, scf	1,510,336	3,303,000
Average Rate, scf/min	98,184	144,787
Breakdown Pressure, psi	2,554	---
Average Treating Pressure, psi	2,569	3,456
Initial Shut-in Pressure, psi	1,311	1,341

The higher treating pressure for Zones 3, 5 and 6 are a result of the very high nitrogen rates. A breakdown pressure is not shown for these zones as it is not distinguishable on the pressure record. This is probably a result of the treatment entering the good Zones 6 and 3 (see Section 7.3 Open Flow Results for discussion of this possibility).

As previously stated, the total flow rate from the well was 3.1 MMcfd. This is a very good flow rate for a Devonian shale producer. A determination of the effectiveness of straight nitrogen as a viable fracturing medium for the Devonian shale will occur as long-term production data become available.

9.0 RESULTS AND ACCOMPLISHMENTS

It appears that application of horizontal drilling will result in at least acceleration of gas production and possibly the addition of recoverable reserves from the Devonian shale. Production data, necessary to validate this statement, will ultimately decide the economics. Obviously, as experience grows and technology advances, cost reductions will result in economic improvement.

The following list highlights the project accomplishments and results achieved on horizontal Devonian shale well 21747:

- The well reached a final total measured depth of 6,263 feet with a true vertical depth of 3,810 feet. Total horizontal displacement is 2,812 feet.
- The maximum angle in the borehole is 96°. The final well inclination is 79° at an azimuth of N10°W.
- The well has six completion zones within the Devonian shale: an openhole-slotted liner section; three cased but uncemented sections containing sliding sleeve completion tools isolated by external casing packers; and, two cemented zones.
- Detailed testing of Zones 1 and 2 shows a reservoir pressure of 350 to 370 psia, natural and stimulated formation skin factors of about -4.5 and a permeability of 0.05 to 0.1 md.
- Total well production from two unstimulated and four nitrogen stimulated zones is 3.1 MMcfd.
- Horizontal drilling will likely result in acceleration of gas production and possibly the addition of recoverable Devonian shale reserves.

10.0 REFERENCES

1. Koziar, G., et al. June 1990. *Devonian Shale Horizontal Well Site Selection*, Topical Report. DOE Contract No. DE-AC21-89MC26343
2. Columbia Gas System Service Corporation; Columbia Natural Resources , Inc.; May 15, 1990. *Drilling Plan - Horizontal Devonian Shale Well # 21747, Common District, Martin County, Kentucky*. DOE Contract NO. DE-AC21-89MC26343

Appendix 1

Daily Drilling Reports

DAILY DRILLING REPORT

DDR No. 1 Date 14 JUN 90 Job No. 211-00001

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today

Depth 3035 m Footage Last 24 Hrs. m Last CSG: Depth Set 2955 m Size 9 7/8 in

MUD DATA

Mud Type	AIR	Wt.	(ppg)	Vis.	PV	YP	WL
Gels	/	% Oil		% Solids	% Sand	pH	Chl.

BIT DATA

[illegible]

MOTOR DATA

[illegible]

PUMP DATA

FORMATION DATA

[illegible]

TIME BREAKDOWN

REMARKS:

[illegible]

3-800 CFM COMPRESSORS 1800 CFM MAX.

MOBILIZATION/DEMObILIZATION CHARGE \$4000

STANDBY DAY RATE \$2000

Company Representative	GRIESEMOR/WALKER
	EC Representative

EC Daily Cost (US\$) 6000

EC Total Cost	(US\$)	6000
---------------	--------	------

Page 1 of 1

DAILY DRILLING REPORT

DDR No. 2 Date 15-JUN-90 Job No. 211-00001

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

.ocation COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 1

Depth	3035 m	Footage Last 24 Hrs.	0 m	Last CSG: Depth Set	2955 m	Size	9 7/8 (in)
-------	--------	----------------------	-----	---------------------	--------	------	------------

MUD DATA

Mud Type	AIR	Wt.	(ppg)	Vis.	PV	YP	WL
Gels	/	% Oil		% Solids	% Sand	pH	Chl.

BIT DATA

[illegible]

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. Δ P (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (m)	Depth Out (m)
1	6 3/4	EC-STEERABLE ANGLE BLD		920604			0.00	0.00	0.00	0.00	3035	

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (gal)

FORMATION DATA

Formation Name	Top (MD) (m)	Lithology #1	L1 %	Lithology #2
		SANDSTONE		

TIME BREAKDOWN

[illegible]

REMARKS:

MOTOR WOULD STALL JUST BELOW CASING AT 2865 DUE
TO STATOR/ROTOR FLEX DECISION WAS MADE TO
TRIP OUT AND LAY DOWN TOP STABILIZER

GRIESEMORWALKER

Company Representative**EC Representative**

EC Daily Cost (US\$) 10000

EC Total Cost	(\$US)	16000
---------------	--------	-------

Page 1 of 1

DAILY DRILLING REPORT

DDR No. 3 Date 16-JUN-90 Job No. 211-00001

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 1;2

Depth 3035 m Footage Last 24 Hrs. 0 m Last CSG: Depth Set 2955 m Size 9 7/8 (in)

MUD DATA

Mud Type	AIR	Wt.	(ppg)	Vis.	PV	YP	WL
Gels	/	% Oil		% Solids	% Sand	pH	Chl.

BIT DATA

[illegible]

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. ΔP (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In ft	Depth Out ft
1	6 3/4	EC-STEERABLE ANGLE BLD		920604			0.00	0.00	0.00	0.00	3035	3035
2	6 3/4	EC-STEERABLE ANGLE BLD		920604			0.00	0.00	0.00	0.00	3035	

PUMP DATA

FORMATION DATA

[illegible]

TIME BREAKDOWN

[illegible]

REMARKS:

REMOVED TOP STABILIZER ON AD-AS MOTOR 4-1/2 IF
ON TOP OF STABILIZER AND 4-1/2 REG PIN ON
BOTTOM HAD NO SUB TO REPLACE STABILIZER
ORDERED ONE AT 3AM TO BE DELIVERED FROM TRI-STATE

Company Representative	GRIESEMOR/WALKER EC Representative
------------------------	---------------------------------------

EC Daily Cost (US\$) 10000

EC Total Cost	(\$US)	26000
---------------	--------	-------

Page 1 of 1

DAILY DRILLING REPORT

DDR No. 4 Date 17-JUN-90 Job No. 211-00001

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 2:3

Depth 3083 m Footage Last 24 Hrs. 48 m Last CSG: Depth Set 2955 m Size 9 7/8 (in)

Footage Last 24 Hrs. 48 m

Last CSG: Depth Set

2955 100

Size 9 7/8 (in)

MUD DATA

Mud Type	AIR	Wt.	(ppg)	Vis.	PV	YP	WL
Gels	/	% Oil		% Solids	% Sand	pH	Chl.

BIT DATA

[illegible]

MOTOR DATA

Run No.	Size (in)	Mtr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nd)	Avg. ΔP (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (ft)	Depth Out (ft)
2	6 3/4	EC-STEERABLE ANGLE BLD		920604			5.00	5.00	7.25	7.25	3035	3083
	6 3/4	EC-STEERABLE ANGLE BLD		920604			0.00	0.00	0.00	0.00	3083	

PUMP DATA

FORMATION DATA

[illegible]

TIME BREAKDOWN

REMARKS:

[illegible]

Company Representative	GRIESEMOR/WALKER
	EC Representative

EC Daily Cost	(\$US)	10000
---------------	--------	-------

EC Total Cost	(RUS)	36000
---------------	-------	-------

Page 1 of 1

DAILY DRILLING REPORT

DDR No. 5 Date 18-JUN-90 Job No. 211-00001Company COLUMBIA NATURAL RESOURCESRig Contractor & No. RAY RESOURCES/7Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field _____

Location COMMON DIST./USA/KENTUCKY/MARTINBHA No(s) Today 3;4Depth 3122 m Footage Last 24 Hrs. 39 m Last CSG: Depth Set 2955 m Size 9 7/8 in

MUD DATA

Mud Type AIR Wt. _____ (ppg) Vis. _____ PV _____ YP _____ WL _____
Gels _____ / _____ % Oil _____ % Solids _____ % Sand _____ pH _____ Chl. _____

BIT DATA

Bit No.	Size (in)	Type	Nozzles (32nds) or TFA	Footage Today (m)	Hours Today	Footage Accum. (m)	Hours Accum.	Depth Out (m)	DULL CONDITION							
									IR	OR	DC	LOC	B/S	G /16"	OC	R PLD
1R2	8 3/4	J44	3*20	39	6.25	39	6.25	3122	2	2						
2	8 3/4	J33	2*15/1*18	0	0.00	0	0.00									

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. Δ P (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (m)	Depth Out (m)
	6 3/4	EC-STEERABLE ANGLE BLD		920604			6.25	6.25	6.25	6.25	3083	3122
	6 1/2	EC-STEERABLE ANGLE BLD		EC05986			0.00	0.00	0.00	0.00	3122	

PUMP DATA

FORMATION DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)	Formation Name	Top (MD) (m)	Lithology #1	L1 %	Lithology #2

TIME BREAKDOWN

REMARKS:

From	Hours	Code	Operation Detail	Bit No.
00:00	0.50	11	RIG REPAIR	1R2
			WEIGHT INDICATOR	
00:30	3.50	25	DIRECTIONAL WORK	1R2
			RIG UP WIRELINE AND RUN IN HOLE	
04:00	3.75	25	DIRECTIONAL WORK	1R2
			WORK ON KELLY	
07:45	1.25	2	DRILLING IN FORMATION	1R2
09:00	0.50	25	DIRECTIONAL WORK	1R2
			WIRELINE SHEAVE	
09:30	0.50	13	DEVIATION SURVEY	1R2
			AT 3097 FEET	
10:00	5.00	2	DRILLING IN FORMATION	1R2
15:00	0.25	13	DEVIATION SURVEY	1R2
			AT 3172 FEET	
15:15	0.75	25	DIRECTIONAL WORK	1R2
			PULL STEERING TOOL	
16:00	2.00	9	TRIPPING OUT (to surface)	1R2
18:00	1.50	25	DIRECTIONAL WORK	1R2
			LAY DOWN MOTOR	
19:30	2.00	25	DIRECTIONAL WORK	2
			PICK UP BAKER MOTOR AND ORIENT	
21:30	2.50	8	TRIPPING IN (from surface)	2
			BHA #4	

KELLY BUSHING FOR WIRELINE WAS NOT WELDED
SQUARELY AND WOULD NOT FIT AT 12:30 STARTED
SOAPING HOLE AT 3114 FEET AT 1800 HOURS MOTOR
OUT POSSIBLY DUE TO HIGH ANGLE BUILD SETTING
CAUSING MOTOR FLEX PROBLEMS.

Company Representative

GRIESEMER/MCDOWELL
EC Representative

EC Daily Cost (\$US) 10000
EC Total Cost (\$US) 46000Page 1 of 1

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMGN DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 4

Depth 3122 m

Footage Last 24 Hrs. 0 m

Last CSG: Depth Set

2955 (10)

Size 9 7/8 (M)

MUD DATA

Mud Type	AIR	Wt	(ppg)	Vis.	PV	YP	WL
----------	-----	----	-------	------	----	----	----

Gels	/	% Oil	% Solids	% Sand	pH	Chl.
------	---	-------	----------	--------	----	------

BIT DATA

[illegible]

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. ΔP (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (ft)	Depth Out (ft)
	6 1/2	EC-STEERABLE ANGLE BLD		EC05986			10.00	10.00	10.25	10.25	3122	3470

PUMP DATA

FORMATION DATA

[illegible]

TIME BREAKDOWN

REMARKS:

From	Hours	Code	Operation Detail	Bkt No.
00:00	0.50	8	TRIPPING IN (from surface)	2
			BHA #4 CONT.	
00:30	1.00	25	DIRECTIONAL WORK	2
			RIG UP STEERING TOOL AND RUN IN HOLE	
01:30	2.00	2	DRILLING IN FORMATION	2
03:30	0.25	13	DEVIATION SURVEY	2
			AT 3156 FEET	
03:45	1.25	2	DRILLING IN FORMATION	2
05:00	0.25	13	DEVIATION SURVEY	2
			AT 3188 FEET	
05:15	1.25	2	DRILLING IN FORMATION	2
06:30	0.50	13	DEVIATION SURVEY	2
			AT 3219 FEET	
07:00	1.25	2	DRILLING IN FORMATION	2
08:15	0.50	13	DEVIATION SURVEY	2
			AT 3250 FEET	
08:45	1.00	2	DRILLING IN FORMATION	2
09:45	0.25	13	DEVIATION SURVEY	2
			AT 3281 FEET	
10:00	0.25	2	DRILLING IN FORMATION	2
10:15	0.25	7	CONDITION MUD AND CIRCULATE	2
10:30	1.00	25	DIRECTIONAL WORK	2
			LAY DOWN STEERING TOOL	

CHANGE BEND IN MOTOR AT 3251 FROM 1-3/8 - 1 TO 2

• 1

CHARLIE BELINGER

Company Representative

GRIESEMER/MCDOWELL

EC Representative

EC Daily Cost (US\$) 10000

EC Total Cost	(\$US\$)	56000
---------------	----------	-------

Page 1 of 2

DAILY DRILLING REPORT

DDR No. 7 Date 20-JUN-90 Job No. 211-00001Company COLUMBIA NATURAL RESOURCESRig Contractor & No. RAY RESOURCES/7Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field _____

Location COMMON DIST./USA/KENTUCKY/MARTINBHA No(s) Today 4;5Depth 3364 (m) Footage Last 24 Hrs. 242 (m) Last CSG: Depth Set 2955 (m) Size 9 7/8 (in)

MUD DATA

Mud Type AIR Wt. _____ (ppg) Vis. _____ PV _____ YP _____ WL _____
Gels / % Oil _____ % Solids _____ % Sand _____ pH _____ C _____

BIT DATA

Bit No.	Size (in)	Type	Nozzles (32nds) or TFA	Footage Today (m)	Hours Today	Footage Accum. (m)	Hours Accum.	Depth Out (m)	DULL CONDITION							
									IR	OR	DC	LOC	B/S	G/16"	OC	R PLD
2	8 3/4	J33	2*15/1*18	348	2.50	348	12.50	3470								
2R1	8 3/4	J33	3*18	117	3.50	117	3.50	3587								

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. Δ P (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (m)	Depth Out (m)
	6 1/2	EC-STEERABLE ANGLE BLD		EC05986			2.50	12.50	2.50	12.75	3122	3470

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)

FORMATION DATA

Formation Name	Top (MD) (m)	Lithology #1	L1 %	Lithology #2

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
00:00	0.50	2	DRILLING IN FORMATION	2
00:30	0.25	13	DEVIATION SURVEY	2
			AT 3379 FEET	
00:45	0.50	2	DRILLING IN FORMATION	2
01:15	0.50	13	DEVIATION SURVEY	2
			AT 3409 FEET	
01:45	0.75	2	DRILLING IN FORMATION	2
02:30	0.25	13	DEVIATION SURVEY	2
			AT 3440 FEET	
02:45	0.75	2	DRILLING IN FORMATION	2
03:30	0.25	13	DEVIATION SURVEY	2
			AT 3470 FEET	
03:45	4.50	9	TRIPPING OUT (to surface)	2
08:15	1.50	25	DIRECTIONAL WORK	2
			LAY DOWN BOTTOM HOLE ASSEMBLY	
09:45	1.00	25	DIRECTIONAL WORK	2R1
			PICK UP BOTOOM HOLE ASSEMBLY	
10:45	2.75	8	TRIPPING IN (from surface)	2R1
			BHA #5	
13:30	0.25	25	DIRECTIONAL WORK	2R1
			CHANGE KELLY BUSHINGS	
13:45	5.75	4	REAMING	2R1

REMARKS:

TIGHT COMING OFF BOTTOM

CHARLIE BELINGER
Company RepresentativeGRIESEMER/MCDOWELL
EC Representative

EC Daily Cost 0 10000

EC Total Cost 0 66000

Page 1 of 2

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field _____

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 5:6

Depth 3587 (m)

Footage Last 24 Hrs. 223 (m)

Last CSG: Depth Set _____

2955 (m)

Size 9 7/8 (in)
MUD DATA

Mud Type _____ Wt. _____ (ppg) Vis. _____ PV _____ YP _____ WL _____
Gels _____ / _____ % Oil _____ % Solids _____ % Sand _____ pH _____ Chl. _____

BIT DATA

Bit No.	Size (in)	Type	Nozzles (32nds) or TFA	Footage Today (m)	Hours Today	Footage Accum. (m)	Hours Accum.	Depth Out (m)	DULL CONDITION							
									IR	OR	DC	LOC	B/S	G/16"	OC	R PLD

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. Δ P (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (m)	Depth Out (m)

PUMP DATA
FORMATION DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)	Formation Name	Top (MD) (m)	Lithology #1	L1 %	Lithology #2

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
14:00	1.00	2	DRILLING IN FORMATION	2R2
15:00	0.25	13	DEVIATION SURVEY	2R2
			AT 3750 FEET	
15:15	1.25	2	DRILLING IN FORMATION	2R2
16:30	0.25	13	DEVIATION SURVEY	2R2
			AT 3780 FEET	
16:45	1.00	2	DRILLING IN FORMATION	2R2
17:45	0.25	13	DEVIATION SURVEY	2R2
			AT 3811 FEET	
18:00	1.50	2	DRILLING IN FORMATION	2R2
19:30	0.25	13	DEVIATION SURVEY	2R2
			AT 3843 FEET	
19:45	1.00	2	DRILLING IN FORMATION	2R2
20:45	0.25	13	DEVIATION SURVEY	2R2
			AT 3867 FEET	
21:00	0.50	7	CONDITION MUD AND CIRCULATE	2R2
			BLOW HOLE	
21:30	2.50	9	TRIPPING OUT (to surface)	2R2

REMARKS:

Company Representative _____

EC Representative _____

EC Daily Cost _____

See Page 1

EC Total Cost _____

See Page 1

Page 2 of 2

DAILY DRILLING REPORT

DDR No. 11 Date 24-JUN-90 Job No. 211-00001Company COLUMBIA NATURAL RESOURCESRig Contractor & No. RAY RESOURCES/7Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field _____

Location COMMON DIST./USA/KENTUCKY/MARTINBHA No(s) Today 8Depth 3954 (m) Footage Last 24 Hrs. 65 (m) Last CSG: Depth Set 2955 (m) Size 9 7/8 (in)

MUD DATA

Mud Type AIR Wt. _____ (ppg) Vis. _____ PV _____ YP _____ WL _____
Gels _____ / _____ % Oil _____ % Solids _____ % Sand _____ pH _____ Chl. _____

BIT DATA

Bit No.	Size (in)	Type	Nozzles (32nds) or TFA	Footage Today (m)	Hours Today	Footage Accum. (m)	Hours Accum.	Depth Out (m)	DULL CONDITION							
									IR	OR	DC	LOC	B/S	G / 16"	OC	R PLD
3R1	8 1/2	HP53A	3"20	0	4.00	0	4.00	3966								

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. Δ P (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (m)	Depth Out (m)
	6 1/2	EC-STEERABLE ANGLE BLD	BENT - 2.00	EC05986			4.00	4.00	7.75	7.75	3966	3966

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)

FORMATION DATA

Formation Name	Top (MD) (m)	Lithology #1	L1 %	Lithology #2

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
00:00	1.50	8	TRIPPING IN (from surface)	3R1
			BHA #8	
01:30	2.25	4	REAMING	3R1
			FROM 3710 TRYING TO ENTER ORIGINAL HOLE	
03:45	1.50	4	REAMING	3R1
			TIGHT AT 3857	
05:15	1.75	25	DIRECTIONAL WORK	3R1
07:00	1.25	25	DIRECTIONAL WORK	3R1
			ATTEMPT TO ENTER ORIGINAL HOLE	
08:15	0.75	25	DIRECTIONAL WORK	3R1
			WOULD NOT ENTER PICK UP KELLY	
09:00	0.75	25	DIRECTIONAL WORK	3R1
			RUN IN WIRELINE - NEW HOLE	
09:45	3.00	25	DIRECTIONAL WORK	3R1
			TRIP OUT 10 STANDS PU SIDE ENTRY SUB	
12:45	0.50	25	DIRECTIONAL WORK	3R1
			INSTALL SIDE ENTRY SUB AND SEAT DOT	
13:15	3.00	25	DIRECTIONAL WORK	3R1
			RIH 2 STANDS AND PUMP DOWN 8 STANDS	
16:15	0.25	2	DRILLING IN FORMATION	3R1
			DRILL 3889 - 3902	
18:30	0.50	13	DEVIATION SURVEY	3R1

REMARKS:

Company Representative		GRIESEMER/MCDOWELL
		EC Representative
EC Daily Cost	0	10000
EC Total Cost	0	98500
Page <u>1</u> of <u>2</u>		

DAILY DRILLING REPORT

DDR No. 12 Date 25-JUN-90 Job No. 211-00001

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field _____

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 8:9

Depth 3954 (m) Footage Last 24 Hrs. 0 (m) Last CSG: Depth Set 2955 (m) Size 9 7/8 (in)

MUD DATA

Mud Type AIR Wt. _____ (ppg) Vis. _____ PV _____ YP _____ WL _____
Gels / % Oil _____ % Solids _____ % Sand _____ pH _____ Chl. _____

BIT DATA

Bit No.	Size (in)	Type	Nozzles (32nds) or TFA	Footage Today (m)	Hours Today	Footage Accum. (m)	Hours Accum.	Depth Out (m)	DULL CONDITION							
									IR	OR	DC	LOC	B/S	G/16"	OC	R PLD
3R1	8 1/2	HP53A	3*20	12	0.00	0	4.00	3966								
3R2	8 1/2	HP53A	3*20	-12	4.00	-12	4.00									

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. ΔP (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (m)	Depth Out (m)
	6 1/2	EC-STEERABLE ANGLE BLD	BENT - 2.00	EC05986			0.00	4.00	0.00	7.75	3966	3966
	6 1/2	EC-STEERABLE ANGLE BLD	FLEX -	5736			4.00	4.00	6.00	6.00	3966	

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)

FORMATION DATA

Formation Name	Top (MD) (m)	Lithology #1	L1 %	Lithology #2

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
00:00	6.00	9	TRIPPING OUT (to surface)	3R1
			TIGHT ON BOTTOM	
06:00	2.00	25	DIRECTIONAL WORK	3R2
			PICK UP MOTOR AND ORIENT	
08:00	1.50	11	RIG REPAIR	3R2
			SLIP 75 FEET OF LINE AND WORK ON BRAKES	
09:30	0.50	10	LUBRICATE RIG	3R2
10:00	2.00	25	DIRECTIONAL WORK	3R2
			ALIGN UPPER TOOL FACE ON MOTOR	
12:00	1.25	8	TRIPPING IN (from surface)	3R2
			BHA #9	
13:15	0.50	11	RIG REPAIR	3R2
			AIR LINES	
13:45	2.50	8	TRIPPING IN (from surface)	3R2
			BRIDGE AT 3650	
16:15	2.00	4	REAMING	3R2
			WASH DOWN FROM 3650	
18:15	1.00	2	DRILLING IN FORMATION	3R2
			DAAB MOTOR	
19:15	0.50	13	DEVIATION SURVEY	3R2
			AT 3998 FEET	
19:45	0.50	2	DRILLING IN FORMATION	3R2

REMARKS:

Company Representative _____ GRIESEMER/MCDOWELL
EC Representative _____

EC Daily Cost 0 10000

EC Total Cost 0 108500

Page 1 of 2

DAILY DRILLING REPORT

DDR No. 13 Date 26-JUN-90 Job No. 211-00001Company COLUMBIA NATURAL RESOURCESRig Contractor & No. RAY RESOURCES/7Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field _____

Location COMMON DIST./USA/KENTUCKY/MARTINBHA No(s) Today 9:10Depth 4100 (m) Footage Last 24 Hrs. 146 (m) Last CSG: Depth Set 2955 (m) Size 9 7/8 (in)

MUD DATA

Mud Type AIR Wt. _____ (ppg) Vis. _____ PV _____ YP _____ WL _____
Gels / % Oil _____ % Solids _____ % Sand _____ pH _____ Chl. _____

BIT DATA

Bit No.	Size (in)	Type	Nozzles (2nds) or TFA	Footage Today (m)	Hours Today	Footage Accum. (m)	Hours Accum.	Depth Out (m)	DULL CONDITION							
									IR	OR	DC	LOC	B/S	G/16"	OC	R PLD
3R2	8 1/2	HP53A	3*20	200	2.00	188	6.00	4154								
4	8 1/2	HPSMJ	3*20	-54	2.00	-54	2.00									

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. Δ P (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (m)	Depth Out (m)
	6 1/2	EC-STEERABLE ANGLE BLD	FLEX -	5736			2.00	6.00	2.25	8.25	3968	4154

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)

FORMATION DATA

Formation Name	Top (MD) (m)	Lithology #1	L1 %	Lithology #2
		SHALE		

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
00:00	0.75	2	DRILLING IN FORMATION	3R2
00:45	0.25	13	DEVIATION SURVEY	3R2
			AT 4123 FEET	
01:00	1.25	2	DRILLING IN FORMATION	3R2
02:15	0.25	13	DEVIATION SURVEY	3R2
			AT 4154 FEET	
02:30	0.25	7	CONDITION MUD AND CIRCULATE	3R2
			BLOW HOLE	
02:45	5.50	9	TRIPPING OUT (to surface)	3R2
			FOR HORIZONTAL ASSEMBLY	
08:15	1.00	25	DIRECTIONAL WORK	3R2
			LAY DOWN BHA #9	
09:15	1.50	25	DIRECTIONAL WORK	4
			PICK UP BHA #10	
10:45	3.00	8	TRIPPING IN (from surface)	4
			CHANGE KELLY BUSHINGS	
13:45	1.75	4	REAMING	4
			3990 - 4154	
15:30	0.75	2	DRILLING IN FORMATION	4
16:15	0.50	11	RIG REPAIR	4
			DRAWWORKS MOTORS	
16:45	1.25	2	DRILLING IN FORMATION	4
			TO 4228	

REMARKS:

DOT STILL LUMPING ALONG AT END OF RUN

CHARLIE BALLENGER
Company RepresentativeGRIESEMER/MCDOWELL
EC Representative

EC Daily Cost 0 10000

EC Total Cost 0 118500

Page 1 of 2

DAILY DRILLING REPORT

DDR No. 14 Date 27-JUN-90 Job No. 211-00001

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 10:11

Depth	4227 m	Footage Last 24 Hrs.	127 m	Last CSG: Depth Set	2955 m	Size	9 7/8 (in)
-------	--------	----------------------	-------	---------------------	--------	------	------------

MUD DATA

Mud Type	AIR	Wt.	(ppg)	Vis.	PV	YP	WL
Gels	/	% Oil		% Solids	% Sand	pH	Chl.

BIT DATA

[illegible]

MOTOR DATA

[illegible]

PUMP DATA

FORMATION DATA

[illegible]

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
00:00	2.50	9S	SHORT TRIP	4
			AND RUN SURVEY	
02:30	5.75	2	DRILLING IN FORMATION	4
			WITH NBIBS	
08:15	0.25	7	CONDITION MUD AND CIRCULATE	4
			BLOW HOLE	
08:30	4.00	13	DEVIATION SURVEY	4
			AT 4294 FEET	
12:30	2.50	9	TRIPPING OUT (to surface)	4
			CHANGE ASSEMBLY	
15:00	0.50	25	DIRECTIONAL WORK	5
			PICK UP BHA 11	
15:30	1.00	25	DIRECTIONAL WORK	5
			LOAD OUT USED MOTORS	
16:30	2.50	8	TRIPPING IN (from surface)	5
19:00	0.75	4	REAMING	5
			120 FEET	
19:45	4.25	2	DRILLING IN FORMATION	5
			4320 FEET	

REMARKS:

Company Representative	GRIESEMER/MCDOWELL EC Representative
------------------------	---

EC Daily Cost 0 2500

EC Total Cost	0	121000
---------------	---	--------

Page 1 of 1

DAILY DRILLING REPORT

DDR No. 15 Date 28-JUN-90 Job No. 211-00001Company COLUMBIA NATURAL RESOURCESRig Contractor & No. RAY RESOURCES/7Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field _____

Location COMMON DIST./USA/KENTUCKY/MARTINBHA No(s) Today 11:12Depth 4599 (m) Footage Last 24 Hrs. 372 (m) Last CSG: Depth Set 2955 (m) Size 9 7/8 (m)

MUD DATA

Mud Type AIR Wt. _____ (ppg) Vis. _____ PV _____ YP _____ WL _____
Gels _____ / _____ % Oil _____ % Solids _____ % Sand _____ pH _____ Chl. _____

BIT DATA

Bit No.	Size (in)	Type	Nozzles (32nds) or TFA	Footage Today (m)	Hours Today	Footage Accum. (m)	Hours Accum.	Depth Out (m)	DULL CONDITION							
									IR	OR	DC	LOC	B/S	G / 16"	OC	R PLD
5	8 1/2	M84F	3*20	94	10.50	94	14.75	4321								
5R1	8 1/2	M84F	3*20	278	0.00	278	0.00									

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. ΔP (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (m)	Depth Out (m)

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)

FORMATION DATA

Formation Name	Top (MD) (m)	Lithology #1	L1 %	Lithology #2
DEVONIAN-LOWER		SHALE		

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
00:00	8.50	2	DRILLING IN FORMATION	5
			FROM 4382 FEET	
08:30	1.50	9	TRIPPING OUT (to surface)	5
			RUN SURVEY AT 4537	
10:00	1.50	8	TRIPPING IN (from surface)	5
			WITH SURVEY TOOL	
11:30	1.50	9	TRIPPING OUT (to surface)	5
			23 STANDS	
13:00	1.50	8	TRIPPING IN (from surface)	5
14:30	1.00	2	DRILLING IN FORMATION	5
15:30	0.75	11	RIG REPAIR	5
			AIR LINE REPAIR	
16:15	1.00	2	DRILLING IN FORMATION	5
17:15	1.25	30	MISCELLANEOUS	5
			CONN PIPE WOULD NOT SLIDE INTO HOLE	
18:30	2.75	9	TRIPPING OUT (to surface)	5
			CHANGE BHA	
21:15	1.00	25	DIRECTIONAL WORK	5R1
			PICK UP NEW BHA	
22:15	1.00	25	DIRECTIONAL WORK	5R1
			FREE UP CUTTERS ON REAMER	
23:15	0.75	8	TRIPPING IN (from surface)	5R1
			BHA #12	

REMARKS:

Company Representative _____ GRIESEMER/MCDOWELL
EC RepresentativeEC Daily Cost 0 2500EC Total Cost 0 123500Page 1 of 1

DAILY DRILLING REPORT

DDR No. 16 Date 29-JUN-90 Job No. 211-00001Company COLUMBIA NATURAL RESOURCESRig Contractor & No. RAY RESOURCES/7Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field _____

Location COMMON DIST./USA/KENTUCKY/MARTINBHA No(s) Today 12Depth 4703 (m) Footage Last 24 Hrs. 104 (m) Last CSG: Depth Set 2955 (m) Size 9 7/8 (m)

MUD DATA

Mud Type AIR Wt. _____ (ppg) Vis. _____ PV _____ YP _____ WL _____
Gels / % Oil _____ % Solids _____ % Sand _____ pH _____ Chl. _____

BIT DATA

Bit No.	Size (in)	Type	Nozzles (32nds) or TFA	Footage Today (m)	Hours Today	Footage Accum. (m)	Hours Accum.	Depth Out (m)	DULL CONDITION							
									IR	OR	DC	LOC	B/S	G /16"	OC	R PLD
5R1	8 1/2	M84F	3*20	216	4.75	216	4.75	4537								

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (32nds)	Avg. Δ P (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (m)	Depth Out (m)

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)

FORMATION DATA

Formation Name	Top (ft)	Lithology #1	L1 %	Lithology #2

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
00:00	2.25	8	TRIPPING IN (from surface)	5R1
02:15	0.25	4	REAMING	5R1
			30 FEET	
02:30	4.75	2	DRILLING IN FORMATION	5R1
			AT 4599 FEET	
07:15	0.25	7	CONDITION MUD AND CIRCULATE	5R1
			BLOW HOLE	
07:30	2.25	9S	SHORT TRIP	5R1
			TIGHT HOLE AT 4322	
09:45	0.50	14	WIRELINE LOGS	5R1
			MAKE UP SURVEY TOOL	
10:15	0.50	8	TRIPPING IN (from surface)	5R1
			TIGHT HOLE	
10:45	2.50	9S	SHORT TRIP	5R1
			WITH WIRELINE	
13:15	2.25	9	TRIPPING OUT (to surface)	5R1
			TWIST OFF BOTTOM JOINT OF HWDP	
15:30	7.50	30	MISCELLANEOUS	5R1
			WAIT ON FISHERMAN	
23:00	1.00	30	MISCELLANEOUS	
			PICK UP FISHING TOOLS	

REMARKS:

Company Representative _____ GRIESEMER/MCDOWELL
EC Representative _____EC Daily Cost 0 2500EC Total Cost 0 126000Page 1 of 1

DAILY DRILLING REPORT

DDR No. 18 Date 01-JUL-90 Job No. 211-00001

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 13;14

Depth 4703 m Footage Last 24 Hrs. 0 m Last CSG: Depth Set 2955 m Size 9 7/8 (in)

MUD DATA

Mud Type AIR Wt. (ppg) Vis. PV YP WL
Gels / % Oil % Solids % Sand pH Chl.

BIT DATA

[illegible]

MOTOR DATA

[illegible]

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (gal)

FORMATION DATA

Formation Name	Top (MCD) (m)	Lithology #1	L1 %	Lithology #2

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
00:00	0.25	9S	SHORT TRIP	5R2
00:15	1.25	25	DIRECTIONAL WORK	5R2
			HANG WIRELINE SHEAVE	
01:30	1.50	13	DEVIATION SURVEY	5R2
			RIH WITH SURVEY TOOL - RAN OUT OF TIME	
03:00	0.25	7	CONDITION MUD AND CIRCULATE	5R2
03:15	0.50	13	DEVIATION SURVEY	5R2
			LAY ENTRY SUB DOWN	
03:45	1.50	13	DEVIATION SURVEY	5R2
			TRY SECOND SURVEY - RAN OUT OF TIME	
05:15	0.50	9S	SHORT TRIP	5R2
			LAY DOWN SIDE DOOR SUB AND SURVEY TOOL	
05:45	0.50	9S	SHORT TRIP	5R2
06:15	2.00	2	DRILLING IN FORMATION	5R2
			4703-4734	
06:15	4.00	9S	SHORT TRIP	5R2
			AND SURVEY	
12:15	1.00	7	CONDITION MUD AND CIRCULATE	5R2
13:15	3.75	9	TRIPPING OUT (to surface)	5R2
			ASSEMBLY CHANGE	
17:00	3.50	8	TRIPPING IN (from surface)	5R3
			BHA #14	

REMARKS:

CORRECTION ON TALLY BOARD FROM 4734 FEET TO 4745
FEET

Company Representative _____ GRIESEMER/MCDOY, J. L.
EC Representative

EC Daily Cost 0 2500

EC Total Cost	0	131000
---------------	---	--------

Page 1 of 2

DDR No. 19 Date 02-JUL-80 Job No. 211-00001

Rig Contractor & No. RAY RESOURCES/7

Field

BHA No(s) Today 14

Size 9 7/8 in

Mud Type AIR Wt. (ppg) Vis. PV YP WL
Gels / % Oil % Solids % Sand pH Chl.

[illegible][illegible][illegible][illegible]

Page 1 of 1

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 14:15

Depth 5025 m

Footage Last 24 Hrs.

0 00

Last CSG: Depth Set

2955 (10)

Size 9 7/8 (M)

MUD DATA

Mud Type AIR WL (ppg) Vis. PV YP WL
Gels / % Oil % Solids % Sand pH Chl.

BIT E AT 3

[illegible]

MOTOR DATA

[illegible]

PUMP DATA

FORMATION DATA

[illegible]

TIME BREAKDOWN

[illegible]

REMARKS:

Company Representative GRIESEMER/MCDOWELL
EC Representative

EC Daily Cost 0 2500

EC Total Cost	0	136000
---------------	---	--------

Page 1 of 1

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 15

Depth 5055 m

Footage Last 24 Hrs. 30 m

Last CSG: Depth Set

2955 m

Size **9 7/8 (In)**

MUD DATA

Mud Type AIR Wt (ppg) Vis. PV YP WL

Gels / % Oil % Solids % Sand pH Chl.

BIT DATA

[illegible]

MOTOR DATA

[illegible]

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)

FORMATION DATA

Formation Name	Top (MD) (m)	Lithology #1	L1 %	Lithology #2

TIME BREAKDOWN

[illegible]

REMARKS:

Company Representative

GRIESEMER/MCDOWELL

EC Representative

EC Daily Cost	0	2500
---------------	---	------

EC Total Cost	0	138500
---------------	---	--------

Page 1 of 1

DAILY DRILLING REPORT

DDR No. 22 Date 05-JUL-90 Job No. 211-00001Company COLUMBIA NATURAL RESOURCESRig Contractor & No. RAY RESOURCES/7Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field _____

Location COMMON DIST./USA/KENTUCKY/MARTINBHA No(s) Today 15Depth 5206 (ft) Footage Last 24 Hrs. 151 (ft) Last CSG: Depth Set 2955 (ft) Size 9 7/8 (in)

MUD DATA

Mud Type AIR Wt. _____ (ppg) Vis. _____ PV _____ YP _____ WL _____
Gels _____ / _____ % Oil _____ % Solids _____ % Sand _____ pH _____ Chl. _____

BIT DATA

Bit No.	Size (in)	Type	Nozzles (2nds) or TFA	Footage Today (ft)	Hours Today	Footage Accum. (ft)	Hours Accum.	Depth Out (ft)	DULL CONDITION							
									IR	OR	DC	LOC	B/S	G/16"	OC	R PLD
5R4	8 1/2	M84F	3"20	1238	13.00	1238	14.75	6263								

MOTOR DATA

Run No.	Size (in)	Mfr. - Type	Deflection Tool & Angle	Serial No.	Rotor Nozzle (2nds)	Avg. Δ P (psi)	Drill Hrs. Today	Drill Hrs. Accum.	Circ. Hrs. Today	Circ. Hrs. Accum.	Depth In (ft)	Depth Out (ft)

PUMP DATA

Pump No.	Liner (in)	Stroke (in)	Vol. per Stroke (gal)	Max Allow SPP (psi)

FORMATION DATA

Formation Name	Top (MD) (ft)	Lithology #1	L1 %	Lithology #2

TIME BREAKDOWN

From	Hours	Code	Operation Detail	Bit No.
00:00	6.50	2	DRILLING IN FORMATION	5R4
06:30	0.50	7	CONDITION MUD AND CIRCULATE	5R4
			BLOW HOLE	
07:00	3.00	9	TRIPPING OUT (to surface)	5R4
			AND PUT 10 MORE STANDS OF PIPE BELOW HW	
10:00	2.00	8	TRIPPING IN (from surface)	5R4
12:00	1.00	2	DRILLING IN FORMATION	5R4
			AT 5206 FEET	
13:00	0.75	11	RIG REPAIR	5R4
			KELLY BUSHINGS	
13:45	2.50	2	DRILLING IN FORMATION	5R4
16:15	0.25	10	LUBRICATE RIG	5R4
18:30	3.00	2	DRILLING IN FORMATION	5R4
19:30	0.25	7	CONDITION MUD AND CIRCULATE	5R4
19:45	2.00	9S	SHORT TRIP	5R4
			SURVEY AT 5393	
21:45	0.25	13	DEVIATION SURVEY	5R4
			RUN SURVEY IN HOLE AND PACK OFF	
22:00	1.50	9S	SHORT TRIP	5R4
23:30	0.50	9S	SHORT TRIP	5R4
			WITH SURVEY TOOL	

REMARKS:

Company Representative

GRIESEMER/MCDOWELL

EC Representative

EC Daily Cost 0 2500EC Total Cost 0 141000Page 1 of 1

DAILY DRILLING REPORT

DDF No. 23 Date 06-JUL-90 Job No. 211-00001

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 15

Depth 5765 (m) Footage Last 24 Hrs. 559 (m) Last CSG: Depth Set 2955 (m) Size 9 7/8 (in)

MUD DATA

Mud Type AIR Wt. (ppg) Vis. PV YP WL
Gels / % Oil % Solids % Sand pH Chl.

BIT DATA

[illegible]

MOTOR DATA

[illegible]

PUMP DATA

FORMATION DATA

[illegible]

TIME BREAKDOWN

[illegible]

REMARKS:

CHARLES BELLINGER
Company Representative

GRIESEMER/MCDOWELL
EC Representative

EC Daily Cost	0	2500
---------------	---	------

EC Total Cost	0	143500
---------------	---	--------

Page 1 of 1

DAILY DRILLING REPORT

DDR No. 25 Date 08-JUL-90 Job No. 211-00001

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES/7

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Location COMMON DIST./USA/KENTUCKY/MARTIN

BHA No(s) Today 15

Depth 6263 (m) Footage Last 24 Hrs. 0 (m) Last CSG: Depth Set 2955 (m) Size 9 7/8 (in)

MUD DATA

Mud Type	AIR	Wt.	(ppg)	Vis.	PV	YP	WL
Gels	/	% Oil		% Solids	% Sand	pH	Chl.

BIT DATA

[illegible]

MOTOR DATA

[illegible]

PUMP DATA

FORMATION DATA

[illegible]

TIME BREAKDOWN

REMARKS:

[illegible]

Company Representative	W A MCDOWELL EC Representative
------------------------	-----------------------------------

EC Daily Cost 0 1800

EC Total Cost	0	147100
---------------	---	--------

Page 1 of 1

Appendix 2

Bottom Hole Assembly Configuration Reports

DEPTH IN 3035'
 DEPTH OUT 3035'
 AVERAGE ANGLE
 OF DRILL _____

COLUMBIA NATURAL
 RESOURCES

CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747

BH- 1

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth in 3035 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 3035 m

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description <small>Describe UBM Stabilizer for NorTrak Run!</small>	Spiral	Blade Length <small>(in)</small>	Blade Width <small>(in)</small>	Gauge Length <small>(in)</small>	Gauge In <small>(in)</small>	Gauge Out <small>(in)</small>
2						8 3/8	8 3/8
4						8 5/8	8 5/8

DRILLPIPE DATA

WEIGHT DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper					4-1/2 XH		Total		
Lower	HWDP				4-1/2 XH	421.15	Below Jars		

Survey Sensor to Bit	88.0	ft	Hole Drag: Up	(x1000 lbs)	Down	(x1000 lbs)
----------------------	------	----	---------------	-------------	------	-------------

Active For Running BHA KICK OFF AND BUILD AT 9-13DEG/100FT.

BHA Results COULD NOT GET TO BOTTOM - SUSPECT MOTOR BINDING

Reason for POOH MOTOR WOULD NOT DRILL DUE TO BINDING STATOR HOUSING AND ROTOR.

Page 1 of 1

EC Representative GRIESEMOR/WALKER

DEPTH IN 3035'
 DEPTH OUT 3083'
 AVERAGE ANGLE
 OF DRILL _____

COLUMBIA NATURAL
 RESOURCES

CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747

BH- 2A

DEPTH IN 3035'
 DEPTH OUT 3083'
 AVERAGE ANGLE
 OF DRILL _____

COLUMBIA NATURAL
 RESOURCES

CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747

BH- 2B

BOTTOM HOLE ASSEMBLY

BHA No. 2 Sidetrack No. Job No. 211-00001Company COLUMBIA NATURAL RESOURCESRig Contractor & No. RAY RESOURCES 7Depth In 3035 ftWell Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field Depth Out 3083 ft

BIT DATA

Item No.	Bit No.	Size (in)	Mfr.	Type	Serial No.	Nozzles (2nd or TFA)	Gauge Length (in)	Depth In (ft)	Depth Out (ft)	Bit Length (ft)
1	1R1	8 3/4	HTC	J44	R121HJ	3*20		3035	3083	1.00

COMPONENT DATA

Item No.	Component Description	Mfr.	Serial No.	Gauge OD (in)	OD (in)	ID (in)	Fishing Neck Length (ft)	Component Length (ft)	Cumulative Length (ft)
2	STEERABLE ANGLE BLD	EC	920604	8.625	6 3/4			19.70	20.7
3	BENT SUB	EC	-		6 3/4	2.875		3.45	24.2
4	CROSSOVER SUB		3013		5 3/4	2.875		1.15	25.3
5	CROSSOVER SUB		958		6 1/8	2.875		0.97	26.3
6	DRILL COLLAR, NM	EC	-		6 3/4	2.875		21.46	47.7
7	CROSSOVER SUB	TS	359		6 1/16	3.250		0.82	48.6
8	CROSSOVER SUB				6 5/8	2.813		2.70	51.3
9	MWD				6 3/4	2.875		30.42	81.7
10	EXTENSION SUB				6 5/8	2.938		2.77	84.4
11	FLOAT SUB	EC	9514		6 3/8			1.71	86.1
12	UBHO SUB	EC	15396		5 7/8	2.250		2.40	88.6
13	CROSSOVER SUB	EC	3718		5 3/4	2.625		0.94	89.5
14	DRILL COLLAR, NM	EC	-		6 1/4			31.30	120.8
15	HEAVY WT DRILL PIPE-14				4 1/2			421.15	541.9

STABILIZER DATA

Item No.	Stabilizer Description <small>Describe UGH Stabilizer for NorTrak Runs!</small>	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)

DRILLPIPE DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper					4-1/2 XH		Total		
Lower	HWDP				4-1/2		Below Jars		

WEIGHT DATA

Survey Sensor to Bit 84.7 ft Hole Drag: Up (x1000 lbs) Down (x1000 lbs)Objective For Running BHA KICK OFF AND BUILDBHA Results Reason for POOH Page 1 of 1EC Representative GRIESEMORWALKER

DEPTH IN 3083'
 DEPTH OUT 3122'
 AVERAGE ANGLE
 OF DRILL _____

COLUMBIA NATURAL
 RESOURCES

CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747

BH- 3

DEPTH IN 3122'
DEPTH OUT 3470'
AVERAGE ANGLE
OF DRILL _____

COLUMBIA NATURAL
RESOURCES

CNR /DOE HORIZONTAL PROSPECT
MARTIN Co. KENTUCKY WELL #21747

BH- 4

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 3122 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 3470 (m)

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe UBM Stabilizer for NorTrak Runal	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)
2		RWT				8 3/8	

DRILLPIPE DATA

Drillpipe -	Grade	OD (in)	ID (in)	Wt/Ft (lb/ft)	Conn.	Length (ft)
Upper						
Lower						

WEIGHT DATA

BHA Weight (x1000 lbs)	In Air	In Mud
Total		
Below Jars		

vey Sensor to Bit	48.0	m	Hole Drag: Up	(x1000 lbs)	Down	(x1000 lbs)
-------------------	------	---	---------------	-------------	------	-------------

Objective For Running BHA BUILD ANGLE

BHA Results BUILT FROM 10.3 TO 12.31 BUR

Reason for POOH

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

DEPTH IN 3470'
DEPTH OUT 3587'
AVERAGE ANGLE
OF DRILL

COLUMBIA NATURAL
RESOURCES

CNR /DOE HORIZONTAL PROSPECT
MARTIN Co. KENTUCKY WELL #21747

BH- 5

DEPTH IN 3587'
 DEPTH OUT 3876'
 AVERAGE ANGLE
 OF DRILL _____

COLUMBIA NATURAL
 RESOURCES

CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747

BH-6&8

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth in 3470 ft

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 3587 m

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe UBM Stabilizer for NorTrak Panel	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)

DRILLPIPE DATA

WEIGHT DATA

							WEIGHT DATA		
Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper							Total		
Lower							Below Jars		

Survey Sensor to Bit 90 Hole Drag: Up (x1000 lbs) Down (x1000 lbs)

Objective For Running BHA REAM AND DRILL TANGENT SECTION

BHA Results

Reason for POOH:

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 3587 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL **Field**

Depth Out 3876 m

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe UBM Stabilizer for NorTrak Run!	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)
2		RWT	15.00	3.00	15.00		

DRILLPIPE DATA

WEIGHT DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper							Total		
Lower							Below Jars		

Sensor to Bit 47.0 ft Hole Drag: Up (x1000 lbs) Down (x1000 lbs)

Objective For Running BHA SECOND BUILD UP SECTION

BHA Results BUR OF 15.8 TO 13.5

Reason for POOH FINISHED BUILD UP SECTION

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

DEPTH IN 3867'
 DEPTH OUT 3966'
 AVERAGE ANGLE
 OF DRILL

COLUMBIA NATURAL
RESOURCES

CNR /DOE HORIZONTAL PROSPECT
MARTIN Co. KENTUCKY WELL #21747

BH- 7

DEPTH IN 3876'
 DEPTH OUT 3876'
 AVERAGE ANGLE
 OF DRILL

COLUMBIA NATURAL
 RESOURCES

CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747

BH-6&8

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 3966 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 3968 m

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe UBM Stabilizer for NorTrak Runel	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)
2		RWT	15.00	3.00	15.00		

DRILLPIPE DATA

WEIGHT DATA

DRILLPIPE DATA							WEIGHT DATA		
Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbf/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper							Total		
Lower							Below Jars		

Survey Sensor to Bit	47.0	ms
----------------------	------	----

Hole Drag: Up (x1000 lbs)

Down (x1000 lbs)

ective For Running BHA BUILD UP SECTION

BHA Results BUR OF 15.8 TO 13.5

Reason for POOH FINISHED BU SECTION

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

DEPTH IN 3966'
 DEPTH OUT 4154'
 AVERAGE ANGLE
 OF DRILL _____

COLUMBIA NATURAL
 RESOURCES

CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747

BH- 9

A Baker Hughes company
Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 3968 fathoms

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 4154 m

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

STABILIZER DATA							
Item No.	Stabilizer Description Describe UBM Stabilizer for NorTrak Pallet	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)
2	STS						

DRILLPIPE DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper							Total		
Lower							Below Jars		

vey Sensor to Bit 47.0 ft Hole Drag: Up 20 (x1000 lbs) Down 20 (x1000 lbs)

Objective For Running BHA BUILD ANGLE TO 88DEG.

BHA Results **BUR / 6.2 TO 8.5**

Reason for POOH FINISHED BUILD UP SECTION

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

DEPTH IN 4154'
 DEPTH OUT 4227'
 AVERAGE ANGLE
 OF DRILL _____

Monel Collar

CMS

Sub - XO

Sub - XO

UBHO

Sub - XO

IBS

Float Sub

Bt

**COLUMBIA NATURAL
RESOURCES**

**CNR /DOE HORIZONTAL PROSPECT
MARTIN Co. KENTUCKY WELL #21747**

BH- 10

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 4154 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 4227 m

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe UHM Stabilizer for NoTrack Runs!	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)

DRILLPIPE DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lb/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper							Total		
Lower							Below Jars		

WEIGHT DATA

BHA Weight (x1000 lbs)	In Air	In Mud
Total		
Below Jars		

Way Sensor to Bit	27.0	ft	Hole Drag: Up	(x1000 lbs)	Down	(x1000 lbs)
-------------------	------	----	---------------	-------------	------	-------------

Objective For Running BHA MAINTAIN DIRECTION AND SLIGHT BUILD

BHA Results BUILT 3.61 DEG/100FT.

Reason for POOH BUILDING TOO MUCH ANGLE

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

DEPTH IN 4227'
 DEPTH OUT 4321'
 AVERAGE ANGLE
 OF DRILL _____

Monel Collar

CMS

UBHO

IBS

Monel Collar

Roller Reamer

Float Sub

Bit

**COLUMBIA NATURAL
 RESOURCES**

**CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747**

BH- 11

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 4227 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Field

Depth Out 4321 m

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe UBM Stabilizer for NorTrek Rural	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)

DRILLPIPE DATA

WEIGHT DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper							Total		
Lower							Below Jars		

Key Sensor to Bit	60.0	ms
-------------------	------	----

Hole Drag: Up (x1000 lbs)

Down (x1000 lbs)

Objective For Running BHA SLIGHT DROP IN ANGLE

BHA Results BUILDING ANGLE

Reason for POOH BUILDING ANGLE

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

DEPTH IN 4321'
DEPTH OUT 4537'
AVERAGE ANGLE
OF DRILL _____

Monel Collar

CMS

UBHO

IBS

Roller Reamer

Float Sub

Bit

COLUMBIA NATURAL
RESOURCES

CNR /DOE HORIZONTAL PROSPECT
MARTIN Co. KENTUCKY WELL #21747

BH- 12

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 4321 (m)

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 4537 (m)

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe UBM Stabilizer for NorTrak Runal	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)

DRILLPIPE DATA

WEIGHT DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper							Total		
Lower							Below Jars		

Way Sensor to Bkt 40.0 m Hole Drag: Up (x1000 lbs) Down (x1000 lbs)

Objective For Running BHA DROP ANGLE AT SLOW RATE

BHA Results

Reason for POOH

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

DEPTH IN 4537'
 DEPTH OUT 4745'
 AVERAGE ANGLE
 OF DRILL _____

Monel Collar

CMS

UBHO

Sub - XO

Roller Reamer

Roller Reamer

Float Sub

Bit

COLUMBIA NATURAL
 RESOURCES

CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747

BH- 13

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 4537 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL

Depth Out 4745 m

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe UBM Stabilizer for NorTrak Runs!	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)

DRILLPIPE DATA

WEIGHT DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper							Total		
Lower							Below Jars		

vey Sensor to Bit (ft) Hole Drag: Up (x1000 lbs) Down (x1000 lbs)

Objective For Running BHA

BHA Results

Reason for POOH

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

DEPTH IN _____
 DEPTH OUT _____
 AVERAGE ANGLE _____
 OF DRILL _____

Monel Collar

Roller Reamer

CMS

UBHO

Sub - XO

Roller Reamer

Drill Collor -- Short

Float Sub

Bit

**COLUMBIA NATURAL
RESOURCES**

**CNR /DOE HORIZONTAL PROSPECT
MARTIN Co. KENTUCKY WELL #21747**

BH- 14

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 4745 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 5025 m

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe URM Stabilizer for NorTrak Runel	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)

DRILLPIPE DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)
Upper						
Lower						

WEIGHT DATA

BHA Weight (x1000 lbs)	In Air	In Mud
Total		
Below Jars		

Survey Sensor to Bit	35.0	ft	Hole Drag: Up	(x1000 lbs)	Down	(x1000 lbs)
----------------------	------	----	---------------	-------------	------	-------------

Objective For Running BHA DROP ANGLE

BHA Results

Reason for POOH

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

DEPTH IN _____
 DEPTH OUT _____
 AVERAGE ANGLE
 OF DRILL _____

Monel Collar

CMS

UBHO

Sub - XO

Roller Reamer

Drill Collor - Short

Roller Reamer

Float Sub

Bit

**COLUMBIA NATURAL
 RESOURCES**

**CNR /DOE HORIZONTAL PROSPECT
 MARTIN Co. KENTUCKY WELL #21747**

BH- 15

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 5025 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 6263 (m)

BIT DATA

[illegible]

COMPONENT DATA

[illegible]

STABILIZER DATA

Item No.	Stabilizer Description Describe UEM Stabilizer for No/Track Runal	Spiral	Blade Length (in)	Blade Width (in)	Gauge Length (in)	Gauge In (in)	Gauge Out (in)

DRILLPIPE DATA

Drillpipe	Grade	OD (in)	ID (in)	Wt/Ft (lbs/ft)	Conn.	Length (ft)	BHA Weight (x1000 lbs)	In Air	In Mud
Upper							Total		
Lower							Below Jars		

WEIGHT DATA

BHA Weight (x1000 lbs)	In Air	In Mud
Total		
Below Jars		

Survey Sensor to Bit	40.0	m	Hole Drag: Up	(x1000 lbs)	Down	(x1000 lbs)
----------------------	------	---	---------------	-------------	------	-------------

Effective For Running BHA HOLD ANGLE

Bi-HA Results

Reason for POOH

Page 1 of 1

EC Representative **GRIESEMER/MCDOWELL**

Appendix 3

Directional Control Summary Including Drill Pipe Stresses

Sta. Num.	H.D. Feet	Incl. Angle Deg.	Azi. Angle Deg.	Coordinates			Vert. Sec. Feet	Closure		Rate Change		Total D.L. Deg/100 Ft	TFO Deg.
		+N,-S Feet	+E,-W Feet	TVD Feet	Dist. Feet	Dire. Deg.		Incl. Deg/100 Ft	Azi. Deg/100 Ft				
1	3035	0.00	28.00	0	0	3035	0	0	0.0	0.00	0.00	0.0	
2	3053	2.80	28.00	0	0	3053	0	0	28.0	15.56	0.00	15.6	
3	3078	5.10	0.00	2	0	3078	2	2	13.6	9.20	112.00	11.8	
4	3108	8.60	347.00	6	-0	3108	5	6	359.9	11.67	43.33	12.7	
5	3140	12.20	343.00	11	-2	3139	11	11	352.1	11.25	12.50	11.5	
6	3171	15.40	340.00	18	-4	3169	18	19	347.8	10.32	9.68	10.6	
7	3202	18.30	338.00	27	-7	3199	27	27	344.9	9.35	6.45	9.5	
8	3233	20.70	336.00	36	-11	3228	38	38	342.7	7.74	6.45	8.0	
9	3264	23.20	333.00	46	-16	3257	49	49	340.8	8.06	9.68	8.8	
10	3300	26.40	336.00	60	-23	3290	64	64	339.3	8.89	8.33	9.6	
11	3331	29.60	339.00	74	-28	3317	79	79	339.0	10.32	9.68	11.3	
12	3362	33.20	341.00	89	-34	3343	95	95	339.2	11.61	6.45	12.1	
13	3392	36.90	342.00	105	-39	3368	112	112	339.5	12.33	3.33	12.5	
14	3423	40.50	343.00	124	-45	3392	131	131	340.0	11.61	3.23	11.8	
15	3488	45.20	350.00	167	-55	3440	175	175	341.7	7.23	10.77	10.3	
16	3519	45.30	349.00	188	-59	3462	197	197	342.5	0.32	3.23	2.3	
17	3550	45.80	346.00	210	-64	3483	219	219	343.0	1.61	9.68	7.1	
18	3531	46.30	345.00	231	-70	3505	241	242	343.3	1.61	3.23	2.8	
19	3610	49.70	344.00	252	-75	3524	263	263	343.4	11.72	3.45	12.0	
20	3641	53.30	344.00	276	-82	3543	287	287	343.4	13.55	0.00	13.5	
21	3672	57.40	345.00	300	-89	3561	312	313	343.5	11.29	3.23	11.6	
22	3703	62.30	348.00	326	-95	3577	339	340	343.7	15.81	9.68	17.9	
23	3734	66.40	350.00	354	-100	3590	367	368	344.1	13.23	6.45	14.4	
24	3765	71.00	351.00	382	-105	3601	395	396	344.6	14.84	3.23	15.1	
25	3796	75.20	347.00	411	-111	3610	424	426	344.9	13.55	12.90	18.3	
26	3855	75.70	347.00	467	-124	3625	481	483	345.2	0.85	0.00	0.9	
27	3886	75.30	348.00	496	-130	3633	511	513	345.3	-1.29	3.23	3.4	
28	3951	75.40	348.00	558	-143	3649	573	576	345.6	0.15	0.00	0.2	
29	3982	76.30	350.00	587	-149	3657	603	606	345.8	2.90	6.45	6.9	
30	4013	78.30	345.00	617	-156	3663	633	636	345.8	8.06	16.13	17.7	
31	4044	30.70	346.00	646	-163	3669	663	667	345.8	6.13	3.23	6.9	
32	4076	32.50	348.00	677	-170	3674	695	698	345.9	5.94	6.25	8.6	
33	4107	34.70	348.00	707	-177	3677	725	729	346.0	6.77	0.00	6.8	
34	4190	38.25	346.00	788	-195	3682	807	812	346.1	4.28	2.41	4.9	
35	4294	92.00	346.00	889	-221	3682	911	916	346.1	3.61	0.00	3.6	
36	4477	95.00	346.00	1066	-265	3671	1092	1098	346.1	1.64	0.00	1.6	
37	4700	96.00	351.00	1284	-309	3649	1312	1320	346.5	0.45	2.24	2.3	
38	4756	95.25	348.00	1338	-319	3644	1367	1376	346.6	-1.34	5.36	5.5	
39	4818	95.00	348.00	1399	-332	3638	1428	1438	346.6	-0.40	0.00	0.4	
40	4880	95.00	348.00	1459	-345	3633	1489	1499	346.7	0.00	0.00	0.1	
41	4942	93.75	350.00	1520	-357	3628	1550	1561	346.8	-2.02	3.23	3.8	
42	5066	91.75	350.00	1642	-378	3622	1672	1685	347.0	-1.61	0.00	1.6	
43	5128	89.00	350.00	1703	-389	3622	1733	1747	347.1	-4.44	0.00	4.4	
44	5252	86.75	351.00	1825	-409	3626	1855	1870	347.4	-1.81	0.81	2.0	
45	5376	85.00	351.00	1947	-429	3635	1976	1994	347.6	-1.41	0.00	1.4	
46	5500	84.00	351.00	2069	-448	3647	2098	2117	347.8	-0.81	0.00	0.8	
47	5624	83.50	350.00	2191	-468	3661	2219	2240	347.9	-0.40	0.81	0.9	
48	5686	82.25	350.00	2251	-479	3668	2279	2302	348.0	-2.02	0.00	2.0	
49	5748	82.25	350.00	2312	-490	3677	2340	2363	348.0	0.00	0.00	0.1	
50	5810	82.25	350.00	2372	-500	3685	2400	2424	348.1	0.00	0.00	0.1	
51	5872	82.25	350.00	2433	-511	3694	2461	2486	348.1	0.00	0.00	0.1	
52	5934	81.50	350.00	2493	-522	3702	2521	2547	348.2	-1.21	0.00	1.2	
53	5996	81.50	350.00	2554	-532	3711	2582	2608	348.2	0.00	0.00	0.1	
54	6120	81.50	350.00	2674	-554	3730	2702	2731	348.3	0.00	0.00	0.0	
55	6182	80.75	350.00	2735	-564	3739	2763	2792	348.3	-1.21	0.00	1.2	
56	6213	80.00	350.00	2765	-570	3745	2793	2823	348.4	-2.42	0.00	2.4	
57	6244	79.00	350.00	2795	-575	3750	2823	2853	348.4	-3.23	0.00	3.2	
58	6263	79.00	350.00	2813	-578	3754	2841	2872	348.4	0.00	0.00	0.3	

MEASURED DEPTH FEET	DRIFT ANGLE DEGREES	DRIFT AZIMUTH DEGREES	BUCKLING NORMAL FORCE	PIPE TENSION			ROTARY TORQUE	FRICTION COEFF.	PIPE WEIGHT #/FT	PIPE OD INCHES	PIPE ID INCHES	HOLE SIZE INCHES	BENDING STRESS PSI
				TRIP OUT	TRIP IN	ROTATE							
0	0.00	346.00	15487.68	110277	-95380	63816	6200	0.50	17.00	5.50	4.892	8.75	0
200	0.00	348.00	13837.26	106877	-89488	60416	6200	0.50	17.00	5.50	4.892	8.75	0
400	0.00	348.00	12523.87	103477	-84585	57016	6200	0.50	17.00	5.50	4.892	8.75	0
600	0.00	348.00	11464.49	100077	-80471	53616	6200	0.50	17.00	5.50	4.892	8.75	0
800	0.00	348.00	10599.93	96677	-76992	50216	6200	0.50	17.00	5.50	4.892	8.75	0
1000	0.00	348.00	9887.18	93277	-74032	46816	6200	0.50	17.00	5.50	4.392	8.75	0
1200	0.00	348.00	9294.37	89877	-71500	43416	6200	0.50	17.00	5.50	4.892	8.75	0
1400	0.00	348.00	8797.48	86477	-69323	40016	6200	0.50	17.00	5.50	4.892	8.75	0
1600	0.00	348.00	8378.18	83077	-67445	36616	6200	0.50	17.00	5.50	4.892	8.75	0
1800	0.00	348.00	8022.23	79677	-65818	33216	6200	0.50	17.00	5.50	4.892	8.75	0
2000	0.00	348.00	7718.47	76277	-64405	29816	6200	0.50	17.00	5.50	4.892	8.75	0
2200	0.00	348.00	7458.06	72377	-63174	26416	6200	0.50	17.00	5.50	4.892	8.75	0
2400	0.00	348.00	7233.90	69477	-62099	23016	6200	0.50	17.00	5.50	4.892	8.75	0
2600	0.00	348.00	7040.25	66077	-61158	19616	6200	0.50	17.00	5.50	4.892	8.75	0
2800	0.00	348.00	8045.82	62677	-60334	16216	6200	0.50	17.00	5.50	4.892	8.75	0
3025	0.00	388.00	580.74	58682	-59502	12221	6200	0.50	17.00	5.50	4.892	8.75	20347
3053	2.80	588.00	530.66	56988	-57762	11915	6128	0.50	17.00	5.50	4.892	8.75	15075
3078	5.10	560.00	502.60	55154	-56118	11491	6056	0.50	17.00	5.50	4.892	8.75	16690
3108	8.60	347.00	404.03	52911	-54124	10985	5972	0.50	17.00	5.50	4.892	8.75	15008
3140	12.20	343.00	299.08	50798	-52348	10450	5900	0.50	17.00	5.50	4.892	8.75	13835
3171	15.40	340.00	234.89	48948	-50861	9938	5844	0.50	17.00	5.50	4.892	8.75	12478
3202	18.30	338.00	189.13	47298	-49599	9434	5802	0.50	17.00	5.50	4.892	8.75	10511
3233	20.70	336.00	153.23	45888	-48612	8937	5774	0.50	17.00	5.50	4.892	8.75	11561
3264	23.20	333.00	137.67	44427	-47537	8448	5744	0.50	17.00	5.50	4.892	8.75	12493
3300	26.40	336.00	85.43	42709	-46203	7892	5713	0.50	17.00	5.50	4.892	8.75	14752
3331	29.60	339.00	58.13	41102	-44839	7427	5682	0.50	17.00	5.50	4.892	8.75	15813
3362	33.20	341.00	34.76	39493	-43394	6977	5656	0.50	17.00	5.50	4.892	8.75	16325
3392	36.90	342.00	19.83	37979	-41972	6560	5638	0.50	17.00	5.50	4.892	8.75	15417
3423	40.50	343.00	13.39	36565	-40623	6149	5627	0.50	17.00	5.50	4.892	8.75	13462
3488	45.20	350.00	2.82	34016	-38405	5338	5559	0.50	17.00	5.50	4.892	8.75	3026
3519	45.30	349.00	1.81	33385	-38385	4967	5513	0.50	17.00	5.50	4.392	8.75	9279
3550	45.80	346.00	1.40	32409	-37806	4598	5465	0.50	17.00	5.50	4.892	8.75	3698
3581	46.30	345.00	0.18	31836	-37660	4233	5422	0.50	17.00	5.50	4.892	8.75	15697
3610	49.70	344.00	0.00	30751	-36446	3903	5404	0.50	17.00	5.50	4.892	8.75	17721
3641	53.90	344.00	0.00	29550	-34986	3577	5385	0.50	17.00	5.50	4.892	8.75	15173
3672	57.40	345.00	0.00	28567	-33758	3279	5355	0.50	17.00	5.50	4.892	8.75	23393
3703	62.30	348.00	0.00	27184	-31926	3015	5325	0.50	17.00	5.50	4.892	8.75	18898
3734	66.40	350.00	0.00	26147	-30461	2787	5289	0.50	17.00	5.50	4.892	8.75	19803
3765	71.00	351.00	0.00	25165	-28942	2595	5253	0.50	17.00	5.50	4.892	8.75	23975
3796	75.20	347.00	0.00	23995	-27241	2442	5208	0.50	17.00	5.50	4.892	8.75	1108
3855	75.70	347.00	0.00	23359	-26770	2190	5089	0.50	17.00	5.50	4.892	8.75	4420
3886	75.30	348.00	0.00	22841	-26570	2058	5023	0.50	17.00	5.50	4.892	8.75	201
3951	75.40	348.00	0.00	22046	-26180	1779	4890	0.50	17.00	5.50	4.892	8.75	9021
3982	76.30	350.00	0.00	21543	-25555	1650	4829	0.50	17.00	5.50	4.892	8.75	23144
4013	78.80	345.00	0.00	20535	-24119	1536	4770	0.50	17.00	5.50	4.892	8.75	9028
4044	80.70	346.00	0.00	20251	-23400	1442	4711	0.50	17.00	5.50	4.892	8.75	11213
4076	82.60	348.00	0.00	19825	-22576	1363	4649	0.50	17.00	5.50	4.892	8.75	8861
4107	84.70	348.00	0.00	19668	-21840	1305	4590	0.50	17.00	5.50	4.892	8.75	6418
4190	88.25	346.00	0.00	19229	-20273	1218	4423	0.50	17.00	5.50	4.892	8.5	4716
4294	92.00	346.00	0.00	18969	-18483	1222	4212	0.50	17.00	5.50	4.892	8.5	2144
4477	95.00	346.00	0.00	18080	-15930	1412	3833	0.50	17.00	5.50	4.892	8.5	2978
4700	96.00	351.00	0.00	16559	-13071	1775	3365	0.50	17.00	5.50	4.892	8.5	7190
4756	95.25	348.00	0.00	15940	-12368	1869	3243	0.50	17.00	5.50	4.892	8.5	527
4818	95.00	348.00	0.00	15476	-11675	1963	3111	0.50	17.00	5.50	4.892	8.5	0
4880	95.00	348.00	0.00	15043	-10953	2055	2979	0.50	17.00	5.50	4.892	8.5	4965
4942	93.75	350.00	0.00	14396	-10332	2135	2842	0.50	17.00	5.50	4.892	8.5	2110
5066	91.75	350.00	0.00	13214	-9160	2236	2569	0.50	17.00	5.50	4.892	8.5	5802
5128	89.00	350.00	0.00	12396	-8773	2243	2424	0.50	17.00	5.50	4.892	8.5	2597
5252	86.75	351.00	0.00	11044	-7767	2165	2150	0.50	17.00	5.50	4.892	8.5	1846
5376	85.00	351.00	0.00	9694	-6781	2013	1879	0.50	17.00	5.50	4.892	8.5	1055
5500	84.00	351.00	0.00	8369	-5785	1811	1613	0.50	17.00	5.50	4.892	8.5	1174
5624	83.50	350.00	0.00	7060	-4781	1582	1349	0.50	17.00	5.50	4.892	8.5	2637

MEASURED DEPTH FEET	DRIFT ANGLE DEGREES	DRIFT AZIMUTH DEGREES	BUCKLING NORMAL FORCE	PIPE TENSION			ROTARY TORQUE	FRICTION COEFF.	PIPE WEIGHT #/FT	PIPE OD INCHES	PIPE ID INCHES	HOLE SIZE INCHES	BENDING STRESS PSI
				TRIP OUT	TRIP IN	ROTATE							
5686	82.25	350.00	0.00	6337	-4341	1451	1215	0.50	17.00	5.50	4.892	8.5	0
5748	82.25	350.00	0.00	5672	-3857	1309	1084	0.50	17.00	5.50	4.892	8.5	0
5810	82.25	350.00	0.00	5008	-3372	1167	954	0.50	17.00	5.50	4.892	8.5	0
5872	82.25	350.00	0.00	4344	-2888	1025	823	0.50	17.00	5.50	4.892	8.5	1582
5934	81.50	350.00	0.00	3649	-2430	876	691	0.50	17.00	5.50	4.892	8.5	0
5996	81.50	350.00	0.00	2972	-1960	720	561	0.50	17.00	5.50	4.892	8.5	0
6120	81.50	350.00	0.00	1618	-1021	408	300	0.50	17.00	5.50	4.892	8.5	1582
6182	80.75	350.00	0.00	929	-563	246	170	0.50	17.00	5.50	4.892	8.5	3165
6213	80.00	350.00	0.00	577	-342	158	105	0.50	17.00	5.50	4.892	8.5	4219
6244	79.00	350.00	0.00	220	-129	62	40	0.50	17.00	5.50	4.892	8.5	0
6263	79.00	350.00	0.00	0	0	0	0	0.50	17.00	5.50	4.892	8.5	4934

Appendix 4

Final Well Survey Record

SURVEY CALCULATION AND FIELD WORKSHEET

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES - 7

Job No. 0211-00001

Sidetrack No.

Page 1 of 3

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL WEISURVEY Section Name

Field Representative W A MCDOWELL

WELL DATA

Target TVD (FT) _____ Target Coord. N/S _____ Slot Coord. N/S _____ Grid Correction _____ 0.000 _____ Depths Measured From: RKB ☒ MSL ☐ SS
Target Description _____ Target Coord. EW _____ Slot Coord. EW _____ Magn. Declination _____ 4.890 _____ Calculation Method MINIMUM CURVATURE
Target Direction _____ (DM) _____ Build/Walk/DL per: 100ft ☒ 30m ☐ 10m ☐ Vert. Sec. Azim. _____ 348.00 _____ Magn. to Map Corr. _____ 4.890 _____ Map North to: TRUE NORTH

SURVEY DATA

Date	Survey Tool Type	Survey Depth (FT)	Incl. Angle (DM)	Hole Direction (DM)	Course Length (FT)	TVD (FT)	Vertical Section	Total Coordinate		DL (per 100 FT)	Build Rate Build (+) Drop (-)	Walk Rate Right (+) Left (-)	Comment
								N(+) / S(-) (FT)	E(+) / W(-) (FT)				
	MMS	2800.00	0 00	0 00		2800.00	0.00	0.00	0.00				TIE IN POINT
08-JUL-90	MMS	2982.00	2 00	205 00	182.00	2981.98	-2.54	-2.88	-1.34	1.10	1.10	0.00	
08-JUL-90	MMS	3044.00	1 45	58 00	82.00	3043.95	-3.05	-3.33	-1.01	5.83	-0.40	-240.32	
08-JUL-90	MMS	3108.00	2 45	32 00	62.00	3105.90	-1.82	-1.54	0.56	2.18	1.61	-38.71	
08-JUL-90	MMS	3168.00	9 00	347 00	62.00	3167.57	4.31	4.46	0.26	11.80	10.08	-72.58	
08-JUL-90	MMS	3230.00	15 00	342 00	62.00	3228.19	17.15	16.82	-3.32	9.81	9.68	-8.06	
08-JUL-90	MMS	3292.00	20 30	337 00	62.00	3287.22	35.80	34.46	-10.05	9.20	8.87	-8.06	
08-JUL-90	MMS	3354.00	28 00	337 00	62.00	3344.16	59.81	56.98	-19.60	8.87	8.87	0.00	
08-JUL-90	MMS	3416.00	33 00	343 00	62.00	3398.10	80.02	85.68	-29.87	12.24	11.29	9.68	
08-JUL-90	MMS	3478.00	40 30	345 00	62.00	3447.75	126.89	121.32	-40.03	12.25	12.10	3.23	
08-JUL-90	MMS	3540.00	45 00	346 00	62.00	3493.26	169.03	162.06	-50.55	7.34	7.26	1.61	
08-JUL-90	MMS	3602.00	45 00	346 00	62.00	3537.10	212.84	204.60	-61.15	0.00	0.00	0.00	
08-JUL-90	MMS	3664.00	48 30	345 00	62.00	3579.58	257.95	248.31	-72.47	5.77	5.65	-1.61	
08-JUL-90	MMS	3726.00	56 15	346 00	62.00	3617.40	306.97	295.82	-84.73	12.56	12.50	1.61	
08-JUL-90	MMS	3788.00	65 00	349 00	62.00	3647.79	360.94	348.52	-96.35	14.73	14.11	4.84	
08-JUL-90	MMS	3850.00	74 00	348 00	62.00	3669.48	418.95	405.37	-107.93	14.59	14.52	-1.61	
08-JUL-90	MMS	3912.00	75 00	347 00	62.00	3698.05	478.69	463.69	-120.87	2.24	1.61	-1.61	
08-JUL-90	MMS	3974.00	78 30	347 00	62.00	3701.31	538.77	522.24	-134.38	2.42	2.42	0.00	
08-JUL-90	MMS	4038.00	80 15	347 00	62.00	3713.80	599.48	581.40	-148.04	6.05	6.05	0.00	
08-JUL-90	MMS	4098.00	84 00	348 00	62.00	3722.29	660.86	641.11	-162.38	6.26	6.05	-1.61	
08-JUL-90	MMS	4160.00	87 00	346 00	62.00	3727.16	722.63	701.08	-177.33	4.84	4.84	0.00	
08-JUL-90	MMS	4190.00	88 15	346 00	36.50	3728.40	752.58	733.16	-184.58	4.17	4.17	0.00	
08-JUL-90	MMS	4200.00	88 45	346 00	10.33	3728.66	762.57	739.86	-187.00	5.00	5.00	0.00	
08-JUL-90	MMS	4260.00	91 00	345 00	60.00	3728.79	822.51	797.94	-202.02	4.10	3.75	-1.67

SURVEY CALCULATION AND FIELD WORKSHEET

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES - 7

Job No. 0211-00001

Sidetrack No.

Page 2 of 3

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL WEI

Survey Section Name

EC Representative W A MCDOWELL

WELL DATA

Target TVD (FT) _____ Target Coord. N/S _____ Slot Coord. N/S _____ Grid Correction 0.000 _____ Depths Measured From: RKB ☒ MSL ☐ SS ☐
Target Description _____ Target Coord. E/W _____ Slot Coord. E/W _____ Magn. Declination 4.890 _____ Calculation Method MINIMUM CURVATURE
Target Direction (DM) _____ Build/Walk/DL per: 100ft ☒ 30m ☐ 10m ☐ Vert. Sec. Azim. 348.00 _____ Magn. to Map Corr. 4.890 _____ Map North to: TRUE NORTH

SURVEY DATA

Date	Survey Tool Type	Survey Depth (FT)	Incl. Angle (DM)	Hole Direction (DM)	Course Length (FT)	TVD (FT)	Vertical Section	Total Coordinate		DL (Per 100 FT)	Build Rate Build (+) Drop (-)	Walk Rate Right (+) Left (-)	Comment
								N(+) / S(-) (FT)	E(+) / W(-) (FT)				
08-JUL-90	MMS	4322.00	93 00	348 00	62.00	3726.63	884.41	857.93	-217.54	3.61	3.23	1.61	
08-JUL-90	MMS	4394.00	93 45	345 00	62.00	3722.98	946.24	917.85	-233.03	2.01	1.21	-1.61	
08-JUL-90	MMS	4446.00	94 45	346 00	62.00	3718.39	1008.01	977.71	-248.51	2.28	1.61	1.61	
08-JUL-90	MMS	4508.00	95 00	348 00	62.00	3713.12	1089.75	1037.65	-263.46	0.40	0.40	0.00	
08-JUL-90	MMS	4570.00	95 15	347 00	62.00	3707.58	1131.48	1097.69	-277.87	1.66	0.40	1.61	
08-JUL-90	MMS	4632.00	95 15	347 00	62.00	3701.90	1193.21	1157.85	-291.76	0.00	0.00	0.00	
08-JUL-90	MMS	4694.00	95 15	347 00	62.00	3698.23	1254.94	1218.01	-305.65	0.00	0.00	0.00	
08-JUL-90	MMS	4756.00	95 15	348 00	62.00	3690.56	1318.68	1278.28	-319.01	1.61	0.00	1.61	
08-JUL-90	MMS	4818.00	95 00	348 00	62.00	3685.02	1376.43	1338.69	-331.85	0.40	-0.40	0.00	
08-JUL-90	MMS	4880.00	95 00	348 00	62.00	3679.62	1440.19	1399.10	-344.69	0.00	0.00	0.00	
08-JUL-90	MMS	4942.00	93 45	350 00	62.00	3674.89	1502.00	1459.78	-356.49	3.80	-2.02	3.23	
08-JUL-90	MMS	5066.00	91 45	350 00	124.00	3668.94	1625.77	1581.75	-377.99	1.61	-1.61	0.00	
08-JUL-90	MMS	5128.00	89 00	350 00	62.00	3668.53	1687.73	1642.80	-388.76	4.44	-4.44	0.00	
08-JUL-90	MMS	5252.00	86 45	351 00	124.00	3673.13	1811.52	1765.01	-409.21	1.99	-1.81	0.81	
08-JUL-90	MMS	5376.00	85 00	351 00	124.00	3682.05	1835.02	1887.16	-428.56	1.41	-1.41	0.00	
08-JUL-90	MMS	5500.00	84 00	351 00	124.00	3693.93	2058.28	2009.06	-447.87	0.81	-0.81	0.00	
08-JUL-90	MMS	5624.00	83 30	350 00	124.00	3707.43	2181.42	2130.64	-466.21	0.90	-0.40	-0.81	
08-JUL-90	MMS	5686.00	82 15	350 00	62.00	3715.12	2242.90	2191.22	-478.89	2.02	-2.02	0.00	
08-JUL-90	MMS	5748.00	82 15	350 00	62.00	3723.46	2304.30	2251.72	-489.56	0.00	0.00	0.00	
08-JUL-90	MMS	5810.00	82 15	350 30	62.00	3731.84	2385.69	2312.27	-499.96	0.80	0.00	0.81	
08-JUL-90	MMS	5872.00	82 15	350 00	62.00	3740.21	2427.07	2372.81	-510.37	0.80	0.00	-0.81	
08-JUL-90	MMS	5934.00	81 30	350 00	62.00	3748.97	2488.41	2433.26	-521.03	1.21	-1.21	0.00	
08-JUL-90	MMS	5996.00	81 30	350 00	62.00	3758.13	2549.69	2493.65	-531.67	0.00	0.00	0.00	
08-JUL-90	MMS	6120.00	81 30	350 00	124.00	3776.46	2672.26	2614.42	-552.97	0.00	0.00	0.00	

SURVEY CALCULATION AND FIELD WORKSHEET

Company COLUMBIA NATURAL RESOURCES

Job No. 0211-00001

Sidetrack No.

Page 3 of 3

Company COLUMBIA NATURAL RESOURCES

R/a Contractor & No. RAY RESOURCES - 7

Field

1

Well Name & No. FEDERAL GAS, OIL + COAL ;

Survey Section Name

EC Representative W A McDowell

EC Representative W A McDowell

EC Representative W A McDowell

WELL DATA

Target TVD	(FT)	Target Coord. N/S	Slot Coord. N/S	Grid Correction	0.000	Depth Measured From: RKB ☒ MSL ☐ S
Target Description		Target Coord. E/W	Slot Coord. E/W	Magn. Declination	4.890	Calculation Method <u>MINIMUM CURVATURE</u>
Target Direction	(DM)	Build/Walk/DL per: 100ft ☒ 30m ☐ 10m ☐	Vert. Sec. Azim.	Magn. to Map Corr.	4.890	Map North to: TRUE NORTH

SURVEY DATA

[illegible]

Appendix 5

Bottom Hole Assembly Performance Reports

Company COLUMBIA NATURAL RESOURCES

Rig Contractor & No. RAY RESOURCES 7

Depth In 3966 m

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL Field

Depth Out 3966 m

BIT DATA

Bit No.	Size (in)	Mfr.	Type	Gauge Length (in)	Nozzles (32nds) or TFA	Footage (ft)	Depth Out (ft)	ROP (Avg.) (min)	Dull Condition							
									IR	OR	DC	LOC	B/S	G/16	OC	R PLD
3R1	8 1/2	RTC	HP53A		3"20	0	3966									
BHA Total Footage								0.0	BHA ROP (Avg.)							

BOTTOM HOLE ASSEMBLY

[illegible]

OPERATIONAL DATA

Rotary Torque _____ Drag Up _____ (lbs) Mud Type _____ AIR PV/YP _____ 0/0
 Drag Dn. _____ (lbs) Mud Weight _____ (ppg) Solids (%) _____

	Inclination (dm)	Azimuth (dm)	TVD (ft)	MD (ft)	Defl. Tool BENT SUB	2.00 (deg)	Rotor Nozzle
In					Accum. Drill Hrs.	4.00	Accum. Circ. Hrs. 7.75 Prior Circ. Hrs. 22.75
Out					Lithology		

[illegible]

Objective For Running BHA: BUILD UP SECTION

Remarks / Results / BUR OF 15.8 TO 13.5

Page 1 of 1

EC Representative GRIESEMER/MCDOWELL

Appendix 6

Drilling Parameters

Appendix 7

Well Summary Graphs

WELL SUMMARY **COLUMBIA NATURAL RESOURCES** **FEDERAL GAS, OIL + COAL #21747** **MARTIN** **KENTUCKY**

DIRECTIONAL SUMMARY - MD
COLUMBIA NATURAL RESOURCES
FEDERAL GAS, OIL + COAL #21747
MARTIN
KENTUCKY

DIRECTIONAL SUMMARY - TVD **COLUMBIA NATURAL RESOURCES** **FEDERAL GAS, OIL + COAL #21747** **MARTIN** **KENTUCKY**

Appendix 8

Drilling Completion Summary

BIT RECORD

Job No. 211-00001

Company **COLUMBIA NATURAL RESOURCES**

Rig Contractor & No.	RAY RESOURCES / 7

Field

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL WELL

Platform / Pad

County / Area **MARTIN / COMMON DIST.**

State / Country KENTUCKY / USA

Township / Block	Range / Sub-Block	Mud Base (Oil or Water)	Spud Date
SEC 11 SN			

[illegible]

Company COLUMBIA NATURAL RESOURCES

Field

Beginning Date 14-JUN-90

Well Name & No. FEDERAL GAS, OIL + COAL #21747/CNR/DOE HORIZONTAL WELL

Ending Date 08-JUL-90

[illegible]

WELL TEST ANALYSIS REPORT (GAS)

WELL 21747 DRAWDOWN

22.7500	336.200	1.0828E+07	22.7500	943540.
23.0000	335.900	1.0808E+07	23.0000	963620.
23.2500	335.300	1.0768E+07	23.2500	1.0038E+06
23.5000	335.000	1.0748E+07	23.5000	1.0238E+06
23.7500	334.800	1.0734E+07	23.7500	1.0372E+06
24.0000	334.600	1.0721E+07	24.0000	1.0506E+06
24.5000	334.200	1.0694E+07	24.5000	1.0774E+06
25.0000	333.800	1.0667E+07	25.0000	1.1041E+06
25.5000	333.500	1.0647E+07	25.5000	1.1242E+06
26.0000	333.100	1.0620E+07	26.0000	1.1510E+06
26.5000	332.600	1.0587E+07	26.5000	1.1844E+06
27.0000	332.300	1.0567E+07	27.0000	1.2045E+06
27.5000	332.000	1.0547E+07	27.5000	1.2246E+06
28.0000	331.700	1.0527E+07	28.0000	1.2447E+06
29.0000	331.000	1.0484E+07	29.0000	1.2877E+06
30.0000	330.100	1.0429E+07	30.0000	1.3422E+06
31.0000	329.600	1.0399E+07	31.0000	1.3724E+06
32.0000	328.700	1.0345E+07	32.0000	1.4269E+06
33.0000	328.400	1.0326E+07	33.0000	1.4450E+06
34.0000	327.700	1.0284E+07	34.0000	1.4874E+06
35.0000	327.000	1.0242E+07	35.0000	1.5298E+06
36.0000	326.500	1.0211E+07	36.0000	1.5600E+06
38.0000	325.500	1.0151E+07	38.0000	1.6206E+06
40.0000	323.000	9.9996E+06	40.0000	1.7719E+06
42.0000	322.200	9.9512E+06	42.0000	1.8203E+06
44.0000	321.000	9.8785E+06	44.0000	1.8929E+06
46.0000	320.100	9.8241E+06	46.0000	1.9474E+06
48.0000	319.300	9.7756E+06	48.0000	1.9958E+06
50.0000	318.300	9.7151E+06	50.0000	2.0563E+06
52.0000	317.400	9.6606E+06	52.0000	2.1108E+06
54.0000	316.300	9.5941E+06	54.0000	2.1774E+06
56.0000	315.400	9.5396E+06	56.0000	2.2319E+06
58.0000	314.500	9.4851E+06	58.0000	2.2863E+06
60.0000	314.000	9.4549E+06	60.0000	2.3166E+06
66.0000	311.800	9.3217E+06	66.0000	2.4497E+06
72.0000	309.700	9.1946E+06	72.0000	2.5769E+06
78.0000	307.400	9.0554E+06	78.0000	2.7161E+06
84.0000	305.700	8.9525E+06	84.0000	2.8189E+06
90.0000	304.200	8.8617E+06	90.0000	2.9097E+06
96.0000	302.400	8.7528E+06	96.0000	3.0187E+06
102.000	301.200	8.6802E+06	102.000	3.0913E+06
108.000	299.300	8.5652E+06	108.000	3.2063E+06
114.000	297.700	8.4731E+06	114.000	3.2984E+06
120.000	297.000	8.4352E+06	120.000	3.3363E+06
126.000	295.400	8.3486E+06	126.000	3.4228E+06
132.000	294.200	8.2837E+06	132.000	3.4878E+06
138.000	293.200	8.2296E+06	138.000	3.5419E+06
142.000	291.200	8.1214E+06	142.000	3.6501E+06
154.000	290.200	8.0673E+06	154.000	3.7042E+06
166.000	288.200	7.9591E+06	166.000	3.8124E+06
168.000	288.000	7.9483E+06	168.000	3.8232E+06

168 hours - 200 Mcfd

Average rate = 197.6 Mcfd

GAS SAMPLE ANALYSIS

Information From Originator	Laboratory Results
Originated By: Name: C. J. Wiley Company: CNR Office: CCW Department: Reservior Engineering	Lab No.: 638 Cyl. No.: Date Received in Lab: 09 / 10 / 90
Report To: Name: Mike Friend Company: CNR Office: CCW Department: Reservior Engineer' Address: 900 Pennsylvania Ave. City: Charleston State/ZIP: WV 25362 Copies To: Mian Ahmad	Hydrocarbons, Mol Percent <u>79.297</u> Methane CH ₄ <u>13.268</u> Ethane C ₂ H ₆ <u>5.017</u> Propane C ₃ H ₈ <u>0.273</u> I-Butane C ₄ H ₁₀ <u>0.955</u> N-Butane C ₄ H ₁₀ Neopentane C ₅ H ₁₂ <u>0.103</u> I-Pentane C ₅ H ₁₂ <u>0.129</u> N-Pentane C ₅ H ₁₂ <u>0.080</u> Hexanes + C ₆ +
Purpose:	Other Components, Mol Percent ____ Hydrogen ____ Argon ____ Oxygen ____ Ethylene (PPM) ____ Sulfur Hex. (PPM) ____ Other ()
Laboratory Results Required (Check those required) ☒ Hydrocarbon Analysis _____ Odorant Level ☒ Inerts Analysis ☒ Relative Density _____ Sulfur Compounds ☒ Heating Value _____ Other: (Describe) _____	Inerts, Mol Percent <u>0.878</u> Nitrogen Carbon Dioxide
Sample Source Data: Meter No.: Sample Taken For (Check One): _____ Independent Producer _____ Planning Dept. _____ TCO Production _____ Annual/Semi DTH ☒ CNR Production _____ Qtr. Sample _____ Storage Dept. _____ Other () Producer: CNR Contract: Co Well No.: 21747 Permit No.(s): State: KY County: Martin Township/District: Farm Name: Other: (Be Specific)	Sulfur Compounds, GR.S/100 C.F. _____ Hydrogen Sulfide _____ Mercaptans _____ Mono-Sulfides _____ Di-Sulfides _____ Total Sulfur Odorant, Lb./MMCF H ₂ S, PPM Volume
	Relative Density: 0.6972 (Specific Gravity) BTU/CF, Gross, Sat: 1200.7 BTU/CF, Gross, Dry: Utilization Fact.: BTU/CF, Net, Sat:
Information From Field	
Sample Line Data: Gas Temp., Deg. F.: 60 Pressure, PSIG: 246 Sample Cylinder Data: Final Cylinder Pressure, PSIG: 100 Location Operation/Maintenance No.: Time and Date Taken: 11:00 AM/PM on 09 / 07 / 90 Date Shipped or Taken to Lab: 09 / 10 / 90 Other Remarks: Sample Taken By: C. J. Wiley (Signature)	Note: BTU and relative density factors are from A.G.A. Report No. 3, Sept. 1985. All reported values are at 14.73, psia, 60° Deg. F. Reported By: KL Date: 09 / 10 / 90 Lab: JA

WELL TEST ANALYSIS REPORT (GAS)			
WELL 21747 BUILDUP			
LOCATION			
County/District	MARTIN	State	KENTUCKY
Division	SOUTHWEST		
Well Name	D.O.E. HORIZONTAL SHALE WELL		
Company	COLUMBIA NATURAL RESOURCES		
COMPLETION			
Field	BIG SANDY	Zone/Sand	DEVONIAN SHALE
FLUID PROPERTIES			
Gas Specific Gravity	0.6972	Bg, bbl/Mscf	7.51
Viscosity, cp	1.104e-2	Ct, 10 ⁻⁶ psi	3029
Pseudo-critical T, R	380.4	Pseudo-critical P, psi	663.2
Mole Fraction N2	8.779e-3		
RESERVOIR PROPERTIES			
Porosity	1e-2	Formation Thickness, ft	725
Wellbore Radius, ft	0.3646		
WELL TEST INFORMATION			
Type of Test	Build-up	Date of test	Sept. 7, 1990
Directory/Path	d:\mikedta\	Main Data file	21747B.MAI
Pressure Data file	21747B.PRS	Pseudo-Pressure file	21747B.PSU
Rate Data file	21747B.FLR	Gauge Depth	3580 md
WELLBORE ESTIMATES			
Storage, bbl/psi	5.875	Cd	1798
CDe2s	0.1839	Fracture half width, ft	143.6
Skin Factor	-4.594	DeltaP across skin, psi	-192.5
Pwf, psi	287.7	Flow Efficiency	3.948
RESERVOIR ESTIMATES			
Permeability, md	7.615e-2	Semi-log slope, 'm'	48.25
Eff. Producing T, hrs	168	Lambda	2e-2
BOUNDARY ESTIMATES			
Duration of Trans., hrs	289.9	Radius of Invest., ft	260
R of closed circle, ft	242.4		
PRESSURE ESTIMATES			
p*, psia	353	z at p*	0.9418
p bar, psia	353	z	0.9418
p/z, psia	374.8		

WELL 21747 BUILDUP

WELL TEST ANALYSIS REPORT (GAS)

WELL 21747 BUILDUP

RATE AND PRESSURE DATA

RATE HISTORY

T of start	MSCF/day
0.00000	197.600
168.000	0.00000

PRESSURE HISTORY

T, hrs	P, psia	m(P)	Deltat	(T+dT)/dT	Deltam(P)
168.000		7.9320E+06			
168.083	287.700	7.9320E+06	0.08299	2025.28	0.00000
168.166	289.200	8.0132E+06	0.16600	1013.05	81155.0
168.250	291.200	8.1214E+06	0.25000	673.000	189361.
168.330	291.700	8.1484E+06	0.33000	510.088	216413.
168.416	292.200	8.1755E+06	0.41600	404.846	243464.
168.500	292.700	8.2026E+06	0.50000	337.000	270516.
168.750	293.200	8.2296E+06	0.75000	225.000	297567.
169.000	293.700	8.2567E+06	1.00000	169.000	324619.
169.250	293.700	8.2567E+06	1.25000	135.400	324619.
169.500	293.700	8.2567E+06	1.50000	113.000	324619.
169.750	294.200	8.2837E+06	1.75000	97.0000	351671.
170.000	294.200	8.2837E+06	2.00000	85.0000	351671.
170.500	294.700	8.3108E+06	2.50000	68.2000	378722.
171.000	295.700	8.3649E+06	3.00000	57.0000	432825.
171.500	295.700	8.3649E+06	3.50000	49.0000	432825.
172.000	296.700	8.4190E+06	4.00000	43.0000	486928.
172.500	296.700	8.4190E+06	4.50000	38.3333	486928.
173.000	297.200	8.4460E+06	5.00000	34.6000	513980.
174.000	298.200	8.5001E+06	6.00000	29.0000	568083.
175.000	299.200	8.5591E+06	7.00000	25.0000	627066.
176.000	299.700	8.5894E+06	8.00000	22.0000	657329.
177.000	300.200	8.6196E+06	9.00000	19.6667	687591.
178.000	301.200	8.6802E+06	10.0000	17.8000	748116.
179.000	301.700	8.7104E+06	11.0000	16.2727	778378.
180.000	302.700	8.7709E+06	12.0000	15.0000	838902.
188.000	307.200	9.0433E+06	20.0000	9.40000	1.1113E+06
198.000	312.200	9.3459E+06	30.0000	6.60000	1.4139E+06
208.000	316.700	9.6183E+06	40.0000	5.20000	1.6862E+06
218.000	320.700	9.8604E+06	50.0000	4.36000	1.9283E+06
228.000	323.700	1.0042E+07	60.0000	3.80000	2.1099E+06
238.000	326.700	1.0224E+07	70.0000	3.40000	2.2915E+06
248.000	329.200	1.0375E+07	80.0000	3.10000	2.4428E+06
258.000	331.200	1.0496E+07	90.0000	2.86667	2.5639E+06
268.000	332.200	1.0560E+07	100.000	2.68000	2.6282E+06
278.000	333.700	1.0661E+07	110.000	2.52727	2.7286E+06
302.000	334.200	1.0694E+07	134.000	2.25373	2.7620E+06
308.000	336.700	1.0861E+07	140.000	2.20000	2.9293E+06
316.000	337.200	1.0895E+07	148.000	2.13514	2.9628E+06

WELL TEST ANALYSIS REPORT (GAS)

WELL 21747 BUILDUP

323.000	338.200	1.0962E+07	155.000	2.08387	3.0297E+06
328.000	338.700	1.0995E+07	160.000	2.05000	3.0632E+06
333.000	339.200	1.1029E+07	165.000	2.01818	3.0966E+06
338.000	340.200	1.1096E+07	170.000	1.98824	3.1636E+06
343.000	340.700	1.1129E+07	175.000	1.96000	3.1970E+06
348.000	341.300	1.1169E+07	180.000	1.93333	3.2372E+06
353.000	341.700	1.1196E+07	185.000	1.90811	3.2639E+06
358.000	342.700	1.1263E+07	190.000	1.88421	3.3308E+06
363.000	343.300	1.1303E+07	195.000	1.86154	3.3710E+06
368.000	343.800	1.1336E+07	200.000	1.84000	3.4045E+06
373.000	344.300	1.1370E+07	205.000	1.81951	3.4379E+06
378.000	344.700	1.1397E+07	210.000	1.80000	3.4647E+06
383.000	345.300	1.1437E+07	215.000	1.78140	3.5048E+06
388.000	345.700	1.1464E+07	220.000	1.76364	3.5316E+06
398.000	346.400	1.1510E+07	230.000	1.73043	3.5784E+06
408.000	347.400	1.1577E+07	240.000	1.70000	3.6454E+06
413.000	347.700	1.1597E+07	245.000	1.68571	3.6654E+06
418.000	348.400	1.1644E+07	250.000	1.67200	3.7123E+06
423.000	348.400	1.1644E+07	255.000	1.65882	3.7123E+06

Horner producing time = 168

WELL 21747 BUILDUP

Horner plot

WELL 21747 BUILDUP

Appendix 9

CTC External Casing Packer

CTC External Casing Packers

Five 10 ft., 5-1/2 in., 23 #/ft., N80 PAYZONE™ Inflatable Formation Packers were installed on July 12, 1990. The top of the rubber elements were positioned at 3533 ft., 4181 ft., 4736 ft., 5117 ft., and 5549 ft. measured depths using the pipe tally. The true vertical depths of the top of the rubber elements in the hole with maximum deviation of 96° are 3471 ft., 3681 ft., 3646 ft., 3622 ft., and 3653 ft. respectively.

Inflation of the top packer with 2 % KCL water was attempted on July 12. The packer would not hold pressure, indicating it must have been damaged during run-in. The bottom four packers were successfully inflated with 2% KCL water using an RTTS on July 31.

The packers were inflated as follows:

<u>Measured Packer Depth</u>	<u>Inflation Volume</u>	<u>Equivalent Average Hole Size</u>	<u>Total Inflation Pressure</u>
3533 ft.	0-damaged during run-in	0	0
4181 ft.	0.2 bbls.	8-1/2 in.	1000 psi plus annulus pressure
4736 ft.	0.35 bbls.	9-1/4 in.	1000 psi plus annulus pressure
5117 ft.	0.25 bbls.	8-3/4 in.	1000 psi plus annulus pressure
5549 ft.	Unknown - inflated while trying to free coiled tubing	Unknown	1000 psi plus annulus pressure

The attached pressure charts, well schematic, job log, debriefing report, and data sheet provide a description of the installation.

Columbia Natural Resources

Pocamontas Development Corporation #21747

Big Sandy Field - martin Co., KY

2. Casing_Press PSI
 3. Slurry Rate 1 BPM
 4. Slurry Total 1 EBL
 5. None

07-30-90

Columbia Natural Resources

4265 San Felipe, Suite 400
Houston, Texas 77027
Ph: (713) 961-3336

DATE 07-12-90

COMPANY Columbia Natural Resources LOCATION Big Sandy Field
Pocahantas Dev. Corp. Martin County, Kentucky
WELL #21747 M.D.

WELL SCHEMATIC		CASING	SIZE	WEIGHT	GRADE	THREAD	DEPTH
		CASING	9 5/8	36	J-55		2954.00
			5 1/2	17	N-80	LT&C	6013.93
DESCRIPTION OF EQUIPMENT AND SERVICES							LENGTH
5 1/2 casing to surface							3281.75
2954.00' Shoe of 9 5/8							
3281.75' Top of F.O. Cementer							5.50
5 jts. + 1 pup jt.							231.45
3518.70' Top of HOS Cementer							3.58
packer lift sub							10.65
3532.93' Top of rubber element							10.18
3543.11' Bottom of rubber element							
packer pin + 1 jt							47.68
3590.79' Top of latch down landing collar							0.94
8 jts.							354.10
3945.83' Top of F.O. cementer							5.50
5 jts. + packer lift sub							229.34
4180.67' Top of rubber element							10.24
4190.91' Bottom of rubber element							
7 jts. + packer pin							310.63
4501.54' Top of F.O. Cementer							5.50
5 jts. + packer lift sub							229.40
4736.44' Top of rubber element							10.22
4746.66' Bottom of rubber element							
3 jts. + packer pin							134.73
4881.39' Top of F.O. cementer							5.50
5 jts. + packer lift sub							230.34
5117.23' Top of rubber element							10.25
5127.48' Bottom of rubber element							
4 jts. + packer pin + 1 pup jt.							184.84
5312.32' Top of F.O. cementer							5.50
5 jts. + packer lift sub							231.42
5549.24' Top of rubber element							10.23
5559.47' Bottom of rubber element							
PREPARED BY							TOTAL LENGTH
9-8

DATE 07-12-90

COMPANY Columbia Natural Resources **LOCATION** _____

WELL _____

WELL SCHEMATIC

[illegible]

Columbia Natural Resources
#21747

JOB LOG

07/12/90

0730 hrs.	Start casing in hole
0830 hrs.	1st packer in hole
0945 hrs.	2nd packer in hole
1015 hrs.	3rd packer in hole
1045 hrs.	4th packer in hole
1130 hrs.	5th packer in hole
1510 hrs.	Casing at desired depth
1530 hrs.	Mix KCL water
1647 hrs.	Test lines to 4000 psi
1650 hrs.	Drop plug
1653 hrs.	Displace with 2% KCL water
1724 hrs.	Bump plug @ 84 bbls. KCL water to 400 psi
	Calculated displacement = 83.3 bbls. KCL water

INFLATION SEQUENCE
Balance Pressure = -1500 psi

	<u>PRESSURE(psi)</u>	<u>VOLUME(bbls)</u>
1724 hrs.	400	0
1726 hrs.	400	
1726 hrs.	800	0.1
1727 hrs.	800	
1727 hrs.	950	0.1
1728 hrs.	950	
1728 hrs.	1050	0.2
1729 hrs.	1050	
1729 hrs.	1100	0.2
1730 hrs.	1100	
1730 hrs.	1250 - open packer	0.25
1731 hrs.	0	
1731 hrs.	400	1.00
1732 hrs.	0	
1732 hrs.	400	1.50
1733 hrs.	0	
1733 hrs.	400	2.00
1734 hrs.	0	
1744 hrs.	0	6.00

Packer not holding pressure

1923 hrs. Drop closing plug
1935 hrs. Pumped 41 bbls. - catch up with fluid - open HOS @ 2200 psi
1948 hrs. Bump plug - close HOS

07/30/90

0850 hrs. Make up Halliburton SIP tool
0855 hrs. Run SIP plus 60 ft. drill pipe
0900 hrs. Test SIP tool to 4100 psi
0905 hrs. Continue running 2-7/8 in. drill pipe
1230 hrs. SIP tool @ 5550 ft. - 5559 ft. - rig up coiled tubing
1345 hrs. Start in hole with coiled tubing
1445 hrs. Coiled tubing on bottom - stuck
1525 hrs. Test lines to 4500 psi
1532 hrs. Start filling coiled tubing and drill pipe with 2% KCL water
1550 hrs. Stop pumps after 10 bbls - pull on coiled tubing - stuck
1608 hrs. Continue filling drill pipe
1700 hrs. Pumped total 30 bbls - no circulation - calculated circulated volume = 25 bbls.
1710 hrs. Rig up on 2-7/8 in. x 1 in. annulus
1720 hrs. Start pumping down annulus
1726 hrs. 16 bbls. filled tubing
1736 hrs. Pull on coiled tubing - stuck
1738 hrs. Try to free coiled tubing by increasing rate - 5500 psi @ 2-1/2 bpm - think we inflated packer
1740 hrs. Shut down after pumping 35 bbls.
1741 hrs. Release pressure to 0 psi
1742 hrs. Rig down Halliburton
1800 hrs. Pull coiled tubing free
1830 hrs. Out of hole with coiled tubing
1900 hrs. Start out of hole with SIP tool

07/31/90

0900 hrs. Start in hole with Halliburton RTTS
1055 hrs. Set RTTS @ 5538 ft. - above packer
1113 hrs. Test lines to 3000 psi - leak

1121 hrs. Re-test lines to 3000 psi - good test
1125 hrs. Start filling drill pipe
1143 hrs. Pumped 25 bbls. KCL water - no pressure - calculated volume
= 25 bbls. - RTTS not set
1146 hrs. Move RTTS to 5598 ft. - below packer
1206 hrs. Start filling drill pipe - took 7 bbls.
1207 hrs. Test RTTS and bridge plug to 2800 psi - holding
1224 hrs. Start pulling RTTS above packer
1230 hrs. Set RTTS @ 5475 ft.
1237 hrs. Start filling drill pipe - took 9 bbls.
1244 hrs. Start pressuring up on bottom packer
1256 hrs. Pressure to 3000 psi - holding - packer inflated 7/30/90 while
trying to free coiled tubing
1258 hrs. Release pressure to 0 psi
1310 hrs. Start moving RTTS
1338 hrs. Set RTTS @ 4977 ft.
1340 hrs. Start filling drill pipe - took 8 bbls.
1353 hrs. Open packer @ 1400 psi
1354 hrs. Packer full
1355 hrs. 1400 psi - holding
1358 hrs. Release pressure to 0 psi
1420 hrs. Start moving RTTS
1430 hrs. Set RTTS @ 4603 ft.
1434 hrs. Start filling drill pipe - took 7 bbls.
1445 hrs. Open packer @ 1400 psi
1446 hrs. Packer full
1448 hrs. 1600 psi - holding
1449 hrs. Release pressure to 0 psi
1453 hrs. Start moving RTTS
1513 hrs. Set RTTS @ 4042 ft.
1518 hrs. Start filling drill pipe - took 6 bbls.
1528 hrs. Open packer @ 1400 psi
1529 hrs. Packer full
1531 hrs. 1400 psi - holding
1532 hrs. Release pressure to 0 psi

Completion Tool Company

4265 San Felipe, Suite 400 Houston, Texas 77027 USA
713/961-3336 Telex 775-781 Telefax 713/961-3302

PAYZONE™ DATA SHEET

Date 07-12-90

Company Columbia Naturat Resources Lease Pocahontas Dev. Corp. #21747

Co. Representative Charlie Bellinger, Larry Friend

Field Big Sandy Location Martin County Kentucky

1.0 OPEN HOLE

1.1 Total Measured Depth	<u>6263</u>
1.2 Drilled Diameter	<u>8 3/4 to 4053 8 1/2 to 6263</u>
1.3 Calipered Diameter	<u>8 1/2 - 9 1/2</u>
1.4 Angle	<u>96° max - pkrs. 46° - 96°</u>
1.5 Mud Weight	<u>Air drilled</u>
1.6 Lost Circulation Zones	<u>-</u>
1.7 Dog Legs	<u>180/100' max</u>
1.8 Washouts	<u>Some</u>
1.9 Junk in Hole	<u>-</u>

2.0 LAST CASING RUN

2.1 Size	<u>9 5/8</u>
2.2 Weight	<u>36</u>
2.3 Grade	<u>J-55</u>
2.4 Shoe Depth	<u>2954</u>
2.5 Dog Legs	<u>-</u>
2.6 Damage	<u>-</u>

3.0 CASING PLAN

3.1 Size	<u>5 1/2</u>
3.2 Weight	<u>17</u>
3.3 Grade	<u>N-80</u>
3.4 Thread Type	<u>LT&C</u>
3.5 Setting Depth	<u>6013.93</u>

4.0 RESERVOIR CHARACTERISTICS

4.1 Formation Type	
4.1.0 Carbonate	<u></u>
4.1.1 <u>Sand/Shale</u>	<u>X</u>
4.2 Fracture Pressure	<u>1200</u>
4.3 Reservoir Pressure	<u>300-500</u>
4.4 Characteristic Production Problems	<u></u>

5.0 INSTALLATION OBJECTIVE(S)

5.1 Sand Control	<u></u>
5.2 Zone Isolation	<u>X</u>
5.3 Protect Cement Sensitive Formation	<u></u>
5.4 Seal Lost Circulation Zone	<u></u>
5.5 Other	<u></u>

6.0 PAYZONE PACKER

	<u>Length</u> (ft)	<u>Serial No.</u>	<u>Setting Depth</u> (ft)	<u>Calipered Hole Size</u> (in)
No. 1	<u>10</u>	<u>E681PC</u>	<u>3532.93']</u> <u>3543.11']</u>	<u>9 3/4</u>
No. 2	<u>10</u>	<u>E675PC</u>	<u>4181.67']</u> <u>4190.91']</u>	<u>8 1/2</u>
No. 3	<u>10</u>	<u>E683PO</u>	<u>4736.44']</u> <u>4746.66']</u>	<u>9 1/4</u>
No. 4	<u>10</u>	<u>E680PC</u>	<u>5117.23']</u> <u>5127.48']</u>	<u>8 3/4</u>
No. 5	<u>10</u>	<u>E682PC</u>	<u>5549.24']</u> <u>5559.47']</u>	<u>8 1/2</u>

7.0 CASING DATA**7.1 Internal Yield PSI**

7740

7.2 Capacity bbl/ft

0.0232

7.3 Capacity ft/bbl

43.01

8.0 PRIMARY CEMENT PROPERTIES

No primary cement

8.1 Lead slurry and additives**8.2 Number sacks****8.3 Weight lb/gal****8.4 Yield ft³/sk****8.5 Water req. gal/sk****8.6 Pump time****8.7 Water loss cc/30 min****8.8 Total mix water barrels****8.9 Total Lead Slurry Barrels****8.10 Tail slurry + additives****8.11 Number sacks****8.12 Weight #/gal****8.13 Yield ft³/sk****8.14 Water req. gal/sk****8.15 Pump time****8.16 Water loss cc/30 min****8.17 Total mix water barrels****8.18 Total Tail Slurry Barrels**

9.0 INFLATION CEMENT REQUIREMENTS

9.1	Top or upper packer Expected inflation volume-barrels	0.45 bbls. for 9 3/4" hole
9.2	Volume top of packer to float collar + 200 ft. barrels	(+) _____
9.3	Total required cement volume-barrels	_____
9.4	Inflation slurry + additives	Inflate pkr w/ 3% KCL Water _____
9.5	Number sacks	_____
9.6	Weight lb/gal	_____
9.7	Yield ft ³ /sk	_____
9.8	Water req gal/sk	_____
9.9	Pump time	_____
9.10	Water loss cc/30 min	_____
9.11	Total mix water barrels	_____
9.12	<u>Total Inflation Slurry Barrels</u>	_____
9.13	Cement footage above packer-feet	_____
9.14	Cement volume above packer-barrels	_____

10.0 DISPLACEMENT CALCULATIONS

10.1	Latch Down Total displacement- float collar depth <u>.3590.79</u> X capacity <u>.0232</u> -barrels	83.32
10.2	Less inflation cement volume-barrels	(-) 0
10.3	<u>Net Displacement Required-barrels</u>	<u>83.31</u>

11.0 CRITICAL DISPLACEMENT VOLUME

11.1 Knock-off rods - packer depth
_____ X capacity _____ -barrels

Knock-off rods knocked off
upper packer before run
bottom 4 packers were run
with knock off rods in place

11.2 Less primary cement
volume-barrels

(-) _____

11.3 Less inflation cement
volume-barrels

(-) _____

11.4 Rods knocked off At-barrels

(Negative value indicates that rods are knocked off before
displacement begins.)

12.0 ANNULUS BOTTOM HOLE PRESSURE

Air Drilled

12.1 Mud height _____ X gradient _____
- psi

12.2 Plus spacer height _____
X gradient _____ - psi

(+) _____

12.3 Plus lead cement height _____ X
gradient _____ - psi

(+) _____

12.4 Plus tail cement height _____
X gradient _____ - psi

(+) _____

12.5 Theoretical Annular Bottom
Hole Pressure-psi

0 _____

T.V.D.
C
top
packer

13.0 CASING BOTTOM HOLE PRESSURE (before inflation)

Water

8.4 13.1 ~~Mud~~ height 3471 X gradient .4368
- psi

1516

13.2 Plus spacer height _____
X gradient _____ - psi

(+) _____

13.3 Plus inflation cement
height _____ X gradient _____ - psi

(+) _____

13.4 Plus tail cement height _____ X
gradient _____ - psi

(+) _____

13.5 Theoretical Casing Bottom Hole
Pressure - psi

1516

14.0 THEORETICAL BALANCE PRESSURE

14.1 Annular bottomhole pressure-psi	0
14.2 Minus casing bottomhole pressure-psi	(-) 1516
14.3 <u>Balance Pressure - psi</u>	- 1516

T.V.D.
@
top
packer

15.0 PACKER LOADING (Expected Pre-Job)

15.1 Hydrostatic @ packer - psi	1516
8.4 height <u>3471</u> X gradient <u>.4368</u>	1000 I.C.V.
height _____ X gradient _____	
height _____ X gradient _____	
15.2 Final surface inflation pressure - psi	(+) 0
15.3 <u>Total Pressure - psi</u>	1000
15.4 Gradient: Total pressure <u>1000</u> /depth <u>3471</u>	0.29

16.0 RADIAL EFFECTIVE STRESS (Expected Pre-Job)

16.1 Packer loading - psi	Not applicable Water inflated
16.2 Minus pore pressure - psi	(-) _____
16.3 <u>Seal Load - psi</u>	_____

17.0 PACKER LOADING (Actual - Post Job)

17.1 Hydrostatic @ Packer - psi	
height _____ X gradient _____	
height _____ X gradient _____	
height _____ X gradient _____	
17.2 Final surface inflation pressure - psi	(+) _____
17.3 <u>Total Pressure - psi</u>	0 packer damaged during run in
17.4 Gradient: Total pressure _____ /depth _____	_____

18.0 RADIAL EFFECTIVE STRESS (Actual - Post Job)

18.1 Packer loading - psi _____

18.2 Minus pore pressure - psi (-) _____

18.3 Seal Load - psi _____

19.0 POST JOB

	No. 1	To be inflated at later date			
		No.2	No. 3	No.4	No. 5
19.1 Shear pin setting - psi	<u>2600</u>	<u>2600</u>	<u>2600</u>	<u>2600</u>	<u>2600</u>
19.2 Sheared @ - psi	<u>2600</u>	_____	_____	_____	
19.3 Inflation control setting - psi	<u>1000</u>	<u>1000</u>	<u>1000</u>	<u>1000</u>	<u>1000</u>

19.4 Net Inflation Volume

Top packer = 0 damaged during run-in

19.5 Comments: _____

Appendix 10

FO Completion Tool Operation

FO Completion Tool Operation

The FO completion tool is a full opening, tubing or drill pipe operated tool run as an integral part of the casing string. It features an enclosed shifting mechanism that controls the force necessary to operate a sliding valve. Since the operating mechanism is totally enclosed, it is protected from cementing materials, solids in fracturing fluids as well as tools that may be run through it.

The tool parts, initially plugged with a ceramic-aluminum material to prevent plugging during cementing and running operations, were easily removed with a nonabrasive fluid during the hydra-jetting operations.

Specially designed seals provide a means of isolating high pressures when the valve is in the closed position. This external design also provides reliable sealing during multiple opening and closing operations. The valve is pressure balanced at all times.

The hydra-jet positioner serves three functions: 1) to shift the FO valve to the open or closed position; 2) to remove the ceramic wafers placed in the tool during manufacturing; and 3) to clean cement residue or other debris from the ID of the tool that could prevent proper shifting of the valve.

A continuous J-slot track in the OD of the positioner mandrel allows the positioner to be run to any selected FO completion tool and operate the valve as required. When the valve is in the open position, the jets are automatically positioned in line radially with each row of fluid parts in the completion tool. A swivel assembly allows easy rotation of the pipe during jetting operations.

Lab tests performed by Halliburton Services, in Duncan, Oklahoma indicate it is probable that the cement sheath between the tool formation will also be penetrated during the jetting operations, thus exposing the formation.

The FO completion tool provides a positive means of opening and closing production ports after the casing is landed. When run in combination with ECP's, as in the lateral section of this well, each zone may be independently tested and treated.

Appendix 11

Mud Log Show Data

Appendix 11

Mud Log Shows Well 21747 Martin County, KY

<u>Measured Depth</u>	<u>Hot Wire Gas</u>	<u>Connection Gas</u>
3073		22
3097		55
3125		74
3127	36	
3156		55
3161	2	
3187		41
3223	14	
3251		120
3254	7	
3265	401	
3282		790
3284	165	
3312		400
3320	60	
3348		400
3379		300
3409		380
3440		240
3470	30	
3479		240
3492	75	
3510		400
3541		600
3560	75	
3574		960
3628		750
3659		700
3690	60	
3719		760
3729	45	
3750		780
3768	195	
3780		800
3811		800
3840	135	

Appendix 11 cont 'd.

**Mud Log Shows
Well 21747
Martin County, KY**

<u>Measured Depth</u>	<u>Hot Wire Gas</u>	<u>Connection Gas</u>
3842		650
3860	30	
3880	150	
3904		900
3932		900
3946	150	
3965		760
3998		880
4029		800
4040	120	
4059		680
4092		1000
4102	340	
4123		800
4167		1300
4196		800
4260		1600
4280	100	
4290		1680
4306	60	
4320		1600
4352		720
4380	25	
4392		1000
4414		1100
4442		1300
4476	50	
4476		1280
4507		680
4538		1200
4540	100	
4552	50	
4578		1040
4610		1120
4640		1000

Appendix 11 cont'd.

**Mud Log Shows
Well 21747
Martin County, KY**

<u>Measured Depth</u>	<u>Hot Wire Gas</u>	<u>Connection Gas</u>
4670		1240
4670	100	
4776		1240
4808		1160
4825	50	
4840		1200
4850	50	
4870	200	
4872		1330
4876	400	
4898	150	
4901		1480
4964		1520
4994		1400
5024		1500
5052		800
5083		720
5115		720
5146		700
5175		760
5236		740
5242	50	
5268		740
5298		800
5329		740
5362		680
5424		780
5448	25	
5456		1040
5485		720
5517		1400
5548		800
5580		780
5610		720

Appendix 11 cont 'd.

**Mud Log Shows
Well 21747
Martin County, KY**

<u>Measured Depth</u>	<u>Hot Wire Gas</u>	<u>Connection Gas</u>
5622	25	680
5643		530
5670		510
5702		630
5738		800
5797		
5815	175	960
5829		1000
5860		800
5890		780
5920		
5950	25	740
5954		800
5985		800
6015		820
6047		780
6078		760
6109		740
6140		740
6171		740
6203		720
6232		

Appendix 12

**Well Test Analysis - Zone 1
Joshi Technologies International, Inc.**

WELL TEST ANALYSIS
CNR-DOE WELL 21747

Prepared for:
COLUMBIA NATURAL RESOURCES
October 28, 1990

Prepared by:
Wenzhong Ding, Ph.D.
JOSHI TECHNOLOGIES INTERNATIONAL, INC.
5801 East 41st Street, Suite 603
Tulsa, Oklahoma 74135

SUMMARY

This report summarizes the well test analysis results for CNR-DOE Well 21747. The report also describes the corresponding calculation procedures.

Both drawdown and buildup data show well defined early-time radial flow period (Radial flow in the vertical plane perpendicular to the wellbore). Analyzing these early-time radial flow period gives:

DRAWDOWN:

Permeability	$\sqrt{k_h k_v} = 0.045 \text{ md}$
Mechanical Skin	$s = -4.3$

BUILDUP:

Permeability	$\sqrt{k_h k_v} = 0.045 \text{ md}$
Mechanical Skin	$s = -4.5$

Note that results obtained from drawdown and buildup are consistent. The negative skin factor could be caused by hole enlargement or fractures near wellbore. Due to insufficient information we are not able to determine individual k_h and k_v values. Assuming an isotropic permeability gives $k_h = k_v = 0.045 \text{ md}$. Drawdown and buildup data do not show pseudoradial flow. Calculations indicate that based on permeability of $k_h = 0.045 \text{ md}$ it will take approximately 441 days to reach pseudoradial flow.

PROCEDURES AND CALCULATIONS

1. DRANDOWN ANALYSIS

Fig. 1 is a log-log plot of pseudopressure drop $m(p_i) - m(p_{wf})$ versus time. This plot clearly shows that wellbore storage effects, which would be characterized by a unit slop straight line, are negligible.

Fig. 2 is a semilog plot of wellbore pseudopressure $m(p_{wf})$ versus producing time. Note this is not a constant rate production, the average flow rate of first 22-hour production is 104.9 Mscf/day while the average flow rate of the remaining production period is 211.6 Mscf/day. Thus, Fig. 2 cannot be used for drawdown analysis, instead, superposition should be used.

Fig. 3 is obtained by using superposition where $[m(p_i) - m(p_{wf})]/q_2$ is plotted versus superposition time $[\log(t_1) - q_1/q_2 \log(t - t_1)]$ ($q_1 = 104.9$ Mscf/day, $q_2 = 211.6$ Mscf/day, $t_1 = 22$ hours). There is a well-defined straight line. We believe that this straight line corresponds to the early-time radial flow period in vertical plane. The slope of this straight line is $m = 2.94 \times 10^4$ psi²-day/cp-Mscf. Calculations based on this straight line are given below.

1). Flow capacity

$$\sqrt{k_h k_v} L = \frac{1637T}{m} = \frac{1637 \times (460 + 120)}{2.94 \times 10^4} = 32.3 \text{ md-ft}$$

$$\sqrt{k_h k_v} = \sqrt{k_h k_v} L / L = 32.3 / 725 = 0.045 \text{ md}$$

2). Mechanical skin factor

$$\left. \frac{\Delta m(p)}{q_2} \right|_{\text{ext.}} = 2.46 \times 10^4$$

$$s = 1.151 \left[\frac{\left. \frac{\Delta m(p)}{q_2} \right|_{\text{ext.}}}{m} - \log \left(\frac{\sqrt{k_h k_v}}{\phi (\mu c_t)_i r_w^2} \right) + 3.23 \right]$$

$$= 1.151 \left[\frac{-2.46 \times 10^4}{2.94 \times 10^4} - \log \left(\frac{0.045}{0.02 \times 3.06 \times 10^{-5} \times 0.23^2} \right) + 3.23 \right]$$

$$= -4.3$$

This negative skin factor may be caused by hole enlargement or fractures near the wellbore.

3) According to literature, the early-time radial flow ends at time equal to t_{e1} where

$$t_{e1} = \frac{1800 d_z^2 \phi \mu c_t}{k_z} = \frac{1800 \times 100^2 \times 0.02 \times 3.06 \times 10^{-5}}{0.045} = 244.8 \text{ hours}$$

This result indicates that the straight line shown on Fig. 3 indeed represents early-time radial flow. In the above equation d_z is the smallest distance between the wellbore and top or bottom boundary which is 100 feet.

Literature also show that the pseudoradial flow occurs if the producing time $t \geq t_{s3}$ where t_{s3} is defined as

$$t_{s3} = \frac{1480L^2\phi\mu c_t}{k_h}$$

For the case considered here, t_{s3} is given by

$$t_{s3} = \frac{1480 \times 725^2 \times 0.02 \times 3.06 \times 10^{-5}}{0.045} = 10580 \text{ hours}$$

$$= 441 \text{ days}$$

which means that pseudoradial flow can be reached after by producing for approximately 441 days due to low permeability.

2. BUILDUP ANALYSIS

Fig. 4 is a log-log plot of $\Delta m(p)$ versus shut in time Δt . Again wellbore storage effects are negligible. Fig. 5 is a Horner Plot which shows a semilog straight line. The semilog straight line corresponds to the early-time radial flow in the vertical plane.

$$m = 6.24 \times 10^6 \text{ psi}^2/\text{cp}/\log$$

1) Flow capacity

$$\sqrt{k_h k_v} L = \frac{1637 q_2 T}{m} = \frac{1637 \times 211.6 \times (460 + 120)}{6.24 \times 10^6} = 32.4 \text{ md-ft}$$

$$\sqrt{k_h k_v} = 32.4 / 725 = 0.045 \text{ md}$$

2) Mechanical skin factor

$$m(p) \Big|_{\text{ext.}} = 1.68 \times 10^6 \text{ psi}^2/\text{cp}$$

$$m(p_{wf.s}) = 7.932 \times 10^6 \text{ psi}^2/\text{cp}$$

$$\begin{aligned} s &= 1.151 \left[\frac{m(p) \Big|_{\text{ext.}} - m(p_{wf.s})}{m} - \log \left(\frac{\sqrt{k_h k_v}}{\phi (\mu c_t)_i r_w^2} \right) + 3.23 \right] \\ &= 1.151 \left[\frac{1.68 \times 10^6 - 7.932 \times 10^6}{2.65 \times 10^5} - \log \left(\frac{0.045}{0.02 \times 3.06 \times 10^{-5} \times 0.23^2} \right) + 3.23 \right] \\ &= -4.5 \end{aligned}$$

DRAWDOWN ANALYSIS CNR-DOE WELL 21747

Figure 1

DRAWDOWN ANALYSIS CNR-DOE WELL 21747

Figure 2

DRAWDOWN ANALYSIS CNR-DOE WELL 21747

Figure 3

BUILDUP ANALYSIS CNR-DOE WELL 21747

Figure 4

BUILDUP ANALYSIS CNR-DOE WELL 21747

Figure 5

Appendix 13

Well Test Analysis - Zone 1 Using Garrett Computing Systems Inc. Software

WELL TEST ANALYSIS REPORT (GAS)			
WELL 21747 DRAWDOWN			
LOCATION			
County/District	MARTIN	State	KENTUCKY
Division	SOUTHWEST		
Well Name	D.O.E. HORIZONTAL SHALE WELL		
Company	COLUMBIA NATURAL RESOURCES		
COMPLETION			
Field	BIG SANDY	Zone/Sand	DEVONIAN SHALE
Casing Size	5.5		
FLUID PROPERTIES			
Gas Specific Gravity	0.6972	Bg, bbl/Mscf	7.51
Viscosity, cp	1.104e-2	Ct, 10^-6 psi	3029
Pseudo-critical T, R	380.4	Pseudo-critical P, psi	663.2
Mole Fraction N2	8.779e-3		
RESERVOIR PROPERTIES			
Porosity	1e-2	Formation Thickness, ft	725
Wellbore Radius, ft	0.3646		
WELL TEST INFORMATION			
Type of Test	Drawdown	Directory/Path	d:\mikedta\
Main Data file	21747D.MAI	Pressure Data file	21747D.PRS
Pseudo-Pressure file	21747D.PSU	Rate Data file	21747D.FLR
Gauge Depth	3580 MD		
WELLBORE ESTIMATES			
Date	AUGUST 31, 1990	Type fracture	NATURAL
Fracture half width, ft	124.3	Skin Factor	-4 .65
DeltaP across skin, psi	-175.6	Pwf, psi	288
RESERVOIR ESTIMATES			
Permeability, md	8.877e-2	Semi-log slope, 'm'	44.3
Lambda	2e-2		
BOUNDARY ESTIMATES			
Duration of Trans., hrs	168	Radius of Invest., ft	213.7
R of closed circle, ft	333.9		
PRESSURE ESTIMATES			
p bar, psia	0		

Post-It™ brand fax transmittal memo 7671

of pages 15

To	Greg Koyan	From	Mike
Cc			CRK
Dep	Marble Cliff	Phone #	
Fax #		Fax #	

WELL 21747 DRAWDOWN

WELL 21747 DRAWDOWN

Miller-Dyes-Hutchinson plot

WELL 21747 DRAWDOWN

WELL 21747 DRAWDOWN

WELL TEST ANALYSIS REPORT (GAS)

WELL 21747 DRAWDOWN

RATE AND PRESSURE DATA

RATE HISTORY

T of start	MSCF/day
0.00000	104.000
22.0000	211.500

PRESSURE HISTORY

T, hrs	P, psia	m(P)	DeltaT	Deltam(P)
0.00000		1.1771E+07		
0.00000	350.300	1.1771E+07	0.00000	0.00000
0.01600	350.000	1.1751E+07	0.01600	20080.0
0.06600	349.900	1.1745E+07	0.06600	26770.0
0.16600	349.400	1.1711E+07	0.16600	60230.0
0.25000	349.000	1.1684E+07	0.25000	87000.0
0.33300	348.900	1.1678E+07	0.33300	93690.0
0.50000	348.500	1.1651E+07	0.50000	120450.
0.75000	348.400	1.1644E+07	0.75000	127150.
1.00000	348.300	1.1638E+07	1.00000	133840.
1.25000	348.200	1.1631E+07	1.25000	140530.
1.75000	348.100	1.1624E+07	1.75000	147220.
2.00000	347.900	1.1611E+07	2.00000	160610.
2.50000	347.800	1.1604E+07	2.50000	167300.
3.00000	347.700	1.1597E+07	3.00000	173990.
4.50000	346.700	1.1531E+07	4.50000	240910.
5.00000	346.400	1.1510E+07	5.00000	260980.
5.50000	346.200	1.1497E+07	5.50000	274360.
6.00000	345.900	1.1477E+07	6.00000	294440.
7.00000	345.700	1.1464E+07	7.00000	307820.
8.00000	345.500	1.1450E+07	8.00000	321210.
9.00000	345.400	1.1444E+07	9.00000	327900.
10.0000	345.200	1.1430E+07	10.0000	341280.
12.0000	344.700	1.1397E+07	12.0000	374740.
14.0000	344.200	1.1363E+07	14.0000	408200.
16.0000	343.800	1.1336E+07	16.0000	434970.
18.0000	343.200	1.1296E+07	18.0000	475120.
20.0000	342.400	1.1243E+07	20.0000	528650.
22.0000	342.200	1.1229E+07	22.0000	542030.
22.0160	341.600	1.1189E+07	22.0160	582190.
22.0330	341.200	1.1163E+07	22.0330	608950.
22.0500	340.900	1.1142E+07	22.0500	629030.
22.0660	340.600	1.1122E+07	22.0660	649100.
22.0830	340.100	1.1089E+07	22.0830	682560.
22.1660	338.900	1.1009E+07	22.1660	762860.
22.2500	337.900	1.0942E+07	22.2500	829780.
22.3300	337.100	1.0888E+07	22.3300	883310.
22.4160	336.800	1.0868E+07	22.4160	903390.
22.5000	336.600	1.0855E+07	22.5000	916770.

Appendix 14

Well Test Analysis - Zone 2 Using Garrett Computing Systems Inc. Software

WELL TEST ANALYSIS REPORT (GAS)			
well no. 21747 martin co., ky dev. shale - zone 2			
LOCATION			
Well Name	821747	County/District	MARTIN
State	KY	Company	CNR
Division	SOUTHWEST		
Well Location		DOE HORIZONTAL WELL	
COMPLETION			
Field	BIG SANDY	Zone/Sand	DEV. SHALE
Casing Size	5-1/2	Total Depth	TD 6263
Tubing shoe Depth	TVD 3754	Packer Depth	5538
Packer Type	CTC #1	Interval(s)	FO #A @ 5312
Frac. job done on	10/1/90		
FLUID PROPERTIES			
Gas Specific Gravity	0.7158	Bg, bbl/Msof	7.144
Viscosity, cp	1.096e-2	Ct, 10^-6 psi	2872
Pseudo-critical T, R	364.6	Pseudo-critical P, psi	647.8
Mole Fraction N2	0.101		
RESERVOIR PROPERTIES			
Porosity	1e-2	Formation Thickness, ft	432
Wellbore Radius, ft	0.3646		
WELL TEST INFORMATION			
Type of Test	Drawdown	Date of test	10/9/90
Directory/Path	d:\automate\	Main Data file	horz2d.mai
Pressure Data file	horz2d.prs	Pseudo-Pressure file	horz2d.psu
Rate Data file	horz2d.flr	Total Duration	146 HRS
Gauge Depth	3300		
WELLBORE ESTIMATES			
Storage, bbl/psi	0.6419	Cd	347.8
CDe2s	1413	Type fracture	STRAIGHT N2
Fracture half width, ft	12.81	Skin Factor	0.7011
DeltaP across skin, psi	4.593	Pwf, psi	303.8
Flow Efficiency	0.9281		
RESERVOIR ESTIMATES			
Permeability, md	0.8523	Semi-log slope, 'm'	7.343
Omega	0.5202	Lambda	5.16e-6
BOUNDARY ESTIMATES			
Duration of Trans., hrs	146	Radius of Invest., ft	636.2
R of closed circle, ft	340.2	L to closed fault, ft	141.8
L to ConstP line, ft	141.8		
PRESSURE ESTIMATES			
p*, psia	367.7	z at p*	0.9455
p bar, psia	367.7	z	0.9455
p/z, psia	388.9		

Enclosure 1

Mud Logging Report

WELL TEST ANALYSIS REPORT (GAS)

well no. 21747 martin co., ky dev. shale - zone 2

RATE AND PRESSURE DATA

RATE HISTORY

T of start	MSCF/day
0.00000	218.160

PRESSURE HISTORY

T, hrs	P, psia	m(P)	DeltaT	Deltam(P)
0.00000		1.3045E+07		
0.00000	367.630	1.3045E+07	0.00000	0.00000
0.01600	367.130	1.3009E+07	0.01600	35950.0
0.03300	366.010	1.2929E+07	0.03300	116480.
0.05000	364.240	1.2801E+07	0.05000	243740.
0.06600	361.960	1.2637E+07	0.06600	407670.
0.08300	360.550	1.2536E+07	0.08300	509050.
0.16600	354.980	1.2144E+07	0.16600	901400.
0.25000	350.670	1.1861E+07	0.25000	1.1846E+06
0.33300	347.280	1.1638E+07	0.33300	1.4073E+06
0.41600	344.490	1.1455E+07	0.41600	1.5906E+06
0.50000	342.320	1.1312E+07	0.50000	1.7331E+06
0.75000	338.120	1.1036E+07	0.75000	2.0090E+06
1.00000	335.540	1.0867E+07	1.00000	2.1785E+06
1.25000	333.560	1.0736E+07	1.25000	2.3086E+06
1.50000	331.790	1.0620E+07	1.50000	2.4249E+06
1.75000	330.620	1.0543E+07	1.75000	2.5018E+06
2.00000	330.070	1.0507E+07	2.00000	2.5379E+06
2.50000	328.140	1.0380E+07	2.50000	2.6647E+06
3.00000	326.880	1.0298E+07	3.00000	2.7475E+06
3.50000	326.070	1.0244E+07	3.50000	2.8007E+06
4.00000	325.510	1.0208E+07	4.00000	2.8375E+06
4.50000	324.960	1.0172E+07	4.50000	2.8736E+06
5.00000	324.600	1.0148E+07	5.00000	2.8973E+06
5.50000	324.240	1.0124E+07	5.50000	2.9209E+06
6.00000	323.890	1.0101E+07	6.00000	2.9438E+06
7.00000	323.280	1.0065E+07	7.00000	2.9801E+06
8.00000	322.780	1.0035E+07	8.00000	3.0098E+06
9.00000	322.370	1.0011E+07	9.00000	3.0342E+06
10.0000	322.020	9.9901E+06	10.0000	3.0550E+06
11.0000	321.710	9.9717E+06	11.0000	3.0734E+06
12.0000	321.460	9.9568E+06	12.0000	3.0883E+06
13.0000	321.150	9.9384E+06	13.0000	3.1067E+06
14.0000	320.950	9.9265E+06	14.0000	3.1186E+06
15.0000	320.750	9.9146E+06	15.0000	3.1305E+06
16.0000	320.450	9.8968E+06	16.0000	3.1483E+06
17.0000	320.140	9.8784E+06	17.0000	3.1667E+06
18.0000	319.990	9.8694E+06	18.0000	3.1757E+06
19.0000	319.840	9.8605E+06	19.0000	3.1846E+06
20.0000	319.640	9.8486E+06	20.0000	3.1965E+06

WELL TEST ANALYSIS REPORT (GAS)

well no. 21747 martin co., ky dev. shale - zone 2

21.0000	319.440	9.8368E+06	21.0000	3.2083E+06
22.0000	319.280	9.8272E+06	22.0000	3.2179E+06
23.0000	319.030	9.8124E+06	23.0000	3.2327E+06
24.0000	318.820	9.7999E+06	24.0000	3.2452E+06
25.0000	318.620	9.7880E+06	25.0000	3.2571E+06
26.0000	318.520	9.7821E+06	26.0000	3.2630E+06
27.0000	318.370	9.7731E+06	27.0000	3.2720E+06
28.0000	318.320	9.7702E+06	28.0000	3.2749E+06
29.0000	317.970	9.7494E+06	29.0000	3.2957E+06
30.0000	317.870	9.7434E+06	30.0000	3.3017E+06
31.0000	317.660	9.7309E+06	31.0000	3.3142E+06
32.0000	317.410	9.7161E+06	32.0000	3.3290E+06
33.0000	317.260	9.7072E+06	33.0000	3.3379E+06
34.0000	317.050	9.6947E+06	34.0000	3.3504E+06
35.0000	316.900	9.6858E+06	35.0000	3.3593E+06
36.0000	316.700	9.6739E+06	36.0000	3.3712E+06
37.0000	316.550	9.6650E+06	37.0000	3.3801E+06
38.0000	316.350	9.6531E+06	38.0000	3.3920E+06
39.0000	316.090	9.6376E+06	39.0000	3.4075E+06
40.0000	315.990	9.6317E+06	40.0000	3.4134E+06
42.0000	315.590	9.6079E+06	42.0000	3.4372E+06
44.0000	315.390	9.5960E+06	44.0000	3.4491E+06
46.0000	314.980	9.5716E+06	46.0000	3.4735E+06
48.0000	314.770	9.5592E+06	48.0000	3.4859E+06
54.0000	314.020	9.5146E+06	54.0000	3.5305E+06
60.0000	313.310	9.4724E+06	60.0000	3.5727E+06
66.0000	312.350	9.4153E+06	66.0000	3.6298E+06
72.0000	311.790	9.3820E+06	72.0000	3.6631E+06
78.0000	311.080	9.3398E+06	78.0000	3.7053E+06
84.0000	310.470	9.3036E+06	84.0000	3.7415E+06
90.0000	309.920	9.2709E+06	90.0000	3.7742E+06
96.0000	309.150	9.2251E+06	96.0000	3.8200E+06
108.000	308.890	9.2096E+06	108.000	3.8355E+06
120.000	307.280	9.1139E+06	120.000	3.9312E+06
132.000	305.920	9.0331E+06	132.000	4.0120E+06
140.000	305.510	9.0087E+06	140.000	4.0364E+06
146.000	303.840	8.9095E+06	146.000	4.1356E+06

well no. 21747 martin co., ky dev. shale - zone 2

Miller-Oyes-Hutchinson plot

well no. 21747 martin co., ky dev. shale - zone 2

well no. 21747 martin co., ky dev. shale - zone 2

Miller-Dyes-Hutchinson plot

well no. 21747 martin co., ky dev. shale - zone 2

Miller-Dyes-Hutchinson plot

well no. 21747 martin co., ky dev. shale - zone 2

Miller-Dyes-Hutchinson plot

WELL TEST ANALYSIS REPORT (GAS)			
WELL NO. 21747 DRAWDOWN - DUAL POROSITY MODEL ZONE 2			
LOCATION			
Well Name	821747	County/District	MARTIN
State	KY	Company	CNR
Division	SOUTHWEST		
Well Location		DOE HORIZONTAL WELL	
COMPLETION			
Field	BIG SANDY	Zone/Sand	DEV. SHALE
Casing Size	5-1/2	Total Depth	TD 6263
Tubing shoe Depth	TVD 3754	Packer Depth	5538
Packer Type	CTC #1	Interval(s)	FO #A @ 5312
Frac. job done on	10/1/90		
FLUID PROPERTIES			
Gas Specific Gravity	0.7158	Bg, bbl/Mscf	7.144
Viscosity, cp	1.096e-2	Ct, 10^-6 psi	2872
Pseudo-critical T, R	364.6	Pseudo-critical P, psi	647.8
Mole Fraction N2	0.101		
RESERVOIR PROPERTIES			
Porosity	1e-2	Formation Thickness, ft	432
Wellbore Radius, ft	0.3646		
WELL TEST INFORMATION			
Type of Test	Drawdown	Date of test	10/9/90
Directory/Path	D:\AUTOMATE\	Main Data file	horz2d.mai
Pressure Data file	horz2d.prs	Pseudo-Pressure file	horz2d.psu
Rate Data file	horz2d.flr	Total Duration	146 HRS
Gauge Depth	3300		
WELLBORE ESTIMATES			
Storage, bbl/psi	0.6479	Cd	351
CDe2s	24.55	Type fracture	STRAIGHT N2
Fracture half width, ft	9.935	Skin Factor	-1.33
DeltaP across skin, psi	-12.48	Pwf, psi	303.8
Flow Efficiency	1.195		
RESERVOIR ESTIMATES			
Permeability, md	0.5948	Semi-log slope, 'm'	10.81
Omega	0.2152	Lambda	1.576e-5
BOUNDARY ESTIMATES			
Duration of Trans., hrs	146	Radius of Invest., ft	531.5
R of closed circle, ft	340.2	L to closed fault, ft	145.9
L to ConstP line, ft	145.9		
PRESSURE ESTIMATES			
p*, psia	367.7	z at p*	0.9455
p bar, psia	367.7	z	0.9455
p/z, psia	388.9		

well no. 21747 martin co., ky dev. shale - zone 2

Miller-Dyes-Hutchinson plot

well no. 21747 martin co., ky dev. shale - zone 2

Miller-Dyes-Hutchinson plot

well no. 21747 martin co., ky dev. shale - zone 2

Miller-Dyes-Hutchinson plot

E1-13

well no. 21747 martin co., ky dev. shale - zone 2

WELL TEST ANALYSIS REPORT (GAS)			
WELL NO. 21747 BUILD-UP TEST DEV. SHALE - ZONE 2			
LOCATION			
Well Name	821747	County/District	MARTIN
State	KY	Company	CNR
Division	SOUTHWEST		
Well Location		DOE HORIZONTAL WELL	
COMPLETION			
Field	BIG SANDY	Zone/Sand	DEV. SHALE
Casing Size	5-1/2	Total Depth	TD 6263
Tubing shoe Depth	TVD 3754	Packer Depth	5538
Packer Type	CTC #1	Interval(s)	FO #A @ 5312
Frac. job done on	10/1/90		
FLUID PROPERTIES			
Gas Specific Gravity	0.7158	Bg, bbl/Mscf	7.023
Viscosity, cp	1.097e-2	Ct, 10^-6 psi	2828
Pseudo-critical T, R	364.6	Pseudo-critical P, psi	647.8
Mole Fraction N2	0.101		
RESERVOIR PROPERTIES			
Porosity	1e-2	Formation Thickness, ft	432
Wellbore Radius, ft	0.3646		
WELL TEST INFORMATION			
Type of Test	Build-up	Date of test	10/15/90
Directory/Path	d:\automate\	Main Data file	HORZ2B.MAI
Pressure Data file	HORZ2B.PRS	Pseudo-Pressure file	HORZ2B.PSU
Rate Data file	HORZ2B.FLR	Gauge Depth	3300
WELLBORE ESTIMATES			
Storage, bbl/psi	0.907	Cd	499.1
CDA?*	3.248e-2	Date	10/1/90
Type fracture	STRAIGHT N2	Fracture half width, ft	25.78
Skin Factor	-4.82	DeltaP across skin, psi	-251
Pwf, psi	303.8	Flow Efficiency	3.885
RESERVOIR ESTIMATES			
Permeability, md	0.1035	Semi-log slope, 'm'	59.96
Eff. Producing T, hrs	146	Omega	1.581e-2
Lambda	5.695e-5		
BOUNDARY ESTIMATES			
Duration of Trans., hrs	210	Radius of Invest., ft	270.4
R of closed circle, ft	331.5	L to closed fault, ft	145.8
L to ConstP line, ft	145.8		
PRESSURE ESTIMATES			
p*, psia	390.8	z at p*	0.9422
p bar, psia	390.8	z	0.9422
p/z, psia	414.8		

WELL TEST ANALYSIS REPORT (GAS)

WELL NO. 21747 MARTIN CO., KY DEV. SHALE - ZONE 2

RATE AND PRESSURE DATA

RATE HISTORY

T of start MSCF/day

0.00000 218.160

146.000 0.00000

PRESSURE HISTORY

T, hrs	P, psia	m(P)	DeltaT	(T+dT)/dT	Deltam(P)
146.000		8.9095E+06			
146.016	303.990	8.9184E+06	0.01601	9122.31	8915.00
146.033	304.350	8.9398E+06	0.03300	4424.60	30316.0
146.050	305.770	9.0242E+06	0.05000	2920.82	114723.
146.066	306.980	9.0961E+06	0.06599	2213.31	186649.
146.083	308.500	9.1865E+06	0.08299	1760.19	277001.
146.166	313.460	9.4813E+06	0.16600	880.516	571834.
146.250	317.810	9.7399E+06	0.25000	585.000	830408.
146.333	322.170	9.9990E+06	0.33299	439.448	1.0896E+06
146.416	325.710	1.0221E+07	0.41600	351.961	1.3113E+06
146.500	328.190	1.0384E+07	0.50000	293.000	1.4742E+06
146.750	334.220	1.0780E+07	0.75000	195.667	1.8704E+06
147.000	337.710	1.1009E+07	1.00000	147.000	2.0997E+06
147.250	340.390	1.1185E+07	1.25000	117.800	2.2757E+06
147.500	342.420	1.1319E+07	1.50000	98.3333	2.4091E+06
147.750	343.840	1.1412E+07	1.75000	84.4286	2.5024E+06
148.000	344.900	1.1481E+07	2.00000	74.0000	2.5720E+06
148.500	345.860	1.1545E+07	2.50000	59.4000	2.6351E+06
149.000	346.570	1.1591E+07	3.00000	49.6667	2.6817E+06
149.500	347.080	1.1625E+07	3.50000	42.7143	2.7152E+06
150.000	347.480	1.1651E+07	4.00000	37.5000	2.7415E+06
150.500	347.990	1.1684E+07	4.50000	33.4444	2.7750E+06
151.000	348.240	1.1701E+07	5.00000	30.2000	2.7914E+06
151.500	348.490	1.1717E+07	5.50000	27.5455	2.8079E+06
152.000	348.650	1.1728E+07	6.00000	25.3333	2.8184E+06
153.000	349.160	1.1761E+07	7.00000	21.8571	2.8519E+06
154.000	349.160	1.1761E+07	8.00000	19.2500	2.8519E+06
155.000	349.660	1.1794E+07	9.00000	17.2222	2.8847E+06
156.000	350.830	1.1871E+07	10.0000	15.6000	2.9616E+06
157.000	350.980	1.1881E+07	11.0000	14.2727	2.9715E+06
158.000	351.230	1.1897E+07	12.0000	13.1667	2.9879E+06
159.000	351.530	1.1917E+07	13.0000	12.2308	3.0076E+06
160.000	351.890	1.1941E+07	14.0000	11.4286	3.0312E+06
161.000	352.090	1.1954E+07	15.0000	10.7333	3.0444E+06
162.000	352.350	1.1971E+07	16.0000	10.1250	3.0615E+06
163.000	352.350	1.1971E+07	17.0000	9.58823	3.0615E+06
164.000	352.700	1.1994E+07	18.0000	9.11111	3.0845E+06
165.000	352.900	1.2007E+07	19.0000	8.68421	3.0976E+06
166.000	353.610	1.2054E+07	20.0000	8.30000	3.1442E+06

WELL TEST ANALYSIS REPORT (GAS)

WELL NO. 21747

MARTIN CO., KY DEV. SHALE - ZONE 2

167.000	353.660	1.2057E+07	21.0000	7.95238	3.1475E+06
168.000	353.910	1.2073E+07	22.0000	7.63636	3.1639E+06
169.000	354.010	1.2080E+07	23.0000	7.34783	3.1705E+06
170.000	354.420	1.2107E+07	24.0000	7.08333	3.1975E+06
171.000	354.570	1.2117E+07	25.0000	6.84000	3.2073E+06
172.000	354.830	1.2134E+07	26.0000	6.61538	3.2244E+06
173.000	354.930	1.2140E+07	27.0000	6.40741	3.2310E+06
174.000	354.930	1.2140E+07	28.0000	6.21429	3.2310E+06
175.000	355.230	1.2160E+07	29.0000	6.03448	3.2507E+06
176.000	355.480	1.2177E+07	30.0000	5.86667	3.2671E+06
177.000	355.530	1.2180E+07	31.0000	5.70968	3.2704E+06
178.000	355.890	1.2203E+07	32.0000	5.56250	3.2940E+06
179.000	356.040	1.2213E+07	33.0000	5.42424	3.3039E+06
180.000	356.190	1.2223E+07	34.0000	5.29412	3.3137E+06
181.000	356.750	1.2263E+07	35.0000	5.17143	3.3534E+06
182.000	356.500	1.2245E+07	36.0000	5.05556	3.3354E+06
183.000	356.750	1.2263E+07	37.0000	4.94595	3.3534E+06
184.000	357.050	1.2284E+07	38.0000	4.84211	3.3749E+06
185.000	357.150	1.2292E+07	39.0000	4.74359	3.3821E+06
186.000	357.310	1.2303E+07	40.0000	4.65000	3.3936E+06
188.000	357.660	1.2328E+07	42.0000	4.47619	3.4188E+06
190.000	358.160	1.2364E+07	44.0000	4.31818	3.4548E+06
192.000	358.370	1.2379E+07	46.0000	4.17391	3.4699E+06
194.000	358.620	1.2397E+07	48.0000	4.04167	3.4878E+06
200.000	359.940	1.2492E+07	54.0000	3.70370	3.5827E+06
206.000	360.700	1.2547E+07	60.0000	3.43333	3.6374E+06
212.000	361.660	1.2616E+07	66.0000	3.21212	3.7064E+06
218.000	362.470	1.2674E+07	72.0000	3.02778	3.7646E+06
224.000	363.130	1.2722E+07	78.0000	2.87179	3.8121E+06
230.000	363.790	1.2769E+07	84.0000	2.73810	3.8595E+06
236.000	364.450	1.2816E+07	90.0000	2.62222	3.9070E+06
248.000	365.910	1.2921E+07	102.000	2.43137	4.0120E+06
260.000	367.130	1.3009E+07	114.000	2.28070	4.0997E+06
272.000	368.190	1.3085E+07	126.000	2.15873	4.1759E+06
284.000	369.510	1.3180E+07	138.000	2.05797	4.2708E+06
292.000	369.760	1.3198E+07	146.000	2.00000	4.2888E+06
296.000	370.170	1.3228E+07	150.000	1.97333	4.3183E+06
308.000	370.930	1.3282E+07	162.000	1.90123	4.3729E+06
320.000	371.680	1.3336E+07	174.000	1.83908	4.4268E+06
332.000	372.290	1.3380E+07	186.000	1.78495	4.4707E+06
344.000	372.850	1.3420E+07	198.000	1.73737	4.5110E+06
356.000	373.200	1.3446E+07	210.000	1.69524	4.5361E+06

Horner producing time = 146

WELL NO. 21747 MARTIN CO., KY DEV. SHALE - ZONE 2

WELL NO. 21747 MARTIN CO., KY DEV. SHALE - ZONE 2

WELL NO. 21747 MARTIN CO., KY DEV. SHALE - ZONE 2

WELL NO. 21747 MARTIN CO., KY DEV. SHALE - ZONE 2

WELL NO. 21747 MARTIN CO., KY DEV. SHALE - ZONE 2

Enclosure 1

Mud Logging Report

KEYSTONE MUDLOGGING Geological/Hydrocarbon Analysis

**R.D. #3, Box 347
Conneaut Lake, PA 16816
(814) 382-4308**

COMPANY COLUMBIA NATURAL RESOURCES
WELL NAME POCAHONTAS DEVELOPMENT CORP.
LOCATION VARNEY QUAD.

COUNTY/STATE MARTIN / KENTUCKY
 DRILLING COMPANY RAY RESOURCES, RIG # 7
 DATES LOGGED JUNE 13 THRU JULY 7, 1990

ENGINEER R. TINGLEY / B. MCCLAIN
J. GOODWIN
 ELEVATION 1312.69 G.L. 10 FT. K.B.
 PERMIT NO# 79650 21747

BG	— BACKGROUND GAS		SANDSTONE		DOLOMITE	OIL FLUORESCENCE:	OIL LEACH:	METHANE: C-1
CG	— CONNECTION GAS		SILTSTONE		SALT	1X = TRACE	1/ = FAINT	ETHANE : C-2
TG	— TRIP GAS		SHALE		CHERT	2X = SCATTERED	2/ = MILKY	PROPANE: C-3
TT	— TEST GAS		LIMESTONE			3X = ABUNDANT	3/ = STRBRST	BUTANE : C-4
BT	— BIT TRIP							ISOBUTNE : C-5
NB	— NEW BIT							
NB	— NEW CORE BIT							

FAULT/FRACTURES: POSS. ⚡ - PROB. ⚡ ⚡

DRILLING RATE MIN. / FT.	DEPTH	LITHOLOGY %	OIL F L U I D F L O W	SAMPLE AND FORMATION DESCRIPTION	HOT WIRE GAS ANALYSIS BG ----- CG -----	CHROMATOGRAPHIC % ANALYSIS OF GAS IN RETURNS
						C1 C2 C3 C4 C5
6-14.10-30	3000			HORIZONTAL WELL SET 9.55" CASING @ 2954'		
6-4.2.				AIR PACK: 2550 CFM W/BOOSTER 215 PSI 10 FT. SAMPLES	10 20 30 40	2. 5 5 5 5
						ABOVE % PER DIV.
	20			BEGIN BUILDING ANGLE		5 5 5 5 5
						5 5 5 5 5
	40			SS: TAN, SBANG, MCMTD FWSRTD, DUL YEL FLR SLTST: GYBRN, YELBRN TCMTD, SCAT SH		5 5 5 5 5

Enclosure 2

Vertical Hole Geophysical Logs

COMPENSATED DENSITY DUAL SPACED NEUTRON LOG

COMPANY _____ WELL _____ FIELD _____ COUNTY _____ STATE _____	COMPANY <u>COLUMBIA NATURAL RESOURCES</u>	
	WELL <u>POCAHONTAS DEV. CORP. NO. 21747</u>	
	FIELD <u>BIG SANDY</u>	
	COUNTY <u>MARTIN</u>	STATE <u>KENTUCKY</u>
	API No.: <u>79650</u> Location: <u>QUAD: VARNEY</u> <u>1220' F N/L 1975' F E/L</u>	
Sec. <u>6</u> Twp <u>0</u> Rge <u>86</u>		Other Services: DLL CDL SONIC

Permanent Datum <u>GL</u>	Elev. <u>1313</u>	Elev.: K.B. <u>1323</u>
Log Measured From <u>KB 10</u> Ft. Above Perm. Datum		D.F. <u>1322</u>
Drilling Measured From <u>KB</u>		G.L. <u>1313</u>

Date	6-13-90			
Run No.	One			
Depth—Driller	2970			
Depth—Logger	2964			
Btm. Log Inter.	2962			
Top Log Inter.	787			
Casing—Driller	13 3/8 @ 791	@	@	@
Casing—Logger	787			
Bit Size	12 1/4			
Type Fluid in Hole	Salt Water			
Dens. / Visc.	-- 1 --			
pH / Fluid Loss	-- 1 -- ml	ml	ml	ml
Source of Sample	Flowline			
R _h @ Meas. Temp.	.10 @ 76 °F	@ °F	@ °F	@ °F
R _h @ Meas. Temp.	-- @ -- °F	@ °F	@ °F	@ °F
R _h @ Meas. Temp.	-- @ -- °F	@ °F	@ °F	@ °F
Source R _h R _h	-- 1 --			
R _h @ BHT	.09 @ 84 °F	@ °F	@ °F	@ °F
Time Since Circ.	3.5 Hours			
Time On Bottom	0134 Hours			
Max. Rec. Temp.	84 °F @ TD	°F @	°F @	°F @
Equip. / Location	7632 i Parker sburgi			
Recorded By	Grant			
Witnessed By	Mr. Rothman

DUAL LATEROLOG

COMPANY _____ WELL _____ FIELD _____ COUNTY _____ STATE _____	COMPANY <u>COLUMBIA NATURAL RESOURCES</u>			
	WELL <u>POCAHONTAS DEV. CORP. NO. 21747</u>			
	FIELD <u>BIG SANDY</u>			
	COUNTY <u>MARTIN</u>		STATE <u>KENTUCKY</u>	
API No.: <u>79650</u>				Other Services:
Location: QUAD: <u>VARNEY</u> <u>1220' F N/L 1975' F E/L</u>				CDL/DSN CDL SONIC
Sec. <u>6</u> Twp <u>0</u> Rge <u>86</u>				
Permanent Datum <u>GL</u> Elev. <u>1313</u>				Elev.: K.B. <u>1323</u>
Log Measured From <u>KB</u> <u>10</u> Ft. Above Perm. Datum				D.F. <u>1322</u>
Drilling Measured From <u>KB</u>				G.L. <u>1313</u>
Date	<u>6-13-90</u>			
Run No.	<u>One</u>			
Depth—Driller	<u>2970</u>			
Depth—Logger	<u>2963</u>			
Btm. Log Inter.	<u>2947</u>			
Top Log Inter.	<u>787</u>			
Casing—Driller 13	<u>3/8 @791</u>	<u>@</u>	<u>@</u>	<u>@</u>
Casing—Logger	<u>787</u>			
Bit Size	<u>12 1/4</u>			
Type Fluid in Hole	<u>Salt Water</u>			
Dens. I Visc.	<u>-- I --</u>	<u>I</u>	<u>I</u>	<u>I</u>
pH I Fluid Loss	<u>-- I -- ml</u>	<u>I ml</u>	<u>I ml</u>	<u>I ml</u>
Source of Sample	<u>Flowline</u>			
R ₁ @ Meas. Temp.	<u>.10 @76 °F</u>	<u>@ °F</u>	<u>@ °F</u>	<u>@ °F</u>
R ₂ @ Meas. Temp.	<u>-- @-- °F</u>	<u>@ °F</u>	<u>@ °F</u>	<u>@ °F</u>
R ₃ @ Meas. Temp.	<u>-- @-- °F</u>	<u>@ °F</u>	<u>@ °F</u>	<u>@ °F</u>
Source R ₁ R ₂	<u>-- I --</u>	<u>I</u>	<u>I</u>	<u>I</u>
R ₁ @ BHT	<u>.09 @84 °F</u>	<u>@ °F</u>	<u>@ °F</u>	<u>@ °F</u>
Time Since Circ.	<u>8 Hours</u>			
Time On Bottom	<u>0354 Hours</u>			
Max. Rec. Temp.	<u>84 °F@TD</u>	<u>°F@</u>	<u>°F@</u>	<u>°F@</u>
Equip. I Location	<u>7632 Parkersburg I</u>	<u>I</u>		<u>I</u>
Recorded By	<u>Grant</u>			
Witnessed By	<u>Mr. Rothman</u>			

Enclosure 3

Free-Fall Geophysical Logs

DUAL INDUCTION LOG

COMPANY WELL FIELD COUNTY STATE	COMPANY <u>COLUMBIA NATURAL RESOURCES</u>	
	WELL <u>POCAHONTAS DEV. CORP. NO. 21747</u>	
	FIELD <u>BIG SANDY</u>	
	COUNTY <u>MARTIN</u>	STATE <u>KENTUCKY</u>
API No.: <u>79650</u>		Other Services: <u>CDL/SNP/TEMP</u>
Location: <u>1220'F N/L 1975'F E/L</u> <u>QUAD: VARNEY</u>		
Sec. <u>6</u> Twp <u>0</u> Rge <u>86</u>		
Permanent Datum <u>GL</u> Elev. <u>1313</u>		Elev.: K.B. <u>1323</u>
Log Measured From <u>KB</u> <u>10</u> Ft. Above Perm. Datum		D.F. <u>1322</u>
Drilling Measured From <u>KB</u>		G.L. <u>1313</u>
Date	<u>7-8-90</u>	
Run No.	<u>Two</u>	
Depth—Driller	<u>6263</u>	
Depth—Logger	<u>**</u>	
Btm. Log Inter.	<u>3641</u>	
Top Log Inter.	<u>2951</u>	
Casing—Driller	<u>9 5/8 @ 2954</u>	<u>@</u>
Casing—Logger	<u>2951</u>	<u>@</u>
Bit Size	<u>8 3/4</u>	
Type Fluid in Hole	<u>Air</u>	
Dens. I Visc.	<u>- I -</u>	<u>I</u>
pH I Fluid Loss	<u>- I - ml</u>	<u>I ml</u>
Source of Sample	<u>-</u>	
R _{at} @ Meas. Temp.	<u>- @ - °F</u>	<u>@ °F</u>
R _{ay} @ Meas. Temp.	<u>- @ - °F</u>	<u>@ °F</u>
R _{at} @ Meas. Temp.	<u>- @ - °F</u>	<u>@ °F</u>
Source R _{ay} R _{at}	<u>- I -</u>	<u>I</u>
R _{at} @ BHT	<u>- @ - °F</u>	<u>@ °F</u>
Time Since Circ.	<u>-</u>	
Time On Bottom	<u>1901 Hours</u>	
Max. Rec. Temp.	<u>87 °F @ TD</u>	<u>°F @</u>
Equip. I Location	<u>7632 Parkersburg I</u>	<u>I</u>
Recorded By	<u>Peerman</u>	
Witnessed By	<u>Mr. Rothman</u>

COMPENSATED DENSITY SIDEWALL NEUTRON TEMPERATURE LOG

COMPANY WELL FIELD COUNTY STATE	COMPANY <u>COLUMBIA NATURAL RESOURCES</u>			
	WELL <u>POCAHONTAS DEV. CORP. NO. 21747</u>			
	FIELD <u>BIG SANDY</u>			
	COUNTY <u>MARTIN</u>		STATE <u>KENTUCKY</u>	
API No.: <u>79650</u>		Other Services:		
Location: <u>1220'F N/L 1975'F E/L</u> <u>QUAD: VARNEY</u>		<u>DI</u>		
Sec. <u>6</u> Twp. <u>0</u> Rge. <u>86</u>				
Permanent Datum <u>GL</u> Elev. <u>1313</u>		Elev.: K.B. <u>1323</u>		
Log Measured From <u>KB</u> <u>10</u> Ft. Above Perm. Datum		D.F. <u>1322</u>		
Drilling Measured From <u>KB</u>		G.L. <u>1313</u>		
Date	<u>7-8-90</u>			
Run No.	<u>Two</u>			
Depth—Dritter	<u>6263</u>			
Depth—Logger	<u>**</u>			
Btm. Log Inter.	<u>3686</u>			
Top Log Inter.	<u>2951</u>			
Casing—Dritter	<u>9 5/8 @ 2954</u>	<u>@</u>	<u>@</u>	
Casing—Logger	<u>2951</u>			
Bit Size	<u>8 3/4</u>			
Type Fluid in Hole	<u>Air</u>			
Dens. Visc.	<u>- -</u>	<u> </u>	<u> </u>	
pH Fluid Loss	<u>- - ml</u>	<u> ml</u>	<u> ml</u>	
Source of Sample	<u>-</u>			
R _u @ Meas. Temp.	<u>- @ - °F</u>	<u>@ °F</u>	<u>@ °F</u>	
R _u @ Meas. Temp.	<u>- @ - °F</u>	<u>@ °F</u>	<u>@ °F</u>	
R _u @ Meas. Temp.	<u>- @ - °F</u>	<u>@ °F</u>	<u>@ °F</u>	
Source R _u R _u	<u>- -</u>	<u> </u>	<u> </u>	
R _u @ BHT	<u>- @ - °F</u>	<u>@ °F</u>	<u>@ °F</u>	
Time Since Circ.	<u>-</u>			
Time On Bottom	<u>2035 Hours</u>			
Max. Rec. Temp.	<u>87 °F @ TD</u>	<u>°F @</u>	<u>°F @</u>	
Equip. Location	<u>7632 Parkersburg</u>	<u> </u>	<u> </u>	
Recorded By	<u>Peerman</u>			
Witnessed By	<u>Mr. Rothmar</u>			

Enclosure 4

Drill Pipe Conveyed Geophysical Logs

Schlumberger

PHASOR/LDT/CNL/TEMP/GR

BIG SANDY VARNEY QUAD POCAHONTAS DEV. CORP. #21747 COLUMBIA NATURAL RESOURCES	COMPANY		COLUMBIA NATURAL RESOURCES	
	WELL		POCAHONTAS DEV. CORP. #21747	
	FIELD		BIG SANDY	
	COUNTY		MARTIN STATE KENTUCKY	
FIELD LOCATION WELL COMPANY	LOCATION	VARNEY QUAD 1220FNL, 1976FEL		Other Services:
	API SERIAL NO.	SECT.	TWP.	RANGE
		06	0	86
Permanent Datum		GROUND LEVEL	Elev.	1313.0 F
Log Measured From		KELLY BUSHING	10.0 F	above Perm. Datum
Well Measured From		KELLY BUSHING		
Date		JULY 11 1990		
Run No.		ONE		
Depth-Driller		6283.0 F		
Depth Logger (Sohl)		6088.0 F		
Bottom Log Interval		6088.0 F		
Top Log Interval		3300.0 F		
Casing-Driller		9 5/8"	Q2954.0 F	
Casing-Logger				
H Size		8 1/4"		
Type Fluid in Hole		AIR		
ens.	Visc.			
H	Fld. Loss			
Source of Sample				
m @ Meas. Temp.				
mf @ Meas. Temp.				
mo @ Meas. Temp.				
Source: Rmi Rmo				
m @ BHT			Q 84.0 DEGF	
Circulation Ended		N/A		
Logger on Bottom		JULY 11 16:28		
Max. Rec. Temp.		84.0 DEGF		
quip.	Location	8272	PARTSVILLE	

Schlumberger

TRUE VERTICAL DEPTH LDT/TEMP/GR

COUNTY	FIELD	WELL	COMPANY	COMPANY COLUMBIA NATURAL RESOURCES	
				WELL POCAHONTAS DEV. CORP. #21747	
				FIELD BIG SANDY	
				COUNTY MARTIN	STATE KENTUCKY
LOCATION	VARNEY QUAD				Other Services:
	1220FNL, 1975FEL				
API SERIAL NO.		SECT.	TWP.	RANGE	
		06	0	86	
Permanent Datum		GROUND LEVEL	Elev.	1313.0 F	Elev.: K.B.1323.0 F
Log Measured From		KELLY BUSHING	10.0 F	above Perm. Datum	D.F.1322.0 F
Drilling Measured From		KELLY BUSHING			G.L.1313.0 F
Date	JULY 11 1990				
Run No.	ONE				
Depth Driller	6263.0 F				
Depth Logger (Schl.)	6088.0 F				
Btm. Log Interval	6088.0 F				
Top Log Interval	3300.0 F				
Casing Driller	9 5/8"	@2954.0 F			
Casing Logger					
Bit Size	8 1/4"				
Type Fluid In Hole	AIR				
Dens.	Visc.				
pH	Fld. Loss				
Source of Sample					
Rm @ Meas. Temp.					
Rmf @ Meas. Temp.					
Rmc @ Meas. Temp.					
Source: Rmf	Rmc				
Rm @ Bit			94.0 DEGF		
Circulation Ended	N/A				
Log on Bottom	JULY 11 16:28				
Max. Res. Temp.	94.0 DEGF				
Equip.	Location	8272	PANTSVILLE		

Enclosure 5

Stimulation Data Treatment Log - Zone 2

HALLIBURTON DATA LOG COMPUFAC Ver. 1.54P 10/01/90

THIS REPORT IS BASED ON SOUND ENGINEERING PRACTICES, BUT BECAUSE OF VARIABLE WELL CONDITIONS AND OTHER INFORMATION WHICH MUST BE RELIED UPON, HALLIBURTON MAKES NO WARRANTY, EXPRESSED OR IMPLIED, AS TO THE ACCURACY OF THE DATA OR ANY CALCULATIONS OR OPINIONS EXPRESSED HEREIN. YOU AGREE THAT HALLIBURTON SHALL NOT BE LIABLE FOR ANY LOSS OR DAMAGE, WHETHER DUE TO NEGLIGENCE OR OTHERWISE, ARISING OUT OF OR IN CONNECTION WITH SUCH DATA, CALCULATIONS OR OPINIONS.

Customer: COLUMBIA NATURAL RESOURCES Ticket Number: 0050753
Contractor: WELL TECH Permit Number: _____
Lease: ROCKMOUNTS DEV. CORP. Well #: 21767
Location: EMILY CREEK Sec.: _____
Field: BIG SANDY Ten.: _____
Country: U.S.A. Eng.: _____
County: MARTIN State: KENTUCKY
Job Type: NITROGEN GAS FRAC

WELL DESCRIPTION

MOLE DEPTH	TYPE	SIZE	WEIGHT
CL - 5300	CBS	5.5	178/FT

PERF DEPTH	NUMBER	SIZE	FORMATION

Open Hole I.D.: _____ Total Depth: 6100
Zone #: 1 Formation: DEVONIAN SHALE
Packer Depth: _____ Packer Type: _____
Baffle/MSB Depth: _____ Baffle Size: _____
BMSY: _____ Frac Gradient: _____

STIMULATION DATA

TYPE	CONC/RATIO	VOLUME
PreFad:		
Pad:		
Acid:		
Sand Laden:		
Flush:		
Overflush:		
Total:		
N2:	100%	1,535,000
CO2:		SCF

PROPPANT TYPE	SIZE	QUANTITY	MAX CONC.

AVE. RATE: 90.295 SCFH AVE. PRESSURE: 2560 AVE. #P: _____

Comments: _____

Legend for Sids

1. Time
2. Casing_Press PSI
3. N2 Total SCF
4. Avg N2 Rate SCFH
5. None

Enclosure 6

Stimulation Data Treatment Log - Zones 3, 5 & 6

HALLIBURTON

STIMULATION DATA LOG

THIS REPORT IS BASED ON SOUND ENGINEERING PRACTICES, BUT BECAUSE OF VARIABLE WELL CONDITIONS AND OTHER INFORMATION WHICH MUST BE RELIED UPON, HALLIBURTON MAKES NO WARRANTY, EXPRESS OR IMPLIED, AS TO THE ACCURACY OF THE DATA OR ANY CALCULATIONS OR OPINIONS EXPRESSED HEREIN. YOU AGREE THAT HALLIBURTON SHALL NOT BE LIABLE FOR ANY LOSS OR DAMAGE, WHETHER DUE TO NEGLIGENCE OR OTHERWISE, ARISING OUT OF OR IN CONNECTION WITH SUCH DATA, CALCULATIONS OR OPINIONS.

DATE : 12/10/90

COMPANY Columbia Natural Gas
 TICKET # 008421 PERMIT # _____
 CONTRACTOR _____
 LEASE Pocahontas Land Devl. WELL # 21747
 SEC _____ TWP _____ RNG _____
 FIELD _____
 LOCATION _____
 COUNTY Martin STATE Ky.
 COUNTRY U.S.A.
 JOB TYPE Nitrogen Frac

WELL DESCRIPTION

HOLE DEPTH	TYPE	SIZE	WEIGHT
CL _____	_____	5 1/2	17 lb.
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
PERF DEPTH	NUMBER	SIZE	
_____	_____	_____	

OPEN HOLE ID _____
 TOTAL DEPTH _____ INCHES
 ZONE # 2-5-6 FORMATION _____
 PACKER DEPTH _____ TYPE _____
 BAFFLE DEPTH _____ SIZE _____

TREATMENT SUMMARY

TYPE	VOLUME
PREPAD	_____
PAD	_____
ACID	_____
FLUSH	_____
OVERFLUSH	_____
TOTAL VOL	SAND LADEN VOL
N2 VOL <u>3,303,000 scf</u>	N2 RATIO
CO2 VOL	CO2 RATIO
AVE RATE <u>144,787 scfm</u>	AVE PRES <u>1456</u>
AVE HHP	MAX ALL PRES

PROPPANT TYPE	SIZE	QUANTITY
_____	_____	_____
_____	_____	_____
_____	_____	_____

COMMENTS: _____

LEGEND

LABEL	DATA	UNITS
1	N2 PRES	PSI
2	N2 RATE	SCFH
CINE	N2 PRES	PSI

END

**DATE
FILMED**

10 / 6 / 92