DOE/PC/79660--T8

Technical Progress Report No. 4

DOE/PC/79660--T8

DE93 004032

DEVELOPMENT OF A VORTEX COMBUSTOR
(VC) FOR SPACE/WATER HEATING APPLICATIONS
(PROOF-OF-CONCEPT MODEL DEVELOPMENT)

To

U.S. Department of Energy
Pittsburgh Energy Technology Center
TPO: Anthony E. Mayne
(Phone) 412-892-4673
P.O. Box 10940
Pittsburgh, PA 15236

for

Project No: DE-AI22-87PC79660

by

Tim T. Fu, Principal Investigator
Energy and Environment Department
Naval Civil Engineering Laboratory
Port Hueneme, CA 93043-5000
(Phone) 805-982-4675

January 1989

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

ENCLOSURE (1)

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

SUMMARY

This is the fourth quarterly technical progress report for DE-AI22-87PC79660 covering the period between 1 August and 31 October 1988.

During this reporting period, firing tests of dry ultrafine coal and coal-water fuel in the 0.15 MB/H exploratory model have been successful. Further exploratory tests are continuing.

Based on the results and experience gained from the exploratory model tests, a 0.6 MB/H experimental model has been designed and the construction is nearly complete. This model incorporates a variable (cooling surface area) center heat removal unit and flexible air flow rate and velocity controls. It is also readily convertible to an outside heat removal arrangement for capacity increase. Suitable instrumentation will be installed for obtaining quantitative data for finalizing the design of the proof-of-concept model. Tests will begin early in December 1988. Design of the proof-of-concept model is expected to be ready for Preliminary Design Review early in 1989.

TABLE OF CONTENTS

	PAGE
SUMMARY.	i
LIST OF TABLES AND FIGURES.	iii
INTRODUCTION.	1
COMBUSTOR DESIGN AND TEST	1
The 0.15 MB/H Exploratory Model.	1
The 0.6 MB/H Experimental Model.	8
The 2-4 MB/H Proof-of-Concept Model.	8
INSTRUMENTATION	11
AUXILIARY SYSTEMS	11
FUTURE PLANS.	11

LIST OF TABLES AND FIGURES

	PAGE
<u>Table</u>	
1. Summary of Major Design Parameters.	12
<u>Figure</u>	
1. The 0.15 MB/H Vortex Combustor for firing CWF.	3
2. Arrangement of CWF and air inlet ports for the 0.15 MB/H hot test model	4
3. Schematic diagram of coal-water fuel supply and. test system	5
4. Basic design of the CWF spray nozzle	6
5. Cold start and hot restart procedure and characteristics of the 0.15 MB/H VC exploratory model	7
6. The 0.6 MB/H Vortex Combustor hot test model	9
7. Arrangement of DUC and air inlet ports for. the 0.6 MB/H VC hot test model	10

INTRODUCTION

This is the fourth quarterly technical progress report for the development of vortexing combustion technology under interagency agreement DE-AI22-87PC79660 covering the period between 1 August and 31 October 1998.

The Vortex Combustor (VC) under development here is a device to burn either Dry Ultrafine Coal (DUC) or Coal-Water Fuel (CWF) in a high swirl and low temperature environment. Being a new concept, technical data relevant to the design of the proof-of-concept model is practically non-existent. In order to minimize the risk of uncertainties, sufficient basic design data must be generated first. To achieve this, two subscale models have been built: A 0.15 MB/H exploratory model and a 0.60 MB/H experimental model.

During this reporting period, the 0.15 MB/H exploratory model has been successfully fired both on DUC and CWF. Based on the results obtained thus far, the 0.6 MB/H experimental model has been redesigned and the construction is nearly complete. The results are presented in this report.

COMBUSTOR DESIGN AND TEST

The 0.15 MB/H Exploratory Model

Efforts have been primarily on test firing of CWF. We have successfully achieved stable and continuous combustion without using support fuel or preheated air. The work accomplished is described below:

Due to the extra time required for water evaporation prior to ignition, the travel distance or residence time of a CWF particle must be larger than that of DUC. The combustion chamber for firing CWF should therefore be larger than for DUC. To achieve this, the height of the

adiabatic section for DUC was increased by use of an "added section" as shown in Figure 1. We note that the space in the combustor is not only narrow but also curved. To prevent fuel particles from impinging on the combustor walls, diverting air is used. Important details of the CWF and air inlet ports are shown in Figure 2.

A CWF supply and test system was built as shown in Figure 3. This system can deliver the fuel spray either to the combustor or to a transparent atomization test chamber for visual observations of the spray quality. Three types of spray nozzles have been tested:

- Straight thru tube outside atomization with compressed air.
- Six commercial fuel oil nozzles.
- Air assisted internal mixing.

The first two types did not perform well and caused excessive depositions on wall surface. The third type was specially designed and manufactured and functioned well. Details of this nozzle are shown in Figure 4. Since developing CWF nozzle is not a part of this work, once a nozzle is found satisfactory, there is no need to look into other nozzles nor to pursue any detailed performance evaluations. Two orifice diameters were tested: 1.2 mm and 1.4 mm. They both performed well. The cold start for CWF procedure is the same as for DUC firing. But for hot restart, the gas temperature in the combustor must be brought up again to the same level as would be for cold start ($\sim 1650^{\circ}\text{F}$) by use of propane before CWF is introduced. A comparison of these between CWF and DUC firing is shown in Figure 5 (CWF is shown in dotted line). Stable and continuous combustion could be achieved without the use of support fuel or preheated air in much

Figure 1. The 0.15 MB/H Vortex Combustor for firing CWF.

(a) CWF and diverting air injection plane.

(b) Igniter plane.

Figure 2. Arrangement of CWF and air inlet ports for the 0.15 MB/H hot test model (see Figure 1).

Figure 3. Schematic diagram of coal-water fuel supply and test system ("Water" indicates provisions for system flushing).

Orifice diameters:

$d = 1.2\text{mm}, 1.4\text{mm}$

Figure 4. Basic design of the CWF spray nozzle.

Figure 5. Cold start and hot restart procedure and characteristics of the 0.15 MB/H VC exploratory model.

was 75 minutes (The firing was terminated in order to change test conditions).

For a combustor of this small size, we have successfully demonstrated the feasibility of single point fuel injection for both CWF and DUC firing. We plan to combine the current separate setups for firing CWF and DUC to a single setup with capability to switch fuel from one to another. Further exploratory experiments on the combined model are being planned.

The 0.6 MB/H Experimental Model

Based on experience gained from testing the 0.15 MB/H model thus far, the design presented in our No. 3 progress report (Figure 1) was simplified as shown in Figure 6. The air and fuel distribution ports of this new design are shown in Figure 7. Construction of this model is nearly complete. Hot testing is expected to begin in December 1988. The basic features of this new design are:

- Simple configuration of the refractory enclosed combustion space.
- Flexible cooling provisions from the center tube assembly. Heat transfer rate can be varied by changing the coolant type (water or air), by changing the heat transfer areas (moving the assembly up and down), and by shielding the cooling surfaces.
- Flexible air injection ports. Air inlet velocity, flow rate, and distribution can all be varied.
- Built-in conservatism for firing at higher rates. Cooling may also be achieved from outside the refractory to increase the firing rate.
- Carefully planned thermal and flow instrumentation for detailed performance evaluations.

The 2-4 MB/H Proof-of-Concept Model

Preliminary design of this model has been completed. It is basically the same as the 0.6 MB/H model. Since many flexibilities have been built

Figure 6. The 0.6 MB/H Vortex Combustor hot test model.

Figure 7. Arrangement of DUC and air inlet ports for the 0.6 MB/H VC hot test model (See Figure 6).

into the 0.6 MB/H model, removing any of them would lead to possibly smaller size and necessarily simpler construction. We need experimental data from testing the 0.6 MB/H model to help finalize our proof-of-concept model. Judging from the current status, we expect to submit the design for preliminary design review about February 1989.

A summary of the major design parameters of all these models is given in Table 1.

INSTRUMENTATION

We have now accumulated an assortment of thermal, flow, and stack gas monitoring instrumentation, and data acquisition equipment intended for this project. Additional instrumentation acquisition is our continuing effort as the demands justify.

AUXILIARY SYSTEMS

In addition to the auxiliary systems that have been used for testing the 0.15 and 0.6 MB/H models, we are now planning the installation of the auxiliary systems for testing the proof-of-concept model. This effort requires design and modifications to an existing boiler. Coordination activities with boiler plant personnel have been increasing.

FUTURE PLANS

- Combine the two 0.15 MB/H test setups for DUC and CWF firing into one single unit capable of switching fuel from one to the other.
- Conduct systematic tests on the 0.6 MB/H model.
- Submit drawings for the proof-of-concept model to PETC for Preliminary Design Review.
- Initiate installation of auxiliary systems/equipment for the proof-of-concept model tests.
- Contact boiler makers for possible involvement in our combustor development.

Table 1. Summary of Major Design Parameters

Capacity, MB/H	0.15	0.6	3
Fuel consumption, lb/hr	5.73	22.9	76.5
Center tube diameters, inch			
Inside	3	14	21
Outside	3.5	19.3	28.7
Combustion chamber diameter, inch	7.5	32	43.9
Bulk Gas velocities, ft/sec			
In center tube	52.5	16.4	16.4
In annulus region	11.3	6.6	6.6
Cooling surface area height, inch	23	39	79
Air flow rate, SCFM	35.4	158	528
Swirl number	8.8	15.6	8.8

END

**DATE
FILMED**

12 / 30 / 92