DOE/PC/89857-T4

2nd

DOE/PC/89857--T4

DE92 018512

**U.S. DEPARTMENT OF ENERGY
PITTSBURGH ENERGY TECHNOLOGY CENTER**

**DIRECT COAL LIQUEFACTION
BASELINE DESIGN
AND
SYSTEM ANALYSIS**

CONTRACT NO. DEAC22 90PC89857

QUARTERLY REPORT

APRIL - JUNE, 1991

Received OSTI

JUL 24 1992

JULY, 1991

PITTSBURGH, PENNSYLVANIA

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Bechtel

3000 Post Oak Boulevard
Houston, Texas 77056-6503
Mailing address: P.O. Box 2166
Houston, Texas 77252-2166

September 20, 1991

DISCLAIMER

U. S. Department of Energy
Pittsburgh Energy Technology Center
Mail Stop 922-H
P. O. Box 10940
Pittsburgh, PA 15236

Attention: Mr. Swenam Lee
Project Manager

Subject: D.O.E. Coal Liquefaction
Base Line Design and System Analysis
Contract No. DE-AC22 90PC89857
Bechtel Job No. 20952
Quarterly Status Report
Letter No. BLD-062

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Dear Mr. Lee:

Attached for your information are three copies of the subject Quarterly Status Report covering the March 18, 1991 through June 23, 1991 reporting period. Copies to other members, as required by the contract are separately and directly transmitted.

Please note that all information contained herein should be considered preliminary pending issue of the final tasks reports.

This report does not contain any confidential information which, as agreed, would have been segregated in the appendix of this report.

If you have any questions or comments on this Quarterly Status Report please contact me.

Sincerely yours,

Sam N. Habash
Project Manager

Attachment

cc: Martin Byrnes, DOE/PETC
Robert Hamilton, DOE/PETC
A. B. Schachtschneider, AMOCO
File

Gilbert V. McGurl, DOE/PETC
Joanne Wastek, DOE/PETC

Bechtel Corporation

TABLE OF CONTENTS

1. INTRODUCTION	1
2. SUMMARY	3
3. TECHNICAL PROGRESS (BY TASK)	5
3.1 TASK I	6
3.2 TASK II	7
3.2.1 Status Update on Process Plants	7
3.2.1.1 Coal Liquefaction (Plant 2)	7
3.2.1.2 Gas Plant (Plant 3)	23
3.2.1.3 Naphtha Hydrotreater (Plant 4)	34
3.2.1.4 Gas Oil Hydrotreater (Plant 5)	40
3.2.1.5 Hydrogen Purification (Plant 6)	48
3.2.1.6 Critical Solvent Deashing Unit - ROSE-SR (Plant 8)	57
3.2.1.7 Hydrogen Production by Coal Gasification (Plant 9)	62
3.2.1.8 Air Separation (Plant 10)	79
3.2.1.9 Sulfur Plant (Plant 11)	83
3.2.2 Status Update on Support Facilities	96
3.2.2.1 Coal Cleaning and Handling (Plant 1)	96
3.2.2.2 Coal Grinding and Drying (Plant 1.4)	109
3.2.2.3 Sewage and Effluent Water Treatment (Plant 34)	113
3.2.3 Options to Baseline	133
3.2.4 Thermal Catalytic Reactor Options	139
3.3 TASK III	141
3.3.1 Methodology to Distribute Cost Estimate of Support Facilities	141
3.4 TASK IV	144
3.4.1 Status of Task IV	144
3.5 TASK V	150
3.5.1 Status of the Simulation Model	150
3.5.2 Kinetic Model for Two Stage Coal Liquefaction Reactor	151
3.6 TASK VI	153
4. KEY PERSONNEL STAFFING REPORT	154

LIST OF TABLES

NO.	TITLE	PAGE
3.1	Analysis Of Feed Coal To Liquefaction Plant	9
3.2	Coal Liquefaction Yield	10
3.3	Quality of Liquefaction Products	11
3.4	Material Balance For Plant 2	19
3.5	Utility Summary For Plant 2	22
3.6	Material Balance For Plant 3	29
3.7	Utility Summary For Plant 3	31
3.8	Naphtha Hydrotreater Product Characteristics	34
3.9	Material Balance For Plant 4	38
3.10	Utility Summary For Plant 4	39
3.11	Feed Characteristics To The Gas Oil Hydrotreater	40
3.12	Product Quality of The Gas Oil Hydrotreater	41
3.13	Material Balance For Plant 5	46
3.14	Utility Summary For Plant 5	47
3.15	Material Balance For Plant 6	55
3.16	Utility Summary For Plant 6	56
3.17	Material Balance For Plant 8	60
3.18	Utility Summary For Plant 8	61
3.19	Gasification Feed Streams	63
3.20	Composition of Coal Gasification Products	64
3.21	Material Balance For Plant 9	75
3.22	Utility Summary For Plant 9	78
3.23	Material Balance For Plant 10	81
3.24	Material Balance For Plant 11	92
3.25	Material Balance For Plant 11.1	93
3.26	Material Balance For Plant 11.2	94
3.27	Utility Summary For Plant 11	95
3.28	Illinois No. 6, Burning Star Mine ROM Coal Analysis	98
3.29	Size Analysis Of ROM Coal	99
3.30	Analysis Of Feed Coal To Liquefaction Plant	100
3.31	Product Size From Coal Cleaning Plant	101
3.32	Utility Summary For Coal Cleaning Plant	106
3.33	Material Balance For Coal Cleaning Plant	108
3.34	Utility Summary For Plant 1.4	112
3.35	Design Characteristics of Runoff	114

LIST OF TABLES - Continued

NO.	TITLE	PAGE
3.36	Process Features and Related Variables	133
3.37	Process Features and Related Variables for Baseline Design	134
3.38	Process Features and Related Variables for Option 1	134
3.39	Process Features and Related Variables for Option 2	135
3.40	Process Features and Related Variables for Option 3	135
3.41	Process Features and Related Variables for Option 4	136
3.42	Process Features and Related Variables for Option 5	136
3.43	Process Features and Related Variables for Option 6	137
3.44	Comparison of Critical Parameter for Baseline and Therm-cat Option	140
3.45	Task IV Description	145
3.46	Status of Task V Simulation Model	150
4.1	Key Personnel Staffing Report	154

LIST OF FIGURES

NO.	TITLE	PAGE
3.1	Process Flow Diagram for Plant 2	14
3.2	Plant 2 Primary Separation	17
3.3	Plant 2 Fractionation	18
3.4	Overall Material Balance	21
3.5	Process Flow Diagram for Plant 3	26
3.6	Process Flow Diagram for Merox Unit of Plant 3	27
3.7	Process Flow Diagram for Plant 4	36
3.8	Process Flow Diagram for Plant 5	44
3.9	High Pressure H ₂ Recovery for Plant 6.1	51
3.10	Low Pressure H ₂ Recovery for Plant 6.2	52
3.11	Amine Regeneration for Plant 6.2	53
3.12	ROSE SR Process for Plant 8	59
3.13	Block Flow Diagram of Hydrogen Production by Coal Gasification	67
3.14	Process Flow Diagram for Plant 9.1	70
3.15	Process Flow Diagram for Plant 9.2	71
3.16	Process Flow Diagram for Plant 9.3/9.4/9.5	72
3.17	Schematic Representation of Plant 9 Material Balance	77
3.18	Process Flow Diagram for Plant 10	80
3.19	Process Flow Diagram for Plant 11.1	85
3.20	Process Flow Diagram for Plant 11.2	88

LIST OF FIGURES - Continued

<u>NO.</u>	<u>TITLE</u>	<u>PAGE</u>
3.21	Process Flow Diagram for Plant 11.3	90
3.22	Simplified Block Flow Diagram for Base Case	102
3.23	Process Flow Diagram for Jig Cleaning	103
3.24	Process Flow Diagram - Coal Receiving	105
3.25	Process Flow Diagram for Coarse Refuse Handling Section	107
3.26	Block Flow Diagram for Plant 1.4	111
3.27	Block Flow Diagram for CSP Runoff Treatment	116
3.28	Block Flow Diagram for Oily Water Treatment	118
3.29	Block Flow Diagram for Deoiled Wastewater Treatment	123
3.30	Block Flow Diagram for Stripped Dephenolated Wastewater Treatment	127
3.31	Block Flow Diagram for Solids Dewatering Treatment	129
3.32	Block Flow Diagram for Sanitary Sewage	131
3.33	Interactive Approach to Cost Scale up Procedure	142
3.34	Noninteractive Approach to Cost Scale up Procedure	143
3.35	Kinetic Model for Two Stage Coal Liquefaction	152

1. INTRODUCTION

Effective May 16, 1990, Bechtel with Amoco as subcontractor, initiated a study to develop a computer model for a base line direct coal liquefaction design for the U.S. Department of Energy's (DOE) Pittsburgh Energy Technology Center (PETC). The project is for a duration of 18 months with an approved budget of \$2 MM. This study is under DOE contract No. DE-AC22 90PC89857.

The primary objective of the study is to develop a computer model for a base line direct coal liquefaction design based on two stage direct coupled catalytic reactors. This primary objective is to be accomplished by completing the following:

- A base line design based on previous DOE/PETC results from Wilsonville pilot plant and other engineering evaluations
- A cost estimate and economic analysis
- A computer model incorporating the above two steps over a wide range of capacities and selected process alternatives
- A comprehensive training program for DOE/PETC Staff to understand and use the computer model
- A thorough documentation of all underlying assumptions for baseline economics, and
- A user manual and training material which will facilitate updating of the model in the future

The progress made during any particular quarter is published in a quarterly report following the duration of the quarter. The report consists of the following four sections:

- Introduction
- Summary
- Technical Progress Report (By Tasks)
- Key Personnel Staffing Report.

Introduction (Continued)

Any confidential information will be presented in the quarterly report as a separate section under the heading "confidential". As agreed upon by DOE/PETC, information included in the confidential section will be treated confidential by DOE/PETC and its contractors.

This report is Bechtel's fourth quarterly progress report and covers the period of March 18, 1991 through June 23, 1991.

2. SUMMARY

Effective May 16, 1990, Bechtel initiated this study, with Amoco as subcontractor, as an assignment from the U.S. Department of Energy (DOE)'s Pittsburgh Energy Technology Center (PETC). The objective of the study is to develop a computer model for a baseline direct coal liquefaction design based on two stage direct coupled catalytic reactors. The study is for a period of 18 months with an approved total budget of \$2MM.

This is Bechtel's fourth quarterly progress report and covers the period (as requested and approved by DOE/PETC) of March 18, 1991 through June 23, 1991. This reporting period was previously covered by three already published monthly status reports.

The report contains accomplishments made during this time period in all the Tasks scheduled for the period i.e., Tasks I through VI. As per schedule, the major focus, however, was on Task II, III, IV and V. Therefore, the accomplishments included in this report are predominantly for these four tasks.

The accomplishments are presented in the report on Task by Task basis for all the Tasks covered during this reporting period.

In Task I (which defines the project) the Project Management Plan Draft Report was completed and subsequently updated incorporating the comments and suggestions of DOE/PETC and their contractors. The final version was sent to DOE/PETC for their approval and subsequently published in August, 1990. The approved copy was the deliverable for the Task.

Project Management Plan report covers the overall scope of work, the methodology of managing the cost and schedule of the project (configuration management), program administration, the deliverables during various phases of work and the definition of the baseline configuration.

In Task II the following activities were accomplished:

- Developed and implemented material balance reconciliation methodology to obtain overall material balances consistent with the HRI report. The material balances for all process plants, viz, Plant 2 (Coal Liquefaction), Plant 3 (Gas Plant), Plant 4 (Naphtha Hydrotreater), Plant 5 (Gas Oil Hydrotreater), Plant 6 (Hydrogen Purification Plant), Plant 8 (Critical Solvent Deashing Unit, ROSE-SR), Plant 9 (Hydrogen Production by Coal Gasification), Plant 10 (Air Separation Plant) and Plant 11 (Sulfur Plant) were completed during this reporting period.

- Updating of Coal Grinding and Drying Plant (Plant 1.4) has been completed. The updated information is included in this report.
- During this reporting period, sewage and effluent water treatment plant (Plant 34) was updated. The updated results are included in this report.
- The methodology to select the options to the base case was developed which is included in this report. Also the combinations of process features for each of these options thus selected are presented in this report. The deliverables for each option are identified and included in this report.
- The methodology to be used for thermal-catalytic reactor option was developed and discussed in this report.

In Task III the following activity was accomplished:

- The methodology to distribute the cost estimate of support facilities was formulated. The methodology thus developed is presented in this report.

In Task IV the following were accomplished:

- During this reporting period progress was made on the various identified subtasks applicable to Task IV. The accomplishments are included in this report.
- Equipment sizing algorithms for Plant 2 including the equipment size scaling equations were developed and included in this report. In addition, equations for capital cost estimation and multiple train requirements were also completed.

In Task V the following activities were accomplished:

- During this reporting period ASPEN process simulation models for several process plants have been developed. The preliminary status of this simulation model is included in this report.

3. TECHNICAL PROGRESS (BY TASKS)

In order to carry out this Study efficiently, the Study has been divided in seven major tasks. Task I defines the project. Task II develops the baseline design. Task III develops the capital, operating and maintenance costs. Task IV develops the mathematical model necessary for the process computer simulation model. Task V develops and verifies the process simulation model. Task VI documents the process simulation model and training. Task VII is a level of effort task for project management, technical coordination and other miscellaneous support functions.

During this reporting period (March 18, 1991 through June 23, 1991) several accomplishments were made in Tasks II, III, IV and VI. These accomplishments are included in this report task by task.

Task I was completed during the first quarterly reporting period. The accomplishment of Task I was documented in the Project Management Plan published in August, 1990. It was also presented in the first quarterly report, covering the period of May 16, 1990 through August 19, 1990).

3.1 TASK I

Task I defines the scope and the methodology of accomplishing the project. It sets the objectives of the project and defines the paths to accomplish those objectives.

As mentioned earlier in Section 3, Task I was completed during the first quarterly reporting period and accomplishments were documented in the Project Management Plan issued in August, 1990.

The Project Management Plan report is comprised of the following 9 sections:

- Executive Summary
- Background/Introduction
- Study Objective
- Overall Scope Of Work
- Configurational Management
- Program Administration
- Deliverables
- Baseline Configuration
- Appendix/Project Procedure Booklet
List Of Contents

The report completing Task 1 was published on time schedule. Detailed accomplishments of Task I were included in the first quarterly report (May 16, 1990 through August 19, 1990) of the project.

3.2 TASK II

Task II concerns the development of the baseline design of the coal liquefaction facility. This part of the study includes the acquisition of process licensor information, incorporation of various processing options into the design, and developing the design of the on-site processing units and offsite facilities (including storage and loading, utilities, and waste handling).

In this task certain plants are handled as packaged plants (or blocks) with an overall heat and material balance only.

3.2.1 Status Update on Process Plants

During this reporting period, several process plants were updated. Status of such updating is included in this section of the report.

3.2.1.1 Coal Liquefaction (Plant 2)

Design Basis Criteria and Considerations

Coal Feed

The coal to be fed to the coal liquefaction plant is washed and dried Illinois No. 6 coal (Burning Star Mine) from Plant 1, the Coal Preparation Plant. Analysis of the basis coal is presented in Table 3.1.

Coal feed to Plant 2 is approximately:

<u>Basis</u>	<u>Per Train</u>	<u>Total</u>
MF basis	3,420 TPSD	17,102 TPSD
MAF basis	3,028 TPSD	15,140 TPSD

Moisture in the coal feed is 2.0 wt. % and ash (MF) content is 11.47 wt. %.

Process

The process used will be close-coupled, catalytic-catalytic, two-stage coal liquefaction (H-COAL by HRI) with ashy recycle, recycle of extract from the critical solvent deashing plant, and recycle of 850°F+ to extinction.

Maximum Reactor Size

The maximum size reactor will process a feed rate of 3,028 TPSD (MAF basis), producing 12,389 BPSD of liquid products (C_5 -850°F). Five trains of the maximum size operating at capacity will be required to reach the proposed production of approximately 62,000 BPSD.

Nominal Reaction Conditions

Nominal coal liquefaction conditions will be:

Reactor Inlet Pressure, psig	3200
Reactor Outlet Pressure, psig	3000
Hydrogen Partial Pressure, psia (outlet of Stage 2 reactor)	1950
Coal Feed, lb MAF/lb catalyst	1.12
Solvent/Coal Ratio, (MAF wt. basis)	2.154
Solvent, wt. %	
Distillate (1000°F-)	38.0
Residuum (1000°F+)	49.9
Ash + Unconverted Coal	12.1
Slurry Tank Temperature, °F	400
Reaction Temperature, °F	
Stage 1	790
Stage 2	760
Coal Feed Analysis	(Table 3.1)

Table 3.1

**Analysis of Feed Coal to Liquefaction
Illinois No. 6 (Burning Star Mine)**

Proximate Analysis (wt. %, Dry Basis)

Volatile Matter	42.2
Fixed Carbon	46.3
Ash	11.5

Ultimate Analysis (wt. %, Dry Basis)

Carbon	71.0
Hydrogen	4.8
Sulfur	3.2
Nitrogen	1.4
Ash	11.5
Chlorine	0.1
Oxygen (by difference)	8.0

Sulfur Forms (wt. %, Dry Basis)

Pyrite	1.0
Sulfitic	0.1
Organic	1.9

Ash Composition (wt. % oxidized)

Phosphorus pentoxide, P_2O_5	0.2
Silica, SiO_2	49.8
Ferric Oxide, Fe_2O_3	17.6
Alumina, Al_2O_3	19.2
Titania, TiO_2	1.0
Lime, CaO	6.3
Magnesia, MgO	1.0
Sulfur Trioxide, SO_3	2.9
Potassium Oxide, K_2O	2.0
Sodium Oxide, Na_2O	0.5
Undetermined	-0.5

Catalyst and Catalyst Addition Rates

Catalyst for the coal liquefaction process will be Amocat 1C in both stages. The catalyst has a bulk density of 35 lb/cft. Catalyst addition rates are specified to be 3.0 lb of catalyst per ton of MAF coal feed for the first stage reactor and 1.5 lb of catalyst per ton of MAF coal feed for the second stage reactor.

Hydrogen Makeup

Makeup hydrogen gas is available at the pressure required for the coal liquefaction plant at a temperature of 110°F. The composition of the makeup hydrogen is approximately 99.0% (vol.) hydrogen and 1.0% (vol.) methane.

Yields

Yields from the coal liquefaction plant are presented in Table 3.2 below:

Table 3.2

Coal Liquefaction Yields

<u>Yields Wt.% MAF Coal Feed</u>	<u>First Stage Outlet</u>	<u>Overall</u>
H ₂ S	2.00	2.86
H ₂ O	7.10	9.51
NH ₃	0.95	1.39
CO	0.04	0.06
CO ₂	0.09	0.14
C ₁	0.91	1.84
C ₂	0.74	1.43
C ₃	0.85	1.52
C ₄	0.40	0.79
C ₅ -350°F	8.00	16.12
350-450°F	4.90	7.51
450-650°F	6.76	25.11
650-850°F	15.20	21.36
850-1000°F	18.52	0.66
1000°F+	26.80	8.39
Unconverted Coal	10.20	7.21
Phenols	0.24	0.30
Ash	12.96	12.96
Hydrogen Consumption	-3.70	-6.20

Product Quality

The API gravity of the product cuts from the first stage and second stage reactors is given in Table 3.3 below:

Table 3.3
Product Quality

<u>Product Cuts</u>	<u>Gravity (°API)</u>	
	<u>First Stage</u>	<u>Overall</u>
C ₅ -350°F	44.5	45.5
350-450°F	24.5	25.0
450-650°F	13.5	14.0
650-850°F	5.0	6.0
850-1000°F	-1.6	-1.5
1000°F+	-11.5	-10.5

Design Considerations

The design of the slurry preparation system of the Coal Liquefaction Plant was based on the concept used in the Breckinridge Project.

The capacity of an individual train was determined by HRI and it was based on reactor diameter and weight considerations. The coal throughput using the maximum-sized reactors was based on the space velocity used in Wilsonville run 257E. The liquefaction of each section including primary separation was designed by HRI.

The process, except the reaction system and slurry and hydrogen preheat system, was modeled using Simulation Science's PROCESS simulation software. The model was used to develop equipment sizing, product separations, and utility requirements for those portions of the plant not provided by HRI. Sizing information supplied by HRI was used directly in the study. This included the slurry and hydrogen preheat system, the reactor system, the high pressure separations system, and the recycle hydrogen compressor.

The process was developed making maximum use of air-fin coolers and condensers to a process outlet temperature of 130°F. The cooling of hot process fluids by steam generation was utilized wherever possible. Most of the steam generated was at the 150 psig level.

The separation system was developed with a two pressure level configuration. Each pressure had three separators: hot at the reactor effluent temperature (760°F), warm at approximately 550 °F, and cold at 130°F. The three separators configuration improved the purity of the recycle hydrogen stream, reduced the amount of heavy material in the gas stream sent to Plant 3, and reduced the amount of gases sent to atmospheric fractionation.

The coil outlet temperatures of the atmospheric and vacuum heaters was maximized to tube coking limitations. The pressures in the two fractionation towers was set at the lowest level practical by overhead condensing and vacuum system limitations in order to achieve as high a bottoms cut point as possible.

Two separate flush oil systems have been incorporated in the design. The light flush oil is taken from the atmospheric tower sidestream and is used for flushing instruments in slurry service. The heavy flush oil is taken from the vacuum tower upper sidestream and is used for flushing the seals of pumps in slurry service.

Process Description and Process Flow Diagrams

The plant consists of three sections. These are: Slurry Preparation and Liquefaction Reaction, Primary Separation and Product Fractionation. These three sections are schematically shown in process flow diagrams, Figures 3.1 through 3.3, respectively.

Slurry Preparation and Liquefaction Reaction

Coal, which has been pulverized and dried in Plant 1.4, is mixed with recycled oil from the downstream plants to form a slurry for feed to the coal liquefaction reactors. The recycle oil used as solvent for the process comes from four sources: slurry oil from the Slurry Hold Tank, upper sidestream product from the Vacuum Distillation Tower, the lower sidestream product (850-1000°F) from the Vacuum Distillation Tower, and the extract product from the Critical Solvent Deashing Plant (ROSE-SM), Plant 8.

Slurry preparation consists of prewetting and mixing. The prewetting occurs in a twin screw mixer in which the 850-1000°F product and a portion of the Vacuum Tower upper sidestream product, which have been cooled in air-fin exchanger (E102) to 180°F, are sprayed on the pulverized coal as it is being turned over in the mixer. This mixture is then fed into the Mix Tank (C101) where it is mixed with the solvent from the other two sources. Those oils are cooled in an exchanger producing 600 psig steam (E101) before entering the Mix Tank. The Mix Tank is equipped with a high-speed agitator. Coal slurry flows to the Slurry Surge Tank (C102) which also contains a mixer to keep the coal in the slurry. The Surge Tank is vented through a scrubber (C103), where the vapors are contacted with a portion of the solvent. The vapors from the scrubber are cooled in an air-fin exchanger (E103) to 130°F and separated into three phases in the Slurry Overhead Receiver (C104). The vapor from that drum

is sent as fuel to the Hydrogen Heater (F102). The hydrocarbon liquid is sent to the Atmospheric Tower. The sour water stream is withdrawn to the Sour Water Flash Drum (C116) and eventually to Plant 34.

Material from the Slurry Surge Tank is pumped by two Slurry Booster Pumps (G103) operating in parallel to the suction of three high pressure reciprocating Reactor Feed Pumps (G105) in parallel. About one-third of the flow from the Slurry Booster Pumps is recycled back to the Slurry Surge Tank to help eliminate dead spots in the tank where coal can settle out of the slurry. The Reactor Feed Pumps move the coal slurry through the Slurry Feed Heater (F101) to the reactors.

As shown on the attached Figure 3.1, the make-up hydrogen stream from coal gasification plant (Plant 9) is combined with the recycle hydrogen stream from Plant 6. A portion of the combined stream is then mixed with the recycle hydrogen stream from the Recycle Hydrogen Compressor (K101) and is first preheated by exchange against the reactor effluent in exchangers E107 and E106. The other portion of the combined hydrogen stream is injected into the coal slurry feed at the inlet to the Slurry Feed Heater (F101) in order to reduce the possibility of coke formation in the heater. Injection of hydrogen into the coal feed slurry also tends to reduce the viscosity of the slurry mixture and results in a lower pressure drop in the slurry feed heater coil. The hydrogen and coal slurry mixture is heated and then fed to the First Stage Reactor (C105). The remaining reactor hydrogen stream is fed to the First Stage Reactor after being heated in the Hydrogen Heater (F102).

The coal slurry-hydrogen mixture from the Slurry Feed Heater and the hydrogen stream from the Hydrogen Heater are introduced into the bottom of the First Stage Reactor. The reactor operates at approximately 790°F average reactor temperature and 3050 psig. The reactor operating temperature is controlled by adjusting the Slurry Feed heater outlet temperature to achieve the desired conversion level in the reactor.

Effluent from the First Stage Reactor is quenched with cold hydrogen from the recycle hydrogen compressor and introduced into the bottom of the Second Stage Reactor (C106). The interstage quench hydrogen flow rate is controlled to maintain the Second Stage Reactor in heat balance at 760°F average reactor temperature.

Figure 3.1 Process Flow Diagram

The reactors incorporate the principle of the ebullated-bed operation. The entire mass in the reactor is held in a fluidized ebullated state by recirculating coal-oil slurry from the top of the reactor through the Ebullating Pumps (G108 and G109) and back into the bottom of the reactor. The ebullated bed ensures the reactor's near isothermal operation under the extreme exothermic reactions involved. Since the coal particles are much finer than the extrudate catalyst, a separation can be made between these solids such that the coal and ash particles are entrained with the liquid-gaseous reactor effluent products, while the catalyst remains behind in suspension in the reactor.

Primary Separation

As shown on Figure 3.2, the effluent from the top of the Second Stage Reactor is sent directly to the Hot High Pressure Separator (C107) at 760°F and 3000 psig. The overhead vapor, after being separated from the slurry, is cooled to 550°F in exchange with recycle and makeup hydrogen in exchanger E106 and enters the Warm High Pressure Separator (C110). The temperature of the separator is set high enough to prevent precipitation of ammonium salts. The overhead of the warm separator is cooled to 130°F in exchange with recycle and makeup hydrogen in exchanger E107 and in air-fin exchanger E109 before entering the Cold High Pressure Separator (C113). Wash water is injected ahead of the air-fin cooler for control of ammonium salt deposition as the vapor is cooled. The vapor from that separator is compressed in the Recycle Hydrogen Compressor (K101) and returned to the reactors as recycle hydrogen. A portion of the stream is purged from the system to the Hydrogen Purification Unit (Plant 6) to prevent the build-up of methane and other non-condensables in the system. The water phase is withdrawn to the Sour Water Flash Drum (C116) and eventually to Plant 34 for recovery of anhydrous ammonia.

The liquid from the Hot High Pressure Separator is flashed to 100 psig in the Hot Low Pressure Separator (C108). The vapor from the Hot Low Pressure Separator is cooled from 750°F to 450°F in exchange with the Warm Low Pressure Separator liquid (E104) and in an exchanger producing 150 psig steam (E105). The mixed vapor-liquid stream then enters the Warm Low Pressure Separator (C111) along with the liquid from the Warm High Pressure Separator. The temperature of the separator is set high enough to prevent precipitation of ammonium salts. The vapor from the Warm Low Pressure Separator is cooled to 130°F in an air-fin cooler (E110) and enters the Cold Low Pressure Separator (C114) along with the liquid from the Cold High Pressure Separator. Wash water is injected ahead of the air-fin cooler for control of ammonium salt deposition. The vapor from this separator is sent to the Hydrogen Purification Plant, the liquid is sent to the Product Distillation Feed Flash Drum (C117), and the water phase is sent to the Sour Water Flash Drum (C116). The liquid from the Warm Low Pressure Separator is heated by the feed to that vessel in exchanger E104 and sent to the Product Distillation Feed Flash Drum. The liquid from the Hot Low Pressure Separator is further flashed to 20 psig in the Recycle Slurry Hold Drum (C109). The vapor is cooled in air-fin exchanger E108 and sent to the Recycle Slurry Hold Drum Overhead Accumulator. The vapor from this drum is sent to Plant 6, the liquid is sent to the Product Distillation Surge Drum, and the water phase is sent to the

Sour Water Flash Drum. Some of the liquid from the Recycle Slurry Hold Drum is pumped as recycle solvent back, using pump G110 to the coal slurry tank with the remainder being sent to the Product Distillation Surge Drum.

Product Fractionation

As shown in Figure 3.3, the liquid products from the three low pressure separators in the coal liquefaction plant are sent to the Product Distillation Feed Flash Drum (C117) from where the combined stream is pumped through the Atmospheric Feed Heater (F103) to the Atmospheric Distillation Tower (C118). Vapors from the surge drum are vented directly to the atmospheric tower. Two products are taken from the Atmospheric Tower Overhead Accumulator (C120): a naphtha product (IBP - 350°F) which is sent as feed to the Naphtha Hydrotreater; and a sour water stream which is sent to the Wash Water Surge Drum (C115) on the Coal Liquefaction Plant. An overhead vapor stream from the overhead accumulator is compressed by Compressor (K102) and sent to Plant 6. A sidestream product (350°F+) is withdrawn from a sidestream stripper (C119) and sent as feed to the Gas Oil Hydrotreater via cold (110°F) intermediate tankage. The bottoms stream off the atmospheric tower is pumped to two dispositions: as recycle solvent back to the Coal Slurry Tank with the remainder being sent to the Vacuum Feed Heater (F104) ahead of the Vacuum Distillation Tower (C122). Three products are taken overhead from the vacuum tower: a light gas oil product (450°F+) which is sent to the Gas Oil Hydrotreater via the same intermediate tankage as the atmospheric sidestream product; an overhead vapor stream which is compressed and sent to Plant 6; and a sour water stream which is sent to the wash water surge drum on the Coal Liquefaction Plant. An upper sidestream product (≈550°F - 850°F) is withdrawn and sent to the Gas Oil Hydrotreater via hot (400°F) intermediate tankage. Some of this stream is recycled back to coal slurry preparation as solvent. A lower sidestream product (850°F - 1000°F) is withdrawn from a sidestream stripper (C123) and sent as recycle solvent back to the Coal Slurry Tank. The vacuum tower bottoms stream is sent to the solids-liquids separation unit, Plant 8.

Figure 3.3 Process Flow Diagram

Material Balance

Plant 2 consists of 5 trains. The material balance per train is shown in Table 3.4. The overall material balance for the Plant 2 is schematically shown in Figure 3.4.

Table 3.4 Material Balance

PLANT 2 (5 TRAINS)								
PLANT INPUT								
Stream No.	2.2	2.3	2.4	2.6	2.5	2.1		
COMPONENTS	COAL #/hr	MAKEUP H2 #/hr	RECYCLE H2 FR #6 #/hr	WASH WATER #/hr	STEAM #/hr	ROSE EXTRACT #/hr	RXN DELTA #/hr	TOTAL INPUT #/hr
N2		223	70					293
H2		15900	4086				-15845	4341
H2O	5817		102	219929	49442		23997	299286
H2S			2				7217	7218
NH3			0				3507	3507
CO			42				151	193
CO2			0				353	353
C1			1501				4843	6144
C2			862				3608	4470
C3			668				3835	4503
C4			291				1993	2284
C5-350			171				40876	40847
350-450			1				18950	18952
450-650			0				63361	63361
650-850			0			76	53898	53974
850-1000			0			353	1665	2018
1000+			0			107317	21171	128488
PHENOLS			0				757	757
MEA			1					1
UNCONVERTED COAL	252333		0				-234140	18193
ASH	32702		0					32702
TOTAL	290852	16123	7794	219929	49442	107746	0	691886
TEMPERATURE (F)		100	100	126	*	300		
PRESSURE (psig)		3425	3425	3200	*	100		

Table 3.4 Material Balance - continued

PLANT OUTPUT							
Stream No.	2.7	2.8	2.9	2.10	2.11	2.12	
	PURGE H2	PURGE GASES	NAPHTHA	GAS OIL	ROSE UNIT FEED	SOUR WATER	TOTAL OUTPUT
COMPONENTS	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr
N2	205	88					293
H2	3442	899					4341
H2O	307	967	486			297526	299286
H2S	2022	2042	23			3131	7218
NH3	483	40				2984	3507
CO	135	58					193
CO2	173	80				100	353
C1	3623	2518	2			1	6144
C2	2007	2436	27				4470
C3	1315	3032	156				4503
C4	161	1781	342				2284
C5-350	85	5349	34227	1098		88	40847
350-450	0	54	631	15858		2409	18952
450-650		5		63354		2	63361
650-850				53898	76		53974
850-1000					2019		2019
1000+					128488		128488
PHENOLS						757	757
MEA		1					1
UNCONVERTED COAL					18193		18193
ASH					32702		32702
TOTAL	13958	19350	35894	134208	181478	306998	691886
TEMPERATURE (F)	130	130	140	110	688	**	
PRESSURE (psig)	2970	50	1	**	13	**	

Notes:

* This stream represents the combination of steam levels utilized by the plant.

** This stream represents a combination of output streams; a single temperature/pressure cannot be reported.

-- The combined sour water flow rate for the plant is represented by 2.12.

$$2.5 = 2.5A + 2.5B + 2.5C + 2.5D + 2.5E$$

$$2.8 = 2.8A + 2.8B + 2.8C + 2.8D$$

$$2.10 = 2.10A + 2.10B + 2.10C$$

$$2.14 = 2.14A + 2.14B$$

$$2.15 = 2.15A + 2.15B$$

BASELINE

NOTES: . Flow rate in lbs/hr

. Number in parenthesis is due to input stream (1). Therefore, to calculate the

% yield subtract out the corresponding number in parenthesis.

. The HC's in sour water are shown in net reactor effluent.

Figure 3.4 Overall Material Balance

Utility Summary

Table 3.5 below presents a summary of the utilities required for Plant 2.

Table 3.5
Plant 2 Utility Summary

Steam, lb/hr	
600 psig	-28,705
150 psig	-19,649
50 psig	11,223
Demineralized Water	
gpm	173
Cooling Water, gpm	1,619
Water, gpm	341
Fuel Gas, MMSCFD	5
Electricity, Kw	11,452
Nitrogen, MMSCFD	0.2

Note: Negative values represent utility production.

3.2.1.2 Gas Plant (Plant 3)

Design Basis, Criteria and Considerations

The Gas Plant consists of the following sections:

- Absorber/deethanizer
- Lean oil stripper/debutanizer
- Depropanizer
- LPG Merox for propane and butane products
- Makeup lean oil stripper

The Gas Plant will be designed as a two-train unit to increase the overall plant reliability.

Feed to the Gas Plant will be tail gas from the Hydrogen Purification Plant (Plant 6). Makeup lean oil is the naphtha product from Plant 2. Lean oil purge from the lean oil stripper/debutanizer will be sent to the Naphtha Hydrotreater (Plant 4). Lean oil stripper off gas is returned to Plant 6 for treating.

The products from the Gas Plant include:

- C₃ LPG
- C₄ LPG
- Fuel Gas

The specification for the two LPG products are as follows:

<u>Specification</u>	<u>C₃ LPG</u> <u>Max.</u>	<u>C₄ LPG</u> <u>Max.</u>
Ethane (vol.%)	2.0	--
Propane (vol.%)	--	2.0
Butane (vol.%)	2.0	--
Pentane (vol.%)	--	2.0
Mercaptans (wt.ppm)	20	20

Design Considerations

Lean oil absorption was used as the method to recover light hydrocarbons from miscellaneous gas streams being sent to the fuel gas system because of the high recovery of propane and butanes, smaller equipment sizes, and recovery without the need for a refrigeration system. The lean oil absorber and rich oil deethanizer operations were combined into a single tower to reduce capital and operating costs.

Naphtha product from the Coal Liquefaction Plant is used as the lean oil makeup. Because the makeup rate is close to the Plant 2 production rate, the total naphtha stream was sent to the Gas Plant. The lean oil purge (Stripper/Debutanizer bottoms) is sent as feed to the Naphtha Hydrotreater. This scheme simplifies the operation of the system and reduces the amount of light components in the feed to Plant 4. The makeup lean oil is stripped prior to entering the absorption system to remove ammonia and acid gases which may contaminate LPG products or fuel gas and light hydrocarbons which may be lost to fuel gas in the absorber overhead stream.

Some pentanes are lost to fuel gas in the absorber overhead vapor stream due to vapor-liquid equilibrium. A refrigerated cooler would be required to recover this lost material; however, little additional propane recovery would be made since the recovery rate is already quite good.

Plant 3 was modeled using the PROCESS simulation software. Equipment was sized using these simulations.

As pointed out earlier, the plant consists of five sections. These are: Absorber/Deethanizer, Lean Oil Stripper/Butanizer, Depropanizer, Makeup Lean Oil Stripper and LPG Merox for propane and butane products. The first four sections of this plant are shown in Process Flow Diagram, Figure 3.5 and the Merox section is shown in Process Flow Diagram, Figure 3.6. The description of each of these sections is included below.

Absorber/Deethanizer

Compressed tail gas from the pressure swing absorption (PSA) unit of the Hydrogen Purification Plant (Plant 6) is fed to a combined lean oil absorber/deethanizer tower to recover the propane and heavier liquids in the stream. The tower is operated at 160 psig. The tower has a reboiler to strip the ethane and lighter components from the rich oil exiting the bottom of the tower. The overhead gas is mixed with the recirculated lean oil and the makeup lean oil and sent to a water cooler before entering the precontactor drum. The vapor product is sent directly to the fuel gas system. The liquid from the precontactor is fed to the top tray of the absorber/deethanizer tower. The precontacting operation improves the recovery of propane from fuel gas and reduces the losses of pentanes in the lean oil to fuel gas by operating the vapor/liquid separation at a lower temperature than available at the top tray of the tower.

Lean Oil Stripper

The lean oil is the naphtha product from Plant 2. The Plant 2 naphtha contains hydrogen sulfide and ammonia which would contaminate the fuel gas, propane, and mixed butane products. Prior to being sent to the absorber/deethanizer as makeup lean oil, the naphtha is stripped of the contaminants in a stripper tower, which operates as a debutanizer. The stripped gases are sent to the low pressure gas compressor in Plant 6 for scrubbing, and recovery of hydrogen and light gases.

Stripper/Debutanizer

Rich oil from the absorber/deethanizer tower is sent to the rich oil stripper tower to remove propane and butanes from the lean oil. The lean oil from the stripper tower is returned to the absorber/deethanizer via heat exchange with the rich oil feed. Some of the recirculated lean oil is purged to the Naphtha Hydrotreater (Plant 4) to remove pentane and heavier hydrocarbons recovered from the feed gases and maintain a more consistent lean oil composition.

Depropanizer

The overhead product from the stripper is fed to a depropanizer tower to separate the light hydrocarbons into two LPG products (propane and mixed butanes). The two products are sent to individual Merox units for the removal of trace sulfur compounds prior to being sent to product storage.

Merox Treating

The Merox units remove mercaptan sulfur compounds from the LPG products (propane and mixed butanes) by dissolving the compounds in a 20° Baume caustic soda solution. This is accomplished in a multistage, vertical Merox extraction. A caustic prewash of 10° Baume solution is required to remove any remaining hydrogen sulfide from the feed stream before entering the extraction tower. The mercaptan-rich caustic solution from the bottom of the extraction towers of the two Merox units flow to the common regeneration section through a small steam heater. The caustic stream is regenerated with air in the presence of a catalyst, where the mercaptans are converted to disulfides. The caustic stream is returned to the Merox units, and the disulfide stream is sent to the Naphtha Hydrotreater feed for disposal.

Plant 3 Gas Plant

Figure 3.5 Process Flow Diagram

Figure 3.6 Process Flow Diagram

Material Balance

The material balance for a single train of this plant is shown in table 3.6 on the next page. Two trains are required.

PLANT 3 (2 TRAINS)

COMPONENTS	PLANT INPUT				PLANT OUTPUT							
	3.1	3.2	TOTAL		3.3	3.6	3.4	3.7	3.8	3.5	TOTAL	
	PLT 2 NAPH #/hr	PSA TG FR PLT 6 #/hr	INPUT #/hr	INPUT #/hr	LO OH GASTO #6 #/hr	SOUR WATER #/hr	FUEL GAS #/hr	PROD #/hr	MIX. C4 PROD #/hr	NAPHTHA TO PLT 4 #/hr	OUTPUT #/hr	OUTPUT #/hr
N2	0	639	639				639				639	
H2	0	1127	1127		0		1127				1127	
H2O	1215	1519	2734		23	1192	1519				2734	
H2S	58	22	79		58		22				79	
NH3	0	0	0				0				0	
CO	0	378	378				378				378	
CO2	0	0	0				0				0	
C1	5	16238	16243		5		16237	1			16243	
C2	68	13192	13259		68		12972	216	4	0	13259	
C3	390	15875	16265		390		24	15641	210	0	16265	
C4	855	14688	15543		855		70	431	14086	101	15543	
C5-350	85568	20549	106117		599		3150	347		102021	106117	
350-450	1578	52	1630		0		1			1629	1630	
450-650	0	13	13		0					13	13	
650-850	0	0	0							0	0	
850-1000	0	0	0							0	0	
1000+	0	0	0							0	0	
PHENOLS	0	0	0							18	18	
MEA		18	18							0	0	
UNCONVERTED COAL	0	0	0							0	0	
ASH	0	0	0							0	0	
TOTAL	88735	84309	174044		1987	1192	36139	16289	14647	103781	174044	
TEMPERATURE (F)	140	95			137	137	100	100	100	130		
PRESSURE (psig)	50	210			40	40	200	285	285	248		

TABLE 3.6

Material Balance

Plant 3

Utility Summary

The utility requirement for this plant is summarized in Table 3.7

Table 3.7 Utility Summary

Plant 3 – Gas Plant

Utilities Summary

The utilities noted below are for one gas plant train.

<u>Equipment Number</u>	<u>Equipment Description</u>	<u>Duty (MMBTU/Hr)</u>	<u>Steam Rate, lbs/hr</u>		
			<u>50 psig</u>	<u>150 psig</u>	<u>600 psig</u>
<u>Steam Consumed</u>					
E103	Absorb/Deeth Reboiler	77.3			106,079
E106	Lean Oil Str Reboiler	43.6			59,833
E109	Depropanizer Reboiler	7.8	8,557		28,818
E112	LO Makeup Strp Reboiler	21.0			
	Mercox Units		36		0
TOTAL			8,593	0	194,730

Table 3.7 Utility Summary - continued

Plant 3 - Gas Plant

Utilities Summary (cont.)

<u>Equipment Number</u>	<u>Equipment Description</u>	<u>BHP</u>	<u>Motor HP</u>	<u>Motor Efficiency</u>	<u>Motor kW</u>
<u>Electricity</u>					
<u>Pumps</u>					
G101	Absorb/Deeth Precontact Liq	55	75	90	46
G102	Intercooler Pumparound	55	75	90	46
G103	Lean Oil Strp Reflux	125	200	91	102
G104	Lean Oil Circulation	55	75	90	46
G105	Depropanizer Reflux	9	15	85	8
G106	LO Makeup Strp Reflux	6	10	83	5
G107	LO Makeup Strp Sour Water	1	2	73	1
G108	LO Makeup Strp Btms	45	60	90	37
<u>Alr-fin Exchangers</u>					
E104	Lean Oil Cooler	108	40	89	91
E111	LO Oil Makeup Strp Ovhd Cond	36	40	89	30
E113	LO Oil Makeup Strp 1st Btms Clr	36	40	89	30
<u>Miscellaneous</u>					
<u>Mercox Units</u>					
TOTAL					1 443

Table 3.7 Utility Summary - continued

Plant 3 - Gas Plant

Utilities Summary (cont.)

<u>Equipment Number</u>	<u>Equipment Description</u>	<u>Duty (MMBtu/Hr)</u>	<u>Delta T (degF)</u>	<u>CW Rate (GPM)</u>
<u>Cooling Water</u>				
E101	Absorb/Deeth Ovhd Cooler	7.0	8	1,750
E102	Absorb/Deeth Intercooler	1.6	13	246
E105	Lean Oil Str Ovhd Condenser	31.5	8	7,875
E108	Depropanizer Ovhd Condenser	7.2	28	514
E110	Depropanizer Btms Cooler	0.5	8	125
E114	LO Makeup Strp 2nd Btms Clr	1.2	8	300
E115	Depropanizer Ovhd Cooler	0.4	8	100
TOTAL				10,910

3.2.1.3 Naphtha Hydrotreater (Plant 4)

Design Basis, Criteria and Considerations

The Naphtha Hydrotreater will be designed as a two-train unit to increase the overall plant reliability.

Feed to the Naphtha Hydrotreater will be the naphtha (C₅-350°F) product from the atmospheric fractionator tower at the Coal Liquefaction Plant (Plant 2) via the Gas Plant (Plant 3).

Design criteria for the Naphtha Hydrotreater is based on the following:

Reactor Inlet Pressure, psig	1,000
Reactor Outlet Pressure, psig	950
Hydrogen Partial Pressure, psia (outlet of reactor)	700
Reactor Inlet Temperature, °F	525
Reactor Outlet Temperature, °F	575
Chemical Hydrogen Consumption, SCF/B	125
LHSV, V/V/hr	2.0
Catalyst Type	NiMo

Characteristics of the product from the Naphtha Hydrotreater is given in Table 3.8 below:

Table 3.8

Naphtha Hydrotreater Product Characteristics

	<u>C₅-350°F</u>
Gravity, °API	52.2
Distillation, TBP °F	
IBP	72
5% (wt.)	110
10%	138
30%	207
50%	246
70%	284
90%	328
95%	340
EP	344
Sulfur, wppm (maximum)	1.0*
Nitrogen, wppm (maximum)	0.2*

*Note: When Nitrogen Specification is achieved at 0.2 wppm Sulfur level will go down further (0.1 wppm).

Design Considerations

Because the Naphtha Hydrotreater is a vapor phase reaction, only cold separators (both high pressure and low pressure) are included in the design of the plant.

The naphtha stream from the Gas Oil Hydrotreater is sent directly to the Plant 4 fractionator because it has already been treated at more severe conditions than those in the Naphtha Hydrotreater.

The fractionator was designed to use 600 psig steam for the reboiler because the bottoms temperature is 450°F and to reduce capital costs.

Process Description and Process Flow Diagram

The Plant includes two distinct sections. These are: 1) Reaction and Primary Separation section and 2) Product Distillation section. Figure 3.6 is the Process Flow Diagram of the Plant.

Reaction and Primary Separation Section. Feed is pumped from intermediate tankage directly to heat exchange with the reactor effluent (E101). Hydrogen is then mixed with the heated feed prior to entering the reactor feed preheater (F101), where the mixture is raised to the reactor inlet temperature. The feed/hydrogen mixture enters the fixed bed reactors (C101 and C102), which operate at a pressure of 1000 psig. The reactor effluent passes through heat exchange with the cold feed (E101), through an air-fin cooler (E102), and to the high pressure separator (C103). Wash water is injected into the reactor effluent line prior to the air-fin cooler for control of ammonium salts. Hydrogen rich vapor is compressed in K101 and returned to the front end of the unit to mix with makeup hydrogen and the unit feed. A purge gas stream is sent to Plant 6 to remove light hydrocarbons from the system. Sour water is removed from the high pressure separator to be eventually sent for ammonia recovery. The hydrocarbon liquid is flashed to 185 psig in the low pressure separator (C105) to remove light hydrocarbons, which are sent to Plant 6. The low pressure separator liquid is then sent to product distillation.

Product Distillation. The low pressure separator liquid is preheated with the product from the fractionator in exchanger E105 before entering the tower (C106). The overhead vapor from the tower is partially condensed and only a vapor product is withdrawn for further processing at Plant 6. The fractionator has a steam-heated reboiler (E104). The bottoms naphtha product is cooled in exchangers (E105 and E106) and sent to product storage.

Plant 4 Naphtha Hydrotreater

Figure 3.7 Process Flow Diagram

Notes: (1) Combined sour water rate is represented by 4.5

Material Balance

Material balance for Plant 4 is shown in Table 3.9. There are two trains in the plant.

Table 3.9 Material Balance
PLANT 4 (2 TRAINS)

COMPONENTS	PLANT INPUT							PLANT OUTPUT					
	4.8	4.9	4.3	4.4	4.7	4.1	4.2A	4.5	4.2B	4.6	4.1	4.2A	4.5
	NAPHTHA FROM #3	PLT # KO	H2 FROM LIQ PLT. 9 & 8	WASH WATER	PLT 5 NAPHTHA	TOTAL INPUT	RXN DELTA						
	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr	#/hr
N2	0	0	0	10	0	10	-246	7	3	10	7	3	10
H2	0	0	0	1250	0	1250	567	948	56	1004	948	56	1004
H2O	0	128	0	9386	0	9514	11	24	23	10081	24	23	10081
H2S	0	0	0	0	0	0	207	0	0	11	0	0	11
NH3	0	0	0	0	0	0	0	8	37	207	8	37	207
CO	0	0	0	0	0	0	0	0	0	0	0	0	0
CO2	0	0	0	0	0	0	0	380	168	549	380	168	549
C1	0	2	3	0	1	6	364	128	245	373	128	245	373
C2	0	7	0	0	2	9	350	61	363	424	61	363	424
C3	0	25	0	0	49	74	1301	103	1724	2008	103	1724	2008
C4	101	59	0	0	455	615	-8985	288	143	103591	288	143	103591
C5-350	102021	1393	0	0	9573	112987	5796			8361			8361
350-450	1629	175	0	0	763	2568	-1			12			12
450-650	13	0	0	0	0	13	0			0			0
650-850	0	0	0	0	0	0	0			0			0
850-1000	0	0	0	0	0	0	0			0			0
1000+	0	0	0	0	0	0	0			0			0
PHENOL.8	0	0	0	0	0	0	-16			2			2
MEA	18	0	0	0	0	18	0			0			0
UNCONVERTED COAL	0	0	0	0	0	0	0			0			0
ASH	0	0	0	0	0	0	0			0			0
TOTAL	103781	1787	1263	9386	10843	127059	0	1947	2	10208	1947	2	10208
TEMPERATURE (F)	130	130	100	112	136			135	135	100	135	135	100
PRESSURE (psig)	148	150	1075	950	200			815	100	153	815	100	153

* This stream represents a combination of streams; a single pressure cannot be reported.

Utility Summary

The utility summary for this Plant is included in Table 3.10.

Table 3.10

Utility Summary

	<u>(per Train)</u>
Steam, lbs/hr (160 psig)	13,311 lbs/hr
Electricity, KW	563.5
Fuel Gas, MM SCFD	0.9
Cooling Water, gpm	1,282

Note: Fuel gas consumption is based on a heating value of 1000 Btu/SCF.

3.2.1.4 Gas Oil Hydrotreater (Plant 5)

Design Basis Criteria and Considerations

The Gas Oil Hydrotreater is designed as a two-train unit to increase the overall plant reliability.

Feeds to the Gas Oil Hydrotreater are the distillate sidestream from the atmospheric tower and the overhead liquid and the upper sidestream from the vacuum tower of the Coal Liquefaction (Plant 2). The three products (350-450°F, 450-650°F, and 650-850°F) will be separated in a fractionator on the back-end of the unit.

Characteristics of the three feeds from Coal Liquefaction are presented in Table 3.11 below:

Table 3.11

Feeds to the Gas Oil Hydrotreater

	<u>Atmospheric Sidestream</u>	<u>Vacuum Overhead</u>	<u>Vacuum Upper SS</u>
Feed Rate, BPSD	16,366	200	25,204
Gravity, °API	16.8	38.1	8.0
Product Cuts (wt.%)			
C ₅ - 0.1	0.5	0.0	
C ₆ -350°F	2.4	71.6	0.4
350-450°F	24.3	23.2	1.8
450-650°F	51.8	4.7	30.1
650-850°F	20.5		66.3
850-1000°F	0.9		1.4

Design criteria for the Gas Oil Hydrotreater is based on the following:

Reactor Inlet Pressure, psig	2,600
Reactor Outlet Pressure, psig	2,500
Hydrogen Partial Pressure, psia (outlet of reactor)	1,800
Reactor Inlet Temperature, °F	600
Reactor Outlet Temperature, °F	750
Chemical Hydrogen Consumption, SCF/B	1,000
LHSV, V/V/hr	1.0
Catalyst Type	NiMo

Characteristics of the products from the Gas Oil Hydrotreater are given in Table 3.12 below:

Table 3.12
Product Quality of the Gas Oil Hydrotreater

	<u>350-450°F</u>	<u>450-650°F</u>	<u>650-850°F</u>
Gravity, °API	29.9	17.3	10.5
Distillation, TBP °F			
IBP	340	414	640
5% (wt.)	348	463	645
10%	358	469	665
30%	376	531	676
50%	399	576	717
70%	414	619	759
90%	433	645	815
95%	449	655	835
EP	465	665	838
Sulfur	20	20	20
Nitrogen	500	500	500

Design Considerations

Three final products (350-450°F, 450-650°F, and 650-850°F) were combined for hydrotreating in the same unit because of the reasons below:

- The reactions conditions recommended are approximately the same for the two heavier products and the lighter product is relatively small.
- Significant savings in capital cost and operating cost are realized by hydrotreating in a common unit even though final fractionation is more complex.
- The initial fractionation on the Coal Liquefaction Plant can be made as rough cuts and thus save capital and operating costs.

The reaction system was designed with parallel reactors and only one in series. Because of the reaction conditions, the reactors were designed with two catalyst beds with an interbed hydrogen quench.

The separation system was designed with high and low pressure systems, each with hot and cold separators. There was no incentive for a warm separator as in Plant 2. The letdown from the high pressure to the low pressure systems was done through an expander turbine to improve the efficiency of the process. The expander was designed to drive the reactor feed booster pump.

It was very difficult to fractionate all three products on the same tower; therefore, the 450°F- material was taken overhead in the fractionator to a small outboard stabilizer tower to make the front-end cut on the 350-450°F product. There was no problem fractionating the 450-650°F as a sidestream product or the 650-850°F as a bottoms product.

Process Description and Process Flow Diagram

This Plant consists of two sections. These are: 1) Reaction and Separation section and 2) Product Distillation section. Figure 3.8, the Process Flow Diagram, schematically depicts the process. The process description is broken down in two parts according to the above two sections.

Reaction and Separation Section

Cold feed is pumped from intermediate tankage through heat exchange with the sidestream product of the atmospheric tower of the Coal Liquefaction Plant. Hot feed is pumped from intermediate tankage directly to the Gas Oil Hydrotreater and is mixed with the preheated cold feed. The mixed feed is pumped up to reactor pressure in the reactor charge pump (G101) driven by an hydraulic expander turbine. The mixed feed is sent through heat exchange with the reactor effluent in E101. Recycle and makeup hydrogen are mixed and heated first in heat exchange with the reactor effluent (E102) and then in a fired heater (F101).

The hydrogen is then mixed with the heated feed prior to entering the fixed bed reactors (C101 and C102), which operate at an inlet pressure of 2600 psig. The reactor effluent passes through sequential heat exchange with the cold feed (E101), hydrogen gas (E102), and the hot low pressure separator liquid (E103) before being sent to the hot high pressure separator (C103). The vapor from the hot high pressure separator is cooled in an air-fin exchanger (E104) and is sent to the cold high pressure separator (C104). Wash water is injected into the reactor effluent line prior to the air-fin cooler for control of ammonium salts. Hydrogen rich vapor from the cold high pressure separator is compressed by K101 and returned to the front end of the unit to mix with makeup hydrogen.

A purge hydrogen stream is sent to Plant 6 to remove light hydrocarbons from the system. Sour water is removed from the cold high pressure separator to be eventually sent for ammonia recovery. The hydrocarbon liquid is sent to the cold low pressure separator (C106). The liquid from the hot high pressure separator is sent to an hydraulic expander turbine (Y101) driving the reactor charge pump before going to the hot low pressure separator (C105). The hot low pressure separator liquid passes through heat exchange with the reactor effluent (E103) and is then sent to product distillation. The hot low pressure separator vapor is cooled in an air-fin exchanger (E105) and sent to the cold low pressure separator (C106). The vapor from this separator is sent to Plant 6, and the liquid is sent to product distillation. Sour water is removed from the cold low pressure separator to be eventually sent for ammonia recovery.

Figure 3.8 Process Flow Diagram

Product Distillation

Liquid from the hot low pressure separator is preheated in exchange with the product fractionator bottoms in E111 and charged as the lower feed to the fractionator (C110). Liquid from the cold low pressure separator is the upper feed to the fractionator. The overhead of the tower has three products: an overhead vapor stream which is sent to Plant 6; an unstabilized liquid product; and a water stream which is recycled to the wash water system. The overhead liquid is sent to an outboard stabilizer (C115) for correcting the initial boiling point of the 350-450°F product. The overhead of the stabilizer has a vapor product which is sent to Plant 6 and a liquid product which is sent to the Naphtha Hydrotreater (Plant 4) product distillation section. The stabilized 350-450°F product is sent to final storage. The sidestream off the main fractionator is steam-stripped (C111) to correct the initial boiling point, cooled, and sent to finished product storage (450-650°F). The bottoms product is sent to heat exchange with the lower feed to the fractionator (E111), cooled in E113, and sent to finished product storage (650-850°F).

Material Balance

The material balance for this plant is shown in Table 3.13. The plant consists of two trains. The material balance shown in the table is for one train only.

PLANT 5 (2 TRAINS)
MATERIAL BALANCE

TABLE 3.13

Stream No.	PLANT INPUT						PLANT OUTPUT									
	5.1	5.2	5.3	5.4	5.5	5.6	5.7-5.9	5.10	5.11	5.12	5.13					
	TT PLT 2 GAS OIL #/hr	H2 FROM #9 & #6 #/hr	WASH WATER #/hr	STEAM #/hr	TOTAL INPUT #/hr	RXN DELTA #/hr	H2 PURGE #/hr	TT VAP TO PLT 6 #/hr	SW VAP TO PLT 6 #/hr	TT SOUR WATER #/hr	STBOH TO PLT 4 #/hr	LT DIST #/hr	HVY DIST #/hr	GAS OIL #/hr	TOTAL OUTPUT #/hr	
COMPONENTS																
N2	0	73			73	-5146	51	22							73	
H2	0	9245			9245	2355	3313	784	2	0					4089	
H2O	0	0	18191	2500	20691	115	396	674	3	21880			94		23047	
H2S	0	0			0	879	1	4		110					115	
NH3	0	0			0		28	57	2	793					879	
CO	0	0			0			0							0	
CO2	0	0			0			0							0	
C1	0	24			24	4092	2935	1175	3	2	1				4116	
C2	0	0			0	3827	1937	1867	1	1	2		19		3827	
C3	0	0			0	5937	2102	3784	1	1	49				5937	
C4	0	0			0	8391	1944	5892	1	1	455				8391	
C5-350	2745	0			2745	17958	1166	6590	1	5	9573	3353	14		20701	
350-450	39845	0			39845	11494	11	85		71	763	45660	4549		51139	
450-650	158385	0			158385	-8036		1		13		925		16263	150349	
650-850	134745	0			134745	-45985		0					12319	76461	88780	
850-1000	0	0			0	4101		0					2	4098	4101	
1000+	0	0			0			0							0	
PHENOLS	0	0			0			0							0	
MEA	0	0			0			0							0	
UNCONVERTED COAL	0	0			0			0							0	
ASH	0	0			0			0							0	
TOTAL	335520	9341	2500	19191	365552	0	13884	21034	12	22876	10843	49938	150144	96823	365553	
TEMPERATURE (F)	299	100	650				135			135	135	110	135	135		
PRESSURE (psig)	50	2600	50				2890			-	10	80	20	20		

* This stream represents a combination of input/output streams of the plant; a single temperature and pressure cannot be reported.

Utility Summary

The utility requirement per train for this plant is summarized in Table 3.14.

Table 3.14

Utility Summary

Steam, lbs/hr	
150 psig	16,932 lbs/hr
600 psig	32,524 lbs/hr
Electricity, KW	1057
Fuel Gas, MM SCFD	1.9
Cooling Water, gpm	4,114

3.2.1.5 Hydrogen Purification (Plant 6)

Design Basis Criteria and Considerations

A centralized hydrogen purification unit is being proposed. The unit will have two major sections:

1. Recovery of hydrogen from high pressure purge gas from the five coal liquefaction plants and gas oil hydrotreater.
2. Recovery of hydrogen from lower pressure purge gas from five coal liquefaction plants, the gas plant and hydrotreaters.

The first section will take sour purge gas from the coal liquefaction plants and gas oil hydrotreater. The hydrogen-rich gas will be water-washed and amine-treated to remove ammonia, carbon dioxide, and hydrogen sulfide. Part of the scrubbed gas will be recycled to plant 2 and the rest will be sent to membrane units for hydrogen recovery. This process was selected because the pressure of the hydrogen product is much higher than for a pressure swing absorber, thus saving recompression costs (both capital and operating). The hydrogen product at a minimum purity level of 99.0 mol% and H_2 product from PSA unit and will be compressed to required pressure. The nonpermeate product will be sent to the PSA unit.

The second section of the plant is fed compressed and treated low pressure gas from the overhead of the Plants 2, 3, 4, and 5. Pressure swing absorption will be used for this service because of the high recovery of hydrogen and because the feed gas pressure is consistent with the point of maximum recovery of hydrogen. The hydrogen product at a minimum of 99.0 mol% purity will be compressed and combined with the hydrogen product from the membrane unit. The light hydrocarbon tail gas stream will be sent to the Gas Plant.

The original flow scheme for the Hydrogen Purification Plant was for the compression and treating of the low pressure gases be done in the Gas Plant with the absorber/deethanizer overhead stream being sent to Plant 6 for hydrogen recovery in the pressure swing absorption (PSA) unit. Because the low pressure gases contained a high percentage of hydrogen and the resultant vapor-liquid equilibrium considerations, it was impossible to obtain an acceptable recovery of propane and butanes in the absorber/deethanizer. Therefore, the flow scheme was switched to place the PSA unit before the absorber/deethanizer. This then caused the move of the compression and treating of the low pressure gases to Plant 6.

The high pressure hydrogen purge streams were sent to a membrane unit for hydrogen recovery rather than a PSA unit because the membrane can better accept a high pressure feed stream, resulting in a higher pressure hydrogen product. This saved hydrogen compression costs. The PSA unit was preferred in the low pressure service because of the higher hydrogen recovery and lower pressure drop in the system. This also saved hydrogen compression costs.

The first stage hydrogen compression on the PSA product exited at the outlet pressure of the membrane unit. The two hydrogen streams were combined before being compressed to the required pressure. This saved capital costs.

Process Description and Process Flow Diagram

The Hydrogen Purification Plant has two sections: (1) recovery of purified hydrogen from high pressure purge gas streams in membrane separation units, and (2) recovery of purified hydrogen from low pressure offgas streams in pressure swing absorption (PSA) units. These are designated as Plant 6.1 and 6.2, respectively. Figure 3.10 is the process flow diagram for Plant 6.1 where Figures 3.10 and 3.11 combined show the process flow diagram for Plant 6.2.

Plant 6.1 High Pressure Purge Gas by Membrane

Purge Gas Scrubbing. The portion of the cold high pressure separator vapor which is purged from the Coal Liquefaction Plants combined with H_2 product from gas oil hydrotreater and is sent to Plant 6. The sour gases are sent first to a water wash tower (C104) to remove ammonia. The ammonia water is sent to Plant 38 for the recovery of anhydrous ammonia. The gas stream exiting the water wash tower is sent to the amine treater (C109) for the removal of carbon dioxide and hydrogen sulfide. The rich amine is sent to a common amine regeneration system located in the low pressure recovery section of the plant. The capacity for the water wash and amine treater towers are provided in two parallel trains for reliability.

Part of the treated hydrogen purge stream is recycled back to coal liquefaction and the rest is sent to the membrane unit.

Membrane Separation Unit. The scrubbed high pressure purge gas is sent to membrane separation units (V101) for hydrogen recovery. This process was selected because the pressure of the hydrogen and nonpermeate products is much higher than for a pressure swing absorber, thus saving recompression costs (both capital and operating). The hydrogen product at a minimum purity level of 99.0 mol% and the purified hydrogen streams from the PSA unit are combined and compressed in the second stage hydrogen compressor (K106), driven by an electric motor. The discharge of the second stage compressor is cooled in an air-fin exchanger (E111). Part of the discharge is sent to plant 4 and part of H_2 makeup. The other part is combined with the treated H_2 purge stream and is compressed to 3300 psig in K-108 and recycled to plant 2. The rest of E111 discharge is sent to K107 and is compressed to the pressure required by plant 5. The K107 discharge stream is cooled in an air-fin exchanger (E112) and with cooling water (E113) before exiting the plant to the makeup hydrogen system. The nonpermeate product is sent to the PSA units for recovery of residual hydrogen.

Plant 6.2 Low Pressure Offgas by PSA

Low Pressure Gas Compression. Miscellaneous gas streams are recovered from Coal Liquefaction (Plant 2), Gas Plant (Plant 3), the Naphtha Hydrotreater (Plant 4), and the Gas Oil Hydrotreater (Plant 5). The low pressure gases (less than 180 psig) are sent to the Low Pressure Gas Compressor (K101). The compressor will have a suction pressure of 5 psig and an intermediate suction of 40 psig. The discharge of the first stage compressor will be cooled in air-fin exchanger E101. The second stage compressor (K102) discharge will be at 250 psig. The discharge from the compressor will be cooled in air-fin exchanger E102.

Low Pressure Gas Scrubbing. Gases after compression are sent first to a water wash tower (C103) to remove ammonia. The ammonia water is sent to Plant 38 for the recovery of anhydrous ammonia. The gas stream exiting the water wash tower is sent to the amine treater (C106) for the removal of carbon dioxide and hydrogen sulfide. The rich amine is sent to a common amine regeneration system. The capacity for the water wash and amine treater towers are provided in two parallel trains for reliability.

Pressure Swing Absorption Unit. This section of the plant is fed the low pressure gas (200 psig) from the overhead stream from the amine treater and the membrane nonpermeate product. Pressure swing absorption (PSA) will be used for this service because of the high recovery of hydrogen. The hydrogen product is at a minimum purity of 99.0 mol %. The product from the PSA unit (V102) is compressed from 190 psig to 500 psig in motor-driven reciprocating compressors (K105). This first stage of compression takes the lower pressure stream up to the product pressure of the membrane separation unit. The first stage discharge is cooled in an air-fin exchanger (E110) and will be sent to Plant 6.1 for further compression. The PSA tail gas stream will be compressed to 200 psig in a two-stage compressor (K103 and K104), cooled by intercooler E107 and aftercoolers E108 and E109, and sent to the Gas Plant for recovery of propane and heavier hydrocarbons.

Amine Regeneration. As shown in Figure 3.11, rich amine streams from the high pressure and intermediate pressure amine treaters are collected in the combined amine separator (C111). Flashed acid gases are sent to the Sulfur Plant (Plant 11). The rich amine is filtered (Y101) and preheated with the lean amine bottoms in exchanger E105 before entering the amine regenerator C112. The overhead acid gas stream is sent to Plant 11. The regenerated lean amine is cooled in E105 and enters the regenerated amine surge drum (C114). Lean amine is then cooled in exchanger E106, filtered (Y102 and Y103), and pumped back to the intermediate pressure amine treater by pump G101 and to the high pressure amine treater by pump G102.

Plant 6.1

High Pressure H2 Recovery

Figure 3.9 Process Flow Diagram

NOTE: 6.9 from 2.8 : 6.10 from 3.3
 6.11 from 4.1 + 4.2a + 4.2b
 6.12 from 5.7 + 5.8 + 5.9 + 5.19

Plant 6.2
 Low Pressure H₂ Recovery
 Figure 3.10 Process Flow Diagram

Plant 6.2
Amine Regeneration

Figure 3.11 Process Flow Diagram

Material Balance

The material balance for the plant is shown in Table 3.15.

Table 3.15 Material Balance

PLANT INPUT

Stream No.	6.3	6.4	6.2+6.13	6.9	6.10	6.11	6.12	6.34	TOTAL
COMPONENTS	PLT 2 H2 PURGE #/hr	PLT 5 H2 PURGE #/hr	WATER #/hr	PLT 2 TO PSA #/hr	PLT 3 TO PSA #/hr	PLT 4 TO PSA #/hr	PLT 5 TO PSA #/hr	MAKEUP AMINE #/hr	INPUT #/hr
N2	1024	102		439	0	20	44		1827
H2	17210	6628		4498	0	2008	1572		31912
H2O	1535	792	30000	4835	48	95	1353	1831	40487
H2S	10110	2		10212	115	0	8		20447
NH3	2415	58		202	0	90	118		2879
CO	877	0		290	0	0	0		987
CO2	865	0		401	0	0	0		1286
C1	18118	5870		12588	10	1097	2356		40038
C2	10035	3874		12179	135	745	3738		30704
C3	6575	4204		15180	780	847	7570		35138
C4	805	3888		8908	1710	3854	11984		30947
C5-350	425	2332		28743	1198	862	13180		44740
350-450	0	22		268	0	0	170		480
450-650	0	0		24	0	0	2		28
650-850	0	0		0	0	0	0		0
850-1000	0	0		0	0	0	0		0
1000+	0	0		0	0	0	0		0
PHENOLS	0	0		0	0	0	0	35	38
MEA	0	0		3	0	0	0		0
UNCONVERTED COAL	0	0			0	0	0		0
TOTAL	68791	27768	14000	98748	3994	9418	42090	1866	281875
TEMPERATURE (F)	130	134	.	.	.	.	.	.	
PRESSURE (psig)	2970	2450	.	10	10	10	10		

PLANT OUTPUT

Stream No.	6.5+6.16	6.7 **	6.8	6.17	6.18	6.33 ***	6.30	TOTAL
COMPONENTS	NH3 H2O #/hr	H2 PROD TO #4,5 #/hr	TT H2 REC TO #2 #/hr	PSA COMP KO LIQ #/hr	PSA TAIL GAS to #3 #/hr	ACID GAS #/hr	TAIL GAS COMP KO LIQ #/hr	OUTPUT #/hr
N2		0	348		1279	0		1827
H2		9230	20429		2253	0		31912
H2O	34938	0	508	255	3037	1749		40487
H2S	1583	0	8		44	18812		20447
NH3	2879	0	0		0	0		2879
CO	0	0	210		757	0		987
CO2	73	0	0		0	1193		1286
C1		54	7505		32478	0	3	40038
C2		0	4308		28384	0	13	30704
C3		0	3338		31749	0	49	35138
C4		0	1453		29375	0	118	30947
C5-350		0	853	5	41098	3	2781	44740
350-450		0	7	4	104	0	345	480
450-650		0	0		28	0		28
650-850		0	0		0	0		0
850-1000		0	0		0	0		0
1000+		0	0		0	0		0
PHENOLS		0	0		0	0		0
MEA		0	3		35	0		38
UNCONVERTED COAL		0	0		0	0		0
ASH		0	0		0	0		0
TOTAL	39473	9284	38970	264	188617	21757	3308	281875
TEMPERATURE (F)	.	.	.	128	95	.	.	
PRESSURE (psig)	.	.	.	45	210	.	.	

* This stream represents a combination of input/output streams; a single temperature/pressure cannot be reported.

** 6.7 = 6.7A + 6.7B

*** 6.33 = 6.33A + 6.33B

Utility Summary

The utilities for this plant are summarized in Table 3.16.

Table 3.16
Utility Summary

	<u>Plant 6.1</u>	<u>Plant 6.2</u>
Steam (50 psig), lbs/hr	4042	55,431
Cooling Water, gpm	1400	5262
Water (Makeup), gpm	28	32
Electricity, KW	24,103	19,841

3.2.1.6 Critical Solvent Deashing Unit - ROSE-SR (Plant 8)

Design Basis, Criteria and Considerations

Feed Rate, BPSD 50,800

<u>Component</u>	<u>Composition, wt%</u>	
	<u>Feed</u> ⁽¹⁾	<u>Ash Concentrate</u> ⁽²⁾
Ash	17.60	40.50
Carbon	73.80	51.66
Hydrogen	6.21	3.54
Nitrogen	0.78	0.83
Sulfur	<u>1.61</u>	<u>3.47</u>
Total	100.00	100.00

(1) Contains unconverted coal 9.8 wt% and solvent 0.9 wt%

(2) Contains unconverted coal 24.2 wt% and solvent 3.1 wt%

Process Description and Process Flow Diagram

The simple operation of the ROSE-SR process is illustrated schematically on the Process Flow Sketch of Plant 8. The feedstock is charged through a mixer Y101, where it is contacted with light hydrocarbon solvent at elevated temperature and pressure. A portion of the solvent is mixed with the feed in Y101, and the remainder of the solvent enters through a separate solvent inlet that provides countercurrent solvent flow. The mixture passes to the asphaltene separator, C101, where the heavy asphaltene/solids fraction drops out of solution and is withdrawn as a liquid from the bottom of the separator. The asphaltene and residual solvent pass through heater F101 to flash tower C102, where the solvent is flashed and stripped from the product and the asphaltene product comes out as ash concentrate.

The solvent-deashed oil phase flows from the top of C101 through heat exchanger E101, where it is heated by the circulating solvent before entering heater F102. The temperature is elevated above the critical temperature of the solvent before the solvent-deashed oil mixture enters the deashed oil separator.

At this increased temperature, the deached oil (DAO) is virtually insoluble in the solvent. Therefore, a phase separation occurs in the DAO separator, C103. The DAO phase is withdrawn from the bottom of C103 and stripped of its solvent in

tower C104. The ROSE extract thus produced comes out of tower C104. The substantially DAO-free supercritical solvent provides a significant part of the enthalpy needed to increase the temperature of the overhead stream from C101 to the conditions in C103. This circulating solvent flows overhead from C103 through exchanger E101, giving up heat to the solvent-DAO solution from C101. The circulating solvent is further cooled in exchanger E102 before returning to C101 via the solvent circulation pump G101. In many applications, E102's process duty is negligible, though the exchangers are sized to handle operational upsets such as an increased charge temperature. E102 is oversized to enable the ROSE unit to handle upsets in charge temperature. The solvent circulation pump G101 develops only the differential pressure necessary to overcome the separator system pressure drop.

The small amount of solvent dissolved in the heavy phases from vessels C101 and C103 (between 7% and 15% of the total extraction solvent) is recovered by conventional stripping in C102 and C104. The recovered solvent is condensed in E103 and then collected in the solvent surge drum C105. This small flow of solvent is pumped by the recycle solvent pump G102 into the large flow of high-pressure circulating solvent upstream of the solvent circulation pump, G101.

PROCESS FLOW DIAGRAM

Figure 3.12

PLANT 8
ROSE PROCESS

Material Balance

The overall material balance for the Critical Solvent Deashing Unit is presented in Table 3.17.

Table 3.17

Material Balance

Stream No.	lbs/hr		
	8.1	8.2	8.3
	<u>Feed</u>	<u>Extract</u>	<u>Ash Concentrate</u>
H ₂ O	0	0	0
850°F-	380	380	0
850-1000°F	10,095	1,765	8,330
1000°F+	642,440	536,585	105,855
Unconverted Coal	90,965	----	90,965
Ash	<u>163,510</u>	<u>----</u>	<u>163,510</u>
Total	907,390	538,730	368,660
Tons/day	10,889	6,465	4,424

Utility Summary

The utility summary for this plant is shown in Table 3.18.

Table 3.18

<u>Utility</u>	<u>Units</u>	<u>Rate</u>
Steam Consumption - 150 psig	(lbs/hr)	25,419
Fuel Gas - Fired	(MMBtu/hr)	212
	(MMSCFD)	5.1
Electricity	(kW)	4,236

Note: Fuel gas rate in MMSCFD is based on a gross heating value of 1,000 Btu/SCF.

3.2.1.7 Hydrogen Production by Coal Gasification (Plant 9)

Design Basis, Criteria and Considerations

Plant 9 is designed to gasify 4,386 tons/day of Ash Concentrate from ROSE-SR Plant and 5,614 tons/day of coal. Most of the syngas from the gasifiers is used to produce 416 MMSCFD of 99.9 volume percent hydrogen product used for the coal liquefaction and hydrotreating plants. Syngas in excess of the above requirement is used for medium Btu fuel gas.

Feed Streams

- 4,386 TPD ash concentrate from Plant 8 (ROSE-SR)
- 5,614 TPD clean coal from Plant 1 (Coal Preparation)
- 8,250 TPD of 99.5 volume percent oxygen from Plant 10 (Air Separation)

Feed analysis and compositions are presented in Table 3.19.

Product Streams

- 416 MMSCFD of 99.9 volume percent hydrogen
- 69 MMSCFD of medium Btu fuel gas
- 28 MMSCFD of acid gas containing H_2S as feed to Sulfur Plant (Plant 11)
- 407 MMSCFD of stripped CO_2 waste gas for discharge to the atmosphere
- 2892 TPD (dry basis) of slag and soot to landfill disposal

Product compositions are presented in Table 3.20.

Gasifier Yields

- For ash concentrate, 33 SCF of $CO + H_2$ per pound of dry and ash-free feed
- For clean coal, 38.7 SCF of $CO + H_2$ per pound of dry and ash-free feed
- Average about 96% carbon conversion to syngas. Unconverted carbon is rejected with slag

TABLE 3.19
GASIFICATION FEED STREAMS

Illinois No.6 Coal

Ultimate Analysis, % (wt.), Dry Basis

Carbon	71.0
Hydrogen	4.8
Nitrogen	1.4
Sulfur	3.2
Oxygen	8.1
Ash	11.5
HHV, Btu/lb	10,951

Ash Mineral Analysis, % (wt.)

SiO ₂	49.8
Fe ₂ O ₃	17.6
Al ₂ O ₃	19.2
TiO ₂	1.0
CaO	6.3
MgO	1.0
SO ₃	2.9
K ₂ O	2.0
Na ₂ O	0.5
P ₂ O ₅	0.2
Undetermined	-0.5

Ash Concentrate

Composition, % (wt.)

850-1000°F	2.3
1000°F+	27.6
Unconverted Coal	25.8
Ash	44.3

HHV, Btu/lb 8,457

Ultimate Analysis, % (wt.), Dry Basis

Carbon	48.3
Hydrogen	2.9
Nitrogen	1.1
Sulfur	3.1
Oxygen	0.3
Ash	44.3

Table 3.20

Composition of Coal Gasification Products

	H ₂ Product <u>Mol %</u>	Medium Btu Gas <u>Mol%</u>	H ₂ S-Rich Off-Gas <u>Mol.%</u>	CO ₂ Off-Gas <u>Mol %</u>
H ₂ O	0.0	0.0	0.44	1.84
H ₂	99.90	74.15	2.71	0.43
CO	0.0	12.29	2.14	0.09
CO ₂	0.0	4.12	63.17	89.52
AR+N ₂	0.10	8.66	1.52	8.11
C ₁	0.0	0.78	0.0	0.01
H ₂ S	0.0	0.0	29.96	0.0
COS	<u>0.0</u>	<u>0.0</u>	<u>0.06</u>	<u>0.0</u>
Total				
#-Mol/hr	49,705	5,823	3,069	44,662
MMSCFD	453	53	28	407

Technology Selection

Two coal gasification technologies, the Texaco and Shell processes, have been evaluated for synthesis gas production in Plant 9. The block flow diagrams for these two processes are presented on Figure 3.13.

The major differences between these two processes are as follows:

	<u>Texaco</u>	<u>Shell</u>
1. Feed Type	Molten coal or coal slurry	Dried and pulverized coal to 70-90% through 200 mesh
2. Operating Conditions	High pressure process. Pressure up to 1100 psig	Low to medium pressure process. Pressure up to 400 psig
3. Gasifier Construction	Vertical cylindrical pressure vessel with refractory lining	Horizontal ellipsoidal vessel. Gasifier shell has a double-walled construction, the inner shell is refractory lined
4. Heat Removal Methods	Direct quench syngas with water in the gasifier and gas scrubber	Recover heat by generating steam in the waste heat boilers
5. Shift Conversion	Produce sufficient steam in the syngas for shift reaction	Steam injection is required for shift reaction to occur
6. Hydrogen Production	Produces higher H_2/CO ratio (0.75) syngas. Less shift conversion required.	Produces low H_2/CO ratio (0.43) syngas which requires more shift catalyst for shift conversion to reach the same H_2 production.

Texaco

Shell

7. Horsepower for Hydrogen Compression

Higher pressure process. Less horsepower required

Low pressure process requires more horsepower for hydrogen compression

8. Water Requirement

Relatively poor quality condensate from the gas cooling sections can be used for direct quenching of syngas

More boiler feed water of higher quality is required for steam generation in the gasifier and waste heat boiler

9. Ability to Handle ROSE bottoms

Its pilot plant had demonstrated that the ash-containing residues obtained from the H-Coal liquefaction plant were process efficiently

No pilot plant result has been reported for H-Coal liquefaction residues

10. Commercial Plant Experience

Several large size commercial plants have been operated successfully since 1980's

Only small demonstration plants have been built

For high pressure hydrogen production, Texaco's gasification process has lower capital and utility costs, and has showed it can process H-Coal liquefaction residues successfully. Therefore, the Texaco technology is recommended for this project as the gasification process for Plant 9.

FIGURE 3.13

Block Flow Diagram – Hydrogen Production by Coal Gasification

Scheme 1 – Texaco Gasification

Scheme 2 – Shell Gasification

Design Considerations

The limiting size for the gasifier reactors was taken as 2,000 TPD of coal or ash concentrate. This is larger than any reactors which have been designed and built to date; however, Texaco has stated that designing this size of gasifier is achievable.

The shift reaction was designed to maximize hydrogen production. The shift reactor vessels were limited in size to 16 feet outside diameter for shop fabrication and transportation considerations.

The RECTISOL process was chosen because it has been commercially proven in this service. The process can separate carbon dioxide from hydrogen sulfide as a relatively pure stream for venting to the atmosphere. The hydrogen sulfide is sent to the Sulfur Plant. PSA is required after RECTISOL to achieve the required hydrogen purity.

Process Description and Process Flow Diagram

Plant 9 consists of seven trains (5 operating and 2 spare) of gasification, five trains of shift conversion and gas cooling, five trains of gas purification, and six trains of hydrogen compression. Process flow diagrams are presented on Flowsheets shown in Figures 3.14 through 3.16 as follows.

<u>Fig. No.</u>	<u>Plant Section No.</u>	<u>Plant Name</u>
3.14	Slurry Preparation and Gasification	9.1
3.15	Shift Reactor and Gas Cooling	9.2
3.16	Hydrogen Purification and Compression	9.3/9.4/9.5

Slurry Preparation and Gasification

Ash concentrate from Plant 8 (ROSE-SR) and coal from Plant 1 (Coal Cleaning and Handling) are fed with water and a special additive to a grinding mill. The slurry from the grinding mill discharges to a slurry run tank.

The slurry feed from slurry feed pumps and oxygen feed from the Plant 10 (Air Separation Plant) combine at the gasifier burner and enter the gasification chamber. This chamber operates at about 950 psig and 2500°F. About 92-95% of the carbon in the coal is converted to gaseous products, and the ash in the coal is slagged.

The gas with the molten slag is quenched in water at the bottom of the chamber. The slag is collected in a slag lock hopper connected to the base of the gasifier. Slag accumulations in the lock hopper are dumped into a sump. Slag dumped into the pit settles to the bottom. From the sump, the partly clarified soot slurry is pumped to a flash system to removed H_2S and other odorous material. The settled slag is dragged over the incline of the drag conveyor.

Synthesis gas leaving the gasifier is further cleaned in a water scrubber to remove the residual slag particles.

Water and condensate collected in the gas cooling system and in the soot water system are recycled to the scrubber.

The size of the gasifier is limited by economic considerations and experience factors. Seven gasifiers of the largest design are included in the base-line design, including two spares to ensure continuous operation at the design capacity.

Figure 3.14

PLANT 9.1 SLURRY PREPARATION & GASIFICATION

Figure 3.15

START UP HEATER

**PLANT 9.2
SHIFT REACTOR &
GAS COOLING**

NH3 WASH COLUMN

CONTACTOR

STRIPPER

REBOILER STRIPPER

METHANOL-H2O SEPARATOR

METHANOL WASH COLUMN

9.13 ACID GAS
9.14 TAIL GAS

Figure 3.16

PLANT 9.3/9.4/9.5
HYDROGEN PURIFICATION &
COMPRESSION

H2 COMPRESSOR

PSA

TREATED GAS

Shift Reactor and Gas Cooling

The clean syngas from the gas scrubber goes to the shift converter where about 97-98% of the carbon monoxide is converted to hydrogen. The shift reaction is highly exothermic. A high temperature favors fast reaction rates but results in unfavorable equilibrium conditions. Initial stages will be designed to achieve high reaction rates at the highest allowable outlet temperature. The maximum allowable outlet temperature must be below the catalyst sintering point and within the limits for practical vessel design. The last reactor temperatures are kept low to obtain the low CO level in the product gas. The inlet temperature to each reactor stage must be kept above the water dew point to avoid catalyst being deactivated in the presence of liquid water.

A system with a multiple reactor design has been developed with the number of stages and trains, and operating conditions being optimized for minimum cost. To accommodate the required capacity, five trains each with three reaction stages were needed as limited by maximum reactor vessel diameter.

The catalyst chosen is either BASF's K8-11 or Haldor Topsoe's type SSK. Both catalysts operate in the sulfide form, thereby permitting handling of sulfur-bearing gas.

The heat of reaction is removed by a steam generator producing 600 psig steam from the first stage, a steam generator producing 150 psig steam from the second stage, and steam generators producing 150 psig and 50 psig steam from the third stage.

The shifted gas is further cooled against boiler feedwater, air, and cooling water and flows to the Hydrogen Purification section for acid gas removal. Process condensate is separated in the hot and warm receivers and pumped to the gas scrubbing and quench sections of the plant.

Hydrogen Purification and Compression

The Rectisol process removes H_2S and CO_2 by physical absorption of acid gas in methanol at relatively low temperature.

The feed gas is first prewashed by water in a water wash tower to remove NH_3 in the gas stream. The feed gas then enters at the bottom of a two-stage contactor where it is contacted with the methanol solution. In the first stage some of the CO_2 and practically all of the H_2S and COS are removed. In the second stage, which is above the first stage, the bulk of the CO_2 is removed.

The rich solvent which contains acid gas is regenerated by pressure reduction in the flash drums. The rich solvent is withdrawn from the flash drums and enter a stripper where the bulk of the CO_2 is stripped from the rich solvent by using nitrogen as the stripping gas.

The methanol leaving the stripper is completely regenerated in a reboiler regeneration column. The lean methanol withdrawn from the bottom of this column is fed to the top of the two-stage contactor. The acid gas, which contains all of the H_2S in the feed gas and some CO_2 , is stripped from this column and sent to sulfur plant.

The fully regenerated methanol from the bottom of the reboiler regeneration column contains all the water in the feed gas. To purge this water, a slip stream is charged to the methanol-water separator column where dry methanol is driven overhead. The overhead vapor is fed to the H_2S stripper. The bottoms from the methanol-water separator is water. A part of this stream is cooled and used for washing traces of methanol vapor from the tail gas (CO_2) stream. The balance is waste water.

The treated gas from the two-stage contactor flows to a pressure swing adsorption unit where the hydrogen is upgraded to a purity of 99.9%. The hydrogen is then compressed and delivered to the coal liquefaction and hydrotreating plants.

Material Balance

The detailed material balance for the plant is shown in Table 3.21 where as the overall material balance is shown in Figure 3.17.

Table 3.21
PLANT 9
MATERIAL BALANCE

Stream Description	Input Streams							
	Ash Conc	Coal	Oxygen	Water fr Pit 38	Makeup Water	Strip Gas	Fresh Water	Wash Water
Stream No Component	9.1 lbs/hr	9.2 lbs/hr	9.3 lbs/hr	9.4 lbs/hr	9.9 lbs/hr	9.12 lbs/hr	9.15 lbs/hr	9.10 lbs/hr
H2O			0	537,600	605,966	0	13,895	25,021
CO2			0	0	0	0	0	0
CO			0	0	0	0	0	0
H2			0	0	0	0	0	0
CH4			0	0	0	0	0	0
H2S			0	0	0	0	0	0
COS			0	0	0	0	0	0
N2+AR			3,440	0	0	102,239	0	0
O2			684,060	0	0	0	0	0
NH3			0	0	0	0	0	0
ASH CONC	368,667							
COAL		464,667						
SLAG								
Total	368,667	464,667	687,500	537,600	605,966	102,239	13,895	25,021
MW			32.0			28.0		
Density, lb/cf				62.2	62.2		62.2	62.2
MMSCFD			196			33		
GPM				1,075	1,212		28	50

Table 3.21 - continued

Stream Description	Output Streams										
	Sour Water	Sour Water	Acid Gas	Tail Gas	Acid Gas	Waste Water	NH3 Water	H2 Prod	Medium TU Ga	Slag	
Stream No Component	9.8 lbs/hr	9.6 lbs/hr	9.7 lbs/hr	9.14 lbs/hr	9.13 lbs/hr	9.16 lbs/hr	9.11 lbs/hr	9.18 lbs/hr	9.17 lbs/hr	9.5 lbs/hr	
H2O	252,614	123,880	244	14,790	0	1,704	25,021	0	0	0	
CO2	5,416	38	6,183	1,759,520	79,146	0	383	0	10,554	0	
CO	0	0	1,844	1,120	1	0	0	0	20,046	0	
H2	5	0	168	390	0	0	0	91,260	17,551	0	
CH4	0	0	1	66	0	0	0	0	733	0	
H2S	250	15	891	7	30,444	0	20	0	0	0	
COS	0	0	57	0	48	0	0	0	0	0	
N2+AR	0	0	18	101,186	1,268	0	0	532	12,595	0	
O2	0	0	13	427	0	0	0	747	2,660	0	
NH3	519	53	4	0	0	0	123	0	0	0	
ASH CONC											
COAL											
SLAG											241,000
Total	258,804	123,986	9,423	1,877,506	110,907	1,704	25,547	92,539	64,139	241,000	
MW			28.4	42.0	40.5			2.0	6.3		
Density, lb/cf	60.7	60.7				62.2	62.2				
MMSCFD			3	407	25			413	93		
GPM	531	255				3	51				

BASELINE

NOTES: Flow rate in lbs/hr

Schematic Representation of Plant 9 Material Balance

Figure 3.17

Utility Summary

Table 3.22 below presents a summary of the utilities required for Plant 9.

Table 3.22

Plant 9 Utility Summary

Utility	Gasification & Shift Conversion	Hydrogen Purification	Hydrogen Compression
Steam, lb/hr		0	0
600 psig	-291,800	50,000	0
150 psig	-812,900	113,000	0
50 psig	-894,300		
Boiler Feedwater, gpm	4,000	0	0
Cooling Water, gpm	33,900	10,500	8,200
Raw Water, gpm	800	78	0
Fuel Gas, MMSCFD	0.62	0	0
Electricity, Kw	14,660	5,900	42,650
Nitrogen, MMSCFD	0	34	0

Note: Negative values represent utility production.

3.2.1.8 Air Separation (Plant 10)

Design Basis Criteria and Considerations and Process Flow Diagram

This is a package plant, the process flow diagram of which is shown in Figure 3.18. The air separation package plants are cryogenic units producing oxygen at 99.5% (mol) purity and nitrogen at 99.9% (mol) purity. Oxygen will be delivered at the pressure required by the selected coal gasification process. Nitrogen will be used for purging, blanketing, and other utility purposes and will be delivered to the utility system at 150 psig. Liquid nitrogen will also be produced off the Air Separation Plant and stored for use during periods of high nitrogen demand.

Plant 10 consists of five parallel trains each sized for 45 MMSCFD of oxygen. Each train can operate independently and uses a low pressure cycle type process. The process features an air compressor to compress the inlet air, direct contact cooling to remove the heat of compression from the air, molecular sieve units to purify the air, fractionation columns to obtain the high purity gaseous oxygen, an expander compressor to provide the refrigeration needed for the process, and an oxygen compressor to pressurize the oxygen product for use in the Coal Gasification Plant.

Material Balance

The overall material balance for this plant is shown in Table 3.23. This balance is for five trains.

PROCESS FLOW DIAGRAM

Figure 3.18

PLANT 10
AIR SEPARATION

Table 3.23 Overall Material Balance

PLANT 10 (5 Trains)

Stream No.	PLANT INPUT			PLANT OUTPUT		
	10.1			10.2		
	Air			Oxygen		
Component	Mol/hr	Mol %		Mol/hr	Mol %	Mol/hr
Oxygen	21,358	20.90%		21,358	99.53%	0
Nitrogen	80,731	79.00%		4	0.02%	80,726
Argon	102	0.10%		97	0.45%	6
Total	102,191			21,459		80,732
Total, lb/hr	2,949,223			687,500		2,261,723
MW	28.86			32.04		28.02
MMSCFD	931			195		736

Utility Summary

The only utility consumed by the Air Separation Plant is electric power. A summary is shown below:

Electricity, Kw	Per train	29,458
	Total	147,290

3.2.1.9 Sulfur Plant (Plant 11)

Design Basis, Criteria and Considerations

Plant Capacity

Design capacity per train 180 LT/D

	<u>No. of Trains</u>	<u>Total Capacity (LT/D)</u>
• Operating	4	720
• Design	5	900

Feed Composition

<u>Stream Component</u>	<u>Acid Gas from Plant 6 mol/hr</u>	<u>Acid Gas from Plant 9.1 mol/hr</u>	<u>Acid Gas from Plant 9.3 mol/hr</u>	<u>Acid Gas from Plant 38 mol/hr</u>	<u>Total Feed mol/hr</u>
H ₂	97	14	0	288	399
H ₂ S	552	26	893	520	1991
CO ₂	27	141	1798	146	2112
N ₂	0	1	45	0	46
NH ₃	0	0	0	1	1
CH ₄	0	0	0	1	1
CO	0	66	0	0	66
H ₂	0	83	0	2	85
COS	0	1	1	0	2
Phenols	0	0	0	4	4
Other HCs	<u>0</u>	<u>0</u>	<u>0</u>	<u>135</u>	<u>135</u>
Total	676	332	2738	1095	4841

Product Compositions

<u>Stream Component</u>	<u>Vent Gas mol/hr</u>	<u>Liquid Sulfur mol/hr</u>
H ₂ O	65	0
H ₂ S	2	0
CO ₂	3074	0
N ₂	9183	0
H ₂	287	0
Liquid Sulfur	<u>0</u>	<u>1991</u>
Total	12720	1991
Total sulfur, LT/D	0.7	684

Yields

- Minimum sulfur recovery for Claus sulfur plant is 95%.
- Total sulfur recovery for Plant 11 is 99.9%.

Typical Sulfur Industry Specifications

● Sulfur	99.5%	minimum
● Carbon	0.2%	maximum
● Ash	50. ppm	maximum
● H ₂ S	50. ppm	maximum
● SO ₂	50. ppm	maximum
● Color	Bright yellow	
● Arsenic, Selenium, Tellurium	Commercially free	

Design Considerations

Three Claus trains were specified to be operational normally to achieve 100% on-line capacity in case one of the trains must be taken out of service on an emergency basis.

The SCOT process was selected for the tail gas treater for the Sulfur Plant because it is a proven process and is becoming an industry standard. It meets all present environmental regulations.

Process Description and Process Flow Diagram

The complete sulfur plant is comprised of three sections. These are, 1) Sulfur Plant, 2) SCOT Unit, and (3) Incinerator. The process description of each section is given below.

Sulfur Plant

The sulfur recovery plant, the description of which is shown in the Process Flow Diagram, Figure 3.19, has been designed in accordance with the principles of the classic "Claus" reaction. About one-third of the hydrogen sulfide (H₂S) in the feed is oxidized to form sulfur dioxide (SO₂) and water (H₂O). The sulfur dioxide then reacts with the remaining hydrogen sulfide to form elemental sulfur and water vapor. Ammonia (NH₃) is oxidized to nitrogen and water. In addition to the reactions noted above, a small part of the feed hydrogen sulfide dissociates to free hydrogen and elemental sulfur. Any hydrocarbons in the acid gas feed are oxidized in the thermal reactor to carbon monoxide (CO), carbon dioxide (CO₂) and water.

The acid gas and the SCOT recycle acid gas are combined and routed to the acid gas knock-out drum. The knock-out drum is designed to removed entrained sour water and condensed hydrocarbons from the acid gas streams.

PLANT 11.1
SULFUR PLANT

Figure 3.19 Process Flow Diagram

The vapor stream, from the acid gas knock-out drum, is fed to the acid gas preheater, where the stream is heated to about 450°F. The hot gas is then fed to the acid gas injector, located on the front chamber of the thermal reactor.

Combustion air is supplied by the air blower to the acid gas injector to oxidize some of the H_2S to SO_2 and H_2O . The quantity of air is controlled to achieve a ratio of H_2S to SO_2 of 2:1. During this reaction, the thermal reactor first and second chamber temperatures are about 2400°F and 2200°F, respectively. The combustion air is heated to about 450°F in the air preheater to help maintain the 2200°F overall thermal reactor temperature.

The hot combustion gas from the thermal reactor second chamber enters a two-pass waste heat boiler. The boiler is designed to cool the hot gas to about 600°F and to generate 150 psig steam. The cooled gas from the boiler enters the thermal sulfur condenser. Most of the sulfur produced in the thermal reactor is condensed as the gas is cooled in the thermal condenser. The thermal condenser is a steam generator and the heat removed from the hot gases generates 50 psig steam. Liquid sulfur is separated from the gas in a separation chamber at the outlet end of the condenser. The condensed sulfur drains to a sulfur seal pot in a sulfur day tank through a steam jacketed drain leg. The seal pot maintains a liquid sulfur seal to prevent the process gas from escaping through the sulfur drain legs.

The cooled gas from the thermal condenser flows to the first reheater. The gas is heated to about 450°F by 600 psig steam.

The hot gas from the first reheater flows downward through the first catalyst converter where the reaction of SO_2 with H_2S occurs over a fixed bed of alumina catalyst. Since the reaction is exothermic, the temperature will rise across the bed. The temperature rise will be the greatest in this reactor because of the higher concentration of reactants present.

The reactor product gas, containing newly formed elemental sulfur, leaves the reactor and enters the first sulfur condenser. The bulk of the sulfur formed in the first catalyst converter is condensed and is drained to the sulfur day tank through a steam jacketed drain leg. Steam at 50 psig is generated on the shell side of the condenser.

The cooled gas from the first condenser flows to the second reheater where it is heated to about 420°F by 600 psig steam. Since the concentration of the reactants are lower in the feed to the second catalyst converter than in the feed to the first, less reaction takes place and the temperature rise across the second converter is lower.

Hot effluent gas from the second converter bed enters the second sulfur condenser. The bulk of the sulfur formed in the second converter is condensed and drained to the sulfur day tank through the third steam jacketed drain leg. Steam at 50 psig is generated on the shell side of the condenser. The cooled gas from the second sulfur condenser flows to the third reheater. This reheater has the same function as the other reheaters, and uses 600 psig saturated steam as a heating medium to heat the third catalyst converter feed to about 400°F.

The third catalyst converter is similar to the first and second catalyst converters. Since the concentration of H_2S and SO_2 is very low in the feed to the third reactor bed, a relatively small amount of sulfur is formed in this stage. The reaction that takes place in this stage results in a very small temperature rise across the catalyst bed. The sulfur formed in the catalyst converter is condensed in the third sulfur condenser and is drained to the sulfur day tank through a steam-jacketed drain leg. The cooled gas (tail gas) from the third sulfur condenser flows to the SCOT tail gas treating unit.

SCOT Unit

The Process Flow Diagram for this section is shown in Figure 3.20. The fundamental reaction in the Hydrogenation Section of the SCOT Unit are hydrogenation of the SO_2 and elemental sulfur. Most of the COS and CS_2 present in the reactor are hydrolyzed by the water vapor in the tail gas.

The sulfur plant tail gas is heated to over 500°F in the SCOT feed heater. The temperature of this stream is controlled to the desired SCOT reactor inlet temperature by means of a temperature controller, which regulates the amount of natural gas or syngas that is fed to the SCOT burner as fuel.

Syngas is added to the feed heater outlet to provide the necessary hydrogen for the hydrogenation of the SO_2 and elemental sulfur to H_2S .

The heated gases then pass downward through the reactor catalyst bed where the SO_2 , elemental sulfur and other sulfur containing compounds (such as COS) are converted to H_2S , CO_2 , CH_4 , and water vapor. To assure the complete reduction of the sulfur compounds to H_2S , an excess above the stoichiometric requirement of hydrogen is fed to the reactor. The reactions are exothermic and cause a temperature rise across the reactor.

The hot gases leaving the SCOT reactor are cooled to about 320°F in the SCOT waste heat exchanger. The waste heat exchanger is a steam generator and the heat removed from the hot gases generates 50 psig steam.

The cooled gases leaving the waste heat exchanger are further cooled to about 100°F by contact with water in the quench tower. The gases enter the quench tower below the tower packing and flow upward, countercurrent to the cool quench water. The quench water is fed to the tower above the packing at a temperature of about 100°F . The temperature of the quench water is raised to about 150°F as it cools the gases in the column. The quench water from the bottom of the column is then pumped by the quench water pumps, through the quench water cooler, where it is cooled before being returned to the top of the tower. The quench water bleed stream is the excess water contained in the quench tower feed gas that is condensed in the quench tower.

The quench tower overhead gas stream enters the SCOT absorber below the bottom tray and flows upward through the absorber countercurrent to the MDEA solution flowing down through the absorber.

Lean MDEA solution at about 100°F is fed to the top of the absorber. The solvent flows downward through the absorber, contacting the gas stream flowing upward and absorbing nearly all of the H₂S and part of the CO₂ from the gas stream. The treated vent gas then leaves the top of the absorber at about 100°F and is directed to the incinerator.

A vent gas analyzer is provided to advise the operator of the SCOT Unit clean up efficiency, H₂S and CO₂, and the amount of excess hydrogen in the vent gas.

Rich solvent is withdrawn from the absorber bottom and is pumped to the SCOT stripper through the lean/rich exchanger. The rich solvent enters the column above tray 5 (from the top). The stripper is heated by a reboiler using 50 psig steam.

The stripper overhead vapor is cooled to about 120°F in the reflux condenser (an air cooler), and collected in the reflux drum. The gas from the top of the reflux drum contains H₂S, CO₂, and H₂O and is routed to the sulfur plant as acid gas feed.

The lean solvent leaves the stripper bottom and flows through the lean/rich exchanger. Lean solvent from the exchanger is pumped to the SCOT absorber by the lean solvent pumps. The lean solvent stream from the pump discharge is cooled to about 100°F in the lean solvent cooler and is fed to the top of the absorber.

Incinerator

The Process Flow Diagram for this section of the plant is shown in Figure 3.21. The incinerator uses a natural draft burner to provide the heat and air necessary for the combustion of the effluent gases. The design combustion temperature is maintained by burning natural gas or syngas as fuel. The SCOT vent gas is routed below the incinerator burner to achieve maximum turbulence and contact with the oxygen (air) at high temperature.

During normal operations, the sulfur plant tail gas flows to the SCOT unit and only the SCOT vent gas is combusted in the incinerator. The design conditions for proper combustion of the SCOT vent gas is 25% excess air at a temperature of about 1200°F. The combustion products are discharged to the atmosphere through a 280 foot stack. A stack gas analyzer is provided to monitor the SO₂ in the stack.

Incinerator

Natural Gas

Waste Gas from
SCOT Absorber

Figure 3.21 Process Flow Diagram
INCINERATOR
PLANT 11.3

Material Balance

Material balance for the complete plant is included in Table 3.24. The material balance for the Sulfur Plant and the SCOT Unit are shown in Tables 3.25 and 3.26, respectively.

Table 3.24

PLANT 11 - SULFUR PLANT

OVERALL MATERIAL BALANCE

Description	Inlet Streams					Outlet Streams						
	Acid Gas	Reducing Gas	Natural gas	Air	Air	S from Thermal Cond	S from 1st S Cond	S from 2nd S Cond	S from 3rd S Cond	Quench Water Bleed	OH Cond Water Bleed	Gas to Incin
Stream No.	11.1	11.13	11.14	11.4	11.15	11.6	11.8	11.10	11.12	11.16	11.17	11.18
Component	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr
H ₂ O	399	0	0	150	7					3137	400	65
CO ₂	2112	0	0	0	0					0	0	3074
CO	66	0	0	0	0					0	0	0
H ₂	85	187	0	0	0					0	0	287
CH ₄	1	0	55	0	0					0	0	0
H ₂ S	1991	0	0	0	0					0	0	2
COS	2	0	0	0	0					0	0	3
SO ₂	0	0	0	0	0					0	0	0
CS ₂	0	0	0	0	0					0	0	0
N ₂	46	0	0	8725	411					0	0	9183
O ₂	0	0	0	2340	109					0	0	0
AR	0	0	0	104	5					0	0	109
NH ₃	1	0	0	0	0					0	0	0
Phenols	4	0	0	0	0					0	0	0
Other HC's	135	0	0	0	0					0	0	0
S vapor as S1	0	0	0	0	0					0	0	0
S liquid as S1						828	906	220	38			
Total	4841	187	55	11319	532	828	906	220	38	3137	400	12720
Lb/hr, total	183563	377	882	325145	15305	26549	29037	7064	1202	56513	7213	398694
MW	37.92	2.02	16.04	28.81	28.81							31.34
Density, lb/cf3										61.39	61.73	116
MMSCFD	44	1.7	0.5	103	5							
GPM						284	311	76	13	115	15	
S Product, LTD												

Table 3.25

PLANT 11.1 - SULFUR PLANT

MATERIAL BALANCE

Description	Acid Gas	Recycle	Total	Air	Gas from	S from	Gas from	S from	Gas from	S from	Tall Gas	S from
Stream No.	11.1	11.2	11.3	11.4	Thermal	Thermal	1st S	1st S	2nd S	2nd S	to	3rd S
Component	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Cond	Cond	Cond	Cond	Cond	Cond	SCOT	Cond
					Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr	Mols/hr
H ₂ O	399	25	424	150	3211		3456		3580		3601	
CO ₂	2112	372	2484	0	3152		3312		3312		3312	
CO	66	0	66	0	42		42		42		42	
H ₂	85	0	85	0	113		113		113		113	
CH ₄	1	0	1	0	0		0		0		0	
H ₂ S	1991	120	2111	0	418		170		46		25	
COS	2	0	2	0	28		3		3		3	
SO ₂	0	0	0	0	355		85		23		12	
CS ₂	0	0	0	0	167		33		33		33	
N ₂	46	0	46	8725	8772		8772		8772		8772	
O ₂	0	0	0	0	0		0		0		0	
AR	0	0	0	104	104		104		104		104	
NH ₃	1	0	1	0	0		0		0		0	
Phenols	4	0	4	0	0		0		0		0	
Other HC's	135	0	135	0	0		0		0		0	
S vapor as S1	0	0	0	0	149		55		21		15	
S liquid as S1												
					828				906		220	38
Total	4841	517	5358	11319	16512	828	16145	906	16049	220	16033	38
Lb/hr, total	183563	20911	204474	326145	504070	26549	475033	29037	467969	7064	466767	1202
MW	37.92	40.45	38.16	28.81	30.53		29.42		29.16		29.11	
Density, lb/cf3												
MMSCFD	44	5	49	103	150		147		146		146	
GPM												
S Product, LTD						284		311		76		13

Table 3.26
PLANT 11.2 - SCOT TAIL GAS TREATING

MATERIAL BALANCE

Description	Tail Gas to SCOT	Reducing Gas	Natural Gas	Air	Quench		OH Cond		Gas to Incin		Recycle	
					Water Bleed	Mols/hr	Water Bleed	Mols/hr	Incinerator	Mols/hr	Acid Gas	Mols/hr
Stream No. Component	11.11	11.13	11.14	11.15	11.16	<u>Mols/hr</u>	11.17	<u>Mols/hr</u>	11.18	<u>Mols/hr</u>	11.2	<u>Mols/hr</u>
H2O	3601	0	0	7	3137	400			65	25		
CO2	3312	0	0	0	0	0			3074	372		
CO	42	0	0	0	0	0			0	0		
H2	113	187	0	0	0	0			287	0		
CH4	0	0	55	0	0	0			0	0		
H2S	25	0	0	0	0	0			2	120		
COS	3	0	0	0	0	0			0	0		
SO2	12	0	0	0	0	0			0	0		
CS2	33	0	0	0	0	0			0	0		
N2	8772	0	0	411	0	0			9183	0		
O2	0	0	0	109	0	0			0	0		
AR	104	0	0	5	0	0			109	0		
NH3	0	0	0	0	0	0			0	0		
Phenols	0	0	0	0	0	0			0	0		
Other HC's	0	0	0	0	0	0			0	0		
S vapor as S1	0	0	0	0	0	0			0	0		
S liquid as S1	15	0	0	0	0	0			0	0		
Total	16033	187	55	531	3137	400			12720	517		
Lb/hr, total	466767	377	882	15305	56513	7213			398694	20911		
MW	29.11	2.02	16.04	28.81	61.39	61.73			31.34	40.45		
Density, lb/cf3												
MMSCFD	146	1.7	0.5	5	115	15			116			
GPM												

Utility Summary

The individual plant utility summaries for the Sulfur Plant and SCOT unit are tabulated below in Table 3.27.

Table 3.27 Utility Summary

Units	CW	Steam Rate, lbs/hr				Fuel Gas	Electr	H2
	gpm	50#	150#	600#	900#	MMSCFD	Kw	MMSCFD
Sulfur	0	-67096	-192975	62024	0	0	2060	1.7
SCOT	8406	123443	0	0	0	1.9	1108	0
Total	8406	56347	-192975	62024	0	1.9	3168	1.7

Note: Negative values represent utility production

3.2.2 Status Update on Support Facilities

During this reporting period several support facilities plants were updated. The status of these updates are discussed below.

3.2.2.1 Coal Cleaning and Handling Plant (Plant 1)

Design Basis, Criteria and Considerations

ROM coal enters the fence line of the complex. The analysis of ROM coal is shown in Table 3.28. ROM coal is cleaned by Jig Cleaning operation.

Storage capacities for ROM Coal and clean coal are as follows:

For ROM coal, "Active Storage" Pile is of 4 days capacity and remaining 24 days of "Inactive Storage".

For clean coal, storage is for 2 days of "Active Storage" pile.

Operation Basis for the base case cleaning plant (Jig) is:

2 shifts a day 5 days a week and 50 weeks per year

Third shift for maintenance

14.5 hrs of operation with 1.5 hrs for start-up, planned and unplanned outages.

Ash content of base case clean coal are as shown below:

Base case, Jig Cleaning	11.47%
Alternate 1, Heavy Medium	8.6%
Alternate 2, Spherical Agglomeration	< 4%

Size analysis for ROM Coal is shown in Table 3.29.

The basis for analysis of clean coal is shown in Table 3.30.

The production rate of this plant is based on the requirement of coal liquefaction plant (Plant 2) and coal gasification plant (Plant 9, the source for hydrogen supply)..

Coal from this coal cleaning and handling plant (Plant 1) is further processed through coal grinding and drying plant (Plant 1.4) where the coal moisture is reduced to 2 wt% and the particle size is reduced to 50% through 200 mesh screen.

Plant 1 design is on the basis of six train each train processing nominal 5000 TPSD. The product size, ash and moisture content of clean coal from Plant 1 is shown in Table 3.31.

Production of Middlings

The possibility of utilizing a potential middlings product with an ash content of around 20 percent for boilers or coal gasification was examined. The recovery of a middlings product is justified when the process sink material (refuse) contains a significant amount of material of economically usable quality. A review of the float/sink data for the design coal revealed that only a clean coal with 11.47 percent ash (Base Case) will be produced from the ROM coal, the refuse will contain no coal of the required middlings quality. The refuse will be exclusively material with an ash content above 68 percent.

Under these circumstances, additional cleaning, dewatering, handling and storage circuits will not be justified to produce a middlings product. Since the boilers or gasifier can use a fuel of 20 percent ash this requirement can be more economically met by ROM Coal.

Table 3.28

**Illinois No. 6 Coal Burning Star Mine
ROM Coal Analysis ⁽¹⁾**

<u>Proximate Analysis</u>	<u>Wt. %</u>
Volatile Matter	33.0
Fixed Carbon	38.3
Ash	20.0
Moisture	8.7
<u>Ultimate Analysis</u>	
Carbon	61.5
Hydrogen	4.2
Nitrogen	1.2
Sulfur	5.1
Chlorine	0.1
Ash	21.9
Oxygen (by difference)	6.0
<u>Sulfur Forms</u>	
Pyrite	3.0
Sulfitic	0.3
Organic	1.8
<u>Ash Composition</u>	
Phosphorus pentoxide, P_2O_5	0.1
Silica, SiO_2	43.8
Ferric Oxide, Fe_2O_3	24.1
Alumina, Al_2O_3	17.1
Titania, TiO_2	0.8
Lime, CaO	5.6
Magnesia, MgO	1.0
Sulfur Trioxide, SO_3	4.1
Potassium Oxide, K_2O	2.1
Sodium Oxide, Na_2O	0.6
Undetermined	0.7

(1) DOE's RFP on Direct Coal Liquefaction Project

Table 3.29
Size Analysis for ROM Coal

<u>Size (inch or mesh)</u>	<u>Percent</u>
3 x 3/8	51
3/8 x 28M	37
28M x 0	12
	<hr/>
Total	100

Table 3.30

**Analysis of Feed Coal to Liquefaction
Illinois No. 6 (Burning Star Mine)**

Proximate Analysis (wt. %, Dry Basis)

Volatile Matter	42.2
Fixed Carbon	46.3
Ash	11.5
Total	100.0

Ultimate Analysis (wt. %, Dry Basis)

Carbon	71.0
Hydrogen	4.8
Nitrogen	1.4
Sulfur	3.2
Chlorine	0.1
Ash	11.5
Oxygen (by difference)	8.0
Total	100.0

Moisture %	8.6
------------	-----

Table 3.31

Product Size from Coal Cleaning Plant

<u>Base Case</u>	<u>Wt %</u>
Particle Size	
3 x 1-1/2	9.4
1-1/2 x 100M	90.6
- Moisture	8.6
Ash	11.47

Process Description, Block Flow Diagram and Process Flow Diagram

Jigs effectively remove mine dilutions and other high ash components from ROM coal. They are extensively used by the coal industry for the preparation of power plant fuel. Depending upon the characteristics of the Rom coal, Jigs can dramatically improve its quality at a very nominal cost.

Jigs are operated at a relatively high specific gravity of separation of 1.8. The washability characteristics of the raw coal and the desired ash/sulfur contents in the clean coal generally determine the specific gravity of separation. A lower ash content in the clean coal usually requires a lower separation gravity. The separation efficiency of Jigs is low below the specific of separation 1.6. This reduced efficiency is reflected in lower than theoretically possible yield of clean coal and/or increased clean coal ash content.

Figure 3.22 presents a Simplified Block Flow Diagram for the Base Case. ROM coal (3 inch x 0) from the storage pile is cleaned in a Baum Jig at a separation gravity of 1.8 providing a float (clean coal) and a coarse refuse. A clean coal screen classifies the coal into three size fractions. The coarse size fraction (3 inch x 1-1/2 inch x 1/8 inch) is dewatered using a centrifuge. The fine clean coal slurry (1/8 inch x 0) is classified at 100 mesh using classifying cyclones. The cyclone underflow joins the 1-1/2 inch x 1/8 inch coal ahead of the centrifuge. The cyclone underflow slurry containing high ash clay solids is diverted to a static thickener where it is thickened to a consistency of approximately 25 percent (solids by weight). The thickened fine refuse is pumped to a settling pond. Clarified water from the thickener overflow is reused in the plant. The crushed and dewatered clean coal is sent to the clean coal storage facility. The dewatered coarse refuse from the Jig is transported to the Refuse Handling Section.

The more detailed description of the plant is shown in Figure 3.23 (process flow diagram for Jig cleaning) which also includes product crushing, dewatering and water recovery.

FIGURE 3.22
JIG CLEANING - BASE CASE
SIMPLIFIED BLOCK FLOW DIAGRAM

The overall material balance for Plant I is shown in Table 3.33. This material balance is per train.

Table 3.33

COAL CLEANING: BASE CASE (JIG)										
OVERALL MATERIAL BALANCE PER TRAIN FOR PLANT I										
		Material In			Material Out					
		Raw Coal	Make-up Water	Total In	Clean Coal	Clean Coal	Total Clean Coal	Refuse	Refuse	Total Refuse
STREAM #		1	18		6	11	19	14	16	18
Coal	TPH	627.6	0.0	627.6	47.1	455.0	502.1	90.8	34.7	125.5
Water	TPH	59.9	101.7	161.5	2.1	45.0	47.1	9.9	104.6	114.5
	GPM	239.6	406.9	646.5	8.4	180.0	188.4	39.8	418.5	458.2
Total										
Stream	TPH	687.5	101.7	789.1	49.2	500.0	549.2	100.7	139.3	240.0
Ash	TPH	137.5	0.0	137.5	5.4	52.2	57.6	59.9	20.0	79.9

- NOTE: (1) Stream #1 Is Raw (MF) Coal Entering The Coal Cleaning Plant
 (2) Stream #19 Is Clean Coal (MF) Leaving The Coal Cleaning Plant
 (3) This Plant Operates Two Shifts A Day With 14.5 Hours On Stream
 Per Day, 5 Days A Week And 50 Weeks A Year
 (4) Each Train Will Deliver Approximately 1.82 MM TYPY Of Clean Coal (MF) To Storage

3.2.2.2 Coal Grinding and Drying (Plant 1.4)

Design Basis Criteria and Considerations and Block Flow Diagram

This plant crushes and dries the coal from the coal cleaning and handling (Plant 1) before it enters the coal liquefaction plant (Plant 2).

Clean coal enters the plant sized at 1-1/2'x0 with up to 15% moisture content and exits (with 50% of the coal minus 200 mesh) and with 2% moisture content. The block flow diagram, Figure 3.26, illustrates the coal grinding and drying process. Moist clean coal from a feeder bin enters the coal mill where it is ground. Dry, heated nitrogen blown into the mill dries and carries the fine coal dust out of the mill to a dust collector unit. The dust collector separates the coal dust from the nitrogen and directs the coal to a crushed coal bin. The nitrogen is recirculated through a heater back into the mill except for a small amount which is purged. The crushed coal product is delivered to Plant 2 via a pneumatic type pump.

This plant is designed to grind and dry 17,102 TPD (dry) of 1-1/2" and less, 55 Hardgrove coal with 15% maximum feed moisture content. The final product has a size of 50% of the coal less than 200 mesh and a 2% moisture content.

The plant is intended to be operated 24 hours per day.

Inert nitrogen gas is utilized for drying and transferring the coal dust to minimize auto-ignition and explosive hazards.

The coal feed and crushed coal product bins must each provide 8 hrs of storage capacity (600 tons at 75 TPH).

Plant Description

The design for this plant is based on coal roller-mills. Twelve identical grinding circuits or trains are required, 2 trains for each Coal Liquefaction (Plant 2) train. The trains are rated at 75 TPH each. Ten trains are normally operating with two spares corresponding to the spare Plant 2 train. The following paragraphs describe one of the trains (see Figure 3.26).

A weigh belt feeder (1.4-T101A-L), located below the 600 ton coal feed bin (1.4-D101A-L), delivers clean coal to the mill (1.4-Y101A-L). The coal is fed to the center of the mill's grinding table where it is ground between the rotating table and three large cylindrical rollers. The ground coal spills over the table's edge and is lifted by a stream of rising hot (660 °F) nitrogen gases to the top of the mill. The hot gases cause an immediate evaporation of the moisture in the coal. A separator at the top of the mill allows the finished coal dust to exit the mill while the coarse fraction falls back to the center of the grinding table for further crushing.

The coal dust leaving the mill dust enters the dust collector baghouse (1.4-Y102A-L). The baghouse directs the stream up through fabric bag filters which separate the coal particles from the nitrogen gas. Particles collect on the outside of the bags and are removed periodically with short bursts of pressurized plant air. The recovered particles are transferred by screw conveyor (1.4-T102A-L) to the 600 ton crushed coal product bin (1.4-D102A-L). The crushed coal is conveyed to Coal Liquefaction (Plant 2) via a pneumatic type feed pump (1.4-G101A-L).

The nitrogen gas enters the nitrogen recycle fan (1.4-K101A-L) where about 90% of the gas is recycled to the mill through a fuel gas fired heater (1.4-F101A-L). The hot nitrogen gas is tempered with make-up nitrogen from the nitrogen bleed damper (1.4-L101A-L) to about 660 °F before entering the mill. The nitrogen gas is not recycled is vented to the atmosphere through a final bag filter.

A feeder hoist (1.4-T103A-L) and overhead travelling crane (1.4-T104A-L) are included with each train for maintenance purposes.

Utility Summary

The utility summary for this Plant is included in Table 3.34.

Table 3.34

Utility Summary

Electricity, KW	12114
Water Circulation, gpm	240
Fired Duty, MM Btu/hr	486
Nitrogen Consumed, MM SCFD	108
Air Consumed, MM SCFD	8.6

3.2.2.3. Sewage and Effluent Water Treatment - (Plant 34)

Design Basis, Criteria and Considerations

Wastewater Treatment (Plant 34) and Water Systems (Plant 32) are closely related and together constitute the Project Water Management System, with the purpose of minimizing both raw water consumption and effluent discharge to public waters during normal plant operation. Waste water streams are segregated on the basis of their compatibility and treated as necessary to make them suitable for reuse, if practical, in lieu of fresh water.

The majority of the water used in the project eventually goes to the atmosphere as water vapor. Some water is disposed of as moisture associated with the solid wastes going to the land fills.

Individual systems described in this section include:

- Coal Storage Pile Runoff Treatment
- Oily Wastewater Treatment
- Deoiled Wastewater Treatment
- Stripped/Dephenoled Wastewater Treatment
- Solids Dewatering
- Sanitary Sewage Treatment

The design basis, process description and block flow diagrams for each of the above treatment systems are given under each treatment system described herein.

Coal Storage Pile Runoff Treatment

The water management policy is: all rain runoff from developed areas is utilized within the complex. Runoff from uncontaminated areas such as building roofs, is routed without treatment to the utility/firewater storage pond. Runoff from potentially contaminated areas, including the coal storage areas, is treated before being sent to the utility/firewater storage pond.

Design Basis. The design of the Coal Storage Pile Runoff Treatment System is based on Bechtel Environmental's in-house data which approximates the runoff of Illinois coals. The design characteristics of the runoff are summarized in Table 3.35.

Table 3.35**Design Characteristics of Runoff - Plant 34**

<u>Parameter</u>	<u>Design</u>
pH	6.0
Total Suspended Solids	1,800
Total Dissolved Solids	800
Sulfate	320
Iron	15
Total Organic Carbon	500
Biochemical Oxygen Demand	5
Chemical Oxygen Demand	2,000

The design is based on the premise that the water will be acidic and therefore bicarbonate alkalinity is insignificant and hardness is entirely noncarbonate. Thus only soda ash is specified to raise the pH and precipitate the calcium and magnesium as carbonates.

Design basis for clarifier:

• Water flow, gpm	600
• Surface flooding, gpd/ft ²	700
• Underflow solids concentration, %wt	2

Design basis for filters:

• Water flow, gpm	600
• Filtration flux, rate, gpm/ft ²	10
• Backwash flux rate, gpm/ft ²	15

The Coal Storage Pile (CSP) Runoff Treatment System is shown in Figure 3.27 and consists of clarification, neutralization and filtration.

The runoff from the "live" and "dead" coal storage piles is routed to a storm surge pond which acts as a flow and composition equalizer and a feed "tank" for the CSP runoff treatment equipment. Additionally, some of the heavier suspended solids are expected to settle out at this point. From the surge pond, the runoff is pumped at a constant 600 gpm rate to the Reactor/Clarifier where it is neutralized with soda ash and clarified with the aid of a polyelectrolyte. Settled solids are withdrawn and pumped to the sludge dewatering facilities at the treatment plant. Reactor/Clarifier effluent is pumped through two down-flow, pressure-type, dual media filters for residual suspended solids removal. A controlled portion of the filtered water is stored in the Filter Backwash Makeup Tank. Periodically the filters are backwashed using filtered water aided by compressed air for scouring the media. Filter backwash water, laden with suspended solids, is returned for reuse.

Oily Wastewater Treatment

The Oily Wastewater Treatment System consists of API gravity separation followed by dissolved air flotation (DAF). Sludges generated by the API separator and DAF units are disposed of by routing to the gassifiers in Plant 9 for incineration.

Oil-contaminated waste-waters from throughout the plant, including contaminated surface runoff, are collected by an underground sewer system and routed to the wastewater treatment area. Major sources of this wastewater are:

- Contaminated process area runoff
- Runoff from the tank farm area
- Runoff from truck and railroad loading and unloading areas
- Water draws from oil storage tanks
- Vessel and pump drains
- Pump cooling water
- Laboratory sink drains
- Condensate collected in process drains

Figure 3.27 Block Flow Diagram

CSP RUNOFF TREATMENT

The design of the oily water treatment system is based on the following estimated wastewater characteristics and flow:

Influent Characteristics

Flow (maximum)	2,650 gpm
PH	6-8
Oils (average)	350 mg/l
TSS	150 mg/l
COD	1,200 mg/l
BOD	500 mg/l

The performance requirements for the process units are as follows:

<u>Unit</u>	<u>Percent Removal Requirements</u>			
	<u>Oils</u>	<u>TSS</u>	<u>COD</u>	<u>BOD</u>
API Separator	50	50	33	30
DAF Units	85	50	40	40

The process is shown in Figure 3.28.

The oily wastewater, on its way to the API Separator flows through a specially designed concrete Static Flow Splitter Box utilizing a combination of weirs and pumps to permit excess flows to be diverted to the oily storm surge tank with a minimum of oil carry-over.

Upon entering the covered and vented API separator forebay, some of the lighter oils float to the surface and the heavier solids settle out. The water then flows on through the two 5 x 11 x 120-foot channels where the oil droplets float the solids (sludge) settles out. The floated oil and settled sludge are moved across the length of the channels in opposite directions, by means of motor-operated endless chains with flights, and are concentrated at opposite ends. Oil is skimmed off to a sump and pumped by the Skimmed Oil Pump to a small heated tank nearby for settling and rough phase separation. Water is drained back to the separator, and oil is withdrawn through a floating skimmer and pumped by the Oil Transfer Pump to Plant 2's distillation feed flash tank. Bottom sludge is pumped by the API Separator Sludge Pump to a sump where float and bottom sludges from the DAF units are also collected and pumped by the Oily Sludge Sump Pump to mix with the Rose bottoms (Plant 8.1) before going to the Coal Gasifiers (Plant 9).

Figure 3.28 Block Flow Diagram

The API separator effluent is pumped by the API Separator Effluent Pump through the Flash Mix Tank and Flocculation Tank to the DAF units. Acid or caustic soda is metered to the flash mix tank to automatically adjust the pH. Polymer is also metered to the flash mix tank at a rate commensurate with the wastewater rate. These chemicals form a dense floc into which some of the small, dispersed oil droplets and suspended solid particles (found in the feed to the DAF units) are trapped. This floc is built up in the flocculation tank by means of a slow-speed mixer-agitator.

The floc containing oily water now enters the twin DAF units, where the oily floc is removed with the aid of small air bubbles. The feed is equally split and fed to the central portion of the circular DAF Flotators. A portion (50%) of the clarified effluent from each flotator and compressed air are held for about 30 seconds in the air saturation tank to dissolve the air in the water. The air-saturated water is depressurized and immediately blended with raw feed to the flotators. There is an independent air saturator for each flotator. The microscopic air bubbles that are thereby formed attach themselves or are trapped in the oil coated floc and rapidly buoy it to the surface of the flotators. The resulting material, known as "float," is skimmed off with slowly revolving scrapers into a hopper from which the float flows by gravity to a sludge collection sump. Some solids settle to the bottom of the flotators. These are removed periodically by bottom sludge pumps and added to the oily sludge sump along with other sludges.

Deoiled Wastewater Treatment

Effluent from the Oily Water Treatment System (API separator followed by dissolved air flotation) is sent to the next stage of wastewater treatment. This treatment stage, Deoiled Wastewater Treatment, consists of a pure oxygen-activated sludge treatment to remove biodegradable organics, followed by dual media filtration to remove suspended solids.

The Oxygen Activated Sludge System employs Marox rotating diffusers to diffuse pure oxygen into wastewater in covered aeration basins. The equipment for the required wastewater capacity consists of three Aeration Basins, six Marox aerators, three Clarifiers, and one Sludge Thickener.

- Aeration basins and aerators

Wastewater flow, gpm	2,650
Food to microorganism ratio (F/M), lb BOD/MLSS-day	0.2
MLSS, mg/l	3000
Detention time, hrs	8.4
BOD reduction, %	90
COD reduction, %	85
Oxygen requirement, lb/lb BOD reduction	1.2

Note:

MLSS - Mixed liquor suspended solids are total solids in aeration basins and includes microorganisms plus other suspended solids.

Mixed liquor volatile suspended solids are that fraction of MLSS which volatilizes upon burning and represents a measure of the microorganism content of the MLSS.

- Activated carbon VOC removal system

- Clarifier

Water flow, gpm	5,400 (including sludge recycle)
MLSS in underflow,	1
Surface loading, gpd/ft ²	700
Sludge recycle, % of incoming flow	50

- Sludge Thickener

Waste sludge flow, gpm	12
Surface loading, gpd/ft	20
Percent MLSS in underflow, %	3

Suspended Solids Removal System (Dual Media Filter System). A dual media filtration system is used to remove suspended solids from the clarified water. The system consists of a Filter Feed Tank, four anthracite/garnet, dual media, pressure type filters, a polymer feed system, and a chlorine feeder.

- Filter Feed Tank - Wastewater flow of 2,650 GPM, four hours holding capacity.
- Chlorine Feeder

Wastewater flow, gpm	2,650
Chlorine dosage, mg/l	10
- Polymer Feed System

Wastewater flow, gpm	2,650
Polymer dosage, mg/l	2
Raw polymer storage capacity, weeks	2
Stock solution storage capacity, hours	8
Stock solution concentration, %	1
- Dual Media Filter System

Wastewater flow, gpm	2,650
Filtration Flux, gpm/ft ²	12
Backwash flux, gpm/ft ²	15

The key design characteristics of the incoming feed and of the filtered effluent are as follows:

	<u>Incoming Feed</u>	<u>Filtered Effluent</u>
Flow, gpm	2,650	2,650
PH	6-8	6-8
COD (ppm)	480	72
BOD (ppm)	210	21
SS (ppm)	38	1

The process for deoiled wastewater treatment is schematically shown in Figure 3.29.

Wastewater from the Oily Wastewater Treatment System flows directly from the Flotators to the Aeration Basins. Weirs regulate the split from the two flotators to the three basins. Recycled sludge from the Clarifiers, thickener overflow from the Sludge Thickener and backwash from the Media Filters are also fed to the front end of the basins. Since the flow from the thickener is small compared to the total flow, it is fed into only one of the three basins. The filter backwash rate is cyclic but of short duration, i.e. 750 GPM during backwash time which is only about 10 minutes out of several hours. Nevertheless, the high instantaneous rate is taken as it occurs, and the flow out of the basin and into the clarifier, which is sensitive to variations in flow rate, is averaged out by the use of "V" notch weirs on the outlet of the basins.

For initial operation, the aeration basins must be spiked with externally acclimated microorganisms. Once the system is in proper operation, there is a net production of microorganisms. Proper microorganism density, as required to destroy the organic matter, is obtained by proper elimination of microorganisms in the concentrated sludge.

Oxygen, wastewater and recycled sludge (microorganisms) are intimately mixed with the use of the Marox Aerators. Microorganisms feed on the biodegradable matter in the water and grow and multiply as the water moves from the feed end to the discharge end of the basins. The wastewater with the microorganisms overflows the basins into the clarifiers. A basin and clarifier work in unison.

Solid matter sinks to the bottom of the clarifier where slow revolving rakes draw it to a sump in the center. Clarified water overflows from the periphery of the clarifier, is collected in a trough, and discharged into the Filter Feed Tank.

Sludge from the center sump of the clarifier is split into two fractions. One part, as required for proper microorganism concentration in the aeration basins, is pumped to the feed end of the basins. The remainder, which represents net microorganism production, is concentrated in the sludge thickener. The thickener is nearly identical to the clarifier except for a special arrangement of paddles on the rakes that is conducive to better sludge concentration. Thus, the underflow is thicker in solids than the feed and goes to a belt press for dewatering. The clarity of the overflow is inconsequential since it is recycled to the aeration basins.

Figure 3.29 Block Flow Diagram

BLOCK FLOW DIAGRAM
DEOILED WASTEWATER
TREATMENT

The effluent from the clarifier will not be free of suspended matter and, therefore, is filtered prior to final use as cooling tower makeup. Filtration is performed with multimedia pressure filters similar to those in other parts of the plant. Operation of such filters is cyclic, i.e., they filter for a time, and when they are loaded with solids as indicated by a high pressure drop, filtration is stopped and the filters are backwashed to flush out the accumulated solids. The filter feed tank is used to dampen flow differences between the clarifier effluent and the filters.

Material to be filtered is pumped at a regulated rate through the four filters. Chlorine is injected into the water to be filtered at a controlled rate to prevent plugging of the filter due to microbiological growth. A polymer is also added at a controlled rate to render the suspended solids more easily filterable.

Stripped/Dephenoled Wastewater Treatment

Following treatment in Plant 38 and 39, the stripped and extracted process wastewater will contain large quantities of dissolved organics and inorganic salts. The organics are those not removed by the extraction process for phenolics removal. Sodium chloride is the main inorganic constituent.

Cooling tower blowdown, boiler blowdown and regeneration water from the demineralizer units also have large quantities of dissolved salts.

The treatment systems for these waste streams consists of biophysical treatment (powdered activated carbon/activated sludge, PACT) to remove the organic matter.

The PAC Activated Sludge/Wet Air Oxidation Treatment process is shown in Figure 3.30

Stripped/extracted sour water and blow-downs are sent to the PAC activated sludge system where the partially oxidized wastewater is treated by an activated sludge process in the presence of activated carbon. The presence of powdered carbon allows operation of the activated sludge system with high concentrations of easily settleable mixed liquor suspended solids (MLSS). The presence of powdered carbon also allows the biological treatment of hard-to-treat, concentrated industrial wastes.

The PAC/effluent, together with returning sludge (PAC and MLSS mixture) and regenerated PAC is fed into five Aeration Basins equipped with a total of 30 pure oxygen aeration systems of the Marox rotating diffuser type. Organics in the PAC/system effluent are biologically degraded in the aeration basins. The effluent overflows from the aeration basins into three clarifiers where PAC and sludge settle out. The clarifier overflow drains to the Filter Feed Tank. Most of the settled solids are recycled to the aeration basin. A small portion constituting the net microorganism production is pumped to the Zimpro wet oxidation system. This stream also contains spent PAC which is regenerated in the wet oxidation system.

The Zimpro wet oxidation system receives waste activated sludge from the deoiled wastewater biological treatment system, the spent PAC and waste activated sludge mixture from the PAC activated sludge system, and digested waste activated sludge from the sanitary sewage treatment package unit. The spent PAC is treated for removal of organics in the reactor; regenerated carbon is then returned to the PAC activated sludge system.

Two parallel wet oxidation trains are used. The solids slurry is first pumped to system pressure (1500 psig) by a positive displacement pump and then passed through a heat exchanger where it is preheated by the hot, oxidized effluent. The temperature of the feed is raised to a point where the oxidation reaction will proceed autogenously (without auxiliary fuel) in the reaction vessel. Oxygen required to support the oxidation reaction is compressed to system pressure and bubbled through the liquid phase in the reactor.

As oxidation progresses within the reactor, the heat of combustion raises the temperature of the reaction products to 530-540°F. The reactor effluent is then passed through the feed preheated for cooling. After cooling, the stream is depressurized to atmospheric pressure. The resultant vapors, containing most of the hydrocarbons, are scrubbed with cold water, to condense as much of the water vapor as possible, and vented to the flare.

Figure 3.30 Block Flow Diagram

BLOCK FLOW DIAGRAM
STRIPPED/DEPHENOLED
WASTEWATER TREATMENT

Solids Dewatering

The oily wastewater treatment system sludge, sanitary plant sludge, and wet air oxidation blowdown are dewatered by a pressure belt filter. The dewatered sludge is hauled to an approved landfill for disposal. The block flow diagram for this system is shown in Figure 3.31.

The design of the dewatering system is based on the following estimated sludge characteristics and flow:

Influent Characteristics

Flow, gpm (maximum)	200
pH	6-8
Percent solids	3.0

The performance requirements of the process units are as follows:

Cake dryness, %	20-30
Polymer consumption, lb/ton Dry Solids	10
Electrical consumption, KWH/ton DS	15-30

Sludges from the oily wastewater treatment system, the sanitary plant and the blowdown from the wet air oxidation are routed to a surge/equalization tank where the sludges are blended together. An air operated diaphragm pump moves the blended sludge from the tank to two belt presses. Just prior to the sludge entering the belt filters, a polymer is added to the stream. The polymer conditions the sludge to enhance the dewatering.

The belt presses are located on the second level of a small building to facilitate the filter cake removal by allowing it to drop by gravity into a dumpster. The polymer storage and feed system are on the ground level with the dumpster. When full the dumpster is hauled off to an approved landfill.

Figure 3.31 Block Flow Diagram

BLOCK FLOW DIAGRAM
SOLIDS DEWATERING

Sanitary Sewage Treatment

Sanitary sewage from the various sanitary facilities throughout the complex is collected in an underground sewer pipe network terminating at the central sewage treatment facility located downhill/downgrade from the project facilities. To avoid excessively deep excavations, with the long sewer runs involved, there is a need to use several sewage lift stations before the sewage reaches its destination. At the terminal end of the sewer network there is a final lift station delivering feed to the above ground sewage treatment plant.

The sanitary sewage treatment plant is a package unit, pre-engineered, shop fabricated, knocked down and reassembled in the field. It is an above ground installation made of the kind used in many industrial plants and small communities.

The package treatment unit is designed to treat 150,000 GPD of sanitary sewage with a maximum five day BOD loading of 250 pounds per day. It is designed to meet the Ten State Standards, which is a widely used basis for municipal sewage treatment design. It is further based on average per capita use of 35 GPD of water and 1,500 employees working the day shift.

The average design feed rate through the system is 109 GPM. The system can tolerate short term hydraulic loadings of up to 400 GPM, which is the design capacity of the pump lift station ahead of the treatment plant.

The process is shown in Figure 3.32.

Sanitary Sewage Treatment Package. The package consists of two above-ground concentric circular tanks. The outer one is divided into three compartments to form an aeration tank, an aerobic digester, and an effluent chlorine contact tank. The inner one is a settling tank.

Sewage is pumped from the Lift Sump into the inner tank, Aeration Basin. The volume of this compartment is 7,160 ft³ providing nine hours of detention time for the design flow rate of 109 GPM. Air from the Air blower is dispersed by special diffusers mounted circumferentially around the wall of the compartment.

Digested sewage overflows the aerator into the Clarifier where suspended solids settle to the bottom and clarified water overflows a circumferential weir into the Chlorine Contact Tank. The clarifier is sized for a minimum of four hours detention time and a rise rate of 700 GPD/ft². Sludge is removed via air lift mechanisms for recycle to the aerator and delivery to the Aerobic Digester.

Figure 3.32 Block Flow Diagram

BLOCK FLOW DIAGRAM

SANITARY SEWAGE
TREATMENT

Clarified water is chlorinated in the chlorine contact tank to destroy any remaining bacteria. This tank has a volume of 3,360 gallons. It is divided into three compartments to force flow over and under and avoid short circuiting. The chlorinated water is forwarded to bio-treatment. Chlorine gas is automatically controlled by the chlorinator which is sized to deliver up to 30 pounds/day. Chlorine supply is from chlorine cylinders.

The aerobic digester is also supplied with air from the blower. Digested sludge is pumped to the wet oxidation reactor for further decomposition. Holding time in the digester is four hours. Overflow from the digester is pumped by an air lift system back to the aerator.

Utility Summary

Electricity - 7000 Kw

50 psig steam - 3000 lb/hr

3.2.3 Options to Baseline

Methodology for Option Selection

- Identify The Primary Process Features And Variables Related To Each Process Feature (Refer Table 3.36 Below)
- Select The Variables For Each Of The Process Features For Baseline Design (Refer To Column 2 Of Table 3.37)
- Define Each Option By Changing The Variable Of One Process Feature At A Time, Maintaining The Variables Of Other Process Features Unchanged
- Combination Of The Newly Defined Process Features Defines The Respective Option
- Various Options Thus Defined are Shown In Tables 3.38 through 3.43.

Table 3.36

Process Features and Related Variables

Process Features:	Variables:
Cleaning Method For Feed Coal	<ul style="list-style-type: none">• Jig• Heavy Media Separation• Spherical Agglomeration
Reactor Configuration	<ul style="list-style-type: none">• Catalytic-Catalytic• Thermal-Catalytic• Catalytic-Catalytic with Vent Gas Separation
Vacuum Bottoms Processing	<ul style="list-style-type: none">• ROSE-SR• Coking Delayed Fluid
Hydrogen Production	<ul style="list-style-type: none">• Coal Gasification(1) Shell Texaco• Steam Reforming Of Natural Gas

(1) Will include ROSE-SR Concentrate Or Coke Where Applicable

Table 3.37

Process Features and Related Variables for Baseline Design

Process Features:	Variables:
Cleaning Method For Feed Coal	Jig
Reactor Configuration	Catalytic-Catalytic
Vacuum Bottoms Processing	ROSE-SR
Hydrogen Production	Coal + ROSE concentrate Gasification Utilizing TEXACO Technology (2)

(2) Selection (Shell vs Texaco) was based on economics and engineering judgement

Table 3.38

Process Features and Related Variables for Option 1

Process Features:	Variables:
Cleaning Method For Feed Coal Reactor Configuration	Heavy Media Separation (3) Catalytic-Catalytic
Vacuum Bottoms Processing	ROSE-SR
Hydrogen Production	Coal + ROSE-SR Concentrate Gasification Utilizing TEXACO Technology

(3) Coal Reactivity Is Assumed To Be Same As That Of The Base Case Coal

Table 3.39

Process Features and Related Variables for Option 2

Process Features:	Variables:
Cleaning Method For Feed Coal	Spherical Agglomeration (3)
Reactor Configuration	Catalytic-Catalytic
Vacuum Bottoms Processing	ROSE-SR
Hydrogen Production	Coal + ROSE-SR Concentrate Gasification Utilizing TEXACO Technology

(3) Coal Reactivity Is Assumed To Be
Same As That Of The Base Case Coal

TABLE 3.40

Process Features and Related Variables for Option 3

Process Features:	Variables:
Feed Coal	Cleaning By Jig
Reactor Configuration	Thermal-Catalytic
Vacuum Bottoms Processing	ROSE-SR
Hydrogen Production	Coal + ROSE-SR Concentrate Gasification Utilizing TEXACO Technology

Table 3.41

Process Features and Related Variables for Option 4

Process Features:	Variables:
Feed Coal	Cleaning By Jig
Reactor Configuration	Catalytic-Catalytic With Vent Gas Separation
Vacuum Bottoms Processing	ROSE-SR
Hydrogen Production	Coal + ROSE-SR Concentrate Gasification Utilizing TEXACO Technology

Table 3.42

Process Features and Related Variables for Option 5

Process Features:	Variables:
Feed Coal	Cleaning By Jig
Reactor Configuration	Catalytic-Catalytic
Vacuum Bottoms Processing	FLUID COKING (4,5)
Hydrogen Production	Coal + Coke Gasification Utilizing Texaco Technology

-
- (4) With DOE/PETC's Approval, Delayed Coking Option As Shown In Table 3.36 Has Been Deleted From The Scope Of Work. Exxon FLUID COKING Technology Was Selected As The Only Coking Technology For The Study.
- (5) Coke Is Sent To Gasifier

Table 3.43

Process Features and Related Variables for Option 6

Process Features:

Feed Coal

Reactor Configuration

Vacuum Bottoms
Processing

Hydrogen Production

Variables:

Cleaning By Jig

Catalytic-Catalytic

ROSE-SR (2)

Steam Reforming
Of Natural Gas

(2) Ash Concentrate Is Sent To Fluid Bed Combustor

DELIVERABLES FOR CASES INVOLVING OPTIONS

- Overall Material Balance
- Overall Block Flow Diagram
- Following Items For Affected Plants Only
 - + Design basis
 - + Process Description and Process Flow Diagram
 - + Material Balance
 - + Major Equipment Summary (1) Or Major Equipment List (2)
 - + Utility Summary
 - + On stream Factor
 - + Water Summary (3)
 - + Catalyst and Chemical Summary (3)
- For All Other Related Plants
 - + Adjustment Based On Associated Flow Rate Change
- Capital Cost Curve Estimate
- Model Output (Material Balance And Capital Cost) To Reflect The Changes Associated With Each Option

-
- (1) Bechtel Developed Plants
 - (2) Licensed Plants
 - (3) Where Applicable

3.2.4 Thermal-Catalytic Reactor Option

Methodology Used For Reactor Sizing:

- Use Wilsonville Run 250 D for Operating Conditions, Conversion and Yields
- Compare the space velocity (based on catalyst volume) between second stage catalytic reactor for the baseline and this option (1.12 vs 0.72 Lb maf coal/hr./Lb catalyst respectively). Refer to Table 3.44.
- Adjust the reactor volume and the number of reactor trains to account for the change in space velocity mentioned above for the second stage reactor (catalytic). Note that directionally the reactor volume per train will be higher than the base case. Also HRI design indicated that for the baseline design the weight of the reactor is the primary constrain for reactor size and consequently the number of trains required for this option will be more than those for the base case.
- Include ebullating bed pump for thermal reactor to induce proper mixing to avoid unacceptable axial temperature gradient.
- Calculate corresponding coal throughput per train.
- Calculate the thermal reactor volume (first stage) using Wilsonville experimental space velocity data (Run 250 D) and the number of trains selected.
- Calculate the diameter of the reactor based on gas velocity correlation (Wilsonville). Diameter being known, calculate height of the reactor from volume.
- The second reactor (catalytic) dimensions are adjusted such that the reactor be hydrodynamically consistent with HRI design.
- Calculate reactor wall thickness using thermal/stress data (mechanical). This step will not be followed. The wall thickness will be assumed to be same as HRI design. The potential minor difference is deemed to have insignificant impact on plant cost.
- Develop overall material balance for Plant 2 keeping product quality consistent with that of baseline.

Table 3.44

**Comparison of Critical Parameter
for Baseline and Therm-cat Option**

Parameter	Baseline Design (Run 257E)	Thermal-Cat Option (Run 250D)
Temp, °F		
Stage 1	790	825
Stage 2	760	740
Coal Space Velocity (Lb MAF Coal/Hr./Lb. Cat)		
Stage 1	1.12	(37.1)*
Stage 2	1.12	0.72

* The Number In Parenthesis Is In Lb MF Coal/Hr./Cubic Ft. Reactor Volume.

3.3 TASK III

Task III concerns the development of the cost estimate and economics for the baseline design and the alternates for the coal liquefaction facility. This part of the study includes the compilation of equipment lists and utilities summary, development of scaling factors for equipment size and plant cost, and development of the estimates for capital equipment, working capital, and owner's costs. Work to perform the economic analyses includes the workup of the manpower requirements and operating costs for the baseline design and for the alternates and the completion of sensitivity studies.

In this task plants are handled as packaged plants or blocks for the purpose of capital investment, and operating costs as well as overall capacity scale-up.

3.3.1 Methodology to Distribute Cost Estimate of Support Facilities

Methodology to distribute the capital cost of support facilities was discussed by the group. The decisions were as follows:

- a) The support facilities will be grouped into two categories i.e., capacity-dependent and capacity-independent plants where cost will be reported by the model.
- b) The scale up of the capacity-dependent plants will be done and printed by the model on plant-by-plant basis using the procedure in Figure 3.34.
- c) The costs from step (b) will then be combined with the costs of capacity-dependent plants in step (a) and reported by the model.

Methodology for Equipment Size Scale Up (Where size information is available) and Cost Scale Up for Plants:

There are two basic approaches to the cost scale up procedure. These can be defined as 1) interactive approach and 2) non-interactive approach.

In the interactive approach the cost scale up is dependent on the equipment sizing scale up. The approach is described schematically in Figure 3.33 below.

Figure 3.33

Interactive Approach to Cost Scale Up Procedure

Here S1 and C1 are the equipment sizes and plant costs for the base case. The Vertical arrow between S1 and C1 suggests that C1 is developed based on S1. Subscripts 2, 3, 4, 5, etc. are the scaled up versions of the base case equipment sizes (S1) and costs (C1).

As one may anticipate, this approach is cumbersome and requires considerable development time. Moreover, it may not be feasible to run the model on PC and it presents a high probability of non-convergence. Also this approach is not applicable for cases where size information on specific plants is not available.

In the non-interactive approach the equipment sizing scale up and the plant cost scale up are done independently. This approach is described schematically in Figure 3.34 below:

Figure 3.34

Noninteractive Approach to Cost Scale Up Procedure

The nomenclature is the same as Figure 3.33. The approach is simple and easily trackable from a modeling point of view. This approach is applicable to all cases including the plants where the equipment size information is not available. This procedure does not adversely affect the accuracy of the final scaled-up cost estimates.

It is therefore concluded that the development of cost vs capacity curve for all plants will be on non-interactive basis with the equipment sizing scale up procedure, as depicted in Figure 3.34 above.

Additionally, the cost scale up procedure for all plants (except plant 2) will be on overall "plant-by-plant" block basis and the size scale up procedure for all plants, where applicable, will be on equipment "class-by-class" basis.

3.4 TASK IV

Task IV concerns the development of the mathematical algorithms and models for equipment sizing, scale-up, costing, and train duplication for incorporation into the ASPEN/SP process simulation model being developed in Task V. Table 3.45 contains a description of the individual subtasks as detailed in the Task I Management Plan.

3.4.1 Status of Task IV

This task was conducted in parallel with the process model development work of Task V. Subtasks 4010 and 4020 called for a review of the existing ASPEN/SP equipment sizing equations for the major pieces of process equipment. This presumed that the simulation program would calculate the cost of each plant section by building it up from the costs of the individual pieces of major equipment. However, in line with conventional industrial practice, DOE/PETC agreed to a costing philosophy which involves a combination of individual equipment costing and factored costs based upon either the capacity of an entire plant or the capacity of an individual plant sub-section (see the topical report for Task III). The costing algorithms that are being implemented in the simulation model parallel this philosophy and eliminate the need for using the ASPEN/SP equipment sizing equations for costing purposes. Costing equations based on individual plant capacity or on individual plant subsections (Plant 2) are presented and discussed herein.

Since the coal liquefaction plant is the only plant in the entire complex that is being modeled in detail, equipment sizing equations were developed only for this plant. As discussed, these equipment sizes are not used directly for plant costing purposes.

Subtask 4030 deals with incorporating equipment size limitations in the process simulation model. Algorithms were developed which control the maximum train size of Plant 2 so as to keep the equipment sizes developed in the baseline design for Plant 2 below the maximum size limitation. This is reflected in the equipment sizing/scaling equations developed for Plant 2. Maximum size limits for the Plant 2 reactor diameter are handled in the kinetic model and are described in the topical report for Task V.

Subtask 4040 deals with the equations to handle multiple train requirements within a process unit. These equations were developed, and for flexibility, incorporate a train duplication parameter tailored to the particular plant. The number of trains may be supplied by the user as an input parameter. If the number of trains is not specified, the model will calculate the number of duplicate plants from the specified maximum and minimum plant capacities.

Subtasks 4050 and 4060 deal with the preparation and issuance of the topical report for Task IV which is being prepared.

Table 3.45**Task IV Description**

Following is a description of the individual subtasks of Task IV.

Subtask Number	Subtask Title	Description
4010	Review ASPEN equations	Review of existing ASPEN equipment sizing equations for major equipment
4020	Develop supplementary scale-up equations	Develop equations and algorithms, as required, to scale major equipment items
4030	Incorporate equipment size limitations	Incorporate major equipment size limits (reactor diameter, etc.) into scale-up equations
4040	Incorporate multiple train requirements	Incorporate into equipment scaling equations a means to handle multiple trains within a process unit. Philosophy may vary with process unit
4050	Draft topical report for Task 4	Report covering development of equations for equipment sizing, scaling, size limitations, and train requirements will be prepared
4060	Review of draft topical report for Task 4	The draft topical report for Task 4 will be reviewed with PETC prior to issue

For Plant 2, common equipment scaling algorithms were used to scale the sizes of the major pieces of process equipment. The scaling of the coal liquefaction reactors were not done using this basis, but are being sized by the kinetic model. This is described in the Task V report.

For all plants, the capital costs are being scaled from the baseline design case cost by a commonly used cost scaling equation that has been extended to allow for multiple trains.

All plants, other than the coal liquefaction plant, are being modeled by black box Fortran user block models. These Fortran user block models incorporate the capital cost scaling equation to predict the cost of each plant as a function of plant capacity and the number of duplicate plants.

The ASPEN/SP model also has been modified to utilize these cost scaling equations to predict the cost of individual pieces or groups of processing equipment as a function of capacity, where required.

Plant 2 Equipment Sizing Algorithms

Various pieces of process equipment are sized as a function of flow rate in order to maintain a constant key parameter for that piece of equipment. For example, tanks and separator drums are sized to maintain a constant residence time. This requires that the vessel volume vary linearly with the volumetric flow rate through it.

Heat exchanger areas and duties vary linearly with capacity. Pump and compressor power requirements also vary linearly with capacity. However, for distillation columns, the cross-sectional area varies linearly with capacity which means that the diameter varies with the square root of the flow rate.

The specific equations used to size the various individual pieces of process equipment for Plant 2 are given below:

Equipment Size Scaling Equations

The following equations are used to size the various pieces of process equipment.

I. Tanks, Overhead Receivers, Separators, and Compressor Knockout Drums

1. Maintain constant H/D .
2. Use correlation $\left(\frac{F_2}{F_1}\right)^{1/3} \times H_1$ or D_1 for calculating the new diameter D_2 and new height H_2 .

F_1 and F_2 are the baseline design case and current case feed rates, respectively.

II. Exchangers

Heat duty: linear with capacity.

Area: linear with capacity.

III. Pumps and Compressors

1. Pumps:

BHP: linear with capacity.

GPM: linear with capacity.

2. Compressors:

BHP: linear with capacity.

CFM: linear with capacity.

IV. Distillation Towers and Strippers

1. Maintain constant tray spacing, number of trays and overall height.

2. New diameter $D_2 = D_1 \left(\frac{F_2}{F_1} \right)^{1/2}$

These equations were programmed in a Fortran subroutine to calculate the sizes of the various major pieces of equipment in Plant 2. These equations are keyed to the material and/or energy flows calculated by the process model for each section of interest in Plant 2. Sizes are calculated for each major piece of equipment, including tanks, overhead receivers, separators, knockout drums, heat exchangers, towers, fired heaters, compressors, and pumps. A listing of the preliminary Fortran source code for this subroutine, which calculates and reports the sizes of the major equipment for Plant 2, will be provided in the Task IV topical report.

For the coal liquefaction reactors, the process model calculates the required sizes based on reaction kinetics which may vary according to the process conditions specified for a particular run. The equipment sizing subroutine will obtain the reactor size results from the process model.

Equations for Capital Cost Estimation

The capital cost for each plant is calculated as a function of the key flow rate by Equations 1 through 3. The key flow rate may be either the total flow rate of a specific feed or product stream or the flow rate of the major component in a specific feed or product stream. For example, the key flow rate for the coal cleaning plant is the clean coal product stream rate in Mlb/hr, and the key flow rate for the hydrogen plants is the useable hydrogen production rate (flow rate of hydrogen in the hydrogen-rich product gas stream) in MM SCF/hr of hydrogen.

$$\text{COST} = \text{FCOST} + (N - 1) * \text{SCOST} \quad (\text{Eq. 1})$$

$$\text{FCOST} = A + B * (F_O / (N * \text{RF}_O))^E \quad (\text{Eq. 2})$$

$$\text{SCOST} = F * \text{FCOST} \quad (\text{Eq. 3})$$

Where:

COST = Total capital cost of all duplicate plants

FCOST = Capital cost of the first plant

SCOST = Capital cost of each subsequent duplicate plant after the first one

N = Total number of duplicate plants, including duplicates and spares

F_O = Total key flow rate of all duplicate plants in appropriate units, such as MM SCF/hour or Mlb/hour

RF_O = Reference key flow rate of a single plant in appropriate units, such as MM SCF/hour or Mlb/hour. This flow rate is used to scale the capital cost of a single plant as a function of plant capacity

A, B, E and F = Constants for the calculation of the capital cost of a single plant as a function of plant capacity

In the above capital cost equation, constant A is the fixed capital cost associated with a single plant. The sum of constants A and B is the capital cost of a single plant of capacity RF_O . Thus, constant B is the variable capital cost of a single plant of capacity RF_O . Constant E is the plant cost scaling exponent. Constant F is the cost reduction factor for the construction of duplicate plants after the first one.

Multiple Train Requirements

The calculation of the number of multiple trains for any specific plant is being handled in a very simplistic way in the Fortran user block models.

First the user has the option of specifying the number of operating duplicate plants. When the number of duplicate plants is specified, that value is used, and no calculations are performed.

Otherwise, the number of operating duplicate plants is calculated based on the supplied maximum and minimum capacity for that plant. The minimum number of operating duplicate plants is selected such that they all have the largest capacity that will not exceed the specified maximum capacity to provide the desired total plant capacity.

This can be expressed mathematically by

$$P = \text{INT} (F_0 / RF_0) \quad (\text{Eq. 4})$$

If $RF_0 - P * F_0$ is greater than zero, then increase the value of P by one.

Where:

P = Total number of operating duplicate plants

F_0 = Total key flow rate of all duplicate plants in appropriate units, such as MM SCF/hour or Mlb/hour.

RF_0 = Maximum key flow rate of a single plant in appropriate units, such as MM SCF/hour or Mlb/hour.

$\text{INT} ()$ = Integer function; generates the largest integer value that is less than the value of the argument. This is the standard Fortran integer function.

Thus, the capacity of each operating duplicate plant is F_0 / P .

Each Fortran user block model has been programmed with the above logic for calculating the number of operating duplicate plants. In addition, for cost calculation purposes, provisions have been provided to allow the user to specify the number of spare plants that may be required only for operating reliability.

However, when the maximum capacity of a single plant is not specified, a single plant will be used. In addition, warning messages will be printed in the plant summary report if either the calculated capacity of a single plant is below the specified minimum capacity of a single plant, or if the capacity of a single plant is above the specified maximum capacity of a single plant.

3.5 TASK V

Task V concerns the development of the ASPEN process simulation model of the baseline design. The model will produce complete heat and material balances, elemental balances around each plant and the entire process complex, a major equipment list and outline specifications for Plant 2, utility requirements, capital cost for all plants, and a discounted cash flow economic model for the total complex. The model will be suitable for studying technology advances and options in a case study approach. The model will not include optimization capabilities.

3.5.1 Status of the Simulation Model

The preliminary status of the Simulation Model is shown in Table 3.46 below:

Table 3.46

<u>Plant</u>	<u>Description</u>	<u>Status</u>
1	Coal Cleaning and Preparation Plant <ul style="list-style-type: none">• Baseline case• Alternate case I• Alternate case II	Completed Completed Completed
2	Coal Liquefaction Plant <ul style="list-style-type: none">• Combined Plant 2, 6, & 8 model• Model of HRI Report• Total reactor yields model• First reactor yields model• Second reactor yields model• Detailed reactor effluent separation section model• Kinetic coal conversion model• Thermal reactor model• Vent gas separation	Completed Completed Completed Completed -- Needs Tuning Spreadsheet -- --
3	Gas Plant	Completed
4	Naphtha Hydrotreater	Completed
5	Gas-oil Hydrotreater	Completed
6	Hydrogen Purification <ul style="list-style-type: none">• Plant 6.1 - Membrane permeation section• Plant 6.2 - PSA section	Completed Completed
8	Carbon Rejection Plant <ul style="list-style-type: none">• ROSE-SR unit• Fluid coker	Completed Started

<u>Plant</u>	<u>Description</u>	<u>Status</u>
8	Carbon Rejection Plant <ul style="list-style-type: none"> • ROSE-SR unit • Fluid coker 	Completed Started
9	Hydrogen Production Plant <ul style="list-style-type: none"> • Coal gasification • Steam Reforming of Natural Gas Option <ul style="list-style-type: none"> a. H2 production b. Fluidized bed combustor 	Completed Completed Started
10	Air Separation	Completed
11	Sulfur Recovery	Completed
31	Steam and Power Generation	Model logic has been developed, but not implemented

Simulation Sciences Subcontract

Simplified Cost Module (ASPEN/SP Documentation Completed)	Completed
Elemental Balance Capability (Expected completion by August 15)	Partly Completed

3.5.2 Kinetic Model for Two Stage Coal Liquefaction Reactor

During this reporting period significant progress has been made on the kinetic modeling of the two stage coal liquefaction reactor.

The methodology used in developing this model is described in the logic diagram shown in Figure 3.35.

Figure 3.35 Kinetic Model for Two Stage Coal Liquefaction

3.6 TASK VI

Task 6 concerns the development of a training manual and a training course for the process simulation model. The training course will include an overview of the system, modification of the reporting system, interfacing user models, modification of chemical properties, use of the cost and economics modules, specifying flowsheets, streams, components, properties, and convergence. Trainees will be instructed through the use of case study example problems.

During this reporting period, facilities have been tentatively reserved for conducting ASPEN training beginning on October 28, 1991 and running through November 1, 1991.

4. KEY PERSONNEL STAFFING REPORT

Key Personnel staffing report for this reporting period (March 18, 1991 through June 23, 1991) as required by DOE/PETC is included in Table 4-1 shown below.

Table 4-1
Key Personnel Staffing Report

Duration of Quarter From March 18, 1991 to June 23, 1991

<u>Name of Key Person</u>	<u>Function</u>	<u>% Time Spent*</u>
<u>Bechtel:</u>		
S. N. Habash	Project Manager	71
S. N. Poddar	Technical/Project Coordinator	89
T. J. Reynolds	Project Secretary	67
R. F. Earhart	Process Manager	48
H. F. Zaras	Support Facil. Manager	91
<u>Amoco:</u>		
A. B. Schachtschneider	Project Manager	9
S. J. Kramer	Principal Investigator	65
Arun Basu	Principal Investigator	26

* (Number of hours spent/total available working hours
for March 18, 1991 through June 23, 1991) x 100.

END

**DATE
FILMED
9 / 22 / 92**