MARTIN MARIETTA

ORNL/ER-32

**ENVIRONMENTAL
RESTORATION
PROGRAM**

**Well Plugging and Abandonment Plan
for Waste Area Grouping 6 at
Oak Ridge National Laboratory,
Oak Ridge, Tennessee**

**R. G. Stansfield
D. D. Huff**

MANAGED BY
MARTIN MARIETTA ENERGY SYSTEMS, INC.
FOR THE UNITED STATES
DEPARTMENT OF ENERGY

UCN-17560 (6 7-91)

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

ENERGY SYSTEMS

ER
»»»»

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from 615-576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

ORNL/ER--82

DE92 018076

Environmental Restoration Division
ORNL Environmental Restoration Program

**Well Plugging and Abandonment Plan for Waste Area Grouping 6
at Oak Ridge National Laboratory, Oak Ridge, Tennessee**

**R. G. Stansfield
D. D. Huff**

Date Issued—June 1992

Prepared by
Environmental Sciences Division
Oak Ridge National Laboratory
ESD Publication 3823

Prepared for
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
under budget and reporting code EW 20

OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37831-6285
managed by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U.S. DEPARTMENT OF ENERGY
under contract DE-AC05-84OR21400

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

MASTER

Author Affiliations

R. G. Stansfield is a geotechnical consultant to, and D. D. Huff is a member of the Environmental Sciences Division, Oak Ridge National Laboratory, Martin Marietta Energy Systems, Inc.

CONTENTS

	<u>Page</u>
ACKNOWLEDGMENTS	v
EXECUTIVE SUMMARY	vii
1. INTRODUCTION	1
1.1 OBJECTIVES AND SCOPE	1
1.2 PURPOSE OF THE P&A PLAN	1
2. WAG 6 BACKGROUND AND ISSUES	2
2.1 SITE HISTORY	2
2.1.1 Waste Disposal Activities	2
2.1.2 Past Well Management Practice	3
2.1.3 Regulatory Setting	3
2.2 ORNL WELL P&A ISSUES	3
3. DECISION PROCESS AND FIELD IMPLEMENTATION FOR P&A	4
3.1 RESPONSIBILITIES	4
3.2 SCHEDULES	4
3.3 WELL INVENTORY, SECURITY, AND MAINTENANCE	5
3.4 DATA GAPS IN THE WELL INVENTORY	5
3.5 WELL ABANDONMENT EVALUATION	5
3.5.1 Wells to be Maintained	8
3.5.2 Wells to be Plugged and Abandoned	8
3.6 IMPLEMENTATION	8
3.6.1 Pre-Abandonment Approvals	9
3.6.2 Coordination	9
3.7 FIELD OPERATIONS	9
3.7.1 Health and Safety	9
3.7.2 Equipment and Materials	10
3.7.3 Site Preparation	10
3.7.4 Well Inspection by Down-hole Camera and Surface- Geophysical Methods	10
3.7.5 Decontamination of Downhole Equipment	10
3.7.6 Site Clean-up and Waste Management	11
3.8. REPORTING REQUIREMENTS	11
4. WELL ABANDONMENT	12
4.1 REQUIREMENTS	12
4.1.1 Performance Requirements	12
4.1.2 Regulatory Requirements	12
4.2 WELL ABANDONMENT CONSIDERATIONS	12
4.2.1 Hydrogeologic Setting	12
4.2.2 Existing Well Design	13
4.2.2.1 Single-cased wells	13
4.2.2.2 Multicased wells	14

4.2.3	Level of Contamination	14
4.3	WELL ABANDONMENT TECHNIQUE	14
4.4	WELL PLUGGING MATERIALS	14
4.4.1	Coarse-Granular Bentonite	14
4.4.2	Crushed Stone or Gravel	15
4.4.3	Type 1 Cement Grout	15
4.4.4	Type 1 Cement/Bentonite Grout	15
4.4.5	Microfine-Cement Grout	15
4.5	P&A METHODS FOR ALL WELL TYPES	15
4.5.1	Waste Trench Wells	16
4.5.2	French Drain Wells	16
4.5.3	Wells in Unconsolidated Strata	16
4.5.4	Non-Screened Bedrock Wells	17
4.5.5	Screened Bedrock Wells	17
REFERENCES		18
APPENDIX A - INVENTORY OF RECORDED WELLS AT WAG 6		19
APPENDIX B - INVENTORY OF WELLS TO BE MAINTAINED AFTER CLOSURE AT WAG 6		39
APPENDIX C - INVENTORY OF WELLS TO BE PLUGGED AND ABANDONED AT WAG 6		43
APPENDIX D - PLUGGING AND ABANDONMENT PROCEDURES		61
APPENDIX E - WELL PLUGGING AND ABANDONMENT FIELD OPERATIONS PLANNING FORM		75
APPENDIX F - WAG 6 WELL PLUGGING AND ABANDONMENT REPORT		81

ACKNOWLEDGMENTS

This project was sponsored by the U.S. Department of Energy's Office of Environmental Restoration and Waste Management in support of the Oak Ridge National Laboratory (ORNL) Environmental Restoration Program. The authors wish to acknowledge the support of F. P. Baxter, the ORNL groundwater program coordinator, R. K. Gryder, and M. A. Wood for their assistance with the well inventory data base. J. Switek and R. O. Kennard provided support for field verification of the wells data. W. Rehfeld and D. Watkins of CER Corporation contributed to earlier drafts of this document. The decisions on wells to be retained in Waste Area Grouping 6 came from a workshop conducted by the authors with the following participants: F. P. Baxter, K. Black (ECE Corp), R. Gryder, G. Moore (University of Tennessee), C. Rightmire, D. Van Hoesen, R. Yager (ECE Corporation), and T. Zondlo.

EXECUTIVE SUMMARY

This plan presents the strategy and detailed approach for well plugging and abandonment (P&A) at Waste Area Grouping 6 (WAG 6). An inventory of 768 wells, the total number known to have been installed in WAG 6 based on a combined review of data and direct field inventory, is provided in Appendix A. All wells that are not required for closure or postclosure surveillance of WAG 6 will be decommissioned. A listing of 69 existing WAG 6 wells that will be maintained for postclosure surveillance is provided in Appendix B, and their locations are shown in Fig. 1. Appendix C contains a list of all WAG 6 wells that will be decommissioned, although some may no longer exist. Their locations are shown in Fig. 2. It is likely that some new wells will be drilled as part of postclosure monitoring of Solid Waste Area 6 (SWSA), but they are beyond the scope of this report. It is intended that this plan provide a basis for developing contracts for cost and schedule determinations for the P&A process.

Of the 768 wells listed in Appendix A, 31 are listed as previously destroyed, but the meaning of this term is not defined. In addition, 89 of the 690 wells listed in Appendix C to be decommissioned could not be located by field search. A further effort will be made, through the use of engineering survey, localized application of a geophysical method, and shallow excavations to find each of the total of 120 destroyed or unlocated wells that are not in waste burial trenches or beneath the Interim Corrective Measure (ICM) caps.

As a general policy, wells in WAG 6 will be decommissioned with essentially all subsurface well materials remaining in place. P&A methods and specific plugging procedures are presented in Appendix D for the various types of well installations and subsurface conditions.

All wells within the waste burial trenches will be plugged with coarse-granular bentonite. Considering the quantities of water anticipated in any of these wells, placement of coarse-granular bentonite should not displace well water upward to the ground surface; thereby avoiding the necessity of containment and disposal of contaminated well water. The coarse-granular bentonite will be placed to fill the well to a level 3.5 feet below the ground surface, followed by the addition of powdered bentonite to a level 3 feet below the ground surface. Type 1 cement grout will then be added to bring the plug to a level 1 foot below the ground surface. (The powdered bentonite will prevent the infiltration and loss of the cement grout through the interstices of the non-hydrated, coarse-granular bentonite.) After 24 hours the casing will be removed to a depth of 1 foot below the ground surface. Excavation will be limited to 1 foot, as the contaminated material in the trenches is covered with approximately 2 feet of noncontaminated soil. The excavation will be backfilled with excavated soil and properly tamped. All of the plugging material will be placed into the well from the ground surface as the well depth will not exceed approximately 20 feet.

All wells in the French drain will be plugged with crushed stone or gravel (3/4 in maximum size) to a level 2 feet below the ground surface. This is the approximate depth of the top the crushed stone drain. The PVC well pipe will be removed to this depth, and the excavation backfilled with excavated soil and properly tamped. There is little potential for contamination in this 2 foot excavation. The stone will be placed into the well from the ground surface.

Wells to be decommissioned that are installed in unconsolidated strata (do not penetrate bedrock) and are not within the burial trenches or French drain will be grouted with Type 1 cement/bentonite grout or microfine-cement grout. Grout will be placed by the tremie method and will displace well water from the top of the well as the grout is pumped into the bottom of the well. Water and water diluted grout will be contained and disposed of properly. Prior to grouting, if records do not document the placement of a grout seal when the well was constructed, wells with casings longer than 10 feet will be perforated or slit from the top of the well screen to within 10 feet of the ground surface to ensure that the annulus will be securely sealed with grout. Microfine-cement grout will be used in those wells that require slitting or perforating; it will also be used in the screened sections of wells that have filter packs longer than 10 feet. After grouting, the upper 3 feet of the well casing will be removed, and the excavation backfilled with the excavated soil and properly tamped.

Wells that penetrate firm bedrock may be plugged with two types of grout. Prior to grouting, if the records do not document the placement of a grout seal when the well was constructed, the casing will be perforated or slit from a depth of 10 feet below the ground surface to the bottom of the casing to insure that the annulus will be securely sealed. It is not the purpose of decommissioning grouting to grout the natural fractures or openings in the rock at any distance away from the borehole; therefore, if the casing is split or requires perforating, two types of grout mixes may be used. Type 1 cement/bentonite grout will be tremied into the exposed bedrock portion of the well, and a more penetrating grout made from microfine cement will be placed in the cased portion. If the casing is not required to be slit or perforated, the well will be grouted with Type 1 cement/bentonite grout only. Grout will be placed by the tremie method and will displace well water from the top of the well as the grout is pumped into the bottom of the well. Water and water diluted grout will be contained and disposed of properly. After grouting the casing will be removed to a depth of 3 feet below the ground. The excavation will be backfilled with excavated soil and properly tamped.

Bedrock wells that were completed with well screens will be decommissioned using the same procedures as for cased and screened wells in unconsolidated material.

Any obstructions detected during depth measurement of wells will be inspected by downhole camera and removed so that grouting or plugging can proceed. Obstruction removal will be accomplished by redrilling or percussion methods inside of existing well casings and screens.

Records will be kept of the P&A process and the ORNL well database will be updated to reflect the plugged and abandoned status of the wells.

1. INTRODUCTION

Site environmental characterization and remediation require data obtained from the installation and sampling of wells. When these wells are no longer needed or not producing reliable information, or are damaged and can act as conduits for contaminant migration, they should be identified and properly decommissioned. This is most important for wells of sufficient depth to create the potential for exchange of fluids between different hydrologic units.

1.1 OBJECTIVES AND SCOPE

The need for a uniform well and borehole plugging and abandonment (P&A) program for the Oak Ridge National Laboratory (ORNL) was discussed in the ORNL Corrective Action Plan written in response to the Tiger Team Report. Details were identified in the Department of Energy (DOE) Environmental Survey of 1987, the DOE Oak Ridge Operations Environmental Protection and Quality Assurance (QA) Appraisal of August and September 1988, and again in the DOE Environmental Safety Health and Quality Assurance (ESH & QA) Appraisal of April 1990. An organizational basis for an ORNL P&A program was suggested in the draft ORNL Groundwater Protection Program Management Plan (May 1990) as a functional responsibility of the Groundwater Protection Program Manager.

In 1988, a closure plan for Waste Area Grouping 6 (WAG 6) was submitted to the U.S. Environmental Protection Agency (USEPA) and the Tennessee Department of Health and Environment (TDHE), [now the Tennessee Department of Environment and Conservation (TDEC)], as required by the Resource Conservation and Recovery Act (RCRA). One step in the closure of WAG 6 is the P&A of all wells that are not required to support monitoring activities during and after closure. This is an important step in preparing the site for future closure activities.

1.2 PURPOSE OF THE P&A PLAN

This P&A plan provides the basis for effectively decommissioning unneeded wells at WAG 6 by eliminating potential well borehole pathways for contaminant migration. The procedures and guidelines contained in this document are applicable to any organization, division, or group that is responsible for wells at WAG 6 and, where conditions are similar, at other ORNL sites.

2. WAG 6 BACKGROUND AND ISSUES

2.1 SITE HISTORY

WAG 6, which includes ORNL's only active disposal site for low-level solid radioactive waste, is located in Melton Valley, about two miles southwest of the ORNL Main Plant Area. The WAG contains three Solid Waste Management Units (SWMUs):

- Solid Waste Storage Area 6 (SWSA 6),
- Emergency Waste Basin (EWB), and
- Explosives Detonation Trench (EDT).

SWSA 6 is the largest of the three SWMUs, with an area of about 68 acres, approximately 20 of which have been used for waste disposal. Low-level radioactive waste has been buried at SWSA 6 since 1969. According to waste disposal records, chemical and biological wastes were buried with the radioactive wastes from the time the site was opened in 1969 until May 1986. In May 1986 operations were modified to eliminate the disposal of hazardous wastes regulated by RCRA.

The EWB, which is located outside of the SWSA 6 boundary, was constructed as a low-level radioactive waste or process waste holding basin, but reportedly has never been used.

The EDT, located in the eastern portion of WAG 6, was used to detonate shock-sensitive chemicals and explosives. The EDT has been backfilled and capped.

A number of characterization studies, research projects, and technology demonstrations have been conducted at WAG 6 over the past decade. Analysis of specifics from these sources is beyond the scope of this presentation. These projects have provided an understanding of the physical characteristics of the site; an approximation of the inventory of materials buried at the site; and a clear indication of the extent of contamination of soils, sediments, surface water and groundwater within WAG 6. They also resulted in the installation of a number of wells.

2.1.1 Waste Disposal Activities

WAG 6 is generally designated as a low-level radioactive waste disposal area; however, chemical and biological wastes have been buried with the radioactive wastes. Prior to May 1986, waste solvents, cleaning solutions, paint thinners, oil, fuel, and various chemicals were buried in "solvent auger holes" and unlined trenches. Records indicate that about 230 55-gallon drums containing waste scintillation fluids were buried in biological waste trenches. Since 1986 only solid waste has been placed in underground concrete "greater confinement disposal" (GCD) silos and in aboveground concrete vaults or casks that have been placed on concrete pads. Areas within SWSA 6 that contain RCRA regulated wastes and that were emplaced after November 8, 1980, have been covered by the ICM caps, constructed of high-density polyethylene.

2.1.2 Past Well Management Practice

Hundreds of wells have been installed throughout the operational history of WAG 6 by several different organizations for a wide variety of purposes. The wells that were installed from the beginning of operations until the late 1970s were mostly perforated, galvanized metal pipes, placed in augered holes with no grout seal in the casing/borehole annulus. Beginning in the late 1970s, increasing attention has been paid to well construction details. Most of the wells were placed either for characterization purposes or to observe the water levels inside burial trenches. In many cases, information about these wells is either not available or is of a very general nature. Many of these wells have been damaged or destroyed by road construction, trench excavation, and lawn mowing. Some well locations are buried under roads, buildings, and ICM caps placed over RCRA regulated areas.

2.1.3 Regulatory Setting

Energy Systems established the Environmental Restoration (ER) Program that is directed toward the cleanup of areas where contamination from past activities is known or suspected. The ER Program, which provides for comprehensive management of contaminated sites until final remediation, was initiated under applicable DOE Orders. In 1986 EPA established its authority to enforce regulatory requirements for ORNL remedial response activities under RCRA Section 3004(u). A RCRA Facility Investigation (RFI) began in 1988 at WAG 6 to characterize the site and to determine the extent of contamination. Then in December 1989, the Oak Ridge Reservation was placed on the National Priorities List, and the provisions of Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) had to be met. Consequently, a Federal Facility Agreement (FFA) was negotiated between DOE-OR, EPA Region IV, and TDEC. The FFA sets priorities for remediation activities, assigns agency roles and responsibilities, and establishes procedures for document review and interaction among the agency officials. Previous agreements regarding Solid Waste Storage Area 6 (SWSA 6) have been incorporated into the FFA, which became effective on January 1, 1992.

2.2 ORNL WELL P&A ISSUES

There has been no central control or organizational responsibility for custody and maintenance of wells at WAG 6. The fact that many unneeded wells at WAG 6 have not been decommissioned was reported during a recent Tiger Team audit of ORNL. At that time it was also noted that a significant number of wells have been inadequately inventoried, secured, or maintained. Further, it was pointed out that many wells may be potential conduits for cross-contamination under certain conditions.

Because many wells have come in contact with hazardous wastes, well abandonment techniques will be used that minimize waste generation and still satisfy abandonment goals. The Well P&A Plan for WAG 6 is designed to meet technical requirements, while recognizing the operational constraints and health and safety concerns at ORNL.

3. DECISION PROCESS AND FIELD IMPLEMENTATION FOR PLUGGING AND ABANDONMENT

Each well in WAG 6 is considered a candidate for P&A and is evaluated as to whether there is a present or future need for the well in support of WAG 6 closure activities. Only needed, undamaged wells, for which available records provide all pertinent information as to their satisfactory construction by today's criteria, or that will be upgraded to meet that criteria, will not be plugged and abandoned.

3.1 RESPONSIBILITIES

The WAG 6 Closure Project is responsible for identifying all wells to be plugged and abandoned and for carrying out field operations in conformance with this P&A plan. Actual field operations will be managed by Energy Systems Engineering for the Environmental Restoration Program. The ORNL Groundwater Program Coordinator (GPC) will be consulted for technical oversight and independent review.

The roles and responsibilities for well P&A as part of WAG 6 closure activities will be defined in separate documents, under the leadership of the WAG 6 Closure Project. One such document is the Project Management Plan, which provides general guidance on roles and responsibilities of the various project team members (C. Oaks, personal communication). A more detailed document, under development by Energy Systems Engineering, deals specifically with the Phase I well closure activities (S.L. Laman, personal communication). The latter document describes interactions between Energy Systems organizations (Engineering, Environmental Sciences Division, Plant Support Organizations - health physics, industrial hygiene, and environmental compliance, and the ORNL groundwater protection program coordinator), and their service contractors Ebasco and MK-Ferguson. This plan will address approvals, responsibilities, and the various plans that will be developed to support the P&A project. It will also address Field Operations, which include health and safety, equipment and materials, site preparation, well inspections, decontamination, waste management, site cleanup, and reporting requirements.

3.2 SCHEDULES

Plans for WAG 6 well decommissioning are divided into two phases. Phase I will deal with wells that are located outside existing RCRA ICM caps and the 100-year flood plain, and Phase II will include the areas under the ICM caps or within the 100-year flood plain. Phase I is further divided into two parts. Part A will involve wells in areas outside the proposed caps that are being considered as alternatives for closure. Part B will include wells that are within the proposed closure cap areas, but are not under existing RCRA ICM caps. It is further anticipated that Phase I, Part A will begin with wells to be P&A that present low probability for the presence of contaminants and few complications. The intent is to progress from the simple to more complex P&A actions. The approximate timing for these activities is:

- Phase I, Part A June 1992 - December 1993
- Phase I, Part B March 1993 - March 1994
- Phase II March 1994 - September 1997

3.3 WELL INVENTORY, SECURITY, AND MAINTENANCE

From previous inventories and direct field inspection, the Environmental Sciences Division (ESD) compiled an inventory of 768 wells known to have been installed at WAG 6. A list of these wells is provided in Appendix A along with their location coordinates and other available pertinent data. As indicated in Appendix A, 9 of the 768 wells were properly decommissioned in 1990. The field inspection was limited to visual observation of the surface characteristics of the well only. Due to time and other constraints, the wells were not opened and measured or examined by other means. This inventory is being used by the ORNL GPC to update the Geographic Information System (GIS) and tabular data for SWSA 6 in order to manage and document the P&A technical oversight function when this plan is implemented.

Guidelines for well security and maintenance inspections, recordkeeping, and required actions are not part of the P&A plan; and therefore are not addressed in this document. They will be the subject of other documents developed under the direction of the ORNL GPC.

3.4 DATA GAPS IN THE WELL INVENTORY

The current inventory (Appendix A) lists 768 wells in WAG 6 and indicates that there are only 185 wells known to be deeper than 22 feet. (The depths of the burial trenches, auger holes, and subsurface silos range to approximately 20 feet.) There are 120 wells from previous inventories that could not be found, and, of that number, only 31 were previously reported as being destroyed. Also, it is not clear for all wells what is meant by the status of "destroyed". At present depth is missing from 182 well records; however, a substantial fraction of these wells are believed to be less than 15 feet deep. Well casing diameter and material information is also missing from some of the records. Further, the inventory indicates that 51 wells are damaged in some fashion, but the extent is not recorded. Prior to well decommissioning, efforts will be made to supply these missing data by additional literature searches and personal interviews and by further well inspection in the field. Specific efforts will be made, through the use of engineering survey, localized application of a geophysical method, and shallow excavations to find each of the total of 120 destroyed or unlocated wells that are not in waste burial trenches or beneath the Interim Corrective Measure (ICM) caps. Improvements in data will be provided periodically to the ORNL GPC for use in operational databases.

3.5 WELL ABANDONMENT EVALUATION

Wells shown in Appendix B are to be saved as active wells after closure of WAG 6, and their locations are shown in Fig. 1. Wells in WAG 6 that are candidates for P&A have been identified and are listed in Appendix C, and their locations are shown in Fig. 2. However,

that list includes wells that were previously destroyed or were not found in field searches. Therefore, because some of the destroyed or unlocated wells may not be found through available methods, the final number of wells that will be P&A at WAG 6 may be less than the total of 690 listed in Appendix C.

3.5.1 Wells to be Maintained

Regulatory and technical requirements determine that a number of wells will have to be maintained after closure of WAG 6. As a result of a workshop of technical representatives of programs involving wells at WAG 6, a total of 69 wells will be maintained after closure of WAG 6. Of these, 26 are current RCRA compliance wells which will be used with the remaining 43 piezometers to evaluate the effectiveness of the closure design, including the three remedial caps presently proposed, during the postclosure period. With the exception of three wells on the list, records indicate that all the wells to be maintained are constructed with the casing/borehole annulus sealed and grouted to prevent the transfer of fluids along the borehole. Three wells, ETF-13, 14, and 15 will have to have their casing/borehole annuli grouted in order to meet today's criteria.

3.5.2 Wells to be Plugged and Abandoned

All existing wells, except those determined to be necessary for WAG 6 closure and post closure surveillance, are to be plugged and abandoned. These wells were evaluated to determine appropriate methods and procedures for decommissioning, as outlined below.

- Data files and location maps of wells identified from the field inventory have been compiled.
- Based on available records and information, determinations have been made as to the type of well construction. Where adequate information about well construction is not available from completed inspections of located wells, the well will be inspected again to specifically determine the type of material and nominal diameter of the well riser pipe and the depth of the well.
- In light of the site's hydrogeology, the potential for migration of contaminants between different water-bearing zones in wells was assessed by reviewing installation details, well logs, and well depth. Depth of wells is one of the most important parameters in this regard. Wells drilled only in the regolith (upper 25 feet or so of the subsurface) have little potential for allowing direct migration of fluids to deeper zones or between saturated units.

3.6 IMPLEMENTATION

The P&A procedures prescribed in Appendix D will be reviewed for final verification when the Well Plugging and Abandonment Field Operations Planning Form (Appendix E) is completed and approved. The procedures to be implemented depend on parameters such as the hydrogeologic setting of the well, and the depth, design, casing materials, location within the site, and level of known or suspected contamination. All of these parameters are not known for all wells, and additional investigation will be made to attempt to fill the data

gaps identified in Sect. 3.3. Although the plan is to decommission all wells by grouting or plugging the well with the casing remaining in place, contingency procedures are provided for decommissioning by removal of the well casing if it is found to be necessary. Further, it can not be assumed that every well in WAG 6 will be decommissioned without some change or deviation to the procedures provided in Appendix D, perhaps due to modification of the well's installation that may have been made through the years. If deviations from Appendix D procedures become necessary, they will be approved by the WAG 6 project manager and the GPC.

3.6.1 Pre-Abandonment Approvals

WAG 6 project personnel will complete Field Operations Planning Forms for Well Plugging and Abandonment (Appendix E) and submit them to the Project Manager and the GPC for approval before field work begins. The field operations plan must identify all wells to be abandoned, methods of abandonment, health and safety considerations, and the responsible organizations performing the work and field oversight.

Any modifications to the Field Operations Plan will be approved by the Project Manager and the GPC, and recorded prior to implementation.

3.6.2 Coordination

A WAG 6 project field supervisor will coordinate activities with the field personnel, schedule field work, and make field decisions as necessary. ORHSP will provide technical assistance to the field supervisor, if requested.

Energy Systems will provide for safety, security, and environmental orientations for the field personnel prior to the start of work.

A technical oversight individual (geologist or qualified engineer) will be present at each well site to document that the P&A procedures and guidelines provided in this plan are being followed.

3.7 FIELD OPERATIONS

The field supervisor will obtain the list of the wells selected for P&A and a map that indicates the exact location of each well scheduled to be decommissioned. The wells will be flagged with surveyor's tape, or in an equally appropriate manner, so that they may be quickly identified in the field.

3.7.1 Health and Safety

P&A of some wells will generate contaminated fluids and other materials. Proper OSHA safety training and equipment is a basic requirement for hazardous materials work. Additionally, work will be performed in accordance with appropriate procedures and standards including SARA/OSHA, HAZWOPER, Standard Practice Procedure X-ESH-1 "Interim Plan for Worker Health and Safety for ORNL Hazardous Waste Operations", and "Health, Safety,

and Environmental Protection Procedures for Excavation Operations, ORNL/M-116/R1". Applicable Site Health and Safety Plan and Comprehensive Work Plan requirements will be met.

3.7.2 Equipment and Materials

The well closure contractor will subcontract all materials, equipment, and field personnel necessary to plug and abandon wells in accordance with the this P&A work plan and the field operations plan.

The well closure contractor will use drilling or augering equipment appropriate to site conditions, drilling depth, and other project requirements. The rigs will be outfitted with the necessary equipment to safely and properly abandon wells. All necessary support equipment (water truck, pumps, mud pan, grouting equipment, supplies, etc.), and a downhole camera, will be provided by the well closure contractor.

3.7.3 Site Preparation

Downhole equipment and sampling devices will be removed from the well. Where present, guard posts will be removed to allow plugging equipment access to the well. The well should then be ready for either logging with the downhole camera or abandonment as required. Plastic sheeting will be placed appropriately to cover the ground surface at the well site during all field operations. If possible, sampling equipment will be salvaged for use by OR.

3.7.4 Well Inspection by Down-hole Camera and Surface-Geophysical Methods

Wells found to have obstructions that do not permit the placement of the grout tremie pipe to the bottom of the well will be inspected and logged via a downhole camera. Use of the camera may help determine the cause of the blockage and how best to remove it. As wells with screened intervals longer than 10 feet will be grouted with microfine-cement grout rather than Type 1 cement/bentonite grout, the camera will be used in any well in which the length of the well screen is not documented in the records. Also, the camera will be used in any open-hole bedrock well in which the cased portion is to be slit or perforated, and the records do not indicate either the length of the open-hole or cased portion of the well. Findings of the camera inspection will be submitted with the P&A Report for that well.

Searches will be made by localized application of surface-geophysical method at surveyed locations of metal-cased wells, shown in the inventory as "not found" or "destroyed" and that are not located within waste burial trenches or ICM capped areas. No other geophysical methods are planned for use in the P&A of wells at WAG 6.

3.7.5 Decontamination of Downhole Equipment

Upon completion of work at a well site, all tools and equipment placed into the well will be screened for radioactive contamination. Tools and equipment determined to be contaminated shall be decontaminated by the use of high pressure, hot-water cleaners or by scrubbing or wiping with potable water and detergent, followed by alcohol or acid and distilled water rinses. Water and other materials used for decontamination will be contained for

proper disposal. Radioactive contamination will be reduced to limits prescribed in the ORNL Health Physics Manual, "Procedures and Practices for Radiation Protection and Radiation Monitoring".

3.7.6 Site Cleanup and Waste Management

During P&A operations, proper site clean-up will be performed. Materials generated during P&A may be classified as hazardous or radioactive and will be collected and disposed of properly, in accordance with the waste management plan to be developed for WAG 6 well decommissioning.

3.8. REPORTING REQUIREMENTS

Documentation of the well-specific procedure used during P&A shall record all dates, times, calculations, logs, and measurements for the decommissioning of each well, along with any notes that may be pertinent. The contractor shall submit an ORNL Well Plugging and Abandonment Report (Appendix F) to ORNL WAG 6 project personnel within a specified time interval of the P&A of each well. After verification of the accuracy and completeness of content, the P&A report will be provided to the GPC within a specified time interval. The P&A contractor shall enter the verified data and information contained in this report into a computer data base system that is suitable for electronic transfer to the GPC's system and shall transfer the data to the GPC within a specified time interval.

Annually, WAG 6 project personnel will prepare a formal report to document the P&A process. This annual report will include an evaluation of effectiveness of field methods, and, if appropriate, describe changes or additions to procedures that improve field operations.

4. WELL ABANDONMENT

4.1 REQUIREMENTS

The primary purpose of well abandonment is to close the well completely to prevent the migration of contaminated fluids into the well and to prevent exchange between water-bearing units along the borehole.

4.1.1 Performance Requirements

P&A methods should not only prevent entry of surface water into a well pipe, but should effectively prevent vertical movement of fluids in the borehole between the hydrostratigraphic units that are penetrated by the well. Decommissioned wells should have minimal influence on the local environment compared with the original geologic setting (USEPA 1975).

4.1.2 Regulatory Requirements

Prior regulatory approval is not required for P&A procedures for wells. However, documentation will be provided to TDEC and USEPA, for information purposes only.

4.2 WELL ABANDONMENT CONSIDERATIONS

Selection of the appropriate method for abandonment is based on information compiled for each well (Allar et al. 1989). Factors that have been considered, and will be reviewed as additional well inventory data are obtained, include

- hydrogeologic setting;
- well design, including depth;
- well construction materials; and
- presence and amount of contamination.

4.2.1 Hydrogeologic Setting

The hydrogeologic conditions at the site (e.g., infiltration rates, in situ permeability of saturated zones, consolidated or unconsolidated strata, dip and strike of bedrock strata and saprolite, fracture spacing density, hydraulic gradients) affect the occurrence and movement of groundwater and contaminant transport in the subsurface.

Contaminants that can move through the vadose zone may move directly to the water table or they may be adsorbed and partially retained within the vadose zone to act as long-term sources of groundwater contamination (USEPA 1975).

When groundwater occurs under unconfined saturated conditions, the objective of decommissioning is to prevent surface water from reaching the water table through the well bore or along the outside of the well casing. When confined saturated conditions exist, well-borehole sealing operations must also restrict groundwater to the saturated zone in which it

occurs (Driscoll 1986). Only unconfined saturated conditions are known to exist at WAG 6 (Bechtel National, Inc. et al. 1991).

At WAG 6 most of the groundwater movement occurs in the upper 50 to 100 feet of the saturated zone, and a preponderance of evidence indicates that active groundwater flow is limited to the upper 150 feet. Below that depth, most fractures in the rock are closed (Bechtel National, Inc. et al. 1991). For much of the site, the regolith consists of an average depth of 25 feet of saprolite, which overlies interstratified carbonate and siltstone bedrock strata. Groundwater flow in the saprolite is through primary porosity induced by the weathering process, and also through secondary porosity resulting from relict structural fractures and joints. In the underlying bedrock, groundwater movement occurs only through pathways provided by fractures and joints existing in an otherwise essentially impermeable rock mass. In the bedrock, secondary porosity (and therefore permeability) decreases with increasing depth. From field tests conducted in the saprolite at WAG 6, the geometric mean hydraulic conductivity was found to be 2.0×10^{-4} cm/sec, while tests in the bedrock indicate a geometric mean hydraulic conductivity of 3.1×10^{-5} cm/sec. Using an effective porosity of 0.03 for both the regolith and bedrock (Bechtel National, Inc. et al. 1991), as derived from field testing, an average groundwater linear velocity in the regolith has been estimated to be 0.33 m/day (120 m/year). An average linear velocity for the shallow bedrock has been estimated to be 0.15 m/day (55 m/year), or less than half that of the regolith (Bechtel National, Inc. et al. 1991).

4.2.2 Existing Well Design

At WAG 6, completed well installations vary according to the subsurface material, groundwater conditions, and the intended use of the well. Wells were designed with screened or perforated intakes in unconsolidated strata. In consolidated strata many of the wells to be decommissioned were completed as open-hole installations below the firm (nonweathered) bedrock, with the cased portion terminating at the top of, or within, firm bedrock. Others were completed with screened sections and filter packs, similar to wells installed in unconsolidated strata. All WAG 6 wells that are to be decommissioned are believed to have been installed as single-cased wells.

4.2.2.1 Single-cased wells

Wells installed in unconsolidated deposits (soils) were usually single-cased wells with the well screen placed at the water table or at a specific point below the water table. A typical design of this type of well consists of a casing and a slotted screen surrounded by a sand-filter pack. The filter pack is isolated from above by a bentonite seal, and the annulus between the well casings and the borehole wall is grouted to the ground surface. The newer water-quality wells, those constructed since 1986, all had the annulus between the borehole wall and well casing grouted at the time of construction. This annulus may or may not have been grouted on older wells installed for various objectives, and was not grouted on the newer wells located within the burial trenches for research purposes. Well casing diameters range from 1 to approximately 7 inches, and consist of PVC, stainless steel, mild steel, or galvanized corrugated steel. Many of the older shallow well installations consist of 6 5/8-inch diameter perforated, corrugated steel casing with no filter pack or grout seal. Other deeper wells into bedrock were completed as open-hole wells in the bedrock portion of the well, with the casing being installed only through the unconsolidated strata penetrated by the well.

4.2.2.2 Multicased wells

The wells installed at WAG 6 to monitor hydraulic heads are all multicased, open-hole (no well screens installed) wells completed in bedrock. However, none of these wells will be decommissioned. They are all adequately designed and constructed, and pose little risk of providing pathways for contaminant migration. Piezometric data on the bedrock saturated zones obtained from these nested wells will continue to be important in postclosure surveillance.

4.2.3 Level of Contamination

Most of the wells to be abandoned at WAG 6 have the potential for some level of contamination. The "in-place" well decommissioning procedures to be implemented minimize the risk of cross-contamination within a well and the amount of field-generated contaminated material. The level and type of contamination in a well will require commensurate personnel health and safety practices, and equipment decontamination procedures between wells.

4.3 WELL ABANDONMENT TECHNIQUE

The best option for closing heavily contaminated wells that are no longer needed is decommissioning in place (Renz 1989). This is particularly true for sites such as WAG 6, where closure is proposed with all radioactive and mixed waste left in place. Methods that involve removal of well casings and screens from wells in contact with hazardous waste would not only displace contaminated groundwater, but other materials, such as drilling fluid, and drilled out casing and cement seals. At WAG 6, this process could create both a health and safety problem to field personnel and a disposal problem, because capacity for consolidation of wastes within the closure area is limited.

Although contingency procedures are provided in Appendix D for complete removal of the well casing, it is planned that wells in WAG 6 will be decommissioned with essentially all subsurface well materials left in place, except for removal of near surface casings to depths of 3 feet or less. Specific procedures will vary depending on subsurface materials penetrated by the well, the depth of the well, and the confidence in the well seal and grout in the existing well. Well diameter and casing material will affect the equipment used in the processes.

4.4 WELL PLUGGING MATERIALS

Five types of materials will be used for plugging wells, including coarse-granular bentonite, crushed stone or gravel, Type 1 cement grout, Type 1 cement/bentonite grout, and microfine-cement grout.

4.4.1 Coarse-Granular Bentonite

Coarse-granular (chips) bentonite will be used to plug wells in the waste burial trenches. These bentonite chips, available from producers in 3/8- and 3/4-inch nominal sizes, will be poured slowly into the well bore from the ground surface. When poured slowly, they will

settle through water found in some the trench wells, and will pack to a density such that subsidence of the bentonite within the well casing should not be a problem. This material will not adversely affect any remedial action alternatives presently under consideration for the trenches.

4.4.2 Crushed Stone or Gravel

Crushed stone or gravel (3/4-inch maximum size) will be used for backfilling wells in the French drain, as crushed stone is the material used in the construction of this structure. Wells will be filled with stone to the top of the drain, which is approximately 2 feet below the ground surface. (The French drain will be sealed by the construction of an approved cap during WAG 6 closure.)

4.4.3 Type 1 Cement Grout

Type 1 cement grout will consist only of Type 1 portland cement and water. It will be used in the upper three feet of the wells in the waste burial trenches.

4.4.4 Type 1 Cement/Bentonite Grout

Type 1 cement/bentonite grout with 4% (by weight) powdered bentonite will be used in all wells in which records document that the well casing/borehole annulus was properly sealed during installation that have screens 10 feet or less in length, and in the open-hole sections of some bedrock wells.

4.4.5 Microfine-Cement Grout

Microfine-cement grout has the ability to infiltrate finer openings and materials than does grout made with Type 1 cement, and its use will give greater assurance that decommissioning grouting is effectively penetrating to the voids in materials outside the casing through slits or perforations, and to the filter packs of the longer length screens. (The microfine cement should be similar or equal to MC-500 microfine cement distributed by Geochemical Corporation, Ridgewood, NJ.) Microfine-cement grout will be used in well installations in which the well casing/borehole annulus is not documented as having been properly sealed during installation, and in which the well casing is more than 10 feet in length. In these wells, the casing will be split or perforated. Also, microfine-cement grout will be used in wells which, although they were properly grouted at the time of installation, have screens greater than 10 feet in length.

4.5 P&A METHODS FOR ALL WELL TYPES

The decommissioning of wells in WAG 6 will be accomplished by grouting or plugging with the casings left in place. Where encountered, obstructions in the well will be removed (where necessary) so that grouting or plugging can proceed. Obstruction removal will be accomplished by redrilling or percussion methods inside of existing well casings and screens with nominal diameters that range from approximately 1 to 7 inches. The P&A methods that will be applied to specific groups of wells are described below, and specific procedures for each group are provided in Appendix D.

4.5.1 Waste Trench Wells

Wells within the waste burial trenches will be plugged with coarse-granular bentonite (for example, "Holeplug[™]" a product produced by Baroid Drilling Fluids, Inc.). Such products require a longer time to hydrate and swell than do bentonite pellets, and can be placed at a rate so that they will fall through the depths of water existing in the WAG 6 wells without bridging and blocking the well. Considering the quantities of water anticipated in any of these wells, placement of coarse-granular bentonite should not displace well water upward to the ground surface; thereby avoiding the necessity of containment and disposal of contaminated well water. The coarse-granular bentonite will be placed to fill the well to a level 3.5 feet below the ground surface, followed by the addition of powdered bentonite to a level 3.0 feet below the ground surface. Type 1 cement grout will then be added to bring the plug to a level 1.0 feet below the ground surface. (The powdered bentonite will prevent the infiltration and loss of the cement grout through the interstices of the non-hydrated, coarse-granular bentonite.) After 24 hours, the upper part of the casing will be removed to a depth of 1.0 feet below the ground surface. The casing will be removed only to a depth of 1 foot in order to guard against the removal of potentially contaminated material, as the trenches are reportedly covered with approximately 2 feet of non-contaminated soil. The excavation for the casing removal will be backfilled with excavated soil and properly tamped. All of the plugging materials will be placed in the well from the ground surface as the well depths will not exceed 20 feet or so.

4.5.2 French Drain Wells

Wells in the French drain will be plugged with crushed stone or gravel (3/4-inch maximum size) to a level 2.0 feet below the ground surface. This is the approximate depth of the top of the French drain which is constructed with crushed stone. At this depth, the PVC well pipe will be cut, and the excavation will be backfilled with excavated soil and properly tamped. There is little potential for contamination in this 2-foot excavation. The stone will be placed in the well by the free fall method from the ground surface.

4.5.3 Wells in Unconsolidated Strata

Wells that are installed in unconsolidated strata (that do not penetrate bedrock), and are not within the waste burial trenches or French drain, will be grouted with a particulate (cement/bentonite or microfine cement) grout. Unless records document that a well's casing/borehole annulus was properly grouted during installation, well casings more than 10 feet in length will be perforated or slit from a depth of 10 feet below the ground surface to the top of the well screen in order to provide pathways for the grout to seal possible voids in the casing/borehole annulus. Grout will be pumped through a tremie pipe initially lowered to the bottom of the well, and pumping will continue until undiluted grout flows from the top of the well. Therefore, well water and diluted grout will be displaced to the surface and will have to be contained and disposed of properly. Microfine-cement grout will be used in all wells in which the casing is slit or perforated, and also in the wells where the screened sections are longer than 10 feet. Type 1 cement/bentonite grout will be used in wells in unconsolidated material that do not meet the foregoing criteria for being grouted with microfine-cement grout. After grouting, the casing will be removed to a depth of 3 feet below the ground. The excavation will be backfilled with the excavated soil and properly tamped.

4.5.4 Non-Screened Bedrock Wells

Wells penetrating firm bedrock with an open-hole interval rather than a well screen, may be plugged with two types of grout. Unless records document that a well's casing/borehole annulus was properly grouted during installation, wells with casings more than 10 feet in length will be perforated or slit from a depth of 10 feet below the ground surface to the bottom of the casing in order to provide pathways for the grout to seal possible voids in the casing/borehole annulus. It is not the purpose of decommissioning grouting to grout the natural fractures or openings in the rock at any distance away from the borehole; therefore, if a well's casing is split or perforated for the use of microfine-cement grout, two types of grout mixes may be used; Type 1 cement/bentonite grout will be placed in the exposed bedrock portion, and the more penetrating microfine-cement grout will be placed in the cased portion. If the casing is not slit or perforated, only Type 1 cement/bentonite grout will be used in the well, and it will be placed by tremie pipe initially lowered to the bottom of the well. Grout will be pumped through the tremie pipe until undiluted grout flows from the top of the well, causing well water and diluted grout to be displaced to the surface, which will have to be contained and disposed of properly. However, in wells where casings have to be slit or perforated and microfine cement is required in the cased portion, it will be pumped through a tremie pipe lowered to the top of the firm Type 1 cement/bentonite grout, in a second operation, following a 24 hour minimum waiting period to allow the Type 1 cement/bentonite grout to set. After grouting, the casing will be removed to a depth of 3 feet below the ground. The excavation will be backfilled with the excavated soil and properly tamped.

4.5.5 Screened Bedrock Wells

Bedrock wells that were completed with well screens will be decommissioned using the same procedures as for cased and screened wells in unconsolidated material.

REFERENCES

- Aller, Linda, T. W. Bennett, G. Hackett, R. J. Petty, J. H. Lehr, D. M. Nielsen, and J. E. Denne. 1989. *Handbook of Suggested Practices for the Design and Installation of Ground-Water Monitoring Wells*. National Water Well Association, Dublin Ohio.
- Bechtel National, Inc./CH2M Hill/ERCE/PEER. 1991. *RCRA Facility Investigation Report for Waste Area Grouping 6 at Oak Ridge National Laboratory, Oak Ridge, Tennessee, Volume 1, ER/ES-22/V1&D1, ORNL/ER/Sub-87/99053/5/V1*. Oak Ridge National Laboratory, Oak Ridge, Tenn.
- Driscoll, F. G. 1986. *Ground Water and Wells*, Johnson Division, St. Paul, Minnesota.
- Renz, M. 1989. "In Situ Decommissioning of Ground Water Monitoring Wells," *Water Well Journal, May*, National Water Well Association, Dublin, Ohio.
- U. S. Environmental Protection Agency. 1975. *Manual of Water Well Construction Practices*. EPA-570/9-75-001, Office of Water Supply.

APPENDIX A
INVENTORY OF RECORDED WELLS AT WAG 6

APPENDIX A. INVENTORY OF RECORDED WELLS AT WAG 6

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u> <u>(in)</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>				
0+54	16527.25	24474.94	6.1	3.00	PVC	
0033	17356.94	25060.42				
0051	15987.20	23972.30	161.0	3.29	STEEL	Destroyed
0059	16720.00	23998.00				Destroyed
0060	16686.00	23914.00				Destroyed
0061	16715.00	23903.00				Destroyed
0090	16782.00	25473.00	5.88		STEEL	
0091	16860.00	25480.00	6.00		STEEL	
0107	17041.00	24402.00	122.3	5.50	STEEL	Not Found
0108	17279.00	24584.00	126.3	5.50	STEEL	
0109	17330.00	24499.00	126.1	5.50	STEEL	
0110	17204.00	24684.00	125.0	5.50	STEEL	Not Found
0111	17502.00	24778.00				Destroyed
0123	17234.00	24644.00				Destroyed
0176CK	17353.69	25178.92				
0182CK	17345.69	25163.19				
0266	15968.00	23327.00	16.6	6.63	STEEL	Not Found
0267	16118.00	23221.00	17.2	6.63	STEEL	Not Found
0268	16365.00	23307.00	20.1	6.63	STEEL	Not Found
0269	16511.00	23104.00	20.0	6.63	STEEL	
0270	16602.00	23303.00	20.7	6.63	STEEL	Not Found
0271	16581.00	23472.00	20.6	6.63	STEEL	Not Found
0272	16221.00	23520.00	8.4	6.63	STEEL	Not Found
0273	16126.00	23633.00	10.8	6.63	STEEL	Not Found
0274	16210.00	23347.00	18.7	6.63	STEEL	Not Found
0275	16206.00	23737.00	8.5	6.63	STEEL	Not Found
0276	16211.00	23895.00	5.6	6.63	STEEL	
0277	16207.00	24182.00	20.8	6.63	STEEL	Not Found
0278	16552.00	24223.00	10.6	6.63	STEEL	Not Found
0279	16696.00	24205.00	10.4	6.63	STEEL	
0280	16640.00	23997.00	18.4	6.63	STEEL	Not Found
0281	16720.00	23998.00	46.7	3.00	STEEL	Not Found
0282	16725.00	24008.00	18.6	6.63	STEEL	Not Found
0283	16729.00	23989.00	18.4	6.63	STEEL	Not Found
0284	16750.00	23983.00	16.8	6.63	STEEL	Not Found
0285	16761.00	23962.00	13.9	6.63	STEEL	Not Found
0286	16767.00	23945.00	13.2	6.63	STEEL	Not Found
0287	16765.00	23927.00	14.6	6.63	STEEL	Not Found
0288	16752.00	23914.00	14.2	6.63	STEEL	Not Found
0289	16765.00	23896.00	15.7	6.63	STEEL	Not Found
0290	16735.00	23907.00	16.7	6.63	STEEL	Not Found
0291	16738.00	23878.00	14.9	6.63	STEEL	Not Found
0292	16773.00	23821.00	13.4	6.63	STEEL	Not Found

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
0293	16718.00	23910.00	17.9	6.63	STEEL	Not Found
0294	16722.00	23921.00	17.9	6.63	STEEL	Not Found
0295	16703.00	23992.00	15.3	6.63	STEEL	Not Found
0296	16967.00	23958.00	18.7	6.63	STEEL	Not Found
0297	16685.00	23847.00				Destroyed
0298	16716.00	23899.00	16.7	6.63	STEEL	Not Found
0299	16705.00	23883.00	18.0	6.63	STEEL	Not Found
0300	16702.00	23868.00	15.5	6.63	STEEL	Not Found
0301A	16687.00	23847.00	9.7	6.63	STEEL	Not Found
0302A	16679.00	23734.00	7.4	6.63	STEEL	Not Found
0303A	16689.00	23782.00	2.6	6.63	STEEL	Not Found
0304	16667.00	23937.00	15.6	6.63	STEEL	Not Found
0305	16660.00	23914.00	13.6	6.63	STEEL	
0306	16679.00	23905.00	17.4	6.63	STEEL	Not Found
0307	16694.00	23897.00	16.2	6.63	STEEL	Not Found
0308	16691.00	23873.00	12.9	6.63	STEEL	Not Found
0309	16716.00	23903.00	26.1	6.63	STEEL	Destroyed
0310	16697.00	23939.00	12.2	6.63	STEEL	Not Found
0311	16936.00	23900.00	18.8	6.63	STEEL	Not Found
0312	16922.00	23529.00	19.2	6.63	STEEL	Not Found
0313	16798.00	23605.00	20.5	6.63	STEEL	Not Found
0314	15983.00	23977.00				Destroyed
0315	15977.00	24188.00	26.6	6.63	STEEL	Not Found
0316	16626.00	24362.00				Destroyed
0317	16766.00	24328.00	13.9	6.63	STEEL	
0318	17225.00	24323.00	14.9	6.63	STEEL	
0319	17625.00	24529.00				Destroyed
0332	17781.00	24634.00				Destroyed
0333	17886.00	24625.00				Destroyed
0334	17715.00	24737.00				Destroyed
0335	17589.00	24965.00				Destroyed
0336	17595.00	25092.00				Destroyed
0337	17717.00	25096.00	10.4	6.63	STEEL	Not Found
0338	17305.00	25158.00	17.1	6.63	STEEL	Not Found
0339	17481.00	25316.00				Destroyed
0340	17130.00	25160.00				Destroyed
0341	16837.00	25165.00	19.7	6.63	STEEL	Not Found
0342	16562.00	25154.00	15.2	6.63	STEEL	Not Found
0343	16763.00	25010.00	23.9	6.63		
0344	16495.00	24810.00	9.1	6.63	STEEL	Not Found
0345	16361.00	24881.00	10.9	6.63	STEEL	Not Found
0346	16435.00	24631.00	16.8	6.63	STEEL	Not Found
0347	16531.00	24604.00	16.4	6.63		
0350	16152.00	24649.00	17.4	6.63	STEEL	Not Found
0351	16028.00	24661.00	24.4	6.63	STEEL	Not Found
0352	15887.00	24305.00	21.0	6.63	STEEL	Not Found

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u> <u>(in)</u>		<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>					
0353	15695.00	24014.00					Destroyed
0354	17234.00	24644.00					Destroyed
0355	16909.00	24991.00	19.3	6.63	STEEL		Not Found
0356	16481.00	24451.00	9.0	6.63	STEEL		
0357	16747.00	24599.00	13.0	6.63	STEEL		Not Found
0358	16090.00	24448.00	18.4	6.63	STEEL		Not Found
0359	16904.00	24867.00	18.7	6.63	STEEL		Not Found
0360	17148.00	24968.00	17.6	6.63	STEEL		Not Found
0361	16446.00	24166.00	8.0	6.63	STEEL		Not Found
0362	16588.00	23718.00	7.8	6.63	STEEL		
0363	16420.00	23748.00	3.6	6.63	STEEL		
0364	16407.00	23838.00	7.7	6.63	STEEL		
0365	16454.00	23681.00	5.6	6.63	STEEL		
0366	17467.00	24926.00	23.0	6.63	STEEL		Not Found
0367	17723.00	25091.00	68.8	3.00	PVC		
0368	17348.00	25155.00	39.4	3.00	PVC		
0369	17476.00	24805.00	48.1	3.00	PVC		Not Found
0370	17145.00	24981.00	34.1	3.00	PVC		
0371	16393.00	25090.00	29.8	3.00	PVC		
0372	16570.00	25042.00	33.1	3.00	PVC		Not Found
0373	16945.00	25208.00	33.9	3.00	PVC		Not Found
0374	17462.00	25346.00	30.9	3.00	PVC		
0375	16935.00	23531.00	26.3	3.00	PVC		
0376	16584.00	23479.00	34.7	3.00	PVC		
0377	16610.00	23297.00	55.8	3.00	PVC		
0378	16474.00	23092.00	60.2	3.00	PVC		
0379	16156.00	23206.00	36.6	3.00	PVC		Not Found
0380	15977.00	23320.00	31.3	3.00	PVC		
0381	16248.00	24266.00	35.3	3.00	PVC		
0382	15814.00	24025.00	21.0	3.00	PVC		
0383	16165.00	24895.00	33.2	3.00	PVC		
0384	16131.00	24377.00	46.2	3.00	PVC		Not Found
0385	17903.00	24669.00	44.8	3.00	PVC		
0386	16892.00	24828.00	12.0	3.00	PVC		Not Found
0387	16986.00	24886.00	10.6	3.00	PVC		Not Found
0388	17111.00	24886.00	11.5	3.00	PVC		Not Found
0389	16798.40	24203.49	14.9	3.00	PVC		
0390	16841.59	24199.67	15.1	3.00	PVC		
0391	16899.81	24192.39	10.0				
0392	16974.25	24317.28	20.4	4.00	PVC		
0393	16953.14	24259.03	24.3	4.00	PVC		
0394	17010.56	24420.05	27.6	4.00	PVC		
0395	16896.17	24235.26	23.5	2.00	PVC		
0396	16894.54	24245.22	22.8	2.00	PVC		
0397	16925.31	24227.29	20.8	2.00	PVC		
0398	16939.44	24427.38	28.1	4.00	PVC		

WELL	COORDINATES		DEPTH (ft)	CASING DIAMETER		CASING MATERIAL	STATUS
	NORTH	EAST		(in)			
0399	16881.25	24349.51	28.6				
0400	17065.08	24304.61	23.8	4.00		PVC	
0401	17022.31	24380.21	28.9	3.00		PVC	
0402	16816.65	24277.51	18.4	4.00		PVC	
0403	16777.67	24163.08	12.7	3.00		PVC	
0403A	16789.60	24181.66	5.8	2.00		PVC	
0404	16786.33	24159.05	10.1	3.00		PVC	
0404A	16800.43	24180.46	5.9	2.00		PVC	
0405	16791.79	24157.98	13.3	3.00		PVC	
0405A	16810.86	24178.24	8.9	2.00		PVC	
0636	17668.04	24326.17	54.0	2.00		PVC	
0637	17715.14	24135.97	66.0	2.00		PVC	
0638	17495.05	24119.35	70.0	2.00		PVC	
0639	17395.38	24138.11	63.5	2.00		PVC	
0640	17614.70	24719.55	60.0	2.00		PVC	Not Found
0641	17383.49	23985.24	60.0	2.00		PVC	
0642	16580.96	24035.55	30.0	2.00		PVC	
0643	16344.38	24204.78	21.5	2.00		PVC	Not Found
0644	16748.86	24848.36	17.0	2.00		PVC	Not Found
0645	17173.65	25274.60	25.0	2.00		PVC	
0646	17550.78	25167.05	39.0	2.00		PVC	
0647	17145.66	24749.00	36.0	2.00		PVC	
0648	17374.55	24524.24	45.0	4.00		PVC	
0649	17375.49	25075.50	37.0	2.00		PVC	
0650A	17273.53	25150.16	60.0	2.00		STL STEEL	
0650B	17273.53	25150.16	60.0	2.00		STL STEEL	
0651	16870.85	25190.67	110.0	2.00		PVC	
0652	16159.68	24900.00	90.0	2.00		PVC	
0653	15792.51	24070.40	63.0	2.00		PVC	
0654	16618.16	24054.76	90.0	2.00		PVC	
0655	17469.72	24815.30	125.0	2.00		PVC	
0656	17923.92	24692.96	120.0	2.00		PVC	
0739	15628.89	23604.03	33.0				
0740	15778.95	23372.39	24.0				
0741	15596.74	23352.05	22.0				
0745	16067.80	23808.30	60.2	4.00		STL STEEL	
0831	17387.40	24133.50	50.7	4.00		STL STEEL	
0832	17385.60	24096.70	85.9	4.00		STL STEEL	
0833	16056.90	23842.40	31.0	2.00		STL STEEL	
0835	15767.70	23951.80	27.5	2.00		STL STEEL	
0836	15748.20	24138.80	28.5	2.00		STL STEEL	
0837	15845.60	24352.60	31.6	2.00		STL STEEL	
0838	16308.70	24934.80	22.8	2.00		STL STEEL	
0839	16308.80	24923.60	56.0	4.00		STL STEEL	
0840	16928.60	25251.70	26.9	2.00		STL STEEL	
0841	17206.30	25294.80	56.5	4.00		STL STEEL	

WELL	COORDINATES		DEPTH (ft)	CASING DIAMETER	CASING MATERIAL	STATUS
	NORTH	EAST		(in)		
0842	17216.10	25298.40	26.8	2.00	STL.STEEL	Destroyed
0843	17597.10	25221.40	21.0	2.00	STL.STEEL	
0844	17602.50	25228.60	52.0	4.00	STL.STEEL	
0845	17108.20	24988.30	41.0	2.00	STL.STEEL	
0846	18030.70	24803.50	81.0	4.00	STL.STEEL	
0847	17769.90	24790.50	67.0	2.00	STL.STEEL	
0848	16942.40	24656.30	32.0	2.00	STL.STEEL	
0849	16781.80	24215.20	32.9	2.00	STL.STEEL	
0850	16595.40	24793.50	22.7	2.00	STL.STEEL	
0851	16485.00	24058.20	21.6	2.00	STL.STEEL	
0852	16346.90	23911.60	25.3	2.00	STL.STEEL	
0853	16695.10	24047.50	27.7	2.00	STL.STEEL	
0854	16711.90	23851.90	27.5	2.00	STL.STEEL	
0855	16755.30	23427.70	52.0	2.00	STL.STEEL	
0856	16764.40	23432.90	82.0	4.00	STL.STEEL	
0857	16538.00	23106.30	70.0	2.00	STL.STEEL	
0858	16542.10	23115.80	106.4	4.00	STL.STEEL	
0859	16009.40	23246.20	26.5	2.00	STL.STEEL	
0860	15999.50	23252.90	61.8	4.00	STL.STEEL	
0936	16144.55	24609.77	400.4	6.63	STEEL	
0937	16148.20	24688.37	215.3	6.63	STEEL	
0938	16170.59	24676.08	61.5	6.63	STEEL	
0939	15814.83	24525.34	400.4	6.63	STEEL	
0940	15827.63	24595.29	215.0	6.63	STEEL	
0941	15833.46	24561.12	63.0	6.63	STEEL	
0945	17540.65	24512.09	402.5	6.63	STEEL	
0999	17518.90	24509.40	295.0	4.50	STEEL	
1+33	16608.03	24469.71	12.2	3.00	PVC	
1+53	16625.30	24469.22	14.1	3.00	PVC	
1+85	16656.08	24467.64	15.7	3.00	PVC	
1000	17498.37	24506.56	178.0	4.50	STEEL	
1001	16862.02	24694.84	400.0	4.50	STEEL	
1002	16810.70	24697.05	197.0	4.50	STEEL	
1003	16782.51	24668.21	79.0	4.50	STEEL	
1035	16417.57	24174.87	15.5	3.00	PVC	
1036	16328.57	24231.08	26.7	3.00	PVC	
1037	16228.14	24175.72	26.2	3.00	PVC	
1038	16251.36	24096.88	15.9	3.00	PVC	
1039	16313.32	24093.26	17.6	3.00	PVC	
1040	16376.13	24103.13	17.4	3.00	PVC	
11-1	16619.80	24013.80	9.1	1.00	PVC	
1157	17806.99	25192.38	61.0	3.00	PVC	
1158	17816.12	25102.46	62.1	3.00	PVC	
1159	17752.28	25062.08	63.1	3.00	PVC	
1160	17654.24	25002.46	57.6	3.00	PVC	
1161	17549.76	24928.23	62.2	3.00	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
1162	17608.96	25086.38	61.8	3.00	PVC	
1163	17689.47	25141.24	64.1	3.00	PVC	
1164	17814.50	24993.14	38.3	3.00	PVC	
1165	17879.49	25041.75	39.1	3.00	PVC	
1166	17697.15	24945.94	36.8	3.00	PVC	
1167	17709.84	25256.02	47.9	3.00	PVC	
1168	17645.69	25295.15	28.9	3.00	PVC	
1169	17895.08	25151.41	37.9	3.00	PVC	
1225	17754.77	24603.65	24.0			
1226	17043.45	23763.29	15.0			
1227	16569.39	23838.21	8.0			
1228	16334.67	23878.80	8.0			
1229	16453.32	24072.69	8.0			
123	16975.26	24307.36		4.00	PVC	
1230	16204.70	24606.50	14.0			
1231	16403.79	24659.86	12.2			
1232	17020.14	24218.89	9.0			
1233	17005.25	24211.90	23.7			
1234	16956.93	25249.05	147.0			
1235	16193.30	24618.50	27.2			
1236	16195.25	23195.49	160.0			
1237	17089.07	23868.74	56.8			
1238	17079.00	23862.43	151.5			
1240	18066.23	25183.89	23.6			
1241	17913.59	25097.59	36.2			
1242	17367.94	25344.78	27.3			
1243	17085.60	25239.04	27.9			
1244	17155.45	25459.01	24.2	2.00	STL STEEL	
1245	16894.94	25429.95	58.1			
1249	16969.58	25244.09	70.0			
1254	16434.11	24112.78	17.5	3.00	PVC	
1255	16479.30	24116.72	14.7	3.00	PVC	
1256	16527.31	24178.87	16.9	3.00	PVC	
1257	16493.30	24251.15	23.1	3.00	PVC	
1258	16409.12	24248.12	25.0	3.00	PVC	
1259	16389.22	24173.59	15.0	3.00	PVC	
126SS	17681.14	25056.18	15.0	2.00	STL STEEL	
127	16918.44	24269.15		3.00	PVC	
129	16975.85	24325.35		4.00	PVC	
13-1	16624.50	24006.20	10.1	1.00	PVC	
13-2	16618.00	23999.70	9.4	1.00	PVC	
13-3	16605.00	23995.90	9.7	1.00	PVC	
13-4	16602.40	24000.60	10.0	1.00	PVC	
13-5	16596.90	23998.00	9.7	2.00	PVC	
13-6	16621.50	24005.00	10.3	1.00	PVC	
131	16904.33	24283.73		3.00	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
135	16916.17	24306.07		3.00	PVC	
137	16960.33	24339.20		4.00	PVC	
139	16900.62	24322.38		3.00	PVC	
13N	16629.60	24007.80	8.3	1.00	PVC	
13NE	16616.20	24004.60	8.0	1.00	PVC	
13NW	16616.20	24008.50	8.4	1.00	PVC	
13S	16591.90	23996.20	8.0	1.00	PVC	
13SE	16602.40	24004.90	6.7	1.00	PVC	
13SW	16610.20	24002.80	9.7	1.00	PVC	
142SS	17675.75	25042.68	15.0	2.50	STL STEEL	
148SS	17634.68	25088.20	15.0	2.00	STL STEEL	
151SS	17637.12	25066.71	15.0	2.00	STL STEEL	
153	16827.49	24298.13		4.00	PVC	
155SS	17561.46	25023.05	15.0	2.00	STL STEEL	
159-6	17670.50	25015.64		6.00	STEEL	
159SS	17639.99	25056.49	15.0	2.00	STL STEEL	
16-1	16626.80	23996.20	7.6			
160	16959.73	24351.82		4.00	PVC	
165-1	17662.50	25012.42	15.0	1.25	PVC	
165-11B	17644.64	25033.48	15.0	1.25	PVC	
165-13B	17640.48	25037.59	15.0	1.50	PVC	
165-1A	17642.85	25038.17	15.0			Not Found
165-2	17658.10	25017.88	15.0	1.25	PVC	
165-2A	17647.13	25030.96	15.0	1.00	PVC	
165-2B	17663.22	25015.78	15.0	1.25	PVC	
165-3	17654.44	25022.45	15.0	1.50	PVC	
165-3A	17653.93	25021.95	15.0	1.00	PVC	
165-3B	17661.79	25017.00	15.0	1.50	PVC	
165-4	17647.73	25030.82	15.0	1.50	PVC	
165-4A	17657.15	25017.44	15.0			Not Found
165-5	17642.93	25037.90	15.0	1.50	PVC	
165-5A	17661.44	25012.64	15.0			Not Found
165-5B	17657.35	25020.87	15.0	1.25	PVC	
165-6	17659.28	25009.24	15.0	1.00	PVC	
165-7B	17654.79	25023.89	15.0	1.50	PVC	
165-8B	17651.07	25026.62	15.0	1.50	PVC	
165-9B	17649.24	25028.87	15.0	1.25	PVC	
165-X	17658.36	25017.87	15.0	1.50	PVC	
165-Y	17641.17	25037.11	15.0	1.00		
165N	17667.44	25007.12	15.0	1.00	PVC	
165NE	17661.58	25023.30	15.0	1.25	PVC	
165NW	17651.49	25016.39	15.0	1.25	PVC	
165S	17638.67	25043.39	15.0	1.25	PVC	
165SE	17649.16	25039.31	15.0	1.25	PVC	
165SS	17650.76	25028.68	15.0	2.50	STL STEEL	
165SW	17639.90	25029.61	15.0	1.25	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
166	17019.05	24385.85		4.00	PVC	
173	16834.27	24352.23		4.00	PVC	
175	17011.52	24405.85		4.00	PVC	
177	16932.88	24382.37		4.00	PVC	
178SS	17556.97	24990.72	15.0	2.00	STL STEEL	
181	16893.61	24379.90		4.00	PVC	
183	16833.51	24366.31		4.00	PVC	
187	16861.92	24391.90		4.00	PVC	
189	16825.56	24382.82		4.00	PVC	
192SS	17620.13	25001.88	15.0	2.00	STL STEEL	
199SS	17595.10	24977.22	15.0	2.00	STL STEEL	
2+02	16674.21	24467.88	16.7	3.00	PVC	
2+26	16695.99	24467.03	17.3	3.00	PVC	
2+51	16724.09	24464.48	18.7	3.00	PVC	
2-1	17817.08	25121.63	15.0	2.00	PVC	
2-1B	17808.68	25125.25	15.0	1.00	PVC	
2-2	17804.34	25133.02	15.0	2.00	PVC	
2-3	17791.59	25146.03	15.0	2.00	PVC	
2-4	17776.31	25160.67	15.0			Not Found
2-5	17762.29	25175.31	15.0	2.00	PVC	
201	16817.55	24423.83		4.00	PVC	
203	16773.11	24007.84		3.00	PVC	
215	16890.20	23991.92		3.00	PVC	
218	16774.40	23998.59		3.00	PVC	
220	16832.90	23984.74		3.00	PVC	
224	16896.54	23971.80		3.00	PVC	
226	16809.03	23974.12		3.00	PVC	
230	16871.99	23956.55		3.00	PVC	
233	16802.50	23959.59		3.00	PVC	
235	16873.33	23937.11		3.00	PVC	
238	16792.25	23941.12		3.00	PVC	
239	16853.58	23922.04		3.00	PVC	
242	16785.64	23927.28		3.00	PVC	
243	16841.91	23906.81		3.00	PVC	
246	16784.47	23916.13		3.00	PVC	
248	16838.90	23892.94		3.00	PVC	
250	16775.50	23897.23		4.00	PVC	
252-1	16470.60	23939.30	10.1	1.00	PVC	
253	16763.43	23888.01		3.00	PVC	
255	16839.49	23873.13		3.00	PVC	
257	16822.65	23860.81		3.00	PVC	
258	16743.65	23877.06		3.00	PVC	
261	17055.64	23995.98		4.00	PVC	
265	17036.62	23997.02		4.00	PVC	
269	17021.44	24000.25		4.00	PVC	
274	17010.50	23938.50		4.00	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
275-1	16446.20	23970.20	7.1	1.00	PVC	
277	16954.00	23782.49		4.00	PVC	
278	17009.88	23917.00		4.00	PVC	
279	16701.65	24206.62		6.00	STEEL	
279-1	16490.10	23962.60	8.4	1.00	PVC	
279-2	16484.40	23962.40	9.6	1.00	PVC	
279-3	16471.90	23961.80	8.4	1.00	PVC	
279-4	16460.50	23961.40	7.7	1.00	PVC	
279-5	16448.60	23961.10	7.0	1.00	PVC	
279-6	16450.60	23962.40	14.3	1.00	PVC	
279-N	16497.10	23962.80	9.4	1.00	PVC	
279-NE	16478.20	23968.50	9.6	1.00	PVC	
279-NW	16478.20	23955.70	10.2	1.00	PVC	
279-S	16443.10	23960.70	11.6	1.00	PVC	
279-SE	16460.90	23967.30	10.1	1.00	PVC	
279-SW	16461.70	23955.50	8.4	1.00	PVC	
282	16962.83	23802.13		4.00	PVC	
284	16755.45	23985.04		6.00	STEEL	
284-1	16448.40	23951.10	7.0	1.00	PVC	
285-1(S)	16500.70	23950.20	6.6	1.50	PVC	
286	17003.20	23905.12		4.00	PVC	
288-1	16533.50	23937.50	11.7	1.50	PVC	
288-2	16523.60	23938.90	12.3	1.50	PVC	
288-3	16515.00	23940.10	9.6	1.50	PVC	
288-4	16506.90	23941.10	10.7	1.50	PVC	
288-5	16496.50	23942.70	7.6	1.00	PVC	
288-6	16498.10	23942.70	10.0	1.00	PVC	
288-N	16539.70	23936.30	9.8	1.50	PVC	
288-NE	16528.00	23942.50	7.7	1.50	PVC	
288-NW	16525.80	23934.00	7.5	1.50	PVC	
288-S	16491.20	23943.50	2.7	1.00	PVC	
288-SE	16508.20	23945.60	12.1	1.50	PVC	
288-SW	16507.00	23937.00	5.6	1.50	PVC	
290	16952.10	23822.48		4.00	PVC	
293	16960.68	23837.77		4.00	PVC	
3+03	16773.11	24458.03	20.3	3.00	PVC	
3+52	16818.25	24452.43	23.9	3.00	PVC	
3+76	16840.88	24449.03	23.3	3.00	PVC	
3-1	17806.88	25107.80	15.0	2.00	PVC	
3-2	17792.87	25119.19	15.0	1.25	PVC	
3-3	17778.85	25131.39	15.0	1.25	PVC	
3-4	17761.02	25146.03	15.0	1.25	PVC	
3-5	17748.28	25158.23	15.0	1.25	PVC	
304	16967.27	23857.00		4.00	PVC	
34	17002.27	24256.15		4.00	PVC	
36	16983.71	24272.78		4.00	STEEL	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
382	15814.00	24025.00		3.00	PVC	
39-1	16929.31	24244.18		4.00	PVC	
39-2	16948.11	24247.05		4.00	PVC	
39-3	16904.44	24237.47		3.50	PVC	
4+01	16870.56	24445.99	26.1	3.00	PVC	
4+27	16893.80	24443.19	25.4	3.00	PVC	
4+58	16922.75	24440.75	28.1	3.00	PVC	
4+77	16943.31	24437.96	29.6	3.00	PVC	
4-1	17787.77	25100.48	15.0	1.25	PVC	
4-2	17776.31	25110.24	15.0	1.25	PVC	
4-3	17763.56	25121.63	15.0	1.25	PVC	
4-4	17749.55	25133.83	15.0	1.25	PVC	
4-5	17738.08	25145.22	15.0	1.25	PVC	
41	16981.93	24291.23		4.00	PVC	
4S	17726.62	25154.16	15.0	1.25	PVC	
5+04	16969.46	24435.04	25.7	3.00	PVC	
5+27	16991.24	24431.87	27.5	3.00	PVC	
5+50	17013.87	24428.95	27.1	3.00	PVC	
5+77	17041.00	24424.94	27.4	3.00	PVC	
5-1	17778.32	25090.69	15.0	2.00	PVC	
5-2	17768.92	25099.73	15.0	1.25	PVC	
5-3	17754.83	25111.57	15.0	1.25	PVC	
5-4	17741.06	25122.03	15.0	1.25	PVC	
5-5	17723.04	25136.06	15.0	1.25	PVC	
5S	17714.19	25143.22	15.0	1.25	PVC	
6+16	17065.21	24411.92	27.2	3.00	PVC	
6-1	17714.85	25122.30	15.0	1.00	PVC	
6-2	17730.25	25112.12	15.0	1.00	PVC	
6-3	17743.36	25100.83	15.0	1.50	PVC	
6-4	17754.17	25091.20	15.0	1.00	PVC	
6-5	17766.62	25081.02	15.0	1.50	PVC	
6N	17772.33	25071.66	15.0	1.50	PVC	
6NE	17754.83	25100.01	15.0	1.25	PVC	
6NW	17744.40	25087.79	15.0	1.25	PVC	
6S	17708.30	25128.08	15.0	1.25	PVC	
6SE	17734.84	25117.62	15.0	1.25	PVC	
6SW	17724.68	25107.44	15.0	1.25	PVC	
7+81	17121.29	24258.15	16.5	3.00	PVC	
7-1	17737.40	25062.80	15.0			Not Found
7-10B	17710.77	25090.47	15.0	1.50	PVC	
7-11B	17706.13	25094.51	15.0	1.25	PVC	
7-12B	17701.90	25099.36	15.0	1.50	PVC	
7-13B	17699.87	25101.78	15.0	1.25	PVC	
7-14B	17698.03	25104.23	15.0	1.25	PVC	
7-15B	17696.60	25105.91	15.0	1.25	PVC	
7-1A	17729.45	25063.35	15.0	1.25	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
7-1B	17738.96	25064.06	15.0	1.25	PVC	Not Found
7-2A	17714.42	25087.78	15.0	1.00	PVC	
7-2B	17736.61	25066.54	15.0	1.50	PVC	
7-3	17713.02	25088.06	15.0			
7-3A	17704.65	25098.39	15.0	1.25	PVC	
7-3B	17734.94	25068.27	15.0	1.50	PVC	
7-4	17703.54	25097.61	15.0	1.50	PVC	
7-4A	17696.31	25108.21	15.0	1.25	PVC	
7-4B	17732.51	25070.39	15.0	1.50	PVC	
7-5	17694.87	25106.03	15.0	1.50	PVC	
7-5A	17727.78	25072.96	15.0	1.50	PVC	
7-5B	17728.48	25073.97	15.0	1.50	PVC	
7-6	17691.23	25107.81	15.0	6.00	STEEL	
7-6B	17725.78	25077.26	15.0	1.50	PVC	
7-7B	17722.13	25080.62	15.0	1.50	PVC	
7-8B	17718.26	25084.08	15.0	1.50	PVC	
7-9B	17714.74	25087.13	15.0	1.50	PVC	
7N	17746.34	25056.66	15.0	1.25	PVC	
7S	17689.18	25113.54	15.0	1.25	PVC	
7SS	17715.54	25085.39	15.0	2.00	STL STEEL	
8-1	17723.25	25050.74	15.0	1.50	PVC	
8-2	17713.71	25061.75	15.0	1.25	PVC	
8-3	17703.22	25074.36	15.0	1.50	PVC	
8-4	17695.35	25083.98	15.0	1.50	PVC	
8-5	17687.73	25094.39	15.0	1.50	PVC	
8-6	17686.94	25097.80	15.0	6.00	STEEL	
8N	17730.40	25045.33	15.0	1.25	PVC	
8NE	17722.77	25069.36	15.0	1.25	PVC	
8NW	17706.56	25059.75	15.0	1.25	PVC	
8S	17679.62	25104.20	15.0	1.25	PVC	
8SE	17705.37	25086.78	15.0	1.25	PVC	
8SSS	17712.28	25062.55	15.0	2.50	STL STEEL	
8SW	17690.35	25078.37	15.0	1.25	PVC	
8TSS	17714.19	25067.56	15.0	2.50	STL STEEL	
9-1	17712.40	25042.32	15.0	1.50	PVC	
9-1A	17674.02	25085.42	15.0	1.50	PVC	
9-2	17702.39	25054.94	15.0	1.50	PVC	
9-2A	17686.12	25074.92	15.0	1.50	PVC	
9-3	17693.62	25064.75	15.0	1.50	PVC	
9SS	17706.56	25048.98	15.0	2.50	STL STEEL	
A-UNK	16984.94	24400.41		1.50	ALUMINUM	
B-UNK	16985.02	24282.45		1.50		
C-UNK	17046.11	24403.38		4.00	STEEL	
C2X1	17192.53	24618.85		3.00	PVC	
C5X1	16717.68	24607.63		3.00	PVC	
C5X2	16715.58	24617.44		3.00	PVC	

WELL	COORDINATES		DEPTH (ft)	CASING DIAMETER	CASING MATERIAL	STATUS
	NORTH	EAST		(in)		
CAP7A	16028.68	24434.39		3.00	PVC	
CAP7B	16036.84	24428.84		3.00	PVC	
CAP7C	16054.01	24413.94		3.00	PVC	
CAP7D	16075.22	24408.26		3.00	PVC	
CAP7E	16090.01	24399.15		3.00	PVC	
D-UNK	16885.56	24274.85		2.00	STL STEEL	
E-UNK	16802.95	24341.18		2.00	ALUMINUM	
ETF-01	16755.97	23641.19	28.7	6.00	STEEL	
ETF-02	16778.27	23665.16	31.8	6.00	STEEL	Not Found
ETF-03	16764.91	23672.79	30.8	6.00	STEEL	
ETF-04	16749.15	23673.34	30.8	6.00	STEEL	
ETF-05	16732.49	23665.30	30.3	6.00	STEEL	
ETF-06	16724.10	23650.96	30.1	6.00	STEEL	
ETF-07	16723.19	23633.64	30.4	6.00	STEEL	
ETF-08	16729.23	23618.57	29.8	6.00	STEEL	
ETF-09	16745.32	23610.28	30.9	6.00	STEEL	
ETF-10	16763.48	23609.83	31.1	6.00	STEEL	
ETF-11	16773.04	23702.57	49.6	6.00	STEEL	
ETF-12	16737.94	23584.36	50.1	6.00	STEEL	
ETF-13	16871.96	23596.33	250.7	6.00	STEEL	
ETF-14	16849.23	23618.51	94.6	6.00	STEEL	
ETF-15	16841.45	23603.47	46.7	6.00	STEEL	
ETF-16	16841.45	23614.14	244.5	6.00	STEEL	Not Found
ETF-17	16782.86	23606.38	18.7	3.00	PVC	
ETF-18	16791.16	23624.78	19.5	3.00	PVC	
ETF-19	16799.41	23643.83	20.1	3.00	PVC	
ETF-20	16769.52	23606.72	21.8	3.00	PVC	
ETF-21	16776.48	23621.54	20.4	3.00	PVC	
ETF-22	16788.03	23641.20	22.5	3.00	PVC	
ETF-23	16797.92	23659.16	20.3	3.00	PVC	
ETF-24	16762.61	23620.24	21.6	3.00	PVC	
ETF-25	16773.88	23637.95	21.6	3.00	PVC	
ETF-26	16784.95	23655.52	21.2	3.00	PVC	
ETF-27	16745.55	23616.44	20.4	3.00	PVC	
ETF-28	16756.48	23632.12	20.3	3.00	PVC	
ETF-29	16769.40	23651.35	20.7	3.00	PVC	
ETF-31	16743.16	23628.76	17.3	3.00	PVC	
ETF-32	16753.22	23646.40	19.8	3.00	PVC	
ETF-33	16764.51	23662.09	20.0	3.00	PVC	
ETF-34	16732.38	23623.74	21.9	3.00	PVC	Not Found
ETF-35	16740.99	23641.55	20.6	3.00	PVC	
ETF-36	16749.06	23658.60	21.2	3.00	PVC	
ETF-37	16757.00	23674.92	21.4	3.00	PVC	
ETF-38	16727.75	23637.84	22.0	3.00	PVC	
ETF-39	16735.81	23654.86	22.2	3.00	PVC	
ETF-40	16743.62	23671.35	20.7	3.00	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
ETF-41	16775.08	23615.37				
ETF-42	16768.83	23647.66				
ETF-43	16756.82	23667.03		2.00	PVC	
ETF-44	16781.68	23631.73		3.00	PVC	
ETF-45	16769.90	23658.30		3.00	PVC	
ETF-46	16737.53	23635.74				
ETF-47	16790.02	23644.27		3.00	PVC	
ETF-48	16792.11	23650.00		3.00	PVC	
ETF-49	16749.51	23622.82		3.00	PVC	
ETF-50	16752.47	23625.14		3.00	PVC	
ETF-51	16744.00	23650.29		3.00	PVC	
ETF-52	16744.80	23652.92		3.00	PVC	
ETF-60	16719.64	23579.65		3.00	PVC	
ETF-61	16680.62	23596.28		3.00	PVC	
ETF-62	16543.92	23612.82		3.00	PVC	
ETF-63	16659.22	23674.22		3.00	PVC	
ETF-64	16775.48	23694.32		3.00	PVC	
ETF-65	16725.93	23730.29		3.00	PVC	
ETF-66	16678.40	23742.97		3.00	PVC	
ETF-AUNK	16748.05	23657.64		2.00	PVC	
ETF-BUNK	16772.16	23635.93		3.00	PVC	
ETF-CUNK	16775.39	23634.87		3.00	PVC	
ETF-GT1	16766.99	23645.68		2.00	PVC	
ETF-GT2	16771.12	23639.66		2.00	PVC	
ETF-GT3	16773.09	23613.66		2.00	PVC	
ETF-T-1	16573.69	23687.86		2.00	ALUMINUM	
ETF-T-2	16572.15	23689.78		2.00	ALUMINUM	
ETF-T-3	16572.39	23686.38		2.00	ALUMINUM	
ETF-T-4	16575.98	23687.95		2.00	ALUMINUM	
ETF-T-5	16563.84	23689.10		2.00	ALUMINUM	
ETF-T-6	16554.17	23690.19		2.00	ALUMINUM	
ETF-T-7	16562.33	23704.10		2.00	ALUMINUM	
EXP-4	17017.56	24424.29	26.0			Not Found
EXP-5	16927.81	24432.54	27.0	1.50	PVC	
F-UNK	16821.32	24234.80		2.50	STEEL	
G-UNK	16573.14	23946.35		3.00	PVC	
H-UNK	16575.74	23906.92		3.00	PVC	
HDTF-1	16397.39	23172.87		4.00	PVC	
HDTF-2	16409.18	23161.35		4.00	PVC	
HDTF-3	16424.95	23159.73		4.00	PVC	
HDTF-4	16361.54	23158.39		4.00	PVC	
I-UNK	16566.80	23843.79		1.00	STEEL	
J-UNK	16644.85	23881.55		2.00	ALUMINUM	
K-UNK	16702.80	23959.51		6.00	STEEL	
L-UNK	16739.36	23870.73		2.00	ALUMINUM	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
M-UNK	16743.81	23871.22		2.00	ALUMINUM	
N-UNK	16925.93	24006.26		2.00	ALUMINUM	
NAT6-4	16350.00	23450.00	19.0	2.0	ALUMINUM	P&A, 1990
NAT6-10	16528.19	23203.77		2.00	ALUMINUM	
O-UNK	16893.07	23843.07		2.00	ALUMINUM	
P-UNK	16933.39	23690.85		3.00	PVC	
Q-UNK	16881.72	23714.62		3.00	PVC	
R-UNK	16827.43	23749.01		3.00	PVC	
S-11	17627.70	24620.80	45.3			
S-UNK	16782.15	23772.93		3.00	PVC	
SITWL10	17146.07	24365.46		4.00	PVC	
SITWL11	17139.32	24359.19		4.00	PVC	
SITWL13	17159.50	24399.51		4.00	PVC	
SITWL14	17147.84	24413.11		4.00	PVC	
SITWL15	17179.05	24391.78	23.0	2.00	STEEL	
SITWL16	17192.24	24384.11	18.0	2.00	STEEL	
SITWL17	17204.57	24411.49	23.0	2.00	STEEL	
SITWL18	17212.04	24374.12	23.0	2.00	STEEL	
SITWL19	17175.40	24341.82	23.0	2.00	STEEL	
SITWL20	17140.68	24406.98	21.0	2.00	STEEL	
SITWL21	17136.96	24388.59	15.0	2.00	STEEL	
SITWL22	17116.64	24395.00	20.0	2.00	STEEL	
SITWL23	17107.90	24409.06	18.0	2.00	STEEL	
SITWL24	17106.38	24423.01	18.0	2.00	STEEL	
SITWL25	17126.84	24428.38	23.0	2.00	STEEL	
SITWL26	17516.78	24702.44	20.0	2.00	STEEL	
SITWL27	17523.15	24683.54	23.0	2.00	STEEL	
SITWL28	17519.68	24669.78	23.0	2.00	STEEL	
SITWL30	17445.39	24642.90	20.0	2.00	STEEL	
SITWL31	17450.41	24632.43	15.0	2.00	STEEL	
SITWL32	17460.86	24627.03	15.0	2.00	STEEL	
SITWL33	17466.71	24596.81	17.0	2.00	STEEL	
SITWL34	17445.81	24592.26	17.0	2.00	STEEL	
SITWL35	17407.55	24623.51	20.0	2.00	STEEL	
SITWL36	17392.32	24606.97	23.0	2.00	STEEL	
SITWL37	17348.87	24578.77		2.00	STEEL	
SITWL38	16035.85	24463.99	23.0	2.00	STEEL	
SITWL39	16053.22	24500.95	23.0	2.00	STEEL	
SITWL40	16051.47	24461.54	25.0	2.00	STEEL	
SITWL41	16068.43	24496.71	23.0	2.00	STEEL	
SITWL42	16071.03	24463.72	23.0	2.00	STEEL	
SITWL43	16064.54	24427.61	23.0	2.00	STEEL	
SITWL44	16086.55	24448.68	23.0	2.00	STEEL	
SITWL45	16108.34	24493.36	20.0	2.00	STEEL	
SITWL46	16114.80	24469.84	23.0	2.00	STEEL	
SITWL47	16098.47	24432.56	20.0	2.00	STEEL	
SITWL6	17443.70	24613.26	18.0	2.00	STL STEEL	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
SITWL7	17406.61	24591.09	18.0	2.00	STL.STEEL	
SITWL8	17387.23	24587.99	18.0	2.00	STL.STEEL	
SITWL9	17153.10	24372.01		4.00	PVC	
SITWLUNX	16133.26	24421.76		4.00	PVC	
T-1	16398.76	23552.76	9.1			Destroyed
T-3	16360.00	23500.00	15.0	2.0	PVC	Not Found
T-4	16350.00	23600.00	12.0	2.0	PVC	Not Found
T-5	16343.83	23695.66	4.7			P&A, 1990
T-7	16299.72	23550.04	9.4			Destroyed
T-9	17676.13	25080.04		6.00	STEEL	
T-10	16250.96	23401.11	21.6			P&A, 1990
T-11	16250.00	23500.00	14.0	2.0	PVC	Not Found
T-12	16366.90	23600.00	10.0	2.0	PVC	Not Found
T-17	16199.86	23550.51	11.3			P&A, 1990
T-18	16201.27	23653.42	7.3			P&A, 1990
T-20	16200.98	23750.45	10.8			P&A, 1990
T-21	16150.00	23300.00	21.0	2.0	PVC	Not Found
T-22	16137.52	23405.93	16.0			P&A, 1990
T-27	16098.86	23253.89	19.3			P&A, 1990
T-34	16050.00	23400.00	15.0	2.0	PVC	Not Found
T-36	15998.81	23455.12	16.5			P&A, 1990
T101	16423.00	25037.00	10.9	1.00	PVC	
T103	17703.00	24683.00	17.0	1.00	PVC	
T105	16574.00	24642.00	10.1	1.00	PVC	
T110	16684.00	24650.00	8.8	1.00	PVC	
T112	16628.00	24651.00	10.4	1.00	PVC	
T120	17650.00	24637.00	14.3	1.00		
T121	17106.00	24629.00	14.8	1.00	PVC	
T123-1	16987.51	24310.33		2.00	STL.STEEL	
T123-2	16966.72	24304.29		2.00	STL.STEEL	
T123-3	16958.89	24302.58		2.00	STL.STEEL	
T125	17042.64	24339.40		3.00	PVC	
T126	17692.54	25036.23		6.00	STEEL	
T133	17015.00	24351.17		3.00	PVC	
T142	17654.44	25072.46		6.00	STEEL	
T145	16824.86	24232.70				
T147	16823.03	24253.99		2.00	PVC	
T150	16824.98	24269.70		2.00	PVC	
T150-1	16829.51	24267.90		2.00	STL.STEEL	
T150-2	16842.83	24275.55		2.00	STL.STEEL	
T150-3	16852.33	24273.64		2.00	STL.STEEL	
T150-4	16862.59	24273.41		2.00	STL.STEEL	
T150-5	16870.70	24277.80		2.00	STL.STEEL	
T152	16825.47	24285.14		2.00	PVC	
T152-1	16816.59	24289.03		2.00	STL.STEEL	
T152-2	16840.07	24292.31		2.00	STL.STEEL	
T152-3	16850.36	24290.57		2.00	STL.STEEL	
T152-4	16862.30	24290.44		2.00	STL.STEEL	
T155	17541.52	25004.44		6.00	STEEL	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
T161	16895.10	24343.43		2.00	PVC	
T162	15768.00	24082.00	11.4	1.50	PVC	
T163	16812.44	24319.61		3.00	PVC	
T165	17659.45	25008.90		6.00	STEEL	
T168	16970.15	24378.73		2.00	STEEL	
T171	16885.25	24356.03		2.00	PVC	
T178	17562.58	24991.86		6.00	STEEL	
T180	15862.00	24076.00	14.3	1.50	PVC	
T185	16929.10	24403.03		3.00	PVC	
T191	16940.99	24417.58		3.00	PVC	
T192	17622.76	24988.85		6.00	STEEL	
T193	16857.93	24405.83		2.00	PVC	
T196	16820.45	24401.66		2.00	PVC	
T198	16866.55	24427.03		2.00	PVC	
T199	17606.41	24987.15		6.00	STEEL	
T201	16914.55	24398.91				
T203	16848.67	24439.98		2.00	PVC	
T205	16805.89	24436.87		4.00	PVC	
T207	16762.32	24442.42		6.00	STEEL	
T225	15949.00	24054.00	14.6	1.50	PVC	
T237	15842.00	24113.00	14.6	1.50	PVC	
T241	15793.00	24134.00	11.7	1.50	PVC	
T250	16836.99	23865.88		3.00	STL STEEL	
T260-2	16614.80	23908.80	9.5	2.00	STL STEEL	
T260-3	16592.10	23908.70	7.0	2.00	STL STEEL	
T308	16757.00	24673.00	9.7	1.00		
T315	16575.00	24965.00	8.3	2.00	STL STEEL	
T318	16638.00	24719.00	9.8	1.00	PVC	
T329	16678.00	24922.00	9.9	1.00	PVC	
T33	17033.87	24265.94		3.00	PVC	
T330	17044.00	24562.00	15.0	1.00	PVC	
T35	17020.20	24279.83		3.00	PVC	
T352	15950.00	24111.00	13.5	1.50	PVC	
T363	16989.00	24567.00	12.4	1.00	PVC	
T367	15896.00	24148.00	10.5	1.50	PVC	
T370	17587.00	24683.00	13.8			
T373	15994.00	24126.00	12.5	1.50	PVC	
T374	15806.00	24177.00	12.2	1.50	PVC	
T380	17642.00	24680.00	11.5	1.00		
T395	16718.00	24942.00	9.3	1.00	PVC	
T397	17049.00	24508.00	14.5	1.00	PVC	
T40	17060.18	24306.44		3.00	STEEL	
T408	17169.00	24550.00	14.8	1.00	PVC	
T41-1	16994.56	24294.65		2.00	STL STEEL	
T41-2	16972.19	24289.20		2.00	STL STEEL	
T41-3	16964.71	24286.70		2.00	STL STEEL	
T413	16598.00	25006.00	9.7	1.00	PVC	
T414	16650.00	24987.00	9.7	1.00	PVC	
T417	17140.90	24529.30	12.8	2.00	STL STEEL	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
T42	16918.43	24254.86		2.00	PVC	
T422	15876.00	24189.00	9.2	1.50	PVC	
T424	16038.00	24168.00	13.9	1.50	PVC	
T426	16729.00	24982.00	10.4	1.00	PVC	
T44	15809.00	23965.00	15.0	1.50	PVC	
T444	17660.00	24715.00	13.3	1.00	STL.STEEL	
T453	15929.00	24220.00	8.7	1.50	PVC	
T57	15761.00	24032.00	14.8	1.50	PVC	
T60	15700.00	24053.00	11.4	1.50	PVC	
T63	15873.00	24026.00	14.6	1.50	PVC	
T69	16870.00	24565.00	10.4	1.00	PVC	
T82	17702.00	24641.00	13.2	1.00	PVC	
T84	17057.00	24690.00	14.1	1.00	PVC	
T85	16638.00	24614.00	10.5	1.00	PVC	
T92-1	16733.00	24613.00	11.6	1.00	PVC	
T92-2	16728.00	24615.00	11.2	1.00		
TR-01	16002.00	24375.00	46.8	4.00	PVC	Not Found
TR-02	15872.00	24541.00	21.7	4.00	PVC	Not Found
TR-03	15762.00	24331.00	23.3	4.00	PVC	
TR-04	15882.00	24409.00	32.2	4.00	PVC	
TR-05	15867.00	24405.00	30.5	4.00	PVC	
TR-06	15855.00	24393.00	31.0	4.00	PVC	
TR-07	15851.00	24378.00	30.7	4.00	PVC	
TR-08	15856.00	24363.00	31.5	4.00	PVC	
TR-09	15867.00	24352.00	32.6	4.00	PVC	Not Found
TR-10	15881.00	24348.00	35.2	4.00	PVC	Not Found
TR-11	15882.00	24379.00	29.1	4.00	PVC	Not Found
TR-12	15946.00	24377.00	34.1	4.00	PVC	Not Found
UNKAA	16414.81	24086.86		2.00	PVC	

APPENDIX B

**INVENTORY OF WELLS TO BE MAINTAINED
AFTER CLOSURE AT WAG 6**

APPENDIX B. INVENTORY OF WELLS TO BE MAINTAINED AFTER CLOSURE AT WAG 6

WELL	COORDINATES		CASING DEPTH DIAMETER		CASING MATERIAL	TYPE WELL
	NORTH	EAST	(ft)	(in)		
0636	17668.04	24326.17	54.0	2.00	PVC	Piezometer
0637	17715.14	24135.97	66.0	2.00	PVC	Piezometer
0638	17495.05	24119.35	70.0	2.00	PVC	Piezometer
0641	17383.49	23985.25	60.0	2.00	PVC	Piezometer
0647	17145.66	24749.00	36.0	2.00	PVC	Piezometer
0650B	17273.53	25150.16	60.0	2.00	STL.STEEL	Piezometer
0656	17923.92	24692.96	120.0	2.00	PVC	Piezometer
0739	15628.89	23604.23	33.0			Piezometer
0740	15778.95	23372.39	24.0			Piezometer
0741	15596.74	23352.05	22.0			Piezometer
0745	16067.80	23808.30	60.2	4.00	STL.STEEL	RCRA Compliance
0831	17387.40	24133.50	50.7	4.00	STL.STEEL	RCRA Compliance
0832	17385.60	24096.70	85.9	4.00	STL.STEEL	RCRA Compliance
0833	16056.90	23842.40	31.0	2.00	STL.STEEL	RCRA Compliance
0835	15767.70	23951.80	27.5	2.00	STL.STEEL	RCRA Compliance
0836	15748.20	24138.80	28.5	2.00	STL.STEEL	RCRA Compliance
0837	15845.60	24352.60	31.6	2.00	STL.STEEL	RCRA Compliance
0838	16308.70	24934.80	22.8	2.00	STL.STEEL	RCRA Compliance
0839	16308.80	24923.60	56.0	4.00	STL.STEEL	RCRA Compliance
0840	16928.60	25251.70	26.9	2.00	STL.STEEL	RCRA Compliance
0841	17206.30	25294.80	56.5	4.00	STL.STEEL	RCRA Compliance
0842	17216.10	25298.40	26.8	2.00	STL.STEEL	RCRA Compliance
0843	17597.10	25221.40	21.0	2.00	STL.STEEL	RCRA Compliance
0844	17602.50	25228.60	52.0	4.00	STL.STEEL	RCRA Compliance
0845	17108.20	24988.30	41.0	2.00	STL.STEEL	Water Quality PZ
0846	18030.70	24803.50	81.0	4.00	STL.STEEL	RCRA Compliance
0847	17769.90	24790.50	67.0	2.00	STL.STEEL	RCRA Compliance
0849	16781.80	24215.20	32.9	2.00	STL.STEEL	Water Quality PZ
0850	16595.40	24793.50	22.7	2.00	STL.STEEL	Water Quality PZ
0852	16346.90	23911.60	25.3	2.00	STL.STEEL	Water Quality PZ
0853	16695.10	24047.50	27.7	2.00	STL.STEEL	Water Quality PZ
0854	16711.90	23851.90	27.5	2.00	STL.STEEL	Water Quality PZ
0855	16755.30	23427.70	52.0	2.00	STL.STEEL	RCRA Compliance
0856	16764.40	23432.90	82.0	4.00	STL.STEEL	RCRA Compliance
0857	16538.00	23106.30	70.0	2.00	STL.STEEL	RCRA Compliance
0858	16542.10	23115.80	106.4	4.00	STL.STEEL	RCRA Compliance
0859	16009.40	23246.20	26.5	2.00	STL.STEEL	RCRA Compliance
0860	15999.60	23252.90	61.8	4.00	STL.STEEL	RCRA Compliance
0936	16144.55	24609.77	400.4	6.63	STEEL	Hydraulic Head
0937	16148.20	24688.37	215.3	6.63	STEEL	Hydraulic Head
0938	16170.59	24676.08	61.5	6.63	STEEL	Hydraulic Head
0939	15814.83	24525.34	400.4	6.63	STEEL	Hydraulic Head
0940	15827.63	24595.29	215.0	6.63	STEEL	Hydraulic Head
0941	15833.46	24561.12	63.0	6.63	STEEL	Hydraulic Head
0945	17540.65	24512.09	402.5	6.63	STEEL	Hydraulic Head
0999	17518.90	24509.40	295.0	4.50	STEEL	Hydraulic Head
1000	17498.37	24506.56	178.0	4.50	STEEL	Hydraulic Head

<u>WELL</u>	<u>COORDINATES</u>		<u>CASING</u>		<u>CASING</u>	<u>TYPE WELL</u>
	<u>NORTH</u>	<u>EAST</u>	<u>DEPTH</u>	<u>DIAMETER</u>		
			<u>(ft)</u>	<u>(in)</u>	<u>MATERIAL</u>	
1001	16862.02	24694.84	400.0	4.50	STEEL	Hydraulic Head
1002	16810.70	24697.05	197.0	4.50	STEEL	Hydraulic Head
1003	16782.51	24668.21	79.0	4.50	STEEL	Hydraulic Head
1036	16328.57	24231.08	26.7	3.00	PVC	Tumulus
1037	16228.14	24175.72	26.2	3.00	PVC	Tumulus
1234	16956.93	25249.05	147.0			Water Quality PZ
1236	16195.25	23195.49	160.0			Water Quality PZ
1237	17089.07	23868.74	56.8			Water Quality PZ
1238	17079.00	23862.43	151.5			Water Quality PZ
1240	18066.23	25183.89	23.6	2.00	STL.STEEL	RFI
1241	17913.59	25097.59	36.2	2.00	STL.STEEL	RFI
1242	17367.94	25344.78	27.3	2.00	STL.STEEL	RCRA Compliance
1243	17085.60	25239.04	27.9	2.00	STL.STEEL	RCRA Compliance
1244	17155.45	25459.01	24.2	2.00	STL.STEEL	RCRA Compliance
1245	16894.94	25429.95	58.1	2.00	STL.STEEL	RCRA Compliance
1249	16969.58	25244.09	70.0	2.00	STL.STEEL	Water Quality PZ
1257	16493.30	24251.15	23.1	3.00	PVC	Tumulus
1258	16409.20	24248.12	25.0	3.00	PVC	Tumulus
ETF-13	16871.96	25596.33	250.7	6.00	STEEL	Piezometer
ETF-14	16849.23	23618.51	94.6	6.00	STEEL	Piezometer
ETF-15	16841.45	23603.27	46.6	6.00	STEEL	Piezometer
S-11	17627.70	24620.80	45.3			Piezometer

APPENDIX C

**INVENTORY OF WELLS TO BE PLUGGED AND ABANDONED
AT WAG 6**

APPENDIX C. INVENTORY OF WELLS TO BE PLUGGED AND ABANDONED AT WAG 6

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>		<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>			
0+54	16527.25	24474.94	6.1	3.00		PVC	
0033	17356.94	25060.42					
0051	15987.20	23972.30	161.0	3.2		STEEL	Destroyed
0059	16720.00	23998.00					Destroyed
0060	16686.00	23914.00					Destroyed
0061	16715.00	23903.00					Destroyed
0090	16782.00	25473.00		5.88		STEEL	
0091	16860.00	25480.00		6.00		STEEL	
0107	17041.00	24402.00	122.3	5.50		STEEL	Not Found
0108	17279.00	24584.00	126.3	5.50		STEEL	
0109	17330.00	24499.00	126.1	5.50		STEEL	
0110	17204.00	24684.00	125.0	5.50		STEEL	Not Found
0111	17502.00	24778.00					Destroyed
0123	17234.00	24644.00					Destroyed
0176CK	17353.69	25178.92					
0182CK	17345.69	25163.19					
0266	15968.00	23327.00	16.6	6.63		STEEL	Not Found
0267	16118.00	23221.00	17.2	6.63		STEEL	Not Found
0268	16365.00	23307.00	20.1	6.63		STEEL	Not Found
0269	16511.00	23104.00	20.0	6.63		STEEL	
0270	16602.00	23303.00	20.7	6.63		STEEL	Not Found
0271	16581.00	23472.00	20.6	6.63		STEEL	Not Found
0272	16221.00	23520.00	8.4	6.63		STEEL	Not Found
0273	16126.00	23633.00	10.8	6.63		STEEL	Not Found
0274	16210.00	23347.00	18.7	6.63		STEEL	Not Found
0275	16206.00	23737.00	8.5	6.63		STEEL	Not Found
0276	16211.00	23895.00	5.6	6.63		STEEL	
0277	16207.00	24182.00	20.8	6.63		STEEL	Not Found
0278	16552.00	24223.00	10.6	6.63		STEEL	Not Found
0279	16696.00	24205.00	10.4	6.63		STEEL	
0280	16640.00	23997.00	18.4	6.63		STEEL	Not Found
0281	16720.00	23998.00	46.7	3.00		STEEL	Not Found
0282	16725.00	24008.00	18.6	6.63		STEEL	Not Found
0283	16729.00	23989.00	18.4	6.63		STEEL	Not Found
0284	16750.00	23983.00	16.8	6.63		STEEL	Not Found
0285	16761.00	23962.00	13.9	6.63		STEEL	Not Found
0286	16767.00	23945.00	13.2	6.63		STEEL	Not Found
0287	16765.00	23927.00	14.6	6.63		STEEL	Not Found
0288	16752.00	23914.00	14.2	6.63		STEEL	Not Found
0289	16765.00	23896.00	15.7	6.63		STEEL	Not Found
0290	16735.00	23907.00	16.7	6.63		STEEL	Not Found
0291	16738.00	23878.00	14.9	6.63		STEEL	Not Found
0292	16773.00	23821.00	13.4	6.63		STEEL	Not Found
0293	16718.00	23910.00	17.9	6.63		STEEL	Not Found
0294	16722.00	23921.00	17.9	6.63		STEEL	Not Found
0295	16703.00	23992.00	15.3	6.63		STEEL	Not Found
0296	16967.00	23958.00	18.7	6.63		STEEL	Not Found

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u> <u>(in)</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>				
0297	16685.00	23847.00				Destroyed
0298	16716.00	23899.00	16.7	6.63	STEEL	Not Found
0299	16705.00	23883.00	18.0	6.63	STEEL	Not Found
0300	16702.00	23868.00	15.5	6.63	STEEL	Not Found
0301A	16687.00	23847.00	9.7	6.63	STEEL	Not Found
0302A	16679.00	23734.00	7.4	6.63	STEEL	Not Found
0303A	16689.00	23782.00	2.6	6.63	STEEL	Not Found
0304	16667.00	23937.00	15.6	6.63	STEEL	Not Found
0305	16660.00	23914.00	13.6	6.63	STEEL	
0306	16679.00	23905.00	17.4	6.63	STEEL	Not Found
0307	16694.00	23897.00	16.2	6.63	STEEL	Not Found
0308	16691.00	23873.00	12.9	6.63	STEEL	Not Found
0309	16716.00	23903.00	26.1	6.63	STEEL	Destroyed
0310	16697.00	23939.00	12.2	6.63	STEEL	Not Found
0311	16936.00	23900.00	18.8	6.63	STEEL	Not Found
0312	16922.00	23529.00	19.2	6.63	STEEL	Not Found
0313	16798.00	23605.00	20.5	6.63	STEEL	Not Found
0314	15983.00	23977.00				Destroyed
0315	15977.00	24188.00	26.6	6.63	STEEL	Not Found
0316	16626.00	24362.00				Destroyed
0317	16766.00	24328.00	13.9	6.63	STEEL	
0318	17225.00	24323.00	14.9	6.63	STEEL	
0319	17625.00	24529.00				Destroyed
0332	17781.00	24634.00				Destroyed
0333	17886.00	24625.00				Destroyed
0334	17715.00	24737.00				Destroyed
0335	17589.00	24965.00				Destroyed
0336	17595.00	25092.00				Destroyed
0337	17717.00	25096.00	10.4	6.63	STEEL	Not Found
0338	17305.00	25158.00	17.1	6.63	STEEL	Not Found
0339	17481.00	25316.00				Destroyed
0340	17130.00	25160.00				Destroyed
0341	16837.00	25165.00	19.7	6.63	STEEL	Not Found
0342	16562.00	25154.00	15.2	6.63	STEEL	Not Found
0343	16763.00	25010.00	23.9	6.63		
0344	16495.00	24810.00	9.1	6.63	STEEL	Not Found
0345	16361.00	24881.00	10.9	6.63	STEEL	Not Found
0346	16435.00	24631.00	16.8	6.63	STEEL	Not Found
0347	16531.00	24604.00	16.4	6.63		
0350	16152.00	24649.00	17.4	6.63	STEEL	Not Found
0351	16028.00	24661.00	24.4	6.63	STEEL	Not Found
0352	15887.00	24305.00	21.0	6.63	STEEL	Not Found
0353	15695.00	24014.00				Destroyed
0354	17234.00	24644.00				Destroyed
0355	16909.00	24991.00	19.3	6.63	STEEL	Not Found
0356	16481.00	24451.00	9.0	6.63	STEEL	
0357	16747.00	24599.00	13.0	6.63	STEEL	Not Found
0358	16090.00	24448.00	18.4	6.63	STEEL	Not Found
0359	16904.00	24867.00	18.7	6.63	STEEL	Not Found

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
0360	17148.00	24968.00	17.6	6.63	STEEL	Not Found
0361	16446.00	24166.00	8.0	6.63	STEEL	Not Found
0362	16588.00	23718.00	7.8	6.63	STEEL	
0363	16420.00	23748.00	3.6	6.63	STEEL	
0364	16407.00	23838.00	7.7	6.63	STEEL	
0365	16454.00	23681.00	5.6	6.63	STEEL	
0366	17467.00	24926.00	23.0	6.63	STEEL	Not Found
0367	17723.00	25091.00	68.8	3.00	PVC	
0368	17348.00	25155.00	39.4	3.00	PVC	
0369	17476.00	24805.00	48.1	3.00	PVC	Not Found
0370	17145.00	24981.00	34.1	3.00	PVC	
0371	16393.00	25090.00	29.8	3.00	PVC	
0372	16570.00	25042.00	33.1	3.00	PVC	Not Found
0373	16945.00	25208.00	33.9	3.00	PVC	Not Found
0374	17462.00	25346.00	30.9	3.00	PVC	
0375	16935.00	23531.00	26.3	3.00	PVC	
0376	16584.00	23479.00	34.7	3.00	PVC	
0377	16610.00	23297.00	55.8	3.00	PVC	
0378	16474.00	23092.00	60.2	3.00	PVC	
0379	16156.00	23206.00	36.6	3.00	PVC	Not Found
0380	15977.00	23320.00	31.3	3.00	PVC	
0381	16248.00	24266.00	35.3	3.00	PVC	
0382	15814.00	24025.00	21.0	3.00	PVC	
0383	16165.00	24895.00	33.2	3.00	PVC	
0384	16131.00	24377.00	46.2	3.00	PVC	Not Found
0385	17903.00	24669.00	44.8	3.00	PVC	
0386	16892.00	24828.00	12.0	3.00	PVC	Not Found
0387	16986.00	24886.00	10.6	3.00	PVC	Not Found
0388	17111.00	24886.00	11.5	3.00	PVC	Not Found
0389	16798.40	24203.49	14.9	3.00	PVC	
0390	16841.59	24199.67	15.1	3.00	PVC	
0391	16899.81	24192.39	10.0			
0392	16974.25	24317.28	20.4	4.00	PVC	
0393	16953.14	24259.03	24.3	4.00	PVC	
0394	17010.56	24420.05	27.6	4.00	PVC	
0395	16896.17	24235.26	23.5	2.00	PVC	
0396	16894.54	24245.22	22.8	2.00	PVC	
0397	16925.31	24227.29	20.8	2.00	PVC	
0398	16939.44	24427.38	28.1	4.00	PVC	
0399	16881.25	24349.51	28.6			
0400	17065.08	24304.61	23.8	4.00	PVC	
0401	17022.31	24380.21	28.9	3.00	PVC	
0402	16816.65	24277.51	18.4	4.00	PVC	
0403	16777.67	24163.08	12.7	3.00	PVC	
0403A	16789.60	24181.66	5.8	2.00	PVC	
0404	16786.33	24159.05	10.1	3.00	PVC	
0404A	16800.43	24180.46	5.9	2.00	PVC	
0405	16791.79	24157.98	13.3	3.00	PVC	
0405A	16810.86	24178.24	8.9	2.00	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
0639	17395.38	24138.11	63.5	2.00	PVC	
0640	17614.70	24719.55	60.0	2.00	PVC	Not Found
0642	16580.96	24035.55	30.0	2.00	PVC	
0643	16344.38	24204.78	21.5	2.00	PVC	Not Found
0644	16748.86	24848.36	17.0	2.00	PVC	Not Found
0645	17173.65	25274.60	25.0	2.00	PVC	
0646	17550.78	25167.05	39.0	2.00	PVC	
0648	17374.55	24524.24	45.0	4.00	PVC	
0649	17375.49	25075.50	37.0	2.00	PVC	
0650A	17273.53	25150.16	60.0	2.00	STL.STEEL	
0651	16870.85	25190.67	110.0	2.00	PVC	
0652	16159.68	24900.00	90.0	2.00	PVC	
0653	15792.51	24070.40	63.0	2.00	PVC	
0654	16618.16	24054.76	90.0	2.00	PVC	
0655	17469.72	24815.30	125.0	2.00	PVC	
0848	16942.40	24656.30	32.0	2.07	STL.STEEL	
0851	16485.00	24058.20	21.6	2.07	STL.STEEL	
1+33	16608.03	24469.71	12.2	3.00	PVC	
1+53	16625.30	24469.22	14.1	3.00	PVC	
1+85	16656.08	24467.64	15.7	3.00	PVC	
1035	16417.57	24174.87	15.5	3.00	PVC	Destroyed
1038	16251.36	24096.88	15.9	3.00	PVC	
1039	16313.32	24093.26	17.6	3.00	PVC	
1040	16376.13	24103.13	17.4	3.00	PVC	
11-1	16619.80	24013.80	9.1	1.00	PVC	
1157	17806.99	25192.38	61.0	3.00	PVC	
1158	17816.12	25102.46	62.1	3.00	PVC	
1159	17752.28	25062.08	63.1	3.00	PVC	
1160	17654.24	25002.46	57.6	3.00	PVC	
1161	17549.76	24928.23	62.2	3.00	PVC	
1162	17608.96	25086.38	61.8	3.00	PVC	
1163	17689.47	25141.24	64.1	3.00	PVC	
1164	17814.50	24993.14	38.3	3.00	PVC	
1165	17879.49	25041.75	39.1	3.00	PVC	
1166	17697.15	24945.94	36.8	3.00	PVC	
1167	17709.84	25256.02	47.9	3.00	PVC	
1168	17645.69	25295.15	28.9	3.00	PVC	
1169	17895.08	25151.41	37.9	3.00	PVC	
1225	17754.77	24603.65	24.0			
1226	17043.45	23763.29	15.0			
1227	16569.39	23838.21	8.0			
1228	16334.67	23878.80	8.0			
1229	16453.32	24072.69	8.0			
123	16975.26	24307.36		4.00	PVC	
1230	16204.70	24606.50	14.0			
1231	16403.79	24659.86	12.2			
1232	17020.14	24218.89	9.0			
1233	17005.25	24211.90	23.7			
1235	16193.30	24618.50	27.2			

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
1254	16434.11	24112.78	17.5	3.00	PVC	
1255	16479.30	24116.72	14.7	3.00	PVC	
1256	16527.31	24178.87	16.9	3.00	PVC	
1259	16389.22	24173.59	15.0	3.00	PVC	
126SS	17681.14	25056.18	15.0	2.00	STL.STEEL	
127	16918.44	24269.15		3.00	PVC	
129	16975.85	24325.35		4.00	PVC	
13-1	16624.50	24006.20	10.1	1.00	PVC	
13-2	16618.00	23999.70	9.4	1.00	PVC	
13-3	16605.00	23995.90	9.7	1.00	PVC	
13-4	16602.40	24000.60	10.0	1.00	PVC	
13-5	16596.90	23998.00	9.7	2.00	PVC	
13-6	16621.50	24005.00	10.3	1.00	PVC	
131	16904.33	24283.73		3.00	PVC	
135	16916.17	24306.07		3.00	PVC	
137	16960.33	24339.20		4.00	PVC	
139	16900.62	24322.38		3.00	PVC	
13N	16629.60	24007.80	8.3	1.00	PVC	
13NE	16616.20	24004.60	8.0	1.00	PVC	
13NW	16616.20	24008.50	8.4	1.00	PVC	
13S	16591.90	23996.20	8.0	1.00	PVC	
13SE	16602.40	24004.90	6.7	1.00	PVC	
13SW	16610.20	24002.80	9.7	1.00	PVC	
142SS	17675.75	25042.68	15.0	2.50	STL.STEEL	
148SS	17634.68	25088.20	15.0	2.00	STL.STEEL	
151SS	17637.12	25066.71	15.0	2.00	STL.STEEL	
153	16827.49	24298.13		4.00	PVC	
155SS	17561.46	25023.05	15.0	2.00	STL.STEEL	
159-6	17670.50	25015.64		6.00	STEEL	
159SS	17639.99	25056.49	15.0	2.00	STL.STEEL	
16-1	16626.80	23996.20	7.6			
160	16959.73	24351.82		4.00	PVC	
165-1	17662.50	25012.42	15.0	1.25	PVC	
165-11B	17644.64	25033.48	15.0	1.25	PVC	
165-13B	17640.48	25037.59	15.0	1.50	PVC	
165-1A	17642.85	25038.17	15.0			Not Found
165-2	17658.10	25017.88	15.0	1.25	PVC	
165-2A	17647.13	25030.96	15.0	1.00	PVC	
165-2B	17663.22	25015.78	15.0	1.25	PVC	
165-3	17654.44	25022.45	15.0	1.50	PVC	
165-3A	17653.93	25021.95	15.0	1.00	PVC	
165-3B	17661.79	25017.00	15.0	1.50	PVC	
165-4	17647.73	25030.82	15.0	1.50	PVC	
165-4A	17657.15	25017.44	15.0			Not Found
165-5	17642.93	25037.90	15.0	1.50	PVC	
165-5A	17661.44	25012.64	15.0			Not Found
165-5B	17657.35	25020.87	15.0	1.25	PVC	
165-6	17659.28	25009.24	15.0	1.00	PVC	
165-7B	17654.79	25023.89	15.0	1.50	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u> <u>(in)</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>				
165-8B	17651.07	25026.62	15.0	1.50	PVC	
165-9B	17649.24	25028.87	15.0	1.25	PVC	
165-X	17658.36	25017.87	15.0	1.50	PVC	
165-Y	17641.17	25037.11	15.0	1.00		
165N	17667.44	25007.12	15.0	1.00	PVC	
165NE	17661.58	25023.30	15.0	1.25	PVC	
165NW	17651.49	25016.39	15.0	1.25	PVC	
165S	17638.67	25043.39	15.0	1.25	PVC	
165SE	17649.16	25039.31	15.0	1.25	PVC	
165SS	17650.76	25028.68	15.0	2.50	STL STEEL	
165SW	17639.90	25029.61	15.0	1.25	PVC	
166	17019.05	24385.85		4.00	PVC	
173	16834.27	24352.23		4.00	PVC	
175	17011.52	24405.85		4.00	PVC	
177	16932.88	24382.37		4.00	PVC	
178SS	17556.97	24990.72	15.0	2.00	STL STEEL	
181	16893.61	24379.90		4.00	PVC	
183	16833.51	24366.31		4.00	PVC	
187	16861.92	24391.90		4.00	PVC	
189	16825.56	24382.82		4.00	PVC	
192SS	17620.13	25001.88	15.0	2.00	STL STEEL	
199SS	17595.10	24977.22	15.0	2.00	STL STEEL	
2+02	16674.21	24467.88	16.7	3.00	PVC	
2+26	16695.99	24467.03	17.3	3.00	PVC	
2+51	16724.09	24464.48	18.7	3.00	PVC	
2-1	17817.08	25121.63	15.0	2.00	PVC	
2-1B	17808.68	25125.25	15.0	1.00	PVC	
2-2	17804.34	25133.02	15.0	2.00	PVC	
2-3	17791.59	25146.03	15.0	2.00	PVC	
2-4	17776.31	25160.67	15.0			Not Found
2-5	17762.29	25175.31	15.0	2.00	PVC	
201	16817.55	24423.83		4.00	PVC	
203	16773.11	24007.84		3.00	PVC	
215	16890.20	23991.92		3.00	PVC	
218	16774.40	23998.59		3.00	PVC	
220	16832.90	23984.74		3.00	PVC	
224	16896.54	23971.80		3.00	PVC	
226	16809.03	23974.12		3.00	PVC	
230	16871.99	23956.55		3.00	PVC	
233	16802.50	23959.59		3.00	PVC	
235	16873.33	23937.11		3.00	PVC	
238	16792.25	23941.12		3.00	PVC	
239	16853.58	23922.04		3.00	PVC	
242	16785.64	23927.28		3.00	PVC	
243	16841.91	23906.81		3.00	PVC	
246	16784.47	23916.13		3.00	PVC	
248	16838.90	23892.94		3.00	PVC	
250	16775.50	23897.23		4.00	PVC	
252-1	16470.60	23939.30	10.1	1.00	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
253	16763.43	23888.01		3.00	PVC	
255	16839.49	23873.13		3.00	PVC	
257	16822.65	23860.81		3.00	PVC	
258	16743.65	23877.06		3.00	PVC	
261	17055.64	23995.98		4.00	PVC	
265	17036.62	23997.02		4.00	PVC	
269	17021.44	24000.25		4.00	PVC	
274	17010.50	23938.50		4.00	PVC	
275-1	16446.20	23970.20	7.1	1.00	PVC	
277	16954.00	23782.49		4.00	PVC	
278	17009.88	23917.00		4.00	PVC	
279	16701.65	24206.62		6.00	STEEL	
279-1	16490.10	23962.60	8.4	1.00	PVC	
279-2	16484.40	23962.40	9.6	1.00	PVC	
279-3	16471.90	23961.80	8.4	1.00	PVC	
279-4	16460.50	23961.40	7.7	1.00	PVC	
279-5	16448.60	23961.10	7.0	1.00	PVC	
279-6	16450.60	23962.40	14.3	1.00	PVC	
279-N	16497.10	23962.86	9.4	1.00	PVC	
279-NE	16478.20	23968.50	9.6	1.00	PVC	
279-NW	16478.20	23955.70	10.2	1.00	PVC	
279-S	16443.10	23960.70	11.6	1.00	PVC	
279-SE	16460.90	23967.30	10.1	1.00	PVC	
279-SW	16461.70	23955.50	8.4	1.00	PVC	
282	16962.83	23802.13		4.00	PVC	
284	16755.45	23985.04		6.00	STEEL	
284-1	16448.40	23951.10	7.0	1.00	PVC	
285-1(S)	16500.70	23950.20	6.6	1.50	PVC	
286	17003.20	23905.12		4.00	PVC	
288-1	16533.50	23937.50	11.7	1.50	PVC	
288-2	16523.60	23938.90	12.3	1.50	PVC	
288-3	16515.00	23940.10	9.6	1.50	PVC	
288-4	16506.90	23941.10	10.7	1.50	PVC	
288-5	16496.50	23942.70	7.6	1.00	PVC	
288-6	16498.10	23942.70	10.0	1.00	PVC	
288-N	16539.70	23936.30	9.8	1.50	PVC	
288-NE	16528.00	23942.50	7.7	1.50	PVC	
288-NW	16525.80	23934.00	7.5	1.50	PVC	
288-S	16491.20	23943.50	2.7	1.00	PVC	
288-SE	16508.20	23945.60	12.1	1.50	PVC	
288-SW	16507.00	23937.00	5.6	1.50	PVC	
290	16952.10	23822.48		4.00	PVC	
293	16960.68	23837.77		4.00	PVC	
3+03	16773.11	24458.03	20.3	3.00	PVC	
3+52	16818.25	24452.43	23.9	3.00	PVC	
3+76	16840.88	24449.03	23.3	3.00	PVC	
3-1	17806.88	25107.80	15.0	2.00	PVC	
3-2	17792.87	25119.19	15.0	1.25	PVC	
3-3	17778.85	25131.39	15.0	1.25	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
3-4	17761.02	25146.03	15.0	1.25	PVC	
3-5	17748.28	25158.23	15.0	1.25	PVC	
304	16967.27	23857.00		4.00	PVC	
34	17002.27	24256.15		4.00	PVC	
36	16983.71	24272.78		4.00	STEEL	
382	15814.00	24025.00		3.00	PVC	
39-1	16929.31	24244.18		4.00	PVC	
39-2	16948.11	24247.05		4.00	PVC	
39-3	16904.44	24237.47		3.50	PVC	
4+01	16870.56	24445.99	26.1	3.00	PVC	
4+27	16893.80	24443.19	25.4	3.00	PVC	
4+58	16922.75	24440.75	28.1	3.00	PVC	
4+77	16943.31	24437.96	29.6	3.00	PVC	
4-1	17787.77	25100.48	15.0	1.25	PVC	
4-2	17776.31	25110.24	15.0	1.25	PVC	
4-3	17763.56	25121.63	15.0	1.25	PVC	
4-4	17749.55	25133.83	15.0	1.25	PVC	
4-5	17738.08	25145.22	15.0	1.25	PVC	
41	16981.93	24291.23		4.00	PVC	
4S	17726.62	25154.16	15.0	1.25	PVC	
5+04	16969.46	24435.04	25.7	3.00	PVC	
5+27	16991.24	24431.87	27.5	3.00	PVC	
5+50	17013.87	24428.95	27.1	3.00	PVC	
5+77	17041.00	24424.94	27.4	3.00	PVC	
5-1	17778.32	25090.69	15.0	2.00	PVC	
5-2	17768.92	25099.73	15.0	1.25	PVC	
5-3	17754.83	25111.57	15.0	1.25	PVC	
5-4	17741.06	25122.03	15.0	1.25	PVC	
5-5	17723.04	25136.06	15.0	1.25	PVC	
5S	17714.19	25143.22	15.0	1.25	PVC	
6+16	17065.21	24411.92	27.2	3.00	PVC	
6-1	17714.85	25122.30	15.0	1.00	PVC	
6-2	17730.25	25112.12	15.0	1.00	PVC	
6-3	17743.36	25100.83	15.0	1.50	PVC	
6-4	17754.17	25091.20	15.0	1.00	PVC	
6-5	17766.62	25081.02	15.0	1.50	PVC	
6N	17772.33	25071.66	15.0	1.50	PVC	
6NE	17754.83	25100.01	15.0	1.25	PVC	
6NW	17744.40	25087.79	15.0	1.25	PVC	
6S	17708.30	25128.08	15.0	1.25	PVC	
6SE	17734.84	25117.62	15.0	1.25	PVC	
6SW	17724.68	25107.44	15.0	1.25	PVC	
7+81	17121.29	24258.15	16.5	3.00	PVC	
7-1	17737.40	25062.80	15.0			Not Found
7-10B	17710.77	25090.47	15.0	1.50	PVC	
7-11B	17706.13	25094.51	15.0	1.25	PVC	
7-12B	17701.90	25099.36	15.0	1.50	PVC	
7-13B	17699.87	25101.78	15.0	1.25	PVC	
7-14B	17698.03	25104.23	15.0	1.25	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
7-15B	17696.60	25105.91	15.0	1.25	PVC	
7-1A	17729.45	25063.35	15.0	1.25	PVC	
7-1B	17738.96	25064.06	15.0	1.25	PVC	
7-2A	17714.42	25087.78	15.0	1.00	PVC	
7-2B	17736.61	25066.54	15.0	1.50	PVC	
7-3	17713.02	25088.06	15.0			Not Found
7-3A	17704.65	25098.39	15.0	1.25	PVC	
7-3B	17734.94	25068.27	15.0	1.50	PVC	
7-4	17703.54	25097.61	15.0	1.50	PVC	
7-4A	17696.31	25108.21	15.0	1.25	PVC	
7-4B	17732.51	25070.39	15.0	1.50	PVC	
7-5	17694.87	25106.03	15.0	1.50	PVC	
7-5A	17727.78	25072.96	15.0	1.50	PVC	
7-5B	17728.48	25073.97	15.0	1.50	PVC	
7-6	17691.23	25107.81	15.0	6.00	STEEL	
7-6B	17725.78	25077.26	15.0	1.50	PVC	
7-7B	17722.13	25080.62	15.0	1.50	PVC	
7-8B	17718.26	25084.08	15.0	1.50	PVC	
7-9B	17714.74	25087.13	15.0	1.50	PVC	
7N	17746.34	25056.66	15.0	1.25	PVC	
7S	17689.18	25113.54	15.0	1.25	PVC	
7SS	17715.54	25085.39	15.0	2.00	STL STEEL	
8-1	17723.25	25050.74	15.0	1.50	PVC	
8-2	17713.71	25061.75	15.0	1.25	PVC	
8-3	17703.22	25074.36	15.0	1.50	PVC	
8-4	17695.35	25083.98	15.0	1.50	PVC	
8-5	17687.73	25094.39	15.0	1.50	PVC	
8-6	17686.94	25097.80	15.0	6.00	STEEL	
8N	17730.40	25045.33	15.0	1.25	PVC	
8NE	17722.77	25069.36	15.0	1.25	PVC	
8NW	17706.56	25059.75	15.0	1.25	PVC	
8S	17679.62	25104.20	15.0	1.25	PVC	
8SE	17705.37	25086.78	15.0	1.25	PVC	
8SSS	17712.28	25062.55	15.0	2.50	STL STEEL	
8SW	17690.35	25078.37	15.0	1.25	PVC	
8TSS	17714.19	25067.56	15.0	2.50	STL STEEL	
9-1	17712.40	25042.32	15.0	1.50	PVC	
9-1A	17674.02	25085.42	15.0	1.50	PVC	
9-2	17702.39	25054.94	15.0	1.50	PVC	
9-2A	17686.12	25074.92	15.0	1.50	PVC	
9-3	17693.62	25064.75	15.0	1.50	PVC	
9SS	17706.56	25048.98	15.0	2.50	STL STEEL	
A-UNK	16984.94	24400.41		1.50	ALUMINUM	
B-UNK	16985.02	24282.45		1.50		
C-UNK	17046.11	24403.38		4.00	STEEL	
C2X1	17192.53	24618.85		3.00	PVC	
C5X1	16717.68	24607.63		3.00	PVC	
C5X2	16715.58	24617.44		3.00	PVC	
CAP7A	16028.68	24434.39		3.00	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
CAP7B	16036.84	24428.84		3.00	PVC	
CAP7C	16054.01	24413.94		3.00	PVC	
CAP7D	16075.22	24408.26		3.00	PVC	
CAP7E	16090.01	24399.15		3.00	PVC	
D-UNK	16885.56	24274.85		2.00	STL STEEL	
E-UNK	16802.95	24341.18		2.00	ALUMINUM	
ETF-01	16755.97	23641.19	28.7	6.00	STEEL	
ETF-02	16778.27	23665.16	31.8	6.00	STEEL	Not Found
ETF-03	16764.91	23672.79	30.8	6.00	STEEL	
ETF-04	16749.15	23673.34	30.8	6.00	STEEL	
ETF-05	16732.49	23665.30	30.3	6.00	STEEL	
ETF-06	16724.10	23650.96	30.1	6.00	STEEL	
ETF-07	16723.19	23633.64	30.4	6.00	STEEL	
ETF-08	16729.23	23618.57	29.8	6.00	STEEL	
ETF-09	16745.32	23610.28	30.9	6.00	STEEL	
ETF-10	16763.48	23609.83	31.1	6.00	STEEL	
ETF-11	16773.04	23702.57	49.6	6.00	STEEL	
ETF-12	16737.94	23584.36	50.1	6.00	STEEL	
ETF-16	16841.45	23614.14	244.5	6.00	STEEL	Not Found
ETF-17	16782.86	23606.38	18.7	3.00	PVC	
ETF-18	16791.16	23624.78	19.5	3.00	PVC	
ETF-19	16799.41	23643.83	20.1	3.00	PVC	
ETF-20	16769.52	23606.72	21.8	3.00	PVC	
ETF-21	16776.48	23621.54	20.4	3.00	PVC	
ETF-22	16788.03	23641.20	22.5	3.00	PVC	
ETF-23	16797.92	23659.16	20.3	3.00	PVC	
ETF-24	16762.61	23620.24	21.6	3.00	PVC	
ETF-25	16773.88	23637.95	21.6	3.00	PVC	
ETF-26	16784.95	23655.52	21.2	3.00	PVC	
ETF-27	16745.55	23616.44	20.4	3.00	PVC	
ETF-28	16756.48	23632.12	20.3	3.00	PVC	
ETF-29	16769.40	23651.35	20.7	3.00	PVC	
ETF-31	16743.16	23628.76	17.3	3.00	PVC	
ETF-32	16753.22	23646.40	19.8	3.00	PVC	
ETF-33	16764.51	23662.09	20.0	3.00	PVC	
ETF-34	16732.38	23623.74	21.9	3.00	PVC	Not Found
ETF-35	16740.99	23641.55	20.6	3.00	PVC	
ETF-36	16749.06	23658.60	21.2	3.00	PVC	
ETF-37	16757.00	23674.92	21.4	3.00	PVC	
ETF-38	16727.75	23637.84	22.0	3.00	PVC	
ETF-39	16735.81	23654.86	22.2	3.00	PVC	
ETF-40	16743.62	23671.35	20.7	3.00	PVC	
ETF-41	16775.08	23615.37				
ETF-42	16768.83	23647.66				
ETF-43	16756.82	23667.03		2.00	PVC	
ETF-44	16781.68	23631.73		3.00	PVC	
ETF-45	16769.90	23658.30		3.00	PVC	
ETF-46	16737.53	23635.74				
ETF-47	16790.02	23644.27		3.00	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u> <u>(in)</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>				
ETF-48	16792.11	23650.00		3.00	PVC	
ETF-49	16749.51	23622.82		3.00	PVC	
ETF-50	16752.47	23625.14		3.00	PVC	
ETF-51	16744.00	23650.29		3.00	PVC	
ETF-52	16744.80	23652.92		3.00	PVC	
ETF-60	16719.64	23579.65		3.00	PVC	
ETF-61	16680.62	23596.28		3.00	PVC	
ETF-62	16643.92	23612.82		3.00	PVC	
ETF-63	16659.22	23674.22		3.00	PVC	
ETF-64	16775.48	23694.32		3.00	PVC	
ETF-65	16725.93	23730.29		3.00	PVC	
ETF-66	16678.40	23742.97		3.00	PVC	
ETF-AUNK	16748.05	23657.64		2.00	PVC	
ETF-BUNK	16772.16	23635.93		3.00	PVC	
ETF-CUNK	16775.39	23634.87		3.00	PVC	
ETF-GT1	16766.99	23645.68		2.00	PVC	
ETF-GT2	16771.12	23639.66		2.00	PVC	
ETF-GT3	16773.09	23613.66		2.00	PVC	
ETF-T-1	16573.69	23687.86		2.00	ALUMINUM	
ETF-T-2	16572.15	23689.78		2.00	ALUMINUM	
ETF-T-3	16572.39	23686.38		2.00	ALUMINUM	
ETF-T-4	16575.98	23687.95		2.00	ALUMINUM	
ETF-T-5	16563.84	23689.10		2.00	ALUMINUM	
ETF-T-6	16554.17	23690.19		2.00	ALUMINUM	
ETF-T-7	16562.33	23704.10		2.00	ALUMINUM	
EXP-4	17017.56	24424.29	26.0			Not Found
EXP-5	16927.81	24432.54	27.0	1.50	PVC	
F-UNK	16821.32	24234.80		2.50	STEEL	
G-UNK	16573.14	23946.35		3.00	PVC	
H-UNK	16575.74	23906.92		3.00	PVC	
HDTF-1	16397.39	23172.87		4.00	PVC	
HDTF-2	16409.18	23161.35		4.00	PVC	
HDTF-3	16424.95	23159.73		4.00	PVC	
HDTF-4	16361.54	23158.39		4.00	PVC	
I-UNK	16566.80	23843.79		1.00	STEEL	
J-UNK	16644.85	23881.55		2.00	ALUMINUM	
K-UNK	16702.80	23959.51		6.00	STEEL	
L-UNK	16739.36	23870.73		2.00	ALUMINUM	
M-UNK	16743.81	23871.22		2.00	ALUMINUM	
N-UNK	16925.93	24006.26		2.00	ALUMINUM	
NAT6-10	16528.19	23203.77		2.00	ALUMINUM	
O-UNK	16893.07	23843.07		2.00	ALUMINUM	
P-UNK	16933.39	23690.85		3.00	PVC	
Q-UNK	16881.72	23714.62		3.00	PVC	
R-UNK	16827.43	23749.01		3.00	PVC	
S-UNK	16782.15	23772.93		3.00	PVC	
SITWL10	17146.07	24365.46		4.00	PVC	
SITWL11	17139.32	24359.19		4.00	PVC	
SITWL13	17159.50	24399.51		4.00	PVC	

WELL	COORDINATES		DEPTH (ft)	CASING DIAMETER		CASING MATERIAL	STATUS
	NORTH	EAST		(in)			
SITWL14	17147.84	24413.11		4.00		PVC	
SITWL15	17179.05	24391.78	23.0	2.00		STEEL	
SITWL16	17192.24	24384.11	18.0	2.00		STEEL	
SITWL17	17204.57	24411.49	23.0	2.00		STEEL	
SITWL18	17212.04	24374.12	23.0	2.00		STEEL	
SITWL19	17175.40	24341.82	23.0	2.00		STEEL	
SITWL20	17140.68	24406.98	21.0	2.00		STEEL	
SITWL21	17136.96	24388.59	15.0	2.00		STEEL	
SITWL22	17116.64	24395.00	20.0	2.00		STEEL	
SITWL23	17107.90	24409.06	18.0	2.00		STEEL	
SITWL24	17106.38	24423.01	18.0	2.00		STEEL	
SITWL25	17126.84	24428.38	23.0	2.00		STEEL	
SITWL26	17516.78	24702.44	20.0	2.00		STEEL	
SITWL27	17523.15	24683.54	23.0	2.00		STEEL	
SITWL28	17519.68	24669.78	23.0	2.00		STEEL	
SITWL30	17445.39	24642.90	20.0	2.00		STEEL	
SITWL31	17450.41	24632.43	15.0	2.00		STEEL	
SITWL32	17460.86	24627.03	15.0	2.00		STEEL	
SITWL33	17466.71	24596.81	17.0	2.00		STEEL	
SITWL34	17445.81	24592.26	17.0	2.00		STEEL	
SITWL35	17407.55	24623.51	20.0	2.00		STEEL	
SITWL36	17392.32	24606.97	23.0	2.00		STEEL	
SITWL37	17348.87	24578.77		2.00		STEEL	
SITWL38	16035.85	24463.99	23.0	2.00		STEEL	
SITWL39	16053.22	24500.95	23.0	2.00		STEEL	
SITWL40	16051.47	24461.54	25.0	2.00		STEEL	
SITWL41	16068.43	24496.71	23.0	2.00		STEEL	
SITWL42	16071.03	24463.72	23.0	2.00		STEEL	
SITWL43	16064.54	24427.61	23.0	2.00		STEEL	
SITWL44	16086.55	24448.68	23.0	2.00		STEEL	
SITWL45	16108.34	24493.36	20.0	2.00		STEEL	
SITWL46	16114.80	24469.84	23.0	2.00		STEEL	
SITWL47	16098.47	24432.56	20.0	2.00		STEEL	
SITWL6	17443.70	24613.26	18.0	2.00		STLSTEEL	
SITWL7	17406.61	24591.09	18.0	2.00		STLSTEEL	
SITWL8	17387.23	24587.99	18.0	2.00		STLSTEEL	
SITWL9	17153.10	24372.01		4.00		PVC	
SITWLUNX	16133.26	24421.76		4.00		PVC	
T-1	16398.76	23552.76	9.1				Destroyed
T-3	16360.0	23500.0	15.0	2.00		PVC	Not Found
T-4	16350.0	23600.0	12.0	2.00		PVC	Not Found
T-11	16250.00	23500.0	14.0	2.00		PVC	Not Found
T-12	16366.9	23600.0	10.0	2.00		PVC	Not Found
T-21	16150.0	23300.0	21.0	2.00		PVC	Not Found
T-34	16050.0	23400.0	15.0	2.00		PVC	Not Found
T-5	16343.83	23695.66	4.7				Destroyed
T-7	16299.72	23550.04	9.4				Destroyed
T-9	17676.13	25080.04		6.00		STEEL	
T101	16423.00	25037.00	10.9	1.00		PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
T103	17703.00	24683.00	17.0	1.00	PVC	
T105	16574.00	24642.00	10.1	1.00	PVC	
T110	16684.00	24650.00	8.8	1.00	PVC	
T112	16628.00	24651.00	10.4	1.00	PVC	
T120	17650.00	24637.00	14.3	1.00		
T121	17106.00	24629.00	14.8	1.00	PVC	
T123-1	16987.51	24310.33		2.00	STL.STEEL	
T123-2	16966.72	24304.29		2.00	STL.STEEL	
T123-3	16958.89	24302.58		2.00	STL.STEEL	
T125	17042.64	24339.40		3.00	PVC	
T126	17692.54	25036.23		6.00	STEEL	
T133	17015.00	24351.17		3.00	PVC	
T142	17654.44	25072.46		6.00	STEEL	
T145	16824.86	24232.70				
T147	16823.03	24253.99		2.00	PVC	
T150	16824.98	24269.70		2.00	PVC	
T150-1	16829.51	24267.90		2.00	STL.STEEL	
T150-2	16842.83	24275.55		2.00	STL.STEEL	
T150-3	16852.33	24273.64		2.00	STL.STEEL	
T150-4	16862.59	24273.41		2.00	STL.STEEL	
T150-5	16870.70	24277.80		2.00	STL.STEEL	
T152	16825.47	24285.14		2.00	PVC	
T152-1	16816.59	24289.03		2.00	STL.STEEL	
T152-2	16840.07	24292.31		2.00	STL.STEEL	
T152-3	16850.36	24290.57		2.00	STL.STEEL	
T152-4	16862.30	24290.44		2.00	STL.STEEL	
T155	17541.52	25004.44		6.00	STEEL	
T161	16895.10	24343.43		2.00	PVC	
T162	15768.00	24082.00	11.4	1.50	PVC	
T163	16812.44	24319.61		3.00	PVC	
T165	17659.45	25008.90		6.00	STEEL	
T168	16970.15	24378.73		2.00	STEEL	
T171	16885.25	24356.03		2.00	PVC	
T178	17562.58	24991.86		6.00	STEEL	
T180	15862.00	24076.00	14.3	1.50	PVC	
T185	16929.10	24403.03		3.00	PVC	
T191	16940.99	24417.58		3.00	PVC	
T192	17622.76	24988.85		6.00	STEEL	
T193	16857.93	24405.83		2.00	PVC	
T196	16820.45	24401.66		2.00	PVC	
T198	16866.55	24427.03		2.00	PVC	
T199	17606.41	24987.15		6.00	STEEL	
T201	16914.55	24398.91				
T203	16848.67	24439.98		2.00	PVC	
T205	16805.89	24436.87		4.00	PVC	
T207	16762.32	24442.42		6.00	STEEL	
T225	15949.00	24054.00	14.6	1.50	PVC	
T237	15842.00	24113.00	14.6	1.50	PVC	
T241	15793.00	24134.00	11.7	1.50	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>		<u>(in)</u>		
T250	16836.99	23865.88		3.00	STL STEEL	
T260-2	16614.80	23908.80	9.5	2.00	STL STEEL	
T260-3	16592.10	23908.70	7.0	2.00	STL STEEL	
T308	16757.00	24673.00	9.7	1.00		
T315	16575.00	24965.00	8.3	2.00	STL STEEL	
T318	16638.00	24719.00	9.8	1.00	PVC	
T329	16678.00	24922.00	9.9	1.00	PVC	
T33	17033.87	24265.94		3.00	PVC	
T330	17044.00	24562.00	15.0	1.00	PVC	
T35	17020.20	24279.83		3.00	PVC	
T352	15950.00	24111.00	13.5	1.50	PVC	
T363	16989.00	24567.00	12.4	1.00	PVC	
T367	15896.00	24148.00	10.5	1.50	PVC	
T370	17587.00	24683.00	13.8			
T373	15994.00	24126.00	12.5	1.50	PVC	
T374	15806.00	24177.00	12.2	1.50	PVC	
T380	17642.00	24680.00	11.5	1.00		
T395	16718.00	24942.00	9.3	1.00	PVC	
T397	17049.00	24508.00	14.5	1.00	PVC	
T40	17060.18	24306.44		3.00	STEEL	
T408	17169.00	24550.00	14.8	1.00	PVC	
T41-1	16994.56	24294.65		2.00	STL STEEL	
T41-2	16972.19	24289.20		2.00	STL STEEL	
T41-3	16964.71	24286.70		2.00	STL STEEL	
T413	16598.00	25006.00	9.7	1.00	PVC	
T414	16650.00	24987.00	9.7	1.00	PVC	
T417	17140.90	24529.30	12.8	2.00	STL STEEL	
T42	16918.43	24254.86		2.00	PVC	
T422	15876.00	24189.00	9.2	1.50	PVC	
T424	16038.00	24168.00	13.9	1.50	PVC	
T426	16729.00	24982.00	10.4	1.00	PVC	
T44	15809.00	23965.00	15.0	1.50	PVC	
T444	17660.00	24715.00	13.3	1.00	STL STEEL	
T453	15929.00	24220.00	8.7	1.50	PVC	
T57	15761.00	24032.00	14.8	1.50	PVC	
T60	15700.00	24053.00	11.4	1.50	PVC	
T63	15873.00	24026.00	14.6	1.50	PVC	
T69	16870.00	24565.00	10.4	1.00	PVC	
T82	17702.00	24641.00	13.2	1.00	PVC	
T84	17057.00	24690.00	14.1	1.00	PVC	
T85	16638.00	24614.00	10.5	1.00	PVC	
T92-1	16733.00	24613.00	11.6	1.00	PVC	
T92-2	16728.00	24615.00	11.2	1.00		
TR-01	16002.00	24375.00	46.8	4.00	PVC	Not Found
TR-02	15872.00	24541.00	21.7	4.00	PVC	Not Found
TR-03	15762.00	24331.00	23.3	4.00	PVC	
TR-04	15882.00	24409.00	32.2	4.00	PVC	
TR-05	15867.00	24405.00	30.5	4.00	PVC	
TR-06	15855.00	24393.00	31.0	4.00	PVC	

<u>WELL</u>	<u>COORDINATES</u>		<u>DEPTH</u> <u>(ft)</u>	<u>CASING</u> <u>DIAMETER</u> <u>(in)</u>	<u>CASING</u> <u>MATERIAL</u>	<u>STATUS</u>
	<u>NORTH</u>	<u>EAST</u>				
TR-07	15851.00	24378.00	30.7	4.00	PVC	
TR-08	15856.00	24363.00	31.5	4.00	PVC	
TR-09	15867.00	24352.00	32.6	4.00	PVC	Not Found
TR-10	15881.00	24348.00	35.2	4.00	PVC	Not Found
TR-11	15882.00	24379.00	29.1	4.00	PVC	Not Found
TR-12	15946.00	24377.00	34.1	4.00	PVC	Not Found
UNKAA	16414.81	24086.86		2.00	PVC	

APPENDIX D

PLUGGING AND ABANDONMENT PROCEDURES

APPENDIX D

PLUGGING AND ABANDONMENT PROCEDURES

D.1 PURPOSE

The purpose of this appendix is to describe detailed procedures for the P&A of wells in WAG 6 at ORNL.

D.2 SCOPE

These procedures are intended to provide for effective decommissioning of wells in order to prevent the migration of contaminants.

D.3 RESPONSIBILITIES

WAG 6 Project personnel shall submit a Well P&A Field Operations Planning Form (Appendix E) to the WAG 6 Project Manager and ORNL Groundwater Program Coordinator (GPC) for approval before field activities begin. Any deviations from the procedures shall be approved by both of these offices prior to implementation. In particular, the results of pressure grouting, as required for wells that have their casings split or perforated (Sect. D.5.4 and D.5.5), should be evaluated, when sufficient experience has been gained with the various well wells encountered, to determine if the procedure should be modified or eliminated.

A geologist or qualified engineer shall be on site to record all information and to verify that the P&A activities are completed as planned. That individual is responsible for identifying any contaminated material generated on site in accordance with ORNL/M-116/R1, "Health, Safety, and Environmental Protection Procedure for Excavating Operations", and for implementing procedures to control and dispose of such material.

Within a specified time interval of completing the field work on each well, the ORNL Well Plugging and Abandonment Report (Appendix F) shall be submitted to the to WAG 6 project oversight personnel, who shall provide it to the GPC after verification of its accuracy and completeness.

D.4 REQUIRED EQUIPMENT

The following equipment at a minimum, shall be required:

- rotary drill rig, water truck, and support vehicles; all in good mechanical condition, properly equipped to complete the specified work;

- grout mixers and mixing tanks, including a separate mixer and holding tank for shear mixing bentonite and water prior to adding the cement, grout pumps, water pumps, and hoses;
- portable mud pan and mud balance;
- plastic sheeting (4 mil thickness);
- containers for collecting and transporting potentially hazardous or radioactive drilling fluid, drill cuttings, fluid grout, groundwater, and well casing;
- hot water pressure washer with an operating range equal to or greater than 800 psi and at least 180°F; and
- A downhole camera and supporting equipment.

D.5 PLUGGING AND ABANDONMENT PROCEDURES

D.5.1 Procedures for Wells in the Waste Trenches

- Measure and record the diameter and depth of the well, and depth to water. If the measurement indicates that the well is not open to its full depth, an attempt shall be made to dislodge any obstruction downward to the bottom of the well. Plastic sheeting shall be placed prior to obstruction dislodging operations, so as to protect the ground surface from contamination by equipment used in the operation. Removal of obstructions shall be attempted only by mechanical percussion or auger methods, with the auger operated in a fashion not to bring material to the surface. If the blockage can not be removed by this effort, the plugging operation shall continue in the portion of the well that is open. Removal of, or attempt to remove, blockages shall be documented in the Plugging and Abandonment Report.
- Calculate the minimum volume of coarse-granular (chips) and powdered bentonite required to plug the well to a level 3.5 feet below the ground surface by determining the inside volume of the well, including screen and casing as follows.

$$V = \frac{3.14 \times r^2}{144} \times D \quad (1)$$

where:

V = volume in cubic feet

r = inside radius of well pipe in inches

D = depth, in feet, of total well installation below ground surface minus 3.0 feet

- Bentonite chips shall be placed slowly into the well at a steady rate not to exceed 25 pounds per minute, up to a level 3.5 feet below the ground surface. Throughout this process, the depth to the bentonite shall be measured and rodded at least at one foot intervals (as determined by placement of the quantity of bentonite calculated to yield

this interval), with a pole clearly marked in 1/2-foot intervals. If measurement indicates that the bentonite has bridged in the casing, the blockage will be removed by manipulation of the measuring pole with an augering action, and the rate of placement of bentonite chips reduced so that bridging will not reoccur.

- Sufficient powdered bentonite shall be placed on top of the coarse-granular bentonite to bring the bentonite to a level 3.0 feet below the ground surface. This shall be followed by Type 1 cement grout to a depth of 1.0 feet below the surface. Type 1 cement grout shall be mixed to a water/cement ratio (by volume) of 0.7 part potable water to 1 part portland cement (5.2 gal of water to one 94 lb bag of cement). This mix will yield a grout with a density of 114.2 pounds per cubic foot (15.3 lbs/gal).
- When the grout has set (minimum 24 hours), the casing shall be removed to a depth of 1.0 feet below the ground surface. If the grout level was less than 1.0 feet below the ground surface prior to casing removal, grout must be added to bring the grout to that level. Grout can be added either before the casing is removed, or after its removal. However, the grout must set for at least 24 hours before the casing excavation can be backfilled.
- The casing excavation shall be backfilled with the excavated soil placed in layers no thicker than 6 inches. Each 6-inch layer of placed soil shall be compacted with three passes of a power-operated tamping machine. Additional clay (CL, as described by the Unified Soil Classification System) soil shall be provided to replace the volume of the casing removed and any volume decrease due to compaction. The completed backfill will be graded so that it will not pond surface water.
- As prescribed in Sect. 3.7.5, decontaminate equipment and tools.

D.5.2 Procedures for French Drain Wells

- Measure and record the diameter and depth of the well, and the depth to water. If the well has an obstruction located 5 feet or higher from the bottom, the well will be inspected via a downhole camera, and the obstruction removed to eliminate the potential for later subsidence. Obstructions can be dislodged by percussion or drilled out with an auger or fluid rotary method.
- Calculate the minimum volume of 3/4-inch, maximum size, stone required to fill the well to a level 2.0 feet below the ground surface by determining the inner volume of the well, including the screen and casing, using equation (1), above, where:

V = calculated volume in cubic feet

r = inside radius of well pipe in inches

D = depth, in feet, of total well installation below ground surface, minus 2.0 feet

- Slowly (so as not to bridge in the casing) pour stone into the well to a level 2.0 feet below the ground surface. Throughout this process, measure the depth to the stone at two foot intervals (as determined by placement of the quantity of stone calculated to yield this interval), with a pole clearly marked in 1/2-foot intervals.

- Remove the casing to a depth of 2.0 feet below the ground surface.
- The casing excavation shall be backfilled with the excavated soil placed in layers no thicker than 6 inches. Each 6-inch layer of placed soil shall be compacted with three passes of a power-operated tamping machine. Additional clay (CL, as described by the Unified Soil Classification System) soil shall be provided to replace the volume of the casing removed and any volume decrease due to compaction. The completed backfill will be graded so that it will not pond surface water.
- As prescribed in Sect. 3.7.5, decontaminate equipment and tools.

D.5.3 Procedures for Wells with Screened or Perforated Intakes

- Prepare the well site for P&A. If present, remove protective posts. Where possible, any sampling hardware shall be salvaged for future use by OR. Spread plastic sheeting, set up equipment, and prepare the containment facility to collect potentially contaminated groundwater, grout, drilling fluids, and drilling debris from the decommissioning operation.
- Measure and record the diameter and depth of the well, and the depth to water. Compare the measured well depth with the recorded depth, and if the measurement indicates that the well may be blocked, inspect the well with a downhole camera. After viewing with the camera, decide whether to remove the obstruction by either drilling with a bit diameter less than the casing diameter, or dislodging it by percussion methods.
- If records do not document that the casing/borehole annulus was properly grouted at the time of installation, and the casing is more than 10 feet in length, perforate or split the casing throughout its length from a depth of 10 feet below the ground surface to the top of the well screen. The well depth should be measured after splitting or perforating the casing to ensure that the well is open for grouting.
- Calculate the minimum volume of grout required to fill the well to the ground surface by determining the inner volume of the well, including the screen and casing, using equation (1), above, where:

V = calculated volume in cubic feet

r = inside radius of well pipe in inches

D = depth, in feet, of total well installation below ground surface

- Type 1 cement/bentonite grout mix shall be 94 pounds of Type 1 cement, 3.8 pounds of powdered bentonite, and 8 gallons of potable water. This mix will yield a grout slurry of approximately 1.6 cubic feet having a density of 103 pounds per cubic foot (13.8 lbs/gal), which results in a gravity grouting pressure of 0.7 psi per foot of the grout column. Mix the bentonite and water thoroughly by shear mixing prior to being mixed with the cement. Type 1 cement/bentonite grout shall be used in wells in which the casing is not split or perforated, and where the well screen length is 10 feet or less.

- Microfine-cement grout mix shall be one part microfine cement (a portland/slag based mixture with at least 50% of particle size less than 4 microns) to one part potable water, by weight. Microfine cement is commonly supplied in 44 pound (20kg), therefore a one bag, 1 to 1, mix will yield approximately 0.94 cubic feet of grout slurry having a density of 94 pounds per cubic foot (12.5 lbs/gal), which results in a gravity grouting pressure of 0.65 psi per foot of the grout column. Microfine-cement grout shall be used in all wells in which the casing is split or perforated, in wells with screens more than 10 feet in length, and in any wells constructed with casings perforated over most of their length.
- Insert a tremie pipe to the bottom of the well. Measure and mark the pipe to ensure that it is placed at the proper depth.
- Pump the prescribed type grout into the well through the tremie pipe, that is initially placed on the bottom of the well. The tremie pipe may be raised as grouting progresses, but always shall be at least 10 feet below the grout surface. Continue pumping the grout until undiluted grout reaches the ground surface. Determination of undiluted grout shall be made by monitoring the density of the grout with a mud balance; the density of the grout at the top of the well shall be equal to the density of the specified grout mix. After the grout pipe has been withdrawn, additional grout may be required to fill the well to within 3.0 feet the ground surface.
- Wells grouted with microfine-cement grout shall be pressure grouted through a packer set in the well casing at the ground surface or, if the casing has been slit or perforated above a depth of 10 feet below the ground surface, set the packer into the casing at a depth of 10 feet below the ground surface. The grout line shall be attached to the packer and microfine-cement grout pumped to the well at a pressure slowly increased. The maximum pressure applied will be no greater than 9.0 psi. The ground surface will be carefully observed during pressure grouting, and if any grout appears at the ground surface, the pressure on the well shall immediately be relieved and the pressure grouting of that well terminated. Pressure grouting shall also be terminated if the well takes a quantity of grout equal to twice the minimum calculated volume of the well. When the maximum pressure is applied for period of 10 minutes with no significant grout takes, pressure grouting shall be terminated.
- When the grout has set (a minimum of 24 hours), the casing shall be removed to a depth of 3.0 feet below the ground surface. If the grout level was less than 3.0 feet below the ground surface prior to casing removal, grout must be added to bring the grout to that level. Grout can be added either before the casing is removed, or after its removal. However, the grout must set for at least 24 hours before the casing excavation can be backfilled.
- The casing excavation shall be backfilled with the excavated soil placed in layers no thicker than 6 inches. Each 6-inch layer of placed soil shall be compacted with three passes of a power-operated tamping machine. Additional clay (CL, as described by the Unified Soil Classification System) soil shall be provided to replace the volume of the casing removed and any volume decrease due to compaction. The completed backfill will be graded so that it will not pond surface water.

- As prescribed in Sect. 3.7.5, decontaminate equipment and tools.

D.5.4 Procedures for Open-Hole Bedrock Wells

- Prepare the well site for P&A. If present, remove protective posts. Where possible, any sampling hardware shall be salvaged for future use by OR. Spread plastic sheeting, set up equipment, and prepare the containment facility to collect potentially contaminated groundwater, grout, drilling fluids, and drilling debris from the decommissioning operation.
- Measure and record the diameter and depth of the well, and the depth to water. Compare the measured well depth to the recorded depth, and if the measurement indicates the well may be blocked, it shall be inspected with a downhole camera. After viewing with the camera, decide whether to remove the obstruction either by drilling with a bit diameter less than the casing or rock-borehole diameter, or dislodging it by percussion methods. Also, if the well casing is to be split or perforated, and neither the length of the open-hole section or the length of the casing is known, the well shall be inspected by the downhole camera to determine the length of the well casing.
- If records do not document that the casing/borehole annulus was properly grouted at the time of installation, and the casing is more than 10 feet in length, perforate or split the casing throughout its length from a depth of 10 feet below the ground surface to the top of the open-hole section. The well depth should be measured after splitting or perforating the casing to ensure that the well is open for grouting.
- If the well casing will not be split or perforated, calculate the minimum volume of grout required to fill the well to the ground surface by determining the inner volume of the well, including the open-hole section and casing, using equation (1), above, where:

V = calculated volume in cubic feet

r = inside radius of well pipe in inches

D = depth, in feet, to the bottom of the open borehole from the ground surface

- If the well casing will be split or perforated, calculate the minimum volume of grout required to fill the open-hole section of the well by determining its volume using equation (1), above, where:

V = calculated volume in cubic feet

r = inside radius of the well pipe in inches

D = length, in feet, from the bottom of the casing to the bottom of the open borehole

- If the well casing will be split or perforated, also calculate the minimum volume of microfine-cement grout required to fill the cased portion of the well by determining the inner volume of the casing from the top of the open-hole portion of the well to the ground surface using equation (1), above, where:

V = calculated volume in cubic feet

r = inside radius of the well pipe in inches

D = length, in feet, of the well pipe from the top of the open portion of the well to the ground surface

- Type 1 cement/bentonite grout mix shall be 94 pounds of Type 1 cement, 3.8 pounds of powdered bentonite, and 8 gallons of potable water. This will produce a slurry of approximately 1.6 cubic feet having a density of 103 pounds per cubic foot (13.8 lbs/gal), which results in a grout pressure of 0.7 psi per foot of the grout column. The bentonite and water shall be mixed thoroughly by shear mixing prior to being mixed with the cement. Type 1 cement/bentonite grout shall be used: 1) to grout the open-hole section of all bedrock wells in which the open-hole section has a calculated volume more than 5.0 cubic feet; and 2) to grout both the open-hole section (regardless of dimensions) and cased section of those bedrock wells where the casing is not split or perforated.
- Microfine-cement grout mix shall be one part microfine cement (a portland/slag based mixture with at least 50% of particle size less than 4 microns) to one part potable water, by weight. Microfine cement is commonly supplied in 44 pound (20kg) bags; therefore a one bag, 1 to 1, mix will yield approximately 0.94 cubic feet of grout slurry having a density of 94 pounds per cubic foot (12.5 lbs/gal), which results in a gravity grouting pressure of 0.65 psi per foot of the grout column. Microfine-cement grout shall be used: 1) to grout the cased section of all open-hole bedrock wells where the casing is split or perforated; and 2) to grout the open-hole section of those bedrock wells where the casing is split or perforated and the open hole section has a calculated volume of 5.0 cubic feet or less.
- Insert a tremie pipe to the bottom of the well. Measure and mark the pipe to ensure that it is placed at the proper depth.
- In open-hole bedrock wells which will be grouted with only one type of grout, either Type 1 cement/bentonite grout or microfine-cement grout, pump the grout into the well through the tremie pipe initially placed at the bottom of the well. The tremie pipe may be raised as grouting progresses, but shall always be at least 10 feet below the grout surface. Pumping of the grout shall continue until undiluted grout reaches the ground surface. Determination of undiluted grout shall be made by monitoring the density of the grout with a mud balance; the density of the grout at the top of the well shall be equal to the density of the specified grout mix. After the grout pipe has been withdrawn, grout shall be added as needed to fill the well to within 3.0 feet of the ground surface.
- In those open-hole bedrock wells in which two types of grout will be used, grouting will be in two separate operations. First, insert a tremie pipe to the bottom of the well. The pipe shall be measured and marked to ensure that it is placed at the proper depth. The quantity of Type 1 cement/bentonite grout calculated to fill the open-hole section of the well shall be pumped through the tremie pipe initially placed at the bottom of the well. The tremie pipe may be raised as grouting progresses, but shall always be at least 10 feet below the level of the grout in the borehole. When the calculated quantity has been pumped into the well, the tremie pipe shall be removed

and the grout allowed to set for at least 24 hours prior to continuing to grout the cased portion of the well. After the grout has set for at least 24 hours, again lower a measured tremie pipe into the well to the top of the firm Type 1 cement/bentonite grout and record its depth. If the tremie is not down to the calculated depth of the top the Type 1 cement/bentonite grout, it shall be jetted down to that level. Microfine-cement grout shall then be pumped through the tremie pipe, initially placed on the top of the Type 1 cement/bentonite grout. The tremie pipe may be raised as grouting progresses, but shall always be at least 10 feet below the grout surface. Pumping of the grout shall continue until undiluted grout reaches the ground surface. Determination of undiluted grout shall be made by monitoring the density of the grout with a mud balance; the density of the grout at the top of the well shall be equal to the density of the specified grout mix. After the grout pipe has been withdrawn, additional grout shall be added as needed to fill the well to within 3.0 feet of the surface.

- Wells grouted with microfine-cement grout shall be pressure grouted through a packer set in the well casing at the ground surface or, if the casing has been slit or perforated above a depth of 10 feet below the ground surface, set the packer into the casing at a depth of 10 feet below the ground surface. The grout line shall be attached to the packer and microfine-cement grout pumped to the well at a pressure slowly increased. The maximum pressure applied will be no greater than 9.0 psi. The ground surface will be carefully observed during pressure grouting, and if any grout appears at the ground surface, the pressure on the well shall immediately be relieved and the pressure grouting of that well terminated. Pressure grouting shall also be terminated if the well takes a quantity of grout equal to twice the minimum calculated volume of the well. When the maximum pressure is applied for period of 10 minutes with no significant grout takes, pressure grouting shall be terminated.
- When the grout has set (a minimum of 24 hours), the casing shall be removed to a depth of 3.0 feet below the ground surface. If the grout level was less than 3.0 feet below the ground surface prior to casing removal, grout must be added to bring the grout to that level. Grout can be added either before the casing is removed, or after its removal. However, the grout must set for at least 24 hours before the casing excavation can be backfilled.
- Backfill the casing excavation with the excavated soil placed in layers no thicker than 6 inches. Each 6-inch layer of soil placed shall be compacted with three passes of a power-operated tamping machine. Additional clay (CL, as described by the Unified Soil Classification System) soil shall be provided to replace the volume of the casing removed and any volume decrease due to compaction. The completed backfill will be graded so that it will not pond surface water.
- As prescribed in Sect. 3.7.5, decontaminate equipment and tools.

D.6. Contingency Abandonment With Casing Removal

As previously stated it is believed that all wells at WAG 6 will be decommissioned with casing remaining in place. However if it becomes necessary to decommission a well by

completely removing the casing and grouting the well borehole the following procedures shall apply.

D.6.1. Removal of PVC Casing

- Measure and record the diameter and depth of the well, and the depth to water. The depth should be compared to documentation of the well's installation to determine the depth of casing to be removed.
- Prepare the well site for P&A by removing protective casing, guard posts, sampling hardware, and concrete pad. Where possible, salvage any sampling hardware for future use by OR. Spread plastic sheeting, set up the drill rig and equipment, and prepare the containment facility to collect potentially contaminated groundwater, grout, drilling fluids, and drilling debris.
- Drill the casing out with a tri-cone bit or over-drill it with a hollow stem auger equipped with a pilot bit or guide rod. Properly dispose of drill cuttings and casing. Drill or ream the well to the depth of the original well borehole, with a bit at least 1/4 inch larger in diameter than the diameter of the original borehole. If a tri-cone bit rotary drilling system is used, all original grout and PVC shall be removed from the borehole before removing the drill string.
- Calculate the minimum volume of grout required to fill the redrilled borehole to the ground surface by determining the inner volume of the redrilled borehole, using equation (1), above, where:

V = calculated volume in cubic feet
 r = radius of the bit used in drilling plus 1/4 inch
 D = depth, in feet, of redrilled borehole

- The grout mix proportion shall be 94 pounds of Type 1 cement, 3.8 pounds of powdered bentonite, and 8 gallons of potable water. This mix will yield a grout slurry of approximately 1.6 cubic feet having a density of 103 pounds per cubic foot (13.8 lbs/gal), which results in a gravity grouting pressure of 0.7 psi per foot of the grout column. Mix the bentonite and water thoroughly by shear mixing prior to being mixed with the cement.
- Insert a tremie pipe to the bottom of the well. The pipe shall be measured and marked to ensure that it is placed at the proper depth. If the borehole has collapsed or is otherwise blocked, it shall be redrilled using a mud-rotary drilling system with a drilling fluid designed to inhibit the borehole from collapsing and to reduce infiltration into the strata penetrated by the borehole. At the completion of redrilling the borehole, the drilling fluid shall be left in the borehole in a state that will stabilize the borehole walls for grout placement by the tremie method.
- Pump the grout through a tremie pipe initially inserted to the bottom of the borehole. The tremie pipe may be raised, but shall always be at least 10 feet below the grout surface. Continue pumping the grout until undiluted grout reaches the ground surface. Determination of undiluted grout shall be made by monitoring the weight of

the grout with a mud balance; the weight of the at the top of the well shall be equal to the density of the specified grout mix. Tremie grouting should be completed in one continuous operation. After the grout pipe has been withdrawn, add grout to fill the well to within 3.0 feet of the surface.

- When the grout has set (a minimum of 24 hours), it shall be excavated to a depth of 3.0 feet below the ground surface. If the grout level was less than 3.0 feet below the ground surface prior to its excavation, grout must be added to bring the grout to that level, prior to excavation. However, the grout must set for at least 24 hours before the excavation can be backfilled.
- Backfill the excavation with the excavated soil placed in layers no thicker than 6 inches. Each 6-inch layer of placed soil shall be compacted with three passes of a power-operated tamping machine. Additional clay (CL, as described by the Unified Soil Classification System) soil shall be provided to replace the volume of the casing removed and any volume decrease due to compaction. The completed backfill will be graded so that it will not pond surface water.
- As prescribed in Sect. 3.7.5, decontaminate equipment and tools.

D.6.2 Removal of Steel Casing

- Measure and record the diameter and depth of the well, and the depth to water. The depth should be compared to documentation of the well's installation to determine the depth of casing to be removed.
- Prepare the well site for P&A by removing protective casing, guard posts, sampling hardware, and concrete pad. Where possible, salvage any sampling hardware for future use by OR. Spread plastic sheeting, set up the drill rig and equipment, and prepare the containment facility to collect potentially contaminated groundwater, grout, drilling fluids, and drilling debris.
- Attempt to pull or jack the casing from the well borehole. If the casing cannot be pulled or jacked out, use a hollow stem auger or wash-over pipe to drill over the casing then withdrawn and disposed of properly. The well shall be drilled or reamed to the depth of the original well borehole, with a bit at least 1/4 inch larger in diameter than the diameter of the original borehole. All original grout shall be removed from the borehole before removing the drill string.
- Calculate the minimum volume of grout required to fill the redrilled borehole to the ground surface by determining the inner volume of the redrilled borehole, using equation (1), above, where:

V = calculated volume in cubic feet

r = radius of the bit used in drilling plus 1/4 inch

D = depth, in feet, of redrilled borehole

- The grout mix proportion shall be 94 pounds of Type 1 cement, 3.8 pounds of powdered bentonite, and 8 gallons of potable water. This mix will produce a grout

slurry of approximately 1.6 cubic feet having a density of 103 pounds per cubic foot (13.8 lbs/gal), which results in a gravity grouting pressure of 0.7 psi per foot of the grout column. The bentonite and water shall be mixed thoroughly by shear mixing prior to being mixed with the cement.

- Insert a tremie pipe to the bottom of the well. The pipe shall be measured and marked to ensure that it is placed at the proper depth. If the borehole has collapsed or is otherwise blocked, it shall be redrilled using a mud-rotary drilling system with a drilling fluid designed to inhibit the borehole from collapsing and to reduce infiltration into the strata penetrated by the borehole. At the completion of redrilling the borehole, the drilling fluid shall be left in the borehole in a state that will stabilize the borehole walls for grout placement by the tremie method.
- Pump grout through a tremie pipe initially inserted to the bottom of the borehole. The tremie pipe may be raised, but shall always be at least 10 feet below the grout surface. Continue pumping the grout until undiluted grout reaches the ground surface. Determination of undiluted grout shall be made by monitoring the weight of the grout with a mud balance; the weight of the grout at the top of the well shall be equal to the density of the specified grout mix. Tremie grouting should be completed in one continuous operation. After the grout pipe has been withdrawn, add grout to fill the well to within 3.0 feet of the surface.
- When the grout has set (a minimum of 24 hours), excavate it to a depth of 3.0 feet below the ground surface. If the grout level was less than 3.0 feet below the ground surface prior to its excavation, grout must be added to bring the grout to that level, prior to excavation. However, the grout must set for at least 24 hours before the excavation can be backfilled.
- Backfill the excavation with the excavated soil placed in layers no thicker than 6 inches. Each 6-inch layer of placed soil shall be compacted with three passes of a power-operated tamping machine. Additional clay (CL, as described by the Unified Soil Classification System) soil shall be provided to replace the volume of the casing removed and any volume decrease due to compaction. The completed backfill will be graded so that it will not pond surface water.
- As prescribed in Sect. 3.7.5, decontaminate equipment and tools.

APPENDIX E

WELL PLUGGING AND ABANDONMENT FIELD OPERATIONS PLANNING FORM

1. Total number of wells to be decommissioned by this plan _____
- 2.

[illegible]

4) Required site preparation (removal of posts, pads, pumps, etc.) _____

5) Proposed method of abandonment

6) Health and safety considerations for well abandonment crew _____

7) Desired startup date _____

Required completion date _____

Date Program Plan Submitted _____

8) Comments _____

Well Plugging and Abandonment
Field Operations Planning Form

Sheet 3

9) Project Manager: Name _____ Dept. _____
Phone _____ Signature _____

10) Well Custodian: Name _____ Dept. _____
Phone _____ Signature _____

11) Proposed technical oversight company _____

12) Proposed drilling subcontractor _____

13) Group that will manage well abandonment program _____

14) Approved by: _____ Date _____
SITE GROUNDWATER COORDINATOR

15) Program plan approval subject to following stipulations: _____

16) Approved by: _____ Date _____
GROUNDWATER PROGRAM COORDINATOR

17) Approved by: _____ Date _____
WAG 6 PROJECT MANAGER

APPENDIX F

WAG 6 WELL PLUGGING AND ABANDONMENT REPORT

WAG 6 WELL PLUGGING AND ABANDONMENT REPORT Sheet 1

Prepared by _____ Date _____

PART A

GENERAL INFORMATION

Well number _____ Location _____

Project name _____

Coordinates: North _____ East _____

Abandonment contractor _____ Driller _____

Oversight contractor _____ Oversight _____

Well abandonment: Date started _____ Date completed _____

PART B

WELL DATA FILE REVIEW

Note: Depths are measured from ground surface to the nearest 0.1 ft.

1. Depth to bottom well below ground surface (from data file) (ft) _____
2. Measured depth from ground surface to bottom of well (ft) _____
3. Depth from ground surface to static water level (ft) _____
4. Total drilled depth of borehole (ft) _____ Diameter of drilled hole (in) _____
5. Ground surface elevation (mean sea level) (ft) _____
6. Reason for well abandonment _____

WAG 6 WELL PLUGGING AND ABANDONMENT REPORT Sheet 2

7. Well Casing

Type of Material	Schedule or Thickness	Nominal I.D. (in)	From (ft)	To (ft)
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

8. Well Screen

Type of Material	Nominal I.D. (in)	Slot Type	From (ft)	To (ft)
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

9. Well Sump

Type of Material	Schedule or Thickness	Nominal I.D. (in)	From (ft)	To (ft)
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

10. Annular Grout

Type of Grout	Annular Thickness (in)	From (ft)	To (ft)
_____	_____	_____	_____
_____	_____	_____	_____

11. Annular Seal

Type of Seal	From (ft)	To (ft)
_____	_____	_____
_____	_____	_____

12. Filter Pack

From (ft)	To (ft)
_____	_____
_____	_____

WAG 6 PLUGGING AND ABANDONMENT REPORT

Sheet 3

PART C

PLUGGING DATA

1. Plugging Materials Calculated and Actually Placed.

Volume of all well/materials calculated by equation:

$$V = \frac{3.14 \times r^2}{144} \times D$$

a. If a waste burial trench well:

V = Volume, in cu. ft., for plugging with bentonite

r = 1/2 inside diameter of casing in inches

D = Depth, in feet, to bottom of well to 3.0' below ground surface

r = _____

D = _____

Calculated Vol. (cu ft)	Bentonite Actually Placed Vol. (cu ft)	Difference Between (Cal. & Placed Vol. Use "+" or "-" sign, or "0")	Vol. of Type 1 Cement Grout Actually Placed

b. If a French Drain Well:

V = Volume, in cu ft, for plugging with stone

r = 1/2 inside diameter of casing, in inches

D = Depth, in feet, to bottom of well to 2.0' below ground surface

r = _____

D = _____

Calculated Vol. (cu ft)	Vol. (cu ft) Stone Actually Placed	Difference Between Cal. & Placed Vol. (use "+" or "-" sign, or "0")

WAG 6 PLUGGING AND ABANDONMENT REPORT

Sheet 4

- c. If a Cased and Screened Well, or an Open-Hole Bedrock Well with only one type of Grout Injected:

V = Volume, in cu ft, for plugging with grout

r = 1/2 inside diameter of casing, in inches

D = Depth, in feet, to bottom of well from ground surface

r = _____

D = _____

Type of Grout	Calculated Vol. (cu ft)	Vol. (cu ft) Grout Actually Placed	Difference Between Cal. & Placed Vol. (Use "+" or "-" sign, or "0")

- d. If an Open-Hole Bedrock Well and two types of Grout Injected:

(1) For Open-Hole Section of Bedrock Well

V = Volume, in cu ft, of open-hole section to be plugged with Type 1 cement/bentonite grout

r = 1/2 inside diameter of borehole, in inches

D = Length, in feet, from bottom of borehole to bottom of casing.

r = _____

D = _____

Type of Grout	Calculated Vol. (cu ft)	Vol. (cu ft) Grout Actually Placed	Difference Between Cal. & Placed Vol. (Use "+" or "-" sign, or "0")

WAG 6 PLUGGING AND ABANDONMENT REPORT Sheet 5

(2) For Cased Section of Bedrock Well

V = Volume, in cu ft, of cased section in to be plugged with microfine-cement grout

r = 1/2 inside diameter of casing, in inches

D = Depth, in feet, from bottom of casing to ground surface

r = _____

D = _____

Type of Grout	Calculated Vol. (cu ft.)	Vol. (cu ft) Grout Actually Placed	Difference Between Cal. & Placed Vol. (Use "+" or "-" sign, "0")

2. Describe the actual method used to abandon this well, including observations via downhole camera and removal of obstructions, if applicable _____

3. Footage actually abandoned (From/To) _____

4. Abandonment problems or deviations from abandonment specifications _____

5. Grout mix used _____

6. Maximum pressure applied through packer, if applicable, and volume of grout take due to applied pressure _____

WAG 6 WELL PLUGGING AND ABANDONMENT REPORT Sheet 6

6. Site Cleanup (Include volumes, site locations and methods)

a. Disposal of well pad, posts and other materials _____

_____b. Disposal of well screen(s) and casing _____

_____c. Disposal of drilling mud _____

_____d. Disposal of excess grout _____

8. Date site cleanup completed _____

9. Site inspected by _____ Date _____

10. Report prepared by _____ Date _____

11. Data accuracy verified by _____ Date _____

12. Well Aandonment Comments

DISTRIBUTION

1. L. D. Bates
2. F. F. Baxter
3. M. A. Bogle
4. H. L. Boston
5. H. M. Braunstein
6. T. W. Burwinkle
7. J. B. Cannon
8. R. B. Clapp
- 9-10. K. W. Cook
11. J. H. Cushman
12. R. K. Davis
13. M. F. P. DeLozier
14. R. B. Dreier
15. T. O. Early
16. C. W. Francis
17. D. E. Fowler
18. H. R. Gaddis
19. S. B. Garland II
20. C. W. Gehrs
21. C. D. Goins
22. P. J. Halsey
23. S. G. Hildebrand
- 24-25. D. D. Huff
26. P. Kanciruk
27. R. O. Kennard
28. R. H. Ketelle
29. H. L. King
30. F. C. Kornegay
31. A. J. Kuhaida, Jr.
32. S. L. Laman
33. V. Legg
- 34-36. D. M. Matteo
37. W. M. McMaster
38. L. E. McNeese
39. G. K. Moore
40. L. W. McMahon
41. J. B. Murphy
42. C. E. Nix
- 43-44. P. T. Owen
45. D. E. Reichle
46. C. T. Rightmire
47. T. H. Row
48. P. A. Rubin
49. G. E. Rymer
50. P. A. Schrandt
51. F. E. Sharples
52. L. A. Shevenell
53. L. G. Shipe
54. D. S. Shriner
55. E. D. Smith
56. D. K. Solomon
57. B. P. Spalding
58. R. G. Stansfield
59. S. H. Stow
60. J. H. Swanks
61. D. W. Swindle
62. J. Switek
63. M. F. Tardiff
64. J. R. Trabalka
65. J. E. Van Cleve
66. S. D. Van Hoesen
67. R. I. Van Hook
68. D. R. Watkins
69. R. K. White
70. A. S. Will
71. M. A. Wood
72. T. F. Zondlo
73. Central Research Library
- 74-78. ER Document Management Center
- 79-83. ESD Library
- 84-85. Laboratory Records Department
86. ORNL Patent Section
87. Office of Assistant Manager for Energy Research and Development, Oak Ridge Operations, P.O. Box 2001, U.S. Department of Energy, Oak Ridge, TN 37831-8600
88. G. W. Bodenstein, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8541
89. P. H. Edmonds, Radian Corporation, 120 S. Jefferson Circle, Oak Ridge, TN 37830
90. J. F. Franklin, Bloedel Professor of Ecosystem Analysis, College of Forest Resources, University of Washington, Anderson Hall (AR-10), Seattle, WA 98195
91. C. Gist, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8541
92. R. C. Harriss, Institute for the Study of Earth, Oceans, and Space, Science and Engineering Research Building, University of New Hampshire, Durham, NH 03824
93. G. M. Hornberger, Professor, Department of Environmental Sciences, University of Virginia, Charlottesville, VA 22903

94. G. Y. Jordy, Director, Office of Program Analysis, Office of Energy Research, ER-30, G-226, U.S. Department of Energy, Washington, DC 20545
95. J. R. Kannard, Program Manager, Bechtel National, Inc., P.O. Box 350, Oak Ridge Corporate Center, 151 Lafayette Drive, Oak Ridge, TN 37830
- 96-99. W. E. Murphie, Department of Energy, Office of Environmental Restoration, Eastern Area D&D Branch, EM-423 (GTN), Washington, DC 20545
100. R. H. Olsen, Professor, Microbiology and Immunology Department, University of Michigan, Medical Sciences II, #5605, 1301 East Catherine Street, Ann Arbor, MI 48109-0620
101. A. Patrinos, Acting Director, Environmental Sciences Division, Office of Health and Environmental Research, ER-74, U.S. Department of Energy, Washington, DC 20585
- 102-106. R. C. Sleeman, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8541
107. J. T. Sweeney, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8541
108. F. J. Wobber, Environmental Sciences Division, Office of Health and Environmental Research, ER-74, U.S. Department of Energy, Washington, DC 20585
- 109-110. Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831

END

**DATE
FILMED**

8 / 31 / 92