**HABITAT RECLAMATION PLAN TO MITIGATE
FOR THE LOSS OF HABITAT DUE TO OIL AND
GAS PRODUCTION ACTIVITIES UNDER
MAXIMUM EFFICIENT RATE
NAVAL PETROLEUM RESERVE NO. 1
KERN COUNTY, CALIFORNIA**

by
David C. Anderson

REVIEWED BY

W. K. Ostler, Director
Environmental Sciences Division

This Document is UNCLASSIFIED

ADC Joel E. Jobst
Scientific Specialist III

NOVEMBER 1994

Work was performed by EG&G/EM, Environmental Sciences Division for the U. S. Departments of Energy, Naval Petroleum Reserves in California, and Chevron U.S.A. Production Company under DOE Contract No. DE-AC08-93NV11265

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

MASTER

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

EXECUTIVE SUMMARY

Activities associated with oil and gas development under the Maximum Efficiency Rate (MER) from 1975 to 2025 will disturb approximately 3,354 acres. Based on 1976 aerial photographs and using a dot grid methodology, the amount of land disturbed prior to MER is estimated to be 3,603 acres. Disturbances on Naval Petroleum Reserve No. 1 (NPR-1) were mapped using 1988 aerial photography and a geographical information system. A total of 6,079 acres were classified as disturbed as of June, 1988. The difference between the number of acres disturbed in 1975 (3,603), and the number of acres disturbed as of 1988 (6,079) acres, is 2,476 acres. Future MER projects on NPR-1 are estimated to disturb an additional 878 acres for a total of 3,354 acres.

Compensation for the loss of habitat will come from the reclamation of disturbed habitat and the acquisition and protection of lands within the boundaries of NPR-1 and Naval Petroleum Reserve No. 2 (NPR-2). Through 1992 approximately 1,176 acres of disturbed habitat have been reclaimed on NPR-1 and NPR-2. This includes the contemporaneous reclamation of 142 acres from 1987 to 1991, the reclamation of 59 acres of abandoned facilities on NPR-1, 125 acres of abandoned facility on NPR-2, and the reclamation of 850 acres of historic disturbance on NPR-1. Reclamation is planned for an additional 1,639 acres through the year 2025. Approximately 1,080 wells are scheduled for abandonment during this period. This action will result in the reclamation of approximately 1,490 acres of well pads and 149 acres of road. About 300 of the 878 acres of projected new disturbances will be reclaimed.

It is estimated that as many as 330 wells on NPR-2 could be abandoned and revegetated, or approximately 495 acres. In addition, about 135 acres of historic disturbances on NPR-2 could be reclaimed to compensate for habitat loss on NPR-1. These disturbances include trails, scraped areas, sump areas, etc. that will be evaluated on a case by case basis to determine if they can be reclaimed without impacting oil and gas production activities on NPR-2.

As part of the overall program to compensate for the loss of habitat due to activities associated with MER, parcels of land currently not under the jurisdiction of DOE will be acquired. The lands under consideration are historically known to be habitat for several endangered species. One parcel is located in Section 22S and covers about 480 acres. The other is on NPR-2 in Section 18D and includes about 140 acres. The parcels of land have been or are currently being cultivated and/or grazed. Acquisition of these 620 acres of land would provide an opportunity to not only protect, but possibly enhance the land as endangered species habitat.

Completed reclamation of 1,176 acres, plus future revegetation of abandoned facilities on NPR-1 (1,639 acres), contemporaneous reclamation of 300 acres, reclamation of abandoned facilities (495 acres) and historic disturbances (135 acres) on NPR-2, and acquisition of 620 acres of land will result in approximately 4,365 compensatory acres. Subtracting the compensatory acres (4,365) from the total amount disturbed during MER (3,354) results in a difference of -1,011 or 1.3 acres of compensation for each acre disturbed.

DISTURBANCE AND COMPENSATION ANALYSIS
NAVAL PETROLEUM RESERVE NO. 1

LAND DISTURBANCES PRIOR TO MER, 1975

ADJUSTED TOTAL DISTURBED, 1975 3,603 Acres

LAND DISTURBANCES THROUGH 1988

Total Disturbance as of 1988 6,625 Acres
Less Agricultural Lands (369) Acres
Less Aqueduct (132) Acres
Less Residential (45) Acres
Less Natural Revegetated Lands (1,465) Acres

ADJUSTED TOTAL DISTURBANCE, 1988 6,079 Acres

LAND DISTURBANCES DUE TO MER

Total Disturbed 1975 to 1988 (6,079 - 3,603) 2,476 Acres
Future MER Disturbances (1989 to 2025) 878 Acres

TOTAL MER DISTURBANCE (1975 to 2025) 3,354 Acres

COMPENSATION

Reclamation of Disturbed Lands

Actual Revegetation through 1992 (NPR-1 and NPR-2) 1,176 Acres

Future Reclamation NPR-1

Previously Disturbed Lands Available Still in Use,
but Planned for Future Abandonment and Revegetation 1,639 Acres

Contemporaneous Reclamation 1993 to 2025 (NPR-1)(33% x 878) 300 Acres

Future Reclamation NPR-2

Previously Disturbed Lands Still in Use, but Could
Be Considered for Future Abandonment and Revegetation 495 Acres

Reclamation of Historic Disturbances 135 Acres

Land Acquisition

NPR-1 and NPR-2 620 Acres

TOTAL COMPENSATION 4,365 Acres

NET (MER DISTURBANCE:COMPENSATION RATIO 1:1.3) (1,011) Acres

TABLE OF CONTENTS

<u>Section</u>	<u>Title</u>	<u>Page</u>
1.	COMPENSATION PLAN	1
1.1	BACKGROUND	1
1.2	OBJECTIVES	3
1.3	INVENTORY OF DISTURBED LANDS	3
1.3.1	Land Disturbances on NPR-1 Prior to MER (1976)	3
1.3.2	Land Disturbances on NPR-1 Due to MER, 1976-2025	4
1.3.3	Land Disturbances on NPR-2	4
1.4	COMPENSATION FOR HABITAT LOSS	5
1.4.1	Naval Petroleum Reserve No. 1	5
1.4.1.1	Reclamation Completed	5
1.4.1.2	Future Reclamation: New Disturbances	5
1.4.1.3	Future Reclamation: Abandoned Facilities	5
1.4.1.4	Land Acquisition	6
1.4.2	Naval Petroleum Reserve No. 2	6
1.4.2.1	Reclamation Completed	6
1.4.2.2	Future Reclamation: Abandoned Facilities	7
1.4.2.3	Future Reclamation: Historic Disturbances	8
1.4.2.4	Land Acquisition	9
2.	RECLAMATION PLAN	10
2.1	REGULATORY REQUIREMENTS	10
2.1.1	Federal Requirements	10
2.1.1.1	National Environmental Policy Act of 1969 (NEPA)	10
2.1.1.2	Endangered Species Act of 1973	10
2.1.2	DOE Orders	10
2.1.2.1	5400.1, General Environmental Protection Program Requirements	10
2.1.2.2	5440.1C, Implementation of the National Environmental Policy Act	11
2.1.2.3	6430.1A, General Design Criteria	11
2.1.3	State Regulations	11
2.1.3.1	California Code of Regulations, Title 14, Register 82, No. 43, Subchapter 2. Environmental Protection	11
2.1.4	Miscellaneous Documents	12
2.1.4.1	Wildlife Management Plan	12
2.1.4.2	A Habitat Restoration Plan for Naval Petroleum Reserve No. 1, Kern County, California	12
2.1.4.3	1985 Reclamation Field Plan for Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California	12
2.1.4.4	Reclamation Plan for the Shallow Oil Zone Steam Flood Project, Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California	12

<u>Section</u>	<u>Title</u>	<u>Page</u>
2.2	BACKGROUND	12
2.3	SELECTION OF RECLAMATION SITES	14
2.4	RECLAMATION TECHNIQUES	15
2.5	RECLAMATION MONITORING	16
2.5.1	Initial Plant Establishment	17
2.5.1.1	Procedures	17
2.5.1.2	Results	17
2.5.2	Vascular Plant Cover and Shrub Density on Revegetated Sites	17
2.5.2.1	Procedures	17
2.5.2.2	Results	18
2.6	RECLAMATION RESEARCH	19
3.	DELIVERABLES	20
4.	MILESTONES IN HABITAT RECLAMATION	21
5.	PERTINENT LITERATURE	22
APPENDIX A		26
APPENDIX B		31
APPENDIX C		40

TABLES

<u>Table</u>	<u>Title</u>	<u>Page</u>
1.	Compensation from reclamation and land acquisition on NPR-1.	7
2.	Compensation from reclamation and land acquisition on NPR-2.	8
3.	Total vascular plant cover on revegetated sites.	18

1.0 COMPENSATION PLAN

1.1 BACKGROUND

Naval Petroleum Reserves in California (NPRC) are comprised of Naval Petroleum Reserve No. 1 (NPR-1) and Naval Petroleum Reserve No. 2 (NPR-2). Both Reserves were created under Presidential Executive Order in 1912 and are currently operated by the U.S. Department of Energy (DOE). NPR-1 was maintained in a reserve status until the oil embargo of the mid 1970s, which resulted in passage of the Naval Petroleum Reserves Production Act in 1976 and production of oil at the maximum efficient rate (MER).

NPR-1 and NPR-2 are located southwest of Bakersfield, California. NPR-1 contains approximately 47,245 acres encompassing the Elk Hills, which is a long, narrow ridge oriented perpendicular to the adjoining Temblor Mountain Range. NPR-2, located directly south of NPR-1, consists of 30,080 acres. The major topographic feature of NPR-2 is the Buena Vista Hills, a low-lying, but distinctive mountain range.

Oil and gas production activities began in the early 1900s and have resulted in the disturbance of land on both NPR-1 and NPR-2. The magnitude of the disturbance has coincided with oil development which intensified in 1976 with MER.

DOE was notified in June, 1979 that construction activities on Elk Hills required a formal consultation with the U.S. Fish and Wildlife Service (FWS) owing to the potential impacts on two endangered species, the San Joaquin kit fox (*Vulpes macrotis mutica*) and blunt-nosed leopard lizard (*Gambelia silus*). Under Section 7 of the Endangered Species Act a formal consultation with FWS was requested in October, 1979. The Biological Opinion rendered for the proposed action offered several reasonable and prudent alternatives to avoid jeopardy to the San Joaquin kit fox and the blunt-nosed leopard lizard, while allowing DOE activities to continue concurrently with mitigation (FWS, 1980). Alternatives specific to habitat reclamation were:

Alternative 3. USN/DOE shall prepare a Master Plan for the restoration of disturbed habitat on NPR-1. The goal of restoration should be equalling optimum carrying capacity on disturbed habitat to that found on comparable native habitat. . . . We further believe, . . . that NPR-2 be given the same consideration for restoration.

Alternative 4. USN/DOE shall commit to the carrying out a compensation/mitigation plan which will . . . offset impacts resulting from MER. The plan should include, . . . off-site purchase of habitat that would otherwise be lost to development, restoration of destroyed habitat, and/or increased carrying capacity of disturbed habitat.

The Navy and, subsequently, DOE supported research on endangered species including the investigation of successful reclamation techniques for NPRC, which resulted in the completion of a Habitat Restoration Plan for NPR-1 in 1985 (O'Farrell and Mitchell, 1985). The Habitat Restoration Plan provided a background of arid land reclamation, a synopsis of reclamation research completed from 1981 to 1983 on NPR-1, and established an approach for meeting the goal of rehabilitating habitat disturbed by oil and gas production activities as a result of MER. Even though the Plan did not include acreages or schedules for restoring equivalent on-site acreage to that lost from MER activities DOE began reclaiming large acreages of disturbed lands on NPR-1 in the fall of 1985.

During the same time as reclamation techniques and plans were being developed, research began on the San Joaquin kit fox and blunt-nosed leopard lizard, the only two species listed as either threatened or endangered at that time. Results of the studies on the two species were important so that FWS would be able to more specifically assess the overall impacts of MER. After several years of research, Biological Assessments on the impacts of MER on the San Joaquin kit fox and blunt-nosed leopard lizard were completed. In addition several topical reports containing the results of the endangered species studies carried out by DOE since the early 1980s were published. With this information formal consultation was requested by DOE on July 1, 1986 on the petroleum development program at maximum efficient rate at NPR-1. A non-jeopardy opinion was rendered by FWS in 1987. Replacement of endangered species habitats lost to project-related actions was one of the reasonable and prudent measures specified to minimize incidental take. To implement this measure, FWS required DOE to meet the following terms and conditions:

- 1) Complete an inventory of disturbed parcels and acreages at NPR-1 that may be revegetated to offset loss of habitat.
- 2) Develop a 10 year program specifying time frames and acreages, with the overall objective of restoring (at a minimum) equivalent on-site acreage to that lost from prior project related actions.
- 3) Examine alternatives, including other means as determined feasible on site, to offset the on-site loss of San Joaquin kit fox habitat.

The inventory of disturbed parcels of land on NPR-1 was completed in early FY89. As was recognized by FWS, preparation of the 10 year program was dependent upon the completion of the inventory. However, in a good faith effort to comply with the measures specified by FWS in the 1980 Biological Opinion, DOE initiated a habitat reclamation program in 1985 and has continued reclamation work on a year by year basis. Beginning in 1987 all sites that had been reclaimed were monitored to determine if the program had been successful in restoring plant cover on disturbed lands.

Information on DOE's habitat reclamation program was disseminated informally to state

and federal regulatory agencies during the first 5-7 years. Topical reports were prepared during this period and distributed to the agencies. The reports on habitat reclamation included a Reclamation Plan by O'Farrell and Mitchell (1985), a reclamation plan specific to work in 1985 (Wolfe, 1986a), a reclamation plan for the steamflood project (Wolfe, 1986b), and a summary of reclamation work on NPR-1 (Anderson, 1987). In more recent years FWS and other agencies have received an update of the program in the form of annual reports and program reviews.

FWS and California Department of Fish and Game (CDFG) are members of an Endangered Species Advisory Committee formed by DOE in 1989. The committee meet 3-4 times each year and during those meetings members were briefed on the progress of reclamation at NPR-1 and have made comments on certain aspects of the reclamation program.

The first draft of a Reclamation Plan for NPR-1, which included acreages, schedules, and alternative means to offset the loss of habitat, was prepared in 1989 following completion of the disturbance mapping project. The document was sent to FWS and CDFG, and both agencies provided comments, which have been incorporated into this document. Since the first version in 1989, the Plan has gone through several revisions. However, the purpose is still to establish a strategy and methodology to compensate for the loss of habitat on NPR-1 due to MER activities.

1.2 OBJECTIVES

The overall objective of this document is provide specific information relating to the on-site habitat restoration program at NPRC. The specific objectives, which relate to the terms and conditions that must be met by DOE as a means of protecting the San Joaquin kit fox from incidental take (U.S. Fish and Wildlife Service, 1987, page 21) are to:

- 1) determine the amount and location of disturbed lands on NPR-1 and the number of acres disturbed as a result of MER activities,
- 2) develop a long term (10 year) program to restore an equivalent on-site acres to that lost from prior project-related actions, and
- 3) examine alternative means to offset kit fox habitat loss.

1.3 INVENTORY OF DISTURBED LANDS

1.3.1 Land Disturbances on NPR-1 Prior to MER (1976)

The amount of land disturbed on NPR-1 prior to MER is estimated to be 3,603 acres using

a dot grid methodology (Bryant, 1943; Mosby, 1980; EG&G/EM, 1987). Transparent dot grids were overlaid on aerial photography taken in 1975. The proportion of dots intercepting disturbed and undisturbed areas was obtained. These procedures were followed for each section of land within NPR-1 boundaries. The number of acres disturbed was determined by multiplying the percentage of disturbed land within that section by the total number of acres in the section. Detailed calculations are found in Appendix A.

1.3.2 Land Disturbances on NPR-1 Due to MER, 1976-2025

The amount of land that will be disturbed from activities associated with MER is estimated to be 3,354 acres. This estimate includes 2,476 acres of known disturbances through 1988, plus 878 acres of estimated future disturbances from 1989 to 2025. The amount of land disturbed on NPR-1 was determined in FY88 and FY89. In FY88 EG&G Energy Measurements, Inc. (EG&G/EM) was tasked by DOE to inventory all disturbed parcels of land on NPR-1 and estimate the amount of disturbance that may have resulted from activities associated with increased oil and gas production activities as directed by implementation of MER. Through the use of aerial photography taken during the summer of 1988 and state-of-the-art mapping techniques (EG&G/EM, 1988), disturbances on NPR-1 were mapped and categorized by type of disturbance. This information was entered into an automated geographic information system (GIS) database and map products and tabular summaries were generated (U.S. Department of Energy, Remote Sensing Laboratory, EG&G/EM, SIGIS Section, Map No. NPR1-92-01.8). A total of 6,079 acres of land was categorized as disturbed as of June 1988 (Appendix A). Subtracting 3,603 acres (Section 1.3.1) of disturbance which occurred prior to 1975 from the number of acres disturbed in 1988 (6,079) provided an estimate of 2,476 acres that have been disturbed due to MER activities between 1975 and 1988.

Future activities associated with MER will disturb approximately 878 acres over the next 30 years. This estimate differs from the 4,369-acre estimate given in the Supplemental Environmental Impact Statement (DOE, 1993) and the Biological Assessment prepared in 1990 (EG&G/EM, 1990). The Biological Assessment was sent to FWS in October 1991 to reinstate consultation under Section 7 of the Endangered Species Act. The 4,369-acre estimate included 101 acres of pipeline development and 3,390 acres of seismic activities. Pipelines and seismic activities are non-federal, third party projects for which compensation will be by the third party at the time of the project. Subtracting the amount of disturbance resulting from pipeline and seismic surveys (4,369 acres) gives a more accurate estimate of 878 acres that will be disturbed on NPR-1 in future years as a result of DOE activities.

1.3.3 Land Disturbances on NPR-2

FWS recommended in the 1980 Biological Opinion that restoration of disturbances located on NPR-2 be considered for restoration to compensate for habitat loss on NPR-1 (U.S. Fish and Wildlife Service, 1980, page 17). This recommendation was the motivation to map

disturbances on NPR-2, although NPR-2 is not subject to development under MER.

Based on 1988 aerial photography, 1,357 acres of land was classified as disturbed on NPR-2 (Appendix A). Mapping disturbed lands on NPR-2 was accomplished using the same procedures as those used on NPR-1 and was completed in the spring of 1992.

1.4 COMPENSATION FOR HABITAT LOSS

Reclamation of historically disturbed sites, contemporaneously disturbed sites and abandoned facilities in combination with land acquisition will compensate (U.S. Fish and Wildlife Service, 1980, page 21) for the loss of habitat on NPR-1 as a result of MER activities. Historic disturbances are defined as those disturbances identified during the disturbance mapping project and include land disturbances on NPR-1 that have occurred from the early 1900s to 1988. Contemporaneous reclamation describes the reclamation efforts that occur immediately after a project is completed and include disturbances such as pipelines, soil borrow areas, well pads, rectifier sites, and side slopes or areas susceptible to erosion. Abandoned facilities are defined as well pads, sump areas, portions of the firebreak, or any other facilities that are no longer needed for oil and gas production activities.

1.4.1 Naval Petroleum Reserve No. 1

1.4.1.1 Reclamation Completed

Reclamation of disturbed habitat on NPR-1 has taken place at an operational level since 1985. All historic disturbances on NPR-1 that were no longer needed for oil and gas production activities were revegetated by the end of 1992. Between 1985 and 1992 approximately 1,051 acres were revegetated on NPR-1: 850 acres of historically disturbed lands no longer needed for oil and gas production, 142 acres of contemporaneous disturbances, and 59 acres of abandoned wells or other facilities (Table 1).

1.4.1.2 Future Reclamation: New Disturbances

Approximately 300 acres of the 878 acres that will be disturbed by oil and gas production activities over the next 30 years will be reclaimed (DOE, 1994). Based on information recorded during endangered species preactivity surveys 34% of the land that is disturbed is revegetated. About 405 acres were disturbed in FY90 and FY91 and 139 of those acres were revegetated. Using this same percentage (34%), it is estimated that of the 878 acres that will be disturbed between 1992 and 2025, 300 acres will be contemporaneously reclaimed (Table 1).

1.4.1.3 Future Reclamation: Abandoned Facilities

Approximately 1,639 acres of habitat disturbed by the abandonment of oil and gas production facilities will be reclaimed between 1992 and 2025. About 1,080 wells will be removed from production and will be abandoned (EG&G/EM, 1990). Based on the assumption that each well pad occupies 2.0 acres, 2,160 acres of abandoned well pads could potentially be reclaimed. However, not all abandoned well sites can be reclaimed. Many sites are adjacent (within 100 feet) to an active well and abandonment of the site is not possible. The number of such well sites is estimated to be 31 % of the total number of new wells, using information provided in the Biological Assessment (EG&G/EM, 1990). It is estimated that the inverse, or 69% of wells totalling 1,490 acres, will be isolated wells and could be reclaimed.

Associated with each well are access roads that can be abandoned and revegetated. Based on the same assumptions used previously, approximately 149 acres of road will be abandoned and revegetated over the next 30 years (1,080 wells x 69% x 0.2 acres of road for each well = 149 acres). This brings the total for all abandoned facilities to 1,639 acres (Table 1).

1.4.1.4 Land Acquisition

As part of the overall program to compensate for the loss of habitat due to activities associated with MER, parcels of land on NPR-1 may be acquired that are currently not under the jurisdiction of DOE. The lands under consideration are historically known to be habitat for several endangered species. Acquisition of the lands by DOE may insure their protection. Two parcels are located in Section 22S and total 480 acres. The San Joaquin kit fox, blunt-nosed leopard lizard, giant kangaroo rat and Hoover's woolly-star are all known to occur either on the two parcels of land or on adjacent lands. Although within NPR-1 boundaries, the parcels of land are accessible to the public. The land is subject to grazing, off-road vehicle use, and agricultural use. DOE has no control over access to the site. The parcels of land have been historically cultivated and/or grazed and some rehabilitation of the lands may be necessary. Acquisition of the land would provide an opportunity to not only protect, but possibly enhance the land as endangered species habitat.

1.4.2 Naval Petroleum Reserve No. 2

1.4.2.1 Reclamation Completed

Over the past five years, 125 acres of disturbed lands on NPR-2 have been revegetated. These were areas disturbed prior to the enactment of the Endangered Species Act and reclamation was performed by lessees. Phillips Petroleum Company abandoned all wells and facilities in Section 30G. Upon completion of the project approximately 25 acres of disturbed land was revegetated. Unocal completed a similar abandonment and clean-up

project on a 320- acre lease in Section 34B. Wells were abandoned and old pipes were removed and 5 acres were reclaimed. A waste water sump in Section 34B covering about 25 acres was abandoned several years ago and has naturally revegetated. A waste water sump and facility in Section 18B were recently abandoned and revegetated. The total area reclaimed was 70 acres.

1.4.2.2 Future Reclamation: Abandoned Facilities

Oil and gas production activities on NPR-2 are on a decline and over the next 30 years it is anticipated that facilities will be abandoned and the land will be returned to its prior use, wildlife habitat. The exact acreage is not available, however, an estimate of 495 acres is made based on the same percentage of existing wells on NPR-1 and the

Table 1. Compensation from reclamation and land acquisition on NPR-1.

RECLAMATION¹ COMPLETED	
Contemporaneous Revegetation: 1987-1991	142
Abandonments:	59
1989-1991	
Historic Disturbances:	<u>850</u>
1985-1992	
Subtotal	1,051
FUTURE RECLAMATION	
Contemporaneous Revegetation: 1992-2025	300
	1,639
Abandoned Facilities: 1992-2025	0
Historic Disturbances:	1,939
Subtotal	
LAND ACQUISITION	
Section 22S north flank of NPR-1	480
Subtotal	480
TOTAL COMPENSATION	3,470
TOTAL MER DISTURBANCES	3,354
DIFFERENCE (MER - COMPENSATION)	(165)

¹The use of the term 'revegetation' or 'reclamation' does not infer that the site supports a vegetative cover equal to adjacent undisturbed land, rather that the site was prepared (ripped and/or disked), seeded and mulched.

number that will be abandoned through the year 2025. On NPR-1 there are approximately 2,016 wells and 1,080 are proposed to be abandoned over the next 30 years (Section 1.4.3.2) which is about 54%. The number of existing wells on DOE-administered lands on NPR-2 is approximately 611. If 54% are abandoned, about 330 wells will be abandoned. Based on 1.5 acres of facilities associated with each well (Section 1.4.3.2), it is estimated that 495 acres (1.5 acres time 330 wells) could be reclaimed as a result of the abandonment of existing wells on NPR-2 (Table 2).

1.4.2.3 Future Reclamation: Historic Disturbances

As many as 135 acres of disturbed lands on NPR-2 could potentially be reclaimed over the next 30 years. Potential reclamation sites were identified during the disturbance mapping project recently completed for DOE-administered lands on NPR-2.

Table 2. Compensation from reclamation and land acquisition on NPR-2.

RECLAMATION¹ COMPLETED	
Abandonments: 1989-1991	125
Subtotal	125
FUTURE RECLAMATION	
Abandoned Facilities	495
Historic Disturbances	<u>135</u>
Subtotal	630
LAND ACQUISITION	
Section 18D, NPR-2	140
Subtotal	140
TOTAL COMPENSATION	895

¹The use of the term 'revegetation' or 'reclamation' does not infer that the site supports a vegetative cover equal to adjacent undisturbed land, rather that the site was prepared (ripped and/or disked), seeded and mulched.

Of the 1,357 acres that are disturbed on NPR-2 (Appendix A, Table A-2) approximately 377 acres could be considered for reclamation. The 377 acres are comprised of well pad sumps, diked washes, trails, soil borrow or scraped areas, all types of disturbances that are least likely to be needed for ongoing oil and gas production activities. On NPR-1 2,325 acres were inventoried and 850 acres of historically disturbed sites (Section 1.4.1) were reclaimed. Based on this same percentage of acres inventoried to

acres reclaimed (37%), about 135 acres of the 377 acres inventoried could be reclaimed. The percentage may actually be higher because oil and gas production activities on NPR-2 are on a decline.

The locations of the potential reclamation sites on NPR-2 were plotted on GIS generated maps (U.S. Department of Energy, Remote Sensing Laboratory, EG&G/EM, SIGIS Section, Map No. NPR1-92-01.8). Each potential reclamation site under DOE administration and not under lease will be evaluated and if approved will be reclaimed. Sites on DOE leased lands will also be evaluated, however, it will be the responsibility of the lessee to reclaim the land. DOE will encourage lessees to restore lands to their pre-disturbance use to the extent possible under the lease agreement.

1.4.2.4 Land Acquisition

DOE will consider the cancellation of leases on NPR-2 so lands can be managed for endangered species. One such lease to be evaluated is with the City of Taft on Section 18D, NPR-2. The City of Taft currently leases the land for the discharge of waste water from their nearby water treatment plant. The total area is about 140 acres. San Joaquin kit foxes are known to occur in the area and conversion of the agricultural lands back to wildlife habitat could benefit the kit fox. An aggressive reclamation plan would have to be developed to return the land to a condition beneficial to endangered species.

2. RECLAMATION PLAN

2.1 REGULATORY REQUIREMENTS

Various environmental acts, regulations, and orders require the Department of Energy (DOE) to prevent or eliminate damage to the environment. These regulations include acts of Congress, such as the National Environmental Policy Act of 1969, and management plans developed by DOE specifically for NPRC. Regulatory requirements pertinent to habitat reclamation on NPRC are discussed in the following sections.

2.1.1 Federal Requirements

2.1.1.1 National Environmental Policy Act of 1969 (NEPA)

NEPA established a national policy for the environment. The purposes of the act were to declare a national environmental policy, and promote efforts to prevent or eliminate damage to the environment and biosphere. The major impact identified in the Environmental Impact Statement (EIS) prepared for petroleum production at maximum efficient rate (U.S. Department of Energy, 1979) was a reduction and degradation of habitat. Concern was also expressed for the eventual recovery of the disturbance since revegetation efforts to that point (1979) had not proven successful.

Mitigation measures were not fully addressed in the EIS but were deferred to compliance with the Wildlife Management Plan (Section 2.1.4) being updated at that time. Mitigation required through consultation with the U.S. Fish and Wildlife Service under Section 7 of the Endangered Species Act would also meet the requirements of NEPA. In the event a supplement to the 1979 EIS is prepared mitigation measures identified in the mitigation action plan and the record of decision will provide further direction regarding reclamation requirements on NPRC.

2.1.1.2 Endangered Species Act of 1973

The policy of Congress as stated in the Endangered Species Act is to ensure that actions authorized, funded or carried out by all federal agencies do not jeopardize the continued existence of endangered or threatened species or result in the destruction or adverse modification of their critical habitat. The effect of this Act on habitat reclamation is described in Section 1.1.

2.1.2 DOE Orders

2.1.2.1 5400.1, General Environmental Protection Program Requirements

DOE Order 5400.1 provides general environmental protection guidance for all DOE

operations. The purpose of the Order is to provide comprehensive direction for programs designed to assure compliance with environmental regulations and DOE policies. The requirements of Order 5400.1 DOE and DOE contractor facilities are required to be operated and managed in a manner that will (1) protect, maintain, and, where necessary, restore environmental quality, and (2) minimize potential threats to the environment.

2.1.2.2 5440.1C, Implementation of the National Environmental Policy Act

This Order establishes procedures for compliance with NEPA. As NEPA established a broad national policy, DOE adopted the policy of full compliance to both the spirit and letter of the NEPA, to assure incorporation of national environmental protection goals in the formulation and implementation of energy programs, and advance goals of restoring, protecting, and enhancing environmental quality.

2.1.2.3 6430.1A, General Design Criteria

This Order provides general requirements for site development. The requirements focus on the minimization of the impact, topsoil salvaging, and reestablishment of natural flora on areas disturbed by construction activities. It states that the "Disturbance of the natural terrain shall be minimized ... " and "where feasible natural flora on or adjacent to the construction site shall be preserved and protected from vehicular and pedestrian traffic ...". It further requires that topsoil be preserved and stockpiled for revegetation efforts. Revegetation of areas disturbed by construction should be designed to restore the site to predisturbance conditions. When revegetation is not feasible due to adverse climatic conditions, terraces, dikes, chemical soil stabilizers, or mulches should be used to stabilize the soil.

2.1.3 State Regulations

2.1.3.1 California Code of Regulations, Title 14, Register 82, No. 43, Subchapter 2. Environmental Protection

Section 1776, Well Site Restoration, under Subchapter 2 of the California Code of Regulations is the only reference to 'restoration' as it pertains to oil and gas development activities on NPR-1. The regulation states that "upon abandonment, ...well location will be graded and cleared of equipment, trash, or other wastes, and returned to as near a natural state as practicable." Concrete cellars are to be removed or filled with earth. Concrete, rock and iron from abandoned well foundations are buried following stipulations from the California Department of Public Health (BPOI, March 25, 1988). The Division of Oil and Gas for the State of California stated that regulations governing oil and gas development activities address the abandonment processes and there are no regulations for the revegetation of disturbed areas (1988, Personal communication, D. C. Mitchell, Senior Oil and Gas Engineer, State of California, Dept. of Conservation, Division of Oil and Gas,

Bakersfield, CA).

2.1.4 Miscellaneous Documents

2.1.4.1 Wildlife Management Plan

The Wildlife Management Plan includes a master wildlife management plan and habitat improvement plan, which are to be executed in cooperation between the Bureau of Sport Fisheries and Wildlife, the California Department of Fish and Game and the Officer in Charge at the Naval Petroleum Reserve. The Wildlife Management Plan was updated in 1986 and referenced the Habitat Restoration Plan prepared in 1985 (O'Farrell and Mitchell, 1985).

2.1.4.2 A Habitat Restoration Plan for Naval Petroleum Reserve No. 1, Kern County, California O'Farrell and Mitchell, 1985)

The reclamation of disturbed lands on NPR-1 between 1985 and 1988 used the guidelines presented in this plan. Recommendations made in the plan have been tested during this period, resulting in the modification of some techniques and the confirmation of others.

2.1.4.3 1985 Reclamation Field Plan for Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California (Wolfe, 1986b)

This report was prepared to facilitate the administration and implementation of the first operational habitat restoration program carried out on NPR-1 in 1985. The content of this document was specific to reclamation work being performed in 1985. It included site preparation recommendations, seed mix specifications, revegetation procedures and a description of reclamation research initiated in 1985.

2.1.4.4 Reclamation Plan for the Shallow Oil Zone (SOZ) Steam Flood Project, Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California (Wolfe, 1986a)

This was a working document prepared for the specific reclamation of lands disturbed during the Steam Flood Project. This project required the reclamation of topsoil piles, cut and fill slopes, borrow areas and other miscellaneous disturbances. Specific seed mixes and seeding rates were prepared for the sites.

2.2 BACKGROUND

NPRC encompasses the Buena Vista Hills and Elk Hills in the southwestern edge of the San Joaquin Valley, just east of, but separate from the steep Temblor Range. Elk Hills is

oriented east-west and geographically is an uplifted alluvium anticline (U.S. Department of Agriculture, Soil Conservation Service, 1987) which has been eroded over the years. The Buena Vista Hills form a northwest-southwest crest along the length of NPR-2. NPRC also includes flatter lands along the edges of Buena Vista and Midway valleys. Elevations range from 290 to 1,551 feet. The soils are characteristically sandy loams or clay/loams. There is a minimal amount of topsoil and underlying layers of soils high in salts as a result of deposits when the area was part of the surrounding basin system. Where extreme erosion occurs these underlying soils are exposed, and provide a marginal medium for plant growth. Leaching of the salts is a slow process because annual rainfall averages less than 5 inches and evaporative summer temperatures frequently exceed 100 degrees Fahrenheit.

The vegetation of both NPRC is described as a San Joaquin Saltbush association by Küchler (1977) or a Lower Sonoran Grassland by Twisselman (1967). The most common shrub species include *Atriplex polycarpa* (desert saltbush), *Atriplex spinifera* (spiny saltbush), *Hymenoclea salsola* (Cheesebush), *Isomeris arborea* (bladderpod), *Eriogonum fasciculatum* (California buckwheat), and *Ceratoides lanata* (winterfat). The most abundant grass is *Bromus rubens* (red brome), however, *Festuca megalura* (fescue) and *Schismus arabicus* (Mediterranean grass) are also common. The most common forb is *Erodium cicutarium* (red-stem filaree).

The natural terrain of NPRC is dissected by steep cut and fill slopes and flat compacted areas created as wells were developed. Soils were often contaminated as the wells were brought into production (O'Farrell and Mitchell, 1985). Some areas that were disturbed during early production years are still in use today. However, many others are no longer used and plants have invaded the sites. In other instances, due to soil compaction, contamination, or severe alteration of the topography, the restoration processes are impeded and require man's intervention.

Early attempts to restore disturbed lands on NPR-1 to preexisting conditions were "rarely ... successful" (U.S. Department of Energy, 1979) leading to the conclusion that one of the unavoidable effects of oil and gas production and MER would be the loss of habitat. Reclamation technologies have improved since then. Acts such as the Surface Mining Control and Reclamation Act of 1977 (SMCRA) on a federal level and the enactment of state mining regulations, although more applicable to hard rock mining, refined previously accepted or standard reclamation procedures. These laws stressed that it was no longer good enough to spread seed and walk away. Greater emphasis was placed on "restoration" of the disturbed habitat. Restoration implies more than reestablishment of plants on a disturbed site, which process is more appropriately defined as revegetation of disturbed lands. Reclamation was synonymous with restoration in the minds of those people who managed early reclamation programs. The term restoration is now much more involved and includes the restoration of soil micorflora and microfauna, as well as native wildlife and plant species.

The demand on the reclamation community to restore a disturbed site to pre-disturbance conditions created an increase in research in all phases of the reclamation process. The effect of this reclamation movement on the philosophy of habitat restoration at Elk Hills was positive. Early statements that reclamation was at best disappointing or that supplemental watering was necessary (U.S. Department of Energy, 1979), became a challenge instead of a deterrent. In line with this optimism, field trials were initiated in the fall of 1981 to (1) test species that might be adapted to the growing conditions characteristic of Elk Hills, (2) evaluate revegetation technologies and determine which would work best for reclamation work at Elk Hills, (3) evaluate the use of native seed sources on Elk Hills, and (4) evaluate reclamation equipment needs for the rather unique conditions that exist in an active oil and gas field (O'Farrell and Mitchell, 1985).

Reclamation was carried out at a research level for the next 3 years. The research provided valuable information on the techniques and materials required to carry out a successful habitat reclamation program at NPR-1. Confidence in what had been learned led to a large scale reclamation effort which began in 1985 and has continued through 1992.

Beginning in 1987 reclaimed sites were evaluated to determine the success of the reclamation efforts. Reclamation techniques were evaluated and, where necessary, techniques were changed to improve the success of the reclamation program.

The primary objective of habitat reclamation on NPRC is to establish a diverse, stable plant community on disturbed sites with the long term goal of supporting a greater abundance and diversity of wildlife species. The habitat conservation program consists of three intermediate objectives. The first focuses on site selection and includes establishing site selection criteria and procedures. The second objective is to establish techniques for reclamation of disturbed habitat on NPR-1 and to document the success of revegetation efforts.

2.3 SELECTION OF RECLAMATION SITES

Beginning in 1985 and continuing through FY92 disturbed sites located within the boundaries of NPR-1 have been selected for reclamation. Prior to 1989, sites were selected by driving the roads in a each section and looking for disturbed sites. This method proved to be more time consuming and less efficient than was desired. Many potential revegetation sites were not detectable using this method.

In 1989 disturbance maps generated from aerial photography were used to locate trails, scraped areas, well pad sumps, borrow sites and other sites that could be considered for reclamation. Each disturbance was located in the field and was evaluated as a potential reclamation site based on (1) whether the site was abandoned and planned for future use, (2) factors limiting plant growth, such as, soil suitability (USDA Forest Service, 1979) or

soil contamination from drilling materials, (3) site accessibility to reclamation equipment, and (4) future development in the general area.

All disturbances identified during the disturbance mapping project in 1988 have now been evaluated to determine eligibility for reclamation. Approximately 650 acres of well pad sumps or diked washes were evaluated, as were 1,055 acres of borrow or scraped areas, 344 acres of trails or unnecessary roads, 445 acres of pipeline rights-of-way, and 140 acres of miscellaneous disturbances (Appendix A, Table A-1).

Abandoned facilities will become a major source of reclamation sites in the future. The Unit Operator identifies those wells that will be taken out of production. After the wells are abandoned by the Unit Operator, a description of the site and a map showing the location is sent to EG&G/EM and the site is scheduled for reclamation during the next fall reclamation season.

Contemporaneous reclamation is an ongoing activity carried out jointly by DOE, EG&G/EM and the Unit Operator. The Unit Operator monitors projects and reports to DOE when a project is completed and reclamation is required. A brief description of the site along with a site map are sent to DOE. DOE reviews the reclamation request and forwards the information on to EG&G/EM. EG&G/EM visits the site and determines what reclamation techniques should be employed and the site is scheduled for revegetation during the next fall reclamation season.

2.4 RECLAMATION TECHNIQUES

After a site is selected and approved for reclamation, specific reclamation techniques are determined. Reclamation specifications have evolved since reclamation work began on NPR-1 in 1985. Specifications were generated when reclamation work became operational in 1985. Since that time they have been reviewed by the Unit Operator, DOE, Chevron U.S.A. (CUSA), CDFG, and FWS. In 1991 the specifications were reviewed by a Task Force comprised of representatives from DOE and CUSA. Several recommendations were made by the Task Force (Chevron U.S.A., 1991), all of which have been incorporated into the specifications currently used on NPR-1 (Appendix B). Specifications shown in Appendix B are those currently used.

Briefly, reclamation procedures at NPR-1 include site preparation, seeding and mulching. Site preparation includes ripping of compacted soils, disking and harrowing to break up large soil aggregates, redistribution of stockpiled topsoil, and the addition of soil nutrients. Ripping and disking improves soil aeration, improves water infiltration, provides a looser, cooler, more moist soil for seed germination, and improves seed-to-soil contact (Vallentine, 1980).

Current Unit Operator policy and procedures specify that during any construction project, the surface 6 inches of topsoil is removed and stockpiled. Topsoil stockpiles are seeded to stabilize the soil and insure biological activity. The topsoil can then be used during reclamation of the construction site or on a site that is being reclaimed in the near vicinity. The addition of topsoil has shown to improve overall plant cover (EG&G/EM, 1989).

Once the site has been properly prepared, it is seeded. Drill seeding is the most common method of distributing seed, although seed is handbroadcasted on sites inaccessible to drill seeding equipment, primarily cut and fill slopes.

Seed mixes and rates used on NPR-1 have been tested since the early 1980s (O'Farrell and Mitchell, 1985; Wolfe, 1986; Anderson, 1987). Originally a wide range of species were used in reclamation work, because superior performing species were unknown. The use of native species was restricted since preferred native species were not available in commercial quantities. When seed is available the high cost usually prohibits its use on a large scale.

After five years of reclamation work and monitoring reclamation success, a list of preferred species has been developed for reclamation work on NPR-1. The list was reviewed and approved by the Task Force and includes shrubs, grasses and forbs (Appendix B, Table B-1). The rate of application of seed is 10-15 Pure Live Seed (PLS) lbs/acre on drill seeded sites and approximately double that amount if seed is hand broadcasted (USDA, Forest Service, 1979; Thornburg, 1982; Vallentine, 1979).

Timing for seeding of disturbed sites is critical and is completed in the fall, just prior to fall and winter precipitation (NPI, 1985; Plummer et.al., 1968; Reclamation Task Force, 1991). Under the sporadic precipitation conditions characteristic of the southern San Joaquin Valley, fall seeding affords the seeds the greatest potential for germination and establishment.

Once the site is seeded, a straw mulch is applied at a rate of 3-4,000 lbs. per acre. The mulch conserves soil moisture and adds needed organic matter to the soil (Kay, 1978; USDA Forest Service, 1979; McGinnies, 1987; NPI, 1985; Oaks, 1982; Thornburg, 1982). Good soil moisture is important for seed germination and plant establishment. The mulch increases the amount of organic matter in the soil, which in turn leads to an increase in biological activity and a more complete restoration of the site.

2.5 RECLAMATION MONITORING

The reclamation monitoring program was designed to evaluate initial plant establishment and growth, and overall condition of reclamation sites. Monitoring revegetated sites qualitatively began in 1987. Monitoring revegetated sites during the first few years is critical. It is during this time that shrubs do or do not become established and problems

become evident (Ostler & Allred, 1987; USDA Forest Service, 1979).

2.5.1 Initial Plant Establishment

2.5.1.1 Procedures

Initial plant establishment and growth are monitored during the first five growing seasons. Sampling occurs between April and June. Maps generated from the GIS database are used to locate each site that has been revegetated. At each site a visual estimate of plant cover, litter cover, and species present are recorded. The use of the site by wildlife is noted by direct observation or by signs of use such as the presence of burrows or scat. Erosion on the site is also classified into 1 of 5 subjective categories and a photograph of the site is taken for year to year comparisons. All information is recorded on a field data sheet (Appendix C).

2.5.1.2 Results

The results of such qualitative monitoring efforts have been reported in EG&G/EM technical reports (EG&G/EM, 1987; EG&G/EM, 1988; EG&G/EM, 1989; EG&G/EM, 1990; EG&G/EM, 1991). Vascular plant cover on sites reclaimed in 1985 and 1986 is lower than on sites reclaimed since 1987 (Table 3). In the first years the reclamation program was operational changes were made in revegetation techniques which may in part account for the greater cover values in more recent years. It is encouraging to note that after just a couple growing seasons vascular plant cover on sites revegetated in 1990 and 1991 is near 50%. This is most likely attributable to the above normal precipitation received during the growing seasons in 1991 and 1992.

Based on the results of qualitative evaluations, remedial action was first taken in the fall of 1991 on 32 sites that were reclaimed in previous years. The majority of the sites had been re-disturbed and reseeding of the sites was the remedial action taken. At other sites earthen berms or pipe and cable barriers were placed to discourage future inadvertent use. The 32 sites totalled approximately 10 acres.

2.5.2 Vascular Plant Cover and Shrub Density on Revegetated Sites

2.5.2.1 Procedures

Currently there are over 1,000 sites on NPR-1 that have been revegetated. In the spring of 1992 and 1993 plant cover and plant density by species were determined on a 10% subsample of sites reclaimed between 1985 and 1992. Vascular plant cover was determined by sampling 100 points along a linear transect. The length of the transect varied depending on the size of the reclamation site. If the site was large enough a 100-meter transect was used. Five points were sampled at five-meter intervals for a total of 100 points. Plant

Table 3. Total vascular plant cover on revegetated sites.

Year Reclaimed	Number of years since site revegetated		
	1	2	5
1985	Data not collected	21 %	13 %
1986	15 %	26 %	14 %
1987	19 %	31 %	40 %
1988	7 %	6 %	50 %
1989	1 %	16 %	-
1990	14 %	47 %	-
1991	51 %	53 %	-
1992	31 %	-	-

density was determined by recording the number of individuals of each species of plants found within 15 0.25 m² quadrats placed at equal intervals along the transect. Shrub density was determined by recording volumetric reading for each shrub found in a belt transect. The number of square meters sampled depended on the size of the site, but a 2-m by 100-m transect was commonly used.

2.5.2.2 Results

A total of 159 sites, representing sites reclaimed between 1985 and 1991, were randomly selected and sampled in the spring of 1992 (EG&G/EM, 1992c) and 257 sites were sampled in the spring of 1993 (EG&G/EM, 1994). Results from both years show that vascular plant cover was highest on sites reclaimed in 1985, which is not unexpected because those sites have had longer time for vegetation to become reestablished. Growing conditions seem to have a greater effect on plant cover than time. Plant cover on sites reclaimed in 1989, 1990 and 1991 was about the same as on sites reclaimed in 1985, 1986 and 1987. Vascular plant cover on sites reclaimed in 1992 was lower, but there was about 20% cover on the sites after just one growing season. Normal precipitation during FY91 and FY92 growing seasons (EG&G/EM, 1993; EG&G/EM, 1994) probably influenced plant cover more than any other factor.

Late spring rains in 1991 and favorable growing conditions in 1992 resulted in a plethora of shrub seedlings in the spring of 1991 and 1992. The number of shrubs/acre on sites reclaimed in 1987 and earlier is about 1,200. On the more recently reclaimed sites it is

closer to 2,800 shrubs/acre. Currently shrub densities are much higher on reclaimed sites than on adjacent undisturbed sites, but will probably decrease over the next few years as herbivory increases and competition for resources intensifies. Shrub seeding rates in 1992 are about 20% of what they were in earlier years (1985-1987).

2.6 RECLAMATION RESEARCH

Field testing of reclamation techniques, plant species and different ways of improving the efficiency and effectiveness of the habitat reclamation program is an ongoing process (O'Farrell and Mitchell, 1985; Wolfe, 1986). Some research plots are established as part of the overall reclamation program, other sites have been established specifically to test (1) species performance on different types of disturbance (Anderson, 1987), (2) the effect of topsoil on plant establishment and production (EG&G/EM, 1989), (3) slope stabilization techniques (EG&G/EM, 1989), and (4) the use of transplants to establish shrubs on burned lands (EG&G/EM, 1992b). Other research needs may be identified during the course of this plan and will be included in the reclamation research program for NPR-1.

3. DELIVERABLES

Information on the habitat restoration program at NPR-1 has been disseminated since the early 1980s. Reports have been prepared and distributed, papers have been presented at professional meetings, and annual briefings on not only habitat reclamation but other aspects of the endangered species program have been presented, in an effort to provide other federal and state agencies and interested parties with information on NPR-1's habitat restoration program. Although there has been no formal submission of specific information as requested by FWS (U.S. Fish and Wildlife Service, 1987, page 23), specific information relating to the on-site restoration program has been and will continue to be made available to them. The following list of deliverables represent how information will be provided to FWS.

Annual Report of the Endangered Species Program at NPRC

Reports will include information on:

- number of sites and acreage reclaimed during current FY,
- other accomplishments related to habitat reclamation during fiscal year, and
- third-party or lessee reclamation activities on NPR-1 and NPR-2.

Briefings on Habitat Restoration Program

Accomplishments and developments presented at Endangered Species Advisory Committee Meetings.

Summary of activities in annual endangered species program review.

Papers prepared for professional meetings or journals.

4. MILESTONES IN HABITAT RECLAMATION

	FISCAL YEAR													
	80	81	82	83	84	85	86	87	88	89	90	91	92	93-25
PREPARE RECLAMATION PLANS														
NPR-1 Reclamation Plan, 1985														
1985 Reclamation														
Steamflood Project														
Task Force Review of Reclamation Specifications														
Reclamation/Compensation Plan														
First Draft														
Reviews:DOE/FWS/CDFG/BPOI/CPDN														
Final														
DISTURBANCE MAPPING														
NPR-1														
NPR-2														
SELECT RECLAMATION SITES														
Ground Recon														
Disturbance Maps														
RECLAMATION OF DISTURBED HABITAT ON NPR-1														
Develop Techniques														
Operational														
Contemporaneous														
Abandonments														
LAND ACQUISITION														
NPR-1														
NPR-2														
MONITOR RECLAMATION SUCCESS														
Quantitative Evaluations														
Qualitative Evaluations														
REPORTING STATUS AND RESULTS														
Annual Reports														
Topical Reports														
Program Reviews														
Advisory Committee														

5. PERTINENT LITERATURE

- Aldon, E. F. 1982. Vegetation stability on mined spoils in the southwest. Pages 198-200. in: E. F. Aldon and W. R. Oaks (eds.). Reclamation of Mined Lands in the Southwest: A symposium. Soil Conservation Society of America, New Mexico Chapter, Albuquerque, New Mexico.
- Anderson, D. C. 1987. Evaluation of habitat restoration on the Naval Petroleum Reserve No. 1, Kern County, California. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. EGG 10282-2179. 42pp.
- Bryant, M.M. 1943. Area determination with the modified grid acreage grid. J. Forestry 41:764-766.
- Chambers, J. C. 1983. Measuring Species Diversity on Revegetated Surface Mines: An Evaluation of Techniques. USDA For. Serv. Research Paper INT-322, Intermt. For. and Range Exp. Stn., Ogden Utah 84401. 15pp.
- Chambers, J.C. and R. W. Brown. 1983. Methods for Vegetation Sampling and Analysis on Revegetated Mined Lands. USDA Forest Service General Technical Report INT-151, Intermt. For and Range Exp. Stn., Ogden Utah. 57pp.
- Chevron, U.S.A., 1991. Letter from Mr. J.M. Brady, Chevron Member of Operating Committee to D.A. Hogan, Director, Naval Petroleum Reserves in California dated February 26, 1991. Subject: NPR-1 Revegetation.
- Clary, Jr., Raimond F. 1983. Planting Techniques and Materials for Revegetation of California Roadsides. U.S.D.A. Research Report No. FHWA/USDA LPMC-2 Final Report. U.S.D.A. Soil Conservation Service, Lockeford, California. 92pp. T Appendices.
- EG&G Energy Measurements, Inc. 1987. Distribution of dens used by radiocollared San Joaquin Kit Fox on Naval Petroleum Reserve No. 1, Kern County, California, 1980-1987. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. 10282-2182. 16 pp.
- EG&G Energy Measurements, Inc. 1988. Endangered Species Program, Naval Petroleum Reserves in California, Annual Report FY87. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. 10617-2004. 36pp.
- EG&G Energy Measurements, Inc. 1989. Endangered Species Program Naval Petroleum Reserves in California. Annual Report FY88. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. 10617-2020. 57 pp.

- EG&G Energy Measurements, Inc. 1990. Biological Assessment of the Effects of Petroleum Production at Maximum Efficient Rate, Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California, on Threatened and Endangered Species. December 1990. 107 pp.
- EG&G Energy Measurements, Inc. 1991. Endangered Species Program Naval Petroleum Reserves in California. Annual Report FY89. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. 10617-2083. 49 pp.
- EG&G Energy Measurements, Inc. 1992a. Endangered Species Program Naval Petroleum Reserves in California. Annual Report FY90. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. 10617-2118. 50 pp.
- EG&G Energy Measurements, Inc. 1992b. Endangered Species Program Naval Petroleum Reserves in California. Annual Report FY91. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. 10617-2131. 71 pp.
- EG&G Energy Measurements, Inc. 1992c. Endangered Species Program Naval Petroleum Reserves in California. Annual Report FY92. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report.
- EG&G Energy Measurements, Inc. 1994. Endangered Species Program Naval Petroleum Reserves in California. Annual Report FY93. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report.
- Hutchings, S.S. and J.e. Schmutz. 1969. A field test of the relative-weight estimate method for determining herbage production. *J. Range Manage.* 22:408-411.
- Kay, B.L. 1978. Mulches for erosion control and plant establishments on disturbed sites. Agronomy Progress Report No. 87, Agricultural Experiment Station. University of California, Davis, California. 19pp.
- Küchler, A.W. 1977. The map of the natural vegetation of California. *in* M.G. Barbour and J. Major (eds.). *Terrestrial Vegetation of California*. J. Wiley and Sons, New York.
- Madrone Associates. 1979a. Liquid products pipeline, storage and railroad facilities (DOE Project 12) Biological assessment San Joaquin Kit Fox (*Vulpes macrotis mutica*), Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California. Final Project Report, U.S. Navy, OICC, Elk Hills, Western Division, NFEC, P.O. Box 40, San Bruno, California 94066.

- Madrone Associates. 1979b. Liquid products pipeline, storage and railroad facilities (DOE Project 12) Biological Assessment Blunt Nosed Leopard Lizard (*Crotaphytus* [=Gambelia] silus), Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California. Final Project Report, U.S. Navy, OICC, Elk Hills, Western Division, NFEC, P.O. Box 40, San Bruno, California 94066.
- McGinnies, W. J. 1987. Effects of hay and straw mulches on the establishment of seeded grasses and legumes on rangeland and a coal strip mine. *J. Range Manage.* 40:119-121.
- Meeuwig, R. O. and J. D. Budy. 1981. Point and Line-Intersect Sampling in Pinyon-Juniper Woodlands. USDA Forest Service Gen. Tech. Rpt. INT-104. Intermt For. and Range Exp. Stn., Ogden, Utah. 38pp.
- Mitchell, J. E. 1983. Analysis of Forage Production for Assessments and Appraisals. USDA Forest Service Gen. Tech. Rpt. RM-98. Rocky Mtn. For. and Range Exp. Stn., Fort Collins, Colorado. 26pp.
- Mosby, H.S. 1980. Reconnaissance mapping and map use. Pages 277-290. in: S. D. Schemnitz (ed.). *Wildlife Management Techniques Manual*. Wildlife Soc., Bethesda, Maryland. 686 p.
- NPI Reclamation Services. 1985. A reclamation manual: Suggested practices for lands disturbed by oil and gas development in the Bear River Divide and adjacent areas. NPI Reclamation Services, Salt Lake City, Utah. 86pp. Appendices.
- Oaks, W. R. 1982. Reclamation and seeding of plant materials for reclamation. Pages 151-150. in: E. F. Aldon and W. R. Oaks (eds.): *Reclamation of mined lands in the Southwest: A symposium*. Soil Conservation Society of America, New Mexico Chapter, Albuquerque, New Mexico.
- O'Farrell, T. P. and D. Mitchell. 1985. A habitat restoration plan for Naval Petroleum Reserve No. 1, Kern County, California. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. EGG 10282-2081. 62pp.
- Office of the Federal Register. 1987. Code of Federal Regulations: Protection of the Environment. Office of the Fed. Reg. Nat. Archives and Records Admin. July 1, 1987. 40:1030pp.
- Pielou, E. C. 1986. Assessing the diversity and composition of restored vegetation. *Can. J. Bot.* 64:1344-1348.
- Plummer, P. A., D. R. Christensen, and S. B. Monsen. 1968. Restoring Big-Game Range in Utah. Publication No. 68-3. Utah Division of Fish and Game, Ephraim, Utah. 183pp.

- Thornburg, A. A. 1982. Plant materials for use on surface-mined lands in arid and semiarid regions. U.S.D.A. Soil Conservation Serv. Rep. SCS-TA-157. Washington, D.C. 88pp.
- U.S. Department of Agriculture, Soil Conservation Service. 1987. Soil survey of Kern County, California. Naval Petroleum Reserve No. 1, Interim Report. 135 pp. U.S. Department of Energy. 1978. Petroleum Production at Maximum Efficient Rate, Naval Petroleum Reserve No. 1 (Elk Hills) Kern County, California. Draft Environmental Impact Statement. DOE/EIS-0012-D.
- U.S. Department of Energy. 1979. Petroleum Production at Maximum Efficient Rate, Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California. Final Environmental Impact Statement. DOE/EIS-0012. 493pp.
- U.S. Department of Energy. 1994. Petroleum Production at Maximum Efficient Rate, Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California. Supplement Environmental Impact Statement. DOE/xxx. xxxpp.
- U.S. Fish and Wildlife Service. 1980. February 1, 1980 AFA-SE, #1-1-80-F-2). Formal Endangered species consultation on Project 12 - Liquid Products Pipeline. Naval Petroleum Reserve Number 1 (Elk Hills), Kern County, California.
- U.S. Fish and Wildlife Service. 1987. December 16, 1987, Reference TAR/1-1-80-F-2R. Formal Endangered species consultation on the petroleum development program at maximum efficient rate at Naval Petroleum Reserve Number 1 (Elk Hills), Kern County, California.
- USDA Forest Service. 1979. User guide to vegetation. USDA For. Serv. Gen. Tech. Rep. INT-64. Intermt. For. and Range Exp. Stn., Ogden Utah. 86pp.
- USDA Forest Service. R-4 Reclamation Field Guide. USDA Forest Service, Region 4. Minerals Management. Ogden Utah. 81pp.
- Vallentine, J. F. 1979. Range Development and Improvements. Brigham Young University Press, Provo, Utah. 551pp.
- Wolfe, M. J. H. 1986a. Reclamation plan for the Shallow Oil Zone (SOZ) steam flood project, Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. EGG 10282-2109. 28pp.
- Wolfe, M. J. H. 1986b. 1985 reclamation field plan for Naval Petroleum Reserve No. 1 (Elk Hills), Kern County, California. U.S. Department of Energy Topical Report, EG&G/EM Santa Barbara Operations Report No. EGG 10282-2102. 41pp.

APPENDIX A

COMPUTATION OF DISTURBANCE ESTIMATES

1975 Disturbance Estimates

A portion of the 6,079 acres of land disturbed on NPR-1 as of 1988 (MER) were disturbed prior to 1976. To quantify the amount of land disturbed as of 1976, aerial photographs of NPR-1 taken in 1975 and a dot grid methodology (Bryant, 1943; Mosby, 1980; EG&G/EM, 1987) were used. Transparent dot grids were overlaid on aerial photographs taken in 1975. The proportion of dots intercepting disturbed and undisturbed areas was obtained. This procedure was completed for each section of land within NPR-1 boundaries. The number of acres disturbed was determined by multiplying the percentage of disturbed land within that section by the total number of acres in the section. There were 3,603 acres disturbed in 1975, which is 7% of the total NPR-1 acreage.

1988 Disturbance Estimates

In 1988 EG&G Energy Measurements, Inc. completed an inventory of disturbed parcels of land within NPR-1 boundaries. Disturbances were mapped and categorized into 1 of 14 different types of disturbance (Table A-1). This information was entered into a geographic information system (GIS) database and tabular summaries were generated. A total of 7,085 acres of land was categorized as disturbed as of June 1988.

Adjustments were necessary so 1988 disturbance estimates were comparable to disturbance estimates made in 1975. Most adjustments were made to disturbance categories that are not associated with MER activities and include disturbance categories for agriculture, aqueduct and residential disturbances. Neither the agricultural or aqueduct disturbances were included in disturbance mapping in 1975. In 1975 agriculture areas on NPR-1 were classified as undisturbed and the aqueduct did not appear on the photographs. The 1988 estimates of disturbance for these two categories, agriculture (369 acres) and aqueduct (132 acres), were subtracted from the gross number of acres disturbed. The residential area of Tupman was considered in both 1975 and 1988 disturbance estimates, however, it is not considered part of MER development and 45 acres were deleted from estimates for both years.

Taking these adjustments into account yields a gross adjusted disturbance estimate of 6,079 acres. This is obtained by reducing the gross estimate of 6,625 by 132 acres of land disturbed by the aqueduct, 369 acres of agricultural lands, and 45 acres of residential areas.

Approximately 2,598 acres were evaluated for potential reclamation. Disturbances classified as well pad sumps or gully plugs, unimproved roads, pipeline rights-of-way, soil borrow or scraped areas, and miscellaneous disturbances were considered to have the highest potential for reclamation. The remaining disturbed areas represent lands that are currently used for oil and gas production activities and include disturbances for well pads, roads, pipeline corridors, tank settings, maintained sections of the firebreak.

Approximately 1,585 acres of the 2,598 acres evaluated for reclamation potential were re-classified as naturally revegetated (Table A-1). A total of 120 acres identified as disturbed on the 1975 aerial photos were also included as a naturally revegetated disturbance on 1988 aerial photography. The 120 acres was subtracted from the original number of acres naturally revegetated (1,465 acres) so that these two categories (disturbed 1975 and naturally revegetated 1988) were not subtracted twice.

As the inventory for potential reclamation sites was made, it was discovered that many lands originally classified as disturbed, have naturally revegetated since they were disturbed, which may have been as long ago as 50 years. Classification of a site as disturbed was based on lack of vegetative cover or an alteration to the natural topography of the land. Disturbances such as old roads, trails, diked washes, etc. that may have only been used temporarily appear as disturbed land. Upon site inspection, many of these areas were found to support a vegetative cover similar to that of adjacent undisturbed lands. In some instances the degree of disturbance was more evident, but the site had revegetated to a point that, in the opinion of the plant ecologist, did not justify re-disturbing the site to seed and mulch it.

Land Disturbances Due to MER

In order to compare 1975 disturbance estimates with 1988 disturbance estimates two important factors must be taken into account. One, is the difference in disturbance estimates due to different methodologies, and the second is the difference due to observer error. To correct the methodology error a 10 sections of land were randomly selected. Using the 1988 aerial photography disturbance estimates were made for each section using the Dot Grid Methodology. Dot Grid estimates were compared to GIS estimates using a simple linear regression equation. The simple linear regression equation is:

$$\text{GIS Estimate} = -22.5415 \text{ acres/section} + (1.2315 \times \text{Dot Grid Estimate of 1988 photos}).$$

The relationship between GIS and Dot Grid was now known, however, it was still not possible to compare 1988 GIS estimates with 1975 Dot Grid estimates because different observers were used for the 1975 estimates than were used to determine the relationship between the GIS and Dot Grid methods. To determine the relationship between the observers, the same observers that used the Dot Grid method on the 1988 aerial photograph, used the Dot Grid method to estimate the percent disturbance on the same sections using 1975 aerial photography. Once again a simple linear regression was used to show the relationship. The equation is:

$$\text{Adjusted Estimate} = -7.2832 \text{ acres/section} + (1.0688 \times \text{Original Disturbance Estimate of 1975 Photography}).$$

The two linear regression equations can be combined so that GIS equivalent estimates can be calculated directly from the original estimates made from the 1975 aerial photographs. The equation is:

$$\text{GIS Equivalent Estimate} = -13.5722 + (1.3162 \times \text{original acres}).$$

Hence, the disturbance estimate made for each section using 1975 aerial photographs, is multiplied by 1.3162 and 13.5772 is subtracted. The adjusted disturbance estimates for each section are summed to provide a disturbance estimate that can be compared to the 1988 GIS estimate. Using this equation it was determined that 3,603 acres were disturbed as of 1975.

Table A-1. Results of 1988 disturbance mapping project on NPR-1.

<u>Disturbance Category</u>	<u>Gross Number Acres Disturbed</u>	<u>Acres Naturally Revegetated</u>	<u>Net Number of Acres Disturbed</u>
Well Pad	1,378	16	1,362
Well Sumps/Gully Plugs	645	490	161
Roads			
Major	344	0	344
Improved	1,288	20	1,268
Unimproved (Trail)	340	154	186
Pipeline			
Corridor	67	24	43
Right of Way	443	421	22
Facilities	634	5	634
Firebreak	223	6	217
Waste Sites	139	6	132
Borrow or Scraped Areas	1,014	445	570
Miscellaneous	11	2	9
SUBTOTAL	6,533	1,585-120=1,465	6,079
OTHER DISTUR- BANCES			
Aqueduct	132	0	132
Agricultural	369	0	369
Residential	45	0	45
SUBTOTAL	546	0	546
TOTALS	7,085	1,585-120=1,465	5,620

The 3,603 acres is subtracted from the 1988 disturbance estimate (6,079 acres) yielding the number of acres disturbed between 1975 and 1988, 2,476 acres. The 878 acres that are estimated to be disturbed through the year 2025 is added to the 2,476 acres, for a total of 3,354 acres that will be disturbed as a result of MER activities on NPR-1 (Table 4-2).

Table A-2. Calculation of number of acres disturbed as a result of oil and gas production activities under MER.

1988 Disturbance Mapping Estimate of Acres Disturbed on NPR-1 Using GIS	6,079 A
Less: 1975 Disturbance Mapping Adjusted Estimate of Acres Disturbed on NPR-1	3,603 A
Acres Disturbed between 1975 and 1988	2,476 A
Plus: Estimated Disturbances Related to MER Activities Through the 2025.	878 A
	—
Difference: 1988 Estimate less 1975 Estimate, plus Future Disturbance	3,354 A

NPR-2

In 1988 EG&G Energy Measurements, Inc. inventoried parcels of land within NPR-2 boundaries and estimated the amount of disturbance for each section. Disturbances were mapped and categorized into 1 of 14 different types of disturbance (Table A-1). This information was entered into a geographic information system (GIS) database and tabular summaries were generated. A total of 7,079 acres of land was categorized as disturbed as of June 1988.

Approximately 377 acres can be evaluated for potential reclamation. Disturbances classified as well pad sumps or gully plugs, unimproved roads, pipeline rights-of-way, soil borrow or scraped areas, and miscellaneous disturbances were considered to have the highest potential for reclamation. The remaining disturbed areas represent lands that are currently used for oil and gas production activities and include disturbances for well pads, roads, pipeline corridors, tank settings, maintained sections of the firebreak.

Approximately 474 of the 1,831 acres of the lands on NPR-2 that were originally classified as disturbed, have been re-classified as naturally revegetated (Table A-3). Classification of a site as disturbed was based on lack of vegetative cover or an alteration to the natural topography of the land. Disturbances such as old roads, trails, diked washes, etc. that may have only been used temporarily appear as disturbed land. Upon site inspection, many of these areas were found to support a vegetative community similar to that of adjacent undisturbed lands.

Table A-3. Results of 1988 Disturbance Mapping Project on NPR-2.

<u>Disturbance Category</u>	<u>Gross Number Acres Disturbed</u>	<u>Acres Naturally Revegetated</u>	<u>Net Number of Acres Disturbed</u>
Well Pad	282	17	265
Well Sumps/Gully Plugs	120	73	47*
Roads			
Major	108	0	108
Improved	482	2	480
Unimproved (Trail)	207	129	78*
Pipeline			
Corridor	4	0	4
Right of Way	39	10	29*
Facilities	123	1	122
Waste Sites	82	62	20*
Borrow or Scraped Areas	367	170	197*
Miscellaneous	17	11	6*
SUBTOTAL	1,831	474	1,357
OTHER DISTUR- BANCES			
Aqueduct	75	0	75
Agricultural	262	83	179
Residential	3	0	3
SUBTOTAL	340	83	257
TOTALS	2,171	557	1,614

* Potential reclamation, total of 377 acres.

APPENDIX B

SPECIFICATIONS FOR SITE PREPARATION AND REVEGETATION NAVAL PETROLEUM RESERVES IN CALIFORNIA KERN COUNTY, CALIFORNIA

SECTION 1. GENERAL

1.1 OBJECTIVE

This document sets the minimum requirements and specifications for preparation and revegetation of land disturbed by activities associated with the drilling and production of oil and gas. The ultimate objective of the revegetation is to rehabilitate endangered species' habitat to a condition similar to that either experienced prior to the disturbance or on adjacent areas that have not been disturbed.

SECTION 2. TECHNICAL REQUIREMENTS

2.1 GENERAL SPECIFICATIONS

2.1.1 Traffic Control

Whenever work creates a condition hazardous to traffic movement or personnel, barricades, lights, signs and other devices as are necessary to prevent accidents or injuries will be used. Loads or vehicles wider than eight feet travelling on roads must be preceded by a "warning vehicle" which has either headlights or warning lights turned on and a sign indicating the type of hazard to follow, i.e. wide load, etc.

2.1.2 Mud and Dust control

Measures shall be taken during all phases of the work to control mud and dust. All soil that impinges upon existing roadways or facilities will be removed. Removal shall be done by washing or grading as appropriate. Dust emanating from the work area and access roads will be controlled by wetting with water.

2.1.3 Working Adjacent to Parking Lots

When working on or near a parking lot, owners of parked cars or other mobile facilities are to be contacted to arrange for their safe removal from the area to prevent damage to any vehicles.

2.1.4 Staging Areas

Staging areas for supplies are restricted to three sites on NPR-1. One area is located in Section 2G, north of Skyline; one in Section 18G behind Gate 45; and an area inside the warehouse area in Section 36S.

2.2 SITE PREPARATION REQUIREMENTS

Site preparation consists of site clean-up, ripping to alleviate soil compaction, disking to break-up soil aggregates, installation of erosion control structures, addition of soil amendments, and other tasks as may be necessary to properly prepare the seedbed. Site specific reclamation procedures are given in a pre-reclamation site inventory prepared for each site and are shown in attachment A.

2.2.1 Site Clean-up

Miscellaneous foreign materials will be removed to an approved disposal site to assure safe site access. Clean-up may include the removal of abandoned pipes, timbers and other debris. Waste shall be hauled to a permitted dump off site. Site clean-up also includes the removal of asphalt, which usually follows ripping of the site.

2.2.2 Ripping

Compacted areas such as abandoned roads, well pad surfaces or staging sites will be ripped to a minimum depth of 6 inches or to the depth indicated on the reclamation record. Ripping will be on dry soils. Roads containing asphalt will be ripped at a depth sufficient to remove all asphalt and leave an non-compacted, yet firm, seedbed. All asphalt will be hauled to a permitted dump off site. Average thickness of asphalt is 3 inches. Fugitive dust control will be as required by law.

2.2.3 Disking

Areas ripped and other surfaces with safe access (a slope of (3:1) will be disked to a depth of 4 inches with an offset disk fitted with a drag chain. Disking will be on the contour and done in a manner to avoid rilling and future serious erosion problems.

2.2.4 Erosion Control/Recontouring

Erosion gullies, berms along roads, and holes shall be filled to blend with the existing topography, to assure proper erosion control and to create a suitable seedbed. The replacement of topsoil will be done when possible. This includes but is not limited to the spreading of topsoils scraped to the side of roads and pipeline rights of way.

Water bars will be constructed on all abandoned roads and pipeline routes according to the following guidelines:

- 2% grade - 200 feet spacing,
- 2-5% grade - 100 feet spacing,
- 4-5% grade - 75 feet spacing,
- >5% grade - 50 feet spacing.

Waterbars will be constructed to drain freely to the natural ground level and to prevent siltation and clogging. The water bar should be a minimum of 1 foot deep, side slopes 2:1 or flatter to allow traffic if necessary, and a grade of 1-3%, sufficient to drain into adjacent natural vegetation.

2.2.5 Soil Amendments

Necessary soil amendments will be applied by the subcontractor prior to seeding and disking in the following amounts:

Phosphorus	20 lbs/acre in form of P_2O_4
Nitrogen	20 lbs/acre

Amounts are for actual amounts/acre of each element. Fertilizer will only be applied on sites where a straw or native hay mulch is used.

2.2.6 Miscellaneous Site Preparation

The surface soils of pipeline rights of way or abandoned roads that are to be revegetated due to repeated vehicular travel frequently become too powdery for successful reseeding. Drill seeding, mulching and crimping are ineffective because both mulch and seed are buried at unacceptable depths (Section 2.3.1). Such soils shall be (1) artificially watered, or (2) delay revegetation until after the initial fall precipitation and the soil structure improves, or (3) mulch and crimp 3-4 tons/A of straw during site preparation, followed by seeding. An additional mulching and crimping may be necessary depending on the depth of the powdery soil and effectiveness of the original mulching.

2.3 REVEGETATION SPECIFICATIONS

Following site preparation seed will be placed in the soil by either drill seeding or hand-broadcast seeding. Mulching and tacking of the mulch will occur after seeding is completed.

2.3.1 Drill Seeding

Drill seeding will be accomplished with a mechanical power-drawn drill followed by a drag

chain or packer wheels. Seeding depth will be between 1/4 inch and 1/2 inch with drill rows approximately 7 inches apart. Drill seeding will be done on areas with slopes of less than 2:1 (horizontal:vertical) and are accessible. Species included in the seed mix and the approximate rates they will be seeded is shown in Table D-1.

2.3.2 Hand broadcasting

Broadcast seeding will occur on sites inaccessible to a mechanical drill seeder or mulcher. The rate of seed application will be twice the rate used for drill seeding.

2.3.3 Mulching

All seeded areas (except those in 2.3.2) will be mulched with straw or native hay within 24 hours of seeding. Straw/native hay will be placed at a rate of 2 tons/A and where slope and accessibility permit crimped with a Caltrans (sheepfoot) type crimper immediately after. The minimum stem length for the straw mulch will be 6 inches.

On sites that are broadcast seeded the straw or native hay mulch will be hand broadcast at a rate of 1.5-2 tons/A. The straw will be secured with a 6-9 month photodegradeable netting. The top and bottom of the netting will be stapled at 1.5 foot intervals. U-shaped staples (6 inches long on rocky or compacted soils, and 12 inches on deeper soils) will be used. Staples will be placed at 3 foot intervals throughout the netting. The top and sides of the netted slope will be buried a minimum of 4 inches. Minimum stem length for the straw will be 6 inches.

SECTION 3. QUALITY ASSURANCE/QUALITY CONTROL

3.1 TIMING

Seeding, mulching and crimping will begin in October and be completed by November 30.

Work hours are from daylight to dark, seven (7) days per week.

3.2 RECORD KEEPING

3.2.1 Reclamation Record

The date sites are prepared for revegetation, the date planted, treatments applied, etc., are recorded on the Reclamation Record section of the Habitat Reclamation Pre-Reclamation Inventory form (Attachment D-1). Each form will be signed by the person actually supervising the field work, so procedures are verified.

When revegetation is completed at each site the reclamation subcontractor submits within 5 working days a completed Reclamation Record for that site to the Habitat Reclamation Specialist.

SECTION 4. EQUIPMENT/MATERIALS REQUIREMENTS

4.1 EQUIPMENT

4.1.1 Site Preparation

Equipment needed to complete site preparation work will include a 4 wheel drive tractor or a dozer. Other equipment needed to complete site preparation work may include, but not be limited to, a front-end loader, dump truck, and disk plow. The equipment will be of a size to most efficiently complete the work and minimize disturbance to adjacent undisturbed habitat.

Two wheel drive tractors or trucks will not be used to rip, disk, seed, or mulch sites, unless written approval is given by the contractor.

4.1.2 Drill Seeder

The seed drill shall be of a native seed type with a minimum of two boxes designed for large and small seed and agitators to keep the seeds mixed. The drill rows shall be approximately 7 inches apart and the drill shall have depth bands capable of placing seed at a maximum depth of 1/2 inch. The drill shall be a Truax, Rangeland or Tye type native seed drill capable of drilling fluffy seed mixes and with rear packer wheels or chains.

4.1.3 Straw Blower

The straw blower shall be of a Bowie, Finn or Reinco type and shall be able to blow a distance of 70 feet to 100 feet.

4.1.4 Crimper

The hay crimper may be of the sheep's foot or Caltrans roller puncher type.

4.2 MATERIALS

4.2.1 Contractor Furnished Materials

Fertilizer and other soil amendments.

Seed.

4.2.2 Contractor Furnished Drawings

Regional Map (1 inches = 1,250')

Detailed section maps showing the location of each site to be rehabilitated (1 inch = 400 feet).

Reclamation specifications for each site to be revegetated.

4.2.3 Reclamation subcontractor Furnished Materials and Equipment

Except as specified in 4.2.1, the reclamation subcontractor shall furnish all materials and equipment to complete the specified work.

Rice straw, delivered and stacked.

SECTION 5.0 - SAFETY/SECURITY

5.1 SAFETY

5.1.1 Safety Plan

All parts of the Unit Operator's Policy and Procedure Manual of Safety and Health (Vol. 12) and Cal-OSHA Safety codes that are related to the work will be followed. This includes, but is not limited to motor vehicle safety, safe use of tools and equipment, fire protection, etc. Violation of safety standards on NPR-1 may result in the denial of access to the work site. All infractions will be reported to the contractor's Habitat Restoration Specialist within 12 hours of the time of occurrence.

5.1.2 Safety Briefing

A safety briefing mandatory for all reclamation subcontractor personnel will be held prior to initiation of any on-site work. The briefing will be conducted by the Unit Operator safety officer or as he may appoint.

5.1.3 Environmental Briefing

An Environmental briefing will be conducted by the Environmental Services Department of the Unit Operator prior to any on site work.

5.1.4 Equipment Inspection

All equipment is subject to inspection for safety reasons at anytime, either by the Unit Operator or the contractor.

5.2 SECURITY

A list of all reclamation subcontractor personnel that will be working on site will be provided to the contractor a minimum of 10 working days prior to the anticipated start date. Access to NPR-1 will not be possible without such documentation.

The reclamation subcontractor will meet with the Security Office prior to the beginning of any work on NPR-1.

Table B-1. Seed Mix Composition

Lifeform	Genus	Species	Common Name	Seeding Rate PLS ¹ LBS/A
-----	-----	-----	-----	-----
Shrub	<i>Atriplex</i>	<i>lentiformis</i>	Valley saltbush	0.5
	<i>Atriplex</i>	<i>polycarpa</i>	Cattle spinach	0.5
	<i>Atriplex</i>	<i>semibaccata</i>	Australian saltbush	0.1
	<i>Atriplex</i>	<i>spinifera</i>	Spiny saltbush	0.5
	<i>Ceratoides</i>	<i>lanata</i>	Winterfat	2.0
	<i>Eriogonum</i>	<i>fasciculatum</i>	California buckwheat	2.0
	<i>Hymenoclea</i>	<i>salsola</i>	Cheesebush	1.0
	<i>Isomeris</i>	<i>arborea</i>	Bladderpod	3.0
Grass	<i>Festuca</i>	<i>megalura</i>	Zorro fescue	2.0
	<i>Schismus</i>	<i>barbatus</i>	Mediterranean grass	0.1
Forbs	<i>Trifolium</i>	<i>hirtum</i>	Rose clover	1.0
	<i>Lupinus</i>	<i>densiflorus</i>	Golden lupine	0.1
	<i>Phacelia</i>	<i>tanacetifolia</i>	Tansy Phacelia	0.1

¹ Pure Live Seed=Percent Germination x Percent Purity

**ATTACHMENT B-1
HABITAT RECLAMATION
Pre-Reclamation Inventory**

SITE USED: Y N
LIMITING FACTORS: Y N
ACCESS: Y N
FUTURE USE: Y N

Reclamation Number: _____ Year: _____
Well No./Name: _____ Sect #: _____ Sect Ltr: _____
SCS Soil Map Unit: _____ Veg Type: _____ Aspect: _____
Slope: _____ Size: _____ X _____ = _____ (Total Acres)
Type of Disturbance: Fill / Cut / Pad / Borrow / Sump / Roadway / Pipeline / Burn / Other
Description: _____
Erosion Classification: 1-Stable / 2-Slight / 3-Moderate / 4-Critical / 5-Severe
Den Present: Yes No Preactivity Survey Needed: Yes No

RECLAMATION RECORD				
SITE PREPARATION		Date Completed	Supervisor	Comments/Changes
Task to be Completed	% of Site			
SEEDING				
Method:				
MULCH				
Method/Type:				
Rate:				
Secure:				

**APPENDIX C
HABITAT RESTORATION
QUALITATIVE ASSESSMENT**

Site Identification	
Reclamation No: _____ Year Reclaimed: _____	Location: _____ Section/Township: _____ Type of Disturbance: _____

Site Status	
Photo Record: Roll #: __ Slide #: __ Observer(s): _____	Site Disturbed since revegetated: YES NO Type of Disturbance: _____ Remedial Reclamation Recommended: YES NO

Cover		
Total Vascular Plant Cover (%): _____ Litter (%): _____	Bare Ground (%): _____ % of Adjacent Undisturbed: _____	% Shrub: _____ % Forb: _____ % Grass: _____

Erosion				
1-Stable	2-Slight	3-Moderate	4-Critical	5-Severe

Wildlife Use of Site																								
Evidence of Herbivory: YES NO Small Mammal Burrows Present: YES NO Dens Present: YES NO	<table style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="3" style="text-align: left; padding: 5px;">Scat Observed</th> </tr> <tr> <td style="width: 33%;">Lagomorph</td> <td style="width: 33%;">Rodent</td> <td style="width: 33%;">Coyote</td> </tr> <tr> <td>Fox</td> <td>Other _____</td> <td></td> </tr> </table> <table style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="3" style="text-align: left; padding: 5px;">Wildlife Observed</th> </tr> <tr> <td style="width: 33%;">Lagomorph</td> <td style="width: 33%;">Rodent</td> <td style="width: 33%;">Coyote</td> </tr> <tr> <td>Fox</td> <td>Grnd Sqr</td> <td>Quail</td> </tr> <tr> <td>Other Bird</td> <td>Other: _____</td> <td></td> </tr> </table>			Scat Observed			Lagomorph	Rodent	Coyote	Fox	Other _____		Wildlife Observed			Lagomorph	Rodent	Coyote	Fox	Grnd Sqr	Quail	Other Bird	Other: _____	
Scat Observed																								
Lagomorph	Rodent	Coyote																						
Fox	Other _____																							
Wildlife Observed																								
Lagomorph	Rodent	Coyote																						
Fox	Grnd Sqr	Quail																						
Other Bird	Other: _____																							

FORM NO. 3530-132
REV: MARCH 1994
SUPERSEDES: APRIL 1990

DISTRIBUTION

U.S. Department of Energy,
Naval Petroleum Reserves in California
Tupman, California

D. A. Hogan (2)
J. C. Killen

U.S. Department of Energy, Office
of Naval Petroleum and Oil Shale Reserves
Washington, D.C.

Capt. E.R. Hunter
D. Silawsky

U.S. Department of Energy,
Nevada Operations Office
Las Vegas, Nevada

Technical Information Officer

USDOE/HQ
Oakridge, Tennessee

OSTI (2)

U.S. Department of Interior,
Fish and Wildlife Service
Sacramento, California

P. Cross

California Department of Fish and Game
Sacramento, California

R. Schlorff

Chevron U.S.A Production Company
Bakersfield, California

J. M. Brady (2)
D. Vroom

Chevron Research and Technology Company
Rickmond, California

P. Y. O'Brien

Bechtel Petroleum Operation, Inc.
Tupman, California

Environmental Services Department (2)

Enterprise Advisory Services, Inc.
Tupman, California

M. Phillips

EG&G/EM LVAO
Las Vegas, Nevada

P.H. Zavattaro
Technical Information Center

EG&G/EM NV Program
Las Vegas, Nevada

J. Michael
T. P. O'Farrell

EG&G/EM Environmental
Sciences Division
Las Vegas, Nevada

D. C. Anderson
W. K. Ostler

EG&G/EM Environmental
Sciences Division
Tupman, California

D. A. Craghill
B. L. Cypher
N. Frost
H. J. Hill
K. A. Spencer
G. D. Warrick
L. White