Depleted Uranium: A DOE Management Challenge

October 1995

U.S. Department of Energy
Office of Environmental Management
Office of Technology Development

This report has been reproduced directly from the best available copy.

Available to DOE and DOE Contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401.

Available to the public from the U.S. Department of Commerce, Technology Administration, National Technical Information Service, Springfield, VA 22161, (703) 487-4650.

Printed with soy ink on recycled paper

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, make any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

Depleted Uranium: A DOE Management Challenge

October 1995

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

U.S. Department of Energy
Office of Environmental Management
Office of Technology Development
Washington, DC 20585

EXECUTIVE SUMMARY

The U.S. Department of Energy (DOE) has a management challenge and financial liability in the form of 50,000 cylinders containing 555,000 metric tons of depleted uranium hexafluoride (UF_6) that are stored at the gaseous diffusion plants. The annual storage and maintenance cost is approximately \$10 million. This report summarizes several studies undertaken by the DOE Office of Technology Development (OTD) to evaluate options for long-term depleted uranium management.

Based on studies conducted to date, the most likely use of the depleted uranium is for shielding of spent nuclear fuel (SNF) or vitrified high-level waste (HLW) containers. The alternative to finding a use for the depleted uranium is disposal as a radioactive waste.¹ Estimated disposal costs, utilizing existing technologies, range between \$3.8 and \$11.3 billion, depending on factors such as applicability of the Resource Conservation and Recovery Act (RCRA) and the location of the disposal site.

The cost of recycling the depleted uranium in a concrete based shielding in SNF/HLW containers, although substantial, is comparable to or less than the cost of disposal. Consequently, the case can be made that if DOE invests in developing depleted uranium shielded containers instead of disposal, a long-term solution to the UF_6 problem is attained at comparable or lower cost than disposal as a waste.

Two concepts for depleted uranium storage casks were considered in these studies. The first is based on standard fabrication concepts previously developed for depleted uranium metal. The second converts the UF_6 to an oxide aggregate that is used in concrete to make dry storage casks.

The concept for using uranium metal as shielding has depleted uranium metal sandwiched between stainless steel shells that form a storage cask. The outer stainless steel shell is sufficiently thick to meet the structural requirements for transportation as well as storage. Neutron shielding is provided by an external polyethylene shell with fins for heat dissipation. This cask concept uses an inner canister functionally similar to the DOE Office of Civilian Radioactive Waste Management (OCRWM) multi-purpose canister (MPC) containing 21 PWR assemblies.

This uranium metal cask option appears technically feasible but, because of the high cost of converting UF_6 to metal and the high cost of uranium metal fabrication, the estimated cost for these casks is substantially higher than current prices for concrete dry storage systems.

This cost issue gave rise to a different cask concept in which the large aggregate in concrete is replaced by an aggregate made from uranium oxide. The concept uses thin walled stainless steel shells to hold the concrete containing the depleted uranium aggregate. The shells could be fabricated from recycled stainless steel from DOE facilities. Although this concept has not been demonstrated, proof-of-principle experiments on materials and design studies on container concepts have shown it to be a reasonable concept.

1. Although the specific radioactivity of depleted uranium is very low and will not interfere with use of the material as shielding, the uranium is still radioactive and disposal as a radioactive material is required.

This depleted uranium concrete concept is estimated to cost about one third of the depleted uranium metal concept. Compared to conventional concrete storage systems, the total weight of the depleted uranium dry storage cask system is about 35 tons less and the concrete storage cask diameter is 40 in. smaller. The technical feasibility of producing a low-cost aggregate remains to be demonstrated but does have precedents for non-nuclear ceramics.

Engineers at ORNL, LANL and INEL have developed concepts that are projected to lower the cost of uranium metal production from UF_6 by using a continuous metallothermic furnace or a plasma reactor. However, even if the conversion costs of UF_6 to uranium metal are reduced to zero, the fabrication costs for depleted uranium metal make the DU metal casks considerably more expensive than is projected for concrete casks with depleted uranium aggregate. Major reductions in depleted uranium metal fabrication cost are needed to make metal containers an economically viable option.

1.0 INTRODUCTION

1.1 Background

The Department of Energy has been enriching uranium for defense and commercial nuclear fuel purposes since the 1940s. The enrichment process produces large quantities of depleted uranium (DU), i.e., uranium containing less than 0.7% of its ^{235}U isotope (the assay of most of the DU inventory is 0.2 to 0.5%). Over the years, this DU has been stored at the three uranium enrichment sites, in 10- and 14-ton steel cylinders, as pure (99.9%) solid uranium hexafluoride (UF_6).

As of March 31, 1994, there were 555,000 metric tons of UF_6 (equivalent to 375,000 metric tons of uranium metal) stored in 50,000 cylinders throughout the DOE complex (Reference 1). Since the United States continues to enrich uranium for commercial nuclear power customers in the U.S. and abroad, approximately 2,500 cylinders are added to this inventory per year. However, since July 1, 1993, UF_6 generation has been the responsibility of the U.S. Enrichment Corporation.

Most of the cylinders containing DU are sitting in the open on concrete pads or on gravel beds. Some have been stored for over 40 years. Until recent changes in world affairs, there was no thought of doing anything with the DU other than storing it until it could be used for further enrichment or as fertile blanket material for breeder reactors. Minor quantities of DU are used for tank armor and/or for armor-piercing penetrators on artillery shells. These latter uses continue, but the demand is very small. While the DOE Field Office in Oak Ridge reported that only about a half dozen of the 50,000 UF_6 -filled containers have leaked, public perception is that these DU containers pose still another risk of a DOE pollution.

During the last several years, environmental officials from the State of Ohio have posed the question as to whether DU is a waste. DOE's position is that DU is a "source material" under terms of the Atomic Energy Act of 1954, as amended, not a waste, and not subject to the Resource Conservation and Recovery Act (RCRA). One exemption from stringent storage and disposal regulations that RCRA affords owners of hazardous waste is designation of the waste as a "Recyclable Material". However, to meet the definition of recyclable there must be a specific beneficial use identified for the material.

1.2 DOE Environmental Management Challenge and Response

In the summer of 1992, the DOE Office of Technology Development (OTD, EM-50) began to explore whether the large stores of DU could indeed be used for radiation shielding in spent nuclear fuel or high-level waste storage casks, or in other products. In FY 1993, EM-50 initiated a series of studies, using both DOE laboratories and private sector subcontractors, to better understand options available for disposal of the UF_6 and to evaluate possible uses for the depleted uranium. Lastly, since the potential uses of depleted uranium are a strong function of cost, other studies were initiated to identify possible technology development that might reduce these costs. It was intended that these studies provide a basis for establishing future DOE policy and research directions for depleted uranium storage, disposal, or future use. These studies and the respective contractors are listed below:

- 1) Depleted Uranium Disposal Options Evaluation [SAIC-Idaho/INEL]: The study identified and evaluated the viable options for disposal of DU. The conversion of the UF_6 to a stable chemical form,

regulatory requirements, and functional/operational parameters were considered in estimating the cost of disposal of the DU as a low-level waste. Additionally, the cost impact on disposal of DU if it were ever declared a RCRA waste was estimated (Reference 2);

2) HLW Transport and Disposal Evaluation [Sandia National Laboratory]: The study examined the use of DU metal as shielding material in a storage and transportation cask for DOE's vitrified HLW. The study assessed the cost advantages/disadvantages of several DU HLW cask options throughout the defense high-level waste management program (Reference 3);

3) Commercial Capabilities Review [Technics Development Corp.]: A market survey was performed to assess the commercial capabilities and costs for conversion of UF_6 to UF_4 and uranium metal and for fabrication of DU metal components. Additionally, regulatory and strategic issues associated with DU recycling were identified (Reference 4);

4) Federal Capabilities Review [ORNL]: A survey of depleted uranium conversion and manufacturing capabilities of the Federal government was performed. The study included identification of areas for manufacturing technology development (Reference 5);

5) Depleted Uranium Management Alternatives [SAIC-Idaho/INEL]: The study looked at the costs of two management alternatives for depleted uranium -- continued storage and conversion of UF_6 into metal for use in a spent fuel storage and transportation cask. A preliminary, conceptual SNF cask design was developed and costs for production estimated (Reference 6);

6) Development of DUCRETE [INEL]: Concrete mixtures containing UO_2 fuel pellets were studied (concrete with DU aggregate is called DUCRETE). Mixtures of conventional concrete and DUCRETE were fabricated and cured in identical conditions. The samples were subjected to compression and tensile testing. Results from the testing established the adequacy for spent fuel storage cask applications (Reference 7);

7) Depleted Uranium Concrete Container Feasibility Studies [PACTEC/INEL and SNC/INEL]: Two independent studies were performed to assess the feasibility of using depleted uranium in concrete as a substitute for conventional aggregate. The depleted uranium oxide concrete, DUCRETE, was shown to have tremendous shielding advantages for applications such as spent fuel storage casks. Feasibility was clearly established and major weight reductions and diameter reductions were identified. These studies identified potential significant advantages to the use of a material where the uranium (gamma shielding) and the hydrogen (neutron shielding) can be varied somewhat independently based on the aggregate to cement and water ratio (References 8 and 9);

8) Conceptual Design of A Transportable DUCRETE Storage Cask [SNC/INEL]: This study evaluated the concept of using a DUCRETE dry storage cask inside of a stainless steel overpack for transport to the repository. Although feasible, the design concept is substantially more complex due to heat transfer limitations during transport (Reference 10);

9) Comparative Economics for DUCRETE Spent Fuel Storage Cask Handling, Transportation, and Capital Requirements [SNC/INEL]: This study compared conventional concrete storage casks to DUCRETE casks on a life-cycle cost basis for three time frames and three utility sizes. Significant economies were identified for the DUCRETE storage system when the cask was used for reactor storage and as a disposal overpack in the geologic repository (Reference 11).

10) Depleted Uranium Plasma Reduction System Study [MK/INEL]: This study provides a life-cycle cost estimate of the production of uranium metal with an advanced process that uses a plasma reactor to produce uranium metal and anhydrous hydrogen fluoride gas (Reference 12).

11) Depleted Uranium Market Study (Kaplan): This study found that the only large market potential for depleted uranium was shielding applications.

These studies provided sufficient information to identify the future disposal cost liability to the Department of Energy if the depleted uranium were disposed as waste and the cost of several potential recycle/reuse options for shielding applications. During these studies, the participants also looked at potential ways to reduce the costs of UF_6 conversion and uranium fabrication with the purpose of identifying emerging technologies that might provide a major cost reduction to some facet of the disposal process or future use options. Specific future technologies that were identified are:

Plasma Conversion of UF_6 to Uranium Metal. Researchers at both INEL and LANL have been active in adapting high temperature plasmas reactors to new chemical processing concepts that minimize the creation of secondary waste streams. INEL has successfully achieved reduction of UF_6 at the laboratory scale using a plasma reactor.

Continuous Metallothermic Reduction. Under sponsorship of the DOE Advanced Vapor Laser Isotope Separations (AVLIS) Program, a continuous metallothermic reduction process for UF_6 has been developed at ORNL. This process combines UF_6 reduction with alloying uranium with iron to produce a lower melting point eutectic. This alloy will have nearly identical shielding properties as uranium metal. Although this method of conversion of UF_6 to uranium metal is expected to be lower cost than the Ames process used at Fernald, it still produces a MgF_2 waste stream that is expected to be slightly radioactive and costly to dispose as low-level waste. Costs of fabrication of this metal alloy are not known.

Depleted Uranium Concrete (DUCRETE). A major barrier to widespread use of uranium metal in shielded casks is the combined cost of UF_6 conversion to metal and fabrication of the metal to a shape. INEL has conceived a concept that would use the depleted uranium oxide as an aggregate in concrete. DUCRETE is expected to have density of about 450 lb/ft³. Using DUCRETE instead of conventional concrete, the size and weight of a spent fuel storage cask is reduced substantially. The UF_6 would first be converted to an oxide, then the oxide would be formed into aggregate. The conversion of UF_6 to an oxide is the same as would be incurred for the disposal option, and the formation of an aggregate can be argued to be the best and lowest cost stabilization method for the oxide powder. Thus, the fabrication cost of a DUCRETE cask is expected to be comparable to conventional concrete casks if the aggregate is supplied by the DOE instead of disposal.

UF_6 Reduction to Oxide. The disposal cost studies used published estimates for UF_6 conversion to U_3O_8 of \$8.40/kg-U. Over the duration of this project, various companies interested in performing the UF_6 conversion services for DOE have suggested that prices closer to \$4 to \$5/kg-U could be expected in a competitive bid process. This expected cost reduction is from companies that produce nuclear fuel and/or from companies active in production of UF_6 as feed material to the enrichment plants. This reduction in cost will reduce both the cost for disposal and the cost of implementing the DUCRETE cask option by about \$1.5 billion if the entire UF_6 inventory is converted to oxide.

Advanced UF_6 conversion methods produce anhydrous hydrogen fluoride which has a recycle value of \$1000 to \$1500 per ton. This not only reduces the cost of UF_6 conversion, it precludes conversion of aqueous hydrogen fluoride to calcium fluoride and disposal as a radioactive waste. The anhydrous HF can be used to fluorinate uranium or sold for other purposes.

If spent fuel and high-level waste storage and disposal canisters were made with DU as shielding (either in metal or DUCRETE form), the following could result:

- 1) The maintenance, re-packaging, and future storage costs of UF_6 would be phased out. Storage sites could be remediated and released. Recyclable UF_6 storage cylinders could be made available to the U.S. Enrichment Corporation for reuse once emptied.
- 2) Shielded casks using DU could be used by utilities for storage of spent fuel or used by DOE for spent fuel and high level waste. Cask conceptual designs developed during this project are compatible with the DOE Multi Purpose Container planned for the storage of commercial nuclear fuel.
- 3) Decisions on actual disposal of DU could be postponed until the decision is made to place the shielded cask into a repository. Future international energy supply conditions could make DU a viable source of fertile material for breeder reactors. Recovery of the uranium from the concrete is very feasible if energy supplies justify recovery.
- 4) The future decontamination and decommissioning of shielded storage facilities for the high-level waste glass would be unnecessary as the self-shielded casks could be sent to the repository or other disposal site.

This report summarizes the findings of the studies introduced above and presents conclusions drawn from that information. DOE is reviewing all of this material in a planned Environmental Impact Statement to determine the most responsible course of action.

2.0 DEPLETED URANIUM FEASIBILITY STUDY RESULTS

2.1 Depleted Uranium Disposal Alternatives

SAIC-Idaho was contracted by INEL to study disposal options and costs for depleted uranium (Reference 2). It was concluded that, due to both cost and regulatory/political considerations, disposal of DU is only feasible at existing DOE sites. Since UF_6 reacts with water to form uranyl fluoride and hydrogen fluoride gas at relatively low temperatures, it is an unsuitable chemical form for disposal. Thus, uranium oxide (U_3O_8) was considered the preferred chemical form for disposal. This observation is consistent with UF_6 management practices in England and France.

The cost for conversion of UF_6 to oxide, packaging, transportation, permitting, and disposal as a low-level waste ranged from \$9.50/kg-U at the Nevada Test Site (NTS) to \$15.00/kg-U at the Hanford site. Under the premise that the UF_6 might be declared a RCRA waste, these costs escalate to at least \$18.56 and \$30.19/kg-U for the same disposal sites².

2. At the time of the study, NTS was considering the acceptance of Mixed Waste (Containing RCRA controlled materials in addition to radionuclides). At this time, officials at NTS have no such plans. Thus, only Hanford might be a suitable future RCRA material site.

Disposal costs were also estimated for uranium in metal form as it was thought the higher effective packing density might provide a cost advantage if environmental considerations were acceptable. Only LLW disposal at the NTS was considered. The U.S. Army has set a precedent for acceptance of DU metal encapsulated in concrete at the NTS. However, total costs estimated for DU metal disposal were about the same as for oxide disposal, primarily due to the higher cost of conversion of UF_6 to metal. The comparison between disposal as an oxide and disposal as a metal is quite unfavorable to the metal if the reduced cost of advanced UF_6 conversion to oxide methods as discussed in Section 2.1.2 is used.

2.1.1 Adjustments for Changes in Disposal Option Basis

Total cost for disposal in the SAIC study was based on a June 1992 inventory of 534,000 metric tons of UF_6 (361,000 MT of uranium metal). The total disposal cost estimated ranged from a low of \$3.4 billion (as LLW at the NTS) to a high of \$10.9 billion (as RCRA waste at Hanford). Adjusting these costs to the updated inventory of 555,000 metric tons makes the range of the disposal option \$3.5 to \$11.3 billion. Since this study was completed, disposal fees at the NTS have also increased;³ the impact of the increased disposal fee for disposal of oxide as LLW at NTS is significant. Adjusting for the increase in the NTS low-level waste disposal fee from \$10 to \$30/ft³ increases the cost of this option by \$320 million. Table 1 summarizes the disposal costs after these adjustments for all of the disposal options.

2.1.2 Cost Reduction Options

In all disposal options, the dominant cost is conversion of UF_6 to oxide or metal. The second largest cost element is disposal of the CaF_2 or MgF_2 as LLW. If technology advances can, as claimed by industry, reduce the conversion cost to about half of that used in the original study and eliminate the fluoride wastes (by producing anhydrous hydrogen fluoride which can be resold rather than calcium or magnesium fluoride which must be disposed as LLW), then substantial reductions in the conversion to oxide and disposal costs can be expected. The adjusted totals would be \$1.9 billion for LLW at the NTS and \$2.5 billion at Hanford. Note that this

Table 1. Disposal Options Cost Summary (375,000 MTU Basis)

Disposal Form	Disposal Location	Total Cost (Billions)
LLW Oxide	Nevada Test Site	\$3.8
	Hanford	\$5.6
RCRA Oxide	Nevada Test Site	\$7.0
	Hanford	\$11.3
LLW Metal	Nevada Test Site	\$3.9
SAIC cost estimates adjusted to DU inventory of 375,000 MTU and current disposal fees		

3. A disposal fee of \$10/ft³ was used in Reference 2. Per telecon, W. J. Quapp with Carl P. Gertz, DOE NV, LLW Manager (4/5/95), the fee for LLW at NTS as of October 1996 will be \$17/ft³ for DOE sites. For trade-off studies such as this, the estimated full cost recovery of \$30/ft³ should be used.

cost reduction assumes a price of \$4.20/kg-U or one half of that used in the SAIC study. For the RCRA costs for the disposal at Hanford option, if one assumes the conversion cost is also reduced by half and no CaF_2 is created for disposal, the cost becomes \$4.8 billion. Actual costs for conversion will not be known until a procurement is executed.

Another cost reduction option is to reduce the volume of material disposed. Using DU oxide aggregate, a ceramic aggregate with a bulk density of about 8 g/cm^3 , for the disposal waste form instead of U_3O_8 powder results in a substantial disposal volume reduction, with attendant cost reductions for disposal containers and the disposal fee.⁴ It was assumed that this solidification process would preclude the separate stabilization step required for U_3O_8 powder to meet the Hanford waste acceptance criteria. Consequently, the use of DU oxide aggregate produces large volume reductions, 66% for NTS and 83% for Hanford, with savings of \$300 to \$600 million in packaging and disposal costs⁵.

Costs of the existing conversion technology and potential new technologies are compared in Table 2.

Table 2. Total Cost Comparison With Technology Advancements (375,000 MTU Basis)	
	Cost(Billions)
<i>Existing Conversion Technology</i>	
Oxide LLW Disposal (NTS & Hanford)	\$3.8 to \$5.6
Oxide RCRA Disposal (Hanford)	\$11.3
Metal LW Disposal (NTS)	\$3.9
<i>New Plasma UF6 Reduction</i>	
Metal LW Disposal	\$1.8
<i>Advanced UF6 Conversion & Elimination of CaF_2</i>	
Oxide LW Disposal (NTS & Hanford)	\$1.9 to \$2.5
Oxide RCRA Disposal (Hanford)	\$4.7 to \$6.6
<i>Advanced UF6 Conversion to Oxide and DU Oxide Aggregate</i>	
LW Disposal (NTS & Hanford)	\$1.6 to \$1.9
RCRA Disposal (Hanford)	\$2.4 to \$3.4

4. Depleted Uranium (DU) oxide aggregate density used for the estimated cost reduction was 8 g/cm^3 ; values of 9 have been achieved in laboratory samples.

5. Although DU oxide aggregate was conceived for use in DUCRETE, it is believed to be an excellent disposal media because of its chemical inertness and projected low cost of production.

2.2 Shielding for Defense High-Level Waste

The Sandia National Laboratories (SNL) study evaluated the system costs of using depleted uranium metal casks for storage and transportation of the vitrified HLW instead of vault storage as is planned at Savannah River Laboratory (Reference 3). In the SNL study, the economic effect of various cask sizes was evaluated. The study concluded that between 81,000 and 95,000 metric tons of DU could be used in HLW canisters. Using a 3% cost escalation factor and 1993 dollars, costs of a total system range from \$4.1 to \$6 billion (or \$51-74/kg-U used in the casks). However, the cost estimated in the SNL study did not include the cost of converting the UF_6 to metal. Including this cost, at the present estimate of \$10/kg-U, adds between \$810 and \$950 million (\$10 times 81,000,00 to 95,000,000 kg) or \$61-\$84/kg-U used in the casks. The adjusted total cost then ranges from \$4.9 to \$7 billion.

The study came to several other conclusions:

- ▶ The total system cost for use of DU metal as a shielding material for defense HLW was essentially the same as the baseline case for HLW disposal, a result of using much larger cask and emplacement overpack costs.
- ▶ Multiple canister transportation/disposal casks will result in significant reduction of repository surface (shielded storage) and subsurface facilities (remote handling) and operations costs.
- ▶ The three DU cask scenarios show it is less costly to use a DU shielded cask than vault storage given a cask of equivalent or larger capacity. The principal cost benefit came from the ability to contact handle and store the waste on relatively inexpensive open concrete pads, thereby eliminating the cost for constructing a permanent shielded storage vault.
- ▶ Larger transportation cask capacity reduced transportation costs. This result is due primarily to the dedicated train mileage charge, which became the controlling transportation cost element. Larger cask capacity resulted in fewer train miles needed to move the waste to the repository.
- ▶ The costs of integral and reusable transportation overpacks were equivalent. The larger integral cask capital costs are offset by not having a separate transportation overpack cost and some reduction in waste acceptance cost. However, a cask that can be directly buried in the repository may have significant cost benefits if all disposal operation were to use contact handled versus remote handled systems.

2.3 Depleted Uranium Spent Fuel Shielding

Spent fuel storage is needed by the nuclear utilities in the U.S. due to the delays in the development of a high-level waste repository for permanent fuel disposal as required in the 1982 Waste Policy Act. Over the last ten to fifteen years, several vendors in the U.S. and Europe have developed a variety of spent fuel dry-storage casks. These casks use materials such as lead, steel, and concrete to provide the required radiation shielding. Costs and benefits of using DU metal or oxide for spent fuel storage have been studied. The physical properties of DU are such that it would offer superior shielding efficiency compared to conventional materials. The major barrier to widespread use of DU for shielding is the current costs of production of uranium metal based storage casks.

The concrete at-reactor fuel storage casks now used by utilities cost about \$30/kg of spent fuel contained, expressed as uranium metal. Steel and lead storage casks which are considerably more expensive were developed first by the industry but, since concrete systems have been licensed, the metallic systems are no longer competitive. The concrete cask is designed only for storage and is not capable of being transported to the MRS or HLW repository. The fuel, which is contained within a relatively thin-walled steel canister⁶ inside the concrete storage cask, must be removed and placed in a transport overpack for shipment. After its useful life for SNF storage, the concrete cask must be decontaminated and disposed.

2.3.1 Depleted Uranium Metal Spent Fuel Storage Casks

Results of the SAIC-Idaho study on Depleted Uranium Management Alternatives (Reference 6) indicate that the cost for a DU metal shielded cask having design characteristics that would allow at-reactor storage and shipment to, and potentially placement in, the repository is \$165/kg of spent fuel contained, expressed as uranium metal. This translates to approximately \$1.5 million for a cask that holds 21 PWR assemblies. If cost credits reflecting the avoided cost of disposal were provided, the cost would be \$102/kg-U contained for low-level waste and \$41/kg-U contained for RCRA disposal. (The credits are based on disposal costs in Reference 2 and represent an average of the costs determined at that time).

The spent nuclear fuel cask of the SAIC study would be fabricated from DU metal for radiation shielding, stainless steel shells for structural strength, high nickel alloy (Alloy 825) as a corrosion barrier, and a removable polyethylene barrier for neutron radiation shielding. It was estimated that approximately 9,500 of these casks (6,300 PWR and 3,200 BWR) would be required to meet the spent fuel storage/disposal requirements through the year 2045 if the geologic repository did not open earlier. The DOE inventory of depleted uranium (375,000 metric tons) is sufficient to fabricate about 8150 casks. The balance of the 9500 casks, if needed, could come from the depleted uranium being generated by the U.S. Enrichment Corporation. The study assumed the casks would be designed for a reference SNF age (time after reactor discharge) of ten years, would not exceed a crane hook load of 100 tons, and would be optimized for PWR fuel burn up of 35,000 MWD/MTU and BWR fuel burn up of 30,000 MWD/MTU.

The study also found:

- Uranium metal's lack of certification by the American Society of Testing and Materials (ASTM) is a barrier to its use in structural applications even though, if alloyed, it has mechanical/structural properties comparable to stainless steels. Therefore, DU metal must be used in combination with steel in spent fuel storage and transportation applications. If certification can be received for a DU metal alloy, an 11% weight reduction in storage casks could be achieved.

6. This canister in the future will be the DOE Multipurpose Canister (MPC).

- Conversion of UF_6 to uranium metal in the study was by the magnesium reduction process (Ames process), which has costs of approximately \$10/kg-U metal. This process is a candidate for cost reduction. INEL and LANL plasma processes and a continuous reduction process developed for the Advanced Vapor Laser Isotope Separation (AVLIS) program by ORNL are possible solutions for reducing UF_6 conversion costs.
- Fabrication costs are another prime target for cost reduction. For 8150 SNF casks, the cost was estimated to be \$12 billion without any disposal credits. The highest single cost element is the DU metal, which costs \$7.9 billion (\$21/kg-U) for conversion and fabrication.

The costs of the depleted uranium metal cask, with and without disposal credits, are listed in Table 3. Costs include all material, labor, design, licensing, and profit for producing an integral SNF storage and transport cask (as conceptualized).

Table 3. Cost Summary for Fabrication of 8150 DU Metal Casks (375,000 MOTU basis)		
Case	Total Cost (Billions)	Total Cost per kg- U SNF Contained
Container Cost w/o DU Disposal Credits	\$12	\$165
Container Cost w/DU LW Disposal Credits (\$12.25/kg-U, Reference 2)	\$7.4	\$102
Container Cost w/DU RCRA Credits (\$24.38/kg-U, Reference 2)	\$2.8	\$41

Costs estimated in the SAIC study use a \$10/kg-U conversion cost (includes HF resale and MgF_2 disposal) and an \$11/kg-U DU fabrication cost. Others have reported the cost for conversion at \$8.80/kg-U and fabrication of a simple as-cast shape as being \$2.20/kg-U (Reference 4).

Plasma conversion technology, suggested by both the INEL and LANL, could significantly reduce the cost of converting UF_6 to U metal, with minimal secondary waste generation. Preliminary cost estimates for conversion of UF_6 to U metal using plasma technology have been developed as a part of EM-50 activities. INEL costs developed to date include capital cost for constructing a 4 metric ton per hour (20,000 tonne per year) conversion facility as well as utility and operational cost (Reference 12). The unit cost estimates from this study are \$3 per kg of UF_6 (\$4.47/kg-U) processed, without credits for the anhydrous HF byproduct. The preliminary cost estimate from LANL for a 40,000 MT/yr hydrogen plasma reduction plant (capital and operating costs), including resale of HF, is \$3.30/kg-U (Reference 13). The impact this new technology could have on the manufacture of DU shielded SNF/HLW casks is depicted in Table 4 (INEL cost numbers were used, LANL estimated costs are lower).

Table 4. Cost Comparison of Recycle Options Assuming Production of 8150 Spent Fuel Storage Casks (375,000 MOTU basis)

	Cost (Billions)
Metal Casks, Existing Technology of UF ₆ to Metal Conversion (Cost range due to variations in estimates from suppliers)	\$8.2 to \$12
Metal Casks, New Plasma Based UF ₆ to Metal Conversion	\$9.5
DUCRETE Storage Casks	\$4.1

2.3.2 Depleted Uranium Concrete Spent Fuel Storage Casks

The feasibility of using DU oxide⁷ as an aggregate in concrete is being explored at the INEL. Preliminary testing and analyses have been performed to determine the structural properties and the shielding effectiveness of various mixtures of sand, cement, and DU oxide aggregate (References 7-10 and 12).

Shielding analyses have shown that concrete with uranium dioxide (UO₂) as an aggregate is approximately 68% better at shielding gamma radiation and 12% better at shielding neutron radiation than conventional concrete (see Figure 1). This significantly reduces the wall thickness required to shield the SNF and, thus, reduces the cask weight sufficiently that handling in the spent fuel pool at the reactor is possible. In addition to modeling concrete with UO₂ aggregate, various types of sands high in hydrogen [e.g., bauxite sand - Al(OH)₃] were evaluated for their impact on neutron shielding wall thickness. DU concrete samples using depleted UO₂ fuel pellets as the aggregate have been made and tested for structural characteristics. Results show that the tensile and compressive strengths of DUCRETE are similar to those of typical construction grade concrete (3,000 to 6,000 psi compressive strength) (Reference 7). The strengths, although 15%-20% less on average than those of the conventional concrete samples tested, are sufficient to meet structural design criteria for a SNF storage cask. The somewhat lower compressive strength is attributed to the use of smooth, centerless-ground UO₂ nuclear fuel pellets (right circular cylinders) as the aggregate in these tests instead of angular rock. When DU oxide aggregate is manufactured, its physical shape and surface finish is expected to be more like that of rock. DU oxide aggregate will also be composed of other binder materials compatible with cement.

Oxidation tests performed on samples of this DUCRETE (using UO₂ fuel pellets) at elevated temperatures have shown that the DU concrete performance is excellent at temperatures up to 150C. Further experimentation is necessary using DU oxide aggregate to determine the thermal, chemical and physical stability.

7. Uranium oxide contained in the aggregate can be either U₃O₈ or UO₂ depending on fabrication parameters.

Preliminary concepts for DUCRETE based storage casks were evaluated (References 8 -- 11). The most reasonable concept evaluated uses a pair of steel shells which will contain the DUCRETE shielding. The outer steel shell provides the structural strength. Approximately 10 inches of DUCRETE will provide the necessary shielding. Compared to conventional concrete, this concept, which is compatible with the MPC specified by DOE, is about 40 inches smaller in diameter and weighs about 35 tons less. The smaller diameter reduces the size of fuel storage at a utility site. The reduced weight allows direct fuel loading in the spent fuel pools for about 88% of the nuclear utilities. This direct loading saves utilities time and reduces radiation exposure to workers (Reference 11). The stainless steel shells for these casks could be fabricated from recycled steel from DOE facilities. Surface radiation doses from the depleted uranium and the previously contaminated steel is probably less than 1% of the total dose when the cask contains spent fuel.

Costs for fabricating SNF storage casks from DUCRETE are estimated to be comparable to those for conventional concrete. Current cost estimates for the DU concrete portion of a SNF storage cask are based on a cost for conversion of UF_6 to U_3O_8 of \$4.20/kg-U (\$1.91/lb -U). This is the range that commercial firms have been discussing and is the same as used in Table 2 for the Advanced Oxide Conversion Options. The estimate of \$2.20/kg-U is used for sintering the UO_2 into a dense aggregate and \$0.12/kg-U for fabricating the DUCRETE into a cylindrical cask. The sintering allowance is judged to be very high, actual costs less than one fourth of that value are probable. Based on these preliminary cost factors, the total estimated cost of conversion and fabrication of the DUCRETE used in the storage cask is \$6.55/kg-U. Associated costs for design and licensing, stainless steel liner fabrication, internals (e.g., fuel basket), and profit are provided in Table 5. The total cost estimated for a 24-PWR DUCRETE storage cask, without DU disposal credits, is ~\$502K, or \$46/kg of spent fuel contained, expressed as uranium metal.

Total cost for 8150 storage casks, neglecting credits for disposal or credits that may be associated with future reuse of the storage cask as a greater than Class C low-level waste cask,⁸ is estimated to be \$4.1 billion. More refined cost studies are in progress. The cost estimate for the DUCRETE cask without the internals and with the DU oxide aggregate furnished by DOE (in lieu of disposal) is \$220K. If the internals cost listed above (\$140K) is included, the total cost for 8150 units becomes \$2.9 billion (\$360K each). In other words, although the final cost of UF_6 conversion to oxide and production of DU oxide aggregate is not well established, the cost estimates show that even with an allowance of \$142K per cask for UF_6 conversion and DU oxide aggregate production (\$502K - \$220K - \$140K), the DUCRETE cask is an attractive option compared to depleted uranium metal. Furthermore, the advantages of smaller size and lighter weight provide transportation advantages. Thus, total life-cycle cost of DUCRETE casks is lower than that of conventional concrete storage casks if the DU oxide aggregate is furnished by DOE in lieu of the costs for disposal (Reference 11). This study assumes the DUCRETE casks are transported empty but with the trains transporting the spent fuel to the geologic repository and then are disposed with the fuel.

8. If the DUCRETE cask is not disposed with spent fuel in the repository, it can be used as a greater than Class C low-level waste transport and disposal cask and disposed with its contents as LLW.

Table 5. Preliminary Cost Estimate for a DUCRETE SNF Container				
Cost Category		Unit Cost (\$/kg)	Quantity (Metric ton)	Estimated Cost (\$1000)
UF ₆ to Oxide Conversion		\$4.20	40	\$168
Aggregate Fabrication		\$2.20	40	\$88
Concrete Fabrication		\$0.18	40	\$7.3
Stainless Steel Liner		\$10.12	3.76	\$38
Internals				\$140
Design and licensing				\$15
			Subtotal	\$456
			Profit @ 10%	46
			Total	\$502

2.4 High-Level Waste DUCRETE Storage Casks

No conceptual studies have been conducted to date to evaluate the applicability of DUCRETE to HLW casks. However, the feasibility is certain since the functional requirements for HLW storage are similar to those for spent fuel. DUCRETE HLW casks are expected to be considerably lower in cost than the uranium metal casks evaluated in the Sandia National Laboratory study (Reference 3).

2.5 Domestic Commercial Capability to Convert UF₆ and/or Fabricate DU Metal Components

Domestic capabilities for conversion of UF₆ to UF₄ and uranium metal were investigated as a part of the DOE EM-50 DU recycle program activities (Reference 4). This investigation was performed to determine if commercial capabilities existed within the U.S. and Canada to support a large-scale DU metal recycle program.

Given the lack of markets for uranium materials with the evaporation of the Cold War, it was questioned whether the existing uranium conversion and/or fabrication base was adequate to support the DU recycle alternatives discussed above. To address this concern, Technics Development Corporation was contracted to visit Canadian and U.S. companies to assess their DU conversion and/or fabrication capabilities.

The Technics investigation identified four commercial companies with existing capabilities and experience in conversion (UF₆ to UF₄ and U metal) and/or fabrication of DU metal into products. Additionally, the investigation identified several companies, which support other aspects of the uranium enrichment industry (e.g., Allied Signal, Inc.), that would have interest in a DU recycle program. The companies identified and their capabilities are summarized below.

- Cameco Corporation (Port Hope, Canada) primarily converts UO_3 to UO_2 or UF_6 ; however, they do have the capability to convert UF_4 to U metal and to cast U metal to shape. Cameco's UF_6 to U metal capacity is 2,500 MOTU/yr, while their casting capacity is 1,660 MOTU/yr (estimated).
- Nuclear Metals Inc. (Concord, MA) and its wholly-owned subsidiary, Carolina Metals, Inc. (Barnwell, SC) has had as its principal product DU penetrators for anti-armor applications for the U.S. Department of Defense. Carolina Metals Inc. has the capability to convert UF_6 to UFO and UFO to U metal at the rates of 2,500 MT/yr and 5,000 MOTU/yr respectively. DU metal melting, cladding, machining, and processing capabilities exist at the Nuclear Metals, Inc. facility in Massachusetts. The cost for UF_6 to UFO conversion is \$2.20/kg- UFO , while that for UFO to U metal is \$6.60/kg-U.
- Aerojet Ordnance (Jonesborough, TN) has the capability to convert UFO to U metal at a rate of 4,000 MOTU/yr. Aerojet is currently producing U metal from UFO purchased from Sequoyah Fuels. Additionally, Aerojet has the capability to convert UF_6 to UFO ; however, their plant is on standby status at this time.
- Allied Signal (Metropolis, IL) has the capability to convert natural U oxide to UF_6 at a rate of 14,000 MOTU/yr using HF and fluorine as reactants. Allied Signal has expressed interest in providing a service to DOE for conversion of depleted UF_6 and recovery of anhydrous HF for use in their uranium fluorination process.

Other companies contacted included Sequoyah Fuels (Gore, OK) and Manufacturing Science Corporation (MSC, Oak Ridge, TN). Sequoyah Fuels has been a major processor of uranium compounds, but due to the declining market they have not reapplied for a NRC license to operate. Sequoyah Fuels is now under an NRC Order for decontamination and decommissioning. MSC has uranium re-melting and metal plate forming capabilities but no UF_6 to UFO or UFO to U metal conversion capabilities.

If DU is determined legally to be a waste, some firms that would otherwise participate in the DU recycle process may refrain from doing so because of the complications of environmental permitting and operation under RCRA. On the other hand, since the size of the potential market is very large, informal inquiries made to date indicate that there will be no shortage of offers if DOE seeks proposals for conversion services.

2.6 Federal Capability to Convert and/or Fabricate Depleted Uranium

In the ORNL (Martin Marietta Energy Systems, MMES) study (Reference 5) on the Federal government's capabilities to handle DU, it was presented that:

No DOE facility can convert UF_6 to either metal or oxide on anything beyond a laboratory scale. The AVLIS technology may be applicable to either or both processes and is being investigated further.

Regarding uranium metal fabrication, DOE has metal working facilities at the INEL, Rocky Flats, Y-12 (ORNL), LLNL, and LANL.

3.0 CONCLUSIONS

Based on existing technology and its associated costs, the minimum cost to DOE of dealing with its current DU inventory is in the neighborhood of \$3.9 billion (for conversion to an oxide and subsequent disposal as low-level waste). This assumes that UF_6 is not declared a RCRA waste and that no special permits are required for continued interim storage in existing cylinders. If the UF_6 were ever declared a RCRA waste, costs for future processing and disposal could more than triple.

The lowest cost option appears to be recycling DU to useful product such as DUCRETE spent fuel and HLW casks. Both the lower cost of converting UF_6 to an oxide and the low cost of fabricating concrete components make these estimated costs lower than those of the metallic uranium casks considered. Although the cost for fabrication of the depleted uranium aggregate is uncertain, there are precedents for large scale, low-cost manufacturing of nonnuclear ceramic materials. DUCRETE is not cost competitive with conventional concrete. However, if DOE provides the converted oxide in the form of aggregate in lieu of having to pay the cost of disposal, DUCRETE casks then appear competitive to conventional concrete casks.

Metal uranium storage casks appear to be much more costly than DUCRETE casks. However, there is a large potential savings in conversion of the UF_6 to uranium metal through application of the direct plasma reduction processes being explored by both INEL and LANL. The technology would directly reduce UF_6 to metal without requiring a reductant such as Mg and, consequently, would eliminate the MgF_2 waste stream and associated costs of MgF_2 disposal. However, this concept has not yet been proved beyond lab scale. To reduce the costs of DU metal casks to levels competitive with current concrete casks or to the projected cost of DUCRETE casks, considerable reduction in the fabrication cost of DU metal is also required. In summary, for DU metal to be competitive, its costs will have to be reduced well below that for present metallic steel and lead casks. This cost objective appears ambitious.

4.0 REFERENCES

1. Martin Marietta Energy Systems, Inc. *Inventory Status and Requirements for Government Owned Uranium*, Y/ES-009 (Draft), August 1993.
2. Hertzler, T. J., et al., *Depleted Uranium Disposal Options Evaluation*, EGG-MS-11297, May 1994.
3. Yoshimura, R., Sandia National Laboratories, *DU Cask Project Cost Analysis Report Outline*, Draft Report, September 1993.
4. Kosinski, F. E., Technics Development Corporation, *Review of Commercial Uranium Processing Capability*, Report TDC-100, Rev. 1, October 29, 1993.
5. Derrington, S., Martin Marietta Energy Systems Inc., *DOE Capabilities on Depleted Uranium Conversion and Fabrication*, Presented at Reuse and Recycle of Depleted Uranium Workshop, October 21, 1993.
6. Hertzler, T. J. and Nishimoto, D. D., *Depleted Uranium Management Alternatives*, EGG-MS-11416, August 1994.
7. Lessing, P. A., *Development of "DUCRETE"*, INEL-94/0029, March 1995.
8. Haelsig, R. T., Packaging Technology Inc., *Depleted Uranium Concrete Container Feasibility Study*, EGG-MS-11400, September, 1994.
9. Hopf, J. E., "Conceptual Design Report for the DUCRETE Spent Fuel Storage Cask System," INEL-95/0030, February 1995.
10. Hopf, J. E., *Conceptual Design Report for a Transportable DUCRETE Spent Fuel Storage Cask System*, INEL-95/0167, April 1995.
11. Powell, F. P., *Comparative Economics for DUCRETE Spent Fuel Storage Cask Handling, Transportation, and Capital Requirements*, INEL-95/0166, March 1995.
12. Rekemeyer, P., et al., *Depleted Uranium Plasma Reduction System Study*, INEL-94/0030, December 1994.
13. Joyce, E. L., et al., *Depleted Uranium Metal Preparation Using Hydrogen Plasma Technology, Intelligent Automation and Soft Computing Trends in Research, Development, and Applications*, Vol. 1, pp 319-324, November 1, 1993 data.
14. Kaplan, S.A., *Depleted Uranium Market Study*, Kapline Enterprises, Y/NA1801, August 1995.