3RD Q 92
91337
DOE/PC/91337--T3

An Experimental Study of NO_x Recycle in the NOXSO Flue Gas Cleanup Process

DE-AC22-91PC 91337

Quarterly Technical Progress Report

Submitted to
U.S. Department of Energy
Pittsburgh Energy Technology Center

July 1 through September 31, 1992

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Prepared by

NOXSO
CORPORATION
P.O. Box 469
Library, PA 15129

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED *TR*

MASTER

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

TABLE OF CONTENTS

- 1.0 Executive Summary**
- 2.0 Introduction**
- 3.0 Project Description**
- 4.0 Project Status**
- 5.0 Planned Activities**
- 6.0 Summary**

Prepared by

NOXSO
CORPORATION
P.O. Box 469
Library, PA 15129

1.0 EXECUTIVE SUMMARY

In the previous reporting period (from April to June), NO injection series of tests have been completed. Part of NO simultaneous injection and NO₂ injection tests were conducted. All the test results showed consistent trends. About 70% average NO_x reduction efficiency has been achieved when NO is injected into the primary air duct, which was not affected by the NO injection flow rate, the furnace load and exit O₂ concentration. When NO is injected into the secondary air duct, the NO_x reduction efficiency ranges from 46% to 60% with dependence on the exit O₂ concentration. The NO simultaneous injection tests showed that the NO_x reduction efficiency increases with the percentage of total NO injected into the primary air duct. About 67% average NO_x reduction efficiency was demonstrated with injection of NO₂ into the secondary air duct, which is higher than that with injection of NO at the same test conditions.

2.0 INTRODUCTION

NO_x recycle is one part of the NOXSO process. In this process, 90% of the acid pollutants (NO_x and SO_2) can be removed simultaneously by adsorption on the surface of a sorbent material. The sorbent is subsequently regenerated by heating and contacting the hot sorbent with a reducing gas followed by steam. The NO_x is removed in the heating process, and the SO_2 is removed by the chemical reaction of the reducing gas and steam. The NO_x stream produced is returned to the combustion process with combustion air, which is called the NO_x recycle. The NO_x is reduced in the flame to N_2 , H_2O , and CO_2 .

The NO_x recycle concept operates by means of two different mechanisms. The first relies on the thermodynamic and kinetic conditions in the flame. When NO_x is fed to the coal combustor at concentrations greater than the equilibrium concentration, a portion of the recycled NO_x is reduced to N_2 and O_2 to approach the equilibrium concentrations (from high to equilibrium value). The kinetic rate of NO formation also decreases due to the high initial recycled NO concentration. The second mechanism relies on the reducing nature of the combustor flame. Free radicals generated at flame temperatures react with the NO_x species reducing them to N_2 and H_2O or CO_2 . Therefore, reaction equilibrium and the reducing atmosphere in the flame both serve to destroy recycled NO_x species.

NO_x recycle will be implemented at the full-scale commercial demonstration plant at Niles, Ohio. The concept of NO_x recycle has been tested previously at the DOE-Pittsburgh Energy Technology Center (PETC) using a 500 lb/hr coal combustor used for the 3/4 MW tests and also using a tunnel furnace capable of being fired with a variety of fuels including gas, fuel oil, coal, and coal-water mixtures. The results were very promising and demonstrated the destruction of NO_x compounds when fed to the combustion system. The data also indicates that the extent of NO_x reduction is determined by the location of the NO_x injection and the combustor design.

This current project is pilot-scale testing of NO_x recycle. The objectives are to provide further fundamental understanding of the NO_x destruction mechanisms and to help with the implementation of NO_x recycle at the Niles plant. A Babcock & Wilcox 6 million Btu/hr Small Boiler Simulator (SBS), (see Figures 1 and 2), was chosen to perform the tests. The SBS is the same type of cyclone furnace as that at Niles and simulates a large cyclone unit very well (see Table 1).

The project involves conducting a series of tests which include injecting NO, NO_2 , and a simulated NO_x recycle stream respectively. The work performed during this reporting period focused on completing all the tests and reducing testing data. The conducted tests included NO_2 injections into the primary air duct, NO_2 injections into the secondary air duct, NO/ NO_2 mixture injections, NO simultaneous injections, and NO/ CH_4 injections. The preliminary data analysis showed that the NO_x reduction efficiency was higher for the NO_2 injection than NO injection. For the NO simultaneous injection tests, the higher percentage of NO injected into the primary air duct, the better the NO_x reduction efficiency. The addition of CH_4 into the NO injection demonstrated very little effects on the NO_x reduction efficiency.

3.0 PROJECT DESCRIPTION

In order to provide further fundamental understanding and practical information for NO_x recycle implementation at the Niles plant, the following four tasks have been defined to be performed in this project:

Task 1: Project Management and Reporting. This includes overall management of the project, preparation of monthly reports, preparation of draft and final project work plan, supervision of tests performed by B&W, and final report preparation.

Task 2: Experimental Testing. This has been subcontracted to B&W. It involves site preparation and testing. A schematic diagram of the NO injection and sampling system is shown in Figure 3. Pure NO gas from the gas cylinder goes through a rotameter and is injected into

the combustion air duct a short distance from the furnace. The sampling probes for the inlet NO and NO_x measurement are installed downstream of the injection location and before the cyclone. Both inlet and stack NO and NO_x concentrations are measured by continuous NO/NO_x analyzers. The tests consist of shakedown, baseline, simulated NO recycle, simulated NO₂ recycle, and novel concept tests. The NO, and NO₂ will be injected separately to investigate their effects on the NO_x destruction in the furnace. The injection of a simulated NO_x recycle stream will also be tested. The injection location will be in the primary air alone, secondary air alone, and both primary air and secondary air together. The varied parameters during the tests are furnace load, outlet oxygen concentration, and the amount of injected gases which are multiples of the baseline NO_x production levels.

Task 3: Data Analysis. The collected data will be analyzed. Data will be compiled into tables and graphs. The test data will be compared with previous NO_x recycle test results using pulverized coal combustor (performed at PETC), and recommendations for burner operation and NO_x recycle will be prepared.

Task 4: Comparison of B&W's pilot scale boiler to Ohio Edison's commercial boiler at Niles, Ohio. The end result of this task will be a comparison of the two units and suggested conditions for the NO_x recycle tests.

4.0 PROJECT STATUS

Experimental Testing

Management and Reporting: A meeting was held between NOXSO and W.R. Grace to evaluate the NO_x recycle tests at B&W. Dr. Beer from MIT attended the meeting as a consultant of W.R. Grace. Qian Zhou presented the overview of the project, the testing plans, and the testing results. A presentation was also given by Qian Zhou to Ohio Edison to review the status of the project. Both meetings were successful. The testing plans and the results were accepted by both W.R. Grace and Ohio Edison.

B&W has requested extension of the project for data reduction. NOXSO has requested the DOE-PETC to extend the project to April 1 at no additional cost to the DOE-PETC.

Site Preparation: Minor modification of the NO₂ injection system has been made to stabilize the NO₂ gas flow.

Testing: All the tests planned have been completed. After the last quarterly technical report, more NO₂ injection tests were conducted with the injection location at the primary air duct and the secondary air duct separately. A few tests with injection of NO/NO₂ mixture were performed. In addition, more NO simultaneous injections and addition of CH₄ into NO injections were tested.

For all the tests, the testing procedures were:

- 1). Measure the baseline stack NO_x before injection of NO.
- 2). Inject NO or NO₂ and take data at the steady state condition.
- 3). Stop injection and measure the baseline condition again before next injection.

Part of preliminary data analysis of the completed tests is given in the following section.

Data Analysis

Testing data reduction is in process at B&W. The preliminary analysis from raw data for part of the completed tests has been done by NOXSO. The results are shown in Figures 4-6. In these figures, the NO_x reduction efficiency is defined as follows:

$$eff.\% = \frac{NO_{xi} + NO_{xb} - NO_{xs}}{NO_{xi}} * 100 \quad (2)$$

where, NO_{xi} is the feed rate of pure NO_x gas (lb/hr), NO_{xb} is the baseline stack NO_x without NO_x injection (lb/hr), and NO_{xs} is the stack NO_x with NO_x injection (lb/hr).

F^* is the normalized NO feed rate which is given by:

$$F^* = \frac{NO_{xi}}{NO_{xb}} \quad (3)$$

The normalized NO_x production rate is calculated according to the following equation:

$$R^* = \frac{R}{R_0} = \frac{NO_{xs} - NO_{xi}}{NO_{xb}}$$

where, R is the net NO_x production rate which equals the NO_x flow rate at the exit of the combustor minus the NO feed rate into the combustor; R_0 is the NO_x production rate at $NO_{xi}=0$, i.e., the baseline NO_x flow rate at the exit of the combustor. The figures, which show the normalized NO_x production rate (R^*) vs. normalized NO_x feed rate (F^*), also indicate the NO_x reduction efficiency if the data can be represented by the straight line described by the equation $R^* = 1 - aF^*$. It can be derived that the parameter "a" is the slope of the line and represents the NO_x reduction efficiency (eff. %).

Figure 4 shows the preliminary testing data analysis of NO_2 injection into the secondary air duct. The test data demonstrate quite consistent NO_x reduction efficiencies similar to the NO injection tests. All the data fell in a straight line at the same testing conditions. The NO_x reduction efficiency is independent on the amount of NO_2 injected. However, the NO_x reduction efficiency is higher than that of NO injections. The similar exit O_2 effects are also displayed. The lower the exit O_2 , the higher the NO_x reduction efficiency due to the increased reducing atmosphere.

The testing results of NO_2 injection into the primary air duct are shown in Figure 5. Higher NO_x reduction efficiency is achieved comparing to the NO_2 injection into the secondary air duct. This is consistent with the test results of NO injections.

The testing data for the NO/ NO_2 mixture injection shown in Figure 5 and 6 fall in between the data of NO and NO_2 injection separately. As expected, the NO_x reduction efficiency

for the NO/NO₂ mixture injection is higher than that for NO injection and lower than that of NO₂ injection.

Very little effects of addition of CH₄ into NO injection were observed during the tests. Further data reduction and data analysis need be done to make conclusions.

5.0 PLANNED ACTIVITIES

Data reduction and analysis will continue. Final report will be written and submitted to the DOE-PETC by March 1, 1992.

6.0 SUMMARY

All the tests planned were completed. The NO₂ injection tests showed higher NO_x reduction than that of NO injection at similar testing conditions. The NO_x reduction efficiency for the NO/NO₂ mixture injection is higher than that for NO injection and lower than that for NO₂ injection separately. The NO_x reduction efficiency is independent on the amount of injected gas (NO, NO₂, or NO/NO₂), but affected by the exit O₂ when NO or NO₂ is injected into the secondary air duct. The optimum injection location which gives higher NO_x reduction efficiency is the primary air duct. The NO_x reduction efficiency increases with the percentage of total NO injected into the primary air duct in the NO simultaneous injection tests.

**Table 1. Comparison of Baseline Conditions Between
the SBS Facility and Commercial Units**

	SBS	Typical Cyclone-Fired Boilers
Cyclone Temperature	>3000°F	>3000°F
Resident Time	1.4 sec. at full load	0.7-2 sec.
Furnace Exit Gas Temperature	2265°F	2200°-2350°F
NO_x Level	900-1200 PPM	600-1400 PPM
Ash Retention	80-85%	60-80%
Unburned Carbon	<1% in Ash	1-20%
Ash Particle Size (MMD; Bahco)	6-8 microns	6-11 microns

Figure 1 Small Boiler Simulator (SBS) Schematic

Figure 2 Cyclone Furnace

Schematic of NO Injection and Sampling System

Figure 3

**TESTING DATA OF NOx RECYCLE
ON B&W'S CYCLONE FURNACE
(NO2 Injection into the Secondary Air Duct)**

Figure 4

**TESTING DATA OF SIMULATED NOx RECYCLE
ON B&W'S CYCLONE FURNACE
(NO₂ Injection Into the Primary Air Duct)**

Figure 5

**TESTING DATA OF SIMULATED NOx RECYCLE
ON B&W'S CYCLONE FURNACE
(NO+NO₂ Injection into the Secondary Air Duct)**

Figure 6