UNITED STATES DEPARTMENT OF ENERGY
Albuquerque, New Mexico

RECEIVED
OCT 07 1985
OSTI

Uranium Mill Tailings Remedial Action Project (UMTRAP)

Slick Rock, Colorado

SRK

Subcontract Documents

Bid Schedule
Special Conditions
Specifications
Subcontract Drawings

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION
& ENVIRONMENTAL GROUP

MASTER

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

UMTRA PROJECT
SUBCONTRACT DOCUMENTS SRK
SLICK ROCK, COLORADO
TABLE OF CONTENTS

BIDDING REQUIREMENTS

Section 00310, Rev. 2 - Bid Schedule

TERMS AND CONDITIONS

Section 00800, Rev. 2 - Special Conditions

SPECIFICATIONS

DIVISION 1 - GENERAL REQUIREMENTS

Section 01010, Rev. 2 - Summary of Work
01019, Rev. 0 - Mobilization
01025, Rev. 0 - Measurement and Payment
01052, Rev. [1]* - Layout of Work and Surveys
01300, Rev. 2 - Submittals
01500, Rev. [3]* - Construction Facilities
01560, Rev. 2 - Temporary Controls
01561, Rev. 0 - Construction Cleaning

DIVISION 2 - SITEWORK

Section 02050, Rev. 0 - Demolition
02081, Rev. 0 - Asbestos, Hazardous and Non-Hazardous
Materials
02090, Rev. 0 - Sealing Monitor Wells
02110, Rev. 0 - Site Clearing
02141, Rev. [1]* - Dewatering and Drainage
02200, Rev. 1 - Earthwork
02205, Rev. 1 - Road Construction
02278, Rev. 1 - Erosion Protection
02771, Rev. 0 - Membrane Liner
02832, Rev. 2 - Chain Link Fence and Gates
02835, Rev. 0 - Deer Fence and Gates
02836, Rev. 0 - Smooth Wire Fence and Gates
02935, Rev. 1 - Seeding

DIVISION 5 - METALS

Section 05275, Rev. 1 - Modification and Repair of County Road
Bridge

* P.I.D. 11-S-08

Document No. 3885-SRK-S-01-02413-06
Issued for Construction-Revision 4
Table of Contents

SUBCONTRACT DRAWINGS

<u>Drawing No.</u>	<u>Title</u>
<u>General</u>	
SRK-GE-10-0301, Rev. 0	Title Sheet
SRK-GE-10-0302, Rev. 1	Location Map, Vicinity Map and List of Drawings
SRK-GE-10-0303, Rev. 1	Processing Sites, Disposal Site and Borrow Sites Location Map
SRK-GE-10-0304, Rev. 1	Proposed Borrow Sources Site Plans
SRK-GE-10-0305, Rev. 1	Fence and Gate Details
<u>Union Carbide Processing Site</u>	
SRK-PS-10-0310, Rev. 1	Site Plan and Construction Facilities
SRK-PS-10-0311, Rev. 1	Existing Utilities and Demolition Plan
SRK-PS-10-0312, Rev. 1	Temporary Site Drainage Plan
SRK-PS-10-0313, Rev. 0	Temporary Drainage Ditches Sections and Details
SRK-PS-10-0314, Rev. 1	Access Control Area Plan, Sections and Details
SRK-PS-10-0315, Rev. 0	Wastewater Retention Basin Sections and Details
SRK-PS-10-0316, Rev. 0	Contaminated Material Excavation Plan
SRK-PS-10-0317, Rev. 0	Final Site Grading Plan
SRK-PS-10-0318, Rev. 0	Borings and Test Pits Location Plan

SUBCONTRACT DRAWINGS (Cont'd.)

<u>Drawing No.</u>	<u>Title</u>
<u>North Continent Processing Site</u>	
SRK-PS-10-0320, Rev. 0	Site Plan and Construction Facilities
SRK-PS-10-0321, Rev. 0	Access Roads and Facilities
SRK-PS-10-0322, Rev. 0	Existing Utilities and Demolition Plan
SRK-PS-10-0323, Rev. 0	Contaminated Material Excavation Plan
SRK-PS-10-0324, Rev. 0	Final Site Grading Plan
SRK-PS-10-0325, Rev. 0	Borings and Test Pits Location Plan
<u>Burro Canyon Disposal Site</u>	
SRK-DS-10-0330, Rev. 1	Access Plan
SRK-DS-10-0331, Rev. [3]*	Site Preparation and Temporary Drainage Facilities
SRK-DS-10-0332, Rev. 1	Access Control Facilities and Wastewater Retention Basin Plan
SRK-DS-10-0333, Rev. 0	Wastewater Retention Basin and Miscellaneous Sections and Details
SRK-DS-10-0334, Rev. [2]*	Tailings Embankment and Final Site Grading Plan
SRK-DS-10-0335, Rev. 1	Tailings Embankment Sections and Details (Sheet 1 of 2)
SRK-DS-10-0336, Rev. 1	Tailings Embankment Sections and Details (Sheet 2 of 2)
SRK-DS-10-0337, Rev. 0	Tailings Embankment Erosion Protection

* P.I.D. 11-S-08

Document No. 3885-SRK-S-01-02413-06
Issued for Construction-Revision 4
Table of Contents

SRK

- 3 -

WP51
041195

SUBCONTRACT DRAWINGS (Cont'd.)

<u>Drawing No.</u>	<u>Title</u>
SRK-DS-10-0338, Rev. 0	Borings and Test Pits Location Plan
SRK-DS-10-0339, Rev. [1]*	Embankment Stand Pipes

END OF TABLE OF CONTENTS

* P.I.D. 11-S-08

Document No. 3885-SRK-S-01-02413-06
Issued for Construction-Revision 4
Table of Contents

SRK

- 4 -

WP51
041195

BID SCHEDULE

SECTION 00310

BID SCHEDULE

Name of Bidder _____ Date: _____

Following are the prices bid for completion of the Work as required by the Subcontract Documents:

Item No.	Spec. Section	Description*	Unit	Estimated Quantity	Unit Price	Amount
<u>000 - MOBILIZATION</u>						
001	01019	Mobilization	L.S.	100%	N/A	_____
002	00800	Payment for Bond Premium	L.S.	100%	N/A	_____
<u>200 - SITE PREPARATION</u>						
[201	01500	Temporary Trailers	L.S.	100%	N/A	_____]
202	01500	Temporary Roads and Parking Areas	L.S.	100%	N/A	_____
203	01500	Temporary Sanitary Facilities	L.S.	100%	N/A	_____
204	01500	Temporary Electric Power	L.S.	100%	N/A	_____
205	01500	Temporary Water	L.S.	100%	N/A	_____
206	01500	Maintenance and Janitorial Services	Month	24		_____
207	01500	Construction of Decontamination Facilities at UC, NC and BC Sites	L.S.	100%	N/A	_____
208	01560	Furnish and Install Silt Fence	L.F.	4,510		_____
209	02050	Demolition and Disposal of Existing Structures and Facilities	L.S.	100%	N/A	_____

† P.I.D. 11-S-07

Document No. 3885-SRK-S-01-02414-04
Issued for Construction-Revision 2
Bid Schedule

SRK

00310 - 1

WP51
022195

Item No.	Spec. Section	Description*	Unit	Estimated Quantity	Unit Price	Amount
210	02090	Sealing of Monitor Wells at UC, NC and BC Sites	L.F.	2,700	_____	_____
211	02200	Excavation of Uncontaminated Material and Placement for Fill as Required for Access Control Facilities, Temporary Drainage Ditches, Dikes and Waste-water Retention Basins at UC, NC and BC Sites	C.Y.	38,820	_____	_____
212	02200	Excavation of Uncontaminated Material for the Tailings Embankment Foundation and Placement in Spoilpile/Stockpile at the BC Site or for Finish Grading at the BC Site	C.Y.	330,720	_____	_____
213	02200	Rock Excavation for the Tailings Embankment Foundation and Placement in Spoilpile/Stockpile at the BC Site or for Finish Grading at the BC Site	C.Y.	209,330	_____	_____
214	02205	Reconstruction of County Road S8 on Original Alignment at the UC Site	L.F.	920	_____	_____
215	02205	Construct Access Roads to the NC and BC Sites including Earthwork and Culverts	L.S.	100%	N/A	_____
216	02205	Excavation at Junction of BC Access Road and State Highway 141	C.Y.	6,450	_____	_____

Document No. 3885-SRK-S-01-02414-04
Issued for Construction-Revision 2
Bid Schedule

SRK

00310 - 2

WP51
022195

Item No.	Spec. Section	Description*	Unit	Estimated Quantity	Unit Price	Amount
217	02771	Furnish and Install Membrane Liner for Waste-water Retention Basins at UC, NC and BC Sites	L.S.	100%	N/A	_____
[218	05275	Repair Existing County Rd Bridge including Furnishing and Installing Structural Steel, Performing Welding, Repair Work, Painting and Testing	L.S.	100%	N/A	_____]†
<u>400 - TAILINGS PILE</u>						
401	02200	Excavation of Contaminated Materials from Tailings Pile and from Windblown and Waterborne Areas at NC Site and Placement in Tailings Embankment	C.Y.	84,800	_____	_____
402	02200	Excavation of Contaminated Materials from Tailings Pile at UC Site and Vicinity Property Stockpile Material and Placement in Tailings Embankment	C.Y.	460,000	_____	_____
403	02200	Excavation of Contaminated Materials from Windblown/Waterborne Areas at UC Site and Placement in Tailings Embankment	C.Y.	85,000	_____	_____
404	02200	Excavation of Contaminated Materials Along Gas Line Right-of-Way at the UC Site and Placement in Tailings Embankment	C.Y.	2,600	_____	_____

† P.I.D. 11-S-07

Item No.	Spec. Section	Description*	Unit	Estimated Quantity	Unit Price	Amount
405	02200	Cleanup of Rock Surface at UC and NC Sites	S.Y.	25,000	_____	_____
406	02081	Handling, Removal, Transportation and Disposal of Asbestos, Hazardous and Non-Hazardous Waste Materials	L.S.	100%	N/A	_____
407	02200	Furnish and Install Displacement Monuments	Each	3	_____	_____
[408	02200	Furnish, Install and Seal Stand Pipes Including Concrete Base and Geotextile Filter for Monitoring and Dewatering System	L.F.	325	_____	_____
409	02200	Operate and Maintain Monitoring and Dewatering System in Tailings Embankment, Provide Pumps and Piping, and Pump Excess Water to Wastewater Retention Basin as Required	Month	12	_____	_____]†
<u>500 - COVER</u>						
[501	02200	Place Radon Barrier Material	C.Y.	26,400	_____	_____]††
502	02200	Place Frost Protection Material	C.Y.	36,750	_____	_____
<u>600 - EROSION PROTECTION</u>						
601	02278	Furnish and Place Riprap Material, Type A	C.Y.	3,300	_____	_____

† P.I.D. 11-S-07

†† P.I.D. 11-S-03

Document No. 3885-SRK-S-01-02414-04

Issued for Construction-Revision 2

Bid Schedule

SRK

00310 - 4

WP51
022195

Item No.	Spec. Section	Description*	Unit	Estimated Quantity	Unit Price	Amount
602	02278	Furnish and Place Riprap Material, Type B	C.Y.	13,800	_____	_____
603	02278	Furnish and Place Riprap Material, Type C	C.Y.	8,400	_____	_____
604	02278	Furnish and Place Bedding Material	C.Y.	11,100	_____	_____
<u>800 - SITE RESTORATION</u>						
801	02200	Place Common Fill Material (Including Topsoil) from Spoilpile/Stockpile at BC Site for Finish Grading of BC Site	C.Y.	84,100	_____	_____
802	02200	Furnish and Place Common Fill Material (Including Topsoil and Embankment for Reconstruction of County Road S8) for Finish Grading of UC and NC Sites	C.Y.	61,800	_____	_____
803	02935	Seeding at UC, NC and BC Sites	Acres	211	_____	_____
<u>900 - FENCING</u>						
[901	02832	Furnish, Install and Remove Chain Link Fence at Petroglyph Site at UC Site	L.F.	370	_____	_____]†
902	02835	Furnish, Install and Remove Deer Fence and Gates at UC, NC and BC Sites	L.F.	6,000	_____	_____

† P.I.D. 11-S-07

Item No.	Spec. Section	Description*	Unit	Estimated Quantity	Unit Price	Amount
903	02836	Furnish, Install and Remove Smooth Wire Fence and Gates at UC, NC and BC Sites	L.F.	10,960	_____	_____

TOTAL (SUBCONTRACT PRICE)

\$_____

* For complete description of a Bid Item and for measurement and payment provisions, see Part 4 of the Specification Section cited.

END OF SECTION 00310

Document No. 3885-SRK-S-01-02414-04
Issued for Construction-Revision 2

Bid Schedule

00310 - 6

SRK

WP51
022195

SPECIAL CONDITIONS

SECTION 00800

SPECIAL CONDITIONS

TABLE OF CONTENTS

<u>ARTICLE</u>	<u>TITLE</u>
SC-1	DEFINITIONS
SC-2	WORK SCHEDULE AND HOLIDAYS
SC-3	CONSTRUCTION RESTRAINTS
SC-4	SITE LOCATION AND ACCESS
SC-5	COORDINATION OF WORK
SC-6	CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS
SC-7	CONSTRUCTION ENVIRONMENT, SAFETY AND HEALTH
SC-8	HEALTH PHYSICS
SC-9	SUBMITTALS
SC-10	QUALITY ASSURANCE
SC-11	PERMITS
SC-12	SUBCONTRACT LABOR AND EQUIPMENT RATES
SC-13	SUBCONTRACT CHANGE NOTICE PROPOSAL
SC-14	VARIATIONS IN QUANTITIES
SC-15	LAWS AND REGULATIONS
SC-16	FUNDING LIMITATIONS
SC-17	CERTIFIED PAYROLLS
SC-18	SUBCONTRACTOR'S LIABILITY
SC-19	COLORADO SALES AND USE TAX
SC-20	MEASUREMENT AND PAYMENT
SC-21	LIMITATIONS ON SUBCONTRACTING
SC-22	BULLETIN BOARDS
SC-23	CONTAMINATED MATERIALS HAUL INSURANCE REQUIREMENTS
SC-24	ENFORCEMENT OF SITE RULES

SC-1 DEFINITIONS

A. Wherever used in the Subcontract Documents the following terms have the meanings indicated which are applicable to both the singular and plural thereof:

1. Access Control Area - Access control area shall include the areas occupied by and in the immediate vicinity of administration facilities including, but not limited to, Contractor's and Subcontractor's office trailers, access control trailer, sanitary facilities, decontamination pad and its contaminated water collection sump, equipment and materials laydown and storage area, employee and service vehicle parking area, roadway connecting vehicular gate to decontamination pad.
2. Addenda - Written and/or graphic instruments issued prior to opening of Bids which clarify, correct or change the bidding documents.
3. ALARA (As Low As Reasonably Achievable) - An approach to radiation protection to manage and control exposures (both individual and collective to the work force and the general public) and releases of radioactive material to the environment at levels as low as is practicable, taking into account social, technical, economic, practical, and public policy considerations. As used in this context, ALARA is not a dose limit but a process, which has the objective of attaining doses as far below the applicable controlling limits as is reasonably achievable.
4. Asbestos - All the asbestiform varieties of serpentinite (chrysotile), riebeckite (crocidolite), cummingtonite-grunerite, anthophyllite, and actinolite-tremolite.
5. Bid - The offer or proposal of the bidder submitted on the prescribed form setting forth the prices for the Work to be performed.
6. Bonds - Bid, performance and payment bonds.
7. Construction Facilities - Construction facilities shall include temporary facilities required during construction phase of the permanent facilities. These facilities are specified in Section 01500.
- [8. Contaminated Materials (C.M.) - "residual radioactive material" as defined by the Uranium Mill Tailings Radiation Control Act of 1978. The term "residual radioactive material" means (1) waste (with

radioactivity levels exceeding the Environmental Protection Agency's Standards found in Federal Register, 48FR602, January 5, 1983, "Standards for Remedial Actions at Inactive Uranium Processing Sites") in the form of tailings resulting from processing of ores for the extraction of uranium and other valuable constituents of ores; and (2) other waste (with radioactivity levels exceeding the Environmental Protection Agency's Standards as referenced above) at a processing site which relate to such processing, including any residual stock of unprocessed ores, low-grade materials, or demolished materials or debris exceeding limits specified for free release. Contaminated levels, which may be based on radium, thorium or other radionuclides, shall be as determined by the Contractor.]*

9. Controlled Area - Areas of elevated gamma, surface contamination and/or airborne radionuclide levels. These areas are generally radiologically posted and require restricted access, some may have localized restrictions; as determined by the Contractor.
10. Day - Day shall mean a calendar day of 24 hours.
11. Fiscal Year - October 1 through September 30.
12. General Requirements - Division 1 of the Specifications.
13. Hazardous Waste - Any material, alone or mixed with other materials, which has no commercial use or value, or which is discarded or is to be discarded by the possessor thereof, either of which because of its quantity, concentration, or physical, chemical, or infectious characteristics may cause or significantly contribute to an increase in mortality or an increase in serious irreversible or incapacitating reversible illness; or pose a substantial present or potential hazard to human health or to the environment when improperly treated, stored, transported, disposed of, or otherwise managed. The term does not include: discharges which are point sources subject to permits under Section 402 of the "Federal Water Pollution Control Act", as amended; source, special nuclear, or byproduct material as defined by the Federal "Atomic Energy Act of 1954", as amended; agricultural waste from the raising of crops or animals, including animal manures, which are returned to the soils as fertilizers or soil conditioners; domestic sewage; irrigation return

* P.I.D. 11-S-07

flows; inert materials deposited for construction for fill or topsoil placement in connection with actual or contemplated construction at such location or for changes in land contour for agricultural and mining purposes; or any waste or other materials exempted or otherwise not regulated as a hazardous waste under the federal act.

14. Lower-Tier Subcontractor/Other Subcontractor:

- a. Lower-tier Subcontractor - An individual firm or corporation having a direct contract with the Subcontractor.
- b. Other Subcontractor - An individual firm or corporation (other than the Subcontractor) having a direct contract with the Contractor for other work on the Project.

- 15. Notice of Award - The written notice by Contractor to the apparent successful bidder stating that upon compliance by the apparent successful bidder with the conditions precedent enumerated therein, within the time specified, Contractor will sign and deliver the Agreement.
- 16. Notice to Proceed - A written notice given by Contractor to Subcontractor fixing the date on which the Subcontract Time will commence to run and on which Subcontractor shall start to perform Subcontractor's obligations under the Subcontract Documents.
- 17. Permanent Facilities - Permanent facilities shall include permanent features of the Project including, but not limited to, the following: Tailings embankment, permanent drainage ditches, finish grading and seeding.
- 18. Project - The total construction of which the Work to be provided under these Subcontract Documents is a part as indicated elsewhere in the Subcontract Documents.
- 19. Project Site/Site/Jobsite: The Project Site or Site shall include the areas occupied by the processing sites, the disposal site, haul routes, and proposed borrow areas.
- 20. Radiation Work Permit (RWP) - An administrative control method by which radiological work can be planned, controlled, and documented, so that radiological conditions and job-specific information on radiological controls are communicated to the workers involved.

21. Shop Drawings - All drawings, diagrams, illustrations, schedules and other data which are specifically prepared by or for Subcontractor to illustrate some portion of the Work and all illustrations, brochures, standard schedules, performance charts, instructions, diagrams and other information prepared by a Supplier and submitted by Subcontractor to illustrate material or equipment for some portion of the Work.
22. Site Manager - The authorized representative of the Contractor who is assigned to the site or any part thereof.
23. Specifications - Those portions of the Subcontract Documents consisting of written technical descriptions of materials, equipment, construction systems, standards and workmanship as applied to the Work and certain administrative details applicable thereto.
24. Subcontract Change Notice/Change Order - A document signed by Subcontractor and Contractor authorizing an addition, deletion, revision, or clarification of the Work, modified in writing and issued on or after the Effective Date of the Agreement.
25. Subcontract Drawings - The drawings which show the character and scope of the Work to be performed and which are referred to in the Subcontract Documents.
26. Subcontract Modification - A document issued to incorporate Subcontract Change Notices/Change Orders and adjustments in the Subcontract Price or Subcontract Time or to modify Subcontract.
27. Subcontract Price - The moneys payable by Contractor to Subcontractor under the Subcontract Documents as stated in the Agreement.
28. Subcontract Time - Duration of time specified in the Subcontract Agreement Form for the completion of the Work under the Subcontract. The time shall commence from the date specified in the written Notice to Proceed, and specified in terms of number of calendar days available in which to complete the Work.
29. Tailings Embankment - See Section 02200.
30. Temporary Facilities - See Construction Facilities in Paragraph 7 above.

31. Temporary Roads - Improvements to existing roads, and construction of new roads if any, carried out by the Subcontractor for his own convenience in the performance of the Subcontract. These improvements or new constructions are not designated on the Subcontract Drawings.
 32. Uncontaminated Materials (U.M.) - All materials with radioactivity levels less than the limits specified in the US Environmental Protection Agency (EPA) Standards (Federal Register, 48FR602, January 5, 1983, "Standards for Remedial Actions at Inactive Uranium Processing Sites"). U.M. includes all naturally occurring in-situ mineralized sediments (uranium bearing deposits) regardless of radioactivity level, although these materials may be radiologically controlled to protect workers from exposure during site operations. U.M. also includes demolished materials or debris with radioactivity levels less than that specified for free release by the Contractor.
 33. Uncontrolled Hazardous Waste Site - An area where an accumulation of hazardous substance creates a threat to the health and safety of individuals or the environment or both. Uranium mill tailings that have a total specific activity above 2000 pCi/g are classified as a Hazardous Substance by the Department of Transportation.
 34. Work - The entire completed construction required under the Subcontract Documents. Work is the result of performance of services, furnishing labor and furnishing and incorporating materials and equipment into the construction, all as required by the Subcontract Documents.
- B. The other terms such as Contractor, Subcontractor, Government, DOE, Subcontract Administrator, Subcontract Documents, MK-F and Site of Work are defined in Article GP-2 of General Provisions.

SC-2 WORK SCHEDULE AND HOLIDAYS

- A. The Subcontractor shall schedule all construction work to be performed no more than ten hours per day and six days per week, excluding Sunday, unless otherwise directed by the Contractor, in accordance with Article GC-3 of the General Conditions and GP-58 of the General Provisions. Requests to work in excess of the stated hours per day and days per week will be granted solely at the discretion of the Contractor. Maintenance of equipment may be allowed up to 20 hours per day, 6 days per week, excluding holidays, if scheduled with

and approved by the Site Manager a minimum of 48 hours in advance of the equipment maintenance shift proposed to be worked.

- B. The following days will be observed as holidays by MK-Ferguson Company, and shall be observed by the Subcontractor and lower-tier subcontractors:

New Year's Day
Presidents' Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Day after Thanksgiving Day
Christmas Day
Day before or after Christmas Day as determined by the Site Manager.

- C. Holidays occurring on Saturday or Sunday will be observed on Friday or Monday.

SC-3 CONSTRUCTION RESTRAINTS

- A. Concurrent Work: MK-Ferguson Company (Contractor) and other subcontractors may be engaged in work in the general areas covered by the Work under this Subcontract. Such personnel will have access to the areas and to the utilities. The Subcontractor shall cooperate and coordinate his work to best utilize the available areas, roadways and facilities. Coordination shall be through the Contractor.
- B. During the course of this Subcontract, the Contractor, and possibly State personnel, will perform radiological surveys, and will conduct tests on excavated areas to determine whether additional contamination remains to be excavated. Results of such tests of contaminated material may take up to seven work days to obtain. This does not relieve the Subcontractor of his contractual obligation to place all contaminated material in the tailings embankment if additional contaminated material is found at a later date. The Subcontractor shall sequence his work as necessary to facilitate radiological surveys and dispose of all contaminated materials.
- C. Upon apparent completion of contaminated material excavation in a distinct area, the Contractor will conduct a radiological verification survey to confirm removal of contamination to EPA standards. This survey may take up to seven work days and may delay the Subcontractor from

proceeding with backfill and/or site grading activities. The Subcontractor shall plan his work accordingly. The State of Colorado may wish to verify the verification survey.

D. Radiological and Nuisance Dust:

1. Proactive Dust Suppression Plan: Thirty days after receipt of Notice to Proceed the Subcontractor shall submit a Proactive Dust Suppression Plan to the Contractor for approval. This plan shall include listing of specific pieces and quantity of equipment to be used, water sources, additives, days and hours of operation during construction activities, days and hours of operation during non-work periods such as between shifts, week-ends, holidays and winter shutdowns which demonstrate the Subcontractor's understanding of the importance of dust suppression requirements. It shall be adequate for all areas within the site boundaries, work areas and non-work areas, radiological and non-radiological areas. Approval of this plan does not relieve the Subcontractor of any responsibilities regarding the control of dust under the terms of the Subcontract.
2. Work Stoppage in Case of Excessive Radionuclides, Airborne and External Exposure: The Contractor will monitor construction activities and will shut down the work or require modifications of the Subcontractor's activities in the event that gaseous or particulate radionuclides exceed limits or airborne particulates are visible. Watering, vehicle speed reduction, voluntary partial shutdowns, respiratory protection and covering of materials emitting radon gas are some actions which shall be taken.
3. Work stoppage in case of Excessive and/or Visible Dust: The Contractor's and Subcontractor's actions regarding dust emissions in nonradiological areas within the site boundary shall be as stated above and in accordance with the Contractor provided CDH, Air Pollution Control Division - Emission Permit. The amount or type of dust suppression equipment in operation shall not prevent the Contractor from stopping work if there is excessive dust. If work stoppages occur due to excessive dust, the Subcontractor shall not recommence work without approval of the Contractor.

- E. Site Speed limit of 25 mph shall be posted, by the Subcontractor at all sites and shall be observed at all times by all construction personnel and equipment operators,

unless otherwise required by applicable permits or approved by the Contractor.

- [F. The Blasting Plan shall be submitted 30 days prior to commencement of any blasting.]*
- G. The Subcontractor shall comply with the State of Colorado Revised Statute entitled Noise Abatement, Article 12, Section 25-12-101, et al. The Subcontractor shall maintain the exhaust systems of all vehicles and equipment to protect against excessive noise and air pollution in compliance with the applicable local, state and federal statutes and permit requirements. The trucks shall be equipped with sound-dampening features. Tailgate chains shall be rubber-insulated and latches shall be adequately secured. Noise surveys may be conducted on all equipment by a Contractor's representative.
- H. The public will have access to all existing public roads, including haul roads constructed by the Subcontractor, during the term of the Subcontract, except as otherwise specified or shown on the Subcontract Drawings. The Subcontractor shall cooperate with private landowners and the public in using the haul roads, and shall be responsible for avoiding conflicts with stock and wildlife. Any work slowdowns or stoppages resulting from use of the haul roads by private landowners, the public, stock and wildlife shall be at the Subcontractor's expense.
- I. If the Subcontractor uncovers any archaeological artifacts or human remains during the term of the Subcontract, he shall immediately halt operations in the immediate vicinity of such a discovery and notify the Contractor. Further work in these areas shall not resume until a qualified archaeologist has inspected the site and completed all resource recovery work.
- J. The Subcontractor shall, in as much as is practical, schedule excavation and backfill in the lower portions of the processing site during that part of the year when the ground water level is the lowest, in order to minimize work below the ground water table.

* P.I.D. 11-S-07

- K. Tailings Pile Excavation: Excavation of the tailings piles shall be performed sequentially to the full depth of each tailings deposit, as determined by the Contractor. The number and size of excavations being worked concurrently will be subject to the Contractor's approval.
- L. Hauling Contaminated Materials: Hauling of contaminated materials to the disposal site shall not commence until the Contractor has given his approval that the tailings embankment is ready to receive contaminated materials.

SC-4 SITE LOCATION AND ACCESS

- A. The location of the sites is specified in Specification Section 01010.
- B. Access: The liability insurance dictates mandatory enforcement by the Contractor of the following restraints to all persons seeking construction site access:
 - 1. Private, personal or agency vehicles not used for authorized construction purposes will not be allowed in the controlled site areas.
 - 2. Parking of private, personal or agency vehicles shall be in a restricted area outside of the controlled site areas as designated by the Site Manager or his representative.

SC-5 COORDINATION OF WORK

The Subcontractor shall carefully coordinate all construction activities with the Site Manager to avoid conflicts and unnecessary delays in construction.

SC-6 CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

- A. Unless otherwise specified elsewhere in the Subcontract Documents, the Subcontractor shall furnish and assume full responsibility for the following facilities and incidentals which are necessary for the furnishing, performance, testing, start-up and completion of the Work as shown on the Subcontract Drawings and as specified in the Specifications:
 - 1. All materials, equipment, plant, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, decontamination facilities and all other

facilities and incidentals as specified in Section 01500.

2. Temporary controls including, but not limited to, dust control, erosion control, noise control, pollution control, surface water control and access and traffic control as specified in Section 01560.
- B. Subcontractor shall be responsible for installing, constructing, maintaining, operating, removing and disposing of the construction facilities and temporary controls through the term of the Subcontract.

SC-7 CONSTRUCTION ENVIRONMENT, SAFETY AND HEALTH

A. Contractor Safety Plan:

1. The Subcontractor shall comply with the Construction Environment, Safety and Health Management Plan (Document No. MK-UMTRA-4).
2. The successful bidder will be issued a controlled copy of the Construction Environment, Safety and Health Management Plan Document with the Notice to Proceed by the Contractor's Subcontract Administrator.
3. The Subcontractor shall comply with radiological programs and procedures required in the current revisions of the RAC/MK-F Health Physics Procedures, Health Physics Monitoring Plan, the Site Specific Health Physics Monitoring Plan, and/or DOE Orders as applicable. Copies of these documents will be provided by the Contractor on request of the Subcontractor.

B. Construction Environment, Safety and Health Orientation and Site Worker Training:

1. All construction personnel on the site shall receive the basic Construction Environment, Safety and Health Orientation and Site Worker Training Course. The Site Worker Training Course covers Safety and Health rules for UMTRA Projects, site emergency procedures, etc. The training will be presented at the site office between the hours of 8:00 a.m. and 5:00 p.m. during scheduled workdays (holidays excluded) to construction personnel, either individually or on a group basis, at a time scheduled by the site ES&H Department. The Subcontractor shall notify the Contractor at least two working days before the training is required. The Site Worker Course requires 4-6 hours to complete, depending upon

the size of the class. No construction personnel will be permitted to work without having received this basic training. It is further required that all site workers will attend a 2-hour Site Worker Refresher Course annually.

2. All employees not subject to the medical surveillance requirements of OSHA Standard 29 CFR 1910.120 shall have a written medical qualification to wear a respirator before they can perform work which requires the use of a respirator. Prior to respirator-fit testing and use of respirator protection, the Subcontractor shall provide the Contractor with a copy of each employee's medical qualification statement.
3. If respirator use becomes necessary for radiological protection, the respirators will be provided by the Contractor with training in the proper use during site worker training. This instruction will be provided to the Subcontractor at no additional cost. The Subcontractor shall notify the Contractor's Representative at least one week in advance of the time that respirator-fit testing is desired. Note, that individuals with beards or facial hair that interferes with a proper respirator seal will not be accepted for respirator training. The Subcontractor shall furnish respirators (including training and respirator-fit testing) for employee protection from nonradiological respiratory hazards.
4. No payment will be made to the Subcontractor for his employees' attendance at Construction Environment, Safety and Health Orientation and Site Worker Training or respirator training provided by the Contractor. Full compensation for such costs will be considered incidental to the Work of this Subcontract.
5. The Subcontractor shall maintain records of all training and other records required by this Subcontract and federal and state laws.
6. Prior or within 60 days of arrival on site, all Subcontractor's field supervisors shall have completed a minimum of a 30-hour construction safety course in OSHA regulations approved by the Contractor.
7. The Subcontractor shall comply with the training requirements of 49 CFR-172.H (i.e. HM-126F) and submit training documents as required by the Contractor.

- C. **Electrical Precautions:** The Subcontractor shall adhere to the provisions and procedures contained in the Construction Environment, Safety and Health Management Plan for Safe Conduct of Electrical Work, and Energy Source - Lockout/Tagout.
- D. **Smoking, Drinking, Eating and Chewing Restrictions:**
1. No smoking will be permitted in the immediate vicinity of any flammable liquids, gases or highly combustible material, or in any area posted as a non-smoking area.
 2. No smoking, drinking, eating or chewing will be permitted in any controlled area.
 3. Haul unit drivers shall not eat or drink in the haul units while the haul units are in motion.
- E. **Ladders, Scaffolds, Man Lifts and Stairways:** All man-lift equipment, ladders, scaffolding and stairways shall be in compliance with applicable OSHA (29 CFR 1926) standards and be subject to inspection by the Contractor prior to and during its use.
- F. **Trench/Excavation Barricades:** Trenching, excavation, shoring, bracing, and barricading requirements shall be in accordance with OSHA standard, 29 CFR 1926, Subpart P.
- G. **Notification of Occurrences:** Subcontractor shall advise the Contractor immediately upon occurrence of any non-routine events, incidents, conditions, truck spills of contaminated materials, accidents, injuries, near-misses, serious safety violations, regulatory violations, etc.
- H. **Responsibility:**
1. **Subcontractor Safety Responsibility:**
 - a. The Subcontractor shall designate in writing a qualified person to implement at all times the Construction Environment, Safety and Health Management Program at the work site. The designated person shall have authority for actions and for control of work activity to prevent accidents. The Subcontractor's safety representative shall be a full-time on-site employee whose only responsibility is to implement the Construction Environment, Safety and Health Management Program and who reports directly to the Subcontractor's management. The Contractor reserves the right to reject any safety person designated by the

Subcontractor and considered unqualified by the Contractor. At all times when the Subcontractor's designated Safety Representative is not available (extended work hours, sick, vacation, day off, seminar, etc.), an alternate representative acceptable to the Contractor shall fulfill all the responsibilities of the Safety Representative.

- b. The Subcontractor's Safety Representative shall make daily work area safety and health inspections wherever any work is ongoing. Such daily inspections shall be documented in writing and shall include a brief description of the inspection findings, deficiencies noted and actions taken or implemented as a result. Copies of the documented inspections shall be made available to the Contractor upon request.
- c. The Subcontractor shall participate and cooperate with Contractor or DOE inspections and audits. All Subcontractor personnel shall be scheduled on a rotational basis to participate in Subcontractor Daily and Weekly site surveillance program activities.
- d. The Subcontractor shall submit at the Pre-Construction Meeting a copy of their company's safety plan.

2. Contractor Safety Responsibility:

- a. Contractor Safety Department personnel or designated representatives will make regular continuing inspections of all facilities and operations within the scope of the Subcontract. These inspections will include the facilities and all operations of the Subcontractor, but do not in any way relieve the Subcontractor of his responsibility for compliance with the provisions of the Construction Environment, Safety and Health Management Plan.
- b. Daily work area safety and health inspections will be made by Contractor personnel.

3. Subcontractor Transportation Responsibility: The Subcontractor shall designate (in writing) a qualified person to implement the following (at all times): the Department of Transportation 49 CFR, the Contractor Hazardous Materials Transportation Requirements and Truck Inspection Plan, the Mill Tailings Shipment

Description and Truck Transportation Manual, and the Emergency Response to Transportation Accidents Manual. This person shall have authority to control work activity in order to prevent accidents. The Subcontractor's Transportation Representative shall be a full-time on-site employee who reports directly to the Subcontractor's management. The Contractor reserves the right to reject any person designated by the Subcontractor who is considered unqualified by the Contractor. At all times, when the Subcontractor's designated Transportation Representative is not available (extended work hours, sick, vacation, seminar, etc.), an alternate representative acceptable to the Contractor shall fulfill all the responsibilities of the Transportation Representative.

- I. Galvanized Materials: Personnel respiratory protection or ventilation is required if a heat process takes place with galvanized materials.
- J. Back-Up Alarms: All construction equipment shall have functioning audible back-up alarms while in use on an UMTRA project.
- K. Asbestos: The Subcontractor shall submit the following to the Contractor for review before work start up:
 - 1. A Certificate of Insurance Coverage, including, but not limited to, the following. These insurance coverage requirements are supplemental to other requirements specified in Article GC-7 of the General Conditions.
 - a. Asbestos Exclusions on Workmen's Compensation or Liability policies will not be accepted. However, separate policies will be satisfactory.
 - b. Whether coverage is on an occurrence or claims made basis, it is required that the coverage or policy be extended or kept in force for at least twenty-four months after completion of the Subcontract.
 - c. The Subcontractor shall provide evidence of coverage by submitting a Certificate of Insurance stating that such exclusions or coverage are in effect.
 - 2. An asbestos plan for the transportation and burial of asbestos materials. The asbestos materials shall be buried in the disposal cell using acceptable cell design criteria. Asbestos materials shall be buried and covered as specified in Section 02081. An Asbestos

Handling and Removal Plan shall be required if asbestos materials are uncovered during site excavations. The detailed requirements for submittal of an Asbestos Handling and Removal Plan are specified in Section 02081.

3. Asbestos Removal Permit: See Article SC-11.B.

L. Unidentified Materials: If unknown materials are encountered by the Subcontractor, work shall stop, the area barricaded, and the Contractor informed for identification and direction for subsequent action. If any of the materials are identified by laboratory analysis as hazardous, the Subcontractor will be immediately notified of applicable standards which the Subcontractor shall comply with for personnel safety, health protection, and scope of work for remediation.

M. Industrial Hygiene:

1. Noise:

a. The UMTRA Project shall comply with the OSHA Construction Occupational Noise Exposure Regulation 29 CFR 1926.52. Sound level surveys and noise dosimetry will be conducted on a continuous basis by the Contractor for both the Contractor and Subcontractor personnel. Noise monitoring data will be available to the Subcontractor for evaluation. Hearing protection is required for any personnel exposed to 85 dB(A) or above. Limit applies for an 8-hour Time Weighted Average (TWA). Excessive noise exposures will require the use and implementation of dual hearing protection (plugs and muffs) or feasible engineering controls.

b. The Subcontractor shall provide baseline and annual audiometric testing (hearing tests) if it is possible to annually track employees, and shall provide training to any employee exposed above 85 dB(A) 8-hour Time Weighted Average (TWA), as required to have an effective hearing conservation program. The baseline audiometric test shall be given to employees within 6 months of hire date. Costs of audiograms and training shall be funded by the Subcontractor without cost to the employee. Subcontractors or their individual employees, who work on an UMTRA site for less than 6 months are not required to perform audiometric tests for purposes of this Subcontract.

- c. The Contractor will monitor Subcontractor compliance with the OSHA 29 CFR 1926.52 regulation by reviewing Subcontractor records and interviewing Subcontractor employees as necessary.
 - d. The Subcontractor shall comply with the State of Colorado Statutes 25-12-101 (revised) and amendment regarding noise standards.
- 2. Dust: Subcontractor's dust control provisions shall be adequate to prevent personnel from potential inhalation exposure to Silica or Nuisance Particulates. Contractor's Safety Department will conduct ongoing dust monitoring and will keep the Subcontractor informed about the need for respiratory protection. The Subcontractor shall provide the necessary respiratory protection for silica where radiological contamination is not present.
 - 3. Confined Space: Prior to confined space entry, the Subcontractor shall read and comply with the confined space entry procedures developed by the Contractor or Subcontractor procedures determined by the Contractor to be equivalent. The procedures require that a permit be completed and kept at the work place. Atmospheric testing will be performed prior to confined space entry for percent oxygen, carbon monoxide, combustibles and hydrogen sulfide. Testing will be done using a direct reading instrument assigned to the Contractor's Environment, Safety and Health personnel.
 - 4. Hazard Communication: The Subcontractor shall comply with the OSHA Hazard Communication Programs for construction industry. Required compliance activities include, but are not limited to:
 - a. Current chemical inventories.
 - b. Material safety data sheets for all chemicals.
 - c. Proper labeling of all chemical containers and chemical storage areas.
 - d. Complete written program available to all work place employees.
 - e. Appropriate training to all employees on hazards of the workplace as required in OSHA 29 CFR 1926.59.

The Subcontractor shall submit to the Contractor a generic Hazard Communication Program at the Pre-

Construction Meeting. The Subcontractor shall submit their site specific Hazard Communication Program for approval within 30 calendar days after the Notice to Proceed. This plan shall be updated as new materials are utilized on site.

5. General Hazards:

- a. The Subcontractor shall be responsible for controlling general hazards as identified by the Contractor. General hazards include heat stress, ultra-violet radiation, chemical exposures and biological agents with potential to cause illness or injury to site personnel.
- b. In addition to those requirements cited in the CFR-1926.106 for working on or near water, the Subcontractor shall provide a means of egress from retention ponds, should someone inadvertently slip into the water. The Subcontractor shall provide and install this means of egress so that the maximum travel distance is no more than 50 feet.

N. Construction Motor Vehicles, Heavy Equipment and Machinery Inspections and Maintenance:

1. General: Prior to the operation of any vehicles or equipment, the Subcontractor shall notify the offices of the County Clerk and County Assessor and provide certification of licensing and assessment of all construction vehicles and equipment.
2. Construction Motor Vehicles:
 - a. Vehicles that are in operation within an off-highway jobsite shall comply with 29 CFR 1926.600 and 29 CFR 1926.601.
 - b. Vehicles that operate on highways or any public roads shall comply with the U.S. DOT 49 CFR. The Subcontractor is responsible for obtaining current editions of 49 CFR. In addition, the Subcontractor shall implement and comply with all requirements of the Contractor's Hazardous Materials Transportation Requirements and Truck Inspection Plan.
 - c. Inspection reports and repair records shall be submitted to the Contractor's Site Manager prior to the initial use of all Motor Vehicles and equipment. Any additional inspection reports or

repair records as required by the Truck Inspection Plan shall also be submitted to the Site Manager.

d. Truck Information: All haul unit vehicles shall be equipped with a computerized system that will:

- 1) Monitor driver trends, habits, routes and equipment. Identify high risk driver activity. Identify when vehicle exceeds operating parameters.
- 2) Monitor fuel economy, speed, idle time and RPM's.
- 3) Present data in a clear, user friendly report format that separates driver and vehicle information.

Any or all data shall be provided to the Contractor within 24 hours upon request.

e. All trucks carrying contaminated materials shall be capable of communication by radio with all other contaminated material haul trucks, decontamination facilities and project supervisors.

3. Heavy Equipment and Machinery:

- a. The Subcontractor shall designate a competent person to inspect the operating safety conditions of all construction Heavy Equipment and Machinery. The Heavy Equipment and Machinery shall be inspected prior to their use and frequently during their use to make certain that they are in safe operating condition. All deficiencies shall be repaired and defective parts replaced before continued use of the equipment or machinery. Records of inspections and repairs shall be maintained by the Subcontractor and be available for inspection by the Contractor.
- b. A thorough annual inspection of the hoisting machinery shall be made by a competent person or by a government or private agency recognized by the U.S. Department of Labor, and inspection reports shall be maintained by the Subcontractor and be available for inspection by the Contractor.
- c. Inspection reports and repair records shall be submitted to the Contractor's Site Manager prior to

the use of such construction vehicles, machinery and equipment on the Project.

d. Material handling Heavy Equipment shall comply with 29 CFR 1926.602.

4. Hoisting and Rigging Equipment: The Subcontractor shall have an effective hoisting and rigging program which includes but is not limited to:

- a. A written record of monthly inspections of equipment, including slings, cables, wire rope, chains, etc.
- b. A method to identify those items for lifting, those strictly for pulling, and those out-of-service.
- c. A written training program for the inspection process, and training documentation.

O. Hazardous Waste Operations (OSHA Standard 29 CFR 1910.120):

1. Training Requirements:

- a. All Subcontractor employees who are expected to work full-time, part-time or routinely on-site, and are exposed to hazardous substances (i.e. uranium mill tailings above 2000 pCi/g total specific activity), or other health and safety hazards shall complete a minimum of 24 hours of initial training or equivalent prior to working on-site. A minimum of 40 hours training is required if self-contained breathing apparatus or air-line respirators are required to be used. These employees shall be provided with an additional three days of on-the-job training by a trained supervisor.
- b. In addition to the 24 hours of initial training, the Subcontractor shall provide 8 hours of supervisor training to all management and supervisory personnel.
- c. The Subcontractor shall provide all employees specified in Paragraphs 1.a and 1.b with 8 hours of refresher training annually. This training is required on or before the anniversary date of the initial training.
- d. All training required by this Special Condition shall comply with the Occupational Safety and Health Administration (OSHA) Standard 29 CFR

1910.120 entitled "HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE".

- e. Should the Subcontractor perform work on-site with employee(s) who are not appropriately trained, a written submittal shall be provided to the Contractor for approval prior to commencement of this work. This submittal shall provide details as to the type and duration of the work, and certify that the work is to occur in a non-exclusion area that is free of exposures to hazardous substances, health hazards, or safety hazards.
- f. Site visitors, vendors, auditors and others who are not full-time, part-time, or routine site workers will be required to complete 45 minutes of Site Visitor Training conducted by the Contractor provided they are escorted on-site at all times by project personnel who are knowledgeable of the exclusion and non-exclusion areas, and will not be exposed to hazardous substances, health hazards or safety hazards.
- g. The Subcontractor is responsible for maintaining the documentation of employees' training and providing a monthly report on the training status of employees to the Contractor.

2. Medical Surveillance Requirements:

- a. The Subcontractor shall provide medical surveillance for all Subcontractor employees who:
1) are or may be exposed to a hazardous substance (i.e. uranium mill tailings above 2000 pCi/g total specific activity), or health hazards at or above the permissible exposure level (PEL), or, if there is no PEL, above the published exposure levels for these substances, without regard to the use of respirators, for thirty days or more a year; or 2) who wear a respirator for thirty days or more a year; or 3) who are injured due to overexposure from an emergency incident involving hazardous substances; or 4) who are members of a HAZMAT Team. Prior to going on site, the Subcontractor shall submit to the Contractor a written explanation which provides justification for any employees who are not included in the medical surveillance program.
- b. The Subcontractor shall provide employees who require medical surveillance with examinations at

the following times: 1) before initial assignment; 2) every twelve months unless the attending physician believes a shorter or longer interval is appropriate (in no case shall the surveillance duration be greater than every two years); 3) at termination of employment from the Uranium Mill Tailings Remedial Action Program unless an examination has occurred within the last six months; 4) immediately when an employee develops symptoms of overexposure to a hazardous substance or health hazard, or is injured or exposed above accepted levels in an emergency situation.

- c. The Subcontractor shall ensure medical examinations are either provided or supervised by a qualified licensed physician. The Subcontractor shall provide, at a minimum, the following information to the attending physician: 1) A copy of OSHA Standard 29 CFR 1910.120; 2) A description of the employee's duties as they relate to the employee's exposure; 3) A copy of the employee's actual or potential exposure levels; 4) A description of the types of personal protective equipment (PPE) used on-site, including respiratory protection; 5) A copy of the employee's past medical examination if requested by the physician.
- d. The physician shall perform, at a minimum, a medical and work history, and an examination that is in relation to the site hazards to which the Subcontractor employee will be exposed including fitness for duty with an emphasis on the ability of the employee to wear an air-purifying respirator and other PPE under stressful conditions such as hot weather and physical work.
- e. The physician shall provide the Subcontractor with a written statement in compliance with OSHA Standard 29 CFR 1910.120 that qualifies or disqualifies the employee on their ability to work on-site. This qualification statement shall specifically address the employee's ability to wear an air purifying respirator. The Subcontractor shall provide a copy of this written statement to the employee and to the Contractor. Employees not qualified to work under the conditions considered in the examination will not be allowed to perform job duties on-site.

3. Record Keeping Requirements:

- a. The Subcontractor shall submit to the Contractor, on the first business day of every month, a complete roster of personnel which lists the following information and accomplishments which comply with OSHA Standard 29 CFR 1910.120, if applicable:
 - Name
 - Social Security Number
 - Site Name
 - Date of Initial 24/40-Hour Training Course
 - Date of Annual 8-Hour Refresher Training Course
 - Date of 8-Hour Supervisor Course
 - Date of Initial Medical Examination
 - Date of Annual Medical Examination
 - Date of Exit Medical Examination
 - Date of Three Day On-The-Job Training
 - Date of Employment Termination
 - b. The Subcontractor shall issue a card to all employees which certifies that they are currently trained and are qualified under the medical examination requirements. The Subcontractor shall ensure each employee has this card readily available for Contractor compliance audits.
4. Responsibility: The Subcontractor is responsible for providing all scheduling and implementation activities related to OSHA Standard CFR 1910.120 and Special Conditions Article SC-7.0. This ensures that employees are trained and medically qualified prior to job assignment. These activities are incidental to the work and there will be no separate payment. In addition, prior costs related to these training and medical examinations which were determined to be unnecessary are not recoverable.
 5. The Subcontractor shall comply with all provisions of OSHA Standard 29 CFR 1910.120, unless more stringent requirements are described or referenced in this document. The Contractor will determine on-site exclusion and non-exclusion areas.
 6. The Subcontractor shall submit to the Contractor for approval a site specific Hazardous Waste Operations, Site Safety and Health Plan in accordance with 29 CFR 1910.120. This plan shall be submitted 10 calendar days prior to any work in a controlled area.

- P. The Subcontractor shall comply with the OSHA Bloodborne Pathogens Standard.
- Q. The Subcontractor shall provide all water retention basins with Life Saving Devices and a means of egress from all basins.
- [R. Operational Readiness Review (ORR): Operational Readiness Reviews will be conducted by the Contractor prior to the start of the following activities; initial startup or restart after a winter shutdown of construction activities; start/restart of rock screening/crushing operations, and any other major operation involving the potential for accident or injury and which is not covered by an existing written Standard Operating Procedure (SOP) as determined by the Contractor.

The purpose of the ORR is to determine that a state of readiness exists to commence operations. The ORR will be conducted by the Contractor with cooperation from the Subcontractor. Following the ORR, an Operational Readiness Evaluation (ORE) will be conducted by the Department of Energy (DOE). Any prestart findings (a finding or concern which is considered detrimental to the readiness state of the operation) shall be corrected by the Subcontractor prior to approval being given by the Contractor to commence operations.

The entire ORR/ORE process takes approximately seven business days to complete. The Subcontractor shall plan its work accordingly.]*

- [S.]* Subcontractor First Aid and Medical Attention Responsibility: In accordance with OSHA standard 29 CFR 1926.50 (a) through (e), the Subcontractor shall ensure the availability of prompt medical attention in the event of serious illness or injury. The Subcontractor shall provide adequately trained personnel, documentation subject to verification, at the project site to render first aid, and first aid supplies approved by a consulting physician. The Subcontractor also shall provide for the prompt transportation of injured or ill persons to a physician or hospital, and communication systems compatible with the emergency medical services to be utilized.

* P.I.D. 11-S-07

1. The Subcontractor shall provide at least one emergency medical technician (EMT-Basic) certified in the State of Colorado, at the processing sites and at the disposal cell site at all times when work is performed.
2. The Subcontractor, in its required Emergency Response Plan, shall develop contingency response procedures to address differing medical emergencies (e.g., response for a heart attack versus a fractured leg), and availability/unavailability of emergency medical service agencies. These procedures shall be coordinated with available emergency medical service agencies for care and transport of injured or ill employees.
3. The Subcontractor shall provide telephones and/or radios for communication with the emergency medical services to be utilized. Emergency telephone numbers for medical services, including available helicopter ambulance services shall be posted near telephones. The Subcontractor also shall comply with all requirements for receiving helicopter ambulances at the processing sites and the disposal cell locations.

SC-8 HEALTH PHYSICS

Portions of the Subcontract work area are located in radiologically controlled area. All work shall be governed by the essential requirements given in the following paragraphs:

- A. Health Physics (HP) Personnel: The Site Manager will monitor the construction work through HP personnel employed by him. The HP personnel will provide radiological surveillance over construction activities and advise supervision on matters concerning radiation safety as related to activities or conditions affecting the construction work.
- B. Radiologically Controlled Areas:
 1. Radiologically controlled areas shall be established as needed at the discretion of the Site HP Manager. They will normally include areas where radioactive contamination levels exceed 10 times the applicable limits or where airborne radioactive material concentrations or external radiation dose exceed the applicable limits.
 2. The Contractor will provide HP personnel to control access to radiologically controlled areas.

3. The Subcontractor shall provide access control facilities as specified in Section 01500.
4. All personnel will be required to sign in and sign out of radiologically controlled areas, including but not limited to name, time and areas where they worked.
5. No eating, drinking, smoking, or chewing will be allowed in a radiologically controlled area. Personnel found to be in violation of this rule may be restricted from the controlled area, and/or have their training certification revoked. Repeated violations may result in permanent restriction from UMTRA sites.
6. All personnel will be required to self-monitor (frisk) for radioactive contamination upon leaving the controlled area. Personnel will be instructed in self-monitoring procedures as a part of the Radiation Worker Training.
7. The Subcontractor shall observe controlled area restrictions and shall take applicable precautions.
8. Dust suppression techniques are required to limit exposure to airborne radionuclides.

C. Protective Clothing for Contamination Control:

1. Protective clothing shall be utilized for contamination control at the discretion of the Contractor.
2. When required, protective clothing may consist of coveralls, gloves, rubber boots, shoe covers, and/or respirators in any combination. At a minimum, all personnel shall wear rubber boots within the controlled area unless this is determined to be unnecessary by the site HP manager.
3. Protective clothing will be provided to the Subcontractor at no charge on a loan basis.
4. Protective clothing will be issued by Contractor personnel at the access control area. Protective clothing shall be put on and removed at the access control area or radiologically controlled area boundary. Personnel will be required to change out of the protective clothing prior to leaving the controlled area.
5. The Contractor will determine when respiratory protection is required during certain construction

activities, when the potential for airborne radiological limits could be exceeded. The Contractor's access control personnel will specify when and where respirator protection is required.

6. The Subcontractor shall ensure that protective clothing items are stored in a weatherproof facility inside the controlled area boundary and that storage areas are maintained in proper order.
7. Compliance with required protective clothing standards is mandatory.

D. Training Requirements:

- [1. All personnel who require access to UMTRA airborne or contaminated areas will be given Radiological Worker II (RW II) training biennially. Course length will be sixteen hours. Class size will be limited to 15 persons unless otherwise approved by the Contractor. A four hour RW II refresher course will be completed in the off year when full retraining is not required.
2. All personnel who may routinely encounter radiological barriers or postings will complete General Employee Radiological Training (GERT) annually. Course length will be two hours. This training is not required for RW II trained personnel.
3. RW II and GERT training is available to Subcontractor personnel at no cost for the instruction. The Subcontractor shall notify the Contractor at least three days in advance when training is desired.
4. Examinations: There will be a RW II examination and a practical evaluation, both of which must be successfully completed by the employee, prior to working on site. RW II candidates who fail either the examination or practical evaluation will be allowed to retake the examination or practical evaluation after counseling by the Contractor. Should the RW II candidate fail either the examination or practical evaluation a second time, a retake will only be administered after reparting the course. If necessary, further retakes may be arranged with the written concurrence of the Contractor.

There will be a GERT examination which the employee must pass prior to working unescorted at the site.]*

* P.I.D. 11-S-07

5. Training in the proper use of respirators for performing specific tasks may be required. For respirator training and employee requirement, see Articles SC-7.B.2 and SC-7.B.4.

E. Radiation Exposure Limits and Dosimetry:

1. Radiation exposure on the UMTRA Project is expected to be well within allowable radiation exposure limits.
2. Prior to working at the construction site each employee shall provide prior radiation exposure records as applicable.
3. Whole body radiation exposure shall be determined by the use of Personal Thermoluminescent Dosimeters (TLD). The Contractor will provide TLDs as required.
4. While working at the construction site, each employee who is issued a TLD is required to wear that TLD. TLDs will be issued and collected upon entrance to and exit from the controlled area.
5. If an individual loses a dosimeter (TLD), that individual shall be restricted from the controlled area until an exposure evaluation has been completed and reviewed by the site Health Physics Manager.
6. No one under the age of 18 shall be permitted to enter or work in the controlled area.

F. Bioassay (Urine and/or Fecal Samples):

1. Employees working in radiologically controlled areas may be required to submit an initial, quarterly, and termination bioassay sample (typically 1 liter will be required).
2. Employees may be required to submit additional bio-assay samples on an occasional basis, to ensure that applicable radionuclide exposure standards are being met.
3. It is the Subcontractor's responsibility to ensure that each employee submits bioassay samples as required by the Subcontract.
4. The Contractor will notify the Subcontractor of any employee who fails to provide a required bioassay sample. The communication will state that urine sample submittal to the Contractor representative is a subcontract requirement. If the issue is not resolved,

the Contractor's Subcontract Administrator will notify the Subcontractor, by written communication, that the employee will be restricted from all radiologically controlled areas.

5. Employees who fail to provide a bioassay sample will not be permitted on the site.
6. In the unlikely event that an employee has a confirmed positive bioassay result, he may be temporarily restricted from the controlled area for radiological evaluation.
7. The Subcontractor shall notify the Contractor of any personnel terminations or transfers as early as possible, but no later than two working days in advance of such terminations or transfers. This notification will allow sufficient time to collect a termination bioassay sample.

(NOTE: The Contractor shall be notified of the termination of any employee so that a final bioassay sample may be collected. This final sample is crucial to the overall radiation program.)

8. Sample tampering and/or deliberate contamination will result in exclusion from all UMTRA work.
- G. Warning Signals: Certain circumstances such as unusual or unanticipated radiation levels, presence of toxic substances, or unsafe working conditions may prompt the Contractor to give verbal information or directions, as Warning Signals, directly to the Subcontractor and his employees. The Subcontractor and his employees shall take required actions as directed by the Contractor or his representative. The Subcontractor shall obtain the name and title of the Contractor's representative providing such information.

H. Decontamination and Monitoring of Vehicles and Equipment:

1. Vehicles, equipment and tools that are to be removed from radiologically controlled areas (free release) shall be cleaned of all potentially contaminated soils and will be monitored for radioactive contamination by the Contractor prior to removal from the area. Vehicles and equipment shall be decontaminated prior to entering and performing work in uncontaminated areas.
2. When vehicles are decontaminated for release from one radiologically controlled area to another (controlled release), they will be monitored for contamination by

the Contractor. The Contractor will initially monitor 100 percent of the vehicles for contamination. As experience begins to indicate that the decontamination process is being performed adequately, the percentage of vehicles that are monitored may be reduced to as few as 10 percent. Monitoring may be increased as contamination levels increase.

3. Vehicle decontamination facilities shall be provided as specified in Section 01500.
4. During snowfall or icing conditions complete removal of snow or ice may be required for radiological monitoring.
5. Equipment will normally be decontaminated prior to any maintenance other than routine servicing.
6. Subcontractor shall be responsible for decontamination of Contractor's vehicles and Contractor's support vehicles and equipment before exiting the controlled area.

I. Tailings Leakage in Uncontrolled Areas:

1. Leakage of tailings or contaminated materials will not be allowed in uncontrolled areas.
2. The Contractor will perform baseline surveys of all haul routes outside of controlled areas.
3. The Contractor will periodically monitor the haul route and compare the data against baseline to detect spills of contaminated material. The Subcontractor shall clean up any contaminated material leaked or spilled outside of the controlled area, and the area shall be restored as required by the Contractor.

J. Disposition of Contaminated Equipment, Tools and Material:

1. The Subcontractor shall use his own or rental equipment in performing the required work under this Subcontract. All tools, vehicles, equipment and material will be inspected for radioactive contamination by the Site HP Manager or his designee prior to removal from the construction area.
2. Should the Subcontractor's tools, material, or equipment become contaminated, they shall be decontaminated before removal from the area. If decontamination becomes necessary, the Site HP Manager will provide instructions for decontamination by the Subcontractor's employees.

Decontamination may consist of steam cleaning, sand blasting, dry brushing, or washing with appropriate liquids. Decontamination required beyond these described will be handled under Article GP-52, "CHANGES" of the General Provisions. All releases shall be on an ALARA basis as determined by the Contractor.

3. If decontamination proves impracticable or impossible, the tools, material, or equipment in question will be retained by the Contractor and an equitable adjustment for same will be negotiated with the Subcontractor provided that:
 - a. There is no fault or negligence of the Subcontractor contributing to the contamination;
 - b. The Subcontractor has followed all the specific instructions of the authorized HP personnel who have surveillance over the work;
 - c. Items or equipment confiscated from the Subcontractor will be documented by a Confiscation Notice furnished to the Subcontractor by the Contractor and signed by HP personnel and the Site Manager;
 - d. The Subcontractor allows reasonable time (a minimum of ten working days, excluding weekends and holidays) in which to attempt decontamination of the item(s) in question. The reimbursement schedule will be as follows:
 - 1) Tools valued less than \$300.00 at 95% of replacement cost.
 - 2) Tools/Equipment \$300.00 and up: If less than one (1) year old or at top of depreciation schedule, at 75% of replacement cost; if at bottom of or off the depreciation schedule, at 50% of replacement cost.
 - e. Failure to agree upon an equitable adjustment shall constitute a dispute within the meaning of Article GP-41 of the General Provisions.
 - f. In view of the foregoing, the Subcontractor is encouraged to plan his work so as to minimize the transfer of equipment into and out of the construction area.

K. Use of Radiation Work Permits:

1. Radiation Work Permits (RWPs) are required for work activities which are not routinely performed, within designated UMTRA Project site boundaries or at designated vicinity properties and:
 - a. Have the potential for exposing involved personnel to substantially higher levels of radiation and/or radioactive material than are normally encountered.
 - b. Require specific training in the use of specialized equipment or techniques.
 - c. Have a greater than normal potential for personnel contamination to occur.
 - d. Are not covered by other Health Physics Procedures.
2. Situations requiring the use of a RWP include, but are not limited to, the following specific work activities:
 - a. Remediation in a contaminated crawl space of a structure.
 - b. Demolition or decontamination of mill buildings.
 - c. Entry into yellow cake buildings.
 - d. Work in a Radiation Area.
3. In addition to signing in on the standard access control log, work crew personnel shall sign in on UMTRA Personnel RWP Log prior to beginning work governed by a RWP. There will be a separate UMTRA Personnel RWP Log for each RWP that is in effect. At the completion of work or upon leaving the task governed by a RWP, work crew personnel are required to frisk and sign out. The purpose is to track time spent working on the job that is governed by each specific RWP.
4. All personnel listed on a RWP shall receive a pre-job review prior to performing any work governed by the RWP.
5. A RWP is only in effect while it is posted.
6. A RWP may be terminated by the Site Health Physics Manager or designee if work is not being performed in accordance with the provisions of the RWP.

SC-9 SUBMITTALS

Pursuant to the provisions of Specification Section 01300 - Submittals, the Subcontractor shall submit samples of materials, schedules and reports, shop drawings, product data, manufacturer's instructions, and design calculations and design drawings to the Contractor.

SC-10 QUALITY ASSURANCE

- A. All work shall be performed to the requirements of the Contractor's Quality Assurance Program. This program meets the applicable requirements of 10 CFR 50 Appendix B and ASME NQA-1-89. The program will be wholly administered by the Contractor for permanent record purposes. All Quality Records will be generated by and maintained by Contractor's personnel except as otherwise noted.
- B. All full-time subcontractor personnel assigned to the UMTRA Project shall receive Indoctrination and Training in the MK-F Quality Assurance Program Plan. The training will be scheduled along with the required health physics training at each site and involves reading a handout and watching a video which is anticipated to take approximately 10 minutes. The Subcontractor shall provide to the Contractor updated personnel rosters of those personnel assigned to the UMTRA Project on an ongoing basis. Each subcontract employee shall sign and date a sheet certifying that he or she received the Quality Assurance Program training.

SC-11 PERMITS

- A. The Contractor will provide the following permits and notifications as required, for the facilities and activities depicted on the Subcontract Drawings, except as noted below in Article SC-11.B:
 - 1. Dredge and Fill (404) Permit - for wetlands
(U.S. Army Corps of Engineers)
 - 2. Threatened or Endangered Species Consultation
(U.S. Fish and Wildlife Service)
 - 3. Cultural Resource Clearance
(Colorado Historic Preservation Office and Advisory Council in Historic Preservation)

4. Air Pollution Emission Permit - for earthmoving activities at the processing sites, disposal site and borrow area
(Colorado Department of Health, Air Pollution Control Division)
5. Air Pollution Emission Permit - for land development at the disposal site
(Colorado Department of Health, Air Pollution Control Division)
6. Air Pollution Emission Permit - for land development at the haul roads
(Colorado Department of Health, Air Pollution Control Division)
7. Construction Dewatering Permit - disposal site
(Colorado Department of Health)
8. [Text Deleted]* [(Not Used)]*
9. Right-of-Way (299) - for haul roads
(U.S. Bureau of Land Management)
10. [Text Deleted]* [(Not Used)]*
11. [Text Deleted]* [(Not Used)]*
12. Water Service Contract
(U.S. Bureau of Reclamation)
13. Water Rights - surface and water storage for processing sites, disposal site and Disappointment Valley borrow area
(Colorado District Water Court)
14. Conditional Use Permit
(San Miguel County Board of Commissioners)
15. Certificate of Designation - for solid waste disposal site - for tailings embankment
(San Miguel County Board of Commissioners and Colorado Department of Health)
16. Approval of Road Construction
(San Miguel County and Colorado Department of Transportation)

* P.I.D. 11-S-03

17. County Road Access Permit
(San Miguel County Roads Department)
 - [18. State Highway Access and Utility Permit - for processing sites and disposal site
(Colorado Department of Transportation)]*
 19. County Road Closure and Detour Approval
(San Miguel County Roads Department)
 20. Re-Zoning/Use Permit - for firehouse relocation
(San Miguel County Board of Commissioners)
 21. Stormwater CPDS Permits - for processing, disposal, and borrow sites
(Colorado Department of Health)
 22. Wastewater CPDS Permits - for processing sites
(Colorado Department of Health)
- B. All other permits and notifications, including but not limited to the following, shall be the responsibility of the Subcontractor in accordance with Article GP-47 of the General Provisions. The Subcontractor shall provide copies of all other permits and notifications to the Contractor.
1. Demolition Permit and Notice of Intent to Perform Asbestos Abatement - asbestos survey prior to demolition
(Colorado Department of Health, Pollution Control Division)
 2. Spill Prevention Control and Countermeasures Plan - for on-site fuel/oil storage
(U.S. Environmental Protection Agency)
 3. Air Pollution Emission Notice and Emission Permit - for trucks, rock crushers, screens, or other sources of air pollution
(Colorado Department of Health, Air Pollution Control Division)
 4. Open Burning Permit (for uncontaminated materials)
(Colorado Department of Health, Air Pollution Control Division)
 5. Right of Entry to State Highway
(Colorado Department of Transportation)

* P.I.D. 11-S-07

6. Building Permit (for Trailer Pads)
(San Miguel County Planning Department)
 7. Mobile Home Siting Permit
(San Miguel County Planning Department)
 8. Approval of Sewage Disposal System Installation
(San Miguel County Department of Health)
 9. Permit to Construct a Well - for Additional Water Supply
and/or Monitor Wells
(Colorado Division of Water Resources)
 10. Well Abandonment Affidavit - material containment plan
(Colorado Division of Water Resources)
 11. For existing or privately owned borrow pits/quarries,
Subcontractor shall verify that the owner/operator has
all permits necessary to operate these facilities. If
Subcontractor elects to develop borrow areas other than
Disappointment Valley borrow source, he shall obtain all
permits required to operate and to obtain access to
those areas including, but not limited to, the
following, as required:
 - a. Mining and Reclamation Permit
(Colorado Mineral Land Reclamation Division)
 - b. Air Pollutant Emissions Notice and Permit
(Colorado Department of Health, Air Pollution
Control Division)
 - c. Land Use Permit
(County Planning Department)
 - d. Electrical Permits as required.
 - e. Threatened or Endangered Species Consultation
(U.S. Fish and Wildlife Service)
 - f. Cultural Resource Clearance
(State Historic Preservation Office and Federal
Land Management Agency [if on federal land])
 - g. Stormwater Permit - for control of surface runoff
from the borrow site
(Colorado Department of Health, Water Quality
Control Division)
- C. The Subcontractor shall comply with the provisions of the
permits at all times during the execution of the

Subcontract. The Contractor will make available to the Bidders the permits and their provisions for review by the Bidders.

- D. Separate measurement or payment will not be made for work required of the Subcontractor for obtaining additional permits and for compliance with the provisions of all permits, unless specifically provided for in this Subcontract. All costs in connection with obtaining such permits and for compliance with such permits will be considered incidental to the Subcontract.

SC-12 SUBCONTRACT LABOR AND EQUIPMENT RATES

- A. Within 30 days after receipt of Notice to Proceed, the Subcontractor shall furnish to the Contractor a list of all equipment to be used on the Project. The list, as a minimum, shall include the following for each piece of equipment:
1. Equipment number, make, model, type, year of manufacture, capacity and/or horsepower, attachments, and any other information necessary to determine applicable Rental Rate Blue Book for Construction Equipment rates. Attachments, if any, shall be reasonable and necessary for the work intended on the job or not be included when calculating appropriate rates.
 2. Hourly rental rate, calculated at the Subcontractor's normal rate for each piece of equipment, not to exceed 60 percent of the monthly rate, divided by 176, from the current edition of the Rental Rate Blue Book for Construction Equipment.
 3. An hourly operating rate for fuel, oil, parts, maintenance and repairs, etc. for actual hours of operation only. This rate shall be not more than 100 percent of the operating rate from the current edition of the Rental Rate Blue Book for Construction Equipment.
 4. When standby of equipment is required, the standby rate shall not exceed hourly rental rate calculated at 60 percent of the monthly rate, divided by 176, from the current edition of the Rental Rate Blue Book for Construction Equipment. No profit will be allowed for standby. Maximum standby time allowed shall be for 8 hours in any day, 40 hours in any week, or 176 hours in any month.

5. The above equipment rates shall be exclusive of Subcontractor overhead and profit.
 6. For any item of equipment utilized which is not listed in the Blue Book for Construction Equipment and for which the Subcontractor wishes to claim a higher rate than for a similar listed item of equipment, the Subcontractor shall contact Data Quest and obtain the necessary information and submit to the Contractor to justify the higher rate.
- B. The above rate information shall also be provided for any subsequent equipment brought onto the site during the term of the Subcontract in addition to the initial list, and shall be provided within five days of the date the equipment arrives.
 - C. The initial equipment rate list submittal, with additions, shall be valid for all pieces of equipment from its receipt until July 1 of the following year.
 - D. The equipment rate list shall be revised on July 1 of each year with the current Blue Book rates. These rates shall be used until the equipment rate list is revised on July 1 of the following year.
 - E. The Subcontractor shall maintain and submit records annually to the Contractor of fuel taxes and vehicle fees paid to the State of Colorado for all construction equipment and vehicles used on the project.
 - F. Within 30 days after receipt of Notice to Proceed, the Subcontractor shall furnish to the Contractor labor rates including premium time for all craft designations to be used on the Project as follows:
 1. List craft category and classification (i.e., loader operator, 6 cy; truck driver, 3 axle; etc.). The category and classification should be consistent with the Davis-Bacon wage determination for the Project.
 2. Labor cost rates including fringe benefits, payroll taxes, and insurance.
 3. Each item in 1 and 2 above shall be listed separately.

The above labor rate information shall be revised and resubmitted on January 1 of each year with current payroll burden rates.

The above labor rates shall be exclusive of Subcontractor overhead and profit.

- G. The rates provided in Paragraphs A through F above shall be used for changes to the Subcontract where unit prices or other methods of pricing do not apply and shall be used solely at the discretion of the Contractor.

SC-13 SUBCONTRACT CHANGE NOTICE PROPOSAL

The Subcontractor, in connection with any proposal he makes for a Subcontract Change Notice, shall furnish a price breakdown, itemized as required by the Subcontract Administrator. Unless otherwise directed, the breakdown shall include all estimated labor and equipment hours, and associated costs, materials, subcontracts, and overhead and profit required to permit an analysis, and shall cover all work involved in the Change Notice, whether such work was deleted, added or changed. Any amount claimed for subtier-subcontractors shall be supported by a similar price breakdown and/or quotes from the subtier-subcontractors. In addition, if the proposal includes a time extension, a justification therefor shall be furnished. The proposal, together with the price breakdown and time extension justification, shall be furnished to the Subcontract Administrator within 30 calendar days after receipt of the Change Notice or as otherwise required by the Subcontract Administrator.

SC-14 VARIATIONS IN QUANTITIES

In all cases, except cancellation of one or more line items, where the quantity of a unit priced line item in the Subcontract is an estimated quantity, and where the actual quantity of such line item varies by more than 10 percent above or 10 percent below the originally estimated quantity stated in the Subcontract, an adjustment in unit price shall be negotiated upon demand of either party for the quantities above or below the stated variation.

SC-15 LAWS AND REGULATIONS

Subcontractor shall give all notices and comply with all laws, ordinances, rules and regulations applicable to the Work. If Subcontractor observes that the Specifications or Subcontract Drawings are at variance therewith, Subcontractor shall give Contractor prompt written notice thereof, and any necessary changes shall be adjusted by an appropriate Modification. If Subcontractor performs any Work

knowing or having reason to know that it is contrary to such laws, ordinances, rules and regulations, and without such notice to Contractor, Subcontractor shall bear all costs arising therefrom; however, it shall not be Subcontractor's primary responsibility to make certain that the Specifications and Subcontract Drawings are in accordance with such laws, ordinances, rules and regulations.

SC-16 FUNDING LIMITATIONS

- A. Of the total Subcontract Price, the sum of \$_____ (to be identified at time of Notice to Proceed) is presently available for payment to the Subcontractor under this Subcontract. It is anticipated that additional funds will be allotted from time to time to this Subcontract subject to Government appropriations available in this fiscal year or succeeding fiscal years. The responsibilities of the Contractor are limited by this clause notwithstanding any contrary provision of the "Payments to Subcontractors" clause or any other clause of this Subcontract.
- B. The Subcontractor agrees to perform or have performed work up to the point at which, in the event of termination of this Subcontract pursuant to the clause hereof entitled "Termination for Convenience", the total amount payable by the Contractor (including amounts payable in respect of lower-tier subcontracts and settlement costs), pursuant to paragraph E below, would in the exercise of reasonable judgment by the Subcontractor approximate the total amount at the time allotted to this Subcontract. The Contractor shall not be obligated in any event to pay or reimburse the Subcontractor in excess of the amount from time to time allotted to this Subcontract, anything to the contrary in this clause or the clauses hereof entitled "Termination for Convenience" as specified in Article GP-55 and "Payments to Subcontractors" as specified in Article GP-38 of the General Provisions notwithstanding.
- C. It is contemplated that funds presently allotted to this Subcontract will cover the work to be performed until _____ (to be identified at time of Notice to Proceed). In the event funds allotted are considered by the Subcontractor to be inadequate to cover the work to be performed until the above date, the Subcontractor shall notify the Subcontract Administrator when the work will reach a point at which, in the event of termination of this Subcontract pursuant to the clause hereof entitled "Termination for Convenience", the total amount payable by the Contractor (including amounts payable in respect of lower-tier subcontracts and settlement costs) pursuant to

Paragraph E below, will approximate 85 percent of the total amount then allotted to this Subcontract. Such notice shall be in writing and shall be given not less than 45 days nor more than 60 days prior to the estimated date when such point will be reached. Such notice shall also state the estimated amount of additional funds required to continue performance to the above stated date.

- D. The Contractor may at any time, allot additional funds for continued performance of this Subcontract. The Subcontract Administrator will promptly notify the Subcontractor in writing, of any such allotment and: (a) determine on the applicable period of Subcontract performance which shall be covered by such funding; (b) modify the date stated in Paragraph C above in order to reflect such extended period of coverage; and (c) modify the amount stated in Paragraph A above. The provisions of Paragraphs B and C, above, shall apply to such additional allotted funds and modified date.
- E. In the event the Subcontractor incurs additional costs, or is delayed in the performance of the work under this Subcontract, solely by reason of the failure of the Contractor to allot additional funds pursuant to Paragraph D above in the amounts sufficient for the timely performance of this Subcontract, and if additional funds are allotted by the Contractor pursuant to Paragraph D for continued performance of this Subcontract, then an equitable adjustment may be made in the Subcontract Price (including appropriate target, billing and ceiling prices where applicable) or in the time required for the performance of the work, or both, and this Subcontract may be modified in writing accordingly; provided, that the Subcontractor provides to the Subcontract Administrator written notice of its claim of entitlement to an equitable adjustment prior to the date then stated in Paragraph C.
- F. Nothing in this clause shall affect the right of the Contractor to terminate this Subcontract pursuant to the clause of this Subcontract entitled "Termination for Convenience".
- G. In order to adequately determine the ongoing current status of the project, and to assure that adequate funding is available in the event that suspension or termination for convenience becomes necessary, the Subcontractor is hereby required to submit a report monthly detailing information necessary to properly determine the expected cost to the Government for such activity.
- H. The monthly report specified in Paragraph G above shall be submitted monthly on the 20th of the month. This report

shall be submitted to the Subcontract Administrator, and is not subject to approval. This report shall provide the actual cost to date, a reasonably accurate estimate of monthly suspension cost (assuming complete suspension), a reasonably accurate estimate of termination cost (as provided in GP-55) as of the date of this monthly report. This report shall include the total amounts that may be payable by the Contractor (including amounts payable in respect of lower-tier subcontracts and settlement costs).

SC-17 CERTIFIED PAYROLLS

In addition to the copies of certified payrolls that are to be submitted each week to the Subcontract Administrator, one copy shall also be submitted to the Site Manager.

SC-18 SUBCONTRACTOR'S LIABILITY

The Subcontractor has total liability for all of his own equipment, supplies, tools, etc., brought on the jobsite or used in the performance of his Subcontract.

SC-19 COLORADO SALES AND USE TAX

- A. The Subcontractor shall submit the enclosed Subcontractor Information Sheet to the Contractor's Business Manager and a copy to the Subcontract Administrator with the required information for his company and for any lower-tier subcontractor. Subcontractors listed on the Information Sheet will be provided exemption certificates from the State of Colorado upon approval of the application by the Contractor. The above information shall be provided to the Contractor for any subsequent lower-tier subcontractors utilized during the course of this Subcontract.
- B. Upon obtaining the certificate from the Colorado Department of Revenue, the Subcontractor and lower-tier Subcontractors shall be exempt from state and local sales and use tax on the purchase of construction materials for use in the building, erection, alteration, or repair of structures, highways, roads, streets, and other public works owned and used by the United States Government, the State of Colorado, its departments and institutions, and its political subdivisions in their governmental capacities only.
- C. The City of Denver imposes a 3 percent sales or use tax but allows an exemption from the tax for goods delivered outside the city limits by common carrier or the vendor's vehicle.

- D. The City of Denver does not exempt materials purchased by a Subcontractor for use in a job for an exempt institution.
- E. Consumable supplies used in the performance of the Subcontract and not becoming part of the permanent construction project will be taxable to the Subcontractor.

SC-20 MEASUREMENT AND PAYMENT

- A. Unless otherwise provided in the Subcontract Documents, no separate measurement or payment will be made for compliance with the provisions of the General Provisions, General Conditions and Special Conditions. Full compensation for such work will be considered to be included in the related items of the Bid Schedule or incidental to the Subcontract.
- B. Payment for the cost of premiums paid by the Subcontractor to obtain performance and payment bonds will be as specified in Article GP-38.E of the General Provisions. The Subcontractor shall quote the price for the premiums by the lump sum in the Bid Schedule. (Bid Schedule Item 002)

SC-21 LIMITATIONS ON SUBCONTRACTING

- A. By submission of an offer and execution of a Subcontract, the Subcontractor agrees that in the performance of the Subcontract:
 - 1. For general construction the Subcontractor shall perform at least 40 percent of the cost of the Subcontract, not including the cost of materials, with its own employees.
- B. Any deviation from the above limitations on subcontracting requirements will require prior approval of the Contractor.

SC-22 BULLETIN BOARDS

Bulletin boards with all required bulletins and all other displayed items shall be located in the Access Control Trailers.

SC-23 CONTAMINATED MATERIALS HAUL INSURANCE REQUIREMENTS

The Subcontractor shall provide the Contractor evidence of insurance (additional bonding will not be accepted) as required by 49 CFR 387, Minimum Levels of Financial Responsibility For Motor Carriers. This requirement is in addition to those limits required by General Condition (GC-7). All other conditions contained within GC-7 shall also apply to this additional insurance. It shall be the Subcontractor's responsibility to obtain a determination

from the U.S. Department of Transportation as to the definition of a hopper-type vehicle. A copy of this determination shall be submitted to the Contractor along with the evidence of insurance as well as a description of the type of vehicle the Subcontractor will use.

SC-24 ENFORCEMENT OF SITE RULES

A. The following site rules are Subcontract requirements and shall be followed by all personnel.

1. No eating, drinking, smoking or chewing (tobacco, snuff, gum, etc.) is allowed in controlled areas.
2. Personal safety equipment (hard hat, safety vest, and leather boots) is required for access to controlled areas.
3. Personal protective equipment (respirators, protective clothing, etc.) shall be used when directed by Contractor staff, or as per subcontract.
4. Personnel shall self-monitor (frisk) for radioactive contamination using standard methods (as taught in Radiation Worker training) upon leaving the controlled area.
5. Entry to, and exit from, controlled areas, radiological areas, exclusion zones and other designated areas will be through approved access locations.
6. Employees that are required to provide bioassay samples shall pick up the sample container within 2 working days of notification, and shall return the sample within 2 days.
7. Personnel shall participate in the Safety, Health, and Radiological training that is required for their job assignment and shall participate in refresher training at the required periodicity.

Compliance with these site rules is mandatory for all personnel. Willful violation will result in a written warning to the employee via the Subcontractor, temporary restriction from controlled areas, and/or mandatory retraining. Repeat violations will result in permanent restriction from UMTRA sites.

END OF SECTION 00800

Subcontractors listed below will be awarded exemption certificates upon approval of your application. Only those subcontractors who purchase construction or building materials for inclusion in the exempt project should be listed. Those subcontractors who provide service only should not be included.

SUBCONTRACTOR INFORMATION

(Additional sheets may be attached if necessary)

Name & Address of Subcontractor:	Name of contact person:	Business phone number:
	Amount of subcontract:	Colorado withholding account number:
	Type of construction:	
Name & Address of Subcontractor:	Name of contact person:	Business phone number:
	Amount of subcontract:	Colorado withholding account number:
	Type of construction:	
Name & Address of Subcontractor:	Name of contact person:	Business phone number:
	Amount of subcontract:	Colorado withholding account number:
	Type of construction:	
Name & Address of Subcontractor:	Name of contact person:	Business phone number:
	Amount of subcontract:	Colorado withholding account number:
	Type of construction:	
Name & Address of Subcontractor:	Name of contact person:	Business phone number:
	Amount of subcontract:	Colorado withholding account number:
	Type of construction:	
Name & Address of Subcontractor:	Name of contact person:	Business phone number:
	Amount of subcontract:	Colorado withholding account number:
	Type of construction:	
Name & Address of Subcontractor:	Name of contact person:	Business phone number:
	Amount of subcontract:	Colorado withholding account number:
	Type of construction:	
Name & Address of Subcontractor:	Name of contact person:	Business phone number:
	Amount of subcontract:	Colorado withholding account number:
	Type of construction:	
Name & Address of Subcontractor:	Name of contact person:	Business phone number:
	Amount of subcontract:	Colorado withholding account number:
	Type of construction:	

SPECIFICATIONS

Division 1
General Requirements

SECTION 01010

SUMMARY OF WORK

PART 1 - GENERAL

1.1 DESCRIPTION OF THE PROJECT

A. General:

1. The Work under this Subcontract covers the removal of contaminated materials from two areas, known as the Union Carbide (UC) mill area and the North Continent (NC) mill area and placing the contaminated materials in the tailings embankment located in the Burro Canyon (BC) area. All areas are in the western portion of San Miguel County, Colorado. The 24.5-acre NC site is in Section 30, Township 44 North, Range 18 West, New Mexico Principal Meridian. The 81.5-acre UC site is in Section 25, Township 44 North, Range 19 West, New Mexico Principal Meridian. The 65-acre BC site is in Sections 21 and 28, Township 44 North, Range 18 West, New Mexico Principal Meridian.
2. Access to all sites is off Colorado Highway 141. Access to the UC site is via San Miguel County Road CR-S8. Access to the NC site is via San Miguel County Road CR-10R.
3. Both the UC and NC sites contain a tailings pile area, some abandoned mill structures, abandoned utilities and windblown/waterborne contaminated areas. In order to stabilize the tailings and meet EPA standards, the tailings and other contaminated materials from the UC and NC sites will be consolidated in a tailings embankment to be constructed at the designated BC site.
4. Access to the NC site will be by San Miguel County Road CR-10R. This road requires upgrading and will be used exclusively by the Subcontractor. During the term of this Subcontract, the public will be denied access on this road.
5. Access to the UC site will be by San Miguel County Road CR-S8. County Road CR-S8 will remain open to the public during construction. The portion of the road that crosses the UC site will be rebuilt. Access to the BC site is by County Road T-11 off State Highway 141. The existing road requires upgrading.

1.2 SCOPE OF WORK

A. General:

1. The work described here is primarily site work related to the excavation of contaminated radioactive materials from both the NC and UC mill areas and placement in the tailings embankment to be located at the BC site. A cover consisting of radon barrier, frost protection layer and erosion protection materials will be placed over the embankment. The Work is outlined in Article 1.2.B below. Such Work is more fully detailed in the Specifications and Subcontract Drawings included herein.
2. The Work includes furnishing all plant, labor, tools, equipment, materials, transportation, and services, and performing all operations necessary for and properly incidental to the construction as shown and noted on the Subcontract Drawings and as specified in these Specifications.

B. The Work Includes:

1. Mobilization: See Section 01019.
2. Road construction as specified in Section 02205 including the following:
 - a. Upgrading of County Road CR-10R to the NC site.
 - b. Reconstruction of County Road CR-S8 on original alignment at the UC site.
 - c. Upgrading County Road T-11 to the BC site.
 - d. Excavations at junction of BC access road and State Highway 141.
3. Construction Facilities: Construction facilities, as specified in Section 01500.
4. Temporary Controls: See Section 01560.
5. Demolition: Demolition of existing foundations, structures, vehicles, existing fences, piping and certain new structures and facilities constructed or installed under this Subcontract shall be demolished as specified in Section 02050, for placement in the tailings embankment.
6. Removal, plugging and abandoning, and demolition of existing utilities as specified in Section 02050 for placement in the tailings embankment.

7. Removal, handling and disposal of asbestos containing materials and identified hazardous and non-hazardous waste materials, as specified in Section 02081.
 8. Sealing of existing monitor wells as specified in Section 02090.
 - [9. Excavation of uncontaminated materials for tailings embankment and stockpiling for later use as radon barrier material or topsoil and backfill for final site grading.]*
 10. Excavation of tailings and contaminated materials from the tailings piles and other areas of the UC and NC sites. Excavation of contaminated materials within a gasline right-of-way in the UC site.
 11. Construction of Tailings Embankment: Construction of tailings embankment at the BC site using tailings from both the UC and NC sites and other contaminated materials resulting from excavations, debris resulting from the demolition, and sediments from the retention basins.
 12. Cover Construction: Construction of a protective cover over the tailings embankment consisting of a compacted layer of radon barrier material, a frost protection layer and layers of rock bedding and riprap from borrow areas or required excavations.
 13. Removal of construction facilities.
 14. Restoration of Sites: After removal of contaminated material, the areas of excavation on and around the UC and the NC sites and borrow areas shall be graded and seeded as shown on the Subcontract Drawings. Areas of fill, including permanent spoil pile at the BC site, shall be graded and seeded. All disturbed areas of the UC, NC and BC sites shall also be seeded.
- C. The above description of the Work is for general information only, and in no way limits the responsibility of the Subcontractor for constructing the Work in strict accordance with the Subcontract Drawings and Specifications listed in the Table of Contents.

* P.I.D. 11-S-03

Document No. 3885-SRK-S-01-02416-04

Issued for Construction-Revision 2

Summary of Work

01010 - 3

SRK

WP51
022195

9. Construct radon barrier cover over the contaminated material in the tailings embankment. [Radon barrier material shall consist of selected fine-grained material obtained from stockpiled material from required excavation at the Burro Canyon Site.]*
10. Construct frost protection layer over the radon barrier. Frost protection material shall come from stockpiled material from required excavation at the BC site.
11. Place erosion protection materials over the frost protection barrier. The erosion protection materials shall consist of a layer of bedding material topped by a layer of rock riprap.
12. Site Restoration: Grade the UC, NC and BC sites and borrow areas to provide drainage including placement of uncontaminated fill and revegetation. Restore access road to BC site to original width and reseed disturbed areas.
13. Demobilization as specified in Section 01019.

1.5 BORROW AREA LOCATION

- A. The following potential borrow areas are identified and shown on the Subcontract Drawings:
 1. Dolores River Borrow Area, a potential source for erosion protection materials, is located at N57,500, E61,000.
 2. [Text Deleted]* [(Not Used)]*
 3. A Borrow Area located within the UC site is also a potential source of erosion protection materials especially larger sizes.
- B. The Subcontractor shall be responsible for processing and selective quarrying to provide materials conforming to the Specifications.

1.6 SUBCONTRACT DRAWINGS

- A. A list of Subcontract Drawings and Titles is provided in the Table of Contents of these Subcontract Documents under "Subcontract Drawings".

* P.I.D. 11-S-03

- B. Where "as shown," "as detailed," "as noted," or words of like meaning are used in the Subcontract Documents, it shall be understood that reference is being made to the Subcontract Drawings unless otherwise specified.

1.7 TIME OF COMPLETION

- [A. The Subcontractor shall commence Work under this Subcontract five calendar days from the receipt of a written Notice to Proceed issued by the Contractor, and shall complete the Work by December 15, 1996.]* No heavy construction activities are permitted between December 15 and April 1 for the BC and NC sites and between December 15 and April 15 for the UC site.
- B. Termination for default, damages for delay and time extensions are specified in Articles GP-42 and GP-56 of General Provisions.

1.8 CODES AND STANDARDS

- A. Pursuant to Article GC-3 of the General Conditions, any material, method, or procedure specified by reference to the number, symbol, or title of a specific specification or standard, such as a Commercial Standard, American National Standard, Federal or State Specification, Industry or Government Code, a trade association code or standard, or other similar standard, shall comply with the requirements in the latest revision thereof and any amendments or supplements thereto in effect on the date of Award of Subcontract, except as limited to type, class or grade, or modified in such reference.
- B. The code, specification or standard referred to, except as modified in these Specifications, shall have full force and effect as though printed in these Specifications. These Specifications and standards are not furnished to bidders because manufacturers and trades involved are assumed to be familiar with their requirements. The Contractor will furnish, upon request, information as to how copies of the specifications and standards referred to may be obtained.

* P.I.D. 11-S-07

Document No. 3885-SRK-S-01-02416-04

Issued for Construction-Revision 2

Summary of Work

SRK

01010 - 7

WP51

022195

1.9 MANUFACTURERS' SPECIFICATIONS AND INSTRUCTIONS

- A. Unless otherwise indicated or specified, all manufactured materials, products, processes, equipment, or the like shall be installed or applied in accordance with the manufacturers' instructions, directions, or specifications. Said installation or application shall be in accordance with printed instructions furnished by the manufacturer of the material or equipment concerned for use under conditions similar to those at the jobsite. Two copies of such instructions shall be furnished to the Contractor and his acceptance thereof obtained before work is begun.
- B. Any deviation from the manufacturers' printed recommendations shall be explained and acknowledged as correct for the circumstances, in writing by the particular manufacturer. Subcontractor will be held responsible for all installations contrary to the manufacturers' recommendations. If any item of material or equipment is found to be installed not in accordance with the manufacturer's recommendations, Subcontractor shall make all changes necessary to achieve such compliance without additional cost to the Contractor.

1.10 WORK QUALITY

- A. Shop and field work shall be performed by qualified craftsmen. All work on this Project shall be performed in accordance with the highest standards of the various trades involved and in accordance with the Subcontract Drawings, reviewed shop drawings and these Specifications.
- B. All Work shall be erected and installed plumb, level, square and true, or true to indicated angle, and in proper alignment and relationship to the work of other trades. All finished work shall be free from defects and damage.
- C. The Contractor reserves the right to reject any materials and work which are not considered to be up to the highest standards of the various trades involved. Such inferior material or work shall be repaired or replaced, as directed, at no additional cost to the Contractor or extension of Subcontract time.

1.11 FIELD MEASUREMENT AND TEMPLATES

Subcontractor shall secure all field measurements required for proper and accurate fabrication and installation of the work included in this Subcontract. Exact measurements are the Subcontractor's responsibility. Subcontractor shall also

furnish or obtain all templates, patterns, and setting instructions required for the installation of all work. All dimensions shall be verified by the Subcontractor by survey in the field.

1.12 ACCESS TO WORK

- A. Pursuant to the provisions of Article GC-17 of the General Conditions, the authorized agents of the following agencies will also have the right of access to inspect the Work covered by these Subcontract Documents during the performance of this Subcontract:
1. United States Department of Energy (DOE)
 2. United States Nuclear Regulatory Commission (NRC)
 3. Colorado Department of Health, Hazardous Materials and Waste Management Division
 4. Various Agencies Listed in Article SC-11 of the Special Conditions
 5. Other Local, State and Federal Agencies
- B. These inspections will be performed in conjunction with an inspection by the Contractor. Reasonable facilities for the proper handling and inspection of the materials and the Work shall be furnished by the Subcontractor.

PART 2 - PRODUCTS

(Not Used)

PART 3 - EXECUTION

(Not Used)

PART 4 - MEASUREMENT AND PAYMENT

(Not Used)

END OF SECTION 01010

SECTION 01019

MOBILIZATION

PART 1 - GENERAL

1.1 SCOPE

A. This Specification Section covers the following:

1. Organization and mobilization of Subcontractor's forces and equipment;
2. Transporting construction plant and equipment to the sites and setting up of same;
3. Transporting tools, materials, and equipment to the sites;
4. Furnishing, installation, construction, maintaining, operation, and subsequent removal and disposal of construction facilities and temporary controls not separately paid for under other Sections of the Subcontract Documents but required for construction of permanent facilities.
5. Subsequent removal of construction plant, equipment, materials and supplies; decontamination of construction equipment and facilities; cleaning of equipment for salvage; cleaning of the site; and restoration and reseedling of offsite construction facilities.

1.2 RELATED WORK

- A. Section 01500 - Construction Facilities
- B. Section 01560 - Temporary Controls
- C. Section 01561 - Construction Cleaning

1.3 DESCRIPTION

A. Mobilization shall include:

1. Furnishing, installation, construction, maintenance and operation of construction facilities and temporary controls identified in Article 1.1.A.4 above;

Document No. 3885-SRK-S-01-02417-02

Issued for Construction-Revision 0

Mobilization

01019 - 1

SRK

WP51
052594

mobilization of all construction equipment, materials, supplies, appurtenances, and the like; manned and ready for commencing and performing the Work.

2. Assembly and delivery to the site of plant, equipment, materials, and supplies necessary for the performance of the Work but which are not intended to be incorporated in the work; the preparation of the Subcontractor's work area; complete assembly, in safe working order, of equipment necessary to perform the required work; personnel services preparatory to commencing actual work; and all other preparatory work required to permit commencement of the actual work on construction items for which payment is provided under the Subcontract.
3. Decontamination of construction facilities, equipment, materials, supplies and appurtenances.
4. Subsequent removal from the site of all construction equipment, materials, supplies, appurtenances, and the like upon completion of the work.
5. Maintenance, operation, subsequent removal and disposal of construction facilities identified in Article 1.1.A.4 above, as required by the Contractor.
6. Cleaning of the site and restoration and reseedling of offsite construction facilities.

PART 2 - PRODUCTS

(Not Used)

PART 3 - EXECUTION

(Not Used)

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Measurement for payment for mobilization will be by the lump sum basis.

4.2 PAYMENT

- A. Payment for mobilization will be made at the lump sum price quoted therefor in the Bid Schedule, and shall include all items as specified herein. Payment for mobilization will be made as follows:
1. Payment of 50 percent of the lump sum price will be made upon completion of "move-in". Move-in is defined as organization of the Subcontractor's manpower and equipment, transporting equipment to the site, and installation of Contractor's and Subcontractor's field offices and other supporting structures.
 2. Payment of the remaining 50 percent of the lump sum price will be made upon completion of work corresponding to 10 percent of the total price quoted in the Bid Schedule exclusive of the price quoted for mobilization.
- B. Payment for furnishing, installing, operating, maintaining, decontaminating, and removing and disposal if required, of construction facilities and temporary controls not covered for payment under any other Bid Items will be considered to be included in the Bid Schedule item for Mobilization.

END OF SECTION 01019

SECTION 01025

MEASUREMENT AND PAYMENT

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section covers descriptions of measurement and payment as they apply to this Subcontract. The provisions of this Section shall be supplemental to the requirements specified in General Provisions, General Conditions and Special Conditions.
- B. Measurement methods specified in the individual Sections of these Specifications shall govern if they differ from methods specified in this Section.
- C. The Subcontractor shall compute all quantities. Such computations shall be based upon surveys performed by the Subcontractor and subject to approval by the Contractor before any progress payments related thereto are made.

1.2 RELATED WORK

- A. General Provisions - Article GP-38: Payments to Subcontractor.
- B. General Conditions - Article GC-4B: Progress Payments.
- C. Section 00800 - Special Conditions: Article SC-14, Variations in Quantities.
- D. Section 01052 - Layout of Work and Surveys.
- E. Section 01300 - Submittals: Schedule of Values and Progress Payment Schedule.

1.3 MEASUREMENT OF QUANTITIES

- A. Measurement Standards: All work to be paid for at a Contract price per unit of measurement will be measured in accordance with United States Standard Measures. A ton shall consist of 2,000 pounds avoirdupois.

B. Measurement by Weight:

1. Reinforcing steel, steel shapes, castings, miscellaneous metal, metal fabrications, and similar items, to be paid for by weight, shall be measured by scale or by handbook weights for the type and quantity of material actually furnished and used.
2. Material to be measured and paid for by scale weight shall be weighed on accurate, Contractor-approved scales, furnished by and at the expense of the Subcontractor. Use platform scales of sufficient size and capacity to permit the entire vehicle or combination of vehicles to rest on the scale platform while being weighed. Combination vehicles may be weighed as separate units provided they are disconnected while being weighed. All scales shall be inspected and certified as often as the Contractor may deem necessary to ascertain accuracy. Costs incurred, as a result of regulating, adjusting, testing, inspecting, and certifying scales, shall be borne by the Subcontractor.
3. The Contractor may be present to witness the weighing and to check and compile the daily record of such scale weights; however, in any case, the Contractor will require that the Subcontractor furnish weigh slips and daily summary weigh sheets. A duplicate weigh slip or a load slip for each vehicle weighed shall be delivered to the Contractor at the point of delivery of the material.
4. If the material is shipped by rail, the certified car weights will be accepted, provided that only actual weight of material will be paid for and not minimum car weight used for assessing freight tariff. Car weights will not be acceptable for material to be passed through mixing plants.
5. Trucks used to haul material being paid for by weight, shall be weighed empty daily and at such additional times as the Contractor may require. Each truck shall bear a plainly legible identification mark. The Contractor may require the weight of the material verified by weighing empty and loaded trucks on such other scales as the Contractor may designate.

C. Measurement By Volume:

1. Measurement by volume will be by the cubic dimension listed or indicated in the Bid Schedule. Method of volume measurement will be as specified in the applicable

Section of the Specifications or as determined or directed by the Contractor.

2. When material is to be measured and paid for on a volume basis and it is impractical to determine the volume by the specified method of measurement, or when requested by the Subcontractor in writing and accepted by the Contractor in writing, the material will be weighed in accordance with the requirements specified for weight measurement. Such weights will be converted to volume measurement for payment purposes. Factors for conversion from weight measurement to volume measurement will be determined by the Contractor and shall be agreed to by the Subcontractor before such method of measurement of pay quantities will be accepted.
- D. Measurement by Area: Measurement by area will be by the square dimension listed or indicated in the Bid Schedule. Method of square measurement will be as determined or directed by the Contractor.
- E. Linear Measurement: Linear measurement will be by the linear dimension listed or indicated in the Bid Schedule. Method of linear measurement will be as determined or directed by the Contractor. Generally, items, components, or work to be measured will be measured at the centerline of the item in place.
- F. Lump-Sum Measurement:
1. Lump-sum measurement will be for the entire item, unit of work, structure, or combination thereof, as listed or indicated in the Bid Schedule.
 2. If the Subcontractor requests progress payments for lump-sum items or amounts in the Bid Schedule, such progress payments will be made in accordance with a Schedule of Values for that item as specified in Specification Section 01300 and Article GC-4B of the General Conditions.
- 1.4 FIELD MEASUREMENT FOR PAYMENT
- A. The Subcontractor shall compute all quantities of Work performed or of materials and equipment delivered to the site, for payment purposes. All such computations shall be subject to approval by the Contractor before any progress payments related thereto are made.

- B. The Contractor may, at any time, verify quantities calculated by the Subcontractor in accordance with the provisions of Section 01052 of these Specifications.
- C. The Subcontractor shall assist the Contractor in the taking of measurements by providing all equipment, workers, and survey crews, as required, for verification of quantities by the Contractor in accordance with the provisions of Section 01052 of these Specifications.
- D. All such assistance in measurement services required of the Subcontractor, as specified, shall be performed under the direction and supervision of the Contractor.

1.5 PAYMENT

- A. Payment will be full compensation for furnishing all labor, materials, tools, equipment, transportation, services, and incidentals, as specified, in Article GP-38 of the General Provisions and Article GC-4B of the General Conditions, and for performing all work necessary for completing the erection or installation of the item or work classification, including all adjusting and balancing, testing, cleaning, and all other incidental work.
- B. Full compensation for all expense involved in conforming to the requirements for measuring materials or work shall be considered as included in the unit or lump-sum prices paid for the materials or work being measured, and no additional compensation will be permitted therefor.
- C. When progress payments are to be made on a portion, area, or section of the work, that portion, area, or section of the work shall be clear of deficiencies and nonconforming items, as determined by the Contractor, prior to making a progress payment.

1.6 VALUES OF UNIT PRICES

- A. The number of units and quantities contained in the Bid Schedule are approximate only, and final payment will be made for the actual number of units and quantities which are incorporated in or made necessary by the Work included in this Subcontract.
- B. In the event that work and/or materials or equipment are required to be furnished to a greater or lesser extent than is indicated by the Subcontract Drawings and Specifications, such work and/or materials or equipment shall be furnished in

greater or lesser quantities, and the adjustment in unit price shall be made as specified in Article SC-14 of the Special Conditions.

1.7 REJECTED MATERIALS

Quantities of material wasted or disposed of in a manner not called for under the Subcontract; rejected loads of material, including material rejected after it has been placed by reasons of the failure of the Subcontractor to conform to the provisions of the Subcontract; material not unloaded from the transporting vehicle; material placed outside the limits indicated on the Subcontract Drawings or established by the Contractor; or material remaining on hand after completion of the Work, will not be paid for, and such quantities shall not be included in the final total quantities. No compensation will be permitted for loading, hauling, and disposing of rejected material.

PART 2 - PRODUCTS

(Not Used)

PART 3 - EXECUTION

(Not Used)

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Separate measurement for payment will not be made for work required under this Section.

4.2 PAYMENT

Separate payment will not be made for work required under this Section. All costs in connection with the work specified herein will be considered to be included in the related items of work in the Bid Schedule, or incidental to the Subcontract.

END OF SECTION 01025

SECTION 01052

LAYOUT OF WORK AND SURVEYS

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section covers the procedures and accuracy requirements for survey services for the following:
 - 1. Layout and performance of work.
 - 2. Field measurement of work quantities for payment purposes.
 - 3. Locations of sampling and testing performed by the Contractor.
 - 4. Determination of as-built locations, lines and grades at completion of the work for preparation of as-built drawings as specified in Section 01300.
- B. Before commencing any layout of work and surveys, the Subcontractor shall give the Contractor five working days written notice in advance so that the Contractor may witness such work.

1.2 DESCRIPTION

- A. Reference Points: The reference points to be provided by the Contractor will include referenced monuments and elevation bench marks in the vicinity of the project. Initial reference points will be furnished and established by the Contractor. Replacement by the Contractor of Contractor-established reference points which have been damaged or destroyed by the Subcontractor will be charged to the Subcontractor at a rate of \$150 per hour. All other necessary reference points shall be established by the Subcontractor.
- B. The Subcontractor shall furnish all necessary detail surveys including all lines, grades, and appropriate surveys as specified.
- C. The Contractor reserves the right to perform any desired checking and/or correction of the Subcontractor's surveys but this shall not relieve the Subcontractor of responsibility for the adequate performance of the work.

- D. Equipment and Personnel: The Subcontractor's instruments and other survey equipment shall be accurate, suitable for the surveys required in accordance with recognized professional standards, and in proper condition and adjustment at all times. A competent surveyor shall perform the work.
- E. Field Notes and Records: The Subcontractor shall record surveys in duplicate page field notebooks. The original pages of such records shall be furnished to the Contractor at intervals required by the Contractor. A duplicate of each field notebook shall be furnished to the Contractor when filled or completed or to meet the requirements of Article GC-4, Progress Payment. If the Subcontractor elects to use electronic survey data collectors, the Subcontractor shall submit to the Contractor duplicates of the field data collected and a licensed copy of the computer software used by the Subcontractor for generating quantitative data, including area, volume and cross-section information.
- F. Use by the Contractor: The Contractor may at any time use line and grade points and markers established by the Subcontractor. The Subcontractor's surveys are a part of the Work and may be checked by the Contractor or representatives of the Contractor at any time. The Subcontractor shall be responsible for any lines, grades, or measurements which do not comply with specified or proper tolerances, or which are otherwise defective, and for any resultant defects in the Work. The Subcontractor will be required to conduct re-surveys or check surveys to correct errors indicated by review of the field notebooks or otherwise detected.

1.3 SURVEYS FOR LAYOUT AND PERFORMANCE OF WORK

The Subcontractor shall perform all surveys for layout and performance of the Work, and shall reduce the field notes and make all necessary calculations and drawings necessary to carry out the Work.

1.4 SURVEYS FOR MEASUREMENT FOR PAYMENT

When the Specifications or the Contractor require Bid Schedule items of work to be measured by surveying methods, the Subcontractor shall perform the surveys. At the Contractor's option, all such surveys, including control surveys run for establishing the measurement reference lines, shall be performed in the presence of the Contractor (or a representative of the Contractor) who will witness the surveying operation by signing the field notes or keeping duplicate field notes. The Subcontractor shall reduce the

field notes and calculate final quantities for payment purposes. A duplicate of the note reductions and calculations shall be given to the Contractor.

1.5 SURVEYS FOR CONTRACTOR SAMPLING AND TESTING LOCATIONS

- A. The Subcontractor shall perform surveying services as specified herein for the locations of Contractor sampling and testing.
- B. Verification of Contaminated Material Cleanup: Upon completion of contaminated material cleanup in any given area, as directed by the Contractor, the Subcontractor shall survey and clearly mark on the ground the locations of verification grid points at locations as directed by the Contractor. The grid dimensions for verification grid points may vary from 150 feet by 150 feet to 30 feet by 30 feet. Verification grid points will be used by the Contractor to obtain samples to confirm that contaminated materials have been removed.
- C. Materials Sampling and Testing: The Subcontractor shall provide surveying services to locate positions, both plan and elevation, of in-place material sampling and testing locations used by the Contractor. The number of sampling and testing locations will be determined by the applicable Specification Section.
- D. The Subcontractor shall mark sampling locations for radiologic samples in the tailings embankment at locations designated by the Contractor and as specified herein. As contaminated materials are placed in the uppermost 20 feet of contaminated materials, the Subcontractor shall mark each location at each 2-foot increment of elevation. Approximately 25 sampling locations will be designated by the Contractor.
- E. All sampling and testing location information shall be submitted in writing to the Contractor showing coordinates and elevations.

1.6 SURVEYS FOR AS-BUILT CONDITIONS

- A. The Subcontractor shall provide surveying services for as-built conditions as specified herein.
- B. The Subcontractor shall provide survey data to confirm that as-built locations of the Work conform to the Subcontract Drawings where coordinates and/or elevations are shown.

- C. Where the Subcontract Drawings or Specifications permit variable locations or detail for specific items of the Work, the Subcontractor shall survey the as-built locations or details. Surveys shall be sufficient to define the features or details at any given location.
- D. The Subcontractor shall survey final disposal locations of all hazardous and non-hazardous materials specified in Section 02081.
- E. The Subcontractor shall survey as-built elevations, on a maximum survey and system of 100 feet by 100 feet, for the as-built finished top surface of the following:
 - 1. Contaminated materials
 - 2. Radon barrier
 - 3. Frost protection layer
 - 4. Topslope and sideslope bedding layer
 - 5. Topslope and sideslope riprap
- F. The Subcontractor shall survey as-built locations of all slope breaks for the tailings embankment.
- G. The Subcontract Drawings shall be neatly marked in red ink with all as-built survey information and submitted to the Contractor in duplicate.
- H. The requirements for submitting as-built survey data shall not relieve the Subcontractor in any way from his responsibility to conform to the requirements of the Work.

1.7 SURVEYING ACCURACY AND TOLERANCES IN LAYOUT OF WORK

- A. Tolerances in layout of Work shall not exceed the following:

<u>Type of Line or Mark</u>	<u>Horizontal Position</u>	<u>Elevation</u>
Permanent reference points	1 in 10,000	$\pm$.01 ft.
Reference points for general excavation and earthwork	1 in 2,000	$\pm$.10 ft.

- B. With the exception of the radon barrier and erosion protection materials, tolerances for the elevations of the top of each layer of fill materials, as derived from design elevations shown on the Subcontract Drawings, shall be ± 0.10 foot.
- C. For the radon barrier, in-place elevations and layer thicknesses shall have a tolerance of ± 0.10 foot from design elevations and thicknesses. Tolerances on erosion protection material thicknesses are specified in Section 02278.
- D. These tolerances shall not supersede stricter tolerances required by the Drawings or Specifications, or by the governing authorities, and shall not otherwise relieve the Subcontractor of responsibility for measurement in compliance therewith.

1.8 SURVEYS FOR DISPLACEMENT MONUMENTS

- [A. Displacement monuments shall be surveyed immediately following installation and thereafter on a bi-weekly basis for the first two months. The frequency of additional surveys will be determined by Contractor. The Subcontractor shall report the coordinates and elevation of the top of the 3/4-inch steel rod and the top of the 1-1/2 inch steel pipe as shown on the Subcontract Drawings.]*
- B. For displacement monuments having total lengths of steel rod and steel pipe greater than 5 feet, the Subcontractor shall survey the top of the steel rod and steel pipe immediately prior to and following installation at each segment of steel rod or steel pipe during construction, as specified in Article 1.8.A.
- C. The top of steel pipe shall be surveyed at the same location on the diameter of the pipe for each measurement.
- D. Displacement monuments shall be surveyed immediately following any disturbance to any displacement monument.

PART 2 - PRODUCTS

(Not Used)

* P.I.D. 11-S-08

Document No. 3885-SRK-S-01-02419-03
Issued for Construction-Revision 1
Layout of Work and Surveys

SRK

01052 - 5

WP51
041195

PART 3 - EXECUTION

(Not Used)

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Separate measurement for payment will not be made for work required under this Section.

4.2 PAYMENT

Separate payment will not be made for work required under this Section. All costs in connection with the work specified herein will be considered to be included in the related item of work in the Bid Schedule, or incidental to the Subcontract.

END OF SECTION 01052

1

.

SECTION 01300

SUBMITTALS

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This Specification Section describes the requirements for the following submittals:

1. Technical Submittals:

- a. Schedule of Technical Submittals
- b. Shop Drawings
- c. Samples
- d. Product Data
- e. Certificates of Compliance
- f. Manufacturer's Instructions, Specifications and Recommendations
- g. Design Calculations and Design Drawings
- h. Winter Shutdown Plan
- i. Drawings Showing Lines and Grades and Survey Data for Conditions at Completion of Construction (As-Built)
- j. Erosion Protection Materials Production Plan
- k. Asbestos, Hazardous and Non-Hazardous Materials Submittals
- l. Proactive Dust Suppression Plan
- m. Demolition Plan
- n. Operations Plan for each Decontamination Facility
- o. Standard Operating Procedures

2. General Submittals:

- a. Schedule of General Submittals
- b. Schedules and Reports
- c. Site Mobilization Schedule
- d. Project Construction Schedule
- e. Schedule of Values/Cost Profile
- f. Hazard Communications Plan
- g. Site Safety Plan
- h. Traffic Plan
- i. Waste Minimization and Recycling Plan
- j. Spill Prevention Control and Countermeasure Plan
- k. Hazardous Waste Operations, Site Safety and Health Plan
- l. Labor and Equipment Rates
- m. Employee Training Summary for Subcontractor's Hoisting and Rigging Plan

Document No. 3885-SRK-S-01-02420-04

Issued for Construction-Revision 2

Submittals

01300 - 1

SRK

WP51
022195

- n. U.S. Department of Transportation Hazardous Material Certificate of Registration
- o. U.S. Department of Transportation Safety Rating
- p. U.S. Department of Transportation Number
- [q. Blasting Plan]*

3. Submittals Not Requiring Contractor's Approval:

- a. Weekly Status Reports
- b. Weekly Manhour Reports/Equipment Hours and Truck Miles Report/Maintenance Report
- c. Certified Payroll
- d. Monthly Construction Schedule Progress Updates
- e. Quarterly Report for Small Business and Small Disadvantaged Business Subcontracting Plan
- f. Monthly Report Detailing Costs in the Event of a Suspension or Termination
- g. Electrical Line Drawings of As-Built Conditions for Electrical Installations and Equipment Connections

- B. The requirements specified in this Section shall be supplemental to the requirements specified in General Provisions, General Conditions, Special Conditions and any other requirements specified in individual sections.
- C. All submittals shall be in the English language.
- D. The Subcontractor shall submit all submittals to the Site Manager. A reproducible copy of the submittal, marked "Information Only", shall be sent to the Subcontract Administrator by the Subcontractor.
- E. Technical and General Submittals shall be numerically serialized by type, Technical Submittal with a "T" prefix (T-1, T-2, T-3, etc.) and General Submittals with a "G" prefix (G-1, G-2, G-3, etc.).
- F. The Site Manager will clearly label the technical and general submittals as follows and return to the Subcontractor:
 - 1. Approved
 - 2. Approved as Noted
 - 3. Revise and Resubmit
 - 4. Rejected
 - 5. Information Only
- G. When submittals are returned marked with either "Revise and Resubmit" or "Rejected" the Subcontractor shall make such revisions and corrections as required and resubmit the submittal with the same submittal number followed by R1 (Revision One). Example: T-5 - R1.

* P.I.D. 11-S-07

Document No. 3885-SRK-S-01-02420-04

Issued for Construction-Revision 2

Submittals

01300 - 2

SRK

WP51

022195

1.2 TECHNICAL SUBMITTALS

A. Schedule of Technical Submittals:

1. The Subcontractor shall prepare and submit a Technical Submittals Schedule listing all technical submittals required in accordance with this Section. The Technical Submittals Schedule shall be submitted at the preconstruction meeting.
2. The Technical Submittals Schedule shall separate submittals by major specification section. This schedule shall include submittal delivery dates, required return dates, material delivery dates, and other pertinent data which may be required to ensure that the project schedule is met by the Subcontractor.
3. This Schedule shall be continually updated to reflect progress and any additions or deletions to the submittal schedule. Copies of the updated schedule shall be furnished to the Contractor during the first week of each calendar month.

B. Shop Drawings:

1. Shop drawings shall establish the actual detail of all manufactured or fabricated items, indicate proper relation of adjoining work, and incorporate minor changes of design or construction to suit actual conditions. Shop drawings shall be drawn to scale and shall be completely dimensioned.
2. Sheet sizes of shop drawings shall be 8 1/2 inches x 11 inches, 11 inches x 17 inches, or 22 inches x 34 inches.
3. A clear space of 3 inch by 3 inch shall be provided on each drawing for the Contractor's review stamp and comments.
4. Shop drawings shall be submitted to the Contractor in the form of a reproducible transparency, together with three blackline or blueline prints.
5. After the Contractor has completed his review of shop drawings, he will return one print to the Subcontractor indicating the approval status as described in Article 1.1.F.
6. The Contractor will review and generally return shop drawings within ten days of receipt by the Site Manager

but in no case will this process take longer than 30 days.

C. Samples:

1. The Subcontractor shall furnish the Contractor at least three samples of each of the various materials, together with the finish thereon, as specified for and intended to be used on or in the work. Samples shall be sent to the Contractor.
2. The Subcontractor shall submit all samples to the Contractor at least 21 days (or earlier, if so specified elsewhere) before purchasing, fabricating, applying, or installing such materials and finishes, unless otherwise stated. The Contractor will review the samples for visual aspects such as kind, color, pattern, and texture, and will approve or ask for resubmittal of samples generally within ten days but in no case longer than thirty days of the Subcontractor's submittal. All approvals of samples will be given by the Contractor in writing.
3. Unless otherwise specified in the various sections of these specifications, the Subcontractor shall submit all samples, other than field samples, in triplicate. A cover letter shall accompany the sample and shall list all items being transmitted, designating their particular usage and location in the project.
4. Each sample shall be identified completely as to product, color, manufacturer, trade name, lot, style, model, location of use, and Subcontract Document reference, as well as the names of the Subcontractor, Supplier, Project and Contractor.
5. Samples shall be submitted and resubmitted until approved as satisfactory. Approval of a sample shall not be taken in itself to change or modify any Subcontract requirement.
6. After the Contractor has performed his review and analysis of samples, two samples will be retained and the remaining sample will be returned to the Subcontractor, with the Contractor's comments.
7. All materials, color, pattern and texture in the completed building or structure shall be equal in every respect to that of the approved samples.

8. Test samples, as designated by the Contractor, may also be selected from the materials or equipment delivered by the Subcontractor to the site for use in the work. If any test sample fails to meet the specification requirements, such materials or equipment which fail the testing, shall be removed and replaced by the Subcontractor with materials or equipment meeting the Specification requirements.
 9. Field samples shall be prepared at the site by the Subcontractor in the manner and number as specified in these specifications. Affected finish work shall not be commenced until the Contractor has approved the field samples, in writing.
- D. Product Data:
1. Each copy shall be marked to identify applicable products, models, options, and other data; manufacturers' standard data shall be supplemented to provide information unique to the work.
 2. The Subcontractor shall submit the number of copies which the Subcontractor requires to be returned, plus two copies which will be retained by the Contractor.
- E. Certificates of Compliance: The Certificate shall clearly identify the applicable materials and reference the applicable Sections of the Subcontract Documents.
- F. Manufacturer's Instructions, Specifications and Recommendations: When required by the manufacturer's warranty requirements, the Subcontractor shall submit manufacturer's printed instructions, specifications and recommendations for delivery, storage, shelf life, assembly, installation, adjusting, and finishing.
- G. Design Calculations and Design Drawings:
1. Design Calculations: When requested by the Contractor, design calculations shall be submitted to the Contractor for review with all pertinent data, assumptions, objectives, criteria, applicable codes, standards and references. The calculations shall be on 8-1/2 by 11-inch or 11 by 17-inch sheets. Each design calculation set shall bear page numbers, titles, revision numbers, date and calculation number. Where multiple number of items are designed in a particular system, the calculations shall be preceded by a table of contents.

2. Design Drawings:

- a. When requested by the Contractor, design drawings shall be submitted to the Contractor for review.
- b. Pertinent requirements of Article 1.2.B of this Section shall be applicable for submittal of design drawings.

H. Winter Shutdown Plans: A winter shutdown plan will be required each year prior to shutdown for sites which will shutdown or limit operations for the winter season. No site work will be permitted between December 15 and April 1 for the BC and NC sites and between December 15 and April 15 for the UC Site. As specified in Section 01500, all required facilities and utilities will be installed and maintained providing uninterrupted service throughout the shutdown periods. This plan shall include grading modifications to drawings, product data and a narrative of the steps the Subcontractor will take to address the following subjects:

1. Erosion from wind and water runoff of both contaminated and uncontaminated areas.
2. Slope protection.
3. Temporary ditching.
4. Placing protective soil cover over contaminated materials in the disposal cell. See Section 02200, Article 3.1.B.2.
5. Furnishing and placing approved surfactant or surface stabilizer over disturbed areas at the processing sites.
6. Grading of excavations and embankments to drain.
7. Segregation of contaminated and uncontaminated runoff.
8. Reduction of water in the retention ponds to allow for spring snow melt.
9. Protection of all equipment and piping from damage due to freezing.
10. Other items which may be required by the Contractor such as personnel and equipment to maintain access and to prepare for emergency situations.

I. Drawings Showing Lines and Grades and Survey Data for Conditions at Completion of Work (As-Built): The Subcontractor shall prepare and submit at completion of work

drawings showing lines and grades (as-built) and survey data for as-built conditions as specified in Section 01052.

- J. Erosion Protection Materials Production Plan: See Section 02278, Article 1.6.
- K. Asbestos, Hazardous and Non-Hazardous Materials Submittals: See Section 02081, Article 1.8.
- L. Proactive Dust Suppression Plan: See Special Conditions, Article SC-3D.
- M. Demolition Plan: See Section 02050, Demolition.
- N. Operations Plan for Each Decontamination Facility: See Section 01500, Article 1.15.G.

1.3 GENERAL SUBMITTALS

- A. Schedule of General Submittals: The Subcontractor shall prepare and submit a Schedule of General Submittals listing all General Submittals required in accordance with the requirements of this Section. The Subcontractor shall prepare and make the initial submittal of the Schedule of General Submittals at the preconstruction meeting.
- B. Schedules and Reports:
 - 1. The Subcontractor shall prepare and submit Schedules and Reports in accordance with the requirements of this Section.
 - 2. The schedules and reports shall describe the Subcontractor's work plan in sufficient detail as delineated below to provide:
 - a. Assurance to the Contractor that the finished work complies accurately with the Subcontract Documents,
 - b. A basis for determining the progress of the work, and
 - c. A basis for the Contractor's internal planning activities.
 - 3. Within fifteen calendar days after Notice to Proceed, the Subcontractor shall provide the Contractor with initial copies of the General Submittals specified in this Section. The cost profile shall be submitted within 30 calendar days. The CPM Project Construction Schedule

shall be generated by Primavera Project Planner Version 5.1 or greater. A copy of all schedule submittals shall also be provided on 3-1/2-inch floppy disks.

4. The schedules shall be in a reproducible form and all of the same scale or may be combined as approved by the Contractor.
5. Unless otherwise specified, the schedules shall be presented in graphic format using Primavera Project Planner Version 5.1 or greater and shall be updated for each construction meeting, or at least monthly, and transmitted to the Contractor.
6. The Subcontractor shall obtain approval of the various schedules specified in this Section before submitting the first application for payment. Schedule revisions also require Contractor approval.

C. Site Mobilization Schedule:

1. Format: The Subcontractor shall present, at the preconstruction meeting, the schedule for site mobilization in bar chart format. The schedule shall delineate the establishment of the construction facilities identified in Section 01500 and as referenced in Section 01019 and shall include the Subcontractor's plan for starting the work.
2. Written Narrative: The Site Mobilization Schedule shall be accompanied by a written narrative discussion of the schedule. The narrative shall provide a man-power level by month for the first three months of the job, transportation routes proposed for delivery of major construction equipment to be used on the project, identification of special permits required and when they are needed, and a description of the temporary facilities to be provided.
3. Status and Progress: The status of mobilization schedule items shall be reported in the Weekly Status Report discussed below.

D. Project Construction Schedule:

1. Scheduling: A preliminary issue of the Project Construction Schedule shall be prepared for review at the preconstruction meeting. Fifteen days after receipt of Notice to Proceed the Subcontractor shall issue the Project Construction Schedule for approval and issue the approved Project Construction Schedule ten days after receipt of approval and comments from the Contractor.

2. Format: The Project Construction Schedule shall consist of the following items, each compatible with the other and developed from the same basis:

a. Method of Construction Narrative

b. CPM Schedule: A time scaled Critical Path Method (CPM) Schedule which depicts proper restraints, activity durations, total float and free float for each schedule activity including a predecessor-successor report and logic diagram.

c. Critical Milestone Dates as listed below:

- 1) Start/Complete Mobilization for each of the sites.
- 2) Start/Complete Installation Office Facilities at the BC site.
- 3) Installation of Remaining Temporary Facilities, Utilities and Controls.
- 4) Start/Complete Site Preparation at the UC, NC and BC sites.
- 5) Start/Complete Access Roads to the NC and BC Sites.
- 6) Start/Complete Reconstruction of County Road S8 at the UC Site.
- 7) Start/Complete Excavation for Tailings Embankment.
- 8) Start/Complete Hauling of Demolition Debris and all Contaminated Materials from the UC and NC Processing Sites and Placement in the Tailings Embankment at the BC Disposal Site.
- 9) Start/Complete Restoration of NC site.
- 10) Open Borrow Sites.
- 11) Start/Complete Radon Barrier Material Placement.
- 12) Start/Complete Cover Placement.
- 13) Start/Complete Erosion Protection Production.
- 14) Start/Complete Erosion Protection Placement.
- 15) Start/Complete Restoration of Sites and BC Access Road.
- 16) Start/Complete Demobilization.

d. Schedule of Values

3. Method of Construction: Method of construction submitted at the preconstruction meeting with the preliminary schedule shall be a written discussion of the Subcontractor's methods for completing the work. The Subcontractor shall briefly describe his approach to the Subcontract.

4. The Use of Schedule Float: In as much as the Subcontractor's Schedule represents the Project

Construction Schedule, the calculated float for an activity is shared by the Subcontractor and Contractor. Adjustments to the schedule float will be equitably resolved by the Contractor.

5. Computer Generated Schedule: The Subcontractor shall generate the CPM Schedule using Primavera Project Planner Version 5.1 or greater. The CPM Schedule shall include all significant items of Work. The Schedule shall identify any interruption of work activities due to winter shutdown as applicable.
6. Comments Incorporated: The Subcontractor shall incorporate the Contractor's comments into revisions of the Project Construction Schedule, adjust the manpower loading as required and within 14 calendar days resubmit the schedule to the Contractor for approval along with a summary of the changes.
7. Revisions made to the schedule shall be given a new revision number and submitted to the Contractor for approval. A written narrative shall accompany any changes to the logic and/or durations of the Construction Schedule. This narrative shall explain in detail what the change involves, the reason for the change, and any effect to the critical path of the schedule. Any effect indicated to the Critical Milestone Dates shall be accompanied by the Subcontractor's plan to meet the schedule as specified.

E. Schedule of Values/Cost Profile:

1. Each time a construction schedule is submitted, it shall be accompanied by a Schedule of Values for the entire Scope of Work. The Schedule of Values shall conform to the format sample (Figure 01300-A) provided with this Section. The Schedule of Values shall be based upon that specific revision of the Construction Schedule, and presented in such a format to clearly provide total period and cumulative cost information for each month for the entire duration of the Subcontract. This Schedule of Values shall be in a form which will provide a correlation between the subcontract bid items and the Subcontractor's schedule activities. The Subcontractor may, at his own risk, plan work in excess of the funding limitations outlined in the Special Conditions.
2. The format and the substance of the finalized Schedule of Values shall be as approved by the Contractor.

- F. Hazard Communications Plan: See Section 00800, Article SC-7.M.4.
- G. Site Safety Plan: See Section 00800, Article SC-7.H.1.d.
- H. Traffic Plan: See Section 00800, Article SC-7.
- I. Waste Minimization and Recycling Plan: See Section 01560, Article 1.7.B.5.
- J. Spill Prevention Control and Countermeasure Plan: See Section 01560, Article 1.7.B.4.
- K. Hazardous Waste Operations, Site Safety and Health Plan: See Section 00800, Article SC-7.O.6.
- L. Labor and Equipment Rates: The Subcontractor shall submit labor and equipment rates as stipulated in Article SC-12, Subcontractor Labor and Equipment Rates, of the Special Conditions.
- M. Employee Training Summary for Subcontractor's Hoisting and Rigging Plan. See Section 00800, Article SC-7.N.4.
- N. U.S. Department of Transportation Hazardous Material Certificate of Registration as required by 49 CFR.
- O. U.S. Department of Transportation Safety Rating as required by 49 CFR.
- P. U.S. Department of Transportation Number as required by 49 CFR.
- [Q. Blasting Plan: See Special Conditions, Article SC-3.F.]*

1.4 SUBMITTALS NOT REQUIRING CONTRACTOR'S APPROVAL

- A. The Subcontractor shall furnish the following submittals for information only. These submittals will not be approved and returned to the Subcontractor.
 - 1. Weekly Status Reports: The Subcontractor shall submit a Weekly Status Report to the Contractor by Friday noon. The report shall be on a form satisfactory to the Contractor, and shall include items such as a Summary of Work completed and a Two-Week Look Ahead Bar Chart.

* P.I.D. 11-S-07

Weekly Status Report shall also include each major piece of equipment present on the site, its make, model type, number of hours idle, number of hours used, etc. as required by the Contractor.

2. Weekly Manhour Report/Equipment Hours and Truck Miles Report/Maintenance Report: The Subcontractor shall tabulate total manhours worked each week with a regular and overtime total, equipment hours of operation and truck miles driven each week, listing all data for Subcontractor and lower-tier subcontractor operations. The tabulations shall be prepared and submitted weekly to the Contractor. The Maintenance Report shall be submitted to the Contractor monthly as follows:

- a. Preventative Maintenance:

_____ # Items completed within Monthly Schedule.

_____ # Items not completed within Monthly Schedule.

- b. Corrective Maintenance:

_____ Number of Corrective Work Requests during month.

_____ Number of Corrective Work Requests open at end of month.

3. Certified Payrolls: Certified Payrolls are to be submitted in strict compliance with Section 10 of MK-Ferguson Company Standard Documents Package for proposed construction subcontracts.
4. Monthly Construction Schedule Progress Updates: The Subcontractor shall submit an updated schedule, with the Critical Milestones clearly identified, by the first of each month. The status of the CPM Schedule shall indicate percent complete by activity, remaining duration of in-progress activities, total float and free float for each schedule activity. The updated schedule shall be given a new number starting with the word UPDATE and submitted to the Contractor for his use. A copy of all schedule submittals shall also be provided on 3-1/2-inch floppy disks as well as in a reproducible form.
5. Quarterly Report for Small Business and Small Disadvantaged Business Subcontracting Plan:

- a. The Subcontractor shall submit to the Subcontract Administrator a quarterly report of small business and small disadvantaged business subcontracting detailing the following information for the previous 3 months:
 - 1) Name of Small Business/Small Disadvantaged Business.
 - 2) Business Designation, i.e. SB or SDB.
 - 3) Amount of Subcontract/Purchase Order awarded and/or purchased.
 - b. The quarterly report shall be submitted on the following dates of each year during the performance of the Subcontract:
 - 1) January 6
 - 2) April 6
 - 3) July 6
 - 4) October 6
6. Monthly Report Detailing Costs in the Event of a Suspension or Termination: See Section 00800, Articles SC-16.G and H.
 7. Electrical Line Drawings of As-Built Conditions for Electrical Installations and Equipment Connections: Electrical As-Built Line Drawings shall be submitted within 15 days after completion of work.

PART 2 - PRODUCTS

(Not Used)

PART 3 - EXECUTION

(Not Used)

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Separate measurement for payment will not be made for work specified in this Section.

4.2 PAYMENT

Separate payment will not be made for work specified in this Section. All costs in connection therewith shall be considered to be incidental to the applicable items of work to which they pertain.

END OF SECTION 01300

UMTRA PROJECT
SUBCONTRACT DOCUMENTS _____
SCHEDULE OF VALUES

SAMPLE

DESCRIPTION	SCHEDULE ACTIVITY NUMBER	BID ITEM		1987						TOTAL DOLLARS
		NUMBER	PERCENT	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	
MOBILIZA- TION	1	001	50%							\$32,000
INSTALL FENCE AT CONTRACT- OR'S OFFICE	2	901 902	25% 100%							\$57,000
EXCAVATION (TAILINGS)	3	204	100%							\$320,000
INSTALL REMAINING FENCE	4	901	75%							\$21,000
DEMOBILIZA- TION	5	001	50%							\$32,000
TOTAL:		PERIOD		\$31,000	\$40,000	\$152,000	\$207,000	\$30,000	\$2,000	\$462,000
		CUMULATIVE		\$31,000	\$71,000	\$223,000	\$430,000	\$460,000	\$462,000	

CONSTRUCTION START DATE: 3/10/87
CONSTRUCTION COMPLETION DATE: 8/07/87

SECTION 01500

CONSTRUCTION FACILITIES

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section covers the requirements for the construction facilities.
- B. Construction facilities shall include, but not be limited to, the following temporary offices, utilities, equipment, materials and services:
 - 1. Subcontractor's Office
 - 2. Contractor's Trailers
 - 3. Parking Areas
 - 4. Janitorial and Maintenance Services
 - 5. Snow Removal Services
 - 6. Temporary Roads
 - 7. Storage of Materials and Equipment
 - 8. Construction Equipment
 - 9. Temporary Sanitary Facilities
 - 10. Temporary Electric Power
 - 11. Temporary Water (Potable and Construction)
 - 12. Decontamination Facilities
 - 13. Temporary Heat
 - 14. Temporary Telephone Service
 - 15. Temporary Fences
- C. The Subcontractor shall be responsible for furnishing, installing, constructing, operating, maintaining, removing and disposing of the facilities as shown on the Subcontract Drawings, as specified in this Specification, and as required by the Contractor for the completion of the Work under the Subcontract. Temporary facilities will be inspected and tested by the Contractor as often as the Contractor deems necessary to ensure satisfactory performance for the anticipated period of usage.
- D. All such temporary facilities shall be located as shown on the Subcontract Drawings, or as directed by the Contractor, and maintained in a clean, safe and sanitary condition at all times until completion of the Subcontract.
- E. Upon completion of the Subcontract, the temporary facilities shall be left in the status specified in Article 1.21 of this Section.

- F. The requirements specified herein are in addition to any requirements specified elsewhere in the Subcontract Documents. Temporary facilities shall meet the requirements for all-weather service.
- G. Certain facilities specified in this Section, although referred to in singular, may be required in greater numbers. The number of facilities required shall be as shown on the Subcontract Drawings or as specified.
- H. All utilities shall be designed and constructed to provide uninterrupted service during construction, and be protected from damage during winter. The electrical service is provided by the San Miguel Power Company and telephone service by Eagle Telecommunication Company. There is no natural gas or water service to the area, but bottled propane service is available from Cortez and Dove Creek.
- I. All land disturbances related to the temporary facilities shall be minimized to the greatest extent possible and the land restored to the extent reasonable and practical, to its original contours by grading to provide positive drainage and by seeding in accordance with Section 02935.

1.2 RELATED WORK

- A. Section 00800 - Special Conditions
- B. Section 01019 - Mobilization
- C. Section 01560 - Temporary Controls
- D. Section 02050 - Demolition
- E. Section 02141 - Dewatering and Drainage
- F. Section 02200 - Earthwork
- G. Section 02205 - Road Construction
- H. Section 02832 - Chain Link Fence and Gates
- I. Section 02835 - Deer Fence and Gates
- J. Section 02836 - Smooth Wire Fence and Gates
- K. Section 02935 - Seeding

1.3 APPLICABLE PUBLICATIONS

A. The Publications listed below form a part of this Specification to the extent referenced. The Publications are referred to in the text by the basic designation only:

1. Illuminating Engineering Society of America (IES), as applicable.
2. MK-F Hazardous Materials Transportation Requirements and Truck Inspection Plan.
3. National Electric Code, Standards as applicable.
4. National Fire Protection Association (NFPA), as applicable.
5. Occupational Safety and Health Administration, Standards as applicable.
6. San Miguel County Land Use Code, as applicable.
7. State of Colorado, Department of Transportation (CDOT): "Standard Specifications for Road and Bridge Construction (1991)".
8. State of Colorado, Department of Transportation (CDOT) Design Manual, as applicable.
9. Uniform Building Code (UBC):
1991 Edition, applicable Chapters and Sections.
10. UMTRA Project Construction Safety and Health Management Plan (MK-UMTRA-4)
11. U.S. Code of Federal Regulations, Title 29, Part 1926, Safety and Health Regulations for Construction.
12. U.S. Department of Transportation, Code of Federal Regulations, Title 49.

B. All required facilities, equipment and utilities shall also be installed, constructed, maintained and operated in accordance with applicable Federal, State, County, and Utility laws, rules, permits and regulations. Notwithstanding contrary provisions of General Provisions, General Conditions and Special Conditions, nothing in the Subcontract Drawings and Specifications shall be construed to permit work not conforming to the above.

- C. Unless otherwise specified elsewhere in the Subcontract Documents, the Subcontractor shall be responsible for obtaining applicable Federal, State, County and local permits and for complying with the provisions of such permits.

1.4 SUBCONTRACTOR'S TEMPORARY OFFICE TRAILERS

- A. The Subcontractor shall furnish and install, in good condition, one or more temporary office trailer/s of suitable size for his office staff. One trailer shall have a conference room of suitable size for meetings with the Contractor and other agencies.
- B. The location of the trailer/s shall be subject to approval by the Contractor prior to setting in place.

1.5 CONTRACTOR'S TRAILERS

- A. The Subcontractor shall furnish and install the following trailers for the Contractor's staff. The final locations of the trailers shall be approved by the Contractor prior to setting in place.

- 1. Access Control Trailers: The Subcontractor shall provide three trailers, one at each of the sites.

- a. The trailers will be used by the Contractor's administrative, security and Health Physics personnel. Each trailer shall include decontamination facilities including change facilities for all personnel working on the site, a single decontamination shower, a sink, and provisions for a washer and dryer, including plumbing and electrical services. All waste water shall drain directly to the recirculation pond.

- b. The trailer at the UC and BC sites shall provide a floor space of 720 square feet (12 ft. x 60 ft.). The trailer for the NC site shall provide a floor space of 480 square feet (12 ft. x 40 ft.) The arrangement shown in the Information for Bidders should generally be followed.

- 2. Quality Control Trailer:

- a. The Subcontractor shall provide one quality control trailer. The quality control trailer will be used as a laboratory for testing of construction materials, and shall be located at the BC site.

- b. The Subcontractor furnished trailer shall be 720 square feet (12 ft. x 60 ft.) and generally follow the floor plan arrangement shown in the Information for Bidders. This trailer will be located outside the controlled area. The Contractor's 10 ft. x 30 ft. trailer, located at the UC Site, shall be relocated to the BC Site and placed along the 12 ft. x 60 ft. trailer in the controlled area.
- c. The Subcontractor shall provide one 320 square feet (8 ft. by 40 ft.) storage van, and it shall be located at the BC site.

3. Change Facilities and Boot Storage Trailers:

- a. The trailers shall be the same size as the corresponding access control trailer for each of the sites and shall be used by the Contractor to provide changing facilities and boot storage facilities for protective boots for all personnel. The facilities shall include a 144 square foot (12 ft. x 12 ft.) changing and personal storage areas at each end. The central area shall contain at least 200 locker cubicles, each 12 inches x 12 inches x 16 inches deep along the walls. Boot storage facilities shall be covered areas with shelves, racks, or other means of storing boots subject to approval by the Contractor. Boot storage facilities shall prevent cross-contamination of boots and shall be capable of being kept clean of contaminated materials. The Subcontractor shall provide three trailers, one at each site.
 - b. Each trailer shall generally follow the arrangement shown in the Information for Bidders.
- B. The access control trailer shall be located at the decontamination area at each of the three sites. The quality control trailers shall be located at the access control area at the BC site. The change facilities trailers shall be located at each of the three sites within the site fence near the access control trailers. Final location of the trailers shall be as approved by the Contractor.
- C. Each trailer shall be properly blocked and leveled and shall be provided with stairs, stoops, and handrail, a deck at the door sill level, skirting all around the trailer, and trailer tie-downs. The Subcontractor shall furnish and install a weatherproof cover over the deck and steps.

- D. Each trailer shall be provided with running water and power, and shall be properly lighted and temperature conditioned for summer and winter use. Wash basins and toilets shall be connected to sanitary facilities specified in Article 1.12.
- E. Access Control trailers shall contain a sink, a single shower for personnel decontamination, and a change facility for occasional use by all personnel working on site. A wash basin shall be installed in the Quality Control trailer and shall be approximately 30 inches by 20 inches wide by 12 inches deep.
- F. The Subcontractor shall design and furnish personnel washing facilities at each of the three access control trailers. As a minimum, the Subcontractor shall include a wash basin with faucet for hand wash, an outside faucet for foot wash, and a 6-foot square concrete slab, 6 inches thick, with a 6-inch high curb. A removable metal grate and a 6-inch drain in the center of the slab draining to a contaminated discharge point shall be installed.
- G. The Subcontractor shall install a washer and dryer at the processing sites and disposal site and a dishwasher at the UC processing site, including utility hook-ups at access control trailers at each site. The Contractor will provide the appliances.
- H. The Subcontractor shall install the trailers no later than April 15 for the BC and NC sites and no later than April 30 for the UC site.
- I. The Subcontractor shall maintain and pay license fees on all trailers as required by applicable regulations.

1.6 PARKING AREAS

- A. No personal vehicles will be permitted inside the construction work area. Vehicles used for construction purposes will be allowed inside the work area, but will be monitored for radioactive contamination at the access gate or control point before leaving the area.
- B. The Subcontractor shall provide parking areas at each of the three sites for maintenance and delivery vehicles, the Contractor's and Subcontractor's representatives, and for other authorized visitors, as indicated on the Subcontract Drawings. Parking for personal cars shall be limited to the Contractor's and Subcontractor's office areas.

- C. Any additional parking required shall be the responsibility of the Subcontractor and subject to the Contractor's approval.
- D. The Subcontractor shall provide an aggregate surfaced area within the access control areas, as indicated on the Subcontract Drawings.
- E. Aggregate surface materials shall conform to the requirements of Section 02205.
- F. Each layer of aggregate surface course shall be compacted to a density of not less than 95 percent of the maximum density determined in accordance with the requirements of ASTM D1557.

1.7 JANITORIAL AND MAINTENANCE SERVICES

- A. The Subcontractor shall provide daily janitorial and maintenance services including, but not limited to, the following for all Contractor's trailers, toilet facilities and the access control areas:
 - 1. Sweep, vacuum, mop, and, if required, polish floors.
 - 2. Clean toilets, doors and windows, office furniture.
 - 3. Collect and dispose of office and yard solid waste.
 - 4. Furnish toilet paper, paper towels, soap, cups, napkins, light bulbs, etc.
 - 5. Operate and maintain trailer services including, but not limited to, the water supply and wastewater collection systems; heating, ventilating and air-conditioning systems; and lighting and security systems, including doors, windows, steps, floors and lighting fixtures.
- B. Janitorial and maintenance services shall be provided throughout the term of the Subcontract.
- C. Janitorial and maintenance personnel shall have the appropriate radiological training in accordance with the requirements of Section 00800, Article SC-8.

1.8 SNOW REMOVAL SERVICES

- A. The Subcontractor shall provide snow removal services in the following areas:
 - 1. Walkways to the office trailers.

2. Parking areas.

3. Equipment and material storage areas.

4. Access roads to site facilities as necessary as determined by the Contractor.

B. Snow removal services shall be provided throughout the term of the Subcontract at no additional cost to the Contractor.

1.9 TEMPORARY ROADS

A. For definition of temporary roads, see Article SC-1 of Section 00800 - Special Conditions.

B. Construction shall be coordinated with and shall be as approved by the Contractor.

C. Thirty days prior to the start of any roadway work, the Subcontractor shall submit, for review and approval, improvement drawings to the Contractor. The submittal shall include the Subcontractor's Quality Control Plan including testing requirements and records. The improvement drawings shall indicate approval by the local, County, State or Federal agency having jurisdiction over such roads.

D. The Subcontractor shall coordinate all road construction activities with local utilities, regulatory agencies, landowners and fire and police departments as applicable.

E. Erosion shall be kept to a minimum and suitable grades and radii of curves shall be maintained to facilitate ease of movement of vehicles and equipment.

F. Longitudinal and cross-drainage facilities including, but not limited to, the ditches, structures, pipes and the like shall be furnished and installed by the Subcontractor.

G. Equipment shall be regularly cleaned so that mud or dirt is not carried onto public roads. Subcontractor shall be responsible for cleaning up any mud or dirt transported by his equipment on public roads.

H. The Subcontractor shall furnish and install road signs, and signals, and shall mark and stripe pavements, if pavement is provided, as required, for the safe operation of vehicles.

I. The construction of County Road CR-S8 detour at the UC site, of the access road to the NC site via County Road CR-10R and

of the access road to the BC site from State Highway 141 is specified in Section 02205.

1.10 STORAGE OF MATERIALS AND EQUIPMENT

- A. Subcontractor shall make arrangements for exterior storage areas for materials, equipment, and debris. Locations and perimeters of such facilities shall be subject to the approval of the Contractor.
- B. All operations of the Subcontractor, including storage of materials, shall be confined to approved areas. Subcontractor shall be liable for any and all damage caused by him during such use by him of property of the Contractor or other parties. Materials shall be stored in accordance with the manufacturer's instructions, as applicable.
- C. Subcontractor shall store construction materials and equipment within boundaries of designated areas or areas approved by the Contractor. Storage of gasoline or similar fuels shall conform to the requirements specified in Article SC-7 of the Special Conditions and Section 01560, Article 1.7.

1.11 CONSTRUCTION EQUIPMENT

- A. Subcontractor shall erect, equip, and maintain all construction equipment in accordance with all applicable statutes, laws, ordinances, rules and regulations of the Contractor or other authority having jurisdiction.
- B. Scaffolding, staging, runways, hoists, barricades, and similar equipment required for performance of the Subcontract shall be provided and maintained by the Subcontractor. Hoists or similar equipment shall be provided with operators and signals, as required.
- C. Subcontractor shall provide, maintain, and remove upon completion of the work, all temporary rigging, scaffolding, hoisting equipment, debris boxes, barricades around openings and excavations, fences, ladders, and all other temporary work, as required for all work hereunder unless otherwise required by the Contractor.
- D. Construction equipment and temporary work shall conform to all the requirements of State, County, and local authorities, OSHA, and underwriters which pertain to operation, safety, and fire hazard. Subcontractor shall furnish and install all items necessary for conformity with such requirements,

whether or not called for under the separate sections of these Specifications.

- E. The Subcontractor shall provide suitable space and lighting for the maintenance of the equipment.

1.12 TEMPORARY SANITARY FACILITIES

- A. Subcontractor shall provide temporary sanitary facilities for use by all employees and persons engaged in the Work, including lower-tier subcontractors, Contractor, DOE, their employees and authorized visitors.
- B. Sanitary facilities include enclosed chemical toilets, washing sinks, pipes, tanks and pumping equipment. These facilities shall meet the requirements of local public health standards. Open pit or trench latrines will not be permitted.
- C. Chemical toilets and washing sinks shall be provided for use by the Subcontractor, his employees and all other workers and suppliers.
- D. Contaminated water from the Access Control and Quality Control trailers' wash sinks, clothes washer, the outside sink and foot wash facilities and from the emergency shower shall be collected to drain into the decontaminated sump by a separate piping system. The contents of the sump shall be pumped into the wastewater retention basin or to the decontamination washwater recycling system.
- E. During the term of the Subcontract, all tanks including the decontamination sump shall be kept pumped out and cleaned of sediment at regular intervals to prevent overflow and contamination of the ground, flowing streams or surface drainage.
- F. Sanitary facilities shall be located as approved by the Contractor, and shall be maintained in a sanitary condition during the entire course of the Work. Subcontractor shall keep such facilities adequately supplied with toilet paper, paper toweling, paper cups, etc., as required.
- G. At completion of the Work, sanitary facilities shall be properly disinfected and the tank and the contents disposed of offsite as Subcontractor's property.

1.13 TEMPORARY ELECTRIC POWER

- A. The Subcontractor shall provide and maintain during the course and progress of the Work all electrical power and wiring requirements to facilitate the work of all trades and services associated with the Work including power for decontamination pads, sump pumps and retention basins. The sites can be served by the San Miguel Power Co. The Subcontractor shall make arrangements with the serving utility and shall pay all charges for providing and maintaining electrical service including usage costs at the sites. All temporary wiring, feeders, and connections and any standby generators or generating capacity required in excess of the serving utility capacity shall be furnished by the Subcontractor. For sites not serviced by the San Miguel Power Company, the Subcontractor shall provide generators providing power 24 hours a day, 7 days a week.
- B. Routing of temporary conductors, including welding leads shall not create a safety hazard nor interfere with operation and maintenance of facilities. Approval from Site Manager shall be obtained prior to making connections to power panels.
- C. All temporary wiring installed by the Subcontractor shall be accomplished in accordance with the requirements of the National Fire Protection Association (NFPA) Codes 70 and 70E (latest edition), using acceptable code materials and equipment.
- D. There may be times during the period of the Subcontract when the Contractor will schedule power outages which will make temporary electrical power unavailable over any of the electrical transmission and distribution systems. Normally, these outages will be scheduled sufficiently in advance to give the Subcontractor prior notification; however, due to operational requirements, it may be necessary to "kill" the lines without prior notification. The Contractor assumes no liability for interruptions, delays, or inconveniences caused to the Subcontractor as a result of such electrical power outages or power failure, scheduled or unscheduled, except that any delay in completion of the work resulting directly from such power outages shall be deemed a delay due to unforeseeable causes beyond the control and without the fault or negligence of the Subcontractor within the meaning of Article GP-56, "TERMINATION FOR DEFAULT-DAMAGES FOR DELAY, TIME EXTENSIONS," of the General Provisions, and the Subcontractor shall be entitled to relief in accordance with the provisions of said Article GP-56, provided he gives written notice of such delay in accordance with the requirements thereof. There will be

no adjustment in the Subcontract Price due to any such electrical power outage or power failure.

E. Subcontractor shall provide power and lighting to all trailers, and for all Work as required, at no extra cost to the Contractor, and as follows:

1. A minimum of 240/120V, single phase, 200A electric service to all Contractor's trailers.
2. Adequate temporary lighting to all trailers, and for all Work, as required.
3. Exterior areas around offices and parking areas shall be provided with security flood lighting conforming to the current IES standards. Yard security lighting shall consist of one pole mounted mercury vapor yard light at each office layout.

F. Temporary power for the Radon Gas Monitor (RGM) Stations and the Air Particulate (AP) Stations: Power provided shall be capable of providing 2-1/2 kW minimum service and shall be 120V, single phase, 60 cycle. The use of generators or temporary power lines shall be at the Subcontractor's option. This power shall be provided and available 30 days prior to contaminated earthmoving activities and maintained at the BC site for 30 days after completion of the radon barrier cover and maintained at the UC and NC sites for 30 days after removal of contaminated materials from the UC and NC sites. Approximate locations of the RGM and AP stations are shown on the Subcontract Drawings. Final locations will be determined in the field by the Contractor.

G. The Subcontractor shall provide upon request as-built drawings of all buried and overhead power supply lines including voltages. All power supply boxes and breaker boxes shall be labeled appropriately including voltages.

H. Temporary power shall be removed at the completion of the Subcontract.

1.14 TEMPORARY WATER

A. General:

1. All temporary water service for drinking, sanitation and construction purposes shall be provided as specified in this Section.

2. Subcontractor shall furnish, install, operate and maintain all equipment and materials as required, including necessary tanks, piping, hoses, meters, valves, fixtures, and the like, to distribute water to various points of usage throughout the site.
3. Electric power and other requirements shall be as specified in Article 1.13.

B. Potable Water:

1. Subcontractor shall provide and maintain adequate supply of chilled drinking water in bottles to all Contractor's trailers from an approved source.
2. Subcontractor shall provide and maintain potable water for sanitary uses to all Contractor's trailers and at the access control areas from an approved source. Subcontractor shall be responsible for making all arrangements for connections, operation, maintenance and distribution of sanitary water to all points of usage on the site. Sanitary distribution alignments on-site shall be subject to approval by the Contractor.
3. Subcontractor shall provide and maintain adequate supply of potable water in all places of employment. The Subcontractor shall comply with 29 CFR 1926.51 and maintain documented evidence that weekly inspections are conducted to assure compliance.

C. Construction Water: The Subcontractor shall make his own arrangements for construction water. Water rights from the Dolores River will be available from the U.S. Bureau of Reclamation for each of the three sites. The Subcontractor shall be responsible for making all necessary arrangements for obtaining, conveying, storing and using all construction water.

D. All plumbing fixtures including wash sinks, emergency shower, and toilets provided in the Contractor's trailers shall be connected to a source of water supply.

1.15 DECONTAMINATION FACILITIES

- A. Prior to leaving the sites, all vehicles, equipment, tools and materials will be checked by the Contractor for radioactive contamination. If the level of contamination is excessive, as determined by Contractor's Health Physics personnel, the contamination shall be removed by the Subcontractor. The Subcontractor shall furnish, install,

operate and maintain decontamination facilities at each of the three sites for:

1. Washing contamination from Subcontractor and Contractor vehicles, equipment, tools and materials that become contaminated during use in the Work.
 2. Recycling washwater from wastewater recirculation pond for reuse as washwater for decontamination.
 - [3. Furnishing make-up water, replacing excessively contaminated water, and emptying the surplus water, when required.]*
 4. Emptying the solids from recirculation ponds sumps, as required.
- B. Each of the decontamination facilities shall, as a minimum, include the following:
1. Decontamination pad with steel grating to facilitate drainage.
 2. High-pressure (75-100 psi), low-flow wash system capable of decontaminating vehicles, tools and equipment, as required, for Work under the Subcontract, consisting of pumps, motors, tanks with suction and discharge piping, valves, meters, gages, nozzles, etc.
 3. Lined recirculation pond.
 4. A ditch or a pipeline from decontamination pad to the retention basin.
- [C. Contaminated washwater and sediments shall be collected from the decontamination pad by gravity to the lined recirculation pond. The water from the pond shall be recycled for reuse as washwater by a pumping system. Excess water shall be used to the extent feasible for dust control of contaminated areas and in moisture-conditioning of soils during construction of fills in contaminated areas. Sediment from the pond shall be collected and disposed of as contaminated material.]*
- [D. At the UC and BC sites, decontamination facilities shall be designed and operated to eliminate washwater flow into the retention basins.]*

* P.I.D. 11-S-08

- [E. The Subcontractor may elect to use a sump, settling basin and recycling system to eliminate washwater flow to the retention basin.]*
- F. The Subcontractor shall submit his proposed decontamination pad and vehicle wash system design, including calculations, drawings, and equipment list with capacities, to the Contractor for review at least 30 days prior to commencement of installation.
- G. The Subcontractor shall submit his operations plan for each decontamination facility 30 days prior to commencement of hauling operations. The submittal shall include, but not be limited to, the following:
 - 1. Safety.
 - 2. Manpower required.
 - 3. Decontamination of vehicles other than haul units.
- H. Demolition and disposal of the decontamination facilities shall conform to Section 02050.

1.16 TEMPORARY HEAT

Subcontractor shall provide, at his own expense, all temporary heat as necessary for the trailers and common enclosures and for proper installation of all work, equipment, and materials, and for the protection of all work and materials, against damage from dampness, cold, and freezing.

1.17 TEMPORARY TELEPHONE SERVICE

- A. The sites can be served by the Eagle Telecommunication Company. The Subcontractor shall make arrangements for telephone service for his own use and shall provide for two lines to the Contractor's access control and quality control trailers at the BC site and one line to the Contractor's access control trailer at the UC site.
- B. All cost of telephone service connections external and internal shall be borne by the Subcontractor.
- C. The Contractor will provide telephones for his own use and pay his own monthly usage costs.

* P.I.D. 11-S-08

1.18 TEMPORARY FENCES

See Sections 02832, 02835 and 02836.

1.19 SHUT-DOWN TIME OF SERVICES

The Subcontractor shall not disconnect or shut down any part of the existing utilities and services, except by express permission of the Contractor. The Subcontractor shall submit schedule of estimated shut-down time in order to obtain such permission, and shall notify all interested parties, utilities, County authorities, etc., as required.

1.20 MAINTENANCE

- A. Subcontractor shall maintain all construction and temporary facilities and utilities in good working condition as required by the Contractor during the term of the Subcontract. Vegetation shall be controlled by cutting or other means, subject to Contractor's approval, in work areas including, but not limited to, office, access control, and fuel storage areas.
- B. The Subcontractor shall maintain existing fences shown on the Subcontract Drawings.
- C. Maintenance of Roads:
 - 1. Subcontractor's maintenance shall include, but not be limited to, haul routes, access roads, intersections, and associated utilities during the term of the Subcontract for the safe and efficient transport of materials, equipment, supplies and personnel.
 - 2. The Subcontractor shall be responsible for maintenance of roads, highways and utilities and traffic control required during maintenance operations. Maintenance shall include patching of roads, shoulders and repair of underground utilities along the haul route. This will include county roads. Patching shall be performed in accordance with Sections 401 and 403 of the Colorado Department of Transportation Standard Specifications and the San Miguel County Land Use Code. Cold mix may be used for patching in cold weather. A complete inspection documenting the existing conditions of the highways and roads shall be submitted by the Subcontractor and will be subject to Contractor's approval.

- D. The Subcontractor shall remove from any road any contaminated material deposited there by his operations. Such removal and cleanup shall be at no additional cost to the Contractor.

1.21 STATUS AT COMPLETION

- A. Upon completion of the Work, or prior thereto, when so required by the Contractor, the Subcontractor shall:

1. Repair existing roads to their original condition or better except for State Highway 141 overlay to be done by others.
2. Demolish any temporary structures including all ramps. Rehabilitate any disturbed wetlands or private property.
3. Remove and dispose of all construction facilities including all equipment and Subcontractor-furnished trailers, and other facilities and utilities including all concrete foundations. Disconnect utilities to the trailers and remove the trailers from the sites.
4. Restore the areas occupied by the construction facilities to their near original contours by grading to provide positive drainage and to promote natural vegetation. Similarly, all areas utilized for temporary facilities shall be returned to substantially their near original, natural state, or as otherwise indicated or directed.
5. Obliterate all on-site temporary roads and reclaim new roads (constructed as temporary roads for the Subcontractor's convenience) and Subcontractor stockpile areas and restore the area to near original conditions to the extent practicable or as required by applicable permits.
6. Restore all disturbed and exposed areas as specified in Sections 02200, 02205 and 02935.
7. Remove and dispose of the fencing and gates.

- B. All temporary facilities removed by the Subcontractor shall be disposed of offsite by the Subcontractor as his property.

PART 2 - PRODUCTS

(Not Used)

PART 3 - EXECUTION

(Not Used)

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

- A. Measurement for payment for the following items will be by their lump sum basis.
 - 1. Temporary Trailers
 - 2. Temporary Roads and Parking Areas
 - 3. Temporary Sanitary Facilities
 - 4. Temporary Electric Power
 - 5. Temporary Water
 - 6. Construction of Decontamination Facilities at the UC, NC and BC Sites
- B. Measurement for payment for janitorial and maintenance services will be by the number of months of janitorial and maintenance services actually provided. Month will be a calendar month.
- C. Separate measurement for payment will not be made for snow removal services.
- D. Separate measurement for payment will not be made for any other item of work specified in this Section.

4.2 PAYMENT

- A. Payment for items 1 through 6 of Article 4.1.A above will be by their applicable lump sum prices quoted therefor in the Bid Schedule. The prices quoted shall include full compensation for furnishing all labor, materials, equipment, tools, accessories and incidentals and for performing all work as specified for designing, fabricating, installing/ construction, operating, maintaining, removing and disposal of the facilities and providing specified services as required through the term of the Subcontract.

- B. Payment for janitorial and maintenance services will be by the unit price per month quoted therefor in the Bid Schedule.
- C. Separate payment will not be made for snow removal services. Full compensation for such work will be considered to be included in the applicable related items of work or incidental to the Subcontract.
- D. Separate payment will not be made for any other item of work specified in this Section. Full compensation for such work will be considered to be included in the applicable related items of work or incidental to the Subcontract.

END OF SECTION 01500

SECTION 01560

TEMPORARY CONTROLS

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section covers the requirements for temporary controls required during the construction of the temporary and permanent works. Temporary controls shall include related equipment, facilities, and incidentals.
- B. Temporary controls shall include, but not be limited to, the following:
 - 1. Dust Control (Nuisance and Radiological)
 - 2. Silt Control
 - 3. Noise Control
 - 4. Pollution Control and Spill Prevention
 - 5. Water Control
 - 6. Access, Traffic and Safety Controls
 - 7. Protection of Exposed Surfaces
- C. The Subcontractor shall be responsible for furnishing, installing, constructing, operating, maintaining, removing and disposing of the controls as shown on the Subcontract Drawings, as specified in this Specification, and as required by the Contractor for the completion of the Work under the Subcontract.
- D. All such temporary controls shall be located as shown on the Subcontract Drawings and as directed by the Contractor, and maintained in clean, safe and sanitary condition at all times until completion of the Subcontract.
- E. Upon completion of the Subcontract, the temporary controls shall be left in the status specified in Article 1.12 of this Section.
- F. The requirements specified herein are in addition to any requirements specified elsewhere in the Subcontract Documents. Temporary controls shall meet the requirements for all-weather service.
- G. All land disturbances related to the temporary controls shall be minimized to the greatest extent possible and the land restored to the extent reasonable and practical, to its original contours by grading to provide positive drainage and by seeding the area as specified in Section 02935.

1.2 RELATED WORK

- A. Section 00800 - Special Conditions
- B. Section 01019 - Mobilization
- C. Section 01500 - Construction Facilities
- D. Section 02141 - Dewatering and Drainage
- E. Section 02200 - Earthwork
- F. Section 02205 - Road Construction
- G. Section 02935 - Seeding

1.3 APPLICABLE PUBLICATIONS

- A. The Publications listed below form a part of this Specification to the extent referenced. The Publications are referred to in the text by the basic designation only:

- 1. American Society for Testing and Materials (ASTM):

D751-89 Methods for Testing Coated Fabrics

D1682-64 Standard Test Methods for Breaking Load and
Elongation of Textile Fabrics (R 1975)

- 2. Colorado Department of Transportation (CDOT):
"Standard Specifications", as applicable.

- 3. DOE Order 5000.3B, DOE Order 5480.11 (Radiation Protection for Occupational Workers), and other applicable DOE orders.

- 4. National Electric Code, Standards as applicable.

- 5. National Fire Protection Association (NFPA), as applicable.

- 6. Occupational Safety and Health Administration, Standards as applicable.

- 7. UMTRA Project Construction Safety and Health Management Program (MK-UMTRA-4)

- 8. Uniform Building Code (UBC):
1991 Edition, applicable Chapters and Sections.

9. U.S. Department of Transportation (DOT):
49 CFR Parts 100-178, 300-399.
 10. U.S. Environmental Protection Agency (EPA):
40 CFR, Standards and Regulations, as applicable.
- B. All required facilities, equipment and utilities shall also be constructed/installed, maintained and operated in accordance with applicable Federal, State, County, and Utility laws, rules, and regulations. Notwithstanding contrary provisions of General Provisions, General Conditions and Special Conditions, nothing in the Subcontract Drawings and Specifications shall be construed to permit work not conforming to such laws, rules and regulations.

1.4 DUST CONTROL

- A. The Subcontractor shall be responsible for providing adequate dust control measures during the term of the Subcontract as required by the Contractor and the State Air Emissions Permits and as stated in the approved Proactive Dust Suppression Plan in accordance with Section 00800, Special Conditions, Article SC-3.
- B. Dust control shall consist of furnishing water supply, required equipment, additives, accessories and incidentals, and carrying out proper and efficient measures wherever and as often as necessary to reduce dust nuisance, and to prevent dust originating from construction operations or from natural causes on all sites and haul roads, as required by the Contractor. Dust shall be controlled.
- C. Water shall be applied by means of pressure-type distributors or pipelines equipped with a spray system or hoses with nozzles that will ensure a uniform application of water.
- D. All equipment used for the application of water shall be equipped with a positive means of shut-off.
- E. All equipment shall be in good operating condition for applying water on the project at all times.
- F. The Subcontractor may use additives if necessary to control dust or to conserve water as approved by the Contractor. If such additives are used, furnishing and applying the additives shall be at no additional expense to the Contractor.
- G. The use, location of application, and the amount and type of additives proposed for use by the Subcontractor shall be

subject to approval by the Contractor and shall meet the requirements of the appropriate regulatory agencies.

- H. The primary sources of water for dust control in contaminated areas at the sites will be recycled water from the decontamination wastewater recirculation systems, wastewater retention basins, or water from tailings and subsoil dewatering to the extent feasible. When these sources are judged inadequate or unacceptable, the Subcontractor may, with the Contractor's approval, use water from an alternate source.
- I. The source of water for dust control in non-radiologically contaminated areas shall be free of contamination.
- J. Dust in parking areas shall also be controlled.
- K. The Subcontractor shall only apply the amount of water necessary for dust control and compaction. Excess water shall not be applied to tailings placed in the disposal cell.

1.5 SILT CONTROL

- A. Silt fences shall be furnished and installed to conform with the following requirements:
 - 1. Structure: woven
 - 2. Width: 36 inches
 - 3. Grab Tensile Strength (ASTM D1682): 175 lbs. (WARP)
 - 4. Mullen Burst Strength (ASTM D751): 300 psi
 - 5. Puncture Strength (ASTM D751): 60 psi
 - 6. Equivalent Opening Size: U.S. Sieve No. 30/70
- B. Posts shall be made of wood minimum 2 inches square, or 1.25-inch x 1.00-inch steel T-section or equivalent, or acceptable plastic with an equivalent section. Post length shall be sufficient for 18-inch embedment in firm ground.
- C. Preassembled silt barrier fences may be used, subject to the Contractor's approval.
- D. Silt fences shall be installed to conform with the details shown on the Subcontract Drawings and in accordance with the manufacturer's written recommendations.

1.6 NOISE CONTROL

See Section 00800, Article SC-7, Paragraph M.

1.7 POLLUTION CONTROL AND SPILL PREVENTION

A. Pollution of Waterways: The Subcontractor's construction and related activities shall be performed by methods that prevent entrance or accidental spillage of solid or liquid matter, contaminants, debris and other objectionable pollutants and wastes into streams, watercourses, flowing or dry, and underground water sources. Such pollutants and wastes will include, but will not be restricted to refuse, earth and earth products, garbage, cement, concrete, sewage effluent, industrial waste, radioactive substances, hazardous chemicals, oil and other petroleum products, aggregate processing tailings, and mineral salts. Pollutants and wastes shall be disposed of in accordance with applicable permit provisions or in a manner acceptable to and approved by the Contractor. All waste materials shall be disposed of within one year of the start of collection in any specific container.

B. Storage and Disposal of Petroleum Products:

1. Petroleum products covered by this Section include all refined and used petroleum products. During project construction, all petroleum products shall be stored in such a way as to prevent contamination of all ground and surface waters. All refined and used petroleum product spills (one gallon or more), or any spill which contaminates surface water, shall be reported immediately to the Contractor.
2. Storage facilities shall conform to the requirements of Construction Environment, Safety and Health Management Program specified in Article SC-7 of the Special Conditions and the Spill Prevention Control Countermeasures (SPCC) provisions of 40 CFR Part 112, if applicable.
3. Lubricating Oil: Lubricating oil may be brought into the project area in steel drums or other means, as the Subcontractor elects. If the total volume of stored oil is greater than 1320 gallons, then the Subcontractor shall provide secondary containment facilities in accordance with EPA regulations contained in the Code of

Federal Regulations 40 CFR 112. [Containment facilities shall be subject to approval by a registered professional engineer.]* Used lubricating oil shall be stored in steel drums, or other approved means, and shall be recycled or returned to the supplier for disposal. It shall not be burned or otherwise disposed of at the project area.

4. If the total volume of stored petroleum products is greater than 1320 gallons and these products are stored above ground, the Subcontractor shall prepare a Spill Prevention Control and countermeasure plan in accordance with applicable EPA and state regulations. This plan shall be approved by a registered professional engineer and shall be submitted to the Contractor for approval 30 days prior to storing petroleum products on site. All storage tanks larger than 1000 gallons shall be hydrostatically tested prior to use including associated piping.
 5. The Subcontractor shall submit for approval by the Contractor a Waste Minimization and Recycling Plan for material generated on-site including, but not limited to, used oil, used anti-freeze, used fuels, used oil filters, used batteries, used containers of maintenance products (e.g. paint cans), oily rags, and petroleum product contaminated soils, prior to the generation of any such materials. This plan shall address all points of generation surveillance, handling, recycling, record keeping, and other pertinent items. The Subcontractor shall not generate hazardous waste.
- C. The following environmental pollution control measures shall be adopted by the Subcontractor for the trucks hauling contaminated materials on public roads to prevent the spread of radioactive contamination in uncontaminated areas:
1. Trucks shall be equipped with leakproof seals and locking devices on dump gates or other approved means to prevent any leakage of contaminated material onto roadways. Switches for operating gates shall be equipped with "arming" switching and an "operation" switch, which shall impede unintended operation of the gates. All gates shall be equipped with locking devices to impede inadvertent opening of the gates.
 2. Trucks shall be totally enclosed by a system that structurally contains the sides and covers all surfaces or a tarpaulin system that covers the top surface

* P.I.D. 11-S-07

completely. The use of crusting agents such as Wen-Don CBD-12 or approved equal applied to the surface of the contaminated materials being transported shall conform to the applicable local, state and federal agency (including permit) requirements. Chemical crusting agents shall be used only after demonstrating to the Contractor the performance of such agents and receiving an approval from the Contractor for use of such agents.

3. Prior to travel on offsite roadways or beyond the contaminated site area, trucks shall be decontaminated by washing with water. All contamination shall be removed as determined by the Contractor. Leakage of material from the vehicle will not be permitted. The Subcontractor shall be responsible to ensure that locking devices and seals are adequately secured prior to release from the contaminated area.
4. Health Physics personnel employed by the Contractor will routinely check trucks for residual contamination prior to release from contaminated areas.

1.8 WATER CONTROL

- A. When water hose usage is required on the project, the water hoses shall be located inside the site areas such that any spills which might be contaminated are contained within the site areas. When it is not feasible to locate hoses inside any site perimeter such that any potentially contaminated spill can be contained inside the site boundary, berms shall be constructed so that any spill will be contained.
- B. For other water control requirements, see Section 02141, Dewatering and Drainage.

1.9 ACCESS, TRAFFIC AND SAFETY CONTROLS

A. Access Control:

1. General:

- a. Private, personal or agency vehicles will not be allowed in the controlled site areas.
- b. Parking of private, personal or agency vehicles shall be in restricted areas outside of the controlled site areas as designated by the Site Manager or his representative.

2. Processing Sites: All access to the processing sites shall be through the access control gates.
3. Disposal Site: All access to the disposal site shall be through the access control gate.

B. Traffic and Safety Controls:

1. The Subcontractor shall post construction areas and roads, including state highway and access road intersections, with traffic control signs or devices used for protection of workers, the public and equipment. The signs or devices shall conform to the American National Standards Institute D6.1E-1988, Manual on Uniform Traffic Control Devices for Streets and Highways, and the latest revision of the Colorado Supplement thereto.
2. Signs or traffic control devices shall be removed or covered as soon as they have served their purpose. It is particularly important to remove any markings on road surfaces which under conditions of poor visibility could cause a driver to turn off the road or into traffic moving in the opposite direction.
3. Barricades for protection of employees shall conform to the portions of the American National Standards Institute D6.1E-1988, Manual on Uniform Traffic Control Devices for Streets and Highways, relating to barricades.
4. Material Haul on Public Roads: All requirements stated in the permits shall be followed for using public roads for hauling materials to the site.
5. The Subcontractor shall be responsible for providing all necessary bonding required by the applicable city, county and state highway departments.
6. All existing, temporary, or maintenance roads may also require decontamination after the construction activities are completed. All costs in connection therewith shall be considered to be incidental to the applicable items of work to which they pertain.
7. Colorado-certified flag persons, properly equipped with International Orange protective clothing and flags, shall be provided by the Subcontractor at all such times, as necessary, to direct or divert pedestrian or vehicular traffic. Four Colorado-certified flag persons shall be posted on State Highway 141, two at either side of the approach to the BC access road turnoff and two at the

approach to the UC and NC sites during truck transport hours.

8. The Subcontractor shall submit a detailed Traffic Plan for all sites prior to hauling activities. The Traffic Plan shall be subject to Contractor's approval.
9. Pursuant to Article GP-51 of General Provisions, Section GC-3C.1.a of General Conditions, the Subcontractor shall construct and maintain fences, planking, barricades, lights, shoring, and warning signs as required by local authorities and Federal and State safety ordinances, and as required, to protect the Contractor's property from damage or loss and as necessary for the protection of the public, and provide walks around any obstructions made in a public place for carrying on the Work covered in this Subcontract. All such protection shall be left in place and maintained until removal is authorized.
10. In addition, the Subcontractor shall guard and protect all workers, pedestrians, and the public from excavations, blasting operations, haul traffic, construction equipment, all obstructions, and other dangerous items or areas by means of adequate railings, guard rails, temporary walks, barricades, warning signs, sirens, directional signs, overhead protection, planking, decking, danger lights, etc.

1.10 PROTECTION OF EXPOSED SURFACES

See Section 02200, Article 3.1.A.

1.11 MAINTENANCE

Subcontractor shall maintain all temporary controls in good working conditions during the term of the Subcontract for the safe and efficient transport of equipment and supplies, and construction of permanent works, as required by the Contractor.

1.12 STATUS AT COMPLETION

- A. Upon completion of the Work, or prior thereto, when so required by the Contractor, Subcontractor shall:

1. Remove all temporary controls as required by the Contractor.

2. Restore and seed disturbed areas as specified in Sections 02200 and 02935.

PART 2 - PRODUCTS

(Not Used)

PART 3 - EXECUTION

(Not Used)

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

- A. With the exception of furnishing and installing silt fence, separate measurement for payment will not be made for work specified in this Section.
- B. Measurement for payment for furnishing and installing silt fence will be by the linear feet of fence furnished and installed.

4.2 PAYMENT

- A. With the exception of furnishing and installing silt fence, separate payment will not be made for work specified in this Section. Payment for such other work will be considered to be included in the applicable related items of work specified elsewhere in the Subcontract Documents or incidental to the Subcontract.
- B. Payment for furnishing and installing silt fence will be by the unit price per linear foot quoted therefor in the Bid Schedule. The price quoted shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for performing all work involved in constructing, maintaining, and removing silt fences, including any clearing, stripping, tree removal, excavation, concrete work, if any, complete, as shown on the Subcontract Drawings and as accepted by the Contractor.

END OF SECTION 01560

Document No. 3885-SRK-S-01-02422-04

Issued for Construction-Revision 2

Temporary Controls

01560 - 10

SRK

WP51
022195

SECTION 01561

CONSTRUCTION CLEANING

1.1 SCOPE

- A. This Specification Section covers furnishing of all labor, materials, equipment, and services, and performing all operations necessary for, and properly incidental to, cleanup during construction and final cleaning of the sites, prior to acceptance of the Project by the Contractor as specified herein and in other sections when specified.
- B. The requirements specified in this Section are supplemental to the requirements specified elsewhere in the Subcontract Documents.
- C. Hazardous waste material cleanup shall be performed in accordance with Section 02081.

1.2 WORK NOT INCLUDED

Chemical, Toxic or Hazardous Waste

1.3 RELATED WORK

- A. Section GC-1D - General Conditions
- B. Section 00800 - Special Conditions: Definitions
- C. Section 01560 - Temporary Controls
- D. Section 02081 - Asbestos, Hazardous and Non-Hazardous Materials
- E. Section 02110 - Site Clearing
- F. Section 02200 - Earthwork
- G. Section 02205 - Road Construction

1.4 GENERAL

- A. It is required that the entire sites be kept in a neat and orderly condition, and the Contractor or his representative

may, at any time during construction, order a general cleanup of the sites as a part of the work under this Section.

- B. Subcontractor shall dispose of waste, trash, and debris in a safe, acceptable manner, in accordance with applicable laws and ordinances and as prescribed by authorities having jurisdiction. No waste material or debris shall be buried on the sites. Burning of trash or debris on the sites will not be permitted.
- C. Location of a dump for trash and debris and the length of haul to such a location and all disposal costs shall be the Subcontractor's responsibility.

1.5 CLEANUP DURING CONSTRUCTION

- A. Cleanup: The Subcontractor will be required to clean up construction work areas including all trailers parking and storage areas and dispose of waste material. Cleanup of construction work areas will be required on a daily basis. At the close of each day's work all small quantities of waste and debris resulting from construction activities shall be gathered up and disposed of as designated in paragraph B below. Waste and debris shall not be allowed to accumulate in such quantities as to create an unsightly appearance, or safety or fire hazard, nor shall it interfere in any way with free access to, and operation of existing facilities.
- B. Waste Disposal:
 - 1. General: Material determined to be waste will be tested for radioactive contamination prior to removal from the construction sites. Testing will be performed by the Contractor at no cost to the Subcontractor to classify the waste into the following two categories for disposal purposes:
 - a. Uncontaminated Waste: The Subcontractor shall provide suitable receptacles for all construction office waste material such as wrapping paper, discarded containers, scrap lumber, scrap metals, etc. Other uncontaminated waste including construction office waste shall be disposed of offsite as Subcontractor's property in a safe, acceptable manner, in accordance with the applicable laws and ordinances and as prescribed by authorities having jurisdiction. No waste material or debris shall be buried on the sites.

- b. Contaminated Waste: Waste materials identified as contaminated materials defined in Article SC-1 and materials resulting from demolition operations and demolished materials stockpiled on site by others shall be disposed of in the construction of the tailings embankment as specified in Section 02200.

1.6 FINAL SITE CLEANUP

- A. Prior to final inspection, the entire site shall be thoroughly cleaned and shall be put into a neat, acceptable condition. All construction waste and unused materials, dunnage, loose rock and stones, excess earth, and debris of any description resulting from the work shall be removed from the entire site.
- B. All construction areas shall be thoroughly cleaned to the satisfaction of the Contractor prior to final acceptance of the completed Subcontract.

PART 2 - PRODUCTS

(Not Used)

PART 3 - EXECUTION

(Not Used)

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT AND PAYMENT

Separate measurement or payment will not be made for work required under this Section. All costs in connection with the work specified herein will be considered incidental to the Subcontract.

END OF SECTION 01561

Division 2

Sitework

SECTION 02050

DEMOLITION

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section describes the requirements for the demolition of the following structures and facilities (including plugging and abandoning of utilities), and disposal of debris as shown on the Subcontract Drawings and as specified in this Section.
1. Existing structures and facilities shown on the Subcontract Drawings and identified in the Information for Bidders including fences, buried utilities and miscellaneous debris.
 2. Miscellaneous debris scattered throughout the site or included in the contaminated materials.
 3. New structures and facilities constructed under this Subcontract including the following:
 - a. Temporary facilities as specified in Section 01500.
 - b. Temporary fences as specified in Section 01500.
 - c. Membrane liners and ballast from wastewater retention and recirculation ponds.
- B. If underground structures, including but not limited to, slabs and foundations, that are not shown on Subcontract Drawings, not visible from the surface, and could not be reasonably foreseen by the Subcontractor are encountered, the Contractor may determine that the structures may be left in place if all of the following conditions are met:
1. The Contractor is notified immediately upon discovery of the structures.
 2. It is determined that the structures were not shown on the Subcontract Drawings and were not visible from the surface at the time of Subcontract award.
 3. If the concrete is not contaminated or if it is feasible to decontaminate the concrete, and if soil below the structure is not contaminated.

4. If the top of the concrete is at least 2 feet below finish grade, and
 5. If the structure does not contain voids determined to be unacceptable by the Contractor.
- C. If underground items are encountered which require special demolition efforts, this work may be considered a changed condition as determined by the Contractor.

1.2 RELATED WORK

- A. Section 00800 - Special Conditions
- B. Section 01500 - Construction Facilities
- C. Section 01560 - Temporary Controls
- D. Section 01561 - Construction Cleaning
- E. Section 02081 - Asbestos, Hazardous and Non-hazardous Materials
- F. Section 02090 - Sealing Monitor Wells
- G. Section 02200 - Earthwork
- H. Section 02205 - Road Construction
- I. Section 02771 - Membrane Liner
- J. Section 02832 - Chain Link Fence and Gates
- K. Section 02835 - Deer Fence and Gates
- L. Section 02836 - Smooth Wire Fence and Gates

1.2 WORK NOT INCLUDED

Removal and disposal of hazardous waste material shall be as specified in Section 02081.

1.3 DEFINITIONS

- A. Demolition: Demolition includes complete dismantling, cutting and breaking up of structures, including all solid contents and associated services and utility lines including their foundations and below grade slabs and footings.

Irrespective of the depth of excavations, all foundations shall be removed, demolished and disposed of as specified in this Section. Demolition also includes removal and disposal of demolished materials and debris, as shown on the Subcontract Drawings and as specified in this Section.

- B. Utility: For the purpose of this Section, utility means any service, such as electric power systems; gas distribution systems; telephone; water distribution; storm drain; and sanitary sewer services.
- C. Decontamination: Decontamination of structures entails the removal of alpha- and beta-gamma-emitting nuclides to acceptable levels as established by the Department of Energy.

1.4 SUBMITTALS

- A. General submittal requirements are specified in Section 01300.
- B. Twenty days prior to the start of Work, the Subcontractor shall submit to the Contractor, for review, a demolition plan including the following:
 - 1. Methods of demolition to be used.
 - 2. Methods of protecting structures, monitor wells, and other facilities to be saved.
 - 3. Schedule showing dates and structures to be demolished.
 - 4. List of equipment to be used.

1.5 DESCRIPTIONS OF STRUCTURES AND FACILITIES

- A. Descriptions of existing structures and facilities to be demolished are contained in a separate document entitled "Information for Bidders" available from the Contractor's office. Location of existing structures and facilities are shown on the Subcontract Drawings.
- B. Following structures and facilities constructed under this Subcontract shall also be demolished by the Subcontractor:
 - 1. Decontamination pads.
 - 2. Membrane liners.
 - 3. Temporary fences.
 - 4. Temporary foundations.

PART 2 - PRODUCTS

(Not Used)

PART 3 - EXECUTION

3.1 DEMOLITION

- A. During the execution of this Subcontract, if unidentified chemically hazardous or toxic waste materials, in addition to the already identified materials, are encountered, the Site Manager shall be immediately notified for identification and subsequent disposition.
- B. Locations of structures to be demolished are shown on the Subcontract Drawings and are described in the Information for Bidders; however, the Subcontract Drawings may not show the locations of all foundations, rubble and debris, concrete pads, and the like, required to be demolished and removed within the boundaries of the project sites.
- C. Pollution Controls:
 - 1. Water sprinkling, temporary enclosures, and other Contractor approved methods shall be used to limit the amount of airborne dust and dirt to the lowest practical level. Demolition work shall comply with governing regulations pertaining to environmental protection.
 - 2. Water shall not be used if it is likely to create hazardous or objectionable conditions such as ice, flooding, or pollution. A Contractor-approved water-based biodegradable wetting agent (surfactant) such as Dupont "Duponol WAQ" or equal may be used to reduce the quantity of water required.
- D. Permit requirements are specified in Article SC-11 of the Special Conditions.
- E. Demolition work shall be carried out using equipment compatible to the structures to be demolished and by methods required to complete the Work in accordance with governing regulations. The structures shall be demolished and the materials and debris disposed of as specified in Section 02200.
- F. Removal or plugging of the utility shall not be undertaken until written approval for such work has been obtained from the Contractor.

G. Unless otherwise specifically indicated on the Subcontract Drawings or in this Specification or otherwise authorized in writing by the Contractor:

1. All aboveground utilities shall be removed, broken up and stockpiled for disposal.
2. All underground utilities within the tailings pile and underground utilities from the contaminated areas shall be removed, broken up and stockpiled for disposal. Underground utilities within the areas shown on the Subcontract Drawings, including west of County Road S9 within the gas plant boundaries and along the gas line right-of-way shall remain in place. All abandoned utilities from the gas plant shall be capped or plugged with concrete grout.
3. When an abandoned utility line is connected to a line that will continue to be used, the abandoned line shall be disconnected first and the in-use line shall be sealed before plugging the abandoned line. Subsurface lines to be plugged or removed shall include mains shown on the Subcontract Drawings and all sub-mains and laterals connecting the buildings to the mains even though not specifically shown on the Subcontract Drawings.
4. The Contractor will obtain approval from the affected utility companies including, but not limited to, San Miguel Electric Company, UMETCO, and Eagle Telecommunications before disturbing utilities. Utilities shall be protected from damage by demolition operations until they are removed from service.

H. All pipes and ducts shall be cut to sizes no greater than 10 feet in length, and stockpiled onsite for disposal. All pipes and ducts 6 inches and larger in diameter shall be longitudinally cut in halves, or crushed flat.

I. Tanks and Vessels:

1. Tanks and vessels shall be emptied of contents prior to removal and demolition. Tanks and vessels shall be cut to pieces no greater than 10 feet long by 8 feet wide. The Subcontractor shall notify the Contractor if underground liquid storage tanks are encountered.
2. Liquid underground storage tanks presently exist near the Recreation Hall. The Subcontractor shall excavate and expose the tanks for survey and size determination and provide access to the interior of the tanks for sampling of the contents by the Contractor. The Contractor will

notify the Colorado Department of Health, Hazardous Materials and Waste Management Division prior to removal and/or demolition of any underground storage tanks.

- J. Solid metals, concrete, masonry and wooden members shall be cut in pieces to be no greater than 10 feet and no more than 27 cubic feet in volume. Solid pieces of concrete greater than 27 cubic feet in volume may be removed and placed in the embankment as approved by the Contractor.
- K. Metal objects with voids shall be crushed to sizes no greater than 27 cubic feet in volume with greatest-void dimension not exceeding 6 inches.
- L. Grading shall be performed, as required by the Contractor, to match existing contours in the vicinity and to facilitate drainage.
- M. All concrete structures, foundations, debris and rubble piles east of County Road S9 shall be removed, broken up and disposed of in the tailings embankment.
- N. The abandoned Recreation Hall (UC32) and dormitory building (UC33) and foundations shall be demolished, broken up and disposed of in the tailings embankment.
- O. After completion of the construction phase, the synthetic membranes shall be removed, decontaminated and disposed of as required by the Contractor. If the membrane cannot be decontaminated by practical means, it shall be disposed of by cutting into strips no greater than 3 feet by 20 feet and placing in the tailings embankment in a manner that would not induce settlement, inhibit water migration, or exceed the 5 percent limit on organic material by volume.
- P. All concrete pads, above ground and buried utilities shall be removed from BLM property area UC45.
- Q. Fences and gates shall be removed and disposed of as the Subcontractor's property. Concrete footings shall be disposed of in the tailings embankment or as directed by the Contractor.
- R. Grading shall be performed, as required by the Contractor, to restore existing grades to near natural conditions and as specified in Section 02200.
- S. Tires shall be decontaminated and disposed of as Subcontractor's property or otherwise cut circumferentially in half or shredded and disposed of in the tailings embankment.

3.2 DISPOSAL OF DEMOLISHED MATERIALS AND DEBRIS

- A. Demolished materials and debris shall be disposed of in the tailings embankment as shown on the Subcontract Drawings and as specified in Section 02200.
- B. Burning of materials removed from demolished structures will not be permitted.
- C. Uncontaminated materials such as fencing, piping, membranes, wooden platforms, and stairs for trailers and other materials shall be removed as the Subcontractor's property as directed by the Contractor.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Measurement for payment for demolition and disposal of existing structures and facilities (including abandoned utilities and rubble) specified in this Section will be on a lump sum basis.

4.2 PAYMENT

- A. Payment for demolition and disposal of existing structures and facilities (including abandoned utilities and rubble) specified in this Section will be by the lump sum price quoted therefor in the Bid Schedule. The price quoted shall include full compensation for furnishing all labor, materials, equipment, incidentals, and for performing all work specified, including, but not limited to, temporary stockpiling, transportation, and placement of demolished materials and debris in the tailings embankment.
- B. Separate payment will not be made for any other work specified in this Section. Full compensation for such work will be considered incidental to the applicable related items of work.

END OF SECTION 02050

Document No. 3885-SRK-S-01-02424-02
Issued for Construction-Revision 0

Demolition
02050 - 7

SRK

WP51
052594

SECTION 02081

ASBESTOS, HAZARDOUS AND NON-HAZARDOUS MATERIALS

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section describes the requirements for handling, removal and disposal of:
 - 1. All friable and nonfriable asbestos-containing materials, and
 - 2. Identified hazardous and non-hazardous materials.
- B. The Subcontractor shall furnish all labor, materials, services, insurance, and equipment necessary to carry out the removal and disposal work in accordance with the Environmental Protection Agency (EPA) and the Occupational, Safety and Health Administration (OSHA) regulations, applicable State and local government regulations, and as specified in this Section and as shown on the Subcontract Drawings.
- C. The requirements specified in this Section are supplemental to the requirements specified in General Provisions, General Conditions and Special Conditions.

1.2 WORK NOT INCLUDED

A. Unidentified Waste:

- 1. The Contractor shall be notified immediately if unidentified wastes are suspected or encountered. Such wastes will be fully characterized and identified through laboratory analysis by the Contractor.
- 2. If the wastes are identified as radiologically contaminated and suitable for disposal in the tailings embankment (Non-hazardous), the Subcontractor may be directed by Subcontract Change Notice to remove and dispose of these wastes in the tailings embankment.
- 3. If the wastes are identified as non-radiologically contaminated (chemical, toxic or hazardous) and not suitable for disposal in the tailings embankment, the

Subcontractor may be directed by a Subcontract Change Notice to remove these wastes.

1.3 RELATED WORK

- A. Section 00800 - Special Conditions
- B. Section 01300 - Submittals
- C. Section 02050 - Demolition
- D. Section 02200 - Earthwork

1.4 DEFINITIONS

See Section 00800, Article SC-1.

1.5 CODES AND REGULATIONS

- A. The Subcontractor shall comply with the applicable codes and regulations including, but not limited to, the following:

- 1. U.S. Department of Labor, Occupational Safety and Health Administration ("OSHA"):

- a. 29 CFR 1910.120, "Hazardous Waste Operations and Emergency Response".
 - b. 29 CFR 1926.58, "Asbestos", which includes regulations governing supervision by a "competent person" and air sampling by approved National Institute of Occupational Safety and Health (NIOSH) methods.

- 2. Environmental Protection Agency ("EPA"):

- National Emissions Standard for Hazardous Air Pollutants (NESHAPS) 40 CFR 61, Subparts A and M.

- 3. State of Colorado Department of Health ("CDH"):

- a. Colorado Waste Facility Siting Rules - Regulations Pertaining to Solid Waste Disposal Sites and Facilities.
 - b. C.R.S. 30-20-10 - Colorado Solid Waste Disposal Site Law.

- c. C.R.S. 25-15-101 - Colorado Hazardous Waste Act for offsite disposal of hazardous waste to an approved hazardous waste site.
 - d. C.R.S. 27-7-501 - Asbestos Control.
 - e. Colorado Air Pollution Regulations, Reg. 8, Part B, "Asbestos Control".
4. U.S. Department of Transportation Regulation 49 CFR 100-199.

- B. Posting Regulations: Current copies of applicable OSHA, EPA and Colorado CDH regulations shall be obtained by the Subcontractor and one copy of each shall be posted on the job site for information of employees. The EPA and CDH notifications and permits of asbestos removal, including the "Plan of procedures to be employed for compliance with EPA regulations" shall also be posted at the job site.

1.6 NOTIFICATION AND APPROVAL REQUIREMENTS

- A. Ten working days prior to the handling and disposal of asbestos-containing materials, the Subcontractor shall submit a written notice to the Colorado Department of Health, Air Pollution Control Division. A copy of the notice shall also be submitted to the Contractor. Notice shall be in compliance with applicable statutes and regulations.
- B. Upon completion of asbestos handling and disposal work, the Subcontractor shall submit a written report to the Colorado Department of Health, Air Pollution Control Division with a copy to the Contractor. The report shall comply with Colorado Department of Health requirements.

1.7 EXPOSURE MONITORING

- A. The airborne asbestos exposure outside of asbestos controlled areas shall not exceed 0.1 fibers/cc air, 8-hour Time-Weighted Average (TWA), which is the action level before reaching 0.2 fibers/cc air, 8-hour TWA, the permissible exposure limit.
- B. All air monitoring for asbestos and other hazardous materials shall be performed under the supervision of a "competent person" as defined in 29 CFR 1926.56(b), (e) and Appendix F. Air monitoring in areas where hazardous materials are stored or handled shall comply with 29 CFR 1910.120.

- C. Documentation of each air sample shall be as specified by the Site Manager and shall include at least the date and time, sample number, exact sampling location, name of individual performing sampling, sampling rate, sampling volume, analytical method, analytical results and limits of quantification and detection as per NIOSH analytical methods.
 - D. Analysis of air samples for asbestos shall be by NIOSH method 7400. All asbestos and chemical samples shall be analyzed by a qualified Contractor-approved laboratory. Results shall be reported to the Site Manager and Albuquerque Project Office Safety and Health Department within five working days of receipt by the Subcontractor. Current Contractor-approved laboratories are Barringer, Golden, Colorado for radio-chemistry analysis and Data Chem, Salt Lake City, Utah for all other analysis. Analyses shall be done in accordance with the Contractor-approved program.
 - E. Preliminary air sampling shall be sufficient to establish the perimeters of asbestos and other hazardous materials control areas to the satisfaction of the Site Manager. During asbestos handling work, samples shall be taken continuously outside each asbestos control area within 10 feet of each decontamination enclosure system exit and within 10 feet of each HEPA exhaust if applicable.
 - F. Air samples shall be taken in the breathing zones of workers removing asbestos and other hazardous materials in sufficient numbers to permit estimation of peak and Time Weighted Average (TWA) Exposures. At a minimum, for TWA exposures, one personal sample on the worker with the highest probable exposure is required in each asbestos control area, per work shift.
 - G. Clearance air samples shall be obtained from inside any structure where asbestos removal occurred. Sampling aggressively in accordance with EPA recommendations is required in sufficient numbers to ensure that the airborne concentration is below 0.01 fibers/cc.
 - H. The Subcontractor shall submit to the Contractor a copy of all analytical data and quality assurance within seven working days of the Subcontractor's receipt of results.
- 1.8 SUBMITTALS
- A. The Subcontractor shall, within fifteen days after receipt of Notice to Proceed, prepare and submit the following, as specified in this Section:

1. Asbestos Characterization, Removal, Handling and Disposal Plan.
 2. Fibrous Glass and Ceramic Fiber Materials Removal, Handling and Disposal Plan.
 3. Hazardous Materials Handling, Transportation and Disposal Plan.
 4. Subcontractor Qualifications.
 5. Qualifications of Health and Safety Personnel.
 6. Training Certificates with Statements of Medical Qualifications of all Asbestos Abatement Workers in compliance with the provisions of 40 CFR 763 (App. C).
 7. Training Certificates for all hazardous materials workers in compliance with the provisions of 29 CFR 1910.120.
 8. Training Certificate of one on-site Supervisor certified by U.S. EPA, National Asbestos Training Center, or Satellite Center, or equivalent, along with Colorado State Supervisor's certification in accordance with Colorado Air Pollution Regulations, Section 8.
 9. Proof of State of Colorado Asbestos Abatement Contractor Licensure.
 10. Proof of appropriate Liability Insurance and Worker's Compensation Coverage.
 11. Medical qualification statements for all Asbestos Abatement and Hazwoper Workers.
 12. Emergency Asbestos Abatement Contingency Plan for spills, leaks, or any release occurring during handling, transportation or disposal.
 13. Emergency Hazardous Materials Contingency Plan for spills, leaks, or any release occurring during handling, transportation or disposal.
- B. General submittals requirements are specified in Section 01300.
- C. Asbestos and Hazardous Materials Handling Plan:
1. In addition to the submittals specified in Section 01300, the Subcontractor shall submit a detailed plan of the work procedures to be used in the handling of asbestos-

containing materials and other hazardous materials. Such plan shall include:

- a. Construction details of the control barrier and the decontamination enclosure system.
 - b. Air monitoring plan.
 - c. Personnel and equipment decontamination plan.
 - d. Location of control areas.
 - e. Layout of change rooms.
 - f. Disposal plan.
 - g. Type of wetting agent and asbestos sealer to be used. Wetting agent and asbestos sealer shall be subject to approval by the Contractor upon receipt of the material safety data sheets.
 - h. Personnel protective equipment.
2. This plan shall be approved by the Contractor prior to the start of any asbestos or hazardous material work.
 3. The Subcontractor and his assigned asbestos abatement and hazardous materials remediation specialist shall meet with the Contractor prior to beginning work to discuss the plan in detail, including work procedures and safety precautions.

D. Subcontractor Qualifications:

1. A statement demonstrating Subcontractor's understanding of asbestos abatement and hazardous materials remediation shall include the following as a minimum:
 - a. Knowledge of asbestos abatement techniques and state-of-the-art abatement and hazardous materials remediation practices and equipment.
 - b. Knowledge of OSHA, EPA, NIOSH, CDH, and any other applicable regulations and requirements regarding asbestos abatement and hazardous materials remediation work practices and equipment.
 - c. Knowledge of the special safety hazards and requirements associated with asbestos abatement and hazardous materials remediation work.
 - d. Knowledge of the health hazards of asbestos and site specific hazardous materials.

2. A statement demonstrating Subcontractor's qualifications and experience shall include the following as a minimum:
 - a. The number of years firm has been engaged in asbestos abatement and removal, and hazardous materials remediation, listed separately, by category.
 - b. List of projects completed in the last five years that are similar in scope to this Project. Include names, addresses and telephone numbers of the purchasers of services; the name of the industrial hygienist, if any, overseeing the work; location; and type of work.
 - c. List all equipment, tools and materials available for use on this Project. Include certification by manufacturer that all HEPA equipment meets the requirements of the latest edition of the American National Standards Institute Standard ANSI Z9.2, "Fundamentals Governing the Design and Operation of Local Exhaust Systems."
 - d. A description of the qualifications and experience of all supervisors proposed for this Project. Include evidence of successful completion of an EPA-approved training course in asbestos removal (including subject matter and duration of course). Also include evidence of previous supervision of at least two asbestos abatement projects and two hazardous materials remediation projects similar in scope and nature to the present project, providing the name, address and telephone number of each of the purchasers of services.
 - e. A description of the asbestos and hazardous materials training program for the workforce, including duration of course, subject matter and qualifications of the instructor. Minimal qualification for training for each employee shall include instruction on the hazards of chemical and asbestos exposure, on the use, fitting and limitations of respirators and protective clothing, on all aspects of asbestos abatement and hazardous materials work procedures, protective measures, and safety precautions. Describe any special expertise of any of the workers.
 - f. A breakdown of the composition of the workforce proposed for this Project including: percentage of personnel trained, experienced, fulltime with

company; percentage of personnel trained, experienced, parttime with company; and percentage of "pick-up" labor.

- g. A copy of the Subcontractor's Personal Protective Equipment Program including the Respiratory Protection Program. Minimal qualifications are as specified in 29 CFR 1926.134.
- h. A description of the Subcontractor's medical surveillance for the employees. Minimal qualifications shall be as specified in 29 CFR 1926.58 or where applicable, state regulations.
- i. A statement regarding the Subcontractor's insurance status.

E. Qualifications of Person Responsible for Health and Safety:

- 1. A statement demonstrating the qualifications and experience of the person responsible for Health and Safety and air monitoring technicians that the Subcontractor intends to employ on this Project shall include the following as a minimum:
 - a. A record of experience qualifying the Health and Safety person as a professional specializing in asbestos abatement and hazardous materials remediation. As a minimum, this shall include a review of previous experience in asbestos abatement and hazardous materials remediation projects, including the names, addresses and telephone numbers of the purchasers of the services; locations of the work performed; and a review of the industrial hygiene activities performed for each job. Air monitoring specialists shall possess State of Colorado Certification.
 - b. A description of each air monitoring technician's training in asbestos and hazardous materials air monitoring, and a review of previous air monitoring experience in asbestos and hazardous materials removal projects, including the names, addresses and telephone numbers of the purchasers of the services; locations of the work performed; and a review of all air monitoring and other inspection activities performed for each job.
 - c. A statement for each person who may be doing asbestos air sample analysis, indicating the qualifications, training program and experience in

asbestos air sample analysis, analytical methods used, dates of training, and average number of asbestos samples analyzed per month in the last twelve months.

- d. A statement indicating the Health and Safety Person's degree of authority on this Project for effecting corrective actions deemed necessary in his or her judgement.

- F. Final Report: The Subcontractor shall submit a Final Report within 45 days of completion of all removal and handling and disposal activities. This report shall include all notes, correspondence, photographs, results, data, plans, procedures, and documentation associated with the work.

1.9 COLORADO DEPARTMENT OF HEALTH, AIR QUALITY CONTROL DIVISION REQUIREMENTS

- A. The Subcontractor shall comply with the following provisions of Colorado Air Quality Control Commission Regulation No. 8 of the State Solid Waste Regulations:

1. As of July 1, 1987, all persons who wish to conduct asbestos abatement work in Colorado are deemed certified according to the requirements contained in C.R.S. 25-7-505 providing that 1) all the applicant's employees have been trained according to Federal Occupational Safety and Health Administration worker training requirements for asbestos abatement workers, and 2) the applicant employs at least one trained and certified supervisor who shall be on-site at all times when abatement work is proceeding.
2. As of July 1, 1987, all abatement project supervisors shall be deemed certified as trained supervisors according to the requirements contained in C.R.S. 25-7-506 providing an applicant has completed a three-day or longer asbestos abatement supervisory course given by any U.S. Environmental Protection Agency National Asbestos Training Center or Satellite Center, or equivalent, within the preceding 12 months from enactment of this regulation.
3. As of January 31, 1992, all personnel conducting asbestos clearance sampling shall be required to successfully complete a state approved sampling training course.

PART 2 - PRODUCTS

2.1 EQUIPMENT

- A. The need for scaffolds, ladders, and powered equipment is apparent due to the height at which some materials to be removed are located. These conditions create other hazards covered for compliance in the Construction Safety and Health Management Program as required in Special Conditions.
- B. The Subcontractor shall include in the handling, transportation and disposal plan, specified in Article 1.6 above, the construction aids he intends to provide.
- C. Construction aids shall be cleaned and free of asbestos fibers and other hazardous materials (and radioactive contamination as specified in Article SC-8 of the Special Conditions) before removal from site-controlled work areas.
- D. The Subcontractor shall provide all necessary transport vehicles for hauling the asbestos-containing and other hazardous materials that CDH will allow for disposal at the disposal site.
- E. The Subcontractor shall provide excavating and compacting equipment for burial of the asbestos-containing and other hazardous materials in the disposal area.

PART 3 - EXECUTION

3.1 GENERAL

- A. Characterization, handling and storage of asbestos-containing materials, glass fibrous and ceramic fiber materials, and contaminated and uncontaminated hazardous, toxic and non-hazardous materials and chemicals shall conform to requirements of Colorado Department of Health's Regulations Pertaining to Solid Waste Disposal Sites and Facilities.
- B. The radiologically contaminated asbestos scrap shall be transported to the disposal site and disposed of in the designated area shown on the Subcontract Drawings and as specified in Paragraph 3.1.A of this Section. The use of such designated area(s) shall appear as part of the County Certificate of Designation for the contaminated materials embankment.

- C. Other Radiologically Contaminated Hazardous and Non-Hazardous Waste Materials: The other radiologically contaminated hazardous and non-hazardous waste materials shall be transported to and disposed of in the tailings embankment as shown on the Subcontract Drawings.
- D. Transport and disposal of other hazardous and non-hazardous waste materials shall conform to the Colorado Hazardous Waste Regulations 6 CCR 1007-3, in addition to applicable 40 CFR and 49 CFR requirements.

3.2 ASBESTOS-CONTAINING MATERIALS

- A. Asbestos materials handling and disposal shall conform to the requirements of this Section and to Section 8 of the Colorado Department of Health's Regulations Pertaining to solid Waste Disposal Sites and Facilities. In case of any conflict, the Contractor will determine the applicability of a particular code or standard.
- B. Types of Asbestos-Containing Material:
 - 1. There are approximately 1300 square feet of siding materials containing 20 to 25 percent chrysotile asbestos on the outside of the recreation building. Asbestos siding shall be removed and stockpiled and handled separately prior to demolition of the recreation building.
 - 2. The transite materials on a pile, identified as No. UC11 on the Subcontract Drawings, are 10 percent chrysotile asbestos. Similar materials are also scattered on the ground in several locations making it difficult to estimate quantity.
 - 3. All floor tiles contain 10 percent to 20 percent asbestos. Removal of the mastic adhesive is not required prior to demolition of the floor slab.
- C. Storage, Transport and Burial of Asbestos-Containing Materials:
 - 1. Storage of ACM shall be maintained so that there is no possibility of ACM release into the environment or causing employee exposures. The ACM shall be placed in two 6 mil polyethylene asbestos disposal bags with proper labels, then placed in either a metal drum with a tight fitting lid or an enclosed storage trailer that allows room for inspections. Storage containers shall be labeled and posted with warning signs as required in OSHA 29 CFR 1926.58.

2. All friable and non-friable asbestos shall be stored in a temporary storage area (TSA) that is designed to be level, have earthen berms to avoid run-on precipitation, warning signs that meet OSHA 29 CFR 1926.58 requirements, and a single stranded wire fence. The storage area shall be located so it does not interfere with site activities and be designed to contain all necessary materials.
3. Asbestos-containing materials shall be adequately contained for transport to the disposal site. The methods of containment shall include sealing, wrapping, bagging, enclosure in drums, or other Contractor-approved method. The Subcontractor shall arrange for water supply needed to wet the asbestos-containing materials.
4. All ACM shall be considered to have radiological activity above 2,000 pCi/g. All asbestos-containing materials shall be disposed of in the contaminated materials disposal cell. The transport vehicle shall enclose the asbestos while on route to the disposal cell. The transport vehicle shall be lined in plastic so that spilled asbestos residues are easily cleaned by a properly trained person. Within 24 hours of arrival at the disposal cell, the asbestos shall be buried under at least 2 feet of soils compacted in a manner to prevent resuspension. The Subcontractor shall prepare the as-built drawings showing the final disposal location and elevation.
5. The materials and containers shall be transported to the disposal site and disposed of at lower elevations in the contaminated materials embankment as directed by the Contractor and as specified in Articles 3.2.E and 3.2.F of this Section. The use of such designated area(s) shall appear as part of the Certificate of Designation for the contaminated materials encapsulation cell.

D. Cleaning Work Areas After Asbestos Removal:

1. After asbestos-containing materials have been transported to the disposal site, work areas and transport vehicles shall be cleaned with significant assurance that no asbestos fibers shall become airborne when other work takes place.
2. The Subcontractor shall notify the Contractor's Site Manager when work is complete for a final visual inspection.

3. Clearance Air Sampling: Aggressive air sampling [as per 40 CFR, Part 763, Appendix A (1987)] shall be conducted to the satisfaction of the Site Manager at each asbestos controlled work area. Asbestos clearance levels shall be below 0.01 fibers/cc air.

E. Colorado Approved Asbestos Disposal Plan:

1. Introduction: The methods for handling, transporting, and burial of the ACM are addressed in this disposal plan. Applicable regulations including OSHA 29 CFR 1926.58, EPA 40 CFR Part 61, and State of Colorado Waste Facility Rules Number 8 have been referenced during development of this work plan.
2. Personnel: Only personnel who are adequately trained and knowledgeable in the hazards of asbestos, proper work procedures, use of respiratory protection, and use of personal protective equipment are allowed to handle the ACM during the disposal process. Personnel who perform this work shall meet the applicable regulations of OSHA 29 CFR 1926.58.
3. Packaging ACM: Friable ACM has been double bagged in 6 mil polyethylene asbestos disposal bags which have warning labels applied. The warning labels state "DANGER, CONTAINS ASBESTOS FIBERS, AVOID CREATING DUST, CANCER AND LUNG DISEASE HAZARD". The friable and non-friable ACM shall remain packaged in this manner throughout the disposal process.
4. Asbestos Emissions: No visible emissions of dusts will be allowed during the handling, transportation, or disposal process of the ACM. Adequate dust control measures, such as wet methods shall be used, as necessary, to prevent any of the friable or non-friable ACM from releasing fibers. Water sprays shall be used to control fibers during the burial of ACM in case of accidental bag rupture or transite pipe breakage. In the case where the ACM bags need to be punctured to release trapped air so that proper compaction after burial may occur, extra water shall be continually applied at the point of puncture. Water used for dust control shall be applied by using hand held garden sprayers, water spray compressors, or water trucks with hoses.
5. Handling ACM:
 - a. All personnel that handle ACM during the disposal process shall wear, at a minimum, a half mask respirator with High Efficiency Particulate Air

(HEPA) filters, Tyvek coveralls with hoods (or equivalent), proper protective gloves and work boots. Additional respiratory protection may be required in order to comply with OSHA 29 CFR 1926.58 requirements.

- b. All personnel protective equipment used during the disposal process including respirator cartridges shall be bagged and disposed of as required in this plan.
6. Work Zones: Work zones shall be constructed around all areas where ACM is handled during the disposal process. The work zone shall include a "contaminated" area and a "clean" area constructed of hazard barrier tape. Only personnel adequately trained and protected may enter the "contaminated" work zone area.
7. Air Monitoring:
- a. Air monitoring for asbestos shall be performed on personnel who have the highest potential exposures and around the perimeters of the work zones to determine area concentrations.
 - b. Results from this monitoring will be made available to the Contractor for personnel involved in the disposal process.
 - c. Air monitoring and analytical techniques shall comply with OSHA 29 CFR 1926.58 requirements.
8. Transportation of ACM:
- a. All ACM shall be loaded into a covered vehicle which has been properly lined with polyethylene plastic. The covered vehicle shall be constructed to ensure that no fibers are released during transportation to the cell. The inside lining shall be designed to facilitate the decontamination process when the ACM is off-loaded.
 - b. A complete inspection of the trucks and trailers used to transport the ACM will be performed by Contractor personnel in accordance with the Hazardous Material Transportation Requirements and Truck Inspection Plan before the ACM is transported to the disposal cell.

9. Burial:

- a. The Contractor will pre-select an appropriate area in the cell where burial will occur. This location shall be properly documented in cell design criteria. The Contractor will determine how the ACM is spaced and deposited into trenches and pits during the burial process so voids are eliminated to be consistent with the approved cell design.
- c. The ACM shall be covered with a minimum of 24 inches of compacted tailings to ensure stable placement.

10. Asbestos-Containing Pipe: Asbestos-containing pipe that is discovered during remedial action activities shall be handled by employees trained in the hazards of asbestos per OSHA 29 CFR 1926.58. The pipe shall be immediately wetted with water and kept wet until buried in the tailings disposal cell. Employees who handle excavated pipe will be monitored for exposure to airborne asbestos fibers by the Contractor's Industrial Hygienist to ensure exposures remain below the permissible exposure levels.

F. Disposal of ACP: The ACP shall be covered with one foot of loose fill and rolled by machinery to remove voids. The area shall then be rolled to a visibly firm condition but need not be tested for compaction to minimize worker exposure. The ACP shall be disposed of in the tailings embankment as directed by the Contractor.

3.3 FIBROUS GLASS AND CERAMIC FIBER MATERIALS

A. General:

1. Scope:

- a. This Article describes the requirements for handling, transportation, and disposal of Man Made Fibrous (MMF) material.
- b. During the Uranium Mill Tailings Remedial Action (UMTRA) demolition process, sources of MMF are removed. These sources of MMF may or may not be radiologically contaminated. All radiologically contaminated MMF is designated for disposal within the disposal cell. MMF not contaminated shall be disposed of offsite as Subcontractor's property.
- c. It is anticipated that MMF material will be encountered in the walls and ceilings of the recreation building and dormitory building. Other

MMF material sources will be insulation for pipes, valves and controls.

2. Notification and Approval:

- a. Ten days prior to the removal and handling of MMF-containing materials, the Subcontractor shall submit to the appropriate agencies, if and as applicable, all appropriate written notices. A copy of the notices shall also be submitted to the Contractor. Notice shall be in compliance with applicable statutes and regulations.
- b. Upon completion of MMF removal and handling, the Subcontractor shall submit, if and as applicable, a written report to the appropriate regulatory agencies that shall comply with all reporting requirements.

3. Exposure Monitoring:

- a. The airborne MMF exposure outside of MMF controlled areas shall not exceed 1.5 fibers/cc air, 8-hour Time-Weighted Average (TWA), which is the action level before reaching 3.0 fibers/cc air, 8-hour TWA, the permissible exposure limit.
- b. All air monitoring for MMF shall be performed under the supervision of a "competent person" as defined in 29 CFR 1926.58(b), (e) and Appendix F. Air monitoring in areas where hazardous materials are stored or handled shall comply with 29 CFR 1910.120.
- c. Documentation of each air sample shall be as specified by the Contractor and shall include at least the date and time, sample number, exact sampling location, name of individual performing sampling, sampling rate, sampling volume, analytical method, analytical results and limits of quantification and detection as per NIOSH analytical methods.
- d. Analysis of air samples for MMF shall be by NIOSH Method 7400. All MMF and chemical samples shall be analyzed by a qualified Contractor-approved laboratory. Results shall be reported to the Contractor within five working days. Current Contractor-approved laboratories are Baringer, Golden, Colorado and Data Chem, Salt Lake City, Utah.
- e. During MMF handling work, air samples shall be taken outside each MMF control area, within ten feet of

each decontamination enclosure system exit and within ten feet of each HEPA exhaust (if applicable), in sufficient quantity to appropriately evaluate exposure potential.

- f. Air samples shall be taken in the breathing zones of workers handling MMF in sufficient numbers to permit estimation of peak and Time Weighted Average (TWA) exposures. At a minimum, for TWA exposures, one personal sample from the worker with the highest probable exposure is required in each MMF control area per work shift.
- g. The Subcontractor shall submit to the Contractor a copy of all air monitoring data within seven days of the Subcontractor's receipt of results.

4. Submittals:

a. MMF Handling, Transportation, and Disposal Plan:

- 1) This plan shall specify how radiologically and non-radiologically MMF will be segregated. It shall describe all equipment needed and shall assure that all such equipment will be available before each work action is begun.
- 2) Subcontractor qualifications.
- 3) Qualifications of Health and Safety Personnel.
- 4) Training certificates for all MMF Abatement Workers in compliance with the provisions of 29 CFR 1910.120.
- 5) Training records that document that all personnel assigned to work with MMF are knowledgeable of health effects and protective measures.

b. MMF and Hazardous Substance Handling Plan: The Subcontractor shall submit a detailed plan of the work procedures to be used in the handling of MMF-containing materials. Such plan shall include as applicable:

- 1) Air Monitoring Plan
- 2) Equipment Decontamination Plan
- 3) Location of Control Areas
- 4) Removal and Handling Plan
- 5) Type of Wetting Agent

- 6) Personal Protective Equipment
- 7) Work Procedures

5. General:

- a. Handling of MMF-containing materials shall conform to the requirements of the applicable state regulations pertaining to Solid Waste Disposal Sites and Facilities.
- b. Radiologically contaminated MMF scrap shall be transported to the tailings embankment as directed by the Contractor.
- c. Non-radiologically contaminated MMF shall be disposed of off-site as Subcontractor's property.
- d. Characterization of MMF is required before demolition begins.

B. Radiologically Contaminated MMF Containing Materials:

1. Storage:

- a. Radiologically contaminated MMF-containing materials shall be adequately contained for transport to the tailings embankment. The methods of containment shall include sealing, wrapping, bagging, enclosure in drums, or other Contractor-approved method. Each package of MMF shall be labeled with the proper labels to identify the contents.
- b. All radiologically contaminated MMF-containing material shall be stored in metal drums or a storage van as specified in Article 3.2.C.3 of this Section.
- c. Personnel: Only personnel who are adequately trained and knowledgeable in the hazards of MMF, proper work procedures, use of respiratory protection, and use of personal protective equipment will be permitted to handle the MMF during the process.
- d. Packaging MMF: MMF shall be bagged in 6 mil polyethylene MMF disposal bags which have warning labels applied. The warning labels shall state "CAUTION. FIBROUS GLASS. AVOID BREATHING DUST." The MMF shall remain packaged in this manner throughout the storage process.
- e. MMF Emissions: No visible emissions of dust will be permitted during the removal, handling or disposal

process of the MMF. Adequate dust control measures, such as wet methods shall be used, as necessary, to prevent any of the MMF from releasing fibers.

f. Handling MMF:

- 1) All personnel that handle MMF during the disposal process shall wear, at a minimum, a half mask respirator with High Efficiency Particulate Air (HEPA) filters, Tyvek coveralls with hoods (or equivalent), proper protective gloves and work boots. Additional respiratory protection may be required depending on exposure monitoring.
- 2) All personal protective equipment used during the handling and storage process including respirator cartridges shall be bagged as required in this plan.

g. Work Zones: Work zones shall be constructed around all areas where MMF is handled during the removal and disposal process. The work zone shall include a "contaminated" area and a "clean" area constructed of hazard barrier tape. Only personnel adequately trained and protected may enter the "contaminated" work zone area.

C. Non-Radiologically Contaminated MMF Containing Materials:

1. Non-radiologically contaminated MMF shall be handled in the same manner as radiologically contaminated MMF except for disposal.
2. Non-radiologically contaminated MMF shall be separated from radiologically contaminated MMF.
3. Non-radiologically contaminated MMF shall be disposed of off-site as Subcontractor's property.

D. Cleaning Work Areas After MMF Removal:

1. After MMF-containing materials have been placed into the TSA, work areas and transport vehicles shall be cleaned to ensure that no MMFs shall become airborne when other work takes place.
2. The Subcontractor shall notify the Contractor when work is complete for a final visual inspection.

3.4 OTHER HAZARDOUS AND NON-HAZARDOUS MATERIALS

- A. General: Hazardous materials characterization, sampling, handling, disposal and associated record keeping shall conform to Colorado Department of Health Hazardous Wastes Regulations 6 CCR 1007-3.
- B. Handling of non-hazardous materials shall conform to applicable federal, state and local regulations pertaining to solid waste disposal.
- C. The handling of all materials under this Section shall be performed in accordance with the applicable OSHA regulations set forth in 29 CFR 1910.120.
- D. The temporary storage area (TSA) shall be designed and constructed. Prior to construction the design shall be submitted to the Contractor for approval. The TSA shall be level, bermed with soil to avoid run-on precipitation, posted, and secured with a single stranded wire fence. The size of the area shall be adequate to store all of the required materials until they are deposited in the tailings embankment. All containers shall be placed on pallets to avoid deterioration which could result from standing in accumulated storm water.
- E. Types of Hazardous and Non-Hazardous Materials: A burned gasoline tank or tanks may be encountered at the old gasoline storage area.
- F. Work areas where hazardous materials or wastes have been remediated shall be cleaned sufficiently to ensure that no visible residual contamination remains.
- G. Any unknown materials discovered during remedial action shall be placed in the TSA at the discretion of the Site Manager.
- H. Disposal Location, Transportation, and Burial: The Subcontractor shall submit to the Site Manager a plan for transportation and disposal of the radiologically contaminated hazardous and non-hazardous materials into the disposal cell. The plan shall include requirements that the drums shall be placed on the surface or in an excavation at the final disposal location, covered with one foot of loose fill, and rolled by machinery. Fill surrounding drums in the immediate vicinity shall be rolled to a visibly firm condition, but need not be tested for compaction to minimize worker exposure. All materials packed inside 85-gallon polyethylene drums shall be removed and the polyethylene drum shall be decontaminated and removed off-site or shredded and placed in the tailings embankment. The plan will be subject

to approval of the Site Manager who will select the disposal locations.

- I. The Subcontractor shall notify the Contractor's Site Manager when work has been completed for final inspection.

3.5 PAINTED SURFACES CONTAINING LEAD

- A. Many pieces of debris, equipment and materials that are included for demolition may be coated with paint containing metallic lead.
- B. Demolition of these items shall be accomplished through the use of shears, cutters or other equipment that will not produce airborne concentrations of lead above the action level as defined by OSHA in the Code of Federal Regulations 29 CFR 1910.1025 of 30 micrograms per cubic meter averaged over an 8-hour period.
- C. Accordingly, the use of gas cutting torches and the like will not be permitted, unless the Subcontractor proves, through a Contractor-approved laboratory, that metallic lead does not exist on the debris, equipment and materials being demolished in quantities that could exceed the specified limit.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Measurement for payment for handling, removal, transportation and disposal of asbestos, hazardous and non-hazardous materials and placement in the tailings embankment will be on a lump sum basis.

4.2 PAYMENT

Payment for handling, removal, transportation and disposal of asbestos, hazardous and non-hazardous materials and placement in the tailings embankment will be by the lump sum price quoted therefor in the Bid Schedule. The price quoted shall include full compensation for furnishing all labor, materials, equipment, tools, accessories and incidentals and for performing all work as specified including, but not limited to, all fees and permits and compliance with the codes and standards.

END OF SECTION 02081

SECTION 02090

SEALING MONITOR WELLS

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section describes the requirements for sealing and abandonment of existing unconfined monitor wells at the UC, NC and the BC sites. The approximate locations of all known wells within the project sites including those to be sealed are shown on the Subcontract Drawings.
- B. Table 02090-1 lists all known unconfined monitor wells that are to be sealed at the UC site. Table 02090-2 lists all known unconfined monitor wells that are to be sealed at the NC site. Table 02090-3 lists all known unconfined monitor wells that are to be sealed at the BC site. Additional well data are given in the Information for Bidders.
- C. Wells not listed in Tables 02090-1, 02090-2 and 02090-3 shall be saved unless otherwise directed by the Contractor.

1.2 APPLICABLE PUBLICATIONS

- A. The Publications listed below form a part of this Specification to the extent referenced. The publications are referred to in the text by the basic designation only:
 - 1. Manual of Water Well Construction Practices, Environmental Protection Agency, EPA-570/9-75-001.
 - 2. American Society for Testing and Materials (ASTM): C150-92 Standard Specification for Portland Cement.
 - 3. State of Colorado, Revised and Amended Rules and Regulations for Water Well Construction and Pump Installation, August 1, 1988 (2CCR 402-2).

1.3 SITE CONDITIONS

Subcontract Drawings show all known wells on and in the vicinity of the processing and disposal sites. The holes for the wells listed and the casings installed are indicated in Tables 02090-1, 02090-2 and 02090-3. The annulus of each well has been backfilled to the surface. Wells not designated to be sealed shall be protected to prevent damage or contamination with foreign substances during construction. Such wells, if damaged, shall be reconstructed by the Subcontractor at no cost to the Contractor.

TABLE 02090-1						
WELLS TO BE SEALED AT UC SITE						
Well No.	Approximate Coordinates		Depth of Well Hole (feet)	Casing Diameter and Type (inches)	Casing Depth (feet)	Screen Interval (feet)
	North	East				
BOTTOM OF WELLS IN ALLUVIUM						
505	58621	60066	19	4" ABS	19	11-19
506	59878	58896	21	4" ABS	19	12-19
507	60020	58704	20	4" ABS	20	10-20
553	58500	58530	25	4" PVC	25	13-23
555	59120	58560	35	4" PVC	33	21-31
557	58560	58275	45	4" PVC	44	32-42
BOTTOM OF WELLS IN SANDSTONE						
551	58460	58520	80	4" PVC	60	48-58
552	58470	58480	80	4" PVC	80	68-78
554	59160	58530	50	4" PVC	50	38-48
558	58110	58825	82	4" PVC	82	70-80
559	58400	59125	52	4" PVC	52	40-50
702	58900	59400	70	4" (Type Unknown)	68	55-65
703	58700	58700	55	4" (Type Unknown)	54.8	41.8-51.8
704	59300	58900	61.5	4" (Type Unknown)	61.5	46-56

TABLE 02090-2						
WELLS TO BE SEALED AT NC SITE						
Well No.	Approximate Coordinates		Depth of Well Hole (feet)	Casing Diameter and Type (inches)	Casing Depth (feet)	Screen Interval (feet)
	North	East				
BOTTOM OF WELLS IN ALLUVIUM						
501	58538	63678	22	4" ABS	21	12-21
503	58247	63269	27	4" ABS	26	20-26
504	58095	63088	19	4" ABS	18	14-18
512	58394	63267	20	4" ABS	20	12-20
686	58620	63769	22	2 "(Type Unknown)	N/A	15-20

TABLE 02090-3						
WELLS TO BE SEALED AT BC SITE						
Well No.	Approximate Coordinates		Depth of Well Hole (feet)	Casing Diameter and Type (inches)	Casing Depth (feet)	Screen Interval (feet)
	North	East				
BOTTOM OF WELLS IN SANDSTONE						
521	19621	22459	353	4" PVC	352	330-350
522	19607	22470	235	4" PVC	235	203-233
523	19620	22476	125	4" PVC	125	103-123
527	18873	22141	81	4" PVC	81	59-79
BOTTOM OF WELLS IN MUDSTONE						
516	19099	21931	227	2" PVC	227	215-225
518	19959	21745	109	4" PVC	109	97-107
519	19960	21758	338	4" PVC	338	316-336
520	19974	21748	240	4" PVC	240	218-238
526	18859	22153	207	4" PVC	207	175-205

PART 2 - PRODUCTS

2.1 MATERIALS

A. Approved sealing materials are as follows:

1. Cement used for sealing mixtures shall meet the requirements of ASTM C150 "Standard Specification for Portland Cement," Type II or Type V (high sulfate resistance), or other cement approved by the Contractor. The cement types shall be compatible with groundwater encountered in the wells to be sealed.
2. Cement grout shall be composed of one sack of Portland Cement (94 pounds), with 3 to 5 percent, by weight, of commercially processed sodium bentonite, to not more than 7.5 gallons of potable water in order to achieve a weight of not less than 15 pounds per gallon. The weight of the neat cement shall be sufficient to prevent flow of water into the well from any aquifer penetrated. Calcium chloride may be added to a Portland cement grout to accelerate the set, but it shall not exceed 2 pounds per sack of dry cement.
3. Chemically inert fill shall consist of well graded uncontaminated natural or crushed granular material in the sand range with sizes between U.S. No. 4 and No. 200. The fill shall be chemically inert with at least 90 percent of the material being siliceous.

PART 3 - EXECUTION

3.1 GENERAL

- A. The State of Colorado well abandonment regulations specified in Article 1.2.A.3 require that wells be sealed in a manner that is compatible with the well design and so as not to act as a conduit for future contamination of groundwater. Detailed well sealing criteria are outlined in the Environmental Protection Agency (EPA) Manual of Water Well Construction Practices, EPA-570/9-75-001, Article 56, pages 133-142. The basic premise of the EPA criterion is to seal abandoned wells and to restore, as much as possible, the geohydrologic regime in existence before the monitor well was constructed.
- B. The following criteria shall apply to all wells to be sealed on and in the vicinity of the sites:

1. The Subcontractor shall notify the Contractor 10 days prior to commencement of well sealing operations.
2. Well sealing operations shall be performed by a State-licensed (Colorado) drilling contractor.
3. All wells shall be sealed in such a manner that they will not act as a conduit for fluids to flow from the specific strata in which they were originally encountered.
4. All wells shall be located in the field and sealed by the Subcontractor prior to the beginning of stripping, grading or other surface-disturbing activities that will hinder the detection and sealing of wells. If any well cannot be located after a reasonable search, the Subcontractor shall, prior to the commencement of the well sealing operations, submit to the Contractor a written report documenting the well number, the areas covered and the effort spent in the search.
5. Upon discovery of any unknown wells during the earthwork operations, the Subcontractor shall give the Site Manager immediate verbal notice followed by written confirmation within 24 hours. Further earthwork activities in the immediate vicinity of the well shall be suspended until approved by the Contractor.

3.2 WELL SEALING PROCEDURES

- A. Unconfined Monitor Wells shall be sealed according to the rules specified in Article 1.2.A.3 and the following procedures:
 1. The Subcontractor shall check each well to be sealed for obstructions that may interfere with the sealing operation and shall remove any such obstructions prior to starting filling operations.
 2. The Subcontractor shall make all efforts to remove the well casings by methods approved by the Contractor as outlined in Article 56 of the EPA Manual of Water Well Construction Practices. Upon removal, if the casings and materials are found to be contaminated, they shall be decontaminated as required by the Contractor, or stockpiled and disposed of as demolition debris after breaking into lengths not greater than 10 feet.
 3. For all wells that the casing removal is not feasible, the well shall be filled with either on-site uncontaminated materials, clean sand or gravel to the static water level, then with chemically inert materials

(see Article 2.1.A.3) to the ground surface. The casing and cement grout, if present, shall be cut off and removed to a minimum of 2 feet and up to 5 feet below the existing grade surface, or the final grade cut elevation if the construction grade surface will be less than the existing grade surface (i.e. in areas of proposed cut), or as otherwise required for construction. A water-tight cover shall be furnished and permanently attached to the top of the casing, and the area shall be backfilled with native soils to the grade surface. The fill materials shall be thoroughly tamped.

4. For all wells that the casing can be removed, the hole shall be filled with chemically inert materials to within 5 feet of the existing grade surface or final grade cut elevation if the construction grade surface will be less than the existing grade surface. The top 5 feet of the hole shall be sealed with materials equal to or less permeable than the top foot of the surrounding soils, and the fill materials shall be thoroughly tamped.

3.3 REPORTING REQUIREMENTS

Within 30 days of the completion of well sealings, the Subcontractor shall submit a Well Abandonment Affidavit to the Colorado Division of Water Resources. A copy of the affidavit shall be submitted to the Contractor.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Measurement for payment for sealing of monitor wells at UC, NC and BC sites will be by the linear feet of wells sealed as measured from the bottom of well to the top of the completed seal.

4.2 PAYMENT

Payment for sealing of monitor wells at UC, NC and BC sites will be by the unit price per linear foot of existing depths of wells to be sealed quoted therefor in the Bid Schedule. The price quoted shall include full compensation for furnishing all materials, equipment, tools, accessories, incidentals, labor, and for performing the work specified in this Section including decontamination and disposal of materials and equipment.

END OF SECTION 02090

SECTION 02110

SITE CLEARING

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section describes the requirements for the following:

1. Clearing of vegetation, stripping of topsoil, and disposal of cleared and stripped materials from work areas.

1.2 DEFINITIONS

- A. Clearing: Clearing is defined as removing brush, other vegetation and trees. All such vegetation and trees shall be cleared down to the natural ground surface.
- B. Stripping of Topsoil: This shall consist of the removal of uncontaminated topsoil, including all roots, organic materials, vegetation, and other unsuitable material, by blading with a bulldozer or other equivalent means. Depth of stripping shall be 6 inches, unless otherwise indicated elsewhere in the Subcontract Documents.

1.3 RELATED WORK

- A. Section 02200 - Earthwork
- B. Section 02205 - Road Construction
- C. Section 02935 - Seeding

PART 2 - PRODUCTS

(Not Used)

PART 3 - EXECUTION

3.1 PRESERVATION OF PROPERTY

Existing improvements, adjacent property, utility and other facilities, and trees and plants that are not to be removed shall be protected from damage.

3.2 CLEARING

- A. Clearing shall be performed on all areas of construction activities. Contaminated cleared materials shall be kept separate from uncontaminated cleared materials.
- B. Uncontaminated cleared materials shall be disposed of as Subcontractor's property or may be used in the Work, as approved by the Contractor. Clearing and stripping of topsoil may be performed in one operation, subject to the Contractor's approval. Disposal of stripped vegetation at the BC site may be by burning. The Subcontractor shall be responsible for obtaining required permits for burning such wastes from Colorado Department of Health, Air Pollution Control Division.
- C. Contaminated cleared material shall be reduced in size as required by the Contractor and disposed of in the tailings embankment as specified in Section 02200.

3.3 STRIPPING

- A. Uncontaminated Areas: Stripping will be required in the following areas:
 - 1. Beneath all fills, including the tailings embankment area, in areas where excavation is not otherwise required;
 - 2. Beneath areas of riprap protection where excavation is not otherwise required.
 - 3. In areas of excavation where excavated materials are to be used as fill.

- B. Contaminated Areas: In areas of excavation where the contaminated surfaces are covered by vegetation, the removal of vegetation and contaminated topsoil may be carried out together with the excavation of underlying contaminated soil in one operation. All contaminated materials, including vegetation and topsoil, shall be disposed of in the tailings embankment.
- C. Stripped material shall be disposed of as specified in Article 3.4.
- D. Wetland Areas: Uncontaminated wetland work areas designated by the Contractor shall be stripped. Stripped uncontaminated material from wetland areas shall be stockpiled separately at the UC and NC sites and used in finish grading of areas designated by the Contractor.

3.4 STOCKPILING OF UNCONTAMINATED TOPSOIL

- A. The top 6 inches of topsoil at the BC site shall be stockpiled in a designated area. The stockpiled topsoil shall be used in the final site grading.
- B. Stockpiling of uncontaminated topsoil at the UC and NC sites shall be performed unless otherwise required by the Contractor upon his determination that there is insufficient uncontaminated organic topsoil in the area to justify the operation. If the Contractor determines that insufficient topsoil exists to justify stockpiling, the materials shall be disposed of in an approved spoil area or as Subcontractor's property.
- C. The stockpile areas shall be on the UC and NC sites as designated by the Contractor. Stockpiled topsoil shall be used in finish grading and seeding of the UC and NC sites. Seeding is specified in Section 02935. Stockpiled stripped soils may be used as common fill for final site grading material at the UC and NC sites as approved by the Contractor.

3.5 BURNING OF CONTAMINATED CLEARED AND STRIPPED MATERIAL

Burning of cleared and stripped materials from contaminated areas will not be permitted.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Separate measurement for payment will not be made for work specified in this Section. All such work will be considered incidental to the applicable related items of work.

4.2 PAYMENT

Separate payment will not be made for work specified in this Section. Full compensation for such work will be considered incidental to the applicable related items of work.

END OF SECTION 02110

SECTION 02141

DEWATERING AND DRAINAGE

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section describes the requirements for the collection and disposal of surface and subsurface water from the work areas, diversion and disposal of surface water from uncontaminated areas outside of work areas, and for the design, construction and maintenance of dewatering and drainage facilities at the UC and NC sites and the BC disposal site.
- B. A gravity dewatering scheme for work in contaminated areas is limited to temporary drainage (collection) ditches, dikes, culverts and wastewater retention basins as shown on the Subcontract Drawings. The Subcontractor shall, as required, design and provide additional gravity or pump systems for dewatering of contaminated water from work areas. Dewatering from windblown tailings and off-pile areas will be accomplished incrementally as removal of contaminated materials proceeds.
- C. Surface (gravity) and subsurface (pump system) dewatering and drainage system shall consist of swales, ditches, dikes, berms, drainage pipes, inlets and manholes, sumps, pumps, drives, piping, meters, gages, valves and other accessories and incidentals as required.
- D. A dewatering scheme for work in uncontaminated areas is not shown on the Subcontract Drawings. The Subcontractor shall, as required, design and construct additional gravity or pump systems or a combination of both systems for dewatering of uncontaminated water from work areas.
- E. If the groundwater level is higher than the bottom of excavation, the Subcontractor shall dewater the excavation, as required, for performance of work in the dry. Stormwater shall be removed from the excavation to maintain dry conditions during excavation and backfill placement.
- F. The Subcontractor shall furnish, install and maintain new drainage pipes (includes culvert pipes) shown on the Subcontract Drawings, and shall maintain existing drainage pipes.

- G. All additional systems provided by the Subcontractor for dewatering and drainage of contaminated or uncontaminated areas shall be in accordance with discharge permits provided by the Contractor.
- H. Earthwork operations shall be planned, scheduled and executed to minimize dewatering. The Subcontractor shall make his own determination, subject to Contractor's approval, for scheduling and executing work in areas which may require dewatering. Available data on ground water at the sites are provided in the Information for Bidders.
- I. At the NC site, the Subcontractor shall install a silt fence along the river bank as shown on the Subcontract Drawings.

1.2 DESCRIPTION

- A. The work of this Section includes, but is not limited to: dewatering work areas by installing sump pumps in low areas and excavations and disposal of water by providing drainage facilities including swales, ditches, interceptor dikes, pipes, and other drainage structures. Water from uncontaminated areas shall be pumped, or allowed to flow by gravity, to diversion ditches or drainage ditches leading to existing drainage courses that flow offsite. Water from contaminated areas shall be pumped, or allowed to flow by gravity, to collection ditches leading to the wastewater retention basin. [Wastewater from decontamination pad shall be collected into the recirculation ponds and either recycled for decontamination or used for dust control in contaminated areas.]*
- B. The Subcontractor shall be responsible for designing, scheduling, utilizing, providing, and maintaining any dikes, ditches, channels, flumes, drains, pipes, sumps, pumping equipment, monitoring wells, other subsurface dewatering devices, and other temporary diversion and protective work necessary to ensure that construction shall be performed in areas free from water and in accordance with all applicable permits.

1.3 PROTECTION

Water from contaminated areas shall not be permitted to flow over uncontaminated areas, unless measures are taken to prevent seepage into uncontaminated materials. The Subcontractor shall provide the measures required to prevent seepage of runoff from contaminated areas into uncontaminated

* P.I.D. 11-S-08

materials, subject to the Contractor's approval. [All potentially contaminated storm water shall be routed to the wastewater retention basins or detention ponds for dust control use within contaminated areas or evaporation.]* Any offsite discharge of retained contaminated water shall be treated as required to meet the water quality standards contained in the Colorado Discharge Permit System (CDPS) permit.

1.4 WORK NOT INCLUDED

- A. Drainage work related to the construction facilities, as specified in Section 01500.
- B. Furnishing, installation, operation, maintenance and removal of mobile wastewater treatment plant.
- C. Treatment of the contaminated water in the wastewater retention basin and discharge of the treated water.

1.5 RELATED WORK

- A. Section 01300 - Submittals
- B. Section 01500 - Construction Facilities
- C. Section 01560 - Temporary Controls
- D. Section 02050 - Demolition
- E. Section 02200 - Earthwork
- F. Section 02205 - Road Construction
- G. Section 02771 - Membrane Liner
- H. Section 02935 - Seeding

PART 2 - PRODUCTS

2.1 MATERIALS AND EQUIPMENT

The Subcontractor shall furnish all materials, equipment and appurtenances required for furnishing, installing, operating, maintaining and removing dewatering facilities, and shall also supply sufficient standby pumping and auxiliary equipment to preclude any interference to pumping operations during periods of breakdown and maintenance.

* P.I.D. 11-S-08

PART 3 - EXECUTION

3.1 DEWATERING PROCEDURES

- A. Surface runoff water from uncontaminated areas shall be pumped, or allowed to flow by gravity to natural drainage courses including diversion ditches. Erosion protection features including, but not limited to, silt fences, check dams, temporary detention ponds and the like shall be provided by the Subcontractor to minimize off-site siltation in the receiving stream. Subcontractor shall submit to the Contractor, for review, his design, layout and calculations, fifteen days prior to the construction of such features. The Subcontractor shall meet applicable permit requirements and other regulations for discharge of water from uncontaminated areas.
- B. [All storm water runoff from contaminated areas at the UC and BC sites shall be routed to collection ditches leading to lined wastewater retention basins. Water from the wastewater retention basins may be used before other sources for dust control in contaminated areas of Work.]*
- C. Water from the NC site shall be allowed to flow by gravity to natural drainage courses. Erosion protection features including, but not limited to, silt fences, check dams, temporary detention ponds and the like shall be provided by the Subcontractor to minimize off site siltation in the receiving stream. The removal of contaminated materials at the NC site shall occur between May 1 and June 30 and shall proceed from the higher elevation toward the receiving stream. The Subcontractor shall submit to the Contractor, for review, his design, layout and calculations, fifteen days prior to the construction of such features. The Subcontractor shall meet applicable permit requirements and other regulations for discharge of water from uncontaminated areas.
- D. The water level in excavation shall be maintained below the lowest point in the excavation during the backfill of the excavation unless otherwise approved by the Contractor.
- E. Ponding of surface water runoff on contaminated materials during storms shall be minimized. The Subcontractor shall maintain in-progress work or furnish additional drainage facilities as required to minimize ponding.

* P.I.D. 11-S-08

3.2 WASTEWATER RETENTION BASINS AND DRAINAGE DITCHES

- A. Wastewater retention basins and drainage ditches at the UC processing site and the BC disposal site shown on the Subcontract Drawings shall be constructed as specified in Sections 02200 and 02771.
- B. Additional temporary drainage ditches or dikes shall be constructed by the Subcontractor as required for collection of contaminated wastewater into the retention basins or to divert uncontaminated water offsite.

3.3 MAINTENANCE

- A. The Subcontractor shall be responsible for the maintenance of all drainage facilities during the term of the Subcontract. Drainage ditches and pipes may require periodic cleaning. Pipes and ditches shall be kept free of sediment deposits, debris and other materials that may restrict or prevent drainage. The Subcontractor, when directed by the Contractor, shall remove and replace all items not functioning properly because of clogging, damage, or deterioration at no additional cost to the Contractor.
- B. After removal of uncontaminated material, the Subcontractor shall fill all depressions and low spots where surface water can pond. The areas shall be graded to drain.

3.4 REMOVAL

- A. When no longer required for water control:
 - 1. Dewatering equipment and silt fences shall be removed, decontaminated as required, and disposed of as Subcontractor's property.
 - 2. Contaminated sediments deposited in ditches and the wastewater retention basins shall be removed and placed in the tailings embankment as specified in Section 02200 and as required by the Contractor. Uncontaminated sediments may be used in the grading of uncontaminated areas of work.
 - 3. Drainage pipes not required for permanent roads shall be removed. Contaminated pipes shall be removed and demolished as specified in Section 02050 and the demolished debris shall be placed in the tailings embankment as specified in Section 02200. Uncontaminated pipes shall be disposed of as Subcontractor's property.

4. Areas occupied by the wastewater retention basins, dikes, spillways, and temporary drainage ditches shall be restored and graded as specified in Section 02200. Membrane liner shall be disposed of as specified in Section 02050.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Separate measurement for payment will not be made for dewatering and drainage work specified in this Section.

4.2 PAYMENT

Separate payment will not be made for dewatering and drainage specified in this Section. Full compensation for furnishing all materials, equipment, labor, tools, accessories, incidentals, and for performing all work as specified in this Section including, but not limited to, the construction of additional lined and unlined temporary drainage ditches, check dams, temporary detention ponds or other facilities, the provision of pumps, sumps, piping, valves, meters, gages, other accessories and incidentals such as pipe supports, excavation and backfill of pipes and pipe supports, and the like, if required, will be considered to be included in the related applicable items of Work specified in the Subcontract.

END OF SECTION 02141

1
.

SECTION 02200

EARTHWORK

PART 1 - GENERAL

1.1 SCOPE

A. This Specification Section describes the requirements for earthwork related to the following:

1. Excavation of contaminated materials from the NC and UC sites.
2. Transportation of contaminated materials from the NC and UC sites to the BC site.
3. Construction of temporary and permanent features, including ditches, berms and swales.
4. Construction of access control area.
5. Construction of wastewater retention basins.
6. Construction of the Tailings Embankment:
 - a. Excavation of uncontaminated common materials.
 - b. Excavation of uncontaminated rock material.
 - c. Placement of excavated contaminated materials in the tailings embankment.
 - d. Placement of demolished materials and debris (resulting from work specified in Section 02050) in the tailings embankment.
 - e. Placement of asbestos and non-hazardous waste materials (resulting from work specified in Section 02081) in the tailings embankment.
 - f. Contaminated cleared vegetation resulting from site clearing specified in Section 02110.
 - g. Contaminated sediments from retention basins, dikes and ditches specified in Section 02141.
 - h. Contaminated vicinity property materials stockpiled by others.

- i. Placement of radon barrier cover.
- j. Placement of frost protection layer.
- 7. Finish grading of the sites, including restoration and regrading of areas occupied by temporary drainage ditches, wastewater retention basins and access control area.
- 8. Placement of materials in permanent stockpiles and spoil piles.
- 9. Furnishing and installing displacement monuments as shown on the Subcontract Drawings.
- B. Construction restraints are specified in Article SC-3 of the Special Conditions.

1.2 WORK NOT INCLUDED

- A. Earthwork related to the construction facilities except those specified in Article 1.1.A above is not included in this Section.
- B. Earthwork for temporary utility pipe trenches is not included in this Section.

1.3 RELATED WORK

- A. Section 00800 - Special Conditions
- B. Section 01300 - Submittals
- C. Section 01500 - Construction Facilities
- D. Section 01560 - Temporary Controls: Dust Control
- E. Section 01561 - Construction Cleaning
- F. Section 02050 - Demolition
- G. Section 02081 - Asbestos, Hazardous and Non-Hazardous Waste
- H. Section 02110 - Site Clearing
- I. Section 02141 - Dewatering and Drainage
- J. Section 02205 - Road Construction

K. Section 02278 - Erosion Protection

L. Section 02935 - Seeding

1.4 DEFINITIONS

A. Contaminated materials and uncontaminated materials are defined in Article SC-1 of the Special Conditions.

B. Excavation: Excavation shall include excavation of all materials including silt, clay, sand, gravel, talus, soft or disintegrated rock, boulders or detached pieces of solid rock and rippable rocks (see definition) but shall exclude rocks requiring drilling and blasting operations. Excavation shall be classified into the following categories:

1. Contaminated Materials Excavation.

2. Uncontaminated Materials Excavation.

C. Contaminated Materials Excavation: This excavation shall include removal of all materials encountered regardless of the nature of the materials encountered including rocks up to the size of 4 cubic yards. Soil investigations do not indicate presence of large rocks in the area. Should individual rock size larger than 4 cubic yards be encountered, the compensation to Subcontractor will be by a Change Order. Contaminated materials excavation shall include excavation of contaminated materials from tailings piles, slime pits, Area "A", access control area, temporary drainage ditches and dikes, the windblown and waterborne areas, and the wastewater retention basins.

D. Uncontaminated Materials Excavation: Uncontaminated materials excavation shall include excavations of uncontaminated materials from the various areas of the sites including, but not limited to, excavations for embankment, drainage ditches, retention basins, trenches, access control area, and finish grading. Uncontaminated materials excavation shall be classified into common excavation and rock excavation in accordance with the following designations and classifications:

1. Rock Excavation: Rock excavation shall include excavation by drilling and planing of material classified as rock and shall include the satisfactory removal of boulders 1/2 cubic yard or more in volume; solid rock; rock material that is in ledges, bedded deposits, and unstratified masses, which cannot be removed without systematic drilling and blasting; and conglomerate

deposits that are so firmly cemented as to possess the characteristics of solid rock that is impossible to remove without systematic drilling and blasting. The Subcontractor shall not proceed with the excavation of this material until the Contractor has classified the materials as common excavation or rock excavation and cross-sections are taken as required. Failure on the part of the Subcontractor to uncover such material, notify the Contractor, and allow ample time for classification and cross-sectioning of the undisturbed surface of such material will cause the forfeiture of the Subcontractor's right of claim to any classification or volume of material to be paid for other than that allowed by the Contractor for the areas of work in which such deposit occurs.

2. Common Excavation: Common excavation shall include the satisfactory removal of all such materials including rippable rocks (see definition below), not materials classified as rock excavation defined above.

E. Overexcavation: Overexcavation is defined as:

1. Excavation carried out beyond the lines and grades indicated on the Subcontract Drawings.
2. Excavation carried out beyond the limits authorized by the Contractor.

F. Slimes: Slimes are the fraction of the tailings consisting of silty clay, clay and clayey silt generally defined as containing 70 percent or more of minus No. 200 Sieve material.

G. Percent Maximum Density: Percent maximum density is the field dry density expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D698 and ASTM D1557, as applicable.

H. Topsoil: Topsoil for use as seed bed shall be free of any admixture of subsoil, foreign matter, toxic substances, and any material or substance that may be harmful to plant growth. Topsoil shall also include the top 6 inches of uncontaminated common material excavated at the BC site and placed in the designated stockpile.

I. Tailings Embankment: Tailings embankment shall consist of relocated contaminated materials, demolished materials and debris, vicinity property materials and the protective cover materials.

- J. Temporary Drainage Facilities: Temporary drainage facilities shall be all drainage ditches, berms and basins of temporary nature and shall include diversion, collection and interceptor ditches as shown on the Subcontract Drawings and other ditches required to accomplish the work.
- K. Subgrade Preparation: Subgrade preparation includes fine grading and compaction of excavations including drainage ditches, backfills, and embankments upon which bedding materials, riprap, or other features are to be constructed. Such surface preparation shall include mixing and manipulation, fine grading, and compaction of materials.
- L. Cover: Cover shall consist of the layers of following fill materials placed over the relocated contaminated materials in the tailings embankment as shown on the Subcontract Drawings:
1. Radon barrier material.
 2. Frost protection material.
 3. Bedding material and riprap material.
- M. Demolished Materials and Debris: Demolished materials and debris resulting from the demolition work are specified under Section 02050.
- N. Finish grading of the site shall include excavation, fill of the various areas of the sites, including backfill for final grading, retention basins, spillways, temporary drainage ditches, spoil piles and permanent stockpiles as shown on the Subcontract Drawings.
- O. Soil-like materials have a maximum particle size of 6 inches and more than 40 percent passing the number 4 sieve.
- P. Rock-like materials have a maximum particle size of 12 inches and less than 40 percent passing the number 4 sieve.
- Q. Frozen Material or Subgrade or Foundation: Material or new subgrade or foundation that has a temperature below freezing and generally contains a visible amount of ice.
- R. Rippable Rock: Rippable rock is defined as mineral matter in place and of such hardness and texture that it can be effectively loosened or broken down by ripping in a single pass with a late model tractor-mounted hydraulic ripper equipped with one digging point of standard manufacturer's design adequately sized for use with and propelled by a crawler-type tractor Caterpillar Model D10N or equal, operating in low gear; or in areas where the use of the

ripper described above is impracticable, rippable rock is defined as mineral material of such hardness and texture that it can be loosened or broken down by a 6-pound drifting pick. The drifting pick shall be Class D, Federal Specification GGG-H-506D, with handle not less than 34 inches in length.

- S. Permanent Spoil Pile: Permanent spoil pile at the BC site consisting of excess materials from required excavations. Spoil pile material shall be considered common fill.

1.5 APPLICABLE PUBLICATIONS

- A. The Publications listed below form a part of this Specification to the extent referenced. The Publications are referred to in the text by the basic designation only:

1. American Society for Testing and Materials (ASTM):

D422-63	Standard Test Method for Particle-Size Analysis of Soils (R1990)
D698-90	Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort
D1140-92	Standard Test Method for Amount of Material in Soils Finer than the No. 200 (75-mm) Sieve
D1556-90	Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method
D1557-91	Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft ³ (2,700 kN-m/m ³))
D2167-84	Standard Test Method for Density and Unit Weight of Soil in Place by the Rubber-Balloon Method (R1990)
D2216-92	Standard Test Method for Laboratory Determination of Water (Moisture) Content of Soil and Rock
D2487-92	Standard Classification of Soils for Engineering Purposes (Unified Soil Classification System)

D2922-91 Standard Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)

D3017-88 Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)

D4643-87 Standard Test Method for Determination of Water (Moisture) Content of Soil by the Microwave Oven Method

2. Blasting practices shall generally be in accordance with the "Blasters Handbook" - 16th Edition by E. I. du Pont de Nemours and Co. (INC) of Wilmington, Delaware 19898.

3. U.S. Code of Federal Regulations (CFR):

40 CFR 61, Subpart T

4. U.S. Federal Specifications (FS):

GGG-H-506D Hoe, Mattock and Pick
Int AMD 1

1.6 PERMITS AND APPLICABLE LAWS

A. All required Federal, State, and local permits for blasting and explosives shall be obtained and paid for by the Subcontractor. Copies of such permits shall be furnished to the Contractor before any blasting operations are started.

B. All blasters and blasting foremen shall be properly qualified and licensed in accordance with the applicable laws and regulations of Federal, State, and local governments.

C. All transportation and storage of explosives shall be in accordance with the applicable laws and regulations of Federal, State and local governments.

1.7 QUALITY ASSURANCE

A. The Contractor will take soil samples and perform moisture, density, gradation and other tests to ascertain that the work is being performed in compliance with these Specifications. Samples may be taken at the place of excavation, stockpiles, or on the fill itself. The Contractor will conduct the density and other tests on the fill and related laboratory testing as frequently as the Contractor considers necessary.

The Subcontractor shall remove surface material and render assistance as necessary to enable sampling and testing.

B. Methods of Sampling and Testing:

1. In-Place Density: ASTM D1556, D2167, or D2922
2. Particle Size Analysis: ASTM D422
3. Percent Passing No. 200 Sieve: ASTM D1140
4. Moisture Content: ASTM D2216, D3017 or D4643
5. Laboratory Moisture-Density Relations: ASTM D698, ASTM D1557
6. Soil Classification: ASTM D2487
7. In-Place Moisture Content: ASTM D3017 or ASTM D4643

C. Suitability of Materials: The suitability of all materials for foundations and backfill will be determined by the Contractor. Fill material shall be approved material from borrow areas or required excavations.

D. The Subcontractor shall make his own determination of any processing that may be required and shall perform testing as required to ensure that the materials meet the Specification requirements.

E. The Contractor may direct that inspection trenches or test pits be cut into fills to determine that the Specifications have been met. Such trenches or pits will be of limited depth and size, and shall be backfilled with the material excavated therefrom, or other fill material meeting the requirements for the zones cut into. Backfill shall be compacted to a density at least equal to that of the contiguous fill.

F. When the Contractor directs inspection trenches or test pits to be excavated into fills and materials are found to meet all Specification requirements, the excavation and refilling shall be paid for as additional work pursuant to the applicable provisions of the General Conditions. Inspection trenches or test pits, and the refilling of the same, shall be at the Subcontractor's expense when it is found that the materials do not meet the Specification requirements.

G. Tolerances: See Specification Section 01052, Article 1.7

1.8 PROTECTION

A. The Subcontractor shall protect the following:

1. Trees, shrubs and other features outside the areas of construction.
2. Benchmarks and monuments, existing structures, fences, walks, pavings, curbs, etc. from equipment and vehicular traffic.
3. Above and below ground utilities not specified for removal.
4. Excavations from cave-in by shoring, bracing, sheet-piling, underpinning or by other methods.
5. Perimeter of excavation top to prevent surface water runoff into excavation.
6. Monitor wells not to be abandoned.
7. Petroglyphs and other archaeological areas identified by the Contractor or encountered during the work.
8. Finished work including displacement monuments.
9. Existing features not part of this Subcontract, e.g., existing roads or existing wells.

1.9 SUBMITTALS

- A. General submittal requirements are specified in Section 01300.
- B. At least 30 days before opening borrow areas, the Subcontractor shall submit a mining plan for each separate borrow area. The plan shall include method of stripping and processing of materials, excavation plan, and a site restoration plan.
- C. At least 30 days before commencing blasting operations, the Subcontractor shall submit to the Contractor for review a detailed blasting plan covering the area to be blasted. The blasting plan shall contain complete hole layouts, proposed loading, delays and all information required by this Specification. The Contractor may require changes in the blasting plan if the results of blasting do not meet Subcontract requirements.

- D. All changes in the blasting plan shall be submitted for approval at least 48 hours prior to the time of the proposed changes.
- E. At least 48 hours before blasting within one-quarter mile of a stream course, the Subcontractor shall submit for approval a plan showing all details of his proposed blasting operation and the scheduled time for the blast.
- F. The Contractor's review of the Subcontractor's proposed blasting procedures shall not be construed to relieve the Subcontractor of his responsibility to protect existing facilities not to be demolished. Any damage done by the Subcontractor's operations shall be repaired at Subcontractor's expense.

1.10 SAFETY PROVISIONS FOR BLASTING

- A. The Subcontractor shall provide and operate at all times an instrument for the detection of approaching electrical storms, including an automatic alarm such as a Litton TSM/C.
- B. Electrical Storms: No explosive material shall be handled, transported or in any way made use of during any period of electrical storm or lightning or other electrical phenomenon. In the event that any such condition should appear imminent or occur, or if some known leakage of electricity should occur in the neighborhood of, or in, the work, while the transport, handling, making-up or charging or other use of explosives is being effected, then the work shall be evacuated and abandoned completely until at least thirty minutes after the condition has ceased or the leakage stopped.
- C. Detonating Explosive Charges:
 - 1. Only approved exploding devices shall be used for detonating charges. Under no circumstances are lighting and power cables to be used for detonating. All pipes, ducts, track, and other metal shall be properly grounded.
 - 2. An adequate warning system shall be provided by the Subcontractor to ensure that all personnel, staff, visitors and anyone else are at a safe distance before blasting takes place.
 - 3. No radio transmitter shall be operated within 75 feet of the area where electric blasting operations are in progress.

4. No naked lights or sparks are allowed anywhere in the vicinity of blasting operations on the surface.
5. Where detonating is carried out electrically the Subcontractor shall take every precaution necessary to prevent premature explosions and misfires. Before connection of the detonating wires to the detonating cable the round shall be tested for electrical continuity in an approved manner with an approved testing device or meter. In the event that this testing should show a lack of continuity then the round shall be retested leaving out one detonator at a time until the fault is identified. Should this procedure identify a faulty detonator then stemming shall be carefully removed from the hole and an additional primer inserted and wired into the circuit in place of the defective one. No attempt shall be made to draw a defective detonator or primer. On satisfactory completion of the circuit all workers other than those immediately necessary shall be withdrawn to a safe distance before detonating wires are connected to the detonating cable, and the connection of the detonating cable to the detonator shall be the last operation.
6. Where detonating is carried out by electricity, following a blast, before any person returns to the work place affected by the operation,
 - a. The detonating cables shall be withdrawn from the battery, blasting machine or other source of electricity and shall be short circuited.
 - b. The blasting switch shall be locked in the open position.
7. Blasting cables and wires shall be clearly distinguishable from other cables and wires and shall only be used for blasting.

D. Misfires of Explosive Charges:

1. Should a misfire occur, then the Subcontractor shall warn all persons affected, and no persons other than those required shall enter the workings until the charge has exploded or, in the case of electrical detonating, an interval of at least twenty minutes has elapsed after operation of the exploder.
2. A misfired detonator may only be removed from the face by means of approved apparatus which permits such an operation to be carried out with absolute safety. Under

no circumstance shall charges which have misfired be otherwise tampered with. Should it prove impossible to extract the charge with safety, then the Contractor may authorize the Subcontractor to explode the charge by sympathetic detonation, the greatest care being taken to ensure that no new hole is drilled to intersect an old one or that the unexploded charge is in any other way affected. After the second shot is detonated, the search shall be made for the unexploded charge.

PART 2 - PRODUCTS

2.1 EXPLOSIVES

A record shall be maintained by the Subcontractor for storage and withdrawal of explosive stocks and detonators. The inventory record shall be subject to inspection at all times. The Subcontractor shall provide such reasonable and adequate protective facilities as may be necessary to prevent loss and theft of explosives and to minimize hazards of subversive action or sabotage. Loss or theft of explosives shall be reported to the Contractor immediately. Overnight storage of explosives and detonators outside of the magazine will not be permitted. Only qualified personnel shall be permitted to handle explosives.

2.2 UNCONTAMINATED FILL MATERIALS

A. General:

1. Fill materials shall be obtained from the required excavations to the extent available. Where the excavated materials do not meet the requirements of the Specifications or they are not available, the materials shall be furnished from uncontaminated areas within the UC, NC and BC sites or from other approved borrow areas selected by the Subcontractor and approved by the Contractor. Excavated materials may be temporarily stockpiled within the site boundaries, as directed by the Contractor, for future use.
2. The Subcontractor shall make his own determination of any processing that may be required, and shall perform testing as required to meet the Specifications for the various construction materials.

3. The Subcontractor shall be responsible for obtaining required permits and approvals for Subcontractor-selected borrow areas in accordance with the provisions of Article SC-11 of the Special Conditions. Contractor approval of a borrow area does not indicate that all material within that area meets the Specification requirements specified herein or that sufficient quantities of acceptable materials exist.
 - a. Submittals to the Contractor for approval of sources proposed for use by the Subcontractor shall include boring logs, borrow area maps and supporting laboratory test data. The Subcontractor also shall provide evidence of availability, right of access to private property including access by the Contractor for sampling and testing, and his plan for hauling the materials to the site. Submittals for approval of sources for uncontaminated fill materials shall be received by the Contractor at least 30 days (60 days for radon barrier materials) before use of the material at the site. The Contractor may perform additional tests to determine if the materials meet the requirements specified herein.
 - b. Approval will be based on evidence of compliance with the requirements specified herein and on verification by the Subcontractor that the volume of materials available is sufficient for construction requirements.
4. Gradations: Gradations specified shall be as determined after delivery to the site, except where normal compaction operations reduce materials to acceptable sizes, in which case in-place gradations shall be acceptable.

B. Uncontaminated Fill Material Requirements:

1. General Fill: Uncontaminated fill materials for common or general fill and imported fill shall conform to the following requirements. All references to "uncontaminated fill" or "uncontaminated fill materials" shall mean "uncontaminated common/general fill" or "uncontaminated common/general fill materials".
 - a. Uncontaminated fill materials shall not contain more than 5 percent organic material, by volume, or other deleterious substances.
 - b. Maximum particle size shall not be greater than the compacted lift thickness in any dimension, except that for fill areas under pavement locations,

maximum stone dimension allowed in the upper 18 inches of the fill shall be 4 inches. Individual large stones shall be distributed within the fill materials to provide visual void-free mass, and be able to meet the requirements of Article 3.8.A. Larger stones may be utilized in initial backfill in the lower layers of finish grading of the site.

[2. Radon Barrier Materials: Radon barrier materials shall conform to the following requirements:

- a. Radon barrier materials shall be selectively excavated, fine-grained uncontaminated soils obtained from required excavation for the tailings embankment at the Burro Canyon Site.
- b. Radon barrier materials shall consist of soils with gradations conforming to the following limits:

U.S. Standard Sieve Size (Square Openings)	Percent Passing (by Weight)
1-inch	100
No. 10	90-100
No. 40	75-100
No. 200	50-100

Radon barrier material containing less than 50 percent passing No. 200 sieve may be processed or mixed with material to meet the minimum passing No. 200 sieve requirement. Percent passing No. 200 sieve shall be determined in accordance with the requirements of ASTM D1140. Compliance with these Specifications will be determined by the Contractor.

- c. Radon barrier material shall not contain more than five percent organic matter, by volume, or other deleterious substances.
- d. Radon barrier material shall be processed to reduce clod sizes to 1-inch or smaller.
- e. Selective excavation and stockpiling of radon barrier material shall be performed in a manner that avoids the inclusion of more than 5 percent by weight of rock particles from rock underlying borrow soils. Rock particles shall mean pieces of rock which do not remold when moistened, as determined by the Contractor.]*

* P.I.D. 11-S-03

Document No. 3885-SRK-S-01-02429-03

Issued for Construction-Revision 1

Earthwork

02200 - 14

WP51

022195

SRK

- C. Frost protection material shall be obtained from required excavations within the BC site area and shall conform to the common fill requirements.

2.3 CONTAMINATED FILL MATERIALS

- A. Contaminated Fill Materials: Contaminated materials defined in Article SC-1 of the Special Conditions resulting from the clearing, stripping and excavation operations in contaminated areas. These materials shall include materials excavated from tailings piles, Area "A" windblown and waterborne areas, contaminated sediments from drainage ditches and wastewater retention basins, recirculation pond, and any other areas designated by the Contractor including vicinity properties and demolished materials and debris.
- B. Demolished Materials and Debris: Demolished materials and debris resulting from work specified in Section 02050 shall be considered as contaminated materials for disposal purposes.
- C. Asbestos and Non-Hazardous Waste Materials: Asbestos and non-hazardous waste materials resulting from work specified in Section 02081.
- D. Vicinity Property Materials: Excavated contaminated materials resulting from cleanup of vicinity properties will be hauled to the site and stockpiled on the tailings embankment by others. The Subcontractor shall make provisions in his schedule and work plan for placement and compaction of vicinity properties materials stockpiled in the tailings embankment by others. The Subcontractor shall make allowances for decontamination of vicinity property subcontractor vehicles.

PART 3 - EXECUTION

3.1 PROTECTION OF EXPOSED SURFACES

- A. During seasonal shutdowns and during other periods of prolonged exposure (more than six weeks) of excavated or filled areas, the Subcontractor shall provide labor, materials and equipment, as required by the Contractor to maintain and protect exposed surfaces of uncontaminated and contaminated materials against wind erosion and excessive stormwater erosion. Prior to the application of protective erosion control measures, the exposed surfaces shall be sloped to drain and compacted with a smooth drum roller to

eliminate ruts and ridges formed by construction equipment. Unless otherwise approved by the Contractor, acceptable methods of erosion protection are as follows:

1. Spraying with Water containing Chemical Additives: Acceptable chemical additives are "Soil Seal Concentrate" as manufactured by Soil Stabilization Products Company of Merced, California; CPB-12 as manufactured by Wen-Don Corporation, 206 West 2nd South, Price, Utah 84501; "Soil-Sement" as manufactured by Midwest Industrial Supply, Inc. of Canton, Ohio; or approved equal. Mixing and application shall be in accordance with the manufacturer's recommendations, or
2. Covering exposed surfaces with geotextile fabric such as "Supac" as manufactured by Phillips Fibers Corporation of Sacramento, California, or approved equal. Handling and installation shall be as recommended by the manufacturer of the product.

B. Contaminated Materials:

1. During earthwork operations, the ground surface and the surface of contaminated materials in the embankment shall be graded to avoid any ponding of storm water on the surface both during shutdowns and during on-going operations.
2. Protective Soil Cover During Winter Shutdown: During winter shutdown a protective soil cover shall be placed over contaminated materials in the disposal cell. A minimum of 3 inches of compacted common fill shall be placed and rolled by a smooth drum roller or other equipment approved by the Contractor. Materials for the temporary soil cover shall meet the requirements for common fill or other materials approved by the Contractor, except that quality control shall be as determined by the Contractor.

- C. Following a seasonal shutdown or period of prolonged exposure of more than six weeks, the Contractor will verify by density tests, that the last lift of materials previously placed and accepted by tests have been maintained at the applicable minimum specified density. Verification by density tests will be performed at frequencies commensurate with those specified in Article 3.6.B.1 of this Section. Materials failing to meet the specified density requirements shall be removed or reworked to satisfy the minimum specified density requirements at no additional cost to the Contractor.

3.2 EARTHWORK - GENERAL

A. Preparation:

1. Required lines, levels, contours and datum shall be identified before the start of earthwork operations.
2. The Subcontractor shall verify the existing above ground and underground utilities, identify them, and notify the Contractor immediately of his finding, if any, for appropriate action by the Contractor.
3. Clearing and stripping shall be as specified in Section 02110.

B. Dewatering and Drainage: Prior to commencement of earthwork operations, the Subcontractor shall verify that the dewatering and drainage facilities are constructed and operational in accordance with the requirements of Section 02141.

C. In order to avoid cross-contamination of uncontaminated material, the contaminated and uncontaminated materials shall be kept separated during earthwork operations. This may include decontamination of equipment used on contaminated material prior to use on uncontaminated material within the controlled area. Stockpiles of contaminated materials shall be placed on contaminated areas only and the drainage collected in the wastewater retention basin.

D. Earthwork shall conform to the lines and grades indicated on the Subcontract Drawings and as specified in this Section.

E. The excavated uncontaminated materials, where practicable, shall be used as fill in various areas of the sites including the construction of retention basin dikes, lined ditch fills, backfill, and fill for the final grading of the sites, and for construction of the tailings embankment and frost protection barrier, as required. Uncontaminated excavated material not utilized in fills may be stockpiled.

F. Temporary drainage ditches shall be constructed and maintained to provide drainage during construction.

3.3 EXCAVATION

A. General:

1. Excavation shall be carried out to reach the lines and grades indicated on the Subcontract Drawings or specified

herein, or, in the case of contaminated materials, as required by the Contractor's Health Physics Personnel.

2. At all times, the Subcontractor shall conduct his operations in such a manner as to prevent free standing water and contamination of uncontaminated materials. The Subcontractor shall, as a minimum, take the following measures to safeguard against such problems:
 - a. Water leaving contaminated excavation area or contaminated area otherwise disturbed by construction activities shall be routed into the retention basin as specified in Section 02141.
 - b. Exposed surfaces of contaminated and uncontaminated materials excavations shall be protected from erosion as specified in Article 3.1 above.
3. The Subcontractor shall remove all excavated material from the excavation site and dispose of it in fills required at the site or use it for other purposes, as approved.
4. Unless otherwise indicated on the Subcontract Drawings, the Subcontractor shall remove all excavated material from the excavation site and dispose of it in fills or the permanent spoil pile.
5. Unsuitable or low density subgrade material not readily capable of in-place compaction as determined by the Contractor shall be excavated as directed by the Contractor and disposed of as specified in Article 3.4.
6. Adequate working space for safety of personnel shall be provided within the limits of the excavation.
7. Except as otherwise noted, care shall be exercised to preserve the material below and beyond the lines of all excavation. Where excavation is carried below grade, the Subcontractor shall backfill to the required grade or to indicated invert grade, as specified, and recompact the backfill to a minimum of 90 percent of the maximum dry density as determined by ASTM D698.
8. Excavation for the convenience of the Subcontractor shall conform to the limits approved by the Contractor and shall be at no additional expense to the Contractor.
9. Excavated material shall be placed at sufficient distance from the edge of excavations to prevent cave-ins or bank slides. Slopes of excavated earth cuts and stockpiles

shall not be steeper than 2(H) to 1(V) unless indicated otherwise on the Subcontract Drawings.

10. Adequate working space for safety of personnel shall be provided within the limits of the excavation. Extra precautions shall be taken to protect workers when excavating near steep rock faces. Boulders or loose rock on the rock face shall be removed as they become exposed.

B. Contaminated Materials Excavation:

1. Contaminated materials excavation shall include excavation of (a) contaminated materials from the tailings piles at the UC and NC sites, (b) windblown and waterborne off-pile areas including Area "A" at the UC site, and (c) materials from retention basins, ditches and dikes. The Subcontractor shall minimize the open excavation area of contaminated materials at any time during excavation work. The Subcontractor shall operate from one or two sides at one time, progressing uniformly to opposite sides for completion, unless directed otherwise by the Site Manager. Contaminated materials shall be excavated to the depths indicated on the Subcontract Drawings, and as required by the Contractor, and placed in the proper part of the tailings embankment. The contaminated material will be excavated generally in priority of its placement in the embankment to minimize rehandling and stockpiling. Excavation shall be carried out to the limits and grades required by the Contractor. Rock requiring drilling and blasting operations shall not be included in this excavation.
2. The Subcontractor shall remove contaminated material from the rock surface. The Subcontractor shall employ whatever methods are necessary in order to achieve an acceptable rock finish, and remove windblown/waterborne contamination from the rock surface and from within rock crevices including hand cleaning and washing out with water.
3. During the excavation operation, tests will be performed by the Contractor to determine the level of radioactive contamination of the material to be excavated in accordance with the requirement of Article SC-3B.

C. Uncontaminated Materials Excavation:

1. General: Uncontaminated materials excavation shall include excavations of uncontaminated materials from the various areas of the site. The excavated materials shall be used as fill in various areas of the sites including

construction of berms, dikes, common fill, roadway fill, structure fill, backfill, and fill for final grading of site, as required. Uncontaminated excavated material may be stockpiled for later use.

2. Rock Excavation:

- a. The Subcontractor shall perform required rock excavation to the limits shown on the Subcontract Drawings or as directed by the Contractor.
- b. Care shall be exercised to avoid excessive overbreak beyond or below grade lines of excavation.
- c. Blasting methods and procedures shall be such that, upon completion of the excavation, all rock surfaces will be sound and relatively uniform. Explosives shall be of such quantity and power and shall be used in a manner that will minimize opening of seams and disturbing of rock outside the prescribed limits of excavation. As the excavation approaches its final limits, the depths of holes for blasting and the quantity of explosives used for each hole shall be reduced so that the rock underlying or adjacent to the final limits is not shattered or otherwise disturbed.
- d. The Subcontractor shall remove all shattered material and debris from excavation.
- e. Excavated rock materials shall be used as fill, where required, or may be stockpiled in approved locations for later placement as fill.

3. Temporary Drainage Ditches:

- a. Drainage ditches shall be cut accurately to the cross sections and grades where indicated. All roots, stumps, rock, and foreign matter in the sides and bottom of ditches shall be trimmed and dressed or removed to conform to the slope, grade, and shape of section indicated. Care shall be taken not to excavate ditches below the grades indicated. Excessive ditch excavation shall be backfilled to grade with compacted material.
- b. Ditches shall be located as shown on the Subcontract Drawings to collect and transport storm runoff, wastewater and water-borne contaminated material to the retention basins during construction, and to divert uncontaminated water from the site.

- c. Ditches shall be fine graded, compacted, and maintained to provide drainage during construction.
- 4. Off-site Borrow Area Excavation for Common Fill:
 - a. Where common fill materials are not available from onsite excavations, such materials shall be obtained from approved offsite borrow areas or other approved sources.
 - b. At least 15 days in advance of placing these materials, the Subcontractor shall submit test results or certificates from the supplier, characterizing the proposed materials, for approval by the Contractor. The Contractor or a soils testing laboratory employed by the Contractor may perform additional testing.
 - c. Only upon approval from the Contractor, such materials shall be furnished and placed in the required fills.
- 5. Wastewater Retention Basin Excavation:
 - a. The wastewater retention basins shall be constructed to the lines and grades shown on the Subcontract Drawings. Contaminated materials shall first be excavated and stockpiled within the area as shown on the Subcontract Drawings, then the excavation and fill for the retention basin shall be accomplished.
 - b. The retention basins shall be demolished when no longer required and the area graded as shown on the Subcontract Drawings and as specified in this Section.
 - c. Construction of the retention basin shall also conform to the requirements specified in Section 02141.
- 6. Borrow Area Excavation:
 - a. Borrow areas shall meet all permit and negotiated requirements as required by the Contractor.
 - b. Necessary clearing, grubbing, and disposal of debris shall be performed by the Subcontractor as incidental operations to the borrow excavation.
 - c. The required material shall be excavated after stripping the topsoil. The topsoil and material not

meeting the Subcontract requirements shall be stockpiled for site grading and restoration.

[Text Deleted]*

7. Permanent Excavation for Final Site Grading: Excavations for final site grading shall be true to line and grade. Any erosion which occurs before placing erosion protection materials or revegetation shall be repaired with compacted backfill. All such repairs shall be at Subcontractor's expense and shall not be included in pay quantities, unless otherwise shown on the Subcontract Drawings.

3.4 DISPOSAL OF EXCAVATED MATERIALS

A. Contaminated Materials: All excavated contaminated materials shall be used as contaminated material fill or stockpiled in the designated areas shown on the Subcontract Drawings until placed in the tailings embankment. Contaminated materials will be placed in the tailings embankment by priority generally as indicated in Article 3.5.B.6. Radiological monitoring of contaminated materials or construction expediency may change this priority as directed by the Contractor.

B. Uncontaminated Materials:

1. Uncontaminated materials excavated from the site, including excavations for trenches, drainage ditches, retention basins, decontamination pads, and the like, which do not classify as contaminated materials, shall be used as uncontaminated material fill for the construction of various features, placed in the permanent spoil pile, or stockpiled for later use as specified in this Section and required by the Contractor.
2. Where used in fills, such material shall be transported directly from the excavation and placed in its final position in such fills whenever possible. If required by the Subcontractor's schedule, the material may be placed temporarily in stockpiles at approved locations. Material in stockpiles shall be protected from contamination of any kind that would render it unsuitable for use in fills.

* P.I.D. 11-S-03

Document No. 3885-SRK-S-01-02429-03

Issued for Construction-Revision 1

Earthwork

02200 - 22

WP51

022195

SRK

3. Excess excavated uncontaminated materials generated during the Work shall be temporarily stockpiled on site for later use or in the designated permanent spoil pile as required by the Contractor.
 4. All operations in the permanent spoil pile and stockpile areas throughout the Work shall be in strict conformity with the requirements of this Section. The Subcontractor shall ensure that silty water from the stockpile areas does not enter nearby waterways. If required, temporary berms, holding ponds, temporary ditches and water containment facilities shall be constructed by the Subcontractor.
 5. Uncontaminated Common and Rock Materials: See Article 3.3.C.1 and 2.
 6. Excess uncontaminated materials shall be disposed of on site or in the spoil area shown on the Subcontract Drawings as approved by the Contractor.
 - [7. Excavated material for the tailings embankment at the Burro Canyon Site, passing the gradation requirements specified in Article 2.2.B.2, shall be stockpiled at the designated area for radon barrier material. Excavated material from the tailings embankment at the Burro Canyon Site not passing the gradation requirements or otherwise processed to meet requirements for radon barrier material shall be stockpiled separately and designated for frost barrier or general fill material.]*
- C. Garbage, refuse, debris, oil, and any waste material which is harmful to the environment or offensive to the area shall be removed from the job site and disposed of offsite in a manner approved by the Contractor.

3.5 FILL CONSTRUCTION

A. General Requirements:

1. Clearing and Stripping: Conform to Section 02110.
2. Fill materials shall be placed and compacted to the lines and grades shown on the Subcontract Drawings or as required by the Contractor.

* P.I.D. 11-S-03

Document No. 3885-SRK-S-01-02429-03

Issued for Construction-Revision 1

Earthwork

02200 - 23

WP51

022195

SRK

3. Prior to placing uncontaminated fill materials, the subgrade will be radiologically surveyed by the Contractor to confirm that EPA standards have been met. These radiological surveys may cause delays to backfill operations of up to seven working days. The Subcontractor shall plan his work accordingly.
4. After the radon barrier has been placed and prior to placement of frost protection, the Contractor will perform radon flux measurements according to Environmental Protection Agency regulations found in 40 CFR 61, Subpart T. Measurements can generally be completed within 48 hours if weather conditions permit. When valid radon flux measurement data have been obtained for an area of the fill, the frost protection materials may be placed over that area. The Subcontractor shall plan his work accordingly.
5. If any portion of the materials placed as fill does not meet the specified requirements, the Subcontractor shall remove such material and replace it with fill materials meeting the specification at no additional cost to the Contractor.
6. Constructed fills shall be maintained to meet the requirements of this Specification until final completion and acceptance of the Work. This shall include all measures to prevent erosion or contamination during construction, including contamination by radioactive material. During seasonal or other extended shutdowns, all exposed surfaces shall be protected with special treatments specified in Article 3.1 above.

B. Placing Requirements:

1. Prior to placement of materials, the in-place density of the Subgrade shall be as specified in Article 3.8. Subgrade preparation, where required, shall be as specified in Article 3.7.
2. No materials shall be placed on any portion of the subgrade or against or upon any structure until consent to place such fill has been obtained from the Contractor.
3. Subgrade and fill materials may require moisture conditioning (wetting or drying) prior to compaction.
4. Fill materials shall be placed in continuous and approximately horizontal layers for their full length and width unless otherwise specified or specifically permitted by the Contractor.

5. The method of dumping and spreading the materials shall ensure uniform distribution of the material.
6. The following sequence shall be followed in placing materials in the tailings embankment:
 - a. Contaminated materials from the NC site and Area A of the UC site. [Text Deleted]*
 - b. Demolition debris.
 - c. UC site tailings.
 - d. UC site windblown/waterborne and subtailings contaminated materials.
 - e. Vicinity property material as delivered to the site and as directed by the Contractor.
 - f. Contaminated materials from all temporary facilities.
 - g. Radon barrier material.
 - h. Frost protection material.
 - i. Bedding material.
 - j. Riprap protection.
7. Loose thickness of each lift of materials shall not be greater than that required to achieve the specified compaction for the entire lift. For material containing particles having a maximum dimension of less than 10 inches the loose lift thickness shall not exceed 12 inches. For material containing particles greater than 10 inches, the loose lift shall be kept to the minimum constructible thickness, as approved by the Contractor. Oversize material shall be placed in accordance with Article 3.5.B.10 and graded to avoid ponding of surface water. Oversize material shall be compacted in accordance with Article 3.5.C.7.
8. Unless otherwise indicated, fill materials shall be placed to a grade no flatter than 2 percent to facilitate drainage of water. In areas where ponding cannot be prevented or ponding has occurred and fill is required to be placed, placing shall begin only after the area is

* P.I.D. 11-S-07

Document No. 3885-SRK-S-01-02429-03

Issued for Construction-Revision 1

Earthwork

02200 - 25

WP51

022195

SRK

dewatered and permission to place is obtained from the Contractor.

9. Materials shall not be placed on frozen subgrade nor shall frozen material be used as fill.
10. Disposing of bulky materials shall be done with care to minimize the volume of voids created in the disposal embankment fill. Pieces of wood, concrete, and steel members shall be cut or broken up as specified in Section 02050, and placed to avoid nesting. Such bulky materials shall be placed in the lower lifts of the tailings embankment as determined by the Contractor. Bulky materials from vicinity properties materials stockpile and from the demolition of temporary facilities at the end of construction shall be placed as low as practicable within the embankment.
11. When no longer needed for control of contamination, as determined by the Contractor, the temporary drainage ditches, retention basin, sumps, and the like shall be removed and the area restored and finish graded as shown on the Subcontract Drawings.

C. Compaction Requirements:

1. Each lift of fill materials shall be compacted to at least the minimum density specified in Article 3.8.
2. During compaction, the moisture content of material shall be maintained within the range specified in Article 3.8.D to achieve specified density. Uniform moisture distribution shall be obtained by disking, blading, or other methods approved by the Contractor prior to compaction of a lift.
3. If the surface of the prepared foundation or the rolled surface of any lift of fill is too wet for proper compaction of the lift of fill material to be placed thereon, it shall be removed, allowed to dry, mixed with dry material, or worked with harrow, scarifier, or other suitable equipment to reduce the water content to the required amount, and then re-compacted before the next succeeding layer of fill is placed.
4. If the surface of the prepared foundation or the rolled surface of any lift of fill is too dry or too smooth to bond properly with the lift of material to be placed thereon, it shall be scarified and moistened by sprinkling to the acceptable moisture content prior to placement of the next lift of fill.

5. Fill compacted to densities lower than the specified minimum density or at moisture contents outside the specified acceptable range of moisture content shall be reworked to meet the density and moisture requirements or removed and replaced by acceptable fill compacted to meet these requirements at no additional cost to the Contractor.
6. Uncontaminated fill material in the permanent stockpile areas shall be compacted by routing of hauling and spreading equipment units. Lift thickness before compaction shall not exceed one foot.
7. Compaction of fill with more than 30 percent retained on a 3/4-inch standard sieve:
 - a. Prior to compaction, materials shall be moisture conditioned as approved by the Contractor. If required, moisture addition shall be limited to the amount of water required to lubricate rock particles. When adding moisture, care shall be taken not to increase the moisture content of underlying soils.
 - b. Compaction shall be accomplished by any of the following combinations of passes and equipment, or approved equal combination:

<u>Equipment</u>	<u>Minimum No. of Passes for 90% Compaction</u>	<u>Minimum No. of Passes for 95% Compaction</u>
BOMAG Vibratory Roller Model 213D	2	4
CAT CS 553 Vibratory Roller	2	4
CAT Compactor Model 825C	2	4
Raygo Vibratory Roller Model 400A	2	4
Track-Type Tractor with Ground Pressure of at Least 9.8 psi	3	5
Towed 5x5 Sheepsfoot, Fully Ballasted	3	4

- c. Materials shall not be subject to requirements of Article 3.8.A.
- 8. Compaction of frost protection materials shall be accomplished by the use of tamping-foot rollers. The length of the feet on the tamping foot rollers shall not be less than 5 inches.
- 9. The top lift of the radon barrier and the frost protection layer shall be compacted with the tamping foot roller to a smooth surface as approved by the Contractor within the specified tolerances while the moisture content is within the specified limits.

3.6 FIELD QUALITY CONTROL

- A. General: The Contractor will take samples and perform tests throughout the construction period, and the Subcontractor shall cooperate in providing access for the Contractor to areas where testing is to be performed and shall schedule his placing to avoid interference with the testing operations.
- B. Tests: The Contractor will perform the following tests on a regular basis.
 - 1. In-place density and moisture content tests for compacted materials where density is specified will be as follows:
 - a. A minimum of one test per 1000 cubic yards of compactable contaminated and uncontaminated materials, excluding radon barrier material.
 - b. A minimum of one test per 500 cubic yards of radon barrier materials placed.
 - c. At least two tests for each day of material placement in excess of 150 cubic yards for each material.
 - d. A minimum of one test per lift and one test per full shift of operations.
 - e. Foundation and Subgrade: Prior to placing the first layer of material on the foundation, the subgrade will be inspected to assure that it has no sign of deterioration due to frost action, erosion due to rainwater, rutting, areas of subsidence, or drying out of the surface. The inspection shall verify that the foundation surface has been moistened, but there is no standing water on the surface and that the foundation surface of cohesive soils has been

scarified or penetrated to ensure proper bonding of overlying material. Unacceptable surface material shall be either removed or excavated and recompacted to Specification requirements.

- f. A minimum of one test per 30,000 sq.ft. on the surface of previously placed materials after a seasonal shutdown or period of prolonged exposure and prior to placing additional materials.
- 2. In-place density tests on areas of soil subgrade at a minimum of one test per 5,000 square yards of the surface area after compaction as stated in Article 3.7.B.
- 3. Gradation tests will be as follows:
 - a. A minimum of one test per 2000 cubic yards of contaminated and uncontaminated materials placed excluding radon barrier materials.
 - b. A minimum of one test per 1000 cubic yards of radon barrier placed.
- 4. The placing and compaction of temporary stockpiles will be subject to the approval of the Contractor.

3.7 SUBGRADE PREPARATION

- A. Subgrade Preparation: Subgrade preparation includes fine grading and compaction of excavations, backfills, embankments (including stockpiles) upon which pavement, surfacing, base, subbase, bedding materials, and riprap or other structures are constructed. Areas excavated to bedrock or to cobbles/gravels do not require subgrade preparation.
- B. Where required for compaction, the entire surface of the subgrade shall be plowed, harrowed, and mixed to a depth of at least 6 inches. Compaction shall be carried out for the full area below finished subgrade to at least the density specified in Article 3.8 below. Soft spots developed during working shall be corrected.
- C. Subgrade for the tailings embankment shall be excavated to the lines indicated on the Subcontract Drawings. Loose material shall be removed to the extent practicable as determined by the Contractor. Subgrade shall not be compacted prior to tailings placement. The Contractor will inspect and approve the tailings embankment subgrade prior to placement of contaminated materials. The Subcontractor shall

minimize disturbance to the subgrade once Contractor's approval has been obtained.

3.8 COMPACTION DENSITIES AND MOISTURE CONTENTS

A. Subgrade of permanent drainage features and embankments, and each layer of embankment and backfill shall be compacted to at least the following percentage of maximum dry density, as determined by ASTM D698 test method:

1. Subgrade Preparation:	90 percent
2. Subgrade Preparation for Permanent Drainage Features	95 percent
3. Tailings Embankment Contaminated Fill Except Top 3 feet	90 percent
4. Tailings Embankment Contaminated Fill Top 3 feet Immediately Below the Bottom of Radon Barrier	95 percent
5. Radon Barrier Layer	95 percent
6. Frost Protection Layer	90 percent
7. Trench Backfill and Common Fill	95 percent
8. Site Restoration	90 percent

B. Embankment erosion protection shall be compacted as specified in Part 3 of Section 02278.

C. Moisture Control:

1. Radon barrier material shall be compacted at moisture contents within zero to plus three percent of the optimum moisture content.
2. Moisture requirements for rock-like materials shall comply with 3.5.C.7.a.

3.9 DISPOSAL OF DEMOLISHED MATERIALS AND DEBRIS

A. All demolished materials and debris including contaminated cleared materials shall be disposed of in the tailings embankment conforming to the applicable provisions of this Section and as required by the Contractor.

- B. During construction of the tailings embankment, provision shall be made to leave required space at proper location in the embankment for the placement of the demolished materials and debris.

3.10 DISPOSAL OF ASBESTOS, HAZARDOUS AND NON-HAZARDOUS WASTE MATERIALS

Disposal of asbestos, hazardous and non-hazardous waste materials in the tailings embankment shall conform to the applicable provisions of this Section and the provisions of the Solid Waste Regulations of the Colorado Department of Health.

3.11 DISPLACEMENT MONUMENTS

Displacement monuments shall be furnished and installed by the Subcontractor as shown on the Subcontract Drawings. The Subcontractor shall take precautions not to damage the monuments once they are installed. Damaged monuments shall be replaced by the Subcontractor at no additional cost to the Contractor. The Subcontractor shall add extension rods to existing monuments as the fill is being placed. All displacement monuments shall be permanently protected as shown in the Subcontract Documents.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

- A. Measurement for payment for the following items of excavation will be by the cubic yards of materials excavated. The quantities for payment will be computed by average end area method from surveys conducted before and after excavation operations, or from lines and dimensions shown on the Subcontract Drawings. Separate measurement for payment will not be made for placement of the materials in their final locations.
 - 1. Excavation of Contaminated Materials from Tailings Pile and from Windblown and Waterborne Areas at NC Site and Placement in Tailings Embankment (Bid Schedule Item 401)
 - 2. Excavation of Contaminated Materials from Tailings Pile at UC Site and Vicinity Property Stockpile Material and Placement in Tailings Embankment (Bid Schedule Item 402)

3. Excavation of Contaminated Materials from Windblown/Waterborne Areas at UC Site and Placement in Tailings Embankment (Bid Schedule Item 403)
 4. Excavation of Contaminated Materials along Gas Line Right-of-Way at the UC Site and Placement in Tailings Embankment (Bid Schedule Item 404)
- B. Measurement for payment for the following items of excavation will be by the cubic yards of materials excavated. Quantities for payment will be computed by average end area method from surveys conducted before and after excavation operations, or from lines and dimensions as shown on the Subcontract Drawings.
1. Excavation of Uncontaminated Material and Placement for Fill as Required for Access Control Facilities, Temporary Drainage Ditches, Dikes and Wastewater Retention Basins at UC, NC and BC Sites (Bid Schedule Item 211)
 2. Excavation of Uncontaminated Materials for the Tailings Embankment Foundation and Placement in Spoilpile/Stockpile at the BC Site or for Finish Grading at the BC Site. (Bid Schedule Item 212)
 3. Rock Excavation for the Tailings Embankment Foundation and Placement in the Spoilpile/Stockpile or for Finish Grading at the BC Site (Bid Schedule Item 213)
- C. Measurement for payment for the following items of fills will be by the cubic yards of material placed in fills. The quantities for payment will be computed by average end area method from surveys conducted before and after placement, or from lines and dimensions as shown on the Subcontract Drawings.
- [1. Place Radon Barrier Material (Bid Schedule Item 501)]*
 2. Place Frost Protection Material (Bid Schedule Item 502)
 3. Place Common Fill Material (Including Topsoil) from Spoilpile/Stockpile at BC Site for Finish Grading of BC Site (Bid Schedule Item 801)

* P.I.D. 11-S-03

4. Furnish and Place Common Fill Material (Including Topsoil and Embankment for Reconstruction of County Road S8) for Finish Grading of UC and NC Sites (Bid Schedule Item 802)
- D. Measurement for payment for furnishing and installing displacement monuments will be by the number of monuments installed. (Bid Schedule Item 407)
- E. Measurement for payment for the following item of work will be by the square yard measured in the horizontal plane from surveys conducted before and after the work as shown on the Subcontract Drawings, or by the methods determined by the Contractor:
1. Cleanup of Rock Surface at UC and NC Sites
(Bid Schedule Item 405)
- F. Separate measurement for payment will not be made for the following items, and such work will be considered incidental to the related items of work:
1. Dust control.
 2. Subgrade preparation.
 3. Temporary stockpiling, permanent spoil pile and stockpile maintenance, and rehandling of materials.
 4. Borrow area excavation, maintenance, restoration, reseeding, and incidental activities.
 5. Protection of exposed surfaces during shutdown.
 6. Disposal of contaminated cleared materials in the tailings embankment resulting from work specified in Section 02110.
 - [7. Shrinkage of contaminated and uncontaminated materials.]*
- G. Overexcavation: Overexcavation for the Subcontractor's convenience or due to error or lack of control by the Subcontractor will not be measured for payment. At the discretion of the Contractor, overexcavation shall be backfilled with compacted contaminated or uncontaminated fill, as required, at the Subcontractor's expense.

* P.I.D. 11-S-07

Document No. 3885-SRK-S-01-02429-03
Issued for Construction-Revision 1

SRK

Earthwork
02200 - 33

WP51
022195

- H. Measurement for payment for disposal of demolished materials and debris will be made under Section 02050.
- I. Measurement for payment for disposal of asbestos, hazardous and non-hazardous waste materials will be made under Section 02081.
- J. No separate measurement for payment will be made for any other excavations or fills specified in this Section.

4.2 PAYMENT

- A. Payment for the items of Article 4.1.A above will be by their applicable unit prices per cubic yard quoted therefor in the Bid Schedule. The prices quoted shall include full compensation for excavating, hauling, and placing the excavated materials in their final locations, including all clearing, stripping, grading, shaping, preparing subgrade, compacting, temporary stockpiling and required rehandling.
- B. Payment for the items of Article 4.1.B above will be by their applicable unit prices per cubic yard quoted therefor in the Bid Schedule. The prices quoted shall include full compensation for excavating, hauling, and placing the excavated materials in temporary stockpiles, or in spoil areas if excess or unsuitable for use as fill, as required, including all clearing, stripping, grading, shaping, and compacting such stockpiles or areas as specified.
- C. Payment for the items of Article 4.1.C above will be by their applicable unit prices per cubic yard quoted therefor in the Bid Schedule. The prices quoted shall include full compensation for hauling the materials from excavated areas or retrieving the materials from temporary stockpiles, and placing the excavated materials in their final locations including all clearing, stripping, grading, shaping, preparing subgrade, and compacting. The prices quoted shall also include full compensation for furnishing imported uncontaminated/erosion protection materials from the Subcontractor's own sources.
- D. Payment for furnishing and installing displacement monuments will be by the unit price per each quoted therefor in the Bid Schedule.
- E. Payment for the item of Article 4.1.E above will be by the unit price per square yard quoted therefor in the Bid Schedule. The price quoted shall include full compensation for removing the materials from the required areas, as required, and placing the excavated materials in their final

locations including all grading, shaping, preparing subgrade, and compacting, as required.

- F. Separate payment will not be made for the items mentioned in Article 4.1.F above. All costs for such work will be considered to be included in the prices quoted for the applicable related items of work.
- G. Payment for disposal of demolished materials and debris will be made under Section 02050.
- H. Payment for disposal of asbestos and non-hazardous waste materials will be made under Section 02081.
- I. Separate payment will not be made for any other excavations or fills specified in this Section. All costs for excavations or for furnishing and placing such fills will be considered to be included in the related items of excavation.
- J. Separate payment will not be made for any other work specified in this Section. All costs for such work will be considered to be included in the related payment items of this Section.

END OF SECTION 02200

SECTION 02205

ROAD CONSTRUCTION

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section covers road construction for the following.
1. Temporary Detour of County Road CR-S8 at the UC site, County Road CR-S8 will remain open to the public during remedial action.
 2. County Road CR-S8 reconstruction. County Road CR-S8 shall be restored to original alignment.
 3. Upgrading of County Road CR-10R to provide access to the NC site from State Highway 141.
 4. Upgrading County Road T-11 to provide access to the BC disposal site from State Highway 141.
 5. Rock excavation near intersection of the BC access road and State Highway 141.

1.2 DESCRIPTION

- A. County Road CR-S8 at the UC Site: The portion of the County Road CR-S8 that crosses the UC site is between the Dolores River bridge and the intersection of County Road CR-S9. The county road shall be temporarily detoured along an existing alignment as shown on the Subcontract Drawings. Prior to constructing the detour, the area along the detour route and south of the detour will be radiologically surveyed by the Contractor. The Subcontractor shall excavate windblown/waterborne contaminated materials south and along the detour route and temporarily stockpile the contaminated material in the area between the existing County road alignment and the detour alignment. After constructing the detour, the Subcontractor shall excavate all contaminated materials between the temporary fence and the detour road alignment including the area along the gas pipeline right-of-way. After removal of contaminated materials south of the temporary fence, the county road shall be reconstructed along the original alignment at a time directed by the Contractor.

- B. County Road CR-10R: Access to the NC site will be via County Road CR-10R. The Subcontractor shall improve and widen the road between the NC site and State Highway 141 as shown on the Subcontract Drawings. Existing culverts shall be lengthened or replaced as required.
- C. County Road T-11: Access to the BC site from State Highway 141 shall follow the approximate alignment of the existing road. The BC access road shall be widened and improved as shown on the Subcontract Drawings. Existing culverts shall be lengthened or replaced as required. At the completion of construction, the road shall be restored to its original width and disturbed areas shall be restored.
- D. The line of sight at the intersection of the BC access road and State Highway 141 shall be improved by excavating the rock ridge northeast of the intersection as shown on the Subcontract Drawings.
- E. For the NC and BC access roads, the Subcontractor shall furnish detailed road designs, including information necessary to substantiate the basis for design items, for approval by the Contractor. The Subcontractor shall construct the roads in accordance with the approved design and shall maintain the roads as specified in this Section, subject to Contractor's approval. The Subcontractor shall perform all work within the haul route limits and in conformance with requirements shown on the Subcontract Drawings and specified in this Section, unless otherwise approved by the Contractor.

1.3 RELATED WORK

- A. Section 01300 - Submittals
- B. Section 01500 - Construction Facilities
- C. Section 01560 - Temporary Controls
- D. Section 02050 - Demolition
- E. Section 02110 - Site Clearing
- F. Section 02141 - Dewatering and Drainage
- G. Section 02200 - Earthwork

1.4 DEFINITIONS

- A. Access Route: The access route shall be the area within which the haul road shall be constructed. The haul route is shown on the Subcontract Drawings, including the right-of-way boundary and other restrictions and requirements.
- B. Access Road: The access road shall be the road and associated facilities, including embankment, excavation, drainage, subgrade, structural road section, and fencing and all other constructed features within the haul route.
- C. Earthwork: Earthwork for road construction shall include, but not be limited to, clearing and grubbing, stripping, excavation, subgrade preparation, embankment construction, structure backfill, erosion control, excavation of ditches and channels appurtenant to the road construction, finish grading of the inlet and outlet approaches of roadway culverts and reclamation of ground adjacent to and in the vicinity of the roadway footprint according to requirements given in the Subcontract Documents and Permits.
- D. Dewatering and Drainage: See Section 02141.
- E. Embankment: Embankment (Road Embankment) shall be pursuant to Colorado Standard Specifications.
- F. Excavation: Excavation shall be "unclassified" pursuant to Section 203.05 of the Colorado Standard Specifications, and shall include removal of all materials encountered regardless of the nature of the materials, including bituminous pavement, topsoil, silt, clay, sand, gravel, talus, boulders and rock.
- G. Backfill: General Backfill (Common/General Fill) for the purpose of these Subcontract Documents shall be all compacted backfill required for Road Earthwork, to include but not be limited to, subgrade remediation, subgrade preparation and road embankment herein specified.
- H. Structural Backfill: Structural Backfill shall be pursuant to Section 206 of the Colorado Standard Specifications.
- I. Road Surface Course: Road Surface Course (Wearing Course) is defined as the top layer of the pavement structure for either aggregate-surfaced or asphalt concrete-surfaced roadway.
- J. Base Course: The layer or layers of specified or selected material of designed thickness placed on a subbase or a subgrade to support a surface course.

- K. Subbase: The layer or layers of specified or selected material of designed thickness placed on a subgrade to support a base course.
- L. Roadbed: The graded portion of a roadway upon which the subbase, base, surface course, and shoulders are constructed.

1.5 APPLICABLE PUBLICATIONS

- A. The Publications listed below form a part of this Specification to the extent referenced. The Publications are referred to in the text by the basic designation only:

- 1. American National Standards Institute (ANSI):

- Manual on Uniform Traffic Control Devices for Streets and Highways

- 2. American Society for Testing and Materials (ASTM):

- C136-92 Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates

- D698-90 Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³ (600 kN-m/m³))

- 3. Colorado Department of Transportation (CDOT):;

- Standard Specifications for Road and Bridge Construction, 1991 Edition.

- 4. San Miguel County Land Use Codes, adopted November 1990.

1.6 QUALITY ASSURANCE

Tolerances: See Specification Section 01052, Article 1.7.

1.7 SUBMITTALS

- A. General submittal requirements are specified in Section 01300.

- B. UC Site Temporary Detour and NC and BC Site Access Roads:

- 1. Plan and Schedule: Twenty days prior to the start of work, the Subcontractor shall submit to the Contractor a Plan and Schedule for constructing the UC site temporary

detour and NC and BC site access roads including improvements and demolition which shall include the following:

- a. Construction schedule.
 - b. Temporary signage and striping.
 - c. Compliance with permit requirements.
- C. Road Designs: The Road Design Submittal shall be submitted to the Contractor for review and approval within 21 days following Notice to Proceed. The Subcontractor shall allow 30 days for the Contractor's review. The submittal shall indicate approval by the agency having jurisdiction over such roads. The submittal shall include:
1. Detailed construction drawings of the road. The drawings shall be prepared by a Civil Engineer registered in the State of Colorado.
 2. Traffic signs and other traffic control elements.
 3. Plans for removal and disposal of materials unacceptable for use in reclamation of the haul routes.

1.8 ROAD DESIGN CRITERIA

- A. Road Design Criteria: The roads shall be designed to the extent practicable in accordance with the San Miguel Land Use Codes for primitive roads. Design criteria for the haul roads shall include the following:
1. Design Speed: As required by Subcontractor's road design to meet requirements specified herein.
 2. Lane Width: As required by the Subcontractor's road design. Minimum width shall be according to minimum criteria set forth for local or mountain roads in Colorado Standard Specifications.
 3. The UC detour road and the BC access road shall be 2 lanes. The NC access road shall be two lanes between Highway 141 and Northing, 56,700, and from Northing 57,500 to the NC site.
 4. The County Road CR-S8 shall be reconstructed along the existing alignment and shall have two lanes.
 5. Safe speed limits shall be subject to approval by the Contractor and shall be posted along the haul route which shall be dependent on grades, curves, safe sight

distance, quality of road construction and road surface. Speed limits posted shall be maximums for good weather and road conditions.

6. Maximum Design Grade of 8 percent.
 7. The roads shall be designed safe for the purpose intended.
 8. The quality of the road shall be adequate for meeting the specified schedule.
 9. The reconstructed County Road CR-S8 at the UC site shall be a Class 6 crushed gravel surface in accordance with Colorado Standard Specifications. The road surface course for other roads shall be as required by the permitting agency and by the Subcontractor for his operations.
 10. The Subcontractor shall prepare and submit to the Contractor all Quality Control records required by the Contractor.
- B. Road design shall include road markings and signage, including stop signs and warning signs on both sides of the vehicle road or trail connecting to or crossing the haul road.
 - C. Drainage Design: The Subcontractor's design shall include longitudinal and cross-drainage facilities including ditches, structures, culverts and the like. The design shall include replacing or lengthening of existing culverts as required. The design shall include outline drawings of corrugated steel pipe and joint details.
 - D. Traffic Control. The Subcontractor's submittal shall indicate where and when flagpersons shall be on duty. The Contractor may require additional flagpersons during the course of the work.
- 1.9 PROTECTION
- A. The Subcontractor shall protect the following:
 1. Trees, shrubs and other features remaining as a portion of final grading.
 2. Bench marks and monuments, existing structures, fences, walks, pavings, curbs, etc. from equipment and vehicular traffic.
 3. Utilities not specified for removal.

4. Excavations from cave-in by shoring, bracing, sheetpiling, underpinning or by other methods.
5. Bottoms of excavations and soil adjacent to and beneath foundations from frost.
6. Top of excavation perimeter to prevent surface water runoff into excavation.

B. Archaeological Sites: The Subcontractor shall protect from disturbance all archaeological sites within the vicinity of the access road right-of-ways.

1.10 DELIVERY AND STORAGE OF MATERIALS

Corrugated steel pipe, structures, and related material shall be delivered in sufficient time to ensure uninterrupted progress of the work. Materials shall be stored in a manner to preclude damage and to permit ready access for inspection and identification of each shipment. Pipe, structures and accessories shall be kept free from dirt, grease, and other foreign matter. Materials showing evidence of unrepairable damage, as determined by the Contractor, will be rejected and shall be immediately removed from the work.

PART 2 - PRODUCTS

2.1 FILL MATERIALS

- A. Base and Subbase Course Materials: The materials for base and subbase courses shall conform to the applicable provisions for gravel streets in San Miguel County Land Use Codes.
- B. Gravel or aggregate surface course for construction of road shoulder shall conform to the applicable provisions of Section 703 of the Colorado Standard Specifications.
- C. Fill Materials: Fill material shall be approved material from excavation or borrow areas as specified in Section 203 of the Colorado Standard Specifications.

2.2 CORRUGATED STEEL PIPE

- A. Corrugated steel pipe and coupling bands shall conform to the applicable provisions of Subsection 707.02 of the Colorado Standard Specifications.

B. Special Sections: Special sections such as elbows, wyes, tees, crosses, bends, reducers and flared inlets shall be furnished as called for on the Subcontract Drawings or as required by the Contractor.

C. Dimensions and Thicknesses: The pipes shall be furnished as follows:

Nominal Inside Diameter:	12 - 36 inches
Corrugations:	2-2/3-inch x 1/2-inch
Minimum Thickness:	0.064 inch

PART 3 - EXECUTION

3.1 GENERAL

- A. Protection of Exposed Surfaces: See Section 02200.
- B. Construction shall be coordinated with and shall be as approved by the Contractor.
- C. The Subcontractor shall coordinate all road construction activities with local utilities, fire and police departments.
- D. Erosion shall be kept to a minimum and suitable grades and radii of curves shall be maintained to facilitate ease of movement of vehicles and equipment.
- E. The Subcontractor shall furnish and install road signs and signals, and shall mark and stripe pavements if pavement is provided, as required, for the safe operation of vehicles.
- F. Longitudinal and cross drainage facilities including, but not limited to, the ditches, structures, pipes and the like shall be furnished and installed by the Subcontractor.
- G. Road demolition items, such as, but not limited to existing culverts, drainage appurtenances, structures and foundations, as required by these Subcontract Documents, shall be disposed of offsite in accordance with all applicable permits and regulations.
- H. Dewatering and drainage shall be performed in accordance with Section 02141 unless otherwise specified herein.
- I. Earthwork shall be as specified in Section 02200 unless otherwise specified herein.

- J. Prior to commencement of earthwork operations, the Subcontractor shall verify that existing site drainage facilities are operational and that positive drainage will be maintained. The Subcontractor shall be responsible for the maintenance of drainage facilities. The Subcontractor shall remove debris and other materials that may restrict, or prevent drainage in drainage facilities when directed by the Contractor.

3.2 SUBBASE, BASE COURSE AND SURFACE COURSE CONSTRUCTION

- A. The construction of the base courses shall conform to the applicable provisions of the San Miguel County Land Use Codes except as modified herein and as approved by the Contractor.
- B. Before placing and spreading base course material the subgrade shall be cleaned of all foreign substances and shall contain no frozen material. It will be inspected by the Contractor for adequate compaction and surface tolerances. Soft and yielding subgrade shall be removed as directed by the Contractor and replaced with granular material. Subgrade shall be computed for 95 percent of maximum dry density as determined by ASTM D698 test method.
- C. Compaction: Each layer of aggregate base courses shall be compacted to 100 percent of maximum dry density as determined by ASTM D698 test method.

3.3 ROAD RECLAMATION

- A. Access route reclamation shall be performed by the Subcontractor in accordance with all applicable permits and agreements including, but not limited to, seeding, drainage restoration, contouring and fencing.
- B. Revegetation within the road right-of-way shall be required and shall be completed during the first planting season after construction. All areas disturbed by construction operations and not otherwise covered by structures or pavement shall be seeded, fertilized, mulched, planted, and otherwise treated to provide an established stand of grass. Seeding shall be in conformance with Section 02935 unless otherwise stated in the permits. Seed mix shall be as specified for the site the access road is serving.
- [C. After completion of hauling material, the Subcontractor shall repave the reconstructed County Road CR-S8 on its original alignment. The Subcontractor shall repair and restore to preconstruction conditions any damaged part of the paved

portions of County Road CR-S8 starting from the temporary detour down to State Highway 141.]*

- D. The Subcontractor shall record and document the preconstruction condition of County Road CR-S8 between the UC site and State Highway 141 and along State Highway 141 between the NC access road intersection and the Disappointment Valley Borrow site. Records and documents shall be sufficient to determine preconstruction conditions and shall be submitted to the Contractor for approval. Records and documents shall include photographs and notes including, but not limited to, the following:

1. Existing roadways.
2. Structures, including fencing.
3. Utilities.
4. Drainage facilities.

Areas that have preconstruction damage or that are in disrepair shall be specifically noted.

3.4 FIELD QUALITY CONTROL

- A. General: The Subcontractor shall cooperate in providing access for the Contractor to areas where testing is to be performed.

1. Access to Work: Authorized agents of the following agencies shall have the right to inspect the road construction:

- a. Colorado Department of Transportation (CDOT)
- b. San Miguel County
- c. The various agencies listed in the Special Conditions, Section SC-11, Permits.

- B. Roads: The testing requirements and frequency shall be in accordance with the Subcontractor's approved design.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

- A. Measurement for payment for access roads to the NC and BC sites, including earthwork, as specified in Section 02200, and culverts will be on a lump sum basis.

* P.I.D. 11-S-07

- [B. Measurement for payment for reconstruction and repaving of County Road CR-S8 on original alignment at the UC site, excluding earthwork which is specified in Section 02200, will be by the linear foot of road reconstruction.]*
- C. Measurement for payment for excavation required at the junction of the BC access road and State Highway 141 will be by the cubic yards excavated.
- D. Separate measurement for payment will not be made for the following items, and such work will be considered incidental to the related items of work:
 - 1. Temporary detour of County Road CR-S8 at the UC site.
 - [2. Restoration of paved portions of County Road CR-S8 starting from the temporary detour down to State Highway 141 at the completion of construction.]*
 - 3. Restoration of County Road T-11 at the BC site.

4.2 PAYMENT

- A. Payment for access roads to the NC and BC sites, including earthwork as specified in Section 02200, and culverts will be by the lump sum price quoted therefor in the Bid Schedule. The prices quoted shall include full compensation for furnishing all labor, materials, equipment, tools, accessories and incidentals, and for performing all work including designing, fabricating, installing/constructing roadwork and required facilities complete in-place, and for protection and maintenance of completed work, as shown on the Subcontract Drawings, as specified in these Specifications and as required by the Contractor.
- B. Payment for reconstruction of County Road CR-S8 on original alignment at the UC site, excluding earthwork which is specified in Section 02200, will be by the unit price per linear foot quoted therefor in the Bid Schedule.
- C. Payment for excavation required at the junction of the BC access road and State Highway 141 will be by the unit price per cubic yard quoted therefor in the Bid Schedule. The price quoted shall include full compensation for excavating, hauling, and disposing of excavated materials.

* P.I.D. 11-S-07

- D. Separate payment will not be made for the items mentioned in Article 4.1.D above. All costs for such work will be considered to be included in the prices quoted for the applicable related items of work or incidental to the Subcontract.
- E. Separate payment will not be made for any other excavations or fills specified in this Section. All costs for excavations or for furnishing and placing such fills will be considered to be included in the related items of excavation.

END OF SECTION 02205

SECTION 02278

EROSION PROTECTION

PART 1 - GENERAL

1.1 SCOPE

This Specification Section describes the requirements for furnishing and placing erosion protection materials (riprap and bedding) for tailings embankment cover and aprons.

1.2 WORK NOT INCLUDED

Erosion protection related to the Construction Facilities and Temporary Controls specified in Sections 01500 and 01560 is not included in the scope of work of this Specification.

1.3 RELATED WORK

- A. Section 01300 - Submittals
- B. Section 02200 - Earthwork

1.4 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this Specification to the extent referenced. The publications are referred to in the text by the basic designation only:

- 1. American Society for Testing and Materials (ASTM):

C88-90	Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
C117-90	Test Method for Materials Finer Than 75 Micrometer (No. 200) Sieve in Mineral Aggregates by Washing
C127-88	Test Method for Specific Gravity and Absorption of Coarse Aggregate
C131-89	Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine

- C136-92 Test Method for Sieve Analysis of Fine and Coarse Aggregates (Rulers or Templates may be Substituted for Sieve Granulation of Particles)
- C295-90 Practice for Petrographic Examination of Aggregates for Concrete
- D75-87 Standard Practice for Sampling Aggregates (R1992)
- D3740-88 Standard Practice for Evaluation of Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction

2. International Society for Rock Mechanics (ISRM), 1981, Rock Characterization Testing and Monitoring, ISRM Suggested Methods, E. T. Brown, Editor, Pergamon Press, New York:

Suggested Method for Determining Indirect Tensile Strength by the Brazil Test, pp. 120-121

Suggested Method for Determination of the Schmidt Rebound Hardness, pp. 101-102

3. National Institute of Standards and Testing (NIST).

1.5 PERMITS

- A. The Contractor will provide permits for the use of borrow areas shown on the Subcontract Drawings as specified in Article SC-11 of Special Conditions. If the Subcontractor uses other sources for erosion protection materials, he shall be responsible for obtaining all required permits.
- B. The Subcontractor shall perform the Work in accordance with the requirements of all applicable permits.

1.6 SUBMITTALS

- A. During production of riprap and bedding materials, the Subcontractor shall submit gradation test results, in triplicate, in accordance with Article 2.1 below. For riprap and bedding materials, quality and gradation tests for each type material shall be performed a minimum of four times during production. An initial sample shall be obtained and tested during the early stages of production activities. Additional samples shall be obtained and tested when approximately one-third and two thirds of the total volume of

material has been produced, and a final sample shall be obtained and tested near completion of the production activities. If the total volume of material for each riprap type or bedding material is greater than 30,000 cubic yards, quality and gradations tests shall be performed for each additional 10,000 cubic yards, or fraction thereof produced. The frequency for performing the quality and gradation tests shall be when approximately 10,000 cubic yards of material has been produced and near completion of production activities.

- B. The Subcontractor shall submit, in writing, the name and qualifications of his proposed testing laboratory to the Contractor for approval. The Subcontractor's proposed laboratory shall meet the requirements of ASTM D3740.
- C. The technical submittal covering the production of erosion protection materials shall include, but not be limited to, the following:
 - 1. Narrative acknowledging permit stipulations for each rock borrow source.
 - 2. Mining plan.
 - 3. Use, handling and storage of explosives.
 - 4. Expected quarry breakage or pit analysis.
 - 5. Required combined product gradation.
 - 6. Production analysis.
 - 7. Flow diagram of production plant showing all products and wastage in tons per hour.
 - 8. Plant layout showing individual pieces of equipment.
 - 9. Complete list of equipment with manufacturers' models, capacities, horsepower and expected production curves.
 - 10. Schedule.
 - 11. Manpower required.
 - 12. Handling of finished products.
 - 13. Safety.
 - 14. Maintenance of public and on site haul roads.

- 15. Dust control.
- 16. Protection of archaeological sites.
- 17. Quality control.
- 18. Drainage erosion control plan.
- 19. Reclamation plan.

- D. If the Subcontractor determines to use other sources for erosion protection materials, a site inspection report containing the information specified in Article 2.3 below shall be submitted, in triplicate, to the Contractor for review and approval of the source, in accordance with the requirements of Section 01300. The site inspection report shall be submitted 90 days prior to production of the material. The Subcontractor shall also provide access to the source for the Contractor for the purpose of investigating and sampling the source materials at least 90 days prior to production of the material.

1.7 QUALITY ASSURANCE

Test Section: For placement control purposes, one test section for Riprap Types A and B each shall be constructed. The test sections shall be not less than 30 feet wide by 50 feet long in size, and shall be constructed on the tailings embankment. Riprap material fully meeting the specified gradations shall be placed in the test sections by the same methods that will be used for production placement. The finished test sections, after testing to ensure that the specified requirements have been met, shall be used as a visual sample for comparison of production work.

PART 2 - PRODUCTS

2.1 GENERAL

- A. Material Sources: Erosion protection materials shall be obtained from sources approved by the Contractor. Potential sources for Types A, B and C riprap and bedding material are the Dolores River borrow site and terrace cobbles and gravels from the UC site south of coordinate N58,500 and west of coordinate E59,400. [A total of 3,500 cubic yards may be removed from the UC site and used as erosion protection at the BC disposal site.]* The material from the two potential

* P.I.D. 11-S-07

borrow sites may be blended or mixed to meet the required gradations requirement.

- B. Subcontractor may propose other sources of materials. The basis for approval of the Subcontractor-proposed sources is specified in Article 2.3. The materials shall meet the requirements of this Specification.
- C. Approval of a source as a borrow area does not mean that all materials excavated will meet the requirements of this Specification. Processing, selective quarrying or both may be necessary to meet the requirements of this Section. The Subcontractor shall be responsible for providing the laboratory test results.
- D. The materials shall be radiologically indistinguishable from the background radioactive level and free from other contamination.
- E. Material shall be dense, sound, resistant to abrasion, and shall be free from cracks, seams, and other defects as shown in the petrographic examination and during field inspection as per Article 3.3 below.
- F. Quality and Gradation Tests: For record purposes the following tests will be performed by the Contractor:

<u>Test</u>	<u>Designation</u>
Gradation	ASTM C117 ASTM C136
Specific Gravity (Saturated Surface Dry Basis)	ASTM C127
Absorption	ASTM C127
Sodium Sulfate Soundness Soundness (5 Cycles)	ASTM C88 Coarse Aggregate
Abrasion (Los Angeles Machine) (100 Cycles)	ASTM C131
Schmidt Rebound Hardness	ISRM Method
Splitting Tensile Strength (Modified-Loading Rate Shall Cause Failure in 1 to 3 minutes)	ISRM Method
Petrographic Examination	ASTM C295

The frequency of tests shall be in accordance with Article 1.6.A for the total amount produced at each quarry regardless of number of types of materials produced.

2.2 QUALITY REQUIREMENTS

A. All riprap and bedding materials used shall meet the following requirements as tested by the Contractor:

1. The tests specified in Table A shall be taken at the frequency specified in 1.6.A for each material type. The score for each test is determined by multiplying the appropriate weighting factor by the score (0 to 10) based on the specific test result. The final score for each sample is the ratio of the sum of the individual test scores (six tests) to the maximum possible score, expressed as a percentage. To be acceptable, the final score shall be no less than 65 percent for Riprap Types A, B and C and bedding material.
2. The Schmidt Rebound Hardness Test and Splitting Tensile Strength Test will not be required on the bedding material or on Type A and Type B Riprap. The scoring of bedding material and Type A and Type B Riprap will be based on the four remaining tests.

2.3 SUBCONTRACTOR-PROPOSED SOURCES

A. The basis for approval of sources proposed by the Subcontractor shall be as follows:

1. A site inspection report by an independent testing laboratory's engineering geologist which shall include, as a minimum, an evaluation of soundness, hardness, and durability for three samples representative of the proposed source. The evaluation of durability shall be based in part on petrographic examination of rock types available from the source. The petrographic examination shall be in accordance with ASTM C295. In addition, the material shall meet the quality requirements of Article 2.2 above. Representativeness of samples shall be determined by the Contractor, based on precise location and source of sample taken in relation to the whole borrow area. The site inspection report shall include locations of all samples and methods of sampling. To be approved as a source, the final score for each sample shall be obtained and evaluated as specified in Article 2.2.A.

2. If available, examples of successful uses of the material including riprap that has been in place on other project sites for more than 20 years, rock that has functioned satisfactorily as foundation stone or building facing for 50 years or more, and abandoned quarry faces which have maintained their integrity after not being worked for approximately 50 years or more. Durability shall be indicated by lack of significant weathering or loss of volume and strength over decades of exposure to natural weathering elements.
3. The Subcontractor shall have a qualified laboratory perform the six types of tests listed in Table 02278A on each sample (minimum of 6 samples) from the proposed source unless existing particle sizes are inadequate to perform Schmidt Rebound Hardness or Tensile Strength tests as specified. Special attention shall be given to ensure that the samples are representative of the proposed rock materials. Test samples shall be obtained from within the precise locations of rock deposits from which materials will be produced. To be approved as a source, the final score for each sample shall be obtained and evaluated as specified in Paragraph 2.2.A.

2.4 GRADATION REQUIREMENTS

- A. Materials shall be reasonably well graded within the following limits, and the Contractor reserves the right of inspection while the samples are taken:

1. Riprap:

- a. Gradation:

<u>U.S. Standard Sieve Size/Nominal Size (Square Openings)</u>	<u>Percent Passing (by weight)</u>
<u>Type A</u>	
3-inch	100
2-inch	20-100
1-1/2-inch	5-40
1-inch	0-15
No. 4	0-5

Type B

7-inch	100
5-inch	30-100
4-inch	15-50
3-inch	0-30
1-inch	0-10
No. 4	0-5

Type C

10-inch	100
7-inch	35-100
5-inch	10-35
4-inch	0-25
No. 4	0-15

- b. Maximum Size: No individual piece shall be greater than 90 percent of the riprap layer thickness.

2. Bedding:

<u>U.S. Standard Sieve Size (Square Openings)</u>	<u>Percent Passing (by weight)</u>
3-inch	100
1-inch	45-100
1/2-inch	20-60
No. 4	10-40
No. 20	0-13
No. 100	0-5

2.5 SOURCE QUALITY CONTROL

The Subcontractor shall provide a trailer and equipment for rock testing at each source and shall have a qualified engineering geologist present at the quarry during production of rock materials to monitor materials acquisition and production to ensure that only materials acceptable under Articles 2.1 and 2.2 as confirmed by the Contractor are processed. The rock testing equipment shall be in good working order and if required, calibrated to National Institute of Standards and Testing (NIST) standards prior to being used. The materials may be inspected and tested by the Contractor at the borrow area prior to mining operations to ensure that they meet the requirements of these Specifications. The Subcontractor shall assist the Contractor in obtaining samples. Gradation requirements will be tested at the placement location.

PART 3 - EXECUTION

3.1 PLACEMENT AND COMPACTION

- A. General: Erosion protection materials shall be handled, loaded, transported, stockpiled and placed in a manner which avoids nonconformance with specifications due to segregation and degradation, including materials moved to and from stockpiles.
- B. Prior to placing bedding or riprap, subgrade preparation shall conform to Specification Section 02200.
- C. Where the required bedding material thickness is 6 inches or less, the bedding material shall be spread and compacted in one layer. Where the required thickness is more than 6 inches, the material shall be spread and compacted in two or more layers of approximately equal thickness and the maximum compacted thickness of any one layer shall not exceed 6 inches.
- D. Each layer of bedding material shall be track-walked with two passes of a D6 bulldozer or equivalent operating up and down the slope, over the entire area of placement.
- E. Dumped riprap shall be placed to its full course thickness in one operation and in such a manner as to avoid displacing the drainage material. The larger stones shall be well distributed throughout the mass. The finished riprap shall be free from pockets of small stones and clusters of larger stones. Placing stone in layers will not be permitted. Placing stone by dumping into chutes or by similar methods likely to cause segregation of the various sizes will not be permitted. The desired distribution of the various sizes of stones throughout the mass shall be obtained by selective loading of the material at the quarry or other source, by controlled dumping of successive loads during final placing, or by other methods of placement which will produce the specified results.
- F. Riprap material may be placed by end-dumping and may be spread by bulldozers or other suitable equipment. Riprap material shall be placed so that the larger pieces are uniformly distributed and the smaller pieces serve to fill the spaces between them to provide well keyed, densely placed layers of the specified thicknesses.
- G. Riprap layers placed upon bedding material shall be placed in such a manner which minimizes horizontal displacement of the bedding material.

- H. Construction equipment other than spreading and compaction equipment shall not be allowed to move over the placed riprap and bedding layers except at equipment crossovers as designated by the Contractor. Each crossover shall be cleaned of all objectionable materials as approved by the Contractor before additional materials are placed in those areas. The Contractor may restrict traffic over placed riprap and bedding layers to minimize damage to completed layers. Areas of riprap and bedding layers damaged by construction equipment shall be restored to meet the requirements of the Specifications.

3.2 TOLERANCES

- A. The material layers shall be placed generally to the limits and thicknesses shown on the Subcontract Drawings within the following tolerances:
1. The top of the radon barrier or bedding subgrade shall be within ± 0.1 foot of the design grades shown on the Subcontract Drawings.
 2. Top of bedding material shall be within 0.1 foot of design grade shown on the Subcontract Drawings.
 3. The in-place thickness of riprap and bedding materials shall be between 90 percent and 125 percent of the thickness shown.
 4. Local irregularities not exceeding the limits of Paragraphs 2 and 3 above will be permitted provided that such irregularities do not form noticeable mounds, ridges, swales or depressions which in the opinion of the Contractor could cause concentrations of surface runoff or form ponds or gullies.

3.3 FIELD QUALITY CONTROL

- A. Source Quality Control: The Subcontractor shall have a qualified engineering geologist present at the quarry during production of rock materials to ensure that only materials acceptable under Articles 2.1 and 2.2 as confirmed by the Contractor are processed. During excavation or blasting of materials, the Contractor will inspect the site to ensure that stripping and material selection procedures are adequate to prevent inclusion of deleterious materials in processed materials. The Contractor reserves the right to inspect and test the materials at any time during or after production and placement. The materials may be inspected and tested by the Contractor at the borrow area prior to mining operations to ensure that they meet the requirements of these Specifica-

tions. The Subcontractor shall assist the Contractor in obtaining samples. Gradation requirements will be tested at the placement location.

- B. Placement Quality Control: The placement of the materials will be inspected, and the materials will be tested by the Contractor during and after placement to ensure that the following requirements are met:
 - 1. Material of the correct type and quality is being placed. Individual pieces or pockets of material greater than or equal to 8 inches in diameter not meeting the requirements noted in Article 2.1.E shall be removed per Paragraph D below. Individual pieces or pockets of material less than 8 inches in diameter not meeting the requirements of Article 2.1.E may be left in place provided that concentrations of such pieces do not exist as determined by the Contractor.
 - 2. The material being placed is clean and free of unsuitable material.
 - 3. The material is being stockpiled, loaded, transported and placed in a manner which minimizes segregation and degradation.
 - 4. The material is being placed to line and grade within the tolerances and limits designated in Article 3.2 above.
 - 5. The larger stones are well distributed and the finished riprap is free from objectionable pockets of small stones and clusters of large stone.
 - 6. The material placed meets the gradation requirements specified.
- C. The Subcontractor may place erosion protection material only at his own risk, if durability test results are not available and approved by the Contractor.
- D. Materials segregated or not placed according to the above requirements shall be regraded or adjusted, using appropriate equipment, to conform with the tolerances and limits given above, at no additional cost to the Contractor.
- E. Materials not meeting the requirements of this Section shall be removed and replaced with specified materials at no additional cost to the Contractor. Rejected materials shall be disposed of offsite as Subcontractor's property at no additional cost to the Contractor. Materials not meeting the grading requirements shall be reprocessed or discarded. The

Contractor may require modification of the processing and grading operations to ensure that the specified grading requirements are met.

- F. During placement of riprap materials and bedding materials, the Contractor will perform a minimum of four gradation tests on each type of material in accordance with Article 2.4 above. An initial sample will be obtained and tested during the early stages of placement activities. Additional samples will be obtained and tested when approximately one-third and two-thirds of the total volume of material has been placed, and a final sample will be obtained and tested near completion of placement activities. If the total volume of material placed for each type of material is greater than 30,000 cubic yards, a gradation test will be performed for each additional 10,000 cubic yards, or fraction thereof placed.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

- A. Measurement for payment for furnishing and placing the following materials will be by the cubic yards of material placed. The quantities will be calculated from the lines and dimensions shown on the Subcontract Drawings:

1. Riprap Material, Type A
2. Riprap Material, Type B
3. Riprap Material, Type C
4. Bedding Material

4.2 PAYMENT

Payment for the items of Article 4.1.A above, will be by their applicable unit prices per cubic yards quoted therefor in the Bid Schedule. The prices quoted shall include full compensation for furnishing labor, materials, tools, equipment and incidentals and for performing specified work including development of the source (where applicable), obtaining required permits (where applicable), clearing, stripping and excavating; processing the materials; testing and evaluating the materials; transporting to placement locations; placing; compacting and consolidating complete in place.

END OF SECTION 02278

Document No. 3885-SRK-S-01-02431-03

Issued for Construction-Revision 1

Erosion Protection

02278 - 12

SRK

WP51
022195

TABLE 02278-A
ROCK QUALITY SCORING CRITERIA

	Weighting Factor			Score										
	Lime- stone	Sand- stone	Igne- ous	10	9	8	7	6	5	4	3	2	1	0
Specific Gravity	12	5	9	2.75	2.70	2.65	2.60	2.55	2.50	2.45	2.40	2.35	2.30	< 2.3
Absorp- tion (%)	13	5	2	0.1	0.3	0.5	0.67	0.83	1.0	1.5	2.0	2.5	3.0	> 3.0
Sodium Sulfate (%)*	4	3	11	1	3	5	6.7	8.3	10	12.5	15	20	25	> 25
Abrasion (%)**	1	8	1	1	3	5	6.7	8.3	10	12.5	15	20	25	> 25
Schmidt Rebound Hardness	11	13	3	70	65	60	54	47	40	32	24	16	8	< 8
Tensile Strength(psi)	5	4	10	1400	1200	1000	833	666	500	400	300	200	100	< 100

1. Scores derived from Tables 6.2 and 6.7 of Ref. 1.
2. Any rock to be used must be qualitatively rated at least "fair" in a petrographic examination conducted by a geologist experienced in petrographic analysis.
3. Weighting Factors derived from Table 7 of Ref. 2, based on inverse of ranking of test methods for each rock type.
4. Test methods should be standardized (ASTM, e.g.) and should be those used in Ref. 2.

Ref. 1 Lindsey, C.G., Long, L.W., and Begej, C.W. (1982), Long-Term Survivability of Riprap for Armoring Uranium Mill Tailings and Covers: A Literature Review, U.S. Nuclear Regulatory Commission, NUREG/CR-2642.

Ref. 2 De Puy, G.W., "Petrographic Investigations of Rock Durability and Comparisons of Various Test Procedures," Engineering Geology, Vol. 2, No. 2, July 1965.

* 5 Cycles
** 100 Revolutions

Document No. 3885-SRK-S-01-02431-03
Issued for Construction-Revision 1
Erosion Protection
02278 - 13

SRK

WP51
022195

SECTION 02771

MEMBRANE LINER

PART 1 - GENERAL

1.1 SCOPE

This Specification Section describes the requirements for furnishing and installing membrane liner systems for temporary drainage ditches and wastewater retention basins and spillways.

1.2 SYSTEM DESCRIPTION

- A. Liner system shall consist of liner, adhesives and accessories required for sterilizing ground and installing liner, vents and other appurtenances.
- B. The ditches and retention basin, where lining is required, will carry water produced from stormwater runoff, decontamination and dewatering operations, including minor amounts of sediment.
- C. The liner will be installed without a protective earthen cover and will be exposed to all natural weathering elements, such as direct sunlight, cold and hot air temperatures, snow, ice, rain and wind.

1.3 RELATED WORK

- A. Section 01300 - Submittals
- B. Section 02050 - Demolition
- C. Section 02141 - Dewatering and Drainage
- D. Section 02200 - Earthwork

1.4 APPLICABLE PUBLICATIONS

- A. The Publications listed below form a part of this Specification to the extent referenced. The Publications are referred to in the text by the basic designation only:

1. American Society for Testing and Materials (ASTM):

- D638-91 Standard Test Method for Tensile Properties of Plastics (As modified by NSF 54)
- D746-79 Standard Test Method for Brittleness Temperature of Plastics and Elastomers by Impact
- D751-89 Standard Test Methods for Coated Fabrics (As modified by NSF 54)
- D792-91 Standard Test Methods for Specific Gravity and Density of Plastics by Displacement
- D1004-90 Standard Test Method for Initial Tear Resistance of Plastic Film and Sheeting
- D1204-84 Standard Test Method for Linear Dimensional Changes of Nonrigid Thermoplastic Sheeting or Film at Elevated Temperature
- D1238-90 Standard Test Method for Flow Rates of Thermoplastics by Extrusion Plastomer (Rev. B)
- D1603-76 Standard Test Method for Carbon Black in Olefin Plastics
- D1693-70 Standard Test Method for Environmental Stress Cracking of Ethylene Plastics
- D3015-72 Standard Practice for Microscopical Examination of Pigment Dispersion in Plastic Compounds
- D4437-84 Standard Practice for Determining the Integrity of Field Seams Used in Joining Flexible Polymeric Sheet Geomembranes

2. National Sanitation Foundation (NSF):

- NSF 54-1991 Flexible Membrane Liners
(Revised May 1991)

3. Federal Standard (FS):

- FTMS 101 Test Methods for Puncture Resistance and Elongation Test (Method 2065)

1.5 QUALITY ASSURANCE

- A. Manufacturer: The manufacturer of the liner shall have manufactured in excess of 10,000,000 square feet of membrane liner. The manufacturer shall also certify in writing that the liner meets or exceeds the NSF Standard 54 physical properties as specified in this Section, and shall withstand a minimum of 5 years of outdoor weathering without cover. The certification shall also state that the liner material is formulated from 100 percent virgin domestic, first quality raw materials.
- B. Fabricator: The liner fabricator shall have fabricated in excess of 10,000,000 square feet of liner.
- C. Installation: The Installation Supervisor shall have supervised installation of lining material in excess of 1,000,000 square feet of liner. The Installation Supervisor shall be present on the site during installation and testing of the liner system.

1.6 SUBMITTALS

- A. General submittal requirements are specified in Section 01300.
- B. The Subcontractor shall submit the following to the Contractor for submittal to the Colorado Department of Health for review and approval 30 days before placement of the material:
 - 1. Product data.
 - 2. Samples of material and accessories.
 - 3. Certificate signed by the manufacturer stating that the system proposed meets the Specification.
 - 4. Six sets of full and complete drawings showing liner installation details. These drawings shall show as a minimum, the panel layouts, liner hold-downs and gas vent details as required for liner installation. Liner hold-downs shall have sufficient weight to prevent uplift and billowing of the liner from wind velocities up to 50 mph.
 - 5. Fabricator's or manufacturer's certified installation instructions.
 - 6. Test reports.

7. Qualifications of installer and supervisor in accordance with the requirements of Article 1.5.C.
8. Certification from a recognized independent testing laboratory that the liner meets the requirements of this Specification and is suitable for its intended purpose.

1.7 SITE CONDITIONS

The sites are at an approximate elevation of 5550 feet to 5900 feet and are located near Slick Rock, Colorado. Recorded temperatures have ranged from a high of 100°F to a low of -20°F with average recorded annual wind speed of 7 mph.

1.8 WARRANTY

- A. Liner materials and factory seams shall be warranted to be free from defects in materials and workmanship for a period of 5 years from the date of acceptance. Installation and field seams shall be warranted free of defects for a period of 5 years from the date of acceptance.
- B. Upon written notification by the Contractor, the Subcontractor shall promptly and completely repair or replace defective lining materials on site which become apparent during such 5-year period. Such repair or replacement shall be done at no cost to the Contractor. The Subcontractor shall be responsible for removal and proper disposal of all liquids, dirt, soil, or contaminated materials required to enable him to carry out the necessary repairs.
- C. The Subcontractor shall provide a written warranty that he has been approved by the liner manufacturer to perform installation of the liner.

PART 2 - PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

The liner material shall be the product of (1) a manufacturer successfully engaged in the business of manufacturing liner materials for the last five years or (2) a manufacturer meeting the requirements of Article 1.5.A above.

documentation that the intermediate and top coat paints are compatible.

3.5 FIELD QUALITY CONTROL

The Subcontractor shall cooperate in providing access for the Contractor in areas where inspection and testing is to be performed.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Measurement for payment for repairing existing county road bridge specified in this Section will be on a lump sum basis.

4.2 PAYMENT

- A. Payment for repairing existing county road bridge, including furnishing and installing structural steel, performing welding, repair work, painting and testing will be by the lump sum price quoted therefor in the Bid Schedule. The price quoted shall include full compensation for furnishing all labor, materials, equipment, tools, and accessories, and for performance of all work as shown on the Subcontract Drawings and as specified in these Specifications and accepted by the Contractor.
- B. Separate payment will not be made for any other work specified in this Section. Full compensation for such work will be considered incidental to the applicable related items of work or incidental to the Subcontract.

END OF SECTION 05275

SKETCH SRK-1
 NEW BOTTOM FLANGE REINFORCEMENT (BOTH GIRDERS)
 COUNTY BRIDGE ON C.R. S8

05275A

SUBCONTRACT DRAWINGS

2.2 MATERIAL

- A. Liner materials shall consist of high density polyethylene (HDPE) specifically compounded to conform to the material properties set forth in the National Sanitation Foundation Standard NSF 54-1991.
- B. The liner material base resin shall be unreinforced HDPE and shall contain between 2 to 3 percent carbon black as defined in ASTM D1603. The resin shall be sampled and tested prior to fabrication of the liner sheets in accordance with ASTM D1238 and D1603 to determine resin index properties and to verify consistent product quality. Resins used for weld materials shall have the same properties as the resin used for liner fabrication.
- C. The fabricated liner material shall meet the following criteria:

<u>Property</u>	<u>Test Method</u>	<u>Specification for Liner Placed in Retention Basin and Ditches</u>
Gauge	---	40 (mils nominal)
Thickness	ASTM D751	36 (mils minimum)
Density	ASTM D792	0.94 (g/cm ² minimum)

(Other tests as specified in NSF 54-1991)

- D. The liner shall have a uniform surface with no visible defects and shall be free of holes, blisters, gels, undispersed ingredients and any contamination or defect that may affect its serviceability. The liner shall be uniform in thickness with a maximum 10 percent deviation from the nominal thickness. The edges shall be straight and free of nicks and cuts. Inspection for pinholes shall be made prior to shipment to the jobsite.
- E. The liner material shall be manufactured to a minimum 15-foot seamless width. Labels on the roll shall identify the thickness, length, width, and manufacturer's mark number.

2.3 FABRICATION

The roll goods shall be factory fabricated into optimum sized panels up to 20,000 square feet, using an approved seaming

method as prescribed by the manufacturer. When the seam is tested for shear and peel, failure of the material including the seam shall not occur at the bonded surfaces.

PART 3 - EXECUTION

3.1 GENERAL

The liner systems shall be installed as shown on the Sub-contract Drawings and as recommended by the manufacturer and the fabricator.

3.2 GROUND SURFACE PREPARATION

- A. Surfaces to be lined shall be smooth and free of all rocks larger than 3/8 inch, and all roots, sharp objects, or debris of any description. The subgrade shall provide a firm, unyielding foundation for the materials, with no abrupt changes or breaks in grade. No standing water or excessive moisture will be permitted during placement. If the liner is not applied within 15 days of surface preparation, the surface shall be protected against growth of vegetation by the application of a suitable short-lived soil sterilant as approved by the Contractor. The soil sterilant used shall be compatible with the liner material to ensure that the liner is not damaged.
- B. Certification from the Installation Supervisor shall be required stating that the surface on which the liner is to be placed is acceptable. No installation of lining shall commence until this certification is furnished to the Contractor. The receiving surface shall be kept in the accepted condition until the installation of the lining is accomplished.

3.3 LINER INSTALLATION

- A. Field joints shall be made with overlapping adjacent sheets and inserting a ribbon of fusion joining resin between the overlapping sheets or over the joint between them. The minimum width of overlap of field seams for fusion welding shall be 3 inches. An alternate seaming procedure as recommended by the manufacturer or fabricator such as the hot wedge method may be proposed for the Contractor's approval. The minimum width of overlap of field seams shall be 4 inches.

1. Joints between liner sheets shall be field welded using the fabricator's fusion joining apparatus and technique. The joining procedure shall consist of softening the liner material by heated air. Directly following the application of heat, a minimum 1-1/2 inch wide hot strip of the same HDPE from which the sheet is made shall be extruded between the overlapping sheets. The overlapping sheets shall then be pressed together with a minimum pressure of 14 psi to form the fusion joint.
2. Penetrations through the liner for pipes, flashings, patches, and the like shall be field welded using a fusion joint gun. The joining procedure shall consist of softening the liner material by heated air. Directly following the application of heat, a hot strip of the same material from which the sheet is made shall be extruded over the joint to produce the fusion joint.
3. Prior to fusion joining, all areas to become joint interfaces shall be clean.
4. Fusion joining shall not take place unless the sheet is dry and shall not be attempted when the ambient temperature is below 45°F or above 90°F as determined by the Contractor.

3.4 INSPECTION AND TESTING

A. HDPE Liner:

1. All fusion joined seams shall be visually examined and probed for voids or imperfect bonds.
2. All fusion joined seams made for the HDPE liner shall be tested along their entire length using vacuum testing. Vacuum testing shall consist of placing a rectangular box (approximately 30 inches long) into the liner seam. The suction chamber shall be connected to the vacuum pump. A foaming agent shall be applied to the seam area under test to indicate possible leaks. The seam shall be maintained under 5 psig suction for a minimum of 10 seconds, and certification given to the Contractor that the seams will provide a film tearing bond. The test areas shall have a minimum of 3-inch overlap from the previous test section.
3. If the hot wedge method of seaming is approved for use as described in Article 3.3.A, the seams shall be tested by pressure testing the air channel formed by the double seam produced by the hot wedge. The method of pressure

testing shall be submitted by the Subcontractor and will be subject to the Contractor's approval.

4. Defects found during the testing shall be repaired and retested. Such tests and adjustments shall be repeated until, in the opinion of the Contractor, the repairs are satisfactory and complete. All repairs shall be made by the Subcontractor at no additional expense to the Contractor.
5. The Subcontractor shall furnish to the Contractor, on a daily basis, if requested, seam samples for testing cut from that days installation. The samples may be tested to determine strength and durability. Any seams not meeting the requirements specified herein shall be repaired by the Subcontractor at no additional expense to the Contractor.
6. The Subcontractor shall repair all areas damaged by sampling immediately after the sample is taken. The repairs shall be made at no additional expense to the Contractor.

3.5 GAS VENTS AND LINER HOLD-DOWNS

- A. Gas vents as recommended by the manufacturer and the fabricator and approved by the Contractor shall be installed in the liner around the perimeter of the basin. Vents shall have a minimum diameter of 4 inches and a maximum spacing of 50 feet on centers.
- B. Liner holddowns, as recommended by the manufacturer and the fabricator and approved by the Contractor, shall be installed over the liner on the embankment and excavation slopes. The holddowns shall be placed on maximum 30-foot centers or over every field seam, whichever is closer.
- C. The liner shall be secured to the floor of the retention basin by liner hold-downs, sandbags or other means to prevent the separation of the liner from the ground surface. Means of securing the liner to the retention basin floor shall be subject to the Contractor's approval.

3.6 ANCHORING

During installation, necessary precautions shall be taken to ensure the liner will not be damaged or moved by wind, rain or dust. The liner shall be installed in such a manner that the liner will be protected from damage or movement by wind,

water, and dust. Venting to prevent damage to the liner shall be provided in accordance with the manufacturer's recommendations.

3.7 MAINTENANCE

The Subcontractor shall maintain and if required, repair synthetic membrane to provide protection from runoff erosion and contamination.

3.8 REMOVAL AND DISPOSAL OF MEMBRANE LINER

After the completion of the construction phase or when retention basin is no longer required, the synthetic membrane shall be removed, decontaminated or demolished and disposed of by cutting into strips no greater than 3 feet by 20 feet and placing in the tailings embankment as specified in Sections 02050 and 02200 and as required by the Contractor.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

- A. Measurement for payment for furnishing, installing, demolition and disposal of membrane liner for wastewater retention basins at UC, NC and BC sites will be on a lump sum basis.
- B. Measurement for payment for preparation of subgrade will be as specified in Section 02200.
- C. Separate measurement for payment will not be made for membrane liner installed in temporary drainage ditches.

4.2 PAYMENT

- A. Payment for furnishing, installing, demolition and disposal of membrane liner for wastewater retention basins at UC, NC and BC sites will be by the lump sum price quoted therefor in the Bid Schedule. The price quoted shall include full compensation for furnishing all labor, materials, tools, equipment, Installation Supervisor, incidentals and for performing all work including, but not limited to, installation, seaming, installation of gas vents and liner hold-downs, excavating,

backfilling of anchor trenches, maintaining, removal, demolition and disposal of the liner as specified.

- B. Payment for preparation of subgrade shall be as specified in Section 02200.
- C. Separate payment will not be made for membrane liner installed in temporary drainage ditches. Full payment for such work will be considered to be included in the related items of work in the Bid Schedule.

END OF SECTION 02771

SECTION 02832

CHAIN LINK FENCE AND GATES

PART 1 - GENERAL

1.1 SCOPE

This Specification Section describes the requirements for furnishing, installing, maintaining, removing and disposing of chain link fencing including [Text Deleted]* posts, fittings, hardware, and concrete footings as shown on the Subcontract Drawings.

1.2 RELATED WORK

- A. Section 01300 - Submittals
- B. Section 02050 - Demolition

1.3 DEFINITIONS

Definitions of fencing components shall be in accordance with ASTM F552.

1.4 APPLICABLE PUBLICATIONS

- A. The Publications listed below form a part of this Specification to the extent referenced. The Publications are referred to in the text by the basic designation only:

1. Chain Link Fence Manufacturers Institute:

- a. Standards for Galvanized Steel Chain Link Fence Fabric
- b. Industrial Steel Specifications for Fence Posts, Gates, and Accessories
- c. Standards for Chain Link Fence Installation

* P.I.D. 11-S-07

2. American Society for Testing and Materials (ASTM):

- A53-90 Standard Specification for Pipe, Steel, Black and Hot-Dipped Zinc-Coated (Galvanized) Welded and Seamless (Rev. B)
- A90-81 Standard Test Method for Weight of Coating on Zinc-Coated (Galvanized) Iron or Steel Articles (R1991)
- A123-89 Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products (Rev. A)
- A153-82 Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware (R1987)
- A239-89 Standard Test Method for Locating the Thinnest Spot in a Zinc (Galvanized) Coating on Iron or Steel Articles by the Preece Test (Copper Sulfate Dip)
- A370-92 Standard Test Methods and Definitions for Mechanical Testing of Steel Products
- A392-91 Standard Specification for Zinc-Coated Steel Chain-Link Fence Fabric (Rev. A)
- C33-92 Specification for Concrete Aggregates
- C94-92 Standard Specification for Ready-Mixed Concrete (Rev. A)
- F552-88 Standard Definitions of Terms Relating to Chain Link Fencing (Rev. B)

3. State of Colorado, Department of Transportation:

- a. Standard Specification for Road and Bridge Construction, 1991 Edition, (Colorado Standard Specifications).
- b. Standard Plans, M&S Standards, November 1992 (Colorado Standard Plans)

1.5 SUBMITTALS

- A. Pursuant to the provisions of Section 01300, three prints of fully detailed shop drawings of fence, gate and hardware,

including footings and installation details, shall be submitted to the Contractor for review.

- B. Pursuant to the provisions of Section 01300, three copies of Certificates of Compliance for all fabricated materials shall be submitted to the Contractor for review.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Fencing shall include fabric, framework, concrete footings, gates, closure at grade depressions, hardware, and all appurtenances and accessories as required for a complete installation. All members, except fittings, shall be steel, hot-dip galvanized after fabrication. Fittings shall be malleable iron, wrought iron, or pressed steel, hot-dip galvanized after fabrication. Fence fabric and tension wire shall be zinc-coated as specified. Heights of fences shall be as shown on the Subcontract Drawings. Tolerance for fabric height is ± 1 inch.
- B. Fence Fabric: No. 9 gage, chain-link steel wire helically woven into 2-inch diamond mesh, hot-dip galvanized, conforming to ASTM A392. Fabric shall be twisted and barbed on the top selvage and knuckled on the bottom selvage. Loops of knuckled selvage shall be closed or nearly closed with a space not exceeding the diameter of the wire. The twisted wire shall be twisted in a closed helix of 1-1/2 machine turns equivalent to three full twists, and cut at an angle to provide sharp barbs. The wire ends beyond the twist shall be at least 1/4-inch long. Steel wire for the fabric, when drawn to the wire gage specified, shall have a minimum tensile strength of 75,000 pounds per square inch when tested in accordance with ASTM A370. Coating of fabric shall be Class II, 2.0 ounces of hot-dip zinc galvanizing per square foot of uncoated wire surface. The weight of coating shall be determined in accordance with the requirements of ASTM A90. The Standard length of fabric roll shall be 50 linear feet ± 1 percent. Each roll shall be a one-piece length. Tolerance for fabric heights shall be plus or minus 1 inch.
- C. Posts:
 - 1. Post shall be Schedule 40 galvanized pipe or equal. Use shall be in accordance with the following table except as noted on the Subcontract Drawings. All pipe shall conform to ASTM A53 for weight and galvanized coating.

Line posts shall be spaced at no more than 10-foot centers.

<u>Post Type and Shape</u>	<u>Nominal Pipe Size, Inches</u>
2. End, Corner and Pull Posts: Round	2.5
3. Intermediate or Line Posts: Round	2.0
4. Gate Posts: Single Leaf Gate Opening Width:	
6 Feet and Less: Round	2.5
6 to 13 Feet: Round	3.5
13 to 18 Feet: Round	6.0
Over 18 Feet: Round	8.0
D. Post-Bracing Assembly: Horizontal braces shall be 1-1/4 inch Schedule 40 steel pipe, conforming to ASTM A53. Diagonal truss type braces shall be 3/8-inch diameter galvanized steel rods with turnbuckle adjustment. Couplings, fittings, and attachment accessories shall be included as required. Horizontal braces (intermediate rails) shall be provided at all corners, terminals, pulls, and at gate posts.	
E. Wire Ties and Clips: Wire ties or clips shall be provided for attaching fabric to line posts, top rail, or tension wire. Wire ties and clips shall be at intervals not greater than 15 inches when attaching fabric to line posts, and the space interval shall not exceed 24 inches when attaching fabric to top rails or tension wire. Wire ties and clips shall be not less than the fabric wire gage size and of the same material and coatings. The minimum weight for zinc coated wire ties and clips is 0.8 ounces of zinc per foot of coated surface area.	
F. Tension Wire, Zinc-Coated Steel: Tension wire for top and bottom edge support of fence fabric shall be No. 7 gage marcelled or crimped coil spring hard tempered carbon steel wire with minimum tensile strength of 70,000 psi, and zinc coating of not less than 1.20 ounce per square foot of coated area.	

- G. Post Caps: Post caps shall be standard malleable iron, wrought iron, or pressed steel, galvanized, designed as a weathertight closure cap for tubular posts.
- H. Stretcher Bars: Stretcher bars shall be one-piece lengths equal to full height of fabric with a minimum cross-section of 3/16 inch by 3/4 inch. Provide one stretcher bar for each gate and end post, and 2 for each corner and pull post.
- I. Stretcher Bar Bands: Bands shall be heavy pressed steel, or malleable iron, spaced not over 15 inches on center to secure stretcher bars to end, corner, pull, and gate posts.
- J. Gates:

1. Gates shall be of chain link fabric, single- or double-leaf swing type as shown on the Subcontract Drawings and furnished complete with all hardware and accessories as required. The size of the gate shall be measured in terms of the length of the horizontal clear distance between the gate posts.
2. Gate Frames: Frames shall be round pipe to match posts in accordance with the following table:

<u>Gate Size</u>	<u>Nominal Pipe Size</u>
Leaf Width	
8 Feet or Less:	
Round	1-1/4 Inch Schedule 40
Leaf Width	
Over 8 Feet:	
Round	1-1/2 Inch Schedule 40

3. Fabrication of Gates: Assemble gate frames by welding or with fittings and rivets for rigid connections. When fittings are used as the construction method for gate frames, the frames shall be fitted with 5/16-inch minimum diameter truss rods. The frames shall be zinc-coated after fabrication. When frames are not zinc-coated after fabrication the welds shall be coated with a zinc rich paint. Use same fabric as for fence. Install fabric with stretcher bars at vertical edges, and tie wires at top and bottom edges. Attach stretcher bars to gate frame at not more than 15 inches on center. Attach hardware with rivets or by other means which will provide security against removal or breakage. Provide additional horizontal and vertical members to ensure proper gate operation and for attachment of fabric, hardware, and accessories. Provide diagonal crossbracing consisting of

3/4-inch diameter adjustable length truss rods on gates where necessary to provide frame rigidity without sag or twist. All gates shall be constructed so that they may be operated by one person.

4. Gate Hardware: Provide the following hardware and accessories for each gate:

- a. Gate Hinges: Gate hinges shall be of adequate strength for the gate, and shall have large bearing surfaces for clamping or bolting in position. Hinge action shall be such that gates may be easily opened and closed by one person. Hinges shall provide for full 180° swing of gate leaf.
- b. Latch: Forked type or plunger-bar type to permit operation from either side of gate. Provide padlock eye as integral part of latch. Locking devices shall be constructed so that the center drop rod or plunger bar cannot be raised when locked.
- c. Keeper: Provide keeper, which automatically engages the gate leaf and holds it in the open position until it is manually released, for each gate leaf.
- d. Double Gates: Provide gate stops for double gates, consisting of mushroom type or flush plate with anchors. Set in concrete to engage the center drop rod or plunger bar. Provide locking device and padlock eyes as an integral part of the latch, requiring one padlock for locking both gate leaves.

K. Accessories: Furnish all miscellaneous materials and accessories, ties, clips, anchors and fastenings as required for a complete installation. Unless otherwise specified, all ferrous items shall be hot dip zinc-coated with an average weight of not less than 1.2 ounces of zinc per square foot of coated surface area.

L. Galvanizing:

- 1. Fence and gate framework, hardware and appurtenances shall be hot dip galvanized per ASTM A53, A123, or A153 as applicable.
- 2. Galvanizing of wire fabric shall be after weaving in accordance with ASTM A392, immersions when tested in accordance with ASTM A239.

2.2 FABRICATION

Chain link fencing shall be fabricated and pre-assembled by the manufacturer in the factory or shop as far as practicable.

2.3 CONCRETE

Concrete: ASTM C94; minimum 2500 psi, 3-inch to 5-inch slump and maximum 1-inch size aggregate. The Subcontractor shall submit a mix design to the Contractor for approval.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Installation of fencing shall be in accordance with the Subcontract Drawings, shop drawings, and the manufacturer's detailed installation drawings, instructions, and recommendations. All posts shall be plumb and rigid after installation. Chain-link fabric shall be smooth and uniformly stretched tight and straight. Tension wires shall be pulled taut.
- B. Chain-link fabric shall be extended to provide approximately 4 inches clearance to the surfaces of grade depressions, drainage swales or ditches. The extended fabric shall be the same piece of the fencing material or a piece of fabric securely attached or welded to adjacent fabric of the fencing. A stretcher bar shall be provided through the vertical height of the fence at the lowest point in the depression to stiffen the extended fabric. The stretcher bars shall be threaded through and attached to the fabric by wire ties. At drainage ditches or swales, no line posts shall be installed within 5 feet of the centerline of the drainage ditches or swales. Line posts shall be spaced evenly from the centerline of the ditch or swale.
- C. Gates shall be installed plumb, level, and secure for full opening without interference. Install ground-set items in concrete for anchorage as recommended by the fence manufacturer. Adjust hardware for smooth operation and lubricate. Gates shall operate smoothly and easily to minimize noise.

- D. All posts shall be embedded into concrete except intermediate or line posts, which may be mechanically driven 3'6" into the ground, as shown on the Subcontract Drawings.
- E. Dimensions of drill holes for post footings and concrete embedment of the posts shall be as shown on the Subcontract Drawings.
- F. Line posts shall be spaced at no more than 10-foot centers.
- G. Corner posts shall be installed at all changes in direction where the deflection angle exceeds 30 degrees.

3.2 CONCRETE PLACEMENT

Concrete shall be placed around posts in a continuous pour. Each post shall be checked for vertical and top alignment, and shall be held in position during placement and finishing operations.

3.3 MAINTENANCE AND REMOVAL

The fence [Text Deleted]* constructed under the Subcontract shall be maintained during the term of the Subcontract and later removed and disposed of as Subcontractor's property when no longer required as determined by the Contractor.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

[Measurement for payment for furnishing, installing and removing chain link fence at petroglyph site at UC site will be by the linear feet of fence installed and removed as shown on the Subcontract Documents and as accepted by the Contractor.]* Measurements will be made along the top of the fence to the nearest foot.

4.2 PAYMENT

[Payment for furnishing, installing and removing chain link fence at petroglyph site at UC site will be by the unit price per linear foot quoted therefor in the Bid Schedule.]*

* P.I.D. 11-S-07

Payment shall include full compensation for performing all work involved in constructing, maintaining, removing and disposing of fences [Text Deleted]*, including any clearing, stripping, tree removal, excavation, concrete or cement, complete in place, as shown on the Subcontract Drawings and as accepted by the Contractor.

END OF SECTION 02832

* P.I.D. 11-S-07

Document No. 3885-SRK-S-01-02433-04
Issued for Construction-Revision 2
Chain Link Fence and Gates

SRK

02832 - 9

WP51
022195

SECTION 02835
DEER FENCE AND GATES

PART 1 - GENERAL

1.1 SCOPE

This Specification Section describes the requirements for furnishing, installing, maintaining and removing deer fence including gates, posts, fittings and hardware as noted on the Subcontract Drawings and as specified in this Section.

1.2 RELATED WORK

- A. Section 02832 - Chain Link Fence and Gates
- B. Section 02836 - Smooth Wire Fence and Gates

1.3 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this Specification to the extent applicable:

1. State of Colorado, Department of Transportation:

- a. Standard Specifications for Road and Bridge Construction, 1991 Edition, (Colorado Standard Specifications).
- b. Standard Plans, M & S Standards, November 1992, (Colorado Standard Plans).

1.4 SUBMITTALS

Pursuant to the provisions of Section 01300, three black-line or blue-line prints and a reproducible transparency of fully detailed drawings of fence, gate and hardware, including footings and installation details, shall be submitted to the Contractor for review.

PART 2 - PRODUCTS

2.1 MATERIALS

A. The materials shall conform to the following:

1. Colorado Standard Specifications, Sections 607.02, 710.01, 710.02 and 710.07, as applicable.

a. Colorado Standard Specifications, Section 607.02, Materials: Materials shall meet the requirements specified in the following subsection of Section 700 - Materials:

Barbed Wire	710.01
Woven Wire	710.02
Fence Posts	710.07

2. Colorado Standard Plans, Drawings M-607-4, sheets 1 and 2, entitled Deer Fence and Gate, as applicable.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Installation of fencing shall be in accordance with the applicable portions of the Colorado Standard Plans and Section 607.03 of the Colorado Standard Specifications and as specified below:

1. Colorado Standard Specifications, Section 607.03, Construction Requirements:

a. Wire or fencing of the size and type required shall be firmly attached to the posts and braces in the manner indicated in Colorado Standard Plan M607-4. All wire shall be stretched taut and be installed to the required spacing.

B. Installation of the deer gate shall be in accordance with the applicable portions of the Colorado Standard Plans.

3.2 MAINTENANCE AND REMOVAL

The fence and gates constructed under the Subcontract shall be maintained during the term of the Subcontract and later removed and disposed of as Subcontractor's property when no longer required as determined by the Contractor.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Measurement for payment for furnishing, installing and removing deer fence and gates at UC, NC and BC sites will be by the linear feet of fence installed and removed as shown on the Subcontract Drawings and as accepted by the Contractor. Measurement will be made along the top of the fence to the nearest foot.

4.2 PAYMENT

Payment for furnishing, installing and removing deer fence and gates at UC, NC and BC sites will be by the unit price per linear foot quoted therefor in the Bid Schedule. The price quoted shall include full compensation for performing all work, including but not limited to, furnishing and installing fence and gates, clearing, stripping, tree removal, excavation, maintenance, removal and disposal of deer fence and gates.

END OF SECTION 02835

SECTION 02836

SMOOTH WIRE FENCE AND GATES

PART 1 - GENERAL

1.1 SCOPE

This Specification Section describes the requirements for furnishing, installing, maintaining, removal and disposal of smooth wire fence as shown on the Subcontract Drawings and as specified in this Section.

1.2 APPLICABLE PUBLICATIONS

- A. The Publications listed below form a part of this Specification to the extent referenced. The Publications are referred to in the text by the basic designation only:

1. American Society for Testing and Materials (ASTM):

A116-88	Standard Specification for Zinc-Coated (Galvanized) Steel Woven Wire Fence Fabric
A121-92	Standard Specification for Zinc-Coated (Galvanized) Steel Barbed Wire (Rev. A)
C33-92	Standard Specification for Concrete Aggregates
C94-92	Standard Specification for Ready-Mixed Concrete (Rev. A)
C150-92	Standard Specification for Portland Cement

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Fencing shall include smooth wire, posts, and all appurtenances and accessories required for complete installation.

- B. Wire shall be minimum 12-1/2 gage galvanized steel wire conforming to the requirements of ASTM A116 coating. The height shall be 47 inches consisting of two horizontal wires with vertical stays spaced 6 inches apart.
- C. Line post shall be tee, channel or U-bar shape, 1.33 lbs. per foot.
- D. Braces shall be 1-1/4-inch Schedule 40 steel pipe, or steel angle section, 2 x 2 x 1/4 inches.
- E. End, corner and pull posts shall be 2-inch Schedule 40 steel pipe, or steel angle section 2-1/2 x 2-1/2 x 1/4 inches.
- F. Hardware for connecting members shall conform to commercial standards.
- G. Gates shall be fabricated as shown on the Subcontract Drawings and as approved by the Contractor. The gates shall be durable and sufficiently strong to prevent entry of livestock.

2.2 CONCRETE

Concrete: Minimum 2500 psi and maximum 1-inch size aggregate. The Subcontractor shall submit a mix design to the Contractor for approval.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Smooth wire fence shall be constructed in accordance with the details shown on the Subcontract Drawings unless otherwise directed by the Contractor.
- B. Line posts shall be set plumb and to the depth and spacing shown on the Subcontract Drawings.
- C. Fence wire shall be stretched by mechanical stretcher or other device designed for such use. The length between pull posts shall not exceed 660 feet.
- D. Gates shall be installed as approved by the Contractor. Gates shall be installed plumb, level and secure for full opening without interference.

3.2 MAINTENANCE AND REMOVAL

The fence constructed under the Subcontract shall be maintained during the term of the Subcontract and later removed and disposed of as Subcontractor's property when no longer required unless otherwise approved by the Contractor.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

Measurement for payment for furnishing, installing and removing smooth wire fence and gates at UC, NC and BC sites will be by the linear feet of fence and gates installed as shown on the Subcontract Drawings. Measurements will be made along the top of the fence to the nearest foot.

4.2 PAYMENT

Payment for furnishing, installing and removing smooth wire fence and gates at UC, NC and BC sites will be by the unit price per linear foot quoted therefor in the Bid Schedule. Payment shall include full compensation for furnishing all labor, tools, equipment, and incidentals, and for performing all work involved in constructing fence, including any clearing, stripping, tree removal, excavation, concrete or cement, complete in place, including maintenance, removal and disposal, as shown on the Subcontract Drawings and as accepted by the Contractor.

END OF SECTION 02836

SECTION 02935

SEEDING

PART 1 - GENERAL

1.1 SCOPE

This Specification Section covers seeding for final site grades at UC, NC, and BC sites, permanent spoil and stockpile areas at the BC site, and restoration of Disappointment Valley borrow area as indicated on the Subcontract Drawings.

1.2 MATERIAL STORAGE

- A. Seeds shall be stored in sealed waterproof containers in a cool, dry, rodent proof location and shall be kept out of direct sunlight until ready for use.
- B. Fertilizer, if required, shall be delivered and stored in waterproof containers which shall show the chemical analysis and name of manufacturer.

PART 2 - PRODUCTS

2.1 SEED MIX

- A. The following seed mix shall be used for seeding of final grades at the UC and NC mill sites, the BC disposal site including spoil area, and the Disappointment Valley borrow site.

[<u>Seed Species</u> <u>Scientific Name</u>		<u>Seeding Rate Pure Live Seed (Pounds Per Acre)</u>
Thickspike Wheatgrass	Agropyron Dasystachyum	3.0
Indian Ricegrass	Oryzopsis Hymenoides	2.0
Arizona Fescue	Festuca Arizonensis	3.0
Fourwing Saltbush	Atriplex Canescens	2.0
Small Burnet	Sanguisorba Minor	<u>3.0</u>
Total		13.0]*

* P.I.D. 11-S-07

- B. The seeding rates shown are for drill applied. These rates shall be increased by 100 percent if broadcasting method of application is used. Hydroseeding shall not be used.

2.2 ACCEPTANCE OF SEED

- A. The Subcontractor shall only use seed which has been certified by the Colorado Department of Agriculture. Seed containers or bags shall have the official blue tag that clearly states "CERTIFIED SEED".
- B. Seed shall be tested according to Association of Official Seed Analysts, International Seed Testing Association, and Federal Seed Act Standards. Tested seed shall be accompanied by certificate of analysis furnished by a certified testing laboratory.
- C. Individual seed types shall be certified as tested for the following:
 - 1. Purity and Germination: Seed stored over 6 months from the date of the original acceptance test shall be retested for germination, and results resubmitted for approval, before seed is used.
 - 2. Prohibited Noxious Weed Seed: Seed shall contain no Federal or State listed prohibited noxious weed seed (an amount within the tolerance of zero percent) as determined by a standard purity test.
 - 3. Restricted Noxious Weed Seed: Seed shall contain no more than 40 seeds per pound of any single species, or 150 seeds per pound of all species combined of restricted noxious weed seed. Restricted noxious weed seed is considered as a component of other crop and weed seed with limitations specified.
 - 4. Weed Seed: Seed shall contain no more than one percent by weight of weed seed of other crops and plant species as determined by standard purity tests.
- D. The Subcontractor shall furnish the Contractor, for approval prior to final acceptance, duplicate copies of a statement by the vendor certifying that each lot of seed has been tested by a certified testing laboratory for seed testing within 6 months of date of delivery. This statement shall include: (1) name and address of laboratory; (2) date of test; (3) lot number for each kind of seed; and (4) results of tests as to name, percentages of purity and of germination, and percentages of weed content, for each kind of seed furnished,

and, in case of a mixture, the pure live seed proportions of each kind of seed as specified herein.

- E. Final acceptance of seed will be made by the Contractor based on the following: Seed shall be furnished separately or in mixture in standard sealed containers or bags with the following information provided by the seed vendor on each seed container label: (1) seed name; (2) lot number; (3) total net weight and pure live seed weight for each kind of seed; (4) percentages of purity and of germination; (5) seed coverage, in acres, on a pure live seed basis; and (6) percentage of maximum weed seed content clearly marked for each kind of seed. Seeds shall be packaged by the vendor in even acre coverage containers.

2.3 WATER

Water used in the planting or care of vegetation shall be free of concentrations of oils, acids, alkalies, salts, or any substance that is injurious to plant life.

2.4 FERTILIZER

Fertilizer, if required, shall be a standard commercial grade that provides the minimum percentage of available nutrients as determined by the soils fertility analysis specified in Article 3.1.E. Fertilizer shall be furnished in new, clean, and sealed containers with the name, weight, and guaranteed analysis of contents clearly marked. A liquid form of fertilizer providing the nutrients as determined by the soils fertility analysis specified in Article 3.1.E may be used. If the fertilizer is delivered in bulk, the Subcontractor shall submit to the Contractor, for each load, a certificate from the manufacturer or supplier indicating compliance with the above requirements.

2.5 MULCH

Mulch shall consist of native or locally grown grass hay or hydromulch. Grass hay shall be free from all viable seed, mold or other objectionable material. Mulch shall be in an air-dry condition and suitable for placing with mulch blower equipment. Final acceptance of mulch will be by the Contractor.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Timing of Seeding: All final grades not covered by gravel or riprap shall be seeded as soon as practical after their completion or as directed by the Contractor. Seeding shall be completed within a few days of the preparation of the seedbed before weeds became established or erosion modifies the tilth and contour of the seedbed. Seeding materials shall not be applied during windy weather, when the ground is excessively wet or frozen, or when snow is present. For best results seeding during the period September 1 to December 15 or prior to prolonged ground frost is recommended.
- B. Grading and Seedbed Preparation: Before applying seed in a given area, any stockpiled topsoil and select fill shall be put in place and the area shall be graded as shown on the Subcontract Drawings, with surfaces sloping gradually towards drainage courses, with no enclosed low spots where water can accumulate. Areas to be seeded that have been damaged by erosion or other causes shall be restored prior to seeding and the seedbed prepared using the disc and pack method to provide a reasonably firm seedbed. Soils that have been over-compacted by traffic or equipment, especially when wet, shall be tilled to break up rooting restrictive layers, and then harrowed, rolled or packed to prepare the required firm seedbed. A minimum of 6 inches of surface soil shall be in a loose condition at the time of fertilizer and seed application.
- C. If soils have insufficient depth or have physical characteristics unsuitable for development of vegetation, topsoil or soil material having the capability of supporting the planned vegetative planting shall be brought in and spread over the deficient areas. The material shall be applied uniformly in sufficient depth to support the type and quality of vegetative cover planned for the site. Source of materials shall be subject to approval of the Contractor.
- D. Seeding installation will not be required over exposed rock surfaces.
- E. Fertilizer Requirements: Micronutrient fertilizer requirements, if any, shall be determined by laboratory soils fertility analysis of representative soil samples from the processing site and disposal site. The Subcontractor shall collect representative soil samples and have them analyzed by a certified soil laboratory. A copy of the laboratory report

shall be submitted to the Contractor for approval prior to application of fertilizer or seed.

3.2 APPLICATION

- A. Seed shall be applied by a drill on all slopes of 3 (horizontal) to 1 (vertical) or flatter. Broadcasting shall be used on steeper slopes, if necessary. Seed shall be applied to a depth of 0.50 to 0.75 inch and at a spacing of not more than 7 inches. The drill shall have the capability of applying the type and rate of seed being planted, as approved by the Contractor. To the greatest extent possible, seeding shall be oriented along (parallel to) land contours. For slopes too steep or soils too moist to use a drill, a mechanical broadcaster may be used and the seed incorporated into the soil by raking, harrowing, or other method approved by the Contractor.
- B. As soon as possible in the same day that seed has been applied, mulch shall be applied at a rate of 1 ton per acre to all areas seeded, and the mulch shall be crimped with a mulch crimper.

3.3 CARE DURING CONSTRUCTION

The Subcontractor shall be responsible for protecting and caring for areas seeded before final acceptance of the work. The Subcontractor shall repair any damage to seeded areas caused by erosion or construction operations without additional compensation.

3.4 PLANT ESTABLISHMENT

The Subcontractor shall be responsible for watering and caring for seeded areas, as required, until adequate vegetative cover is established. Reseeding, if required, will be at no additional cost to the Contractor.

PART 4 - MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

- A. Measurement for payment for seeding at UC, NC and BC sites will be by the acres of surfaces actually seeded and approved at the UC, NC and BC sites and for restoration of the

Disappointment Valley borrow site. Quantities shall be computed from the horizontal projection of the seeded plane.

- B. Separate measurement for payment will not be made for any incidental products, work and services, including but not limited to, placing topsoil, preparing the surface, applying fertilizer, mulching, watering, and erosion repair related to seeding.
- C. Separate measurement for payment will not be made for any seeding required along the access roads right-of-ways or for access road retardation.

4.2 PAYMENT

Payment for seeding at UC, NC and BC sites will be by the unit price per acre quoted therefor in the Bid Schedule. The price quoted shall include full compensation for furnishing all materials, tools, equipment, incidentals, labor, and for performing all work specified herein for complete work.

END OF SECTION 02935

SECTION 05275

MODIFICATION AND REPAIR OF COUNTY ROAD BRIDGE

PART 1 - GENERAL

1.1 SCOPE

- A. This Specification Section describes modification and repair work required for San Miguel County Bridge on County Road S-8 over the Delores River. The bridge is a welded girder, with composite deck. The girder plates are stitch welded. The modifications and repair to the bridge include the following:

- [1. Visual inspection of all welds including flange-to-web, cover plate-to-bottom flange and stiffeners to web to check for cracks. The welds shall have the paint removed prior to inspection. Cracked welds shall be repaired by grinding to base metal and rewelding.]*
2. Surface preparation of steel including paint removal in all areas requiring welding.
3. Addition of fillet welding on all flange-to-web and cover plate-to-bottom flange welds in order to provide a continuous fillet weld between web and flange and between bottom flange and cover plate as shown on the Subcontract Drawings. [All welding shall be performed per AWS D1.1-94 using E60XX electrodes.]*
4. Addition of structural channel steel members to the cover plate of the bottom flange with continuous welds as shown on the Subcontract Drawings.
- [5. Visual inspection of all new welds per AWS D1.1 is required. Magnetic particle testing shall be performed on all new and existing flange-to-web, cover plate to bottom flange, channel to cover plate, and any stiffener to web welds repaired per Article 1.1.A.1. Magnetic particle testing shall be performed using an AC yoke in accordance with ASME Section V.]*
6. Sandblasting or grinding of the rusted bearing at the south abutment and preparing the surface for welding a new steel plate to the bearing.

* P.I.D. 11-S-06

7. Welding a new steel plate to the existing bearing at the south abutment for reinforcement. The steel plate shall be 4-inch x 4-inch x 1/2-inch thick.
- [8. Hand-loose bolts shall be replaced with the existing size and grade and tighten in accordance with American Institute of Steel Construction (AISC).]*
9. Applying an intermediate field coat to new steel surfaces.
10. Applying new top coat to all steel surfaces of the bridge.

1.2 RELATED WORK

Section 01300 - Submittals

1.3 WORK NOT INCLUDED

Repair or replacement of concrete deck, if required, is not included in this Specification.

1.4 APPLICABLE PUBLICATIONS

A. The Publications listed below form a part of this Specification to the extent referenced. The Publications are referred to in the text by the basic designation only.

1. American Society for Testing and Materials (ASTM):

A36-93 Standard Specification for Structural Steel
(Rev. A)

2. American Welding Society (AWS):

D1.1-94 Structural Welding Code, Steel

3. State of Colorado, Department of Transportation (CDOT), Standard Specifications for Road and Bridge Construction - 1991.

* P.I.D. 11-S-06

1.5 QUALITY ASSURANCE

- A. All work shall be subject to inspection by the Contractor.
- B. Welding shall be performed in accordance with AWS D1.1 and CDOT Standard Specifications.
- C. Intermediate field coat and top coat shall be applied in accordance with CDOT Standard Specifications.

1.6 SUBMITTALS

- A. Certificates of Compliance for Structural Steel and Paint.
- B. Certificates for qualified welders.
- [C. Results of final visual weld inspection reports and magnetic particle weld inspection reports.]*
- D. Results of inspection and tests on existing paint and new paint.
- E. General submittal requirements are specified in Section 01300.

1.7 TESTS

- A. Contractor Testing: Inspection, coring, testing and evaluation of the concrete bridge decking will be performed by an independent laboratory retained by the Contractor.
- B. Subcontractor Testing:
 - 1. Inspection and non-destructive testing of all welds performed by the Subcontractor will be performed by a qualified independent laboratory retained by the Subcontractor.
 - 2. The Subcontractor shall sample and test existing paint on the bridge for lead constituents, prior to beginning repair work. If laboratory tests determine that lead is present in the existing paint, then the Subcontractor shall develop a work plan, using appropriate hazardous material mitigating procedures, for removal and disposal of the lead paint and to protect workers. The work plan shall be submitted to the Contractor and shall be subject to approval.

* P.I.D. 11-S-06

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Structural channel steel (MC10x41.1) shall conform to the requirements of ASTM A36.
- B. The steel plate for bearing reinforcement on the south abutment shall conform to the requirements of ASTM A36.
- C. The intermediate field coat and top coat shall be alkyd paint, Alternative 1, as specified in Section 708.03 of the CDOT Standard Specifications for Road and Bridge Construction.
- D. Paint shall be of a color that most closely matches the existing paint color as approved by the Contractor and shall be compatible with the existing paint.

PART 3 - EXECUTION

3.1 COORDINATION OF WORK

During the repair work, the bridge will be used by the Contractor and the public. The Subcontractor shall plan and coordinate the work to avoid disruptions to others.

3.2 SURFACE PREPARATION FOR WELDING

Existing structural steel surfaces which will be welded shall be prepared by sandblasting or other means down to bare metal to the surface condition required by AWS D1.1.

3.3 SURFACE PREPARATION FOR INTERMEDIATE COAT

Prior to applying intermediate coat, all adhering dirt, grease, and foreign matter shall be removed. Rust and scale shall be removed to bare metal. The existing surfaces shall be prepared for intermediate coat in accordance with the paint manufacturer's recommendations.

3.4 TOP COAT APPLICATION

After applying intermediate coat, the bridge shall be painted with one top coat. The Subcontractor shall submit written

**UNITED
DEPARTMENT**

**UM
URANIUM MILL T
ACTION**

CONSTRUCTI

SLICK ROC

UNITED STATES DEPARTMENT OF ENERGY

TRAP

TAILINGS REMEDIAL PROJECT

ON DRAWINGS

SLICK ROCK, COLORADO

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO
UNLESS THE ORIGINAL SIGNATURE APPEARS HERE.

QA REVIEWED FOR
QUALITY REQUIREMENTS
BY: *[Signature]*
05/23/94

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO									
DESIGNED <i>[Signature]</i>	DRAWN <i>[Signature]</i>	SLICK ROCK SITE SLICK ROCK, COLORADO TITLE SHEET							
CHECKED <i>[Signature]</i>									
INSPECTED <i>[Signature]</i>									
RECOMMENDED <i>[Signature]</i>									
APPROVED <i>[Signature]</i>	DATE 5/24/94	DATE 5/24/94	DATE 5/24/94	DOE PROJECT ENGINEER <i>[Signature]</i>	DATE 6/10/94	PROJECT NO. DE-AC04-83AL18796			
MORRISON KNUDSEN CORPORATION UMTRA PROJECT						DRAWING NO. GRK CE 12 0701			
5/10/94 ISSUED FOR CONSTRUCTION						REV.			

LIST OF DRAWINGS

	DRAWING NO.	DRAWING TITLE
GENERAL	SRK-GE-10-0301	TITLE SHEET
	SRK-GE-10-0302	LOCATION MAP, VICINITY MAP AND LIST OF DRAWINGS
	SRK-GE-10-0303	PROCESSING SITES, DISPOSAL SITE AND BORROW SITES LOCATION MAP
	SRK-GE-10-0304	PROPOSED BORROW SOURCES SITE PLANS
	SRK-GE-10-0305	FENCE AND GATE DETAILS
UNION CARBIDE PROCESSING SITE	SRK-PS-10-0310	SITE PLAN AND CONSTRUCTION FACILITIES
	SRK-PS-10-0311	EXISTING UTILITIES AND DEMOLITION PLAN
	SRK-PS-10-0312	TEMPORARY SITE DRAINAGE PLAN
	SRK-PS-10-0313	TEMPORARY DRAINAGE DITCHES SECTIONS AND DETAILS
	SRK-PS-10-0314	ACCESS CONTROL AREA PLAN, SECTIONS AND DETAILS
	SRK-PS-10-0315	WASTEWATER RETENTION BASIN SECTIONS AND DETAILS
	SRK-PS-10-0316	CONTAMINATED MATERIAL EXCAVATION PLAN
	SRK-PS-10-0317	FINAL SITE GRADING PLAN
NORTH CONTINENT PROCESSING SITE	SRK-PS-10-0318	BORINGS AND TEST PITS LOCATION PLAN
	SRK-PS-10-0320	SITE PLAN AND CONSTRUCTION FACILITIES
	SRK-PS-10-0321	ACCESS ROADS AND FACILITIES
	SRK-PS-10-0322	EXISTING UTILITIES AND DEMOLITION PLAN
	SRK-PS-10-0323	CONTAMINATED MATERIAL EXCAVATION PLAN
	SRK-PS-10-0324	FINAL SITE GRADING PLAN
	SRK-PS-10-0325	BORINGS AND TEST PITS LOCATION PLAN
BURRO CANYON DISPOSAL SITE	SRK-DS-10-0330	ACCESS PLAN
	SRK-DS-10-0331	SITE PREPARATION AND TEMPORARY DRAINAGE FACILITIES
	SRK-DS-10-0332	ACCESS CONTROL FACILITIES AND WASTEWATER RETENTION BASIN PLAN
	SRK-DS-10-0333	WASTEWATER RETENTION BASIN AND MISC. SECTIONS AND DETAILS
	SRK-DS-10-0334	TAILINGS EMBANKMENT AND FINAL SITE GRADING PLAN
	SRK-DS-10-0335	TAILINGS EMBANKMENT SECTIONS AND DETAILS (SHEET 1 OF 2)
	SRK-DS-10-0336	TAILINGS EMBANKMENT SECTIONS AND DETAILS (SHEET 2 OF 2)
	SRK-DS-10-0337	TAILINGS EMBANKMENT EROSION PROTECTION
	SRK-DS-10-0338	BORINGS AND TEST PITS LOCATION PLAN
	SRK-DS-10-0339	EMBANKMENT STAND PIPES

THIS SEAL IS NOT VALID IN THE STATE OF NEW MEXICO
UNLESS THE ORIGINAL SIGNATURE APPEARS HERE

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO

DESIGNED R.F.C.	DRAWN B.J.L.
CHECKED A. BAHAM	
INSPECTED J.S. RAMON	
RECOMMENDED R.F. CLARE	

SLICK ROCK SITE
SLICK ROCK, COLORADO
**LOCATION MAP, VICINITY MAP AND
LIST OF DRAWINGS**

APPROVED
P.M. CHEN

DATE
5/24/94

D. BOLTON
5/24/94

C. RICKETTS
5/24/94

DOE PROJECT ENGINEER
R. EDGE

DATE
8/10/94

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UMTRA PROJECT

PROJECT NO.

DE-AC04-83AL18796

DRAWING NO.

REV.

REVISED PER PID 11-S-03 AND PID 11-S-07

ISSUED FOR CONSTRUCTION

AMS JSR DJL DAB RWC

	$\triangle$
	$\triangle$
	$\triangle$
250	$\triangle$
planks	$\triangle$
studied	$\triangle$
QA	NR

	△
	△
	△
30	△
31	△
32	△
33	△
34	△
35	△
36	△
37	△
38	△
39	△
40	△
41	△
42	△
43	△
44	△
45	△
46	△
47	△
48	△
49	△
50	△
51	△
52	△
53	△
54	△
55	△
56	△
57	△
58	△
59	△
60	△
61	△
62	△
63	△
64	△
65	△
66	△
67	△
68	△
69	△
70	△
71	△
72	△
73	△
74	△
75	△
76	△
77	△
78	△
79	△
80	△
81	△
82	△
83	△
84	△
85	△
86	△
87	△
88	△
89	△
90	△
91	△
92	△
93	△
94	△
95	△
96	△
97	△
98	△
99	△
100	△

NOTES:

1. RADON BARRIER MATERIAL SHALL BE OBTAINED FROM THE BURRO CANYON DISPOSAL SITE AS SPECIFIED.
2. ASSUMED COORDINATE SYSTEM IS TAKEN FROM THE SURVEY CONDUCTED BY M. H. SMITH, R.L.S. 10738, ESTABLISHING HORIZONTAL AND VERTICAL CONTROL FOR THE SLICK ROCK SITES.
3. AT THE DOLORES RIVER BORROW SITE THE TOPSOIL SHALL BE STRIPPED AND STOCKPILED WITHIN THE SITE BOUNDARIES.
4. AFTER REMOVAL OF MATERIAL, THE BORROW SITE SHALL BE REGRADED TO DRAIN. FINAL SLOPES SHALL NOT BE STEEPER THAN FIVE (5) HORIZONTAL TO 1 VERTICAL. THE FINAL GRADE AT THE DOLORES RIVER SITE SHALL DRAIN TOWARD THE RIVER.
5. AFTER FINAL GRADING AT THE DOLORES RIVER SITE, TOPSOIL SHALL BE REPLACED IN UNIFORM THICKNESS AND SEEDED. THE DOLORES RIVER SITE SHALL BE PLANTED WITH COMMERCIAL CRESTED-WHEAT SEED IN ACCORDANCE WITH SUPPLIERS' RECOMMENDATION.
6. A POWER LINE CROSSES THE DOLORES RIVER BORROW AREA. EXCAVATIONS SHALL BE AT LEAST 20 FEET AWAY FROM THE BASE OF THE UTILITY POLES.
7. EXISTING ROADS ADJACENT TO THE BORROW AREAS SHALL BE MAINTAINED AND KEPT OPEN TO THE PUBLIC.
8. UC BORROW AREA CONTAINS LARGE COBBLES AND GRAVEL THAT MAY BE COMBINED WITH MATERIAL FROM THE DOLORES RIVER BORROW SITE TO PRODUCE THE REQUIRED RIPRAP SIZE. SEE DWG. NO. SRK-PS-10-0318 FOR BORING AND TEST PIT LOCATIONS.
9. NO MORE THAN 3,500 CY MAY BE REMOVED FROM THE UC SITE FOR USE AS RIPRAP AND BEDDING MATERIAL.

REFERENCE DRAWINGS:

- SRK-GE-10-0303 PROCESSING SITES, DISPOSAL SITE AND BORROW SITES LOCATION MAP
- SRK-PS-10-0318 BORINGS AND TEST PITS LOCATION PLAN

LEGEND:

- ⊕ TEST PIT (1986)
- ⊕ TEST PIT (1987)
- 3500 --- ESTIMATED CONTOURS
- FLOW LINE

U. S. DEPARTMENT OF ENERGY									
ALBUQUERQUE, NEW MEXICO									
SLICK ROCK SITE									
SLICK ROCK, COLORADO									
PROPOSED BORROW SOURCES									
SITE PLANS									
DESIGNED	DRAWN								
CHKD	11/2								
CHECKED	ALM								
INSPECTED	J.S. Rando								
RECOMMENDED	Robert A. Chen								
APPROVED	PK Chen	DATE	5/24/94	5-24-94	DOB PROJECT ENGINEER	DATE	6/11/94		
MORRISON KNUDSEN CORPORATION									
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP									
UMTRA PROJECT									
180 HOWARD ST. SAN FRANCISCO, CA 94105									
PROJECT NO.									
DE-AC04-83AL18796									
DRAWING NO.									
SRK-GE-10-0304									
REV.									
1									

DATE	REVISIONS	BY	CK	EDD	ENG.	QA	DOE
				MGR.	MGR.	MGR.	APP.
7/93	REVISED PER PID 11-S-03 AND PID 11-S-07	AMS	JSR	JH	DB	AE	
7/94	ISSUED FOR CONSTRUCTION	-	-	-	-	-	-

QA REVIEWED FOR QUALITY REQUIREMENTS BY *[Signature]* 11/2

CORNER OR
TERMINAL
POST

STRETCHER
BAR BAND

STRETCHER BAR
LACED THRU EDGE
OF MESH FABRIC

1'-0" MIN.
DIAMETER

CHAIN LINK FENCE
TYPICAL PULL POST ASSEMBLY
NOT TO SCALE

END POST
NOT T

DATE 05-20-94

FILENAME 388576/SRKCE305.DGN

TWIN DRIVEWAY GATES
NOT TO SCALE

630
11/11/94
C.S.
05/22/94
QA
10/1/94

CHAIN LINK FENCE
TYPICAL CORNER AND TERMINAL DETAIL
 NOT TO SCALE

NOTES:

1. MINOR ADJUSTMENTS TO DETAILS SHOWN WILL BE ACCEPTABLE IN ORDER TO CONFORM TO LOCAL STANDARD PRACTICE.
2. SMOOTH WIRE FENCE END, CORNER POST AND EVERY SIXTH LINE POST (EVERY 150 FEET FENCE LENGTH) SHALL BE PROVIDED WITH BRACES. ANCHOR SHOWN ON THE DRAWING SHALL BE SECURELY FASTENED TO EACH LINE POST TO RESIST MOVEMENT. ALL POSTS SHALL BE DRIVEN WITHOUT CONCRETE FOOTING TO EMBEDMENT DEPTHS SHOWN.
3. HOLES IN END POSTS, CORNER POSTS, LINE POSTS WITH BRACE AND BRACES SHALL ACCOMMODATE 1/2" DIA GALVANIZED MACHINE BOLTS.
4. LINE POST SHALL BE "U" OR "STUDDED TEE" STEEL POST AS DIRECTED BY THE CONTRACTOR.
5. WOVEN WIRE FENCE SHALL BE INSTALLED ALONG THE POSTS AND FASTENED WITH WIRE TIES.
6. THE PLASTIC FILTER CLOTH SHALL BE SECURED TO THE TOP OF THE FENCE WITH WIRE TIES OR HOG RINGS AND THE BOTTOM SHALL BE ENTRENCHED ALONG THE BASE OF THE FENCE AND STABILIZED WITH ROCK.
7. SUBCONTRACTOR MAY USE HAY BALES IN LIEU OF SILT FENCE AS APPROVED BY CONTRACTOR.
8. GATE MATERIAL SHALL BE GALVANIZED STEEL OR ALUMINUM.

SMOOTH WIRE FENCE
 NOT TO SCALE

END POST TIE
 NOT TO SCALE

TYPICAL SILT FENCE DETAIL
 NOT TO SCALE

TIES FOR "STUDDED TEE" OR "U" POSTS
 NOT TO SCALE

TH BRACING
 SCALE

U. S. DEPARTMENT OF ENERGY
 ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE
 SLICK ROCK, COLORADO

FENCE AND GATE DETAILS

DESIGNED
 R.F.C.
 CHECKED
 A. BANANI
 INSPECTED
 J.S. RANDENI
 RECOMMENDED
 R.F. CLAIRE

APPROVED
 P.K. CHEN

DATE
 5/24/94

D. BOLTON
 5/24/94

C. RICKETTS
 5/24/94

DOE PROJECT ENGINEER
 R. EDGE

DATE
 6/10/94

MORRISON KNUDSEN CORPORATION
 ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
 UMTRA PROJECT
 180 HOWARD ST. SAN FRANCISCO, CA 94105

PROJECT NO.
 DE-AC04-83AL18796
 DRAWING NO.
 SPK-CE-10-0305
 REV. 1

DATE	REVISION	BY	CHK	DES	ENG	QA	DOE
11/16/94	REVISED AS PER PID 11-5-01	JSR	AMB	DM	SB	CR	MS
12/1/94	ISSUED FOR CONSTRUCTION	-	-	-	-	-	-

E 61,000

(2)

TABLE 1
PROPERTY OWNERSHIPS
(SEE NOTE 6)

NO.	OWNERSHIPS NAMES
2	BUREAU OF LAND MANAGEMENT
3	ROSE, TROY J. AND IONE F.
4	REDD, PAUL DAVID
6	UMETCO MINERAL CORP.
7	ROCKY MOUNTAIN NATURAL GAS COMPANY

NOTES:

1. THE PETROGLYPH SITE LOCATED ON THE CLIFF FACE WEST OF THE COUNTY ROAD BRIDGE IS DESCRIBED IN UMTRA ARCHEOLOGICAL REPORT NO. 24. INFORMATION TO BIDDERS. A CHAIN LINK FENCE APPROXIMATELY 370 FEET IN LENGTH SHALL BE ERRECTED OUTSIDE THE LIMIT OF CONTAMINATION TO PROTECT THE PETROGLYPH SITE ON THE CLIFF FACE. FINAL LOCATION SHALL BE DETERMINED IN THE FIELD.
2. SITE BOUNDARY SHOWN IS FOR PROJECT DESCRIPTION PURPOSES ONLY. ACTUAL CONSTRUCTION MAY EXTEND BEYOND SITE BOUNDARIES.
3. SITE BOUNDARY AND COORDINATES ARE FROM THE SURVEY CONDUCTED BY M.H. SMITH, R.L.S. 10738, ESTABLISHING HORIZONTAL AND VERTICAL CONTROL FOR THE SLICK ROCK SITES.
4. NO FENCE POSTS SHALL BE INSTALLED WITHIN GAS LINE R.O.W. TEMPORARY STAYS SHALL BE USED TO SUPPORT THE WIRE.
5. SEE INFORMATION FOR BIDDERS FOR THE BEARINGS OF SITE BOUNDARY AND FOR THE LOCATIONS OF BRASS SURVEY CAPS.
6. PROPERTY OWNERSHIP SHOWN ON DRAWINGS ARE AS OF FEB. 1993.
7. SEE DRAWING NO. SRK-GE-10-0305 FOR FENCING DETAILS.
8. PROPERTY BOUNDARY AND SITE BOUNDARY COINCIDE AT GAS PLANT.
9. SEE INFORMATION FOR BIDDERS FOR LOCATION OF GAS LINE R.O.W.
10. COORDINATES AND ELEVATIONS ARE TAKEN FROM INFORMATION FOR BIDDERS. SUBCONTRACTOR SHALL INDEPENDENTLY VERIFY DATA.
11. SUBCONTRACTOR SHALL PROVIDE AND INSTALL DEER FENCE AND GATES AROUND ALL WATER RETENTION PONDS INCLUDING RETENTION BASINS, RECIRCULATION PONDS AND CONSTRUCTION WATER STORAGE PONDS AS APPROVED BY THE CONTRACTOR.

REFERENCE DRAWINGS:

- SRK-GE-10-0305 FENCE AND GATE DETAILS
 SRK-PS-10-0312 TEMPORARY SITE DRAINAGE PLAN
 SRK-PS-10-0314 ACCESS CONTROL AREA
 PLAN, SECTIONS AND DETAILS

LEGEND:

- SITE BOUNDARY (SEE NOTE 3)
 - - - - - APPROXIMATE LIMITS OF TAILINGS PILES
 - - - - - APPROXIMATE LIMITS OF WINDBLOWN/WATERBORN CONTAMINATED MATERIALS OUTSIDE SITE BOUNDARY FENCE
 ● AIR PARTICULATE (AP) STATION
 ▲ RADON GAS MONITOR (RGM) STATION
 ⊙ BRASS SURVEY CAP SET IN CONCRETE (EXISTING)
 — PROPERTY LINE
 (3) PROPERTY OWNERSHIPS
 SEE TABLE 1

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF NEW MEXICO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

200 0 200 400
 SCALE FEET

U. S. DEPARTMENT OF ENERGY
 ALBUQUERQUE, NEW MEXICO

DESIGNED R.F.C. DRAWN B.M.
 CHECKED ALJ.M. BAHAM
 INSPECTED J. S. RAHMAN
 RECOMMENDED R.F. CLARE

APPROVED P. K. CHEN

DATE 5/24/94

D. BOLTON 5/24/94

C. RICKETTS 5/24/94

DOE PROJECT ENGINEER R. EDGE

DATE 6/10/94

MORRISON KNUDSEN CORPORATION
 ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
 UMTRA PROJECT
 180 HOWARD ST. SAN FRANCISCO, CA 94105

PROJECT NO.
 DE-AC04-83AL18796

DRAWING NO.
 SRK-PS-10-0310

REV. 1

DATE	REVISION	BY	CK	CHK	CHK	QA	DOC
11/15/94	REVISED AS PER PID 11-S-01	SRK	ANG	DM	DB	CR	RR
12/10/94	ISSUED FOR CONSTRUCTION	-	-	-	-	-	-

NOTES:

1. LOCATION OF ROCKY MOUNTAIN NATURAL GAS TRANSMISSION LINE IS APPROXIMATE. ACTUAL LOCATION TO BE DETERMINED IN THE FIELD BY ROCKY MOUNTAIN NATURAL GAS COMPANY.
2. ROCKY MOUNTAIN NATURAL GAS PIPELINE IS BURIED APPROXIMATELY 2' - 2 1/2', EXCEPT UNDER THE COUNTY ROAD WHERE THE DEPTH IS 4' - 5'. PORTIONS OF ABANDONED UTILITIES WITHIN THE GAS LINE RIGHT OF WAY SHALL REMAIN.
3. NOT ALL BURIED ABANDONED UTILITIES WITHIN THE PROCESSING SITE AREA HAVE BEEN LOCATED. ABANDONED WATER, SEWAGE, GAS LINES AND ELECTRIC CONDUIT THAT ARE NOT SHOWN ON THIS DRAWING MAY BE ENCOUNTERED DURING CONSTRUCTION.
4. UTILITIES SHOWN ARE FOR INFORMATION ONLY. A PLAN FOR RELOCATION OF EXISTING UTILITIES SHALL BE SUBMITTED BY THE SUBCONTRACTOR AND APPROVED BY THE CONTRACTOR, AS PER SECTION 01300 OF THE SPECIFICATIONS.
5. SEE SECTION 02050 OF SPECIFICATIONS FOR ITEMS TO BE DEMOLISHED.
6. FIREHOUSE AND PROPANE TANK (UC31) AND WOODEN SHED (UC43) SHALL REMAIN INTACT.
7. EXISTING FENCES SHALL BE REMOVED EXCEPT FOR FENCES AROUND GAS PLANT, FLARE PIT, AND TRAILER PAD AREA. NO DEMOLITION SHALL BE DONE INSIDE THE GAS PLANT BOUNDARY.
9. ALL ABANDONED ABOVE GROUND UTILITIES ARE TO BE REMOVED.
10. BURIED UTILITIES WEST OF COUNTY ROAD 59 AND WITHIN SHADED AREA SHALL REMAIN IN PLACE.
11. NO DEMOLITION SHALL BE DONE IN UC42 EXCEPT AS NOTED IN NOTE 9.
12. ALL ABANDONED UMETCO OVERHEAD ELECTRIC LINES ARE TO BE REMOVED NORTH OF POWER POLE AT N 58,682, E 59,688. POLE SHALL BE ADEQUATELY BRACED OR CUYED PRIOR TO REMOVAL OF LINES.

LEGEND:

- *--- EXISTING FENCE
- A--- UNDERGROUND ALARM CABLE
- E--- OVERHEAD ELECTRIC LINES (UNLESS NOTED OTHERWISE)
- G--- UNDERGROUND GAS LINES
- T--- UNDERGROUND TELEPHONE (OPTIC FIBERS)
- SS--- SEWER SYSTEM
- W--- UNDERGROUND WATER
- UC9 CONTRACTOR'S DESCRIPTIVE NUMBERING SYSTEM. FOR DESCRIPTION OF STRUCTURE OR AREA SEE INFORMATION FOR BIDDERS
- AREAS WHERE UNDERGROUND UTILITIES ARE TO REMAIN
- ⊗ FIRE HYDRANT

NOTE: THIS DRAWING IS THE PROPERTY OF THE STATE OF COLORADO. IT IS TO BE USED ONLY FOR THE PROJECT FOR WHICH IT WAS PREPARED. IT IS TO BE RETURNED TO THE STATE OF COLORADO WHEN NO LONGER NEEDED. UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO

DESIGNED
RFC
CHECKED
A. BANANI
INSPECTED
J.S. RANDEN
RECOMMENDED
ROBERT F. CLAIRE

APPROVED
P.K. CHEN

DATE
5/24/94

D. BOLTON
5/24/94

C. RICKETTS
5/24/94

DOE PROJECT ENGINEER
R. EDGE

DATE
6/10/94

SLICK ROCK SITE SLICK ROCK, COLORADO UNION CARBIDE PROCESSING SITE EXISTING UTILITIES AND DEMOLITION PLAN

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UMTRA PROJECT
110 HOWARD ST., SAN FRANCISCO, CA 94102

PROJECT NO.
DE-AC04-83AL18796

DRAWING NO.
SRK-PS-10-0311

REV.

REVISED PER PD 11-5-07

ISSUED FOR CONSTRUCTION

BY VTC/VN

REV. 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100

DATE 11-15-94

FILENAME 388576.dwg

3.30
11/15/94
C.A.
06/97
04

NOTES:

1. AREAS BETWEEN DITCH 1 AND DIKE 1, THAT ARE LOWER THAN ELEVATION 5434.0 SHALL BE BACKFILLED AND GRADED TO DRAIN INTO THE RETENTION BASIN.
2. THE RETENTION BASIN BERM, ON THE RIVER SIDE, BETWEEN DITCH 1 AND DIKE 1, SHALL BE AT EL. 5434.5. THE BENCH ON THE PILE SIDE, BETWEEN DITCH 1 AND DIKE 1, SHALL BE AT EL. 5434.0.
3. SUBCONTRACTOR SHALL PROVIDE FOR POSITIVE DRAINAGE TOWARD THE RETENTION BASIN OR MAKE PROVISIONS AND REMOVE WATER FROM ANY PONDED AREA.
4. SUBCONTRACTOR SHALL PROVIDE FOR AND MAINTAIN POSITIVE DRAINAGE.
5. ALONG EXISTING COUNTY ROAD, BOTTOM OF DRAINAGE PATH SHALL BE MIN. 1' BELOW TOP OF THE ROAD.
6. SUBCONTRACTOR SHALL GRADE ROAD TO PROVIDE POSITIVE DRAINAGE TOWARD TEMPORARY DITCHES. BEGIN LOCATION OF TEMPORARY DITCHES AT APPROXIMATE LOCATIONS AS SHOWN. EXACT LOCATIONS SHALL BE DETERMINED IN THE FIELD BY THE SUBCONTRACTOR.
7. ROAD SHALL BE TEMPORARILY CLOSED TO ALLOW FOR TEMPORARY DITCH CROSSING. ROAD SHALL BE RESTORED AT END OF CONSTRUCTION.
8. THE ACTUAL LOCATION MAY BE ADJUSTED BY THE CONTRACTOR TO BETTER FIT THE FIELD CONDITION.
9. EXISTING COUNTY ROAD CR-58 SHALL BE DETOURED TO LOCATION SHOWN UNTIL AREA SOUTH OF THE FENCE IS REMEDIATED AND DEMOLITION DEBRIS IS REMOVED.
10. TEMPORARY ROAD DETOUR SHALL BE 20' WIDE, GRADED AND MAINTAINED. NO SURFACE COURSE IS REQUIRED.
11. AFTER AREA SOUTH OF FENCE IS REMEDIATED, COUNTY ROAD CR-58 SHALL BE RECONSTRUCTED ALONG THE ORIGINAL ALIGNMENT.
12. SUBCONTRACTOR SHALL PROVIDE AND INSTALL DEER FENCE AND GATES AROUND ALL WATER RETENTION PONDS INCLUDING RETENTION BASINS, RECIRCULATION PONDS AND CONSTRUCTION WATER STORAGE PONDS AS APPROVED BY THE CONTRACTOR.

REFERENCE DRAWINGS:

- SRK-PS-10-0313 TEMPORARY DRAINAGE DITCHES SECTIONS AND DETAILS
- SRK-PS-10-0314 ACCESS CONTROL AREA SECTIONS AND DETAILS
- SRK-PS-10-0315 WASTEWATER RETENTION BASIN SECTIONS AND DETAILS

LEGEND:

- DRAINAGE DITCH
- SURFACE FLOWPATH

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

U.S. DEPARTMENT OF ENERGY
ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE
SLICK ROCK, COLORADO
UNION CARBIDE PROCESSING SITE
TEMPORARY SITE DRAINAGE
PLAN

DESIGNED
RFC
CHECKED
A. M. BANANE
INSPECTED
J. S. RANDEN
RECOMMENDED
R. F. CLARE

APPROVED
P. K. CHEN

DATE
5/24/94

D. BOLTON
5/24/94

C. ROCKETTS
5/24/94

DOE PROJECT ENGINEER
R. EDGE

DATE
6/11/94

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UMTRA PROJECT

PROJECT NO.
DE-AC04-83AL18796

DRAWING NO.

REV.

11/16/94	REVISED AS PER PID 11-5-01	JSR	AMB	DMJ	DC	CP	RR
12/10/94	ISSUED FOR CONSTRUCTION	-	-	-	-	-	-

1. NO FILL SHALL BE PLACED WITHIN 10' OF SEASONAL HIGH WATER LEVEL FOR THE DOLORES RIVER.

SRX-PS-10-0312 TEMPORARY SITE DRAINAGE PLAN
SRX-PS-10-0315 WASTEWATER RETENTION BASIN
SECTIONS AND DETAILS

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO
UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

[illegible]

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO			
DESIGNED <i>RP</i>	DRAWN S.M.	SLICK ROCK SITE SLICK ROCK, COLORADO UNION CARBIDE PROCESSING SITE	
CHECKED <i>AL</i>		INSPECTED <i>J.S. Kunkle</i>	
PERMANENT <i>7/14/74</i>		TEMPORARY DRAINAGE DITCHES SECTIONS AND DETAILS	
APPROVED <i>OK Chen</i>	DATE <i>5/24/74</i>	PROJECT ENGINEER <i>5/24/74</i>	DATE <i>4/1/74</i>
MORRISON KNUDSEN CORPORATION ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP ULTRA PROJECT 10000 F. RD. DUBLINO, CA 94568		PROJECT NO. DE-AC04-83AL18796 DRAWING NO. SDX-PS-02-0313

PLAN
ACCESS CONTROL AREA
(SEE DWG. NO. SRK-PS-10-0310)

DATE 11-18-94

FILENAME 308576\SRKUC314.DGN

63
uh
8.4
1.0

NOTES:

1. ACCESS CONTROL AREA SHALL BE CONSTRUCTED AFTER REMOVAL OF THE CONTAMINATED MATERIAL WITHIN THE AREA. CONTAMINATED MATERIAL SHALL ALSO BE REMOVED FROM ALL OFFICE FACILITIES AND TRAILER AREA PRIOR TO CONSTRUCTION OF THESE FACILITIES.
2. ALL EXCAVATED CUT SLOPES SHALL BE AS REQUIRED FOR STABILITY BUT NO STEEPER THAN 2(H):1(V), UNLESS OTHERWISE INDICATED.
3. ADJACENT AREAS SHALL BE GRADED TO PROVIDE DRAINAGE FOR ACCESS CONTROL AREA.
4. THE SECTIONS AND DETAILS SHOWN MAY BE ADJUSTED BY THE SUBCONTRACTOR AS REQUIRED FOR HIS OR HER OPERATIONS, SUBJECT TO CONTRACTOR'S APPROVAL.
5. DUMMY GROOVE JOINTS SHALL BE FORMED OR SAWED IN THE CONCRETE PAVEMENT FOR DECON PAD AT A MAXIMUM SPACING OF 15 FEET.
6. CONSTRUCTION JOINTS, IF REQUIRED, SHALL BE LOCATED AT DUMMY GROOVE JOINTS ONLY. DOWEL BARS SHALL BE LUBRICATED BEFORE RESUMPTION OF PAVING.
7. THE SECTIONS AND DETAILS OF THE DECONTAMINATION PAD AND WASH WATER RECIRCULATION BASIN SHOWN ARE A SAMPLE DESIGN ONLY. SUBCONTRACTOR SHALL SUBMIT DETAILED DESIGN OF DECONTAMINATION FACILITIES FOR APPROVAL.
8. THE SUMP SHALL BE CONSTRUCTED OF REINFORCED CONCRETE AND BE DESIGNED SO A BACKHOE OR FRONT END LOADER CAN EASILY REMOVE THE SEDIMENTS.
9. LOCATION OF TRAILERS IN THE ACCESS CONTROL AREA SHALL BE SUBJECT TO THE CONTRACTOR'S APPROVAL.
10. CONTRACTOR MAY REVISE ALIGNMENT AND LOCATION OF TURNING RADIUS OF ACCESS RAMP.
11. SUBCONTRACTOR SHALL PROVIDE AND INSTALL DEER FENCE AND GATES AROUND ALL WATER RETENTION PONDS INCLUDING RETENTION BASINS, RECIRCULATION PONDS AND CONSTRUCTION WATER STORAGE PONDS AS APPROVED BY THE CONTRACTOR.

REFERENCE DRAWINGS:

- SRK-GE-10-0305 FENCE AND GATE DETAILS
- SRK-PS-10-0310 SITE PLAN AND CONSTRUCTION FACILITIES
- SRK-PS-10-0312 TEMPORARY SITE DRAINAGE PLAN
- SRK-PS-10-0315 WASTEWATER RETENTION BASIN SECTIONS AND DETAILS

LEGEND:

- 4" AGGREGATE COVERED SURFACE
- CONCRETE PAVEMENT

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW

NO	DATE	REVISION	BY	CHKD	APPD	QA	DOC
1	11/16/94	REVISED AS PER PID 11-S-01	SC	AMB	DMA	DB	CP
2	12/10/94	ISSUED FOR CONSTRUCTION	-	-	-	-	-

U.S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO			
DESIGNED RFC		DRAWN B.H./M.Z.	
CHECKED A. BAHAM		SLICK ROCK SITE SLICK ROCK, COLORADO UNION CARBIDE PROCESSING SITE	
INSPECTED J.S. RAMOS		ACCESS CONTROL AREA PLAN, SECTIONS AND DETAILS	
RECOMMENDED R.F. CLARE		PROJECT NO. DE-AC04-83AL18796	
APPROVED P.K. CHEN		DATE 5/24/94	DATE 5/24/94
DATE 5/24/94		C. RICKETTS 5/24/94	DOE PROJECT ENGINEER R. EDGE 5/10/94
MORRISON KNUDSEN CORPORATION ENVIRONMENTAL GROUP UMTRA PROJECT			
DRAWING NO. CDK-DC-10-0311		REV.

NOTES:

1. SQUARE TRENCH ALTERNATE MAY BE USED.

REFERENCE DRAWINGS:

SRK-PS-10-0312 TEMPORARY SITE DRAINAGE PLAN

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO			
SLICK ROCK SITE SLICK ROCK, COLORADO UNION CARBIDE PROCESSING SITE			
WASTEWATER RETENTION BASIN SECTIONS AND DETAILS			
DESIGNED J. S. Lundgren	DRAWN B. J. H. / MZ	CHECKED A. C. M. / B	INSPECTED J. S. Lundgren
APPROVED P. K. Chan	DATE 5/24/94	PROJECT ENGINEER G. Russell Ely	DATE 6/10/94
MORRISON KNUDSEN CORPORATION ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP UMTRA PROJECT		PROJECT NO. DE-AC04-83AL18796	
ISSUED FOR CONSTRUCTION		DRAWING NO.

DATE 05-10-84
FILENAME 388378.WPLOT37.097

UNTRA PROJECT

15/10/74	ISSUED FOR CONSTRUCTION
----------	-------------------------

NOTES:

- SEE INFORMATION FOR BIDDERS FOR WELL BORING AND TEST PIT LOGS AND COORDINATES.

LEGEND:

- 506 MONITOR WELLS
- ◆ 552 MONITOR WELLS (JACOBS, 1989)
- ⊕ 768 BORINGS (1986)
- ⊕ SRU-D10 BORINGS (1987)
- 125 BORINGS (JACOBS, 1985)
- ⊕ 212 BORINGS (JACOBS, 1989)
- △ 735 PIEZOCONES (1966)
- ⊕ 785 TEST PITS (1986)
- ⊕ SRU-D11 TEST PITS (1987)

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

100 0 100 200
SCALE FEET

QA REVIEWED FOR
QUALITY REQUIREMENTS
BY: J. S. Kandel

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE SLICK ROCK, COLORADO UNION CARBIDE PROCESSING SITE BORINGS AND TEST PITS LOCATION PLAN

DESIGNED BY: B.J.L.
CHECKED BY: J.S. Kandel
INSPECTED BY: J.S. Kandel
RECOMMENDED BY: J.S. Kandel
APPROVED BY: J.S. Kandel

DATE: 5/24/94
PROJECT NO.: DE-AC04-83AL18796

DATE: 5/24/94

DOE PROJECT ENGINEER: J. S. Kandel

DATE: 6/10/94

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UNTRA PROJECT

PROJECT NO. DE-AC04-83AL18796

DRAWING NO. REV.

ISSUED FOR CONSTRUCTION

NOTES:

- SUBCONTRACTOR SHALL OBTAIN ALL PERMITS TO WIDEN THE NC SITE HAUL ROAD TO TWO LANES FROM STATE HIGHWAY 141 TO N 56,700, AND FROM N 57,500 TO NC SITE ACCESS GATE.
- SUBCONTRACTOR SHALL REPLACE OR EXTEND ALL EXISTING CULVERTS AS REQUIRED BY THE COUNTY AND THE CONTRACTOR.
- SUBCONTRACTOR MAY ADJUST ALIGNMENT AND LOCATION OF TURNING RADIUS OF ACCESS ROAD TO THE NC SITE.
- THE SECTIONS AND DETAILS OF THE WASH WATER RETENTION BASIN SHOWN ARE SAMPLE DESIGNS ONLY. THE SECTIONS AND DETAILS MAY BE ADJUSTED BY THE SUBCONTRACTOR AS REQUIRED FOR HIS OR HER OPERATIONS SUBJECT TO CONTRACTOR'S APPROVAL.
- SEE DWG NO. SRK-PS-10-0314 FOR TYPICAL CONSTRUCTION AND CONTRACTION JOINT DETAILS FOR THE DECONTAMINATION PAD.
- STORAGE TANKS MAY BE USED IN LIEU OF A MEMBRANE LINED RECIRCULATION BASIN.
- LOCATION OF TRAILERS IN THE ACCESS CONTROL AREA SHALL BE SUBJECT TO THE CONTRACTOR'S APPROVAL.
- SUBCONTRACTOR SHALL PROVIDE AND INSTALL DEER FENCE AND GATES AROUND ALL WATER RETENTION PONDS INCLUDING RETENTION BASINS, RECIRCULATION PONDS AND CONSTRUCTION WATER STORAGE POUNDS AS APPROVED BY THE CONTRACTOR.

ACCESS CONTROL FACILITY

REFERENCE DRAWINGS:

- SRK-PS-10-0314 ACCESS CONTROL AREA PLAN, SECTIONS AND DETAILS
 SRK-PS-10-0315 WASTEWATER RETENTION BASIN, SECTIONS AND DETAILS
 SRK-PS-10-0320 SITE PLAN AND CONSTRUCTION FACILITIES

LEGEND:

—T— EXISTING BURIED TELEPHONE LINE

SECTION B

TYPICAL SECTION A

NOT TO SCALE

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE
 SLICK ROCK, COLORADO
 NORTH CONTINENT PROCESSING SITE

ACCESS ROADS AND FACILITIES

DESIGNED T.P.	DRAWN BH
CHECKED R.C. Ba	
INSPECTED T.S. Randem	
RECOMMENDED T.H. Law	
APPROVED P.K. Chen	

DATE
5/24/94

DATE
5-24-94

DATE
5/24/94

DATE
4/14/94

PROJECT NO.

DE-AC04-83AL18796

MORRISON KNUDSEN CORPORATION
 ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
 UMTRA PROJECT

DRAWING NO.

LINE

ISSUED FOR CONSTRUCTION

FILENAME 388378.BRNG322.DGN
DATE 01-28-84

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100

NOTES:

1. C.S.P. MANHOLES ARE APPROXIMATELY 3 FEET TO 4 FEET DEEP APPARENTLY INTERCONNECTED WITH TERRA COTTA PIPE. THE C.S.P. SHALL BE REMOVED AND THE HOLES BACKFILLED WITH UNCONTAMINATED MATERIAL.
2. UNDERGROUND UTILITIES MAY BE LEFT IN PLACE IF UNCONTAMINATED.
3. ALL ABANDONED OVERHEAD ELECTRICAL LINES AND POLES BETWEEN N 58,178, E 62,467 AND N 58,373, E 64,055 SHALL BE REMOVED. EXISTING POLES AT THESE LOCATIONS SHALL BE BRACED OR GUYED BEFORE REMOVING LINES.

LEGEND:

- CSP M.H. CORRUGATED STEEL PIPE MANHOLE
- E— OVERHEAD ELECTRIC LINES
- T— UNDERGROUND TELEPHONE (FIBER OPTICS)
- NC CONTRACTOR DESCRIPTIVE NUMBERING SYSTEM, FOR DESCRIPTION OF STRUCTURE OR AREA SEE INFORMATION FOR BIDDERS
- FORMER HOUSING SITES, NO APPARENT DEMOLITION MATERIAL

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

CA REVIEWED
QUALITY REQUIREMENTS
BY *[Signature]*

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE
SLICK ROCK, COLORADO
NORTH CONTINENT PROCESSING SITE
**EXISTING UTILITIES
AND DEMOLITION PLAN**

DESIGNED *[Signature]* DRAWN *[Signature]*
CHECKED *[Signature]*
INSPECTED *[Signature]*
RECOMMENDED *[Signature]*
APPROVED *[Signature]*

DATE *5/24/94* PROJECT ENGINEER *[Signature]* DATE *5/10/94*

MORRISON KNUDSEN CORPORATION
BIOENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UNITRA PROJECT
80 HOWARD ST. SAN FRANCISCO, CA 94108

PROJECT NO. **DE-AC04-83AL18796**
DRAWING NO. **SRK-PS-10-0322** REV. **0**

NO.	DATE	REVISION	BY	CK	CHK	CHK	CA	DOE
1		ISSUED FOR CONSTRUCTION						
2								
3								
4								
5								
6								
7								
8								
9								
10

NOTES:

1. ALL CUTS SHALL BE 20H:KV UNLESS OTHERWISE NOTED.
2. DEPTHS AND LIMITS OF CONTAMINATED MATERIALS SHOWN ARE APPROXIMATE AND WILL BE CONFIRMED BY THE CONTRACTOR DURING CONSTRUCTION. BOTTOM GRADES OF EXCAVATION FOR CONTAMINATED MATERIAL MAY VARY FROM THOSE SHOWN AND MAY BE MORE IRREGULAR.
3. HEAVY EQUIPMENT SHALL OPERATE NO CLOSER THAN 5' TO POWER LINE POLES WHICH REMAIN. CONTAMINATED MATERIAL AROUND THE POLES SHALL BE EXCAVATED BY HAND. POLES SHALL BE BRACED IF NECESSARY. THE AREA AROUND THE POLES SHALL BE RESTORED TO ORIGINAL GRADE FOR A MINIMUM DISTANCE OF 5' AROUND EACH POLE.
4. ALL REMOVAL OF CONTAMINATED MATERIALS SHALL BE DONE DURING THE MONTHS OF MAY AND JUNE ONLY.
5. INSTALL A SILT FENCE ALONG THE DOLORES RIVER AS APPROVED BY THE CONTRACTOR. THE FINAL LOCATION WILL BE DETERMINED IN THE FIELD. SEE DWG. NO. SRK-GE-10-0305 FOR SILT FENCE DETAIL.
6. ROCK MAY BE ENCOUNTERED UNDER THE TAILINGS PILE AND OTHER AREAS. SEE NOTE 8.
7. ALL CONTAMINATED SOIL ON EXPOSED OR EXCAVATED ROCK SURFACES SHALL BE REMOVED. THIS MAY REQUIRE HAND EXCAVATION OR WASHING DOWN TO REMOVE ALL SURFACE CONTAMINATION. THE LIMITS OF CONTAMINATED MATERIALS ON ROCK SURFACES WILL BE DETERMINED IN THE FIELD.
8. CONTAMINATED MATERIALS FROM THE N.C. SITE SHALL BE STOCKPILED AT A LOCATION AS DETERMINED BY THE CONTRACTOR IN THE B.C. SITE IF THE DISPOSAL CELL EXCAVATION IS NOT READY FOR PLACEMENT OF CONTAMINATED MATERIAL.

REFERENCE DRAWINGS:

SRK-GE-10-0305 FENCE AND GATE DETAILS

LEGEND:

- SILT FENCE
- ESTIMATED LIMIT AND DEPTH IN FEET OF CONTAMINATED MATERIAL
- EXISTING POWER POLES TO REMAIN

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

QA REVIEWED FOR QUALITY REQUIREMENTS BY J. H. Chisum

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE SLICK ROCK, COLORADO NORTH CONTINENT PROCESSING SITE CONTAMINATED MATERIAL EXCAVATION PLAN

DESIGNED BY J. H. Chisum
CHECKED BY J. H. Chisum
INSPECTED BY J. H. Chisum
RECOMMENDED BY J. H. Chisum

APPROVED BY J. H. Chisum

DATE 5-24-94

PROJECT NO. DE-AC04-83AL18796

DATE 6/10/94

PROJECT NO. DE-AC04-83AL18796

DATE 6/10/94

PROJECT NO. DE-AC04-83AL18796

DATE 6/10/94

PROJECT NO. DE-AC04-83AL18796

DATE 6/10/94

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UMTRA PROJECT

PROJECT NO. DE-AC04-83AL18796
DRAWING NO. SRK-GE-10-0305
REV.

DATE 11-15-94

FILENAME 3085761500130a.DGN

630
11/15/94
G.D.
6/2/94
QA
MK-F

DETAIL 1

100 0 100 200
SCALE FOOT

TYP. SECTION A
NOT TO SCALE

NOTES:

1. SUBCONTRACTOR SHALL REPLACE OR EXTEND EXISTING CULVERT.
2. SUBCONTRACTOR TO DETERMINE ALIGNMENT AND LOCATION OF TURNING RADIUS OF ACCESS ROAD.
3. EXCAVATION LIMITS SHOWN ARE A MINIMUM, SUBCONTRACTOR MAY EXCAVATE BELOW LIMITS SHOWN UPON APPROVAL OF CONTRACTOR.
4. SEE INFORMATION FOR BIDDERS FOR DESCRIPTION OF SITE.
5. ALL WORK FROM HIGHWAY 141 R.O.W. IS ON BLM LAND.
6. OVERHEAD ELECTRIC LINES WITHIN THE DISPOSAL SITE BOUNDARY SHALL BE RELOCATED BY OTHERS AS REQUIRED.
7. SEE INFORMATION FOR BIDDERS FOR LOCATION OF PIPELINE R.O.W.
8. THE ACCESS ROAD SHALL HAVE A MINIMUM WIDTH OF 40 FEET AND A MINIMUM SURFACE COURSE OF 6" OF GRAVEL AS APPROVED BY CONTRACTOR. THE ACCESS ROAD SHALL BE WITHIN 50 FEET OF E. OF EXISTING ROAD. AT THE END OF REMEDIATION THE HAUL ROAD SHALL BE RESTORED TO ORIGINAL WIDTH AND DAMAGED AREAS REGRADED AND RESEED.

REFERENCE DRAWINGS:

- SRK-DS-10-0331 SITE PREPARATION AND TEMPORARY DRAINAGE FACILITIES
- SRK-DS-10-0332 ACCESS CONTROL FACILITIES AND WASTEWATER RETENTION BASIN
- SRK-DS-10-0334 TAILINGS EMBANKMENT AND FINAL SITE GRADING PLAN

LEGEND:

- E— OVERHEAD ELECTRIC LINE
- ARCHEOLOGICAL SITE (SEE NOTE 4)
- EXISTING FENCE

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

QA REVIEWED FOR
QUALITY REQUIREMENTS
BY: G. DOTTLE 6/22/94

U. S. DEPARTMENT OF ENERGY
ALBUQUERQUE, NEW MEXICO

DESIGNED
RFC

DRAWN
RGS

CHECKED
A. BANANI

INSPECTED
J.S. RANDENI

RECOMMENDED
R.F. CLAIRE

SLICK ROCK SITE
SLICK ROCK, COLORADO
BURRO CANYON

ACCESS PLAN

APPROVED
P.K. CHEN

DATE
5/24/94

C. RICKETTS
5/24/94

DATE PROJECT ENGINEER
R. EDGE

DATE
6/10/94

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UMTRA PROJECT
180 HOWARD ST. SAN FRANCISCO, CA 94105

PROJECT NO.
DE-AC04-83AL18796

DRAWING NO.
SRK-DS-10-0330

REV.
1

NO.	DATE	REVISION	BY	CK	E.S.D. WDR	ENG. WDR	QA WDR	DOC ADD
1	11/1/94	REVISED AS PER PID 11-S-01	ESR	AME	CHU	DS	CR	RGS
2	5/19/94	ISSUED FOR CONSTRUCTION	-	-	-	-	-	-

DATE 01-05-93

FILENAME 3085761.dwg

CD	11/21/92	1
CD	2/22/95	1
CD	11/21/92	1
CD	6/2/94	1
CD	11/21/92	1
CD	6/2/94	1
CD	11/21/92	1
CD	6/2/94	1

NOTES:

- LOCATIONS OF THE DITCHES ARE APPROXIMATE AND SHALL BE APPROVED BY THE CONTRACTOR.
- EXCAVATED MATERIALS FROM UNDERNEATH THE CELL SHALL BE FIRST PLACED IN THIS AREA. REMAINING EXCESS MATERIAL SHALL BE STOCKPILED IN THE DESIGNATED AREAS. SEE DWG. NO. SRK-DS-10-0334 FOR GRADING REQUIREMENTS.
- SEDIMENTATION FROM STOCKPILE SHALL BE CONTROLLED USING SILT FENCES AS APPROVED BY THE CONTRACTOR. SEE DWG. NO. SRK-GE-10-0305 FOR SILT FENCE DETAIL.
- FINAL GRADE OF SPOIL PILE SHALL BE CONFINED TO AREA SHOWN ON PLAN. SIDE SLOPES OF SPOIL PILE SHALL BE APPROXIMATELY 5(H):1(V) BUT NO STEEPER THAN 3(H):1(V). FINAL SLOPES SHALL AVOID ANGLES AND LONG STRAIGHT SECTIONS AS SHOWN ON THE DRAWING SRK-DS-10-0334 AS REQUIRED BY THE CONTRACTOR TO MATCH EXISTING TERRAIN.
- FILL FOR FINAL SITE GRADING AFTER EMBANKMENT CONSTRUCTION SHALL COME FROM MATERIAL PLACED WITHIN SPOIL STOCK PILE AREA.
- BERM SHALL BE CONSTRUCTED PRIOR TO HAULING CONTAMINATED MATERIAL TO THE SITE.
- BOTTOM OF DISPOSAL CELL EXCAVATION SHOWN IS MAXIMUM. ACTUAL BOTTOM ELEVATION MAY BE HIGHER THAN SHOWN AS DETERMINED BY THE CONTRACTOR.
- FOR CLARITY ACCESS AND EXIT RAMPS ARE NOT SHOWN. RAMPS SHALL BE CONSTRUCTED BY THE SUBCONTRACTOR AS APPROVED BY THE CONTRACTOR.
- NO FILL SHALL BE PLACED BEYOND THE FENCE LINE.
- SUBCONTRACTOR SHALL VERIFY COORDINATES AND ELEVATIONS OF ALL SURVEY MONUMENTS.
- TOPSOILS SHALL BE STOCKPILED SEPARATELY WITHIN THE SPOIL/STOCKPILE AREA.
- SUBCONTRACTOR SHALL PROVIDE AND INSTALL DEER FENCE AND GATES AROUND ALL WATER RETENTION PONDS INCLUDING RETENTION BASINS, RECIRCULATION PONDS AND CONSTRUCTION WATER STORAGE PONDS AS APPROVED BY THE CONTRACTOR.
- STOCKPILE AREAS FOR THE RADON BARRIER AND TOPSOIL SHALL BE WITHIN THE BOUNDARIES OF THE SPOIL/STOCKPILE AREA AS SHOWN OR AS OTHERWISE DIRECTED BY THE CONTRACTOR.

REFERENCE DRAWINGS:

- SRK-GE-10-0305 FENCE AND GATE DETAILS
- SRK-DS-10-0332 ACCESS CONTROL FACILITIES AND WASTEWATER RETENTION BASIN PLAN
- SRK-DS-10-0333 WASTE WATER RETENTION BASIN AND MISCELLANEOUS SECTIONS AND DETAILS
- SRK-DS-10-0334 TAILINGS EMBANKMENT AND FINAL SITE GRADING PLAN

LEGEND:

- T.O.B. TOP OF BERM
- SURVEY MONUMENTS (SEE NOTE 10)
- SILT FENCE
- EXISTING FENCE

NOTE: THIS SET IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL IS APPROVED BY THE BUREAU OF LAND MANAGEMENT.

RECEIVED FOR QUALITY REQUIREMENTS BY G. BOTTLE 6/2/94

100 0 100 200
SCALE FEET

U. S. DEPARTMENT OF ENERGY
ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE
SLICK ROCK, COLORADO
BURRO CANYON SITE

SITE PREPARATION AND TEMPORARY DRAINAGE FACILITIES

DESIGNED R.F.C.	DRAWN B.H.
CHECKED A. BAHAM	
INSPECTED J.S. RANDEN	
RECOMMENDED R.F. CLARE	
APPROVED P.K. CHEN	

DATE 5/24/94	D. BOLTON 5/24/94	C. RICKETTS 5/24/94	DOC PROJECT ENGINEER R. EDGE	24" E 5/10/94
-----------------	----------------------	------------------------	---------------------------------	------------------

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UNITA PROJECT

PROJECT NO.
DE-AC04-83AL18796

REVISED PER = D 11-S-08	SR	CA	DL	HN	CR	ABS
REVISED PER = D 11-S-07	AMB	JSR	DRS	DB	BH	RE
REVISED AS PER = P11-S-01	JSR	AMB	DRS	DB	CR	CGS
ISSUED FOR CONSTRUCTION	-	-	-	-	-	-

DATE 10-25-94

FILENAME 318171580337.DGN

330
11/21/94
C.D.
6/2/94
QA
10-1

NOTES:

1. LOCATION OF TRAILERS IN THE ACCESS CONTROL AREA SHALL BE SUBJECT TO THE CONTRACTOR'S APPROVAL.
2. SEDIMENTATION FROM ALL OFF SITE FACILITIES SHALL BE CONTROLLED USING SILT FENCES AS APPROVED BY THE CONTRACTOR. SEE DWG. NO. SRK-GE-10-0305 FOR SILT FENCE DETAIL.
3. THE TOTAL DEPTH BETWEEN TOP OF DIKE AND BOTTOM OF DITCH SHALL BE A MINIMUM OF 2'-6". ACTUAL HEIGHT OF DIKE MAY VARY. THE DITCH INVERT SHALL BE SLOPED TO DRAIN.
4. THE TOTAL DEPTH BETWEEN TOP OF ROAD BED AND BOTTOM OF DITCH SHALL BE A MINIMUM OF 3'-6" ON THE SOUTH WEST SIDE OF THE ROAD APPROXIMATELY BETWEEN E 21,760 AND E 22,200.
5. SEE DWG. NO. SRK-GE-10-0305 FOR FENCE DETAILS.
6. THE SECTIONS AND DETAILS OF THE WASH WATER RECIRCULATION BASIN SHOWN ARE A SAMPLE DESIGN ONLY. THE SECTIONS AND DETAILS MAY BE ADJUSTED BY THE SUBCONTRACTOR AS REQUIRED FOR HIS OPERATIONS SUBJECT TO THE CONTRACTOR'S APPROVAL.
7. SEE DWG. NO. SRK-PS-10-0314 FOR TYPICAL CONSTRUCTION AND CONTRACTION JOINT DETAILS FOR THE DECONTAMINATION PAD.
8. NOT USED.
9. THE TOTAL DEPTH BETWEEN TOP OF ROAD BED AND BOTTOM OF DITCH DECREASES FROM 3.5' AT E 22,200 TO 0' AT E 22,329.

REFERENCE DRAWINGS:

- SRK-GE-10-0305 FENCE AND GATE DETAILS
- SRK-PS-10-0314 ACCESS CONTROL AREA PLAN SECTIONS AND DETAILS
- SRK-DS-10-0333 WASTEWATER RETENTION BASIN AND MISCELLANEOUS SECTIONS AND DETAILS

LEGEND:

- AGGREGATE COVERED SURFACE
- SILT FENCE
- EXISTING FENCE

QA REVIEWED FOR QUALITY REQUIREMENTS BY G. DALL 5/27/94

50 0 50 100
SCALE FEET

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPLIES BELOW.

U. S. DEPARTMENT OF ENERGY
ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE
SLICK ROCK, COLORADO
BURRO CANYON DISPOSAL SITE
ACCESS CONTROL FACILITIES AND
WASTEWATER RETENTION BASIN
PLAN

DESIGNED
RFC
CHECKED
A. BANANI
INSPECTED
J.S. RANDENI
RECOMMENDED
R.F. CLAIRE
APPROVED
P.K. CHEN

DATE
5/24/94
D. BOLTON
5/24/94
C. RICKETTS
5/24/94
DOE PROJECT ENGINEER
R. EDGE
DATE
6/10/94

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
ULTRA PROJECT
800 HOWARD ST. SAN FRANCISCO, CA 94105

PROJECT NO.
DE-AC04-83AL18796

DRAWING NO.
SRK-DS-10-0332

REV.
1

DATE	REVISION	BY	OK	E & D	ENG.	QA	DOE
11/16/94	REVISED AS PER PID 11-S-01	IR	AM	DM	DB	CR	RS
05/10/94	ISSUED FOR CONSTRUCTION	-	-	-	-	-	-

SPILLWAY

DETAIL 1
NOT TO SCALE 0332

DITCH NO. 1 PROFILE

(SEE DWG. SRK-PS-10-0331)

DATE 01-28-04

ELEVATION 5840.00

1	2
3	4
5	6
7	8
9	10
11	12
13	14
15	16
17	18
19	20
21	22
23	24
25	26
27	28
29	30
31	32
33	34
35	36
37	38
39	40
41	42
43	44
45	46
47	48
49	50
51	52
53	54
55	56
57	58
59	60
61	62
63	64
65	66
67	68
69	70
71	72
73	74
75	76
77	78
79	80
81	82
83	84
85	86
87	88
89	90
91	92
93	94
95	96
97	98
99	100

TYPICAL NEW DISPLACEMENT MONUMENT DETAIL

(SRK-DS-10-0334)
NOT TO SCALE

SPILLWAY SECTION

(B)
0332

NOTES:

1. THE PIPE SHALL BE PLACED DIRECTLY ON THE PLATE. PIPES SHALL NOT BE ATTACHED TO PLATES OR RODS.
2. PIPES AND RODS WITH TOTAL LENGTH GREATER THAN 4'-0\"/>

REFERENCE DRAWINGS:

- SRK-PS-10-0315 WASTEWATER RETENTION BASIN - SECTIONS AND DETAILS
- SRK-DS-10-0331 SITE PREPARATION AND TEMPORARY DRAINAGE FACILITIES
- SRK-DS-10-0332 ACCESS CONTROL FACILITIES AND WASTEWATER RETENTION BASIN PLAN
- SRK-DS-10-0334 TAILINGS EMBANKMENT AND FINAL SITE GRADING PLAN

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE SLICK ROCK, COLORADO BURRO CANYON DISPOSAL SITE WASTEWATER RETENTION BASIN AND MISCELLANEOUS SECTIONS AND DETAILS

DESIGNED BY: [Signature]
CHECKED BY: [Signature]
INSPECTED BY: [Signature]
RECOMMENDED BY: [Signature]

APPROVED BY: [Signature]

DATE: 5/24/94

DATE: 5-24-94

DATE: 5/24/94

DATE: 6/10/94

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UMTRA PROJECT

PROJECT NO. DE-AC04-83AL18796

DRAWING NO. SRK-DS-10-0332 REV.

FILENAME 308576158BC3146.DGN DATE 04-05-93

6315
2-11-1993
G.D.
11/21/94
G.D.
6/2/94
JA
14-1

NOTES:

1. SLOPES BEYOND EMBANKMENT AREA SHALL BE UNIFORMLY GRADED AS DIRECTED BY THE CONTRACTOR TO PROMOTE SHEET FLOW AWAY FROM THE EMBANKMENT.
2. RESTORE RETENTION BASIN, ACCESS CONTROL, STOCKPILE AND OTHER DISTURBED AREAS TO ORIGINAL GRADE AS DIRECTED BY THE CONTRACTOR.
3. FOR DISPLACEMENT MONUMENT DETAIL, SEE DWG. NO. SRK-DS-10-0333.
4. TYPICAL RADIUS SHOWN IS FOR EMBANKMENT TOP AND SIDESLOPE.
5. FINAL SLOPES OF SPOIL PILE SHALL BE GRADED TO BLEND INTO SURROUNDING TERRAIN AS DIRECTED BY THE CONTRACTOR. ANGLES AND LONG STRAIGHT SECTIONS SHALL BE AVOIDED. FINAL SLOPES SHALL BE APPROXIMATELY 5(H) : 1(V) BUT NO STEEPER THAN 3(H) : 1(V).
6. ALL DISTURBED AREAS BEYOND THE RIPRAP SHALL BE SEEDED IN ACCORDANCE WITH THE SPECIFICATIONS.
7. NO FINAL SITE GRADING WILL BE PERMITTED EAST OF EXISTING FENCE.
8. ACTUAL TOP SLOPE GRADE BREAK MAY DIFFER FROM THAT SHOWN BASED ON ACTUAL VOLUME OF CONTAMINATED MATERIAL PLACED ON EMBANKMENT.

REFERENCE DRAWINGS:

- SRK-DS-10-0333 WASTEWATER RETENTION BASIN AND MISCELLANEOUS SECTIONS AND DETAILS
- SRK-DS-10-0335 TAILINGS EMBANKMENT SECTIONS AND DETAILS (SHEET 1 OF 2)
- SRK-DS-10-0336 TAILINGS EMBANKMENT SECTIONS AND DETAILS (SHEET 2 OF 2)

LEGEND:

- DISPLACEMENT MONUMENT
- FINISH GRADE CONTOURS
- EXISTING FENCE

NOTE THIS SEAL IS NOT VALID IN THE STATE OF CO UNLESS THE ORIGINAL SIGNATURE APPEARS &

QA REVIEWED FOR QUALITY REQUIREMENTS BY: E. BOTTLE 5/27/94

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO

DESIGNED
RFC
DRAWN
MIZ
CHECKED
A. BANANI
INSPECTED
J.S. RANDENI
RECOMMENDED
R.F. CLAIRE

SLICK ROCK SITE
SLICK ROCK, COLORADO
BURRO CANYON
TAILINGS EMBANKMENT AND FINAL
SITE GRADING PLAN

APPROVED
P.K. CHEN
DATE
5/24/94
D. BOLTON
5/24/94
C. RICKETTS
5/24/94
DOE PROJECT ENGRER
R. EDGE
DATE
6/10/94

MORRISON KNUDSEN CORPORATION
ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
UMTRA PROJECT
100 " WARD ST. SAN FRANCISCO, CA 94103

PROJECT NO.
DE-AC04-83AL18796

DRAWING NO.
SRK-DS-10-0334
REV.
2

DATE	REVISION	BY	CHK	E & D	ENV	QA	DOC
4/24/95	REVISED AS PER PID 11-S-08	JSR	AMB	DRS	DB	CR	CGS
11/15/94	REVISED AS PER PID 11-S-01	JSR	AMB	DRS	DB	CR	CGS
4/15/94	ISSUED FOR CONSTRUCTION	-	-	-	-	-	-

SECTION A
0334

TYPICAL TRANSITION FROM
RIPRAP TYPE A TO TYPE B

DETAIL 1
NOT TO SCALE

TYPICAL APRON
DETAIL IN FILL

DETAIL 2
NOT TO SCALE

DATE	02-21-95
FILENAME	38657-08C313.DGN
DESIGNER	CSO
CHECKED	2/13/95
DATE	2/2/94
BY	DA
NO	NO

NOTES:

1. CONTAMINATED MATERIAL FROM UC SITE, AREA "A" SHALL BE PLACED WITH NORTH CONTINENT SITE CONTAMINATED MATERIAL.
2. PILE HEIGHT VARIES DEPENDING UPON THE VOLUME OF CONTAMINATED MATERIAL. THE SECTION SHOWN INCLUDES CONTINGENCY.
3. SLOPE IS 2% UNLESS SHOWN OTHERWISE ON DWG. NO. SRK-DS-10-0334.
4. UC TAILINGS SHALL BE PLACED AT LEAST 15' FROM THE RADON BARRIER AS SHOWN.
5. LIMITS OF CONTAMINATED MATERIALS ARE APPROXIMATE.
6. DEPTH OF BENCH TO BE DETERMINED IN THE FIELD.
7. BOTTOM OF DISPOSAL CELL EXCAVATION SHOWN IS MAXIMUM. ACTUAL BOTTOM ELEVATION MAY VARY AS DETERMINED BY THE CONTRACTOR.
8. TRACK WALKING OR OTHER COMPACTION OF BEDDING MATERIAL IN DITCHES IS NOT REQUIRED.

REFERENCE DRAWINGS:

SRK-DS-10-0334 TAILINGS EMBANKMENT AND FINAL SITE GRADING PLAN

NOTE: THIS SEAL IS NOT VALID IN THE STATE OF COLORADO UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

20
FEET

QA REVIEWED FOR QUALITY REQUIREMENTS BY: G. DOYLE 6/2/94

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO

SLICK ROCK SITE
SLICK ROCK, COLORADO
BURRO CANYON

TAILINGS EMBANKMENT SECTIONS AND DETAILS (SHEET 1 OF 2)

DESIGNED
REC

CHECKED
F.A. BANANI

INSPECTED
J. RANDEN

RECOMMENDED
R.F. CLAIRE

APPROVED
PK. CHEN

DATE
5/24/94

D. BOLTON
5/24/94

C. RICKETTS
5/24/94

DOE PROJECT ENGINEER
RUSSEL EDGE

DATE
6/10/94

PROJECT NO.

DE-AC04-83AL18796

DRAWING NO.

SRK-DS-10-0335

REV.

MORRISON KNUDSEN CORPORATION
UMTRA PROJECT

REVISED PER PID 11-S-03
ISSUED FOR CONSTRUCTION

SECTION C
NOT TO SCALE
0337

SECTION B 0334

TYPICAL APRON
DETAIL IN CUT 1
NOT TO SCALE

TYPICAL EX

DATE 02-21-95

FILENAME 3885781 Sm-0333.dgn

630	2/13/95	2
C.D.	6/7/94	2
DA	10-1	2

TYPE A (8" THICK)
 G LAYER (8" THICK)
 PROTECTION LAYER (2'-0" THICK)
 BARRIER (1'-6" THICK)

7, DWG SRK-DS-10-0335

NOTES:

1. LIMITS OF CONTAMINATED MATERIALS ARE APPROXIMATE.
2. SLOPE IS 2% UNLESS OTHERWISE NOTED ON DWG. NO. SRK-DS-10-0334.
3. SUBCONTRACTOR SHALL LOCATE CONSTRUCTION ACCESS AND EXIT RAMPS AS REQUIRED AND APPROVED BY THE CONTRACTOR. RAMPS WILL REMAIN IN PLACE DURING BACKFILL.
4. SOIL AND LOOSE ROCK SHALL BE EXCAVATED DOWN TO NON-RIPPABLE ROCK.
5. CHAIN LINK FENCE SHALL BE INSTALLED TO PREVENT FALLING MATERIAL AS REQUIRED.
6. SPALLING ROCK SHALL BE REMOVED AS REQUIRED.
7. LOOSE FRACTURED ROCK THAT MAY BE DISLODGED DURING EXCAVATION SHALL BE REMOVED.
8. SIDE SLOPE EXCAVATION MUST BE AT OR BELOW LIMITS SHOWN. ADDITIONAL EXCAVATION PAST THIS LIMIT MAY BE REQUIRED FOR STABILITY AND CONSTRUCTABILITY.
9. TRACK WALKING OR OTHER COMPACTION OF BEDDING MATERIAL IN DITCHES IS NOT REQUIRED.

REFERENCE DRAWINGS:

- SRK-DS-10-0334 TAILINGS EMBANKMENT AND FINAL GRADING PLAN
 SRK-DS-10-0335 TAILINGS EMBANKMENT SECTIONS AND DETAILS (SHEET 1 OF 2)

THIS SEAL IS NOT VALID IN THE STATE OF COLORADO
 UNLESS THE ORIGINAL SIGNATURE APPEARS BELOW.

AVATED ROCK SLOPE SECTION
 (NOT TO SCALE) (SEE NOTE 8)

QA REVIEWED FOR
 QUALITY REQUIREMENTS
 BY: G. DOYLE 6/2/94

U. S. DEPARTMENT OF ENERGY
 ALBUQUERQUE, NEW MEXICO

DESIGNED
 R.F.C.
 CHECKED
 A. BANANI
 INSPECTED
 J. RANDEN
 RECOMMENDED
 R.F. CLAIRE
 APPROVED
 PK. CHEN

SLICK ROCK SITE
 SLICK ROCK, COLORADO
 BURRO CANYON

TAILINGS EMBANKMENT SECTIONS
 AND DETAILS (SHEET 2 OF 2)

DATE 5/24/94 D. BOLTON C. RICKETTS DOE PROJECT ENGINEER RUSSEL EDGE DATE 6/10/94

MORRISON KNUDSEN CORPORATION
 ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP
 UTRCA PROJECT

PROJECT NO. DE-AC04-83AL18796

REVISED PER PID 11-5-03
 ISSUED FOR CONSTRUCTION

SEE NOTE 12

5840

FILE NAME: 34437A.DWG DATE: 01-28-94

1. SEE INFORMATION FOR BIDDERS FOR WELL BORING AND TEST PIT LOGS AND COORDINATES.

655 TEST PITS (JAKES, 1993)
 603 BORE HOLES (JAKES, 1993)
 530 BORE HOLES (JACOBS, 1990)
 517 MONITORING WELLS (JACOBS, 1990)
 540 TEST PITS (JACOBS, 1990)
 X—X—X EXISTING FENCE

QA REVIEWED FOR
QUALITY REQUIREMENTS
BY ST. 11 DATE 06/02/91

SLICK ROCK SITE
SLICK ROCK, COLORADO
BURRO CANYON
**BORINGS AND TEST PITS
LOCATION PLAN**

DESIGNED <i>[Signature]</i>	DRAWN B.J.L.
CHECKED <i>AL. M. B...</i>	
INSPECTED <i>J. S. Kandjira</i>	
RECOMMENDED <i>[Signature]</i>	

APPROVED

MORRISON KNUDSEN CORPORATION
DIVIDING, CONSTRUCTION & ENVIRONMENTAL GROUP
ULTRA PROJECT

- <i>Completed</i> <i>Revised</i> <i>5/24/94</i>	DOE PROJECT ENGINEER <i>Knowledge</i>	DATE <i>6/1/94</i>
--	--	-----------------------

PROJECT NO. DE-AC04-83AL18796

DRAWING NO.	CDK DC-10-0338	REV.	A
-------------	----------------	------	---

STAND PIPE - LAYOUT PLAN

TABLE 1 - PROPOSED STAND PIPE LOCATION COORDINATES

STAND PIPE	COORDINATE	
	NORTHING	EASTING
MW-1	19,600	21,900
MW-2	19,700	22,200
MW-3	19,375	22,050
MW-4	19,550	22,350

DATE 04/05/95

FILENAME D:\388576\WELLS.DGN

630
04/05/95
S.J.B.
04/05/95
QA
MW-F

NOTES:

1. THE CASINGS FOR THE STAND PIPES SHALL BE EXTENDED VERTICALLY AS THE TAILINGS EMBANKMENT IS CONSTRUCTED. ALL STAND PIPE CASINGS SHALL HAVE A MINIMUM 2- FOOT EXTENSION ABOVE THE SURROUNDING SURFACE DURING PLACEMENT OF CONTAMINATED MATERIALS.
2. LOCATION OF STAND PIPES MAY VARY DEPENDING ON FINAL SURFACE ELEVATIONS OF CELL EXCAVATION. FINAL LOCATIONS WILL BE DETERMINED BY THE CONTRACTOR.
3. STAND PIPES CASING AND COUPLERS SHALL CONSIST OF SCHEDULE 40 RIGID PVC PIPE.
4. THE WATER COLLECTED IN THE STAND PIPES SHALL BE PUMPED TO THE WASHWATER RECIRCULATION POND AS DIRECTED BY THE CONTRACTOR.
5. PRIOR TO PLACING THE RADON BARRIER MATERIAL THE STAND PIPES SHALL BE SEALED WITH BENTONITE PELLETS BY THE SUBCONTRACTOR, AS APPROVED BY THE CONTRACTOR.
6. GEOTEXTILE FILTER SHALL BE NONWOVEN POLYESTER WITH THICKNESS OF 70 MILS AS APPROVED BY THE CONTRACTOR. GEOTEXTILE FABRIC SHALL HAVE A 3" MINIMUM OVERLAP AT JOINTS.
7. DAMAGED STAND PIPES SHALL BE REPAIRED OR REPLACED BY THE SUBCONTRACTOR.
8. CONCRETE SHALL BE SACKRETE MIXED PER MANUFACTURERS SPECIFICATIONS.

STAND PIPE DETAIL
NOT TO SCALE

NOTE: THIS SEAL IS VOID IF THE STATE OF NEW MEXICO
UNLESS THE ORIGINAL SIGNATURE APPEARS

DATE	REVISION	BY	CHKD	APP'D	DOE
10/1/95	REVISED PER PID 11-5-08	J.R.	C.L.	C.L.	CR
11/1/95	ISSUED FOR CONSTRUCTION	-	-	-	-

U. S. DEPARTMENT OF ENERGY ALBUQUERQUE, NEW MEXICO					
DESIGNED AMB		DRAWN BS		SLICK ROCK SITE SLICK ROCK, COLORADO	
CHECKED J. S. RANDENI		INSPECTED C. LIZARDO		RECOMMENDED R. F. CLAIRE	
APPROVED D. R. SANDERS		DATE 2/21/95	D. BOLTON 2/21/95	B. HALTON 2/21/95	DOE PROJECT ENGINEER RUSSEL EDGE
PROJECT NO. DE-AC04-83AL18796		DRAWING NO. SRK-DS-10-0339			
MORRISON KNUDSEN CORPORATION ENGINEERING, CONSTRUCTION & ENVIRONMENTAL GROUP ULTRA PROJECT 300 HOWARD ST. SAN FRANCISCO, CA 94103					