REAL-TIME IN SITU DETECTION OF ORGANIC CONTAMINANTS BY LASER-INDUCED FLUORESCENCE SYSTEM

Final Topical Report

Prepared for:

Federal Energy Technology Center
AAD Document Control
U.S. Department of Energy
PO Box 10940, MS 921-143
Pittsburgh, PA 15236-0940

Base Cooperative Agreement DE-FC26-98FT40320--04 (Task 1.3)
Performance Monitor: Mildred Perry

Prepared by:

Jaroslav Šolc
James A. Sorensen
Daniel J. Stepan

Energy & Environmental Research Center
University of North Dakota
PO Box 9018
Grand Forks, ND 58202-9018

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government, nor any agency thereof, nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report is available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Road, Springfield, VA 22161; phone orders accepted at (703) 487-4650.

EERC DISCLAIMER

LEGAL NOTICE This research report was prepared by the Energy & Environmental Research Center (EERC), an agency of the University of North Dakota, as an account of work sponsored by the U.S. Department of Energy. Because of the research nature of the work performed, neither the EERC nor any of its employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement or recommendation by the EERC.

ACKNOWLEDGMENT

This report was prepared with the support of the U.S. Department of Energy (DOE), Federal Energy Technology Center, Cooperative Agreement No. DE-FC26-98FT40320. However, any opinions, findings, conclusions, or recommendations expressed herein are those of the author(s) and do not necessarily reflect the views of the DOE.

TABLE OF CONTENTS

LIST OF FIGURES	i
EXECUTIVE SUMMARY	ii
1.0 INTRODUCTION AND BACKGROUND	1
2.0 TECHNOLOGY DESCRIPTION	2
3.0 FIELD DEMONSTRATION	2
4.0 RESULTS	3
4.1 Performance Evaluation	3
4.2 Limits of the Technology	5
4.3 Cost Evaluation and Other Considerations	6
5.0 CONCLUSIONS	6
6.0 ACKNOWLEDGMENTS	7
7.0 REFERENCES	7
SOIL PROFILES SLP 1–8	Appendix A
TEST FUEL – CALIBRATION	Appendix B
SOIL PROFILES SLP 6–10 WITH LABORATORY ANALYSIS AND SOIL LOGS	Appendix C

LIST OF FIGURES

1 Site location	1
2 Location of test borings	3
3 Cross-Sections SLP–1–6	4

REAL-TIME IN SITU DETECTION OF ORGANIC CONTAMINANTS BY LASER-INDUCED FLUORESCENCE SYSTEM

EXECUTIVE SUMMARY

The ability of a truck mounted laser-induced fluorescence (LIF) sensor to detect polycyclic aromatic hydrocarbons (PAHs) in contaminated soils was demonstrated at a well-characterized, active Superfund site in St. Louis Park, Minnesota. LIF imaging is an optical technique in which the fluorescence of compounds irradiated by a laser is measured. LIF can be used to detect either subsurface petroleum hydrocarbons or uranium and provides a method to rapidly survey a site. Various versions of LIF systems have been tested, including hand-held, airborne, and cone penetrometer-mounted systems. The technology used for this demonstration was provided by Dakota Technologies, Inc. (DTI), of Fargo, North Dakota, and was deployed in a percussion soil probing device mounted on a light truck. The weight of the truck including the LIF equipment was 12,500 lb.

The Superfund site, Number 980609804, was contaminated with coal tars, creosote, and carcinogenic PAHs. Ten 10-ft-deep soil penetrations were made, each requiring approximately 20 to 25 min to complete LIF measurements and grout. The resulting fluorescence intensity profiles permitted delineation of the interface between the 5- to 8-ft-thick uncontaminated fill and the underlying PAH-contaminated materials. The LIF-generated data were compared with laboratory soil analysis at selected locations. It was shown that LIF is not capable of detailed hydrocarbon speciation, but the results indicated a correspondence of high total PAH concentrations with peaks on the fluorescence intensity record. In addition, LIF-generated continuous profiles illustrated PAH distribution better than laboratory analysis that represented a wider sampling interval.

Based on information provided by DTI, 300 ft of pushes can be advanced per day under normal conditions. The estimated cost per foot of measured and recorded soil profile ranges from about \$8/ft to \$18/ft including grouting. These estimates do not include permit fees, health plan development costs, or mobilization/demobilization costs, which vary with each location. DTI's LIF sensor costs compare favorably to costs for conventional drilling, sampling, and analyses (which range from \$50/ft to \$100/ft) as well as the costs for the U.S. Navy's LIF sensor technology (\$12/ft to \$20/ft).

The results of the field demonstration showed that the field-deployed LIF method can provide information on hot spots and contaminant plume geometry in real time, to guide the sampling effort and enable accurate placement and construction of monitoring wells. Minimal wastes are generated and worker exposure to potentially hazardous materials is substantially less than during conventional drilling and sampling activities. The LIF technology can be easily deployed in various settings and has the ability to provide quality screening-level data in a timely, cost-effective, and environmentally acceptable manner.

1.0 INTRODUCTION AND BACKGROUND

The LIF technology was tested and evaluated at a well-characterized, active Superfund site located in St. Louis Park, Minnesota. The site location is shown in Figure 1. Wastes (including carcinogenic PAHs) from Reilly Tar & Chemical Corporation were originally disposed on the site and discharged to an adjacent wetland. In accordance with the Consent Decree for the Reilly Site, the City began to fill the property with clean soil in 1985. The results of the site characterization conducted by ENSR indicate that the site is currently covered by up to 12 ft of clean fill. The underlying bog area is impacted as deep as 65 ft by coal tars, creosote, and petroleum chemicals.

1

2.0 TECHNOLOGY DESCRIPTION

Laser-induced fluorescence imaging (LIFI) is an optical technique in which the fluorescence of compounds irradiated by a laser is measured. The system uses a pulsed excimer laser with a light wavelength of 308 nanometers. LIFI, which can be used to detect either subsurface petroleum hydrocarbons or uranium, provides a method to rapidly survey a site. It can be used to identify contaminant “hot spots,” assist in waste cleanup activities, and monitor remedial progress, but is not sufficiently developed to permit accurate contaminant quantitation. Various versions of LIFI systems have been tested, including hand-held, airborne, and direct push technology systems. The LIF sensor discussed in this report was deployed in a percussion soil probing device.

The LIF sensor used a wavelength-tunable ultraviolet laser source to induce a fluorescence response in the petroleum hydrocarbons. Measurement of the fluorescence was made through a sapphire window on a probe that was pushed into the ground using a percussion soil probing device. Feedback was applied to the hydraulics of the percussion hammer to emulate an ASTM penetration rate of 2 cm/sec for cone penetrometers. Optical fibers integrated with the geotechnical probe and cone penetrometer umbilical carried the fluorescence measurement to the optical detector located in the truck (EPA, 1997a).

3.0 FIELD DEMONSTRATION

The major objectives of the field demonstration were to 1) verify the technology performance at a well-characterized contaminated site and 2) evaluate the technology's baseline economics. The demonstration was conducted by DTI on December 1, 1998, and was monitored by the Energy & Environmental Research Center (EERC), the lead environmental consulting firm for the site; ENSR; and the Minnesota Pollution Control Agency (MPCA). DTI operators drilled and recorded information on PAH distribution in the soil at ten different locations on the south end of the site, as shown in Figure 2. Five of the soil profiles, SLP-1 through SLP-5, were located so as to provide supplemental PAH distribution information in a W-E cross section between ENSR borings. The remaining five borings were located where ENSR had previously documented and analyzed soil cores. These preexisting analytical data were compared to the LIF demonstration results since a limited budget precluded laboratory analyses during this project. The tenth hole was located in an uncontaminated area so as to gather background contamination data. The soil profiles were analyzed to a depth of 10 ft. In general, material identified as coal tar-related PAHs were detected at depths starting from 5 to 8 ft below the surface. Following the measurements, all of the 1-in.-diameter borings were plugged with Volclay Grout II in compliance with Minnesota environmental standards.

Figure 2. Location of test borings.

4.0 RESULTS

4.1 Performance Evaluation

Soil profile measurements from SLP-1 through SLP-5 are provided in Appendix A. The resulting profiles, when aligned in a cross section as shown in Figure 3, demonstrate that two- and three-dimensional models of the site contamination can be easily derived from the LIF method. The response for the 5- to 8-ft-thick uncontaminated fill contrasts with the fluorescence noted for PAH-contaminated underlying materials. Generation of a plot and grouting the borehole took DTI operators approximately 20 to 25 min. The shape of the curve representing fluorescence intensity shows clearly defined zones that are enriched with PAHs. The selected peaks, or data points on the curve, can be further analyzed and their waveforms compared to “calibration” graphs. This is shown in Appendix B. The calibration or reference samples are prepared from soil materials that have been saturated with specific fuels to illustrate the difference between the corresponding waveforms or “fingerprints” and the false color presentation. The false color coding of the generated graphical profiles does not pertain to response intensity; however, the shape of either calibration curves or curves derived from soils saturated with diesel fuels typically are different waveforms with a much stronger signal than, for example, creosote.

Demonstration Borings SLP-6 through SLP-10 were placed at the locations of ENSR Boreholes B250, D300, E200, C200, and F250, as shown in Figure 2. LIF profiles, soil logs, and relevant laboratory analyses for these boreholes are provided in Appendix C.

Figure 3. Cross-Sections SLP – 1–6.

Comparison between the LIF and the analytical data indicate that high total PAH concentrations corresponded well with peaks on fluorescence intensity record. Although not quantitative, the LIF-generated continuous profiles illustrated PAH distribution much better than one laboratory analysis that typically represents a specific 2- to 3-ft-long interval.

A detailed evaluation of soil parameters with respect to their influence on fluorescence measurements was beyond the scope of this project. It is reasonable, however, to expect that a higher fluorescence intensity would be associated with more permeable soils that had been exposed to PAHs for a prolonged period of time so as to become fully saturated.

The primary application of the demonstrated LIF system is as a screening-level investigation. Analysis by standard laboratory techniques of site-specific soil samples could be used for LIF sensor calibration immediately prior to field detection. Such calibration could enhance the semiquantitative capabilities of the demonstrated technology.

The detailed, real-time data regarding the nature and occurrence of subsurface contamination provided by the Geoprobe-mounted LIF would result in optimizing the characterization and monitoring activities at brownfield sites. In particular, application of the LIF technology to a brownfield site can be used to guide the collection of soil samples to be analyzed for compliance purposes and the placement of monitoring wells. The data generated by the LIF may also be used to design more effective and efficient remediation strategies by allowing designers to target very specific, well-defined zones of contamination.

4.2 Limits of the Technology

Site accessibility is naturally limited by the size and weight of the truck carrying the cone penetrometer and LIF equipment. For this demonstration, all of the equipment, including a Ford four-wheel drive truck as demonstrated by DTL, weighed 12,500 lb (6.25 tons/5.7 metric tonnes). This specific configuration is significantly more mobile and flexible than heavier drilling equipment.

Applicability of LIF to a given site depends in large part on the cone penetrometer probe's ability to penetrate various materials. The presence of gravel, boulders, cobbles, cementitious materials, and various buried debris, bricks, concrete blocks, etc., in fill materials can severely limit the use of a penetrometer. As is the case with other intrusive characterization methods, it is important to delineate all underground utilities and structures prior to initiating screening activities on site.

Fluorescence intensity readings are affected by different LIF response to various petroleum hydrocarbons, sensitivity to variations in the soil matrix, and spectral overlap in complex samples. Aliphatic hydrocarbons, single-ring aromatics, and most two-ring PAHs do not contribute to the LIF signal. The fluorescence properties of a hydrocarbon mixture may also change as a result of changed chemical composition due to weathering, biodegradation, and volatilization after long-term exposure to and interaction with the environment (EPA, 1997b). Soil matrix properties that

affect LIF sensitivity include soil grain size, mineralogy, moisture content, and surface area. Details of these factors are provided in the cited EPA document.

4.3 Cost Evaluation and Other Considerations

The following costs provided by DTI are based on an 8-hr day. Typical production per day is 200–300 ft of measured soil profile in Minnesota and 300–500 ft in North Dakota. The differences are due to state grouting regulations. Costs are as follows:

Mobilization fee (includes two people)	\$2.50/mile
Per diem (Minnesota, two people)	\$258/day
LIF Fee (operator and LIF equipment)	\$1500/day
Geoprobe (probe operator and equipment)	\$1500/day
Grouting (\$2.00/ft in MN, \$1.10/ft in ND)	\$600/day
TOTAL	\$3858/day plus mobilization fee

Under normal conditions, 300 ft of pushes can be easily advanced per day. The estimated cost per foot of measured and recorded soil profile ranges from about \$8/ft (in North Dakota) to \$18/ft (in Minnesota), including grouting. These estimates do not include costs for permit fees, health plan development, and mobilization/demobilization costs which vary with each location. These costs compare favorably to conventional drilling, which ranges from \$15/ft to \$20/ft for drilling and installation of monitoring wells and between \$50/ft and \$100/ft for drilling and site characterization sampling. In addition, the costs to analyze total petroleum hydrocarbon (TPH) content or recoverable TPH average \$90 to \$150 per analyzed soil sample.

5.0 CONCLUSIONS

- The comparison of LIF-generated data with the soil analysis at selected locations indicates that high total PAH concentrations corresponded well with fluorescence intensity peaks.
- The fluorescence intensity profiles obtained during the demonstration permitted delineation of the interface between the uncontaminated 5- to 8-ft-thick fill and underlying PAH-contaminated materials.
- Continuous profiles illustrate PAH distribution better than laboratory analysis that represents a wider sampling interval.
- At \$8/ft to \$18/ft, the estimated cost of using DTI's LIF sensor compares favorably to the cost for conventional drilling, sampling, and analyses (\$50/ft to \$100/ft) as well as the costs estimated for the U.S. Navy's LIF sensor/cone penetrometer technology (\$12/ft to \$20/ft).
- LIFI is not capable of detailed hydrocarbon speciation.

The field-deployed LIF method can provide information on hot spots and contaminant plume geometry in real time, to guide the sampling effort and enable accurate placement and construction of monitoring wells. Minimal wastes are generated, and worker exposure to potentially hazardous materials is substantially less than during conventional drilling and sampling activities. The results of the field demonstration show that the LIF technology can be easily deployed in various settings and has the ability to provide quality screening-level data in a timely, cost-effective, and environmentally acceptable manner.

6.0 ACKNOWLEDGMENTS

The authors wish to express their thanks to Steve Adamek and Randy St. Germain of DTI for field demonstration and data on LIF technology. The indispensable support by Bill Gregg of ENSR in providing the demonstration site access and background information is gratefully acknowledged.

7.0 REFERENCES

- EPA, 1997a, Environmental technology verification program verification statement—rapid optical screening tool (ROST): U.S. Environmental Protection Agency; No. EPA-VS-SCM-01, EPA National Exposure Research Laboratory, Las Vegas, Nevada.
- EPA, 1997b, Innovative technology verification report—site characterization and analysis penetrometer system (SCAPS) laser-induced fluorescence (LIF) sensor and support system: U.S. Environmental Protection Agency; Pub. No. EPA/600/R-97/019, National Exposure Research Laboratory: Las Vegas, Nevada.
- Federal Remediation Technologies Roundtable, 1999, Field Sampling and Analysis Technologies Matrix Version 1.0: URL <http://www.frtr.gov/site/index.html> (accessed March 18, 1999).

APPENDIX A

SOIL PROFILES SLP 1–8

APPENDIX B

TEST FUEL – CALIBRATION

APPENDIX C

SOIL PROFILES SLP 6–10 WITH LABORATORY ANALYSIS AND SOIL LOGS

NATIONAL
ENVIRONMENTAL
TESTING, INC.

Cedar Falls Division
704 Enterprise Drive
Cedar Falls, IA 50613
Tel: (319) 277-2401
Fax: (319) 277-2425

ANALYTICAL REPORT

Pete Moore
ENSR-ST. LOUIS PARK
4500 Park Glen
Suite #210
St. Louis Park, MN 55416

09/29/1998

NET Job Number: 98.11773

NET Sample Number: 472447

Project ID: PAH Soils #1620-018

Sample ID: B + 250 4-6' Project #1620-018

Date Taken: 09/17/1998

Date Received: 09/19/1998

<u>Analyte</u>	<u>Result</u>		<u>Unit</u>		<u>Flag</u>		<u>Analyst</u>		<u>Date</u>		<u>Method</u>		<u>Quantitation</u>	
% Solids	82.66		%				as	as	09/24/1998					
Prep. BNA - NONAQUEOUS	complete						as	as	09/24/1998		SW 3540			
BNA - 8270 NONAQUEOUS														
Benzo(a)anthracene	23.0		ug/g				ccb	ccb	09/25/1998		SW 8270C		5.9	
Benzo(b)fluoranthene	13.8		ug/g				ccb	ccb	09/25/1998		SW 8270C		5.9	
Benzo(k)fluoranthene	13.8		ug/g				ccb	ccb	09/25/1998		SW 8270C		5.9	
Benzo(a)pyrene	12.7		ug/g				ccb	ccb	09/25/1998		SW 8270C		5.9	
Chrysene	19.5		ug/g				ccb	ccb	09/25/1998		SW 8270C		5.9	
Dibenzo(a,h)anthracene	<5.9		ug/g				ccb	ccb	09/25/1998		SW 8270C		5.9	
Indeno(1,2,3-cd)pyrene	4.0		ug/g		J		ccb	ccb	09/25/1998		SW 8270C		5.9	
Total PAH	86.8		ug/g				rlb	rlb	09/29/1998					

J - Variability is increased: result is below linear calibration range.

R.L. Bindert
Operations Manager

Project No: 1620-018

Client: City of St. Louis Park - EDA

Project: Phase II Site Investigation

Location: 7250 State Highway 7

Log of Borehole: B+250

ENSR Corporation
4500 Park Glen Road Suite
210
St. Louis Park, MN 55416

File Name: R:\ENSR\1620-018\B-250.LOG

Depth	Description	Soil Symbol	PID	Comments
	SOD			
1				
2	Brown SAND with gravel and silt		0	
3				
4				Collected soil sample from 4 to 6'
5			33	for cPAH analysis
6	Brown SAND with peat, gravel and silt			
7			78	Stained soil
8	Dark brown PEAT			
	End of Borehole			
9				
10	Total Boring Depth = 8ft.			
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				

Drilled by: Bergerson Caswell

Drill Date: September 17, 1998

Drill Method: Simco Earthprobe 200

Inspected By: Peter Moore

cPAH concentration: 86.8 ppm

Methane Concentration: Not Collected

NATIONAL
ENVIRONMENTAL
TESTING, INC.

Cedar Falls Division
704 Enterprise Drive
Cedar Falls, IA 50613
Tel: (319) 277-2401
Fax: (319) 277-2425

ANALYTICAL REPORT

Pete Moore
ENSR-ST. LOUIS PARK
4500 Park Glen
Suite #210
St. Louis Park, MN 55416

09/29/1998

NET Job Number: 98.11773

NET Sample Number: 472445

Project ID: PAH Soils #1620-018

Sample ID: D + 300 4-6' Project #1620-018

Date Taken: 09/17/1998

Date Received: 09/19/1998

<u>Analyte</u>	<u>Result</u>	<u>Units</u>	<u>Result</u> <u>Flag</u>	<u>Analyst</u>	<u>Date</u> <u>Analyzed</u>	<u>Method</u>	<u>Quantitation</u> <u>Limit</u>
% Solids	94.19	%		sas	09/24/1998		
Prep, BNA - NONAQUEOUS	complete			asz	09/24/1998	SW 3540	
BNA - 8270 NONAQUEOUS							
Benzo(a)anthracene	<1.7	ug/g		ccb	09/25/1998	SW 8270C	1.7
Benzo(b)fluoranthene	<1.7	ug/g		ccb	09/25/1998	SW 8270C	1.7
Benzo(k)fluoranthene	<1.7	ug/g		ccb	09/25/1998	SW 8270C	1.7
Benzo(a)pyrene	<1.7	ug/g		ccb	09/25/1998	SW 8270C	1.7
Chrysene	<1.7	ug/g		ccb	09/25/1998	SW 8270C	1.7
Dibenzo(a,h)anthracene	<1.7	ug/g		ccb	09/25/1998	SW 8270C	1.7
Indeno(1,2,3-cd)pyrene	<1.7	ug/g		ccb	09/25/1998	SW 8270C	1.7
Total PAH	---	ug/g		rlb	09/29/1998

R.L. Bindert
Operations Manager

NATIONAL
ENVIRONMENTAL
TESTING, INC.

Cedar Falls Division
704 Enterprise Drive
Cedar Falls, IA 50613
Tel: (319) 277-2401
Fax: (319) 277-2425

ANALYTICAL REPORT

Pete Moore
ENSR-ST. LOUIS PARK
4500 Park Glen
Suite #210
St. Louis Park, MN 55416

09/29/1998

NET Job Number: 98.11773

NET Sample Number: 472459

Project ID: PAH Soils #1620-018

Sample ID: D + 300 7-8' Project #1620-018

Date Taken: 09/17/1998

Date Received: 09/19/1998

<u>Analyte</u>	<u>Result</u>	<u>Units</u>	<u>Flag</u>	<u>Analyst</u>	<u>Date Analyzed</u>	<u>Method</u>	<u>Quantitation Limit</u>
% Solids	84.02	%		sas	09/24/1998		
Prep, BNA - NONAQUEOUS	complete			asz	09/24/1998	SW 3540	
BNA - 8270 NONAQUEOUS							
Benzo(a)anthracene	355	ug/g		ccb	09/26/1998	SW 8270C	20
Benzo(b)fluoranthene	210	ug/g		ccb	09/26/1998	SW 8270C	20
Benzo(k)fluoranthene	193	ug/g		ccb	09/26/1998	SW 8270C	20
Benzo(a)pyrene	198	ug/g		ccb	09/26/1998	SW 8270C	20
Chrysene	331	ug/g		ccb	09/26/1998	SW 8270C	20
Dibenzo(a,h)anthracene	28.9	ug/g		ccb	09/26/1998	SW 8270C	20
Indeno(1,2,3-cd)pyrene	65.1	ug/g		ccb	09/26/1998	SW 8270C	20
Total PAH	1,381	ug/g		rlb	09/29/1998		

R.L. Bindert
Operations Manager

slp08

NATIONAL
ENVIRONMENTAL
TESTING, INC.

Cedar Falls Division
704 Enterprise Drive
Cedar Falls, IA 50613
Tel: (319) 277-2401
Fax: (319) 277-2425

ANALYTICAL REPORT

Pete Moore
ENSR-ST. LOUIS PARK
4500 Park Glen
Suite #210
St. Louis Park, MN 55416

09/29/1998

NET Job Number: 98.11773

NET Sample Number: 472439

Project ID: PAH Soils #1620-018

Sample ID: E + 200 4-7' Project #1620-018

Date Taken: 09/17/1998

Date Received: 09/19/1998

<u>Analyte</u>	<u>Result</u>	<u>Units</u>	<u>Result</u> <u>Flag</u>	<u>Analyst</u>	<u>Date</u> <u>Analyzed</u>	<u>Method</u>	<u>Quantitation</u> <u>Limit</u>
% Solids	82.67	%		sas	09/24/1998		
Prep. BNA - NONAQUEOUS	complete			clj	09/20/1998	SW 3540	
BNA - 8270 NONAQUEOUS							
Benzo(a)anthracene	9.9	ug/g		dmd	09/23/1998	SW 8270C	2.3
Benzo(b)fluoranthene	8.2	ug/g		dmd	09/23/1998	SW 8270C	2.3
Benzo(k)fluoranthene	8.9	ug/g		dmd	09/23/1998	SW 8270C	2.3
Benzo(a)pyrene	8.8	ug/g		dmd	09/23/1998	SW 8270C	2.3
Chrysene	10.2	ug/g		dmd	09/23/1998	SW 8270C	2.3
Dibenzo(a,h)anthracene	<2.3	ug/g		dmd	09/23/1998	SW 8270C	2.3
Indeno(1,2,3-cd)pyrene	3.5	ug/g		dmd	09/23/1998	SW 8270C	2.3
Total PAH	49.5	ug/g		rlb	09/29/1998		

R.L. Bindert
Operations Manager

Project No: 1620-018

Client: City of St. Louis Park - EDA

Project: Phase II Site Investigation

Location: 7250 State Highway 7

Log of Borehole: E+200

ENSR.

ENSR Corporation
4500 Park Glen Road Suite
210
St. Louis Park, MN 55416

File Name: R:\ENSR\1620-018\E-200.LOG

Depth	Description	Soil Symbol	PID	Comments
1	SOD			
2	Dark brown CLAY with gravel, silt and organics		0	Collected soil sample from 4 to 7' for cPAH analysis
3				
4				Refusal of sampling probe
5			0	
6	As above with a 4 inch thick layer of calcium hydroxide sludge			
7	End of Borehole			
8	Total Boring Depth = 7 ft.			
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				

Drilled by: Bergerson Caswell

Drill Date: September 17, 1998

Drill Method: Simco Earthprobe 200

Inspected By: Peter Moore

cPAH concentration: 49.5 ppm

Methane Concentration: Not Collected

NATIONAL
ENVIRONMENTAL
TESTING, INC.

Cedar Falls Division
704 Enterprise Drive
Cedar Falls, IA 50613
Tel: (319) 277-2401
Fax: (319) 277-2425

ANALYTICAL REPORT

Pete Moore
ENSR-ST. LOUIS PARK
4500 Park Glen
Suite #210
St. Louis Park, MN 55416

09/29/1998

NET Job Number: 98.11773

NET Sample Number: 472426

Project ID: PAH Soils #1620-018

Sample ID: C + 200 6-8' Project #1620-018

Date Taken: 09/17/1998

Date Received: 09/19/1998

<u>Analyte</u>	<u>Result</u>	<u>Units</u>	<u>Flag</u>	<u>Analyst</u>	<u>Date Analyzed</u>	<u>Method</u>	<u>Quantitation Limit</u>
% Solids	86.20	%		sas	09/22/1998		
Prep, BNA - NONAQUEOUS	complete			clj	09/20/1998	SW 3540	
BNA - 8270 NONAQUEOUS							
Benzo(a)anthracene	1.1	ug/g		dmd	09/21/1998	SW 8270C	0.40
Benzo(b)fluoranthene	0.53	ug/g		dmd	09/21/1998	SW 8270C	0.40
Benzo(k)fluoranthene	0.54	ug/g		dmd	09/21/1998	SW 8270C	0.40
Benzo(a)pyrene	0.47	ug/g		dmd	09/21/1998	SW 8270C	0.40
Chrysene	0.90	ug/g		dmd	09/21/1998	SW 8270C	0.40
Dibenzo(a,h)anthracene	<0.40	ug/g		dmd	09/21/1998	SW 8270C	0.40
Indeno(1,2,3-cd)pyrene	<0.40	ug/g		dmd	09/21/1998	SW 8270C	0.40
Total PAH	3.5	ug/g		rlb	09/29/1998		

R.L. Bindert
Operations Manager

Project No: 1620-018

Client: City of St. Louis Park - EDA

Project: Phase II Site Investigation

Location: 7250 State Highway 7

Log of Borehole: C+200

ENSR.

ENSR Corporation
4500 Park Glen Road Suite
210
St. Louis Park, MN 55416

File Name: R:\ENSR\1620-018\IC-200.LOG

Depth	Description	Soil Symbol	PID	Comments
	SOD			
1	Dark brown SAND with gravel, silt and organics			Collected soil sample from 6 to 8' for cPAH analysis
2			0	
3				
4			0	
5	Dark brown SLIGHTLY SILTY SAND with organics			
6			0	
7	End of Borehole Total Boring Depth = 8 ft.			
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				

Drilled by: Bergerson Caswell

Drill Date: September 17, 1998

Drill Method: Simco Earthprobe 200

Inspected By: Peter Moore

cPAH concentration: 3.5 ppm

Methane Concentration: Not Collected

NATIONAL
ENVIRONMENTAL
TESTING, INC.

Cedar Falls Division
704 Enterprise Drive
Cedar Falls, IA 50613
Tel: (319) 277-2401
Fax: (319) 277-2425

ANALYTICAL REPORT

Pete Moore
ENSR-ST. LOUIS PARK
4500 Park Glen
Suite #210
St. Louis Park, MN 55416

09/29/1998

NET Job Number: 98.11773

NET Sample Number: 472442

Project ID: PAH Soils #1620-018

Sample ID: F + 250 8-10' Project #1620-018

Date Taken: 09/17/1998

Date Received: 09/19/1998

Analyte	Result	Units	Flag	Analyst	Date Analyzed	Method	Quantitation Limit
% Solids	76.06	%		sas	09/24/1998		
Prep, BNA - NONAQUEOUS	complete			asz	09/24/1998	SW 3540	
BNA - 8270 NONAQUEOUS							
Benzo(a)anthracene	<11	ug/g		ccb	09/25/1998	SW 8270C	11
Benzo(b)fluoranthene	16.4	ug/g		ccb	09/25/1998	SW 8270C	11
Benzo(k)fluoranthene	10.4	ug/g		ccb	09/25/1998	SW 8270C	11
Benzo(a)pyrene	12.2	ug/g		ccb	09/25/1998	SW 8270C	11
Chrysene	<11	ug/g		ccb	09/25/1998	SW 8270C	11
Dibenzo(a,h)anthracene	<11	ug/g		ccb	09/25/1998	SW 8270C	11
Indeno(1,2,3-cd)pyrene	6.6	ug/g	J	ccb	09/25/1998	SW 8270C	11
Total PAH	45.6	ug/g		rlb	09/29/1998		

J - Variability is increased: result is below linear calibration range.

R.L. Bindert
Operations Manager

Project No: 1620-018

Client: City of St. Louis Park - EDA

Project: Phase II Site Investigation

Location: 7250 State Highway 7

Log of Borehole: F+250

ENSR Corporation
4500 Park Glen Road Suite
210
St. Louis Park, MN 55416

File Name: R:\ENSR\1620-018\F-250.LOG

Depth	Description	Soil Symbol	PID	Comments
	SOD			
1				
2	Brown SAND with gravel and silt		0	
3				
4				
5				
6	Dark brown PEAT with sand and silt		0	
7				
8				Collected soil sample from 8 to 10' for cPAH analysis
9	Dark brown SAND with gravel			
10			0	
11	Dark brown PEAT			
12	End of Borehole Total Boring Depth = 12 ft.			
13				
14				
15				
16				
17				
18				
19				
20				

Drilled by: Bergerson Caswell

Drill Date: September 17, 1998

Drill Method: Simco Earthprobe 200

Inspected By: Peter Moore

cPAH concentration: 45.6 ppm

Methane Concentration: Not Collected