SYSTEM DESIGN DOCUMENT

FOR THE

PLUTONIUM

STABILIZATION AND PACKAGING SYSTEM

CONTRACT NO: DE-AC03-96SF20948

CDRL SEQUENCE NO. A001

Prepared for:

Department of Energy - Oakland

Prepared by:

BNFL Inc.

in association with

Stone and Webster Engineering Corporation
Raytheon Engineers & Constructors, Inc.
Pajarito Scientific Corporation
Toeroek Associates, Inc.
BNFL Engineering, Ltd.
Denver, CO

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

REVIEWED FOR CLASSIFICATION/UCNI
By [Signature]
Date 06/27/96

DISCLAIMER

**Portions of this document may be illegible
in electronic image products. Images are
produced from the best available original
document.**

Table of Contents

Section Titles	Page
1.0 Scope	1
1.1 Identification	1
1.2 System Overview	1
1.3 Document Overview	1
2.0 Referenced Documents	2
3.0 Operational Concepts	3
3.1 User Needs	3
3.2 Operational Environment	3
3.3 Support Environment	7
3.3.1 Support Concept	8
3.3.2 Support Facilities	10
3.4 System Architecture	10
3.5 Operational Scenarios	13
4.0 System Design	15
4.1 Hardware Configuration Item (HWCI) Identification	15
Stabilization Process (19)	
4.1.1 Receipt Area	19
Receipt Hood (19); Airlock Container Handler (21); Entry Airlock (22)	
4.1.2 Material Preparation Area	24
Material Preparation Glovebox (24); Can Handlers (26); Entry and Exit	
Isolation Doors (27); Container Opener (28); Powder Dispensing Station	
(29); Metal Brushing Station (31); Convenience Can Transfer Port (33);	
Decontamination Station (34); Compactor Station (36); Material Transfer	
Ports (37)	
4.1.3 Transport Area	38
Transport Glovebox (38); Can/Tray Handler (40); Transport Glovebox	
Television Monitoring System (41)	
4.1.4 Furnace Area	42
Furnace Glovebox (42); Stabilization Furnaces (44)	
4.1.5 LOI Test Area	46
LOI Glovebox (46); LOI Sampling Station (48); Sample Desiccator (49);	
LOI Furnace (51);	

Table of Contents

Packaging Process (53)	
4.1.6	Tipping/Dispense/Fill Area 53 Oxide Tipping Glovebox (53); Seismic Displacement Absorber (55); Furnace Tray Elevator/Transpose Unit (56); Furnace Tray Tipper (56); Convenience Can Transfer Unit (57); Material Transfer Port (58); Dispense/Fill Glovebox (59); Convenience Can Post In Sphincter Seal (61); Convenience Can Magazine (62); Convenience Can Handler (62); Can Loading Station (64); Cap Removal/Replacement Station (64); Can Fill Station (65); Cap Monitoring Station (66); Can Orientation Station (67); Convenience Can Post Out Unit (68); Convenience Can Identification and Weigh Station (69)
4.1.7	Can Weigh and Cap Insertion Area 70 Can Weigh and Cap Insertion Glovebox (70); Gaslock (72); Convenience Can Extraction Unit (73); Convenience Can Turntable (74); Weigh Scale and Bar Code Reader (75); Convenience Can Pusher (76); Inner Can Cap Post In Sphincter Seal (77); Inner Can Cap Magazine (78); Material Transfer Port (79)
4.1.8	Inner Can Handling Area 79 Inner Can Handling Fume Cabinet (80); Inner Can Rotating Sphincter Seal (81); Inner Can Storage Magazine (82); Laser Welding/Cutting Tools (83); Laser Generator (84); Inner Can Handling Unit (85)
4.1.9	Outer Can Weld and Monitoring Area 86 Can Turntable/Trolley (86); Outer Can Handler (87); Inner Can Leak Detection Unit (88); Helium Fill/Lid Fittment Unit (90); Outer Can Welder (91); Outer Can Contamination Check Unit (91); Outer Can Leak Detection Unit (93)
4.1.10	Lag Storage Trolley 94 HWCI's Common to Several Pu SPS Areas (95)
4.1.11	Furnace Trays 95
4.1.12	Storage Package 96 Convenience Can and Cap (96); Inner Can (97); Inner Cap (97); Outer Can and Lid (99)
4.1.13	Hood/Glovebox Atmosphere 100 Supply and Exhaust Filtration (100)
4.1.14	Electrical 102 Power Distribution (102); Lighting (105)
4.1.15	Support Structures and Platforms 105
4.1.16	Fire Protection 106

Table of Contents

4.1.17	Pu SPS Control System	107
	Plutonium Stabilization Control System (PSCS) (107); Plutonium Packaging Control System (PPCS) (111); Data Management System (DMS) (113)	
4.1.18	Process Radiometric Instrumentation	114
	Container Assay Monitor (115); Plutonium Hold Up System (116)	
4.2	Computer Software Configuration Item (CSCI) Identification	118
4.2.1	Stabilization Process Control System Software	118
4.2.2	Packaging Process Control System Software	119
4.2.3	Data Management System Software	121
4.2.4	Data Highway Communication Software	122
4.2.5	Process Radiometric Instrumentation Software	122
4.3	Manual Operations Identification	124
4.3.1	Receipt Area Actions	124
	Package/Can Movement from Transfer Trolley (124); Container/Can Identification and Data Entry (124); Site Storage Package Frisking (125); Outer Container Removal and Bagging (125); Transfer from Receipt Hood into the Entry Airlock (125); Transfer from S-16 Conveyor into the Entry Airlock (126)	
4.3.2	Material Preparation Area Actions	126
	Outer Container Removal (126); Plastics Removal (127); Outer Container Bagout (127); Plastics Bagout (127); Transfer of Container/Can to Container Assay Monitor (128); Inner Site Container Opening (128); Site Convenience Can/Small Metals Vessel Transfer (128); Oxide Dispensing (129); Inspection for Metals (129); Disposition of Off-Normal Materials and Chunky Oxides (129); Placement of Small Metal Pieces into Transfer Vessel (130); Metal Brushing (130); Convenience Can Posting (130); Convenience Can Bar Code Reading (130); Convenience Can Weighing (131); Metal Placement into the Convenience Can (131); Convenience Can Capping (131); Convenience Can Cap Bagout (132); Inner Site Container Decontamination (132); Inner Site Container Compaction (132); Compacted Inner Site Container Bagout (133)	

Table of Contents

4.3.3	LOI Test Area Actions	133
	Placement of Small Metal Pieces into Furnace Tray (133); Sampling (134); Data Entry of Sample Data (134); Sample Heating (134); Sample Weighing (135); Cooling in the Sample Desiccator (135); Sample Disposal (135); Visual Inspection of Empty Furnace Tray (135); Visual Inspection of Filled Furnace Tray (136)	
4.3.4	Tipping/Dispense/Fill Area Actions	136
	Convenience Can Posting (136)	
4.3.5	Can Weigh and Cap Insertion Area Actions	136
	Load a Special Inner Can Cap (136); Bag Out Stubs (136)	
4.3.6	Inner Can Handling Area Actions	137
	Load Inner Cans (137)	
4.3.7	Outer Can Weld and Monitoring Area Actions	137
	Load an Outer Lid (137); Load an Outer Can (137); Move the Lag Storage Trolley (137)	
5.0	Notes	138
5.1	Background Information	138
5.2	Acronyms and Abbreviations	139
5.3	Glossary of Terminology	141

Table of Contents

Figures	Page
SDD-1A, Pu SPS Process Flow Diagram, Sheet 1, Stabilization Process	16
SDD-1B, Pu SPS Process Flow Diagram, Sheet 2, Packaging Process	17
SDD-2, Pu SPS Glovebox Arrangement Diagram	18
SDD-3, Pu SPS Glovebox Ventilation System Diagram	101
SDD-4, Pu SPS Electrical One-Line Diagram	104
SDD-5, Pu SPS Control Block Diagram	110
Tables	Page
Preliminary Pu SPS Safety SSCs	5
Pu SPS Operational Scenarios	13
Appendices	Page
A. Applicability of Requirements to Equipment in Specific Areas	A-1
B. System Classification Methodology	B-1

SPECIAL NOTE: There are contract changes regarding technical issues that are currently being negotiated and will affect this document. In most cases, anticipated contract changes are highlighted using double angles <<example>>.

Bracketed italics [*example*] have been used to indicate contract requirements.

Italics have been used to indicate direct quotations from reference documents.

| All figures provided are current as of the System Design Document revision date
| only. Drawing revisions that might affect these figures will not result in a change to
| this document unless the text is also significantly affected.

[The System Design Document describes the design of a system and its operational and support environments. It describes the organization of a system as composed of Hardware Configuration Items (HWCI), Computer Software Configuration Items (CSCI), and the interaction of the system with manual operations to perform operational tasks.

The System Design Document contains the highest level design information for the system. The System Design Document describes the allocation of system requirements to HWCI, CSCI, and the manual operations that interact with the system.

The System Design Document describes the characteristics of each HWCI and CSCI to the Government.

The System Design Document is used by the contractor for two primary purposes, namely: (1) present the system design at the System Design Review, (2) use the design information as the basis for developing the Software Requirements Specification for each CSCI, the Interface Control Documents for the system, and the requirements specification for each HWCI.

The System Design Document is used by the government to assess the design of a system. The System Design Document provides an overview of the system that may also be used by training personnel, support personnel, or users of the system.]

| Updated through Contract Mod 9
| and DOE comment resolutions

1.0 Scope

1.1 Identification

[This paragraph ... shall contain the approved identification number, title, and abbreviation, if applicable, of the system to which this System Design Document applies. This paragraph shall identify the higher-level specification containing the requirements from which the design of the system was derived.]

This document describes the highest level design information for the Plutonium Stabilization and Packaging System (Pu SPS), as required by DOE contract DE-AC03-96SF20948 through contract modification 9 for equipment in Building 707 at Rocky Flats Environmental Technology Site (RFETS). It derives its requirements from the System Specification of the Pu SPS (ID: SS/Pu SPS @RF/707).

1.2 System Overview

[This paragraph ... shall briefly state the purpose of the system to which this System Design Document applies.]

The overall objective of this system is to stabilize and package plutonium metals and oxides of >50% wt, as well as other selected isotopes, in accordance with the requirements of the DOE standard for safe storage of these materials for 50 years (reference 2.1.8). This system will support completion of a stabilization and packaging campaigns of the plutonium inventory at a number of affected sites before the year 2002. The storage package will be standard for all sites and will provide a minimum of two uncontaminated, organics free confinement barriers for the packaged material. The affected sites within the DOE complex include Rocky Flats Environmental Technology Site, Hanford Site, and Savannah River Site (SRS).

1.3 Document Overview

[This paragraph ... shall summarize the purpose and contents of this document.]

This document describes the Pu SPS system and user characteristics from an operational perspective. System goals were coordinated with site operators and line management, DOE representatives, and a broad span of engineers to prepare this document. The applicability of particular requirements in the System Specification to individual subsystems or components is provided in this document. It therefore provides guidance for developing procurement and installation specifications, interface requirements, and test plans. The intended audience includes system operators and management, system engineers, and the DOE.

2.0 Referenced Documents

[This section ... shall list by document number and title all documents referenced in this document. This section shall also identify the source for all documents not available through normal Government stocking activities.]

- 2.1 10 CFR 835, Occupational Radiation Protection.
- 2.2 DOE Order 5480.19, Conduct of Operations.
- 2.3 DOE Order 5480.23, Nuclear Safety Analysis Reports.
- 2.4 DOE Standard DOE-STD-3009-94, Preparation Guide for U.S. DOE Nonreactor Nuclear Facility Safety Analysis Reports.
- 2.5 DOE Standard DOE-STD-1027-92, Hazard Categorization and Accident Analysis Techniques for Compliance with DOE Order 5480.23, Nuclear Safety Analysis Reports.
- 2.6 DOE Standard DOE-STD-1021-93, Natural Phenomena Hazards Performance Categorization Guidelines for Structures, Systems, and Components.
- 2.7 DOE Order 5633.3B, Control and Accountability of Nuclear Materials.
- 2.8 DOE Standard DOE-STD-3013-94, Criteria for Safe Storage of Plutonium Metals and Oxides.
- 2.9 DOE Contract DE-AC03-96SF20948, Plutonium Stabilization and Packaging System.

3.0 Operational Concepts

3.1 User Needs

[This subparagraph ... shall summarize the user needs that are to be met by the system and shall reference the document(s) in which these needs are stated.]

The Pu SPS functional, and operational requirements, as established in DOE contract DE-AC03-96SF20948, are:

- 1) provide radiological containment and shielding at all times,
- 2) receipt and unloading of existing containers,
- 3) prepare metals for packaging [by removing corrosion products],
- 4) prepare metals [fines] and oxides for stabilization,
- 5) perform stabilization,
- 6) provide and perform packaging of metals and oxides,
- 7) meet material control and accountability requirements,
- 8) leak detection,
- 9) provide rework capability.

3.2 Operational Environment

[This paragraph ... shall describe the environment in which the system is intended to be employed.]

The Plutonium Stabilization and Packaging System (Pu SPS) will be located in an area where access is restricted to insure national security as well as employee and public safety. Personnel must possess a suitable security clearance to gain area access. Strict accountability of Special Nuclear Material is maintained throughout the Pu SPS process. Material will be retrieved from secure storage vaults external to the Pu SPS process area, transported to the Pu SPS for processing, and returned to secure storage vaults after processing is complete. Information required for material control and accountability will be documented on a work control traveller.

Employee and public safety is assured through an aggressive Radiation Protection Program mandated by reference 2.1 that includes appropriate radiation surveys to monitor equipment, facility, and site radiological conditions, radiological postings placed appropriately to warn personnel of radiation hazards, individual radiation exposure monitoring, and applicable radiation safety training of all personnel entering the process area. Work with radioactive materials is controlled with the use of a Radiation Work Permit that defines appropriate safety controls to protect the worker, the public, and the environment.

All facility activity is conducted according to the requirements of reference 2.2. Control over equipment status is established through formal site and facility procedures to ensure that proper configure control is maintained. An Integrated Work Control Program (IWCP) establishes the review and approval requirements for site activities. This control includes instructions for system alignments, lockout/tagout of components, verification of technical specification compliance prior to plant operating mode change, authorization prior to removing or restoring equipment to service during maintenance activities, and identification and documentation of equipment deficiencies. Control is maintained through a central control room or station from which all work activities and equipment configurations are coordinated. Formal work reviews are conducted daily at Plan-of-the-Day meetings where activities are discussed. Operations logs are established to record day to day activities and equipment operational status, and to provide an accurate history of facility operations.

It is the responsibility of the on-shift operating crew to safely operate the facility through adherence to operating procedures, technical specifications, and operational safety requirements using sound operating practices. The authority for daily operations is vested in the on-duty shift manager. Work is performed to formal operating procedures where procedural changes are not allowed unless proper reviews are conducted, and changes approved in writing. Employees have authorization to stop work in the event of unsafe conditions or actions.

Audible communications are used to transmit operating and emergency information within the facility through a site wide public address system that may be accessed locally within the building, or from various other site locations. Several different emergency alarms are present in the facility, and include criticality, high airborne radioactivity, general fire, and glovebox overheat alarms. Employees are trained to take appropriate actions for each alarm and may include immediate evacuation from the affected areas, or facility. Telephones, pagers, and radio communications are used to augment communications throughout the facility.

Solid waste generated as a result of Pu SPS operations are segregated according to established waste acceptance criteria and containerized for shipment to suitable waste repositories onsite or offsite. Solid radioactive waste generated will be shipped to an approved radioactive waste repository and meet all local, state, and federal requirements. Radioactive liquid wastes, if any, will be processed onsite. Mixed hazardous or non-radioactive wastes, including solid and liquid wastes, will be handled according to site procedures and meet all local, state, and federal requirements.

Inspections, audits reviews, investigations, and self-assessments all are a part of the checks and balances used in the operating program. Workers and supervisors are held accountable for operating performance.

For determining the extent of additional reviews and care in designing, installing, operating, and maintaining Pu SPS structures, systems, and components (SSCs), the DOE has defined certain categories and classifications.

DOE classifications of SSCs involve hazard category, performance category, and safety classification. The definition of hazard category is provided in reference 2.3 and additional guidance is found in references 2.4 and 2.5. The Pu SPS should be given a preliminary classification of Hazard Category 2, consistent with Building 707 at RFETS.

Reference 2.6 provides guidance for natural phenomena hazard performance categorization. SSCs of the Pu SPS that provide a safety function should be designed to PC-3 due to plutonium hazards and consistent with system requirements (requirement QUAL-3 in the System Specification).

Appendix B (System Classification Methodology) was developed for understanding the determination of system safety classifications as RFETS and other sites, and for establishing a consistent methodology for Pu SPS application. Using this methodology with the RFETS accident analysis for Building 707 thermal stabilization processes resulted in the following table that identifies, in a very preliminary manner, the "Safety SSCs" for the Pu SPS. During project design a more comprehensive analysis will be performed to finalize the Pu SPS Safety SSCs.

Preliminary Pu SPS Safety SSCs		
Safety SSC Description	Safety Issue to Address	Applicable Criteria
Criticality Drains on the following: Entry Airlock Material Preparation Glovebox Transport Glovebox Furnace Glovebox LOI Glovebox Oxide Tipping Glovebox Seismic Displacement Absorber (?) Dispense/Fill Glovebox Can Weigh/Cap Insertion Glovebox Gaslock	Provide critically safe storage of nuclear material, considering the potential entry of water from the ventilation ductwork or from room fire sprinklers through damaged glovebox areas during a DBE.	#3 (Prevent criticality)

Gloveboxes & penetrations, including: Entry Airlock Material Preparation Glovebox Convenience Can Transfer Port Material Transfer Ports Transport Glovebox Furnace Gloveboxes LOI Glovebox Oxide Tipping Glovebox Seismic Displacement Absorber Dispense/Fill Glovebox Convenience Can Post In Sphincter Seal Can Weigh/Cap Insertion Glovebox Inner Cap Sphincter Seal Material Transfer Port Inner Can Handling Fume Cabinet Inner Can Rotating Sphincter Seal Utility Supply/Return Connections Nitrogen/Helium/Downdraft Ductwork	Provide shielding and confinement of radioactive material.	#1 (Public protection) #5 (Worker Protection OSRs)
Ventilation, including Glovebox Dump Valves, for the following: Receipt Hood Entry Airlock Material Preparation Glovebox Transport Glovebox Furnace Glovebox LOI Glovebox Oxide Tipping Glovebox Dispense/Fill Glovebox Can Weigh/Cap Insertion Glovebox Gaslock Inner Can Handling Fume Cabinet	Provide a cascading pressure differential (ensure air flow is from areas of lesser contamination). Maintain a minimum face velocity for hoods.	#1 (Public protection) #5 (Worker Protection OSRs)
Hard-wired Interlocks, for the following, Entry Airlock Doors	Provide confinement of radioactive material.	#1 (Public protection) #5 (Worker Protection OSRs)
Fire Prevention Equipment (Glovebox Oxygen Monitoring)	Provide means of checking the inert atmosphere in process areas containing pyrophoric plutonium.	#1 (Public protection)
Fire Suppression Equipment for: Metal Brushing Station LOI Sampling Station	Provide fire suppression in process areas containing pyrophoric plutonium.	#1 (Public protection)

Fire Detection Equipment for: Receipt Hood Entry Airlock Material Preparation Area Transport Glovebox Furnace Glovebox LOI Glovebox Oxide Tipping Glovebox Dispense/Fill Glovebox Can Weigh and Cap Insertion Glovebox Inner Can Handling Fume Cabinet	Provide fire detection in process areas containing plutonium metal or oxide.	#1 (Public protection)
Storage Packages, specifically: Inner Can and Cap Outer Can and Lid	Provide safe storage of plutonium by preventing internally-initiated releases to the room.	#1 (Public protection)

3.3 Support Environment

[This paragraph ... shall describe the support environment for the operational system during the Production and Deployment phase of the system life cycle.]

During the production and deployment phase of the Pu SPS, the system will be supported by a full time engineering, operations and maintenance staff in Building 707 of RFETS. This staff, which is currently supporting the operation of similar glovebox systems, will continue to perform surveillance, maintenance, and repair of building facilities required to support the operation of the Pu SPS. This staff will also cover normal building activities (i.e. - health physics, safeguards and security, criticality engineering and safety engineering). The operation of this system is not expected to significantly impact the current level of support staff needed to fulfill these building operations.

The operation, maintenance and repair of the SPS will be provided by RFETS operations and maintenance personnel who have successfully completed Pu SPS system specific training identified in the system specification, which will initially be provided by the BNFL Team. The team will also recommend system planned maintenance requirements and a spare parts inventory necessary to support a required goal for system availability during the production and deployment phase.

3.3.1 Support Concept

[This subparagraph ... shall describe the support concept for the system. This subparagraph shall include the following:

- a. Use of multipurpose or automated test equipment*
- b. Repair versus replacement criteria*
- c. Level of maintenance*
- d. Maintenance and repair cycles*
- e. Government and contractor support*
- f. Accessibility*
- g. Other.]*

The Pu SPS is designed for consistent and robust operation. All in-box equipment is configured for hands-on in-situ repair or disposal in accordance with the principles listed below.

- Minimized in-situ repair requirements to reduce production down time and personnel radiation exposure. Generally this means that equipment will run until it fails, then be disposed of, through the waste route or removable access panels.
- Minimized routine maintenance requirements to reduce production down time and personnel radiation exposure. This is achieved by the use of sealed bearings, obviating the use of elastomer covers or shrouds.
- Use of proven, low cost equipment capable of many thousands of cycles before failure. The extensive use of suitably sized, standard industrial pneumatic cylinders for moving and positioning. Typically these actuators have lives in excess of 100,000 cycles.
- Maintainable equipment located inside the gloveboxes has, where possible, been configured in modules from readily available components. Modules have been sized, located, or attached such that they can be accessed for in-situ repair or be easily removed from their working position. All motors are located outside of containment, where possible, with drive shafts penetrating through proven seal technology.
- All modules or replacement components are attached using varying types of quick release devices that permit, in most cases, one hand manipulation. Extensive use of such devices prevent the need to use wrenches, screwdrivers, or special tools in gloveboxes.

- Electrical switches and other feedback devices are clamped in easily adjustable and releasable mountings to aid in replacement. Electrical devices are also fitted with the appropriate length of lead, terminating in a plug for attachment to a mating socket installed in an electrical bulkhead.

The initial campaign of five to seven years will require only typical preventive maintenance. Once the Pu SPS is shutdown and low volume operations are anticipated (over the remainder of its 50 year design life), more extensive maintenance may be required prior to restart. A typical list of restart required maintenance actions include:

- Inspection of moving seals, wear points, welds, and moving parts.
- Lubricating all bearings, sliding surfaces, and gear boxes.
- Thorough checking of instrumentation and control equipment, including calibration.
- Replacement of worn or faulty parts.
- Cleaning to reduce contamination.
- Tightening all fasteners.
- Restarting of the system to initialize the process after shutdown.

The layout of the Pu SPS considers the access needs for normal operation, emergency conditions, and maintenance.

- Those areas requiring continuous or nearly continuous occupancy are located on the outer perimeter of the gloveboxes. These areas include the operator positions for the Receipt Hood, Entry Airlock, Material Preparation Area, LOI Test Area, Tipping/Dispense/Fill Area, Can Weigh and Cap Insertion Area, Inner Can Handling Area, and Outer Can Weld and Monitoring Area.
- Access to the areas between the gloveboxes is limited to activities that occur infrequently. These activities are loading empty cans into the Dispense/Fill glovebox once per day, and refilling the dewar for the Container Assay Monitor 3 or 4 times per week.
- The remote control console is located in the corridor outside the room, reducing radiation doses and emergency egress concerns.
- The longest egress path from the Pu SPS during normal operations is for the operator at the Receipt Hood. The total egress path is about 45 feet to the doors connecting to the corridor.
- The Furnace Gloveboxes are fitted with access panels, allowing the furnaces to be removed for repair or replacement. Other gloveboxes are fitted with access panels where required for maintenance.

3.3.2 Support Facilities

[This subparagraph ... shall describe the system support facilities and equipment to be used during the Production and Deployment phase of the system life cycle. A quantitative description of existing facilities and equipment shall be provided in sufficient detail so that their availability may be verified.]

Existing site general support facilities will be used to support the Pu SPS in the following areas:

- Building Structure (for protection from natural phenomena)
- Operators and Maintenance Personnel, including support associated with them (training facilities, shop areas, work control processes, craft tools and equipment, etc.)
- Facility Management Group
- Instrument Calibration Group
- Building Engineering/Utilities Groups
- Property Management Group
- Health and Safety Group
- Health Physics Access Controls (including radiation control technicians and engineers)
- Nuclear/Criticality Safety Groups
- Fire Protection Engineering Group
- Procedures Development Group
- Site Quality Assurance and Quality Control Groups
- Safeguards and Security Access Controls
- Fire Department
- Site Construction Support
- Plutonium Transport Mechanisms (to and from the vault)
- Plutonium Storage Vault Area
- Warehousing of Spare Parts

Specific interfaces between the Pu SPS and existing site facilities are summarized in section 3.4 and are detailed in the Interface Requirements Document (Appendix A of the System Specification).

3.4 System Architecture

[This paragraph ... shall describe the internal structure of the system. The HWCIs, CSCIs, and manual operations shall be identified and their purpose summarized. The relationships among the HWCIs, CSCIs shall be described. This paragraph shall also identify and state the purpose of each external

interface of the system. A system architecture diagram may be used to illustrate the system top-level architecture.]

The system process diagram of the Pu SPS (Figures SDD-1A/SDD-1B on pages 16/17) illustrates its top level architecture and operation. A general arrangement diagram is also provided (Figure SDD-2 on page 18).

The internal structure of the Pu SPS is divided into the following HWCIs:

Stabilization Process

- **Receipt Area** (to transfer the site storage packages/site convenience cans into the Pu SPS)
- **Material Preparation Area** (to prepare plutonium metals for storage, prepare plutonium oxides for stabilization, and prepare process waste streams for disposal/storage)
- **Transport Area** (for internal material movement of furnace trays and convenience cans of metal)
- **Furnace Area** (to thermally stabilize plutonium oxides)
- **LOI Test Area** (to test for completion of oxide stabilization and handle small pieces of plutonium metal)

Packaging Process

- **Tipping/Dispense/Fill Area** (to transfer oxides in furnace trays to convenience cans)
- **Can Weigh and Cap Insertion Area** (to put filled convenience can and cap/bung into inner can)
- **Inner Can Handling Area** (to stage inner cans and laser weld/cut the assembly)
- **Outer Can Weld and Monitoring Area** (to load/seal the outer can, and check for contamination/leaks)

Additional HWCIs that are common to several areas of the Pu SPS are:

- **Lag Storage Trolley** (for temporary storage of completed storage packages)
- **Furnace Trays** (for transporting oxide in the Pu SPS, including stabilization within the furnace)
- **Storage Packages** (for safe interim 50 year storage of plutonium metal and its oxide)
- **Receipt Hood/Fume Cabinet/Glovebox Atmosphere** (for control of gases in hoods and gloveboxes)
- **Electrical** (for power distribution and lighting)
- **Support Structures and Platforms** (for hoods, gloveboxes, and other Pu SPS equipment)
- **Fire Protection** (for detection and suppression of fires)
- **Pu SPS Control System** (for control of stabilization and packaging processes, including data for MC&A and storage package certification requirements)
- **Process Radiometric Instrumentation** (for support of criticality limits and SNM/ONM accountability)

Pu SPS implementation will require the following CSCIs:

- **Plutonium Stabilization Control System Software** (for control of stabilization processes)
- **Plutonium Packaging Control System Software** (for control of packaging processes)
- **Data Management System Software** (for data collection and reporting, supporting MC&A and storage package certification requirements)
- **Data Highway Communication Software** (for electronic sharing of Pu SPS control and data signals).
- **Process Radiometric Instrumentation Software** (for preprocessing of radiation instrument data).

The required manual operations for the Pu SPS are:

- **Receipt Area Actions** (site storage package/site convenience can movement from a transfer trolley or the S-16 conveyor, data entry of site inner container/site convenience can identification, site storage package "frisking" and container(s) transfer to an airlock, outer container removal/bagging)
- **Material Preparation Area Actions** (packaging removal, site inner container/site convenience can assaying, weighing operations, transfer of container/can into container assay monitor, inner site container/site convenience can opening, metal conditioning and transfer to convenience can, replacement of site convenience can caps, placement for oxide transfer to the furnace tray, disposition of off-normal materials and chunky oxides, reduction of inner site container surface radioactivity, inner site container compaction, container/can and plastic and equipment transfers)
- **LOI Test Area Actions** (LOI sampling, weighing, heating, cooling, and sample transfer to tray, visual inspection of furnace trays, placement of small metal pieces in a furnace tray of oxide)
- **Tipping/Dispense/Fill Area Actions** (loading of empty convenience caps)
- **Can Weigh and Cap Insertion Area Actions** (loading of inner can caps, removal of "stubs")
- **Inner Can Handling Area Actions** (loading of inner and outer cans and lids)
- **Outer Can Weld and Monitoring Area Actions** (transfer of storage packages)

The required external interfaces for the Pu SPS are:

- Inert Ventilation System
- Downdraft System
- Nitrogen System
- Process Cooling Water
- Helium System
- Instrument Air/Plant Air System

- Liquid Nitrogen
- Bottled Carbon Dioxide, Helium, and Nitrogen Gases
- Conveyor System
- 120 VAC Power Supply System (Lighting)
- 120 VAC Power Supply System (Equipment)
- 480 VAC 3-Phase Power Supply System
- Glovebox Overheat Detection and Alarm System
- Oxygen Detection and Alarm System
- Safeguards Accountability Network

3.5 Operational Scenarios

[This paragraph ... shall describe each operational scenario of the system. A table may be provided to illustrate the operational scenarios in which each configuration item executes and each manual operation is performed. In addition this paragraph shall describe the general flow of both execution control and data between configuration items while operating in operational scenarios. Flow diagrams may be used to illustrate execution control and data flow in each operational scenario.]

The basic overall operation of the Pu SPS is described in section 3.1 of the System Specification. A detailed logic diagram of Pu SPS operations is also provided in that same area. The table below identifies the operational scenarios that are performed on the incoming containers of plutonium in order to produce storage packages suitable for 50 years of interim storage. In these evolutions, a limited amount of waste products also result; ones that are properly processed for disposal/storage.

Configuration Items and Manual Operations	Pu SPS Operational Scenarios		
	Metal Processing	Oxide Processing	Waste Processing
Receipt Area	yes	yes	yes
Material Preparation Area	yes	yes	yes
Transport Area	pass through	yes	no
Furnace Area	yes	yes	no
LOI Test Area	yes	yes	no
Tipping/Dispense/Fill Area	only can handling	yes	no
Can Weigh and Cap Insertion Area	yes	yes	yes

Configuration Items and Manual Operations	Pu SPS Operational Scenarios		
	Metal Processing	Oxide Processing	Waste Processing
Inner Can Handling Area	yes	yes	no
Outer Can Weld and Monitoring Area	yes	yes	no
Lag Storage Trolley	yes	yes	no
Furnace Trays	no	yes	no
Storage Packages	yes	yes	no
Hood/Glovebox Atmosphere	yes	yes	yes
Electrical	yes	yes	yes
Support Structures and Platforms	yes	yes	yes
Fire Protection	yes	yes	yes
Pu SPS Control System	yes	yes	yes
Process Radiometric Instrumentation	yes	yes	yes
Plutonium Stabilization Control System Software	yes	yes	yes
Plutonium Packaging Control System Software	yes	yes	yes
Data Management System Software	yes	yes	yes
Data Highway Communication Software	yes	yes	yes
Process Radiometric Instrumentation Software	yes	yes	yes
Receipt Area Actions	yes	yes	yes
Material Preparation Area Actions	yes	yes	yes
LOI Test Area Actions	yes	yes	no
Tipping/Dispense/Fill Area Actions	no	yes	no
Can Weigh and Cap Insertion Area Actions	yes	yes	yes
Inner Can Handling Area Actions	yes	yes	no
Outer Can Weld and Monitoring Area Actions	yes	yes	no

4.0 System Design

[This section ... shall be divided into the following paragraphs and subparagraphs to identify each HWCI, CSCI, and manual operation that interacts with the system. A description of the relationship of HWCI, CSCIs, and manual operations within the system shall be provided.]

4.1 Hardware Configuration Item (HWCI) Identification

[This paragraph ... shall be divided into subparagraphs to identify the system requirements allocated wholly or partially to each HWCI.]

[This subparagraph ... shall identify a HWCI by name and shall state its purpose. This subparagraph shall identify each requirement by a project-unique identifier from the System Specification allocated wholly or partially to the HWCI. This subparagraph shall identify each interface external to the system addressed by the HWCI. Each interface external to the system shall be described in detailed quantitative terms (e.g. input-output voltages, dimensions, tolerances, loads, speeds, etc.), or by reference to an ICD or System Specification paragraph. This subparagraph shall describe any additional design constraints on the HWCI.]

Pu SPS
Plutonium Stabilization and Packaging System

PROCESS FLOW DIAGRAM
SHEET 1
STABILIZATION

FIGURE SDD-1A

TIPPING/DISPENSE/FILL
AREA

CAN WEIGH AND CAP
INSERTION AREA

INNER
HANDL

FIGURE SDD-1B

10' 15' 25'

Pu SPS
Plutonium Stabilization and Packaging System

GLOVEBOX ARRANGEMENT DIAGRAM

FIGURE SDD-2

Stabilization Process

4.1.1 Receipt Area

This area receives incoming plutonium site storage packages or site convenience cans from site storage and transfers them into the Material Preparation Area. The Receipt Area includes the following major equipment items: the Receipt Hood, the Airlock Container Handler, and the Entry Airlock.

All equipment in the Receipt Area must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCI are identified in the following discussions.

4.1.1.1 Receipt Hood

The purpose of this HWCI is to provide a protected work area for initial receipt incoming site storage packages/site convenience cans from a transfer trolley, "frisking" of the outer container and packaging materials, and packaging (bagging) of empty outer containers without surface contamination.

4.1.1.1.1 Current Description and Anticipated Operations

- a) An existing site storage package is transferred from a transfer trolley into the Receipt Hood, where the outer container is hand monitored for surface radiation and the work control traveller numbers are recorded via either bar code scanning or keyboard entry into the PSCS.
- b) The outer container is opened manually, either by untaping slip-on covers or cutting crimp sealed lids with a container opener, and the contents are hand monitored for surface radiation.
- c) If free of contamination, the inner site container (including any packaging materials) is removed from the outer container manually and transferred through the Entry Airlock to the Material Preparation Area.
- d) If radioactive contamination is found, the entire site storage package (outer and inner containers, including packaging materials such as tape) is transferred through the Entry Airlock to the Material Preparation Area for disposal/storage preparation.
- e) Uncontaminated outer containers and packaging materials such as tape are prepared for low-level radioactive waste disposal/storage.

- f) Ventilation flow through the Receipt Hood is sufficient to maintain a minimum face velocity of 150 fpm with the Receipt Hood sash fully open. This face velocity will prevent possible airborne radioactive particles in the Receipt Hood from entering the room area.
- g) The Receipt Hood is designed with adequate space to allow operations and maintenance personnel to perform the tasks assigned to them.
- h) Outer shipping containers (such as DOT 2R primary containment vessels) will be opened while the shipping container is still on the trolley. The inner container(s) will then be brought into the Receipt Hood for processing, as described above.
- i) If required by analysis, the Receipt Hood will be provided with radiation shielding to reduce personnel dose rates to ALARA with a goal of 500 mrem/year to the whole body, from all sources within the Pu SPS.
- j) If required by analysis, the shielding will be a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.

4.1.1.1.2 Specific HWCI Requirements

The Receipt Hood must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
RA-6	Support needs for frisker.
MPA-1	Unload/decon existing containers.
HGA-5	Ventilation needed.
E-7	Lighting type.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PSC-3	Entry of process data.
PRI-2	Sodium iodine detectors.
RAM-7	Removable shielding.
SAFE-9	Platforms/work surfaces.

4.1.1.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.1.2 Airlock Container Handler

The purpose of this HWCI is to transfer site containers/site convenience cans from the Receipt Hood and the existing Module J (S-16) conveyor into the Material Preparation Area. The Airlock Container Handler is located inside the Entry Airlock.

4.1.1.2.1 Current Description and Anticipated Operations

- a) The Airlock Container Handler moves laterally inside the Entry Airlock and also reaches through each of the 3 airlock doors to transfer site containers/site convenience cans through the doors.
- b) Site containers/site convenience cans to be moved from the Receipt Hood into the Material Preparation Area are manually placed on the Receipt Hood side of the Entry Airlock door. The airlock door then opens, the Airlock Container Handler reaches through the open airlock door and picks up the site container/site convenience can and moves it into the airlock, the Receipt Hood airlock door closes, the Material Preparation Area airlock door opens, the Airlock Container Handler reaches through the open airlock door and sets the site container/site convenience can on the Can Handler in the Material Preparation Area, the Airlock Container Handler retreats into the Entry Airlock, then the airlock door closes.
- c) Site convenience cans to be moved from the S-16 conveyor are manually removed from the chainveyor and placed on the S-16 conveyor side of the S-16 conveyor airlock door. Space is provided in the connection to the conveyor to do this out of the way of the chainveyor. The Entry Airlock door then opens, the Airlock Container Handler reaches through the open airlock door and picks up the site convenience can and moves it into the airlock, the S-16 conveyor airlock door closes, the Material Preparation Area airlock door opens, the Airlock Container Handler reaches through the open airlock door and sets the site convenience can on the Can Handler in the Material Preparation Area, the Airlock Container Handler retreats into the Entry Airlock, and the airlock door closes.
- d) A small purge flow of nitrogen bleeds out of the Airlock Container Handler into the airlock to minimize contamination of its internal mechanisms.

4.1.1.2.2 Specific HWCI Requirements

The Airlock Container Handler must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

RA-2	Interface with site conveyor.
------	-------------------------------

PSC-4	Control automatic operations.
-------	-------------------------------

SAFE-6	Machine guards.
--------	-----------------

4.1.1.2.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.1.3 Entry Airlock

The purpose of this HWCI is to transfer incoming plutonium site storage containers/site convenience cans into the inert atmosphere of the Material Preparation Glovebox.

4.1.1.3.1 Current Description and Anticipated Operations

- a) The Entry Airlock has 3 doors that connect to the Receipt Hood, to the S-16 conveyor, and to the Material Preparation Glovebox.
- b) The Entry Airlock also makes a connection with the existing J Module S-16 conveyor. Site convenience cans transported via the S-16 conveyor are presumed to have surface contamination.
- c) The site containers/site convenience cans are moved from the Entry Airlock into the Material Preparation Glovebox by the Airlock Container Handler, which reaches through the airlock door.
- d) The Entry Airlock is of the purged type to prevent transfer of air from the Receipt Hood into the inerted S-16 Conveyor and the Material Preparation Glovebox. The purge gas is nitrogen to match the atmosphere in the Material Preparation Glovebox.
- e) The door near the S-16 Conveyor provides fire separation.

- f) The airlock doors are pneumatically operated under semi-automatic control. The 3 doors are interlocked so that no more than one door may be opened at one time.
- g) The Entry Airlock is provided with radiation shielding to reduce personnel dose rates to ALARA with a goal of 500 mrem/year to the whole body, from all sources within the Pu SPS.
- h) Shielding is a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.

4.1.1.3.2 Specific HWCI Requirements

The Entry Airlock must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

RA-3	Airlock size.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
FPS-4	Fire door isolation.
PSC-1	Monitor/control interlocks.
PSC-2	Monitor/control environment.
SAFE-10	Compressed gases.
BOX-7	Airlocks.
BOX-9	Pass-through connectors.
BOX-11	Leak tightness.
BOX-14	Shutoffs for utilities.
BOX-15	Airlock inop if operator near.
BOX-16	Pneumatic gas type.

4.1.1.3.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.2 Material Preparation Area

This area prepares plutonium metals for storage, prepares plutonium oxides for stabilization, and prepares process waste streams for disposal/storage. Material Assay is also performed in this area, as described in the Container Assay Monitor (section 4.1.18) on page 115. The Material Preparation Area includes the following major equipment items: the Material Preparation Glovebox, the Can Handlers, the Entry and Exit Isolation Doors, the Container Opener, the Powder Dispensing Station, the Metal Brushing Station, the Convenience Can Transfer Port, the Decontamination Station, the Compactor Station, and Material Transfer Ports.

All equipment in the Material Preparation Area must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCI are identified in the following discussions.

4.1.2.1 Material Preparation Glovebox

The purpose of this HWCI to confine radioactive materials within the glovebox, maintain an inert (nitrogen) atmosphere for processing plutonium, and provide radiation shielding for operators.

4.1.2.1.1 Current Description and Anticipated Operations

- a) The Material Preparation Glovebox is a leaktight stainless steel "L" shaped box enclosure, approximately 11 ft by 9 ft in size. The skin of the enclosure is about 3/16" thick Type 304 stainless steel. The internal structural members and supports and exterior support stands are Type 304 stainless steel.
- b) The Material Preparation Glovebox is fitted with gloveports, gloves, lights, and shielded windows to assist in maintenance of the equipment inside. All normal operations inside the glovebox are performed under semi-automatic or manual control.
- c) The Material Preparation Glovebox is provided with radiation shielding to reduce personnel dose rates to ALARA with a goal of 500 mrem/year to the whole body, from all sources within the Pu SPS.
- d) Shielding is a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.

4.1.2.1.2 Specific HWCI Requirements

The Material Preparation Glovebox must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
MPA-2	Remove oxide/inert atmosphere.
SP-27	Convenience can atmosphere.
HGA-6	Oxygen analysis equipment.
HGA-7	Excess oxygen actions.
HGA-11	Preclude oxide dispersion.
E-3	Electrical connections (dust).
E-4	Electrical connections (plugs).
E-6	Lighting - amounts.
E-7	Lighting - type.
E-8	Lighting - location.
SSP-6	304 stainless steel.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PSC-1	Monitor/control interlocks.
PSC-2	Monitor/control environment.
PRI-1	Assay equipment.
PRI-2	Sodium iodine detectors.
RAM-7	Removable shielding.
SAFE-9	Platform/work surfaces.
BOX-1	Design reference documents.
BOX-2	304 stainless steel.
BOX-3	Light windows.
BOX-4	Gloveports.
BOX-5	Storage shelves.
BOX-6	Butt welds/floor fit.
BOX-7	Airlocks.
BOX-8	Consistent appearances.
BOX-9	Pass-through connectors.
BOX-10	Gas supply filters.
BOX-11	Leak tightness.
BOX-12	Glovebox cooling.

- BOX-13 Criticality drains.
- BOX-14 Shutoffs for utilities.
- DECON-2 Glovebox finish.
- DECON-3 Surface sealing.
- DECON-4 Lifting lugs.

4.1.2.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.2.2 Can Handlers

The purpose of this HWCI is for moving site containers and convenience cans within the Material Preparation Glovebox.

4.1.2.2.1 Current Description and Anticipated Operations

- a) Two Can Handlers are provided. The first Can Handler moves site containers/cans to the Container Assay Monitor, and inner site containers to the Decontamination Station and the Compactor Station. The second Can Handler moves site containers/cans to the Container Opening and Metal Brushing Station, and to the Powder Dispensing Station.
- b) Incoming site containers/cans are initially placed on the first Material Preparation Area Can Handler by the Airlock Container Handler, which reaches through the Entry Airlock door and places the site containers/cans on the first Can Handler.
- c) The second Can Handler takes site containers/cans from the first Can Handler by reaching through the Entry Isolation Door separating the Container Opening and Metal Brushing Station from the Decontamination Station.
- d) At any one station, site containers/cans are manually removed from and placed on the Can Handlers. For example, at the Container Assay Monitor, site containers/cans are manually moved between the Can Handler and the Container Assay Monitor.
- e) Convenience cans are removed from the Material Preparation Area through the Exit Isolation Door by the Can/Tray Handler in the Transport Area.

- f) Both Can Handlers have space for only a single site container/can on the handler at one time. This reduces criticality problems because two site containers/cans cannot be placed on one Can Handler at the same time.
- g) Neither Can Handler is required to transport furnace trays. All furnace tray transport, including placing trays at and removing trays from the Powder Dispensing Station, is accomplished with the Can/Tray handler in the Transport Area.
- h) A small purge flow of nitrogen bleeds out of the Can Handlers into the glovebox to minimize contamination of its internal mechanisms.

4.1.2.2.2 Specific HWCI Requirements

The Can Handlers must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
RA-1	Receipt of existing containers.
MPA-1	Unload/decon existing containers.
TA-3	Accurate can/tray movement.
SP-26	Alternate convenience cans.
PSC-1	Monitor/control interlocks.
PSC-4	Control automatic operations.
SAFE-6	Machine guards.
CRIT-9	Metal cans separate in DBE.

4.1.2.2.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.2.3 Entry and Exit Isolation Doors

The purpose of this HWCI is to minimize the spread of contamination from the areas of highest potential contamination (the second section of the Material Preparation Glovebox, where inner site containers/site convenience cans are opened, oxides dispensed, and metals brushed), to the areas of

lowest potential contamination (the first section of the Material Preparation Glovebox, where inner site containers/site convenience cans enter and are assayed, and empty inner site containers decontaminated, compacted, assayed again, and bagged out to disposal/storage; and the Transport Area, where convenience cans and trays are moved between the gloveboxes, furnaces, and sample area).

4.1.2.3.1 Current Description and Anticipated Operations

- a) The door is semi-automatically operated with pneumatic operators.

4.1.2.3.2 Specific HWCI Requirements

The Entry and Exit Isolation Doors must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
SAFE-10	Compressed gases.
BOX-7	Airlocks.
BOX-15	Airlock inop if operator near.
BOX-16	Pneumatic gas type.

4.1.2.3.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.2.4 Container Opener

The purpose of this HWCI is removing the lid of the inner site container (after any packaging materials have been manually cut off).

4.1.2.4.1 Current Description and Anticipated Operations

- a) The packaging materials are cut off and disposed of through a Material Transfer Port located in the Material Preparation Glovebox.
- b) The inner site container ("Freund") is moved into the container opener located in front of the

work area at arms reach, clamped in place, and the lid is removed. The clamp is released and the opened inner site container is placed onto a Can Handler located to the right of the station.

4.1.2.4.2 Specific HWCI Requirements

The Container Opener must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
MPA-1	Unload/decon existing containers.
MPA-6	Open new packages.
E-1	Design criteria.
E-3	Electrical connections (dust).
PSC-1	Monitor/control interlocks.
PSC-4	Control automatic operations.
SAFE-6	Machine guards.
SAFE-9	Platform/work surfaces.
CRIT-9	Metal cans separate in DBE.

4.1.2.4.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.2.5 Powder Dispensing Station

The purpose of this HWCI is to transfer an inner site container/site convenience can plutonium oxide to a furnace tray using a screened feeder funnel, oxide hopper, screw conveyor, oxide vibrator, and tray funnel cover. Plutonium metals remain within the inner site container/site convenience can, which is transferred back to the Metal Brushing Station.

4.1.2.5.1 Current Description and Anticipated Operations

- a) An inner site container/site convenience can holding plutonium oxide, which may be mixed with metal, is conveyed to the Powder Dispensing Station by the Can Handler, where it is clamped to

- a screened feeder funnel. An empty furnace tray is also delivered to the Powder Dispensing Station by the Can/Tray Handler located in the Transport Area, and a sealed connection is made to a tray funnel cover.
- b) The inner site container/site convenience can and funnel are inverted and an oxide vibrator is turned on to help empty the container into an oxide hopper. The screw conveyor at the base of the oxide hopper loads the furnace tray with the aid of a weight detector. When a set weight in the furnace tray is reached or a set volume of oxide has been dispensed, the filling is automatically stopped.
 - c) The plutonium oxide is blended by the following sequence of actions: inversion of the inner site container/site convenience can at the top of the screened feeder funnel, passage through the screen, accumulation in the oxide hopper, passage through the screw conveyor, and accumulation and spreading in the furnace tray using the oxide vibrator.
 - d) After a preset vibration and dust settling time (estimated at 15 to 45 minutes), the furnace tray is disconnected from the tray funnel cover and lowered. The furnace tray is moved to one of the stabilization furnaces by the Can/Tray Handler in the Transport Area.
 - e) The inner site container/site convenience can is lowered from the inverted position and metals that did not pass the screened feeder funnel fall back into the container. The inner site container/site convenience can is manually unclamped, and pieces of metal that are too small to be brushed (< 100 grams) may be removed for stabilization in a furnace tray of oxide. Off-normal site materials (ceramics, graphite, ferrous hardware, chunky oxides, etc.) may also be removed for disposition by an operator. The inner site container/site convenience can is then placed on the Can/Tray Handler, which moves it back to the Metal Brushing Station.
 - f) Small pieces of plutonium metal for stabilization can be placed in a small transfer vessel for movement to the LOI Sampling Station by the Can/Tray Handler.
 - g) Rework capabilities are provided within the Material Preparation Area. Storage packages which are retrieved for inspection or which fail the leak detection test are introduced back into the Pu SPS via the Receipt Area. After the outer can is removed, the same process as described above is used for these rework packages.

4.1.2.5.2 Specific HWCI Requirements

The Powder Dispensing Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
MPA-1	Unload/decon existing containers.
MPA-3	Combine brushed oxides.
MPA-4	Homogenize oxides.
MPA-7	Place small Pu metal with oxide.
MPA-8	Handle coarse materials.
MPA-9	Non-homogeneous oxides.
MPA-10	Inspect pre/post stabilization.
MPA-15	Automated oxide dispensing.
MPA-16	Auto tray overfill checking.
FT-1	Maximum container capacity.
FT-2	Maximum oxide depth.
HGA-11	Preclude oxide dispersion.
E-1	Design criteria.
E-3	Electrical connectors (dust).
SP-26	Alternate convenience cans.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PSC-2	Monitor/control interlocks.
PSC-4	Control automatic operations.
SAFE-6	Machine guards.
CRIT-9	Metal cans separate in DBE.

4.1.2.5.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.2.6 Metal Brushing Station

The purpose of this HWCI is removing plutonium metals from the inner site containers/site

convenience cans, brushing the loose oxides off, then placing the metals into clean screw top convenience cans (or reusing the site convenience cans by replacing the convenience can cap). Filled cans are capped and made available to Can/Tray Handler in the Transport Area. Brushed oxides are returned via a Can Handler to the Powder Dispensing Station.

4.1.2.6.1 Current Description and Anticipated Operations

- a) Inner site containers/site convenience cans with plutonium metals are conveyed to the Metal Brushing Station from the Powder Dispensing Station by the Can Handler. Here the metal pieces are removed from the inner site container/site convenience can and loose oxides are manually brushed from the metal pieces into the original inner site container/site convenience can in an isolated environment. The inner site container/site convenience can, with brushed plutonium oxides, is then conveyed by the Can Handler, back to the Powder Dispensing Station, and the powder added to the oxide stream awaiting stabilization.
- b) The brushed plutonium metals may be placed into a new convenience can or into a site convenience can. If a site convenience can is used, then its cap must be replaced with one that will fit with a positive closure mechanism and has magnetic properties for use by handling equipment in the packaging process. When the proper measured weight of metal has been placed in the convenience can, the top is replaced and the can is placed into an accumulator which lowers the cans for access by a Can/Tray Handler in the Transport Area.
- c) Convenience cans containing plutonium metals are marked with a bar code. These bar codes are read with a bar code reader through a viewport for data entry into the PSCS.
- d) Scale accuracy will be per reference 2.7 with a readability of 1.0 grams for an 8000 gram maximum capacity.

4.1.2.6.2 Specific HWCI Requirements

The Metal Brushing Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
MPA-2	Remove oxide/inert atmosphere.
MPA-3	Combine brushed oxides.
MPA-7	Place small Pu metal w/oxide.

MPA-8	Handle coarse materials.
SP-26	Alternate convenience cans.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
FPS-3	Oxide heat detectors.
FPS-5	Mag oxide buckets.
PSC-3	Entry of process data.
PPC-1	Can balances.
SAFE-9	Platform/work surfaces.
CRIT-5	Fixed location for metal cans.
CRIT-8	Covered trays and cans.
CRIT-11	One metal convenience can.
CRIT-12	Only one container (make-up)

4.1.2.6.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.2.7 Convenience Can Transfer Port

The purpose of this HWCI is passing convenience cans, or just their caps, into or out of the Material Preparation Glovebox for plutonium metal filling without a breach of glovebox confinement.

4.1.2.7.1 Current Description and Anticipated Operations

- a) New convenience cans or replacement can caps are posted in through a transfer port. Only one convenience can may be in the Metal Brushing Area at one time.
- b) Convenience can caps that have been replaced are placed into the transfer port for bagging prior to disposal/storage.

4.1.2.7.2 Specific HWCI Requirements

The Convenience Can Transfer Port must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No. Summary of Requirement

MPA-2	Remove oxide/inert atmosphere.
SP-26	Alternate convenience cans.
PSC-1	Monitor/control interlocks.
PSC-3	Entry of process data.
BOX-9	Pass-through connectors.
BOX-11	Leak tightness.
SAFE-9	Platforms/work surfaces.
CRIT-11	One metal convenience can.

4.1.2.7.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.2.8 Decontamination Station

The purpose of this HWCI is to reduce the plutonium oxide layer present on the inner surface of the empty inner site containers sufficiently to more efficiently meet transportation (TRUPACT-II) and storage (WIPP) requirements.

4.1.2.8.1 Current Description and Anticipated Operations

- a) The Decontamination Station incorporates a vacuum system that consists of a brush mounted on the inlet nozzle and two filtration stages. The first stage, located within the glovebox, uses a cyclone separator and a cleanable high efficiency prefilter. Plutonium oxide will be collected in the first stage. The second stage, located outside of the glovebox, uses a cartridge HEPA filter.
- b) Site convenience cans not reused will be decontaminated.
- c) The Decontamination Station is separated by the Entry Isolation Door from the Metal Brushing and Powder Dispensing Stations to it keep relatively clean.
- d) Inner site containers are brought into the Decontamination Station and visually inspected by an operator before they are cleaned.

- e) After the inner site container has been cleaned it is visually inspected again. Plutonium oxide has a green tint that should be easily observed by the operator. If it is apparent that the oxide is below a readily visible 0.3 grams of ^{239}Pu FGE, the inner site container is transferred by the Can Handler to the Compactor Station.

Additional Information: In accordance with the TRUPACT-II Authorized Methods for Payload Control (TRAMPAC) document, the maximum allowable ^{239}Pu fissile gram equivalent (FGE) per TRUPACT-II is 325 grams. This quantity includes the measured value plus the total error. Each TRUPACT-II can accommodate 14 standard 55-gallon waste drums. All of which must share the 325 gram ^{239}Pu FGE limit. This leaves on average only 23.2 grams of ^{239}Pu FGE per waste drum.

Oxide residue has been estimated to be approximately 25 microns thick. If uniform thickness exists over the inner surface area of each inner container, then as much as 4.6 grams of plutonium oxide could be present per inner container.

Disposal of as many as 75 compacted containers per 55 gallon drum (depending on site specific requirements) limits the ^{239}Pu FGE per container to no more than 0.3 grams. This equates to an oxide layer no thicker than 1.6 microns.

4.1.2.8.2 Specific HWCI Requirements

The Decontamination Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
MPA-1	Unload/decon existing containers.
E-1	Design criteria.
E-3	Electrical connectors (dust).
PSC-1	Monitor/control interlocks.
PSC-3	Entry of process data.
PSC-4	Control automatic operations.
EMR-1	Assay equipment protection.
SAFE-7	Electrical safety.
SAFE-9	Platform/work surfaces.
SAFE-10	Compressed gases.
DECON-3	Surface sealing.

4.1.2.8.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.2.9 Compactor Station

The purpose of this HWCI is compressing (primarily) inner site containers after decontamination to reduce waste disposal/storage volume.

4.1.2.9.1 Current Description and Anticipated Operations

- a) An inner site container is transferred to the Compactor Station by a Can Handler after it has been emptied and decontaminated.
- b) The inner site container is placed upside down in the Compactor Station, with its lid placed on the container's bottom side by the operator.
- c) A safety door on the Compactor Station is closed and the operator activates the electric motor by using both hands for simultaneous interlock activation within the glovebox.
- d) The inner site container is compacted by mechanical force. The container gas atmosphere is vented within the glovebox through an air escape hole in the base of the Compactor Station.
- e) Compaction will reduce the inner site container volume by about 80%.

4.1.2.9.2 Specific HWCI Requirements

The Compactor Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
MPA-1	Unload/decon existing containers.
MPA-11	Compact existing containers.
MPA-12	Maximum compaction height.
MPA-13	Compactor interlock.

MPA-14	Operation within 5 minutes.
PSC-1	Monitor/control interlocks.
PSC-3	Entry of process data.
PSC-4	Control automatic operations.
SAFE-6	Machine guarding.
SAFE-9	Platform/work surfaces.

4.1.2.9.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.2.10 Material Transfer Ports

The purpose of these HWCI is to remove metal radioactive wastes, plastic/tape radioactive wastes, and to transfer other items in or out of the Material Preparation Glovebox.

4.1.2.10.1 Current Description and Anticipated Operations

- a) The compacted inner site containers and any uncrushed containers or cans are placed into a Material Transfer Port for bagging and loaded into a waste disposal drum.
- b) The plastic/tape wastes are placed into a Material Transfer Port for bagging and loaded into a waste disposal drum.

4.1.2.10.2 Specific HWCI Requirements

The Material Transfer Ports must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
MPA-1	Unload/decon existing containers.
MPA-2	Remove oxide/inert atmosphere.
MPA-5	Remove plastics, etc.
SAFE-9	Platforms/work surfaces.
BOX-11	Leak tightness.

4.1.2.10.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.3 Transport Area

This area automatically transports convenience cans of plutonium metal and furnace trays between the Material Preparation Area, the Furnace Area, the LOI Test Area, and the Tipping/Dispense/Fill Area with no operator manual involvement. The Transport Area includes the following major equipment items: the Transport Glovebox, the Can/Tray Handler, and the Transport Glovebox Television Monitoring System.

All equipment in the Transport Area must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCIs are identified in the following discussions.

4.1.3.1 Transport Glovebox

The purpose of this HWCI to confine radioactive materials within the glovebox, maintain an inert (nitrogen) atmosphere for processing plutonium metals and oxides, and provide radiation shielding for operators.

4.1.3.1.1 Current Description and Anticipated Operations

- a) The Transport Glovebox is a leaktight stainless steel rectangular box enclosure, approximately 1 ft by 12 ft in size. The skin of the enclosure is about 3/16" thick Type 304 stainless steel. The internal structural members and supports and exterior support stands are Type 304 stainless steel.
- b) The Transport Glovebox is fitted with gloveports, gloves, lights, and shielded windows to assist in maintenance of the Can/Tray Handler. All operations inside the glovebox are normally performed under automatic control, with no manual intervention required.
- c) The Transport Glovebox is provided with radiation shielding to reduce personnel dose rates to ALARA with a goal of 500 mrem/year to the whole body, from all sources within the Pu SPS.
- d) Shielding is a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.

4.1.3.1.2 Specific HWCI Requirements

The Transport Glovebox must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

HGA-6	Oxygen analysis equipment.
HGA-7	Excess oxygen actions.
HGA-11	Preclude oxide dispersion.
E-3	Electrical connections (dust).
E-4	Electrical connections (plugs).
E-6	Lighting - amounts.
E-7	Lighting - type.
E-8	Lighting - location.
SSP-6	304 stainless steel.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PSC-2	Monitor/control environment.
PRI-2	Sodium iodine detectors.
RAM-7	Removable shielding.
BOX-1	Design reference documents.
BOX-2	304 stainless steel.
BOX-3	Light windows.
BOX-4	Gloveports.
BOX-5	Storage shelves.
BOX-6	Butt welds/floor fit.
BOX-7	Airlocks.
BOX-8	Consistent appearances.
BOX-9	Pass-through connectors.
BOX-10	Gas supply filters.
BOX-11	Leak tightness.
BOX-12	Glovebox cooling.
BOX-13	Criticality drains.
BOX-14	Shutoffs for utilities.
CRIT-10	No DBE water in furnace.

DECON-2 Glovebox finish.
DECON-3 Surface sealing.
DECON-4 Lifting lugs.

4.1.3.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.3.2 Can/Tray Handler

The purpose of this HWCI is moving filled furnace trays out of the Material Preparation Area, into (and out of) the Furnace Area and LOI Test Area, and into the Tipping/Dispense/Fill Area. It returns empty furnace trays from the Tipping/Dispense/Fill Area to the Material Preparation Area. It also moves convenience cans out of the Material Preparation Area and into the Tipping/Dispense/Fill Area. It has the capability of moving furnace trays into the LOI Test Area for visual inspection, and moving transfer vessels of small pieces of plutonium metals into the LOI Test Area for placement into furnace trays of oxide for stabilization.

4.1.3.2.1 Current Description and Anticipated Operations

- a) The Can/Tray Handler transports furnace trays containing unstabilized plutonium oxide from the Material Preparation Area into the Furnace Area. The Can/Tray Handler places the furnace tray inside the furnace through the open furnace door.
- b) The Can/Tray Handler consists of a carriage propelled by a linear motor to provide positioning for various stations, and a robotic arm mounted on the carriage to provide four degrees of freedom. The robotic arm is fitted with an end effector to pick and place furnace trays and convenience cans at the various stations.
- c) Convenience cans containing plutonium metals are transported through the Transport Area from the Material Preparation Area to the Tipping/Dispense/Fill Area. The cans are not opened or processed in any way in the Transport Area.
- d) Transfer vessels containing small plutonium metal pieces to be stabilized can be transported from the Material Preparation Glovebox to the LOI Test Area by the Can/Tray Handler.

- e) A small purge flow of nitrogen bleeds out of the Can/Tray Handler into the glovebox to minimize contamination of its internal mechanisms.

4.1.3.2.2 Specific HWCI Requirements

The Can/Tray Handler must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
SP-26	Alternate convenience cans.
PSC-1	Monitor/control interlocks.
PSC-4	Control automatic operations.
PPC-2	Monitor/control interlocks.
CRIT-5	Fixed location for metal cans.
CRIT-9	Metal cans separate in DBE.

4.1.3.2.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.3.3 Transport Glovebox Television Monitoring System

The purpose of this HWCI is to provide operators with the capability to visually monitor the operation of the automated Can/Tray Handler. In this way, the robotics becomes an observable extension or remote assist to the operator.

4.1.3.3.1 Current Description and Anticipated Operations

- a) The Transport Glovebox includes viewports for the closed circuit television cameras, which are installed outside of the glovebox in fixed locations.
- b) Television monitor(s) are located at the remote control console, and provide a view of Can/Tray Handler operations, furnace contents during loading/unloading, and furnace door operations.

4.1.3.3.2 Specific HWCI Requirements

The Transport Glovebox Television Monitoring System must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
TA-4	Remote visual monitoring.

4.1.3.3.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.4 Furnace Area

This area is used for thermal stabilization of plutonium oxide. The Furnace Area includes the following major equipment items: two Furnace Gloveboxes, each with a Stabilization Furnace.

All equipment in the Furnace Area must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCIs are identified in the following discussions.

4.1.4.1 Furnace Glovebox

The purpose of this HWCI is to confine radioactive materials within the glovebox, maintain an inert atmosphere within the glovebox when not stabilizing plutonium, provide radiation shielding for operators, and provide structural support for equipment associated with the glovebox.

4.1.4.1.1 Current Description and Anticipated Operations

- a) Each Furnace Glovebox is a leaktight stainless steel rectangular box enclosure, approximately 3½ ft by 4 ft in size. The skin of the enclosure is about 3/16" thick Type 304 stainless steel. The internal structural members and supports and exterior support stands are Type 304 stainless steel.
- b) Each Furnace Glovebox is fitted with removable panels to allow access to the furnaces for repair or element replacement. The furnace door and chamber is accessible from gloveports and windows located in the Transport Area for minor maintenance and repair.

- c) Each Furnace Glovebox is provided with radiation shielding to reduce personnel dose rates to ALARA with a goal of 500 mrem/year to the whole body, from all sources within the Pu SPS.
- d) Shielding is a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.
- e) Each Furnace Glovebox is swept with inerting system gas to maintain an inert atmosphere and provide partial cooling of the furnace. Both an inerting gas supply and an exhaust will be provided in each of the furnace glovebox areas.
- f) Supplemental cooling of the furnace glovebox will be provided by water cooled panels attached to the sides of the furnaces. The cooling loop water volume will be limited by using a closed loop or "limited supply" equipment arrangement. The supply volume will be limited to a volume equivalent to less than a 2" depth in the furnace glovebox area.

4.1.4.1.2 Specific HWCII Requirements

The Furnace Gloveboxes must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
FURN-5	Furnace controller.
HGA-11	Preclude oxide dispersion.
E-3	Electrical connectors (dust).
E-4	Electrical connectors (plugs).
SSP-6	304 stainless steel.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PSC-1	Monitor/control interlocks.
PSC-2	Monitor/control environment.
PRI-2	Sodium iodine detectors.
RAM-7	Removable shielding.
BOX-1	Design reference documents.
BOX-2	304 stainless steel.
BOX-6	Butt welds/floor fit.
BOX-8	Consistent appearances.
BOX-9	Pass-through connectors.

- BOX-10 Gas supply filters.
- BOX-11 Leak tightness.
- BOX-12 Glovebox cooling.
- BOX-13 Criticality drains.
- BOX-14 Shutoffs for utilities.
- DECON-2 Glovebox finish.
- DECON-3 Surface sealing.
- CRIT-10 No DBE water in furnace.

4.1.4.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.4.2 Stabilization Furnaces

The purpose of this HWCI is to thermally stabilize the plutonium oxide powder at a temperature of 1000 C for a minimum of two hours in an oxidizing atmosphere.

4.1.4.2.1 Description and Operation

- a) Two independent Stabilization Furnaces are provided, each of which is capable of meeting the throughput requirements. Each furnace is capable of processing two trays of plutonium oxide at a time. The stabilization furnaces are connected to the Transport Area at their material transfer end. The Stabilization Furnaces consist of the furnace itself with a pneumatically operated furnace door, furnace controls, and water cooled panels.
- b) One of the two Stabilization Furnaces is charged with two furnace trays from the Can/Tray Handler in the Transport Area, through the furnace door. The furnace door is closed and the furnace cycle is initiated. The stabilization cycle will be alternated between the two furnaces. Loading of furnace trays of plutonium oxide and heating, and cooling of furnace trays and unloading, will be performed on alternate days.
- c) The Stabilization Furnaces are capable of temperatures of about 1200 C and can be controlled ± 50 C. The furnaces operate with 480 VAC 3-phase power.

- d) During stabilization, the furnace atmosphere is instrument/plant air. The air is piped directly into the Stabilization Furnace and exhausted into the Downdraft System.
- e) The air supply is monitored for moisture content (< 1000 ppm moisture).
- f) After stabilization is completed, a purge of nitrogen gas will be used. The purge rate will be the same as the oxidation air rate. The nitrogen will be monitored for moisture content.
- g) The furnace trays are cooled to room temperature within the nitrogen inerted Stabilization Furnaces.
- h) The furnace door is opened and the Can/Tray Handler removes the furnace tray of stabilized oxide.
- i) The chamber size of each of the Stabilization Furnaces is about 14"x14"x14", to accommodate two trays.

4.1.4.2.2 Specific HWCI Requirements

The Stabilization Furnaces must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

FURN-1	Oxide temp/time.
FURN-5	Furnace controller.
FURN-6	Furnace temp/time.
HGA-11	Preclude oxide dispersion.
E-1	Design Criteria.
PSC-4	Control automatic operations.
CRIT-7	Furnace tray spacing.
CRIT-9	Covered trays and cans.
HENG-6	Display devices.

4.1.4.2.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.5 LOI Test Area

This area verifies that plutonium oxide processed through the stabilization furnaces has achieved an acceptable Loss on Ignition (LOI) test value. It also serves as a visual inspection station for furnace trays and provides a location for placement of small pieces of plutonium metal into a furnace tray of oxide. The LOI Test Area includes the following major equipment items: the LOI Glovebox, the LOI Sampling Station, the Sample Desiccator, and the LOI Furnace.

All equipment in the LOI Test Area must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCI's are identified in the following discussions.

4.1.5.1 LOI Glovebox

The purpose of this HWCI is to confine radioactive materials within the glovebox, maintain a shielded and dry atmosphere for testing plutonium oxides, and provide radiation shielding for operators.

The LOI Glovebox is connected to the Transport Area, where a Can/Tray Handler will deliver a furnace tray from the Furnace Area to the LOI Glovebox. Samples are taken manually from each furnace tray and then LOI tested. The LOI Test Area includes a small muffle furnace that operates at conditions similar to the main Stabilization Furnaces. Spent samples are returned to the next batch of furnace trays of plutonium oxides.

4.1.5.1.1 Current Description and Anticipated Operations

- a) The LOI Glovebox is a leaktight stainless steel rectangular box enclosure, approximately 3 ft by 4 ft in size. The skin of the enclosure is about 3/16" thick Type 304 stainless steel. The internal structural members and supports and exterior support stands are Type 304 stainless steel.
- b) The LOI Glovebox is fitted with gloveports, gloves, lights, and shielded windows to operate the equipment inside. All operations inside the glovebox are performed manually.
- c) Cooling the LOI glovebox is performed by sweeping the area with inerting system gas.
- d) The LOI Glovebox is provided with radiation shielding to reduce personnel dose rates to ALARA with a goal of 500 mrem/year to the whole body, from all sources within the Pu SPS.
- e) Shielding is a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.

4.1.5.1.2 Specific HWCI Requirements

The LOI Glovebox must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

FURN-2	Furnace atmosphere.
FURN-4	Outside temperature.
HGA-11	Preclude oxide dispersion.
E-3	Electrical connectors (dust).
E-4	Electrical connectors (plugs).
E-6	Lighting - amounts.
E-7	Lighting - types.
E-8	Lighting - location.
SSP-6	304 stainless steel.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PSC-1	Monitor/control interlocks.
PSC-2	Monitor/control environment.
PRI-2	Sodium iodine detectors.
RAM-7	Removable shielding.
SAFE-9	Platform/work surfaces.
BOX-1	Design reference documents.
BOX-2	304 stainless steel.
BOX-3	Light windows.
BOX-4	Gloveports.
BOX-5	Storage shelves.
BOX-6	Butt welds/floor fit.
BOX-8	Consistent appearances.
BOX-9	Pass-through connectors.
BOX-10	Gas supply filters.
BOX-11	Leak tightness.
BOX-12	Glovebox cooling.
BOX-13	Criticality drains.
BOX-14	Shutoffs for utilities.
DECON-2	Glovebox finish.

DECON-3 Surface sealing.

DECON-4 Lifting lugs.

4.1.5.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.5.2 LOI Sampling Station

The purpose of this HWCI is to obtain a plutonium oxide sample from the furnace trays for LOI testing.

4.1.5.2.1 Current Description and Anticipated Operations

- a) The Can/Tray Handler in the Transport Area places the furnace tray within the LOI Test Area for sampling.
- b) The sampling device is located in the LOI Area. A representative sample is manually removed from the furnace tray and placed in a crucible. The sample crucible and furnace tray identifiers are manually recorded via a local keyboard.
- c) The nominal sample size is estimated to be up to 20 to 30 grams.
- d) Samples are weighed both before and after heating in the LOI furnace. The weights are automatically entered into the PSCS, and the change in weight is calculated.
- e) The Can/Tray Handler in the Transport Area removes the furnace tray from the LOI Test Area once a sample has been taken.
- f) Empty furnace trays may be visually inspected for integrity at the LOI Sampling Station before being moved to the tray weighing portion of the Powder Dispensing Station, and oxide filled furnace trays may be inspected before and after thermal stabilization.
- g) Transfer vessels containing small plutonium metal pieces (< 100 grams) can be brought to the LOI Sampling Station for an operator to place them in a furnace tray of plutonium oxide prior to stabilization.

4.1.5.2.2 Specific HWCI Requirements

The LOI Sampling Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

MPA-7	Place small Pu metal w/oxide.
MPA-8	Handle coarse materials.
MPA-10	Inspect pre/post stabilization.
LOI-2	Test accuracy.
LOI-4	Weigh just after cooling.
FT-2	Maximum oxide depth.
E-1	Design criteria.
FPS-5	Mag oxide buckets.
PSC-1	Monitor/control interlocks.
PSC-3	Entry of process data.
PSC-4	Control automatic operations.
SAFE-9	Platform/work surfaces.
HENG-6	Display devices.

4.1.5.2.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.5.3 Sample Desiccator

The purpose of this HWCI is maintaining the LOI samples in a very dry atmosphere while the samples are cooling outside the LOI Furnace from 200 C to ambient room temperature, prior to being weighed a second time. This ensures that the samples will not readsorb moisture during this interval, which could lead to false LOI test results.

4.1.5.3.1 Current Description and Anticipated Operations

- The Sample Desiccator is a sealed chamber supplied with nitrogen having a moisture content of < 100 ppm (-45 C dew point). Nitrogen pressure in the desiccator will be at a slight positive pressure, relative to the LOI Glovebox (but still negative relative to the room atmosphere), to

ensure that no humid glovebox nitrogen affects the LOI sample. The nitrogen is leaked into the LOI Glovebox.

- b) The samples are manually placed into the Sample Desiccator directly from the LOI Furnace when the LOI Furnace has cooled to 200 C.
- c) After the samples are allowed to cool to approximately room temperature in the desiccator, they are manually removed from the Sample Desiccator and weighed, one by one. Each sample must be weighed within an estimated 5 minutes of opening the Sample Desiccator door.

4.1.5.3.2 Specific HWCI Requirements

The Sample Desiccator must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
LOI-3	Cool in desiccator.
LOI-4	Weigh just after cooling.
FPS-1	Detection/alarm system.
PSC-1	Monitor/control interlocks.
PSC-2	Monitor/control environment.
RAM-7	Removable shielding.
BOX-1	Design reference documents.
BOX-2	304 stainless steel.
BOX-5	Storage shelves.
BOX-6	Butt welds/floor fit.
BOX-7	Airlocks.
BOX-8	Consistent appearances.
BOX-9	Pass-through connectors.
BOX-10	Gas supply filters.
BOX-11	Leak tightness.
BOX-12	Glovebox cooling.
BOX-13	Criticality drains.
BOX-14	Shutoffs for utilities.
DECON-2	Glovebox finish.
DECON-3	Surface sealing.

4.1.5.3.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.5.4 LOI Furnace

The purpose of this HWCI is heating the plutonium oxide sample to determine completeness of the stabilization process.

4.1.5.4.1 Current Description and Anticipated Operations

- a) The LOI Furnace is sized to test at least 2 crucible samples at one time.
- b) The LOI Furnace is capable of a maximum temperature of about 1200 C. The temperature can be controlled to about -0/+50 C and operates on 480 VAC 3-phase power.
- | c) During LOI testing, the LOI Furnace atmosphere is instrument/plant air. The air supply is monitored for moisture content (< 1000 ppm maximum moisture) and filtered prior to injection into the LOI Furnace.
- d) The LOI Furnace and samples are cooled with dry air until the furnace has cooled to approximately 200 C, at which time the furnace door is opened and the test crucibles are manually removed.
- | e) The LOI Furnace cavity is square; approximately 6" wide, 6" deep, 6" tall.
- | f) The LOI Furnace exterior shell is rectangular; approximately 24" wide, 24" deep, and 20" tall.

4.1.5.4.2 Specific HWCI Requirements

The LOI Furnace must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

FURN-2	Furnace atmosphere.
--------	---------------------

FURN-3	Inside glovebox.
LOI-1	Test method.
HGA-11	Preclude oxide dispersion.
E-1	Design criteria.
PSC-1	Monitor/control interlocks.
PSC-4	Control automatic operations.
SAFE-6	Machine guards.

4.1.5.4.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

Packaging Process

4.1.6 Tipping/Dispense/Fill Area

This area transfers plutonium oxides in furnace trays to convenience cans, and moves filled convenience cans (of both oxide and metal) to the Can Weigh and Cap Insertion Area. The Tipping/Dispense/Fill Area includes the following major equipment items: the Oxide Tipping Glovebox, the Seismic Displacement Absorber, the Furnace Tray Elevator/Transpose Unit, the Furnace Tray Tipper, the Convenience Can Transfer Unit, a Material Transfer Port, the Dispense/Fill Glovebox, the Convenience Can Post In Sphincter Seal, the Convenience Can Handler, and the Convenience Can Post Out Unit. External to the gloveboxes is a Convenience Can Identification and Weigh Station.

All equipment in the Transfer/Dispense/Fill Area must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCIs are identified in the following discussions.

4.1.6.1 Oxide Tipping Glovebox

The purpose of this HWCIs to confine radioactive materials within the glovebox, maintain an inert (nitrogen) atmosphere for processing plutonium metals and oxides, and provide radiation shielding for operators.

4.1.6.1.1 Current Description and Anticipated Operations

- a) The Oxide Tipping Glovebox shell is a leaktight stainless steel enclosure, approximately 2 m high by 1 m wide by 1.5 m deep in size. The skin of the enclosure is about 10 mm thick Type 304 stainless steel. The internal structure members and supports and exterior supports are Type 304 stainless steel.
- b) The Oxide Tipping Glovebox is fitted with gloveports, gloves, lights, and shielded windows to assist with maintenance of internal equipment. All normal operations inside the glovebox are performed under semi-automatic control with no manual intervention.
- c) The Oxide Tipping Glovebox is provided with radiation shielding to reduce personnel dose to ALARA with a goal of 500 mrem/year to the whole body from all sources within Pu SPS.
- d) Shielding is a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.

4.1.6.1.2 Specific HWCI Requirements

The Oxide Tipping Glovebox must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
HGA-6	Oxygen analysis equipment.
HGA-7	Excess oxygen actions.
HGA-11	Preclude oxide dispersion.
E-3	Electrical connections (dust).
E-4	Electrical connections (plugs).
E-6	Lighting - amounts.
E-7	Lighting - type.
E-8	Lighting - location.
SSP-6	304 stainless steel.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PSC-1	Monitor/control interlocks.
PPC-2	Monitor/control interlocks.
PPC-3	Monitor/control environment.
PRI-2	Sodium iodine detectors.
RAM-7	Removable shielding.
BOX-1	Design reference documents.
BOX-2	304 stainless steel.
BOX-3	Light windows.
BOX-4	Gloveports.
BOX-5	Storage shelves.
BOX-6	Butt welds/floor fit.
BOX-8	Consistent appearances.
BOX-9	Pass-through connectors.
BOX-10	Gas supply filters.
BOX-11	Leak tightness.
BOX-13	Criticality drains.
BOX-14	Shutoffs for utilities.
DECON-2	Glovebox finish.
DECON-3	Surface sealing.
DECON-4	Lifting lugs.

4.1.6.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.6.2 Seismic Displacement Absorber

The purpose of this HWCI is seismic decoupling of the stabilization process from the packaging process by allowing the two process sections to move independently of each other during a design basis seismic event. This permits the two process sections to be dynamically analyzed separately.

4.1.6.2.1 Current Description and Anticipated Operations

- a) The Seismic Displacement Absorber consists of two stainless steel flanges connected by a bellows allowing movement between two independent gloveboxes, the Transport Glovebox and the Oxide Tipping Glovebox.
- b) The overall size is approximately 750 mm square, with a 575 mm inside diameter and a length of 300 mm.

4.1.6.2.2 Specific HWCI Requirements

The Seismic Displacement Absorber must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

SSP-8	Seismic decoupling.
-------	---------------------

4.1.6.2.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.3 Furnace Tray Elevator/Transpose Unit

The purpose of this HWCI is movement of furnace trays from the drop off location of the Can/Tray Handler in the Transport Area to the Furnace Tray Tipper and back again.

4.1.6.3.1 Current Description and Anticipated Operations

- a) The tray transpose unit collects full furnace trays of plutonium oxide from a defined location and specified orientation.
- b) The full furnace trays are raised by a servomotor elevator and transferred into the tipping arm by the tray transpose unit.
- c) Empty furnace trays are retrieved from the tipping arm and lowered by an elevator, then and transferred to a defined location for retrieval by the Can/Tray Handler in the Transport Area.

4.1.6.3.2 Specific HWCI Requirements

The Furnace Tray Elevator/Transpose Unit must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

TFA-1	Auto move trays to tipper arm.
PPC-5	Control automatic ops.

4.1.6.3.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.4 Furnace Tray Tipper

The purpose of this HWCI is emptying the plutonium oxide in a furnace tray by inverting them, then allowing the oxide to flow down (with vibratory assistance) through a dispense tube into a convenience can.

4.1.6.4.1 Current Description and Anticipated Operations

- a) The Furnace Tray Tipper receives a furnace tray from the Elevator/Transpose Unit, into a vertically arranged radial arm.
- b) The furnace tray is automatically clamped by a spring mechanism when the tipping arm starts to move.
- c) The tipping arm rotates through 180° driven by an electrical actuator located outside of the Oxide Tipping Glovebox.
- d) The tray contents are emptied into a convenience can via a pneumatic valve and dispensing tube.
- e) The tipping arm rotates back 180° to return the empty tray to the Elevator/Transpose Unit.

4.1.6.4.2 Specific HWCI Requirements

The Furnace Tray Tipper must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
TFA-3	Controlled oxide tipping.
TFA-7	Handle chunky oxides.
PPC-5	Control automatic ops.
BOX-16	Pneumatic gas type.
SAFE-10	Compressed gases.

4.1.6.4.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.5 Convenience Can Transfer Unit

The purpose of this HWCI is moving convenience cans of plutonium metal from the dropoff location of the Transport Area Can/Tray Handler, then depositing them at the Cap Removal/Replacement Station.

4.1.6.5.1 Current Description and Anticipated Operations

- a) An electromagnet picks up a metal filled convenience can by its lid from the defined drop off location.
- b) A pneumatic cylinder raises the electromagnet (and can), and a rodless pneumatic cylinder transfers the can to the start of the carousel.
- c) The can is lowered, and the electromagnet de-energized to release the can.

4.1.6.5.2 Specific HWCI Requirements

The Convenience Can Transfer Unit must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
TFA-5	Auto move cans in area.
SP-26	Alternate convenience cans.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.
CRIT-5	Fixed location for metal cans.
CRIT-9	Metal cans separate in DBE.

4.1.6.5.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.6 Material Transfer Port

The purpose of this HWCI is only for transfer of equipment for maintenance purposes.

4.1.6.6.1 Current Description and Anticipated Operations

- a) The Material Transfer Port enables transfer of equipment into and from the Tipping/Dispense/Fill Area during maintenance work.

4.1.6.6.2 Specific HWCI Requirements

The Material Transfer Port must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
SAFE-9	Platforms/work areas.
BOX-11	Leak tightness.

4.1.6.6.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.7 Dispense/Fill Glovebox

The purpose of this HWCI to confine radioactive materials within the glovebox, maintain an inert (nitrogen) atmosphere for processing plutonium metals and oxides, and provide radiation shielding for operators.

4.1.6.7.1 Current Description and Anticipated Operations

- a) The glovebox shell is a leaktight stainless steel enclosure, approximately 2 m high by 1.5 m wide by 1.3 m deep in size. The skin of the enclosure is about 10 mm thick Type 304 stainless steel. The internal structure members and supports and exterior supports are Type 304 stainless steel.
- b) The Dispense/Fill Glovebox is fitted with gloveports, gloves, lights, and shielded windows to assist with maintenance of internal equipment. Most normal operations inside the glovebox are performed under semi-automatic control with limited manual intervention for loading empty convenience cans.
- c) The Dispense/Fill Glovebox is provided with radiation shielding to reduce personnel dose to ALARA with a goal of 500 mrem/year to the whole body from all sources within Pu SPS.
- d) Shielding is a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.

- e) The atmosphere supply to the Dispense/Fill Glovebox, which is ultimately the atmosphere within the convenience can, is monitored for composition and moisture content.

4.1.6.7.2 Specific HWCI Requirements

The Dispense/Fill Glovebox must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
SP-27	Convenience can atmosphere.
HGA-6	Oxygen analysis equipment.
HGA-7	Excess oxygen actions.
E-3	Electrical connections (dust).
E-4	Electrical connections (plugs).
E-6	Lighting - amounts.
E-7	Lighting - type.
E-8	Lighting - location.
SSP-6	304 stainless steel.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PPC-2	Monitor/control interlocks.
PPC-3	Monitor/control environment.
PRI-2	Sodium iodine detectors.
RAM-7	Removable shielding.
BOX-1	Design reference documents.
BOX-2	304 stainless steel.
BOX-3	Light windows.
BOX-4	Gloveports.
BOX-5	Storage shelves.
BOX-6	Butt welds/floor fit.
BOX-7	Airlocks.
BOX-8	Consistent appearances.
BOX-9	Pass-through connectors.
BOX-10	Gas supply filters.
BOX-11	Leak tightness.
BOX-13	Criticality drains.
BOX-14	Shutoffs for utilities.

DECON-2 Glovebox finish.
DECON-3 Surface sealing.
DECON-4 Lifting lugs.

4.1.6.7.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.6.8 Convenience Can Post In Sphincter Seal

The purpose of this HWCI is passing convenience cans into the Dispense/Fill Glovebox for plutonium oxide filling without a breach of glovebox confinement.

4.1.6.8.1 Current Description and Anticipated Operations

- a) The sphincter seal is a multiple rubber ring system sized to the diameter of a convenience can.
- b) New convenience cans are posted in through the sphincter seal and staged in the Convenience Can Magazine.
- c) An empty convenience can is always present in the sphincter seal to maintain the glovebox environment.
- d) Operational procedures and an internal stop bar prevents inadvertent ejection of a can.

4.1.6.8.2 Specific HWCI Requirements

The Convenience Can Post In Sphincter Seal must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

BOX-11	Leak tightness.
--------	-----------------

4.1.6.8.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.9 Convenience Can Magazine

The purpose of this HWCI is temporary storage of three convenience cans within the glovebox, prior to filling operations.

4.1.6.9.1 Current Description and Anticipated Operations

- a) When required, convenience cans are automatically fed from the magazine to the Convenience Can Handler Unit at the Can Loading Station.

4.1.6.9.2 Specific HWCI Requirements

The Convenience Can Magazine must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

TFA-5	Auto move cans in area.
-------	-------------------------

PPC-5	Control automatic ops.
-------	------------------------

4.1.6.9.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.10 Convenience Can Handler

The purpose of this HWCI is movement of convenience cans around the carousel, within the Dispense/Fill Glovebox, visiting the various stations as required.

4.1.6.10.1 Current Description and Anticipated Operations

- a) The Convenience Can Handler consists of a horizontal radial arm and a semi-circular carousel. The arm is driven by an electric drive and gearbox, external to the glovebox.
- b) A pneumatic clamp cylinder "piggy-backed" to the radial arm is used to clamp the convenience cans at the various stations.
- c) The carousel stations are:
 - Can Loading Station
 - Cap Removal/Replacement Station
 - Can Fill Station
 - Cap Monitoring Station
 - Can Orientation Station

4.1.6.10.2 Specific HWCI Requirements

The Convenience Can Handler must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

TFA-2	Remove/replace screw caps.
TFA-3	Controlled oxide tipping.
TFA-4	Weight confirmation.
TFA-5	Auto move cans in area.
SP-26	Alternate convenience cans.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.
CRIT-5	Fixed locations for metal cans.

4.1.6.10.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.11 Can Loading Station

The purpose of this HWCI is to allow automated pickup of empty convenience cans.

4.1.6.11.1 Current Description and Anticipated Operations

- a) The Can Loading Station provides a known location for the Convenience Can Handler to obtain empty convenience cans from the Convenience Can Storage Magazine.

4.1.6.11.2 Specific HWCI Requirements

The Can Loading Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

TFA-5	Auto move cans in area.
PPC-5	Control automatic ops.

4.1.6.11.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.12 Cap Removal/Replacement Station

The purpose of this HWCI is automated removal and replacement of the convenience can cap to support oxide filling.

4.1.6.12.1 Current Description and Anticipated Operations

- a) Cap removal and replacement is accomplished by an electric drive and gearbox that is raised and lowered by a pneumatic cylinder. A torque limiter is used to control the tightness of the cap on the can.
- b) A empty convenience can is moved by the transfer arm from the Convenience Can Magazine/Can Loading Station to the Cap Removal/Replacement Station and clamped in place.

The lid is unscrewed and raised clear of the can. The clamp is released and the lidless can is moved to the Can Fill Station by the transfer arm.

- c) The filled convenience can is unclamped and moved from the Can Fill Station to the Cap Removal/Replacement Station and clamped. The lid is lowered and screwed on. The clamp is released and the lidded can is moved via the Can Monitoring Station to the Can Orientation Station.
- d) Convenience cans filled with metal, either with screw-top caps or with press-on caps, are placed directly at this station by the Convenience Can Transfer Unit for movement past the Can Monitoring Station to the Can Orientation Station.

4.1.6.12.2 Specific HWCI Requirements

The Cap Removal/Replacement Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
TFA-2	Remove/replace screw caps.
SP-26	Alternate convenience cans.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.

4.1.6.12.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.13 Can Fill Station

The purpose of this HWCI is verifying the weight of plutonium oxide that is tipped into a convenience can.

4.1.6.13.1 Current Description and Anticipated Operations

- a) The convenience can and dispense tube are vibrated for about 10 minutes during furnace tray tipping to allow for complete emptying of the tray. A settling period after filling (of about 30 minutes) is used to minimize plutonium oxide dispersal prior to replacement of the cap.
- b) A moveable section of the semi-circular carousel lowers the convenience can onto a weigh table.
- c) A pneumatic cylinder mounted at the side of the track moves the platform up and down in. Vertical glide stops are used to indicate the platform position.
- d) The filled convenience can is moved to the Cap Removal/Replacement Station for rescrewing the cap.

4.1.6.13.2 Specific HWCI Requirements

The Can Fill Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
TFA-3	Controlled oxide tipping.
TFA-4	Weight confirmation.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.

4.1.6.13.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.14 Cap Monitoring Station

The purpose of this HWCI is checking the presence and correct location of the convenience can cap.

4.1.6.14.1 Current Description and Anticipated Operations

- a) The filled and capped convenience can is moved from the Cap Removal/Replacement Station to the Can Orientation Station, passing beneath the Cap Monitoring Station.
- b) A pair of proximity switches and a pivoting quadrant check the height of the lid on the convenience can to detect the presence and correct seating of the convenience can lid, as the can passes beneath the Cap Monitoring Station.

4.1.6.14.2 Specific HWCI Requirements

The Cap Monitoring Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
TFA-2	Remove/replace screw caps.
SP-26	Alternate convenience cans.
PPC-5	Control automatic ops.
CRIT-5	Fixed location for metal cans.

4.1.6.14.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.15 Can Orientation Station

The purpose of this HWCI is rotating the convenience cans to a horizontal position in preparation for transfer to the Inner Cap Insertion Area via the Gaslock.

4.1.6.15.1 Current Description and Anticipated Operations

- a) A convenience can is moved from the Cap Removal/Replacement Station.
- b) The can clamp cylinder is used to push the can from the can transfer arm on the carousel into the Can Orientation Station.

- c) The Can Orientation Station rotates through 90°, bringing the can to a horizontal position.

4.1.6.15.2 Specific HWCI Requirements

The Can Orientation Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
TFA-5	Auto move cans in area.
SP-26	Alternate convenience cans.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.
CRIT-5	Fixed location for metal cans.

4.1.6.15.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.16 Convenience Can Post Out Unit

The purpose of this HWCI is moving a filled convenience can from the Tipping/Dispense/Fill Area into the Gaslock of the Can Weigh and Cap Insertion Glovebox.

4.1.6.16.1 Current Description and Anticipated Operations

- a) With the convenience can in a horizontal position and the Gaslock door opened, a pushing bar (driven by a pneumatic rodless cylinder) moves the can into the Gaslock.

4.1.6.16.2 Specific HWCI Requirements

The Convenience Can Post Out Unit must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No. Summary of Requirement

TFA-6	Auto move cans to gaslock.
SP-26	Alternate convenience cans.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.
CRIT-5	Fixed location for metal cans.

4.1.6.16.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.6.17 Convenience Can Identification and Weigh Station

The purpose of this HWCI is to accurately determine the weight of a specific convenience can before it is introduced into the Dispense/Fill Glovebox.

4.1.6.17.1 Current Description and Anticipated Operations

- a) The weigh scale consists of a Mettler Toledo weigh platform and a Allen Bradley bar code reader, both linked to the PPCS.
- b) The empty convenience can is placed on the weigh platform, and when the data has stabilized, the operator sends the data to the PPCS.
- c) Once the weight and identification is recorded, the convenience can may be posted into the Pu SPS for use.

4.1.6.17.2 Specific HWCI Requirements

The Convenience Can Identification and Weigh Station must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No. Summary of Requirement

PSC-3	Entry of process data.
-------	------------------------

PPC-1 Can balances.
PPC-4 Entry of process data.

4.1.6.17.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.7 Can Weigh and Cap Insertion Area

This area loads an inner can with a convenience can and a cap (or bung). The Can Weigh and Cap Insertion Area includes the following major equipment items: the Can Weigh and Cap Insertion Glovebox, the Gaslock, the Convenience Can Turntable, the Weigh Scale and Bar Code Reader, the Convenience Can Pusher, the Inner Can Cap Post In Sphincter Seal, the Inner Can Cap Magazine, and the Material Transfer Port.

All equipment in the Can Weigh and Cap Insertion Area must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCI are identified in the following discussions.

4.1.7.1 Can Weigh and Cap Insertion Glovebox

The purpose of this HWCI is to confine radioactive materials within the glovebox, maintain a helium atmosphere for sealing within the inner cans, and provide radiation shielding for operators.

4.1.7.1.1 Current Description and Anticipated Operations

- a) The Can Weigh and Cap Insertion Glovebox shell is a leaktight stainless steel enclosure. The skin of the enclosure is Type 304 stainless steel. The internal structure members and supports and exterior supports are Type 304 stainless steel.
- b) The Can Weigh and Cap Insertion Glovebox is fitted with gloveports, gloves, lights, and shielded windows to assist with maintenance of internal equipment. Most normal operations inside the glovebox are performed under semi-automatic control with limited manual intervention for loading the special inner can caps (or bungs) and removing the inner can "stubs."

- c) The Can Weigh and Cap Insertion Glovebox is provided with radiation shielding to reduce personnel dose to ALARA with a goal of 500 mrem/year to the whole body from all sources within Pu SPS.
- e) Shielding is a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.
- f) Due to the small inleakage of air via the sintered filter in the inner can cap while the sealed inner can is being removed, the atmosphere within the Can Weigh and Cap Insertion Glovebox is monitored for composition and moisture content.

4.1.7.1.2 Specific HWCI Requirements

The Can Weigh and Cap Insertion Glovebox must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
SP-7	Filled with helium (inner).
HGA-6	Oxygen analysis equipment.
HGA-7	Excess oxygen actions.
E-3	Electrical connections (dust).
E-4	Electrical connections (plugs).
E-6	Lighting - amounts.
E-7	Lighting - type.
E-8	Lighting - location.
SSP-6	304 stainless steel.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PPC-2	Monitor/control interlocks.
PPC-3	Monitor/control environment.
PRI-2	Sodium iodine detectors.
RAM-7	Removable shielding.
BOX-1	Design reference documents.
BOX-2	304 stainless steel.
BOX-3	Light windows.
BOX-4	Gloveports.
BOX-5	Storage shelves.

BOX-6 Butt welds/floor fit.
BOX-7 Airlocks.
BOX-8 Consistent appearances.
BOX-9 Pass-through connectors.
BOX-10 Gas supply filters.
BOX-11 Leak tightness.
BOX-13 Criticality drains.
BOX-14 Shutoffs for utilities.
DECON-2 Glovebox finish.
DECON-3 Surface sealing.
DECON-4 Lifting lugs.

4.1.7.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.7.2 Gaslock

The purpose of this HWCI is transferring convenience cans of plutonium metal and oxide between the nitrogen atmosphere of the Dispense/Fill Glovebox and the helium atmosphere of the Can Weigh and Cap Insertion Glovebox. It is located completely within the Dispense/Fill Glovebox and the Can Weigh and Cap Insertion Glovebox.

4.1.7.2.1 Current Description and Anticipated Operations

- a) The Gaslock has two doors that connect to the Dispense/Fill Glovebox and the Can Weigh and Cap Insertion Glovebox.
- b) A convenience can of plutonium metal or oxide is moved into the Gaslock by the Convenience Can Post Out Unit, and is moved out of the Gaslock by the Convenience Can Extraction Unit/Can Pusher.
- c) The Gaslock is of the purged type to prevent transfer of nitrogen into the Can Weigh and Cap Insertion Glovebox.

- d) The Gaslock doors are pneumatically operated and software interlocked so that only one door may be opened at one time.

4.1.7.2.2 Specific HWCI Requirements

The Gaslock must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
PPC-2	Monitor/control interlocks.
PPC-3	Monitor/control environment.
SAFE-10	Compressed gases.
BOX-7	Airlocks.
BOX-14	Shutoffs for utilities.
BOX-15	Airlock inop if operator near.
BOX-16	Pneumatic gas type.
CRIT-5	Fixed location for metal cans.
CRIT-9	Metal cans separate in DBE.

4.1.7.2.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.7.3 Convenience Can Extraction Unit

The purpose of this HWCI is removing a convenience can of plutonium metal or oxide from the Gaslock and placing it on the Convenience can Turntable.

4.1.7.3.1 Current Description and Anticipated Operations

- a) After the Gaslock door is opened, the pneumatic cylinder of the Convenience Can Extraction Unit extends a permanent magnet into the Gaslock and attaches to the cap of the convenience can.

- b) The cylinder retracts, pulling the convenience can along until it is partially extracted from the Gaslock.
- c) The Convenience Can Pusher now extends to complete the extraction of the can from the Gaslock. The can contacts a physical stop, separating the can from the magnet. The can now rests on the Convenience Can Turntable.

4.1.7.3.2 Specific HWCI Requirements

The Convenience Can Extraction Unit must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
CWCI-1	Auto move cans from gaslock.
SP-26	Alternate convenience cans.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.
CRIT-5	Fixed location for metal cans.

4.1.7.3.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.7.4 Convenience Can Turntable

The purpose of this HWCI is moving the convenience can within the Can Weigh and Cap Insertion Area.

4.1.7.4.1 Current Description and Anticipated Operations

- a) The Convenience Can Turntable consists of a horizontal radial arm, driven by a pneumatic actuator, positioned external and below the Can Weigh and Cap Insertion Glovebox.
- b) A small pneumatic cylinder can raise and lower the Convenience Can Turntable a short distance.

- c) Convenience cans are transferred within the Can Weigh and Cap Insertion Glovebox by 180° rotation of the Convenience Can Turntable.

4.1.7.4.2 Specific HWCI Requirements

The Convenience Can Turntable must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

CWCI-2	Auto move cans in area.
SP-26	Alternate convenience cans.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.
CRIT-5	Fixed location for metal cans.

4.1.7.4.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.7.5 Weigh Scale and Bar Code Reader

The purpose of this HWCI is to provide a tared weight of the convenience can contents, matched to a can identity.

4.1.7.5.1 Current Description and Anticipated Operations

- The weigh scale consists of a Mettler Toledo type KA weigh platform (linked to the PPCS) and a calibration test weight.
- The calibration weight is suspended on a cantilevered arm that can be moved up and down in ball bushings, by the action of a pneumatic cylinder. Thus the weight is lowered onto the weigh platform for the calibration check and lifted off when the can is to be weighed.
- A special "V" support is attached to the weigh platform to support the full can during weighing.

- d) The bar code reader is positioned external and above the Can Weigh and Cap Insertion Glovebox. It identifies the convenience can through a viewport.

4.1.7.5.2 Specific HWCI Requirements

The Weigh Scale and Bar Code Reader must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

CWCI-3	Auto can weighing and ID.
SP-26	Alternate convenience cans.
PPC-1	Can balances.
PPC-4	Entry of process data.
PPC-5	Control automatic ops.
CRIT-5	Fixed location for metal cans.

4.1.7.5.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.7.6 Convenience Can Pusher

The purpose of this HWCI is insertion of the convenience can, followed by a special inner can cap (or bung) into an inner can. It also operates in conjunction with the Convenience Can Extraction Unit to remove a filled convenience can from the Gaslock.

4.1.7.6.1 Current Description and Anticipated Operations

- a) A large diameter, pneumatic cylinder pushes a convenience can from the Convenience Can Turntable into an inner can waiting in the Inner Can Post Out Rotating Sphincter Seal.
- b) The same cylinder then pushes a special inner can cap (or bung) into the same inner can.

4.1.7.6.2 Specific HWCI Requirements

The Convenience Can Pusher must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

CWCI-4	Auto fill of inner can.
SP-26	Alternate convenience cans.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.
CRIT-5	Fixed location for metal cans.

4.1.7.6.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.7.7 Inner Can Cap Post In Sphincter Seal

The purpose of this HWCI is passing inner can caps into the Can Weigh and Cap Insertion Glovebox without a breach of glovebox confinement.

4.1.7.7.1 Current Description and Anticipated Operations

- The sphincter seal is a multiple rubber ring system sized to the diameter of a special inner can cap (or bung).
- New inner can caps are posted in through the sphincter seal and staged in the Inner Can Cap Magazine.
- A special inner can cap (or bung) is always present in the sphincter seal to maintain the glovebox environment.
- Operational procedures and an internal stop bar prevent inadvertent ejection of a inner cap.

4.1.7.7.2 Specific HWCI Requirements

The Inner Can Cap Post In Sphincter Seal must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

BOX-10	Leak tightness.
--------	-----------------

4.1.7.7.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.7.8 Inner Can Cap Magazine

The purpose of this HWCI is temporary storage of the special inner can caps (or bungs) within the glovebox, with automated feed for insertion into filled inner cans.

4.1.7.8.1 Current Description and Anticipated Operations

- The Inner Can Cap Magazine stores special inner can caps (or bungs) waiting insertion into inner cans. The inner can caps are manually loaded into the magazine via a sphincter seal.
- When required a couple of small pneumatic cylinders feed inner cans from the magazine to the Convenience Can Pusher for pressing into the end of the inner can.

4.1.7.8.2 Specific HWCI Requirements

The Inner Can Cap Magazine must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

CWCI-4	Auto fill of inner can.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
BOX-16	Pneumatic gas type.

4.1.7.8.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.7.9 Material Transfer Port

The purpose of this HWCI is removal of inner can stubs from the helium atmosphere of the glovebox for bagged transfer to disposal/storage.

4.1.7.9.1 Current Description and Anticipated Operations

- a) Inner can stubs discharged from the rotating sphincter fall into a Stub Collection Chute.
- b) When four inner can stubs are present in the chute an operator manually discharges them via this Material Transfer Port.

4.1.7.9.2 Specific HWCI Requirements

The Material Transfer Port must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

SAFE-9	Platforms/work areas.
BOX-11	Leak tightness.

4.1.7.9.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.8 Inner Can Handling Area

This area welds and cuts inner/convenience can assemblies. The Inner Can Handling Area includes the Inner Can Handling Fume Cabinet, the Inner Can Rotating Sphincter Seal, the Inner Can Storage Magazine, the Laser Welding/Cutting Tool, the Laser Generator, and the Inner Can Handling Unit.

All equipment in the Inner Can Handling Area must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCI's are identified in the following discussions.

4.1.8.1 Inner Can Handling Fume Cabinet

The purpose of this HWCI is area ventilation for laser welding and cutting of the inner can.

4.1.8.1.1 Current Description and Anticipated Operations

- a) The Inner Can Handling Fume Cabinet shell is a stainless steel enclosure.
- b) The Inner Can Handling Fume Cabinet is fitted with an acrylic sliding door system on the front face and hinged shield doors.
- c) Shielding is a sandwiched layer of laminated beechwood and lead to provide shielding for neutron and gamma radiation.

4.1.8.1.2 Specific HWCI Requirements

The Inner Can Handling Fume Cabinet must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

HGA-5	Hood air velocity.
E-7	Lighting - type.
FPS-1	Detection/alarm system.
FPS-2	Glovebox overheat detection.
PRI-2	Sodium iodine detectors.
RAM-7	Removable shielding.
SAFE-11	Laser light.

4.1.8.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.8.2 Inner Can Rotating Sphincter Seal

The purpose of this HWCI is support of the inner can while items are placed into it, rotation of the inner can during welding and cutting operations, and transfer of sealed inner cans from the helium atmosphere of the Can Weigh and Cap Insertion Glovebox into the Inner Can Handling Fume Cabinet without a breach of glovebox confinement.

4.1.8.2.1 Current Description and Anticipated Operations

- a) The sphincter seal rotation unit is comprised of two units on a common frame; a can clamping unit and a sphincter seal unit. Both units rotate on bearings driven from the same layshaft through pairs of gears. A combined stepper motor gearbox unit within the Inner Can Handling Fume Cabinet provides motive power.
- b) The rotating sphincter seal holds an empty inner can awaiting the arrival of a filled convenience can. The convenience can is placed into the inner can and a cap from the inner cap magazine is then inserted.
- c) The sphincter begins to rotate and the inner cap is first welded to the can, and then the sealed inner/convenience can assembly is cut off, leaving a stub in the sphincter seal. The speed and positioning is precisely controlled.
- d) Sphincter rotation is stopped and the sealed inner can is moved away by the Inner Can Handling Unit.
- e) Pushing a new inner can into the sphincter seal from the Inner Can Handling Fume Cabinet forces the stub out, back into the helium filled glovebox.
- f) The stub is transferred to disposal/storage through the Material Transfer Port.
- g) An empty inner can (or when cut off, its stub) is always present in the sphincter seal to maintain the isolated glovebox environment.

4.1.8.2.2 Specific HWCI Requirements

The Inner Can Post Out Rotating Sphincter Seal must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No. Summary of Requirement

ICHA-1	Automated welding/cutting.
PPC-2	Monitor/control interlocks.
PPC-5	Control automatic ops.
RAM-6	Maintain inside from outside.
ENVR-3	Glovebox environment.
SP-7	Filled with helium (inner).
BOX-11	Leak tightness.
CRIT-5	Fixed locations for metal cans.

4.1.8.2.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.8.3 Inner Can Storage Magazine

The purpose of this HWCI is storing inner cans to be used in the near term (maintaining the sphincter seal).

4.1.8.3.1 Current Description and Anticipated Operations

- a) The Inner Can Storage Magazine stores inner cans awaiting transfer into the Inner Can Handling Fume Cabinet.
- b) Inner cans are manually loaded into the magazine by opening a pair of hinged shield doors.
- c) A pneumatic toggle mechanism allows one can at a time to be transferred into the Inner Can Handling Fume Cabinet.

4.1.8.3.2 Specific HWCI Requirements

The Inner Can Storage Magazine must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No. Summary of Requirement

PPC-2	Monitor/control interlocks.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.

4.1.8.3.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

| 4.1.8.4 Laser Welding/Cutting Tools

| The purpose of this HWCI is sealing the inner can to its cap and cutting off the remaining stub.

4.1.8.4.1 Current Description and Anticipated Operations

a)	The Laser Welding/Cutting Tools consist of two laser heads with a micro adjustment on the laser cutting head.
b)	One head performs welding operations using helium as the shroud gas, and one head performs cutting operations using helium as the assist gas.
c)	The laser cutting head is mounted on a swinging arm driven by a pneumatic cylinder to retract it when not operating.
d)	To prevent personnel from viewing the laser light and its reflections, there are interlocks with the shielding panels over the acrylic windows, with the flap for the Inner Can Storage Magazine, and the software for initiating inner can leak testing.

4.1.8.4.2 Specific HWCI Requirements

| The Laser Welding/Cutting Tools must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No. Summary of Requirement

ICHA-1	Automated welding/cutting.
PPC-5	Control automatic ops.
SP-8	Sealed/leaktight (inner).
SP-22	Automated closure.
SAFE-10	Compressed gases.
SAFE-11	Laser light.

4.1.8.4.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.8.5 Laser Generator

The purpose of this HWCI is generating the light beam for welding and cutting the inner can and welding the outer can.

4.1.8.5.1 Current Description and Anticipated Operations

- a) A continuous-wave solid state laser module with a maximum output of about 2800 watts (controlled to produce a maximum of about 2000 watts at the laser welding/cutting tool), provides the intense beam of light used for sealing and cutting the inner cans and sealing the outer cans.
- b) The laser beam is carried to the laser welding/cutting tool using a fiber optic light cable, allowing easy replacement without complicated adjustments.
- c) The laser is computer processor controlled which performs the internal laser monitoring and control functions, as well as those of external beam guiding and monitoring components. It has input/output interfaces for connection with the PPCS.

4.1.8.5.2 Specific HWCI Requirements

The Laser Generator must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

ICHA-1	Automated welding/cutting.
OWM-3	Auto outer can welding.
PPC-5	Control automated ops.
SP-8	Sealed/leaktight (inner).
SP-14	ASME VIII (outer).
SP-22	Automated closure.
SAFE-10	Compressed gases.
SAFE-11	Laser light.

4.1.8.5.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.8.6 Inner Can Handling Unit

The purpose of this HWCI is moving inner cans within the Inner Can Handling Area.

4.1.8.6.1 Current Description and Anticipated Operations

- The Inner Can Handling Unit transports inner cans within the Inner Can Handling Fume Cabinet by using an overhead pneumatic rodless cylinder, a pair of gripper cylinders, and a pair of pneumatic pusher cylinders. It also includes a pneumatic post out cylinder and a pneumatic backstop for inner cans.
- A can is transferred from the Inner Can Storage Magazine into the rotating sphincter seal near the laser heads via a gripper/pusher unit.
- Sealed cans are posted out via the same gripper/pusher unit and a posting out unit that moves into position behind the can and ejects the can into an outer can on the Can Turntable/Trolley.

4.1.8.6.2 Specific HWCI Requirements

The Inner Can Handling Unit must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
ICHA-1	Automated welding/cutting.
ICHA-2	Auto can movement in area.
ICHA-3	Auto push out of stubs.
PPC-2	Monitor/control interlocks.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
CRIT-5	Fixed location for metal cans.

4.1.8.6.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.9 Outer Can Weld and Monitoring Area

This area loads and seals the outer can, and checks for surface contamination and leaks. The Outer Can Weld and Monitoring Area includes the following major equipment items: the Can Turntable/Trolley, the Outer Can Handling Unit, the Inner Can Leak Detection Unit, the Helium Fill/Lid Fittment Unit, the Outer Can Welder, the Outer Can Contamination Check Unit, and the Outer Can Leak Detection Unit.

All equipment in the Outer Can Weld and Monitoring Area must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCIs are identified in the following discussions.

4.1.9.1 Can Turntable/Trolley

The purpose of this HWCI is moving outer cans within the Outer Can Weld and Monitoring Area.

4.1.9.1.1 Current Description and Anticipated Operations

- a) The turntable is electrically driven, with a trolley mounted on a track on top of the turntable. The trolley is driven by a "serapid" chain drive from a pneumatic motor, and is reset by a small pneumatic cylinder.
- b) It receives sealed inner can assemblies from the Inner Can Handling Unit into empty outer cans.
- c) Outer cans are transferred, on the trolley, in and out of each Leak Detection Unit, the Outer Can Welder, the Contamination Check Unit, and finally into the Lag Storage Trolley.

4.1.9.1.2 Specific HWCI Requirements

The Can Turntable/Trolley must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

OWM-6	Auto receipt inner can.
OWM-7	Auto move cans in area.
OWM-8	Auto move package to trolley.
PPC-5	Control automatic ops.
SAFE-9	Platform/work surfaces.
SAFE-10	Compressed gases.

4.1.9.1.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.9.2 Outer Can Handler

The purpose of this HWCI is manipulation and movement of the outer can on top of the Can Turntable/Trolley.

4.1.9.2.1 Current Description and Anticipated Operations

- a) A can turntable is mounted on top of the Can Turntable/Trolley.

- b) Outer cans are clamped in place using a pneumatic cylinder that is hydraulically damped.
- c) The Outer Can Handler positions the outer can for loading into and from the Inner Can Leak Test Facility.
- d) The Outer Can Handler also positions the outer can for loading into and from the Helium Fill/Lid Fittment Unit.
- e) A small pneumatic cylinder raises and lowers the turntable to engage the Resistance Welder.

4.1.9.2.2 Specific HWCI Requirements

The Outer Can Handler must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
OWM-6	Auto receipt inner can.
OWM-7	Auto move cans in area.
OWM-8	Auto move package to trolley.
PPC-2	Monitor/control interlocks.
PPC-5	Control automatic ops.
SAFE-10	Compressed gases.
LST-2	Trolley movement interlocks.
PPC-2	Monitor/control interlocks.

4.1.9.2.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.9.3 Inner Can Leak Detection Unit

The purpose of this HWCI is checking sealed inner cans for helium leakage.

4.1.9.3.1 Current Description and Anticipated Operations

- a) A outer can containing a sealed inner/convenience can assembly is positioned at the Leak Detection Unit by the Can Turntable/Trolley and the Outer Can Handler.
- b) The leak testing head is indexed into position and the outer can inserted, making a seal.
- c) The space between the welded inner can and the outer can is evacuated by a vacuum pump in a mass spectrometer.
- d) A mass spectrometer is used to detect trace amounts of helium leakage from the inner can assembly.
- e) Atmospheric pressure is restored and the outer can is removed by the Can Turntable/Trolley and the Outer Can Handler.

4.1.9.3.2 Specific HWCI Requirements

The Inner Can Leak Detection Unit must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
OWM-1	Helium leak detection.
OWM-2	Auto inner can leak check.
PPC-5	Control automatic ops.
PPC-7	Leak & contamination test info.
SP-8	Sealed/leaktight (inner).
SAFE-10	Compressed gases.

4.1.9.3.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.9.4 Helium Fill/Lid Fittment Unit

The purpose of this HWCI is to fill the interspace between the inner and outer cans with helium, and to press fit the outer lid onto the outer can.

4.1.9.4.1 Current Description and Anticipated Operations

- a) An outer lid is placed in the unit.
- b) An outer can assembly is placed in the 1st stage position by the Can Turntable/Trolley and Outer Can Handler.
- c) The unit is evacuated and a seal is held against the outer can assembly by atmospheric pressure.
- d) The unit is filled with helium to about 2 psi, which includes the interspace between the inner and outer cans.
- e) The outer can is pushed to the 2nd stage position with a force of about 1000 to 2000 newtons, pressing the cap into the can.
- f) The seal pressure is released and the outer can assembly is removed by the Can Turntable/Trolley and Outer Can Handler for movement to the Outer Can Welder.

4.1.9.4.2 Specific HWCI Requirements

The Helium Fill/Lid Fittment Unit must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

PPC-5	Control automatic ops.
SP-14	Filled with helium (outer).
SAFE-9	Platforms/work surfaces.

4.1.9.4.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.9.5 Outer Can Welder

The purpose of this HWCI is to weld the joint between the outer can and its cap, sealing the storage package.

4.1.9.5.1 Current Description and Anticipated Operations

- a) The Outer Can Handler presents the outer can assembly to the welder.
- b) The welder, using a laser beam from the same laser generator used to weld the inner can, welds the lid to the outer can (using helium as the shroud gas).
- c) The Outer Can Handler retrieves the outer can assembly, now a complete storage package, from the welder.

4.1.9.5.2 Specific HWCI Requirements

The Outer Can Welder must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

OWM-3	Auto outer can welding.
PPC-5	Control automatic ops.
SP-16	ASME VIII (outer)
SP-22	Automated closure.
SAFE-10	Compressed gases.
SAFE-11	Laser light.

4.1.9.5.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.9.6 Outer Can Contamination Check Unit

The purpose of this HWCI is confirming the final storage package is free of radioactive contamination.

4.1.9.6.1 Current Description and Anticipated Operations

- a) Outer cans are transferred into the Contamination Check Unit via the Can Turntable/Trolley.
- b) The Contamination Check Unit turntable and drive systems allow diametrical and axial swabbing of the can surface. This allows full swabbing of the storage package's outer surface, to pick up any evidence of contamination.
- c) The storage package is rotated and manipulated by two driven units and a turntable, to bring the surfaces up to the operating area of the swab. The sequence of operations is end cap surface, plain end surface, and the cylindrical surface.
- d) The swab is traversed across the surfaces by a linear actuator, and held in contact with a spring loaded parallel link that is capable of following surface contours.
- e) At the end of the operation, the small swabbing head is moved to an alpha contamination monitor for radiation checking.

4.1.9.6.2 Specific HWCI Requirements

The Outer Can Contamination Check Unit must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

OWM-4	Auto outer can contamination check.
SP-3	No surface contamination.
PPC-5	Control automatic ops.
PPC-7	Leak & contamination test info.
SAFE-10	Compressed gases.

4.1.9.6.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.9.7 Outer Can Leak Detection Unit

The purpose of this HWCI is checking the final storage package for helium leakage.

4.1.9.7.1 Current Description and Anticipated Operations

- a) The Can Turntable/Trolley and Outer Can Handler moves the storage package into a stainless steel vacuum chamber fitted with a seal door.
- b) The chamber is evacuated by a vacuum pump in a mass spectrometer.
- c) A mass spectrometer is used to detect trace amounts of helium leakage from the outer can.
- d) Atmospheric pressure is restored and the storage package is removed by the Can Turntable/Trolley and the Outer Can Handler.

4.1.9.7.2 Specific HWCI Requirements

The Outer Can Leak Detection Unit must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

OWM-1	Helium leak detection.
OWM-5	Auto outer can leak check.
PPC-5	Control automatic ops.
PPC-7	Leak & contamination test info.
SP-14	Filled with helium (outer).
SAFE-10	Compressed gases.

4.1.9.7.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.10 Lag Storage Trolley

The purpose of this HWCI is shielded and critically safe transfer of storage containers out of the Pu SPS area to a remote storage area.

4.1.10.1 Current Description and Anticipated Operations

- a) The Lag Storage Trolley is a manually wheeled cart with a shielded compartment on top that holds two Pu SPS storage packages.
- b) The cart is normally in place in the Outer Can Weld and Monitoring Area, held in place by interlocks.
- c) Two cans are automatically inserted into the Lag Storage Trolley by the Can Turntable/Trolley and Outer Can Handler.
- d) When filled, the compartment door on the Lag Storage Trolley is shut. Interlocks ensure that the Lag Storage Trolley can not be moved until its door is shut.
- e) The filled Lag Storage Trolley is manually wheeled away from the Pu SPS and replaced by a second, identical, empty Lag Storage Trolley.

4.1.10.2 Specific HWCI Requirements

The Lag Storage Trolley must comply with the requirements identified in Appendix A.

4.1.10.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

HWCIIs Common to Several Pu SPS Areas

4.1.11 Furnace Trays

This system is used for transporting plutonium oxide within the Pu SPS from when it is removed from the inner container until it is placed into a convenience can, including stabilization within the Furnace Glovebox.

4.1.11.1 Current Description and Anticipated Operations

- a) The nominal tray inside dimensions are approximately 26 cm square by 5 cm deep (about 10" square by 2" deep).
- b) Empty furnace trays are mated to the Powder Dispensing Station in the Material Preparation Area to prevent dispersal of plutonium oxide into the Material Preparation Glovebox.
- c) The furnace tray rests on a tray weighing device that controls the Powder Dispensing Station. Empty furnace tray weights are trended.
- d) The Powder Dispensing Station fills the furnace tray to a maximum load of 4.99 kg of plutonium oxide with a estimated maximum depth of 1.5 inches. These values can be modified if needed for different feed streams.
- e) The furnace trays are heated to 1000 C for a period of two hours in the Stabilization Furnace. The furnace tray materials and physical design will withstand repeated exposure to this temperature without excessive oxidation, interaction with the oxide powder, or distortion.
- f) The furnace trays are cooled in the Stabilization Furnace overnight.
- g) The furnace tray contents are sampled at the LOI Test Area. The samples are placed into crucibles that have unique identifiers that can be correlated to the unique identifiers on the furnace trays.
- h) In the Tipping/Dispense/Fill Area, the furnace trays are mated to an automated sealing mechanism on the Furnace Tray Tipper to prevent dispersal of plutonium oxide into the gloveboxes, and the furnace tray contents are deposited into a convenience can.
- i) The empty furnace tray is returned to the Material Preparation Area for reuse.

4.1.11.2 Specific HWCI Requirements

The Furnace Trays must comply with the requirements identified in Appendix A.

4.1.11.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.12 Storage Package

This HWCI provides safe, interim 50 year storage of plutonium metal and its oxide. The Storage Package includes the following major equipment items: the Convenience Can and Cap, the Inner Can, the Inner Cap, and the Outer Can and Lid.

4.1.12.1 Convenience Can and Cap

The purpose of the HWCI is to store plutonium oxide.

4.1.12.1.1 Current Description and Anticipated Operations

- a) The Convenience Can and Cap is a stainless steel container with a screwed cap. Overall size is 112 mm diameter x 213.45 mm length.
- b) Convenience cans provided by the site may be of several styles and sizes.

4.1.12.1.2 Specific HWCI Requirements

The Convenience Can and Cap must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

SP-27	Convenience can atmosphere.
-------	-----------------------------

4.1.12.1.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

| 4.1.12.2 Inner Can

The purpose of the HWCI is to store a convenience can and cap.

4.1.12.2.1 Current Description and Anticipated Operations

- | a) The inner can is a stainless steel container 117 mm diameter x 231 mm length.

4.1.12.2.2 Specific HWCI Requirements

- | The Inner Can must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

SP-1	Two confinement barriers.
SP-3	No surface contamination.
SP-5	Container markings.
SP-7	Filled with helium (inner).
SP-8	Sealed/leaktight (inner).
SP-9	Leaktight post drops (inner).
SP-10	304L s/s or equal steel.
SP-11	Pressure test (inner).
SP-12	Internal pressure indicator.
SP-26	Alternate convenience cans.

4.1.12.2.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

| 4.1.12.3 Inner Cap

- | The purpose of this HWCI is to cap an inner can.

4.1.12.3.1 Current Description and Anticipated Operations

- | a) The inner cap is manufactured in stainless steel 116.5 mm diameter x 130 mm length.

- b) To prevent pressurization of the inner can cap during welding, a small (about 35 mm diameter) sintered metal filter vents gas into the Can Weigh and Cap Insertion Glovebox. This filter is rated at 99.88% efficiency for particles ranging in size as low as 0.3 to 0.5 μm and is made of 316L stainless steel. The filter also allows a small amount of air leakage into the helium atmosphere of the Can Weigh and Cap Insertion Glovebox.
- c) Pressurization of the inner can can be detected by movement of a deflection device that should be visible using radiographic techniques.

4.1.12.3.2 Specific HWCI Requirements

The Inner Cap must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
SP-1	Two confinement barriers.
SP-3	No surface contamination.
SP-5	Container markings.
SP-7	Filled with helium (inner).
SP-8	Sealed/leaktight (inner).
SP-9	Leaktight post drops (inner).
SP-10	304L s/s or equal steel.
SP-11	Pressure test (inner).
SP-12	Internal pressure indicator.
SP-26	Alternate convenience cans.

4.1.12.3.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.12.4 Outer Can and Lid

The purpose of this HWCI is to store an inner can and cap.

4.1.12.4.1 Current Description and Anticipated Operations

- a) The outer can and lid is a stainless steel container 125 mm diameter x 254 mm length.

4.1.12.4.2 Specific HWCI Requirements

The Outer Can and Lid must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

SP-1	Two confinement barriers.
SP-3	No surface contamination.
SP-5	Container markings.
SP-14	Filled with helium (outer).
SP-15	304L s/s or equal (outer).
SP-16	ASME VIII (outer).
SP-17	Max design pressure (outer).
SP-18	External pressure (outer).
SP-19	Free standing (outer).
SP-20	Maximum size (outer).
SP-21	Robotics compatible (outer).
SP-22	Automated closure.
SP-23	Leaktight post drops (outer).
SP-24	Alternate inner cans.
SP-25	Test using alternate inners.

4.1.12.4.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.13 Hood/Glovebox Atmosphere

Figure SDD-3 on the next page is a schematic diagram of the air, nitrogen, and helium ventilation systems.

4.1.13.1 Supply and Exhaust Filtration

The purpose of this HWCI is to prevent contamination of the supply and exhaust ducts exterior to the Pu SPS.

4.1.13.1.1 Current Description and Anticipated Operations

- a) Radial flow HEPA filtration is furnished for each exhaust point, as close as practical to the shell of the glovebox.
- b) Backflow prevention dampers are provided in supply ducts.
- c) HEPA filters are furnished at each inlet point, as close as practical to the shell of the glovebox.
- d) Inlet points are designed to slow and disperse the incoming gases, to prevent scattering of plutonium oxide and additional loading of the filters.

4.1.13.1.2 Specific HWCI Requirements

The Supply and Filtration Equipment must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
HGA-3	Intake filters.
HGA-4	Exhaust filters.
HGA-9	HEPA filtration.
HGA-11	Preclude oxide dispersion.

4.1.13.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System

NOTES:

1. ALL TE's FEED GLOVEBOX OVERHEAT DETECTION SYSTEM.
2. OXYGEN ANALYZERS IN RFETS SCOPE. TAPS PROVIDED IN PIPING/DUCTWORK.
3. DUMP VALVE OPEN (VALVE LIMIT SWITCH NOT CLOSED) TO BE ALARMED.
4. CONTROL OF GAS FLOW TO FURNACES AND DESSICATOR PROVIDED BY INTEGRATED MASS FLOW CONTROL VALVE AND COMMON CONTROL PROCESSOR.
5. MOISTURE DETECTION IN INSTRUMENT AIR/PLANT AIR SYSTEM SUPPLY AND NITROGEN SYSTEM SUPPLY IN RFETS SCOPE.

Pu SPS
Plutonium Stabilization and Packaging System
GLOVEBOX VENTILATION SYSTEM
DIAGRAM

FIGURE SDD-3

4.1.14 Electrical

Figure SDD-4 on the next page is a preliminary one-line diagram of the Pu SPS electrical system.

4.1.14.1 Power Distribution

The purpose of this HWCI is the distribution of 120 VAC and 480 VAC, 60 hz electrical power.

4.1.14.1.1 Current Description and Anticipated Operations

- a) One 480 VAC panelboard is provided to serve the gloveboxes and hoods on the ground floor for the stabilization and packaging processes. The panelboard will require approximately 60 KVA.
- b) One 120 VAC emergency service power supply will be required on the ground floor for glovebox dump valves, and possibly other safety loads as determined by the USQD.
- c) One 208/120 VAC, 3-phase panelboard is provided to serve the gloveboxes and hoods for the stabilization process. Power is provided to the glovebox, instrumentation, convenience receptacles, and small electrically powered equipment. The 120 VAC power for the packaging process electrical equipment will be derived from the 480 VAC supply and be distributed from a terminal strip. Pu SPS glovebox lighting will plug into overhead receptacle strips.
- d) A 480 VAC feeder will be required on the second floor for a 3-phase, 60 hertz laser unit that requires approximately 111 KVA.

4.1.14.1.2 Specific HWCI Requirements

Power distribution must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

RA-6	Support needs for frisker.
E-5	UPS, per safety analysis.

4.1.14.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

- CAD NO: 00201001.0002

OR

Pu SPS
Plutonium Stabilization and Packaging System
GLOVEBOX ELECTRICAL
ONE-LINE DIAGRAM

FIGURE SDD-4

4.1.14.2 Lighting

The purpose of this HWCI is to provide adequate light at working surfaces and areas inside the gloveboxes and hoods.

4.1.14.2.1 Current Description and Anticipated Operations

- a) Lights are provided to achieve a minimum of 50 to 60 foot-candles of illumination at the working level, as perceived by an operator looking through glovebox windows. Greater illumination will be considered for critical work areas such as inspection points.
- b) Light fixtures generally are placed outside the gloveboxes and illuminate the glovebox interior through windows. The light attenuation through the light and viewing windows is considered in the selection of the fixtures.
- c) Lights for the Pu SPS stabilization process and the Pu SPS packaging process are placed on separate circuits provided by RFETS.

4.1.14.2.2 Specific HWCI Requirements

Lighting must comply with the requirements identified in Appendix A.

4.1.14.2.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.15 Support Structures and Platforms

This system is used to physically support hoods, gloveboxes, and other Pu SPS equipment.

4.1.15.1 Current Description and Anticipated Operations

- a) The Pu SPS stabilization process and the Pu SPS packaging process are separated by a seismic displacement absorber.
- b) The Receipt Area and the S-16 conveyor are separated by a seismic displacement absorber.

- c) Shielding is bolted to the glovebox frames or provide as standalone shadow shields where economical.
- d) Consideration will be given to having major equipment internal to the gloveboxes, such as the Stabilization Furnaces and Powder Dispensing Station, supported by the glovebox frames rather than the skin of the gloveboxes.

4.1.15.1.1 Specific HWCI Requirements

Support structures and platforms must comply with the requirements identified in Appendix A.

4.1.15.2 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.16 Fire Protection

The purpose of this HWCI is local detection and suppression of fires.

4.1.16.1 Current Description and Anticipated Operations

- a) Fire detection is accomplished with heat detectors mounted at strategic locations in the gloveboxes and hoods. The detectors are connected to the Building 707 fire protection system and to local alarms.
- b) A Fire Hazards Analysis will be performed to augment the existing Fire Hazards Analysis for RFETS Building 707 and consider the new or revised fire hazards resulting from the installation and operation of the Pu SPS.
- c) Fire separation between the Pu SPS and the existing S-16 conveyor is accomplished by the Entry Airlock isolating door. This airlock is normally closed, is air tight, and is opened only when material is being transferred from the S-16 conveyor to the Pu SPS by an operator. Interlocks allow only one of the airlock doors to be opened at one time. Therefore, fire separation is provided at all times. The Fire Hazards Analysis will include a comparison of this isolation technique to the requirements identified in FPS-4 in the System Specification.

- d) Life safety requirements of the System Specification FPS-6 will be met for Pu SPS installation defined as an ordinary hazard, consistent with the existing Fire Hazards Analysis for RFETS Building 707.

4.1.16.1.1 Specific HWCI Requirements

Fire protection equipment must comply with the requirements identified in Appendix A.

4.1.16.2 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.17 Pu SPS Control System

The Pu SPS Control System consists of three major subsystems: the Plutonium Stabilization Control System, the Plutonium Packaging Control System, and the Data Management System. The Pu SPS Control Block Diagram (Figure SDD-5 on page 110) shows the overall arrangement of the Pu SPS Control System.

All Pu SPS Control System equipment must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCI are identified in the following discussions.

4.1.17.1 Plutonium Stabilization Control System (PSCS)

The purpose of this HWCI is control of the mechanized operations within the Pu SPS stabilization process, which includes activities in the Receipt Area, Material Preparation Area, Transport Area, Furnace Area, and LOI Test Area.

4.1.17.1.1 Current Description and Anticipated Operations

The PSCS consists of the following primary components:

- A Programmable Logic Controller (PLC), providing control, monitoring, and integration of the PSCS components.

- Operator control panels and interfaces strategically located to allow Operators to control selected operations within the gloveboxes.
- PLC Input/Output (I/O) cards and hardware installed in electrical equipment boxes mounted around the outside of the gloveboxes.
- Serial interfaces with equipment and instrumentation that are not interfaced with standard hardwired PLC Input/Output cards. These may include items such as the process radiometric instrumentation, furnace controllers, weigh scales, bar code readers, and keypads provided for container identification recording.
- Control actuators and Instrumentation in the gloveboxes providing monitoring, feedback, and data collection.
- Furnace controllers, integrated with the PLC, controlling furnace temperature, temperature ramp rates, and dwell times.
- A dedicated Ethernet TCP/IP Data Highway connection to the Data Management System (DMS) and to the Plutonium Packaging Control System (PPCS). The data highway provides control and coordination with the PPCS, and provides for the transmission of process information to the DMS.
- An Operator Interface Unit (OIU), consisting of a Video Display Unit (VDU), keyboard, computer, software and printer, located in a remote control console in the corridor at RFETS. The OIU provides remote control and alarm monitoring of the gloveboxes and automatic PLC operations, and provides a programming terminal for the PLC.

Manual operations for the stabilization process will be controlled from local control panels on the gloveboxes, and maintenance functions will be accomplished from local control panels.

4.1.17.1.2 Specific HWCI Requirements

The Plutonium Stabilization Control System must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

RA-4	Process traveller number.
------	---------------------------

MPA-15	Automated oxide dispensing.
MPA-16	Auto tray overfill checking.
TA-1	Transport cans without spills.
TA-2	Transport trays without spills.
TA-3	Accurate can/tray movement.
FURN-1	Oxide temperature/time.
FURN-7	Hold 2 trays.
PSC-1	Monitor/control interlocks.
PSC-2	Monitor/control environment.
PSC-3	Entry of process data.
PSC-4	Control of automatic ops.
PSC-5	Info to DMS.
PRI-3	Limited assay data transfer.
BOX-15	Airlock inop if operator near.
CRIT-4	Initial container assay.
CRIT-5	Fixed locations for metal cans.
CRIT-6	Fixed locations in processes.

4.1.17.1.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

BUILDING 371
COMPUTER VAULT

RADIATION CONTROLLED AREA

LEGEND:

—○—○— LOCAL AREA NETWORK

ABBREVIATIONS

CCTV - CLOSED CIRCUIT TELEVISION

DH⁺ - PLC DATA HIGHWAY

DMS - DATA MANAGEMENT SYSTEM

I/O - INPUT/OUTPUT SIGNALS - SEE NOTE 1

PLC - PROGRAMMABLE LOGIC CONTROLLER

SNM - SPECIAL NUCLEAR MATERIALS

NOTES:

1. I/O SIGNALS INCLUDE DISCRETE I/O, 4-20 mA ANALOG AND SERIAL DATA LINKS FROM DEVICES SUCH AS: WEIGH SCALES, CONTAINER MONITOR, Pu HOLD UP SYSTEM, KEY PAD TERMINALS AND BARCODE READERS.

Pu SPS
Plutonium Stabilization and Packaging System
GLOVEBOX CONTROL BLOCK DIAGRAM

FIGURE SDD-5

4.1.17.2 Plutonium Packaging Control System (PPCS)

The purpose of this HWCI is control of the mechanized operations within the Pu SPS packaging process.

4.1.17.2.1 Current Description and Anticipated Operations

Operations are handled by the Operator Interface Unit (OIU) through PLCs. There is no local operator control of the packaging process, but a local control panel is provided for maintenance purposes. Operator intervention is only required to load empty cans and caps into their magazines. The process is one of mechanical handling, through set sequences, with all movements monitored by proximity switches linked into the OIU. Each sequence is instigated by operator action, but the operations within the sequence are controlled by the PLC (e.g. - the operator initiates the sequence to move an empty convenience can to the cap removal station, but all of the movements are controlled by the PLC, and at the end of the movement sequence the PLC stops to await the sequence to remove the cap). The signals from all proximity switches in the sequence are displayed on mimic diagrams on VDUs to allow the operator to follow the progress. Should the status of a switch be incorrect, this will be flagged and operations halted until corrective action is taken.

Only one can is moved through the packaging process at any one time. Interlocks prevent a second can from starting until the inner can is loaded into an outer can. Similarly, only one outer can assembly is allowed to move through the checking and monitoring stages at any one time.

The PPCS consists of the following primary components:

- A Programmable Logic Controller (PLC), providing control, monitoring, and integration of the PPCS components.
- Operator control panels and interfaces strategically located to allow Operators to monitor selected operations within the gloveboxes.
- PLC Input/Output (I/O) cards and hardware installed in electrical equipment boxes mounted around the outside of the gloveboxes.
- Serial interfaces with equipment and instrumentation that are not interfaced with standard hardwired PLC Input/Output cards. These may include items such as the process, weigh scales, and bar code readers provided for can identity recording.

- Control actuators and Instrumentation in the gloveboxes providing monitoring, feedback, and data collection.
- A dedicated Ethernet TCP/IP Data Highway connection to the Data Management System (DMS) and to the Plutonium Stabilization Control System (PSCS). The data highway provides control and coordination with the PSCS, and provides for the transmission of process information to the DMS.
- An Operator Interface Unit (OIU), consisting of a Video Display Unit (VDU), keyboard, computer, software and printer, located in a remote control console in the corridor at RFETS. The OIU provides remote control and alarm monitoring of the gloveboxes and automatic PLC operations, and provides a programming terminal for the PLC.

4.1.17.2.2 Specific HWCI Requirements

The Plutonium Packaging Control System must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
RA-4	Process traveller number.
TFA-1	Auto move trays to tipper arm.
TFA-2	Remove/replace screw caps.
TFA-3	Controlled oxide tipping.
TFA-4	Weight confirmation.
TFA-5	Auto move cans in area.
TFA-6	Auto move cans to gaslock.
CWCI-1	Auto move cans from gaslock.
CWCI-2	Auto move cans in area.
CWCI-3	Auto can weighing and identification.
CWCI-4	Auto fill of inner can.
ICHA-1	Automated welding/cutting.
ICHA-2	Auto can movement in area.
ICHA-3	Auto push out of stubs.
OWM-2	Auto inner leak check.
OWM-3	Auto outer can welding.
OWM-4	Auto outer can contamination check.
OWM-5	Auto outer can leak check.

OWM-6	Auto receipt of inner can.
OWM-7	Auto move cans in area.
OWM-8	Auto move package to trolley.
LST-2	Trolley movement interlocks.
PPC-2	Monitor/control interlocks.
PPC-3	Monitor/control environment.
PPC-4	Entry of process data.
PPC-5	Control automatic ops.
PPC-6	Info to DMS.
PPC-7	Leak & contamination test info.
SAFE-11	Laser light.
BOX-15	Airlock inop if operator near.
CRIT-5	Fixed locations for metal cans.
CRIT-6	Fixed locations in processes.

4.1.17.2.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.1.17.3 Data Management System (DMS)

The purpose of this HWCI is transitory process data collection and reporting of information for site material control and accountability requirements and storage package certification requirements.

4.1.17.3.1 Current Description and Anticipated Operations

The DMS consists of the components needed to interface with the RFETS SNM control computer on the SAN, and may include the following primary components:

- A Personal Computer (PC) with a hard drive (for data storage), a floppy disk (for data transfer), and a Data Highway interface card (for data gathering), plus the appropriate software to convert the process information to site material control and accountability and storage package certification information.
- An Operator Interface Unit (OIU) consisting of:
 - VDU for displaying reports and data
 - Keyboard for data entry and manipulation

- Laser printer for report hard copies
- A dot matrix alarm printer, depending on equipment locations.

4.1.17.3.2 Specific HWCI Requirements

The Data Management System must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

DMS-1	MC&A info to SNM computer.
DMS-2	Purge data.
DMS-3	Storage package certification.
DMS-4	System ops info.
RADP-3	Self-shielding.
SAFE-10	Compressed gases.
CRIT-4	Initial container assay.
CRIT-5	Fixed location for metal cans.
CRIT-6	Fixed locations in processes.

4.1.17.3.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.18 Process Radiometric Instrumentation

Two process radiometric instruments are provided to support control and accountability of Nuclear Materials in accordance with reference 2.7. One is the Container Assay Monitor and the other is the Plutonium Hold Up System.

All Process Radiometric Instrumentation must comply with the requirements identified in Appendix A. Requirements that are specific to selected HWCI are identified in the following discussions.

4.1.18.1 Container Assay Monitor

The purpose of this system is twofold. Its prime function is in support of control and accountability of nuclear materials. As incoming containers are brought into the Pu SPS, they are "logged in" by reading the outer container identification number that will also be provided on the work control traveller. This information limits the details that will identify the quantity of fissile material entering the Pu SPS material balance area to the RFETS SNM computer system on the SAN. In order to verify this information ($\pm 10\%$), the Pu SPS includes a Container Assay Monitor that will independently determine the quantity of plutonium in the incoming container. The result of the assay will be displayed to an operator who compares the Pu SPS measurement to the existing measurement on the work control traveller. In the event of a discrepancy between the two readings, RFETS management will determine the appropriate actions to take.

4.1.18.1.1 Current Description and Anticipated Operations

- a) Following introduction of the site storage packages to the Pu SPS, the inner bagged containers will be removed and passed into the glovebox. After removing the bag, the inner container is passed into a glovebox "bulge" around which a Container Assay Monitor is assembled. The Container Assay Monitor will consist of a Passive Neutron Coincidence Counter complemented by High Resolution Gamma spectroscopy system capable of assaying plutonium in the range of 0.2 to 5.2 Kg. The system will have a total uncertainty of better than 10% at 5 Kg.
- b) On completion of the assay, the monitor will determine the total plutonium content of the container and will download this data to the DMS via the PSCS, which, ultimately, will in turn transfer its data to the RFETS SNM computer system on the SAN. Any plutonium assay data required within the Pu SPS will use the Pu SPS Container Assay Monitor data. Isotopic distribution will not be reported.
- c) A second function of the Container Assay Monitor is to assay the emptied inner containers prior to bagging them out into the 55 gallon drum for disposal/storage to support the site strategy for loading of drums prior to transport and disposal/storage. It is currently anticipated that several (perhaps 6) compacted containers will be assayed at one time.

For determination of the plutonium content of emptied, compacted containers, it is expected that insufficient gamma ray signals will be present to make use of the gamma detectors. For this reason, conservative, default plutonium isotopic ratios will be used to determine the total plutonium content of these packages. Periodic checks will be made to compare the defaulted isotopic ratios with the measured ratios from the feed containers.

4.1.18.1.2 Specific HWCI Requirements

The Container Assay Monitor must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
--------	------------------------

PSC-3	Entry of process data.
PRI-1	Assay equipment.
PRI-3	Limited assay data transfer.
EMR-1	Assay equipment protection.

4.1.18.1.3 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.1.18.2 Plutonium Hold Up System

The purpose of the Pu hold up system is to locate and crudely quantify hold-up of fissile materials within the Pu SPS. The measurements obtained will be used to support both material control and accountability issues and criticality issues.

4.1.18.2.1 Current Description and Anticipated Operations

A Sodium Iodide (NaI) detection system will be provided. This system will consist of a number of shielded NaI detectors plus associated counting electronics and software, positioned in key locations where plutonium could accumulate. Locations will be chosen where hold up could potentially occur unnoticed, such as ventilation ducts and "nooks and crannies". The system will be designed so that the detectors will be moveable to several locations. Each location will have a processing algorithm associated with it which will convert count rate to a crude value of Pu hold up for that location. The detectors will also be designed so that they can be manipulated by hand to monitor any region of interest.

4.1.18.2.2 Specific HWCI Requirements

The Plutonium Hold Up System must comply with the following specific requirements, in addition to the requirements identified in Appendix A for all equipment:

SS No.	Summary of Requirement
---------------	-------------------------------

PRI-2	Sodium iodine detectors.
-------	--------------------------

4.1.18.2.3 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.2 Computer Software Configuration Item (CSCI) Identification

[This paragraph ... shall be divided into subparagraphs to identify the system requirements allocated wholly or partially to each CSCI.]

[This subparagraph ... shall identify a CSCI by name and shall state its purpose. This subparagraph shall identify each requirement by project-unique identifier from the System Specification allocated wholly or partially to the CSCI. This subparagraph shall identify each interface external to the system addressed by the CSCI. Each interface external to the system shall be described in detailed quantitative terms (e.g., bits per second, word length, message format, frequency of messages, priority rules, protocol), or by reference to an ICD or System Specification paragraph. This subparagraph shall describe any additional design constraints on the CSCI.]

4.2.1 Stabilization Process Control System Software

The purpose of this CSCI is to control the mechanized operations of the Receipt Area, the Material Preparation Area, the Transport Area, the Furnace Area, and LOI Test Area. Software for the PSCS includes the program logic running on the Programmable Logic Controller (PLC), and software running on the Operator Interface Unit (OIU) computer.

4.2.1.1 Current Description and Anticipated Operations

The PSCS includes the following software packages:

- Programmable Logic Controller (PLC) program logic provides the instructions for accomplishing the desired control functions and operations of the PSCS. The program resides in the PLC processor in battery-backed CMOS RAM memory.
- Programming software is used to configure the PLC program. The programming software will be provided on the Operator Interface Unit (OIU) computer. It will be DOS or Windows compatible and provide on-line and off-line programming capability. The PLC program is loaded from the OIU into the PLC via the data highway. The software allows for maintenance of the PLC program, and allows for any revisions or modifications that may be required. The programming software incorporates password protection and privileges, guarding the PLC program logic and data tables against unintentional changes.

- Operator Interface Software gives the Operator a graphical interface with the process for control, monitoring, and alarming of the glovebox process operation. The software runs on the Operator Interface Unit (OIU), which provides a Video Display Unit (VDU) and keyboard.

4.2.1.1.1 Specific CSCI Requirements

Stabilization Process Control Software must comply with the following specific requirements, in addition to the requirements identified in Appendix A for the Plutonium Stabilization Control System:

SS No.	Summary of Requirement
---------------	-------------------------------

SECR-1	Password for configuration software.
--------	--------------------------------------

4.2.1.2 Interface Requirements

There are no direct, external interface requirements for this HWCI.

4.2.2 Packaging Process Control System Software

The purpose of this CSCI is to control the mechanized operations of the Tipping/Dispense/Fill Area, the Can Weigh and Cap Insertion Area, the Inner Can Handling Area, and the Outer Can Weld and Monitoring Areas. Software for the PPCS includes program control software running on the Programmable Logic Controller, and software running on the Operator Interface Unit (OIU) computer.

4.2.2.1 Current Description and Anticipated Operations

The software on the PLC will be ladder logic application code. A global approach will be used such that every main process or scheduler will have a dedicated area of code known as an "engine." When viewing the code for each section of the "engine," it will look identical in structure, the only difference between the sections are the addresses present on the rung.

Each series of processes or schedulers are numbered consecutively, as are the main sequences and subsequences, and have an area of memory for storage of a set of numbers that determines the order of both the main sequences and their number subsequences. At this stage it is estimated that the PPCS will have approximately 9 schedulers, 50 to 70 main sequences, and 150 to 200 subsequences.

The input/output signals are read in using an I/O handler task, which will read the signals into a table so that the next logic coding can operate on a static set of input/output signals. The next set of logic will deal with the commands arriving from the OIU. There will be separate routines for the encoders, areas of logic for data storage, interface drivers for communications to other devices and systems, and finally, the basic code for communications via the database modules.

The overall requirement of the application code is to control the process. To accomplish this, there will be schedulers that are basically a list of all main sequences that are used for mechanical movement within the process. Subsequences are called from the main sequences in the order required, noting that subsequences may be used more than once in either the same sequence or in another sequence.

The operator will choose and start a scheduler from his control panel mimic display, and the scheduler will then make logical decisions at certain points in the process, dependent on equipment conditions. The scheduler will also prompt the operator for a needed decision. The operator has the ability to issue a stop command to halt the scheduler. Each scheduler has its own task list to step through, one that is exclusive to that process and has a direct numerical relationship to that process.

When a scheduler calls a main sequence, the main sequence will check its interlocks and if they are proper, will move to the next step, which is to run the subsequences, in order, until the main sequence has been completed. At the completion of each subsequence, the PLC software will notify the OIU to highlight the control panel mimic display of a completed sequence.

The subsequences are normally run by the main sequence in Mode 1, but in the event of an abnormality (i.e. - a check not correct or an interlock unsatisfied), the operator selects Mode 2 for identification of the problem on a diagnostic display. When the problem is fixed, the operator can continue to issue commands individually to complete the sequence, then automatic operation can be resumed (Mode 1).

Alarms will either be derived directly from analog or digital signal inputs, or from the software to indicate potential damage to equipment. They will appear on the VDU mimic display with the latest, unacknowledged alarm, and alarm summary pages (first ordered chronologically, then by priority, if more than one occurs at one time). The operator will be able to display and scroll alarms and print them. Each alarm will be displayed with the date, time, details of the condition, and priority. Alarms will also set off an audible tone and a visual flash.

Software development will be formally controlled with initial planning for:

- Development languages and platforms

- Modes of execution
- Configuration control
- Operations and sequences
- Plant parameters
- Signal descriptions
- Operator interfacing
- Alarms
- Events
- Error/exception handling
- Power-up/-down routines
- Program utilities

4.2.2.1.1 Specific CSCI Requirements

Packaging Process Control Software must comply with the following specific requirements, in addition to the requirements identified in Appendix A for the Plutonium Packaging Control System:

SS No.	Summary of Requirement
---------------	-------------------------------

SECR-1	Password for configuration software.
---------------	--------------------------------------

4.2.2.2 Interface Requirements

There are no direct, external interface requirements for this CSCI.

4.2.3 Data Management System Software

The purpose of this CSCI is to capture and record the MC&A and storage package certification information.

4.2.3.1 Current Description and Anticipated Operations

The DMS includes the following software packages:

- MS-DOS or MS-Windows based operating system
- A trend software package for displaying or recording process information, if required.

- A spreadsheet package for compiling reports
- A translation package for converting Data Highway information to operating system information.

4.2.3.1.1 Specific CSCI Requirements

Data Management System Software must comply with the following specific requirements, in addition to the requirements identified in Appendix A for the Data Management System:

SS No.	Summary of Requirement
---------------	-------------------------------

SECR-1	Password for configuration software.
--------	--------------------------------------

4.2.3.2 Interface Requirements

The external interface requirements for this HWCI are identified in Appendix A of the System Specification.

4.2.4 Data Highway Communication Software

The purpose of this CSCI is communicating information on a data highway from the PSCS and PPCS to the DMS. The data highway will operate on the protocol used by the PLC vendor's equipment.

4.2.5 Process Radiometric Instrumentation Software

The purpose of this CSCI is to convert the raw counts obtained from the detectors into a meaningful result.

4.2.5.1 Current Description and Anticipated Operations

- a) Container Assay Monitor Software - This CSCI determines the plutonium content from a measure of the plutonium isotopics and the ^{240}Pu equivalent count rate. It will also perform other tasks, such as verification checks and background compensation.
- b) In the case of incoming containers, once the total plutonium content has been calculated, this is

Instrumentation display screen. This information is also uploaded to the DMS via the PSCS, and ultimately to the RFETS SNM control computer on the SAN.

- c) In the case of emptied inner containers, the PSCS software will accumulate the total quantity of plutonium sent to a 55 gallon waste drum.
- d) Plutonium Hold Up System Software - A limited amount of software will be provided to convert a radiation detector count rate into a crude value of plutonium hold up for that location.

4.2.5.1.1 Specific CSCI Requirements

Process Radiometric Instrumentation Software must comply with the following specific requirements, in addition to the requirements identified in Appendix A for the Process Radiometric Instrumentation:

SS No.	Summary of Requirement
PRI-3	Limited assay data transfer.
SECR-1	Password for configuration software.

4.2.5.2 Interface Requirements

There are no direct, external interfaces for this CSCI.

4.3 Manual Operations Identification

[This paragraph ... shall be divided into subparagraphs to identify system requirements met in conjunction with each manual operation.]

[This subparagraph ... shall identify a manual operation by name shall state its purpose. This subparagraph shall identify each requirement by project-unique identifier from the System Specification that is met in conjunction with the manual operation and shall describe any additional design constraints that affect the manual operation.]

4.3.1 Receipt Area Actions

These manual operations involve site storage package/site convenience can movement from a transfer trolley or the S-16 conveyor, data entry of inner site container/site convenience can identification, site storage package “frisking” and container(s) transfer to an airlock, and outer container removal/bagging.

4.3.1.1 Package/Can Movement from Transfer Trolley

The purpose of this action is to bring an existing site storage package/site convenience can into a protected work area of the Pu SPS.

Package/can movement from the transfer trolley must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

RA-1	Receipt of existing containers.
------	---------------------------------

4.3.1.2 Container/Can Identification and Data Entry

The purpose of this action is to check that the received inner site container/site convenience can corresponds to that identified on the work control traveller, and to enter data into the PSCS for support of MC&A and storage package certification requirements. Pertinent data includes traveller number, previous assay data, operator identification, and inner site container/site convenience can identification. This data will be entered either by bar code reading of traveller information or by keypad entry.

This action must comply with the following specific requirements:

SS No. Summary of Requirement

RA-4 Process Traveller No.

PSC-3 Entry of process data.

4.3.1.3 Site Storage Package Frisking

The purpose of this action is to monitor the incoming site storage package (after the outer container has been opened slightly) for radioactive contamination, and also monitor outgoing waste for contact radiation levels, both using a hand-held frisker.

4.3.1.4 Outer Container Removal and Bagging

The purpose of this action is to open and remove (after frisking) the outer container, including tape or other packaging materials. This action includes separation of hard waste (e.g., the container body and lid) from soft waste (e.g., tape), bagging the waste, and placing the waste into separate waste receptacles.

This action must comply with the following specific requirements:

SS No. Summary of Requirement

MPA-5 Remove plastics, etc.

4.3.1.5 Transfer from Receipt Hood into the Entry Airlock

The purpose of this action is to transfer items into the Entry Airlock for processing in the Pu SPS. Several different types of items could be passed into the Pu SPS:

- Bagged inner site containers, free of surface contamination.
- A site storage package (outer/inner containers), with surface contamination present.
- An inner/convenience can assembly, for oxide restabilization and repackaging.
- A bagged (due to poor sealing), inner/convenience can assembly.
- Miscellaneous tools, supplies, and maintenance materials.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

RA-5	Receipt via manual trolley.
------	-----------------------------

4.3.1.6 Transfer from S-16 Conveyor into the Entry Airlock

The purpose of this action is to transfer a site convenience can into the Entry Airlock for processing in the Pu SPS by removing it from the basket that hangs within the S-16 conveyor and placing it on the Airlock Container Handler. The site convenience can is presumed to have surface contamination.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

RA-2	Interface with site conveyor.
------	-------------------------------

4.3.2 Material Preparation Area Actions

These manual operations involve packaging removal, site inner container/site convenience can assaying, weighing operations, transfer of container/can to container assay monitor, inner site container/site convenience can opening, metal conditioning and transfer to convenience can, replacement of site convenience can caps, placement for oxide transfer to the furnace tray, placement of small metal pieces in a furnace tray of oxide, reduction of inner site container surface radioactivity, inner site container compaction, container/can and plastic and equipment transfers.

4.3.2.1 Outer Container Removal

The purpose of this action is to remove an outer container, if present, that has surface contamination.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

MPA-5	Remove plastics, etc.
-------	-----------------------

4.3.2.2 Plastics Removal

The purpose of this action is to remove the layers of plastic/tape around an incoming potentially contaminated inner site container/site convenience can.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

MPA-5	Remove plastics, etc.
-------	-----------------------

4.3.2.3 Outer Container Bagout

The purpose of this action is to transfer outer containers with surface contamination, which will not be processed at the Decontamination Station or Compactor Station, to disposal/storage via the Material Transfer Port for metals.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

MPA-5	Remove plastics, etc.
-------	-----------------------

4.3.2.4 Plastics Bagout

The purpose of this action is to gather discarded plastic and tape packing materials and to transfer them to disposal/storage via the Material Transfer Port for soft materials.

This action must comply with the following specific requirements:

SS No. Summary of Requirement

MPA-5 Remove plastics, etc.

4.3.2.5 Transfer of Container/Can to Container Assay Monitor

The purpose of this action is to transfer the inner site container/site convenience can from the Can/Tray Handler into the Container Assay Monitor by placing it on a lifting mechanism (which will transfer it into the monitor).

This action must comply with the following specific requirements:

SS No. Summary of Requirement

PRI-1 Assay equipment.

4.3.2.6 Inner Site Container Opening

The purpose of this action is to open the inner site container by either removing a strip of tape or by using the Container Opener.

This action must comply with the following specific requirements:

SS No. Summary of Requirement

MPA-1 Unload/decon existing containers.

4.3.2.7 Site Convenience Can/Small Metals Vessel Transfer

The purpose of this action is to place a site convenience can or a vessel containing small pieces of plutonium metal for stabilization near the Exit Isolation Door for retrieval by the Can/Tray Handler in the Transport Area.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

SP-26	Alternate convenience cans.
-------	-----------------------------

4.3.2.8 Oxide Dispensing

The purpose of this action is to remove oxide from the inner site container/site convenience can by placing it on a funneled screened feeder funnel of the Powder Dispensing Station.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

MPA-15	Automated oxide dispensing.
--------	-----------------------------

4.3.2.9 Inspection for Metals

The purpose of this action is to determine if the inner site container/site convenience can, after removal of oxides, contains plutonium metals.

4.3.2.10 Disposition of Off-Normal Materials and Chunky Oxides

The purpose of this action is to remove off-normal site materials (such as ceramics, graphite, iron and stainless steel hardware) and chunky oxides from the normal process.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

MPA-8	Handle coarse materials.
-------	--------------------------

4.3.2.11 Placement of Small Metal Pieces into Transfer Vessel

The purpose of this action is to remove pieces of plutonium metal (that are too small for brushing, < 100 grams) and placing them in a transfer vessel for movement to the LOI Sampling Station.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
---------------	-------------------------------

MPA-7	Place small Pu metal w/oxide.
-------	-------------------------------

4.3.2.12 Metal Brushing

The purpose of this action is to manually brush oxides from pieces of plutonium metal into the original inner site container/site convenience can.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
---------------	-------------------------------

MPA-2	Remove oxide/inert atmosphere.
-------	--------------------------------

4.3.2.13 Convenience Can Posting

The purpose of this action is to transfer an empty convenience can or a replacement cap for a site convenience can into the glovebox, while maintaining the inerted atmosphere.

4.3.2.14 Convenience Can Bar Code Reading

The purpose of this action is to enter the bar code of the posted in convenience can or the replacement cap for a site convenience can into the PSCS using a hand-held bar code reader through a glovebox viewport.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

PSC-3	Entry of process data.
-------	------------------------

4.3.2.15 Convenience Can Weighing

The purpose of this action is to place an empty convenience can on a balance/scale to set its empty weight.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

SP-6	Storage amounts.
------	------------------

4.3.2.16 Metal Placement into the Convenience Can

The purpose of this action is to first place a brushed, plutonium metal piece on the balance/scale, next to the convenience can, to verify the total weight is within acceptable limits. If so, then the plutonium metal is placed into the convenience can. If not, then a smaller piece is selected and weighed.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

SP-6	Storage amounts.
------	------------------

4.3.2.17 Convenience Can Capping

The purpose of this action is to replace the convenience can cap onto a filled can. If a site convenience can is used, the its cap must be replaced with one that will fit with a positive closure mechanism and has magnetic properties for use by handling equipment in the packaging process.

4.3.2.18 Convenience Can Cap Bagout

The purpose of this action is to transfer old site convenience can caps, which will not be processed at the Decontamination Station or Compactor Station, to disposal/storage via the Convenience Can Transfer Port.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
---------------	-------------------------------

MPA-5	Remove plastics, etc.
-------	-----------------------

4.3.2.19 Inner Site Container Decontamination

The purpose of this action is to remove surface contamination from inner site containers and their caps before they are compacted for disposal/storage.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
---------------	-------------------------------

MPA-1	Unload/decon existing containers.
-------	-----------------------------------

4.3.2.20 Inner Site Container Compaction

The purpose of this action is to reduce the volume of the decontaminated inner site containers.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
---------------	-------------------------------

MPA-1	Unload/decon existing containers.
-------	-----------------------------------

4.3.2.21 Compacted Inner Site Container Bagout

The purpose of this action is to transfer compacted inner site containers to disposal/storage via the Material Transfer Port for metals.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
---------------	-------------------------------

MPA-1	Unload/decon existing containers.
-------	-----------------------------------

4.3.3 LOI Test Area Actions

These manual operations involve taking samples of stabilized plutonium oxide from furnace trays, cooling them from 200 C to room temperature in the Sample Desiccator, heating the samples in the LOI Furnace, weighing the samples before and after heating, and returning the tested sample to another furnace tray of stabilized plutonium oxide (for subsequent packaging). It also includes the visual inspection of furnace trays and the placement of small pieces of plutonium metal into a furnace tray of oxide.

4.3.3.1 Placement of Small Metal Pieces into Furnace Tray

The purpose of this action is to remove pieces of plutonium metal (that are too small for brushing, < 100 grams) and placing them in a furnace tray of oxide for conversion to oxide in the stabilization furnace.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
---------------	-------------------------------

MPA-7	Place small Pu metal w/oxide.
-------	-------------------------------

4.3.3.2 Sampling

The purpose of this action is to take a representative sample of stabilized plutonium oxide from a furnace tray. This action includes collecting the sample and placing the sample in a test crucible.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

LOI-1	Test method.
-------	--------------

4.3.3.3 Data Entry of Sample Data

The purpose of this action is to enter (via the LOI Test Area keyboard) the unique identifiers for the furnace tray and the crucible into the PSCS for correlation with the test results.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

PSC-3	Entry of process data.
-------	------------------------

4.3.3.4 Sample Heating

The purpose of this action is to place sample crucibles in the LOI Furnace, close the furnace door, initiate the heating cycle, open the furnace door after the furnace has cooled, and remove the sample crucibles from the furnace.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
--------	------------------------

LOI-1	Test method.
-------	--------------

LOI-5	Consider volatiles in oxide.
-------	------------------------------

4.3.3.5 Sample Weighing

The purpose of this action is to weigh the samples in the crucibles, both before and after heating in the LOI Furnace. This action includes entering (via the LOI Test Area keyboard) of the crucible unique identifiers into the PSCS for correlation of the test results with the furnace tray identifier.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
---------------	-------------------------------

LOI-1	Test method.
LOI-3	Cool in desiccator.
LOI-5	Consider volatiles in oxide.

4.3.3.6 Cooling in the Sample Desiccator

The purpose of this action is to place (and remove) the sample crucibles in the Sample Desiccator for cooling in an ultra-dry atmosphere.

This action must comply with the following specific requirements:

SS No.	Summary of Requirement
---------------	-------------------------------

LOI-3	Cool in desiccator.
LOI-4	Weigh just after cooling.

4.3.3.7 Sample Disposal

The purpose of this action is to return LOI samples to the next incoming batch of stabilized oxide.

4.3.3.8 Visual Inspection of Empty Furnace Tray

The purpose of this action is to visually check an empty furnace tray for degradation prior to its reuse.

4.3.3.9 Visual Inspection of Filled Furnace Tray

The purpose of this action is to visually check a furnace tray of plutonium oxide prior to and after thermal stabilization, as required by site specific operating procedures.

SS No.	Summary of Requirement
---------------	-------------------------------

MPA-10	Inspect pre/post stabilization.
--------	---------------------------------

4.3.4 Tipping/Dispense/Fill Area Actions

These manual operations involve loading of empty convenience cans for filling with plutonium oxide.

4.3.4.1 Convenience Can Posting

The purpose of this action is to insert an empty convenience can into a glovebox sphincter, thus pushing an empty can into the Convenience Can Magazine for use while maintaining a seal for the inerted atmosphere.

4.3.5 Can Weigh and Cap Insertion Area Actions

These manual operations involve loading of inner can caps (or bungs) and removal of "stubs".

4.3.5.1 Load a Special Inner Can Cap

The purpose of this action is to post several inner can caps (or bungs) into the Can Weigh and Cap Insertion Glovebox through a sphincter seal into the storage magazine for automated retrieval during Pu SPS packaging operations.

4.3.5.2 Bag Out Stubs

The purpose of this action is to remove several potentially contaminated "stubs" that were cut from the sealed inner can assemblies, and to bag them for disposal/storage through a Material Transfer Port.

4.3.6 Inner Can Handling Area Actions

These manual operations involve loading of inner cans.

4.3.6.1 Load Inner Cans

The purpose of this action is to place several empty inner cans into the storage magazine for automated retrieval during Pu SPS packaging operations.

4.3.7 Outer Can Weld and Monitoring Area Actions

These manual operations involve movement of outer cans and their lids, and the transfer of completed storage packages.

4.3.7.1 Load an Outer Lid

The purpose of this action is to place the lid of an outer can in the Helium Fill/Lid Fittment Unit.

4.3.7.2 Load an Outer Can

The purpose of this action is to place an outer can on the Can Turntable/Trolley for receiving an inner/convenience can assembly.

4.3.7.3 Move the Lag Storage Trolley

The purpose of this action is to remove the Lag Storage Trolley from the Pu SPS area to the site location used for storage of completed storage packages.

5.0 Notes

[This section ... shall contain any general information that aids in understanding this document (e.g., background information, glossary, formula derivations). This section shall include an alphabetical listing of all acronyms, abbreviations, and their meanings as used in this document.]

5.1 Background Information

Within the DOE complex there are several sites, which, due to the abrupt halt in weapons production and the associated use of plutonium, have plutonium inadequately stored or in a state that is unacceptable from a safety standpoint. The DNFSB has recommended that an integrated program be formulated to convert such materials to a form or condition suitable for a safe interim storage period of 50 years. Further, it has been recommended that plutonium metals (>50% wt) be repackaged and plutonium oxides be stabilized and repackaged to meet current storage standards of DOE-STD-3013-94 by May 2002.

To achieve this program, the DOE requires a prototype unit to be installed at RFETS in Module J of Building 707. After approval of the design, systems are intended to be installed in Room 3206 of Building 371 at RFETS, at the Hanford Site, and possibly at the SRS. This program requires a systems engineering approach, involving the integration of several DOE sites, to develop a robust system that is easily adaptable to the facility and material conditions prevailing at each site.

5.2 Acronyms and Abbreviations

ALARA	As Low As Reasonably Achievable (exposure to ionizing radiation)
BNFL	British Nuclear Fuels Ltd.
CRDL	Contract Data Requirements List
CSCI	Computer Software Configuration Item
DBE	Design Basis Earthquake
DBW	Design Basis Wind
DHCS	Data Highway Communications Software
DNFSB	Defense Nuclear Facilities Safety Board
DMS	Data Management System
DOT	(U.S.) Department of Transportation
FGE	Fissile Gram Equivalent
HEPA	High Efficiency Particulate Air (filter)
HWCI	Hardware Configuration Item
IEC	International Electrotechnical Commission
IRD	Interface Requirements Document
IWCP	Integrated Work Control Program (used at RFETS)
LCO	Limiting Condition for Operation
LOI	Loss on Ignition (for testing oxide stabilization)
MC&A	Material Control and Accountability (ref: DOE Order 5633.3)
MSDS	Material Safety Data Sheet
NDE	Non-Destructive Examination
NEC	National Electric Code
NFPA	National Fire Protection Association
NRC	(U.S.) Nuclear Regulatory Commission
OIU	Operator Interface Unit
OJT	On the Job Training
ONM	Other Nuclear Material (includes neptunium ???)
ORR	Operational Readiness Review (ref: DOE Order 5480.5)
OSHA	Occupational Safety and Health Administration (or Act)
OSR	Operational Safety Requirement
PC	Performance Category (ref: DOE-STD-1021-93)
PCV	Primary Containment Vessel
PLC	Programmable Logic Controller
PPCS	Plutonium Packaging Control System
PSCS	Plutonium Stabilization Control System
Pu SPS	Plutonium Stabilization and Packaging System
PVC	Poly Vinyl Chloride (plastic bag material)
QAP	Quality Assurance Plan
RAM	Reliability, Availability, and Maintainability (analysis)
RCRA	Resource Conservation and Recovery Act

5.2 Acronyms and Abbreviations (continued)

RFETS	Rocky Flats Environmental Technology Site
SAAM	Selective Alpha Air Monitor
SAN	Safeguards Accountability Network (a classified system at RFETS)
SDD	System Design Document
SNM	Special Nuclear Material (plutonium or uranium-235)
SRS	Savannah River Site
SS	System Specification/System Requirements Document
SSCs	Structures, Systems, and Components
TID	Tamper Indicating Device
TSR	Technical Safety Requirement (ref: DOE Order 5480.22)
UPS	Uninterruptible Power Supply (for safety equipment electrical power)
USQD	Unreviewed Safety Question Determination (ref: DOE Order 5480.21)
VAC	Volts - Alternating Current
VDC	Volts - Direct Current
VDU	Visual Display Unit
VOC	Volatile Organic Compound
WIPP	Waste Isolation Pilot Project (Carlsbad, New Mexico)

5.3 Glossary of Terminology

Radiation Controlled Area - An area requiring Health Physics access control. There are three subdivisions, based on radiation type and level (and thus ventilation zoning):

Zone 1 - Areas of process within confinement, such as gloveboxes.

Zone 2 - Manned areas immediately outside Zone 1 areas.

Personnel in Zone 2 areas are segregated from the potential of internal exposure to ionizing radiation by virtue of separate ventilation (but not from the potential of direct exposure to ionizing radiation).

Zone 3 - Manned areas outside of Zone 2 areas.

Personnel in Zone 3 areas are further segregated from the potential of internal exposure to ionizing radiation and are generally shielded from the potential of direct exposure to ionizing radiation by intervening walls and equipment.

Confinement Systems:

(DOE Order 6430.1A, 1304-6.1)

Primary Confinement - Primary confinement is provided by piping, tanks, gloveboxes, encapsulating material, and the like, and any off-gas system that controls effluent from within the primary confinement. It provides confinement of hazardous material to the vicinity of its processing.

Secondary Confinement - Secondary confinement is provided by walls, ceilings, floors, and associated ventilation exhaust systems of the cell or enclosure surrounding the process material or equipment. Except in the case of glovebox operations, the area inside this barrier is usually unoccupied; it provides protection for operating personnel.

Tertiary Confinement - Tertiary confinement is provided by the walls, floor, roof, and associated ventilation exhaust system of the facility. It provides a final barrier against release of hazardous material to the environment.

Storage Packages - The multi-component assembly for plutonium storage. For clarity they are described as:

Containers - The site-furnished plutonium storage packages that enter the Pu SPS process. Generally they consist of:

- inner container (with the plutonium material)
- sealed plastic bags (around the inner container)
- outer container (for transport of the bagged inner container).

| The site may also furnish a convenience can of plutonium materials, which may or may not be reused,
| and may or may not be within sealed plastic bags.

5.3 Glossary of Terminology (continued)

Cans - The BNFL-furnished plutonium storage packages that will often replace the site furnished containers within the Pu SPS process. Generally they consist of:

- convenience can (a screw top or other can in contact with the plutonium material)
- inner can (a sealed {by automated laser welding} stainless steel can, housing a convenience can)
- outer can (a sealed {by an automated welding process} stainless steel can that houses both the convenience and inner cans for transport).

Appendix A

Applicability of Requirements to Equipment in Specific Areas

The attached table identifies each of the requirements identified in sections 3 and 5 of the System Specification, and indicates which requirements apply to **all** equipment in both specific and common areas. It also flags a requirement that may apply to some equipment in an area.

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWC1 text)		Stabilization					Packaging					Common HWCIs							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
SPS-1	Throughput	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X
SPS-2	Minimize waste	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SPS-3	MC&A support	X	X	X	X	X	X	X	X	X	X	X	X	p				p	X
SPS-4	Ops thru contam walls		X	X	X	X	X	X	X			X	p	p	p	p	p	p	X
SPS-5	Pyro/Chem reactivity	X	X	X	X	X													
SPS-6	Adsorbed water hazard	X	X	X	X	X	X	X	X	X	X	X	X	p	X	X	X	p	X
SPS-7	Spread of powders		X	X	X	X	X	X				X	X	p	p	p	p	p	X
SPS-8	Design for PC-3/Group II	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SPS-9	SSC loads, including seismic	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SPS-10	SC/SS installation	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SPS-11	Retention of mat'l in Pu SPS	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
RA-1	Receive existing containers	X	p																
RA-2	Interface with site conveyer	p																	
RA-3	Airlock size	p																	
RA-4	Process Traveller No.																	p	
RA-5	Receipt via manual trolley	X																	
RA-6	Support needs for frisker	p													p				

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWC1 text)		Stabilization					Packaging					Common HWCIs							
SS No.	Summary of Requirement from System Specification	R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
MPA-1	Unload/decon existing cont.	p	p																
MPA-2	Remove oxide/inert atmosphere		p																
MPA-3	Combine brushed oxides		p																
MPA-4	Homogenize oxides		p																
MPA-5	Remove plastics, etc.	p	p																
MPA-6	Open new packages		p																
MPA-7	Place small Pu metal w/oxide		p			p													
MPA-8	Handle coarse materials		p																
MPA-9	Non-homogeneous oxides		p																
MPA-10	Inspect pre/post stabilization		p			p													
MPA-11	Compact existing containers		p																
MPA-12	Maximum compaction height		p																
MPA-13	Compactor interlock		p																
MPA-14	Operation within 5 minutes		p																
MPA-15	Automated oxide dispensing		p															p	
MPA-16	Auto tray overfill checking		p															p	
TA-1	Transport cans without spills			p														p	

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWCI text)		Stabilization					Packaging					Common HWCI's							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
TA-2	Transport trays without spills			p														p	
TA-3	Accurate can/tray movement	p	p	p														p	
TA-4	Remote visual monitoring			p															
FURN-1	Oxide temp/time				p							X						p	
FURN-2	Furnace atmosphere				X	p								p					
FURN-3	Inside glovebox				X	p													
FURN-4	Outside temperature				X	p													
FURN-5	Furnace controller				p														
FURN-6	Furnace temp/time				p														
FURN-7	Hold two trays				X													p	
LOI-1	Test method					p													
LOI-2	Test accuracy					p													
LOI-3	Cool in desiccator					p													
LOI-4	Weigh just after cooling					p													
LOI-5	Consider volatiles in oxide					p													
TFA-1	Auto move tray to tipper arm						p											p	
TFA-2	Remove/replace screw caps						p											p	

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWCi text)		Stabilization					Packaging					Common HWCIs							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
TFA-3	Controlled oxide tipping						p											p	
TFA-4	Weight confirmation						p											p	
TFA-5	Auto move cans in area						p											p	
TFA-6	Auto move cans to gaslock						p											p	
TFA-7	Handle chunky oxides						p												
CWCI-1	Auto move cans fm gaslock							p										p	
CWCI-2	Auto move cans in area							p										p	
CWCI-3	Auto can weighing and ID							p										p	
CWCI-4	Auto fill of inner can							p										p	
ICHA-1	Automated welding/cutting								p									p	
ICHA-2	Auto can movement in area								p									p	
ICHA-3	Auto push out of stubs								p									p	
OWM-1	Helium leak detection									p									
OWM-2	Auto inner leak check									p								p	
OWM-3	Auto outer can welding									p								p	
OWM-4	Auto outer can contam check									p								p	
OWM-5	Auto outer can leak check									p								p	

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWCI text)		Stabilization					Packaging					Common HWCIs							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
OWM-6	Auto receipt inner can									p								p	
OWM-7	Auto move cans in area									p								p	
OWM-8	Auto move package to trolley									p								p	
LST-1	Two packages in trolley									p	X								
LST-2	Trolley movement interlocks										X							p	
LST-3	Spare trolleys										X								
LST-4	ALARA trolley shielding										X								
FT-1	Maximum container capacity		p									X							
FT-2	Maximum oxide depth		p			p						X							
FT-3	Tray sizing				p							X							
FT-4	Tray durability											X							
SP-1	Two confinement barriers												p						
SP-2	No organics												X						
SP-3	No surface contamination									p			p						
SP-4	Thermal loads												X						
SP-5	Container markings												p						
SP-6	Storage amounts												X						

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWC1 text)		Stabilization					Packaging					Common HWCIs							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
SP-7	Filled with helium (inner)								p				p						
SP-8	Sealed/leaktight (inner)								p	p			p						
SP-9	Leaktight post drops (inner)												p						
SP-10	304L s/s or equal (inner)												p						
SP-11	Pressure test (inner)												p						
SP-12	Internal pressure indicator												p						
SP-13	Size/thermal expansion												X						
SP-14	Filled with helium (outer)												p						
SP-15	304L s/s or equal (outer)									p			p						
SP-16	ASME VIII (outer)												p						
SP-17	Max design pressure (outer)												p						
SP-18	External pressure (outer)												p						
SP-19	Free standing (outer)												p						
SP-20	Maximum size (outer)												p						
SP-21	Robotics compatible (outer)												p						
SP-22	Automated closure									p			X						
SP-23	Leaktight post drops (outer)												p						
SP-24	Alternate inner cans												p						

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWCI text)		Stabilization					Packaging					Common HWCI's							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
SP-25	Test using alternate inners												p						
SP-26	Alternate convenience cans		p	p			p	p					p						
SP-27	Convenience can atmosphere		p				p						p						
HGA-1	SS/SC seismic requirements													X					
HGA-2	Backflow prevention													p					
HGA-3	Intake filters													p					
HGA-4	Exhaust filters													p					
HGA-5	Hood air velocity	p							p										
HGA-6	Oxygen analysis equipment		p	p			p	p											
HGA-7	Excess oxygen actions		p	p			p	p											
HGA-8	Flow to less contamination													X					
HGA-9	HEPA filtration													p					
HGA-10	Dump valve design													p					
HGA-11	Preclude oxide dispersion		p	p	p	p	p												
E-1	Design criteria		p		p	p													
E-2	Electrical cabinets														X			X	
E-3	Electrical connectors (dust)		p	p	p	p	p	p											

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWCI text)		Stabilization					Packaging					Common HWCI's							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
E-4	Electrical connectors (plugs)		p	p	p	p	p	p											
E-5	UPS, per safety analysis														p				
E-6	Lighting - amounts		p	p		p	p	p											
E-7	Lighting - type	p	p	p		p	p	p	p										
E-8	Lighting - location		p	p		p	p	p											
E-9	National Electric Code	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
SSP-1	Support design per Perf Cat	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
SSP-2	Support constr per Perf Cat	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
SSP-3	Impact with existing items															X			
SSP-4	Concrete anchorage															X			
SSP-5	Support frequency															X			
SSP-6	304 stainless steel		p	p	p	p	p	p											
SSP-7	Anchorage seismic loads	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
SSP-8	Seismic decoupling						p												
FPS-1	Detection/alarm system	p	p	p	p	p	p	p	p										
FPS-2	Glovebox overheat detection	p	p	p	p	p	p	p											
FPS-3	Oxide heat detectors		p																

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWC1 text)		Stabilization					Packaging					Common HWCIs							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
FPS-4	Fire door isolation	p																	
FPS-5	Mag oxide buckets		p			p													
FPS-6	Life safety code	X	X	X	X	X	X	X	X	X									
FPS-7	Fire codes and standards	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
PSC-1	Monitor/control interlocks	p	p	p	p	p	p											p	
PSC-2	Monitor/control environment	p	p	p	p	p	p											p	
PSC-3	Entry of process data	p	p			p	p											p	p
PSC-4	Control automatic ops	p	p	p	p	p												p	
PSC-5	Info to DMS																	p	
PPC-1	Can balances		p				p	p											
PPC-2	Monitor/control interlocks			p			p	p	p	p								p	
PPC-3	Monitor/control environment						p	p										p	
PPC-4	Entry of process data						p	p										p	
PPC-5	Control automatic ops						p	p	p	p								p	
PPC-6	Info to DMS																	p	
PPC-7	Leak & contam test info									p								p	
DMS-1	MC&A info to SNM computer																	p	

to Equipment in Specific Areas

X= All Equipment in Area
p= Part of Equipment (see HWCI text)

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWCI text)		Stabilization					Packaging					Common HWCIs							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
RAM-7	Removable shielding	p	p	p	p	p	p	p	p										
RAM-8	Spare equipment	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
ENVR-1	Elevation	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
ENVR-2	Room Environment	X								X	X								
ENVR-3	Glovebox Environment		X	X	X	X	X	X	p										
MATL-1	Gasket materials	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
MATL-2	Use of stainless steels	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
TOX-1	No asbestos	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
TOX-2	No mercury (except in lights)	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
TOX-3	No PCBs	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
TOX-4	Clad lead shielding	X	X	X	X	X	X	X	X	X	X			X		X			X
TOX-5	Use of MSDS	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
PART-1	Avoid counterfeit parts	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
PART-2	Mechanical fasteners	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
PART-3	Electrical standards	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
EMR-1	Assay equipment protection		p																p
NAME-1	Unique IDs per site	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWC1 text)		Stabilization						Packaging						Common HWCIs					
		R	M	T	F	L	T	C	I	O	L	F	S	H	S	S	C	P	R
SS No.	Summary of Requirement from System Specification	A	A	A	A	I	A	A	A	M	T	T	E	A	P	P	I	I	I
NAME-2	Master Equipment List (MEL)	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
NAME-3	Use site labeling standard	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SAFE-1	Protection from hazards	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SAFE-2	Safe shutdown in emergency	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SAFE-3	Design of safety class items	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SAFE-4	Gloveboxes not sharp		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SAFE-5	Meet IS&H, NFPA, & OSHA	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SAFE-6	Machine guards	p	p			p													
SAFE-7	Electrical safety	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SAFE-8	Lockout/tagout	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SAFE-9	Platforms/work surfaces	p	p			p		p		p							X		
SAFE-10	Compressed gases	p	p					p	p	p									p
SAFE-11	Laser light								p	p							p		
RADP-1	ALARA in design	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
RADP-2	Source compositions	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
RADP-3	Self-shielding	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	p
RADP-4	Use DOE RadCon Manual	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWCI text)		Stabilization					Packaging					Common HWCI's							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
SS No.	Summary of Requirement from System Specification																		
RADP-5	500 mrem/yr to whole body	X	X	X	X	X	X	X	X	X	X								
RADP-6	Shielding materials	X	X	X	X	X	X	X	X	X	X			X		X			X
RADP-7	10 rem/yr to extremities	X	X	X	X	X	X	X	X	X	X								
RADP-8	Methods of ALARA design	X	X	X	X	X	X	X	X	X	X			X		X			X
RADP-9	Contamination containment		X	X	X	X	X	X	X				X						
RADP-10	Components minimize radcon	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
BOX-1	Design reference documents		p	p	p	p	p	p											
BOX-2	304 stainless steel		p	p	p	p	p	p											
BOX-3	Light windows		p	p		p	p	p											
BOX-4	Gloveports		p	p		p	p	p											
BOX-5	Storage shelves		p	p		p	p	p											
BOX-6	Butt welds/floor fit		p	p	p	p	p	p											
BOX-7	Airlocks	p	p	p	p	p	p	p											
BOX-8	Consistent appearances		p	p	p	p	p	p											
BOX-9	Pass-through connectors		p	p	p	p	p	p											
BOX-10	Gas supply filters		p	p	p	p	p	p											
BOX-11	Leak tightness		p	p	p	p	p	p	p										
BOX-12	Glovebox cooling		p	p	p	p	p	p											

Applicability of Requirements to Equipment in Specific Areas

SS No.		X= All Equipment in Area p= Part of Equipment (see HWCi text)		Stabilization				Packaging						Common HWCIs																															
				R	A	M	P	T	F	L	O	I	C	W	C	I	C	H	A	O	L	S	T	F	T	S	P	A	H	E	S	F	P	C	t	r	i	P	R	I					
BOX-13	Criticality drains			p	p	p	p	p	p	p	p	p	p	p																															
BOX-14	Shutoffs for utilities			p	p	p	p	p	p	p	p	p	p	p																															
BOX-15	Airlock inop if operator near	p		p																																									
BOX-16	Pneumatic gas type	p		p	p	p	p	p	p	p	p	p	p	p																															
DECON-1	No glovebox crevices			X	X	X	X	X	X	X	X	X	X	X																															
DECON-2	Glovebox finish			p	p	p	p	p	p	p	p	p	p	p																															
DECON-3	Surface sealing			p	p	p	p	p	p	p	p	p	p	p																															
DECON-4	Lifting lugs			p	p	p	X	p	p	p	p	p	p	p																															
DECON-5	Easy decon disassembly			X	X	X	X	X	X	X	X	X	X	X																															
CRIT-1	Desirable geometry	X		X	X	X	X	X	X	X	X	X	X	X																															
CRIT-2	Assume moderation via arms	X		X	X	X	X	X	X	X	X	X	X	X																															
CRIT-3	No hydrogenous liquids	X		X	X	X	X	X	X	X	X	X	X	X																															
CRIT-4	Initial container assay																																												
CRIT-5	Fixed location for metal cans			p	p																																								
CRIT-6	Fixed locations in processes	X		X	X	X	X	X	X	X	X	X	X	X																															
CRIT-7	Furnace tray spacing					p	p																																						
CRIT-8	Covered trays and cans			p	p	p	p																																						

Applicability of Requirements to Equipment in Specific Areas

X= All Equipment in Area p= Part of Equipment (see HWCI text)		Stabilization					Packaging					Common HWCI's							
		R A	M P A	T A	F A	L O I	T D A	C W C I	I C H A	O W M	L S T	F T	S P	H G A	E	S S P	F P	C t r l	P R I
CRIT-9	Metal cans separate in DBE		p	p			p												
CRIT-10	No DBE water in furnace			p	p														
CRIT-11	One metal convenience can		p																
CRIT-12	Only one container (make-up)		p																
CRIT-13	Area Pu metal limit	X	X	X			X	X	X	X	X		X						
CRIT-14	Area Pu oxide limit	X	X	X	X	X	X	X	X	X	X	X	X						
HENG-1	Work surface height	X	X			X					X								
HENG-2	Internal support locations		X	X	X	X													
HENG-3	Human body dimensions	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
HENG-4	Process control strategy																	X	
HENG-5	Operating procedures	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
HENG-6	Display devices																	X	
HENG-7	Warning alarms/indications																	X	
HENG-8	Labeling	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
HENG-9	Handicap access	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X
HENG-10	Environmental conditions	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SECR-1	Password for config software																	p	p

[illegible]

Appendix B

System Classification Methodology

10 Introduction

The Plutonium Stabilization and Packaging System (Pu SPS) is being designed for use in multiple Department of Energy (DOE) sites to stabilize potentially pyrophoric forms of plutonium (Pu), and package stabilized Pu dioxide powder and metals for storage in at least two nested containers, each with welded lids, that will meet the DOE 50-year packaging requirements of DOE Standard 3013 [DOE, 1994c]. A prototype Pu SPS process is initially planned for installation in Building 707 at the DOE Rocky Flats Environmental Technology Site (RFETS), then in RFETS Building 371, and in the Plutonium Finishing Plant at the DOE Hanford Reservation. Option 1 to the contract addresses possible installation in the new Actinide Packaging and Storage Facility being designed for the DOE Savannah River Site (SRS). The design objective of the Pu SPS is to be compatible for the four facilities at the three sites, as well as at facilities at other DOE sites such as the Los Alamos National Laboratory and the Lawrence Livermore National Laboratory. The purpose of this appendix is to provide guidance on safety classification of structures, systems, and components (SSCs) for the Pu SPS. This methodology does not change the existing safety classification of facility SSCs important to safety.

20 DOE Order 6430.1A Safety Classification Requirements

The DOE contract for the Pu SPS (DE-AC03-96SF20948, Attachment II, Section 4.5.1) requires that safety class systems be identified as defined by DOE Order 6430.1A, "General Design Criteria" [DOE, 1989]. Safety class requirements are provided in Section 1300-3 of that Order, which defines safety class as "systems, components, and structures, including portions of process systems, whose failure could adversely affect the environment or the safety and health of the public." Section 1300-3.2 establishes six characteristics (i.e., criteria) for safety classification [information in brackets added]:

- Those whose failure would produce exposure consequences that would exceed the guidelines in Section 1300-1.4, Guidance on Limiting Exposure of the Public, at the site boundary or nearest point of public access,
- Those required to maintain operating parameters within the safety limits specified in the OSRs [Operational Safety Requirements] during normal operations and anticipated operational occurrences,

- Those required for nuclear criticality safety,
- Those required to monitor the release of radioactive materials to the environment during and after a DBA [design basis accident],
- Those required to achieve and maintain the facility in a safe shutdown condition,
- Those that control the safety class items described above.

The most important criterion is the reference to Section 1300-1.4 which in turn references DOE Order 5400.5, "Radiation Protection of the Public and the Environment" [DOE, 1990]. DOE Order 5400.5 establishes radiological limits for routine emissions, such as 100 mrem (Committed Effective Dose Equivalent - CEDE) per year, or a planned one-time release of 500 mrem (provided that lifetime commitments are less than an average of 100 mrem per year), but does not establish separate limits from potential accidents.

Other safety classification criteria are based on the safety analysis accident analysis or defense-in-depth principles. DOE has issued further guidance on the DOE 6430.1A criterion to monitor DBA releases which relates it to the Safety Analysis Report (SAR) safety analysis and resultant Technical Safety Requirements (TSRs, or current Operational Safety Requirements (OSRs) where TSRs don't exist) [Goldenberg, 1993].

30. Other DOE Safety Classification Guidance

Since the 1989 issuance of DOE Order 6430.1A, the definition of safety class SSCs for DOE nonreactor nuclear facilities has been evolving. For example, another of the mandated references in the DOE contract (DE-AC03-96SF20948, Attachment II, Section 4.1.2.2) is use of the DOE 1020-series of standards on natural phenomena hazards (NPH). The DOE Standard 1021, "Natural Phenomena Hazards Performance Categorization Guidelines for Structures, Systems, and Components" [DOE, 1993b] designates safety class differently for reactors and non-reactors as:

Safety class SSCs shall be determined in accordance with DOE 5480.30 (for nuclear reactor facilities, Reference 4). For other facilities, SSCs that must function (during and following an NPH event) to satisfy the safety requirements given in 5481.1B and 5480.23, will be termed safety class SSCs.

For nuclear reactors, DOE Order 5480.30 [DOE, 1993a] defines safety class SSCs similar to that provided by DOE Order 6430.1A, except adds "primary environmental monitors" and the phrase "as identified by safety analysis." For other facilities, such as non-reactor nuclear facilities, the DOE Standard 1021 defines safety class SSCs as those determined by the referenced safety analysis Orders.

The DOE Order 6430.1A requirements on safety class have been replaced by DOE Order O420.1 [DOE, 1995c], which is in the process of being implemented at most DOE sites. The DOE Order O 420.1 states that:

Detailed application of these requirements shall be guided by safety analyses that establish the identification and functions of safety (safety class and safety significant) Structures, Systems, and Components (SSCs) for a facility and establish the significance to safety of functions performed by those SSCs.

The commonality of all of these definitions is that the safety analysis should be used to identify safety class SSCs. The SAR for most existing DOE nuclear facilities were developed per the requirements of DOE Order 5481.1B, "Safety Analysis and Review System" [DOE, 1986]. For nuclear facilities, this Order was replaced by DOE Order 5480.23, "Nuclear Safety Analysis Reports" [DOE, 1992a]. Most DOE sites with plutonium facilities are in the process of phased implementation of the new DOE Order 5480.23. However, RFETS does not have a DOE Order 5480.23 implementation plan, and instead is implementing a new "necessary and sufficient" authorization basis process [McEahern, 1996] that is to provide equivalency to the DOE Order 5480.23 requirements.

40. Current DOE Safety Classification Guidance

DOE's most recent guidance for safety classification of SSCs for nonreactor nuclear facilities is provided in DOE Standard 3009 [DOE, 1994b]. This standard was developed to implement DOE Order 5480.23 for nuclear facilities. Standard 3009 was also developed to assist in implementation of the DOE natural phenomena standards (e.g., DOE Standards 1021 and 1020) by providing guidance on safety classification of SSCs.

DOE Standard 3009 provides this guidance for safety classification based on a hazards analysis and an accident analysis. Rather than a single safety class distinction, the standard establishes "Safety-class" and "Safety-significant" SSCs. Together, the two classifications are called "Safety SSCs," and guidance on the level of information required for the safety analysis report (SAR) is provided in Chapter 4, "Safety Structures, Systems, and Components."

Safety-class SSCs are defined by DOE Standard 3009 (which is the same as in DOE Order 5480.30), as:

Systems, structures, or components including primary environmental monitors and portions of process systems, whose failure could adversely affect the environment, or safety and health of the public as identified by safety analysis. [DOE 5480.30]

For the purpose of implementing this Standard, the phrase "adversely affect" means Evaluation Guidelines are exceeded. Safety-class SSCs are systems, structures, or components whose preventive

or mitigative function is necessary to keep hazardous material exposure to the public below the offsite Evaluation Guidelines. This definition would typically exclude items such as primary environmental monitors and most process equipment.

Safety-significant SSCs are defined by DOE Standard 3009 as:

Structures, systems, and components not designated as safety-class SSCs but whose preventive or mitigative function is a major contributor to defense in depth (i.e., prevention of uncontrolled material releases) and/or worker safety as determined from hazard analysis.

As a general rule of thumb, safety-significant SSC designations based on worker safety are limited to those systems, structures, or components whose failure is estimated to result in an acute worker fatality or serious injuries to workers. Serious injuries, as used in this definition, refers to medical treatment for immediately life-threatening or permanently disabling injuries (e.g., loss of eye, loss of limb) from other than standard industrial hazards. It specifically excludes potential latent effects (e.g., potential carcinogenic effects of radiological exposure or uptake).

The general rule of thumb cited above is not an Evaluation Guideline. It is a lower threshold of concern for which safety-significant SSC designation may be warranted, not a quantitative criteria. Estimates of worker consequences for the purpose of safety-significant SSC designation are not intended to require detailed analytical modeling. Considerations should be based on engineering judgment of possible effects and the potential added value of safety-significant SSC designation.

[Note: Safety-significant SSC as used in this Standard distinguishes a specific category of SSCs other than safety-class SSCs. It should not be confused with the generic modifier "safety significant" used in DOE orders (e.g., DOE 5480.23.)]

In summary, Safety-class SSCs are those required to protect the public and whose failure could potentially result in exceeding accident Evaluation Guidelines. Safety-significant SSCs are those required to provide defense-in-depth to protect the public, or to protect the worker from immediately life-threatening situations. Safety-class SSCs can only be determined from a quantitative accident analysis, while Safety-significant SSCs should preferably be determined from a qualitative hazard analysis as required by DOE Standard 3009 Chapter 3, "Hazard and Accident Analyses." Safety-significant SSCs can also be determined from the accident analysis based on the defense-in-depth principle where the SSCs were credited to prevent or mitigate accidents, but their failure would not result in exceeding Evaluation Guidelines.

50. Evaluation Guidelines

To implement DOE Standard 3009 to designate Safety-class SSCs, Evaluation Guidelines must be established. DOE initially proposed Evaluation Guidelines in draft Standard 3005, "Evaluation

Guidelines for Accident Analysis and Safety Structures, Systems, and Components" [DOE, 1994a]. These proposed Evaluation Guidelines were based on step functions (i.e., similar to a risk curve) of radiological consequence limits (e.g., ranging from 0.5 to 25 rem to the public) versus three accident frequency bins (Anticipated, Unlikely, Extremely Unlikely).

DOE/HQ recommended withdrawing the draft DOE Standard 3005, and proposed adding an appendix to DOE Standard 3009 to establish Evaluation Guidelines for consistent complex-wide implementation [DOE, 1995a]. A proposed draft Appendix A was issued for review that: (1) recommended using an offsite radiological Evaluation Guideline of 25 rem CEDE instead of a risk curve or frequency-consequence step functions; (2) recommended an offsite nonradiological Evaluation Guideline of ERPG-2; and (3) eliminated establishment of onsite radiological and nonradiological Evaluation Guidelines. A final DOE Standard 3009 Appendix A has not been issued by DOE.

The Defense Nuclear Facilities Safety Board (DNFSB) has issued Recommendation 94-3 [DNFSB, 1994] which in part recommends development of different safety classification guidelines. The DNFSB also recommended revision of the relationship among safety classification of SSCs, hazard categorization of nuclear activities and facilities, and natural phenomena performance categorization of SSCs as currently established by DOE Standard 1021. RFETS has developed an Implementation Plan to disposition the DNFSB Recommendation 94-3 sub-recommendations 5 and 6, but has not resolved the safety classification approach at this time. Discussions with DNFSB staff and consultants have suggested that Evaluation Guidelines should be based on 0.5 rem to the public to designate safety class SSCs.

Regarding hazard categorization, the definition of hazard category is provided in DOE Order 5480.23 [DOE, 1992a]. DOE Standard 1027 [DOE, 1992b] provides more prescriptive guidance for classifying the facility, facility segmentation, and individual nuclear activities. RFETS Buildings 707 and 371, and Hanford's Plutonium Finishing Plant, have already been classified by their operating contractors as Hazard Category 2 nuclear facilities per the guidance of DOE Standard 1027. Individual nuclear activities within these facilities, e.g., thermal stabilization and current packaging operations, have not had a hazard classification per the new Order and Standard. For the Pu SPS project, the thermal stabilization and packaging operations should be designated a preliminary hazard classification of Hazard Category 2.

DOE Standard 1021 provides guidance for NPH performance categorization [DOE, 1993b]. The Pu SPS SSCs should be designed as Performance Category 3 (PC-3), as identified in the DOE contract (DE-AC03-96SF20948, Attachment II, Section 4.1.2.2). This is an appropriate performance categorization for any facility handling substantial quantities of plutonium. For information purposes, the structure of Building 707A (Modules J and K) would probably not meet PC-3 criteria because it was only upgraded to RFETS's previous Design Basis Earthquake (DBE) of 0.21g horizontal acceleration at surface. RFETS has not established design criteria for a PC-3 earthquake for any of the nuclear facilities, although Building 371 was determined to have a capacity that would meet an Evaluation Basis Earthquake defined similar to PC-3 loads. Pu SPS SSCs that provide a safety

function should be designed to the DOE Standard 1020 [DOE, 1994d] PC-3 criteria due to the plutonium hazards and considering that the process is also planned for installation in other similar facilities and sites.

60. Operating Contractors Safety Classification Procedures

As mentioned earlier, most DOE sites with plutonium facilities are in the process of phased implementation of the new DOE Order 5480.23 and do not have upgraded safety analyses developed per the guidelines of DOE Standard 3009 that have been approved by DOE. Consequently, some operating contractor procedures for safety classification have been upgraded per the DOE Standard 3009 guidance while others have not (e.g., worker safety SSCs are included in safety class designations). Since DOE/HQ has not issued Evaluation Guidelines, most contractor procedures for safety classification within the DOE complex are not consistent with each other. A comparison of safety classification guidance for the three sites proposed for Pu SPS, DOE Order 6430.1A, and other industry standards (e.g., ANSI N46.1; Brookhaven, 1986; 10 CFR Part 72) is provided in Table B-2 at the end of this appendix. A summary of contractor procedures at the three DOE sites and how they relate to DOE Standard 3009 follows.

The RFETS procedure [RFETS, 1996a] designates System Categories. System Category 1 & 2 SSCs are determined as those SSCs credited in the Authorization Basis (e.g., SAR accident analysis) to assure public or worker nuclear safety related to immediate fatalities or serious injuries; System Category 3 SSCs are other standard industrial safety, fire protection, or security systems; and System Category 4 SSCs are non-safety related. System Category 1 & 2 SSCs are called Vital Safety Systems, and would be equivalent to the DOE Standard 3009 Safety-class and Safety-significant designation, but a further segregation cannot be made. The RFETS procedure does not have any Evaluation Guidelines for identifying safety class SSCs, and does not attempt to make a safety class or safety significant designation.

The Hanford procedure [WHC, 1996] has been revised to implement DOE Standard 3009, and provides additional or more conservative guidance. This procedure designates two levels of safety classification, "safety class" and "safety significant." Safety class SSCs protect the public from exceeding radiological risk guidelines, or prevent a nuclear criticality. Safety significant SSCs protect against an acute worker fatality or multiple serious injuries to workers, protect other onsite (non-facility) workers from exceeding radiological or hazardous chemical risk guidelines, provide defense-in-depth to protect the public from radiological releases, or protect the public from exceeding hazardous chemical risk guidelines. Additional qualitative criteria similar to DOE Order 6430.1A apply to safety class and safety significant SSCs, which are not required by DOE Standard 3009, but are useful in determining safety SSCs. Evaluation guidelines for safety classification of SSCs are 0.5 rem Committed Effective Dose Equivalent (CEDE) plus Effective Dose Equivalent (EDE) for the public (safety class) and 5 rem (CEDE + EDE) for onsite workers (safety significant SSCs), but both can also be replaced by quantitative risk curves (i.e., step functions of consequence limits versus three

frequency bins) as identified in Table B-2 at the end of this appendix. Hanford also has offsite and onsite nonradiological guidelines to designate safety significant SSCs. The Hanford procedure implements DOE Standard 3009, except for: (1) establishing offsite and onsite Evaluation Guidelines based on risk curves (similar to those originally proposed in the draft DOE Standard 3005 [DOE, 1994a]), instead of the DOE-proposed Standard 3009 Appendix A 25 rem Evaluation Guideline; and (2) including prevention and mitigation of nuclear criticality accidents as safety class, regardless of exceeding the radiological risk curves.

Like the Hanford procedure, the SRS procedure [WSRS, 1995] has been revised to implement DOE Standard 3009, and provides additional or more conservative guidance. It designates those SSCs that are important to safety as determined by the safety analysis as "Safety Class" or "Safety Significant." Safety Class SSCs are those whose failure could exceed Offsite Radiological or Nonradiological Guidelines (i.e., risk curves as listed in Table B-2 at the end of this appendix). Safety Significant SSCs are those whose failure could exceed Onsite Radiological or Nonradiological Guidelines (i.e., risk curves as listed in Table B-2 at the end of this appendix), or prevent worker fatalities or permanent disabilities from other than routine hazards. Additional qualitative criteria similar to DOE Order 6430.1A apply to Safety Class and Safety Significant SSCs, which are not required by DOE Standard 3009, but are useful in determining safety SSCs. The SRS procedure implements DOE Standard 3009, except for establishing offsite and onsite Evaluation Guidelines based on risk curves (similar to those originally proposed in the draft DOE Standard 3005 [DOE, 1994a]), instead of the DOE-proposed Standard 3009 Appendix A 25 rem Evaluation Guideline.

70. Recommended Safety Classification for Pu SPS

The designation of SSCs for the Pu SPS as either Safety-class or Safety-significant as recommended by DOE Standard 3009 cannot be determined at this time because:

- (1) DOE has not finalized Evaluation Guidelines to designate Safety-class and Safety-significant SSCs,
- (2) Contractor safety classification procedures and Evaluation Guidelines are not consistent with each other,
- (3) Facility Final SARs have not been upgraded to DOE Order 5480.23 based on DOE Standard 3009,
- (4) The technical basis for safety classification, i.e., a hazard and accident analysis performed per DOE Standard 3009 guidance for a Preliminary SAR, is not planned for the Pu SPS for the two facilities at RFETS and one at Hanford. Instead, an unreviewed safety question determination (USQD) per DOE Order 5480.21, "Unreviewed Safety Questions," and contractor procedures is planned for the RFETS Building 707 prototype. The USQD will not provide sufficient hazard

| analysis information for Safety-significant determination (although worker risk will be
| qualitatively addressed), but should provide adequate accident analysis basis for Safety-class
| determination.

Even when Evaluation Guidelines are finally issued by DOE/HQ for consistent application of DOE
Standard 3009 at all DOE sites, it will not affect the Building 707 Final SAR in the near term. RFETS
| has not implemented DOE Order 5480.23 for Building 707 and is planning to develop a new
| authorization basis (i.e., Basis for Operations) per the "necessary and sufficient" process being
| implemented at RFETS [McEahern, 1996].

Therefore, the Pu SPS project will adopt one designation of "Safety-SSC" based on the DOE Standard
3009 guidance that combines Safety-class and Safety-significant criteria. The general guidance of DOE
| Orders 6430.1A and O 420.1 will be used, as modified by the Hanford and SRS procedures. Safety-
SSCs are those required to prevent or mitigate potential accidents as determined by safety analysis to
be performed later in the design process. Those characteristics of Safety-SSCs that may be applicable
to Pu SPS are listed in Table B-1.

Table B-1. Safety-SSC Classification Criteria

Structures, systems, and components (SSCs) required to prevent or mitigate potential accidents as determined by the safety analysis are Safety-SSCs if they meet one or more of the following criteria:	
1.	Required to ensure that any credible event shall not exceed 0.5 rem (50-year CEDE) to an individual member of the public.
2.	Required to prevent an acute fatality to facility or onsite workers, or life-threatening or permanently disabling injuries to a group of workers, except where the SSCs are controlled through an implemented institutional safety or radiation protection program.
3.	Required to prevent, monitor, or detect a nuclear criticality accident, even if that accident would not meet or exceed criterion (1) or (2).
4.	Required to provide a supporting function to ensure that the Safety-SSC criteria (1), (2), and (3) can be provided or to ensure that the required safety function is not prevented.
5.	Required to maintain operating parameters within the TSRs or OSRs that are necessary to ensure the Safety-SSC criteria (1), (2), and (3).
6.	Required to achieve or maintain the operating process or facility in a safe shutdown condition where the consequences to the public may exceed criterion (1).

A 0.5 rem (50-year CEDE) Evaluation Guideline is used for criterion 1 to protect the public. This is consistent with DOE Order 6430.1A (i.e., one-time release per DOE Order 5400.5), the Brookhaven recommendation for nonreactor nuclear facilities, and the Hanford and SRS procedures (i.e., for high probability accidents, or those where a quantitative assessment of accident probability of occurrence is not performed). No specific non-radiological Evaluation Guidelines are deemed necessary for the Pu SPS project due to the lack of significant quantities of chemicals. Also, no specific radiological Evaluation Guidelines are proposed for onsite workers, consistent with current DOE/HQ recommendations.

A general approach for the Pu SPS project to apply this safety classification criteria is shown in Figure B-1. Steps 1 through 5 and 7 will result in one of three classification designations, i.e., Safety-SSC (Step 6), non-Safety-SSC subject to RFETS System Category 3 designation (Step 8), and non-Safety-SSC subject to RFETS System Category 4 (Step 9).

Figure B-1 Safety Classification Method

The first step is to identify the SSC for classification. This should be defined at the structure and system level, rather than components. The system's primary functions are then described.

The second step is to define hazards and accidents of concern for the process and material of interest. This will generally be accomplished by review of previous safety analysis.

Step 3 is to identify any safety functions that prevent or mitigate any accident potential. In addition to nuclear hazards, this includes identifying common industrial hazards that could cause injury to workers or the public or damage to property or the environment. These common industrial hazards are of interest to assure that institutional safety controls are identified, and their contribution to a nuclear accident, i.e., can the hazard initiate or worsen a Pu accident.

The fourth step then identifies those hazards that could contribute to an accident involving Pu (i.e., release or criticality). This is necessary in order to designate Safety-SSCs versus other safety-related SSCs to control common industrial hazards.

The Table B-1 Safety-SSC criteria are applied in Step 5. If any of the six criteria are met, then the SSC is designated as a Safety-SSC in Step 6. These SSCs are generally equivalent to the RFETS System Category 1/2 designation, WHC safety class and safety significant designations, or WSRS Safety Class and Safety Significant designations. Those SSCs that may be exceptions can be re-assessed based on the Table B-1 Safety-SSC criteria.

The Table B-1 criteria will be applied by reviewing existing SARs, USQDs, etc., and previous contractor safety classification designations for processes similar to the Pu SPS. These safety analyses include the Building 707 Final SAR [FSAR, 1987], the environmental assessment for thermal stabilization in Buildings 707 and 371 [DOE, 1995b and EG&G 1993], applicable RFETS unreviewed safety question determinations, and hazard and accident analysis (e.g., Final SARs, USQDs, etc.) performed at Hanford and SRS for similar operations.

Source terms from analyzed accidents where the SSC was assumed to fail or was not credited to mitigate accidents can be extracted and applied with conservative dispersion and dose assessment methods (e.g., 95 percentile meteorology) to assess dose to a hypothetical maximum offsite individual. At RFETS, conservative consequences methods based on application of the MACCS computer code [Chanin, 1990] and an averaged 1.9 kilometer distance to the site boundary result in approximately 1 rem CEDE per gram of Pu (of particle size less than 10 microns) released to the atmosphere [Peterson, 1993]. The site boundary distance for Hanford and SRS is much greater, and therefore should not result in additional SSCs needing designation as Safety-SSCs.

General guidance on design and quality assurance requirements for Safety-SSCs is listed in Appendix A and B of Hanford procedure WHC-CM-4-46, Section 9.0. The "single failure criterion" from DOE Order 6430.1A and as discussed in the Hanford procedure should only apply to those SSCs necessary to protect the public so that criterion 1 of Table B-1 is not exceeded. Components in the system may

not be required to provide the safety function and can be "downgraded." This can be performed per the RFETS procedure 2-C93-COEM-DES-273 [RFETS, 1996b] as analyzed by a Failure Mode and Effects Analysis (FMEA) or Item Functional Classification Table.

The remaining steps apply to RFETS only. Step 7 addresses those SSC functions for worker safety, environmental protection, or safeguards and security purposes. Step 8 designates this as a non-Safety-SSC subject to the RFETS System Category 3 designation. Design requirements are those required or recommended by standard industrial codes. Some enhanced quality assurance and other management controls may be required, e.g., see RFETS procedure 1-V51-COEM-DES-210.

If the SSC provides no worker safety, environmental protection, or safeguards and security functions, then it is designated as a non-Safety-SSC for RFETS in Step 9. This is equivalent to the RFETS System Category 4. Standard industrial design requirements are applicable, and no quality assurance requirements are anticipated for these SSCs.

This safety classification approach will be re-assessed after its initial implementation for the RFETS Building 707 Pu SPS prototype to incorporate lessons learned. In addition, it will be re-assessed based on improvements being made within the DOE complex (e.g., DNFSB Recommendation 94-3 Integrated Program Plan, and future revisions to the three contractor's procedures).

80. References

- ANSI N46.1 *Guidance for Defining Safety-Related Features of Nuclear Fuel Cycle Facilities*, ANSI N46.1-1980, American National Standard, July 1981
- Brookhaven, 1986 *Non-Reactor Nuclear Facilities: Standards and Criteria Guide*, DOE/TIC-111603, Rev. 1, Brookhaven National Laboratory, Upton, New York, September 1986
- Chanin, 1990 D. I. Chanin, et. al., *MELCOR Accident Consequence Code System (MACCS)*, NUREG/CR-4691, prepared by Sandia National Laboratories for U.S. Nuclear Regulatory Commission, Washington, D.C., Volumes 1, 2, and 3, February 1990
- DNFSB, 1994 "Recommendation 94-3 to the Secretary of Energy," Defense Nuclear Facilities Safety Board, Washington, D.C., September 26, 1994
- DOE, 1986 *Safety Analysis and Review System*, DOE Order 5481.1B, U.S. Department of Energy, Washington, D.C., September 1986
- DOE, 1989 *General Design Criteria*, DOE Order 6430.1A, U.S. Department of Energy, Washington, D.C., 1989
- DOE, 1990 *Radiation Protection of the Public and the Environment*, DOE Order 5400.5, U.S. Department of Energy, Washington, D.C., February 8, 1990
- DOE, 1992a *Nuclear Safety Analysis Reports*, DOE Order 5480.23, U.S. Department of Energy, Washington, D.C., April 1992
- DOE, 1992b *Hazard Categorization and Accident Analysis Techniques for Compliance with DOE Order 5480.23, Nuclear Safety Analysis Reports*, DOE Standard DOE-STD-1027-92, U.S. Department of Energy, Washington, D.C., December 1992
- DOE, 1993a *Nuclear Reactor Safety Design Criteria*, DOE Order 5480.30, U.S. Department of Energy, Washington, D.C., January 1993
- DOE, 1993b *Natural Phenomena Hazards Performance Categorization Guidelines for Structures, Systems, and Components*, DOE Standard DOE-STD-1021-93, U.S. Department of Energy, Washington, D.C., July 1993

- DOE, 1994a *Evaluation Guidelines for Accident Analysis and Safety Structures, Systems, and Components*, proposed DOE Standard DOE-STD-3005-YR, U.S. Department of Energy, Washington, D.C., February 25, 1994 (draft)
- DOE, 1994b *Preparation Guide for U.S. Department of Energy Nonreactor Nuclear Facility Safety Analysis Reports*, DOE Standard DOE-STD-3009-94, U.S. Department of Energy, Washington, D.C., July 1994
- DOE, 1994c *Criteria for Safe Storage of Plutonium Metals and Oxides*, DOE Standard DOE-STD-3013-94, U.S. Department of Energy, Washington, D.C., December 1994
- DOE, 1994d *Natural Phenomena Hazards Design and Evaluation Criteria for Department of Energy Facilities*, DOE Standard DOE-STD-1020-94, U.S. Department of Energy, Washington, D.C., April 1994
- DOE, 1995a Gerald E. Gears memorandum to Distribution, "Proposed Cancellation of Draft DOE-STD-3005-94 and Addition of Appendix to DOE-STD-3009-94," Office of Engineering, Operations, Security and Transition Support, Defense Programs, U.S. Department of Energy, Washington, D.C., January 20, 1995
- DOE, 1995b *Environmental Assessment For the Consolidation and Interim Storage of Special Nuclear Material at Rocky Flats Environmental Technology Site*, DOE/EA-1060, U.S. Department of Energy, Rocky Flats Field Office, Golden, Colorado, June 1995
- DOE, 1996c *Facility Safety*, DOE Order O 420.1, U.S. Department of Energy, Washington, D.C., Change 1, November 16, 1995
- EG&G, 1993 *Thermal Stabilization Risk Analysis Technical Support Document, Resumption of Thermal Stabilization of Plutonium Oxide in Building 707, Rocky Flats Plant, Golden, Colorado*, Ecology & NEPA Division, EG&G Rocky Flats, Inc., Golden, Colorado, August 1993
- FSAR, 1987 *Building 707 Final Safety Analysis Report*, Rockwell International, Rocky Flats Plant, Golden, Colorado, June 1987 (with 1995 OSRs)
- Goldenberg, 1993 Goldenberg, N. letter to R. Stark, Division of Systems Analysis and Standards, "Request for Interpretation of Safety Class Items in DOE 6430.1A - INT.93-2," Office of Nuclear Safety Policy and Standards, U.S. Department of Energy, Washington, D.C., September 9, 1993

McEahern, 1996	McEahern, P. letter to Distribution, "Approval of Authorization Basis Summary Plan," ABG:PMM:07117, Authorization Basis Group, U.S. Department of Energy, Rocky Flats Environmental Technology Site, Golden, CO, June 13, 1996
Peterson, 1993	Peterson, Vern L. <i>Reference Computations of Public Dose and Cancer Risk From Airborne Releases of Plutonium</i> , NSTR-015-93, Nuclear Safety Engineering, EG&G Rocky Flats, Inc., Rocky Flats Environmental Technology Site, Golden, Colorado, December 23, 1993
RFETS, 1996a	"Design Process Requirements," 1-V51-COEM-DES-210, <i>Conduct of Engineering Manual</i> , Kaiser-Hill Company, Rocky Flats Environmental Technology Site, Golden, Colorado, 95-DMR-0011210, February 5, 1996
RFETS, 1996b	"Engineering Standards for Procurement," 2-C93-COEM-DES-273, <i>Conduct of Engineering Manual</i> , Kaiser-Hill Company, Rocky Flats Environmental Technology Site, Golden, Colorado, 95-DMR-000143, February 5, 1996
WHC, 1996	"Safety Classification of Structures, Systems, and Components," Section 9.0, WHC-CM-4-46, <i>Safety Analysis Manual</i> , Westinghouse Hanford Company, Hanford Site, Richland, WA, February 26, 1996, Rev. 2
WSRS, 1995	"Functional Classification Methodology Manual (U)," Rev. 12 May 1995, and Procedure 2.25, Rev. 3 of <i>Procedure Manual E7, "Conduct of Engineering and Technical Support (U),"</i> as cited in <i>Safety Class and Safety Significant Final Functional Classification Report for the Defense Waste Processing Facility (DWPF) (U)</i> , WSRC-TR-95-0189, Westinghouse Savannah River Company, Savannah River Site, Aiken, GA, July 1995

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	DOE 6430.1A	DOE/TIC-11603-Rev.1 BNL-51444-Rev.1	ANSI N46.1-1980	RFETS System Category 1 & 2	RFETS System Category 3
	Section 1300-3.2	Section 1.2.3		1-V51-COEM-DES-210	1-V51-COEM-DES-210
Definition	Safety class items are systems, components, and structures, including portions of process systems, whose failure could adversely affect the environment or the safety and health of the public.	A safety class system is a system:	Safety-related - The function of any structure, system, component, or administrative procedure, the failure of which may result in a dose commitment in excess of the dose commitment guides prescribed in this standard.	Those engineered safety features credited or designated as in an approved Authorization Basis document which have been determined to be essential to assuring public safety or worker nuclear safety related to immediate fatalities or serious injuries.	SSCs that do not meet the requirements of System Category 1 & 2, but: - are relied upon for worker protection from radiological or toxicological hazards; or, - Are required for protection of SNM or classified material; or
	Specifically, safety class items are those systems, components, and structures with the following characteristics:			For design activities where DOE Order 6430.1A applies, those SSCs that meet the Safety Class criteria in Section 1300-3	
radiological emissions/exposures, including routine operations	Those whose failure would exceed the guidelines in Section 1300-1.4, Guidance on Limiting Exposure of the Public	(3) required to maintain dose consequences within the guidelines specified in the appropriate facility-specific appendix and discussed in 1.2.1			
OSR/TSR limits	Those required to maintain operating parameters within the safety limits specified in the OSRs during normal operations and anticipated operational occurrences				
nuclear criticality safety	Those required for nuclear criticality safety	(2) required for nuclear criticality safety		This includes . . . those SSCs required for nuclear criticality safety.	

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	WHC Safety Class	WHC Safety Significant	WSRS Safety Class	WSRS Safety Significant	NRC Spent Fuel Storage Important to Safety
	WHC-CM-4-46, Section 9.0	WHC-CM-4-46, Section 9.0	WSRC-TM-93-9	WSRC-TM-93-9	10 CFR 72.3 and 72.106
Definition	Safety class SSCs prevent or mitigate releases to the public that would otherwise exceed the offsite radiological risk guidelines, or prevent accidental nuclear criticality. These SSCs:	Safety significant SSCs prevent or mitigate releases of radiological materials to onsite workers and toxic chemicals to the offsite public and onsite workers, including defense-in-depth barriers; and worker safety SSCs as listed below. These SSCs:	Safety Class functions are selected to prevent (preferred) or to mitigate the release and are those:	Safety Significant functions are defined as those:	SSCs important to safety mean those features of the ISFSI or MRS whose function is:
					(3) To provide reasonable assurance that spent fuel or high-level radioactive waste can be received, handled, packaged, stored, and retrieved without undue risk to the health and safety of the public.
radiological emissions/exposures, including routine operations	1. Prevent or mitigate offsite public exposure in excess of 0.5 rem (excluding ingestion) -- risk criteria (below) can also be used. (formerly SC-1)	6. Prevent or mitigate onsite exposure to radiological materials in excess of 5 rem EDE - risk criteria (below) can also be used. (formerly SC-2)	1) required to ensure that any credible event shall not exceed the Offsite Radiological Evaluation Guidelines to an individual member of the public		(1) To maintain the conditions required to store spent fuel or high-level radioactive waste safely,
OSR/TSR limits	4. Maintain operating parameters within the TSRs or OSRs that protect the public per criteria 1 or 2. (formerly SC-1)	11. Maintain operating parameters within the TSRs or OSRs that protect the onsite worker per criterion 6. (formerly SC-2)	4) required to maintain operating parameters within the TSR Safety Limits that are required to ensure the Safety Class 1, 2, and 3 criteria are met.	5) required to maintain operating parameters within the TSR Safety Limits that are required to ensure the Safety Significant 1, 2, 3, and 4 criteria are met.	
nuclear criticality safety	5. Maintain double contingency protection against an accidental nuclear criticality as defined in WHC-CM-4-29, Nuclear Criticality Safety. (formerly SC-1)			3) required to prevent, monitor, or detect a nuclear criticality accident even if that accident would not directly impact worker safety.	

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	DOE 6430.1A	DOE/TIC-11603-Rev.1 BNL-51444-Rev.1	ANSI N46.1-1980	RFETS System Category 1 & 2	RFETS System Category 3
	Section 1300-3.2	Section 1.2.3		1-V51-COEM-DES-210	1-V51-COEM-DES-210
prevent or mitigate accident	Those required to mitigate the consequences of DBAs to the extent that the guidelines of Section 1300-1.4.2 are not exceeded	(1) required to prevent or mitigate the consequences of a postulated release of radioactive material that has the potential for causing offsite doses in excess of 0.5 rem to the whole body . . .	All SSCs or actions that are required to prevent an accident or to limit a potential offsite dose commitment from a postulated accident to below the indicated dose commitment guides	This includes those SSCs that are credited for the detection or mitigation of the nuclear consequences of credible, postulated accidents as defined in the Authorization Basis or supporting analysis. . . (definition of Vital Safety Function)	
monitor releases from accidents	Those required to monitor the release of radioactive materials to the environment during and after a DBA				
safe shutdown condition	Those required to achieve and maintain the facility in a safe shutdown condition				
support safety system (monitor, control, support systems, etc.)	Those that monitor or control the safety class items described above			Those existing SSCs whose failure could reasonable inhibit or prevent System Category 1 & 2 SSCs from performing their Intended Vital Safety Function...	- Are designated as Facility Support Systems in an approved Authorization Basis/Authorization Agreement; or

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	WHC Safety Class	WHC Safety Significant	WSRS Safety Class	WSRS Safety Significant	NRC Spent Fuel Storage Important to Safety
prevent or mitigate accident	WHC-CM-4-46, Section 9.0 included in safety class definition, as listed above	WHC-CM-4-46, Section 9.0 included in safety significant definition, as listed above	WSRC-TM-93-9 Safety Class functions are selected to prevent (preferred) or to mitigate the release ...	WSRC-TM-93-9 Safety Significant SSCs and Administrative Controls are required to prevent (preferred) or to mitigate the event ...	10 CFR 72.3 and 72.106 (2) To prevent damage to the spent fuel or the high-level radioactive waste container during handling and storage, or
monitor releases from accidents	3. Monitor the release of radioactive materials to the environment during and after accidents where the monitor's output initiates Emergency Response Plan actions or operator shutdown actions per #2. (formerly SC-1)	10. Monitor the release of radioactive and/or hazardous materials to the environment during and after accidents where the monitor's output initiates Emergency Response Plan actions or operator shutdown actions per #8. (formerly SC-1 or SC-2)			
safe shutdown condition	2. Place or maintain an operating process in a safe condition that prevents or mitigates consequences to the public in excess of 0.5 rem. (formerly SC-1)	8. Place or maintain an operating process in a safe condition that prevents or mitigates consequences that exceed criteria 6 or 7. (formerly SC-1 or SC-2)			
support safety system (monitor, control, support systems, etc.)	14. Support the safety function of a safety class SSC. This includes control and monitoring functions (operating air, electrical power, instrumentation, etc.). (formerly SC-1)	15. Support the safety function of a safety significant SSC. This includes control and monitoring functions (operating air, electrical power, instrumentation, etc.). (formerly SC-1 or SC-2)	3) required to provide a supporting function to ensure that criteria 1 and 2 Safety Class functions can be provided ...	4) required to provide a supporting function to ensure that criteria 1 and 2 Safety Significant functions can be provided ...	

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	DOE 6430.1A	DOE/TIC-11603-Rev.1 BNL-51444-Rev.1	ANSI N46.1-1980	RFETS System Category 1 & 2	RFETS System Category 3
	Section 1300-3.2	Section 1.2.3		1-V51-COEM-DES-210	1-V51-COEM-DES-210
Two-over-one protection	(non-safety class items) failure shall not prevent safety class items from performing their required functions.	Alternately, it may be necessary to upgrade the quality and reliability of a nonsafety class system by designing it as a safety class system in order to take credit for its safety function in the safety analysis.		Those existing SSCs whose failure could reasonable inhibit or prevent System Category 1 & 2 SSCs from performing their intended Vital Safety Function...	
defense-in-depth					
process system considerations		Safety class systems include process systems that are required to perform a safety function(s) in addition to their normal process function and engineered safety feature systems.			
shielding or containment					Systems providing for containment or shielding of radioactive material or contamination
fire protection systems					- Provide automatic fire suppression or detection capability.
emergency response					- Are required for site response in an emergency; or (includes Site LS/DW)
breathing air systems					Breathing air system

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	WHC Safety Class	WHC Safety Significant	WSRS Safety Class	WSRS Safety Significant	NRC Spent Fuel Storage Important to Safety
	WHC-CM-4-46, Section 9.0	WHC-CM-4-46, Section 9.0	WSRC-TM-93-9	WSRC-TM-93-9	10 CFR 72.3 and 72.106
Two-over-one protection		Footnote 3, Table 1. SSCs that may prevent the adequate function of safety SSCs through physical interaction (seismic, pipe whip, jet impingement, water damage, environmental changes, etc.) are considered to be safety significant. (formerly SC-1 or SC-2)	3) required ... to ensure that the required Safety Class function is not prevented.	4) required ... to ensure that the required Safety Significant function is not prevented.	
defense-in-depth		12. Provide defense-in-depth prevention or mitigation of an uncontrolled release of radioactive and/or hazardous material deemed significant. (not included in previous SC designations)		6) required to ensure that the minimum number of levels (ranging from 0 to 4) of control (physical barriers or Admin. Controls) are met.	
process system considerations					
shielding or containment					
fire protection systems					
emergency response					
breathing air systems					

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	DOE 6430.1A	DOE/TIC-11603-Rev.1 BNL-51444-Rev.1	ANSI N46.1-1980	RFETS System Category 1 & 2	RFETS System Category 3
	Section 1300-3.2	Section 1.2.3		1-V51-COEM-DES-210	1-V51-COEM-DES-210
chemical hazards		refers to DOE Orders, OSHA, and industry references			Systems which contain pesticides, carcinogens, beryllium, or toxic chemicals in sufficient quantities ...
Offsite MOI Guidelines: (50-yr CEDE + EDE dose)	ALARA < 0.1 rem/yr or one time 0.5 rem release	risk curve	0.5 rem	No dose criteria; only if credited in FSAR accident analysis	Not applicable
- Normal operations (> 1/yr)		ALARA < 0.1 rem/yr from all pathways, or 25 mrem/yr from air pathway only	Standard does not apply to normal operations and attendant releases		
- Anticipated Events (1E-2/yr - 1/yr, or 1E-1/yr)		0.1 to 0.5 rem			
- Unlikely Events (1E-4/yr - 1E- 2/yr)		0.5 to 2.5 rem (10% of 10CFR100)			
- Extremely Unlikely Events (1E 6/yr - 1E-4/yr)		6 to 25 rem (25% - 100% of 10CFR100)			
- Incredible Events (< 1E-6/yr)	Yes; don't have to design for	MOI dose may exceed 25 rem		Yes	Yes
- risk curve	No	Figure 1.2-1 illustrates the intent of the dose guidelines and must not be interpreted as establishing a continuum of consequence limits.	No	No	No
Onsite Guidelines: (50-yr CEDE + EDE dose)	None	Dose to onsite personnel:	Standard does not apply to onsite exposures	None	None
- Normal operations (> 1/yr)		ALARA < 1 rem/yr			
- Anticipated Events (1E-2/yr - 1/yr, or 1E-1/yr)					
- Unlikely Events (1E-4/yr - 1E- 2/yr)		None - address in site emergency plan			
- Extremely Unlikely Events (1E 6/yr - 1E-4/yr)		None - address in site emergency plan			
- Incredible Events (< 1E-6/yr)					

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	WHC Safety Class	WHC Safety Significant	WSRS Safety Class	WSRS Safety Significant	NRC Spent Fuel Storage Important to Safety
	WHC-CM-4-46, Section 9.0	WHC-CM-4-46, Section 9.0	WSRC-TM-93-9	WSRC-TM-93-9	10 CFR 72.3 and 72.106
chemical hazards		7. Prevent or mitigate toxic chemical exposure to within the risk guidelines of WHC-CM-4-46, Chapter 7.0. (formerly SC-1 or SC-2)	2) required to ensure that any credible event shall not exceed the Offsite Nonradiological Evaluation Guidelines to an individual member of the public.	2) based on a quantitative analysis, required to ensure that any credible event shall not result in a release that is either (1) in excess of 29 CFR 1910.119 TQs, or (2) exceed onsite hazardous material criteria (Figure 8.2)	
Offsite MOI Guidelines: (50-yr CEDE + EDE dose)	risk curve	Not applicable	Figure 8.1 risk curve	Not applicable	5 rem
- Normal operations (> 1/yr)	Footnote 1, Table 1, states that frequency > 0.1/yr are considered planned events that must be mitigated within normal operational limits.				
- Anticipated Events (1E-2/yr - 1/yr, or 1E-1/yr)	0.5 rem		0.5 rem		
- Unlikely Events (1E-4/yr - 1E-2/yr)	5 rem		5 rem		
- Extremely Unlikely Events (1E-6/yr - 1E-4/yr)	25 rem		25 rem		
- Incredible Events (< 1E-6/yr)	Yes		Yes		
- risk curve	from WHC-CM-4-46, Section 7.0; Rev. 4	from WHC-CM-4-46, Section 7.0; Rev. 4	Yes		No
Onsite Guidelines: (50-yr CEDE + EDE dose)	Not applicable	risk curve	Not applicable	Figure 8.2 risk curve	
- Normal operations (> 1/yr)		not applicable			
- Anticipated Events (1E-2/yr - 1/yr, or 1E-1/yr)		5 rem		25 rem or ERPG-2	
- Unlikely Events (1E-4/yr - 1E-2/yr)		25 rem		25 rem or ERPG-2	
- Extremely Unlikely Events (1E-6/yr - 1E-4/yr)		100 rem		100 rem or ERPG-3	
- Incredible Events (< 1E-6/yr)		Yes		Yes	

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	DOE 6430.1A Section 1300-3.2	DOE/TIC-11603-Rev.1 BNL-51444-Rev.1 Section 1.2.3	ANSI N46.1-1980	RFETS System Category 1 & 2 1-V51-COEM-DES-210	RFETS System Category 3 1-V51-COEM-DES-210
Nuclear Facility Worker Accident Guidelines:	None		Standard does not apply to nuclear facility workers	No dose criteria; only if credited in FSAR accident analysis	
- accidents		< guidance on emergency exposures during rescue and recovery activities (DOE 5480.1A, Chp XI, 4.e)			
Accident dose guideline definition			Dose Commitment Guides - The committed dose or dose fractions that constitute the criteria for determining the designation of SSCs as safety-related		
Nonsafety class systems	Failure of these items shall not adversely affect the environment or the safety and health of the public.	If the maximum conservatively calculated potential offsite dose due to system failure will not exceed 0.5 rem, and if the system is not required for nuclear criticality safety, the system may be designed as a nonsafety class system.	Non-safety related if SSC failure does not result in dose > dose commitment guides	Non-safety class (NSC) items - Any SSC which is not required to assure that a System Category 1 or 2 system performs its intended vital safety function(s). . . Category 3 and 4 systems are classified as NSC.	System Category 4 is defined as SSCs that do not meet the requirements of System Category 1 & 2 or System Category 3.
methods		On the basis of the accident analysis performed to assess the potential radiological hazards at a particular facility, the adequacy of the safety classification recommended by this guide can be determined.	From the model of the accident, those features and procedures essential to limiting the calculated dose commitment below the design guideline levels can be identified		

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	WHC Safety Class	WHC Safety Significant	WSRS Safety Class	WSRS Safety Significant	NRC Spent Fuel Storage Important to Safety
	WHC-CM-4-46, Section 9.0	WHC-CM-4-46, Section 9.0	WSRC-TM-93-9	WSRC-TM-93-9	10 CFR 72.3 and 72.106
Nuclear Facility Worker Accident Guidelines:		13. Prevent or mitigate an acute fatality to a facility worker or serious injury to a group of workers, except where the SSCs are controlled through an implemented institutional safety or radiation protection program. (formerly SC-3)		1) based on a qualitative evaluation in a hazard analysis a) whose failure could result in a worker fatality or immediately life threatening or permanently disabling injuries from non-routinely-encountered hazards ...	
- accidents		9. Prevent or mitigate exposure > 5 rem EDE or an airborne concentration of toxic material > the applicable chemical ERPG-2 limit to facility operators who are relied on to achieve the safe condition of criteria 2 and 8. (formerly SC-1 or SC-2)		1) based on a qualitative evaluation in a hazard analysis: b) required to prevent the exposure to a worker ... exceed ERPG-3, or Hazard Category 3 thresholds for radionuclides ...	
Accident dose guideline definition					
Nonsafety class systems					
methods			The accident scenarios as described in the FSAR are used to identify those hazards requiring Safety Class functions.	A Defense in Depth Evaluation (DIDE) based on a process hazard analysis is used to identify candidate Safety Significant SSCs and Administrative Controls.	

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	DOE 6430.1A	DOE/TIC-11603-Rev.1 BNL-51444-Rev.1	ANSI N46.1-1980	RFETS System Category 1 & 2	RFETS System Category 3
	Section 1300-3.2	Section 1.2.3		1-V51-COEM-DES-210	1-V51-COEM-DES-210
other info				Vital Safety Systems (VSS) - Those SSCs that are relied on to accomplish Vital Safety Functions (Category 1). . . VSS and boundaries are defined by documents referenced in the Controlled Documents List (CDL).	System Category 3 SSCs are typically covered in Administrative Controls if an approved Authorization Basis/Agreement exists.

Table B-2. COMPARISON OF SAFETY CLASSIFICATION GUIDANCE

Criteria	WHC Safety Class	WHC Safety Significant	WSRS Safety Class	WSRS Safety Significant	NRC Spent Fuel Storage Important to Safety
	WHC-CM-4-46, Section 9.0	WHC-CM-4-46, Section 9.0	WSRC-TM-93-9	WSRC-TM-93-9	10 CFR 72.3 and 72.106
other info			In addition to the SSCs required to address the 4 Safety Class criteria, some SSCs may be chosen based on management decision to obtain further total dose reduction or defense in depth.	6) required to ensure that the minimum number of levels of control (varying from 0 to 3) are met.	