C/PNL -- 029

PNL-10864 Vol. 1
UC-1600

RECEIVED

DEC-28 1995

CS-17

Field Monitoring and Evaluation of a Residential Gas-Engine-Driven Heat Pump

Volume 1 - Cooling Season

September 1995

Prepared for the U.S. Department of Energy
Federal Energy Management Program
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Operated for the U.S. Department of Energy
by Battelle Memorial Institute

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor Battelle Memorial Institute, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or Battelle Memorial Institute. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PACIFIC NORTHWEST LABORATORY
operated by
BATTELLE MEMORIAL INSTITUTE
for the
UNITED STATES DEPARTMENT OF ENERGY
under Contract DE-AC06-76RLO 1830

The contents of this report are printed on recycled paper.

Field Monitoring and Evaluation
of a Residential Gas-Engine-Driven
Heat Pump

Volume 1 - Cooling Season

J. D. Miller

September 1995

Prepared for
the U.S. Department of Energy
Federal Energy Management Program
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Richland, Washington 99352

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

MASTER

Preface

The Federal government is the largest single energy consumer in the United States; consumption approaches 1.5 quads/year of energy (1 quad = 10^{15} Btu) at a cost valued at nearly \$10 billion annually. The U.S. Department of Energy (DOE) Federal Energy Management Program (FEMP) supports efforts to reduce energy use and associated expenses in the Federal sector. One such effort, the New Technology Demonstration Program (NTDP), seeks to evaluate new energy-saving U.S. technologies and secure their more timely adoption by the U.S. government.

Pacific Northwest Laboratory (PNL)^(a) is one of four DOE national multiprogram laboratories that participate in the NTDP by providing technical expertise and equipment to evaluate new, energy-saving technologies being studied and evaluated under that program.

This two-volume report describes a field evaluation that PNL conducted for DOE/FEMP and the U.S. Department of Defense (DoD) Strategic Environmental Research and Development Program (SERDP) to examine the performance of a candidate energy-saving technology—a gas-engine-driven heat pump. The unit was installed at a single residence at Fort Sam Houston, a U.S. Army base in San Antonio, Texas, and the performance was monitored under the NTDP. Participating in this effort under a Cooperative Research and Development Agreement (CRADA) were York International, the heat pump manufacturer; Gas Research Institute (GRI), the technology developer; City Public Service of San Antonio, the local utility; American Gas Cooling Center (AGCC); Fort Sam Houston; and PNL.

(a) Pacific Northwest Laboratory is operated for the U.S. Department of Energy under Contract DE-AC06-76RLO 1830 by Battelle Memorial Institute.

Summary

Through its Office of Federal Energy Management Program (FEMP), the U.S. Department of Energy (DOE) provides technical and administrative support to Federal agency programs directed at reducing energy consumption and cost in Federal buildings and facilities. One such program is the New Technology Demonstration Program (NTDP).

In this context, NTDP is a demonstration of a U.S. energy-related technology at a Federal site. Through a partnership with a Federal site, the utility serving the site, a manufacturer of an energy-related technology, and other organizations associated with these interests, DOE can evaluate new technologies. Through the results of the program, Federal agency decision makers have more hands-on information with which to validate a decision to utilize a new technology in their facilities. The partnership of these interests is secured through a Cooperative Research and Development Agreement (CRADA).

The purpose of the Fort Sam Houston/Triathlon demonstration is to evaluate the performance and cost-effectiveness of the Triathlon gas heat pump (GHP) in the Federal sector. This is done by measuring the performance of the candidate unit and comparing it to the measured performance of conventional HVAC systems currently in the residences at the base. The energy consumption, thermal measurements, and maintenance records will be primary elements in the life-cycle cost analysis of potential savings from the candidate unit.

The NTDP project at Fort Sam Houston (San Antonio, Texas) features a 3-ton gas-engine-driven heat pump. A single-cylinder, four-stroke, 5-hp engine fueled by natural gas drives the heat pump's compressor. A distinctive feature of the technology is an inherent load-matching capability. The heat pump can vary engine speed and blower fan speed, and thereby dynamically control capacity to balance with thermal loads. This balance reduces cycling and the associated thermal losses and equipment wear. The unit also produces added heating capacity through engine-waste heat recovery. The Triathlon GHP is manufactured by York International.

Three test houses at the Fort were used for the field comparison of the Triathlon against conventional residential heating, ventilating, and air-conditioning (HVAC) systems. The houses were chosen to have identical structural design and solar exposure and to be occupied by families with one or two children. Two of the houses currently have HVAC systems that represent the best available at the Fort. This includes pulse-combustion furnaces and air conditioners with scroll compressors. A third house represents the worst case, with the oldest of the Fort's conventional air conditioners and furnaces. These HVAC systems bracket the range of equipment performance currently at the Fort and typically found in many other residential installations at Federal facilities.

Baseline measurements on the three comparison units started in August 1993. One of the comparison units was replaced with the Triathlon GHP in June 1994. Side-by-side monitoring of the

Triathlon GHP and the two remaining comparison systems continued through June 1995. Monitoring of the Triathlon GHP continues through the end of December 1995.

Performance maps, based on field data, were developed for the existing residential furnaces and air conditioners monitored at Fort Sam Houston. These maps present a common basis for comparisons between the GHP and the existing equipment. The comparisons are done by projecting (mapping) the field-measured characteristics of the comparison units onto the actual loads and operating conditions seen by the GHP. This approach supplements a pre/post-measure evaluation by decoupling the measured equipment performance from the effects of different envelope characteristics, occupant behavior, and weather. Details of the technical approach used in the evaluation, including instrumentation and methodology, are presented in this volume.

Findings from the summer-cooling test have demonstrated the Triathlon GHP to be a reliable system for Fort Sam Houston. There were no forced outages during the test, giving the unit a 100% reliability record.

Throughout the cooling test season, the GHP operated at performance levels anticipated by the manufacturer. This test unit showed normal operating behavior relative to a computer simulation of the GHP. The cooling-season test results demonstrated GHP performance levels slightly above those established in the Phase I Field Test program conducted by the unit's developers. The GHP demonstrated a thermal coefficient of performance (COP) of 1.128 and a cost-equivalent test-period energy efficiency ratio (TP_EER)^(a) of 12.23 kBtu/kWh. An electric air conditioner would require a TP_EER of 12.23 to have the same overall operating costs as the GHP (based on San Antonio residential fuel prices).

The occupants concluded that the GHP provided good comfort with acceptable levels of operating noise. Monitoring of indoor humidity during cooling operation showed nearly identical average humidity levels (and associated comfort) by the Triathlon and comparison air conditioners during the summer test.

The GHP has shown potential to reduce cooling-energy costs over more conventional air conditioners. In a normal San Antonio summer, the GHP uses 41.5 kcf of gas and 864 kWh of electricity. This amount of fuel costs \$227 (based on San Antonio residential prices) and corresponds to a savings of \$111 to \$139 over the three comparison air conditioners in this field

(a) TP_EER should never be directly compared with SEER or EER. EER and SEER are based on chamber measurements of capacity and consumption. EER is a direct presentation of chamber performance at rating conditions. SEER is based on chamber measurements and standard procedures that estimate the dynamic performance of the unit over an entire season of national average conditions. TP_EER is an indicator of actual field efficiency as subject to operating conditions seen in the field test. Generally, field conditions for a TP_EER are more severe than those used in calculating a SEER (e.g., a return temperature of 80°F is assumed in SEER calculations). As a result, TP_EER measurements will generally be significantly lower than SEER ratings.

test. The savings relative to the best of the comparison units (10.45 SEER) was \$111 (32.9%).

Abbreviations, Acronyms, and Initialisms

AGCC	American Gas Cooling Center
ANSI	American National Standards Institute
ARI	Air-Conditioning and Refrigeration Institute
ASHRAE	American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc.
Btu	British thermal unit
CDD	cooling degree-day
COP	coefficient of performance
CRADA	Cooperative Research and Development Agreement
DAS	data acquisition system
DoD	U.S. Department of Defense
DOE	U.S. Department of Energy
EER	energy efficiency rating (ratio)
FEMP	Federal Energy Management Program
GHP	gas heat pump
GRI	Gas Research Institute
HVAC	heating, ventilating, and air conditioning
k	thousand
kWh	kilowatt-hour
M	million
NCDC	National Climatic Data Center
NTDP	New Technology Demonstration Program
PNL	Pacific Northwest Laboratory
RTD	resistance temperature device
SEER	seasonal energy efficiency rating
SERDP	Strategic Environmental Research and Development Program
TP_EER	test-period energy efficiency ratio
TRY	Test Reference Year

Contents

Preface	iii
Summary	v
Abbreviations, Acronyms, and Initialisms	vii
Introduction	1
Background	3
Triathlon Gas Heat Pump	3
Comparison Units	7
Demonstration Site	8
Methodology	10
Instrumentation	15
Analysis	19
Data Reduction	19
Performance Mapping	20
Pre/Post Analysis	25
Normal Weather Year	26
Computer Simulations	27
Results	29
Unit and Instrumentation Maintenance and Other Events During Testing	29
Weather Characteristics	31
Triathlon Performance	32
Comparison Units Performance	32
Comparison Units Projected Performance	34
Savings	36
Occupant Comfort	36
Conclusions	39
References	41
Appendix A - Joint Statement of Work	A.1
Appendix B - Instrumentation Details for Gas Heat Pump Monitoring	B.1

Appendix C - Performance Check by Computer Simulation	C.1
Appendix D - Additional Field Data on Triathlon	D.1
Appendix E - Fuel Price Calculations	E.1

Figures

1	Front View, Triathlon GHP Outdoor Unit (Engine and Compressor) With Weather-Monitoring Sensors Mounted on House to Left of Unit	3
2	Side View, Triathlon GHP Outdoor Unit, Showing Gas, Refrigerant, Glycol, Electric Power, and Monitoring Instrumentation Lines	4
3	Triathlon GHP Outdoor Unit With Back Panel Removed	5
4	Triathlon GHP Outdoor Unit With Side Panel Removed	6
5	Triathlon GHP Indoor Unit With Condensate Tipping Bucket Meter (Near Box) and Duct Instrumentation	7
6	Test House 1 at Fort Sam Houston, San Antonio, Texas	9
7	HVAC Capacity Monitoring Instrumentation Used in Baseline Measurements	16
8	Baseline and Triathlon Data Acquisition Systems at Test House 1	17
9	Regression on Manufacturer's Steady-State Total Capacity Data	21
10	Regression of Relative Capacity With Duty Cycle for Unit 2	22
11	Regression of Relative Capacity With Duty Cycle for Unit 3	22
12	Triathlon Total Load Time Series	23
13	Measured and Self-Mapped Energy Use Time Series From Unit 2	23
14	Regression of Daily Total Load Against Outdoor Temperature, House 1, 1994 Cooling Season Test (Triathlon Installed)	25
15	Regression of Daily Total Load Against Outdoor Temperature, House 1, 1993 Cooling Season Test (Baseline)	26
16	Distribution of Outdoor Operating Temperatures at House 1 During 1993 and 1994 Cooling Seasons	31

17	Distribution of Indoor Operating Relative Humidity	37
18	Distribution of Indoor Operating Temperature	37

Tables

1	Manufacturers' Rated Performance of Test Units	8
2	Fort Sam Houston Test House Occupancy History	9
3	Cooling Test Periods	30
4	Commissioned Performance Periods	30
5	Triathlon GHP 1994 Cooling-Season Test Performance	33
6	Comparison Units Performance in 1993 Test Season	34
7	Comparison Units Performance in 1994 Test Season	35
8	Commissioned Performance of Comparison Units Projected Onto 1994 Loads and Operating Conditions of Triathlon Unit	36
9	Normal Year Savings by Triathlon Unit Relative to Comparison Units	36

Introduction

The purpose of the New Technology Demonstration Program (NTDP) is to install and evaluate new U.S.-developed energy technologies at Federal facilities and evaluate their performance. Through the results of the program, Federal agency decision makers have more hands-on information with which to consider a new technology and validate any decision to utilize it in their facilities. The NTDP seeks to identify new energy-saving technologies, determine which have the broadest application in, and benefit to, the Federal sector, and then shorten the deployment time for those technologies that prove beneficial to the Federal market by providing a demonstration of the energy savings potential and the cost-effectiveness of these new technologies in the Federal sector. The NTDP supports Federal facilities in their effort to meet goals established in Executive Order 12902^(a) and the Energy Policy and Conservation Act.^(b)

The purpose of the Fort Sam Houston/Triathlon demonstration is to evaluate the performance and cost-effectiveness of the Triathlon gas heat pump (GHP) in the Federal sector. This is done by monitoring the performance of the candidate unit and comparing it to that of the conventional HVAC systems currently in the residences at the base. The energy consumption, thermal measurements, and maintenance records will be primary elements in life-cycle cost analysis of potential savings from the candidate unit (see Joint Statement of Work in Appendix A).

The NTDP project at Fort Sam Houston (San Antonio, Texas) features a 3-ton gas-engine-driven heat pump. A single-cylinder, four-stroke, 5-hp engine fueled by natural gas drives the heat pump's compressor (Harnish et al. 1991). A distinctive feature of the technology is an inherent load-matching capability. The heat pump can vary engine speed and blower fan speed, and thereby dynamically control capacity to balance with thermal loads. This balance reduces cycling and the associated thermal losses and equipment wear. The unit also produces added heating capacity through engine-waste heat recovery. The Triathlon GHP is manufactured by York International.

Baseline measurements on three comparison units at the Fort started in August 1993. One of the comparison units was replaced with the Triathlon GHP in June 1994. Side-by-side monitoring of the Triathlon and the two remaining comparison units continued through June 1995. Monitoring of the Triathlon GHP continues through the end of December 1995.

-
- (a) "Each agency shall develop and implement a program with the intent of reducing energy consumption by 30 percent by the year 2005, based on energy consumption per-gross-square-foot of its buildings in use, to the extent that these measures are cost-effective."
 - (b) "Not later than January 1, 2005, each agency shall, to the maximum extent practicable, install in Federal buildings owned by the United States all energy and water conservation measures with payback periods of less than 10 years. . ."

This volume is the first of a two-volume report on the Fort Sam Houston/Triathlon demonstration. Volume 1 describes the cooling performance of the Triathlon GHP during the 1994 cooling-season test relative to three comparison air conditioners. Emphasis is given to describing the methodology used in the cooling analysis (and to be used in the heating analysis) and to describing the instrumentation used in the monitoring. Although operating cost comparisons are made, the life-cycle cost analysis is presented in Volume 2. Volume 2 presents results from monitoring during the heating season, additional information on features of the Triathlon, and life-cycle cost analysis for Fort Sam Houston and other Federal facilities in the United States.

Background

Triathlon Gas Heat Pump

The Triathlon GHP is a heat pump with a compressor driven by a natural-gas-fired engine. By contrast, an electric air conditioner has a compressor driven by an electric motor. The GHP single-cylinder, four-stroke, 5-hp engine was developed by Briggs & Stratton. Annual maintenance involves changing the oil, oil filter, air filter, and spark plug. It has heavy-duty pistons, hydraulic valve lifters, water cooling, and pressurized oil lubrication. Lean-burn combustion enhances efficiency and minimizes emissions. Endurance tests of the engine indicate a lifetime in excess of 40,000 h, or 10 to 15 years of typical heat pump use. Engine noise is 65 db at 3 ft, approximately the same as that of the most advanced electric heat pump. The outdoor and indoor sections of the GHP are shown in Figures 1 through 5.

Figure 1. Front View, Triathlon GHP Outdoor Unit (Engine and Compressor)
With Weather-Monitoring Sensors Mounted on House to Left of Unit

Figure 2. Side View, Triathlon GHP Outdoor Unit, Showing Gas, Refrigerant, Glycol, Electric Power, and Monitoring Instrumentation Lines

The primary advantage of the GHP is lower operating cost. According to the Gas Research Institute (GRI), "The annual cost to operate the gas heat pump can be up to 50% less than a gas furnace/electric-air-conditioner combination or an electric heat pump." (GRI 1993). A secondary advantage is improved occupant comfort from less variation of temperature and humidity in the house. This improvement results from the GHP's variable-speed operation and electronic controls. The heat pump can vary engine speed and blower fan speed, thereby dynamically controlling capacity to balance with thermal loads. This balance reduces cycling and the associated thermal losses and equipment wear; it tends also to reduce summertime humidity levels in the house.

In the heating season, the GHP provides supply-air temperatures warmer than conventional heat pumps because of waste-heat recovery from the engine. The waste heat is delivered via a water-glycol loop to a separate radiator in the indoor unit. This feature eliminates the uncomfortably cool supply air produced by electric heat pumps during defrost cycles and periods of low outdoor ambient temperatures. The heat recovery also improves heating capacity. Compared to electric heat pumps, the gas heat pump has nearly twice the heating capacity at 0°F. Recovered heat can also be used for domestic hot water heating. On summer days, it can meet up to 100% of water heating needs.

Figure 3. Triathlon GHP Outdoor Unit With Back Panel Removed

When supplemental heat is required, the GHP meets the added load with a gas-fired auxiliary boiler (heating COP, 0.82; capacity, 65 kBtu/h). The boiler is contained in the outdoor unit and circulates hot fluid to the water-glycol radiator contained in the indoor unit. In extreme cold, the system controls shut down the heat pump and the auxiliary boiler is the sole source of heating. Outdoor temperatures below 5°F trigger a heat pump shutdown. As temperatures rise above 5°F, the heat pump is released from the shutdown mode.

Figure 4. Triathlon GHP Outdoor Unit With Side Panel Removed

The mechanical power of the engine can also be used to drive a generator to produce electricity. This power can be used to drive the heat pump fan and blower or to maintain certain critical home base power needs.^(a)

(a) This feature was not evaluated in this demonstration.

Figure 5. Triathlon GHP Indoor Unit With Condensate Tipping Bucket Meter (Near Box) and Duct Instrumentation

Early field tests indicate an average coefficient of performance (COP) of 1.3 for heating and 1.1 for cooling (York International and Battelle 1993). These results, on an energy cost basis, are as good as, or better than, the comparable figures for the most advanced electric equipment.

Comparison Units

Table 1 lists the manufacturers' performance specification for the Triathlon and the air conditioners against which it was compared. Units 1 and 2 were manufactured in 1991, used scroll compressors, and

Table 1. Manufacturers' Rated Performance of Test Units

	Compressor Type	Date Built	Capacity, kBtu/h ^(a)	EER ^(a)	SEER
Triathlon	Reciprocating	1993	38.8	----	16.2 ^(b)
Unit 1	Scroll	1991	33.8	9.53	10.45
Unit 2	Scroll	1991	33.8	9.53	10.45
Unit 3	Reciprocating	1975	40	7.5	-----

(a) Noted in terms of Air-Conditioning and Refrigeration Institute (ARI) conditions.

(b) Cost-equivalent SEER obtained through chamber measurements and calculations as outlined in ANSI Standard Z21.40.4 and using local San Antonio residential prices for natural gas and electricity.

were the same model. Unit 3 represented the oldest of the existing units at the base and used a reciprocating compressor.

Demonstration Site

The demonstration was done in the single-family residential area of the Fort where many identical 1500-ft² homes are occupied by officers and their families. The three test houses are approximately 45 years old, stucco on masonry construction, one story in height with a partially below-grade basement and with the remainder of the house over a crawl space. The HVAC systems are installed in the unconditioned basements. All units have individual gas meters that are owned and read by City Public Service of San Antonio. A typical test house is shown in Figure 6. The occupancy history for the test houses is shown in Table 2.

Figure 6. Test House 1 at Fort Sam Houston, San Antonio, Texas

Table 2. Fort Sam Houston Test House Occupancy History

Address	Period	Adults	Children
764 Chaffee (Unit 3 site)	09/15/94-06/12/95	2	1
	08/13/94-09/14/94	Vacant	
	11/15/91-08/12/94	2	2
766 Chaffee (Unit 2 site)	02/24/94-06/12/95	2	0
	12/30/93-02/23/94	Vacant	
	10/21/91-12/30/93	2	1
842 Chaffee (Unit 1 site)	01/26/94-06/12/95	2	2
	12/01/93-01/25/94	Vacant	
	04/15/93-11/30/93	2	2

Methodology

Ideally, a performance comparison of two HVAC units is done side-by-side under identical operating conditions. While this can be achieved under steady-state testing in the laboratory, dynamic field conditions in houses with occupants are difficult to control so as to yield equivalent side-by-side conditions. A pre/post assessment^(a) approach offers some advantages in that the house and possibly the occupants remain the same during the two phases of the test. However, changes in weather and occupant behavior lead to changes in operating conditions and equipment loading that can be addressed only partially with weather normalization techniques.

To address these potential problems, a hybrid approach is taken in this demonstration. The approach includes

- a weather-normalized pre/post comparison of energy usage
- performance mapping of the existing units followed by a projection of their maps onto the load records from the installed candidate unit.

A performance map is a form of empirical model that is used to predict a system's (unit and thermostat) response to a time series of load and operating conditions. The loads and conditions recorded from monitoring the candidate unit drive the performance maps of the existing unit. The result is a prediction of the existing unit's energy usage under the conditions and loads of the candidate unit. Performance mapping offers advantages over the pre/post and side-by-side comparisons in that changes in weather, loading, and operating conditions are addressed. The key component of the map is a regression-based characterization of part-load performance.

Maps should be capable of projecting to a wide range of operating and loading conditions. With air conditioners, where capacity depends on ambient conditions, this capability can be achieved through mapping relative to manufacturers' steady-state performance data. Doing so minimizes the need for a broad range of baseline conditions. Essentially, the ratio of the measured total capacity to a fit of the manufacturer's steady-state total capacity data is correlated with the duty cycle. Duty cycle is defined as the blower fractional on-time during a cycle relative to the sum of the on-time and the prior off-time. With the furnace, the capacity is not strongly dependent on operating conditions; therefore, the capacity map is absolute and only a function of a duty cycle. Equation (1) shows the functional form of the air-conditioner maps.

(a) A pre/post evaluation is a comparison of some measurable performance parameter during two time periods. Pre denotes the period before installation of the candidate measure; post is the period after the installation.

$$C = C_{ss}(T_{odb}, T_{idb}, T_{iwb}, \dot{V}) C_{pl}(x) \quad (1)$$

$$P = P_{ss}(T_{odb}, T_{iwb}, \dot{V}) P_{cf}$$

where C = part-load total capacity, Btu/h
 C_{ss} = manufacturer's steady-state total capacity, Btu/h
 C_{pl} = air-conditioner part-load factor (function of duty cycle)
 x = duty cycle
 T_{odb} = outdoor dry-bulb temperature, °F
 T_{idb} = indoor dry-bulb temperature, °F
 T_{iwb} = indoor wet-bulb temperature, °F
 $\dot{V}$ = volumetric flow rate of evaporator fan, cfm
 P = compressor power consumption, kW
 P_{ss} = manufacturer's steady-state data on compressor power, kW
 P_d = empirically-based correction factor to P_{ss} .

Equation (2) shows the form for the furnace.

$$H = H_{ss} H_{pl}(x) \quad (2)$$

where H = part-load furnace output capacity, Btu/h
 H_{ss} = manufacturer's steady-state output capacity, Btu/h
 H_{pl} = furnace part-load factor (function of duty cycle)
 x = duty cycle.

The maps are implemented through use of a time-series record of load and conditions in which the candidate unit runs. For each time increment in the series, the load balance in Equation (3) is solved to determine what run time (duty cycle) is necessary to satisfy the load at the recorded conditions. The equation is solved through iteration because the capacity is dependent on the part-load functions, which are nonlinear with respect to duty cycle and make closed-form solutions unavailable. If the estimate of run time is smaller than minimum run times seen during periods of low load (from the baseline data), the load is not acted on but added to the next period. This keeps the simulation from artificially low loading. The mapping technique can be tested by comparing the map against its own baseline load and energy record and requiring that the map's estimate of energy consumption equal the actual measured energy total in the baseline data.

$$L_c = xC(x)$$

$$L_h = xH(x) \quad (3)$$

where L_c = total cooling load, Btu/h
 L_h = heating load, Btu/h.

With run time estimated, the unit's energy consumption is estimated through Equation (4). The compressor's power draw is calculated from an empirically-based correction to a fit of the manufacturer's data on compressor power [P in Equation (1)]. The power draw from the condenser fan and supply fan is determined from average field measurements (P_{fans}). For the furnace, gas consumption is calculated using an empirically determined correction factor to the manufacturer's steady-state input capacity, H_{icd} in Equation (4):

$$\begin{aligned} E_c &= X(P + P_{fans}) \\ E_h &= XH_{iss}H_{icf} \end{aligned} \quad (4)$$

where E_c = electricity consumed by air conditioner, kWh
 P = compressor power consumption, kW
 P_{fans} = condenser and supply fan power consumption, kW
 E_h = fuel consumed by furnace, Btu
 H_{iss} = manufacturer's steady-state input capacity, Btu/h
 H_{icd} = correction factor to H_{iss} .

To complement the performance mapping, a pre/post comparison is done in the house that received the Triathlon unit. A zero-load-outdoor temperature is found for the monitoring periods before and after the installation of the unit. These temperatures serve as the basis for cooling degree-day (CDD) calculations. The CDD number for the pre- and post-period then serves to form a correction factor that accounts for changes in weather and occupant behavior (e.g., thermostat setting). The projected energy use is then calculated as shown in Equation (5):

$$E = (CDD_{post}/CDD_{pre}) E_{pre} \quad (5)$$

Three test houses at the Fort were chosen to support the hybrid approach. The houses have identical structural design and solar exposure and are occupied by families with one or two children. Energy records were checked to see that the houses are typical of other similar houses at the Fort and that the existing HVAC systems have capacities similar to that of the 3-ton Triathlon unit. Two of the houses currently have HVAC systems that represent the best available at the Fort. This includes pulse-combustion furnaces and air conditioners with scroll compressors. A third house represents the worst case, with the oldest of the Fort's conventional air conditioners and furnaces. These HVAC systems bracket the range of equipment performance currently at the Fort.

Baseline data collection (begun in August 1993) continued until the new gas-engine-driven heat pump was installed in June 1994 at house 1. Data collection on the Triathlon and the two remaining comparison units then continued through June 1995. This allows pre/post comparison

between the best case and the candidate in the installation house, and mapping from all three comparison units to the candidate load and conditions record.

At the end of the comparative-monitoring period, the occupants at house 1 were interviewed. The questions were designed to determine occupant comfort (thermal and acoustic), operating convenience, and general level of acceptance of the new technology. A summary of the interview is presented in the Results section of this volume:

Instrumentation

Baseline monitoring in support of the hybrid assessment approach involved measurements of system outputs (capacity), system inputs (energy consumption), and operating conditions. All measurements in the airstream (return-air psychrometric and sensible capacity) are conditionally sampled to produce an average over periods of output (supply fan is on). Measurements of conditions outside the airstream, such as conditioned space, basement, and outdoor condenser temperatures, are based on continuous sampling. Data loggers at the three test houses produced a record of measurements at 15-minute intervals. All averages are based on 5-second sampling intervals. The records were downloaded daily to a computer at PNL in Richland, Washington, for storage and analysis.

Operating conditions are characterized by temperature measurements in the return airstream, in the basement duct, and outside (sun-shielded) near the condenser. Platinum resistance temperature devices (RTDs) are used for the absolute temperature measurements. Humidity in the return airstream is measured with solid-state polymer film sensors calibrated using saturated salt solutions.

Sensible capacity (differential temperature) is measured with a 24-gauge type-T thermopile using six junction pairs. Six junctions are placed upstream of the furnace filter on a single support rod followed by six junctions downstream of the evaporator coils on two support rods (Figure 7). Volumetric flow rate of the supply air-handler is determined with a heat injection test using a 5-kW heating coil commonly used as a backup heat source for heat pump systems. Flow rate is determined for the high-speed blower mode associated with air-conditioner operation and the low-speed blower mode associated with furnace operation. Latent capacity (condensate flow) is recorded by counting contact closures from a calibrated tipping bucket rain gauge. Barometric pressure is measured with a variable-capacitance ceramic sensor. Supply fan speed (in revolutions per minute) is recorded with an optical sensor that counts the passes of a piece of reflective tape attached to the far side of the fan rotor. Cycling data is recorded as a count of the times the supply fan turns on during the 15-minute logger period.

Electric energy use is measured with current transformers at the compressor, condenser fan, and supply fan. Contact closures from a reed switch on an inline gas meter are counted to record volumetric flow of natural gas to the furnace.

When Unit 1 was replaced by the Triathlon in June 1994, additional instrumentation was added to accommodate the Triathlon's variable airflow and to monitor critical internal components and systems. Because of variable flow rates, independent logger averages of ΔT (temperature drop across the cooling coils) and V (volumetric flow rate) at the indoor coil do not properly represent the changing system capacity. Instead, the product, $V\Delta T$, must be averaged over the period the supply fan runs. This requires a real-time multiplication capability in the data logger and a real-time volumetric flow rate measurement. The new logger was a personal-computer-based

Duct Instrumentation

Figure 7. HVAC Capacity Monitoring Instrumentation Used in Baseline Measurements

system with conditional sampling capabilities and real-time cross-channel math processing. A laboratory-based correlation along with a site calibration is used to determine V from fan power and speed data. See Appendix B for detailed descriptions of the instrumentation for the gas-engine heat pump and a schematic diagram with sensor locations. The data acquisition system used on the Triathlon is located on the right-hand side in Figure 8. The system used on the comparison units is pictured on the left-hand side in Figure 8.

Figure 8. Baseline and Triathlon Data Acquisition Systems at Test House 1

Analysis

Data Reduction

Analysis begins with interpretation of raw sensor measurements made at the field sites. The field measurements on the HVAC systems can be classified as inputs (gas and electricity consumption), outputs (sensible and latent cooling), and operating conditions (return and outdoor).

Sensible and latent capacity are calculated with Equation (6) (ASHRAE 1989). In the sensible calculation, it is assumed that the supply air fan runs at a constant speed and provides approximately constant volumetric flow. In other words, the fan by design provides constant volumetric flow; it is assumed that neither accumulation of dust in the furnace filter nor possible changes in the outlet dampers by the occupants will affect volumetric flow. The corresponding mass flow was calculated using a psychrometric routine for specific volume, which included corrections for barometric pressure, temperature, and moisture. Pressure data were not available from the site sensor prior to June 1994 but were integrated from an online public database (on the Internet) of hourly San Antonio weather from the National Climatic Data Center (NCDC). These sea-level-referenced pressures were then corrected for site elevation.

$$\begin{aligned} S &= 60 \dot{V} \Delta T \rho (P_b, T_{ldb}, T_{lwb}) c_p \\ c_p &= 0.24 + 0.444W \\ L &= \dot{m}_{cond} (h_g(T_{ldb}) - h_{cond}) \\ h_g &= 1061 + 0.444T_{ldb} \end{aligned} \tag{6}$$

where S = sensible cooling capacity, Btu/h
 $\dot{V}$ = supply airflow rate, cfm
 ΔT = temperature differential across evaporator coils, °F
 ρ = air density, lb air/ft³
 P_b = barometric pressure, in. Hg
 T_{ldb} = dry-bulb temperature of return air, °F
 T_{lwb} = wet-bulb temperature of return air, °F
 c_p = specific heat of air, Btu/lbm °F
 W = humidity ratio of return air, lb water/lb dry air
 L = latent cooling capacity, Btu/h
 $\dot{m}_{cond}$ = condensate flow rate, lb/h
 h_g = specific enthalpy of saturated water vapor, Btu/lbm water
 h_{cond} = specific enthalpy of condensate at 50°F, Btu/lbm water.

The efficiency of the furnace was calculated using natural gas heating values as shown in Equation (7) where the factor 1020 Btu/ft³ is the value (for standard conditions) used throughout the analysis. This value was reported by City Public Service of San Antonio for June 1994. This equation is used with the gas meter's volumetric flow records to account for variations in density from pressure and temperature. The house gas-line temperature was estimated from a temperature measurement inside the gas submeter (Triathlon) or on the surface of the gas line (comparison units).

$$H_v = 1020 \frac{(P_{site} + \Delta P)}{P_{st}} \frac{T_{st}}{T_{line}} \quad (7)$$

where H_v = heating value of natural gas, Btu/ft³
 P_{site} = barometric pressure at the site, in. Hg
 ΔP = house line pressure above atmospheric, in. Hg
 P_{st} = standard pressure, 29.921, in. Hg
 T_{st} = standard temperature, 518.7, °R
 T_{line} = temperature of gas in house line, °R.

In analyzing field capacity data taken from fixed-interval data loggers, consideration must be given to the relationship between the logging interval and the cycling characteristics of the equipment. Ideally, the field data logger should have the capability of recording a time stamp at the beginning and end of each HVAC cycle. This type of sampling, triggered by events, clearly supports mapping by duty cycle. However, fixed-interval-logger periods must be chosen carefully so as to collect enough data to resolve the elements of each cycling event. If the logger intervals chosen are too long, multiple cycles will be lumped in one logger interval and will be indistinguishable.

Single HVAC system cycles divided by logger time boundaries can be reassembled and placed in the period where the event terminates. This is done with logic filters that act on the record of cycle counts, run time, and energy usage. Consumptions, outputs, and run times are totaled for the cycle. In addition to the unit's performance, duty cycle is calculated and recorded. This is defined as the blower fractional on-time during a cycle relative to the sum of the on-time and the preceding off-time.

Performance Mapping

An initial step in performance mapping of the air-conditioner data from the comparison units is the regression of the manufacturers' steady-state total-capacity data against flow rate, return, and outdoor conditions [see Figure 9 and C_{ss} in Equation (1)]. Also, the manufacturers' data on compressor power is regressed to give a relationship for compressor power draw as a function of conditions [P_{ss} in Equation (1)].

Figure 9. Regression on Manufacturers' Steady-State Total Capacity Data

The remaining component in the map $[C_p(x)]$ in Equation (1) is determined by regressing the relative capacity of the unit against duty cycle. Relative capacity is defined as the ratio of the field measured capacity during a cycle to the manufacturer's steady-state capacity at the measured operating conditions. Here the field-measured capacities are those that result from the logic filters described above. The results of these regressions are illustrated for Units 2 and 3 in Figures 10 and 11, respectively. These plots show the reductions in capacity with decreasing duty cycle that result from cycling losses.

The final step in preparing for the mapping calculations is to prepare the load time series that represents the cooling load on the house in which the Triathlon was installed. This time series serves as input to the map-load balance [Equation (3)]. To prepare the representative time series, the raw time series of the Triathlon cooling output is smoothed with a box-car routine. This is essentially a running average (composed of nine 15-min periods) that removes the cycling variations and produces a smooth time series that preserves the variations in the building load. A segment of the Triathlon load series (smoothed and raw) is shown in Figure 12.

Before actually mapping to the Triathlon load series, a check is made to see how well a unit's map can predict its own measured energy use. This self-mapping exercise serves as a general check on the technique and gives confirmation of the specific correlations done in developing the maps. This is done by mapping onto the unit's own smoothed-load time series. The results of the self-mapping test for Unit 2 are illustrated in Figure 13. This shows the excellent agreement, throughout the diurnal swings of 10 days in June, between the actual energy consumption

Figure 10. Regression of Relative Capacity With Duty Cycle for Unit 2

Figure 11. Regression of Relative Capacity With Duty Cycle for Unit 3

Figure 12. Triathlon Total Load Time Series

Figure 13. Measured and Self-Mapped Energy Use Time Series From Unit 2

(smoothed) and the predictions from the mapping. If the time series are totaled over the time basis used for developing the part-load curves, the self-mapping result differs from the actual measured energy consumption by less than 0.2% for both Units 2 and 3.

Pre/Post Analysis

To complement the mapping analysis, a pre/post analysis is applied to the baseline energy consumption recorded for Unit 1 in 842 Chaffee (before the installation of the Triathlon). As described in the methodology section, the pre/post comparison is made by adjusting the baseline data with CDD correction factor. The factor is the ratio of the CDDs for the pre- and post-periods where the base temperature for the CDD calculation is determined from the zero-load floating point for the house.

Plots of daily average load and outdoor temperature are shown in Figures 14 and 15. The x-axis intercept of these plots indicates the zero-load floating point (67.0°F in 1994, 65.3°F in 1993). Differences in the floating point can be caused by changes in the occupant thermostat set point and differences in the solar gains. The slope is nearly the same for both plots and indicates structural characteristics that impact heat transfer, driven by the outdoor temperature (such as conduction through the walls and air infiltration), have remained the same from the pre- to the post-period. The calculation of CDD in 1994 for the house with the Triathlon was 1783.1 (base 67.0°F); in 1993, it was 847.5 (base 65.3°F). This results in a pre-period to post-period correction factor of 2.10.

Figure 14. Regression of Daily Total Load Against Outdoor Temperature, House 1, 1994 Cooling Season Test (Triathlon Installed)

Figure 15. Regression of Daily Total Load Against Outdoor Temperature, House 1, 1993 Cooling Season Test (Baseline)

Normal Weather Year

The final step in the comparative analysis is to estimate the energy use and corresponding energy savings that would be seen in a normal weather year. A projection to the normal weather year accounts for an unusually hot, cold, or short test period. A normal year is defined as the Test Reference Year (TRY) for San Antonio during the period 1948 to 1975 (Olsen et al. 1984). This TRY year has 2471 CDD relative to a base temperature of 67°F.

This projection is done by calculating the ratio of the CDD during a normal year in San Antonio (2471 CDD) to those during the 1994 test season (1783 CDD). In these calculations, a base temperature of 67°F is used and reflects the outdoor temperature where the house at 842 Chaffee balanced with no load during the 1994 test season. All results from the 1994 test period at 842 Chaffee, including those projected to conditions at 842 Chaffee by the mapping or pre/post techniques, can then be converted to a normal weather year using this factor of 1.386. However, this projection technique does give a slightly conservative estimate of the Triathlon full-season performance. This is because the 1994 season includes the peak and end of the season (not the beginning) and because the Triathlon has higher efficiency at lower loads (and lower speeds) due to its variable-speed capability.

Computer Simulations

The field performance of the Triathlon was periodically compared against a computer simulation of its steady-state performance. This simulation served first to establish a baseline performance level of the unit relative to the model. Subsequent performance checks against the computer model were compared to baseline to check for performance deviations throughout the season. Significant deviations from the baseline can be indications of equipment failure. The gas-engine heat pump model, owned and developed by GRI, is an evolution of the Mark III heat pump model developed by Oak Ridge National Laboratory for electric heat pump simulation (Fischer and Rice 1986a,b).

Results

Unit and Instrumentation Maintenance and Other Events During Testing

To best present the results of the monitoring, it is useful to start with a brief history of the equipment downtime and maintenance during the testing periods. This provides the rationale behind any subsetting of the data. Throughout the discussion of the results, a distinction is made between commissioned performance and actual full test-season performance. Commissioned performance is determined over a period starting with the commissioning of the unit (including normal maintenance by the base or local dealer) at the beginning of the test period and ending with any event that would cause a significant change in the unit's performance. Commissioned performance differs from full test-season performance only when there is a maintenance event (e.g., a compressor fails and requires a replacement).

The baseline monitoring on the three comparison units started August 22, 1993. All three units performed at their commissioned levels through the baseline cooling-season test period, which ended October 20, 1993. However, Unit 2 had restricted airflow throughout the 1993 and 1994 cooling seasons. The air-conditioner airflow rate at the end of the 1993 season was measured at 577 cfm (compared to 1115 measured for Unit 1). The low-speed fan mode (furnace) for Unit 2 produced slightly lower flow rates of 564 cfm. The low flow rates and nearly identical readings for the two fan modes led to the conclusion that there was a problem with the blower or some restriction in the duct system. No changes were made in the 1993 season, but plans were made to inspect the ducts and replace the blower at the beginning of the 1994 season.

An instrumentation failure occurred in the Unit 3 house 22 days into the test. This was the result of a clogged tipping-bucket meter on the condensate line. As a result, no latent capacity measurements on Unit 3 were available until repairs were completed in June 1994. The logger in the Unit 2 house quickly developed problems in its analog boards. This left in question all of the baseline measurements on Unit 2 except for the energy consumption data. It was also determined that the cycling rate of Unit 1 coupled with the logger sampling rates used in 1993 would preclude this unit from a true duty-cycle part-load analysis as shown in Figures 14 and 15. Because of this, Units 1 and 2 were assumed to have the same part-load response as is shown in Figure 14. Logger and tipping-bucket sensor repairs were made at the beginning of the 1994 cooling season.

The 1994 cooling season was defined to start with the removal of Unit 1 and the installation of the Triathlon heat pump June 17, 1994. The test period ran 167 days through the end of November. During this period, the Triathlon unit had 100% reliability (no downtime).

In June 1994, ice was found on the evaporator coils of Units 2 and 3. It was determined that the icing problem in Unit 3 was the result of a low refrigerant charge. It was thought there might be a developing leak at the refrigerant input tap. Adding refrigerant to proper levels eliminated the icing problem. The problem in Unit 2 was determined to be partly the result of low airflow

across the evaporator coil. After Unit 1 was removed, the Unit 1 blower was taken and installed into Unit 2 in an attempt to improve airflow. Unit 2 showed only minor improvement in airflow (689 cfm in cooling mode, 619 in heating mode) over the evaporator coils. The duct system in the attic was inspected for obstructions or damage but none was found. At that time, the increase in airflow from the new fan appeared to eliminate the icing problem in Unit 2.

However, as the testing season progressed, the low airflow in Unit 2, coupled with occupant-thermostat settings as low as 70°F, contributed to two additional periods of coil icing totaling roughly 50 days. The first icing period started approximately 15 days into the cooling season. During the periods of icing, the occupant ran the blower fan continuously to melt the ice when the compressor cycled off. The occupant was encouraged to change to higher thermostat settings, yet clearly the performance of Unit 2 was less than would be expected at normal airflow rates and more conservative thermostat settings.

Unit 3 had a compressor failure 45 days into the 1994 cooling season. The condensing unit was replaced with a scroll-compressor-based unit similar to that used with Units 1 and 2.

Based on this event history, the total cooling-season test periods and commissioned-performance test periods for the four units are shown in Tables 3 and 4. The Triathlon performance analysis is based on the full 1994 cooling season. The pre/post-comparative analysis is based on full 1993 test season data from Unit 1. Mapping-comparative analysis is based on the commissioned-performance test periods for Units 1, 2, and 3.

Table 3. Cooling Season Test Periods

<u>Test Type</u>	<u>Dates</u>	<u>Day Range</u> <u>0 = 1/1/93</u>	<u>Days</u>
Comparison	6/17/94-11/30/94	532-699	167
Baseline	8/22/93-10/20/93	233-293	60

Table 4. Commissioned-Performance Test Periods.

<u>HVAC System</u>	<u>Dates</u>	<u>Day Range</u> <u>0 = 1/1/93</u>	<u>Days</u>
Triathlon	6/17/94-11/30/94	532-699	167
Unit 1	8/22/93-10/20/93	233-293	60
Unit 2	6/17/94- 6/26/94	532-542	10
Unit 3	6/17/94- 7/31/94	532-577	45

Both the baseline and comparison test periods captured peak and late summer conditions. This fully represents the typical range of summer operating conditions. The commissioned-performance test periods for Units 2 and 3 were significantly shorter. However the mapping methodology allows for calibration of the maps from a relatively short amount of monitoring time. The 10 days for Unit 2 is considered acceptable because a relatively large range (as characterized by duty cycle, and outdoor temperature) of cycle events was recorded.

Weather Characteristics

A distribution of the outdoor operating temperatures during the 1993 and 1994 cooling seasons is illustrated in Figure 16. The traces in the plot are essentially an outline of a histogram of outdoor operating temperatures normalized so that the area under the curve is equal to 1. The data here represents when the compressor is running (i.e., hours during which there is no call for cooling are not included in the distribution). The mean temperatures, represented with vertical lines, differ by less than 1°F. The 1994 season had the warmer outdoor operating conditions. Mean outdoor operating temperatures in 1994 for the Unit 2 and 3 houses (not shown in the plot) differ from that for the Triathlon house by less than 1°F. Statistics on operating conditions are included in each performance summary that follows.

Figure 16. Distribution of Outdoor Operating Temperatures at House 1 During 1993 and 1994 Cooling Seasons

Triathlon Performance

The Triathlon GHP demonstrated normal performance levels during the 1994 cooling season. There were no forced outages during the test, giving the unit a 100% reliability record. Throughout the test, the unit showed normal operating behavior relative to the computer simulation of the Triathlon (see Appendix C). The cooling-season test results demonstrated performance levels slightly above those established in the Phase I Field Test program (York International and Battelle 1993) conducted by the unit's developers. The only maintenance performed during the test period was the replacement of the indoor air filter by the dealer on October 19, 1994. This was done because indoor blower power consumption at minimum speed had risen from 77 W to nearly 140 W and indicated that the indoor air filter had become saturated.

The Triathlon GHP energy results are shown in Table 5 for the 1994 cooling season. The GHP had a thermal coefficient of performance (COP) of 1.128 and a cost-equivalent test-period energy efficiency ratio (TP_EER) of 12.23 kBtu/kWh.^(a) An electric air conditioner would require a TP_EER of 12.23 to have the same overall operating costs as the GHP (based on residential fuel prices). Additional details on the performance of the Triathlon, including the daily average summaries, are included in Appendix D.

Comparison Units' Performance

Unit 1 operated at expected efficiency levels and had the best performance of the three comparison units. Unit 2 had expected poor performance due to low airflow rates at the evaporator, lower than normal thermostat settings, and the resulting coil icing. Tables 6 and 7 summarize the performance of these units. Dashes are shown in cells where there was no data due to instrumentation outages. A particular unit may have more than one column. The first column shows the results for the entire test period. Additional columns may be given to represent performance over a subset of the total test period. For example, in 1993 because of a tipping bucket failure, latent capacity data was not available on Unit 3 after day 255. The two additional columns show the available results before and after the sensor failure. Also in 1993, only electricity usage is shown for Unit 2 because of a logger failure. A second column is shown

(a) TP_EER should never be directly compared with SEER or EER. EER and SEER are based on chamber measurements of capacity and consumption. EER is a direct presentation of chamber performance at rating conditions. SEER is based on chamber measurements along with standard procedures that estimate the dynamic performance of the unit over an entire season of national average conditions. TP_EER is an indicator of actual field efficiency as subject to operating conditions seen in the field test. Generally, field conditions for a TP_EER are more severe than those used in calculating a SEER (e.g., a return temperature of 80°F is assumed in SEER calculations). As a result, TP_EER measurements will generally be significantly lower than SEER ratings.

Table 5. Triathlon GHP 1994 Cooling-Season Test Performance (June 17, 1994, through November 30, 1994)

Parameter	Value
Mean outdoor dry-bulb, °F	80.7
Mean room dry-bulb, °F	76.4
Mean return dry-bulb, °F	74.1
Mean return wet-bulb, °F	62.0
Mean return relative humidity, %	50.6
Run time, h	1729
Sensible Cooling Output, MBtu	26.3
Latent Cooling Output, MBtu	8.1
Cooling output, MBtu ^(a)	34.5
Gas consumption, MBtu ^(b)	30.5
Thermal COP ^(c)	1.128
Electricity consumption, kWh ^(d)	623
Cost-equivalent fuel consumption, kWh ^(e)	2817
Cost-equivalent TP_EER, kBtu/kWh ^(f)	12.23
Energy cost, \$(^g)	163.6

- (a) Total sensible and latent cooling provided during the cooling season (MBtu).
- (b) Total natural gas consumed during the cooling season (MBtu). The fuel heating value of 1020 Btu/ft³ provided by City Public Service of San Antonio was assumed throughout the test period.
- (c) Cooling output divided by the gas consumption.
- (d) Total electricity consumed by the two system fans (electricity used by the starter motor, less than 1% of the total, is not included).
- (e) On a cost basis, the gas consumption of the Triathlon is converted to an equivalent electricity consumption. This effective electricity usage is then added to the actual electricity usage. The resulting total is the cost-equivalent fuel usage by the Triathlon GHP. San Antonio average costs of \$0.4257/ccf and \$0.05810/kWh were used to represent the fuel-cost rates from 6/94 through 11/94. These cost are derived from monthly adjusted rates from City Public Service of San Antonio. The monthly rates are weighted by fuel usage of the Triathlon to arrive at the two average-fuel-cost rates above (see Appendix E).
- (f) Cooling output divided by the cost-equivalent fuel usage during the test period (kBtu/kWh). (An electric air conditioner operating in substitution for the Triathlon at 842 Chaffee would need an equal TP_EER to have the same overall operating cost as the Triathlon GHP.)
- (g) Effective electricity consumption is converted to dollars using \$0.05810/kWh for the Triathlon GHP. A rate of \$0.06315/kWh is used for the comparison units. The higher rate for the comparison units reflects the impact of the peak-capacity charge of \$0.015/kWh for electric usage in excess of 600 kWh/mo, applicable from June through September (see Appendix E).

Table 6. Comparison Units' Performance in 1993 Test Season

	Unit 1	Unit 2	Unit 3		
Range of days (233 = 8/22/93)	233-293 *	233-293	233-293	233-255	255-293
Total cooling output, MBtu	18.0	---- ^(a)	----	11.2	----
Total electricity input, kWh	1942	2366	3487	1772	1715
TP_EER, kBtu/kWh ^(b)	9.28	----	----	6.32	----
Energy cost, \$	123	149	220	112	108
Duration, days	60	60	60	22	38
Run time, h	568	750	841	422	419
Sensible capacity, kBtu/h	24.4	----	21.1	21.3	20.9
Latent capacity, kBtu/h	7.4	----	----	5.2	----
Total capacity, kBtu/h	31.7	----	----	26.5	----
Mean room dry-bulb, °F	74.9	----	72.6	72.6	72.5
Mean return dry-bulb, °F	74.4	----	71.6	71.5	71.7
Mean return wet-bulb, °F	61.6	----	61.7	61.0	62.1
Mean return humidity, %	48.2	----	57.2	55.1	58.7
Mean outdoor dry-bulb, °F	79.3	----	78.4	80.9	76.8

(a) Dashed line indicates no data because of instrumentation outages.

(b) TP_EER for an electric air conditioner is the ratio of total cooling output (kBtu) to total electricity input (kWh).

for Unit 2 in 1994 to represent 10 days before the first signs of the icing problem appeared. Also in 1994, two additional columns are shown for Unit 3 for before and after the compressor failure. The periods that are used in pre/post and mapping analysis are marked with an asterisk (*) after the range of days.

Comparison Units Projected Performance

Commissioned performance of the comparison units was projected onto the operating conditions and loads seen by the Triathlon GHP in the house at 842 Chaffee. Both the mapping and the

Table 7. Comparison Units' Performance in 1994 Test Season

	Unit 2		Unit 3		
	532-699	532-542*	532-699	532-578*	586-699
Range of days (532 = 6/17/94)					
Total cooling output, MBtu	54.8	4.8	47.3	19.3	24.8
Total electricity input, kWh	6861	621	5201	2381	2482
TP_EER, kBtu/kWh	7.99	7.76	9.10	8.11	9.97
Energy cost, \$	433	39.2	328	150	157
Duration, days	167	10.4	167	46	113
Run time, h	2160	184	1338	586	664
Sensible capacity, kBtu/h	19.8	19.5	27.3	26.0	28.2
Latent capacity, kBtu/h	5.6	6.7	8.1	6.9	9.1
Total capacity, kBtu/h	25.4	26.2	35.4	32.9	37.3
Mean room dry-bulb, °F	72.5	70.0	73.5	75.4	71.9
Mean return dry-bulb, °F	71.1	68.6	71.9	74.0	69.7
Mean return wet-bulb, °F	57.2	55.6	59.9	61.5	58.3
Mean return humidity, %	42.3	43.6	49.7	49.3	50.3
Mean outdoor dry-bulb, °F	80.8	82.6	78.9	83.8	75.4

pre/post CDD correction techniques were used (see the Methodology and Analysis sections). These projections are summarized in Table 8. These projected energy numbers are the consumptions that would be seen during the 1994 season if these units had been installed in 842 Chaffee in substitution for the Triathlon unit. The TP_EER shown here is the 1994 recorded total test-period load at 842 Chaffee divided by these energy consumption numbers and are an indicator of the projected performance at 842 Chaffee.

These projected TP_EER values can be compared with actual commissioned performance TP_EERs of the comparison units (see Tables 6 and 7 in the columns marked with a "*"). Differences seen in such a comparison reflect the differences in the operating conditions of the Triathlon and those of the comparison unit. For example, Unit 2 had a commissioned test period efficiency of 7.76 kBtu/kWh while operating under average conditions of 68.6°F return dry-bulb and 82.6°F outdoor dry-bulb. Its efficiency improved to 8.28 kBtu/kWh when projected to the milder operating conditions of the Triathlon at 842 Chaffee (74.1°F return dry-bulb, 80.7°F outdoor dry-bulb).

Table 8. Commissioned Performance of Comparison Units Projected Onto 1994 Loads and Operating Conditions of Triathlon Unit (842 Chaffee)

<u>Projection Technique</u>	<u>Energy Use, kWh</u>	<u>TP_EER</u>
Unit 1 pre/post	4087	8.43
Unit 1 coil-map	3862	8.92
Unit 2 coil-map	4162	8.28
Unit 3 coil-map	4185	8.23

Savings

The 1994 Triathlon cooling season energy consumption (Table 5) and the 1994 projected performance (Table 8) of the comparison units can be extended to normal weather year results using the CDD correction factor of 1.386 (see discussion in Analysis section). Table 9 summarizes these normal year energy consumptions and the corresponding energy cost savings of the Triathlon relative to the comparison units. Cost calculations are based on San Antonio residential fuel prices (see Appendix E). The GHP consumes \$227 of fuel in a normal summer in the Fort Sam Houston test house. The Triathlon GHP saved from \$111 to \$139 over the projected performance of the three comparison units. The best representative of savings relative to a conventional air conditioner is the \$111 (32.9%) savings of Unit 1 (10.45 SEER).

Occupant Comfort

Occupant comfort is difficult to characterize by measurement; many parameters affect human comfort. However, an attempt is made in Figures 17 and 18 with distribution plots of indoor relative humidity and indoor dry-bulb temperature. These room humidities are based on a measurement of

Table 9. Normal Cooling Season Savings by Triathlon Unit Relative to Comparison Units

	<u>Gas Use, kcf</u>	<u>Electricity Use, kWh</u>	<u>Energy Cost, \$</u>	<u>Energy Cost Savings, \$</u>	<u>Energy Cost Savings, %</u>
Triathlon	41.5	864	226.8	----	----
Unit 1 (pre/post)	0.0	5663	357.7	131	36.6
Unit 1 (mapped)	0.0	5351	338.0	111	32.9
Unit 2 (mapped)	0.0	5768	364.2	137	37.7
Unit 3 (mapped)	0.0	5799	366.2	139	38.1

Figure 17. Distribution of Indoor Operating Relative Humidity

Figure 18. Distribution of Indoor Operating Temperature

room temperature and return air humidity while the unit is cooling. These plots are similar to plotting an outline of a histogram except they are normalized so that the area under each curve is equal to 1. The mean of each distribution is indicated with a vertical line.

Figure 17 shows a nearly identical humidity result of 47% for Units 1 and 3 and the Triathlon. Unit 2 shows lower humidity levels because of less evaporator-coil airflow and possibly because of the lower thermostat set point. Lower temperatures will increase the run times and the amount of dehumidification but also increase the moisture gains from infiltration. The lower airflow shifts the capacity of the unit from sensible to latent.

Interviews were conducted with the occupants of the house with the Triathlon GHP. The occupants indicated that the unit had provided good comfort. They commented that attempts to get them a thermostat manual had failed and left them unable to use all the features of the thermostat. When they needed to change the temperature, they used the "temporary" set-point adjustment feature on the thermostat. The startup and running sounds from the outdoor section of the Triathlon was the greatest concern of the occupants. Although they said these sounds did not disturb them when they were inside the house, they were concerned about disturbing their neighbors. They commented that the nature of the startup sounds reminded them of a lawnmower. They were pleased with the small amount of sound coming from the indoor fan (due to the variable-speed operation).

Conclusions

Findings from the summer-cooling test have demonstrated the Triathlon GHP to be a reliable system for Fort Sam Houston. The unit had no downtime, and it operated at performance levels anticipated by the manufacturer. The unit's COP during the summer-cooling test was 1.128.

The occupants concluded that the GHP provided good comfort with acceptable levels of operating noise. Monitoring of indoor humidity during cooling operation showed nearly identical average humidity levels (and associated comfort) by the Triathlon and comparison air conditioners during the summer test.

The GHP has shown potential to reduce cooling-energy costs over more conventional air conditioners. In a normal San Antonio summer, the GHP uses 41.5 kcf of gas and 864 kWh of electricity. This amount of fuel costs \$227 (based on San Antonio residential prices) and corresponds to a savings of \$111 to \$139 over the three comparison air conditioners in this field test. The savings relative to the best of the comparison units (10.45 SEER) was \$111 (32.9%).

References

- American National Standards Institute. 1994. American National Standard for Performance Testing and Rating of Gas-Fired, A/C, and Heat Pumping Appliances, Z21.40.4. New York.
- American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. 1989. 1989 ASHRAE Handbook - Fundamentals. Atlanta.
- Fischer, S. K., and C. K. Rice. 1986a. The Oak Ridge Heat Pump Design Model: Mark III Version Program Documentation. ORNL/TM-10192, Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Fischer, S. K., and C. K. Rice. 1986b. The Oak Ridge Heat Pump Models: I. A Steady-State Computer Design Model for Air-to-Air Heat Pumps. ORNL/CON--90/R1 DE84 001577, Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Gas Research Institute. 1993. "Residential Engine-Driven Gas Heat Pump." Tech Profile 393RPP12000, Chicago.
- Harnish, J. T., D. W. Procknow, F. E. Jakob, T. A. Klausling, C. E. French, and G. Nowakowski. 1991. "Residential Gas Heat Pump Design and Development." Paper presented to Cogeneration and Energy Conservation for the 90's. March 18-19, 1991, Mesa, Arizona.
- Olsen, A. R., S. Moreno, J. J. Deringer, and C. R. Watson. 1984. Weather Data for Simplified Energy Calculation, Volume III. Western United States: TRY Data. PNL-5143 Vol. III, Pacific Northwest Laboratory, Richland, Washington.
- York International and Battelle Columbus Laboratories. 1993. Field Test of the York Gas Heat Pump. GRI-92/0509, National Technical Information Service, Springfield, Virginia.

Appendix A

Joint Statement of Work

JOINT STATEMENT OF WORK
TEST BED DEMONSTRATION PROJECT

FT. SAM HOUSTON

NATURAL GAS HEAT PUMP TEST BED

1.0 BACKGROUND

The Federal government is the largest single consumer of energy in the United States. Although energy use is decreasing, there are opportunities for further reduction. Through its Office of Federal Energy Management Program (FEMP), the U.S. Department of Energy (DOE) has been providing technical and administrative support to Federal agency programs directed at reducing energy consumption and cost in Federal buildings and facilities. One such program is the Test Beds Demonstration Program (TBDP), or test bed.

A test bed is a demonstration of a U.S. energy-related technology at a Federal site. Through a partnership with a Federal site, the utility serving the Federal site, a manufacturer of an energy-related technology, Pacific Northwest Laboratory (PNL), and other organizations associated with these interests, new technologies can be evaluated. The partnership of these interests is secured through a Cooperative Research and Development Agreement (CRADA).

The goals of the Test Bed Demonstration Program are:

- To deploy a new U.S. technology in the Federal sector.
- To improve the energy efficiency of the Federal sector.
- To reduce life cycle costs and improve reliability of Federal installations.
- To stimulate widespread commercialization of U.S. technology.
- To document ways in which Federal facility management can affect change.
- To show that government and industry can work together toward common goals.

2.0 OVERALL PURPOSE AND OBJECTIVES

The purpose of this CRADA is to install, operate, monitor, evaluate and make known the results of the demonstration of a 3-ton natural gas engine driven heat pump (gas heat pump or the technology) to be installed at Ft. Sam Houston, Texas. This JSOW forms part of the Natural Gas Heat Pump Test Bed CRADA C/PNL which has as a major objective, the rapid and widespread application of this new U.S. technology by the Federal sector.

York and the Gas Research Institute's (GRI) objectives are to further document the capability of their products by installing them in the Federal building environment and having their performance monitored. City Public Service's objectives are to improve their summer and winter load patterns to more effectively use their system capabilities. Ft. Sam Houston's objectives are to reduce energy consumption and cost associated with their operations. The American Gas Cooling Center's (AGCC) objectives are to demonstrate the energy, cost, and environmental benefits of gas cooling technologies. A secondary objective is to take greater advantage of existing collaborations between product development organizations, the Federal sector, utilities, and associated organizations.

3.0 TECHNICAL OBJECTIVES

The technical objectives of this collaboration are derived from the requirements within the FEMP and present technology deployment and energy conservation efforts within the heating, ventilating, and air conditioning industry and utility sector. These objectives will be met by work to be done individually and collectively by PNL staff, York, Ft. Sam Houston, City Public Service, GRI and AGCC. The results of this collaboration will include a high-level data reporting, analysis, and management system to support the deployment efforts associated with the technology. The technical objectives are:

- Successfully install, commission, operate, maintain, and document the performance of the York 3-ton natural gas engine driven heat pump.
- Determine the life cycle cost savings that can be achieved by using the York 3-ton natural gas engine driven heat pump, based on the documented installed cost and operating and maintenance costs.
- Determine if any specific improvements are required in the York 3-ton natural gas engine driven heat pump before it can be successfully deployed in the Federal sector.
- Determine the most effective way to facilitate the widespread and rapid deployment of the York 3-ton natural gas engine driven heat pump in the Federal sector and to clearly define any barriers to deployment.

4.0 INDIVIDUAL RESPONSIBILITIES

The approach to achieving the objectives stated above involves extensive collaboration between the PNL, York, Ft. Sam Houston, City Public Service, GRI and AGCC. Each party has roles and responsibilities. Through a synergistic effort a significant advancement in deployment of this technology, necessary to support the increased use of this U.S. technology and reduce Federal energy use, will occur. The overall responsibilities are defined here. Detailed responsibilities are defined in subsequent sections of the JSOW.

PNL will have two primary responsibilities in this collaboration. First PNL will provide overall project management and reporting. Second, PNL will oversee monitoring of the existing equipment and the heat pump, analysis of the operating data, and preparation of the results of the evaluation.

York and GRI will provide the 3-ton natural gas engine driven heat pump, assist with its instrumentation, and support its maintenance during the demonstration project.

City Public Service will provide energy to Ft. Sam Houston, gas metering devices, and, along with GRI, assist with data acquisition and assessment.

Ft. Sam Houston will provide facility access and support all efforts to install, operate, and monitor the technology demonstration.

AGCC will support outreach efforts to communicate the results of the project within the Federal sector.

5.0 DESCRIPTION OF THE OVERALL PROJECT

To demonstrate a new technology, it must be installed, maintained, operated, and monitored. In addition, the results of the installation must be effectively communicated to those in the public and private sectors. The natural gas heat pump test bed covered by this joint statement of work has four distinct areas for activity: planning, execution, documentation, and decommissioning. Within each area numerous tasks are contemplated.

The objective of planning is to ensure that the technology installation at the site can be effectively implemented and that necessary and appropriate data to evaluate the technology will be obtained. This includes tasks related to site preparation, technology procurement and delivery, identification of a methodology to evaluate technology performance, the design of the data acquisition system, and the monitoring and reporting process.

The objective of execution is to obtain the data necessary to serve as a basis for an evaluation of the technology. This includes monitoring baseline information from the existing systems, installing the new technology in a single family residence, operating the building and its systems, monitoring the stream of evaluation data, and recording maintenance activity throughout the length of the project.

The objective of documentation is to record and present the results of the project and make them available. This includes data analysis, preparation of interim and final results, and participation in activities to communicate the results of the project in support of technology deployment.

The objective of decommissioning is to remove the technology, if so desired, and the monitoring equipment. This is a return of the installation to its original, or some other agreed upon, condition. The effort described herein anticipates that the technology will perform as expected by the manufacturer. If the technology cannot complete the test, decommissioning will supersede all tasks remaining, except for publication of the final report on the project.

A description of each of the tasks to be performed to meet these objectives is provided in Sections 6.0, 7.0, 8.0, and 9.0. The partners having primary and secondary responsibility are specified for each task. The anticipated deliverable for each task is also stated.

PNL will have the lead responsibility for project management, monthly progress reports, and, with assistance provided by all test bed partners as appropriate (based on who has lead responsibility for the task), all specific reports specified herein.

A task-by-task schedule for the project is provided in Section 10.0.

6.0 PLANNING

The planning effort includes those activities necessary to design the project so that the installation of the gas heat pump can be made at Ft. Sam Houston, necessary operating data can be obtained from the test home as well as several baseline homes, and the formal technology demonstration can be ended. It includes any activity up to the point where full operation and data acquisition begins in addition to the consideration of what to do when the test is completed.

6.1 Site Evaluation

Obtain a description of the candidate single family homes fronting essentially on the 700 and 800 blocks of Patch and Chaffee Roads, their existing energy systems and as-built construction, and available information about past operation, maintenance, and control of the energy systems that will be replaced or modified. This must include necessary schematics, energy consumption and billing information, maintenance records, and photographs, as well as other information necessary to portray the building as it currently exists. This information must emphasize and detail those parts of the building and energy systems that will be changed pursuant to the project and which will impact the validity of any tests associated with the technology.

Primary responsibility: Ft. Sam Houston.

Secondary responsibility: PNL.

Deliverable: A report detailing the "before" condition of the homes and their energy systems that focuses on those aspects of the building and energy systems to which the new technology will apply and reduce energy use and cost.

6.2 Integration of Monitoring Instrumentation

The gas heat pump will first be shipped to Battelle Memorial Institute who, under contract to York and GRI, will integrate performance monitoring sensors into the gas heat pump unit. This includes the installation of various temperature, pressure, and flow sensors in the heat pump. A bench-top test of the heat-pump and instrumentation package will be conducted to insure the proper operation of the data acquisition system before shipment to Ft. Sam Houston for installation.

Primary responsibility: York and GRI.

Secondary responsibility: PNL.

Deliverable: A report documenting the location of sensors in the heat pump, any heat-pump modifications needed to accommodate the instrumentation, and the results of the bench-top check-out; also, the necessary data logging instrumentation, software, and manuals to support the collection and processing of data from the sensors monitoring the gas engine driven heatpump.

6.3 Equipment Specification and Delivery

Based on the description of the existing building and energy systems installation and operating history, provide the necessary drawings, operations and maintenance manuals, specifications, and instructions for installation and commissioning of the 3-ton natural gas engine driven heat pump instrumented under Task 6.2. This will include those items that must be modified on site to accommodate the technology, as well as equipment and accessories that must be delivered. Deliver to the site the 3-ton natural gas engine driven heat pump and any necessary accessories (such as tools, fixtures, and consumables) required to install and commission the technology. Although Federal facility staff are not to be responsible for any service and maintenance they must be provided training to understand the operation and maintenance of the technology. Also provide a baseline operating specification and a statement of technology goals in terms of fuel consumption, reduction, availability and reliability, service and maintenance.

Primary responsibility: GRI and York.

Secondary responsibility: Ft. Sam Houston.

Deliverables: The gas heat pump, drawings, operations and maintenance manuals, specifications, and instructions that will ensure the proper installation and commissioning of the technology; and any accessories necessary to facilitate technology installation and commissioning.

6.4 Technology Monitoring Design and Delivery

Design a monitoring approach for the project based on the description of the homes, the gas heat pump, the installation instructions, the report on the "before" condition of the building, and information that will be needed to evaluate the technology. This will include defining what is to be measured and logged, the method of measurement, the increment at which measurement should be taken, the method of data acquisition and reporting, and the necessary report formats, forms, and log sheets to be used. In addition, provide the equipment needed for baseline monitoring and the corresponding installation, operation, and maintenance instructions. Also develop and define the quality assurance program for the acquisition of the performance and the operations and maintenance data.

Primary responsibility: PNL.

Secondary responsibility: York, GRI, and City Public Service.

Deliverable: A detailed plan for technology monitoring; also, the necessary instrumentation to support the collection of baseline data from the existing HVAC systems.

6.5 Technology and Monitoring Installation

Install the technology and the data acquisition equipment based on the instructions and plan prepared pursuant to Sections 6.3 and 6.4 above. Also conduct testing and field verification work to further establish both the "before" conditions for the test and baseline upon which to technology will be evaluated. Subsequent to installation, commission the technology and the data acquisition equipment and conduct a test to verify that it will properly function; that all necessary data are being obtained and can be secured according to the technology monitoring plan.

Primary responsibility for technology side: York and GRI.

Secondary responsibility for technology side: Ft. Sam Houston.

Primary responsibility for monitoring side: PNL.

Secondary responsibility for monitoring side: City Public Service.

Deliverable: A report documenting the installation process, documenting that the installation is functioning properly, and that it is being properly monitored.

6.6 Technology Decommissioning

To provide for the completion of the test and possible removal or continuation of the operation, a plan for responsibilities under technology and removal scenarios must be prepared. This plan must also include a contingency plan to address the early forced removal of the technology due to failure of the technology or catastrophic events which could adversely impact the specific site or Ft. Sam Houston.

Primary responsibility: PNL.

Secondary responsibility: Ft. Sam Houston.

Deliverable: A plan for unscheduled and scheduled decommissioning of the technology.

7.0 EXECUTION

The execution effort includes those activities necessary to operate, maintain, monitor, and document the performance of the gas heat pump throughout the project and to ensure that information on the progress and results associated with the project is made available to those associated with the project.

7.1 Performance Monitoring and Data Acquisition

Monitor the operation of the gas heat pump and other baseline homes as well as other building and system functions pursuant to Section 6.4.. This includes acquisition of all data (at specified intervals)

that are defined as critical to technology performance monitoring, and conduct of data validation tests to ensure that accurate data are being obtained. Carry out calibration of any automated data acquisition equipment throughout the test, as required. Implement all quality assurance program tasks associated with performance and operations and maintenance data acquisition.

Primary responsibility: PNL.

Secondary responsibility: City Public Service.

Deliverable: Monthly reports on the status of the test and data acquisition effort.

7.2 Operation and Maintenance

Operate and maintain the gas heat pump as defined by the operations and maintenance manual and training provided by the manufacturer, commensurate with the building use, the intended purpose of the gas heat pump, and other requirements of the managers of the facility. Data must be logged with sufficient accuracy to permit detailed cost and reliability analyses to be carried out. This includes maintaining a log of all O&M activities, parts and materials usage and cost, labor cost, and downtime associated with maintenance of the technology.

Primary responsibility: York.

Secondary responsibility: Ft. Sam Houston.

Deliverable: Monthly reports on technology maintenance activities and expenses.

7.3 Data Analysis

Analyze the performance and operation and maintenance data to determine the performance, energy use, operating costs, and life cycle cost, associated with the gas heat pump and other baseline homes, as well as the reliability, safety, and serviceability aspects of the installation.

Primary responsibility: PNL.

Secondary responsibility: City Public Service.

Deliverable: A preliminary report midway through the test period on the results of the data analysis and a final report containing the results of the data analysis for the entire test period.

7.4 Energy Supply

The energy required to operate the gas heat pump must be provided. If the gas heat pump is expected to operate during facility-wide energy supply interruptions, the necessary connection to any stand-by power source or back-up fuel source must be made, maintained, and routinely tested.

Primary responsibility: City Public Service.

Secondary responsibility: Ft. Sam Houston.

Deliverable: Continuous energy supply (including the interconnection to the stand-by power source if required) to the building and its systems so that the technology can perform its intended function.

8.0 DOCUMENTATION

Documentation includes those efforts necessary to record the project activities, evaluate the project, determine the level of success of the project, and present the results of the project.

8.1 Preparation of Test Bed Report

The data acquired pursuant to Section 7.1 and 7.2 and the analysis conducted on the data pursuant to Section 7.3 will make it possible to report on the results of the gas heat pump installation. Prepare a report detailing if and to what degree the 3-ton natural gas engine driven heat pump will benefit the Federal sector. In preparing this report the information obtained in Section 6.1 to describe the "before" condition of the building and the data acquired pursuant to the test of the baseline homes and new technology must be used. This must include performance, energy use, operating costs, maintenance costs, reliability, quality of service, and other factors considered important for evaluation.

Primary responsibility: PNL.

Secondary responsibility: City Public Service, GRI, York, and Ft. Sam Houston.

Deliverable: A detailed report that contains the results of the data acquisition and analysis effort, the expected benefits of the gas heat pump in the Federal sector, a description of any necessary improvements required in the gas heat pump before its widespread deployment in the Federal sector, and a description of any factors limiting deployment.

8.2 Development of Project Presentation and Media

Commensurate with the success of the project, develop necessary materials to communicate the results of the project and identify those in the Federal sector, policy makers, utilities, and others involved in impacting technology use in the Federal sector. In addition, identify the most effective media for making these materials and the results of the project available. This could include a press release, video, printed matter, conference, or workshop.

Primary responsibility: PNL.

Secondary responsibility: AGCC, York, and GRI.

Deliverable: A communication package on the results of the project targeted to different key audiences.

8.3 Implementation of Presentation

Implement the most beneficial presentation through the most effective media based on the efforts of Section 8.2. The purpose of this presentation will be to communicate the results of the project to those in the Federal sector who could specify increased use of the gas heat pump in the Federal sector and who would support the test bed concept. In addition communication must also focus on those in the private sector who would advocate the use of the gas heat pump and the test bed concept.

Primary responsibility: AGCC and GRI.

Secondary responsibility: York, City Public Service, Ft. Sam Houston, and PNL.

Deliverable: A copy of the presentation and a report on its implementation, distribution, and reception.

9.0 DECOMMISSIONING

The decommissioning effort includes those activities necessary to remove the technology (if it is determined that it is to be removed) as well as the monitoring equipment.

9.1 Technology Removal

If it is determined that the technology is to be removed pursuant to the plan developed under Section 6.6, or due to a failure in the technology, the building is to be returned to its previous condition or to some other condition agreed upon in advance by the Ft. Sam Houston, York, and GRI. The equipment that was installed to monitor the technology installation and any accessory equipment associated with the monitoring installation must also be removed.

Primary responsibility for equipment: York and GRI.

Secondary responsibility for equipment: Ft. Sam Houston.

Primary responsibility for monitoring: PNL.

Secondary responsibility for monitoring: City Public Service.

Deliverable: A report on the disposition of the technology and the monitoring equipment, and the return of the installation to the Federal site in an acceptable manner.

10.0 PROJECT SCHEDULE AND RESPONSIBILITIES

The following schedule shows each of the tasks in Sections 6.0 through 9.0 and the starting point, ending point, and duration of each task. Timelines are shown for years 1993 through 1995.

Appendix B

Instrumentation Details for Gas Heat Pump Monitoring

Appendix B

Instrumentation Details for Gas Heat Pump Monitoring

This appendix contains documentation on the data acquisition system (DAS) used in monitoring the Triathlon GHP. This documentation was provided to PNL by Battelle Columbus Laboratory in Ohio. As a subcontractor to the Gas Research Institute, Battelle had the role of installing the monitoring instrumentation on the GHP and collecting the data from this DAS. The following are pages from original documents produced by Battelle-Columbus.

ATTACHMENT 1

Triathlon CRADA Unit DAS: Installation, Calibration, and Data Format

DAS Installation

The York Triathlon unit was instrumented using instrumentation provided from the York 10-unit field test. Several minor modifications were made to accommodate changes in the hardware and system configuration. Complete documentation on the configuration and wiring of the DAS is attached.

Checkout

The DAS instrumentation was fully checked out by operating the unit in the laboratory. All sensor inputs and wiring were confirmed to be operational. The DAS cable design permits the instrumentation to be easily reconnected after shipping to the test site.

Calibrations

All preliminary calibrations to individual sensors and to instrumentation subsystems were performed at Battelle. All calibrations performed at Battelle's instrument lab are against NIST traceable standards. These calibrations include:

- Gas meter calibration in Battelle's Instrument Lab
- Suction and Discharge pressure transducer calibration in Battelle's Instrument Lab
- Barometric pressure transducer calibration in Battelle's Instrument Lab
- Calibration of the Metrabyte A/D board
- Calibration of the engine speed signal
- Initial calibration of the RTD current supply boards
- Trial calibration of the indirect indoor airflow measurement methods

Remaining calibrations performed upon installation at the test site include:

- Final calibration of the RTD current supply boards
- Calibration of the thermocouple cold junction compensation
- System capacity calibration of the airflow measurement using the electric resistance heat injection method developed during the original 10-unit field test

Data Reporting

Data collected during the York Triathlon field test will be analyzed and reported in several different manners. Daily graphs of GHP operation are performed with CGHP, a custom graphic and data display utility which has proven to be a useful tool in quickly visualizing single-day operation of the GHP. It also has been very useful in diagnosing operational problems with the GHP. A sample CGHP graph from the York 10-unit field test is shown in Figure 1. The CGHP utility has been provided to Jim Miller and PNL.

Performance data are reduced in several steps and loaded into a database. This data base is then queried to generate a periodic performance report. The periodic performance report will be issued on a monthly basis along with the monthly report. A sample periodic performance report is shown in Figure 2.

OUTDOOR UNIT

York Triathlon Cra
Showing DA

INDOOR UNIT

Indoor Unit System Schematic
Sensor Locations

Desig.	Measured Parameter	Units	Range	Device
RTD1-00	RTD Cal Channel 1			
RTD1-01	ID Coil Return Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-02	ID Coil Return Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-03	ID Coil Return Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-04	ID Coil Return Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-05	ID Coil Intermediate Air T	F	0 - 0.1 V	100 Ohm RTD
RTD1-06	ID Coil Intermediate Air T	F	0 - 0.1 V	100 Ohm RTD
RTD1-07	ID Coil Supply Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-08	ID Coil Supply Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-09	ID Coil Supply Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-10	ID Coil Supply Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-11	ID Coil Supply Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-12	ID Coil Supply Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-13	ID Coil Supply Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-14	ID Coil Supply Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD1-15	ID Coil Supply Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD2-00	RTD Cal Channel 2			
RTD2-01	Outdoor Temperature	F	0 - 0.1 V	100 Ohm RTD
RTD2-02	Outdoor Temperature	F	0 - 0.1 V	100 Ohm RTD
RTD2-03	Outdoor Temperature	F	0 - 0.1 V	100 Ohm RTD
RTD2-04	OD Coil Air Outlet Temp	F	0 - 0.1 V	100 Ohm RTD
RTD2-05	OD Coil Air Outlet Temp	F	0 - 0.1 V	100 Ohm RTD
RTD2-06	Thermostat Wall Temp	F	0 - 0.1 V	100 Ohm RTD
RTD2-07	Thermostat Wall Temp	F	0 - 0.1 V	100 Ohm RTD
RTD2-08	Room Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD2-09	Room Air Temp	F	0 - 0.1 V	100 Ohm RTD
RTD2-10	Natural Gas Temp	F	0 - 0.1 V	100 Ohm RTD
RTD2-14	ID Power Consumption	Watts	0 - 0.1 V	0 - 1 KW OS W10B
RTD2-15	OD Power Consumption	Watts	0 - 0.1 V	0 - 1 KW OS W10B
TC6-00	Thermocouple Compensation			
TC3-01	ID Coil Liquid Line Temp	F	Millivolts	Type K Thermocoup
TC3-02	ID Coil Mid Temp	F	Millivolts	Type K Thermocoup
TC3-03	ID Coil Mid Temp	F	Millivolts	Type K Thermocoup
TC3-04	ID Coil Vapor Line Temp	F	Millivolts	Type K Thermocoup
TC3-05	ID Coolant Inlet Temp	F	Millivolts	Type K Thermocoup
TC3-06	ID Coolant Outlet Temp	F	Millivolts	Type K Thermocoup
TC3-07	OD Coil Liquid Line Temp	F	Millivolts	Type K Thermocoup
TC3-08	OD Coil Mid Temp	F	Millivolts	Type K Thermocoup
TC3-09	OD Coil Mid Temp	F	Millivolts	Type K Thermocoup
TC3-10	OD Coil Vapor Line Temp	F	Millivolts	Type K Thermocoup
TC3-11	Engine Compartment Temp	F	Millivolts	Type K Thermocoup
TC3-12	Engine Oil Temp	F	Millivolts	Type K Thermocoup
TC3-13	Compressor Seal Temp	F	Millivolts	Type K Thermocoup
TC3-14	Pre Accum. Suction Temp	F	Millivolts	Type K Thermocoup
TC3-15	Compressor Suction Temp	F	Millivolts	Type K Thermocoup

TC7-00	Thermocouple Compensation			
TC4-01	Compressor Dischg Temp	F	Millivolts	Type K Thermocoup
TC4-02	Coolant Temp into Engine	F	Millivolts	Type K Thermocoup
TC4-03	Coolant Temp into Aux Heat	F	Millivolts	Type K Thermocoup
TC4-04	Coolant Temp out of Aux He	F	Millivolts	Type K Thermocoup
TC4-05	Coolant Temp into Radiator	F	Millivolts	Type K Thermocoup
TC4-06	Coolant Temp out of Radiat	F	Millivolts	Type K Thermocoup
TC4-07	Coolant Temp out of Engine	F	Millivolts	Type K Thermocoup
TC4-08	Coolant Temp Warm-up Loop	F	Millivolts	Type K Thermocoup
TC4-09	Coolant Temp @ Check Valve	F	Millivolts	Type K Thermocoup
TC4-10	Coolant Temp Rtn to Tstat	F	Millivolts	Type K Thermocoup
TC4-11	Encl Temp in Control Tray	F	Millivolts	Type K Thermocoup
=====				
VO-00	Compressor Suction Press	Psis	1 - 6 VDC	Data Inst. SA500
VO-01	Compressor Dischg Press	Psis	1 - 6 VDC	Data Inst. SA500
VO-02	Oil Lubricant Press	Psis	1 - 6 VDC	Data Inst. SA100
VO-03	Barometric Press	Psia	1 - 6 VDC	Data Inst. XT15
VO-04	Commanded Engine Speed	RPM	1 - 2 VDC	From W7505
VO-05	Indoor Relative Humidity	%	0 - 5 VDC	Valasia RH Meter
VO-06	ID Relative Humidity Temp	F	0 - 5 VDC	Valasia RH Meter
VO-07	Outdoor Relative Humidity	%	0 - 5 VDC	Valasia RH Meter
VO-08	OD Relative Humidity Temp	F	0 - 5 VDC	Valasia RH Meter
VO-09	Indoor Airflow	CFM	0 - 5 VDC	FMT Air Flow
VO-10				
VO-11	Actual Engine Speed	RPM	0 - 5 VDC	From Microtach
VO-12	Reversing Valve State	Heat/Cool	0 - 5 VDC	From 24 VAC Sig
VO-13	Coolant Valve State	On-Off	0 - 5 VDC	From 24 VAC Sig
VO-14	Auxiliary Heater Gas Valve	On-Off	0 - 5 VDC	From 24 VAC Sig
VO-15				
=====				
DB0-0	Natural Gas Consumption	CFH	Pulse 0-5	Rockwell as modif
DB0-1	Indoor Blower Wheel Speed	RPM	Pulse 0-5	BAE Hall Sensor
DB0-2	Latent Capacity	Btu/Hr	Pulse, clo	Belfort Model 30
DB0-3	ID Elect Consump.	W-Hr	Pulse, clo	Ohio Semitronics
DB0-4	OD Elect Consump.	W-Hr	Pulse, clo	Ohio Semitronics
=====				

York Gas Heat Pump Field Test **Data Acquisition System (DAS)**

The data acquisition system (DAS) at each of the York GHP field test sites was designed, built, and maintained by Battelle and developed specifically to meet the needs of this test program. Many of the components and the history of the software date back to prior field testing of residential gas heat pumps. The current DAS was adapted and developed for use with an early GHP field experiment^(2,3) and then further expanded to meet the requirements of the ten-unit York GHP field test. The DAS logged and displayed data on a continuous basis. Remote access to the DAS could be made via a modem allowing current or logged heat pump operations to be reviewed. The DAS proved to be highly effective at providing reliable and accurate performance data as well as detailed information on the heat pump for characterization and troubleshooting of problems.

Components

The main components of the DAS were the DAS enclosure, the sensors, and the IBM PC-XT. The sensors and the computer were linked to the DAS with shielded cables to reduce electromagnetic interference. The DAS enclosure regulated the sensor power, conditioned the sensor outputs, and then linked these outputs to the computer.

Quality Assurance

Battelle's Instrument Laboratory (BIL) verified the proper operation of sensors critical to heat pump performance monitoring; in addition, BIL calibrated all critical instruments traceable to the National Bureau of Standards (NBS). Throughout testing, instrumentation was continuously monitored by Battelle staff for drift and inaccuracies. In addition to the component-level calibration performed by BIL, Battelle field service engineers and technicians conducted system-level calibration and verification at the specific field sites.

DAS Hardware

Sensors

The DAS sensors monitored conditions of the indoor and outdoor units as well as ambient conditions at the site. A listing of the sensors and their designations is shown in Table I-3. Figure I-5 shows a schematic of the field test GHP and sensor locations.

Resistance Temperature Devices (RTDs) and Thermocouples (TCs)

Temperatures were monitored at 48 locations by use of 100 ohm resistance temperature devices (RTDs) and type K duplex wired thermocouples (TCs). Grids of RTDs were used to measure the temperature rise or drop across the indoor unit. Multipoint measurements significantly improved the measurement accuracy and averaged where the air temperature was nonuniform. This method also allowed redundancy should a sensor fail. Individual measurements were automatically excluded from the grid average if they fell outside of an acceptable range. Four measurement points were used for the return air temperature and nine for the supply. Two RTDs were used between the refrigeration and coolant heat exchanger to determine the relative contribution of these coils.

The air outlet temperature of the heat pump outdoor coil was measured by a grid of three RTDs mounted on each coil face of the outdoor coil. The air outlet temperature of the outdoor coil was measured by two RTDs mounted on the coil face of the heat pump by the outdoor fan exhaust. These measurements indicated the air temperature as seen by the heat pump and might have exhibited recirculation effects as a result of hot soak and solar effects due to the heat pump's location. Attempts were made to minimize these effects; however, this measurement might not represent the actual outdoor temperatures when the outdoor fan is off.

The indoor coil supply air temperature (supplied to the house) was measured at the exit of the indoor unit by a grid of nine RTDs. Intermediate temperatures were measured within the indoor unit by two RTDs located between the indoor fan and the indoor coil. The indoor return (return from the house) was measured by four RTDs located at the entrance of the indoor unit underneath the indoor coil.

The room temperature and thermostat temperature were measured by four RTDs located within the thermostat at the site. Natural gas temperature was measured by one RTD. The natural gas temperature and pressure were used to determine the density of the natural gas supplied to the heat pump.

The critical components and systems of the GHP (e.g., coolant loop, engine, refrigerant circuit, etc.) were heavily instrumented with thermocouples, primarily for diagnostic purposes.

Barometric and System Pressures

Data Instrument type SA R0-200, SA R0-500, and SA R0-100 sensors were used to monitor the compressor suction, the compressor discharge, and the engine oil lubricant pressure respectively. The aforementioned pressure readings were oversampled to average out fluctuations due to compressor pulsations. Barometric pressure at the site was monitored by use of a Data Instruments XT15 sensor to correct for airflow measurements and to determine the natural gas line pressure. No pressure sensor failures were experienced with over 1×10^9 cycles per sensor per site.

Humidity and Temperature Transmitter

Two Vaisala series HMD 30YB Humidity and Temperature Transmitters were employed to monitor temperature and humidity within the plenum on the indoor unit and the ambient conditions in the vicinity of the outdoor unit. The maximum humidity uncertainty for the Vaisala sensor was ± 3 percent RH within the 90 to 100 percent RH range and ± 2 percent RH in the 0 to 90 percent RH range. The output uncertainty for temperature on the Vaisala sensor was ± 0.2 C. The outdoor humidity sensor was protected with a solar and weather shield. The indoor humidity sensor, located in the plenum, measured relative humidity with respect to the return air temperature to the indoor unit. The return air temperature at most sites was less than the temperature in the living space, and since the water content was relatively constant, the relative humidity in the living space was less than the humidity of the return air at the indoor unit.

Humidity measurements greater than the living space conditions were frequently measured when the indoor blower was shut off after the GHP had been in the cooling mode. These higher humidity measurements were due to the evaporation of condensate from the indoor coil and the condensate tray.

Electronic Airflow Measurement System and the Indirect Airflow Measurement Method

Initially only an Ebtron Model 400 hot wire airflow sensor was used for measuring airflow inside the return air duct. As testing progressed a noticeable drift over time became apparent at both high and low flow conditions; hence a second method of monitoring airflow was developed. The second method, referred to as the indirect method, used a detailed blower map to determine airflow from the blower wheel speed and power consumption. A detailed description of the development and application of this method is described in Reference 4.

Engine RPM

The DAS measured the actual engine speed by monitoring the engine control system (ECS-3). The ECS-3 output a pulse width modulation (PWM) signal which was converted to a 0 to 5 VDC signal corresponding to the engine speed. This signal was calibrated on-site with a digital tachometer. A polynomial was generated for voltage versus engine rpm and was incorporated into the DAS program which displayed and recorded engine speed in rpm.

Natural Gas Meter

The natural gas consumption of the heat pump was monitored by use of a Battelle modified Rockwell gas meter. The Battelle modification consisted of replacing the Rockwell gas meter top plate with a plate housing a Hall-effect sensor and substituting a linkage with a magnet for the existing coupling link. The Hall-effect sensor provided a pulse output for each 1/8 cubic foot of gas consumed. The digital signal was read by the Counter Debounce board and was summed by the software for display and logging.

Tipping Bucket

Latent capacity of the heat pump was recorded by use of a modified Belfort Model 302B Rain Gauge Assembly. The unit metered the condensate draining from the indoor coil. A reed switch was used to produce a pulse output for each tip of the instrument. The unit capacity was calibrated at Battelle's Instrument Lab and each tip of the bucket was incremented as a unit of latent heat. Measurement of latent capacity using a positive displacement device such as the tipping bucket insured accuracy and long-term stability of the measurement. There was, however, a finite amount of time lag between formation of condensate and actual measurement. This time delay could vary from 15 minutes to over an hour under worst-case conditions. For this reason, the instantaneous cooling capacity could be slightly inaccurate; however, the long-term (> 1 hour) averages were representative.

Electronic Watt Watt-Hour Transducer

Indoor and outdoor electric power consumptions were monitored by use of Ohio Semitronic Series W10B Watt Watt-Hour Transducers. Pulse outputs were generated by these devices for recording the cumulative energy use. An analog signal output from the meter was also used for instantaneous power measurement.

DAS Enclosure

Internal to the DAS enclosure were control boards which acted as an interface for the computer and the sensors. The boards also regulated the sensors' output power and filtered the input signals from the sensors. The DAS housed five general purpose MetraByte EXP-16 multiplexer boards, a custom Counter Debounce board, a custom engine sensor interface board, and an OPTO 22 Input Module. The DAS enclosure also provided 15 VDC and 24 VDC regulated power for the boards and sensors. The DAS enclosure was prewired and used a number of plug-in type connectors, which significantly improves ease of installation, removal, and calibration.

MetraByte EXP-16 Boards

The DAS enclosure contained five EXP-16 boards which multiplex the analog inputs to the single 16-channel analog to digital (A/D) board. The V0 board was one of the MetraByte EXP-16 boards which served as a high level analog input board. Sixteen signals such as the engine rpm, valve states, pressure readings, and airflow were relayed from the sensors to the computer via this board. Two of the MetraByte EXP-16 boards were used for signal conditioning the RTDs. A custom current supply board was used to regulate the current supplies for the RTDs. The last two MetraByte EXP-16 boards (TC3 and TC4) were used for inputs from the thermocouples.

Debounce Board (DBO)

The Debounce Board (DBO) debounced noisy pulse inputs from switch closure type devices. The board has five channels which were dedicated to counting signals from the gas meter, the indoor

blower, the tipping bucket, the indoor electric watt-hour meter, and the outdoor electric watt-hour meter. Digital signals from the sensors were conditioned for the counter/timer input.

OPTO 22 Input Module (OPTO 22)

The OPTO 22 Input Module (OPTO 22) served as an optically coupled interface module. Valve status was monitored as a 24 VAC signal from the GHP control system. The OPTO 22 converted the 0 to 24 VDC signal to a 0 to 5 VDC signal which could be read by the V0 board.

Engine Sensor Interface Board (RB)

The RB board powered the engine hour meter, the barometric pressure transducer, and the OPTO 22 board. The RB board also conditioned the pulse width modulation (PWM) output from the ECS-3 and produced a 0 to 5 VDC analog output for engine rpm.

IBM PC-XT and the Gas Heat Pump DAS Monitoring Program

The DAS made use of an IBM PC-XT equipped with a modem, a MetraByte CTM-05 multifunction counter/timer, and a MetraByte DAS-8 analog to digital input board. The monitoring software for the heat pump DAS was written in MicroSoft Quick Basic and was custom developed for this field testing program. The program continuously sampled all analog inputs from the DAS up to 20 times a second. The samples were used to update the display every 5 seconds. Samples that were displayed are shown in Figures I-6 through I-9. The data were logged to disk approximately every 10 to 15 minutes depending on the mode of the system. During standby modes the interval was increased to 30 minutes to minimize the size of the data files. At any point should the GHP change modes the program averaged the data taken during the elapsed period and recorded it.

A Practical Peripherals 2400 Baud modem was installed in the computer at each of the sites. This allowed authorized personnel to remotely access the site information for troubleshooting and data retrieval. Access was linked via the commercial communications software, Carbon Copy. During a link session the local computer could display the current screen at the site. Display screens could be changed at the site through the remote link. The communication link served as a means to upload or download files to or from the site. SAIC also used the communication link for daily retrieval of the GHP performance data.

Operating Mode

To determine the operating mode of the heat pump, the DAS monitors the status of the system. The mode depends upon the status of the engine, indoor blower, coolant valve, reversing valve, auxiliary heater, and the W7505 Controller advisory signal. Solenoid valves are used to control the flow of coolant and refrigerant within the heat pump. Voltage at the solenoids controlling these valves is used

to determine valve control system status. Table I-4 lists the conditions used to determine the GHP modes in the DAS program. Table I-4 also shows the predominant operating modes of the GHP.

GEHP Data Acquisition PC Screen 1

```

Screen 1      - Battelle CP5L Field Test at Y08.Atlanta -      v.Y08-0701
Count: 24     Mode: 5     Cooling Mode                        14:51:02  07-31-91

ID-Coil DBT In:      79.0 °F          OD-Coil DBT In:      79.6 °F
ID-Coil DBT Out:     59.7 °F          OD-Coil DBT Out:     90.9 °F
ID Humidity:         59.2 %           Gas Use Rate:       14.337 SCFt/Hr
                                           Counter              9
ID-Coil Air Flow:    596 SCFM          Gas Use:            1.132 SCFt
                                           Correction Factor    1.000
Refrig Sens. Q:      -13101 Btu/Hr
Coolant Sens. Q:      617 Btu/Hr       Suction Pressure:   68.4 Psig
Total Sens. Q:        -12484 Btu/Hr    Disch. Pressure:    167.9 Psig
Latent Q:             -6625 Btu/Hr      Engine Speed:       1247 RPM
Total Q:              -19109 Btu/Hr     Elec Consumption:   262 Watts

Gas Consumption:     14710 Btu/Hr

F1Screen1  F2Screen2  F3Screen3  F4Screen4  F9Shell  F10Quit

```

FIGURE I-6. GHP DATA ACQUISITION PC SCREEN 1

GEHP Data Acquisition PC Screen 4

```

Screen 4      - Battelle CP5L Field Test at Y08.Atlanta -      v.Y08-0701
Count: 38     Mode: 5     Cooling Mode                        14:52:15  07-31-91

*** V0 ***
00 Comp Suct Press    67.8 Psig
01 Comp Dischg Press  168.7 Psig
02 Oil Lub Press      50.7 Psig
03 Bar Press          13.85 Psia
04 Command Eng Spd    1187 RPM

05 ID Rel Hum         59.3 %
06 ID Rel Hum Temp    71.6 °F
07 OD Rel Hum         81.1 %
08 OD Rel Hum Temp    79.8 °F
09 ID Airflow         715.0 CFM
10 ID Return Temp     0 °F

11 Actual Eng Speed    1247 RPM
12 Reversing Valve State 5
13 Coolant Valve State 5
14 Aux Heater Gas Valve 0
15 Advisory Status     0

*** DB0 ***
0 Nat Gas Consump      1 1/8 CuFt
1 Site Nat Gas Consump 0 CuFt
2 Latent Capacity      1 7.95 cc
3 ID Elec Consump      0 W-Hr
4 OD Elec Consump      1 W-Hr

*** Misc Inputs ***
ID Power Consump       52 Watts
OD Power Consump      217 Watts
ID Blower Speed        600 RPM
Indoor Airflow Est     598 SCFM

F1Screen1  F2Screen2  F3Screen3  F4Screen4  F9Shell  F10Quit

```

FIGURE I-7. GHP DATA ACQUISITION PC SCREEN 2

GEHP Data Acquisition PC Screen 2

Screen 2 - Battelle CP5L Field Test at Y08.Atlanta - V.Y08-0701
 Count: 32 Mode: 5 Cooling Mode 14:51:42 08-31-91

*** RTD1 ***		*** RTD2 ***	
00	RTD Cal Channel 1	00	RTD Cal Channel 2
01	ID Coil Retn Air Temp 71.2 °F	01	OD Temp 80.0 °F
02	ID Coil Retn Air Temp 71.6 °F	02	OD Temp 80.0 °F
03	ID Coil Retn Air Temp 71.2 °F	03	OD Temp 79.7 °F
04	ID Coil Retn Air Temp 71.4 °F		
05	ID Coil Int Air Temp 50.8 °F	04	OD Coil Air Outl Temp 94.0 °F
06	ID Coil Int Air Temp 51.2 °F	05	OD Coil Air Outl Temp 89.1 °F
		06	Thermostat Wall Temp 74.9 °F
07	ID Coil Sup Air Temp 52.5 °F	07	Thermostat Wall Temp 74.9 °F
08	ID Coil Sup Air Temp 47.1 °F		
09	ID Coil Sup Air Temp 54.1 °F	08	Room Air Temp 72.8 °F
10	ID Coil Sup Air Temp 50.2 °F	09	Room Air Temp 73.4 °F
11	ID Coil Sup Air Temp 53.0 °F		
12	ID Coil Sup Air Temp 51.8 °F	10	Nat Gas Temp 68.3 °F
13	ID Coil Sup Air Temp 51.9 °F		
14	ID Coil Sup Air Temp 51.3 °F		
15	ID Coil Sup Air Temp 55.7 °F		

F1Screen 1 F2Screen 2 F3Screen 3 F4Screen 4 F9Shell F10Quit

FIGURE I-8. GHP DATA ACQUISITION PC SCREEN 3

GEHP Data Acquisition PC Screen 3

Screen 3 - Battelle CP5L Field Test at Y08.Atlanta - V.Y08-0701
 Count: 35 Mode: 5 Cooling Mode 14:51:57 07-31-91

*** TC3 ***		*** TC4 ***	
00	TC CJ Compensation 79.6 °F	00	TC CJ Compensation 79.7 °F
01	ID Coil Liq Line Temp 82.9 °F	01	Comp Dischg Temp 156.5 °F
02	ID Coil Mid Temp 41.6 °F	02	Cool Temp Into Eng 167.2 °F
03	ID Coil Mid Temp 42.1 °F	03	Cool Temp Into Aux Heat 78.5 °F
04	ID Coil Vapor Line Temp 54.2 °F	04	Cool Temp Out Aux Heat 77.4 °F
05	ID Coolant Inlet Temp 64.9 °F		
06	ID Coolant Outlet Temp 62.7 °F	05	Cool Temp Into Rad 166.7 °F
		06	Cool Temp Out Rad 98.4 °F
07	OD Coil Liq Line Temp 81.2 °F	07	Cool Temp Out Eng 169.9 °F
08	OD Coil Mid Temp 95.6 °F		
09	OD Coil Mid Temp 96.2 °F	08	Water Tmp In DHW Coil 66.7 °F
10	OD Coil Vapor Line Temp 63.8 °F	09	Water Tmp Out DHW Coil 61.1 °F
		10	DHW Tank Temp 142.5 °F
11	Eng Compartment Temp 136.0 °F		
12	Eng Oil Temp 157.0 °F		
13	Comp Seal Temp 122.4 °F		
14	Pre Accum Suct Temp 66.6 °F		
15	Comp Suction Temp 73.9 °F		

F1Screen 1 F2Screen 2 F3Screen 3 F4Screen 4 F9Shell F10Quit

FIGURE I-9. GHP DATA ACQUISITION PC SCREEN 4

TABLE I-4. GHP MODES AND SYSTEM STATES

MODE	DISPLAY	ADVIS STATE	REV VALVE	AUX HTR	ENG STAT	BLWR STATE	COOL VALVE
0	Standby	off	on	on/off	off	on/off	on/off
0	Standby (Fan On, Cool)	off	on	on/off	off	on	on/off
0	Standby (Fan On, Heat)	off	off	off	off	on	on/off
1	Heating (Eng Only)	off	off	off	on	on/off	on/off
2	Heating (Eng & Aux Htr)	off	off	on	on	on/off	on/off
3	Heating (Aux Htr Only)	off	off	on	off	on/off	on/off
4	ID Fan Overrun (Heat)	off	off	off	off	on	on/off
4	ID Fan Overrun (Cool)	off	on	on/off	off	on	on/off
5	Cooling Mode	off	on	on/off	on	on/off	on
6	Defrost (Eng Only)	off	on	off	on	on/off	on/off
7	Defrost (Eng & Aux Htr)	off	on	on	on	on/off	on/off
8	Engine Down - Advisory	on	on/off	on/off	off	on/off	on/off

Appendix C

Performance Check by Computer Simulation

Appendix C

Performance Check by Computer Simulation

The documentation in this appendix was provided to PNL by Battelle-Columbus. Battelle served as a subcontractor to the Gas Research Institute and had the role of installing the monitoring instrumentation on the GHP and collecting the data from that system. The following are pages from original documents produced by Battelle.

Attachment 2. Performance Check of the San Antonio Triathlon GHP

	Measured Performance	Model Est. Performance	Difference
Date	8/20/94		
Time	10:58:08 - 11:58:21		
Unit operating at steady state conditions for 2 hours prior to sample period			
Sample Period	60.22 min		
Outdoor Amb. Temp	94.8 #F	Input	
Outdoor Amb. RH	32.6 %	Input	
Indoor Return Temp	74.2 #F	Input	
Indoor Return RH	50.5 %	Input	
Indoor Supply Temp	57.9 #F	56.2 #F	1.7 #F
Engine Speed	2999 RPM	Input	
Indoor Airflow	1257 SCFM	Input	
Compressor Superheat	28 #F	Input	
Suction Temp	59.4 #F	64.4 #F	5.0 #F
Suction Pressure	57 psig	63 psig	6 psi
Discharge Temp	185.0 #F	208.4 #F	23.4 #F
Discharge Pressure	236 psig	233 psig	3 psi
Indoor Power	549 Watts		
Outdoor Power	212 Watts		
Capacity, Sensible	21,996 Btu/Hr	24,720 Btu/Hr	11.0 %
Capacity, Latent	8,491 Btu/Hr	7,800 Btu/Hr	8.9 %
Capacity, Total	30,487 Btu/Hr	32,520 Btu/Hr	6.3 %
Gas Use	42,005 Btu/Hr	39,530 Btu/Hr	6.3 %
Gas COP	0.73	0.82	11.8 %

Attachment 2. Performance Check of the San Antonio Triathlon GHP (Continued)

	Measured Performance	Model Est. Performance	Difference
Date	8/20/94		
Time	16:42:27 - 17:42:40		
Unit operating at steady state conditions for 6 hours prior to sample period			
Sample Period	60.22 min		
Outdoor Amb. Temp	95.0 #F	Input	
Outdoor Amb. RH	24.5 %	Input	
Indoor Return Temp	74.8 #F	Input	
Indoor Return RH	44.9 %	Input	
Indoor Supply Temp	57.6 #F	56.1 #F	1.5 #F
Engine Speed	1207 RPM	Input	
Indoor Airflow	735 SCFM	Input	
Compressor Superheat	28.4 #F	Input	
Suction Temp	68.9 #F	72.2 #F	3.3 #F
Suction Pressure	69 psig	74 psig	5 psi
Discharge Temp	164.1 #F	185.6 #F	21.5 #F
Discharge Pressure	210 psig	213 psig	3 psi
Indoor Power	121 Watts		
Outdoor Power	212 Watts		
Capacity, Sensible	13,584 Btu/Hr	14,890 Btu/Hr	8.8 %
Capacity, Latent	3,432 Btu/Hr	2,030 Btu/Hr	69.1 %
Capacity, Total	17,016 Btu/Hr	16,920 Btu/Hr	0.6 %
Gas Use	16,014 Btu/Hr	15,590 Btu/Hr	2.7 %
Gas COP	1.063	1.085	2.0 %

Appendix D

Additional Field Data on Triathlon

Appendix D

Additional Field Data on Triathlon

This appendix contains field data provided by Battelle-Columbus. Battelle served as a subcontractor to the Gas Research Institute and had the role of installing the monitoring instrumentation on the GHP and collecting the data from that system. The following are pages from original documents produced by Battelle.

Revised Periodic Performance Report
for San Antonio Triathlon Test Site

	Reporting Period from 11/01/94 thru 11/30/94	Cumulative from 06/17/94 thru 11/30/94
Total time [Hrs] =	720.0	4008.0
Data time [Hrs] =	714.2 (99.2 %)	3991.5 (99.6 %)
Engine time [Hrs] =	151.0 (21.1 %)	1840.0 (46.1 %)
Availability =	100.0 %	100.0 %
Engine Cycles =	481	2505
Defrost Cycles =	0	0
Auxiliary Heater Cycles =	1	1
Average Outdoor Temp [F] =	63.9	76.2
Minimum Outdoor Temp [F] =	44.6 (11/30/94)	44.6 (11/30/94)
Maximum Outdoor Temp [F] =	84.0 (11/03/94)	97.8 (06/25/94)
Peak Cooling Day [KBtu] =	-192.1 (11/04/94)	-465.5 (07/10/94)
Peak Heating Day [KBtu] =	314.3 (11/24/94)	314.3 (11/24/94)
Cooling Performance (Modes 4,5):		
Cooling Engine Op. [Hrs] =	50.1	1729.1
Electricity Use [KWHr] =	14.7	627.5
Sensible Capacity [KBtu] =	-622.0	-26316.3
Latent Capacity [KBtu] =	-234.5	-8110.9
Total Cooling Cap. [KBtu] =	-856.5	-34427.2
Gas Use [KBtu] =	783.4	30510.5
Thermal COP =	1.093 (73.7 F)	1.128 (83.4 F)
EER Equiv. 1994 Natl Avg =	12.1 (73.7 F)	12.2 (83.4 F)
Cooling Operating Cost =	\$ 3.88	\$ 163.80
Heating Performance, Engine Only (Modes 1,4,6,7):		
Heating Engine Op. [Hrs] =	100.8	110.9
Electricity Use [KWHr] =	31.5	34.5
Refrig. Capacity [KBtu] =	1937.0	2125.3
Coolant Capacity [KBtu] =	361.4	373.9
Total Heating Cap. [KBtu] =	2298.4	2499.2
Gas Use [KBtu] =	1793.6	1968.8
Thermal COP =	1.281 (54.5 F)	1.269 (54.8 F)
Heating Performance, Overall (Modes 1-4,6,7):		
Heating Eng+Aux Op. [Hrs] =	100.9	111.0
Electricity Use [KWHr] =	31.6	34.6
Refrig. Capacity [KBtu] =	1938.8	2127.1
Coolant Capacity [KBtu] =	363.4	375.9
Total Heating Cap. [KBtu] =	2302.2	2503.0
Gas Use [KBtu] =	1800.3	1975.5
Thermal COP =	1.279 (54.5 F)	1.267 (54.8 F)
HPF Equiv. 1994 Natl Avg =	14.3 (54.5 F)	14.2 (54.8 F)
Heating Operating Cost =	\$ 8.81	\$ 9.62
Total Operating Cost =	\$ 12.69	\$ 173.42
City Public Serv. Avg. Rates: Gas = \$ 4.1578/MBtu, Electric = \$0.05791/KWh		

yt940710.dat

San Antonio Triathlon GHP

Thermostat Cycle Rate, Cooling 1994

Daily Cooling Operation History, 1994

San Antonio Triathlon GHP

Daily Cooling Operation History, 1994

■ Daily Gas Use	+ Daily Sens. Cooling	* Daily Lat. Cooling
▲ Daily Total Cooling	× Daily Power Use	

San Antonio Triathlon GHP

Daily Cooling Operation History, 1994

San Antonio Triathlon GHP

Daily Cooling Operation History, 1994

▲ Indoor Rel. Hum. + Supply Temperature

Daily summary file - San Antonio Crada Site

Site	Date	Total Time	Total Data	Total Eng	Total Adv	F C	---Cycles--	Min	Avg	Max	-----Cooling-----												
								OO	OO	OO	Cool	Eng	Air	OO	ID	ID	Daily	Daily	Daily	Daily	Daily	Daily	Daily
YY	MM/DD/YY	[Hrs]	[Hrs]	[Hrs]	[Hrs]	O F	Eng Def Aux	THum	THum	THum	Time	Speed	Flow	Temp	RelHm	Supply	SenCap	LatCap	Elect	Gas	TCOP	TCOP	TCOP
								[F]	[F]	[F]	[Hrs]	[RPM]	[SCFM]	[F]	[X]	[F]	[KBTu]	[KBTu]	[KWHr]	[KBTu]	[KBTu]	[KBTu]	[KBTu]
yt	06/17/94	24.00	23.283	15.471	0.000	0 0	25 0 0	75.0	83.3	94.8	15.471	1313	728	84.3	53.5	57.3	-212.9	-72.5	5.0	261.4	-1.092		
yt	06/18/94	24.00	24.000	13.301	0.000	0 0	18 0 0	73.5	82.1	94.3	13.301	1305	733	84.7	51.3	57.0	-190.5	-60.5	4.3	218.2	-1.150		
yt	06/19/94	24.00	24.000	8.367	0.000	0 0	21 0 0	70.6	75.7	87.6	8.367	1229	694	77.7	52.7	58.3	-111.6	-34.2	2.5	124.1	-1.175		
yt	06/20/94	24.00	24.000	14.770	0.000	0 0	17 0 0	68.8	79.3	93.4	14.770	1390	775	82.9	51.8	55.9	-219.4	-73.2	4.9	250.8	-1.167		
yt	06/21/94	24.00	24.000	12.341	0.000	0 0	18 0 0	71.0	79.0	92.7	12.341	1286	727	80.5	52.6	56.4	-171.9	-55.1	3.8	191.6	-1.185		
yt	06/22/94	24.00	24.000	18.012	0.000	0 0	15 0 0	73.0	81.7	93.3	18.012	1238	711	83.6	51.3	55.6	-250.2	-83.1	5.4	275.9	-1.208		
yt	06/23/94	24.00	24.000	15.794	0.000	0 0	19 0 0	74.4	83.6	95.4	15.794	1310	740	85.5	51.7	56.7	-222.9	-70.6	5.1	257.3	-1.141		
yt	06/24/94	24.00	24.000	17.305	0.000	0 0	12 0 0	71.3	85.6	96.7	17.305	1975	977	88.2	51.0	56.8	-303.6	-104.5	8.4	448.0	-0.911		
yt	06/25/94	24.00	24.000	18.899	0.000	0 0	7 0 0	76.1	87.2	97.8	18.899	1921	972	89.2	50.8	56.4	-335.7	-118.9	8.8	480.0	-0.947		
yt	06/26/94	24.00	24.000	20.067	0.000	0 0	10 0 0	76.6	85.8	94.8	20.067	1241	718	87.3	50.5	56.4	-281.5	-93.8	6.2	320.2	-1.172		
yt	06/27/94	24.00	24.000	20.677	0.000	0 0	11 0 0	74.5	85.6	96.5	20.677	1370	771	87.5	49.4	56.1	-313.1	-94.3	6.9	362.0	-1.126		
yt	06/28/94	24.00	23.992	19.556	0.000	0 0	12 0 0	73.4	86.2	97.2	19.556	1337	757	88.2	50.0	56.3	-287.7	-87.0	6.4	333.1	-1.125		
yt	06/29/94	24.00	24.000	20.725	0.000	0 0	11 0 0	73.7	84.8	96.3	20.725	1461	803	86.7	49.6	56.3	-320.2	-100.6	7.4	385.7	-1.091		
yt	06/30/94	24.00	24.000	17.842	0.000	0 0	16 0 0	72.5	82.7	93.9	17.842	1367	772	85.1	50.1	56.8	-266.8	-84.3	6.0	303.6	-1.157		
yt	07/01/94	24.00	24.000	19.442	0.000	0 0	15 0 0	74.2	84.0	94.5	19.442	1274	733	86.2	49.9	56.3	-277.0	-83.1	6.1	310.7	-1.159		
yt	07/02/94	24.00	24.000	18.167	0.000	0 0	8 0 0	76.1	84.6	93.6	18.167	1775	929	87.2	49.0	56.8	-319.5	-103.1	7.9	412.5	-1.024		
yt	07/03/94	24.00	24.000	18.195	0.000	0 0	15 0 0	74.0	83.7	94.1	18.195	1403	787	86.0	49.4	56.4	-278.1	-78.6	6.3	324.4	-1.100		
yt	07/04/94	24.00	24.000	17.673	0.000	0 0	14 0 0	74.7	83.6	94.1	17.673	1386	783	86.0	49.7	56.6	-269.3	-82.4	6.0	308.3	-1.141		
yt	07/05/94	24.00	24.000	19.498	0.000	0 0	9 0 0	76.4	84.7	96.2	19.498	1419	795	85.8	49.8	56.5	-297.8	-99.2	6.8	350.1	-1.134		
yt	07/06/94	24.00	24.000	19.651	0.000	0 0	11 0 0	77.0	84.7	95.1	19.651	1394	778	85.1	49.8	56.2	-290.8	-92.7	6.8	348.6	-1.100		
yt	07/07/94	24.00	24.000	18.808	0.000	0 0	10 0 0	76.1	85.3	96.3	18.808	1920	966	88.6	50.4	57.6	-328.5	-116.7	9.1	474.3	-0.939		
yt	07/08/94	24.00	24.000	19.743	0.000	0 0	11 0 0	76.5	85.1	95.1	19.743	1454	810	87.3	49.7	57.4	-306.0	-101.9	7.1	365.2	-1.117		
yt	07/09/94	24.00	24.000	19.235	0.000	0 0	8 0 0	76.6	84.2	95.1	19.235	1469	819	84.4	48.5	56.2	-306.9	-94.3	6.9	353.4	-1.135		
yt	07/10/94	24.00	24.000	20.261	0.000	0 0	12 0 0	74.1	83.8	93.5	20.261	1941	970	85.4	48.8	56.5	-357.3	-108.2	9.8	511.0	-0.911		
yt	07/11/94	24.00	24.000	16.245	0.000	0 0	18 0 0	74.0	85.5	95.6	16.245	1432	800	86.9	49.5	57.2	-248.9	-73.6	5.9	296.6	-1.087		
yt	07/12/94	24.00	24.000	19.210	0.000	0 0	12 0 0	74.8	84.9	96.7	19.210	1782	925	86.7	49.8	57.1	-332.3	-113.6	8.6	442.0	-1.009		
yt	07/13/94	24.00	24.000	17.172	0.000	0 0	11 0 0	75.5	84.5	94.9	17.172	2085	1016	86.0	49.4	56.8	-314.8	-106.0	9.1	469.7	-0.896		
yt	07/14/94	24.00	23.596	18.489	0.000	0 0	11 0 0	77.3	85.2	94.5	18.489	1422	807	86.9	49.9	56.5	-284.0	-96.0	6.6	331.9	-1.145		
yt	07/15/94	24.00	24.000	18.166	0.000	0 0	13 0 0	77.1	85.2	94.8	18.166	1503	820	85.7	49.8	57.0	-284.7	-94.0	6.9	349.9	-1.083		
yt	07/16/94	24.00	24.000	18.379	0.000	0 0	11 0 0	76.5	85.4	95.6	18.379	1622	877	87.8	49.4	57.0	-305.7	-98.1	7.5	383.4	-1.053		
yt	07/17/94	24.00	24.000	19.354	0.000	0 0	12 0 0	74.9	85.3	95.9	19.354	1619	871	86.7	48.3	56.6	-327.5	-95.0	7.9	399.7	-1.057		
yt	07/18/94	24.00	24.000	18.343	0.000	0 0	16 0 0	72.8	84.8	94.5	18.343	1211	722	86.7	47.3	56.3	-264.9	-63.9	5.8	280.2	-1.173		
yt	07/19/94	24.00	24.000	15.706	0.000	0 0	21 0 0	74.8	84.9	95.1	15.706	1241	732	86.8	47.8	57.8	-229.3	-59.7	5.1	246.2	-1.174		
yt	07/20/94	24.00	24.000	16.414	0.000	0 0	16 0 0	75.8	85.2	95.2	16.414	1230	729	87.5	47.5	57.2	-239.4	-63.5	5.3	256.9	-1.180		
yt	07/21/94	24.00	24.000	15.586	0.000	0 0	19 0 0	75.7	85.3	95.6	15.586	1212	721	87.5	47.5	57.6	-224.5	-58.0	5.0	240.7	-1.173		
yt	07/22/94	24.00	24.000	16.259	0.000	0 0	17 0 0	74.6	86.1	96.6	16.259	1740	905	88.7	48.0	57.9	-284.5	-76.9	7.3	369.4	-0.978		
yt	07/23/94	24.00	24.000	19.636	0.000	0 0	14 0 0	74.9	86.3	97.0	19.636	1692	890	87.5	47.4	57.2	-345.1	-89.9	8.4	431.6	-1.008		
yt	07/24/94	24.00	24.000	16.099	0.000	0 0	11 0 0	72.6	84.6	96.9	16.099	1822	919	85.8	46.8	56.5	-291.5	-71.2	7.4	383.7	-0.945		
yt	07/25/94	24.00	24.000	16.708	0.000	0 0	11 0 0	72.3	84.6	97.0	16.708	1492	818	86.1	46.9	56.8	-276.7	-72.0	6.4	318.1	-1.096		
yt	07/26/94	24.00	23.757	18.798	0.000	0 0	14 0 0	73.1	85.4	96.3	18.798	1390	792	86.6	47.3	56.7	-297.6	-78.0	6.8	331.3	-1.134		
yt	07/27/94	24.00	24.000	20.298	0.000	0 0	12 0 0	78.0	85.4	95.6	20.298	1295	762	86.5	45.6	56.2	-319.0	-70.8	6.8	330.1	-1.181		
yt	07/28/94	24.00	24.000	10.262	0.000	0 0	19 0 0	70.8	80.8	92.5	10.262	1517	820	82.7	42.8	56.0	-179.2	-14.5	4.0	194.2	-0.998		
yt	07/29/94	24.00	24.000	15.835	0.000	0 0	20 0 0	70.2	81.6	93.6	15.835	1339	771	83.4	45.0	55.2	-253.4	-41.6	5.5	261.0	-1.131		
yt	07/30/94	24.00	24.000	12.789	0.000	0 0	25 0 0	69.7	79.2	88.8	12.789	1245	732	80.3	47.8	56.8	-188.9	-41.2	4.1	191.4	-1.202		
yt	07/31/94	24.00	24.000	15.121	0.000	0 0	15 0 0	73.7	80.2	89.4	15.121	1453	817	81.5	48.3	56.0	-242.5	-68.8	5.6	265.6	-1.172		

Daily summary file - San Antonio Crada Site, cont'd

Site	Date	Total Time	Total Data Time	Total Eng Hours	Total Adv Hours	F	C	---Cycles---	Min	Avg	Max	Cooling													
YY	MM/DD/YY	[Hrs]	[Hrs]	[Hrs]	[Hrs]	O	F	Eng Def Aux	OD THum [F]	OD THum [F]	OD THum [F]	Cool Time [Hrs]	Eng Speed [RPM]	Air Flow [SCFM]	OD Temp [F]	ID RelHm [%]	ID Supply [F]	Daily SenCap [KBtu]	Daily LatCap [KBtu]	Daily Elect [KWHr]	Daily Gas [KBtu]	Daily TCOP			
yt	08/01/94	24.00	23.802	14.121	0.000	0	0	20 0 0	71.3	81.1	92.8	14.121	1268	742	81.7	48.7	56.9	-208.0	-59.2	4.6	217.6	-1.228			
yt	08/02/94	24.00	24.000	13.428	0.000	0	0	18 0 0	71.0	81.2	91.5	13.428	1623	864	82.8	48.1	57.1	-231.2	-60.9	5.6	274.2	-1.065			
yt	08/03/94	24.00	24.000	18.511	0.000	0	0	13 0 0	72.3	82.7	92.4	18.511	1374	790	85.0	46.9	55.9	-291.2	-75.6	6.5	314.2	-1.167			
yt	08/04/94	24.00	24.000	15.346	0.000	0	0	12 0 0	72.3	79.8	91.9	15.346	1351	782	78.6	47.9	56.2	-238.7	-74.7	5.2	246.7	-1.273			
yt	08/05/94	24.00	24.000	12.207	0.000	0	0	14 0 0	71.9	77.9	90.9	12.207	1297	760	80.9	49.1	56.4	-180.1	-52.9	4.1	192.1	-1.213			
yt	08/06/94	24.00	24.000	16.142	0.000	0	0	16 0 0	70.6	81.8	92.9	16.142	1276	755	85.2	49.8	57.3	-233.6	-72.7	5.4	258.6	-1.184			
yt	08/07/94	24.00	24.000	16.765	0.000	0	0	14 0 0	74.6	84.1	94.8	16.765	1599	862	86.8	49.2	57.7	-274.2	-89.9	7.0	347.2	-1.049			
yt	08/08/94	24.00	24.000	14.541	0.000	0	0	20 0 0	76.7	83.3	93.3	14.541	1304	762	83.8	49.7	58.2	-213.3	-70.0	5.0	238.1	-1.190			
yt	08/09/94	24.00	24.000	15.045	0.000	0	0	25 0 0	70.5	76.0	81.7	15.045	1239	737	75.9	51.3	56.9	-210.9	-75.4	4.8	221.0	-1.295			
yt	08/10/94	24.00	24.000	10.848	0.000	0	0	15 0 0	71.1	78.4	89.0	10.848	1437	810	81.1	51.4	57.6	-168.2	-57.3	4.0	191.1	-1.180			
yt	08/11/94	24.00	24.000	14.937	0.000	0	0	17 0 0	70.9	80.6	89.8	14.937	1322	766	83.7	50.4	57.0	-218.5	-70.9	5.2	245.8	-1.178			
yt	08/12/94	24.00	24.000	16.191	0.000	0	0	18 0 0	72.7	81.8	90.4	16.191	1217	729	84.3	48.7	57.0	-230.1	-64.8	5.2	244.9	-1.204			
yt	08/13/94	24.00	24.000	14.829	0.000	0	0	17 0 0	74.1	82.4	91.0	14.829	1416	807	83.3	49.5	57.1	-233.7	-71.3	5.4	263.0	-1.160			
yt	08/14/94	24.00	24.000	18.067	0.000	0	0	14 0 0	74.2	83.4	92.6	18.067	1346	789	84.3	48.5	56.4	-276.0	-78.9	6.4	305.4	-1.162			
yt	08/15/94	24.00	24.000	14.060	0.000	0	0	18 0 0	75.1	83.3	94.8	14.060	1418	805	83.4	48.7	57.5	-221.2	-64.0	5.2	249.2	-1.145			
yt	08/16/94	24.00	24.000	15.104	0.000	0	0	17 0 0	73.4	83.1	94.6	15.104	1312	768	84.9	48.9	58.5	-226.7	-71.0	5.3	247.8	-1.201			
yt	08/17/94	24.00	24.000	15.522	0.000	0	0	18 0 0	73.6	84.5	94.7	15.522	1541	829	87.0	48.9	58.6	-246.6	-76.8	6.3	310.3	-1.042			
yt	08/18/94	24.00	24.000	15.743	0.000	0	0	21 0 0	75.5	85.6	95.3	15.743	1772	895	88.0	48.4	58.3	-269.4	-74.7	7.3	367.5	-0.936			
yt	08/19/94	24.00	24.000	19.242	0.000	0	0	16 0 0	77.1	85.2	94.9	19.242	1402	812	86.4	48.9	57.7	-298.5	-93.7	7.1	340.9	-1.150			
yt	08/20/94	24.00	24.000	20.040	0.000	0	0	10 0 0	75.6	85.5	96.0	20.040	1740	906	87.7	48.6	57.5	-337.6	-114.8	9.2	453.3	-0.998			
yt	08/21/94	24.00	24.000	19.067	0.000	0	0	9 0 0	73.7	82.1	93.5	19.067	1331	786	83.2	48.5	57.5	-289.9	-93.9	6.7	314.5	-1.220			
yt	08/22/94	24.00	24.000	12.974	0.000	0	0	20 0 0	73.0	82.2	92.4	12.974	1422	801	83.6	50.5	58.6	-196.6	-66.9	5.0	230.4	-1.144			
yt	08/23/94	24.00	24.000	16.112	0.000	0	0	14 0 0	76.6	84.2	94.8	16.112	1361	791	85.0	50.1	58.5	-241.3	-86.7	5.9	271.0	-1.210			
yt	08/24/94	24.00	24.000	16.611	0.000	0	0	18 0 0	75.7	82.0	95.8	16.611	1299	769	82.9	49.6	58.1	-244.1	-82.7	5.7	261.7	-1.249			
yt	08/25/94	24.00	23.947	12.246	0.000	0	0	22 0 0	73.7	81.6	91.3	12.246	1297	761	82.8	50.6	59.1	-177.8	-60.3	4.3	193.4	-1.231			
yt	08/26/94	24.00	24.000	13.968	0.000	0	0	21 0 0	73.2	83.2	92.7	13.968	1442	825	85.6	49.6	58.7	-222.3	-70.6	5.4	251.2	-1.166			
yt	08/27/94	24.00	24.000	20.188	0.000	0	0	12 0 0	74.3	82.7	93.4	20.188	1330	788	83.9	48.6	57.4	-304.6	-95.6	7.1	330.8	-1.210			
yt	08/28/94	24.00	24.000	14.791	0.000	0	0	15 0 0	72.5	82.5	92.6	14.791	1351	795	85.3	48.2	57.9	-227.6	-65.5	5.4	249.9	-1.173			
yt	08/29/94	24.00	24.000	15.752	0.000	0	0	16 0 0	75.7	84.2	94.0	15.752	1430	817	85.7	48.0	58.3	-251.0	-75.4	6.1	283.6	-1.151			
yt	08/30/94	24.00	24.000	14.307	0.000	0	0	20 0 0	74.7	80.8	88.6	14.307	1393	801	81.2	50.5	58.6	-216.9	-78.2	5.3	246.3	-1.198			
yt	08/31/94	24.00	24.000	12.259	0.000	0	0	21 0 0	75.6	79.7	86.9	12.259	1242	751	79.5	51.6	58.8	-173.2	-64.6	4.0	184.8	-1.286			
yt	09/01/94	24.00	24.000	11.379	0.000	0	0	26 0 0	74.1	80.2	90.0	11.379	1259	751	80.6	51.9	59.4	-161.6	-59.6	3.9	176.4	-1.254			
yt	09/02/94	24.00	24.000	16.870	0.000	0	0	20 0 0	72.8	80.3	90.7	16.870	1237	753	81.8	51.3	57.4	-239.0	-86.1	5.6	255.4	-1.273			
yt	09/03/94	24.00	24.000	13.906	0.000	0	0	18 0 0	71.5	81.4	91.5	13.906	1333	785	83.8	50.4	58.4	-209.5	-68.5	5.0	232.3	-1.197			
yt	09/04/94	24.00	24.000	16.206	0.000	0	0	14 0 0	73.0	82.0	93.3	16.206	1259	765	83.5	47.9	56.7	-243.2	-64.3	5.6	253.9	-1.211			
yt	09/05/94	24.00	23.771	17.330	0.000	0	0	11 0 0	70.7	81.3	92.7	17.330	1343	798	84.0	47.9	56.6	-270.9	-75.6	6.3	289.0	-1.199			
yt	09/06/94	24.00	24.000	13.982	0.000	0	0	16 0 0	73.6	83.4	93.6	13.982	1250	759	84.8	47.5	57.8	-209.4	-53.0	4.8	218.0	-1.203			
yt	09/07/94	24.00	23.468	14.802	0.000	0	0	20 0 0	68.6	83.1	94.0	14.802	1434	828	84.9	48.6	58.8	-240.4	-71.3	5.9	263.2	-1.184			
yt	09/08/94	24.00	24.000	7.285	0.000	0	0	22 0 0	70.7	72.4	75.5	7.285	1227	745	72.1	53.4	59.2	-103.8	-39.7	2.5	103.2	-1.390			
yt	09/09/94	24.00	24.000	6.382	0.000	0	0	15 0 0	69.0	72.9	79.4	6.382	1306	771	73.0	54.5	58.2	-91.8	-37.3	2.3	98.3	-1.314			
yt	09/10/94	24.00	24.000	9.286	0.000	0	0	22 0 0	68.0	74.8	84.6	9.286	1237	746	76.7	55.4	58.5	-126.9	-54.0	3.1	137.2	-1.319			
yt	09/11/94	24.00	24.000	9.264	0.000	0	0	21 0 0	71.0	75.9	84.9	9.264	1237	750	77.1	56.4	58.7	-124.5	-54.9	3.1	135.3	-1.326			
yt	09/12/94	24.00	24.000	6.790	0.000	0	0	16 0 0	71.8	75.5	82.8	6.790	1309	778	76.2	56.3	59.1	-94.0	-43.8	2.4	106.8	-1.291			
yt	09/13/94	24.00	24.000	7.145	0.000	0	0	22 0 0	72.6	76.4	87.2	7.145	1233	747	76.5	57.7	60.3	-95.1	-48.9	2.4	105.3	-1.367			
yt	09/14/94	24.00	24.000	7.609	0.000	0	0	20 0 0	71.8	75.2	85.1	7.609	1245	756	75.2	56.6	59.3	-103.1	-48.6	2.6	113.2	-1.339			
yt	09/15/94	24.00	24.000	7.768	0.000	0	0	18 0 0	71.4	77.3	86.4	7.768	1253	763	78.3	56.4	59.5	-105.9	-49.5	2.7	115.1	-1.351			

Daily summary file - San Antonio Crada Site, cont'd

Site		Date	Total Time	Total Data	Total Eng	Total Adv	F	C	---Cycles---			Min	Avg	Max	-----Cooling-----											
YY	MM/DD/YY	[Hrs]	[Hrs]	[Hrs]	[Hrs]	[Hrs]	O	F	Eng	Def	Aux	THum	THum	THum	Cool Time	Eng Speed	Air Flow	OD Temp	ID RelHm	ID Supply	Daily SenCap	Daily LatCap	Daily Elect	Daily Gas	Daily TCOP	
YY	MM/DD/YY	[Hrs]	[Hrs]	[Hrs]	[Hrs]	[Hrs]	O	F	Eng	Def	Aux	[F]	[F]	[F]	[Hrs]	[RPM]	[SCFM]	[F]	[X]	[F]	[KBtu]	[KBtu]	[KWHr]	[KBtu]		
yt	09/16/94	24.00	24.000	7.354	0.000	0 0	21	0	0	0	0	71.8	76.6	86.7	7.354	1239	752	76.3	56.0	59.7	-100.4	-44.3	2.5	107.6	-1.345	
yt	09/17/94	24.00	24.000	7.562	0.000	0 0	24	0	0	0	0	71.4	77.1	86.3	7.562	1210	736	79.1	51.5	57.9	-106.7	-20.6	2.5	111.2	-1.144	
yt	09/18/94	24.00	24.000	5.872	0.000	0 0	15	0	0	0	0	66.9	75.9	86.5	5.872	1221	745	79.1	48.0	57.6	-88.0	-12.5	2.0	87.3	-1.152	
yt	09/19/94	24.00	24.000	7.880	0.000	0 0	17	0	0	0	0	66.4	75.6	85.3	7.880	1249	760	78.0	47.6	56.5	-120.2	-20.9	2.7	117.8	-1.198	
yt	09/20/94	24.00	23.724	8.249	0.000	0 0	22	0	0	0	0	63.0	74.6	84.7	8.249	1216	744	76.4	49.7	57.1	-121.4	-25.3	2.8	118.2	-1.241	
yt	09/21/94	24.00	24.000	6.042	0.000	0 0	17	0	0	0	0	63.6	74.3	84.1	6.042	1282	766	74.4	49.6	57.4	-93.3	-20.9	2.2	90.7	-1.259	
yt	09/22/94	24.00	24.000	2.452	0.000	0 0	11	0	0	0	0	58.4	67.9	79.8	2.452	1227	740	67.8	51.0	58.4	-36.3	-5.3	0.9	35.0	-1.190	
yt	09/23/94	24.00	24.000	1.723	0.000	0 0	5	0	0	0	0	54.1	66.9	78.2	1.723	1302	772	71.1	46.9	55.0	-27.1	-1.7	0.6	26.9	-1.066	
yt	09/24/94	24.00	24.000	2.121	0.000	0 0	9	0	0	0	0	59.3	69.8	80.0	2.121	1256	748	75.3	44.7	57.3	-32.6	0.0	0.7	32.8	-0.995	
yt	09/25/94	24.00	24.000	3.179	0.000	0 0	8	0	0	0	0	58.7	71.4	85.2	3.179	1298	785	73.4	46.4	55.7	-50.8	-3.4	1.1	49.0	-1.106	
yt	09/26/94	24.00	24.000	5.783	0.000	0 0	13	0	0	0	0	60.3	73.4	85.7	5.783	1230	754	77.5	46.6	56.2	-88.2	-12.2	2.0	84.8	-1.184	
yt	09/27/94	24.00	24.000	8.935	0.000	0 0	19	0	0	0	0	63.2	76.0	90.0	8.935	1254	755	80.7	49.5	57.3	-131.1	-28.5	3.2	135.8	-1.175	
yt	09/28/94	24.00	24.000	7.686	0.000	0 0	21	0	0	0	0	65.7	76.5	88.1	7.686	1235	748	78.7	49.2	58.5	-113.4	-23.8	2.7	111.8	-1.227	
yt	09/29/94	24.00	24.000	7.547	0.000	0 0	16	0	0	0	0	61.7	75.4	87.4	7.547	1271	770	77.7	46.6	57.1	-119.6	-19.9	2.7	115.7	-1.205	
yt	09/30/94	24.00	24.000	9.913	0.000	0 0	16	0	0	0	0	67.8	75.9	86.0	9.913	1260	768	78.6	48.4	56.5	-150.7	-36.5	3.4	151.3	-1.237	
yt	10/01/94	24.00	24.000	10.693	0.000	0 0	20	0	0	0	0	66.3	77.0	86.9	10.693	1218	755	79.0	49.9	57.2	-156.5	-40.1	3.7	157.8	-1.246	
yt	10/02/94	24.00	24.000	11.015	0.000	0 0	18	0	0	0	0	68.2	79.2	89.6	11.015	1349	781	81.9	48.8	57.3	-167.3	-43.9	4.2	186.4	-1.133	
yt	10/03/94	24.00	24.000	12.454	0.000	0 0	14	0	0	0	0	70.4	80.9	91.7	12.454	1551	870	82.9	48.1	57.3	-210.7	-56.5	5.5	240.4	-1.111	
yt	10/04/94	24.00	24.000	10.986	0.000	0 0	23	0	0	0	0	71.9	78.6	88.0	10.986	1242	759	79.4	50.0	58.5	-161.9	-49.0	3.9	162.3	-1.299	
yt	10/05/94	24.00	24.000	10.423	0.000	0 0	23	0	0	0	0	66.8	76.7	86.2	10.423	1295	774	77.9	49.5	57.8	-157.3	-42.5	3.8	161.3	-1.239	
yt	10/06/94	24.00	23.999	10.591	0.000	0 0	13	0	0	0	0	68.2	77.9	88.7	10.591	1376	812	80.1	49.4	56.7	-164.6	-49.2	4.1	176.8	-1.210	
yt	10/07/94	24.00	22.661	9.889	0.000	0 0	22	0	0	0	0	66.2	78.7	86.7	9.889	1458	832	80.1	52.8	59.1	-149.7	-54.2	4.1	177.3	-1.150	
yt	10/08/94	24.00	24.000	3.130	0.000	0 0	12	0	0	0	0	62.0	67.6	77.0	3.130	1208	737	69.3	52.9	58.2	-44.0	-9.4	1.1	44.5	-1.197	
yt	10/09/94	24.00	24.000	0.000	0.000	0 0	0	0	0	0	0	58.8	64.8	71.7	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/10/94	24.00	23.750	0.000	0.000	0 0	0	0	0	0	0	53.7	63.5	73.0	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/11/94	24.00	24.000	0.000	0.000	0 0	0	0	0	0	0	53.7	63.3	74.6	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/12/94	24.00	24.000	0.000	0.000	0 0	0	0	0	0	0	50.1	63.3	75.2	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/13/94	24.00	24.000	0.000	0.000	0 0	0	0	0	0	0	54.0	64.7	74.8	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/14/94	24.00	24.000	0.000	0.000	0 0	0	0	0	0	0	58.0	61.5	66.1	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/15/94	24.00	24.000	0.000	0.000	0 0	0	0	0	0	0	59.8	66.2	72.9	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/16/94	24.00	23.565	8.799	0.000	0 0	12	0	0	0	0	73.3	77.6	84.8	8.799	1275	770	80.5	58.3	58.9	-113.7	-58.3	3.1	139.0	-1.237	
yt	10/17/94	24.00	20.376	9.487	0.000	0 0	16	0	0	0	0	72.9	79.6	87.2	9.487	1588	873	80.7	57.1	59.1	-139.3	-68.1	4.2	187.8	-1.104	
yt	10/18/94	24.00	23.813	6.848	0.000	0 0	13	0	0	0	0	68.0	71.4	74.9	6.848	1537	796	71.3	56.2	56.6	-96.3	-47.8	2.7	126.3	-1.140	
yt	10/19/94	24.00	24.000	4.935	0.000	0 0	11	0	0	0	0	69.6	75.8	84.7	4.935	1245	663	79.2	55.6	57.7	-59.3	-24.8	1.4	74.7	-1.126	
yt	10/20/94	24.00	24.000	10.205	0.000	0 0	10	0	0	0	0	73.2	78.1	86.5	10.205	1260	674	81.3	52.3	56.6	-126.1	-51.6	2.9	160.8	-1.105	
yt	10/21/94	24.00	23.316	11.435	0.000	0 0	23	0	0	0	0	73.8	78.3	86.3	11.435	1214	653	80.7	52.8	56.8	-137.6	-49.8	3.1	170.3	-1.101	
yt	10/22/94	24.00	23.595	10.743	0.000	0 0	26	0	0	0	0	72.1	76.5	83.1	10.743	1231	659	77.1	54.5	57.6	-130.9	-52.2	3.0	158.5	-1.155	
yt	10/23/94	24.00	23.651	9.157	0.000	0 0	18	0	0	0	0	70.9	75.6	83.6	9.157	1268	676	76.6	54.2	57.4	-115.7	-46.7	2.6	139.5	-1.164	
yt	10/24/94	24.00	23.391	8.808	0.000	0 0	15	0	0	0	0	70.4	75.8	83.9	8.808	1317	697	78.1	52.2	56.3	-116.6	-41.3	2.6	141.4	-1.117	
yt	10/25/94	24.00	24.000	1.151	0.000	0 0	5	0	0	0	0	56.4	66.1	73.0	1.151	1216	645	66.7	57.0	58.2	-13.7	-4.1	0.3	16.3	-1.093	
yt	10/26/94	24.00	24.000	0.790	0.000	0 0	3	0	0	0	0	53.1	58.0	64.8	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/27/94	24.00	24.000	4.167	0.000	0 0	17	0	0	0	0	51.4	56.6	60.9	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/28/94	24.00	24.000	4.048	0.000	0 0	17	0	0	0	0	55.3	62.4	71.0	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	10/29/94	24.00	24.000	1.336	0.000	0 0	6	0	0	0	0	56.2	65.9	75.9	0.264	1238	653	63.7	56.4	57.5	-3.2	0.0	0.1	4.0	-0.798	
yt	10/30/94	24.00	24.000	1.780	0.000	0 0	7	0	0	0	0	59.7	67.2	77.1	1.780	1301	684	73.5	58.7	57.4	-21.5	-6.6	0.5	28.6	-0.986	
yt	10/31/94	24.00	23.891	0.262	0.000	0 0	1	0	0	0	0	57.3	68.3	80.5	0.262	1230	665	72.0	58.6	59.9	-2.9	-0.4	0.1	4.1	-0.808	

Party Summary Title			San Antonio			Cradle Creek, Cont'd			Cooling																
Site	Date	Total	Total	Total	F	C	---Cycles---			Min	Avg	Max	Cool	Eng	Air	OD	ID	ID	Daily	Daily	Daily	Daily	Daily		
YY	MM/DD/YY	Time	Data	Eng	Adv	O	F	Eng	Def	Aux	THum	OD	THum	THum	Time	Speed	Flow	Temp	RelHm	Supply	SenCap	LatCap	Elect	Gas	TCOP
		[Hrs]	[Hrs]	[Hrs]	[Hrs]						[F]		[F]	[F]	[Hrs]	[RPM]	[SCFM]	[F]	[%]	[F]	[KBtu]	[KBtu]	[KWHr]	[KBtu]	
yt	11/01/94	24.00	23.183	0.000	0.000	0	0	0	0	0	47.1	57.9	68.0	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000
yt	11/02/94	24.00	24.000	0.496	0.000	0	0	2	0	0	57.3	71.0	82.0	0.496	1220	653	75.3	66.3	61.1	-4.9	-1.2	0.1	7.7	-0.794	
yt	11/03/94	24.00	22.664	5.629	0.000	0	0	17	0	0	73.2	77.0	84.0	5.629	1206	648	78.4	59.8	59.2	-64.0	-32.7	1.5	82.3	-1.174	
yt	11/04/94	24.00	21.448	10.973	0.000	0	0	22	0	0	74.7	77.2	82.0	10.973	1301	693	77.3	56.4	55.9	-137.1	-55.0	3.2	173.7	-1.106	
yt	11/05/94	24.00	23.603	3.004	0.000	0	0	11	0	0	54.6	63.4	75.9	3.004	1212	647	68.2	53.2	55.8	-38.4	-7.4	0.8	42.3	-1.085	
yt	11/06/94	24.00	24.000	0.000	0.000	0	0	0	0	0	54.6	62.9	73.6	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/07/94	24.00	23.999	0.233	0.000	0	0	1	0	0	54.1	65.8	75.3	0.233	1244	662	71.5	61.4	59.4	-2.4	0.0	0.1	3.8	-0.641	
yt	11/08/94	24.00	24.000	3.673	0.000	0	0	11	0	0	70.2	75.2	82.4	3.673	1208	651	77.3	59.1	58.8	-42.6	-20.1	1.0	53.8	-1.165	
yt	11/09/94	24.00	24.000	1.886	0.000	0	0	9	0	0	53.7	66.7	80.4	1.886	1213	643	69.7	61.1	59.9	-21.0	-9.2	0.5	27.2	-1.111	
yt	11/10/94	24.00	24.000	5.589	0.000	0	0	16	0	0	46.6	52.8	62.2	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/11/94	24.00	24.000	11.039	0.000	0	0	27	0	0	45.5	54.2	62.1	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/12/94	24.00	24.000	6.863	0.000	0	0	25	0	0	57.3	63.1	68.6	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/13/94	24.00	24.000	5.806	0.000	0	0	17	0	0	66.3	72.1	79.0	4.401	1393	735	74.0	56.4	55.7	-58.8	-22.6	1.4	75.2	-1.082	
yt	11/14/94	24.00	24.000	5.363	0.000	0	0	20	0	0	63.2	71.7	78.8	5.363	1205	648	72.0	58.4	56.6	-62.7	-25.0	1.5	76.6	-1.145	
yt	11/15/94	24.00	24.000	0.031	0.000	0	0	1	0	0	56.3	58.1	62.6	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/16/94	24.00	24.000	5.959	0.000	0	0	23	0	1	54.6	58.6	62.5	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/17/94	24.00	24.000	7.055	0.000	0	0	24	0	0	58.9	65.1	73.9	2.625	1630	824	64.7	50.7	51.9	-42.4	-12.0	1.0	50.4	-1.078	
yt	11/18/94	24.00	24.000	2.311	0.000	0	0	9	0	0	63.6	67.9	71.3	1.996	1215	655	69.5	63.3	56.4	-21.6	-10.2	0.6	29.8	-1.067	
yt	11/19/94	24.00	24.000	3.961	0.000	0	0	7	0	0	69.7	73.5	79.6	3.676	1409	740	74.1	56.5	55.3	-49.0	-19.4	1.2	64.6	-1.059	
yt	11/20/94	24.00	24.000	0.747	0.000	0	0	4	0	0	52.4	68.0	76.7	0.747	1204	645	71.6	64.1	59.4	-7.7	-4.1	0.2	11.2	-1.055	
tf	11/21/94	24.00	24.000	4.237	0.000	0	0	17	0	0	45.5	60.5	75.2	0.834	1630	818	61.9	46.5	51.3	-14.0	0.0	0.3	16.2	-0.864	
yt	11/22/94	24.00	23.282	2.507	0.000	0	0	12	0	0	56.5	66.2	76.4	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/23/94	24.00	24.000	7.905	0.000	0	0	25	0	0	48.0	53.2	63.4	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/24/94	24.00	24.000	14.134	0.000	0	0	33	0	0	47.4	49.2	53.4	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/25/94	24.00	24.000	6.861	0.000	0	0	22	0	0	53.4	61.4	72.1	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/26/94	24.00	24.000	2.087	0.000	0	0	10	0	0	56.7	68.1	78.6	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/27/94	24.00	24.000	4.818	0.000	0	0	19	0	0	61.8	70.9	79.7	4.546	1249	670	72.4	56.8	56.6	-55.4	-15.6	1.3	68.6	-1.036	
yt	11/28/94	24.00	24.000	6.764	0.000	0	0	30	0	0	51.9	57.2	63.2	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/29/94	24.00	24.000	7.840	0.000	0	0	31	0	0	49.5	58.5	69.4	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	
yt	11/30/94	24.00	24.000	13.196	0.000	0	0	36	0	0	44.6	51.8	60.9	0.000	0	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.000	

Appendix E

Fuel Price Calculations

Appendix E

Fuel Price Calculations

The fuel prices used in the operating cost analysis are \$0.4257/ccf and \$0.0581/kWh for the Triathlon. For the comparison units, a price of \$0.06315/kWh is used for electricity. These averages are derived from the monthly adjusted costs reported by City Public Service of San Antonio (Table E.1). The averages are calculated over the test period using monthly fuel usage as weights (Table E.2). Monthly electric rates are subject to an additional peak capacity charge of \$0.015/kWh for electric usage in excess of 600 kWh/mo, applicable from June through September. Individual residential gas and electric bills include a service availability charge of \$4.25/mo for gas and \$3.85 for electricity. These charges are not included in the monthly adjusted costs.

Table E.1. Retail Cost of Electricity and Gas During 1994 Cooling Test Period

Days 516 = 6/1/94	Electricity Cost, \$/kWh	Gas Cost, \$/ccf
516-545	0.05684	0.41198
546-576	0.05806	0.43976
577-607	0.06141	0.43956
608-637	0.05661	0.41012
638-668	0.05297	0.37916
669-698	0.05482	0.40086

Table E.2. Gas and Electricity Usage During 1994 Cooling Test Period

Days 516 = 6/1/94	Triathlon Monthly Electricity Usage, kWh	Triathlon Monthly Gas Usage, MBtu	Unit 1 Projected Monthly Electricity Usage, kWh
516-545	80	4.2	549
546-576	207	10.5	1354
577-607	174	8.3	1115
608-637	90	4.0	482
638-668	56	2.7	302
669-698	15	0.8	59

Distribution

No. of Copies		No. of Copies	
	Offsite		Offsite
2	DOE/Office of Scientific and Technical Information	3	S. Young Director of Engineering & Housing HQ 5th U.S. Army at Fort Sam Houston San Antonio, TX 78334
18	U.S. Department of Energy Federal Energy Management Program 1000 Independence Avenue SW Washington, DC 20585 ATTN: K. Dean DeVine (EE-44) (15) M. Ginsberg (EE-44) J. Brodrick (EE-422) J. D. Ryan (EE-422)	3	J. Brogan Gas Research Institute 8600 W. Bryn Mawr Avenue Chicago, IL 60631
	V. Petrolati EE-91 DOE/In-House Energy Management U.S. Department of Energy 1000 Independence Avenue SW Washington, DC 20585	3	P. E. Miles City Public Service of San Antonio, Texas Gas Operations Division P.O. Box 1771 San Antonio, TX 78296
	M. Carr Office of the Secretary of Defense DASD (L) EP Pentagon Washington, DC 20301-8000	3	R. Sweetser American Gas Cooling Center 1515 Wilson Boulevard Arlington, VA 22209
	A. Gillespie ATTN: FCEN-RDF FORSCOM Building 200 Fort McPherson, GA 30330-6000		C. Collins Family Housing Guidance and Standards Analyst Naval Facilities Engineering Command 200 Stovall Street Alexandria, VA 22332-2300
3	B. Swartz York International P.O. Box 1592, Mail Code 191B York, PA 17405		A. Houtzager Army Housing Divison Office of the Assistant Chief of Staff for Installation Management DAIM-FDH-F U.S. Army Center for Public Works 7701 Telegraph Road Alexandria, VA 22315-3862

No. of
Copies

Onsite

2 W. G. Atterbury
Battelle Memorial Institute
505 King Avenue
Columbus, OH 43201

E. Lauterstein
Reliable Distributing Company
1952 Shipman Drive
San Antonio, TX 78219

J. Freund
Comfort-Air Engineering Inc.
11403 Jones-Maltsberger
San Antonio, TX 78216

H. Gaberson
NFEFC-code 60
560 Center Drive
Port Hueneme, CA 93043-4328

P. W. Adcock
Oak Ridge National Laboratory
P.O. Box 2008
Oak Ridge, TN 37831-6070

B. Carroll
Lawrence Berkeley Laboratory
1 Cyclotron Road
Berkeley, CA 94720

B. K. Thomas
National Renewable Energy Laboratory
Suite 710
409 12th Street SW
Washington, DC 20024-2125

No. of
Copies

Onsite

DOE Richland Operations Office

P. W. Kruger A5-54

46 Pacific Northwest Laboratory

P. R. Armstrong K5-20
D. R. Conover BWO
J. A. Dirks K8-18
D. R. Dixon (5) K8-17
W. D. Hunt (5) BWO
J. D. Miller (5) K5-20
G. B. Parker K9-62
S. A. Parker K5-08
W. F. Sandusky K5-08
M. K. Stockmeyer (20) BWO
D. W. Winiarski K5-08
Technical Report Files (5)