A-7900-013-1

ENGINEERING CHANGE NOTICE

Page 2 of 2

1. ECN (use no. from pg. 1)

631389

15. Design Verification Required

☐ Yes
☒ No

16. Cost Impact

ENGINEERING

Additional ☐ \$
Savings ☐ \$

CONSTRUCTION

Additional ☐ \$
Savings ☐ \$

17. Schedule Impact (days)

Improvement ☐
Delay ☐

18. Change Impact Review: Indicate the related documents (other than the engineering documents identified on Side 1) that will be affected by the change described in Block 12. Enter the affected document number in Block 19.

SDD/DD	☐	Seismic/Stress Analysis	☐	Tank Calibration Manual	☐
Functional Design Criteria	☐	Stress/Design Report	☐	Health Physics Procedure	☐
Operating Specification	☐	Interface Control Drawing	☐	Spares Multiple Unit Listing	☐
Criticality Specification	☐	Calibration Procedure	☐	Test Procedures/Specification	☐
Conceptual Design Report	☐	Installation Procedure	☐	Component Index	☐
Equipment Spec.	☐	Maintenance Procedure	☐	ASME Coded Item	☐
Const. Spec.	☐	Engineering Procedure	☐	Human Factor Consideration	☐
Procurement Spec.	☐	Operating Instruction	☐	Computer Software	☐
Vendor Information	☐	Operating Procedure	☐	Electric Circuit Schedule	☐
OM Manual	☐	Operational Safety Requirement	☐	ICRS Procedure	☐
FSAR/SAR	☐	IEFD Drawing	☐	Process Control Manual/Plan	☐
Safety Equipment List	☐	Cell Arrangement Drawing	☐	Process Flow Chart	☐
Radiation Work Permit	☐	Essential Material Specification	☐	Purchase Requisition	☐
Environmental Impact Statement	☐	Fac. Proc. Samp. Schedule	☐	Tickler File	☐
Environmental Report	☐	Inspection Plan	☐		☐
Environmental Permit	☐	Inventory Adjustment Request	☐		☐

19. Other Affected Documents: (NOTE: Documents listed below will not be revised by this ECN.) Signatures below indicate that the signing organization has been notified of other affected documents listed below.

Document Number/Revision

Document Number/Revision

Document Number Revision

20. Approvals

Signature

Date

Signature

Date

OPERATIONS AND ENGINEERING

Cog. Eng. G. M. Koreski/J. N. Strode *G.M. Koreski* 9/18/96

Cog. Mgr. W. B. Barton *W.B. Barton* 9/18/96

QA _____

Safety _____

Environ. _____

Other _____

AM Umek, Director, TWRS Engineering — *A.M. Umek* 9/18/96

JO Honeyman, Director, Disposal Programs *J. Honeyman* 9/18/96

JH Wicks, Jr., Director, Tank Farm Transition Projects *J.H. Wicks, Jr.* 9/20/96

JE Geary, Manager, Evaporator Projects *J.E. Geary* 9/18/96

UCB

John C. Truax

ARCHITECT-ENGINEER

PE _____

QA _____

Safety _____

Design _____

Environ. _____

Other A. M. Umek, Director TWRS Eng. _____

DEPARTMENT OF ENERGY

Signature or a Control Number that tracks the Approval Signature

ADDITIONAL

Operational Waste Volume Projection

JN Strode/GM Koreski

WHC, Richland, WA 99352

U.S. Department of Energy Contract DE-AC06-87RL10930

EDT/ECN: 631389

UC: 2030

Org Code: 74A10

Charge Code: N1820

B&R Code: *FW2/2007/*

Total Pages: *61*

Key Words: Waste Volume Projection, Tank Space Management Board, Waste Volume Reduction, Double-Shell Tank, Evaporator, LERF

Abstract: Waste receipts to the double-shell tank system are analyzed and wastes through the year 2015 are projected based on generation trends of the past 12 months. A computer simulation of site operations is performed, which results in projections of tank fill schedules, tank transfers, evaporator operations, tank retrieval, and aging waste tank usage.

This projection incorporates current budget planning and the clean-up schedule of the Tri-Party Agreement. Assumptions were current as of June 1996.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: WHC/BCS Document Control Services, P.O. Box 1970, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

Kenn J. Bros *9/20/96*
Release Approval Date

Approved for Public Release

[illegible]

RECORD OF
REVISION

(1) Document Number

SU-101-ER-029

Page 1

(2) Title

Operational Waste Volume Projection

CHANGE CONTROL RECORD

(3) Revision	(4) Description of Change - Replace, Add, and Delete Pages	Authorized for Release		
		(5) Eng. Prod. Engr.	(6) Eng. Prod. Mgr.	Date
	(7) Previous revisions have been done on the now obsolete IRACOR and Record of Revision forms.			
13	Incorporated per ECN 140301	RL Shaver <i>RL Shaver</i>	RD Fox <i>RLS RD F 4-13-90</i>	
14	Incorporated per ECN 118924	R.L. Shaver <i>RL Shaver</i>	R.D. Fox <i>RLS RD F 7-10-90</i>	
15 <i>RS</i>	Incorporated per ECN 118963	GM Koreski/ JN Strode <i>G.M. Koreski</i> <i>J.N. Strode</i>	RD Fox <i>RLS RD F 4-11-91</i>	
16 <i>RS</i>	Incorporated per ECN 169259	GM Koreski/ JN Strode <i>G.M. Koreski</i> <i>J.N. Strode</i>	GT Frater <i>GT Frater 10-5-91</i>	
17 <i>RS</i>	Incorporated per ECN 195548 ^{195548 (2-5-92)}	G. M. Koreski J. N. Strode <i>G.M. Koreski</i> <i>J.N. Strode</i>	G. T. Frater <i>GT Frater</i> 4-21-93	
18	Incorporated per ECN 603360	G. M. Koreski J. N. Strode <i>G.M. Koreski</i> <i>J.N. Strode</i>	R. A. Dodd <i>RA Dodd</i>	
19 <i>RS</i>	Incorporated per ECN 189210	G. M. Koreski J. N. Strode <i>G.M. Koreski</i> <i>J.N. Strode</i>	N. W. Kirch <i>NWKul 4-26-94</i>	
<i>20</i> 20:	Incorporated per ECN 166505	G. M. Koreski J. N. Strode <i>G.M. Koreski</i> <i>J.N. Strode</i>	N. W. Kirch <i>NWKul 9/2/94</i>	

OPERATIONAL WASTE VOLUME PROJECTION

JUNE 1996

Prepared by

JN Strode
GM Koreski

This Page Intentionally Left Blank

TABLE OF CONTENTS

1.0	SUMMARY	1
2.0	INTRODUCTION	5
2.1	Purpose	5
2.2	Methodology	5
3.0	GENERAL FACILITY DESCRIPTIONS AND ASSUMPTIONS	7
3.1	B Plant/WESF	7
3.2	242-A Evaporator and LERF	7
3.3	Grout	10
3.4	Effluent Treatment Facility	10
3.5	PFP	11
3.6	PUREX	11
3.7	S Plant	12
3.8	Salt Well Liquid Pumping	12
3.9	Single-Shell Tank Solids Retrieval	14
3.10	Solid Waste Trench 31 Leachate	15
3.11	T Plant	15
3.12	Tank Farms	16
3.13	UO ₂ Facility	19
3.14	Waste Sampling and Characterization Facility (WSCF)	19
3.15	100 Area	19
3.16	300 Area	20
3.17	400 Area	20
3.18	Phase I Privatization Processing	20
3.19	Phase II Privatization Processing	25
3.20	Watch List/Safety	25
3.21	Spare/Contingency Space	25
3.22	Waste Segregation	25
3.23	Loss of DST Space	27
3.24	New DST Construction	27
3.25	DST Tank Solids Levels	27
3.27	IMUST Wastes	27
3.28	Assumption Summary	27
4.0	LOWER AND UPPER PLANNING CASE ASSUMPTIONS	32
4.1	Lower Planning Case Assumptions	32
4.2	Upper Planning Case Assumptions	33
5.0	RESULTS AND CONCLUSIONS	34
5.1	Baseline Case Results and Conclusions	34
5.2	Lower Planning Case Results and Conclusions	59
5.3	Upper Planning Case Results and Conclusions	61
5.4	Actual Waste Generation Compared to Management Limits	63
6.0	SPACE SAVING ALTERNATIVES	69
7.0	BIBLIOGRAPHY	71

APPENDICES

Acronyms	A-2
--------------------	-----

TABLE OF CONTENTS (CONTINUED)

FIGURES

1. Comparison of the Tank Requirements for the 6/96 Projection Cases	2
2. Methodology of the OWVP	5
3. Double-Shell Tank Requirements for the Baseline Case	38
4. Double-Shell Tank Inventory and Space for the Baseline Case	40
5. Facility Waste Generation Graphic	43
6. Tank Fill Graphic	43
7. Tank Levels During Four-Year Projection	45
8. Simplified Schematic of Current and Planned Routings	46
9. Dilute Receiver Tanks and 242-A Evaporator Operations	50
10. PUREX Facility Waste Generation and Tank Levels	52
11. West Area Waste Generation and SY Tank Levels	53
12. B Plant and Hanford Facility Waste	54
13. AP Farm Tank Levels	55
14. AN Farm Tank Levels	56
15. Aging Tank Requirements	57
16. Aging Waste Tank Usage	58
17. Double-Shell Tank Requirements for the Lower Planning Case	60
18. Double-Shell Tank Requirements for the Upper Planning Case	62
19. Monthly Facility Generations	64
20. Comparison of Monthly Average Waste Generation to Target Rate	65
21. Monthly Contributions from SWL Pumping	66
22. Contributions from Facility TCO	67

TABLES

1. Summary of Assumptions for the June 1996 Projection Cases	3
2. Risk Assessment Summary for Waste Volume Projections	4
3. Salt Well Pumping Schedule for the Baseline Case	13
4. Operational Tanks and Usage	17
5. Summary of In-Tank Washing Activities	23
6. Projected Pretreatment Schedule for Phase I	24
7. Waste Compatibility Matrix	26
8. DST Solids Levels (Kgal)	27
9. Assumption Matrix	28
10. Spreadsheet of Waste Additions and Reductions for Baseline Case	39
11. Evaporator WVR and LERF Additions for the Baseline Case	47
12. Evaporator Campaign Schedule for the Baseline Case	48
13. Comparison of Average Monthly Waste Generation Rates	63
14. Facility Waste Storage and Capacity	68

1.0 SUMMARY

The Operational Waste Volume Projection (OWVP) presents a basis for evaluating future Double-Shell Tank (DST) space through FY 2015. This report presents a projected range of tank needs which is used to generate recommendations regarding site activities, waste management activities, facility requirements, and the need to build additional double-shell tanks. This document presents the results of three distinct projections cases (Baseline, Lower Planning, and Upper Planning Cases). Operating assumptions for the three cases were established prior to June 1996:

- o The Baseline Case presents projected DST needs based on TPA milestones, TWRS program planning, and the current operational assumptions. The Baseline Case does not require construction of additional DSTs through FY 2015.
- o The Lower Planning Case predicts the impacts of a delay in SWL pumping and SST solids retrieval. This projection does not exceed available space through FY 2015.
- o The Upper Planning Case presents the impacts of a one tank loss in FY 1998, an evaporator outage in 2003, and an evaporator shutdown from FY 2011 on. This projection, as expected, exceeds available space. The excess tank space requirements from 2013 on confirm the need to maintain evaporation capacity to avoid the need for building new tanks or delaying TPA milestones.

A comparison of the projected tank space needs required for the three projection cases is depicted in Figure 1. Key assumptions for the three projection cases are summarized in Table 1. Differences in assumptions have been highlighted. Detailed assumptions and space saving alternatives are presented later in this document. A brief summary of the risks associated with these projections is provided in Table 2. At a minimum, this DST space forecast will be updated annually with the latest information available regarding the estimated volume of waste requiring storage in the DSTs.

Areas Requiring Management Consideration

Facility waste minimization requirements initiated by the Tank Space Management Board (TSMB) helped to guarantee tank space availability prior to the 242-A Evaporator restart. However, considering the possibility of future tank space shortages, the Terminal Clean-out (TCO) and monthly waste generations will continually need to be minimized.

Should a tank space shortage occur during the projection period (Figure 1), the shortage could be solved using a combination of the following actions (see Section 6.0 for a more complete listing):

- o delay the Single-Shell Tank (SST) stabilization
- o delay the SST solids retrieval
- o accelerate pretreatment and vitrification of waste
- o construct new double-shell tanks
- o establish Phase II contract terms for privatization to require rates of retrieval and processing equivalent to TPA rates

Figure 1. Comparison of Tank Requirements For The 6/96 Projection Cases

Table 1. Summary of Assumptions For the June 1996 Projection Cases (references in Sect. 3)

Facility or Project	Baseline Case (L968C) Assumptions	Lower Planning Case (L96LC) Assumptions	Upper Planning Case (L96UC) Assumptions
Total Monthly Facility Generations	27.9-36.6 Kgal/month	27.9-36.6 Kgal/month	27.9-36.6 Kgal/month
PUREX TCO	TCO FY96 (0.045 Mgal DN)	TCO FY96 (0.045 Mgal DN)	TCO FY96 (0.045 Mgal DN)
B Plant TCO	TCO FY96-98 (0.125 Mgal DN)	TCO FY96-98 (0.125 Mgal DN)	TCO FY96-98 (0.125 Mgal DN)
100N Area TCO	TCO FY97 (0.014 Mgal DN & solids)	TCO FY97 (0.014 Mgal DN & solids)	TCO FY97 (0.014 Mgal DN & solids)
100K Area TCO	TCO FY97-00 (0.35 Mgal DN)	TCO FY97-00 (0.35 Mgal DN)	TCO FY97-00 (0.35 Mgal DN)
105 F & H Basin Cleanout	TCO FY00-03 (0.24 Mgal DN)	TCO FY00-03 (0.24 Mgal DN)	TCO FY00-03 (0.24 Mgal DN)
Evaporator Operation Outage	Yearly beyond 2015 None	Yearly beyond 2015 None	Yearly thru 2010 only FY 2003
Liquid Effluent Treatment Facility Startup Rate (Mgal/Year)	11/1995 50	11/1995 50	11/1995 50
SST Stabilization Porosity Saltcake/Sludge Complexed SWL Volume Pumped Volume Pumped 1997-98	50%/21% 1.75 Mgal 5.57 Mgal (1996-99) 4.47 Mgal (1997-98)	50%/21% 1.75 Mgal 5.57 Mgal (1996-2001) 2.45 Mgal (1997-98)	50%/21% 1.75 Mgal 5.57 Mgal (1996-99) 4.47 Mgal (1997-98)
PPP Stabilization	30 Kgal (FY 1996-2006)	30 Kgal (FY 1996-2006)	30 Kgal (FY 1996-2006)
Tank 101-SY Dilution (Date)	No Dilution until treatment (2011)	No Dilution until treatment (2011)	No Dilution until treatment (2011)
Tank 103-SY Dilution (Date)	No Dilution until treatment (2011)	No Dilution until treatment (2011)	No Dilution until treatment (2011)
SST Solids Retrieval 106-C solids (start; receiver tank) SST Solids Retrieval Start Rate SST Waste Retrieval Complete SST Site Closure Complete	FY 1997; Tank 102-AY 12/2003 2.8 Mgal in FY 2004-2005; 4.1 Mgal in FY 2006-2007; FY 2018 FY 2024	FY 1997; Tank 102-AY 12/2003 2.8 Mgal in FY 2004-2005; 1.7 Mgal in FY 2006-2007; FY 2018 FY 2024	FY 1997; Tank 102-AY 12/2003 2.8 Mgal in FY 2004-2005; 4.1 Mgal in FY 2006-2007; FY 2018 FY 2024
Phase I Privatization Processing startup	06/2002	06/2002	06/2002
LAW Pretreatment Rate (Mgal/Yr)	2.03 in 1st Year (6/2002-5/2003) 2.22 in 2nd Year	2.03 in 1st Year (6/2002-5/2003) 2.22 in 2nd Year	2.03 in 1st Year (6/2002-5/2003) 2.22 in 2nd Year
LAW Vendor Tanks LAW Intermediate Staging Tanks Entrained Solids Receipt Tank	2 (full) 2 1	2 (full) 2 1	2 (full) 2 1
Phase II Privatization Maximum Processing Rate, Mgal/Yr @ 7M Na HLW Vitrification startup	2011 22.1 2013	2011 22.1 2013	2011 22.1 2013
In-Tank Washing (FY 1998-2004) Consolidate NCAW solids Consolidate NCAW supernates to	Case 8 Modified No 101-AY + 1 DST	Case 8 Modified No 101-AY + 1 DST	Case 8 Modified No 101-AY + 1 DST
Evaporation Limit for Wastes--SpG	1.41	1.41	1.41
Spare Space	2.28	2.28	2.28
Contingency Tank	None	None	None
Loss of DST Space	None	None	1 Tank (1998)

Table 2. Risk Assessment Summary for Waste Volume Projections

RISK ASSESSMENT SUMMARY FOR WASTE VOLUME PROJECTIONS									
Technical/Program Basis for Waste Volume Projections	Confidence of Basis Being Accurate			Waste Volume Impact if Wrong			Consequence if Assumption Wrong		COMMENTS
	HIGH	MED	LO	MAJOR	MINOR	QUANTITY	MAJOR	MINIMAL	
Remaining SWL pumping volume is ~5.57 Mgal		X		X		Dependent on magnitude of change	X		Delay TPA milestones; Large concentrated volume; Section 3.8
CC waste and TRU sludge in Tank 102-SY are compatible			X	X		Dependent on magnitude of change	X		Could delay SWL pumping TPA milestones; Sect. 3.8
242-A Evaporator available without an outage to 2015		X		X		Dependent on magnitude of change	X		Tank Space Projections based on concentrated volumes; Sect. 3.2
Evaporation limit for new DSSF will be SpG of 1.41		X		X		Dependent on magnitude of change	X		Reduction in SpG could be required by safety; Sect. 3.2
Facility generations will not exceed Base Case levels		X			X	Dependent on magnitude of change		X	Small concentrated volume; could delay site cleanup; Sect. 3.0
Facility TCO volumes: PUREX < 0.045 Mgal B Plant < 0.125 Mgal 100 Areas < 0.6 Mgal		X			X	Dependent on magnitude of change		X	Could delay site cleanup; Sect. 3.0
No loss of DST space		X		X		1 mgal/tank	X		Sect. 3.23
LAW Phase I treatment starts FY02; ~2.2 Mgal/yr		X		X		Dependent on magnitude of change	X		Could delay SST solids retrieval (TPA); Sect. 3.18
LAW Phase II treatment starts FY11; 22.1 Mgal/yr		X		X		Dependent on magnitude of change	X		Could delay SST solids retrieval (TPA); Sect. 3.19
Crossite transfer lines are available		X		X		Dependent on magnitude of change	X		Could delay SWL pumping TPA milestones and/or site cleanup Sect. 3.12
Use Grout in emergencies to free up 2-3 Mgal of space			X	X		Dependent on magnitude of change	X		DOE and public acceptance unlikely; Sects. 3.3 & 5.1
No volume set aside for upsets or new streams			X		X	Dependent on magnitude of change	X		Consequences depend on volume, composition, and timing Sect. 3.21

2.0 INTRODUCTION

2.1 Purpose

The purpose of the Operational Waste Volume Projection (OWVP) is to present a basis for evaluating future Double-Shell Tank (DST) needs to meet Tri-Party Agreement Milestone (TPA) M-46-00. This report presents a projected range of tank needs which is used to generate recommendations regarding site activities, waste management activities, facility requirements, and the need to build additional DSTs. This document presents the results of three projections cases (Baseline, Lower Planning, and Upper Planning Cases) which represent varying degrees of tank space demands. All projection cases incorporate the "privatization" of waste treatment and disposal. The term "privatization" refers to the revised DOE strategy for treatment of Hanford tank wastes which would use private contractors to design, permit, build, operate, and deactivate the facilities for waste treatment and immobilization (DOE, 1995). The Baseline Case is intended to present tank space needs based on TPA milestones, TWRS program planning, and current operational assumptions. The Lower Planning Case was completed using assumptions requested which might lower tank space needs. The Upper Planning Case uses an assumption requested by the Washington Department of Ecology and others which will increase tank space needs. Operating assumptions for the three cases were established prior to June 1996. Need dates for new DST construction, tank retrievals, facility schedules, waste generation reductions, conflicts in meeting TPA milestones (WDOE, 1994; WHC, 1996a; WHC, 1996b), and funding priorities can then be reviewed in relation to tank space availability.

2.2 Methodology

The process followed in preparing an OWVP is shown in Figure 2, below.

Figure 2. Methodology of the OWVP

The process of updating the OWVP begins with the request for updated facility or project "assumptions" from each of the operating facilities and projects that will contribute waste to DST inventory. The term "assumption" in this document refers to engineering inputs or bases supplied by the facilities based on their future operational plans (determined by budget, DOE directive, TPA milestones, etc.). Typical assumptions include operating schedules, waste generation rates, stream compositions, modes of operation, etc. The operating facilities and projects provide estimates of volume, composition, and radionuclide content data for each distinct waste stream exiting the facility. In addition to the projected facility waste generation rates, the processing schedules of each of the plants are factored into the projection. For the Plutonium-Uranium Extraction (PUREX) facility, B Plant, and 100 Area facilities the projected volumes of waste generated from TCO are estimated and entered. For the Plutonium Finishing Plant (PFP), 300 Area, 400 Area, and Tank Farms, monthly waste generations are entered from facility inputs and/or actual observed generation rates. These projected waste generation rates and plant schedules are used to project waste volumes that each plant will be producing per month or year. The composition data is used to calculate Waste Volume Reduction Factors (WVRFs) and to determine waste segregation requirements (due to chemical, radionuclide, or heat content). The WVRF (Riley, 1988) is defined as the percent of water (by volume) that can be removed from a waste stream to achieve a certain interim waste form such as double-shell slurry feed. From the facility assumptions, a matrix of basic assumptions for the three cases to be incorporated into the OWVP projections were prepared and presented to WHC management and program office for approval.

Once the projection cases have been approved, the database of past waste gains, transfers, and evaporations is updated with data from the most recent months of Tank Farm operations. The early years of the projection are simulated in more detail than the later years. In the first period of the projection, monthly waste volumes are predicted. For the last years of the projection, yearly waste volumes are predicted.

The processing sequence in the simulation is designed to model the actual activities in the tank farms. After a dilute receiver tank is filled with waste, the contents are transferred to an available holding tank. The dilute waste must remain in the holding tank for at least four months to allow for sampling and characterization before it can be transferred to the 242-A Evaporator feed tank (Tank 102-AW) for evaporation. After dilute waste is concentrated in the 242-A Evaporator, it is sent to a slurry receiver tank (Tank 106-AW) as Double-Shell Slurry Feed (DSSF) which will eventually be disposed of through the Low-Activity Waste (LAW) pretreatment and vitrification process.

The processing sequence for the Neutralized Current Acid Waste (NCAW) solids is for the solids to be washed in-tank and then immobilized in the High-Level Waste (HLW) vitrification plant. The separated supernates and washes will be pretreated to form high-level and low-activity waste streams. The HLW vitrification facility will incorporate high-level and transuranic (TRU) wastes into a glass matrix for disposal. The low-activity waste stream will be sent to LAW vitrification for final disposal.

3.0 GENERAL FACILITY DESCRIPTIONS AND ASSUMPTIONS

A brief description of the facilities and projects pertinent to this projection are listed in the following section. Facility operating dates, waste generation volumes, WVRFs, flushes, and other pertinent assumptions are described. This information has been summarized for each of the three cases in Table 9, which is included at the end of this section. The spreadsheet for the Baseline Case (Section 5.1) lists the waste generations for each year for facilities that presented a range of waste generation rates (e.g., S Plant and T Plant).

3.1 B Plant/WESF

B Plant was constructed in 1945 to recover plutonium by the bismuth phosphate process. The facility was refurbished in 1967 to recover cesium and strontium byproducts from the high level waste tanks (Kutsch, 1996a). In 1974, the Waste Encapsulation and Storage Facility (WESF), was constructed on the west end of B Plant to support B Plant's mission. WESF's original mission was to encapsulate, cool, store, and monitor the high heat generating cesium and strontium capsules. The byproduct recovery mission was completed in FY 1984 and B Plant was once considered for waste pretreatment. B Plant is no longer considered a viable option for pretreatment of Hanford tank waste and is presently transitioning to shutdown in FY 1998.

B Plant discharges a low-level miscellaneous waste stream (dilute non-complexed waste) resulting from cell drainage, vessel clean-out, condensate collection, etc. Future TCO activities will generate wastes that can be separated into three categories (Smith, 1994): 1) aqueous phase waste generated during organic solvent removal (may be complexed waste); 2) dilute non-complexed (DN) waste; and 3) uncharacterized waste resulting from vessel flushing (assumed to be DN waste). Uncharacterized wastes will be characterized when they are produced.

B Plant/WESF projected miscellaneous waste generations for the Baseline Case (Kutsch, 1996b) were 9 Kgal/month during FY 1996 and 5 Kgal/month until plant stabilization has been completed. Cleanout and stabilization of B Plant is estimated to occur from FY 1996-1998 and will generate approximately 125 Kgal of additional uncharacterized (assumed to be dilute non-complexed in this projection) TCO wastes (Kutsch, 1996). When B Plant has completed TCO, WESF will continue to generate approximately 5 Kgal/year of waste from 1999-2028. The WVRF to evaporate either B Plant miscellaneous or TCO waste to DSSF is 99 (Sederburg, 1995). No flushes are anticipated for B Plant miscellaneous or TCO streams based on their dilute nature and lack of solids.

All three cases in this document were based on the waste generations described above. The upper waste rate supplied by B Plant engineers (Kutsch, 1996b) would increase the B Plant/WESF monthly waste generation from 5 Kgal/month to approximately 8 Kgal/month from 1997-1998.

3.2 242-A Evaporator and LERF

The 242-A Evaporator was restarted on April 15, 1994. To understand the projection model for the 242-A Evaporator, it is necessary to understand the waste flow during evaporator operation and the simulation model. Waste from

the dilute holding tanks are transferred into the evaporator feed tank (Tank 102-AW). Waste in the feed tank is then transferred to the 242-A Evaporator for boil-down. In the evaporator operation, four to six months is required for wastes to be sampled and analyzed per Evaporator DQO requirements (Von Bargen, 1995) before they can be evaporated.

- o This projection model assumed that the 242-A Evaporator would operate in a "Linked Run" process mode (Guthrie, 1993). A "Linked Run" is a continuous operation of the 242-A Evaporator, made possible by simultaneously transferring from the DST's to the Evaporator feed tank (Tank 102-AW).
- o A period of four to six months is required from the time a holding tank is filled with dilute wastes before the waste can be evaporated. This period allows time for sampling and analysis, documentation, and facility preparation (Guthrie, 1993). These projections assumed that a four month period would be required for these purposes.
- o In the computer simulation, dilute waste is transferred to the evaporator feed tank (Tank 102-AW) for evaporation. Provided the waste has not reached its concentration limit, the monthly evaporation is continued until the maximum Waste Volume Reduction (WVR) for the month is achieved.
- o The desired WVR for each 242-A Evaporator campaign is determined by boil-down studies, computer simulation, and/or process control sampling. The concentration of waste increases after each pass through the Evaporator until it reaches a concentration level consistent with engineering studies. The waste volume projection model of the 242-A Evaporator operation used in these projections cases produced DSSF with a specific gravity of 1.41. Upon reaching the desired concentration level, the concentrated waste is transferred to the evaporator receiver tank (Tank 106-AW). At the end of a campaign or when Tank 106-AW has been filled, DSSF is transferred to a holding tank.
- o The Liquid Effluent Retention Facility (LERF) with a 13 million gallon storage capacity was used to store the evaporator process condensate until the condensate could be treated.
- o The ratio of process condensate sent to LERF for every gallon of Waste Volume Reduction (WVR) for Evaporator Campaigns 94-1, 94-2, and 95-1 was 1.29, 1.24, and 1.26, respectively (Guthrie, 1996). The average for the first three campaigns was 1.26 gallon of condensate/gallon of WVR which was the value used in this document to project future condensate production. The evaporator seal water and demister spray upgrade could reduce future process condensate production to 1.15 gallon of condensate/gallon of WVR which would lower the value used for future projections. The Effluent Treatment Facility started to process the condensate stored in LERF Basins 42 and 43 in November 1995 and processed all stored condensate by August 1996 (Wagner 1996). Since the Effluent Treatment Facility has a capacity of approximately 50 Mgal/year (Wagner, 1996), it was assumed that LERF capacity would not limit future evaporator operations.

- o The maximum monthly WVR during Evaporator operation should be approximately 1500 kgal/month based on a near optimum Campaign 94-2 performance with approximately a 50% initial WVR per pass through the evaporator. (Guthrie, 1996).
- o An average evaporation rate of 750 Kgal/month (Guthrie, 1996) was used in this simulation taking in to consideration:
 - the 242-A Evaporator historical processing rates
 - downtime between campaigns
 - waste characterization
 - staging and tank transfers
- o The simulation used in this projection evaporates all dilute wastes to a concentrated interim storage form in the same year that a tank has been filled. This assumption is valid if the evaporator is operating and the yearly waste generation rate has not exceeded the annual WVR limit of the evaporator. Historically, dilute wastes were concentrated to near the aluminate boundary which would produce concentrated wastes with a specific gravity which could range from 1.3 to 1.67. However, it has been noted that all of the DSTs currently on the Flammable Gas Watch List (i.e., tanks with safety concerns related to hydrogen build-up) have specific gravities greater than 1.4 (Reynolds, 1994). To avoid production of future Flammable Gas Watch List tanks, it has been proposed that all future waste concentrations should be limited to a specific gravity of 1.41 unless additional technical evaluation shows flammable gas will not build-up (Fowler, 1995a and Fowler, 1995b).

The waste volume projection model of the 242-A Evaporator operation used in projections thru 1994, typically produced DSSF with a specific gravity of 1.50-1.55. Reducing these wastes to a specific gravity of 1.41 could increase waste storage volumes by approximately 22-35 percent, depending on the chemical composition of the waste. This document projected DST needs based on the evaporation of wastes to a specific gravity of 1.41.

- o The first Evaporator Campaign (94-1) started on April 15, 1994 and evaporated the wastes stored in Tanks 102-AW, 106-AW, and 103-AP. This campaign achieved approximately 2.42 Mgal of WVR.
- o The second Evaporator Campaign (94-2) started on September 22, 1994 and evaporated the wastes stored in Tanks 102-AW, 106-AW, 101-AP, 107-AP, and 108-AP. This campaign achieved approximately 2.79 Mgal of WVR.
- o The third Evaporator Campaign (95-1) started on June 8, 1995 and evaporated the wastes stored in Tanks 102-AW, 106-AW, 107-AP, and 108-AP. This campaign achieved approximately 2.16 Mgal of WVR.
- o The fourth evaporator campaign (96-1) started in May 1996 and evaporated dilute non-complexed wastes stored in Tank 104-AP (from Tanks 102-SY, 105-AW, and 102-AY). This campaign achieved 1.12 Mgal of WVR (Guthrie, 1996b).
- o The fifth evaporator campaign (97-1) is assumed to start in February 1997 to evaporate Tank 105-AP (dilute non-complexed waste from

Tank 101-AN). The sixth evaporator campaign (97-2) is assumed to start in the summer of 1997 to evaporate dilute complexed waste from Tanks 101-AY and 106-AN.

- o The Baseline projection assumed that evaporation capability would be available annually to evaporate all dilute wastes. The annual evaporation of dilute waste minimizes tank space requirements and allows site cleanup activities to continue unabated to allow completion of TPA milestones.
- o Previous projections assumed that the 242-A Evaporator would require a 1 year outage for maintenance and or upgrades every 10 years based on a 10 year design life of the 242-A Evaporator (WHC-EP-0342). The Baseline projection assumed the 242-A Evaporator would operate thru FY 2005 with additional evaporator capability coming on line in FY 2005 to allow annual evaporations through FY 2015.
- o Evaporator training runs prior to evaporator operation were estimated to add approximately 50 Kgal/year to tank farms and 50 Kgal/year to the LERF for evaporator certification training (Guthrie, 1996). The training run in April 1995, added 57 Kgal to DSTs.
- o Evaporator flushing after each campaign was previously projected to add 35 Kgal/campaign (Haigh, 1992). Actual flushes for the first three campaigns completed since April 1995 have varied from 27 to 58 kgal/campaign.
- o Projected waste generations for the 242-A Evaporator due to training/flushing for FY 1995 evaporator operations was 85 Kgal. For the years 1996-1999, it was estimated that 1 to 2 campaigns would be required each year based on waste generations, segregation requirements, and tank space availability. The additional operations would be needed to evaporate the anticipated increased SWL (complexed and non-complexed) and TCO wastes. Based on these considerations, the projected waste generation for the evaporator was increased to 100 Kgal/year for the period 1996-1999. From FY 2000 on, the estimated evaporator waste generation was reduced to 85 Kgal/year. The WVR for evaporation of these flushes to DSSF was 99 (Sederburg, 1995).

3.3 Grout

- o No additional Grout Vaults are scheduled to be poured at the Hanford site. TWRS program planning requires that all tank wastes be separated into low-activity and high-activity fractions and each fraction be immobilized into suitable waste forms for ultimate disposal. Tanks that were originally designated and set aside as grout feed tanks were used for other purposes.

3.4 Effluent Treatment Facility

- o A new facility called the Effluent Treatment Facility (ETF) started operation in November 1995 to process the stored evaporator condensate from the LERF, newly generated evaporator condensate, and aqueous waste water containing low specific radioactivity (Wagner, 1996). Treated

effluent is discharged to the State Approved Land Disposal Site (SALDS), north of the 200 West Area. This site was chosen to allow tritium to decay away before the groundwater migration reaches the Columbia River. The ETF does not remove tritium because no feasible production-scale tritium removal technology presently exists. The ETF has a capacity to treat 50 Mgal/year for future feeds. The ETF should not send any streams to DSTs.

3.5 PFP

The Plutonium Finishing Plant (PFP) is a facility in the 200 West Area which houses the processes and supporting operations for (Bergquist, 1996):

- 1) stabilization of reactive solid residues by muffle furnace calcination (OPERATIONAL);
- 2) shipping, receiving and storage of special nuclear materials (OPERATIONAL);
- 3) analytical and development laboratories (OPERATIONAL);
- 4) treatment and handling of PFP liquid wastes destined for tank farms and the ETF (OPERATIONAL).

An Environmental Impact Statement (EIS) was issued for public comment in November 1995 covering the PFP facility stabilization and clean out. Since the record of decision is not expected until late in FY 1996, the waste volume projection for PFP was based on the preferred alternative identified in the EIS for facility cleanout and stabilization. The volume of waste anticipated to be produced for the Baseline Case is developed from the existing waste generation rate at PFP (100 untreated gallons/month), and the anticipated use of a direct denitration vertical calciner coupled with an ion exchange pretreatment system currently being developed and tested by the development laboratories. The vertical calciner (Bergquist, 1996) is the most promising technology for plutonium residue stabilization and facility clean out. The Baseline Case would generate a total of 30 Kgal of waste from 1996 through 2006 (Bergquist, 1996). The WVRF to evaporate PFP wastes to DSSF is 81 (Sederburg, 1995). Flush volumes for PFP stabilization waste streams is 22 per cent (flushes of waste transfer lines from PFP to 244-TX and from 244-TX to Tank 102-SY).

Although the waste generations used for the Lower and Upper Planning Cases were the same as those used for the Baseline Case, generation volume for PFP stabilization could run as high as 36 Kgal for other stabilization methods (Bergquist, 1996). The percent solids experienced in past PFP waste generations are listed below (Barrington, 1991):

% Solids in PRF waste	3.5%
% Solids in RMC waste	4.4%
% Solids in lab waste	4.5%

3.6 PUREX

The Plutonium Uranium Extraction (PUREX) Facility was used to separate irradiated N Reactor fuel into plutonium nitrate, uranyl nitrate hexahydrate (UHN), neptunium nitrate, and waste products. The main processing operations involved dissolution of cladding and irradiated fuel, solvent extraction and

conversion of plutonium nitrate to plutonium oxide. Acid recovery, solvent treatment systems, and off-gas treatment supported the major processes.

Westinghouse Hanford Company has been directed by the Department of Energy (DOE) to proceed with deactivation of PUREX. A detailed plan for the deactivation of the PUREX facility was completed in the fourth quarter of FY 1993. Deactivation of PUREX started in April 1994 and will continue through FY 1997 (Ethington, 1996) with most of the waste being sent to DSTs by the end of FY 1996. It is assumed that all waste transfers from PUREX to the DST system will cease once deactivation has been completed.

The amount of waste remaining to be transferred from PUREX to the DSTs for all three projection cases was projected to be 45 Kgal of low level non-dangerous waste (Ethington, 1996). Based on the average waste composition presented for PUREX TCO wastes, the WVRf for evaporation of PUREX TCO wastes to DSSF is 99 (Sederburg, 1995). Flush volumes for PUREX TCO waste streams is 10 per cent.

3.7 S Plant

S Plant (or 222-S Labs) is a dedicated laboratory facility. The Laboratory currently provides analytical chemistry services in support of Westinghouse Hanford Company's processing plants and tank characterization. Emphasis is on waste management processing plants, environmental monitoring programs, B Plant, Tank Farms, 242-A Evaporator, Waste Encapsulation Storage Facility (WESF), PUREX Facility, Plutonium Finishing Plant (PFP), research support activities, and essential materials. Most of the radioactive liquid waste generated at the laboratory complex originates from analytical activities performed within the 222-S Laboratory in support of tank characterization (Collins, 1996). Radioactive and radioactive hazardous (mixed) wastes generated by the 222-S Laboratory are discharged to the 219-S Waste Handling Facility. Dilute, non-complexed wastes are currently being transported to 204-AR vault via tanker truck. Projected S Plant monthly waste generation rates (Collins, 1996) were approximately 8 Kgal/month for FY 1996 and 10 Kgal/month for FY 1997 through 2028 for the Baseline Case. All three projection cases used the same waste generation rates. Based on the waste composition presented for 222-S Laboratory wastes, the WVRf for evaporation of 222-S miscellaneous wastes to DSSF is 99 (Sederburg, 1995). Flush volumes for 222-S waste streams is 22 per cent.

3.8 Salt Well Liquid Pumping

Salt Well Liquid (SWL) pumping will occur for single-shell tanks (SSTs) which have 50,000 gallons or more of drainable interstitial liquid. Pumping is scheduled to stop when the output rate decreases to 0.05 gallons per minute. SWL pumping assumptions for all three projection cases are listed below:

- o The Baseline Case used a 50 percent saltcake porosity/21 percent sludge porosity resulting in a remaining volume of 5.57 million gallons (Brown, 1996) of SWL to be pumped from FY 1996 through the end of FY 1999 to meet TPA milestone M-41-00 (volume for Tank 106-C included with single shell tank solids retrieval). The schedule for SWL pumping (Saueressig, 1996) delays pumping of complexed SWL and flammable gas tank wastes in 200 W Area until FY 1998. The WVRf for evaporation of non-complexed SWL

to DSSF is 47 (Sederburg, 1995). The WVRF for evaporation of complexed SWL to Complexant Concentrate (CC) is 10 (Sederburg, 1995).

- o Flushing of the salt well liquid and transfer lines will generate approximately 1.45 Mgal (26 percent) of water (Brown, 1996). The WVRF used for this flush is 99 (Sederburg, 1995).
- o Approximately 1.75 Mgal (31 percent) of the total SWL volume is complexed based on available analytical information.
- o The pumping schedule for the Baseline Case is presented in Table 3 based on the March 5, 1996 Draft Interim Stabilization Tri-Party Agreement M-41-00 Recovery Plan (Saueressig, 1996). Total volumes were taken from Brown (1996) at 50% saltcake porosity/21% sludge porosity.

Table 3. Salt Well Pumping Schedule for the Baseline Case

Salt Well Pumping Schedule for 50% Saltcake/21% Sludge Porosity (Brown, 1996)					
FISCAL YEAR	EAST AREA		WEST AREA		TOTALS
	DN	DC	DN	DC	
1989	55 KGAL	0 KGAL	0 KGAL	17 KGAL	72 KGAL
1990	44 KGAL	0 KGAL	0 KGAL	0 KGAL	44 KGAL
1991	227 KGAL	0 KGAL	0 KGAL	0 KGAL	227 KGAL
1992	121 KGAL	0 KGAL	0 KGAL	0 KGAL	121 KGAL
1993	0 KGAL	0 KGAL	37 KGAL	0 KGAL	37 KGAL
1994	189 KGAL	0 KGAL	32 KGAL	0 KGAL	221 KGAL
1995	194 KGAL	105 KGAL	18 KGAL	0 KGAL	317 KGAL
1996	4 KGAL	0 KGAL	272 KGAL	0 KGAL	276 KGAL
1997	255 KGAL	494 KGAL	1399 KGAL	0 KGAL	2148 KGAL
1998	133 KGAL	395 KGAL	1265 KGAL	530 KGAL	2323 KGAL
1999	0 KGAL	23 KGAL	432 KGAL	317 KGAL	772 KGAL
2000	0 KGAL	0 KGAL	0 KGAL	0 KGAL	0 KGAL
TOTALS	1222 KGAL	1017 KGAL	3455 KGAL	864 KGAL	6558 KGAL

- o Total Amount of SWL to be pumped from FY 1996-1999 for the Baseline Case is approximately 5.57 Mgal without flush.
- o Tank 101-AN was designated as the East Area dilute non-complexed SWL receiver tank.
- o Tank 101-AY is currently designated as the East Area complexed SWL receiver tank. This projection assumed that the contents of Tank 101-AY were pumped to Tank 108-AP in late FY 1996 to allow Tank 101-AY to be

used for in-tank washing. Tank 108-AP would be the future receiver for East Area Complexed SWL.

- o Pumping SWL in West Area presents special problems due both to the limited tank space available and due to the transuranic (TRU) heel in Tank 102-SY. Tanks 101-SY and 103-SY contain complexed waste and are also designated as Watch List Tanks. Addition of waste to Watch List tanks is prohibited unless a safer alternative cannot be found.

Therefore, Tank 102-SY was designated as the West Area SWL receiver for both non-complexed and complexed SWL starting in FY 1998. Tank 102-SY contains approximately 133 Kgal of TRU solids (Table 8) that are not scheduled to be retrieved until 12/1998 (Barton, 1996). Historically, complexed waste and TRU wastes have been segregated to minimize the amount of waste requiring more expensive disposal and to comply with U.S. Department of Energy (DOE) Order 5820.2A. The Hanford Site has implemented this order by segregating waste that was considered complexed (greater than 10 grams/liter total organic carbon) from TRU waste sludge (Reynolds, 1995). The schedule presented in Table 3 would require pumping complexed SWL over the sludge in Tank 102-SY in order to meet TPA milestones for the years 1998-1999. Studies are being conducted to resolve this issue and to determine exactly how much of the waste in the 200 West Area are complexed (Estey, 1996). Some options include--delaying complexed SWL pumping in West Area until Tank 102-SY solids are retrieved; accelerating the retrieval of the TRU solids from Tank 102-SY; dilution and retrieval of the waste from either Tank 101-SY or 103-SY to free up additional tank space; conduct experiments to prove the complexed SWL can be added to the TRU solids in Tank 102-SY without solubilizing the TRU; or use a DCRT to pump complexed SWL to East Area without sending the waste to Tank 102-SY. In this projection, the complexed wastes are shown being pumped to Tank 102-SY to meet the revised TPA schedule (Saueressig, 1996).

3.9 Single-Shell Tank Solids Retrieval

- o The TPA start date for retrieval of Tank 106-C (M-45-03A) is October 1997 but this projection assumed that the start date for retrieval of Tank 106-C would be October 1996 to satisfy Safety Initiative 6e (Wang, 1994 and Grumbly, 1993). Retrieval of Tank 106-C solids will require approximately a 3:1 ratio of dilution water to solids (Estey, 1994). Solids retrieved from Tank 106-C will be stored in Tank 102-AY.
- o Approximately 12.2 Mgal of sludge and 23.4 Mgal of saltcake will be retrieved from SSTs (Hanlon, 1995). Dilution of these solids for retrieval and pretreatment results in a total of approximately 139 Mgal (Shelton, 1995).
- o Retrieval of the remaining solids from all 149 SSTs will begin in December 2003 (M-45-03-T1) and be completed by the end of FY 2018. Saltcake will be diluted to 5 M Na and sludge will be diluted to 10 weight percent solids. Approximately a 3:1 ratio of dilution water to solids will be required for the retrieval of the remaining SST solids. It is further assumed that all solids will be removed from the SSTs and that SST site closure will be complete by FY 2024 (M-45-06).

- o The retrieval schedule for SST solids for all three projection cases was based on Case P21B of the TWRS Disposal Program assumptions (Washenfelter, 1996a) with 0.7 Mgal of the retrieved waste volume shifted from 2004 to 2005. (Note: A different schedule was received too late to be included in these projection cases (Washenfelter, 1996b)). Approximately 2.8 Mgal (retrieved volume) of wastes would be retrieved during the period 2004-2005 beginning with Tanks 103-AX, 103-C, 102-A, and 105-C. The as retrieved volumes for the remaining SST solids are shown in the spreadsheet for the Baseline Case (Section 5.1) and are based on retrieval at 5 M Na. It was assumed that the as retrieved SST wastes would be concentrated to 7 M Na for storage purposes which increases evaporation needs during the period 2004-2015 (Washenfelter, 1996b).

3.10 Solid Waste Trench 31 Leachate

A leachate collected from the mixed waste landfill (Trench 31). The maximum daily leachate volume is estimated to be 110,000 gallons from the 24 hour/25 year precipitation event (McKenney, 1994). There is only a remote chance that this waste stream will be transferred to DSTs and this stream has not been included in any of the three projection cases.

3.11 T Plant

T Plant's primary mission is decontamination and treatment of radiologically and chemically contaminated waste and equipment located throughout the Hanford site (Triner, 1996). T Plant also provides inspection and repackaging services to various Hanford facilities and the certification (hydrostatic leak testing) of the railcars used to transport liquid wastes to Tank Farms. New railcars are being procured which will eliminate the need for hydrostatic leak testing and the projected waste volumes reflect this decrease. The 2706-T Low-Level Decontamination Facility (where low-level equipment decontamination is performed) is an approved decontamination facility that commenced operation in September 1994. Limited 221-T canyon decontamination activities (primarily Tank Farms long-length contaminated equipment) were initiated in 1995.

T Plant is currently testing new decontamination techniques (ice blasting and CO₂ decontamination systems) which have reduced liquid waste generations from those reported previously. Dilute, non-complexed wastes collected at T Plant during decontamination, repackaging, condensate collection, or railcar certification are currently being transported to 204-AR vault via railcar. These wastes contain approximately 5 % solids (Triner, 1996). Projected T Plant monthly waste generations (Triner, 1996) were based on a combination of anticipated work loads and actual observed generation rates. The projected volumes supplied by T Plant engineers decreased from 3.6 Kgal/month in FY 1996 to 2.5 Kgal/month in FY 2028 (waste volume generations for each year are shown in the spreadsheet for the Baseline Case--Section 5.1). All three projection cases used the same generation rates. The WVRf for evaporation of T Plant miscellaneous wastes to DSSF is 99 (Sederburg, 1995). Flush volumes for T Plant waste streams is 22 per cent.

3.12 Tank Farms

There are currently 28 double-shell tanks (DSTs) used to receive, store, and evaporate the liquid wastes generated at the Hanford facilities to an interim waste form. The interim waste form (e.g., DSSF) is currently stored in tank farms awaiting pretreatment and vitrification for final disposal. Tank farm waste generation sources and operational considerations are listed below for the aging and non-aging waste tanks. Tank Farm waste generations are primarily from line, cross-site, and air-lift circulator flushes.

Aging Double-Shell Tanks

Four of the DSTs (AY and AZ farms) are designated as aging waste tanks that were designed to store high-heat wastes (e.g., NCAW wastes or wastes containing high-heat loads due to the presence of ^{90}Sr or ^{137}Cs). The aging waste tanks are equipped with condensers and air-lift circulators. The purpose of the condensers is to handle the vapors from primary tank vent systems when hot liquid is present. Condensates are collected in catch tanks (e.g., 151-AZ, 152-AX, or TK-417) and returned either to an aging waste tank or to a dilute receiver tank. The air-lift circulators aid in suspending NCAW solids and in heat removal. Air-lift circulators require periodic flushing to prevent clogging.

Aging waste tank operation assumptions used in all three projections follow:

- o Aging waste tanks can be used for storage of dilute non-aging waste.
- o It is assumed that there will be no additional aging waste produced by the Hanford facilities. However, certain wastes containing high ^{90}Sr or ^{137}Cs contents may require storage in aging waste tanks due to their radioactivity.
- o Single-shell tank (SST) solids retrieved from Tank 106-C will be stored in an aging DST (Tank 102-AY) due to the high heat contents of the solids.
- o One million gallons of aging tank space is kept available for receiving the contents of an aging waste tank, in the unlikely event of a tank leak (Department of Energy order 5820.2A).
- o Tank 102-AY was designated as the 200 East Area dilute receiver for non-complexed wastes through mid FY 1996 and then Tank 106-AP was designated as the 200 East Area dilute receiver. This change allowed Tank 102-AY to be used to store the solids retrieved from Tank 106-C in FY 1997. Tank 106-AP is currently receiving direct transfers of wastes from B Plant, and rail or truck shipments via 204-AR vault from S Plant, T Plant, 100 Area, 300 Area, and 400 Area.

Non-Aging Double-Shell Tanks

The remaining 24 DSTs are called non-aging waste tanks and are used to store wastes that do not contain high-heat loads in accordance with applicable

operational and waste segregation policies. Non-aging waste tank operation assumptions are as follows:

- o Approximately 66 Kgal of caustic will be added to Tank 107-AN in FY 1997 to mitigate the low caustic condition in the tank for all projection cases (Carothers, 1996a and 1996b).
- o Operational tank usage for this projection are summarized in Table 4.
- o Starting in FY 1999, 0.72 Mgal of operational space in the evaporator Feed and Receipt Tanks (Tanks 102-AW and 106-AW) was used as spare space (Awadalla, 1995) in all three projection cases.
- o It was assumed that the TRU solids in Tank 102-SY would be retrieved to Tank 105-AW starting in December 1998 (Barton, 1996). The NCRW solids in Tank 105-AW were not combined with the solids in Tank 103-AW in this projection.

Table 4. Operational Tanks and Usage

Operation	Designated Tank
Evaporator Feed Tank	Tank 102-AW (modeled as a full tank)
Evaporator Receiver Tank	Tank 106-AW (tank level varies)
Dilute Receiver Tank	Tank 105-AW (PUREX direct transfers)
Dilute Receiver Tank	Tank 106-AP (1996-1999)
200 East SWL Receiver (DN)	Tank 101-AN
200 East SWL Receiver (DC)	Tank 108-AP
200 West SWL Receiver (DN)	Tank 102-SY
200 West SWL Receiver (DC)	Tank 102-SY
Private Contractor Feed Tanks	Tanks 106-AP and 108-AP
Intermediate Staging Tanks	Tanks 102-AP and 106-AP
Sr/TRU/Entrained Solids Return Waste	Tank 102-AZ (6/2002-mid FY 2003)
Sr/TRU/Entrained Solids Return Waste	Tank 101-AZ (mid FY 2003-2015)
Spare Tank Space	Tank 103-AP (1996-1998)

- o Flushes are generated during the receipt of waste transfers either from railroad tank cars, tanker trucks, or after tank to tank transfers. Percent flushes are included with a description of each of the facility generations in Section 3.
- o Some proposed tank usage changes were received too late to incorporate in these projections. These changes for the 200 East Area would include

the use of Tank 101-AN as the complexed SWL receiver and use of Tank 106-AP as the non-complexed SWL receiver (Hanson, 1996).

Projected waste generations for Tank Farms were based on a combination of previously observed waste generation rates and anticipated operational needs that are explained below:

- o Tank Farm water additions to DSTs. Tank Farms waste generation rates and flushing activities generally increase with the restart of the 242-A Evaporator due to the additional waste transfers. The 242-A Evaporator was restarted in April 1994. During the period April 1994 through May 1995, the average monthly waste generation rate for Tank Farms was 10.92 Kgal/month. The average monthly waste generation for Tank Farms during FY 1996 was 7.3 Kgal/month. The target rate set for Tank Farms waste generations was 10 Kgal/month. All three projection cases estimated that Tank Farms would generate 10 Kgal/month or 120 Kgal/year to cover transfer line and air-lift circulator flushes. The WVR for evaporation of these flushes to DSSF was 99 (Sederburg, 1995).
- o Cross-site Transfers. All projection cases assumed that either the existing cross-site transfer line or the new cross-site transfer line (Project W-058, scheduled to be completed in 1998) would be available to allow cross-site transfer of SWL, facility generations, DST solids from Tank 102-SY and/or SST solids. Without operable cross-site lines many of the TPA milestones involving West area wastes could not be achieved.

Previous projections have estimated that 50 Kgal of water (35 Kgal testing + 20 Kgal for transfer) would be needed for cross-site transfers. In this projection the water addition for cross-sites was reduced to 35 Kgal/transfer due to waste minimization actions defined for the FY 1995 transfer. During the period 1997-1999, approximately two cross-sites would be needed each year due either to the volume of SWL being pumped or to the pumping of non-complexed and complexed SWL through Tank 102-SY during the same year. Based on the projected cross-site testing and transfers anticipated, 70 Kgal/year was projected for the period FY 1996-2015. All three projection cases used the same volumes for cross-site transfer line tests and flushes. The WVR for evaporation of these flushes to DSSF was 99 (Sederburg, 1995).

- o Tank Fill Limits (except for special tank fill considerations):
 - AY, AZ Tanks: 980 Kgals
 - All other DSTs: 1140 Kgals
- o The assumptions used to simulate tank transfers in this projection are listed below:
 - Tank 102-SY: 879 Kgal in the tank, and PRF not operating, pumped down to 50 Kgal above solids.
 - Tank 102-AY: Start transfer at 900 Kgal.
 - Tank 105-AW and other dilute receivers: Start transfer at 1000 Kgal, pump down to 50 Kgal above solids.

3.13 UO₃ Facility

The UO₃ Facility concentrated and calcined uranyl nitrate hexahydrate (UNH) recovered by the PUREX plant to produce uranium oxide (UO₃) and nitric acid (HNO₃). Until now, the UO₃ Facility has not produced any DST wastes. Rainwater collected at the facility will be sent to cribs.

3.14 Waste Sampling and Characterization Facility (WSCF)

The Waste Sampling and Characterization Facility (WSCF) was started in FY 1994. This projection assumed that WSCF would send its waste to ETF and not to DSTs (Collins, 1996).

3.15 100 Area

100-N Basin

The 100-N Basin was constructed in 1963 to receive irradiated fuel assemblies discharged from the N Reactor for the purpose of inspection, storage, and preparation for shipment. In 1988 the N Reactor was placed in a "cold standby" status (shutdown but capable of restarting). In 1989 all nuclear fuel was removed from N Basin and transferred to K Basin. In 1991 the Department of Energy-Richland (DOE-RL) directed Westinghouse to begin deactivation activities. A significant quantity of radioactively contaminated equipment, hardware, debris, and sediment have accumulated in 100-N Basin that will need to be removed. Deactivation of the N Basin Facility will occur over the period FY 1996 through 1997. For the Baseline Case, it was assumed that N Basin water and Emergency Dump Basin water would be transferred to ETF for processing (Greenidge, 1996). Approximately 524 gallons of sediment would be slurried in 13,000 gallons of North Cask Pit residual water and transferred to DSTs in FY 1997. The same waste generation volume was used for all three cases.

100-K Basin

Fuel handling operations have resulted in some cladding damage to N-Reactor fuel. Subsequent fuel oxidation resulted in fuel and fission products accumulating in fuel canisters and in K Basin where the fuel handling occurred. Aluminum oxide, iron oxide, concrete grit, and other debris has accumulated and mixed with the fuel corrosion products to form a sludge on the basin floor. Approximately 350 Kgal of water and sediment (approximately 18.5 Kgal of sediment) would be transferred to DSTs (Alderman, 1996). Transfers would occur on a monthly basis over a four year period (1997-2000). The above generations for 100-K Basin cleanout were used in all three projection cases. (Late Note: Generations from 100-K Basin could be delayed until 1999 and be received on a weekly basis).

105-F & 105-H Basins

Plans to cleanout the 105-F and 105-H Basins are still being reviewed and the date of cleanout is uncertain due to funding. The projected plan is to clean out the 40,000 gallons in 105-F in the year 2000 and the 200,000 gallons from 105-H in the year 2003 (Griffin, 1996). These assumptions for 105-F and 105-H Basin cleanout were used for all three projection cases.

The WVRF for evaporation of all 100 Area Basin wastes to DSSF is 99 (Sederburg, 1995). Flush volumes for 100 Area wastes is 44 per cent.

3.16 300 Area

Facilities in the 300 Area are used primarily for research and development activities or for analytical support. Some waste received in FY 1995 was generated by decon of facilities. Liquid wastes from the various 300 Area facilities are transferred to the 340 Facility. Liquid wastes collected at the 340 Facility are transferred to 204-AR vault in 20,000 gallon railroad tank cars. Facilities in the 300 Area sent 58 Kgal of waste to DSTs (4.8 Kgal/month) in FY 1995. The Baseline Case projected 4.5 Kgal/month of miscellaneous waste would be generated from 300 Area facilities (Halgren, 1995b). All three projection cases used the same generation rates. Based on the chemical composition supplied for 300 Area waste streams (Halgren, 1995a), the WVRf for evaporation of 300 Area miscellaneous wastes to DSSF is 94 (Sederburg, 1995). Flush volume for 300 Area waste streams is 44 per cent.

3.17 400 Area

There are three major facilities in the 400 Area (Miller, 1996). These include the Fast Flux Test Facility (FFTF), the Maintenance and Storage Facility (MASF), and the Fuel and Material Examination Facility (FMEF). Radioactive liquid waste is primarily generated in conjunction with the removal of residual sodium from reactor components or with decontamination activities. A phased process was begun in December 1993 to place the FFTF into a radiologically and industrially safe shutdown condition. Shutdown of the FFTF has increased the amount of liquid waste generated by the plant's Sodium Removal System. Approximately 11 Kgal of wastes were received from 400 Area in FY 1994-1995 (~0.5 Kgal/month). The Baseline Case projected 0.5 Kgal/month of miscellaneous waste would be generated from 400 Area facilities. All three projection cases used the same generation rates. The WVRf for evaporation of 400 Area miscellaneous wastes to DSSF is 94 (Sederburg, 1995). Flush volume for 300 Area waste streams is 44 per cent.

3.18 Phase I Privatization Processing

- o Privatization Concept. The revised DOE strategy for treatment of Hanford tank wastes, termed "privatization," would use private contractors to design, permit, build, operate, and decommission the facilities for waste treatment and immobilization (DOE, 1995). Final details of the privatization work will not be developed until later in the process and the assumptions listed below are subject to change. As currently proposed, privatization would be divided into two phases. Phase I would include privatization of waste tank supernatant pretreatment, Low-Activity Waste (LAW) immobilization, and an optional High-Level Waste (HLW) immobilization (Washenfelder, 1996b) by two private contractors. The scale of processing during Phase I of privatization has been established to demonstrate the technical and commercial capability. Phase II of privatization would include additional tank waste retrieval, supernatant pretreatment, sludge/solid pretreatment, LAW immobilization, HLW immobilization, disposition of encapsulated Cs/Sr, and interim storage of immobilized waste (Washenfelder, 1996b).

- o Phase I Schedule. The target schedule for Phase I is summarized below and may slightly exceed TPA dates:

-Contract Award for Phase 1A	August 31, 1996
-Start construction	December 31, 1999
-Operations	June 1, 2002-June 1, 2011

- o Waste Staging Tanks. It was assumed that Tanks 106-AP and 108-AP would be transferred to the two private contractors in FY 2000. At the time these tanks were transferred to the private contractors they were filled with the initial feed to be processed in Phase I.

Tanks 102-AP and 104-AP were used for intermediate staging of wastes by the Project Hanford Management Contractor (PHMC). Wastes from Tanks 102-AP and 104-AP were transferred to Tanks 106-AP and 108-AP, respectively, approximately one month before the scheduled pretreatment date. Intermediate feed staging requires that Tanks 102-AP and 104-AP are then immediately refilled with the next scheduled batch of feed. A nominal 10 days are allocated for setup and transfer of feed to the intermediate feed staging tanks - this is small enough to be modeled with an immediate refill (Certa, 1996).

- o HLW Pretreatment and Immobilization. Phase I processing of tank waste sludges would be conducted within existing DSTs and would involve sludges in Tanks 101-AZ, 102-AZ, 102-AY, and the high heat solids retrieved from single-shell tank 106-C. In Revision 21 of this document, it was assumed that all NCAW solids and the 106-C solids would be combined into one aging waste tank (Tank 102-AZ) and that all NCAW supernates would be concentrated into one aging waste tank (Tank 101-AZ). Since that document was published, studies have been completed which looked at numerous sludge washing/combination options (Powell, 1996a and 1996b). The alternatives for consolidating high heat sludges have been reviewed by a decision board comprised of WHC management, a DOE/RL representative, and a WDOE representative. It was concluded that consolidating all the sludges into a single tank would require modifications to the tank farm safety basis. The preliminary decision reached was not to consolidate all the high heat sludges into a single tank. The selected alternative (Alternative 8 Modified) would wash the sludges in the tanks they reside in without additional consolidation of solids. The NCAW supernates could not be combined into a single aging tank (Tank 101-AY) due to the 5 M Na limit but would be concentrated and sent to Tank 101-AY and an additional non-aging tank (Powell, 1996b). The in-tank washing assumptions summarized in Table 5 and presented below are preliminary and subject to change in future revisions of this document.

In-Tank Washing of Tank 101-AZ Sludge

- o The first step of in-tank washing for all three projection cases involved the decanting of supernatant from Tank 101-AZ to Tank 101-AY (contents of Tank 101-AY previously transferred to AP Farm) in FY 1997 (Wasenfelder, 1996b). The decanted aging waste supernate from Tank 101-AZ would require storage in an aging waste tank due to its heat content.

- o Approximately 280,000 gallons of wash solution (0.1 M sodium hydroxide, 0.011 M sodium nitrate) is added in November 1997. The solids are mobilized with mixer pumps, settled for one month, and the wash is decanted in January 1998 to a non-aging DST.
- o The washed NCAW solids would then be sampled to determine the effectiveness of the washing process. Finally, approximately 160,000 gallons of solution (0.1 M sodium hydroxide, 0.011 M sodium nitrate) would be added to the washed NCAW solids in May 1998. This solution would be used to mix and transfer the washed solids to the private contractors for disposal during the period June 2002 through January 2003.

In-Tank Washing of Tank 102-AZ Sludge

- o The supernatant from Tank 102-AZ is concentrated in-tank and then decanted in October 2000. A portion of this supernatant would go to Tank 101-AY with the remainder going to non-aging DSTs. Due to questions about the allowable final Na concentration and the amount of heat in the supernatant, storage of the remaining supernatant could require one or two additional DSTs (Powell, 1996a and 1996b). The projection cases assumed this supernatant would be stored in Tank 101-AY plus one additional non-aging DST.
- o Approximately 230,000 gallons of wash solution (0.1 M sodium hydroxide, 0.011 M sodium nitrate) is added in November 2000. The solids are mobilized with mixer pumps, settled for one month, and the wash is decanted in January 2001 to a non-aging DST. This washing process is repeated again in the period February to April 2001 with the addition of 160,000 gallons of wash solution.
- o The washed NCAW solids would then be sampled to determine the effectiveness of the washing process. Finally, approximately 130,000 gallons of solution (0.1 M sodium hydroxide, 0.011 M sodium nitrate) would be added to the washed NCAW solids in May 2001. This solution would be used to mix and transfer the washed solids to the private contractors for disposal during the period August 2003 to January 2005.

In-Tank Washing of Tank 102-AY/Tank 106-C Sludges

- o The supernatant from Tank 102-AY is decanted from Tank 102-AY in October 2003. This supernatant would be transferred to a non-aging DST for further evaporation.
- o Approximately 320,000 gallons of wash solution (0.1 M sodium hydroxide, 0.011 M sodium nitrate) is added in November 2003. The solids are mobilized with mixer pumps, settled for one month, and the wash is decanted in January 2004 to a non-aging DST. This washing process is repeated again during the period November 2003 through May 2004.
- o The washed NCAW solids would then be sampled to determine the effectiveness of the washing process. Finally, approximately 320,000 gallons of solution (0.1 M sodium hydroxide, 0.011 M sodium nitrate) would be added to the washed NCAW solids in June 2004. This solution would be used to mix and transfer the washed solids to the private

contractors for disposal during the period June 2005 through February 2008.

- o All three projection cases assumed that approximately 340 metric tons of high-level waste oxides would be transferred to the vendor for immobilization during the period June 2002 through June 2008. It was assumed that this action would process all solids from Tanks 101-AZ, 102-AZ, 102-AY, and 106-C. The private contractor would provide a tank for receipt of the washed sludges; existing DSTs would not be used for these functions (Washenfelter, 1996b).
- o In-tank washing activities and waste work-off for the modified alternative 8 case are summarized in the following table.

Table 5. Summary of In-Tank Washing Activities
(Modified Alternative 8)

Date	In-Tank Washing Activity
Sept. 1997	Complete retrieval of Tank 106-C solids into Tank 102-AY.
Oct. 1997	Decant the NCAW supernate from Tank 101-AZ to Tank 101-AY.
Nov. 1997-April 1998	Wash NCAW solids in Tank 101-AZ twice.
May 1998	Sample Tank 101-AZ solids and cover with liquid.
Oct. 2000	Decant Tank 102-AZ supernatant to Tank 101-AY and two other non-aging DSTs.
Nov. 2000-April 2001	Wash NCAW solids in Tank 102-AZ twice.
May 2001	Sample Tank 102-AZ solids and cover with liquid.
June 2002-Jan. 2003	Transfer Tank 101-AZ solids to contractors.
Aug. 2003-Jan. 2005	Transfer Tank 102-AZ solids to contractors.
Oct. 2003	Decant supernatant from tank 102-AY to a non-aging DST.
Nov. 2003-May 2004	Wash solids in Tank 102-AY (existing solids plus Tank 106-C solids) twice.
June 2004	Sample Tank 102-AY solids and cover with liquid.
June 2005-Feb. 2008	Transfer Tank 102-AY solids to contractors

- o Low-Activity Waste (LAW) Treatment. The current DOE strategy calls for a demonstration of LAW treatment and immobilization by two private vendors at a rate dependent on the type of waste being processed. Envelope A wastes are defined as double-shell slurry feed (DSSF), double-shell slurry (DSS), and dilute non-complexed waste (DN). Envelope B wastes are NCAW supernatants. Envelope C wastes are primarily complexant concentrate (CC). Minimum and maximum processing quantities for each contractor are listed below:

Waste Type	Minimum Amount Processes (Metric Tons Sodium)	Maximum Amount Processes (Metric Tons Sodium)
Envelope A	2600	4900
Envelope B	100	1000
Envelope C	100	2400
Total A+B+C	---	5100

All projection cases assumed that each contractor would process the maximum quantity of waste.

- o **Schedule for LAW Pretreatment.** The schedule used for pretreatment of LAW is shown below in Table 6. Tank dilutions, contractor number, and multiple batches are not shown. This schedule was developed from input supplied by Washenfelter (1996b) except for known tank usage changes (the second feed tank is now Tank 105-AP and not Tank 106-AP as shown in Revision 21 of this document, etc.). Solids are left in the tanks when wastes are retrieved for LAW pretreatment.

Table 6. Projected Pretreatment Schedule for Phase I

Tank	Waste Type	Envelope	Vol(Kgal) w/ solids	MT Na approx.	Existing or Future Waste	Processing Start
105-AN	DSSF	A	1110	1186	Existing	6/ 1/2002
105-AP	DSSF	A	1140	1238	Future	4/20/2003
104-AN	DSSF	A	1061	834	Existing	3/21/2004
101-AW	DSSF	A	1127	906	Existing	11/12/2004
103-AN	DSS	A	955	1216	Existing	7/24/2005
101-AY	NCAW Supern	B	978	250	Future	6/19/2006
107-AN	CC	C	1057	778	Existing	9/19/2006
102-AN	CC	C	1082	1004	Existing	5/29/2007
106-AN	CC	C	1136	1485	Existing	3/ 2/2008
107-AP	CC	C	1104	1169	Existing	1/19/2009
101-AP	DSSF	A	1140	134	Future	12/ 6/2009

- o **Storage of Separated Sr/TRU and Entrained Solids.** Entrained solids and transuranic (TRU) elements removed from LAW waste by the private contractors were assumed to be returned to one DST for storage. Tank space was tight enough in FY 2002-3, that the Sr/TRU and entrained solids stream being returned from Phase I treatment is temporarily sent to Tank 102-AZ. By mid 2003, the solids have been removed from Tank 101-AZ and this stream is sent to Tank 101-AZ from this time until the end of the projection.

3.19 Phase II Privatization Processing

The scale of processing during Phase I of privatization has been established to demonstrate the technical and commercial capability. Phase II of privatization would include the remaining tank waste retrieval, supernatant pretreatment, sludge/solid pretreatment, LAW immobilization, HLW immobilization, disposition of encapsulated Cs/Sr, and interim storage of immobilized waste (Washenfelder, 1996b). The proposed target schedule for Phase II processing is summarized below:

o Contract Award	2004
o Design, permitting, licensing, construction, and startup	
-Low-Activity Wastes	2005-2011
-High-Level Wastes	2005-2013
o Operations	
-Low-Activity Wastes	2011-2021
-High-Level Wastes	2013-2028
o Estimated Processing Rates	
-Liquid Wastes, Mgal/yr @ 7M Na	22.1
-Solid Wastes, Mgal/yr	1.24

3.20 Watch List/Safety

- o All three projection cases assumed that agitation using a mixer pump would continue to be used for mitigation of the flammable gas buildup in Tanks 101-SY and 103-SY. It was assumed that these tanks would not require dilution until just prior to retrieval for pretreatment which was scheduled to start in Phase II. To allow use of Tanks 101-SY and 103-SY for SST solids retrieval, it was assumed that these two tanks needed to be cleaned out early in Phase II. Tanks 101-SY and 103-SY were diluted 1:1 and transferred to East Area during FY 2010-2011 to meet the pretreatment schedule.

3.21 Spare/Contingency Space

- o A total of 2.28 million gallons (one aging and one non-aging tank) of spare space was reserved in case of a leak in an aging waste tank (DOE Order 5820.2A) for all three projection cases. From 1999 on, 0.72 Mgal of the operational space in Tanks 102-AW and 106-AW was designated as spare space (Awadalla, 1995) in all three projection cases.
- o At the request of WHC and DOE management, one tank of contingency space has usually been set aside in the long range projection (1999 on) to account for possible inaccuracies in the WVP software when projecting waste generations and/or waste volume reduction factors. To minimize tank space needs, no contingency space is set aside in any of the three projection cases (Awadalla, 1995).

3.22 Waste Segregation

Waste segregation and compatibility are requirements of DOE Order 5820.2A (DOE, 1990) and WAC 173-303-395 (Dangerous Waste Regulations). The overriding purpose of waste

segregation and compatibility are to ensure the safety of waste storage and tank farms operations; to minimize future pretreatment costs; and to comply with DOE Order 5820.2A and WAC 173-303-393. Wastes that are typically segregated include:

- Phosphate Wastes--dilute phosphate (DP) or concentrated phosphate (CP).
- Wastes Containing High Organic Concentrations--dilute complexed (DC) or complexant concentrate (CC).
- TRU containing wastes--Neutralized Cladding Removal Wastes (NCRW solids) or PFP solids (PT).
- Watch list tank wastes to prevent inadvertent commingling with other wastes.
- Pretreated waste streams.
- Washed NCAW solids, etc.
- Concentrated interim waste types--e.g., double-shell slurry feed (DSSF) or double-shell slurry (DSS) need to be separated from dilute wastes to prevent the need to reconcentrate.
- Wastes exhibiting exothermic reactions.

All three projections assume that current waste segregation practices are observed with the exception of SWL pumping in 200 West Area as discussed in Section 3.8. Waste segregation practices are summarized in Table 7 (Fowler, 1995).

Table 7. Waste Compatibility Matrix

		Receiver Waste Type							
		DN	DSSF	DC	CC	(PD) NCRW	PT	NCAW	CP
Source Waste Type	DN	X	X	X	X	X	X	X	X
	DSSF	X	X						
	DC			X	X*				
	CC			X*	X				
	(PD) NCRW SOLIDS	X				X	X		
	(PT) PFP SOLIDS	X				X	X		
	NCAW							X	
	CP								X

(*) Adding CC to DC is permitted but would not ordinarily be done. The volume of combined waste which would need to be evaporated would be increased, resulting in increased evaporation costs.

3.23 Loss of DST Space

Corrosion studies completed to date (Anantamula and Ohl, 1996) show a 40-60% chance of a pit corrosion failure occurring in a DST by FY 2028. Some of the corrosion potential could be mitigated by maintaining a corrosion control program for the DSTs. In the Baseline Case, it was assumed that none of the DSTs would be removed from service by the end of FY 2015.

3.24 New DST Construction

All three projection cases assumed that no new DSTs would be constructed by 2015.

3.25 DST Tank Solids Levels

Solids levels in the DSTs are shown in Table 8 (Hanlon, 1996; Estey and Guthrie, 1996; and Koreski, 1995). Solids levels have been estimated for the tanks marked with an asterisk (*) based on the previous solids level measurement and the percent solids in facility generations that have been added to the tank since the last solids level measurement. Tanks with no solids level listed have either not been measured or have a minimal solids volume. The total DST solids used for this projection was approximately 5.045 Mgal.

Table 8. DST Solids Levels (Kgal)

TANK	SOLIDS	TANK	SOLIDS	TANK	SOLIDS	TANK	SOLIDS
101-AY	83	101-AN	33	101-AP		101-AW	344
102-AY	32	102-AN	89	102-AP		102-AW	36
101-AZ	35	103-AN	413	103-AP		103-AW*	487
102-AZ	95	104-AN	495	104-AP		104-AW*	390
101-SY	605	105-AN	560	105-AP	154	105-AW	300
102-SY*	133	106-AN	17	106-AP		106-AW*	225
103-SY	385	107-AN	134	107-AP			
				108-AP			

3.27 IMUST Wastes

Approximately 500 kilogallons of wastes are projected to be received from Independent Miscellaneous Underground Storage Tanks (IMUSTs) between FY 2011 and 2015 (Wacek, 1996). This is a new waste type added to these projections that will be updated in the future.

3.28 Assumption Summary

Assumptions used for all cases are presented in Table 9.

Table 9. Assumption Matrix
For the 1996 Operational Waste Volume Projection
 (All Years are Fiscal Years)

	TPA Baseline	Lower Planning	Upper Planning
	Case	Case	Case
<u>Meets TPA Milestones</u>	Yes	No	Yes
<u>Facility Generations</u>			
Total Limit, Kgal/mo	27.9-36.6	27.9-36.6	27.9-36.6
<u>PUREX</u>			
Monthly Rate, Kgal/mo	0	0	0
TCO Scheduled	1996	1996	1996
TCO Volume, Kgal	45 DN	45 DN	45 DN
Flush for TCO	10%	10%	10%
WVRF for TCO (to DSSF)	99	99	99
<u>B Plant/WESF</u>			
Monthly Rate, Kgal/mo	9 (1996)	9 (1996)	9 (1996)
Monthly Rate, Kgal/mo	5 (1997-1998)	5 (1997-1998)	5 (1997-1998)
Monthly Rate, Kgal/mo	0.5(1999-2028)	0.5(1999-2028)	0.5(1999-2028)
Flush for misc. waste	0%	0%	0%
WVRF, misc. waste(to DSSF)	99	99	99
TCO Scheduled	1996-1998	1996-1998	1996-1998
TCO Volume, Kgal DN	125	125	125
Flush for TCO	10%	10%	10%
WVRF for TCO (to DSSF)	99	99	99
<u>S Plant</u>			
Monthly Rate, Kgal/mo	8 (1996)	8 (1996)	8 (1996)
Monthly Rate, Kgal/mo	10 (1997-2028)	10 (1997-2028)	10 (1997-2028)
Flush for misc. waste	22%	22%	22%
WVRF, misc. waste(to DSSF)	99	99	99
<u>T Plant</u>			
Monthly Rate, Kgal/mo	2.5 to 3.6	2.5 to 3.6	2.5 to 3.6
Flush for misc. waste	22%	22%	22%
WVRF, misc. waste(to DSSF)	99	99	99
<u>300 Area</u>			
Monthly Rate, Kgal/mo	4.5	4.5	4.5
Flush for misc. waste	44%	44%	44%
WVRF, misc. waste(to DSSF)	94	94	94
<u>400 Area</u>			
Monthly Rate, Kgal/mo	0.5	0.5	0.5
Flush for misc. waste	44%	44%	44%
WVRF, misc. waste(to DSSF)	94	94	94
<u>IMUST</u>			
Tot. Volume, Kgal (2011-15)	500	500	500
<u>Tank Farms</u>			
Monthly Rate, Kgal/mo	10	10	10
WVRF, flushes (to DSSF)	99	99	99

**Table 9. Assumption Matrix
For the 1996 Operational Waste Volume Projection
(continued)**

	TPA Baseline Case	Lower Planning Case	Upper Planning Case
<u>100 Area</u>			
<u>100-N</u>			
TCO Scheduled	1996-1997	1996-1997	1996-1997
TCO Waste Received	1997	1997	1997
TCO Volume, Kgal	13.5	13.5	13.5

<u>100-K Basin Cleanout</u>			
TCO Scheduled	1997-2000	1997-2000	1997-2000
TCO Volume, Kgal	350	350	350

<u>105-F & 105-H Basin</u>			
TCO waste in 2000, Kgal	40	40	40
TCO waste in 2003, Kgal	200	200	200

Flush, ALL 100 Area Waste	44%	44%	44%
WVRF, ALL TCO waste(to DSSF)	99	99	99
<u>Solid Waste Mixed Waste Trench 31 Leachate</u>			
Monthly Rate, Kgal/mo	0	0	0
WVRF (to DSSF)	99	99	99
<u>Tank 107-AN Caustic Addition</u>			
Addition in 1997 (Kgal)	66	66	66
<u>Salt Well Liquid Pumping</u>			
Volume remaining (Mgal)	5.57	5.57	5.57
Volume pumped in 1996	0.276	0.276	0.276
Volume pumped in 1997	2.148	1.250	2.148
Volume pumped in 1998	2.323	1.200	2.323
West Area Receiver	Tank 102-SY	Tank 102-SY	Tank 102-SY
Start Complexed SWL in 200W	1998	1999	1998
Pumping Completion, FY	1999	2001	1999
Dilute Complexed SWL (Mgal)	1.75	1.75	1.75
Porosity saltcake/sludge	50%/21%	50%/21%	50%/21%
Flush for SWL Pumping	26%	26%	26%
WVRF, non-complexed (to DSSF)	47	47	47
WVRF, complexed (to DSSF)	10	10	10
<u>Single-Shell Tank (SST) Solids</u>			
Tank 106-C Retrieval	1997	1997	1997
Start Remaining SST Retvl	2004	2004	2004
Tank Farm Closure start	2018	2018	2018
Approximate Dilution Ratio	3:1	3:1	3:1
Retrieved Vol 2004-2005(Mgal)	2.8	2.8	2.8
Retrieved Vol 2006-2007(Mgal)	4.1	1.7	4.1
Meets TPA Milestones	Yes	Yes	Yes
No. SSTs Retrieved	149	149	149
Sludge Retrieved (Mgal)	12.2	12.2	12.2
Saltcake Retrieved (Mgal)	23.4	23.4	23.4

Table 9. Assumption Matrix
For the 1996 Operational Waste Volume Projection
(continued)

	TPA Baseline Case	Lower Planning Case	Upper Planning Case
<u>PFP Stabilization</u>			
Dates	1996-2006	1996-2006	1996-2006
Volume, Kgal	30	30	30
Flush	22%	22%	22%
WVRF	81	81	81
<u>Evaporator</u>			
241-A Shutdown	~2005	~2005	2010
New Evaporator (Privatize)	2005	2005	None
Next Outage Date	None	None	2003
Evaporation Product	dDSSF	dDSSF	dDSSF
Evaporation Limit (g/ml)	1.41	1.41	1.41
LERF capacity (Mgal)	13	13	13
Gal. condensate/gal. WVR	1.26	1.26	1.26
Yearly evaporation of DN (i.e., maintain currency)	Yes	Yes	No
<u>Effluent Treatment Facility</u>			
Start date (mo/yr)	11/1995	11/1995	11/1995
Rate (Mgal/year)	50	50	50
<u>Watch List/Safety</u>			
101-SY Dilution & date	None	None	None
103-SY Dilution & date	None	None	None
Require cross-site transfer	No	No	No
<u>Spare/Contingency Space</u>			
Spare Space, Mgal	2.28	2.28	2.28
Use 0.72 Mgal of Operational space in 106-AW as part of spare space from 1999 on	Yes	Yes	Yes
Contingency space, Mgal	None	None	None
-date	N/A	N/A	N/A
<u>Waste Segregation/DST Solids</u>			
Total DST solids (Mgal)	5045	5045	5045
Store DSSF on NCRW solids	Yes	Yes	Yes
Store DSSF on NCAW solids	No	No	No
Segregate Complexed wastes	Yes	Yes	Yes
<u>Loss of DST Space</u>			
Number Tanks Removed from Service	None	None	1
Date Tank Removed	N/A	N/A	1998
<u>New DST Construction</u>			
Date Constructed	None	None	None
	N/A	N/A	N/A
<u>New Cross-Site Transfer Line</u>			
Start Construction (TPA)	11/1995	11/1995	11/1995
Operational (TPA)	02/1998	02/1998	02/1998
Old line operational	Yes	Yes	Yes

**Table 9. Assumption Matrix
For the 1996 Operational Waste Volume Projection
(continued)**

	TPA Baseline Case	Lower Planning Case	Upper Planning Case
<u>DST Retrieval</u>			
102-SY solids retrieved to 200 East Area	12/1998	12/1998	12/1998
Consolidation of NCRW solids in 103-AW & 105-AW	No	No	No
<u>Pretreatment</u>			
Case	Privatization	Privatization	Privatization
Contract Award 1A	08/1996	08/1996	08/1996
Includes New Evaporator	Yes	Yes	No
Start Construction(mo/yr)	12/1999	12/1999	12/1999
Operations (Phase I)	06/2002-06/2011	06/2002-06/2011	06/2002-06/2011
Processing Rate	Maximum	Maximum	Maximum
Envelope A (MT Na)	4900	4900	4900
Envelope B (MT Na)	1000	1000	1000
Envelope C (MT Na)	2400	2400	2400
Staging/Characterization time per tank	100 days	100 days	100 days
Concentration limit of retrieved DSSF, CC	7 M, Na	7 M, Na	7 M, Na
Approximate Volume Pretreated, Mgal			
Yr 1 (06/2002-05/2003)	2.03	2.03	2.03
Yr 2 (05/2003-06/2004)	2.22	2.22	2.22
Vendor Feed Tank	2(full)	2(full)	2(full)
Intermediate Stage Tank	2	2	2
LAW Receipt Tank	0	0	0
Entr. Solid Receipt Tanks	1	1	1
HLW Immobilization of solids from 101-AZ, 102-AZ, 106-C, and 102-AY	2002-2008	2002-2008	2002-2008
HLW Immobilized (MT)	340	340	340
<u>Phase II Privatization Processing</u>			
Contract Award	2005	2005	2005
LAW Operations	2011-2021	2011-2021	2011-2021
HLW Operations	2013-2028	2013-2028	2013-2028
Maximum Processing Rates			
Liquid Wastes, Mgal/yr @7M Na	22.1	22.1	22.1
Solid Wastes, Mgal/yr	1.24	1.24	1.24
<u>In-Tank Washing</u>			
Case Identification	8 Modified	8 Modified	8 Modified
Consolid. of NCAW solids	No	No	No
Consolidate NCAW supernate to	101-AY + 1 DST	101-AY + 1 DST	101-AY + 1 DST
Decant 101-AZ	10/1997	10/1997	10/1997
Decant 102-AZ	10/2000	10/2000	10/2000
Decant 102-AY	10/2003	10/2003	10/2003

4.0 LOWER AND UPPER PLANNING CASE ASSUMPTIONS

The Baseline Case is meant to project DST needs based on TPA milestones, TWRS program planning, and the most realistic operational assumptions. The Baseline Case presents a basis for evaluating future DST space needs through the end of FY 2015. This report presents a projected range of tank needs which is used to generate recommendations regarding site activities, waste management activities, facility requirements, and the need to build additional double-shell tanks. This document presents the results of three projections cases--Baseline Case, Lower Planning Case, and the Upper Planning Case. Assumptions presented for the Lower and Upper Planning Case do not always reflect TPA milestones but present a range of operational assumptions meant to answer the impact of various delays or changes on DST need. The Lower and Upper Planning Cases do not present a lower or an upper limit on double-shell tank needs which could vary significantly depending on the assumption changes. Operating assumptions for the Baseline Case were established in May 1996 (Barton, 1996). The following section will describe assumptions specific to the Lower and Upper Planning Cases. These assumptions are also summarized in Table 9.

4.1 Lower Planning Case Assumptions

Assumptions for the Lower Planning Case are the same as those for the Baseline Case except for the following:

- o Saltwell Liquid Pumping. The volume of waste pumped per year was reduced during 1997-1998 and the pumping of complexed waste in 200 West Area was delayed until 1999 which allowed completion of the cross-site transfer line and removal of the solids from Tank 102-SY to be completed. The SWL assumption changes for the Lower Planning Case have been highlighted below for easier comparison to the assumptions for the Baseline Case:

Assumption	Baseline and Upper Planning Cases	Lower Planning Case
Volume Pumped in 1996 (Mgal)	0.276	0.276
Volume Pumped in 1997 (Mgal)	2.148	1.25
Volume Pumped in 1998 (Mgal)	2.323	1.20
Volume Pumped in 1999 (Mgal)	0.772	1.173
Volume Pumped in 2000 (Mgal)	0	1.05
Volume Pumped in 2001 (Mgal)	0	0.57
Start Complexed SWL Pumping in 200 West Area	1998	1999
Pumping Completion, FY	1999	2001

- o Single-Shell Tank Solids Retrieval. The volume of single-shell tank solids retrieved was reduced during the period FY 2004 to 2007 to demonstrate the impact of delaying SST solids retrieval on DST space requirements. The volume changes were assumed to be moved to FY 2017-2018. Again, the SST solids retrieval assumption changes have been highlighted below for easier comparison to the assumptions for the Baseline Case:

Assumption	Baseline and Upper Planning Cases	Lower Planning Case
Volume Retrieved in 2004 (Mgal)	0.8	0.8
Volume Retrieved in 2005 (Mgal)	2.0	2.0
Volume Retrieved in 2006 (Mgal)	2.4	0.87
Volume Retrieved in 2007 (Mgal)	1.7	0.78
Volume Retrieved in 2008 (Mgal)	1.3	1.3

4.2 Upper Planning Case Assumptions

Assumptions for the Upper Planning Case are the same as those for the Baseline Case except for the following:

- o Loss of Double-shell Tank Space. At the request of the Washington Department of Ecology, one tank was removed from service in 1998 (Hepner, 1996). For these purposes, Tank 107-AN was selected as the tank removed from service. Tank 107-AN is currently caustic deficient and could be more susceptible to corrosion.
- o Evaporation Maintenance Outage. The 242-A Evaporator was shutdown in FY 2003 for a one year period for maintenance.
- o Loss of Evaporation Capability. A loss of evaporation capability was assumed from FY 2010 to the end of the projection.

5.0 RESULTS AND CONCLUSIONS

The results of a waste volume projection can be used to forecast tank space needs versus time, forecast evaporator operation, LAW pretreatment and disposal, HLW pretreatment and disposal, analyze tank space issues for aging and non-aging waste tanks, tank usage, or to determine the need and schedule for retrievals or cross-site transfers. To predict tank space needs, a graphic is produced showing tank count versus time as compared to the available space. A short range waste volume projection predicts tank space needs over approximately a three year period in monthly intervals. A long range waste volume projection predicts tank space needs over a longer range (1994-2015) in yearly intervals.

Except for near term scheduled evaporator operations, both types of projections assume that dilute waste will be evaporated to DSSF in the year they are produced, provided an evaporator is operational and the WVR limit of the evaporator has not been exceeded. In later parts of the Baseline and Lower Planning Case projections when tank space becomes tight due to pretreatment needs and/or the amount of SST solids being retrieved, the evaporator is assumed to operate yearly even if volumes are small to minimize waste storage needs. Long range projection graphics for the Baseline, Lower Planning, and Upper Planning Case are presented in Sections 5.1, 5.2, and 5.3, respectively. Short range graphics, tank usage graphics, evaporator WVR data, and a spreadsheet showing inputs/outputs have been included for the Baseline Case only. Results of the projection cases are included in the following sections.

5.1 Baseline Case Results and Conclusions

Assumptions for the Baseline Case represent the current planning basis for TWRS programs. The one exception is the Phase II disposal plant capacity which has been increased to match retrieval rates to assure sufficient tank space was available. Projected tank space needs for the Baseline Case are shown in Figure 3. The Baseline Case manages projected tank space needs within the available tank space (28 DSTs) by incorporating several space saving assumption changes that were not included in the previous document. These space saving alternatives eliminate the need to build additional DSTs but add additional risks to the TWRS program. These actions and some of the risks are listed below:

- o Waste generation rates and TCO volumes have been reduced compared to previous projections.
- o It was assumed that agitation using a mixer pump would continue to be used for mitigation of the flammable gas buildup in Tank 101-SY. It was assumed that neither Tank 101-SY or 103-SY would require dilution until just prior to retrieval for pretreatment during Phase II processing. Since additional space in 200 West Area will be needed to handle SST solids retrieval, Tanks 101-SY and 103-SY were assumed to be the first two tanks treated in Phase II processing (an exact sequence of tanks for Phase II had not been determined before this projections was completed). This meant the 1:1 dilution for these tanks was completed in 2010-2011 to allow retrieval and mixing prior to the startup of Phase II processing in FY 2011.

If the mixer pump option was not available to meet the flammable gas buildup and a 1:1 dilution was required at a future date the increase in tank space to dilute both Tanks 101-SY and 103-SY would be approximately 1.9 million gallons.

- o In Revision 21 of this document, it was assumed that all NCAW solids and the 106-C solids would be combined into one aging waste tank (Tank 102-AZ) and that all NCAW supernates would be concentrated into one aging waste tank (Tank 101-AZ). Since that document was published, studies have been completed which looked at numerous sludge washing/combination options (Powell, 1996a). The alternatives for consolidating high heat sludges have been reviewed by a decision board comprised of WHC management, a DOE/RL representative, and a WDOE representative. It was concluded that consolidating all the sludges into a single tank would require modifications to the tank farm safety basis. The preliminary decision reached was not to consolidate all the high heat sludges into a single tank. The selected alternative (Alternative 8 Modified) would wash the sludges in the tanks they reside in without additional consolidation of solids. The NCAW supernates could not be combined into a single aging tank (Tank 101-AZ) due to the 5 M Na limit but would be concentrated and sent to Tank 101-AZ and an additional non-aging tank (Powell, 1996b). This action has increased DST needs from FY 2001 as compared to Revision 21 DST space needs.
- o In Revision 21 of this document, it was assumed that all NCRW and PFP solids could be consolidated into one DST (Awadalla, 1995). In this document (Rev. 22) it was assumed that the solids in Tanks 103-AW and 105-AW would not be combined. However, the PFP solids from Tank 102-SY and the solids from the 100 Area TCO activities were combined into Tank 105-AW. To further minimize the impact of this non consolidation of solids compared to Revision 21, this projection assumed that slurry feed (DSSF) could be stored on top of the TRU solids in Tanks 104-AW and 105-AW. The acceptability of this assumption is still being reviewed.
- o Operational space in Tanks 102-AW and 106-AW was used to provide 0.72 Mgal of the required 2.28 Mgal of spare space from 1999 on (Awadalla, 1995). This assumption change reduces operational space which may create operational/space problems during the period when SST solids are being retrieved.
- o Tank space in the Baseline Projection is tight enough that additional waste transfers and multiple uses of a tank were required to stay within the available space. For example, the excess DSSF produced in FY 1998-99 had originally caused a tank space shortage of one tank. To alleviate this problem required tank use changes:

Tank 101-AN was being used for dilute waste receipts but had to be used to store the excess DSSF. This meant that Tank 102-AZ had to be used as a dilute receiver from FY 1998-2000. Tank 102-AZ could not be used as a dilute receiver beyond FY 2003 because it was scheduled for in-tank washing beginning in FY 2003. After the DSSF was removed from Tank 101-AN in late 2000, it was again used to receive dilute wastes.

Tank space was tight enough in FY 2002-3, that the Sr/TRU and entrained solids stream being returned from Phase I treatment is temporarily sent to Tank 102-AZ. By mid 2003, the solids have been removed from Tank 101-AZ and this stream is sent to Tank 101-AZ from this time until the end of the projection.

- o Tank 102-SY was used to pump complexed SWL in West area starting in mid FY 1998 in order to meet intermediate TPA milestones for SWL pumping. Retrieval of the TRU solids in this tank is not scheduled until 12/1998. Segregation issues involving contacting complexed SWL with the TRU heel in Tank 102-SY may make this assumption impossible which could delay SWL pumping TPA milestones (see Section 3.8 for more on SWL pumping).
- o Single-shell tank solids are scheduled for retrieval starting in FY 2004. Retrieval has assumed that these wastes will have to be diluted to approximately 5 M Na or 10 wt% solids for retrieval purposes. To minimize storage space, it was assumed that the retrieved wastes could be reconcentrated to 7 M Na for storage purposes (Washenfelter, 1996b). If the retrieved single-shell tank solids cannot be reconcentrated, the pretreatment rate would need to be increased sharply to avoid a tank space shortage.
- o At the request of DOE and WHC management, revisions of this document prior to Revision 21 had included one tank of contingency space in the long range portion (FY 1999 on) to account for any inaccuracies in waste generation rates or waste volume reduction factors. This contingency space has been removed (Awadalla, 1995).
- o In the Baseline Projection it was assumed that evaporator capacity was available on an annual basis from FY 1996-2015. A reduction in evaporation capacity during years when space is tight or when waste receipts are high could result in a tank space shortage.
- o This projection assumed that dilute non-complexed waste could be evaporated to a specific gravity (SpG) of 1.41. Limiting the evaporation of waste to a SpG of 1.41 has been proposed as an acceptable threshold for preventing the accumulation of flammable gas in DSTs (Fowler, 1995b). The special projection L9503A which was completed in April 1995 (Awadalla, 1995) reduced waste to a SpG of 1.35. The higher specific gravity limit used in this projection allows waste to be evaporated further, saving approximately 2/3 of a tank by the end of the projection.
- o Some double-shell tanks are nearing their design life. The Baseline Projection does not provide for the loss of any DST space through 2015. The volume of this impact would be approximately one million gallons if one DST is lost (see the Upper Planning Case).

The space saving actions listed above eliminate the need for construction of new DST space that was recommended based on previous projection (Rev. 20) but introduce additional uncertainties and risks into the overall TWRS program. If many of these items are not possible or if waste generations exceed those used in this projection, it may be necessary to either delay site cleanup activities, delay TPA milestones (e.g., SWL pumping and/or SST solids

retrieval), increase the waste pretreatment rate, or build additional tank space in order to avoid exceeding the available DST space. Additional studies are currently in progress to address and solve the issues that have been identified.

A spreadsheet summarizing the waste generations, evaporator WVR, and pretreatment requirements has been added to this document and is included as Table 10. This spreadsheet is included to present a global view of how the various inputs and outputs affect tank space. This spreadsheet is useful to review waste inventories and waste receipts but cannot accurately predict the dynamics of tank usage or the full impact of partially filled tanks on tank space needs.

Figure 4 shows the waste additions and available space in a bar graph format to allow the user to more easily visualize the tank space usage. Numbered comments have been added to the bar graph explaining the inventory changes. These comments follow the figure.

In conclusion, the Baseline projection case extends through 2015 and does not require building new tanks based on current assumptions. Should the projection require building new tanks, approximately six to eight years lead time would be required to provide additional storage tanks. Consequently, a decision to add storage capacity can be delayed until 1998 when the tank space needs will be re-evaluated. Annual evaluation of tank space needs and the decisions on additional storage capacity are required by the M-46 series Tri-Party Agreement Milestones.

Figure 3. Double-Shell Tank Requirements for the Baseline Case

Table 10. Spreadsheet of Waste Additions and Reductions for Baseline Case

FISCAL YEAR	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015
STARTING INVENTORY	0	19420	19204	21564	22411	21645	22941	23169	22359	21524	21464	22170	21705	23018	22015	21717	21940	21240	21887	25125	26858
SPACE UTILIZATION																					
Spare Space	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280	2280
Watchlist Space	716	716	716	716	716	703	703	703	408	611	426	426	426	426	426	396	0	0	0	0	0
Contingency Space	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Segregated Space	1010	1399	2324	2391	1900	2097	2372	2435	1466	1425	619	810	956	1006	41	41	41	0	0	0	0
Priority Operational Space	2496	3410	1856	2327	2265	3165	3197	3963	4494	4721	4358	5587	3265	4269	4640	3202	4025	4177	4129	2399	1872
NEW WASTE ADDITIONS																					
B Plant/WSCF	0	108	60	60	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5
S Plant	0	96	114	114	114	114	114	114	114	114	114	114	114	114	114	114	114	114	114	114	114
T Plant	0	44	40	40	40	40	40	31	31	31	31	31	31	31	31	31	31	31	31	31	31
300/400 Areas	0	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60
TCO	0	70	151	138	88	128	0	0	200	0	0	0	0	0	0	0	0	0	0	0	0
Flushes	0	180	741	780	335	213	108	106	194	106	106	106	106	106	106	106	106	106	106	106	106
SWL Pumping	0	276	2148	2323	772	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Tank Farms	0	198	190	190	190	190	190	190	190	190	190	190	190	190	190	190	190	190	190	190	190
SST Retrieval	0	0	200	0	0	0	0	0	0	800	1969	2400	1661	1300	1400	998	0	10600	18200	24800	26100
PPF	0	2	2	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
Inventory	19421	0	66	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Retrieval Water	0	0	600	0	399	0	0	0	0	0	0	0	0	0	0	0	1110	2104	0	0	0
Everything Else	0	0	0	0	0	0	0	35	150	150	150	150	150	150	150	150	250	250	250	250	250
Pretreatment Dilution	0	0	0	0	0	1374	0	0	570	449	1040	302	1732	554	450	0	0	0	0	0	0
In-Tank Washing	0	0	0	440	0	0	520	0	0	640	0	0	0	0	0	0	0	0	0	0	0
NEW WASTE ADDITIONS TOTAL	19421	1034	4372	4148	2006	2127	1040	544	1517	2548	3668	3361	4049	2510	2506	2764	2860	11366	18956	25556	26856
TOTAL WASTE BEFORE EVAP	19421	20454	23578	25514	24218	23573	23782	23516	23877	24074	25136	25533	25756	25531	24521	24482	24801	32596	40845	50683	53716
EVAPORATOR WVR	0	-1250	-2012	-3301	-2772	-831	-812	-671	-545	-542	-1140	-1096	-896	-903	-848	-740	-586	-2943	-5158	-6627	-7426
CUM EVAPORATOR WVR	0	-1250	-3262	-6563	-9335	-10166	-10978	-11649	-12194	-12736	-13876	-14972	-15868	-16771	-17619	-18359	-18945	-21888	-27046	-33873	-41299
Outflow to Pretreatment Facility	0	0	0	0	0	0	0	-585	-1662	-1787	-1662	-2522	-1632	-2524	-1956	-1801	-2974	-7766	-10560	-16996	-18900
Outflow to the Vitrification Plant	0	0	0	0	0	0	0	-98	-145	-279	-160	-208	-208	-86	0	0	0	0	0	0	0
EVAP & OUTFLOWS TOTAL	0	-1250	-2012	-3301	-2772	-831	-812	-1354	-2352	-2608	-2962	-3826	-2736	-3513	-2804	-2541	-3560	-10709	-15718	-23823	-26326
NET INVENTORY CHANGE	19421	-216	2360	847	-766	1296	228	-810	-835	-60	706	-465	1313	-1003	-298	223	-700	647	3238	1733	530
END OF YEAR INVENTORY	19421	19204	21564	22411	21645	22941	23169	22359	21524	21464	22170	21705	23018	22015	21717	21940	21240	21887	25125	26858	27388
TOTAL CAPACITY	25923	27009	28740	30125	28806	31186	31721	31740	30172	30501	29853	30808	29945	29996	29104	27859	27586	28344	31534	31537	31540
	23	24	26	27	26	28	28	28	27	27	27	28	27	27	26	25	25	25	28	28	28

Figure 4. Double-Shell Tank Inventory and Space for the Baseline Case

Comments for Figure 4--Double-Shell Tank Inventory and Space for the Baseline Case

This bar chart graphic is meant to show the increase and decrease in the various waste categories or waste types for the Baseline Projection L96BC. Tank space needs for "in-tank washing" have been included. Spare and pretreatment receipt tanks are not shown. Beginning in 1999, a portion of the evaporator operational space maintained in Tanks 102-AW and 106-AW (abbreviated 2AW and 6AW on Figure 4) will also be considered as spare space to decrease tank space needs. Levels of Dilute Non-complexed waste (DN) in the dilute receiver and evaporator tanks will vary with time. The bar for each year depicts the tank space needs for the end of that fiscal year and may not show tank space changes occurring during the fiscal year.

Numbered Comments for "Tank Inventory and Space" Graphic

1. "Watch List" (WL) tank inventories are constant from 1995-2000. In FY 2000, the contents of Tank 105-AN are diluted and transferred to the intermediate staging tanks to supply feed for Phase I pretreatment.
2. Space above Neutralized Cladding Removal Waste (NCRW) solids is routinely used to store Dilute Non-complexed (DN) waste. For clarity, the graph shows this DN inventory in with the other DN inventory toward the top of the graph. (i.e, to ascertain "free" space, add the space shown in the NCRW group to that shown in the DN group).
3. Space above PFP Tru (PT) solids is used to store DN waste, (see note 2). It is assumed that complexed salt well liquid pumping in 200 West Area would be added to Tank 102-SY before the PT (PFP TRU) solids were retrieved (see note 9).
4. The slight decrease in the NCAW category in 1996 is caused by in-tank concentration of the NCAW supernates.
5. In 1996 there is an increase in space above the Dilute Complexed (DC) waste inventory. This results from pumping the DC waste from Tank 101-AY (980 Kgal) to Tank 108-AP (1140 Kgal tank), thus creating more net headspace. Reduction in the DC waste inventory in 1997 is caused by an evaporation. Evaporation is necessary to prevent overflow of Tank 108-AP. Projection L96BC included approximately 1.75 Mgal of additional complexed SWL as compared to the previous 2.1 Mgal projection for the 6/95 OWVP.
6. The CC (or DSSF) group shows increases in inventory over time (e.g., 1997) due to the evaporation of complexed wastes. When a CC tank becomes full, a new tank must be added, which obviously has empty space in it. This is shown graphically year-to-year with step increases in the number of CC tanks and variations in the available space shown in the group. Increase in CC volumes occur due to Salt Well Liquid (SWL) pumping.
7. The increase in NCAW tank needs in 1997 results from the retrieval of Tank 106-C solids to Tank 102-AY. Tank 106-C solids are high heat solids that have been added to the NCAW waste category (must be stored in aging waste tanks, e.g. 102-AY).

8. The increase in NCAW inventory and tank needs starting in 1997 were partially caused by in-tank washing of the NCAW solids. The final result of the operations were completed by the end of FY 2004 but the NCAW solids vitrification is not completed until FY 2008 and included (See Table 5 for additional detail):
 - No consolidation of NCAW solids.
 - NCAW supernates were evaporated and combined into Tank 101-AY.
9. The PT (PFP TRU) solids from Tank 102-SY were cross-sited to Tank 103-AW beginning 12/98. Therefore, the PT waste category and space are eliminated by the end of FY 99.
10. Retrieval of Single-Shell Tank Solids (SSTS) was started in FY 2004. Initial SST solids were stored in Tanks 104-AN and 102-SY.
11. Decrease in DSSF inventory in FY 2003 results from Phase I pretreatment.
12. Increase in CC inventory in 2010 is caused by dilution and staging of watch list waste from Tank 101-SY for pretreatment in Phase II. The watch list tank count has decreased by one and the CC inventory has increased due to dilution and staging. In 2011 the watch list category has been eliminated when Tank 103-SY has been diluted and staged for pretreatment.
13. CP waste is pretreated in FY 2012 and this category is eliminated.

Interpretation of Short Range Projection Results

This section provides an interpretation of detailed short range projection results. The OWVP presents certain information in the form of graphics. A number of these graphics show 12 months of historical operations and 24-36 months of projected operations. Most of the vertical axis represents thousands of gallons of waste generated. An example of this type of graphic is the facility waste generation graphic. The volume generated per month for each facility is depicted on a facility waste generation graph. An example of the facility waste generation graph for PUREX waste is shown below (Figure 5).

Figure 5. Facility Waste Generation Graphic

In the computer simulation, facility waste streams are routed to a receiver tank. A tank fill graphic shows the filling of the receiver tank and is on the same page as the facility waste generation graph of the waste stream it receives. The tank fill graphic shows the rate a specific tank is filled with waste. Usually when a receiver tank is full, waste is transferred to a holding tank. This waste is either evaporated or stored for future disposal. For every transfer out of a tank, there is a corresponding receipt of the same volume into another tank or facility. For every evaporation out of a tank there is a corresponding receipt of the more concentrated waste in the receiving tank and an increase in the condensate from the 242-A Evaporator being sent to the LERF.

An example of this type of graph (a tank fill graphic) for Tank 105-AW is shown below (Figure 6).

Figure 6. Tank Fill Graphic

The accuracy of this projection is directly related to the facility supplied assumptions. Some of the major assumptions are listed below:

- o Process operating schedules define the planned dates of plant operations or deactivation activities. These assumptions are consistent with the TWRS program planning. Volumes and schedules for the various Hanford facilities for the three projection cases are presented in Sections 3 and 4.
- o Plant waste generation assumptions define the volume and type of waste that will be generated by the plants. These assumptions result from an analysis of recent waste generation history and future plans specified by the plants. Most waste streams volumes are projected based on historical data and/or facility supplied operating schedules. Section 5.4 includes a comparison of actual waste receipts to the new facility waste generation targets for the period October 1995 to June 30, 1996.

Tank roles and waste routings define the use of tanks in the system. For example, a tank will be designated to act as receiver of the PUREX facility miscellaneous waste (Tank 105-AW), while other tanks will store concentrated waste.

The graphics depicted on the next few pages summarize the short range projection results of the Baseline Case. Figure 7 shows the role of each tank for a period of four years. It should be noted that if a tank has several transfers in or out of the tank in one month, no fluctuation in the tank level may appear. This is because the graphic program plots tank levels as of the last day of the month and any changes that occur during the month are not shown. The simplified routing schematic shown in Figure 8 depicts the assumptions that are made about the routing of waste from the plants to the tanks and from tanks to the facilities.

Figure 7. Tank Levels During the Short Range Projection

Figure 8. Simplified Schematic of Current and Planned Routings

The results of this projection are forecasts of evaporator operations, LAW pretreatment and disposal, HLW pretreatment and disposal, and an analysis of tank space issues for aging and non-aging waste tanks.

Evaporator WVR and LERF Condensate

Schedule and operational considerations presented in Section 3 result in the following Evaporator Waste Volume Reduction (WVR) and LERF Condensate production volumes for the Baseline Case. The ratio of process condensate sent to LERF for every gallon of Waste Volume Reduction (WVR) for Evaporator Campaigns 94-1, 94-2, and 95-1 was 1.29, 1.24, and 1.26, respectively (Guthrie, 1996). The average for the first three campaigns was 1.26 gallon of condensate/gallon of WVR which was the value used in this document to project future condensate production recorded in Table 11. These volumes also assume that there will be no evaporator outages before 2015. The waste sources, campaign schedule, and concentrated waste receiver tanks used in this projection are summarized Table 12.

Table 11. Evaporator WVR and LERF Additions for the Baseline Case

FISCAL YEAR	EVAPORATOR WVR (KGAL)	CONDENSATE TO LERF (KGAL)
1996	1250	1580
1997	2000	2500
1998	3300	4160
1999	2770	3490
2000	830	1050
2001	810	1020
2002	480	600
2003	550	690
2004	540	680
2005	1140	1440
2006	1100	1390
2007	900	1130
2008	900	1130
2009	850	1070
2010	740	930
2011	590	740
2012	2940	3700
2013	5160	6500
2014	6930	8730
2015	7430	9360

Table 12. Evaporator Campaign Schedule for the Baseline Case

Campaign	Start Date	Staging Tank(s)	Source	Waste Feed Type	Feed Volume (Kgal)	Receiver Tank
97-1	2/97	105-AP	102-AW(102-AY) 101-AN	DN DN-SWL	400 970	101-AP 105-AP
97-2	5/97	108-AP	101-AY & 106-AN	DC	900	106-AN
98-1	10/97	107-AP 104-AW 104-AP	106-AP & 102-AY 104-AW 102-SY	DN DN DN-SWL	1100 + 740+ 1000	105-AP 101-AP
98-2	4/98	107-AP 103-AP	102-SY 102-SY	DN-SWL DN-SWL	1000 1000	101-AP 104-AW 101-AN
99-1	10/98	108-AP	E.Saltwells/Gen	DC-SWL	850	106-AN 107-AP
99-2	4/99	101-AN 104-AP 106-AP	101-AN 102-SY 106-AP	DN-SWL DN-SWL DN	1000 + 1000 + 1000	101-AN
99-3	8/99	108-AP	E.Gen,102-SY	DC-SWL	1000	107-AP

Note: Tank 101-AP is characterized and once the contents are found to be suitable, the DSSF contents are stored on top of the solids in Tanks 103-AW and 104-AW in early 1998. This allows Tank 101-AP to be refilled later in 1998. This method should allow topping off Tanks 103-AW and 104-AW with DSSF with less likelihood of producing another watch list tank than direct transfers from Tank 106-AW.

See Figure 9 for dilute receiver tanks, evaporator WVR, and the 242-A Evaporator operating schedules for the Baseline Case.

Based on the 50 Mgal/year treatment capacity for the ETF, the ETF should have no problem processing the projected evaporator condensates thru 2015. There should be sufficient LERF and DST space for storage of Hanford facilities generated waste and condensates between FY 1996 and the end of 2015, provided:

- the 242-A Evaporator schedule is achieved
- the amount of condensate sent to LERF does not grossly exceed the 1.3 gallon condensate/gallon WVR factor
- facilities stay within their respective generation limits
- no unexpected waste receipts are received in the DSTs

Figure 9. Dilute Receiver Tanks and 242-A Evaporator Operations

NON-AGING TANK SPACE

In later parts of the projections when tank space becomes tight due to pretreatment needs and/or the amount of SST solids being retrieved, the evaporator is assumed to operate yearly to minimize waste storage needs and to decrease the volume of retrieved SST solids waste. Tank space pinches occurring between FY 2000 and FY 2015 (Figure 3) are caused by a combination of factors, including:

- o SWL pumping (SST stabilization) volumes pumped by the end of FY 1999
- o Four tanks are designated for staging wastes for Phase I pretreatment--two vendor tanks (Tanks 106-AP and 108-AP) and two intermediate staging tanks (Tanks 102-AP and 104-AP)
- o The large volume of SST solids retrieved beginning in FY 2004
- o The decision not to operate the Grout Facility has eliminated an early means of freeing up DST space
- o The decision not to consolidate NCAW solids has increased the DST space needs from 2001 on

Figures 10 through 14 show the operation of most of the DST waste tanks for the Baseline Case projection.

Figure 10. PUREX Facility Waste Generations and Tank Levels

Figure 11. West Area Waste Generations and Tank Levels

Figure 12. B Plant and Hanford Facility Waste

Figure 13. AP Tank Farm Levels

Figure 14. AN Tank Farm Levels

AGING WASTE TANK SPACE

It is assumed that the PUREX facility will not restart. With PUREX not restarting only two aging waste tanks (Tanks 101-AZ and 102-AZ) are required to store existing aging waste.

One additional aging waste tank will be required to retrieve and store the contents of Tank 106-C (a SST containing high heat waste). Waste from Tank 106-C is assumed to go to Tank 102-AY in FY 1997. This may cause a problem for final disposal of the contents of Tank 102-AY if the heel in Tank 102-AY is high in chlorides as indicated by initial characterization studies.

In Revision 21 of this document, it was assumed that all NCAW solids and the 106-C solids would be combined into one aging waste tank (Tank 102-AZ) and that all NCAW supernates would be concentrated into one aging waste tank (Tank 101-AZ). Since that document was published, studies have been completed which looked at numerous sludge washing/combination options (Powell, 1996a). The alternatives for consolidating high heat sludges have been reviewed by a decision board comprised of WHC management, a DOE/RL representative, and a WDOE representative. It was concluded that consolidating all the sludges into a single tank would require modifications to the tank farm safety basis. The preliminary decision reached was not to consolidate all the high heat sludges into a single tank. The selected alternative (Alternative 8 Modified) would wash the sludges in the tanks they reside in without additional consolidation of solids. The NCAW supernates could not be combined into a single aging tank (Tank 101-AY) due to the 5 M Na limit but would be concentrated and sent to Tank 101-AY and an additional non-aging tank (Powell, 1996b). This action has increased DST needs from FY 2001 as compared to Revision 21 DST space needs.

A graph of aging waste tank space requirements as a function of time is presented in Figure 15. The uses of each individual aging waste tank for the Baseline Case are shown in Figure 16.

Figure 15. Aging Tank Requirements

Figure 16. Aging Waste Tank Usage

5.2 Lower Planning Case Results and Conclusions

Tank space needs for the Lower Planning Case are shown in Figure 17. Results from this projection indicate that decreasing the rate of SWL pumping during the period FY 1997-1998 would lower the DST space needs making reserve space available for other purposes. The SWL pumping volume for the Lower Planning Case was decreased by 2 million gallons during the period FY 1997-1998 but the reduction in tank count is only one tank. This anomaly is explained by the difference in actual stored volume for SWL. The waste volume reduction factor for non-complexed SWL is approximately 47 percent meaning that approximately 53 percent of the pumped volume difference would be translated into saved space or 1.06 Mgal (one non-aging DST holds 1.14 Mgal).

The 2.4 Mgal reduction in the SST solids retrieval volumes during the period FY 2006-2007 resulted in a two tank decrease in DST space needs until 2012. Reconcentration of the retrieved SST wastes was assumed to save approximately 25-30 percent of the retrieved volume resulting in approximately a two tank differential. Note that the magnitude of the volume saved by reconcentration of the retrieved SST solids waste will vary depending on what percent of the waste is dissolved saltcake and what portion is retrieval water added to retrieve SST solids.

Figure 17. Double-Shell Tank Requirements for the Lower Planning Case

5.3 Upper Planning Case Results and Conclusions

Tank space needs for the Upper Planning Case are shown in Figure 18. The assumption changes and their impact are summarized below:

Loss of One Tank. The projected loss of tank space (tank 107-AN was taken out of service) in 1998 has increased tank space requirements by one tank and this in turn causes the projected tank space needs to exceed available space by the end of FY 2000.

Evaporator Maintenance Outage. The evaporator maintenance outage in 2003 does not result in an increase in tank count because there is space available in Tank 102-AW and in the dilute receiver tanks to store the estimated 550 Kgal of wastes to be evaporated in 2003. This result indicates that the evaporator maintenance outage could also be scheduled in other years when the projected WVR is low without impacting tank count.

Evaporator Shutdown. Knowing that the evaporator shutdown was going to occur in 2011, all dilute in the evaporator feed tank and dilute receiver tanks was evaporated off in 2010 to minimize impact of the shutdown. This resulted in some additional space to handle waste receipts in 2011-12 without impacting tank count. Note also that there were no SST solids retrieval volumes scheduled for 2011. By 2013 the available tank space has been grossly exceeded due to the large volume of SST solids waste retrieved in that year.

Assuming the evaporator shutdown was scheduled to occur, the only way to avoid exceeding the available space in 2013 is to decrease SST solids retrieval (TPA milestone), increase the pretreatment rate, or build additional tanks. By 2015, some of the SST retrieval cases (Washenfelter, 1996b) could result in retrieval of up to 34 Mgal of waste per year. The maximum treatment rate of 22.1 Mgal/year (Washenfelter, 1996b) would not be able to handle the scheduled SST solid retrieval volumes. The results of the Upper Planning Case indicate that the evaporator capability needs to be maintained to avoid exceeding available tank space during SST solids retrieval.

Figure 18. Double-Shell Tank Requirements For The Upper Planning Case

5.4 Actual Waste Generation Compared to Management Limits

During the Tank Space Management Board (TSMB) meeting on August 7, 1991, the need to establish new facility waste generation limits was discussed with the Hanford facility representatives based on additional delays in the 242-A Evaporator restart. A new total monthly waste generation rate of 64 Kgal/month was adopted based on: discussions with facility representatives, the average monthly waste generation rate for each facility during FY 1991, and the need to provide contingency space for potential delays in the 242-A Evaporator restart.

Facility generation limits were not established for high priority waste generations, which were assigned to "Priority Space". These generations included the PFP stabilization campaign (safety), SWL pumping (TPA milestone), and the 242-A Evaporator (space necessary for the mini-run and restart).

New average monthly waste generation targets have been established for this projection with waste generations being reduced by the facilities (references and discussion in Section 3). Table 13 presents a comparison of the previous limits established for each facility, the newly established target rates for this projection, and the actual average monthly waste generation rate (Kgal/month) for the period October 1995 through June 30, 1996.

Table 13. Comparison of Average Monthly Waste Generation Rates (Kgal/month)

FACILITY	64 KGAL/MONTH MANAGEMENT LIMIT FROM OWVP REV. 20	FACILITY TARGET FOR REV. 22	AVERAGE MONTHLY FACILITY GENERATIONS (10/95 - 6/96)
TANK FARMS	10.0	10.0	7.3
B PLANT	23.0	9.0	8.8
T PLANT	6.0	3.6	2.7
S PLANT	5.0	8.0	2.7
300 AREA	5.0	4.5	4.7
400 AREA	0.0	0.5	0.0
TOTAL	64.0	35.6	26.2

Monthly Totals do not Include Terminal Clean-out Volumes or SWL Pumping

Due to the commendable efforts by the Hanford facilities, all waste generators are at or below their new waste generation target for the period October 1995 through June 30, 1996. A comparison of the volumes of waste entering the DST tank space for that time period is compared graphically to the various targets or projected generations in Figures 19-22. Estimated facility holdups or stored waste as of June 30, 1996 are presented in Table 14.

NOTE: THIS GRAPHIC DEPICTS CONTRIBUTIONS FROM FACILITY GENERATIONS; TERMINAL CLEAN-OUT AND SWL PUMPING IS NOT SHOWN

Figure 19. Comparison of Facility Generations to "TARGET"

Comparison of the Average Monthly Waste Generation Rate (Kgal/month)
To their Respective Target Rate for the
Period October 1, 1995 through June 30, 1996

Figure 20. Comparison of Monthly Average Waste Generation To Target Rate

Figure 21. Contributions From Salt Well Liquid Pumping

Figure 22. Contributions From TCO (June 30, 1996)

Table 14. Facility Waste Storage and Capacity in Kgal as of June 1996

FACILITY	ACTUAL HOLD-UP	WASTE STORAGE CAPACITY	PROCESS VESSELS CAPACITY
PUREX		100	215
B Plant	10	0	#225
S Plant	2	9	0
T Plant	17	50	0
100 Area	0	50	0
300 Area	7	60	0
400 Area	10	23	0
PFP	2	16	0
TOTAL=	48	308	440

25 Kgal capacity for storage of waste, the remaining space is not routed for storage (Killoy, 1992).

6.0 SPACE SAVING ALTERNATIVES

In the near term, space saving alternatives include waste minimization, continued availability of the 242-A Evaporator, LERF availability, and the operation of the ETF. These alternatives must be considered because new inputs to the system may develop (e.g., unexpected new waste streams or a leaking SST or DST).

Should a tank space shortage develop in the period 1998 through 2015, response to the shortage for the Baseline Case must be in one of three areas. The inflows to the system must be reduced, the outflows to the system must be increased (or started earlier), or the available tank space increased. Inflows to the system include miscellaneous facility waste generations, TCO wastes, in-tank washing, dilution of Tanks 101 and 103-SY (for pretreatment), pretreatment, SWL pumping, and SST solids retrieval. Outflows include the 242-A Evaporator and waste disposal (pretreatment and vitrification). Increasing the tank space available could be done by building more tanks (a six to eight year task), mixing segregated waste types (which would gain about half a million gallons of space but increase interim storage and final disposal costs), or operating without reserved spare tank space. A cost/benefit analysis needs to be completed to determine the best alternative.

In addition to minimizing waste generations, other actions could be pursued. The list below includes many actions which can result in tank space savings or economization, and can serve as a starting point in a tank space optimization program.

PUREX Facility

- TCO of PUREX will be completed by FY 1997. Most of the volume to be transferred from the PUREX facility to DSTs has already been received. Therefore, waste reductions for PUREX will not be a viable option.

B Plant

- Continue to reduce waste being generated at B Plant
- Route BCP waste to cribs
- Evaporate dilute waste, from B Plant and other facilities, in B Plant concentrators
- Replace steam heaters with electric heaters
- Make TCO at B Plant dependent on tank space availability

Plutonium Finishing Plant

- Continue to reduce waste being generated at PFP (only 30 Kgal of total waste are scheduled to be generated from FY 1996-2006)

6.0 SPACE SAVING ALTERNATIVES (CONTINUED)

Tank Farms

- Continue to reduce waste being added to DSTs
- Continue waste accountability and minimization controls
- Develop a total waste cutoff plan
- Increase the 5 M Na limitation on aging waste tanks
- Use dilute waste for retrieval, air lift circulator flushes, line flushes, etc.
- Increase the WVR of the 242-A Evaporator
- Accelerate plans to consolidate solids from Tanks 102-SY into Tank 105-AW
- Delay SWL pumping
- Build new tanks
- Accept loss of waste segregation (used in an extreme emergency)
- Store facility generated waste in designated "spare tank space" (used in an extreme emergency)
- Improve efficiency of the 242-A Evaporator
- Solidify treated waste and dispose of as low level waste in burial grounds
- Consolidate NCAW and Tank 106-C solids in one aging tank with one additional aging tank being used to combine NCAW supernates (requires modification of safety basis).
- Increase the heat limit on non-aging DSTs to allow either the Tank 106-C wastes or the supernate from Tank 101-AZ to be stored in a non-aging DSTs if the in-tank washing consolidations are not allowed
- Concentrate DSSF to Double-Shell Slurry (DSS). Experience with Tank 101-SY makes this alternative highly unlikely.
- Store waste in single-shell tanks (used in an extreme emergency; would require approval by DOE, EPA, and Ecology)
- Store waste in facility storage tanks or portable tanks such as railcars (used in an extreme emergency; total space available is small compared to the contents of a DST)

Grout

- Reinstate the Grout Disposal Program
- Grout the existing waste in Tanks 102-AP and 101-AW

7.0 BIBLIOGRAPHY

- Alderman, C. J., January 29, 1996, Internal Memo (CJA-96-002) to J. N. Strode, "Waste Volume Projection Assumptions for K Basins Sludge."
- Anantatmula, R. P. and Ohl, P. C., June 28, 1996, WHC-SD-WM-ER-0585, Rev. 0, "DST Remaining Useful Life Estimates."
- Awadalla, N. G., April 19, 1995, WHC-SD-W236A-ER-021, Rev. 1, "Multi-Function Waste Tank Facility, Phase Out Basis."
- Barrington, C. A., May 7, 1991, Letter to J. G. Propson, "Plutonium Finishing Plant Waste Volume Projection for Fiscal Years 1991 - 2015."
- Barton, W. B., May 16, 1996, Internal Memo (74A10-96-066) to Distribution, "Operational Waste Volume Projection Assumptions for 1996."
- Bergquist, G. G., January 1, 1996, Internal Memo (15530-96-GGB-010) to J. N. Strode, "Plutonium Finishing Plant Waste Volume Projection for the Period Fiscal Year 1996-2028."
- Brown, R. G., May 1996, WHC-SD-W236A-ES-012, Rev. 1, "Multi-Function Waste Tank Facility Path Forward Engineering Analysis Technical Task 3.3, Single-Shell Tank Contents."
- Carothers, K. G., January 30, 1996a, Personal Communication with J. N. Strode, Caustic Addition to Tank 107-AN--Revised Schedule.
- Carothers, K. G., March 19, 1996b, Personal Communication with J. N. Strode, Caustic Addition to Tank 107-AN--Revised Schedule.
- Certa, P. J. and D. L. Penwell, Received July 13, 1995, Personal Communication--Hardcopy of Retrieval Sequence RE087SST.TXT for "2C3-087"--Ramped Pretreatment.
- Certa, P. J., et. al., August 1996, WHC-SD-WM-RPT-224, Rev. 0, "Low-Level Waste Feed Staging Plan."
- Collins, G. T., January 31, 1996, Internal Memo (75755-96-006) to J. N. Strode, "Waste Volume Projection Assumptions for 222-S Laboratory and the Waste Sampling and Characterization Facility (WSCF) for the Period FY 1996-2028."
- DOE Order RL 5820.2A, August 1990, Radioactive Waste Management, Waste Management Div., U.S. Department of Energy, Richland, Washington.
- DOE 1995, January 24, 1995, memorandum from T. P. Grumbly, Assistant Secretary for Environmental Management to the Department of Energy Secretary, U. S. Department of Energy, Washington, D. C., "Proceed with privatization of Hanford tank waste treatment by consulting with regulators, the Hanford Advisory Board, and other stakeholders, and to establish a full-time DOE task force to carry out the necessary procurement steps to implement privatization."

7.0 BIBLIOGRAPHY (CONTINUED)

Estey, S. D., May 31, 1994, WHC-SD-W320-TI-002, Rev. 0A, "Project W-320 Tank 241-C-106 Sluicing Process Flowsheet."

Estey, S. D. and Guthrie, M. D., March 29, 1996, Internal Memo (74A10-96-029) to N. G. Awadalla, "Data Analysis and Criteria Development to Prevent Accumulation of DST Waste With Unacceptable Gas Retention Behavior."

Estey, S. D., April 1996, WHC-SD-WM-TI-747, Rev. 0, "TRU Activity and Complexed Waste Considerations for 200 West Area SST Interim Stabilization Planning."

Ethington, P. R., February 5, 1996, Internal Memo (17330-96-009) to N. W. Kirch, "Forecasted PUREX Plant Liquid Waste."

Fowler, K. D., April 1995a, WHC-SD-WM-OCD-015, Rev. 1, "Data Quality Objectives for Tank Farms Waste Compatibility."

Fowler, K. D., April 1995b, WHC-SD-WM-DQO-001, Rev. 1, "Data Quality Objectives for Tank Farms Waste Compatibility Program."

Greenidge, M. E., February 29, 1996, Letter (027213) to W. B. Barton, "Waste Volume Projection Assumptions for 100-N Area Facilities for the Period FY 1996-2028."

Griffin, P. W., February 14, 1996, cc: Mail Message to J. N. Strode, "Waste Volume Projection Assumption for 105-F and 105-H Basins."

Grumbly, T. P., August 1993, "Safety Initiatives."

Guthrie, M. D., August 18, 1993, Letter to G. M. Koreski and J. N. Strode, "Assumptions for the Operational Waste Volume Projection (for the 242-A Evaporator)."

Guthrie, M. D., January 26, 1996, Internal Memo (77310-96-005) to J. N. Strode, "1996 242-A Evaporator Waste Projection Assumptions."

Guthrie, M. D., August 1996b, WHC-SD-WM-PE-056 Rev. 0 Draft, "Campaign 96-1 Post Run Document."

Haigh, P. G., January 21, 1992, Personal Communication.

Halgren, D. L., February 3, 1995, Internal Memo (86730-95-005) to J. N. Strode, "Waste Volume Projection Assumptions for the 300 Area for the Period of Fiscal years 1995-2028."

Halgren, D. L., June 21, 1995, cc: Mail Message to J. N. Strode, "340 Waste Volume."

Hanlon, B. M., March 1996, WHC-EP-0182-96, "Waste Tank Summary Report for Month Ending March 31, 1995."

7.0 BIBLIOGRAPHY (CONTINUED)

Hanson, G. N., September 9, 1996, cc: Mail Message to W. B. Barton, "Comments WHC-SD-WM-ER-029 Rev 22."

Hepner, N. T., cc: Mail Message to consider one tank loss.

Koreski, G. M., August 30, 1995, DSI to Jim Strode, "Comments on Solids Levels in Table 7 (6/95 OWVP)."

Kutsch, D. B., January 10, 1996a, Internal Memo (16D20-96-DBK-011) to J. N. Strode, "B Plant Assumption for Waste Volume Projections for 1996 Through 2028."

Kutsch, D. B., March 26, 1995b, cc: Mail Message to J. N. Strode, "B Plant Waste Volume Projection (corrected)."

McKenney, D. E., May 13, 1994, DSI to Nick Kirch, "Leachate Composition from Mixed Waste Landfill."

Miller, P. C., January 16, 1996, Internal Memo (RC-96-001) to J. N. Strode, "Waste Volume Projection Assumptions for 400 Area for the Period FY 1996-2028."

Orme, R. M., March 1995a, WHC-SD-WM-TI-693 Rev. 0, "Preliminary Time-Phased TWRS Process Model Results."

Orme, R. M., August 1995b, WHC-SD-WM-TI-613 Rev. 1, "TWRS Process Flowsheet."

Powell, W. J., January 22, 1996, WHC-SD-WM-ER-532, Rev.0, "Neutralized Current Acid Waste Consolidation Management Plan."

Powell, W. J., February 23, 1996, cc: Mail Message to W. B. Barton, "Modified NCAW Alternative 8."

Reynolds, D. A., March 8, 1994, Presentation at the Meeting- Assumption Changes for the Operational Waste Volume Projection.

Reynolds, D. A., May 3, 1995, WHC-SD-W236A-ES-015, Rev. 0, "Waste Segregation Analysis for Salt Well Pumping the the 200 West Area - Task 3.4."

Riley, D. C. et al, March 1988, SD-WM-TI-309, Rev. 1, "Waste Generation and Processing Rates with Volume Reduction Factors - 1988."

Saueressig, D. L., Information Received at a Meeting held March 13, 1996, March 5, 1996 Draft of Interim Stabilization Tri-Party Agreement M-41-00 Recovery Plan."

Sederburg, J. P., April 1995, WHC-SD-WM-TI-690, Rev. 0, "Waste Volume Reduction Factors for Potential 242-A Evaporator Feed."

7.0 BIBLIOGRAPHY (CONTINUED)

- Shelton, L. W. Jr., July 28, 1995, cc: Mail Message to J. N. Strode, "Tank Inventories."
- Smith, D. K., February 25, 1994, Internal Memo (16500-94-DKS-023) to G. M. Koreski/J. N. Strode, "B Plant Comments on the Assumptions for the Operational Waste Volume Projection."
- Triner, G. C., January 10, 1996, Internal Memo (87470-96-GCT-002) to J. N. Strode, "Waste Volume Projection Assumptions for T Plant for the Period FY 1996-2028."
- Von Barga, B. H., April 25, 1995, WHC-SD-WM-DQO-014, Rev. 1, "242A Evaporator/Lerf Data Quality Objective."
- Wacek, H. J., June 28, 1996, cc: Mail Message, "Operational Waste Volume Projection Assumptions for 1996."
- Wagner, R. N., January 29, 1996, cc: Mail Message to J. N. Strode, "(ETF) WVP Assumptions."
- Wang, O. S., March 1, 1994, cc: Mail Message to G. M. Koreski and J. N. Strode, "Assumptions for the Operational Waste Volume Projection."
- Washenfelder, D. J., June 26, 1996a, DSI to W. B. Barton, "Revised Attachment 1 to Internal Memo Titled 'Revised TWRS Disposal Program Assumptions for Operational Waste Volume Projection-73410-96-013'."
- Washenfelder, D. J., July 29, 1996b, DSI to W. B. Barton, "Revised Attachment 1 and 2 to Internal Memo Titled 'Revised TWRS Disposal Program Assumptions for Operational Waste Volume Projection-73410-96-013'."
- Washington State Department of Ecology (WDOE), U.S. Environmental Protection Agency, and U. S. Department of Energy, Fourth Amendment, January 1994, "Hanford Federal Facility Agreement and Consent Order" (Tri-Party Agreement).
- WHC 1996a, July 3, 1996, "Federal Facility Agreement and Consent Order Change Control Form," Change Number M-60-95-03.
- WHC 1996b, July 3, 1996, "Federal Facility Agreement and Consent Order Change Control Form," Change Number M-50-95-01.

APPENDIX

APPENDIX. Acronyms

ASD	- ammonia scrubber distillate from
ASF	- ammonia scrubber feed from
AW	- aging waste, also called NCAW
BCP	- B Plant process condensate
CC	- complexant concentrate waste
CP	- concentrated phosphate waste
DC	- dilute complexed waste
DCRT	- doubly contained receiver tank
DN	- dilute non-complexed waste
DOE	- U.S. Department of Energy
DP	- dilute phosphate waste
DSS	- double-shell slurry (most concentrated double-shell tank waste)
DSSF	- double-shell slurry feed
DST	- double-shell tank
EIS	- Environmental Impact Study
FFTF	- Fast Flux Test Facility
FSAR	- Facility Safety Analysis Report
FY	- fiscal year
GTF	- Grout Treatment Facility
HFW	- Hanford facility waste (waste produced at 100, 300, 400 areas)
HLW	- High Level Waste
IPM	- Initial Pretreatment Module
IX	- ion-exchange
KGAL	- kilogallon (1000 gallons)
LERF	- Liquid Effluent Retention Facility
LETF	- Liquid Effluent Treatment Facility
LAW	- Low Activity Waste
MOTU	- metric tons of uranium
NCAW	- neutralized current acid waste
NCRW	- neutralized coating (cladding) removal waste (synonym: cladding removal waste)
OWVP	- Operational Waste Volume Projection
NEA	- National Environmental Policy Act
NSF	- New Pretreatment Facility
NEV	- New Pretreatment Vault
PAD	- process distillate discharge from PUREX
PFP	- Plutonium Finishing Plant
PRF	- Plutonium Reclamation Facility
PAW	- phosphate/sulfate waste
PHMC	- Project Hanford Management Contractor
PUREX	- Plutonium-Uranium Extraction
RMC	- Remote Mechanical C Line
SpG	- Specific Gravity
SST	- single-shell tank
SWL	- salt well liquid
TCO	- terminal clean-out
TOE	- total operating efficiency
TPA	- Tri-Party Agreement
TRU	- transuranic
TRUEX	- Transuranic Extraction Process
TSMB	- Tank Space Management Board
UO ₂	- Uranium Oxide Facility
WSCF	- Waste Sampling and Characterization Facility
WVR	- waste volume reduction

INTERNAL DISTRIBUTION

C. J. Alderman	R3-48
J. N. Appel	G3-21
E. G. Backlund	T5-54
R. F. Bacon	S7-85
J. J. Badden	T4-07
D. G. Baide	S2-48
W. B. Barton <u>283</u>	R2-11
P. A. Baynes	H6-33
G. G. Bergquist	T5-55
P. K. Bhatia	R2-54
J. W. Bloom	A2-34
D. M. Bogen	T5-50
L. E. Borneman	R1-90
R. J. Bottenus	T4-52
W. W. Bowen	S4-66
V. C. Boyles	R1-43
S. L. Brey	T6-12
D. L. Burt	R2-54
K. G. Carothers	R1-56
Central Files	A3-88
P. J. Certa	H5-61
R. A. Dodd	S5-07
S. M. Eiholzer	S5-85
L. F. Ermold	S7-84
P. R. Ethington	S5-85
P. Felise	B4-55
D. L. Flyckt	S6-71
G. D. Forehand	R3-86
G. T. Frater	S7-16
J. C. Fulton	R3-11
J. S. Garfield	H5-49
K. A. Gasper	G3-21
G. J. Gauck	T4-07
J. E. Geary	S5-07
S. O. Godfrey	S6-81
L. D. Goodwin	T6-12
M. E. Greenidge	X5-54
P. W. Griffin	X5-53
M. L. Grygiel	H6-33
M. D. Guthrie	R1-43
M. J. Hall	T6-12
D. G. Hamrick	S6-15
G. N. Hanson	S5-05
D. G. Harlow	S6-19
J. P. Harris III	S2-48
J. P. Hayfield	S6-18
J. O. Honeyman	G3-21

INTERNAL DISTRIBUTION (CONTINUED)

R. D. Jensen	G3-21	
J. Jo	R2-12	
N. W. Kirch	R2-11	
G. M. Koreski <i>JK</i>	R2-11	(10 copies)
E. J. Kosiancic	H5-61	
M. J. Kupfer	H5-27	
J. M. Light	R3-25	
S. S. Lowe	H6-29	
J. P. Marshall, Jr	H5-61	
M. A. McLaughlin	B2-35	
W. E. Meeuwse	S5-05	
D. P. Mendoza	H5-68	
L. C. Mercado	T4-08	
G. A. Meyer	S2-48	
J. C. Midgett	S6-65	
P. C. Miller	R1-51	
W. C. Miller	R1-56	
R. J. Murkowski	H5-03	
D. J. Newland	B3-51	
R. J. Nicklas	R1-43	
P. C. Ohl	R1-30	
R. M. Orme	H5-27	
M. A. Payne	S7-84	
G. L. Parsons	R3-47	
W. A. Peiffer	S6-19	
R. S. Popielarczyk	A2-34	
R. W. Powell	G3-21	
R. E. Raymond	S7-12	
D. P. Reber	T4-07	
D. W. Reberger	S5-13	
C. A. Rieck	S2-48	
S. H. Riffaey	R1-56	
L. H. Rodgers	T5-54	
W. W. Rutherford	R3-25	
D. J. Saueressig	S8-05	
D. L. Schilperoort	X8-29	
J. S. Schofield	S7-12	
L. W. Shelton	H5-49	
J. P. Sloughter	R2-54	
D. K. Smith	S6-60	
J. N. Strode <i>JS</i>	R2-11	(10 copies)
G. R. Tardiff	S5-05	
J. D. Thomson	H6-35	
J. E. Truax	R2-50	

INTERNAL DISTRIBUTION (CONTINUED)

A. M. Umek	S7-81
J. E. Van Beek	S2-48
E. C. Vogt	T5-50
B. H. Von Bargaen	R1-43
J. A. Voogd	H5-03
B. L. Wallace	S6-60
G. L. Walley	T6-20
D. J. Washenfelder	H5-27
R. A. Watrous	H5-27
D. J. Watson	X3-79
J. H. Wicks, Jr.	R2-50
K. D. Wiemers	K6-51
J. D. Williams	H6-30
G. F. Williamson	H5-03
C. M. Winkler	S5-14
R. D. Wojtasek	S7-84
C. D. Wollam	S6-22
R. B. Wurz	S6-71

DEPARTMENT OF ENERGY (DOE RL)

M. L. Ramsay	S7-54
A. B. Sidpara	S7-54
H. J. Wacek	S7-54
D. D. Wodrich	S7-50

WASHINGTON STATE DEPARTMENT OF ECOLOGY

Nuclear & Mixed Waste Management Program

P.O. Box 47600

Olympia, WA 98504-7600

N. T. Hepner